CRC Handbook of Chemistry and Physics

Editor-in-Chief

David R. Lide
Former Director, Standard Reference Data
National Institute of Standards and Technology

Editorial Advisory Board

Grace Baysinger
Swain Chemistry and Chemical Engineering Library
Stanford University
Stanford, CA 94305-5080

Lev I. Berger
California Institute of Electronics and Materials Science
2115 Flame Tree Way
Hemet, CA 92545

Robert N. Goldberg
Biotechnology Division
National Institute of Standards and Technology
Gaithersburg, MD 20899

Henry V. Kehiaian
ITODYS
University of Paris VII
1, rue Guy de la Brosse
75005 Paris, France

Kozo Kuchitsu
Department of Chemistry
Josai University,
Sakado 350-0295, Japan

Gerd Rosenblatt
1177 Miller Avenue
Berkeley, CA 94708

Dana L. Roth
Millikan Library / Caltech 1-32
1200 E. California Blvd.
Pasadena, CA 91125

Daniel Zwillinger
Mathematics Department
Rensselaer Polytechnic Institute
Troy, NY 12180

PREFACE

The 86th Edition of the print *CRC Handbook of Physics and Chemistry* has undergone a face lift. For the first time in over 40 years, the page size has been increased, which will provide flexibility in adding new material. The page layout and typeface have also been modernized, leading to more easily readable text and tables.

The pdf files in the electronic version of the *Handbook* mimic the new layout of the pages in the print edition. Furthermore, the number of interactive tables has been increased from 76 to 103. Among the topics included for the first time in interactive form are vapor pressure of the elements at high temperature; heat of dilution and molar conductivity of acids; electron and proton affinities; atomic transition probabilities; speed of sound in various media; the NIST thermocouple tables; and many others. The database from which these interactive tables are generated now has over 106,000 records which can be searched, manipulated, and displayed in a variety of ways.

In terms of content, several new topics appear in the 86th Edition, including:

- Electron Inelastic Mean Free Paths
- Proton Affinities
- Vapor Pressures (Solvent Activities) for Binary Polymer Solutions
- Selected Properties of Semiconductor Solid Solutions
- Electrical Conductivity of Aqueous Solutions

There are also major updates and expansions of a number of tables, such as:

- Bond Dissociation Energies (previously called Strengths of Chemical Bonds)
- NIST Atomic Transition Probability Tables
- Properties of Semiconductors
- Summary Table of Particle Properties
- Atomic Masses and Abundances
- Threshold Limits for Airborne Contaminants
- Standard Transformed Gibbs Energy ofFormation for Important Biochemical Species

The overall philosophy of the *Handbook* remains the same, namely, to provide broad coverage of all types of data commonly encountered by physical scientists and engineers in a user-friendly format. In spite of the growing popularity of Internet searching, which often turns up voluminous information of questionable quality, we feel there is still a need for a concise, reliable reference source spanning the full range of the physical sciences and focusing on key data that are frequently needed by R&D professionals, engineers, and students. The *CRC Handbook*, in its print, CDROM, and Internet formats, is aimed at serving these needs. The data contained in the *Handbook* have been carefully evaluated by experts in each field; quality control is a high priority and the sources are documented. The annual updates make it possible to add new and better data in a timely fashion. In this way we hope to continue the role of the *CRC Handbook* as a unique reference source.

The *Handbook of Chemistry and Physics* is dependent on the efforts of many contributors throughout the world. Valuable suggestions have been received from the Editorial Advisory Board and from many users. The assistance and support of Dr. Fiona

Macdonald, Chemistry Publisher at Taylor and Francis, is greatly appreciated. Finally, I want to thank the editorial and production staff at Taylor and Francis for all their efforts.

Comments and suggestions may be sent to drlide@post.harvard.edu.

David R. Lide
May 2005

The 86th Edition is dedicated to my wife, Bettijoyce Breen Lide

How To Cite this Reference

The recommended form of citation is: David R. Lide, ed., *CRC Handbook of Chemistry and Physics, 86th Edition (CDROM Version 2006)*, Taylor and Francis, Boca Raton, FL. If a specific table is cited, use the format: "Physical Constants of Organic Compounds", in *CRC Handbook of Chemistry and Physics, 86th Edition (CDROM Version 2006),* David R. Lide, ed., Taylor and Francis, Boca Raton, FL.

This work contains information obtained from authentic and highly regarded sources. Reprinted material is quoted with permission, and sources are indicated. A wide variety of references are listed. Best efforts have been made to select and verify the data on the basis of sound scientific judgment, but the author and the publisher cannot accept responsibility for the validity of all materials or for the consequences of their use.

© Copyright Taylor and Francis Group LLC 2006

CURRENT CONTRIBUTORS

Robert A. Alberty
Department of Chemistry
Massachusetts Institute of Technology
Cambridge, MA 02139

Lev I. Berger
California Institute of Electronics and Materials Science
2115 Flame Tree Way
Hemet, California 92545

A. K. Covington
Department of Chemistry
University of Newcastle
Newcastle upon Tyne NE1 7RU
England

K. Fischer
LTP GmbH
Oppelner Strasse 12
D-26135 Oldenburg, Germany

Jean-Claude Fontaine
ITODYS
CNRS, University of Paris VII
1 rue Guy de la Brosse
75005 Paris, France

J.R. Fuhr
Atomic Physics Division
National Institute of Standards and Technology
Gaithersburg, Maryland 20899

J. Gmehling
Universität Oldenburg
Fakultät V, Technische Chemie
D-26111 Oldenburg, Germany

Robert N. Goldberg
Biotechnology Division
National Institute of Standards and Technology
Gaithersburg, Maryland 20899

Norman E. Holden
National Nuclear Data Center
Brookhaven National Laboratory
Upton, New York 11973

Henry V. Kehiaian
ITODYS
University of Paris VII
1 rue Guy de la Brosse
75005 Paris, France

J. Alistair Kerr
School of Chemistry
University of Birmingham
Birmingham B 15 2TT England

J. Krafczyk
DDBST GmbH
Industriestrasse 1
D-26121 Oldenburg, Germany

Frank J. Lovas
8616 Melwood Rd.
Bethesda, Maryland 20817

Yu-Ran Luo
College of Marine Science
University of South Florida
140 7th Ave. South
St. Petersburg , FL 33701

William C. Martin
Atomic Physics Division
National Institute of Standards and Technology
Gaithersburg, Maryland 20899

J. Menke
DDBST GmbH
Industriestrasse 1
D-26121 Oldenburg, Germany

Thomas M. Miller
Air Force Research Laboratory/VSBP
29 Randolph Rd.
Hanscom AFB, Massachusetts 01731-3010

Peter J. Mohr
Physics Laboratory
National Institute of Standards and Technology
Gaithersburg, Maryland 20899

Cedric J. Powell
Surface and Microanalysis Science Division
National Institute of Standards and Technology
Gaithersburg, Maryland 20899

Joseph Reader
Atomic Physics Division
National Institute of Standards and Technology
Gaithersburg, Maryland 20899

Paul A. Redhead
1958 Norway Crescent
Ottawa, ON K1H 5N7
Canada

Lewis E. Snyder
Astronomy Department
University of Illinois
Urbana, Illinois 61801

B. N. Taylor
Physics Laboratory
National Institute of Standards and Technology
Gaithersburg, Maryland 20899

Petr Vanýsek
Department of Chemistry
Northern Illinois University
DeKalb, Illinois 60115

Wolfgang L. Wiese
Atomic Physics Division
National Institute of Standards and Technology
Gaithersburg, Maryland 20899

Christian Wohlfarth
Institut für Physikalische Chemie
Martin Luther University
D-06217 Merseburg
Germany

Daniel Zwillinger
Mathematics Department
Rensselaer Polytechnic Institute
Troy, New York 12180

Piotr Zyla
Particle Data Group
Lawrence Berkeley Laboratory
1 Cyclotron Road
Berkeley, California 94720

FUNDAMENTAL PHYSICAL CONSTANTS

Peter J. Mohr and Barry N. Taylor

These tables give the 2002 self-consistent set of values of the basic constants and conversion factors of physics and chemistry recommended by the Committee on Data for Science and Technology (CODATA) for international use. The 2002 set replaces the previously recommended 1998 CODATA set. The 2002 adjustment takes into account the data considered in the 1998 adjustment as well as the data that became available between 31 December 1998, the closing date of that adjustment, and 31 December 2002, the closing date of the new adjustment.

This report was prepared by the authors under the auspices of the CODATA Task Group on Fundamental Constants. The members of the Task Group are:

F. Cabiati, Istituto Elettrotecnico Nazionale "Galileo Ferraris," Italy
E. R. Cohen, Science Center, Rockwell International (retired), United States of America
K. Fujii, National Metrology Institute of Japan, Japan
S. G. Karshenboim, D. I. Mendeleyev All-Russian Research Institute for Metrology, Russian Federation
I. Lindgren, Chalmers University of Technology and Göteborg University, Sweden
B. A. Mamyrin, A. F. Ioffe Physical-Technical Institute, Russian Federation
W. Martienssen, Johann Wolfgang Goethe-Universität, Germany
P. J. Mohr, National Institute of Standards and Technology, United States of America
F. Nez, Laboratoire Kastler-Brossel, France
B. W. Petley, National Physical Laboratory, United Kingdom
T. J. Quinn, Bureau International des Poids et Mesures
B. N. Taylor, National Institute of Standards and Technology, United States of America
W. Wöger, Physikalisch-Technische Bundesanstalt, Germany
B. M. Wood, National Research Council, Canada
Z. Zhang, National Institute of Metrology, China (People's Republic of)

Reference

Mohr, P. J. and Taylor, B. N., *The 2002 CODATA Recommended Values of the Fundamental Physical Constants*, Web Version 4.0, NIST Physical Data web site <http://physics.nist.gov/cuu/constants> (December 2003); *Rev. Mod. Phys*. 76, No. 4, October 2004.

TABLE I. An Abbreviated List of the CODATA Recommended Values of the Fundamental Constants of Physics and Chemistry Based on the 2002 Adjustment

Quanity	Symbol	Numerical value	Unit	Relative std. uncert. u_r
speed of light in vacuum	c, c_0	299 792 458	m s^{-1}	(exact)
magnetic constant	μ_0	$4\pi \times 10^{-7}$	N A^{-2}	
		$= 12.566\ 370\ 614\ldots \times 10^{-7}$	N A^{-2}	(exact)
electric constant $1/\mu_0 c^2$	ε_0	$8.854\ 187\ 817\ldots \times 10^{-12}$	F m^{-1}	(exact)
Newtonian constant of gravitation	G	$6.6742(10) \times 10^{-11}$	m^3 kg^{-1} s^{-2}	1.5×10^{-4}
Planck constant	h	$6.626\ 0693(11) \times 10^{-34}$	J s	1.7×10^{-7}
$h/2\pi$	$\hbar$	$1.054\ 571\ 68(18) \times 10^{-34}$	J s	1.7×10^{-7}
elementary charge	e	$1.602\ 176\ 53(14) \times 10^{-19}$	C	8.5×10^{-8}
magnetic flux quantum $h/2e$	ϕ_0	$2.067\ 833\ 72(18) \times 10^{-15}$	Wb	8.5×10^{-8}
conductance quantum $2e^2/h$	G_0	$7.748\ 091\ 733(26) \times 10^{-5}$	S	3.3×10^{-9}
electron mass	m_e	$9.109\ 3826(16) \times 10^{-31}$	kg	1.7×10^{-7}
proton mass	m_p	$1.672\ 621\ 71(29) \times 10^{-27}$	kg	1.7×10^{-7}
proton-electron mass ratio	m_p/m_e	1836.152 672 61(85)		4.6×10^{-10}
fine-structure constant $e^2/4\pi\varepsilon_0\hbar c$	α	$7.297\ 352\ 568(24) \times 10^{-3}$		3.3×10^{-9}
inverse fine-structure constant	α^{-1}	137.035 999 11(46)		3.3×10^{-9}
Rydberg constant $\alpha^2 m_e c/2h$	R_∞	10 973 731.568 525(73)	m^{-1}	6.6×10^{-12}
Avogadro constant	N_A, L	$6.022\ 1415(10) \times 10^{23}$	mol^{-1}	1.7×10^{-7}
Faraday constant $N_A e$	F	96 485.3383(83)	C mol^{-1}	8.6×10^{-8}
molar gas constant	R	8.314 472(15)	J mol^{-1} K^{-1}	1.7×10^{-6}
Boltzmann constant R/N_A	k	$1.380\ 6505(24) \times 10^{-23}$	J K^{-1}	1.8×10^{-6}
Stefan-Boltzmann constant $(\pi^2/60)k^4/\hbar^3c^2$	σ	$5.670\ 400(40) \times 10^{-8}$	W m^{-2} K^{-4}	7.0×10^{-6}
Non-SI units accepted for use with the SI				
electron volt: (e/C) J	eV	$1.602\ 176\ 53(14) \times 10^{-19}$	J	8.5×10^{-8}
(unified) atomic mass unit 1 u = $m_u = (1/12)m(^{12}C) = 10^{-3}$ kg mol$^{-1}/N_A$	u	$1.660\ 538\ 86(28) \times 10^{-27}$	kg	1.7×10^{-7}

TABLE II. The CODATA Recommended Values of the Fundamental Constants of Physics and Chemistry Based on the 2002 Adjustment

Quantity	Symbol	Numerical value	Unit	Relative std. uncert. u_r
Universal				
speed of light in vacuum	c, c_0	299 792 458	m s^{-1}	(exact)
magnetic constant	μ_0	$4\pi \times 10^{-7}$	N A^{-2}	
		$= 12.566\ 370\ 614\ldots \times 10^{-7}$	N A^{-2}	(exact)
electric constant $1/\mu_0 c^2$	ε_0	$8.854\ 187\ 817\ldots \times 10^{-12}$	F m^{-1}	(exact)
characteristic impedance of vacuum $\sqrt{\mu_0/\varepsilon_0} = \mu_0 c$	Z_0	376.730 313 461…	Ω	(exact)
Newtonian constant of gravitation	G	$6.6742(10) \times 10^{-11}$	m^3 kg^{-1} s^{-2}	1.5×10^{-4}
	$G/\hbar c$	$6.7087(10) \times 10^{-39}$	(GeV/c^2)$^{-2}$	1.5×10^{-4}
Planck constant	h	$6.626\ 0693(11) \times 10^{-34}$	J s	1.7×10^{-7}
in eV s		$4.135\ 667\ 43(35) \times 10^{-15}$	eV s	8.5×10^{-8}
$h/2\pi$	$\hbar$	$1.054\ 571\ 68(18) \times 10^{-34}$	J s	1.7×10^{-7}
in eV s		$6.582\ 119\ 15(56) \times 10^{-16}$	eV s	8.5×10^{-8}
$\hbar c$ in MeV fm		197.326 968(17)	MeV fm	8.5×10^{-8}
Planck mass $(\hbar c/G)^{1/2}$	m_P	$2.176\ 45(16) \times 10^{-8}$	kg	7.5×10^{-5}
Planck temperature $(\hbar c^5/G)^{1/2}/k$	T_P	$1.416\ 79(11) \times 10^{32}$	K	7.5×10^{-5}
Planck length $\hbar/m_P c = (\hbar G/c^3)^{1/2}$	l_P	$1.616\ 24(12) \times 10^{-35}$	m	7.5×10^{-5}
Planck time $l_P/c = (\hbar G/c^5)^{1/2}$	t_P	$5.391\ 21(40) \times 10^{-44}$	s	7.5×10^{-5}
Electromagnetic				
elementary charge	e	$1.602\ 176\ 53(14) \times 10^{-19}$	C	8.5×10^{-8}
	e/h	$2.417\ 989\ 40(21) \times 10^{14}$	A J^{-1}	8.5×10^{-8}
magnetic flux quantum $h/2e$	Φ_0	$2.067\ 833\ 72(18) \times 10^{-15}$	Wb	8.5×10^{-8}
conductance quantum $2e^2/h$	G_0	$7.748\ 091\ 733(26)\times10^{-5}$	S	3.3×10^{-9}
inverse of conductance quantum	G_0^{-1}	12 906.403 725(43)	Ω	3.3×10^{-9}
Josephson constant[1] $2e/h$	K_J	$483\ 597.879(41)\times10^9$	Hz V^{-1}	8.5×10^{-8}
von Klitzing constant[2] $h/e^2 = \mu_0 c/2\alpha$	R_K	25 812.807 449(86)	Ω	3.3×10^{-9}
Bohr magneton $e\hbar/2m_e$	μ_B	$927.400\ 949(80)\times10^{-26}$	J T^{-1}	8.6×10^{-8}
in eV T^{-1}		$5.788\ 381\ 804(39)\times10^{-5}$	eV T^{-1}	6.7×10^{-9}
	μ_B/h	$13.996\ 2458(12)\times10^9$	Hz T^{-1}	8.6×10^{-8}
	μ_B/hc	46.686 4507(40)	m^{-1} T^{-1}	8.6×10^{-8}
	μ_B/k	0.671 7131(12)	K T^{-1}	1.8×10^{-6}
nuclear magneton $e\hbar/2m_p$	μ_N	$5.050\ 783\ 43(43)\times10^{-27}$	J T^{-1}	8.6×10^{-8}
in eV T^{-1}		$3.152\ 451\ 259(21)\times10^{-8}$	eV T^{-1}	6.7×10^{-9}
	μ_N/h	7.622 593 71(65)	MHz T^{-1}	8.6×10^{-8}
	μ_N/hc	$2.542\ 623\ 58(22)\times10^{-2}$	m^{-1} T^{-1}	8.6×10^{-8}
	μ_N/k	$3.658\ 2637(64)\times10^{-4}$	K T^{-1}	1.8×10^{-6}
Atomic and Nuclear				
General				
Fine-structure constant $e^2/4\pi\varepsilon_0\hbar c$	α	$7.297\ 352\ 568(24)\times10^{-3}$		3.3×10^{-9}
inverse fine-structure constant	α^{-1}	137.035 999 11(46)		3.3×10^{-9}
Rydberg constant $\alpha^2 m_e c/2h$	R_∞	10 973 731.568 525(73)	m^{-1}	6.6×10^{-12}
	$R_\infty c$	$3.289\ 841\ 960\ 360(22)\times10^{15}$	Hz	6.6×10^{-12}
	$R_\infty hc$	$2.179\ 872\ 09(37)\times10^{-18}$	J	1.7×10^{-7}
$R_\infty hc$ in eV		13.605 6923(12)	eV	8.5×10^{-8}
Bohr radius $\alpha/4\pi R_\infty = 4\pi\varepsilon_0\hbar^2/m_e e^2$	a_0	$0.529\ 177\ 2108(18)\times10^{-10}$	m	3.3×10^{-9}
Hartree energy $e^2/4\pi\varepsilon_0 a_0 = 2R_\infty hc = \alpha^2 m_e c^2$	E_h	$4.359\ 744\ 17(75)\times10^{-18}$	J	1.7×10^{-7}
in eV		27.211 3845(23)	eV	8.5×10^{-8}
quantum of circulation	$h/2m_e$	$3.636\ 947\ 550(24)\times10^{-4}$	m^{2}s^{-1}	6.7×10^{-9}
	h/m_e	$7.273\ 895\ 101(48)\times10^{-4}$	m^{2}s^{-1}	6.7×10^{-9}
Electroweak				
Fermi coupling constant[3]	$G_F/(\hbar c)^3$	$1.166\ 39(1)\times10^{-5}$	GeV^{-2}	8.6×10^{-6}
weak mixing angle[4] θ_W (on-shell scheme) $\sin^2\theta_W = s_W^2 \equiv 1 - (m_W/m_Z)^2$	$\sin^2\theta_W$	0.222 15(76)		3.4×10^{-3}
Electron, e$^-$				
electron mass	m_e	$9.109\ 3826(16)\times10^{-31}$	kg	1.7×10^{-7}
in u, $m_e = A_r(e)$ u (electron relative atomic mass times u)		$5.485\ 799\ 0945(24)\times10^{-4}$	u	4.4×10^{-10}

Quantity	Symbol	Numerical value	Unit	Relative std. uncert. u_r
energy equivalent	$m_e c^2$	8.187 1047(14)×10^{-14}	J	1.7×10^{-7}
in MeV		0.510 998 918(44)	MeV	8.6×10^{-8}
electron-muon mass ratio	m_e/m_μ	4.836 331 67(13)×10^{-3}		2.6×10^{-8}
electron-tau mass ratio	m_e/m_τ	2.875 64(47)×10^{-4}		1.6×10^{-4}
electron-proton mass ratio	m_e/m_p	5.446 170 2173(25)×10^{-4}		4.6×10^{-10}
electron-neutron mass ratio	m_e/m_n	5.438 673 4481(38)×10^{-4}		7.0×10^{-10}
electron-deuteron mass ratio	m_e/m_d	2.724 437 1095(13)×10^{-4}		4.8×10^{-10}
electron to alpha particle mass ratio	m_e/m_α	1.370 933 555 75(61)×10^{-4}		4.4×10^{-10}
electron charge to mass quotient	$-e/m_e$	−1.758 820 12(15)×10^{11}	C kg^{-1}	8.6×10^{-8}
electron molar mass $N_A m_e$	M(e), M_e	5.485 799 0945(24)×10^{-7}	kg mol^{-1}	4.4×10^{-10}
Compton wavelength $h/m_e c$	λ_C	2.426 310 238(16)×10^{-12}	m	6.7×10^{-9}
$\lambda_C/2\pi = \alpha a_0 = \alpha^2/4\pi R_\infty$	$\lambda\!\!\!^{-}_C$	386.159 2678(26)×10^{-15}	m	6.7×10^{-9}
classical electron radius $\alpha^2 a_0$	r_e	2.817 940 325(28)×10^{-15}	m	1.0×10^{-8}
Thomson cross section $(8\pi/3)r_e^2$	σ_e	0.665 245 873(13)×10^{-28}	m^2	2.0×10^{-8}
electron magnetic moment	μ_e	−928.476 412(80)×10^{-26}	J T^{-1}	8.6×10^{-8}
to Bohr magneton ratio	μ_e/μ_B	−1.001 159 652 1859(38)		3.8×10^{-12}
to nuclear magneton ratio	μ_e/μ_N	−1838.281 971 07(85)		4.6×10^{-10}
electron magnetic moment anomaly $\lvert\mu_e\rvert/\mu_B - 1$	a_e	1.159 652 1859(38)×10^{-3}		3.2×10^{-9}
electron g-factor $-2(1 + a_e)$	g_e	−2.002 319 304 3718(75)		3.8×10^{-12}
electron-muon magnetic moment ratio	μ_e/μ_μ	206.766 9894(54)		2.6×10^{-8}
electron-proton magnetic moment ratio	$\mu_e\mu_p$	−658.210 6862(66)		1.0×10^{-8}
electron to shielded proton magnetic moment ratio (H_2O, sphere, 25°C)	μ_e/μ_p'	−658.227 5956(71)		1.1×10^{-8}
electron-neutron magnetic moment ratio	μ_e/μ_n	960.920 50(23)		2.4×10^{-7}
electron-deuteron magnetic moment ratio	μ_e/μ_d	−2 143.923 493(23)		1.1×10^{-8}
electron to shielded helion[5] magnetic moment ratio (gas, sphere, 25°C)	μ_e/μ_h'	864.058 255(10)		1.2×10^{-8}
electron gyromagnetic ratio $2\lvert\mu_e\rvert/\hbar$	γ_e	1.760 859 74(15)×10^{11}	s^{-1} T^{-1}	8.6×10^{-8}
	$\gamma_e/2\pi$	28 024.9532(24)	MHz T^{-1}	8.6×10^{-8}
Muon, μ^-				
muon mass	m_μ	1.883 531 40(33)×10^{-28}	kg	1.7×10^{-7}
in u, $m_\mu = A_r(\mu)$ u (muon relative atomic mass times u)		0.113 428 9264(30)	u	2.6×10^{-8}
energy equivalent	$m_\mu c^2$	1.692 833 60(29)×10^{-11}	J	1.7×10^{-7}
in MeV		105.658 3692(94)	MeV	8.9×10^{-8}
muon-electron mass ratio	m_μ/m_e	206.768 2838(54)		2.6×10^{-8}
muon-tau mass ratio	m_μ/m_τ	5.945 92(97)×10^{-2}		1.6×10^{-4}
muon-proton mass ratio	m_μ/m_p	0.112 609 5269(29)		2.6×10^{-8}
muon-neutron mass ratio	m_μ/m_n	0.112 454 5175(29)		2.6×10^{-8}
muon molar mass $N_A m_\mu$	$M(\mu)$, M_μ	0.113 428 9264(30)×10^{-3}	kg mol^{-1}	2.6×10^{-8}
muon Compton wavelength $h/m_\mu c$	$\lambda_{C,\mu}$	11.734 441 05(30)×10^{-15}	m	2.5×10^{-8}
$\lambda_{C,\mu}/2\pi$	$\lambda\!\!\!^{-}_{C,\mu}$	1.867 594 298(47)×10^{-15}	m	2.5×10^{-8}
muon magnetic moment	μ_μ	−4.490 447 99(40)×10^{-26}	J T^{-1}	8.9×10^{-8}
to Bohr magneton ratio	μ_μ/μ_B	−4.841 970 45(13)×10^{-3}		2.6×10^{-8}
to nuclear magneton ratio	μ_μ/μ_N	−8.890 596 98(23)		2.6×10^{-8}
muon magnetic moment anomaly $\lvert\mu_\mu\rvert/(e\hbar/2m_\mu) - 1$	α_μ	1.165 919 81(62)×10^{-3}		5.3×10^{-7}
muon g-factor $-2(1 + \alpha_\mu)$	g_μ	−2.002 331 8396(12)		6.2×10^{-10}
muon-proton magnetic moment ratio	μ_μ/μ_p	−3.183 345 118(89)		2.8×10^{-8}
Tau, τ^-				
tau mass[6]	m_τ	3.167 77(52)×10^{-27}	kg	1.6×10^{-4}
in u, $m_\tau = A_r(\tau)$ u (tau relative atomic mass times u)		1.907 68(31)	u	1.6×10^{-4}
energy equivalent	$m_\tau c^2$	2.847 05(46)×10^{-10}	J	1.6×10^{-4}
in MeV		1776.99(29)	MeV	1.6×10^{-4}
tau-electron mass ratio	m_τ/m_e	3477.48(57)		1.6×10^{-4}
tau-muon mass ratio	m_τ/m_μ	16.8183(27)		1.6×10^{-4}
tau-proton mass ratio	m_τ/m_p	1.893 90(31)		1.6×10^{-4}
tau-neutron mass ratio	m_τ/m_n	1.891 29(31)		1.6×10^{-4}
tau molar mass $N_A m_\tau$	$M(\tau)$, M_τ	1.907 68(31)×10^{-3}	kg mol^{-1}	1.6×10^{-4}
tau Compton wavelength $h/m_\tau c$	$\lambda_{C,\tau}$	0.697 72(11)×10^{-15}	m	1.6×10^{-4}
$\lambda_{C,\tau}/2\pi$	$\lambda\!\!\!^{-}_{C,\tau}$	0.111 046(18)×10^{-15}	m	1.6×10^{-4}

Quantity	Symbol	Numerical value	Unit	Relative std. uncert. u_r
Proton, p				
proton mass	m_p	1.672 621 71(29)×10^{-27}	kg	1.7×10^{-7}
in u, $m_p = A_r$(p) u (proton relative atomic mass times u)		1.007 276 466 88(13)	u	1.3×10^{-10}
energy equivalent	$m_p c^2$	1.503 277 43(26)×10^{-10}	J	1.7×10^{-7}
in MeV		938.272 029(80)	MeV	8.6×10^{-8}
proton-electron mass ratio	m_p/m_e	1836.152 672 61(85)		4.6×10^{-10}
proton-muon mass ratio	m_p/m_μ	8.880 243 33(23)		2.6×10^{-8}
proton-tau mass ratio	m_p/m_τ	0.528 012(86)		1.6×10^{-4}
proton-neutron mass ratio	m_p/m_n	0.998 623 478 72(58)		5.8×10^{-10}
proton charge to mass quotient	e/m_p	9.578 833 76(82)×10^{7}	C kg^{-1}	8.6×10^{-8}
proton molar mass $N_A m_p$	M(p), M_p	1.007 276 466 88(13)×10^{-3}	kg mol^{-1}	1.3×10^{-10}
proton Compton wavelength $h/m_p c$	$\lambda_{C,p}$	1.321 409 8555(88)×10^{-15}	m	6.7×10^{-9}
$\lambda_{C,p}/2\pi$	$\lambda\!\!\!^{-}_{C,P}$	0.210 308 9104(14)×10^{-15}	m	6.7×10^{-9}
proton rms charge radius	R_p	0.8750(68)×10^{-15}	m	7.8×10^{-3}
proton magnetic moment	μ_p	1.410 606 71(12)×10^{-26}	J T^{-1}	8.7×10^{-8}
to Bohr magneton ratio	μ_p/μ_B	1.521 032 206(15)×10^{-3}		1.0×10^{-8}
to nuclear magneton ratio	μ_p/μ_N	2.792 847 351(28)		1.0×10^{-8}
proton g-factor $2\mu_p/\mu_N$	g_p	5.585 694 701(56)		1.0×10^{-8}
proton-neutron magnetic moment ratio	μ_p/μ_n	−1.459 898 05(34)		2.4×10^{-7}
shielded proton magnetic moment (H_2O, sphere, 25°C)	μ'_p	1.410 570 47(12)×10^{-26}	J T^{-1}	8.7×10^{-8}
to Bohr magneton ratio	μ'_p/μ_B	1.520 993 132(16)×10^{-3}		1.1×10^{-8}
to nuclear magneton ratio	μ'_p/μ_N	2.792 775 604(30)		1.1×10^{-8}
proton magnetic shielding correction $1-\mu'_p/\mu_p$ (H_2O, sphere, 25°C)	σ'_p	25.689(15)×10^{-6}		5.7×10^{-4}
proton gyromagnetic ratio $2\mu_p/\hbar$	γ_p	2.675 222 05(23)×10^{8}	s^{-1} T^{-1}	8.6×10^{-8}
	$\gamma_p/2\pi$	42.577 4813(37)	MHz T^{-1}	8.6×10^{-8}
shielded proton gyromagnetic ratio $2\mu'_p/\hbar$ (H_2O, sphere, 25°C)	γ'_p	2.675 153 33(23)×10^{8}	s^{-1} T^{-1}	8.6×10^{-8}
	$\gamma'_p/2\pi$	42.576 3875(37)	MHz T^{-1}	8.6×10^{-8}
Neutron, n				
neutron mass	m_n	1.674 927 28(29)×10^{-27}	kg	1.7×10^{-7}
in u, $m_n = A_r$ (n) u (neutron relative atomic mass times u)		1.008 664 915 60(55)	u	5.5×10^{-10}
energy equivalent	$m_n c^2$	1.505 349 57(26)×10^{-10}	J	1.7×10^{-7}
in MeV		939.565 360(81)	MeV	8.6×10^{-8}
neutron-electron mass ratio	m_n/m_e	1838.683 6598(13)		7.0×10^{-10}
neutron-muon mass ratio	m_n/m_μ	8.892 484 02(23)		2.6×10^{-8}
neutron-tau mass ratio	m_n/m_τ	0.528 740(86)		1.6×10^{-4}
neutron-proton mass ratio	m_n/m_p	1.001 378 418 70(58)		5.8×10^{-10}
neutron molar mass $N_A m_n$	M(n), M_n	1.008 664 915 60(55)×10^{-3}	kg mol^{-1}	5.5×10^{-10}
neutron Compton wavelength $h/m_n c$	$\lambda_{C,n}$	1.319 590 9067(88)×10^{-15}	m	6.7×10^{-9}
$\lambda_{C,n}/2\pi$	$\lambda\!\!\!^{-}_{C,n}$	0.210 019 4157(14)×10^{-15}	m	6.7×10^{-9}
neutron magnetic moment	μ_n	−0.966 236 45(24)×10^{-26}	J T^{-1}	2.5×10^{-7}
to Bohr magneton ratio	μ_n/μ_B	−1.041 875 63(25)×10^{-3}		2.4×10^{-7}
to nuclear magneton ratio	μ_n/μ_N	−1.913 042 73(45)		2.4×10^{-7}
neutron g-factor $2\mu_n/\mu_N$	g_n	−3.826 085 46(90)		2.4×10^{-7}
neutron-electron magnetic moment ratio	μ_n/μ_e	1.040 668 82(25)×10^{-3}		2.4×10^{-7}
neutron-proton magnetic moment ratio	μ_n/μ_p	−0.684 979 34(16)		2.4×10^{-7}
neutron to shielded proton magnetic moment ratio (H_2O, sphere, 25°C)	μ_n/μ'_p	−0.684 996 94(16)		2.4×10^{-7}
neutron gyromagnetic ratio $2\lvert\mu_n\rvert/\hbar$	γ_n	1.832 471 83(46)×10^{8}	s^{-1} T^{-1}	2.5×10^{-7}
	$\gamma_n/2\pi$	29.164 6950(73)	MHz T^{-1}	2.5×10^{-7}
Deuteron, d				
deuteron mass	m_d	3.343 583 35(57)×10^{-27}	kg	1.7×10^{-7}
in u, $m_d = A_r$(d) u (deuteron relative atomic mass times u)		2.013 553 212 70(35)	u	1.7×10^{-10}
energy equivalent	$m_d c^2$	3.005 062 85(51)×10^{-10}	J	1.7×10^{-7}
in MeV		1875.612 82(16)	MeV	8.6×10^{-8}
deuteron-electron mass ratio	m_d/m_e	3670.482 9652(18)		4.8×10^{-10}
deuteron-proton mass ratio	m_d/m_p	1.999 007 500 82(41)		2.0×10^{-10}
deuteron molar mass $N_A m_d$	M(d), M_d	2.013 553 212 70(35)×10^{-3}	kg mol^{-1}	1.7×10^{-10}
deuteron rms charge radius	R_d	2.1394(28)×10^{-15}	m	1.3×10^{-3}

Quantity	Symbol	Numerical value	Unit	Relative std. uncert. u_r
deuteron magnetic moment	μ_d	0.433 073 482(38)×10^{-26}	J T^{-1}	8.7×10^{-8}
to Bohr magneton ratio	μ_d/μ_B	0.466 975 4567(50)×10^{-3}		1.1×10^{-8}
to nuclear magneton ratio	μ_d/μ_N	0.857 438 2329(92)		1.1×10^{-8}
deuteron-electron magnetic moment ratio	μ_d/μ_e	−4.664 345 548(50) ×10^{-4}		1.1×10^{-8}
deuteron-proton magnetic moment ratio	μ_d/μ_p	0.307 012 2084(45)		1.5×10^{-8}
deuteron-neutron magnetic moment ratio	μ_d/μ_n	−0.448 206 52(11)		2.4×10^{-7}
Helion, h				
helion mass[5]	m_h	5.006 412 14(86)×10^{-27}	kg	1.7×10^{-7}
in u, $m_h = A_r$(h) u (helion relative atomic mass times u)		3.014 932 2434(58)	u	1.9×10^{-9}
energy equivalent	$m_h c^2$	4.499 538 84(77)×10^{-10}	J	1.7×10^{-7}
in MeV		2808.391 42(24)	MeV	8.6×10^{-8}
helion-electron mass ratio	m_h/m_e	5495.885 269(11)		2.0×10^{-9}
helion-proton mass ratio	m_h/m_p	2.993 152 6671(58)		1.9×10^{-9}
helion molar mass $N_A m_h$	M(h), M_h	3.014 932 2434(58)×10^{-3}	kg mol^{-1}	1.9×10^{-9}
shielded helion magnetic moment (gas, sphere, 25°C)	μ'_h	−1.074 553 024(93)×10^{-26}	J T^{-1}	8.7×10^{-8}
to Bohr magneton ratio	μ'_h/μ_B	−1.158 671 474(14)×10^{-3}		1.2×10^{-8}
to nuclear magneton ratio	μ'_h/μ_N	−2.127 497 723(25)		1.2×10^{-8}
shielded helion to proton magnetic moment ratio (gas, sphere, 25°C)	μ'_h/μ_P	−0.761 766 562(12)		1.5×10^{-8}
shielded helion to shielded proton magnetic moment ratio (gas/H_2O, spheres, 25°C)	μ'_h/μ'_P	−0.761 786 1313(33)		4.3×10^{-9}
shielded helion gyromagnetic ratio $2\|\mu'_h\|/\hbar$ (gas, sphere, 25°C)	γ'_h	2.037 894 70(18)×10^{8}	s^{-1} T^{-1}	8.7×10^{-8}
	$\gamma'_h/2\pi$	32.434 1015(28)	MHz T^{-1}	8.7×10^{-8}
Alpha particle, α				
alpha particle mass	m_α	6.644 6565(11)×10^{-27}	kg	1.7×10^{-7}
in u, $m_\alpha = A_r(\alpha)$ u (alpha particle relative atomic mass times u)		4.001 506 179 149(56)	u	1.4×10^{-11}
energy equivalent	$m_\alpha c^2$	5.971 9194(10)×10^{-10}	J	1.7×10^{-7}
in MeV		3727.379 17(32)	MeV	8.6×10^{-8}
alpha particle to electron mass ratio	m_α/m_e	7294.299 5363(32)		4.4×10^{-10}
alpha particle to proton mass ratio	m_α/m_p	3.972 599 689 07(52)		1.3×10^{-10}
alpha particle molar mass $N_A m_\alpha$	$M(\alpha)$, M_α	4.001 506 179 149(56)×10^{-3}	kg mol^{-1}	1.4×10^{-11}
Physico-Chemical				
Avogadro constant	N_A, L	6.022 1415(10)×10^{23}	mol^{-1}	1.7×10^{-7}
atomic mass constant $m_u = (1/12)m(^{12}C) = 1$ u = 10^{-3} kg mol$^{-1}/N_A$	m_u	1.660 538 86(28)×10^{-27}	kg	1.7×10^{-7}
energy equivalent	$m_u c^2$	1.492 417 90(26)×10^{-10}	J	1.7×10^{-7}
in MeV		931.494 043(80)	MeV	8.6×10^{-8}
Faraday constant[7] $N_A e$	F	96 485.3383(83)	C mol^{-1}	8.6×10^{-8}
molar Planck constant	$N_A h$	3.990 312 716(27) ×10^{-10}	J s mol^{-1}	6.7×10^{-9}
	$N_A hc$	0.119 626 565 72(80)	J m mol^{-1}	6.7×10^{-9}
molar gas constant	R	8.314 472(15)	J mol^{-1} K^{-1}	1.7×10^{-6}
Boltzmann constant R/N_A	k	1.380 6505(24)×10^{-23}	J K^{-1}	1.8×10^{-6}
in eV K^{-1}		8.617 343(15)×10^{-5}	eV K^{-1}	1.8×10^{-6}
	k/h	2.083 6644(36) ×10^{10}	Hz K^{-1}	1.7×10^{-6}
	k/hc	69.503 56(12)	m^{-1} K^{-1}	1.7×10^{-6}
molar volume of ideal gas RT/p				
T = 273.15 K, p = 101.325 kPa	V_m	22.413 996(39) ×10^{-3}	m^3 mol^{-1}	1.7×10^{-6}
Loschmidt constant N_A/V_m	n_0	2.686 7773(47)×10^{25}	m^{-3}	1.8×10^{-6}
T = 273.15 K, p = 100 kPa	V_m	22.710 981(40) ×10^{-3}	m^3 mol^{-1}	1.7×10^{-6}
Sackur-Tetrode constant (absolute entropy constant)[8]				
$5/2 + \ln[(2\pi m_u kT_1/h^2)^{3/2} kT_1/p_0]$				
T_1 = 1 K, p_0 = 100 kPa	S_0/R	−1.151 7047(44)		3.8×10^{-6}
T_1 = 1 K, p_0 = 101.325 kPa		−1.164 8677(44)		3.8×10^{-6}
Stefan-Boltzmann constant $(\pi^2/60)k^4/\hbar^3c^2$	σ	5.670 400(40)×10^{-8}	W m^{-2} K^{-4}	7.0×10^{-6}
first radiation constant $2\pi hc^2$	c_1	3.741 771 38(64)×10^{-16}	W m^2	1.7×10^{-7}
first radiation constant for spectral radiance $2hc^2$	c_{1L}	1.191 042 82(20)×10^{-16}	W m^2 sr^{-1}	1.7×10^{-7}
second radiation constant hc/k	c_2	1.438 7752(25)×10^{-2}	m K	1.7×10^{-6}
Wien displacement law constant $b = \lambda_{max} T = c_2/4.965\,114\,231\ldots$	b	2.897 7685(51)×10^{-3}	m K	1.7×10^{-6}

[1] See the "Adopted values" table for the conventional value adopted internationally for realizing representations of the volt using the Josephson effect.
[2] See the "Adopted values" table for the conventional value adopted internationally for realizing representations of the ohm using the quantum Hall effect.
[3] Value recommended by the Particle Data Group (Hagiwara *et al*., 2002).
[4] Based on the ratio of the masses of the W and Z bosons m_W/m_Z recommended by the Particle Data Group (Hagiwara et al., 2002). The value for $\sin^2\theta_W$ they recommend, which is based on a particular variant of the modified minimal subtraction ($\overline{MS}$) scheme, is $\sin^2\hat{\theta}_W(M_Z) = 0.231\ 24(24)$.
[5] The helion, symbol h, is the nucleus of the ^{3}He atom.
[6] This and all other values involving m_τ are based on the value of $m_\tau c^2$ in MeV recommended by the Particle Data Group (Hagiwara et al., 2002), but with a standard uncertainty of 0.29 MeV rather than the quoted uncertainty of −0.26 MeV, +0.29 MeV.
[7] The numerical value of F to be used in coulometric chemical measurements is 96 485.336(16) [1.7×10^{-7}] when the relevant current is measured in terms of representations of the volt and ohm based on the Josephson and quantum Hall effects and the internationally adopted conventional values of the Josephson and von Klitzing constants K_{J-90} and R_{K-90} given in the "Adopted values" table.
[8] The entropy of an ideal monoatomic gas of relative atomic mass A_r is given by $S = S_0 + (3/2)R \ln A_r - R \ln(p/p_0) + (5/2)R \ln(T/\mathrm{K})$.

TABLE III. Internationally Adopted Values of Various Quantities

Quantity	Symbol	Numerical value	Unit	Relative std. uncert. u_r
molar mass of ^{12}C	$M(^{12}C)$	12×10^{-3}	kg mol^{-1}	(exact)
molar mass constant $M(^{12}C)/12$	M_u	1×10^{-3}	kg mol^{-1}	(exact)
conventional value of Josephson constant	K_{J-90}	483 597.9	GHz V^{-1}	(exact)
conventional value of von Klitzing constant	R_{K-90}	25 812.807	Ω	(exact)
standard atmosphere		101 325	Pa	(exact)
standard acceleration of gravity	g_n	9.806 65	m s^{-2}	(exact)

TABLE IV. The Values of Some Energy Equivalents Derived From the Relations $E = mc^2 = hc/\lambda = h\nu = kT$, and Based on the 2002 CODATA Adjustment of the Values of the Constants

1 eV = (e/C) J, 1 u = m_u = (1/12)m(^{12}C) = 10^{-3} kg mol$^{-1}/N_A$, and $E_h = 2R_\infty hc = \alpha^2 m_e c^2$ is the Hartree Energy (hartree)

	Relevant unit			
	J	**kg**	**m^{-1}**	**Hz**
1 J	(1 J) = 1 J	(1 J)/c^2 =1.112 650 056 ×10^{-17} kg	(1 J)/hc = 5.034 117 20(86)×10^{24} m^{-1}	(1 J)/h =1.509 190 37(26)×10^{33} Hz
1 kg	(1 kg)c^2 = 8.987 551 787 ×10^{16} J	(1 kg) = 1kg	(1 kg)c/h = 4.524 438 91(77)×10^{41} m^{-1}	(1 kg)c^2/h = 1.356 392 66(23)×10^{50} Hz
1 m^{-1}	(1 m^{-1})hc = 1.986 445 61(34)×10^{-25} J	(1 m^{-1})h/c = 2.210 218 81(38)×10^{-42} kg	(1 m^{-1}) = 1 m^{-1}	(1 m^{-1})c = 299 792 458 Hz
1 Hz	(1 Hz)h = 6.626 0693(11) ×10^{-34} J	(1 Hz)h/c^2 = 7.372 4964(13)×10^{-51} kg	(1 Hz)/c = 3.335 640 952×10^{-9} m^{-1}	(1 Hz) = 1 Hz
1 K	(1 K)k = 1.380 6505(24) ×10^{-23} J	(1 K)k/c^2 =1.536 1808(27) ×10^{-40} kg	(1 K)k/hc = 69.503 56(12) m^{-1}	(1 K)k/h = 2.083 6644(36)×10^{10} Hz
1 eV	(1 eV) =1.602 176 53(14) ×10^{-19} J	(1 eV)/c^2 = 1.782 661 81(15)×10^{-36} kg	(1 eV)/hc = 8.065 544 45(69)×10^5 m^{-1}	(1 eV)/h = 2.417 989 40(21)×10^{14} Hz
1 u	(1 u)c^2 = 1.492 417 90(26) ×10^{-10} J	(1 u) = 1.660 538 86(28)×10^{-27} kg	(1 u)c/h = 7.513 006 608(50) ×10^{14} m^{-1}	(1 u)c^2/h = 2.252 342 718(15)×10^{23} Hz
1 E_h	(1 E_h) = 4.359 744 17(75)×10^{-18} J	(1 E_h)/c^2 = 4.850 869 60(83) ×10^{-35} kg	(1 E_h)/hc = 2.194 746 313 705(15)×10^7 m^{-1}	(1 E_h)/h = 6.579 683 920 721(44)×10^{15} Hz

TABLE V. The Values of Some Energy Equivalents Derived From the Relations $E = mc^2 = hc/\lambda = h\nu = kT$, and Based on the 2002 CODATA Adjustment of the Values of the Constants

1 eV = (e/C) J, 1 u = m_u = (1/12)m(^{12}C) = 10^{-3} kg mol$^{-1}/N_A$, and $E_h = 2R_\infty hc = \alpha^2 m_e c^2$ is the Hartree Energy (hartree)

	Relevant unit			
	K	**eV**	**u**	**E_h**
1 J	(1 J)/k = 7.242 963(13)×10^{22} K	(1 J) = 6.241 509 47(53)×10^{18} eV	(1 J)/c^2 =6.700 5361(11)×10^9 u	(1 J) = 2.293 712 57(39) ×10^{17} E_h
1 kg	(1 kg)c^2/k =6.509 650(11) ×10^{39} K	(1 kg)c^2 = 5.609 588 96(48)×10^{35} eV	(1 kg) = 6.022 1415(10)×10^{26} u	(1 kg)c^2 = 2.061 486 05(35)×10^{34} E_h
1 m^{-1}	(1 m^{-1})hc/k = 1.438 7752(25)×10^{-2} K	(1 m^{-1})hc = 1.239 841 91(11)×10^{-6} eV	(1 m^{-1})h/c = 1.331 025 0506(89) ×10^{-15} u	(1 m^{-1})hc = 4.556 335 252 760(30) ×10^{-8} E_h
1 Hz	(1 Hz)h/k = 4.799 2374(84)×10^{-11} K	(1 Hz)h = 4.135 667 43(35)×10^{-15} eV	(1 Hz)h/c^2 = 4.439 821 667(30)×10^{-24} u	(1 Hz)h = 1.519 829 846 006(10)×10^{-16} E_h
1 K	(1 K) = 1 K	(1 K)k = 8.617 343(15)×10^{-5} eV	(1 K)k/c^2 =9.251 098(16)×10^{-14} u	(1 K)k = 3.166 8153(55)×10^{-6} E_h
1 eV	(1 eV)/k = 1.160 4505(20)×10^4 K	(1 eV) = 1 eV	(1 eV)/c^2 = 1.073 544 171(92)×10^{-9} u	(1 eV) = 3.674 932 45(31) ×10^{-2} E_h
1 u	(1 u)c^2/k = 1.080 9527(19)×10^{13} K	(1 u)c^2 = 931.494 043(80)×10^6 eV	(1 u) = 1 u	(1 u)c^2 = 3.423 177 686(23) ×10^7 E_h
1 E_h	(1 E_h)/k = 3.157 7465(55) ×10^5 K	(1 E_h) = 27.211 3845(23) eV	(1 E_h)/c^2 = 2.921 262 323(19)×10^{-8} u	(1 E_h) = 1 E_h

FUNDAMENTAL PHYSICAL CONSTANTS — FREQUENTLY USED CONSTANTS

Quantity	Symbol	Value	Unit	Relative std. uncert. u_r
speed of light in vacuum	c, c_0	299 792 458	m s^{-1}	(exact)
magnetic constant	μ_0	$4\pi \times 10^{-7}$	N A^{-2}	
		$= 12.566\,370\,614\ldots \times 10^{-7}$	N A^{-2}	(exact)
electric constant $1/\mu_0 c^2$	ε_0	$8.854\,187\,817\ldots \times 10^{-12}$	F m^{-1}	(exact)
Newtonian constant of gravitation	G	$6.6742(10) \times 10^{-11}$	m^3 kg^{-1} s^{-2}	1.5×10^{-4}
Plank constant	h	$6.626\,0693(11) \times 10^{-34}$	J s	1.7×10^{-7}
$h/2\pi$	$\hbar$	$1.054\,571\,68(18) \times 10^{-34}$	J s	1.7×10^{-7}
elementary charge	e	$1.602\,176\,53(14) \times 10^{-19}$	C	8.5×10^{-8}
magnetic flux quantum $h/2e$	ϕ_0	$2.067\,833\,72(18) \times 10^{-15}$	Wb	8.5×10^{-8}
conductance quantum $2e^2/h$	G_0	$7.748\,091\,733(26) \times 10^{-5}$	S	3.3×10^{-9}
electron mass	m_e	$9.109\,3826(16) \times 10^{-31}$	kg	1.7×10^{-7}
proton mass	m_p	$1.672\,621\,71(29) \times 10^{-27}$	kg	1.7×10^{-7}
proton-electron mass ratio	m_p/m_e	1836.152 672 61(85)		4.6×10^{-10}
fine-structure constant $e^2/4\pi\varepsilon_0\hbar c$	α	$7.297\,352\,568(24) \times 10^{-3}$		3.3×10^{-9}
inverse fine-structure constant	α^{-1}	137.035 999 11(46)		3.3×10^{-9}
Rydberg constant $\alpha^2 m_e c/2h$	R_∞	10 973 731.568 525(73)	m^{-1}	6.6×10^{-12}
Avogadro constant	N_A, L	$6.022\,1415(10) \times 10^{23}$	mol^{-1}	1.7×10^{-7}
Faraday constant $N_A e$	F	96 485.3383(83)	C mol^{-1}	8.6×10^{-8}
molar gas constant	R	8.314 472(15)	J mol^{-1} K^{-1}	1.7×10^{-6}
Boltzmann constant R/N_A	k	$1.380\,6505(24) \times 10^{-23}$	J K^{-1}	1.8×10^{-6}
Stefan-Boltzmann constant $(\pi^2/60)k^4/\hbar^3c^2$	σ	$5.670\,400(40) \times 10^{-8}$	W m^{-2} K^{-4}	7.0×10^{-6}
		Non-SI units accepted for use with the SI		
electron volt: (e/C) J	eV	$1.602\,176\,53(14) \times 10^{-19}$	J	8.5×10^{-8}
(unified) atomic mass unit 1 u= $m_u = {}^1/_{12}\, m(^{12}C) = 10^{-3}$ kg mol^{-1}/N_A	u	$1.660\,538\,86(28) \times 10^{-27}$	kg	1.7×10^{-7}

STANDARD ATOMIC WEIGHTS (2001)

This table of atomic weights includes the changes made in 1999 and 2001 by the IUPAC Commission on Atomic Weights and Isotopic Abundances. The Standard Atomic Weights apply to the elements as they exist naturally on Earth, and the uncertainties take into account the isotopic variation found in most laboratory samples. Further comments on the variability are given in the footnotes.

The number in parentheses following the atomic weight value gives the uncertainty in the last digit. An atomic weight entry in brackets indicates that the element that has no stable isotopes; the value given is the atomic mass in u (or the mass number, if the mass is not accurately known) for the isotope of longest half-life. Thorium, protactinium, and uranium have no stable isotopes, but the terrestrial isotopic composition is sufficiently uniform to permit a standard atomic weight to be specified.

References

1. de Laeter, J. R., Böhlke, J. K., De Bièvre, P., Hidaka, H., Peiser, H. S., Rosman, K. J. R., and Taylor, P. D. P., *Pure Appl. Chem*., 75, 683, 2003.
2. Coplen, T. D., *Pure Appl. Chem*., 73, 667, 2001.
3. Coplen, T. D., *J. Phys. Chem. Ref. Data*, 30, 701, 2001.
4. Loss, R. D., Atomic Weights of the Elements 2001, *Pure Appl. Chem*., 75, 1107, 2003.

Name	Symbol	Atomic no.	Atomic weight	Footnotes
Actinium	Ac	89	[227.0277]	a
Aluminum	Al	13	26.981538(2)	
Americium	Am	95	[243.0614]	a
Antimony	Sb	51	121.760(1)	g
Argon	Ar	18	39.948(1)	g r
Arsenic	As	33	74.92160(2)	
Astatine	At	85	[209.9871]	a
Barium	Ba	56	137.327(7)	
Berkelium	Bk	97	[247.0703]	a
Beryllium	Be	4	9.012182(3)	
Bismuth	Bi	83	208.98038(2)	
Bohrium	Bh	107	[264.12]	a
Boron	B	5	10.811(7)	g m r
Bromine	Br	35	79.904(1)	
Cadmium	Cd	48	112.411(8)	g
Calcium	Ca	20	40.078(4)	g
Californium	Cf	98	[251.0796]	a
Carbon	C	6	12.0107(8)	g r
Cerium	Ce	58	140.116(1)	g
Cesium	Cs	55	132.90545(2)	
Chlorine	Cl	17	35.453(2)	g m r
Chromium	Cr	24	51.9961(6)	
Cobalt	Co	27	58.933200(9)	
Copper	Cu	29	63.546(3)	r
Curium	Cm	96	[247.0704]	a
Darmstadtium	Ds	110	[281]	a
Dubnium	Db	105	[262.1141]	a
Dysprosium	Dy	66	162.500(1)	g
Einsteinium	Es	99	[252.0830]	a
Erbium	Er	68	167.259(3)	g
Europium	Eu	63	151.964(1)	g
Fermium	Fm	100	[257.0951]	a
Fluorine	F	9	18.9984032(5)	
Francium	Fr	87	[223.0197]	a
Gadolinium	Gd	64	157.25(3)	g
Gallium	Ga	31	69.723(1)	
Germanium	Ge	32	72.64(1)	
Gold	Au	79	196.96655(2)	
Hafnium	Hf	72	178.49(2)	
Hassium	Hs	108	[277]	a
Helium	He	2	4.002602(2)	g r
Holmium	Ho	67	164.93032(2)	
Hydrogen	H	1	1.00794(7)	g m r
Indium	In	49	114.818(3)	
Iodine	I	53	126.90447(3)	
Iridium	Ir	77	192.217(3)	
Iron	Fe	26	55.845(2)	
Krypton	Kr	36	83.798(2)	g m
Lanthanum	La	57	138.9055(2)	g
Lawrencium	Lr	103	[262.1097]	a
Lead	Pb	82	207.2(1)	g r
Lithium	Li	3	6.941(2)	b g m r
Lutetium	Lu	71	174.967(1)	g
Magnesium	Mg	12	24.3050(6)	
Manganese	Mn	25	54.938049(9)	
Meitnerium	Mt	109	[268.1388]	a
Mendelevium	Md	101	[258.0984]	a
Mercury	Hg	80	200.59(2)	
Molybdenum	Mo	42	95.94(2)	g
Neodymium	Nd	60	144.24(3)	g
Neon	Ne	10	20.1797(6)	g m
Neptunium	Np	93	[237.0482]	a
Nickel	Ni	28	58.6934(2)	
Niobium	Nb	41	92.90638(2)	
Nitrogen	N	7	14.0067(2)	g r
Nobelium	No	102	[259.1010]	a
Osmium	Os	76	190.23(3)	g
Oxygen	O	8	15.9994(3)	g r
Palladium	Pd	46	106.42(1)	g
Phosphorus	P	15	30.973761(2)	
Platinum	Pt	78	195.078(2)	
Plutonium	Pu	94	[244.0642]	a
Polonium	Po	84	[208.9824]	a
Potassium	K	19	39.0983(1)	g
Praseodymium	Pr	59	140.90765(2)	
Promethium	Pm	61	[144.9127]	a
Protactinium	Pa	91	231.03588(2)	
Radium	Ra	88	[226.0254]	a
Radon	Rn	86	[222.0176]	a
Rhenium	Re	75	186.207(1)	
Rhodium	Rh	45	102.90550(2)	
Roentgenium	Rg	111	[272.1535]	a
Rubidium	Rb	37	85.4678(3)	g
Ruthenium	Ru	44	101.07(2)	g
Rutherfordium	Rf	104	[261.1088]	a
Samarium	Sm	62	150.36(3)	g
Scandium	Sc	21	44.955910(8)	
Seaborgium	Sg	106	[266.1219]	a

Name	Symbol	Atomic no.	Atomic weight	Footnotes
Selenium	Se	34	78.96(3)	r
Silicon	Si	14	28.0855(3)	r
Silver	Ag	47	107.8682(2)	g
Sodium	Na	11	22.989770(2)	
Strontium	Sr	38	87.62(1)	g r
Sulfur	S	16	32.065(5)	g r
Tantalum	Ta	73	180.9479(1)	
Technetium	Tc	43	[97.9072]	a
Tellurium	Te	52	127.60(3)	g
Terbium	Tb	65	158.92534(2)	
Thallium	Tl	81	204.3833(2)	
Thorium	Th	90	232.0381(1)	g
Thulium	Tm	69	168.93421(2)	
Tin	Sn	50	118.710(7)	g
Titanium	Ti	22	47.867(1)	
Tungsten	W	74	183.84(1)	
Ununbium	Uub	112	[285]	a
Ununhexium	Uuh	116	[289]	a
Ununquadium	Uuq	114	[289]	a
Uranium	U	92	238.02891(3)	g m
Vanadium	V	23	50.9415(1)	
Xenon	Xe	54	131.293(6)	g m
Ytterbium	Yb	70	173.04(3)	g
Yttrium	Y	39	88.90585(2)	
Zinc	Zn	30	65.409(4)	
Zirconium	Zr	40	91.224(2)	g

[a] No stable isotope exists. The atomic mass in u (or the mass number, if the mass is not accurately known) is given in brackets for the isotope of longest half-life. Elements 112, 114, and 116 have been reported but not confirmed. There is controversy over the longest-lived isotope of Ds (element 110).

[b] Commercially available Li materials have atomic weights that range between 6.939 and 6.996; if a more accurate value is required, it must be determined for the specific material.

[g] Geological specimens are known in which the element has an isotopic composition outside the limits for the normal material. The difference between the atomic weight of the element in such specimens and that given in the table may exceed the stated uncertainty.

[m] Modified isotopic compositions may be found in commercially available material because it has been subject to an undisclosed or inadvertent isotopic fractionation. Substantial deviations in atomic weight of the element from that given in the table can occur.

[r] Range in isotopic composition of normal terrestrial material prevents a more precise atomic weight being given; the tabulated value should be applicable to any normal material.

STANDARD ATOMIC WEIGHTS (2001)

Z	Element	Symbol	Atomic Weight
1	Hydrogen	H	1.00794(7)
2	Helium	He	4.002602(2)
3	Lithium	Li	6.941(2)
4	Beryllium	Be	9.012182(3)
5	Boron	B	10.811(7)
6	Carbon	C	12.0107(8)
7	Nitrogen	N	14.0067(2)
8	Oxygen	O	15.9994(3)
9	Fluorine	F	18.9984032(5)
10	Neon	Ne	20.1797(6)
11	Sodium	Na	22.989770(2)
12	Magnesium	Mg	24.3050(6)
13	Aluminum	Al	26.981538(2)
14	Silicon	Si	28.0855(3)
15	Phosphorus	P	30.973761(2)
16	Sulfur	S	32.065(5)
17	Chlorine	Cl	35.453(2)
18	Argon	Ar	39.948(1)
19	Potassium	K	39.0983(1)
20	Calcium	Ca	40.078(4)
21	Scandium	Sc	44.955910(8)
22	Titanium	Ti	47.867(1)
23	Vanadium	V	50.9415(1)
24	Chromium	Cr	51.9961(6)
25	Manganese	Mn	54.938049(9)
26	Iron	Fe	55.845(2)
27	Cobalt	Co	58.933200(9)
28	Nickel	Ni	58.6934(2)
29	Copper	Cu	63.546(3)
30	Zinc	Zn	65.409(4)
31	Gallium	Ga	69.723(1)
32	Germanium	Ge	72.64(1)
33	Arsenic	As	74.92160(2)
34	Selenium	Se	78.96(3)
35	Bromine	Br	79.904(1)
36	Krypton	Kr	83.798(2)
37	Rubidium	Rb	85.4678(3)
38	Strontium	Sr	87.62(1)
39	Yttrium	Y	88.90585(2)
40	Zirconium	Zr	91.224(2)
41	Niobium	Nb	92.90638(2)
42	Molybdenum	Mo	95.94(2)
43	Technetium	Tc	[97.9072]
44	Ruthenium	Ru	101.07(2)
45	Rhodium	Rh	102.90550(2)
46	Palladium	Pd	106.42(1)
47	Silver	Ag	107.8682(2)
48	Cadmium	Cd	112.411(8)
49	Indium	In	114.818(3)
50	Tin	Sn	118.710(7)
51	Antimony	Sb	121.760(1)
52	Tellurium	Te	127.60(3)
53	Iodine	I	126.90447(3)
54	Xenon	Xe	131.293(6)
55	Cesium	Cs	132.90545(2)
56	Barium	Ba	137.327(7)
57	Lanthanum	La	138.9055(2)
58	Cerium	Ce	140.116(1)
59	Praseodymium	Pr	140.90765(2)
60	Neodymium	Nd	144.24(3)
61	Promethium	Pm	[144.9127]
62	Samarium	Sm	150.36(3)
63	Europium	Eu	151.964(1)
64	Gadolinium	Gd	157.25(3)
65	Terbium	Tb	158.92534(2)
66	Dysprosium	Dy	162.500(1)
67	Holmium	Ho	164.93032(2)
68	Erbium	Er	167.259(3)
69	Thulium	Tm	168.93421(2)
70	Ytterbium	Yb	173.04(3)
71	Lutetium	Lu	174.967(1)
72	Hafnium	Hf	178.49(2)
73	Tantalum	Ta	180.9479(1)
74	Tungsten	W	183.84(1)
75	Rhenium	Re	186.207(1)
76	Osmium	Os	190.23(3)
77	Iridium	Ir	192.217(3)
78	Platinum	Pt	195.078(2)
79	Gold	Au	196.96655(2)
80	Mercury	Hg	200.59(2)
81	Thallium	Tl	204.3833(2)
82	Lead	Pb	207.2(1)
83	Bismuth	Bi	208.98038(2)
84	Polonium	Po	[208.9824]
85	Astatine	At	[209.9871]
86	Radon	Rn	[222.0176]
87	Francium	Fr	[223.0197]
88	Radium	Ra	[226.0254]
89	Actinium	Ac	[227.0277]
90	Thorium	Th	232.0381(1)
91	Protactinium	Pa	231.03588(2)
92	Uranium	U	238.02891(3)
93	Neptunium	Np	[237.0482]
94	Plutonium	Pu	[244.0642]
95	Americium	Am	[243.0614]
96	Curium	Cm	[247.0704]
97	Berkelium	Bk	[247.0703]
98	Californium	Cf	[251.0796]
99	Einsteinium	Es	[252.0830]
100	Fermium	Fm	[257.0951]
101	Mendelevium	Md	[258.0984]
102	Nobelium	No	[259.1010]
103	Lawrencium	Lr	[262.1097]
104	Rutherfordium	Rf	[261.1088]
105	Dubnium	Db	[262.1141]
106	Seaborgium	Sg	[266.1219]
107	Bohrium	Bh	[264.12]
108	Hassium	Hs	[277]
109	Meitnerium	Mt	[268.1388]
110	Darmstadtium	Ds	[271]
111	Roentogenium	Rg	[272]
112	Ununbium	Uub	[285]
114	Ununquadium	Uuq	[289]
116	Ununhexium	Uuh	[289]

See page **1**-7 for further information

ATOMIC MASSES AND ABUNDANCES

This table lists the mass (in atomic mass units, symbol u) and the natural abundance (in percent) of the stable nuclides and a few important radioactive nuclides. A complete table of all nuclides may be found in Section 11 ("Table of the Isotopes").

The atomic masses were taken from the 2003 evaluation of Audi, Wapstra, and Thibault (References 2, 3). The number in parentheses following the mass value is the uncertainty in the last digit(s) given. An asterisk * after an entry indicates the mass value was derived not purely from experimental data, but at least partly from systematic trends.

Natural abundance values were taken from the IUPAC Technical Report "Atomic Weight of the Elements: Review 2000" (Reference 4); these entries are also followed by uncertainties in the last digit(s) of the stated values. This uncertainty includes both the estimated measurement uncertainty and the reported range of variation in different terrestrial sources of the element (see Reference 4 for full details and caveats regarding elements whose abundance is variable). The absence of an entry in the Abundance column indicates a radioactive nuclide not present in nature or an element whose isotopic composition varies so widely that a meaningful natural abundance cannot be defined.

References

1. Holden, N. E., "Table of the Isotopes", in Lide, D. R., Ed., *CRC Handbook of Chemistry and Physics, 86th Ed.*, CRC Press, Boca Raton FL, 2005.
2. Audi, G., Wapstra, A. H., and Thibault, *Nucl. Phys*., A729, 336, 2003.
3. Audi, G., and Wapstra, A. H., Atomic Mass Data Center, World Wide Web site, <http://www.nndc.bnl.gov/amdc/index.html>
4. de Laeter, J. R., Böhlke, J. K., De Bièvre, P., Hidaka, H., Peiser, H. S., Rosman, K. J. R., and Taylor, P. D. P., *Pure Appl. Chem*. 75, 683, 2003.

Z	Isotope	Mass in u	Abundance in %
1	^{1}H	1.00782503207(10)	99.9885(70)
	^{2}H	2.0141017778(4)	0.0115(70)
	^{3}H	3.0160492777(25)	
2	^{3}He	3.0160293191(26)	0.000134(3)
	^{4}He	4.00260325415(6)	99.999866(3)
3	^{6}Li	6.015122795(16)	7.59(4)
	^{7}Li	7.01600455(8)	92.41(4)
4	^{9}Be	9.0121822(4)	100
5	^{10}B	10.0129370(4)	19.9(7)
	^{11}B	11.0093054(4)	80.1(7)
6	^{11}C	11.0114336(10)	
	^{12}C	12.0000000(0)	98.93(8)
	^{13}C	13.0033548378(10)	1.07(8)
	^{14}C	14.003241989(4)	
7	^{14}N	14.0030740048(6)	99.636(7)
	^{15}N	15.0001088982(7)	0.364(7)
8	^{16}O	15.99491461956(16)	99.757(16)
	^{17}O	16.99913170(12)	0.038(1)
	^{18}O	17.9991610(7)	0.205(14)
9	^{18}F	18.0009380(6)	
	^{19}F	18.99840322(7)	100
10	^{20}Ne	19.9924401754(19)	90.48(3)
	^{21}Ne	20.99384668(4)	0.27(1)
	^{22}Ne	21.991385114(19)	9.25(3)
11	^{22}Na	21.9944364(4)	
	^{23}Na	22.9897692809(29)	100
	^{24}Na	23.99096278(8)	
12	^{24}Mg	23.985041700(14)	78.99(4)
	^{25}Mg	24.98583692(3)	10.00(1)
	^{26}Mg	25.982592929(30)	11.01(3)
13	^{27}Al	26.98153863(12)	100
14	^{28}Si	27.9769265325(19)	92.223(19)
	^{29}Si	28.976494700(22)	4.685(8)
	^{30}Si	29.97377017(3)	3.092(11)
15	^{31}P	30.97376163(20)	100
	^{32}P	31.97390727(20)	
16	^{32}S	31.97207100(15)	94.99(26)
	^{33}S	32.97145876(15)	0.75(2)
	^{34}S	33.96786690(12)	4.25(24)
	^{35}S	34.96903216(11)	
	^{36}S	35.96708076(20)	0.01(1)
17	^{35}Cl	34.96885268(4)	75.76(10)
	^{37}Cl	36.96590259(5)	24.24(10)
18	^{36}Ar	35.967545106(29)	0.3365(30)
	^{38}Ar	37.9627324(4)	0.0632(5)
	^{40}Ar	39.9623831225(29)	99.6003(30)
19	^{39}K	38.96370668(20)	93.2581(44)
	^{40}K	39.96399848(21)	0.0117(1)
	^{41}K	40.96182576(21)	6.7302(44)
	^{42}K	41.96240281(24)	
	^{43}K	42.960716(10)	
20	^{40}Ca	39.96259098(22)	96.941(156)
	^{42}Ca	41.95861801(27)	0.647(23)
	^{43}Ca	42.9587666(3)	0.135(10)
	^{44}Ca	43.9554818(4)	2.086(110)
	^{45}Ca	44.9561866(4)	
	^{46}Ca	45.9536926(24)	0.004(3)
	^{47}Ca	46.9545460(24)	
	^{48}Ca	47.952534(4)	0.187(21)
21	^{45}Sc	44.9559119(9)	100
22	^{46}Ti	45.9526316(9)	8.25(3)
	^{47}Ti	46.9517631(9)	7.44(2)
	^{48}Ti	47.9479463(9)	73.72(3)
	^{49}Ti	48.9478700(9)	5.41(2)
	^{50}Ti	49.9447912(9)	5.18(2)
23	^{50}V	49.9471585(11)	0.250(4)
	^{51}V	50.9439595(11)	99.750(4)
24	^{50}Cr	49.9460442(11)	4.345(13)
	^{51}Cr	50.9447674(11)	
	^{52}Cr	51.9405075(8)	83.789(18)
	^{53}Cr	52.9406494(8)	9.501(17)
	^{54}Cr	53.9388804(8)	2.365(7)
25	^{54}Mn	53.9403589(14)	
	^{55}Mn	54.9380451(7)	100
26	^{52}Fe	51.948114(7)	
	^{54}Fe	53.9396105(7)	5.845(35)
	^{55}Fe	54.9382934(7)	
	^{56}Fe	55.9349375(7)	91.754(36)
	^{57}Fe	56.9353940(7)	2.119(10)
	^{58}Fe	57.9332756(8)	0.282(4)
	^{59}Fe	58.9348755(8)	
27	^{57}Co	56.9362914(8)	

Z	Isotope	Mass in u	Abundance in %
	^{58}Co	57.9357528(13)	
	^{59}Co	58.9331950(7)	100
	^{60}Co	59.9338171(7)	
28	^{58}Ni	57.9353429(7)	68.0769(89)
	^{59}Ni	58.9343467(7)	
	^{60}Ni	59.9307864(7)	26.2231(77)
	^{61}Ni	60.9310560(7)	1.1399(6)
	^{62}Ni	61.9283451(6)	3.6345(17)
	^{63}Ni	62.9296694(6)	
	^{64}Ni	63.9279660(7)	0.9256(9)
29	^{63}Cu	62.9295975(6)	69.15(3)
	^{64}Cu	63.9297642(6)	
	^{65}Cu	64.9277895(7)	30.85(3)
30	^{64}Zn	63.9291422(7)	48.268(321)
	^{65}Zn	64.9292410(7)	
	^{66}Zn	65.9260334(10)	27.975(77)
	^{67}Zn	66.9271273(10)	4.102(21)
	^{68}Zn	67.9248442(10)	19.024(123)
	^{70}Zn	69.9253193(21)	0.631(9)
31	^{67}Ga	66.9282017(14)	
	^{68}Ga	67.9279801(16)	
	^{69}Ga	68.9255736(13)	60.108(9)
	^{71}Ga	70.9247013(11)	39.892(9)
32	^{68}Ge	67.928094(7)	
	^{70}Ge	69.9242474(11)	20.38(18)
	^{72}Ge	71.9220758(18)	27.31(26)
	^{73}Ge	72.9234589(18)	7.76(8)
	^{74}Ge	73.9211778(18)	36.72(15)
	^{76}Ge	75.9214026(18)	7.83(7)
33	^{75}As	74.9215965(20)	100
34	^{74}Se	73.9224764(18)	0.89(4)
	^{75}Se	74.9225234(18)	
	^{76}Se	75.9192136(18)	9.37(29)
	^{77}Se	76.9199140(18)	7.63(16)
	^{78}Se	77.9173091(18)	23.77(28)
	^{79}Se	78.9184991(18)	
	^{80}Se	79.9165213(21)	49.61(41)
	^{82}Se	81.9166994(22)	8.73(22)
35	^{79}Br	78.9183371(22)	50.69(7)
	^{81}Br	80.9162906(21)	49.31(7)
36	^{78}Kr	77.9203648(12)	0.355(3)
	^{80}Kr	79.9163790(16)	2.286(10)
	^{82}Kr	81.9134836(19)	11.593(31)
	^{83}Kr	82.914136(3)	11.500(19)
	^{84}Kr	83.911507(3)	56.987(15)
	^{86}Kr	85.91061073(11)	17.279(41)
37	^{85}Rb	84.911789738(12)	72.17(2)
	^{86}Rb	85.91116742(21)	
	^{87}Rb	86.909180527(13)	27.83(2)
38	^{84}Sr	83.913425(3)	0.56(1)
	^{85}Sr	84.912933(3)	
	^{86}Sr	85.9092602(12)	9.86(1)
	^{87}Sr	86.9088771(12)	7.00(1)
	^{88}Sr	87.9056121(12)	82.58(1)
	^{89}Sr	88.9074507(12)	
	^{90}Sr	89.907738(3)	
39	^{89}Y	88.9058483(27)	100
40	^{90}Zr	89.9047044(25)	51.45(40)
	^{91}Zr	90.9056458(25)	11.22(5)
	^{92}Zr	91.9050408(25)	17.15(8)
	^{94}Zr	93.9063152(26)	17.38(28)
	^{96}Zr	95.9082734(30)	2.80(9)
41	^{93}Nb	92.9063781(26)	100
42	^{92}Mo	91.906811(4)	14.77(31)
	^{94}Mo	93.9050883(21)	9.23(10)
	^{95}Mo	94.9058421(21)	15.90(9)
	^{96}Mo	95.9046795(21)	16.68(1)
	^{97}Mo	96.9060215(21)	9.56(5)
	^{98}Mo	97.9054082(21)	24.19(26)
	^{99}Mo	98.9077119(21)	
	^{100}Mo	99.907477(6)	9.67(20)
43	^{97}Tc	96.906365(5)	
	^{98}Tc	97.907216(4)	
	^{99}Tc	98.9062547(21)	
44	^{96}Ru	95.907598(8)	5.54(14)
	^{98}Ru	97.905287(7)	1.87(3)
	^{99}Ru	98.9059393(22)	12.76(14)
	^{100}Ru	99.9042195(22)	12.60(7)
	^{101}Ru	100.9055821(22)	17.06(2)
	^{102}Ru	101.9043493(22)	31.55(14)
	^{104}Ru	103.905433(3)	18.62(27)
	^{106}Ru	105.907329(8)	
45	^{103}Rh	102.905504(3)	100
46	^{102}Pd	101.905609(3)	1.02(1)
	^{104}Pd	103.904036(4)	11.14(8)
	^{105}Pd	104.905085(4)	22.33(8)
	^{106}Pd	105.903486(4)	27.33(3)
	^{108}Pd	107.903892(4)	26.46(9)
	^{110}Pd	109.905153(12)	11.72(9)
47	^{107}Ag	106.905097(5)	51.839(8)
	^{109}Ag	108.904752(3)	48.161(8)
48	^{106}Cd	105.906459(6)	1.25(6)
	^{108}Cd	107.904184(6)	0.89(3)
	^{110}Cd	109.9030021(29)	12.49(18)
	^{111}Cd	110.9041781(29)	12.80(12)
	^{112}Cd	111.9027578(29)	24.13(21)
	^{113}Cd	112.9044017(29)	12.22(12)
	^{114}Cd	113.9033585(29)	28.73(42)
	^{116}Cd	115.904756(3)	7.49(18)
49	^{111}In	110.905103(5)	
	^{113}In	112.904058(3)	4.29(5)
	^{115}In	114.903878(5)	95.71(5)
50	^{112}Sn	111.904818(5)	0.97(1)
	^{113}Sn	112.905171(4)	
	^{114}Sn	113.902779(3)	0.66(1)
	^{115}Sn	114.903342(3)	0.34(1)
	^{116}Sn	115.901741(3)	14.54(9)
	^{117}Sn	116.902952(3)	7.68(7)
	^{118}Sn	117.901603(3)	24.22(9)
	^{119}Sn	118.903308(3)	8.59(4)
	^{120}Sn	119.9021947(27)	32.58(9)
	^{122}Sn	121.9034390(29)	4.63(3)
	^{124}Sn	123.9052739(15)	5.79(5)
51	^{121}Sb	120.9038157(24)	57.21(5)
	^{123}Sb	122.9042140(22)	42.79(5)
52	^{120}Te	119.904020(10)	0.09(1)
	^{122}Te	121.9030439(16)	2.55(12)
	^{123}Te	122.9042700(16)	0.89(3)
	^{124}Te	123.9028179(16)	4.74(14)
	^{125}Te	124.9044307(16)	7.07(15)
	^{126}Te	125.9033117(16)	18.84(25)
	^{128}Te	127.9044631(19)	31.74(8)

Z	Isotope	Mass in u	Abundance in %
	^{130}Te	129.9062244(21)	34.08(62)
53	^{123}I	122.905589(4)	
	^{125}I	124.9046302(16)	
	^{127}I	126.904473(4)	100
	^{129}I	128.904988(3)	
	^{131}I	130.9061246(12)	
54	^{124}Xe	123.9058930(20)	0.0952(3)
	^{126}Xe	125.904274(7)	0.0890(2)
	^{128}Xe	127.9035313(15)	1.9102(8)
	^{129}Xe	128.9047794(8)	26.4006(82)
	^{130}Xe	129.9035080(8)	4.0710(13)
	^{131}Xe	130.9050824(10)	21.2324(30)
	^{132}Xe	131.9041535(10)	26.9086(33)
	^{134}Xe	133.9053945(9)	10.4357(21)
	^{136}Xe	135.907219(8)	8.8573(44)
55	^{129}Cs	128.906064(5)	
	^{133}Cs	132.905451933(24)	100
	^{134}Cs	133.906718475(28)	
	^{136}Cs	135.9073116(20)	
	^{137}Cs	136.9070895(5)	
56	^{130}Ba	129.9063208(30)	0.106(1)
	^{132}Ba	131.9050613(11)	0.101(1)
	^{133}Ba	132.9060075(11)	
	^{134}Ba	133.9045084(4)	2.417(18)
	^{135}Ba	134.9056886(4)	6.592(12)
	^{136}Ba	135.9045759(4)	7.854(24)
	^{137}Ba	136.9058274(5)	11.232(24)
	^{138}Ba	137.9052472(5)	71.698(42)
	^{140}Ba	139.910605(9)	
57	^{138}La	137.907112(4)	0.090(1)
	^{139}La	138.9063533(26)	99.910(1)
58	^{136}Ce	135.907172(14)	0.185(2)
	^{138}Ce	137.905991(11)	0.251(2)
	^{140}Ce	139.9054387(26)	88.450(51)
	^{141}Ce	140.9082763(26)	
	^{142}Ce	141.909244(3)	11.114(51)
	^{144}Ce	143.913647(4)	
59	^{141}Pr	140.9076528(26)	100
60	^{142}Nd	141.9077233(25)	27.2(5)
	^{143}Nd	142.9098143(25)	12.2(2)
	^{144}Nd	143.9100873(25)	23.8(3)
	^{145}Nd	144.9125736(25)	8.3(1)
	^{146}Nd	145.9131169(25)	17.2(3)
	^{148}Nd	147.916893(3)	5.7(1)
	^{150}Nd	149.920891(3)	5.6(2)
61	^{145}Pm	144.912749(3)	
	^{147}Pm	146.9151385(26)	
62	^{144}Sm	143.911999(3)	3.07(7)
	^{147}Sm	146.9148979(26)	14.99(18)
	^{148}Sm	147.9148227(26)	11.24(10)
	^{149}Sm	148.9171847(26)	13.82(7)
	^{150}Sm	149.9172755(26)	7.38(1)
	^{152}Sm	151.9197324(27)	26.75(16)
	^{154}Sm	153.9222093(27)	22.75(29)
63	^{151}Eu	150.9198502(26)	47.81(6)
	^{153}Eu	152.9212303(26)	52.19(6)
64	^{152}Gd	151.9197910(27)	0.20(1)
	^{154}Gd	153.9208656(27)	2.18(3)
	^{155}Gd	154.9226220(27)	14.80(12)
	^{156}Gd	155.9221227(27)	20.47(9)
	^{157}Gd	156.9239601(27)	15.65(2)
	^{158}Gd	157.9241039(27)	24.84(7)
	^{160}Gd	159.9270541(27)	21.86(19)
65	^{159}Tb	158.9253468(27)	100
66	^{156}Dy	155.924283(7)	0.056(3)
	^{158}Dy	157.924409(4)	0.095(3)
	^{160}Dy	159.9251975(27)	2.329(18)
	^{161}Dy	160.9269334(27)	18.889(42)
	^{162}Dy	161.9267984(27)	25.475(36)
	^{163}Dy	162.9287312(27)	24.896(42)
	^{164}Dy	163.9291748(27)	28.260(54)
67	^{165}Ho	164.9303221(27)	100
68	^{162}Er	161.928778(4)	0.139(5)
	^{164}Er	163.929200(3)	1.601(3)
	^{166}Er	165.9302931(27)	33.503(36)
	^{167}Er	166.9320482(27)	22.869(9)
	^{168}Er	167.9323702(27)	26.978(18)
	^{170}Er	169.9354643(30)	14.910(36)
69	^{169}Tm	168.9342133(27)	100
70	^{168}Yb	167.933897(5)	0.13(1)
	^{169}Yb	168.935190(5)	
	^{170}Yb	169.9347618(26)	3.04(15)
	^{171}Yb	170.9363258(26)	14.28(57)
	^{172}Yb	171.9363815(26)	21.83(67)
	^{173}Yb	172.9382108(26)	16.13(27)
	^{174}Yb	173.9388621(26)	31.83(92)
	^{176}Yb	175.9425717(28)	12.76(41)
71	^{175}Lu	174.9407718(23)	97.41(2)
	^{176}Lu	175.9426863(23)	2.59(2)
72	^{174}Hf	173.940046(3)	0.16(1)
	^{176}Hf	175.9414086(24)	5.26(7)
	^{177}Hf	176.9432207(23)	18.60(9)
	^{178}Hf	177.9436988(23)	27.28(7)
	^{179}Hf	178.9458161(23)	13.62(2)
	^{180}Hf	179.9465500(23)	35.08(16)
73	^{180}Ta	179.9474648(24)	0.012(2)
	^{181}Ta	180.9479958(19)	99.988(2)
74	^{180}W	179.946704(4)	0.12(1)
	^{182}W	181.9482042(9)	26.50(16)
	^{183}W	182.9502230(9)	14.31(4)
	^{184}W	183.9509312(9)	30.64(2)
	^{186}W	185.9543641(19)	28.43(19)
75	^{185}Re	184.9529550(13)	37.40(2)
	^{187}Re	186.9557531(15)	62.60(2)
76	^{184}Os	183.9524891(14)	0.02(1)
	^{186}Os	185.9538382(15)	1.59(3)
	^{187}Os	186.9557505(15)	1.96(2)
	^{188}Os	187.9558382(15)	13.24(8)
	^{189}Os	188.9581475(16)	16.15(5)
	^{190}Os	189.9584470(16)	26.26(2)
	^{192}Os	191.9614807(27)	40.78(19)
77	^{191}Ir	190.9605940(18)	37.3(2)
	^{193}Ir	192.9629264(18)	62.7(2)
78	^{190}Pt	189.959932(6)	0.014(1)
	^{192}Pt	191.9610380(27)	0.782(7)
	^{194}Pt	193.9626803(9)	32.967(99)
	^{195}Pt	194.9647911(9)	33.832(10)
	^{196}Pt	195.9649515(9)	25.242(41)
	^{198}Pt	197.967893(3)	7.163(55)
79	^{197}Au	196.9665687(6)	100
	^{198}Au	197.9682423(6)	
80	^{196}Hg	195.965833(3)	0.15(1)

Z	Isotope	Mass in u	Abundance in %
	^{197}Hg	196.967213(3)	
	^{198}Hg	197.9667690(4)	9.97(20)
	^{199}Hg	198.9682799(4)	16.87(22)
	^{200}Hg	199.9683260(4)	23.10(19)
	^{201}Hg	200.9703023(6)	13.18(9)
	^{202}Hg	201.9706430(6)	29.86(26)
	^{203}Hg	202.9728725(18)	
	^{204}Hg	203.9734939(4)	6.87(15)
81	^{201}Tl	200.970819(16)	
	^{203}Tl	202.9723442(14)	29.52(1)
	^{205}Tl	204.9744275(14)	70.48(1)
82	^{204}Pb	203.9730436(13)	1.4(1)
	^{206}Pb	205.9744653(13)	24.1(1)
	^{207}Pb	206.9758969(13)	22.1(1)
	^{208}Pb	207.9766521(13)	52.4(1)
	^{210}Pb	209.9841885(16)	
83	^{207}Bi	206.9784707(26)	
	^{209}Bi	208.9803987(16)	100
84	^{209}Po	208.9824304(20)	
	^{210}Po	209.9828737(13)	
85	^{210}At	209.987148(8)	
	^{211}At	210.9874963(30)	
86	^{211}Rn	210.990601(7)	
	^{220}Rn	220.0113940(24)	
	^{222}Rn	222.0175777(25)	
87	^{223}Fr	223.0197359(26)	
88	^{223}Ra	223.0185022(27)	
	^{224}Ra	224.0202118(24)	
	^{226}Ra	226.0254098(25)	
	^{228}Ra	228.0310703(26)	
89	^{227}Ac	227.0277521(26)	
90	^{228}Th	228.0287411(24)	
	^{230}Th	230.0331338(19)	
	^{232}Th	232.0380553(21)	100
91	^{231}Pa	231.0358840(24)	100
92	^{233}U	233.0396352(29)	
	^{234}U	234.0409521(20)	0.0054(5)
	^{235}U	235.0439299(20)	0.7204(6)
	^{236}U	236.0455680(20)	
	^{238}U	238.0507882(20)	99.2742(10)
93	^{237}Np	237.0481734(20)	
	^{239}Np	239.0529390(22)	
94	^{238}Pu	238.0495599(20)	
	^{239}Pu	239.0521634(20)	
	^{240}Pu	240.0538135(20)	
	^{241}Pu	241.0568515(20)	
	^{242}Pu	242.0587426(20)	
	^{244}Pu	244.064204(5)	
95	^{241}Am	241.0568291(20)	
	^{243}Am	243.0613811(25)	
96	^{243}Cm	243.0613891(22)	
	^{244}Cm	244.0627526(20)	
	^{245}Cm	245.0654912(22)	
	^{246}Cm	246.0672237(22)	
	^{247}Cm	247.070354(5)	
	^{248}Cm	248.072349(5)	
97	^{247}Bk	247.070307(6)	
	^{249}Bk	249.0749867(28)	
98	^{249}Cf	249.0748535(24)	
	^{250}Cf	250.0764061(22)	
	^{251}Cf	251.079587(5)	
	^{252}Cf	252.081626(5)	
99	^{252}Es	252.082980(50)	
100	^{257}Fm	257.095105(7)	
101	^{256}Md	256.094060(60)	
	^{258}Md	258.098431(5)	
102	^{259}No	259.10103(11)*	
103	^{262}Lr	262.10963(22)*	
104	^{261}Rf	261.108770(30)*	
105	^{262}Db	262.11408(20)*	
106	^{263}Sg	263.11832(13)*	
107	^{264}Bh	264.12460(30)*	
108	^{265}Hs	265.13009(15)*	
109	^{268}Mt	268.13873(34)*	
110	^{281}Ds	281.16206(78)*	
111	^{272}Rg	273.15362(36)*	

ELECTRON CONFIGURATION AND IONIZATION ENERGY OF NEUTRAL ATOMS IN THE GROUND STATE

William C. Martin

The ground state electron configuration, ground level, and ionization energy of the elements hydrogen through rutherfordium are listed in this table. The electron configurations of elements heavier than neon are shortened by using rare-gas element symbols in brackets to represent the corresponding electrons. See the references for details of the notation for Pa, U, and Np. Ionization energies to higher states (and more precise values of the first ionization energy for certain elements) may be found in the table "Ionization Energies of Atoms and Atomic Ions" in Section 10 of this *Handbook*.

References

1. Martin, W. C., Musgrove, A., Kotochigova, S., and Sansonetti, J. E., NIST Physical Reference Data Web Site, <http://physics.nist.gov/PhysRefData/IonEnergy/ionEnergy.html>, October 2004.
2. Martin, W. C., and Wiese, W. L., "Atomic Spectroscopy", in *Atomic, Molecular, & Optical Physics Handbook*, ed. by G.W.F. Drake (AIP, Woodbury, NY, 1996) Chapter 10, pp. 135-153.

Z		Element	Ground-state configuration	Ground level	Ionization energy (eV)
1	H	Hydrogen	$1s$	$^2S_{1/2}$	13.5984
2	He	Helium	$1s^2$	$^1S_0$	24.5874
3	Li	Lithium	$1s^2\ 2s$	$^2S_{1/2}$	5.3917
4	Be	Beryllium	$1s^2\ 2s^2$	$^1S_0$	9.3227
5	B	Boron	$1s^2\ 2s^2\ 2p$	$^2P^o_{1/2}$	8.2980
6	C	Carbon	$1s^2\ 2s^2\ 2p^2$	$^3P_0$	11.2603
7	N	Nitrogen	$1s^2\ 2s^2\ 2p^3$	$^4S^o_{3/2}$	14.5341
8	O	Oxygen	$1s^2\ 2s^2\ 2p^4$	$^3P_2$	13.6181
9	F	Fluorine	$1s^2\ 2s^2\ 2p^5$	$^2P^o_{3/2}$	17.4228
10	Ne	Neon	$1s^2\ 2s^2\ 2p^6$	$^1S_0$	21.5645
11	Na	Sodium	[Ne] $3s$	$^2S_{1/2}$	5.1391
12	Mg	Magnesium	[Ne] $3s^2$	$^1S_0$	7.6462
13	Al	Aluminum	[Ne] $3s^2\ 3p$	$^2P^o_{1/2}$	5.9858
14	Si	Silicon	[Ne] $3s^2\ 3p^2$	$^3P_0$	8.1517
15	P	Phosphorus	[Ne] $3s^2\ 3p^3$	$^4S^o_{3/2}$	10.4867
16	S	Sulfur	[Ne] $3s^2\ 3p^4$	$^3P_2$	10.3600
17	Cl	Chlorine	[Ne] $3s^2\ 3p^5$	$^2P^o_{3/2}$	12.9676
18	Ar	Argon	[Ne] $3s^2\ 3p^6$	$^1S_0$	15.7596
19	K	Potassium	[Ar] $4s$	$^2S_{1/2}$	4.3407
20	Ca	Calcium	[Ar] $4s^2$	$^1S_0$	6.1132
21	Sc	Scandium	[Ar] $3d\ 4s^2$	$^2D_{3/2}$	6.5615
22	Ti	Titanium	[Ar] $3d^2\ 4s^2$	$^3F_2$	6.8281
23	V	Vanadium	[Ar] $3d^3\ 4s^2$	$^4F_{3/2}$	6.7462
24	Cr	Chromium	[Ar] $3d^5\ 4s$	$^7S_3$	6.7665
25	Mn	Manganese	[Ar] $3d^5\ 4s^2$	$^6S_{5/2}$	7.4340
26	Fe	Iron	[Ar] $3d^6\ 4s^2$	$^5D_4$	7.9024
27	Co	Cobalt	[Ar] $3d^7\ 4s^2$	$^4F_{9/2}$	7.8810
28	Ni	Nickel	[Ar] $3d^8\ 4s^2$	$^3F_4$	7.6398
29	Cu	Copper	[Ar] $3d^{10}\ 4s$	$^2S_{1/2}$	7.7264
30	Zn	Zinc	[Ar] $3d^{10}\ 4s^2$	$^1S_0$	9.3942
31	Ga	Gallium	[Ar] $3d^{10}\ 4s^2\ 4p$	$^2P^o_{1/2}$	5.9993
32	Ge	Germanium	[Ar] $3d^{10}\ 4s^2\ 4p^2$	$^3P_0$	7.8994
33	As	Arsenic	[Ar] $3d^{10}\ 4s^2\ 4p^3$	$^4S^o_{3/2}$	9.7886
34	Se	Selenium	[Ar] $3d^{10}\ 4s^2\ 4p^4$	$^3P_2$	9.7524
35	Br	Bromine	[Ar] $3d^{10}\ 4s^2\ 4p^5$	$^2P^o_{3/2}$	11.8138
36	Kr	Krypton	[Ar] $3d^{10}\ 4s^2\ 4p^6$	$^1S_0$	13.9996
37	Rb	Rubidium	[Kr] $5s$	$^2S_{1/2}$	4.1771
38	Sr	Strontium	[Kr] $5s^2$	$^1S_0$	5.6949
39	Y	Yttrium	[Kr] $4d\ 5s^2$	$^2D_{3/2}$	6.2173
40	Zr	Zirconium	[Kr] $4d^2\ 5s^2$	$^3F_2$	6.6339
41	Nb	Niobium	[Kr] $4d^4\ 5s$	$^6D_{1/2}$	6.7589
42	Mo	Molybdenum	[Kr] $4d^5\ 5s$	$^7S_3$	7.0924
43	Tc	Technetium	[Kr] $4d^5\ 5s^2$	$^6S_{5/2}$	7.28
44	Ru	Ruthenium	[Kr] $4d^7\ 5s$	$^5F_5$	7.3605

Z		Element	Ground-state configuration	Ground level	Ionization energy (eV)
45	Rh	Rhodium	[Kr] $4d^8\ 5s$	$^4F_{9/2}$	7.4589
46	Pd	Palladium	[Kr] $4d^{10}$	$^1S_0$	8.3369
47	Ag	Silver	[Kr] $4d^{10}\ 5s$	$^2S_{1/2}$	7.5762
48	Cd	Cadmium	[Kr] $4d^{10}\ 5s^2$	$^1S_0$	8.9938
49	In	Indium	[Kr] $4d^{10}\ 5s^2\ 5p$	$^2P^o_{1/2}$	5.7864
50	Sn	Tin	[Kr] $4d^{10}\ 5s^2\ 5p^2$	$^3P_0$	7.3439
51	Sb	Antimony	[Kr] $4d^{10}\ 5s^2\ 5p^3$	$^4S^o_{3/2}$	8.6084
52	Te	Tellurium	[Kr] $4d^{10}\ 5s^2\ 5p^4$	$^3P_2$	9.0096
53	I	Iodine	[Kr] $4d^{10}\ 5s^2\ 5p^5$	$^2P^o_{3/2}$	10.4513
54	Xe	Xenon	[Kr] $4d^{10}\ 5s^2\ 5p^6$	$^1S_0$	12.1298
55	Cs	Cesium	[Xe] $6s$	$^2S_{1/2}$	3.8939
56	Ba	Barium	[Xe] $6s^2$	$^1S_0$	5.2117
57	La	Lanthanum	[Xe] $5d\ 6s^2$	$^2D_{3/2}$	5.5769
58	Ce	Cerium	[Xe] $4f\ 5d\ 6s^2$	$^1G^o_4$	5.5387
59	Pr	Praseodymium	[Xe] $4f^3\ 6s^2$	$^4I^o_{9/2}$	5.473
60	Nd	Neodymium	[Xe] $4f^4\ 6s^2$	$^5I_4$	5.5250
61	Pm	Promethium	[Xe] $4f^5\ 6s^2$	$^6H^o_{5/2}$	5.582
62	Sm	Samarium	[Xe] $4f^6\ 6s^2$	$^7F_0$	5.6437
63	Eu	Europium	[Xe] $4f^7\ 6s^2$	$^8S^o_{7/2}$	5.6704
64	Gd	Gadolinium	[Xe] $4f^7\ 5d\ 6s^2$	$^9D^o_2$	6.1498
65	Tb	Terbium	[Xe] $4f^9\ 6s^2$	$^6H^o_{15/2}$	5.8638
66	Dy	Dysprosium	[Xe] $4f^{10}\ 6s^2$	$^5I_8$	5.9389
67	Ho	Holmium	[Xe] $4f^{11}\ 6s^2$	$^4I^o_{15/2}$	6.0215
68	Er	Erbium	[Xe] $4f^{12}\ 6s^2$	$^3H_6$	6.1077
69	Tm	Thulium	[Xe] $4f^{13}\ 6s^2$	$^2F^o_{7/2}$	6.1843
70	Yb	Ytterbium	[Xe] $4f^{14}\ 6s^2$	$^1S_0$	6.2542
71	Lu	Lutetium	[Xe] $4f^{14}\ 5d\ 6s^2$	$^2D_{3/2}$	5.4259
72	Hf	Hafnium	[Xe] $4f^{14}\ 5d^2\ 6s^2$	$^3F_2$	6.8251
73	Ta	Tantalum	[Xe] $4f^{14}\ 5d^3\ 6s^2$	$^4F_{3/2}$	7.5496
74	W	Tungsten	[Xe] $4f^{14}\ 5d^4\ 6s^2$	$^5D_0$	7.8640
75	Re	Rhenium	[Xe] $4f^{14}\ 5d^5\ 6s^2$	$^6S_{5/2}$	7.8335
76	Os	Osmium	[Xe] $4f^{14}\ 5d^6\ 6s^2$	$^5D_4$	8.4382
77	Ir	Iridium	[Xe] $4f^{14}\ 5d^7\ 6s^2$	$^4F_{9/2}$	8.9670
78	Pt	Platinum	[Xe] $4f^{14}\ 5d^9\ 6s$	$^3D_3$	8.9588
79	Au	Gold	[Xe] $4f^{14}\ 5d^{10}\ 6s$	$^2S_{1/2}$	9.2255
80	Hg	Mercury	[Xe] $4f^{14}\ 5d^{10}\ 6s^2$	$^1S_0$	10.4375
81	Tl	Thallium	[Xe] $4f^{14}\ 5d^{10}\ 6s^2\ 6p$	$^2P^o_{1/2}$	6.1082
82	Pb	Lead	[Xe] $4f^{14}\ 5d^{10}\ 6s^2\ 6p^2$	$^3P_0$	7.4167
83	Bi	Bismuth	[Xe] $4f^{14}\ 5d^{10}\ 6s^2\ 6p^3$	$^4S^o_{3/2}$	7.2855
84	Po	Polonium	[Xe] $4f^{14}\ 5d^{10}\ 6s^2\ 6p^4$	$^3P_2$	8.414
85	At	Astatine	[Xe] $4f^{14}\ 5d^{10}\ 6s^2\ 6p^5$	$^2P^o_{3/2}$	
86	Rn	Radon	[Xe] $4f^{14}\ 5d^{10}\ 6s^2\ 6p^6$	$^1S_0$	10.7485
87	Fr	Francium	[Rn] $7s$	$^2S_{1/2}$	4.0727
88	Ra	Radium	[Rn] $7s^2$	$^1S_0$	5.2784
89	Ac	Actinium	[Rn] $6d\ 7s^2$	$^2D_{3/2}$	5.17
90	Th	Thorium	[Rn] $6d^2\ 7s^2$	$^3F_2$	6.3067
91	Pa	Protactinium	[Rn] $5f^2(^3H_4)\ 6d\ 7s^2$	$(4,3/2)_{11/2}$	5.89
92	U	Uranium	[Rn] $5f^3(^4I^o_{9/2})\ 6d\ 7s^2$	$(9/2,3/2)^o_6$	6.1941
93	Np	Neptunium	[Rn] $5f^4(^5I_4)\ 6d\ 7s^2$	$(4,3/2)_{11/2}$	6.2657
94	Pu	Plutonium	[Rn] $5f^6\ 7s^2$	$^7F_0$	6.0260
95	Am	Americium	[Rn] $5f^7\ 7s^2$	$^8S^o_{7/2}$	5.9738
96	Cm	Curium	[Rn] $5f^7\ 6d\ 7s^2$	$^9D^o_2$	5.9914
97	Bk	Berkelium	[Rn] $5f^9\ 7s^2$	$^6H^o_{15/2}$	6.1979
98	Cf	Californium	[Rn] $5f^{10}\ 7s^2$	$^5I_8$	6.2817
99	Es	Einsteinium	[Rn] $5f^{11}\ 7s^2$	$^4I^o_{15/2}$	6.42
100	Fm	Fermium	[Rn] $5f^{12}\ 7s^2$	$^3H_6$	6.50
101	Md	Mendelevium	[Rn] $5f^{13}\ 7s^2$	$^2F^o_{7/2}$	6.58
102	No	Nobelium	[Rn] $5f^{14}\ 7s^2$	$^1S_0$	6.65
103	Lr	Lawrencium	[Rn] $5f^{14}\ 7s^2\ 7p$?	$^2P^o_{1/2}$?	4.9?
104	Rf	Rutherfordium	[Rn] $5f^{14}\ 6d^2\ 7s^2$?	$^3F_2$?	6.0?

INTERNATIONAL TEMPERATURE SCALE OF 1990 (ITS-90)

B. W. Mangum

A new temperature scale, the International Temperature Scale of 1990 (ITS-90), was officially adopted by the Comité International des Poids et Mesures (CIPM), meeting 26—28 September 1989 at the Bureau International des Poids et Mesures (BIPM). The ITS-90 was recommended to the CIPM for its adoption following the completion of the final details of the new scale by the Comité Consultatif de Thermométrie (CCT), meeting 12—14 September 1989 at the BIPM in its 17th Session. The ITS-90 became the official international temperature scale on 1 January 1990. The ITS-90 supersedes the present scales, the International Practical Temperature Scale of 1968 (IPTS-68) and the 1976 Provisional 0.5 to 30 K Temperature Scale (EPT-76).

The ITS-90 extends upward from 0.65 K, and temperatures on this scale are in much better agreement with thermodynamic values that are those on the IPTS-68 and the EPT-76. The new scale has subranges and alternative definitions in certain ranges that greatly facilitate its use. Furthermore, its continuity, precision, and reproducibility throughout its ranges are much improved over that of the present scales. The replacement of the thermocouple with the platinum resistance thermometer at temperatures below 961.78°C resulted in the biggest improvement in reproducibility.

The ITS-90 is divided into four primary ranges:

1. Between 0.65 and 3.2 K, the ITS-90 is defined by the vapor pressure-temperature relation of ^{3}He, and between 1.25 and 2.1768 K (the λ point) and between 2.1768 and 5.0 K by the vapor pressure-temperature relations of ^{4}He. T_{90} is defined by the vapor pressure equations of the form:

$$T_{90} / \mathrm{K} = A_0 + \sum_{i=1}^{9} A_i \left[\left(\ln(p / \mathrm{Pa}) - B \right) / C \right]^i$$

   The values of the coefficients A_i, and of the constants A_o, B, and C of the equations are given below.
2. Between 3.0 and 24.5561 K, the ITS-90 is defined in terms of a ^{3}He or ^{4}He constant volume gas thermometer (CVGT). The thermometer is calibrated at three temperatures — at the triple point of neon (24.5561 K), at the triple point of equilibrium hydrogen (13.8033 K), and at a temperature between 3.0 and 5.0 K, the value of which is determined by using either ^{3}He or ^{4}He vapor pressure thermometry.
3. Between 13.8033 K (−259.3467°C) and 1234.93 K (961.78°C), the ITS-90 is defined in terms of the specified fixed points given below, by resistance ratios of platinum resistance thermometers obtained by calibration at specified sets of the fixed points, and by reference functions and deviation functions of resistance ratios which relate to T_{90} between the fixed points.
4. Above 1234.93 K, the ITS-90 is defined in terms of Planck's radiation law, using the freezing-point temperature of either silver, gold, or copper as the reference temperature.

Full details of the calibration procedures and reference functions for various subranges are given in:

The International Temperature Scale of 1990, *Metrologia,* 27, 3, 1990; errata in *Metrologia,* 27, 107, 1990.

Defining Fixed Points of the ITS-90

Material[a]	Equilibrium state[b]	Temperature T_{90} (K)	Temperature t_{90} (°C)
He	VP	3 to 5	−270.15 to −268.15
e-H_2	TP	13.8033	−259.3467
e-H_2 (or He)	VP (or CVGT)	≈17	≈ −256.15
e-H_2 (or He)	VP (or CVGT)	≈20.3	≈ −252.85
Ne[c]	TP	24.5561	−248.5939
O_2	TP	54.3584	−218.7916
Ar	TP	83.8058	−189.3442
Hg[c]	TP	234.3156	−38.8344
H_2O	TP	273.16	0.01
Ga[c]	MP	302.9146	29.7646
In[c]	FP	429.7485	156.5985
Sn	FP	505.078	231.928
Zn	FP	692.677	419.527
Al[c]	FP	933.473	660.323
Ag	FP	1234.93	961.78
Au	FP	1337.33	1064.18
Cu[c]	FP	1357.77	1084.62

[a] e-H_2 indicates equilibrium hydrogen, that is, hydrogen with the equilibrium distribution of its ortho and para states. Normal hydrogen at room temperature contains 25% para hydrogen and 75% ortho hydrogen.

[b] VP indicates vapor pressure point; CVGT indicates constant volume gas thermometer point; TP indicates triple point (equilibrium temperature at which the solid, liquid, and vapor phases coexist); FP indicates freezing point, and MP indicates melting point (the equilibrium temperatures at which the solid and liquid phases coexist under a pressure of 101 325 Pa, one standard atmosphere). The isotopic composition is that naturally occurring.

[c] Previously, these were secondary fixed points.

Values of Coefficients in the Vapor Pressure Equations for Helium

Coef. or constant	^{3}He 0.65—3.2 K	^{4}He 1.25—2.1768 K	^{4}He 2.1768—5.0 K
A_0	1.053 447	1.392 408	3.146 631
A_1	0.980 106	0.527 153	1.357 655
A_2	0.676 380	0.166 756	0.413 923
A_3	0.372 692	0.050 988	0.091 159
A_4	0.151 656	0.026 514	0.016 349
A_5	−0.002 263	0.001 975	0.001 826
A_6	0.006 596	−0.017 976	−0.004 325
A_7	0.088 966	0.005 409	−0.004 973
A_8	−0.004 770	0.013 259	0
A_9	−0.054 943	0	0
B	7.3	5.6	10.3
C	4.3	2.9	1.9

CONVERSION OF TEMPERATURES FROM THE 1948 AND 1968 SCALES TO ITS-90

This table gives temperature corrections from older scales to the current International Temperature Scale of 1990 (see the preceding table for details on ITS-90). The first part of the table may be used for converting Celsius temperatures in the range -180 to 4000°C from IPTS-68 or IPTS-48 to ITS-90. Within the accuracy of the corrections, the temperature in the first column may be identified with either t_{68}, t_{48}, or t_{90}. The second part of the table is designed for use at lower temperatures to convert values expressed in kelvins from EPT-76 or IPTS-68 to ITS-90.

The references give analytical equations for expressing these relations. Note that Reference 1 supersedes Reference 2 with respect to corrections in the 630 to 1064°C range.

References

1. Burns, G. W. et al., in *Temperature: Its Measurement and Control in Science and Industry*, Vol. 6, Schooley, J. F., Ed., American Institute of Physics, New York, 1993.
2. Goldberg, R. N. and Weir, R. D., *Pure and Appl. Chem.,* 1545, 1992.

t/°C	$t_{90}-t_{68}$	$t_{90}-t_{48}$	t/°C	$t_{90}-t_{68}$	$t_{90}-t_{48}$	t/°C	$t_{90}-t_{68}$	$t_{90}-t_{48}$	t/°C	$t_{90}-t_{68}$	$t_{90}-t_{48}$
−180	0.008	0.020	290	−0.039	0.032	760	0.04	0.60	2400	−1.00	3.2
−170	0.010	0.017	300	−0.039	0.034	770	0.05	0.63	2500	−1.07	3.4
−160	0.012	0.007	310	−0.039	0.035	780	0.05	0.66	2600	−1.15	3.7
−150	0.013	0.000	320	−0.039	0.036	790	0.05	0.69	2700	−1.24	3.8
−140	0.014	0.001	330	−0.040	0.036	800	0.05	0.72	2800	−1.32	4.0
−130	0.014	0.008	340	−0.040	0.037	810	0.05	0.75	2900	−1.41	4.2
−120	0.014	0.017	350	−0.041	0.036	820	0.04	0.76	3000	−1.50	4.4
−110	0.013	0.026	360	−0.042	0.035	830	0.04	0.79	3100	−1.59	4.6
−100	0.013	0.035	370	−0.043	0.034	840	0.03	0.81	3200	−1.69	4.8
−90	0.012	0.041	380	−0.045	0.032	850	0.02	0.83	3300	−1.78	5.1
−80	0.012	0.045	390	−0.046	0.030	860	0.01	0.85	3400	−1.89	5.3
−70	0.011	0.045	400	−0.048	0.028	870	0.00	0.87	3500	−1.99	5.5
−60	0.010	0.042	410	−0.051	0.024	880	−0.02	0.87	3600	−2.10	5.8
−50	0.009	0.038	420	−0.053	0.022	890	−0.03	0.89	3700	−2.21	6.0
−40	0.008	0.032	430	−0.056	0.019	900	−0.05	0.90	3800	−2.32	6.3
−30	0.006	0.024	440	−0.059	0.015	910	−0.06	0.92	3900	−2.43	6.6
−20	0.004	0.016	450	−0.062	0.012	920	−0.08	0.93	4000	−2.55	6.8
−10	0.002	0.008	460	−0.065	0.009	930	−0.10	0.94			
0	0.000	0.000	470	−0.068	0.007	940	−0.11	0.96	T/K	$T_{90}-T_{76}$	$T_{90}-T_{68}$
10	−0.002	−0.006	480	−0.072	0.004	950	−0.13	0.97	5	−0.0001	
20	−0.005	−0.012	490	−0.075	0.002	960	−0.15	0.97	6	−0.0002	
30	−0.007	−0.016	500	−0.079	0.000	970	−0.16	0.99	7	−0.0003	
40	−0.010	−0.020	510	−0.083	−0.001	980	−0.18	1.00	8	−0.0004	
50	−0.013	−0.023	520	−0.087	−0.002	990	−0.19	1.02	9	−0.0005	
60	−0.016	−0.026	530	−0.090	−0.001	1000	−0.20	1.04	10	−0.0006	
70	−0.018	−0.026	540	−0.094	0.000	1010	−0.22	1.05	11	−0.0007	
80	−0.021	−0.027	550	−0.098	0.002	1020	−0.23	1.07	12	−0.0008	
90	−0.024	−0.027	560	−0.101	0.007	1030	−0.23	1.10	13	−0.0010	
100	−0.026	−0.026	570	−0.105	0.011	1040	−0.24	1.12	14	−0.0011	−0.006
110	−0.028	−0.024	580	−0.108	0.018	1050	−0.25	1.14	15	−0.0013	−0.003
120	−0.030	−0.023	590	−0.112	0.025	1060	−0.25	1.17	16	−0.0014	−0.004
130	−0.032	−0.020	600	−0.115	0.035	1070	−0.25	1.19	17	−0.0016	−0.006
140	−0.034	−0.018	610	−0.118	0.047	1080	−0.26	1.20	18	−0.0018	−0.008
150	−0.036	−0.016	620	−0.122	0.060	1090	−0.26	1.20	19	−0.0020	−0.009
160	−0.037	−0.012	630	−0.125	0.075	1100	−0.26	1.2	20	−0.0022	−0.009
170	−0.038	−0.009	640	−0.11	0.12	1200	−0.30	1.4	21	−0.0025	−0.008
180	−0.039	−0.005	650	−0.10	0.15	1300	−0.35	1.5	22	−0.0027	−0.007
190	−0.039	−0.001	660	−0.09	0.19	1400	−0.39	1.6	23	−0.0030	−0.007
200	−0.040	0.003	670	−0.07	0.24	1500	−0.44	1.8	24	−0.0032	−0.006
210	−0.040	0.007	680	−0.05	0.29	1600	−0.49	1.9	25	−0.0035	−0.005
220	−0.040	0.011	690	−0.04	0.32	1700	−0.54	2.1	26	−0.0038	−0.004
230	−0.040	0.014	700	−0.02	0.37	1800	−0.60	2.2	27	−0.0041	−0.004
240	−0.040	0.018	710	−0.01	0.41	1900	−0.66	2.3	28		−0.005
250	−0.040	0.021	720	0.00	0.45	2000	−0.72	2.5	29		−0.006
260	−0.040	0.024	730	0.02	0.49	2100	−0.79	2.7	30		−0.006
270	−0.039	0.028	740	0.03	0.53	2200	−0.85	2.9	31		−0.007
280	−0.039	0.030	750	0.03	0.56	2300	−0.93	3.1	32		−0.008

T/K	$T_{90}-T_{76}$	$T_{90}-T_{68}$	T/K	$T_{90}-T_{76}$	$T_{90}-T_{68}$	T/K	$T_{90}-T_{76}$	$T_{90}-T_{68}$	T/K	$T_{90}-T_{76}$	$T_{90}-T_{68}$
33		–0.008	57		0.000	81		0.008	150		0.014
34		–0.008	58		0.001	82		0.008	160		0.014
35		–0.007	59		0.002	83		0.008	170		0.013
36		–0.007	60		0.003	84		0.008	180		0.012
37		–0.007	61		0.003	85		0.008	190		0.012
38		–0.006	62		0.004	86		0.008	200		0.011
39		–0.006	63		0.004	87		0.008	210		0.010
40		–0.006	64		0.005	88		0.008	220		0.009
41		–0.006	65		0.005	89		0.008	230		0.008
42		–0.006	66		0.006	90		0.008	240		0.007
43		–0.006	67		0.006	91		0.008	250		0.005
44		–0.006	68		0.007	92		0.008	260		0.003
45		–0.007	69		0.007	93		0.008	270		0.001
46		–0.007	70		0.007	94		0.008	273.16		0.000
47		–0.007	71		0.007	95		0.008	300		–0.006
48		–0.006	72		0.007	96		0.008	400		–0.031
49		–0.006	73		0.007	97		0.009	500		–0.040
50		–0.006	74		0.007	98		0.009	600		–0.040
51		–0.005	75		0.008	99		0.009	700		–0.055
52		–0.005	76		0.008	100		0.009	800		–0.089
53		–0.004	77		0.008	110		0.011	900		–0.124
54		–0.003	78		0.008	120		0.013			
55		–0.002	79		0.008	130		0.014			
56		–0.001	80		0.008	140		0.014			

INTERNATIONAL SYSTEM OF UNITS (SI)

The International System of Units, abbreviated as SI (from the French name *Le Système International d'Unités*), was established in 1960 by the 11th General Conference on Weights and Measures (CGPM) as the modern metric system of measurement. The core of the SI is the seven base units for the physical quantities length, mass, time, electric current, thermodynamic temperature, amount of substance, and luminous intensity. These base units are:

	SI base unit	
Base quantity	**Name**	**Symbol**
length	meter	m
mass	kilogram	kg
time	second	s
electric current	ampere	A
thermodynamic temperature	kelvin	K
amount of substance	mole	mol
luminous intensity	candela	cd

The SI base units are defined as follows:

meter: The meter is the length of the path travelled by light in vacuum during a time interval of 1/299 792 458 of a second.

kilogram: The kilogram is the unit of mass; it is equal to the mass of the international prototype of the kilogram.

second: The second is the duration of 9 192 631 770 periods of the radiation corresponding to the transition between the two hyperfine levels of the ground state of the cesium 133 atom.

ampere: The ampere is that constant current which, if maintained in two straight parallel conductors of infinite length, of negligible circular cross-section, and placed 1 meter apart in vacuum, would produce between these conductors a force equal to $2 \cdot 10^{-7}$ newton per meter of length.

kelvin: The kelvin, unit of thermodynamic temperature, is the fraction 1/273.16 of the thermodynamic temperature of the triple point of water.

mole: The mole is the amount of substance of a system which contains as many elementary entities as there are atoms in 0.012 kilogram of carbon 12. When the mole is used, the elementary entities must be specified and may be atoms, molecules, ions, electrons, other particles, or specified groups of such particles.

candela: The candela is the luminous intensity, in a given direction, of a source that emits monochromatic radiation of frequency $540 \cdot 10^{12}$ hertz and that has a radiant intensity in that direction of 1/683 watt per steradian.

SI derived units

Derived units are units which may be expressed in terms of base units by means of the mathematical symbols of multiplication and division (and, in the case of °C, subtraction). Certain derived units have been given special names and symbols, and these special names and symbols may themselves be used in combination with those for base and other derived units to express the units of other quantities. The next table lists some examples of derived units expressed directly in terms of base units:

	SI derived unit	
Physical quantity	**Name**	**Symbol**
area	square meter	m^2
volume	cubic meter	m^3
speed, velocity	meter per second	m/s
acceleration	meter per second squared	m/s^2
wave number	reciprocal meter	m^{-1}
density, mass density	kilogram per cubic meter	kg/m^3
specific volume	cubic meter per kilogram	m^3/kg
current density	ampere per square meter	A/m^2
magnetic field strength	ampere per meter	A/m
concentration (of amount of substance)	mole per cubic meter	mol/m^3
luminance	candela per square meter	cd/m^2
refractive index	(the number) one	1[(a)]

[(a)] The symbol "1" is generally omitted in combination with a numerical value.

For convenience, certain derived units, which are listed in the next table, have been given special names and symbols. These names and symbols may themselves be used to express other derived units. The special names and symbols are a compact form for the expression of units that are used frequently. The final column shows how the SI units concerned may be expressed in terms of SI base units. In this column, factors such as m^0, kg^0 ..., which are all equal to 1, are not shown explicitly.

			SI derived unit expressed in terms of:	
Physical quantity	**Name**	**Symbol**	**Other SI units**	**SI base units**
plane angle	radian[(a)]	rad	$m \cdot m^{-1} = 1$[(b)]	
solid angle	steradian[(a)]	sr[(c)]	$m^2 \cdot m^{-2} = 1$[(b)]	
frequency	hertz	Hz	s^{-1}	
force	newton	N	$m \cdot kg \cdot s^{-2}$	
pressure, stress	pascal	Pa	N/m^2	$m^{-1} \cdot kg \cdot s^{-2}$
energy, work, quantity of heat	joule	J	$N \cdot m$	$m^2 \cdot kg \cdot s^{-2}$
power, radiant flux	watt	W	J/s	$m^2 \cdot kg \cdot s^{-3}$
electric charge, quantity of electricity	coulomb	C	$s \cdot A$	
electric potential difference, electromotive force	volt	V	W/A	$m^2 \cdot kg \cdot s^{-3} \cdot A^{-1}$
capacitance	farad	F	C/V	$m^{-2} \cdot kg^{-1} \cdot s^4 \cdot A^2$
electric resistance	ohm	Ω	V/A	$m^2 \cdot kg \cdot s^{-3} \cdot A^{-2}$
electric conductance	siemens	S	A/V	$m^{-2} \cdot kg^{-1} \cdot s^3 \cdot A^2$
magnetic flux	weber	Wb	$V \cdot s$	$m^2 \cdot kg \cdot s^{-2} \cdot A^{-1}$

magnetic flux density	tesla	T	Wb/m²	kg · s⁻² · A⁻¹
inductance	henry	H	Wb/A	m² · kg · s⁻² · A⁻²
Celsius temperature	degree Celsius[d]	°C		K
luminous flux	lumen	lm	cd · sr[c]	m² · m⁻² · cd = cd
illuminance	lux	lx	lm/m²	m² · m⁻⁴ · cd = m⁻² · cd
activity (of a radionuclide)	becquerel	Bq		s⁻¹
absorbed dose, specific energy (imparted), kerma	gray	Gy	J/kg	m² · s⁻²
dose equivalent, ambient dose equivalent, directional dose equivalent, personal dose equivalent, organ equivalent dose	sievert	Sv	J/kg	m² · s⁻²
catalytic activity	katal	kat		s⁻¹ · mol

[a] The radian and steradian may be used with advantage in expressions for derived units to distinguish between quantities of different nature but the same dimension. Some examples of their use in forming derived units are given in the next table.
[b] In practice, the symbols rad and sr are used where appropriate, but the derived unit "1" is generally omitted in combination with a numerical value.
[c] In photometry, the name steradian and the symbol sr are usually retained in expressions for units.
[d] It is common practice to express a thermodynamic temperature, symbol T, in terms of its difference from the reference temperature T_0 = 273.15 K. The numerical value of a Celsius temperature t expressed in degrees Celsius is given by $t/°C = T/K-273.15$. The unit °C may be used in combination with SI prefixes, e.g., millidegree Celsius, m°C. Note that there should never be a space between the ° sign and the letter C, and that the symbol for kelvin is K, not °K.

The SI derived units with special names may be used in combinations to provide a convenient way to express more complex physical quantities. Examples are given in the next table:

	SI derived unit		
Physical Quantity	**Name**	**Symbol**	**As SI base units**
dynamic viscosity	pascal second	Pa · s	m⁻¹ · kg · s⁻¹
moment of force	newton meter	N · m	m² · kg · s⁻²
surface tension	newton per meter	N/m	kg · s⁻²
angular velocity	radian per second	rad/s	m · m⁻¹ · s⁻¹ = s⁻¹
angular acceleration	radian per second squared	rad/s²	m · m⁻¹ · s⁻² = s⁻²
heat flux density, irradiance	watt per square meter	W/m²	kg · s⁻³
heat capacity, entropy	joule per kelvin	J/K	m⁻³ · kg · s⁻² · K⁻¹
specific heat capacity, specific entropy	joule per kilogram kelvin	J/(kg · K)	m² · s⁻² · K⁻¹
specific energy	joule per kilogram	J/kg	m² · s⁻²
thermal conductivity	watt per meter kelvin	W/(m · K)	m · kg · s⁻³ · K⁻¹
energy density	joule per cubic meter	J/m³	m⁻¹ · kg · s⁻²
electric field strength	volt per meter	V/m	m · kg · s⁻³· A⁻¹
electric charge density	coulomb per cubic meter	C/m³	m⁻³ · s · A
electric flux density	coulomb per square meter	C/m²	m⁻² · s · A
permittivity	farad per meter	F/m	m⁻³ · kg⁻¹ · s⁴ · A²
permeability	henry per meter	H/m	m · kg · s⁻² · A⁻²
molar energy	joule per mole	J/mol	m² · kg · s⁻² · mol⁻¹
molar entropy, molar heat capacity	joule per mole kelvin	J/(mol · K)	m² · kg · s⁻² · K⁻¹ · mol⁻¹
exposure (x and γ rays)	coulomb per kilogram	C/kg	kg⁻¹ · s · A
absorbed dose rate	gray per second	Gy/s	m² · s⁻³
radiant intensity	watt per steradian	W/sr	m⁴ · m⁻²· kg· s⁻³ = m² · kg· s⁻³
radiance	watt per square meter steradian	W/(m² · sr)	m² · m⁻² · kg · s⁻³ = kg · s⁻³
catalytic (activity) concentration	katal per cubic meter	kat/m³	m⁻³ · s⁻¹ · mol

In practice, with certain quantities preference is given to the use of certain special unit names, or combinations of unit names, in order to facilitate the distinction between different quantities having the same dimension. For example, the SI unit of frequency is designated the hertz, rather than the reciprocal second, and the SI unit of angular velocity is designated the radian per second rather than the reciprocal second (in this case retaining the word radian emphasizes that angular velocity is equal to 2π times the rotational frequency). Similarly the SI unit of moment of force is designated the newton meter rather than the joule.

In the field of ionizing radiation, the SI unit of activity is designated the becquerel rather than the reciprocal second, and the SI units of absorbed dose and dose equivalent the gray and sievert, respectively, rather than the joule per kilogram. In the field of catalysis, the SI unit of catalytic activity is designated the katal rather than the mole per second. The special names becquerel, gray, sievert, and katal were specifically introduced because of the dangers to human health which might arise from mistakes involving the units reciprocal second, joule per kilogram and mole per second.

Units for dimensionless quantities, quantities of dimension one

Certain quantities are defined as the ratios of two quantities of the same kind, and thus have a dimension which may be expressed by the number one. The unit of such quantities is necessarily a derived unit coherent with the other units of the SI and, since it is formed as the ratio of two identical SI units, the unit also may be expressed by the number one. Thus the SI unit of all quantities having the dimensional product one is the number one. Examples of such quantities are refractive index, relative permeability, and friction factor. Other quantities having the unit 1 include "characteristic numbers" like the Prandtl number and numbers which represent a count, such as a number of molecules, degeneracy (number of energy levels), and partition function in statistical thermodynamics. All of these quantities are described as being dimensionless, or of dimension one, and have the coherent SI unit 1. Their values are simply expressed as numbers and, in general, the unit 1 is not explicitly shown. In a few cases, however, a special name is given to this unit, mainly to avoid confusion between some compound derived units. This is the case for the radian, steradian and neper.

SI prefixes

The following prefixes have been approved by the CGPM for use with SI units. Only one prefix may be used before a unit. Thus 10^{-12} farad should be designated pF, not μμF.

Factor	Name	Symbol	Factor	Name	Symbol
10^{24}	yotta	Y	10^{-1}	deci	d
10^{21}	zetta	Z	10^{-2}	centi	c
10^{18}	exa	E	10^{-3}	milli	m
10^{15}	peta	P	10^{-6}	micro	μ
10^{12}	tera	T	10^{-9}	nano	n
10^{9}	giga	G	10^{-12}	pico	p
10^{6}	mega	M	10^{-15}	femto	f
10^{3}	kilo	k	10^{-18}	atto	a
10^{2}	hecto	h	10^{-21}	zepto	z
10^{1}	deka	da	10^{-24}	yocto	y

The kilogram

Among the base units of the International System, the unit of mass is the only one whose name, for historical reasons, contains a prefix. Names and symbols for decimal multiples and submultiples of the unit of mass are formed by attaching prefix names to the unit name "gram" and prefix symbols to the unit symbol "g".

Example : 10^{-6} kg = 1 mg (1 milligram) *but not* 1 μkg (1 microkilogram).

Units used with the SI

Many units that are not part of the SI are important and widely used in everyday life. The CGPM has adopted a classification of non-SI units: (1) units accepted for use with the SI (such as the traditional units of time and of angle); (2) units accepted for use with the SI whose values are obtained experimentally; and (3) other units currently accepted for use with the SI to satisfy the needs of special interests.

(1) Non-SI units accepted for use with the International System

Name	Symbol	Value in SI units
minute	min	1 min = 60 s
hour	h	1 h= 60 min = 3600 s
day	d	1 d = 24 h = 86 400 s
degree	°	1° = (π/180) rad
minute	’	1’ = (1/60)° = (π/10 800) rad
second	”	1” = (1/60)’ = (π/648 000) rad
liter	l, L	1L= 1 dm^3= 10^{-3} m^3
metric ton	t	1 t = 10^3 kg
neper[a]	Np	1 Np = 1
bel[b]	B	1 B = (1/2) ln 10 Np

[a] The neper is used to express values of such logarithmic quantities as field level, power level, sound pressure level, and logarithmic decrement. Natural logarithms are used to obtain the numerical values of quantities expressed in nepers. The neper is coherent with the SI, but is not yet adopted by the CGPM as an SI unit. In using the neper, it is important to specify the quantity.

[b] The bel is used to express values of such logarithmic quantities as field level, power level, sound-pressure level, and attenuation. Logarithms to base ten are used to obtain the numerical values of quantities expressed in bels. The submultiple decibel, dB, is commonly used.

(2) Non-SI units accepted for use with the International system, whose values in SI units are obtained experimentally

Name	Symbol	Value in SI Units
electronvolt[b]	eV	1 eV = 1.602 176 53(14) ·10^{-19} J[a]
dalton[c]	Da	1 Da = 1.660 538 86(28) · 10^{-27} kg[a]
unified atomic mass unit[c]	u	1 u = 1 Da
astronomical unit[d]	ua	1 ua = 1.495 978 706 91(06) · 10^{11} m[a]

[a] For the electronvolt and the dalton (unified atomic mass unit), values are quoted from the 2002 CODATA set of the Fundamental Physical Constants (p. 1-1 of this Handbook). The value given for the astronomical unit is quoted from the IERS Conventions 2003 (D.D. McCarthy and G. Petit, eds., IERS Technical Note 32, Frankfurt am Main: Verlag des Bundesamts für Kartographie und Geodäsie, 200). The value of ua in meters comes from the JPL ephemerides DE403 (Standish E.M. 1995, "Report of the IAU WGAS Sub-Group on Numerical Standards", in "Highlights of Astronomy", Appenlzer ed., pp 180-184, Kluwer Academic Publishers, Dordrecht). It has been determined in "TDB" units using Barycentric Dynamical Time TDB as a time coordinate for the barycentric system.

[b] The electronvolt is the kinetic energy acquired by an electron in passing through a potential difference of 1 V in vacuum.

[c] The Dalton and unified atomic mass unit are alternative names for the same unit, equal to 1/12 of the mass of an unbound atom of the nuclide ^{12}C, at rest and in its ground state. The dalton may be combined with SI prefixes to express the masses of large molecules in kilodalton, kDa, or megadalton, MDa.

[d] The astronomical unit is a unit of length approximately equal to the mean Earth-Sun distance. It is the radius of an unperturbed circular Newtonian orbit about the Sun of a particle having infinitesimal mass, moving with a mean motion of 0.017 202 098 95 radians/day (known as the Gaussian constant).

(3) Other non-SI units currently accepted for use with the International System

Name	Symbol	Value in SI Units
nautical mile		1 nautical mile = 1852 m
knot		1 nautical mile per hour = (1852/3600) m/s
are		1 a = 1 dam^2 = 10^2 m^2
hectare	ha	1 ha = 1 hm^2 = 10^4 m^2
bar	bar	1 bar = 0.1 MPa = 100 kPa = 10^5 Pa
ångström	Å	1 Å = 0.1 nm = 10^{-10} m
barn	b	1 b = 100 fm^2 = 10^{-28} m^2

Other non-SI units

The SI does not encourage the use of cgs units, but these are frequently found in old scientific texts. The following table gives the relation of some common cgs units to SI units.

Name	Symbol	Value in SI units
erg	erg	1 erg = 10^{-7} J
dyne	dyn	1 dyn = 10^{-5} N
poise	P	1P = 1dyn· s/cm^2 = 0.1 Pa·· s
stokes	St	1 St = 1 cm^2/s = 10^{-4} m^2/s
gauss	G	1G ≙ 10^{-4} T
oersted	Oe	1 Oe ≙ (1000/4π) A/m
maxwell	Mx	1Mx ≙ 10^{-8} Wb
stilb	sb	1 sb = 1 cd/cm^2 = 10^4 cd/m^2
phot	ph	1 ph = 10^4 lx
gal	Gal	1 Gal = 1 cm/s^2 = 10^{-2} m/s^2

Note: The symbol ≙ should be read as "corresponds to"; these units cannot strictly be equated because of the different dimensions of the electromagnetic cgs and the SI.

Examples of other non-SI units found in the older literature and their relation to the SI are given below. Use of these units in current texts is discouraged.

Name	Symbol	Value in SI units
curie	Ci	$1\ \text{Ci} = 3.7 \cdot 10^{10}\ \text{Bq}$
roentgen	R	$1\ \text{R} = 2.58 \cdot 10^{-4}\ \text{C/kg}$
rad	rad	$1\ \text{rad} = 1\ \text{cGy} = 10^{-2}\ \text{Gy}$
rem	rem	$1\ \text{rem} = 1\ \text{cSv} = 10^{-2}\ \text{Sv}$
X unit		$1\ \text{X unit} \approx 1.002 \cdot 10^{-4}\ \text{nm}$
gamma	γ	$1\ \gamma = 1\ \text{nT} = 10^{-9}\ \text{T}$
jansky	Jy	$1\text{Jy} = 10^{-26}\ \text{W} \cdot \text{m}^{-2} \cdot \text{Hz}^{-1}$
fermi		$1\ \text{fermi} = 1\ \text{fm} = 10^{-15}\ \text{m}$
metric carat		$1\ \text{metric carat} = 200\ \text{mg} = 2 \cdot 10^{-4}\ \text{kg}$
torr	Torr	$1\ \text{Torr} = (101325/760)\ \text{Pa}$
standard atmosphere	atm	$1\ \text{atm} = 101325\ \text{Pa}$
calorie[a]	cal	$1\ \text{cal} = 4.184\ \text{J}$
micron	μ	$1\ \mu = 1\ \mu\text{m} = 10^{-6}\ \text{m}$

[a] Several types of calorie have been used; the value given here is the so-called "thermochemical calorie".

References

1. Taylor, B. N., *The International System of Units (SI)*, NIST Special Publication 330, National Institute of Standards and Technology, Gaithersburg, MD, 2001.
2. Bureau International des Poids et Mesures, *Le Système International d'Unités (SI)*, 7th French and English Edition, BIPM, Sèvres, France, 1998; 8th Edition to be published 2006.
3. Taylor, B. N., *Guide for the Use of the International System of Units (SI)*, NIST Special Publication 811, National Institute of Standards and Technology, Gaithersburg, MD, 1995.
4. NIST Physical Reference Data web site, <http://physics.nist.gov/cuu/Units/index.html>, October 2004.

CONVERSION FACTORS

The following table gives conversion factors from various units of measure to SI units. It is reproduced from NIST Special Publication 811, *Guide for the Use of the International System of Units (SI)*. The table gives the factor by which a quantity expressed in a non-SI unit should be multiplied in order to calculate its value in the SI. The SI values are expressed in terms of the base, supplementary, and derived units of SI in order to provide a coherent presentation of the conversion factors and facilitate computations (see the table "International System of Units" in this Section). If desired, powers of ten can be avoided by using SI Prefixes and shifting the decimal point if necessary.

Conversion from a non-SI unit to a different non-SI unit may be carried out by using this table in two stages, e.g.,

$$1 \text{ cal}_{th} = 4.184 \text{ J}$$

$$1 \text{ Btu}_{IT} = 1.055056 \text{ E+03 J}$$

Thus,

$$1 \text{ Btu}_{IT} = (1.055056 \text{ E+03} \div 4.184) \text{ cal}_{th} = 252.164 \text{ cal}_{th}$$

Conversion factors are presented for ready adaptation to computer readout and electronic data transmission. The factors are written as a number equal to or greater than one and less than ten with six or fewer decimal places. This number is followed by the letter E (for exponent), a plus or a minus sign, and two digits which indicate the power of 10 by which the number must be multiplied to obtain the correct value. For example:

$$3.523\ 907 \text{ E-02 is } 3.523\ 907 \times 10^{-2}$$

or

$$0.035\ 239\ 07$$

Similarly:

$$3.386\ 389 \text{ E+03 is } 3.386\ 389 \times 10^{3}$$

or

$$3\ 386.389$$

A factor in boldface is exact; i.e., all subsequent digits are zero. All other conversion factors have been rounded to the figures given in accordance with accepted practice. Where less than six digits after the decimal point are shown, more precision is not warranted.

It is often desirable to round a number obtained from a conversion of units in order to retain information on the precision of the value. The following rounding rules may be followed:

1. If the digits to be discarded begin with a digit less than 5, the digit preceding the first discarded digit is not changed.

   Example: 6.974 951 5 rounded to 3 digits is 6.97

2. If the digits to be discarded begin with a digit greater than 5, the digit preceding the first discarded digit is increased by one.

   Example: 6.974 951 5 rounded to 4 digits is 6.975

3. If the digits to be discarded begin with a 5 and at least one of the following digits is greater than 0, the digit preceding the 5 is increased by 1.

   Example: 6.974 851 rounded to 5 digits is 6.974 9

4. If the digits to be discarded begin with a 5 and all of the following digits are 0, the digit preceding the 5 is unchanged if it is even and increased by one if it is odd. (Note that this means that the final digit is always even.)

   Examples:
   6.974 951 5 rounded to 7 digits is 6.974 952
   6.974 950 5 rounded to 7 digits is 6.974 950

Reference

Taylor, B. N., *Guide for the Use of the International System of Units (SI)*, NIST Special Publication 811, 1995 Edition, Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402, 1995.

Factors in **boldface** are exact

To convert from	to	Multiply by	
abampere	ampere (A)	**1.0**	**E+01**
abcoulomb	coulomb (C)	**1.0**	**E+01**
abfarad	farad (F)	**1.0**	**E+09**
abhenry	henry (H)	**1.0**	**E–09**
abmho	siemens (S)	**1.0**	**E+09**
abohm	ohm (Ω)	**1.0**	**E–09**
abvolt	volt (V)	**1.0**	**E–08**
acceleration of free fall, standard (g_n)	meter per second squared (m/s^2)	**9.806 65**	**E+00**
acre (based on U.S. survey foot)[9]	square meter (m^2)	4.046 873	E+03
acre foot (based on U.S. survey foot)[9]	cubic meter (m^3)	1.233 489	E+03
ampere hour (A · h)	coulomb (C)	**3.6**	**E+03**
ångström (Å)	meter (m)	**1.0**	**E–10**
ångström (Å)	nanometer (nm)	**1.0**	**E–01**
are (a)	square meter (m^2)	**1.0**	**E+02**
astronomical unit (ua or AU)	meter (m)	1.495 979	E+11
atmosphere, standard (atm)	pascal (Pa)	**1.013 25**	**E+05**
atmosphere, standard (atm)	kilopascal (kPa)	**1.013 25**	**E+02**
atmosphere, technical (at)[10]	pascal (Pa)	**9.806 65**	**E+04**
atmosphere, technical (at)[10]	kilopascal (kPa)	**9.806 65**	**E+01**

[9] The U.S. survey foot equals (1200/3937) m. 1 international foot = 0.999998 survey foot.

[10] One technical atmosphere equals one kilogram-force per square centimeter (1 at = 1 kgf/cm^2).

To convert from	to	Multiply by	
bar (bar)	pascal (Pa)	**1.0**	**E+05**
bar (bar)	kilopascal (kPa)	**1.0**	**E+02**
barn (b)	square meter (m^2)	**1.0**	**E–28**
barrel [for petroleum, 42 gallons (U.S.)](bbl)	cubic meter (m^3)	1.589 873	E–01
barrel [for petroleum, 42 gallons (U.S.)](bbl)	liter (L)	1.589 873	E+02
biot (Bi)	ampere (A)	**1.0**	**E+01**
British thermal unit$_{IT}$ (Btu_{IT})[11]	joule (J)	1.055 056	E+03
British thermal unit$_{th}$ (Btu_{th})[11]	joule (J)	1.054 350	E+03
British thermal unit (mean) (Btu)	joule (J)	1.055 87	E+03
British thermal unit (39 °F) (Btu)	joule (J)	1.059 67	E+03
British thermal unit (59 °F) (Btu)	joule (J)	1.054 80	E+03
British thermal unit (60 °F) (Btu)	joule (J)	1.054 68	E+03
British thermal unit$_{IT}$ foot per hour square foot degree Fahrenheit [$Btu_{IT} \cdot ft/(h \cdot ft^2 \cdot °F)$]	watt per meter kelvin [W/(m · K)]	1.730 735	E+00
British thermal unit$_{th}$ foot per hour square foot degree Fahrenheit [$Btu_{th} \cdot ft/(h \cdot ft^2 \cdot °F)$]	watt per meter kelvin [W/(m · K)]	1.729 577	E+00
British thermal unit$_{IT}$ inch per hour square foot degree Fahrenheit [$Btu_{IT} \cdot in/(h \cdot ft^2 \cdot °F)$]	watt per meter kelvin [W/(m · K)]	1.442 279	E–01
British thermal unit$_{th}$ inch per hour square foot degree Fahrenheit [$Btu_{th} \cdot in/(h \cdot ft^2 \cdot °F)$]	watt per meter kelvin [W/(m · K)]	1.441 314	E–01
British thermal unit$_{IT}$ inch per second square foot degree Fahrenheit [$Btu_{IT} \cdot in/(s \cdot ft^2 \cdot °F)$]	watt per meter kelvin [W/(m · K)]	5.192 204	E+02
British thermal unit$_{th}$ inch per second square foot degree Fahrenheit [$Btu_{th} \cdot in/(s \cdot ft^2 \cdot °F)$]	watt per meter kelvin [W/(m · K)]	5.188 732	E+02
British thermal unit$_{IT}$ per cubic foot (Btu_{IT}/ft^3)	joule per cubic meter (J/m^3)	3.725 895	E+04
British thermal unit$_{th}$ per cubic foot (Btu_{th}/ft^3)	joule per cubic meter (J/m^3)	3.723 403	E+04
British thermal unit$_{IT}$ per degree Fahrenheit (Btu_{IT}/ °F)	joule per kelvin (J/ k)	1.899 101	E+03
British thermal unit$_{th}$ per degree Fahrenheit (Btu_{th}/ °F)	joule per kelvin (J/ k)	1.897 830	E+03
British thermal unit$_{IT}$ per degree Rankine (Btu_{IT}/ °R)	joule per kelvin (J/ k)	1.899 101	E+03
British thermal unit$_{th}$ per degree Rankine (Btu_{th}/ °R)	joule per kelvin (J/ k)	1.897 830	E+03
British thermal unit$_{IT}$ per hour (Btu_{IT}/h)	watt (W)	2.930 711	E–01
British thermal unit$_{th}$ per hour (Btu_{th}/h)	watt (W)	2.928 751	E–01
British thermal unit$_{IT}$ per hour square foot degree Fahrenheit [$Btu_{IT}/(h \cdot ft^2 \cdot °F)$]	watt per square meter kelvin [W/(m² · K)]	5.678 263	E+00
British thermal unit$_{th}$ per hour square foot degree Fahrenheit [$Btu_{th}/(h \cdot ft^2 \cdot °F)$]	watt per square meter kelvin [W/(m² · K)]	5.674 466	E+00
British thermal unit$_{th}$ per minute (Btu_{th}/min)	watt (W)	1.757 250	E+01
British thermal unit$_{IT}$ per pound (Btu_{IT}/lb)	joule per kilogram (J/kg)	**2.326**	**E+03**
British thermal unit$_{th}$ per pound (Btu_{th}/lb)	joule per kilogram (J/kg)	2.324 444	E+03
British thermal unit$_{IT}$ per pound degree Fahrenheit [$Btu_{IT}/(lb \cdot °F)$]	joule per kilogram kelvin (J/(kg · K)]	**4.1868**	**E+03**
British thermal unit$_{th}$ per pound degree Fahrenheit [$Btu_{th}/(lb \cdot °F)$]	joule per kilogram kelvin [J/(kg · K)]	**4.184**	**E+03**
British thermal unit$_{IT}$ per pound degree Rankine [$Btu_{IT}/(lb \cdot °R)$]	joule per kilogram kelvin [J/(kg · K)]	**4.1868**	**E+03**
British thermal unit$_{th}$ per pound degree Rankine [$Btu_{th}/(lb \cdot °R)$]	joule per kilogram kelvin [J/(kg · K)]	**4.184**	**E+03**
British thermal unit$_{IT}$ per second (Btu_{IT}/s)	watt (W)	1.055 056	E+03
British thermal unit$_{th}$ per second (Btu_{th}/s)	watt (W)	1.054 350	E+03

[11] The Fifth International Conference on the Properties of Steam (London, July 1956) defined the International Table calorie as 4.1868 J. Therefore the exact conversion factor for the International Table Btu is 1.055 055 852 62 kJ. Note that the notation for International Table used in this listing is subscript "IT". Similarily, the notation for thermochemical is subscript "th." Further, the thermochemical Btu, Btu_{th}, is based on the thermochemical calorie, cal_{th}, where cal_{th} = 4.184 J exactly.

To convert from	to	Multiply by	
British thermal unit$_{IT}$ per second square foot degree Fahrenheit [Btu$_{IT}$/(s · ft^2 · °F)]	watt per square meter kelvin [W/(m^2 · K)]	2.044 175	E+04
British thermal unit$_{th}$ per second square foot degree Fahrenheit [Btu$_{th}$/(s · ft^2 · °F)]	watt per square meter kelvin [W/(m^2 · K)]	2.042 808	E+04
British thermal unit$_{IT}$ per square foot (Btu$_{IT}$/ft^2)	joule per square meter (J/m^2)	1.135 653	E+04
British thermal unit$_{th}$ per square foot (Btu$_{th}$/ft^2)	joule per square meter (J/m^2)	1.134 893	E+04
British thermal unit$_{IT}$ per square foot hour [(Btu$_{IT}$/(ft^2 · h)]	watt per square meter (W/m^2)	3.154 591	E+00
British thermal unit$_{th}$ per square foot hour [Btu$_{th}$/(ft^2 · h)]	watt per square meter (W/m^2)	3.152 481	E+00
British thermal unit$_{th}$ per square foot minute [Btu$_{th}$/(ft^2 · min)]	watt per square meter (W/m^2)	1.891 489	E+02
British thermal unit$_{IT}$ per square foot second [(Btu$_{IT}$/(ft^2 · s)]	watt per square meter (W/m^2)	1.135 653	E+04
British thermal unit$_{th}$ per square foot second [Btu$_{th}$/(ft^2 · s)]	watt per square meter (W/m^2)	1.134 893	E+04
British thermal unit$_{th}$ per square inch second [Btu$_{th}$/(in^2 · s)]	watt per square meter (W/m^2)	1.634 246	E+06
bushel (U.S.) (bu)	cubic meter (m^3)	3.523 907	E–02
bushel (U.S.) (bu)	liter (L)	3.523 907	E+01
calorie$_{IT}$ (cal$_{IT}$)[11]	joule (J)	**4.1868**	**E+00**
calorie$_{th}$ (cal$_{th}$)[11]	joule (J)	**4.184**	**E+00**
calorie (cal) (mean)	joule (J)	4.190 02	E+00
calorie (15 °C) (cal$_{15}$)	joule (J)	4.185 80	E+00
calorie (20 °C) (cal$_{20}$)	joule (J)	4.181 90	E+00
calorie$_{IT}$, kilogram (nutrition)[12]	joule (J)	**4.1868**	**E+03**
calorie$_{th}$, kilogram (nutrition)[12]	joule (J)	**4.184**	**E+03**
calorie (mean), kilogram (nutrition)[12]	joule (J)	4.190 02	E+03
calorie$_{th}$ per centimeter second degree Celsius [cal$_{th}$/(cm · s · °C)]	watt per meter kelvin [W/(m · K)]	**4.184**	**E+02**
calorie$_{IT}$ per gram (cal$_{IT}$/g)	joule per kilogram (J/kg)	**4.1868**	**E+03**
calorie$_{th}$ per gram (cal$_{th}$/g)	joule per kilogram (J/kg)	**4.184**	**E+03**
calorie$_{IT}$ per gram degree Celsius [cal$_{IT}$/(g · °C)]	joule per kilogram kelvin [J/(kg · K)]	**4.1868**	**E+03**
calorie$_{th}$ per gram degree Celsius [cal$_{th}$/(g · °C)]	joule per kilogram kelvin [J/(kg · K)]	**4.184**	**E+03**
calorie$_{IT}$ per gram kelvin [cal$_{IT}$/(g · K)]	joule per kilogram kelvin [J /(kg · K)]	**4.1868**	**E+03**
calorie$_{th}$ per gram kelvin [cal$_{th}$/ (g · K)]	joule per kilogram kelvin [J /(kg · K)]	**4.184**	**E+03**
calorie$_{th}$ per minute (cal$_{th}$/min)	watt (W)	6.973 333	E–02
calorie$_{th}$ per second (cal$_{th}$/s)	watt (W)	**4.184**	**E+00**
calorie$_{th}$ per square centimeter (cal$_{th}$/cm^2)	joule per square meter (J/m^2)	**4.184**	**E+04**
calorie$_{th}$ per square centimeter minute [cal$_{th}$/(cm^2 · min)]	watt per square meter (W/m^2)	6.973 333	E+02
calorie$_{th}$ per square centimeter second [cal$_{th}$/(cm^2 · s)]	watt per square meter (W/m^2)	**4.184**	**E+04**
candela per square inch (cd/in^2)	candela per square meter (cd/m^2)	1.550 003	E+03
carat, metric	kilogram (kg)	**2.0**	**E–04**
carat, metric	gram (g)	**2.0**	**E–01**
centimeter of mercury (0 °C)[13]	pascal (Pa)	1.333 22	E+03
centimeter of mercury (0 °C)[13]	kilopascal (kPa)	1.333 22	E+00
centimeter of mercury, conventional (cmHg)[13]	pascal (Pa)	1.333 224	E+03

[12] The kilogram calorie or "large calorie" is an obsolete term used for the kilocalorie, which is the calorie used to express the energy content of foods. However, in practice, the prefix "kilo" is usually omitted.

[13] Conversion factors for mercury manometer pressure units are calculated using the standard value for the acceleration of gravity and the density of mercury at the stated temperature. Additional digits are not justified because the definitions of the units do not take into account the compressibility of mercury or the change in density caused by the revised practical temperature scale, ITS-90. Similar comments also apply to water manometer pressure units. Conversion factors for conventional mercury and water manometer pressure units are based on ISO 31-3.

To convert from	to	Multiply by	
centimeter of mercury, conventional (cmHg)[13]	kilopascal (kPa)	1.333 224	E+00
centimeter of water (4 °C)[13]	pascal (Pa)	9.806 38	E+01
centimeter of water, conventional (cmH_2O)[13]	pascal (Pa)	**9.806 65**	**E+01**
centipoise (cP)	pascal second (Pa · s)	**1.0**	**E–03**
centistokes (cSt)	meter squared per second (m^2/s)	**1.0**	**E–06**
chain (based on U.S survey foot) (ch)[9]	meter (m)	2.011 684	E+01
circular mil	square meter (m^2)	5.067 075	E–10
circular mil	square millimeter (mm^2)	5.067 075	E–04
clo	square meter kelvin per watt ($m^2 \cdot K/W$)	1.55	E–01
cord (128 ft^3)	cubic meter (m^3)	3.624 556	E+00
cubic foot (ft^3)	cubic meter (m^3)	2.831 685	E–02
cubic foot per minute (ft^3 /min)	cubic meter per second (m^3/s)	4.719 474	E–04
cubic foot per minute (ft^3 /min)	liter per second (L/s)	4.719 474	E–01
cubic foot per second (ft^3/s)	cubic meter per second (m^3/s)	2.831 685	E–02
cubic inch (in^3)[14]	cubic meter (m^3)	1.638 706	E–05
cubic inch per minute (in^3 /min)	cubic meter per second (m^3/s)	2.731 177	E–07
cubic mile (mi^3)	cubic meter (m^3)	4.168 182	E+09
cubic yard (yd^3)	cubic meter (m^3)	7.645 549	E–01
cubic yard per minute (yd^3/min)	cubic meter per second (m^3/s)	1.274 258	E–02
cup (U.S.)	cubic meter (m^3)	2.365 882	E–04
cup (U.S.)	liter (L)	2.365 882	E–01
cup (U.S.)	milliliter (mL)	2.365 882	E+02
curie (Ci)	becquerel (Bq)	**3.7**	**E+10**
darcy[15]	meter squared (m^2)	9.869 233	E–13
day (d)	second (s)	**8.64**	**E+04**
day (sidereal)	second (s)	8.616 409	E+04
debye (D)	coulomb meter (C · m)	3.335 641	E–30
degree (angle) (°)	radian (rad)	1.745 329	E–02
degree Celsius (temperature) (°C)	kelvin (K)	T/ K = t / °C+**273.15**	
degree Celsius (temperature interval) (°C)	kelvin (K)	**1.0**	**E+00**
degree centigrade (temperature)[16]	degree Celsius (°C)	t / °C ≈ t / deg.cent.	
degree centigrade (temperature interval)[16]	degree Celsius (°C)	1.0	E+00
degree Fahrenheit (temperature) (°F)	degree Celsius (°C)	t / °C = (t / °F **–32**)/**1.8**	
degree Fahrenheit (temperature) (°F)	kelvin (K)	T/ K = (t / °F + **459.67**)/**1.8**	
degree Fahrenheit (temperature interval)(°F)	degree Celsius (°C)	5.555 556	E–01
degree Fahrenheit (temperature interval) (°F)	kelvin (K)	5.555 556	E–01
degree Fahrenheit hour per British thermal $unit_{IT}$ ($°F \cdot h/Btu_{IT}$)	kelvin per watt (K/W)	1.895 634	E+00
degree Fahrenheit hour per British thermal $unit_{th}$ ($°F \cdot h/Btu_{th}$)	kelvin per watt (K/W)	1.896 903	E+00
degree Fahrenheit hour square foot per British thermal $unit_{IT}$ ($°F \cdot h \cdot ft^2/Btu_{IT}$)	square meter kelvin per watt ($m^2 \cdot K/W$)	1.761 102	E–01
degree Fahrenheit hour square foot per British thermal $unit_{th}$ ($°F \cdot h \cdot ft^2/Btu_{th}$)	square meter kelvin per watt ($m^2 \cdot K/W$)	1.762 280	E–01
degree Fahrenheit hour square foot per British thermal $unit_{IT}$ inch [$°F \cdot h \cdot ft^2/(Btu_{IT} \cdot in)$]	meter kelvin per watt (m · K/W)	6.933 472	E+00
degree Fahrenheit hour square foot per British thermal $unit_{th}$ inch [$°F \cdot h \cdot ft^2/(Btu_{th} \cdot in)$]	meter kelvin per watt (m · K/W)	6.938 112	E+00
degree Fahrenheit second per British thermal $unit_{IT}$ ($°F \cdot s/Btu_{IT}$)	kelvin per watt (K/W)	5.265 651	E–04
degree Fahrenheit second per British thermal $unit_{th}$ ($°F \cdot s/Btu_{th}$)	kelvin per watt (K/W)	5.269 175	E–04
degree Rankine (°R)	kelvin (K)	T/ K = (T/ °R)/**1.8**	
degree Rankine (temperature interval) (°R)	kelvin (K)	5.555 556	E–01
denier	kilogram per meter (kg/m)	1.111 111	E–07
denier	gram per meter (g/m)	1.111 111	E–04
dyne (dyn)	newton (N)	**1.0**	**E–05**
dyne centimeter (dyn · cm)	newton meter (N · m)	**1.0**	**E–07**
dyne per square centimeter (dyn/cm^2)	pascal (Pa)	**1.0**	**E–01**

[14] The exact conversion factor is 1.638 706 4 E–05.

[15] The darcy is a unit for expressing the permeability of porous solids, not area.

[16] The centigrade temperature scale is obsolete; the degree centigrade is only approximately equal to the degree Celsius.

To convert from	to	Multiply by	
electronvolt (eV)	joule (J)	1.602 177	E–19
EMU of capacitance (abfarad)	farad (F)	**1.0**	**E+09**
EMU of current (abampere)	ampere (A)	**1.0**	**E+01**
EMU of electric potential (abvolt)	volt (V)	**1.0**	**E–08**
EMU of inductance (abhenry)	henry (H)	**1.0**	**E–09**
EMU of resistance (abohm)	ohm (Ω)	**1.0**	**E–09**
erg (erg)	joule (J)	**1.0**	**E–07**
erg per second (erg/s)	watt (W)	**1.0**	**E–07**
erg per square centimeter second |1obrkt&1ru|/(cm² · s)]	watt per square meter (W/m²)	**1.0**	**E–03**
ESU of capacitance (statfarad)	farad (F)	1.112 650	E–12
ESU of current (statampere)	ampere (A)	3.335 641	E–10
ESU of electric potential (statvolt)	volt (V)	2.997 925	E+02
ESU of inductance (stathenry)	henry (H)	8.987 552	E+11
ESU of resistance (statohm)	ohm (Ω)	8.987 552	E+11
faraday (based on carbon 12)	coulomb (C)	9.648 531	E+04
fathom (based on U.S survey foot)[9]	meter (m)	1.828 804	E+00
fermi	meter (m)	**1.0**	**E–15**
fermi	femtometer (fm)	**1.0**	**E+00**
fluid ounce (U.S.) (fl oz)	cubic meter (m³)	2.957 353	E–05
fluid ounce (U.S.) (fl oz)	milliliter (mL)	2.957 353	E+01
foot (ft)	meter (m)	**3.048**	**E–01**
foot (U.S survey ft)[9]	meter (m)	3.048 006	E–01
footcandle	lux (lx)	1.076 391	E+01
footlambert	candela per square meter (cd/m²)	3.426 259	E+00
foot of mercury, conventional (ftHg)[13]	pascal (Pa)	4.063 666	E+04
foot of mercury, conventional (ftHg)[13]	kilopascal (kPa)	4.063 666	E+01
foot of water (39.2 °F)[13]	pascal (Pa)	2.988 98	E+03
foot of water (39.2 °F)[13]	kilopascal (kPa)	2.988 98	E+00
foot of water, conventional (ftH_2O)[13]	pascal (Pa)	2.989 067	E+03
foot of water, conventional (ftH_2O)[13]	kilopascal (kPa)	2.989 067	E+00
foot per hour (ft/h)	meter per second (m/s)	8.466 667	E–05
foot per minute (ft/min)	meter per second (m/s)	**5.08**	**E–03**
foot per second (ft/s)	meter per second (m/s)	**3.048**	**E–01**
foot per second squared (ft/s²)	meter per second squared (m/s²)	**3.048**	**E–01**
foot poundal	joule (J)	4.214 011	E–02
foot pound-force (ft · lbf)	joule (J)	1.355 818	E+00
foot pound-force per hour (ft · lbf/h)	watt (W)	3.766 161	E–04
foot pound-force per minute (ft · lbf/min)	watt (W)	2.259 697	E–02
foot pound-force per second (ft · lbf/s)	watt (W)	1.355 818	E+00
foot to the fourth power (ft⁴)[17]	meter to the fourth power (m⁴)	8.630 975	E–03
franklin (Fr)	coulomb (C)	3.335 641	E–10
gal (Gal)	meter per second squared (m/s²)	**1.0**	**E–02**
gallon [Canadian and U.K (Imperial)] (gal)	cubic meter (m³)	**4.546 09**	**E–03**
gallon [Canadian and U.K (Imperial)] (gal)	liter (L)	**4.546 09**	**E+00**
gallon (U.S.) (gal)	cubic meter (m³)	3.785 412	E–03
gallon (U.S.) (gal)	liter (L)	3.785 412	E+00
gallon (U.S.) per day (gal/d)	cubic meter per second (m³/s)	4.381 264	E–08
gallon (U.S.) per day (gal/d)	liter per second (L/s)	4.381 264	E–05
gallon (U.S.) per horsepower hour [gal / (hp · h)]	cubic meter per joule (m³/J)	1.410 089	E–09
gallon (U.S.) per horsepower hour [gal / (hp · h)]	liter per joule (L/ J)	1.410 089	E–06
gallon (U.S.) per minute (gpm)(gal/min)	cubic meter per second (m³/s)	6.309 020	E–05
gallon (U.S.) per minute (gpm)(gal/min)	liter per second (L/ s)	6.309 020	E–02
gamma (γ)	tesla (T)	**1.0**	**E–09**
gauss (Gs, G)	tesla (T)	**1.0**	**E–04**
gilbert (Gi)	ampere (A)	7.957 747	E–01

[17] This is a unit for the quantity second moment of area, which is sometimes called the "moment of section" or "area moment of inertia" of a plane section about a specified axis.

To convert from	to	Multiply by	
gill [Canadian and U.K (Imperial)] (gi)	cubic meter (m^3)	1.420 653	E–04
gill [Canadian and U.K (Imperial)] (gi)	liter (L)	1.420 653	E–01
gill (U.S.) (gi)	cubic meter (m^3)	1.182 941	E–04
gill (U.S.) (gi)	liter (L)	1.182 941	E–01
gon (also called grade) (gon)	radian (rad)	1.570 796	E–02
gon (also called grade) (gon)	degree (angle) (°)	**9.0**	**E–01**
grain (gr)	kilogram (kg)	**6.479 891**	**E–05**
grain (gr)	milligram (mg)	**6.479 891**	**E+01**
grain per gallon (U.S.) (gr/gal)	kilogram per cubic meter (kg/m^3)	1.711 806	E–02
grain per gallon (U.S.) (gr/gal)	milligram per liter (mg/L)	1.711 806	E+01
gram-force per square centimeter (gf/cm^2)	pascal (Pa)	**9.806 65**	**E+01**
gram per cubic centimeter (g/cm^3)	kilogram per cubic meter (kg/m^3)	**1.0**	**E+03**
hectare (ha)	square meter (m^2)	**1.0**	**E+04**
horsepower (550 ft · lbf/s) (hp)	watt (W)	7.456 999	E+02
horsepower (boiler)	watt (W)	9.809 50	E+03
horsepower (electric)	watt (W)	**7.46**	**E+02**
horsepower (metric)	watt (W)	7.354 988	E+02
horsepower (U.K.)	watt (W)	7.4570	E+02
horsepower (water)	watt (W)	7.460 43	E+02
hour (h)	second (s)	**3.6**	**E+03**
hour (sidereal)	second (s)	3.590 170	E+03
hundredweight (long, 112 lb)	kilogram (kg)	5.080 235	E+01
hundredweight (short, 100 lb)	kilogram (kg)	4.535 924	E+01
inch (in)	meter (m)	**2.54**	**E–02**
inch (in)	centimeter (cm)	**2.54**	**E+00**
inch of mercury (32 °F)[13]	pascal (Pa)	3.386 38	E+03
inch of mercury (32 °F)[13]	kilopascal (kPa)	3.386 38	E+00
inch of mercury (60 °F)[13]	pascal (Pa)	3.376 85	E+03
inch of mercury (60 °F)[13]	kilopascal (kPa)	3.376 85	E+00
inch of mercury, conventional (inHg)[13]	pascal (Pa)	3.386 389	E+03
inch of mercury, conventional (inHg)[13]	kilopascal (kPa)	3.386 389	E+00
inch of water (39.2 °F)[13]	pascal (Pa)	2.490 82	E+02
inch of water (60 °F)[13]	pascal (Pa)	2.4884	E+02
inch of water, conventional (inH_2O)[13]	pascal (Pa)	2.490 889	E+02
inch per second (in/s)	meter per second (m/s)	**2.54**	**E–02**
inch per second squared (in/s^2)	meter per second squared (m/s^2)	**2.54**	**E–02**
inch to the fourth power (in^4)[17]	meter to the fourth power (m^4)	4.162 314	E–07
kayser (K)	reciprocal meter (m^{-1})	**1.0**	**E+02**
kelvin (K)	degree Celsius (°C)	t / °C = T/ K –	**273.15**
kilocalorie$_{IT}$ ($kcal_{IT}$)	joule (J)	**4.1868**	**E+03**
kilocalorie$_{th}$ ($kcal_{th}$)	joule (J)	**4.184**	**E+03**
kilocalorie (mean) (kcal)	joule (J)	4.190 02	E+03
kilocalorie$_{th}$ per minute ($kcal_{th}$ /min)	watt (W)	6.973 333	E+01
kilocalorie$_{th}$ per second ($kcal_{th}$ /s)	watt (W)	**4.184**	**E+03**
kilogram-force (kgf)	newton (N)	**9.806 65**	**E+00**
kilogram-force meter (kgf · m)	newton meter (N · m)	**9.806 65**	**E+00**
kilogram-force per square centimeter (kgf/cm^2)	pascal (Pa)	**9.806 65**	**E+04**
kilogram-force per square centimeter (kgf/cm^2)	kilopascal (kPa)	**9.806 65**	**E+01**
kilogram-force per square meter (kgf/m^2)	pascal (Pa)	**9.806 65**	**E+00**
kilogram-force per square millimeter (kgf/mm^2)	pascal (Pa)	**9.806 65**	**E+06**
kilogram-force per square millimeter (kgf/mm^2)	megapascal (MPa)	**9.806 65**	**E+00**
kilogram-force second squared per meter ($kgf \cdot s^2/m$)	kilogram (kg)	**9.806 65**	**E+00**
kilometer per hour (km/h)	meter per second (m/s)	2.777 778	E–01
kilopond (kilogram-force) (kp)	newton (N)	**9.806 65**	**E+00**
kilowatt hour (kW · h)	joule (J)	**3.6**	**E+06**
kilowatt hour (kW · h)	megajoule (MJ)	**3.6**	**E+00**

To convert from	to	Multiply by	
kip (1 kip=1000 lbf)	newton (N)	4.448 222	E+03
kip (1 kip=1000 lbf)	kilonewton (kN)	4.448 222	E+00
kip per square inch (ksi) (kip/in^2)	pascal (Pa)	6.894 757	E+06
kip per square inch (ksi) (kip/in^2)	kilopascal (kPa)	6.894 757	E+03
knot (nautical mile per hour)	meter per second (m/s)	5.144 444	E–01
lambert[18]	candela per square meter (cd/m^2)	3.183 099	E+03
langley (cal$_{th}$/cm^2)	joule per square meter (J/m^2)	**4.184**	**E+04**
light year (l.y.)[19]	meter (m)	9.460 73	E+15
liter (L)[20]	cubic meter (m^3)	**1.0**	**E–03**
lumen per square foot (lm/ft^2)	lux (lx)	1.076 391	E+01
maxwell (Mx)	weber (Wb)	**1.0**	**E–08**
mho	siemens (S)	**1.0**	**E+00**
microinch	meter (m)	**2.54**	**E–08**
microinch	micrometer (μm)	**2.54**	**E–02**
micron (μ)	meter (m)	**1.0**	**E–06**
micron (μ)	micrometer (μm)	**1.0**	**E+00**
mil (0.001 in)	meter (m)	**2.54**	**E–05**
mil (0.001 in)	millimeter (mm)	**2.54**	**E–02**
mil (angle)	radian (rad)	9.817 477	E–04
mil (angle)	degree (°)	**5.625**	**E–02**
mile (mi)	meter (m)	**1.609 344**	**E+03**
mile (mi)	kilometer (km)	**1.609 344**	**E+00**
mile (based on U.S survey foot) (mi)[9]	meter (m)	1.609 347	E+03
mile (based on U.S survey foot) (mi)[9]	kilometer (km)	1.609 347	E+00
mile, nautical [21]	meter (m)	**1.852**	**E+03**
mile per gallon (U.S.) (mpg) (mi/gal)	meter per cubic meter (m/m^3)	4.251 437	E+05
mile per gallon (U.S.) (mpg) (mi/gal)	kilometer per liter (km/L)	4.251 437	E–01
mile per gallon (U.S.) (mpg) (mi/gal)[22]	liter per 100 kilometer (L/100 km)	divide 235.215 by number of miles per gallon	
mile per hour (mi/h)	meter per second (m/s)	**4.4704**	**E–01**
mile per hour (mi/h)	kilometer per hour (km/h)	**1.609 344**	**E+00**
mile per minute (mi/min)	meter per second (m/s)	**2.682 24**	**E+01**
mile per second (mi/s)	meter per second (m/s)	**1.609 344**	**E+03**
millibar (mbar)	pascal (Pa)	**1.0**	**E+02**
millibar (mbar)	kilopascal (kPa)	**1.0**	**E–01**
millimeter of mercury, conventional (mmHg)[13]	pascal (Pa)	1.333 224	E+02
millimeter of water, conventional (mmH_2O)[13]	pascal (Pa)	**9.806 65**	**E+00**
minute (angle) (')	radian (rad)	2.908 882	E–04
minute (min)	second (s)	**6.0**	**E+01**
minute (sidereal)	second (s)	5.983 617	E+01
oersted (Oe)	ampere per meter (A/m)	7.957 747	E+01
ohm centimeter (Ω · cm)	ohm meter (Ω · m)	**1.0**	**E–02**
ohm circular-mil per foot	ohm meter (Ω · m)	1.662 426	E–09
ohm circular-mil per foot	ohm square millimeter per meter (Ω · mm^2/m)	1.662 426	E–03
ounce (avoirdupois) (oz)	kilogram (kg)	2.834 952	E–02
ounce (avoirdupois) (oz)	gram (g)	2.834 952	E+01
ounce (troy or apothecary) (oz)	kilogram (kg)	3.110 348	E–02
ounce (troy or apothecary) (oz)	gram (g)	3.110 348	E+01
ounce [Canadian and U.K fluid (Imperial)] (fl oz)	cubic meter (m^3)	2.841 306	E–05
ounce [Canadian and U.K fluid (Imperial)] (fl oz)	milliliter (mL)	2.841 306	E+01

[18] The exact conversion factor is $10^4/\pi$.

[19] This conversion factor is based on 1 d = 86 400 s; and 1 Julian century = 36 525 d. (See *The Astronomical Almanac for the Year 1995*, page K6, U.S. Government Printing Office, Washington, DC, 1994).

[20] In 1964 the General Conference on Weights and Measures reestablished the name "liter" as a special name for the cubic decimeter. Between 1901 and 1964 the liter was slightly larger (1.000 028 dm^3); when one uses high-accuracy volume data of that time, this fact must be kept in mind.

[21] The value of this unit, 1 nautical mile = 1852 m, was adopted by the First International Extraordinary Hydrographic Conference, Monaco, 1929, under the name "International nautical mile."

[22] For converting fuel economy, as used in the U.S., to fuel consumption.

To convert from	to	Multiply by	
ounce (U.S. fluid) (fl oz)	cubic meter (m^3)	2.957 353	E–05
ounce (U.S fluid) (fl oz)	milliliter (mL)	2.957 353	E+01
ounce (avoirdupois)-force (ozf)	newton (N)	2.780 139	E–01
ounce (avoirdupois)-force inch (ozf · in)	newton meter (N · m)	7.061 552	E–03
ounce (avoirdupois)-force inch (ozf · in)	millinewton meter (mN · m)	7.061 552	E+00
ounce (avoirdupois) per cubic inch (oz/ in^3)	kilogram per cubic meter (kg/m^3)	1.729 994	E+03
ounce (avoirdupois) per gallon [Canadian and U.K (Imperial)] (oz/gal)	kilogram per cubic meter (kg/m^3)	6.236 023	E+00
ounce (avoirdupois) per gallon [Canadian and U.K (Imperial)] (oz/gal)	gram per liter (g/L)	6.236 023	E+00
ounce (avoirdupois) per gallon (U.S.)(oz/gal)	kilogram per cubic meter (kg/m^3)	7.489 152	E+00
ounce (avoirdupois) per gallon (U.S.)(oz/gal)	gram per liter (g/L)	7.489 152	E+00
ounce (avoirdupois) per square foot (oz/ ft^2)	kilogram per square meter (kg/m^2)	3.051 517	E–01
ounce (avoirdupois) per square inch (oz/ in^2)	kilogram per square meter (kg/m^2)	4.394 185	E+01
ounce (avoirdupois) per square yard(oz/yd^2)	kilogram per square meter (kg/m^2)	3.390 575	E–02
parsec (pc)	meter (m)	3.085 678	E+16
peck (U.S.) (pk)	cubic meter (m^3)	8.809 768	E–03
peck (U.S.) (pk)	liter (L)	8.809 768	E+00
pennyweight (dwt)	kilogram (kg)	1.555 174	E–03
pennyweight (dwt)	gram (g)	1.555 174	E+00
perm (0 °C)	kilogram per pascal second square meter [kg/(Pa · s · m^2)]	5.721 35	E–11
perm (23 °C)	kilogram per pascal second square meter [kg/(Pa · s · m^2)]	5.745 25	E–11
perm inch (0 °C)	kilogram per pascal second meter [kg/(Pa · s · m)]	1.453 22	E–12
perm inch (23 °C)	kilogram per pascal second meter [kg/(Pa · s · m)]	1.459 29	E–12
phot (ph)	lux (lx)	**1.0**	**E+04**
pica (computer) (1/6 in)	meter (m)	4.233 333	E–03
pica (computer) (1/6 in)	millimeter (mm)	4.233 333	E+00
pica (printer's)	meter (m)	4.217 518	E–03
pica (printer's)	millimeter (mm)	4.217 518	E+00
pint (U.S dry) (dry pt)	cubic meter (m^3)	5.506 105	E–04
pint (U.S dry) (dry pt)	liter (L)	5.506 105	E–01
pint (U.S liquid) (liq pt)	cubic meter (m^3)	4.731 765	E–04
pint (U.S liquid) (liq pt)	liter (L)	4.731 765	E–01
point (computer) (1/72 in)	meter (m)	3.527 778	E–04
point (computer) (1/72 in)	millimeter (mm)	3.527 778	E–01
point (printer's)	meter (m)	3.514 598	E–04
point (printer's)	millimeter (mm)	3.514 598	E–01
poise (P)	pascal second (Pa · s)	**1.0**	**E–01**
pound (avoirdupois) (lb)[23]	kilogram (kg)	4.535 924	E–01
pound (troy or apothecary) (lb)	kilogram (kg)	3.732 417	E–01
poundal	newton (N)	1.382 550	E–01
poundal per square foot	pascal (Pa)	1.488 164	E+00
poundal second per square foot	pascal second (Pa · s)	1.488 164	E+00
pound foot squared (lb · ft^2)	kilogram meter squared (kg · m^2)	4.214 011	E–02
pound-force (lbf)[24]	newton (N)	4.448 222	E+00
pound-force foot (lbf · ft)	newton meter (N · m)	1.355 818	E+00
pound-force foot per inch (lbf · ft/in)	newton meter per meter (N · m/m)	5.337 866	E+01
pound-force inch (lbf · in)	newton meter (N · m)	1.129 848	E–01
pound-force inch per inch (lbf · in/in)	newton meter per meter (N · m/m)	4.448 222	E+00
pound-force per foot (lbf/ft)	newton per meter (N/m)	1.459 390	E+01
pound-force per inch (lbf/in)	newton per meter (N/m)	1.751 268	E+02
pound-force per pound (lbf/lb) (thrust to mass ratio)	newton per kilogram (N/kg)	**9.806 65**	**E+00**
pound-force per square foot (lbf/ft^2)	pascal (Pa)	4.788 026	E+01
pound-force per square inch (psi) (lbf/in^2)	pascal (Pa)	6.894 757	E+03

[23] The exact conversion factor is 4.535 923 7 E–01. All units that contain the pound refer to the avoirdupois pound unless otherwise specified.

[24] If the local value of the acceleration of free fall is taken as g_n=9.806 65 m/ s^2 (the standard value), the exact conversion factor is 4.448 221 615 260 5 E+00.

To convert from	to	Multiply by	
pound-force per square inch (psi) (lbf/in^2)	kilopascal (kPa)	6.894 757	E+00
pound-force second per square foot (lbf · s/ft^2)	pascal second (Pa · s)	4.788 026	E+01
pound-force second per square inch (lbf · s/in^2)	pascal second (Pa · s)	6.894 757	E+03
pound inch squared (lb · in^2)	kilogram meter squared (kg · m^2)	2.926 397	E–04
pound per cubic foot (lb/ft^3)	kilogram per cubic meter (kg/m^3)	1.601 846	E+01
pound per cubic inch (lb/in^3)	kilogram per cubic meter (kg/m^3)	2.767 990	E+04
pound per cubic yard (lb/yd^3)	kilogram per cubic meter (kg/m^3)	5.932 764	E–01
pound per foot (lb/ft)	kilogram per meter (kg/m)	1.488 164	E+00
pound per foot hour [lb/(ft · h)]	pascal second (Pa · s)	4.133 789	E–04
pound per foot second [lb/(ft · s)]	pascal second (Pa · s)	1.488 164	E+00
pound per gallon [Canadian and U.K (Imperial)] (lb/gal)	kilogram per cubic meter (kg/m^3)	9.977 637	E+01
pound per gallon [Canadian and U.K (Imperial)] (lb/gal)	kilogram per liter (kg/L)	9.977 637	E–02
pound per gallon (U.S.) (lb/gal)	kilogram per cubic meter (kg/m^3)	1.198 264	E+02
pound per gallon (U.S.) (lb/gal)	kilogram per liter (kg/L)	1.198 264	E–01
pound per horsepower hour [lb/(hp · h)]	kilogram per joule (kg/J)	1.689 659	E–07
pound per hour (lb/h)	kilogram per second (kg/s)	1.259 979	E–04
pound per inch (lb/in)	kilogram per meter (kg/m)	1.785 797	E+01
pound per minute (lb/min)	kilogram per second (kg/s)	7.559 873	E–03
pound per second (lb/s)	kilogram per second (kg/s)	4.535 924	E–01
pound per square foot (lb/ft^2)	kilogram per square meter (kg/m^2)	4.882 428	E+00
pound per square inch (*not* pound-force) (lb/in^2)	kilogram per square meter (kg/m^2)	7.030 696	E+02
pound per yard (lb/yd)	kilogram per meter (kg/m)	4.960 546	E–01
psi (pound-force per square inch) (lbf/in^2)	pascal (Pa)	6.894 757	E+03
psi (pound-force per square inch) (lbf/in^2)	kilopascal (kPa)	6.894 757	E+00
quad (10^{15} Btu_{IT})[11]	joule (J)	1.055 056	E+18
quart (U.S dry) (dry qt)	cubic meter (m^3)	1.101 221	E–03
quart (U.S dry) (dry qt)	liter (L)	1.101 221	E+00
quart (U.S liquid) (liq qt)	cubic meter (m^3)	9.463 529	E–04
quart (U.S liquid) (liq qt)	liter (L)	9.463 529	E–01
rad (absorbed dose) (rad)	gray (Gy)	**1.0**	**E–02**
rem (rem)	sievert (Sv)	**1.0**	**E–02**
revolution (r)	radian (rad)	6.283 185	E+00
revolution per minute (rpm) (r/min)	radian per second (rad/s)	1.047 198	E–01
rhe	reciprocal pascal second [(Pa · s)$^{-1}$]	**1.0**	**E+01**
rod (based on U.S survey foot) (rd)[9]	meter (m)	5.029 210	E+00
roentgen (R)	coulomb per kilogram (C/kg)	**2.58**	**E–04**
rpm (revolution per minute) (r/min)	radian per second (rad/s)	1.047 198	E–01
second (angle) (")	radian (rad)	4.848 137	E–06
second (sidereal)	second (s)	9.972 696	E–01
shake	second (s)	**1.0**	**E–08**
shake	nanosecond (ns)	**1.0**	**E+01**
slug (slug)	kilogram (kg)	1.459 390	E+01
slug per cubic foot (slug/ft^3)	kilogram per cubic meter (kg/m^3)	5.153 788	E+02
slug per foot second [slug/(ft · s)]	pascal second (Pa · s)	4.788 026	E+01
square foot (ft^2)	square meter (m^2)	**9.290 304**	**E–02**
square foot per hour (ft^2/h)	square meter per second (m^2/s)	**2.580 64**	**E–05**
square foot per second (ft^2/s)	square meter per second (m^2/s)	**9.290 304**	**E–02**
square inch (in^2)	square meter (m^2)	**6.4516**	**E–04**
square inch (in^2)	square centimeter (cm^2)	**6.4516**	**E+00**
square mile (mi^2)	square meter (m^2)	2.589 988	E+06
square mile (mi^2)	square kilometer (km^2)	2.589 988	E+00
square mile (based on U.S survey foot) (mi^2)[9]	square meter (m^2)	2.589 998	E+06
square mile (based on U.S survey foot) (mi^2)[9]	square kilometer (km^2)	2.589 998	E+00

To convert from	to	Multiply by	
square yard (yd^2)	square meter (m^2)	8.361 274	E–01
statampere	ampere (A)	3.335 641	E–10
statcoulomb	coulomb (C)	3.335 641	E–10
statfarad	farad (F)	1.112 650	E–12
stathenry	henry (H)	8.987 552	E+11
statmho	siemens (S)	1.112 650	E–12
statohm	ohm (Ω)	8.987 552	E+11
statvolt	volt (V)	2.997 925	E+02
stere (st)	cubic meter (m^3)	**1.0**	**E+00**
stilb (sb)	candela per square meter (cd/m^2)	**1.0**	**E+04**
stokes (St)	meter squared per second (m^2/s)	**1.0**	**E–04**
tablespoon	cubic meter (m^3)	1.478 676	E–05
tablespoon	milliliter (mL)	1.478 676	E+01
teaspoon	cubic meter (m^3)	4.928 922	E–06
teaspoon	milliliter (mL)	4.928 922	E+00
tex	kilogram per meter (kg/m)	**1.0**	**E–06**
therm (EC)[25]	joule (J)	**1.055 06**	**E+08**
therm (U.S.)[25]	joule (J)	**1.054 804**	**E+08**
ton, assay (AT)	kilogram (kg)	2.916 667	E–02
ton, assay (AT)	gram (g)	2.916 667	E+01
ton-force (2000 lbf)	newton (N)	8.896 443	E+03
ton-force (2000 lbf)	kilonewton (kN)	8.896 443	E+00
ton, long (2240 lb)	kilogram (kg)	1.016 047	E+03
ton, long, per cubic yard	kilogram per cubic meter (kg/m^3)	1.328 939	E+03
ton, metric (t)	kilogram (kg)	**1.0**	**E+03**
tonne (called "metric ton" in U.S.) (t)	kilogram (kg)	**1.0**	**E+03**
ton of refrigeration (12 000 Btu_{IT}/h)	watt (W)	3.516 853	E+03
ton of TNT (energy equivalent)[26]	joule (J)	**4.184**	**E+09**
ton, register	cubic meter (m^3)	2.831 685	E+00
ton, short (2000 lb)	kilogram (kg)	9.071 847	E+02
ton, short, per cubic yard	kilogram per cubic meter (kg/m^3)	1.186 553	E+03
ton, short, per hour	kilogram per second (kg/s)	2.519 958	E–01
torr (Torr)	pascal (Pa)	1.333 224	E+02
unit pole	weber (Wb)	1.256 637	E–07
watt hour (W · h)	joule (J)	**3.6**	**E+03**
watt per square centimeter (W/cm^2)	watt per square meter (W/m^2)	**1.0**	**E+04**
watt per square inch (W/in^2)	watt per square meter (W/m^2)	1.550 003	E+03
watt second (W · s)	joule (J)	**1.0**	**E+00**
yard (yd)	meter (m)	**9.144**	**E–01**
year (365 days)	second (s)	**3.1536**	**E+07**
year (sidereal)	second (s)	3.155 815	E+07
year (tropical)	second (s)	3.155 693	E+07

[25] The therm (EC) is legally defined in the Council Directive of 20 December 1979, Council of the European Communities (now the European Union, EU). The therm (U.S.) is legally defined in the Federal Register of July 27, 1968. Although the therm (EC), which is based on the International Table Btu, is frequently used by engineers in the United States, the therm (U.S.) is the legal unit used by the U.S natural gas industry.

[26] Defined (not measured) value.

CONVERSION OF TEMPERATURES

From	To	
Celsius	Fahrenheit	$t_F/^\circ F = (9/5)\ t/^\circ C + 32$
	Kelvin	$T/K = t/^\circ C + 273.15$
	Rankine	$T/^\circ R = (9/5)\ (t/^\circ C + 273.15)$
Fahrenheit	Celsius	$t/^\circ C = (5/9)\ [(t_F/^\circ F) - 32]$
	Kelvin	$T/K = (5/9)\ [(t_F/^\circ F) - 32] + 273.15$
	Rankine	$T/^\circ R = t_F/^\circ F + 459.67$
Kelvin	Celsius	$t/^\circ C = T/K - 273.15$
	Rankine	$T/^\circ R = (9/5)\ T/K$
Rankine	Fahrenheit	$t_F/^\circ F = T/^\circ R - 459.67$
	Kelvin	$T/K = (5/9)\ T/^\circ R$

Definition of symbols:

T = thermodynamic (absolute) temperature

t = Celsius temperature (the symbol θ is also used for Celsius temperature)

t_F = Fahrenheit temperature

Designation of Large Numbers

	U.S.A.	Other countries
10^6	million	million
10^9	billion	milliard
10^{12}	trillion	billion
10^{15}	quadrillion	billiard
10^{18}	quintillion	trillion
100^{100}	googol	
10^{googol}	googolplex	

CONVERSION FACTORS FOR ENERGY UNITS

If greater accuracy is required, use the *Energy Equivalents* section of the *Fundamental Physical Constants* table.

	Wavenumber $\tilde{\nu}$ cm^{-1}	**Frequency ν MHz**	**Energy E aJ**	**Energy E eV**	**Energy E E_h**	**Molar energy E_m kJ/mol**	**Molar energy E_m kcal/mol**	**Temperature T K**
$\tilde{\nu}$: 1 cm^{-1}	$\doteq$ 1	2.997925×10^{4}	1.986447×10^{-5}	1.239842×10^{-4}	4.556335×10^{-6}	11.96266×10^{-3}	2.85914×10^{-3}	1.438769
ν: 1 MHz	$\doteq 3.33564 \times 10^{-5}$	1	6.626076×10^{-10}	4.135669×10^{-9}	1.519830×10^{-10}	3.990313×10^{-7}	9.53708×10^{-8}	4.79922×10^{-5}
1 aJ	$\doteq$ 50341.1	1.509189×10^{9}	1	6.241506	0.2293710	602.2137	143.9325	7.24292×10^{4}
E: 1 eV	$\doteq$ 8065.54	2.417988×10^{8}	0.1602177	1	3.674931×10^{-2}	96.4853	23.0605	1.16045×10^{4}
E_h	$\doteq$ 219474.63	6.579684×10^{9}	4.359748	27.2114	1	2625.500	627.510	3.15773×10^{5}
E_m: 1 kJ/mol	$\doteq$ 83.5935	2.506069×10^{6}	1.660540×10^{-3}	1.036427×10^{-2}	3.808798×10^{-4}	1	0.239006	120.272
1 kcal/mol	$\doteq$ 349.755	1.048539×10^{7}	6.947700×10^{-3}	4.336411×10^{-2}	1.593601×10^{-3}	4.184	1	503.217
T: 1 K	$\doteq$ 0.695039	2.08367×10^{4}	1.380658×10^{-5}	8.61738×10^{-5}	3.16683×10^{-6}	8.31451×10^{-3}	1.98722×10^{-3}	1

Examples of the use of this table:

$$1 \text{ aJ} \doteq 50341 \text{ cm}^{-1}$$

$$1 \text{ eV} \doteq 96.4853 \text{ kJ mol}^{-1}$$

The symbol $\doteq$ should be read as meaning corresponds to or is equivalent to.

$E = h\nu = hc\tilde{\nu} = kT$; $E_m = N_A E$; E_h is the Hartree energy

CONVERSION FACTORS FOR PRESSURE UNITS

	Pa	**kPa**	**MPa**	**bar**	**atmos**	**Torr**	**μmHg**	**psi**
Pa	1	0.001	0.000001	0.00001	9.8692×10^{-6}	0.0075006	7.5006	0.0001450377
kPa	1000	1	0.001	0.01	0.0098692	7.5006	7500.6	0.1450377
MPa	1000000	1000	1	10	9.8692	7500.6	7500600	145.0377
bar	100000	100	0.1	1	0.98692	750.06	750060	14.50377
atmos	101325	101.325	0.101325	1.01325	1	760	760000	14.69594
Torr	133.322	0.133322	0.000133322	0.00133322	0.00131579	1	1000	0.01933672
μmHg	0.133322	0.000133322	1.33322×10^{-7}	1.33322×10^{-6}	1.31579×10^{-6}	0.001	1	1.933672×10^{-5}
psi	6894.757	6.894757	0.006894757	0.06894757	0.068046	51.7151	51715.1	1

To convert a pressure value from a unit in the left hand column to a new unit, multiply the value by the factor appearing in the column for the new unit. For example:

1 kPa = 9.8692×10^{-3} atmos
1 Torr = 1.33322×10^{-4} MPa

Notes: μmHg is often referred to as "micron"
Torr is essentially identical to mmHg
psi is an abbreviation for the unit pound–force per square inch
psia (as a term for a physical quantity) implies the true (absolute) pressure
psig implies the true pressure minus the local atmospheric pressure

CONVERSION FACTORS FOR THERMAL CONDUCTIVITY UNITS

MULTIPLY ↓ by appropriate factor to OBTAIN→	Btu_{IT} $h^{-1}\,ft^{-1}\,°F^{-1}$	Btu_{IT} in. $h^{-1}\,ft^{-2}\,°F^{-1}$	Btu_{th} $h^{-1}\,ft^{-1}\,°F^{-1}$	Btu_{th} in. $h^{-1}\,ft^{-2}\,°F^{-1}$	cal_{IT} s^{-1} $cm^{-1}\,°C^{-1}$	cal_{th} s^{-1} $cm^{-1}\,°C^{-1}$	$kcal_{th}$ h^{-1} $m^{-1}\,°C^{-1}$	J s^{-1} $cm^{-1}\,K^{-1}$	W $cm^{-1}\,K^{-1}$	W $m^{-1}\,K^{-1}$	mW cm^{-1} K^{-1}
Btu_{IT} $h^{-1}\,ft^{-1}\,°F^{-1}$	1	12	1.00067	12.0080	4.13379×10^{-3}	4.13656×10^{-3}	1.48916	1.73073×10^{-2}	1.73073×10^{-2}	1.73073	17.3073
Btu_{IT} in. $h^{-1}\,ft^{-2}\,°F^{-1}$	8.33333×10^{-2}	1	8.33891×10^{-2}	1.00067	3.44482×10^{-4}	3.44713×10^{-4}	0.124097	1.44228×10^{-3}	1.44228×10^{-3}	0.144228	1.44228
Btu_{th} $h^{-1}\,ft^{-1}\,°F^{-1}$	0.999331	11.9920	1	12	4.13102×10^{-3}	4.13379×10^{-3}	1.48816	1.72958×10^{-2}	1.72958×10^{-2}	1.72958	17.2958
Btu_{th} in. $h^{-1}\,ft^{-2}\,°F^{-1}$	8.32776×10^{-2}	0.999331	8.33333×10^{-2}	1	3.44252×10^{-4}	3.44482×10^{-4}	0.124014	1.44131×10^{-3}	1.44131×10^{-3}	0.144131	1.44131
cal_{IT} $s^{-1}\,cm^{-1}\,°C^{-1}$	2.41909×10^{2}	2.90291×10^{3}	2.42071×10^{2}	2.90485×10^{3}	1	1.00067	3.60241×10^{2}	4.1868	4.1868	4.1868×10^{2}	4.1868×10^{3}
cal_{th} $s^{-1}\,cm^{-1}\,°C^{-1}$	2.41747×10^{2}	2.90096×10^{3}	2.41909×10^{2}	2.90291×10^{3}	0.999331	1	3.6×10^{2}	4.184	4.184	4.184×10^{2}	4.184×10^{3}
$kcal_{th}$ $h^{-1}\,m^{-1}\,°C^{-1}$	0.671520	8.05824	0.671969	8.06363	2.77592×10^{-3}	2.77778×10^{-3}	1	1.16222×10^{-2}	1.16222×10^{-2}	1.16222	11.6222
J $s^{-1}\,cm^{-1}\,K^{-1}$	57.7789	6.93347×10^{2}	57.8176	6.93811×10^{2}	0.238846	0.239006	86.0421	1	1	1×10^{2}	1×10^{3}
W $cm^{-1}\,K^{-1}$	57.7789	6.93347×10^{2}	57.8176	6.93811×10^{2}	0.238846	0.239006	86.0421	1	1	1×10^{2}	1×10^{3}
W $m^{-1}\,K^{-1}$	0.577789	6.93347	0.578176	6.93811	2.38846×10^{-3}	2.39006×10^{-3}	0.860421	1×10^{-2}	1×10^{-2}	1	10
mW $cm^{-1}\,K^{-1}$	5.77789×10^{-2}	0.693347	5.78176×10^{-2}	0.693811	2.38846×10^{-4}	2.39006×10^{-4}	8.60421×10^{-2}	1×10^{-3}	1×10^{-3}	0.1	1

CONVERSION FACTORS FOR ELECTRICAL RESISTIVITY UNITS

To convert FROM ↓ multiply by appropriate factor to OBTAIN →	abΩ cm	μΩ cm	Ω cm	StatΩ cm	Ω m	Ω cir. mil ft^{-1}	Ω in.	Ω ft
abohm centimeter	1	1×10^{-3}	10^{-9}	1.113×10^{-21}	10^{-11}	6.015×10^{-3}	3.937×10^{-10}	3.281×10^{-11}
microohm centimeter	10^{3}	1	10^{-6}	1.113×10^{-18}	10^{-8}	6.015	3.937×10^{-7}	3.281×10^{-6}
ohm centimeter	10^{8}	10^{6}	1	1.113×10^{-12}	1×10^{-2}	6.015×10^{6}	3.937×10^{-1}	3.281×10^{-2}
statohm centimeter (esu)	8.987×10^{20}	8.987×10^{17}	8.987×10^{11}	1	8.987×10^{9}	5.406×10^{18}	3.538×10^{11}	2.949×10^{10}
ohm meter	10^{11}	10^{8}	10^{2}	1.113×10^{-10}	1	6.015×10^{8}	3.937×10^{1}	3.281
ohm circular mil per foot	1.662×10^{2}	1.662×10^{-1}	1.662×10^{-7}	1.850×10^{-19}	1.662×10^{-9}	1	6.54×10^{-6}	5.45×10^{-9}
ohm inch	2.54×10^{9}	2.54×10^{6}	2.54	2.827×10^{-12}	2.54×10^{-2}	1.528×10^{7}	1	8.3×10^{-2}
ohm foot	3.048×10^{10}	3.048×10^{7}	3.048×10^{-1}	3.3924×10^{-11}	3.048×10^{-1}	1.833×10^{8}	12	1

CONVERSION FACTORS FOR CHEMICAL KINETICS

Equivalent Second Order Rate Constants

A \ B	$cm^3\ mol^{-1}s^{-1}$	$dm^3\ mol^{-1}s^{-1}$	$m^3\ mol^{-1}s^{-1}$	$cm^3\ molecule^{-1}s^{-1}$	$(mm\ Hg)^{-1}s^{-1}$	$atm^{-1}s^{-1}$	$ppm^{-1}min^{-1}$	$m^2\ kN^{-1}s^{-1}$
1 $cm^3\ mol^{-1}\ s^{-1}$ =	1	10^{-3}	10^{-6}	1.66×10^{-24}	$1.604 \times 10^{-5}\ T^{+1}$	$1.219 \times 10^{-2}\ T^{+1}$	2.453×10^{-9}	$1.203 \times 10^{-4}\ T^{+1}$
1 $dm^3\ mol^{-1}\ s^{-1}$ =	10^3	1	10^{-3}	1.66×10^{-21}	$1.604 \times 10^{-2}\ T^{+1}$	$12.19\ T^{+1}$	2.453×10^{-6}	$1.203 \times 10^{-1}\ T^{+1}$
1 $m^3\ mol^{-1}\ s^{-1}$ =	10^6	10^3	1	1.66×10^{-18}	$16.04\ T^{+1}$	$1.219 \times 10^{4}\ T^{+1}$	2.453×10^{-3}	$120.3\ T^{+1}$
1cm^3 molecule $^{-1}s^{-1}$ =	6.023×10^{23}	6.023×10^{20}	6.023×10^{17}	1	$9.658 \times 10^{18} T^{+1}$	$7.34 \times 10^{21}\ T^{+1}$	1.478×10^{15}	$7.244 \times 10^{19} T^{+1}$
1 $(mm\ Hg)^{-1}\ s^{-1}$ =	$6.236 \times 10^{4}\ T$	$62.36\ T$	$6.236 \times 10^{-2}\ T$	$1.035 \times 10^{-19}\ T$	1	760	4.56×10^{-2}	7.500
1 $atm^{-1}\ s^{-1}$	$82.06\ T$	$8.206 \times 10^{-2}\ T$	$8.206 \times 10^{-5}\ T$	$1.362 \times 10^{-22}\ T$	1.316×10^{-3}	1	6×10^{-5}	9.869×10^{-3}
1 $ppm^{-1}\ min^{-1}$ = at 298 K, 1 atm total pressure	4.077×10^{8}	4.077×10^{5}	407.7	6.76×10^{-16}	21.93	1.667×10^{4}	1	164.5
1 $m^2\ kN^{-1}s^{-1}$ =	$8314\ T$	$8.314\ T$	$8.314 \times 10^{-3}\ T$	$1.38 \times 10^{-20}\ T$	0.1333	101.325	6.079×10^{-3}	1

To convert a rate constant from one set of units A to a new set B find the conversion factor for the row A under column B and multiply the old value by it, e.g.. to convert cm^3 $molecule^{-1}$ s^{-1} to m^3 mol^{-1} s^{-1} multiply by 6.023×10^{17}.

Table adapted from High Temperature Reaction Rate Data No. 5, The University, Leeds (1970).

Equivalent Third Order Rate Constants

A \ B	$cm^6\ mol^{-2}s^{-1}$	$dm^6\ mol^{-1}s^{-1}$	$m^6\ mol^{-2}\ s^{-1}$	$cm^6\ molecule^{-2}\ s^{-1}$	$(mm\ Hg)^{-2}\ s^{-1}$	$atm^{-2}\ s^{-1}$	$ppm^{-2}\ min^{-1}$	$m^4\ kN^{-2}s^{-1}$
1 $cm^6\ mol^{-2}\ s^{-1}$=	1	10^{-6}	10^{-12}	2.76×10^{-48}	$2.57 \times 10^{-10} T^{+2}$	$1.48 \times 10^{-4}\ T^{-2}$	1.003×10^{-19}	$1.477 \times 10^{-8} T^{+2}$
1 $dm^6\ mol^{-2}\ s^{-1}$ =	10^6	1	10^{-6}	2.76×10^{-42}	$2.57 \times 10^{-4} T^{+2}$	$148\ T^{+2}$	1.003×10^{-13}	$1.477 \times 10^{-2} T^{+2}$
1 $m^6\ mol^{-2}\ s^{-1}$=	10^{12}	10^6	1	2.76×10^{-36}	$257\ T^{+2}$	$1.48 \times 10^{8} T^{+2}$	1.003×10^{-7}	$1.477 \times 10^{4} T^{+2}$
1cm^6 molecule $^{-2}s^{-1}$=	3.628×10^{47}	3.628×10^{41}	3.628×10^{35}	1	$9.328 \times 10^{37} T^{+2}$	$5.388 \times 10^{43} T^{+2}$	3.64×10^{28}	$5.248 \times 10^{39} T^{+2}$
1 $(mm\ Hg)^{-2}\ s^{-1}$ =	$3.89 \times 10^{9}\ T^2$	$3.89 \times 10^{3}\ T^2$	$3.89 \times 10^{-3}\ T^2$	$1.07 \times 10^{-38} T^2$	1	5.776×10^{5}	3.46×10^{-5}	56.25
1 $atm^{-2}\ s^{-1}$ =	$6.733 \times 10^{3}\ T^2$	$6.733 \times 10^{-3}\ T^2$	$6.733 \times 10^{-9}\ T^2$	$1.86 \times 10^{-44} T^2$	1.73×10^{-6}	1	6×10^{-11}	9.74×10^{-5}
1 $ppm^{-2}\ min^{-1}$= at 298K, 1 atm total pressure	9.97×10^{18}	9.97×10^{12}	9.97×10^{6}	2.75×10^{-29}	2.89×10^{4}	1.667×10^{10}	1	1.623×10^{6}
1 $m^1\ kN^{-2}s^{-1}$=	$6.91 \times 10^{7}\ T^2$	$6.91\ T^2$	$69.1 \times 10^{-5}\ T^2$	$1.904 \times 10^{-40}\ T^2$	0.0178	1.027×10^{4}	6.16×10^{-7}	1

From *J. Phys. Chem. Ref. Data*, 9, 470, 1980, by permission of the authors and the copyright owner, the American Institute of Physics.

CONVERSION FACTORS FOR IONIZING RADIATION

Conversion Between SI and Other Units

Quantity	Symbol for quantity	Expression in SI units	Expression in symbols for SI units	Special name for SI units	Symbols using special names	Conventional units	Symbol for conventional unit	Value of conventional unit in SI units
Activity	A	1 per second	s^{-1}	becquerel	Bq	curie	Ci	3.7×10^{10} Bq
Absorbed dose	D	joule per kilogram	$J\ kg^{-1}$	gray	Gy	rad	rad	0.01 Gy
Absorbed dose rate	$\dot{D}$	joule per kilogram second	$J\ kg^{-1}\ s^{-1}$		$Gy\ s^{-1}$	rad	rad s^{-1}	0.01 Gy s^{-1}
Average energy per ion pair	W	joule	J			electronvolt	eV	1.602×10^{-19} J
Dose equivalent	H	joule per kilogram	$J\ kg^{-1}$	sievert	Sv	rem	rem	0.01 Sv
Dose equivalent rate	$\dot{H}$	joule per kilogram second	$J\ kg^{-1}\ s^{-1}$		$Sv\ s^{-1}$	rem per second	rem s^{-1}	0.01 Sv s^{-1}
Electric current	I	ampere	A			ampere	A	1.0 A
Electric potential difference	U, V	watt per ampere	$W\ A^{-1}$	volt	V	volt	V	1.0 V
Exposure	$\dot{X}$	coulomb per kilogram	$C\ kg^{-1}$			roentgen	R	2.58×10^{-4} C kg^{-1}
Exposure rate	X	coulomb per kilogram second	$C\ kg^{-1}\ s^{-1}$			roentgen	R s^{-1}	2.58×10^{-4} C kg^{-1} s^{-1}
Fluence	ϕ	1 per meter squared	m^{-2}			1 per centimeter squared	cm^{-2}	1.0×10^{4} m^{-2}
Fluence rate	Φ	1 per meter squared second	$m^{-2}\ s^{-1}$			1 per centimeter squared second	$cm^{-2}\ s^{-1}$	1.0×10^{4} m^{-2} s^{-1}
Kerma	K	joule per kilogram	$J\ kg^{-1}$	gray	Gy	rad	rad	0.01 Gy
Kerma rate	$\dot{K}$	joule per kilogram second	$J\ kg^{-1}\ s^{-1}$		$Gy\ s^{-1}$	rad per second	rad s^{-1}	0.01 Gy s^{-1}
Lineal energy	y	joule per meter	$J\ m^{-1}$			kiloelectron volt per micrometer	keV μm^{-1}	1.602×10^{-10} J m^{-1}
Linear energy transfer	L	joule per meter	$J\ m^{-1}$			kiloelectron volt per micrometer	keV μm^{-1}	1.602×10^{-10} J m^{-1}
Mass attenuation coefficient	μ/ρ	meter squared per kilogram	$m^2\ kg^{-1}$			centimeter squared per gram	$cm^2\ g^{-1}$	0.1 m^2 kg^{-1}
Mass energy transfer coefficient	μ_{tr}/ρ	meter squared per kilogram	$m^2\ kg^{-1}$			centimeter squared per gram	$cm^2\ g^{-1}$	0.1 m^2 kg^{-1}
Mass energy absorption coefficient	μ_{en}/ρ	meter squared per kilogram	$m^2\ kg^{-1}$			centimeter squared per gram	$cm^2\ g^{-1}$	0.1 m^2 kg^{-1}
Mass stopping power	S/ρ	joule meter squared per kilogram	$J\ m^2\ kg^{-1}$			MeV centimeter squared per gram	MeV $cm^2\ g^{-1}$	1.602×10^{-14} J m^2 kg^{-1}
Power	P	joule per second	$J\ s^{-1}$	watt	W	watt	W	1.0 W
Pressure	p	newton per meter squared	$N\ m^{-2}$	pascal	Pa	torr	torr	(101325/760)Pa
Radiation chemical yield	G	mole per joule	$mol\ J^{-1}$			molecules per 100 electron volts	molecules $(100\ eV)^{-1}$	1.04×10^{-7} mol J^{-1}
Specific energy	z	joule per kilogram	$J\ kg^{-1}$	gray	Gy	rad	rad	0.01 Gy

Conversion of Radioactivity Units from MBq to mCi and μCi

MBq	mCi	MBq	mCi	MBq	mCi	MBq	mCi	MBq	mCi
7000	189.	700	18.9	70	1.89	7	189	0.7	18.9
6000	162.	600	16.2	60	1.62	6	162	0.6	16.2
5000	135.	500	13.5	50	1.35	5	135	0.5	13.5
4000	108.	400	10.8	40	1.08	4	108	0.4	10.8
3000	81.	300	8.1	30	810	3	81	0.3	8.1
2000	54.	200	5.4	20	540	2	54	0.2	5.4
1000	27.	100	2.7	10	270	1	27	0.1	2.7
900	24.	90	2.4	9	240	0.9	24		
800	21.6	80	2.16	8	220	0.8	21.6		

Conversion of Radioactivity Units from mCi and μCi to MBq

mCi	MBq	mCi	MBq	mCi	MBq	μCi	MBq	μCi	MBq	μCi	MBq
200	7400	40	1480	5	185	1000	37.0	200	7.4	30	1.11
150	5550	30	1110	4	148	900	33.3	100	3.7	20	0.74
100	3700	20	740	3	111	800	29.6	90	3.33	10	0.37
90	3330	10	370	2	74.0	700	25.9	80	2.96	5	0.185
80	2960	9	333	1	37.0	600	22.2	70	2.59	2	0.074
70	2590	8	296			500	18.5	60	2.22	1	0.037
60	2220	7	259			400	14.8	50	1.85		
50	1850	6	222			300	11.1	40	1.48		

Conversion of Radioactivity Units

100 TBq (10^{14} Bq)	=	2.7 kCi (2.7×10^{3} Ci)
10 TBq (10^{13} Bq)	=	270 Ci (2.7×10^{2} Ci)
1 TBq (10^{12} Bq)	=	27 Ci (2.7×10^{1} Ci)
100 GBq (10^{11} Bq)	=	2.7 Ci (2.7×10^{0} Ci)
10 GBq (10^{10} Bq)	=	270 mCi (2.7×10^{-1} Ci)
1 GBq (10^{9} Bq)	=	27 mCi (2.7×10^{-2} Ci)
100 MBq (10^{8} Bq)	=	2.7 mCi (2.7×10^{-3} Ci)
10 MBq (10^{7} Bq)	=	270 μCi (2.7×10^{-4} Ci)
1 MBq (10^{6} Bq)	=	27 μCi (2.7×10^{-5} Ci)

100 kBq (10^{5} Bq)	=	2.7 μCi (2.7×10^{-6}Ci)
10 kBq (10^{4} Bq)	=	270 nCi (2.7×10^{-7} Ci)
1 kBq (10^{3} Bq)	=	27 nCi (2.7×10^{-8} Ci)
100 Bq (10^{2} Bq)	=	2.7 nCi (2.7×10^{-9} Ci)
10 Bq (10^{1} Bq)	=	270 pCi (2.7×10^{-10} Ci)
1 Bq (10^{0} Bq)	=	27 pCi (2.7×10^{-11} Ci)
100 mBq (10^{-1} Bq)	=	2.7 pCi (2.7×10^{-12} Ci)
10 mBq (10^{-2} Bq)	=	270 fCi (2.7×10^{-13} Ci)
1 mBq (10^{-3} Bq)	=	27 fCi (2.7×10^{-14} Ci)

Conversion of Absorbed Dose Units

SI Units		Conventional
100 Gy (10^{2} Gy)	=	10,000 rad (10^{4} rad)
10 Gy (10^{1} Gy)	=	1,000 rad (10^{3} rad)
1 Gy (10^{0} Gy)	=	100 rad (10^{2} rad)
100 mGy (10^{-1} Gy)	=	10 rad (10^{1} rad)
10 mGy (10^{-2} Gy)	=	1 rad (10^{0} rad)
1 mGy (10^{-3} Gy)	=	100 mrad (10^{-1} rad)

SI Units		Conventional
100 μGy (10^{-4} Gy)	=	10 mrad (10^{-2} rad)
10 μGy (10^{-5} Gy)	=	1 mrad (10^{-3} rad)
1 μGy (10^{-6} Gy)	=	100 μrad (10^{-4} rad)
100 nGy (10^{-7} Gy)	=	10 μrad (10^{-5} rad)
10 nGy (10^{-8} Gy)	=	1 μrad (10^{-6} rad)
1 nGy (10^{-9} Gy)	=	100 nrad (10^{-7} rad)

Conversion of Dose Equivalent Units

100 Sv (10^{2} Sv)	=	10,000 rem (10^{4} rem)
10 Sv (10^{1} Sv)	=	1,000 rem (10^{3} rem)
1 Sv (10^{0} Sv)	=	100 rem (10^{2} rem)
100 mSv (10^{-1} Sv)	=	10 rem (10^{1} rem)
10 mSv (10^{-2} Sv)	=	1 rem (10^{0} rem)
1 mSv (10^{-3} Sv)	=	100 mrem (10^{-1} rem)

100 μSv (10^{-4} Sv)	=	10 mrem (10^{-2} rem)
10 μSv (10^{-5} Sv)	=	1 mrem (10^{-3} rem)
1 μSv (10^{-6} Sv)	=	100 μrem (10^{-4} rem)
100 nSv (10^{-7} Sv)	=	10 μrem (10^{-5} rem)
10 nSv (10^{-8} Sv)	=	1 μrem (10^{-6} rem)
1 nSv (10^{-9} Sv)	=	100 nrem (10^{-7} rem)

VALUES OF THE GAS CONSTANT IN DIFFERENT UNIT SYSTEMS

In SI units the value of the gas constant, R, is:

R = 8.314472 Pa m^3 K^{-1} mol^{-1}
= 8314.472 Pa L K^{-1} mol^{-1}
= 0.08314472 bar L K^{-1} mol^{-1}

This table gives the appropriate value of R for use in the ideal gas equation, $PV = nRT$, when the variables are expressed in other units. The following conversion factors for pressure units were used in generating the table:


1 atm = 101325 Pa
1 psi = 6894.757 Pa
1 torr (mm Hg) = 133.322 Pa [at 0°C]
1 in Hg = 3386.38 Pa [at 0°C]
1 in H_2O = 249.082 Pa [at 4°C]
1 ft H_2O = 2988.98 Pa [at 4°C]

Reference

Mohr, P. J., and Taylor, B. N., "The 2002 CODATA Recommended Values of the Fundamental Physical Constants", *Rev. Mod. Phys.* 77, 1, 2005. See also <http://physics.nist.gov/constants>

Units of *V, T, n*			Units of *P*						
V	***T***	***n***	**kPa**	**atm**	**psi**	**mmHg**	**in Hg**	**in H_2O**	**ft H_2O**
ft^3	K	mol	0.2936228	0.00289784	0.0425864	2.20236	0.0867070	1.17881	0.0982351
		lb·mol	133.1851	1.31443	19.3168	998.973	39.3296	534.704	44.5587
	°R	mol	0.1631238	0.00160990	0.0236591	1.22353	0.0481706	0.654900	0.0545751
		lb·mol	73.99170	0.730242	10.7316	554.984	21.8498	297.058	24.7548
cm^3	K	mol	8314.472	82.0574	1205.91	62363.8	2455.27	33380.4	2781.71
		lb·mol	3771381	37220.6	546993	282878000	1113690	15141100	1261760
	°R	mol	4619.151	45.5875	669.951	34646.5	1364.03	18544.7	1545.39
		lb·mol	2095211	20678.1	303885	15715400	618717	8411730	700979
L	K	mol	8.314472	0.0820574	1.20591	62.3638	2.45527	33.3804	2.78171
		lb·mol	3771.381	37.2206	546.993	28287.8	1113.69	15141.1	1261.76
	°R	mol	4.619151	0.0455875	0.669951	34.6465	1.36403	18.5447	1.54539
		lb·mol	2095.211	20.6781	303.885	15715.4	618.717	8411.73	700.979
m^3	K	mol	0.008314472	0.0000820574	0.00120591	0.0623638	0.00245527	0.0333804	0.00278171
		lb·mol	3.771381	0.0372206	0.546993	28.2878	1.11369	15.1411	1.26176
	°R	mol	0.004619151	0.0000455875	0.000669951	0.0346465	0.00136403	0.0185447	0.00154539
		lb·mol	2.095211	0.0206781	0.303885	15.7154	0.618717	8.41173	0.700979

PERIODIC TABLE OF THE ELEMENTS



1 Group IA	2 IIA	3 IIIA IIIB	4 IVA IVB	5 VA VB	6 VIA VIB	7 VIIA VIIB	8	9 VIIIA VIII	10	11 IB IB	12 IIB IIB	13 IIIB IIIA	14 IVB IVA	15 VB VA	16 VIB VIA	17 VIIB VIIA	18 VIIIA	Shell
1 +1 -1 H 1.00794 1																	2 0 He 4.002602 2	K
3 +1 Li 6.941 2-1	4 +2 Be 9.012182 2-2											5 +3 B 10.811 2-3	6 +2 +4 -4 C 12.0107 2-4	7 +1 +2 +3 +4 +5 -1 -2 -3 N 14.0067 2-5	8 -2 O 15.9994 2-6	9 -1 F 18.9984032 2-7	10 0 Ne 20.1797 2-8	K-L
11 +1 Na 22.989770 2-8-1	12 +2 Mg 24.3050 2-8-2											13 +3 Al 26.981538 2-8-3	14 +2 +4 -4 Si 28.0855 2-8-4	15 +3 +5 -3 P 30.973761 2-8-5	16 +4 +6 -2 S 32.065 2-8-6	17 +1 +5 +7 -1 Cl 35.453 2-8-7	18 0 Ar 39.948 2-8-8	K-L-M
19 +1 K 39.0983 -8-8-1	20 +2 Ca 40.078 -8-8-2	21 +3 Sc 44.955910 -8-9-2	22 +2 +3 +4 Ti 47.867 -8-10-2	23 +2 +3 +4 +5 V 50.9415 -8-11-2	24 +2 +3 +6 Cr 51.9961 -8-13-1	25 +2 +3 +4 +7 Mn 54.938049 -8-13-2	26 +2 +3 Fe 55.845 -8-14-2	27 +2 +3 Co 58.933200 -8-15-2	28 +2 +3 Ni 58.6934 -8-16-2	29 +1 +2 Cu 63.546 -8-18-1	30 +2 Zn 65.409 -8-18-2	31 +3 Ga 69.723 -8-18-3	32 +2 +4 Ge 72.64 -8-18-4	33 +3 +5 -3 As 74.92160 -8-18-5	34 +4 +6 -2 Se 78.96 -8-18-6	35 +1 +5 -1 Br 79.904 -8-18-7	36 0 Kr 83.798 -8-18-8	-L-M-N
37 +1 Rb 85.4678 -18-8-1	38 +2 Sr 87.62 -18-8-2	39 +3 Y 88.90585 -18-9-2	40 +4 Zr 91.224 -18-10-2	41 +3 +5 Nb 92.90638 -18-12-1	42 +6 Mo 95.94 -18-13-1	43 +4 +6 +7 Tc (98) -18-13-2	44 +3 Ru 101.07 -18-15-1	45 +3 Rh 102.90550 -18-16-1	46 +2 +3 Pd 106.42 -18-18-0	47 +1 Ag 107.8682 -18-18-1	48 +2 Cd 112.411 -18-18-2	49 +3 In 114.818 -18-18-3	50 +2 +4 Sn 118.710 -18-18 -4	51 +3 +5 -3 Sb 121.760 -18-18-5	52 +4 +6 -2 Te 127.60 -18-18-6	53 +1 +5 +7 -1 I 126.90447 -18-18-7	54 0 Xe 131.293 -18-18-8	-M-N-O
55 +1 Cs 132.90545 -18-8-1	56 +2 Ba 137.327 -18-8-2	57* +3 La 138.9055 -18-9-2	72 +4 Hf 178.49 -32-10-2	73 +5 Ta 180.9479 -32-11-2	74 +6 W 183.84 -32-12-2	75 +4 +6 +7 Re 186.207 -32-13-2	76 +3 +4 Os 190.23 -32-14-2	77 +3 +4 Ir 192.217 -32-15-2	78 +2 +4 Pt 195.078 -32-17-1	79 +1 +3 Au 196.96655 -32-18-1	80 +1 +2 Hg 200.59 -32-18-2	81 +1 +3 Tl 204.3833 -32-18-3	82 +2 +4 Pb 207.2 -32-18-4	83 +3 +5 Bi 208.98038 -32-18-5	84 +2 +4 Po (209) -32-18-6	85 At (210) -32-18-7	86 0 Rn (222) -32-18-8	-N-O-P
87 +1 Fr (223) -18-8-1	88 +2 Ra (226) -18-8-2	89** +3 Ac (227) -18-9-2	104 +4 Rf (261) -32-10-2	105 Db (262) -32-11-2	106 Sg (266) -32-12-2	107 Bh (264) -32-13-2	108 Hs (277) -32-14-2	109 Mt (268) -32-15-2	110 Ds (271) -32-16-2	111 Rg (272)	112 Uub (285)		114 Uuq (289)		116 Uuh (289)			-O-P-Q

* Lanthanides	58 +3 +4 Ce 140.116 -19-9-2	59 +3 Pr 140.90765 -21-8-2	60 +3 Nd 144.24 -22-8-2	61 +3 Pm (145) -23-8-2	62 +2 +3 Sm 150.36 -24-8-2	63 +2 +3 Eu 151.964 -25-8-2	64 +3 Gd 157 .25 -25-9-2	65 +3 Tb 158.92534 -27-8-2	66 +3 Dy 162.500 -28-8-2	67 +3 Ho 164.93032 -29-8-2	68 +3 Er 167.259 -30-8-2	69 +3 Tm 168.93421 -31-8-2	70 +2 +3 Yb 173.04 -32-8-2	71 +3 Lu 174.967 -32-9-2				-N-O-P
** Actinides	90 +4 Th 232.0381 -18-10-2	91 +5 +4 Pa 231.03588 -20-9-2	92 +3 +4 +5 +6 U 238.02891 -21-9-2	93 +3 +4 +5 +6 Np (237) -22-9-2	94 +3 +4 +5 +6 Pu (244) -24-8-2	95 +3 +4 +5 +6 Am (243) -25-8-2	96 +3 Cm (247) -25-9-2	97 +3 +4 Bk (247) -27-8-2	98 +3 Cf (251) -28-8-2	99 +3 Es (252) -29-8-2	100 +3 Fm (257) -30-8-2	101 +2 +3 Md (258) -31-8-2	102 +2 +3 No (259) -32-8-2	103 +3 Lr (262) -32-8-3				-O-P-Q

The new IUPAC format numbers the groups from 1 to 18. The previous IUPAC numbering system and the system used by Chemical Abstracts Service (CAS) are also shown. For radioactive elements that do not occur in nature, the mass number of the most stable isotope is given in parentheses. Elements 112, 114, and 116 have been reported but not confirmed.

References

1. G. J. Leigh, Editor, *Nomenclature of Inorganic Chemistry*, Blackwell Scientific Publications, Oxford, 1990.
2. *Chemical and Engineering News*, 63(5), 27, 1985.
3. Atomic Weights of the Elements, 2001, *Pure & Appl. Chem.*, 75, 1107, 2003.

Metallic solids

Non-metallic solids

Liquids

Gases

UNITS FOR MAGNETIC PROPERTIES

Quantity	Symbol	Gaussian & cgs emu [a]	Conversion factor, C [b]	SI & rationalized mks [c]
Magnetic flux density, magnetic induction	B	gauss (G) [d]	10^{-4}	tesla (T), Wb/m^2
Magnetic flux	Φ	maxwell (Mx), $G \cdot cm^2$	10^{-8}	weber (Wb), volt second ($V \cdot s$)
Magnetic potential difference, magnetomotive force	U, F	gilbert (Gb)	$10/4\pi$	ampere (A)
Magnetic field strength, magnetizing force	H	oersted (Oe),[e] Gb/cm	$10^3/4\pi$	A/m[f]
(Volume) magnetization [g]	M	emu/cm^3 [h]	10^3	A/m
(Volume) magnetization	$4\pi M$	G	$10^3/4\pi$	A/m
Magnetic polarization, intensity of magnetization	J, I	emu/cm^3	$4\pi \times 10^{-4}$	T, Wb/m^2 [i]
(Mass) magnetization	σ, M	emu/g	1	$A \cdot m^2/kg$
			$4\pi \times 10^{-7}$	$Wb \cdot m/kg$
Magnetic moment	m	emu, erg/G	10^{-3}	$A \cdot m^2$, joule per tesla (J/T)
Magnetic dipole moment	j	emu, erg/G	$4\pi \times 10^{-10}$	$Wb \cdot m$ [i]
(Volume) susceptibility	χ, κ	dimensionless, emu/cm^3	4π	dimensionless
			$(4\pi)^2 \times 10^{-7}$	henry per meter (H/m), Wb/(A·m)
(Mass) susceptibility	χ_ρ, κ_ρ	cm^3/g, emu/g	$4\pi \times 10^{-3}$	m^3/kg
			$(4\pi)^2 \times 10^{-10}$	$H \cdot m^2/kg$
(Molar) susceptibility	χ_{mol}, κ_{mol}	cm^3/mol, emu/mol	$4\pi \times 10^{-6}$	m^3/mol
			$(4\pi)^2 \times 10^{-13}$	$H \cdot m^2/mol$
Permeability	μ	dimensionless	$4\pi \times 10^{-7}$	H/m, Wb/(A·m)
Relative permeability[j]	μ_r	not defined		dimensionless
(Volume) energy density, energy product [k]	W	erg/cm^3	10^{-1}	J/m^3
Demagnetization factor	D, N	dimensionless	$1/4\pi$	dimensionless

[a] Gaussian units and cgs emu are the same for magnetic properties. The defining relation is $B = H + 4\pi M$.

[b] Multiply a number in Gaussian units by C to convert it to SI (e.g., $1\ G \times 10^{-4}\ T/G = 10^{-4}\ T$).

[c] SI (*Système International d'Unités*) has been adopted by the National Bureau of Standards. Where two conversion factors are given, the upper one is recognized under, or consistent with, SI and is based on the definition $B = \mu_0(H + M)$, where $\mu_0 = 4\pi \times 10^{-7}$ H/m. The lower one is not recognized under SI and is based on the definition $B = \mu_0 H + J$, where the symbol I is often used in place of J.

[d] 1 gauss = 10^5 gamma (γ).

[e] Both oersted and gauss are expressed as $cm^{-1/2} \cdot g^{1/2} \cdot s^{-1}$ in terms of base units.

[f] A/m was often expressed as "ampere–turn per meter" when used for magnetic field strength.

[g] Magnetic moment per unit volume.

[h] The designation "emu" is not a unit.

[i] Recognized under SI, even though based on the definition $B = \mu_0 H + J$. See footnote *c*.

[j] $\mu_r = \mu/\mu_0 = 1+\chi$, all in SI. μ_r is equal to Gaussian μ.

[k] $B \cdot H$ and $\mu_0\, M \cdot H$ have SI units J/m^3; $M \cdot H$ and $B \cdot H/4\pi$ have Gaussian units erg/cm^3.

R. B. Goldfarb and F. R. Fickett, U.S. Department of Commerce, National Bureau of Standards, Boulder, Colorado 80303, March 1985, NBS Special Publication 696. For sale by the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402.

SYMBOLS AND TERMINOLOGY FOR PHYSICAL AND CHEMICAL QUANTITIES

The International Organization for Standardization (ISO), International Union of Pure and Applied Chemistry (IUPAC), and the International Union of Pure and Applied Physics (IUPAP) have jointly developed a set of recommended symbols for physical and chemical quantities. Consistent use of these recommended symbols helps assure unambiguous scientific communication. The list below is reprinted from Reference 1 with permission from IUPAC. Full details may be found in the following references:

1. Ian Mills, Ed., *Quantities, Units, and Symbols in Physical Chemistry,* Blackwell Scientific Publications, Oxford, 1988.
2. E. R. Cohen and P. Giacomo, *Symbols, Units, Nomenclature, and Fundamental Constants in Physics*, Document IUPAP–25, 1987; also published in *Physica*, 146A 1–68, 1987.
3. *ISO Standards Handbook 2: Units of Measurement*, International Organization of Standardization, Geneva, 1982.

GENERAL RULES

The value of a physical quantity is expressed as the product of a numerical value and a unit, e.g.:

$T = 300$ K
$V = 26.2$ cm^3
$C_p = 45.3$ J mol^{-1} K^{-1}

The symbol for a physical quantity is always given in italic (sloping) type, while symbols for units are given in roman type. Column headings in tables and axis labels on graphs may conveniently be written as the physical quantity symbol divided by the unit symbol, e.g.:

T/K
V/cm^3
$C_p/\mathrm{J\ mol^{-1}\ K^{-1}}$

The values in the table or graph axis are then pure numbers. Subscripts to symbols for physical quantities should be italic if the subscript refers to another physical quantity or to a number, e.g.:

C_p – heat capacity at constant pressure
B_n – nth virial coefficient

Subscripts which have other meanings should be in roman type:

m_{p} – mass of the proton
E_{k} – kinetic energy

The following tables give the recommended symbols for the major classes of physical and chemical quantities. The expression in the Definition column is given as an aid in identifying the quantity but is not necessarily the complete or unique definition. The SI Unit gives one (not necessarily unique) expression for the coherent SI unit for the quantity. Other equivalent unit expressions, including those which involve SI prefixes, may be used.

Name	Symbol	Definition	SI unit
Space and Time			
cartesian space coordinates	x, y, z		m
spherical polar coordinates	r, θ, ϕ		m, 1, 1
generalized coordinate	q, q_i		(varies)
position vector	r	$r = xi + y\boldsymbol{j} + z\boldsymbol{k}$	m
length	l		m
special symbols:			
height	h		
breadth	b		
thickness	d, δ		
distance	d		
radius	r		
diameter	d		
path length	s		
length of arc	s		
area	A, A_s, S		m^2
volume	$V, (v)$		m^3
plane angle	$\alpha, \beta, \gamma, \theta, \phi \ldots$	$\alpha = s/r$	rad, 1
solid angle	ω, Ω	$\omega = A/r^2$	sr, 1
time	t		s
period	T	$T = t/N$	s
frequency	ν, f	$\nu = 1/T$	Hz
circular frequency, angular frequency	ω	$\omega = 2\pi\nu$	rad s^{-1}, s^{-1}
characteristic time interval, relaxation time, time constant	τ, T	$\tau = \lvert \mathrm{d}t/\mathrm{d}\ln x \rvert$	s
angular velocity	ω	$\omega = \mathrm{d}\phi/\mathrm{d}t$	rad s^{-1}, s^{-1}
velocity	$\boldsymbol{v}, \boldsymbol{u}, \boldsymbol{w}, \boldsymbol{c}, \dot{\boldsymbol{r}}$	$\boldsymbol{v} = \mathrm{d}\boldsymbol{r}/\mathrm{d}t$	m s^{-1}

Name	Symbol	Definition	SI unit
speed	v, u, w, c	$v = \lvert \boldsymbol{v} \rvert$	$\mathrm{m\ s^{-1}}$
acceleration	$\boldsymbol{a}, (g)$	$\boldsymbol{a} = \mathrm{d}\boldsymbol{v}/\mathrm{d}t$	$\mathrm{m\ s^{-2}}$
Classical Mechanics			
mass	m		kg
reduced mass	μ	$\mu = m_1 m_2/(m_1 + m_2)$	kg
density, mass density	ρ	$\rho = m/V$	$\mathrm{kg\ m^{-3}}$
relative density	d	$d = \rho/\rho$	1
surface density	ρ_A, ρ_S	$\rho_A = m/A$	$\mathrm{kg\ m^{-2}}$
specific volume	v	$v = V/m = 1/\rho$	$\mathrm{m^3\ kg^{-1}}$
momentum	$\boldsymbol{p}$	$\boldsymbol{p} = m\boldsymbol{v}$	$\mathrm{kg\ m\ s^{-1}}$
angular momentum, action	$\boldsymbol{L}$	$\boldsymbol{L} = \boldsymbol{r} \times \boldsymbol{p}$	J s
moment of inertia	I, J	$I = \Sigma m_i r_i^2$	$\mathrm{kg\ m^2}$
force	$\boldsymbol{F}$	$\boldsymbol{F} = \mathrm{d}\boldsymbol{p}/\mathrm{d}t = m\boldsymbol{a}$	N
torque, moment of a force	$\boldsymbol{T}, (\boldsymbol{M})$	$\boldsymbol{T} = \boldsymbol{r} \times \boldsymbol{F}$	N m
energy	E		J
potential energy	E_p, V, Φ	$E_p = \int \boldsymbol{F} \cdot d\boldsymbol{s}$	J
kinetic energy	E_k, T, K	$E_k = 1/2mv^2$	J
work	W, w	$W = \int \boldsymbol{F} \cdot d\boldsymbol{s}$	J
Hamilton function	H	$H(q, p) = T(q, p) + V(q)$	J
Lagrange function	L	$L(q, \dot{q}) = T(q, \dot{q}) - V(q)$	J
pressure	p, P	$p = F/A$	Pa, $\mathrm{N\ m^{-2}}$
surface tension	γ, σ	$\gamma = \mathrm{d}W/\mathrm{d}A$	$\mathrm{N\ m^{-1}}$, $\mathrm{J\ m^{-2}}$
weight	$G, (W, P)$	$G = mg$	N
gravitational constant	G	$F = Gm_1 m_2/r^2$	$\mathrm{N\ m^2\ kg^{-2}}$
normal stress	σ	$\sigma = F/A$	Pa
shear stress	τ	$\tau = F/A$	Pa
linear strain, relative elongation	ε, e	$\varepsilon = \Delta l/l$	1
modulus of elasticity, Young's modulus	E	$E = \sigma/\varepsilon$	Pa
shear strain	γ	$\gamma = \Delta x/d$	1
shear modulus	G	$G = \tau/\gamma$	Pa
volume strain, bulk strain	θ	$\theta = \Delta V/V_0$	1
bulk modulus, compression modulus	K	$K = -V_0(\mathrm{d}p/\mathrm{d}V)$	Pa
viscosity, dynamic viscosity	η, μ	$\tau_{x,z} = \eta(\mathrm{d}v_x/\mathrm{d}z)$	Pa s
fluidity	ϕ	$\phi = 1/\eta$	$\mathrm{m\ kg^{-1}\ s}$
kinematic viscosity	ν	$\nu = \eta/\rho$	$\mathrm{m^2\ s^{-1}}$
friction coefficient	$\mu, (f)$	$F_{\mathrm{frict}} = \mu F_{\mathrm{norm}}$	1
power	P	$P = \mathrm{d}W/\mathrm{d}t$	W
sound energy flux	P, P_a	$P = \mathrm{d}E/\mathrm{d}t$	W
acoustic factors			
reflection factor	ρ	$\rho = P_r/P_0$	1
acoustic absorption factor	$\alpha_a, (\alpha)$	$\alpha_a = 1 - \rho$	1
transmission factor	τ	$\tau = P_{\mathrm{tr}}/P_0$	1
dissipation factor	δ	$\delta = \alpha_a - \tau$	1
Electricity and Magnetism			
quantity of electricity, electric charge	Q		C
charge density	ρ	$\rho = Q/V$	$\mathrm{C\ m^{-3}}$
surface charge density	σ	$\sigma = Q/A$	$\mathrm{C\ m^{-2}}$
electric potential	V, ϕ	$V = \mathrm{d}W/\mathrm{d}Q$	V, $\mathrm{J\ C^{-1}}$
electric potential difference	$U, \Delta V, \Delta\phi$	$U = V_2 - V_1$	V
electromotive force	E	$E = \int(\boldsymbol{F}/Q) \cdot d\boldsymbol{s}$	V
electric field strength	$\boldsymbol{E}$	$\boldsymbol{E} = \boldsymbol{F}/Q = -\ \mathrm{grad}\ V$	$\mathrm{V\ m^{-1}}$
electric flux	Ψ	$\Psi = \int \boldsymbol{D} \cdot \mathrm{d}\boldsymbol{A}$	C
electric displacement	$\boldsymbol{D}$	$\boldsymbol{D} = \varepsilon\boldsymbol{E}$	$\mathrm{C\ m^{-2}}$
capacitance	C	$C = Q/U$	F, $\mathrm{C\ V^{-1}}$
permittivity	ε	$\boldsymbol{D} = \varepsilon\boldsymbol{E}$	$\mathrm{F\ m^{-1}}$
permittivity of vacuum	ε_0	$\varepsilon_0 = \mu_0^{-1} c_0^{-2}$	$\mathrm{F\ m^{-1}}$
relative permittivity	ε_r	$\varepsilon_r = \varepsilon/\varepsilon_0$	1
dielectric polarization (dipole moment per volume)	$\boldsymbol{P}$	$\boldsymbol{P} = \boldsymbol{D} - \varepsilon_0\boldsymbol{E}$	$\mathrm{C\ m^{-2}}$
electric susceptibility	χ_e	$\chi_e = \varepsilon r - 1$	1
electric dipole moment	$\boldsymbol{p}, \boldsymbol{\mu}$	$\boldsymbol{p} = Q\boldsymbol{r}$	C m

Name	Symbol	Definition	SI unit
electric current	I	$I = \mathrm{d}Q/\mathrm{d}t$	A
electric current density	$\boldsymbol{j}, \boldsymbol{J}$	$I = \int \boldsymbol{j} \cdot \mathrm{d}\boldsymbol{A}$	A m^{-2}
magnetic flux density, magnetic induction	$\boldsymbol{B}$	$\boldsymbol{F} = Q\boldsymbol{v} \times \boldsymbol{B}$	T
magnetic flux	Φ	$\Phi = \int \boldsymbol{B} \cdot \mathrm{d}\boldsymbol{A}$	A m^{-2}
magnetic field strength	$\boldsymbol{H}$	$\boldsymbol{B} = \mu \boldsymbol{H}$	A m^{-2}
permeability	μ	$\boldsymbol{B} = \mu \boldsymbol{H}$	N A^{-2}, H m^{-1}
permeability of vacuum	μ_0		H m^{-1}
relative permeability	μ_r	$\mu_r = \mu/\mu_0$	1
magnetization (magnetic dipole moment per volume)	$\boldsymbol{M}$	$\boldsymbol{M} = \boldsymbol{B}/\mu_0 - H$	A m^{-1}
magnetic susceptibility	$\chi, \kappa, (\chi_m)$	$\chi = \mu_r - 1$	1
molar magnetic susceptibility	χ_m	$\chi_m = V_m \chi$	m^3 mol^{-1}
magnetic dipole moment	$\boldsymbol{m}, \boldsymbol{\mu}$	$E_p = -\boldsymbol{m} \cdot \boldsymbol{B}$	A m^2, J T^{-1}
electrical resistance	R	$R = U/I$	Ω
conductance	G	$G = 1/R$	S
loss angle	δ	$\delta = (\pi/2) + \phi_I - \phi_U$	1, rad
reactance	X	$X = (U/I)\sin\delta$	Ω
impedance (complex impedance)	Z	$Z = R + iX$	Ω
admittance (complex admittance)	Y	$Y = 1/Z$	S
susceptance	B	$Y = G + \mathrm{i}B$	S
resistivity	ρ	$\rho = E/j$	Ω m
conductivity	κ, γ, σ	$\kappa = 1/\rho$	S m^{-1}
self–inductance	L	$E = -L(\mathrm{d}I/\mathrm{d}t)$	H
mutual inductance	M, L_{12}	$E_1 = L_{12}(\mathrm{d}I_2/\mathrm{d}t)$	H
magnetic vector potential	$\boldsymbol{A}$	$\boldsymbol{B} = \nabla \times \boldsymbol{A}$	Wb m^{-1}
Poynting vector	$\boldsymbol{S}$	$\boldsymbol{S} = \boldsymbol{E} \times \boldsymbol{H}$	W m^{-2}
Quantum Mechanics			
momentum operator	$\hat{\boldsymbol{p}}$	$\hat{\boldsymbol{p}} = -\mathrm{i}h\nabla$	m^{-1} J s
kinetic energy operator	$\hat{T}$	$\hat{T} = -(h^2/2m)\nabla^2$	J
Hamiltonian operator	$\hat{H}$	$\hat{H} = \hat{T} + V$	J
wavefunction, state function	Ψ, ψ, ϕ	$\hat{H}\psi = E\psi$	(m$^{-3/2}$)
probability density	P	$P = \psi^*\psi$	(m^{-3})
charge density of electrons	ρ	$\rho = -eP$	(C m^{-3})
probability current density	$\boldsymbol{S}$	$\boldsymbol{S} = -i\hbar(\psi^*\nabla\psi - \psi\nabla\psi^*)/2m_e$	(m^{-2} s^{-1})
electric current density of electrons	$\boldsymbol{j}$	$\boldsymbol{j} = -e\boldsymbol{S}$	(A m^{-2})
matrix element of operator Â	$A_{ij}, \langle i\|\hat{A}\|j\rangle$	$A_{ij} = \int \psi_i^* \hat{A} \psi_j \mathrm{d}\tau$	(varies)
expectation value of operator Â	$\langle A\rangle, \bar{A}$	$\langle A\rangle = \int \psi^* \hat{A} \Psi \mathrm{d}\tau$	(varies)
hermitian conjugate of Â	$\hat{A}^\dagger$	$(\hat{A}^\dagger)_{ij} = (A_{ji})^*$	(varies)
commutator of Â and $\hat{B}$	$[\hat{A}, \hat{B}], [\hat{A}, \hat{B}]_-$	$[\hat{A}\,\hat{B}] = \hat{A}\hat{B} - \hat{B}\hat{A}$	(varies)
anticommutator	$[\hat{A}, \hat{B}]_+$	$[\hat{A}, \hat{B}]_+ = \hat{A}\hat{B} + \hat{B}\hat{A}$	(varies)
spin wavefunction	$\alpha; \beta$		1
coulomb integral	H_{AA}	$H_{AA} = \int \psi_A^* \hat{H} \psi_A \mathrm{d}\tau$	J
resonance integral	H_{AB}	$H_{AB} = \int \psi_A^* \hat{H} \psi_B \mathrm{d}\tau$	J
overlap integral	S_{AB}	$S_{AB} = \int \psi_A^* \psi_B \mathrm{d}\tau$	1
Atoms and Molecules			
nucleon number, mass number	A		1
proton number, atomic number	Z		1
neutron number	N	$N = A - Z$	1
electron rest mass	m_e		kg
mass of atom, atomic mass	m_a, m		kg
atomic mass constant	m_u	$m_u = m_a(^{12}C)/12$	kg
mass excess	Δ	$\Delta = m_a - Am_u$	kg
elementary charge, proton charge	e		C
Planck constant	h		J s
Planck constant/2π	$\hbar$	$\hbar = h/2\pi$	J s
Bohr radius	a_0	$a_0 = 4\pi\varepsilon_0\hbar^2/m_e e^2$	m
Hartree energy	E_h	$E_h = \hbar^2/m_e a_0^2$	J
Rydberg constant	R_∞	$R_\infty = E_h/2hc$	m^{-1}
fine structure constant	α	$\alpha = e^2/4\pi\varepsilon_0\hbar c$	1

Name	Symbol	Definition	SI unit
ionization energy	E_i		J
electron affinity	E_{ea}		J
dissociation energy	E_d, D		J
from the ground state	D_0		J
from the potential minimum	D_e		J
principal quantum number (H atom)	n	$E = -hcR/n^2$	1
angular momentum quantum numbers	see under Spectroscopy		
magnetic dipole moment of a molecule	$\boldsymbol{m}$,$\boldsymbol{\mu}$	$E_p = -\boldsymbol{m}\cdot\boldsymbol{B}$	J T^{-1}
magnetizability of a molecule	ξ	$\boldsymbol{m} = \xi B$	J T^{-2}
Bohr magneton	μ_B	$\mu_B = e\hbar/2m_e$	J T^{-1}
nuclear magneton	μ_N	$\mu_N = (m_e/m_p)\mu_B$	J T^{-1}
magnetogyric ratio (gyromagnetic ratio)	γ	$\gamma = \mu/L$	C kg^{-1}
g factor	g		1
Larmor circular frequency	ω_L	$\omega_L = (e/2m)B$	s^{-1}
Larmor frequency	ν_L	$\nu_L = \omega_L/2\pi$	Hz
longitudinal relaxation time	T_1		s
transverse relaxation time	T_2		s
electric dipole moment of a molecule	$\boldsymbol{p}$, $\boldsymbol{\mu}$	$E_p = -\boldsymbol{p}\cdot\boldsymbol{E}$	C m
quadrupole moment of a molecule	$\boldsymbol{Q}$; $\boldsymbol{\Theta}$	$E_p = 1/2\boldsymbol{Q}\colon\boldsymbol{V}'' = 1/3\boldsymbol{\Theta}\colon\boldsymbol{V}''$	C m^2
quadrupole moment of a nucleus	eQ	$eQ = 2\cdot\langle\Theta_{ZZ}\rangle$	C m^2
electric field gradient tensor	$\boldsymbol{q}$	$q_{\alpha\beta} = -\partial^2 V/\partial\alpha\partial\beta$	V m^{-2}
quadrupole interaction energy tensor	$\boldsymbol{\chi}$	$\chi_{\alpha\beta} = eQq_{\alpha\beta}$	J
electric polarizability of a molecule	α	p (induced) $= \alpha E$	C m^2 V^{-1}
activity (of a radioactive substance)	$\boldsymbol{A}$	$A = -\mathrm{d}N_B/\mathrm{d}t$	Bq
decay (rate) constant, disintegration (rate) constant	λ	$A = \gamma N_B$	s^{-1}
half life	$t_{1/2}$, $T_{1/2}$		s
mean life	τ		s
level width	Γ	$\Gamma = \hbar/\tau$	J
disintegration energy	Q		J
cross section (of a nuclear reaction)	σ		m^2
Spectroscopy			
total term	T	$T = E_{tot}/hc$	m^{-1}
transition wavenumber	$\tilde{\nu}$, (ν)	$\tilde{\nu} = T' - T''$	m^{-1}
transition frequency	ν	$\nu = (E' - E'')/h$	Hz
electronic term	T_e	$T_e = E_e/hc$	m^{-1}
vibrational term	G	$G = E_{vib}/hc$	m^{-1}
rotational term	F	$F = E_{rot}/hc$	m^{-1}
spin orbit coupling constant	A	$T_{s.o.} = A\langle\hat{\boldsymbol{L}}\cdot\hat{\boldsymbol{S}}\rangle$	m^{-1}
principal moments of inertia	I_A; I_B; I_C	$I_A \le I_B \le I_C$	kg m^2
rotational constants,			
in wavenumber	$\tilde{A}$; $\tilde{B}$; $\tilde{C}$	$\tilde{A} = h/8\pi^2 cI_A$	m^{-1}
in frequency	A; B; C	$A = h/8\pi^2 I_A$	Hz
inertial defect	Δ	$\Delta = I_C - I_A - I_B$	kg m^2
asymmetry parameter	κ	$\kappa = \dfrac{(2B - A - C)}{(A - C)}$	1
centrifugal distortion constants,			
S reduction	D_J; D_{JK}; D_K; d_1; d_2		m^{-1}
A reduction	Δ_J; Δ_{JK}; Δ_K; δ_J; δ_K		m^{-1}
harmonic vibration wavenumber	ω_e; ω_r		m^{-1}
vibrational anharmonicity constant	$\omega_e x_e$; x_{rs}; $g_{tt'}$		m^{-1}
vibrational quantum numbers	v_r; l_t		1
Coriolis zeta constant	ζ_{rs}^{α}		1
angular momentum quantum numbers	see additional information below		
degeneracy, statistical weight	g, d, β		1
electric dipole moment of a molecule	$\boldsymbol{p}$, $\boldsymbol{\mu}$	$E_p = -\boldsymbol{p}\cdot\boldsymbol{E}$	C m
transition dipole moment of a molecule	$\boldsymbol{M}$, $\boldsymbol{R}$	$\boldsymbol{M} = \int\psi'\boldsymbol{p}\psi''\mathrm{d}\tau$	C m
molecular geometry, interatomic distances,			
equilibrium distance	r_e		m
zero–point average distance	r_z		m

Name	Symbol	Definition	SI unit
ground state distance	r_0		m
substitution structure distance	r_s		m
vibrational coordinates,			
internal coordinates	R_i, r_i, θ_j, *etc.*		(varies)
symmetry coordinates	S_i		(varies)
normal coordinates			
mass adjusted	Q_r		$kg^{1/2}$ m
dimensionless	q_r		1
vibrational force constants,			
diatomic	f, (k)	$f = \partial^2 V/\partial r^2$	J m^{-2}
polyatomic,			
internal coordinates	f_{ij}	$f_{ij} = \partial^2 V/\partial r_i \partial r_j$	(varies)
symmetry coordinates	F_{ij}	$F_{ij} = \partial^2 V/\partial S_i \partial S_j$	(varies)
dimensionless normal coordinates	$\phi_{rst...}$, $k_{rst...}$		m^{-1}
nuclear magnetic resonance (NMR),			
magnetogyric ratio	γ	$\gamma = \mu/I\hbar$	C kg^{-1}
shielding constant	σ_A	$B_A = (1 - \sigma_A)B$	1
chemical shift, δ scale	δ	$\delta = 10^6(\nu - \nu_0)/\nu_0$	1
(indirect) spin–spin coupling constant	J_{AB}	$\hat{H}/h = J_{AB}\hat{I}_A \cdot \hat{I}_B$	Hz
direct (dipolar) coupling constant	D_{AB}		Hz
longitudinal relaxation time	T_1		s
transverse relaxation time	T_2		s
electron spin resonance, electron paramagnetic resonance (ESR, EPR),			
magnetogyric ratio	γ	$\gamma = \mu/s\hbar$	C kg^{-1}
g factor	g	$h\nu = g\mu_B B$	1
hyperfine coupling constant,			
in liquids	a, A	$\hat{H}_{hfs}/h = a\hat{S} \cdot \hat{I}$	Hz
in solids	T	$\hat{H}_{hfs}/h = \hat{S} \cdot T \cdot \hat{I}$	Hz

Angular momentum	Operator symbol	Quantum number symbol: Total	*Z*–axis	*z*-axis
electron orbital	$\hat{\boldsymbol{L}}$	L	M_L	Λ
one electron only	$\hat{l}$	l	m_l	λ
electron spin	$\hat{S}$	S	M_S	Σ
one electron only	$\hat{s}$	s	m_s	σ
electron orbital + spin	$\hat{\boldsymbol{L}} + \hat{S}$			$\Omega=\Lambda+\Sigma$
nuclear orbital (rotational)	$\hat{R}$	R		K_R, k_R
nuclear spin	$\hat{I}$	I	M_I	
internal vibrational				
spherical top	$\hat{l}$	$l(l\zeta)$		K_l
other	$\hat{\jmath}$, $\hat{\pi}$			$l(l\zeta)$
sum of $R + L(+ j)$	$\hat{N}$	N		K, k
sum of $N + S$	$\hat{J}$	J	M_J	K, k
sum of $J + I$	$\hat{F}$	F	M_F	

Electromagnetic Radiation

Name	Symbol	Definition	SI unit
wavelength	λ		m
speed of light			
in vacuum	c_0		m s^{-1}
in a medium	c	$c = c_0/n$	m s^{-1}
wavenumber in vacuum	$\tilde{\nu}$	$\tilde{\nu} = \nu/c_0 = 1/n\lambda$	m^{-1}
wavenumber (in a medium)	σ	$\sigma = 1/\lambda$	m^{-1}
frequency	ν	$\nu = c/\lambda$	Hz
circular frequency, pulsatance	ω	$\omega = 2\pi\nu$	s^{-1}, rad s^{-1}
refractive index	n	$n = c_0/c$	1
Planck constant	h		J s

Name	Symbol	Definition	SI unit
Planck constant/2π	$\hbar$	$\hbar = h/2\pi$	J s
radiant energy	Q, W		J
radiant energy density	ρ, w	$\rho = Q/V$	J m^{-3}
spectral radiant energy density			
in terms of frequency	ρ_ν, w_ν	$\rho = \mathrm{d}\rho/\mathrm{d}\nu$	J m^{-3} Hz^{-1}
in terms of wavenumber	$\rho_{\tilde\nu}$, $w_{\tilde\nu}$	$\rho_{\tilde\nu} = \mathrm{d}\rho / \mathrm{d}\tilde\nu$	J m^{-2}
in terms of wavelength	ρ_λ, w_λ	$\rho_\lambda = \mathrm{d}\rho/\mathrm{d}\lambda$	J m^{-4}
Einstein transition probabilities			
spontaneous emission	A_{nm}	$\mathrm{d}N_n/\mathrm{d}t = -A_{nm}N_n$	s^{-1}
stimulated emission	B_{nm}	$\mathrm{d}N_n/\mathrm{d}t = -\rho_{\tilde\nu}(\tilde\nu_{\mathrm{nm}}) \times B_{nm}N_n$	s kg^{-1}
stimulated absorption	B_{mn}	$\mathrm{d}N_n/\mathrm{d}t = -\rho_{\tilde\nu}(\tilde\nu_{\mathrm{nm}})\, B_{mn}N_m$	s kg^{-1}
radiant power, radiant energy per time	Φ, P	$\Phi = \mathrm{d}Q/\mathrm{d}t$	W
radiant intensity	I	$I = \mathrm{d}\Phi/\mathrm{d}\Omega$	W sr^{-1}
radiant exitance (emitted radiant flux)	M	$M = \mathrm{d}\Phi/\mathrm{d}A_{\mathrm{source}}$	W m^{-2}
irradiance, (radiant flux received)	E, (I)	$E = \mathrm{d}\Phi/\mathrm{d}A$	W m^{-2}
emittance	ε	$\varepsilon = M/M_{\mathrm{bb}}$	1
Stefan–Boltzmann constant	σ	$M_{\mathrm{bb}} = \sigma T^4$	W m^{-2} K^{-4}
first radiation constant	c_1	$c_1 = 2\pi h c_0^2$	W m^2
second radiation constant	c_2	$c_2 = hc_0/k$	K m
transmittance, transmission factor	τ, T	$\tau = \Phi_{\mathrm{tr}}/\Phi_0$	1
absorptance, absorption factor	α	$\alpha = \Phi_{\mathrm{abs}}/\Phi_0$	1
reflectance, reflection factor	ρ	$\rho = \Phi_{\mathrm{refl}}/\Phi_0$	1
(decadic) absorbance	A	$A = -\lg(1-\alpha_i)$	1
napierian absorbance	B	$B = -\ln(1-\alpha_i)$	1
absorption coefficient			
(linear) decadic	a, K	$a = A/l$	m^{-1}
(linear) napierian	α	$\alpha = B/l$	m^{-1}
molar (decadic)	ε	$\varepsilon = a/c = A/cl$	m^2 mol^{-1}
molar napierian	κ	$\kappa = \alpha/c = B/cl$	m^2 mol^{-1}
absorption index	k	$k = \alpha/4\pi\tilde\nu$	1
complex refractive index	$\hat n$	$\hat n = n + \mathrm{i}k$	1
molar refraction	R, R_m	$R = \dfrac{(n^2-1)}{(n^2+2)}V_m$	m^3 mol^{-1}
angle of optical rotation	α		1, rad
Solid State			
lattice vector	$\boldsymbol{R}$, $\boldsymbol{R_0}$		m
fundamental translation vectors for the crystal lattice	$\boldsymbol{a_1}$; $\boldsymbol{a_2}$; $\boldsymbol{a_3}$, $\boldsymbol{a}$; $\boldsymbol{b}$; $\boldsymbol{c}$	$\boldsymbol{R} = n_1\boldsymbol{a_1} + n_2\boldsymbol{a_2} + n_3\boldsymbol{a_3}$	m
(circular) reciprocal lattice vector	$\boldsymbol{G}$	$\boldsymbol{G}\cdot\boldsymbol{R} = 2\pi m$	m^{-1}
(circular) fundamental translation vectors for the reciprocal lattice	$\boldsymbol{b_1}$; $\boldsymbol{b_2}$; $\boldsymbol{b_3}$, $\boldsymbol{a}^*$; $\boldsymbol{b}^*$; $\boldsymbol{c}^*$	$\boldsymbol{a_i}\cdot\boldsymbol{b_k} = 2\pi\delta_{ik}$	m^{-1}
lattice plane spacing	d		m
Bragg angle	θ	$n\lambda = 2d\sin\theta$	1, rad
order of reflection	n		1
order parameters			
short range	σ		1
long range	s		1
Burgers vector	$\boldsymbol{b}$		m
particle position vector	$\boldsymbol{r}$, $\boldsymbol{R_j}$		m
equilibrium position vector of an ion	$\boldsymbol{R_0}$		m
displacement vector of an ion	$\boldsymbol{u}$	$\boldsymbol{u} = \boldsymbol{R} - \boldsymbol{R_0}$	m
Debye–Waller factor	B, D		1
Debye circular wavenumber	q_D		m^{-1}
Debye circular frequency	ω_D		s^{-1}
Grüneisen parameter	γ, Γ	$\gamma = \alpha V/\kappa C_v$	1
Madelung constant	α, $\mathcal{M}$	$E_{\mathrm{coul}} = \dfrac{\alpha N_{\mathrm{A}} z_+ z_- e^2}{4\pi\varepsilon_0 R_0}$	1
density of states	N_E	$N_E = \mathrm{d}N(E)/\mathrm{d}E$	J^{-1} m^{-3}
(spectral) density of vibrational modes	N_ω, g	$N_\omega = \mathrm{d}N(\omega)/\mathrm{d}\omega$	s m^{-3}

Name	Symbol	Definition	SI unit
resistivity tensor	ρ_{ik}	$\boldsymbol{E} = \boldsymbol{\rho} \cdot \boldsymbol{j}$	Ω m
conductivity tensor	σ_{ik}	$\sigma = \rho^{-1}$	S m^{-1}
thermal conductivity tensor	λ_{ik}	$\boldsymbol{J}_q = -\boldsymbol{\lambda} \cdot \mathrm{grad}\ T$	W m^{-1} K^{-1}
residual resistivity	ρ_R		Ω m
relaxation time	τ	$\tau = l/v_F$	s
Lorenz coefficient	L	$L = \lambda/\sigma T$	V^2 K^{-2}
Hall coefficient	A_H, $\boldsymbol{R}_H$	$\boldsymbol{E} = \boldsymbol{\rho} \cdot \boldsymbol{j} + R_H(\boldsymbol{B} \times \boldsymbol{j})$	m^3 C^{-1}
thermoelectric force	E		V
Peltier coefficient	Π		V
Thomson coefficient	μ, (τ)		V K^{-1}
work function	Φ	$\Phi = E_\infty - E_F$	J
number density, number concentration	n, (p)		m^{-3}
gap energy	E_g		J
donor ionization energy	E_d		J
acceptor ionization energy	E_a		J
Fermi energy	E_F, ε_F		J
circular wave vector, propagation vector	k, $\boldsymbol{q}$	$k = 2\pi/\lambda$	m^{-1}
Bloch function	$u_k(\boldsymbol{r})$	$\psi(\boldsymbol{r}) = u_k(\boldsymbol{r}) \exp(\mathrm{i}\boldsymbol{k} \cdot \boldsymbol{r})$	$m^{-3/2}$
charge density of electrons	ρ	$\rho(\boldsymbol{r}) = -e\psi^*(\boldsymbol{r})\psi(\boldsymbol{r})$	C m^{-3}
effective mass	m^*		kg
mobility	μ	$\mu = v_{drift}/E$	m^2 V^{-1} s^{-1}
mobility ratio	b	$b = \mu_n/\mu_p$	1
diffusion coefficient	D	$\mathrm{d}N/\mathrm{d}t = -DA(\mathrm{d}n/\mathrm{d}x)$	m^2 s^{-1}
diffusion length	L	$L = \sqrt{D\tau}$	m
characteristic (Weiss) temperature	θ, θ_w		K
Curie temperature	T_C		K
Néel temperature	T_N		K
Statistical Thermodynamics			
number of entities	N		1
number density of entities, number concentration	n, C	$n = N/V$	m^{-3}
Avogadro constant	L, N_A		mol^{-1}
Boltzmann constant	k, k_B		J K^{-1}
gas constant (molar)	R	$R = Lk$	J K^{-1} mol^{-1}
molecular position vector	$\boldsymbol{r}$ (x, y, z)		m
molecular velocity vector	$\boldsymbol{c}(c_x, c_y, c_z)$, $\boldsymbol{u}(u_x, u_y, u_z)$	$\boldsymbol{c} = \mathrm{d}\boldsymbol{r}/\mathrm{d}t$	m s^{-1}
molecular momentum vector	$\boldsymbol{p}(p_x, p_y, p_z)$	$\boldsymbol{p} = m\boldsymbol{c}$	kg m s^{-1}
velocity distribution function (Maxwell)	$f(c_x)$	$f(c_x) = (m/2\pi kT)^{1/2} \times \exp(-mc_x^2/2kT)$	m^{-1} s
speed distribution function (Maxwell–Boltzmann)	$F(c)$	$F(c) = (m/2\pi kT)^{3/2} \times 4\pi c^2 \exp(-mc^2/2kT)$	m^{-1} s
average speed	$\bar{c}$, $\bar{u}$, $\langle c \rangle$, $\langle u \rangle$	$\bar{c} = \int cF(c)\mathrm{d}c$	m s^{-1}
generalized coordinate	q		(m)
generalized momentum	p	$p = \partial L/\partial \dot{q}$	(kg m s^{-1})
volume in phase space	Ω	$\Omega = (1/h)\int p\mathrm{d}q$	1
probability	P		1
statistical weight, degeneracy	g, d, W, ω, β		1
density of states	$\rho(E)$	$\rho(E) = \mathrm{d}N/\mathrm{d}E$	J^{-1}
partition function, sum over states, for a single molecule	q, z	$q = \sum_i g_i \exp(-\varepsilon_i/kT)$	1
for a canonical ensemble (system, or assembly)	Q, Z		1
microcanonical ensemble	Ω		1
grand (canonical ensemble)	Ξ		1
symmetry number	σ, s		1
reciprocal temperature parameter	β	$\beta = 1/kT$	J^{-1}
characteristic temperature	Θ		K

Name	Symbol	Definition	SI unit
General Chemistry			
number of entities (e.g. molecules, atoms, ions, formula units)	N		1
amount (of substance)	n	$n_B = N_B/L$	mol
Avogadro constant	L, N_A		mol^{-1}
mass of atom, atomic mass	m_a, m		kg
mass of entity (molecule, or formula unit)	m_f, m		kg
atomic mass constant	m_u	$m_u = m_a(^{12}C)/12$	kg
molar mass	M	$M_B = m/n_B$	kg mol^{-1}
relative molecular mass (relative molar mass, molecular weight)	M_r	$M_{r,B} = m_B/m_u$	1
molar volume	V_m	$V_{m,B} = V/n_B$	m^3 mol^{-1}
mass fraction	w	$w_B = m_B/\Sigma m_i$	1
volume fraction	ϕ	$\phi_B = V_B/\Sigma V_i$	1
mole fraction, amount fraction, number fraction	x, y	$x_B = n_B/\Sigma n_i$	1
(total) pressure	p, P		Pa
partial pressure	p_B	$p_B = y_B p$	Pa
mass concentration (mass density)	γ, ρ	$\gamma_B = m_B/V$	kg m^{-3}
number concentration, number density of entities	C, n	$C_B = N_B/V$	m^{-3}
amount concentration, concentration	c	$c_B = n_B/V$	mol m^{-3}
solubility	s	$s_B = c_B$ (saturated solution)	mol m^{-3}
molality (of a solute)	m, (b)	$m_B = n_B/m_A$	mol kg^{-1}
surface concentration	Γ	$\Gamma_B = n_B/A$	mol m^{-2}
stoichiometric number	ν		1
extent of reaction, advancement	ξ	$\Delta\xi = \Delta n_B/\nu_B$	mol
degree of dissociation	α		1
Chemical Thermodynamics			
heat	q, Q		J
work	w, W		J
internal energy	U	$\Delta U = q + w$	J
enthalpy	H	$H = U + pV$	J
thermodynamic temperature	T		K
Celsius temperature	θ, t	$\theta/^oC = T/K - 273.15$	^oC
entropy	S	$dS \geq dq/T$	J K^{-1}
Helmholtz energy, (Helmholtz function)	A	$A = U - TS$	J
Gibbs energy, (Gibbs function)	G	$G = H - TS$	J
Massieu function	J	$J = -A/T$	J K^{-1}
Planck function	Y	$Y = -G/T$	J K^{-1}
surface tension	γ, σ	$\gamma = (\partial G/\partial A_s)_{T,p}$	J m^{-2}, N m^{-1}
molar quantity X	X_m	$X_m = X/n$	(varies)
specific quantity X	x	$x = X/m$	(varies)
pressure coefficient	β	$\beta = (\partial p/\partial T)v$	Pa K^{-1}
relative pressure coefficient	α_p	$\alpha_p = (1/p)(\partial p/\partial T)_V$	K^{-1}
compressibility,			
isothermal	κ_T	$\kappa_T = -(1/V)(\partial V/\partial p)_T$	Pa^{-1}
isentropic	κ_S	$\kappa_S = -(1/V)(\partial V/\partial p)_S$	Pa^{-1}
linear expansion coefficient	α_l	$\alpha_l = (1/l)(\partial l/\partial T)$	K^{-1}
cubic expansion coefficient	α, α_V, γ	$\alpha = (1/V)(\partial V/\partial T)_p$	K^{-1}
heat capacity,			
at constant pressure	C_p	$C_p = (\partial H/\partial T)_p$	J K^{-1}
at constant volume	C_V	$C_V = (\partial U/\partial T)_V$	J K^{-1}
ratio of heat capacities	γ, (κ)	$\gamma = C_p/C_V$	1
Joule–Thomson coefficient	μ, μ_{JT}	$\mu = (\partial T/\partial p)_H$	K Pa^{-1}
second virial coefficient	B	$pV_m = RT(1 + B/V_m + \ldots)$	m^3 mol^{-1}
compression factor (compressibility factor)	Z	$Z = pV_m/RT$	1
partial molar quantity X	X_B, (X'_B)	$X_B = (\partial X/\partial n_B)_{T,p,n_{j\neq B}}$	(varies)
chemical potential (partial molar Gibbs energy)	μ	$\mu_B = (\partial G/\partial n_B)_{T,p,n_{j\neq B}}$	J mol^{-1}
absolute activity	λ	$\lambda_B = \exp(\mu_B/RT)$	1

Name	Symbol	Definition	SI unit
standard chemical potential	$\mu^{\ominus}$, μ^{o}		J mol^{-1}
standard partial molar enthalpy	$H_{\mathrm{B}}^{\ominus}$	$H_{\mathrm{B}}^{\ominus} = \mu_B^{\ominus} + TS_B^{\ominus}$	J mol^{-1}
standard partial molar entropy	$S_{\mathrm{B}}^{\ominus}$	$S_{\mathrm{B}}^{\ominus} = -(\partial\mu_B^{\ominus}/\partial T)_p$	J mol^{-1} K^{-1}
standard reaction Gibbs energy (function)	$\Delta_r G^{\ominus}$	$\Delta_r G^{\ominus} = \sum_{\mathrm{B}} \nu_{\mathrm{B}} \mu_{\mathrm{B}}^{\ominus}$	J mol^{-1}
affinity of reaction	A, $(\mathcal{A})$	$A = -(\partial G/\partial\xi)_{p,T} = -\sum_{\mathrm{B}} \nu_{\mathrm{B}}\mu_{\mathrm{B}}$	J mol^{-1}
standard reaction enthalpy	$\Delta_r H^{\ominus}$	$\Delta_r H^{\ominus} = \sum_{\mathrm{B}} \nu_{\mathrm{B}} H_{\mathrm{B}}^{\ominus}$	J mol^{-1}
standard reaction entropy	$\Delta_r S^{\ominus}$	$\Delta_r S^{\ominus} = \sum_{\mathrm{B}} \nu_{\mathrm{B}} S_{\mathrm{B}}^{\ominus}$	J mol^{-1} K^{-1}
equilibrium constant	$K^{\ominus}$, K	$K^{\ominus} = \exp(-\Delta_r G^{\ominus}/RT)$	1
equilibrium constant,			
pressure basis	K_p	$K_p = \prod_{\mathrm{B}} p_B^{\nu_{\mathrm{B}}}$	Pa$^{\Sigma\nu}$
concentration basis	K_c	$K_c = \prod_{\mathrm{B}} c_{\mathrm{B}}^{\nu_{\mathrm{B}}}$	(mol m^{-3})$^{\Sigma\nu}$
molality basis	K_m	$K_m = \prod_{\mathrm{B}} m_{\mathrm{B}}^{\nu_{\mathrm{B}}}$	(mol kg^{-1})$^{\Sigma\nu}$
fugacity	f, $\tilde{p}$	$f_{\mathrm{B}} = \lambda_{\mathrm{B}} \lim_{p\to 0} (p_{\mathrm{B}}/\lambda_{\mathrm{B}})_T$	Pa
fugacity coefficient	ϕ	$\phi_{\mathrm{B}} = f_{\mathrm{B}}/p_{\mathrm{B}}$	1
activity and activity coefficient referenced to Raoult's law, (relative) activity	a	$a_{\mathrm{B}} = \exp\left[\frac{\mu_{\mathrm{B}} - \mu_{\mathrm{B}}^{*}}{RT}\right]$	1
activity coefficient	f	$f_{\mathrm{B}} = a_{\mathrm{B}}/x_{\mathrm{B}}$	1
activities and activity coefficients referenced to Henry's law, (relative) activity, molality basis	a_m	$a_{m,\mathrm{B}} = \exp\left[\frac{\mu_{\mathrm{B}} - \mu_{\mathrm{B}}^{\ominus}}{RT}\right]$	1
concentration basis	a_c	$a_{c,\mathrm{B}} = \exp\left[\frac{\mu_{\mathrm{B}} - \mu_{\mathrm{B}}^{\ominus}}{RT}\right]$	1
mole fraction basis	a_x	$a_{x,\mathrm{B}} = \exp\left[\frac{\mu_{\mathrm{B}} - \mu_{\mathrm{B}}^{\ominus}}{RT}\right]$	1
activity coefficient,			
molality basis	γ_m	$a_{m,\mathrm{B}} = \gamma_{m,\mathrm{B}} m_{\mathrm{B}}/m^{\ominus}$	1
concentration basis	γ_c	$a_{c,\mathrm{B}} = \gamma_{c,\mathrm{B}} c_{\mathrm{B}}/c^{\ominus}$	1
mole fraction basis	γ_x	$a_{x,\mathrm{B}} = \gamma_{x,\mathrm{B}} x_{\mathrm{B}}$	1
ionic strength,			
molality basis	I_m, I	$I_m = \frac{1}{2}\Sigma m_{\mathrm{B}} z_{\mathrm{B}}^2$	mol kg^{-1}
concentration basis	I_c, I	$I_c = \frac{1}{2}\Sigma c_{\mathrm{B}} z_{\mathrm{B}}^2$	mol m^{-3}
osmotic coefficient,			
molality basis	ϕ_m	$\phi_m = (\mu_{\mathrm{A}}^{*} - \mu_{\mathrm{A}})/(RTM_{\mathrm{A}}\Sigma m_{\mathrm{B}})$	1
mole fraction basis	ϕ_x	$\phi_x = (\mu_{\mathrm{A}} - \mu_{\mathrm{A}}^{*})/(RT\ln x_{\mathrm{A}})$	1
osmotic pressure	Π	$\Pi = c_{\mathrm{B}}RT$ (ideal dilute solution)	Pa

(i) Symbols used as subscripts to denote a chemical process or reaction

These symbols should be printed in roman (upright) type, without a full stop (period).

vaporization, evaporation (liquid → gas)	vap
sublimation (solid → gas)	sub
melting, fusion (solid → liquid)	fus
transition (between two phases)	trs
mixing of fluids	mix
solution (of solute in solvent)	sol
dilution (of a solution)	dil
adsorption	ads
displacement	dpl
immersion	imm

Name	Symbol	Definition	SI unit
reaction in general	r		
atomization	at		
combustion reaction	c		
formation reaction	f		
(ii) Recommended superscripts			
standard	$^{\ominus}$, ^{o}		
pure substance	*		
infinite dilution	$^{\infty}$		
ideal	id		
activated complex, transition state	‡		
excess quantity	^{E}		
Chemical Kinetics			
rate of change of quantity X	$\dot{X}$	$\dot{X} = \mathrm{d}X/\mathrm{d}t$	(varies)
rate of conversion	$\dot{\xi}$	$\dot{\xi} = \mathrm{d}\xi/\mathrm{d}t$	mol s^{-1}
rate of concentration change (due to chemical reaction)	r_B,ν_B	$r_B = \mathrm{d}c_B/\mathrm{d}t$	mol m^{-3} s^{-1}
rate of reaction (based on amount concentration)	ν	$\nu = \dot{\xi}/V = \nu_B^{-1}\mathrm{d}c_B/\mathrm{d}t$	mol m^{-3} s^{-1}
partial order of reaction	n_B	$\nu = k\Pi c_B^{n_B}$	1
overall order of reaction	n	$n = \Sigma n_B$	1
rate constant, rate coefficient	k	$\nu = k\Pi c_B^{n_B}$	(mol^{-1} m^3)$^{n-1}$ s^{-1}
Boltzmann constant	k, k_B		J K^{-1}
half life	$t_{1/2}$	$c(t_{1/2}) = c_0/2$	s
relaxation time	τ	$\tau = 1/(k_1 + k_{-1})$	s
energy of activation, activation energy	E_a, E	$E_a = RT^2\,\mathrm{d}\ln k/\mathrm{d}T$	J mol^{-1}
pre–exponential factor	A	$k = A\exp(-E_a/RT)$	(mol^{-1} m^3)$^{n-1}$ s^{-1}
volume of activation	$\Delta^{\ddagger}V$	$\Delta^{\ddagger}V = -RT \times (\partial\ln k/\partial p)_T$	m^3 mol^{-1}
collision diameter	d	$d_{AB} = r_A + r_B$	m
collision cross–section	σ	$\sigma_{AB} = \pi d_{AB}^2$	m^2
collision frequency	Z_A		s^{-1}
collision number	Z_{AB}, Z_{AA}		m^{-3} s^{-1}
collision frequency factor	z_{AB}, z_{AA}	$z_{AB} = Z_{AB}/Lc_Ac_B$	m^3 mol^{-1} s^{-1}
standard enthalpy of activation	$\Delta^{\ddagger}H^{\ominus}$, $\Delta H^{\ddagger}$		J mol^{-1}
standard entropy of activation	$\Delta^{\ddagger}S^{\ominus}$, $\Delta S^{\ddagger}$		J mol^{-1} K^{-1}
standard Gibbs energy of activation	$\Delta^{\ddagger}G^{\ominus}$, $\Delta G^{\ddagger}$		J mol^{-1}
quantum yield, photochemical yield	ϕ		1
Electrochemistry			
elementary charge (proton charge)	e		C
Faraday constant	F	$F=eL$	C mol^{-1}
charge number of an ion	z	$z_B = Q_B/e$	1
ionic strength	I_c, I	$I_c = \tfrac{1}{2}\Sigma c_i z_i^2$	mol m^{-3}
mean ionic activity	$a_{\pm}$	$a_{\pm} = m_{\pm}\gamma_{\pm}/m^{\ominus}$	1
mean ionic molality	$m_{\pm}$	$m_{\pm}^{(\nu_+ + \nu_-)} = m_+^{\nu_+}m_-^{\nu_-}$	mol kg^{-1}
mean ionic activity coefficient	$\gamma_{\pm}$	$\gamma_{\pm}^{(\nu_+ + \nu_-)} = \gamma_+^{\nu_+}\gamma_-^{\nu_-}$	1
charge number of electrochemical cell reaction	n, (z)		1
electric potential difference (of a galvanic cell)	ΔV, E, U	$\Delta V = V_R - V_L$	V
emf, electromotive force	E	$E = \lim_{I\to 0}\Delta V$	V
standard emf, standard potential of the electrochemical cell reaction	$E^{\ominus}$	$E^{\ominus} = -\Delta_r G^{\ominus}/nF = (RT/nF)\ln K^{\ominus}$	V
standard electrode potential	$E^{\ominus}$		V
emf of the cell, potential of the electrochemical cell reaction	E	$E = E^{\ominus} - (RT/nF) \times \Sigma\nu_i \ln a_i$	V
pH	pH	$\mathrm{pH} \approx -\lg\left[\dfrac{c(\mathrm{H}^+)}{\mathrm{mol\ dm^{-3}}}\right]$	1
inner electric potential	ϕ	$\nabla\phi = -\boldsymbol{E}$	V

Name	Symbol	Definition	SI unit
outer electric potential	ψ	$\psi = Q/4\pi\varepsilon_0 r$	V
surface electric potential	χ	$\chi = \phi - \psi$	V
Galvani potential difference	$\Delta\phi$	$\Delta_\alpha^\beta\phi = \phi^\beta - \phi^\alpha$	V
volta potential difference	$\Delta\psi$	$\Delta_\alpha^\beta\psi = \psi^\beta - \psi^\alpha$	V
electrochemical potential	$\tilde{\mu}$	$\tilde{\mu}_B^{\ \alpha} = (\partial G/\partial n_B^{\ \alpha})$	J mol^{-1}
electric current	I	$I = \mathrm{d}Q/\mathrm{d}t$	A
(electric) current density	j	$j = I/A$	A m^{-2}
(surface) charge density	σ	$\sigma = Q/A$	C m^{-2}
electrode reaction rate constant	k	$k_{ox} = I_a/(nFA\prod_i c_i^{n_i})$	(varies)
mass transfer coefficient, diffusion rate constant	k_d	$k_{d,B} = \lvert\nu_B\rvert I_{l,B}/nFcA$	m s^{-1}
thickness of diffusion layer	δ	$\delta_B = D_B/k_{d,B}$	m
transfer coefficient (electrochemical)	α	$\alpha_c = \frac{-\lvert\nu\rvert RT}{nF}\frac{\partial \ln\lvert I_c\rvert}{\partial E}$	1
overpotential	η	$\eta = E_I - E_{I=0} - IR_u$	V
electrokinetic potential (zeta potential)	ζ		V
conductivity	κ, (σ)	$\kappa = j/E$	S m^{-1}
conductivity cell constant	K_{cell}	$K_{cell} = \kappa R$	m^{-1}
molar conductivity (of an electrolyte)	Λ	$\Lambda_B = \kappa/c_B$	S m^2 mol^{-1}
ionic conductivity, molar conductivity of an ion	λ	$\lambda_B = \lvert z_B\rvert Fu_B$	S m^2 mol^{-1}
electric mobility	u, (μ)	$u_B = \nu_B/E$	m^2 V^{-1} s^{-1}
transport number	t	$t_B = j_B/\Sigma j_i$	1
reciprocal radius of ionic atmosphere	κ	$\kappa = (2F^2I/\varepsilon RT)^{1/2}$	m^{-1}
Colloid and Surface Chemistry			
specific surface area	a, a_s, s	$a = A/m$	m^2 kg^{-1}
surface amount of B, adsorbed amount of B	$n_B^{\ s}$, $n_B^{\ a}$		mol
surface excess of B	$n_B^{\ \sigma}$		mol
surface excess concentration of B	Γ_B, $(\Gamma_B^{\ \sigma})$	$\Gamma_B = n_B^{\ \sigma}/A$	mol m^{-2}
total surface excess concentration	Γ, (Γ^σ)	$\Gamma = \sum_i \Gamma_i$	mol m^{-2}
area per molecule	a, σ	$a_B = A/N_B^{\ \sigma}$	m^2
area per molecule in a filled monolayer	a_m, σ_m	$a_{m,B} = A/N_{m,B}$	m^2
surface coverage	θ	$\theta = N_B^{\ \sigma}/N_{m,B}$	1
contact angle	θ		1, rad
film thickness	t, h, δ		m
thickness of (surface or interfacial) layer	τ, δ, t		m
surface tension, interfacial tension	γ, σ	$\gamma = (\partial G/\partial A_s)_{T,p}$	N m^{-1}, J m^{-2}
film tension	Σ_f	$\Sigma_f = 2\gamma_f$	N m^{-1}
reciprocal thickness of the double layer	κ	$\kappa = [2F^2I_c/\varepsilon RT]^{1/2}$	m^{-1}
average molar masses			
number–average	M_n	$M_n = \Sigma n_i M_i/\Sigma n_i$	kg mol^{-1}
mass–average	M_m	$M_m = \Sigma n_i M_i^2/\Sigma n_i M_i$	kg mol^{-1}
Z–average	M_Z	$M_Z = \Sigma n_i M_i^3/\Sigma n_i M_i^2$	kg mol^{-1}
sedimentation coefficient	s	$s = \nu/a$	s
van der Waals constant	λ		J
retarded van der Waals constant	β, B		J
van der Waals–Hamaker constant	A_H		J
surface pressure	π^s, π	$\pi^s = \gamma^0 - \gamma$	N m^{-1}
Transport Properties			
flux (of a quantity X)	J_X, J	$J_X = A^{-1}\,\mathrm{d}X/\mathrm{d}t$	(varies)
volume flow rate	q_V, $\dot{V}$	$q_v = \mathrm{d}V/\mathrm{d}t$	m^3 s^{-1}
mass flow rate	q_m, $\dot{m}$	$q_m = \mathrm{d}m/\mathrm{d}t$	kg s^{-1}
mass transfer coefficient	k_d		m s^{-1}
heat flow rate	ϕ	$\phi = \mathrm{d}q/\mathrm{d}t$	W
heat flux	J_q	$J_q = \phi/A$	W m^{-2}
thermal conductance	G	$G = \phi/\Delta T$	W K^{-1}
thermal resistance	R	$R = 1/G$	K W^{-1}

Name	Symbol	Definition	SI unit
thermal conductivity	λ, k	$\lambda = J_q/(\mathrm{d}T/\mathrm{d}l)$	W m^{-1} K^{-1}
coefficient of heat transfer	h, (k, K, α)	$h = J_q/\Delta T$	W m^{-2} K^{-1}
thermal diffusivity	a	$a = \lambda/\rho c_p$	m^2 s^{-1}
diffusion coefficient	D	$D = J_n/(\mathrm{d}c/\mathrm{d}l)$	m^2 s^{-1}

The following symbols are used in the definitions of the dimensionless quantities: mass (m), time (t), volume (V), area (A), density (ρ), speed (v), length (l), viscosity (η), pressure (p), acceleration of free fall (g), cubic expansion coefficient (α), temperature (T), surface tension (γ), speed of sound (c), mean free path (λ), frequency (f), thermal diffusivity (a), coefficient of heat transfer (h), thermal conductivity (k), specific heat capacity at constant pressure (c_p), diffusion coefficient (D), mole fraction (x), mass transfer coefficient (k_d), permeability (μ), electric conductivity (κ), and magnetic flux density (B).

Name	Symbol	Definition	SI unit
Reynolds number	Re	$Re = pvl/\eta$	1
Euler number	Eu	$Eu = \Delta p/\rho v^2$	1
Froude number	Fr	$Fr = v/(lg)^{1/2}$	1
Grashof number	Gr	$Gr = l^3 g\alpha\Delta T\rho^2/\eta^2$	1
Weber number	We	$We = \rho v^2 l/\gamma$	1
Mach number	Ma	$Ma = v/c$	1
Knudsen number	Kn	$Kn = \lambda/l$	1
Strouhal number	Sr	$Sr = lf/v$	1
Fourier number	Fo	$Fo = at/l^2$	1
Péclet number	Pe	$Pe = vl/a$	1
Rayleigh number	Ra	$Ra = l^3 g\alpha\Delta T\rho/\eta a$	1
Nusselt number	Nu	$Nu = hl/k$	1
Stanton number	St	$St = h/\rho v c_p$	1
Fourier number for mass transfer	Fo^*	$Fo^* = Dt/l^2$	1
Péclet number for mass transfer	Pe^*	$Pe^* = vl/D$	1
Grashof number for mass transfer	Gr^*	$Gr^* = l^3 g\left(\frac{\partial\rho}{\partial x}\right)_{T,p}\left(\frac{\Delta x\rho}{\eta}\right)$	1
Nusselt number for mass transfer	Nu^*	$Nu^* = k_d l/D$	1
Stanton number for mass transfer	St^*	$St^* = k_d/v$	1
Prandtl number	Pr	$Pr = \eta/\rho a$	1
Schmidt number	Sc	$Sc = \eta/\rho D$	1
Lewis number	Le	$Le = a/D$	1
magnetic Reynolds number	Rm, Re_m	$Rm = v\mu\kappa l$	1
Alfvén number	Al	$Al = v(\rho\mu)^{1/2}/B$	1
Hartmann number	Ha	$Ha = Bl\,(\kappa/\eta)^{1/2}$	1
Cowling number	Co	$Co = B^2/\mu\rho v^2$	1

NOMENCLATURE OF CHEMICAL COMPOUNDS

The International Union of Pure and Applied Chemistry (IUPAC) maintains several commissions that deal with the naming of chemical substances. In general, the approach of IUPAC is to present rules for arriving at names in a systematic manner, rather than recommending a unique name for each compound. Thus there are often several alternative "IUPAC names", depending on which nomenclature system is used, each of which may have advantages in specific applications. However, each of these names will be unambiguous.

Organizations such as the Chemical Abstacts Service and the Beilstein Institute that prepare indexes to the chemical literature must adopt a system for selecting unique names in order to avoid excessive cross referencing. Chemical Abstracts Service uses a system which groups together compounds derived from a single parent compound. Thus most index names are inverted (e.g., Benzene, bromo rather than bromobenzene; Acetic acid, sodium salt rather than sodium acetate). In this *Handbook* the CAS Index Names are used only in the table "Physical Constants of Organic Compounds". Other tables use more familiar names which, with a few possible exceptions, conform to one of the IUPAC naming systems.

Recommended names for the most common substituent groups, ligands, ions, and organic rings are given in the two following tables, "Nomenclature for Inorganic Ions and Ligands" and "Organic Substituent Groups and Ring Systems". For the basics of macromolecular nomenclature, see "Naming Organic Polymers" in Section 13.

Some of the most useful recent guides to chemical nomenclature, prepared by IUPAC and other organizations such as the International Union of Biochemistry and Molecular Biology (IUBMB) and the American Chemical Society are listed below . These books contain citations to the more detailed nomenclature documents in each area.

Inorganic Chemistry

International Union of Pure and Applied Chemistry, *Nomenclature of Inorganic Chemistry, Recommendations 1990*, Leigh, G. J., Ed., Blackwell Scientific Publications, Oxford, 1990.

Block, B. P., Powell, W. H., and Fernelius, W. C., *Inorganic Chemical Nomenclature, Principles and Practice*, American Chemical Society, Washington, 1990.

Organic Chemistry

International Union of Pure and Applied Chemistry, *A Guide to IUPAC Nomenclature of Organic Compounds, Recommendations 1993,* Panico, R., Powell, W. H., and Richer, J.-C., Eds., Blackwell Scientific Publications, Oxford, 1993.

International Union of Pure and Applied Chemistry, *Glossary of Class Names of Organic Compounds and Reactive Intermediates Based on Structure*, Moss, G. P., Smith, P. A. S., and Tavernier, D., Eds., *Pure & Appl. Chem*, 67, 1307, 1995.

Rhodes, P.H., *The Organic Chemist's Desk Reference*, Chapman & Hall, London, 1995.

International Union of Pure and Applied Chemistry, *Basic Terminology of Stereochemistry*, Moss, G. P., Ed., *Pure & Applied Chemistry*, 68, 2193, 1966.

Macromolecular Chemistry

International Union of Pure and Applied Chemistry, *Compendium of Macromolecular Nomenclature*, Metanomski, W. V., Ed., Blackwell Scientific Publications, Oxford, 1991.

International Union of Pure and Applied Chemistry, *Glossary of Basic Terms in Polymer Science*, Jenkins, A.D., Kratochvil, P., Stepto, R. F. T., and Suter, U. W., Eds., *Pure & Appl. Chem*, 68, in press.

Biochemistry

International Union of Biochemistry and Molecular Biology, *Biochemical Nomenclature and Related Documents, 2nd Edition, 1992*, Portland Press, London, 1993; includes recommendations of the IUPAC-IUBMB Joint Commission on Biochemical Nomenclature.

International Union of Biochemistry and Molecular Biology, *Enzyme Nomenclature, 1992*, Academic Press, Orlando, FL, 1992.

IUPAC-IUBMB Joint Commission on Biochemical Nomenclature, *Nomenclature of Carbohydrates, Recommendations 1996*, McNaught, A. D., Ed., *Pure & Appl. Chem*., 68, 1919, 1996.

General

Chemical Abstracts Service, *Naming and Indexing Chemical Substances for Chemical Abstracts, Appendix IV, Chemical Abstracts 1994 Index Guide.*

NOMENCLATURE FOR INORGANIC IONS AND LIGANDS

See the table "Nomenclature of Chemical Compounds" for references. The assistance of Warren H. Powell in preparing this list is gratefully acknowledged.

Group	As cation	As anion	As ligand	As prefix in organic compounds
H	hydrogen	hydride	hydrido	
F	fluorine	fluoride	fluoro	fluoro
Cl	chlorine	chloride	chloro	chloro
Br	bromine	bromide	bromo	bromo
I	iodine	iodide	iodo	iodo
ClO	chlorosyl	hypochlorite	hypochlorito	chlorosyl
ClO_2	chloryl	chlorite	chlorito	chloryl
ClO_3	perchloryl	chlorate	chlorato	perchloryl
ClO_4		perchlorate		
IO	iodosyl	hypoiodite		iodoso
IO_2	iodyl			iodyl; iodoxy
O		oxide	oxo	oxo
O_2		peroxide (O_2^{2-}) hyperoxide (O_2^-)	peroxo	peroxy
HO		hydroxide	hydroxo	hydroxy
HO_2		hydrogen peroxide	hydrogen peroxo	hydroperoxy
S		sulfide	thio; sulfido	thio; thioxo
HS		hydrogen sulfide	thiolo	mercapto
S_2		disulfide	disulfido	
SO	sulfinyl; thionyl			sulfinyl
SO_2	sulfonyl; sulfuryl	sulfoxylate		sulfonyl
SO_3		sulfite	sulfito	
HSO_3		hydrogen sulfite	hydrogen sulfito	
S_2O_3		thiosulfate	thiosulfato	
SO_4		sulfate	sulfato	
Se		selenide	seleno	seleno; selenoxo
SeO	seleninyl			seleninyl
SeO_2	selenonyl			selenonyl
SeO_3		selenite	selenito	
SeO_4		selenate	selenato	
Te		telluride	telluro	telluro; telluroxo
CrO_2	chromyl			
UO_2	uranyl			
NpO_2	neptunyl			
PuO_2	plutoryl			
AmO_2	americyl			
N		nitride	nitrido	
N_3		azide	azido	
NH		imide	imido	imino
NH_2		amide	amido	amino
NHOH		hydroxylamide	hydroxylamido	hydroxyamino
N_2H_3		hydrazide	hydrazido	hydrazino; diazanyl
NO	nitrosyl		nitrosyl	nitroso
NO_2	nitryl		nitro	nitro
ONO		nitrite	nitrito	
NS	thionitrosyl			
NO_3		nitrate	nitrato	
N_2O_3		hyponitrite	hyponitrito	
P		phosphide	phosphido	phosphinidyne
PO	phosphoryl			phosphoroso; phosphinylidyne
PO_2	phospho			
PS	thiophosphoryl			phosphinothioylidyne; thiophosphorozo
PH_2O_3		hypophosphite	hypophosphito	
PHO_3		phosphite	phosphito	
PO_4		phosphate	phosphato	

Group	As cation	As anion	As ligand	As prefix in organic compounds
AsO_4		arsenate	arsenato	
VO	vanadyl			
CO	carbonyl		carbonyl	carbonyl
CS	thiocarbonyl			thiocarbonyl
CH_3O		methanolate	methoxo	methoxy
C_2H_5O		ethanolate	ethoxo	ethoxy
CH_3S		methanethiolate	methanethiolato	methylthio
C_2H_5S		ethanethiolate	ethanethiolato	ethylthio
CN	cyanogen	cyanide	cyano	cyano
OCN		cyanate	cyanato	cyanato
SCN		thiocyanate	thiocyanato	thiocyanato
SeCN		selenocyanate	selenocyanato	selenocyanato
TeCN		tellurocyanate	tellurocyanato	tellurocyanato
CO_3		carbonate	carbonato	
HCO_3		hydrogen carbonate	hydrogen carbonato	carboxycarbonyl
C_2O_4		oxalate	oxalato	

ORGANIC SUBSTITUENT GROUPS AND RING SYSTEMS

The first part of this table lists substituent groups and their line formulas. A substituent group is defined by IUPAC as a group that replaces one or more hydrogen atoms attached to a parent structure. Such groups are sometimes called radicals, but IUPAC now reserves the term radical for a free molecular species with unpaired electrons. IUPAC does not recommend some of these names, which are marked here with asterisks (e.g., amyl*), but they are included in this list because they are often encountered in the older literature. Substituent group names which are formed by systematic rules (e.g., methyl from methane, ethyl from ethane, etc.) are included here only for the first few members of a homologous series.

In the second part of the table a number of common organic ring compounds are shown, with the conventional numbering of the ring positions indicated.

The help of Warren H. Powell in preparing this table is greatly appreciated. Pertinent references may be found in the table "Nomenclature of Chemical Compounds."

Substituent Groups

acetamido (acetylamino)	CH_3CONH-
acetoacetyl	CH_3COCH_2CO-
acetonyl	CH_3COCH_2-
acetyl	CH_3CO-
acryloyl* (1-oxo-2-propenyl)	CH_2=$CHCO$-
alanyl (from alanine)	$CH_3CH(NH_2)CO$-
β-alanyl	$H_2N(CH_2)_2CO$-
allyl (2-propenyl)	CH_2=$CHCH_2$-
allylidene (2-propenylidene)	CH_2=CHCH=
amidino (aminoiminomethyl)	$H_2NC(=NH)$-
amino	H_2N-
amyl* (pentyl)	$CH_3(CH_2)_4$-
anilino (phenylamino)	C_6H_5NH-
anisidino	$CH_3OC_6H_4NH$-
anthranoyl (2-aminobenzoyl)	2-$H_2NC_6H_4CO$-
arsino	AsH_2-
azelaoyl (from azelaic acid)	$-OC(CH_2)_7CO$-
azido	N_3-
azino	=N-N=
azo	-N=N-
azoxy	-N(O)=N-
benzal* (benzylidene)	C_6H_5CH=
benzamido (benzoylamino)	C_6H_5CONH-
benzhydryl (diphenylmethyl)	$(C_6H_5)_2CH$-
benzoxy* (benzoyloxy)	C_6H_5COO-
benzoyl	C_6H_5CO-
benzyl	$C_6H_5CH_2$-
benzylidene	C_6H_5CH=
benzylidyne	C_6H_5C≡
biphenylyl	$C_6H_5C_6H_5$-
biphenylene	$-C_6H_4-C_6H_4$-
butoxy	C_4H_9O-
sec-butoxy (1-methylpropoxy)	$C_2H_5CH(CH_3)O$-
tert-butoxy (1,1-dimethylethoxy)	$(CH_3)_3CO$-
butyl	$CH_3(CH_2)_3$-
sec-butyl (1-methylpropyl)	$CH_3CH_2CH(CH_3)$-
tert-butyl (1,1-dimethylethyl)	$(CH_3)_3C$-
butyryl (1-oxobutyl)	$CH_3(CH_2)_2CO$-
caproyl* (hexanoyl)	$CH_3(CH_2)_4CO$-
capryl* (decanoyl)	$CH_3(CH_2)_8CO$-
capryloyl* (octanoyl)	$CH_3(CH_2)_6CO$-
carbamido (carbamoylamino)	H_2NCONH-
carbamoyl (aminocarbonyl)	H_2NCO-
carbamyl (aminocarbonyl)	H_2NCO-
carbazoyl (hydrazinocarbonyl)	H_2NNHCO-
carbethoxy (ethoxycarbonyl)	C_2H_5OCO-
carbonyl	=C=O
carboxy	HOOC-
cetyl* (hexadecyl)	$CH_3(CH_2)_{15}$-
chloroformyl (chlorcarbonyl)	$ClCO$-
cinnamoyl	C_6H_5CH=$CHCO$-
cinnamyl (3-phenyl-2-propenyl)	C_6H_5CH=$CHCH_2$-
cinnamylidene	C_6H_5CH=CHCH=
cresyl* (hydroxymethylphenyl)	$HO(CH_3)C_6H_4$-
crotonoyl	CH_3CH=$CHCO$-
crotyl (2-butenyl)	CH_3CH=$CHCH_2$-
cyanamido (cyanoamino)	NCNH-
cyanato	NCO-
cyano	NC-
decanedioyl	$-OC(CH_2)_8CO$-
decanoyl	$CH_3(CH_2)_8CO$-
diazo	N_2=
diazoamino	-NHN=N-
disilanyl	H_3SiSiH_2-
disiloxanyloxy	$H_3SiOSiH_2O$-
disulfinyl	-S(O)S(O)-
dithio	-SS-
enanthoyl* (heptanoyl)	$CH_3(CH_2)_5CO$-
epoxy	-O-
ethenyl (vinyl)	CH_2=CH-
ethynyl	HC≡C-
ethoxy	C_2H_5O-
ethyl	CH_3CH_2-
ethylene	$-CH_2CH_2$-
ethylidene	CH_3CH=
ethylthio	C_2H_5S-
formamido (formylamino)	HCONH-
formyl	HCO-
furmaroyl (from fumaric acid)	-OCCH=CHCO-
furfuryl (2-furanylmethyl)	$OC_4H_3CH_2$-
furfurylidene (2-furanylmethylene)	OC_4H_3CH=
glutamoyl (from glutamic acid)	$-OC(CH_2)_2CH(NH_2)CO$-
glutaryl (from glutaric acid)	$-OC(CH_2)_3CO$-
glycylamino	H_2NCH_2CONH-
glycoloyl; glycolyl (hydroxyacetyl)	$HOCH_2CO$-
glycyl (aminoacetyl)	H_2NCH_2CO-
glyoxyloyl; glyoxylyl (oxoacetyl)	HCOCO-
guanidino	$H_2NC(=NH)NH$-
guanyl (aminoiminomethyl)	$H_2NC(=NH)$-
heptadecanoyl	$CH_3(CH_2)_{15}CO$-
heptanamido	$CH_3(CH_2)_5CONH$-
heptanedioyl	$-OC(CH_2)_5CO$-
heptanoyl	$CH_3(CH_2)_5CO$-
hexadecanoyl	$CH_3(CH_2)_{14}CO$-
hexamethylene (1,6-hexanediyl)	$-(CH_2)_6$-
hexanedioyl	$-OC(CH_2)_4CO$-
hippuryl (N-benzoylglycyl)	$C_6H_5CONHCH_2CO$-
hydrazino	H_2NNH-
hydrazo	-HNNH-
hydrocinnamoyl	$C_6H_5(CH_2)_2CO$-

hydroperoxy	HOO-
hydroxyamino	HONH-
hydroxy	HO-
imino	HN=
iodoso* (iodosyl)	OI-
iodyl	O_2I-
isoamyl* (isopentyl; 3-methylbutyl)	$(CH_3)_2CH(CH_2)_2$-
isobutenyl (2-methyl-1-propenyl)	$(CH_3)_2C$=CH-
isobutoxy (2-methylpropoxy)	$(CH_3)_2CHCH_2O$-
isobutyl (2-methylpropyl)	$(CH_3)_2CHCH_2$-
isobutylidene (3-methylpropylidene)	$(CH_3)_2CHCH$=
isobutyryl (2-methyl-1-oxopropyl)	$(CH_3)_2CHCO$-
isocyanato	OCN-
isocyano	CN-
isohexyl (4-methylpentyl)	$(CH_3)_2CH(CH_2)_3$-
isoleucyl (from isoleucine)	$C_2H_5CH(CH_3)CH(NH_2)CO$-
isonitroso* (hydroxyamino)	HON=
isopentyl (3-methylbutyl)	$(CH_3)_2CH(CH_2)_2$-
isopentylidene (3-methylbutylidene)	$(CH_3)_2CHCH_2CH$=
isopropenyl (1-methylethenyl)	$CH_2=C(CH_3)$-
isopropoxy (1-methylethoxy)	$(CH_3)_2CHO$-
isopropyl (1-methylethyl)	$(CH_3)_2CH$-
isopropylidene (1-methylethylidene)	$(CH_3)_2C$=
isothiocyanato (isothiocyano)	SCN-
isovaleryl* (3-methyl-1-oxobutyl)	$(CH_3)_2CHCH_2CO$-
lactoyl (from lactic acid)	$CH_3CH(OH)CO$-
lauroyl (from lauric acid)	$CH_3(CH_2)_{10}CO$-
lauryl (dodecyl)	$CH_3(CH_2)_{11}$-
leucyl (from leucine)	$(CH_3)_2CHCH_2CH(NH_2)CO$-
levulinoyl (from levulinic acid)	$CH_3CO(CH_2)_2CO$-
malonyl (from malonic acid)	$-OCCH_2CO$-
mandeloyl (from mandelic acid)	$C_6H_5CH(OH)CO$-
mercapto	HS-
mesityl	2,4,6-$(CH_3)_3C_6H_2$-
methacryloyl (from methacrylic acid)	$CH_2=C(CH_3)CO$-
methallyl (2-methyl-2-propenyl)	$CH_2=C(CH_3)CH_2$-
methionyl (from methionine)	$CH_3SCH_2CH_2CH(NH_2)CO$-
methoxy	CH_3O-
methyl	H_3C-
methylene	H_2C=
methylthio	CH_3S-
myristoyl (from myristic acid)	$CH_3(CH_2)_{12}CO$-
myristyl (tetradecyl)	$CH_3(CH_2)_{13}$-
naphthyl	$(C_{10}H_7)$-
naphthylene	$-(C_{10}H_6)$-
neopentyl (2,2-dimethylpropyl)	$(CH_3)_3CCH_2$-
nitramino (nitroamino)	O_2NNH-
nitro	O_2N-
nitrosamino (nitrosoamino)	ONNH-
nitrosimino (nitrosoimino)	ONN=
nitroso	ON-
nonanoyl (from nonanoic acid)	$CH_3(CH_2)_7CO$-
oleoyl (from oleic acid)	$CH_3(CH_2)_7CH=CH(CH_2)_7CO$-
oxalyl (from oxalic acid)	-OCCO-
oxo	O=
palmitoyl (from palmitic acid)	$CH_3(CH_2)_{14}CO$-
pentamethylene (1,5-pentanediyl)	$-(CH_2)_5$-
pentyl	$CH_3(CH_2)_4$-
tert-pentyl	$CH_3CH_2C(CH_3)_2$-
phenacyl	$C_6H_5COCH_2$-
phenacylidene	C_6H_5COCH=
phenethyl (2-phenylethyl)	$C_6H_5CH_2CH_2$-
phenoxy	C_6H_5O-
phenyl	C_6H_5-
phenylene (benzenediyl)	$-C_6H_4$-
phosphino* (phosphanyl)	H_2P-
phosphinyl* (phosphinoyl)	$H_2P(O)$-
phospho	O_2P-
phosphono	$(HO)_2P(O)$-
phthaloyl (from phthalic acid)	1,2-$C_6H_4(CO-)_2$
picryl (2,4,6-trinitrophenyl)	2,4,6-$(NO_2)_3C_6H_2$-
pimeloyl (from pimelic acid)	$-OC(CH_2)_5CO$-
piperidino (1-piperidinyl)	$C_5H_{10}N$-
pivaloyl (from pivalic acid)	$(CH_3)_3CCO$-
prenyl (3-methyl-2-butenyl)	$(CH_3)_2C=CHCH_2$-
propargyl (2-propynyl)	$HC\equiv CCH_2$-
1-propenyl	$-CH=CHCH_2$
2-propenyl (allyl)	$CH_2=CHCH_2$-
propionyl* (propanyl)	CH_3CH_2CO-
propoxy	$CH_3CH_2CH_2O$-
propyl	$CH_3CH_2CH_2$-
propylidene	CH_3CH_2CH=
pyrryl (pyrrolyl)	C_3H_4N-
salicyloyl (2-hydroxybenzoyl)	2-HOC_6H_4CO-
selenyl* (selanyl; hydroseleno)	HSe-
seryl (from serine)	$HOCH_2CH(NH_2)CO$-
siloxy	H_3SiO-
silyl	H_3Si-
silylene	H_2Si=
sorboyl (from sorbic acid)	$CH_3CH=CHCH=CHCO$-
stearoyl (from stearic acid)	$CH_3(CH_2)_{14}CO$-
stearyl (octadecyl)	$CH_3(CH_2)_{17}$-
styryl (2-phenylethenyl)	$C_6H_5CH=CH$-
suberoyl (from suberic acid)	$-OC(CH_2)_6CO$-
succinyl (from succinic acid)	$-OCCH_2CH_2CO$-
sulfamino (sulfoamino)	$HOSO_2NH$-
sulfamoyl (sulfamyl)	H_2NSO_2-
sulfanilyl [(4-aminophenyl)sulfonyl]	4-$H_2NC_6H_4SO_2$-
sulfeno	HOS-
sulfhydryl (mercapto)	HS-
sulfinyl	OS=
sulfo	HO_3S-
sulfonyl (sulfuryl)	$-SO_2$-
terephthaloyl	1,4-$C_6H_4(CO-)_2$
tetramethylene	$-(CH_2)_4$-
thienyl (from thiophene)	(C_4H_3S)-
thiocarbonyl (carbothionyl)	=CS
thiocarboxy	HOSC-
thiocyanato (thiocyano)	NCS-
thionyl* (sulfinyl)	-SO-
threonyl (from threonine)	$CH_3CH(OH)CH(NH_2)CO$-
toluidino [(methylphenyl)amino]	$CH_3C_6H_4NH$-
toluoyl (methylbenzoyl)	$CH_3C_6H_4CO$-
tolyl (methylphenyl)	$CH_3C_6H_4$-
α-tolyl (benzyl)	$C_6H_5CH_2$-
tolylene (methylphenylene)	$-(CH_3C_6H_3)$-
tosyl [(4-methylphenyl) sulfonyl)]	4-$CH_3C_6H_4SO_2$-
triazano	H_2NNHNH-
trimethylene (1,3-propanediyl)	$-(CH_2)_3$-
trityl (triphenylmethyl)	$(C_6H_5)_3C$-
valeryl* (pentanoyl)	$CH_3(CH_2)_3CO$-
valyl (from valine)	$(CH_3)_2CHCH(NH_2)CO$-
vinyl (ethenyl)	$CH_2=CH$-
vinylidene (ethenylidene)	$CH_2=C$=
xylidino [(dimethylphenyl)amino]	$(CH_3)_2C_6H_3NH$-
xylyl (dimethylphenyl)	$(CH_3)_2C_6H_3$-
xylylene [phenelenebis(methylene)]	$-CH_2C_6H_4CH_2$-

Organic Ring Compounds


Cyclopropane



Spiropentane


Cyclobutane



Cyclopentane


Furan


Thiophene



Pyrrole (Azole)



2*H*-Pyrrole (2*H*-Azole)


Pyrazole (1,2-Diazole)


3*H*-Pyrrole (3*H*-Azole)


2*H*-Imidazole (1,3-Diazole)


1,2,3-Triazole


1,2,4-Triazole


1,2-Dithiole


1,3-Dithiole


3*H*-1,2-Oxathiole


Isoxazole (1,2-Oxazole)


Thiazole (1,3-Thiazole)


Oxazole (1,3-Oxazole)



Isothiazole (1,2-Thiazole)


1,2,3-Oxadiazole


1,2,4-Oxadiazole


1,2,5-Oxadiazole (Furazan)



1,3,4-Oxadiazole


1,2,3,4-Oxatriazole



1,2,3,5-Oxatriazole


3*H*-1,2,3-Dioxazole


1,2,4-Dioxazole


1,3,2-Dioxazole


1,3,4-Dioxazole


5*H*-1,2,5-Oxathiazole



1,3-Oxathiole



Benzene


Cyclohexane


2*H*-Pyran


4*H*-Pyran


2*H*-Pyran-2-one (2-Pyrone)



4*H*-Pyran-4-one (4-Pyrone)


1,2-Dioxin



1,3-Dioxin


Pyridine


Pyridazine


Pyrimidine


Pyrazine


Piperazine


1,3,5-Triazine (*s*-Triazine)


1,2,4-Triazine (*as*-Triazine)


1,2,3-Triazine (*v*-Triazine)



4*H*-1,2-Oxazine



2*H*-1,3-Oxazine


6*H*-1,3-Oxazine


6*H*-1,2-Oxazine


1,4-Oxazine



2*H*-1,2-Oxazine


4*H*-1,4-Oxazine



1,2,5-Oxathiazine


1,2,6-Oxathiazine


1,2,4-Oxadiazine


1,3,5-Oxadiazine



Morpholine



Azepine



Oxepin



Thiepin



4*H*-1,2-Diazepine



Indene



2*H*-Indene (Isoindene)



Benzofuran



Isobenzofuran



Benzo[b]thiophene



Benzo[c]thiophene



Indole



3*H*-Indole



1*H*-Indole



Cyclopenta[b]pyridine



Pyrano[3,4-b]-pyrrole



Indazole



Benzisoxazole (Indoxazene)



Benzoxazole



2,1-Benzisoxazole



Naphthalene



1,2,3,4-Tetrahydronaphthalene (Tetralin)



Octahydronaphthalene (Decalin)



2*H*-1-Benzopyran (2*H*-Chromene)



2*H*-1-Benzopyran-2-one (Coumarin)



4H-1-Benzopyran-4-one (Chromen-4-one)



1*H*-2-Benzopyran-1-one (Isocoumarin)



3*H*-2-Benzopyran-1-one (Isochromen-3-one)



Quinoline



Isoquinoline



Cinnoline



Quinazoline



1,8-Naphthyridine



1,7-Naphthyridine



1,5-Naphthyridine



1,6-Naphthyridine



2*H*-1,3-Benzoxazine



2*H*-1,4-Benzoxazine



1*H*-2,3-Benzoxazine



4*H*-3,1-Benzoxazine



2*H*-1,2-Benzoxazine



4H-1,4-Benzoxazine



Anthracene



Phenanthrene


Phenalene



Fluorene



Carbazole


Xanthene


Acridine


Norpinane (Bicyclo[3.1.1]heptane)


7*H*-Purine


R = Nearly always methyl
R′ = Usually methyl
R″ = Various groups

Steroid ring system

SCIENTIFIC ABBREVIATIONS AND SYMBOLS

This table lists some symbols, abbreviations, and acronyms encountered in the physical sciences. Most entries in italic type are symbols for physical quantities; for more details on these, see the table "Symbols and Terminology for Physical and Chemical Quantities" in this section. Additional information on units may be found in the table "International System of Units" in Section 1. Many of the terms to which these abbreviations refer are included in the tables "Definitions of Scientific Terms" in Section 2 and "Techniques for Materials Characterization" in Section 12.

Publication practices vary with regard to the use of capital or lower case letters for many abbreviations. An effort has been made to follow the most common practices in this table, but much variation is found in the literature. Likewise, policies on the use of periods in an abbreviation vary considerably. Periods are generally omitted in this table unless they are necessary for clarity. Periods should never appear in SI units. The SI prefixes (m, k ,M, etc.) are not listed here, since they should never be used alone, but selected combinations with SI units (e.g., mg, kV, MW) are included.

Abbreviations are listed in alphabetical order without regard to case. Entries beginning with Greek letters fall at the end of the table.

a	absorption coefficient, acceleration, activity
a_0	Bohr radius
A	ampere, adenine (in genetic code)
Å	ångstrom
A	absorbance, area, Helmholtz energy, mass number
A_H	Hall coefficient
A_r	atomic weight (relative atomic mass)
AAS	atomic absorption spectroscopy
Abe	abequose
abs	absolute
ac	alternating current
Ac	acetyl
AcOH	acetic acid
ACT	activated complex theory
ACTH	adrenocorticotropic hormone
Ade	adenine
ADP	adenosine diphosphate
ads	adsorption
ae	eon (10^9 years)
AES	atomic emission spectroscopy, Auger electron spectroscopy
AF	audio frequency
AFM	atomic force microscopy
AI	artificial intelligence
AIM	atoms in molecules
Al	Alfen number
Ala	alanine
alc	alcohol
aliph.	aliphatic
alk.	alkaline
All	allose
Alt	altrose
am	amorphous solid
Am	amyl
AM	amplitude modulation
AMP	adenosine 5´-monophosphate
amu	atomic mass unit (recommended symbol is u)
anh, anhyd	anhydrous
antilog	antilogarithm
AO	atomic orbital
AOM	angular overlap model
Api	apiose
APS	appearance potential spectroscopy
APW	augmented plane wave
aq	aqueous
Ar	aryl
Ara	arabinose
Ara-ol	arabinitol
Arg	arginine
as, asym	asymmetrical (as chemical descriptor)
ASCII	American National Standard Code for Information Interchange
ASE	aromatic stabilization energy
Asn	asparagine
Asp	aspartic acid
at	atomization
atm	standard atmosphere
ATP	adenosine 5´-triphosphate
ATR	attenuated total internal reflection
at.wt.	atomic weight
AU	astronomical unit
av	average
avdp	avoirdupois
b	barn
B	magnetic flux density, second virial coefficient, susceptance
bar	bar (pressure unit)
bbl	barrel
bcc	body centered cubic
BCS	Bardeen-Cooper-Schrieffer (theory)
BDE	bond dissociation energy
Bé	Baumé
BET	Brunauer-Emmett-Teller (method)
BeV	billion electronvolt
Bhn	Brinell hardness number
Bi	biot
BN	bond number
BNS	nuclear backscattering spectroscopy
BO	bond order, Born-Oppenheimer (approximation)
BOD	biochemical oxygen demand
bp	boiling point
bpy	2,2´-bipyridine
Bq	becquerel
BRE	bond resonance energy
BSSE	basis set superposition error
Btu	British thermal unit
bu	bushel
Bu	butyl
Bz	benzoyl
Bzl	benzyl
c	combustion reaction
c	amount concentration, specific heat, velocity
c_0	speed of light in vacuum
C	coulomb, cytosine (in genetic code)
°C	degree Celsius
C	capacitance, heat capacity, number concentration
ca.	approximately
cal	calorie

calc	calculated
CARS	coherent anti-Stokes Raman spectroscopy
CAS RN	Chemical Abstracts Service Registry Number
CAT	clear-air turbulence, computerized axial tomography
CBS	complete basis set
cc	cubic centimeter
CCD	charge-coupled device
cd	candela, condensed phase
c.d.	current density
CD	circular dichroism
CDP	cytidine 5′-diphosphate
CEPA	couplet electron pair approximation
cf.	compare
cfm	cubic feet per minute
cgs	centimeter-gram-second system
CHF	coupled Hartree-Fock (method)
Ci	curie
CI	configuration interaction, chemical ionization
CIDEP	chemically induced dynamic electron polarization
CIDNP	chemically induced dynamic nuclear polarization
cir	circular
CKFF	Cotton-Kraihanzel force field
CL	cathode luminescence
cm	centimeter
c.m.	center of mass
c.m.c.	critical micelle concentration
CMO	canonical molecular orbital
CMP	cytidine 5′-monophosphate
CN	coordination number
CNDO	complete neglect of differential overlap
Co	Cowling number
COD	chemical oxygen demand
conc	concentrated, concentration
const	constant
cos	cosine
cosh	hyperbolic cosine
COSY	correlation spectroscopy (in NMR)
cot	cotangent
coth	hyperbolic cotangent
cp	candle power
cP	centipoise
Cp	cyclopentadienyl
CP	chemically pure
CPA	coherent potential approximation
cpd	contact potential difference
cps	cycles per second
CPT	charge conjugation-space inversion-time reversal (theorem)
CPU	central processing unit
cr, cryst	crystalline (phase)
CRU	constitutional repeating unit
csc	cosecant
ct	carat
CT	charge transfer
CTEM	conventional transmission electron microscopy
CTP	cytidine 5′-triphosphate
CTR	controlled thermonuclear reaction
cu	cubic
CV	cyclic voltammetry
CVD	chemical vapor deposition
cw	continuous wave
cwt	hundredweight (112 pounds)
Cy	cyclohexyl
cyl	cylinder
Cys	cysteine
d	day, deuteron
d	distance, density, dextrorotatory
D	debye unit
D	diffusion coefficient, dissociation energy, electric displacement
Da	dalton
DA	donor-acceptor (complex)
dB	decibel
dc	direct current
DE	delocalization energy
dec	decomposes
deg	degree
den	density
det	determinant
dev	deviation
DFT	density functional theory
diam	diameter
dil	dilute, dilution
DIM	diatomics in molecules
dm	decimeter
dmf, DMF	*N,N*-dimethylformamide
dmso, DMSO	dimethylsulfoxide
DNA	deoxyribonucleic acid
DNase	deoxyribonuclease
DNMR	dynamic nuclear magnetic resonance
DOS	density of states
doz	dozen
d.p.	degree of polymerization
dpl	displacement
dpm	disintegrations per minute
dps	disintegrations per second
dr	dram
dRib	2-deoxyribose
DRIFT	diffuse reflectance infrared Fourier transform
DRS	diffuse reflectance spectroscopy
DSC	differential scanning calorimetry
DTA	differential thermal analysis
dyn	dyne
e	electron, base of natural logarithms
e	elementary charge, linear strain
E	electric field strength, electromotive force, energy, modulus of elasticity, entgegen (*trans* configuration)
E_h	Hartree energy
EA	electron affinity
EAN	effective atomic number
ECP	effective core potential
ECR	electron cyclotron resonance
ED	electron diffraction, effective dose
EDS	energy dispersive x-ray spectroscopy
EDTA	ethylenediaminetetraacetic acid
EELS	electron energy loss spectroscopy
EFFF	energy factored force field
EHMO	extended Hückel molecular orbital
EHT	extended Hückel theory
emf	electromotive force
emu	electromagnetic unit system
en	ethylenediamine
ENDOR	electron-nuclear double resonance
EOS	equation of state
EPMA	electron probe microanalysis
EPR	electron paramagnetic (spin) resonance
eq, eqn	equation
eqQ	quadrupole coupling constant
erf	error function
erg	erg

ESCA	electron spectroscopy for chemical analysis
e.s.d.	estimated standard deviation
ESD	electron stimulated desorption
ESR	electron spin resonance
est	estimate, estimated
esu	electrostatic unit system
Et	ethyl
ET	electron transfer, ephemeris time
Et_2O	diethyl ether
e.u.	entropy unit
Eu	Euler number
eV	electronvolt
EWG	electron withdrawing group
EXAFS	extended x-ray absorption fine structure
EXELFS	extended energy loss fine structure
exp	exponential function
expt	experimental
ext	external
f	formation reaction
f	activity coefficient, aperture ratio, focal length, force constant, frequency, fugacity
F	farad
°F	degree Fahrenheit
F	Faraday constant, force, angular momentum
FAD	flavin adenine dinucleotide
fcc	face centered cubic
FEL	free electron laser
FEM	field emission microscopy
FEMO	free electron molecular orbital
FET	field effect transistor
fid	free induction decay
FIM	field ion microscopy
FIR	far infrared
fl	fluid (phase)
FM	frequency modulation
Fo	Fourier number
fp	freezing point
fpm	feet per minute
fps	feet per second, foot-pound-second system
Fr	franklin
Fr	Froude number
Fru	fructose
FSGO	floating spherical Gaussian orbital
ft	foot
ft-lb	foot pound
FT	Fourier transform
FTIR	Fourier transform infrared spectroscopy
Fuc	fucose
Fuc-ol	fucitol
fus	fusion (melting)
g	gram, gas
g	acceleration due to gravity, degeneracy, statistical weight, Landé g-factor
G	gauss, guanine (in genetic code)
G	electrical conductance, Gibbs energy, gravitational constant, sheer modulus
gal	gallon
Gal	gal, galileo, galactose
GalN	galactosamine
GC	gas chromatography
GC-MS	gas chromatography-mass spectrometry
GDMS	glow discharge mass spectroscopy
gem	geminal (on the same carbon atom)
GeV	gigaelectronvolt
GIAO	gauge invariant atomic orbital
gl	glacial
GLC	gas-liquid chromatography
Glc	glucose
GlcN	glucosamine
Glc-ol	glucitol
Gln	glutamine
Glu	glutamic acid
Gly	glycine
GMP	guanosine 5´-triphosphate
GMT	Greenwich mean time
gpm	gallons per minute
gps	gallons per second
gr	grain
Gr	Grashof number
GTO	gaussian type atomic orbital
Gua	guanine
Gul	gulose
GUT	grand unified theory
GVB	generalized valence bond
GWS	Glashow-Weinberg-Salam (theory)
Gy	gray, gigayear
h	helion, hour
h	Planck constant
H	henry
H	enthalpy, Hamiltonian function, magnetic field
H_0	Hubble constant
ha	hectare
Ha	Hartmann number
Hacac	acetylacetone
HAM	hydrogenic atoms in molecules
hav	haversine
Hb	hemoglobin
hcp	hexagonal closed packed
Hea	ethanolamine
HEIS	high energy ion scattering
HEP	high energy physics
HF	high frequency
hfs	hyperfine structure
Him	imidazole
His	histidine
HMO	Hückel molecular orbital
HOMO	highest occupied molecular orbital
hp	horsepower
HPLC	high-performance liquid chromatography
Hpz	pyrazole
hr	hour
HREELS	high resolution electron energy loss spectroscopy
HREM	high resolution electron microscopy
HSAB	hard-soft acid-base (theory)
HSE	homodesmotic stabilization energy
Hz	hertz
i	square root of minus one
I	electric current, ionic strength, moment of inertia, nuclear spin angular momentum, radiant intensity
IAT	international atomic time
i-Bu	isobutyl
IC	integrated circuit
ICP	inductively coupled plasma
ICR	ion cyclotron resonance
id	ideal (solution)
ID	inside diameter
Ido	idose
IDP	inosine 5´-diphosphate
IE	ionization energy
i.e.p.	isoelectric point

IEPA	independent electron pair approximation
IF	intermediate frequency
IGLO	individual gauge for localized orbitals
Ile	isoleucine
Im	imaginary part
imm	immersion
IMPATT	impact ionization avalanche transit time
in.	inch
INDO	intermediate neglect of differential overlap
INS	inelastic neutron scattering, ion neutralization spectroscopy
int	internal
I/O	input/output
IP	ionization potential
IPN	interpenetrating polymer network
i-Pr	isopropyl
IPR	isotopic perturbation of resonance
IPTS	International Practical Temperature Scale
IR	infrared
IRAS	reflection-absorption infrared spectroscopy
IRC	intrinsic reaction coordinate
isc	intersystem crossing
ISE	isodesmic stabilization energy
ISS	ion scattering spectroscopy
ITP	inosine 5´-triphosphate
ITS	International Temperature Scale (1990)
IU	international unit
j	angular momentum, electric current density
J	joule
J	angular momentum, electric current density, flux, Massieu function
k	absorption index, Boltzmann constant, rate constant, thermal conductivity, wave vector
K	kelvin
K	absorption coefficient, bulk modulus, equilibrium constant, kinetic energy
kb	kilobar, kilobase (DNA or RNA)
kcal	kilocalorie
KE	kinetic energy
keV	kiloelectronvolt
kg	kilogram
kgf	kilogram force
kJ	kilojoule
km	kilometer
Kn	Knudsen number
kPa	kilopascal
kt	karat
kV	kilovolt
kva	kilovolt ampere
kW	kilowatt
kwh	kilowatt hour
l	liquid, liter
l	angular momentum, length, levorotatory
L	liter, lambert
L	Avogadro constant, inductance, Lagrange function
lat.	latitude
lb	pound
lbf	pound force
lc	liquid crystal
LC	liquid chromatography
LCAO	linear combination of atomic orbitals
LD	lethal dose
Le	Lewis function
LED	light emitting diode
LEED	low-energy electron diffraction
LEIS	low energy ion scattering
Leu	leucine
LFER	linear free energy relationship
lim	limit
LIMS	laser ionization mass spectroscopy, laboratory information management system
liq	liquid
lm	lumen
ln	logarithm (natural)
LNDO	local neglect of differential overlap
log	logarithm (common)
long.	longitude
LST	local sidereal time
LT	local time
LTE	local thermodynamic equilibrium
LUMO	lowest unoccupied molecular orbital
lut	lutidine
lx	lux
ly	langley
l.y.	light year
Lys	lysine
Lyx	lyxose
m	meter, molal (as in 0.1 m solution), metastable (isotope)
m	magnetic dipole moment, mass, molality, angular momentum component, *meta* (as chemical descriptor)
M	molar (as in 0.1 M solution), metal (in chemical formulas)
M	magnetization, molar mass, mutual inductance, torque, angular momentum component
M_r	molecular weight (relative molar mass)
Ma	Mach number
Man	mannose
MASNMR	magic angle spinning nuclear magnetic resonance
max	maximum
MBE	molecular beam epitaxy
MBPT	many body perturbation theory
MC	Monte Carlo (method)
MCD	magnetic circular dichroism
MCPF	modified couple pair functional
MCSCF	multi-configurational self-consistent field
MD	molecular dynamics
Me	methyl
MEP	molecular electrostatic potential
MERP	minimum energy reaction path
Mes	mesityl
MESFET	metal-semiconductor field-effect transistor
Met	methionine
meV	millielectronvolt
MeV	megaelectronvolt
MF	molecular formula
mg	milligram
MHD	magnetohydrodynamics
mi	mile
MIM	molecules-in-molecules
min	minimum, minute
MINDO	modified intermediate neglect of differential overlap
MIR	mid-infrared
misc	miscible
MKS	meter-kilogram-second system
MKSA	meter-kilogram-second-ampere system
mL, ml	milliliter
mm	millimeter
MM	molecular mechanics
mmf	magnetomotive force
mmHg	millimeter of mercury
MO	molecular orbital

mol	mole
mol.wt.	molecular weight
mon	monomeric form
MOS	metal-oxide semiconductor
MOSFET	metal-oxide semiconductor field-effect transistor
mp	melting point
MPa	megapascal
MPA	Mulliken population analysis
Mpc	megaparsec
MRI	magnetic resonance imaging
mRNA	messenger RNA
ms	millisecond
MS	mass spectroscopy
MSL	mean sea level
Mur	muramic acid
mV	millivolt
mW	milliwatt
MW	megawatt, microwave, molecular weight
Mx	maxwell
n	neutron
n	amount of substance, number density, principal quantum number, refractive index, normal (in chemical formulas)
N	newton
N	angular momentum, neutron number
N_A	Avogadro constant
N_E	density of states
NAA	neutron activation analysis
NAD	nicotinamide adenine dinucleotide
NADH	reduced NAD
NADP	nicotinamide adenine dinucleotide phosphate
NAO	natural atomic orbital
NBO	natural bond order
nbp	normal boiling point
Neu	neuraminic acid
NEXAFS	near-edge x-ray absorption fine structure
ng	nanogram
NIR	near infrared
nm	nanometer
NMR	nuclear magnetic resonance
NNDO	neglect of nonbonded differential overlap
NO	natural orbital
NOE	nuclear Overhauser effect
NPA	natural population analysis
NQR	nuclear quadrupole resonance
NRA	prompt nuclear reaction analysis
ns	nanosecond
NTP	normal temperature and pressure
Nu	nucleophile
Nu	Nusselt number
o	*ortho* (as chemical descriptor)
obs, obsd	observed
OD	optical density, outside diameter
Oe	oersted
ORD	optical rotatory dispersion
oz	ounce
p	proton
p	dielectric polarization, electric dipole moment, momentum, pressure, *para* (as chemical descriptor)
P	poise
P	power, pressure, probability, sound energy flux
Pa	pascal
PA	proton affinity
PAS	photoacoustic spectroscopy
pc	parsec
PCR	polymerase chain reaction
PD	potential difference
pdl	poundal
pe	probable error
Pe	Péclet number
PES	photoelectron spectroscopy
PET	positron emission tomography
peth	petroleum ether
pf	power factor
pg	picogram
pH	negative log of hydrogen ion concentration
Ph	phenyl
Phe	phenylalanine
pI	isoelectric point
pip	piperidine
p*K*	negative log of ionization constant
pm	picometer
PMO	perturbational molecular orbital
PNDO	partial neglect of differential overlap
PNRA	prompt nuclear reaction analysis
pol	polymeric form
ppb	parts per billion
ppm	parts per million
PPP	Pariser-Parr-Pople (method)
ppt	parts per thousand, precipitate
Pr	propyl
Pr	Prandtl number
PRDDO	partial retention of diatomic differential overlap
Pro	proline
ps	picosecond
PS	photoelectron spectroscopy
PSD	photon stimulated desorption
Psi	psicose
psi	pounds per square inch
psia	pounds per square inch absolute
psig	pounds per square inch gage
pt	pint
PVT	pressure-volume-temperature
py	pyridine
q	electric field gradient, flow rate, heat, wave vector (phonons)
Q	electric charge, heat, partition function, quadrupole moment, radiant energy, vibrational normal coordinate
QCD	quantum chromodynamics
QED	quantum electrodynamics
Q.E.D.	quod erat demonstrandum (which was to be proved)
QSAR	quantitative structure-activity relationship
QSO	quasi-stellar object (quasar)
qt	quart
quad	quadrillion Btu (= 1.05510^{18} J)
Qui	quinovose
q.v.	quod vide (which you should see)
r	reaction
r	position vector, radius
R	roentgen, alkyl radical (in chemical formulas)
°R	degree Rankine
R	electrical resistance, gas constant, molar refraction, Rydberg constant
RA	right ascension
rad	radian
RAIRS	reflection-absorption infrared spectroscopy
RAM	random access memory
RBS	Rutherford backscattering spectroscopy
RE	resonance energy
Re	real part
RED	radial electron distribution
REM	reflection electron microscopy

rem	roentgen equivalent man
RF	radiofrequency
Rha	rhamnose
RHEED	reflection high-energy electron diffraction
RHF	restricted Hartree-Fock (theory)
RIA	radioimmunoassay
Rib	ribose
Ribulo	ribulose
rms	root mean square
RNA	ribonucleic acid
RNase	ribonuclease
rRNA	ribosomal RNA
ROHF	restricted open shell Hartree-Fock
ROM	read only memory
RPA	random phase approximation
rpm	revolutions per minute
rps	revolutions per second
RRK	Rice-Ramsperger-Kassel (theory)
RRKM	Rice-Ramsperger-Kassel-Marcus (theory)
RRS	resonance Raman spectroscopy
RS	Raman spectroscopy
Ry	rydberg
s	second, solid
s	path length, solubility, spin angular momentum, symmetry number, symmetrical (as stereochemical descriptor)
S	siemens
S	area, entropy, probability current density, Poynting vector, symmetry coordinate, spin angular momentum
SALC	symmetry adapted linear combinations
SALI	surface analysis by laser ionization
SAM	scanning Auger microscopy
SANS	small angle neutron scattering
Sar	sarcosine
sat, satd	saturated
SAXS	small angle x-ray scattering
s-Bu	*sec*-butyl
Sc	Schmidt number
SCE	saturated calomel electrode
SCF	self-consistent field
SCR	silicon-controlled rectifier
sd	standard deviation
sec	secant, second
sec	secondary (in chemical name)
SEELFS	surface sensitive energy loss fine structure
SEM	scanning electron microscope
sepn	separation
Ser	serine
SERS	surface-enhanced Raman spectroscopy
SET	single electron transfer
SEXAFS	surface extended x-ray absorption fine structure
Sh	Sherwood number
SI	International System of Units
SIMS	secondary ion mass spectroscopy
sin	sine
SINDO	symmetrically orthogonalized INDO method
sinh	hyperbolic sine
SIPN	semi-interpenetrating polymer network
SLAM	scanning laser acoustic microscopy
sln	solution
SMO	semiempirical molecular orbital
SMOW	Standard Mean Ocean Water
SNMS	sputtered neutral mass spectroscopy
SNU	solar neutrino unit
SO	spin orbital
sol	soluble, solution
soln	solution
SOMO	singly occupied molecular orbital
Sor	sorbose
sp gr	specific gravity
SPM	scanned probe microscopy
sq	square
sr	steradian
Sr	Strouhal number
SSMS	spark source mass spectroscopy
St	stoke
St	Stanton number
std, stnd	standard (state)
STEM	scanning transmission electron microscope
STM	scanning tunneling microscopy
STO	Slater type orbital
STP	standard temperature and pressure
sub	sublimation, sublimes
Sv	sievert
t	metric tonne, triton
t	Celsius temperature, thickness, time, transport number
T	tesla
T	kinetic energy, period, term value, temperature (thermodynamic), torque, transmittance
Tag	tagatose
Tal	talose
tan	tangent
tanh	hyperbolic tangent
t-Bu	*tert*-butyl
TCA	trichloroacetic acid
TCE	trichloroethylene
tcne	tetracyanoethylene
TCSCF	two configuration self-consistent field
TE	transverse electric
TED	transmission electron diffraction, transferred electron device
TEM	transmission electron microscopy, transverse electromagnetic
temp	temperature
tert	tertiary (in chemical name)
TFD	Thomas-Fermi-Dirac (method)
TGA	thermo-gravimetric analysis
theor	theoretical
thf, THF	tetrahydrofuran
Thr	threonine
Thy	thymine
TL	thermoluminescence
TLC	thin-layer chromatography
TM	transverse magnetic
Tol	tolyl
Torr	torr
tRNA	transfer RNA
Trp	tryptophan
trs	transition
TS	transition state
tsp	teaspoon
Tyr	tyrosine
u	unified atomic mass unit
u	Bloch function, electric mobility, velocity
U	uracil (in genetic code)
U	electric potential difference, internal energy
UDP	uridine 5′-diphosphate
UHF	ultrahigh frequency, unrestricted Hartree-Fock (theory)
UMP	uridine 5′-monophosphate
uns, unsym	unsymmetrical (as chemical descriptor)

UPES	ultraviolet photoelectron spectroscopy
UPS	ultraviolet photoelectron spectroscopy
ur	urea
Ura	uracil
USP	United States Pharmacopeia
UT	universal time
UTP	uridine 5′-triphosphate
UV	ultraviolet
ν	reaction rate, specific volume, velocity, vibrational quantum number, vicinal (as chemical descriptor)
V	volt
V	electric potential, potential energy, volume
Val	valine
vap	vaporization
VB	valence band, valence bond
VCD	vibrational circular dichroism
VHF	very high frequency
vic	vicinal (on adjacent carbon atoms)
VIS	visible region of the spectrum
vit	vitreous
VSEPR	valence shell electron pair repulsion
VSLI	very large scale integrated (circuit)
VUV	vacuum ultraviolet
v/v	volume per volume (volume of solute divided by volume of solution, expressed as percent)
w	energy density, mass fraction, velocity, work
W	watt
W	radiant energy, statistical weight, work
WAXS	wide angle x-ray scattering
Wb	weber
We	Weber number
WKB	Wentzel-Kramers-Brillouin (method)
wt	weight
w/v	weight per volume (mass of solute divided by volume of solution, generally expressed as g/100 mL)
w/w	weight per weight (mass of solute divided by mass of solution, expressed as percent)
x	mole fraction
X	X unit, halogen (in chemical formula)
X	reactance
XAFS	x-ray absorption fine structure
XANES	x-ray absorption near-edge structure
XPES	x-ray photoelectron spectroscopy
XPS	x-ray photoelectron spectroscopy
XRD	x-ray diffraction
XRF	x-ray fluorescence
XRS	x-ray spectroscopy
Xyl	xylose
y, yr	year
Y	admittance, Planck function, Young's modulus
yd	yard
z	charge number (of an ion), collision frequency factor
Z	atomic number, compression factor, collision number, impedance, partition function, zusammen (*cis* configuration)
ZDO	zero differential overlap
ZPE, ZPVE	zero point vibrational energy
ZULU	Greenwich mean time
α	alpha particle
α	absorption coefficient, degree of dissociation, electric polarizability, expansion coefficient, fine structure constant
β	beta particle
γ	photon
γ	activity coefficient, conductivity, magnetogyric ratio, mass concentration, ratio of heat capacities, surface tension
Γ	Gruneisin parameter, level width, surface concentration
δ	chemical shift, Dirac delta function, Kronecker delta, loss angle
Δ	inertia defect, mass defect
ε	emittance, Levi-Civita symbol, linear strain, molar absorption coefficient, permittivity
η	overpotential, viscosity
θ	Bragg angle, temperature, scattering angle, surface coverage
Θ	quadrupole moment
κ	compressibility, conductivity, magnetic susceptibility, molar absorption coefficient, transmission coefficient
λ	absolute activity, radioactive decay constant, thermal conductivity, wavelength
Λ	angular momentum, ionic conductivity
μ	muon
μ	chemical potential, electric dipole moment, electric mobility, friction coefficient, Joule-Thompson coefficient, magnetic dipole moment, mobility, permeability
μF	microfarad
μg	microgram
μm	micrometer
μs	microsecond
ν	frequency, kinematic velocity, stoichiometric number, wavenumber
ν_e	neutrino
π	pion
Π	osmotic pressure, Peltier coefficient
ρ	density, reflectance, resistivity
σ	electrical conductivity, cross section, normal stress, shielding constant (NMR), Stefan-Boltzmann constant, surface tension
τ	transmittance, chemical shift, shear stress, relaxation time
ϕ	electrical potential, fugacity coefficient, osmotic coefficient, quantum yield, volume fraction, wavefunction
Φ	magnetic flux, potential energy, radiant power, work function
χ	magnetic susceptibility, electronegativity
χ_e	electric susceptibility
ψ	wavefunction
ω	circular frequency, angular velocity, harmonic vibration wavenumber, statistical weight
Ω	ohm
Ω	axial angular momentum, solid angle

GREEK, RUSSIAN, AND HEBREW ALPHABETS

The following table presents the Hebrew, Greek, and Russian alphabets, their letters, the names of the letters, and the English equivalents.

Hebrew[1,3]			Greek[4]			Russian	
א	aleph	’ 2	A α	alpha	a	А а	a
ב	beth	b, bh	B β	beta	b	Б б	b
ג	gimel	g, gh	Γ γ	gamma	g, n	В в	v
ד	daleth	d, dh	Δ δ	delta	d	Г г	g
ה	he	h	E ε	epsilon	e	Д д	d
ו	waw	w	Z ζ	zeta	z	Е е	e
ז	zayin	z	H η	eta	ē	Ж ж	zh
ח	heth	ḥ	Θ θ	theta	th	З з	z
ט	teth	ṭ	I ι	iota	i	И и Й й	i, ĭ
י	yodh	y	K κ	kappa	k	К к	k
כ ך	kaph	k, kh	Λ λ	lambda	l	Л л	l
ל	lamedh	l	M μ	mu	m	М м	m
מ ם	mem	m	N ν	nu	n	Н н	n
נ ן	nun	n	Ξ ξ	xi	x	О о	o
ס	samekh	s	O o	omicron	o	П п	p
ע	ayin	‘	Π π	pi	p	Р р	r
פ ף	pe	p, ph	P ρ	rho	r, rh	С с	s
צ ץ	sadhe	ṣ	Σ σ ς	sigma	s	Т т	t
ק	qoph	q	T τ	tau	t	У у	u
ר	resh	r	Ῠ υ	upsilon	y, u	Ф ф	f
שׁ	sin	ś	Φ ϕ	phi	ph	Х х	kh
שׂ	shin	sh	X χ	chi	ch	Ц ц	ts
ת	taw	t, th	Ψ ψ	psi	ps	Ч ч	ch
			Ω ω	omega	ō	Ш ш	sh
						Щ щ	shch
						Ъ ъ[5]	”
						Ы ы	y
						Ь ь[6]	’
						Э э	e
						Ю ю	yu
						Я я	ya

[1] Where two forms of a letter are given, the second one is the form used at the end of a word.
[2] Not represented in transliteration when initial.
[3] The Hebrew letters are primarily consonants; a few of them are also used secondarily to represent certain vowels, when provided at all, by means of a system of dots or strokes adjacent to the consonated characters.
[4] The letter gamma is transliterated “n”only before velars; the letter upsilon is transliterated “u”only as the final element in diphthongs.
[5] This sign indicates that the immediately preceding consonant is not palatized even though immediately followed by a palatized vowel.
[6] This sign indicates that the immediately preceding consonant is palatized even though not immediately followed by a palatized vowel.

DEFINITIONS OF SCIENTIFIC TERMS

Brief definitions of selected terms of importance in chemistry, physics, and related fields of science are given in this section. The selection process emphasizes the following types of terms:

- Physical quantities
- Units of measure
- Classes of chemical compounds and materials
- Important theories, laws, and basic concepts.

Individual chemical compounds are not included.

Definitions have taken wherever possible from the recommendations of international or national bodies, especially the International Union of Pure and Applied Chemistry (IUPAC) and International Organization for Standardization (ISO). For physical quantities and units, the recommended symbol is also given. The source of such definitions is indicated by the reference number in brackets following the definition. In many cases these official definitions have been edited in the interest of stylistic consistency and economy of space. The user is referred to the original source for further details.

An asterisk (*) following a term indicates that further information can be found by consulting the index of this handbook under the entry for that term.

References

1. *ISO Standards Handbook 2, Units of Measurement*, International Organization for Standardization, Geneva, 1992.
2. *Quantities, Units, and Symbols in Physical Chemistry, Second Edition*, International Union of Pure and Applied Chemistry, Blackwell Scientific Publications, Oxford, 1993.
3. *Compendium of Chemical Terminology*, International Union of Pure and Applied Chemistry, Blackwell Scientific Publications, Oxford, 1987.
4. *A Guide to IUPAC Nomenclature of Organic Compounds*, International Union of Pure and Applied Chemistry, Blackwell Scientific Publications, Oxford, 1993.
5. *Glossary of Class Names of Organic Compounds and Reactive Intermediates Based on Structure, Pure and Applied Chemistry*, 67, 1307, 1995.
6. *Compendium of Analytical Nomenclature*, International Union of Pure and Applied Chemistry, Blackwell Scientific Publications, Oxford, 1987.
7. *Nomenclature of Inorganic Chemistry*, International Union of Pure and Applied Chemistry, Blackwell Scientific Publications, Oxford, 1990.
8. *Glossary of Basic Terms in Polymer Science, Pure and Applied Chemistry*, 68, 2287, 1996.
9. *The International Temperature Scale of 1990, Metrologia*, 27, 107, 1990.
10. *Compilation of ASTM Standard Definitions*, American Society of Testing and Materials, Philadelphia, 1990.
11. *ASM Metals Reference Book*, American Society for Metals, Metals Park, OH, 1983.

***Ab initio* method** - An approach to quantum-mechanical calculations on molecules which starts with the Schrödinger equation and carries out a complete integration, without introducing empirical factors derived from experimental measurement.

Absorbance (*A*) - Defined as $-\log(1-\alpha) = \log(1/\tau)$, where α is the absorptance and τ the transmittance of a medium through which a light beam passes. [2]

Absorbed dose (*D*) - For any ionizing radiation, the mean energy imparted to an element of irradiated matter divided by the mass of that element. [1]

Absorptance (α) - Ratio of the radiant or luminous flux in a given spectral interval absorbed in a medium to that of the incident radiation. Also called absorption factor. [1]

Absorption coefficient (*a*) - The relative decrease in the intensity of a collimated beam of electromagnetic radiation, as a result of absorption by a medium, during traversal of an infinitesimal layer of the medium, divided by the length traversed. [1]

Absorption coefficient, molar (ε) - Absorption coefficient divided by amount-of-substance concentration of the absorbing material in the sample solution ($\varepsilon = a/c$). The SI unit is m^2/mol. Also called extinction coefficient, but usually in units of $mol^{-1}dm^3cm^{-1}$. [2]

Acceleration - Rate of change of velocity with respect to time.

Acceleration due to gravity (*g*)* - The standard value (9.80665 m/s^2) of the acceleration experienced by a body in the earth's gravitational field. [1]

Acenes - Polycyclic aromatic hydrocarbons consisting of fused benzene rings in a rectilinear arrangement. [5]

Acid - Historically, a substance that yields an H^+ ion when it dissociates in solution, resulting in a pH<7. In the Brönsted definition, an acid is a substance that donates a proton in any type of reaction. The most general definition, due to G.N. Lewis, classifies any chemical species capable of accepting an electron pair as an acid.

Acid dissociation constant (K_a)* - The equilibrium constant for the dissociation of an acid HA through the reaction $HA + H_2O \rightleftharpoons A^- + H_3O^+$. The quantity $pK_a = -\log K_a$ is often used to express the acid dissociation constant.

Actinides - The elements of atomic number 89 through 103, e.g., Ac, Th, Pa, U, Np, Pu, Am, Cm, Bk, Cf, Es, Fm, Md, No, Lr. [7]

Activation energy* - In general, the energy that must be added to a system in order for a process to occur, even though the process may already be thermodynamically possible. In chemical kinetics, the activation energy is the height of the potential barrier separating the products and reactants. It determines the temperature dependence of the reaction rate.

Activity - For a mixture of substances, the absolute activity λ of substance B is defined as $\lambda_B = \exp(\mu_B/RT)$, where μ_B is the chemical potential of substance B, R the gas constant, and T the thermodynamic temperature. The relative activity a is defined as $a_B = \exp[(\mu_B - \mu_B^\circ)/RT]$, where μ_B° designates the chemical potential in the standard state. [2]

Activity coefficient (γ)* - Ratio of the activity a_B of component B of a mixture to the concentration of that component. The value of γ depends on the method of stating the composition. For mole fraction x_B, the relation is $a_B = \gamma_B x_B$; for molarity c_B, it is $a_B = \gamma_B c_B/c^\circ$, where c° is the standard state composition (typically chosen as 1 mol/L); for molality m_B, it is $a_B = \gamma_B m_B/m^\circ$, where m° is the standard state molality (typically 1 mol/kg). [2]

Activity, of radioactive substance (*A*) - The average number of spontaneous nuclear transitions from a particular energy state occurring in an amount of a radionuclide in a small time interval divided by that interval. [1]

Acyl groups - Groups formed by removing the hydroxy groups from oxoacids that have the general structure RC(=O)(OH) and replacement analogues of such acyl groups. [5]

Adiabatic process - A thermodynamic process in which no heat enters or leaves the system.

Admittance (*Y*) - Reciprocal of impedance. $Y = G + iB$, where G is conductance and B is susceptance. [1]

Adsorption - A process in which molecules of gas, of dissolved substances in liquids, or of liquids adhere in an extremely thin layer to surfaces of solid bodies with which they are in contact. [10]

Albedo* - The ratio of the light reflected or scattered from a surface to the intensity of incident light. The term is often used in reference to specific types of terrain or to entire planets.

Alcohols - Compounds in which a hydroxy group, -OH, is attached to a saturated carbon atom. [5]

Aldehydes - Compounds RC(=O)H, in which a carbonyl group is bonded to one hydrogen atom and to one R group. [5]

Aldoses - Aldehydic parent sugars (polyhydroxyaldehydes $H[CH(OH)]_nC(=O)H$, $n>1$) and their intramolecular hemiacetals. [5]

Aldoximes - Oximes of aldehydes: RCH=NOH. [5]

Alfvén number (*Al*) - A dimensionless quantity used in plasma physics, defined by $Al = v(\rho\mu)^{1/2}/B$, where ρ is density, v is velocity, μ is permeability, and B is magnetic flux density. [2]

Alfven waves - Very low frequency waves which can exist in a plasma in the presence of a uniform magnetic field. Also called magnetohydrodynamic waves.

Alicyclic compounds - Aliphatic compounds having a carbocyclic ring structure which may be saturated or unsaturated, but may not be a benzenoid or other aromatic system. [5]

Aliphatic compounds - Acyclic or cyclic, saturated or unsaturated carbon compounds, excluding aromatic compounds. [5]

Alkali metals - The elements lithium, sodium, potassium, rubidium, cesium, and francium.

Alkaline earth metals - The elements calcium, strontium, barium, and radium. [7]

Alkaloids - Basic nitrogen compounds (mostly heterocyclic) occurring mostly in the plant kingdom (but not excluding those of animal origin). Amino acids, peptides, proteins, nucleotides, nucleic acids, and amino sugars are not normally regarded as alkaloids. [5]

Alkanes - Acyclic branched or unbranched hydrocarbons having the general formula C_nH_{2n+2}, and therefore consisting entirely of hydrogen atoms and saturated carbon atoms. [5]

Alkenes - Acyclic branched or unbranched hydrocarbons having one carbon-carbon double bond and the general formula C_nH_{2n}. Acyclic branched or unbranched hydrocarbons having more than one double bond are alkadienes, alkatrienes, etc. [5]

Alkoxides - Compounds, ROM, derivatives of alcohols, ROH, in which R is saturated at the site of its attachment to oxygen and M is a metal or other cationic species. [5]

Alkyl groups - Univalent groups derived from alkanes by removal of a hydrogen atom from any carbon atom: C_nH_{2n+1}-. The groups derived by removal of a hydrogen atom from a terminal carbon atom of unbranched alkanes form a subclass of normal alkyl (*n*-alkyl) groups. The groups RCH_2-, R_2CH-, and R_3C- (R not equal to H) are primary, secondary, and tertiary alkyl groups, respectively. [5]

Alkynes - Acyclic branched or unbranched hydrocarbons having a carbon-carbon triple bond and the general formula C_nH_{2n-2}, RC≡CR´. Acyclic branched or unbranched hydrocarbons having more than one triple bond are known as alkadiynes, alkatriynes, etc. [5]

Allotropy - The occurrence of an element in two or more crystalline forms.

Allylic groups - The group CH_2=$CHCH_2$- (allyl) and derivatives formed by substitution. The term 'allylic position' or 'allylic site' refers to the saturated carbon atom. A group, such as -OH, attached at an allylic site is sometimes described as "allylic". [5]

Amagat volume unit - A non-SI unit previously used in high pressure science. It is defined as the molar volume of a real gas at one atmosphere pressure and 273.15 K. The approximate value is 22.4 L/mol.

Amides - Derivatives of oxoacids R(C=O)(OH) in which the hydroxy group has been replaced by an amino or substituted amino group. [5]

Amine oxides - Compounds derived from tertiary amines by the attachment of one oxygen atom to the nitrogen atom: R_3N^+-O^-. By extension the term includes the analogous derivatives of primary and secondary amines. [5]

Amines - Compounds formally derived from ammonia by replacing one, two, or three hydrogen atoms by hydrocarbyl groups, and having the general structures RNH_2 (primary amines), R_2NH (secondary amines), R_3N (tertiary amines). [5]

Amino acids* - Compounds containing both a carboxylic acid group (-COOH) and an amino group (-NH_2). The most important are the α-amino acids, in which the -NH_2 group in attached to the C atom adjacent to the -COOH group. In the β-amino acids, there is an intervening carbon atom. [4]

Ampere (A)* - The SI base unit of electric current. [1]

Ampere's law - The defining equation for the magnetic induction $\boldsymbol{B}$, viz., $d\boldsymbol{F} = I d\boldsymbol{l} \times \boldsymbol{B}$, where $d\boldsymbol{F}$ is the force produced by a current I flowing in an element of the conductor $d\boldsymbol{l}$ pointing in the direction of the current.

Ångström (Å) - A unit of length used in spectroscopy, crystallography, and molecular structure, equal to 10^{-10} m.

Angular momentum (*L*) - The angular momentum of a particle about a point is the vector product of the radius vector from this point to the particle and the momentum of the particle; i.e., $\boldsymbol{L} = \boldsymbol{r} \times \boldsymbol{p}$. [1]

Angular velocity (ω) - The angle through which a body rotates per unit time.

Anilides - Compounds derived from oxoacids R(C=O)(OH) by replacing the -OH group by the -NHPh group or derivative formed by ring substitution. Also used for salts formed by replacement of a nitrogen-bound hydrogen of aniline by a metal. [5]

Anion - A negatively charged atomic or molecular particle.

Antiferroelectricity* - An effect analogous to antiferromagnetism in which electric dipoles in a crystal are ordered in two sublattices that are polarized in opposite directions, leading to zero net polarization. The effect vanishes above a critical temperature.

Antiferromagnetism* - A type of magnetism in which the magnetic moments of atoms in a solid are ordered into two antiparallel aligned sublattices. Antiferromagnets are characterized by a zero or small positive magnetic susceptibility. The

susceptibility increases with temperature up to a critical value, the Néel temperature, above which the material becomes paramagnetic.

Antiparticle - A particle having the same mass as a given elementary particle and a charge equal in magnitude but opposite in sign.

Appearance potential* - The lowest energy which must be imparted to the parent molecule to cause it to produce a particular specified parent ion. This energy, usually stated in eV, may be imparted by electron impact, photon impact, or in other ways. More properly called appearance energy. [3]

Appearance potential spectroscopy (APS) - See Techniques for Materials Characterization, page 12-1.

Are (a) - A unit of area equal to 100 m^2. [1]

Arenes - Monocyclic and polycyclic aromatic hydrocarbons. See aromatic compounds. [5]

Aromatic compounds - Compounds whose structure includes a cyclic delocalized π-electron system. Historical use of the term implies a ring containing only carbon (e.g., benzene, naphthalene), but it is often generalized to include heterocyclic structures such as pyridine and thiophene. [5]

Arrhenius equation - A key equation in chemical kinetics which expresses the rate constant k as $k = A\exp(-E_a/RT)$, where E_a is the activation energy, R the molar gas constant, and T the temperature. A is called the preexponential factor and, for simple gas phase reactions, may be identified with the collision frequency.

Arsines - AsH_3 and compounds derived from it by substituting one, two or three hydrogen atoms by hydrocarbyl groups. $RAsH_2$, R_2AsH, R_3As (R not equal to H) are called primary, secondary and tertiary arsines, respectively. [5]

Aryl groups - Groups derived from arenes by removal of a hydrogen atom from a ring carbon atom. Groups similarly derived from heteroarenes are sometimes subsumed in this definition. [5]

Astronomical unit (AU)* - The mean distance of the earth from the sun, equal to $1.49597870 \times 10^{11}$ m.

Atomic absorption spectroscopy (AAS) - See Techniques for Materials Characterization, page **12-**1.

Atomic emission spectroscopy (AES) - See Techniques for Materials Characterization, page **12-**1.

Atomic force microscopy (AFM) - See Techniques for Materials Characterization, page 12-1.

Atomic mass* - The mass of a nuclide, normally expressed in unified atomic mass units (u).

Atomic mass unit (u)* - A unit of mass used in atomic, molecular, and nuclear science, defined as the mass of one atom of ^{12}C divided by 12. Its approximate value is 1.66054×10^{-27} kg. Also called the unified atomic mass unit. [1]

Atomic number (Z) - A characteristic property of an element, equal to the number of protons in the nucleus.

Atomic weight (A_r)* - The ratio of the average mass per atom of an element to 1/12 of the mass of nuclide ^{12}C. An atomic weight can be defined for a sample of any given isotopic composition. The standard atomic weight refers to a sample of normal terrestrial isotopic composition. The term relative atomic mass is synonymous with atomic weight. [2]

Attenuated total reflection (ATR) - See Techniques for Materials Characterization, page 12-1.

Auger effect - An atomic process in which an electron from a higher energy level fills a vacancy in an inner shell, transferring the released energy to another electron which is ejected.

Aurora - An atmospheric phenomenon in which streamers of light are produced when electrons from the sun are guided into the thermosphere by the earth's magnetic field. It occurs in the polar regions at altitudes of 95—300 km.

Avogadro constant (N_A)* - The number of elementary entities in one mole of a substance.

Azeotrope - A liquid mixture in a state where the variation of vapor pressure with composition at constant temperature (or, alternatively, the variation of normal boiling point with composition) shows either a maximum or a minimum. Thus when an azeotrope boils the vapor has the same composition as the liquid.

Azides - Compounds bearing the group $-N_3$, viz. $-N=N^+=N^-$; usually attached to carbon, e.g. PhN_3, phenyl azide or azidobenzene. Also used for salts of hydrazoic acid, HN_3, e.g. NaN_3, sodium azide. [5]

Azines - Condensation products, $R_2C=NN=CR_2$, of two moles of a carbonyl compound with one mole of hydrazine. [5]

Azo compounds - Derivatives of diazene (diimide), HN=NH, wherein both hydrogens are substituted by hydrocarbyl groups, e.g., PhN=NPh, azobenzene or diphenyldiazene. [5]

Balmer series - The series of lines in the spectrum of the hydrogen atom which corresponds to transitions between the state with principal quantum number $n = 2$ and successive higher states. The wavelengths are given by $1/\lambda = R_H(1/4 - 1/n^2)$, where n = 3,4,... and R_H is the Rydberg constant for hydrogen. The first member of the series ($n = 2 \rightleftharpoons 3$), which is often called the H_α line, falls at a wavelength of 6563 Å.

Bar (bar) - A unit of pressure equal to 10^5 Pa.´

Bardeen-Cooper-Schrieffer (BCS) theory - A theory of superconductivity which is based upon the formation of electron pairs as a result of an electron-lattice interaction. The theory relates the superconducting transition temperature to the density of states and the Debye temperature.

Barn (b) - A unit used for expressing cross sections of nuclear processes, equal to 10^{-28} m^2.

Barrel - A unit of volume equal to 158.9873 L.

Baryon - Any elementary particle built up from three quarks. Examples are the proton, neutron, and various short-lived hyperons. Baryons have odd half-integer spins.

Base - Historically, a substance that yields an OH^- ion when it dissociates in solution, resulting in a pH>7. In the Brönsted definition, a base is a substance capable of accepting a proton in any type of reaction. The more general definition, due to G.N. Lewis, classifies any chemical species capable of donating an electron pair as a base.

Becquerel (Bq)* - The SI unit of radioactivity (disintegrations per unit time), equal to s^{-1}. [1]

Beer's law - An approximate expression for the change in intensity of a light beam that passes through an absorbing medium, viz., $\log(I/I_0) = -\varepsilon cl$, where I_0 is the incident intensity, I is the final intensity, ε is the molar (decadic) absorption coefficient, c is the molar concentration of the absorbing substance, and l is the path length. Also called the Beer-Lambert law

Binding energy* - A generic term for the energy required to decompose a system into two or more of its constituent parts. In nuclear physics, the binding energy is the energy differ-

ence between a nucleus and the separated nucleons of which it is composed (the energy equivalent of the mass defect). In atomic physics, it is the energy required to remove an electron from an atom.

Biot (Bi) - A name sometimes used for the unit of current in the emu system.

Birefringence - A property of certain crystals in which two refracted rays result from a single incident light ray. One, the ordinary ray, follows the normal laws of refraction, while the other, the extraordinary ray, exhibits a variable refractive index which depends on the direction in the crystal.

Black body radiation* - The radiation emitted by a perfect black body, i.e., a body which absorbs all radiation incident on it and reflects none. The wavelength dependence of the radiated energy density ρ (energy per unit volume per unit wavelength range) is given by the Planck formula

$$\rho = \frac{8\pi hc}{\lambda^5 (e^{hc/\lambda kt} - 1)}$$

where λ is the wavelength, h is Planck's constant, c is the speed of light, k is the Boltzmann constant, and T is the temperature.

Black hole - A very dense object, formed in a supernova explosion, whose gravitational field is so large that no matter or radiation can escape from the object.

Bloch wave function - A solution of the Schrödinger equation for an electron moving in a spatially periodic potential; used in the band theory of solids.

Bohr magneton (μ_B)* - The atomic unit of magnetic moment, defined as $eh/4\pi m_e$, where h is Planck's constant, m_e the electron mass, and e the elementary charge. It is the moment associated with a single electron spin.

Bohr, bohr radius (a_0)* - The radius of the lowest orbit in the Bohr model of the hydrogen atom, defined as $\varepsilon_o h^2/\pi m_e e^2$, where ε_o is the permittivity of a vacuum, h is Planck's constant, m_e the electron mass, and e the elementary charge. It is customarily taken as the unit of length when using atomic units.

Boiling point - The temperature at which the liquid and gas phases of a substance are in equilibrium at a specified pressure. The normal boiling point is the boiling point at normal atmospheric pressure (101.325 kPa).

Boltzmann constant (k)* - The molar gas constant R divided by Avogadro's constant.

Boltzmann distribution - An expression for the equilibrium distribution of molecules as a function of their energy, in which the number of molecules in a state of energy E is proportional to $\exp(-E/kT)$, where k is the Boltzmann constant and T is the temperature.

Bond strength - See Dissociation energy.

Born-Haber cycle* - A thermodynamic cycle in which a crystalline solid is converted to gaseous ions and then reconverted to the solid. The cycle permits calculation of the lattice energy of the crystal.

Bose-Einstein distribution - A modification of the Boltzmann distribution which applies to a system of particles that are bosons. The number of particles of energy E is proportional to $[e^{(E-\mu)/kT}-1]^{-1}$, where μ is a normalization constant, k is the Boltzmann constant, and T is the temperature.

Boson - A particle that obeys Bose-Einstein Statistics; specifically, any particle with spin equal to zero or an integer. This includes the photon, pion, deuteron, and all nuclei of even mass number.

Boyle's law - The empirical law, exact only for an ideal gas, which states that the volume of a gas is inversely proportional to its pressure at constant temperature.

Bragg angle (θ) - Defined by the equation $n\lambda = 2d\sin\theta$, which relates the angle θ between a crystal plane and the diffracted x-ray beam, the wavelength λ of the x-rays, the crystal plane spacing d, and the diffraction order n (any integer).

Bravais lattices* - The 14 distinct crystal lattices that can exist in three dimensions. They include three in the cubic crystal system, two in the tetragonal, four in the orthorhombic, two in the monoclinic, and one each in the triclinic, hexagonal, and trigonal systems.

Breakdown voltage - The potential difference at which an insulating substance undergoes a physical or chemical change that causes it to become a conductor, thus allowing current to flow through the sample.

Bremsstrahlung - Electromagnetic radiation generated when the velocity of a charged particle is reduced (literally, "braking radiation"). An example is the x-ray continuum resulting from collisions of electrons with the target in an x-ray tube.

Brewster angle - The angle of incidence for which the maximum degree of plane polarization occurs when a beam of unpolarized light is incident on the surface of a medium of refractive index n. At this angle, the angle between the reflected and refracted beams is 90°. The value of the Brewster angle is $\tan^{-1} n$.

Brillouin scattering - The scattering of light by acoustic phonons in a solid or liquid.

Brillouin zone - A region of allowed wave vectors and energy levels in a crystalline solid, which plays a part in the propagation of waves through the lattice.

British thermal unit (Btu) - A non-SI unit of energy, equal to approximately 1055 J. Several values of the Btu, defined in slightly different ways, have been used.

Brownian motion - The random movements of small particles suspended in a fluid, which arise from collisions with the fluid molecules.

Brunauer-Emmett-Teller method (BET) - See Techniques for Materials Characterization, page 12-1.

Buffer* - A solution designed to maintain a constant pH when small amounts of a strong acid or base are added. Buffers usually consist of a fairly weak acid and its salt with a strong base. Suitable concentrations are chosen so that the pH of the solution remains close to the pK_a of the weak acid.

Calorie (cal) - A non-SI unit of energy, originally defined as the heat required to raise the temperature of 1 g of water by 1°C. Several calories of slightly different values have been used. The thermochemical calorie is now defined as 4.184 J.

Candela (cd)* - The SI base unit of luminous intensity. [1]

Capacitance (C) - Ratio of the charge acquired by a body to the change in potential. [1]

Carbamates - Salts or esters of carbamic acid, $H_2NC(=O)OH$, or of N-substituted carbamic acids: $R_2NC(=O)OR'$, (R′ = hydrocarbyl or a cation). The esters are often called urethanes or urethans, a usage that is strictly correct only for the ethyl esters. [5]

Carbenes - The electrically neutral species H_2C: and its derivatives, in which the carbon is covalently bonded to two univa-

lent groups of any kind or a divalent group and bears two nonbonding electrons, which may be spin-paired (singlet state) or spin-non-paired (triplet state). [5]

Carbinols - An obsolete term for substituted methanols, in which the name carbinol is synonymous with methanol. [5]

Carbohydrates - Originally, compounds such as aldoses and ketoses, having the stoichiometric formula $C_n(H_2O)_n$ (hence "hydrates of carbon"). The generic term carbohydrate now includes mono-, oligo-, and polysaccharides, as well as their reaction products and derivatives. [5]

Carboranes - A contraction of carbaboranes. Compounds in which a boron atom in a polyboron hydride is replaced by a carbon atom with maintenance of the skeletal structure. [5]

Carboxylic acids - Oxoacids having the structure RC(=O)OH. The term is used as a suffix in systematic name formation to denote the -C(=O)OH group including its carbon atom. [5]

Carnot cycle - A sequence of reversible changes in a heat engine using a perfect gas as the working substance, which is used to demonstrate that entropy is a state function. The Carnot cycle also provides a means to calculate the efficiency of a heat engine.

Catalyst - A substance that participates in a particular chemical reaction and thereby increases its rate but without a net change in the amount of that substance in the system. [3]

Catenanes, catena compounds - Hydrocarbons having two or more rings connected in the manner of links of a chain, without a covalent bond. More generally, the class catena compounds embraces functional derivatives and hetero analogues. [5]

Cation - A positively charged atomic or molecular particle.

Centipoise (cP) - A common non-SI unit of viscosity, equal to mPa s.

Centrifugal distortion - An effect in molecular spectroscopy in which rotational levels are lowered in energy, relative to the values of a rigid rotor, as the rotational angular momentum increases. The effect may be understood classically as a stretching of the bonds in the molecule as it rotates faster, thus increasing the moment of inertia.

Ceramic - A nonmetallic material of very high melting point.

Cerenkov radiation - Light emitted when a beam of charged particles travels through a medium at a speed greater than the speed of light in the medium. It is typically blue in color.

Cgs system of units - A system of units based upon the centimeter, gram, and second. The cgs system has been supplanted by the International System (SI).

Chalcogens - The Group VIA elements (oxygen, sulfur, selenium, tellurium, and polonium). Compounds of these elements are called chalcogenides. [7]

Chaotic system - A complex system whose behavior is governed by deterministic laws but whose evolution can vary drastically when small changes are made in the initial conditions.

Charge - See Electric charge.

Charles' law - The empirical law, exact only for an ideal gas, which states that the volume of a gas is directly proportional to its temperature at constant pressure.

Charm - A quantum number introduced in particle physics to account for certain properties of elementary particles and their reactions.

Chelate - A compound characterized by the presence of bonds from two or more bonding sites within the same ligand to a central metal atom. [3]

Chemical potential - For a mixture of substances, the chemical potential of constituent B is defined as the partial derivative of the Gibbs energy G with respect to the amount (number of moles) of B, with temperature, pressure, and amounts of all other constituents held constant. Also called partial molar Gibbs energy. [2]

Chemical shift* - A small change in the energy levels (and hence in the spectra associated with these levels) resulting from the effects of chemical binding in a molecule. The term is used in fields such as NMR, Mössbauer, and photoelectron spectroscopy, where the energy levels are determined primarily by nuclear or atomic effects.

Chiral molecule - A molecule which cannot be superimposed on its mirror image. A common example is an organic molecule containing a carbon atom to which four different atoms or groups are attached. Such molecules exhibit optical activity, i.e., they rotate the plane of a polarized light beam.

Chlorocarbons - Compounds consisting solely of chlorine and carbon. [5]

Chromatography* - A method for separation of the components of a sample in which the components are distributed between two phases, one of which is stationary while the other moves. In gas chromatography the gas moves over a liquid or solid stationary phase. In liquid chromatography the liquid mixture moves through another liquid, a solid, or a gel. The mechanism of separation of components may be adsorption, differential solubility, ion-exchange, permeation, or other mechanisms. [6]

Clapeyron equation - A relation between pressure and temperature of two phases of a pure substance that are in equilibrium, viz., $\mathrm{d}p/\mathrm{d}T = \Delta_{\mathrm{trs}}S/\Delta_{\mathrm{trs}}V$, where $\Delta_{\mathrm{trs}}S$ is the difference in entropy between the phases and $\Delta_{\mathrm{trs}}V$ the corresponding difference in volume.

Clathrates - Inclusion compounds in which the guest molecule is in a cage formed by the host molecule or by a lattice of host molecules. [5]

Clausius (Cl) - A non-SI unit of entropy or heat capacity defined as cal/K = 4.184 J/K. [2]

Clausius-Clapeyron equation - An approximation to the Clapeyron equation applicable to liquid-gas and solid-gas equilibrium, in which one assumes an ideal gas with volume much greater than the condensed phase volume. For the liquid-gas case, it takes the form $\mathrm{d}(\ln p)/\mathrm{d}T = \Delta_{\mathrm{vap}}H/RT^2$, where R is the molar gas constant and $\Delta_{\mathrm{vap}}H$ is the molar enthalpy of vaporization. For the solid-gas case, $\Delta_{\mathrm{vap}}H$ is replaced by the molar enthalpy of sublimation, $\Delta_{\mathrm{sub}}H$.

Clausius-Mosotti equation - A relation between the dielectric constant ε_r at optical frequencies and the polarizability α:

$$\frac{\varepsilon_r - 1}{\varepsilon_r + 2} = \frac{\rho N_A \alpha}{3M\varepsilon_0}$$

where ρ is density, N_A is Avogadro's number, M is molar mass, and ε_0 is the permittivity of a vacuum.

Clebsch-Gordon coefficients - A set of coefficients used to describe the vector coupling of angular momenta in atomic and nuclear physics.

Codon - A set of three bases, chosen from the four primary bases found in the DNA molecule (uracil, cytosine, adenine, and guanine), which specifies the production of a particular amino

acid or carries some other genetic instruction. For example, the codon UCA specifies the amino acid serine, CAG specifies glutamine, etc. There are a total of 64 codons.

Coercive force - The magnetizing force at which the magnetic flux density is equal to zero. [10]

Coercivity* - The maximum value of coercive force that can be attained when a magnetic material is symmetrically magnetized to saturation induction. [10]

Coherent anti-Stokes Raman spectroscopy (CARS) - See Techniques for Materials Characterization, page **12-**1.

Colloid - Molecules or polymolecular particles dispersed in a medium that have, at least in one direction, a dimension roughly between 1 nm and 1 μm. [3]

Color center - A defect in a crystal that gives rise to optical absorption, thus changing the color of the material. A common type is the F-center, which results when an electron occupies the site of a negative ion.

Compressibility (κ)* - The fractional change of volume as pressure is increased, viz., $\kappa = -(1/V)(dV/dp)$. [1]

Compton wavelength (λ_C)* - In the scattering of electromagnetic radiation by a free particle (e.g., electron, proton), $\lambda_C = h/mc$ is the increase in wavelength, at a 90° scattering angle, corresponding to the transfer of energy from radiation to particle. Here h is Planck's constant, c the speed of light, and m the mass of the particle.

Conductance (G)* - For direct current, the reciprocal of resistance. More generally, the real part of admittance. [1]

Conductivity, electrical (σ)* - The reciprocal of the resistivity. [1]

Conductivity, thermal - See Thermal conductivity.

Congruent transformation - A phase transition (melting, vaporization, etc.) in which the substance preserves its exact chemical composition.

Constitutional repeating unit (CRU) - In polymer science, the smallest constitutional unit, the repetition of which constitutes a regular macromolecule, i.e., a macromolecule with all units connected identically with respect to directional sense. [8]

Copolymer - A polymer derived from more than one species of monomer. [8]

Coriolis effect - The deviation from simple trajectories when a mechanical system is described in a rotating coordinate system. It affects the motion of projectiles on the earth and in molecular spectroscopy leads to an important interaction between the rotational and vibrational motions. The effect may be described by an additional term in the equations of motion, called the Coriolis force.

Cosmic rays* - High energy nuclear particles, electrons, and photons, originating mostly outside the solar system, which continually bombard the earth's atmosphere.

Coulomb (C)* - The SI unit of electric charge, equal to A s. [1]

Coulomb's law - The statement that the force F between two electrical charges q_1 and q_2 separated by a distance r is $F = (4\pi\varepsilon_0)^{-1} q_1 q_2 / r^2$, where ε_0 is the permittivity of a vacuum.

Covalent bond - A chemical bond between two atoms whose stability results from the sharing of two electrons, one from each atom.

Cowling number (Co) - A dimensionless quantity used in plasma physics, defined by $Co = B^2/\mu\rho v^2$, where ρ is density, v is velocity, μ is permeability, and B is magnetic flux density. [2]

CPT theorem - A theorem in particle physics which states that any local Lagrangian theory that is invariant under proper Lorentz transformations is also invariant under the combined operations of charge conjugation, C, space inversion, P, and time reversal, T, taken in any order.

Critical point* - In general, the point on the phase diagram of a two-phase system at which the two coexisting phases have identical properties and therefore represent a single phase. At the liquid-gas critical point of a pure substance, the distinction between liquid and gas vanishes, and the vapor pressure curve ends. The coordinates of this point are called the critical temperature and critical pressure. Above the critical temperature, it is not possible to liquefy the substance.

Cross section (σ)* - A measure of the probability of collision (or other interaction) between a beam of particles and a target which it encounters. In rough terms it is the effective area the target particles present to the incident ones; however, the precise definition depends on the nature of the interaction. A general definition of σ is the number of encounters per unit time divided by nv, where n is the concentration of incident particles and v their velocity.

Crosslink - In polymer science, a small region in a macromolecule from which at least four chains emanate, and formed by reactions involving sites or groups on existing macromolecules or by interactions between existing macromolecules. [8]

Crown compounds - Macrocyclic polydentate compounds, usually uncharged, in which three or more coordinating ring atoms (usually oxygen or nitrogen) are or may become suitably close for easy formation of chelate complexes with metal ions or other cationic species. [5]

Crust* - The outer layer of the solid earth, above the Mohorovicic discontinuity. Its thickness averages about 35 km on the continents and about 7 km below the ocean floor.

Cryoscopic constant (E_f)* - The constant that expresses the amount by which the freezing point T_f of a solvent is lowered by a non-dissociating solute, through the relation $\Delta T_f = E_f m$, where m is the molality of the solute.

Curie (Ci) - A non-SI unit of radioactivity (disintegrations per unit time), equal to 3.7×10^{10} s^{-1}.

Curie temperature (T_C)* - For a ferromagnetic material, the critical temperature above which the material becomes paramagnetic. Also applied to the temperature at which the spontaneous polarization disappears in a ferroelectric solid. [1]

Cyanohydrins - Alcohols substituted by a cyano group, most commonly, but not limited to, examples having a CN and an OH group attached to the same carbon atom. They are formally derived from aldehydes or ketones by the addition of hydrogen cyanide. [5]

Cycloalkanes - Saturated monocyclic hydrocarbons (with or without side chains). See alicyclic compounds. Unsaturated monocyclic hydrocarbons having one endocyclic double or one triple bond are called cycloalkenes and cycloalkynes, respectively. [5]

Cyclotron resonance - The resonant absorption of energy from a system in which electrons or ions that are orbiting in a uniform magnetic field are subjected to radiofrequency or microwave radiation. The resonance frequency is given by $\nu = eH/2\pi m^* c$, where e is the elementary charge, H is the magnetic field strength, m^* is the effective mass of the charged particle, and c is the speed of light. The effect occurs in both solids (involving electrons or holes) and in low pressure gasses (involving ions)

Dalton (Da) - A name sometimes used in biochemistry for the unified atomic mass unit (u).

De Broglie wavelength - The wavelength associated with the wave representation of a moving particle, given by h/mv, where h is Planck's constant, m the particle mass, and v the velocity.

De Haas-Van Alphen effect - An effect observed in certain metals and semiconductors at low temperatures and high magnetic fields, characterized by a periodic variation of magnetic susceptibility with field strength.

Debye equation* - The relation between the relative permittivity (dielectric constant) ε_r, polarizability α, and permanent dipole moment μ in a dielectric material whose molecules are free to rotate. It takes the form

$$\frac{\varepsilon_r - 1}{\varepsilon_r + 2} = \frac{\rho N_A}{3M\varepsilon_0}\left(\alpha + \frac{\mu^2}{3kT}\right)$$

where ρ is density, N_A is Avogadro's number, M is molar mass, and ε_0 is the permittivity of a vacuum.

Debye length - In the Debye-Hückel theory of ionic solutions, the effective thickness of the cloud of ions of opposite charge which surrounds each given ion and shields the Coulomb potential produced by that ion.

Debye temperature (θ_D)* - In the Debye model of the heat capacity of a crystalline solid, $\theta_D = h\nu_D/k$, where h is Planck's constant, k is the Boltzmann constant, and ν_D is the maximum vibrational frequency the crystal can support. For $T << \theta_D$, the heat capacity is proportional to T^3.

Debye unit (D) - A non-SI unit of electric dipole moment used in molecular physics, equal to 3.335641×10^{-30} C m.

Debye-Waller factor (*D*) - The factor by which the intensity of a diffraction line is reduced because of lattice vibrations. [1]

Defect - Any departure from the regular structure of a crystal lattice. A Frenkel defect results when an atom or ion moves to an interstitial position and leaves behind a vacancy. A Schottky defect involves either a vacancy where the atom has moved to the surface or a structure where a surface atom has moved to an interstitial position.

Degree of polymerization - The number of monomeric units in a macromolecule or an oligomer molecule. [8]

Dendrite - A tree-like crystalline pattern often observed, for example, in ice crystals and alloys in which the crystal growth branches repeatedly.

Density (ρ)* - In the most common usage, mass density or mass per unit volume. More generally, the amount of some quantity (mass, charge, energy, etc.) divided by a length, area, or volume.

Density of states (N_E, ρ) - The number of one-electron states in an infinitesimal interval of energy, divided by the range of that interval and by volume. [1]

Dew point* - The temperature at which liquid begins to condense as the temperature of a gas mixture is lowered. In meteorology, it is the temperature at which moisture begins to condense on a surface in contact with the air.

Diamagnetism - A type of magnetism characterized by a negative magnetic susceptibility, so that the material, when placed in an external magnetic field, becomes weakly magnetized in the direction opposite to the field. This magnetization is independent of temperature.

Diazo compounds - Compounds having the divalent diazo group, $=N^+=N^-$, attached to a carbon atom, e.g., $CH_2=N_2$ diazomethane. [5]

Dielectric constant (ε)* - Ratio of the electric displacement in a medium to the electric field strength. Also called permittivity. [1]

Dienes - Compounds that contain two fixed double bonds (usually assumed to be between carbon atoms). Dienes in which the two double-bond units are linked by one single bond are termed conjugated. [5]

Differential scanning calorimetry (DSC) - See Techniques for Materials Characterization, page 12-1.

Differential thermal analysis (DTA) - See Techniques for Materials Characterization, page 12-1.

Diffusion* - The migration of atoms, molecules, ions, or other particles as a result of some type of gradient (concentration, temperature, etc.).

Diopter - A unit used in optics, formally equal to m^{-1}. It is used in expressing dioptic power, which is the reciprocal of the focal length of a lens.

Dipole moment, electric (*p*,μ)* - For a distribution of equal positive and negative charge, the magnitude of the dipole moment vector is the positive charge multiplied by the distance between the centers of positive and negative charge distribution. The direction is given by the line from the center of negative charge to the center of positive charge.

Dipole moment, magnetic (*m*,μ) - Formally defined in electromagnetic theory as a vector quantity whose vector product with the magnetic flux density equals the torque. The magnetic dipole generated by a current I flowing in a small loop of area A has a magnetic moment of magnitude IA. In atomic and nuclear physics, a magnetic moment is associated with the angular momentum of a particle; e.g., an electron with orbital angular momentum $\boldsymbol{l}$ exhibits a magnetic moment of $-e\boldsymbol{l}/2m_e$ where e is the elementary charge and m_e the mass of the electron. [1]

Disaccharides - Compounds in which two monosaccharides are joined by a glycosidic bond. [5]

Dislocation - An extended displacement of a crystal from a regular lattice. An edge dislocation results when one portion of the crystal has partially slipped with respect to the other, resulting in an extra plane of atoms extending through part of the crystal. A screw dislocation transforms successive atomic planes into the surface of a helix.

Dispersion - Splitting of a beam of light (or other electromagnetic radiation) of mixed wavelengths into the constituent wavelengths as a result of the variation of refractive index of the medium with wavelength.

Dissociation constant* - The equilibrium constant for a chemical reaction in which a compound dissociates into its constituent parts.

Dissociation energy (D_e)* - For a diatomic molecule, the difference between the energies of the free atoms at rest and the minimum in the potential energy curve. The term bond dissociation energy (D_0), which can be applied to polyatomic molecules as well, is used for the difference between the energies of the fragments resulting when a bond is broken and the energy of the original molecule in its lowest energy state. The term bond strength implies differences in enthalpy rather than energy.

Domain - A small region of a solid in which the magnetic or electric moments of the individual units (atoms, molecules, or ions) are aligned in the same direction.

Domain wall - The transition region between adjacent ferromagnetic domains, generally a layer with a thickness of a few hundred ångström units. Also called Bloch wall.

Doppler effect - The change in the apparent frequency of a wave (sound, light, or other) when the source of the wave is moving relative to the observer.

Dose equivalent (*H*) - The product of the absorbed dose of radiation at a point of interest in tissue and various modifying factors which depend on the type of tissue and radiation. [1]

Drift velocity - The velocity of charge carriers (electrons, ions, etc.) moving under the influence of an electric field in a medium which subjects the carriers to some frictional force.

Dyne (dyn) - A non-SI (cgs) unit of force, equal to 10^{-5} N.

Ebullioscopic constant (E_b)* - The constant that expresses the amount by which the boiling point T_b of a solvent is raised by a non-dissociating solute, through the relation $\Delta T_b = E_b m$, where m is the molality of the solute.

Eddy currents - Circulating currents set up in conducting bulk materials or sheets by varying magnetic fields.

Effinghausen effect - The appearance of a temperature gradient in a current carrying conductor that is placed in a transverse magnetic field. The direction of the gradient is perpendicular to the current and the field.

Eigenvalue - An allowed value of the constant a in the equation $Au = au$, where A is an operator acting on a function u (which is called an eigenfunction). In quantum mechanics, the outcome of any observation is an eigenvalue of the corresponding operator. Also called characteristic value.

Einstein - A non-SI unit used in photochemistry, equal to one mole of photons.

Einstein temperature (θ_V) - In the Einstein theory of the heat capacity of a crystalline solid, $\theta_V = h\nu/k$, where h is Planck's constant, k is the Boltzmann constant, and ν is the vibrational frequency of the crystal.

Einstein transition probability - A constant in the Einstein relation $A_{ij} + B_{ij}\rho$ for the probability of a transition between two energy levels i and j in a radiation field of energy density ρ. The A_{ij} coefficient describes the probability of spontaneous emission, while B_{ij} and B_{ji} govern the probability of stimulated emission and absorption, respectively ($B_{ij} = B_{ji}$).

Elastic limit - The greatest stress which a material is capable of sustaining without any permanent strain remaining after complete release of the stress. [10]

Elastic modulus - See Young's modulus.

Electric charge (*Q*) - The quantity of electricity; i.e., the property that controls interactions between bodies through electrical forces.

Electric current (*I*) - The charge passing through a circuit per unit time. [1]

Electric displacement (*D*) - A vector quantity whose magnitude equals the electric field strength multiplied by the permittivity of the medium and whose direction is the same as that of the field strength.

Electric field strength (*E*) - The force exerted by an electric field on a point charge divided by the electric charge. [1]

Electric potential (*V*) - A scalar quantity whose gradient is equal to the negative of the electric field strength.

Electrical conductance - See Conductance

Electrical resistance - See Resistance

Electrical resistivity - See Resistivity.

Electrochemical series* - An arrangement of reactions which produce or consume electrons in an order based on standard electrode potentials. A common arrangement places metals in decreasing order of their tendency to give up electrons.

Electrode potential* - The electromotive force of a cell in which the electrode on the left is the standard hydrogen electrode and that on the right is the electrode in question. [2]

Electrolysis - The decomposition of a substance as a result of passing an electric current between two electrodes immersed in the sample.

Electromotive force (emf) - The energy supplied by a source divided by the charge transported through the source. [1]

Electron* - An elementary particle in the family of leptons, with negative charge and spin of 1/2.

Electron affinity* - The energy difference between the ground state of a gas-phase atom or molecule and the lowest state of the corresponding negative ion.

Electron cyclotron resonance (ECR) - See Techniques for Materials Characterization, page 12-1.

Electron energy loss spectroscopy (EELS) - See Techniques for Materials Characterization, page 12-1.

Electron nuclear double resonance (ENDOR) - See Techniques for Materials Characterization, page 12-1.

Electron paramagnetic resonance (EPR) - See Techniques for Materials Characterization, page 12-1.

Electron probe microanalysis (EPMA) - See Techniques for Materials Characterization, page 12-1.

Electron spectroscopy for chemical analysis (ESCA) - See Techniques for Materials Characterization, page 12-1.

Electron spin (*s*) - The quantum number, equal to 1/2, that specifies the intrinsic angular momentum of the electron.

Electron stimulated desorption (ESD) - See Techniques for Materials Characterization, page 12-1.

Electron volt (eV)* - A non-SI unit of energy used in atomic and nuclear physics, equal to approximately 1.602177×10^{-19} J. The electron volt is defined as the kinetic energy acquired by an electron upon acceleration through a potential difference of 1 V. [1]

Electronegativity* - A parameter originally introduced by Pauling which describes, on a relative basis, the power of an atom or group of atoms to attract electrons from the same molecular entity. [3]

Electrophoresis - The motion of macromolecules or colloidal particles in an electric field. [3]

Emissivity (ε)* - Ratio of the radiant flux emitted per unit area to that of an ideal black body at the same temperature. Also called emittance. [1]

Emu - The electromagnetic system of units, based upon the cm, g, and s plus the emu of current (sometimes called the abampere).

Enantiomers - A chiral molecule and its non-superposable mirror image. The two forms rotate the plane of polarized light by equal amounts in opposite directions. Also called optical isomers.

Energy (*E,U*)* - The characteristic of a system that enables it to do work.

Energy gap* - In the theory of solids, the region between two energy bands, in which no bound states can occur.

Enols, alkenols - The term refers specifically to vinylic alcohols, which have the structure HOCR´=CR_2. Enols are tautomeric with aldehydes (R´ = H) or ketones (R´ not equal to H). [5]

Enthalpy (*H*)* - A thermodynamic function, especially useful when dealing with constant-pressure processes, defined by $H = E + PV$, where E is energy, P pressure, and V volume. [1]

Enthalpy of combustion* - The enthalpy change in a combustion reaction. Its negative is the heat released in combustion.

Enthalpy of formation, standard* - The enthalpy change for the reaction in which a substance is formed from its constituent elements, each in its standard reference state (normally refers to 1 mol, sometimes to 1 g, of the substance).

Enthalpy of fusion* - The enthalpy change in the transition from solid to liquid state.

Enthalpy of sublimation - The enthalpy change in the transition from solid to gas state.

Enthalpy of vaporization* - The enthalpy change in the transition from liquid to gas state.

Entropy (*S*)* - A thermodynamic function defined such that when a small quantity of heat dQ is received by a system at temperature T, the entropy of the system is increased by dQ/T, provided that no irreversible change takes place in the system. [1]

Entropy unit (e.u.) - A non-SI unit of entropy, equal to 4.184 J/K mol.

Ephemeris time - Time measured in tropical years from January 1, 1900.

Epoxy compounds - Compounds in which an oxygen atom is directly attached to two adjacent or non-adjacent carbon atoms of a carbon chain or ring system; thus cyclic ethers. [5]

Equation of continuity - Any of a class of equations that express the fact that some quantity (mass, charge, energy, etc.) cannot be created or destroyed. Such equations typically specify that the rate of increase of the quantity in a given region of space equals the net current of the quantity flowing into the region.

Equation of state* - An equation relating the pressure, volume, and temperature of a substance or system.

Equilibrium constant (*K*)* - For a chemical reaction $a\mathrm{A} + b\mathrm{B} \rightleftharpoons c\mathrm{C} + d\mathrm{D}$, the equilibrium constant is defined by:

$$K = \frac{a_{\mathrm{C}}{}^{c} \cdot a_{\mathrm{D}}{}^{d}}{a_{\mathrm{A}}{}^{a} \cdot a_{\mathrm{B}}{}^{b}}$$

where a_i is the activity of component i. To a certain approximation, the activities can be replaced by concentrations. The equilibrium constant is related to $\Delta_r G°$, the standard Gibbs energy change in the reaction, by $RT \ln K = -\Delta_r G°$.

Equivalent conductance - See Conductivity, electrical

Erg (erg) - A non-SI (cgs) unit of energy, equal to 10^{-7} J.

Esters - Compounds formally derived from an oxoacid RC(=O)(OH) and an alcohol, phenol, heteroarenol, or enol by linking, with formal loss of water from an acidic hydroxy group of the former and a hydroxy group of the latter. [5]

Esu - The electrostatic system of units, based upon the cm, g, and s plus the esu of charge (sometimes called the statcoulomb or franklin).

Ethers - Compounds with formula ROR, where R is not equal to H. [5]

Euler number (*Eu*) - A dimensionless quantity used in fluid mechanics, defined by $Eu = \Delta p/\rho v^2$, where p is pressure, ρ is density, and v is velocity. [2]

Eutectic - The point on a two-component solid-liquid phase diagram which represents the lowest melting point of any possible mixture. A liquid having the eutectic composition will freeze at a single temperature without change of composition.

Excitance (*M*) - Radiant energy flux leaving an element of a surface divided by the area of that element. [1]

Exciton - A localized excited state consisting of a bound electron-hole pair in a molecular or ionic crystal. The exciton can propagate through the crystal.

Exosphere - The outermost part of the earth's atmosphere, beginning at about 500 to 1000 km above the surface. It is characterized by densities so low that air molecules can escape into outer space.

Expansion coefficient - See thermal expansion coefficient.

Extended electron energy loss fine structure (EXELFS) - See Techniques for Materials Characterization, page 12-1.

Extended x-ray absorption fine structure (EXAFS) - See Techniques for Materials Characterization, page 12-1.

Extinction coefficient - See Absorption coefficient, molar

F-Center - See Color center

Fahrenheit temperature (°F) - The temperature scale based on the assignment of 32°F = 0°C and a temperature interval of °F =(5/9)°C; i.e., t/°F = (9/5)t/°C + 32.

Farad (F)* - The SI unit of electric capacitance, equal to C/V. [1]

Faraday constant (*F*)* - The electric charge of 1 mol of singly charged positive ions; i.e., $F = N_A e$, where N_A is Avogadro's constant and e is the elementary charge. [1]

Faraday effect* - The rotation of the plane of plane-polarized light by a medium placed in a magnetic field parallel to the direction of the light beam. The effect can be observed in solids, liquids, and gasses.

Fatty acids - Aliphatic monocarboxylic acids derived from or contained in esterified form in an animal or vegetable fat, oil, or wax. Natural fatty acids commonly have a chain of 4 to 28 carbons (usually unbranched and even-numbered), which may be saturated or unsaturated. By extension, the term is sometimes used to embrace all acyclic aliphatic carboxylic acids. [5]

Fermat's principle - The law that a ray of light traversing one or more media will follow a path which minimizes the time required to pass between two given points.

Fermi (f) - Name sometimes used in nuclear physics for the femtometer.

Fermi level - The highest energy of occupied states in a solid at zero temperature. Sometimes called Fermi energy. The Fermi surface is the surface in momentum space formed by electrons occupying the Fermi level.

Fermi resonance - An effect observed in vibrational spectroscopy when an overtone of one fundamental vibration closely coincides in energy with another fundamental of the same symmetry species. It leads to a splitting of vibrational bands.

Fermi-Dirac distribution - A modification of the Boltzmann distribution which takes into account the Pauli exclusion principle. The number of particles of energy E is proportional to $[e^{(E-\mu)/kT}+1]^{-1}$, where μ is a normalization constant, k the Boltzmann constant, and T the temperature. The distribution is applicable to a system of fermions.

Fermion - A particle that obeys Fermi-Dirac statistics. Specifically, any particle with spin equal to an odd multiple of 1/2. Examples are the electron, proton, neutron, muon, etc.

Ferrimagnetism* - A type of magnetism in which the magnetic moments of atoms in a solid are ordered into two nonequivalent sublattices with unequal magnetic moments, leading to a nonzero magnetic susceptibility.

Ferrite - A ferrimagnetic material of nominal formula MFe_2O_4, where M is a divalent metal; widely used in microwave switches and other solid state devices.

Ferroelectricity* - The retention of electric polarization by certain materials after the external field that produced the polarization has been removed.

Ferromagnetism* - A type of magnetism in which the magnetic moments of atoms in a solid are aligned within domains which can in turn be aligned with each other by a weak magnetic field. Some ferromagnetic materials can retain their magnetization when the external field is removed, as long as the temperature is below a critical value, the Curie temperature. They are characterized by a large positive magnetic susceptibility.

Fick's law - The statement that the flux J of a diffusing substance is proportional to the concentration gradient, i.e., $J = -D(\mathrm{d}c/\mathrm{d}x)$, where D is called the diffusion coefficient.

Field - A mathematical construct which describes the interaction between particles resulting from gravity, electromagnetism, or other physical phenomena. In classical physics a field is described by equations. Quantum field theory introduces operators to represent the physical observables.

Field emission microscopy (FEM) - See Techniques for Materials Characterization, page 12-1.

Field ion microscopy (FIM) - See Techniques for Materials Characterization, page 12-1.

Fine structure - The splitting in spectral lines that results from interactions of the electron spin with the orbital angular momentum.

Fine structure constant (α)* - Defined as $e^2/2hc\varepsilon_0$, where e is the elementary charge, h Planck's constant, c the speed of light, and ε_0 the permittivity of a vacuum. It is a measure of the strength of the electromagnetic interaction between particles.

First radiation constant (c_1)* - Constant ($= 2\pi hc^2$) in the equation for the radiant excitance M_λ of a black body:

$$M_\lambda = \frac{c_1 \lambda^{-5} \Delta\lambda}{e^{c_2/\lambda T} - 1}$$

where λ is the wavelength, T is the temperature, and $c_2 = hc/k$ is the second radiation constant.

Flash point - The lowest temperature at which vapors above a volatile combustible substance will ignite in air when exposed to a flame. [10]

Fluence (F) - Term used in photochemistry to specify the energy per unit area delivered in a given time interval, for example by a laser pulse. [2]

Fluorocarbons - Compounds consisting solely of fluorine and carbon. [5]

Fluxoid - The quantum of magnetic flux in superconductivity theory, equal to $hc/2e$, where h is Planck's constant, c the velocity of light, and e the elementary charge.

Force (F) - The rate of change of momentum with time. [1]

Force constants (f, k)* - In molecular vibrations, the coefficients in the expression of the potential energy in terms of atom displacements from their equilibrium positions. In a diatomic molecule, $f = \mathrm{d}^2V/\mathrm{d}r^2$, where $V(r)$ is the potential energy and r is the interatomic distance. [2]

Fourier number (Fo) - A dimensionless quantity used in fluid mechanics, defined by $Fo = at/l^2$, where a is thermal diffusivity, t is time, and l is length. [2]

Fourier transform infrared spectroscopy (FTIR) - A technique for obtaining an infrared spectrum by use of an interferometer in which the path length of one of the beams is varied. A Fourier transformation of the resulting interferogram yields the actual spectrum. The technique is also used for NMR and other types of spectroscopy.

Fractals - Geometrical objects that are self-similar under a change of scale; i.e., they appear similar at all levels of magnification. They can be considered to have fractional dimensionality. Examples occur in diverse fields such as geography (rivers and shorelines), biology (trees), and solid state physics (amorphous materials).

Franck-Condon principle - An important principle in molecular spectroscopy which states that the nuclei in a molecule remain essentially stationary while an electronic transition is taking place. The physical interpretation rests on the fact that the electrons move much more rapidly than the nuclei because of their much smaller mass.

Franklin (Fr) - Name sometimes given to the unit of charge in the esu system.

Fraunhofer diffraction - Diffraction of light in situations where the source and observation point are so far removed that the wave surfaces may be considered planar.

Fraunhofer lines - Sharp absorption lines in the spectrum of sunlight, caused by absorption of the solar blackbody radiation by atoms near the sun's surface.

Free radical - See Radicals. The term "free radical" is often used more broadly for molecules that have a paramagnetic ground state (e.g., O_2) and sometimes for any transient or highly reactive molecular species.

Freezing point - See Melting point

Frequency (ν)* - Number of cycles of a periodic phenomenon divided by time. [1]

Fresnel diffraction - Diffraction of light in a situation where the source and observation point are sufficiently close together that the curvature of the wave surfaces must be taken into account.

Froude number (Fr) - A dimensionless quantity used in fluid mechanics, defined by $Fr = v/(lg)^{1/2}$, where v is velocity, l is length, and g is acceleration due to gravity. [2]

Fugacity (f_B) - For a gas mixture, the fugacity of component B is defined as the absolute activity λ_B times the limit, as the pressure p approaches zero at constant temperature, of p_B/λ_B. [2]

Fullerenes - Compounds composed solely of an even number of carbon atoms, which form a cage-like fused-ring polycyclic system with twelve five-membered rings and the rest six-membered rings. The archetypal example is [60]fullerene, where the atoms and bonds delineate a truncated icosahedron. The term has been broadened to include any closed cage structure consisting entirely of three-coordinate carbon atoms. [5]

Fulvalenes - The hydrocarbon fulvalene and its derivatives formed by substitution (and by extension, analogues formed

by replacement of one or more carbon atoms of the fulvalene skeleton by a heteroatom). [5]

Fulvenes - The hydrocarbon fulvene and its derivatives formed by substitution (and by extension, analogues formed by replacement of one or more carbon atoms of the fulvene skeleton by a heteroatom). [5]

Fundamental vibrational frequencies* - In molecular spectroscopy, the characteristic vibrational frequencies obtained when the vibrational energy is expressed in normal coordinates. They determine the primary features of the infrared and Raman spectra of the molecule.

γ - Name sometimes used for microgram.

γ-rays* - Electromagnetic radiation (photons) with energy greater than about 0.1 MeV (wavelength less than about 1 pm).

g*-Factor of the electron - The proportionality factor in the equation relating the magnetic moment μ of an electron to its total angular momentum quantum number *J*, i.e., $\mu = -g\mu_B J$, where μ_B is the Bohr magneton. Also called Landé factor.

Gal - A non-SI unit of acceleration, equal to 0.01 m/s. Also called galileo.

Gallon (US) - A unit of volume equal to 3.785412 L.

Gallon (UK, Imperial) - A unit of volume equal to 4.546090 L.

Gauss (G) - A non-SI unit of magnetic flux density (*B*) equal to 10^{-4} T.

Gaussian system of units - A hybrid system used in electromagnetic theory, which combines features of both the esu and emu systems.

Gel - A colloidal system with a finite, but usually rather small, yield stress (the sheer stress at which yielding starts abruptly). [3]

Genetic code* - The set of relations between each of the 64 codons of DNA and a specific amino acid (or other genetic instruction).

Gibbs energy (*G*)* - An important function in chemical thermodynamics, defined by $G = H-TS$, where H is the enthalpy, S the entropy, and T the thermodynamic temperature. Sometimes called Gibbs free energy and, in older literature, simply "free energy". [2]

Gibbs phase rule - The relation $F = C - P + 2$, where C is the number of components in a mixture, P is the number of phases, and F is the degrees of freedom, i.e., the number of intensive variables that can be changed independently without affecting the number of phases.

Glass transition temperature* - The temperature at which an amorphous polymer is transformed, in a reversible way, from a viscous or rubbery condition to a hard and relatively brittle one. [10]

Glow discharge mass spectroscopy (GDMS) - See Techniques for Materials Characterization, page 12-1.

Gluon - A hypothetical particle postulated to take part in the binding of quarks, in analogy to the role of the photon in electromagnetic interactions.

Glycerides - Esters of glycerol (propane-1,2,3-triol) with fatty acids, widely distributed in nature. They are by long-established custom subdivided into triglycerides, 1,2- or 1,3-diglycerides, and 1- or 2-monoglycerides, according to the number and positions of acyl groups. [5]

Glycols - Dihydric alcohols in which two hydroxy groups are on different carbon atoms, usually but not necessarily adjacent. Also called diols. [5]

Grain (gr) - A non-SI unit of mass, equal to 64.79891 mg.

Grain boundary - The interface between two regions of different crystal orientation.

Grashof number (*Gr*) - A dimensionless quantity used in fluid mechanics, defined by $Gr = l^3 g\alpha\Delta T\rho^2/\eta^2$, where T is temperature, ρ is density, l is length, η is viscosity, α is cubic expansion coefficient, and g is acceleration of gravity. [2]

Gravitational constant (*G*)* - The universal constant in the equation for the gravitational force between two particles, $F = Gm_1m_2/r^2$, where r is the distance between the particles and m_1 and m_2 are their masses. [1]

Gray (Gy)* - The SI unit of absorbed dose of radiation, equal to J/kg. [1]

Gregorian calendar - The modification of the Julian calendar introduced in 1582 by Pope Gregory XII which specified that a year divisible by 100 is a leap year only if divisible by 400.

Grignard reagents - Organomagnesium halides, RMgX, having a carbon-magnesium bond (or their equilibrium mixtures in solution with $R_2Mg + MgX_2$). [5]

Gruneisen parameter (γ) - Defined by $\gamma = \alpha_V/\kappa\, c_V\, \rho$, where α_V is the cubic thermal expansion coefficient, κ is the isothermal compressibility, c_V is the specific heat capacity at constant volume, and ρ is the mass density. γ is independent of temperature for most crystalline solids. [1]

Gyromagnetic ratio (γ) - Ratio of the magnetic moment of a particle to its angular momentum. Also called magnetogyric ratio.

Hadron - Any elementary particle that can take part in the strong interaction. Hadrons are subdivided into baryons, with odd half integer spins, and mesons, which have zero or integral spin.

Hall effect* - The development of a transverse potential difference V in a conducting material when subjected to a magnetic field H perpendicular to the direction of the current. The potential difference is given by $V = R_H BJt$, where B is the magnetic induction, J the current density, t the thickness of the specimen in the direction of the potential difference, and R_H is called the Hall coefficient.

Halocarbon - A compound containing no elements other than carbon, hydrogen, and one or more halogens. In common practice, the term is used mainly for compounds of no more than four or five carbon atoms.

Halogens - The elements F, Cl, Br, I, and At. Compounds of these elements are called halogenides or halides. [7]

Hamiltonian (*H*) - An expression for the total energy of a mechanical system in terms of the momenta and positions of constituent particles. In quantum mechanics, the Hamiltonian operator appears in the eigenvalue equation $H\psi = E\psi$, where E is an energy eigenvalue and ψ the corresponding eigenfunction.

Hardness* - The resistance of a material to deformation, indentation, or scratching. Hardness is measured on various scales, such as Mohs, Brinell, Knoop, Rockwell, and Vickers. [10]

Hartmann number (*Ha*) - A dimensionless quantity used in plasma physics, defined by $Ha = Bl(\kappa/\eta)^{1/2}$, where B is magnetic flux density, l is length, κ is electric conductivity, and η is viscosity. [2]

Hartree (E_h)* - An energy unit used in atomic and molecular science, equal to approximately $4.3597482 \times 10^{-18}$ J.

Hartree-Fock method - A iterative procedure for solving the Schrödinger equation for an atom or molecule in which the equation is solved for each electron in an initial assumed po-

tential from all the other electrons. The new potential that results is used to repeat the calculation and the procedure continued until convergence is reached. Also called self-consistent field (SCF) method.

Heat capacity* - Defined in general as dQ/dT, where dQ is the amount of heat that must be added to a system to increase its temperature by a small amount dT. The heat capacity at constant pressure is $C_p = (\partial H/\partial T)_p$; that at constant volume is $C_V = (\partial E/\partial T)_V$, where H is enthalpy, E is internal energy, p is pressure, V is volume, and T is temperature. An upper case C normally indicates the molar heat capacity, while a lower case c is used for the specific (per unit mass) heat capacity. [1]

Heat of formation, vaporization, etc. - See corresponding terms under Enthalpy.

Hectare (ha) - A unit of area equal to 10^4 m^2. [1]

Heisenberg uncertainty principle - The statement that two observable properties of a system that are complementary, in the sense that their quantum-mechanical operators do not commute, cannot be specified simultaneously with absolute precision. An example is the position and momentum of a particle; according to this principle, the uncertainties in position Δq and momentum Δp must satisfy the relation $\Delta p \Delta q \geq h/4\pi$, where h is Planck's constant.

Heitler-London model - An early quantum-mechanical model of the hydrogen atom which introduced the concept of the exchange interaction between electrons as the primary reason for stability of the chemical bond.

Helicon - A low-frequency wave generated when a metal at low temperature is exposed to a uniform magnetic field and a circularly polarized electric field.

Helmholz energy (*A*) - A thermodynamic function defined by $A = E\text{-}TS$, where E is the energy, S the entropy, and T the thermodynamic temperature. [2]

Hemiacetals - Compounds having the general formula $R_2C(OH)OR'$ (R′ not equal to H). [5]

Henry (H)* - The SI unit of inductance, equal to Wb/A. [1]

Henry's law * - An expression which applies to an ideal dilute solution in which one or more gasses are dissolved, viz., $p_i = H_i x_i$, where p_i is the partial pressure of component i above the solution, x_i is its mole fraction in the solution, and H_i is the Henry's law constant (a characteristic of the given gas and solvent, as well as the temperature).

Hermitian operator - An operator A that satisfies the relation $\int u_m^* A u_n \, dx = (\int u_n^* A u_m \, dx)^*$, where * indicates the complex conjugate. The eigenvalues of Hermitian operators are real, and eigenfunctions belonging to different eigenvalues are orthogonal.

Hertz (Hz) - The SI unit of frequency, equal to s^{-1}. [1]

Heterocyclic compounds - Cyclic compounds having as ring members atoms of at least two different elements, e.g., quinoline, 1,2-thiazole, bicyclo[3.3.1]tetrasiloxane. [5]

Heusler alloys - Alloys of manganese, copper, aluminum, nickel, and sometimes other metals which find important uses as permanent magnets.

Holography - A technique for creating a three-dimensional image of a object by recording the interference pattern between a light beam diffracted from the object and a reference beam. The image can be reconstructed from this pattern by a suitable optical system.

Homopolymer - A polymer derived from one species of (real, implicit, or hypothetical) monomer. [8]

Hooke's law - The statement that the ratio of stress to strain is a constant in a totally elastic medium.

Horse power - A non-SI unit of energy, equal to approximately 746 W.

Hubble constant - The ratio of the recessional velocity of an extragalactic object to the distance of that object. Its value is about 2×10^{-18} s^{-1}.

Huckel theory - A simple approximation for calculating the energy of conjugated molecules in which only the resonance integrals between neighboring bonds are considered. Also called CNDO method (complete neglect of differential overlap).

Hume-Rothery rules - A set of empirical rules for predicting the occurrence of solid solutions in metallic systems. The rules involve size, crystal structure, and electronegativity.

Hund's rules - A series of rules for predicting the sequence of energy states in atoms and molecules. One of the important results is that when two electrons exist in different orbitals, the state with their spins parallel (triplet state) lies at lower energy than the state with antiparallel spins (singlet).

Hydrazines - Hydrazine (diazane), H_2NNH_2, and its hydrocarbyl derivatives. When one or more substituents are acyl groups, the compound is a hydrazide. [5]

Hydrocarbon - A compound containing only carbon and hydrogen. [5]

Hydrolysis - A reaction occurring in water in which a chemical bond is cleaved and a new bond formed with the oxygen atom of water.

Hyperfine structure - Splitting of energy levels and spectral lines into several closely spaced components as a result of interaction of nuclear spin angular momentum with other angular momenta in the atom or molecule.

Hysteresis* - An irreversible response of a system (parameter A) as a function of an external force (parameter F), usually symmetric with respect to the origin of the A vs. F graph after the initial application of the force. A common example is magnetic induction vs. magnetic field strength in a ferromagnet.

Ideal gas law - The equation of state $pV = RT$, which defines an ideal gas, where p is pressure, V molar volume, T temperature, and R the molar gas constant.

Ideal solution - A solution in which solvent-solvent and solvent-solute interactions are identical, so that properties such as volume and enthalpy are exactly additive. Ideal solutions follow Raoult's law, which states that the vapor pressure p_i of component i is $p_i = x_i p_i^*$, where x_i is the mole fraction of component i and p_i^* the vapor pressure of the pure substance i.

Ignition temperature* - The lowest temperature at which combustion of a material will occur spontaneously under specified conditions. Sometimes called autoignition temperature, kindling point. [10]

Imides - Diacyl derivatives of ammonia or primary amines, especially those cyclic compounds derived from diacids. Also used for salts having the anion RN_2^-. [5]

Impedence (*Z*) - The complex representation of potential difference divided by the complex representation of current. In terms of reactance X and resistance R, the impedance is given by $Z = R + iX$. [1]

Index of refraction (*n*)* - For a non-absorbing medium, the ratio of the velocity of electromagnetic radiation *in vacuo* to the phase velocity of radiation of a specified frequency in the medium. [1]

Inductance - The ratio of the electromagnetic force induced in a coil by a current to the rate of change of the current.

Inductive coupled plasma mass spectroscopy (ICPMS) - See Techniques for Materials Characterization, page 12-1.

Inertial defect - In molecular spectroscopy, the quantity I_c-I_a-I_b for a molecule whose equilibrium configuration is planar, where I_a, I_b, and I_c are the effective principal moments of inertia. The inertial defect for a rigid planar molecule would be zero, but vibration-rotation interactions in a real molecule lead to a positive inertial defect.

Insulator - A material in which the highest occupied energy band (valence band) is completely filled with electrons, while the next higher band (conduction band) is empty. Solids with an energy gap of 5 eV or more are generally considered as insulators at room temperature. Their conductivity is less than 10^{-6} S/m and increases with temperature.

Intercalation compounds - Compounds resulting from reversible inclusion, without covalent bonding, of one kind of molecule in a solid matrix of another compound, which has a laminar structure. The host compound, a solid, may be macromolecular, crystalline, or amorphous. [5]

International System of Units (SI)* - The unit system adopted by the General Conference on Weights and Measures in 1960. It consists of seven base units (meter, kilogram, second, ampere, kelvin, mole, candela), plus derived units and prefixes. [1]

International Temperature Scale (ITS-90)* - The official international temperature scale adopted in 1990. It consists of a set of fixed points and equations which enable the thermodynamic temperature to be determined from operational measurements. [9]

Ion - An atomic or molecular particle having a net electric charge. [3]

Ion exchange - A process involving the adsorption of one or several ionic species accompanied by the simultaneous desorption (displacement) of one or more other ionic species. [3]

Ion neutralization spectroscopy (INS) - See Techniques for Materials Characterization, page 12-1.

Ionic strength (*I*) - A measure of the total concentration of ions in a solution, defined by $I = 1/2\Sigma_i z_i^2 m_i$, where z_i is the charge of ionic species i and m_i is its molality. For a 1-1 electrolyte at molality m, $I = m$.

Ionization constant* - The equilibrium constant for a reaction in which a substance in solution dissociates into ions.

Ionization potential* - The minimum energy required to remove an electron from an isolated atom or molecule (in its vibrational ground state) in the gaseous phase. More properly called ionization energy. [3]

Irradiance (*E*) - The radiant energy flux incident on an element of a surface, divided by the area of that element. [1]

Isentropic process - A thermodynamic process in which the entropy of the system does not change.

Ising model - A model describing the coupling between two atoms in a ferromagnetic lattice, in which the interaction energy is proportional to the negative of the product of the spin components along a specified axis.

Isobar - A line connecting points of equal pressure on a graphical representation of a physical system.

Isochore - A line or surface of constant volume on a graphical representation of a physical system.

Isoelectric point* - The pH of a solution or dispersion at which the net charge on the macromolecules or colloidal particles is zero. In electrophoresis there is no motion of the particles in an electric field at the isoelectric point.

Isomers - In chemistry, compounds that have identical molecular formulas but differ in the nature or sequence of bonding of their atoms or in the arrangement of their atoms in space. In physics, nuclei of the same atomic number Z and mass number A but in different energy states. [3]

Isomorphs - Substances of different chemical nature but having the same crystal structure.

Isotactic macromolecule - A tactic macromolecule, essentially comprising only one species of repeating unit which has chiral or prochiral atoms in the main chain in a unique arrangement with respect to its adjacent constitutional units. [8]

Isotherm - A line connecting points of equal temperature on a graphical representation of a physical system.

Isothermal process - A thermodynamic process in which the temperature of the system does not change.

Isotones - Nuclides having the same neutron number N but different atomic number Z. [3]

Isotopes - Two or more nuclides with the same atomic number Z but different mass number A. The term is sometimes used synonymously with nuclide, but it is preferable to reserve the word nuclide for a species of specific Z and A. [3]

Jahn-Teller effect - An interaction of vibrational and electronic motions in a nonlinear molecule which removes the degeneracy of certain electronic energy levels. It can influence the spectrum, crystal structure, and magnetic properties of the substance.

Johnson noise - Electrical noise generated by random thermal motion of electrons in a conductor or semiconductor. Also called thermal noise.

Josephson effect - The tunneling of electron pairs through a thin insulating layer which separates two superconductors. When a potential difference is applied to the superconductors, an alternating current is generated whose frequency is precisely proportional to the potential difference. This effect has important applications in metrology and determination of fundamental physical constants.

Joule (J)* - The SI unit of energy, equal to N m. [1]

Joule-Thomson coefficient (μ) - A parameter which describes the temperature change when a gas expands adiabatically through a nozzle from a high pressure to a low pressure region. It is defined by $\mu = (\partial T/\partial p)_H$, where H is enthalpy.

Julian calendar - The calendar introduced by Julius Caeser in 46 B.C. which divided the year into 365 days with a leap year of 366 days every fourth year.

Julian date (JD) - The number of days elapsed since noon Greenwich Mean Time on January 1, 4713 B.C. Thus January 1, 2000, 0h (midnight) will be JD 2,451,543.5. This dating system was introduced by Joseph Scaliger in 1582.

Kaon - One of the elementary particles in the family of mesons. Kaons have a spin of zero and may be neutral or charged.

Kelvin (K)* - The SI base unit of thermodynamic temperature. [1]

Kepler's laws - The three laws of planetary motion, which established the elliptical shape of planetary orbits and the relation between orbital dimensions and the period of rotation.

Kerr effect* - An electrooptical effect in which birefringence is induced in a liquid or gas when a strong electric field is applied perpendicular to the direction of an incident light beam. The Kerr constant k is given by n_1-$n_2 = k\lambda E^2$, where λ is the wavelength, E is the electric field strength, and n_1 and n_2 are the indices of refraction of the ordinary and extraordinary rays, respectively.

Ketenes - Compounds in which a carbonyl group is connected by a double bond to an alkylidene group: $R_2C{=}C{=}O$. [5]

Ketones - Compounds in which a carbonyl group is bonded to two carbon atoms: $R_1R_2C{=}O$ (neither R may be H). [5]

Kilogram (kg)* - The SI base unit of mass. [1]

Kinetic energy (E_k, T) - The energy associated with the motion of a system of particles in a specified reference frame. For a single particle of mass m moving at velocity v, $E_k = 1/2mv^2$.

Kirchhoff's laws - Basic rules for electric circuits, which state (a) the algebraic sum of the currents at a network node is zero and (b) the algebraic sum of the voltage drops around a closed path is zero.

Klein-Gordon equation - A relativistic extension of the Schrödinger equation.

Klein-Nishima formula - An expression for the scattering cross section of a photon by an unbound electron, based upon the Dirac electron theory.

Knight shift - The change in magnetic resonance frequency of a nucleus in a metal relative to the same nucleus in a diamagnetic solid. The effect is due to the polarization of the conduction electrons in the metal.

Knudsen number (*Kn*) - A dimensionless quantity used in fluid mechanics, defined by $Kn = \lambda/l$, where λ is mean free path and l is length. [2]

Kondo effect - A large increase in electrical resistance observed at low temperatures in certain dilute alloys of a magnetic metal in a nonmagnetic material.

Kramers-Kronig relation - A set of equations relating the real and imaginary parts of the index of refraction of a medium

Lactams - Cyclic amides of amino carboxylic acids, having a 1-azacycloalkan-2-one structure, or analogues having unsaturation or heteroatoms replacing one or more carbon atoms of the ring. [5]

Lactones - Cyclic esters of hydroxy carboxylic acids, containing a 1-oxacycloalkan-2-one structure, or analogues having unsaturation or heteroatoms replacing one or more carbon atoms of the ring. [5]

Lagrangian function (*L*) - A function used in classical mechanics, defined as the kinetic energy minus the potential energy for a system of particles.

Lamb shift - The small energy difference between the $^2S_{1/2}$ and $^2P_{1/2}$ levels in the hydrogen atom, which results from interactions between the electron and the radiation field.

Laminar flow - Smooth, uniform, non-turbulent flow of a gas or liquid in parallel layers, with little mixing between layers. It is characterized by small values of the Reynolds number.

Landé *g*-factor - See *g*-Factor of the electron

Langevin function - The mathematical function $L(x) = (e^x+e^{-x})/(e^x-e^{-x})-1/x$, which occurs in the expression for the average dipole moment of a group of rotating polar molecules in an electric field: $\mu_{av} = \mu L(\mu E/kT)$, where μ is the electric dipole moment of a single molecule, E is the electric field strength, k is the Boltzmann constant, and T is the temperature.

Lanthanides - The elements of atomic number 57 through 71, which share common chemical properties: La, Ce, Pr, Nd, Pm, Sm, Eu, Gd, Tb, Dy, Ho, Er, Tm, Yb, Lu. [7]

Larmor frequency (ν_L) - The precession frequency of a magnetic dipole in an applied magnetic field. In particular, a nucleus in a magnetic field of strength B has a Larmor frequency of $\gamma B/2\pi$, where γ is the magnetogyric ratio of the nucleus.

Laser* - A device in which an optical cavity is filled with a medium where a population inversion can be produced by some means. When the resonant frequency of the cavity bears the proper relation to the separation of the inverted energy levels, stimulated emission occurs, producing a highly monochromatic, coherent beam of light.

Laser ionization mass spectroscopy (LIMS) - See Techniques for Materials Characterization, page 12-1.

Lattice constants* - Parameters specifying the dimensions of a unit cell in a crystal lattice, specifically the lengths of the cell edges and the angles between them.

Lattice energy* - The energy per ion pair required to separate completely the ions in a crystal lattice at a temperature of absolute zero.

Laue diagram - A diffraction pattern produced when an x-ray beam passes through a thin slice of a crystal and impinges on a detector behind the crystal.

Lenz's law - The statement that the current induced in a circuit by a change in magnetic flux is so directed as to oppose the change in flux

Leonard-Jones potential - A simple but useful function for approximating the interaction between two neutral atoms or molecules separated by a distance r by writing the potential energy as $U(r) = 4\varepsilon\{(r_0/r)^{12} - (r_0/r)^6\}$, where ε and r_0 are adjustable parameters. In this form the depth of the potential well is ε and the minimum occurs at $2^{1/6}r_0$. The $(1/r)^{12}$ term is often replaced by other powers of $1/r$.

Lepton - One of the class of elementary particles that do not take part in the strong interaction. Included are the electron, muon, and neutrino. All leptons have a spin of 1/2.

Lewis number (*Le*) - A dimensionless quantity used in fluid mechanics, defined by $Le = a/D$, where a is thermal diffusivity and D is diffusion coefficient. [2]

Ligand field theory - A description of the structure of crystals containing a transition metal ion surrounded by nonmetallic ions (ligands). It is based on construction of molecular orbitals involving the *d*-orbitals of the central metal ion and combinations of atomic orbitals of the ligands.

Light year (l.y.) - A unit of distance used in astronomy, defined as the distance light travels in one year in a vacuum. Its approximate value is 9.46073×10^{15} m.

Lignins - Macromolecular constituents of wood related to lignans, composed of phenolic propylbenzene skeletal units, linked at various sites and apparently randomly. [5]

Ligroin - The petroleum fraction consisting mostly of C_7 and C_8 hydrocarbons and boiling in the range 90-140°C; commonly used as a laboratory solvent.

Lipids - A loosely defined term for substances of biological origin that are soluble in nonpolar solvents. They consist of saponifiable lipids, such as glycerides (fats and oils) and phospholipids, as well as nonsaponifiable lipids, principally steroids. [5]

Lipoproteins - Clathrate complexes consisting of a lipid enwrapped in a protein host without covalent binding, in such a way that

the complex has a hydrophilic outer surface consisting of all the protein and the polar ends of any phospholipids. [5]

Liter (L)* - A synonym for cubic decimeter. [1]

Lithosphere* - The outer layer of the solid earth, extending from the base of the mantle to the surface of the crust.

Lorentz contraction - The reduction in length of a moving body in the direction of motion, given by the factor $(1-v^2/c^2)^{1/2}$, where v is the velocity of the body and c the velocity of light. Also known as the FitzGerald-Lorentz contraction.

Lorentz force - The force exerted on a point charge Q moving at velocity $\boldsymbol{v}$ in the presence of external fields $\boldsymbol{E}$ and $\boldsymbol{B}$. It is given (in SI units) by $\boldsymbol{F} = Q(\boldsymbol{E} + \boldsymbol{v} \times \boldsymbol{B})$.

Loss angle (δ) - For a dielectric material in an alternating electromagnetic field, δ is the phase difference between the current and the potential difference. The function tan δ is a measure of the ratio of the power dissipated in the dielectric to the power stored.

Low energy electron diffraction (LEED) - See Techniques for Materials Characterization, page 12-1.

Lumen (lm)* - The SI unit of luminous flux, equal to cd sr. [1]

Luminous flux (Φ) - The intensity of light from a source multiplied by the solid angle. The SI unit is lumen. [1]

Lux (lx)* - The SI unit of illuminance, equal to cd sr m^{-2}. [1]

Lyddane-Sachs-Teller relation - A relation between the phonon frequencies and dielectric constants of an ionic crystal which states that $(\omega_T/\omega_L)^2 = \varepsilon(\infty)/\varepsilon(0)$, where ω_T is the angular frequency of transverse optical phonons, ω_L that of longitudinal optical phonons, $\varepsilon(0)$ is the static dielectric constant, and $\varepsilon(\infty)$ the dielectric constant at optical frequencies.

Lyman series - The series of lines in the spectrum of the hydrogen atom which corresponds to transitions between the ground state (principal quantum number $n = 1$) and successive excited states. The wavelengths are given by $1/\lambda = R_H(1-1/n^2)$, where $n = 2,3,4,\ldots$ and R_H is the Rydberg constant for hydrogen. The first member of the series ($n = 1 \leftrightarrow 2$), which is often called the Lyman-α line, falls at a wavelength of 1216 Å, and the series converges at 912 Å, the ionization limit of hydrogen.

Mach number (*Ma*) - A dimensionless quantity used in fluid mechanics, defined by $Ma = v/c$, where v is velocity and c is the speed of sound. [2]

Macromolecule - A molecule of high relative molecular mass (molecular weight), the structure of which essentially comprises the multiple repetition of units derived, actually or conceptually, from molecules of low relative molecular mass [8]

Madelung constant* - A constant characteristic of a particular crystalline material which gives a measure of the electrostatic energy binding the ions in the crystal.

Magnetic field strength (*H*) - An axial vector quantity, the curl of which is equal to the current density, including the displacement current. [1]

Magnetic induction (*B*) - An axial vector quantity such that the force exerted on an element of current is equal to the vector product of this element and the magnetic induction. [1]

Magnetic moment - See Dipole moment, magnetic.

Magnetic susceptibility (χ_m, κ)* - Defined by $\chi_m = (\mu-\mu_0)/\mu_0$, where μ is the permeability of the medium and μ_0 the permeability of a vacuum. [1]

Magnetization (*M*) - Defined by $M = (B/\mu_0)-H$, where B is magnetic induction, H magnetic field strength, and μ_0 the permeability of a vacuum. [1]

Magnetogyric ratio (γ) - Ratio of the magnetic moment of a particle to its angular momentum. Also called gyromagnetic ratio.

Magneton - See Bohr magneton, Nuclear magneton.

Magnetostriction* - The change in dimensions of a solid sample when it is placed in a magnetic field.

Magnon - A quantum of magnetic energy associated with a spin wave in a ferromagnetic or antiferromagnetic crystal.

Mantle - The layer of the earth between the crust and the liquid outer core, which begins about 2900 km below the earth's surface.

Maser - A device in which a microwave cavity is filled with a medium where a population inversion can be produced by some means. When the resonant frequency of the cavity bears the proper relation to the separation of the inverted energy levels, the device can serve as an amplifier or oscillator at that frequency.

Mass (*m*)* - Quantity of matter. Mass can also be defined as "resistance to acceleration".

Mass defect (*B*) - Defined by $B = Zm(^1H) + Nm_n - m_a$, where Z is the atomic number, $m(^1H)$ is the mass of the hydrogen atom, N is the neutron number, m_n is the rest mass of the neutron, and m_a is the mass of the atom in question. Thus Bc^2 can be equated to the binding energy of the nucleus if the binding energy of atomic electrons is neglected. [1]

Mass excess (Δ) - Defined by $\Delta = m_a - Am_u$, where m_a is the mass of the atom, A the number of nucleons, and m_u the unified atomic mass constant ($m_u = 1$ u). [1]

Mass fraction (w_B) - The ratio of the mass of substance B to the total mass of a mixture. [1]

Mass number (*A*) - A characteristic property of a specific isotope of an element, equal to the sum of the number of protons and neutrons in the nucleus.

Mass spectrometry - An analytical technique in which ions are separated according to the mass/charge ratio and detected by a suitable detector. The ions may be produced by electron impact on a gas, a chemical reaction, energetic vaporization of a solid, etc. [6]

Massieu function - A thermodynamic function defined by $J = -A/T$, where A is the Helmholz energy and T the thermodynamic temperature. [2]

Matthiessen's rule - The statement that the electrical resistivity ρ of a metal can be written as $\rho = \rho_L + \rho_i$, where ρ_L is due to scattering of conduction electrons by lattice vibrations and ρ_i to scattering by impurities and imperfections. If the impurity concentration is small, ρ_i is temperature independent.

Maxwell (Mx)* - A non-SI unit of magnetic field strength (H) equal to 10^{-8} Wb. [1]

Maxwell's equations - The fundamental equations of electromagnetism. In a form appropriate to SI units, they are:

$$\text{curl } \boldsymbol{H} = \partial \boldsymbol{D}/\partial t + \boldsymbol{j}$$
$$\text{div } \boldsymbol{B} = 0$$
$$\text{curl } \boldsymbol{E} = -\partial \boldsymbol{B}/\partial t$$
$$\text{div } \boldsymbol{D} = \rho$$

where $\boldsymbol{H}$ is the magnetic field strength, $\boldsymbol{B}$ the magnetic induction, $\boldsymbol{E}$ the electric field strength, $\boldsymbol{D}$ the electric displacement, $\boldsymbol{j}$ the current density, ρ the charge density, and t is time.

Maxwell-Boltzmann distribution - An expression for the fraction of molecules $f(v)$ in a gas that have velocity v within a specified interval. It takes the form

$$f(v) = 4\pi(M/2\pi RT)^{3/2} v^2 e^{-Mv^2/2RT}$$

where M is the molar mass, R the molar gas constant, and T the temperature.

Mean free path* - The average distance a gas molecule travels between collisions.

Meissner effect - The complete exclusion of magnetic induction from the interior of a superconductor.

Melting point* - The temperature at which the solid and liquid phases of a substance are in equilibrium at a specified pressure (normally taken to be atmospheric unless stated otherwise).

Mercaptans - A traditional term abandoned by IUPAC, synonymous with thiols. This term is still widely used. [5]

Meson - Any elementary particle that has zero or integral spin. Mesons are responsible for the forces between protons and neutrons in the nucleus.

Mesosphere - The part of the earth's atmosphere extending from the top of the stratosphere (about 50 km above the surface) to 80-90 km. It is characterized by a decrease in temperature with increasing altitude.

Metal - A material in which the highest occupied energy band (conduction band) is only partially filled with electrons. The electrical conductivity of metals generally decreases with temperature.

Metallocenes - Organometallic coordination compounds in which one atom of a transition metal such as iron, ruthenium or osmium is bonded to and only to the face of two cyclopentadienyl ligands which lie in parallel planes. [5]

Meter (m)* - The SI base unit of length. [1]

Methine group - In organic compounds, the -C= group. [5]

Mho - An archaic name for the SI unit siemens (reciprocal ohm).

Micelle - A particle formed by the aggregation of surfactant molecules (typically, 10 to 100 molecules) in solution. For aqueous solutions, the hydrophilic end of the molecule is on the surface of the micelle, while the hydrophobic end (often a hydrocarbon chain) points toward the center. At the critical micelle concentration (cmc) the previously dissolved molecules aggregate into a micelle.

Micron (μ) - An obsolete name for micrometer.

Mie scattering - The scattering of light by spherical dielectric particles whose diameter is comparable to the wavelength of the light.

Milky way - The band of light in the night sky resulting from the stars in the galactic plane. The term is also used to denote the galaxy in which the sun is located.

Miller indices (*hkl*) - A set of indices used to label planes in a crystal lattice. [2]

Millimeter of mercury (mmHg) - A non-SI unit of pressure, equal to 133.322 Pa. The name is generally considered interchangeable with torr.

Mobility (μ)* - In solid state physics, the drift velocity of electrons or holes in a solid divided by the applied electric field strength. The term is used in a similar sense in other fields.

Molality (*m*) - A measure of concentration of a solution in which one states the amount of substance (i.e., number of moles) of solute per kilogram of solvent. Thus a 0.1 molal solution (often written as 0.1 m) has m = 0.1 mol/kg.

Molar mass - The mass of one mole of a substance. It is normally expressed in units of g/mol, in which case its numerical value is identical with the molecular weight (relative molecular mass). [1]

Molar quantity - It is often convenient to express an extensive quantity (e.g., volume, enthalpy, heat capacity, etc.) as the actual value divided by amount of substance (number of moles). The resulting quantity is called molar volume, molar enthalpy, etc

Molar refraction (*R*) - A property of a dielectric defined by the equation $R = V_m[(n^2-1)/(n^2+2)]$, where n is the index of refraction of the medium (at optical wavelengths) and V_m the molar volume. It is related to the polarizability α of the molecules that make up the medium by the Lorenz-Lorentz equation, $R = N_A\alpha/3\varepsilon_0$, where N_A is Avogadro's constant and ε_0 is the permittivity of a vacuum.

Molarity (*c*) - A measure of concentration of a solution in which one states the amount of substance (i.e., number of moles) of solute per liter of solution. Thus a 0.1 molar solution (often referred to as 0.1 M) has a concentration c = 0.1 mol/L.

Mole (mol)* - The SI base unit of amount of substance. [1]

Mole fraction (x_B) - The ratio of the amount of substance (number of moles) of substance B to the total amount of substance in a mixture. [1]

Molecular orbital - See Orbital.

Molecular weight (M_r)* - The ratio of the average mass per molecule or specified entity of a substance to 1/12 of the mass of nuclide ^{12}C. Also called relative molar (or molecular) mass. [1]

Moment of inertia (*I*) - The moment of inertia of a body about an axis is the sum (or integral) of the products of its elements of mass and the squares of their distances from the axis. [1]

Momentum (*p*) - The product of mass and velocity. [1]

Monomer - A substance consisting of molecules which can undergo polymerization, thereby contributing constitutional units to the essential structure of a macromolecule. [8]

Monosaccharides - A term which includes aldoses, ketoses, and a wide variety of derivatives. [5]

Mössbauer effect - The recoilless emission of γ-rays from nuclei bound in a crystal under conditions where the recoil energy associated with the γ emission is taken up by the crystal as a whole. This results in a very narrow line width, which can be exploited in various types of precise measurements.

Muon* - An unstable elementary particle of spin 1/2 and mass about 200 times that of the electron.

Naphtha - The petroleum fraction consisting mostly of C_6 to C_8 hydrocarbons and boiling in the range 80-120°C. Solvents derived from this fraction include ligroin and petroleum ether.

Nautical mile - A non-SI unit of length, equal to exactly 1852 m.

Navier-Stokes equations - A set of complex equations for the motion of a viscous fluid subject to external forces.

Néel temperature (T_N)* - The critical temperature above which an antiferromagnetic substance becomes paramagnetic. [1]

Nernst effect - The production of an electric field in a conductor subject to an applied magnetic field and containing a transverse temperature gradient. The electric field is perpendicular to the magnetic field and the temperature gradient.

Network - In polymer science, a highly ramified macromolecule in which essentially each constitutional unit is connected to each other constitutional unit and to the macroscopic phase boundary by many permanent paths through the macromolecule, the number of such paths increasing with the number of intervening bonds. The paths must on the average be coextensive with the macromolecule. [8]

Neutrino - A stable elementary particle in the lepton family. Neutrinos have zero (or at least near-zero) rest mass and spin 1/2.

Neutron* - An elementary particle on spin 1/2 and zero charge. The free neutron has a mean lifetime of 887 seconds. Neutrons and protons, which are collectively called nucleons, are the constituents of the nucleus.

Neutron activation analysis (NAA) - See Techniques for Materials Characterization, page 12-1.

Neutron number (*N*) - A characteristic property of a specific isotope of an element, equal to the number of neutrons in the nucleus.

Newton (N)* - The SI unit of force, equal to m kg s^{-2}. [1]

Nitriles - Compounds having the structure RC≡N; thus C-substituted derivatives of hydrocyanic acid, HC≡N. [5]

Nitrosamines - N-Nitroso amines: compounds of the structure R_2NNO. Compounds RNHNO are not ordinarily isolatable, but they, too, are nitrosamines. The name is a contraction of N-nitrosoamine and, as such, does not require the N locant. [5]

Nuclear magnetic resonance (NMR)* - A widely used technique in which the resonant absorption of radiofrequency radiation by magnetic nuclei in a magnetic field is measured. The results give important information on the local environment of each nucleus.

Nuclear magneton (μ_N)* - The unit of nuclear magnetic moment, defined as $eh/4\pi m_p$, where h is Planck's constant, m_p the proton mass, and e the elementary charge.

Nuclear quadrupole resonance (NQR) - See Techniques for Materials Characterization, page 12-1.

Nuclear reaction analysis (NRA) - See Techniques for Materials Characterization, page 12-1.

Nuclear spin (*I*) - The quantum number that specifies the intrinsic angular momentum of a particular nucleus. The magnitude of the angular momentum is given by $[I(I+1)]^{1/2}\, h/2\pi$, where h is Planck's constant.

Nucleic acids* - Macromolecules, the major organic matter of the nuclei of biological cells, made up of nucleotide units, and hydrolyzable into certain pyrimidine or purine bases (usually adenine, cytosine, guanine, thymine, uracil), D-ribose or 2-deoxy-D-ribose. [5]

Nucleon - A collective term for the proton and neutron.

Nucleosides - Ribosyl or deoxyribosyl derivatives (rarely, other glycosyl derivatives) of certain pyrimidine or purine bases. They are thus glycosylamines or N-glycosides related to nucleotides by the lack of phosphorylation. [5]

Nucleotides - Compounds formally obtained by esterification of the 3′ or 5′ hydroxy group of nucleosides with phosphoric acid. They are the monomers of nucleic acids and are formed from them by hydrolytic cleavage. [5]

Nuclide - A species of atoms in which each atom has identical atomic number Z and identical mass number A. [3]

Nusselt number (*Nu*) - A dimensionless quantity used in fluid mechanics, defined by $Nu = hl/k$, where h is coefficient of heat transfer, l is length, and k is thermal conductivity. [2]

Nyquist theorem - An expression for the mean square thermal noise voltage across a resistor, given by $4RkT\Delta f$ where R is the resistance, k the Boltzmann constant, T the temperature, and Δf the frequency band within which the voltage is measured.

Octanol-water partition coefficient (*P*)* - A measure of the way in which a compound will partition itself between the octanol and water phases in the two-phase octanol-water system, and thus an indicator of certain types of biological activity. Specifically, P is the ratio of the concentration (in moles per liter) of the compound in the octanol phase to that in the water phase at infinite dilution. The quantity normally reported is log P.

Oersted (Oe) - A non-SI unit of magnetic field (H), equal to 79.57747 A/m.

Ohm (Ω)* - The SI unit of electric resistance, equal to V/A. [1]

Ohm's law - A relation among electric current I, potential difference V, and resistance R, viz., $I = V/R$. The resistance is constant at constant temperature to high precision for many materials.

Olefins - Acyclic and cyclic hydrocarbons having one or more carbon-carbon double bonds, apart from the formal ones in aromatic compounds. The class olefins subsumes alkenes and cycloalkenes and the corresponding polyenes. [5]

Oligomer - A substance consisting of molecules of intermediate relative molecular mass (molecular weight), the structure of which essentially comprises the multiple repetition of units derived, actually or conceptually, from molecules of low relative molecular mass. In contrast to a polymer, the properties of an oligomer can vary significantly with the removal of one or a few of its units. [8]

Oligopeptides - Peptides containing from three to nine amino groups. [5]

Onsager relations - An important set of equations in the thermodynamics of irreversible processes. They express the symmetry between the transport coefficients describing reciprocal processes in systems with a linear dependence of flux on driving forces.

Optical rotary power - Angle by which the plane of polarization of a light beam is rotated by an optically active medium, divided by path length and by concentration of the active constituent. Depending on whether mass or molar concentration is used, the modifier "specific" or "molar" is attached. [2]

Orbital - A one-electron wavefunction. Atomic orbitals are classified as s-, p-, d,- or f-orbitals according to whether the angular momentum quantum number $l = 0$, 1, 2, or 3. Molecular orbitals, which are usually constructed as linear combinations of atomic orbitals, describe the distribution of electrons over the entire molecule.

Oscillator strength (*f*) - A measure of the intensity of a spectroscopic transition, defined by

$$f = \frac{8\pi^2 Mev}{3he^2}\left|\mu_{ij}\right|^2$$

where ν is the frequency, μ_{ij} the transition dipole moment, m_e the mass of the electron, e the elementary charge, and h Planck's constant.

Osmosis - The flow of a solvent in a system in which two solutions of different concentration are separated by a semipermeable membrane which cannot pass solute molecules. The solvent will flow from the side of lower concentration to that of higher concentration, thus tending to equalize the concentrations. The pressure that must be applied to the more concentrated side to stop the flow is called the osmotic pressure.

Osmotic coefficient (ϕ) - Defined by $\phi = \ln a_A/(M_A \Sigma m_B)$, where M_A is the molar mass of substance A (normally the solvent), a_A is its activity, and the m_B are molalities of the solutes. [1]

Osmotic pressure (Π) - The excess pressure necessary to maintain osmotic equilibrium between a solution and the pure solvent separated by a membrane permeable only to the solvent. In an ideal dilute solution $\Pi = c_B RT$, where c_B is the amount-of-substance concentration of the solute, R is the molar gas constant, and T the temperature. [1,2]

Ostwald dilution law - A relation for the concentration dependence of the molar conductivity Λ of an electrolyte solution, viz.,

$$\frac{1}{\Lambda} = \frac{1}{\Lambda^\circ} + \frac{\Lambda c}{K(\Lambda^\circ)^2}$$

where c is the solute concentration, K is the equilibrium constant for dissociation of the solute, and Λ° is the conductivity at $c\Lambda = 0$.

Ounce (oz) - A non-SI unit of mass. The avoirdupois ounce equals 28.34952 g, while the troy ounce equals 31.10348 g.

Overpotential (η) - In an electrochemical cell, the difference between the potential of an electrode and its zero-current value.

Oximes - Compounds of structure $R_2C{=}NOH$ derived from condensation of aldehydes or ketones with hydroxylamine. Oximes from aldehydes may be called aldoximes; those from ketones may be called ketoximes. [5]

Oxo compounds - Compounds containing an oxygen atom, =O, doubly bonded to carbon or another element. The term thus embraces aldehydes, carboxylic acids, ketones, sulfonic acids, amides and esters. [5]

Ozonides - The 1,2,4-trioxolanes formed by the reaction of ozone at a carbon-carbon double bond, or the analogous compounds derived from acetylenic compounds. [5]

Pair production - A process in which a photon is converted into a particle and its antiparticle (e.g., an electron and positron) in the electromagnetic field of a nucleus.

Paraffins - Obsolescent term for saturated hydrocarbons, commonly but not necessarily acyclic. Still widely used in the petrochemical industry, where the term designates acyclic saturated hydrocarbons, and stands in contradistinction to naphthenes. [5]

Paramagnetism* - A type of magnetism characterized by a positive magnetic susceptibility, so that the material becomes weakly magnetized in the direction of an external field. The magnetization disappears when the field in removed. In the simplest approximation (Curie's law) the susceptibility is inversely proportional to temperature.

Parity - The property of a quantum-mechanical wave function that describes its behavior under the symmetry operation of coordinate inversion. A parity of +1 (or even) is assigned if the wave function does not change sign when the signs of all the coordinates are changed; the parity is -1 (or odd) if the wave function changes sign under this operation.

Parsec (pc) - A unit of distance defined as the distance at which 1 astronomical unit (AU) subtends an angle of 1 second of arc. It is equal to 206264.806 AU or 3.085678×10^{16} m.

Particle induced x-ray emission (PIXE) - See Techniques for Materials Characterization, page 12-1.

Partition function (*q*, *z*) - For a single molecule, $q = \Sigma_i g_i \exp(\varepsilon_i/kT)$, where ε_i is an energy level of degeneracy g_i, k the Boltzmann constant, and T the absolute temperature; the summation extends over all energy states. For a system of N non-interacting molecules which are indistinguishable, as in an ideal gas, the canonical partition function $Q = qN/N!$.

Pascal (Pa)* - The SI unit of pressure, equal to N/m^2. [1]

Paschen series - The series of lines in the spectrum of the hydrogen atom which corresponds to transitions between the state with principal quantum number $n = 3$ and successive higher states. The wavelengths are given by $1/\lambda = R_H(1/9\text{-}1/n^2)$, where $n = 4,5,6,\ldots$ and R_H is the Rydberg constant. The first member of the series ($n = 3 \leftrightarrow 4$), which is often called the P_α line, falls in the infrared at a wavelength of 1.875 μm.

Paschen-Back effect - In atomic spectroscopy, the decoupling of electron spin from orbital angular momentum as the strength of an external magnetic field is increased.

Pauli exclusion principle - The statement that two electrons in an atom cannot have identical quantum numbers; thus if there are two electrons in the same orbital, their spin quantum numbers must be of opposite sign.

Pearson symbol - A code for designating crystallographic information, including the crystal system, the lattice type, and the number of atoms per unit cell.

Péclet number (*Pe*) - A dimensionless quantity used in fluid mechanics, defined by $Pe = vl/a$, where v is velocity, l is length, and a is thermal diffussivity. [2]

Peltier effect - The absorption or generation of heat (depending on the current direction) which occurs when an electric current is passed through a junction between two materials.

Peptides - Amides derived from two or more amino carboxylic acid molecules (the same or different) by formation of a covalent bond from the carbonyl carbon of one to the nitrogen atom of another with formal loss of water. [5]

Permeability (μ) - Magnetic induction divided by magnetic field strength; i.e. $\mu = B/H$. The relative permeability $\mu_r = \mu/\mu_0$, where μ_0 is the permeability of a vacuum. [1]

Permittivity (ε) - Ratio of the electric displacement in a medium to the electric field strength. Also called dielectric constant. [1]

Peroxides - Compounds of structure ROOR in which R may be any organic group. In inorganic chemistry, salts of the anion O_2^{-2} [5]

Peroxy acids - Acids in which an acidic -OH group has been replaced by an -OOH group; e.g. $CH_3C(=O)OOH$ peroxyacetic acid, $PhS(=O)_2OOH$ benzeneperoxysulfonic acid. [5]

Petroleum ether - The petroleum fraction consisting of C_5 and C_6 hydrocarbons and boiling in the range 35-60°C; commonly used as a laboratory solvent.

pH* - A convenient measure of the acid-base character of a solution, usually defined by $pH = -\log [c(H^+)/\text{mol L}^{-1})]$, where $c(H^+)$ is the concentration of hydrogen ions.The more precise definition is in terms af activity rather than concentration. [2]

Phenols - Compounds having one or more hydroxy groups attached to a benzene or other arene ring. [5]

Phonon - A quantum of energy associated with a vibrational mode of a crystal lattice.

Phosphines - PH_3 and compounds derived from it by substituting one, two or three hydrogen atoms by hydrocarbyl groups.

RPH_2, R_2PH and R_3P (R not equal to H) are called primary, secondary and tertiary phosphines, respectively. [5]

Phosphonium compounds - Salts (and hydroxides) $[R_4P]^+X^-$ containing tetracoordinate phosphonium ion and the associated anion. [5]

Phosphonium ylides - Compounds having the structure R_3P^+-$C^-R_2 \rightleftharpoons R_3P{=}CR_2$. Also known as Wittig reagents. [5]

Phosphoresence - The process by which a molecule is excited by light to a higher electronic state and then undergoes a radiationless transition to a state of different multiplicity from which it decays, after some delay, to the ground state. The emitted light is normally of longer wavelength than the exciting light because vibrational energy has been dissipated.

Photoelectric effect - The complete absorption of a photon by a solid with the emission of an electron.

Photon - An elementary particle of zero mass and spin 1/2. The photon is involved in electromagnetic interactions and is the quantum of electromagnetic radiation.

Photon stimulated desorption (PSD) - See Techniques for Materials Characterization, page 12-1.

Pinacols - Tetra(hydrocarbyl)ethane-1,2-diols, $R_2C(OH)C(OH)R_2$, of which the tetramethyl example is the simplest one and is itself commonly known as pinacol. [5]

Pion - An elementary particle in the family of mesons. Pions have zero spin and may be neutral or charged. They participate in the strong interaction which holds the nucleus together.

p*K** - The negative logarithm (base 10) of an equilibrium constant *K*. For pK_a, see Acid dissociation constant.

Planck constant (*h*)* - The elementary quantum of action, which relates energy to frequency through the equation $E = h\nu$.

Planck distribution - See Black body radiation

Planck function - A thermodynamic function defined by $Y = -G/T$, where G is Gibbs energy and T thermodynamic temperature. [2]

Plasma - A highly ionized gas in which the charge of the electrons is balanced by the charge of the positive ions, so that the system as a whole is electrically neutral.

Plasmon - A quantum associated with a plasma oscillation in the electron gas of a solid.

Point group* - A group of symmetry operations (rotations, reflections, etc.) that leave a molecule invariant. Every molecular conformation can be assigned to a specific point group, which plays a major role in determining the spectrum of the molecule.

Poise (P) - A non-SI unit of viscosity, equal to 0.1 Pa s.

Poiseuille's equation - A formula for the rate of flow of a viscous fluid through a tube:

$$\frac{dV}{dt} = \frac{(p_1^2 - p_2^2)\pi r^4}{16 l \eta p_0}$$

where V is the volume as measured at pressure p_0; p_1 and p_2 are the pressures at each end of the tube; r is the radius and l the length of the tube; and η is the viscosity.

Poisson ratio (μ) - The absolute value of the ratio of the transverse strain to the corresponding axial strain resulting from uniformly distributed axial stress below the proportional limit (i.e., where Hooke's law is valid). [10]

Polariton - A quantum associated with the coupled modes of photons and optical phonons in an ionic crystal.

Polarizability (α)* - The change in dipole moment of a molecule produced by an external electric field; specifically, $\alpha_{ab} = \partial p_a / \partial E_b$, where p_a is the dipole moment component on the a axis and E_b is the component of the electric field strength along the b axis. [2]

Polymer - A substance composed of molecules of high relative molecular mass (molecular weight), the structure of which essentially comprises the multiple repetition of units derived, actually or conceptually, from molecules of low relative molecular mass. A single molecule of a polymer is called a macromolecule. [8]

Polypeptides - Peptides containing 10 or more amino acid residues. See also Peptides. [5]

Polysaccharides - Compounds consisting of a large number of monosaccharides linked glycosidically. This term is commonly used only for those containing more than ten monosaccharide residues. Also called glycans. [5]

Porphyrins - Natural pigments containing a fundamental skeleton of four pyrrole nuclei united through the α-positions by four methine groups to form a macrocyclic structure (porphyrin is designated porphine in Chemical Abstracts indexes). [5]

Positron - The antiparticle of the electron. It has the same mass and spin as an electron, and an equal but opposite charge.

Positronium - The hydrogen-like "atom" formed from a positron nucleus and an electron. Its lifetime is very short because of annihilation of the positron and electron.

Potential - See Electric potential

Potential energy (E_p, *V, U*) - The portion of the energy of a system that is associated with its position in a force field.

Pound (lb) - A non-SI unit of mass, equal to 0.4535924 kg.

Power (*P*) - Rate of energy transfer. For electrical circuits, this is equal to the product of current and potential difference, $P = IV$. [1]

Poynting vector (*S*) - For electromagnetic radiation, the vector product of the electric field strength and the magnetic field strength. [1]

Prandtl number (*Pr*) - A dimensionless quantity used in fluid mechanics, defined by $Pr = \eta/\rho a$, where η is viscosity, ρ is density, and a is thermal diffusivity. [2]

Pressure* - Force divided by area. [1]

Proteins - Naturally occurring and synthetic polypeptides having molecular weights greater than about 10,000 (the limit is not precise). See also Peptides. [5]

Proton* - A stable elementary particle of unit positive charge and spin 1/2. Protons and neutrons, which are collectively called nucleons, are the constituents of the nucleus.

Pulsar - A neutron star which rotates rapidly and emits electromagnetic radiation in regular pulses at a frequency related to the rotation period.

Purine bases* - Purine and its substitution derivatives, especially naturally occurring examples. [5]

Pyrimidine bases* - Pyrimidine and its substitution derivatives, especially naturally occurring examples. [5]

Q-switching - A technique for obtaining very high power from a laser by keeping the Q factor of the laser cavity low while the population inversion builds up, then suddenly increasing the Q to initiate the stimulated emission.

Quad - A unit of energy defined as 10^{15} Btu, equal to approximately 1.055056×10^{18} J.

Quadrupole moment - A coefficient of the third term (after monopole and dipole) in the power series expansion of the electric potential of an array of charges. A nucleus of spin greater than 1/2 has a non-vanishing nuclear quadrupole moment which can interact with the electric field gradient of the surrounding electrons. Molecular quadrupole moments have an influence on intermolecular forces.

Quality factor (*Q*) - The ratio of the absolute value of the reactance of an electrical system to the resistance; thus a measure of the energy stored per cycle relative to the energy dissipated.

Quantum yield - In photochemistry, the number of moles transformed in a specific process, either physically (e.g., by emission of photons) or chemically, per mole of photons absorbed by the system. [3]

Quark - An elementary entity which has not been directly observed but is considered a constituent of protons, neutrons, and other hadrons.

Quasar - An extragalactic object emitting electromagnetic radiation at a very high power level and showing a very large red shift, thus indicating that the object is receding at a speed approaching the speed of light.

Quasicrystal - A solid having conventional crystalline properties but whose lattice does not display translational periodicity.

Quaternary ammonium compounds - Derivatives of ammonium compounds, $NH_4^+ Y^-$, in which all four of the hydrogens bonded to nitrogen have been replaced with hydrocarbyl groups. Compounds having a carbon-nitrogen double bond (i.e. $R_2C{=}N^+R_2Y^-$) are more accurately called iminium compounds. [5]

Quinones - Compounds having a fully conjugated cyclic dione structure, such as that of benzoquinones, derived from aromatic compounds by conversion of an even number of -CH= groups into -C(=O)- groups with any necessary rearrangement of double bonds. [5]

Racemic mixture - A mixture of equal amounts of a pair of enantiomers (optical isomers); such a mixture is not optically active.

Rad - A non-SI unit of absorbed dose of radiation, equal to 0.01 Gy.

Radiance (*L*) - The radiant intensity in a given direction from an element of a surface, divided by the area of the orthogonal projection of this element on a plane perpendicular to the given direction. [1]

Radiant intensity (*I*) - The radiant energy flux leaving an element of a source within an element of solid angle, divided by that element of solid angle. [1]

Radicals - Molecular entities possessing an unpaired electron, such as $\cdot CH_3$, $\cdot SnH_3$, $\cdot Cl$. (In these formulas the dot, symbolizing the unpaired electron, should be placed so as to indicate the atom of highest spin density, if this is possible). [5]

Raman effect - The inelastic scattering of light by a molecule, in which the incident photon either gives up to, or receives energy from, one of the internal vibrational modes of the molecule. The scattered light thus has either a lower frequency (Stokes radiation) or higher frequency (anti-Stokes radiation) than the incident light. These shifts provide a measure of the normal vibrational frequencies of the molecule.

Rankine cycle - A thermodynamic cycle which can be used to calculate the ideal performance of a heat engine that uses a condensable vapor as the working fluid (e.g., a steam engine or a heat pump).

Rankine temperature - A thermodynamic temperature scale based on a temperature interval °R = (5/9) K ; i.e., $T/°R = (9/5)T/K = t/°F + 459.67$.

Raoult's law - The expression for the vapor pressure p_i of component i in an ideal solution, viz., $p_i = x_i p_{i0}$, where x_i is the mole fraction of component i and p_{i0} the vapor pressure of the pure substance i.

Rare earth elements - The elements Sc, Y, and the lanthanides (La, Ce, Pr, Nd, Pm, Sm, Eu, Gd, Tb, Dy, Ho, Er, Tm, Yb, Lu). [7]

Rayleigh number (*Ra*) - A dimensionless quantity used in fluid mechanics, defined by $Ra = l^3 g\alpha\Delta T\rho/\eta a$, where l is length, g is acceleration of gravity, α is cubic expansion coefficient, T is temperature, ρ is density, η is viscosity, and a is thermal diffusivity. [2]

Rayleigh scattering - The scattering of light by particles which are much smaller than the wavelength of the light. It is characterized by a scattered intensity which varies as the inverse fourth power of the wavelength.

Rayleigh wave - A guided elastic wave along the surface of a solid; also called surface acoustic wave.

Reactance (*X*) - The imaginary part of impedance. For an inductive reactance L and a capacitive reactance C in series, the reactance is $X = L\omega - 1/(C\omega)$, where ω is 2π times the frequency of the current. [1]

Red shift - A displacement of a spectral line toward longer wavelengths. This can occur through the Doppler effect (e.g., in the light from receding galaxies) or, in the general theory of relativity, from the effects of a star's gravitational field.

Reflectance (ρ) - Ratio of the radiant or luminous flux at a given wavelength that is reflected to that of the incident radiation. Also called reflection factor. [1]

Reflection high energy electron diffraction (RHEED) - See Techniques for Materials Characterization, page 12-1.

Relative humidity* - The ratio of the partial pressure of water vapor in air to the saturation vapor pressure of water at the same temperature, expressed as a percentage. [10]

Relative molar mass - See Molecular weight.

Rem - A non-SI unit of dose equivalent, equal to 0.01 Sv.

Resistance (*R*) - Electric potential difference divided by current when there is no electromotive force in the conductor. This definition applies to direct current. More generally, resistance is defined as the real part of impedance. [1]

Resistivity (ρ) - Electric field strength divided by current density when there is no electromotive force in the conductor. Resistivity is an intrinsic property of a material. For a conductor of uniform cross section with area A and length L, and whose resistance is R, the resistivity is given by $\rho = RA/L$. [1]

Reynolds number (*Re*) - A dimensionless quantity used in fluid mechanics, defined by $Re = \rho v l/\eta$, where ρ is density, v is velocity, l is length, and η is viscosity. [2]

Rheology - The study of the flow of liquids and deformation of solids. Rheology addresses such phenomena as creep, stress relaxation, anelasticity, nonlinear stress deformation, and viscosity.

Ribonucleic acids (RNA) - Naturally occurring polyribonucleotides. See also nucleic acids, nucleosides, nucleotides, ribonucleotides. [5]

Ribonucleotides - Nucleotides in which the glycosyl group is a ribosyl group. See also nucleotides. [5]

Roentgen (R) - A unit used for expressing the charge (positive or negative) liberated by x-ray or γ radiation in air, divided by the mass of air. A roentgen is defined as 2.58×10^{-4} C/kg.

Rotational constants - In molecular spectroscopy, the constants appearing in the expression for the rotational energy levels as a function of the angular momentum quantum numbers. These constants are proportional to the reciprocals of the principal moments of inertia, averaged over the vibrational motion.

Rutherford back scattering (RBS) - See Techniques for Materials Characterization, page 12-1.

Rydberg constant (R_∞)* - The fundamental constant which appears in the equation for the energy levels of hydrogen-like atoms; i.e., $E_n = hcR_\infty Z^2\mu/n^2$, where h is Planck's constant, c the speed of light, Z the atomic number, μ the reduced mass of nucleus and electron, and n the principal quantum number (n = 1, 2, ...).

Rydberg series - A regular series of lines in the spectrum of an atom or molecule, with the spacing between successive lines becoming smaller as the frequency increases (wavelength decreases). The series eventually converges to a limit which usually corresponds to the complete removal of an electron from the atom or molecule.

Sackur-Tetrode equation* - An equation for the molar entropy S_m of an ideal monatomic gas: $S_m = R\ln(e^{5/2}\, V/N_A\Lambda^3)$, where R is the molar gas constant, V is the volume, and N_A is Avogadro's number. The constant Λ is given by $\Lambda = h/(2\pi mkT)^{1/2}$, where h is Planck's constant, m the atomic mass, k the Boltzmann constant, and T the temperature.

Salinity (S)* - A parameter used in oceanography to describe the concentration of dissolved salts in seawater. It is defined in terms of electrical conductivity relative to a standard solution of KCl. When expressed in units of parts per thousand, S may be roughly equated to the concentration of dissolved material in grams per kilogram of seawater.

Salt - An ionic compound formed by the reaction of an acid and a base.

Scanned probe microscopy (SPM) - See Techniques for Materials Characterization, page 12-1.

Scanning electron microscopy (SEM) - See Techniques for Materials Characterization, page 12-1.

Scanning laser acoustic microscopy (SLAM) - See Techniques for Materials Characterization, page 12-1.

Scanning transmission electron microscopy (STEM) - See Techniques for Materials Characterization, page 12-1.

Scanning tunneling microscopy (STM) - See Techniques for Materials Characterization, page 12-1.

Schiff bases - Imines bearing a hydrocarbyl group on the nitrogen atom: $R_2C{=}NR'$ (R′ not equal to H). Considered by many to be synonymous with azomethines. [5]

Schmidt number (Sc) - A dimensionless quantity used in fluid mechanics, defined by $Sc = \eta/\rho D$, where η is viscosity, ρ is density, and D is diffusion coefficient. [2]

Schottky barrier - A potential barrier associated with a metal-semiconductor contact. It forms the basis for the rectifying device known as the Schottly diode.

Schrödinger equation - The basic equation of wave mechanics which, for systems not dependent on time, takes the form:

$$-(\hbar/2m)\nabla^2\psi + V\psi = E\psi$$

where ψ is the wavefunction, V is the potential energy expressed as a function of the spatial coordinates, E is an energy eigenvalue, ∇^2 is the Laplacian operator, $\hbar$ is Planck's constant divided by 2π, and m is the mass.

Second (s)* - The SI base unit of time. [1]

Second radiation constant (c_2)* - See First radiation constant.

Secondary ion mass spectroscopy (SIMS) - See Techniques for Materials Characterization, page 12-1.

Seebeck effect - The development of a potential difference in a circuit where two different metals or semiconductors are joined and their junctions maintained at different temperatures. It is the basis of the thermocouple.

Selenides - Compounds having the structure RSeR (R not equal to H). They are thus selenium analogues of ethers. Also used for metal salts of H_2Se. [5]

Semicarbazones - Compounds having the structure $R_2C{=}NNHC(=O)NH_2$, formally derived by condensation of aldehydes or ketones with semicarbazide [$NH_2NHC(=O)NH_2$]. [5]

Semiconductor - A material in which the highest occupied energy band (valence band) is completely filled with electrons at T = 0 K, and the energy gap to the next highest band (conduction band) ranges from 0 to 4 or 5 eV. With increasing temperature electrons are excited into the conduction band, leading to an increase in the electrical conductivity.

Semiquinones - Radical anions having the structure -O-Z-O· where Z is an ortho- or para-arylene group or analogous heteroarylene group; they are formally generated by the addition of an electron to a quinone. [5]

SI units* - The International System of Units adopted in 1960 and recommended for use in all scientific and technical fields. [1]

Siemens (S)* - The SI unit of electric conductance, equal to Ω^{-1}. [1]

Sievert (Sv)* - The SI unit of dose equivalent (of radiation), equal to J/kg. [1]

Silanes - Saturated silicon hydrides, analogues of the alkanes; i.e. compounds of the general formula Si_nH_{2n+2}. Silanes may be subdivided into silane, oligosilanes, and polysilanes. Hydrocarbyl derivatives are often referred to loosely as silanes. [5]

Silicones - Polymeric or oligomeric siloxanes, usually considered unbranched, of general formula $[\text{-}OSiR_2\text{-}]_n$ (R not equal to H). [5]

Siloxanes - Saturated silicon-oxygen hydrides with unbranched or branched chains of alternating silicon and oxygen atoms (each silicon atom is separated from its nearest silicon neighbors by single oxygen atoms). [5]

Skin effect - The concentration of high frequency alternating currents near the surface of a conductor.

Slater orbital - A particular mathematical expression for the radial part of the wave function of a single electron, which is used in quantum-mechanical calculations of the energy and other properties of atoms and molecules.

Small angle neutron scattering (SANS) - See Techniques for Materials Characterization, page 12-1.

Snell's law - The relation between the angle of incidence i and the angle of refraction r of a light beam which passes from a medium of refractive index n_0 to a medium of index n_1, viz., $\sin i/\sin r = n_1/n_0$.

Solar constant* - The mean radiant energy flux from the sun on a unit surface normal to the direction of the rays at the mean

distance of the earth from the sun. The value is approximately 1373 W/m^2.

Solar wind - The stream of high velocity hydrogen and helium ions emitted by the sun which flows through the solar system and beyond.

Soliton - A spatially localized wave in a solid or liquid that can interact strongly with other solitons but will afterwards regain its original form.

Solubility* - A quantity expressing the maximum concentration of some material (the solute) that can exist in another liquid or solid material (the solvent) at thermodynamic equilibrium at specified temperature and pressure. Common measures of solubility include the mass of solute per unit mass of solution (mass fraction), mole fraction of solute, molality, molarity, and others.

Solubility product constant (K_{sp})* - The equilibrium constant for the dissolution of a sparsely soluble salt into its constituent ions.

Space group* - A group of symmetry operations (reflections, rotations, etc.) that leave a crystal invariant. A total of 230 space groups have been identified.

Spark source mass spectroscopy (SSMS) - See Techniques for Materials Characterization, page 12-1.

Specific gravity - Ratio of the mass density of a material to that of water. Since one must specify the temperature of both the sample and the water to have a precisely defined quantity, the use of this term is now discouraged.

Specific heat - Heat capacity divided by mass. See Heat capacity.

Specific quantity - It is often convenient to express an extensive quantity (e.g., volume, enthalpy, heat capacity, etc.) as the actual value divided by mass. The resulting quantity is called specific volume, specific enthalpy, etc.

Specific rotation $[\alpha]^{\theta}_{\lambda}$ - For an optically active substance, defined by $[\alpha]^{\theta}_{\lambda} = \alpha/\gamma l$, where α is the angle through which plane polarized light is rotated by a solution of mass concentration γ and path length l. Here θ is the Celsius temperature and λ the wavelength of the light at which the measurement is carried out. Also called specific optical rotatory power. [2]

Spin (s, I)* - A measure of the intrinsic angular momentum of a particle, which it possesses independent of its orbital motion. The symbol s is used for the spin quantum number of an electron, while I is generally used for nuclear spin.

Spiro compounds - Compounds having one atom (usually a quaternary carbon) as the only common member of two rings. [5]

Stacking fault - An error in the normal sequence of layer growth in a crystal.

Standard mean ocean water (SMOW) - A standard sample of pure water of accurately known isotopic composition which is maintained by the International Atomic Energy Agency. It is used for precise calibration of density and isotopic composition measurements.

Standard reduction potential ($E°$) - The zero-current potential of a cell in which the specified reduction reaction occurs at the right-hand electrode and the left-hand electrode is the standard hydrogen electrode. Also called Standard electrode potential.

Standard state - A defined state (specified temperature, pressure, concentration, etc.) for tabulating thermodynamic functions and carrying out thermodynamic calculations. The standard state pressure is usually taken as 100,000 Pa (1 bar), but various standard state temperatures are used. [2]

Stanton number (St) - A dimensionless quantity used in fluid mechanics, defined by $St = h/\rho v c_p$, where h is coefficient of heat transfer, ρ is density, v is velocity, and c_p is specific heat capacity at constant pressure. [2]

Stark effect - The splitting of an energy level of an atom or molecule, and hence a splitting of spectral lines arising from that level, as a result of the application of an external electric field.

Statistical weight (g) - The number of distinct states corresponding to the same energy level. Also called degeneracy.

Stefan-Boltzmann constant (σ)* - Constant in the equation for the radiant exitance M (radiant energy flux per unit area) from a black body at thermodynamic temperature T, viz. $M = \sigma T^4$. [1]

Stibines - SbH_3 and compounds derived from it by substituting one, two or three hydrogen atoms by hydrocarbyl groups: R_3Sb. $RSbH_2$, R_2SbH, and R_3Sb (R not equal to H) are called primary, secondary and tertiary stibines, respectively. [5]

Stochastic process - A process which involves random variables and whose outcome can thus be described only in terms of probabilities.

Stoichiometric number (ν) - The number appearing before the symbol for each compound in the equation for a chemical reaction. By convention, it is negative for reactants and positive for products. [2]

Stokes (St) - A non-SI unit of kinematic viscosity, equal to 10^{-4} m^2/s.

Stokes' law - The statement, valid under certain conditions, that the viscous force F experienced by a sphere of radius a moving at velocity v in a medium of viscosity η is given by $F = -6\pi\eta a v$.

Strain - The deformation of a body that results from an applied stress.

Stratosphere - The part of the earth's atmosphere extending from the top of the troposphere (typically 10 to 15 km above the surface) to about 50 km. It is characterized by an increase in temperature with increasing altitude.

Stress - Force per unit area (pressure) applied to a body. Tensile stress tends to stretch or compress the body in the direction of the applied force. Sheer stress results from a tangential force which tends to twist the body.

Strong interaction - The short range (order of 1 fm) attractive forces between protons, neutrons, and other hadrons which are responsible for the stability of the nucleus.

Strouhal number (Sr) - A dimensionless quantity used in fluid mechanics, defined by $Sr = lf/v$, where l is length, f is frequency, and v is velocity. [2]

Structure factor - In x-ray crystallography, the sum of the scattering factors of all the atoms in a unit cell, weighted by an appropriate phase factor. The intensity of a given reflection is proportional to the square of the structure factor.

Sublimation pressure - The pressure of a gas in equilibrium with a solid at a specified temperature.

Sulfides - Compounds having the structure RSR (R not equal to H). Such compounds were once called thioethers. In an inorganic sense, salts or other derivatives of hydrogen sulfide. [5]

Sulfones - Compounds having the structure, $RS(=O)_2R$ (R not equal to H), e.g. $C_2H_5S(=O)_2CH_3$, ethyl methyl sulfone. [5]

Sulfonic acids - $HS(=O)_2OH$, sulfonic acid, and its S-hydrocarbyl derivatives. [5]

Sulfoxides - Compounds having the structure $R_2S=O$ (R not equal to H), e.g. $Ph_2S=O$, diphenyl sulfoxide. [5]

Superconductor - A material that experiences a nearly total loss of electrical resistivity below a critical temperature T_c. The effect can occur in pure metals, alloys, semiconductors, organic compounds, and certain inorganic solids.

Superfluid - A fluid with near-zero viscosity and extremely high thermal conductivity. Liquid helium exhibits these properties below 2.186 K (the λ point).

Supernova - A star in the process of exploding because of instabilities which follow the exhaustion of its nuclear fuel.

Surface analysis by laser ionization (SALI) - See Techniques for Materials Characterization, page 12-1.

Surface tension (γ,σ)* - The force per unit length in the plane of the interface between a liquid and a gas, which resists an increase in the area of that surface. It can also be equated to the surface Gibbs energy per unit area.

Surfactant - A substance which lowers the surface tension of the medium in which it is dissolved, and/or the interfacial tension with other phases, and accordingly is positively adsorbed at the liquid-vapor or other interfaces. [3]

Susceptance (*B*) - Imaginary part of admittance. [1]

Svedberg - A non-SI unit of time, used to express sedimentation coefficients, equal to 10^{-13} s.

Syndiotactic macromolecule - A tactic macromolecule, essentially comprising alternating enantiomeric configurational base units which have chiral or prochiral atoms in the main chain in a unique arrangement with respect to their adjacent constitutional units. In this case the repeating unit consists of two configurational base units that are enantiomeric. [8]

Tacticity - The orderliness of the succession of configurational repeating units of a macromolecule or oligomer molecule. In a tactic macromolecule essentially all the configurational repeating units are identical with respect to directional sense. See Configurational repeating unit, Isotactic, Syndiotactic. [8]

Tautomerism - Isomerism of the general form G-X-Y=Z ⇌ X=Y-Z-G, where the isomers (called tautomers) are readily interconvertible; the atoms connecting the groups X, Y, Z are typically any of C, H, O, or S, and G is a group which becomes an electrofuge (i.e., a group that does not carry away the bonding electron pair when it leaves its position in the molecule) or nucleofuge (a group that does carry away the bonding electrons when leaving) during isomerization. The commonest case, when the electrofuge is H^+, is also known as prototropy. A common example, written so as to illustrate the general pattern given above, is keto-enol tautomerism, such as

$$H\text{-}O\text{-}C(CH_3)=CH\text{-}CO_2Et \text{ (enol)} \rightleftharpoons (CH_3)C(=O)\text{-}CH_2\text{-}CO_2Et \text{ (keto)}$$

In some cases the interconversion rate between tautomers is slow enough to permit isolation of the separate keto and enol forms. [5]

Tensile strength* - In tensile testing, the ratio of maximum load a body can bear before breaking to original cross-sectional area. Also called ultimate strength. [11]

Terpenes - Hydrocarbons of biological origin having carbon skeletons formally derived from isoprene [$CH_2=C(CH_3)CH=CH_2$]. [5]

Terpenoids - Natural products and related compounds formally derived from isoprene units. They contain oxygen in various functional groups. The skeleton of terpenoids may differ from strict additivity of isoprene units by the loss or shift of a methyl (or other) group. [5]

Tesla (T)* - The SI unit of magnetic flux density (B), equal to V s/m^2. [1]

Thermal conductivity* - Rate of heat flow divided by area and by temperature gradient. [1]

Thermal diffusivity - Thermal conductivity divided by density and by specific heat capacity at constant pressure. [1]

Thermal expansion coefficient (α)* - The linear expansion coefficient is defined by $\alpha_l = (1/l)(dl/dT)$; the volume expansion coefficient by $\alpha_V = (1/V)(dV/dT)$. [1]

Thermionic emission - The emission of electrons from a solid as a result of heat. The effect requires a high enough temperature to impart sufficient kinetic energy to the electrons to exceed the work function of the solid.

Thermodynamic laws - The foundation of the science of thermodynamics:

First law: The internal energy of an isolated system is constant; if energy is supplied to the system in the form of heat dq and work dw, then the change in energy $dU = dq + dw$.

Second law: No process is possible in which the only result is the transfer of heat from a reservoir and its complete conversion to work.

Third law: The entropy of a perfect crystal approaches zero as the thermodynamic temperature approaches zero.

Thermoelectric power - For a bar of a pure material whose ends are at different temperatures, the potential difference divided by the difference in temperature of the ends. See also Seeback effect.

Thermogravimetric analysis (TGA) - See Techniques for Materials Characterization, page 12-1.

Thermosphere - The layer of the earth's atmosphere extending from the top of the mesosphere (typically 80–90 km above the surface) to about 500 km. It is characterized by a rapid increase in temperature with increasing altitude up to about 200 km, followed by a leveling off in the 300–500 km region.

Thiols - Compounds having the structure RSH (R not equal to H). Also known by the term mercaptans (abandoned by IUPAC); e.g. CH_3CH_2SH, ethanethiol. [5]

Thomson coefficient (μ, τ) - The heat power developed in the Thomson effect (whereby heat is evolved in a conductor when a current is flowing in the presence of a temperature gradient), divided by the current and the temperature difference. [1]

Tonne (t) - An alternative name for megagram (1000 kg). [1]

Torque (*T*) - For a force $\boldsymbol{F}$ that produces a torsional motion, $\boldsymbol{T} = \boldsymbol{r} \times \boldsymbol{F}$, where $\boldsymbol{r}$ is a vector from some reference point to the point of application of the force.

Torr - A non-SI unit of pressure, equal to 133.322 Pa. The name is generally considered interchangeable with millimeter of mercury.

Townsend coefficient - In a radiation counter, the number of ionizing collisions by an electron per unit path length in the direction of an applied electric field.

Transducer - Any device that converts a signal from acoustical, optical, or some other form of energy into an electrical signal (or vice versa) while preserving the information content of the original signal.

Transistor - A voltage amplifier using controlled electron currents inside a semiconductor.

Transition metals - Elements characterized by a partially filled *d* subshell. The First Transition Series comprises Sc, Ti, V, Cr, Mn, Fe, Co, Ni, Cu. The Second and Third Transition Series include the lanthanides and actinides, respectively. [7]

Transition probability* - See Einstein transition probability.

Transmittance (τ) - Ratio of the radiant or luminous flux at a given wavelength that is transmitted to that of the incident radiation. Also called transmission factor. [1]

Tribology - The study of frictional forces between solid surfaces.

Triple point* - The point in p,T space where the solid, liquid, and gas phases of a substance are in thermodynamic equilibrium. The corresponding temperature and pressure are called the triple point temperature and triple point pressure.

Troposphere - The lowest part of the earth's atmosphere, extending to 10-15 km above the surface. It is characterized by a decrease in temperature with increasing altitude. The exact height varies with latitude and season.

Tunnel diode - A device involving a p-n junction in which both sides are so heavily doped that the Fermi level on the p-side lies in the valence band and on the n-side in the conduction band. This leads to a current-voltage curve with a maximum, so that the device exhibits a negative resistance in some regions.

Ultraviolet photoelectron spectroscopy (UPS) - See Techniques for Materials Characterization, page 12-1.

Umklapp process - A process involving the interaction of three or more waves (lattice or electron) in a solid in which the sum of the wave vectors does not equal zero.

Unified atomic mass unit (u)* - A unit of mass used in atomic, molecular, and nuclear science, defined as the mass of one atom of ^{12}C divided by 12. Its approximate value is 1.66054×10^{-27} kg. [1]

Universal time (t_U, UT) - Mean solar time counted from midnight at the Greenwich meridian. Also called Greenwich mean time (GMT). The interval of mean solar time is based on the average, over one year, of the time between successive transits of the sun across the observer's meridian.

Vacancy - A missing atom or ion in a crystal lattice.

Van Allen belts - Two toroidal regions above the earth's atmosphere containing protons and electrons. The outer belt at about 25,000 km above the surface is probably of solar origin. The inner belt at about 3000 km contains more energetic particles from outside the solar system.

Van der Waals' equation* - An equation of state for fluids which takes the form:

$$pV_m = RT\left(\frac{1}{V_m - b} - \frac{a}{V_m^2}\right)$$

where p is pressure, V_m is molar volume, T is temperature, R is the molar gas constant, and a and b are characteristic parameters of the substance which describe the effect of attractive and repulsive intermolecular forces, respectively.

Van der Waals' force - The weak attractive force between two molecules which arises from electric dipole interactions. It can lead to the formation of stable but weakly bound dimer molecules or clusters.

Van't Hoff equation - The equation expressing the temperature dependence of the equilibrium constant K of a chemical reaction:

$$\frac{d\ln K}{dT} = \frac{\Delta_r H^\circ}{RT^2}$$

where $\Delta_r H^\circ$ is the standard enthalpy of reaction, R the molar gas constant, and T the temperature. Also called van't Hoff isochore.

Vapor pressure* - The pressure of a gas in equilibrium with a liquid (or, in some usage, a solid) at a specified temperature.

Varistor - A device that utilizes the properties of certain metal oxides with small amounts of impurities, which show abrupt nonlinearities at specific voltages where the material changes from a semiconductor to an insulator.

Velocity (v) - Rate of change of distance with time.

Verdet constants (V)* - Angle of rotation of a plane polarized light beam passing through a medium in a magnetic field, divided by the field strength and by the path length.

Virial equation of state* - An equation relating the pressure p, molar volume V_m, and temperature T of a real gas in the form of an expansion in powers of the molar volume, viz., $pV_m = RT(1+BV_m^{-1}+CV_m^{-2}+ \ldots)$, where R is the molar gas constant. B is called the second virial coefficient, C the third virial coefficient, etc. The virial coefficients are functions of temperature.

Viscosity (η)* - The proportionality factor between sheer rate and sheer stress, defined through the equation $F = \eta A(dv/dx)$, where F is the tangential force required to move a planar surface of area A at velocity v relative to a parallel surface separated from the first by a distance x. Sometimes called dynamic or absolute viscosity. The term kinematic viscosity (symbol ν) is defined as η divided by the mass density.

Volt (V)* - The SI unit of electric potential, equal to W/A. [1]

Volume fraction (ϕ_j) - Defined as $V_j/\Sigma_i V_i$, where V_j is the volume of the specified component and the V_i are the volumes of all the components of a mixture prior to mixing. [2]

Watt (W)* - The SI unit of power, equal to J/s. [1]

Wave function - A function of the coordinates of all the particles in a quantum mechanical system (and, in general, of time) which fully describes the state of the system. The product of the wave function and its complex conjugate is proportional to the probability of finding a particle at a particular point in space.

Weak interaction - The weak forces (order of 10^{-12} of the strong interaction) between elementary particles which are responsible for beta decay and other nuclear effects.

Weber (Wb)* - The SI unit of magnetic flux, equal to V s. [1]

Weber number (We) - A dimensionless quantity used in fluid mechanics, defined by $We = \rho v^2 l/\gamma$, where ρ is density, v is velocity, l is length, and γ is surface tension. [2]

Weight - That force which, when applied to a body, would give it an acceleration equal to the local acceleration of gravity. [1]

Wiedeman-Franz law - The law stating that the thermal conductivity k and electrical conductivity σ of a pure metal are related by $k = L\sigma T$, where T is the temperature and L (called the Lorenz ratio) has the approximate value 2.45×10^{-8} V^2/K^2.

Wien displacement law - The relation, which can be derived from the Planck formula for black body radiation, that

$\lambda_{max} T = 0.0028978$ m K, where λ_{max} is the wavelength of maximum radiance at temperature T.

Wigner-Seitz method - A method of calculating electron energy levels in a solid using a model in which each electron is subject to a spherically symmetric potential.

Wittig reagents - See phosphonium ylides.

Work (*W*) - Force multiplied by the displacement in the direction of the force. [1]

Work function (Φ)* - The energy difference between an electron at rest at infinity and an electron at the Fermi level in the interior of a substance. It is thus the minimum energy required to remove an electron from the interior of a solid to a point just outside the surface. [1]

X unit (X) - A unit of length used in x-ray crystallography, equal to approximately 1.002×10^{-13} m.

X-ray photoelectron spectroscopy (XPS) - See Techniques for Materials Characterization, page 12-1.

Yield strength - The stress at which a material exhibits a specified deviation (often chosen as 0.2% for metals) from proportionality of stress and strain. [11]

Young's modulus (*E*) - In tension or compression of a body below its elastic limit, the ratio of stress to corresponding strain. Since strain is normally expressed on a fractional basis, Young's modulus has dimensions of pressure. Also called elastic modulus. [11]

Zeeman effect - The splitting of an energy level of an atom or molecule, and hence a splitting of spectral lines arising from that level, as a result of the application of an external magnetic field.

Zener diode - A control device utilizing a p-n junction with a well defined reverse-bias avalanche breakdown voltage.

Zeotrope - A liquid mixture that shows no maximum or minimum when vapor pressure is plotted against composition at constant temperature. See Azeotrope.

Zero-point energy - The energy possessed by a quantum mechanical system as a result of the uncertainty principle even when it is in its lowest energy state; e.g., the difference between the lowest energy level of a harmonic oscillator and the minimum in the potential well.

Zeta potential (ζ) - The electric potential at the surface of a colloidal particle relative to the potential in the bulk medium at a long distance. Also called electrokinetic potential.

Zwitterions - Neutral compounds having formal unit electrical charges of opposite sign. Some chemists restrict the term to compounds with the charges on non-adjacent atoms. Sometimes referred to as inner salts, dipolar ions (a misnomer). [5]

THERMODYNAMIC FUNCTIONS AND RELATIONS

p = pressure V = volume T = temperature
n_i = amount of substance i
$x_i = n_i/\Sigma_j n_j$ = mole fraction of substance i

Energy	U
Entropy	S
Enthalpy	$H = U + pV$
Helmholtz energy	$A = U - TS$
Gibbs energy	$G = U + pV - TS$
Isobaric heat capacity	$C_p = (\partial H/\partial T)_p$
Isochoric heat capacity	$C_V = (\partial U/\partial T)_V$
Isobaric expansivity	$\alpha = V^{-1}(\partial V/\partial T)_p$
Isothermal compressibility	$\kappa_T = -V^{-1}(\partial V/\partial p)_T$
Isentropic compressibility	$\kappa_S = -V^{-1}(\partial V/\partial p)_S$
	$\kappa_T - \kappa_S = T\alpha^2 V/C_p$
	$C_p - C_V = T\alpha^2 V/\kappa_T$
Gibbs-Helmholtz equation	$H = G - T(\partial G/\partial T)_p$
Maxwell relations	$(\partial S/\partial p)_T = -(\partial V/\partial T)_p$
	$(\partial S/\partial V)_T = -(\partial p/\partial T)_V$
Joule-Thomson expansion	$\mu_{JT} = (\partial T/\partial p)_H = -\{V - T(\partial V/\partial T)_p\}/C_p$
	$\phi_{JT} = (\partial H/\partial p)_T = V - T(\partial V/\partial T)_p$
Partial molar quantity	$X_i = (\partial X/\partial n_i)_{T,p,nj\neq i}$
Chemical potential	$\mu_i = (\partial G/\partial n_i)_{T,p,nj\neq i}$
Perfect gas [symbol pg]	$pV = (\Sigma_i n_i)RT$
	$\mu_i^{pg} = \mu_i^{\theta} + RT \ln(x_i p/p^{\theta})$
Fugacity	$f_i = (x_i p)\exp\{(\mu_i - \mu_i^{pg})/RT\}$
Activity coefficient	$\gamma_i = f_i/(x_i f_i^{\theta})$
Gibbs-Duhem relation	$0 = S\mathrm{d}T - V\mathrm{d}p + \Sigma_i n_i \mathrm{d}\mu_i$

[Superscript θ in above equations indicates standard state]

Notation for chemical and physical changes (X = H, S, G, etc.):

Chemical reaction	$\Delta_r X$
Formation from elements	$\Delta_f X$
Combustion	$\Delta_c X$
Fusion (cry→liq)	$\Delta_{fus} X$
Vaporization (liq→gas)	$\Delta_{vap} X$
Sublimation (cry→gas)	$\Delta_{sub} X$
Phase transition	$\Delta_{trs} X$
Solution	$\Delta_{sol} X$
Mixing	$\Delta_{mix} X$
Dilution	$\Delta_{dil} X$

PHYSICAL CONSTANTS OF ORGANIC COMPOUNDS

The basic physical constants and structure diagrams for about 10,900 organic compounds are presented in this table. An effort has been made to include the compounds most frequently encountered in the laboratory, the workplace, and the environment. Particular emphasis has been given to substances that are considered environmental or human health hazards. In making the selection of compounds for the table, added weight was assigned to the appearance of a compound in various lists or reference sources such as:

- Laboratory reagent lists, e.g., the ACS *Reagent Chemicals* volume (Ref. 1)
- The DIPPR list of industrially important compounds (Ref. 2) and the (much larger) TSCA Inventory of chemicals used in commerce
- The Hazardous Substance Data Bank (Ref. 3)
- The UNEP list of Persistent Organic Pollutants (Ref. 4)
- Chemicals on Reporting Rules (CORR), a database of about 7500 regulated compounds prepared by the Environmental Protection Agency (Ref. 5)
- The EPA Integrated Risk Information System (IRIS), a database of human health effects of exposure to chemicals in the environment (Ref. 6)
- Compendia of chemicals of biochemical or medical importance, such as *The Merck Index* (Ref. 10)
- Specialized tables in this *Handbook*

It should be noted that the above lists vary widely in their choice of chemical names, and even in the use of Chemical Abstracts Registry Numbers. To the extent possible, we have attempted to systematize the names and registry numbers for this table.

Clearly, criteria of this type are somewhat subjective, and compounds considered important by some users have undoubtedly been omitted. Suggestions for additional compounds or other improvements are welcomed.

The data in the table have been derived from many sources, including both the primary literature and evaluated compilations. The *Handbook of Data on Organic Compounds, Third Edition* (Reference 7) and the *Chapman & Hall/CRC Combined Chemical Dictionary* (Reference 8) were important sources. Other useful compilations of physical property data for organic compounds are listed in References 9-19. Many boiling point values (and some melting point and density values) were taken from recent physical chemistry literature dealing with fluid properties. Where conflicts were found, the value deemed most reliable was chosen.

The table is arranged alphabetically by substance name, which generally is either an IUPAC systematic name or, in the case of pesticides, pharmaceuticals, and other complex compounds, a simple trivial name. Names in ubiquitous use, such as acetic acid and formaldehyde, are adopted rather than their systematic equivalents. Synonyms are given in the column following the primary name, and structure diagrams are given on the page facing the data listing. The explanation of the data columns follows:

- **No.**: An identification number used in the indexes.
- **Name**: Primary name of the substance
- **Synonym**: A synonym in common use. When the primary name is non-systematic, a systematic name may appear here.
- **Mol. Form.**: The molecular formula written in the Hill convention.
- **CAS RN**: The Chemical Abstracts Service Registry Number for the compound.
- **Mol. Wt**: Molecular weight (relative molar mass) as calculated with the 2001 IUPAC Standard Atomic Weights.
- **Physical Form**: A notation of the physical phase, color, crystal type, or other features of the compound at ambient temperature. Abbreviations are given below.
- **mp**: Normal melting point in ˚C. A value is sometimes followed by "dec", indicating decomposition is observed at the stated temperature (so that it is probably not a true melting point). The notation "tp" indicates a triple point, where solid, liquid, and gas are in equilibrium.
- **bp**: Normal boiling point in ˚C, if it is available. This is the temperature at which the liquid phase is in equilibrium with the vapor at a pressure of 760 mmHg (101.325 kPa). A notation "sp" following the value indicates a sublimation point, where the vapor pressure of the solid phase reaches 760 mmHg. When a notation such as "dec" or "exp" (explodes) follows the value, the temperature may not be a true boiling point. A simply entry "sub" indicates the solid has a significant sublimation pressure at ambient temperatures. The boiling point at reduced pressure is listed in some cases, with or without the normal boiling point. Here the superscript indicates the pressure in mmHg.
- **den**: Density (mass per unit volume) in g/cm^3. The temperature in ˚C is indicated by a superscript. Values refer to the liquid or solid phase, and all values are true densities, not specific gravities. The number of decimal places gives a rough estimate of the accuracy of the value.
- n_D: Refractive index, at the temperature in ˚C indicated by the superscript. Unless otherwise indicated, all values refer to a wavelength of 589 nm (sodium D line). Values are given only for liquids and solids.
- **Solubility**: Qualitative indication of solubility in common solvents. Abbreviations are:

i	insoluble
sl	slightly soluble
s	soluble
vs	very soluble
msc	miscible
dec	decomposes

Abbreviations for solvents are given below.

In order to facilitate the location of compounds in the table, three indexes are provided:

- **Synonym Index**: Includes common synonyms, but not the primary name by which the table is arranged.
- **Molecular Formula Index**: Lists compounds by molecular formula in the Hill Order (see Preface to this *Handbook*).
- **CAS Registry Number Index**: Lists compounds by Chemical Abstracts Service Registry Number. Note there is some redundancy in this index, because many compounds have several Registry Numbers associated with them. Thus the CAS RN in a table entry may differ from the CAS RN that points to it in the index. For example, CAS RN 1319-77-3 in the index points to all three cresol isomers, each of which has its own specific CAS RN.

The assistance of Fiona Macdonald in checking names and formulas is gratefully acknowledged, as well as the efforts of Janice Shackleton, Trupti Desai, Nazila Kamaly, Matt Griffiths, and Lawrence Braschi in preparing the structure diagrams.

List of Abbreviations


Ac	acetyl
Ac_2O	acetic anhydride
AcOEt	ethyl acetate
ac	acid
ace	acetone
al	alcohol (ethanol)
alk	alkali
amor	amorphous
anh	anhydrous
aq	aqueous
bipym	bipyramidal
bl	blue
blk	black
bp	boiling point
br	brown
bt	bright
Bu	butyl
BuOH	1-butanol
bz	benzene
chl	chloroform
col	colorless
con, conc	concentrated
cry	crystals
ctc	carbon tetrachloride
cy, cyhex	cyclohexane
dec	decomposes
den	density
dil	dilute
diox	dioxane
dk	dark
DMF	dimethylformamide
DMSO	dimethyl sulfoxide
efflor	efflorescent
Et	ethyl
EtOH	ethanol
eth	diethyl ether
exp	explodes
fl	flakes
flr	fluorescent
fum	fumes, fuming
gl	glacial
gr	gray
gran	granular
grn	green
hex	hexagonal
HOAc	acetic acid
hp	heptane
hx	hexane
hyd	hydrate
hyg	hygroscopic
i	insoluble
i-	iso-
iso	isooctane
lf	leaves
lig	ligroin
liq	liquid
lo	long
mcl	monoclinic
Me	methyl
MeCN	acetonitrile
MeOH	methanol
misc, msc	miscible
mp	melting point
n	refractive index
nd	needles
oct	octahedra, octahedral
oran	orange
orth	orthorhombic
os	organic solvents
pa	pale
peth	petroleum ether
Ph	phenyl
PhCl	chlorobenzene
$PhNH_2$	aniline
$PhNO_2$	nitrobenzene
pl	plates
pow	powder
Pr	propyl
PrOH	1-propanol
pr	prisms
purp	purple
py	pyridine
pym	pyramids, pyramidal
reac	reacts
rhom	rhombic
s	soluble
sat	saturated
sc	scales
sl	slightly soluble
soln	solution
sp	sublimation point
stab	stable
sub	sublimes
sulf	sulfuric acid
syr	syrup
tab	tablets
tcl	triclinic
tetr	tetragonal
tfa	trifluoroacetic acid
thf, THF	tetrahydrofuran
tol	toluene
tp	triple point
trg	trigonal
unstab	unstable
vap	vapor
viol	violet
visc	viscous
vol	volatile
vs	very soluble
w	water
wh	white
xyl	xylene
ye	yellow


References


1. American Chemical Society, *Reagent Chemicals, Ninth Edition*, Oxford University Press, New York, 2000.
2. Daubert, T. E., Danner, R. P., Sibul, H. M., and Stebbins, C. C., *Physical and Thermodynamic Properties of Pure Compounds: Data Compilation*, extant 2002 (core with supplements), Taylor & Francis, Bristol, PA.
3. National Library of Medicine, *Hazardous Substances Data Bank*, <http://toxnet.nlm.nih.gov/cgi-bin/sis/htmlgen?HSDB>.
4. United Nations Environmental Program, *Persistent Organic Pollutants*, <http://www.chem.unep.ch/pops/>.


5. Environmental Protection Agency, *Chemicals on Reporting Rules*, <http://www.epa.gov/opptintr/CORR>.
6. Environmental Protection Agency, *Integrated Risk Information System*, <http://www.epa.gov/iris/index.html>.
7. Lide, D. R., and Milne, G. W. A., Editors, *Handbook of Data on Organic Compounds, Third Edition*, CRC Press, Boca Raton, FL, 1993.
8. Macdonald, F., Editor, *Chapman & Hall/CRC Combined Chemical Dictionary,* <http://www.chemnetbase.com/scripts/ccdweb.exe>.
9. Linstrom, P. J., and Mallard, W. G., Editors, *NIST Chemistry WebBook*, NIST Standard Reference Database No. 69, July 2001, National Institute of Standards and Technology, Gaithersburg, MD 20899, <http://webbook.nist.gov>.
10. Thermodynamics Research Center, National Institute of Standards and Technology, *TRC Thermodynamic Tables*, <http://trc.nist.gov>.
11. O'Neil, M. J., Editor, *The Merck Index, Thirteenth Edition*, Merck & Co., Rahway, NJ, 2001.
12. Stevenson, R. M., and Malanowski, S., *Handbook of the Thermodynamics of Organic Compounds*, Elsevier, New York, 1987.
13. Riddick, J. A., Bunger, W. B., and Sakano, T. K., *Organic Solvents*, Fourth Edition, John Wiley & Sons, New York, 1986.
14. *Physical Constants of Hydrocarbon and Non-Hydrocarbon Compounds*, ASTM Data Series DS 4B, ASTM, Philadelphia, 1988.
15. *Beilstein Database*, <http://www.mdli.com/products/xfirebeilstein.html>.
16. *Landolt-Börnstein Numerical Data and Functional Relationships in Science and Technology,* <http://www.landolt-boernstein.com>.
17. Vargaftik, N.B., Vinogradov, Y. K., and Yargin, V. S., *Handbook of Physical Properties of Liquids and Gases, Third Edition*, Begell House, New York, 1996
18. Lide, D. R., and Kehiaian, H. V., *Handbook of Thermophysical and Thermochemical Data*, CRC Press, Boca Raton, FL, 1994.
19. Lide, D. R., Editor, *Properties of Organic Compounds*, <http://www.chemnetbase.com/scripts/pocweb.exe>.


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1	Abate	Temephos	$C_{16}H_{20}O_6P_2S_3$	3383-96-8	466.469		30		1.32		
2	Abietic acid		$C_{20}H_{30}O_2$	514-10-3	302.451	mcl pl (al-w)	173.5	250^{9}			vs ace, bz, eth, EtOH
3	Abscisic acid		$C_{15}H_{20}O_4$	21293-29-8	264.318	cry (chl-peth)	160	sub 120			vs ace, eth, chl
4	Acacetin	5,7-Dihydroxy-2-(4-methoxyphenyl)-4*H*-1-benzopyran-4-one	$C_{16}H_{12}O_5$	480-44-4	284.263	ye nd (95% al)	263				vs EtOH
5	Acebutolol, (±)		$C_{18}H_{28}N_2O_4$	37517-30-9	336.426	cry	121				
6	Acedapsone		$C_{16}H_{16}N_2O_4S$	77-46-3	332.374	pa ye nd (eth) lf (dil al)	290				sl H_2O
7	Acenaphthene	1,2-Dihydroacenaphthylene	$C_{12}H_{10}$	83-32-9	154.207		93.4	279	1.222^{20}	1.6048^{95}	i H_2O; sl EtOH, chl; vs bz; s HOAc
8	Acenaphthylene	Acenaphthalene	$C_{12}H_8$	208-96-8	152.192		91.8	280	0.8987^{16}		i H_2O; vs EtOH, eth, bz; sl chl
9	1,2-Acenaphthylenedione		$C_{12}H_6O_2$	82-86-0	182.175	ye nd (HOAc)	261	sub	1.4800^{20}		i H_2O; sl EtOH, bz, HOAc; s lig
10	Acenocoumarol	Nicoumalone	$C_{19}H_{15}NO_6$	152-72-7	353.325	cry (ace aq)	198				i H_2O
11	Acephate	Phosphoramidothioic acid, acetyl-, *O,S*-dimethyl ester	$C_4H_{10}NO_3PS$	30560-19-1	183.166		88		1.35^{20}		
12	Acepromazine		$C_{19}H_{22}N_2OS$	61-00-7	326.455	oran oil		$230^{0.5}$			
13	Acesulfame		$C_4H_5NO_4S$	33665-90-6	163.153	nd (bz)	123.2				s bz, chl
14	Acetaldehyde	Ethanal	C_2H_4O	75-07-0	44.052	vol liq or gas	-123.37	20.1	0.7834^{18}	1.3316^{20}	msc H_2O, EtOH, eth, bz; sl chl
15	Acetaldehyde phenylhydrazone		$C_8H_{10}N_2$	935-07-9	134.178		99.5	150^{40}, 135^{21}			vs EtOH
16	Acetaldoxime	Acetaldehyde oxime	C_2H_5NO	107-29-9	59.067	nd	45	115	0.9656^{20}	1.4264^{20}	s H_2O, chl; msc EtOH, eth
17	Acetamide	Ethanamide	C_2H_5NO	60-35-5	59.067	trg mcl (al-eth)	80.16	222.0	0.9986^{85}	1.4278	vs H_2O, EtOH
18	Acetanilide	*N*-Phenylacetamide	C_8H_9NO	103-84-4	135.163		114.3	304	1.2190^{15}		sl H_2O; vs EtOH, ace; s eth, s bz, tol
19	Acetazolamide	*N*-[5-(Aminosulfonyl)-1,3,4-thiadiazol-2-yl]acetamide	$C_4H_6N_4O_3S_2$	59-66-5	222.246		260.5				sl H_2O
20	Acethion		$C_8H_{17}O_4PS_2$	919-54-0	272.322	liq		$137^{1.5}$	1.18^{20}		
21	Acetic acid	Ethanoic acid	$C_2H_4O_2$	64-19-7	60.052		16.64	117.9	1.0446^{25}	1.3720^{20}	msc H_2O, EtOH, eth, ace, bz; s chl, CS_2
22	Acetic acid, 2-phenylhydrazide		$C_8H_{10}N_2O$	114-83-0	150.177	hex pr (eth)	130.0				vs H_2O, EtOH; sl eth, chl, tfa; s bz
23	Acetic anhydride		$C_4H_6O_3$	108-24-7	102.089	liq	-74.1	139.5	1.082^{20}	1.3901^{20}	vs H_2O; s EtOH, bz; msc eth; sl ctc
24	Acetoacetanilide		$C_{10}H_{11}NO_2$	102-01-2	177.200	pr or nd (bz or lig)	86				sl H_2O; s EtOH, eth, bz, chl, acid, lig
25	Acetoacetic acid		$C_4H_6O_3$	541-50-4	102.089	cry (eth)	36.5	dec 100			vs H_2O, eth, EtOH
26	2-Acetoacetoxyethyl methacrylate	2-(Methacryloyloxy)ethyl acetoacetate	$C_{10}H_{14}O_5$	21282-97-3	214.215	liq		$100^{0.8}$	1.122	1.4560^{20}	
27	Acetochlor		$C_{14}H_{20}ClNO_2$	34256-82-1	269.768	ye liq		$134^{0.4}$		1.5272^{20}	sl H_2O
28	Acetohexamide		$C_{15}H_{20}N_2O_4S$	968-81-0	324.396	cry (EtOH aq)	188				i H_2O, eth; sl EtOH, chl; s py
29	Acetohydrazide		$C_2H_6N_2O$	1068-57-1	74.081		67	137^{25}			s H_2O, EtOH; sl eth
30	Acetohydroxamic acid	*N*-Hydroxyacetamide	$C_2H_5NO_2$	546-88-3	75.067	hyg cry	90				
31	1-Acetonaphthone		$C_{12}H_{10}O$	941-98-0	170.206		34	297	1.1171^{21}	1.6280^{22}	i H_2O; s EtOH, eth, ace, chl
32	2-Acetonaphthone		$C_{12}H_{10}O$	93-08-3	170.206	nd (lig, dil al)	56	302			sl EtOH, ctc
33	Acetone	2-Propanone	C_3H_6O	67-64-1	58.079	liq	-94.7	56.05	0.7845^{25}	1.3588^{20}	msc H_2O, EtOH, eth, ace, bz, chl
34	Acetone cyanohydrin		C_4H_7NO	75-86-5	85.105		-19	82^{23}	0.932^{19}	1.3992^{20}	vs H_2O, EtOH, eth; s ace, bz, chl; i peth
35	Acetone (2,4-dinitrophenyl) hydrazone		$C_9H_{10}N_4O_4$	1567-89-1	238.200	ye nd or pl (al)	128				i H_2O; s EtOH, eth, bz, chl, AcOEt
36	Acetone (1-methylethylidene) hydrazone	Dimethyl ketazine	$C_6H_{12}N_2$	627-70-3	112.172	liq	-12.5	133	0.8390^{20}	1.4535^{20}	msc H_2O, EtOH, eth; s ace
37	Acetone thiosemicarbazide		$C_4H_9N_3S$	1752-30-3	131.199	ye cry	176				s ace



Abate



Abietic acid



Abscisic acid



Acacetin



Acebutolol, (±)



Acedapsone



Acenaphthene



Acenaphthylene


1,2-Acenaphthylenedione



Acenocoumarol


Acephate


Acepromazine



Acesulfame



Acetaldehyde



Acetaldehyde phenylhydrazone


Acetaldoxime



Acetamide



Acetanilide



Acetazolamide



Acethion



Acetic acid



Acetic acid, 2-phenylhydrazide



Acetic anhydride



Acetoacetanilide



Acetoacetic acid



2-Acetoacetoxyethyl methacrylate



Acetochlor


Acetohexamide


Acetohydrazide



Acetohydroxamic acid



1-Acetonaphthone



2-Acetonaphthone


Acetone


Acetone cyanohydrin



Acetone (2,4-dinitrophenyl)hydrazone



Acetone (1-methylethylidene)hydrazone



Acetone thiosemicarbazide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
38	Acetonitrile	Methyl cyanide	C_2H_3N	75-05-8	41.052	liq	-43.82	81.65	0.7857^{20}	1.3442^{30}	msc H_2O, EtOH, eth, ace, bz, ctc
39	Acetophenone	Methyl phenyl ketone	C_8H_8O	98-86-2	120.149	mcl pr or pl	20.5	202	1.0281^{20}	1.5372^{20}	sl H_2O; s EtOH, eth, ace, bz, con sulf, chl
40	Acetophenone azine	Methylphenyl ketazine	$C_{16}H_{16}N_2$	729-43-1	236.311		120				
41	Acetoxon	Acetophos	$C_8H_{17}O_5PS$	2425-25-4	256.257	liq		$73^{0.005}$			
42	*N*-Acetylacetamide		$C_4H_7NO_2$	625-77-4	101.105	nd (eth)	79	223.5			s H_2O, EtOH, eth, chl, lig
43	*N*-Acetyl-*L*-alanine		$C_5H_9NO_3$	97-69-8	131.130		125				
44	4-(Acetylamino)benzenesulfonyl chloride	Acetylsulfanilyl chloride	$C_8H_8ClNO_3S$	121-60-8	233.673	nd (bz), pr (bz-chl)	149				vs EtOH, eth; s bz, chl
45	2-(Acetylamino)benzoic acid		$C_9H_9NO_3$	89-52-1	179.172	nd (HOAc)	187.5				sl H_2O; s EtOH; vs eth, ace, bz, HOAc
46	4-(Acetylamino)benzoic acid		$C_9H_9NO_3$	556-08-1	179.172	nd (HOAc)	256.5				i H_2O; s EtOH; sl eth, tfa
47	2-(Acetylamino)-2-deoxy-*D*-glucose	*N*-Acetyl-*D*-glucosamine	$C_8H_{15}NO_6$	7512-17-6	221.208		205				
48	2-(Acetylamino)-2-deoxy-*D*-mannose	*N*-Acetyl-*D*-mannosamine	$C_8H_{15}NO_6$	3615-17-6	221.208	cry (ace aq)	128				dec alk
49	2-(Acetylamino)fluorene		$C_{15}H_{13}NO$	53-96-3	223.270	cry (dil al)	193				i H_2O; s EtOH, eth, HOAc
50	4-(Acetylamino)fluorene		$C_{15}H_{13}NO$	28322-02-3	223.270	br cry (bz)	200				
51	6-(Acetylamino)hexanoic acid	ε-Acetamidocaproic acid	$C_8H_{15}NO_3$	57-08-9	173.210	cry (ace)	104.5				
52	4-Acetylanisole		$C_9H_{10}O_2$	100-06-1	150.174	pl (peth)	38.5	258	1.0818^{41}	1.547^{41}	sl H_2O; s EtOH, eth, ace, chl
53	2-Acetylbenzoic acid		$C_9H_8O_3$	577-56-0	164.158	nd (w), pr (bz)	114.5	111^{2}			vs H_2O, eth, EtOH
54	3-Acetylbenzoic acid		$C_9H_8O_3$	586-42-5	164.158		172	111^{2}			s H_2O; msc EtOH
55	4-Acetylbenzoic acid		$C_9H_8O_3$	586-89-0	164.158	nd (w)	208	sub			vs H_2O
56	Acetyl benzoylperoxide	Acetozone	$C_9H_8O_4$	644-31-5	180.158	wh nd (lig)	37	130^{19}			vs eth
57	Acetyl bromide	Ethanoyl bromide	C_2H_3BrO	506-96-7	122.948	liq	-96	76	1.6625^{16}	1.4486^{20}	msc eth, bz, chl; s ace
58	Acetyl chloride	Ethanoyl chloride	C_2H_3ClO	75-36-5	78.497	liq	-112.8	50.7	1.1051^{20}	1.3886^{20}	msc eth, ace, bz, chl; s ctc
59	Acetylcholine bromide		$C_7H_{16}BrNO_2$	66-23-9	226.112	hyg cry	146				vs H_2O
60	Acetylcholine chloride		$C_7H_{16}ClNO_2$	60-31-1	181.661		150				s H_2O, EtOH; i eth
61	Acetylcholine iodide		$C_7H_{16}INO_2$	2260-50-6	273.112	hyg	163				
62	2-Acetylcyclohexanone		$C_8H_{12}O_2$	874-23-7	140.180		-11	112^{18}, 101^{14}	1.0782^{25}	1.5138^{20}	s ctc
63	2-Acetylcyclopentanone		$C_7H_{10}O_2$	1670-46-8	126.153			73^{20}	1.0431^{25}	1.4906^{20}	
64	*N*-Acetyl-*L*-cysteine	Acetylcysteine	$C_5H_9NO_3S$	616-91-1	163.195	cry (w)	109.5				
65	3-Acetyldihydro-2(3*H*)-furanone	α-Acetylbutyrolactone	$C_6H_8O_3$	517-23-7	128.126			107^{5}	1.1846^{20}	1.4585^{20}	vs H_2O
66	1-Acetyl-2,5-dihydroxybenzene	2,5-Dihydroxyacetophenone	$C_8H_8O_3$	490-78-8	152.148	ye grn nd (dil al or w)	205.3				sl H_2O, eth, bz; s EtOH
67	Acetylene	Ethyne	C_2H_2	74-86-2	26.037	col gas	-80.7 (triple point)	-84.7 sp	0.377^{25} (p>1 atm)		sl H_2O, EtOH, CS_2; s ace, bz, chl
68	*N*-Acetylethanolamine		$C_4H_9NO_2$	142-26-7	103.120		63.5	166^{8}	1.1079^{25}	1.4674^{20}	msc H_2O; s ace; sl bz, lig
69	Acetyl fluoride	Ethanoyl fluoride	C_2H_3FO	557-99-3	62.042	vol liq or gas	-84	20.8	1.032^{25}		msc EtOH, eth; s bz, chl; sl CS_2
70	*N*-Acetylglutamic acid		$C_7H_{11}NO_5$	1188-37-0	189.166	pr (w)	199				s H_2O, EtOH
71	*N*-Acetylglycine	Aceturic acid	$C_4H_7NO_3$	543-24-8	117.104	lo nd (w, MeOH)	206				vs H_2O, ace, EtOH
72	*trans*-1-Acetyl-4-hydroxy-*L*-proline	Oxaceprol	$C_7H_{11}NO_4$	33996-33-7	173.167	cry (Ac)	132				vs H_2O, MeOH
73	1-Acetyl-1*H*-imidazole		$C_5H_6N_2O$	2466-76-4	110.114		104.5				sl H_2O; s EtOH, eth, chl, THF
74	Acetyl iodide	Ethanoyl iodide	C_2H_3IO	507-02-8	169.948			108	2.0673^{20}	1.5491^{20}	vs eth
75	Acetyl isothiocyanate		C_3H_3NOS	13250-46-9	101.127			132.5	1.1523^{13}	1.5231^{18}	s eth, CS_2
76	*N*6-Acetyl-*L*-lysine		$C_8H_{16}N_2O_3$	692-04-6	188.224		265 dec				
77	*N*-Acetyl-*DL*-methionine		$C_7H_{13}NO_3S$	1115-47-5	191.248		114.5				
78	*N*-Acetyl-*L*-methionine	Methionamine	$C_7H_{13}NO_3S$	65-82-7	191.248		105.5				
79	1-Acetyl-17-methoxyaspidospermidine	Aspidospermine	$C_{22}H_{30}N_2O_2$	466-49-9	354.485	nd or pr (al) nd (peth)	208	220^{2}			sl H_2O, eth; s EtOH, bz, chl
80	*N*-Acetyl-*N*-methylacetamide		$C_5H_9NO_2$	1113-68-4	115.131	liq	-25	195; 114.5^{61}	1.0663^{25}	1.4502^{25}	msc H_2O; i eth
81	1-Acetyl-3-methylpiperidine		$C_8H_{15}NO$	4593-16-2	141.211	liq	-13.6	239	0.9684^{25}	1.4731^{25}	vs H_2O
82	3-Acetyl-6-methyl-2*H*-pyran-2,4(3*H*)-dione	Dehydroacetic acid	$C_8H_8O_4$	520-45-6	168.148		109	270			vs H_2O, eth; sl EtOH, chl


Acetonitrile



Acetophenone



Acetophenone azine



Acetoxon



N-Acetylacetamide



N-Acetyl-*L*-alanine



4-(Acetylamino)benzenesulfonyl chloride



2-(Acetylamino)benzoic acid



4-(Acetylamino)benzoic acid



2-(Acetylamino)-2-deoxy-*D*-glucose



2-(Acetylamino)-2-deoxy-*D*-mannose



2-(Acetylamino)fluorene



4-(Acetylamino)fluorene



6-(Acetylamino)hexanoic acid


4-Acetylanisole


2-Acetylbenzoic acid



3-Acetylbenzoic acid



4-Acetylbenzoic acid



Acetyl benzoylperoxide



Acetyl bromide



Acetyl chloride



Acetylcholine bromide



Acetylcholine chloride



Acetylcholine iodide


2-Acetylcyclohexanone



2-Acetylcyclopentanone


N-Acetyl-*L*-cysteine



3-Acetyldihydro-2(3*H*)-furanone



1-Acetyl-2,5-dihydroxybenzene


Acetylene



N-Acetylethanolamine


Acetyl fluoride



N-Acetylglutamic acid



N-Acetylglycine



trans-1-Acetyl-4-hydroxy-*L*-proline



1-Acetyl-1*H*-imidazole



Acetyl iodide



Acetyl isothiocyanate



*N*6-Acetyl-*L*-lysine



N-Acetyl-*DL*-methionine


N-Acetyl-*L*-methionine



1-Acetyl-17-methoxyaspidospermidine



N-Acetyl-*N*-methylacetamide



1-Acetyl-3-methylpiperidine



3-Acetyl-6-methyl-2*H*-pyran-2,4(3*H*)-dione


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
83	4-Acetylmorpholine		$C_6H_{11}NO_2$	1696-20-4	129.157		14.5	152^{50}, 118^{12}	1.1145^{20}	1.4827^{20}	msc H_2O; s EtOH, ace, ctc
84	*N*-Acetylneuraminic acid	Aceneuramic acid	$C_{11}H_{19}NO_9$	131-48-6	309.271		186				
85	Acetyl nitrate		$C_2H_3NO_4$	591-09-3	105.050			exp 60; 22^{70}	1.24^{15}		
86	2-(Acetyloxy)benzoic acid	Acetylsalicylic acid	$C_9H_8O_4$	50-78-2	180.158	nd (w), mcl tab (w)	135				s H_2O, eth, chl; vs EtOH; sl bz
87	4-(Acetyloxy)benzoic acid		$C_9H_8O_4$	2345-34-8	180.158		188.5				
88	2-(Acetyloxy)-5-bromobenzoic acid	5-Bromoacetylsalicylic acid	$C_9H_7BrO_4$	1503-53-3	259.054	nd (al)	60				i H_2O; vs EtOH, eth
89	4-(Acetyloxy)-3-methoxybenzaldehyde		$C_{10}H_{10}O_4$	881-68-5	194.184		78				sl H_2O; vs EtOH, eth
90	2-(Acetyloxy)-1-phenylethanone		$C_{10}H_{10}O_3$	2243-35-8	178.184	orth pl	49	270	1.1169^{65}	1.5036^{65}	i H_2O; vs EtOH, eth, chl; sl bz, lig
91	1-(Acetyloxy)-2-propanone	Acetoxyacetone	$C_5H_8O_3$	592-20-1	116.116			171; 63^{11}	1.0757^{20}	1.4141^{20}	vs H_2O, eth, EtOH
92	(Acetyloxy)tributylstannane	Tributyltin acetate	$C_{14}H_{30}O_2Sn$	56-36-0	349.097		84.7				
93	(Acetyloxy)triphenylstannane	Triphenyltin acetate	$C_{20}H_{18}O_2Sn$	900-95-8	409.066		121.5				
94	4-Acetylphenyl acetate		$C_{10}H_{10}O_3$	13031-43-1	178.184						s ctc, CS_2
95	*N*-Acetyl-*L*-phenylalanine		$C_{11}H_{13}NO_3$	2018-61-3	207.226		173.5				s EtOH
96	*N*-Acetyl-*L*-phenylalanine, ethyl ester		$C_{13}H_{17}NO_3$	2361-96-8	235.279	cry (EtOH aq)	93				
97	*N*-Acetyl-*L*-phenylalanine, methyl ester		$C_{12}H_{15}NO_3$	3618-96-0	221.252	nd (peth) or visc oil (chl)	91				
98	Acetyl phosphate		$C_2H_5O_5P$	590-54-5	140.032	unstab in soln					
99	1-Acetylpiperidine		$C_7H_{13}NO$	618-42-8	127.184	liq	-13.4	226.5	1.011^{9}	1.4790^{25}	vs H_2O, EtOH
100	1-Acetyl-4-piperidinone		$C_7H_{11}NO_2$	32161-06-1	141.168			218; $124^{0.2}$	1.146^{25}	1.5026^{20}	
101	3-Acetylpyridine adenine dinucleotide	3-Acetyl NAD	$C_{22}H_{28}N_6O_{14}P_2$	86-08-8	662.436	solid					
102	4-Acetylthioanisole		$C_9H_{10}OS$	1778-09-2	166.239		81.5				
103	Acetyl thiocholine iodide		$C_7H_{16}INOS$	1866-15-5	289.177		205				
104	*N*-Acetyl-*L*-tryptophan		$C_{13}H_{14}N_2O_3$	1218-34-4	246.261	nd (dil MeOH)	189.5				s H_2O, EtOH, alk
105	*N*-Acetyl-*L*-tyrosine		$C_{11}H_{13}NO_4$	537-55-3	223.226	cry (w); pl (diox)	153				
106	*N*-Acetyl-*L*-tyrosine ethyl ester		$C_{13}H_{17}NO_4$	840-97-1	251.279		80.5				
107	*N*-Acetyl-*L*-valine		$C_7H_{13}NO_3$	96-81-1	159.183		164				
108	Acid Fuchsin	Fuchsin, acid	$C_{20}H_{17}N_3Na_2O_9S_3$	3244-88-0	585.539						sl H_2O, EtOH
109	Acifluorfen	5-[2-Chloro-4-(trifluoromethyl) phenoxy]-2-nitrobenzoic acid	$C_{14}H_7ClF_3NO_5$	50594-66-6	361.658		150				
110	Aconine		$C_{25}H_{41}NO_9$	509-20-6	499.596	amor	132				s H_2O, EtOH, chl; sl eth, lig
111	Aconitine		$C_{34}H_{47}NO_{11}$	302-27-2	645.737	orth lf	204				vs bz, EtOH, chl
112	9-Acridinamine	Aminacrine	$C_{13}H_{10}N_2$	90-45-9	194.231	ye nd (ace or al)	241				s EtOH, ace; sl DMSO; vs dil HCl
113	Acridine	Dibenzo[b,e]pyridine	$C_{13}H_9N$	260-94-6	179.217	orth nd or pr (al)	106(form a); 110(form b)	344.86	1.005^{20}		i H_2O; sl ctc; vs EtOH, eth, bz
114	3,6-Acridinediamine	Proflavine	$C_{13}H_{11}N_3$	92-62-6	209.246	ye nd (al or w)	285				s H_2O; vs EtOH; sl eth, bz
115	9(10*H*)-Acridinone		$C_{13}H_9NO$	578-95-0	195.216	ye lf (al)	>300				i H_2O, eth, bz; sl EtOH; s HOAc, alk
116	Acrolein	2-Propenal	C_3H_4O	107-02-8	56.063	liq	-87.7	52.6	0.840^{20}	1.4017^{20}	vs H_2O; s EtOH, eth, ace; sl chl
117	Acrylamide	2-Propenamide	C_3H_5NO	79-06-1	71.078	lf (bz)	84.5	192.6			vs H_2O, chl; s EtOH, eth, ace
118	Acrylic acid	2-Propenoic acid	$C_3H_4O_2$	79-10-7	72.063		12.5	141	1.0511^{20}	1.4224^{20}	msc H_2O, EtOH, eth; s ace, bz, ctc
119	Acrylonitrile	Propenenitrile	C_3H_3N	107-13-1	53.063	liq	-83.48	77.3	0.8007^{25}	1.3911^{20}	s H_2O; vs ace, bz, eth, EtOH
120	Acyclovir		$C_8H_{11}N_5O_3$	59277-89-3	225.205	cry (EtOH)	225				
121	Adenine	1*H*-Purin-6-amine	$C_5H_5N_5$	73-24-5	135.128	orth nd (+3w)	360 dec	sub 220			s H_2O; sl EtOH; i eth, chl
122	Adenosine	β-*D*-Ribofuranoside, adenine-9	$C_{10}H_{13}N_5O_4$	58-61-7	267.242	n(w+3/2)	235.5				sl H_2O; i EtOH
123	Adenosine cyclic 3',5'-(hydrogen phosphate)	cAMP	$C_{10}H_{12}N_5O_6P$	60-92-4	329.206	cry	219				
124	Adenosine 3',5'-diphosphate	3'-Adenylic acid, 5'-(dihydrogen phosphate)	$C_{10}H_{15}N_5O_{10}P_2$	1053-73-2	427.202	amor pow					



4-Acetylmorpholine



N-Acetylneuraminic acid



Acetyl nitrate



2-(Acetyloxy)benzoic acid



4-(Acetyloxy)benzoic acid



2-(Acetyloxy)-5-bromobenzoic acid



4-(Acetyloxy)-3-methoxybenzaldehyde



2-(Acetyloxy)-1-phenylethanone



1-(Acetyloxy)-2-propanone



(Acetyloxy)tributylstannane



(Acetyloxy)triphenylstannane



4-Acetylphenyl acetate



N-Acetyl-*L*-phenylalanine



N-Acetyl-*L*-phenylalanine, ethyl ester



N-Acetyl-*L*-phenylalanine, methyl ester



Acetyl phosphate



1-Acetylpiperidine



1-Acetyl-4-piperidinone



3-Acetylpyridine adenine dinucleotide



4-Acetylthioanisole



Acetyl thiocholine iodide



N-Acetyl-*L*-tryptophan



N-Acetyl-*L*-tyrosine



N-Acetyl-*L*-tyrosine ethyl ester



N-Acetyl-*L*-valine



Acid Fuchsin



Acifluorfen



Aconine


Aconitine



9-Acridinamine



Acridine


3,6-Acridinediamine



9(10*H*)-Acridinone



Acrolein



Acrylamide



Acrylic acid



Acrylonitrile


Acyclovir



Adenine



Adenosine



Adenosine cyclic 3',5'-(hydrogen phosphate)



Adenosine 3',5'-diphosphate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
125	Adenosine 5'-methylenediphosphonate	Adenosine, 5'-[hydrogen (phosphonomethyl) phosphonate]	$C_{11}H_{17}N_5O_9P_2$	3768-14-7	425.229	cry (w)	204				s H_2O
126	Adenosine 3'-phosphate	3'-Adenylic acid	$C_{10}H_{14}N_5O_7P$	84-21-9	347.222	col nd	195 dec				
127	Adenosine 5'-triphosphate	ATP	$C_{10}H_{16}N_5O_{13}P_3$	56-65-5	507.181		144 dec				
128	*S*-Adenosyl-*L*-homocysteine		$C_{14}H_{20}N_6O_5S$	979-92-0	384.411		210 dec				
129	5'-Adenylic acid	Adenosine 5'-monophosphate	$C_{10}H_{14}N_5O_7P$	61-19-8	347.222		195 dec				vs H_2O; s EtOH, 10% HCl
130	Adipamic acid		$C_6H_{11}NO_3$	334-25-8	145.156	nd (w)	161.5				
131	Adiphenine hydrochloride		$C_{20}H_{26}ClNO_2$	50-42-0	347.879	cry	113.5				vs H_2O; sl EtOH, eth
132	Adipic acid	1,6-Hexanedioic acid	$C_6H_{10}O_4$	124-04-9	146.141	mcl pr (w, ace, lig)	152.5	337.5	1.360^{25}		sl H_2O; vs EtOH; s eth; i HOAc, lig
133	Adiponitrile	Hexanedinitrile	$C_6H_8N_2$	111-69-3	108.141	nd (eth)	1	295	0.9676^{20}	1.4380^{20}	sl H_2O, eth; s chl, EtOH
134	Adrenalone		$C_9H_{11}NO_3$	99-45-6	181.188	nd	235 dec				sl H_2O, EtOH, eth
135	Affinin	*N*-(2-Methylpropyl)-2,6,8-decatrienamide	$C_{14}H_{23}NO$	25394-57-4	221.339	ye oil	23	$162^{0.5}$		1.5134^{25}	i H_2O
136	Aflatoxin B1		$C_{17}H_{12}O_6$	1162-65-8	312.273	cry	268				
137	Aflatoxin B2		$C_{17}H_{14}O_6$	7220-81-7	314.289		287.5				
138	Aflatoxin G1		$C_{17}H_{12}O_7$	1165-39-5	328.273	cry	245				
139	Agaritine	*L*-Glutamic acid, 5-[2-[4-(hydroxymethyl)phenyl] hydrazide]	$C_{12}H_{17}N_3O_4$	2757-90-6	267.281	cry (dil al)	207 dec				vs H_2O
140	Ajmalan-17,21-diol, (17*R*,21α)	Ajmaline	$C_{20}H_{26}N_2O_2$	4360-12-7	326.432	pl (+3.5w) (aq AcOEt)	206				i H_2O; s EtOH, chl; sl eth, bz
141	Alachlor		$C_{14}H_{20}ClNO_2$	15972-60-8	269.768		40	$100^{0.02}$	1.133^{25}		
142	*DL*-Alanine	*DL*-2-Aminopropanoic acid	$C_3H_7NO_2$	302-72-7	89.094	orth pr or nd (w)	300 dec	sub 250	1.424^{25}		s H_2O; vs EtOH
143	*D*-Alanine	2-Aminopropanoic acid, (*R*)	$C_3H_7NO_2$	338-69-2	89.094	nd (w, al)	314 dec	sub			s H_2O; sl EtOH; i eth
144	*L*-Alanine	2-Aminopropanoic acid, (*S*)	$C_3H_7NO_2$	56-41-7	89.094	orth (w)	297 dec	sub 250	1.432^{22}		s H_2O; sl EtOH, py; i eth, ace
145	β-Alanine	3-Aminopropanoic acid	$C_3H_7NO_2$	107-95-9	89.094	nd, orth pr (al)	200 dec		1.437^{19}		s H_2O; sl EtOH; i eth, ace
146	Alantolactone		$C_{15}H_{20}O_2$	546-43-0	232.319	nd	76	275			vs bz, eth, EtOH, chl
147	Aldicarb		$C_7H_{14}N_2O_2S$	116-06-3	190.263		99		1.195^{25}		
148	Aldosterone		$C_{21}H_{28}O_5$	52-39-1	360.444	cry (HOAc)	166.5				
149	Aldoxycarb *S,S*-dioxide		$C_7H_{14}N_2O_4S$	1646-88-4	222.262	cry	141				sl H_2O
150	Aldrin		$C_{12}H_8Cl_6$	309-00-2	364.910		104				i H_2O; s EtOH, eth, ace, bz
151	Alizarin	1,2-Dihydroxy-9,10-anthracenedione	$C_{14}H_8O_4$	72-48-0	240.212	oran or red tcl nd or pr (al)	289.5				sl H_2O; s EtOH, eth, ace, bz; i chl
152	Alizarin Red S	Sodium alizarinesulfonate	$C_{14}H_7NaO_7S$	130-22-3	342.257						vs H_2O; s EtOH
153	Alizarin Yellow R		$C_{13}H_9N_3O_5$	2243-76-7	287.227	oran-br nd (dil HOAc)	253 dec				vs H_2O, EtOH
154	Alizurol purple	1-Hydroxy-4-[(4-methylphenyl) amino]-9,10-anthracenedione	$C_{21}H_{15}NO_3$	81-48-1	329.349	flat viol nd					s H_2SO_4
155	Alkannin		$C_{16}H_{16}O_5$	23444-65-7	288.295	br-red pr (bz)	149	sub 140			vs EtOH
156	Allantoic acid	Bis[(aminocarbonyl)amino] acetic acid	$C_4H_8N_4O_4$	99-16-1	176.132	nd	170 dec				sl H_2O, os, dil acid
157	Allantoin		$C_4H_6N_4O_3$	97-59-6	158.116	mcl pl or	239				sl H_2O; s EtOH, NaOH; i eth, MeOH
158	Allene		C_3H_4	463-49-0	40.064	col gas	-136.6	-34.4	0.584^{25} (p>1 atm)	1.4168	vs bz, peth
159	Allethrin		$C_{19}H_{26}O_3$	584-79-2	302.407				1.010^{20}		
160	Allicin		$C_6H_{10}OS_2$	539-86-6	162.272			dec	1.112^{20}	1.561^{20}	vs H_2O
161	Allopregnane-3β,21-diol-11,20-dione		$C_{21}H_{32}O_4$	566-02-9	348.477	cry (aq, ac, +w) nd (bz, ac)	190				
162	Allopregnan-20β-ol-3-one	5α-Pregnan-20β-ol-3-one	$C_{21}H_{34}O_2$	516-58-5	318.494		185				
163	Allopurinol	1,5-Dihydro-4*H*-pyrazolo[3,4-d] pyrimidin-4-one	$C_5H_4N_4O$	315-30-0	136.112	cry	350				
164	*D*-Allose		$C_6H_{12}O_6$	2595-97-3	180.155	cry (w)	128				vs H_2O
165	Alloxanic acid		$C_4H_4N_2O_5$	470-44-0	160.085	tcl pr (eth)	162 dec				vs H_2O, EtOH
166	Alloxantin		$C_8H_6N_4O_8$	76-24-4	286.156	orth pr (w+2)	254 dec				sl H_2O, EtOH, eth



Adenosine 5'-methylenediphosphonate



Adenosine 3'-phosphate



Adenosine 5'-triphosphate



S-Adenosyl-*L*-homocysteine



5'-Adenylic acid



Adipamic acid



Adiphenine hydrochloride



Adipic acid



Adiponitrile



Adrenalone



Affinin



Aflatoxin B1



Aflatoxin B2



Aflatoxin G1



Agaritine



Ajmalan-17,21-diol, (17*R*,21α)



Alachlor



DL-Alanine



D-Alanine



L-Alanine



β-Alanine



Alantolactone



Aldicarb



Aldosterone



Aldoxycarb *S,S*-dioxide



Aldrin



Alizarin



Alizarin Red S



Alizarin Yellow R



Alizurol purple



Alkannin



Allantoic acid



Allantoin



Allene



Allethrin



Allicin



Allopregnane-3β,21-diol-11,20-dione


Allopregnan-20β-ol-3-one



Allopurinol



D-Allose



Alloxanic acid


Alloxantin


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
167	Allyl acetate		$C_5H_8O_2$	591-87-7	100.117			103.5	0.9275^{20}	1.4049^{20}	sl H_2O; s ace; msc EtOH, eth
168	Allyl acetoacetate		$C_7H_{10}O_3$	1118-84-9	142.152	liq	-85	196; 66.5^{14}	1.0366^{20}	1.4398^{20}	s H_2O, lig; msc EtOH, bz
169	Allyl acrylate		$C_6H_8O_2$	999-55-3	112.127			121	0.9441^{20}	1.4320^{20}	sl H_2O; s EtOH, eth, acid
170	Allyl alcohol	2-Propen-1-ol	C_3H_6O	107-18-6	58.079	liq	-129	97.0	0.8540^{20}	1.4135^{20}	msc H_2O, EtOH, eth; s chl
171	Allylamine	2-Propen-1-amine	C_3H_7N	107-11-9	57.095	liq	-88.2	53.3	0.758^{20}	1.4205^{20}	msc H_2O, EtOH, eth; s chl
172	*N*-Allylaniline	Allylphenylamine	$C_9H_{11}N$	589-09-3	133.190			219; 106^{12}	0.9736^{25}	1.563^{20}	sl H_2O; s EtOH, ace; msc eth
173	Allylbenzene	2-Propenylbenzene	C_9H_{10}	300-57-2	118.175	liq	-40	156	0.8920^{20}	1.5131^{20}	i H_2O; s EtOH, eth, bz, ctc
174	α-Allylbenzenemethanol		$C_{10}H_{12}O$	936-58-3	148.201			228.5	1.004^{18}	1.5289^{21}	
175	Allyl benzoate		$C_{10}H_{10}O_2$	583-04-0	162.185				1.0569^{15}	1.5178^{20}	i H_2O; s EtOH, eth, ace, MeOH
176	Allyl butanoate		$C_7H_{12}O_2$	2051-78-7	128.169			142; 44.5^{15}	0.9017^{20}	1.4158^{20}	i H_2O; msc EtOH, eth; sl ctc
177	Allyl carbamate		$C_4H_7NO_2$	2114-11-6	101.105						sl ctc
178	Allylchlorodimethylsilane		$C_5H_{11}ClSi$	4028-23-3	134.680			111	0.8964^{20}	1.4195^{20}	
179	Allyl chloroformate		$C_4H_5ClO_2$	2937-50-0	120.535	hyg liq		109.5	1.136	1.4220^{20}	
180	Allyl *trans*-cinnamate	Allyl *trans*-3-phenyl-2-propenoate	$C_{12}H_{12}O_2$	1866-31-5	188.222			dec 268; 163^{17}	1.048^{23}	1.530^{20}	i H_2O; vs EtOH; msc eth; sl ctc
181	1-Allylcyclohexanol		$C_9H_{16}O$	1123-34-8	140.222			190	0.9341^{22}	1.4756^{22}	
182	1-Allylcyclohexene	1-(2-Propenyl)cyclohexene	C_9H_{14}	13511-13-2	122.207	liq		156			
183	Allylcyclopentane		C_8H_{14}	3524-75-2	110.197	liq	-110.7	125	0.793^{25}	1.4412^{20}	s chl
184	Allyldiethoxymethylsilane		$C_8H_{18}O_2Si$	18388-45-9	174.314			155	0.8572^{25}	1.4104^{20}	
185	Allyldiethylamine	*N,N*-Diethyl-2-propen-1-amine	$C_7H_{15}N$	5666-17-1	113.201			110	0.7477^{25}	1.4209^{20}	
186	Allyldimethylamine	*N,N*-Dimethyl-2-propen-1-amine	$C_5H_{11}N$	2155-94-4	85.148			63.5	0.7094^{25}	1.4010^{20}	
187	Allyl ethyl ether		$C_5H_{10}O$	557-31-3	86.132			67.6	0.7651^{20}	1.3881^{20}	i H_2O; msc EtOH, eth; s ace
188	Allyl formate		$C_4H_6O_2$	1838-59-1	86.090			83.6	0.9460^{20}		sl H_2O; s EtOH; msc eth
189	Allyl 2-furancarboxylate	Allyl 2-furanoate	$C_8H_8O_3$	4208-49-5	152.148			207.5	1.115^{25}	1.4945^{20}	s eth, ace; sl ctc
190	Allyl glycidyl ether		$C_6H_{10}O_2$	106-92-3	114.142			154	0.9698^{20}	1.4332^{20}	
191	Allyl hexanoate		$C_9H_{16}O_2$	123-68-2	156.222			186	0.8869^{20}		
192	Allyl (hydroxymethyl)carbamate		$C_5H_9NO_3$	24935-97-5	131.130	cry (tol)	57				
193	Allyl isocyanate		C_4H_5NO	1476-23-9	83.089			88			
194	Allyl isothiocyanate		C_4H_5NS	57-06-7	99.155	liq	-80	152	1.0126^{20}	1.5306^{20}	vs bz, eth, EtOH
195	Allyl methacrylate		$C_7H_{10}O_2$	96-05-9	126.153			67^{50}, 55^{30}	0.9335^{20}	1.4360^{20}	
196	4-Allyl-2-methoxyphenol	Eugenol	$C_{10}H_{12}O_2$	97-53-0	164.201	liq	-7.5	253.2	1.0652^{20}	1.5405^{20}	i H_2O; msc EtOH, eth; s chl, HOAc, oils
197	4-Allyl-2-methoxyphenyl acetate	1,3,4-Eugenol acetate	$C_{12}H_{14}O_3$	93-28-7	206.237	pr (al)	30.5	281; 127^{6}	1.0806^{20}	1.5205^{20}	i H_2O; s EtOH; sl ctc
198	Allyl 3-methylbutanoate		$C_8H_{14}O_2$	2835-39-4	142.196			154			
199	Allylmethyldichlorosilane		$C_4H_8Cl_2Si$	1873-92-3	155.099			119.5	1.0758^{20}	1.4419^{20}	
200	2-(Allyloxy)ethanol	Ethylene glycol monoallyl ether	$C_5H_{10}O_2$	111-45-5	102.132			158.5	0.9580^{20}	1.4358^{20}	msc H_2O; vs EtOH; s bz, ctc, MeOH
201	2-Allylphenol		$C_9H_{10}O$	1745-81-9	134.174	liq	-6	220	1.0246^{15}	1.5181^{20}	vs eth
202	4-Allylphenol	Chavicol	$C_9H_{10}O$	501-92-8	134.174		15.8	238	1.0203^{15}	1.5441^{18}	vs eth, EtOH, chl
203	Allyl phenyl ether		$C_9H_{10}O$	1746-13-0	134.174			191.7	0.9811^{20}	1.5223^{20}	i H_2O; s EtOH; msc eth; sl ctc
204	Allyl propanoate	2-Propenyl propanoate	$C_6H_{10}O_2$	2408-20-0	114.142			123	0.9140^{20}	1.4105^{20}	s EtOH, eth, ace
205	*N*-Allyl-2-propen-1-amine	Diallylamine	$C_6H_{11}N$	124-02-7	97.158			111		1.4387^{20}	s EtOH, eth
206	Allyl propyl disulfide		$C_6H_{12}S_2$	2179-59-1	148.289			79^{13}		1.5219^{20}	
207	3-(Allylsulfinyl)-*L*-alanine, (*S*)	Alliin	$C_6H_{11}NO_3S$	556-27-4	177.221	nd (dil ac)	165				vs H_2O
208	Allylthiourea	Thiosinamine	$C_4H_8N_2S$	109-57-9	116.185	mcl or orth pr (w)	78		1.217^{20}	1.5936^{78}	s H_2O, EtOH; sl eth; i bz
209	Allyltrichlorosilane	Trichloro-2-propenylsilane	$C_3H_5Cl_3Si$	107-37-9	175.517		35	117.5	1.2011^{20}	1.4460^{20}	
210	Allyltriethoxysilane		$C_9H_{20}O_3Si$	2550-04-1	204.339			100^{50}, 82^{28}	0.9030^{20}	1.4072^{20}	
211	Allyltrimethylsilane		$C_6H_{14}Si$	762-72-1	114.261			85	0.7158^{25}	1.4074^{20}	i H_2O
212	Allylurea		$C_4H_8N_2O$	557-11-9	100.119	nd (al)	85				msc H_2O, EtOH; sl eth, chl; i peth



Allyl acetate



Allyl acetoacetate



Allyl acrylate



Allyl alcohol



Allylamine



N-Allylaniline



Allylbenzene



α-Allylbenzenemethanol



Allyl benzoate



Allyl butanoate



Allyl carbamate



Allylchlorodimethylsilane



Allyl chloroformate



Allyl *trans*-cinnamate


1-Allylcyclohexanol



1-Allylcyclohexene



Allylcyclopentane



Allyldiethoxymethylsilane



Allyldiethylamine



Allyldimethylamine



Allyl ethyl ether



Allyl formate



Allyl 2-furancarboxylate



Allyl glycidyl ether



Allyl hexanoate



Allyl (hydroxymethyl)carbamate



Allyl isocyanate



Allyl isothiocyanate



Allyl methacrylate



4-Allyl-2-methoxyphenol



4-Allyl-2-methoxyphenyl acetate



Allyl 3-methylbutanoate



Allylmethyldichlorosilane



2-(Allyloxy)ethanol



2-Allylphenol



4-Allylphenol



Allyl phenyl ether



Allyl propanoate



N-Allyl-2-propen-1-amine



Allyl propyl disulfide



3-(Allylsulfinyl)-*L*-alanine, (*S*)


Allylthiourea


Allyltrichlorosilane



Allyltriethoxysilane



Allyltrimethylsilane



Allylurea


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
213	Allyl vinyl ether	3-(Ethenyloxy)-1-propene	C_5H_8O	3917-15-5	84.117			66	0.7900^{20}	1.4062^{20}	i H_2O; s eth, ace, chl
214	Aloin A		$C_{21}H_{22}O_9$	1415-73-2	418.395		149.3				s H_2O, EtOH, ace; sl eth, bz; i chl
215	Alphaprodine		$C_{16}H_{23}NO_2$	15867-21-7	261.360	cry	103				
216	Alstonidine		$C_{22}H_{24}N_2O_4$	25394-75-6	380.437	cry (eth)	189				vs ace, EtOH
217	Alstonine		$C_{21}H_{20}N_2O_3$	642-18-2	348.395	ye nd (ace)	207 dec				
218	*D*-Altrose		$C_6H_{12}O_6$	1990-29-0	180.155	pr (MeOH,al)	103.5				vs H_2O
219	Aluminum 2-butoxide	2-Butanol, aluminum salt	$C_{12}H_{27}AlO_3$	2269-22-9	246.322			197^{20}			
220	Aluminum distearate	Hydroxyaluminum distearate	$C_{36}H_{71}AlO_5$	300-92-5	610.928	wh pow	145				i H_2O
221	Aluminum ethanolate	Aluminum ethoxide	$C_6H_{15}AlO_3$	555-75-9	162.163	liq/wh solid	140	200^{7}			dec H_2O; sl xyl
222	Aluminum isopropoxide		$C_9H_{21}AlO_3$	555-31-7	204.243	hyg wh solid	119	135^{10}, $94^{0.5}$			reac H_2O; s EtOH, bz, peth, chl
223	Alverine	*N*-Ethyl-bis(3-phenylpropyl) amine	$C_{20}H_{27}N$	150-59-4	281.435	oil		$166^{0.3}$			
224	α-Amanitin		$C_{39}H_{54}N_{10}O_{14}S$	23109-05-9	918.970	nd	254 dec				
225	Amaranth dye		$C_{20}H_{11}N_2Na_3O_{10}S_3$	915-67-3	604.472	dk red pow					s H_2O
226	Ametryn		$C_9H_{17}N_5S$	834-12-8	227.330		88				
227	Amminetrimethylboron		$C_3H_{12}BN$	1830-95-1	72.945		73.5				
228	19-Amino-8,11,13-abietatriene		$C_{20}H_{31}N$	1446-61-3	285.467	cry	44.5				
229	2-Aminoacetamide		$C_2H_6N_2O$	598-41-4	74.081	hyg nd (chl)	67.5				vs H_2O, EtOH; sl eth, bz; s ace, chl
230	Aminoacetonitrile		$C_2H_4N_2$	540-61-4	56.066			58^{15}			vs EtOH
231	Aminoacetonitrile monohydrochloride		$C_2H_5ClN_2$	6011-14-9	92.527	hyg cry (al)	165 dec				
232	α-Aminoacetophenone hydrochloride		$C_8H_{10}ClNO$	5468-37-1	171.624		194 dec				
233	1-Aminoadamantane hydrochloride	Adamantanamine hydrochloride	$C_{10}H_{18}ClN$	665-66-7	187.710	cry (al-eth)	360 dec				vs H_2O, EtOH
234	2-Aminoadipic acid		$C_6H_{11}NO_4$	626-71-1	161.156	pl (w)	207.0				sl H_2O, EtOH, eth
235	3-Aminoalanine	2,3-Diaminopropionic acid	$C_3H_8N_2O_2$	515-94-6	104.108	hyg rosettes	110				vs H_2O
236	1-Amino-9,10-anthracenedione	1-Aminoanthraquinone	$C_{14}H_9NO_2$	82-45-1	223.227	red nd (al)	253.5	sub			vs ace, bz, EtOH, chl
237	2-Amino-9,10-anthracenedione	2-Aminoanthraquinone	$C_{14}H_9NO_2$	117-79-3	223.227	red nd (al, HOAc)	304.5	sub			i H_2O, eth; sl EtOH; s ace, bz, chl
238	4-Aminoazobenzene		$C_{12}H_{11}N_3$	60-09-3	197.235	oran mcl nd (al)	127	>360			sl H_2O, lig; s EtOH, eth, bz, chl
239	2-Aminobenzaldehyde		C_7H_7NO	529-23-7	121.137	silv lf	40.5	80^{2}			sl H_2O; vs EtOH, eth; s bz, chl; i lig
240	3-Aminobenzaldehyde		C_7H_7NO	1709-44-0	121.137	nd (AcOEt)	29				s eth, acid
241	4-Aminobenzaldehyde		C_7H_7NO	556-18-3	121.137	pl (w)	71.5				s H_2O, EtOH, eth, acid
242	2-Aminobenzamide		$C_7H_8N_2O$	88-68-6	136.151		110.5 dec				s H_2O, EtOH; sl eth, bz; vs AcOEt
243	4-Aminobenzamide		$C_7H_8N_2O$	2835-68-9	136.151	ye cry (+1/4w)	183				sl H_2O; s EtOH, eth
244	α-Aminobenzeneacetic acid, (±)	α-Phenylglycine	$C_8H_9NO_2$	2835-06-5	151.163	pl	292 dec	sub 255			s alk; sl os
245	4-Aminobenzeneacetic acid	*p*-Aminophenylacetic acid	$C_8H_9NO_2$	1197-55-3	151.163	pl (w)	200 dec				i H_2O; sl EtOH, DMSO
246	5-Amino-1,3-benzenedicarboxylic acid		$C_8H_7NO_4$	99-31-0	181.147	pr(al), pl(w)	360	sub			i H_2O; sl EtOH
247	4-Aminobenzeneethanol		$C_8H_{11}NO$	104-10-9	137.179	nd (al)	108				
248	2-Aminobenzenemethanamine		$C_7H_{10}N_2$	4403-69-4	122.167		61	269			vs EtOH
249	2-Aminobenzenemethanol		C_7H_9NO	5344-90-1	123.152		83.5	273			s H_2O, EtOH, eth, HOAc; vs bz, chl
250	4-Aminobenzenesulfonamide	Sulfanilamide	$C_6H_8N_2O_2S$	63-74-1	172.205	lf (dil al)	165.5		1.08^{25}		s H_2O, EtOH, eth, ace; sl chl, peth
251	2-Aminobenzenesulfonic acid	Orthanilic acid	$C_6H_7NO_3S$	88-21-1	173.190	pr (+ 1/2w)	>320 dec				sl H_2O; i EtOH, eth
252	3-Aminobenzenesulfonic acid	Metanilic acid	$C_6H_7NO_3S$	121-47-1	173.190	nd, pr (w +1)	dec				sl H_2O, EtOH; i eth
253	4-Aminobenzenesulfonic acid	Sulfanilic acid	$C_6H_7NO_3S$	121-57-3	173.190	orth pl or mcl (w+2)	288		1.485^{25}		sl H_2O; i EtOH, eth
254	4-Aminobenzenesulfonyl fluoride	*p*-Sulfanilyl fluoride	$C_6H_6FNO_2S$	98-62-4	175.181		68.5				



Allyl vinyl ether



Aloin A



Alphaprodine



Alstonidine



Alstonine



D-Altrose



Aluminum 2-butoxide



Aluminum distearate



Aluminum ethanolate



Aluminum isopropoxide



Alverine



α-Amanitin



Amaranth dye



Ametryn



Amminetrimethylboron



19-Amino-8,11,13-abietatriene



2-Aminoacetamide



Aminoacetonitrile



Aminoacetonitrile monohydrochloride



α-Aminoacetophenone hydrochloride



1-Aminoadamantane hydrochloride



2-Aminoadipic acid



3-Aminoalanine



1-Amino-9,10-anthracenedione



2-Amino-9,10-anthracenedione



4-Aminoazobenzene



2-Aminobenzaldehyde



3-Aminobenzaldehyde



4-Aminobenzaldehyde



2-Aminobenzamide



4-Aminobenzamide



α-Aminobenzeneacetic acid, (±)



4-Aminobenzeneacetic acid



5-Amino-1,3-benzenedicarboxylic acid



4-Aminobenzeneethanol



2-Aminobenzenemethanamine



2-Aminobenzenemethanol


4-Aminobenzenesulfonamide



2-Aminobenzenesulfonic acid



3-Aminobenzenesulfonic acid



4-Aminobenzenesulfonic acid



4-Aminobenzenesulfonyl fluoride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
255	2-Aminobenzenethiol		C_6H_7NS	137-07-5	125.192		26	234		1.4606^{20}	s EtOH, eth
256	4-Aminobenzenethiol		C_6H_7NS	1193-02-8	125.192		46	143^{17}			s H_2O, EtOH
257	2-Aminobenzonitrile		$C_7H_6N_2$	1885-29-6	118.136	ye pr (CS_2) nd (peth)	51	263			sl H_2O; vs EtOH, eth, ace, bz; i peth
258	3-Aminobenzonitrile		$C_7H_6N_2$	2237-30-1	118.136	nd (dil al or CCl_4)	54.3	289			sl H_2O; vs EtOH, eth, ace, chl
259	4-Aminobenzonitrile		$C_7H_6N_2$	873-74-5	118.136	pr or pl (w)	87.0				sl H_2O, ctc; vs EtOH, eth, ace, bz
260	4-Aminobenzophenone		$C_{13}H_{11}NO$	1137-41-3	197.232	lf (dil al)	124	246^{13}			sl H_2O, tfa; s EtOH, eth, HOAc
261	*N*-(4-Aminobenzoyl)-*L*-glutamic acid		$C_{12}H_{14}N_2O_5$	4271-30-1	266.249	cry (w)	173				
262	*N*-(4-Aminobenzoyl)glycine	*p*-Aminohippuric acid	$C_9H_{10}N_2O_3$	61-78-9	194.186	pr or nd (w)	198.5				vs ace, bz, EtOH
263	2-Aminobiphenyl		$C_{12}H_{11}N$	90-41-5	169.222	lf (dil al)	51	299			i H_2O; s EtOH, eth, bz; sl DMSO, peth
264	3-Aminobiphenyl		$C_{12}H_{11}N$	2243-47-2	169.222	nd	31.5				sl H_2O; s EtOH, eth, ace, bz
265	4-Aminobiphenyl	*p*-Biphenylamine	$C_{12}H_{11}N$	92-67-1	169.222	lf (dil al)	53.5	302			sl H_2O; s EtOH, eth, ace, chl
266	2-Amino-5-bromobenzoic acid	5-Bromoanthranilic acid	$C_7H_6BrNO_2$	5794-88-7	216.033	nd	219.5				s DMSO
267	1-Amino-4-bromo-9,10-dihydro-9,10-dioxo-2-anthracenesulfonic acid	1-Amino-4-bromoanthraquinone-2-sulfonic acid	$C_{14}H_8BrNO_5S$	116-81-4	382.187	red nd (w)					
268	*DL*-2-Aminobutanoic acid		$C_4H_9NO_2$	2835-81-6	103.120	lf (w)	304 dec	sub	1.2300^{20}		vs H_2O; sl EtOH; i eth, bz
269	*L*-2-Aminobutanoic acid		$C_4H_9NO_2$	1492-24-6	103.120	lf (dil al), cry (al)	292 dec				s H_2O; sl EtOH, eth; i bz
270	*DL*-3-Aminobutanoic acid		$C_4H_9NO_2$	2835-82-7	103.120	nd (al)	194.3				vs H_2O; i EtOH, eth, bz
271	4-Aminobutanoic acid	γ-Aminobutyric acid	$C_4H_9NO_2$	56-12-2	103.120	pr or nd (al) lf (MeOH-eth)	203 dec				vs H_2O; sl EtOH, ace; i eth, bz
272	2-Amino-1-butanol, (±)		$C_4H_{11}NO$	13054-87-0	89.136	liq	-1.0	178	0.9162^{20}	1.4489^{25}	msc H_2O, EtOH, eth; sl chl
273	4-Amino-1-butanol		$C_4H_{11}NO$	13325-10-5	89.136			205; 125^{34}	0.967^{12}	1.4625^{20}	s H_2O, EtOH; i eth
274	4-Amino-*N*-[(butylamino) carbonyl]benzenesulfonamide	Carbutamide	$C_{11}H_{17}N_3O_3S$	339-43-5	271.336		144.5				
275	Aminocarb		$C_{11}H_{16}N_2O_2$	2032-59-9	208.257	cry	94				sl H_2O, bz; s ace
276	*N*-(Aminocarbonyl)acetamide		$C_3H_6N_2O_2$	591-07-1	102.092		218	sub 180			sl H_2O, eth; s EtOH
277	[4-[(Aminocarbonyl)amino] phenyl]arsonic acid	Carbarsone	$C_7H_9AsN_2O_4$	121-59-5	260.079	nd (w)	174				sl H_2O, DMSO, EtOH; i eth, chl; s alk
278	*N*-(Aminocarbonyl)-2-bromo-2-ethylbutanamide	Carbromal	$C_7H_{13}BrN_2O_2$	77-65-6	237.094	orth (dil al)	118		1.544^{25}		sl H_2O, chl; s ace, bz
279	*N*-(Aminocarbonyl)-2-bromo-3-methylbutanamide	Bromisovalum	$C_6H_{11}BrN_2O_2$	496-67-3	223.067	nd or lf (to)	154	sub	1.56^{15}		vs ace, bz, eth, EtOH
280	[2-(Aminocarbonyl)phenoxy]acetic acid	Salicylamide *O*-acetic acid	$C_9H_9NO_4$	25395-22-6	195.172		221				s alk
281	7-Aminocephalosporanic acid		$C_{10}H_{12}N_2O_5S$	957-68-6	272.277	cry					
282	1-Amino-5-chloro-9,10-anthracenedione	1-Amino-5-chloroanthraquinone	$C_{14}H_8ClNO_2$	117-11-3	257.673		212				
283	4-Amino-6-chloro-1,3-benzenedisulfonamide	Chloraminophenamide	$C_6H_8ClN_3O_4S_2$	121-30-2	285.729		254.5				
284	5-Amino-2-chlorobenzenesulfonic acid	6-Chlorometanilic acid	$C_6H_6ClNO_3S$	88-43-7	207.635	nd (w)	280 dec				
285	2-Amino-5-chlorobenzoic acid		$C_7H_6ClNO_2$	635-21-2	171.582		211				
286	5-Amino-2-chlorobenzoic acid		$C_7H_6ClNO_2$	89-54-3	171.582		188		1.519^{15}		vs EtOH
287	2-Amino-5-chlorobenzophenone	2-Benzoyl-4-chloroaniline	$C_{13}H_{10}ClNO$	719-59-5	231.677	ye nd	100.5				vs H_2O, EtOH, peth, chl
288	2-Amino-4-chloro-5-methylbenzenesulfonic acid	2-Chloro-*p*-toluidine-5-sulfonic acid	$C_7H_8ClNO_3S$	88-51-7	221.662	short nd (w)					
289	2-Amino-4-chlorophenol	2-Hydroxy-5-chloroaniline	C_6H_6ClNO	95-85-2	143.571		140				sl DMSO
290	1-Aminocyclopentanecarboxylic acid	Cycloleucine	$C_6H_{11}NO_2$	52-52-8	129.157	cry (al-w)	330 dec				
291	7-Aminodeacetoxycephalosporanic acid		$C_8H_{10}N_2O_3S$	22252-43-3	214.241		241 dec				
292	1-Amino-1-deoxy-*D*-glucitol	Glucamine	$C_6H_{15}NO_5$	488-43-7	181.187	cry (MeOH)	127				vs H_2O, EtOH
293	2-Amino-2-deoxy-*D*-glucose	*D*-Glucosamine	$C_6H_{13}NO_5$	3416-24-8	179.171						vs H_2O



2-Aminobenzenethiol



4-Aminobenzenethiol



2-Aminobenzonitrile



3-Aminobenzonitrile



4-Aminobenzonitrile



4-Aminobenzophenone



N-(4-Aminobenzoyl)-*L*-glutamic acid



N-(4-Aminobenzoyl)glycine



2-Aminobiphenyl



3-Aminobiphenyl



4-Aminobiphenyl



2-Amino-5-bromobenzoic acid



1-Amino-4-bromo-9,10-dihydro-9,10-dioxo-2-anthracenesulfonic acid



DL-2-Aminobutanoic acid



L-2-Aminobutanoic acid



DL-3-Aminobutanoic acid



4-Aminobutanoic acid



2-Amino-1-butanol, (±)



4-Amino-1-butanol



4-Amino-*N*-[(butylamino)carbonyl]benzenesulfonamide



Aminocarb



N-(Aminocarbonyl)acetamide



[4-[(Aminocarbonyl)amino]phenyl]arsonic acid



N-(Aminocarbonyl)-2-bromo-2-ethylbutanamide



N-(Aminocarbonyl)-2-bromo-3-methylbutanamide



[2-(Aminocarbonyl)phenoxy]acetic acid



7-Aminocephalosporanic acid



1-Amino-5-chloro-9,10-anthracenedione



4-Amino-6-chloro-1,3-benzenedisulfonamide



5-Amino-2-chlorobenzenesulfonic acid



2-Amino-5-chlorobenzoic acid



5-Amino-2-chlorobenzoic acid



2-Amino-5-chlorobenzophenone



2-Amino-4-chloro-5-methylbenzenesulfonic acid


2-Amino-4-chlorophenol



1-Aminocyclopentanecarboxylic acid



7-Aminodeacetoxycephalosporanic acid



1-Amino-1-deoxy-*D*-glucitol



2-Amino-2-deoxy-*D*-glucose


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
294	1-Amino-2,4-dibromo-9,10-anthracenedione		$C_{14}H_7Br_2NO_2$	81-49-2	381.020	red nd (xyl)	226				
295	3-Amino-2,5-dichlorobenzoic acid	Chloramben	$C_7H_5Cl_2NO_2$	133-90-4	206.027		200				sl DMSO
296	2-Amino-2',5-dichlorobenzophenone		$C_{13}H_9Cl_2NO$	2958-36-3	266.122		≈80				
297	2-Amino-4,6-dichlorophenol		$C_6H_5Cl_2NO$	527-62-8	178.016	long nd (CS_2)	95.5	sub 70			
298	4-Amino-2,6-dichlorophenol		$C_6H_5Cl_2NO$	5930-28-9	178.016	nd or lf (w, bz)	168	sub			i H_2O; vs EtOH, eth; s ace; sl bz, HOAc
299	2-Amino-1,7-dihydro-7-methyl-6*H*-purin-6-one	7-Methylguanine	$C_6H_7N_5O$	578-76-7	165.153		370				
300	5-Amino-2,3-dihydro-1,4-phthalazinedione	Luminol	$C_8H_7N_3O_2$	521-31-3	177.161	ye nd (al)	330.5				i H_2O; sl EtOH, eth; vs alk; s HOAc
301	2-Amino-1,7-dihydro-6*H*-purine-6-thione	Thioguanine	$C_5H_5N_5S$	154-42-7	167.193		>360				
302	6-Amino-1,3-dihydro-2*H*-purin-2-one	Isoguanine	$C_5H_5N_5O$	3373-53-3	151.127		>360				i H_2O
303	2-Amino-3,4-dimethylimidazo[4,5-f]quinoline	Me-IQ	$C_{12}H_{12}N_4$	77094-11-2	212.250	cry	297				
304	2-Amino-4,6-dinitrophenol	Picramic acid	$C_6H_5N_3O_5$	96-91-3	199.121	dk red nd (al) pr (chl)	169				vs bz, EtOH
305	2-Aminoethanesulfonic acid	Taurine	$C_2H_7NO_3S$	107-35-7	125.147	mcl pr (w)	328				vs H_2O
306	1-Aminoethanol	Acetaldehyde ammonia	C_2H_7NO	75-39-8	61.083	orth (eth-al)	97	dec 110			s H_2O; sl eth
307	2-(2-Aminoethoxy)ethanol	Diglycolamine	$C_4H_{11}NO_2$	929-06-6	105.136		-12.5	221	1.0572^{20}		
308	*N*-(2-Aminoethyl)acetamide		$C_4H_{10}N_2O$	1001-53-2	102.134		51				s H_2O, EtOH, bz; i eth
309	6-Amino-3-ethyl-1-allyl-2,4(1*H*,3*H*)-pyrimidinedione	Aminometradine	$C_9H_{13}N_3O_2$	642-44-4	195.218	cry (+1w, w)	143				
310	1-[(2-Aminoethyl)amino]-2-propanol	*N*-(2-Hydroxypropyl) ethylenediamine	$C_5H_{14}N_2O$	123-84-2	118.177			94^{3}	0.9837^{25}	1.4738^{20}	
311	4-(2-Aminoethyl)-1,2-benzenediol, hydrochloride	Dopamine hydrochloride	$C_8H_{12}ClNO_2$	62-31-7	189.640	nd (w)	241 dec				vs H_2O, MeOH
312	α-(1-Aminoethyl) benzenemethanol, [*S*-(*R**,*R**)]-		$C_9H_{13}NO$	492-39-7	151.205	pl(MeOH)	77.5				vs eth, EtOH, chl
313	α-(1-Aminoethyl) benzenemethanol, hydrochloride		$C_9H_{14}ClNO$	53631-70-2	187.666		198.5				s H_2O
314	*N*-(2-Aminoethyl)ethanolamine		$C_4H_{12}N_2O$	111-41-1	104.150			239; 105^{10}	1.0286^{20}	1.4863^{20}	msc H_2O, EtOH; s ace; sl bz, lig
315	4-(2-Aminoethyl)phenol	Tyramine	$C_8H_{11}NO$	51-67-2	137.179	pl or nd (bz, w), cry (al)	164.5	206^{25}			sl H_2O, bz, DMSO; s EtOH, xyl; i tol
316	*N*-(2-Aminoethyl)-1,3-propanediamine	*N*-(3-Aminopropyl) ethylenediamine	$C_5H_{15}N_3$	13531-52-7	117.193			87^{3}		1.4805^{25}	
317	2-Amino-2-ethyl-1,3-propanediol		$C_5H_{13}NO_2$	115-70-8	119.163		37.5	152^{10}	1.099^{20}	1.490^{20}	msc H_2O
318	*L*-2-Aminohexanedioic acid	2-Aminoadipic acid	$C_6H_{11}NO_4$	542-32-5	161.156	cry (EtOH, w)	205 dec				sl H_2O, EtOH, eth
319	6-Aminohexanenitrile	5-Cyano-1-pentylamine	$C_6H_{12}N_2$	2432-74-8	112.172	liq		118^{16}			
320	6-Aminohexanoic acid	ε-Aminocaproic acid	$C_6H_{13}NO_2$	60-32-2	131.173	lf (eth)	205				vs H_2O; i EtOH; sl MeOH
321	6-Amino-1-hexanol		$C_6H_{15}NO$	4048-33-3	117.189		57	137^{30}			
322	1-Amino-4-hydroxy-9,10-anthracenedione		$C_{14}H_9NO_3$	116-85-8	239.226		216.5				s EtOH, ace
323	3-Amino-4-hydroxybenzenesulfonic acid		$C_6H_7NO_4S$	98-37-3	189.190	orth (w+1)	>300				sl H_2O; i EtOH, eth
324	4-Amino-2-hydroxybenzohydrazide	*p*-Aminosalicylic acid hydrazide	$C_7H_9N_3O_2$	6946-29-8	167.165	nd (al)	195				vs EtOH
325	2-Amino-3-hydroxybenzoic acid		$C_7H_7NO_3$	548-93-6	153.136	lf (w)	253.5				sl H_2O; s EtOH, eth, chl
326	4-Amino-2-hydroxybenzoic acid	*p*-Aminosalicylic acid	$C_7H_7NO_3$	65-49-6	153.136	nd, pl (al-eth)	150 dec				s H_2O, EtOH, eth, ace; i bz, peth, chl
327	5-Amino-2-hydroxybenzoic acid	Mesalamine	$C_7H_7NO_3$	89-57-6	153.136		283				sl H_2O; i EtOH
328	3-Amino-4-hydroxybutanoic acid	γ-Hydroxy-β-aminobutyric acid	$C_4H_9NO_3$	589-44-6	119.119	pr	216				vs H_2O; sl EtOH, chl, eth, AcOEt
329	4-Amino-3-hydroxybutanoic acid, (±)		$C_4H_9NO_3$	924-49-2	119.119	pr (w), cry (dil al)	218				vs H_2O
330	4-(2-Amino-1-hydroxyethyl)-1,2-benzenediol, (±)		$C_8H_{11}NO_3$	138-65-8	169.178		189 dec				
331	1-Amino-4-hydroxy-2-methoxy-9,10-anthracenedione		$C_{15}H_{11}NO_4$	2379-90-0	269.253						sl chl
332	4-Amino-5-(hydroxymethyl)-2(1*H*)-pyrimidinone	5-Hydroxymethylcytosine	$C_5H_7N_3O_2$	1123-95-1	141.129		>300 dec				



1-Amino-2,4-dibromo-9,10-anthracenedione



3-Amino-2,5-dichlorobenzoic acid



2-Amino-2',5-dichlorobenzophenone



2-Amino-4,6-dichlorophenol



4-Amino-2,6-dichlorophenol



2-Amino-1,7-dihydro-7-methyl-6*H*-purin-6-one



5-Amino-2,3-dihydro-1,4-phthalazinedione


2-Amino-1,7-dihydro-6*H*-purine-6-thione



6-Amino-1,3-dihydro-2*H*-purin-2-one



2-Amino-3,4-dimethylimidazo[4,5-f]quinoline



2-Amino-4,6-dinitrophenol



2-Aminoethanesulfonic acid



1-Aminoethanol



2-(2-Aminoethoxy)ethanol



N-(2-Aminoethyl)acetamide



6-Amino-3-ethyl-1-allyl-2,4(1*H*,3*H*)-pyrimidinedione



1-[(2-Aminoethyl)amino]-2-propanol



4-(2-Aminoethyl)-1,2-benzenediol, hydrochloride



α-(1-Aminoethyl)benzenemethanol, [*S*-(*R**,*R**)]-



α-(1-Aminoethyl)benzenemethanol, hydrochloride



N-(2-Aminoethyl)ethanolamine



4-(2-Aminoethyl)phenol



N-(2-Aminoethyl)-1,3-propanediamine



2-Amino-2-ethyl-1,3-propanediol



L-2-Aminohexanedioic acid



6-Aminohexanenitrile



6-Aminohexanoic acid



6-Amino-1-hexanol



1-Amino-4-hydroxy-9,10-anthracenedione



3-Amino-4-hydroxybenzenesulfonic acid



4-Amino-2-hydroxybenzohydrazide



2-Amino-3-hydroxybenzoic acid



4-Amino-2-hydroxybenzoic acid



5-Amino-2-hydroxybenzoic acid


3-Amino-4-hydroxybutanoic acid



4-Amino-3-hydroxybutanoic acid, (±)



4-(2-Amino-1-hydroxyethyl)-1,2-benzenediol, (±)



1-Amino-4-hydroxy-2-methoxy-9,10-anthracenedione



4-Amino-5-(hydroxymethyl)-2(1*H*)-pyrimidinone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
333	4-Amino-5-hydroxy-2,7-naphthalenedisulfonic acid	1-Naphthol-8-amino-3,6-disulfonic acid	$C_{10}H_9NO_7S_2$	90-20-0	319.311						sl H_2O, EtOH, eth
334	4-Amino-3-hydroxy-1-naphthalenesulfonic acid	1-Amino-2-naphthol-4-sulfonic acid	$C_{10}H_9NO_4S$	116-63-2	239.248	gray nd					i H_2O, EtOH, bz; s alk
335	2-Amino-4-hydroxypteridine		$C_6H_5N_5O$	2236-60-4	163.137	ye cry	>360				
336	5-Amino-1*H*-imidazole-4-carboxamide		$C_4H_6N_4O$	360-97-4	126.117	cry (EtOH)	170				
337	*O*-[(Aminoiminomethyl)amino]-*L*-homoserine	Canavanine	$C_5H_{12}N_4O_3$	543-38-4	176.174	cry (al)					vs H_2O
338	(Aminoiminomethyl)urea		$C_2H_6N_4O$	141-83-3	102.095	pr	105	dec 160			s H_2O, py; sl EtOH; i eth, bz, chl, CS_2
339	2-Amino-5-iodobenzoic acid		$C_7H_6INO_2$	5326-47-6	263.033		220 dec				sl H_2O, tfa; vs EtOH, eth, ace; s bz
340	4-Amino-1*H*-isoindole-1,3(2*H*)-dione		$C_8H_6N_2O_2$	2518-24-3	162.146		269.5				
341	4-Amino-3-isoxazolidinone, (*R*)	Cycloserine	$C_3H_6N_2O_2$	68-41-7	102.092		155 dec				s H_2O; sl MeOH
342	1-Amino-2-methyl-9,10-anthracenedione	1-Amino-2-methylanthraquinone	$C_{15}H_{11}NO_2$	82-28-0	237.254		205.5				i H_2O; s EtOH, bz, chl; sl eth
343	α-(Aminomethyl) benzenemethanol	Phenylethanolamine	$C_8H_{11}NO$	7568-93-6	137.179		56.5	160^{17}			vs H_2O; s EtOH
344	β-(Aminomethyl) benzenepropanoic acid	4-Amino-3-phenylbutyric acid	$C_{10}H_{13}NO_2$	1078-21-3	179.216		252 dec				
345	2-Amino-5-methylbenzenesulfonic acid		$C_7H_9NO_3S$	88-44-8	187.216	lt ye nd	132 dec				vs H_2O
346	*trans*-4-(Aminomethyl) cyclohexanecarboxylic acid	Tranexamic acid	$C_8H_{15}NO_2$	1197-18-8	157.211		>300				vs H_2O
347	4-Amino-4-methyl-2-pentanone	Diacetonamine	$C_6H_{13}NO$	625-04-7	115.173			$25^{0.14}$			s H_2O; msc EtOH, eth
348	2-Amino-4-methylphenol		C_7H_9NO	95-84-1	123.152	cry (w), orth (bz), lf or nd	136	sub			sl H_2O, bz; s EtOH, eth, chl; i lig
349	4-Amino-2-methylphenol		C_7H_9NO	2835-96-3	123.152	nd or lf (bz)	176.5	sub			sl H_2O, bz; s EtOH, eth
350	4-Amino-3-methylphenol		C_7H_9NO	2835-99-6	123.152	pr (dil al) cry (bz)	179				sl H_2O; vs EtOH, eth; s DMSO
351	(Aminomethyl)phosphonic acid		CH_6NO_3P	1066-51-9	111.038	cry	309				
352	2-Amino-2-methyl-1,3-propanediol		$C_4H_{11}NO_2$	115-69-5	105.136		110	151^{10}			vs H_2O; s EtOH
353	*L*-3-Amino-2-methylpropanoic acid		$C_4H_9NO_2$	144-90-1	103.120	cry (w)	182				
354	2-Amino-2-methyl-1-propanol	2-Aminoisobutanol	$C_4H_{11}NO$	124-68-5	89.136		25.5	165.5	0.934^{20}	1.449^{20}	msc H_2O; s ctc
355	4-Amino-5-methyl-2(1*H*)-pyrimidinone	5-Methylcytosine	$C_5H_7N_3O$	554-01-8	125.129	pr (w+1/2)	270 dec				s H_2O, acid; sl EtOH; i eth
356	3-(Aminomethyl)-3,5,5-trimethylcyclohexanol	1-Hydroxy-3-aminomethyl-3,5,5-trimethylcyclohexane	$C_{10}H_{21}NO$	15647-11-7	171.280		45.5	265	0.969^{25}	1.4904^{20}	
357	3-Amino-2-naphthalenecarboxylic acid	3-Amino-2-naphthoic acid	$C_{11}H_9NO_2$	5959-52-4	187.195	ye lf (dil al)	216.5				s EtOH, eth
358	2-Amino-1,4-naphthalenedione		$C_{10}H_7NO_2$	2348-81-4	173.169		207				i H_2O, alk; s EtOH, eth, HOAc
359	7-Amino-1,3-naphthalenedisulfonic acid	Amido-G-Acid	$C_{10}H_9NO_6S_2$	86-65-7	303.311	mcl pr or nd (w+4)	274				vs H_2O, EtOH
360	2-Amino-1,5-naphthalenedisulfonic acid	2-Naphthylamine-1,5-disulfonic acid	$C_{10}H_9NO_6S_2$	117-62-4	303.311		>300				
361	4-Amino-1,6-naphthalenedisulfonic acid	1-Naphthylamine-4,7-disulfonic acid	$C_{10}H_9NO_6S_2$	85-75-6	303.311						vs H_2O
362	4-Amino-1,7-naphthalenedisulfonic acid	1-Naphthylamine-4,6-disulfonic acid	$C_{10}H_9NO_6S_2$	85-74-5	303.311						vs H_2O, EtOH
363	2-Amino-1-naphthalenesulfonic acid	2-Naphthylamine-1-sulfonic acid	$C_{10}H_9NO_3S$	81-16-3	223.248	sc(hot w)					s DMSO
364	4-Amino-1-naphthalenesulfonic acid	1-Naphthylamine-4-sulfonic acid	$C_{10}H_9NO_3S$	84-86-6	223.248	wh nd (w+1/2) red-br cry	dec		1.6703^{25}		i H_2O; sl EtOH; s MeOH, py
365	5-Amino-1-naphthalenesulfonic acid	1-Naphthylamine-5-sulfonic acid	$C_{10}H_9NO_3S$	84-89-9	223.248	wh cry					s H_2O; i eth
366	6-Amino-1-naphthalenesulfonic acid	2-Naphthylamine-5-sulfonic acid	$C_{10}H_9NO_3S$	81-05-0	223.248	nd(w)					i H_2O, EtOH, eth
367	7-Amino-1-naphthalenesulfonic acid	Badische acid	$C_{10}H_9NO_3S$	86-60-2	223.248	nd (w+1), pl (aq ace)					vs HOAc
368	8-Amino-1-naphthalenesulfonic acid	1-Naphthylamine-8-sulfonic acid	$C_{10}H_9NO_3S$	82-75-7	223.248	nd					vs gl HOAc
369	6-Amino-2-naphthalenesulfonic acid	Bronner acid	$C_{10}H_9NO_3S$	93-00-5	223.248	lf					i cold H_2O; sl hot H_2O



4-Amino-5-hydroxy-2,7-naphthalenedisulfonic acid



4-Amino-3-hydroxy-1-naphthalenesulfonic acid



2-Amino-4-hydroxypteridine



5-Amino-1*H*-imidazole-4-carboxamide



O-[(Aminoiminomethyl)amino]-*L*-homoserine



(Aminoiminomethyl)urea



2-Amino-5-iodobenzoic acid



4-Amino-1*H*-isoindole-1,3(2*H*)-dione



4-Amino-3-isoxazolidinone, (*R*)



1-Amino-2-methyl-9,10-anthracenedione



α-(Aminomethyl)benzenemethanol



β-(Aminomethyl)benzenepropanoic acid



2-Amino-5-methylbenzenesulfonic acid



trans-4-(Aminomethyl)cyclohexanecarboxylic acid



4-Amino-4-methyl-2-pentanone



2-Amino-4-methylphenol



4-Amino-2-methylphenol



4-Amino-3-methylphenol



(Aminomethyl)phosphonic acid



2-Amino-2-methyl-1,3-propanediol



L-3-Amino-2-methylpropanoic acid



2-Amino-2-methyl-1-propanol



4-Amino-5-methyl-2(1*H*)-pyrimidinone



3-(Aminomethyl)-3,5,5-trimethylcyclohexanol



3-Amino-2-naphthalenecarboxylic acid



2-Amino-1,4-naphthalenedione



7-Amino-1,3-naphthalenedisulfonic acid



2-Amino-1,5-naphthalenedisulfonic acid



4-Amino-1,6-naphthalenedisulfonic acid



4-Amino-1,7-naphthalenedisulfonic acid



2-Amino-1-naphthalenesulfonic acid



4-Amino-1-naphthalenesulfonic acid


5-Amino-1-naphthalenesulfonic acid



6-Amino-1-naphthalenesulfonic acid



7-Amino-1-naphthalenesulfonic acid



8-Amino-1-naphthalenesulfonic acid



6-Amino-2-naphthalenesulfonic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
370	8-Amino-2-naphthalenesulfonic acid	1,7-Cleve's acid	$C_{10}H_9NO_3S$	119-28-8	223.248	nd or pr (w)					sl EtOH; s eth
371	5-Amino-1-naphthol	1-Amino-6-hydroxynaphthalene	$C_{10}H_9NO$	83-55-6	159.184		170				sl DMSO
372	1-Amino-2-naphthol		$C_{10}H_9NO$	2834-92-6	159.184	silvery lf (bz, eth)	150 dec				sl H_2O, eth; s EtOH; vs dil alk, acid
373	8-Amino-2-naphthol	8-Amino-β-naphthol	$C_{10}H_9NO$	118-46-7	159.184	nd (w, al)	206	sub			s H_2O, eth; vs EtOH; sl bz, lig
374	2-Amino-4-nitrobenzoic acid		$C_7H_6N_2O_4$	619-17-0	182.134	oran pr (dil al)	269				i H_2O; vs EtOH, eth, ace; s xyl
375	2-Amino-5-nitrobenzoic acid		$C_7H_6N_2O_4$	616-79-5	182.134	lf (al), ye nd (w, dil al)	269				i H_2O, bz, chl, xyl; s EtOH, eth
376	2-Amino-5-nitrobenzonitrile		$C_7H_5N_3O_2$	17420-30-3	163.134		203.5				sl DMSO
377	3-Amino-1-nitroguanidine		$CH_5N_5O_2$	18264-75-0	119.084		187.8				sl H_2O
378	2-Amino-4-nitrophenol		$C_6H_6N_2O_3$	99-57-0	154.123	oran pr (+w)	146				sl H_2O, ace; vs EtOH; s eth, bz, HOAc
379	2-Amino-5-nitrophenol		$C_6H_6N_2O_3$	121-88-0	154.123		205.8				s H_2O, EtOH, bz
380	4-Amino-2-nitrophenol		$C_6H_6N_2O_3$	119-34-6	154.123	dk red pl or nd (w, al)	131	110^{12}			s H_2O, EtOH, eth; sl DMSO
381	2-Aminooctanoic acid, (±)		$C_8H_{17}NO_2$	644-90-6	159.227	lf (w)	270	sub			sl H_2O, EtOH, eth, bz; s HOAc
382	Aminooxoacetohydrazide	Semioxamazide	$C_2H_5N_3O_2$	515-96-8	103.080		221 dec				sl H_2O; i EtOH, eth; vs alk, acid
383	*cis*-4-Amino-4-oxo-2-butenoic acid	Maleamic acid	$C_4H_5NO_3$	557-24-4	115.088	cry (al)	172.5				vs H_2O, EtOH
384	5-Amino-4-oxopentanoic acid	5-Aminolevulinic acid	$C_5H_9NO_3$	106-60-5	131.130	cry (EtOH)	118				
385	(Aminooxy)acetic acid, hydrochloride (2:1)		$C_4H_{11}ClN_2O_6$	2921-14-4	218.592		152.5				
386	6-Aminopenicillanic acid	Penicin	$C_8H_{12}N_2O_3S$	551-16-6	216.257	cry (w)	208				
387	5-Aminopentanoic acid		$C_5H_{11}NO_2$	660-88-8	117.147	lf (dil al)	157 dec	dec			s H_2O; sl EtOH; i eth, bz, lig
388	5-Amino-1-pentanol		$C_5H_{13}NO$	2508-29-4	103.163		38.5	221.5	0.9488^{17}	1.4618^{17}	msc H_2O, EtOH, ace
389	2-Aminophenol		C_6H_7NO	95-55-6	109.126	wh orth bipym nd (bz)	174	sub 153	1.328^{25}		s H_2O, eth; vs EtOH; sl bz, tfa
390	3-Aminophenol		C_6H_7NO	591-27-5	109.126	pr (to)	123	164^{11}			s H_2O, tol; vs EtOH, eth; sl bz, DMSO
391	4-Aminophenol		C_6H_7NO	123-30-8	109.126	wh pl (w)	187.5	$110^{0.3}$			sl H_2O, tfa; vs EtOH; i bz, chl; s alk
392	*N*-(3-Aminophenyl)acetamide		$C_8H_{10}N_2O$	102-28-3	150.177	nd or pl (bz)	88				vs H_2O, EtOH, ace; sl eth, bz
393	*N*-(4-Aminophenyl)acetamide	*p*-Aminoacetanilide	$C_8H_{10}N_2O$	122-80-5	150.177	nd (w)	166.5	267			s H_2O; vs EtOH, eth
394	(4-Aminophenyl)arsonic acid	Arsanilic acid	$C_6H_8AsNO_3$	98-50-0	217.055	mcl nd (w, al)	232		1.9571^{10}		s H_2O, eth; sl EtOH, DMSO; i ace, bz
395	*N*-(4-Aminophenyl)-1,4-benzenediamine	4,4'-Diaminodiphenylamine	$C_{12}H_{13}N_3$	537-65-5	199.251	lf (w)	158	dec			vs eth, EtOH
396	2-Amino-1-phenylethanone	Phenacylamine	C_8H_9NO	613-89-8	135.163	ye cry	20	251		1.6160^{20}	i H_2O; s eth; sl ctc
397	1-(3-Aminophenyl)ethanone	*m*-Aminoacetophenone	C_8H_9NO	99-03-6	135.163	pa ye pl (al), lf (eth)	98.5	289.5			sl H_2O; s EtOH
398	1-(4-Aminophenyl)ethanone	*p*-Aminoacetophenone	C_8H_9NO	99-92-3	135.163	ye mcl pr (al)	106	294; 195^{15}			vs eth, EtOH
399	1-(4-Aminophenyl)-1-pentanone		$C_{11}H_{15}NO$	38237-74-0	177.243	cry (bz-peth)	74.5	161^{3}			i H_2O; s EtOH, eth
400	1-(4-Aminophenyl)-1-propanone	*p*-Aminopropiophenone	$C_9H_{11}NO$	70-69-9	149.189	pl (al, w), nd (w)	140				s DMSO
401	*N*-[(4-Aminophenyl)sulfonyl] acetamide	Sulfacetamide	$C_8H_{10}N_2O_3S$	144-80-9	214.241		183				sl H_2O; s EtOH; i eth; vs ace, alk
402	5-[(4-Aminophenyl)sulfonyl]-2-thiazolamine	Thiazolsulfone	$C_9H_9N_3O_2S_2$	473-30-3	255.316	nd (al)	220 dec				vs ace, eth, EtOH, diox
403	4-Aminophthalimide	5-Amino-1*H*-isoindole-1,3(2*H*)-dione	$C_8H_6N_2O_2$	3676-85-5	162.146			$224^{0.5}$			
404	3-Amino-1,2-propanediol, (±)		$C_3H_9NO_2$	13552-31-3	91.109			dec 265; 145^{9}	1.1752^{20}	1.4910^{25}	s H_2O, EtOH; i eth, bz
405	3-Aminopropanenitrile	3-Aminopropionitrile	$C_3H_6N_2$	151-18-8	70.093			185; 88^{20}	0.9584^{20}	1.4396^{20}	
406	2-Amino-1-propanol, (±)		C_3H_9NO	6168-72-5	75.109			174.5		1.4502^{20}	vs H_2O, EtOH, eth; sl chl



8-Amino-2-naphthalenesulfonic acid



5-Amino-1-naphthol



1-Amino-2-naphthol



8-Amino-2-naphthol



2-Amino-4-nitrobenzoic acid



2-Amino-5-nitrobenzoic acid



2-Amino-5-nitrobenzonitrile



3-Amino-1-nitroguanidine



2-Amino-4-nitrophenol



2-Amino-5-nitrophenol



4-Amino-2-nitrophenol



2-Aminooctanoic acid, (±)



Aminooxoacetohydrazide



cis-4-Amino-4-oxo-2-butenoic acid



5-Amino-4-oxopentanoic acid



(Aminooxy)acetic acid, hydrochloride (2:1)



6-Aminopenicillanic acid



5-Aminopentanoic acid



5-Amino-1-pentanol



2-Aminophenol



3-Aminophenol



4-Aminophenol



N-(3-Aminophenyl)acetamide



N-(4-Aminophenyl)acetamide



(4-Aminophenyl)arsonic acid



N-(4-Aminophenyl)-1,4-benzenediamine



2-Amino-1-phenylethanone



1-(3-Aminophenyl)ethanone



1-(4-Aminophenyl)ethanone



1-(4-Aminophenyl)-1-pentanone



1-(4-Aminophenyl)-1-propanone



N-[(4-Aminophenyl)sulfonyl]acetamide


5-[(4-Aminophenyl)sulfonyl]-2-thiazolamine



4-Aminophthalimide



3-Amino-1,2-propanediol, (±)



3-Aminopropanenitrile



2-Amino-1-propanol, (±)


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
407	3-Amino-1-propanol	Propanolamine	C_3H_9NO	156-87-6	75.109		12.4	187.5	0.9824^{25}	1.4617^{20}	s H_2O, EtOH, eth
408	1-Amino-2-propanol	Isopropanolamine	C_3H_9NO	1674-56-2	75.109		0.9	159.4	0.9611^{20}	1.4479^{20}	msc H_2O, EtOH, eth, ace, bz, ctc
409	α-(1-Aminopropyl) benzenemethanol	α-(α-Aminopropyl)benzyl alcohol	$C_{10}H_{15}NO$	5897-76-7	165.232	pl (bz-eth)	79.5				
410	*N*-(3-Aminopropyl)-*N*-methyl-1,3-propanediamine		$C_7H_{19}N_3$	105-83-9	145.246			232.5; 112^6	0.9023^{20}	1.4705^{25}	
411	Aminopropylon		$C_{16}H_{22}N_4O_2$	3690-04-8	302.372	pr (bz)	181				vs H_2O
412	4-(2-Aminopropyl)phenol, (±)	Hydroxyamphetamine	$C_9H_{13}NO$	1518-86-1	151.205	cry (bz)	125.5				s H_2O, EtOH, bz, chl, AcOEt
413	*N*-(3-Aminopropyl)-1,3-propanediamine	Bis(3-aminopropyl)amine	$C_6H_{17}N_3$	56-18-8	131.219		-14	151^{50}	0.938^{25}	1.4810^{20}	s chl
414	Aminopterin		$C_{19}H_{20}N_8O_5$	54-62-6	440.413	ye cry	262 dec				
415	4-Amino-*N*-pyrazinylbenzenesulfonamide	Sulfapyrazine	$C_{10}H_{10}N_4O_2S$	116-44-9	250.277	nd ($PhNO_2$)	251				i H_2O, EtOH, eth, bz, chl; s py; sl ace
416	3-Amino-1*H*-pyrazole-4-carbonitrile	3-Amino-4-cyanopyrazole	$C_4H_4N_4$	16617-46-2	108.102	cry (w)	173				
417	2-Amino-3-pyridinecarboxylic acid		$C_6H_6N_2O_2$	5345-47-1	138.124		296 dec				sl H_2O
418	6-Amino-3-pyridinecarboxylic acid	6-Aminonicotinic acid	$C_6H_6N_2O_2$	3167-49-5	138.124	cry (dil HOAc, +2w)	312				
419	4-Amino-*N*-2-pyridinylbenzenesulfonamide	Sulfapyridine	$C_{11}H_{11}N_3O_2S$	144-83-2	249.289	ye oran (al)	192				i H_2O, bz, ctc; s EtOH
420	5-Amino-2,4(1*H*,3*H*)-pyrimidinedione	5-Aminouracil	$C_4H_5N_3O_2$	932-52-5	127.102	nd (w)	dec				i H_2O; s alk, acid
421	6-Amino-2,4(1*H*,3*H*)-pyrimidinedione		$C_4H_5N_3O_2$	873-83-6	127.102	cry (w)	dec				vs H_2O
422	4-Amino-2(1*H*)-pyrimidinethione	2-Thiocytosine	$C_4H_5N_3S$	333-49-3	127.168						sl DMSO
423	5-Amino-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	Uramil	$C_4H_5N_3O_3$	118-78-5	143.101	nd or pl (w)	>400				s H_2O, chl; i eth, bz
424	4-Amino-*N*-2-pyrimidinylbenzenesulfonamide	Sulfadiazine	$C_{10}H_{10}N_4O_2S$	68-35-9	250.277	cry (w), wh pow	255 dec				sl H_2O, EtOH, ace, DMSO
425	Aminopyrine		$C_{13}H_{17}N_3O$	58-15-1	231.293	pr or pl (lig or AcOEt)	134.5				vs H_2O, bz, EtOH
426	4-Amino-*N*-2-quinoxalinylbenzenesulfonamide	Sulfaquinoxaline	$C_{14}H_{12}N_4O_2S$	59-40-5	300.336		247.5				sl H_2O, EtOH, ace; s aq alk
427	4-(Aminosulfonyl)benzoic acid	Carzenide	$C_7H_7NO_4S$	138-41-0	201.201	pr or lf (w)	291 dec				i H_2O; vs EtOH; sl eth; i bz
428	*N*-[4-(Aminosulfonyl)phenyl] acetamide	Acetylsulfanilamide	$C_8H_{10}N_2O_3S$	121-61-9	214.241	nd (HOAc)	219.5				s H_2O, EtOH, ace
429	5-Amino-1,3,4-thiadiazole-2(3*H*)-thione		$C_2H_3N_3S_2$	2349-67-9	133.195		243.0				
430	2-Amino-4(5*H*)-thiazolone		$C_3H_4N_2OS$	556-90-1	116.141	pr or nd (w)	256 dec				sl H_2O; i EtOH, eth
431	*N*-(Aminothioxomethyl)acetamide	Acetylthiourea	$C_3H_6N_2OS$	591-08-2	118.157	pr (w), orth (al)	165				sl H_2O, eth; s DMSO, EtOH
432	*N*-Amino-2-thioxo-4-thiazolidinone	3-Aminorhodanine	$C_3H_4N_2OS_2$	1438-16-0	148.206		101.5				s DMSO
433	1-Amino-2,2,2-trichloroethanol	Chloral ammonia	$C_2H_4Cl_3NO$	507-47-1	164.418	nd (al)	73	dec 100			vs bz, eth, EtOH
434	4-Amino-3,5,6-trichloro-2-pyridinecarboxlic acid	Picloram	$C_6H_3Cl_3N_2O_2$	1918-02-1	241.459		218.5				
435	11-Aminoundecanoic acid		$C_{11}H_{23}NO_2$	2432-99-7	201.307		189.0				
436	Amiton		$C_{10}H_{24}NO_3PS$	78-53-5	269.342	liq		$76^{0.01}$		1.4655^{27}	
437	Amitraz	*N*-Methylbis(2,4-xylyliminomethyl)amine	$C_{19}H_{23}N_3$	33089-61-1	293.406		86		1.128^{20}		
438	Amitriptyline		$C_{20}H_{23}N$	50-48-6	277.404	cry	196 (HCl)				
439	Ammonium ferric oxalate		$C_6H_{12}FeN_3O_{12}$	14221-47-7	374.017		165 dec		$1.78^{17.5}$		vs H_2O; i EtOH
440	Ammonium perfluorooctanoate		$C_8H_4F_{15}NO_2$	3825-26-1	431.100	solid					
441	Ammonium propanoate		$C_3H_9NO_2$	17496-08-1	91.109	hyg cry	45				s H_2O
442	Amobarbital	5-Ethyl-5-isopentyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	$C_{11}H_{18}N_2O_3$	57-43-2	226.272		157				vs bz, EtOH, chl
443	Amolanone	3-[2-(Diethylamino)ethyl]-3-phenyl-2(3*H*)-benzofuranone	$C_{20}H_{23}NO_2$	76-65-3	309.403	cry (peth)	43.4	$193^{2.0}$		1.5614^{25}	
444	Amoxicillin		$C_{16}H_{19}N_3O_5S$	26787-78-0	365.404	cry (w)					s H_2O
445	Amphecloral		$C_{11}H_{12}Cl_3N$	5581-35-1	264.579			$96.^{0.5}$		1.530	
446	Amphotericin B		$C_{47}H_{73}NO_{17}$	1397-89-3	924.080	ye pr (DMF)	170 dec				i H_2O; sl DMF; s DMSO
447	Ampicillin		$C_{16}H_{19}N_3O_4S$	69-53-4	349.405	cry	200 dec				sl H_2O
448	Ampyrone		$C_{11}H_{13}N_3O$	83-07-8	203.240	pa ye cry (bz)	109				s H_2O, EtOH, bz, chl; sl eth



3-Amino-1-propanol



1-Amino-2-propanol



α-(1-Aminopropyl)benzenemethanol



N-(3-Aminopropyl)-*N*-methyl-1,3-propanediamine



Aminopropylon



4-(2-Aminopropyl)phenol, (±)



N-(3-Aminopropyl)-1,3-propanediamine



Aminopterin



4-Amino-*N*-pyrazinylbenzenesulfonamide



3-Amino-1*H*-pyrazole-4-carbonitrile



2-Amino-3-pyridinecarboxylic acid



6-Amino-3-pyridinecarboxylic acid



4-Amino-*N*-2-pyridinylbenzenesulfonamide



5-Amino-2,4(1*H*,3*H*)-pyrimidinedione



6-Amino-2,4(1*H*,3*H*)-pyrimidinedione



4-Amino-2(1*H*)-pyrimidinethione



5-Amino-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione



4-Amino-*N*-2-pyrimidinylbenzenesulfonamide



Aminopyrine



4-Amino-*N*-2-quinoxalinylbenzenesulfonamide



4-(Aminosulfonyl)benzoic acid



N-[4-(Aminosulfonyl)phenyl]acetamide



5-Amino-1,3,4-thiadiazole-2(3*H*)-thione



2-Amino-4(5*H*)-thiazolone



N-(Aminothioxomethyl)acetamide



N-Amino-2-thioxo-4-thiazolidinone



1-Amino-2,2,2-trichloroethanol



4-Amino-3,5,6-trichloro-2-pyridinecarboxlic acid



11-Aminoundecanoic acid



Amiton



Amitraz



Amitriptyline



Ammonium ferric oxalate



Ammonium perfluorooctanoate



Ammonium propanoate



Amobarbital



Amolanone


Amoxicillin



Amphecloral



Amphotericin B



Ampicillin



Ampyrone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
449	Amygdalin		$C_{20}H_{27}NO_{11}$	29883-15-6	457.428		224.5				vs H_2O; sl EtOH; i eth, chl
450	Anacardic acid		$C_{22}H_{32}O_3$	11034-77-8	344.487	cry (ace)	35.5				vs eth, EtOH, peth
451	Anagyrine		$C_{15}H_{20}N_2O$	486-89-5	244.332	pe ye glass		265^{12}, 212^{4}			s H_2O, eth, bz; vs EtOH, chl; i lig
452	Androstane		$C_{19}H_{32}$	24887-75-0	260.457	lf (ace-MeOH)	50	60$^{0.003}$			vs ace, eth, EtOH, peth
453	Androstane-17-carboxylic acid, (5β,17β)	Etiocholanic acid	$C_{20}H_{32}O_2$	438-08-4	304.467	nd (gl HOAc)	228.5	sub 160			
454	Androstane-3,17-diol, (3α,5α,17β)	Epiandrostanediol	$C_{19}H_{32}O_2$	1852-53-5	292.456	nd (ace aq)	223				
455	5α-Androstane-3,17-dione		$C_{19}H_{28}O_2$	846-46-8	288.424	cry (MeOH)	135				
456	5β-Androstane-3,17-dione		$C_{19}H_{28}O_2$	1229-12-5	288.424	cry (ace-hx)	135				
457	Androst-4-ene-3,17-dione	4-Androstene-3,17-dione	$C_{19}H_{26}O_2$	63-05-8	286.408		143(form a); 173(form b)				
458	Androst-4-ene-3,11,17-trione	Adrenosterone	$C_{19}H_{24}O_3$	382-45-6	300.392	nd (al)	222	sub			sl H_2O; s EtOH, eth, ace, chl
459	Anemonin	*trans*-1,7-Dioxadispiro[4.0.4.2] dodeca-3,9-diene-2,8-dione	$C_{10}H_8O_4$	508-44-1	192.169	orth pl (chl) nd (al or bz)	158				vs chl
460	Anhalamine		$C_{11}H_{15}NO_3$	643-60-7	209.242	nd (al)	187.5				vs eth, EtOH
461	Anhalonidine		$C_{12}H_{17}NO_3$	17627-77-9	223.268	oct cry (bz, eth)	160.5				vs H_2O, EtOH
462	Anhalonine		$C_{12}H_{15}NO_3$	519-04-0	221.252	rhom nd	86	140$^{0.02}$			vs EtOH, bz, chl, eth, peth
463	2,5-Anhydro-3,4-dideoxyhexitol	Tetrahydro-2,5-furandimethanol	$C_6H_{12}O_3$	104-80-3	132.157		<-50	265	1.154^{20}		vs H_2O, ace, bz, EtOH
464	Anilazine	2,4-Dichloro-6-(*o*-chloroanilino)-*s*-triazine	$C_9H_5Cl_3N_4$	101-05-3	275.522		160		1.8^{20}		
465	Anileridine		$C_{22}H_{28}N_2O_2$	144-14-9	352.469	cry	83				s H_2O
466	Aniline	Benzenamine	C_6H_7N	62-53-3	93.127	oily liq	-6.02	184.17	1.0217^{20}	1.5863^{20}	s H_2O, ctc, lig; msc EtOH, eth, ace, bz
467	Aniline-2-carboxylic acid	*o*-Anthranilic acid	$C_7H_7NO_2$	118-92-3	137.137	lf (al)	146.5	sub	1.412^{20}		s H_2O, EtOH, eth; sl bz, tfa; vs chl, py
468	Aniline-3-carboxylic acid	*m*-Anthranilic acid	$C_7H_7NO_2$	99-05-8	137.137		173		1.51^{25}		sl H_2O, EtOH; s eth, tfa; vs ace; i bz
469	Aniline-4-carboxylic acid	*p*-Anthranilic acid	$C_7H_7NO_2$	150-13-0	137.137	mcl pr (w)	188.2		1.374^{20}		s H_2O, EtOH, eth; sl ace; i bz, chl
470	Aniline hydrobromide		C_6H_8BrN	542-11-0	174.039		286				
471	Aniline hydrochloride	Benzenamine hydrochloride	C_6H_8ClN	142-04-1	129.588	lf or nd	198		1.2215^{4}		vs H_2O, EtOH; i eth, chl; sl DMSO
472	Aniline nitrate		$C_6H_8N_2O_3$	542-15-4	156.139	orth	190 dec		1.356^{4}		vs H_2O, eth, EtOH
473	Aniline sulfate (2:1)		$C_{12}H_{16}N_2O_4S$	542-16-5	284.331				1.377^{4}		s H_2O; sl EtOH, tfa; i eth
474	Anisole	Methoxybenzene	C_7H_8O	100-66-3	108.138	liq	-37.13	153.7	0.9940^{20}	1.5174^{20}	i H_2O; s EtOH, eth, chl; vs ace, bz
475	Anisotropine methylbromide	Octatropine methylbromide	$C_{17}H_{32}BrNO_2$	80-50-2	362.346	cry (ace)	329				
476	Antazoline		$C_{17}H_{19}N_3$	91-75-8	265.353	cry	122				
477	Anthra[9,1,2-cde]benzo[rst] pentaphene-5,10-dione		$C_{34}H_{16}O_2$	116-71-2	456.490	viol-bl or blk nd ($PhNO_2$)	492 dec				i EtOH, bz, HOAc; s xyl, py, sulf
478	2-Anthracenamine		$C_{14}H_{11}N$	613-13-8	193.244	ye lf (al)	238.8	sub			i H_2O; s EtOH; i con sulf
479	Anthracene		$C_{14}H_{10}$	120-12-7	178.229	tab or mcl pr (al)	215.76	339.9	1.28^{25}		i H_2O; sl EtOH, eth, ace, bz, chl, ctc
480	9-Anthracenecarbonitrile		$C_{15}H_9N$	1210-12-4	203.239		177.5		1.3000^{20}		
481	9-Anthracenecarboxaldehyde		$C_{15}H_{10}O$	642-31-9	206.239	oran nd (dil HOAc)	104.5				i H_2O; s bz, HOAc
482	1-Anthracenecarboxylic acid	1-Anthroic acid	$C_{15}H_{10}O_2$	607-42-1	222.239	ye nd (HOAc) ye pr (al)	251.5	sub			i H_2O; s EtOH, eth; sl bz, chl
483	2-Anthracenecarboxylic acid	2-Anthroic acid	$C_{15}H_{10}O_2$	613-08-1	222.239	ye lf (al) nd, lf (sub)	281	sub			vs HOAc
484	9-Anthracenecarboxylic acid	9-Anthroic acid	$C_{15}H_{10}O_2$	723-62-6	222.239		217 dec	sub			i H_2O; s EtOH
485	9,10-Anthracenedicarbonitrile		$C_{16}H_8N_2$	1217-45-4	228.248		337 dec				
486	9,10-Anthracenediol		$C_{14}H_{10}O_2$	4981-66-2	210.228	br or ye nd	180				vs eth, EtOH



Amygdalin



Anacardic acid



Anagyrine



Androstane



Androstane-17-carboxylic acid, (5β,17β)



Androstane-3,17-diol, (3α,5α,17β)



5α-Androstane-3,17-dione



5β-Androstane-3,17-dione



Androst-4-ene-3,17-dione



Androst-4-ene-3,11,17-trione



Anemonin



Anhalamine


Anhalonidine



Anhalonine



2,5-Anhydro-3,4-dideoxyhexitol



Anilazine



Anileridine



Aniline



Aniline-2-carboxylic acid



Aniline-3-carboxylic acid



Aniline-4-carboxylic acid



Aniline hydrobromide



Aniline hydrochloride



Aniline nitrate



Aniline sulfate (2:1)



Anisole



Anisotropine methylbromide



Antazoline



Anthra[9,1,2-cde]benzo[rst]pentaphene-5,10-dione



2-Anthracenamine



Anthracene



9-Anthracenecarbonitrile



9-Anthracenecarboxaldehyde


1-Anthracenecarboxylic acid



2-Anthracenecarboxylic acid



9-Anthracenecarboxylic acid



9,10-Anthracenedicarbonitrile



9,10-Anthracenediol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
487	9,10-Anthracenedione	Anthraquinone	$C_{14}H_8O_2$	84-65-1	208.213	ye orth nd (al, bz)	286	377	1.438^{20}		i H_2O; sl EtOH, eth, bz, chl
488	9-Anthracenemethanol		$C_{15}H_{12}O$	1468-95-7	208.255		160.5				
489	1,4,9,10-Anthracenetetrol		$C_{14}H_{10}O_4$	476-60-8	242.227		148				
490	1,2,10-Anthracenetriol	Anthrarobin	$C_{14}H_{10}O_3$	577-33-3	226.227	ye lf, nd (al-w)	208				sl H_2O; vs EtOH, eth, ace; s bz
491	1,8,9-Anthracenetriol	Anthralin	$C_{14}H_{10}O_3$	1143-38-0	226.227	ye pl or nd (lig)	179				i H_2O; s EtOH, ace, bz; sl eth; vs py
492	1-Anthracenol		$C_{14}H_{10}O$	610-50-4	194.228	cry (bz), br nd or lf (al)	158	234^{13}			i H_2O; vs EtOH, eth; s NaOH
493	9-Anthracenol	Anthranol	$C_{14}H_{10}O$	529-86-2	194.228	ye red lf (dil al)	152				
494	9(10*H*)-Anthracenone	Anthrone	$C_{14}H_{10}O$	90-44-8	194.228	nd (bz-lig, HOAc)	155				s ace, bz, con sulf, dil alk
495	Antimony potassium tartrate trihydrate	Tartar emetic	$C_8H_{10}K_2O_{15}Sb_2$	28300-74-5	667.873	col cry			2.6		sl H_2O
496	Apholate		$C_{12}H_{24}N_9P_3$	52-46-0	387.300		148				
497	Aphylline		$C_{15}H_{24}N_2O$	577-37-7	248.364	cry	52.5	200^4			vs ace, bz, eth, EtOH
498	Apigenin	5,7-Dihydroxy-2-(4-hydroxyphenyl)-4*H*-1-benzopyran-4-one	$C_{15}H_{10}O_5$	520-36-5	270.237	ye nd (aq py)	347.5				i H_2O; s EtOH, py; vs dil alk
499	Apoatropine		$C_{17}H_{21}NO_2$	500-55-0	271.355	pr (chl)	62				sl H_2O, lig; vs EtOH, eth, ace, bz
500	Apocodeine		$C_{18}H_{19}NO_2$	641-36-1	281.350	pr (MeOH)	123.5				sl EtOH; s eth, ace, bz, lig
501	Apomorphine		$C_{17}H_{17}NO_2$	58-00-4	267.323	hex pl (chl-peth) rods (eth)	195 dec				sl H_2O; s EtOH, eth, ace, bz, alk
502	Apomorphine, hydrochloride		$C_{17}H_{18}ClNO_2$	314-19-2	303.784	grn in air mcl pr	205 dec				
503	Aprobarbital	5-Isopropyl-5-allyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	$C_{10}H_{14}N_2O_3$	77-02-1	210.229	cry	141				vs ace, eth, EtOH, chl
504	*L*-Arabinitol		$C_5H_{12}O_5$	7643-75-6	152.146		102.5				vs H_2O; sl EtOH; i eth
505	α-*D*-Arabinopyranose		$C_5H_{10}O_5$	608-45-7	150.130	cry (MeOH)	155.5		1.585^{25}		
506	6-*O*-α-*L*-Arabinopyranosyl-*D*-Glucose	Vicianose	$C_{11}H_{20}O_{10}$	14116-69-9	312.271	nd (dil al)	210 dec				vs H_2O
507	*DL*-Arabinose		$C_5H_{10}O_5$	20235-19-2	150.130	pr, nd (al)	164.5		1.585^{20}		vs H_2O; sl EtOH; i eth, bz
508	α-*D*-Arabinose		$C_5H_{10}O_5$	31178-68-4	150.130		156		1.585^{25}		vs H_2O; sl EtOH; i eth, ace, MeOH
509	β-*D*-Arabinose		$C_5H_{10}O_5$	31178-69-5	150.130		156		1.625^{25}		vs H_2O; sl EtOH; i eth, ace, MeOH
510	Aramite		$C_{15}H_{23}ClO_4S$	140-57-8	334.860		-37.3	195^2	1.143^{20}	1.5100^{20}	vs ace, bz, eth, EtOH
511	Arecaidine	1,2,5,6-Tetrahydro-1-methyl-3-pyridinecarboxylic acid	$C_7H_{11}NO_2$	499-04-7	141.168	pl (dil al) tab (dil al +1w)	232 dec				vs H_2O; i EtOH, eth, bz, chl
512	Arecoline		$C_8H_{13}NO_2$	63-75-2	155.195			209	1.0485^{20}	1.486^{-20}	msc H_2O, EtOH, eth; s chl
513	*D*-Arginine		$C_6H_{14}N_4O_2$	7200-25-1	174.201		217 dec				i H_2O, EtOH, eth, bz
514	*L*-Arginine		$C_6H_{14}N_4O_2$	74-79-3	174.201		244 dec				s H_2O; sl EtOH; i eth
515	*L*-Arginine, monohydrochloride		$C_6H_{15}ClN_4O_2$	1119-34-2	210.662		219				
516	Artemisin	8-Hydroxysantonin	$C_{15}H_{18}O_4$	481-05-0	262.302	cry	203	$260^{0.1}$			sl H_2O, chl; s AcOEt; i peth
517	Ascaridole	1-Methyl-4-isopropyl-2,3-dioxabicyclo[2.2.2]oct-5-ene	$C_{10}H_{16}O_2$	512-85-6	168.233	liq	3.3	exp; 115^{15}, $39^{0.2}$	1.0103^{20}	1.4769^{20}	i H_2O; s EtOH, ace, bz, tol; sl chl
518	*L*-Ascorbic acid	Vitamin C	$C_6H_8O_6$	50-81-7	176.124		191 dec		1.65^{25}		vs H_2O; s EtOH; i eth, bz, chl, peth
519	Ascorbyl palmitate	6-Hexadecanoylascorbic acid	$C_{22}H_{38}O_7$	137-66-6	414.533		112				
520	*L*-Asparagine	α-Aminosuccinamic acid	$C_4H_8N_2O_3$	70-47-3	132.118	orth (w+1)	235		1.543^{15}		s H_2O; i EtOH, eth, MeOH
521	*D*-Asparagine, monohydrate		$C_4H_{10}N_2O_4$	5794-24-1	150.133		215		1.523^{15}		sl H_2O; i EtOH, eth, bz, MeOH
522	*L*-Asparagine, monohydrate		$C_4H_{10}N_2O_4$	5794-13-8	150.133		234		1.543^{15}		sl H_2O; i EtOH, eth, bz, MeOH



9,10-Anthracenedione



9-Anthracenemethanol



1,4,9,10-Anthracenetetrol



1,2,10-Anthracenetriol



1,8,9-Anthracenetriol



1-Anthracenol



9-Anthracenol



9(10*H*)-Anthracenone



Antimony potassium tartrate trihydrate



Apholate



Aphylline



Apigenin



Apoatropine



Apocodeine



Apomorphine



Apomorphine, hydrochloride



Aprobarbital



L-Arabinitol



α-*D*-Arabinopyranose



6-*O*-α-*L*-Arabinopyranosyl-*D*-Glucose



DL-Arabinose



α-*D*-Arabinose



β-*D*-Arabinose



Aramite



Arecaidine



Arecoline



D-Arginine



L-Arginine



L-Arginine, monohydrochloride



Artemisin



Ascaridole


L-Ascorbic acid



Ascorbyl palmitate



L-Asparagine



D-Asparagine, monohydrate



L-Asparagine, monohydrate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
523	Aspartame	*L*-α-Aspartyl-*L*-phenylalanine, 2-methyl ester	$C_{14}H_{18}N_2O_5$	22839-47-0	294.303	nd (w)	246.5				
524	*DL*-Aspartic acid		$C_4H_7NO_4$	617-45-8	133.104	mcl pr (w)	277.5		1.6622^{13}		sl H_2O; i EtOH, eth, bz, py
525	*L*-Aspartic acid	*L*-Aminosuccinic acid	$C_4H_7NO_4$	56-84-8	133.104	orth lf (w)	270		1.6603^{13}		sl H_2O; i EtOH, eth, bz; s dil HCl, py
526	Aspergillic acid		$C_{12}H_{20}N_2O_2$	490-02-8	224.299	pa ye rods	98				vs bz, eth, EtOH
527	Astemizole		$C_{28}H_{31}FN_4O$	68844-77-9	458.570	wh cry	149.1				i H_2O; s os
528	Asulam	Methyl [(4-aminophenyl) sulfonyl]carbamate	$C_8H_{10}N_2O_4S$	3337-71-1	230.241		144				
529	Atenolol		$C_{14}H_{22}N_2O_3$	29122-68-7	266.336	cry (AcOEt)	147				sl H_2O, diox, ace; i chl; s MeOH, HOAc
530	Atisine	Anthorine	$C_{22}H_{33}NO_2$	466-43-3	343.503	orth bipym	58.5				vs eth, EtOH, chl
531	Atrazine		$C_8H_{14}ClN_5$	1912-24-9	215.684		173				
532	Atropine		$C_{17}H_{23}NO_3$	51-55-8	289.370	orth nd (dil al)	118.5	sub 95			vs H_2O, EtOH; i eth; sl chl
533	Auramine hydrochloride		$C_{17}H_{24}ClN_3O$	2465-27-2	321.845	ye nd (w)	267				sl H_2O
534	Aureothin		$C_{22}H_{23}NO_6$	2825-00-5	397.421	ye pr	158				vs ace, EtOH, chl
535	Aurin		$C_{19}H_{14}O_3$	603-45-2	290.312	dk red lf or orth	309 dec				i H_2O, bz; s EtOH, alk; sl eth, chl
536	Aurin tricarboxylic acid, triammonium salt	Aluminon	$C_{22}H_{23}N_3O_9$	569-58-4	473.433	red-br pow					s H_2O; sl EtOH; i peth
537	Avermectin B1a	Abamectin	$C_{48}H_{72}O_{14}$	71751-41-2	873.078		152				
538	3-Azabicyclo[3.2.2]nonane		$C_8H_{15}N$	283-24-9	125.212			166^{500}			
539	1-Azabicyclo[2.2.2]octane	Quinuclidine	$C_7H_{13}N$	100-76-5	111.185	cry (eth)	158				vs H_2O, ace, eth, EtOH
540	1-Azabicyclo[2.2.2]octan-3-ol	3-Quinuclidinol	$C_7H_{13}NO$	1619-34-7	127.184	cry (bz)	221	sub 120			s ace
541	Azacitidine	4-Amino-1-β-*D*-ribofuranosyl-1,3,5-triazine-2(1*H*)-one	$C_8H_{12}N_4O_5$	320-67-2	244.205	cry	229				
542	Azacyclotridecan-2-one		$C_{12}H_{23}NO$	947-04-6	197.317		152.5				
543	8-Azaguanine		$C_4H_4N_6O$	134-58-7	152.114		300				
544	Azaserine		$C_5H_7N_3O_4$	115-02-6	173.128	ye-grn orth cry	150 dec				vs H_2O; sl EtOH, ace, MeOH
545	Azathioprine	6-[(1-Methyl-4-nitro-1*H*-imidazol-5-yl)thio]-1*H*-purine	$C_9H_7N_7O_2S$	446-86-6	277.263	ye cry	243 dec				sl H_2O, EtOH, chl
546	6-Azauridine	2-β-*D*-Ribofuranosyl-1,2,4-triazine-3,5(2*H*,4*H*)-dione	$C_8H_{11}N_3O_6$	54-25-1	245.189		158				s H_2O
547	Azetidine		C_3H_7N	503-29-7	57.095	liq	-70.0	63	0.8436^{20}	1.4287^{25}	vs ace, bz, eth, EtOH
548	2-Azetidinecarboxylic acid		$C_4H_7NO_2$	2517-04-6	101.105	cry (95% MeOH)	217 dec				
549	2-Azetidinone		C_3H_5NO	930-21-2	71.078		73.5	106^{15}			vs eth, EtOH, chl
550	Azidobenzene		$C_6H_5N_3$	622-37-7	119.124	pa ye oil	-27.5	70^{11}	1.0860^{20}	1.5589^{25}	i H_2O; sl EtOH, eth
551	1-Azido-4-chlorobenzene		$C_6H_4ClN_3$	3296-05-7	153.569		20	96^{20}	1.2634^{25}		i H_2O; s eth
552	2-Azidoethanol		$C_2H_5N_3O$	1517-05-1	87.080			75^{40}	1.146^{24}		vs H_2O
553	1-Azido-4-methylbenzene		$C_7H_7N_3$	2101-86-2	133.151		-29.0	dec 180; 80^{10}	1.0527^{23}		vs eth, EtOH
554	(Azidomethyl)benzene		$C_7H_7N_3$	622-79-7	133.151			108^{23}, 78^{12}	1.0730^{19}	1.5341^{25}	i H_2O; msc EtOH, eth
555	Azinphos ethyl		$C_{12}H_{16}N_3O_3PS_2$	2642-71-9	345.377	nd	53	111$^{0.001}$	1.284^{20}		reac alk
556	Azinphos-methyl		$C_{10}H_{12}N_3O_3PS_2$	86-50-0	317.324		73		1.44^{20}		
557	1-Aziridineethanol		C_4H_9NO	1072-52-2	87.120			168	1.088^{25}	1.4560^{20}	
558	*trans*-Azobenzene	*trans*-Diphenyldiazene	$C_{12}H_{10}N_2$	17082-12-1	182.220	oran-red mcl lf (al)	67.88	293	1.203^{20}	1.6266^{78}	sl H_2O; s EtOH, eth, bz, chl; vs py
559	*cis*-Azobenzene	*cis*-Diphenyldiazene	$C_{12}H_{10}N_2$	1080-16-6	182.220	oran-red pl (peth)	71				sl H_2O; s EtOH, eth, bz, HOAc, lig
560	3,3'-Azobenzenedisulfonyl chloride		$C_{12}H_8Cl_2N_2O_4S_2$	104115-88-0	379.239	red nd (eth)	166.5				vs eth
561	1,1'-Azobiscyclohexanecarbonitrile		$C_{14}H_{20}N_4$	2094-98-6	244.336		100				i H_2O; s lig
562	2,2'-Azobis[isobutyronitrile]	2,2'-Azobis[2-methylpropionitrile]	$C_8H_{12}N_4$	78-67-1	164.208						i H_2O; sl EtOH, eth
563	Azobutane		$C_8H_{18}N_2$	2159-75-3	142.242			60^{18}			
564	Azopropane		$C_6H_{14}N_2$	821-67-0	114.188			114			
565	*cis*-Azoxybenzene	Diphenyldiazene 1-oxide, (*E*)	$C_{12}H_{10}N_2O$	21650-65-7	198.219		87		1.166^{20}	1.633^{20}	



Aspartame



DL-Aspartic acid



L-Aspartic acid



Aspergillic acid



Astemizole



Asulam



Atenolol



Atisine



Atrazine



Atropine



Auramine hydrochloride


Aureothin



Aurin



Aurin tricarboxylic acid, triammonium salt



Avermectin B1a



3-Azabicyclo[3.2.2]nonane



1-Azabicyclo[2.2.2]octane



1-Azabicyclo[2.2.2]octan-3-ol



Azacitidine


Azacyclotridecan-2-one



8-Azaguanine


Azaserine



Azathioprine



6-Azauridine



Azetidine



2-Azetidinecarboxylic acid



2-Azetidinone



Azidobenzene



1-Azido-4-chlorobenzene



2-Azidoethanol



1-Azido-4-methylbenzene



(Azidomethyl)benzene



Azinphos ethyl



Azinphos-methyl



1-Aziridineethanol



trans-Azobenzene



cis-Azobenzene



3,3'-Azobenzenedisulfonyl chloride


1,1'-Azobiscyclohexanecarbonitrile



2,2'-Azobis[isobutyronitrile]



Azobutane



Azopropane



cis-Azoxybenzene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
566	*trans*-Azoxybenzene	Diphenyldiazene 1-oxide, (*Z*)	$C_{12}H_{10}N_2O$	20972-43-4	198.219		34.6		1.1590^{25}		i H_2O; s EtOH, eth
567	Azoxyethane	Diethyldiazine 1-oxide	$C_4H_{10}N_2O$	16301-26-1	102.134	liq		46			
568	Azulene	Bicyclo[5.3.0]decapentaene	$C_{10}H_8$	275-51-4	128.171	bl or gr-blk lf (al)	99	dec 270; 125^{10}			i H_2O; s EtOH, eth, ace, acid; sl chl
569	Balan	*N*-Butyl-*N*-ethyl-2,6-dinitro-4-(trifluoromethyl)aniline	$C_{13}H_{16}F_3N_3O_4$	1861-40-1	335.279		66	121$^{0.5}$, 148^{7}			
570	Barban		$C_{11}H_9Cl_2NO_2$	101-27-9	258.101		75				
571	Barbital	5,5-Diethylbarbituric acid	$C_8H_{12}N_2O_3$	57-44-3	184.192	nd (w)	190		1.220^{25}		sl H_2O; s EtOH, eth, ace, chl, lig, tfa
572	Barbituric acid		$C_4H_4N_2O_3$	67-52-7	128.086	orth pr (w +2)	248	dec 260			s H_2O, eth; sl EtOH
573	Bayleton	Triadimefon	$C_{14}H_{16}ClN_3O_2$	43121-43-3	293.749		82		1.22^{20}		
574	Bebeerine		$C_{36}H_{38}N_2O_6$	477-60-1	594.696	cry (bz, eth, chl-MeOH)	221				s EtOH, MeOH, eth; vs ace, chl
575	Benactyzine	2-(Diethylamino)ethyl benzilate	$C_{20}H_{25}NO_3$	302-40-9	327.418	cry	51				
576	Benactyzine hydrochloride	2-Diethylaminoethyl benzilate hydrochloride	$C_{20}H_{26}ClNO_3$	57-37-4	363.878		177.5				s H_2O; i eth
577	Benalaxyl		$C_{20}H_{23}NO_3$	71626-11-4	325.402		79		1.27^{25}		
578	Bendiocarb	1,3-Benzodioxol-4-ol, 2,2-dimethyl-, methylcarbamate	$C_{11}H_{13}NO_4$	22781-23-3	223.226		130		1.25^{20}		
579	Bendroflumethiazide		$C_{15}H_{14}F_3N_3O_4S_2$	73-48-3	421.415	cry	225				i H_2O, bz, eth; s EtOH, ace
580	Benomyl		$C_{14}H_{18}N_4O_3$	17804-35-2	290.318		dec				
581	Bensulfuron-methyl		$C_{16}H_{18}N_4O_7S$	83055-99-6	410.402		187				
582	Bensulide		$C_{14}H_{24}NO_4PS_3$	741-58-2	397.514		34.4		1.224^{20}		
583	Bentazon		$C_{10}H_{12}N_2O_3S$	25057-89-0	240.278		138				
584	Benz[c]acridine	12-Azabenz[a]anthracene	$C_{17}H_{11}N$	225-51-4	229.276	nd (dil al)	132				vs bz, eth, EtOH
585	Benzaldehyde	Benzenecarboxaldehyde	C_7H_6O	100-52-7	106.122	liq	-57.1	178.8	1.0401^{25}	1.5463^{20}	sl H_2O; msc EtOH, eth; vs ace, bz
586	Benzaldehyde hydrazone	Benzylidene hydrazine	$C_7H_8N_2$	5281-18-5	120.152	lf	16	140^{14}			s EtOH
587	*cis*-Benzaldehyde oxime		C_7H_7NO	622-32-2	121.137	pr	36.5	200	1.1111^{20}	1.5908^{20}	vs bz, eth, EtOH
588	*trans*-Benzaldehyde oxime		C_7H_7NO	622-31-1	121.137	nd (eth)	35	119^{10}	1.145^{20}		s H_2O; vs EtOH, eth
589	Benzaldehyde, phenylhydrazone		$C_{13}H_{12}N_2$	588-64-7	196.247	nd (lig), pr	157.0				sl EtOH, eth; s ace, bz, liq NH_3
590	Benzaldehyde, (phenylmethylene) hydrazone		$C_{14}H_{12}N_2$	588-68-1	208.258	ye pr (al)	93				i H_2O; s EtOH, eth, ace, bz, chl; sl ctc
591	Benzamide	Benzoic acid amide	C_7H_7NO	55-21-0	121.137	mcl pr or pl (w)	127.3	290	1.0792^{130}		sl H_2O, eth, bz; vs EtOH, ctc, CS_2
592	Benz[a]anthracene	1,2-Benzanthracene	$C_{18}H_{12}$	56-55-3	228.288	lf (al)	160.5	438			i H_2O; vs EtOH
593	Benz[a]anthracene-7,12-dione		$C_{18}H_{10}O_2$	2498-66-0	258.271		170.5				sl EtOH, eth, lig; s ace; vs bz, chl
594	Benzanthrone		$C_{17}H_{10}O$	82-05-3	230.260		170				sl bz
595	Benzene	[6]Annulene	C_6H_6	71-43-2	78.112	orth pr or liq	5.49	80.09	0.8765^{20}	1.5011^{20}	sl H_2O; msc EtOH, eth, ace, chl; s ctc
596	Benzeneacetaldehyde	Phenylacetaldehyde	C_8H_8O	122-78-1	120.149		33.5	195	1.0272^{20}	1.5255^{20}	sl H_2O; s ace; msc EtOH, eth
597	Benzeneacetamide	α-Phenylacetamide	C_8H_9NO	103-81-1	135.163		157				sl H_2O, eth, bz; s EtOH
598	Benzeneacetic acid	Phenylacetic acid	$C_8H_8O_2$	103-82-2	136.149	lf, pl (peth)	76.5	265.5	1.228^{6}		sl H_2O, chl; vs EtOH, eth; s ace; i lig
599	Benzeneacetic acid, hydrazide		$C_8H_{10}N_2O$	937-39-3	150.177		115.5				
600	Benzeneacetic anhydride		$C_{16}H_{14}O_3$	1555-80-2	254.280	pr or nd (eth)	73.3	195^{12}			vs eth, chl
601	Benzeneacetonitrile	Benzyl cyanide	C_8H_7N	140-29-4	117.149	liq	-23.8	233.5	1.0205^{15}	1.5211^{25}	
602	Benzeneacetyl chloride	Phenylacetyl chloride	C_8H_7ClO	103-80-0	154.594			170^{250}, 105^{24}	1.1682^{20}	1.5325^{20}	vs eth
603	Benzenearsonic acid		$C_6H_7AsO_3$	98-05-5	202.040	cry (w)	158 dec				vs H_2O, EtOH
604	Benzeneboronic acid		$C_6H_7BO_2$	98-80-6	121.930		219				sl H_2O; s EtOH, eth, bz
605	Benzenebutanoic acid		$C_{10}H_{12}O_2$	1821-12-1	164.201	lf (w)	52	290			s H_2O, EtOH, eth
606	Benzenebutanol		$C_{10}H_{14}O$	3360-41-6	150.217			140^{14}		1.5214^{20}	
607	Benzenecarboperoxoic acid	Perbenzoic acid	$C_7H_6O_3$	93-59-4	138.121	mcl pl (peth)	42	100^{14}			vs ace, bz, eth, EtOH
608	Benzenecarbothioamide		C_7H_7NS	2227-79-4	137.203		117				



trans-Azoxybenzene



Azoxyethane



Azulene



Balan



Barban



Barbital



Barbituric acid



Bayleton



Bebeerine



Benactyzine



Benactyzine hydrochloride



Benalaxyl



Bendiocarb



Bendroflumethiazide



Benomyl



Bensulfuron-methyl



Bensulide



Bentazon



Benz[c]acridine



Benzaldehyde



Benzaldehyde hydrazone



cis-Benzaldehyde oxime



trans-Benzaldehyde oxime



Benzaldehyde, phenylhydrazone


Benzaldehyde, (phenylmethylene)hydrazone



Benzamide



Benz[a]anthracene



Benz[a]anthracene-7,12-dione



Benzanthrone



Benzene



Benzeneacetaldehyde



Benzeneacetamide



Benzeneacetic acid



Benzeneacetic acid, hydrazide



Benzeneacetic anhydride



Benzeneacetonitrile



Benzeneacetyl chloride



Benzenearsonic acid


Benzeneboronic acid



Benzenebutanoic acid



Benzenebutanol



Benzenecarboperoxoic acid



Benzenecarbothioamide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
609	Benzenecarbothioic acid		C_7H_6OS	98-91-9	138.187	ye pl (HOAc)	24	86[10]	1.28[20]	1.6040[20]	vs ace, bz, eth, EtOH
610	Benzenecarboximidamide, monohydrochloride		$C_7H_9ClN_2$	1670-14-0	156.612	orth pr (w +2)	169				s H_2O, EtOH; sl tfa
611	1,2-Benzenediamine	*o*-Phenylenediamine	$C_6H_8N_2$	95-54-5	108.141	brsh ye lf (w) pl (chl)	102.1	257			s H_2O, eth, bz, chl; vs EtOH
612	1,3-Benzenediamine	*m*-Phenylenediamine	$C_6H_8N_2$	108-45-2	108.141	orth (al)	66.0	285	1.0096[58]	1.6339[58]	vs H_2O; s EtOH, eth, bz
613	1,4-Benzenediamine	*p*-Phenylenediamine	$C_6H_8N_2$	106-50-3	108.141	wh pl (bz, eth)	141.1	267			sl H_2O; s EtOH, eth, bz, chl
614	1,2-Benzenediamine, dihydrochloride		$C_6H_{10}Cl_2N_2$	615-28-1	181.062		250 dec				
615	1,3-Benzenediamine, dihydrochloride		$C_6H_{10}Cl_2N_2$	541-69-5	181.062						s H_2O
616	1,4-Benzenediamine, dihydrochloride		$C_6H_{10}Cl_2N_2$	624-18-0	181.062						s H_2O
617	1,2-Benzenedicarbonyl dichloride	Phthaloyl chloride	$C_8H_4Cl_2O_2$	88-95-9	203.023		15.5	281.1	1.4089[20]	1.5684[20]	
618	1,3-Benzenedicarbonyl dichloride		$C_8H_4Cl_2O_2$	99-63-8	203.023	pr(eth)	43.5	276	1.3880[17]	1.570[47]	sl H_2O, EtOH; s eth
619	1,4-Benzenedicarbonyl dichloride		$C_8H_4Cl_2O_2$	100-20-9	203.023	nd or pl (lig)	83.5	258; 125[9]			s eth
620	1,2-Benzenedicarboxaldehyde		$C_8H_6O_2$	643-79-8	134.133	ye cry or nd (lig)	55.8	83[0.8]			vs eth, EtOH
621	1,3-Benzenedicarboxaldehyde		$C_8H_6O_2$	626-19-7	134.133	nd (dil al)	89.5	246; 136[13]			sl H_2O, eth, chl; vs EtOH; s ace, bz
622	1,4-Benzenedicarboxaldehyde		$C_8H_6O_2$	623-27-8	134.133	nd (w)	117	246			sl H_2O; vs EtOH; s eth, chl, alk
623	1,2-Benzenedicarboxamide	Phthalamide	$C_8H_8N_2O_2$	88-96-0	164.162	cry	222	dec			sl H_2O, EtOH; i eth
624	1,4-Benzenedicarboxamide		$C_8H_8N_2O_2$	3010-82-0	164.162	nd (w), pl (HOAc)	322.3				
625	1,2-Benzenedicarboxylic acid, bis(2-butoxyethyl) ester	Bis(2-butoxyethyl) phthalate	$C_{20}H_{30}O_6$	117-83-9	366.448			270			
626	1,2-Benzenedicarboxylic acid, bis(2-methoxyethyl) ester	Bis(2-methoxyethyl) phthalate	$C_{14}H_{18}O_6$	117-82-8	282.289		-60.0	230[10]	1.1596[20]		
627	1,2-Benzenedicarboxylic acid, diallyl ester	Diallyl phthalate	$C_{14}H_{14}O_4$	131-17-9	246.259			161[4]			
628	1,2-Benzenedicarboxylic acid, dipropyl ester	Dipropyl phthalate	$C_{14}H_{18}O_4$	131-16-8	250.291	liq	-31.0	304.5	1.0767[20]		i H_2O; s EtOH, eth
629	1,3-Benzenedimethanamine	*m*-Xylene diamine	$C_8H_{12}N_2$	1477-55-0	136.194			247	1.052[20]		vs H_2O, eth, EtOH
630	1,2-Benzenedimethanol		$C_8H_{10}O_2$	612-14-6	138.164	pl (eth, peth)	64.8	145[3]			s H_2O, EtOH; vs eth; sl bz
631	1,3-Benzenedimethanol		$C_8H_{10}O_2$	626-18-6	138.164	nd (bz)	57	156[13]	1.1610[18]		vs H_2O, eth, EtOH
632	1,4-Benzenedimethanol		$C_8H_{10}O_2$	589-29-7	138.164	nd (w)	117.5	140[1]			vs H_2O, ace, eth, EtOH
633	1,2-Benzenediol, diacetate		$C_{10}H_{10}O_4$	635-67-6	194.184	nd (al)	64.5	142[9]			i H_2O; vs EtOH, eth, chl; s peth
634	1,4-Benzenediol, diacetate		$C_{10}H_{10}O_4$	1205-91-0	194.184	pl (w, al)	123.5		0.8731[25]		s H_2O; vs EtOH, eth, chl, lig
635	1,3-Benzenediol, monobenzoate		$C_{13}H_{10}O_3$	136-36-7	214.216		134.5				
636	1,3-Benzenedisulfonic acid		$C_6H_6O_6S_2$	98-48-6	238.238	hyg cry					
637	1,3-Benzenedisulfonyl dichloride		$C_6H_4Cl_2O_4S_2$	585-47-7	275.130		61.8	195[10.5]			
638	1,2-Benzenedithiol		$C_6H_6S_2$	17534-15-5	142.242		28.5	238.5			vs EtOH, eth, bz; s AcOEt
639	1,3-Benzenedithiol		$C_6H_6S_2$	626-04-0	142.242	lf	27	245			vs bz, eth, EtOH
640	Benzeneethanamine	1-Amino-2-phenylethane	$C_8H_{11}N$	64-04-0	121.180	liq	<0	195	0.9640[25]	1.5290[25]	s H_2O, ctc; vs EtOH, eth
641	Benzeneethanamine, hydrochloride		$C_8H_{12}ClN$	156-28-5	157.641	pl or lf (al)	218.5				vs H_2O, EtOH
642	Benzeneethanol	Phenethyl alcohol	$C_8H_{10}O$	60-12-8	122.164	liq	-27	218.2	1.0202[20]	1.5325[20]	sl H_2O; msc EtOH, eth
643	Benzenehexacarboxylic acid	Mellitic acid	$C_{12}H_6O_{12}$	517-60-2	342.169	nd (al)	287 dec				vs H_2O; s EtOH, sulf
644	Benzenemethanamine, hydrochloride		$C_7H_{10}ClN$	3287-99-8	143.614		258.3				vs H_2O, EtOH
645	Benzenemethanesulfonyl chloride		$C_7H_7ClO_2S$	1939-99-7	190.648	pr (eth), nd (bz)	93				vs eth, bz
646	Benzenemethanesulfonyl fluoride		$C_7H_7FO_2S$	329-98-6	174.193		92.0				
647	Benzenemethanethiol	Thiobenzyl alcohol	C_7H_8S	100-53-8	124.204	liq	-30	194.5	1.058[20]	1.5151[20]	i H_2O; vs EtOH, eth; sl ctc; s CS_2
648	Benzenepentanoic acid	5-Phenylvaleric acid	$C_{11}H_{14}O_2$	2270-20-4	178.228	pl (w), pr (peth)	57.5	190[30]			sl H_2O; vs EtOH; s os
649	Benzenepentanol		$C_{11}H_{16}O$	10521-91-2	164.244			155[20], 150[18]	0.9725[20]	1.5156[20]	vs eth, EtOH



Benzenecarbothioic acid



Benzenecarboximidamide, monohydrochloride



1,2-Benzenediamine



1,3-Benzenediamine



1,4-Benzenediamine



1,2-Benzenediamine, dihydrochloride



1,3-Benzenediamine, dihydrochloride



1,4-Benzenediamine, dihydrochloride



1,2-Benzenedicarbonyl dichloride



1,3-Benzenedicarbonyl dichloride



1,4-Benzenedicarbonyl dichloride



1,2-Benzenedicarboxaldehyde



1,3-Benzenedicarboxaldehyde



1,4-Benzenedicarboxaldehyde



1,2-Benzenedicarboxamide



1,4-Benzenedicarboxamide



1,2-Benzenedicarboxylic acid, bis(2-butoxyethyl) ester



1,2-Benzenedicarboxylic acid, bis(2-methoxyethyl) ester



1,2-Benzenedicarboxylic acid, diallyl ester



1,2-Benzenedicarboxylic acid, dipropyl ester



1,3-Benzenedimethanamine



1,2-Benzenedimethanol



1,3-Benzenedimethanol



1,4-Benzenedimethanol



1,2-Benzenediol, diacetate



1,4-Benzenediol, diacetate



1,3-Benzenediol, monobenzoate



1,3-Benzenedisulfonic acid



1,3-Benzenedisulfonyl dichloride



1,2-Benzenedithiol



1,3-Benzenedithiol



Benzeneethanamine



Benzeneethanamine, hydrochloride



Benzeneethanol



Benzenehexacarboxylic acid



Benzenemethanamine, hydrochloride


Benzenemethanesulfonyl chloride



Benzenemethanesulfonyl fluoride



Benzenemethanethiol



Benzenepentanoic acid



Benzenepentanol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
650	Benzenepropanal	Hydrocinnamic aldehyde	$C_9H_{10}O$	104-53-0	134.174	mcl	47	224; 117[28]	1.0190[20]		i H_2O; vs EtOH; msc eth
651	Benzenepropanenitrile	Hydrocinnamonitrile	C_9H_9N	645-59-0	131.174	liq	-1	261; 141[25]	1.0016[20]	1.5266[28]	s EtOH, eth; sl chl
652	Benzenepropanethiol		$C_9H_{12}S$	24734-68-7	152.256			121[23], 109[10]	1.01[25]	1.5494[20]	
653	Benzenepropanoic acid	Hydrocinnamic acid	$C_9H_{10}O_2$	501-52-0	150.174	nd (w)	48	279.8	1.0712[49]		s H_2O, EtOH, eth, ctc, CS_2; vs bz
654	Benzenepropanol	Hydrocinnamyl alcohol	$C_9H_{12}O$	122-97-4	136.190		<-18	235	0.995[25]	1.5357[25]	s H_2O, ctc; msc EtOH, eth
655	Benzenepropanol carbamate	Phenprobamate	$C_{10}H_{13}NO_2$	673-31-4	179.216		102				i H_2O; s EtOH, chl
656	Benzenepropanoyl chloride		C_9H_9ClO	645-45-4	168.619			dec 225; 105[10]	1.135[21]		s eth, CS_2
657	Benzeneseleninic acid	Phenylseleninic acid	$C_6H_6O_2Se$	6996-92-5	189.07		124.5		1.93[20]		sl H_2O; i bz; vs alk
658	Benzeneselenol		C_6H_6Se	645-96-5	157.07			183.6; 84[25]	1.4865[15]		i H_2O; s EtOH; vs eth, ctc
659	Benzenesulfinic acid		$C_6H_6O_2S$	618-41-7	142.176	pr (w)	84	dec			sl H_2O; s EtOH, eth, bz; i peth
660	Benzenesulfinyl chloride		C_6H_5ClOS	4972-29-6	160.621	pl (peth)	38	71[1.5]	1.3469[25]	1.3470[25]	s eth, chl
661	Benzenesulfonamide		$C_6H_7NO_2S$	98-10-2	157.191	lf, nd (w)	156				sl H_2O, tfa; s EtOH, eth
662	Benzenesulfonic acid	Besylic acid	$C_6H_6O_3S$	98-11-3	158.175	nd (bz)	65				vs H_2O, EtOH; i eth; sl bz; s HOAc
663	Benzenesulfonyl chloride	Phenylsulfonyl chloride	$C_6H_5ClO_2S$	98-09-9	176.621		14.5	dec 251	1.3470[15]		i H_2O; vs EtOH; s eth, ctc
664	Benzenesulfonyl fluoride	Phenylsulfonyl fluoride	$C_6H_5FO_2S$	368-43-4	160.166			203.5	1.3286[20]	1.4932[18]	s EtOH, eth
665	1,2,4,5-Benzenetetracarboxylic acid	Pyromellitic acid	$C_{10}H_6O_8$	89-05-4	254.150	tcl pr (w+2)	276				sl H_2O; s EtOH
666	Benzenethiol	Phenyl mercaptan	C_6H_6S	108-98-5	110.177	liq	-14.93	169.1	1.0775[20]	1.5893[20]	i H_2O; s EtOH, eth, bz; sl ctc
667	1,3,5-Benzenetricarbonyl trichloride		$C_9H_3Cl_3O_3$	4422-95-1	265.477		36.3	180[16]			s chl
668	1,2,3-Benzenetricarboxylic acid	Hemimellitic acid	$C_9H_6O_6$	569-51-7	210.140	pr (al)	200		1.546[20]		vs eth, EtOH
669	1,2,4-Benzenetricarboxylic acid	Trimellitic acid	$C_9H_6O_6$	528-44-9	210.140	nd (w) cry (al) cry (HOAc)	219				vs H_2O, eth, EtOH
670	1,3,5-Benzenetricarboxylic acid		$C_9H_6O_6$	554-95-0	210.140	pr or nd (w+1)	380				sl H_2O; vs EtOH, eth
671	1,2,4-Benzenetricarboxylic acid 1,2-anhydride, 4-chloride	4-(Chloroformyl)phthalic anhydride	$C_9H_3ClO_4$	1204-28-0	210.571		66				
672	1,2,4-Benzenetricarboxylic acid, triallyl ester		$C_{18}H_{18}O_6$	2694-54-4	330.332		<-30		1.164[20]		
673	1,2,3-Benzenetriol	Pyrogallol	$C_6H_6O_3$	87-66-1	126.110	lf or nd (bz)	133	309	1.453[4]	1.561[134]	vs H_2O, EtOH, eth, NH_3; s ace; i bz
674	1,2,4-Benzenetriol	Hydroxyhydroquinone	$C_6H_6O_3$	533-73-3	126.110	pl (eth), lf or pl (w)	140.5				vs H_2O, EtOH, eth; i bz, chl
675	1,3,5-Benzenetriol	Phloroglucinol	$C_6H_6O_3$	108-73-6	126.110	lf or pl (w +2)	218.5	sub	1.46[25]		sl H_2O; vs EtOH, eth, bz, py; s ace
676	1,2,4-Benzenetriol triacetate		$C_{12}H_{12}O_6$	613-03-6	252.219		99	300			s EtOH, chl, MeOH
677	Benzestrol		$C_{20}H_{26}O_2$	85-95-0	298.419	cry (al)	164				vs ace, eth, EtOH, HOAc
678	Benzethonium chloride		$C_{27}H_{42}ClNO_2$	121-54-0	448.081	pl (chl/eth)	165 (hyd)				vs H_2O; s ace, chl, EtOH
679	Benzidene-3,3'-dicarboxylic acid	3,3'-Dicarboxybenzidine	$C_{14}H_{12}N_2O_4$	2130-56-5	272.256	nd	300 dec				
680	*p*-Benzidine	[1,1'-Biphenyl]-4,4'-diamine	$C_{12}H_{12}N_2$	92-87-5	184.236	nd (w)	120	401			sl H_2O, eth, DMSO; s EtOH
681	Benzil	Diphenylethanedione	$C_{14}H_{10}O_2$	134-81-6	210.228	ye pr (al)	94.87	347	1.084[102]		i H_2O; vs EtOH, eth; s ace; sl ctc
682	1*H*-Benzimidazol-2-amine		$C_7H_7N_3$	934-32-7	133.151	pl (w)	224				s H_2O, EtOH, ace; sl eth, bz, DMSO
683	1*H*-Benzimidazole	*N,N'*-Methenyl-*o*-phenylenediamine	$C_7H_6N_2$	51-17-2	118.136	orth bipym pl (w)	170.5	>360			sl H_2O, eth; vs EtOH; i bz; s dil alk
684	1*H*-Benzimidazole-2-acetonitrile		$C_9H_7N_3$	4414-88-4	157.172		208.4				
685	1*H*-Benz[de]isoquinoline-1,3(2*H*)-dione		$C_{12}H_7NO_2$	81-83-4	197.190	nd (chl-al)	300				
686	Benzo[c]chrysene		$C_{22}H_{14}$	194-69-4	278.346	nd (AcOH)	126.5				
687	Benzo[g]chrysene	Benzo[a]triphenylene	$C_{22}H_{14}$	196-78-1	278.346	nd (AcOH)	114.5				



Benzenepropanal



Benzenepropanenitrile



Benzenepropanethiol


Benzenepropanoic acid



Benzenepropanol



Benzenepropanol carbamate



Benzenepropanoyl chloride



Benzeneseleninic acid



Benzeneselenol



Benzenesulfinic acid



Benzenesulfinyl chloride


Benzenesulfonamide



Benzenesulfonic acid



Benzenesulfonyl chloride



Benzenesulfonyl fluoride



1,2,4,5-Benzenetetracarboxylic acid



Benzenethiol



1,3,5-Benzenetricarbonyl trichloride



1,2,3-Benzenetricarboxylic acid



1,2,4-Benzenetricarboxylic acid



1,3,5-Benzenetricarboxylic acid



1,2,4-Benzenetricarboxylic acid 1,2-anhydride, 4-chloride



1,2,4-Benzenetricarboxylic acid, triallyl ester



1,2,3-Benzenetriol



1,2,4-Benzenetriol



1,3,5-Benzenetriol



1,2,4-Benzenetriol triacetate



Benzestrol


Benzethonium chloride



Benzidene-3,3'-dicarboxylic acid



p-Benzidine



Benzil



1*H*-Benzimidazol-2-amine


1*H*-Benzimidazole



1*H*-Benzimidazole-2-acetonitrile



1*H*-Benz[de]isoquinoline-1,3(2*H*)-dione



Benzo[c]chrysene


Benzo[g]chrysene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
688	1*H*,3*H*-Benzo[1,2-c:4,5-c']difuran-1,3,5,7-tetrone		$C_{10}H_2O_6$	89-32-7	218.119		285.3				
689	1,3,2-Benzodioxaborole		$C_6H_5BO_2$	274-07-7	119.914		12	88[156], 50[50]	1.2700[20]	1.5070[20]	
690	1,3-Benzodioxol-5-amine		$C_7H_7NO_2$	14268-66-7	137.137		42	144[16]			
691	1,3-Benzodioxole		$C_7H_6O_2$	274-09-9	122.122			172.5; 77[27]	1.064[25]	1.5398[20]	
692	1,3-Benzodioxole-5-carboxaldehyde	Piperonal	$C_8H_6O_3$	120-57-0	150.132		37	263			sl H_2O; vs EtOH; msc eth; s ace, chl
693	1,3-Benzodioxole-5-carboxylic acid	Piperonylic acid	$C_8H_6O_4$	94-53-1	166.132		229				
694	1,3-Benzodioxole-5-ethanamine		$C_9H_{11}NO_2$	1484-85-1	165.189			166[20], 101[1]	1.225[20]	1.5620[20]	
695	1,3-Benzodioxole-5-methanamine		$C_8H_9NO_2$	2620-50-0	151.163			139[13], 100[0.07]	1.214[25]	1.5635[20]	
696	1,3-Benzodioxole-5-methanol		$C_8H_8O_3$	495-76-1	152.148	nd (peth)	58	157[16]			sl H_2O; s EtOH, eth, bz, chl; i lig
697	1,3-Benzodioxol-5-ol		$C_7H_6O_3$	533-31-3	138.121		64.9				
698	*trans,trans*-5-(1,3-Benzodioxol-5-yl)-2,4-pentadienoic acid	Piperinic acid	$C_{12}H_{10}O_4$	136-72-1	218.205	nd (al), ye nd (sub)	215.8	sub			vs EtOH
699	7,8-Benzoflavone	2-Phenyl-4*H*-naphtho[1,2-b] pyran-4-one	$C_{19}H_{12}O_2$	604-59-1	272.297	ye pl (al)	157				sl EtOH, chl; s sulf
700	Benzo[b]fluoranthene	Benz[e]acephenanthrylene	$C_{20}H_{12}$	205-99-2	252.309	nd (bz)	168				i H_2O; msc bz
701	Benzo[j]fluoranthene	Dibenzo[a,jk]fluorene	$C_{20}H_{12}$	205-82-3	252.309	ye pl (al) nd (HOAc)	166				i H_2O; sl EtOH, HOAc
702	Benzo[k]fluoranthene	2,3,1',8'-Binaphthylene	$C_{20}H_{12}$	207-08-9	252.309	pa ye nd (bz)	217	480			i H_2O; s EtOH, bz, HOAc
703	11*H*-Benzo[a]fluorene		$C_{17}H_{12}$	238-84-6	216.277	pl (ace or HOAc)	189.5	405			i H_2O; sl EtOH; s eth, bz, chl
704	11*H*-Benzo[b]fluorene		$C_{17}H_{12}$	243-17-4	216.277		212	401			i H_2O
705	Benzofuran	Coumarone	C_8H_6O	271-89-6	118.133		<-18	174	1.0913[25]	1.5615[17]	i H_2O; s EtOH, eth
706	2-Benzofurancarboxylic acid	Coumarilic acid	$C_9H_6O_3$	496-41-3	162.142	nd (w)	192.5	312.5			vs EtOH
707	2(3*H*)-Benzofuranone		$C_8H_6O_2$	553-86-6	134.133		50	249	1.2236[14]		
708	3(2*H*)-Benzofuranone		$C_8H_6O_2$	7169-34-8	134.133	red nd (al)	102.5	152[15]			vs bz
709	1-(2-Benzofuranyl)ethanone		$C_{10}H_8O_2$	1646-26-0	160.170		76	126[11]			s H_2O
710	Benzofurazan, 1-oxide		$C_6H_4N_2O_2$	480-96-6	136.108		71.5		1.280[80]		
711	Benzohydrazide	Benzoic acid, hydrazide	$C_7H_8N_2O$	613-94-5	136.151	pl (w)	115	dec 267			s H_2O, EtOH; sl eth, ace, chl
712	Benzoic acid	Benzenecarboxylic acid	$C_7H_6O_2$	65-85-0	122.122	mcl lf or nd	122.35	249.2	1.2659[15]	1.504[132]	sl H_2O; vs EtOH, eth; s ace, bz, chl
713	Benzoic anhydride		$C_{14}H_{10}O_3$	93-97-0	226.227	pr (eth)	42.5	360	1.989[15]	1.5767[15]	i H_2O, lig; s EtOH, eth; sl chl
714	Benzoin	2-Hydroxy-1,2-diphenylethanone, (±)	$C_{14}H_{12}O_2$	579-44-2	212.244		137	344; 194[12]	1.310[20]		vs EtOH, chl
715	Benzonitrile	Phenyl cyanide	C_7H_5N	100-47-0	103.122	liq	-13.99	191.1	1.0093[15]	1.5289[20]	sl H_2O; msc EtOH; vs ace, bz; s ctc
716	Benzo[ghi]perylene	1,12-Benzperylene	$C_{22}H_{12}$	191-24-2	276.330	ye-grn lf (bz)	272.5				i H_2O
717	Benzo[c]phenanthrene	Tetrahelicene	$C_{18}H_{12}$	195-19-7	228.288		68				i H_2O; sl EtOH, lig
718	Benzophenone	Diphenyl ketone	$C_{13}H_{10}O$	119-61-9	182.217	(α) orth pr (al); (β) mcl pr	47.9 (α); 26 (β)	305.4	1.111[18]	1.6077[19]	i H_2O; vs EtOH, eth, chl, ace; s bz
719	Benzophenone hydrazone		$C_{13}H_{12}N_2$	5350-57-2	196.247		97.3	227[55]			
720	Benzophenone, oxime	Diphenyl ketoxime	$C_{13}H_{11}NO$	574-66-3	197.232	nd (al)	144				i H_2O; vs EtOH, eth, chl, ace; s bz
721	3,3',4,4'-Benzophenonetetracarboxylic acid dianhydride	4,4'-Carbonyldiphthalic anhydride	$C_{17}H_6O_7$	2421-28-5	322.226		216				
722	Benzo-2-phenylhydrazide		$C_{13}H_{12}N_2O$	532-96-7	212.246	pr (al), nd (w)	168	314			sl H_2O, eth; s EtOH, bz, chl
723	Benzopurpurine 4B	C.I. Direct Red 2, disodium salt	$C_{34}H_{26}N_6Na_2O_6S_2$	992-59-6	724.716	br pow					s H_2O, EtOH, ac, H_2SO_4
724	2*H*-1-Benzopyran	1,2-Chromene	C_9H_8O	254-04-6	132.159			132[102], 91[13]	1.0993[16]	1.5869[24]	i H_2O
725	[2]Benzopyrano[6,5,4-def][2] benzopyran-1,3,6,8-tetrone	1,4,5,8-Naphthalenetetracarboxylic acid anhydride	$C_{14}H_4O_6$	81-30-1	268.178	nd (al)	450	sub 320			i H_2O; s Na_2CO_3, HOAc
726	1*H*-2-Benzopyran-1-one	Isocoumarin	$C_9H_6O_2$	491-31-6	146.143	pl (bz)	47	286			i H_2O; vs EtOH, eth, bz, CS_2
727	2*H*-1-Benzopyran-2-one	Coumarin	$C_9H_6O_2$	91-64-5	146.143	orth pym (eth)	71	301.7	0.935[20]		s H_2O, EtOH, alk; vs eth, chl, py



1*H*,3*H*-Benzo[1,2-c:4,5-c']difuran-1,3,5,7-tetrone



1,3,2-Benzodioxaborole



1,3-Benzodioxol-5-amine



1,3-Benzodioxole



1,3-Benzodioxole-5-carboxaldehyde



1,3-Benzodioxole-5-carboxylic acid



1,3-Benzodioxole-5-ethanamine



1,3-Benzodioxole-5-methanamine



1,3-Benzodioxole-5-methanol



1,3-Benzodioxol-5-ol



trans,trans-5-(1,3-Benzodioxol-5-yl)-2,4-pentadienoic acid



7,8-Benzoflavone


Benzo[b]fluoranthene



Benzo[j]fluoranthene



Benzo[k]fluoranthene


11*H*-Benzo[a]fluorene



11*H*-Benzo[b]fluorene



Benzofuran



2-Benzofurancarboxylic acid



2(3*H*)-Benzofuranone



3(2*H*)-Benzofuranone



1-(2-Benzofuranyl)ethanone



Benzofurazan, 1-oxide



Benzohydrazide



Benzoic acid



Benzoic anhydride



Benzoin



Benzonitrile



Benzo[ghi]perylene



Benzo[c]phenanthrene



Benzophenone



Benzophenone hydrazone



Benzophenone, oxime



3,3',4,4'-Benzophenonetetracarboxylic acid dianhydride



Benzo-2-phenylhydrazide


Benzopurpurine 4B



2*H*-1-Benzopyran



[2]Benzopyrano[6,5,4-def][2]benzopyran-1,3,6,8-tetrone



1*H*-2-Benzopyran-1-one



2*H*-1-Benzopyran-2-one


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
728	4*H*-1-Benzopyran-4-one		$C_9H_6O_2$	491-38-3	146.143	nd (peth w)	59	sub	1.2900^{20}		sl H_2O; s EtOH, eth, bz, chl
729	Benzo[a]pyrene	2,3-Benzopyrene	$C_{20}H_{12}$	50-32-8	252.309		181.1				i H_2O; vs chl
730	Benzo[e]pyrene	1,2-Benzpyrene	$C_{20}H_{12}$	192-97-2	252.309	pa ye nd (bz-MeOH)	181.4	311			i H_2O
731	Benzo[f]quinoline	β-Naphthoquinoline	$C_{13}H_9N$	85-02-9	179.217	lf (peth or w)	94	352; 203^{8}			sl H_2O; vs EtOH, bz, eth; s ace
732	Benzo[h]quinoline		$C_{13}H_9N$	230-27-3	179.217	lf (eth), pl (peth)	52	339; 233^{47}	1.2340^{20}		sl H_2O; s EtOH, eth, ace, bz, ctc
733	*p*-Benzoquinone	2,5-Cyclohexadiene-1,4-dione	$C_6H_4O_2$	106-51-4	108.095	ye mcl pr (w)	115	sub	1.318^{20}		sl H_2O, peth; s EtOH, eth, chl
734	2,1,3-Benzothiadiazole		$C_6H_4N_2S$	273-13-2	136.174		43	206			
735	2-Benzothiazolamine	2-Aminobenzothiazole	$C_7H_6N_2S$	136-95-8	150.201	pl (w), lf (w)	132				sl H_2O; s EtOH, eth, chl, con HCl
736	6-Benzothiazolamine	6-Aminobenzothiazole	$C_7H_6N_2S$	533-30-2	150.201	pr (w)	87				i H_2O, eth; s EtOH
737	Benzothiazole	Benzosulfonazole	C_7H_5NS	95-16-9	135.187		1.0	231	1.2460^{20}	1.6379^{20}	sl H_2O; vs EtOH, eth, CS_2; s ace
738	2(3*H*)-Benzothiazolethione	2-Mercaptobenzothiazole	$C_7H_5NS_2$	149-30-4	167.252	pa ye mcl nd(al, MeOH)	181		1.42^{20}		i H_2O; s EtOH; sl eth, bz, DMSO
739	2(3*H*)-Benzothiazolethione, sodium salt		$C_7H_4NNaS_2$	2492-26-4	189.234						sl H_2O
740	2(3*H*)-Benzothiazolone		C_7H_5NOS	934-34-9	151.186	pr (dil al), nd	139	360			i H_2O; vs EtOH, eth
741	2(3*H*)-Benzothiazolone, hydrazone		$C_7H_7N_3S$	615-21-4	165.216		202.8				
742	2-(2-Benzothiazolyl)phenol		$C_{13}H_9NOS$	3411-95-8	227.281	nd or lf (al)	131	179^{3}			s EtOH
743	Benzo[b]thiophene	Thianaphthene	C_8H_6S	95-15-8	134.199	lf	32	221	1.1484^{32}	1.6374^{37}	i H_2O; vs EtOH; s eth, ace, bz; sl chl
744	Benzo[b]thiophene-2-carboxylic acid	Thionaphthene-2-carboxylic acid	$C_9H_6O_2S$	6314-28-9	178.208	nd (w)	240.5				vs eth
745	1*H*-Benzotriazole	1,2,3-Triaza-1*H*-indene	$C_6H_5N_3$	95-14-7	119.124	nd (chl or bz)	100	204^{15}			sl H_2O; s EtOH, bz, chl, tol, DMF
746	Benzo[b]triphenylene		$C_{22}H_{14}$	215-58-7	278.346	nd (al, HOAc)	205				i H_2O; vs bz
747	3*H*-2,1-Benzoxathiol-3-one 1,1-dioxide		$C_7H_4O_4S$	81-08-3	184.170	nd or pr (bz)	129.5	184^{18}			vs bz, chl
748	2*H*-3,1-Benzoxazine-2,4(1*H*)-dione		$C_8H_5NO_3$	118-48-9	163.131	pr (al, gl HOAc) cry (al)	243 dec				sl H_2O, EtOH, ace; i eth, bz, chl
749	Benzoxazole	1-Oxa-3-azaindene	C_7H_5NO	273-53-0	119.121	pr (dil al)	31	182.5	1.1754^{20}	1.5594^{20}	i H_2O; s EtOH, sulf
750	2(3*H*)-Benzoxazolethione		C_7H_5NOS	2382-96-9	151.186	nd (w)	196				sl H_2O, ace, EtOH; vs eth, HOAc
751	2(3*H*)-Benzoxazolone		$C_7H_5NO_2$	59-49-4	135.121		138	335; 230^{30}			sl H_2O; s EtOH, eth, tfa
752	2-(2-Benzoxazolyl)phenol		$C_{13}H_9NO_2$	835-64-3	211.216	pink nd (al, HOAc)	123.5	338			sl H_2O; vs EtOH; s eth, ace, bz
753	*N*-Benzoyl-*DL*-alanine		$C_{10}H_{11}NO_3$	1205-02-3	193.199	pl, pr or lf (eth)	165.5	dec			s H_2O, EtOH; sl eth, DMSO
754	4-(Benzoylamino)-2-hydroxybenzoic acid	Benzoylpas	$C_{14}H_{11}NO_4$	13898-58-3	257.242		260.5				
755	Benzoyl azide	Benzazide	$C_7H_5N_3O$	582-61-6	147.134	pl (ace)	32	exp	1.1680^{35}		vs eth, EtOH
756	2-Benzoylbenzoic acid		$C_{14}H_{10}O_3$	85-52-9	226.227	tcl nd (w+1)	129.0				vs EtOH, eth; s bz; sl chl
757	4-Benzoylbenzoic acid		$C_{14}H_{10}O_3$	611-95-0	226.227	nd (HOAc), pl (al) mcl lf (w)	199	sub			sl H_2O, tfa, bz; s EtOH, eth, HOAc
758	2-Benzoylbenzoic acid, hydrazide		$C_{14}H_{12}N_2O_2$	787-84-8	240.257	nd (al)	242.3				sl H_2O; i EtOH, eth, chl; s MeOH
759	4-Benzoylbiphenyl	4-Phenylbenzophenone	$C_{19}H_{14}O$	2128-93-0	258.313		101.5	420; 156$^{0.1}$			
760	Benzoyl bromide	Benzoic acid, bromide	C_7H_5BrO	618-32-6	185.018	liq	-24	218.5	1.570^{15}	1.5868^{25}	msc eth
761	Benzoyl chloride	Benzoic acid, chloride	C_7H_5ClO	98-88-4	140.567	liq	-0.4	197.2; 71^{9}	1.2120^{20}	1.5537^{20}	msc eth; s bz, ctc, CS_2
762	Benzoyl cyclohexane	Cyclohexyl phenyl ketone	$C_{13}H_{16}O$	712-50-5	188.265	nd (peth)	59.5	164^{18}			
763	Benzoylecgonine		$C_{16}H_{19}NO_4$	519-09-5	289.327	nd (w)	195				vs bz, EtOH
764	Benzoylferrocene		$C_{17}H_{14}FeO$	1272-44-2	290.137		110.0				
765	Benzoyl fluoride	Benzoic acid, fluoride	C_7H_5FO	455-32-3	124.112	liq	-28	154.5	1.1400^{20}		vs EtOH, eth; s ctc



4*H*-1-Benzopyran-4-one



Benzo[a]pyrene



Benzo[e]pyrene



Benzo[f]quinoline


Benzo[h]quinoline



p-Benzoquinone



2,1,3-Benzothiadiazole



2-Benzothiazolamine



6-Benzothiazolamine



Benzothiazole


2(3*H*)-Benzothiazolethione



2(3*H*)-Benzothiazolethione, sodium salt



2(3*H*)-Benzothiazolone



2(3*H*)-Benzothiazolone, hydrazone



2-(2-Benzothiazolyl)phenol



Benzo[b]thiophene


Benzo[b]thiophene-2-carboxylic acid


1*H*-Benzotriazole



Benzo[b]triphenylene



3*H*-2,1-Benzoxathiol-3-one 1,1-dioxide



2*H*-3,1-Benzoxazine-2,4(1*H*)-dione



Benzoxazole



2(3*H*)-Benzoxazolethione



2(3*H*)-Benzoxazolone



2-(2-Benzoxazolyl)phenol



N-Benzoyl-*DL*-alanine



4-(Benzoylamino)-2-hydroxybenzoic acid



Benzoyl azide



2-Benzoylbenzoic acid



4-Benzoylbenzoic acid



2-Benzoylbenzoic acid, hydrazide



4-Benzoylbiphenyl



Benzoyl bromide


Benzoyl chloride



Benzoyl cyclohexane



Benzoylecgonine



Benzoylferrocene



Benzoyl fluoride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
766	*N*-Benzoylglycine	Hippuric acid	$C_9H_9NO_3$	495-69-2	179.172	pr (w or al)	191.5		1.371^{20}		s H_2O, EtOH; sl eth, bz, chl; i peth
767	Benzoyl iodide	Benzoic acid, iodide	C_7H_5IO	618-38-2	232.018	nd	1.5	128^{20}	1.746^{18}		vs eth, EtOH
768	2-Benzoylmethyl-6(2-hydroxy-2-phenylethyl)-1-methylpiperidine, hydrochloride		$C_{22}H_{28}ClNO_2$	63990-84-1	373.916		183.5				sl H_2O; s EtOH; vs chl
769	3-(Benzoyloxy)-8-methyl-8-azabicyclo[3.2.1]octane-2-carboxylic acid, ethyl ester, [1*R*-(*exo,exo*)]	Cocaethylene	$C_{18}H_{23}NO_4$	529-38-4	317.381	pr (eth)	109				vs eth, EtOH
770	Benzoyl peroxide		$C_{14}H_{10}O_4$	94-36-0	242.227	orth (eth), pr	105	exp		1.543	sl H_2O; s EtOH, eth, ace, bz, CS_2
771	1-Benzoylpiperidine		$C_{12}H_{15}NO$	776-75-0	189.253	tcl	49	320.5			i H_2O; s EtOH, eth; sl ctc
772	*N*-Benzoyl-*L*-tyrosine ethyl ester		$C_{18}H_{19}NO_4$	3483-82-7	313.349		119.5				
773	Benzphetamine		$C_{17}H_{21}N$	156-08-1	239.356			$127^{0.02}$		1.5515^{19}	vs eth, EtOH, MeOH, chl
774	Benzpiperylon		$C_{22}H_{25}N_3O$	53-89-4	347.453	cry (al)	182 dec				
775	Benzquinamide		$C_{22}H_{32}N_2O_5$	63-12-7	404.499	cry	131				
776	Benzthiazide		$C_{15}H_{14}ClN_3O_4S_3$	91-33-8	431.938	cry (EtOH)	236				i H_2O; s alk
777	*N*-Benzylacetamide		$C_9H_{11}NO$	588-46-5	149.189		61	157^{2}			vs EtOH, eth
778	Benzyl acetate		$C_9H_{10}O_2$	140-11-4	150.174	liq	-51.3	213	1.0550^{20}	1.5232^{20}	sl H_2O; msc EtOH; s eth, ace, chl
779	Benzyl acrylate		$C_{10}H_{10}O_2$	2495-35-4	162.185			228	1.0573^{20}	1.5143^{20}	i H_2O; s EtOH, eth, ace, ctc
780	Benzyl alcohol	Benzenemethanol	C_7H_8O	100-51-6	108.138	liq	-15.4	205.31	1.0419^{24}	1.5396^{20}	s H_2O, EtOH, eth, ace, bz, MeOH, chl
781	Benzylamine	Benzenemethanamine	C_7H_9N	100-46-9	107.153			185; 90^{12}	0.9813^{20}	1.5401^{20}	msc H_2O, EtOH, eth; vs ace; s bz; sl chl
782	4-(Benzylamino) benzenesulfonamide	*N*4-Benzylsulfanilamide	$C_{13}H_{14}N_2O_2S$	104-22-3	262.327		171				
783	2-[Benzylamino]ethanol		$C_9H_{13}NO$	104-63-2	151.205			$225; 154^{12}$	1.065^{25}	1.5430^{20}	
784	4-Benzylaniline		$C_{13}H_{13}N$	1135-12-2	183.249	mcl (lig)	34.5	300	1.038^{25}		vs eth, EtOH, lig
785	*N*-Benzylaniline	*N*-Phenylbenzenemethanamine	$C_{13}H_{13}N$	103-32-2	183.249	pr	37.5	306.5	1.0298^{65}	1.6118^{25}	vs eth, EtOH
786	α-Benzylbenzenepropanoic acid		$C_{16}H_{16}O_2$	618-68-8	240.297	pl (peth HOAc) nd (w)	90	235^{18}			vs bz, eth, EtOH
787	2-Benzyl-1*H*-benzimidazole	Bendazol	$C_{14}H_{12}N_2$	621-72-7	208.258	nd (bz)	187				vs bz, EtOH, gl HOAc
788	Benzyl benzoate		$C_{14}H_{12}O_2$	120-51-4	212.244	nd or lf	21	323.5	1.1121^{25}	1.5680^{20}	i H_2O; s EtOH, eth, ace, bz, MeOH, chl
789	4-Benzyl-1,1'-biphenyl		$C_{19}H_{16}$	613-42-3	244.330	lf	85	285^{110}	1.171^{0}		i H_2O; s EtOH, ctc; vs eth, bz
790	Benzyl butanoate		$C_{11}H_{14}O_2$	103-37-7	178.228			239	1.0111^{20}	1.4920^{20}	i H_2O; vs EtOH, eth; s ctc
791	Benzyl butyl phthalate	Butyl benzyl phthalate	$C_{19}H_{20}O_4$	85-68-7	312.360	liq		370	1.119^{25}		i H_2O
792	Benzyl chloroacetate		$C_9H_9ClO_2$	140-18-1	184.619			$147^{9}, 85^{0.4}$	1.2223^{4}	1.5426^{18}	vs eth, EtOH
793	Benzyl chloroformate	Carbobenzoxy chloride	$C_8H_7ClO_2$	501-53-1	170.594	oily liq		103^{20}	1.195^{25}	1.5190^{20}	s eth, ace, bz
794	Benzyl *trans*-cinnamate	Benzyl *trans*-3-phenyl-2-propenoate	$C_{16}H_{14}O_2$	78277-23-3	238.281	pr	39	dec 350; 244^{5}	1.109^{15}		i H_2O; s EtOH, eth; sl bz
795	Benzyl dodecanoate	Benzyl laurate	$C_{19}H_{30}O_2$	140-25-0	290.440		8.5	210^{12}	0.9429^{25}	1.4812^{24}	vs bz, eth, EtOH, peth
796	Benzylethylamine	*N*-Ethylbenzenemethanamine	$C_9H_{13}N$	14321-27-8	135.206			194	0.9342^{17}	1.5117^{20}	sl H_2O, ctc; s EtOH, eth, bz, chl
797	*N*-Benzyl-*N*-ethylaniline	Ethylbenzylaniline	$C_{15}H_{17}N$	92-59-1	211.303	pa ye oil	35	$288; 185^{22}$	1.001^{55}	1.5943^{23}	i H_2O; s EtOH, eth, chl
798	Benzyl ethyl ether		$C_9H_{12}O$	539-30-0	136.190			186	0.9478^{20}	1.4955^{20}	i H_2O; msc EtOH, eth
799	Benzyl formate		$C_8H_8O_2$	104-57-4	136.149			$203; 84^{10}$	1.081^{20}	1.5154^{20}	i H_2O; s EtOH, ace; msc eth; sl ctc
800	Benzyl fumarate		$C_{18}H_{16}O_4$	538-64-7	296.318	cry pow	59	210^{5}			vs eth, EtOH, chl
801	Benzylidene diacetate	Toluene-α,α-diol, diacetate	$C_{11}H_{12}O_4$	581-55-5	208.211	pl (eth)	46	220	1.11^{20}		vs bz, eth, EtOH
802	Benzylimidobis(*p*-methoxyphenyl) methane		$C_{22}H_{21}NO_2$	524-96-9	331.408	pa ye cry	90				vs eth, chl
803	2-Benzyl-1*H*-isoindole-1,3(2*H*)-dione		$C_{15}H_{11}NO_2$	2142-01-0	237.254	ye nd (al)	116		1.343^{18}		s EtOH, HOAc; sl DMSO



N-Benzoylglycine



Benzoyl iodide



2-Benzoylmethyl-6(2-hydroxy-2-phenylethyl)-1-methylpiperidine, hydrochloride



3-(Benzoyloxy)-8-methyl-8-azabicyclo[3.2.1]octane-2-carboxylic acid, ethyl ester, [1*R*-(*exo*,*exo*)]



Benzoyl peroxide



1-Benzoylpiperidine



N-Benzoyl-*L*-tyrosine ethyl ester



Benzphetamine



Benzpiperylon



Benzquinamide



Benzthiazide



N-Benzylacetamide



Benzyl acetate



Benzyl acrylate



Benzyl alcohol



Benzylamine



4-(Benzylamino)benzenesulfonamide



2-[Benzylamino]ethanol



4-Benzylaniline



N-Benzylaniline



α-Benzylbenzenepropanoic acid



2-Benzyl-1*H*-benzimidazole



Benzyl benzoate



4-Benzyl-1,1'-biphenyl



Benzyl butanoate



Benzyl butyl phthalate



Benzyl chloroacetate



Benzyl chloroformate



Benzyl *trans*-cinnamate



Benzyl dodecanoate



Benzylethylamine



N-Benzyl-*N*-ethylaniline



Benzyl ethyl ether


Benzyl formate



Benzyl fumarate



Benzylidene diacetate



Benzylimidobis(*p*-methoxyphenyl)methane



2-Benzyl-1*H*-isoindole-1,3(2*H*)-dione


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
804	Benzylisopropylamine	*N*-Isopropylbenzenemethanamine	$C_{10}H_{15}N$	102-97-6	149.233			200; 93[10]	0.892[25]	1.5025[20]	
805	Benzyl isothiocyanate	(Isothiocyanatomethyl)benzene	C_8H_7NS	622-78-6	149.214	ye oil		243	1.1246[16]	1.6049[15]	i H_2O; msc EtOH; s eth
806	Benzyl methacrylate		$C_{11}H_{12}O_2$	2495-37-6	176.212			144[50]			
807	Benzyl 3-methylbutanoate		$C_{12}H_{16}O_2$	103-38-8	192.254			245; 136[25]	0.9983[15]	1.4884[20]	
808	Benzyl methyl ether		$C_8H_{10}O$	538-86-3	122.164	liq	-52.6	170	0.9634[20]	1.5008[20]	i H_2O, lig; vs EtOH, eth; s bz
809	1-Benzyl-2-methylhydrazine	1-Methyl-2-phenylmethylhydrazine	$C_8H_{12}N_2$	10309-79-2	136.194	liq		117[20]			
810	Benzyl 2-methylpropanoate	Benzyl isobutyrate	$C_{11}H_{14}O_2$	103-28-6	178.228			228; 114[20]	1.0159[18]	1.4883[20]	
811	Benzyl nitrite		$C_7H_7NO_2$	935-05-7	137.137	oil		81[35]	1.075[25]	1.4989[25]	
812	*N*-Benzyloxycarbonylaspartame		$C_{22}H_{24}N_2O_7$	33605-72-0	428.435	cry	122				
813	Benzyloxycarbonyl-*L*-glutamine		$C_{13}H_{16}N_2O_5$	2650-64-8	280.276		134.5				s DMSO
814	Benzyloxycarbonylglycine		$C_{10}H_{11}NO_4$	1138-80-3	209.199		121				s ace
815	Benzyloxycarbonylglycyl-*L*-leucine		$C_{16}H_{22}N_2O_5$	1421-69-8	322.356		100				
816	Benzyloxycarbonylglycyl-*L*-phenylalanine		$C_{19}H_{20}N_2O_5$	1170-76-9	356.372		126				
817	2-(Benzyloxy)ethanol	Ethylene glycol monobenzyl ether	$C_9H_{12}O_2$	622-08-2	152.190	oil	<-75	256	1.0640[20]	1.5233[20]	vs H_2O, eth, EtOH
818	Benzylpenicillin sodium		$C_{16}H_{17}N_2NaO_4S$	69-57-8	356.372	nd (BuOH aq)	215		1.41		vs H_2O; s MeOH; i ace, eth, chl
819	2-Benzylphenol	*o*-Benzylphenol	$C_{13}H_{12}O$	28994-41-4	184.233		21	312		1.5994[20]	vs ace, bz, EtOH
820	4-Benzylphenol	*p*-Benzylphenol	$C_{13}H_{12}O$	101-53-1	184.233		84	322			s H_2O, EtOH, eth, bz, ctc, HOAc, chl
821	Benzyl phenyl ether		$C_{13}H_{12}O$	946-80-5	184.233	lf (al)	40	286.5			
822	1-Benzylpiperazine		$C_{11}H_{16}N_2$	2759-28-6	176.258			146[12]		1.5430[28]	s H_2O, EtOH, eth; sl chl
823	1-Benzylpiperidine		$C_{12}H_{17}N$	2905-56-8	175.270			245	0.9625[16]	1.5227[20]	
824	4-Benzylpiperidine		$C_{12}H_{17}N$	31252-42-3	175.270		16.8	270; 150[17]	0.9970[20]	1.5337[25]	i H_2O; s EtOH, eth
825	Benzyl propanoate		$C_{10}H_{12}O_2$	122-63-4	164.201			221	1.0335[20]		
826	2-Benzylpyridine		$C_{12}H_{11}N$	101-82-6	169.222	nd	12.5	277; 149[16]	1.067[0]	1.5785[20]	i H_2O; s EtOH, eth, chl
827	4-Benzylpyridine		$C_{12}H_{11}N$	2116-65-6	169.222		12.4	288; 180[31]	1.0612[20]	1.5818[20]	i H_2O; s EtOH, ctc; vs eth
828	Benzyl 3-pyridinecarboxylate	Benzyl nicotinate	$C_{13}H_{11}NO_2$	94-44-0	213.232			170[3]			
829	1-Benzyl-1*H*-pyrrole		$C_{11}H_{11}N$	2051-97-0	157.212		15	247	1.0183[20]	1.5655[24]	i H_2O; vs EtOH, eth
830	Benzyl 1,2-pyrrolidinedicarboxylate, (*S*)	*N*-(Benzyloxycarbonyl)-*L*-proline	$C_{13}H_{15}NO_4$	1148-11-4	249.263		78.5			1.5310[20]	sl chl
831	Benzyl salicylate		$C_{14}H_{12}O_3$	118-58-1	228.243			320	1.1799[20]	1.5805[20]	sl H_2O; s EtOH, eth, ctc
832	*O*-Benzyl-*L*-serine	3-(Benzyloxy)-*L*-alanine	$C_{10}H_{13}NO_3$	4726-96-9	195.215		218 dec				
833	Benzylsulfonic acid		$C_7H_8O_3S$	100-87-8	172.202	hyg cry					
834	4-[(Benzylsulfonyl)amino]benzoic acid	*p*-(Benzylsulfonamido)benzoic acid	$C_{14}H_{13}NO_4S$	536-95-8	291.323		229.5				vs EtOH
835	(Benzylsulfonyl)benzene		$C_{13}H_{12}O_2S$	3112-88-7	232.298	nd (al)	146		1.1261[153]		i H_2O; sl EtOH, eth, bz
836	(Benzylthio)benzene		$C_{13}H_{12}S$	831-91-4	200.299	lf (al)	43.5	197[27]			i H_2O; s EtOH, eth, con sulf
837	Benzyl thiocyanate	α-Thiocyanatotoluene	C_8H_7NS	3012-37-1	149.214	pr (al)	43	232			i H_2O; s EtOH, eth, chl, CS_2
838	Benzyltrimethylammonium chloride		$C_{10}H_{16}ClN$	56-93-9	185.694		243				vs H_2O; s ace
839	Benzylurea		$C_8H_{10}N_2O$	538-32-9	150.177	nd (al)	148	dec 200			vs ace, EtOH
840	Bephenium chloride		$C_{17}H_{22}ClNO$	13928-81-9	291.816	cry (ace)	135				
841	Berberine		$C_{20}H_{19}NO_5$	2086-83-1	353.369	red-ye nd (w+6) cry (chl)	145				vs eth, EtOH
842	Berberine chloride dihydrate		$C_{20}H_{22}ClNO_6$	633-65-8	407.845	ye cry					
843	Bergenin		$C_{14}H_{16}O_9$	477-90-7	328.272	cry (MeOH)	238				vs H_2O, EtOH
844	Beryllium 2,4-pentanedioate	Beryllium acetylacetonate	$C_{10}H_{14}BeO_4$	10210-64-7	207.228		108	270	1.168[20]		
845	Betaine	1-Carboxy-*N,N,N*-trimethylmethanaminium, inner salt	$C_5H_{11}NO_2$	107-43-7	117.147	pr or lf (al)	293 dec				vs H_2O, MeOH; s EtOH; sl eth, chl
846	Betaine, hydrochloride		$C_5H_{12}ClNO_2$	590-46-5	153.608	mcl cry (al)	227.5				vs H_2O
847	Betamethasone		$C_{22}H_{29}FO_5$	378-44-9	392.460	cry (AcOMe)	232 dec				
848	Bethanidine		$C_{10}H_{15}N_3$	55-73-2	177.246	cry (aq MeOH)	196				



Benzylisopropylamine



Benzyl isothiocyanate



Benzyl methacryalate



Benzyl 3-methylbutanoate



Benzyl methyl ether



1-Benzyl-2-methylhydrazine



Benzyl 2-methylpropanoate



Benzyl nitrite



N-Benzyloxycarbonylaspartame



Benzyloxycarbonyl-*L*-glutamine



Benzyloxycarbonylglycine



Benzyloxycarbonylglycyl-*L*-leucine



Benzyloxycarbonylglycyl-*L*-phenylalanine



2-(Benzyloxy)ethanol



Benzylpenicillin sodium



2-Benzylphenol



4-Benzylphenol



Benzyl phenyl ether



1-Benzylpiperazine



1-Benzylpiperidine



4-Benzylpiperidine



Benzyl propanoate



2-Benzylpyridine



4-Benzylpyridine



Benzyl 3-pyridinecarboxylate



1-Benzyl-1*H*-pyrrole



Benzyl 1,2-pyrrolidinedicarboxylate, (*S*)



Benzyl salicylate



O-Benzyl-*L*-serine



Benzylsulfonic acid



4-[(Benzylsulfonyl)amino]benzoic acid



(Benzylsulfonyl)benzene



(Benzylthio)benzene



Benzyl thiocyanate



Benzyltrimethylammonium chloride



Benzylurea



Bephenium chloride



Berberine



Berberine chloride dihydrate



Bergenin


Beryllium 2,4-pentanedioate



Betaine



Betaine, hydrochloride



Betamethasone



Bethanidine

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
849	Betonicine		$C_7H_{13}NO_3$	515-25-3	159.183	pr (dil al, +1w)	252 dec				vs EtOH
850	Betulaprenol 9	Nonaisoprenol	$C_{45}H_{74}O$	13190-97-1	631.069	oil or cry	41				s chl
851	9,9'-Bianthracene		$C_{28}H_{18}$	1055-23-8	354.443		321.3				
852	Δ2,2'(3*H*,3'H)-Bibenzo[b] thiophene-3,3'-dione	Durindone Red	$C_{16}H_8O_2S_2$	522-75-8	296.364	br nd (xyl) red mcl nd (bz)	359	sub			i H_2O, EtOH; sl chl, CS_2; s bz, xyl
853	Bicyclo[2.2.1]heptane		C_7H_{12}	279-23-2	96.170		87.5	105.3			vs ace, bz, eth, EtOH
854	Bicyclo[4.1.0]heptane	Norcarane	C_7H_{12}	286-08-8	96.170			116.5	0.853^{25}	1.4564^{20}	
855	Bicyclo[2.2.1]heptan-2-one		$C_7H_{10}O$	497-38-1	110.153		89.5	170			
856	Bicyclo[2.2.1]hept-2-ene		C_7H_{10}	498-66-8	94.154		45	96			
857	Bicyclo[2.2.1]hept-5-ene-2-carbonitrile		C_8H_9N	95-11-4	119.164		13	84^{10}	0.999^{25}	1.4885^{20}	
858	Bicyclo[2.2.1]hept-5-ene-2-carboxaldehyde		$C_8H_{10}O$	5453-80-5	122.164			71^{20}	1.018^{25}	1.4893^{20}	
859	Bicyclo[2.2.1]hept-5-ene-2-methanol		$C_8H_{12}O$	95-12-5	124.180			103^{20}			
860	[1,1'-Bicyclohexyl]-2-one	2-Cyclohexylcyclohexanone	$C_{12}H_{20}O$	90-42-6	180.286	liq	-32	264	0.9696^{25}	1.4877^{25}	
861	1,1'-Bicyclopentyl		$C_{10}H_{18}$	1636-39-1	138.250						s ctc, CS_2
862	[1,1'-Bicyclopentyl]-2-ol	2-Hydroxybicyclopentyl	$C_{10}H_{18}O$	4884-25-7	154.249		20	235.5	0.9785^{15}	1.4884^{17}	
863	[1,1'-Bicyclopentyl]-2-one		$C_{10}H_{16}O$	4884-24-6	152.233	liq	-13	232.5	0.9745^{21}	1.4763	
864	Bifenox	Methyl 5-(2,4-dichlorophenoxy) -2-nitrobenzoate	$C_{14}H_9Cl_2NO_5$	42576-02-3	342.131		85				
865	Bifenthrin		$C_{23}H_{22}ClF_3O_2$	82657-04-3	422.868		69		1.2^{125}		
866	Biguanide	Imidodicarbonimidic diamide	$C_2H_7N_5$	56-03-1	101.111	pr or nd (al)	136	dec 142			vs H_2O; s EtOH; i bz, chl
867	Bikhaconitine	3-Deoxypseudaconitine	$C_{36}H_{51}NO_{11}$	6078-26-8	673.790		164				vs eth, EtOH, chl
868	Bilirubin		$C_{33}H_{36}N_4O_6$	635-65-4	584.662	red mcl pr or pl (chl)					i H_2O; sl EtOH, eth; s bz, chl
869	Biliverdine	Dehydrobilirubin	$C_{33}H_{34}N_4O_6$	114-25-0	582.646	dk grn pl or pr (MeOH)	>300				i H_2O; s EtOH, bz; sl eth, chl, CS_2
870	Binapacryl		$C_{15}H_{18}N_2O_6$	485-31-4	322.313		70		1.27^{20}		
871	1,1'-Binaphthalene	1,1'-Binaphthyl	$C_{20}H_{14}$	604-53-5	254.325	(i) pl(HOAc) (ii) orth (peth)	160	>360; 240^{12}	1.3000^{20}		i H_2O; sl EtOH; s eth, ace, bz, CS_2
872	2,2'-Binaphthalene		$C_{20}H_{14}$	612-78-2	254.325	bl flr pl (al)	187.9	452			i H_2O; sl EtOH; s eth, bz, CS_2
873	[1,1'-Binaphthalene]-2,2'-diol		$C_{20}H_{14}O_2$	602-09-5	286.324	nd (al), cry (w)	220				i H_2O; s EtOH, eth, alk; sl chl
874	Biotin	Coenzyme R	$C_{10}H_{16}N_2O_3S$	58-85-5	244.310	nd (w)	232 dec				s H_2O, EtOH; sl eth, chl
875	2,2'-Bioxirane	Diepoxybutane	$C_4H_6O_2$	1464-53-5	86.090		2.0	144	1.113^{20}	1.435^{20}	vs H_2O, EtOH
876	Biphenyl	Diphenyl	$C_{12}H_{10}$	92-52-4	154.207	lf (dil al)	68.93	256.1	1.04^{20}	1.588^{77}	i H_2O; s EtOH, eth; vs bz, ctc, MeOH
877	[1,1'-Biphenyl]-4-acetic acid	Felbinac	$C_{14}H_{12}O_2$	5728-52-9	212.244		160.5				
878	[1,1'-Biphenyl]-4-carbonitrile		$C_{13}H_9N$	2920-38-9	179.217		88	190^{20}			i H_2O; vs EtOH, eth
879	[1,1'-Biphenyl]-4-carbonyl chloride		$C_{13}H_9ClO$	14002-51-8	216.662		111	160^{2}			
880	[1,1'-Biphenyl]-2,2'-diamine		$C_{12}H_{12}N_2$	1454-80-4	184.236	pr or nd (al)	81	162^{4}	1.3090^{20}		s H_2O, ace, bz
881	[1,1'-Biphenyl]-2,4'-diamine		$C_{12}H_{12}N_2$	492-17-1	184.236	nd (dil al)	54.5	363			i H_2O; s EtOH, eth
882	[1,1'-Biphenyl]-4,4'-diamine, dihydrochloride		$C_{12}H_{14}Cl_2N_2$	531-85-1	257.158		>300				
883	[1,1'-Biphenyl]-2,2'-dicarboxylic acid	*o,o'*-Diphenic acid	$C_{14}H_{10}O_4$	482-05-3	242.227	mcl pr or lf (w) cry (HOAc)	233.5	sub			i H_2O; s EtOH, eth
884	[1,1'-Biphenyl]-2,2'-diol		$C_{12}H_{10}O_2$	1806-29-7	186.206		109	320	1.3420^{20}		s H_2O, EtOH, eth, ace, bz; sl peth, chl
885	[1,1'-Biphenyl]-2,5-diol		$C_{12}H_{10}O_2$	1079-21-6	186.206	nd (dil al)	97.5				vs EtOH
886	[1,1'-Biphenyl]-4,4'-diol		$C_{12}H_{10}O_2$	92-88-6	186.206		278 dec				sl H_2O, bz, DMSO; s EtOH, eth
887	[1,1'-Biphenyl]-4,4'-disulfonic acid		$C_{12}H_{10}O_6S_2$	5314-37-4	314.333	pr	72.5	>200			vs H_2O
888	[1,1'-Biphenyl]-3,3',4,4'-tetramine, tetrahydrochloride		$C_{12}H_{18}Cl_4N_4$	7411-49-6	360.110		245 dec				
889	[1,1'-Biphenyl]-3,3',5,5'-tetrol	Diresorcinol	$C_{12}H_{10}O_4$	531-02-2	218.205	pl or nd (w+2)	310				vs H_2O, eth, EtOH


Betonicine


Betulaprenol 9


9,9'-Bianthracene



Δ2,2'(3*H*,3'H)-Bibenzo[b]thiophene-3,3'-dione



Bicyclo[2.2.1]heptane



Bicyclo[4.1.0]heptane



Bicyclo[2.2.1]heptan-2-one



Bicyclo[2.2.1]hept-2-ene



Bicyclo[2.2.1]hept-5-ene-2-carbonitrile



Bicyclo[2.2.1]hept-5-ene-2-carboxaldehyde



Bicyclo[2.2.1]hept-5-ene-2-methanol



[1,1'-Bicyclohexyl]-2-one



1,1'-Bicyclopentyl



[1,1'-Bicyclopentyl]-2-ol



[1,1'-Bicyclopentyl]-2-one



Bifenox



Bifenthrin



Biguanide



Bikhaconitine



Bilirubin



Biliverdine



Binapacryl



1,1'-Binaphthalene



2,2'-Binaphthalene



[1,1'-Binaphthalene]-2,2'-diol



Biotin



2,2'-Bioxirane



Biphenyl



[1,1'-Biphenyl]-4-acetic acid



[1,1'-Biphenyl]-4-carbonitrile



[1,1'-Biphenyl]-4-carbonyl chloride



[1,1'-Biphenyl]-2,2'-diamine



[1,1'-Biphenyl]-2,4'-diamine



[1,1'-Biphenyl]-4,4'-diamine, dihydrochloride



[1,1'-Biphenyl]-2,2'-dicarboxylic acid



[1,1'-Biphenyl]-2,2'-diol


[1,1'-Biphenyl]-2,5-diol



[1,1'-Biphenyl]-4,4'-diol



[1,1'-Biphenyl]-4,4'-disulfonic acid



[1,1'-Biphenyl]-3,3',4,4'-tetramine, tetrahydrochloride



[1,1'-Biphenyl]-3,3',5,5'-tetrol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
890	*N*-[1,1'-Biphenyl]-4-ylacetamide		$C_{14}H_{13}NO$	4075-79-0	211.259	cry (dil MeOH)	172.8				i H_2O; vs EtOH, ace, MeOH
891	1-[1,1'-Biphenyl]-4-ylethanone		$C_{14}H_{12}O$	92-91-1	196.244	pr (ace), cry (al)	121	326	1.251^{0}		i H_2O; vs EtOH, ace; sl chl
892	2-[1,1'-Biphenyl]-4-yl-5-phenyl-1,3,4-oxadiazole		$C_{20}H_{14}N_2O$	852-38-0	298.337		168				
893	2,2'-Bipyridine	α,α'-Dipyridyl	$C_{10}H_8N_2$	366-18-7	156.184	pr (peth)	72	273.5			sl H_2O; vs EtOH, eth, bz, chl
894	2,3'-Bipyridine	2,3'-Bipyridyl	$C_{10}H_8N_2$	581-50-0	156.184			295.5	1.140^{20}	1.6223^{20}	i H_2O; vs EtOH, eth, bz, chl; sl peth
895	2,4'-Bipyridine	2,4'-Bipyridyl	$C_{10}H_8N_2$	581-47-5	156.184		61.5	281			sl H_2O; vs EtOH, eth, chl
896	3,3'-Bipyridine	3,3'-Bipyridyl	$C_{10}H_8N_2$	581-46-4	156.184		68	291.5	1.1614^{20}		vs H_2O, EtOH; sl eth
897	4,4'-Bipyridine	γ,γ'-Dipyridyl	$C_{10}H_8N_2$	553-26-4	156.184	nd (w+2)	114	305			sl H_2O; vs EtOH, bz, chl; s eth
898	2,2'-Biquinoline		$C_{18}H_{12}N_2$	119-91-5	256.301	pl or lf (al)	196				i H_2O; vs EtOH; s eth, ace, bz
899	4,4'-Bis(acetoacetamido)-3,3'-dimethyl-1,1'-biphenyl	*N,N*-Bis(acetoacetyl)-3,3'-dimethylbenzidine	$C_{22}H_{24}N_2O_4$	91-96-3	380.437		212				sl DMSO
900	Bisacodyl		$C_{22}H_{19}NO_4$	603-50-9	361.391		133.5				
901	Bis(4-amino-3-chlorophenyl) methane	4,4-Methylene-bis(2-chloroaniline)	$C_{13}H_{12}Cl_2N_2$	101-14-4	267.153						s ctc
902	Bis(4-aminocyclohexyl)methane		$C_{13}H_{26}N_2$	1761-71-3	210.358		15	320	0.92^{75}		
903	Bis(2-aminoethyl)amine	Diethylenetriamine	$C_4H_{13}N_3$	111-40-0	103.166	ye hyg liq	-39	207	0.9569^{20}	1.4810^{25}	msc H_2O, EtOH; i eth; s lig
904	*N,N'*-Bis(2-aminoethyl)-1,2-ethanediamine	Triethylenetetramine	$C_6H_{18}N_4$	112-24-3	146.234		12	266.5		1.4971^{20}	s H_2O, EtOH, acid
905	Bis(2-aminophenyl)disulfide		$C_{12}H_{12}N_2S_2$	1141-88-4	248.366		93				i H_2O; vs EtOH, eth
906	Bis(4-aminophenyl)disulfide		$C_{12}H_{12}N_2S_2$	722-27-0	248.366		85				s H_2O; vs EtOH, eth, chl; sl bz, lig
907	1,2-Bis(4-aminophenyl)ethane		$C_{14}H_{16}N_2$	621-95-4	212.290	pl (w)	137	sub			i H_2O; vs EtOH
908	Bis(4-aminophenyl) sulfone	Dapsone	$C_{12}H_{12}N_2O_2S$	80-08-0	248.300	cry (95% al)	175.5				s EtOH; sl DMSO
909	Bis(4-aminophenyl) sulfoxide	4,4'-Sulfinyldianiline	$C_{12}H_{12}N_2OS$	119-59-5	232.300	pr (w, al)	175 dec				s H_2O, EtOH
910	1,4-Bis(3-aminopropoxy)butane	1,4-Butanediol bis(3-aminopropyl) ether	$C_{10}H_{24}N_2O_2$	7300-34-7	204.310	liq		135^{3}	0.96^{20}	1.4619^{20}	
911	*N,N'*-Bis(3-aminopropyl)-1,4-butanediamine	Spermine	$C_{10}H_{26}N_4$	71-44-3	202.340		29	150^{5}			
912	*N,N'*-Bis(3-aminopropyl)-1,4-butanediamine, tetrahydrochloride		$C_{10}H_{30}Cl_4N_4$	306-67-2	348.184		301.5				s H_2O
913	Bis(2-bromoethyl) ether	Bromex	$C_4H_8Br_2O$	5414-19-7	231.914			115^{32}, 92^{12}	1.8452^{20}	1.5131^{27}	
914	1,2-Bis(bromomethyl)benzene		$C_8H_8Br_2$	91-13-4	263.958	orth (chl)	95	$129^{4.5}$	1.988^{25}		i H_2O; s EtOH, eth, ctc, chl, peth, lig
915	1,3-Bis(bromomethyl)benzene		$C_8H_8Br_2$	626-15-3	263.958	nd (chl), pr (ace)	77	137^{20}	1.959^{25}		i H_2O; s EtOH, eth, chl, lig
916	1,4-Bis(bromomethyl)benzene		$C_8H_8Br_2$	623-24-5	263.958	mcl pr (al), cry (chl, bz)	144.5	245	2.012^{25}		i H_2O; vs EtOH, chl; sl eth; s bz
917	2,2-Bis(bromomethyl)-1,3-propanediol	Pentaerythritol dibromide	$C_5H_{10}Br_2O_2$	3296-90-0	261.940	nd (bz)	113				
918	1,3-Bis(bromomethyl) tetramethyldisiloxane		$C_6H_{16}Br_2OSi_2$	2351-13-5	320.169			233; 103^{15}	1.3918^{25}	1.4719^{25}	
919	Bis(4-bromophenyl) ether		$C_{12}H_8Br_2O$	2050-47-7	327.999	lf (al)	60.5	339	1.8^{25}		i H_2O; s EtOH, bz; vs eth; sl chl
920	Bis(2-(2-butoxyethoxy)ethyl) adipate		$C_{22}H_{42}O_8$	141-17-3	434.563	liq			1.1^{25}		
921	1,4-Bis(α-(*tert*-butyldioxy) isopropyl)benzene		$C_{20}H_{34}O_4$	2781-00-2	338.482	cry	79				
922	Bis(3-*tert*-butyl-5-ethyl-2-hydroxyphenyl)methane		$C_{25}H_{36}O_2$	88-24-4	368.553	cry	123				
923	Bis(4-chlorobenzoyl) peroxide		$C_{14}H_8Cl_2O_4$	94-17-7	311.118	pr cry (bz)	141				
924	1,2-Bis(2-chloroethoxy)ethane		$C_6H_{12}Cl_2O_2$	112-26-5	187.064			232	1.195^{20}	1.4592^{25}	s ctc
925	Bis(2-chloroethoxy)methane		$C_5H_{10}Cl_2O_2$	111-91-1	173.037			215.0			
926	*N,N*-Bis(2-chloroethyl)aniline	Aniline mustard	$C_{10}H_{13}Cl_2N$	553-27-5	218.123	pr	45	164^{14}			sl eth; s EtOH, MeOH
927	Bis(2-chloroethyl) carbonate		$C_5H_8Cl_2O_3$	623-97-2	187.021		8	241	1.3506^{20}	1.461^{20}	i H_2O
928	Bis(2-chloroethyl) 2-chloroethylphosphonate		$C_6H_{12}Cl_3O_3P$	6294-34-4	269.490			170.2^{5}		1.488^{25}	



N-[1,1'-Biphenyl]-4-ylacetamide



1-[1,1'-Biphenyl]-4-ylethanone



2-[1,1'-Biphenyl]-4-yl-5-phenyl-1,3,4-oxadiazole



2,2'-Bipyridine



2,3'-Bipyridine



2,4'-Bipyridine



3,3'-Bipyridine



4,4'-Bipyridine



2,2'-Biquinoline



4,4'-Bis(acetoacetamido)-3,3'-dimethyl-1,1'-biphenyl



Bisacodyl



Bis(4-amino-3-chlorophenyl)methane



Bis(4-aminocyclohexyl)methane



Bis(2-aminoethyl)amine



N,N'-Bis(2-aminoethyl)-1,2-ethanediamine



Bis(2-aminophenyl)disulfide



Bis(4-aminophenyl)disulfide



1,2-Bis(4-aminophenyl)ethane



Bis(4-aminophenyl) sulfone



Bis(4-aminophenyl) sulfoxide



1,4-Bis(3-aminopropoxy)butane



N,N'-Bis(3-aminopropyl)-1,4-butanediamine



N,N'-Bis(3-aminopropyl)-1,4-butanediamine, tetrahydrochloride 4HCl



Bis(2-bromoethyl) ether



1,2-Bis(bromomethyl)benzene



1,3-Bis(bromomethyl)benzene



1,4-Bis(bromomethyl)benzene



2,2-Bis(bromomethyl)-1,3-propanediol



1,3-Bis(bromomethyl)tetramethyldisiloxane



Bis(4-bromophenyl) ether



Bis(2-(2-butoxyethoxy)ethyl) adipate



1,4-Bis(α-(*tert*-butyldioxy)isopropyl)benzene



Bis(3-*tert*-butyl-5-ethyl-2-hydroxyphenyl)methane



Bis(4-chlorobenzoyl) peroxide


1,2-Bis(2-chloroethoxy)ethane



Bis(2-chloroethoxy)methane



N,N-Bis(2-chloroethyl)aniline



Bis(2-chloroethyl) carbonate



Bis(2-chloroethyl) 2-chloroethylphosphonate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
929	Bis(2-chloroethyl) ether	Dichloroethyl ether	$C_4H_8Cl_2O$	111-44-4	143.012	liq	-51.9	178.5	1.22^{20}	1.451^{20}	i H_2O; s EtOH, eth, ace; msc bz
930	Bis(2-chloroethyl)methylamine hydrochloride	Nitrogen mustard hydrochloride	$C_5H_{12}Cl_3N$	55-86-7	192.515	hyg nd	111.5				
931	*N,N'*-Bis(2-chloroethyl)-*N*-nitrosourea	Carmustine	$C_5H_9Cl_2N_3O_2$	154-93-8	214.049	lt ye pow	31				vs H_2O, EtOH
932	Bis(2-chloroethyl) sulfide	Mustard gas	$C_4H_8Cl_2S$	505-60-2	159.078		13.5	216	1.2741^{20}	1.5313^{20}	
933	1,2-Bis(2-chloroethylsulfonyl) ethane		$C_6H_{12}Cl_2O_4S_2$	3944-87-4	283.193	cry (MeOH/ HOAc)	205				
934	1,2-Bis(chloromethyl)benzene		$C_8H_8Cl_2$	612-12-4	175.056	mcl (lig)	55	239.5	1.393^{25}		i H_2O; vs EtOH, eth, chl; s ctc
935	1,3-Bis(chloromethyl)benzene		$C_8H_8Cl_2$	626-16-4	175.056	cry	34.2	251.5	1.302^{20}		i H_2O; vs EtOH, eth; sl chl
936	1,4-Bis(chloromethyl)benzene		$C_8H_8Cl_2$	623-25-6	175.056	pl (al)	100	dec 245; 135^{16}	1.417^{25}		i H_2O; vs EtOH, eth, ace, chl; sl HOAc
937	Bis(chloromethyl) ether		$C_2H_4Cl_2O$	542-88-1	114.958	liq	-41.5	106	1.323^{15}	1.435^{21}	msc EtOH, eth
938	3,3-Bis(chloromethyl)oxetane		$C_5H_8Cl_2O$	78-71-7	155.022	liq	18.7	101^{27}	1.295^{25}		
939	2,2-Bis(chloromethyl)-1,3-propanediol	Pentaerythritol dichlorohydrin	$C_5H_{10}Cl_2O_2$	2209-86-1	173.037	cry	83	159^{12}			
940	1,3-Bis(chloromethyl) tetramethyldisiloxane		$C_6H_{16}Cl_2OSi_2$	2362-10-9	231.267	liq	-90	204; 92^{21}	1.045^{20}	1.4398^{20}	
941	Bis(4-chlorophenoxy)methane	Di(4-chlorophenoxy)methane	$C_{13}H_{10}Cl_2O_2$	555-89-5	269.123	cry (peth)	70.5	191^{6}			vs ace, bz
942	Bis(4-chlorophenyl) disulfide		$C_{12}H_8Cl_2S_2$	1142-19-4	287.228		72.8				s chl
943	Bis(4-chlorophenyl)ethanedione		$C_{14}H_8Cl_2O_2$	3457-46-3	279.119		197.8				
944	1,1-Bis(4-chlorophenyl)ethanol		$C_{14}H_{12}Cl_2O$	80-06-8	267.150		70				i H_2O, EtOH; s eth, bz
945	1,2-Bis(2-chlorophenyl)-hydrazine	2,2'-Dichlorohydrazobenzene	$C_{12}H_{10}Cl_2N_2$	782-74-1	253.126		87				
946	Bis(4-chlorophenyl)methane		$C_{13}H_{10}Cl_2$	101-76-8	237.124		55.5	188^{18}	1.365^{17}		s EtOH
947	Bis(4-chlorophenyl) sulfone		$C_{12}H_8Cl_2O_2S$	80-07-9	287.162		147.9	250^{10}			sl H_2O; s EtOH, chl
948	*N,N'*-Bis(4-chlorophenyl)thiourea	Di(*p*-chlorophenyl)thiourea	$C_{13}H_{10}Cl_2N_2S$	1220-00-4	297.202	nd	176				
949	1,1-Bis(4-chlorophenyl)-2,2,2-trichloroethanol		$C_{14}H_9Cl_5O$	115-32-2	370.485	cry (petr)	77.5	$180^{0.1}$			i H_2O, os
950	Bis(3-chloropropyl) ether	3-Chloropropyl ether	$C_6H_{12}Cl_2O$	629-36-7	171.064			216; 90.5^{11}	1.136^{20}	1.4158^{20}	s EtOH, eth
951	Bis(2-cyanoethyl) ether		$C_6H_8N_2O$	1656-48-0	124.140			161^{5}, $111^{0.5}$	1.0504^{20}	1.4405^{20}	
952	Bis(2-cyanoethyl) sulfide		$C_6H_8N_2S$	111-97-7	140.206			$163^{1.5}$		1.5047^{20}	
953	Bis(η-cyclopentadienyl)titanium chloride		$C_{10}H_{10}Cl_2Ti$	1271-19-8	248.959	red cry	289	258^{10}	1.60		sl H_2O, bz; s chl, EtOH, tol
954	Bis(η-cyclopentadienyl)zirconium chloride		$C_{10}H_{10}Cl_2Zr$	1291-32-3	292.316			$180^{0.5}$			
955	1,2-Bis(dibromomethyl)benzene		$C_8H_6Br_4$	13209-15-9	421.750	mcl	116.5				sl H_2O; vs chl; i lig
956	Bis(2,4-dichlorobenzoyl) peroxide		$C_{14}H_6Cl_4O_4$	133-14-2	380.008		106				
957	1,3-Bis(dichloromethyl) tetramethyldisiloxane		$C_6H_{14}Cl_4OSi_2$	2943-70-6	300.157			149^{50}, 117^{11}	1.2213^{20}	1.4660^{20}	
958	Bis(2,4-dichlorophenyl)ether	2,2',4,4'-Tetrachlorodiphenyl ether	$C_{12}H_6Cl_4O$	28076-73-5	307.987	cry (eth)	71				
959	4,4'-Bis(diethylamino) benzophenone	Michler's ethyl ketone	$C_{21}H_{28}N_2O$	90-93-7	324.459	lf (al)	95.3				
960	Bis(diethyldithiocarbamate)nickel		$C_{10}H_{20}N_2NiS_4$	14267-17-5	355.232			$202^{0.02}$			
961	Bis(diethyldithiocarbamate)zinc		$C_{10}H_{20}N_2S_4Zn$	14324-55-1	361.948			$178^{0.05}$			
962	Bis(difluoromethyl) ether	Difluoromethyl ether	$C_2H_2F_4O$	1691-17-4	118.030	col gas		2	1.43^{20}		
963	Bis(2-dimethylaminoethyl) ether	2,2'-Oxybis[*N,N*-dimethylethanamine]	$C_8H_{20}N_2O$	3033-62-3	160.257	liq		80^{15}			
964	Bis[4-(dimethylamino)phenyl] methane	Michler's Base	$C_{17}H_{22}N_2$	101-61-1	254.370	pl or tab (al, lig)	91.5	dec 390; 183^{3}			i H_2O; sl EtOH; vs eth, bz; s acid
965	Bis[4-(dimethylamino)phenyl] methanethione	4,4'-Bis(dimethylamino) thiobenzophenone	$C_{17}H_{20}N_2S$	1226-46-6	284.419	pl	204				i H_2O, EtOH, lig; sl eth; s bz, chl, HOAc
966	Bis(4-dimethylaminophenyl) methanol	4,4'-Bis(dimethylamino) benzhydrol	$C_{17}H_{22}N_2O$	119-58-4	270.369		102.0				i H_2O; vs EtOH; s eth, bz, HOAc
967	1,3-Bis(dimethylamino)-2-propanol		$C_7H_{18}N_2O$	5966-51-8	146.230			181.5	0.8788^{20}	1.4418^{20}	vs H_2O
968	4,4'-Bis(dimethylamino) triphenylmethane		$C_{23}H_{26}N_2$	129-73-7	330.465	nd or lf (al, bz)	102				vs bz, eth
969	Bis(dimethyldithiocarbamate) copper		$C_6H_{12}CuN_2S_4$	137-29-1	303.978			$206^{0.01}$			
970	Bis(dimethyldithiocarbamate) nickel		$C_6H_{12}N_2NiS_4$	15521-65-0	299.125			$208^{0.002}$			



Bis(2-chloroethyl) ether



Bis(2-chloroethyl)methylamine hydrochloride



N,N'-Bis(2-chloroethyl)-*N*-nitrosourea



Bis(2-chloroethyl) sulfide



1,2-Bis(2-chloroethylsulfonyl)ethane



1,2-Bis(chloromethyl)benzene



1,3-Bis(chloromethyl)benzene



1,4-Bis(chloromethyl)benzene



Bis(chloromethyl) ether



3,3-Bis(chloromethyl)oxetane



2,2-Bis(chloromethyl)-1,3-propanediol



1,3-Bis(chloromethyl)tetramethyldisiloxane



Bis(4-chlorophenoxy)methane



Bis(4-chlorophenyl) disulfide



Bis(4-chlorophenyl)ethanedione



1,1-Bis(4-chlorophenyl)ethanol



1,2-Bis(2-chlorophenyl)-hydrazine



Bis(4-chlorophenyl)methane



Bis(4-chlorophenyl) sulfone



N,N'-Bis(4-chlorophenyl)thiourea



1,1-Bis(4-chlorophenyl)-2,2,2-trichloroethanol



Bis(3-chloropropyl) ether



Bis(2-cyanoethyl) ether



Bis(2-cyanoethyl) sulfide



Bis(η-cyclopentadienyl)titanium chloride



Bis(η-cyclopentadienyl)zirconium chloride



1,2-Bis(dibromomethyl)benzene



Bis(2,4-dichlorobenzoyl) peroxide



1,3-Bis(dichloromethyl)tetramethyldisiloxane



Bis(2,4-dichlorophenyl)ether



4,4'-Bis(diethylamino)benzophenone



Bis(diethyldithiocarbamate)nickel



Bis(diethyldithiocarbamate)zinc



Bis(difluoromethyl) ether



Bis(2-dimethylaminoethyl) ether



Bis[4-(dimethylamino)phenyl]methane



Bis[4-(dimethylamino)phenyl]methanethione


Bis(4-dimethylaminophenyl)methanol



1,3-Bis(dimethylamino)-2-propanol



4,4'-Bis(dimethylamino)triphenylmethane



Bis(dimethyldithiocarbamate)copper



Bis(dimethyldithiocarbamate)nickel


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
971	2,5-Bis(1,1-dimethylpropyl)-1,4-benzenediol	2,5-Di-*tert*-pentylhydroquinone	$C_{16}H_{26}O_2$	79-74-3	250.376		180				
972	2,4-Bis(1,1-dimethylpropyl) phenol		$C_{16}H_{26}O$	120-95-6	234.376		26.0	169^{22}			
973	1,2-Bis(diphenylphosphino)ethane	Diphos	$C_{26}H_{24}P_2$	1663-45-2	398.417		143.5				
974	1,3-Bis(2,3-epoxypropoxy) benzene	Diglycidyl resorcinol ether	$C_{12}H_{14}O_4$	101-90-6	222.237		42.5	$147^{0.4}$	1.2183^{30}	1.5408^{20}	
975	Bis(2-ethoxyethyl) phthalate		$C_{16}H_{22}O_6$	605-54-9	310.342		34	345	1.1229^{21}		
976	Bis(ethoxymethyl) ether		$C_6H_{14}O_3$	5648-29-3	134.173			140.6			
977	*N,N'*-Bis(4-ethoxyphenyl) ethanimidamide monohydrochloride	Phenacaine hydrochloride	$C_{18}H_{23}ClN_2O_2$	620-99-5	334.841	cry (w+1)	191				vs H_2O, EtOH, chl
978	Bis(ethylenediamine)copper dichloride	Cupriethylenediamine dichloride	$C_4H_{16}Cl_2CuN_4$	15243-01-3	254.649	dk bl cry					s EtOH
979	Bis(2-ethylhexyl) adipate		$C_{22}H_{42}O_4$	103-23-1	370.566		-67.8	214^{5}	0.922^{25}	1.4474^{20}	vs ace, eth, EtOH
980	Bis(2-ethylhexyl)amine		$C_{16}H_{35}N$	106-20-7	241.456			161^{21}			
981	Bis(2-ethylhexyl) azelate		$C_{25}H_{48}O_4$	103-24-2	412.647		-78	237^{5}	0.915^{25}	1.446^{25}	i H_2O; s EtOH, ace, bz; sl ctc
982	Bis(2-ethylhexyl) ether	2,2'-Diethyldihexyl ether	$C_{16}H_{34}O$	10143-60-9	242.440			269; 144^{13}		1.4325^{20}	sl ctc
983	Bis(2-ethylhexyl) phosphate		$C_{16}H_{35}O_4P$	298-07-7	322.420	visc liq		$155^{0.015}$	0.975^{25}		sl H_2O; s bz, hx
984	Bis(2-ethylhexyl) phosphonate	Bis(2-ethylhexyl) phosphite	$C_{16}H_{35}O_3P$	3658-48-8	306.421	liq		150^{1}	0.93^{25}	1.4420^{20}	
985	Bis(2-ethylhexyl) phosphorodithioate		$C_{16}H_{35}O_2PS_2$	5810-88-8	354.552	cry					s bz, hp, chl
986	Bis(2-ethylhexyl) phthalate	Di-*sec*-octyl phthalate	$C_{24}H_{38}O_4$	117-81-7	390.557	liq	-55	384	0.981^{25}	1.4853^{20}	sl ctc
987	Bis(2-ethylhexyl) sebacate		$C_{26}H_{50}O_4$	122-62-3	426.673		-48	256^{5}	0.912^{25}	1.451^{25}	vs ace, bz, EtOH
988	Bis(2-ethylhexyl) sodium sulfosuccinate	Docusate sodium	$C_{20}H_{37}NaO_7S$	577-11-7	444.559	waxy solid					s peth, ctc, eth, ace
989	Bis(2-ethylhexyl) terephthalate		$C_{24}H_{38}O_4$	6422-86-2	390.557			383			
990	2,2-Bis(ethylsulfonyl)butane	Sulfonethylmethane	$C_8H_{18}O_4S_2$	76-20-0	242.357	pl (w)	76	dec	1.199^{85}		s chl
991	Bis[4-(hexyloxy)phenyl]diazene, 1-oxide		$C_{24}H_{34}N_2O_3$	2587-42-0	398.538						s chl
992	*N,N'*-Bis(2-hydroxybenzylidene)-1,2-ethylenediamine	Disalicylidene-1,2-ethanediamine	$C_{16}H_{16}N_2O_2$	94-93-9	268.310		125.5				sl EtOH, eth; s bz, chl
993	Bis(2-hydroxy-3-*tert*-butyl-5-methylphenyl)methane		$C_{23}H_{32}O_2$	119-47-1	340.499	nd (peth)	131				
994	Bis(2-hydroxy-5-chlorophenyl) sulfide	Fenticlor	$C_{12}H_8Cl_2O_2S$	97-24-5	287.162		174				i H_2O; s EtOH, eth, gl HOAc
995	2-[Bis(2-hydroxyethyl)amino] ethanol hydrochloride	Triethanolamine hydrochloride	$C_6H_{16}ClNO_3$	637-39-8	185.649	cry (al)	179.5				vs H_2O
996	*N,N*-Bis(2-hydroxyethyl) butylamine	Butylbis(2-hydroxyethyl)amine	$C_8H_{19}NO_2$	102-79-4	161.243			275; 80^{35}	0.9681^{20}	1.4625^{20}	s chl
997	Bis(2-hydroxyethyl) disulfide		$C_4H_{10}O_2S_2$	1892-29-1	154.251		26	$160^{3.5}$			
998	*N,N*-Bis(2-hydroxyethyl) dodecanamide		$C_{16}H_{33}NO_3$	120-40-1	287.438	waxy solid	38.7				
999	*N,N*-Bis(2-hydroxyethyl) ethylamine	*N*-Ethyldiethanolamine	$C_6H_{15}NO_2$	139-87-7	133.189	ye liq	-50	247	1.0135^{20}	1.4663^{20}	vs H_2O, EtOH; sl eth
1000	*N,N'*-Bis(2-hydroxyethyl) ethylenediamine		$C_6H_{16}N_2O_2$	4439-20-7	148.203		97.5	136^{1}			s H_2O
1001	*N,N*-Bis(2-hydroxyethyl)glycine	Bicine	$C_6H_{13}NO_4$	150-25-4	163.172	nd (al)	194 dec				vs H_2O; i EtOH
1002	Bis(2-hydroxyethyl)methylamine	Methyldiethanolamine	$C_5H_{13}NO_2$	105-59-9	119.163	liq	-21	247	1.043^{25}	1.4685^{20}	vs H_2O
1003	*N,N*-Bis(2-hydroxyethyl)-3-methylaniline	Diethanol-*m*-toluidine	$C_{11}H_{17}NO_2$	91-99-6	195.259		64.5	160^{1}			sl chl
1004	*N,N*-Bis(2-hydroxyethyl)-1,3-propanediamine	3-(Aminopropyl)diethanolamine	$C_7H_{18}N_2O_2$	4985-85-7	162.230			160^{1}			
1005	Bis(2-hydroxyethyl) sulfide	2,2'-Thiodiethanol	$C_4H_{10}O_2S$	111-48-8	122.186	liq	-10.2	282	1.1793^{25}	1.5211^{20}	msc H_2O, EtOH, chl, AcOEt; s eth; sl bz
1006	Bis(2-hydroxyethyl) terephthalate	Bis(2-hydroxyethyl) 1,4-benzenedicarboxylate	$C_{12}H_{14}O_6$	959-26-2	254.235	cry (w)	109.5				
1007	1,2-Bis(2-hydroxyethylthio)ethane		$C_6H_{14}O_2S_2$	5244-34-8	182.304		64.8	$170^{0.5}$			s H_2O, EtOH, bz, peth
1008	Bis(2-hydroxy-4-methoxyphenyl) methanone	2,2'-Dihydroxy-4,4'-dimethoxybenzophenone	$C_{15}H_{14}O_5$	131-54-4	274.269		139.5				
1009	1,3-Bis(hydroxymethyl)-2-imidazolidone	1,3-Dimethylolethyleneurea	$C_5H_{10}N_2O_3$	136-84-5	146.144	cry (MeOH)	101				
1010	2,2-Bis(4-hydroxy-3-methylphenyl)propane	Bisphenol C	$C_{17}H_{20}O_2$	79-97-0	256.340	nd (xyl)	140				
1011	2,2-Bis(hydroxymethyl)-1,3-propanediol, tetra(2-propenoyl) ester	Pentaerythritol tetraacrylate	$C_{17}H_{20}O_8$	4986-89-4	352.336		17.3		1.185^{25}		
1012	2,2-Bis(hydroxymethyl)-1,3-propanediol, tri(2-propenoyl) ester	Pentaerythritol triacrylate	$C_{14}H_{18}O_7$	3524-68-3	298.289				1.180^{20}		



2,5-Bis(1,1-dimethylpropyl)-1,4-benzenediol



2,4-Bis(1,1-dimethylpropyl)phenol



1,2-Bis(diphenylphosphino)ethane



1,3-Bis(2,3-epoxypropoxy)benzene



Bis(2-ethoxyethyl) phthalate



Bis(ethoxymethyl) ether



N,N'-Bis(4-ethoxyphenyl)ethanimidamide monohydrochloride



Bis(ethylenediamine)copper dichloride



Bis(2-ethylhexyl) adipate



Bis(2-ethylhexyl)amine



Bis(2-ethylhexyl) azelate



Bis(2-ethylhexyl) ether



Bis(2-ethylhexyl) phosphate



Bis(2-ethylhexyl) phosphonate



Bis(2-ethylhexyl) phosphorodithioate



Bis(2-ethylhexyl) phthalate



Bis(2-ethylhexyl) sebacate



Bis(2-ethylhexyl) sodium sulfosuccinate



Bis(2-ethylhexyl) terephthalate



2,2-Bis(ethylsulfonyl)butane



Bis[4-(hexyloxy)phenyl]diazene, 1-oxide



N,N'-Bis(2-hydroxybenzylidene)-1,2-ethylenediamine



Bis(2-hydroxy-3-*tert*-butyl-5-methylphenyl)methane



Bis(2-hydroxy-5-chlorophenyl) sulfide



2-[Bis(2-hydroxyethyl)amino]ethanol hydrochloride



N,N-Bis(2-hydroxyethyl)butylamine



Bis(2-hydroxyethyl) disulfide



N,N-Bis(2-hydroxyethyl)dodecanamide



N,N-Bis(2-hydroxyethyl)ethylamine



N,N'-Bis(2-hydroxyethyl)ethylenediamine



N,N-Bis(2-hydroxyethyl)glycine



Bis(2-hydroxyethyl)methylamine



N,N-Bis(2-hydroxyethyl)-3-methylaniline



N,N-Bis(2-hydroxyethyl)-1,3-propanediamine



Bis(2-hydroxyethyl) sulfide



Bis(2-hydroxyethyl) terephthalate



1,2-Bis(2-hydroxyethylthio)ethane


Bis(2-hydroxy-4-methoxyphenyl)methanone



1,3-Bis(hydroxymethyl)-2-imidazolidone



2,2-Bis(4-hydroxy-3-methylphenyl)propane



2,2-Bis(hydroxymethyl)-1,3-propanediol, tetra(2-propenoyl) ester



2,2-Bis(hydroxymethyl)-1,3-propanediol, tri(2-propenoyl) ester


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1013	2,2-Bis(4-hydroxyphenyl)butane	Bisphenol B	$C_{16}H_{18}O_2$	77-40-7	242.313		120.5				vs ace, MeOH
1014	Bis(4-hydroxyphenyl)methane	Bisphenol AD	$C_{13}H_{12}O_2$	620-92-8	200.233		162.5	sub			s EtOH, eth, chl, alk; sl DMSO; i CS_2
1015	2,2-Bis(4-hydroxyphenyl)propane	Bisphenol A	$C_{15}H_{16}O_2$	80-05-7	228.287	cry or fl	153	220[4], 222[3]			i H_2O; vs EtOH, eth, bz, alk; s HOAc
1016	2,2-Bis(4-hydroxyphenyl)propane dimethacrylate	Bisphenol A dimethacrylate	$C_{23}H_{24}O_4$	3253-39-2	364.435		73				
1017	Bis(4-hydroxyphenyl) sulfone	Bisphenol S	$C_{12}H_{10}O_4S$	80-09-1	250.270	nd (w), orth bipym	240.5		1.3663[15]		i H_2O; s EtOH, eth; sl bz, DMSO
1018	Bis(2-mercaptoethyl) sulfide	2,2'-Dimercaptodiethyl sulfide	$C_4H_{10}S_3$	3570-55-6	154.317		-11	135[18]	1.183[25]	1.5982[20]	
1019	Bis(2-methallyl) carbonate		$C_9H_{14}O_3$	64057-79-0	170.205		201.3	66[3]	0.943[25]	1.4371[20]	
1020	Bis(2-methoxyethyl)amine	2-Methoxy-*N*-(2-methoxyethyl) ethanamine	$C_6H_{15}NO_2$	111-95-5	133.189						s ctc
1021	Bis(4-methoxyphenyl)diazene, 1-oxide		$C_{14}H_{14}N_2O_3$	1562-94-3	258.272	ye nd (al)			1.1711[11]		s EtOH, ace, bz; sl chl
1022	Bis(4-methoxyphenyl)ethanedione		$C_{16}H_{14}O_4$	1226-42-2	270.280		133				sl EtOH, chl
1023	1,4-Bis(methylamino)-9,10-anthracenedione		$C_{16}H_{14}N_2O_2$	2475-44-7	266.294						sl chl
1024	1,3-Bis(1-methylethenyl)benzene	1,3-Diisopropenylbenzene	$C_{12}H_{14}$	3748-13-8	158.239	liq		231	0.925	1.5570[20]	
1025	Bis(4-methylphenyl) disulfide	Di-*p*-Tolyl disulfide	$C_{14}H_{14}S_2$	103-19-5	246.391	nd or lf (al)	47.5	212[20]	1.114[51]		i H_2O; s EtOH, ace; vs eth
1026	Bis(4-methylphenyl) ether	*p*-Tolyl ether	$C_{14}H_{14}O$	1579-40-4	198.260		51	285			vs bz, eth, EtOH
1027	Bis(1-methyl-1-phenylethyl) peroxide	Dicumyl peroxide	$C_{18}H_{22}O_2$	80-43-3	270.367	cry (EtOH)	40	100[0.2]			
1028	Bis(4-methylphenyl)mercury	Di-*p*-tolylmercury	$C_{14}H_{14}Hg$	537-64-4	382.85		245.7				
1029	1,4-Bis(4-methyl-5-phenyloxazol-2-yl)benzene	2,2'-*p*-Phenylenebis(4-methyl-5-phenyloxazole)	$C_{26}H_{20}N_2O_2$	3073-87-8	392.449		232				sl chl
1030	Bis(4-methylphenyl) sulfide	Di-*p*-tolyl sulfide	$C_{14}H_{14}S$	620-94-0	214.326	nd (al)	57.3	>300; 175[16]			i H_2O; s EtOH, ace, bz, HOAc; sl chl
1031	Bis(4-methylphenyl) sulfone	Di-*p*-tolyl sulfone	$C_{14}H_{14}O_2S$	599-66-6	246.325	pr(bz), nd(w,al)	159	406			sl H_2O, eth; s EtOH, bz, chl, CS_2
1032	*N,N'*-Bis(2-methylphenyl)thiourea		$C_{15}H_{16}N_2S$	137-97-3	256.366	nd (al, sub)					vs bz, EtOH, chl
1033	1,3-Bis(1-methyl-4-piperidyl) propane		$C_{15}H_{30}N_2$	64168-11-2	238.412		13.7	215[50]	0.8962[25]	1.4804[25]	
1034	Bis(methylthio)methane		$C_3H_8S_2$	1618-26-4	108.226			148			
1035	1,2-Bis(*N*-morpholino)ethane		$C_{10}H_{20}N_2O_2$	1723-94-0	200.278	wh-ye (eth,lig)	75	285; 160[25]			vs H_2O, ace, bz, EtOH
1036	Bismuth acetate		$C_6H_9BiO_6$	22306-37-2	386.111	col tablets	250				i H_2O
1037	Bismuth subsalicylate		$C_7H_5BiO_4$	14882-18-9	362.093	pr					i H_2O, EtOH; reac alk
1038	Bis(2-nitrophenyl) disulfide		$C_{12}H_8N_2O_4S_2$	1155-00-6	308.333		198.5				i H_2O, eth; sl EtOH, ace, bz, HOAc
1039	Bis(3-nitrophenyl) disulfide	Nitrophenide	$C_{12}H_8N_2O_4S_2$	537-91-7	308.333		84				sl EtOH, chl; s eth
1040	Bis(4-nitrophenyl) disulfide		$C_{12}H_8N_2O_4S_2$	100-32-3	308.333		182	255[0.1]			sl EtOH, HOAc
1041	1,2-Bis(4-nitrophenyl)ethane	4,4'-Dinitrobibenzyl	$C_{14}H_{12}N_2O_4$	736-30-1	272.256	ye nd (al,bz)	181.8				i EtOH; sl eth, bz, chl, HOAc
1042	*N,N'*-Bis(4-nitrophenyl)urea	4,4'-Dinitrocarbanilide	$C_{13}H_{10}N_4O_5$	587-90-6	302.242		312 dec				
1043	Bis(2,4-pentanedionato)cobalt	Cobalt(II) bis(acetylacetonate)	$C_{10}H_{14}CoO_4$	14024-48-7	257.149	bl-viol cry	167				
1044	Bis(1-phenylethyl)amine		$C_{16}H_{19}N$	10024-74-5	225.329			296.5	1.018[15]	1.573	
1045	1,2-Bis(2,4,6-tribromophenoxy) ethane		$C_{14}H_8Br_6O_2$	37853-59-1	687.637	nd (bz/EtOH)	222				
1046	*N,N'*-Bis(2,2,2-trichloro-1-hydroxyethyl)urea		$C_5H_6Cl_6N_2O_3$	116-52-9	354.831		196				vs ace, EtOH
1047	1,4-Bis(trichloromethyl)benzene		$C_8H_4Cl_6$	68-36-0	312.836	cry (bz, eth)	109				s chl
1048	Bis(trichloromethyl) carbonate	Triphosgene	$C_3Cl_6O_3$	32315-10-9	296.748	cry (eth, peth)	79	203	1.6290[80]		
1049	Bis(tridecyl) thiodipropanoate	Ditridecyl thiodipropionate	$C_{32}H_{62}O_4S$	10595-72-9	542.897			265[0.25]			vs EtOH
1050	3,5-Bis(trifluoromethyl)aniline		$C_8H_5F_6N$	328-74-5	229.123			85[15], 76[10]	1.487[25]	1.4335[20]	
1051	1,3-Bis(trifluoromethyl)benzene		$C_8H_4F_6$	402-31-3	214.108			116	1.3790[25]	1.3916[25]	i H_2O
1052	1,4-Bis(trifluoromethyl)benzene		$C_8H_4F_6$	433-19-2	214.108	liq		115			
1053	Bis(trifluoromethyl) disulfide		$C_2F_6S_2$	372-64-5	202.141			34.6			vs EtOH, peth
1054	1,2-Bis(trimethylsilyl)acetylene		$C_8H_{18}Si_2$	14630-40-1	170.400		26	134	0.770[20]	1.413[20]	
1055	Bis(2,4,6-trinitrophenyl) sulfide	Dipicryl sulfide	$C_{12}H_4N_6O_{12}S$	2217-06-3	456.258	ye cry	230	exp			
1056	Bis[2-(vinyloxy)ethyl] ether	Diethylene glycol divinyl ether	$C_8H_{14}O_3$	764-99-8	158.195			81[10]			
1057	Bithionol		$C_{12}H_6Cl_4O_2S$	97-18-7	356.052		188		1.73[25]		vs ace



2,2-Bis(4-hydroxyphenyl)butane



Bis(4-hydroxyphenyl)methane



2,2-Bis(4-hydroxyphenyl)propane



2,2-Bis(4-hydroxyphenyl)propane dimethacrylate



Bis(4-hydroxyphenyl) sulfone



Bis(2-mercaptoethyl) sulfide



Bis(2-methallyl) carbonate



Bis(2-methoxyethyl)amine



Bis(4-methoxyphenyl)diazene, 1-oxide



Bis(4-methoxyphenyl)ethanedione



1,4-Bis(methylamino)-9,10-anthracenedione



1,3-Bis(1-methylethenyl)benzene



Bis(4-methylphenyl) disulfide



Bis(4-methylphenyl) ether



Bis(1-methyl-1-phenylethyl)peroxide



Bis(4-methylphenyl)mercury


1,4-Bis(4-methyl-5-phenyloxazol-2-yl)benzene



Bis(4-methylphenyl) sulfide



Bis(4-methylphenyl) sulfone



N,N'-Bis(2-methylphenyl)thiourea



1,3-Bis(1-methyl-4-piperidyl)propane


Bis(methylthio)methane



1,2-Bis(*N*-morpholino)ethane



Bismuth acetate



Bismuth subsalicylate



Bis(2-nitrophenyl) disulfide



Bis(3-nitrophenyl) disulfide



Bis(4-nitrophenyl) disulfide



1,2-Bis(4-nitrophenyl)ethane



N,N'-Bis(4-nitrophenyl)urea



Bis(2,4-pentanedionato)cobalt



Bis(1-phenylethyl)amine



1,2-Bis(2,4,6-tribromophenoxy)ethane



N,N'-Bis(2,2,2-trichloro-1-hydroxyethyl)urea



1,4-Bis(trichloromethyl)benzene



Bis(trichloromethyl) carbonate



Bis(tridecyl) thiodipropanoate



3,5-Bis(trifluoromethyl)aniline



1,3-Bis(trifluoromethyl)benzene



1,4-Bis(trifluoromethyl)benzene


Bis(trifluoromethyl) disulfide



1,2-Bis(trimethylsilyl)acetylene



Bis(2,4,6-trinitrophenyl) sulfide



Bis[2-(vinyloxy)ethyl] ether



Bithionol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1058	2,2'-Bithiophene		$C_8H_6S_2$	492-97-7	166.264		33	260			i H_2O; vs EtOH; s eth, ctc, HOAc
1059	Bixin		$C_{25}H_{30}O_4$	6983-79-5	394.504	viol pr (ace)	198				i H_2O; s EtOH, ace; sl eth, bz, HOAc
1060	Boldenone	Dehydrotestosterone	$C_{19}H_{26}O_2$	846-48-0	286.408		165				
1061	Boldine		$C_{19}H_{21}NO_4$	476-70-0	327.375	cry (eth)	163				vs EtOH, chl
1062	Bomyl		$C_9H_{15}O_8P$	122-10-1	282.184	ye oil		160[17]			sl H_2O; vs ace, EtOH, xyl
1063	Borane carbonyl		CH_3BO	13205-44-2	41.845	col gas	-137	-64			dec H_2O
1064	Borneol, (±)		$C_{10}H_{18}O$	6627-72-1	154.249	lf (lig)	208	sub	1.011[20]		i H_2O; vs EtOH, eth, bz
1065	*l*-Bornyl acetate		$C_{12}H_{20}O_2$	5655-61-8	196.286		27	223.5	0.982[25]	1.4626[20]	sl H_2O; s EtOH, eth
1066	Bornylamine		$C_{10}H_{19}N$	32511-34-5	153.265		163				vs ace, bz, eth, EtOH
1067	Bornyl chloride	2-Chloro-1,7,7-trimethylbicyclo[2.2.1]heptane, *endo*	$C_{10}H_{17}Cl$	464-41-5	172.695	nd	132	207.5			vs bz, eth, EtOH, peth
1068	Bornyl 3-methylbutanoate, (1*R*)	*d*-Bornyl isovalerate	$C_{15}H_{26}O_2$	53022-14-3	238.366			257.5	0.955[25]		vs eth, EtOH
1069	Boron trifluoride - dimethyl ether complex		$C_2H_6BF_3O$	353-42-4	113.874		-14	dec 127	1.2410[20]	1.302[20]	
1070	Boron trifluoride etherate		$C_4H_{10}BF_3O$	109-63-7	141.927	liq	-60.4	125.5	1.125[25]	1.348[20]	dec H_2O; vs eth, EtOH
1071	Brilliant Green		$C_{27}H_{34}N_2O_4S$	633-03-4	482.635	small gold cry					vs H_2O, EtOH
1072	Brilliant Yellow		$C_{26}H_{20}N_4Na_2O_8S_2$	3051-11-4	626.569	ye cry (w)					s H_2O, EtOH; sl ace
1073	Brodifacoum		$C_{31}H_{23}BrO_3$	56073-10-0	523.417	off-wh pow	230				i H_2O; sl EtOH, bz; s ace, chl
1074	Bromacil	5-Bromo-3-*sec*-butyl-6-methyluracil	$C_9H_{13}BrN_2O_2$	314-40-9	261.115		158		1.55[25]		
1075	Bromadiolone		$C_{30}H_{23}BrO_4$	28772-56-7	527.406	ye-wh pow	205				vs DMF; sl ace, chl, EtOH, eth; i hx
1076	Bromal hydrate		$C_2H_3Br_3O_2$	507-42-6	298.756	mcl pr (w+1)	53.5	dec	2.5661[40]		vs eth, EtOH
1077	Bromdian	Tetrabromobisphenol A	$C_{15}H_{12}Br_4O_2$	79-94-7	543.871		179				s EtOH, eth, bz, chl
1078	*N*-Bromoacetamide		C_2H_4BrNO	79-15-2	137.963	nd (chl-hx)	103.5				vs eth
1079	Bromoacetic acid		$C_2H_3BrO_2$	79-08-3	138.948	hex or orth cry	50	208	1.9335[50]	1.4804[50]	msc H_2O, EtOH, eth; s ace, bz; sl chl
1080	Bromoacetone		C_3H_5BrO	598-31-2	136.975	liq	-36.5	138; 31.5[8]	1.634[23]	1.4697[15]	sl H_2O; s EtOH, eth, ace
1081	α-Bromoacetophenone	ω-Bromoacetophenone	C_8H_7BrO	70-11-1	199.045	nd (al) orth pr (al) pl(peth)	50.5	135[18]	1.647[20]		i H_2O; s EtOH, peth; vs eth, bz, chl
1082	4-(Bromoacetyl)biphenyl	2-Bromo-4'-phenylacetophenone	$C_{14}H_{11}BrO$	135-73-9	275.140	nd (95% al)	127				
1083	Bromoacetyl bromide		$C_2H_2Br_2O$	598-21-0	201.844			148.5	2.312[22]	1.5449[20]	s ace, ctc
1084	Bromoacetylene		C_2HBr	593-61-3	104.933	col gas		4.7			vs eth
1085	5-(2-Bromoallyl)-5-*sec*-butylbarbituric acid	Butallylonal	$C_{11}H_{15}BrN_2O_3$	1142-70-7	303.152		131.5				vs eth, EtOH
1086	5-(2-Bromoallyl)-5-isopropylbarbituric acid	Propallylonal	$C_{10}H_{13}BrN_2O_3$	545-93-7	289.125	cry (dil HOAc, dil al)	181				sl H_2O, eth, bz; vs EtOH, ace, HOAc
1087	2-Bromoaniline		C_6H_6BrN	615-36-1	172.023		32	229	1.578[20]	1.6113[20]	i H_2O; s EtOH, eth
1088	3-Bromoaniline		C_6H_6BrN	591-19-5	172.023		18.5	251	1.5793[20]	1.6260[20]	sl H_2O; s EtOH, eth
1089	4-Bromoaniline		C_6H_6BrN	106-40-1	172.023	orth bipym nd (60% al)	66.4	dec	1.4970[100]		i H_2O; s EtOH, eth; sl chl
1090	2-Bromoanisole		C_7H_7BrO	578-57-4	187.034		1.3	216	1.5018[20]	1.5727[20]	i H_2O; vs EtOH, eth
1091	3-Bromoanisole		C_7H_7BrO	2398-37-0	187.034			211; 105[16]		1.5635[20]	i H_2O; s EtOH, eth, bz, CS_2
1092	4-Bromoanisole		C_7H_7BrO	104-92-7	187.034		13.5	215	1.4564[20]	1.5642[20]	sl H_2O; vs EtOH, eth, chl; s ctc
1093	2-Bromobenzaldehyde		C_7H_5BrO	6630-33-7	185.018		21.5	230		1.5925[20]	i H_2O; vs EtOH, bz; sl ctc
1094	3-Bromobenzaldehyde		C_7H_5BrO	3132-99-8	185.018			234		1.5935[20]	i H_2O; vs EtOH, eth; sl ctc
1095	4-Bromobenzaldehyde		C_7H_5BrO	1122-91-4	185.018	lf (dil al)	58	67[2]			i H_2O; vs EtOH, bz; sl chl


2,2'-Bithiophene



Bixin



Boldenone



Boldine



Bomyl



Borane carbonyl


Borneol, (±)



l-Bornyl acetate



Bornylamine



Bornyl chloride



Bornyl 3-methylbutanoate, (1*R*)



Boron trifluoride - dimethyl ether complex



Boron trifluoride etherate



Brilliant Green



Brilliant Yellow


Brodifacoum



Bromacil


Bromadiolone



Bromal hydrate



Bromdian



N-Bromoacetamide


Bromoacetic acid



Bromoacetone



α-Bromoacetophenone


4-(Bromoacetyl)biphenyl



Bromoacetyl bromide



Bromoacetylene



5-(2-Bromoallyl)-5-*sec*-butylbarbituric acid



5-(2-Bromoallyl)-5-isopropylbarbituric acid



2-Bromoaniline



3-Bromoaniline



4-Bromoaniline



2-Bromoanisole


3-Bromoanisole



4-Bromoanisole



2-Bromobenzaldehyde



3-Bromobenzaldehyde



4-Bromobenzaldehyde


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1096	Bromobenzene	Phenyl bromide	C_6H_5Br	108-86-1	157.008	liq	-30.72	156.06	1.4950^{20}	1.5597^{20}	i H_2O; vs EtOH, eth, bz; s ctc
1097	4-Bromobenzeneacetic acid		$C_8H_7BrO_2$	1878-68-8	215.045	nd (w)	116	sub			sl H_2O; vs EtOH, eth, CS_2
1098	4-Bromobenzeneacetonitrile		C_8H_6BrN	16532-79-9	196.045	pa ye cry (al)	48.0				vs bz, EtOH
1099	α-Bromobenzeneacetonitrile	α-Bromobenzyl cyanide	C_8H_6BrN	5798-79-8	196.045	ye cry (dil al)	29	dec 242; 133^{12}	1.539^{29}		i H_2O; vs EtOH, eth, ace, bz, chl
1100	2-Bromo-1,4-benzenediol		$C_6H_5BrO_2$	583-69-7	189.007	lf (lig), cry (chl)	111.5	sub			vs H_2O, EtOH, eth, bz; sl chl, lig; s HOAc
1101	4-Bromobenzenesulfonyl chloride	*p*-Brosyl chloride	$C_6H_4BrClO_2S$	98-58-8	255.517	tcl or mcl pl (eth)	76	153^{15}			i H_2O; vs eth; s chl
1102	4-Bromobenzenethiol		C_6H_5BrS	106-53-6	189.073	lf (al)	73	230.5	1.5260^{83}		sl H_2O, EtOH; vs eth, ctc, chl
1103	2-Bromobenzoic acid		$C_7H_5BrO_2$	88-65-3	201.018	mcl pr (w), nd	150	sub	1.929^{25}		sl H_2O, DMSO; s EtOH, eth, ace, chl
1104	3-Bromobenzoic acid		$C_7H_5BrO_2$	585-76-2	201.018	mcl nd (dil al)	155	>280	1.845^{20}		i H_2O; s EtOH, eth
1105	4-Bromobenzoic acid		$C_7H_5BrO_2$	586-76-5	201.018	nd (eth), lf (w), mcl pr	254.5		1.894^{20}		sl H_2O, DMSO; s EtOH, eth
1106	2-Bromobenzonitrile		C_7H_4BrN	2042-37-7	182.018	nd (w)	55.5	252			s H_2O; vs EtOH; sl chl
1107	3-Bromobenzonitrile		C_7H_4BrN	6952-59-6	182.018		39.5	225			vs EtOH, eth; sl chl
1108	4-Bromobenzonitrile		C_7H_4BrN	623-00-7	182.018	nd (w, al)	114	236			s H_2O, EtOH, eth, chl
1109	6-Bromobenzo[a]pyrene		$C_{20}H_{11}Br$	21248-00-0	331.205	cry (ace/ MeOH)	223				
1110	2-Bromobenzoyl chloride		C_7H_4BrClO	7154-66-7	219.463	nd	11	243		1.5963^{20}	sl ctc
1111	4-Bromobenzoyl chloride		C_7H_4BrClO	586-75-4	219.463	nd (peth)	42	246; 181^{125}			vs EtOH, eth, bz, lig
1112	2-Bromobiphenyl		$C_{12}H_9Br$	2052-07-5	233.103		0.8	297	1.2175^{26}	1.6248^{25}	vs eth, EtOH
1113	3-Bromobiphenyl		$C_{12}H_9Br$	2113-57-7	233.103			300; 171^{17}		1.6411^{20}	i H_2O
1114	4-Bromobiphenyl		$C_{12}H_9Br$	92-66-0	233.103	pl (al)	91.5	310	0.9327^{25}		i H_2O; s EtOH, eth, bz, HOAc; sl chl
1115	1-Bromo-2-(bromomethyl) benzene		$C_7H_6Br_2$	3433-80-5	249.931	cry (al, lig)	31	129^{19}			vs eth, EtOH, HOAc
1116	1-Bromo-3-(bromomethyl) benzene		$C_7H_6Br_2$	823-78-9	249.931	nd or lf	42	122^{12}			s chl
1117	1-Bromo-4-(bromomethyl) benzene	*p*-Bromobenzyl bromide	$C_7H_6Br_2$	589-15-1	249.931	nd (al)	63				sl H_2O; s EtOH, bz, chl; vs eth, CS_2
1118	2-Bromo-2-(bromomethyl) pentanedinitrile	1,2-Dibromo-2,4-dicyanobutane	$C_6H_6Br_2N_2$	35691-65-7	265.933		52				i H_2O; vs ace, bz, DMF
1119	2-Bromo-1-(4-bromophenyl) ethanone	*p*-Bromophenacyl bromide	$C_8H_6Br_2O$	99-73-0	277.941	nd (al)	111				i H_2O; s EtOH, eth, chl
1120	2-Bromo-1,3-butadiene		C_4H_5Br	1822-86-2	132.987			42^{165}	1.397^{20}	1.4988^{20}	vs eth, EtOH
1121	1-Bromobutane	Butyl bromide	C_4H_9Br	109-65-9	137.018	liq	-112.6	101.6	1.2758^{20}	1.4401^{20}	i H_2O; msc EtOH, eth, ace; sl ctc; s chl
1122	2-Bromobutane, (±)	(±)-*sec*-Butyl bromide	C_4H_9Br	5787-31-5	137.018	liq	-112.65	91.3	1.2585^{20}	1.4366^{20}	vs ace, eth, chl
1123	Bromobutanedioic acid, (±)	Bromosuccinic acid	$C_4H_5BrO_4$	584-98-5	196.985		161		2.073^{25}		s H_2O, EtOH; sl HOAc
1124	4-Bromobutanenitrile		C_4H_6BrN	5332-06-9	148.002			206	1.4967^{20}	1.4818^{20}	s EtOH, eth, chl
1125	2-Bromobutanoic acid, (±)	*DL*-α-Bromobutyric acid	$C_4H_7BrO_2$	2385-70-8	167.002		-2.0	dec 217; 127^{25}	1.5641^{20}		s H_2O, EtOH, eth
1126	4-Bromobutanoic acid		$C_4H_7BrO_2$	2623-87-2	167.002		33	142^{25}, 125^{7}			
1127	3-Bromo-2-butanone		C_4H_7BrO	814-75-5	151.002			36^{11}			
1128	*cis*-1-Bromo-1-butene		C_4H_7Br	31849-78-2	135.003			86.1	1.3265^{15}	1.4536^{20}	i H_2O; s eth, ace, bz, chl; sl ctc
1129	*trans*-1-Bromo-1-butene		C_4H_7Br	32620-08-9	135.003	liq	-100.3	94.7	1.3209^{15}	1.4527^{20}	i H_2O; s eth, ace, bz, chl; sl ctc
1130	2-Bromo-1-butene		C_4H_7Br	23074-36-4	135.003	liq	-133.4	88	1.3209^{15}	1.4527^{20}	i H_2O; s eth, ace, bz, chl; sl ctc
1131	4-Bromo-1-butene		C_4H_7Br	5162-44-7	135.003			98.5	1.3230^{20}	1.4622^{20}	sl H_2O; vs bz, eth, EtOH
1132	1-Bromo-2-butene		C_4H_7Br	4784-77-4	135.003			104.5	1.3371^{25}	1.4822^{20}	i H_2O; s EtOH, eth, ctc; vs chl, bz
1133	*cis*-2-Bromo-2-butene		C_4H_7Br	3017-68-3	135.003	liq	-111.5	93.9	1.3416^{15}	1.4631^{19}	i H_2O; s EtOH, eth, ctc; vs chl, bz



Bromobenzene



4-Bromobenzeneacetic acid



4-Bromobenzeneacetonitrile



α-Bromobenzeneacetonitrile



2-Bromo-1,4-benzenediol



4-Bromobenzenesulfonyl chloride



4-Bromobenzenethiol



2-Bromobenzoic acid



3-Bromobenzoic acid



4-Bromobenzoic acid



2-Bromobenzonitrile



3-Bromobenzonitrile



4-Bromobenzonitrile



6-Bromobenzo[a]pyrene



2-Bromobenzoyl chloride



4-Bromobenzoyl chloride



2-Bromobiphenyl



3-Bromobiphenyl



4-Bromobiphenyl


1-Bromo-2-(bromomethyl)benzene



1-Bromo-3-(bromomethyl)benzene


1-Bromo-4-(bromomethyl)benzene



2-Bromo-2-(bromomethyl)pentanedinitrile



2-Bromo-1-(4-bromophenyl)ethanone



2-Bromo-1,3-butadiene



1-Bromobutane


2-Bromobutane, (±)



Bromobutanedioic acid, (±)



4-Bromobutanenitrile



2-Bromobutanoic acid, (±)



4-Bromobutanoic acid



3-Bromo-2-butanone


cis-1-Bromo-1-butene


trans-1-Bromo-1-butene



2-Bromo-1-butene



4-Bromo-1-butene



1-Bromo-2-butene



cis-2-Bromo-2-butene

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1134	*trans*-2-Bromo-2-butene		C_4H_7Br	3017-71-8	135.003	liq	-114.6	85.6	1.3323^{15}	1.4602^{16}	i H_2O; s EtOH, eth, ctc; vs chl, bz
1135	(4-Bromobutoxy)benzene		$C_{10}H_{13}BrO$	1200-03-9	229.113	cry (al)	41	154^{18}			sl EtOH, ctc
1136	1-Bromo-4-*tert*-butylbenzene		$C_{10}H_{13}Br$	3972-65-4	213.114		19	231.5	1.2286^{20}	1.5436^{20}	i H_2O; s eth, bz, chl
1137	2-Bromo-3'-chloroacetophenone	3-Chlorophenacyl bromide	C_8H_6BrClO	41011-01-2	233.490	nd	40	397.5			vs EtOH
1138	1-Bromo-2-chlorobenzene		C_6H_4BrCl	694-80-4	191.453	liq	-12.3	204	1.6387^{25}	1.5809^{20}	i H_2O; vs bz; sl ctc
1139	1-Bromo-3-chlorobenzene		C_6H_4BrCl	108-37-2	191.453	liq	-21.5	196	1.6302^{20}	1.5771^{20}	i H_2O; vs EtOH, eth
1140	1-Bromo-4-chlorobenzene		C_6H_4BrCl	106-39-8	191.453	nd or pl (al, eth)	68	196	1.576^{71}	1.5531^{70}	i H_2O; sl EtOH; s eth, bz, ctc, chl
1141	1-Bromo-4-chlorobutane		C_4H_8BrCl	6940-78-9	171.464			175; 63^{10}	1.489^{20}	1.4885^{20}	i H_2O; s EtOH, eth, chl; sl ctc
1142	Bromochlorodifluoromethane	Halon 1211	$CBrClF_2$	353-59-3	165.365	col gas	-159.5	-3.7			
1143	3-Bromo-1-chloro-5,5-dimethylhydantoin		$C_5H_6BrClN_2O_2$	126-06-7	241.471		162				
1144	1-Bromo-1-chloroethane		C_2H_4BrCl	593-96-4	143.410			83	1.667^{10}	1.4660^{20}	
1145	1-Bromo-2-chloroethane		C_2H_4BrCl	107-04-0	143.410	liq	-16.7	107	1.7392^{20}	1.4908^{20}	sl H_2O; s EtOH, eth, chl
1146	Bromochlorofluoromethane		CHBrClF	593-98-6	147.374	liq	-115	36	1.9771^{0}	1.4144^{25}	i H_2O; s eth, ace, chl
1147	Bromochloromethane	Halon 1011	CH_2BrCl	74-97-5	129.384	liq	-87.9	68.0	1.9344^{20}	1.4838^{20}	i H_2O; s EtOH, eth, ace, bz
1148	1-Bromo-4-(chloromethyl) benzene	*p*-Bromobenzyl chloride	C_7H_6BrCl	589-17-3	205.480	nd (al, peth)	50	236			i H_2O; vs EtOH, eth; s peth
1149	2-Bromo-1-(4-chlorophenyl) ethanone	*p*-Chlorophenacyl bromide	C_8H_6BrClO	536-38-9	233.490	nd	96.5				
1150	1-Bromo-2-chloropropane		C_3H_6BrCl	3017-96-7	157.437			118	1.531^{20}	1.4745^{20}	vs ace, bz, eth, EtOH
1151	1-Bromo-3-chloropropane		C_3H_6BrCl	109-70-6	157.437	liq	-58.9	143.3	1.5969^{20}	1.4864^{20}	i H_2O; vs EtOH, eth, chl
1152	2-Bromo-1-chloropropane		C_3H_6BrCl	3017-95-6	157.437			117	1.537^{20}	1.4795^{20}	i H_2O; vs EtOH, eth; s ace, bz
1153	2-Bromo-2-chloropropane		C_3H_6BrCl	2310-98-7	157.437			95	1.495^{20}	1.4575^{20}	vs ace, bz, eth, EtOH
1154	1-Bromo-2-chloro-1,1,2-trifluoroethane		$C_2HBrClF_3$	354-06-3	197.381			52.5	1.8574^{25}	1.3738^{20}	
1155	2-Bromo-2-chloro-1,1,1-trifluoroethane	Halothane	$C_2HBrClF_3$	151-67-7	197.381			50.2; 20^{243}	1.8563^{25}	1.3697^{0}	sl H_2O; s peth
1156	Bromocresol Green	Bromcresol Green	$C_{21}H_{14}Br_4O_5S$	76-60-8	698.014	wh or red (+7w) ye (HOAc)	218.5				sl H_2O; vs EtOH, eth, AcOEt; s bz
1157	Bromocresol Purple	Bromcresol Purple	$C_{21}H_{16}Br_2O_5S$	115-40-2	540.222		241.5				
1158	Bromocycloheptane	Cycloheptyl bromide	$C_7H_{13}Br$	2404-35-5	177.082			101^{40}, 75^{12}	1.3080^{20}	1.4996^{20}	i H_2O; vs eth, chl
1159	Bromocyclohexane	Cyclohexyl bromide	$C_6H_{11}Br$	108-85-0	163.055	liq	-56.5	166.2	1.3359^{20}	1.4957^{20}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
1160	*trans*-4-Bromocyclohexanol		$C_6H_{11}BrO$	32388-22-0	179.054	pl (hx)	81.5				
1161	2-Bromocyclohexanone		C_6H_9BrO	822-85-5	177.038			114^{32}, 90^{14}	1.340^{25}	1.5085^{25}	
1162	3-Bromocyclohexene		C_6H_9Br	1521-51-3	161.039			81^{40}, 56^{11}	1.3890^{20}	1.5320^{20}	i H_2O; s eth, bz, chl
1163	Bromocyclopentane	Cyclopentyl bromide	C_5H_9Br	137-43-9	149.029			137.5	1.3873^{20}	1.4886^{20}	sl ctc
1164	1-Bromodecane		$C_{10}H_{21}Br$	112-29-8	221.178	liq	-29.2	240.6	1.0702^{20}	1.4557^{20}	i H_2O; vs eth, chl; s ctc
1165	2-Bromodecanoic acid		$C_{10}H_{19}BrO_2$	2623-95-2	251.161		2.0	140^{2}	1.1912^{24}	1.4595^{24}	vs eth
1166	1-Bromo-3,5-dichlorobenzene		$C_6H_3BrCl_2$	19752-55-7	225.898	pr (al)	83	232			i H_2O; s EtOH, eth, chl; vs bz
1167	4-Bromo-1,2-dichlorobenzene		$C_6H_3BrCl_2$	18282-59-2	225.898	pr	25	237			i H_2O; sl EtOH; vs eth, bz, chl
1168	Bromodichlorofluoromethane	Halon 1121	$CBrCl_2F$	353-58-2	181.819	liq		52.8	1.95^{22}		
1169	Bromodichloromethane		$CHBrCl_2$	75-27-4	163.829	liq	-57	90	1.980^{20}	1.4964^{20}	i H_2O; vs EtOH, eth, ace, bz; sl ctc
1170	4-Bromo-2,5-dichlorophenol		$C_6H_3BrCl_2O$	1940-42-7	241.897	nd	71.5				
1171	2-Bromo-1,1-diethoxyethane		$C_6H_{13}BrO_2$	2032-35-1	197.070			$170; 66^{18}$	1.283^{20}	1.4387^{20}	s EtOH, eth
1172	4-Bromo-*N*,*N*-diethylaniline		$C_{10}H_{14}BrN$	2052-06-4	228.129	nd or pr	38	270			i H_2O; vs EtOH, eth
1173	Bromodifluoromethane		$CHBrF_2$	1511-62-2	130.920		-145	-14.6	1.55^{16}		s H_2O; vs EtOH
1174	3-Bromo-4,5-dihydro-2(3*H*)-furanone	α-Bromo-γ-butyrolactone	$C_4H_5BrO_2$	5061-21-2	164.986			130^{20}	1.8^{20}	1.5059^{20}	



trans-2-Bromo-2-butene



(4-Bromobutoxy)benzene



1-Bromo-4-*tert*-butylbenzene


2-Bromo-3'-chloroacetophenone



1-Bromo-2-chlorobenzene


1-Bromo-3-chlorobenzene



1-Bromo-4-chlorobenzene


1-Bromo-4-chlorobutane


Bromochlorodifluoromethane



3-Bromo-1-chloro-5,5-dimethylhydantoin



1-Bromo-1-chloroethane



1-Bromo-2-chloroethane


Bromochlorofluoromethane


Bromochloromethane


1-Bromo-4-(chloromethyl)benzene


2-Bromo-1-(4-chlorophenyl)ethanone



1-Bromo-2-chloropropane



1-Bromo-3-chloropropane



2-Bromo-1-chloropropane



2-Bromo-2-chloropropane


1-Bromo-2-chloro-1,1,2-trifluoroethane



2-Bromo-2-chloro-1,1,1-trifluoroethane


Bromocresol Green


Bromocresol Purple


Bromocycloheptane



Bromocyclohexane



trans-4-Bromocyclohexanol



2-Bromocyclohexanone



3-Bromocyclohexene


Bromocyclopentane


1-Bromodecane



2-Bromodecanoic acid



1-Bromo-3,5-dichlorobenzene



4-Bromo-1,2-dichlorobenzene


Bromodichlorofluoromethane


Bromodichloromethane


4-Bromo-2,5-dichlorophenol



2-Bromo-1,1-diethoxyethane



4-Bromo-*N*,*N*-diethylaniline



Bromodifluoromethane



3-Bromo-4,5-dihydro-2(3*H*)-furanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1175	5-Bromo-*N*,2-dihydroxybenzamide	5-Bromosalicylhydroxamic acid	$C_7H_6BrNO_3$	5798-94-7	232.032	cry (al)	232 dec				
1176	2-Bromo-1,4-dimethoxybenzene		$C_8H_9BrO_2$	25245-34-5	217.060	oil		262; 130^{10}	1.445	1.5700^{20}	
1177	4-Bromo-1,2-dimethoxybenzene		$C_8H_9BrO_2$	2859-78-1	217.060			254.5	1.702^{25}	1.5743^{20}	
1178	2-Bromo-1,1-dimethoxyethane		$C_4H_9BrO_2$	7252-83-7	169.017			149	1.430^{20}	1.4450^{20}	s eth, ace, chl
1179	4-Bromo-*N*,*N*-dimethylaniline		$C_8H_{10}BrN$	586-77-6	200.076		55	264	1.3220^{100}		i H_2O; s EtOH; vs eth
1180	1-Bromo-2,4-dimethylbenzene		C_8H_9Br	583-70-0	185.061	liq	-17	205	1.3419^{20}	1.5501^{20}	i H_2O; vs EtOH, eth, ace
1181	1-Bromo-3,5-dimethylbenzene		C_8H_9Br	556-96-7	185.061			204	1.362^{20}	1.5462^{22}	vs eth; s ace, bz
1182	2-Bromo-1,3-dimethylbenzene		C_8H_9Br	576-22-7	185.061			203.5; 100^{20}		1.5552^{20}	vs eth; s ace, bz
1183	2-Bromo-1,4-dimethylbenzene		C_8H_9Br	553-94-6	185.061	lf or pl	9	199; 88^{13}	1.3582^{18}	1.5514^{18}	i H_2O; vs EtOH; s bz
1184	4-Bromo-1,2-dimethylbenzene		C_8H_9Br	583-71-1	185.061	liq	-0.2	214.5	1.3708^{20}	1.5530^{20}	i H_2O; vs EtOH, eth
1185	*trans*-1-Bromo-3,7-dimethyl-2,6-octadiene	*trans*-Geranyl bromide	$C_{10}H_{17}Br$	6138-90-5	217.146			101^{12}, 47$^{0.005}$	1.0940^{22}	1.5027^{20}	
1186	1-Bromo-2,2-dimethylpropane		$C_5H_{11}Br$	630-17-1	151.045			106	1.1997^{20}	1.4370^{20}	i H_2O; s EtOH, eth, ace, bz; vs chl
1187	2-Bromo-4,6-dinitroaniline		$C_6H_4BrN_3O_4$	1817-73-8	262.018	ye nd (al or HOAc)	153.5	sub			vs EtOH, ace; s HOAc
1188	1-Bromo-2,4-dinitrobenzene		$C_6H_3BrN_2O_4$	584-48-5	247.003	ye nd (al)	75				vs EtOH
1189	α-Bromodiphenylmethane		$C_{13}H_{11}Br$	776-74-9	247.130		45	184^{20}, 152^{2}			s EtOH, chl; vs bz
1190	1-Bromododecane	Lauryl bromide	$C_{12}H_{25}Br$	143-15-7	249.231	liq	-9.5	276	1.0399^{20}	1.4583^{20}	i H_2O; s EtOH, eth, ctc; msc ace
1191	2-Bromododecanoic acid		$C_{12}H_{23}BrO_2$	111-56-8	279.214	pl	32	158^{2}	1.1474^{74}	1.4585^{24}	vs bz, eth, EtOH, lig
1192	Bromoethane	Ethyl bromide	C_2H_5Br	74-96-4	108.965	liq	-118.6	38.5	1.4604^{20}	1.4239^{20}	sl H_2O; msc EtOH, eth, chl
1193	2-Bromoethanol	Ethylene bromohydrin	C_2H_5BrO	540-51-2	124.964			150; 51^{4}	1.7629^{20}	1.4915^{20}	msc H_2O, EtOH, eth; sl lig
1194	Bromoethene	Vinyl bromide	C_2H_3Br	593-60-2	106.949	vol liq or gas	-139.54	15.8	1.4933^{20}	1.4380^{20}	i H_2O; s EtOH, eth, ace, bz, chl
1195	1-Bromo-2-ethoxybenzene		C_8H_9BrO	583-19-7	201.060			223	1.4223^{20}		vs eth, EtOH
1196	1-Bromo-4-ethoxybenzene		C_8H_9BrO	588-96-5	201.060		2.0	231	1.4071^{25}	1.5517^{20}	i H_2O; vs EtOH, eth; s chl
1197	(2-Bromoethoxy)benzene		C_8H_9BrO	589-10-6	201.060		39	dec 240; 128^{20}	1.3555^{20}		i H_2O; vs EtOH, eth
1198	1-Bromo-2-ethoxyethane	2-Bromoethyl ethyl ether	C_4H_9BrO	592-55-2	153.017			127.5	1.3852^{0}	1.4447^{20}	sl H_2O; msc EtOH, eth
1199	2-Bromoethyl acetate		$C_4H_7BrO_2$	927-68-4	167.002	liq	-13.8	162.5	1.514^{20}	1.457^{23}	vs H_2O, chl; msc EtOH, eth
1200	2-Bromoethylamine hydrobromide	2-Bromoethanamine hydrobromide	$C_2H_7Br_2N$	2576-47-8	204.892		174.0				
1201	(1-Bromoethyl)benzene		C_8H_9Br	585-71-7	185.061			219; 92^{11}	1.3535^{25}	1.5543^{25}	
1202	(2-Bromoethyl)benzene		C_8H_9Br	103-63-9	185.061	liq	-55.9	219; 105^{18}	1.3643^{20}	1.5372^{20}	i H_2O; s eth, bz; sl ctc
1203	1-Bromo-2-ethylbenzene		C_8H_9Br	1973-22-4	185.061	liq	-67.9	199.3	1.3548^{20}	1.5472^{20}	vs ace, bz, eth, EtOH
1204	1-Bromo-3-ethylbenzene		C_8H_9Br	2725-82-8	185.061			202	1.3493^{20}	1.5465^{20}	
1205	1-Bromo-4-ethylbenzene		C_8H_9Br	1585-07-5	185.061	liq	-43.5	204	1.3423^{20}	1.5445^{20}	vs ace, bz, eth, EtOH
1206	(2-Bromoethyl)cyclohexane		$C_8H_{15}Br$	1647-26-3	191.109	liq	-57	212	1.2357^{20}	1.4899^{20}	
1207	*N*-(2-Bromoethyl)phthalimide		$C_{10}H_8BrNO_2$	574-98-1	254.081	nd (w)	83				vs eth; sl chl
1208	1-Bromo-4-ethynylbenzene		C_8H_5Br	766-96-1	181.030		64.5	89^{16}			s chl
1209	1-Bromo-2-fluorobenzene		C_6H_4BrF	1072-85-1	174.998			154	1.0738^{21}	1.5337^{20}	
1210	1-Bromo-3-fluorobenzene		C_6H_4BrF	1073-06-9	174.998			150	1.7081^{20}	1.5257^{20}	s ctc
1211	1-Bromo-4-fluorobenzene		C_6H_4BrF	460-00-4	174.998	liq	-17.4	151.5	1.593^{15}	1.5310^{15}	i H_2O; s EtOH, eth, chl
1212	1-Bromo-2-fluoroethane		C_2H_4BrF	762-49-2	126.955			71.5	1.7044^{25}	1.4236^{20}	vs eth, EtOH
1213	Bromofluoromethane		CH_2BrF	373-52-4	112.929	vol liq or gas		19			s EtOH; vs chl
1214	2-Bromofuran		C_4H_3BrO	584-12-3	146.970			103	1.6500^{20}	1.4980^{20}	sl H_2O; s EtOH, eth, ace, bz
1215	3-Bromofuran		C_4H_3BrO	22037-28-1	146.970			103	1.6606^{20}	1.4958^{20}	vs ace, bz, eth, EtOH
1216	5-Bromo-2-furancarboxaldehyde		$C_5H_3BrO_2$	1899-24-7	174.981	cry (50% al)	83.5	201; 112^{16}			vs eth, EtOH
1217	1-Bromoheptadecane		$C_{17}H_{35}Br$	3508-00-7	319.364		29.6	349	0.9916^{20}	1.4625^{20}	i H_2O; vs chl
1218	1-Bromoheptane	Heptyl bromide	$C_7H_{15}Br$	629-04-9	179.098	liq	-56.1	178.9	1.1400^{20}	1.4502^{20}	i H_2O; vs EtOH, eth; sl ctc; s chl



5-Bromo-*N*,2-dihydroxybenzamide



2-Bromo-1,4-dimethoxybenzene


4-Bromo-1,2-dimethoxybenzene



2-Bromo-1,1-dimethoxyethane



4-Bromo-*N*,*N*-dimethylaniline



1-Bromo-2,4-dimethylbenzene


1-Bromo-3,5-dimethylbenzene



2-Bromo-1,3-dimethylbenzene



2-Bromo-1,4-dimethylbenzene



4-Bromo-1,2-dimethylbenzene



trans-1-Bromo-3,7-dimethyl-2,6-octadiene



1-Bromo-2,2-dimethylpropane


2-Bromo-4,6-dinitroaniline



1-Bromo-2,4-dinitrobenzene


α-Bromodiphenylmethane



1-Bromododecane



2-Bromododecanoic acid



Bromoethane



2-Bromoethanol



Bromoethene



1-Bromo-2-ethoxybenzene



1-Bromo-4-ethoxybenzene



(2-Bromoethoxy)benzene



1-Bromo-2-ethoxyethane



2-Bromoethyl acetate



2-Bromoethylamine hydrobromide



(1-Bromoethyl)benzene



(2-Bromoethyl)benzene



1-Bromo-2-ethylbenzene


1-Bromo-3-ethylbenzene



1-Bromo-4-ethylbenzene



(2-Bromoethyl)cyclohexane



N-(2-Bromoethyl)phthalimide


1-Bromo-4-ethynylbenzene


1-Bromo-2-fluorobenzene


1-Bromo-3-fluorobenzene



1-Bromo-4-fluorobenzene



1-Bromo-2-fluoroethane



Bromofluoromethane


2-Bromofuran



3-Bromofuran



5-Bromo-2-furancarboxaldehyde



1-Bromoheptadecane



1-Bromoheptane

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1219	2-Bromoheptane	2-Heptyl bromide	$C_7H_{15}Br$	1974-04-5	179.098		47	166	1.1277^{20}	1.4503^{20}	i H_2O; vs bz; s ctc, chl
1220	4-Bromoheptane	4-Heptyl bromide	$C_7H_{15}Br$	998-93-6	179.098			161; 84^{72}	1.1351^{20}	1.4495^{20}	i H_2O; s bz, ctc, chl
1221	1-Bromohexadecane		$C_{16}H_{33}Br$	112-82-3	305.337		18	336	0.9991^{20}	1.4618^{25}	i H_2O; s eth
1222	2-Bromohexadecanoic acid		$C_{16}H_{31}BrO_2$	18263-25-7	335.320		52.8				
1223	1-Bromohexane	Hexyl bromide	$C_6H_{13}Br$	111-25-1	165.071	liq	-83.7	155.3	1.1744^{20}	1.4478^{20}	i H_2O; msc EtOH, eth; s ace; vs chl
1224	2-Bromohexane		$C_6H_{13}Br$	3377-86-4	165.071			143; 78^{90}	1.1658^{20}	1.4832^{25}	i H_2O; vs EtOH; s eth, ace; sl ctc
1225	3-Bromohexane		$C_6H_{13}Br$	3377-87-5	165.071			142	1.1799^{20}	1.4472^{20}	vs ace, eth, EtOH, chl
1226	2-Bromohexanoic acid, (±)		$C_6H_{11}BrO_2$	2681-83-6	195.054		2.0	240; 140^{23}	1.2810^{33}		s EtOH, eth
1227	6-Bromohexanoic acid		$C_6H_{11}BrO_2$	4224-70-8	195.054	cry (peth)	35	167^{20}			vs peth
1228	6-Bromohexanoyl chloride		$C_6H_{10}BrClO$	22809-37-6	213.499			101^{6}			
1229	1-Bromo-4-(hexyloxy)benzene		$C_{12}H_{17}BrO$	30752-19-3	257.166			156^{13}	1.2306^{20}	1.5262^{20}	
1230	5-Bromo-2-hydroxybenzaldehyde		$C_7H_5BrO_2$	1761-61-1	201.018	nd (al), lf (eth)	105.5				i H_2O; s EtOH, eth; sl chl
1231	4-Bromo-α-hydroxybenzeneacetic acid, (±)	*p*-Bromomandelic acid	$C_8H_7BrO_3$	7021-04-7	231.044		119				vs H_2O, EtOH, eth, bz, chl
1232	5-Bromo-2-hydroxybenzenemethanol	Bromosaligenin	$C_7H_7BrO_2$	2316-64-5	203.034	lf (bz)	113				vs bz, eth, EtOH, chl
1233	5-Bromo-2-hydroxybenzoic acid		$C_7H_5BrO_3$	89-55-4	217.017	nd (w, dil al)	169.8	sub 100			sl H_2O, ace; vs EtOH, eth
1234	3-Bromo-4-hydroxy-5-methoxybenzaldehyde		$C_8H_7BrO_3$	2973-76-4	231.044	pl (HOAc), nd, pl (al)	167.0				i H_2O; s EtOH, DMSO; sl eth, bz
1235	1-Bromo-2-iodobenzene		C_6H_4BrI	583-55-1	282.904		9.5	257; 120^{15}	2.2570^{25}	1.6618^{25}	i H_2O; sl EtOH, HOAc; s ace
1236	1-Bromo-3-iodobenzene		C_6H_4BrI	591-18-4	282.904	liq	-9.3	252; 120^{18}			i H_2O; sl EtOH, HOAc
1237	1-Bromo-4-iodobenzene		C_6H_4BrI	589-87-7	282.904	pr or pl (eth-al)	92	252			i H_2O; sl EtOH, chl; s eth
1238	Bromoiodomethane		CH_2BrI	557-68-6	220.835			139.5	2.926^{17}	1.6410^{20}	vs chl
1239	1-Bromo-4-isocyanatobenzene	*p*-Bromophenyl isocyanate	C_7H_4BrNO	2493-02-9	198.017	nd		226			vs eth
1240	1-Bromo-4-isopropylbenzene		$C_9H_{11}Br$	586-61-8	199.087	liq	-22.5	218.7	1.3145^{20}	1.5569^{20}	i H_2O; s eth, bz, chl; sl ctc
1241	4-Bromoisoquinoline		C_9H_6BrN	1532-97-4	208.055	cry (peth)	41.5	282.5			vs eth
1242	Bromomethane	Methyl bromide	CH_3Br	74-83-9	94.939	col gas	-93.68	3.5	1.6755^{20}	1.4218^{20}	sl H_2O; msc EtOH, eth, chl, CS_2
1243	1-Bromo-2-methoxyethane		C_3H_7BrO	6482-24-2	138.991			110	1.4623^{20}	1.44753^{20}	
1244	Bromomethoxymethane		C_2H_5BrO	13057-17-5	124.964			87	1.5976^{20}	1.4562^{20}	
1245	2-Bromo-4-methylaniline		C_7H_8BrN	583-68-6	186.050	lf	26	240	1.510^{20}	1.5999^{20}	i H_2O; s EtOH, eth
1246	4-Bromo-2-methylaniline		C_7H_8BrN	583-75-5	186.050	cry (al)	59.5	240			sl H_2O, chl; s EtOH; vs eth, HOAc
1247	(Bromomethyl)benzene	Benzyl bromide	C_7H_7Br	100-39-0	171.035	liq	-1.5	201	1.4380^{25}	1.5752^{20}	i H_2O; msc EtOH, eth; s ctc
1248	4-(Bromomethyl)benzoic acid		$C_8H_7BrO_2$	6232-88-8	215.045		226.3				
1249	3-(Bromomethyl)benzonitrile		C_8H_6BrN	28188-41-2	196.045		96.5	130^{4}			
1250	4-(Bromomethyl)benzonitrile		C_8H_6BrN	17201-43-3	196.045		114				
1251	1-Bromo-2-methylbutane, *DL*		$C_5H_{11}Br$	5973-11-5	151.045			119	1.2205^{20}	1.4452^{20}	i H_2O; s EtOH, eth; vs chl
1252	1-Bromo-3-methylbutane	Isopentyl bromide	$C_5H_{11}Br$	107-82-4	151.045	liq	-112	120.4	1.2071^{20}	1.4420^{20}	i H_2O; s EtOH, eth; sl ctc; vs chl
1253	2-Bromo-2-methylbutane	*tert*-Pentyl bromide	$C_5H_{11}Br$	507-36-8	151.045			108	1.197^{18}	1.4421	
1254	3-Bromo-3-methylbutanoic acid	β-Bromoisovaleric acid	$C_5H_9BrO_2$	5798-88-9	181.028	nd (lig)	74				vs bz, eth, EtOH
1255	1-Bromo-3-methyl-2-butene		C_5H_9Br	870-63-3	149.029			dec 131; 50^{40}	1.2930^{15}	1.4930^{15}	vs ace, bz, eth, EtOH
1256	1-(Bromomethyl)-2-chlorobenzene		C_7H_6BrCl	611-17-6	205.480			109^{10}			
1257	(Bromomethyl) chlorodimethylsilane		$C_3H_8BrClSi$	16532-02-8	187.539			131	1.375^{25}	1.4630^{25}	
1258	1-Bromo-3-methylcyclohexane	3-Methylcyclohexyl bromide	$C_7H_{13}Br$	13905-48-1	177.082			181; 60^{11}	1.2676^{15}	1.4979^{20}	i H_2O; vs eth; s bz
1259	(Bromomethyl)cyclohexane		$C_7H_{13}Br$	2550-36-9	177.082			76^{26}	1.283^{20}	1.4907^{30}	vs bz, eth, chl
1260	1-(Bromomethyl)-3-fluorobenzene		C_7H_6BrF	456-41-7	189.025			88^{20}		1.5474^{20}	
1261	3-(Bromomethyl)heptane		$C_8H_{17}Br$	18908-66-2	193.125			67^{10}			



2-Bromoheptane



4-Bromoheptane



1-Bromohexadecane



2-Bromohexadecanoic acid



1-Bromohexane



2-Bromohexane



3-Bromohexane



2-Bromohexanoic acid, (±)



6-Bromohexanoic acid



6-Bromohexanoyl chloride



1-Bromo-4-(hexyloxy)benzene


5-Bromo-2-hydroxybenzaldehyde



4-Bromo-α-hydroxybenzeneacetic acid, (±)



5-Bromo-2-hydroxybenzenemethanol


5-Bromo-2-hydroxybenzoic acid



3-Bromo-4-hydroxy-5-methoxybenzaldehyde



1-Bromo-2-iodobenzene



1-Bromo-3-iodobenzene


1-Bromo-4-iodobenzene



Bromoiodomethane



1-Bromo-4-isocyanatobenzene



1-Bromo-4-isopropylbenzene



4-Bromoisoquinoline



Bromomethane



1-Bromo-2-methoxyethane



Bromomethoxymethane



2-Bromo-4-methylaniline



4-Bromo-2-methylaniline



(Bromomethyl)benzene


4-(Bromomethyl)benzoic acid



3-(Bromomethyl)benzonitrile



4-(Bromomethyl)benzonitrile



1-Bromo-2-methylbutane, *DL*



1-Bromo-3-methylbutane


2-Bromo-2-methylbutane



3-Bromo-3-methylbutanoic acid



1-Bromo-3-methyl-2-butene



1-(Bromomethyl)-2-chlorobenzene


(Bromomethyl)chlorodimethylsilane



1-Bromo-3-methylcyclohexane



(Bromomethyl)cyclohexane



1-(Bromomethyl)-3-fluorobenzene



3-(Bromomethyl)heptane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1262	1-(Bromomethyl)-2-methylbenzene		C_8H_9Br	89-92-9	185.061	pr	21	217; 108^{16}	1.3811^{23}	1.5730^{20}	i H_2O; s EtOH, eth, ace, bz
1263	1-(Bromomethyl)-3-methylbenzene		C_8H_9Br	620-13-3	185.061			212.5	1.3711^{23}	1.5660^{20}	i H_2O; vs EtOH, eth
1264	1-(Bromomethyl)-4-methylbenzene		C_8H_9Br	104-81-4	185.061	nd (al)	35	220	1.324^{25}		i H_2O; s EtOH; vs eth, chl
1265	1-(Bromomethyl)naphthalene		$C_{11}H_9Br$	3163-27-7	221.093	cry (peth, al)	56	183^{18}, 167^{10}			vs ace, bz, eth, EtOH
1266	2-(Bromomethyl)naphthalene		$C_{11}H_9Br$	939-26-4	221.093	lf (al)	56	213^{100}, 167^{14}			s EtOH, eth, chl, HOAc
1267	1-(Bromomethyl)-3-nitrobenzene		$C_7H_6BrNO_2$	3958-57-4	216.033	nd or pl (al)	59.3	162^{13}			i H_2O; s EtOH
1268	1-(Bromomethyl)-4-nitrobenzene		$C_7H_6BrNO_2$	100-11-8	216.033	nd (al)	99.5				sl H_2O, chl; vs EtOH, eth; s HOAc
1269	2-(Bromomethyl)-4-nitrophenol		$C_7H_6BrNO_3$	772-33-8	232.032		148				
1270	(Bromomethyl)oxirane, (±)		C_3H_5BrO	82584-73-4	136.975	liq	-40	137	1.615^{14}	1.4841^{20}	i H_2O; s EtOH, eth, bz, chl
1271	1-Bromo-2-methylpentane	2-Methylpentyl bromide	$C_6H_{13}Br$	25346-33-2	165.071			141	1.1624^{20}	1.4495^{20}	vs eth, chl
1272	1-Bromo-4-methylpentane		$C_6H_{13}Br$	626-88-0	165.071			145	1.1683^{20}	1.4490	vs eth, chl
1273	2-Bromo-2-methylpentane		$C_6H_{13}Br$	4283-80-1	165.071			142.5; 70^{100}		1.442^{23}	vs eth, chl
1274	3-Bromo-3-methylpentane		$C_6H_{13}Br$	25346-31-0	165.071			130; 76^{100}	1.1835^{20}	1.4525^{20}	vs eth, chl
1275	2-Bromo-4-methylphenol		C_7H_7BrO	6627-55-0	187.034	nd (peth)	56.5	213.5	1.5422^{25}	1.5772^{20}	sl H_2O; s EtOH, bz, chl
1276	1-(Bromomethyl)-3-phenoxybenzene	3-Phenoxybenzyl bromide	$C_{13}H_{11}BrO$	51632-16-7	263.129	oil					
1277	2-Bromo-1-(4-methylphenyl) ethanone		C_9H_9BrO	619-41-0	213.070	nd or lf (al)	51	157^{14}			vs eth, EtOH
1278	*N*-(Bromomethyl)phthalimide	2-(Bromomethyl)-1*H*-isoindole-1,3(2*H*)-dione	$C_9H_6BrNO_2$	5332-26-3	240.054	pr (chl, bz)	151.5				s ace; sl bz, chl; vs AcOEt
1279	1-Bromo-2-methylpropane	Isobutyl bromide	C_4H_9Br	78-77-3	137.018	liq	-119	91.1	1.272^{15}	1.4348^{20}	i H_2O; vs EtOH, eth, ace, chl, bz; s ctc
1280	2-Bromo-2-methylpropane	*tert*-Butyl bromide	C_4H_9Br	507-19-7	137.018	liq	-16.2	73.3	1.4278^{20}	1.4278^{20}	i H_2O; sl ctc
1281	2-Bromo-2-methylpropanoic acid	α-Bromoisobutyric acid	$C_4H_7BrO_2$	2052-01-9	167.002	cry (peth)	48.5	199; 115^{24}	1.4969^{60}		
1282	2-Bromo-2-methylpropanoyl bromide		$C_4H_6Br_2O$	20769-85-1	229.898			163	1.4067^{14}		vs ace, CS_2
1283	1-Bromo-2-methylpropene		C_4H_7Br	3017-69-4	135.003			91	1.336^{20}		
1284	3-Bromo-2-methylpropene		C_4H_7Br	1458-98-6	135.003			95	1.313^{20}		
1285	2-(Bromomethyl)tetrahydrofuran		C_5H_9BrO	1192-30-9	165.028			170; 70^{22}	1.4679^{20}	1.4850^{20}	s EtOH, eth
1286	(Bromomethyl)trimethylsilane		$C_4H_{11}BrSi$	18243-41-9	167.120			116.5	1.170^{25}	1.4460^{20}	
1287	1-Bromonaphthalene	1-Naphthyl bromide	$C_{10}H_7Br$	90-11-9	207.067	oily liq	6.1	281	1.4785^{20}	1.658^{20}	s H_2O, ace; msc EtOH, eth, bz; sl ctc
1288	2-Bromonaphthalene		$C_{10}H_7Br$	580-13-2	207.067	pl or orth lf (al)	55.9	281.5	1.605^{25}	1.6382^{60}	i H_2O; s EtOH, eth, bz, CS_2; sl ctc
1289	4-Bromo-1,8-naphthalenedicarboxylic anhydride		$C_{12}H_5BrO_3$	81-86-7	277.070		222				
1290	1-Bromo-2-naphthol	1-Bromo-β-naphthol	$C_{10}H_7BrO$	573-97-7	223.066	orth pr (bz-lig) nd (HOAc)	84	130			i H_2O; s EtOH, eth, bz; sl chl; vs HOAc
1291	4-Bromo-2-nitroaniline		$C_6H_5BrN_2O_2$	875-51-4	217.020	oran-ye nd (w)	111.5	sub			vs EtOH
1292	1-Bromo-2-nitrobenzene		$C_6H_4BrNO_2$	577-19-5	202.006	pa ye (al)	43	258	1.6245^{80}		i H_2O; vs EtOH; s eth, ace, bz; sl chl
1293	1-Bromo-3-nitrobenzene		$C_6H_4BrNO_2$	585-79-5	202.006	orth	56	265	1.7036^{20}	1.5979^{20}	sl H_2O; s EtOH, eth, bz
1294	1-Bromo-4-nitrobenzene	*p*-Nitrobromobenzene	$C_6H_4BrNO_2$	586-78-7	202.006	orth or mcl pr (al)	127	256	1.948^{25}		i H_2O; s EtOH, eth, bz; sl chl
1295	Bromonitromethane		CH_2BrNO_2	563-70-2	139.937			149; 71^{40}		1.4880^{20}	vs EtOH
1296	2-Bromo-2-nitro-1,3-propanediol	Bronopol	$C_3H_6BrNO_4$	52-51-7	199.989		131.5				
1297	1-Bromononane		$C_9H_{19}Br$	693-58-3	207.151	liq	-29.0	221.4; 88^{4}	1.0845^{25}	1.4522^{25}	
1298	1-Bromooctadecane		$C_{18}H_{37}Br$	112-89-0	333.391	cry (al)	28.2	362; 210^{10}	0.9848^{20}	1.4631^{20}	i H_2O; s EtOH, eth; sl ctc
1299	1-Bromooctane	Octyl bromide	$C_8H_{17}Br$	111-83-1	193.125	liq	-55.0	200.8	1.1072^{25}	1.4503^{25}	i H_2O; msc EtOH, eth; sl ctc
1300	2-Bromooctane, (±)		$C_8H_{17}Br$	60251-57-2	193.125			188.5	1.0878^{25}	1.4442^{25}	i H_2O; msc EtOH, eth
1301	8-Bromooctanoic acid		$C_8H_{15}BrO_2$	17696-11-6	223.108	nd (peth)	38.5	147^{2}			vs bz, eth, EtOH
1302	1-Bromopentadecane		$C_{15}H_{31}Br$	629-72-1	291.311		19	322	1.0675^{20}	1.4611^{20}	i H_2O; s ace; vs chl



1-(Bromomethyl)-2-methylbenzene



1-(Bromomethyl)-3-methylbenzene



1-(Bromomethyl)-4-methylbenzene



1-(Bromomethyl)naphthalene



2-(Bromomethyl)naphthalene



1-(Bromomethyl)-3-nitrobenzene



1-(Bromomethyl)-4-nitrobenzene



2-(Bromomethyl)-4-nitrophenol



(Bromomethyl)oxirane, (±)



1-Bromo-2-methylpentane



1-Bromo-4-methylpentane



2-Bromo-2-methylpentane



3-Bromo-3-methylpentane


2-Bromo-4-methylphenol



1-(Bromomethyl)-3-phenoxybenzene



2-Bromo-1-(4-methylphenyl)ethanone



N-(Bromomethyl)phthalimide


1-Bromo-2-methylpropane



2-Bromo-2-methylpropane


2-Bromo-2-methylpropanoic acid



2-Bromo-2-methylpropanoyl bromide



1-Bromo-2-methylpropene



3-Bromo-2-methylpropene



2-(Bromomethyl)tetrahydrofuran



(Bromomethyl)trimethylsilane



1-Bromonaphthalene



2-Bromonaphthalene



4-Bromo-1,8-naphthalenedicarboxylic anhydride



1-Bromo-2-naphthol



4-Bromo-2-nitroaniline


1-Bromo-2-nitrobenzene



1-Bromo-3-nitrobenzene



1-Bromo-4-nitrobenzene



Bromonitromethane



2-Bromo-2-nitro-1,3-propanediol



1-Bromononane


1-Bromooctadecane



1-Bromooctane



2-Bromooctane, (±)



8-Bromooctanoic acid



1-Bromopentadecane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1303	Bromopentafluorobenzene		C_6BrF_5	344-04-7	246.960	liq	-31	137	1.981^{25}	1.4490^{20}	
1304	Bromopentafluoroethane		C_2BrF_5	354-55-2	198.917	col gas		-21	1.8098^{25}		
1305	1-Bromopentane	Pentyl bromide	$C_5H_{11}Br$	110-53-2	151.045	liq	-88.0	129.8	1.2182^{20}	1.4447^{20}	i H_2O; s EtOH, bz, chl; sl ctc; msc eth
1306	2-Bromopentane		$C_5H_{11}Br$	107-81-3	151.045	liq	-95.5	117.4	1.2075^{20}	1.4413^{20}	vs bz, eth, EtOH, chl
1307	3-Bromopentane		$C_5H_{11}Br$	1809-10-5	151.045	liq	-126.2	118.6	1.214^{20}	1.4441^{20}	i H_2O; s EtOH, eth, bz, chl
1308	5-Bromopentanenitrile		C_5H_8BrN	5414-21-1	162.029			111^{12}, 103^{10}	1.3989^{20}	1.4780^{20}	
1309	5-Bromopentanoic acid		$C_5H_9BrO_2$	2067-33-6	181.028		40.0	142^{13}			s chl
1310	5-Bromo-1-pentene		C_5H_9Br	1119-51-3	149.029			125.5	1.2581^{20}	1.4640^{20}	
1311	9-Bromophenanthrene	9-Phenanthryl bromide	$C_{14}H_9Br$	573-17-1	257.125	pr (al)	64.5	>360	1.4093^{10}		i H_2O; s EtOH, eth, CS_2; sl chl
1312	2-Bromophenol		C_6H_5BrO	95-56-7	173.007		5.6	194.5	1.4924^{20}	1.589^{20}	sl H_2O, chl; s EtOH, eth, alk
1313	3-Bromophenol		C_6H_5BrO	591-20-8	173.007		33	236.5			sl H_2O, ctc; vs EtOH, eth; s chl, alk
1314	4-Bromophenol		C_6H_5BrO	106-41-2	173.007		66.4	238	1.840^{15}		s H_2O, chl; vs EtOH, eth
1315	Bromophenol Blue	Bromphenol Blue	$C_{19}H_{10}Br_4O_5S$	115-39-9	669.960	hex pr (HOAc-ace)	279 dec				sl H_2O; s EtOH, bz, HOAc
1316	1-Bromo-4-phenoxybenzene	4-Bromophenyl phenyl ether	$C_{12}H_9BrO$	101-55-3	249.102		18.72	$126^{3.5}$	1.6088^{20}	1.6084^{20}	i H_2O; s eth, ctc
1317	(4-Bromophenoxy)trimethylsilane		$C_9H_{13}BrOSi$	17878-44-3	245.188			126^{25}	1.2619^{20}	1.5145^{20}	
1318	*N*-(4-Bromophenyl)acetamide	*p*-Bromoacetanilide	C_8H_8BrNO	103-88-8	214.060	nd (60% al)	168		1.717^{25}		i H_2O; s EtOH, chl; sl eth, bz
1319	1-(3-Bromophenyl)ethanone		C_8H_7BrO	2142-63-4	199.045		7.5	133^{19}		1.5755^{20}	i H_2O; s ace, bz
1320	1-(4-Bromophenyl)ethanone	*p*-Bromoacetophenone	C_8H_7BrO	99-90-1	199.045	lf (al)	50.5	257; 130^{11}	1.647^{25}	1.647	i H_2O; s EtOH, eth, bz, ctc, HOAc
1321	(4-Bromophenyl)hydrazine	(*p*-Bromophenyl)hydrazine	$C_6H_7BrN_2$	589-21-9	187.037	nd (w), lf (lig), cry (al)	108				vs eth, EtOH, lig
1322	2-(4-Bromophenyl)-1*H*-indene-1,3(2*H*)-dione	Bromindione	$C_{15}H_9BrO_2$	1146-98-1	301.135	cry (lig)	138				
1323	(4-Bromophenyl) phenylmethanone		$C_{13}H_9BrO$	90-90-4	261.113	lf (al)	82.5	350			i H_2O; sl EtOH, eth, bz, peth
1324	2-Bromo-1-phenyl-1-propanone		C_9H_9BrO	2114-00-3	213.070			247.5	1.4298^{20}	1.5720^{20}	i H_2O; s EtOH, eth, ace, bz, ctc
1325	Bromophos		$C_8H_8BrCl_2PS$	2104-96-3	317.999	ye cry	54	$141^{0.01}$			sl H_2O; s eth, ctc, tol
1326	Bromophos-ethyl		$C_{10}H_{12}BrCl_2O_3PS$	4824-78-6	394.049	pale-ye liq		$122^{0.004}$			
1327	1-Bromopropane	Propyl bromide	C_3H_7Br	106-94-5	122.992	liq	-110.3	71.1	1.3537^{20}	1.4343^{20}	sl H_2O; s EtOH, eth, ace, bz, chl, ctc
1328	2-Bromopropane	Isopropyl bromide	C_3H_7Br	75-26-3	122.992	liq	-89.0	59.5	1.3140^{20}	1.4251^{20}	sl H_2O; s ace, bz, chl; msc EtOH, eth
1329	3-Bromopropanenitrile		C_3H_4BrN	2417-90-5	133.975			92^{25}, 69^{7}	1.6152^{20}	1.4800^{20}	vs EtOH, eth; sl ctc
1330	2-Bromopropanoic acid, (±)		$C_3H_5BrO_2$	10327-08-9	152.975	pr	25.7	203.5	1.7000^{20}	1.4753^{20}	vs H_2O, EtOH, eth; sl chl
1331	3-Bromopropanoic acid	β-Bromopropionic acid	$C_3H_5BrO_2$	590-92-1	152.975	pl (CCl_4)	62.5	141^{45}	1.48^{25}		s H_2O, EtOH, eth, bz, chl
1332	3-Bromo-1-propanol		C_3H_7BrO	627-18-9	138.991			105^{185}, 80^{22}	1.5374^{20}	1.4834^{25}	s H_2O; msc EtOH, eth
1333	1-Bromo-2-propanol		C_3H_7BrO	19686-73-8	138.991			146.5	1.5585^{30}	1.4801^{20}	s H_2O; vs EtOH, eth
1334	2-Bromopropanoyl bromide		$C_3H_4Br_2O$	563-76-8	215.871			153	2.0611^{16}		
1335	2-Bromopropanoyl chloride		C_3H_4BrClO	7148-74-5	171.420			132	1.697^{11}	1.4780^{20}	s eth, chl; sl ctc
1336	*cis*-1-Bromopropene		C_3H_5Br	590-13-6	120.976	liq	-113	57.8	1.4291^{20}	1.4560^{20}	i H_2O; s eth, ace, chl
1337	*trans*-1-Bromopropene		C_3H_5Br	590-15-8	120.976			63.2			
1338	2-Bromopropene		C_3H_5Br	557-93-7	120.976	liq	-126	48.4	1.3965^{16}	1.4467^{16}	i H_2O; s eth, ace, chl
1339	3-Bromopropene	Allyl bromide	C_3H_5Br	106-95-6	120.976	liq	-119	70.1	1.398^{20}	1.4697^{20}	i H_2O; msc EtOH, eth; s ctc, chl, CS_2
1340	(3-Bromo-1-propenyl)benzene		C_9H_9Br	4392-24-9	197.071	nd (al, eth)	34	130^{10}	1.3428^{30}	1.613^{20}	vs EtOH
1341	(3-Bromopropoxy)benzene		$C_9H_{11}BrO$	588-63-6	215.086		10.7	127^{18}	1.364^{16}		vs eth
1342	3-Bromopropylamine hydrobromide	3-Bromo-1-propanamine hydrobromide	$C_3H_9Br_2N$	5003-71-4	218.918		171.5				



Bromopentafluorobenzene



Bromopentafluoroethane



1-Bromopentane



2-Bromopentane


3-Bromopentane



5-Bromopentanenitrile



5-Bromopentanoic acid



5-Bromo-1-pentene



9-Bromophenanthrene



2-Bromophenol



3-Bromophenol



4-Bromophenol



Bromophenol Blue



1-Bromo-4-phenoxybenzene



(4-Bromophenoxy)trimethylsilane



N-(4-Bromophenyl)acetamide



1-(3-Bromophenyl)ethanone



1-(4-Bromophenyl)ethanone



(4-Bromophenyl)hydrazine



2-(4-Bromophenyl)-1*H*-indene-1,3(2*H*)-dione


(4-Bromophenyl)phenylmethanone



2-Bromo-1-phenyl-1-propanone


Bromophos



Bromophos-ethyl



1-Bromopropane



2-Bromopropane



3-Bromopropanenitrile


2-Bromopropanoic acid, (±)


3-Bromopropanoic acid


3-Bromo-1-propanol


1-Bromo-2-propanol



2-Bromopropanoyl bromide



2-Bromopropanoyl chloride



cis-1-Bromopropene



trans-1-Bromopropene


2-Bromopropene



3-Bromopropene



(3-Bromo-1-propenyl)benzene



(3-Bromopropoxy)benzene


3-Bromopropylamine hydrobromide

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1343	Bromopropylate	4,4'-Dibromobenzilic acid isopropyl ester	$C_{17}H_{16}Br_2O_3$	18181-80-1	428.115		77		1.59^{20}		
1344	(3-Bromopropyl)benzene		$C_9H_{11}Br$	637-59-2	199.087			219.5; 117^{25}	1.3106^{25}	1.5440^{25}	i H_2O; vs eth
1345	3-Bromo-1-propyne	Propargyl bromide	C_3H_3Br	106-96-7	118.960			89	1.579^{19}	1.4922^{20}	s EtOH, eth, bz, ctc, chl
1346	2-Bromopyridine		C_5H_4BrN	109-04-6	157.997	liq	-40.1	193; 75^{13}	1.6337^{20}	1.5734^{20}	sl H_2O; s EtOH, eth, ctc
1347	3-Bromopyridine		C_5H_4BrN	626-55-1	157.997	liq	-27.3	173; 69^{18}	1.645^{0}	1.5694^{20}	s H_2O; vs EtOH, eth
1348	4-Bromopyridine		C_5H_4BrN	1120-87-2	157.997		0.5	$29^{0.4}$	1.6450^{0}	1.5694^{20}	s ace, bz
1349	5-Bromo-2,4(1*H*,3*H*)-pyrimidinedione	5-Bromouracil	$C_4H_3BrN_2O_2$	51-20-7	190.983		310				
1350	3-Bromoquinoline		C_9H_6BrN	5332-24-1	208.055	ye oil	13.3	275		1.6641^{20}	s chl; vs HOAc
1351	6-Bromoquinoline		C_9H_6BrN	5332-25-2	208.055		24	281			s EtOH, eth, acid
1352	*N*-Bromosuccinimide		$C_4H_4BrNO_2$	128-08-5	177.985	cry (bz)	174		2.098^{25}		sl H_2O, AcOEt, eth; vs ace; i hx
1353	1-Bromotetradecane		$C_{14}H_{29}Br$	112-71-0	277.284		5.6	307	1.0170^{20}	1.4603^{20}	vs ace, bz, EtOH
1354	2-Bromothiazole		C_3H_2BrNS	3034-53-5	164.024			171	1.82^{25}	1.5927^{20}	
1355	1-(5-Bromo-2-thienyl)ethanone		C_6H_5BrOS	5370-25-2	205.072	nd (al)	94.5	103^{4}			sl EtOH; s ctc
1356	2-Bromothiophene	2-Thienyl bromide	C_4H_3BrS	1003-09-4	163.036			150	1.684^{20}	1.5868^{20}	i H_2O; vs eth, ace; s ctc
1357	3-Bromothiophene		C_4H_3BrS	872-31-1	163.036			159.5	1.735^{20}	1.5919^{20}	i H_2O; s ace, bz; sl chl
1358	Bromothymol Blue	Bromthymol Blue	$C_{27}H_{28}Br_2O_5S$	76-59-5	624.381		201				vs eth, EtOH
1359	2-Bromotoluene		C_7H_7Br	95-46-5	171.035	liq	-27.8	181.7	1.4232^{20}	1.5565^{20}	i H_2O; vs EtOH, eth, bz; msc ctc
1360	3-Bromotoluene		C_7H_7Br	591-17-3	171.035	liq	-39.8	183.7	1.4099^{20}	1.5510^{20}	i H_2O; s EtOH, ace, chl; msc eth; sl ctc
1361	4-Bromotoluene		C_7H_7Br	106-38-7	171.035	cry (al)	28.5	184.3	1.3959^{35}	1.5477^{20}	i H_2O; s EtOH, eth, ace, bz, chl; sl ctc
1362	Bromotrichloromethane		$CBrCl_3$	75-62-7	198.274	liq	-5.65	105	2.012^{25}	1.5065^{20}	vs eth, EtOH
1363	1-Bromotridecane		$C_{13}H_{27}Br$	765-09-3	263.257		6.2	292	1.0234^{25}	1.4574^{25}	i H_2O; vs chl
1364	Bromotriethylsilane		$C_6H_{15}BrSi$	1112-48-7	195.173	liq	-49.3	163; 66^{24}	1.143^{20}	1.4561^{20}	
1365	2-Bromo-1,1,1-trifluoroethane		$C_2H_2BrF_3$	421-06-7	162.936	vol liq or gas	-93.9	26	1.7881^{20}	1.3331^{20}	
1366	Bromotrifluoroethene		C_2BrF_3	598-73-2	160.920	col gas		-2.5			
1367	Bromotrifluoromethane		$CBrF_3$	75-63-8	148.910	col gas	-172	-57.8	1.5800^{20}		i H_2O; vs chl
1368	1-Bromo-2-(trifluoromethyl) benzene		$C_7H_4BrF_3$	392-83-6	225.006			167.5	1.652^{25}	1.4817^{20}	
1369	1-Bromo-3-(trifluoromethyl) benzene		$C_7H_4BrF_3$	401-78-5	225.006		1	151.5	1.613^{25}	1.4716^{20}	
1370	1-Bromo-4-(trifluoromethyl) benzene		$C_7H_4BrF_3$	402-43-7	225.006			160	1.607^{25}	1.4705^{25}	
1371	2-Bromo-1,3,5-trimethylbenzene		$C_9H_{11}Br$	576-83-0	199.087	liq	-1	225	1.3191^{10}	1.5510^{20}	i H_2O; vs eth; s bz; sl ctc
1372	Bromotrinitromethane		$CBrN_3O_6$	560-95-2	229.931		17.5	56^{10}	2.0312^{20}	1.4808^{20}	vs EtOH, chl
1373	Bromotriphenylmethane	Triphenylmethyl bromide	$C_{19}H_{15}Br$	596-43-0	323.226		153	230^{15}	1.5500^{20}		
1374	1-Bromoundecane		$C_{11}H_{23}Br$	693-67-4	235.205	liq	-9.7	258.8	1.0494^{25}	1.4552^{25}	sl ctc
1375	11-Bromoundecanoic acid		$C_{11}H_{21}BrO_2$	2834-05-1	265.188	nd (liq)	57	188^{18}			vs ace, bz, eth, EtOH
1376	(1-Bromovinyl)benzene		C_8H_7Br	98-81-7	183.046		-44	86^{14}, 71^{3}	1.4025^{23}	1.5881^{20}	
1377	(*cis*-2-Bromovinyl)benzene		C_8H_7Br	588-73-8	183.046		-7	55^{2}	1.4322^{10}	1.5990^{22}	
1378	(*trans*-2-Bromovinyl)benzene		C_8H_7Br	588-72-7	183.046		7	dec 219; 108^{20}	1.4269^{16}	1.6093^{20}	i H_2O; msc EtOH, eth; s chl
1379	1-Bromo-2-vinylbenzene		C_8H_7Br	2039-88-5	183.046	liq	-52.8	209.2; 98^{20}	1.4160^{20}	1.5927^{20}	
1380	1-Bromo-3-vinylbenzene		C_8H_7Br	2039-86-3	183.046			92^{20}	1.4059^{20}	1.5933^{20}	
1381	1-Bromo-4-vinylbenzene		C_8H_7Br	2039-82-9	183.046		7.7	212; 103^{20}	1.3984^{20}	1.5947^{20}	i H_2O; vs chl; s HOAc
1382	Brompheniramine		$C_{16}H_{19}BrN_2$	86-22-6	319.239	ye oily liq		$150^{0.5}$			s dil acid
1383	Brucine		$C_{23}H_{26}N_2O_4$	357-57-3	394.463	mcl pr (w +4)	178				sl H_2O, eth, bz; vs EtOH, chl
1384	Brucine hydrochloride	2,3-Dimethoxystrychnidin-10-one, monohydrochloride	$C_{23}H_{27}ClN_2O_4$	5786-96-9	430.924	pr					vs H_2O, EtOH
1385	Brucine sulfate heptahydrate	2,3-Dimethoxystrychnidin-10-one, sulfate, heptahydrate	$C_{46}H_{68}N_4O_{19}S$	60583-39-3	1013.113	nd (w)					s H_2O; sl EtOH, chl, tfa; vs MeOH; i bz
1386	Bucolome	5-Butyl-1-cyclohexyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	$C_{14}H_{22}N_2O_3$	841-73-6	266.336	nd (MeOH)	84	$186^{0.8}$			



Bromopropylate



(3-Bromopropyl)benzene



3-Bromo-1-propyne



2-Bromopyridine



3-Bromopyridine



4-Bromopyridine


5-Bromo-2,4(1*H*,3*H*)-pyrimidinedione



3-Bromoquinoline


6-Bromoquinoline


N-Bromosuccinimide



1-Bromotetradecane


2-Bromothiazole


1-(5-Bromo-2-thienyl)ethanone



2-Bromothiophene


3-Bromothiophene



Bromothymol Blue



2-Bromotoluene



3-Bromotoluene



4-Bromotoluene


Bromotrichloromethane



1-Bromotridecane



Bromotriethylsilane



2-Bromo-1,1,1-trifluoroethane



Bromotrifluoroethene



Bromotrifluoromethane



1-Bromo-2-(trifluoromethyl)benzene


1-Bromo-3-(trifluoromethyl)benzene



1-Bromo-4-(trifluoromethyl)benzene



2-Bromo-1,3,5-trimethylbenzene



Bromotrinitromethane



Bromotriphenylmethane



1-Bromoundecane



11-Bromoundecanoic acid



(1-Bromovinyl)benzene



(*cis*-2-Bromovinyl)benzene



(*trans*-2-Bromovinyl)benzene



1-Bromo-2-vinylbenzene



1-Bromo-3-vinylbenzene



1-Bromo-4-vinylbenzene


Brompheniramine



Brucine



Brucine hydrochloride



Brucine sulfate heptahydrate



Bucolome


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1387	Bufotalin		$C_{26}H_{36}O_6$	471-95-4	444.560	cry (+1 al)	223 dec				i H_2O; s EtOH, chl
1388	Bulbocapnine		$C_{19}H_{19}NO_4$	298-45-3	325.359	pr (al)	199.5				i H_2O; s EtOH; vs chl
1389	*sec*-Bumeton	*N*-*sec*-Butyl-*N'*-ethyl-6-methoxy-1,3,5-triazine-2,4-diamine	$C_{10}H_{19}N_5O$	26259-45-0	225.291		87				
1390	BUSAN 72A	(2-Benzothiazolylthio)methyl thiocyanate	$C_9H_6N_2S_3$	21564-17-0	238.352	liq		dec			
1391	Butachlor		$C_{17}H_{26}ClNO_2$	23184-66-9	311.847		<-5	156$^{.5}$	1.070^{25}		
1392	1,2-Butadiene	Methylallene	C_4H_6	590-19-2	54.091	vol liq or gas	-136.2	10.9	0.676^{0}	1.4205^{1}	i H_2O; msc EtOH, eth; vs bz
1393	1,3-Butadiene	Divinyl	C_4H_6	106-99-0	54.091	col gas	-108.91	-4.41	0.6149^{25} (p>1 atm	1.4292^{-25}	i H_2O; s EtOH, eth, bz; vs ace
1394	1,3-Butadien-1-ol acetate		$C_6H_8O_2$	1515-76-0	112.127			58^{40}	0.945^{25}	1.4690^{20}	
1395	(*trans*)-1,3-Butadienylbenzene		$C_{10}H_{10}$	16939-57-4	130.186		2.3	76^{11}	0.9286^{20}	1.6089^{25}	i H_2O; s EtOH, eth, ace, bz
1396	1,3-Butadiyne	Diacetylene	C_4H_2	460-12-8	50.059	vol liq or gas	-36.4	10.3	0.7364^{0}	1.4189^{5}	vs H_2O, eth, ace; s chl, EtOH
1397	Butalbital	5-Isobutyl-5-allyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	$C_{11}H_{16}N_2O_3$	77-26-9	224.256	pr	138.5				sl H_2O; s EtOH, eth, ace, chl; i lig
1398	Butanal	Butyraldehyde	C_4H_8O	123-72-8	72.106	liq	-96.86	74.8	0.8016^{20}	1.3843^{20}	s H_2O; msc EtOH; vs ace, bz; sl chl
1399	Butanal oxime		C_4H_9NO	110-69-0	87.120	liq	-29.5	154	0.923^{20}		vs H_2O, ace, bz; msc EtOH, eth; s chl
1400	Butanamide	Butyramide	C_4H_9NO	541-35-5	87.120	lf (bz)	114.8	216	0.8850^{120}	1.4087^{130}	sl H_2O, eth; i bz; s EtOH
1401	Butane		C_4H_{10}	106-97-8	58.122	col gas	-138.3	-0.5	0.573^{25} (p>1 atm)	1.3326^{20}	i H_2O; vs EtOH, eth, chl
1402	Butanedial		$C_4H_6O_2$	638-37-9	86.090			dec 170; 58^{9}	1.065^{20}	1.4262^{18}	vs H_2O, ace, eth, EtOH
1403	1,4-Butanediamine	Putrescine	$C_4H_{12}N_2$	110-60-1	88.151	lf	21.91	158.5	0.877^{25}	1.4969^{20}	s H_2O
1404	1,4-Butanediamine dihydrochloride		$C_4H_{14}Cl_2N_2$	333-93-7	161.073	nd or lf (al, w)	280 dec	sub			vs H_2O, EtOH; i eth, bz, MeOH
1405	1,2-Butanediol, (±)		$C_4H_{10}O_2$	26171-83-5	90.121			190.5	1.0024^{20}	1.4378^{20}	s H_2O, EtOH, ace
1406	1,3-Butanediol	1,3-Butylene glycol	$C_4H_{10}O_2$	107-88-0	90.121		<-50	207.5	1.0053^{20}	1.4401^{20}	
1407	1,4-Butanediol	Tetramethylene glycol	$C_4H_{10}O_2$	110-63-4	90.121		20.4	235	1.0171^{20}	1.4460^{20}	msc H_2O; s EtOH, DMSO; sl eth
1408	2,3-Butanediol		$C_4H_{10}O_2$	6982-25-8	90.121	cry (eth)	7.6	182.5	1.0033^{20}	1.4310^{25}	msc H_2O, EtOH; s eth, ace, chl
1409	1,4-Butanediol diacetate		$C_8H_{14}O_4$	628-67-1	174.195		12	229	1.0479^{15}	1.4251^{15}	
1410	1,4-Butanediol diacrylate		$C_{10}H_{14}O_4$	1070-70-8	198.216			83$^{0.3}$	1.105^{25}		
1411	1,4-Butanediol diglycidyl ether	1,4-Bis(2,3-epoxypropoxy) butane	$C_{10}H_{18}O_4$	2425-79-8	202.248			266; 155^{11}	1.1^{25}	1.4611^{20}	
1412	1,3-Butanediol dimethacrylate		$C_{12}H_{18}O_4$	1189-08-8	226.269			290		1.4495^{25}	vs ace, eth, EtOH, lig
1413	1,4-Butanediol dimethacrylate		$C_{12}H_{18}O_4$	2082-81-7	226.269	liq		133^{4}, 76$^{0.027}$	1.025^{20}	1.4560^{20}	sl H_2O
1414	1,4-Butanediol dimethylsulfonate	Busulfan	$C_6H_{14}O_6S_2$	55-98-1	246.301	cry	116				i H_2O; sl EtOH, ace
1415	2,3-Butanedione	Diacetyl	$C_4H_6O_2$	431-03-8	86.090	liq	-1.2	88	0.9808^{18}	1.3951^{20}	vs H_2O; msc EtOH, eth; s bz, ctc
1416	2,3-Butanedione monooxime		$C_4H_7NO_2$	57-71-6	101.105	pr (chl), lf (w)	76.8	185.5			sl H_2O; vs EtOH, eth, chl; s alk
1417	Butanedioyl dichloride	Succinyl chloride	$C_4H_4Cl_2O_2$	543-20-4	154.980	pl or lf	20	193.3	1.3748^{20}	1.4683^{20}	s eth, ace, bz
1418	1,4-Butanedithiol	Tetramethylenedithiol	$C_4H_{10}S_2$	1191-08-8	122.252	liq	-53.9	195.5	1.0021^{0}	1.5290^{20}	i H_2O; vs EtOH; sl ctc
1419	Butanenitrile	Propyl cyanide	C_4H_7N	109-74-0	69.106	liq	-111.9	117.6	0.7936^{20}	1.3842^{20}	sl H_2O, ctc; msc EtOH, eth; s bz
1420	1-Butanesulfonyl chloride		$C_4H_9ClO_2S$	2386-60-9	156.631			75^{10}		1.4559^{20}	
1421	1,4-Butane sultone	1,2-Oxathiane 2,2-dioxide	$C_4H_8O_3S$	1633-83-6	136.170	liq	13.5	135^{4}	1.331^{20}	1.4640^{20}	
1422	1,2,3,4-Butanetetracarboxylic acid		$C_8H_{10}O_8$	1703-58-8	234.160	lf (w) cry (ace)	236.5				vs H_2O, EtOH
1423	1,2,3,4-Butanetetrol	Erythritol	$C_4H_{10}O_4$	149-32-6	122.120	bipym tetr pr	121.5	330.5	1.451^{20}		s H_2O; i eth, bz
1424	1,2,3,4-Butanetetrol tetranitrate, (*R**,*S**)	Erythrityl tetranitrate	$C_4H_6N_4O_{12}$	7297-25-8	302.111		61				vs EtOH
1425	1-Butanethiol	Butyl mercaptan	$C_4H_{10}S$	109-79-5	90.187	liq	-115.7	98.5	0.8416^{20}	1.4440^{20}	sl H_2O, chl; vs EtOH, eth


Bufotalin


Bulbocapnine



sec-Bumeton



BUSAN 72A


Butachlor



1,2-Butadiene



1,3-Butadiene



1,3-Butadien-1-ol acetate



(*trans*)-1,3-Butadienylbenzene

1,3-Butadiyne



Butalbital



Butanal



Butanal oxime



Butanamide



Butane



Butanedial


1,4-Butanediamine



1,4-Butanediamine dihydrochloride



1,2-Butanediol, (±)



1,3-Butanediol



1,4-Butanediol



2,3-Butanediol



1,4-Butanediol diacetate


1,4-Butanediol diacrylate



1,4-Butanediol diglycidyl ether



1,3-Butanediol dimethacrylate



1,4-Butanediol dimethacrylate



1,4-Butanediol dimethylsulfonate



2,3-Butanedione



2,3-Butanedione monooxime



Butanedioyl dichloride



1,4-Butanedithiol



Butanenitrile



1-Butanesulfonyl chloride


1,4-Butane sultone


1,2,3,4-Butanetetracarboxylic acid



1,2,3,4-Butanetetrol



1,2,3,4-Butanetetrol tetranitrate, (*R*,S**)



1-Butanethiol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1426	2-Butanethiol	*sec*-Butyl mercaptan	$C_4H_{10}S$	91840-99-2	90.187	liq	-165	85.0	0.8295^{20}	1.4366^{20}	s EtOH, eth, bz, peth; sl ctc
1427	1,2,4-Butanetriol		$C_4H_{10}O_3$	3068-00-6	106.120			190^{18}, 172^{12}	1.18^{20}	1.4688^{20}	vs H_2O, EtOH
1428	Butanilicaine	2-(Butylamino)-*N*-(2-chloro-6-methylphenyl)acetamide	$C_{13}H_{19}ClN_2O$	3785-21-5	254.755	cry	46	$145^{0.001}$			
1429	Butanoic acid	Butyric acid	$C_4H_8O_2$	107-92-6	88.106	liq	-5.1	163.75	0.9528^{25}	1.3980^{20}	msc H_2O, EtOH, eth; sl ctc
1430	Butanoic anhydride	Butyric anhydride	$C_8H_{14}O_3$	106-31-0	158.195	liq	-75	200	0.9668^{20}	1.4070^{20}	s eth; sl ctc
1431	1-Butanol	Butyl alcohol	$C_4H_{10}O$	71-36-3	74.121	liq	-88.6	117.73	0.8095^{20}	1.3988^{20}	s H_2O, bz; msc EtOH, eth; vs ace
1432	2-Butanol	*sec*-Butyl alcohol	$C_4H_{10}O$	78-92-2	74.121	liq	-88.5	99.51	0.8063^{20}	1.3978^{20}	vs H_2O; msc EtOH, eth; s bz, ctc
1433	2-Butanone	Methyl ethyl ketone	C_4H_8O	78-93-3	72.106	liq	-86.64	79.59	0.7999^{25}	1.3788^{20}	vs H_2O; msc EtOH, eth, ace, bz; s chl
1434	2-Butanone (1-methylpropylidene) hydrazone		$C_8H_{16}N_2$	5921-54-0	140.226			171.5	0.8404^{20}	1.4511^{20}	
1435	2-Butanone oxime		C_4H_9NO	96-29-7	87.120	liq	-29.5	152.5	0.9232^{20}	1.4410^{20}	s H_2O, chl; msc EtOH, eth
1436	2-Butanone peroxide	Methyl ethyl ketone peroxide	$C_8H_{16}O_4$	1338-23-4	176.211	col liq		exp 110			sl H_2O; misc os
1437	Butanoyl chloride	*n*-Butyryl chloride	C_4H_7ClO	141-75-3	106.551	liq	-89	102	1.0277^{20}	1.4121^{20}	msc eth
1438	Butaperazine		$C_{24}H_{31}N_3OS$	653-03-2	409.587			$275^{0.05}$			
1439	Butazolamide	*N*-[5-(Aminosulfonyl)-1,3,4-thiadiazol-2-yl]butanamide	$C_6H_{10}N_4O_3S_2$	16790-49-1	250.298	cry	261 dec				
1440	*trans*-2-Butenal	*trans*-Crotonaldehyde	C_4H_6O	123-73-9	70.090	liq	-76	102.2	0.8516^{20}	1.4366^{20}	s H_2O, chl; vs EtOH, eth, ace; msc bz
1441	1-Butene	1-Butylene	C_4H_8	106-98-9	56.107	col gas	-185.34	-6.26	0.588^{25} (p>1 atm)	1.3962^{20}	i H_2O; vs EtOH, eth; s bz
1442	*cis*-2-Butene		C_4H_8	590-18-1	56.107	col gas	-138.88	3.71	0.616^{25} (p>1 atm)	1.3931^{-25}	i H_2O; vs EtOH, eth; s bz
1443	*trans*-2-Butene		C_4H_8	624-64-6	56.107	col gas	-105.52	0.88	0.599^{25} (p>1 atm)	1.3848^{-25}	s bz
1444	*trans*-2-Butenedinitrile		$C_4H_2N_2$	764-42-1	78.072	nd (bz-peth)	96.8	186	0.9416^{111}	1.4349^{111}	s H_2O, EtOH, eth, ace, bz, chl; sl peth
1445	*cis*-2-Butene-1,4-diol		$C_4H_8O_2$	6117-80-2	88.106		2.0	235	1.0698^{20}	1.4782^{20}	s H_2O; vs EtOH
1446	*trans*-2-Butene-1,4-diol		$C_4H_8O_2$	821-11-4	88.106		25	131^{13}	1.0700^{20}	1.4755^{20}	vs H_2O, EtOH
1447	*trans*-2-Butenedioyl dichloride	Fumaric acid dichloride	$C_4H_2Cl_2O_2$	627-63-4	152.964	pa ye lig		159	1.408^{20}	1.5004^{18}	
1448	*cis*-2-Butenenitrile	Isocrotononitrile	C_4H_5N	1190-76-7	67.090	liq		107.4			
1449	*trans*-2-Butenenitrile	Crotononitrile	C_4H_5N	627-26-9	67.090	liq	-51.5	120	0.8239^{20}	1.4225^{20}	s eth, ace
1450	3-Butenenitrile	Allyl cyanide	C_4H_5N	109-75-1	67.090	liq	-87	119	0.8341^{20}	1.4060^{20}	sl H_2O; msc EtOH, eth
1451	*cis*-2-Butenoic acid	Isocrotonic acid	$C_4H_6O_2$	503-64-0	86.090	nd or pr (peth)	15	169	1.0267^{20}	1.4450^{20}	vs H_2O; s EtOH
1452	*trans*-2-Butenoic acid	Crotonic acid	$C_4H_6O_2$	107-93-7	86.090	mcl pr or nd (w, lig)	71.5	184.7	0.9604^{77}	1.4249^{77}	vs H_2O, EtOH; s eth, ace, lig
1453	3-Butenoic acid		$C_4H_6O_2$	625-38-7	86.090	liq	-35	169	1.0091^{20}	1.4239^{20}	s H_2O; msc EtOH, eth
1454	2-Butenoic anhydride	Crotonic acid anhydride	$C_8H_{10}O_3$	623-68-7	154.163			247; 129^{19}	1.0397^{20}	1.4745^{20}	vs eth
1455	*cis*-2-Buten-1-ol	*cis*-Crotyl alcohol	C_4H_8O	4088-60-2	72.106			123	0.8662^{20}	1.4342^{25}	s H_2O
1456	*trans*-2-Buten-1-ol	*trans*-Crotyl alcohol	C_4H_8O	504-61-0	72.106		<-30	121.2	0.8521^{20}	1.4288^{20}	vs H_2O; msc EtOH, eth; s chl
1457	3-Buten-1-ol		C_4H_8O	627-27-0	72.106			113.5	0.8424^{20}	1.4224^{20}	s H_2O, ace; msc EtOH, eth; sl chl
1458	3-Buten-2-ol		C_4H_8O	598-32-3	72.106			97			
1459	3-Buten-2-one	Methyl vinyl ketone	C_4H_6O	78-94-4	70.090			81.4	0.864^{20}	1.4081^{20}	s H_2O, EtOH, bz; vs eth, ace; sl ctc
1460	2-Butenoyl chloride		C_4H_5ClO	10487-71-5	104.535			124.5	1.0905^{20}	1.460^{18}	vs ace
1461	(*trans*-1-Butenyl)benzene		$C_{10}H_{12}$	1005-64-7	132.202	liq	-43.1	198.7	0.9019^{20}	1.5420^{20}	i H_2O; s EtOH, eth, bz, ctc
1462	2-Butenylbenzene		$C_{10}H_{12}$	1560-06-1	132.202			176	0.8831^{20}	1.5101^{20}	
1463	3-Butenylbenzene		$C_{10}H_{12}$	768-56-9	132.202	liq	-70	177	0.8831^{20}	1.5059^{20}	i H_2O; s eth, bz
1464	1-Buten-3-yne	Vinylacetylene	C_4H_4	689-97-4	52.075	col gas		5.1	0.7094^{0}	1.4161^{1}	i H_2O; s bz
1465	Butethamine hydrochloride	2-Isobutylaminoethyl 4-aminobenzoate	$C_{13}H_{21}ClN_2O_2$	553-68-4	272.771	cry	194				s H_2O; sl EtOH, bz, chl; i eth



2-Butanethiol


1,2,4-Butanetriol


Butanilicaine



Butanoic acid



Butanoic anhydride



1-Butanol



2-Butanol



2-Butanone



2-Butanone (1-methylpropylidene)hydrazone



2-Butanone oxime


2-Butanone peroxide


Butanoyl chloride


Butaperazine



Butazolamide


trans-2-Butenal



1-Butene



cis-2-Butene


trans-2-Butene



trans-2-Butenedinitrile



cis-2-Butene-1,4-diol


trans-2-Butene-1,4-diol



trans-2-Butenedioyl dichloride



cis-2-Butenenitrile



trans-2-Butenenitrile



3-Butenenitrile



cis-2-Butenoic acid



trans-2-Butenoic acid


3-Butenoic acid


2-Butenoic anhydride



cis-2-Buten-1-ol



trans-2-Buten-1-ol



3-Buten-1-ol



3-Buten-2-ol


3-Buten-2-one



2-Butenoyl chloride


(*trans*-1-Butenyl)benzene



2-Butenylbenzene



3-Butenylbenzene



1-Buten-3-yne



Butethamine hydrochloride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1466	Buthalital sodium		$C_{11}H_{15}N_2NaO_2S$	510-90-7	262.304						vs H_2O; sl EtOH; i eth, bz
1467	Buthiazide		$C_{11}H_{16}ClN_3O_4S_2$	2043-38-1	353.846		221.5				
1468	Buthiobate	Denmert	$C_{21}H_{28}N_2S_2$	51308-54-4	372.590	ye oil	32		1.0865^{25}	1.596^{26}	i H_2O; s os
1469	Butonate		$C_8H_{14}Cl_3O_5P$	126-22-7	327.527			129$^{0.5}$			
1470	Butoxyacetylene		$C_6H_{10}O$	3329-56-4	98.142			104	0.8200^{20}	1.4067	vs eth, EtOH
1471	4-Butoxyaniline		$C_{10}H_{15}NO$	4344-55-2	165.232			132^{4}			
1472	4-Butoxybenzaldehyde		$C_{11}H_{14}O_2$	5736-88-9	178.228			148^{10}			
1473	2-Butoxyethanol	Ethylene glycol monobutyl ether	$C_6H_{14}O_2$	111-76-2	118.174	liq	-74.8	168.4	0.9015^{20}	1.4198^{20}	msc H_2O, EtOH, eth; sl ctc
1474	2-[2-(2-Butoxyethoxy)ethoxy] ethanol		$C_{10}H_{22}O_4$	143-22-6	206.280			278	0.9890^{20}	1.4389^{20}	vs EtOH, MeOH
1475	2-(2-Butoxyethoxy)ethyl thiocyanate	Lethane 384	$C_9H_{17}NO_2S$	112-56-1	203.302	liq		122$^{0.25}$			i H_2O; vs os
1476	1-(2-Butoxyethoxy)-2-propanol		$C_9H_{20}O_3$	124-16-3	176.253	col liq	-90	230	0.931^{20}		s H_2O
1477	2-Butoxyethyl acetate	Ethylene glycol monobutyl ether acetate	$C_8H_{16}O_3$	112-07-2	160.211	liq		192			
1478	2-Butoxyethyl (2,4-dichlorophenoxy)acetate	2,4-D 2-Butoxyethyl ester	$C_{14}H_{18}Cl_2O_4$	1929-73-3	321.197			159^{1}	1.232^{20}		
1479	2-Butoxyethyl (2,4,5-trichlorophenoxy)acetate	2,4,5-T Butoxyethyl ester	$C_{14}H_{17}Cl_3O_4$	2545-59-7	355.642			164^{1}	1.280^{20}		s ctc
1480	4-Butoxy-*N*-hydroxybenzeneacetamide	Bufexamac	$C_{12}H_{17}NO_3$	2438-72-4	223.268	nd (ace)	154				
1481	1-Butoxy-4-methylbenzene		$C_{11}H_{16}O$	10519-06-9	164.244			229.5	0.9205^{25}	1.4970^{20}	s eth
1482	4-Butoxyphenol		$C_{10}H_{14}O_2$	122-94-1	166.217		65.5	125^{4}			vs ace, bz, eth, EtOH
1483	4-[3-(4-Butoxyphenoxy)propyl] morpholine	Pramoxine	$C_{17}H_{27}NO_3$	140-65-8	293.401			196^{6}			
1484	1-Butoxy-2-propanol		$C_7H_{16}O_2$	5131-66-8	132.201			171.5; 71^{20}	0.882^{20}	1.4168^{20}	s EtOH, eth, bz, ctc, MeOH
1485	Butralin	4-*tert*-Butyl-*N*-*sec*-butyl-2,6-dinitroaniline	$C_{14}H_{21}N_3O_4$	33629-47-9	295.335		60	135$^{0.5}$			
1486	*N*-Butylacetamide		$C_6H_{13}NO$	1119-49-9	115.173			229	0.8960^{25}	1.4388^{25}	
1487	Butyl acetate		$C_6H_{12}O_2$	123-86-4	116.158	liq	-78	126.1	0.8825^{20}	1.3941^{20}	sl H_2O; msc EtOH, eth; s ace, chl
1488	*sec*-Butyl acetate		$C_6H_{12}O_2$	105-46-4	116.158	liq	-98.9	112	0.8748^{20}	1.3888^{20}	sl H_2O, ctc; s EtOH, eth
1489	*tert*-Butyl acetate		$C_6H_{12}O_2$	540-88-5	116.158			95.1	0.8665^{20}	1.3855^{20}	s EtOH, eth, chl, HOAc
1490	*tert*-Butylacetic acid		$C_6H_{12}O_2$	1070-83-3	116.158		6.5	190	0.9124^{20}	1.4096^{20}	s EtOH, eth
1491	Butyl acetoacetate		$C_8H_{14}O_3$	591-60-6	158.195		-35.6	127^{50}, 85^{8}	0.9671^{25}	1.4137^{20}	sl H_2O; msc EtOH, bz, lig
1492	Butyl acrylate		$C_7H_{12}O_2$	141-32-2	128.169	liq	-64.6	145	0.8898^{20}	1.4185^{20}	i H_2O; s EtOH, eth, ace; sl ctc
1493	*tert*-Butyl acrylate		$C_7H_{12}O_2$	1663-39-4	128.169	liq		120; 62^{60}	0.879^{25}	1.4110^{20}	
1494	Butylamine	1-Butanamine	$C_4H_{11}N$	109-73-9	73.137	liq	-49.1	77.00	0.7414^{20}	1.4031^{20}	msc H_2O; s EtOH, eth
1495	*sec*-Butylamine	2-Butanamine, (±)-	$C_4H_{11}N$	33966-50-6	73.137		<-72	62.73	0.7246^{20}	1.3932^{20}	s H_2O, chl; msc EtOH, eth; vs ace
1496	*tert*-Butylamine	2-Methyl-2-propanamine	$C_4H_{11}N$	75-64-9	73.137	liq	-66.94	44.04	0.6958^{20}	1.3784^{20}	msc H_2O, EtOH, eth; s chl
1497	Butylamine hydrochloride	1-Butanamine hydrochloride	$C_4H_{12}ClN$	3858-78-4	109.598		213		0.982^{20}		sl H_2O, EtOH
1498	Butyl 4-aminobenzoate	Butamben	$C_{11}H_{15}NO_2$	94-25-7	193.243	cry (al or bz)	58	173^{8}			i H_2O; s EtOH, eth, bz, chl
1499	2-(Butylamino)ethanol		$C_6H_{15}NO$	111-75-1	117.189			199; 91^{11}	0.8907^{20}	1.4437^{20}	vs H_2O, EtOH, eth
1500	2-(*tert*-Butylamino)ethanol		$C_6H_{15}NO$	4620-70-6	117.189		44	176.5; 72^{14}	0.8818^{20}		
1501	*N*-*tert*-Butylaminoethyl methacrylate		$C_{10}H_{19}NO_2$	3775-90-4	185.264			102^{12}			s chl
1502	2-(*tert*-Butylaminothio) benzothiazole	*N*-*tert*-Butyl-2-benzothiazolesulfenamide	$C_{11}H_{14}N_2S_2$	95-31-8	238.372		108				
1503	2-*sec*-Butylaniline		$C_{10}H_{15}N$	55751-54-7	149.233			120^{16}	0.9574^{20}		s EtOH, ace, bz; sl ctc
1504	4-Butylaniline		$C_{10}H_{15}N$	104-13-2	149.233	pa ye		261	0.945^{20}		sl ctc
1505	4-*sec*-Butylaniline		$C_{10}H_{15}N$	30273-11-1	149.233			238; 118^{15}	0.949^{15}	1.5360^{29}	vs bz, eth
1506	4-*tert*-Butylaniline		$C_{10}H_{15}N$	769-92-6	149.233	ye rd (peth)	17	241	0.9525^{15}	1.5380^{20}	sl H_2O; msc EtOH, eth; vs bz; s ctc
1507	*N*-Butylaniline		$C_{10}H_{15}N$	1126-78-9	149.233	liq	-14.4	243.5	0.9323^{20}	1.5341^{20}	vs eth, EtOH
1508	*N*-*tert*-Butylaniline		$C_{10}H_{15}N$	937-33-7	149.233			215; 95^{19}		1.5270^{20}	s EtOH; vs ace, bz, chl
1509	2-*tert*-Butyl-9,10-anthracenedione		$C_{18}H_{16}O_2$	84-47-9	264.319		99				s ctc, CS_2



Buthalital sodium



Buthiazide



Buthiobate



Butonate



Butoxyacetylene



4-Butoxyaniline



4-Butoxybenzaldehyde



2-Butoxyethanol



2-[2-(2-Butoxyethoxy)ethoxy]ethanol



2-(2-Butoxyethoxy)ethyl thiocyanate



1-(2-Butoxyethoxy)-2-propanol



2-Butoxyethyl acetate



2-Butoxyethyl (2,4-dichlorophenoxy)acetate



2-Butoxyethyl (2,4,5-trichlorophenoxy)acetate



4-Butoxy-*N*-hydroxybenzeneacetamide



1-Butoxy-4-methylbenzene



4-Butoxyphenol



4-[3-(4-Butoxyphenoxy)propyl]morpholine



1-Butoxy-2-propanol



Butralin



N-Butylacetamide



Butyl acetate



sec-Butyl acetate



tert-Butyl acetate


tert-Butylacetic acid


Butyl acetoacetate



Butyl acrylate



tert-Butyl acrylate



Butylamine



sec-Butylamine



tert-Butylamine



Butylamine hydrochloride



Butyl 4-aminobenzoate



2-(Butylamino)ethanol



2-(*tert*-Butylamino)ethanol



N-*tert*-Butylaminoethyl methacrylate



2-(*tert*-Butylaminothio)benzothiazole



2-*sec*-Butylaniline



4-Butylaniline


4-*sec*-Butylaniline



4-*tert*-Butylaniline



N-Butylaniline



N-*tert*-Butylaniline



2-*tert*-Butyl-9,10-anthracenedione


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1510	*tert*-Butyl azidoformate	*tert*-Butyl carbonazidate	$C_5H_9N_3O_2$	1070-19-5	143.144	unstab >80		73[70]			
1511	4-Butylbenzaldehyde		$C_{11}H_{14}O$	1200-14-2	162.228			123[7]		1.5265	
1512	4-*tert*-Butylbenzaldehyde		$C_{11}H_{14}O$	939-97-9	162.228	liq		107[11], 130[25]	0.970	1.5270[20]	
1513	Butylbenzene		$C_{10}H_{14}$	104-51-8	134.218	liq	-87.85	183.31	0.8601[20]	1.4898[20]	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
1514	*sec*-Butylbenzene, (±)	2-Phenylbutane	$C_{10}H_{14}$	36383-15-0	134.218	liq	-82.7	173.3	0.8621[20]	1.4902[20]	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
1515	*tert*-Butylbenzene		$C_{10}H_{14}$	98-06-6	134.218	liq	-57.8	169.1	0.8665[20]	1.4927[20]	i H_2O; vs EtOH, eth; msc ace, bz
1516	4-*tert*-Butyl-1,2-benzenediol		$C_{10}H_{14}O_2$	98-29-3	166.217		54.3	285; 160[22]			s tfa
1517	2-*tert*-Butyl-1,4-benzenediol		$C_{10}H_{14}O_2$	1948-33-0	166.217		128				
1518	*N*-*tert*-Butylbenzenemethanamine		$C_{11}H_{17}N$	3378-72-1	163.260			75[5]		1.4951[25]	
1519	4-*tert*-Butylbenzenemethanol		$C_{11}H_{16}O$	877-65-6	164.244			236; 140[20]	0.928[25]	1.5179[20]	
1520	Butyl benzoate		$C_{11}H_{14}O_2$	136-60-7	178.228	liq	-22.4	250.3	1.000[20]	1.4940[25]	i H_2O; msc EtOH, eth; s ace; sl ctc
1521	2-*tert*-Butylbenzoic acid		$C_{11}H_{14}O_2$	1077-58-3	178.228	pl (dil al)	80.5				vs EtOH
1522	3-*tert*-Butylbenzoic acid		$C_{11}H_{14}O_2$	7498-54-6	178.228	nd (peth)	128.8				vs EtOH, peth
1523	4-*tert*-Butylbenzoic acid		$C_{11}H_{14}O_2$	98-73-7	178.228	nd (dil al)	164.5				i H_2O; vs EtOH, bz; s chl
1524	4-Butylbenzoyl chloride		$C_{11}H_{13}ClO$	28788-62-7	196.673			155[26]	1.051[25]	1.5351[20]	
1525	4-*tert*-Butylbenzoyl chloride		$C_{11}H_{13}ClO$	1710-98-1	196.673			266; 135[20]	1.007[25]	1.5364[20]	
1526	2-Butyl-1,1'-biphenyl		$C_{16}H_{18}$	54532-97-7	210.314	liq	-9.65	291.2	0.9676[20]	1.5604[20]	
1527	*tert*-Butyl bromoacetate		$C_6H_{11}BrO_2$	5292-43-3	195.054			73[25]		1.4430[20]	vs eth, EtOH
1528	Butyl butanoate		$C_8H_{16}O_2$	109-21-7	144.212	liq	-91.5	166	0.8700[20]	1.4075[20]	i H_2O; msc EtOH, eth; s ctc
1529	Butyl *cis*-2-butenedioate	Monobutyl maleate	$C_8H_{12}O_4$	925-21-3	172.179	oil			1.09[25]		
1530	Butyl carbamate		$C_5H_{11}NO_2$	592-35-8	117.147	pr	53	dec 204; 108[14]			vs EtOH; sl chl
1531	Butyl chloroacetate		$C_6H_{11}ClO_2$	590-02-3	150.603			183	1.0704[20]	1.4297[20]	vs eth, EtOH
1532	*tert*-Butyl chloroacetate		$C_6H_{11}ClO_2$	107-59-5	150.603			150; 50[10]		1.4260[20]	dec H_2O
1533	Butylchlorodimethylsilane		$C_6H_{15}ClSi$	1000-50-6	150.722			139	0.876[20]	1.5145[20]	
1534	Butyl chloroformate		$C_5H_9ClO_2$	592-34-7	136.577			142	1.074[25]	1.4114[20]	msc eth; s ace; sl ctc
1535	*N*-Butyl-4-chloro-2-hydroxybenzamide	Buclosamide	$C_{11}H_{14}ClNO_2$	575-74-6	227.688		91.5				
1536	Butyl 2-chloropropanoate		$C_7H_{13}ClO_2$	54819-86-2	164.630			184	1.0253[20]	1.4263[20]	vs eth
1537	Butyl 3-chloropropanoate		$C_7H_{13}ClO_2$	27387-79-7	164.630			104[22], 92[6]	1.0370[20]	1.4321[20]	vs H_2O, eth
1538	*tert*-Butyl chromate		$C_8H_{18}CrO_4$	1189-85-1	230.223	red cry (peth)	-5				reac H_2O
1539	Butyl citrate		$C_{18}H_{32}O_7$	77-94-1	360.443		-20	233[22]	1.043[20]	1.4460[20]	
1540	Butyl cyanoacetate		$C_7H_{11}NO_2$	5459-58-5	141.168			231; 115[15]	1.0010[20]	1.4200[20]	
1541	Butylcyclohexane		$C_{10}H_{20}$	1678-93-9	140.266	liq	-74.73	180.9	0.7902[20]	1.4408[20]	i H_2O
1542	*sec*-Butylcyclohexane		$C_{10}H_{20}$	7058-01-7	140.266			179.3	0.8131[20]	1.4467[20]	i H_2O; s ace
1543	*tert*-Butylcyclohexane		$C_{10}H_{20}$	3178-22-1	140.266	liq	-41.2	171.5	0.8127[20]	1.4469[20]	i H_2O
1544	2-*tert*-Butylcyclohexanol		$C_{10}H_{20}O$	13491-79-7	156.265		45	139[95]	0.902[25]		
1545	*cis*-4-*tert*-Butylcyclohexanol		$C_{10}H_{20}O$	937-05-3	156.265		83	112[15]			
1546	*trans*-4-*tert*-Butylcyclohexanol		$C_{10}H_{20}O$	21862-63-5	156.265		83	112[15]			
1547	4-*tert*-Butylcyclohexanone		$C_{10}H_{18}O$	98-53-3	154.249		48	90[9]			
1548	Butylcyclohexylamine	*N*-Butylcyclohexanamine	$C_{10}H_{21}N$	10108-56-2	155.281		208.3				sl H_2O, ctc; vs EtOH, eth
1549	Butyl cyclohexyl phthalate		$C_{18}H_{24}O_4$	84-64-0	304.382	col liq		≈205[5]	1.076[25]		sl H_2O; misc os
1550	Butylcyclopentane		C_9H_{18}	2040-95-1	126.239	liq	-108	156.6	0.7846[20]	1.4316[20]	vs ace, bz, eth, EtOH
1551	Butyl dichloroacetate		$C_6H_{10}Cl_2O_2$	29003-73-4	185.048			193.5	1.1820[20]	1.4420[20]	vs eth, EtOH
1552	Butyl (2,4-dichlorophenoxy) acetate	2,4-D Butyl ester	$C_{12}H_{14}Cl_2O_3$	94-80-4	277.143		9	133[1]			
1553	5-Butyldihydro-2(3*H*)-furanone		$C_8H_{14}O_2$	104-50-7	142.196			132[20]	0.9796[19]	1.4451[19]	s EtOH; sl ctc
1554	Butyldimethylamine	*N,N*-Dimethyl-1-butanamine	$C_6H_{15}N$	927-62-8	101.190			95	0.7206[20]	1.3970[20]	msc H_2O, EtOH, eth, ace, bz
1555	1-*tert*-Butyl-3,5-dimethylbenzene		$C_{12}H_{18}$	98-19-1	162.271	liq	-18	207	0.8668[20]		s ctc
1556	4-*tert*-Butyl-2,6-dimethyl-3,5-dinitroacetophenone	Musk ketone	$C_{14}H_{18}N_2O_5$	81-14-1	294.303	ye cry	135.5				vs chl
1557	2-*tert*-Butyl-4,6-dimethylphenol		$C_{12}H_{18}O$	1879-09-0	178.270		22.3	249	0.917[80]	1.5183[20]	i alk
1558	4-*tert*-Butyl-2,5-dimethylphenol		$C_{12}H_{18}O$	17696-37-6	178.270		71.2	264	0.939[80]	1.5311[20]	s alk
1559	4-*tert*-Butyl-2,6-dimethylphenol		$C_{12}H_{18}O$	879-97-0	178.270		82.4	248	0.916[80]		s alk
1560	1-*tert*-Butyl-3,5-dimethyl-2,4,6-trinitrobenzene		$C_{12}H_{15}N_3O_6$	81-15-2	297.263	pl, nd (al)	110				i H_2O; sl EtOH; s eth, chl
1561	2-*tert*-Butyl-4,6-dinitrophenol		$C_{10}H_{12}N_2O_5$	1420-07-1	240.212	ye solid	126				



tert-Butyl azidoformate



4-Butylbenzaldehyde



4-*tert*-Butylbenzaldehyde



Butylbenzene



sec-Butylbenzene, (±)



tert-Butylbenzene



4-*tert*-Butyl-1,2-benzenediol



2-*tert*-Butyl-1,4-benzenediol



N-*tert*-Butylbenzenemethanamine



4-*tert*-Butylbenzenemethanol



Butyl benzoate



2-*tert*-Butylbenzoic acid



3-*tert*-Butylbenzoic acid



4-*tert*-Butylbenzoic acid



4-Butylbenzoyl chloride



4-*tert*-Butylbenzoyl chloride



2-Butyl-1,1'-biphenyl



tert-Butyl bromoacetate



Butyl butanoate



Butyl *cis*-2-butenedioate



Butyl carbamate



Butyl chloroacetate



tert-Butyl chloroacetate



Butylchlorodimethylsilane



Butyl chloroformate



N-Butyl-4-chloro-2-hydroxybenzamide



Butyl 2-chloropropanoate



Butyl 3-chloropropanoate



tert-Butyl chromate



Butyl citrate



Butyl cyanoacetate



Butylcyclohexane



sec-Butylcyclohexane



tert-Butylcyclohexane



2-*tert*-Butylcyclohexanol



cis-4-*tert*-Butylcyclohexanol



trans-4-*tert*-Butylcyclohexanol



4-*tert*-Butylcyclohexanone



Butylcyclohexylamine



Butyl cyclohexyl phthalate



Butylcyclopentane



Butyl dichloroacetate



Butyl (2,4-dichlorophenoxy)acetate



5-Butyldihydro-2(3*H*)-furanone



Butyldimethylamine



1-*tert*-Butyl-3,5-dimethylbenzene



4-*tert*-Butyl-2,6-dimethyl-3,5-dinitroacetophenone


2-*tert*-Butyl-4,6-dimethylphenol



4-*tert*-Butyl-2,5-dimethylphenol



4-*tert*-Butyl-2,6-dimethylphenol



1-*tert*-Butyl-3,5-dimethyl-2,4,6-trinitrobenzene



2-*tert*-Butyl-4,6-dinitrophenol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1562	5-Butyldocosane		$C_{26}H_{54}$	55282-16-1	366.707		208	244[10]	0.8058[20]	1.4503[20]	
1563	11-Butyldocosane		$C_{26}H_{54}$	13475-76-8	366.707			242.5[10]	0.8041[20]	1.4499[20]	
1564	Butyl dodecanoate		$C_{16}H_{32}O_2$	106-18-3	256.424			180[18]			
1565	Butylethylamine	*N*-Ethyl-1-butanamine	$C_6H_{15}N$	13360-63-9	101.190			107.5	0.7398[20]	1.4040[20]	msc EtOH, eth, ace, bz
1566	1-*tert*-Butyl-4-ethylbenzene		$C_{12}H_{18}$	7364-19-4	162.271	liq	-38.4	211	0.8641[20]		
1567	Butyl ethyl ether		$C_6H_{14}O$	628-81-9	102.174	liq	-124	92.3	0.7495[20]	1.3818[20]	i H_2O; msc EtOH, eth; vs ace
1568	*sec*-Butyl ethyl ether		$C_6H_{14}O$	2679-87-0	102.174			81	0.7503[20]	1.3802[20]	i H_2O; vs EtOH, eth
1569	*tert*-Butyl ethyl ether	Ethyl *tert*-butyl ether	$C_6H_{14}O$	637-92-3	102.174	liq	-94	72.6	0.736[25]	1.3756[20]	i H_2O; vs EtOH, eth
1570	2-*tert*-Butyl-4-ethylphenol		$C_{12}H_{18}O$	96-70-8	178.270		23	250			
1571	2-Butyl-2-ethyl-1,3-propanediol		$C_9H_{20}O_2$	115-84-4	160.254	wh cry	43.8	262	0.927[50]	1.4587[25]	sl H_2O, ace; s EtOH
1572	5-Butyl-5-ethyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	Butethal	$C_{10}H_{16}N_2O_3$	77-28-1	212.245		128.5				
1573	Butyl ethyl sulfide		$C_6H_{14}S$	638-46-0	118.240	liq	-95.1	144.3	0.8376[20]	1.4492[10]	vs EtOH; s chl
1574	*tert*-Butyl ethyl sulfide	2-Methyl-2-propanethiol	$C_6H_{14}S$	14290-92-7	118.240	liq	-88.9	120.4; 56[109]			
1575	*N*-*tert*-Butylformamide		$C_5H_{11}NO$	2425-74-3	101.147	liq	16	202	0.903	1.4330[20]	
1576	Butyl formate		$C_5H_{10}O_2$	592-84-7	102.132	liq	-91.5	106.1	0.8958[20]	1.3887[20]	sl H_2O; s ace; msc EtOH, eth
1577	*sec*-Butyl formate		$C_5H_{10}O_2$	589-40-2	102.132			97	0.8846[20]	1.3865[20]	sl H_2O; s ace; msc EtOH, eth
1578	*tert*-Butyl formate	1,1-Dimethylethyl formate	$C_5H_{10}O_2$	762-75-4	102.132	liq		82	0.872	1.3790[20]	
1579	Butyl glycidyl ether		$C_7H_{14}O_2$	2426-08-6	130.185			169; 75[26]	0.918[20]		
1580	Butyl heptanoate	Butyl enanthate	$C_{11}H_{22}O_2$	5454-28-4	186.292	liq	-67.5	226.2	0.8638[20]	1.4204[20]	vs ace, bz, eth, EtOH
1581	Butyl hexanoate	Butyl caproate	$C_{10}H_{20}O_2$	626-82-4	172.265	liq	-64.3	208	0.8653[20]	1.4152[20]	i H_2O; s EtOH; msc eth
1582	*tert*-Butylhydrazine hydrochloride		$C_4H_{13}ClN_2$	7400-27-3	124.612		192.5				
1583	Butyl hydrogen succinate	Monobutyl succinate	$C_8H_{14}O_4$	5150-93-6	174.195		8.6	136.5[3]	1.0732[20]	1.4360[20]	
1584	*tert*-Butyl hydroperoxide		$C_4H_{10}O_2$	75-91-2	90.121		6	dec 89; 36[17]	0.8960[20]	1.4015[20]	s H_2O, EtOH, eth, ctc, chl
1585	*tert*-Butyl-4-hydroxyanisole	Butylated hydroxyanisole	$C_{11}H_{16}O_2$	25013-16-5	180.244	wax	51	268			i H_2O; s peth, EtOH
1586	Butyl 2-hydroxybenzoate		$C_{11}H_{14}O_3$	2052-14-4	194.227	liq	-5.9	271	1.0728[20]	1.5115[20]	sl ctc
1587	Butyl 4-hydroxybenzoate	Butylparaben	$C_{11}H_{14}O_3$	94-26-8	194.227		68.5				sl H_2O, ctc; s EtOH
1588	Butyl *cis*-12-hydroxy-9-octadecenoate, (*R*)	Butyl ricinoleate	$C_{22}H_{42}O_3$	151-13-3	354.566			275[13]	0.9058[22]	1.4566[22]	vs eth
1589	*tert*-Butyl hypochlorite		C_4H_9ClO	507-40-4	108.566	ye liq		77.5	0.9583[18]	1.403[20]	i H_2O; vs eth, bz; s ace
1590	Butyl isobutyl ether		$C_8H_{18}O$	17071-47-5	130.228	liq		151	0.763[15]	1.4077[21]	vs ace, eth, EtOH
1591	*tert*-Butyl isobutyl ether		$C_8H_{18}O$	33021-02-2	130.228	liq		112.0			
1592	Butyl isocyanate		C_5H_9NO	111-36-4	99.131			115	0.880[20]	1.4060[20]	
1593	Butyl isocyanide		C_5H_9N	2769-64-4	83.132			120	0.78[20]		vs eth, EtOH
1594	*tert*-Butyl isopropyl ether		$C_7H_{16}O$	17348-59-3	116.201	liq	-88	87.6	0.7365[25]		s chl
1595	Butyl isothiocyanate	1-Isothiocyanatobutane	C_5H_9NS	592-82-5	115.197			168	0.9546[20]	1.501[20]	vs eth, EtOH
1596	*sec*-Butyl isothiocyanate, (±)	2-Isothiocyanatobutane, (±)	C_5H_9NS	116724-11-9	115.197			159.5	0.944[12]		vs eth, EtOH
1597	*tert*-Butyl isothiocyanate	2-Isothiocyanato-2-methylpropane	C_5H_9NS	590-42-1	115.197		10.5	140	0.9187[10]		
1598	Butyl lactate		$C_7H_{14}O_3$	34451-18-8	146.184			77[10]	0.9744[27]		vs eth, EtOH
1599	Butyl methacrylate		$C_8H_{14}O_2$	97-88-1	142.196			160	0.8936[20]	1.4240[20]	vs eth, EtOH
1600	*tert*-Butyl methacrylate		$C_8H_{14}O_2$	585-07-9	142.196			135.2			
1601	1-*tert*-Butyl-4-methoxybenzene		$C_{11}H_{16}O$	5396-38-3	164.244		19.0	238	0.9383[20]	1.5039[20]	
1602	1-*tert*-Butyl-2-methoxy-4-methyl-3,5-dinitrobenzene		$C_{12}H_{16}N_2O_5$	83-66-9	268.265	pa ye lf (al)	85	185[16]			i H_2O; sl EtOH; s eth, chl
1603	2-*tert*-Butyl-4-methoxyphenol		$C_{11}H_{16}O_2$	121-00-6	180.244			184[50]			
1604	3-*tert*-Butyl-4-methoxyphenol		$C_{11}H_{16}O_2$	88-32-4	180.244		65				
1605	Butylmethylamine	*N*-Methyl-1-butanamine	$C_5H_{13}N$	110-68-9	87.164			91	0.7637[15]		
1606	1-*tert*-Butyl-2-methylbenzene	2-*tert*-Butyltoluene	$C_{11}H_{16}$	1074-92-6	148.245	liq	-50.3	200.4	0.8897[20]	1.5076[20]	vs ace, bz, eth, EtOH
1607	1-*tert*-Butyl-3-methylbenzene	3-*tert*-Butyltoluene	$C_{11}H_{16}$	1075-38-3	148.245	liq	-41.4	189.3	0.8657[20]	1.4944[20]	vs ace, bz, eth, EtOH
1608	1-*tert*-Butyl-4-methylbenzene	4-*tert*-Butyltoluene	$C_{11}H_{16}$	98-51-1	148.245	liq	-52	190	0.8612[20]	1.4918[20]	i H_2O; sl EtOH; vs eth, chl; s ace, bz
1609	Butyl 2-methylbutanoate	Butyl *o*-toluate	$C_9H_{18}O_2$	15706-73-7	158.238			179	0.8620[20]	1.4135[20]	
1610	Butyl 3-methylbutanoate	Butyl *p*-toluate	$C_9H_{18}O_2$	109-19-3	158.238					1.4058[25]	



5-Butyldocosane



11-Butyldocosane



Butyl dodecanoate



Butylethylamine



1-*tert*-Butyl-4-ethylbenzene



Butyl ethyl ether


sec-Butyl ethyl ether



tert-Butyl ethyl ether



2-*tert*-Butyl-4-ethylphenol



2-Butyl-2-ethyl-1,3-propanediol



5-Butyl-5-ethyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione



Butyl ethyl sulfide



tert-Butyl ethyl sulfide



N-*tert*-Butylformamide



Butyl formate



sec-Butyl formate



tert-Butyl formate


Butyl glycidyl ether



Butyl heptanoate



Butyl hexanoate



tert-Butylhydrazine hydrochloride



Butyl hydrogen succinate


tert-Butyl hydroperoxide



tert-Butyl-4-hydroxyanisole



Butyl 2-hydroxybenzoate



Butyl 4-hydroxybenzoate



Butyl *cis*-12-hydroxy-9-octadecenoate, (*R*)



tert-Butyl hypochlorite



Butyl isobutyl ether



tert-Butyl isobutyl ether



Butyl isocyanate



Butyl isocyanide



tert-Butyl isopropyl ether



Butyl isothiocyanate



sec-Butyl isothiocyanate, (±)



tert-Butyl isothiocyanate



Butyl lactate



Butyl methacrylate



tert-Butyl methacrylate



1-*tert*-Butyl-4-methoxybenzene



1-*tert*-Butyl-2-methoxy-4-methyl-3,5-dinitrobenzene



2-*tert*-Butyl-4-methoxyphenol



3-*tert*-Butyl-4-methoxyphenol



Butylmethylamine


1-*tert*-Butyl-2-methylbenzene



1-*tert*-Butyl-3-methylbenzene


1-*tert*-Butyl-4-methylbenzene



Butyl 2-methylbutanoate



Butyl 3-methylbutanoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1611	Butyl methyl ether		$C_5H_{12}O$	628-28-4	88.148	liq	-115.7	70.16	0.7392^{25}	1.3736^{20}	i H_2O; msc EtOH, eth; s ace
1612	*sec*-Butyl methyl ether		$C_5H_{12}O$	116783-23-4	88.148			59.1	0.7415^{20}	1.3680^{25}	vs ace, eth, EtOH
1613	2-*tert*-Butyl-4-methylphenol		$C_{11}H_{16}O$	2409-55-4	164.244		51.5	237	0.9247^{75}	1.4969^{75}	sl H_2O; s ace, bz, chl
1614	2-*tert*-Butyl-5-methylphenol		$C_{11}H_{16}O$	88-60-8	164.244		46.5	127^{11}	0.922^{80}	1.5250^{20}	i H_2O; s EtOH, eth, ace
1615	2-*tert*-Butyl-6-methylphenol		$C_{11}H_{16}O$	2219-82-1	164.244		31	230	0.9240^{80}	1.5195^{20}	
1616	4-*tert*-Butyl-2-methylphenol		$C_{11}H_{16}O$	98-27-1	164.244		27.5	237; 132^{20}	0.965^{20}	1.5230^{20}	i H_2O; s eth, ace, bz
1617	Butyl methyl sulfide		$C_5H_{12}S$	628-29-5	104.214	liq	-97.8	123.4	0.8426^{20}	1.4477^{20}	vs EtOH, MeOH
1618	*tert*-Butyl methyl sulfide		$C_5H_{12}S$	6163-64-0	104.214	liq		98.9			
1619	4-Butylmorpholine		$C_8H_{17}NO$	1005-67-0	143.227	liq	-57.1	213.5	0.9068^{20}	1.4451^{20}	vs H_2O, ace, bz, EtOH
1620	1-Butylnaphthalene		$C_{14}H_{16}$	1634-09-9	184.277	liq	-19.8	289.3	0.9738^{20}	1.5819^{20}	i H_2O; s EtOH, eth, ace, bz
1621	2-Butylnaphthalene		$C_{14}H_{16}$	1134-62-9	184.277	liq	-2.5	292	0.9673^{20}	1.5777^{20}	vs ace, bz, EtOH
1622	Butyl nitrate		$C_4H_9NO_3$	928-45-0	119.119			133	1.0228^{30}	1.4013^{23}	i H_2O; s EtOH, eth; sl ctc
1623	Butyl nitrite		$C_4H_9NO_2$	544-16-1	103.120			78	0.9114^{25}	1.3762^{20}	msc EtOH, eth
1624	*tert*-Butyl nitrite		$C_4H_9NO_2$	540-80-7	103.120	pa ye liq		63	0.8670^{20}	1.368^{20}	sl H_2O; s EtOH, eth, chl, CS_2
1625	*sec*-Butyl nitrite		$C_4H_9NO_2$	924-43-6	103.120			68.5	0.8726^{20}	1.3710^{20}	vs eth, EtOH, chl
1626	4-(Butylnitrosoamino)-1-butanol	*N*-Butyl-*N*-(4-hydroxybutyl) nitrosamine	$C_8H_{18}N_2O_2$	3817-11-6	174.241			$115^{0.01}$			
1627	5-Butylnonane		$C_{13}H_{28}$	17312-63-9	184.361			217.5	0.7635^{18}	1.4273^{18}	
1628	Butyl nonanoate	Butyl pelargonate	$C_{13}H_{26}O_2$	50623-57-9	214.344		-38	123^{20}	0.8520^{25}	1.4262^{25}	
1629	Butyl octanoate		$C_{12}H_{24}O_2$	589-75-3	200.318	liq	-42.9	240.5	0.8628^{20}	1.4232^{25}	vs ace, eth, EtOH
1630	2-Butyl-1-octanol		$C_{12}H_{26}O$	3913-02-8	186.333			246.5; 132^{15}	0.891^{20}		
1631	Butyl oleate	Butyl *cis*-9-octadecenoate	$C_{22}H_{42}O_2$	142-77-8	338.567	ye cry	-26.4	227^{15}	0.8704^{15}	1.4480^{25}	vs EtOH
1632	*tert*-Butyl 3-oxobutanoate		$C_8H_{14}O_3$	1694-31-1	158.195			71.5^{11}	0.9756^{20}	1.4180^{20}	
1633	Butyl 4-oxopentanoate	Butyl levulinate	$C_9H_{16}O_3$	2052-15-5	172.221			237.5	0.9735^{20}	1.4290^{20}	sl chl
1634	Butyl palmitate	Butyl hexadecanoate	$C_{20}H_{40}O_2$	111-06-8	312.531	cry (dil al)	16.9			1.4312^{50}	i H_2O; s EtOH, eth
1635	Butyl pentanoate		$C_9H_{18}O_2$	591-68-4	158.238	liq	-92.8	185.8	0.8710^{15}	1.4128^{20}	sl H_2O; s EtOH, eth
1636	*sec*-Butyl pentanoate		$C_9H_{18}O_2$	116836-32-9	158.238			174.5	0.8605^{20}	1.4070^{20}	vs bz, eth, py, EtOH
1637	4-(1-Butylpentyl)pyridine		$C_{14}H_{23}N$	2961-47-9	205.340			$265; 181^{50}$	0.8878^{25}	1.4846^{25}	
1638	*tert*-Butyl peroxybenzoate	Benzoyl *tert*-butyl peroxide	$C_{11}H_{14}O_3$	614-45-9	194.227			$75^{0.2}$	1.021^{25}	1.4990^{20}	
1639	2-Butylphenol		$C_{10}H_{14}O$	3180-09-4	150.217	liq	-20	235	0.975^{20}	1.5180^{25}	i H_2O; s EtOH, eth, alk
1640	2-*sec*-Butylphenol		$C_{10}H_{14}O$	89-72-5	150.217		16	$228; 116^{21}$	0.9804^{25}	1.5200^{25}	
1641	2-*tert*-Butylphenol		$C_{10}H_{14}O$	88-18-6	150.217	liq	-6.8	223	0.9783^{20}	1.5160^{20}	s EtOH, ctc, alk; vs eth
1642	3-Butylphenol		$C_{10}H_{14}O$	4074-43-5	150.217			248	0.974^{20}		vs eth, EtOH
1643	3-*tert*-Butylphenol		$C_{10}H_{14}O$	585-34-2	150.217	nd (peth)	42.3	240			s EtOH, alk; vs eth
1644	4-Butylphenol		$C_{10}H_{14}O$	1638-22-8	150.217		22	248	0.976^{22}	1.5165^{25}	i H_2O; s EtOH, eth, alk; sl ctc
1645	4-*sec*-Butylphenol	4-(1-Methylpropyl)phenol	$C_{10}H_{14}O$	99-71-8	150.217		61.5	241	0.986^{20}	1.5182^{21}	i H_2O; s EtOH, alk; vs eth
1646	4-*tert*-Butylphenol		$C_{10}H_{14}O$	98-54-4	150.217	nd (lig)	98	237	0.908^{80}	1.4787^{114}	s H_2O, EtOH, eth, chl, alk
1647	4-*tert*-Butylphenol, phosphate (3:1)		$C_{30}H_{39}O_4P$	78-33-1	494.602						i EtOH; sl eth, bz
1648	[(4-*tert*-Butylphenoxy)methyl] oxirane		$C_{13}H_{18}O_2$	3101-60-8	206.281			167^{14}, $145^{0.5}$	1.036^{25}	1.5145^{20}	
1649	*N*-Butyl-*N*-phenylacetamide		$C_{12}H_{17}NO$	91-49-6	191.269		24.5	281	0.9912^{20}	1.5146^{20}	sl chl
1650	1-(4-*tert*-Butylphenyl)ethanone		$C_{12}H_{16}O$	943-27-1	176.254		17.7	263; 137^{20}	0.9635^{20}	1.518^{15}	
1651	Butyl phenyl ether	Butoxybenzene	$C_{10}H_{14}O$	1126-79-0	150.217	liq	-19.4	210	0.9351^{20}	1.4969^{20}	s eth, ace
1652	*N*-Butylpiperidine		$C_9H_{19}N$	4945-48-6	141.254			176	0.8245^{20}	1.4467^{20}	
1653	Butylpropanedioic acid	Butylmalonic acid	$C_7H_{12}O_4$	534-59-8	160.168	pr (w)	104.5				vs H_2O; s EtOH, eth
1654	Butyl propanoate	Butyl propionate	$C_7H_{14}O_2$	590-01-2	130.185	liq	-89	146.8	0.8754^{20}	1.4014^{20}	sl H_2O, ctc; msc EtOH, eth
1655	*sec*-Butyl propanoate		$C_7H_{14}O_2$	591-34-4	130.185			133	0.8657^{20}	1.3952^{20}	s EtOH, eth
1656	*N*-*tert*-Butyl-2-propenamide	*N*-*tert*-Butylacrylamide	$C_7H_{13}NO$	107-58-4	127.184	cry (bz)	128				sl H_2O; i peth



Butyl methyl ether



sec-Butyl methyl ether


2-*tert*-Butyl-4-methylphenol



2-*tert*-Butyl-5-methylphenol



2-*tert*-Butyl-6-methylphenol



4-*tert*-Butyl-2-methylphenol



Butyl methyl sulfide



tert-Butyl methyl sulfide



4-Butylmorpholine



1-Butylnaphthalene



2-Butylnaphthalene



Butyl nitrate



Butyl nitrite



tert-Butyl nitrite



sec-Butyl nitrite



4-(Butylnitrosoamino)-1-butanol



5-Butylnonane



Butyl nonanoate



Butyl octanoate



2-Butyl-1-octanol



Butyl oleate



tert-Butyl 3-oxobutanoate



Butyl 4-oxopentanoate



Butyl palmitate



Butyl pentanoate



sec-Butyl pentanoate



4-(1-Butylpentyl)pyridine



tert-Butyl peroxybenzoate



2-Butylphenol



2-*sec*-Butylphenol



2-*tert*-Butylphenol



3-Butylphenol



3-*tert*-Butylphenol



4-Butylphenol



4-*sec*-Butylphenol



4-*tert*-Butylphenol



4-*tert*-Butylphenol, phosphate (3:1)



[(4-*tert*-Butylphenoxy)methyl]oxirane



N-Butyl-*N*-phenylacetamide



1-(4-*tert*-Butylphenyl)ethanone



Butyl phenyl ether


N-Butylpiperidine



Butylpropanedioic acid



Butyl propanoate



sec-Butyl propanoate



N-*tert*-Butyl-2-propenamide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1657	Butyl propyl ether		$C_7H_{16}O$	3073-92-5	116.201			118.1	0.7772^{0}		i H_2O; vs EtOH, eth
1658	4-*tert*-Butylpyridine		$C_9H_{13}N$	3978-81-2	135.206	liq	-41	196.5	0.915^{25}	1.4958^{20}	s ctc, CS_2
1659	5-Butyl-2-pyridinecarboxylic acid	Fusaric acid	$C_{10}H_{13}NO_2$	536-69-6	179.216		97				
1660	Butyl stearate		$C_{22}H_{44}O_2$	123-95-5	340.583		27	343	0.854^{25}	1.4328^{50}	i H_2O; s EtOH; vs ace
1661	Butyl thiocyanate	1-Thiocyanobutane	C_5H_9NS	628-83-1	115.197			186	0.9563^{15}	1.4360^{20}	i H_2O; s EtOH, eth
1662	2-Butylthiophene		$C_8H_{12}S$	1455-20-5	140.246			181.5	0.9537^{20}	1.5090^{20}	
1663	Butyl thiophene-2-carboxylate	Butyl 2-thiophenecarboxylate	$C_9H_{12}O_2S$	56053-84-0	184.255			$58^{0.15}$			
1664	Butyl 4-toluenesulfonate		$C_{11}H_{16}O_3S$	778-28-9	228.308			165^{6}	1.1319^{20}	1.5050^{20}	i H_2O; s eth; sl ctc
1665	Butyl trichloroacetate		$C_6H_9Cl_3O_2$	3657-07-6	219.493			204	1.2778^{20}	1.4525^{25}	s ctc
1666	Butyl (2,4,5-trichlorophenoxy) acetate	2,4,5-T Butyl ester	$C_{12}H_{13}Cl_3O_3$	93-79-8	311.588		28.5	337			
1667	Butyltrichlorosilane	Trichlorobutylsilane	$C_4H_9Cl_3Si$	7521-80-4	191.559			148.5	1.1606^{20}	1.4363^{20}	s eth, bz, tol, AcOEt
1668	Butyl trifluoroacetate		$C_6H_9F_3O_2$	367-64-6	170.129			102	1.0268^{22}	1.353^{22}	s chl
1669	Butylurea		$C_5H_{12}N_2O$	592-31-4	116.161	tab (w), nd (bz)	97.0				vs H_2O, EtOH; sl chl
1670	*sec*-Butylurea	(1-Methylpropyl)urea	$C_5H_{12}N_2O$	689-11-2	116.161	pr (w)	169				
1671	*tert*-Butylurea		$C_5H_{12}N_2O$	1118-12-3	116.161		176 dec				s H_2O; vs EtOH; sl bz
1672	1-*tert*-Butyl-4-vinylbenzene	*p*-*tert*-Butylstyrene	$C_{12}H_{16}$	1746-23-2	160.255	liq	-36.9	99^{14}	0.89^{20}		
1673	Butyl vinyl ether	1-(Ethenyloxy)butane	$C_6H_{12}O$	111-34-2	100.158	liq	-92	94	0.7888^{20}	1.4026^{20}	i H_2O; vs EtOH, ace; msc eth; s bz
1674	*tert*-Butyl vinyl ether	2-(Ethenyloxy)-2-methylpropane	$C_6H_{12}O$	926-02-3	100.158	liq	-112	75	0.7691^{20}	1.3922^{20}	
1675	1-Butyne	Ethylacetylene	C_4H_6	107-00-6	54.091	col gas	-125.7	8.08	0.6783^{0}	1.3962^{20}	i H_2O; s EtOH, eth
1676	2-Butyne	Dimethylacetylene	C_4H_6	503-17-3	54.091	vol liq or gas	-32.2	26.9	0.6910^{20}	1.3921^{20}	i H_2O; s EtOH, eth, ctc
1677	2-Butynediamide	Cellocidin	$C_4H_4N_2O_2$	543-21-5	112.087	cry (dil MeOH)	217 dec				sl H_2O, chl, EtOH, eth, gl HOAc
1678	2-Butynedinitrile		C_4N_2	1071-98-3	76.056		20.5	76.5	0.9708^{25}	1.4647^{25}	
1679	2-Butynedioic acid		$C_4H_2O_4$	142-45-0	114.057		183 dec				vs H_2O, EtOH, eth
1680	2-Butyne-1,4-diol	Bis(hydroxymethyl)acetylene	$C_4H_6O_2$	110-65-6	86.090	pl (bz, AcOEt)	50	238		1.4804^{20}	vs H_2O, EtOH, ace; sl eth; i bz, peth
1681	2-Butyne-1,4-diol diacetate	1,4-Diacetoxy-2-butyne	$C_8H_{10}O_4$	1573-17-7	170.163			122^{10}		1.4611^{20}	s ctc
1682	2-Butynoic acid		$C_4H_4O_2$	590-93-2	84.074	pl (eth, peth)	78	203	0.9641^{20}		vs H_2O, eth, EtOH, chl
1683	2-Butyn-1-ol		C_4H_6O	764-01-2	70.090	liq	-1.1	148	0.9370^{20}	1.4530^{20}	vs eth, EtOH
1684	3-Butyn-1-ol		C_4H_6O	927-74-2	70.090	liq	-63.6	129	0.9257^{20}	1.4409^{20}	vs H_2O, EtOH
1685	3-Butyn-2-ol		C_4H_6O	2028-63-9	70.090	liq	-1.5	106.5	0.8618^{20}	1.4207^{20}	vs H_2O, eth, EtOH
1686	3-Butyn-2-one	Ethynyl methyl ketone	C_4H_4O	1423-60-5	68.074			84	0.8793^{20}	1.4070^{20}	
1687	3-Butynylbenzene		$C_{10}H_{10}$	16520-62-0	130.186			190	0.9258^{20}	1.5208^{20}	
1688	γ-Butyrolactone	Oxolan-2-one	$C_4H_6O_2$	96-48-0	86.090	liq	-43.61	204	1.1296^{20}	1.4341^{20}	vs ace, bz, eth, EtOH
1689	Cacotheline		$C_{21}H_{21}N_3O_7$	561-20-6	427.408	ye cry	>300				sl H_2O
1690	γ-Cadinene		$C_{15}H_{24}$	39029-41-9	204.352			126^{12}	0.9182^{15}	1.3166^{20}	
1691	Cadmium bis(diethyldithiocarbamate)		$C_{10}H_{20}CdN_2S_4$	14239-68-0	408.950	wh cry	255				
1692	Caffeine		$C_8H_{10}N_4O_2$	58-08-2	194.191	wh nd (w+1) , hex pr (sub)	238	sub 90	1.23^{19}		sl H_2O, EtOH; i eth, ctc; s chl, py
1693	Calactin	19-Oxogomphoside	$C_{29}H_{40}O_9$	20304-47-6	532.623	small pr (ace)	271				
1694	Calcium ascorbate		$C_{12}H_{14}CaO_{12}$	5743-27-1	390.310	tricl cry (w)					s H_2O; i MeOH, EtOH
1695	Calcium citrate		$C_{12}H_{10}Ca_3O_{14}$	7693-13-2	498.433	cry (w)	≈100 dec (hyd)				sl H_2O; i EtOH
1696	Calcium cyanamide	Calcium carbimide	$CCaN_2$	156-62-7	80.102	col hex cry	≈1340	sub	2.29		dec H_2O
1697	Calcium cyclamate		$C_{12}H_{24}CaN_2O_6S_2$	139-06-0	396.535	cry					vs H_2O
1698	Calcium gluconate		$C_{12}H_{22}CaO_{14}$	299-28-5	430.373	cry					i EtOH, os
1699	Calcium iodobehenate	Iododocosanoic acid, calcium salt	$C_{44}H_{84}CaI_2O_4$	1319-91-1	971.023	wh-ye pow					i H_2O, EtOH, eth; s chl
1700	Calcium lactate		$C_6H_{10}CaO_6$	814-80-2	218.217	wh pow (w)					s H_2O; i EtOH
1701	Calcium 2,4-pentanedioate	Calcium acetylacetonate	$C_{10}H_{14}CaO_4$	19372-44-2	238.294	col cry (MeOH)	dec				



Butyl propyl ether



4-*tert*-Butylpyridine



5-Butyl-2-pyridinecarboxylic acid



Butyl stearate



Butyl thiocyanate



2-Butylthiophene



Butyl thiophene-2-carboxylate



Butyl 4-toluenesulfonate



Butyl trichloroacetate



Butyl (2,4,5-trichlorophenoxy)acetate



Butyltrichlorosilane


Butyl trifluoroacetate



Butylurea


sec-Butylurea


tert-Butylurea



1-*tert*-Butyl-4-vinylbenzene


Butyl vinyl ether



tert-Butyl vinyl ether



1-Butyne


2-Butyne



2-Butynediamide


2-Butynedinitrile



2-Butynedioic acid


2-Butyne-1,4-diol


2-Butyne-1,4-diol diacetate



2-Butynoic acid


2-Butyn-1-ol



3-Butyn-1-ol



3-Butyn-2-ol



3-Butyn-2-one



3-Butynylbenzene



γ-Butyrolactone



Cacotheline



γ-Cadinene



Cadmium bis(diethyldithiocarbamate)



Caffeine



Calactin



Calcium ascorbate



Calcium citrate



Calcium cyanamide


Calcium cyclamate



Calcium gluconate



Calcium iodobehenate



Calcium lactate



Calcium 2,4-pentanedioate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1702	Calcium thioglycollate		$C_4H_6CaO_4S_2$	814-71-1	222.297	pr (w)	220 dec				s H_2O, chl; sl EtOH; i eth, bz
1703	Calotoxin	4'β-Hydroxy-19-oxogomphoside	$C_{29}H_{40}O_{10}$	20304-49-8	548.622	cry (EtOH)	268				
1704	Calotropin		$C_{29}H_{40}O_9$	1986-70-5	532.623	pl (EtOH)	221				s H_2O, EtOH; i eth
1705	Calusterone		$C_{28}H_{48}O$	17021-26-0	400.680	cry (ace)	157.5				
1706	Camphene, (+)	2,2-Dimethyl-3-methylenebicyclo[2.2.1] heptane, (1R)-	$C_{10}H_{16}$	5794-03-6	136.234	nd	52	161	0.8950^{50}	1.4570^{25}	vs eth
1707	Camphene, (-)	2,2-Dimethyl-3-methylenebicyclo[2.2.1] heptane, (1*S*)-	$C_{10}H_{16}$	5794-04-7	136.234		52	158	0.8446^{50}	1.4564^{54}	vs eth
1708	*d*-Camphocarboxylic acid		$C_{11}H_{16}O_3$	18530-30-8	196.243	pr (eth, 50% al)	127.5				vs bz, eth, EtOH
1709	Camphor, (±)	1,7,7-Trimethylbicyclo[2.2.1] heptan-2-one, (±)	$C_{10}H_{16}O$	21368-68-3	152.233	wh rhom cry (EtOH)	178.3	sub			i H_2O; vs EtOH, eth; s ace, bz, ctc
1710	Camphor, (+)	1,7,7-Trimethylbicyclo[2.2.1] heptan-2-one, (1*R*)	$C_{10}H_{16}O$	464-49-3	152.233	pl	178.8	207.4	0.990^{25}	1.5462	i H_2O; vs EtOH, eth; s ace, bz
1711	Camphor, (-)	1,7,7-Trimethylbicyclo[2.2.1] heptan-2-one, (1*S*)	$C_{10}H_{16}O$	464-48-2	152.233		178.6		0.9853^{18}		i H_2O; vs EtOH, eth, HOAc; s ace, bz
1712	Camphoric acid, (±)	1,2,2-Trimethyl-1,3-cyclopentanedicarboxylic acid, (1*RS*, 3*SR*)	$C_{10}H_{16}O_4$	5394-83-2	200.232	pr, lf	202		1.186		sl H_2O; s chl, eth, EtOH
1713	*d*-Camphorsulfonic acid		$C_{10}H_{16}O_4S$	3144-16-9	232.297	pr (HOAc)	195 dec				vs H_2O; i eth; sl HOAc
1714	Canadine, (±)	*DL*-Tetrahydroberberine	$C_{20}H_{21}NO_4$	29074-38-2	339.386	mcl nd (al)	134				vs EtOH, chl
1715	Cannabidiol		$C_{21}H_{30}O_2$	13956-29-1	314.462	rods (peth)	67	188^{2}	1.040^{40}	1.5404^{20}	i H_2O; s EtOH, eth, bz, chl
1716	Cannabinol	6,6,9-Trimethyl-3-pentyl-6*H*-dibenzo[b,d]pyran-1-ol	$C_{21}H_{26}O_2$	521-35-7	310.430	pl, lf (peth)	77	$185^{0.05}$			i H_2O; s EtOH, eth, ace, bz, peth, alk
1717	Canrenone		$C_{22}H_{28}O_3$	976-71-6	340.455	cry (AcOEt)	150				
1718	Cantharidin		$C_{10}H_{12}O_4$	56-25-7	196.200	orth pl	218	sub 84			i H_2O; sl EtOH, eth, ace, bz; s HOAc
1719	Caprolactam	6-Hexanelactam	$C_6H_{11}NO$	105-60-2	113.157	lf (lig)	69.3	270			vs H_2O, bz, EtOH, chl
1720	Capsaicin		$C_{18}H_{27}NO_3$	404-86-4	305.412	mcl pl or sc (peth)	65	$215^{0.01}$			i H_2O; vs EtOH; s eth, bz, peth; sl con HCl
1721	Capsanthin	3,3'-Dihydroxy-β,κ-caroten-6'-one, (3*R*,3'*S*,5'*R*)	$C_{40}H_{56}O_3$	465-42-9	584.871		176				
1722	Captafol		$C_{10}H_9Cl_4NO_2S$	2425-06-1	349.061	cry	161				
1723	Captan		$C_9H_8Cl_3NO_2S$	133-06-2	300.590	cry (CCl_4)	172.5		1.74^{25}		vs chl
1724	Captopril	1-(3-Mercapto-2-methyl-1-oxypropyl)proline	$C_9H_{15}NO_3S$	62571-86-2	217.285	cry (AcOEt)	105				s H_2O, EtOH, chl
1725	Carbachol		$C_6H_{15}ClN_2O_2$	51-83-2	182.648		210 dec				vs H_2O, MeOH; sl EtOH; i eth, chl
1726	Carbamic chloride	Carbamyl chloride	CH_2ClNO	463-72-9	79.486			dec 62			
1727	Carbamodithioic acid		CH_3NS_2	594-07-0	93.172						vs EtOH, eth
1728	Carbamoyl dihydrogen phosphate		CH_4NO_5P	590-55-6	141.021	unstab in soln					
1729	Carbaryl		$C_{12}H_{11}NO_2$	63-25-2	201.221		145		1.228^{25}		vs ace, DMF
1730	Carbazole	Dibenzopyrolle	$C_{12}H_9N$	86-74-8	167.206	pl or lf	246.3	354.69			i H_2O; sl EtOH, eth, bz, chl; s ace
1731	9*H*-Carbazole-9-acetic acid		$C_{14}H_{11}NO_2$	524-80-1	225.243	lf (AcOEt)	215				vs eth, EtOH, chl, HOAc
1732	Carbendazim	Carbamic acid, 1*H*-benzimidazol-2-yl-, methyl ester	$C_9H_9N_3O_2$	10605-21-7	191.186		300 dec		1.45		
1733	Carbetapentane	Pentoxyverine	$C_{20}H_{31}NO_3$	77-23-6	333.465			$165^{0.01}$			
1734	*N*-Carbethoxyphthalimide	*N*-(Ethoxycarbonyl)phthalimide	$C_{11}H_9NO_4$	22509-74-6	219.194		91				
1735	Carbic anhydride		$C_9H_8O_3$	129-64-6	164.158	orth cry (peth)	164.5		1.417^{25}		vs ace, bz, EtOH, chl
1736	Carbimazole		$C_7H_{10}N_2O_2S$	22232-54-8	186.231	cry, pow	123.5				vs ace, chl
1737	Carbobenzoxyhydrazine	Benzyl carbazate	$C_8H_{10}N_2O_2$	5331-43-1	166.177		69.5				
1738	Carbofuran		$C_{12}H_{15}NO_3$	1563-66-2	221.252		151		1.18		
1739	Carboimidic difluoride		CHF_2N	2712-98-3	65.023	gas	-90	-13 dec			
1740	γ-Carboline	5*H*-Pyrido[4,3-b]indole	$C_{11}H_8N_2$	244-69-9	168.195	nd	225		1.352		sl H_2O, bz; vs MeOH; s EtOH



Calcium thioglycollate



Calotoxin


Calotropin



Calusterone



Camphene, (+)



Camphene, (-)



d-Camphocarboxylic acid



Camphor, (±)



Camphor, (+)



Camphor, (-)



Camphoric acid, (±)



d-Camphorsulfonic acid


Canadine, (±)



Cannabidiol



Cannabinol



Canrenone



Cantharidin



Caprolactam



Capsaicin



Capsanthin



Captafol



Captan



Captopril



Carbachol



Carbamic chloride



Carbamodithioic acid



Carbamoyl dihydrogen phosphate



Carbaryl



Carbazole



9*H*-Carbazole-9-acetic acid



Carbendazim



Carbetapentane


N-Carbethoxyphthalimide



Carbic anhydride


Carbimazole


Carbobenzoxyhydrazine


Carbofuran


Carboimidic difluoride


γ-Carboline


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1741	Carbon dioxide	Carbonic anhydride	CO_2	124-38-9	44.010	col gas	-56.56 tp	-78.5 sp	0.720^{25} (p>1 atm)		sl H_2O
1742	Carbon diselenide	Carbon selenide	CSe_2	506-80-9	169.93	ye liq	-43.7	125.5	2.6823^{20}	1.8454^{20}	
1743	Carbon disulfide	Carbon bisulfide	CS_2	75-15-0	76.141	col liq	-112.1	46	1.2632^{20}	1.6319^{20}	s H_2O, chl; msc EtOH, eth
1744	Carbonic acid		CH_2O_3	463-79-6	62.025						Aq. soln. of CO_2
1745	Carbonic dihydrazide	Carbohydrazide	CH_6N_4O	497-18-7	90.085	nd (dil al)	154		1.616^{20}		vs H_2O, EtOH
1746	Carbon monoxide	Carbon oxide	CO	630-08-0	28.010	col gas	-205.02	-191.5	0.7909^{-19}		sl H_2O; s bz, HOAc
1747	Carbonochloridic acid, 4-nitrophenyl ester		$C_7H_4ClNO_4$	7693-46-1	201.565		80	160^{19}			
1748	Carbonochloridic acid, (4-nitrophenyl)methyl ester		$C_8H_6ClNO_4$	4457-32-3	215.592		32.8				
1749	Carbonochloridic acid, 2,2,2-trichloroethyl ester		$C_3H_2Cl_4O_2$	17341-93-4	211.859			63^{11}			
1750	Carbonothioic dichloride	Thiophosgene	CCl_2S	463-71-8	114.982	red liq		73	1.508^{15}	1.5442^{20}	dec H_2O, EtOH; s eth
1751	Carbonothioic dihydrazide	1,3-Diamino-2-thiourea	CH_6N_4S	2231-57-4	106.151	nd, pl (w) nd, pl (w)	170 dec				vs H_2O
1752	Carbon oxyselenide	Carbonyl selenide	COSe	1603-84-5	106.97	col gas; unstab	-122	-21.5			dec H_2O
1753	Carbon oxysulfide	Carbonyl sulfide	COS	463-58-1	60.075	col gas	-138.8	-50	1.028^{17}	1.24^{-87}	sl H_2O; s EtOH; vs KOH
1754	Carbon suboxide	1,2-Propadiene-1,3-dione	C_3O_2	504-64-3	68.031	col gas	-107	6.8	1.114^{0}	1.4538^{0}	s eth, bz, CS_2
1755	Carbonyl bromide	Bromophosgene	CBr_2O	593-95-3	187.818			64.5	2.52^{15}		
1756	Carbonyl chloride	Phosgene	CCl_2O	75-44-5	98.916	col gas	-127.78	8	1.3719^{25} (p>1 atm		s bz, ctc, chl, tol, HOAc
1757	Carbonyl chloride fluoride	Carbonic chloride fluoride	CClFO	353-49-1	82.461	col gas	-148	-47.2			reac H_2O
1758	Carbonyl dicyanide		C_3N_2O	1115-12-4	80.044	liq	-36	65.5	1.124^{20}	1.3919^{20}	s eth, ace, ctc, chl
1759	*N,N'*-Carbonyldiimidazole		$C_7H_6N_4O$	530-62-1	162.149	cry (bz)	119				
1760	Carbonyl fluoride		CF_2O	353-50-4	66.007	col gas	-111.2	-84.5	1.139^{25}		
1761	Carbophenothion		$C_{11}H_{16}ClO_2PS_3$	786-19-6	342.866			$82^{0.01}$	1.271^{20}		
1762	Carbosulfan		$C_{20}H_{32}N_2O_3S$	55285-14-8	380.544			126	1.056^{20}		
1763	Carboxin		$C_{12}H_{13}NO_2S$	5234-68-4	235.302		94				
1764	2-Carboxybenzeneacetic acid		$C_9H_8O_4$	89-51-0	180.158		184.5		1.4100^{20}		s H_2O, EtOH; sl eth; i bz, chl
1765	*N*-(*D*-1-Carboxyethyl)-*L*-arginine	Octopine	$C_9H_{18}N_4O_4$	34522-32-2	246.264	nd (w)	281				
1766	*L*-γ-Carboxyglutamic acid		$C_6H_9NO_6$	53861-57-7	191.138	cry	167				
1767	*S*-(Carboxymethyl)-*L*-cysteine	Carbocysteine	$C_5H_9NO_4S$	638-23-3	179.195	nd	206				
1768	2-Carboxyphenyl 2-hydroxybenzoate	Salsalate	$C_{14}H_{10}O_5$	552-94-3	258.226		147				sl ace
1769	3-Carene, (+)		$C_{10}H_{16}$	498-15-7	136.234			171; 123^{200}	0.8549^{30}	1.469^{3}	vs ace, bz, eth
1770	Carisoprodol		$C_{12}H_{24}N_2O_4$	78-44-4	260.330	cry	92				s os
1771	Carminic acid		$C_{22}H_{20}O_{13}$	1260-17-9	492.386	red mcl pr (aq, MeOH)	136 dec				s H_2O, EtOH; sl eth; i bz, chl
1772	Carnitine	4-Amino-3-hydroxybutanoic acid trimethylbetaine	$C_7H_{15}NO_3$	541-15-1	161.199	cry (al-ace), hyg	197 dec				vs H_2O, EtOH
1773	Carnosine	*N*-β-Alanyl-*L*-histidine	$C_9H_{14}N_4O_3$	305-84-0	226.232		260				vs H_2O
1774	α-Carotene		$C_{40}H_{56}$	7488-99-5	536.873	red pl or pr (peth, bz-MeOH)	187.5		1.00^{20}		vs bz, eth, chl
1775	β-Carotene		$C_{40}H_{56}$	7235-40-7	536.873	red br hex pr (bz-MeOH)	183		1.00^{20}		i H_2O; sl EtOH, chl; s eth, ace, bz
1776	β,ψ-Carotene	γ-Carotene	$C_{40}H_{56}$	472-93-5	536.873	red pr (bz-MeOH), viol pr (eth)	153				i H_2O, EtOH; sl eth, peth; s bz, chl
1777	ψ,ψ-Carotene	*trans*-Lycopene	$C_{40}H_{56}$	502-65-8	536.873	red pr or nd (peth)	175				sl EtOH, peth; s eth; vs bz, chl, CS_2
1778	β,β-Carotene-3,3'-diol, (3*R*,3'*R*)	Zeaxanthin	$C_{40}H_{56}O_2$	144-68-3	568.872	ye pr (MeOH) orth (chl-eth)	215.5	$227^{0.06}$			i H_2O; sl EtOH; s eth, ace, bz, py, chl
1779	β,ε-Carotene-3,3'-diol, (3*R*,3'*R*,6'*R*)	Xanthophyll	$C_{40}H_{56}O_2$	127-40-2	568.872	ye or viol pr (eth-MeOH)	196				vs bz, eth, EtOH, peth
1780	β,β-Caroten-3-ol, (3*R*)	Cryptoxanthin	$C_{40}H_{56}O$	472-70-8	552.872	garnet red pr (bz-MeOH)	160				vs bz, chl
1781	β,ψ-Caroten-3-ol, (3*R*)	Rubixanthin	$C_{40}H_{56}O$	3763-55-1	552.872	dk red nd (bz-MeOH) oran-red (bz-peth)	160				sl EtOH, peth; s bz, chl


Carbon dioxide


Carbon diselenide


Carbon disulfide



Carbonic acid


Carbonic dihydrazide


Carbon monoxide



Carbonochloridic acid, 4-nitrophenyl ester



Carbonochloridic acid, (4-nitrophenyl)methyl ester



Carbonochloridic acid, 2,2,2-trichloroethyl ester


Carbonothioic dichloride


Carbonothioic dihydrazide



Carbon oxyselenide



Carbon oxysulfide



Carbon suboxide


Carbonyl bromide



Carbonyl chloride



Carbonyl chloride fluoride



Carbonyl dicyanide



N,N'-Carbonyldiimidazole



Carbonyl fluoride



Carbophenothion



Carbosulfan



Carboxin



2-Carboxybenzeneacetic acid



N-(*D*-1-Carboxyethyl)-*L*-arginine



L-γ-Carboxyglutamic acid



S-(Carboxymethyl)-*L*-cysteine



2-Carboxyphenyl 2-hydroxybenzoate



3-Carene, (+)



Carisoprodol



Carminic acid



Carnitine



Carnosine



α-Carotene



β-Carotene



β,ψ-Carotene


ψ,ψ-Carotene



β,β-Carotene-3,3'-diol, (3*R*,3'*R*)



β,ε-Carotene-3,3'-diol, (3*R*,3'*R*,6'*R*)



β,β-Caroten-3-ol, (3*R*)



β,ψ-Caroten-3-ol, (3*R*)


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1782	ψ,ψ-Caroten-16-ol	Lycoxanthin	$C_{40}H_{56}O$	19891-74-8	552.872	red pl (bz-MeOH)	168				i H_2O; sl EtOH; s bz, CS_2
1783	Caroverine		$C_{22}H_{27}N_3O_2$	23465-76-1	365.468	cry	69	$202^{0.01}$			sl i-PrOH
1784	Carpaine		$C_{28}H_{50}N_2O_4$	3463-92-1	478.708	mcl pr (al, ace)	121				vs ace, bz, eth, EtOH
1785	Cartap hydrochloride		$C_7H_{16}ClN_3O_2S_2$	22042-59-7	273.804	cry	180				s H_2O; sl EtOH, MeOH
1786	Carvenone, (*S*)		$C_{10}H_{16}O$	10395-45-6	152.233			233	0.9289^{20}	1.4805^{20}	i H_2O; s ace
1787	(*R*)-Carvone	*p*-Mentha-1,8-dien-6-one, (*R*)	$C_{10}H_{14}O$	6485-40-1	150.217		25.2	231	0.9593^{20}	1.4988^{20}	sl H_2O; vs EtOH; s eth, ctc, chl
1788	(*S*)-Carvone	*p*-Mentha-1,8-dien-6-one, (*S*)	$C_{10}H_{14}O$	2244-16-8	150.217		<15	231	0.965^{20}	1.4989^{20}	sl H_2O; vs EtOH; s eth, chl
1789	Caryophyllene		$C_{15}H_{24}$	87-44-5	204.352			$122^{13.5}$	0.9075^{20}	1.4986^{20}	vs bz
1790	Casimiroin	6-Methoxy-9-methyl-1,3-dioxolo[4,5-h]quinolin-8(9*H*)-one	$C_{12}H_{11}NO_4$	477-89-4	233.220						sl chl
1791	Cassaine		$C_{24}H_{39}NO_4$	468-76-8	405.572	fl (eth)	142.5				s EtOH, ace, chl, eth, bz, MeOH
1792	Caulophylline		$C_{12}H_{16}N_2O$	486-86-2	204.267	cry (w+2), nd (al, bz)	137				vs H_2O, ace, bz, EtOH
1793	α-Cedrene		$C_{15}H_{24}$	469-61-4	204.352	oil		$262.5; 125^{12}$			
1794	Cedrol		$C_{15}H_{26}O$	77-53-2	222.366		86		0.9479^{90}	1.4824^{90}	
1795	Cefazolin		$C_{14}H_{14}N_8O_4S_3$	25953-19-9	454.508	nd (ace aq)	200 dec				s DMF, py; sl MeOH; i chl, bz, eth
1796	β-Cellobiose		$C_{12}H_{22}O_{11}$	13360-52-6	342.296	cry (dil al)	225 dec				s H_2O; i EtOH, eth, ace, bz
1797	Cellotriose		$C_{18}H_{32}O_{16}$	33404-34-1	504.437		208				
1798	Cephalexin		$C_{16}H_{17}N_3O_4S$	15686-71-2	347.389	cry					
1799	Cephaloglycin	Kafocin	$C_{18}H_{19}N_3O_6S$	3577-01-3	405.425	cry (w)	≈220 dec				
1800	Cephaloridine		$C_{19}H_{17}N_3O_4S_2$	50-59-9	415.486	cry					s H_2O
1801	Cephalothin		$C_{16}H_{16}N_2O_6S_2$	153-61-7	396.437		160				
1802	Cephapirin		$C_{17}H_{17}N_3O_6S_2$	21593-23-7	423.463	cry (ace aq)	155				
1803	Cepharanthine		$C_{37}H_{38}N_2O_6$	481-49-2	606.707	ye amor pow	150				
1804	Cephradine		$C_{16}H_{19}N_3O_4S$	38821-53-3	349.405	col cry (w)	141 dec				
1805	Cerulenin	2,3-Epoxy-4-oxo-7,10-dodecadienamide, (2*R*,3*S*)-	$C_{12}H_{17}NO_3$	17397-89-6	223.268	wh nd	94				sl H_2O; s bz, EtOH, ace; i peth
1806	Cevadine		$C_{32}H_{49}NO_9$	62-59-9	591.733	flat nd (eth)	213 dec				
1807	Chavicine		$C_{17}H_{19}NO_3$	495-91-0	285.338						vs eth, EtOH, peth
1808	Cheirolin		$C_5H_9NO_2S_2$	505-34-0	179.261	cry (eth)	47.5	200^{3}			vs EtOH, chl
1809	Chelerythrine		$C_{21}H_{19}NO_5$	34316-15-9	365.380	cry (chl-MeOH)		207			vs chl
1810	Chelidonine	Stylophorine	$C_{20}H_{19}NO_5$	476-32-4	353.369	mcl pr (al)	135.5	$220^{0.002}$			i H_2O; s EtOH, eth, chl
1811	Chinomethionat		$C_{10}H_6N_2OS_2$	2439-01-2	234.297		170				
1812	Chloral hydrate		$C_2H_3Cl_3O_2$	302-17-0	165.403		57	dec 96	1.9081^{20}		vs H_2O, bz, eth, EtOH
1813	Chlorambucil		$C_{14}H_{19}Cl_2NO_2$	305-03-3	304.213		65				
1814	Chloramine B	*N*-Chlorobenzenesulfonamide sodium	$C_6H_5ClNNaO_2S$	127-52-6	213.618	pr (w)	190				sl EtOH; i chl, eth
1815	Chloramine T	*N*-Chloro-4-methylbenzenesulfonamide sodium	$C_7H_7ClNNaO_2S$	127-65-1	227.645	pr (hyd)	180 (hyd)				s H_2O; i bz, chl, eth
1816	Chloramphenicol		$C_{11}H_{12}Cl_2N_2O_5$	56-75-7	323.129	pa ye pl or nd (w)	150.5	sub			vs ace, EtOH, chl
1817	Chloramphenicol palmitate		$C_{27}H_{42}Cl_2N_2O_6$	530-43-8	561.537	cry (bz)	90				vs bz, eth, EtOH
1818	Chloranilic acid	2,5-Dichloro-3,6-dihydroxy-2,5-cyclohexadiene-1,4-dione	$C_6H_2Cl_2O_4$	87-88-7	208.984	red lf (w+2)	283.5				s H_2O
1819	Chlorbenside	1-Chloro-4[[(4-chlorophenyl) methyl]thio]benzene	$C_{13}H_{10}Cl_2S$	103-17-3	269.189		75		1.4210^{20}		
1820	Chlorbicyclen		$C_9H_6Cl_8$	2550-75-6	397.768	pow	105	174^{2}			
1821	Chlorbromuron	N'-(4-Bromo-3-chlorophenyl)-N-methoxy-N-methylurea	$C_9H_{10}BrClN_2O_2$	13360-45-7	293.544		96		1.69^{20}		
1822	Chlorbufam	1-Methyl-2-propynyl(3-chlorophenyl)carbamate	$C_{11}H_{10}ClNO_2$	1967-16-4	223.656	cry	45.5				sl H_2O; s MeOH, EtOH, ace
1823	Chlorcyclizine		$C_{18}H_{21}ClN_2$	82-93-9	300.826	oil		$140^{0.12}$			
1824	Chlordane		$C_{10}H_6Cl_8$	57-74-9	409.779		106	175^{1}	1.60^{25}		
1825	Chlordantoin		$C_{11}H_{17}Cl_3N_2O_2S$	5588-20-5	347.689						s CS_2
1826	Chlordene		$C_{10}H_6Cl_6$	3734-48-3	338.873	cry (EtOH)	155				
1827	Chlordimeform		$C_{10}H_{13}ClN_2$	6164-98-3	196.676		35	$156^{0.4}$	1.105^{25}	1.5885^{25}	vs bz, eth, EtOH



ψ,ψ-Caroten-16-ol



Caroverine



Carpaine



Cartap hydrochloride



Carvenone, (*S*)



(*R*)-Carvone



(*S*)-Carvone



Caryophyllene



Casimiroin



Cassaine



Caulophylline



α-Cedrene



Cedrol



Cefazolin



β-Cellobiose



Cellotriose



Cephalexin



Cephaloglycin



Cephaloridine



Cephalothin



Cephapirin



Cepharanthine



Cephradine



Cerulenin



Cevadine



Chavicine



Cheirolin



Chelerythrine



Chelidonine



Chinomethionat



Chloral hydrate



Chlorambucil



Chloramine B



Chloramine T



Chloramphenicol



Chloramphenicol palmitate



Chloranilic acid



Chlorbenside



Chlorbicyclen



Chlorbromuron



Chlorbufam


Chlorcyclizine



Chlordane



Chlordantoin



Chlordene



Chlordimeform


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1828	Chlorendic acid	1,4,5,6,7,7-Hexachloro-5-norbornene-2,3-dicarboxylic acid	$C_9H_4Cl_6O_4$	115-28-6	388.844	cry (w)	232				
1829	Chlorendic anhydride		$C_9H_2Cl_6O_3$	115-27-5	370.828		235				
1830	Chlorfenvinphos		$C_{12}H_{14}Cl_3O_4P$	470-90-6	359.569			$170^{0.05}$			
1831	Chlorflurecol	9*H*-Fluorene-9-carboxylic acid, 2-chloro-9-hydroxy-	$C_{14}H_9ClO_3$	2464-37-1	260.672				1.496^{20}		
1832	Chloridazon	3(2*H*)-Pyridazinone, 5-amino-4-chloro-2-phenyl-	$C_{10}H_8ClN_3O$	1698-60-8	221.643		205				
1833	Chlorimuron-ethyl		$C_{15}H_{15}ClN_4O_6S$	90982-32-4	414.821		186				
1834	Chlormephos	Chloromethyl *O,O*-diethyl dithiophosphate	$C_5H_{12}ClO_2PS_2$	24934-91-6	234.705	oil		$83^{0.1}$		1.5244	sl H_2O; misc os
1835	Chlormequat chloride		$C_5H_{13}Cl_2N$	999-81-5	158.069		239 dec				
1836	Chlormezanone		$C_{11}H_{12}ClNO_3S$	80-77-3	273.736	cry	117				sl EtOH
1837	Chlornaphazine		$C_{14}H_{15}Cl_2N$	494-03-1	268.182	pl (peth)	55	210^{5}			vs ace, bz, eth, EtOH
1838	Chloroacetaldehyde		C_2H_3ClO	107-20-0	78.497	liq	-16.3	85.5	1.19		s eth
1839	2-Chloroacetamide		C_2H_4ClNO	79-07-2	93.512		121	225			s H_2O; vs EtOH; sl eth
1840	Chloroacetic acid		$C_2H_3ClO_2$	79-11-8	94.497	mcl pl	63	189.3	1.4043^{40}	1.4351^{55}	vs H_2O; s EtOH, eth, bz, chl; sl ctc
1841	Chloroacetic anhydride		$C_4H_4Cl_2O_3$	541-88-8	170.979	pr (bz)	46	203	1.5497^{20}		
1842	4-Chloroacetoacetanilide	*N*-Acetoacetyl-4-chloroaniline	$C_{10}H_{10}ClNO_2$	101-92-8	211.645		132				
1843	Chloroacetone		C_3H_5ClO	78-95-5	92.524	liq	-44.5	119	1.15^{20}		s H_2O, EtOH, eth, chl
1844	Chloroacetonitrile	Chloromethyl cyanide	C_2H_2ClN	107-14-2	75.497			126.5	1.1930^{20}	1.4202^{25}	vs eth, EtOH
1845	α-Chloroacetophenone	ω-Chloroacetophenone	C_8H_7ClO	532-27-4	154.594	pl(dil al), rhom, lf (peth)	56.5	247	1.324^{15}		i H_2O; vs EtOH, eth, bz; s ace, peth
1846	4-(2-Chloroacetyl)acetanilide		$C_{10}H_{10}ClNO_2$	140-49-8	211.645		218				
1847	Chloroacetyl chloride		$C_2H_2Cl_2O$	79-04-9	112.942	liq	-22	106	1.4202^{20}	1.4530^{20}	msc eth; s ace, ctc
1848	Chloroacetylene		C_2HCl	593-63-5	60.482	col gas	-126	-30			sl EtOH
1849	9-Chloroacridine		$C_{13}H_8ClN$	1207-69-8	213.663	nd (al)	121	sub			vs H_2O, EtOH
1850	2-Chloroaniline		C_6H_6ClN	95-51-2	127.572	liq	-1.9	208.8		1.5895^{20}	i H_2O; msc EtOH; s eth, ace
1851	3-Chloroaniline		C_6H_6ClN	108-42-9	127.572	liq	-10.28	230.5	1.2161^{20}	1.5941^{20}	i H_2O; msc EtOH, eth, ace, bz; s chl
1852	4-Chloroaniline		C_6H_6ClN	106-47-8	127.572	orth pr	70.5	232	1.429^{19}	1.5546^{87}	s H_2O, EtOH, eth, chl
1853	2-Chloroaniline hydrochloride		$C_6H_7Cl_2N$	137-04-2	164.033	pl (w, aq al)	235		1.505^{18}		vs H_2O
1854	3-Chloroaniline hydrochloride		$C_6H_7Cl_2N$	141-85-5	164.033	pl	222				vs H_2O, EtOH
1855	2-Chloroanisole	1-Chloro-2-methoxybenzene	C_7H_7ClO	766-51-8	142.583	liq	-26.8	198.5	1.1911^{20}	1.5480^{20}	i H_2O; s EtOH, eth; sl chl
1856	3-Chloroanisole	1-Chloro-3-methoxybenzene	C_7H_7ClO	2845-89-8	142.583			193.5	1.1759^{12}	1.5365^{20}	i H_2O; s EtOH, eth
1857	4-Chloroanisole	1-Chloro-4-methoxybenzene	C_7H_7ClO	623-12-1	142.583		<-18	197.5	1.201^{20}	1.5390^{20}	i H_2O; vs EtOH, eth, chl; s ctc
1858	1-Chloroanthracene		$C_{14}H_9Cl$	4985-70-0	212.674	lf (HOAc)	83.5		1.1707^{100}	1.6959^{100}	i H_2O; s EtOH, eth, bz, ctc
1859	1-Chloro-9,10-anthracenedione		$C_{14}H_7ClO_2$	82-44-0	242.658	ye nd (to or al)	163	sub			i H_2O; sl EtOH, ctc; msc eth; s bz
1860	2-Chloro-9,10-anthracenedione		$C_{14}H_7ClO_2$	131-09-9	242.658	pa ye nd (al, HOAc)	211	sub			i H_2O, eth; sl EtOH, bz; vs tol; s $PhNO_2$
1861	2-Chlorobenzaldehyde		C_7H_5ClO	89-98-5	140.567	nd	12.4	211.9	1.2483^{20}	1.5662^{20}	sl H_2O; s EtOH, eth, ace, bz, ctc
1862	3-Chlorobenzaldehyde		C_7H_5ClO	587-04-2	140.567	pr	17.5	213.5	1.2410^{20}	1.5650^{20}	sl H_2O, chl; s EtOH, eth, ace, bz
1863	4-Chlorobenzaldehyde		C_7H_5ClO	104-88-1	140.567	pl	47.5	213.5	1.196^{61}	1.555^{61}	s H_2O, ace, chl; vs EtOH, eth, bz
1864	2-Chlorobenzamide		C_7H_6ClNO	609-66-5	155.582	orth nd (w)	141.8				s H_2O, EtOH, eth
1865	Chlorobenzene	Phenyl chloride	C_6H_5Cl	108-90-7	112.557	liq	-45.31	131.72	1.1058^{20}	1.5241^{20}	i H_2O; msc EtOH, eth; vs bz, ctc
1866	2-Chlorobenzeneacetic acid		$C_8H_7ClO_2$	2444-36-2	170.594	nd (w)	96				sl H_2O; vs EtOH
1867	3-Chlorobenzeneacetic acid		$C_8H_7ClO_2$	1878-65-5	170.594	pl (dil al), nd (lig)	77.5				sl H_2O, bz, ctc, EtOH; msc eth



Chlorendic acid



Chlorendic anhydride



Chlorfenvinphos



Chlorflurecol



Chloridazon


Chlorimuron-ethyl



Chlormephos



Chlormequat chloride



Chlormezanone



Chlornaphazine


Chloroacetaldehyde



2-Chloroacetamide



Chloroacetic acid



Chloroacetic anhydride



4-Chloroacetoacetanilide


Chloroacetone



Chloroacetonitrile


α-Chloroacetophenone



4-(2-Chloroacetyl)acetanilide



Chloroacetyl chloride



Chloroacetylene



9-Chloroacridine



2-Chloroaniline



3-Chloroaniline



4-Chloroaniline



2-Chloroaniline hydrochloride



3-Chloroaniline hydrochloride



2-Chloroanisole



3-Chloroanisole



4-Chloroanisole



1-Chloroanthracene



1-Chloro-9,10-anthracenedione


2-Chloro-9,10-anthracenedione



2-Chlorobenzaldehyde



3-Chlorobenzaldehyde


4-Chlorobenzaldehyde



2-Chlorobenzamide



Chlorobenzene



2-Chlorobenzeneacetic acid



3-Chlorobenzeneacetic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1868	4-Chlorobenzeneacetic acid		$C_8H_7ClO_2$	1878-66-6	170.594	nd (w)	105.5				s H_2O, EtOH, eth, bz
1869	2-Chlorobenzeneacetonitrile		C_8H_6ClN	2856-63-5	151.594		24	251	1.1737^{18}		
1870	3-Chlorobenzeneacetonitrile		C_8H_6ClN	1529-41-5	151.594		11.5	261; 135^{10}	1.1806^{30}	1.5437^{20}	
1871	4-Chlorobenzeneacetonitrile		C_8H_6ClN	140-53-4	151.594		29	265.0	1.1778^{30}		s ctc
1872	α-Chlorobenzeneacetyl chloride		$C_8H_6Cl_2O$	2912-62-1	189.039			120^{23}, 110^{14}	1.196^{25}	1.5440^{20}	
1873	3-Chlorobenzenecarboperoxoic acid		$C_7H_5ClO_3$	937-14-4	172.566		92 dec				
1874	4-Chloro-1,2-benzenediamine	4-Chloro-*o*-phenylenediamine	$C_6H_7ClN_2$	95-83-0	142.586	pl (bz-lig) lf (w)	76				sl H_2O; vs EtOH, eth; s bz, lig
1875	4-Chloro-1,3-benzenediamine		$C_6H_7ClN_2$	5131-60-2	142.586	pl or nd	91				vs EtOH
1876	2-Chloro-1,4-benzenediamine	2-Chloro-*p*-phenylenediamine	$C_6H_7ClN_2$	615-66-7	142.586	nd	64				
1877	3-Chloro-1,2-benzenediol		$C_6H_5ClO_2$	4018-65-9	144.556	cry (lig)	48.5	110^{11}			vs lig
1878	4-Chloro-1,2-benzenediol		$C_6H_5ClO_2$	2138-22-9	144.556	lf (bz-peth)	90.5	139$^{10.5}$			vs H_2O, ace, eth, EtOH
1879	4-Chloro-1,3-benzenediol		$C_6H_5ClO_2$	95-88-5	144.556			257			vs H_2O, EtOH, eth, ace, bz, CS_2
1880	2-Chloro-1,4-benzenediol		$C_6H_5ClO_2$	615-67-8	144.556	red lf (chl), nd (bz)	108	263			vs H_2O, chl; s EtOH, eth; vs bz
1881	2-Chlorobenzenemethanamine		C_7H_8ClN	89-97-4	141.599			72^{2}		1.5594^{25}	
1882	3-Chlorobenzenemethanamine		C_7H_8ClN	4152-90-3	141.599			89^{2}		1.5570^{25}	
1883	4-Chlorobenzenemethanamine		C_7H_8ClN	104-86-9	141.599			109^{13}		1.5566^{25}	
1884	4-Chlorobenzenemethanethiol		C_7H_7ClS	6258-66-8	158.649		19.5	113^{17}	1.202^{25}	1.5893^{20}	
1885	2-Chlorobenzenemethanol		C_7H_7ClO	17849-38-6	142.583	lf or nd (dil al)	73	230			sl H_2O; vs EtOH, eth, lig
1886	4-Chlorobenzenemethanol		C_7H_7ClO	873-76-7	142.583	nd (w), pl (bz or bz-lig)	75	235			vs bz, eth, EtOH
1887	2-Chlorobenzenesulfonamide		$C_6H_6ClNO_2S$	6961-82-6	191.636	lf (al)	188				vs EtOH
1888	4-Chlorobenzenesulfonamide		$C_6H_6ClNO_2S$	98-64-6	191.636	pr or pl (eth)	146				vs bz, eth
1889	4-Chlorobenzenesulfonic acid	*p*-Chlorobenzenesulfonic acid	$C_6H_5ClO_3S$	98-66-8	192.620	nd (w+1)	67	147^{25}			s H_2O, EtOH; i eth, bz
1890	4-Chlorobenzenesulfonyl chloride		$C_6H_4Cl_2O_2S$	98-60-2	211.066		51	141^{15}			vs eth, bz
1891	2-Chlorobenzenethiol		C_6H_5ClS	6320-03-2	144.622			205.5	1.2752^{10}		sl H_2O, EtOH
1892	3-Chlorobenzenethiol		C_6H_5ClS	2037-31-2	144.622			206	1.2637^{13}		i H_2O; s EtOH, eth, chl, peth
1893	4-Chlorobenzenethiol		C_6H_5ClS	106-54-7	144.622		61	206	1.1911^{20}	1.5480^{20}	i H_2O; vs EtOH, eth, bz; sl chl
1894	Chlorobenzilate		$C_{16}H_{14}Cl_2O_3$	510-15-6	325.186		37	157$^{0.07}$	1.2816^{20}		
1895	2-Chloro-1,3,2-benzodioxaphosphole		$C_6H_4ClO_2P$	1641-40-3	174.522		30	80^{20}	1.4650^{20}	1.5712^{20}	
1896	2-Chlorobenzoic acid		$C_7H_5ClO_2$	118-91-2	156.567	mcl pr (w)	140.2	sub	1.544^{20}		s H_2O, bz; vs EtOH, eth, ace; sl CS_2
1897	3-Chlorobenzoic acid		$C_7H_5ClO_2$	535-80-8	156.567	pr (w)	158	sub	1.496^{25}		sl H_2O, bz, ctc, CS_2; s EtOH, eth
1898	4-Chlorobenzoic acid		$C_7H_5ClO_2$	74-11-3	156.567	tcl pr (al-eth)	243				i H_2O, bz, ctc; vs EtOH; sl eth, ace
1899	2-Chlorobenzonitrile		C_7H_4ClN	873-32-5	137.567	nd	46.3	232			sl H_2O; s EtOH, eth, chl
1900	3-Chlorobenzonitrile		C_7H_4ClN	766-84-7	137.567		41	100^{15}			i H_2O; s EtOH, eth
1901	4-Chlorobenzonitrile		C_7H_4ClN	623-03-0	137.567	nd (al)	95	223; 95^{5}	1.1133^{17}		sl H_2O, lig; s EtOH, eth, bz, chl
1902	2-Chlorobenzophenone	2-Chlorophenyl phenyl ketone	$C_{13}H_9ClO$	5162-03-8	216.662	pl (chl-lig)	54	330			
1903	4-Chloro-2-benzothiazolamine		$C_7H_5ClN_2S$	19952-47-7	184.646		204				
1904	6-Chloro-2-benzothiazolamine		$C_7H_5ClN_2S$	95-24-9	184.646		200				
1905	2-Chlorobenzothiazole		C_7H_4ClNS	615-20-3	169.632		24	248	1.3715^{10}	1.6338^{10}	vs ace, eth, EtOH
1906	5-Chloro-1*H*-benzotriazole		$C_6H_4ClN_3$	94-97-3	153.569		158				
1907	6-Chloro-2*H*-3,1-benzoxazine-2,4(1*H*)-dione	5-Chloroisatoic anhydride	$C_8H_4ClNO_3$	4743-17-3	197.576		280 dec				
1908	5-Chloro-2-benzoxazolamine	Zoxazolamine	$C_7H_5ClN_2O$	61-80-3	168.580	pl (bz)	184.5				vs EtOH
1909	2-Chlorobenzoxazole		C_7H_4ClNO	615-18-9	153.566		7	201.5	1.3453^{18}	1.5678^{20}	
1910	5-Chloro-2(3*H*)-benzoxazolone	Chlorzoxazone	$C_7H_4ClNO_2$	95-25-0	169.566	cry (ace)	191.5				vs EtOH, MeOH
1911	2-Chlorobenzoyl chloride		$C_7H_4Cl_2O$	609-65-4	175.012	liq	-4	238		1.5726^{16}	s ctc
1912	3-Chlorobenzoyl chloride		$C_7H_4Cl_2O$	618-46-2	175.012			225		1.5677^{20}	
1913	4-Chlorobenzoyl chloride		$C_7H_4Cl_2O$	122-01-0	175.012		16	222	1.3770^{20}	1.5756^{20}	sl chl
1914	1-Chloro-4-benzylbenzene		$C_{13}H_{11}Cl$	831-81-2	202.679		7.5	299; 147^{8}	1.1247^{20}		vs ace



4-Chlorobenzeneacetic acid



2-Chlorobenzeneacetonitrile



3-Chlorobenzeneacetonitrile



4-Chlorobenzeneacetonitrile



α-Chlorobenzeneacetyl chloride



3-Chlorobenzenecarboperoxoic acid



4-Chloro-1,2-benzenediamine



4-Chloro-1,3-benzenediamine



2-Chloro-1,4-benzenediamine



3-Chloro-1,2-benzenediol



4-Chloro-1,2-benzenediol



4-Chloro-1,3-benzenediol



2-Chloro-1,4-benzenediol



2-Chlorobenzenemethanamine



3-Chlorobenzenemethanamine



4-Chlorobenzenemethanamine



4-Chlorobenzenemethanethiol



2-Chlorobenzenemethanol


4-Chlorobenzenemethanol



2-Chlorobenzenesulfonamide



4-Chlorobenzenesulfonamide



4-Chlorobenzenesulfonic acid



4-Chlorobenzenesulfonyl chloride



2-Chlorobenzenethiol



3-Chlorobenzenethiol



4-Chlorobenzenethiol



Chlorobenzilate



2-Chloro-1,3,2-benzodioxaphosphole



2-Chlorobenzoic acid



3-Chlorobenzoic acid



4-Chlorobenzoic acid



2-Chlorobenzonitrile



3-Chlorobenzonitrile



4-Chlorobenzonitrile



2-Chlorobenzophenone



4-Chloro-2-benzothiazolamine



6-Chloro-2-benzothiazolamine



2-Chlorobenzothiazole



5-Chloro-1*H*-benzotriazole



6-Chloro-2*H*-3,1-benzoxazine-2,4(1*H*)-dione



5-Chloro-2-benzoxazolamine



2-Chlorobenzoxazole


5-Chloro-2(3*H*)-benzoxazolone



2-Chlorobenzoyl chloride


3-Chlorobenzoyl chloride



4-Chlorobenzoyl chloride


1-Chloro-4-benzylbenzene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1915	*o*-Chlorobenzylidene malononitrile		$C_{10}H_5ClN_2$	2698-41-1	188.613	wh cry	96	312			sl H_2O; s bz, diox, EtOAc, ace
1916	2-Chlorobiphenyl		$C_{12}H_9Cl$	2051-60-7	188.652	mcl (dil al)	34	274	1.1499^{32}		i H_2O; vs eth, EtOH, lig
1917	3-Chlorobiphenyl		$C_{12}H_9Cl$	2051-61-8	188.652		16	284.5	1.1579^{25}	1.6181^{25}	vs ace, eth, EtOH
1918	4-Chlorobiphenyl		$C_{12}H_9Cl$	2051-62-9	188.652	lf (lig or al)	78.8	292.9; 146^{10}			i H_2O; s EtOH, eth, lig
1919	4'-Chloro-[1,1'-biphenyl]-4-amine	4-Amino-4'-chlorodiphenyl	$C_{12}H_{10}ClN$	135-68-2	203.667	cry (peth)	134				vs ace, bz, eth
1920	3-Chloro-[1,1'-biphenyl]-2-ol	2-Phenyl-6-chlorophenol	$C_{12}H_9ClO$	85-97-2	204.651		6	dec 317	1.24^{25}	1.6237^{30}	i H_2O; s EtOH, eth, ace, bz
1921	4-Chloro-1,2-butadiene		C_4H_5Cl	25790-55-0	88.536			88	0.9891^{20}	1.4775^{20}	vs ace, bz, eth
1922	1-Chloro-1,3-butadiene		C_4H_5Cl	627-22-5	88.536			68	0.9606^{20}	1.4712^{20}	vs eth, EtOH, chl
1923	2-Chloro-1,3-butadiene	Chloroprene	C_4H_5Cl	126-99-8	88.536	liq	-130	59.4	0.956^{20}	1.4583^{20}	sl H_2O; msc eth, ace, bz
1924	4-Chlorobutanal		C_4H_7ClO	6139-84-0	106.551			51^{13}	1.106^{8}	1.4466^{8}	vs ace, eth, EtOH
1925	1-Chlorobutane	Butyl chloride	C_4H_9Cl	109-69-3	92.567	liq	-123.1	78.4	0.8857^{20}	1.4023^{20}	i H_2O; msc EtOH, eth; sl ctc
1926	2-Chlorobutane	(±)-*sec*-Butyl chloride	C_4H_9Cl	53178-20-4	92.567	liq	-131.3	68.2	0.8732^{20}	1.3971^{20}	vs bz, eth, EtOH, chl
1927	4-Chlorobutanenitrile		C_4H_6ClN	628-20-6	103.551			192	1.0934^{15}	1.4413^{20}	i H_2O; s EtOH, eth; sl ctc
1928	2-Chlorobutanoic acid		$C_4H_7ClO_2$	4170-24-5	122.551			189^{627}, 101^{15}	1.1796^{20}	1.441^{20}	sl H_2O; vs EtOH, eth
1929	3-Chlorobutanoic acid		$C_4H_7ClO_2$	625-68-3	122.551	cry (eth)	16	116^{22}	1.1898^{20}	1.4221^{20}	s EtOH; vs eth; sl ctc
1930	4-Chlorobutanoic acid		$C_4H_7ClO_2$	627-00-9	122.551		16	196^{22}, $68^{0.2}$	1.2236^{20}	1.4642^{20}	vs EtOH
1931	4-Chloro-1-butanol		C_4H_9ClO	928-51-8	108.566			84^{16}	1.0883^{20}	1.4518^{20}	vs eth, EtOH
1932	1-Chloro-2-butanol	α-Butylene chlorohydrin	C_4H_9ClO	1873-25-2	108.566			141	1.068^{25}	1.4400^{20}	s EtOH, eth
1933	3-Chloro-2-butanone		C_4H_7ClO	4091-39-8	106.551			115	1.0554^{25}	1.4219^{20}	
1934	4-Chlorobutanoyl chloride		$C_4H_6Cl_2O$	4635-59-0	140.996			173.5	1.2581^{20}	1.4616^{20}	s eth
1935	2-Chloro-1-butene		C_4H_7Cl	2211-70-3	90.552			58.5	0.9107^{15}	1.4165^{21}	vs ace, bz, eth, EtOH
1936	3-Chloro-1-butene		C_4H_7Cl	563-52-0	90.552			64.5	0.8978^{20}	1.4149^{20}	vs eth, ace; s chl
1937	4-Chloro-1-butene		C_4H_7Cl	927-73-1	90.552			75	0.9211^{20}	1.4233^{20}	vs ace, eth, chl
1938	*cis*-1-Chloro-2-butene		C_4H_7Cl	4628-21-1	90.552			84.1	0.9426^{20}	1.4390^{20}	i H_2O; s EtOH, ace, chl
1939	*trans*-1-Chloro-2-butene		C_4H_7Cl	4894-61-5	90.552			85	0.9295^{20}	1.4350^{20}	i H_2O; s ace, chl
1940	*cis*-2-Chloro-2-butene		C_4H_7Cl	2211-69-0	90.552	liq	-117.3	70.6	0.9239^{20}	1.4240^{20}	i H_2O; msc EtOH; s ace, chl
1941	*trans*-2-Chloro-2-butene		C_4H_7Cl	2211-68-9	90.552	liq	-105.8	62.8	0.9138^{20}	1.4190^{20}	i H_2O; msc EtOH; s ace, chl
1942	1-Chloro-4-*tert*-butylbenzene		$C_{10}H_{13}Cl$	3972-56-3	168.663			213	1.0075^{18}	1.5123^{20}	
1943	Chloro-(*tert*-butyl)dimethylsilane		$C_6H_{15}ClSi$	18162-48-6	150.722		89.5	125			
1944	Chloro(*tert*-butyl)diphenylsilane		$C_{16}H_{19}ClSi$	58479-61-1	274.861			$120^{0.06}$	1.07^{20}	1.5675^{20}	
1945	2-Chloro-4-*tert*-butylphenol		$C_{10}H_{13}ClO$	98-28-2	184.662			114^{8}			
1946	3-Chloro-1-butyne		C_4H_5Cl	21020-24-6	88.536			68.5	1.4218^{25}	1.4218^{25}	
1947	2-Chloro-*N*-(2-chloroethyl) ethanamine, hydrochloride		$C_4H_{10}Cl_3N$	821-48-7	178.488		215.0				
1948	2-Chloro-*N*-(2-chloroethyl)-*N*-ethylethanamine	HN1	$C_6H_{13}Cl_2N$	538-07-8	170.080	col liq	-34	66^{12}	1.0861^{23}	1.4653^{25}	i H_2O
1949	2-Chloro-*N*-(2-chloroethyl)-*N*-methylethanamine	Mechlorethamine	$C_5H_{11}Cl_2N$	51-75-2	156.053		-60	87^{18}, 64^{5}			sl H_2O; msc ctc, DMF
1950	1-Chloro-2-(chloromethyl) benzene	2-Chlorobenzyl chloride	$C_7H_6Cl_2$	611-19-8	161.029	liq	-17	217	1.2699^{0}	1.5530^{20}	i H_2O; sl EtOH, ctc; vs eth, bz
1951	1-Chloro-3-(chloromethyl) benzene	3-Chlorobenzyl chloride	$C_7H_6Cl_2$	620-20-2	161.029			216; 110^{25}	1.2695^{15}	1.5554^{20}	vs EtOH
1952	1-Chloro-4-(chloromethyl) benzene	4-Chlorobenzyl chloride	$C_7H_6Cl_2$	104-83-6	161.029	nd (dil al)	31	223			sl ctc
1953	Chloro(chloromethyl) dimethylsilane		$C_3H_8Cl_2Si$	1719-57-9	143.088			115.5	1.0865^{20}	1.4360^{20}	
1954	3-Chloro-2-(chloromethyl)-1-propene		$C_4H_6Cl_2$	1871-57-4	124.997	liq	-14	138	1.1782^{20}	1.4753	vs EtOH, chl
1955	1-Chloro-4-[(chloromethyl)thio] benzene		$C_7H_6Cl_2S$	7205-90-5	193.094		21.5	128^{12}	1.346^{25}	1.6055^{20}	
1956	2-Chloro-1-(4-chlorophenyl) ethanone		$C_8H_6Cl_2O$	937-20-2	189.039	nd (al)	101.5	270			s EtOH, bz, MeOH




o-Chlorobenzylidene malononitrile




2-Chlorobiphenyl




3-Chlorobiphenyl




4-Chlorobiphenyl




4'-Chloro-[1,1'-biphenyl]-4-amine



3-Chloro-[1,1'-biphenyl]-2-ol




4-Chloro-1,2-butadiene




1-Chloro-1,3-butadiene



2-Chloro-1,3-butadiene




4-Chlorobutanal




1-Chlorobutane




2-Chlorobutane




4-Chlorobutanenitrile




2-Chlorobutanoic acid




3-Chlorobutanoic acid



4-Chlorobutanoic acid




4-Chloro-1-butanol



1-Chloro-2-butanol



3-Chloro-2-butanone




4-Chlorobutanoyl chloride




2-Chloro-1-butene




3-Chloro-1-butene



4-Chloro-1-butene



cis-1-Chloro-2-butene




trans-1-Chloro-2-butene




cis-2-Chloro-2-butene




trans-2-Chloro-2-butene




1-Chloro-4-*tert*-butylbenzene



Chloro-(*tert*-butyl)dimethylsilane




Chloro(*tert*-butyl)diphenylsilane




2-Chloro-4-*tert*-butylphenol




3-Chloro-1-butyne




2-Chloro-*N*-(2-chloroethyl)ethanamine, hydrochloride




2-Chloro-*N*-(2-chloroethyl)-*N*-ethylethanamine




2-Chloro-*N*-(2-chloroethyl)-*N*-methylethanamine




1-Chloro-2-(chloromethyl)benzene




1-Chloro-3-(chloromethyl)benzene




1-Chloro-4-(chloromethyl)benzene




Chloro(chloromethyl)dimethylsilane



3-Chloro-2-(chloromethyl)-1-propene





1-Chloro-4-[(chloromethyl)thio]benzene





2-Chloro-1-(4-chlorophenyl)ethanone

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1957	3-Chlorocholest-5-ene, (3β)		$C_{27}H_{45}Cl$	910-31-6	405.099	nd (al, ace)	96				i H_2O; s EtOH, ace, bz, chl; vs CS_2
1958	*trans-o*-Chlorocinnamic acid		$C_9H_7ClO_2$	939-58-2	182.604		212				vs eth, EtOH
1959	*trans-m*-Chlorocinnamic acid		$C_9H_7ClO_2$	14473-90-6	182.604		165				s EtOH, eth
1960	*trans-p*-Chlorocinnamic acid		$C_9H_7ClO_2$	940-62-5	182.604		249.5				vs ace, eth, EtOH
1961	Chlorocyclohexane	Cyclohexyl chloride	$C_6H_{11}Cl$	542-18-7	118.604	liq	-43.81	142	1.000^{20}	1.4626^{20}	i H_2O; msc EtOH, eth, ace, bz; vs chl
1962	2-Chlorocyclohexanone		C_6H_9ClO	822-87-7	132.587		23	82^{15}	1.160^{20}	1.4825^{20}	s eth, bz, diox; sl ctc
1963	1-Chlorocyclohexene		C_6H_9Cl	930-66-5	116.588			142.5	1.0361^{19}	1.4797^{20}	s eth, ace, ctc, chl
1964	Chlorocyclopentane	Cyclopentyl chloride	C_5H_9Cl	930-28-9	104.578			114	1.0051^{20}	1.4510^{20}	i H_2O; s eth, ace, bz, ctc
1965	2-Chlorocyclopentanone		C_5H_7ClO	694-28-0	118.562			87^{19}, 73^{12}	1.185^{25}	1.4750^{20}	
1966	3-Chlorocyclopentene		C_5H_7Cl	96-40-2	102.563			40^{40}, 27^{30}	1.0388^{25}	1.4708^{26}	vs eth, EtOH, chl
1967	4-Chloro-2-cyclopentylphenol	Dowicide 9	$C_{11}H_{13}ClO$	13347-42-7	196.673			183^{18}			
1968	1-Chlorodecane		$C_{10}H_{21}Cl$	1002-69-3	176.727	liq	-31.3	225.9	0.8696^{20}	1.4380^{20}	i H_2O; vs eth, chl; s ctc
1969	10-Chloro-1-decanol		$C_{10}H_{21}ClO$	51309-10-5	192.726		12.5	187^{15}	0.9630^{25}	1.4578^{20}	vs eth, EtOH
1970	2-Chloro-*N,N*-diallylacetamide	Allidochlor	$C_8H_{12}ClNO$	93-71-0	173.640	liq		116^{1}, $92^{0.7}$	1.088^{25}	1.4932^{25}	sl H_2O; s EtOH
1971	Chlorodiazepoxide		$C_{16}H_{14}ClN_3O$	58-25-3	299.754		236.2				
1972	Chlorodibromomethane		$CHBr_2Cl$	124-48-1	208.280	liq	-20	120	2.451^{20}	1.5482^{20}	i H_2O; s EtOH, eth, ace, bz
1973	Chloro(dichloromethyl) dimethylsilane	(Dichloromethyl) dimethylchlorosilane	$C_3H_7Cl_3Si$	18171-59-0	177.533	liq	-48	149	1.2369^{20}	1.461^{20}	
1974	5-Chloro-*N*-(3,4-dichlorophenyl)-2-hydroxybenzamide	3',4',5-Trichlorosalicylanilide	$C_{13}H_8Cl_3NO_2$	642-84-2	316.568		247				
1975	2-Chloro-1,1-diethoxyethane		$C_6H_{13}ClO_2$	621-62-5	152.619			157.4	1.0180^{20}	1.4170^{20}	sl H_2O, ctc; msc EtOH, eth
1976	3-Chloro-1,1-diethoxypropane		$C_7H_{15}ClO_2$	35573-93-4	166.646			84^{25}	0.9951^{19}	1.4268^{20}	vs ace, bz
1977	2-Chloro-*N,N*-diethylacetamide		$C_6H_{12}ClNO$	2315-36-8	149.618			192^{25}			
1978	2-Chloro-*N,N*-diethylethanamine, hydrochloride		$C_6H_{15}Cl_2N$	869-24-9	172.096		200				sl H_2O
1979	Chlorodifluoroacetic acid		$C_2HClF_2O_2$	76-04-0	130.478	hyg	25	122		1.3559^{20}	s chl
1980	1-Chloro-1,1-difluoroethane	Refrigerant 142b	$C_2H_3ClF_2$	75-68-3	100.495	col gas	-130.8	-9.1	1.107^{25}		i H_2O; s bz
1981	1-Chloro-2,2-difluoroethane		$C_2H_3ClF_2$	338-65-8	100.495			35.1			
1982	1-Chloro-2,2-difluoroethene	1-Chloro-2,2-difluoroethylene	C_2HClF_2	359-10-4	98.479	col gas	-138.5	-18.5			
1983	Chlorodifluoromethane	Refrigerant 22	$CHClF_2$	75-45-6	86.469	col gas	-157.42	-40.7	1.4909^{-69}		sl H_2O; s eth, ace, chl
1984	7-Chloro-2,3-dihydro-1*H*-inden-4-ol	Chlorindanol	C_9H_9ClO	145-94-8	168.619	nd (peth)	92				
1985	10-Chloro-5,10-dihydrophenarsazine	Phenarsazine chloride	$C_{12}H_9AsClN$	578-94-9	277.581	ye cry	195		1.65		i H_2O; sl ctc, bz, xyl
1986	5-Chloro-2,4-dimethoxyaniline		$C_8H_{10}ClNO_2$	97-50-7	187.624		91				
1987	2-Chloro-1,1-dimethoxyethane		$C_4H_9ClO_2$	97-97-2	124.566			127.5	1.068^{20}	1.4150^{20}	sl EtOH, eth, bz, ctc
1988	*N*-(4-Chloro-2,5-dimethoxyphenyl)-3-oxobutanamide		$C_{12}H_{14}ClNO_4$	4433-79-8	271.697		107				s chl
1989	Chlorodimethylaluminum	Dimethylaluminum chloride	C_2H_6AlCl	1184-58-3	92.504	hyg liq	-21	126	0.996		reac H_2O; s hx
1990	2-Chloro-10-(3-dimethylaminopropyl) phenothiazine monohydrochloride	Aminazin hydrochloride	$C_{17}H_{20}Cl_2N_2S$	69-09-0	355.325		195 dec				s H_2O; i eth, bz; vs chl, EtOH
1991	2-Chloro-*N,N*-dimethylaniline		$C_8H_{10}ClN$	698-01-1	155.625			205	1.1067^{20}	1.5578^{20}	vs bz, EtOH
1992	3-Chloro-*N,N*-dimethylaniline		$C_8H_{10}ClN$	6848-13-1	155.625			232			sl H_2O; s EtOH, ace, bz
1993	4-Chloro-*N,N*-dimethylaniline		$C_8H_{10}ClN$	698-69-1	155.625	nd (al)	35.5	231	1.0480^{100}		s EtOH
1994	2-Chloro-1,4-dimethylbenzene		C_8H_9Cl	95-72-7	140.610		0.8	187	1.0589^{15}		i H_2O; s ace, ctc; vs bz
1995	4-Chloro-1,2-dimethylbenzene		C_8H_9Cl	615-60-1	140.610	liq	-6	194	1.0682^{15}		i H_2O; s ace, ctc; vs bz
1996	2-Chloro-*N,N*-dimethylethanamine, hydrochloride		$C_4H_{11}Cl_2N$	4584-46-7	144.043		201.0				sl H_2O
1997	(2-Chloro-1,1-dimethylethyl) benzene	Neophyl chloride	$C_{10}H_{13}Cl$	515-40-2	168.663			223; 105^{18}	1.047^{20}	1.5247^{20}	vs ace, bz, eth, EtOH
1998	4-Chloro-2,5-dimethylphenol		C_8H_9ClO	1124-06-7	156.609	silv-grn nd (lig)	74.5				sl H_2O; vs bz, EtOH, peth


3-Chlorocholest-5-ene, (3β)


trans-o-Chlorocinnamic acid


trans-m-Chlorocinnamic acid


trans-p-Chlorocinnamic acid


Chlorocyclohexane



2-Chlorocyclohexanone



1-Chlorocyclohexene



Chlorocyclopentane



2-Chlorocyclopentanone



3-Chlorocyclopentene


4-Chloro-2-cyclopentylphenol


1-Chlorodecane



10-Chloro-1-decanol



2-Chloro-*N*,*N*-diallylacetamide



Chlorodiazepoxide



Chlorodibromomethane



Chloro(dichloromethyl)dimethylsilane



5-Chloro-*N*-(3,4-dichlorophenyl)-2-hydroxybenzamide


2-Chloro-1,1-diethoxyethane



3-Chloro-1,1-diethoxypropane


2-Chloro-*N*,*N*-diethylacetamide


2-Chloro-*N*,*N*-diethylethanamine, hydrochloride



Chlorodifluoroacetic acid



1-Chloro-1,1-difluoroethane



1-Chloro-2,2-difluoroethane



1-Chloro-2,2-difluoroethene



Chlorodifluoromethane


7-Chloro-2,3-dihydro-1*H*-inden-4-ol



10-Chloro-5,10-dihydrophenarsazine



5-Chloro-2,4-dimethoxyaniline



2-Chloro-1,1-dimethoxyethane



N-(4-Chloro-2,5-dimethoxyphenyl)-3-oxobutanamide



Chlorodimethylaluminum



2-Chloro-10-(3-dimethylaminopropyl)phenothiazine monohydrochloride



2-Chloro-*N*,*N*-dimethylaniline



3-Chloro-*N*,*N*-dimethylaniline



4-Chloro-*N*,*N*-dimethylaniline


2-Chloro-1,4-dimethylbenzene



4-Chloro-1,2-dimethylbenzene



2-Chloro-*N*,*N*-dimethylethanamine, hydrochloride



(2-Chloro-1,1-dimethylethyl)benzene



4-Chloro-2,5-dimethylphenol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
1999	4-Chloro-2,6-dimethylphenol		C_8H_9ClO	1123-63-3	156.609	nd (w)	83				sl H_2O; vs bz, EtOH, HOAc
2000	4-Chloro-3,5-dimethylphenol	Chloroxylenol	C_8H_9ClO	88-04-0	156.609		115	246			sl H_2O, bz, peth; s EtOH, eth
2001	Chlorodimethylphenylsilane		$C_8H_{11}ClSi$	768-33-2	170.712			195; 82^{16}	1.032^{20}	1.5082^{20}	
2002	1-Chloro-*N,N*-dimethyl-2-propanamine, hydrochloride		$C_5H_{13}Cl_2N$	17256-39-2	158.069						s chl
2003	1-Chloro-2,2-dimethylpropane		$C_5H_{11}Cl$	753-89-9	106.594	liq	-20	84.3	0.8660^{20}	1.4044^{20}	vs bz, eth, EtOH, chl
2004	3-Chloro-2,2-dimethylpropanoic acid		$C_5H_9ClO_2$	13511-38-1	136.577		41.5	110^{10}			vs ctc
2005	Chlorodimethylsilane		C_2H_7ClSi	1066-35-9	94.616	liq	-111	34.7	0.852	1.3830^{20}	
2006	2-Chloro-4,6-dinitroaniline		$C_6H_4ClN_3O_4$	3531-19-9	217.567	ye cry (DMF aq)	157				
2007	4-Chloro-2,6-dinitroaniline		$C_6H_4ClN_3O_4$	5388-62-5	217.567	oran-ye nd (al)	147				s EtOH
2008	1-Chloro-2,4-dinitrobenzene		$C_6H_3ClN_2O_4$	97-00-7	202.552	ye orth (eth) nd (al) ye cry	53	315	1.4982^{75}	1.5857^{60}	i H_2O; sl EtOH; s eth, bz, CS_2
2009	2-Chloro-1,3-dinitrobenzene		$C_6H_3ClN_2O_4$	606-21-3	202.552	ye nd (al, HOAc)	88	315	1.6867^{16}		i H_2O; s EtOH, eth, tol; sl chl
2010	1-Chloro-2,4-dinitronaphthalene		$C_{10}H_5ClN_2O_4$	2401-85-6	252.611	ye nd (bz)	146.5				
2011	4-Chloro-2,6-dinitrophenol		$C_6H_3ClN_2O_5$	88-87-9	218.551	pa ye cry	81		1.74^{22}		vs eth, EtOH, chl
2012	2-Chloro-3,5-dinitropyridine		$C_5H_2ClN_3O_4$	2578-45-2	203.541		66.5				
2013	2-Chloro-1,3-dinitro-5-(trifluoromethyl)benzene		$C_7H_2ClF_3N_2O_4$	393-75-9	270.550		57				
2014	4-Chloro-1,3-dioxolan-2-one	Chloroethylene carbonate	$C_3H_3ClO_3$	3967-54-2	122.507	liq	110	213; 122^{18}	1.504	1.4540^{20}	
2015	2-Chloro-1,2-diphenylethanone		$C_{14}H_{11}ClO$	447-31-4	230.689	nd (al)	68.5	dec			s EtOH; sl chl; i alk
2016	Chlorodiphenylmethane		$C_{13}H_{11}Cl$	90-99-3	202.679		16	140^{3}	1.140^{25}	1.5951^{20}	s chl
2017	1-Chlorododecane	Lauryl chloride	$C_{12}H_{25}Cl$	112-52-7	204.780	liq	-9.3	263.2	0.8673^{20}	1.4434^{20}	i H_2O; vs EtOH; msc ace, ctc; s bz
2018	Chloroethane	Ethyl chloride	C_2H_5Cl	75-00-3	64.514	vol liq or gas	-138.4	12.3	0.8902^{25} (p>1 atm	1.3676^{20}	sl H_2O, chl; vs EtOH; msc eth
2019	2-Chloroethanesulfonyl chloride		$C_2H_4Cl_2O_2S$	1622-32-8	163.023			201.5	1.555^{20}	1.4920^{20}	
2020	2-Chloroethanol	Ethylene chlorohydrin	C_2H_5ClO	107-07-3	80.513	liq	-67.5	128.6	1.2019^{20}	1.4419^{20}	msc H_2O, EtOH; sl eth; s chl
2021	2-Chloroethanol, 4-methylbenzenesulfonate		$C_9H_{11}ClO_3S$	80-41-1	234.699			210^{21}			i H_2O; s ctc
2022	Chloroethene	Vinyl chloride	C_2H_3Cl	75-01-4	62.498	col gas	-153.84	-13.8	0.9106^{20}	1.3700^{20}	sl H_2O; s EtOH; vs eth
2023	1-Chloro-4-ethoxybenzene		C_8H_9ClO	622-61-7	156.609		21	213	1.1254^{20}	1.5252^{20}	s EtOH, eth, HOAc; vs bz; sl ctc
2024	(2-Chloroethoxy)benzene		C_8H_9ClO	622-86-6	156.609		28	218.5			i H_2O; vs EtOH, eth, ace, bz; sl ctc
2025	1-Chloro-1-ethoxyethane		C_4H_9ClO	7081-78-9	108.566			93.5	0.9655^{20}	1.4053^{20}	
2026	2-(2-Chloroethoxy)ethanol		$C_4H_9ClO_2$	628-89-7	124.566			180; 80^{5}	1.18^{25}	1.4529^{20}	vs H_2O; msc EtOH, eth
2027	2-Chloroethyl acetate	β-Chloroethyl acetate	$C_4H_7ClO_2$	542-58-5	122.551			145	1.178^{20}	1.4234^{20}	i H_2O; msc EtOH, eth; s ctc
2028	2-Chloroethyl acetoacetate		$C_6H_9ClO_3$	54527-68-3	164.586			198; 120^{19}	1.2055^{21}	1.4430^{20}	vs bz, eth, EtOH
2029	2-Chloroethylamine hydrochloride	2-Chloroethanamine hydrochloride	$C_2H_7Cl_2N$	870-24-6	115.990		146.3				vs H_2O, ace, EtOH
2030	(1-Chloroethyl)benzene		C_8H_9Cl	672-65-1	140.610			105^{50}			
2031	(2-Chloroethyl)benzene		C_8H_9Cl	622-24-2	140.610			197.5; 92^{20}	1.069^{25}	1.5276^{20}	i H_2O; s EtOH, eth, ace, bz, CS_2
2032	1-Chloro-2-ethylbenzene		C_8H_9Cl	89-96-3	140.610	liq	-82.7	178.4	1.0569^{20}	1.5218^{20}	i H_2O; s ace, bz, ctc, chl
2033	1-Chloro-3-ethylbenzene		C_8H_9Cl	620-16-6	140.610	liq	-55	183.8	1.0529^{20}	1.5195^{20}	vs ace, bz, eth, EtOH
2034	1-Chloro-4-ethylbenzene		C_8H_9Cl	622-98-0	140.610	liq	-62.6	184.4	1.0455^{20}	1.5175^{20}	i H_2O; msc EtOH, eth, ace, peth; s HOAc
2035	2-Chloroethyl chloroformate		$C_3H_4Cl_2O_2$	627-11-2	142.969			155	1.3847^{20}	1.4483^{20}	i H_2O; s EtOH, eth, ace, bz; sl ctc
2036	1-(2-Chloroethyl)-3-cyclohexyl-1-nitrosourea	Lomustine	$C_9H_{16}ClN_3O_2$	13010-47-4	233.695	ye pow	90				i H_2O; s EtOH
2037	*N*-(2-Chloroethyl)dibenzylamine	Dibenamine	$C_{16}H_{18}ClN$	51-50-3	259.774	oily liq		169^{3}			



4-Chloro-2,6-dimethylphenol


4-Chloro-3,5-dimethylphenol



Chlorodimethylphenylsilane



1-Chloro-*N*,*N*-dimethyl-2-propanamine, hydrochloride



1-Chloro-2,2-dimethylpropane



3-Chloro-2,2-dimethylpropanoic acid



Chlorodimethylsilane



2-Chloro-4,6-dinitroaniline



4-Chloro-2,6-dinitroaniline



1-Chloro-2,4-dinitrobenzene



2-Chloro-1,3-dinitrobenzene



1-Chloro-2,4-dinitronaphthalene



4-Chloro-2,6-dinitrophenol



2-Chloro-3,5-dinitropyridine


2-Chloro-1,3-dinitro-5-(trifluoromethyl)benzene



4-Chloro-1,3-dioxolan-2-one



2-Chloro-1,2-diphenylethanone



Chlorodiphenylmethane


1-Chlorododecane



Chloroethane



2-Chloroethanesulfonyl chloride



2-Chloroethanol



2-Chloroethanol, 4-methylbenzenesulfonate



Chloroethene



1-Chloro-4-ethoxybenzene



(2-Chloroethoxy)benzene



1-Chloro-1-ethoxyethane



2-(2-Chloroethoxy)ethanol


2-Chloroethyl acetate



2-Chloroethyl acetoacetate



2-Chloroethylamine hydrochloride



(1-Chloroethyl)benzene



(2-Chloroethyl)benzene



1-Chloro-2-ethylbenzene


1-Chloro-3-ethylbenzene



1-Chloro-4-ethylbenzene


2-Chloroethyl chloroformate



1-(2-Chloroethyl)-3-cyclohexyl-1-nitrosourea



N-(2-Chloroethyl)dibenzylamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2038	*N*-(2-Chloroethyl)dibenzylamine hydrochloride	Dibenamine hydrochloride	$C_{16}H_{19}Cl_2N$	55-43-6	296.235	cry	194				i H_2O; s EtOH, dil acid
2039	Chloroethyldimethylsilane		$C_4H_{11}ClSi$	6917-76-6	122.669			89.5	0.8675^{20}	1.4105^{20}	
2040	2-Chloroethyl ethyl ether		C_4H_9ClO	628-34-2	108.566			107.5	0.9895^{20}	1.4113^{20}	sl H_2O; msc eth; s chl
2041	2-Chloroethyl isocyanate		C_3H_4ClNO	1943-83-5	105.523			44^{17}			
2042	1-(2-Chloroethyl)-3-(4-methylcyclohexyl)-1-nitrosourea	Semustine	$C_{10}H_{18}ClN_3O_2$	13909-09-6	247.722	cry	64 dec				
2043	5-(2-Chloroethyl)-4-methylthiazole	Clomethiazole	C_6H_8ClNS	533-45-9	161.653	oil		92^{7}	1.233^{25}		
2044	*N*-(2-Chloroethyl)morpholine		$C_6H_{12}ClNO$	3240-94-6	149.618			42^{1}			
2045	4-(2-Chloroethyl)morpholine, hydrochloride		$C_6H_{13}Cl_2NO$	3647-69-6	186.079		185				
2046	1-Chloro-2-(ethylthio)ethane		C_4H_9ClS	693-07-2	124.632			157	1.0663^{25}		
2047	2-Chloroethyl vinyl ether		C_4H_7ClO	110-75-8	106.551	liq	-70	108	1.0495^{20}	1.4378^{20}	vs EtOH, eth; sl chl
2048	3-Chloro-4-fluoroaniline		C_6H_5ClFN	367-21-5	145.562		45.0	227.0			
2049	1-Chloro-2-fluorobenzene		C_6H_4ClF	348-51-6	130.547	liq	-43	137.6	1.2233^{30}	1.4918^{30}	i H_2O; s ace, bz
2050	1-Chloro-3-fluorobenzene		C_6H_4ClF	625-98-9	130.547			127.6	1.221^{25}	1.4911	
2051	1-Chloro-4-fluorobenzene		C_6H_4ClF	352-33-0	130.547	liq	-26.8	130	1.4990^{15}	1.4990^{15}	i H_2O; s EtOH, eth, bz
2052	1-Chloro-1-fluoroethane		C_2H_4ClF	1615-75-4	82.504	vol liq or gas		16.2			
2053	1-Chloro-2-fluoroethane		C_2H_4ClF	762-50-5	82.504			52.8	1.1747^{20}	1.3775^{20}	vs eth, EtOH
2054	Chlorofluoromethane		CH_2ClF	593-70-4	68.478	col gas	-135.1	-9.1			sl H_2O; vs chl
2055	1-Chloro-3-fluoro-2-methylbenzene		C_7H_6ClF	443-83-4	144.574			154	1.191^{25}	1.5026^{20}	
2056	2-Chloro-1-fluoro-4-nitrobenzene	3-Chloro-4-fluoronitrobenzene	$C_6H_3ClFNO_2$	350-30-1	175.545		41.5	229.5			
2057	4-Chloro-1-(4-fluorophenyl)-1-butanone		$C_{10}H_{10}ClFO$	3874-54-2	200.636			136^{6}	1.22^{25}	1.5255^{20}	
2058	3-Chloro-2,5-furandione		C_4HClO_3	96-02-6	132.502		33	196	1.5375^{25}	1.4980^{20}	
2059	1-Chloro-1,2,2,3,3,4,4-heptafluorocyclobutane	Refrigerant C317	C_4ClF_7	377-41-3	216.485	liq or gas	-39.1	25	1.602^{15}		
2060	1-Chloroheptane	Heptyl chloride	$C_7H_{15}Cl$	629-06-1	134.647	liq	-69.5	160.4	0.8762^{20}	1.4264^{20}	i H_2O; msc EtOH, eth; sl ctc; s chl
2061	2-Chloroheptane		$C_7H_{15}Cl$	1001-89-4	134.647			61^{32}, 46^{19}	0.8672^{20}	1.4221^{20}	i H_2O; vs eth; s bz, chl, HOAc
2062	3-Chloroheptane		$C_7H_{15}Cl$	999-52-0	134.647			144; 48^{20}	0.8690^{20}	1.4228^{20}	vs bz, eth
2063	4-Chloroheptane		$C_7H_{15}Cl$	998-95-8	134.647			144	0.8710^{20}	1.4237^{20}	vs bz, eth
2064	7-Chloro-1-heptanol	Heptamethylene chlorohydrin	$C_7H_{15}ClO$	55944-70-2	150.646	cry (peth, bz)	11	150^{20}	0.9998^{15}	1.4537^{25}	vs EtOH, peth
2065	1-Chlorohexadecane		$C_{16}H_{33}Cl$	4860-03-1	260.886		17.9	326.6	0.8635^{20}	1.4503^{20}	i H_2O
2066	1-Chlorohexane	Hexyl chloride	$C_6H_{13}Cl$	544-10-5	120.620	liq	-94.0	135.1	0.8781^{20}	1.4200^{20}	i H_2O; s EtOH, eth, ace, bz; vs chl; sl ctc
2067	2-Chlorohexane	2-Hexyl chloride	$C_6H_{13}Cl$	638-28-8	120.620			122.5	0.8694^{21}	1.4142^{22}	vs ace, bz, eth, EtOH
2068	3-Chlorohexane	3-Hexyl chloride	$C_6H_{13}Cl$	2346-81-8	120.620			123	0.8684^{20}	1.4163^{20}	vs ace, bz, eth, EtOH
2069	6-Chloro-1-hexanol		$C_6H_{13}ClO$	2009-83-8	136.619			107^{12}	1.0241^{20}	1.4550^{20}	sl H_2O; vs EtOH, eth
2070	4-Chloro-17-hydroxyandrost-4-en-3-one, (17β)	Clostebol	$C_{19}H_{27}ClO_2$	1093-58-9	322.869		189				
2071	5-Chloro-2-hydroxybenzaldehyde		$C_7H_5ClO_2$	635-93-8	156.567	pl (al)	100.3	105^{12}			i H_2O; vs EtOH; s eth, alk
2072	4-Chloro-α-hydroxybenzeneacetic acid		$C_8H_7ClO_3$	492-86-4	186.593		120.3				vs bz, EtOH
2073	3-Chloro-4-hydroxybenzoic acid		$C_7H_5ClO_3$	3964-58-7	172.566	nd (w)	171	sub			sl H_2O, bz, chl; vs EtOH, eth, ace
2074	5-Chloro-2-hydroxybenzoic acid		$C_7H_5ClO_3$	321-14-2	172.566	nd (w, al)	174.8				s H_2O, eth; vs EtOH, bz; sl ace
2075	2-Chloro-5-hydroxybenzophenone		$C_{13}H_9ClO_2$	85-19-8	232.662		95.3				i H_2O
2076	3-Chloro-4-hydroxy-5-methoxybenzaldehyde		$C_8H_7ClO_3$	19463-48-0	186.593	tetr	165				i H_2O; s EtOH, HOAc
2077	1-Chloro-2-iodobenzene		C_6H_4ClI	615-41-8	238.453		0.7	234.5	1.9515^{25}	1.6331^{25}	i H_2O; s ace; sl ctc
2078	1-Chloro-3-iodobenzene		C_6H_4ClI	625-99-0	238.453			230	1.9255^{20}		i H_2O; s ace
2079	1-Chloro-4-iodobenzene		C_6H_4ClI	637-87-6	238.453	lf (ace, al)	57	227	1.886^{27}		i H_2O; s EtOH, $PhNO_2$; sl chl
2080	1-Chloro-4-iodobutane		C_4H_8ClI	10297-05-9	218.464	liq		116; 89^{19}	1.785	1.5400^{20}	
2081	Chloroiodomethane		CH_2ClI	593-71-5	176.384			109	2.422^{20}	1.5822^{20}	vs ace, bz, eth, EtOH



N-(2-Chloroethyl)dibenzylamine hydrochloride



Chloroethyldimethylsilane



2-Chloroethyl ethyl ether



2-Chloroethyl isocyanate



1-(2-Chloroethyl)-3-(4-methylcyclohexyl)-1-nitrosourea



5-(2-Chloroethyl)-4-methylthiazole


N-(2-Chloroethyl)morpholine



4-(2-Chloroethyl)morpholine, hydrochloride



1-Chloro-2-(ethylthio)ethane


2-Chloroethyl vinyl ether



3-Chloro-4-fluoroaniline


1-Chloro-2-fluorobenzene



1-Chloro-3-fluorobenzene



1-Chloro-4-fluorobenzene



1-Chloro-1-fluoroethane



1-Chloro-2-fluoroethane



Chlorofluoromethane



1-Chloro-3-fluoro-2-methylbenzene



2-Chloro-1-fluoro-4-nitrobenzene



4-Chloro-1-(4-fluorophenyl)-1-butanone



3-Chloro-2,5-furandione



1-Chloro-1,2,2,3,3,4,4-heptafluorocyclobutane



1-Chloroheptane



2-Chloroheptane



3-Chloroheptane



4-Chloroheptane



7-Chloro-1-heptanol



1-Chlorohexadecane



1-Chlorohexane



2-Chlorohexane



3-Chlorohexane



6-Chloro-1-hexanol



4-Chloro-17-hydroxyandrost-4-en-3-one, (17β)



5-Chloro-2-hydroxybenzaldehyde


4-Chloro-α-hydroxybenzeneacetic acid



3-Chloro-4-hydroxybenzoic acid



5-Chloro-2-hydroxybenzoic acid



2-Chloro-5-hydroxybenzophenone


3-Chloro-4-hydroxy-5-methoxybenzaldehyde


1-Chloro-2-iodobenzene



1-Chloro-3-iodobenzene



1-Chloro-4-iodobenzene



1-Chloro-4-iodobutane



Chloroiodomethane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2082	1-Chloro-3-iodopropane		C_3H_6ClI	6940-76-7	204.437			171	1.904^{20}	1.5472^{20}	i H_2O; s eth, bz, chl; sl ctc
2083	5-Chloro-7-iodo-8-quinolinol	Iodochlorhydroxyquin	C_9H_5ClINO	130-26-7	305.499	ye br nd (al)	178.5				sl EtOH; s HOAc
2084	1-Chloro-2-isocyanatobenzene		C_7H_4ClNO	3320-83-0	153.566		30.5	200; 115^{43}			sl ctc
2085	1-Chloro-3-isocyanatobenzene		C_7H_4ClNO	2909-38-8	153.566			113^{43}			sl chl
2086	1-Chloro-2-isopropylbenzene		$C_9H_{11}Cl$	2077-13-6	154.636	liq	-74.4	191.1	1.0341^{20}	1.5168^{20}	vs ace, bz, eth, EtOH
2087	1-Chloro-4-isopropylbenzene		$C_9H_{11}Cl$	2621-46-7	154.636	liq	-12.3	198.3	1.0208^{20}	1.5117^{20}	i H_2O; msc EtOH, eth, ace, ctc; vs bz
2088	1-Chloro-4-isothiocyanatobenzene		C_7H_4ClNS	2131-55-7	169.632	nd (al)	46	249.5			i H_2O; s EtOH
2089	Chloromethane	Methyl chloride	CH_3Cl	74-87-3	50.488	col gas	-97.7	-24.09	0.911^{25} (p>1 atm)	1.3389^{20}	sl H_2O; s EtOH; msc eth, ace, bz, chl
2090	4-Chloro-2-methoxyaniline	4-Chloro-2-anisidine	C_7H_8ClNO	93-50-5	157.598	nd or pr (dil al)	52	260			s EtOH, eth, bz, chl
2091	5-Chloro-2-methoxyaniline		C_7H_8ClNO	95-03-4	157.598	nd (dil al)	84				s EtOH; sl lig
2092	(Chloromethoxy)ethane	Chloromethyl ethyl ether	C_3H_7ClO	3188-13-4	94.540			83	1.0188^{15}	1.4040^{20}	
2093	1-Chloro-2-methoxyethane		C_3H_7ClO	627-42-9	94.540			92.5	1.0345^{20}	1.4111^{20}	vs H_2O, eth
2094	[(Chloromethoxy)methyl]benzene		C_8H_9ClO	3587-60-8	156.609			103^{13}	1.1350^{20}	1.5192^{20}	
2095	1-(Chloromethoxy)propane		C_4H_9ClO	3587-57-3	108.566			109	0.9884^{20}	1.4125^{20}	vs eth, EtOH
2096	Chloromethyl acetate		$C_3H_5ClO_2$	625-56-9	108.524			116	1.194^{20}	1.409^{20}	vs eth, EtOH
2097	5-Chloro-2-(methylamino) benzophenone	*N*-Methyl-2-amino-5-chlorobenzophenone	$C_{14}H_{12}ClNO$	1022-13-5	245.704		92				
2098	4-Chloro-*N*-methylaniline		C_7H_8ClN	932-96-7	141.599			240	1.169^{11}	1.5835^{20}	s EtOH, ace, bz
2099	2-Chloro-4-methylaniline		C_7H_8ClN	615-65-6	141.599		7	220	1.151^{20}	1.5748^{22}	sl EtOH, bz
2100	2-Chloro-6-methylaniline		C_7H_8ClN	87-63-8	141.599			215; 97^{10}			
2101	3-Chloro-2-methylaniline		C_7H_8ClN	87-60-5	141.599		1	245		1.5880^{20}	s H_2O, EtOH; i eth, bz
2102	3-Chloro-4-methylaniline		C_7H_8ClN	95-74-9	141.599		26	243			s EtOH; sl ctc
2103	4-Chloro-2-methylaniline	*p*-Chloro-*o*-toluidine	C_7H_8ClN	95-69-2	141.599	lf (al)	30.3	244			s EtOH; sl ctc
2104	5-Chloro-2-methylaniline		C_7H_8ClN	95-79-4	141.599		26	239; 140^{38}			vs EtOH
2105	1-Chloro-2-methyl-9,10-anthracenedione		$C_{15}H_9ClO_2$	129-35-1	256.684		170.5				i EtOH, eth; sl py
2106	(Chloromethyl)benzene	Benzyl chloride	C_7H_7Cl	100-44-7	126.584	liq	-45	179	1.1004^{20}	1.5391^{20}	i H_2O; msc EtOH, eth, chl; sl ctc
2107	3-Chloro-*N*-methylbenzenemethanamine		$C_8H_{10}ClN$	39191-07-6	155.625			88^{4}		1.5350^{25}	s chl
2108	α-(Chloromethyl) benzenemethanol		C_8H_9ClO	1674-30-2	156.609			128^{17}, 121^{11}	1.1926^{20}	1.5523^{20}	s EtOH; vs eth
2109	4-Chloro-α-methylbenzenemethanol		C_8H_9ClO	3391-10-4	156.609			121^{15}		1.5505^{20}	s ctc
2110	5-(Chloromethyl)-1,3-benzodioxole		$C_8H_7ClO_2$	20850-43-5	170.594		20.5	134^{14}	1.312^{25}	1.5660^{20}	
2111	1-Chloro-3-methylbutane	Isopentyl chloride	$C_5H_{11}Cl$	107-84-6	106.594	liq	-104.4	98.9	0.8750^{20}	1.4084^{20}	sl H_2O; msc EtOH, eth; vs chl
2112	2-Chloro-2-methylbutane		$C_5H_{11}Cl$	594-36-5	106.594	liq	-73.5	85.6	0.8653^{20}	1.4055^{20}	sl H_2O; s EtOH, eth, ctc
2113	2-Chloro-3-methylbutane		$C_5H_{11}Cl$	631-65-2	106.594			91.5	0.878^{20}		
2114	1-Chloro-3-methyl-2-butene		C_5H_9Cl	503-60-6	104.578			109	0.9273^{20}	1.4485^{20}	vs ace, eth, EtOH, chl
2115	3-Chloro-3-methyl-1-butyne		C_5H_7Cl	1111-97-3	102.563	liq	-61	76	0.9061^{20}		
2116	(Chloromethyl)cyclopropane		C_4H_7Cl	5911-08-0	90.552	liq	-90.9	88	0.98^{25}	1.4350^{20}	
2117	1-(Chloromethyl)-2,4-dimethylbenzene		$C_9H_{11}Cl$	824-55-5	154.636			215.5; 110^{20}	1.0580^{19}		vs bz, eth, EtOH
2118	(Chloromethyl) dimethylphenylsilane		$C_9H_{13}ClSi$	1833-51-8	184.738			225	1.0240^{25}		s ctc, CS_2
2119	Chloromethyldiphenylsilane		$C_{13}H_{13}ClSi$	144-79-6	232.781			295	1.1277^{20}	1.5742^{20}	
2120	1-Chloro-3-(1-methylethoxy)-2-propanol		$C_6H_{13}ClO_2$	4288-84-0	152.619			182; 87^{20}	1.0910^{20}	1.4370^{25}	s EtOH, eth
2121	1-(Chloromethyl)-4-ethylbenzene		$C_9H_{11}Cl$	1467-05-6	154.636			95^{15}		1.5290^{25}	vs bz, EtOH, chl
2122	(1-Chloro-1-methylethyl)benzene		$C_9H_{11}Cl$	934-53-2	154.636			98^{1}	1.192^{25}	1.5290^{25}	
2123	1-(Chloromethyl)-2-fluorobenzene		C_7H_6ClF	345-35-7	144.574			172; 86^{40}	1.216^{25}	1.5150^{20}	
2124	1-(Chloromethyl)-4-fluorobenzene		C_7H_6ClF	352-11-4	144.574			82^{26}, 76^{20}	1.2143^{20}	1.5130	
2125	2-(Chloromethyl)furan		C_5H_5ClO	617-88-9	116.546			49^{26}	1.1783^{20}	1.4941^{20}	vs bz, eth, EtOH
2126	3-(Chloromethyl)heptane		$C_8H_{17}Cl$	123-04-6	148.674			172	0.8769^{20}	1.4319^{20}	i H_2O; s EtOH, eth, ace, bz; sl ctc



1-Chloro-3-iodopropane



5-Chloro-7-iodo-8-quinolinol


1-Chloro-2-isocyanatobenzene



1-Chloro-3-isocyanatobenzene



1-Chloro-2-isopropylbenzene



1-Chloro-4-isopropylbenzene



1-Chloro-4-isothiocyanatobenzene



Chloromethane



4-Chloro-2-methoxyaniline



5-Chloro-2-methoxyaniline



(Chloromethoxy)ethane



1-Chloro-2-methoxyethane



[(Chloromethoxy)methyl]benzene



1-(Chloromethoxy)propane



Chloromethyl acetate



5-Chloro-2-(methylamino)benzophenone



4-Chloro-*N*-methylaniline



2-Chloro-4-methylaniline



2-Chloro-6-methylaniline



3-Chloro-2-methylaniline



3-Chloro-4-methylaniline



4-Chloro-2-methylaniline



5-Chloro-2-methylaniline



1-Chloro-2-methyl-9,10-anthracenedione



(Chloromethyl)benzene


3-Chloro-*N*-methylbenzenemethanamine


α-(Chloromethyl)benzenemethanol



4-Chloro-α-methylbenzenemethanol


5-(Chloromethyl)-1,3-benzodioxole


1-Chloro-3-methylbutane



2-Chloro-2-methylbutane



2-Chloro-3-methylbutane



1-Chloro-3-methyl-2-butene



3-Chloro-3-methyl-1-butyne



(Chloromethyl)cyclopropane



1-(Chloromethyl)-2,4-dimethylbenzene



(Chloromethyl)dimethylphenylsilane



Chloromethyldiphenylsilane



1-Chloro-3-(1-methylethoxy)-2-propanol



1-(Chloromethyl)-4-ethylbenzene


(1-Chloro-1-methylethyl)benzene



1-(Chloromethyl)-2-fluorobenzene



1-(Chloromethyl)-4-fluorobenzene



2-(Chloromethyl)furan



3-(Chloromethyl)heptane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2127	4-Chloro-5-methyl-2-isopropylphenol	Chlorothymol	$C_{10}H_{13}ClO$	89-68-9	184.662		63	258.5			vs H_2O; s EtOH, eth, bz, ctc, peth, alk
2128	1-(Chloromethyl)-4-methoxybenzene		C_8H_9ClO	824-94-2	156.609	nd	24.5	262.5	1.261^{20}	1.580^{20}	vs ace, bz, eth
2129	1-(Chloromethyl)-2-methylbenzene		C_8H_9Cl	552-45-4	140.610			198; 90^{20}	1.063^{25}	1.5410^{25}	vs eth, EtOH
2130	1-(Chloromethyl)-3-methylbenzene		C_8H_9Cl	620-19-9	140.610			195.5	1.064^{20}	1.5345^{20}	i H_2O; s EtOH, eth
2131	1-(Chloromethyl)-4-methylbenzene		C_8H_9Cl	104-82-5	140.610			201; 90^{20}	1.0512^{20}	1.5380	i H_2O; s EtOH; msc eth
2132	Chloromethyl methyl ether		C_2H_5ClO	107-30-2	80.513	liq	-103.5	59.5	1.063^{10}	1.397^{20}	s EtOH, eth, ace, chl
2133	2-(Chloromethyl)-2-methyloxirane		C_4H_7ClO	598-09-4	106.551			122	1.1011^{20}	1.4310^{20}	vs H_2O, eth
2134	1-(Chloromethyl)naphthalene		$C_{11}H_9Cl$	86-52-2	176.642	pr	32	291.5	1.1813^{20}	1.6380^{20}	i H_2O; s EtOH, ctc, peth
2135	2-(Chloromethyl)naphthalene		$C_{11}H_9Cl$	2506-41-4	176.642	lf (al)	48.5	169^{20}			i H_2O; s EtOH, peth
2136	1-(Chloromethyl)-2-nitrobenzene		$C_7H_6ClNO_2$	612-23-7	171.582	cry (lig)	50.0	125^{4}		1.5557^{62}	i H_2O; s EtOH, eth, HOAc; vs ace, bz
2137	1-(Chloromethyl)-3-nitrobenzene		$C_7H_6ClNO_2$	619-23-8	171.582	pa ye nd (lig)	46	173^{34}		1.5577^{62}	vs ace, bz, eth, EtOH
2138	1-(Chloromethyl)-4-nitrobenzene	4-Nitrobenzyl chloride	$C_7H_6ClNO_2$	100-14-1	171.582	pl or nd (al)	71			1.5647^{62}	i H_2O; s EtOH, eth; vs ace, bz, AcOEt
2139	1-Chloro-2-methyl-3-nitrobenzene		$C_7H_6ClNO_2$	83-42-1	171.582	nd (dil al)	37.8	238		1.5377^{69}	i H_2O; s EtOH
2140	1-Chloro-2-methyl-4-nitrobenzene		$C_7H_6ClNO_2$	13290-74-9	171.582	ye cry	42.5	249			vs eth
2141	1-Chloro-4-methyl-2-nitrobenzene	4-Chloro-3-nitrotoluene	$C_7H_6ClNO_2$	89-60-1	171.582		7	261; 118^{11}		1.5572^{20}	i H_2O; s ctc
2142	2-Chloro-1-methyl-4-nitrobenzene		$C_7H_6ClNO_2$	121-86-8	171.582	nd (al)	66.5	260		1.5470^{69}	sl H_2O, chl; s EtOH, eth, HOAc
2143	4-Chloro-1-methyl-2-nitrobenzene		$C_7H_6ClNO_2$	89-59-8	171.582	mcl nd	38	242; 115.5^{11}	1.2559^{80}		i H_2O; s EtOH, eth; sl chl
2144	2-Chloro-4-methylpentane		$C_6H_{13}Cl$	25346-32-1	120.620			113	0.8610^{20}	1.4113^{20}	vs eth
2145	3-(Chloromethyl)pentane		$C_6H_{13}Cl$	4737-41-1	120.620			126; 83^{202}	0.8914^{20}	1.4222^{20}	vs bz, eth, chl
2146	2-Chloro-4-methylphenol	2-Chloro-*p*-cresol	C_7H_7ClO	6640-27-3	142.583			195.5	1.1785^{27}	1.5200^{27}	vs bz, eth, EtOH
2147	2-Chloro-5-methylphenol	6-Chloro-*m*-cresol	C_7H_7ClO	615-74-7	142.583	pr (peth)	45.5	196	1.215^{15}		vs H_2O, EtOH
2148	2-Chloro-6-methylphenol	6-Chloro-*o*-cresol	C_7H_7ClO	87-64-9	142.583			189; 80^{20}		1.5449^{20}	sl H_2O; s eth
2149	3-Chloro-4-methylphenol	3-Chloro-*p*-cresol	C_7H_7ClO	615-62-3	142.583	nd (al)	55.5	228			vs bz, eth, EtOH
2150	4-Chloro-2-methylphenol	4-Chloro-*o*-cresol	C_7H_7ClO	1570-64-5	142.583	nd (peth)	51	223			sl H_2O; s peth
2151	4-Chloro-3-methylphenol	4-Chloro-*m*-cresol	C_7H_7ClO	59-50-7	142.583	nd (peth)	67	235			sl H_2O, chl; s EtOH, eth, peth
2152	(4-Chloro-2-methylphenoxy)acetic acid	MCPA	$C_9H_9ClO_3$	94-74-6	200.618	pl (bz, to)	120				sl H_2O; vs EtOH, eth; s bz, ctc
2153	4-(4-Chloro-2-methylphenoxy) butanoic acid		$C_{11}H_{13}ClO_3$	94-81-5	228.672		100				
2154	Chloromethylphenylsilane		C_7H_9ClSi	1631-82-9	156.685			113^{100}	1.043^{20}	1.5171^{20}	
2155	(Chloromethyl)phosphonic acid		CH_4ClO_3P	2565-58-4	130.468	nd (bz/ $MeNO_2$)	90				
2156	*N*-Chloromethylphthalimide		$C_9H_6ClNO_2$	17564-64-6	195.603		135.5				
2157	2-Chloro-2-methylpropanal		C_4H_7ClO	917-93-1	106.551			90	1.053^{15}	1.4160^{16}	vs eth, EtOH
2158	1-Chloro-2-methylpropane	Isobutyl chloride	C_4H_9Cl	513-36-0	92.567	liq	-130.3	68.5	0.8773^{20}	1.3984^{20}	sl H_2O, ctc; s eth, ace, chl
2159	2-Chloro-2-methylpropane	*tert*-Butyl chloride	C_4H_9Cl	507-20-0	92.567	liq	-25.60	50.9	0.8420^{20}	1.3857^{20}	sl H_2O; msc EtOH, eth; s bz, ctc, chl
2160	1-Chloro-2-methylpropene	Dimethylvinyl chloride	C_4H_7Cl	513-37-1	90.552			68	0.9186^{20}	1.4221^{20}	sl H_2O; s chl
2161	3-Chloro-2-methylpropene		C_4H_7Cl	563-47-3	90.552			71.5	0.9165^{20}	1.4291^{20}	msc EtOH, eth; s ace; vs chl
2162	3-(Chloromethyl)pyridine, hydrochloride		$C_6H_7Cl_2N$	6959-48-4	164.033	hyg	143.8				
2163	Chloromethylsilane		CH_5ClSi	993-00-0	80.590	col gas	-135	$7; -45^{63}$			
2164	1-Chloro-4-(methylsulfonyl) benzene	4-Chlorobenzenethiol, *S*-methyl, *S,S*-dioxide	$C_7H_7ClO_2S$	98-57-7	190.648		98				
2165	1-Chloro-4-(methylthio)benzene		C_7H_7ClS	123-09-1	158.649			105^{10}			
2166	1-Chloro-2-(methylthio)ethane		C_3H_7ClS	542-81-4	110.606			140; 60^{30}	1.123^{20}	1.4902^{20}	s EtOH, eth, ace
2167	Chloro(methylthio)methane		C_2H_5ClS	2373-51-5	96.579			105	1.153^{25}	1.4963^{20}	
2168	(Chloromethyl)trimethylsilane		$C_4H_{11}ClSi$	2344-80-1	122.669			98.5	0.879^{25}	1.4175^{20}	



4-Chloro-5-methyl-2-isopropylphenol



1-(Chloromethyl)-4-methoxybenzene



1-(Chloromethyl)-2-methylbenzene



1-(Chloromethyl)-3-methylbenzene



1-(Chloromethyl)-4-methylbenzene



Chloromethyl methyl ether



2-(Chloromethyl)-2-methyloxirane



1-(Chloromethyl)naphthalene



2-(Chloromethyl)naphthalene



1-(Chloromethyl)-2-nitrobenzene



1-(Chloromethyl)-3-nitrobenzene



1-(Chloromethyl)-4-nitrobenzene



1-Chloro-2-methyl-3-nitrobenzene



1-Chloro-2-methyl-4-nitrobenzene



1-Chloro-4-methyl-2-nitrobenzene



2-Chloro-1-methyl-4-nitrobenzene



4-Chloro-1-methyl-2-nitrobenzene



2-Chloro-4-methylpentane



3-(Chloromethyl)pentane



2-Chloro-4-methylphenol



2-Chloro-5-methylphenol



2-Chloro-6-methylphenol



3-Chloro-4-methylphenol



4-Chloro-2-methylphenol



4-Chloro-3-methylphenol


(4-Chloro-2-methylphenoxy)acetic acid



4-(4-Chloro-2-methylphenoxy)butanoic acid


Chloromethylphenylsilane



(Chloromethyl)phosphonic acid



N-Chloromethylphthalimide



2-Chloro-2-methylpropanal


1-Chloro-2-methylpropane



2-Chloro-2-methylpropane



1-Chloro-2-methylpropene



3-Chloro-2-methylpropene



3-(Chloromethyl)pyridine, hydrochloride



Chloromethylsilane


1-Chloro-4-(methylsulfonyl)benzene



1-Chloro-4-(methylthio)benzene



1-Chloro-2-(methylthio)ethane



Chloro(methylthio)methane



(Chloromethyl)trimethylsilane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2169	1-Chloronaphthalene	1-Naphthyl chloride	$C_{10}H_7Cl$	90-13-1	162.616	oily liq	-2.5	259; 106.5[5]	1.1880[25]	1.6326[20]	i H_2O; s EtOH, eth, bz, CS_2; sl ctc
2170	2-Chloronaphthalene		$C_{10}H_7Cl$	91-58-7	162.616	pl (dil al), lf	58.0	256	1.1377[71]	1.6079[13]	i H_2O; s EtOH, eth, bz, chl, CS_2
2171	4-Chloro-1-naphthol		$C_{10}H_7ClO$	604-44-4	178.615	nd (chl, aq al)	120.5				s EtOH, eth, ace, bz, chl
2172	Chloroneb	1,4-Dichloro-2,5-dimethoxybenzene	$C_8H_8Cl_2O_2$	2675-77-6	207.055		134	268			
2173	2-Chloro-4-nitroaniline		$C_6H_5ClN_2O_2$	121-87-9	172.569	ye nd (w)	108				vs eth, EtOH, HOAc
2174	2-Chloro-5-nitroaniline		$C_6H_5ClN_2O_2$	6283-25-6	172.569	ye nd (lig)	121				vs eth, EtOH, HOAc
2175	4-Chloro-2-nitroaniline		$C_6H_5ClN_2O_2$	89-63-4	172.569	dk oran-ye pr (dil al)	116.5				vs EtOH, eth, HOAc; sl ace, lig
2176	4-Chloro-3-nitroaniline		$C_6H_5ClN_2O_2$	635-22-3	172.569	ye nd or pr (w) nd (peth)	103				s H_2O, eth, chl; vs EtOH; sl lig
2177	5-Chloro-2-nitroaniline		$C_6H_5ClN_2O_2$	1635-61-6	172.569	ye nd (CS_2) ye lf (al, bz)	127.8	sub			vs eth, EtOH
2178	1-Chloro-5-nitro-9,10-anthracenedione		$C_{14}H_6ClNO_4$	129-40-8	287.656		315.3				i H_2O, EtOH, eth, lig; sl bz; s py
2179	2-Chloro-5-nitrobenzaldehyde		$C_7H_4ClNO_3$	6361-21-3	185.565	cry (al)	81.3				vs EtOH, chl
2180	4-Chloro-3-nitrobenzaldehyde		$C_7H_4ClNO_3$	16588-34-4	185.565		64.5				sl H_2O; s chl
2181	1-Chloro-2-nitrobenzene	*o*-Chloronitrobenzene	$C_6H_4ClNO_2$	88-73-3	157.555	mcl nd	32.1	245.5	1.368[242]		i H_2O; s EtOH, eth, bz; vs ace, tol, py
2182	1-Chloro-3-nitrobenzene	*m*-Chloronitrobenzene	$C_6H_4ClNO_2$	121-73-3	157.555	pa ye orth pr (al)	44.4	235.5	1.343[50]	1.5374[80]	i H_2O; s EtOH, eth, bz, chl, CS_2
2183	1-Chloro-4-nitrobenzene	*p*-Chloronitrobenzene	$C_6H_4ClNO_2$	100-00-5	157.555	mcl pr	82	242	1.2979[90]	1.5376[100]	i H_2O; sl EtOH; s eth, chl, CS_2
2184	5-Chloro-3-nitro-1,2-benzenediamine		$C_6H_6ClN_3O_2$	42389-30-0	187.584		167				
2185	4-Chloro-3-nitrobenzenesulfonamide		$C_6H_5ClN_2O_4S$	97-09-6	236.633	ye cry (EtOH)	175				
2186	4-Chloro-3-nitrobenzenesulfonyl chloride		$C_6H_3Cl_2NO_4S$	97-08-5	256.064		60.8				
2187	2-Chloro-4-nitrobenzoic acid		$C_7H_4ClNO_4$	99-60-5	201.565	nd (w)	141.8				s H_2O, EtOH, eth, bz
2188	2-Chloro-5-nitrobenzoic acid		$C_7H_4ClNO_4$	2516-96-3	201.565	nd or pr (w)	166.5		1.608[18]		sl H_2O, ace; s EtOH, eth, bz
2189	4-Chloro-3-nitrobenzoic acid		$C_7H_4ClNO_4$	96-99-1	201.565	nd or pl (w)	182.8		1.645[18]		i H_2O; sl EtOH, ace
2190	1-Chloro-1-nitroethane		$C_2H_4ClNO_2$	598-92-5	109.512			124.5	1.2837[20]	1.4224[20]	i H_2O; s EtOH, ctc, alk
2191	2-Chloro-4-nitrophenol		$C_6H_4ClNO_3$	619-08-9	173.554	wh nd (50% al)	111				s H_2O, EtOH, eth, chl; sl bz
2192	4-Chloro-2-nitrophenol		$C_6H_4ClNO_3$	89-64-5	173.554	ye mcl pr (al)	88.5				i H_2O; s EtOH, eth, chl; sl ace
2193	5-Chloro-2-nitrophenol		$C_6H_4ClNO_3$	611-07-4	173.554	ye pr or nd (w)	41	sub			sl H_2O; s EtOH, eth, HOAc
2194	1-Chloro-1-nitropropane		$C_3H_6ClNO_2$	600-25-9	123.539			142	1.207[20]	1.4251[20]	sl H_2O, chl; s EtOH, eth, oils
2195	2-Chloro-2-nitropropane		$C_3H_6ClNO_2$	594-71-8	123.539		-21.5	dec 134; 57[50]	1.2[20]	1.4378[19]	sl H_2O; s EtOH, eth, ctc, oils; i KOH
2196	2-Chloro-3-nitropyridine		$C_5H_3ClN_2O_2$	5470-18-8	158.543	nd (w)	104.0				
2197	1-Chloro-2-nitro-4-(trifluoromethyl)benzene		$C_7H_3ClF_3NO_2$	121-17-5	225.553	liq	-1.3	222; 95[10]	1.511[25]	1.4893[20]	
2198	1-Chloro-4-nitro-2-(trifluoromethyl)benzene		$C_7H_3ClF_3NO_2$	777-37-7	225.553		22	232	1.527[25]	1.5083[26]	
2199	1-Chlorononane		$C_9H_{19}Cl$	2473-01-0	162.700	liq	-39.4	205.2	0.8706[20]	1.4343[20]	i H_2O; s eth, chl
2200	9-Chloro-1-nonanol		$C_9H_{19}ClO$	51308-99-7	178.699		28	147[14]		1.4575[20]	vs eth, EtOH
2201	1-Chlorooctadecane		$C_{18}H_{37}Cl$	3386-33-2	288.940		28.6	352	0.8616[20]	1.4524[20]	i H_2O; sl ctc
2202	1-Chlorooctane	Octyl chloride	$C_8H_{17}Cl$	111-85-3	148.674	liq	-57.8	183.5	0.8734[20]	1.4309[20]	i H_2O; vs EtOH, eth; sl ctc
2203	2-Chlorooctane		$C_8H_{17}Cl$	628-61-5	148.674			172; 75[28]	0.8658[17]	1.4273[21]	i H_2O; vs EtOH, eth
2204	8-Chloro-1-octanol		$C_8H_{17}ClO$	23144-52-7	164.673			139[19]		1.4563[25]	vs eth, EtOH
2205	Chloropentafluoroacetone		C_3ClF_5O	79-53-8	182.476	col gas	-133	8			
2206	Chloropentafluorobenzene		C_6ClF_5	344-07-0	202.509			117.96	1.568[25]	1.4256[20]	



1-Chloronaphthalene



2-Chloronaphthalene



4-Chloro-1-naphthol



Chloroneb



2-Chloro-4-nitroaniline



2-Chloro-5-nitroaniline



4-Chloro-2-nitroaniline



4-Chloro-3-nitroaniline



5-Chloro-2-nitroaniline



1-Chloro-5-nitro-9,10-anthracenedione



2-Chloro-5-nitrobenzaldehyde



4-Chloro-3-nitrobenzaldehyde



1-Chloro-2-nitrobenzene



1-Chloro-3-nitrobenzene



1-Chloro-4-nitrobenzene



5-Chloro-3-nitro-1,2-benzenediamine


4-Chloro-3-nitrobenzenesulfonamide



4-Chloro-3-nitrobenzenesulfonyl chloride



2-Chloro-4-nitrobenzoic acid



2-Chloro-5-nitrobenzoic acid



4-Chloro-3-nitrobenzoic acid



1-Chloro-1-nitroethane



2-Chloro-4-nitrophenol



4-Chloro-2-nitrophenol



5-Chloro-2-nitrophenol



1-Chloro-1-nitropropane



2-Chloro-2-nitropropane



2-Chloro-3-nitropyridine



1-Chloro-2-nitro-4-(trifluoromethyl)benzene



1-Chloro-4-nitro-2-(trifluoromethyl)benzene



1-Chlorononane



9-Chloro-1-nonanol



1-Chlorooctadecane


1-Chlorooctane



2-Chlorooctane



8-Chloro-1-octanol



Chloropentafluoroacetone



Chloropentafluorobenzene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2207	Chloropentafluoroethane	Refrigerant 115	C_2ClF_5	76-15-3	154.466	col gas	-99.4	-39.1	1.5678^{-42}	1.2678^{-42}	i H_2O; s EtOH, eth
2208	1-Chloropentane	Pentyl chloride	$C_5H_{11}Cl$	543-59-9	106.594	liq	-99.0	108.4	0.8820^{20}	1.4126^{20}	i H_2O; msc EtOH, eth; s bz, ctc; vs chl
2209	2-Chloropentane, (+)	*sec*-Pentyl chloride	$C_5H_{11}Cl$	29882-57-3	106.594	liq	-137	97.0	0.8698^{20}	1.4069^{20}	i H_2O; s EtOH, eth, bz; vs chl
2210	3-Chloropentane		$C_5H_{11}Cl$	616-20-6	106.594	liq	-105	97.5	0.8731^{20}	1.4082^{20}	i H_2O; s EtOH, eth, bz; sl ace
2211	5-Chloropentanoic acid		$C_5H_9ClO_2$	1119-46-6	136.577		18	230	1.3416^{25}	1.4555^{20}	vs eth, EtOH
2212	5-Chloro-1-pentanol		$C_5H_{11}ClO$	5259-98-3	122.593			112^{12}		1.4518^{20}	vs eth, EtOH
2213	5-Chloro-2-pentanone		C_5H_9ClO	5891-21-4	120.577			106^{110}, 76^{34}	1.0523^{20}	1.4375^{20}	s eth, ace; sl ctc
2214	1-Chloro-3-pentanone		C_5H_9ClO	32830-97-0	120.577			68^{20}		1.4361^{20}	vs eth, EtOH
2215	5-Chloropentanoyl chloride		$C_5H_8Cl_2O$	1575-61-7	155.022			83^{12}	1.210^{18}	1.4639^{20}	vs eth
2216	4-Chloro-2-pentene		C_5H_9Cl	1458-99-7	104.578			103; 47^{25}	0.8988^{20}	1.4322^{20}	vs ace, eth, chl
2217	2-Chlorophenol		C_6H_5ClO	95-57-8	128.556		9.4	174.9	1.2634^{20}	1.5524^{20}	sl H_2O, chl; s EtOH, eth; vs bz
2218	3-Chlorophenol		C_6H_5ClO	108-43-0	128.556		32.6	214	1.245^{45}	1.5565^{40}	sl H_2O, chl; s EtOH, eth; vs bz
2219	4-Chlorophenol		C_6H_5ClO	106-48-9	128.556		42.8	220	1.2651^{40}	1.5579^{40}	sl H_2O; vs EtOH, eth, bz; s alk
2220	Chlorophenol Red		$C_{19}H_{12}Cl_2O_5S$	4430-20-0	423.266	grn-br cry	261				sl H_2O; s EtOH
2221	2-Chloro-10*H*-phenothiazine		$C_{12}H_8ClNS$	92-39-7	233.717		198.5				
2222	2-Chlorophenoxyacetic acid		$C_8H_7ClO_3$	614-61-9	186.593	nd (w, al)	148.5				s H_2O, EtOH
2223	3-Chlorophenoxyacetic acid		$C_8H_7ClO_3$	588-32-9	186.593	cry (w)	110				i H_2O
2224	(4-Chlorophenoxy)acetic acid		$C_8H_7ClO_3$	122-88-3	186.593	pr or nd (w)	156.5				vs H_2O; sl chl
2225	1-Chloro-4-phenoxybenzene	4-Chlorophenyl phenyl ether	$C_{12}H_9ClO$	7005-72-3	204.651			284.5	1.2026^{15}	1.599	
2226	3-(4-Chlorophenoxy)-1,2-propanediol	Chlorphenesin	$C_9H_{11}ClO_3$	104-29-0	202.634	cry	78	214^{19}			i H_2O; vs EtOH, eth; s bz, con sulf
2227	2-(3-Chlorophenoxy)propanoic acid	Cloprop	$C_9H_9ClO_3$	101-10-0	200.618	cry	113	$100^{1.5}$			
2228	2-Chloro-*N*-phenylacetamide		C_8H_8ClNO	587-65-5	169.609	nd (dil HOAc)		sub			vs bz, eth, EtOH
2229	*N*-(2-Chlorophenyl)acetamide		C_8H_8ClNO	533-17-5	169.609		88.3				i H_2O; s EtOH, bz, chl; vs eth
2230	*N*-(3-Chlorophenyl)acetamide		C_8H_8ClNO	588-07-8	169.609	nd	79	333			sl H_2O; vs EtOH, eth, bz, CS_2; s chl
2231	*N*-(4-Chlorophenyl)acetamide		C_8H_8ClNO	539-03-7	169.609		179	333	1.385^{22}		i H_2O; s EtOH; vs eth; sl ctc
2232	4-Chloro-α-phenylbenzenemethanol		$C_{13}H_{11}ClO$	119-56-2	218.678		59				sl chl
2233	4-Chlorophenyl benzenesulfonate		$C_{12}H_9ClO_3S$	80-38-6	268.715	col cry	62		1.33		sl H_2O
2234	4-Chloro-1-phenyl-1-butanone		$C_{10}H_{11}ClO$	939-52-6	182.646		19.5	131^{4}	1.137^{25}	1.5459^{20}	
2235	4-Chlorophenyl 4-chlorobenzenesulfonate	Ovex	$C_{12}H_8Cl_2O_3S$	80-33-1	303.161		86.5				i H_2O; sl EtOH; s ace
2236	(2-Chlorophenyl)(4-chlorophenyl) methanone	2,4'-Dichlorodiphenyl ketone	$C_{13}H_8Cl_2O$	85-29-0	251.108	pr (al)	67	214^{22}	1.393^{14}		s EtOH; sl chl
2237	*N'*-(4-Chlorophenyl)-*N,N*-dimethylurea	Monuron	$C_9H_{11}ClN_2O$	150-68-5	198.648	wh pl (MeOH)	170.5				i H_2O; sl EtOH, ace
2238	1-(3-Chlorophenyl)ethanone	*m*-Chloroacetophenone	C_8H_7ClO	99-02-5	154.594			244; 129^{30}	1.2130^{40}	1.5494^{20}	s EtOH, eth, ace
2239	1-(4-Chlorophenyl)ethanone	*p*-Chloroacetophenone	C_8H_7ClO	99-91-2	154.594		20	232	1.1922^{20}	1.5550^{20}	i H_2O; msc EtOH, eth; s chl
2240	5-(4-Chlorophenyl)-6-ethyl-2,4-pyrimidinediamine	Pyrimethamine	$C_{12}H_{13}ClN_4$	58-14-0	248.711		233.5				
2241	2-(4-Chlorophenyl)-1*H*-indene-1,3(2*H*)-dione	Clorindione	$C_{15}H_9ClO_2$	1146-99-2	256.684	dk red nd (al)	145.5				vs bz, eth, EtOH
2242	4-Chlorophenyl isocyanate		C_7H_4ClNO	104-12-1	153.566		31.3	116^{45}			
2243	1-(2-Chlorophenyl)-2-methyl-2-propylamine	Clortermine	$C_{10}H_{14}ClN$	10389-73-8	183.678	liq		117^{16}			
2244	*N*-(2-Chlorophenyl)-3-oxobutanamide		$C_{10}H_{10}ClNO_2$	93-70-9	211.645		106.5				s EtOH; i eth, lig
2245	(4-Chlorophenyl) phenylmethanone		$C_{13}H_9ClO$	134-85-0	216.662	nd (al)	77.5	332			s EtOH, eth, ace; sl ctc
2246	3-(2-Chlorophenyl)propanoic acid		$C_9H_9ClO_2$	1643-28-3	184.619	nd or lf (w)	102				
2247	3-(3-Chlorophenyl)propanoic acid		$C_9H_9ClO_2$	21640-48-2	184.619	lf (peth)	77				
2248	3-(4-Chlorophenyl)propanoic acid		$C_9H_9ClO_2$	2019-34-3	184.619		126				
2249	3-Chloro-1-phenyl-1-propanone	2-Chloroethyl phenyl ketone	C_9H_9ClO	936-59-4	168.619	lf (eth), cry (al, peth)	49.5	113^{4}			



Chloropentafluoroethane



1-Chloropentane



2-Chloropentane, (+)



3-Chloropentane



5-Chloropentanoic acid


5-Chloro-1-pentanol



5-Chloro-2-pentanone



1-Chloro-3-pentanone



5-Chloropentanoyl chloride



4-Chloro-2-pentene



2-Chlorophenol



3-Chlorophenol



4-Chlorophenol



Chlorophenol Red



2-Chloro-10*H*-phenothiazine



2-Chlorophenoxyacetic acid



3-Chlorophenoxyacetic acid



(4-Chlorophenoxy)acetic acid



1-Chloro-4-phenoxybenzene



3-(4-Chlorophenoxy)-1,2-propanediol



2-(3-Chlorophenoxy)propanoic acid



2-Chloro-*N*-phenylacetamide



N-(2-Chlorophenyl)acetamide



N-(3-Chlorophenyl)acetamide



N-(4-Chlorophenyl)acetamide



4-Chloro-α-phenylbenzenemethanol



4-Chlorophenyl benzenesulfonate



4-Chloro-1-phenyl-1-butanone



4-Chlorophenyl 4-chlorobenzenesulfonate



(2-Chlorophenyl)(4-chlorophenyl)methanone



N'-(4-Chlorophenyl)-*N,N*-dimethylurea



1-(3-Chlorophenyl)ethanone



1-(4-Chlorophenyl)ethanone



5-(4-Chlorophenyl)-6-ethyl-2,4-pyrimidinediamine



2-(4-Chlorophenyl)-1*H*-indene-1,3(2*H*)-dione



4-Chlorophenyl isocyanate



1-(2-Chlorophenyl)-2-methyl-2-propylamine



N-(2-Chlorophenyl)-3-oxobutanamide


(4-Chlorophenyl)phenylmethanone



3-(2-Chlorophenyl)propanoic acid



3-(3-Chlorophenyl)propanoic acid



3-(4-Chlorophenyl)propanoic acid



3-Chloro-1-phenyl-1-propanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2250	1-(4-Chlorophenyl)-1-propanone		C_9H_9ClO	6285-05-8	168.619		37.3	135[31], 114[2]			i H_2O; s EtOH, CS_2; sl chl
2251	3-(3-Chlorophenyl)-2-propynoic acid		$C_9H_5ClO_2$	7396-28-3	180.588	cry (HOAc, bz-peth)	144.5				vs HOAc
2252	Chlorophenylsilane	Phenylchlorosilane	C_6H_7ClSi	4206-75-1	142.659			162.5	1.0683^{20}	1.5340^{20}	
2253	1-Chloro-4-(phenylsulfonyl) benzene	Sulphenone	$C_{12}H_9ClO_2S$	80-00-2	252.716		94				i H_2O; sl EtOH; s eth; vs ace, bz
2254	5-Chloro-1-phenyltetrazole		$C_7H_5ClN_4$	14210-25-4	180.595		123				
2255	(2-Chlorophenyl)thiourea		$C_7H_7ClN_2S$	5344-82-1	186.662	nd or pl	146				vs bz, EtOH
2256	α-Chlorophyll		$C_{55}H_{72}MgN_4O_5$	479-61-8	893.490	bl blk hex pl	152.3				i H_2O; vs EtOH, eth; s lig
2257	β-Chlorophyll		$C_{55}H_{70}MgN_4O_6$	519-62-0	907.473	bl-blk or grn pow	125				i H_2O; vs EtOH, eth, py; s MeOH
2258	Chloropropamide	4-Chloro-*N*-[(propylamino) carbonyl]benzenesulfonamide	$C_{10}H_{13}ClN_2O_3S$	94-20-2	276.739	cry (EtOH)	128				i H_2O; s EtOH; sl eth, bz
2259	2-Chloropropanal		C_3H_5ClO	683-50-1	92.524			86	1.182^{15}	1.431^{17}	vs bz, eth
2260	1-Chloropropane	Propyl chloride	C_3H_7Cl	540-54-5	78.541	liq	-122.9	46.5	0.8899^{20}	1.3879^{20}	sl H_2O, ctc; msc EtOH, eth; s bz, chl
2261	2-Chloropropane	Isopropyl chloride	C_3H_7Cl	75-29-6	78.541	liq	-117.18	35.7	0.8617^{20}	1.3777^{20}	sl H_2O; msc EtOH, eth; s bz, ctc, chl
2262	3-Chloro-1,2-propanediol	α-Chlorohydrin	$C_3H_7ClO_2$	96-24-2	110.540	ye liq		dec 213; 116[11]	1.325^{18}	1.4809^{20}	s H_2O, EtOH, eth
2263	2-Chloro-1,3-propanediol	Glycerol β-chlorohydrin	$C_3H_7ClO_2$	497-04-1	110.540			146[18], 124[14]	1.3219^{20}	1.4831^{20}	vs H_2O, ace, EtOH
2264	3-Chloro-1,2-propanediol dinitrate	Clonitrate	$C_3H_5ClN_2O_6$	2612-33-1	200.534	sl ye liq		192.5	1.5112^{9}		vs ace, EtOH, chl
2265	3-Chloropropanenitrile	β-Chloropropionitrile	C_3H_4ClN	542-76-7	89.524	liq	-51	175.5	1.1573^{20}	1.4360^{20}	sl ctc
2266	2-Chloropropanoic acid	2-Chloropropionic acid	$C_3H_5ClO_2$	598-78-7	108.524			185	1.2585^{20}	1.4380^{20}	msc H_2O, EtOH, eth; s ace
2267	3-Chloropropanoic acid	β-Chloropropionic acid	$C_3H_5ClO_2$	107-94-8	108.524	lf (w), hyg cry (lig)	41	dec 204			s H_2O, EtOH, chl; msc eth
2268	2-Chloro-1-propanol	Propylene chlorohydrin	C_3H_7ClO	78-89-7	94.540			133.5	1.103^{20}	1.4390^{20}	vs H_2O, eth, EtOH
2269	3-Chloro-1-propanol		C_3H_7ClO	627-30-5	94.540			165	1.1309^{20}	1.4459^{20}	vs H_2O; s EtOH, eth; sl ctc
2270	1-Chloro-2-propanol	*sec*-Propylene chlorohydrin	C_3H_7ClO	127-00-4	94.540			127	1.113^{20}	1.4392^{20}	msc H_2O, EtOH, eth; sl ctc
2271	3-Chloropropanoyl chloride		$C_3H_4Cl_2O$	625-36-5	126.969			144	1.3307^{13}	1.4549^{20}	sl H_2O; vs EtOH, eth, chl
2272	*cis*-1-Chloropropene		C_3H_5Cl	16136-84-8	76.525	liq	-134.8	32.8	0.9347^{20}	1.4055^{20}	i H_2O; s eth, ace, bz, chl
2273	*trans*-1-Chloropropene		C_3H_5Cl	16136-85-9	76.525	liq	-99	37.4	0.9349^{20}	1.4054^{20}	i H_2O; s eth, ace, bz, chl
2274	2-Chloropropene	Isopropenyl chloride	C_3H_5Cl	557-98-2	76.525	vol liq or gas	-137.4	22.6	0.9017^{20}	1.3973^{20}	i H_2O; s eth, ace, bz, chl
2275	3-Chloropropene	Allyl chloride	C_3H_5Cl	107-05-1	76.525	liq	-134.5	45.1	0.9376^{20}	1.4157^{20}	i H_2O; msc EtOH, eth, ace, bz, lig; sl ctc
2276	2-Chloro-2-propenenitrile		C_3H_2ClN	920-37-6	87.508	liq	-65	88.5	1.096^{25}	1.4290^{20}	
2277	2-Chloropropenoic acid	2-Chloroacrylic acid	$C_3H_3ClO_2$	598-79-8	106.508		66	sub			
2278	*trans*-(3-Chloro-1-propenyl) benzene		C_9H_9Cl	21087-29-6	152.620		8.5	106[13]	1.0926^{20}	1.5851^{20}	vs ace, bz, eth, EtOH
2279	Chloropropham		$C_{10}H_{12}ClNO_2$	101-21-3	213.661		41	149[2]	1.18^{30}	1.5388^{20}	
2280	Chloropropylate		$C_{17}H_{16}Cl_2O_3$	5836-10-2	339.213	pow	73				sl H_2O; s os
2281	(3-Chloropropyl)benzene		$C_9H_{11}Cl$	104-52-9	154.636			219.5	1.056^{21}	1.5160^{25}	sl ctc
2282	3-Chloropropyl chloroformate		$C_4H_6Cl_2O_2$	628-11-5	156.996			177	1.2926^{25}	1.4456^{20}	i H_2O
2283	(3-Chloropropyl)trimethoxysilane		$C_6H_{15}ClO_3Si$	2530-87-2	198.720			91	1.077^{25}	1.4183^{25}	
2284	(3-Chloropropyl)trimethylsilane		$C_6H_{15}ClSi$	2344-83-4	150.722			151	0.8789^{20}	1.4319^{20}	
2285	3-Chloro-1-propyne	Propargyl chloride	C_3H_3Cl	624-65-7	74.509		-78	58	1.030^{25}	1.4349^{20}	i H_2O; msc EtOH, eth, bz; s ctc
2286	6-Chloro-1*H*-purine	6-Chloropurine	$C_5H_3ClN_4$	87-42-3	154.558	nd (w)	176 dec				
2287	6-Chloro-3-pyridazinamine		$C_4H_4ClN_3$	5469-69-2	129.548		220				
2288	5-Chloro-2-pyridinamine		$C_5H_5ClN_2$	1072-98-6	128.560	pl	137	127[11]			s H_2O, EtOH; sl DMSO; i peth, lig
2289	2-Chloropyridine		C_5H_4ClN	109-09-1	113.546	oil		170	1.205^{15}	1.5320^{20}	sl H_2O; s EtOH, eth
2290	3-Chloropyridine		C_5H_4ClN	626-60-8	113.546			148; 86[100]		1.5304^{20}	sl H_2O
2291	4-Chloropyridine		C_5H_4ClN	626-61-9	113.546	liq	-43.5	147.5	1.2000^{25}		s H_2O; msc EtOH



1-(4-Chlorophenyl)-1-propanone



3-(3-Chlorophenyl)-2-propynoic acid



Chlorophenylsilane



1-Chloro-4-(phenylsulfonyl)benzene



5-Chloro-1-phenyltetrazole


(2-Chlorophenyl)thiourea


α-Chlorophyll



β-Chlorophyll



Chloropropamide



2-Chloropropanal



1-Chloropropane



2-Chloropropane



3-Chloro-1,2-propanediol



2-Chloro-1,3-propanediol



3-Chloro-1,2-propanediol dinitrate



3-Chloropropanenitrile



2-Chloropropanoic acid


3-Chloropropanoic acid


2-Chloro-1-propanol


3-Chloro-1-propanol


1-Chloro-2-propanol



3-Chloropropanoyl chloride



cis-1-Chloropropene



trans-1-Chloropropene



2-Chloropropene



3-Chloropropene



2-Chloro-2-propenenitrile



2-Chloropropenoic acid



trans-(3-Chloro-1-propenyl)benzene



Chloropropham


Chloropropylate



(3-Chloropropyl)benzene



3-Chloropropyl chloroformate



(3-Chloropropyl)trimethoxysilane



(3-Chloropropyl)trimethylsilane


3-Chloro-1-propyne



6-Chloro-1*H*-purine


6-Chloro-3-pyridazinamine



5-Chloro-2-pyridinamine



2-Chloropyridine



3-Chloropyridine



4-Chloropyridine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2292	2-Chloro-3-pyridinecarboxylic acid		$C_6H_4ClNO_2$	2942-59-8	157.555		>175 dec				
2293	6-Chloro-3-pyridinecarboxylic acid		$C_6H_4ClNO_2$	5326-23-8	157.555		198 dec				
2294	4-Chloropyridine, hydrochloride		$C_5H_5Cl_2N$	7379-35-3	150.006			sub 210			
2295	Chloroquine		$C_{18}H_{26}ClN_3$	54-05-7	319.872		90				
2296	2-Chloroquinoline		C_9H_6ClN	612-62-4	163.604	nd (aq al)	38	266; 153[22]	1.2464[25]	1.6342[25]	i H_2O; vs EtOH, eth; s bz, chl
2297	4-Chloroquinoline		C_9H_6ClN	611-35-8	163.604	cry	34.5	262; 130[15]	1.251[25]		sl H_2O; vs EtOH, eth; s dil HCl
2298	6-Chloroquinoline		C_9H_6ClN	612-57-7	163.604	pr (eth), nd (al)	43.8	263		1.6110[56]	
2299	8-Chloroquinoline		C_9H_6ClN	611-33-6	163.604	liq	-20	288.5	1.2834[14]	1.6408[14]	s H_2O; vs EtOH, eth, ace, bz, chl
2300	5-Chloro-8-quinolinol	Cloxyquin	C_9H_6ClNO	130-16-5	179.603	cry (al)	130				
2301	2-Chlorostyrene		C_8H_7Cl	2039-87-4	138.595	liq	-63.1	188.7	1.1000[20]	1.5649[20]	s EtOH, eth, ace, ctc, HOAc; msc peth
2302	3-Chlorostyrene		C_8H_7Cl	2039-85-2	138.595			63[6]	1.1033[20]	1.5625[20]	i H_2O; s EtOH, eth
2303	4-Chlorostyrene		C_8H_7Cl	1073-67-2	138.595		15.9	192	1.0868[20]	1.5660[20]	i H_2O; s EtOH, eth; msc ace, bz, ctc
2304	*N*-Chlorosuccinimide		$C_4H_4ClNO_2$	128-09-6	133.534	pl (CCl_4)	150		1.65[25]		sl H_2O, EtOH, bz, lig; s ace, HOAc
2305	1-Chlorotetradecane		$C_{14}H_{29}Cl$	2425-54-9	232.833		4.9	296.8	0.8654[20]	1.4474[20]	i H_2O; s EtOH, chl; vs ace, bz; sl ctc
2306	6-Chloro-*N,N,N′,N′*-tetraethyl-1,3,5-triazine-2,4-diamine		$C_{11}H_{20}ClN_5$	580-48-3	257.764	oily liq	27	155[9]	1.0956[20]	1.5320[20]	vs bz, chl, EtOH, lig
2307	1-Chloro-1,1,2,2-tetrafluoroethane		C_2HClF_4	354-25-6	136.476	col gas	-117	-11.7			
2308	1-Chloro-1,2,2,2-tetrafluoroethane		C_2HClF_4	2837-89-0	136.476	col gas		-12			
2309	Chlorothalonil		$C_8Cl_4N_2$	1897-45-6	265.911		250	350	1.7[25]		i H_2O; sl ace, cyhex
2310	Chlorothen	Chloromethapyrilene	$C_{14}H_{18}ClN_3S$	148-65-2	295.831			155[10], 192[5]	1.1751[25]		
2311	Chlorothiazide		$C_7H_6ClN_3O_4S_2$	58-94-6	295.724		350 dec				
2312	2-Chlorothiophene	2-Thienyl chloride	C_4H_3ClS	96-43-5	118.585	liq	-71.9	128.3	1.2863[20]	1.5487[20]	i H_2O; msc EtOH, eth; sl chl
2313	5-Chloro-2-thiophenecarboxaldehyde		C_5H_3ClOS	7283-96-7	146.595			77.5[5]		1.6036[25]	sl chl
2314	2-Chloro-9*H*-thioxanthen-9-one		$C_{13}H_7ClOS$	86-39-5	246.712		153.5				
2315	2-Chlorotoluene		C_7H_7Cl	95-49-8	126.584	liq	-35.8	159.0	1.0825[20]	1.5268[20]	i H_2O; s EtOH, bz; msc eth, ace, chl
2316	3-Chlorotoluene		C_7H_7Cl	108-41-8	126.584	liq	-47.8	161.8	1.075[20]	1.5214[19]	i H_2O; s EtOH, bz, ctc, chl; msc eth
2317	4-Chlorotoluene		C_7H_7Cl	106-43-4	126.584		7.5	162.4	1.0697[20]	1.5150[20]	i H_2O; s EtOH, ctc, chl; msc eth
2318	6-Chloro-1,3,5-triazine-2,4-diamine		$C_3H_4ClN_5$	3397-62-4	145.551		>330				
2319	1-Chloro-2-(trichloromethyl) benzene		$C_7H_4Cl_4$	2136-89-2	229.919		29.4	264.3	1.5187[20]	1.5836[20]	i H_2O; s eth, ace; sl ctc
2320	1-Chloro-4-(trichloromethyl) benzene		$C_7H_4Cl_4$	5216-25-1	229.919			245	1.4463[20]		vs ace, eth
2321	Chlorotriethoxysilane		$C_6H_{15}ClO_3Si$	4667-99-6	198.720	liq	-51	156	1.030[20]	1.3999[20]	vs EtOH
2322	Chlorotriethylplumbane	Lead triethyl chloride	$C_6H_{15}ClPb$	1067-14-7	329.8		123 dec				s H_2O
2323	Chlorotriethylsilane		$C_6H_{15}ClSi$	994-30-9	150.722			144.5	0.8967[20]	1.4314[20]	
2324	1-Chloro-1,1,2-trifluoroethane		$C_2H_2ClF_3$	421-04-5	118.485	vol liq or gas		12			
2325	1-Chloro-1,2,2-trifluoroethane		$C_2H_2ClF_3$	431-07-2	118.485	vol liq or gas		17.3			
2326	2-Chloro-1,1,1-trifluoroethane		$C_2H_2ClF_3$	75-88-7	118.485	col gas	-105.5	6.1	1.389[0]	1.3090[0]	
2327	Chlorotrifluoroethene	Chlorotrifluoroethylene	C_2ClF_3	79-38-9	116.469	col gas	-158.2	-27.8	1.54[-60]	1.38[0]	s bz, chl
2328	Chlorotrifluoromethane	Refrigerant 13	$CClF_3$	75-72-9	104.459	col gas	-181	-81.4			i H_2O
2329	2-Chloro-5-(trifluoromethyl) aniline		$C_7H_5ClF_3N$	121-50-6	195.570			103[25]	1.428[25]	1.4975[20]	
2330	4-Chloro-3-(trifluoromethyl) aniline		$C_7H_5ClF_3N$	320-51-4	195.570		36.5	132[27]			
2331	1-Chloro-2-(trifluoromethyl) benzene	*o*-Chlorobenzotrifluoride	$C_7H_4ClF_3$	88-16-4	180.555	liq	-6	152.2	1.2540[30]	1.4513[25]	s chl
2332	1-Chloro-3-(trifluoromethyl) benzene	*m*-Chlorobenzotrifluoride	$C_7H_4ClF_3$	98-15-7	180.555	liq	-56	137.5	1.3311[25]	1.4438[25]	



2-Chloro-3-pyridinecarboxylic acid



6-Chloro-3-pyridinecarboxylic acid



4-Chloropyridine, hydrochloride



Chloroquine



2-Chloroquinoline



4-Chloroquinoline



6-Chloroquinoline



8-Chloroquinoline



5-Chloro-8-quinolinol



2-Chlorostyrene


3-Chlorostyrene


4-Chlorostyrene



N-Chlorosuccinimide



1-Chlorotetradecane



6-Chloro-*N,N,N',N'*-tetraethyl-1,3,5-triazine-2,4-diamine


1-Chloro-1,1,2,2-tetrafluoroethane



1-Chloro-1,2,2,2-tetrafluoroethane



Chlorothalonil


Chlorothen


Chlorothiazide



2-Chlorothiophene



5-Chloro-2-thiophenecarboxaldehyde



2-Chloro-9*H*-thioxanthen-9-one



2-Chlorotoluene



3-Chlorotoluene


4-Chlorotoluene


6-Chloro-1,3,5-triazine-2,4-diamine


1-Chloro-2-(trichloromethyl)benzene


1-Chloro-4-(trichloromethyl)benzene


Chlorotriethoxysilane


Chlorotriethylplumbane



Chlorotriethylsilane



1-Chloro-1,1,2-trifluoroethane



1-Chloro-1,2,2-trifluoroethane



2-Chloro-1,1,1-trifluoroethane



Chlorotrifluoroethene


Chlorotrifluoromethane



2-Chloro-5-(trifluoromethyl)aniline



4-Chloro-3-(trifluoromethyl)aniline



1-Chloro-2-(trifluoromethyl)benzene


1-Chloro-3-(trifluoromethyl)benzene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2333	1-Chloro-4-(trifluoromethyl) benzene	*p*-Chlorobenzotrifluoride	$C_7H_4ClF_3$	98-56-6	180.555	liq	-33	138.5	1.3340^{25}	1.4431^{30}	
2334	3-Chloro-1,1,1-trifluoropropane		$C_3H_4ClF_3$	460-35-5	132.512	liq	-106.5	45.1	1.3253^{20}	1.3350^{20}	i H_2O
2335	2-Chloro-2,4,4-trimethylpentane		$C_8H_{17}Cl$	6111-88-2	148.674		-26	dec 147; 44^{16}	0.8746^{20}	1.4308^{20}	vs EtOH
2336	Chlorotrimethylstannane		C_3H_9ClSn	1066-45-1	199.266		38.5	148			s H_2O, chl, os
2337	2-Chloro-1,3,5-trinitrobenzene	Picryl chloride	$C_6H_2ClN_3O_6$	88-88-0	247.549	wh nd or pl (chl, al-lig)	83		1.797^{20}		i H_2O; s EtOH, bz; sl eth; vs ace, tol
2338	Chlorotrinitromethane		$CClN_3O_6$	1943-16-4	185.480		2.3	dec 134; 56^{40}	1.6769^{20}	1.4500^{20}	vs eth, EtOH, chl
2339	Chlorotriphenylmethane		$C_{19}H_{15}Cl$	76-83-5	278.775	nd or pr (bz-peth)	113.5	310			i H_2O; sl EtOH; vs eth, bz, chl; s ace
2340	Chlorotriphenylsilane		$C_{18}H_{15}ClSi$	76-86-8	294.851			241^{35}			
2341	Chlorotriphenylstannane	Triphenyltin chloride	$C_{18}H_{15}ClSn$	639-58-7	385.475		103.5				s chl
2342	Chlorotripropylstannane		$C_9H_{21}ClSn$	2279-76-7	283.426		-23.5	123^{13}	1.2678^{28}	1.49102^{28}	s ctc, os
2343	Chlorovinyldimethylsilane		C_4H_9ClSi	1719-58-0	120.653			83.5	0.8744^{20}	1.4141^{20}	
2344	Chloroxuron	*N'*-[4-(4-Chlorophenoxy)phenyl] -*N,N*-dimethylurea	$C_{15}H_{15}ClN_2O_2$	1982-47-4	290.745		151				
2345	Chlorozotocin		$C_9H_{16}ClN_3O_7$	54749-90-5	313.692	cry	147 dec				s H_2O
2346	Chlorphenesin carbamate		$C_{10}H_{12}ClNO_4$	886-74-8	245.660	cry (bz)	90				vs ace, EtOH, diox
2347	Chlorpheniramine		$C_{16}H_{19}ClN_2$	132-22-9	274.788	oily liq		142^{1}			
2348	Chlorpheniramine maleate	Chloroprophenpyridamine	$C_{20}H_{23}ClN_2O_4$	113-92-8	390.861		132.5				
2349	Chlorphentermine	2-(4-Chlorobenzyl)-2-propylamine	$C_{10}H_{14}ClN$	461-78-9	183.678	liq		$231; 101^{2}$			
2350	Chlorpromazine	2-Chloro-*N,N*-dimethyl-10*H*-phenothiazine-10-propanamine	$C_{17}H_{19}ClN_2S$	50-53-3	318.864			$202^{0.8}$			i H_2O; vs EtOH, eth, bz, chl; s dil HCl
2351	Chlorprothixene		$C_{18}H_{18}ClNS$	113-59-7	315.861	pale ye cry	97				i H_2O, EtOH, eth, chl
2352	Chlorpyrifos		$C_9H_{11}Cl_3NO_3PS$	2921-88-2	350.586		42				
2353	Chlorpyrifos-methyl		$C_7H_7Cl_3NO_3PS$	5598-13-0	322.534		43				
2354	Chlorsulfuron		$C_{12}H_{12}ClN_5O_4S$	64902-72-3	357.773		176				
2355	Chlortetracycline		$C_{22}H_{23}ClN_2O_8$	57-62-5	478.879	gold-ye	168.5				i H_2O, eth; sl EtOH, ace, bz; s diox
2356	Chlorthalidone		$C_{14}H_{11}ClN_2O_4S$	77-36-1	338.765	wh pow or cry	225 dec				s alk, EtOH; sl eth
2357	Chlorthion		$C_8H_9ClNO_5PS$	500-28-7	297.653	ye cry	21	$125^{0.1}$	1.437^{20}	1.5661^{20}	i H_2O; vs bz, eth, EtOH
2358	Chlorthiophos		$C_{11}H_{15}Cl_2O_3PS_2$	21923-23-9	361.245			$150^{0.001}$			
2359	Chlortoluron	*N'*-(3-Chloro-4-methylphenyl)-*N,N*-dimethylurea	$C_{10}H_{13}ClN_2O$	15545-48-9	212.675	cry	147				sl H_2O; s os
2360	Cholane		$C_{24}H_{42}$	548-98-1	330.590	pr (al)	90	$190^{0.001}$			
2361	Cholan-24-oic acid	Cholanic acid	$C_{24}H_{40}O_2$	25312-65-6	360.574	nd (al), cry (HOAc)	163.5				s EtOH, chl, HOAc
2362	Cholesta-3,5-diene		$C_{27}H_{44}$	747-90-0	368.638	wh nd (al)	80	260^{13}	0.925^{100}		i H_2O; s EtOH; msc eth, bz, chl; vs lig
2363	Cholesta-5,7-dien-3-ol, (3β)	7-Dehydrocholesterol	$C_{27}H_{44}O$	434-16-2	384.637	pl (+1w), (eth-MeOH)	150.5				i H_2O; sl EtOH; s eth, ace
2364	Cholesta-8,24-dien-3-ol, (3β,5α)		$C_{27}H_{44}O$	128-33-6	384.637	pl (MeOH) ,nd	110	$160^{0.001}$			s ace, chl, MeOH
2365	Cholestane, (5α)	28,29,30-Trinorlanostane	$C_{27}H_{48}$	481-21-0	372.670	sc or pl (eth-al, ace)	80	250^{1}	0.9090^{88}	1.4887^{88}	i H_2O; sl EtOH; vs eth, bz, chl
2366	Cholestane, (5β)	Coprostane	$C_{27}H_{48}$	481-20-9	372.670	orth nd (al, ace)	72		0.9119^{87}	1.4884^{88}	vs eth, chl
2367	Cholestanol	Dihydrocholesterol	$C_{27}H_{48}O$	80-97-7	388.669	sc (al,+1w)	141.5				vs eth, chl
2368	Cholestan-3-ol, (3α,5α)	Epicholestanol	$C_{27}H_{48}O$	516-95-0	388.669	nd (al)	185.5				s chl
2369	Cholest-4-en-3-ol, (3β)	Allocholesterol	$C_{27}H_{46}O$	517-10-2	386.653	nd (eth-MeOH)	132				i H_2O; s EtOH; vs eth, ace, bz, chl
2370	Cholest-5-en-3-ol, (3α)	Epicholesterol	$C_{27}H_{46}O$	474-77-1	386.653	cry (al, chl-MeOH)	141.5				sl EtOH
2371	Cholest-5-en-3-ol (3β), acetate		$C_{29}H_{48}O_2$	604-35-3	428.690	wh nd (ace, al)	115.5				vs bz, eth, chl
2372	Cholest-5-en-3-ol (3β), benzoate		$C_{34}H_{50}O_2$	604-32-0	490.760	wh nd	151.3		0.9413^{200}		i EtOH; s eth, chl
2373	Cholest-5-en-3-ol (3β)-, hexadecanoate		$C_{43}H_{76}O_2$	601-34-3	625.062	wh nd (eth al)	79.3				vs bz, chl
2374	Cholest-5-en-3-ol (3β)-, *cis*-9-octadecenoate		$C_{45}H_{78}O_2$	303-43-5	651.100		46.3				s chl



1-Chloro-4-(trifluoromethyl)benzene



3-Chloro-1,1,1-trifluoropropane



2-Chloro-2,4,4-trimethylpentane



Chlorotrimethylstannane



2-Chloro-1,3,5-trinitrobenzene


Chlorotrinitromethane



Chlorotriphenylmethane



Chlorotriphenylsilane



Chlorotriphenylstannane



Chlorotripropylstannane



Chlorovinyldimethylsilane



Chloroxuron



Chlorozotocin



Chlorphenesin carbamate



Chlorpheniramine



Chlorpheniramine maleate






Chlorphentermine



Chlorpromazine



Chlorprothixene



Chlorpyrifos



Chlorpyrifos-methyl



Chlorsulfuron



Chlortetracycline



Chlorthalidone



Chlorthion



Chlorthiophos



Chlortoluron



Cholane



Cholan-24-oic acid



Cholesta-3,5-diene



Cholesta-5,7-dien-3-ol, (3β)



Cholesta-8,24-dien-3-ol, (3β,5α)



Cholestane, (5α)



Cholestane, (5β)



Cholestanol



Cholestan-3-ol, (3α,5α)



Cholest-4-en-3-ol, (3β)


Cholest-5-en-3-ol, (3α)



Cholest-5-en-3-ol (3β), acetate



Cholest-5-en-3-ol (3β), benzoate



Cholest-5-en-3-ol (3β)-, hexadecanoate



Cholest-5-en-3-ol (3β)-, *cis*-9-octadecenoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2375	Cholest-4-en-3-one		$C_{27}H_{44}O$	601-57-0	384.637	nd or pl (al)	81.5	$245^{0.03}$			
2376	Cholesterol		$C_{27}H_{46}O$	57-88-5	386.653	orth or tcl lf (al) nd (eth)	148.5	dec 360; $233^{0.5}$	1.067^{20}		i H_2O; sl EtOH, ace; s bz, HOAc; vs diox
2377	Cholic acid	3,7,12-Trihydroxycholan-24-oic acid, (3α,5β,7α,12α)	$C_{24}H_{40}O_5$	81-25-4	408.572		198				sl H_2O; s EtOH, ace, alk; vs eth, chl
2378	Choline chloride		$C_5H_{14}ClNO$	67-48-1	139.624	hyg cry	305 dec				vs H_2O, EtOH
2379	Choline chloride dihydrogen phosphate	Phosphorylcholine	$C_5H_{15}ClNO_4P$	107-73-3	219.605	visc liq					
2380	Chorismic acid		$C_{10}H_{10}O_6$	617-12-9	226.182	cry	148				s H_2O
2381	Chromium carbonyl		C_6CrO_6	13007-92-6	220.056	col orth cry	dec 130	sub	1.77		i H_2O, EtOH; s eth, chl
2382	Chromium(II) oxalate		C_2CrO_4	814-90-4	140.015	ye-grn pow (hyd)					i H_2O, EtOH; s dil acid
2383	Chromium(III) 2,4-pentanedioate	Chromium acetylacetonate	$C_{15}H_{21}CrO_6$	21679-31-2	349.320	red mcl cry	208	345	1.34		i H_2O; s bz
2384	Chromotrope 2B		$C_{16}H_9N_3Na_2O_{10}S_2$	548-80-1	513.366	red-br pow	300				s H_2O; i EtOH
2385	Chrysamminic acid	1,8-Dihydroxy-2,4,5,7-tetranitro-9,10-anthracenedione	$C_{14}H_4N_4O_{12}$	517-92-0	420.202	ye pl or lf	exp	dec			vs eth, EtOH
2386	6-Chrysenamine	6-Aminochrysene	$C_{18}H_{13}N$	2642-98-0	243.303	lf (al)	210.5				
2387	Chrysene	Benzo[a]phenanthrene	$C_{18}H_{12}$	218-01-9	228.288	red bl fl or orth pl (bz, HOAc)	255.5	448	1.274^{20}		i H_2O; sl EtOH, eth, ace, bz, CS_2; s tol
2388	Ciafos		$C_9H_{10}NO_3PS$	2636-26-2	243.219	ye to red-ye liq	15	$120^{0.09}$ dec		1.5404^{32}	sl H_2O; vs chl, EtOH, ace, MeOH
2389	Cicutoxin	8,10,12-Heptadecatriene-4,6-diyne-1,14-diol	$C_{17}H_{22}O_2$	505-75-9	258.356	pr (eth/peth)	54				s hot H_2O, EtOH, eth, chl
2390	C.I. Direct Blue 6, tetrasodium salt	Direct Blue 6	$C_{32}H_{20}N_6Na_4O_{14}S_4$	2602-46-2	932.752	dk bronze pow					
2391	Cimetidine		$C_{10}H_{16}N_6S$	51481-61-9	252.339	cry	142				
2392	Cinchonamine		$C_{19}H_{24}N_2O$	482-28-0	296.406	orth nd (al) orth pr (MeOH)	186				i H_2O; vs EtOH, eth; s bz, chl
2393	Cinchonidine		$C_{19}H_{22}N_2O$	485-71-2	294.390	or pl or pr (al)	210.5	sub			i H_2O, bz; s EtOH, chl, py; sl eth
2394	Cinchonine		$C_{19}H_{22}N_2O$	118-10-5	294.390	pr nd (al, eth)	265				
2395	Cinchotoxine		$C_{19}H_{22}N_2O$	69-24-9	294.390	nd or pr (eth)	59				i H_2O; vs EtOH, eth, ace, bz, chl
2396	*trans*-Cinnamaldehyde	3-Phenyl-2-propenal, (*E*)-	C_9H_8O	14371-10-9	132.159	ye liq	-7.5	246	1.0497^{20}	1.6195^{20}	sl H_2O; s EtOH, eth, chl; i lig
2397	Cinnamedrine	α-[1-[Methyl(3-phenylallyl) amino]ethyl]benzenemethanol	$C_{19}H_{23}NO$	90-86-8	281.392		75				
2398	*cis*-Cinnamic acid	3-Phenyl-2-propenoic acid, (*Z*)	$C_9H_8O_2$	102-94-3	148.159	mcl pr (w)	42				vs EtOH, HOAc, lig
2399	*trans*-Cinnamic acid	3-Phenyl-2-propenoic acid, (*E*)	$C_9H_8O_2$	140-10-3	148.159	mcl pr (dil al)	133	300	1.2475^4		i H_2O, lig; vs EtOH; s eth, ace, bz
2400	*trans*-Cinnamyl anthranilate		$C_{16}H_{15}NO_2$	87-29-6	253.296	cry	64				
2401	Cinnamyl cinnamate		$C_{18}H_{16}O_2$	122-69-0	264.319	nd (al)	44		1.1565^4		i H_2O; s EtOH, chl; vs eth
2402	Cinnamyl formate	3-Phenyl-2-propen-1-ol, formate	$C_{10}H_{10}O_2$	104-65-4	162.185		0	252	1.086^{25}		
2403	Cinnoline	1,2-Benzodiazine	$C_8H_6N_2$	253-66-7	130.147	pa ye cry (lig)	38	$114^{0.3}$			vs eth, EtOH
2404	Cinoxate	3-(4-Methoxyphenyl)-2-propenoic acid, 2-ethoxyethyl ester	$C_{14}H_{18}O_4$	104-28-9	250.291	col liq	-25	185^2	1.102^{25}	1.567^{20}	i H_2O; msc EtOH
2405	Cinquasia Red	Quinacridone	$C_{20}H_{12}N_2O_2$	1047-16-1	312.321	red-viol cry	390				i H_2O, os
2406	Ciodrin		$C_{14}H_{19}O_6P$	7700-17-6	314.271			$135^{0.03}$	1.19^{25}		
2407	C.I. Pigment Red 170		$C_{26}H_{22}N_4O_4$	2786-76-7	454.478	red solid					
2408	C.I. Pigment Yellow 1		$C_{17}H_{16}N_4O_4$	2512-29-0	340.334	ye cry	256				
2409	C.I. Pigment Yellow 12		$C_{32}H_{26}Cl_2N_6O_4$	6358-85-6	629.492	ye cry	317				
2410	Cisapride		$C_{23}H_{29}ClFN_3O_4$	81098-60-4	465.945	cry (hp)	132				
2411	Citral	3,7-Dimethyl-2,6-octadienal	$C_{10}H_{16}O$	5392-40-5	152.233			228.3	0.8888^{20}	1.4898^{20}	i H_2O; msc EtOH, eth
2412	β-Citraurin		$C_{30}H_{40}O_2$	650-69-1	432.638	pl (bz-peth), cry (al)	147				i H_2O; vs EtOH, eth, ace, bz; sl lig
2413	Citrazinic acid	1,2-Dihydro-6-hydroxy-2-oxo-4-pyridinecarboxylic acid	$C_6H_5NO_4$	99-11-6	155.109	ye pow	>300 dec				s H_2O, alk; sl HCl



Cholest-4-en-3-one



Cholesterol



Cholic acid



Choline chloride



Choline chloride dihydrogen phosphate



Chorismic acid



Chromium carbonyl



Chromium(II) oxalate



Chromium(III) 2,4-pentanedioate



Chromotrope 2B



Chrysamminic acid



6-Chrysenamine



Chrysene



Ciafos



Cicutoxin



C.I. Direct Blue 6, tetrasodium salt



Cimetidine



Cinchonamine



Cinchonidine



Cinchonine



Cinchotoxine



trans-Cinnamaldehyde



Cinnamedrine



cis-Cinnamic acid



trans-Cinnamic acid



trans-Cinnamyl anthranilate



Cinnamyl cinnamate



Cinnamyl formate



Cinnoline



Cinoxate



Cinquasia Red



Ciodrin



C.I. Pigment Red 170



C.I. Pigment Yellow 1


C.I. Pigment Yellow 12



Cisapride



Citral



β-Citraurin



Citrazinic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2414	Citric acid	2-Hydroxy-1,2,3-propanetricarboxylic acid	$C_6H_8O_7$	77-92-9	192.124	orth (w+1)	153	dec	1.665^{20}		vs H_2O, EtOH; s eth, AcOEt; i bz, chl
2415	Citric acid monohydrate	2-Hydroxy-1,2,3-propanetricarboxylic acid, monohydrate	$C_6H_{10}O_8$	5949-29-1	210.138	cry (w)	135		1.542		vs H_2O; vs EtOH, eth
2416	Citrinin	Antimycin	$C_{13}H_{14}O_5$	518-75-2	250.247	ye nd (MeOH)	178 dec				i H_2O; sl EtOH, eth; s ace, bz
2417	Citrulline	*N*5-(Aminocarbonyl)-*L*-ornithine	$C_6H_{13}N_3O_3$	372-75-8	175.185	pr (aq MeOH)	222				s H_2O; i EtOH, MeOH
2418	Citrus Red 2		$C_{18}H_{16}N_2O_3$	6358-53-8	308.331	cry	156				sl H_2O; s EtOH
2419	C.I. Vat Blue 6	7,16-Dichloro-6,15-dihydro-5,9,14,18-anthrazinetetrone	$C_{28}H_{12}Cl_2N_2O_4$	130-20-1	511.312	viol-bl pow					
2420	C.I. Vat Yellow 4	Anthanthrone	$C_{24}H_{12}O_2$	128-66-5	332.351	ye cry					
2421	Clayton Yellow	Thiazol Yellow G	$C_{28}H_{19}N_5Na_2O_6S_4$	1829-00-1	695.721	ye-br pow					s H_2O, EtOH, H_2SO_4
2422	Clemastine fumarate		$C_{25}H_{30}ClNO_5$	14976-57-9	459.963		181				
2423	Clindamycin		$C_{18}H_{33}ClN_2O_5S$	18323-44-9	424.983	ye amorp solid					
2424	Cloconazole		$C_{18}H_{15}Cl_3N_2O$	77175-51-0	310.777		73				s EtOAc
2425	Clofentezine	3,6-Bis(2-chlorophenyl)-1,2,4,5-tetrazine	$C_{14}H_8Cl_2N_4$	74115-24-5	303.147		182				
2426	Clofibrate		$C_{12}H_{15}ClO_3$	637-07-0	242.698			149^{20}			
2427	Cloforex		$C_{13}H_{18}ClNO_2$	14261-75-7	255.741	cry	52.8	$89^{0.005}$			
2428	Clomazone	2-(2-Chlorobenzyl)-4,4-dimethyl-1,2-oxazolidin-3-one	$C_{12}H_{14}ClNO_2$	81777-89-1	239.698				1.192^{20}		
2429	Clomiphene		$C_{26}H_{28}ClNO$	911-45-5	405.959		117				
2430	Clonazepam		$C_{15}H_{10}ClN_3O_3$	1622-61-3	315.711	wh cry	237.5				i H_2O, bz; sl ace, MeOH, chl
2431	Clonidine		$C_9H_9Cl_2N_3$	4205-90-7	230.093	cry	137				
2432	Clopidol		$C_7H_7Cl_2NO$	2971-90-6	192.043	pow	>320				i H_2O
2433	Clopyralid	3,6-Dichloro-2-pyridinecarboxylic acid	$C_6H_3Cl_2NO_2$	1702-17-6	192.000		151				
2434	Clorophene		$C_{13}H_{11}ClO$	120-32-1	218.678		48.5	$161^{3.5}$	1.185^{58}		s ctc, CS_2
2435	Clotrimazole		$C_{22}H_{17}ClN_2$	23593-75-1	344.836	cry	148				sl H_2O, bz; s ace, chl, AcOEt, DMF
2436	Clozapine	Clozaril	$C_{18}H_{19}ClN_4$	5786-21-0	326.824	ye cry	183.5				
2437	Cobalt carbonyl	Dicobalt octacarbonyl	$C_8Co_2O_8$	10210-68-1	341.947	oran cry	51 dec		1.78		i H_2O; s EtOH, eth, CS_2
2438	Cobalt hydrocarbonyl	Tetracarbonylhydrocobalt	C_4HCoO_4	16842-03-8	171.982	ye liq or gas	≈-30	10			s os
2439	Cobalt(III) 2,4-pentanedioate	Cobalt(III) acetylacetonate	$C_{15}H_{21}CoO_6$	21679-46-9	356.257		240				
2440	Cocaine		$C_{17}H_{21}NO_4$	50-36-2	303.354	mcl pr (al)	98	$187^{0.1}$		1.5022^{98}	sl H_2O; vs EtOH, eth, bz, py; s CS_2
2441	Coclaurine		$C_{17}H_{19}NO_3$	486-39-5	285.338	pl (al)	220.5				
2442	Codamine		$C_{20}H_{25}NO_4$	21040-59-5	343.418	pr (bz, eth)	127				vs eth, EtOH, chl
2443	Codeine		$C_{18}H_{21}NO_3$	76-57-3	299.365	orth cry (w, dil al, eth)	157.5	250^{22}, $140^{1.5}$	1.32^{25}		s H_2O, eth, bz, chl, tol; vs EtOH; i peth
2444	Codeine phosphate		$C_{18}H_{24}NO_7P$	52-28-8	397.361	lf or pr (dil al)	227 dec				vs EtOH, chl
2445	Coenzyme A		$C_{21}H_{36}N_7O_{16}P_3S$	85-61-0	767.535	pow; unstab in air					s H_2O
2446	Coenzyme I	Nicotinamide adenine dinucleotide	$C_{21}H_{27}N_7O_{14}P_2$	53-84-9	663.425	hyg pow					s H_2O
2447	Coenzyme II	Nicotinamide adenine dinucleotide phosphate	$C_{21}H_{28}N_7O_{17}P_3$	53-59-8	743.405	gray-wh pow					s H_2O
2448	Colchiceine		$C_{21}H_{23}NO_6$	477-27-0	385.411	pa ye nd (diox)	178.5		1.24^{25}		sl H_2O; vs EtOH, chl; i eth, bz
2449	Colchicine		$C_{22}H_{25}NO_6$	64-86-8	399.437	ye pl (w + 1/2) ye cry (bz)	156				vs H_2O, EtOH
2450	Colistin A		$C_{53}H_{100}N_{16}O_{13}$	7722-44-3	1169.47	amorp pow					sl H_2O, EtOH, hx; s acids, MeOH
2451	Collinomycin		$C_{27}H_{20}O_{12}$	27267-69-2	536.441	oran pr (chl-MeOH)	281				vs ace, diox, chl
2452	Columbin		$C_{20}H_{22}O_6$	546-97-4	358.385	nd (MeOH)	195.5				i H_2O; sl ace, AcOEt, MeOH; s chl
2453	Conessine		$C_{24}H_{40}N_2$	546-06-5	356.588	lf or pl (ace)	125.5	$166^{0.1}$			sl H_2O; s chl, HOAc



Citric acid



Citric acid monohydrate



Citrinin



Citrulline



Citrus Red 2



C.I. Vat Blue 6



C.I. Vat Yellow 4



Clayton Yellow



Clemastine fumarate






Clindamycin



Cloconazole



Clofentezine



Clofibrate



Cloforex



Clomazone



Clomiphene



Clonazepam



Clonidine



Clopidol



Clopyralid



Clorophene



Clotrimazole



Clozapine



Cobalt carbonyl



Cobalt hydrocarbonyl



Cobalt(III) 2,4-pentanedioate



Cocaine



Coclaurine



Codamine



Codeine



Codeine phosphate



Coenzyme A



Coenzyme I



Coenzyme II


Colchiceine



Colchicine



Collinomycin



Columbin



Conessine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2454	Congo Red		$C_{32}H_{22}N_6Na_2O_6S_2$	573-58-0	696.663	pow	>360				sl H_2O; s EtOH; i eth
2455	Conhydrine		$C_8H_{17}NO$	3238-62-8	143.227	nd (peth)	121	226			sl H_2O; vs bz, eth, EtOH
2456	Conhydrine, (+)	2-(α-Hydroxypropyl)piperidine	$C_8H_{17}NO$	495-20-5	143.227	lf (eth)	121	226			sl H_2O; vs eth, EtOH, chl
2457	Coniferin		$C_{16}H_{22}O_8$	531-29-3	342.341	nd (w+2)	186				s H_2O, py; sl EtOH; i eth
2458	Conquinamine		$C_{19}H_{24}N_2O_2$	464-86-8	312.406	ye tetr	123				sl H_2O; s EtOH, eth, chl
2459	Convallatoxin		$C_{29}H_{42}O_{10}$	508-75-8	550.637	pr (eth/ MeOH)	238				s EtOH, ace; sl chl; i eth
2460	Copaene		$C_{15}H_{24}$	3856-25-5	204.352			248.5	0.8996^{20}	1.4894^{20}	i H_2O; s eth, ace, HOAc, lig
2461	Copper(II) ethylacetoacetate	Bis(ethylacetoacetato)copper	$C_{12}H_{18}CuO_6$	14284-06-1	321.813	grn cry (EtOH)	192				s EtOH, chl
2462	Copper(II) gluconate	Cupric gluconate	$C_{12}H_{22}CuO_{14}$	527-09-3	453.841	bl-grn cry	156				sl EtOH; i os
2463	Copper(II) 2,4-pentanedioate	Copper(II) acetylacetonate	$C_{10}H_{14}CuO_4$	13395-16-9	261.762	bl pow	284 dec	sub			sl H_2O; s chl
2464	Copper phthalocyanine	Pigment Blue 15	$C_{32}H_{16}CuN_8$	147-14-8	576.069	bl-purp cry					i H_2O, EtOH; s conc H2SO4
2465	Coronene		$C_{24}H_{12}$	191-07-1	300.352	ye nd (bz)	437.4	525	1.371^{25}		i H_2O, con sulf; sl bz
2466	Corticosterone		$C_{21}H_{30}O_4$	50-22-6	346.461	nd (al, pl) (ace)	181				i H_2O; s EtOH, eth, ace
2467	Corybulbine		$C_{21}H_{25}NO_4$	518-77-4	355.429	nd (al)	237.5				i H_2O; sl EtOH, eth; s ace, bz, HCl
2468	Corycavamine		$C_{21}H_{21}NO_5$	521-85-7	367.396	pr (eth, al)	149				vs EtOH, chl
2469	Corydaline		$C_{22}H_{27}NO_4$	518-69-4	369.454	pr (al)	136				vs bz, eth, EtOH, chl
2470	Corydine		$C_{20}H_{23}NO_4$	476-69-7	341.402	tetr pr (eth)	149				vs eth, EtOH, chl
2471	Corynantheine		$C_{22}H_{26}N_2O_3$	18904-54-6	366.452		165.5				vs EtOH
2472	Cotarnine		$C_{12}H_{15}NO_4$	82-54-2	237.252	nd (bz), cry (eth)	132 dec				sl H_2O; s EtOH, eth, bz, chl, NH_4OH
2473	Coumaphos		$C_{14}H_{16}ClO_5PS$	56-72-4	362.766		93		1.474		
2474	Coumestrol	3,9-Dihydroxy-6*H*-benzofuro[3,2-c][1] benzopyran-6-one	$C_{15}H_8O_5$	479-13-0	268.222	cry rods	385 dec				i H_2O; sl EtOH, ace; i eth
2475	Creatine		$C_4H_9N_3O_2$	57-00-1	131.133	mcl pr (w+1)	303 dec		1.33^{25}		s H_2O; sl EtOH; i eth
2476	Creatinine		$C_4H_7N_3O$	60-27-5	113.118	orth pr (w+2) lf (w)	300 dec				s H_2O; sl EtOH; i eth, ace, chl
2477	*o*-Cresol	2-Methylphenol	C_7H_8O	95-48-7	108.138		31.03	191.04	1.0327^{35}	1.5386^{35}	s H_2O; vs EtOH, eth; msc ace, bz, ctc
2478	*m*-Cresol	3-Methylphenol	C_7H_8O	108-39-4	108.138		12.24	202.27	1.0339^{20}	1.5401^{20}	sl H_2O; msc EtOH, eth, ace, bz, ctc
2479	*p*-Cresol	4-Methylphenol	C_7H_8O	106-44-5	108.138	pr	34.77	201.98	1.0185^{40}	1.5312^{20}	sl H_2O; msc EtOH, eth, ace, bz, ctc
2480	*o*-Cresolphthalein		$C_{22}H_{18}O_4$	596-27-0	346.376	cry (al)	223				vs EtOH
2481	*o*-Cresolphthalein complexone	Metalphthalein	$C_{32}H_{32}N_2O_{12}$	2411-89-4	636.602	ye cry pow	186				i H_2O; s EtOH, ace, alk
2482	Cresol Red	*o*-Cresolsulfonphthalein	$C_{21}H_{18}O_5S$	1733-12-6	382.430	red-br cry pow	>300				vs H_2O, EtOH
2483	*p*-Cresyl diphenyl phosphate		$C_{19}H_{17}O_4P$	78-31-9	340.309	col liq	-40		1.208^{25}		i H_2O; s os
2484	Crimidine		$C_7H_{10}ClN_3$	535-89-7	171.627	br wax	87	143^{4}			vs EtOH
2485	Cromolyn	Cromoglicic acid	$C_{23}H_{16}O_{11}$	16110-51-3	468.366	col cry	241 dec				
2486	Crufomate		$C_{12}H_{19}ClNO_3P$	299-86-5	291.711		60	118$^{0.01}$			
2487	Cryptopine	Cryptocavine	$C_{21}H_{23}NO_5$	482-74-6	369.412	pr or pl (bz) nd (chl-MeOH)	223		1.315^{20}		i H_2O; sl EtOH, eth, bz; s chl, HOAc
2488	Crystal Violet	Gentian violet	$C_{25}H_{30}ClN_3$	548-62-9	407.979	grn pow	215 dec				vs H_2O, chl
2489	Cubebin		$C_{20}H_{20}O_6$	18423-69-3	356.369	nd (al, bz)	131.5				vs eth, EtOH, chl
2490	Cucurbitacin B		$C_{32}H_{46}O_8$	6199-67-3	558.702	cry (EtOH)	181				
2491	Cucurbitacin C		$C_{32}H_{48}O_8$	5988-76-1	560.718	cry (AcOEt)	207.5				
2492	Cupferron		$C_6H_9N_3O_2$	135-20-6	155.154		163.5				sl DMSO
2493	Cupreine		$C_{19}H_{22}N_2O_2$	524-63-0	310.390	pr (eth)	202				vs EtOH
2494	Curan-17-ol, (16α)	Geissoschizoline	$C_{19}H_{26}N_2O$	18397-07-4	298.421	pa ye amor pow	135 dec				i H_2O; vs EtOH, eth, chl



Congo Red



Conhydrine



Conhydrine, (+)



Coniferin



Conquinamine



Convallatoxin



Copaene



Copper(II) ethylacetoacetate



Copper(II) gluconate



Copper(II) 2,4-pentanedioate



Copper phthalocyanine



Coronene



Corticosterone



Corybulbine



Corycavamine



Corydaline



Corydine



Corynantheine



Cotarnine



Coumaphos



Coumestrol



Creatine



Creatinine



o-Cresol



m-Cresol



p-Cresol



o-Cresolphthalein



o-Cresolphthalein complexone



Cresol Red



p-Cresyl diphenyl phosphate



Crimidine



Cromolyn



Crufomate



Cryptopine



Crystal Violet



Cubebin


Cucurbitacin B



Cucurbitacin C



Cupferron



Cupreine



Curan-17-ol, (16α)


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2495	Curcumin	Turmeric	$C_{21}H_{20}O_6$	458-37-7	368.380	oran ye pr, orth pr (MeOH)	183				vs EtOH, HOAc
2496	Curine		$C_{36}H_{38}N_2O_6$	436-05-5	594.696	pr, nd (chl-MeOH)	221				vs ace, bz, py
2497	Cuscohygrine		$C_{13}H_{24}N_2O$	454-14-8	224.342	oil		169^{23}, 122^{2}	0.9733^{20}	1.4832^{20}	vs H_2O, bz, eth, EtOH
2498	Cusparine	2-[2-(1,3-Benzodioxol-5-yl) ethyl]-4-methoxyquinoline	$C_{19}H_{17}NO_3$	529-92-0	307.343	(α) wh or ye nd (peth); (β) amber pr	92(α form); 111(β form)				i H_2O; vs ace, bz, eth, EtOH
2499	Cyamemazine		$C_{19}H_{21}N_3S$	3546-03-0	323.455	ye pow	92	212$^{0.25}$			i H_2O; s EtOH
2500	Cyanamide	Cyanogenamide	CH_2N_2	420-04-2	42.040	nd	45.56	140^{19}	1.282^{20}	1.4418^{48}	vs H_2O, EtOH; s eth, ace, bz; sl CS_2
2501	Cyanazine		$C_9H_{13}ClN_6$	21725-46-2	240.692		168				
2502	Cyanic acid	Hydrogen cyanate	CHNO	420-05-3	43.025	unstab liq or gas	-86	23	1.140^{20}		vs H_2O, bz, eth, chl
2503	2-Cyanoacetamide		$C_3H_4N_2O$	107-91-5	84.076	pl (w)	121.5				vs H_2O
2504	Cyanoacetic acid		$C_3H_3NO_2$	372-09-8	85.062		66	dec 160; 108^{15}			s H_2O, EtOH, eth; sl chl, HOAc
2505	Cyanoacetohydrazide	Cyacetacide	$C_3H_5N_3O$	140-87-4	99.091	pr (al)	114.5				vs H_2O, EtOH
2506	Cyanoacetylene		C_3HN	1070-71-9	51.047		5	42.5	0.8167^{17}	1.3868^{25}	sl H_2O; s EtOH
2507	3-Cyanobenzoic acid		$C_8H_5NO_2$	1877-72-1	147.132	nd (w)	219	sub			sl H_2O; s EtOH, eth
2508	4-Cyanobenzoic acid		$C_8H_5NO_2$	619-65-8	147.132		219				s H_2O, EtOH, eth, HOAc; sl tfa
2509	4-Cyanobutanoic acid		$C_5H_7NO_2$	39201-33-7	113.116	hyg cry	45				s H_2O, EtOH, eth, bz
2510	2-Cyanoethyl acrylate		$C_6H_7NO_2$	106-71-8	125.126			108^{12}	1.062^{20}		
2511	Cyanofenphos		$C_{15}H_{14}NO_2PS$	13067-93-1	303.317		83			1.5839^{25}	sl H_2O
2512	Cyanogen		C_2N_2	460-19-5	52.034	col gas	-27.83	-21.1	0.9537^{-21}		s H_2O, EtOH, eth
2513	Cyanogen bromide	Bromine cyanide	CBrN	506-68-3	105.922	nd	52	61.5	2.015^{20}		s H_2O, EtOH, eth
2514	Cyanogen chloride	Chlorine cyanide	CClN	506-77-4	61.471	col vol liq or gas	-6.5	13	1.186^{20}		s H_2O, EtOH; vs eth
2515	Cyanogen fluoride	Fluorine cyanide	CFN	1495-50-7	45.016	col gas	-82	-46			
2516	Cyanogen iodide	Iodine cyanide	CIN	506-78-5	152.922	nd (al, eth)	146.7	sub	2.84^{18}		vs eth, EtOH
2517	Cyanoguanidine	Dicyanodiamide	$C_2H_4N_4$	461-58-5	84.080		211		1.404^{14}		s H_2O, EtOH, ace; i eth, bz, chl
2518	Cyanomethylmercury	Methylmercurynitrile	C_2H_3HgN	2597-97-9	241.64	cry (chl)	92	subl			vs H_2O, EtOH, bz; s eth
2519	(4-Cyanophenoxy)acetic acid		$C_9H_7NO_3$	1878-82-6	177.157	cry (w)	178				
2520	2-Cyano-*N*-phenylacetamide		$C_9H_8N_2O$	621-03-4	160.172	nd (al)	199.5				
2521	4-Cyanothiazole		$C_4H_2N_2S$	1452-15-9	110.137	nd	58				
2522	Cyanuric acid	1,3,5-Triazine-2,4,6(1*H*,3*H*,5*H*)-trione	$C_3H_3N_3O_3$	108-80-5	129.074	wh cry	>330	sub	1.75^{25}		sl hot H_2O, ace, bz, EtOH; s conc HCl
2523	Cyanuric fluoride	2,4,6-Trifluoro-1,3,5-triazine	$C_3F_3N_3$	675-14-9	135.047			72.8			
2524	Cycasin		$C_8H_{16}N_2O_7$	14901-08-7	252.222	nd (ace aq)	154 dec				
2525	Cyclandelate		$C_{17}H_{24}O_3$	456-59-7	276.371		52	193^{14}			i H_2O
2526	Cyclizine		$C_{18}H_{22}N_2$	82-92-8	266.381	cry (peth)	106				i H_2O; s chl; sl EtOH
2527	Cycloate	Carbamothioic acid, cyclohexylethyl-, *S*-ethyl ester	$C_{11}H_{21}NOS$	1134-23-2	215.356		11.5	145^{10}	1.0156^{30}		
2528	Cyclobarbital		$C_{12}H_{16}N_2O_3$	52-31-3	236.266	lf (w)	173				i H_2O; vs EtOH; s eth, dil alk; sl HOAc
2529	Cyclobutanamine	Aminocyclobutane	C_4H_9N	2516-34-9	71.121			82	0.8328^{20}	1.4363^{19}	
2530	Cyclobutane	Tetramethylene	C_4H_8	287-23-0	56.107	vol liq or gas	-90.7	12.6	0.7038^{0}	1.375^{20}	i H_2O; vs EtOH, ace; msc eth; s bz
2531	Cyclobutanecarbonitrile	Cyanocyclobutane	C_5H_7N	4426-11-3	81.117			149.6			
2532	Cyclobutanecarboxylic acid		$C_5H_8O_2$	3721-95-7	100.117	liq	-1.0	190; 74^{2}	1.0599^{20}	1.4400^{20}	sl H_2O; msc EtOH, eth
2533	1,1-Cyclobutanedicarboxylic acid		$C_6H_8O_4$	5445-51-2	144.126	pr (w, eth)	158.0				vs H_2O; s EtOH, eth, bz; sl lig
2534	Cyclobutanol	Hydroxycyclobutane	C_4H_8O	2919-23-5	72.106			124	0.9218^{15}	1.4371^{20}	
2535	Cyclobutanone		C_4H_6O	1191-95-3	70.090	liq	-50.9	99	0.9547^{0}	1.4215^{20}	s H_2O, eth, bz, chl, tol; vs EtOH; i peth


Curcumin



Curine


Cuscohygrine



Cusparine



Cyamemazine



Cyanamide


Cyanazine



Cyanic acid



2-Cyanoacetamide



Cyanoacetic acid



Cyanoacetohydrazide


Cyanoacetylene


3-Cyanobenzoic acid


4-Cyanobenzoic acid



4-Cyanobutanoic acid


2-Cyanoethyl acrylate


Cyanofenphos


Cyanogen


Cyanogen bromide



Cyanogen chloride


Cyanogen fluoride


Cyanogen iodide



Cyanoguanidine



Cyanomethylmercury



(4-Cyanophenoxy)acetic acid



2-Cyano-*N*-phenylacetamide



4-Cyanothiazole



Cyanuric acid



Cyanuric fluoride


Cycasin


Cyclandelate



Cyclizine



Cycloate



Cyclobarbital


Cyclobutanamine


Cyclobutane


Cyclobutanecarbonitrile


Cyclobutanecarboxylic acid



1,1-Cyclobutanedicarboxylic acid



Cyclobutanol



Cyclobutanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2536	Cyclobutene		C_4H_6	822-35-5	54.091	col gas		2	0.733^{0}		vs ace; s bz, peth
2537	Cyclochlorotine		$C_{24}H_{31}Cl_2N_5O_7$	12663-46-6	572.439	nd (MeOH)	255 dec				
2538	Cyclodecane		$C_{10}H_{20}$	293-96-9	140.266		10	202	0.8538^{25}	1.4716^{20}	
2539	1,2-Cyclodecanedione	Sebacil	$C_{10}H_{16}O_2$	96-01-5	168.233		40.5	104^{10}			
2540	Cyclodecanol		$C_{10}H_{20}O$	1502-05-2	156.265		40.5	125^{12}	0.9606^{20}	1.4926^{20}	s EtOH
2541	Cyclodecanone		$C_{10}H_{18}O$	1502-06-3	154.249	amor pow	28	106^{13}	0.9654^{20}	1.4806^{20}	vs bz, eth, chl
2542	α-Cyclodextrin	Cyclomaltohexaose	$C_{36}H_{60}O_{30}$	10016-20-3	972.843	hx pl or nd					vs cold H_2O; i hot H_2O
2543	β-Cyclodextrin	Cyclomaltoheptaose	$C_{42}H_{70}O_{35}$	7585-39-9	1134.984	mcl cry (w)	260 dec				
2544	γ-Cyclodextrin	Cyclomaltooctaose	$C_{48}H_{80}O_{40}$	17465-86-0	1297.125	sq pl or rods					
2545	Cyclododecane		$C_{12}H_{24}$	294-62-2	168.319	nd (al)	60.4	247	0.82^{80}		
2546	Cyclododecanol		$C_{12}H_{24}O$	1724-39-6	184.318			286			
2547	Cyclododecanone		$C_{12}H_{22}O$	830-13-7	182.302		59	127^{12}	0.9059^{66}	1.4571^{60}	
2548	1,5,9-Cyclododecatriene	CDT	$C_{12}H_{18}$	4904-61-4	162.271	liq	-17	240	0.84^{100}		
2549	*cis*-Cyclododecene		$C_{12}H_{22}$	1129-89-1	166.303			133^{35}, 71^{2}		1.4840^{20}	vs bz, chl
2550	*trans*-Cyclododecene		$C_{12}H_{22}$	1486-75-5	166.303			113^{17}		1.4850^{20}	vs bz, chl
2551	*cis*-9-Cycloheptadecen-1-one	Civetone	$C_{17}H_{30}O$	542-46-1	250.419		32.5	343; 159^{2}			
2552	1,3-Cycloheptadiene		C_7H_{10}	4054-38-0	94.154	liq	-110.4	120.5	0.868^{25}	1.4978^{20}	
2553	Cycloheptanamine		$C_7H_{15}N$	5452-35-7	113.201			54^{11}		1.4724^{20}	
2554	Cycloheptane		C_7H_{14}	291-64-5	98.186	liq	-8.46	118.4	0.8098^{20}	1.4436^{20}	i H_2O; vs EtOH, eth; s bz, chl
2555	1,2-Cycloheptanedione		$C_7H_{10}O_2$	3008-39-7	126.153		-40	108^{17}	1.0583^{22}	1.4689^{22}	s EtOH
2556	Cycloheptanol		$C_7H_{14}O$	502-41-0	114.185		7.2	185	0.9554^{20}	1.40705^{20}	sl H_2O; vs EtOH, eth
2557	Cycloheptanone	Suberone	$C_7H_{12}O$	502-42-1	112.169			178.5	0.9508^{20}	1.4608^{20}	i H_2O; vs EtOH, eth
2558	1,3,5-Cycloheptatriene	Tropilidene	C_7H_8	544-25-2	92.139	liq; cub cry (-80°C)	-79.5	117; 60.5^{122}	0.8875^{19}	1.5343^{20}	i H_2O; s EtOH, eth; vs bz, chl
2559	2,4,6-Cycloheptatrien-1-one		C_7H_6O	539-80-0	106.122		-7	113^{15}, 84^{6}	1.095^{22}	1.6172^{22}	vs bz, chl
2560	Cycloheptene		C_7H_{12}	628-92-2	96.170	liq	-56	115	0.8228^{20}	1.4552^{20}	i H_2O; s EtOH, eth, bz, chl; sl ctc
2561	1,3-Cyclohexadiene		C_6H_8	592-57-4	80.128	liq	-89	80.5	0.8405^{20}	1.4755^{20}	i H_2O; s EtOH, bz, chl, peth; vs eth
2562	1,4-Cyclohexadiene	1,4-Dihydrobenzene	C_6H_8	628-41-1	80.128	liq	-49.2	85.5	0.8471^{20}	1.4725^{20}	i H_2O; msc EtOH, eth; s bz, chl, peth
2563	3,5-Cyclohexadiene-1,2-dione		$C_6H_4O_2$	583-63-1	108.095	red pl or pr	≈65 dec				s eth, ace, bz; i peth
2564	2,5-Cyclohexadiene-1,4-dione, dioxime		$C_6H_6N_2O_2$	105-11-3	138.124	pa ye nd (w)	240 dec				s H_2O
2565	Cyclohexane	Hexahydrobenzene	C_6H_{12}	110-82-7	84.159		6.59	80.73	0.7739^{25}	1.4235^{25}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
2566	Cyclohexaneacetic acid		$C_8H_{14}O_2$	5292-21-7	142.196	nd (HCO_2H)	33	245	1.0423^{18}	1.4775^{20}	sl H_2O; s eth, ace
2567	Cyclohexanecarbonitrile	Cyclohexyl cyanide	$C_7H_{11}N$	766-05-2	109.169	liq	11	184; 76^{16}	0.919	1.4505^{20}	
2568	Cyclohexanecarbonyl chloride		$C_7H_{11}ClO$	2719-27-9	146.614			180	1.0962^{15}	1.4711^{29}	
2569	Cyclohexanecarboxaldehyde		$C_7H_{12}O$	2043-61-0	112.169			159.3	0.9035^{20}	1.4496^{20}	s H_2O, eth
2570	Cyclohexanecarboxylic acid	Hexahydrobenzoic acid	$C_7H_{12}O_2$	98-89-5	128.169	mcl pr	31.5	232.5	1.0334^{22}	1.4530^{20}	sl H_2O, ctc; vs EtOH, bz, chl
2571	*cis*-1,2-Cyclohexanediamine	*cis*-1,2-Diaminocyclohexane	$C_6H_{14}N_2$	1436-59-5	114.188	liq		40^{2}	0.952^{20}	1.4951^{20}	
2572	*trans*-1,2-Cyclohexanediamine	*trans*-1,2-Diaminocyclohexane	$C_6H_{14}N_2$	1121-22-8	114.188		14.8	80^{15}, 41^{2}	0.951^{20}		
2573	*trans*-1,4-Cyclohexanedicarboxylic acid		$C_8H_{12}O_4$	619-82-9	172.179	pr (w)	312.5	sub 300			sl H_2O, eth; vs EtOH; s ace; i chl
2574	1,3-Cyclohexanedimethanamine		$C_8H_{18}N_2$	2579-20-6	142.242		<-70	220	0.945^{20}		vs H_2O, eth, EtOH
2575	1,4-Cyclohexanedimethanol		$C_8H_{16}O_2$	105-08-8	144.212		43	283; 167^{10}			
2576	*cis*-1,2-Cyclohexanediol		$C_6H_{12}O_2$	1792-81-0	116.158		100	120^{15}	1.0297^{101}		s EtOH, ace, bz; sl chl
2577	*trans*-1,4-Cyclohexanediol		$C_6H_{12}O_2$	6995-79-5	116.158	mcl pr (ace)	143		1.18^{20}		s H_2O, EtOH, MeOH; i eth; sl ace
2578	1,2-Cyclohexanedione	1,2-Dioxocyclohexane	$C_6H_8O_2$	765-87-7	112.127	cry (peth)	40	194	1.1187^{21}	1.4995^{20}	s H_2O, EtOH, eth, bz
2579	1,3-Cyclohexanedione	Dihydroresorcinol	$C_6H_8O_2$	504-02-9	112.127	pr (bz)	105.5		1.0861^{91}	1.4576^{102}	s H_2O, EtOH, ace, chl; sl eth, bz
2580	1,4-Cyclohexanedione	Tetrahydroquinone	$C_6H_8O_2$	637-88-7	112.127	mcl pl (w), nd (peth)	78	132^{20}	1.0861^{91}		s H_2O, EtOH, eth, ace, bz, chl



Cyclobutene



Cyclochlorotine



Cyclodecane



1,2-Cyclodecanedione



Cyclodecanol



Cyclodecanone



α-Cyclodextrin



β-Cyclodextrin



γ-Cyclodextrin



Cyclododecane



Cyclododecanol


Cyclododecanone



1,5,9-Cyclododecatriene


cis-Cyclododecene



trans-Cyclododecene



cis-9-Cycloheptadecen-1-one



1,3-Cycloheptadiene


Cycloheptanamine



Cycloheptane


1,2-Cycloheptanedione


Cycloheptanol


Cycloheptanone



1,3,5-Cycloheptatriene



2,4,6-Cycloheptatrien-1-one


Cycloheptene



1,3-Cyclohexadiene



1,4-Cyclohexadiene



3,5-Cyclohexadiene-1,2-dione



2,5-Cyclohexadiene-1,4-dione, dioxime



Cyclohexane



Cyclohexaneacetic acid



Cyclohexanecarbonitrile



Cyclohexanecarbonyl chloride



Cyclohexanecarboxaldehyde



Cyclohexanecarboxylic acid



cis-1,2-Cyclohexanediamine



trans-1,2-Cyclohexanediamine



trans-1,4-Cyclohexanedicarboxylic acid



1,3-Cyclohexanedimethanamine



1,4-Cyclohexanedimethanol


cis-1,2-Cyclohexanediol



trans-1,4-Cyclohexanediol



1,2-Cyclohexanedione



1,3-Cyclohexanedione



1,4-Cyclohexanedione


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2581	1,2-Cyclohexanedione dioxime	Nioxime	$C_6H_{10}N_2O_2$	492-99-9	142.155	nd (w, HOAc)	192				s H_2O, ace, chl; sl tfa
2582	Cyclohexaneethanol		$C_8H_{16}O$	4442-79-9	128.212			208	0.9229^{20}	1.4641^{20}	s EtOH, eth, bz
2583	Cyclohexanemethanamine		$C_7H_{15}N$	3218-02-8	113.201			160	0.87^{25}	1.4630^{20}	
2584	Cyclohexanemethanol	Cyclohexylcarbinol	$C_7H_{14}O$	100-49-2	114.185	liq	-43	183	0.9297^{20}	1.4644^{20}	vs eth, EtOH
2585	Cyclohexanepropanoic acid		$C_9H_{16}O_2$	701-97-3	156.222		16	276.5	0.912^{25}	1.4638^{20}	s H_2O, eth; sl ctc
2586	Cyclohexanethiol	Cyclohexyl mercaptan	$C_6H_{12}S$	1569-69-3	116.224			158.8	0.9782^{20}	1.4921^{20}	vs ace, bz, eth, EtOH
2587	Cyclohexanol	Cyclohexyl alcohol	$C_6H_{12}O$	108-93-0	100.158	hyg nd	25.93	160.84	0.9624^{20}	1.4641^{20}	s H_2O, EtOH, eth, ace; msc bz; sl chl
2588	Cyclohexanone	Pimelic ketone	$C_6H_{10}O$	108-94-1	98.142	liq	-27.9	155.43	0.9478^{20}	1.4507^{20}	s H_2O, EtOH, eth, ace, bz, chl, ctc
2589	Cyclohexanone oxime		$C_6H_{11}NO$	100-64-1	113.157	hex pr (lig)	90	206			s H_2O, EtOH, eth, MeOH; sl chl
2590	Cyclohexanone peroxide		$C_{12}H_{22}O_5$	78-18-2	246.300	cry or long nd	79				
2591	Cyclohexene	Tetrahydrobenzene	C_6H_{10}	110-83-8	82.143	liq	-103.5	82.98	0.8110^{20}	1.4465^{20}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
2592	1-Cyclohexenecarbonitrile	1-Cyanocyclohexene	C_7H_9N	1855-63-6	107.153			81^{12}			
2593	1-Cyclohexene-1-carboxaldehyde		$C_7H_{10}O$	1192-88-7	110.153			69^{18}	0.9694^{20}	1.5005^{20}	s EtOH, eth
2594	3-Cyclohexene-1-carboxaldehyde		$C_7H_{10}O$	100-50-5	110.153		1.0	105	0.9692^{20}	1.4745^{20}	s ace, MeOH; sl ctc
2595	1-Cyclohexene-1-carboxylic acid		$C_7H_{10}O_2$	636-82-8	126.153		38	241	1.109^{20}	1.4902^{20}	sl H_2O; s EtOH, ace
2596	3-Cyclohexene-1-carboxylic acid		$C_7H_{10}O_2$	4771-80-6	126.153		17	234.5	1.0820^{20}	1.4814^{20}	vs H_2O; s EtOH, ace
2597	4-Cyclohexene-1,2-dicarboxylic acid		$C_8H_{10}O_4$	88-98-2	170.163	pr (w)	173.0				
2598	2-Cyclohexen-1-ol		$C_6H_{10}O$	822-67-3	98.142			164	0.9923^{15}	1.4790^{25}	s EtOH, ace
2599	2-Cyclohexen-1-one		C_6H_8O	930-68-7	96.127	liq	-53	170	0.9620^{25}	1.4883^{20}	vs EtOH; s ace
2600	1-Cyclohexen-1-ylbenzene		$C_{12}H_{14}$	771-98-2	158.239	liq	-11	252	0.9939^{20}	1.5718^{20}	vs MeOH
2601	2-(1-Cyclohexen-1-yl) cyclohexanone		$C_{12}H_{18}O$	1502-22-3	178.270			116^{3}		1.5070^{20}	
2602	1-(1-Cyclohexen-1-yl)ethanone		$C_8H_{12}O$	932-66-1	124.180		73	201.5	0.9655^{20}	1.4881^{20}	s EtOH, eth
2603	3-Cyclohexenylmethyl 3-cyclohexenecarboxylate		$C_{14}H_{20}O_2$	2611-00-9	220.308	liq		153^{7}, $109^{0.6}$			
2604	4-(3-Cyclohexen-1-yl)pyridine		$C_{11}H_{13}N$	70644-46-1	159.228		22.1	226	1.0222^{25}	1.5466^{25}	
2605	Cycloheximide		$C_{15}H_{23}NO_4$	66-81-9	281.349	pl (al)	119				vs EtOH
2606	Cyclohexyl acetate		$C_8H_{14}O_2$	622-45-7	142.196			173; 96^{75}	0.968^{20}	1.442^{20}	vs eth, EtOH
2607	Cyclohexyl acrylate		$C_9H_{14}O_2$	3066-71-5	154.206			183; 88^{20}	1.0275^{20}	1.4673^{20}	i H_2O; msc EtOH, eth; s chl
2608	Cyclohexylamine	Cyclohexanamine	$C_6H_{13}N$	108-91-8	99.174	liq	-17.8	134	0.8191^{20}	1.4625^{15}	s H_2O, ctc; vs EtOH; msc eth, ace, bz
2609	Cyclohexylamine hydrochloride	Cyclohexanamine hydrochloride	$C_6H_{14}ClN$	4998-76-9	135.635	nd (w, al-eth)	206.5				vs H_2O, EtOH
2610	2-(Cyclohexylaminothio) benzothiazole		$C_{13}H_{16}N_2S_2$	95-33-0	264.409		103				
2611	*N*-Cyclohexylaniline		$C_{12}H_{17}N$	1821-36-9	175.270	mcl pr	16	279; 192^{73}	1.0155^{20}	1.5610^{20}	i H_2O; s EtOH, eth, bz
2612	Cyclohexylbenzene		$C_{12}H_{16}$	827-52-1	160.255	pl	7.07	240.1	0.9427^{20}	1.5329^{20}	i H_2O; vs EtOH; s eth; sl ctc
2613	Cyclohexyl benzoate		$C_{13}H_{16}O_2$	2412-73-9	204.265		<-10	285	1.0429^{20}	1.5200^{20}	i H_2O; s EtOH, eth
2614	Cyclohexyl butanoate		$C_{10}H_{18}O_2$	1551-44-6	170.249			213	0.9572^{0}		i H_2O; s EtOH; sl ctc
2615	3-Cyclohexyl-2-butenoic acid	Cicrotoic acid	$C_{10}H_{16}O_2$	25229-42-9	168.233	pr (aq-MeOH)	85.5				
2616	Cyclohexyl chloroformate		$C_7H_{11}ClO_2$	13248-54-9	162.614			87.5^{27}			vs eth
2617	Cyclohexylcyclohexane		$C_{12}H_{22}$	92-51-3	166.303		4	238			sl H_2O; s EtOH, eth
2618	Cyclohexyldiethylamine	*N,N*-Diethylcyclohexanamine	$C_{10}H_{21}N$	91-65-6	155.281			192; 85^{20}	0.8443^{25}		s EtOH; sl ctc
2619	Cyclohexyldimethylamine	*N,N*-Dimethylcyclohexanamine	$C_8H_{17}N$	98-94-2	127.228			162			
2620	2-Cyclohexyl-4,6-dinitrophenol		$C_{12}H_{14}N_2O_5$	131-89-5	266.249	cry	104				sl H_2O; s bz, DMF
2621	(1,2-Cyclohexylenedinitrilo) tetraacetic acid monohydrate	CDTA	$C_{14}H_{24}N_2O_9$	13291-61-7	364.349	cry (w)	215				
2622	1-Cyclohexylethanone		$C_8H_{14}O$	823-76-7	126.196			180.5	0.9176^{20}	1.4565^{16}	i H_2O; s eth
2623	Cyclohexylethylamine	*N*-Ethylcyclohexanamine	$C_8H_{17}N$	5459-93-8	127.228			164	0.868^{0}		sl H_2O, ctc; msc EtOH, eth


1,2-Cyclohexanedione dioxime


Cyclohexaneethanol


Cyclohexanemethanamine



Cyclohexanemethanol



Cyclohexanepropanoic acid


Cyclohexanethiol



Cyclohexanol



Cyclohexanone



Cyclohexanone oxime



Cyclohexanone peroxide



Cyclohexene



1-Cyclohexenecarbonitrile


1-Cyclohexene-1-carboxaldehyde


3-Cyclohexene-1-carboxaldehyde



1-Cyclohexene-1-carboxylic acid



3-Cyclohexene-1-carboxylic acid



4-Cyclohexene-1,2-dicarboxylic acid



2-Cyclohexen-1-ol



2-Cyclohexen-1-one



1-Cyclohexen-1-ylbenzene



2-(1-Cyclohexen-1-yl)cyclohexanone



1-(1-Cyclohexen-1-yl)ethanone


3-Cyclohexenylmethyl 3-cyclohexenecarboxylate



4-(3-Cyclohexen-1-yl)pyridine



Cycloheximide



Cyclohexyl acetate



Cyclohexyl acrylate



Cyclohexylamine



Cyclohexylamine hydrochloride



2-(Cyclohexylaminothio)benzothiazole



N-Cyclohexylaniline



Cyclohexylbenzene



Cyclohexyl benzoate



Cyclohexyl butanoate



3-Cyclohexyl-2-butenoic acid



Cyclohexyl chloroformate



Cyclohexylcyclohexane



Cyclohexyldiethylamine


Cyclohexyldimethylamine



2-Cyclohexyl-4,6-dinitrophenol



(1,2-Cyclohexylenedinitrilo)tetraacetic acid monohydrate



1-Cyclohexylethanone



Cyclohexylethylamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2624	4-Cyclohexyl-3-ethyl-4*H*-1,2,4-triazole	Hexazole	$C_{10}H_{17}N_3$	4671-03-8	179.262	pr (eth)	89.5	227^{10}			vs H_2O, bz, chl
2625	Cyclohexyl formate		$C_7H_{12}O_2$	4351-54-6	128.169			162	1.0057^{0}	1.4430^{20}	i H_2O; s EtOH, HOAc, HCOOH; vs eth
2626	Cyclohexyl hydroperoxide		$C_6H_{12}O_2$	766-07-4	116.158		-20	$42^{0.1}$	1.019^{20}	1.4645^{25}	vs eth, EtOH, HOAc
2627	Cyclohexylideneacetonitrile		$C_8H_{11}N$	4435-18-1	121.180			107^{22}	0.9483^{15}	1.4382^{25}	vs eth, EtOH
2628	2-Cyclohexylidenecyclohexanone		$C_{12}H_{18}O$	1011-12-7	178.270	cry (MeOH aq)	56.5				
2629	Cyclohexyl isocyanate	Isocyanatocyclohexane	$C_7H_{11}NO$	3173-53-3	125.168			172	0.98^{25}	1.4551^{20}	
2630	Cyclohexylisopropylamine	*N*-Isopropylcyclohexanamine	$C_9H_{19}N$	1195-42-2	141.254			62^{12}	0.859^{25}	1.4480^{20}	
2631	Cyclohexyl isothiocyanate	Isothiocyanatocyclohexane	$C_7H_{11}NS$	1122-82-3	141.234			221	1.0339^{20}	1.5375^{20}	i H_2O; s EtOH, eth; sl ctc
2632	Cyclohexylmagnesium chloride		$C_6H_{11}ClMg$	931-51-1	142.909	hyg liq					s eth
2633	Cyclohexyl methacrylate		$C_{10}H_{16}O_2$	101-43-9	168.233			210	0.9626^{20}	1.4578^{20}	
2634	Cyclohexylmethylamine	*N*-Methylcyclohexanamine	$C_7H_{15}N$	100-60-7	113.201			147	0.8660^{23}	1.4560^{20}	sl H_2O; vs EtOH; msc eth; s chl
2635	Cyclohexyl 2-methylpropanoate		$C_{10}H_{18}O_2$	1129-47-1	170.249			204	0.9489^{0}		vs eth, EtOH
2636	2-Cyclohexylphenol		$C_{12}H_{16}O$	119-42-6	176.254	nd (lig)	56.5				vs EtOH, HOAc
2637	4-Cyclohexylphenol		$C_{12}H_{16}O$	1131-60-8	176.254	nd (bz)	133	294; 133^{4}			i H_2O; vs EtOH, eth; s bz; sl lig
2638	α-Cyclohexyl-α-phenyl-1-piperidinepropanol	Trihexphenidyl	$C_{20}H_{31}NO$	144-11-6	301.466		114				
2639	Cyclohexyl propanoate		$C_9H_{16}O_2$	6222-35-1	156.222			193; 93^{35}	0.9359^{20}	1.4403^{20}	i H_2O; s EtOH, eth, ace, ctc
2640	Cyclohexylsulfamic acid	Cyclamic acid	$C_6H_{13}NO_3S$	100-88-9	179.237		169.5				vs alk
2641	Cyclononane		C_9H_{18}	293-55-0	126.239		11	178.4	0.8463^{25}	1.4666^{20}	
2642	Cyclononanone		$C_9H_{16}O$	3350-30-9	140.222		34	148^{24}, 94^{12}	0.9560^{20}	1.4729^{20}	s EtOH
2643	1,4-Cyclooctadiene		C_8H_{12}	1073-07-0	108.181	liq	-53	145	0.8754^{20}		
2644	*cis,cis*-1,5-Cyclooctadiene		C_8H_{12}	111-78-4	108.181	liq	-56.4	150.5	0.883^{20}	1.4905^{25}	vs bz
2645	Cyclooctanamine	Aminocyclooctane	$C_8H_{17}N$	5452-37-9	127.228	liq	-48	190	0.928^{25}	1.4804^{20}	
2646	Cyclooctane		C_8H_{16}	292-64-8	112.213		14.59	149	0.8349^{20}	1.4586^{20}	i H_2O; s bz, lig
2647	Cyclooctanol		$C_8H_{16}O$	696-71-9	128.212		25.1	99^{16}	0.9740^{20}	1.4871^{20}	s EtOH
2648	Cyclooctanone		$C_8H_{14}O$	502-49-8	126.196		29	196	0.9581^{20}	1.4694^{20}	i H_2O; s EtOH, ace, bz; sl ctc
2649	1,3,5,7-Cyclooctatetraene	[8]Annulene	C_8H_8	629-20-9	104.150	liq	-2.4	140.5	0.9206^{20}	1.5381^{20}	s EtOH, eth, ace, bz
2650	1,3,5-Cyclooctatriene		C_8H_{10}	1871-52-9	106.165	liq	-83	145.5	0.8971^{25}	1.5035^{25}	
2651	*cis*-Cyclooctene		C_8H_{14}	931-87-3	110.197	liq	-12	138	0.8472^{20}	1.4698^{20}	s EtOH, eth, ctc
2652	*trans*-Cyclooctene		C_8H_{14}	931-89-5	110.197	liq	-59	143	0.8483^{20}	1.4741^{25}	s EtOH, chl; sl ctc
2653	Cyclooctyne		C_8H_{12}	1781-78-8	108.181			158	0.868^{20}	1.4850^{20}	
2654	Cyclopamine	11-Deoxojervine	$C_{27}H_{41}NO_2$	4449-51-8	411.621	nd (EtOH)	237				
2655	Cyclopentadecane		$C_{15}H_{30}$	295-48-7	210.399	nd (MeOH)	61.3		0.8364^{61}	1.4592^{61}	
2656	Cyclopentadecanol	Exaltol	$C_{15}H_{30}O$	4727-17-7	226.398	cry (MeOH)	80.5	177^{11}, $145^{0.3}$	0.930^{20}	1.4555^{98}	
2657	Cyclopentadecanone		$C_{15}H_{28}O$	502-72-7	224.382		63	$120^{0.3}$	0.8895^{25}	1.4637^{60}	sl H_2O; s EtOH, ace
2658	1,3-Cyclopentadiene	Pyropentylene	C_5H_6	542-92-7	66.102	liq	-85	41	0.8021^{20}	1.4440^{20}	i H_2O; msc EtOH, eth, bz; s ace
2659	Cyclopentane	Pentamethylene	C_5H_{10}	287-92-3	70.133	liq	-93.4	49.3	0.7457^{20}	1.4065^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
2660	Cyclopentaneacetic acid		$C_7H_{12}O_2$	1123-00-8	128.169	pl	13.5	228	1.0216^{18}	1.4523^{18}	
2661	Cyclopentanecarbonitrile	Cyanocyclopentane	C_6H_9N	4254-02-8	95.142	liq	-76	170; 67^{10}	0.912	1.4410^{20}	
2662	Cyclopentanecarboxaldehyde		$C_6H_{10}O$	872-53-7	98.142			133.5	0.9371^{20}	1.4432^{20}	vs H_2O, eth, EtOH
2663	Cyclopentanecarboxylic acid	Cyclopentanoic acid	$C_6H_{10}O_2$	3400-45-1	114.142	liq	-7	212; 104^{11}	1.0527^{20}	1.4532^{20}	sl H_2O, ctc; s MeOH
2664	*cis*-1,2-Cyclopentanediol		$C_5H_{10}O_2$	5057-98-7	102.132		30	124^{29}, 100^{10}			
2665	*trans*-1,2-Cyclopentanediol		$C_5H_{10}O_2$	5057-99-8	102.132		54.7	226; 136^{21}			
2666	Cyclopentanemethanol		$C_6H_{12}O$	3637-61-4	100.158			163	0.9332^{20}	1.4579^{20}	
2667	Cyclopentanepropanoic acid		$C_8H_{14}O_2$	140-77-2	142.196			158^{26}, 131^{12}	1.0100^{17}	1.4570^{20}	
2668	Cyclopentanethiol	Cyclopentyl mercaptan	$C_5H_{10}S$	1679-07-8	102.198			132.1	0.9550^{20}		
2669	Cyclopentanol	Cyclopentyl alcohol	$C_5H_{10}O$	96-41-3	86.132	liq	-17.5	140.42	0.9488^{20}	1.4530^{20}	sl H_2O, ctc; s EtOH, eth, ace
2670	Cyclopentanone	Adipic ketone	C_5H_8O	120-92-3	84.117	liq	-51.90	130.57	0.9487^{20}	1.4366^{20}	i H_2O; s EtOH, ace, ctc, hx; msc eth
2671	Cyclopentanone oxime		C_5H_9NO	1192-28-5	99.131		57.8	196			vs H_2O, bz



4-Cyclohexyl-3-ethyl-4*H*-1,2,4-triazole



Cyclohexyl formate



Cyclohexyl hydroperoxide



Cyclohexylideneacetonitrile



2-Cyclohexylidenecyclohexanone



Cyclohexyl isocyanate



Cyclohexylisopropylamine



Cyclohexyl isothiocyanate



Cyclohexylmagnesium chloride



Cyclohexyl methacrylate



Cyclohexylmethylamine



Cyclohexyl 2-methylpropanoate



2-Cyclohexylphenol



4-Cyclohexylphenol


α-Cyclohexyl-α-phenyl-1-piperidinepropanol


Cyclohexyl propanoate



Cyclohexylsulfamic acid


Cyclononane



Cyclononanone



1,4-Cyclooctadiene


cis,cis-1,5-Cyclooctadiene


Cyclooctanamine


Cyclooctane



Cyclooctanol



Cyclooctanone



1,3,5,7-Cyclooctatetraene



1,3,5-Cyclooctatriene



cis-Cyclooctene



trans-Cyclooctene


Cyclooctyne


Cyclopamine



Cyclopentadecane


Cyclopentadecanol


Cyclopentadecanone


1,3-Cyclopentadiene



Cyclopentane


Cyclopentaneacetic acid


Cyclopentanecarbonitrile



Cyclopentanecarboxaldehyde


Cyclopentanecarboxylic acid


cis-1,2-Cyclopentanediol


trans-1,2-Cyclopentanediol


Cyclopentanemethanol


Cyclopentanepropanoic acid



Cyclopentanethiol



Cyclopentanol


Cyclopentanone



Cyclopentanone oxime


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2672	Cyclopentene		C_5H_8	142-29-0	68.118	liq	-135.0	44.2	0.7720^{20}	1.4225^{20}	i H_2O; s EtOH, eth, bz, ctc, peth
2673	1-Cyclopentenecarbonitrile	1-Cyanocyclopentene	C_6H_7N	3047-38-9	93.127	liq		81^{30}			
2674	1-Cyclopentene-1-carboxaldehyde		C_6H_8O	6140-65-4	96.127	liq	-32	146	0.970^{21}	1.4872^{17}	
2675	2-Cyclopentene-1-tridecanoic acid, (*S*)	Chaulmoogric acid	$C_{18}H_{32}O_2$	29106-32-9	280.446	pl or lf (al, HOAc)	68.5	247^{20}			vs eth, chl
2676	2-Cyclopentene-1-undecanoic acid, (*R*)	Hydnocarpic acid	$C_{16}H_{28}O_2$	459-67-6	252.392		60.5				vs EtOH, chl, peth
2677	2-Cyclopenten-1-one		C_5H_6O	930-30-3	82.101			$136; 40^{12}$	0.989^{15}	1.4629^{15}	vs eth, EtOH
2678	3-Cyclopenten-1-one		C_5H_6O	14320-37-7	82.101	liq		28^{17}			
2679	*N*-(1-Cyclopenten-1-yl)pyrrolidine	1-Pyrrolidinylcyclopentene	$C_9H_{15}N$	7148-07-4	137.222			105^{15}		1.5128^{20}	
2680	Cyclopenthiazide		$C_{13}H_{18}ClN_3O_4S_2$	742-20-1	379.883		238				
2681	Cyclopentobarbital		$C_{12}H_{14}N_2O_3$	76-68-6	234.250	cry (w, dil al)	139.5				sl H_2O; vs EtOH
2682	Cyclopentylamine	Cyclopentanamine	$C_5H_{11}N$	1003-03-8	85.148	liq	-82.7	108	0.8689^{20}	1.4728^{25}	s ace, bz, chl
2683	Cyclopentylbenzene		$C_{11}H_{14}$	700-88-9	146.229			219	0.9462^{20}	1.5280^{20}	vs eth
2684	2-Cyclopentylidenecyclopentanone		$C_{10}H_{14}O$	825-25-2	150.217			135^{25}	1.0179^{18}	1.5215^{18}	
2685	Cyclopentyl methyl sulfide		$C_6H_{12}S$	7133-36-0	116.224			156.2			
2686	Cyclophosphamide	Cyclophosphane	$C_7H_{15}Cl_2N_2O_2P$	50-18-0	261.086		43				vs H_2O; sl bz, chl, diox, EtOH
2687	Cycloposine		$C_{33}H_{51}NO_7$	23185-94-6	573.761		268				
2688	Cyclopropane	Trimethylene	C_3H_6	75-19-4	42.080	col gas	-127.58	-32.81	0.617^{25} (p>1 atm)	1.3799^{-42}	s H_2O, bz, peth; vs EtOH, eth
2689	Cyclopropanecarbonitrile	Cyclopropyl cyanide	C_4H_5N	5500-21-0	67.090			135.1	0.8946^{20}	1.4229^{20}	s eth, hx; sl ctc
2690	Cyclopropanecarbonyl chloride		C_4H_5ClO	4023-34-1	104.535			119	1.1516^{20}		
2691	Cyclopropanecarboxaldehyde	Formylcyclopropane	C_4H_6O	1489-69-6	70.090	liq		100	0.938	1.4298^{20}	
2692	Cyclopropanecarboxylic acid		$C_4H_6O_2$	1759-53-1	86.090		18.5	183	1.0885^{20}	1.4390^{20}	s H_2O, EtOH, eth; sl ctc
2693	1,1-Cyclopropanedicarboxylic acid		$C_5H_6O_4$	598-10-7	130.100	pr or nd (chl) pr (w +1)	140.5				vs H_2O, eth
2694	Cyclopropanemethanol		C_4H_8O	2516-33-8	72.106			124	0.911^{25}		sl ctc
2695	Cyclopropanone		C_3H_4O	5009-27-8	56.063		stable only at low temp.				
2696	Cyclopropene		C_3H_4	2781-85-3	40.064	gas		dec -36			
2697	Cyclopropylamine	Cyclopropanamine	C_3H_7N	765-30-0	57.095	liq	-35.39	50.5	0.8240^{20}	1.4210^{20}	msc H_2O; s EtOH, eth, chl
2698	Cyclopropylbenzene		C_9H_{10}	873-49-4	118.175	liq	-31	$173.6; 80^{37}$	0.9317^{20}	1.5285^{20}	i H_2O; s eth, ace, chl
2699	Cyclopropyl methyl ether		C_4H_8O	540-47-6	72.106	liq	-119	44.7	0.8100^{20}	1.3802^{20}	vs H_2O, bz, eth, EtOH
2700	Cyclopropyl methyl ketone		C_5H_8O	765-43-5	84.117	liq	-68.3	111.3	0.8984^{20}	1.4251^{20}	vs H_2O, eth, EtOH
2701	Cyclotetramethylenetetranitramine	HMX	$C_4H_8N_8O_8$	2691-41-0	296.156	cry	286	exp			
2702	Cyclothiazide		$C_{14}H_{16}ClN_3O_4S_2$	2259-96-3	389.878		234				
2703	Cycluron	*N*'-Cyclooctyl-*N*,*N*-dimethylurea	$C_{11}H_{22}N_2O$	2163-69-1	198.305	cry	138				sl H_2O; s bz, ace; vs MeOH
2704	Cyfluthrin		$C_{22}H_{18}Cl_2FNO_3$	68359-37-5	434.287		60				
2705	Cygon		$C_5H_{12}NO_3PS_2$	60-51-5	229.258		52	$117^{0.1}$	1.277^{65}		
2706	Cyhalothrin	2,2-Dimethylcyclopropanecarboxylate	$C_{23}H_{19}ClF_3NO_3$	91465-08-6	449.850		49.2				
2707	Cyhexatin	Stannane, tricyclohexylhydroxy-	$C_{18}H_{34}OSn$	13121-70-5	385.172		196				
2708	Cypermethrin		$C_{22}H_{19}Cl_2NO_3$	52315-07-8	416.297		70		1.25^{20}		
2709	Cyprazine		$C_9H_{14}ClN_5$	22936-86-3	227.694		167				
2710	Cyproheptadine		$C_{21}H_{21}N$	129-03-3	287.399	cry (EtOH aq)	113				
2711	Cyromazine	*N*-Cyclopropyl-1,3,5-triazine-2,4,6-triamine	$C_6H_{10}N_6$	66215-27-8	166.183	cry	220				
2712	Cystamine dihydrochloride		$C_4H_{14}Cl_2N_2S_2$	56-17-7	225.203	nd (MeOH)	218 dec				vs H_2O, EtOH
2713	Cysteamine		C_2H_7NS	60-23-1	77.149	cry (sub)	99.5	dec			vs H_2O, EtOH
2714	*L*-Cysteic acid		$C_3H_7NO_5S$	13100-82-8	169.157	cry	260 dec				s H_2O; i EtOH
2715	*L*-Cysteine	Propanoic acid, 2-amino-3-mercapto-, (*R*)-	$C_3H_7NO_2S$	52-90-4	121.159	cry (w)	240 dec				vs H_2O, ace, EtOH
2716	*L*-Cysteine, ethyl ester, hydrochloride		$C_5H_{12}ClNO_2S$	868-59-7	185.673		125.8				vs H_2O
2717	*L*-Cysteine, hydrochloride		$C_3H_8ClNO_2S$	52-89-1	157.620	cry	175 dec				s H_2O
2718	*L*-Cystine	3,3'-Dithiobis(2-aminopropanoic acid)	$C_6H_{12}N_2O_4S_2$	56-89-3	240.300	hex pl or pr (w)	260 dec		1.677^{25}		sl H_2O; i EtOH, eth, bz; s acid, alk
2719	Cytarabine	Cytosine arabinoside	$C_9H_{13}N_3O_5$	147-94-4	243.216	pr (EtOH aq)	212				s H_2O


Cyclopentene


1-Cyclopentenecarbonitrile



1-Cyclopentene-1-carboxaldehyde



2-Cyclopentene-1-tridecanoic acid, (*S*)



2-Cyclopentene-1-undecanoic acid, (*R*)


2-Cyclopenten-1-one



3-Cyclopenten-1-one



N-(1-Cyclopenten-1-yl)pyrrolidine


Cyclopenthiazide



Cyclopentobarbital



Cyclopentylamine


Cyclopentylbenzene


2-Cyclopentylidenecyclopentanone


Cyclopentyl methyl sulfide


Cyclophosphamide


Cycloposine



Cyclopropane


Cyclopropanecarbonitrile


Cyclopropanecarbonyl chloride


Cyclopropanecarboxaldehyde


Cyclopropanecarboxylic acid



1,1-Cyclopropanedicarboxylic acid


Cyclopropanemethanol


Cyclopropanone



Cyclopropene



Cyclopropylamine



Cyclopropylbenzene



Cyclopropyl methyl ether



Cyclopropyl methyl ketone



Cyclotetramethylenetetranitramine



Cyclothiazide



Cycluron



Cyfluthrin



Cygon



Cyhalothrin



Cyhexatin



Cypermethrin



Cyprazine



Cyproheptadine



Cyromazine



Cystamine dihydrochloride



Cysteamine



L-Cysteic acid


L-Cysteine



L-Cysteine, ethyl ester, hydrochloride



L-Cysteine, hydrochloride



L-Cystine



Cytarabine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2720	Cytidine	4-Amino-1-β-*D*-ribofuranosyl-2(1*H*)-pyrimidinone	$C_9H_{13}N_3O_5$	65-46-3	243.216	nd (dil al)	230 dec				vs H_2O; sl EtOH
2721	2'-Cytidylic acid	Cytidine 2'-monophosphate	$C_9H_{14}N_3O_8P$	85-94-9	323.196		239 dec				
2722	3'-Cytidylic acid	Cytidine 3'-monophosphate	$C_9H_{14}N_3O_8P$	84-52-6	323.196		233 dec				s H_2O, EtOH
2723	5'-Cytidylic acid	Cytidine 5'-monophosphate	$C_9H_{14}N_3O_8P$	63-37-6	323.196	orth nd	233 dec				vs H_2O, EtOH
2724	Cytisine	Sophorine	$C_{11}H_{14}N_2O$	485-35-8	190.241	pr	153	218[2]			vs H_2O, EtOH, MeOH; s bz, ace
2725	Cytochalasin B		$C_{29}H_{37}NO_5$	14930-96-2	479.608	nd (ace)	219				
2726	Cytochalasin D	Zygosporin A	$C_{30}H_{37}NO_6$	22144-77-0	507.618	nd (ace/ peth)	270				
2727	Cytochalasin E		$C_{28}H_{33}NO_7$	36011-19-5	495.565		207				
2728	Cytosine		$C_4H_5N_3O$	71-30-7	111.102	mcl or tcl pl (w+1)	322 dec				s H_2O; sl EtOH, chl; i eth
2729	Dacarbazine	5-(3,3-Dimethyl-1-triazenyl)-1*H*-imidazole-4-carboxamide	$C_6H_{10}N_6O$	4342-03-4	182.182	cry	205				
2730	Dactinomycin		$C_{62}H_{86}N_{12}O_{16}$	50-76-0	1255.416		245 dec				
2731	Daidzein	7-Hydroxy-3-(4-hydroxyphenyl) -4*H*-1-benzopyran-4-one	$C_{15}H_{10}O_4$	486-66-8	254.238	pa ye pr (50% al)	323 dec	sub			s EtOH, eth
2732	Daminozide	Butanedioic acid, mono(2,2-dimethylhydrazide)	$C_6H_{12}N_2O_3$	1596-84-5	160.170		154.5				
2733	Dantrolene		$C_{14}H_{10}N_4O_5$	7261-97-4	314.253	cry (DMF aq)	280				
2734	Datiscetin		$C_{15}H_{10}O_6$	480-15-9	286.236	pa ye nd (al, aq HOAc)	277.5				vs ace, eth, EtOH
2735	Daucol		$C_{15}H_{26}O_2$	887-08-1	238.366	cry	114	128[2]			
2736	Daunorubicin		$C_{27}H_{29}NO_{10}$	20830-81-3	527.520	red nd	208				
2737	Dazomet		$C_5H_{10}N_2S_2$	533-74-4	162.276	nd (bz)	106				reac H_2O; s EtOH
2738	Decabromobiphenyl ether	Bis(pentabromophenyl) ether	$C_{12}Br_{10}O$	1163-19-5	959.167	ye pr (tol)	305				i H_2O
2739	Decachlorobiphenyl		$C_{12}Cl_{10}$	2051-24-3	498.658	cry (bz)	309				i H_2O
2740	1,3-Decadiene	1-Hexyl-1,3-butadiene	$C_{10}H_{18}$	2051-25-4	138.250			169	0.752[30]		vs bz
2741	1,9-Decadiene		$C_{10}H_{18}$	1647-16-1	138.250			167	0.75[25]	1.4325[20]	
2742	2,2',3,3',4,4',5,5',6,6'-Decafluoro-1,1'-biphenyl		$C_{12}F_{10}$	434-90-2	334.112		67.5	206	1.785[20]		
2743	*cis*-Decahydronaphthalene	*cis*-Decalin	$C_{10}H_{18}$	493-01-6	138.250	liq	-42.9	195.8	0.8965[20]	1.4810[20]	i H_2O; msc EtOH; vs eth, ace, chl
2744	*trans*-Decahydronaphthalene	*trans*-Decalin	$C_{10}H_{18}$	493-02-7	138.250	liq	-30.4	187.3	0.8659[25]	1.4695[20]	i H_2O; vs EtOH, eth, ace; msc bz; sl MeOH
2745	Decahydro-2-naphthol	Decahydro-β-naphthol	$C_{10}H_{18}O$	825-51-4	154.249			109[14]	0.996[25]	1.4992[20]	
2746	Decamethonium dibromide		$C_{16}H_{38}Br_2N_2$	541-22-0	418.294	cry (MeOH/ ace)	269 dec				i eth
2747	Decamethylcyclopentasiloxane		$C_{10}H_{30}O_5Si_5$	541-02-6	370.770	liq	-38	210	0.9593[20]	1.3982[20]	i H_2O
2748	Decamethyltetrasiloxane		$C_{10}H_{30}O_3Si_4$	141-62-8	310.685	liq	-76	194	0.8536[25]	1.3895[20]	i H_2O; sl EtOH; s bz, peth
2749	Decanal	Capraldehyde	$C_{10}H_{20}O$	112-31-2	156.265	liq	-4.0	208.5	0.830[15]	1.4287[20]	i H_2O; s EtOH, eth, ace; sl ctc
2750	Decane		$C_{10}H_{22}$	124-18-5	142.282	liq	-29.6	174.15	0.7266[25]	1.4090[25]	i H_2O; msc EtOH; s eth; sl ctc
2751	1,10-Decanediamine		$C_{10}H_{24}N_2$	646-25-3	172.311		59.73	140[12]			
2752	Decanedinitrile		$C_{10}H_{16}N_2$	1871-96-1	164.247		7.6	204[16]	0.913[20]	1.4474[20]	i H_2O; s chl
2753	1,10-Decanediol	Decamethylene glycol	$C_{10}H_{22}O_2$	112-47-0	174.281	nd (w, dil al)	74	192[20]			sl H_2O, eth; vs EtOH; s DMSO; i lig
2754	Decanedioyl dichloride		$C_{10}H_{16}Cl_2O_2$	111-19-3	239.139		-1.3	220[75], 165[11]	1.1212[20]	1.4684[18]	
2755	Decanenitrile	Caprinitrile	$C_{10}H_{19}N$	1975-78-6	153.265	liq	-17.9	243; 106[10]	0.8199[20]	1.4296[20]	vs ace, eth, EtOH, chl
2756	1-Decanethiol	Decyl mercaptan	$C_{10}H_{22}S$	143-10-2	174.347	liq	-26	240.6	0.8443[20]	1.4509[20]	i H_2O; s EtOH, eth
2757	Decanoic acid	Capric acid	$C_{10}H_{20}O_2$	334-48-5	172.265	nd	31.4	268.7	0.8858[40]	1.4288[40]	i H_2O; vs ace, bz, eth, EtOH
2758	1-Decanol	Capric alcohol	$C_{10}H_{22}O$	112-30-1	158.281		6.9	231.1	0.8297[20]	1.4372[20]	i H_2O; msc EtOH, eth, ace, bz, chl; s ctc
2759	2-Decanol		$C_{10}H_{22}O$	74742-10-2	158.281	liq	-1.2	211	0.8250[20]	1.4326[25]	s EtOH, bz; msc eth, ace; sl ctc
2760	3-Decanol		$C_{10}H_{22}O$	1565-81-7	158.281	liq	-7.5	213; 101[12]	0.827[20]	1.434[20]	
2761	4-Decanol	1-Propylheptyl alcohol	$C_{10}H_{22}O$	2051-31-2	158.281	liq	-11	210.5	0.8261[20]	1.4320[20]	i H_2O; s EtOH, ctc
2762	5-Decanol		$C_{10}H_{22}O$	5205-34-5	158.281	liq	8.7	201	0.824[20]	1.4333[20]	
2763	2-Decanone	Methyl octyl ketone	$C_{10}H_{20}O$	693-54-9	156.265	nd	14	210; 96[12]	0.8248[20]	1.4255[20]	i H_2O; s EtOH, eth; sl ctc



Cytidine



2'-Cytidylic acid



3'-Cytidylic acid



5'-Cytidylic acid



Cytisine



Cytochalasin B



Cytochalasin D



Cytochalasin E



Cytosine



Dacarbazine



Dactinomycin



Daidzein



Daminozide



Dantrolene



Datiscetin



Daucol



Daunorubicin



Dazomet



Decabromobiphenyl ether



Decachlorobiphenyl



1,3-Decadiene



1,9-Decadiene



2,2',3,3',4,4',5,5',6,6'-Decafluoro-1,1'-biphenyl



cis-Decahydronaphthalene



trans-Decahydronaphthalene



Decahydro-2-naphthol



Decamethonium dibromide



Decamethylcyclopentasiloxane



Decamethyltetrasiloxane



Decanal



Decane



1,10-Decanediamine



Decanedinitrile



1,10-Decanediol



Decanedioyl dichloride



Decanenitrile



1-Decanethiol



Decanoic acid



1-Decanol


2-Decanol



3-Decanol



4-Decanol



5-Decanol



2-Decanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2764	3-Decanone	Ethyl heptyl ketone	$C_{10}H_{20}O$	928-80-3	156.265	liq	1.3	203	0.8251^{20}	1.4252^{20}	s EtOH, eth, ctc
2765	4-Decanone	Hexyl propyl ketone	$C_{10}H_{20}O$	624-16-8	156.265	liq	-9	206.5	0.824^{20}	1.4240^{21}	i H_2O; msc EtOH, eth
2766	Decanoyl chloride	Caprinoyl chloride	$C_{10}H_{19}ClO$	112-13-0	190.710	liq	-34.5	95	0.919^{25}	1.4410^{20}	s eth, ctc
2767	*trans*-2-Decenal		$C_{10}H_{18}O$	3913-81-3	154.249			230; 107^{11}			
2768	1-Decene		$C_{10}H_{20}$	872-05-9	140.266	liq	-66.3	170.5	0.7408^{20}	1.4215^{20}	i H_2O; msc EtOH, eth
2769	*cis*-2-Decene		$C_{10}H_{20}$	20348-51-0	140.266	col liq		174.2			
2770	*trans*-2-Decene		$C_{10}H_{20}$	20063-97-2	140.266	col liq		173.3			
2771	*cis*-5-Decene		$C_{10}H_{20}$	7433-78-5	140.266	col liq	-112	171; 73^{20}	0.7445^{20}	1.4258^{20}	i H_2O; msc EtOH, eth; sl ctc
2772	*trans*-5-Decene		$C_{10}H_{20}$	7433-56-9	140.266	col liq	-73	171	0.7401^{20}	1.4243^{20}	i H_2O; msc EtOH, eth; sl ctc
2773	9-Decenoic acid	Caproleic acid	$C_{10}H_{18}O_2$	14436-32-9	170.249		26.5	158^{21}, 142^{4}	0.9238^{15}	1.4507^{15}	vs eth, EtOH
2774	9-Decen-1-ol	Decylenic alcohol	$C_{10}H_{20}O$	13019-22-2	156.265			236	0.876^{25}	1.4480^{20}	
2775	3-Decen-2-one	Heptylidene acetone	$C_{10}H_{18}O$	10519-33-2	154.249			$102^{15.3}$	0.8473^{20}	1.4480^{20}	
2776	Declomycin	Demeclocycline	$C_{21}H_{21}ClN_2O_8$	127-33-3	464.853	cry	176 dec				
2777	Decyl acetate		$C_{12}H_{24}O_2$	112-17-4	200.318	liq	-15	244	0.8671^{20}	1.4273^{20}	i H_2O; s EtOH, eth, bz, ctc, HOAc
2778	Decylamine	1-Decanamine	$C_{10}H_{23}N$	2016-57-1	157.297		17	220.5	0.7936^{20}	1.4369^{20}	sl H_2O; msc EtOH, eth, ace, bz, chl
2779	Decylbenzene		$C_{16}H_{26}$	104-72-3	218.377	liq	-14.4	293	0.8555^{20}	1.4832^{20}	vs ace, bz, eth, EtOH
2780	Decylcyclohexane		$C_{16}H_{32}$	1795-16-0	224.425	liq	-0.9	299	0.8186^{20}	1.4534^{20}	
2781	Decylcyclopentane		$C_{15}H_{30}$	1795-21-7	210.399	liq	-22	279	0.8110^{20}	1.4486^{20}	vs ace, bz, eth, EtOH
2782	Decyl decanoate		$C_{20}H_{40}O_2$	1654-86-0	312.531		9.7	219^{15}	0.8586^{20}	1.4423^{20}	vs eth
2783	Decyl formate		$C_{11}H_{22}O_2$	5451-52-5	186.292	liq		243			
2784	11-Decylheneicosane		$C_{31}H_{64}$	55320-06-4	436.840		10.0	282.0^{10}	0.8116^{20}	1.4540^{20}	
2785	1-Decylnaphthalene		$C_{20}H_{28}$	26438-27-7	268.436		15	379	0.9322^{20}	1.5435^{20}	
2786	Decyloxirane		$C_{12}H_{24}O$	2855-19-8	184.318					1.4347^{25}	sl ctc
2787	Decyl vinyl ether	1-(Ethenyloxy)decane	$C_{12}H_{24}O$	765-05-9	184.318		-41	101^{10}	0.812^{20}	1.4346^{20}	
2788	1-Decyne	Octylacetylene	$C_{10}H_{18}$	764-93-2	138.250	liq	-44	174	0.7655^{20}	1.4265^{20}	i H_2O; s EtOH, eth
2789	5-Decyne	Dibutylacetylene	$C_{10}H_{18}$	1942-46-7	138.250	liq	-73	177; 78.8^{25}	0.7690^{20}	1.4331^{20}	i H_2O; s EtOH, eth
2790	Dehydroabietic acid	8,11,13-Abietatrien-18-oic acid	$C_{20}H_{28}O_2$	1740-19-8	300.435	cry (EtOH aq)	172				
2791	Delphinidin		$C_{15}H_{11}ClO_7$	528-53-0	338.697		>350				vs H_2O, EtOH, MeOH; s AcOEt
2792	Delphinine		$C_{33}H_{45}NO_9$	561-07-9	599.712	orth (al)	199				i H_2O; s chl, ace, eth; vs EtOH
2793	Deltamethrin		$C_{22}H_{19}Br_2NO_3$	52918-63-5	505.199		99				
2794	Demecarium bromide		$C_{32}H_{52}Br_2N_4O_4$	56-94-0	716.588	hyg pow	165 dec				vs H_2O; sl ace; i ace, eth
2795	Demeton	Systox	$C_8H_{19}O_3PS_2$	8065-48-3	258.339	oily liq		134^{2}			i H_2O; s EtOH, tol
2796	Demeton-*S*-methyl		$C_6H_{15}O_3PS_2$	919-86-8	230.285	ye liq		$89^{0.15}$, 118^{1}	1.20^{20}	1.5063^{20}	i H_2O; s os
2797	2'-Deoxyadenosine		$C_{10}H_{13}N_5O_3$	958-09-8	251.242						sl H_2O
2798	2'-Deoxyadenosine 5'-triphosphate		$C_{10}H_{16}N_5O_{12}P_3$	1927-31-7	491.182	cry (EtOH aq)					
2799	6-Deoxy-*L*-ascorbic acid		$C_6H_8O_5$	528-81-4	160.125	pr (AcOEt)	168	sub 160			vs H_2O, ace, EtOH
2800	Deoxycholic acid	3,12-Dihydroxycholan-24-oic acid, (3α,5β,12α)	$C_{24}H_{40}O_4$	83-44-3	392.573	cry (al)	177				
2801	2'-Deoxycytidine 5'-monophosphate	2'-Deoxy-5'-cytidylic acid	$C_9H_{14}N_3O_7P$	1032-65-1	307.197	pow	183 dec				
2802	2'-Deoxy-5-fluorouridine	Floxuridine	$C_9H_{11}FN_2O_5$	50-91-9	246.191	cry	150				
2803	2-Deoxy-*D*-glucose		$C_6H_{12}O_5$	154-17-6	164.156		146.5				
2804	2'-Deoxyguanosine 5'-monophosphate	2'-Deoxy-5'-guanylic acid	$C_{10}H_{14}N_5O_7P$	902-04-5	347.222						s H_2O
2805	2-Deoxy-*D*-*chiro*-inositol	*D*-Quercitol	$C_6H_{12}O_5$	488-73-3	164.156	pr (w, dil al)	236		1.5845^{13}		vs H_2O
2806	1-Deoxy-1-(methylamino)-*D*-glucitol	*N*-Methylglucamine	$C_7H_{17}NO_5$	6284-40-8	195.214	cry (MeOH)	128.5				s H_2O
2807	6-Deoxy-3-*O*-methylgalactose	Digitalose	$C_7H_{14}O_5$	4481-08-7	178.183	nd (AcOEt)	119				vs H_2O
2808	*D*-2-Deoxyribose		$C_5H_{10}O_4$	533-67-5	134.131		90				
2809	Deserpidine		$C_{32}H_{38}N_2O_8$	131-01-1	578.652	nd or pr	230.5				i H_2O; s EtOH, chl



3-Decanone



4-Decanone



Decanoyl chloride



trans-2-Decenal



1-Decene



cis-2-Decene



trans-2-Decene



cis-5-Decene



trans-5-Decene



9-Decenoic acid



9-Decen-1-ol



3-Decen-2-one



Declomycin



Decyl acetate



Decylamine



Decylbenzene



Decylcyclohexane



Decylcyclopentane


Decyl decanoate



Decyl formate



11-Decylheneicosane



1-Decylnaphthalene



Decyloxirane



Decyl vinyl ether



1-Decyne



5-Decyne



Dehydroabietic acid



Delphinidin



Delphinine



Deltamethrin



Demecarium bromide



Demeton



Demeton-*S*-methyl



2'-Deoxyadenosine



2'-Deoxyadenosine 5'-triphosphate



6-Deoxy-*L*-ascorbic acid



Deoxycholic acid



2'-Deoxycytidine 5'-monophosphate



2'-Deoxy-5-fluorouridine



2-Deoxy-*D*-glucose



2'-Deoxyguanosine 5'-monophosphate


2-Deoxy-*D*-*chiro*-inositol



1-Deoxy-1-(methylamino)-*D*-glucitol



6-Deoxy-3-*O*-methylgalactose



D-2-Deoxyribose



Deserpidine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2810	Desethyl atrazine	6-Chloro-*N*-isopropyl-1,3,5-triazine-2,4-diamine	$C_6H_{10}ClN_5$	6190-65-4	187.630	cry	136				
2811	Desferrioxamine	Deferoxamine	$C_{25}H_{48}N_6O_8$	70-51-9	560.684	cry (EtOH aq)	139				
2812	Desipramine		$C_{18}H_{22}N_2$	50-47-5	266.381			173$^{0.02}$			
2813	Desmedipham		$C_{16}H_{16}N_2O_4$	13684-56-5	300.309		120				
2814	Desmetryne		$C_8H_{15}N_5S$	1014-69-3	213.304	cry	85				
2815	Desthiobiotin		$C_{10}H_{18}N_2O_3$	533-48-2	214.261	lo nd (H_2O)	157				s H_2O
2816	Dexamethasone		$C_{22}H_{29}FO_5$	50-02-2	392.460		262				
2817	Dexon	Sodium dimethylaminobenzenediazosulfonate	$C_8H_{10}N_3NaO_3S$	140-56-7	251.238	ye-br pow					sl H_2O; s DMF
2818	Dexpanthenol		$C_9H_{19}NO_4$	81-13-0	205.252	hyg oil		dec	1.20^{20}	1.497^{20}	vs H_2O, EtOH, MeOH; sl eth
2819	Dextroamphetamine sulfate		$C_{18}H_{28}N_2O_4S$	51-63-8	368.491		>300		1.15^{25}		vs H_2O
2820	Dextromethorphan hydrobromide		$C_{18}H_{26}BrNO$	125-69-9	352.309	wh cry pow	123				s EtOH, chl; i eth
2821	Diacetone alcohol	4-Hydroxy-4-methyl-2-pentanone	$C_6H_{12}O_2$	123-42-2	116.158	liq	-44	167.9	0.9387^{20}	1.4213^{20}	msc H_2O, EtOH, eth; s chl
2822	3,3-Diacetoxy-1-propene		$C_7H_{10}O_4$	869-29-4	158.152	liq	-37.6	180	1.0760^{20}	1.4193^{20}	vs ace, bz, eth, EtOH
2823	1,3-Diacetylbenzene		$C_{10}H_{10}O_2$	6781-42-6	162.185		32	152^{15}			sl H_2O, peth; s EtOH, bz, chl, HOAc
2824	1,4-Diacetylbenzene	4-Acetylacetophenone	$C_{10}H_{10}O_2$	1009-61-6	162.185		113.0	128^{3}			vs EtOH; sl chl
2825	*N,N'*-Diacetyl-4,4'-diaminobiphenyl		$C_{16}H_{16}N_2O_2$	613-35-4	268.310	nd (HOAc)	328.3				
2826	Diacetylmorphine		$C_{21}H_{23}NO_5$	561-27-3	369.412	orth	173	273^{12}	1.56^{25}		vs bz, chl
2827	Diacetylperoxide	Acetyl peroxide	$C_4H_6O_4$	110-22-5	118.089	nd (eth) lf	30	63^{21}			vs eth, EtOH
2828	Dialifor		$C_{14}H_{17}ClNO_4PS_2$	10311-84-9	393.846		68				
2829	Diallate		$C_{10}H_{17}Cl_2NOS$	2303-16-4	270.219			150^{9}			
2830	Diallylcyanamide		$C_7H_{10}N_2$	538-08-9	122.167			142^{90}, 95^{9}			s EtOH; sl eth, ctc
2831	Diallyl diethylene glycol carbonate	Diethylene glycol bis(allyl carbonate)	$C_{12}H_{18}O_7$	142-22-3	274.267	col liq	-4	161^{2}	1.14^{20}		i H_2O; s os
2832	Diallyldimethylsilane		$C_8H_{16}Si$	1113-12-8	140.299			137; 68^{50}	0.7679^{20}	1.4420^{20}	
2833	Diallyl disulfide		$C_6H_{10}S_2$	2179-57-9	146.273			100^{48}, 79^{16}	1.0237^{15}		
2834	Diallyl ether	Allyl ether	$C_6H_{10}O$	557-40-4	98.142	liq	-6	94	0.8260^{20}	1.4163^{20}	i H_2O; msc EtOH, eth; vs ace; s chl
2835	Diallyl fumarate		$C_{10}H_{12}O_4$	2807-54-7	196.200			140^{3}	1.0768^{20}	1.4670^{25}	vs ace, bz, eth, EtOH
2836	Diallyl isophthalate	Di-2-propenyl 1,3-benzenedicarboxylate	$C_{14}H_{14}O_4$	1087-21-4	246.259			176^{5}			
2837	Diallyl maleate		$C_{10}H_{12}O_4$	999-21-3	196.200			129^{10}, 109^{3}	1.075^{20}	1.4699^{20}	s chl
2838	Diallyl oxalate		$C_8H_{10}O_4$	615-99-6	170.163			217	1.1582^{20}	1.4481^{20}	i H_2O; s EtOH, ace, bz; sl chl
2839	*N,N*-Diallyl-2-propen-1-amine	Triallylamine	$C_9H_{15}N$	102-70-5	137.222		94	155.5	0.809^{20}	1.4502^{20}	s EtOH, eth, ace, bz, acid
2840	5,5-Diallyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	Allobarbital	$C_{10}H_{12}N_2O_3$	52-43-7	208.213	lf	172				sl H_2O, DMSO; s EtOH, eth, bz
2841	Diallyl sulfide		$C_6H_{10}S$	592-88-1	114.208	liq	-85	138.6	0.8877^{27}	1.4870^{25}	vs eth, EtOH
2842	Diallyl trisulfide		$C_6H_{10}S_3$	2050-87-5	178.338			117^{16}	1.0845^{15}		vs eth
2843	Diamantane	Congressane	$C_{14}H_{20}$	2292-79-7	188.309	cry	236				
2844	1,2-Diamino-9,10-anthracenedione		$C_{14}H_{10}N_2O_2$	1758-68-5	238.241	viol nd	303.5				sl EtOH, eth, chl, xyl; s py, con sulf
2845	1,4-Diamino-9,10-anthracenedione		$C_{14}H_{10}N_2O_2$	128-95-0	238.241	dk viol nd (py)	268				sl H_2O; s EtOH, bz, $PhNO_2$; vs py
2846	1,5-Diamino-9,10-anthracenedione		$C_{14}H_{10}N_2O_2$	129-44-2	238.241	dk red nd (al, HOAc)	319	sub			i H_2O; sl EtOH, eth, ace, bz; s $PhNO_2$
2847	1,8-Diamino-9,10-anthracenedione		$C_{14}H_{10}N_2O_2$	129-42-0	238.241	red nd (al, HOAc)	265				i H_2O; s EtOH, py; sl eth, HOAc
2848	2,6-Diamino-9,10-anthracenedione		$C_{14}H_{10}N_2O_2$	131-14-6	238.241	red-br pr (aq-py)	320 dec				sl H_2O; s EtOH, chl, con sulf, xyl, py
2849	4,4'-Diaminoazobenzene		$C_{12}H_{12}N_4$	538-41-0	212.250	ye nd (al), oran-ye pr (al)	250.5				sl H_2O, lig; s EtOH; vs bz, chl
2850	3,5-Diaminobenzoic acid		$C_7H_8N_2O_2$	535-87-5	152.151	nd (+1w)	228				sl H_2O, tfa; s EtOH; vs eth



Desethyl atrazine



Desferrioxamine



Desipramine



Desmedipham



Desmetryne



Desthiobiotin



Dexamethasone



Dexon



Dexpanthenol



Dextroamphetamine sulfate



Dextromethorphan hydrobromide



Diacetone alcohol



3,3-Diacetoxy-1-propene



1,3-Diacetylbenzene



1,4-Diacetylbenzene



N,N'-Diacetyl-4,4'-diaminobiphenyl



Diacetylmorphine



Diacetylperoxide



Dialifor



Diallate



Diallylcyanamide



Diallyl diethylene glycol carbonate



Diallyldimethylsilane



Diallyl disulfide



Diallyl ether



Diallyl fumarate


Diallyl isophthalate


Diallyl maleate


Diallyl oxalate



N,N-Diallyl-2-propen-1-amine



5,5-Diallyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione


Diallyl sulfide


Diallyl trisulfide



Diamantane



1,2-Diamino-9,10-anthracenedione



1,4-Diamino-9,10-anthracenedione


1,5-Diamino-9,10-anthracenedione



1,8-Diamino-9,10-anthracenedione



2,6-Diamino-9,10-anthracenedione



4,4'-Diaminoazobenzene



3,5-Diaminobenzoic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2851	2,4-Diaminobutanoic acid		$C_4H_{10}N_2O_2$	305-62-4	118.134	hyg cry					s H_2O; sl EtOH, MeOH
2852	*cis*-2,3-Diamino-2-butenedinitrile		$C_4H_4N_4$	1187-42-4	108.102		178.5		1.41^{20}		
2853	1,8-Diamino-4,5-dihydroxy-9,10-anthracenedione		$C_{14}H_{10}N_2O_4$	128-94-9	270.240	bl nd (xyl)					i H_2O; s bz, xyl, EtOH
2854	4,4'-Diaminodiphenyl ether	4,4-Oxydianiline	$C_{12}H_{12}N_2O$	101-80-4	200.235		189 dec	>300			
2855	4,4'-Diaminodiphenylmethane	4,4'-Methylenedianiline	$C_{13}H_{14}N_2$	101-77-9	198.263	pl or nd (w) pl (bz)	92.5	398; 257^{18}			sl H_2O; vs EtOH, eth, bz
2856	4,4'-Diaminodiphenyl sulfide	4,4'-Thiodianiline	$C_{12}H_{12}N_2S$	139-65-1	216.301	nd (w)	108.5				sl H_2O; vs EtOH, eth, bz; s tfa
2857	3,3'-Diaminodiphenyl sulfone	3,3'-Sulfonyldianiline	$C_{12}H_{12}N_2O_2S$	599-61-1	248.300		168.5				vs H_2O, EtOH
2858	*meso*-2,6-Diaminoheptanedioic acid	2,6-Diaminopimelic acid	$C_7H_{14}N_2O_4$	922-54-3	190.197	nd (w)	314 dec				s H_2O
2859	1,4-Diamino-2-methoxy-9,10-anthracenedione		$C_{15}H_{12}N_2O_3$	2872-48-2	268.267		235				
2860	1,4-Diamino-5-nitro-9,10-anthracenedione		$C_{14}H_9N_3O_4$	82-33-7	283.239		278				
2861	2,4-Diaminophenol		$C_6H_8N_2O$	95-86-3	124.140	lf	79 dec				vs H_2O, ace, EtOH
2862	2,4-Diaminophenol, dihydrochloride		$C_6H_{10}Cl_2N_2O$	137-09-7	197.061	nd	235 dec				vs H_2O
2863	3,7-Diaminophenothiazin-5-ium chloride	Thionine	$C_{12}H_{10}ClN_3S$	581-64-6	263.745						sl H_2O, EtOH, eth; s bz, chl, acid
2864	4-[(2,4-Diaminophenyl)azo] benzenesulfonamide	Prontosil	$C_{12}H_{14}ClN_5O_2S$	103-12-8	327.790		249.5				sl H_2O; s EtOH, ace, oils, fats
2865	1,3-Diamino-2-propanol		$C_3H_{10}N_2O$	616-29-5	90.123	cry	42.8				i eth, bz
2866	4,4'-Diamino-2,2'-stilbenedisulfonic acid	Amsonic acid	$C_{14}H_{14}N_2O_6S_2$	81-11-8	370.400	ye nd	300				sl H_2O
2867	4,6-Diamino-1,3,5-triazin-2(1*H*)-one		$C_3H_5N_5O$	645-92-1	127.105	nd (aq Na_2CO_3)	dec				i H_2O, EtOH, eth, bz, HOAc; s acid, alk
2868	8,8'-Diapo-ψ,ψ-carotenedioic acid	Crocetin	$C_{20}H_{24}O_4$	27876-94-4	328.403	brick red orth	286				sl H_2O, EtOH; i eth, bz; s py; vs NaOH
2869	Diatrizoic acid	*N,N'*-Diacetyl-3,5-diamino-2,4,6-triiodobenzoic acid	$C_{11}H_9I_3N_2O_4$	117-96-4	613.913	cry (EtOH aq)	300				
2870	Diazenedicarboxamide	Azodicarbonamide	$C_2H_4N_4O_2$	123-77-3	116.079		212 dec				
2871	Diazinon		$C_{12}H_{21}N_2O_3PS$	333-41-5	304.345			$87^{0.05}$	1.1088^{20}	1.4922^{20}	
2872	Diazomethane		CH_2N_2	334-88-3	42.040	ye gas	-145	-23			vs eth, diox
2873	Dibenz[a,h]acridine		$C_{21}H_{13}N$	226-36-8	279.335	ye cry	228				
2874	Dibenz[a,j]acridine	7-Azadibenz[a,j]anthracene	$C_{21}H_{13}N$	224-42-0	279.335		216				i H_2O
2875	Dibenz[c,h]acridine		$C_{21}H_{13}N$	224-53-3	279.335	ye cry (EtOH)	189				
2876	Dibenz[a,h]anthracene	1,2:5,6-Dibenzanthracene	$C_{22}H_{14}$	53-70-3	278.346	pl (dil ace)	269.5				i H_2O; sl EtOH; s ace, bz, CS_2
2877	Dibenz[a,j]anthracene		$C_{22}H_{14}$	224-41-9	278.346	oran lf or nd (bz)	197.5				i H_2O, HOAc; sl EtOH, eth, bz; s peth
2878	5*H*-Dibenz[b,f]azepine-5-carboxamide	Carbamazepine	$C_{15}H_{12}N_2O$	298-46-4	236.268		190.2				
2879	Dibenzepin		$C_{18}H_{21}N_3O$	4498-32-2	295.379		117	$185^{0.01}$			
2880	7*H*-Dibenzo[c,g]carbazole		$C_{20}H_{13}N$	194-59-2	267.324	cry (EtOH)	158				
2881	13*H*-Dibenzo[a,i]carbazole		$C_{20}H_{13}N$	239-64-5	267.324		221.3				i H_2O
2882	Dibenzo[b,k]chrysene		$C_{26}H_{16}$	217-54-9	328.405		400				
2883	Dibenzo[b,e][1,4]dioxin	Diphenylene dioxide	$C_{12}H_8O_2$	262-12-4	184.191	nd (MeOH)	120.5				
2884	Dibenzofuran	2,2'-Biphenylene oxide	$C_{12}H_8O$	132-64-9	168.191	lf or nd (al)	86.5	287	1.0886^{99}	1.6079^{99}	i H_2O; s EtOH, ace, bz; vs eth, HOAc
2885	Dibenzo[a,e]pyrene	Naphtho[1,2,3,4-def]chrysene	$C_{24}H_{14}$	192-65-4	302.368	pa ye nd(xyl)	233.5				sl EtOH, ace, bz, HOAc; s tol, con sulf
2886	Dibenzo[a,h]pyrene	Dibenzo[b,def]chrysene	$C_{24}H_{14}$	189-64-0	302.368	oran pl	315				
2887	Dibenzo[a,i]pyrene	Benzo[rst]pentaphene	$C_{24}H_{14}$	189-55-9	302.368		281.5	$275^{0.05}$			
2888	Dibenzo[a,l]pyrene	Dibenzo[def,p]chrysene	$C_{24}H_{14}$	191-30-0	302.368	ye pl (bz/EtOH)	164.5				
2889	Dibenzothiophene		$C_{12}H_8S$	132-65-0	184.257	nd (dil al, lig)	98.2	332.5			i H_2O; s chl, MeOH; vs EtOH, bz
2890	Dibenz[c,e]oxepin-5,7-dione		$C_{14}H_8O_3$	6050-13-1	224.212	nd (HOAc or bz)	217	sub			i H_2O; sl eth
2891	Dibenzoyl disulfide	Benzoyl disulfide	$C_{14}H_{10}O_2S_2$	644-32-6	274.358	pr(al), sc(chl-peth)	134.5	dec			i H_2O; sl EtOH, eth; s CS_2



2,4-Diaminobutanoic acid



cis-2,3-Diamino-2-butenedinitrile



1,8-Diamino-4,5-dihydroxy-9,10-anthracenedione



4,4'-Diaminodiphenyl ether



4,4'-Diaminodiphenylmethane



4,4'-Diaminodiphenyl sulfide



3,3'-Diaminodiphenyl sulfone



meso-2,6-Diaminoheptanedioic acid



1,4-Diamino-2-methoxy-9,10-anthracenedione



1,4-Diamino-5-nitro-9,10-anthracenedione



2,4-Diaminophenol



2,4-Diaminophenol, dihydrochloride



3,7-Diaminophenothiazin-5-ium chloride



4-[(2,4-Diaminophenyl)azo]benzenesulfonamide



1,3-Diamino-2-propanol



4,4'-Diamino-2,2'-stilbenedisulfonic acid



4,6-Diamino-1,3,5-triazin-2(1*H*)-one



8,8'-Diapo-ψ,ψ-carotenedioic acid



Diatrizoic acid



Diazenedicarboxamide



Diazinon



Diazomethane



Dibenz[a,h]acridine



Dibenz[a,j]acridine



Dibenz[c,h]acridine



Dibenz[a,h]anthracene



Dibenz[a,j]anthracene



5*H*-Dibenz[b,f]azepine-5-carboxamide



Dibenzepin



7*H*-Dibenzo[c,g]carbazole



13*H*-Dibenzo[a,i]carbazole



Dibenzo[b,k]chrysene



Dibenzo[b,e][1,4]dioxin



Dibenzofuran



Dibenzo[a,e]pyrene



Dibenzo[a,h]pyrene


Dibenzo[a,i]pyrene



Dibenzo[a,l]pyrene



Dibenzothiophene



Dibenz[c,e]oxepin-5,7-dione



Dibenzoyl disulfide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2892	Dibenzylamine	*N*-Benzylbenzenemethanamine	$C_{14}H_{15}N$	103-49-1	197.276		-26	dec 300; 270^{250}	1.0256^{22}	1.5781^{20}	i H_2O; vs EtOH, eth; s ctc
2893	Dibenzyl disulfide		$C_{14}H_{14}S_2$	150-60-7	246.391	lf (al)	71.5				sl H_2O; s EtOH, eth, bz, MeOH
2894	*N,N'*-Dibenzyl-1,2-ethanediamine	Benzathine	$C_{16}H_{20}N_2$	140-28-3	240.343	oily lig	26	195^{4}	1.024^{20}	1.5635^{20}	vs bz, eth, EtOH
2895	Dibenzyl ether	Benzyl ether	$C_{14}H_{14}O$	103-50-4	198.260		1.8	298	1.0428^{20}	1.5168^{20}	i H_2O; msc EtOH, eth; s ctc
2896	2,6-Dibenzylidenecyclohexanone		$C_{20}H_{18}O$	897-78-9	274.356		117.5	190^{20}			sl EtOH; s bz, HOAc
2897	Dibenzyl malonate		$C_{17}H_{16}O_4$	15014-25-2	284.307			187^{2}	1.137^{25}	1.5447^{20}	
2898	Dibenzyl phosphite		$C_{14}H_{15}O_3P$	17176-77-1	262.241		-2.5	$162^{0.1}$		1.5521^{18}	
2899	Dibenzyl sulfide	Benzyl sulfide	$C_{14}H_{14}S$	538-74-9	214.326	pl (eth or chl)	49.5	dec	1.0583^{50}		i H_2O; s EtOH, eth, CS_2
2900	Dibenzyl sulfone		$C_{14}H_{14}O_2S$	620-32-6	246.325	nd (al-bz)	152	dec 290			i H_2O; sl EtOH; vs ace; s bz, HOAc
2901	Dibenzyl sulfoxide		$C_{14}H_{14}OS$	621-08-9	230.325	lf (al, w)	134	dec 210			i H_2O; vs EtOH, eth
2902	1,3-Dibenzylurea		$C_{15}H_{16}N_2O$	1466-67-7	240.300	nd (al)	169.5				vs EtOH, HOAc
2903	Dibromoacetic acid		$C_2H_2Br_2O_2$	631-64-1	217.844	hyg cry	49	195^{250}, 130^{16}			vs H_2O; vs EtOH, eth
2904	Dibromoacetonitrile		C_2HBr_2N	3252-43-5	198.844			169; 68^{24}	2.369^{20}	1.5393^{20}	
2905	2,4-Dibromoaniline		$C_6H_5Br_2N$	615-57-6	250.919	orth bipym (chl) nd or lf (al)	79.5	156^{74}	2.260^{20}		s EtOH, eth, chl, HOAc
2906	3,5-Dibromoaniline		$C_6H_5Br_2N$	626-40-4	250.919	nd (dil al)	57				vs EtOH, eth, bz
2907	9,10-Dibromoanthracene		$C_{14}H_8Br_2$	523-27-3	336.022	ye nd (to or xyl)	226	sub			i H_2O; sl EtOH, eth, bz; s chl
2908	*o*-Dibromobenzene	1,2-Dibromobenzene	$C_6H_4Br_2$	583-53-9	235.904		7.1	225	1.9843^{20}	1.6155^{20}	i H_2O; s EtOH; msc eth, ace, bz, ctc
2909	*m*-Dibromobenzene	1,3-Dibromobenzene	$C_6H_4Br_2$	108-36-1	235.904	liq	-7	218	1.9523^{20}	1.6083^{17}	i H_2O; s EtOH; msc eth
2910	*p*-Dibromobenzene	1,4-Dibromobenzene	$C_6H_4Br_2$	106-37-6	235.904	pl	87.43	218.5	2.261^{17}	1.5742	i H_2O; s EtOH, bz; vs eth, ace, CS_2
2911	4,4'-Dibromobenzophenone	Bis(4-bromophenyl) ketone	$C_{13}H_8Br_2O$	3988-03-2	340.010	pl (al)	177	395			vs bz, HOAc, chl
2912	4,4'-Dibromo-1,1'-biphenyl		$C_{12}H_8Br_2$	92-86-4	312.000	mcl pr (MeOH)	164	357.5			i H_2O; sl EtOH; s bz
2913	1,3-Dibromo-2,2-bis(bromomethyl)propane	Pentaerythritol tetrabromide	$C_5H_8Br_4$	3229-00-3	387.734	cry (ace), nd (lig)	163	305.5	2.596^{15}		s EtOH, bz, tol; sl eth, chl
2914	3,5-Dibromo-*N*-(4-bromophenyl)-2-hydroxybenzamide	Tribromsalan	$C_{13}H_8Br_3NO_2$	87-10-5	449.921		227				
2915	1,1-Dibromobutane		$C_4H_8Br_2$	62168-25-6	215.915			158; 91^{101}	1.784^{25}	1.4988^{25}	
2916	1,2-Dibromobutane	α-Butylene dibromide	$C_4H_8Br_2$	533-98-2	215.915	liq	-65.4	166.3	1.7915^{20}	1.4025^{20}	i H_2O; s eth, chl
2917	1,3-Dibromobutane		$C_4H_8Br_2$	107-80-2	215.915			174	1.800^{20}	1.507^{20}	i H_2O; s eth, chl; sl ctc
2918	1,4-Dibromobutane		$C_4H_8Br_2$	110-52-1	215.915	liq	-16.5	197	1.8199^{25}	1.5167^{25}	i H_2O; sl ctc; s chl
2919	2,3-Dibromobutane		$C_4H_8Br_2$	5408-86-6	215.915	liq	-24	161	1.7893^{22}	1.5133^{22}	i H_2O; s eth
2920	*trans*-1,4-Dibromo-2-butene		$C_4H_6Br_2$	821-06-7	213.899	pl (peth)	53.4	203; 74^{14}			sl H_2O, chl; vs EtOH, peth; s ace
2921	1,4-Dibromo-2-butyne		$C_4H_4Br_2$	2219-66-1	211.883			92^{15}	2.014^{18}	1.588^{18}	s eth, ace; vs chl
2922	α,α'-Dibromo-*d*-camphor		$C_{10}H_{14}Br_2O$	514-12-5	310.025		61		1.854^{21}		i H_2O; vs EtOH, eth, bz, chl; s AcOEt
2923	Dibromochlorofluoromethane		CBr_2ClF	353-55-9	226.270			80.3	2.3173^{22}	1.4570^{20}	
2924	1,2-Dibromo-3-chloropropane		$C_3H_5Br_2Cl$	96-12-8	236.333			196	2.093^{14}	1.553^{14}	i H_2O
2925	1,2-Dibromo-1-chloro-1,2,2-trifluoroethane		$C_2Br_2ClF_3$	354-51-8	276.277		50	93			
2926	2,2-Dibromo-2-cyanoacetamide		$C_3H_2Br_2N_2O$	10222-01-2	241.868	cry (bz)	126				
2927	*trans*-1,2-Dibromocyclohexane, (±)		$C_6H_{10}Br_2$	5183-77-7	241.951		-2.0	145^{100}, 105^{20}	1.7759^{20}	1.5445^{19}	vs ace, bz, eth, EtOH
2928	1,10-Dibromodecane	Decamethylene dibromide	$C_{10}H_{20}Br_2$	4101-68-2	300.074	pl (al)	28	161^{9}, 128^{4}	1.335^{30}	1.4927^{25}	i H_2O; sl EtOH; s eth
2929	1,2-Dibromo-1,1-dichloroethane		$C_2H_2Br_2Cl_2$	75-81-0	256.751	liq	-26	195	2.135^{20}	1.5662^{20}	vs ace, bz, eth, EtOH
2930	1,2-Dibromo-1,2-dichloroethane		$C_2H_2Br_2Cl_2$	683-68-1	256.751	liq	-26	195	2.135^{20}	1.5662^{20}	i H_2O; s EtOH, eth, ace, bz
2931	Dibromodichloromethane		CBr_2Cl_2	594-18-3	242.725		38	150.2	2.42^{25}		i H_2O; s EtOH, eth, ace, bz
2932	1,2-Dibromo-1,1-difluoroethane	Genetron 132b-B2	$C_2H_2Br_2F_2$	75-82-1	223.842	liq	-61.3	92.5	2.2238^{20}	1.4456^{20}	



Dibenzylamine



Dibenzyl disulfide



N,N'-Dibenzyl-1,2-ethanediamine



Dibenzyl ether



2,6-Dibenzylidenecyclohexanone



Dibenzyl malonate



Dibenzyl phosphite



Dibenzyl sulfide



Dibenzyl sulfone



Dibenzyl sulfoxide



1,3-Dibenzylurea


Dibromoacetic acid



Dibromoacetonitrile



2,4-Dibromoaniline



3,5-Dibromoaniline



9,10-Dibromoanthracene



o-Dibromobenzene



m-Dibromobenzene



p-Dibromobenzene



4,4'-Dibromobenzophenone



4,4'-Dibromo-1,1'-biphenyl



1,3-Dibromo-2,2-bis(bromomethyl)propane


3,5-Dibromo-*N*-(4-bromophenyl)-2-hydroxybenzamide



1,1-Dibromobutane



1,2-Dibromobutane



1,3-Dibromobutane


1,4-Dibromobutane



2,3-Dibromobutane



trans-1,4-Dibromo-2-butene



1,4-Dibromo-2-butyne


α,α'-Dibromo-*d*-camphor



Dibromochlorofluoromethane



1,2-Dibromo-3-chloropropane



1,2-Dibromo-1-chloro-1,2,2-trifluoroethane


2,2-Dibromo-2-cyanoacetamide


trans-1,2-Dibromocyclohexane, (±)


1,10-Dibromodecane


1,2-Dibromo-1,1-dichloroethane



1,2-Dibromo-1,2-dichloroethane


Dibromodichloromethane



1,2-Dibromo-1,1-difluoroethane

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2933	Dibromodifluoromethane		CBr_2F_2	75-61-6	209.816	vol liq or gas	-110.1	22.76			s H_2O, eth, ace, bz
2934	1,3-Dibromo-5,5-dimethyl-2,4-imidazolidinedione	Dibromantine	$C_5H_6Br_2N_2O_2$	77-48-5	285.922		198 dec				
2935	1,3-Dibromo-2,2-dimethylpropane		$C_5H_{10}Br_2$	5434-27-5	229.941			184; 80^{26}	1.6775^{20}	1.5090	
2936	1,12-Dibromododecane		$C_{12}H_{24}Br_2$	3344-70-5	328.127	nd (al,HOAc)	41	215^{15}			i H_2O; vs EtOH, chl; s eth, HOAc
2937	1,1-Dibromoethane	Ethylidene dibromide	$C_2H_4Br_2$	557-91-5	187.861	liq	-63	108.0	2.0555^{20}	1.5128^{20}	i H_2O; s EtOH, ace, bz; sl chl; vs eth
2938	1,2-Dibromoethane	Ethylene dibromide	$C_2H_4Br_2$	106-93-4	187.861		9.84	131.6	2.1683^{25}	1.5356^{25}	vs ace, bz, eth, EtOH
2939	*cis*-1,2-Dibromoethene	*cis*-1,2-Dibromoethylene	$C_2H_2Br_2$	590-11-4	185.845	liq	-53	112.5	2.2464^{20}	1.5428^{20}	i H_2O; vs EtOH, eth; s ace, bz, chl
2940	*trans*-1,2-Dibromoethene	*trans*-1,2-Dibromoethylene	$C_2H_2Br_2$	590-12-5	185.845	liq	-6.5	108	2.2308^{20}	1.5505^{18}	i H_2O; vs EtOH, eth; s ace, bz, chl
2941	1,2-Dibromo-1-ethoxyethane		$C_4H_8Br_2O$	2983-26-8	231.914			80^{20}	1.7320^{20}	1.5044^{20}	vs EtOH, chl
2942	1,2-Dibromoethyl acetate		$C_4H_6Br_2O_2$	24442-57-7	245.898	liq		89.5^{16}	1.91^{20}		
2943	(1,2-Dibromoethyl)benzene		$C_8H_8Br_2$	93-52-7	263.958		75	133^{19}			s EtOH, eth, bz, chl, HOAc, MeOH, lig
2944	Dibromofluoromethane		$CHBr_2F$	1868-53-7	191.825	liq	-78	64.9	2.421^{20}	1.4685^{20}	i H_2O; s EtOH, eth, ace, bz, chl
2945	1,2-Dibromoheptane		$C_7H_{14}Br_2$	42474-21-5	257.994			228	1.5086^{20}	1.4986^{20}	
2946	1,7-Dibromoheptane	Heptamethylene dibromide	$C_7H_{14}Br_2$	4549-31-9	257.994		41.7	263	1.5306^{20}	1.5034^{20}	i H_2O; s eth, ace, bz, ctc, chl
2947	2,3-Dibromoheptane		$C_7H_{14}Br_2$	21266-88-6	257.994			101^{17}	1.5139^{20}	1.4992^{20}	
2948	3,4-Dibromoheptane		$C_7H_{14}Br_2$	21266-90-0	257.994			107^{24}	1.5182^{20}	1.5010^{20}	
2949	1,2-Dibromo-1,1,2,3,3,3-hexafluoropropane		$C_3Br_2F_6$	661-95-0	309.830			72.8	2.1630^{20}		i H_2O
2950	1,2-Dibromohexane		$C_6H_{12}Br_2$	624-20-4	243.967			103^{36}	1.5774^{20}	1.5024^{20}	vs bz, eth, chl
2951	1,6-Dibromohexane		$C_6H_{12}Br_2$	629-03-8	243.967	liq	-1.2	245.5	1.6025^{25}	1.5054^{25}	i H_2O; s eth, ace, chl; sl ctc
2952	3,4-Dibromohexane		$C_6H_{12}Br_2$	89583-12-0	243.967			80^{13}	1.6027^{20}	1.5043^{20}	
2953	3,5-Dibromo-2-hydroxybenzaldehyde	3,5-Dibromosalicylaldehyde	$C_7H_4Br_2O_2$	90-59-5	279.914	pa ye pr	86	sub			vs bz, eth, chl
2954	3,5-Dibromo-2-hydroxybenzoic acid	3,5-Dibromosalicylic acid	$C_7H_4Br_2O_3$	3147-55-5	295.913	nd	228				s ace
2955	3,5-Dibromo-4-hydroxybenzonitrile	Bromoxynil	$C_7H_3Br_2NO$	1689-84-5	276.913		190				
2956	Dibromomethane	Methylene bromide	CH_2Br_2	74-95-3	173.835	liq	-52.5	97	2.4969^{20}	1.5420^{20}	sl H_2O; msc EtOH, eth, ace; s ctc
2957	1,4-Dibromo-2-methylbenzene	2,5-Dibromotoluene	$C_7H_6Br_2$	615-59-8	249.931		5.6	236	1.8127^{17}	1.5982^{18}	i H_2O
2958	2,4-Dibromo-1-methylbenzene		$C_7H_6Br_2$	31543-75-6	249.931		-9.7	103^{11}	1.8176^{25}	1.5964^{25}	
2959	(Dibromomethyl)benzene		$C_7H_6Br_2$	618-31-5	249.931		1.0	156^{23}	1.8365^{28}	1.6147^{20}	i H_2O; msc EtOH, eth
2960	2,3-Dibromo-2-methylbutane		$C_5H_{10}Br_2$	594-51-4	229.941		7	62^{17}	1.6717^{20}	1.5729^{25}	
2961	2,4-Dibromo-6-methylphenol		$C_7H_6Br_2O$	609-22-3	265.930	nd (peth)	58	dec 265; 105^{4}			s chl
2962	1,2-Dibromo-2-methylpropane		$C_4H_8Br_2$	594-34-3	215.915		10.5	150	1.7827^{20}	1.5119^{20}	s EtOH, eth, chl
2963	1,4-Dibromonaphthalene		$C_{10}H_6Br_2$	83-53-4	285.963		83	310			i H_2O; s EtOH, eth; sl HOAc
2964	2,6-Dibromo-4-nitroaniline		$C_6H_4Br_2N_2O_2$	827-94-1	295.916	ye nd (al, HOAc)	207				sl H_2O; s HOAc
2965	2,6-Dibromo-4-nitrophenol		$C_6H_3Br_2NO_3$	99-28-5	296.901	pa ye pr or lf (al)	145 dec				i H_2O; vs EtOH, eth; sl ace, bz, HOAc
2966	1,9-Dibrononane		$C_9H_{18}Br_2$	4549-33-1	286.047	liq	-22.5	285; 154^{10}	1.4229^{20}		
2967	1,4-Dibromooctafluorobutane		$C_4Br_2F_8$	335-48-8	359.838			97			
2968	1,8-Dibromooctane	Octamethylene dibromide	$C_8H_{16}Br_2$	4549-32-0	272.021		15.5	271	1.4594^{25}	1.4971^{25}	i H_2O; s eth, ctc, chl
2969	1,2-Dibromopentane		$C_5H_{10}Br_2$	3234-49-9	229.941			184	1.668^{18}		
2970	1,4-Dibromopentane		$C_5H_{10}Br_2$	626-87-9	229.941		-34.4	146^{150}, 99^{14}	1.6222^{20}	1.5086^{20}	
2971	1,5-Dibromopentane		$C_5H_{10}Br_2$	111-24-0	229.941	liq	-39.5	222.3	1.6928^{25}	1.5102^{25}	i H_2O; s bz, chl; sl ctc
2972	2,4-Dibromopentane		$C_5H_{10}Br_2$	19398-53-9	229.941			75^{21}, 60^{12}	1.6659^{20}	1.4987^{20}	
2973	2,4-Dibromophenol		$C_6H_4Br_2O$	615-58-7	251.903	nd (peth)	38	238.5	2.0700^{20}		sl H_2O, ctc; vs EtOH, eth, bz
2974	2,6-Dibromophenol		$C_6H_4Br_2O$	608-33-3	251.903	nd (w)	56.5	255; 162^{21}			s H_2O; vs EtOH, eth



Dibromodifluoromethane


1,3-Dibromo-5,5-dimethyl-2,4-imidazolidinedione


1,3-Dibromo-2,2-dimethylpropane



1,12-Dibromododecane



1,1-Dibromoethane



1,2-Dibromoethane


cis-1,2-Dibromoethene



trans-1,2-Dibromoethene



1,2-Dibromo-1-ethoxyethane



1,2-Dibromoethyl acetate



(1,2-Dibromoethyl)benzene



Dibromofluoromethane



1,2-Dibromoheptane



1,7-Dibromoheptane



2,3-Dibromoheptane



3,4-Dibromoheptane



1,2-Dibromo-1,1,2,3,3,3-hexafluoropropane



1,2-Dibromohexane


1,6-Dibromohexane



3,4-Dibromohexane



3,5-Dibromo-2-hydroxybenzaldehyde



3,5-Dibromo-2-hydroxybenzoic acid


3,5-Dibromo-4-hydroxybenzonitrile



Dibromomethane



1,4-Dibromo-2-methylbenzene



2,4-Dibromo-1-methylbenzene



(Dibromomethyl)benzene



2,3-Dibromo-2-methylbutane


2,4-Dibromo-6-methylphenol



1,2-Dibromo-2-methylpropane



1,4-Dibromonaphthalene



2,6-Dibromo-4-nitroaniline



2,6-Dibromo-4-nitrophenol


1,9-Dibromononane



1,4-Dibromooctafluorobutane



1,8-Dibromooctane



1,2-Dibromopentane


1,4-Dibromopentane



1,5-Dibromopentane



2,4-Dibromopentane


2,4-Dibromophenol



2,6-Dibromophenol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
2975	1,2-Dibromopropane	Propylene dibromide	$C_3H_6Br_2$	78-75-1	201.888	liq	-55.49	141.9	1.9324^{20}	1.5201^{20}	s EtOH, eth, chl; sl ctc
2976	1,3-Dibromopropane		$C_3H_6Br_2$	109-64-8	201.888	liq	-34.5	167.3	1.9701^{25}	1.5204^{25}	i H_2O; s EtOH, eth, chl; sl ctc
2977	2,2-Dibromopropane		$C_3H_6Br_2$	594-16-1	201.888			113	1.880^{20}		vs eth, EtOH, chl
2978	2,3-Dibromopropanoic acid		$C_3H_4Br_2O_2$	600-05-5	231.871		66.5	160^{20}, 138^{12}			vs bz, eth, EtOH
2979	2,3-Dibromo-1-propanol		$C_3H_6Br_2O$	96-13-9	217.887			219	2.120^{20}		
2980	1,3-Dibromo-2-propanol		$C_3H_6Br_2O$	96-21-9	217.887	ye liq		dec 219; 105^{16}	2.1364^{20}	1.5495^{25}	vs ace, eth, EtOH
2981	2,3-Dibromo-1-propanol, phosphate (3:1)	Tris(2,3-dibromopropyl) phosphate	$C_9H_{15}Br_6O_4P$	126-72-7	697.610						s chl
2982	1,3-Dibromo-2-propanone	1,3-Dibromoacetone	$C_3H_4Br_2O$	816-39-7	215.871	nd	26	97^{22}	2.1670^{18}		vs eth, CS_2
2983	1,1-Dibromo-1-propene		$C_3H_4Br_2$	13195-80-7	199.872			125	1.9767^{20}	1.5260^{20}	sl H_2O; s bz, ctc, chl
2984	1,2-Dibromo-1-propene		$C_3H_4Br_2$	26391-16-2	199.872			131.5	2.0076^{20}		
2985	2,3-Dibromo-1-propene		$C_3H_4Br_2$	513-31-5	199.872			141; 37.7^{11}	2.0345^{25}	1.5416^{25}	i H_2O; s eth, ace, chl
2986	3,5-Dibromopyridine		$C_5H_3Br_2N$	625-92-3	236.893	nd (al)	112	222			sl H_2O; s EtOH, eth
2987	5,7-Dibromo-8-quinolinol	Broxyquinoline	$C_9H_5Br_2NO$	521-74-4	302.950	nd (al)	196	sub			i H_2O; s EtOH, ace, bz, chl, HOAc; sl eth
2988	2,6-Dibromoquinone-4-chlorimide	2,6-Dibromo-4-(chloroimino)-2,5-cyclohexadien-1-one	$C_6H_2Br_2ClNO$	537-45-1	299.347	ye pr (al or HOAc)	83				vs EtOH
2989	1,14-Dibromotetradecane	Tetradecamethylene dibromide	$C_{14}H_{28}Br_2$	37688-96-3	356.180	lf (al-eth) cry (al)	50.4	190^{8}			vs eth, EtOH, chl
2990	1,2-Dibromotetrafluoroethane	Refrigerant 114B2	$C_2Br_2F_4$	124-73-2	259.823	liq	-110.32	47.35	2.149^{25}	1.361^{25}	i H_2O
2991	2,3-Dibromothiophene		$C_4H_2Br_2S$	3140-93-0	241.932	liq	-17.5	218.5; 89^{13}		1.6304^{22}	
2992	2,5-Dibromothiophene		$C_4H_2Br_2S$	3141-27-3	241.932	liq	-6	210.3	2.142^{23}	1.6288^{20}	i H_2O; vs EtOH, eth; s ctc
2993	3,4-Dibromothiophene		$C_4H_2Br_2S$	3141-26-2	241.932		4.5	221.5			
2994	1,2-Dibromo-1,1,2-trifluoroethane	Halon 2302	$C_2HBr_2F_3$	354-04-1	241.832			76	2.274^{27}	1.4191^{24}	
2995	2,6-Dibromo-3,4,5-trihydroxybenzoic acid	Dibromogallic acid	$C_7H_4Br_2O_5$	602-92-6	327.912	nd, pr or lf (w+1)	150				vs H_2O, eth, EtOH
2996	3,5-Dibromo-*L*-tyrosine		$C_9H_9Br_2NO_3$	300-38-9	338.980	nd or pl	245				sl H_2O, EtOH; i eth; s alk, acid
2997	Dibucaine	Cinchocaine	$C_{20}H_{29}N_3O_2$	85-79-0	343.463	hyg cry	64				
2998	Dibucaine hydrochloride		$C_{20}H_{30}ClN_3O_2$	61-12-1	379.924		94 dec				s chl
2999	1,4-Dibutoxybenzene		$C_{14}H_{22}O_2$	104-36-9	222.324		45.5	158^{15}			s ctc
3000	1,2-Dibutoxyethane	Ethylene glycol dibutyl ether	$C_{10}H_{22}O_2$	112-48-1	174.281	liq	-69.1	203.3	0.8319^{25}	1.4112^{25}	
3001	Dibutoxymethane	Butylal	$C_9H_{20}O_2$	2568-90-3	160.254	liq	-58.1	179.2	0.8339^{20}	1.4072^{17}	
3002	Dibutyl adipate		$C_{14}H_{26}O_4$	105-99-7	258.354		-32.4	165^{10}	0.9613^{20}	1.4369^{20}	i H_2O; msc EtOH, eth
3003	Dibutylamine	*N*-Butylbutanamine	$C_8H_{19}N$	111-92-2	129.244	liq	-62	159.6	0.7670^{20}	1.4177^{20}	s H_2O, ace, bz; vs EtOH, eth
3004	Di-*sec*-butylamine	*N*-*sec*-Butyl-2-butanamine	$C_8H_{19}N$	626-23-3	129.244			134	0.7534^{20}	1.4162^{20}	vs H_2O; s EtOH
3005	2-Dibutylaminoethanol		$C_{10}H_{23}NO$	102-81-8	173.296			114^{18}			
3006	*N,N*-Dibutylaniline		$C_{14}H_{23}N$	613-29-6	205.340	liq	-32.2	274.8	0.9037^{20}	1.5186^{20}	i H_2O; msc EtOH, eth; vs ace, bz; s ctc
3007	1,4-Di-*tert*-butylbenzene		$C_{14}H_{22}$	1012-72-2	190.325	nd (MeOH)	79.5	238; 109^{15}	0.9850^{20}		i H_2O; s EtOH, eth
3008	2,5-Di-*tert*-butyl-1,4-benzenediol		$C_{14}H_{22}O_2$	88-58-4	222.324	cry (aq HOAc)	213.5				
3009	Dibutylbis(dodecylthio)stannane	Dibutyltin bis(dodecyl sulfide)	$C_{32}H_{68}S_2Sn$	1185-81-5	635.722	col liq		$122^{0.3}$	1.05^{20}		s tol, hp
3010	Dibutyl carbonate		$C_9H_{18}O_3$	542-52-9	174.237			207	0.9251^{20}	1.4117^{20}	i H_2O; s EtOH, eth
3011	Di-*tert*-butyl carbonate		$C_9H_{18}O_3$	34619-03-9	174.237	cry (al)	40	158			vs EtOH
3012	2,5-Di-*tert*-butyl-2,5-cyclohexadiene-1,4-dione		$C_{14}H_{20}O_2$	2460-77-7	220.308	ye cry (al)	152.5				i H_2O; s EtOH, eth, bz, chl, HOAc
3013	2,6-Di-*tert*-butyl-2,5-cyclohexadiene-1,4-dione		$C_{14}H_{20}O_2$	719-22-2	220.308		69	$60^{0.01}$			
3014	2,6-Di-*tert*-butyl-4-(dimethylaminomethyl)phenol		$C_{17}H_{29}NO$	88-27-7	263.418	pl (EtOH)	94	179^{40}			
3015	2,2-Dibutyl-1,3,2-dioxastannepin-4,7-dione		$C_{12}H_{20}O_4Sn$	78-04-6	346.995	ye solid	110				
3016	Dibutyl disulfide		$C_8H_{18}S_2$	629-45-8	178.359	oil		226; 117^{20}	0.938^{20}	1.4923^{20}	i H_2O; msc EtOH, eth
3017	Di-*tert*-butyl disulfide		$C_8H_{18}S_2$	110-06-5	178.359		-2.5	88^{21}	0.9226^{20}	1.4899^{20}	
3018	*cis*-1,2-Di-*tert*-butylethene	*cis*-2,2,5,5-Tetramethyl-3-hexene	$C_{10}H_{20}$	692-47-7	140.266	liq		144	0.744^{20}	1.4270^{20}	



1,2-Dibromopropane



1,3-Dibromopropane



2,2-Dibromopropane


2,3-Dibromopropanoic acid


2,3-Dibromo-1-propanol



1,3-Dibromo-2-propanol



2,3-Dibromo-1-propanol, phosphate (3:1)



1,3-Dibromo-2-propanone



1,1-Dibromo-1-propene



1,2-Dibromo-1-propene



2,3-Dibromo-1-propene


3,5-Dibromopyridine



5,7-Dibromo-8-quinolinol


2,6-Dibromoquinone-4-chlorimide



1,14-Dibromotetradecane



1,2-Dibromotetrafluoroethane



2,3-Dibromothiophene



2,5-Dibromothiophene



3,4-Dibromothiophene


1,2-Dibromo-1,1,2-trifluoroethane



2,6-Dibromo-3,4,5-trihydroxybenzoic acid



3,5-Dibromo-*L*-tyrosine



Dibucaine



Dibucaine hydrochloride


HCl



1,4-Dibutoxybenzene



1,2-Dibutoxyethane



Dibutoxymethane



Dibutyl adipate



Dibutylamine



Di-*sec*-butylamine



2-Dibutylaminoethanol



N,*N*-Dibutylaniline



1,4-Di-*tert*-butylbenzene



2,5-Di-*tert*-butyl-1,4-benzenediol



Dibutylbis(dodecylthio)stannane



Dibutyl carbonate



Di-*tert*-butyl carbonate



2,5-Di-*tert*-butyl-2,5-cyclohexadiene-1,4-dione


2,6-Di-*tert*-butyl-2,5-cyclohexadiene-1,4-dione


2,6-Di-*tert*-butyl-4-(dimethylaminomethyl)phenol



2,2-Dibutyl-1,3,2-dioxastannepin-4,7-dione



Dibutyl disulfide



Di-*tert*-butyl disulfide



cis-1,2-Di-*tert*-butylethene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3019	Dibutyl ether		$C_8H_{18}O$	142-96-1	130.228	liq	-95.2	140.28	0.7684^{20}	1.3992^{20}	i H_2O; msc EtOH, eth; vs ace; sl ctc
3020	Di-*sec*-butyl ether		$C_8H_{18}O$	6863-58-7	130.228	liq		121.1	0.756^{25}		
3021	Di-*tert*-butyl ether		$C_8H_{18}O$	6163-66-2	130.228	liq		107.23	0.7658^{20}	1.3949^{20}	
3022	*N,N'*-Di-*tert*-butylethylenediamine	*N,N'*-Di-*tert*-butylethanediamine	$C_{10}H_{24}N_2$	4062-60-6	172.311	cry	53.3	189	0.69		
3023	2,6-Di-*tert*-butyl-4-ethylphenol		$C_{16}H_{26}O$	4130-42-1	234.376		44	272			i alk
3024	*N,N*-Dibutylformamide		$C_9H_{19}NO$	761-65-9	157.253						s ctc, CS_2
3025	Dibutyl fumarate		$C_{12}H_{20}O_4$	105-75-9	228.285	liq	-13.5	285; 150^4	0.9775^{20}	1.4469^{20}	i H_2O; s ace, chl
3026	*N,N'*-Dibutyl-1,6-hexanediamine		$C_{14}H_{32}N_2$	4835-11-4	228.417			$138^{3.5}$		1.4470^{25}	
3027	3,5-Di-*tert*-butyl-2-hydroxybenzoic acid		$C_{15}H_{22}O_3$	19715-19-6	250.334		163.3				s chl
3028	Di-*tert*-butyl ketone		$C_9H_{18}O$	815-24-7	142.238	liq	-25.2	152	0.8240^{18}	1.4194^{20}	i H_2O; s EtOH, eth, ace, chl, HOAc
3029	Dibutyl maleate		$C_{12}H_{20}O_4$	105-76-0	228.285		<-80	280; 142^{10}			
3030	Dibutyl malonate		$C_{11}H_{20}O_4$	1190-39-2	216.275	liq	-83	251.5	0.9824^{20}	1.4262^{20}	i H_2O; s EtOH, eth, ace, bz, HOAc, ctc
3031	Di-*tert*-butyl malonate		$C_{11}H_{20}O_4$	541-16-2	216.275		-6	113^{31}, 66^2	1.4184^{20}	1.4184^{29}	s ace, chl
3032	Dibutylmercury		$C_8H_{18}Hg$	629-35-6	314.82			223; 105^{10}	1.7779^{20}	1.5057^{20}	
3033	2,4-Di-*tert*-butyl-5-methylphenol	DBMC	$C_{15}H_{24}O$	497-39-2	220.351		62.1	282	0.912^{80}		i H_2O; s EtOH, eth, ace, bz, ctc
3034	2,4-Di-*tert*-butyl-6-methylphenol		$C_{15}H_{24}O$	616-55-7	220.351		51	269	0.891^{80}		i alk
3035	2,6-Di-*tert*-butyl-4-methylphenol		$C_{15}H_{24}O$	128-37-0	220.351		71	265	0.8937^{75}	1.4859^{75}	i H_2O; s EtOH, ace, bz, peth; i alk
3036	Dibutyl nonanedioate		$C_{17}H_{32}O_4$	2917-73-9	300.434			170^2			sl chl
3037	Dibutyl oxalate		$C_{10}H_{18}O_4$	2050-60-4	202.248	liq	-30.5	241; 96^2	0.9873^{20}	1.4234^{20}	i H_2O; s EtOH, eth
3038	Di-*tert*-butyl peroxide	DTBP	$C_8H_{18}O_2$	110-05-4	146.228	liq	-40	111	0.704^{20}	1.3890^{20}	i H_2O; msc ace; s ctc, lig
3039	2,6-Di-*sec*-butylphenol		$C_{14}H_{22}O$	5510-99-6	206.324	liq	-42	257.5		1.5080^{20}	
3040	2,4-Di-*tert*-butylphenol		$C_{14}H_{22}O$	96-76-4	206.324		56.5	263.5		1.5080^{20}	sl ctc; i alk
3041	2,6-Di-*tert*-butylphenol		$C_{14}H_{22}O$	128-39-2	206.324	pr (al)	39	161^{50}, 133^{20}		1.5001^{20}	sl EtOH; s ctc; i alk
3042	3,5-Di-*tert*-butylphenol		$C_{14}H_{22}O$	1138-52-9	206.324		88				
3043	Dibutyl phosphate		$C_8H_{19}O_4P$	107-66-4	210.208	oil		$136^{0.05}$	1.06^{20}		s ctc, BuOH
3044	Dibutyl phosphonate		$C_8H_{19}O_3P$	1809-19-4	194.209	oil		230; 131^{19}	0.985^{25}	1.4220^{20}	
3045	Dibutyl phthalate		$C_{16}H_{22}O_4$	84-74-2	278.344	liq	-35	340	1.0465^{20}	1.4911^{20}	i H_2O; msc EtOH, eth, bz; s ctc
3046	2,6-Di-*tert*-butylpyridine		$C_{13}H_{21}N$	585-48-8	191.313			120^{20}			
3047	Dibutyl sebacate		$C_{18}H_{34}O_4$	109-43-3	314.461	liq	-10	344.5	0.9405^{15}	1.4433^{15}	i H_2O; s eth, ctc
3048	Dibutyl succinate		$C_{12}H_{22}O_4$	141-03-7	230.301	liq	-29.2	274.5	0.9752^{20}	1.4299^{20}	i H_2O; s EtOH, eth, bz, ctc
3049	Di-*tert*-butyl succinate		$C_{12}H_{22}O_4$	926-26-1	230.301		36.5	109^9			
3050	Dibutyl sulfate	Butyl sulfate	$C_8H_{18}O_4S$	625-22-9	210.292	liq		115^6			
3051	Dibutyl sulfide		$C_8H_{18}S$	544-40-1	146.294	liq	-79.7	185	0.8386^{20}	1.4530^{20}	vs eth, EtOH, chl
3052	Di-*sec*-butyl sulfide		$C_8H_{18}S$	626-26-6	146.294			165	0.8348^{20}	1.4506^{20}	i H_2O; vs EtOH, eth
3053	Di-*tert*-butyl sulfide		$C_8H_{18}S$	107-47-1	146.294	liq	-9.0	149.1	0.815^{25}	1.4506^{20}	
3054	Dibutyl sulfite	Butyl sulfite	$C_8H_{18}O_3S$	626-85-7	194.292			230	0.9957^{20}	1.4310^{20}	s EtOH, eth
3055	Dibutyl sulfone		$C_8H_{18}O_2S$	598-04-9	178.293		45	291	0.9885^{47}		i H_2O; s EtOH, eth
3056	Dibutyl sulfoxide		$C_8H_{18}OS$	2168-93-6	162.293	nd (dil al)	32.6	dec	0.8317^{23}	1.4669^{20}	i H_2O; s EtOH, eth
3057	Dibutyl tartrate		$C_{12}H_{22}O_6$	87-92-3	262.299	pr	22	320	1.0909^{20}	1.4451^{20}	vs H_2O, ace, EtOH
3058	*N,N'*-Dibutylthiourea		$C_9H_{20}N_2S$	109-46-6	188.333	nd (al)	78				
3059	Dibutyltin dichloride	Dibutyldichlorostannane	$C_8H_{18}Cl_2Sn$	683-18-1	303.845	solid	43	135^{10}			s hx, eth, thf
3060	Dibutyltin dilaurate		$C_{32}H_{64}O_4Sn$	77-58-7	631.558	ye liq or cry	23				i H_2O, MeOH; s eth, bz, ctc
3061	Dicapthon		$C_8H_9ClNO_5PS$	2463-84-5	297.653	cry (MeOH)	53				i H_2O; s ace, tol, xyl, AcOEt
3062	Dicentrine		$C_{20}H_{21}NO_4$	517-66-8	339.386						s chl
3063	Dichlofenthion		$C_{10}H_{13}Cl_2O_3PS$	97-17-6	315.153						s ctc, CS_2
3064	Dichlofluanid		$C_9H_{11}Cl_2FN_2O_2S_2$	1085-98-9	333.229	wh pow	105.3				i H_2O; s ace, MeOH, xyl
3065	Dichloroacetaldehyde		$C_2H_2Cl_2O$	79-02-7	112.942			90.5	1.436^{25}		sl EtOH



Dibutyl ether



Di-*sec*-butyl ether



Di-*tert*-butyl ether



N,N'-Di-*tert*-butylethylenediamine



2,6-Di-*tert*-butyl-4-ethylphenol



N,N-Dibutylformamide



Dibutyl fumarate



N,N'-Dibutyl-1,6-hexanediamine


3,5-Di-*tert*-butyl-2-hydroxybenzoic acid



Di-*tert*-butyl ketone



Dibutyl maleate



Dibutyl malonate



Di-*tert*-butyl malonate


Dibutylmercury



2,4-Di-*tert*-butyl-5-methylphenol



2,4-Di-*tert*-butyl-6-methylphenol



2,6-Di-*tert*-butyl-4-methylphenol



Dibutyl nonanedioate



Dibutyl oxalate



Di-*tert*-butyl peroxide



2,6-Di-*sec*-butylphenol



2,4-Di-*tert*-butylphenol



2,6-Di-*tert*-butylphenol



3,5-Di-*tert*-butylphenol



Dibutyl phosphate



Dibutyl phosphonate



Dibutyl phthalate



2,6-Di-*tert*-butylpyridine



Dibutyl sebacate



Dibutyl succinate



Di-*tert*-butyl succinate



Dibutyl sulfate



Dibutyl sulfide



Di-*sec*-butyl sulfide



Di-*tert*-butyl sulfide



Dibutyl sulfite



Dibutyl sulfone



Dibutyl sulfoxide



Dibutyl tartrate



N,N'-Dibutylthiourea



Dibutyltin dichloride



Dibutyltin dilaurate


Dicapthon



Dicentrine



Dichlofenthion



Dichlofluanid


Dichloroacetaldehyde


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3066	2,2-Dichloroacetamide		$C_2H_3Cl_2NO$	683-72-7	127.957		99.4	234			s H_2O, EtOH, eth; sl ace
3067	Dichloroacetic acid		$C_2H_2Cl_2O_2$	79-43-6	128.942		13.5	194; 102^{20}	1.5634^{20}	1.4658^{20}	msc H_2O, EtOH, eth; s ace; sl ctc
3068	Dichloroacetic anhydride		$C_4H_2Cl_4O_3$	4124-30-5	239.869		18.0	dec 215; 100^{10}	1.574^{24}		
3069	1,1-Dichloroacetone		$C_3H_4Cl_2O$	513-88-2	126.969			120	1.304^{18}		sl H_2O; s EtOH; msc eth
3070	1,3-Dichloroacetone		$C_3H_4Cl_2O$	534-07-6	126.969	pr or nd	45	173.4	1.3826^{46}	1.4716^{40}	s H_2O, EtOH, eth
3071	Dichloroacetonitrile		C_2HCl_2N	3018-12-0	109.942			112.5	1.369^{20}	1.4391^{25}	s MeOH
3072	Dichloroacetyl chloride		C_2HCl_3O	79-36-7	147.387			108	1.5315^{16}	1.4591^{20}	dec H_2O, EtOH; msc eth
3073	Dichloroacetylene		C_2Cl_2	7572-29-4	94.927	liq	-66	33	1.261^{20}	1.42790^{20}	s EtOH, eth, ace
3074	4-[(Dichloroamino)sulfonyl] benzoic acid	Halazone	$C_7H_5Cl_2NO_4S$	80-13-7	270.091	pr (HOAc)	195 dec				sl H_2O, chl; vs HOAc; i peth
3075	2,3-Dichloroaniline		$C_6H_5Cl_2N$	608-27-5	162.017	nd (lig)	24	252			s EtOH, ace; vs eth; sl bz, ctc, lig
3076	2,4-Dichloroaniline		$C_6H_5Cl_2N$	554-00-7	162.017	pr (ace) nd (dil al) (lig)	63.5	245	1.567^{20}		sl H_2O, chl; s EtOH, eth
3077	2,5-Dichloroaniline		$C_6H_5Cl_2N$	95-82-9	162.017	nd (lig)	50	251			sl H_2O; s EtOH, eth, bz, chl, CS_2
3078	2,6-Dichloroaniline		$C_6H_5Cl_2N$	608-31-1	162.017		39				sl H_2O; s EtOH, eth
3079	3,4-Dichloroaniline		$C_6H_5Cl_2N$	95-76-1	162.017	nd (lig)	72	272			s EtOH, eth; sl bz, chl
3080	3,5-Dichloroaniline		$C_6H_5Cl_2N$	626-43-7	162.017	nd (lig, dil al)	52	261			i H_2O; s EtOH, eth, ctc, lig
3081	9,10-Dichloroanthracene		$C_{14}H_8Cl_2$	605-48-1	247.120	ye nd (MeCOEt or CCl_4)	213.5				sl EtOH, eth, chl; s bz
3082	1,5-Dichloro-9,10-anthracenedione		$C_{14}H_6Cl_2O_2$	82-46-2	277.103	ye nd (to)	252				i H_2O; sl EtOH, ace; s bz, HOAc
3083	1,8-Dichloro-9,10-anthracenedione		$C_{14}H_6Cl_2O_2$	82-43-9	277.103	ye nd (HOAc)	202.5				i H_2O; sl EtOH; s bz, tol, $PhNO_2$
3084	*trans*-4,4'-Dichloroazobenzene		$C_{12}H_8Cl_2N_2$	1602-00-2	251.111	ye nd (ace)	189				
3085	4,4'-Dichloroazoxybenzene		$C_{12}H_8Cl_2N_2O$	614-26-6	267.110	ye nd (EtOH)	158				
3086	2,3-Dichlorobenzaldehyde		$C_7H_4Cl_2O$	6334-18-5	175.012	cry (dil al)	66				vs eth, EtOH
3087	2,4-Dichlorobenzaldehyde		$C_7H_4Cl_2O$	874-42-0	175.012	pr	73.3	105^{15}			i H_2O; s EtOH, eth, bz, chl, HOAc
3088	2,6-Dichlorobenzaldehyde		$C_7H_4Cl_2O$	83-38-5	175.012	nd (lig)	71.8				vs eth, EtOH, lig
3089	3,4-Dichlorobenzaldehyde		$C_7H_4Cl_2O$	6287-38-3	175.012		44	247.5			i H_2O; s EtOH, eth; sl ctc
3090	3,5-Dichlorobenzaldehyde		$C_7H_4Cl_2O$	10203-08-4	175.012	nd or lf (dil HOAc)	65	240			vs ace, bz, eth, EtOH
3091	2,6-Dichlorobenzamide		$C_7H_5Cl_2NO$	2008-58-4	190.027	cry	198				
3092	*o*-Dichlorobenzene	1,2-Dichlorobenzene	$C_6H_4Cl_2$	95-50-1	147.002	liq	-17.0	180	1.3059^{20}	1.5515^{20}	i H_2O; s EtOH, eth; msc ace, bz, ctc
3093	*m*-Dichlorobenzene	1,3-Dichlorobenzene	$C_6H_4Cl_2$	541-73-1	147.002	liq	-24.8	173	1.2884^{20}	1.5459^{20}	i H_2O; s EtOH, eth, bz; msc ace
3094	*p*-Dichlorobenzene	1,4-Dichlorobenzene	$C_6H_4Cl_2$	106-46-7	147.002	mcl pr, lf (ace)	53.09	174	1.2475^{55}	1.5285^{20}	i H_2O; msc EtOH, ace, bz; s eth, ctc
3095	2,5-Dichloro-1,4-benzenediamine		$C_6H_6Cl_2N_2$	20103-09-7	177.031	pr (w)	170				
3096	2,6-Dichloro-1,4-benzenediamine		$C_6H_6Cl_2N_2$	609-20-1	177.031	nd, pr (dil al)	125				s EtOH, eth, ace, bz
3097	3,5-Dichloro-1,2-benzenediol		$C_6H_4Cl_2O_2$	13673-92-2	179.001	pr	83.5				sl H_2O; s EtOH; vs ace
3098	4,5-Dichloro-1,2-benzenediol		$C_6H_4Cl_2O_2$	3428-24-8	179.001	pr(chl-CS_2) nd(bz-peth)	116.5				s H_2O; vs EtOH, bz
3099	4,6-Dichloro-1,3-benzenediol		$C_6H_4Cl_2O_2$	137-19-9	179.001		113	254			vs H_2O, EtOH, eth, ace; sl lig
3100	2,5-Dichloro-1,4-benzenediol		$C_6H_4Cl_2O_2$	824-69-1	179.001	nd or pr w, ace, bz)	172.5		1.8150^{24}		s H_2O; vs EtOH, eth, ace
3101	4,5-Dichloro-1,3-benzenedisulfonamide	Dichlorphenamide	$C_6H_6Cl_2N_2O_4S_2$	120-97-8	305.159		228.7				
3102	2,4-Dichlorobenzenemethanamine		$C_7H_7Cl_2N$	95-00-1	176.044			125^{13}		1.5762^{25}	s chl
3103	2,4-Dichlorobenzenemethanol	2,4-Dichlorobenzyl alcohol	$C_7H_6Cl_2O$	1777-82-8	177.028		59.5	150^{25}			s chl
3104	*N,N*-Dichlorobenzenesulfonamide		$C_6H_5Cl_2NO_2S$	473-29-0	226.081	ye mcl or pl	76				s EtOH; sl ctc



2,2-Dichloroacetamide



Dichloroacetic acid


Dichloroacetic anhydride



1,1-Dichloroacetone



1,3-Dichloroacetone



Dichloroacetonitrile



Dichloroacetyl chloride



Dichloroacetylene



4-[(Dichloroamino)sulfonyl]benzoic acid



2,3-Dichloroaniline



2,4-Dichloroaniline



2,5-Dichloroaniline



2,6-Dichloroaniline



3,4-Dichloroaniline



3,5-Dichloroaniline



9,10-Dichloroanthracene



1,5-Dichloro-9,10-anthracenedione



1,8-Dichloro-9,10-anthracenedione



trans-4,4'-Dichloroazobenzene



4,4'-Dichloroazoxybenzene



2,3-Dichlorobenzaldehyde


2,4-Dichlorobenzaldehyde



2,6-Dichlorobenzaldehyde



3,4-Dichlorobenzaldehyde



3,5-Dichlorobenzaldehyde



2,6-Dichlorobenzamide



o-Dichlorobenzene



m-Dichlorobenzene



p-Dichlorobenzene



2,5-Dichloro-1,4-benzenediamine



2,6-Dichloro-1,4-benzenediamine



3,5-Dichloro-1,2-benzenediol



4,5-Dichloro-1,2-benzenediol



4,6-Dichloro-1,3-benzenediol


2,5-Dichloro-1,4-benzenediol



4,5-Dichloro-1,3-benzenedisulfonamide



2,4-Dichlorobenzenemethanamine



2,4-Dichlorobenzenemethanol



N,N-Dichlorobenzenesulfonamide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3105	2,5-Dichlorobenzenethiol		$C_6H_4Cl_2S$	5858-18-4	179.067			115^{50}			
3106	2,2'-Dichloro-*p*-benzidine	[1,1'-Biphenyl]-4,4'-diamine, 2,2'-dichloro-	$C_{12}H_{10}Cl_2N_2$	84-68-4	253.126	nd (w), pr (al)	165				vs eth, EtOH
3107	3,3'-Dichloro-*p*-benzidine	[1,1'-Biphenyl]-4,4'-diamine, 3,3'-dichloro-	$C_{12}H_{10}Cl_2N_2$	91-94-1	253.126	nd	132.5				i H_2O; s EtOH, bz, HOAc
3108	3,3'-Dichloro-*p*-benzidine dihydrochloride		$C_{12}H_{12}Cl_4N_2$	612-83-9	326.048						i H_2O; vs EtOH
3109	2,4-Dichlorobenzoic acid		$C_7H_4Cl_2O_2$	50-84-0	191.012	nd (w or bz)	164.2	sub			s H_2O, EtOH, eth, bz, chl; sl ace
3110	2,5-Dichlorobenzoic acid		$C_7H_4Cl_2O_2$	50-79-3	191.012	nd (w)	154.4	301			sl H_2O, DMSO; s EtOH, eth
3111	2,6-Dichlorobenzoic acid		$C_7H_4Cl_2O_2$	50-30-6	191.012	nd (al), pr (w)	144	sub			s H_2O, EtOH, eth, bz, chl
3112	3,4-Dichlorobenzoic acid		$C_7H_4Cl_2O_2$	51-44-5	191.012	nd (w, al, bz)	208.5				s H_2O, eth; vs EtOH; sl DMSO
3113	3,5-Dichlorobenzoic acid		$C_7H_4Cl_2O_2$	51-36-5	191.012	nd (al, w)	188	sub			sl H_2O, lig, DMSO; s EtOH, eth
3114	2,6-Dichlorobenzonitrile	Dichlobenil	$C_7H_3Cl_2N$	1194-65-6	172.012	cry (peth)	144.5	270			
3115	4,4'-Dichlorobenzophenone	Bis(4-chlorophenyl) ketone	$C_{13}H_8Cl_2O$	90-98-2	251.108	pl (al)	147.5	353	1.4500^{20}		i H_2O; s EtOH; vs eth, chl; sl ace
3116	3,4-Dichlorobenzotrifluoride	1,2-Dichloro-4-(trifluoromethyl) benzene	$C_7H_3Cl_2F_3$	328-84-7	215.000	liq		$173.5; 64^{14}$	1.4729^{25}		
3117	2,3-Dichlorobenzoyl chloride		$C_7H_3Cl_3O$	2905-60-4	209.457	liq		140^{14}			
3118	2,4-Dichlorobenzoyl chloride		$C_7H_3Cl_3O$	89-75-8	209.457		16.5	150^{34}, $111^{7.5}$		1.5895^{20}	s ctc
3119	2,5-Dichlorobenzoyl chloride		$C_7H_3Cl_3O$	2905-61-5	209.457	liq		95.4^{1}			
3120	3,4-Dichlorobenzoyl chloride		$C_7H_3Cl_3O$	3024-72-4	209.457		25	242			sl ctc
3121	2,5-Dichlorobiphenyl		$C_{12}H_8Cl_2$	34883-39-1	223.098			182^{30}, 171^{15}			i H_2O
3122	2,6-Dichlorobiphenyl		$C_{12}H_8Cl_2$	33146-45-1	223.098	cry	35.5				i H_2O
3123	3,3'-Dichlorobiphenyl		$C_{12}H_8Cl_2$	2050-67-1	223.098	nd (dil al)	29	320			vs bz, eth, EtOH
3124	4,4'-Dichlorobiphenyl		$C_{12}H_8Cl_2$	2050-68-2	223.098	pr or nd (al, to-peth)	149.3	317	1.4420^{0}		i H_2O; sl EtOH, chl; s bz
3125	1,1-Dichloro-2,2-bis(*p*-chlorophenyl)ethane		$C_{14}H_{10}Cl_4$	72-54-8	320.041		109.5	193^{1}			sl chl
3126	2,2-Dichloro-1,1-bis(4-chlorophenyl)ethene		$C_{14}H_8Cl_4$	72-55-9	318.026		89				
3127	2,3-Dichloro-1,3-butadiene		$C_4H_4Cl_2$	1653-19-6	122.981			98	1.1829^{20}	1.4890^{20}	vs chl
3128	1,1-Dichlorobutane	Butylidene chloride	$C_4H_8Cl_2$	541-33-3	127.013			113.8	1.0863^{20}	1.4355^{20}	i H_2O; s chl
3129	1,2-Dichlorobutane		$C_4H_8Cl_2$	616-21-7	127.013			124.1	1.1116^{25}	1.4450^{20}	i H_2O; s eth, chl; sl ctc
3130	1,3-Dichlorobutane		$C_4H_8Cl_2$	1190-22-3	127.013			134	1.1158^{20}	1.4445^{20}	i H_2O; s eth, chl; sl ctc
3131	1,4-Dichlorobutane		$C_4H_8Cl_2$	110-56-5	127.013	liq	-37.3	161	1.1331^{25}	1.4522^{25}	i H_2O; vs chl
3132	2,2-Dichlorobutane		$C_4H_8Cl_2$	4279-22-5	127.013	liq	-74	104	1.1048^{25}	1.4295	i H_2O; s chl
3133	2,3-Dichlorobutane, (±)		$C_4H_8Cl_2$	2211-67-8	127.013	liq	-80	$119; 53^{80}$	1.105^{25}	1.4409^{25}	i H_2O
3134	1,4-Dichloro-2,3-butanediol		$C_4H_8Cl_2O_2$	2419-73-0	159.012		126.5	150^{30}			vs EtOH
3135	3,4-Dichloro-1-butene		$C_4H_6Cl_2$	760-23-6	124.997	liq	-61	116	1.1170^{20}	1.4641^{20}	i H_2O; s EtOH, eth, ctc; vs chl, bz
3136	*cis*-1,3-Dichloro-2-butene		$C_4H_6Cl_2$	10075-38-4	124.997			$130; 34^{20}$	1.1605^{20}	1.4735^{20}	vs ace, bz, eth, EtOH
3137	*trans*-1,3-Dichloro-2-butene		$C_4H_6Cl_2$	7415-31-8	124.997			$132; 53^{50}$	1.160^{20}	1.4719^{20}	vs ace, bz, eth, EtOH
3138	*cis*-1,4-Dichloro-2-butene		$C_4H_6Cl_2$	1476-11-5	124.997	liq	-48	152.5	1.188^{25}	1.4887^{25}	vs ace, bz, eth, EtOH
3139	*trans*-1,4-Dichloro-2-butene		$C_4H_6Cl_2$	110-57-6	124.997		1.0	155.4	1.183^{25}	1.4871^{25}	vs ace, bz, eth, EtOH
3140	1,4-Dichloro-2-butyne		$C_4H_4Cl_2$	821-10-3	122.981			165.5	1.258^{20}	1.5058^{20}	s eth, ace; sl ctc; vs chl
3141	2,6-Dichloro-4-(chloroimino)-2,5-cyclohexadien-1-one	Gibbs' reagent	$C_6H_2Cl_3NO$	101-38-2	210.445		66				
3142	1,2-Dichloro-4-(chloromethyl) benzene		$C_7H_5Cl_3$	102-47-6	195.474		37.5	241			i H_2O; s EtOH, ctc
3143	2,4-Dichloro-1-(chloromethyl) benzene		$C_7H_5Cl_3$	94-99-5	195.474			120^{13}			
3144	Dichloro(chloromethyl) methylsilane		$C_2H_5Cl_3Si$	1558-33-4	163.506			121.5	1.2858^{20}	1.4500^{20}	
3145	Dichloro(2-chlorovinyl)arsine		$C_2H_2AsCl_3$	541-25-3	207.318	liq	0.1	190	1.888^{20}		
3146	2,5-Dichloro-2,5-cyclohexadiene-1,4-dione		$C_6H_2Cl_2O_2$	615-93-0	176.985	pa ye mcl pr (al)	162.3				i H_2O; sl EtOH; s eth, chl



2,5-Dichlorobenzenethiol



2,2'-Dichloro-*p*-benzidine



3,3'-Dichloro-*p*-benzidine



3,3'-Dichloro-*p*-benzidine dihydrochloride



2,4-Dichlorobenzoic acid



2,5-Dichlorobenzoic acid



2,6-Dichlorobenzoic acid



3,4-Dichlorobenzoic acid



3,5-Dichlorobenzoic acid



2,6-Dichlorobenzonitrile



4,4'-Dichlorobenzophenone



3,4-Dichlorobenzotrifluoride



2,3-Dichlorobenzoyl chloride



2,4-Dichlorobenzoyl chloride



2,5-Dichlorobenzoyl chloride



3,4-Dichlorobenzoyl chloride



2,5-Dichlorobiphenyl


2,6-Dichlorobiphenyl



3,3'-Dichlorobiphenyl



4,4'-Dichlorobiphenyl



1,1-Dichloro-2,2-bis(*p*-chlorophenyl)ethane



2,2-Dichloro-1,1-bis(4-chlorophenyl)ethene


2,3-Dichloro-1,3-butadiene


1,1-Dichlorobutane



1,2-Dichlorobutane



1,3-Dichlorobutane



1,4-Dichlorobutane



2,2-Dichlorobutane


2,3-Dichlorobutane, (±)



1,4-Dichloro-2,3-butanediol



3,4-Dichloro-1-butene



cis-1,3-Dichloro-2-butene



trans-1,3-Dichloro-2-butene



cis-1,4-Dichloro-2-butene



trans-1,4-Dichloro-2-butene



1,4-Dichloro-2-butyne



2,6-Dichloro-4-(chloroimino)-2,5-cyclohexadien-1-one


1,2-Dichloro-4-(chloromethyl)benzene



2,4-Dichloro-1-(chloromethyl)benzene



Dichloro(chloromethyl)methylsilane



Dichloro(2-chlorovinyl)arsine



2,5-Dichloro-2,5-cyclohexadiene-1,4-dione


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3147	2,6-Dichloro-2,5-cyclohexadiene-1,4-dione		$C_6H_2Cl_2O_2$	697-91-6	176.985	ye orth (lig, bz)	121.8				sl H_2O, EtOH; s chl
3148	1,1-Dichlorocyclohexane		$C_6H_{10}Cl_2$	2108-92-1	153.049	liq	-47	171	1.1559^{20}	1.4803^{20}	
3149	*cis*-1,2-Dichlorocyclohexane		$C_6H_{10}Cl_2$	10498-35-8	153.049	liq	-1.5	206.9	1.2021^{20}	1.4967^{20}	vs bz
3150	1,10-Dichlorodecane		$C_{10}H_{20}Cl_2$	2162-98-3	211.172		15.6	167^{28}	0.9945^{25}	1.4586^{25}	
3151	2,7-Dichlorodibenzo-*p*-dioxin		$C_{12}H_6Cl_2O_2$	33857-26-0	253.081	cry	201				
3152	1,2-Dichloro-4-(dichloromethyl) benzene		$C_7H_4Cl_4$	56961-84-3	229.919			257	1.515^{22}		vs bz, eth, EtOH
3153	Dichloro(dichloromethyl) methylsilane		$C_2H_4Cl_4Si$	1558-31-2	197.951			149	1.4116^{20}	1.4700^{20}	
3154	2,3-Dichloro-5,6-dicyanobenzoquinone		$C_8Cl_2N_2O_2$	84-58-2	227.004	ye-oran cry	214.5				vs bz, HOAc, diox
3155	Dichlorodiethylsilane		$C_4H_{10}Cl_2Si$	1719-53-5	157.114		-96.5	dec 129	1.0504^{20}	1.4309^{20}	
3156	1,1-Dichloro-1,2-difluoroethane		$C_2H_2Cl_2F_2$	25915-78-0	134.940	col liq		48.4			
3157	1,2-Dichloro-1,1-difluoroethane		$C_2H_2Cl_2F_2$	1649-08-7	134.940	liq	-101.2	46.2	1.4163^{20}	1.36193^{20}	sl H_2O
3158	1,2-Dichloro-1,2-difluoroethane		$C_2H_2Cl_2F_2$	431-06-1	134.940	liq	-101.2	59.6	1.4163^{20}	1.3619^{20}	
3159	1,1-Dichloro-2,2-difluoroethene	1,1-Dichloro-2,2-difluoroethylene	$C_2Cl_2F_2$	79-35-6	132.924	vol liq or gas	-116	19	1.555^{-20}	1.383^{-20}	
3160	*cis*-1,2-Dichloro-1,2-difluoroethene	Fluorocarbon 1112	$C_2Cl_2F_2$	311-81-9	132.924	vol liq	-119.6	21.1	1.495^{0}		
3161	*trans*-1,2-Dichloro-1,2-difluoroethene		$C_2Cl_2F_2$	381-71-5	132.924	vol liq	-93.3	22	1.494^{0}		
3162	Dichlorodifluoromethane	Refrigerant 12	CCl_2F_2	75-71-8	120.914	col gas	-158	-29.8			sl H_2O; s EtOH, eth, HOAc
3163	2,2-Dichloro-1,1-difluoro-1-methoxyethane	Methoxyflurane	$C_3H_4Cl_2F_2O$	76-38-0	164.966	col liq	-35	105	1.43^{20}	1.3861^{20}	
3164	2,2'-Dichlorodiisopropyl ether		$C_6H_{12}Cl_2O$	108-60-1	171.064			187	1.103^{20}	1.4505^{20}	i H_2O; msc EtOH, eth, ace; vs bz
3165	1,4-Dichloro-2,5-dimethylbenzene		$C_8H_8Cl_2$	1124-05-6	175.056		71	222			s chl
3166	2,5-Dichloro-2,5-dimethylhexane		$C_8H_{16}Cl_2$	6223-78-5	183.119	lf, nd	67.5		0.9543^{20}		vs bz, eth, EtOH, chl
3167	1,3-Dichloro-5,5-dimethyl hydantoin		$C_5H_6Cl_2N_2O_2$	118-52-5	197.019	pr	132		1.5^{20}		sl H_2O; s chl, ctc, bz
3168	2,4-Dichloro-3,5-dimethylphenol	Dichloroxylenol	$C_8H_8Cl_2O$	133-53-9	191.055		83				vs eth
3169	Dichlorodimethylsilane		$C_2H_6Cl_2Si$	75-78-5	129.061	liq	-16	70.3	1.064^{25}	1.4038^{20}	dec H_2O, EtOH
3170	2,3-Dichloro-1,4-dioxane		$C_4H_6Cl_2O_2$	95-59-0	156.996		30	81^{10}	1.468^{20}	1.4928^{20}	i H_2O; vs eth, ace, bz, ctc, diox
3171	Dichlorodiphenylmethane		$C_{13}H_{10}Cl_2$	2051-90-3	237.124			dec 305; 190^{21}	1.235^{18}		s eth, bz, ctc
3172	Dichlorodiphenylsilane		$C_{12}H_{10}Cl_2Si$	80-10-4	253.199			305	1.204^{25}	1.5800^{20}	s EtOH, eth, ace, bz, ctc
3173	1,1-Dichloroethane	Ethylidene dichloride	$C_2H_4Cl_2$	75-34-3	98.959	liq	-96.9	57.3	1.1757^{20}	1.4164^{20}	sl H_2O; vs EtOH, eth; s ace, bz
3174	1,2-Dichloroethane	Ethylene dichloride	$C_2H_4Cl_2$	107-06-2	98.959	liq	-35.7	83.5	1.2454^{25}	1.4422^{25}	sl H_2O; vs EtOH; msc eth; s ace, bz, chl
3175	2,2-Dichloroethanol		$C_2H_4Cl_2O$	598-38-9	114.958			146	1.4040^{25}	1.4626^{25}	sl H_2O, ctc; s EtOH, eth
3176	1,1-Dichloroethene	Vinylidene chloride	$C_2H_2Cl_2$	75-35-4	96.943	liq	-122.56	31.6	1.213^{20}	1.4249^{20}	i H_2O; s EtOH, ace, bz; vs eth, chl
3177	*cis*-1,2-Dichloroethene	*cis*-1,2-Dichloroethylene	$C_2H_2Cl_2$	156-59-2	96.943	liq	-80.0	60.1	1.2837^{20}	1.4490^{20}	sl H_2O; msc EtOH, eth, ace; vs bz, chl
3178	*trans*-1,2-Dichloroethene	*trans*-1,2-Dichloroethylene	$C_2H_2Cl_2$	156-60-5	96.943	liq	-49.8	48.7	1.2565^{20}	1.4454^{20}	sl H_2O; msc EtOH, eth, ace; vs bz, chl
3179	1,2-Dichloro-1-ethoxyethane		$C_4H_8Cl_2O$	623-46-1	143.012			145	1.1370^{20}	1.4435^{20}	sl chl
3180	1,2-Dichloroethyl acetate		$C_4H_6Cl_2O_2$	10140-87-1	156.996	liq		79^{33}, 32^{10}			
3181	Dichloroethylaluminum	Ethylaluminum chloride	$C_2H_5AlCl_2$	563-43-9	126.949	hyg solid or liq	32	115^{50}	1.207		reac H_2O
3182	Dichloroethylmethylsilane		$C_3H_8Cl_2Si$	4525-44-4	143.088			101	1.0047^{20}	1.4197^{20}	
3183	2',7'-Dichlorofluorescein	2',7'-Dichloro-3,6-fluorandiol	$C_{20}H_{10}Cl_2O_5$	76-54-0	401.196						sl DMSO
3184	1,1-Dichloro-1-fluoroethane		$C_2H_3Cl_2F$	1717-00-6	116.949	liq	-103.5	32.0	1.250^{10}	1.3600^{10}	i H_2O
3185	1,2-Dichloro-1-fluoroethane		$C_2H_3Cl_2F$	430-57-9	116.949	liq	-60	73.8	1.3814^{20}	1.4132^{20}	
3186	1,1-Dichloro-2-fluoroethene	1,1-Dichloro-2-fluoroethylene	C_2HCl_2F	359-02-4	114.933	liq	-108.8	37.5	1.3732^{16}	1.4031^{16}	
3187	Dichlorofluoromethane	Refrigerant 21	$CHCl_2F$	75-43-4	102.923	col gas	-135	8.9	1.405^{9}	1.3724^{9}	i H_2O; s EtOH, eth, ctc, chl, HOAc
3188	(Dichlorofluoromethyl)benzene		$C_7H_5Cl_2F$	498-67-9	179.019	liq	-26.8	179	1.3138^{11}	1.5180^{11}	vs EtOH
3189	1,1-Dichloro-2-fluoropropene		$C_3H_3Cl_2F$	430-95-5	128.960			78	1.3026^{25}	1.4196^{25}	
3190	1,7-Dichloroheptane		$C_7H_{14}Cl_2$	821-76-1	169.092			124^{35}	1.0408^{25}	1.4565^{25}	



2,6-Dichloro-2,5-cyclohexadiene-1,4-dione



1,1-Dichlorocyclohexane



cis-1,2-Dichlorocyclohexane


1,10-Dichlorodecane


2,7-Dichlorodibenzo-*p*-dioxin



1,2-Dichloro-4-(dichloromethyl)benzene


Dichloro(dichloromethyl)methylsilane


2,3-Dichloro-5,6-dicyanobenzoquinone


Dichlorodiethylsilane


1,1-Dichloro-1,2-difluoroethane


1,2-Dichloro-1,1-difluoroethane



1,2-Dichloro-1,2-difluoroethane



1,1-Dichloro-2,2-difluoroethene



cis-1,2-Dichloro-1,2-difluoroethene



trans-1,2-Dichloro-1,2-difluoroethene



Dichlorodifluoromethane



2,2-Dichloro-1,1-difluoro-1-methoxyethane


2,2'-Dichlorodiisopropyl ether


1,4-Dichloro-2,5-dimethylbenzene



2,5-Dichloro-2,5-dimethylhexane



1,3-Dichloro-5,5-dimethyl hydantoin


2,4-Dichloro-3,5-dimethylphenol



Dichlorodimethylsilane



2,3-Dichloro-1,4-dioxane


Dichlorodiphenylmethane


Dichlorodiphenylsilane



1,1-Dichloroethane



1,2-Dichloroethane



2,2-Dichloroethanol


1,1-Dichloroethene



cis-1,2-Dichloroethene



trans-1,2-Dichloroethene


1,2-Dichloro-1-ethoxyethane



1,2-Dichloroethyl acetate



Dichloroethylaluminum


Dichloroethylmethylsilane



2',7'-Dichlorofluorescein


1,1-Dichloro-1-fluoroethane



1,2-Dichloro-1-fluoroethane


1,1-Dichloro-2-fluoroethene



Dichlorofluoromethane



(Dichlorofluoromethyl)benzene



1,1-Dichloro-2-fluoropropene



1,7-Dichloroheptane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3191	1,2-Dichloro-1,2,3,3,4,4-hexafluorocyclobutane		$C_4Cl_2F_6$	356-18-3	232.939	liq	-24.2	59.5			
3192	1,2-Dichloro-3,3,4,4,5,5-hexafluorocyclopentene		$C_5Cl_2F_6$	706-79-6	244.949	liq	-105.8	90.7	1.6546^{20}	1.3676^{20}	
3193	1,2-Dichloro-1,1,2,3,3,3-hexafluoropropane		$C_3Cl_2F_6$	661-97-2	220.928			34.1			i H_2O
3194	1,3-Dichloro-1,1,2,2,3,3-hexafluoropropane	Refrigerant 216	$C_3Cl_2F_6$	662-01-1	220.928	liq	-125.4	35.7	1.573^{20}	1.3030^{20}	
3195	1,5-Dichloro-1,1,3,3,5,5-hexamethyltrisiloxane		$C_6H_{18}Cl_2O_2Si_3$	3582-71-6	277.369	liq	-53	184	1.018^{20}		dec H_2O
3196	1,2-Dichlorohexane		$C_6H_{12}Cl_2$	2162-92-7	155.065			173	1.085^{15}		vs eth, chl
3197	1,6-Dichlorohexane		$C_6H_{12}Cl_2$	2163-00-0	155.065			204	1.0676^{25}	1.4555^{25}	i H_2O; s eth, ctc, chl
3198	3,5-Dichloro-2-hydroxybenzaldehyde		$C_7H_4Cl_2O_2$	90-60-8	191.012	ye orth (HOAc)	95				i H_2O
3199	3,5-Dichloro-2-hydroxybenzoic acid		$C_7H_4Cl_2O_3$	320-72-9	207.011	nd (dil al) orth pr	220.5	sub			sl H_2O; vs EtOH, eth
3200	2,6-Dichloroindophenol, sodium salt	Tillman's reagent	$C_{12}H_6Cl_2NNaO_2$	620-45-1	290.078	dk grn cry					s H_2O, EtOH, ace
3201	5,6-Dichloro-1,3-isobenzofurandione	4,5-Dichlorophthalic anhydride	$C_8H_2Cl_2O_3$	942-06-3	217.006	tab or pr (to)	188	313			vs eth, EtOH, tol
3202	Dichloromethane	Methylene chloride	CH_2Cl_2	75-09-2	84.933	liq	-97.2	40	1.3266^{20}	1.4242^{20}	sl H_2O; msc EtOH, eth; s ctc
3203	1,2-Dichloro-3-methoxybenzene		$C_7H_6Cl_2O$	1984-59-4	177.028		32				
3204	1,3-Dichloro-2-methoxybenzene	2,6-Dichloroanisole	$C_7H_6Cl_2O$	1984-65-2	177.028	liq	10	105^{20}	1.291	1.5430^{20}	
3205	2,4-Dichloro-1-methoxybenzene		$C_7H_6Cl_2O$	553-82-2	177.028	pr	28.5	232; 125^{10}			sl chl
3206	3,6-Dichloro-2-methoxybenzoic acid	Dicamba	$C_8H_6Cl_2O_3$	1918-00-9	221.038	cry (pent)	115		1.57^{25}		
3207	(Dichloromethyl)benzene	Benzal chloride	$C_7H_6Cl_2$	98-87-3	161.029	liq	-17	205	1.26^{25}	1.5502^{20}	i H_2O; vs eth, EtOH
3208	*N,N*-Dichloro-4-methylbenzenesulfonamide	Dichloramine-T	$C_7H_7Cl_2NO_2S$	473-34-7	240.108	pr(chl-peth)	83				i H_2O; s EtOH, eth, bz, ctc, HOAc
3209	Dichloromethylborane	Methyldichloroborane	CH_3BCl_2	7318-78-7	96.752	col gas		11			
3210	2,3-Dichloro-2-methylbutane	Amylene dichloride	$C_5H_{10}Cl_2$	507-45-9	141.038			129	1.0696^{15}	1.4450^{18}	i H_2O; vs eth, EtOH
3211	1,1-Dichloromethyl methyl ether	Methoxydichloromethane	$C_2H_4Cl_2O$	4885-02-3	114.958			85	1.271^{25}	1.4300^{20}	
3212	2,4-Dichloro-3-methylphenol		$C_7H_6Cl_2O$	17788-00-0	177.028	pr (peth)	58	236; 77^{4}			vs eth, chl
3213	2,4-Dichloro-6-methylphenol		$C_7H_6Cl_2O$	1570-65-6	177.028	nd (w, peth)	55				sl H_2O; vs EtOH, eth, chl, CS_2
3214	2,6-Dichloro-4-methylphenol		$C_7H_6Cl_2O$	2432-12-4	177.028	nd (lig)	39	231; 138^{28}			i H_2O; vs eth, EtOH, HOAc
3215	Dichloromethylphenylsilane		$C_7H_8Cl_2Si$	149-74-6	191.131			206.5	1.1866^{20}	1.5180^{20}	
3216	Dichloromethylphosphine	Methylphosphonous dichloride	CH_3Cl_2P	676-83-5	116.915			12^{50}	1.304^{20}	1.4940^{20}	
3217	1,2-Dichloro-2-methylpropane	1,2-Dichloroisobutane	$C_4H_8Cl_2$	594-37-6	127.013			106.5	1.093^{20}	1.4370^{20}	i H_2O; msc EtOH, eth, ace, bz, ctc
3218	2,4-Dichloro-5-methylpyrimidine		$C_5H_4Cl_2N_2$	1780-31-0	163.004	pl (al)	26	235			sl H_2O; vs EtOH, eth, bz, chl
3219	2,4-Dichloro-6-methylpyrimidine		$C_5H_4Cl_2N_2$	5424-21-5	163.004	nd (lig)	46.5	219			vs bz, eth, EtOH, chl
3220	Dichloromethylsilane		CH_4Cl_2Si	75-54-7	115.035	liq	-93	41	1.105^{25}		
3221	1,2-Dichloronaphthalene		$C_{10}H_6Cl_2$	2050-69-3	197.061	pl (al)	36	296.5	1.3147^{49}	1.5338^{49}	s EtOH, eth
3222	1,3-Dichloronaphthalene		$C_{10}H_6Cl_2$	2198-75-6	197.061	nd or pr (al)	62.3	291			s EtOH
3223	1,4-Dichloronaphthalene		$C_{10}H_6Cl_2$	1825-31-6	197.061	nd or pr (al, ace)	67.5	288; 147^{12}	1.2997^{76}	1.6228^{76}	i H_2O; sl EtOH; s eth, bz, HOAc; vs ace
3224	1,5-Dichloronaphthalene		$C_{10}H_6Cl_2$	1825-30-5	197.061	nd or lf (al) pr (sub)	107	sub	1.4900^{20}		i H_2O; sl EtOH; s eth
3225	1,6-Dichloronaphthalene		$C_{10}H_6Cl_2$	2050-72-8	197.061	nd or pr (al, peth)	49	sub			
3226	1,7-Dichloronaphthalene		$C_{10}H_6Cl_2$	2050-73-9	197.061	nd or pr (al, HOAc)	63.5	285.5	1.2611^{100}	1.6092^{100}	s EtOH, eth, bz, HOAc
3227	1,8-Dichloronaphthalene		$C_{10}H_6Cl_2$	2050-74-0	197.061	orth pl (hx) nd (al, sub)	89	sub	1.2924^{100}	1.6236^{100}	s EtOH, peth
3228	2,3-Dichloronaphthalene		$C_{10}H_6Cl_2$	2050-75-1	197.061	orth lf (al)	120				i H_2O; sl EtOH; vs eth
3229	2,6-Dichloronaphthalene		$C_{10}H_6Cl_2$	2065-70-5	197.061	nd or lf (al) pl (eth, bz)	140.5	285			sl EtOH; s eth, bz, chl, HOAc
3230	2,7-Dichloronaphthalene		$C_{10}H_6Cl_2$	2198-77-8	197.061	pl or lf (al)	115.0				vs EtOH; s hx, HOAc
3231	2,3-Dichloro-1,4-naphthalenedione	Dichlone	$C_{10}H_4Cl_2O_2$	117-80-6	227.044	ye nd (al)	195				i H_2O; sl EtOH, eth, bz; s chl



1,2-Dichloro-1,2,3,3,4,4-hexafluorocyclobutane



1,2-Dichloro-3,3,4,4,5,5-hexafluorocyclopentene



1,2-Dichloro-1,1,2,3,3,3-hexafluoropropane



1,3-Dichloro-1,1,2,2,3,3-hexafluoropropane



1,5-Dichloro-1,1,3,3,5,5-hexamethyltrisiloxane



1,2-Dichlorohexane


1,6-Dichlorohexane



3,5-Dichloro-2-hydroxybenzaldehyde



3,5-Dichloro-2-hydroxybenzoic acid



2,6-Dichloroindophenol, sodium salt



5,6-Dichloro-1,3-isobenzofurandione



Dichloromethane



1,2-Dichloro-3-methoxybenzene


1,3-Dichloro-2-methoxybenzene


2,4-Dichloro-1-methoxybenzene


3,6-Dichloro-2-methoxybenzoic acid



(Dichloromethyl)benzene



N,N-Dichloro-4-methylbenzenesulfonamide



Dichloromethylborane



2,3-Dichloro-2-methylbutane


1,1-Dichloromethyl methyl ether


2,4-Dichloro-3-methylphenol



2,4-Dichloro-6-methylphenol



2,6-Dichloro-4-methylphenol


Dichloromethylphenylsilane



Dichloromethylphosphine



1,2-Dichloro-2-methylpropane



2,4-Dichloro-5-methylpyrimidine



2,4-Dichloro-6-methylpyrimidine



Dichloromethylsilane



1,2-Dichloronaphthalene



1,3-Dichloronaphthalene



1,4-Dichloronaphthalene



1,5-Dichloronaphthalene



1,6-Dichloronaphthalene



1,7-Dichloronaphthalene


1,8-Dichloronaphthalene



2,3-Dichloronaphthalene



2,6-Dichloronaphthalene



2,7-Dichloronaphthalene



2,3-Dichloro-1,4-naphthalenedione


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3232	2,4-Dichloro-1-naphthol	2,4-Dichloro-α-naphthol	$C_{10}H_6Cl_2O$	2050-76-2	213.060	nd (al, bz)	107.5	180			vs bz, eth, EtOH
3233	2,6-Dichloro-4-nitroaniline		$C_6H_4Cl_2N_2O_2$	99-30-9	207.014	ye nd (al, HOAc)	191				s EtOH, acid; sl DMSO
3234	1,2-Dichloro-3-nitrobenzene		$C_6H_3Cl_2NO_2$	3209-22-1	192.000	mcl nd (peth, HOAc)	61.5	257.5	1.721^{14}		i H_2O; s EtOH, eth, ace, bz, peth; sl chl
3235	1,2-Dichloro-4-nitrobenzene		$C_6H_3Cl_2NO_2$	99-54-7	192.000	nd (al)	43	255.5	1.4558^{75}		i H_2O; s EtOH, eth; sl ctc
3236	1,3-Dichloro-5-nitrobenzene		$C_6H_3Cl_2NO_2$	618-62-2	192.000	mcl pr or lf (HOAc, al)	65.4		1.4000^{100}		i H_2O; s EtOH, eth
3237	1,4-Dichloro-2-nitrobenzene		$C_6H_3Cl_2NO_2$	89-61-2	192.000	pl or pr (al) pl (AcOEt)	56	267	1.439^{75}	1.4390^{75}	i H_2O; s EtOH, eth, bz, CS_2; sl ctc
3238	2,4-Dichloro-1-nitrobenzene		$C_6H_3Cl_2NO_2$	611-06-3	192.000	nd (al)	34	258.5	1.4790^{80}	1.5512^{70}	i H_2O; s EtOH, eth; sl chl
3239	1,1-Dichloro-1-nitroethane	Ethide	$C_2H_3Cl_2NO_2$	594-72-9	143.957			123.5			s ctc
3240	2,6-Dichloro-4-nitrophenol		$C_6H_3Cl_2NO_3$	618-80-4	207.999	br nd (w)	127 exp		1.822^{25}		vs eth, chl
3241	1,1-Dichloro-1-nitropropane		$C_3H_5Cl_2NO_2$	595-44-8	157.984			145	1.312^{20}		s ctc
3242	1,9-Dichlorononane		$C_9H_{18}Cl_2$	821-99-8	197.145			260; 138^{17}	1.0173^{25}	1.4586^{25}	
3243	1,8-Dichlorooctane		$C_8H_{16}Cl_2$	2162-99-4	183.119			241	1.0248^{25}	1.4572^{25}	
3244	1,3-Dichloro-1,1,2,2,3-pentafluoropropane		$C_3HCl_2F_5$	507-55-1	202.938	liq		52	1.55^{25}		
3245	3,3-Dichloro-1,1,1,2,2-pentafluoropropane	Refrigerant 225ca	$C_3HCl_2F_5$	422-56-0	202.938	liq		45.5	1.54^{25}		
3246	1,2-Dichloropentane		$C_5H_{10}Cl_2$	1674-33-5	141.038			148.3	1.0872^{20}	1.4485^{20}	i H_2O; s EtOH; vs chl
3247	1,5-Dichloropentane		$C_5H_{10}Cl_2$	628-76-2	141.038	liq	-72.8	179	1.0956^{25}	1.4545^{25}	i H_2O; s EtOH, eth, bz, ctc
3248	2,3-Dichloropentane		$C_5H_{10}Cl_2$	600-11-3	141.038	liq	-77.3	139	1.0789^{20}	1.4464^{20}	i H_2O
3249	Dichlorophene		$C_{13}H_{10}Cl_2O_2$	97-23-4	269.123	cry (bz, peth)	177.5				i H_2O; s EtOH, ace
3250	2,3-Dichlorophenol		$C_6H_4Cl_2O$	576-24-9	163.001	cry (lig, bz)	58				s EtOH, eth, bz, lig
3251	2,4-Dichlorophenol		$C_6H_4Cl_2O$	120-83-2	163.001	hex nd (bz)	45	210			sl H_2O; s EtOH, eth, bz, chl
3252	2,5-Dichlorophenol		$C_6H_4Cl_2O$	583-78-8	163.001	pr (bz, peth)	59	211			sl H_2O; vs EtOH, eth; s bz, peth
3253	2,6-Dichlorophenol		$C_6H_4Cl_2O$	87-65-0	163.001	nd (peth)	68.5	220; 82^{4}	1.653^{20}		vs EtOH, eth; s bz, peth
3254	3,4-Dichlorophenol		$C_6H_4Cl_2O$	95-77-2	163.001	nd (bz-peth)	68	253			sl H_2O; vs EtOH, eth; s bz, peth
3255	3,5-Dichlorophenol		$C_6H_4Cl_2O$	591-35-5	163.001	pr (peth)	68	233			sl H_2O; vs EtOH, eth; s peth
3256	(2,4-Dichlorophenoxy)acetic acid	2,4-D	$C_8H_6Cl_2O_3$	94-75-7	221.038	cry (bz)	140.5	160$^{0.4}$			i H_2O; s EtOH; sl bz, DMSO
3257	4-(2,4-Dichlorophenoxy)butanoic acid	Butyrac 118	$C_{10}H_{10}Cl_2O_3$	94-82-6	249.090		118				
3258	2-(2,4-Dichlorophenoxy) propanoic acid	Dichlorprop	$C_9H_8Cl_2O_3$	120-36-5	235.064		117.5				sl H_2O, lig; s EtOH, eth
3259	Dichlorophenylarsine		$C_6H_5AsCl_2$	696-28-6	222.932	liq	-19	255	1.6516^{20}	1.6386^{15}	vs bz, eth, EtOH
3260	2,4-Dichlorophenyl benzenesulfonate	Genite	$C_{12}H_8Cl_2O_3S$	97-16-5	303.161		45.5				s ctc, CS_2
3261	2,2-Dichloro-1-phenylethanone		$C_8H_6Cl_2O$	2648-61-5	189.039	amor	20.5	249	1.340^{16}	1.5686^{20}	s EtOH, bz, ctc
3262	1-(2,4-Dichlorophenyl)ethanone		$C_8H_6Cl_2O$	2234-16-4	189.039		33.5			1.5640^{20}	i H_2O
3263	1-(2,5-Dichlorophenyl)ethanone		$C_8H_6Cl_2O$	2476-37-1	189.039		12	118^{12}	1.321^{30}	1.5595^{30}	
3264	1-(3,4-Dichlorophenyl)ethanone		$C_8H_6Cl_2O$	2642-63-9	189.039	nd (peth)	76	135^{12}			i H_2O; s ctc, lig
3265	3,4-Dichlorophenyl isocyanate	1,2-Dichloro-5-isocyanatobenzene	$C_7H_3Cl_2NO$	102-36-3	188.011	cry	42	112^{12}			
3266	3,5-Dichlorophenyl isocyanate	1,3-Dichloro-5-isocyanatobenzene	$C_7H_3Cl_2NO$	34893-92-0	188.011		33		1.380		
3267	*N*-(3,4-Dichlorophenyl)-2-methyl-2-propenamide	Dicryl	$C_{10}H_9Cl_2NO$	2164-09-2	230.090	cry (al-peth)	128				vs ace, EtOH
3268	3-(2,4-Dichlorophenyl)-2-propenoic acid		$C_9H_6Cl_2O_2$	1201-99-6	217.049		234				s DMSO
3269	Dichlorophenylsilane	Phenyldichlorosilane	$C_6H_6Cl_2Si$	1631-84-1	177.104			181	1.221^{25}		dec H_2O
3270	1,1-Dichloropropane	Propylidene chloride	$C_3H_6Cl_2$	78-99-9	112.986			88.1	1.1321^{20}	1.4289^{20}	s EtOH, eth, bz, chl
3271	1,2-Dichloropropane, (±)	Propylene dichloride	$C_3H_6Cl_2$	26198-63-0	112.986	liq	-100.53	96.4	1.1560^{20}	1.4394^{20}	sl H_2O; s EtOH, eth, bz, chl
3272	1,3-Dichloropropane		$C_3H_6Cl_2$	142-28-9	112.986	liq	-99.5	120.9	1.1785^{25}	1.4455^{25}	sl H_2O; vs EtOH, eth; s bz, chl
3273	2,2-Dichloropropane		$C_3H_6Cl_2$	594-20-7	112.986	liq	-33.9	69.3	1.1136^{20}	1.4148^{20}	i H_2O; s EtOH, bz, chl; msc eth



2,4-Dichloro-1-naphthol



2,6-Dichloro-4-nitroaniline


1,2-Dichloro-3-nitrobenzene



1,2-Dichloro-4-nitrobenzene



1,3-Dichloro-5-nitrobenzene



1,4-Dichloro-2-nitrobenzene



2,4-Dichloro-1-nitrobenzene



1,1-Dichloro-1-nitroethane



2,6-Dichloro-4-nitrophenol



1,1-Dichloro-1-nitropropane



1,9-Dichlorononane



1,8-Dichlorooctane



1,3-Dichloro-1,1,2,2,3-pentafluoropropane



3,3-Dichloro-1,1,1,2,2-pentafluoropropane



1,2-Dichloropentane



1,5-Dichloropentane



2,3-Dichloropentane



Dichlorophene



2,3-Dichlorophenol



2,4-Dichlorophenol



2,5-Dichlorophenol



2,6-Dichlorophenol



3,4-Dichlorophenol



3,5-Dichlorophenol



(2,4-Dichlorophenoxy)acetic acid



4-(2,4-Dichlorophenoxy)butanoic acid



2-(2,4-Dichlorophenoxy)propanoic acid



Dichlorophenylarsine



2,4-Dichlorophenyl benzenesulfonate



2,2-Dichloro-1-phenylethanone



1-(2,4-Dichlorophenyl)ethanone



1-(2,5-Dichlorophenyl)ethanone



1-(3,4-Dichlorophenyl)ethanone



3,4-Dichlorophenyl isocyanate



3,5-Dichlorophenyl isocyanate



N-(3,4-Dichlorophenyl)-2-methyl-2-propenamide


3-(2,4-Dichlorophenyl)-2-propenoic acid


Dichlorophenylsilane



1,1-Dichloropropane



1,2-Dichloropropane, (±)



1,3-Dichloropropane



2,2-Dichloropropane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3274	2,2-Dichloropropanoic acid	2,2-Dichloropropionic acid	$C_3H_4Cl_2O_2$	75-99-0	142.969			187.5; 92^{14}	1.389^{12}		vs H_2O, alk, EtOH; s eth, ctc
3275	2,3-Dichloro-1-propanol		$C_3H_6Cl_2O$	616-23-9	128.985	visc		184	1.3607^{20}	1.4819^{20}	sl H_2O, lig; msc EtOH, eth, ace, bz
3276	1,3-Dichloro-2-propanol		$C_3H_6Cl_2O$	96-23-1	128.985			176	1.3506^{17}	1.4837^{20}	vs H_2O, EtOH; msc eth; s ace, chl
3277	2,3-Dichloro-1-propanol, phosphate (3:1)		$C_9H_{15}Cl_6O_4P$	78-43-3	430.904			190$^{0.1}$	1.517^{22}		
3278	2,3-Dichloropropanoyl chloride		$C_3H_3Cl_3O$	7623-13-4	161.414			53^{17}	1.4757^{20}	1.4764^{20}	
3279	1,1-Dichloropropene		$C_3H_4Cl_2$	563-58-6	110.970			76.5	1.1864^{25}	1.4430^{25}	i H_2O; s eth, ace, chl
3280	*cis*-1,2-Dichloropropene		$C_3H_4Cl_2$	6923-20-2	110.970			93		1.4549^{20}	i H_2O; s ace, bz, chl
3281	*trans*-1,2-Dichloropropene		$C_3H_4Cl_2$	7069-38-7	110.970			77	1.1818^{20}	1.4471^{20}	i H_2O; vs EtOH, ctc, MeOH
3282	*cis*-1,3-Dichloropropene	*cis*-1,3-Dichloropropylene	$C_3H_4Cl_2$	10061-01-5	110.970			104.3	1.224^{20}	1.4682^{20}	i H_2O; s eth, bz, chl
3283	*trans*-1,3-Dichloropropene	*trans*-1,3-Dichloropropylene	$C_3H_4Cl_2$	10061-02-6	110.970			112	1.217^{20}	1.4730^{20}	i H_2O; s eth, bz, chl
3284	2,3-Dichloropropene		$C_3H_4Cl_2$	78-88-6	110.970		10	94	1.211^{20}	1.4603^{20}	i H_2O; msc EtOH; s eth, bz, chl
3285	3,6-Dichloropyridazine		$C_4H_2Cl_2N_2$	141-30-0	148.978		68.8	89$^{0.2}$			s chl
3286	2,6-Dichloropyridine		$C_5H_3Cl_2N$	2402-78-0	147.990		87	211			
3287	4,6-Dichloro-2-pyrimidinamine		$C_4H_3Cl_2N_3$	56-05-3	163.993		215				s DMSO
3288	2,4-Dichloropyrimidine		$C_4H_2Cl_2N_2$	3934-20-1	148.978		59	198; 101^{23}			
3289	4,7-Dichloroquinoline		$C_9H_5Cl_2N$	86-98-6	198.049	cry (MeOH), nd (80% al)	93	148^{10}			sl chl
3290	5,7-Dichloro-8-quinolinol	Chloroxine	$C_9H_5Cl_2NO$	773-76-2	214.048	cry (al)	179.5				sl EtOH, ace, chl, DMSO; s alk, bz, peth
3291	2,3-Dichloroquinoxaline		$C_8H_4Cl_2N_2$	2213-63-0	199.037	cry (al, bz)	152				i H_2O; vs EtOH, bz, chl, HOAc
3292	2,5-Dichlorostyrene		$C_8H_6Cl_2$	1123-84-8	173.040		8.0	93^{5}, 74^{3}	1.246^{20}	1.5798^{20}	
3293	1,2-Dichloro-3,4,5,6-tetrafluorobenzene		$C_6Cl_2F_4$	1198-59-0	218.964			157.7			
3294	1,1-Dichloro-1,2,2,2-tetrafluoroethane	Refrigerant 114a	$C_2Cl_2F_4$	374-07-2	170.921	col gas	-56.6	3.4	1.455^{25} (p>1 atm)	1.3092^{0}	vs bz, eth, EtOH
3295	1,2-Dichloro-1,1,2,2-tetrafluoroethane	Refrigerant 114	$C_2Cl_2F_4$	76-14-2	170.921	col gas	-92.53	3.5	1.455^{25} (p>1 atm)	1.3092^{0}	i H_2O; vs eth, EtOH
3296	1,2-Dichloro-1,1,2,2-tetramethyldisilane		$C_4H_{12}Cl_2Si_2$	4342-61-4	187.215			148; 49^{18}	1.010^{20}	1.4548^{20}	
3297	1,3-Dichloro-1,1,3,3-tetramethyldisiloxane		$C_4H_{12}Cl_2OSi_2$	2401-73-2	203.214	liq	-37.5	138	1.038^{20}		
3298	2,5-Dichlorothiophene		$C_4H_2Cl_2S$	3172-52-9	153.030	liq	-40.5	162	1.4422^{20}	1.5626^{20}	i H_2O; msc EtOH, eth; s ctc
3299	2,3-Dichlorotoluene		$C_7H_6Cl_2$	32768-54-0	161.029		6	207.5	1.2458^{20}	1.5511^{20}	vs bz
3300	2,4-Dichlorotoluene		$C_7H_6Cl_2$	95-73-8	161.029	liq	-13.5	201	1.2476^{20}	1.5511^{20}	i H_2O; s ctc
3301	2,5-Dichlorotoluene		$C_7H_6Cl_2$	19398-61-9	161.029		2.5	200	1.2535^{20}	1.5449^{20}	i H_2O; s bz
3302	2,6-Dichlorotoluene		$C_7H_6Cl_2$	118-69-4	161.029		25.8	198	1.2686^{20}	1.5507^{20}	i H_2O; s chl
3303	3,4-Dichlorotoluene		$C_7H_6Cl_2$	95-75-0	161.029	liq	-15.2	208.9	1.2564^{20}	1.5471^{20}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
3304	1,3-Dichloro-1,3,5-triazine-2,4,6(1*H*,3*H*,5*H*)-trione	Dichlorocyanuric acid	$C_3HCl_2N_3O_3$	2782-57-2	197.964	cry	226.6				
3305	1,2-Dichloro-4-(trichloromethyl) benzene		$C_7H_3Cl_5$	13014-24-9	264.364		25.8	283.1	1.5913^{20}	1.5886^{20}	
3306	1,2-Dichloro-1,1,2-trifluoroethane	Refrigerant 123a	$C_2HCl_2F_3$	354-23-4	152.930	vol liq or gas	-78	29.5	1.50^{25}		
3307	2,2-Dichloro-1,1,1-trifluoroethane		$C_2HCl_2F_3$	306-83-2	152.930	vol liq or gas	-107	27.82	1.4638^{25}		sl H_2O
3308	2,2-Dichloro-1,1,2-trifluoroethane	Refrigerant 123b	$C_2HCl_2F_3$	812-04-4	152.930			30.2			
3309	2,4-Dichloro-1-(trifluoromethyl) benzene	2,4-Dichlorobenzotrifluoride	$C_7H_3Cl_2F_3$	320-60-5	215.000					1.4802^{20}	
3310	4,5-Dichloro-2-(trifluoromethyl)-1*H*-benzimidazole	Chloroflurazole	$C_8H_3Cl_2F_3N_2$	3615-21-2	255.024		213.5				
3311	Dichlorovinylmethylsilane		$C_3H_6Cl_2Si$	124-70-9	141.072			92.5	1.0868^{20}	1.4270^{20}	dec H_2O
3312	Dichlorvos	Phosphoric acid, 2,2-dichloroethenyl dimethyl ester	$C_4H_7Cl_2O_4P$	62-73-7	220.976			140^{20}, 84^{1}	1.415^{25}		


2,2-Dichloropropanoic acid


2,3-Dichloro-1-propanol


1,3-Dichloro-2-propanol



2,3-Dichloro-1-propanol, phosphate (3:1)



2,3-Dichloropropanoyl chloride



1,1-Dichloropropene



cis-1,2-Dichloropropene



trans-1,2-Dichloropropene



cis-1,3-Dichloropropene



trans-1,3-Dichloropropene



2,3-Dichloropropene



3,6-Dichloropyridazine



2,6-Dichloropyridine



4,6-Dichloro-2-pyrimidinamine



2,4-Dichloropyrimidine


4,7-Dichloroquinoline



5,7-Dichloro-8-quinolinol



2,3-Dichloroquinoxaline



2,5-Dichlorostyrene



1,2-Dichloro-3,4,5,6-tetrafluorobenzene


1,1-Dichloro-1,2,2,2-tetrafluoroethane



1,2-Dichloro-1,1,2,2-tetrafluoroethane



1,2-Dichloro-1,1,2,2-tetramethyldisilane



1,3-Dichloro-1,1,3,3-tetramethyldisiloxane



2,5-Dichlorothiophene



2,3-Dichlorotoluene



2,4-Dichlorotoluene


2,5-Dichlorotoluene



2,6-Dichlorotoluene


3,4-Dichlorotoluene



1,3-Dichloro-1,3,5-triazine-2,4,6(1*H*,3*H*,5*H*)-trione



1,2-Dichloro-4-(trichloromethyl)benzene


1,2-Dichloro-1,1,2-trifluoroethane



2,2-Dichloro-1,1,1-trifluoroethane


2,2-Dichloro-1,1,2-trifluoroethane



2,4-Dichloro-1-(trifluoromethyl)benzene



4,5-Dichloro-2-(trifluoromethyl)-1*H*-benzimidazole



Dichlorovinylmethylsilane



Dichlorvos


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3313	Diclofop-methyl	Methyl 2-[4-(2,4-dichlorophenoxy)phenoxy] propanoate	$C_{16}H_{14}Cl_2O_4$	51338-27-3	341.186		40	$176^{0.1}$			
3314	Dicrotophos		$C_8H_{16}NO_5P$	141-66-2	237.191			400; $130^{0.1}$	1.216^{15}		
3315	Dicumarol		$C_{19}H_{12}O_6$	66-76-6	336.294	nd	290				
3316	Dicyanamide	Cyanocyanamide	C_2HN_3	504-66-5	67.049	aq soln only					
3317	*o*-Dicyanobenzene	*o*-Phthalodinitrile	$C_8H_4N_2$	91-15-6	128.131	nd (w, lig)	141	150^{10}	1.1250^{25}		sl H_2O, lig; vs EtOH, bz; s eth, ace
3318	*m*-Dicyanobenzene	*m*-Phthalodinitrile	$C_8H_4N_2$	626-17-5	128.131	nd(al)	162	sub	0.992^{40}		sl H_2O; vs EtOH; s eth, bz, chl; i peth
3319	*p*-Dicyanobenzene	*p*-Phthalodinitrile	$C_8H_4N_2$	623-26-7	128.131	nd (w, MeOH)	224	sub			i H_2O; sl EtOH, eth; s bz; vs HOAc
3320	Dicyclohexyl adipate		$C_{18}H_{30}O_4$	849-99-0	310.429		35				s chl
3321	Dicyclohexylamine	*N*-Cyclohexylcyclohexanamine	$C_{12}H_{23}N$	101-83-7	181.318		-0.1	dec 256; 114^{9}	0.9123^{20}	1.4842^{20}	sl H_2O, ctc; s EtOH, eth, bz
3322	Dicyclohexylamine nitrite	*N*-Cyclohexylcyclohexanamine, nitrite	$C_{12}H_{24}N_2O_2$	3129-91-7	228.331	cry	182 dec				
3323	Dicyclohexylcarbodiimide		$C_{13}H_{22}N_2$	538-75-0	206.327		34.5	123^{6}, $99^{0.5}$			
3324	Dicyclohexyl disulfide		$C_{12}H_{22}S_2$	2550-40-5	230.433	liq		195^{20}			
3325	Dicyclohexyl ether		$C_{12}H_{22}O$	4645-15-2	182.302	liq	-36	242.5	0.9227^{20}	1.4741^{20}	
3326	Dicyclohexylmethanone		$C_{13}H_{22}O$	119-60-8	194.313		57	159^{20}	0.986^{0}	1.4860^{20}	s eth, ace, ctc
3327	Dicyclohexylphosphine		$C_{12}H_{23}P$	829-84-5	198.285			281; 129^{8}	0.904^{25}	1.5163^{20}	
3328	Dicyclohexyl phthalate		$C_{20}H_{26}O_4$	84-61-7	330.418	pr (al)	66	225^{4}	1.383^{20}	1.431^{20}	i H_2O; s EtOH, eth; sl chl
3329	*N,N'*-Dicyclohexylthiourea		$C_{13}H_{24}N_2S$	1212-29-9	240.408	cry (MeOH)	180				
3330	1,3-Dicyclohexylurea		$C_{13}H_{24}N_2O$	2387-23-7	224.342		233.8				
3331	Dicyclomine hydrochloride	Dicycloverine hydrochloride	$C_{19}H_{36}ClNO_2$	67-92-5	345.948	cry	165				
3332	Dicyclopentadiene		$C_{10}H_{12}$	1755-01-7	132.202		32	dec 170; 65^{14}	0.9302^{35}	1.5050^{35}	vs eth, EtOH
3333	Dicyclopentyl ether	Cyclopentyl ether	$C_{10}H_{18}O$	10137-73-2	154.249	liq		80^{13}			
3334	Dicyclopropyl ketone		$C_7H_{10}O$	1121-37-5	110.153			161	0.977^{25}	1.4670^{20}	
3335	Didecylamine	*N*-Decyl-1-decanamine	$C_{20}H_{43}N$	1120-49-6	297.562			359.0			
3336	Didecyl ether		$C_{20}H_{42}O$	2456-28-2	298.546		16	$196^{15.5}$	0.8187^{20}		
3337	Didecyl phthalate		$C_{28}H_{46}O_4$	84-77-5	446.663		2.5	240^{3}	0.9639^{20}		
3338	3',4'-Didehydro-β,ψ-caroten-16'-oic acid	Torularhodin	$C_{40}H_{52}O_2$	514-92-1	564.840	purp nd (MeOH-eth)	211				vs py, chl, CS_2
3339	2',3'-Dideoxyinosine	Didanosine	$C_{10}H_{12}N_4O_3$	69655-05-6	236.227	wh cry (EtOH aq)	162				
3340	2,6-Dideoxy-3-*O*-methyl-*ribo*-hexose	Cymarose	$C_7H_{14}O_4$	579-04-4	162.184	pr (eth-peth) nd (ace)	101				vs H_2O, ace, EtOH
3341	Didodecanoyl peroxide	Lauroyl peroxide	$C_{24}H_{46}O_4$	105-74-8	398.620	wh pl	49				i H_2O; s chl
3342	Didodecylamine	*N*-Dodecyl-1-dodecanamine	$C_{24}H_{51}N$	3007-31-6	353.669		53.7	263^{27}			vs bz, eth, EtOH, chl
3343	Didodecyl phosphate		$C_{24}H_{51}O_4P$	7057-92-3	434.633	cry (MeOH)	59				
3344	Didodecyl phthalate	1,2-Benzenedicarboxylic acid, didodecyl ester	$C_{32}H_{54}O_4$	2432-90-8	502.769		22.0	256^{1}	0.9389^{20}		
3345	Dieldrin		$C_{12}H_8Cl_6O$	60-57-1	380.909		175.5		1.75^{25}		i H_2O; sl EtOH; s ace, bz
3346	Dienestrol		$C_{18}H_{18}O_2$	84-17-3	266.335	cry (dil al)	227.5	sub 130			vs ace, eth, EtOH
3347	1,2:8,9-Diepoxy-*p*-menthane	Limonene diepoxide	$C_{10}H_{16}O_2$	96-08-2	168.233		242				
3348	Diethanolamine	Bis(2-hydroxyethyl)amine	$C_4H_{11}NO_2$	111-42-2	105.136		28	268.8	1.0966^{20}	1.4776^{20}	vs H_2O, EtOH; sl eth, bz
3349	Diethatyl, ethyl ester		$C_{16}H_{22}ClNO_3$	38727-55-8	311.804	cry	49.5				
3350	4,4'-Diethoxyazobenzene		$C_{16}H_{18}N_2O_2$	588-52-3	270.326	ye lf (al)	162	dec			i H_2O; sl EtOH; s eth, bz, chl; vs HOAc
3351	3,4-Diethoxybenzaldehyde		$C_{11}H_{14}O_3$	2029-94-9	194.227		22	279; 200^{50}	1.0100^{22}		vs EtOH
3352	1,2-Diethoxybenzene		$C_{10}H_{14}O_2$	2050-46-6	166.217	pr (peth, dil al)	44	219	1.0075^{20}	1.5083^{25}	s EtOH, ctc; vs eth
3353	1,4-Diethoxybenzene		$C_{10}H_{14}O_2$	122-95-2	166.217	pl (dil al)	72	246			vs EtOH; s eth, bz, ctc, chl
3354	4,4-Diethoxy-1-butanamine		$C_8H_{19}NO_2$	6346-09-4	161.243			196	0.933^{25}	1.4275^{20}	
3355	1,1-Diethoxy-*N,N*-dimethylmethanamine		$C_7H_{17}NO_2$	1188-33-6	147.216			129	0.859^{25}	1.4007^{20}	
3356	Diethoxydimethylsilane	Dimethyldiethoxysilane	$C_6H_{16}O_2Si$	78-62-6	148.276	liq	-87	114	0.865^{25}	1.3811^{20}	s ctc
3357	Diethoxydiphenylsilane		$C_{16}H_{20}O_2Si$	2553-19-7	272.415			302; 167^{15}	1.0329^{20}	1.5269^{20}	
3358	2,2-Diethoxyethanamine		$C_6H_{15}NO_2$	645-36-3	133.189	liq	-78	163	0.9159^{25}	1.4123^{25}	vs H_2O, eth, EtOH, chl



Diclofop-methyl



Dicrotophos



Dicumarol



Dicyanamide



o-Dicyanobenzene



m-Dicyanobenzene



p-Dicyanobenzene



Dicyclohexyl adipate



Dicyclohexylamine



Dicyclohexylamine nitrite



Dicyclohexylcarbodiimide



Dicyclohexyl disulfide



Dicyclohexyl ether



Dicyclohexylmethanone



Dicyclohexylphosphine



Dicyclohexyl phthalate



N,N'-Dicyclohexylthiourea



1,3-Dicyclohexylurea



Dicyclomine hydrochloride



Dicyclopentadiene



Dicyclopentyl ether



Dicyclopropyl ketone



Didecylamine



Didecyl ether



Didecyl phthalate



3',4'-Didehydro-β,ψ-caroten-16'-oic acid



2',3'-Dideoxyinosine



2,6-Dideoxy-3-*O*-methyl-*ribo*-hexose



Didodecanoyl peroxide



Didodecylamine



Didodecyl phosphate



Didodecyl phthalate



Dieldrin



Dienestrol



1,2:8,9-Diepoxy-*p*-menthane



Diethanolamine



Diethatyl, ethyl ester



4,4'-Diethoxyazobenzene



3,4-Diethoxybenzaldehyde



1,2-Diethoxybenzene



1,4-Diethoxybenzene


4,4-Diethoxy-1-butanamine



1,1-Diethoxy-*N,N*-dimethylmethanamine



Diethoxydimethylsilane



Diethoxydiphenylsilane



2,2-Diethoxyethanamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3359	1,1-Diethoxyethane	Acetal	$C_6H_{14}O_2$	105-57-7	118.174	liq	-100	102.25	0.8254^{20}	1.3834^{20}	s H_2O, chl; msc EtOH, eth; vs ace
3360	1,2-Diethoxyethane	Ethylene glycol diethyl ether	$C_6H_{14}O_2$	629-14-1	118.174	liq	-74.0	121.2	0.8351^{25}	1.3898^{25}	vs ace, bz, eth, EtOH
3361	1,1-Diethoxyethene		$C_6H_{12}O_2$	2678-54-8	116.158			68^{100}	0.7932^{20}	1.3643^{21}	
3362	Diethoxymethane		$C_5H_{12}O_2$	462-95-3	104.148	liq	-66.5	88	0.8319^{20}	1.3748^{18}	s H_2O; msc EtOH; vs ace, bz; sl chl
3363	2-(Diethoxymethyl)furan		$C_9H_{14}O_3$	13529-27-6	170.205			191.5	0.9976^{20}	1.4451^{20}	vs EtOH
3364	Diethoxymethylphenylsilane		$C_{11}H_{18}O_2Si$	775-56-4	210.346			218	0.9627^{20}	1.4690^{20}	
3365	Diethoxymethylsilane		$C_5H_{14}O_2Si$	2031-62-1	134.250			98	0.829^{25}		
3366	1,1-Diethoxypentane		$C_9H_{20}O_2$	3658-79-5	160.254			59^{12}	0.829^{22}	1.4029^{22}	
3367	1,1-Diethoxypropane		$C_7H_{16}O_2$	4744-08-5	132.201			123	0.825^{20}	1.3924^{19}	s H_2O, ace, bz; vs EtOH, eth
3368	2,2-Diethoxypropane		$C_7H_{16}O_2$	126-84-1	132.201			114	0.8200^{21}	1.3891^{20}	s EtOH, ace, bz; vs eth; sl ctc
3369	3,3-Diethoxy-1-propene	Acrolein, diethyl acetal	$C_7H_{14}O_2$	3054-95-3	130.185			123.5	0.8543^{15}	1.4000^{20}	sl H_2O; msc EtOH, eth
3370	3,3-Diethoxy-1-propyne		$C_7H_{12}O_2$	10160-87-9	128.169			139	0.8942^{22}	1.4140^{20}	vs ace, eth, EtOH, chl
3371	*N,N*-Diethylacetamide		$C_6H_{13}NO$	685-91-6	115.173			185.5	0.9130^{17}	1.4374^{17}	s H_2O, EtOH; msc eth, ace, bz; sl ctc
3372	Diethyl 2-acetamidomalonate		$C_9H_{15}NO_5$	1068-90-2	217.219	cry (al,bz-peth)	96.3	185^{20}			sl H_2O, eth; s tfa, EtOH
3373	*N,N*-Diethylacetoacetamide		$C_8H_{15}NO_2$	2235-46-3	157.211	liq		76^{13}			
3374	Diethyl acetylphosphonate		$C_6H_{13}O_4P$	919-19-7	180.138			114^{20}	1.1005^{20}	1.4200^{26}	
3375	Diethyl 2-acetylsuccinate		$C_{10}H_{16}O_5$	1115-30-6	216.231			$255; 133^{17}$	1.081^{20}	1.4346^{20}	i H_2O; s EtOH, eth, bz; sl chl
3376	Diethyl adipate		$C_{10}H_{18}O_4$	141-28-6	202.248	liq	-19.8	245	1.0076^{20}	1.4272^{20}	i H_2O; s EtOH, eth
3377	Diethyl 2-allylmalonate		$C_{10}H_{16}O_4$	2049-80-1	200.232			$222.5; 93^{6}$	1.0098^{20}	1.4305^{20}	i H_2O; vs EtOH, eth; s ctc
3378	Diethylamine	*N*-Ethylethanamine	$C_4H_{11}N$	109-89-7	73.137	liq	-49.8	55.5	0.7056^{20}	1.3864^{20}	vs H_2O; msc EtOH; s eth, ctc
3379	Diethylamine hydrochloride	*N*-Ethylethanamine hydrochloride	$C_4H_{12}ClN$	660-68-4	109.598	lf (al-eth)	228.5		1.0477^{22}		vs H_2O, EtOH
3380	(Diethylamino)acetonitrile		$C_6H_{12}N_2$	3010-02-4	112.172			170	0.8660^{20}	1.4260^{20}	s H_2O
3381	4-(Diethylamino)benzaldehyde		$C_{11}H_{15}NO$	120-21-8	177.243	ye nd (w)	41	172^{10}			vs H_2O; s EtOH, eth, bz, ctc
3382	2-(Diethylamino)-*N*-(2,6-dimethylphenyl)acetamide	Lidocaine	$C_{14}H_{22}N_2O$	137-58-6	234.337	nd (bz, al)	68.5	181^{4}			vs bz, eth, EtOH, chl
3383	2-(Diethylamino)-*N*-(2,6-dimethylphenyl)acetamide, monohydrochloride		$C_{14}H_{23}ClN_2O$	73-78-9	270.798		128				vs H_2O
3384	2-Diethylaminoethanol		$C_6H_{15}NO$	100-37-8	117.189	hyg		163	0.8921^{20}	1.4412^{20}	msc H_2O; s EtOH, eth, ace, bz, peth; sl ctc
3385	2-[2-(Diethylamino)ethoxy]ethanol		$C_8H_{19}NO_2$	140-82-9	161.243			$221.5; 92^{7}$	0.9421^{25}	1.4480^{20}	
3386	2-(Diethylamino)ethyl acrylate		$C_9H_{17}NO_2$	2426-54-2	171.237		<-60	81^{10}	0.937^{20}	1.4376^{25}	
3387	2-Diethylaminoethyl 4-aminobenzoate	Procaine	$C_{13}H_{20}N_2O_2$	59-46-1	236.310	nd (w+2) pl (lig or eth)	61				sl H_2O; s EtOH, eth, bz, chl
3388	2-(*N,N*-Diethylamino)ethyl methacrylate		$C_{10}H_{19}NO_2$	105-16-8	185.264			80^{10}	0.92^{30}		
3389	2-(Diethylamino)ethyl 2-phenylbutanoate	Butethamate	$C_{16}H_{25}NO_2$	14007-64-8	263.376			168^{11}		1.4909^{20}	
3390	4-(Diethylamino)-2-hydroxybenzaldehyde		$C_{11}H_{15}NO_2$	17754-90-4	193.243		65.0				
3391	Diethyl 2-aminomalonate		$C_7H_{13}NO_4$	6829-40-9	175.183			$122^{16}, 116^{12}$	1.100^{16}	1.4353^{16}	vs H_2O, EtOH, eth; s ace, bz; i lig
3392	7-(Diethylamino)-4-methyl-2*H*-1-benzopyran-2-one		$C_{14}H_{17}NO_2$	91-44-1	231.291	cry (al, bz-lig)					sl H_2O; s EtOH, eth, ace
3393	3-(Diethylamino)phenol		$C_{10}H_{15}NO$	91-68-9	165.232	orth bipym (CS_2-lig)	78	$276; 170^{15}$			s H_2O, EtOH, eth, CS_2; sl lig
3394	2-(Diethylamino)-1-phenyl-1-propanone	Diethylpropion	$C_{13}H_{19}NO$	90-84-6	205.296	liq		111^{14}			
3395	3-(Diethylamino)-1-propanol		$C_7H_{17}NO$	622-93-5	131.216			189.5	0.8600^{20}	1.4439^{20}	s EtOH; s eth, ace, bz; sl chl
3396	3-(Diethylamino)-1-propyne	*N,N*-Diethyl-2-propargylamine	$C_7H_{13}N$	4079-68-9	111.185	liq		120			
3397	2,6-Diethylaniline		$C_{10}H_{15}N$	579-66-8	149.233		1.5	243	0.906^{25}	1.5452^{20}	



1,1-Diethoxyethane



1,2-Diethoxyethane



1,1-Diethoxyethene



Diethoxymethane



2-(Diethoxymethyl)furan



Diethoxymethylphenylsilane



Diethoxymethylsilane



1,1-Diethoxypentane



1,1-Diethoxypropane



2,2-Diethoxypropane



3,3-Diethoxy-1-propene



3,3-Diethoxy-1-propyne



N,N-Diethylacetamide



Diethyl 2-acetamidomalonate



N,N-Diethylacetoacetamide



Diethyl acetylphosphonate



Diethyl 2-acetylsuccinate



Diethyl adipate



Diethyl 2-allylmalonate



Diethylamine



Diethylamine hydrochloride



(Diethylamino)acetonitrile



4-(Diethylamino)benzaldehyde



2-(Diethylamino)-*N*-(2,6-dimethylphenyl)acetamide



2-(Diethylamino)-*N*-(2,6-dimethylphenyl)acetamide, monohydrochloride



2-Diethylaminoethanol



2-[2-(Diethylamino)ethoxy]ethanol



2-(Diethylamino)ethyl acrylate



2-Diethylaminoethyl 4-aminobenzoate



2-(*N,N*-Diethylamino)ethyl methacrylate



2-(Diethylamino)ethyl 2-phenylbutanoate



4-(Diethylamino)-2-hydroxybenzaldehyde



Diethyl 2-aminomalonate



7-(Diethylamino)-4-methyl-2*H*-1-benzopyran-2-one


3-(Diethylamino)phenol



2-(Diethylamino)-1-phenyl-1-propanone



3-(Diethylamino)-1-propanol



3-(Diethylamino)-1-propyne



2,6-Diethylaniline


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3398	*N,N*-Diethylaniline		$C_{10}H_{15}N$	91-66-7	149.233	ye oil	-38.8	216.3	0.9307^{20}	1.5409^{20}	sl H_2O; s EtOH, ace, ctc; vs eth, chl
3399	Diethylarsine		$C_4H_{11}As$	692-42-2	134.052			105	1.1338^{24}	1.4709	vs ace, bz, eth, EtOH
3400	*N,N*-Diethylbenzamide		$C_{11}H_{15}NO$	1696-17-9	177.243			132^{5}			
3401	*o*-Diethylbenzene	1,2-Diethylbenzene	$C_{10}H_{14}$	135-01-3	134.218	liq	-31.2	184	0.8800^{20}	1.5035^{20}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
3402	*m*-Diethylbenzene	1,3-Diethylbenzene	$C_{10}H_{14}$	141-93-5	134.218	liq	-83.9	181.1	0.8602^{20}	1.4955^{20}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
3403	*p*-Diethylbenzene	1,4-Diethylbenzene	$C_{10}H_{14}$	105-05-5	134.218	liq	-42.83	183.7	0.8620^{20}	1.4967^{20}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
3404	*N,N*-Diethyl-1,4-benzenediamine		$C_{10}H_{16}N_2$	93-05-0	164.247			261			vs bz
3405	Diethyl benzylidenemalonate	Diethyl benzalmalonate	$C_{14}H_{16}O_4$	5292-53-5	248.275		32	216^{30}, 196^{14}	1.1045^{20}	1.5389^{20}	i H_2O; s EtOH, eth, ace, bz
3406	Diethyl benzylmalonate		$C_{14}H_{18}O_4$	607-81-8	250.291			300	1.076^{15}	1.4872^{20}	i H_2O; sl chl
3407	Diethyl benzylphosphonate		$C_{11}H_{17}O_3P$	1080-32-6	228.225			110^{2}		1.4930^{20}	s ctc
3408	Diethylbromoacetamide	2-Bromo-2-ethylbutanamide	$C_6H_{12}BrNO$	511-70-6	194.069		67				sl H_2O, chl; vs EtOH, eth, bz
3409	Diethyl 2-bromomalonate	Ethyl bromomalonate	$C_7H_{11}BrO_4$	685-87-0	239.064		-54	dec 254	1.4022^{25}	1.4521^{20}	i H_2O; msc EtOH, eth; s ace, ctc
3410	*N,N*-Diethylbutanamide		$C_8H_{17}NO$	1114-76-7	143.227			206	0.8884^{20}	1.4403^{25}	vs H_2O, EtOH
3411	Diethyl 2-butylmalonate	Pentane-1,1-dicarboxylic acid, diethyl ester	$C_{11}H_{20}O_4$	133-08-4	216.275			238	0.9764^{20}	1.4250^{20}	vs EtOH, eth
3412	Diethyl 2-butynedioate		$C_8H_{10}O_4$	762-21-0	170.163		0.8	184^{200}	1.0075^{20}	1.4425^{20}	s EtOH, eth, ctc
3413	Diethylcarbamazine citrate		$C_{16}H_{29}N_3O_8$	1642-54-2	391.416	cry	138				
3414	Diethylcarbamic chloride		$C_5H_{10}ClNO$	88-10-8	135.592			186			
3415	*N,N'*-Diethylcarbanilide		$C_{17}H_{20}N_2O$	85-98-3	268.353	cry (al)	79				i H_2O; vs EtOH; s chl
3416	Diethyl carbonate	Ethyl carbonate	$C_5H_{10}O_3$	105-58-8	118.131	liq	-43	126	0.9692^{25}	1.3845^{20}	i H_2O; s EtOH, eth, chl
3417	*O,O*-Diethyl chloridothionophosphate	Diethyl thiophosphoryl chloride	$C_4H_{10}ClO_2PS$	2524-04-1	188.613			45^{3}			s ctc
3418	Diethylchloroaluminum		$C_4H_{10}AlCl$	96-10-6	120.557			134^{70}			
3419	Diethyl chloromalonate	Ethyl chloromalonate	$C_7H_{11}ClO_4$	14064-10-9	194.613			222	1.2040^{20}	1.4327^{20}	i H_2O; msc EtOH, eth, chl; s CS_2
3420	Diethyl chlorophosphonate	Diethoxyphosphoryl chloride	$C_4H_{10}ClO_3P$	814-49-3	172.547			93.5	1.205^{19}	1.4170^{20}	
3421	Diethylcyanamide		$C_5H_{10}N_2$	617-83-4	98.146	liq	-80.6	188	0.854^{20}	1.4126^{25}	i H_2O; s EtOH, eth
3422	Diethyl 1,1-cyclobutanedicarboxylate		$C_{10}H_{16}O_4$	3779-29-1	200.232			224	1.0456^{20}	1.4330^{26}	vs EtOH; sl ctc
3423	1,1-Diethylcyclohexane		$C_{10}H_{20}$	78-01-3	140.266			179.5			
3424	Diethyl 1,1-cyclopropanedicarboxylate		$C_9H_{14}O_4$	1559-02-0	186.205			215; 100^{12}	1.055^{25}	1.4345^{18}	vs EtOH, eth
3425	Diethyl dibutylmalonate		$C_{15}H_{28}O_4$	596-75-8	272.381			150^{12}	0.9457^{20}	1.4341^{20}	i H_2O; s EtOH, eth, ctc
3426	Diethyl dicarbonate	Pyrocarbonic acid diethyl ester	$C_6H_{10}O_5$	1609-47-8	162.140			93^{18}	1.120^{20}	1.3960^{20}	vs ace, EtOH, lig
3427	Diethyl [(diethanolamino)methyl] phosphonate		$C_9H_{22}NO_5P$	2781-11-5	255.249	liq		$150^{0.01}$			
3428	5,5-Diethyldihydro-2*H*-1,3-oxazine-2,4(3*H*)-dione	Diethadione	$C_8H_{13}NO_3$	702-54-5	171.194	cry (eth)	97.5				
3429	Diethyl 1,4-dihydro-2,4,6-trimethyl-3,5-pyridinedicarboxylate	3,5-Diethoxycarbonyl-1,4-dihydrocollidine	$C_{14}H_{21}NO_4$	632-93-9	267.322	lt bl flr pl (al)	131				sl H_2O, EtOH, eth, CS_2; vs chl
3430	Diethyldimethyllead	Diethyldimethylplumbane	$C_6H_{16}Pb$	1762-27-2	295.4	col liq		51^{13}	1.79^{20}		
3431	Diethyl 2,6-dimethyl-3,5-pyridinedicarboxylate		$C_{13}H_{17}NO_4$	1149-24-2	251.279		71	301; 208^{40}			i H_2O; s EtOH, eth, bz, chl, lig
3432	Diethyl 3,5-dimethylpyrrole-2,4-dicarboxylate		$C_{12}H_{17}NO_4$	2436-79-5	239.268	nd (dil al)	137.8				i H_2O; sl EtOH, eth; s ace, bz, HOAc
3433	Diethyl disulfide		$C_4H_{10}S_2$	110-81-6	122.252	liq	-101.5	154.0	0.9931^{20}	1.5073^{20}	sl H_2O; msc EtOH, eth
3434	*N,N*-Diethyldodecanamide		$C_{16}H_{33}NO$	3352-87-2	255.439			166^{2}	0.847^{25}	1.4545^{20}	s chl
3435	Diethylene glycol	Diglycol	$C_4H_{10}O_3$	111-46-6	106.120	liq	-10.4	245.8	1.1197^{15}	1.4472^{20}	s H_2O, EtOH, eth, chl
3436	Diethylene glycol, bischloroformate	Oxydi-2,1-ethanediyl carbonochloridate	$C_6H_8Cl_2O_5$	106-75-2	231.031	liq		126^{5}	1.39^{20}	1.4542^{20}	
3437	Diethylene glycol diacetate		$C_8H_{14}O_5$	628-68-2	190.194		18	200	1.1068^{15}	1.4348^{20}	vs EtOH
3438	Diethylene glycol dibenzoate		$C_{18}H_{18}O_5$	120-55-8	314.333		33.5	280^{24}, 250^{1}	1.1690^{15}		vs H_2O, EtOH



N,N-Diethylaniline



Diethylarsine



N,N-Diethylbenzamide



o-Diethylbenzene



m-Diethylbenzene



p-Diethylbenzene



N,N-Diethyl-1,4-benzenediamine



Diethyl benzylidenemalonate



Diethyl benzylmalonate



Diethyl benzylphosphonate



Diethylbromoacetamide



Diethyl 2-bromomalonate



N,N-Diethylbutanamide



Diethyl 2-butylmalonate



Diethyl 2-butynedioate



Diethylcarbamazine citrate



Diethylcarbamic chloride



N,N'-Diethylcarbanilide



Diethyl carbonate



O,O-Diethyl chloridothionophosphate


Diethylchloroaluminum



Diethyl chloromalonate



Diethyl chlorophosphonate



Diethylcyanamide



Diethyl 1,1-cyclobutanedicarboxylate



1,1-Diethylcyclohexane



Diethyl 1,1-cyclopropanedicarboxylate


Diethyl dibutylmalonate



Diethyl dicarbonate



Diethyl [(diethanolamino)methyl]phosphonate



5,5-Diethyldihydro-2*H*-1,3-oxazine-2,4(3*H*)-dione



Diethyl 1,4-dihydro-2,4,6-trimethyl-3,5-pyridinedicarboxylate



Diethyldimethyllead



Diethyl 2,6-dimethyl-3,5-pyridinedicarboxylate



Diethyl 3,5-dimethylpyrrole-2,4-dicarboxylate



Diethyl disulfide


N,N-Diethyldodecanamide



Diethylene glycol



Diethylene glycol, bischloroformate



Diethylene glycol diacetate



Diethylene glycol dibenzoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3439	Diethylene glycol dibutyl ether	Bis(2-butoxyethyl) ether	$C_{12}H_{26}O_3$	112-73-2	218.332	liq	-60	256	0.885^{25}	1.4235^{20}	
3440	Diethylene glycol diethyl ether	Bis(2-ethoxyethyl) ether	$C_8H_{18}O_3$	112-36-7	162.227	liq	-45	188	0.9063^{20}	1.4115^{20}	vs H_2O, EtOH; s eth
3441	Diethylene glycol dimethacrylate	Oxydiethylene methacrylate	$C_{12}H_{18}O_5$	2358-84-1	242.268			>200; 150^{8}	1.0821^{20}	1.4571^{25}	
3442	Diethylene glycol dimethyl ether	Diglyme	$C_6H_{14}O_3$	111-96-6	134.173	liq	-68	162	0.9434^{20}	1.4097^{20}	msc H_2O, EtOH, eth
3443	Diethylene glycol dinitrate	2,2'-Oxybisethanol, dinitrate	$C_4H_8N_2O_7$	693-21-0	196.116			$44^{0.01}$			
3444	Diethylene glycol monobutyl ether		$C_8H_{18}O_3$	112-34-5	162.227	liq	-68	231	0.9553^{20}	1.4306^{20}	msc H_2O; vs EtOH, eth, ace; s bz
3445	Diethylene glycol monobutyl ether acetate	2-(2-Butoxyethoxy)ethyl acetate	$C_{10}H_{20}O_4$	124-17-4	204.264	liq	-32	245	0.985^{20}	1.4262^{20}	vs ace, eth, EtOH
3446	Diethylene glycol monododecanoate	2-(2-Hydroxyethoxy)ethyl laurate	$C_{16}H_{32}O_4$	141-20-8	288.423	lt ye	17.5	>270	0.96^{25}		msc EtOH, eth, ace; s bz, tol
3447	Diethylene glycol monoethyl ether	Carbitol	$C_6H_{14}O_3$	111-90-0	134.173	hyg liq		196	0.9885^{20}	1.4300^{20}	msc H_2O, EtOH, ace, bz; vs eth
3448	Diethylene glycol monoethyl ether acetate	Carbitol acetate	$C_8H_{16}O_4$	112-15-2	176.211	liq	-25	218.5	1.0096^{20}	1.4213^{20}	vs H_2O, ace, eth, EtOH
3449	Diethylene glycol monohexyl ether	2-[2-(Hexyloxy)ethoxy]ethanol	$C_{10}H_{22}O_3$	112-59-4	190.280	col liq	-28	258; 192^{100}			
3450	Diethylene glycol monomethyl ether	2-(2-Methoxyethoxy)ethanol	$C_5H_{12}O_3$	111-77-3	120.147			193	1.035^{20}	1.4264^{20}	msc H_2O, ace; vs EtOH, eth
3451	Diethylene glycol monopropyl ether		$C_7H_{16}O_3$	6881-94-3	148.200	liq	-53.3	213; 124^{4}			
3452	*N,N*-Diethyl-1,2-ethanediamine	*N,N*-Diethylethylenediamine	$C_6H_{16}N_2$	100-36-7	116.204			144	0.8280^{20}	1.4340^{20}	msc H_2O; s EtOH, eth, ctc, tol
3453	*N,N'*-Diethyl-1,2-ethanediamine		$C_6H_{16}N_2$	111-74-0	116.204			146	0.8280^{20}	1.4340^{20}	vs H_2O, eth, EtOH, tol
3454	Diethyl ether	Ethyl ether	$C_4H_{10}O$	60-29-7	74.121	liq	-116.2	34.5	0.7138^{20}	1.3526^{20}	sl H_2O; msc EtOH, bz, eth; vs ace
3455	Diethyl (ethoxymethylene) malonate	2-Ethoxy-1,1-bis(ethoxycarbonyl)ethene	$C_{10}H_{16}O_5$	87-13-8	216.231			dec 280; 165^{19}		1.4600^{20}	i H_2O; s EtOH, eth; sl chl
3456	Diethyl ethylidenemalonate		$C_9H_{14}O_4$	1462-12-0	186.205			116^{17}, 86^{3}	1.0404^{20}	1.4308^{17}	vs eth, EtOH
3457	Diethyl ethylmalonate		$C_9H_{16}O_4$	133-13-1	188.221			208; 98^{12}	1.006^{20}	1.4166^{20}	sl H_2O; vs EtOH, eth, ace, chl
3458	Diethyl ethylphenylmalonate		$C_{15}H_{20}O_4$	76-67-5	264.318			170^{19}	1.071^{20}	1.4896^{25}	i H_2O; s EtOH, eth; sl chl
3459	Diethyl ethylphosphonate		$C_6H_{15}O_3P$	78-38-6	166.155			198; 90^{16}	1.0259^{20}	1.4163^{20}	sl H_2O; s EtOH, eth
3460	*N,N*-Diethylformamide		$C_5H_{11}NO$	617-84-5	101.147			177.5	0.9080^{19}	1.4321^{25}	msc H_2O, ace, bz; vs EtOH, eth
3461	Diethyl fumarate		$C_8H_{12}O_4$	623-91-6	172.179		0.8	214	1.0452^{20}	1.4412^{20}	i H_2O; s ace, chl
3462	Diethyl glutarate		$C_9H_{16}O_4$	818-38-2	188.221	syr liq	-24.1	236.5	1.0220^{20}	1.4241^{20}	vs eth
3463	3,4-Diethylhexane		$C_{10}H_{22}$	19398-77-7	142.282			163.9	0.7472^{25}	1.4190^{20}	
3464	Di-2-ethylhexyl maleate		$C_{20}H_{36}O_4$	142-16-5	340.498			156^{7}	0.94^{20}		
3465	1,2-Diethylhydrazine		$C_4H_{12}N_2$	1615-80-1	88.151			85.5	0.797^{26}	1.4204^{20}	vs bz, eth, EtOH
3466	Diethyl 1,2-hydrazinedicarboxylate	Diethyl bicarbamate	$C_6H_{12}N_2O_4$	4114-28-7	176.170	nd (chl), pr (w)	135	dec 250	1.324^{8}		vs eth, EtOH
3467	Diethyl hydrogen phosphate	Diethyl phosphate	$C_4H_{11}O_4P$	598-02-7	154.101	syr		dec 203; $87^{0.0001}$	1.1800^{20}	1.4170^{20}	vs eth
3468	*N,N*-Diethyl-4-hydroxy-3-methoxybenzamide	Ethamivan	$C_{12}H_{17}NO_3$	304-84-7	223.268		95				s chl
3469	Diethyl iminodiacetate		$C_8H_{15}NO_4$	6290-05-7	189.210	orth cry	247 dec				
3470	Diethyl isobutylmalonate		$C_{11}H_{20}O_4$	10203-58-4	216.275				0.9804^{20}	1.4236^{20}	i H_2O; vs EtOH, eth; s chl
3471	Diethyl isophthalate		$C_{12}H_{14}O_4$	636-53-3	222.237		11.5	302	1.1239^{17}	1.508^{18}	i H_2O
3472	Diethyl isopropylidenemalonate		$C_{10}H_{16}O_4$	6802-75-1	200.232			176.5; 116^{14}	1.0282^{18}	1.4486^{17}	vs ace, EtOH
3473	Diethyl isopropylmalonate	Ethyl isopropylmalonate	$C_{10}H_{18}O_4$	759-36-4	202.248			215	0.9961^{20}	1.4188^{21}	sl H_2O, ctc; vs EtOH, eth; s chl
3474	Diethyl ketomalonate	Ethyl mesoxalate	$C_7H_{10}O_5$	609-09-6	174.151	pa ye grn oil	-30	210; 105^{19}	1.1419^{16}	1.4310^{22}	vs H_2O; s EtOH, eth, chl; i CS_2
3475	Diethyl malate	Diethyl hydroxybutanedioate	$C_8H_{14}O_5$	7554-12-3	190.194			253; 124^{13}	1.1290^{20}		
3476	Diethyl maleate		$C_8H_{12}O_4$	141-05-9	172.179	liq	-8.8	223	1.0662^{20}	1.4416^{20}	i H_2O; s EtOH, eth; sl chl
3477	Diethyl malonate		$C_7H_{12}O_4$	105-53-3	160.168	liq	-50	200	1.0551^{20}	1.4139^{20}	sl H_2O; msc EtOH, eth; vs ace, bz
3478	Diethyl mercury		$C_4H_{10}Hg$	627-44-1	258.71			159; 57^{16}	2.43^{20}		s eth; sl EtOH
3479	Diethylmethylamine	*N*-Ethyl-*N*-methylethanamine	$C_5H_{13}N$	616-39-7	87.164	liq	-196	66	0.703^{25}	1.3879^{25}	vs H_2O, EtOH, eth



Diethylene glycol dibutyl ether



Diethylene glycol diethyl ether



Diethylene glycol dimethacrylate



Diethylene glycol dimethyl ether



Diethylene glycol dinitrate



Diethylene glycol monobutyl ether



Diethylene glycol monobutyl ether acetate



Diethylene glycol monododecanoate



Diethylene glycol monoethyl ether



Diethylene glycol monoethyl ether acetate



Diethylene glycol monohexyl ether



Diethylene glycol monomethyl ether



Diethylene glycol monopropyl ether



N,N-Diethyl-1,2-ethanediamine



N,N'-Diethyl-1,2-ethanediamine



Diethyl ether



Diethyl (ethoxymethylene)malonate



Diethyl ethylidenemalonate



Diethyl ethylmalonate



Diethyl ethylphenylmalonate



Diethyl ethylphosphonate



N,N-Diethylformamide



Diethyl fumarate



Diethyl glutarate



3,4-Diethylhexane



Di-2-ethylhexyl maleate



1,2-Diethylhydrazine



Diethyl 1,2-hydrazinedicarboxylate



Diethyl hydrogen phosphate



N,N-Diethyl-4-hydroxy-3-methoxybenzamide



Diethyl iminodiacetate



Diethyl isobutylmalonate



Diethyl isophthalate



Diethyl isopropylidenemalonate



Diethyl isopropylmalonate



Diethyl ketomalonate


Diethyl malate



Diethyl maleate



Diethyl malonate



Diethyl mercury



Diethylmethylamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3480	*N,N*-Diethyl-2-methylaniline		$C_{11}H_{17}N$	606-46-2	163.260	liq	-60	209	0.9286^{20}	1.5153^{20}	sl H_2O; msc EtOH, eth; s ctc
3481	*N,N*-Diethyl-4-methylaniline		$C_{11}H_{17}N$	613-48-9	163.260			229	0.9242^{16}		sl H_2O; msc EtOH, eth
3482	*N,N*-Diethyl-3-methylbenzamide	DEET	$C_{12}H_{17}NO$	134-62-3	191.269			160^{19}, 111^{1}	0.996^{20}	1.5212^{20}	vs H_2O, bz, eth, EtOH
3483	1,3-Diethyl-5-methylbenzene		$C_{11}H_{16}$	2050-24-0	148.245	liq	-74.1	205	0.8748^{20}	1.5027^{20}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
3484	*N*4,*N*4-Diethyl-2-methyl-1,4-benzenediamine, monohydrochloride	4-*N,N*-Diethyl-1,4-diamino-2-methylbenzene, hydrochloride	$C_{11}H_{19}ClN_2$	2051-79-8	214.735	cry	250 dec				
3485	*N,N*-Diethyl-3-methylbutanamide	Isovaleryl diethylamide	$C_9H_{19}NO$	533-32-4	157.253			211	0.8764^{20}	1.4422^{20}	vs eth, EtOH
3486	Diethyl methylenesuccinate		$C_9H_{14}O_4$	2409-52-1	186.205		58.5	228	1.0467^{20}	1.4377^{20}	msc EtOH; s eth, bz; vs ace
3487	Diethyl methylmalonate		$C_8H_{14}O_4$	609-08-5	174.195			201	1.0225^{20}	1.4126^{20}	sl H_2O; vs EtOH, eth, ace, chl
3488	Diethyl methylphosphonate		$C_5H_{13}O_3P$	683-08-9	152.129			194	1.0406^{30}	1.4101^{30}	s H_2O, EtOH, eth; i bz
3489	*N,N*-Diethyl-4-methyl-1-piperazinecarboxamide	Diethylcarbamazine	$C_{10}H_{21}N_3O$	90-89-1	199.293		48	110^{3}			
3490	3,3-Diethyl-5-methyl-2,4-piperidinedione		$C_{10}H_{17}NO_2$	125-64-4	183.248		75.5				s H_2O, bz, chl, EtOH
3491	*N,N*-Diethyl-1-naphthalenamine		$C_{14}H_{17}N$	84-95-7	199.292			285	1.013^{20}	1.5961^{20}	s EtOH, eth, bz; sl ctc
3492	*N,N*-Diethyl-4-nitroaniline		$C_{10}H_{14}N_2O_2$	2216-15-1	194.230	ye nd (lig) pl (al)	77.5		1.225^{25}		s EtOH; sl lig
3493	*N,N*-Diethyl-4-nitrosoaniline		$C_{10}H_{14}N_2O$	120-22-9	178.230	grn mcl pr (eth) grn lf (ace)	87.5		1.24^{15}		sl H_2O; s EtOH, eth, ace, chl
3494	Diethyl nonanedioate	Diethyl azelate	$C_{13}H_{24}O_4$	624-17-9	244.328	liq	-18.5	291.5	0.9729^{20}	1.4351^{20}	i H_2O; s EtOH, eth
3495	Diethyl oxalate		$C_6H_{10}O_4$	95-92-1	146.141	liq	-40.6	185.7	1.0785^{20}	1.4101^{20}	sl H_2O; msc EtOH, eth, ace; s ctc
3496	Diethyl oxobutanedioate	Diethyl oxalacetate	$C_8H_{12}O_5$	108-56-5	188.178			131^{24}	1.131^{20}	1.4561^{17}	i H_2O; msc EtOH, eth, bz; vs ace
3497	Diethyl 3-oxo-1,5-pentanedioate	Diethyl 1,3-acetonedicarboxylate	$C_9H_{14}O_5$	105-50-0	202.204			250	1.113^{20}		sl H_2O; msc EtOH
3498	3,3-Diethylpentane	Tetraethylmethane	C_9H_{20}	1067-20-5	128.255	liq	-33.1	146.3	0.7536^{20}	1.4206^{20}	i H_2O; s eth, bz
3499	N^1,N^1-Diethyl-1,4-pentanediamine	Novoldiamine	$C_9H_{22}N_2$	140-80-7	158.284			201	0.814^{20}	1.4429^{20}	
3500	2,2-Diethyl-4-pentenamide	Novonal	$C_9H_{17}NO$	512-48-1	155.237	wh pow	75.5				vs eth, EtOH
3501	Diethyl 2-pentenedioate	Diethyl glutaconate	$C_9H_{14}O_4$	2049-67-4	186.205			237	1.0496^{20}	1.4411^{20}	vs eth, EtOH
3502	Diethylperoxide		$C_4H_{10}O_2$	628-37-5	90.121	liq	-70	65	0.8240^{19}	1.3715^{17}	sl H_2O; msc EtOH, eth
3503	*N,N*-Diethyl-10*H*-phenothiazine-10-ethanamine	Diethazine	$C_{18}H_{22}N_2S$	60-91-3	298.446	oil		$167^{0.5}$			i H_2O; s dil HCl
3504	*N,N*-Diethyl-α-phenylbenzenemethanamine	*N,N*-Diethylbenzhydrylamine	$C_{17}H_{21}N$	519-72-2	239.356		58.5	170^{17}			
3505	Diethyl phenylmalonate		$C_{13}H_{16}O_4$	83-13-6	236.264		16.5	dec 205; 168^{12}	1.0950^{20}	1.4977^{20}	vs ace, EtOH
3506	Diethyl phenylphosphonite		$C_{10}H_{15}O_2P$	1638-86-4	198.199			235; 62^{1}	1.032^{16}		
3507	5,5-Diethyl-1-phenyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	Phenetharbital	$C_{14}H_{16}N_2O_3$	357-67-5	260.288		178				vs EtOH
3508	Diethylphosphine		$C_4H_{11}P$	627-49-6	90.104			85	0.786^{20}		
3509	Diethyl phosphonate		$C_4H_{11}O_3P$	762-04-9	138.102			54^{6}			s ctc
3510	*O,O*′-Diethyl phosphorodithionate		$C_4H_{11}O_2PS_2$	298-06-6	186.233						s H_2O
3511	Diethyl phthalate		$C_{12}H_{14}O_4$	84-66-2	222.237	liq	-40.5	295	1.232^{14}	1.5000^{21}	i H_2O; msc EtOH, eth; s ace, bz, ctc
3512	3,3-Diethyl-2,4-piperidinedione	Piperidione	$C_9H_{15}NO_2$	77-03-2	169.221	nd (w)	104				vs H_2O, EtOH, chl, MeOH
3513	*N,N*-Diethylpropanamide		$C_7H_{15}NO$	1114-51-8	129.200			191	0.8972^{20}	1.4425^{20}	vs EtOH
3514	*N,N*-Diethyl-1,3-propanediamine		$C_7H_{18}N_2$	104-78-9	130.231			168.5	0.822^{20}	1.443^{20}	
3515	Diethylpropanedioic acid	Diethylmalonic acid	$C_7H_{12}O_4$	510-20-3	160.168	pr (w,bz)	127 dec				vs H_2O, EtOH, eth; sl bz, chl
3516	2,2-Diethyl-1,3-propanediol		$C_7H_{16}O_2$	115-76-4	132.201		61.5	240.5	1.050^{20}	1.4574^{25}	vs H_2O, EtOH, eth; s chl
3517	Diethyl 2-propylmalonate		$C_{10}H_{18}O_4$	2163-48-6	202.248			$221; 114^{22}$	0.989^{20}	1.4197^{20}	sl H_2O; vs EtOH, eth
3518	*N,N*-Diethyl-3-pyridinecarboxamide	Nikethamide	$C_{10}H_{14}N_2O$	59-26-7	178.230	ye solid or visc liq	25	dec 280; 175^{25}	1.060^{25}	1.525^{20}	sl DMSO



N,N-Diethyl-2-methylaniline



N,N-Diethyl-4-methylaniline



N,N-Diethyl-3-methylbenzamide



1,3-Diethyl-5-methylbenzene



*N*4,*N*4-Diethyl-2-methyl-1,4-benzenediamine, monohydrochloride



N,N-Diethyl-3-methylbutanamide



Diethyl methylenesuccinate



Diethyl methylmalonate



Diethyl methylphosphonate



N,N-Diethyl-4-methyl-1-piperazinecarboxamide



3,3-Diethyl-5-methyl-2,4-piperidinedione



N,N-Diethyl-1-naphthalenamine



N,N-Diethyl-4-nitroaniline



N,N-Diethyl-4-nitrosoaniline



Diethyl nonanedioate



Diethyl oxalate



Diethyl oxobutanedioate



Diethyl 3-oxo-1,5-pentanedioate



3,3-Diethylpentane



N′,*N*′-Diethyl-1,4-pentanediamine



2,2-Diethyl-4-pentenamide



Diethyl 2-pentenedioate



Diethylperoxide



N,N-Diethyl-10*H*-phenothiazine-10-ethanamine



N,N-Diethyl-α-phenylbenzenemethanamine



Diethyl phenylmalonate



Diethyl phenylphosphonite



5,5-Diethyl-1-phenyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione



Diethylphosphine



Diethyl phosphonate



O,O-Diethyl phosphorodithionate



Diethyl phthalate



3,3-Diethyl-2,4-piperidinedione



N,N-Diethylpropanamide


N,N-Diethyl-1,3-propanediamine



Diethylpropanedioic acid



2,2-Diethyl-1,3-propanediol



Diethyl 2-propylmalonate



N,N-Diethyl-3-pyridinecarboxamide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3519	*N,N*-Diethyl-4-pyridinecarboxamide	Isonicotinic acid diethylamide	$C_{10}H_{14}N_2O$	530-40-5	178.230			119[1]		1.525[20]	vs H_2O, ace, eth, EtOH
3520	3,3-Diethyl-2,4(1*H*,3*H*)-pyridinedione	Pyrithyldione	$C_9H_{13}NO_2$	77-04-3	167.205		90.7				
3521	Diethyl sebacate		$C_{14}H_{26}O_4$	110-40-7	258.354		2.5	305; 188[19]	0.9646[20]	1.4306[20]	sl H_2O, ctc; s EtOH, ace; i bz
3522	Diethyl selenide		$C_4H_{10}Se$	627-53-2	137.08	pa ye	55	108	1.2300[20]	1.4768[20]	
3523	Diethylsilane		$C_4H_{12}Si$	542-91-6	88.224	liq	-134.3	57	0.6843[20]	1.3921[20]	i H_2O
3524	*trans*-Diethylstilbestrol		$C_{18}H_{20}O_2$	56-53-1	268.351	pl (bz)	170.5				vs eth, EtOH, chl
3525	*trans*-Diethylstilbestrol dipropanoate	Clinestrol	$C_{24}H_{28}O_4$	130-80-3	380.477	pr (MeOH)	104				vs bz, eth, EtOH
3526	*trans*-Diethylstilbestrol monomethyl ether	Mestilbol	$C_{19}H_{22}O_2$	18839-90-2	282.377	nd (bz-peth)	117.5	190[0.3]			vs ace, eth, EtOH
3527	Diethyl succinate	Ethyl succinate	$C_8H_{14}O_4$	123-25-1	174.195	liq	-21	217.7	1.0402[20]	1.4201[20]	i H_2O; msc EtOH, eth; s ace, chl
3528	Diethyl sulfate		$C_4H_{10}O_4S$	64-67-5	154.185	oil	-24	208	1.172[25]	1.3989[20]	i H_2O; msc EtOH, eth
3529	Diethyl sulfide		$C_4H_{10}S$	352-93-2	90.187	liq	-103.91	92.1	0.8362[20]	1.4430[20]	sl H_2O, ctc; s EtOH, eth
3530	Diethyl sulfite	Ethyl sulfite	$C_4H_{10}O_3S$	623-81-4	138.185			158; 51[13]	1.1[20]	1.4310[20]	s EtOH, eth
3531	Diethyl sulfone	Ethyl sulfone	$C_4H_{10}O_2S$	597-35-3	122.186	orth pl	73.5	248	1.357[20]		s H_2O, eth; vs bz; i peth
3532	Diethyl sulfoxide		$C_4H_{10}OS$	70-29-1	106.186	syr	14	104[25], 90[15]	1.0092[22]		vs H_2O, eth, EtOH
3533	Diethyl *DL*-tartrate		$C_8H_{14}O_6$	57968-71-5	206.193		18.7	281; 158[14]	1.2046[20]	1.4438[20]	sl H_2O; msc EtOH, eth; s ace, ctc
3534	Diethyl telluride		$C_4H_{10}Te$	627-54-3	185.72	red-ye		137.5	1.599[15]	1.5182[15]	vs EtOH
3535	Diethyl terephthalate		$C_{12}H_{14}O_4$	636-09-9	222.237	mcl pr (al, peth)	44	302	1.0989[45]		i H_2O; vs EtOH, eth
3536	Diethyl thiodipropionate		$C_{10}H_{18}O_4S$	673-79-0	234.313			174[15], 121[2]	1.1034[20]	1.4655[20]	
3537	*N,N'*-Diethylthiourea		$C_5H_{12}N_2S$	105-55-5	132.227		78	dec			s H_2O, EtOH; vs eth; sl ctc
3538	*N,N*-Diethyl-1,1,1-trimethylsilanamine	(Diethylamino)trimethylsilane	$C_7H_{19}NSi$	996-50-9	145.319			126.3	0.7627[20]	1.4112[20]	
3539	Diethyltrisulfide		$C_4H_{10}S_3$	3600-24-6	154.317		-72.6	85[26]	1.1082[20]	1.5689[13]	
3540	*N,N*-Diethylurea		$C_5H_{12}N_2O$	634-95-7	116.161	pl, nd (eth)	75	95[0.02]			vs H_2O, EtOH, bz, lig; s eth
3541	*N,N'*-Diethylurea		$C_5H_{12}N_2O$	623-76-7	116.161	tab (lig), hyg nd (al)	112.5	263	1.0415[25]	1.4616[40]	vs H_2O, EtOH, eth
3542	Diethyl vinylphosphonate		$C_6H_{13}O_3P$	682-30-4	164.139			110[2]	1.068[25]	1.4290[20]	
3543	Diethyl zinc	Zinc diethyl	$C_4H_{10}Zn$	557-20-0	123.531	col liq	-28	118; 80[200]	1.2065[20]	1.4936[20]	dec H_2O; msc eth, peth, bz
3544	Difenoconazole		$C_{19}H_{17}Cl_2N_3O_3$	119446-68-3	406.262		76	220[0.03]			
3545	Difenzoquat methyl sulfate	1*H*-Pyrazolium, 1,2-dimethyl-3,5-diphenyl-, methyl sulfate	$C_{18}H_{20}N_2O_4S$	43222-48-6	360.428		157				
3546	Diflubenzuron	*N*-[[(4-Chlorophenyl)amino] carbonyl]-2,6-difluorobenzamide	$C_{14}H_9ClF_2N_2O_2$	35367-38-5	310.683		239				
3547	Difluoroacetic acid		$C_2H_2F_2O_2$	381-73-7	96.033	liq	-1	133	1.526[25]	1.3470[20]	
3548	2,4-Difluoroaniline		$C_6H_5F_2N$	367-25-9	129.108	liq	-7.5	170	1.268[25]	1.5063[20]	
3549	*o*-Difluorobenzene	1,2-Difluorobenzene	$C_6H_4F_2$	367-11-3	114.093	liq	-47.1	94	1.1599[18]	1.4451[18]	i H_2O; s ace, bz, chl
3550	*m*-Difluorobenzene	1,3-Difluorobenzene	$C_6H_4F_2$	372-18-9	114.093	liq	-69.12	82.6	1.1572[20]	1.4374[20]	i H_2O; s ace, bz
3551	*p*-Difluorobenzene	1,4-Difluorobenzene	$C_6H_4F_2$	540-36-3	114.093	liq	-23.55	89	1.1701[20]	1.4422[20]	i H_2O; s ace, bz; sl ctc
3552	4,4'-Difluoro-1,1'-biphenyl	4,4'-Difluorodiphenyl	$C_{12}H_8F_2$	398-23-2	190.189	mcl pr (al) lf (w)	94.5	254.5			i H_2O; vs EtOH, bz, chl; s eth, ace
3553	1,1-Difluorocyclohexane		$C_6H_{10}F_2$	371-90-4	120.140	liq		99.5			
3554	3,3-Difluorocyclopropene		$C_3H_2F_2$	56830-75-2	76.045	liq		34			
3555	Difluorodimethylsilane		$C_2H_6F_2Si$	353-66-2	96.152	col gas	-87.5	2.5			
3556	1,5-Difluoro-2,4-dinitrobenzene		$C_6H_2F_2N_2O_4$	327-92-4	204.088		75.5	132[2]			sl EtOH
3557	Difluorodiphenylsilane		$C_{12}H_{10}F_2Si$	312-40-3	220.290			246; 157[50]	1.145[17]	1.5221[25]	
3558	1,1-Difluoroethane	Ethylidene difluoride	$C_2H_4F_2$	75-37-6	66.050	col gas	-117	-24.05	0.896[25] (p>1 atm)	1.3011[-72]	
3559	1,2-Difluoroethane	Ethylene difluoride	$C_2H_4F_2$	624-72-6	66.050	vol liq		26			vs bz, eth, chl
3560	1,1-Difluoroethene	Vinylidene fluoride	$C_2H_2F_2$	75-38-7	64.034	col gas	-144	-85.7			vs eth, EtOH
3561	*cis*-1,2-Difluoroethene	*cis*-1,2-Difluoroethylene	$C_2H_2F_2$	1630-77-9	64.034	col gas		-26			
3562	*trans*-1,2-Difluoroethene	*trans*-1,2-Difluoroethylene	$C_2H_2F_2$	1630-78-0	64.034	col gas		-53.1			
3563	Difluoromethane	Methylene fluoride	CH_2F_2	75-10-5	52.024	col gas	-136.8 tp	-51.6	1.2139[-52]		i H_2O; s EtOH



N,N-Diethyl-4-pyridinecarboxamide



3,3-Diethyl-2,4(1*H*,3*H*)-pyridinedione



Diethyl sebacate



Diethyl selenide



Diethylsilane


trans-Diethylstilbestrol



trans-Diethylstilbestrol dipropanoate



trans-Diethylstilbestrol monomethyl ether



Diethyl succinate



Diethyl sulfate


Diethyl sulfide



Diethyl sulfite



Diethyl sulfone



Diethyl sulfoxide



Diethyl *DL*-tartrate


Diethyl telluride



Diethyl terephthalate



Diethyl thiodipropionate



N,N'-Diethylthiourea



N,N-Diethyl-1,1,1-trimethylsilanamine


Diethyltrisulfide



N,N-Diethylurea



N,N'-Diethylurea



Diethyl vinylphosphonate



Diethyl zinc


Difenoconazole



Difenzoquat methyl sulfate



Diflubenzuron



Difluoroacetic acid


2,4-Difluoroaniline


o-Difluorobenzene


m-Difluorobenzene



p-Difluorobenzene



4,4'-Difluoro-1,1'-biphenyl


1,1-Difluorocyclohexane


3,3-Difluorocyclopropene


Difluorodimethylsilane


1,5-Difluoro-2,4-dinitrobenzene


Difluorodiphenylsilane


1,1-Difluoroethane


1,2-Difluoroethane



1,1-Difluoroethene


cis-1,2-Difluoroethene



trans-1,2-Difluoroethene


Difluoromethane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3564	2-(Difluoromethoxy)-1,1,1-trifluoroethane	Difluoromethyl 2,2,2-trifluoroethyl ether	$C_3H_3F_5O$	1885-48-9	150.047	col liq		29			
3565	Difluoromethylborane		CH_3BF_2	373-64-8	63.843	gas		-78.5[287]			reac H_2O
3566	2,4-Difluoro-1-nitrobenzene		$C_6H_3F_2NO_2$	446-35-5	159.091		9.8	207	1.4571[14]	1.5149[14]	sl chl
3567	2,2-Difluoropropane		$C_3H_6F_2$	420-45-1	80.077	col gas	-104.8	-0.4	0.9205[20] (p>1 atm)	1.2904[20]	
3568	1,3-Difluoro-2-propanol		$C_3H_6F_2O$	453-13-4	96.076			127; 55[34]	1.24[25]	1.3725[20]	
3569	Di-2-furanylethanedione		$C_{10}H_6O_4$	492-94-4	190.153	ye nd (al), cry (bz)	166.3				sl H_2O; s EtOH, eth, bz, chl
3570	Di-2-furanylethanedione dioxime	α-Furildioxime	$C_{10}H_8N_2O_4$	522-27-0	220.182		167				sl EtOH, eth, bz, lig
3571	1,5-Di-2-furanyl-1,4-pentadien-3-one		$C_{13}H_{10}O_3$	886-77-1	214.216	hyg pr (peth) ye pr (lig)	60.5	181[4]			vs eth, EtOH, chl
3572	Difurfuryl disulfide	Furfuryl disulfide	$C_{10}H_{10}O_2S_2$	4437-20-1	226.315		10	167[13], 112[0.5]			vs EtOH
3573	Difurfuryl ether	Furfuryl ether	$C_{10}H_{10}O_3$	4437-22-3	178.184			101[2]	1.1405[20]	1.5088[20]	i H_2O
3574	Digitonin		$C_{56}H_{92}O_{29}$	11024-24-1	1229.312		237.5				
3575	Digitoxigenin		$C_{23}H_{34}O_4$	143-62-4	374.514		253				s EtOH; vs MeOH
3576	Digitoxin		$C_{41}H_{64}O_{13}$	71-63-6	764.939	pr (dil al)	255.5				sl H_2O; vs EtOH; s eth, chl, MeOH, py
3577	Digitoxose		$C_6H_{12}O_4$	527-52-6	148.157	cry (MeOH+eth)	112				vs H_2O, ace; s py, AcOEt
3578	Diglycidyl ether	Bis(2,3-epoxypropyl) ether	$C_6H_{10}O_3$	2238-07-5	130.141			260	1.1195[20]		
3579	Diglycolic acid	2,2'-Oxydiacetic acid	$C_4H_6O_5$	110-99-6	134.088	mcl pr (w + 1)	148	dec			vs H_2O, eth, EtOH
3580	Digoxigenin		$C_{23}H_{34}O_5$	1672-46-4	390.513	pr (AcOEt)	222				vs EtOH, MeOH; sl chl
3581	Digoxin		$C_{41}H_{64}O_{14}$	20830-75-5	780.939	trc pl (dil al, py)	249 dec				vs EtOH
3582	Diheptylamine	*N*-Heptyl-1-heptanamine	$C_{14}H_{31}N$	2470-68-0	213.403	nd	31.5	271; 135[9]	0.7956[21]		sl H_2O; s EtOH; vs eth
3583	Diheptyl ether	Heptyl ether	$C_{14}H_{30}O$	629-64-1	214.387			258.5	0.8008[20]	1.4275[20]	vs eth, EtOH
3584	Diheptyl phthalate		$C_{22}H_{34}O_4$	3648-21-3	362.503			360			
3585	Diheptyl sulfide	Heptyl sulfide	$C_{14}H_{30}S$	629-65-2	230.453		70	298	0.8416[20]	1.4606[20]	i H_2O; s eth
3586	Dihexylamine	*N*-Hexyl-1-hexanamine	$C_{12}H_{27}N$	143-16-8	185.349	liq	-13.1	236; 75[1]	0.7889[20]	1.4339[20]	s EtOH, eth
3587	Dihexyl ether	Hexyl ether	$C_{12}H_{26}O$	112-58-3	186.333			226	0.7936[20]	1.4204[20]	i H_2O; s eth; sl ctc
3588	Dihexyl hexanedioate		$C_{18}H_{34}O_4$	110-33-8	314.461	liq	-9	348; 182.5[4]	0.941[20]		
3589	Dihexyl phthalate		$C_{20}H_{30}O_4$	84-75-3	334.450			210[5]			
3590	Dihexyl sulfide	Hexyl sulfide	$C_{12}H_{26}S$	6294-31-1	202.399			230; 136[20]	0.8411[20]	1.4586[20]	
3591	15,16-Dihydroaflatoxin G_1	Aflatoxin G_2	$C_{17}H_{14}O_7$	7241-98-7	330.289		239.3				
3592	9,10-Dihydroanthracene		$C_{14}H_{12}$	613-31-0	180.245	tab or pr	111	305	1.215[20]		i H_2O; s EtOH, eth, bz, chl
3593	6,15-Dihydro-5,9,14,18-anthrazinetetrone	Indanthrene	$C_{28}H_{14}N_2O_4$	81-77-6	442.422	bl nd	485 dec				i H_2O, EtOH, eth, ace, bz; s $PhNO_2$, dil alk
3594	1,2-Dihydrobenz[j]aceanthrylene	Cholanthrene	$C_{20}H_{14}$	479-23-2	254.325	pa ye lf (bz-al)	174				i H_2O; s EtOH, bz, HOAc, lig, tol
3595	9,10-Dihydro-9,10[1',2']-benzenoanthracene	Triptycene	$C_{20}H_{14}$	477-75-8	254.325	cry (cyhex)	256				
3596	1,3-Dihydro-2*H*-benzimidazole-2-thione	2-Benzimidazolethiol	$C_7H_6N_2S$	583-39-1	150.201	pl (dil al or NH_3)	298				vs EtOH
3597	1,3-Dihydro-2*H*-benzimidazol-2-one		$C_7H_6N_2O$	615-16-7	134.135	lf (w or al)	318 dec				sl H_2O, eth, bz; s ace; vs EtOH
3598	2,3-Dihydro-1,4-benzodioxin		$C_8H_8O_2$	493-09-4	136.149			212; 103[6]	1.180[20]	1.5485[20]	
3599	2,3-Dihydrobenzofuran	Coumaran	C_8H_8O	496-16-2	120.149	liq	-21.5	188.5	1.058[25]	1.5497[20]	vs eth, EtOH, chl
3600	3,4-Dihydro-1*H*-2-benzopyran	Isochroman	$C_9H_{10}O$	493-05-0	134.174		4	110[25], 90[12]	1.067[25]	1.5444[20]	
3601	3,4-Dihydro-2*H*-1-benzopyran		$C_9H_{10}O$	493-08-3	134.174		4.8	215; 98[18]	1.072[20]	1.5444[20]	s H_2O; msc os
3602	3,4-Dihydro-2*H*-1-benzopyran-2-one		$C_9H_8O_2$	119-84-6	148.159	lf	25	272	1.169[18]	1.5563[20]	i H_2O; sl EtOH, eth, ctc; s chl
3603	2,3-Dihydro-4*H*-1-benzopyran-4-one	4-Chromanone	$C_9H_8O_2$	491-37-2	148.159		36.5	160[50], 127[13]	1.1291[100]	1.5750	s EtOH; vs eth, ace, bz, chl; sl ctc
3604	6,7-Dihydrobenzo[b]thiophen-4(5*H*)-one	4,5,6,7-Tetrahydro-4-benzothiophenone	C_8H_8OS	13414-95-4	152.214						sl chl
3605	2,3-Dihydro-4*H*-1-benzothiopyran-4-one		C_9H_8OS	3528-17-4	164.224		29	154[12]	1.2487[14]	1.6395[20]	
3606	4,5-Dihydro-2-benzyl-1*H*-imidazole	Tolazoline	$C_{10}H_{12}N_2$	59-98-3	160.215	cry (peth)	67				
3607	7,8-Dihydrobiopterin		$C_9H_{13}N_5O_3$	6779-87-9	239.231	hyg nd (w)					s H_2O



2-(Difluoromethoxy)-1,1,1-trifluoroethane



Difluoromethylborane



2,4-Difluoro-1-nitrobenzene



2,2-Difluoropropane



1,3-Difluoro-2-propanol



Di-2-furanylethanedione



Di-2-furanylethanedione dioxime



1,5-Di-2-furanyl-1,4-pentadien-3-one



Difurfuryl disulfide



Difurfuryl ether



Digitonin



Digitoxigenin



Digitoxin



Digitoxose



Diglycidyl ether



Diglycolic acid



Digoxigenin



Digoxin



Diheptylamine



Diheptyl ether



Diheptyl phthalate



Diheptyl sulfide



Dihexylamine



Dihexyl ether



Dihexyl hexanedioate



Dihexyl phthalate



Dihexyl sulfide



15,16-Dihydroaflatoxin G_1



9,10-Dihydroanthracene


6,15-Dihydro-5,9,14,18-anthrazinetetrone


1,2-Dihydrobenz[j]aceanthrylene



9,10-Dihydro-9,10[1',2']-benzenoanthracene


1,3-Dihydro-2*H*-benzimidazole-2-thione



1,3-Dihydro-2*H*-benzimidazol-2-one


2,3-Dihydro-1,4-benzodioxin



2,3-Dihydrobenzofuran


3,4-Dihydro-1*H*-2-benzopyran



3,4-Dihydro-2*H*-1-benzopyran



3,4-Dihydro-2*H*-1-benzopyran-2-one


2,3-Dihydro-4*H*-1-benzopyran-4-one



6,7-Dihydrobenzo[b]thiophen-4(5*H*)-one



2,3-Dihydro-4*H*-1-benzothiopyran-4-one



4,5-Dihydro-2-benzyl-1*H*-imidazole



7,8-Dihydrobiopterin


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3608	Dihydrocodeine		$C_{18}H_{23}NO_3$	125-28-0	301.381	cry (aq, MeOH)	112.5	248^{15}			
3609	16,17-Dihydro-15*H*-cyclopenta[a] phenanthrene	1,2-Cyclopentenophenanthrene	$C_{17}H_{14}$	482-66-6	218.293	nd (al, petr)	135.5				i H_2O; s EtOH, peth
3610	10,11-Dihydro-5*H*-dibenz[b,f] azepine		$C_{14}H_{13}N$	494-19-9	195.260						s chl
3611	10,11-Dihydro-5*H*-dibenzo[a,d] cyclohepten-5-one		$C_{15}H_{12}O$	1210-35-1	208.255		30	203^{7}	1.1635^{20}	1.6324^{20}	
3612	2,5-Dihydro-2,5-dimethoxyfuran		$C_6H_{10}O_3$	332-77-4	130.141			161	1.073^{25}	1.4339^{20}	
3613	3,4-Dihydro-6,7-dimethoxy-1(2*H*) -isoquinolinone	Corydaldine	$C_{11}H_{13}NO_3$	493-49-2	207.226	mcl pr (w, al)	175				vs H_2O, bz, eth, EtOH
3614	1,2-Dihydro-1,5-dimethyl-2-phenyl-3*H*-pyrazol-3-one	Antipyrine	$C_{11}H_{12}N_2O$	60-80-0	188.225	lf or sc (eth, bz)	114	319			vs H_2O, EtOH
3615	2,3-Dihydro-1,4-dioxin		$C_4H_6O_2$	543-75-9	86.090			94.1	1.0836^{20}	1.4372^{20}	s ctc
3616	9,10-Dihydro-9,10-dioxo-2-anthracenecarboxylic acid		$C_{15}H_8O_4$	117-78-2	252.223	ye nd (HOAc)	291	sub			sl EtOH, HOAc; i eth, bz; s ace
3617	9,10-Dihydro-9,10-dioxo-1,5-anthracenedisulfonic acid		$C_{14}H_8O_8S_2$	117-14-6	368.339	ye nd (HCl +4w) pl (dil HOAc)	310 dec				vs H_2O, EtOH, HOAc
3618	9,10-Dihydro-9,10-dioxo-2,6-anthracenedisulfonic acid		$C_{14}H_8O_8S_2$	84-50-4	368.339						vs H_2O; s EtOH; i eth, bz
3619	9,10-Dihydro-9,10-dioxo-1-anthracenesulfonic acid		$C_{14}H_8O_5S$	82-49-5	288.276	lf (HOAc) ye lf (conc HCl, +3w)	216.0				vs H_2O, HOAc; s EtOH
3620	9,10-Dihydro-9,10-dioxo-2-anthracenesulfonic acid		$C_{14}H_8O_5S$	84-48-0	288.276	ye lf (+3w)					vs H_2O; s EtOH; i eth
3621	9,10-Dihydro-9,10-dioxo-1-anthracenesulfonic acid, sodium salt	Sodium anthraquinone-1-sulfonate	$C_{14}H_7NaO_5S$	128-56-3	310.258	ye lf (w)					sl H_2O
3622	9,10-Dihydro-9,10-dioxo-2-anthracenesulfonic acid, sodium salt		$C_{14}H_7NaO_5S$	131-08-8	310.258						sl DMSO
3623	7,8-Dihydrofolic acid		$C_{19}H_{21}N_7O_6$	4033-27-6	443.413	ye cry					
3624	2,3-Dihydrofuran		C_4H_6O	1191-99-7	70.090			54.5	0.927^{25}	1.4239^{20}	
3625	2,5-Dihydrofuran		C_4H_6O	1708-29-8	70.090					1.4311^{20}	
3626	2,3-Dihydro-3-hydroxy-1-methyl-1*H*-indole-5,6-dione	Adrenochrome	$C_9H_9NO_3$	54-06-8	179.172		125 dec				vs H_2O, EtOH; i eth, bz
3627	2,3-Dihydro-1*H*-inden-5-amine		$C_9H_{11}N$	24425-40-9	133.190	nd (peth)	37.5	$248; 131^{15}$			sl H_2O, chl; s eth, ace, bz
3628	2,3-Dihydro-1*H*-inden-1-ol		$C_9H_{10}O$	6351-10-6	134.174	pl (peth)	54.8	$220; 128^{12}$			vs bz, EtOH, chl
3629	2,3-Dihydro-1*H*-inden-5-ol		$C_9H_{10}O$	1470-94-6	134.174		58	253			sl H_2O, peth; vs EtOH, eth; s sulf
3630	2,3-Dihydro-1*H*-inden-1-one		C_9H_8O	83-33-0	132.159	ta, nd (w + 3)	42	$243; 129^{12}$	1.0943^{40}	1.561^{25}	sl H_2O; vs EtOH, eth, ace, chl
3631	1,3-Dihydro-2*H*-inden-2-one	2-Indanone	C_9H_8O	615-13-4	132.159	nd (al, eth)	59	dec 218	1.0712^{69}	1.538^{67}	i H_2O; vs EtOH, eth, ace, chl
3632	1a,6a-Dihydro-6*H*-indeno[1,2-b] oxirene		C_9H_8O	768-22-9	132.159		24.5	113^{20}, 98^{6}	1.1255^{24}		s chl
3633	2,3-Dihydro-1*H*-indole		C_8H_9N	496-15-1	119.164			229	1.069^{20}	1.5923^{20}	sl H_2O; s eth, ace, bz
3634	1,3-Dihydro-2*H*-indol-2-one		C_8H_7NO	59-48-3	133.148	nd (w)	128	227^{23}, 195^{17}			s H_2O, EtOH, eth
3635	2,3-Dihydro-1*H*-isoindol-1-one		C_8H_7NO	480-91-1	133.148	nd (w)	151	$338; 103^{18}$			vs eth, EtOH, chl
3636	Dihydro-α-lipoic acid	6,8-Dimercaptooctanoic acid	$C_8H_{16}O_2S_2$	462-20-4	208.342	ye liq		$145^{0.2}$			
3637	3,4-Dihydro-6-methoxy-1(2*H*)-naphthalenone	6-Methoxy-α-tetralone	$C_{11}H_{12}O_2$	1078-19-9	176.212	cry (MeOH, lig)	78	171^{11}			
3638	3,4-Dihydro-2-methoxy-2*H*-pyran		$C_6H_{10}O_2$	4454-05-1	114.142	liq		128	1.006	1.4420^{20}	
3639	1,2-Dihydro-3-methylbenz[j] aceanthrylene	3-Methylcholanthrene	$C_{21}H_{16}$	56-49-5	268.352	ye nd (bz)	180	280^{80}	1.28^{20}		i H_2O
3640	2,3-Dihydro-2-methylbenzofuran		$C_9H_{10}O$	1746-11-8	134.174			197.5	1.061^{25}	1.5308	
3641	Dihydro-3-methylene-2,5-furandione		$C_5H_4O_3$	2170-03-8	112.084	orth bipym pr (eth, chl)	69	139^{30}, 114^{18}			sl eth; vs chl
3642	Dihydro-3-methylene-2(3*H*)-furanone	α-Methylene butyrolactone	$C_5H_6O_2$	547-65-9	98.101			85^{10}	1.1206^{20}	1.4650^{20}	s H_2O, eth, ace, bz; sl ctc; vs EtOH
3643	Dihydro-3-methyl-2,5-furandione		$C_5H_6O_3$	4100-80-5	114.100		34	239	1.22^{25}		
3644	Dihydro-3-methyl-2(3*H*)-furanone	2-Methyl-γ-butyrolactone	$C_5H_8O_2$	1679-47-6	100.117	liq		$200; 79^{10}$	1.0570^{20}	1.4325^{20}	
3645	Dihydro-4-methyl-2(3*H*)-furanone	3-Methyl-γ-butyrolactone	$C_5H_8O_2$	1679-49-8	100.117	liq		76^{11}	1.058^{20}	1.4339^{20}	
3646	Dihydro-5-methyl-2(3*H*)-furanone, (±)	(±)-γ-Valerolactone	$C_5H_8O_2$	57129-69-8	100.117	liq	-31	206	1.0551^{20}	1.4328^{20}	msc H_2O; s EtOH, ace; sl ctc
3647	4,5-Dihydro-2-methyl-1*H*-imidazole	Lysidine	$C_4H_8N_2$	534-26-9	84.120	hyg	107	196.5			vs H_2O, EtOH; i eth; s chl



Dihydrocodeine



16,17-Dihydro-15*H*-cyclopenta[a]phenanthrene


10,11-Dihydro-5*H*-dibenz[b,f]azepine



10,11-Dihydro-5*H*-dibenzo[a,d]cycloheptene-5-one



2,5-Dihydro-2,5-dimethoxyfuran



3,4-Dihydro-6,7-dimethoxy-1(2*H*)-isoquinolinone



1,2-Dihydro-1,5-dimethyl-2-phenyl-3*H*-pyrazol-3-one



2,3-Dihydro-1,4-dioxin



9,10-Dihydro-9,10-dioxo-2-anthracenecarboxylic acid



9,10-Dihydro-9,10-dioxo-1,5-anthracenedisulfonic acid



9,10-Dihydro-9,10-dioxo-2,6-anthracenedisulfonic acid


9,10-Dihydro-9,10-dioxo-1-anthracenesulfonic acid


9,10-Dihydro-9,10-dioxo-2-anthracenesulfonic acid



9,10-Dihydro-9,10-dioxo-1-anthracenesulfonic acid, sodium salt



9,10-Dihydro-9,10-dioxo-2-anthracenesulfonic acid, sodium salt



7,8-Dihydrofolic acid



2,3-Dihydrofuran


2,5-Dihydrofuran



2,3-Dihydro-3-hydroxy-1-methyl-1*H*-indole-5,6-dione



2,3-Dihydro-1*H*-inden-5-amine


2,3-Dihydro-1*H*-inden-1-ol



2,3-Dihydro-1*H*-inden-5-ol



2,3-Dihydro-1*H*-inden-1-one



1,3-Dihydro-2*H*-inden-2-one



1a,6a-Dihydro-6*H*-indeno[1,2-b]oxirene



2,3-Dihydro-1*H*-indole



1,3-Dihydro-2*H*-indol-2-one



2,3-Dihydro-1*H*-isoindol-1-one



Dihydro-α-lipoic acid


3,4-Dihydro-6-methoxy-1(2*H*)-naphthalenone



3,4-Dihydro-2-methoxy-2*H*-pyran


1,2-Dihydro-3-methylbenz[j]aceanthrylene


2,3-Dihydro-2-methylbenzofuran



Dihydro-3-methylene-2,5-furandione


Dihydro-3-methylene-2(3*H*)-furanone


Dihydro-3-methyl-2,5-furandione



Dihydro-3-methyl-2(3*H*)-furanone


Dihydro-4-methyl-2(3*H*)-furanone



Dihydro-5-methyl-2(3*H*)-furanone, (±)



4,5-Dihydro-2-methyl-1*H*-imidazole


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3648	1,3-Dihydro-1-methyl-2*H*-imidazole-2-thione	Methimazole	$C_4H_6N_2S$	60-56-0	114.169	lf (al)	146	dec 280			vs H_2O; s EtOH, chl; sl eth, bz, lig
3649	2,3-Dihydro-1-methyl-1*H*-indene		$C_{10}H_{12}$	767-58-8	132.202			190.6	0.938^{25}	1.5266^{20}	i H_2O
3650	3,4-Dihydro-2-methyl-1(2*H*)-naphthalenone		$C_{11}H_{12}O$	1590-08-5	160.212		15	136^{16}	1.057^{25}	1.5535^{20}	
3651	4-(4,5-Dihydro-3-methyl-5-oxo-1*H*-pyrazol-1-yl)benzenesulfonic acid		$C_{10}H_{10}N_2O_4S$	89-36-1	254.262	nd (w+1)	≈300 dec				
3652	1,2-Dihydro-5-methyl-2-phenyl-3*H*-pyrazol-3-one	5-Hydroxy-3-methyl-1-phenylpyrazole	$C_{10}H_{10}N_2O$	19735-89-8	174.198		128	287^{105}, 191^{17}	1.2600^{20}	1.637	s H_2O, EtOH; sl bz; i peth
3653	2,4-Dihydro-5-methyl-2-phenyl-3*H*-pyrazol-3-one		$C_{10}H_{10}N_2O$	89-25-8	174.198	mcl pr (w)	127	287^{105}, 191^{17}		1.637	
3654	3,6-Dihydro-4-methyl-2*H*-pyran		$C_6H_{10}O$	16302-35-5	98.142			117.5	0.912^{25}	1.4495^{20}	
3655	4,5-Dihydro-2-methylthiazole		C_4H_7NS	2346-00-1	101.171	liq	-101	145	1.067^{25}	1.5200^{20}	
3656	1,2-Dihydronaphthalene		$C_{10}H_{10}$	447-53-0	130.186	liq	-8	206.5	0.9974^{20}	1.5814^{20}	
3657	1,4-Dihydronaphthalene	Δ 2-Dialin	$C_{10}H_{10}$	612-17-9	130.186	pl	25	211.5	0.9928^{33}	1.5577^{20}	
3658	3,4-Dihydro-2(1*H*)-naphthalenone		$C_{10}H_{10}O$	530-93-8	146.185		18	237	1.1055^{27}	1.5598^{20}	i H_2O; s eth, bz
3659	1,2-Dihydro-5-nitroacenaphthylene		$C_{12}H_9NO_2$	602-87-9	199.205		103				s H_2O, EtOH, eth, lig
3660	1,6-Dihydro-6-oxo-3-pyridinecarboxylic acid		$C_6H_5NO_3$	5006-66-6	139.109	nd(w)	310 dec	sub			sl H_2O, tfa; i EtOH, eth, bz, chl
3661	Dihydro-5-pentyl-2(3*H*)-furanone	4-Hydroxynonanoic acid lactone	$C_9H_{16}O_2$	104-61-0	156.222	oil		134^{12}			
3662	9,10-Dihydrophenanthrene		$C_{14}H_{12}$	776-35-2	180.245	nd (MeOH)	34.5	168^{15}	1.0757^{40}	1.6415^{20}	s chl
3663	2,3-Dihydro-2-phenyl-4*H*-1-benzopyran-4-one		$C_{15}H_{12}O_2$	487-26-3	224.255	nd (lig)	76				i H_2O; s ace, bz; sl ctc
3664	4,5-Dihydro-2-(phenylmethyl)-1*H*-imidazole, monohydrochloride		$C_{10}H_{13}ClN_2$	59-97-2	196.676		174				
3665	4,5-Dihydro-5-phenyl-2-oxazolamine	Aminorex	$C_9H_{10}N_2O$	2207-50-3	162.187	cry (bz)	137				
3666	1,4-Dihydro-1-phenyl-5*H*-tetrazole-5-thione	1-Phenyl-5-mercapto-1*H*-tetrazole	$C_7H_6N_4S$	86-93-1	178.215		145				
3667	Dihydro-5-propyl-2(3*H*)-furanone	γ-Propyl-γ-butyrolactone	$C_7H_{12}O_2$	105-21-5	128.169			84^{5}		1.4385^{25}	
3668	2,3-Dihydro-6-propyl-2-thioxo-4(1*H*)-pyrimidinone	Propylthiouracil	$C_7H_{10}N_2OS$	51-52-5	170.231	w pow (w)	219				sl H_2O, chl, DMSO, EtOH; i eth, bz
3669	1,7-Dihydro-6*H*-purine-6-thione	6-Mercaptopurine	$C_5H_4N_4S$	50-44-2	152.178	ye pr (w, + l w)	313 dec				i H_2O; s alk
3670	3,4-Dihydro-2*H*-pyran		C_5H_8O	110-87-2	84.117			86	0.921^{19}	1.4402^{19}	s H_2O, EtOH; sl chl
3671	3,6-Dihydro-2*H*-pyran		C_5H_8O	3174-74-1	84.117	liq		95	0.94^{19}		
3672	Dihydro-2*H*-pyran-2,6(3*H*)-dione		$C_5H_6O_3$	108-55-4	114.100		56.3	158^{15}		1.4110^{20}	
3673	4,5-Dihydro-1*H*-pyrazole	2-Pyrazoline	$C_3H_6N_2$	109-98-8	70.093			144	1.0200^{17}	1.4796^{17}	vs H_2O, eth, EtOH
3674	1,2-Dihydro-3,6-pyridazinedione	Maleic hydrazide	$C_4H_4N_2O_2$	123-33-1	112.087	cry (w)	307				sl H_2O, EtOH, tfa
3675	Dihydro-2,4(1*H*,3*H*)-pyrimidinedione	5,6-Dihydrouracil	$C_4H_6N_2O_2$	504-07-4	114.103	nd (w)	275.5				vs H_2O; s EtOH, chl, MeOH
3676	2,5-Dihydro-1*H*-pyrrole	3-Pyrroline	C_4H_7N	109-96-6	69.106			90.5	0.9097^{20}	1.4664^{20}	vs H_2O, ace, eth, EtOH
3677	3,4-Dihydro-2(1*H*)-quinolinone	Hydrocarbostyril	C_9H_9NO	553-03-7	147.173	pr (al, eth)	163.5	201^{45}			vs eth, EtOH
3678	1,4-Dihydro-2,3-quinoxalinedione	2,3-Quinoxalinediol	$C_8H_6N_2O_2$	15804-19-0	162.146	nd (w)	410				vs H_2O; sl EtOH, eth; s bz, DMSO, HOAc
3679	Dihydrotachysterol		$C_{28}H_{46}O$	67-96-9	398.664	cry (MeOH)	131				i H_2O; s os
3680	Dihydrothebaine		$C_{19}H_{23}NO_3$	561-25-1	313.391		162.5				i H_2O; s EtOH, bz, AcOEt
3681	4,5-Dihydro-2-thiazolamine		$C_3H_6N_2S$	1779-81-3	102.158	nd or lf (bz)	85.3	dec			vs H_2O, EtOH, bz, chl
3682	2,3-Dihydrothiophene		C_4H_6S	1120-59-8	86.156			112.1			
3683	2,5-Dihydrothiophene		C_4H_6S	1708-32-3	86.156			122.4			
3684	2,5-Dihydrothiophene 1,1-dioxide	3-Sulfolene	$C_4H_6O_2S$	77-79-2	118.155		64.5				s chl
3685	Dihydro-2(3*H*)-thiophenone		C_4H_6OS	1003-10-7	102.155			111^{52}, 39^{1}	1.18^{25}	1.5230^{20}	
3686	Dihydro-2-thioxo-4,6(1*H*,5*H*)-pyrimidinedione	2-Thiobarbituric acid	$C_4H_4N_2O_2S$	504-17-6	144.152	pl (w)	235 dec				sl H_2O; s EtOH, dil alk, dil HCl
3687	2,3-Dihydro-2-thioxo-4(1*H*)-pyrimidinone	2-Thiouracil	$C_4H_4N_2OS$	141-90-2	128.152	pr (w, al)	>340 dec				sl H_2O, EtOH, DMSO; s anh HF
3688	1,2-Dihydro-3*H*-1,2,4-triazole-3-thione		$C_2H_3N_3S$	3179-31-5	101.130		222.5				s DMSO
3689	(1,3-Dihydro-1,3,3-trimethyl-2*H*-indol-2-ylidene)acetaldehyde		$C_{13}H_{15}NO$	84-83-3	201.264						s chl



1,3-Dihydro-1-methyl-2*H*-imidazole-2-thione


2,3-Dihydro-1-methyl-1*H*-indene


3,4-Dihydro-2-methyl-1(2*H*)-naphthalenone



4-(4,5-Dihydro-3-methyl-5-oxo-1*H*-pyrazol-1-yl)benzenesulfonic acid



1,2-Dihydro-5-methyl-2-phenyl-3*H*-pyrazol-3-one



2,4-Dihydro-5-methyl-2-phenyl-3*H*-pyrazol-3-one



3,6-Dihydro-4-methyl-2*H*-pyran



4,5-Dihydro-2-methylthiazole



1,2-Dihydronaphthalene



1,4-Dihydronaphthalene



3,4-Dihydro-2(1*H*)-naphthalenone



1,2-Dihydro-5-nitroacenaphthylene



1,6-Dihydro-6-oxo-3-pyridinecarboxylic acid



Dihydro-5-pentyl-2(3*H*)-furanone



9,10-Dihydrophenanthrene



2,3-Dihydro-2-phenyl-4*H*-1-benzopyran-4-one



4,5-Dihydro-2-(phenylmethyl)-1*H*-imidazole, monohydrochloride


4,5-Dihydro-5-phenyl-2-oxazolamine


1,4-Dihydro-1-phenyl-5*H*-tetrazole-5-thione



Dihydro-5-propyl-2(3*H*)-furanone


2,3-Dihydro-6-propyl-2-thioxo-4(1*H*)-pyrimidinone



1,7-Dihydro-6*H*-purine-6-thione



3,4-Dihydro-2*H*-pyran


3,6-Dihydro-2*H*-pyran



Dihydro-2*H*-pyran-2,6(3*H*)-dione



4,5-Dihydro-1*H*-pyrazole



1,2-Dihydro-3,6-pyridazinedione



Dihydro-2,4(1*H*,3*H*)-pyrimidinedione



2,5-Dihydro-1*H*-pyrrole


3,4-Dihydro-2(1*H*)-quinolinone


1,4-Dihydro-2,3-quinoxalinedione


Dihydrotachysterol


Dihydrothebaine



4,5-Dihydro-2-thiazolamine



2,3-Dihydrothiophene


2,5-Dihydrothiophene



2,5-Dihydrothiophene 1,1-dioxide


Dihydro-2(3*H*)-thiophenone



Dihydro-2-thioxo-4,6(1*H*,5*H*)-pyrimidinedione



2,3-Dihydro-2-thioxo-4(1*H*)-pyrimidinone



1,2-Dihydro-3*H*-1,2,4-triazole-3-thione



(1,3-Dihydro-1,3,3-trimethyl-2*H*-indol-2-ylidene)acetaldehyde


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3690	2,3-Dihydro-1,1,3-trimethyl-3-phenyl-1*H*-indene		$C_{18}H_{20}$	3910-35-8	236.352	tcl pr (al)	52.5	308.5	1.0009^{20}	1.5681^{20}	i H_2O; s EtOH, bz, MeOH
3691	1,2-Dihydro-2,2,4-trimethylquinoline		$C_{12}H_{15}N$	147-47-7	173.254		26.5	260; 132^{13}			
3692	1,4-Dihydroxy-9,10-anthracenedione	Quinizarin	$C_{14}H_8O_4$	81-64-1	240.212	ye red lf (eth) dk red nd	200				s H_2O, EtOH, eth, bz, KOH, sulf
3693	1,5-Dihydroxy-9,10-anthracenedione	Anthrarufin	$C_{14}H_8O_4$	117-12-4	240.212	pa ye pl (gl HOAc)	280	sub			i H_2O; sl EtOH, eth, ace, CS_2; s bz
3694	1,8-Dihydroxy-9,10-anthracenedione	Danthron	$C_{14}H_8O_4$	117-10-2	240.212	red or red-ye nd or lf (al)	193	sub			i H_2O; sl EtOH, eth; s ace, HOAc, alk
3695	2,6-Dihydroxy-9,10-anthracenedione		$C_{14}H_8O_4$	84-60-6	240.212	ye nd (al)	360 dec				sl H_2O, EtOH; i eth, bz, chl; s alk
3696	2,7-Dihydroxy-9,10-anthracenedione		$C_{14}H_8O_4$	572-93-0	240.212	ye nd (+1w, dil al) nd (sub)	353.8	sub			i H_2O; s EtOH; sl eth, bz, chl
3697	2,2'-Dihydroxyazobenzene		$C_{12}H_{10}N_2O_2$	2050-14-8	214.219	gold-ye lf (bz), nd (al)	173	140$^{0.001}$			i H_2O; sl EtOH, bz; vs eth; s con alk
3698	2,3-Dihydroxybenzaldehyde		$C_7H_6O_3$	24677-78-9	138.121	ye nd	108	235; 120^{16}			vs ace, EtOH, HOAc
3699	2,4-Dihydroxybenzaldehyde	β-Resorcylaldehyde	$C_7H_6O_3$	95-01-2	138.121	nd (eth-lig)	135	226^{22}			s H_2O, HOAc; vs EtOH, eth, chl; sl bz
3700	2,5-Dihydroxybenzaldehyde		$C_7H_6O_3$	1194-98-5	138.121	ye nd (bz)	100.0				vs H_2O, EtOH, chl
3701	3,4-Dihydroxybenzaldehyde	Protocatechualdehyde	$C_7H_6O_3$	139-85-5	138.121	lf (w, to)	153 dec				s H_2O; vs EtOH, eth
3702	*N*,2-Dihydroxybenzamide	Salicylhydroxamic acid	$C_7H_7NO_3$	89-73-6	153.136	nd (HOAc)	168	sub			sl H_2O, DMSO; vs EtOH, eth; s HOAc
3703	2,5-Dihydroxybenzeneacetic acid	Homogentisic acid	$C_8H_8O_4$	451-13-8	168.148	pr (w+1), lf (al-chl)	153				vs H_2O, EtOH, eth; i bz, chl
3704	2,3-Dihydroxybenzoic acid		$C_7H_6O_4$	303-38-8	154.121	pr or nd (w+1)	205.5		1.542^{20}		s H_2O, EtOH, eth; sl ace
3705	2,4-Dihydroxybenzoic acid	β-Resorcylic acid	$C_7H_6O_4$	89-86-1	154.121	cry (+w)	226 dec				s H_2O, EtOH, eth, bz; i CS_2
3706	2,5-Dihydroxybenzoic acid	Gentisic acid	$C_7H_6O_4$	490-79-9	154.121	nd or pr (w)	199.5				vs H_2O, EtOH, eth; s ace; i bz, chl, CS_2
3707	2,6-Dihydroxybenzoic acid		$C_7H_6O_4$	303-07-1	154.121	nd (+w)	167 dec				s H_2O, EtOH, eth; i chl; sl tfa
3708	3,4-Dihydroxybenzoic acid	Protocatechuic acid	$C_7H_6O_4$	99-50-3	154.121	mcl nd (w+1)	201 dec		1.524^{4}		sl H_2O; vs EtOH; s eth; i bz
3709	3,5-Dihydroxybenzoic acid		$C_7H_6O_4$	99-10-5	154.121	pr or nd	239				sl H_2O, ace; vs EtOH, eth
3710	2,2'-Dihydroxybenzophenone	Bis(2-hydroxyphenyl) ketone	$C_{13}H_{10}O_3$	835-11-0	214.216		59.5	333			i H_2O; s EtOH, eth, chl
3711	4,4'-Dihydroxybenzophenone	Bis(4-hydroxyphenyl) ketone	$C_{13}H_{10}O_3$	611-99-4	214.216	nd (lig), cry (w)	210		1.133^{131}		sl H_2O; s EtOH, eth, ace; i bz, CS_2
3712	6,7-Dihydroxy-2*H*-1-benzopyran-2-one	Esculetin	$C_9H_6O_4$	305-01-1	178.142	nd (w), pr (HOAc) lf (sub)	276	sub			sl H_2O, eth; s EtOH, ace, chl, AcOEt
3713	7,8-Dihydroxy-2*H*-1-benzopyran-2-one	Daphnetin	$C_9H_6O_4$	486-35-1	178.142	ye nd (dil al)	262	sub			s H_2O, EtOH; sl eth, bz, chl, CS_2
3714	2,4-Dihydroxybutanoic acid		$C_4H_8O_4$	1518-62-3	120.105	liq		96^{3}			
3715	3,6-Dihydroxycholan-24-oic acid, (3α,5β,6α)	Hyodeoxycholic acid	$C_{24}H_{40}O_4$	83-49-8	392.573	cry (AcOEt)	198.5				sl H_2O, eth, ace, bz; s EtOH, HOAc
3716	3,7-Dihydroxycholan-24-oic acid, (3α,5β,7β)	Ursodiol	$C_{24}H_{40}O_4$	128-13-2	392.573	pl (al)	203				vs EtOH; sl eth
3717	3,7-Dihydroxycholan-24-oic acid, (3α,5β,7α)	Chenodiol	$C_{24}H_{40}O_4$	474-25-9	392.573	nd (EtOAc+hep)	119				i H_2O, bz; vs EtOH, ace; s eth, HOAc
3718	1,25-Dihydroxycholecalciferol	Calcitriol	$C_{27}H_{44}O_3$	32222-06-3	416.636	wh cry pow	115				sl EtOH, MeOH, thf, AcOEt
3719	2,5-Dihydroxy-2,5-cyclohexadiene-1,4-dione		$C_6H_4O_4$	615-94-1	140.094	dk ye nd	211				sl H_2O, ace, DMSO; s EtOH, HOAc; i eth



2,3-Dihydro-1,1,3-trimethyl-3-phenyl-1*H*-indene



1,2-Dihydro-2,2,4-trimethylquinoline



1,4-Dihydroxy-9,10-anthracenedione



1,5-Dihydroxy-9,10-anthracenedione



1,8-Dihydroxy-9,10-anthracenedione



2,6-Dihydroxy-9,10-anthracenedione



2,7-Dihydroxy-9,10-anthracenedione



2,2'-Dihydroxyazobenzene



2,3-Dihydroxybenzaldehyde



2,4-Dihydroxybenzaldehyde



2,5-Dihydroxybenzaldehyde



3,4-Dihydroxybenzaldehyde



N,2-Dihydroxybenzamide



2,5-Dihydroxybenzeneacetic acid



2,3-Dihydroxybenzoic acid



2,4-Dihydroxybenzoic acid



2,5-Dihydroxybenzoic acid



2,6-Dihydroxybenzoic acid



3,4-Dihydroxybenzoic acid



3,5-Dihydroxybenzoic acid



2,2'-Dihydroxybenzophenone



4,4'-Dihydroxybenzophenone



6,7-Dihydroxy-2*H*-1-benzopyran-2-one



7,8-Dihydroxy-2*H*-1-benzopyran-2-one



2,4-Dihydroxybutanoic acid


3,6-Dihydroxycholan-24-oic acid, (3α,5β,6α)



3,7-Dihydroxycholan-24-oic acid, (3α,5β,7β)



3,7-Dihydroxycholan-24-oic acid, (3α,5β,7α)



1,25-Dihydroxycholecalciferol



2,5-Dihydroxy-2,5-cyclohexadiene-1,4-dione


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3720	2,3-Dihydroxy-2-cyclopenten-1-one	Reductic acid	$C_5H_6O_3$	80-72-8	114.100		212				s H_2O, EtOH; sl eth, ace, AcOEt; i bz
3721	2,6-Dihydroxy-2,6-dimethyl-4-heptanone	Di(2-hydroxy-2-methylpropyl) ketone	$C_9H_{18}O_3$	3682-91-5	174.237	pale ye cry					
3722	2,2'-Dihydroxydiphenylmethane	2,2'-Methylenebisphenol	$C_{13}H_{12}O_2$	2467-02-9	200.233		118.3	363	1.280^{25}		
3723	4,4'-Dihydroxydiphenyl sulfide	4,4'-Thiobisphenol	$C_{12}H_{10}O_2S$	2664-63-3	218.271	mcl pr or lf (al)	151				sl H_2O, EtOH, eth, CS_2
3724	1,8-Dihydroxy-3-(hydroxymethyl)-9,10-anthracenedione	Aloe-emodol	$C_{15}H_{10}O_5$	481-72-1	270.237	oran ye nd (to, al)	223.5	sub			vs bz, eth, EtOH
3725	2,3-Dihydroxymaleic acid	Dihydroxymaleic acid	$C_4H_4O_6$	526-84-1	148.071	pl (w+2)	155 dec				sl H_2O, eth, MeOH; s EtOH
3726	α,4-Dihydroxy-3-methoxybenzeneacetic acid	Vanilmandelic acid	$C_9H_{10}O_5$	55-10-7	198.172	sc (bz-eth)	132 dec				vs H_2O, ace, eth
3727	7,8-Dihydroxy-6-methoxy-2*H*-1-benzopyran-2-one	Fraxetin	$C_{10}H_8O_5$	574-84-5	208.168	pl (dil al)	231				vs EtOH
3728	5,7-Dihydroxy-3-(4-methoxyphenyl)-4*H*-1-benzopyran-4-one		$C_{16}H_{12}O_5$	491-80-5	284.263		214.8				
3729	(2,6-Dihydroxy-4-methoxyphenyl) phenylmethanone	Cotoin	$C_{14}H_{12}O_4$	479-21-0	244.243	ye pr (chl) lf or nd (w)	130.5				vs ace, bz, eth, EtOH
3730	1,7-Dihydroxy-3-methoxy-9*H*-xanthen-9-one	Gentisin	$C_{14}H_{10}O_5$	437-50-3	258.226	ye orth	266.5				i H_2O; vs EtOH; i ace; s py
3731	1,8-Dihydroxy-3-methyl-9,10-anthracenedione	Chrysophanic acid	$C_{15}H_{10}O_4$	481-74-3	254.238	ye hex or mcl nd (sub)	196	sub	0.92^{25}		vs bz, HOAc
3732	2,4-Dihydroxy-6-methylbenzoic acid	*o*-Orsellinic acid	$C_8H_8O_4$	480-64-8	168.148	nd (dil HOAc, +1w)	176 dec				s EtOH, eth
3733	5,7-Dihydroxy-4-methyl-2*H*-1-benzopyran-2-one		$C_{10}H_8O_4$	2107-76-8	192.169	nd (al), lf (HOAc)	283				sl H_2O, eth, bz, chl; vs EtOH, alk
3734	6,7-Dihydroxy-4-methyl-2*H*-1-benzopyran-2-one		$C_{10}H_8O_4$	529-84-0	192.169	ye nd (dil al)	275				s H_2O, EtOH, HOAc
3735	5,8-Dihydroxy-1,4-naphthalenedione		$C_{10}H_6O_4$	475-38-7	190.153	dk red mcl pr (bz) red-br nd (al)	232	sub			sl H_2O, EtOH, eth; s HOAc
3736	4,5-Dihydroxy-2,7-naphthalenedisulfonic acid	Chromotropic acid	$C_{10}H_8O_8S_2$	148-25-4	320.296	nd or lf (w+2)					s H_2O, alk; i EtOH, eth
3737	5,6-Dihydroxynaphtho[2,3-f] quinoline-7,12-dione	Alizarin Blue	$C_{17}H_9NO_4$	568-02-5	291.258	br-viol nd (bz)	269				vs bz, gl HOAc
3738	1,2-Dihydroxy-3-nitro-9,10-anthracenedione	Alizarin Orange	$C_{14}H_7NO_6$	568-93-4	285.209	oran nd or pl (HOAc)	244 dec	sub			sl H_2O; s EtOH, bz, chl, sulf, HOAc
3739	9,10-Dihydroxyoctadecanedioic acid, (*R**,*R**)-(±)	Phloionic acid	$C_{18}H_{34}O_6$	23843-52-9	346.459	cry (al)	126				
3740	9,10-Dihydroxyoctadecanoic acid	9,10-Dihydroxystearic acid	$C_{18}H_{36}O_4$	120-87-6	316.477		90				i H_2O; sl EtOH, eth
3741	5,7-Dihydroxy-2-phenyl-4*H*-1-benzopyran-4-one	Chrysin	$C_{15}H_{10}O_4$	480-40-0	254.238	lt ye pr (MeOH)	285.5				i H_2O; s EtOH, ace; sl eth, bz, CS_2
3742	1-(2,4-Dihydroxyphenyl)ethanone	Resacetophenone	$C_8H_8O_3$	89-84-9	152.148	nd or lf	146		1.18^{141}		i H_2O, chl; s EtOH, py; sl eth, bz
3743	(2,4-Dihydroxyphenyl) phenylmethanone	Benzoresorcinol	$C_{13}H_{10}O_3$	131-56-6	214.216	nd (w)	144				i H_2O; s EtOH; vs eth; sl bz, chl
3744	3-(3,4-Dihydroxyphenyl)-2-propenoic acid	Caffeic acid	$C_9H_8O_4$	331-39-5	180.158	ye pr, pl (w)	225 dec				vs EtOH
3745	Dihydroxyphenylstibine oxide	Benzenestibonic acid	$C_6H_7O_3Sb$	535-46-6	248.878	nd (HOAc)	139				
3746	17,21-Dihydroxypregna-1,4-diene-3,11,20-trione	Prednisone	$C_{21}H_{26}O_5$	53-03-2	358.428		234 dec				
3747	17,21-Dihydroxypregn-4-ene-3,20-dione	11-Deoxy-17-hydrocorticosterone	$C_{21}H_{30}O_4$	152-58-9	346.461		215				vs ace, EtOH, chl
3748	17,21-Dihydroxypregn-4-ene-3,11,20-trione	Cortisone	$C_{21}H_{28}O_5$	53-06-5	360.444		222				sl H_2O, eth, bz, chl; s EtOH, ace
3749	2,3-Dihydroxypropanal, (±)		$C_3H_6O_3$	56-82-6	90.078	nd or pr (40% MeOH)	145	145$^{0.8}$	1.453^{18}		s H_2O; sl EtOH, eth; i bz, peth, lig
3750	2,3-Dihydroxypropanoic acid, (*R*)	Glyceric acid	$C_3H_6O_4$	6000-40-4	106.078	thick gum		dec			
3751	1,3-Dihydroxy-2-propanone	Dihydroxyacetone	$C_3H_6O_3$	96-26-4	90.078		90				s H_2O, EtOH, eth, ace; i lig
3752	2,3-Dihydroxypropyl decanoate	Decanoic acid glycerol monoester	$C_{13}H_{26}O_4$	2277-23-8	246.343	pr (peth)	53				
3753	2,3-Dihydroxypropyl octanoate	Octanoic acid glycerol monoester	$C_{11}H_{22}O_4$	26402-26-6	218.291	cry (peth)	40				



2,3-Dihydroxy-2-cyclopenten-1-one



2,6-Dihydroxy-2,6-dimethyl-4-heptanone



2,2'-Dihydroxydiphenylmethane



4,4'-Dihydroxydiphenyl sulfide



1,8-Dihydroxy-3-(hydroxymethyl)-9,10-anthracenedione



2,3-Dihydroxymaleic acid



α,4-Dihydroxy-3-methoxybenzeneacetic acid



7,8-Dihydroxy-6-methoxy-2*H*-1-benzopyran-2-one



5,7-Dihydroxy-3-(4-methoxyphenyl)-4*H*-1-benzopyran-4-one



(2,6-Dihydroxy-4-methoxyphenyl)phenylmethanone



1,7-Dihydroxy-3-methoxy-9*H*-xanthen-9-one



1,8-Dihydroxy-3-methyl-9,10-anthracenedione



2,4-Dihydroxy-6-methylbenzoic acid



5,7-Dihydroxy-4-methyl-2*H*-1-benzopyran-2-one



6,7-Dihydroxy-4-methyl-2*H*-1-benzopyran-2-one



5,8-Dihydroxy-1,4-naphthalenedione



4,5-Dihydroxy-2,7-naphthalenedisulfonic acid



5,6-Dihydroxynaphtho[2,3-f]quinoline-7,12-dione



1,2-Dihydroxy-3-nitro-9,10-anthracenedione



9,10-Dihydroxyoctadecanedioic acid, (*R**,*R**)-(±)



9,10-Dihydroxyoctadecanoic acid



5,7-Dihydroxy-2-phenyl-4*H*-1-benzopyran-4-one



1-(2,4-Dihydroxyphenyl)ethanone



(2,4-Dihydroxyphenyl)phenylmethanone



3-(3,4-Dihydroxyphenyl)-2-propenoic acid



Dihydroxyphenylstibine oxide



17,21-Dihydroxypregna-1,4-diene-3,11,20-trione



17,21-Dihydroxypregn-4-ene-3,20-dione



17,21-Dihydroxypregn-4-ene-3,11,20-trione


2,3-Dihydroxypropanal, (±)



2,3-Dihydroxypropanoic acid, (*R*)



1,3-Dihydroxy-2-propanone



2,3-Dihydroxypropyl decanoate



2,3-Dihydroxypropyl octanoate

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3754	4,8-Dihydroxy-2-quinolinecarboxylic acid	Xanthurenic acid	$C_{10}H_7NO_4$	59-00-7	205.168	ye micry cry (w)	289				i H_2O; s EtOH, dil HCl; sl eth, bz
3755	Dihydroxytartaric acid		$C_4H_6O_8$	76-30-2	182.086		114.5				
3756	3,4-Dihydroxy-5-[(3,4,5-trihydroxybenzoyl)oxy]benzoic acid	Digallic acid	$C_{14}H_{10}O_9$	536-08-3	322.224	nf (dil al + 1w)	269 dec				vs ace, EtOH
3757	2-(3,6-Dihydroxy-9*H*-xanthen-9-yl)benzoic acid	Fluorescin	$C_{20}H_{14}O_5$	518-44-5	334.322	col or ye nd (eth), pl (bz)	126				i H_2O; s EtOH, eth, ace, bz, HOAc
3758	Diiodoacetylene		C_2I_2	624-74-8	277.830	orth nd (lig)	81.5	exp			vs ace, bz, eth, EtOH
3759	2,4-Diiodoaniline		$C_6H_5I_2N$	533-70-0	344.920	br nd or orth cry (al)	95.5		2.748^{25}		vs ace, bz, eth, EtOH
3760	*o*-Diiodobenzene	1,2-Diiodobenzene	$C_6H_4I_2$	615-42-9	329.905	pl or pr (lig)	27	287; 100^{3}	2.54^{20}	1.7179^{20}	i H_2O; sl EtOH
3761	*m*-Diiodobenzene	1,3-Diiodobenzene	$C_6H_4I_2$	626-00-6	329.905	orth pl or pr (eth-al)	40.4	285	2.47^{25}		i H_2O; vs eth, EtOH, chl
3762	*p*-Diiodobenzene	1,4-Diiodobenzene	$C_6H_4I_2$	624-38-4	329.905	orth lf (al)	131.5	285			i H_2O; s EtOH; vs eth; sl chl
3763	1,4-Diiodobutane		$C_4H_8I_2$	628-21-7	309.916		5.8	125^{15} dec	2.3494^{25}	1.6184^{25}	i H_2O; sl ctc; s os
3764	1,2-Diiodoethane		$C_2H_4I_2$	624-73-7	281.862	ye mcl pr or orth (eth)	83	200	3.325^{20}	1.871^{20}	sl H_2O; s EtOH, eth, ace, chl
3765	*cis*-1,2-Diiodoethene	*cis*-1,2-Diiodoethylene	$C_2H_2I_2$	590-26-1	279.846		-14	72.5^{16}	3.0625^{20}		i H_2O; s eth, chl
3766	4,4'-Diiodofluorescein		$C_{20}H_{10}I_2O_5$	38577-97-8	584.099	oran-red pow					sl H_2O; s alk, EtOH
3767	1,6-Diiodohexane	Hexamethylene diiodide	$C_6H_{12}I_2$	629-09-4	337.968	nd	9.5	163^{17}, 141^{10}	2.0342^{25}	1.5837^{25}	i H_2O; vs EtOH, eth
3768	Diiodomethane	Methylene iodide	CH_2I_2	75-11-6	267.836	ye nd or lf	6.1	182	3.3211^{20}	1.7411^{20}	sl H_2O, ctc; s EtOH, eth, bz, chl
3769	2,6-Diiodo-4-nitrophenol	Disophenol	$C_6H_3I_2NO_3$	305-85-1	390.902	lt ye cry (gl HOAc)	157				vs EtOH
3770	1,5-Diiodopentane	Pentamethylene diiodide	$C_5H_{10}I_2$	628-77-3	323.942		9	149^{20}, 101^{3}	2.1692^{25}	1.5987^{25}	i H_2O; s eth, chl
3771	1,2-Diiodopropane		$C_3H_6I_2$	598-29-8	295.889				2.490^{18}		vs eth, EtOH
3772	1,3-Diiodopropane	Trimethylene diiodide	$C_3H_6I_2$	627-31-6	295.889		-20	dec 227; 110^{19}	2.5612^{25}	1.6391^{25}	i H_2O; s eth, ctc, chl
3773	5,7-Diiodo-8-quinolinol	Iodoquinol	$C_9H_5I_2NO$	83-73-8	396.951	ye nd (HOAc, xyl)	210				sl H_2O, bz, chl, eth; vs EtOH; s alk
3774	3,5-Diiodo-*L*-tyrosine		$C_9H_9I_2NO_3$	300-39-0	432.981	ye nd (w, 70% al)	213				sl H_2O; i EtOH, eth, bz
3775	Diisobutyl adipate		$C_{14}H_{26}O_4$	141-04-8	258.354			293; 187^{15}	0.9543^{19}	1.4301^{20}	
3776	Diisobutylaluminum chloride		$C_8H_{18}AlCl$	1779-25-5	176.664	hyg col liq	-40	152^{10}	0.905	1.4506^{20}	s eth, hx
3777	Diisobutylaluminum hydride		$C_8H_{19}Al$	1191-15-7	142.219	liq		140^{4}, 85$^{0.5}$			s cyhex, eth, bz, tol
3778	Diisobutylamine	2-Methyl-*N*-(2-methylpropyl)-1-propanamine	$C_8H_{19}N$	110-96-3	129.244	liq	-73.5	139.6		1.4090^{20}	sl H_2O, ctc; s EtOH, eth, ace, bz
3779	Diisobutyl carbonate		$C_9H_{18}O_3$	539-92-4	174.237			190	0.9138^{20}	1.4072^{20}	i H_2O; msc EtOH, eth
3780	Diisobutyl ether	1,1'-Oxybis[2-methylpropane]	$C_8H_{18}O$	628-55-7	130.228			122.6	0.761^{15}		i H_2O; msc EtOH, eth
3781	Diisobutyl phthalate		$C_{16}H_{22}O_4$	84-69-5	278.344			296.5; 159^{4}	1.0490^{15}		s ctc
3782	Diisobutyl sulfide		$C_8H_{18}S$	592-65-4	146.294	liq	-105.5	171	0.8363^{10}		
3783	1,3-Diisocyanatobenzene		$C_8H_4N_2O_2$	123-61-5	160.130	cry	51	103^{8}			
3784	1,4-Diisocyanatobenzene		$C_8H_4N_2O_2$	104-49-4	160.130	cry	95	117^{14}			
3785	Diisodecyl phthalate	Bis(8-methylnonyl)phthalate	$C_{28}H_{46}O_4$	26761-40-0	446.663	liq	-50	253^{4}	0.966^{20}		i H_2O; s os
3786	Diisononyl phthalate	Bis(7-methyloctyl)phthalate	$C_{26}H_{42}O_4$	28553-12-0	418.609	col liq					i H_2O; s ace, MeOH; bz, eth
3787	Diisooctyl adipate		$C_{22}H_{42}O_4$	1330-86-5	370.566			210^{4}			
3788	Diisooctyl phthalate		$C_{24}H_{38}O_4$	27554-26-3	390.557			370			
3789	Diisopentylamine	3-Methyl-*N*-isopentyl-1-butanamine	$C_{10}H_{23}N$	544-00-3	157.297	liq	-44	188	0.7672^{21}	1.4235^{20}	i H_2O; s EtOH; msc eth
3790	Diisopentyl ether	Diisoamyl ether	$C_{10}H_{22}O$	544-01-4	158.281			172.5	0.7777^{20}	1.4085^{20}	i H_2O; vs ace, EtOH, chl
3791	Diisopentyl phthalate	Diisoamyl phthalate	$C_{18}H_{26}O_4$	605-50-5	306.397			dec 334	1.0209^{16}	1.4871^{20}	vs EtOH
3792	Diisopentyl sulfide		$C_{10}H_{22}S$	544-02-5	174.347	liq	-74.6	211	0.8323^{20}	1.4520^{20}	i H_2O; msc EtOH; vs eth
3793	Diisopropanolamine	1,1'-Iminobis-2-propanol	$C_6H_{15}NO_2$	110-97-4	133.189	cry	44.5	250; 151^{23}	0.989^{20}		s H_2O, EtOH; sl eth
3794	Diisopropyl adipate		$C_{12}H_{22}O_4$	6938-94-9	230.301		-0.6	120$^{6.5}$	0.9569^{20}	1.4247^{20}	vs ace, eth, EtOH



4,8-Dihydroxy-2-quinolinecarboxylic acid


Dihydroxytartaric acid



3,4-Dihydroxy-5-[(3,4,5-trihydroxybenzoyl)oxy]benzoic acid



2-(3,6-Dihydroxy-9*H*-xanthen-9-yl)benzoic acid


Diiodoacetylene


2,4-Diiodoaniline


o-Diiodobenzene



m-Diiodobenzene



p-Diiodobenzene


1,4-Diiodobutane



1,2-Diiodoethane



cis-1,2-Diiodoethene



4,4'-Diiodofluorescein


1,6-Diiodohexane



Diiodomethane



2,6-Diiodo-4-nitrophenol



1,5-Diiodopentane



1,2-Diiodopropane



1,3-Diiodopropane



5,7-Diiodo-8-quinolinol



3,5-Diiodo-*L*-tyrosine



Diisobutyl adipate



Diisobutylaluminum chloride



Diisobutylaluminum hydride



Diisobutylamine



Diisobutyl carbonate



Diisobutyl ether



Diisobutyl phthalate



Diisobutyl sulfide



1,3-Diisocyanatobenzene



1,4-Diisocyanatobenzene



Diisodecyl phthalate



Diisononyl phthalate



Diisooctyl adipate



Diisooctyl phthalate



Diisopentylamine


Diisopentyl ether



Diisopentyl phthalate



Diisopentyl sulfide



Diisopropanolamine



Diisopropyl adipate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3795	Diisopropylamine	*N*-Isopropyl-2-propanamine	$C_6H_{15}N$	108-18-9	101.190	liq	-61	83.9	0.7153^{20}	1.3924^{20}	vs ace, bz, eth, EtOH
3796	2,6-Diisopropylaniline		$C_{12}H_{19}N$	24544-04-5	177.286	liq	-45	257	0.94^{25}	1.5332^{20}	
3797	1,2-Diisopropylbenzene		$C_{12}H_{18}$	577-55-9	162.271	liq	-57	204	0.8701^{20}	1.4960^{20}	i H_2O; msc EtOH, eth, ace, bz, ctc
3798	1,3-Diisopropylbenzene		$C_{12}H_{18}$	99-62-7	162.271	liq	-63.1	203.2	0.8559^{20}	1.4883^{20}	i H_2O; msc EtOH, eth, ace, bz, ctc
3799	1,4-Diisopropylbenzene		$C_{12}H_{18}$	100-18-5	162.271	liq	-17	210.3	0.8568^{20}	1.4898^{20}	i H_2O; msc EtOH, eth, ace, bz, ctc
3800	*p*-Diisopropylbenzene hydroperoxide		$C_{12}H_{18}O_2$	98-49-7	194.270	waxy cry	30.1	123^{1}	0.9932^{20}		i H_2O
3801	*N,N*-Diisopropyl-2-benzothiazolesulfenamide		$C_{13}H_{18}N_2S_2$	95-29-4	266.425		59.0				
3802	*N,N'*-Diisopropylcarbodiimide		$C_7H_{14}N_2$	693-13-0	126.199			147	0.806^{25}	1.4320^{20}	
3803	Diisopropyl disulfide		$C_6H_{14}S_2$	4253-89-8	150.305	liq	-69	177	0.9435^{20}	1.4916^{20}	
3804	*N,N*-Diisopropylethanolamine	*N,N*-Diisopropyl-2-aminoethanol	$C_8H_{19}NO$	96-80-0	145.243			190	0.826^{25}	1.4417^{20}	
3805	Diisopropyl ether	Isopropyl ether	$C_6H_{14}O$	108-20-3	102.174	liq	-85.4	68.4	0.7192^{25}	1.3658^{25}	sl H_2O; msc EtOH, eth; s ace, ctc
3806	Diisopropyl methylphosphonate		$C_7H_{17}O_3P$	1445-75-6	180.182			66^{3}		1.4120^{16}	
3807	2,6-Diisopropylnaphthalene		$C_{16}H_{20}$	24157-81-1	212.330	cry (MeOH)	70				
3808	Diisopropyl oxalate		$C_8H_{14}O_4$	615-81-6	174.195			190	1.002^{20}	1.4100^{20}	vs eth, EtOH
3809	Diisopropyl phosphonate		$C_6H_{15}O_3P$	1809-20-7	166.155			97^{40}, 76^{10}	0.9970^{18}		
3810	*O,O*-Diisopropyl phosphorodithioate		$C_6H_{15}O_2PS_2$	107-56-2	214.286	liq		71^{3}	1.09^{20}		s EtOH, bz, ace, ctc, chl
3811	Diisopropyl phthalate	1,2-Benzenedicarboxylic acid, diisopropyl ester	$C_{14}H_{18}O_4$	605-45-8	250.291			130^{12}	1.0615^{15}	1.4900^{20}	
3812	Diisopropyl sulfide		$C_6H_{14}S$	625-80-9	118.240	liq	-78.1	120.0	0.8142^{20}	1.4438^{20}	i H_2O; s EtOH, eth
3813	Diisopropyl tartrate, (±)		$C_{10}H_{18}O_6$	58167-01-4	234.246		34	275; 154^{12}	1.1166^{20}		vs ace, eth, EtOH
3814	Diisopropyl thioperoxydicarbonate	Diisopropyl dixanthogen	$C_8H_{14}O_2S_4$	105-65-7	270.456		52				s chl
3815	1,4-Diisothiocyanatobenzene	Bitoscanate	$C_8H_4N_2S_2$	4044-65-9	192.261	nd (ace, HOAc)	132				
3816	Diketene		$C_4H_4O_2$	674-82-8	84.074	liq	-6.5	126.1	1.0877^{20}	1.4379^{20}	
3817	Dilactic acid	2,2'-Oxybispropanoic acid	$C_6H_{10}O_5$	19201-34-4	162.140	orth	112.5				vs H_2O, eth
3818	Dimefline		$C_{20}H_{21}NO_3$	1165-48-6	323.386		109.5				s chl
3819	Dimefox	Tetramethylphosphorodiamidic fluoride	$C_4H_{12}FN_2OP$	115-26-4	154.122	liq		86^{15}	1.1151^{20}	1.4267^{20}	vs H_2O, bz, eth
3820	Dimemorfan	3,17-Dimethylmorphinan, (9 α,13 α,14 α)-	$C_{18}H_{25}N$	36309-01-0	255.399	ye oil	92	$133^{0.3}$			
3821	2,3-Dimercaptobutanedioic acid		$C_4H_6O_4S_2$	2418-14-6	182.219	wh cry (MeOH)	193				
3822	1,4-Dimercapto-2,3-butanediol		$C_4H_{10}O_2S_2$	7634-42-6	154.251		42.5				s chl
3823	2,2'-Dimercaptodiethyl ether	2-Mercaptoethyl ether	$C_4H_{10}OS_2$	2150-02-9	138.251	liq	-80	217; 64^{2}	1.114^{20}		
3824	2,3-Dimercapto-1-propanol	Dimercaprol	$C_3H_8OS_2$	59-52-9	124.225			$83^{0.8}$	1.2463^{20}	1.5749^{20}	s EtOH, eth, oils; sl chl
3825	Dimetan®		$C_{11}H_{17}NO_3$	122-15-6	211.258	cry	46	175^{11}			s H_2O, cyhex; vs EtOH, eth, ace
3826	Dimethipin	2,3-Dihydro-5,6-dimethyl-1,4-dithiin, 1,1,4,4-tetraoxide	$C_6H_{10}O_4S_2$	55290-64-7	210.271		165				
3827	Dimethirimol	5-Butyl-2-(dimethylamino)-6-methylpyrimidin-4(1*H*)-one	$C_{11}H_{19}N_3O$	5221-53-4	209.288	nd	102				sl H_2O; vs chl, xyl; s EtOH, ace
3828	Dimethisoquin	2-[(3-Butyl-1-isoquinolinyl)oxy] -*N,N*-dimethylethanamine	$C_{17}H_{24}N_2O$	86-80-6	272.385		146	156^{3}		1.5486^{20}	s H_2O, EtOH
3829	Dimethoxane	2,6-Dimethyl-1,3-dioxan-4-ol acetate	$C_8H_{14}O_4$	828-00-2	174.195	liq		86^{10}	1.0655^{20}	1.4310^{20}	msc H_2O; s os
3830	2',5'-Dimethoxyacetophenone		$C_{10}H_{12}O_3$	1201-38-3	180.200	cry	21	156^{14}	1.139	1.5441^{20}	
3831	1,2-Dimethoxy-4-allylbenzene		$C_{11}H_{14}O_2$	93-15-2	178.228	liq	-2.0	254.7	1.0396^{20}	1.5340^{20}	i H_2O; s EtOH, eth
3832	4,7-Dimethoxy-5-allyl-1,3-benzodioxole	Apiole	$C_{12}H_{14}O_4$	523-80-8	222.237	nd	29.5	294; 179^{35}	1.015^{20}	1.5360^{20}	vs ace, bz, EtOH, lig
3833	2,4-Dimethoxyaniline		$C_8H_{11}NO_2$	2735-04-8	153.179	pl (lig)	33.5	262.0			sl H_2O, chl; s EtOH, eth, bz, lig
3834	2,5-Dimethoxyaniline		$C_8H_{11}NO_2$	102-56-7	153.179		82.5	270			s H_2O, EtOH, chl, lig
3835	3,4-Dimethoxyaniline		$C_8H_{11}NO_2$	6315-89-5	153.179	lf (eth)	87.5	159^{14}			s eth, chl



Diisopropylamine



2,6-Diisopropylaniline



1,2-Diisopropylbenzene



1,3-Diisopropylbenzene



1,4-Diisopropylbenzene



p-Diisopropylbenzene hydroperoxide



N,N-Diisopropyl-2-benzothiazolesulfenamide



N,N'-Diisopropylcarbodiimide



Diisopropyl disulfide



N,N-Diisopropylethanolamine



Diisopropyl ether



Diisopropyl methylphosphonate



2,6-Diisopropylnaphthalene



Diisopropyl oxalate



Diisopropyl phosphonate



O,O-Diisopropyl phosphorodithioate


Diisopropyl phthalate



Diisopropyl sulfide



Diisopropyl tartrate, (±)



Diisopropyl thioperoxydicarbonate



1,4-Diisothiocyanatobenzene



Diketene



Dilactic acid



Dimefline



Dimefox



Dimemorfan



2,3-Dimercaptobutanedioic acid



1,4-Dimercapto-2,3-butanediol



2,2'-Dimercaptodiethyl ether



2,3-Dimercapto-1-propanol



Dimetan®



Dimethipin



Dimethirimol



Dimethisoquin



Dimethoxane



2',5'-Dimethoxyacetophenone


1,2-Dimethoxy-4-allylbenzene



4,7-Dimethoxy-5-allyl-1,3-benzodioxole



2,4-Dimethoxyaniline



2,5-Dimethoxyaniline



3,4-Dimethoxyaniline


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3836	2,4-Dimethoxybenzaldehyde		$C_9H_{10}O_3$	613-45-6	166.173	nd (al or lig)	72	290; 165^{10}			i H_2O; s EtOH, eth, bz; sl chl
3837	2,5-Dimethoxybenzaldehyde		$C_9H_{10}O_3$	93-02-7	166.173		52	270; 146^{10}			sl H_2O; s EtOH, eth
3838	3,4-Dimethoxybenzaldehyde	Veratraldehyde	$C_9H_{10}O_3$	120-14-9	166.173	nd (eth, lig, to)	43	281; 155^{10}			sl H_2O, chl; vs EtOH, eth
3839	3,5-Dimethoxybenzaldehyde		$C_9H_{10}O_3$	7311-34-4	166.173		46.3	151^{16}			sl H_2O, peth; s EtOH, bz
3840	1,2-Dimethoxybenzene	Veratrole	$C_8H_{10}O_2$	91-16-7	138.164		22.5	206	1.0810^{25}	1.5827^{21}	sl H_2O; s EtOH, eth, ctc
3841	1,3-Dimethoxybenzene		$C_8H_{10}O_2$	151-10-0	138.164	liq	-52	217.5	1.0521^{25}	1.5231^{20}	sl H_2O; s EtOH, eth, bz, ctc, sulf
3842	1,4-Dimethoxybenzene		$C_8H_{10}O_2$	150-78-7	138.164	lf (w)	59	212.6	1.0375^{55}		sl H_2O; s EtOH, chl; vs eth, bz
3843	3,4-Dimethoxybenzeneacetic acid		$C_{10}H_{12}O_4$	93-40-3	196.200	cry (bz-peth) nd (w+1)	98				s H_2O, chl; vs EtOH, eth
3844	3,4-Dimethoxybenzeneethanamine		$C_{10}H_{15}NO_2$	120-20-7	181.232			164^{14}		1.5464^{20}	s ctc
3845	3,4-Dimethoxybenzenemethanamine		$C_9H_{13}NO_2$	5763-61-1	167.205			156^{12}, 120^{3}	1.143^{25}		s chl
3846	3,4-Dimethoxybenzenemethanol		$C_9H_{12}O_3$	93-03-8	168.189	visc oil		298; 172^{12}	1.178^{17}	1.555^{17}	s H_2O, EtOH
3847	3,3'-Dimethoxybenzidine	Dianisidine	$C_{14}H_{16}N_2O_2$	119-90-4	244.289	lf or nd (w)	137				i H_2O; s EtOH, eth, ace, bz, chl
3848	3,3'-Dimethoxybenzidine-4,4'-diisocyanate		$C_{16}H_{12}N_2O_4$	91-93-0	296.277	cry	112				
3849	2,4-Dimethoxybenzoic acid		$C_9H_{10}O_4$	91-52-1	182.173		108.5				sl H_2O; s EtOH, eth, chl, HOAc
3850	2,6-Dimethoxybenzoic acid		$C_9H_{10}O_4$	1466-76-8	182.173		186 dec				
3851	3,4-Dimethoxybenzoic acid	Veratric acid	$C_9H_{10}O_4$	93-07-2	182.173	nd (w or HOAc) orth (sub)	181	sub			i H_2O; vs EtOH, eth; sl chl
3852	3,5-Dimethoxybenzoic acid		$C_9H_{10}O_4$	1132-21-4	182.173	nd (w), pr (al)	185.5	sub			vs eth, EtOH
3853	4,4'-Dimethoxybenzoin	*p*-Anisoin	$C_{16}H_{16}O_4$	119-52-8	272.296	pr (dil al)	114.0				sl H_2O, chl, EtOH, eth; s ace
3854	5,7-Dimethoxy-2*H*-1-benzopyran-2-one	Limettin	$C_{11}H_{10}O_4$	487-06-9	206.195	pr or nd (al)	149	dec 200			sl H_2O; vs EtOH, ace, chl; i eth, lig
3855	4,4'-Dimethoxy-1,1'-biphenyl		$C_{14}H_{14}O_2$	2132-80-1	214.260	lf (bz)	175	sub			i H_2O, peth; vs EtOH, bz, chl; sl eth
3856	Dimethoxyborane		$C_2H_7BO_2$	4542-61-4	73.887	vol liq or gas	-130.6	25.9			dec H_2O
3857	4,4-Dimethoxy-2-butanone		$C_6H_{12}O_3$	5436-21-5	132.157			50^{5}			s ctc
3858	2,6-Dimethoxy-2,5-cyclohexadiene-1,4-dione	2,6-Dimethoxy-*p*-quinone	$C_8H_8O_4$	530-55-2	168.148	ye mcl pr (HOAc)	256	sub			sl H_2O, EtOH, eth; s tfa; vs alk, HOAc
3859	Dimethoxydimethylsilane		$C_4H_{12}O_2Si$	1112-39-6	120.223			82	0.8646^{20}	1.3708^{20}	dec H_2O
3860	Dimethoxydiphenylsilane		$C_{14}H_{16}O_2Si$	6843-66-9	244.362			286; 161^{15}	1.0771^{20}	1.5447^{20}	
3861	1,1-Dimethoxydodecane	Lauraldehyde, dimethyl acetal	$C_{14}H_{30}O_2$	14620-52-1	230.387			133^{5}		1.4310^{25}	vs eth, EtOH
3862	2,2-Dimethoxyethanamine		$C_4H_{11}NO_2$	22483-09-6	105.136		-78	137^{95}	0.966^{25}	1.4170^{20}	
3863	1,2-Dimethoxyethane	Ethylene glycol dimethyl ether	$C_4H_{10}O_2$	110-71-4	90.121	liq	-69.20	84.50	0.8637^{25}	1.3770^{25}	s H_2O, EtOH, eth, ace, bz, chl, ctc
3864	(2,2-Dimethoxyethyl)benzene		$C_{10}H_{14}O_2$	101-48-4	166.217			193.5			
3865	4,8-Dimethoxyfuro[2,3-b] quinoline	Fagarine	$C_{13}H_{11}NO_3$	524-15-2	229.231	pr (al)	142				sl H_2O, peth; s EtOH, eth, bz, chl
3866	1,1-Dimethoxyhexadecane	Palmitaldehyde, dimethyl acetal	$C_{18}H_{38}O_2$	2791-29-9	286.494		10	144^{2}	0.8542^{20}	1.4382^{25}	vs ace, eth, EtOH
3867	2,4-Dimethoxy-6-hydroxyacetophenone	Xanthoxylin	$C_{10}H_{12}O_4$	90-24-4	196.200	cry (al)	82	185^{20}			vs eth, EtOH
3868	5,6-Dimethoxy-1-indanone		$C_{11}H_{12}O_3$	2107-69-9	192.211		119.5				sl ctc
3869	6,7-Dimethoxy-1(3*H*)-isobenzofuranone	Meconin	$C_{10}H_{10}O_4$	569-31-3	194.184	wh nd (w)	102.5				sl H_2O; s EtOH, eth, ace, bz, HOAc, chl
3870	Dimethoxymethane	Methylal	$C_3H_8O_2$	109-87-5	76.095	liq	-105.1	42	0.8593^{20}	1.3513^{20}	s H_2O; vs ace, bz, eth, EtOH
3871	1,2-Dimethoxy-4-methylbenzene		$C_9H_{12}O_2$	494-99-5	152.190	pr (eth)	24	220	1.0509^{25}	1.5257^{25}	i H_2O; sl ctc; vs os
3872	1,3-Dimethoxy-5-methylbenzene		$C_9H_{12}O_2$	4179-19-5	152.190			244	1.0478^{15}	1.5234^{20}	vs bz, eth, EtOH
3873	1,4-Dimethoxy-2-methylbenzene		$C_9H_{12}O_2$	24599-58-4	152.190		21	214.0			
3874	*N*-(Dimethoxymethyl) dimethylamine	Dimethylformamide dimethyl acetal	$C_5H_{13}NO_2$	4637-24-5	119.163			104	0.897^{25}	1.3972^{20}	



2,4-Dimethoxybenzaldehyde



2,5-Dimethoxybenzaldehyde



3,4-Dimethoxybenzaldehyde



3,5-Dimethoxybenzaldehyde



1,2-Dimethoxybenzene



1,3-Dimethoxybenzene



1,4-Dimethoxybenzene



3,4-Dimethoxybenzeneacetic acid



3,4-Dimethoxybenzeneethanamine



3,4-Dimethoxybenzenemethanamine



3,4-Dimethoxybenzenemethanol



3,3'-Dimethoxybenzidine



3,3'-Dimethoxybenzidine-4,4'-diisocyanate



2,4-Dimethoxybenzoic acid



2,6-Dimethoxybenzoic acid



3,4-Dimethoxybenzoic acid



3,5-Dimethoxybenzoic acid



4,4'-Dimethoxybenzoin



5,7-Dimethoxy-2*H*-1-benzopyran-2-one



4,4'-Dimethoxy-1,1'-biphenyl



Dimethoxyborane



4,4-Dimethoxy-2-butanone



2,6-Dimethoxy-2,5-cyclohexadiene-1,4-dione



Dimethoxydimethylsilane



Dimethoxydiphenylsilane



1,1-Dimethoxydodecane



2,2-Dimethoxyethanamine



1,2-Dimethoxyethane



(2,2-Dimethoxyethyl)benzene



4,8-Dimethoxyfuro[2,3-b]quinoline



1,1-Dimethoxyhexadecane



2,4-Dimethoxy-6-hydroxyacetophenone



5,6-Dimethoxy-1-indanone



6,7-Dimethoxy-1(3*H*)-isobenzofuranone


Dimethoxymethane



1,2-Dimethoxy-4-methylbenzene



1,3-Dimethoxy-5-methylbenzene



1,4-Dimethoxy-2-methylbenzene



N-(Dimethoxymethyl)dimethylamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3875	2,2-Dimethoxy-*N*-methylethanamine		$C_5H_{13}NO_2$	122-07-6	119.163			140	0.928^{25}	1.4115^{20}	
3876	Dimethoxymethylphenylsilane		$C_9H_{14}O_2Si$	3027-21-2	182.292			129^{79}		1.4795^{20}	
3877	1,2-Dimethoxy-4-nitrobenzene		$C_8H_9NO_4$	709-09-1	183.162	ye nd (al-w)	98	230^{15}	1.1888^{133}		i H_2O; vs EtOH, eth; s chl; sl lig
3878	1,4-Dimethoxy-2-nitrobenzene		$C_8H_9NO_4$	89-39-4	183.162	gold-ye nd (dil al)	72.5		1.1666^{132}		i H_2O; s EtOH, bz, chl, sulf
3879	2,6-Dimethoxyphenol		$C_8H_{10}O_3$	91-10-1	154.163	mcl pr (w)	56.5	261			vs eth, EtOH
3880	3,5-Dimethoxyphenol		$C_8H_{10}O_3$	500-99-2	154.163		37	199^{35}, 170^{10}			s eth, bz; sl lig
3881	1-(3,4-Dimethoxyphenyl)ethanone		$C_{10}H_{12}O_3$	1131-62-0	180.200	pr (dil al)	51	287			vs H_2O, bz, EtOH, chl
3882	1,1-Dimethoxypropane		$C_5H_{12}O_2$	4744-10-9	104.148			86	0.8648^{20}		
3883	2,2-Dimethoxypropane		$C_5H_{12}O_2$	77-76-9	104.148	liq	-47	83	0.847^{25}	1.3780^{20}	
3884	3,3-Dimethoxy-1-propene		$C_5H_{10}O_2$	6044-68-4	102.132			88	0.862^{25}	1.3954^{20}	
3885	1,2-Dimethoxy-4-(1-propenyl) benzene		$C_{11}H_{14}O_2$	93-16-3	178.228		18	270.5	1.0521^{20}	1.5616^{20}	
3886	4,5-Dimethoxy-6-(2-propenyl)-1,3-benzodioxole	Apiole (Dill)	$C_{12}H_{14}O_4$	484-31-1	222.237	oil	29.5	285	1.1598^{15}	1.5305^{17}	
3887	1,2-Dimethoxy-4-vinylbenzene		$C_{10}H_{12}O_2$	6380-23-0	164.201					1.5711^{20}	s chl
3888	Dimethylacetal		$C_4H_{10}O_2$	534-15-6	90.121	liq	-113.2	64.5	0.8501^{20}	1.3668^{20}	s H_2O, EtOH, eth, ctc, chl; vs ace
3889	*N,N*-Dimethylacetamide	*N,N*-Dimethylethanamide	C_4H_9NO	127-19-5	87.120	liq	-18.59	165	0.9372^{25}	1.4341^{25}	msc H_2O, EtOH, eth, ace, bz, chl
3890	2,7-Dimethyl-3,6-acridinediamine, monohydrochloride	Acridine Yellow	$C_{15}H_{16}ClN_3$	135-49-9	273.761	red cry pow					s hot H_2O, EtOH
3891	Dimethyl adipate		$C_8H_{14}O_4$	627-93-0	174.195	cry	10.3	115^{13}	1.0600^{20}	1.4283^{20}	i H_2O; s EtOH, eth, ctc, HOAc
3892	3,3-Dimethylallyl diphosphate	3-Methyl-2-butenyl pyrophosphate	$C_5H_{12}O_7P_2$	358-72-5	246.092	cry (MeOH)					
3893	Dimethylamine	*N*-Methylmethanamine	C_2H_7N	124-40-3	45.084	col gas	-92.18	6.88	0.6804^{0}	1.350^{17}	vs H_2O; s EtOH, eth
3894	Dimethylamine hydrochloride	*N*-Methylmethanamine hydrochloride	C_2H_8ClN	506-59-2	81.545	orth nd (al)	171				vs H_2O, EtOH, chl
3895	(Dimethylamino)acetonitrile		$C_4H_8N_2$	926-64-7	84.120			137.5	0.8649^{20}	1.4095^{20}	vs H_2O, EtOH
3896	4'-(Dimethylamino)acetophenone	4-Acetyl-*N,N*-dimethylaniline	$C_{10}H_{13}NO$	2124-31-4	163.216	nd (w, peth)	105.5				vs H_2O, eth, lig; sl chl
3897	10-[(Dimethylamino)acetyl]-10*H*-phenothiazine	Ahistan	$C_{16}H_{16}N_2OS$	518-61-6	284.375	cry	144.5				
3898	*p*-(Dimethylamino)azobenzene		$C_{14}H_{15}N_3$	60-11-7	225.289	ye lf (al)	117	dec			i H_2O; vs EtOH, py; s eth; sl chl, lig
3899	2',3-Dimethyl-4-aminoazobenzene	4-*o*-Tolylazo-*o*-toluidine	$C_{14}H_{15}N_3$	97-56-3	225.289	ye lf (al)	102				vs eth, EtOH
3900	4-(Dimethylamino)benzaldehyde	Ehrlich's reagent	$C_9H_{11}NO$	100-10-7	149.189	lf (w)	74.5	176^{17}	1.0254^{100}		sl H_2O, chl; s EtOH, eth, ace, bz
3901	*p*-(Dimethylamino) benzalrhodanine		$C_{12}H_{12}N_2OS_2$	536-17-4	264.365	dp red nd (xyl)	270 dec				i H_2O; sl EtOH, bz; vs eth, ctc; s ace
3902	2-(Dimethylamino)benzoic acid		$C_9H_{11}NO_2$	610-16-2	165.189	pr, nd (eth)	72	sub			vs H_2O, eth, EtOH
3903	3-(Dimethylamino)benzoic acid		$C_9H_{11}NO_2$	99-64-9	165.189	nd (w)	152.5				sl H_2O, chl; s EtOH, eth
3904	4-(Dimethylamino)benzoic acid		$C_9H_{11}NO_2$	619-84-1	165.189	nd (al)	242.5				s EtOH; sl eth
3905	4,4'-Dimethylaminobenzophenonimide	Brilliant Oil Yellow	$C_{17}H_{21}N_3$	492-80-8	267.369	ye or col pl (al)	136				i H_2O; s EtOH; sl eth
3906	(Dimethylamino)dimethylborane		$C_4H_{12}BN$	1113-30-0	84.956	liq	-92	65			vs eth, ace
3907	6-(Dimethylamino)-4,4-diphenyl-3-heptanone		$C_{21}H_{27}NO$	76-99-3	309.445		99.5				vs EtOH
3908	6-(Dimethylamino)-4,4-diphenyl-3-hexanone	Normethadone	$C_{20}H_{25}NO$	467-85-6	295.419	oily liq		165^{3}			
3909	2-(Dimethylamino)ethyl acrylate		$C_7H_{13}NO_2$	2439-35-2	143.184		<-60	95^{50}	0.938^{20}		
3910	3-[2-(Dimethylamino)ethyl]-1*H*-indol-5-ol	Bufotenine	$C_{12}H_{16}N_2O$	487-93-4	204.267	pr (EtOAc)	146.5	$320^{0.1}$			vs eth, EtOH
3911	2-(Dimethylamino)ethyl methacrylate		$C_8H_{15}NO_2$	2867-47-2	157.211			63^{6}			
3912	4-[2-(Dimethylamino)ethyl]phenol	Hordenine	$C_{10}H_{15}NO$	539-15-1	165.232	orth pr (al), nd (w)	117.5	173^{11}			vs eth, EtOH, chl
3913	*N*-[2-(Dimethylamino)ethyl]-*N,N',N'*-trimethyl-1,2-ethanediamine		$C_9H_{23}N_3$	3030-47-5	173.299			84^{12}		1.4413^{25}	
3914	5-(Dimethylamino)-1-naphthalenesulfonyl chloride	Dansyl chloride	$C_{12}H_{12}ClNO_2S$	605-65-2	269.747		70				



2,2-Dimethoxy-*N*-methylethanamine



Dimethoxymethylphenylsilane



1,2-Dimethoxy-4-nitrobenzene


1,4-Dimethoxy-2-nitrobenzene



2,6-Dimethoxyphenol



3,5-Dimethoxyphenol



1-(3,4-Dimethoxyphenyl)ethanone



1,1-Dimethoxypropane



2,2-Dimethoxypropane


3,3-Dimethoxy-1-propene



1,2-Dimethoxy-4-(1-propenyl)benzene



4,5-Dimethoxy-6-(2-propenyl)-1,3-benzodioxole



1,2-Dimethoxy-4-vinylbenzene


Dimethylacetal



N,N-Dimethylacetamide



2,7-Dimethyl-3,6-acridinediamine, monohydrochloride



Dimethyl adipate



3,3-Dimethylallyl diphosphate



Dimethylamine



Dimethylamine hydrochloride



(Dimethylamino)acetonitrile



4'-(Dimethylamino)acetophenone



10-[(Dimethylamino)acetyl]-10*H*-phenothiazine



p-(Dimethylamino)azobenzene



2',3-Dimethyl-4-aminoazobenzene



4-(Dimethylamino)benzaldehyde


p-(Dimethylamino)benzalrhodanine



2-(Dimethylamino)benzoic acid



3-(Dimethylamino)benzoic acid



4-(Dimethylamino)benzoic acid



4,4'-Dimethylaminobenzophenonimide



(Dimethylamino)dimethylborane



6-(Dimethylamino)-4,4-diphenyl-3-heptanone



6-(Dimethylamino)-4,4-diphenyl-3-hexanone



2-(Dimethylamino)ethyl acrylate


3-[2-(Dimethylamino)ethyl]-1*H*-indol-5-ol



2-(Dimethylamino)ethyl methacrylate



4-[2-(Dimethylamino)ethyl]phenol



N-[2-(Dimethylamino)ethyl]-*N,N',N'*-trimethyl-1,2-ethanediamine



5-(Dimethylamino)-1-naphthalenesulfonyl chloride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3915	3-(Dimethylamino)phenol		$C_8H_{11}NO$	99-07-0	137.179	nd (lig)	86	266.5		1.5895^{26}	i H_2O; s EtOH, eth, ace, bz, CS_2
3916	4-(Dimethylamino)phenol		$C_8H_{11}NO$	619-60-3	137.179		77	165^{30}			sl H_2O; s EtOH, eth
3917	[4-(Dimethylamino)phenyl] phenylmethanone	4-(Dimethylamino) benzophenone	$C_{15}H_{15}NO$	530-44-9	225.286	ye lf (al) nd (peth)	92.5				i H_2O; sl EtOH; vs eth; s chl, peth
3918	3-(Dimethylamino)-1-phenyl-1-propanone, hydrochloride		$C_{11}H_{16}ClNO$	879-72-1	213.704		153.5				
3919	3-[4-(Dimethylamino)phenyl]-2-propenal	4-(Dimethylamino) cinnamaldehyde	$C_{11}H_{13}NO$	6203-18-5	175.227		139.5				
3920	3-(Dimethylamino)propanenitrile		$C_5H_{10}N_2$	1738-25-6	98.146			173	0.8705^{20}		
3921	2-(Dimethylamino)-1-propanol		$C_5H_{13}NO$	15521-18-3	103.163			150.3	0.8820^{26}		s H_2O
3922	3-(Dimethylamino)-1-propanol		$C_5H_{13}NO$	3179-63-3	103.163			163.5	0.872^{25}	1.4360^{20}	s ctc
3923	1-(Dimethylamino)-2-propanol		$C_5H_{13}NO$	108-16-7	103.163			124.5	0.837^{25}	1.4193^{20}	s ctc
3924	3-(Dimethylamino)-1-propyne	*N,N*-Dimethyl-2-propargylamine	C_5H_9N	7223-38-3	83.132			80	0.7792^{20}	1.4195^{20}	
3925	2-Dimethylaminopurine	*N,N*-Dimethyl-1*H*-purin-6-amine	$C_7H_9N_5$	938-55-6	163.180		263				
3926	2-(*p*-Dimethylaminostyryl) benzothiazole		$C_{17}H_{16}N_2S$	1628-58-6	280.387	ye nd (MeOH)	207 dec				
3927	2,3-Dimethylaniline	2,3-Xylidine	$C_8H_{11}N$	87-59-2	121.180		<-15	221.5	0.9931^{20}	1.5684^{20}	sl H_2O; vs EtOH, eth; s ctc
3928	2,4-Dimethylaniline	2,4-Xylidine	$C_8H_{11}N$	95-68-1	121.180	liq	-14.3	214	0.9723^{20}	1.5569^{20}	sl H_2O, ctc; s EtOH, eth, bz
3929	2,5-Dimethylaniline	2,5-Xylidine	$C_8H_{11}N$	95-78-3	121.180	ye lf (lig)	15.5	214	0.9790^{21}	1.5591^{21}	sl H_2O; s eth, ctc
3930	2,6-Dimethylaniline	2,6-Xylidine	$C_8H_{11}N$	87-62-7	121.180		11.2	215	0.9842^{20}	1.5610^{20}	vs eth, EtOH
3931	3,4-Dimethylaniline	3,4-Xylidine	$C_8H_{11}N$	95-64-7	121.180	pl or pr (lig)	51	228	1.076^{18}		sl H_2O, chl; s eth; vs lig
3932	3,5-Dimethylaniline	3,5-Xylidine	$C_8H_{11}N$	108-69-0	121.180		9.8	220.5	0.9706^{20}	1.5581^{20}	sl H_2O; s eth, ctc
3933	*N*,2-Dimethylaniline		$C_8H_{11}N$	611-21-2	121.180			207.5	0.9709^{20}	1.5649^{20}	i H_2O; msc EtOH, eth; s ace
3934	*N*,3-Dimethylaniline		$C_8H_{11}N$	696-44-6	121.180			206.5	0.9660^{20}	1.5557^{25}	i H_2O; msc EtOH, eth; s ace
3935	*N*,4-Dimethylaniline		$C_8H_{11}N$	623-08-5	121.180			210	0.9348^{55}	1.5568^{20}	i H_2O; msc EtOH, eth; s ace
3936	*N,N*-Dimethylaniline		$C_8H_{11}N$	121-69-7	121.180	pa ye	2.42	194.15	0.9557^{20}	1.5582^{20}	sl H_2O; s EtOH, eth, ace, bz; vs chl
3937	*N,N*-Dimethylaniline hydrochloride		$C_8H_{12}ClN$	5882-44-0	157.641	hyg pl (w, bz)	90		1.1156^{19}		vs H_2O, EtOH, chl
3938	2,6-Dimethylanisole		$C_9H_{12}O$	1004-66-6	136.190			182.5	0.9619^{14}	1.5053^{14}	i H_2O; s EtOH, eth, bz, ctc
3939	3,5-Dimethylanisole		$C_9H_{12}O$	874-63-5	136.190			194; 89^{15}	0.9627^{15}	1.5110^{20}	i H_2O; s EtOH, eth, bz, CS_2; sl ctc
3940	9,10-Dimethylanthracene		$C_{16}H_{14}$	781-43-1	206.282		183.6	360.0			i H_2O
3941	1,4-Dimethyl-9,10-anthracenedione		$C_{16}H_{12}O_2$	1519-36-4	236.265	ye nd (al, sub)	140.5	sub			i H_2O; sl EtOH; s bz, xyl, HOAc
3942	Dimethylarsine		C_2H_7As	593-57-7	105.999	liq, ign in air	-136.1	36	1.208^{29}		vs ace, bz, eth, EtOH
3943	Dimethylarsinic acid	Cacodylic acid	$C_2H_7AsO_2$	75-60-5	137.998		195	>200			vs H_2O; s EtOH; i eth
3944	2,4-Dimethylbenzaldehyde		$C_9H_{10}O$	15764-16-6	134.174	liq	-9	218			s EtOH; s eth, ace, bz; sl chl
3945	2,5-Dimethylbenzaldehyde	Isoxylaldehyde	$C_9H_{10}O$	5779-94-2	134.174			220	0.9500^{20}		vs EtOH; s eth, ace, bz, ctc
3946	3,5-Dimethylbenzaldehyde		$C_9H_{10}O$	5779-95-3	134.174		9	221			vs ace, bz, eth, EtOH
3947	*N,N*-Dimethylbenzamide		$C_9H_{11}NO$	611-74-5	149.189		44.8	272.0			
3948	7,12-Dimethylbenz[a]anthracene	9,10-Dimethyl-1,2-benzanthracene	$C_{20}H_{16}$	57-97-6	256.341	pa ye pl (al, HOAc)	122.5				vs ace, bz
3949	4,5-Dimethyl-1,2-benzenediamine		$C_8H_{12}N_2$	3171-45-7	136.194		128				
3950	*N,N*-Dimethyl-1,2-benzenediamine		$C_8H_{12}N_2$	2836-03-5	136.194	oil		218; 90^{22}	0.995^{22}		sl H_2O; vs EtOH, eth, ace, bz
3951	*N,N*-Dimethyl-1,3-benzenediamine		$C_8H_{12}N_2$	2836-04-6	136.194		<-20	270; 138^{10}	0.995^{25}		sl H_2O; vs EtOH, eth
3952	*N,N*-Dimethyl-1,4-benzenediamine	Dimethyl-*p*-phenylenediamine	$C_8H_{12}N_2$	99-98-9	136.194	nd (bz)	53	263	1.036^{20}		s H_2O, chl; vs EtOH, eth, bz; sl lig
3953	2,5-Dimethyl-1,3-benzenediol		$C_8H_{10}O_2$	488-87-9	138.164	nd (bz), pr (w)	163	278.5			s H_2O, EtOH, eth



3-(Dimethylamino)phenol



4-(Dimethylamino)phenol



[4-(Dimethylamino)phenyl]phenylmethanone



3-(Dimethylamino)-1-phenyl-1-propanone, hydrochloride



3-[4-(Dimethylamino)phenyl]-2-propenal



3-(Dimethylamino)propanenitrile



2-(Dimethylamino)-1-propanol


3-(Dimethylamino)-1-propanol



1-(Dimethylamino)-2-propanol



3-(Dimethylamino)-1-propyne



2-Dimethylaminopurine



2-(*p*-Dimethylaminostyryl)benzothiazole



2,3-Dimethylaniline



2,4-Dimethylaniline



2,5-Dimethylaniline



2,6-Dimethylaniline



3,4-Dimethylaniline



3,5-Dimethylaniline



N,2-Dimethylaniline



N,3-Dimethylaniline



N,4-Dimethylaniline



N,*N*-Dimethylaniline


N,*N*-Dimethylaniline hydrochloride


2,6-Dimethylanisole



3,5-Dimethylanisole



9,10-Dimethylanthracene



1,4-Dimethyl-9,10-anthracenedione



Dimethylarsine



Dimethylarsinic acid



2,4-Dimethylbenzaldehyde



2,5-Dimethylbenzaldehyde



3,5-Dimethylbenzaldehyde



N,*N*-Dimethylbenzamide



7,12-Dimethylbenz[a]anthracene


4,5-Dimethyl-1,2-benzenediamine



N,*N*-Dimethyl-1,2-benzenediamine



N,*N*-Dimethyl-1,3-benzenediamine



N,*N*-Dimethyl-1,4-benzenediamine



2,5-Dimethyl-1,3-benzenediol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3954	2,6-Dimethyl-1,4-benzenediol		$C_8H_{10}O_2$	654-42-2	138.164	nd (xyl), cry (w)	152.3				vs eth, EtOH
3955	*N*,β-Dimethylbenzeneethanamine	Phenylpropylmethylamine	$C_{10}H_{15}N$	93-88-9	149.233			207.5	0.915^{25}		vs bz, eth, EtOH
3956	α,α-Dimethylbenzeneethanamine	Phentermine	$C_{10}H_{15}N$	122-09-8	149.233	oily liq		205; 100^{21}			
3957	α,α-Dimethylbenzenemethanamine		$C_9H_{13}N$	585-32-0	135.206			196.5	0.9423^{20}	1.5181^{25}	
3958	α,4-Dimethylbenzenemethanol	1-(4-Methylphenyl)ethanol	$C_9H_{12}O$	536-50-5	136.190			219	0.9668^{25}	1.5246^{20}	i H_2O; vs EtOH, eth
3959	α,α-Dimethylbenzenemethanol	α-Cumyl alcohol	$C_9H_{12}O$	617-94-7	136.190	pr	36	202	0.9735^{20}	1.5325^{20}	i H_2O; s EtOH, eth, bz, HOAc
3960	α,α-Dimethylbenzenepropanol	Benzyl-*tert*-butanol	$C_{11}H_{16}O$	103-05-9	164.244	nd	24.5	121^{13}	0.9626^{21}	1.5077^{21}	i H_2O; vs EtOH, eth, ace, bz
3961	*N*,4-Dimethylbenzenesulfonamide		$C_8H_{11}NO_2S$	640-61-9	185.244	pl (dil al)	78.5		1.340^{25}		vs eth, EtOH
3962	5,6-Dimethyl-1*H*-benzimidazole	Dimedazole	$C_9H_{10}N_2$	582-60-5	146.188	cry (eth)	205.5	sub			s H_2O, EtOH, eth, chl, DMSO
3963	2,4-Dimethylbenzoic acid		$C_9H_{10}O_2$	611-01-8	150.174	mcl or tcl nd (w)	90	268			sl H_2O; s EtOH, ace, bz, chl, HOAc, tol
3964	2,5-Dimethylbenzoic acid		$C_9H_{10}O_2$	610-72-0	150.174	nd (al)	132	sub	1.069^{21}		i H_2O; s EtOH, eth, ace, bz
3965	2,6-Dimethylbenzoic acid		$C_9H_{10}O_2$	632-46-2	150.174	nd (lig)	116	274.5; 155^{17}			sl H_2O, lig; s EtOH, eth
3966	3,4-Dimethylbenzoic acid		$C_9H_{10}O_2$	619-04-5	150.174	pr (al)	167.3				i H_2O; s EtOH, eth, bz
3967	3,5-Dimethylbenzoic acid	Mesitylenic acid	$C_9H_{10}O_2$	499-06-9	150.174	nd (w, al)	171.1	sub			sl H_2O; vs EtOH, eth
3968	4,4'-Dimethylbenzophenone	Bis(4-methylphenyl) ketone	$C_{15}H_{14}O$	611-97-2	210.271	orth (al)	96.5	334			vs ace, bz, eth, EtOH
3969	7,8-Dimethylbenzo[g]pteridine-2,4(1*H*,3*H*)-dione	Lumichrome	$C_{12}H_{10}N_4O_2$	1086-80-2	242.233	ye cry (chl)	300				sl H_2O, EtOH, chl
3970	2,5-Dimethylbenzoxazole		C_9H_9NO	5676-58-4	147.173			218.5	1.0880^{18}	1.5412^{20}	s ctc
3971	*N*,*N*-Dimethylbenzylamine	Dimethylbenzylamine	$C_9H_{13}N$	103-83-3	135.206			181	0.915^{0}	1.5011^{20}	sl H_2O; msc EtOH, eth
3972	*N*,*N*-Dimethyl-*N*'-benzyl-1,2-ethanediamine	*N*-Benzyl-*N*',*N*'-dimethyl-1,2-ethanediamine	$C_{11}H_{18}N_2$	103-55-9	178.274			145^{30}, 123^{11}	0.9343^{20}	1.5089^{20}	
3973	*N*,*N*-Dimethyl-*N*'-benzyl-*N*'-2-pyridinyl-1,2-ethanediamine	Tripelennamine	$C_{16}H_{21}N_3$	91-81-6	255.358	ye oil		140$^{0.1}$		1.576^{25}	misc H_2O
3974	6,6-Dimethylbicyclo[3.1.1]heptan-2-one, (1*R*)		$C_9H_{14}O$	38651-65-9	138.206	liq	-1	209	0.9807^{20}	1.4787^{20}	vs eth, EtOH
3975	2,3-Dimethylbicyclo[2.2.1]hept-2-ene	2,3-Dimethyl-2-norbornene	C_9H_{14}	529-16-8	122.207			140.5	0.8698^{17}	1.4688^{17}	s eth, ace, bz
3976	6,6-Dimethylbicyclo[3.1.1]hept-2-ene-2-ethanol		$C_{11}H_{18}O$	128-50-7	166.260			235; 110^{10}	0.973^{25}	1.4930^{20}	s chl
3977	2,2'-Dimethylbiphenyl		$C_{14}H_{14}$	605-39-0	182.261	cry (al)	19.5	256	0.9906^{20}	1.5752^{20}	i H_2O; vs EtOH, eth, bz; s ace
3978	3,3'-Dimethylbiphenyl		$C_{14}H_{14}$	612-75-9	182.261		9	280	0.9995^{20}	1.5946^{20}	i H_2O; vs EtOH, eth, bz; s ace
3979	4,4'-Dimethylbiphenyl		$C_{14}H_{14}$	613-33-2	182.261	mcl pr (eth)	125	295	0.917^{121}		i H_2O; sl EtOH; s eth, ace, bz, CS_2
3980	4,4'-Dimethyl-2,2'-bipyridine		$C_{12}H_{12}N_2$	1134-35-6	184.236		171.5				s chl
3981	2,3-Dimethyl-1,3-butadiene	Diisopropenyl	C_6H_{10}	513-81-5	82.143	liq	-76	68.8	0.7222^{25}	1.4394^{20}	s ctc
3982	*N*,*N*-Dimethylbutanamide		$C_6H_{13}NO$	760-79-2	115.173	liq	-40	186; 125^{100}	0.9064^{25}	1.4391^{25}	vs ace, bz, eth, EtOH
3983	3,3-Dimethyl-2-butanamine		$C_6H_{15}N$	3850-30-4	101.190	liq	-20	102	0.7668^{20}	1.4105^{25}	vs H_2O
3984	2,2-Dimethylbutane	Neohexane	C_6H_{14}	75-83-2	86.175	liq	-98.8	49.73	0.6444^{25}	1.3688^{20}	i H_2O; s EtOH, eth; vs ace, bz, peth, ctc
3985	2,3-Dimethylbutane		C_6H_{14}	79-29-8	86.175	liq	-128.10	57.93	0.6616^{20}	1.3750^{20}	i H_2O; s EtOH, eth; vs ace, bz, peth, ctc
3986	2,3-Dimethyl-2,3-butanediol	Pinacol	$C_6H_{14}O_2$	76-09-5	118.174	nd (al,eth)	43.32	174.4			sl H_2O, CS_2; vs EtOH, eth
3987	2,3-Dimethyl-2-butanethiol		$C_6H_{14}S$	1639-01-6	118.240	liq		126.1			
3988	2,2-Dimethylbutanoic acid		$C_6H_{12}O_2$	595-37-9	116.158	liq	-14	186	0.9276^{20}	1.4145^{20}	sl H_2O; s EtOH, eth
3989	2,2-Dimethyl-1-butanol		$C_6H_{14}O$	1185-33-7	102.174		<-15	136.5	0.8283^{20}	1.4208^{20}	sl H_2O; s EtOH, eth
3990	3,3-Dimethyl-1-butanol		$C_6H_{14}O$	624-95-3	102.174	liq	-60	143	0.844^{15}	1.4323^{15}	sl H_2O; s EtOH, eth, ace
3991	2,3-Dimethyl-2-butanol		$C_6H_{14}O$	594-60-5	102.174	liq	-14	118.4	0.8236^{20}	1.4176^{20}	s H_2O; msc EtOH, eth
3992	3,3-Dimethyl-2-butanol, (±)		$C_6H_{14}O$	20281-91-8	102.174		5.6	120.4	0.8122^{25}	1.4148^{20}	sl H_2O; vs EtOH, eth



2,6-Dimethyl-1,4-benzenediol



N,β-Dimethylbenzeneethanamine



α,α-Dimethylbenzeneethanamine



α,α-Dimethylbenzenemethanamine



α,4-Dimethylbenzenemethanol



α,α-Dimethylbenzenemethanol



α,α-Dimethylbenzenepropanol



N,4-Dimethylbenzenesulfonamide



5,6-Dimethyl-1*H*-benzimidazole



2,4-Dimethylbenzoic acid



2,5-Dimethylbenzoic acid



2,6-Dimethylbenzoic acid



3,4-Dimethylbenzoic acid



3,5-Dimethylbenzoic acid



4,4'-Dimethylbenzophenone


7,8-Dimethylbenzo[g]pteridine-2,4(1*H*,3*H*)-dione



2,5-Dimethylbenzoxazole



N,*N*-Dimethylbenzylamine



N,*N*-Dimethyl-*N*'-benzyl-1,2-ethanediamine



N,*N*-Dimethyl-*N*'-benzyl-*N*'-2-pyridinyl-1,2-ethanediamine



6,6-Dimethylbicyclo[3.1.1]heptan-2-one, (1*R*)



2,3-Dimethylbicyclo[2.2.1]hept-2-ene


6,6-Dimethylbicyclo[3.1.1]hept-2-ene-2-ethanol



2,2'-Dimethylbiphenyl


3,3'-Dimethylbiphenyl


4,4'-Dimethylbiphenyl


4,4'-Dimethyl-2,2'-bipyridine



2,3-Dimethyl-1,3-butadiene


N,*N*-Dimethylbutanamide



3,3-Dimethyl-2-butanamine



2,2-Dimethylbutane



2,3-Dimethylbutane


2,3-Dimethyl-2,3-butanediol


2,3-Dimethyl-2-butanethiol


2,2-Dimethylbutanoic acid


2,2-Dimethyl-1-butanol



3,3-Dimethyl-1-butanol


2,3-Dimethyl-2-butanol


3,3-Dimethyl-2-butanol, (±)

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
3993	3,3-Dimethyl-2-butanone	Pinacolone	$C_6H_{12}O$	75-97-8	100.158	liq	-52.5	106.1	0.7229^{25}	1.3952^{20}	sl H_2O; s EtOH, eth, ace, ctc
3994	3,3-Dimethylbutanoyl chloride		$C_6H_{11}ClO$	7065-46-5	134.603			130; 68^{100}	0.969^{20}	1.4210^{20}	vs eth
3995	2,3-Dimethyl-1-butene		C_6H_{12}	563-78-0	84.159	liq	-157.3	55.6	0.6803^{20}	1.3995^{20}	i H_2O; s EtOH, eth, ace, ctc, CS_2
3996	3,3-Dimethyl-1-butene		C_6H_{12}	558-37-2	84.159	liq	-115.2	41.2	0.6529^{20}	1.3763^{20}	i H_2O; s EtOH, eth, ctc, chl
3997	2,3-Dimethyl-2-butene		C_6H_{12}	563-79-1	84.159	liq	-74.19	73.3	0.7080^{20}	1.4122^{20}	i H_2O; s EtOH, eth, ace, chl
3998	*N*-(1,3-Dimethylbutyl)-*N'*-phenyl-1,4-benzenediamine		$C_{18}H_{24}N_2$	793-24-8	268.397		46	164^{1}			
3999	3,3-Dimethyl-1-butyne	*tert*-Butylacetylene	C_6H_{10}	917-92-0	82.143	liq	-78.2	37.7	0.6623^{25}	1.3736^{20}	
4000	Dimethyl 2-butynedioate		$C_6H_6O_4$	762-42-5	142.110			dec 197; 98^{20}	1.1564^{20}	1.4434^{20}	s EtOH, eth, ctc
4001	Dimethyl cadmium		C_2H_6Cd	506-82-1	142.480		-4.5	105.5 (exp 150)	1.9846^{18}	1.5488	s peth
4002	Dimethylcarbamic chloride	Dimethylcarbamoyl chloride	C_3H_6ClNO	79-44-7	107.539	liq	-33	167	1.168^{25}	1.4540^{20}	
4003	Dimethylcarbamothioic chloride		C_3H_6ClNS	16420-13-6	123.605	pr	42.5	98^{10}			vs eth; s chl, peth
4004	Dimethyl carbate		$C_{11}H_{14}O_4$	39589-98-5	210.227	cry	38	$137^{12.5}$	1.164^{21}	1.4852^{20}	i H_2O
4005	Dimethyl carbonate	Methyl carbonate	$C_3H_6O_3$	616-38-6	90.078		0.5	90.5	1.0636^{25}	1.3687^{20}	i H_2O; s EtOH, eth; sl ctc
4006	Dimethylcyanamide		$C_3H_6N_2$	1467-79-4	70.093			163.5		1.4089^{19}	vs ace, eth, EtOH
4007	2,3-Dimethyl-2,5-cyclohexadiene-1,4-dione		$C_8H_8O_2$	526-86-3	136.149	ye nd	55	sub			sl H_2O; s EtOH, eth, chl
4008	2,5-Dimethyl-2,5-cyclohexadiene-1,4-dione		$C_8H_8O_2$	137-18-8	136.149	ye nd (al)	126.0				sl H_2O, EtOH; s eth, bz, chl
4009	2,6-Dimethyl-2,5-cyclohexadiene-1,4-dione		$C_8H_8O_2$	527-61-7	136.149	ye nd	72.5	sub	1.0479^{28}		s chl
4010	1,1-Dimethylcyclohexane		C_8H_{16}	590-66-9	112.213	liq	-33.3	119.6	0.7809^{20}	1.4290^{20}	i H_2O; s EtOH, eth, ace, bz; msc ctc
4011	*cis*-1,2-Dimethylcyclohexane		C_8H_{16}	2207-01-4	112.213	liq	-49.8	129.8	0.7963^{20}	1.4360^{20}	i H_2O; s EtOH, bz, ctc; msc eth, ace
4012	*trans*-1,2-Dimethylcyclohexane		C_8H_{16}	6876-23-9	112.213	liq	-88.15	123.5	0.7760^{20}	1.4270^{20}	i H_2O; s EtOH, eth; msc ace, bz; vs lig
4013	*cis*-1,3-Dimethylcyclohexane		C_8H_{16}	638-04-0	112.213	liq	-75.53	120.1	0.7660^{20}	1.4229^{20}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
4014	*trans*-1,3-Dimethylcyclohexane		C_8H_{16}	2207-03-6	112.213	liq	-90.07	124.5	0.79^{15}	1.4284^{25}	
4015	*cis*-1,4-Dimethylcyclohexane		C_8H_{16}	624-29-3	112.213	liq	-87.39	124.4	0.7829^{20}	1.4230^{20}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
4016	*trans*-1,4-Dimethylcyclohexane		C_8H_{16}	2207-04-7	112.213	liq	-36.93	119.4	0.77^{15}	1.4185^{25}	i H_2O
4017	Dimethyl *trans*-1,4-cyclohexanedicarboxylate		$C_{10}H_{16}O_4$	3399-22-2	200.232	ndl (eth)	71				s eth
4018	5,5-Dimethyl-1,3-cyclohexanedione	5,5-Dimethyldihydroresorcinol	$C_8H_{12}O_2$	126-81-8	140.180	nd (w)	150 dec				sl H_2O, eth; s ace, ctc; vs chl, HOAc
4019	*N*,α-Dimethylcyclohexaneethanamine	Propylhexedrine	$C_{10}H_{21}N$	101-40-6	155.281			205; 82^{10}	0.8501^{20}	1.4600^{20}	vs EtOH
4020	3,3-Dimethylcyclohexanol		$C_8H_{16}O$	767-12-4	128.212		11.5	185; 99.5^{35}	0.9128^{14}	1.4606^{15}	
4021	2,2-Dimethylcyclohexanone		$C_8H_{14}O$	1193-47-1	126.196	liq	-20.5	172	0.9145^{20}	1.4486^{20}	
4022	2,6-Dimethylcyclohexanone		$C_8H_{14}O$	2816-57-1	126.196			175	0.925^{25}	1.4460^{20}	
4023	3,3-Dimethylcyclohexanone		$C_8H_{14}O$	2979-19-3	126.196			180; 72^{25}	0.909^{15}	1.4482^{17}	
4024	4,4-Dimethylcyclohexanone		$C_8H_{14}O$	4255-62-3	126.196		39	73^{14}	0.932^{20}	1.4537^{24}	
4025	1,2-Dimethylcyclohexene		C_8H_{14}	1674-10-8	110.197	liq	-84.1	138	0.8220^{25}	1.4620^{20}	
4026	1,3-Dimethylcyclohexene		C_8H_{14}	2808-76-6	110.197			127	0.799^{25}	1.449^{20}	
4027	3,5-Dimethyl-2-cyclohexen-1-one		$C_8H_{12}O$	1123-09-7	124.180			208.5	0.9400^{20}	1.4812^{20}	s EtOH, eth
4028	1,1-Dimethylcyclopentane		C_7H_{14}	1638-26-2	98.186	liq	-69.8	87.5	0.7499^{25}	1.4136^{20}	
4029	*cis*-1,2-Dimethylcyclopentane		C_7H_{14}	1192-18-3	98.186	liq	-54	99.5	0.7680^{25}	1.4222^{20}	
4030	*trans*-1,2-Dimethylcyclopentane		C_7H_{14}	822-50-4	98.186	liq	-117.6	91.9	0.7468^{25}	1.4120^{20}	
4031	*cis*-1,3-Dimethylcyclopentane		C_7H_{14}	2532-58-3	98.186	liq	-133.7	90.8	0.7402^{25}	1.4089^{20}	
4032	*trans*-1,3-Dimethylcyclopentane		C_7H_{14}	1759-58-6	98.186	liq	-134	91.7	0.7443^{25}	1.4107^{20}	
4033	*N*,α-Dimethylcyclopentaneethanamine	Cyclopentamine	$C_9H_{19}N$	102-45-4	141.254			171		1.4500^{20}	
4034	1,2-Dimethylcyclopentene		C_7H_{12}	765-47-9	96.170	liq	-90.4	105.8	0.7928^{25}	1.4448^{20}	
4035	1,5-Dimethylcyclopentene		C_7H_{12}	16491-15-9	96.170	liq	-118	99	0.780^{20}	1.4331^{20}	
4036	1,1-Dimethylcyclopropane		C_5H_{10}	1630-94-0	70.133	vol liq or gas	-109	20.6	0.6604^{20}	1.3668^{20}	i H_2O; s EtOH; vs eth, sulf



3,3-Dimethyl-2-butanone


3,3-Dimethylbutanoyl chloride



2,3-Dimethyl-1-butene


3,3-Dimethyl-1-butene


2,3-Dimethyl-2-butene


N-(1,3-Dimethylbutyl)-*N*'-phenyl-1,4-benzenediamine



3,3-Dimethyl-1-butyne



Dimethyl 2-butynedioate


Dimethyl cadmium



Dimethylcarbamic chloride



Dimethylcarbamothioic chloride



Dimethyl carbate


Dimethyl carbonate


Dimethylcyanamide


2,3-Dimethyl-2,5-cyclohexadiene-1,4-dione


2,5-Dimethyl-2,5-cyclohexadiene-1,4-dione


2,6-Dimethyl-2,5-cyclohexadiene-1,4-dione



1,1-Dimethylcyclohexane



cis-1,2-Dimethylcyclohexane



trans-1,2-Dimethylcyclohexane



cis-1,3-Dimethylcyclohexane



trans-1,3-Dimethylcyclohexane



cis-1,4-Dimethylcyclohexane


trans-1,4-Dimethylcyclohexane



Dimethyl *trans*-1,4-cyclohexanedicarboxylate



5,5-Dimethyl-1,3-cyclohexanedione



N,α-Dimethylcyclohexaneethanamine


3,3-Dimethylcyclohexanol


2,2-Dimethylcyclohexanone



2,6-Dimethylcyclohexanone


3,3-Dimethylcyclohexanone


4,4-Dimethylcyclohexanone


1,2-Dimethylcyclohexene



1,3-Dimethylcyclohexene



3,5-Dimethyl-2-cyclohexen-1-one



1,1-Dimethylcyclopentane


cis-1,2-Dimethylcyclopentane


trans-1,2-Dimethylcyclopentane


cis-1,3-Dimethylcyclopentane


trans-1,3-Dimethylcyclopentane


N,α-Dimethylcyclopentaneethanamine


1,2-Dimethylcyclopentene



1,5-Dimethylcyclopentene



1,1-Dimethylcyclopropane

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4037	*cis*-1,2-Dimethylcyclopropane		C_5H_{10}	930-18-7	70.133	liq	-140.9	37.0	0.6889^{25}	1.3829^{20}	i H_2O; s EtOH; vs eth; sl ctc
4038	*trans*-1,2-Dimethylcyclopropane		C_5H_{10}	2402-06-4	70.133	vol liq or gas	-149.6	28.2	0.6648^{25}	1.3713^{20}	vs eth, EtOH
4039	Dimethyldecylamine	*N,N*-Dimethyl-1-decanamine	$C_{12}H_{27}N$	1120-24-7	185.349			234.5			
4040	Dimethyldiacetoxysilane	Bis(acetyloxy)dimethylsilane	$C_6H_{12}O_4Si$	2182-66-3	176.243	liq	-12.5	165	1.0540^{20}	1.4030^{20}	
4041	*trans*-Dimethyldiazene	Azomethane	$C_2H_6N_2$	4143-41-3	58.082	gas	-78	1.5	0.743^{0}	1.4199^{19}	vs ace, EtOH, eth; s ctc, hp
4042	2,2-Dimethyl-1,3-dioxane-4,6-dione	Meldrum's acid	$C_6H_8O_4$	2033-24-1	144.126		94				
4043	*cis*-3,6-Dimethyl-1,4-dioxane-2,5-dione		$C_6H_8O_4$	4511-42-6	144.126	orth (eth)	96.8	150^{25}			
4044	2,2-Dimethyl-1,3-dioxolane-4-methanol	Isopropylidene glycerol	$C_6H_{12}O_3$	100-79-8	132.157			82^{10}	1.064^{20}	1.4383^{20}	
4045	Dimethyldiphenoxysilane		$C_{14}H_{16}O_2Si$	3440-02-6	244.362		-23	131^{5}	1.0599^{25}	1.5330^{20}	
4046	2,3-Dimethyl-2,3-diphenylbutane	Dicumene	$C_{18}H_{22}$	1889-67-4	238.368	cry (MeOH)	119.5				
4047	3,3'-Dimethyldiphenylmethane 4,4'-diisocyanate		$C_{17}H_{14}N_2O_2$	139-25-3	278.305						s chl
4048	2,9-Dimethyl-4,7-diphenyl-1,10-phenanthroline		$C_{26}H_{20}N_2$	4733-39-5	360.450		280 dec				
4049	Dimethyldiphenylsilane		$C_{14}H_{16}Si$	778-24-5	212.363			277; 173^{45}	0.9867^{20}	1.5644^{20}	
4050	*N,N'*-Dimethyl-*N,N'*-diphenylurea		$C_{15}H_{16}N_2O$	611-92-7	240.300	pl (al)	122	350			vs H_2O, EtOH, ace; sl eth, bz, CS_2
4051	Dimethyl disulfide	Methyl disulfide	$C_2H_6S_2$	624-92-0	94.199	liq	-84.67	109.74	1.0625^{20}	1.5289^{20}	i H_2O; msc EtOH, eth
4052	*O,O*-Dimethyl dithiophosphate	*O,O*-Dimethyl phosphorodithionate	$C_2H_7O_2PS_2$	756-80-9	158.180	liq		56^{4}	1.29^{20}		
4053	*N,N*-Dimethyldodecylamine oxide		$C_{14}H_{31}NO$	1643-20-5	229.402	hyg nd (tol)	130.5				
4054	1,2-Dimethylenecyclohexane		C_8H_{12}	2819-48-9	108.181			127; 60^{90}	0.8361^{20}	1.4718^{25}	i H_2O; s EtOH, eth, bz, chl; vs ace
4055	*N,N*-Dimethyl-1,2-ethanediamine		$C_4H_{12}N_2$	108-00-9	88.151			104	0.803^{25}	1.4260^{20}	
4056	*N,N'*-Dimethyl-1,2-ethanediamine		$C_4H_{12}N_2$	110-70-3	88.151			120	0.828^{15}		s EtOH, eth, dil HCl
4057	*N,N*-Dimethylethanolamine	Deanol	$C_4H_{11}NO$	108-01-0	89.136	liq	-59	134	0.8866^{20}	1.4300^{20}	msc H_2O, EtOH, eth; s chl
4058	Dimethyl ether	Methyl ether	C_2H_6O	115-10-6	46.068	col gas	-141.5	-24.8			s H_2O, EtOH, eth, ace, chl; sl bz
4059	(1,1-Dimethylethoxy)benzene		$C_{10}H_{14}O$	6669-13-2	150.217	liq	-24	185.5	0.9214^{20}		
4060	[(1,1-Dimethylethoxy)methyl] oxirane		$C_7H_{14}O_2$	7665-72-7	130.185	liq	-70	152	0.898^{20}		
4061	*N,N*-Dimethylformamide	DMF	C_3H_7NO	68-12-2	73.094	liq	-60.48	153	0.9445^{25}	1.4305^{20}	msc H_2O, EtOH, eth, ace, bz; sl lig
4062	Dimethyl fumarate		$C_6H_8O_4$	624-49-7	144.126		103.5	193	1.37^{20}	1.4062^{111}	i H_2O; s ace, chl
4063	2,5-Dimethylfuran		C_6H_8O	625-86-5	96.127	liq	-62.8	93	0.8883^{20}	1.4363^{20}	i H_2O; s EtOH, eth, ace, bz, HOAc, chl
4064	3,4-Dimethyl-2,5-furandione		$C_6H_6O_3$	766-39-2	126.110	pl or lf (dil al)	96	223	1.107^{100}		sl H_2O; vs EtOH, eth, bz, chl
4065	Dimethyl germanium sulfide		C_2H_6GeS	16090-49-6	134.77	col cry	54.5	302			
4066	Dimethyl glutarate		$C_7H_{12}O_4$	1119-40-0	160.168	liq	-42.5	214; 109^{21}	1.0876^{20}	1.4242^{20}	vs EtOH, eth; s chl
4067	*N,N*-Dimethylglycine		$C_4H_9NO_2$	1118-68-9	103.120	hyg nd (PrOH)	185.5				vs H_2O, MeOH; s EtOH, eth, ace
4068	Dimethylglyoxime		$C_4H_8N_2O_2$	95-45-4	116.119	nd (to or dil al)	245.5	sub 234			i H_2O; vs EtOH, eth; sl bz, tol
4069	2,6-Dimethyl-1,5-heptadiene		C_9H_{16}	6709-39-3	124.223	liq	-70	143	0.7648^{25}		
4070	2,2-Dimethylheptane		C_9H_{20}	1071-26-7	128.255	liq	-113	132.7	0.7105^{20}	1.4016^{20}	i H_2O; s eth, ctc; vs ace, chl; msc bz
4071	2,3-Dimethylheptane		C_9H_{20}	3074-71-3	128.255	liq	-116	140.5	0.7260^{20}	1.4088^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, chl
4072	2,4-Dimethylheptane		C_9H_{20}	2213-23-2	128.255			132.9	0.7115^{25}	1.4034^{20}	i H_2O; msc EtOH, eth, ace, bz, chl, peth
4073	2,5-Dimethylheptane		C_9H_{20}	2216-30-0	128.255			136	0.7198^{20}	1.4033^{20}	vs ace, bz, eth, EtOH
4074	2,6-Dimethylheptane		C_9H_{20}	1072-05-5	128.255	liq	-102.9	135.2	0.7089^{20}	1.4011^{20}	sl chl
4075	3,3-Dimethylheptane		C_9H_{20}	4032-86-4	128.255			137.3	0.7254^{20}	1.4087^{20}	i H_2O; msc EtOH; s eth; vs ace, bz



cis-1,2-Dimethylcyclopropane



trans-1,2-Dimethylcyclopropane



Dimethyldecylamine



Dimethyldiacetoxysilane



trans-Dimethyldiazene



2,2-Dimethyl-1,3-dioxane-4,6-dione



cis-3,6-Dimethyl-1,4-dioxane-2,5-dione



2,2-Dimethyl-1,3-dioxolane-4-methanol



Dimethyldiphenoxysilane


2,3-Dimethyl-2,3-diphenylbutane


3,3'-Dimethyldiphenylmethane 4,4'-diisocyanate



2,9-Dimethyl-4,7-diphenyl-1,10-phenanthroline


Dimethyldiphenylsilane



N,N'-Dimethyl-*N,N'*-diphenylurea



Dimethyl disulfide



O,O-Dimethyl dithiophosphate


N,N-Dimethyldodecylamine oxide



1,2-Dimethylenecyclohexane



N,N-Dimethyl-1,2-ethanediamine


N,N'-Dimethyl-1,2-ethanediamine



N,N-Dimethylethanolamine



Dimethyl ether



(1,1-Dimethylethoxy)benzene


[(1,1-Dimethylethoxy)methyl]oxirane



N,N-Dimethylformamide



Dimethyl fumarate



2,5-Dimethylfuran



3,4-Dimethyl-2,5-furandione



Dimethyl germanium sulfide



Dimethyl glutarate



N,N-Dimethylglycine



Dimethylglyoxime



2,6-Dimethyl-1,5-heptadiene



2,2-Dimethylheptane


2,3-Dimethylheptane



2,4-Dimethylheptane



2,5-Dimethylheptane


2,6-Dimethylheptane



3,3-Dimethylheptane

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4076	3,4-Dimethylheptane		C_9H_{20}	922-28-1	128.255			140.6	0.7314^{20}	1.4108^{20}	i H_2O; s eth, ctc; vs ace, chl; msc bz
4077	3,5-Dimethylheptane		C_9H_{20}	926-82-9	128.255			136	0.7225^{20}	1.4083^{20}	i H_2O; s eth, ctc; vs ace, chl; msc bz
4078	4,4-Dimethylheptane		C_9H_{20}	1068-19-5	128.255			135.2	0.7221^{20}	1.4076^{20}	i H_2O; s eth, ctc; vs ace, chl; msc bz
4079	Dimethyl heptanedioate	Dimethyl pimelate	$C_9H_{16}O_4$	1732-08-7	188.221		-21	120^{10}, 80^{1}	1.0625^{20}	1.4309^{20}	sl H_2O; s EtOH, eth, bz
4080	2,6-Dimethyl-2-heptanol		$C_9H_{20}O$	13254-34-7	144.254			173	0.8186^{20}	1.4242^{20}	
4081	2,6-Dimethyl-4-heptanol	Diisobutylcarbinol	$C_9H_{20}O$	108-82-7	144.254			174.5	0.8114^{20}	1.4242^{20}	i H_2O; s EtOH, eth; sl ctc
4082	3,5-Dimethyl-4-heptanol		$C_9H_{20}O$	19549-79-2	144.254			186	0.836^{18}	1.4283^{20}	sl H_2O
4083	2,6-Dimethyl-4-heptanone	Diisobutyl ketone	$C_9H_{18}O$	108-83-8	142.238	liq	-41.5	169.4	0.8062^{20}	1.412^{21}	i H_2O; msc EtOH, eth; s ctc
4084	2,6-Dimethyl-5-heptenal		$C_9H_{16}O$	106-72-9	140.222	oil		120^{100}			
4085	*N*,6-Dimethyl-5-hepten-2-amine	Isometheptene	$C_9H_{19}N$	503-01-5	141.254			177			vs eth, EtOH
4086	2,5-Dimethyl-1,5-hexadiene		C_8H_{14}	627-58-7	110.197	liq	-75.6	114.3	0.743^{20}	1.43995^{21}	i H_2O; s ace, chl
4087	2,5-Dimethyl-2,4-hexadiene		C_8H_{14}	764-13-6	110.197		14	134.5	0.7577^{25}	1.4785^{20}	i H_2O; s EtOH, eth, bz, chl
4088	2,2-Dimethylhexane		C_8H_{18}	590-73-8	114.229	liq	-121.1	106.86	0.6953^{20}	1.3935^{20}	vs ace, bz, eth, EtOH
4089	2,3-Dimethylhexane		C_8H_{18}	584-94-1	114.229			115.62	0.6912^{25}	1.4011^{20}	vs ace, bz, EtOH, lig
4090	2,4-Dimethylhexane		C_8H_{18}	589-43-5	114.229			109.5	0.6962^{25}	1.3929^{25}	
4091	2,5-Dimethylhexane		C_8H_{18}	592-13-2	114.229	liq	-91	109.12	0.6901^{25}	1.3925^{20}	i H_2O; msc EtOH, ace, bz; s eth
4092	3,3-Dimethylhexane		C_8H_{18}	563-16-6	114.229	liq	-126.1	111.97	0.7100^{20}	1.4001^{20}	i H_2O; msc EtOH; vs eth, ace, bz
4093	3,4-Dimethylhexane		C_8H_{18}	583-48-2	114.229			117.73	0.7151^{25}	1.4041^{20}	i H_2O; s eth; msc EtOH, ace, bz
4094	2,5-Dimethyl-2,5-hexanediamine		$C_8H_{20}N_2$	23578-35-0	144.258			184; 63^{8}	0.8485^{15}	1.4459^{20}	
4095	2,5-Dimethyl-2,5-hexanediol	1,1,4,4-Tetramethyl-1,4-butanediol	$C_8H_{18}O_2$	110-03-2	146.228	pr (AcOEt) fl (peth)	88.50	214	0.898^{20}		s H_2O; vs EtOH, bz, chl
4096	2,2-Dimethyl-1-hexanol		$C_8H_{18}O$	2370-13-0	130.228			95^{29}			
4097	2,3-Dimethyl-1-hexene		C_8H_{16}	16746-86-4	112.213			110.5	0.7172^{25}	1.4113^{20}	
4098	5,5-Dimethyl-1-hexene		C_8H_{16}	7116-86-1	112.213			104	0.705^{25}	1.4049^{20}	
4099	2,3-Dimethyl-2-hexene		C_8H_{16}	7145-20-2	112.213	liq	-115.1	121.8	0.7366^{25}	1.4268^{20}	
4100	2,5-Dimethyl-2-hexene		C_8H_{16}	3404-78-2	112.213			112.2	0.7182^{20}	1.4140^{20}	
4101	*cis*-2,2-Dimethyl-3-hexene		C_8H_{16}	690-92-6	112.213	liq	-137.4	105.5	0.7086^{25}	1.4099^{20}	
4102	*trans*-2,2-Dimethyl-3-hexene		C_8H_{16}	690-93-7	112.213			100.8	0.6995^{25}	1.4063^{20}	
4103	3,5-Dimethyl-1-hexen-3-ol		$C_8H_{16}O$	3329-48-4	128.212			146.5	0.8382^{20}	1.4342^{20}	
4104	1-(1,5-Dimethyl-4-hexenyl)-4-methylbenzene	α-Curcumene	$C_{15}H_{22}$	644-30-4	202.336			140^{19}	0.8805^{20}	1.4989^{20}	i H_2O; s bz
4105	2,5-Dimethyl-3-hexyne-2,5-diol		$C_8H_{14}O_2$	142-30-3	142.196		95	205	0.947^{20}		s H_2O, chl; vs EtOH, eth, ace, bz
4106	1,1-Dimethylhydrazine		$C_2H_8N_2$	57-14-7	60.098	liq, fumes in air	-57.20	63.9	0.791^{22}	1.4075^{22}	vs H_2O, EtOH, eth, MeOH
4107	1,2-Dimethylhydrazine		$C_2H_8N_2$	540-73-8	60.098	fumes (air)	-8.9	81	0.8274^{20}	1.4209^{20}	msc H_2O, EtOH, eth
4108	1,2-Dimethylhydrazine dihydrochloride		$C_2H_{10}Cl_2N_2$	306-37-6	133.019	pr (w)	170 dec				vs H_2O, EtOH
4109	Dimethyl hydrogen phosphate	Dimethyl phosphate	$C_2H_7O_4P$	813-78-5	126.048			dec 174	1.3225^{20}	1.408^{25}	vs H_2O, ace, EtOH
4110	Dimethyl hydrogen phosphite		$C_2H_7O_3P$	868-85-9	110.049			170.5	1.2002^{20}	1.4036^{20}	s EtOH, py; sl ctc
4111	1,2-Dimethyl-1*H*-imidazole		$C_5H_8N_2$	1739-84-0	96.131			206	1.0051^{11}		vs H_2O, eth, EtOH
4112	2,4-Dimethyl-1*H*-imidazole		$C_5H_8N_2$	930-62-1	96.131		92	267			
4113	5,5-Dimethyl-2,4-imidazolidinedione		$C_5H_8N_2O_2$	77-71-4	128.130	pr (dil al)	178	sub			vs H_2O, EtOH, eth, ace, bz, chl; s DMSO
4114	1,1-Dimethylindan		$C_{11}H_{14}$	4912-92-9	146.229			191	0.919^{20}	1.5135^{25}	
4115	1,3-Dimethyl-1*H*-indole		$C_{10}H_{11}N$	875-30-9	145.201	nd	142	258.5			s eth
4116	2,3-Dimethyl-1*H*-indole		$C_{10}H_{11}N$	91-55-4	145.201		107.5	287			
4117	*N,N*-Dimethyl-1*H*-indole-3-ethanamine	*N,N*-Dimethyltryptamine	$C_{12}H_{16}N_2$	61-50-7	188.268		46				



3,4-Dimethylheptane


3,5-Dimethylheptane



4,4-Dimethylheptane




Dimethyl heptanedioate




2,6-Dimethyl-2-heptanol




2,6-Dimethyl-4-heptanol




3,5-Dimethyl-4-heptanol




2,6-Dimethyl-4-heptanone





2,6-Dimethyl-5-heptenal





N,6-Dimethyl-5-hepten-2-amine



2,5-Dimethyl-1,5-hexadiene



2,5-Dimethyl-2,4-hexadiene



2,2-Dimethylhexane



2,3-Dimethylhexane


2,4-Dimethylhexane



2,5-Dimethylhexane


3,3-Dimethylhexane



3,4-Dimethylhexane




2,5-Dimethyl-2,5-hexanediamine





2,5-Dimethyl-2,5-hexanediol





2,2-Dimethyl-1-hexanol



2,3-Dimethyl-1-hexene



5,5-Dimethyl-1-hexene


2,3-Dimethyl-2-hexene



2,5-Dimethyl-2-hexene



cis-2,2-Dimethyl-3-hexene


trans-2,2-Dimethyl-3-hexene



3,5-Dimethyl-1-hexen-3-ol


1-(1,5-Dimethyl-4-hexenyl)-4-methylbenzene




2,5-Dimethyl-3-hexyne-2,5-diol



1,1-Dimethylhydrazine



1,2-Dimethylhydrazine



1,2-Dimethylhydrazine dihydrochloride



Dimethyl hydrogen phosphate




Dimethyl hydrogen phosphite




1,2-Dimethyl-1*H*-imidazole




2,4-Dimethyl-1*H*-imidazole




5,5-Dimethyl-2,4-imidazolidinedione



1,1-Dimethylindan



1,3-Dimethyl-1*H*-indole




2,3-Dimethyl-1*H*-indole





N,*N*-Dimethyl-1*H*-indole-3-ethanamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4118	*N,N*-Dimethyl-1*H*-indole-3-methanamine	Gramine	$C_{11}H_{14}N_2$	87-52-5	174.242	nd or pl (ace)	138.5				i H_2O; s EtOH, eth, chl; i peth
4119	Dimethyl isophthalate		$C_{10}H_{10}O_4$	1459-93-4	194.184	nd(dil al)	67.5	282	1.194^{20}	1.5168^{20}	sl H_2O
4120	1,4-Dimethyl-7-isopropylazulene	Guaiazulene	$C_{15}H_{18}$	489-84-9	198.304	bl-viol pl (al)	31.5	167^{12}	0.973^{20}		s EtOH, eth, AcOEt
4121	1,6-Dimethyl-4-isopropylnaphthalene	Cadalene	$C_{15}H_{18}$	483-78-3	198.304			294; 149^{10}	0.9667^{25}	1.5785^{25}	vs oils
4122	2,4-Dimethyl-3-isopropylpentane		$C_{10}H_{22}$	13475-79-1	142.282	liq	-81.7	157.1	0.7545^{25}	1.4246^{20}	
4123	3,5-Dimethylisoxazole		C_5H_7NO	300-87-8	97.116			143	0.99^{25}	1.4421^{20}	
4124	Dimethylmagnesium	Magnesium dimethyl	C_2H_6Mg	2999-74-8	54.374	solid	220 dec	subl			
4125	Dimethyl maleate	Methyl *cis*-butenedioate	$C_6H_8O_4$	624-48-6	144.126	liq	-19	202	1.1606^{20}	1.4416^{20}	sl H_2O, lig; s eth, ctc
4126	Dimethyl malonate	Methyl malonate	$C_5H_8O_4$	108-59-8	132.116	liq	-61.9	181.4	1.528^{20}	1.4135^{20}	sl H_2O; msc EtOH; vs ace, bz; s chl
4127	Dimethylmalonic acid	Dimethylpropanedioc acid	$C_5H_8O_4$	595-46-0	132.116	pr (bz/peth)	192.5	subl			s hot H_2O
4128	Dimethyl mercury		C_2H_6Hg	593-74-8	230.66			93	3.17^{25}	1.5452^{20}	i H_2O; vs EtOH, eth
4129	Dimethyl *cis*-2-methyl-2-butenedioate	Dimethyl citraconate	$C_7H_{10}O_4$	617-54-9	158.152			210.5	1.1153^{20}	1.4473^{20}	vs ace, eth, EtOH
4130	Dimethyl methylenesuccinate		$C_7H_{10}O_4$	617-52-7	158.152	hyg mcl (MeOH)	38	208	1.1241^{18}	1.4457^{20}	s EtOH, eth, MeOH; vs ace
4131	Dimethyl methylmalonate		$C_6H_{10}O_4$	609-02-9	146.141			174	1.0977^{20}	1.4128^{20}	vs ace, eth, EtOH, chl
4132	Dimethyl methylphosphonate		$C_3H_9O_3P$	756-79-6	124.075			181; 79.5^{20}	1.1684^{20}	1.4099^{30}	s H_2O, EtOH, eth
4133	*trans*-2,2-Dimethyl-3-(2-methyl-1-propenyl) cyclopropanecarboxylic acid		$C_{10}H_{16}O_2$	4638-92-0	168.233	pr	20.0	245			vs eth, EtOH, chl
4134	Dimethyl 2-methylsuccinate		$C_7H_{12}O_4$	1604-11-1	160.168			196	1.076^{25}	1.4200^{20}	
4135	Dimethyl *p*-(methylthio)phenyl phosphate		$C_9H_{13}O_4PS$	3254-63-5	248.235	liq			1.273^{21}		sl H_2O; s ace, EtOH, diox, ctc, xyl
4136	2,6-Dimethylmorpholine		$C_6H_{13}NO$	141-91-3	115.173	liq	-88	146.6	0.9329^{20}	1.4460^{20}	msc H_2O, EtOH, bz, lig; s ace; sl chl
4137	Dimethyl morpholinophosphoramidate	Dimethyl 4-morpholinylphosphonate	$C_6H_{14}NO_4P$	597-25-1	195.153	liq		96^{1}			
4138	1,2-Dimethylnaphthalene		$C_{12}H_{12}$	573-98-8	156.223		0.8	266.5	1.0179^{20}	1.6166^{20}	i H_2O; s eth, bz
4139	1,3-Dimethylnaphthalene		$C_{12}H_{12}$	575-41-7	156.223	liq	-6	263	1.0144^{20}	1.6140^{20}	i H_2O; s eth, bz
4140	1,4-Dimethylnaphthalene		$C_{12}H_{12}$	571-58-4	156.223		7.6	268	1.0166^{20}	1.6127^{20}	i H_2O; vs EtOH; msc eth, ace, bz, ctc
4141	1,5-Dimethylnaphthalene		$C_{12}H_{12}$	571-61-9	156.223		82	265			i H_2O; vs bz, eth
4142	1,6-Dimethylnaphthalene		$C_{12}H_{12}$	575-43-9	156.223	liq	-16.9	264	1.0021^{20}	1.6166^{20}	i H_2O; s eth, bz
4143	1,7-Dimethylnaphthalene		$C_{12}H_{12}$	575-37-1	156.223	liq	-13.9	263	1.0115^{20}	1.6083^{20}	i H_2O; s eth, bz
4144	1,8-Dimethylnaphthalene		$C_{12}H_{12}$	569-41-5	156.223		65	270	1.003^{20}		i H_2O; s eth, bz
4145	2,3-Dimethylnaphthalene	Guajen	$C_{12}H_{12}$	581-40-8	156.223	lf (al)	105	268	1.003^{20}	1.5060^{20}	i H_2O; vs bz, eth
4146	2,6-Dimethylnaphthalene		$C_{12}H_{12}$	581-42-0	156.223		112	262	1.003^{20}		i H_2O
4147	2,7-Dimethylnaphthalene		$C_{12}H_{12}$	582-16-1	156.223		97	265	1.003^{20}		
4148	*N,N*-Dimethyl-1-naphthylamine		$C_{12}H_{13}N$	86-56-6	171.238	viol flr cry		250; 140^{13}	1.0423^{20}	1.624^{15}	i H_2O; s EtOH, eth, ctc
4149	*N,N*-Dimethyl-2-naphthylamine		$C_{12}H_{13}N$	2436-85-3	171.238	dk red nd	52.5	305	1.0279^{60}	1.6443^{53}	i H_2O; s EtOH, eth
4150	*N,N*-Dimethyl-2-nitroaniline		$C_8H_{10}N_2O_2$	610-17-3	166.177	ye-oran	-20	146^{20}	1.1794^{20}	1.6102^{20}	s H_2O, eth; vs EtOH, chl
4151	*N,N*-Dimethyl-3-nitroaniline		$C_8H_{10}N_2O_2$	619-31-8	166.177	red mcl pr (eth)	60.5	282.5	1.313^{17}		i H_2O; s EtOH, eth
4152	*N,N*-Dimethyl-4-nitroaniline		$C_8H_{10}N_2O_2$	100-23-2	166.177	ye nd (al)	164.5				i H_2O; s EtOH, eth, HOAc
4153	1,2-Dimethyl-3-nitrobenzene		$C_8H_9NO_2$	83-41-0	151.163	nd (al)	15	240	1.1402^{20}	1.5441^{20}	i H_2O; s EtOH, ctc
4154	1,2-Dimethyl-4-nitrobenzene	4-Nitro-*o*-xylene	$C_8H_9NO_2$	99-51-4	151.163	ye pr (al)	30.5	251; 143^{21}	1.112^{15}	1.5202^{20}	i H_2O; msc EtOH
4155	1,3-Dimethyl-2-nitrobenzene		$C_8H_9NO_2$	81-20-9	151.163		15	226	1.112^{15}	1.5202^{20}	i H_2O; vs EtOH; s ctc
4156	1,3-Dimethyl-5-nitrobenzene		$C_8H_9NO_2$	99-12-7	151.163	nd (al)	75	274			i H_2O; vs EtOH, eth
4157	1,4-Dimethyl-2-nitrobenzene		$C_8H_9NO_2$	89-58-7	151.163	pa ye liq	-25	240.5	1.132^{15}	1.5413^{20}	i H_2O; s EtOH
4158	2,4-Dimethyl-1-nitrobenzene		$C_8H_9NO_2$	89-87-2	151.163		9	247; 122^{18}	1.135^{15}	1.5473^{25}	i H_2O; s eth, ace, bz, chl
4159	1,2-Dimethyl-5-nitro-1*H*-imidazole	Dimetridazole	$C_5H_7N_3O_2$	551-92-8	141.129	nd (w)	138.5				vs eth, EtOH
4160	*N,N*-Dimethyl-4-[2-(4-nitrophenyl)ethenyl]aniline		$C_{16}H_{16}N_2O_2$	4584-57-0	268.310		258.3				

N,N-Dimethyl-1*H*-indole-3-methanamine


Dimethyl isophthalate



1,4-Dimethyl-7-isopropylazulene



1,6-Dimethyl-4-isopropylnaphthalene



2,4-Dimethyl-3-isopropylpentane


3,5-Dimethylisoxazole



Dimethylmagnesium



Dimethyl maleate



Dimethyl malonate


Dimethylmalonic acid



Dimethyl mercury



Dimethyl *cis*-2-methyl-2-butenedioate



Dimethyl methylenesuccinate



Dimethyl methylmalonate



Dimethyl methylphosphonate



trans-2,2-Dimethyl-3-(2-methyl-1-propenyl)cyclopropanecarboxylic acid



Dimethyl 2-methylsuccinate



Dimethyl *p*-(methylthio)phenyl phosphate



2,6-Dimethylmorpholine



Dimethyl morpholinophosphoramidate



1,2-Dimethylnaphthalene



1,3-Dimethylnaphthalene



1,4-Dimethylnaphthalene



1,5-Dimethylnaphthalene



1,6-Dimethylnaphthalene



1,7-Dimethylnaphthalene



1,8-Dimethylnaphthalene



2,3-Dimethylnaphthalene



2,6-Dimethylnaphthalene



2,7-Dimethylnaphthalene



N,N-Dimethyl-1-naphthylamine



N,N-Dimethyl-2-naphthylamine



N,N-Dimethyl-2-nitroaniline



N,N-Dimethyl-3-nitroaniline



N,N-Dimethyl-4-nitroaniline



1,2-Dimethyl-3-nitrobenzene



1,2-Dimethyl-4-nitrobenzene



1,3-Dimethyl-2-nitrobenzene


1,3-Dimethyl-5-nitrobenzene



1,4-Dimethyl-2-nitrobenzene



2,4-Dimethyl-1-nitrobenzene



1,2-Dimethyl-5-nitro-1*H*-imidazole



N,N-Dimethyl-4-[2-(4-nitrophenyl)ethenyl]aniline


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4161	*N*,4-Dimethyl-*N*-nitrosobenzenesulfonamide	*p*-Tolylsulfonylmethylnitrosamide	$C_8H_{10}N_2O_3S$	80-11-5	214.241	cry	60				i H_2O; vs EtOH, eth
4162	Dimethyl nonanedioate	Methyl azelate	$C_{11}H_{20}O_4$	1732-10-1	216.275		-0.8	156^{20}	1.0082^{20}	1.4367^{20}	i H_2O; s EtOH, ace, bz, ctc
4163	6,6-Dimethyl-2-norpinene-2-carboxaldehyde	Myrtenal	$C_{10}H_{14}O$	564-94-3	150.217	unstab oil		99^{15}			
4164	*cis*-3,7-Dimethyl-2,6-octadienal		$C_{10}H_{16}O$	106-26-3	152.233			120^{20}	0.8869^{20}	1.4869^{20}	i H_2O; msc EtOH, eth
4165	*trans*-3,7-Dimethyl-2,6-octadienal		$C_{10}H_{16}O$	141-27-5	152.233			229	0.8888^{20}	1.4898^{20}	i H_2O; msc EtOH, eth
4166	3,7-Dimethyl-1,6-octadiene	Citronellene	$C_{10}H_{18}$	2436-90-0	138.250				0.7601^{20}	1.4362^{20}	
4167	3,7-Dimethyl-2,6-octadienoic acid	Geranic acid	$C_{10}H_{16}O_2$	459-80-3	168.233	oil					
4168	*cis*-3,7-Dimethyl-2,6-octadien-1-ol	Nerol	$C_{10}H_{18}O$	106-25-2	154.249		<-15	225; 125^{25}	0.8756^{20}	1.4746^{20}	vs EtOH
4169	*cis*-3,7-Dimethyl-2,6-octadien-1-ol acetate		$C_{12}H_{20}O_2$	141-12-8	196.286			134^{25}, 93^{3}	0.905^{15}	1.452^{20}	
4170	*trans*-3,7-Dimethyl-2,6-octadien-1-ol formate		$C_{11}H_{18}O_2$	105-86-2	182.260			dec 229; 113^{25}	0.9086^{25}	1.4659^{20}	i H_2O; vs EtOH; s eth, ace
4171	2,2-Dimethyloctane		$C_{10}H_{22}$	15869-87-1	142.282			155	0.7208^{25}	1.4082^{20}	
4172	2,3-Dimethyloctane		$C_{10}H_{22}$	7146-60-3	142.282			164.3	0.7377^{20}	1.4146^{20}	
4173	2,4-Dimethyloctane		$C_{10}H_{22}$	4032-94-4	142.282			156	0.7226^{25}	1.4091^{20}	
4174	2,5-Dimethyloctane		$C_{10}H_{22}$	15869-89-3	142.282			158.5	0.7264^{25}	1.4112^{20}	
4175	2,6-Dimethyloctane		$C_{10}H_{22}$	2051-30-1	142.282			160.4	0.7313^{20}	1.4097^{20}	
4176	2,7-Dimethyloctane		$C_{10}H_{22}$	1072-16-8	142.282	liq	-54.9	159.9	0.7202^{25}	1.4086^{20}	s eth, HOAc
4177	3,4-Dimethyloctane		$C_{10}H_{22}$	15869-92-8	142.282			163.4	0.7410^{25}	1.4182^{20}	
4178	3,6-Dimethyloctane		$C_{10}H_{22}$	15869-94-0	142.282			160.8	0.7324^{25}	1.4139^{20}	
4179	Dimethyl octanedioate	Dimethyl suberate	$C_{10}H_{18}O_4$	1732-09-8	202.248	liq	-1.6	268	1.0217^{20}	1.4341^{20}	i H_2O; s EtOH, eth, ace; sl ctc
4180	3,7-Dimethyl-1,7-octanediol		$C_{10}H_{22}O_2$	107-74-4	174.281			265	0.937^{20}	1.4599^{20}	sl bz, tol
4181	2,2-Dimethyloctanoic acid		$C_{10}H_{20}O_2$	29662-90-6	172.265			140^{13}			
4182	2,2-Dimethyl-1-octanol		$C_{10}H_{22}O$	2370-14-1	158.281	liq		97	0.84^{20}		
4183	3,7-Dimethyl-1-octanol		$C_{10}H_{22}O$	106-21-8	158.281			212.5	0.832^{25}	1.438^{25}	s eth
4184	2,6-Dimethyl-2-octanol	Tetrahydromyrcenol	$C_{10}H_{22}O$	18479-57-7	158.281			80.5^{10}	0.8023^{25}	1.4220^{25}	
4185	3,6-Dimethyl-3-octanol		$C_{10}H_{22}O$	151-19-9	158.281	liq	-67.5	202.2	0.8347^{22}	1.4370^{20}	
4186	3,7-Dimethyl-3-octanol		$C_{10}H_{22}O$	78-69-3	158.281			205.1	0.826^{25}	1.433^{25}	
4187	*cis*-3,7-Dimethyl-1,3,6-octatriene	*cis*-β-Ocimene	$C_{10}H_{16}$	3338-55-4	136.234				0.799^{20}		
4188	*trans*-3,7-Dimethyl-1,3,6-octatriene	*trans*-β-Ocimene	$C_{10}H_{16}$	3779-61-1	136.234				0.799^{20}		
4189	3,7-Dimethyl-1,3,7-octatriene	α-Ocimene	$C_{10}H_{16}$	502-99-8	136.234			dec 177	0.8000^{20}	1.4862^{20}	i H_2O; s EtOH, eth, chl, HOAc
4190	*cis, cis*-2,6-Dimethyl-2,4,6-octatriene	*cis-allo*-Ocimene	$C_{10}H_{16}$	17202-20-9	136.234	liq					
4191	*trans,trans*-2,6-Dimethyl-2,4,6-octatriene	*trans-allo*-Ocimene	$C_{10}H_{16}$	3016-19-1	136.234	liq	-35.4	188; 91^{20}	0.8118^{20}	1.5446^{20}	
4192	3,7-Dimethyl-6-octenal	Citronellal	$C_{10}H_{18}O$	106-23-0	154.249	nd or orth cry		207.5	0.853^{20}	1.4473^{20}	sl H_2O; s EtOH
4193	3,7-Dimethyl-1-octene		$C_{10}H_{20}$	4984-01-4	140.266	col liq		154	0.7396^{20}	1.4212^{20}	
4194	3,7-Dimethyl-6-octenoic acid	Citronellic acid	$C_{10}H_{18}O_2$	502-47-6	170.249			$257; 157^{23}$	0.9234^{21}		
4195	3,7-Dimethyl-6-octen-1-ol, (*R*)	Citronellol, (+)	$C_{10}H_{20}O$	1117-61-9	156.265	oil		$224; 108^{10}$	0.8550^{20}	1.4565^{20}	sl H_2O; msc EtOH, eth
4196	3,7-Dimethyl-6-octen-1-ol, (*S*)	Citronellol, (-)	$C_{10}H_{20}O$	7540-51-4	156.265	oil		$224; 108^{10}$	0.859^{18}	1.4576^{18}	vs eth, EtOH
4197	3,7-Dimethyl-7-octen-1-ol, (*S*)	Rhodinol	$C_{10}H_{20}O$	6812-78-8	156.265			114^{12}	0.8549^{20}	1.4556^{20}	vs eth, EtOH
4198	3,7-Dimethyl-6-octen-3-ol		$C_{10}H_{20}O$	18479-51-1	156.265			94^{14}	0.8695^{15}	1.4569^{15}	
4199	3,7-Dimethyl-6-octen-1-ol, acetate	Citronellol acetate	$C_{12}H_{22}O_2$	150-84-5	198.302			115^{10}			
4200	Dimethyloldihydroxyethyleneurea	4,5-Dihydroxy-1,3-bis(hydroxymethyl)-2-imidazolidinone	$C_5H_{10}N_2O_5$	1854-26-8	178.143	hyg cry					
4201	Dimethyl oxalate		$C_4H_6O_4$	553-90-2	118.089	mcl tab	54.8	163.5	1.1716^{60}	1.379^{82}	sl H_2O; s EtOH, eth, ace, chl
4202	5,5-Dimethyl-2,4-oxazolidinedione	Dimethadione	$C_5H_7NO_3$	695-53-4	129.115		76.5				
4203	3,3-Dimethyloxetane		$C_5H_{10}O$	6921-35-3	86.132			80.6	0.834^{25}	1.3965^{20}	
4204	3,3-Dimethyl-2-oxetanone		$C_5H_8O_2$	1955-45-9	100.117			58^{15}			
4205	2,2-Dimethyloxirane	2-Methyl-1,2-epoxypropane	C_4H_8O	558-30-5	72.106			52	0.8112^{20}	1.3712^{22}	s EtOH, eth
4206	*cis*-2,3-Dimethyloxirane		C_4H_8O	1758-33-4	72.106	liq	-80	60	0.8226^{25}	1.3802^{20}	vs eth, ace, bz
4207	*trans*-2,3-Dimethyloxirane		C_4H_8O	6189-41-9	72.106	liq	-85	56.5	0.8010^{25}	1.3736^{20}	vs eth, ace, bz
4208	3,3-Dimethyl-2-oxobutanoic acid		$C_6H_{10}O_3$	815-17-8	130.141		90.5	$189; 80^{15}$			sl H_2O; s eth, bz, chl, CS_2
4209	*N*-(1,1-Dimethyl-3-oxobutyl)-2-propenamide	Diacetone acrylamide	$C_9H_{15}NO_2$	2873-97-4	169.221						s chl
4210	Dimethyl 3-oxo-1,5-pentanedioate	Dimethyl 1,3-acetonedicarboxylate	$C_7H_{10}O_5$	1830-54-2	174.151			150^{25}, $77^{0.6}$	1.185^{25}	1.4434^{20}	



N,4-Dimethyl-*N*-nitrosobenzenesulfonamide



Dimethyl nonanedioate



6,6-Dimethyl-2-norpinene-2-carboxaldehyde



cis-3,7-Dimethyl-2,6-octadienal



trans-3,7-Dimethyl-2,6-octadienal



3,7-Dimethyl-1,6-octadiene



3,7-Dimethyl-2,6-octadienoic acid



cis-3,7-Dimethyl-2,6-octadien-1-ol



cis-3,7-Dimethyl-2,6-octadien-1-ol acetate



trans-3,7-Dimethyl-2,6-octadien-1-ol formate



2,2-Dimethyloctane



2,3-Dimethyloctane



2,4-Dimethyloctane



2,5-Dimethyloctane



2,6-Dimethyloctane



2,7-Dimethyloctane



3,4-Dimethyloctane



3,6-Dimethyloctane



Dimethyl octanedioate



3,7-Dimethyl-1,7-octanediol



2,2-Dimethyloctanoic acid



2,2-Dimethyl-1-octanol



3,7-Dimethyl-1-octanol



2,6-Dimethyl-2-octanol



3,6-Dimethyl-3-octanol



3,7-Dimethyl-3-octanol



cis-3,7-Dimethyl-1,3,6-octatriene



trans-3,7-Dimethyl-1,3,6-octatriene



3,7-Dimethyl-1,3,7-octatriene



cis, *cis*-2,6-Dimethyl-2,4,6-octatriene



trans,*trans*-2,6-Dimethyl-2,4,6-octatriene



3,7-Dimethyl-6-octenal



3,7-Dimethyl-1-octene



3,7-Dimethyl-6-octenoic acid



3,7-Dimethyl-6-octen-1-ol, (*R*)



3,7-Dimethyl-6-octen-1-ol, (*S*)



3,7-Dimethyl-7-octen-1-ol, (*S*)


3,7-Dimethyl-6-octen-3-ol


3,7-Dimethyl-6-octen-1-ol, acetate


Dimethyloldihydroxyethyleneurea


Dimethyl oxalate


5,5-Dimethyl-2,4-oxazolidinedione



3,3-Dimethyloxetane



3,3-Dimethyl-2-oxetanone



2,2-Dimethyloxirane


cis-2,3-Dimethyloxirane



trans-2,3-Dimethyloxirane



3,3-Dimethyl-2-oxobutanoic acid


N-(1,1-Dimethyl-3-oxobutyl)-2-propenamide



Dimethyl 3-oxo-1,5-pentanedioate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4211	2,4-Dimethyl-1,3-pentadiene		C_7H_{12}	1000-86-8	96.170	liq	-114	93.2	0.7343^{23}	1.4390^{23}	
4212	*N,N*-Dimethylpentanamide		$C_7H_{15}NO$	6225-06-5	129.200		-51	141^{100}	0.8962^{25}	1.4419^{25}	vs H_2O, eth, EtOH
4213	2,2-Dimethylpentane		C_7H_{16}	590-35-2	100.202	liq	-123.7	79.2	0.6739^{20}	1.3822^{20}	i H_2O; s EtOH, eth; msc ace, bz, hp, chl
4214	2,3-Dimethylpentane		C_7H_{16}	565-59-3	100.202			89.78	0.6908^{25}	1.3894^{25}	i H_2O; s EtOH, eth; msc ace, bz, chl
4215	2,4-Dimethylpentane		C_7H_{16}	108-08-7	100.202	liq	-119.2	80.49	0.6727^{20}	1.3815^{20}	i H_2O; s EtOH, eth; msc ace, bz, chl, hp
4216	3,3-Dimethylpentane		C_7H_{16}	562-49-2	100.202	liq	-134.4	86.06	0.6936^{20}	1.3909^{20}	i H_2O; s EtOH, eth; msc ace, bz, hp, chl
4217	3,3-Dimethylpentanedioic acid anhydride	Dihydro-4,4-dimethyl-2*H*-pyran-2,6(3*H*)-dione	$C_7H_{10}O_3$	4160-82-1	142.152		125.8	181^{25}, 156^{20}			
4218	3,3-Dimethylpentanedioic acid		$C_7H_{12}O_4$	4839-46-7	160.168	mcl pl, nd (bz)	103.5	126^{415}, 89^{2}	1.4278^{20}		vs H_2O, EtOH, eth; sl bz; i lig
4219	2,2-Dimethylpentanoic acid		$C_7H_{14}O_2$	1185-39-3	130.185	liq		98^{9}	0.9189^{20}		
4220	2,2-Dimethyl-1-pentanol		$C_7H_{16}O$	2370-12-9	116.201						s chl
4221	2,3-Dimethyl-2-pentanol		$C_7H_{16}O$	4911-70-0	116.201				0.804^{20}		sl H_2O
4222	2,4-Dimethyl-2-pentanol		$C_7H_{16}O$	625-06-9	116.201		<-20	133.1	0.8103^{20}	1.4172^{20}	sl H_2O; s EtOH, eth, ctc
4223	2,2-Dimethyl-3-pentanol		$C_7H_{16}O$	3970-62-5	116.201	liq	-2.5	135	0.8253^{20}	1.4223^{20}	i H_2O; s EtOH, eth
4224	2,3-Dimethyl-3-pentanol		$C_7H_{16}O$	595-41-5	116.201		<-30	139.7	0.833^{20}	1.4287^{20}	sl H_2O, bz; s EtOH, eth
4225	2,4-Dimethyl-3-pentanol		$C_7H_{16}O$	600-36-2	116.201		<-70	138.7	0.8288^{20}	1.4250^{20}	sl H_2O; s EtOH, eth
4226	4,4-Dimethyl-2-pentanone		$C_7H_{14}O$	590-50-1	114.185	liq	-64	126	0.809^{25}	1.4036^{20}	
4227	2,2-Dimethyl-3-pentanone		$C_7H_{14}O$	564-04-5	114.185	liq	-45	125.6	0.8125^{20}	1.4065^{20}	sl H_2O; s EtOH, eth, ace, chl
4228	2,4-Dimethyl-3-pentanone	Diisopropyl ketone	$C_7H_{14}O$	565-80-0	114.185	liq	-69	125.4	0.8108^{20}	1.3999^{20}	sl H_2O; msc EtOH, eth; s bz; sl ctc
4229	2,3-Dimethyl-1-pentene		C_7H_{14}	3404-72-6	98.186	liq	-134.3	84.3	0.7051^{20}	1.4033^{20}	i H_2O; msc EtOH, eth; vs dil sulf
4230	2,4-Dimethyl-1-pentene		C_7H_{14}	2213-32-3	98.186	liq	-124.1	81.6	0.6943^{20}	1.3986^{20}	i H_2O; msc EtOH, eth; s bz, ctc, chl
4231	3,3-Dimethyl-1-pentene		C_7H_{14}	3404-73-7	98.186	liq	-134.3	77.5	0.6974^{20}	1.3984^{20}	i H_2O; msc EtOH, eth; s bz, chl
4232	3,4-Dimethyl-1-pentene		C_7H_{14}	7385-78-6	98.186			80.8	0.6934^{25}	1.3992^{20}	
4233	4,4-Dimethyl-1-pentene		C_7H_{14}	762-62-9	98.186	liq	-136.6	72.5	0.6827^{20}	1.3818^{20}	i H_2O; msc EtOH, eth; s bz, ctc, chl
4234	2,3-Dimethyl-2-pentene		C_7H_{14}	10574-37-5	98.186	liq	-118.3	97.5	0.7277^{20}	1.4208^{20}	i H_2O; s EtOH, eth, bz, chl
4235	2,4-Dimethyl-2-pentene		C_7H_{14}	625-65-0	98.186	liq	-127.7	83.4	0.6954^{20}	1.4040^{20}	i H_2O; s EtOH, eth, bz, ctc
4236	*cis*-3,4-Dimethyl-2-pentene		C_7H_{14}	4914-91-4	98.186	liq	-113.4	89.3	0.7092^{25}	1.4104^{20}	
4237	*trans*-3,4-Dimethyl-2-pentene		C_7H_{14}	4914-92-5	98.186	liq	-124.2	91.5	0.7124^{25}	1.4128^{20}	
4238	*cis*-4,4-Dimethyl-2-pentene		C_7H_{14}	762-63-0	98.186	liq	-135.4	80.4	0.6951^{25}	1.4026^{20}	
4239	*trans*-4,4-Dimethyl-2-pentene		C_7H_{14}	690-08-4	98.186	liq	-115.2	76.7	0.6889^{20}	1.3982^{20}	i H_2O; s EtOH, eth, bz, chl
4240	4,4-Dimethyl-1-pentyne		C_7H_{12}	13361-63-2	96.170	liq	-75.7	76.1	0.7142^{20}	1.3983^{20}	vs bz, eth, chl
4241	4,4-Dimethyl-2-pentyne		C_7H_{12}	999-78-0	96.170	liq	-82.4	83	0.7176^{20}	1.4071^{20}	i H_2O; s eth, bz, chl; sl ctc
4242	Dimethylperoxide		$C_2H_6O_2$	690-02-8	62.068	vol liq or gas	-100	14	0.8677^{0}	1.3503^{0}	sl EtOH, eth; s tol, HOAc
4243	2,9-Dimethyl-1,10-phenanthroline	Neocuproine	$C_{14}H_{12}N_2$	484-11-7	208.258	cry, 1/2w (w, lig)	159.5				
4244	3,4-Dimethylphenol phosphate (3:1)		$C_{24}H_{27}O_4P$	3862-11-1	410.442		72	261^{7}			i H_2O; sl EtOH, chl, hx; s bz
4245	5-(2,5-Dimethylphenoxy)-2,2-dimethylpentanoic acid	Gemfibrozil	$C_{15}H_{22}O_3$	25812-30-0	250.334	cry	62	$159^{0.02}$			
4246	*N*-(2,4-Dimethylphenyl)acetamide		$C_{10}H_{13}NO$	2050-43-3	163.216	nd (al)	129.3	170^{10}			vs EtOH, chl
4247	1-[(2,4-Dimethylphenyl)azo]-2-naphthol	1-(2,4-Xylylazo)-2-naphthol	$C_{18}H_{16}N_2O$	3118-97-6	276.332	red nd (al)	166				vs eth, EtOH
4248	1-[(2,5-Dimethylphenyl)azo]-2-naphthol	1-(2,5-Xylylazo)-2-naphthol	$C_{18}H_{16}N_2O$	85-82-5	276.332	nd (al)	153				
4249	1-(2,4-Dimethylphenyl)ethanone	2,4-Dimethylacetophenone	$C_{10}H_{12}O$	89-74-7	148.201			228	1.0121^{15}	1.5340^{20}	vs eth, EtOH



2,4-Dimethyl-1,3-pentadiene





N,N-Dimethylpentanamide


2,2-Dimethylpentane



2,3-Dimethylpentane


2,4-Dimethylpentane



3,3-Dimethylpentane




3,3-Dimethylpentanedioic acid anhydride




3,3-Dimethylpentanedioic acid




2,2-Dimethylpentanoic acid




2,2-Dimethyl-1-pentanol




2,3-Dimethyl-2-pentanol




2,4-Dimethyl-2-pentanol




2,2-Dimethyl-3-pentanol




2,3-Dimethyl-3-pentanol




2,4-Dimethyl-3-pentanol




4,4-Dimethyl-2-pentanone




2,2-Dimethyl-3-pentanone





2,4-Dimethyl-3-pentanone



2,3-Dimethyl-1-pentene



2,4-Dimethyl-1-pentene


3,3-Dimethyl-1-pentene



3,4-Dimethyl-1-pentene


4,4-Dimethyl-1-pentene



2,3-Dimethyl-2-pentene



2,4-Dimethyl-2-pentene



cis-3,4-Dimethyl-2-pentene


trans-3,4-Dimethyl-2-pentene


cis-4,4-Dimethyl-2-pentene



trans-4,4-Dimethyl-2-pentene


4,4-Dimethyl-1-pentyne



4,4-Dimethyl-2-pentyne




Dimethylperoxide




2,9-Dimethyl-1,10-phenanthroline




3,4-Dimethylphenol phosphate (3:1)




5-(2,5-Dimethylphenoxy)-2,2-dimethylpentanoic acid




N-(2,4-Dimethylphenyl)acetamide



1-[(2,4-Dimethylphenyl)azo]-2-naphthol





1-[(2,5-Dimethylphenyl)azo]-2-naphthol





1-(2,4-Dimethylphenyl)ethanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4250	1-(2,5-Dimethylphenyl)ethanone	2,5-Dimethylacetophenone	$C_{10}H_{12}O$	2142-73-6	148.201	liq	-18.1	232.5	0.9963^{19}	1.5291^{20}	i H_2O; vs EtOH, eth, bz, CS_2
4251	1-(3,4-Dimethylphenyl)ethanone	3,4-Dimethylacetophenone	$C_{10}H_{12}O$	3637-01-2	148.201	liq	-1.5	246.5	1.0090^{14}	1.5413^{15}	i H_2O; vs EtOH, eth, bz; s ctc, HOAc
4252	4,4-Dimethyl-1-phenyl-1-penten-3-one		$C_{13}H_{16}O$	538-44-3	188.265		43	154^{25}	0.9508^{46}	1.5523^{25}	
4253	2,2-Dimethyl-1-phenyl-1-propanone		$C_{11}H_{14}O$	938-16-9	162.228			220	0.963^{26}	1.5086^{19}	s ace
4254	3,5-Dimethyl-1-phenyl-1*H*-pyrazole		$C_{11}H_{12}N_2$	1131-16-4	172.226			$272; 145^{12.5}$	1.0566^{20}	1.5738^{19}	vs eth, EtOH, chl
4255	4,4-Dimethyl-1-phenyl-3-pyrazolidinone	4,4-Dimethylphenidone	$C_{11}H_{14}N_2O$	2654-58-2	190.241		176				
4256	*N,N*-Dimethyl-γ-phenyl-2-pyridinepropanamine	Pheniramine	$C_{16}H_{20}N_2$	86-21-5	240.343			$181^{13}, 135^{0.5}$	1.0081^{25}	1.5519^{25}	vs bz, eth, EtOH, chl
4257	1,3-Dimethyl-3-phenyl-2,5-pyrrolidinedione	Methsuximide	$C_{12}H_{13}NO_2$	77-41-8	203.237		52.5	$121^{0.1}$			
4258	Dimethylphenylsilane		$C_8H_{12}Si$	766-77-8	136.267			156.5	0.8891^{20}	1.4995^{20}	i H_2O
4259	*N,N*-Dimethyl-*N'*-phenylurea	Fenuron	$C_9H_{12}N_2O$	101-42-8	164.203	cry (hx)	132				
4260	Dimethylphosphine		C_2H_7P	676-59-5	62.051	vol liq or gas		25			i H_2O; s EtOH, eth
4261	Dimethylphosphinic acid		$C_2H_7O_2P$	3283-12-3	94.050	cry (bz)	92	377			vs H_2O, EtOH, eth; s bz
4262	*O,O*-Dimethyl phosphorochloridothioate	Dimethyl chlorothiophosphate	$C_2H_6ClO_2PS$	2524-03-0	160.560	hyg liq		68^{12}	1.322	1.4820^{20}	
4263	Dimethyl phthalate		$C_{10}H_{10}O_4$	131-11-3	194.184	pa ye	5.5	283.7	1.1905^{20}	1.5138^{20}	i H_2O; msc EtOH, eth; s bz; sl ctc
4264	1,4-Dimethylpiperazine		$C_6H_{14}N_2$	106-58-1	114.188	liq	-0.59	131	0.8600^{20}	1.4474^{20}	vs H_2O, EtOH, eth
4265	*cis*-2,5-Dimethylpiperazine		$C_6H_{14}N_2$	6284-84-0	114.188	orth bipym nd or pr (chl)	114	162		1.4720^{20}	vs H_2O, EtOH, chl; sl eth, bz
4266	1,2-Dimethylpiperidine, (±)		$C_7H_{15}N$	2512-81-4	113.201			127.5	0.824^{15}	1.4395^{20}	vs H_2O, eth, EtOH
4267	2,6-Dimethylpiperidine		$C_7H_{15}N$	504-03-0	113.201			127	0.8158^{25}	1.4377^{20}	msc H_2O, EtOH, eth; sl ctc; s acid
4268	3,5-Dimethylpiperidine	3,5-Lupetidine	$C_7H_{15}N$	35794-11-7	113.201			144	0.853^{25}	1.4454^{20}	
4269	2,2-Dimethylpropanal	Pivaldehyde	$C_5H_{10}O$	630-19-3	86.132		6	77.5	0.7923^{17}	1.3791^{20}	s EtOH, eth
4270	2,2-Dimethylpropanamide		$C_5H_{11}NO$	754-10-9	101.147						s tfa
4271	*N,N*-Dimethylpropanamide		$C_5H_{11}NO$	758-96-3	101.147	liq	-45	175	0.9269^{20}		
4272	*N,N*-Dimethyl-1-propanamine	Dimethylpropylamine	$C_5H_{13}N$	926-63-6	87.164			66	0.7152^{20}	1.3860^{20}	vs bz, eth, EtOH
4273	*N,N*-Dimethyl-1,3-propanediamine		$C_5H_{14}N_2$	109-55-7	102.178			132	0.8272^{20}		
4274	2,2-Dimethyl-1,3-propanediol	Neopentyl glycol	$C_5H_{12}O_2$	126-30-7	104.148	nd (bz)	129.13	208			s H_2O, bz, chl; vs EtOH, eth
4275	2,2-Dimethylpropanenitrile	*tert*-Butyl cyanide	C_5H_9N	630-18-2	83.132		15	106.1	0.7586^{25}	1.3774^{20}	
4276	2,2-Dimethyl-1-propanethiol	Neopentyl mercaptan	$C_5H_{12}S$	1679-08-9	104.214	liq		103.7			
4277	2,2-Dimethylpropanoic acid	Trimethylacetic acid	$C_5H_{10}O_2$	75-98-9	102.132	nd	35	164	0.905^{50}	1.3931^{30}	sl H_2O; vs EtOH, eth
4278	2,2-Dimethyl-1-propanol	Neopentyl alcohol	$C_5H_{12}O$	75-84-3	88.148		52.5	113.5	0.812^{20}		sl H_2O; vs EtOH, eth; s ctc
4279	2,2-Dimethylpropanoyl chloride	Pivalic acid chloride	C_5H_9ClO	3282-30-2	120.577			107	1.003^{20}	1.4139^{20}	vs eth
4280	*N,N*-Dimethyl-2-propenamide	*N,N*-Dimethylacrylamide	C_5H_9NO	2680-03-7	99.131	liq		81^{20}	0.962^{25}	1.4730^{20}	
4281	2,2-Dimethylpropylamine	2,2-Dimethyl-1-propanamine	$C_5H_{13}N$	5813-64-9	87.164			82	0.7455^{20}	1.4023^{20}	vs eth
4282	(1,1-Dimethylpropyl)benzene		$C_{11}H_{16}$	2049-95-8	148.245			192.4	0.8748^{20}	1.4958^{20}	
4283	(2,2-Dimethylpropyl)benzene		$C_{11}H_{16}$	1007-26-7	148.245			185	0.8581^{18}	1.4884^{18}	
4284	4-(1,1-Dimethylpropyl) cyclohexanone		$C_{11}H_{20}O$	16587-71-6	168.276		96	$125^{16}, 109^{11}$	0.920^{25}	1.4677^{20}	
4285	1,1-Dimethylpropyl 3-methylbutanoate	*tert*-Pentyl isopentanoate	$C_{10}H_{20}O_2$	542-37-0	172.265			173.5	0.8729^{0}		vs EtOH
4286	2-(1,1-Dimethylpropyl)phenol		$C_{11}H_{16}O$	3279-27-4	164.244						sl ctc
4287	4-(1,1-Dimethylpropyl)phenol	*p-tert*-Pentylphenol	$C_{11}H_{16}O$	80-46-6	164.244		95	262.5			
4288	4,6-Dimethyl-2*H*-pyran-2-one		$C_7H_8O_2$	675-09-2	124.138	lf (eth)	51.5	245			vs H_2O, eth, EtOH
4289	2,6-Dimethyl-4*H*-pyran-4-one		$C_7H_8O_2$	1004-36-0	124.138	pl, nd (sub)	132	$251; 140^{25}$	0.9953^{137}		s H_2O, EtOH, eth, ace
4290	2,3-Dimethylpyrazine		$C_6H_8N_2$	5910-89-4	108.141			156	1.0281^{0}		s H_2O, EtOH, eth
4291	2,5-Dimethylpyrazine		$C_6H_8N_2$	123-32-0	108.141		15	155	0.9887^{20}	1.4980^{20}	msc H_2O, EtOH, eth; s ace, chl
4292	2,6-Dimethylpyrazine		$C_6H_8N_2$	108-50-9	108.141	pr	47.5	155.6	0.9647^{50}		s H_2O, EtOH, eth; sl ctc
4293	1,3-Dimethyl-1*H*-pyrazole		$C_5H_8N_2$	694-48-4	96.131			137	0.9561^{17}	1.4734^{15}	vs H_2O



1-(2,5-Dimethylphenyl)ethanone



1-(3,4-Dimethylphenyl)ethanone



4,4-Dimethyl-1-phenyl-1-penten-3-one



2,2-Dimethyl-1-phenyl-1-propanone



3,5-Dimethyl-1-phenyl-1*H*-pyrazole


4,4-Dimethyl-1-phenyl-3-pyrazolidinone


N,N-Dimethyl-γ-phenyl-2-pyridinepropanamine


1,3-Dimethyl-3-phenyl-2,5-pyrrolidinedione



Dimethylphenylsilane



N,N-Dimethyl-*N'*-phenylurea



Dimethylphosphine


Dimethylphosphinic acid



O,O-Dimethyl phosphorochloridothioate



Dimethyl phthalate


1,4-Dimethylpiperazine



cis-2,5-Dimethylpiperazine



1,2-Dimethylpiperidine, (±)



2,6-Dimethylpiperidine



3,5-Dimethylpiperidine


2,2-Dimethylpropanal


2,2-Dimethylpropanamide


N,N-Dimethylpropanamide



N,N-Dimethyl-1-propanamine


N,N-Dimethyl-1,3-propanediamine


2,2-Dimethyl-1,3-propanediol



2,2-Dimethylpropanenitrile



2,2-Dimethyl-1-propanethiol



2,2-Dimethylpropanoic acid



2,2-Dimethyl-1-propanol



2,2-Dimethylpropanoyl chloride



N,N-Dimethyl-2-propenamide



2,2-Dimethylpropylamine



(1,1-Dimethylpropyl)benzene



(2,2-Dimethylpropyl)benzene



4-(1,1-Dimethylpropyl)cyclohexanone


1,1-Dimethylpropyl 3-methylbutanoate



2-(1,1-Dimethylpropyl)phenol



4-(1,1-Dimethylpropyl)phenol


4,6-Dimethyl-2*H*-pyran-2-one


2,6-Dimethyl-4*H*-pyran-4-one



2,3-Dimethylpyrazine



2,5-Dimethylpyrazine



2,6-Dimethylpyrazine



1,3-Dimethyl-1*H*-pyrazole


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4294	3,5-Dimethyl-1*H*-pyrazole		$C_5H_8N_2$	67-51-6	96.131	cry (peth, al)	107.5	218	0.8839^{16}		s H_2O, ace; vs EtOH, eth, bz, MeOH
4295	2,7-Dimethylpyrene		$C_{18}H_{14}$	15679-24-0	230.304		230				
4296	4,6-Dimethyl-2-pyridinamine		$C_7H_{10}N_2$	5407-87-4	122.167		61	235			
4297	*N,N*-Dimethyl-2-pyridinamine		$C_7H_{10}N_2$	5683-33-0	122.167		182	196	1.0149^{14}	1.5663^{20}	s EtOH, eth, bz
4298	*N,N*-Dimethyl-4-pyridinamine		$C_7H_{10}N_2$	1122-58-3	122.167	pl (eth)	114				vs H_2O, EtOH, bz, chl; s eth
4299	2,3-Dimethylpyridine	2,3-Lutidine	C_7H_9N	583-61-9	107.153			161.12	0.9319^{25}	1.5057^{20}	s H_2O, EtOH, eth
4300	2,4-Dimethylpyridine	2,4-Lutidine	C_7H_9N	108-47-4	107.153	liq	-64	158.38	0.9309^{20}	1.5010^{20}	vs H_2O, EtOH, eth; s ace
4301	2,5-Dimethylpyridine	2,5-Lutidine	C_7H_9N	589-93-5	107.153	liq	-16	156.98	0.9297^{20}	1.5006^{20}	sl H_2O; vs EtOH; msc eth; s ace
4302	2,6-Dimethylpyridine	2,6-Lutidine	C_7H_9N	108-48-5	107.153	liq	-6.1	144.01	0.9226^{20}	1.4953^{20}	msc H_2O; sl EtOH; s eth, ace, chl
4303	3,4-Dimethylpyridine	3,4-Lutidine	C_7H_9N	583-58-4	107.153	liq	-11	179.10	0.9281^{20}	1.5096^{20}	sl H_2O, ctc; s EtOH, eth, ace, chl
4304	3,5-Dimethylpyridine	3,5-Lutidine	C_7H_9N	591-22-0	107.153	liq	-6.6	171.84	0.9419^{20}	1.5061^{20}	s H_2O, EtOH, eth, ace; sl ctc
4305	2,6-Dimethylpyridine-1-oxide		C_7H_9NO	1073-23-0	123.152	hyg	35	133^{22}	1.073^{25}	1.5706^{20}	
4306	4,6-Dimethyl-2-pyrimidinamine		$C_6H_9N_3$	767-15-7	123.155		153.5				s H_2O, EtOH, ace, bz; i eth; vs chl
4307	2,6-Dimethyl-4-pyrimidinamine	Kyanmethin	$C_6H_9N_3$	461-98-3	123.155	nd (al), pl (bz)	183	sub			sl H_2O, EtOH, bz, chl
4308	4,6-Dimethylpyrimidine		$C_6H_8N_2$	1558-17-4	108.141		25	159		1.4880^{20}	vs H_2O
4309	1,3-Dimethyl-2,4(1*H*,3*H*)-pyrimidinedione		$C_6H_8N_2O_2$	874-14-6	140.140		123.5				sl EtOH; s eth, chl
4310	2,4-Dimethylpyrrole		C_6H_9N	625-82-1	95.142	pa bl flr cry		168	0.9236^{20}	1.5048^{20}	sl H_2O; vs EtOH, eth, bz; s chl
4311	2,5-Dimethylpyrrole		C_6H_9N	625-84-3	95.142		6.5	171; 51^{8}	0.9353^{20}	1.5036^{20}	i H_2O; vs EtOH, eth
4312	1,2-Dimethylpyrrolidine		$C_6H_{13}N$	765-48-0	99.174	oil		99	0.799^{20}		s H_2O
4313	2,4-Dimethylquinoline	4-Methylquinaldine	$C_{11}H_{11}N$	1198-37-4	157.212	orth pr (eth)		265	1.0611^{15}	1.6075^{20}	sl H_2O, chl; vs EtOH, eth
4314	2,6-Dimethylquinoline		$C_{11}H_{11}N$	877-43-0	157.212	orth pr (eth)	60	266.5			sl H_2O, EtOH, eth, chl; vs bz
4315	2,7-Dimethylquinoline	*m*-Toluquinaldine	$C_{11}H_{11}N$	93-37-8	157.212		61	264.5			sl H_2O; s EtOH, eth, chl
4316	2,3-Dimethylquinoxaline		$C_{10}H_{10}N_2$	2379-55-7	158.199	nd (w+3, ace)	106				s EtOH, eth, ace, bz, chl, acid
4317	Dimethyl sebacate		$C_{12}H_{22}O_4$	106-79-6	230.301	lo pr	38	175^{20}, 144^{5}	0.9882^{28}	1.4355^{28}	i H_2O; s EtOH, eth, ace, ctc
4318	Dimethyl selenide	Methyl selenide	C_2H_6Se	593-79-3	109.03			57	1.4077^{15}		vs eth, EtOH, chl
4319	Dimethylsilane	2-Silapropane	C_2H_8Si	1111-74-6	60.171	col gas	-150	-20	0.68^{-80}		
4320	Dimethylstearylamine	Dymanthine	$C_{20}H_{43}N$	124-28-7	297.562		22.9				
4321	Dimethyl succinate		$C_6H_{10}O_4$	106-65-0	146.141		19	196.4	1.1198^{20}	1.4197^{20}	sl H_2O, ctc; s EtOH, ace; vs eth
4322	Dimethylsulfamoyl chloride	Dimethylaminosulfonyl chloride	$C_2H_6ClNO_2S$	13360-57-1	143.593			80^{16}			
4323	Dimethyl sulfate		$C_2H_6O_4S$	77-78-1	126.132		-27	dec 188; 76^{15}	1.3322^{20}	1.3874^{20}	s H_2O, eth, bz, ctc; msc EtOH; i CS_2
4324	Dimethyl sulfide		C_2H_6S	75-18-3	62.134	liq	-98.24	37.33	0.8483^{20}	1.4438^{20}	sl H_2O; s EtOH, eth
4325	Dimethyl sulfite		$C_2H_6O_3S$	616-42-2	110.132			126	1.2129^{20}	1.4083^{20}	s H_2O, EtOH, eth
4326	2,4-Dimethylsulfolane		$C_6H_{12}O_2S$	1003-78-7	148.223	liq	-1.5	281	1.1362^{20}	1.4732^{20}	vs lig
4327	Dimethyl sulfone		$C_2H_6O_2S$	67-71-0	94.133	pr	108.9	238	1.1700^{110}	1.4226	s H_2O, EtOH, bz
4328	Dimethyl sulfoxide	DMSO	C_2H_6OS	67-68-5	78.133		17.89	189	1.1010^{25}	1.4793^{20}	s H_2O, EtOH, eth, ace, ctc, AcOEt
4329	Dimethyl *L*-tartrate	Dimethyl 2,3-dihydroxybutanedioate, [*R*-(*R**,*R**)]-	$C_6H_{10}O_6$	608-68-4	178.139	(i) cry (bz) (ii) cry (w)	50(form a); 61(form b)	280	1.306^{45}		vs H_2O, ace, eth, EtOH
4330	Dimethyl telluride		C_2H_6Te	593-80-6	157.67	pa ye		94			vs EtOH
4331	Dimethyl terephthalate		$C_{10}H_{10}O_4$	120-61-6	194.184		141	288	1.075^{141}		sl H_2O, EtOH, MeOH; s eth, chl
4332	Dimethyl tetrachloroterephthalate		$C_{10}H_6Cl_4O_4$	1861-32-1	331.965		155				
4333	2,7-Dimethylthiachromine-8-ethanol		$C_{12}H_{14}N_4OS$	92-35-3	262.330	ye pr (chl)	228.8	sub			s H_2O, MeOH; sl EtOH, eth, ace, chl


3,5-Dimethyl-1*H*-pyrazole


2,7-Dimethylpyrene



4,6-Dimethyl-2-pyridinamine



N,*N*-Dimethyl-2-pyridinamine


N,*N*-Dimethyl-4-pyridinamine



2,3-Dimethylpyridine



2,4-Dimethylpyridine



2,5-Dimethylpyridine



2,6-Dimethylpyridine


3,4-Dimethylpyridine



3,5-Dimethylpyridine



2,6-Dimethylpyridine-1-oxide



4,6-Dimethyl-2-pyrimidinamine


2,6-Dimethyl-4-pyrimidinamine



4,6-Dimethylpyrimidine



1,3-Dimethyl-2,4(1*H*,3*H*)-pyrimidinedione



2,4-Dimethylpyrrole



2,5-Dimethylpyrrole



1,2-Dimethylpyrrolidine


2,4-Dimethylquinoline


2,6-Dimethylquinoline



2,7-Dimethylquinoline



2,3-Dimethylquinoxaline


Dimethyl sebacate



Dimethyl selenide


Dimethylsilane



Dimethylstearylamine



Dimethyl succinate


Dimethylsulfamoyl chloride


Dimethyl sulfate



Dimethyl sulfide



Dimethyl sulfite



2,4-Dimethylsulfolane



Dimethyl sulfone



Dimethyl sulfoxide


Dimethyl *L*-tartrate



Dimethyl telluride



Dimethyl terephthalate


Dimethyl tetrachloroterephthalate


2,7-Dimethylthiachromine-8-ethanol

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4334	2,5-Dimethyl-1,3,4-thiadiazole		$C_4H_6N_2S$	27464-82-0	114.169		65	202.5			sl H_2O, EtOH, eth
4335	2,7-Dimethylthianthrene	Mesulphen	$C_{14}H_{12}S_2$	135-58-0	244.375	nd (HOAc,al)	123	184^{3}			vs ace, eth, peth, chl
4336	2,4-Dimethylthiazole		C_5H_7NS	541-58-2	113.182			146; 71^{50}	1.0562^{15}	1.5091^{20}	sl H_2O; s EtOH, eth, chl
4337	4,5-Dimethylthiazole		C_5H_7NS	3581-91-7	113.182		83.5	158	1.0699^{20}		vs eth, EtOH
4338	*N,N*-Dimethylthioacetamide		C_4H_9NS	631-67-4	103.186		74.5				
4339	Dimethyl thiodipropionate		$C_8H_{14}O_4S$	4131-74-2	206.260			162^{18}, 148^{18}	1.1559^{20}	1.4740^{20}	
4340	2,3-Dimethylthiophene		C_6H_8S	632-16-6	112.193	liq	-49	141.6	1.0021^{20}	1.5192^{20}	i H_2O; vs EtOH, eth; s bz
4341	2,4-Dimethylthiophene		C_6H_8S	638-00-6	112.193			140.7	0.9938^{20}	1.5104^{20}	i H_2O; s EtOH, eth, bz
4342	2,5-Dimethylthiophene		C_6H_8S	638-02-8	112.193	liq	-62.6	136.5	0.9850^{20}	1.5129^{20}	i H_2O; s EtOH, eth, bz
4343	3,4-Dimethylthiophene		C_6H_8S	632-15-5	112.193			145	0.993^{25}	1.5206^{20}	i H_2O; s EtOH; vs eth
4344	*N,N*-Dimethylthiourea		$C_3H_8N_2S$	6972-05-0	104.174	cry (w)	161.5				
4345	*N,N'*-Dimethylthiourea		$C_3H_8N_2S$	534-13-4	104.174	hyg pl	62				vs H_2O, EtOH, ace; sl eth, bz; i CS_2
4346	2,6-Dimethyl-4-tridecylmorpholine	Tridemorph	$C_{19}H_{39}NO$	24602-86-6	297.519			141$^{1.3}$	0.86		
4347	*N,N*-Dimethyl-*N'*-[3-(trifluoromethyl)phenyl]urea	Fluometuron	$C_{10}H_{11}F_3N_2O$	2164-17-2	232.201		164				vs ace, EtOH
4348	Dimethyl trisulfide		$C_2H_6S_3$	3658-80-8	126.264			41^{6}			
4349	6,10-Dimethyl-3,5,9-undecatrien-2-one	Pseudoionone	$C_{13}H_{20}O$	141-10-6	192.297	pa ye oil		144^{12}	0.8984^{20}	1.5335^{20}	s EtOH, eth, chl, MeOH
4350	*N,N*-Dimethylurea		$C_3H_8N_2O$	598-94-7	88.108	mcl pr (al, chl)	182.1		1.2555^{25}		s H_2O; sl EtOH, tfa; i eth
4351	*N,N'*-Dimethylurea		$C_3H_8N_2O$	96-31-1	88.108	orth bipym (chl-eth)	106.6	269	1.142^{25}		vs H_2O, EtOH; i eth; sl chl
4352	Dimethyl zinc		C_2H_6Zn	544-97-8	95.478	liq, ign in air	-43.0	46	1.386^{10}		s eth; msc peth
4353	Dimetilan		$C_{10}H_{16}N_4O_3$	644-64-4	240.259	col solid	69	205^{13}			s H_2O, chl, EtOH, ace, xyl
4354	Dimorpholamine		$C_{20}H_{38}N_4O_4$	119-48-2	398.541	cry (peth)	41.5	229$^{0.4}$			vs H_2O
4355	*N,N'*-Di-2-naphthyl-1,4-benzenediamine		$C_{26}H_{20}N_2$	93-46-9	360.450		235				i EtOH, eth, bz
4356	Di-2-naphthyl disulfide		$C_{20}H_{14}S_2$	5586-15-2	318.455	nd	139.5		1.144^{145}	1.4555^{20}	i H_2O; vs EtOH, eth; i lig
4357	*N,N'*-Di-1-naphthylurea		$C_{21}H_{16}N_2O$	607-56-7	312.364	nd (py, HOAc)	296	sub			vs py
4358	Diniconazole		$C_{15}H_{17}Cl_2N_3O$	83657-24-3	326.221	cry	149				s H_2O, ace, MeOH, xyl
4359	Dinitramine		$C_{11}H_{13}F_3N_4O_4$	29091-05-2	322.241		98				
4360	2,3-Dinitroaniline		$C_6H_5N_3O_4$	602-03-9	183.122		128		1.646^{50}		i H_2O; s EtOH; sl eth
4361	2,4-Dinitroaniline		$C_6H_5N_3O_4$	97-02-9	183.122	ye nd (ace) grn ye tab (al)	180.0		1.615^{14}		i H_2O; sl EtOH, ace, HCl
4362	2,5-Dinitroaniline		$C_6H_5N_3O_4$	619-18-1	183.122	oran nd (al)	138.0				vs EtOH
4363	2,6-Dinitroaniline		$C_6H_5N_3O_4$	606-22-4	183.122	gold lf (HOAc) ye nd (al)	141.5				i H_2O, lig; sl EtOH; s eth, bz
4364	3,5-Dinitroaniline		$C_6H_5N_3O_4$	618-87-1	183.122	ye nd (dil al)	163		1.601^{50}		i H_2O; s EtOH, eth; sl ace, bz
4365	1,5-Dinitro-9,10-anthracenedione		$C_{14}H_6N_2O_6$	82-35-9	298.207	pa ye nd (xyl)	385	sub			i H_2O; sl EtOH, eth, bz; vs $PhNO_2$
4366	1,8-Dinitro-9,10-anthracenedione		$C_{14}H_6N_2O_6$	129-39-5	298.207		312				
4367	2,4-Dinitrobenzaldehyde		$C_7H_4N_2O_5$	528-75-6	196.117	pa ye pr (al), pl (bz)	72	200^{15}			sl H_2O, chl, lig; s EtOH, eth, bz
4368	3,5-Dinitrobenzamide	Nitromide	$C_7H_5N_3O_5$	121-81-3	211.132	lf (w)	184				vs H_2O
4369	1,2-Dinitrobenzene	*o*-Dinitrobenzene	$C_6H_4N_2O_4$	528-29-0	168.107	nd (bz), pl (al)	116.5	318; 194^{30}	1.3119^{120}	1.565^{17}	i H_2O; s EtOH, bz, chl, AcOEt; sl DMSO
4370	1,3-Dinitrobenzene	*m*-Dinitrobenzene	$C_6H_4N_2O_4$	99-65-0	168.107	orth pl (al)	90.3	291; 167^{14}	1.5751^{18}		sl H_2O; vs EtOH, ace, py; s eth, tol
4371	1,4-Dinitrobenzene	*p*-Dinitrobenzene	$C_6H_4N_2O_4$	100-25-4	168.107	nd (al)	173.5	297; 183^{34}	1.625^{18}		i H_2O; sl EtOH, chl; s ace, bz, tol
4372	2,4-Dinitro-1,3-benzenediol	2,4-Dinitroresorcinol	$C_6H_4N_2O_6$	519-44-8	200.105	ye lf (al)	147.5				sl H_2O, EtOH
4373	2,4-Dinitrobenzenesulfenyl chloride		$C_6H_3ClN_2O_4S$	528-76-7	234.617	ye pr (bz-peth)	99				vs bz, chl, HOAc; sl peth



2,5-Dimethyl-1,3,4-thiadiazole


2,7-Dimethylthianthrene


2,4-Dimethylthiazole



4,5-Dimethylthiazole


N,N-Dimethylthioacetamide



Dimethyl thiodipropionate



2,3-Dimethylthiophene



2,4-Dimethylthiophene



2,5-Dimethylthiophene



3,4-Dimethylthiophene



N,N-Dimethylthiourea



N,N'-Dimethylthiourea



2,6-Dimethyl-4-tridecylmorpholine


N,N-Dimethyl-*N'*-[3-(trifluoromethyl)phenyl]urea



Dimethyl trisulfide



6,10-Dimethyl-3,5,9-undecatrien-2-one



N,N-Dimethylurea



N,N'-Dimethylurea



Dimethyl zinc



Dimetilan



Dimorpholamine



N,N'-Di-2-naphthyl-1,4-benzenediamine



Di-2-naphthyl disulfide



N,N'-Di-1-naphthylurea



Diniconazole



Dinitramine



2,3-Dinitroaniline



2,4-Dinitroaniline



2,5-Dinitroaniline



2,6-Dinitroaniline



3,5-Dinitroaniline



1,5-Dinitro-9,10-anthracenedione



1,8-Dinitro-9,10-anthracenedione



2,4-Dinitrobenzaldehyde



3,5-Dinitrobenzamide


1,2-Dinitrobenzene



1,3-Dinitrobenzene



1,4-Dinitrobenzene



2,4-Dinitro-1,3-benzenediol



2,4-Dinitrobenzenesulfenyl chloride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4374	2,4-Dinitrobenzenesulfonic acid		$C_6H_4N_2O_7S$	89-02-1	248.170	nd (w+3)	108				vs H_2O, EtOH; sl eth; i bz, peth
4375	2,4-Dinitrobenzoic acid		$C_7H_4N_2O_6$	610-30-0	212.116	nd (w)	183		1.672^{20}		sl H_2O, EtOH, bz
4376	3,4-Dinitrobenzoic acid		$C_7H_4N_2O_6$	528-45-0	212.116	cry (dil al)	166				sl H_2O; vs EtOH, eth
4377	3,5-Dinitrobenzoic acid		$C_7H_4N_2O_6$	99-34-3	212.116	mcl pr (al)	205				sl H_2O; vs EtOH, HOAc
4378	3,5-Dinitrobenzoyl chloride		$C_7H_3ClN_2O_5$	99-33-2	230.562	ye nd (bz)	74	196^{12}			s eth, chl
4379	2,2'-Dinitro-1,1'-biphenyl		$C_{12}H_8N_2O_4$	2436-96-6	244.203	ye mcl pr or nd (al)	126	305	1.45^{25}		i H_2O; vs EtOH; s eth, bz; sl ace, lig
4380	4,4'-Dinitro-1,1'-biphenyl		$C_{12}H_8N_2O_4$	1528-74-1	244.203	nd (al)	242.3				i H_2O; sl EtOH; s bz, HOAc
4381	1,4-Dinitrobutane		$C_4H_8N_2O_4$	4286-49-1	148.118	pl (al)	33.5	176^{13}			i H_2O; sl EtOH; s eth, bz, MeOH
4382	4,4'-Dinitrodiphenylamine	4-Nitro-*N*-(4-nitrophenyl)aniline	$C_{12}H_9N_3O_4$	1821-27-8	259.217	ye nd(al)	217.5				i H_2O, tol; sl EtOH, bz; s ace, HOAc
4383	4,4'-Dinitrodiphenyl ether	Bis(4-nitrophenyl) ether	$C_{12}H_8N_2O_5$	101-63-3	260.202		146.0				i H_2O; sl EtOH, eth; s bz, HOAc
4384	4,4'-Dinitrodiphenyl sulfide	Bis(4-nitrophenyl) sulfide	$C_{12}H_8N_2O_4S$	1223-31-0	276.268	oran pl (HOAc)	160.5				i H_2O; sl EtOH; s con sulf
4385	1,1-Dinitroethane		$C_2H_4N_2O_4$	600-40-8	120.064	ye mcl (bz, MeOH)		185.5	1.349^{24}		sl H_2O; s EtOH, eth
4386	1,2-Dinitroethane		$C_2H_4N_2O_4$	7570-26-5	120.064		39.5	95^{5}	1.4597^{20}	1.4468^{20}	vs eth, EtOH
4387	Dinitromethane		$CH_2N_2O_4$	625-76-3	106.038	ye nd	<-15	exp 100			i H_2O; s EtOH, eth
4388	1,3-Dinitronaphthalene		$C_{10}H_6N_2O_4$	606-37-1	218.166	ye nd (bz, py-w)	148	sub			i H_2O; s EtOH, ace
4389	1,5-Dinitronaphthalene		$C_{10}H_6N_2O_4$	605-71-0	218.166	hex nd (ace, HOAc)	219	sub	1.5860^{20}		i H_2O; sl EtOH, ace; s bz, py; vs eth
4390	1,8-Dinitronaphthalene		$C_{10}H_6N_2O_4$	602-38-0	218.166	ye orth pl (chl)	173	dec 445			i H_2O; sl EtOH, bz; s ace, chl, py
4391	2,4-Dinitro-1-naphthol		$C_{10}H_6N_2O_5$	605-69-6	234.165	ye nd (al, chl)	138.8				
4392	2,3-Dinitrophenol		$C_6H_4N_2O_5$	66-56-8	184.106	ye nd (w)	144.5		1.681^{20}		sl H_2O, DMSO; vs EtOH, eth; s bz
4393	2,4-Dinitrophenol		$C_6H_4N_2O_5$	51-28-5	184.106	pa ye pl or lf (w)	114.8	sub	1.683^{24}		sl H_2O; s EtOH, eth, ace, bz, tol, chl, py
4394	2,5-Dinitrophenol		$C_6H_4N_2O_5$	329-71-5	184.106	ye mcl pr or nd (w,lig)	108				vs bz, eth
4395	2,6-Dinitrophenol		$C_6H_4N_2O_5$	573-56-8	184.106	pa ye orth nd or lf (dil al)	63.5				i H_2O; vs EtOH, eth; s bz, chl; sl ctc
4396	3,4-Dinitrophenol		$C_6H_4N_2O_5$	577-71-9	184.106	tcl nd (w)	134		1.672^{25}		vs bz, eth, EtOH
4397	2,4-Dinitrophenol, acetate		$C_8H_6N_2O_6$	4232-27-3	226.143	cry (MeOH)	72.5				
4398	4-[(2,4-Dinitrophenyl)amino] phenol		$C_{12}H_9N_3O_5$	119-15-3	275.216	red lf	195.5				s alk
4399	2,4-Dinitro-*N*-phenylaniline		$C_{12}H_9N_3O_4$	961-68-2	259.217	ye red nd (al)	157.8				i H_2O; s EtOH, ace; sl eth, bz, DMSO
4400	2,4-Dinitrophenyl dimethylcarbamodithioate		$C_9H_9N_3O_4S_2$	89-37-2	287.315		152.5		1.54^{20}		i H_2O; s EtOH, ace, bz
4401	(2,4-Dinitrophenyl)hydrazine		$C_6H_6N_4O_4$	119-26-6	198.137	blsh-red (al)	194				i H_2O; s EtOH; sl eth, bz, chl, DMSO
4402	1,1-Dinitropropane		$C_3H_6N_2O_4$	601-76-3	134.091	liq	-42	184	1.2610^{25}	1.4339^{20}	s alk
4403	1,3-Dinitropropane		$C_3H_6N_2O_4$	6125-21-9	134.091		-21.4	103^{1}	1.353^{26}	1.4654^{20}	i H_2O; s eth
4404	2,2-Dinitropropane		$C_3H_6N_2O_4$	595-49-3	134.091		53	185.5	1.30^{25}		sl H_2O
4405	2,2-Dinitro-1,3-propanediol		$C_3H_6N_2O_6$	2736-80-3	166.089	wh pl (bz)	142				
4406	1,6-Dinitropyrene		$C_{16}H_8N_2O_4$	42397-64-8	292.246		>300				
4407	1,8-Dinitropyrene		$C_{16}H_8N_2O_4$	42397-65-9	292.246		300				
4408	Dinitrosopentamethylenetetramine		$C_5H_{10}N_6O_2$	101-25-7	186.172	cry (MeOH)	207				
4409	1,4-Dinitrosopiperazine		$C_4H_8N_4O_2$	140-79-4	144.133	pa ye pl (w)	159.0				vs EtOH
4410	4,4'-Dinitro-2,2'-stilbenedisulfonic acid		$C_{14}H_{10}N_2O_{10}S_2$	128-42-7	430.366	cry (AcOH)	266				
4411	Dinobuton	Dessin	$C_{14}H_{18}N_2O_7$	973-21-7	326.302	ye cry (EtOH)	60				
4412	Dinocap		$C_{18}H_{24}N_2O_6$	6119-92-2	364.393			$136^{0.01}$			
4413	Dinonyl adipate		$C_{24}H_{46}O_4$	151-32-6	398.620			205^{1}			



2,4-Dinitrobenzenesulfonic acid



2,4-Dinitrobenzoic acid



3,4-Dinitrobenzoic acid



3,5-Dinitrobenzoic acid



3,5-Dinitrobenzoyl chloride



2,2'-Dinitro-1,1'-biphenyl



4,4'-Dinitro-1,1'-biphenyl



1,4-Dinitrobutane


4,4'-Dinitrodiphenylamine



4,4'-Dinitrodiphenyl ether



4,4'-Dinitrodiphenyl sulfide



1,1-Dinitroethane



1,2-Dinitroethane



Dinitromethane



1,3-Dinitronaphthalene



1,5-Dinitronaphthalene



1,8-Dinitronaphthalene



2,4-Dinitro-1-naphthol



2,3-Dinitrophenol



2,4-Dinitrophenol



2,5-Dinitrophenol



2,6-Dinitrophenol



3,4-Dinitrophenol



2,4-Dinitrophenol, acetate



4-[(2,4-Dinitrophenyl)amino]phenol


2,4-Dinitro-*N*-phenylaniline



2,4-Dinitrophenyl dimethylcarbamodithioate



(2,4-Dinitrophenyl)hydrazine



1,1-Dinitropropane



1,3-Dinitropropane



2,2-Dinitropropane



2,2-Dinitro-1,3-propanediol



1,6-Dinitropyrene



1,8-Dinitropyrene



Dinitrosopentamethylenetetramine


1,4-Dinitrosopiperazine



4,4'-Dinitro-2,2'-stilbenedisulfonic acid



Dinobuton



R = NO_2, R' = C_8H_{17}
and
R = C_8H_{17}, R' = NO_2
Dinocap



Dinonyl adipate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4414	Dinonyl ether		$C_{18}H_{38}O$	2456-27-1	270.494	liq		318	0.81	1.4356^{20}	
4415	Dinonyl phthalate		$C_{26}H_{42}O_4$	84-76-4	418.609			413			
4416	Dinoseb	Phenol, 2-(1-methylpropyl)-4,6-dinitro-	$C_{10}H_{12}N_2O_5$	88-85-7	240.212		40		1.265^{45}		
4417	Dioctadecylamine	Distearylamine	$C_{36}H_{75}N$	112-99-2	521.988		72.9	268^{2}			vs chl
4418	Dioctylamine	*N*-Octyl-1-octanamine	$C_{16}H_{35}N$	1120-48-5	241.456	nd	35.5	297.5	0.7963^{26}	1.4415^{26}	vs eth, EtOH
4419	Dioctyl ether		$C_{16}H_{34}O$	629-82-3	242.440	liq	-7.6	283	0.8063^{20}	1.4327^{20}	sl H_2O; s EtOH, eth, ctc
4420	Dioctyl hexanedioate		$C_{22}H_{42}O_4$	123-79-5	370.566		9.6	191^{2}	0.922^{25}		
4421	Dioctyl maleate		$C_{20}H_{36}O_4$	2915-53-9	340.498	liq		$242^{0.002}$	0.94^{20}	1.4539^{20}	
4422	Dioctyl phthalate		$C_{24}H_{38}O_4$	117-84-0	390.557		25	220^{4}			
4423	Dioctyl sebacate	Dioctyl decanedioate	$C_{26}H_{50}O_4$	2432-87-3	426.673		18	$218^{0.5}$	0.9074^{25}		s ctc
4424	Dioctyl sulfide	Octyl sulfide	$C_{16}H_{34}S$	2690-08-6	258.506			202^{29}, 180^{10}	0.842^{25}	1.4610^{20}	
4425	Dioctyl terephthalate		$C_{24}H_{38}O_4$	4654-26-6	390.557	cry		425	1.21^{62}		
4426	Dioscorine		$C_{13}H_{19}NO_2$	3329-91-7	221.296	grn-ye pr (eth)	34				s H_2O, ace, chl, EtOH; sl eth, bz
4427	1,3-Dioxane	1,3-Dioxacyclohexane	$C_4H_8O_2$	505-22-6	88.106	liq	-45	106.1	1.0286^{25}	1.4165^{20}	msc H_2O, EtOH, eth, ace, bz
4428	1,4-Dioxane	1,4-Dioxacyclohexane	$C_4H_8O_2$	123-91-1	88.106		11.85	101.5	1.0337^{20}	1.4224^{20}	msc H_2O, EtOH, eth, ace, bz; s ctc
4429	1,4-Dioxane-2,5-dione		$C_4H_4O_4$	502-97-6	116.073	lf (al, al-chl)	85.4				vs ace
4430	1,4-Dioxane-2,6-dione	Diglycollic anhydride	$C_4H_4O_4$	4480-83-5	116.073	cry (bz)	92.5	240.5; 120^{12}			
4431	Dioxathion		$C_{12}H_{26}O_6P_2S_4$	78-34-2	456.538		-20		1.257^{26}		
4432	1,3-Dioxepane		$C_5H_{10}O_2$	505-65-7	102.132						s chl
4433	1,3-Dioxolane	1,3-Dioxacyclopentane	$C_3H_6O_2$	646-06-0	74.079	liq	-97.22	78	1.060^{20}	1.3974^{20}	msc H_2O; s EtOH, eth, ace
4434	1,3-Dioxol-2-one		$C_3H_2O_3$	872-36-6	86.046	liq	22	162; 73^{32}	1.35^{25}		
4435	Dioxybenzone	(2-Hydroxy-4-methoxyphenyl)(2-hydroxyphenyl)methanone	$C_{14}H_{12}O_4$	131-53-3	244.243			172^{1}			
4436	Dioxypyramidon		$C_{13}H_{17}N_3O_3$	519-65-3	263.292	pr	105.5	197^{2}			s H_2O, EtOH
4437	Dipentaerythritol		$C_{10}H_{22}O_7$	126-58-9	254.278	cry (w)	221		1.366^{15}		s hot H_2O
4438	Dipentene	*p*-Menthadiene	$C_{10}H_{16}$	7705-14-8	136.234	liq	-95.5	178	0.8402^{21}	1.4727^{20}	
4439	Dipentylamine	Diamylamine	$C_{10}H_{23}N$	2050-92-2	157.297			202.5	0.7771^{20}	1.4272^{20}	sl H_2O; vs EtOH; msc eth; s ace
4440	Dipentyl *cis*-2-butenedioate	Dipentyl maleate	$C_{14}H_{24}O_4$	10099-71-5	256.339	liq		161^{10}	0.974^{20}		
4441	Dipentyl ether	Amyl ether	$C_{10}H_{22}O$	693-65-2	158.281	liq	-69	190	0.7833^{20}	1.4119^{20}	i H_2O; msc EtOH, eth; s chl
4442	2,6-Di-*tert*-pentyl-4-methylphenol	2,6-Bis(1,1-dimethylpropyl)-4-methylphenol	$C_{17}H_{28}O$	56103-67-4	248.403			283	0.931^{25}	1.4950^{20}	
4443	Di-*tert*-pentyl peroxide		$C_{10}H_{22}O_2$	10508-09-5	174.281		-55	58^{14}, 38^{9}	0.808^{20}	1.4095^{20}	
4444	Dipentyl phthalate		$C_{18}H_{26}O_4$	131-18-0	306.397			205^{11}			s ctc, CS_2
4445	Dipentyl sulfide		$C_{10}H_{22}S$	872-10-6	174.347		-51.3	$86^{3.7}$	0.8407^{20}	1.4561^{20}	i H_2O; s eth
4446	Dipentyl sulfoxide		$C_{10}H_{22}OS$	1986-90-9	190.346		58	120^{1}			
4447	Diphenamid	Benzeneacetamide, *N,N*-dimethyl-α-phenyl-	$C_{16}H_{17}NO$	957-51-7	239.312		135		$1.17^{23.3}$		
4448	Diphenidol	1,1-Diphenyl-4-piperidinyl-1-butanol	$C_{21}H_{27}NO$	972-02-1	309.445	nd (peth)	104.5				
4449	Diphenolic acid		$C_{17}H_{18}O_4$	126-00-1	286.323	cry (w)	171.5				vs H_2O, ace, EtOH
4450	1,2-Diphenoxyethane	Ethylene glycol diphenyl ether	$C_{14}H_{14}O_2$	104-66-5	214.260	lf (al)	98	182^{12}			i H_2O; sl EtOH; s eth, chl
4451	*N,N*-Diphenylacetamide		$C_{14}H_{13}NO$	519-87-9	211.259	wh cry pow	103	sub			sl H_2O, eth, chl; s EtOH
4452	Diphenylacetylene		$C_{14}H_{10}$	501-65-5	178.229	mcl pr or pl (al)	62.5	300	0.9657^{100}		i H_2O; sl EtOH, chl; vs eth
4453	2-(Diphenylacetyl)-1*H*-indene-1,3(2*H*)-dione	Diphenadione	$C_{23}H_{16}O_3$	82-66-6	340.371	pa ye mcl (al)	146.5			1.670	vs ace, HOAc
4454	Diphenylamine	*N*-Phenylbenzenamine	$C_{12}H_{11}N$	122-39-4	169.222	mcl lf(dil al)	53.2	302	1.158^{22}		i H_2O; vs EtOH, ace; s eth; sl chl
4455	Diphenylamine-2,2'-dicarboxylic acid		$C_{14}H_{11}NO_4$	579-92-0	257.242	ye cry (al)	296 dec				
4456	Diphenylamine-4-sulfonic acid, sodium salt	Sodium diphenylamine-4-sulfonate	$C_{12}H_{10}NNaO_3S$	6152-67-6	271.267	ye cry					
4457	9,10-Diphenylanthracene		$C_{26}H_{18}$	1499-10-1	330.421		246.5				
4458	Diphenylarsinous chloride	Chlorodiphenylarsine	$C_{12}H_{10}AsCl$	712-48-1	264.582	orth pl (peth)	44	337	1.4820^{16}	1.6332^{56}	vs ace, bz, eth, EtOH
4459	*N,N'*-Diphenyl-1,4-benzenediamine	*N,N'*-Diphenyl-*p*-phenylenediamine	$C_{18}H_{16}N_2$	74-31-7	260.333		150	$222^{0.5}$			sl EtOH, eth, bz, chl; i acid



Dinonyl ether



Dinonyl phthalate



Dinoseb



Dioctadecylamine



Dioctylamine



Dioctyl ether



Dioctyl hexanedioate



Dioctyl maleate


Dioctyl phthalate


Dioctyl sebacate



Dioctyl sulfide



Dioctyl terephthalate



Dioscorine


1,3-Dioxane


1,4-Dioxane


1,4-Dioxane-2,5-dione



1,4-Dioxane-2,6-dione



Dioxathion



1,3-Dioxepane



1,3-Dioxolane



1,3-Dioxol-2-one


Dioxybenzone



Dioxypyramidon



Dipentaerythritol



Dipentene



Dipentylamine



Dipentyl *cis*-2-butenedioate



Dipentyl ether



2,6-Di-*tert*-pentyl-4-methylphenol



Di-*tert*-pentyl peroxide



Dipentyl phthalate



Dipentyl sulfide



Dipentyl sulfoxide


Diphenamid



Diphenidol



Diphenolic acid



1,2-Diphenoxyethane



N,*N*-Diphenylacetamide



Diphenylacetylene



2-(Diphenylacetyl)-1*H*-indene-1,3(2*H*)-dione



Diphenylamine


Diphenylamine-2,2'-dicarboxylic acid



Diphenylamine-4-sulfonic acid, sodium salt



9,10-Diphenylanthracene



Diphenylarsinous chloride



N,*N*'-Diphenyl-1,4-benzenediamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4460	α,α-Diphenylbenzeneethanol		$C_{20}H_{18}O$	4428-13-1	274.356	nd(bz-lig) pr (peth)	89.5	222^{11}			i H_2O; vs EtOH; sl eth, chl, peth
4461	α,α-Diphenylbenzenemethanethiol	Triphenylmethyl mercaptan	$C_{19}H_{16}S$	3695-77-0	276.395		105.8				
4462	*N,N'*-Diphenyl-[1,1'-biphenyl]-4,4'-diamine	*N,N'*-Diphenylbenzidine	$C_{24}H_{20}N_2$	531-91-9	336.429	lf or pl	247				i H_2O; sl EtOH, eth, bz; vs tol, HOAc
4463	*trans,trans*-1,4-Diphenyl-1,3-butadiene		$C_{16}H_{14}$	538-81-8	206.282	lf (al, HOAc)	154.3	352			vs bz, eth, EtOH, peth
4464	1,4-Diphenyl-1,3-butadiyne	Diphenyldiacetylene	$C_{16}H_{10}$	886-66-8	202.250		86.5				
4465	1,1-Diphenylbutane		$C_{16}H_{18}$	719-79-9	210.314		27	287	0.9928^{20}	1.5664^{20}	i H_2O; s EtOH, eth, bz, chl
4466	1,2-Diphenylbutane		$C_{16}H_{18}$	5223-59-6	210.314			291; 152^{11}	0.9673^{20}	1.5554^{20}	i H_2O; s EtOH, eth, bz, chl
4467	1,4-Diphenylbutane		$C_{16}H_{18}$	1083-56-3	210.314		52.5	317	0.9880^{20}		i H_2O; s EtOH, eth, chl
4468	1,3-Diphenyl-1-butene		$C_{16}H_{16}$	7614-93-9	208.298		47.5	311	0.9996^{20}	1.590^{15}	
4469	*trans*-1,4-Diphenyl-2-butene-1,4-dione		$C_{16}H_{12}O_2$	959-28-4	236.265	ye nd (al, bz)	111				sl EtOH; s bz, HOAc; vs chl; i lig
4470	1,3-Diphenyl-2-buten-1-one	Dypnone	$C_{16}H_{14}O$	495-45-4	222.281			342.5	1.1080^{15}	1.6343^{20}	vs eth, EtOH
4471	Diphenylcarbamic chloride		$C_{13}H_{10}ClNO$	83-01-2	231.677	lf (al)	84.5				
4472	Diphenylcarbazone		$C_{13}H_{12}N_4O$	538-62-5	240.260	oran oran nd (bz) pr (al)	157 dec				i H_2O; vs EtOH, bz, chl
4473	*N,N'*-Diphenylcarbodiimide		$C_{13}H_{10}N_2$	622-16-2	194.231		169	331; 175^{20}			sl H_2O, EtOH, eth; s bz
4474	Diphenyl carbonate	Phenyl carbonate	$C_{13}H_{10}O_3$	102-09-0	214.216	nd (al, bz)	83	306	1.1215^{87}		i H_2O; s EtOH, eth, ctc, HOAc
4475	2,2'-Diphenylcarbonic dihydrazide	*sym*-Diphenylcarbazide	$C_{13}H_{14}N_4O$	140-22-7	242.276	cry (al + 1) cry (HOAc)	170	dec			sl H_2O, eth; s EtOH, ace, bz
4476	Diphenyl chlorophosphonate		$C_{12}H_{10}ClO_3P$	2524-64-3	268.632			314^{272}	1.296^{25}	1.5500^{20}	s tfa
4477	Diphenyl diselenide	Phenyl diselenide	$C_{12}H_{10}Se_2$	1666-13-3	312.13	ye nd	63.5	202^{11}	1.557^{80}	1.743^{20}	s EtOH, eth, xyl, MeOH
4478	Diphenyl disulfide	Phenyl disulfide	$C_{12}H_{10}S_2$	882-33-7	218.337	nd(al) or orth	62	310	1.353^{20}		i H_2O; s EtOH, eth, bz, CS_2
4479	1,1-Diphenylethane		$C_{14}H_{14}$	612-00-0	182.261	liq	-17.9	272.6	0.9997^{20}	1.5756^{20}	i H_2O; msc EtOH, eth; s bz
4480	1,2-Diphenylethane	Dibenzyl	$C_{14}H_{14}$	103-29-7	182.261	mcl pr (MeOH)	52.5	284	0.9780^{25}	1.5476^{60}	i H_2O; s EtOH, eth, CS_2
4481	*N,N'*-Diphenylethanediamide		$C_{14}H_{12}N_2O_2$	620-81-5	240.257	lf (bz)	254	>360			vs bz
4482	*N,N'*-Diphenyl-1,2-ethanediamine	1,2-Dianilinoethane	$C_{14}H_{16}N_2$	150-61-8	212.290	cry (dil al)	74	229^{12}, 178^{2}			i H_2O; s EtOH, eth; sl tfa
4483	1,2-Diphenyl-1,2-ethanediol, (*R*,R**)-(±)		$C_{14}H_{14}O_2$	655-48-1	214.260	nd (w,al),tab (eth)	122.5	>300			i H_2O, lig; vs EtOH, eth; s ace
4484	1,1-Diphenylethene		$C_{14}H_{12}$	530-48-3	180.245		8.2	277	1.0232^{20}	1.6085^{20}	i H_2O; s eth, chl
4485	Diphenyl ether		$C_{12}H_{10}O$	101-84-8	170.206		26.87	258.0	1.0661^{30}	1.5787^{25}	i H_2O; s EtOH, eth, bz, HOAc; sl chl
4486	Diphenyl 2-ethylhexyl phosphate		$C_{20}H_{27}O_4P$	1241-94-7	362.399			232^{5}	1.090^{25}	1.510^{25}	
4487	*N,N*-Diphenylformamide		$C_{13}H_{11}NO$	607-00-1	197.232	orth (dil al)	73.5	337.5; 189^{13}			i H_2O; s EtOH, eth, bz; sl ctc
4488	2,5-Diphenylfuran		$C_{16}H_{12}O$	955-83-9	220.265	nd or lf (dil al)	91	344			i H_2O; vs EtOH, eth; s ace, bz
4489	*N,N'*-Diphenylguanidine	1,3-Diphenylguanidine	$C_{13}H_{13}N_3$	102-06-7	211.262	mcl nd (al, to)	150	dec 170	1.13^{20}		sl H_2O; s EtOH, ctc chl, tol; vs eth
4490	1,6-Diphenyl-1,3,5-hexatriene		$C_{18}H_{16}$	1720-32-7	232.320	lf (ace)	202.3				i H_2O, EtOH, eth, HOAc; s ace; sl bz, chl
4491	1,1-Diphenylhydrazine		$C_{12}H_{12}N_2$	530-50-7	184.236	tab (lig)	50.5	220^{40}	1.190^{16}		vs bz, eth, EtOH, chl
4492	1,2-Diphenylhydrazine	Hydrazobenzene	$C_{12}H_{12}N_2$	122-66-7	184.236	tab (al-eth)	131		1.158^{16}		vs EtOH; sl bz, DMSO; i HOAc
4493	5,5-Diphenyl-4-imidazolidinone	Doxenitoin	$C_{15}H_{14}N_2O$	3254-93-1	238.284	pl (MeOH)	183				
4494	Diphenyl isophthalate		$C_{20}H_{14}O_4$	744-45-6	318.323		138				s chl
4495	Diphenylketene	Diphenylethenone	$C_{14}H_{10}O$	525-06-4	194.228	red-ye liq		267.5	1.1107^{13}	1.615^{14}	
4496	Diphenyl maleate		$C_{16}H_{12}O_4$	7242-17-3	268.264	pl (lig)	73	226^{15}			vs ace, bz, eth, EtOH
4497	Diphenylmercury	Mercuriodibenzene	$C_{12}H_{10}Hg$	587-85-9	354.80			204^{10}	2.318^{25}		i H_2O; sl EtOH, eth; s bz, chl
4498	Diphenylmethane		$C_{13}H_{12}$	101-81-5	168.234	pr nd	25.4	265.0	1.001^{26}	1.5753^{20}	i H_2O; s EtOH, eth, chl



α,α-Diphenylbenzeneethanol



α,α-Diphenylbenzenemethanethiol



N,N'-Diphenyl-[1,1'-biphenyl]-4,4'-diamine



trans,trans-1,4-Diphenyl-1,3-butadiene



1,4-Diphenyl-1,3-butadiyne



1,1-Diphenylbutane



1,2-Diphenylbutane



1,4-Diphenylbutane



1,3-Diphenyl-1-butene



trans-1,4-Diphenyl-2-butene-1,4-dione



1,3-Diphenyl-2-buten-1-one



Diphenylcarbamic chloride



Diphenylcarbazone



N,N'-Diphenylcarbodiimide



Diphenyl carbonate



2,2'-Diphenylcarbonic dihydrazide



Diphenyl chlorophosphonate



Diphenyl diselenide



Diphenyl disulfide



1,1-Diphenylethane



1,2-Diphenylethane



N,N'-Diphenylethanediamide



N,N'-Diphenyl-1,2-ethanediamine



1,2-Diphenyl-1,2-ethanediol, (*R**,*R**)-(±)



1,1-Diphenylethene



Diphenyl ether



Diphenyl 2-ethylhexyl phosphate



N,N-Diphenylformamide



2,5-Diphenylfuran



N,N'-Diphenylguanidine



1,6-Diphenyl-1,3,5-hexatriene



1,1-Diphenylhydrazine



1,2-Diphenylhydrazine



5,5-Diphenyl-4-imidazolidinone


Diphenyl isophthalate



Diphenylketene



Diphenyl maleate



Diphenylmercury



Diphenylmethane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4499	4,4'-Diphenylmethane diisocyanate	Methylene diphenyl diisocyanate	$C_{15}H_{10}N_2O_2$	101-68-8	250.252		37	196^{5}	1.197^{70}	1.5906^{50}	s ace, bz, $PhNO_2$
4500	Diphenylmethanethione		$C_{13}H_{10}S$	1450-31-3	198.283		53.5	174^{14}			sl EtOH, eth, peth; vs bz, chl
4501	*N,N'*-Diphenylmethanimidamide		$C_{13}H_{12}N_2$	622-15-1	196.247	nd (al)	142	>250			sl H_2O, peth; s EtOH, ace, bz; vs eth
4502	Diphenylmethanol	Benzohydrol	$C_{13}H_{12}O$	91-01-0	184.233	nd (lig)	69	298; 180^{20}			sl H_2O; vs EtOH, eth, ctc, chl; s HOAc
4503	2-(Diphenylmethoxy)-*N,N*-dimethylethanamine	Diphenhydramine	$C_{17}H_{21}NO$	58-73-1	255.355	oil		165^{3}			
4504	Diphenyl methylphosphonate		$C_{13}H_{13}O_3P$	7526-26-3	248.214		35	205^{13}	1.2051^{20}		i H_2O
4505	2-(Diphenylmethyl)-1-piperidineethanol	Diphemethoxidine	$C_{20}H_{25}NO$	13862-07-2	295.419		106.5	$180^{0.1}$			
4506	2,5-Diphenyloxazole		$C_{15}H_{11}NO$	92-71-7	221.254	nd (lig)	74	360	1.0940^{100}	1.6231^{100}	i H_2O; vs EtOH, eth; sl chl
4507	1,5-Diphenyl-1,4-pentadien-3-one	Dibenzalacetone	$C_{17}H_{14}O$	538-58-9	234.292	pl or lf (ace, AcOEt)	113 dec	dec			i H_2O; sl EtOH, eth; s ace, chl
4508	4,7-Diphenyl-1,10-phenanthroline		$C_{24}H_{16}N_2$	1662-01-7	332.397		220 dec				
4509	Diphenylphosphinous chloride	Chlorodiphenylphosphine	$C_{12}H_{10}ClP$	1079-66-9	220.634	hyg ye liq		320; 174^{5}	1.229	1.6360^{20}	
4510	Diphenyl phosphonate		$C_{12}H_{11}O_3P$	4712-55-4	234.187		12	218^{26}	1.223^{25}	1.5575^{20}	
4511	Diphenyl phthalate	Phenyl phthalate	$C_{20}H_{14}O_4$	84-62-8	318.323	pr (al, lig)	73	253^{14}			i H_2O; sl EtOH, eth, ctc
4512	α,α-Diphenyl-2-piperidinemethanol	Pipradrol	$C_{18}H_{21}NO$	467-60-7	267.366	cry (hx)	97.5				
4513	1,3-Diphenylpropane		$C_{15}H_{16}$	1081-75-0	196.288	liq	6	300; $123^{1.7}$	1.007^{20}	1.5760^{20}	
4514	2,2-Diphenylpropane		$C_{15}H_{16}$	778-22-3	196.288		29	282.5	0.9980^{20}		
4515	1,3-Diphenyl-1,3-propanedione	Dibenzoylmethane	$C_{15}H_{12}O_2$	120-46-7	224.255		70.5				s EtOH, eth, chl, dil NaOH
4516	1,3-Diphenyl-1-propanone	Phenethyl phenyl ketone	$C_{15}H_{14}O$	1083-30-3	210.271	lf (EtOH)	72.5	360			
4517	1,1-Diphenyl-2-propanone	1,1-Diphenylacetone	$C_{15}H_{14}O$	781-35-1	210.271		46	307; 174^{10}		1.5361^{16}	s EtOH, eth, bz, chl, lig
4518	1,3-Diphenyl-2-propanone	Dibenzyl ketone	$C_{15}H_{14}O$	102-04-5	210.271	cry (al, peth)	35	331	1.195^{0}		i H_2O; s EtOH, eth, peth
4519	3,3-Diphenyl-2-propenal	β-Phenylcinnamaldehyde	$C_{15}H_{12}O$	1210-39-5	208.255	pa ye pr (lig)	44.8	205^{14}			
4520	1,1-Diphenyl-1-propene		$C_{15}H_{14}$	778-66-5	194.272		52	280; 149^{11}	1.0250^{20}	1.5880^{20}	i H_2O; s EtOH, bz
4521	*trans*-1,3-Diphenyl-2-propen-1-one	Chalcone	$C_{15}H_{12}O$	614-47-1	208.255	pa ye lf, pr, nd (peth)	59	dec 346	1.0712^{62}		i H_2O; sl EtOH; s eth, bz, chl, CS_2
4522	1-(3,3-Diphenylpropyl)piperidine	Fenpiprane	$C_{20}H_{25}N$	3540-95-2	279.420		41.5	215^{8}			
4523	3,5-Diphenyl-1*H*-pyrazole		$C_{15}H_{12}N_2$	1145-01-3	220.269	cry (al)	200				
4524	1,4-Diphenyl-3,5-pyrazolidinedione	Phenopyrazone	$C_{15}H_{12}N_2O_2$	3426-01-5	252.268	cry (EtOAc, Diox)	233.5				
4525	Diphenyl selenide		$C_{12}H_{10}Se$	1132-39-4	233.17	ye nd (bz)	1.3	301.5	1.351^{20}	1.5500^{20}	i H_2O; msc EtOH, eth; s bz, xyl
4526	Diphenylsilane		$C_{12}H_{12}Si$	775-12-2	184.309			134^{16}, 96^{13}	0.9969^{20}	1.5800^{20}	s ctc, CS_2
4527	Diphenylsilanediol		$C_{12}H_{12}O_2Si$	947-42-2	216.308						sl DMSO
4528	Diphenyl succinate		$C_{16}H_{14}O_4$	621-14-7	270.280	lf (al)	121	330; 222.5^{15}			i H_2O; s EtOH, eth, ace, bz
4529	Diphenyl sulfide	Phenyl sulfide	$C_{12}H_{10}S$	139-66-2	186.272	liq	-25.9	296	1.1136^{20}	1.6334^{20}	i H_2O; s EtOH, ctc; msc eth, bz, CS_2
4530	Diphenyl sulfone		$C_{12}H_{10}O_2S$	127-63-9	218.271	mcl pr(bz) pl(al)	128.5	379	1.252^{20}		i H_2O; s EtOH, eth, bz
4531	Diphenyl sulfoxide		$C_{12}H_{10}OS$	945-51-7	202.271	pr(lig)	71.2	340^{16}			vs EtOH, eth, bz, HOAc; sl chl; i peth
4532	*N,N'*-Diphenylthiourea	*sym*-Diphenylthiourea	$C_{13}H_{12}N_2S$	102-08-9	228.312		154.5		1.32^{25}		sl H_2O; vs EtOH, eth, chl, oils
4533	1,3-Diphenyl-1-triazene	Diazoaminobenzene	$C_{12}H_{11}N_3$	136-35-6	197.235	ye lf or pr (al)	98				i H_2O; vs EtOH, eth, bz, py
4534	*N,N*-Diphenylurea		$C_{13}H_{12}N_2O$	603-54-3	212.246	tab (al)	189	dec	1.276^{25}		sl H_2O; s EtOH, eth, chl
4535	*N,N'*-Diphenylurea	Carbanilide	$C_{13}H_{12}N_2O$	102-07-8	212.246	orth pr (al)	239	260 dec	1.239^{25}		sl H_2O, EtOH; s eth, py, HOAc; i bz
4536	Diphosgene	Carbonochloridic acid, trichloromethyl ester	$C_2Cl_4O_2$	503-38-8	197.832	liq	-57	128	1.6525^{14}	1.4566^{22}	vs eth, EtOH
4537	1,2-Dipiperidinoethane		$C_{12}H_{24}N_2$	1932-04-3	196.332	liq	-0.5	265	0.9160^{25}	1.4853^{25}	
4538	1,1'-Dipiperidinomethane	1,1'-Methylenedipiperidine	$C_{11}H_{22}N_2$	880-09-1	182.306			230; 122^{15}	0.9269^{20}	1.4820^{20}	
4539	1,3-Di-4-piperidylpropane	4,4'-Trimethylenedipiperidine	$C_{13}H_{26}N_2$	16898-52-5	210.358		67.1	329			vs H_2O



4,4'-Diphenylmethane diisocyanate



Diphenylmethanethione



N,N'-Diphenylmethanimidamide



Diphenylmethanol



2-(Diphenylmethoxy)-*N,N*-dimethylethanamine



Diphenyl methylphosphonate



2-(Diphenylmethyl)-1-piperidineethanol



2,5-Diphenyloxazole



1,5-Diphenyl-1,4-pentadien-3-one



4,7-Diphenyl-1,10-phenanthroline



Diphenylphosphinous chloride



Diphenyl phosphonate



Diphenyl phthalate



α,α-Diphenyl-2-piperidinemethanol



1,3-Diphenylpropane



2,2-Diphenylpropane



1,3-Diphenyl-1,3-propanedione



1,3-Diphenyl-1-propanone



1,1-Diphenyl-2-propanone



1,3-Diphenyl-2-propanone



3,3-Diphenyl-2-propenal



1,1-Diphenyl-1-propene



trans-1,3-Diphenyl-2-propen-1-one



1-(3,3-Diphenylpropyl)piperidine



3,5-Diphenyl-1*H*-pyrazole



1,4-Diphenyl-3,5-pyrazolidinedione



Diphenyl selenide



Diphenylsilane



Diphenylsilanediol



Diphenyl succinate



Diphenyl sulfide



Diphenyl sulfone



Diphenyl sulfoxide



N,N'-Diphenylthiourea



1,3-Diphenyl-1-triazene



N,N-Diphenylurea


N,N'-Diphenylurea



Diphosgene



1,2-Dipiperidinoethane



1,1'-Dipiperidinomethane



1,3-Di-4-piperidylpropane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4540	Diploicin		$C_{16}H_{10}Cl_4O_5$	527-93-5	424.059		232				
4541	Di-2-propenoyldiethyleneglycol		$C_{10}H_{14}O_5$	4074-88-8	214.215			200	1.1110^{25}	1.4595^{25}	
4542	Di-2-propenoyl-2,2-dimethyl-1,3-propanediol	2-Propenoic acid, 2,2-dimethyl-1,3-propanediyl ester	$C_{11}H_{16}O_4$	2223-82-7	212.243					1.4542^{25}	
4543	Di-2-propenoyl-1,6-hexanediol	2-Propenoic acid, 1,6-hexanediyl ester	$C_{12}H_{18}O_4$	13048-33-4	226.269				1.010^{25}		
4544	Dipropetryn	6-(Ethylthio)-*N,N'*-diisopropyl-1,3,5-triazine-2,4-diamine	$C_{11}H_{21}N_5S$	4147-51-7	255.384		105				
4545	1,2-Dipropoxyethane		$C_8H_{18}O_2$	18854-56-3	146.228	liq		163.2 dec	0.8312^{25}	1.4013^{25}	
4546	Dipropoxymethane	Formaldehyde, dipropyl acetal	$C_7H_{16}O_2$	505-84-0	132.201	liq	-97.3	140.5	0.8345^{20}	1.3939^{19}	vs ace, bz, eth, EtOH
4547	*N,N*-Dipropylacetamide		$C_8H_{17}NO$	1116-24-1	143.227			209.5	0.8992^{17}	1.4419^{17}	vs EtOH
4548	Dipropyl adipate		$C_{12}H_{22}O_4$	106-19-4	230.301		-15.7	151^{11}	0.9790^{20}	1.4314^{20}	vs eth, EtOH, chl
4549	Dipropylamine	*N*-Propyl-1-propanamine	$C_6H_{15}N$	142-84-7	101.190	liq	-63	109.3	0.7400^{20}	1.4050^{20}	s H_2O, EtOH; msc eth; vs ace, bz
4550	4-[(Dipropylamino)sulfonyl] benzoic acid	Probenecid	$C_{13}H_{19}NO_4S$	57-66-9	285.360		195				
4551	*N,N*-Dipropylaniline		$C_{12}H_{19}N$	2217-07-4	177.286	ye lf		242	0.9104^{20}	1.5271^{20}	i H_2O; s EtOH, eth, ace, bz; sl ctc
4552	Dipropylcarbamothioic acid, *S*-ethyl ester	EPTC	$C_9H_{19}NOS$	759-94-4	189.318			127^{20}	0.9546^{30}		
4553	Dipropyl carbonate		$C_7H_{14}O_3$	623-96-1	146.184			168	0.9435^{20}	1.4008^{20}	sl H_2O; msc EtOH, eth
4554	Dipropyl disulfide		$C_6H_{14}S_2$	629-19-6	150.305	liq	-85.6	195.8	0.9599^{20}	1.4981^{20}	
4555	Dipropylene glycol		$C_6H_{14}O_3$	25265-71-8	134.173			230.5	1.0206^{20}		msc H_2O; s EtOH
4556	Dipropylene glycol dibenzoate		$C_{20}H_{22}O_5$	27138-31-4	342.386			197^{1}			
4557	Dipropylene glycol monomethyl ether	1-(2-Methoxyisopropoxy)-2-propanol	$C_7H_{16}O_3$	34590-94-8	148.200	liq	-80	188.3	0.95	1.4190^{20}	
4558	Dipropyl ether	Propyl ether	$C_6H_{14}O$	111-43-3	102.174	liq	-114.8	90.08	0.7466^{20}	1.3809^{20}	sl H_2O; vs eth, EtOH
4559	Dipropyl fumarate		$C_{10}H_{16}O_4$	14595-35-8	200.232			110^{5}	1.0129^{20}	1.4435^{20}	s EtOH, eth
4560	Dipropyl maleate		$C_{10}H_{16}O_4$	2432-63-5	200.232			126^{12}	1.0245^{20}	1.4434^{20}	i H_2O; s EtOH, eth, ace, bz
4561	Dipropyl oxalate		$C_8H_{14}O_4$	615-98-5	174.195	liq	-44.3	211	1.0188^{20}	1.4158^{20}	sl H_2O; msc EtOH; s eth
4562	5,5-Dipropyl-2,4-oxazolidinedione		$C_9H_{15}NO_3$	512-12-9	185.220		42.5	149^{3}			
4563	Dipropyl succinate		$C_{10}H_{18}O_4$	925-15-5	202.248	liq	-5.9	250.8	1.0020^{20}	1.4250^{20}	vs ace, bz, eth
4564	Dipropyl sulfate		$C_6H_{14}O_4S$	598-05-0	182.238			120^{20}	1.1064^{20}	1.4135^{20}	vs peth
4565	Dipropyl sulfide		$C_6H_{14}S$	111-47-7	118.240	liq	-102.5	142.9	0.814^{17}	1.4487^{20}	i H_2O; s EtOH, eth
4566	Dipropyl sulfone		$C_6H_{14}O_2S$	598-03-8	150.239	cry	29.5		1.0278^{50}	1.4456^{30}	sl H_2O; s EtOH, eth
4567	Dipropyl sulfoxide		$C_6H_{14}OS$	4253-91-2	134.239	nd	22.5	80^{2}	0.9654^{20}	1.4663^{20}	vs eth, EtOH
4568	Dipyridamole		$C_{24}H_{40}N_8O_4$	58-32-2	504.627		163				
4569	Di-2-pyridinyl disulfide, *N,N'*-dioxide	Dipyrithione	$C_{10}H_8N_2O_2S_2$	3696-28-4	252.313	cry (MeOH)	205				
4570	2,2'-Dipyrrolylmethane		$C_9H_{10}N_2$	21211-65-4	146.188	lf or nd (al)	73	164^{12}			vs bz, eth, EtOH
4571	Diquat		$C_{12}H_{12}N_2$	2764-72-9	184.236	Cation					
4572	Diquat dibromide		$C_{12}H_{12}Br_2N_2$	85-00-7	344.044		337		1.24^{20}		
4573	Disodium calcium EDTA	Edetate calcium disodium	$C_{10}H_{12}CaN_2Na_2O_8$	62-33-9	374.268	pow					s H_2O
4574	Disodium hydrogen citrate	Sodium acid citrate	$C_6H_6Na_2O_7$	144-33-2	236.088	wh pow (w)	149 dec				vs H_2O
4575	Disperse Blue No. 1	1,4,5,8-Tetraamino-9,10-anthracenedione	$C_{14}H_{12}N_4O_2$	2475-45-8	268.271	red-br nd	331				
4576	Distearyl thiodipropionate	Dioctadecyl thiobispropanoate	$C_{42}H_{82}O_4S$	693-36-7	683.163	cry	61				
4577	Disulfiram		$C_{10}H_{20}N_2S_4$	97-77-8	296.539		71.5	117^{17}			i H_2O; s EtOH; sl eth; vs chl
4578	Disulfoton		$C_8H_{19}O_2PS_3$	298-04-4	274.405		-25	$108^{0.01}$, 128^{1}	1.144^{20}		
4579	1,2-Dithiane		$C_4H_8S_2$	505-20-4	120.237	nd	32.5	80^{14}, 60^{5}		1.5981^{25}	s eth, bz, chl
4580	1,3-Dithiane		$C_4H_8S_2$	505-23-7	120.237		54	89^{14}		1.5981^{25}	vs bz, eth, chl
4581	1,4-Dithiane		$C_4H_8S_2$	505-29-3	120.237	mcl pr	112.3	199.5			sl H_2O; s EtOH, eth, ctc, CS_2, HOAc
4582	Dithianone		$C_{14}H_4N_2O_2S_2$	3347-22-6	296.324	nd (ace)	220				
4583	Dithiazanine iodide		$C_{23}H_{23}IN_2S_2$	514-73-8	518.476	grn nd (MeOH)	248 dec				i H_2O
4584	2,2'-Dithiobisbenzoic acid	Diphenyl disulfide-2,2'-dicarboxylic acid	$C_{14}H_{10}O_4S_2$	119-80-2	306.357		289.5				i H_2O; s EtOH, eth
4585	3,3'-Dithiobispropanoic acid		$C_6H_{10}O_4S_2$	1119-62-6	210.271		158				
4586	3,3'-Dithiobis-*D*-valine		$C_{10}H_{20}N_2O_4S_2$	20902-45-8	296.407		204.5				



Diploicin



Di-2-propenoyldiethyleneglycol



Di-2-propenoyl-2,2-dimethyl-1,3-propanediol



Di-2-propenoyl-1,6-hexanediol



Dipropetryn



1,2-Dipropoxyethane



Dipropoxymethane



N,N-Dipropylacetamide



Dipropyl adipate



Dipropylamine



4-[(Dipropylamino)sulfonyl]benzoic acid



N,N-Dipropylaniline



Dipropylcarbamothioic acid, *S*-ethyl ester



Dipropyl carbonate



Dipropyl disulfide



Dipropylene glycol



Dipropylene glycol dibenzoate



Dipropylene glycol monomethyl ether



Dipropyl ether



Dipropyl fumarate



Dipropyl maleate



Dipropyl oxalate



5,5-Dipropyl-2,4-oxazolidinedione



Dipropyl succinate



Dipropyl sulfate



Dipropyl sulfide



Dipropyl sulfone



Dipropyl sulfoxide



Dipyridamole



Di-2-pyridinyl disulfide, *N,N'*-dioxide



2,2'-Dipyrrolylmethane



Diquat



Diquat dibromide



Disodium calcium EDTA


Disodium hydrogen citrate


Disperse Blue No. 1


Distearyl thiodipropionate



Disulfiram



Disulfoton



1,2-Dithiane



1,3-Dithiane



1,4-Dithiane


Dithianone



Dithiazanine iodide



2,2'-Dithiobisbenzoic acid


3,3'-Dithiobispropanoic acid


3,3'-Dithiobis-*D*-valine

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4587	2,5-Dithiobiurea	1,2-Hydrazinedicarbothioamide	$C_2H_6N_4S_2$	142-46-1	150.226	nd (w)	214				
4588	4,4′-Dithiodimorpholine		$C_8H_{16}N_2O_2S_2$	103-34-4	236.355		124.5				s chl
4589	1,2-Dithiolane		$C_3H_6S_2$	557-22-2	106.210		77	90^{27}			
4590	1,3-Dithiolane	1,3-Dithiacyclopentane	$C_3H_6S_2$	4829-04-3	106.210	liq	-50	175	1.259^{17}	1.5975^{15}	s EtOH, eth, xyl
4591	1,3-Dithiolane-2-thione		$C_3H_4S_3$	822-38-8	136.259		35	307			
4592	Dithiopyr		$C_{15}H_{16}F_5NO_2S_2$	97886-45-8	401.416		65				
4593	Dithizone		$C_{13}H_{12}N_4S$	60-10-6	256.326	bl-blk (chl-al)	167 dec				i H_2O; sl EtOH, eth; s chl, alk
4594	Di(*p*-tolyl)carbodiimide		$C_{15}H_{14}N_2$	726-42-1	222.285		58.5	221^{20}	1.1500^{20}		
4595	1,2-Di(*p*-tolyl)ethane	1,2-Bis(*p*-tolyl)ethane	$C_{16}H_{18}$	538-39-6	210.314	lf (al)	85	178^{18}			i H_2O; sl EtOH; s bz, peth
4596	*N,N′*-Di(*o*-tolyl)guanidine		$C_{15}H_{17}N_3$	97-39-2	239.316	cry (dil al)	179		1.10^{20}		sl H_2O, tfa, EtOH; vs eth; s chl
4597	Ditridecyl phthalate		$C_{34}H_{58}O_4$	119-06-2	530.823	liq		$285^{3.5}$	0.952^{25}		
4598	Diundecyl phthalate		$C_{30}H_{50}O_4$	3648-20-2	474.716	cry (EtOH)	35.5				
4599	Diuron		$C_9H_{10}Cl_2N_2O$	330-54-1	233.093		158				
4600	*o*-Divinylbenzene	1,2-Divinylbenzene	$C_{10}H_{10}$	91-14-5	130.186			82^{14}	0.9325^{22}	1.5767^{20}	s ace, bz
4601	*m*-Divinylbenzene	1,3-Divinylbenzene	$C_{10}H_{10}$	108-57-6	130.186		-52.3	121^{76}, 52^{3}	0.9294^{20}	1.5760^{20}	s ace, bz
4602	*p*-Divinylbenzene	1,4-Divinylbenzene	$C_{10}H_{10}$	105-06-6	130.186		31	95^{18}, $34^{0.2}$	0.913^{40}	1.5835^{25}	s ace, bz
4603	*cis*-1,2-Divinylcyclobutane		C_8H_{12}	16177-46-1	108.181			38^{38}	0.8010^{20}	1.4563^{20}	
4604	*trans*-1,2-Divinylcyclobutane		C_8H_{12}	6553-48-6	108.181			112.5	0.7817^{20}	1.4451^{20}	
4605	Divinyl ether		C_4H_6O	109-93-3	70.090	vol liq or gas	-100.6	28.3	0.773^{20}	1.3989^{20}	i H_2O; msc EtOH, eth, ace, chl
4606	Divinyl sulfide	Vinyl sulfide	C_4H_6S	627-51-0	86.156		20	84	0.9174^{15}		sl H_2O; s ace; msc EtOH, eth
4607	Divinyl sulfone	Vinyl sulfone	$C_4H_6O_2S$	77-77-0	118.155	liq	-26	234.5	1.177^{25}	1.4765^{20}	
4608	1,3-Divinyl-1,1,3,3-tetramethyldisiloxane		$C_8H_{18}OSi_2$	2627-95-4	186.399	liq	-99.7	39	0.811^{20}	1.4123^{20}	
4609	Djenkolic acid		$C_7H_{14}N_2O_4S_2$	498-59-9	254.327	nd(w)	≈325 dec				
4610	DMPA		$C_{10}H_{14}Cl_2NO_2PS$	299-85-4	314.169	solid	51.4	150^{2}			sl H_2O; vs bz, ctc, ace
4611	Docosane		$C_{22}H_{46}$	629-97-0	310.600	pl(to), cry (eth)	43.6	368.6	0.7944^{20}	1.4455^{20}	i H_2O; s EtOH, chl; vs eth
4612	Docosanoic acid	Behenic acid	$C_{22}H_{44}O_2$	112-85-6	340.583	nd	81.5	306^{60}	0.8223^{90}	1.4270^{100}	sl H_2O, EtOH, eth
4613	1-Docosanol		$C_{22}H_{46}O$	661-19-8	326.599	cry (ace, chl)	72.5	$180^{0.22}$			sl H_2O, eth; vs EtOH, MeOH; s chl
4614	13-Docosenamide	Erucamide	$C_{22}H_{43}NO$	112-84-5	337.582	cry	94				
4615	1-Docosene		$C_{22}H_{44}$	1599-67-3	308.584		38	367	0.794^{25}		
4616	*cis*-13-Docosenoic acid	Erucic acid	$C_{22}H_{42}O_2$	112-86-7	338.567	nd (al)	34.7	265^{15}	0.860^{55}	1.4758^{20}	i H_2O; s EtOH, ctc; vs eth, MeOH
4617	*trans*-13-Docosenoic acid	Brassidic acid	$C_{22}H_{42}O_2$	506-33-2	338.567	pl (al)	61.9	282^{30}, 256^{10}	0.8585^{57}	1.4347^{100}	
4618	5,7-Dodecadiyne	Dibutylbutadiyne	$C_{12}H_{18}$	1120-29-2	162.271			103^{8}			
4619	Dodecamethylcyclohexasiloxane		$C_{12}H_{36}O_6Si_6$	540-97-6	444.923	liq	-1.5	245	0.9672^{25}	1.4015^{20}	i H_2O
4620	Dodecamethylpentasiloxane		$C_{12}H_{36}O_4Si_5$	141-63-9	384.840	liq	-80	232; 105^{12}	0.8755^{20}	1.3925^{20}	s ctc, CS_2
4621	Dodecanal	Lauraldehyde	$C_{12}H_{24}O$	112-54-9	184.318	lf	44.5	185^{100}, $100^{2.5}$	0.8352^{15}	1.435^{22}	i H_2O; sl EtOH; s eth
4622	Dodecanamide		$C_{12}H_{25}NO$	1120-16-7	199.333	nd	110	199^{12}		1.4287^{110}	i H_2O; s EtOH, ace, ctc; sl eth, bz
4623	Dodecane		$C_{12}H_{26}$	112-40-3	170.334	liq	-9.57	216.32	0.7495^{20}	1.4210^{20}	i H_2O; vs EtOH, eth, ace, ctc, chl
4624	1,12-Dodecanediamine		$C_{12}H_{28}N_2$	2783-17-7	200.363		67.38	135^{3}			
4625	Dodecanedioic acid		$C_{12}H_{22}O_4$	693-23-2	230.301		128	222^{25}	1.15^{25}		s tfa
4626	1,12-Dodecanediol		$C_{12}H_{26}O_2$	5675-51-4	202.333	cry (bz, dil al)	81.3	189^{12}			s tfa
4627	Dodecanenitrile	Lauronitrile	$C_{12}H_{23}N$	2437-25-4	181.318		4	277; 198^{100}	0.8240^{20}	1.4361^{20}	i H_2O; msc EtOH, eth, ace, bz, chl
4628	1-Dodecanethiol		$C_{12}H_{26}S$	112-55-0	202.399	liq	-6.7	277; 143^{15}	0.844^{20}	1.4589^{20}	i H_2O; s EtOH, eth, chl
4629	Dodecanoic acid	Lauric acid	$C_{12}H_{24}O_2$	143-07-7	200.318	nd (al)	43.8	91.4	0.8679^{50}	1.4183^{82}	i H_2O; vs EtOH, eth; s ace; msc bz
4630	Dodecanoic anhydride		$C_{24}H_{46}O_3$	645-66-9	382.620	lf (al, eth)	41.8		0.8533^{70}	1.4292^{70}	vs EtOH
4631	1-Dodecanol	Lauryl alcohol	$C_{12}H_{26}O$	112-53-8	186.333	lf (dil al)	23.9	260	0.8309^{24}		i H_2O; s EtOH, eth; sl bz
4632	2-Dodecanol		$C_{12}H_{26}O$	10203-28-8	186.333		19	252	0.8286^{20}	1.4400^{20}	



2,5-Dithiobiurea



4,4'-Dithiodimorpholine



1,2-Dithiolane



1,3-Dithiolane



1,3-Dithiolane-2-thione



Dithiopyr



Dithizone



Di(*p*-tolyl)carbodiimide



1,2-Di(*p*-tolyl)ethane



N,N'-Di(*o*-tolyl)guanidine



Ditridecyl phthalate


Diundecyl phthalate


Diuron



o-Divinylbenzene


m-Divinylbenzene



p-Divinylbenzene



cis-1,2-Divinylcyclobutane



trans-1,2-Divinylcyclobutane



Divinyl ether



Divinyl sulfide



Divinyl sulfone



1,3-Divinyl-1,1,3,3-tetramethyldisiloxane



Djenkolic acid



DMPA



Docosane



Docosanoic acid


1-Docosanol



13-Docosenamide



1-Docosene



cis-13-Docosenoic acid



trans-13-Docosenoic acid


5,7-Dodecadiyne



Dodecamethylcyclohexasiloxane



Dodecamethylpentasiloxane



Dodecanal



Dodecanamide



Dodecane



1,12-Dodecanediamine



Dodecanedioic acid



1,12-Dodecanediol



Dodecanenitrile


1-Dodecanethiol



Dodecanoic acid


Dodecanoic anhydride



1-Dodecanol



2-Dodecanol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4633	2-Dodecanone	Decyl methyl ketone	$C_{12}H_{24}O$	6175-49-1	184.318		21	246.5	0.8198^{20}	1.4330^{20}	i H_2O; s EtOH, eth, ace; sl ctc
4634	Dodecanoyl chloride		$C_{12}H_{23}ClO$	112-16-3	218.763		-17	145^{18}	0.9169^{25}	1.4458^{20}	vs eth
4635	1-Dodecene		$C_{12}H_{24}$	112-41-4	168.319	liq	-35.2	213.8	0.7584^{20}	1.4300^{20}	i H_2O; s EtOH, eth, ace, ctc, peth
4636	*trans*-2-Dodecenedioic acid	Traumatic acid	$C_{12}H_{20}O_4$	6402-36-4	228.285	cry (al,ace)	165.5				vs eth, EtOH, chl
4637	2-Dodecenylsuccinic anhydride		$C_{16}H_{26}O_3$	19780-11-1	266.375	hyg cry	42	181^{5}			
4638	Dodecyl acetate		$C_{14}H_{28}O_2$	112-66-3	228.371		0.7	265; 180^{40}	0.8652^{22}	1.4439^{20}	
4639	Dodecyl acrylate	Lauryl 2-propenoate	$C_{15}H_{28}O_2$	2156-97-0	240.382		4	$120^{0.8}$	0.8727^{20}		
4640	Dodecylamine	1-Dodecanamine	$C_{12}H_{27}N$	124-22-1	185.349		28.3	259	0.8015^{20}	1.4421^{20}	sl H_2O; msc EtOH, eth, bz, chl
4641	Dodecylamine, acetate	1-Dodecanamine, acetate	$C_{14}H_{31}NO_2$	2016-56-0	245.402		69.5				vs H_2O, EtOH
4642	Dodecylamine hydrochloride	Lauryl amine hydrochloride	$C_{12}H_{28}ClN$	929-73-7	221.810		186				vs H_2O, EtOH
4643	4-Dodecylaniline		$C_{18}H_{31}N$	104-42-7	261.446		41.5	211^{10}			
4644	Dodecylbenzene	Laurylbenzene	$C_{18}H_{30}$	123-01-3	246.431		3	328	0.8551^{20}	1.4824^{20}	i H_2O
4645	4-Dodecylbenzenesulfonic acid		$C_{18}H_{30}O_3S$	121-65-3	326.494			>205			
4646	Dodecylcyclohexane		$C_{18}H_{36}$	1795-17-1	252.479		12.5	331	0.8223^{20}	1.4559^{20}	
4647	Dodecyl mercaptoacetate		$C_{14}H_{28}O_2S$	3746-39-2	260.436		1.5	171^{3}			
4648	Dodecyl methacrylate		$C_{16}H_{30}O_2$	142-90-5	254.408			142^{4}	0.866^{20}		
4649	Dodecyloxirane	1,2-Epoxytetradecane	$C_{14}H_{28}O$	3234-28-4	212.371	oil		$95^{0.4}$	0.845	1.4408^{20}	
4650	2-(Dodecyloxy)ethanol		$C_{14}H_{30}O_2$	4536-30-5	230.387			$143^{0.8}$			
4651	4-Dodecyloxy-2-hydroxybenzophenone		$C_{25}H_{34}O_3$	2985-59-3	382.536		43.5				
4652	4-Dodecylphenol		$C_{18}H_{30}O$	104-43-8	262.430	nd (bz)	66	175^{2}			
4653	1-Dodecylpiperidine		$C_{17}H_{35}N$	5917-47-5	253.467	pa ye		161^{5}, $115^{0.6}$	0.8378^{20}	1.4588^{20}	
4654	Dodecyl sulfate	Lauryl sulfate	$C_{12}H_{26}O_4S$	151-41-7	266.397	cry					s H_2O
4655	Dodecyltetraethylene glycol monoether	3,6,9,12-Tetraoxatetracosan-1-ol	$C_{20}H_{42}O_5$	5274-68-0	362.544			247^{10}			
4656	Dodecyl 3,4,5-trihydroxybenzoate		$C_{19}H_{30}O_5$	1166-52-5	338.438		96.5				s ace
4657	Dodecyltrimethylammonium chloride		$C_{15}H_{34}ClN$	112-00-5	263.891		246 dec				vs H_2O, ace, EtOH, chl
4658	1-Dodecyne	Decylacetylene	$C_{12}H_{22}$	765-03-7	166.303	liq	-19	215	0.7788^{20}	1.4340^{20}	
4659	6-Dodecyne		$C_{12}H_{22}$	6975-99-1	166.303			210; 100^{14}	0.785^{20}	1.4442^{20}	vs ace, eth, EtOH
4660	Dodine	Dodecylguanidine, monoacetate	$C_{15}H_{33}N_3O_2$	2439-10-3	287.442		136				
4661	Dopamine	4(2-Aminoethyl)-1,2-benzenediol	$C_8H_{11}NO_2$	51-61-6	153.179	pr					
4662	Dothiepin		$C_{19}H_{21}NS$	113-53-1	295.442		56	$172^{0.05}$			
4663	Dotriacontane	Bicetyl	$C_{32}H_{66}$	544-85-4	450.866	pl (bz,chl,HOAc,eth)	69.4	467	0.8124^{20}	1.4550^{20}	i H_2O; sl EtOH, chl; s eth, ctc; vs bz
4664	Doxepin		$C_{19}H_{21}NO$	1668-19-5	279.376	oily liq		$155^{0.03}$, $265^{0.2}$			
4665	Doxorubicin	Adriamycin	$C_{27}H_{29}NO_{11}$	23214-92-8	543.519	cry	230				
4666	Doxorubicin hydrochloride	Adriamycin hydrochloride	$C_{27}H_{30}ClNO_{11}$	25316-40-9	579.980	oran-red nd	204 dec				s H_2O, MeOH; i ace, bz, chl, eth, peth
4667	Doxylamine		$C_{17}H_{22}N_2O$	469-21-6	270.369	liq		$139^{0.5}$			
4668	Drimenin		$C_{15}H_{22}O_2$	2326-89-8	234.335	cry	133	$110^{0.1}$			i H_2O
4669	Dromostanolone propanoate	2-Methyl-17-(1-oxopropoxy) androstan-3-one, (2α,5α,17β)	$C_{23}H_{36}O_3$	521-12-0	360.530		128				
4670	Droperidol	Dehydrobenzperidol	$C_{22}H_{22}FN_3O_2$	548-73-2	379.427	cry (w)	146 (hyd)				i H_2O; sl EtOH, eth, bz; s chl, DMF
4671	Dydrogesterone		$C_{21}H_{28}O_2$	152-62-5	312.446	cry (ace/hx)	170				
4672	Dyphylline		$C_{10}H_{14}N_4O_4$	479-18-5	254.243		161.5				
4673	Ecgonidine		$C_9H_{13}NO_2$	484-93-5	167.205	cry (MeOH) (MeOH-eth)	228 dec				vs H_2O
4674	Ecgonine		$C_9H_{15}NO_3$	481-37-8	185.220	mcl pr	205				vs H_2O, EtOH
4675	Echimidine		$C_{20}H_{31}NO_7$	520-68-3	397.463	glass					
4676	Echinochrome A	2-Ethyl-3,5,6,7,8-pentahydroxy-1,4-naphthalenedione	$C_{12}H_{10}O_7$	517-82-8	266.203	red nd (Diox-w)	220 dec	sub 120			sl H_2O; s EtOH, ace; vs eth, bz
4677	Echitamine		$C_{22}H_{30}N_2O_5$	6871-44-9	402.483		206				s H_2O, EtOH, eth, chl, con sulf; i peth
4678	Edrophonium chloride		$C_{10}H_{16}ClNO$	116-38-1	201.693	cry	162				vs H_2O; s EtOH; i eth, chl
4679	Efloxate	Ethyl [(4-oxo-2-phenyl-4*H*-1-benzopyran-7-yl)oxy]acetate	$C_{19}H_{16}O_5$	119-41-5	324.327		123.7				s chl
4680	Eicosamethylnonasiloxane		$C_{20}H_{60}O_8Si_9$	2652-13-3	681.455			307.5; 198^{16}	0.9173^{20}	1.3980^{20}	vs bz



2-Dodecanone
Dodecanoyl chloride
1-Dodecene
trans-2-Dodecenedioic acid
2-Dodecenylsuccinic anhydride
Dodecyl acetate
Dodecyl acrylate
Dodecylamine
Dodecylamine, acetate
Dodecylamine hydrochloride
4-Dodecylaniline
Dodecylbenzene
4-Dodecylbenzenesulfonic acid
Dodecylcyclohexane
Dodecyl mercaptoacetate
Dodecyl methacrylate
Dodecyloxirane
2-(Dodecyloxy)ethanol
4-Dodecyloxy-2-hydroxybenzophenone
4-Dodecylphenol
1-Dodecylpiperidine
Dodecyl sulfate
Dodecyltetraethylene glycol monoether
Dodecyl 3,4,5-trihydroxybenzoate
Dodecyltrimethylammonium chloride
1-Dodecyne
6-Dodecyne
Dodine
Dopamine
Dothiepin
Dotriacontane
Doxepin
Doxorubicin
Doxorubicin hydrochloride
Doxylamine
Drimenin
Dromostanolone propanoate
Droperidol
Dydrogesterone
Dyphylline
Ecgonidine
Ecgonine
Echimidine
Echinochrome A
Echitamine
Edrophonium chloride
Efloxate
Eicosamethylnonasiloxane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4681	Eicosane	Icosane	$C_{20}H_{42}$	112-95-8	282.547	lf (al)	36.6	343	0.7886^{20}	1.4425^{20}	i H_2O; s eth, peth, bz; sl chl; vs ace
4682	Eicosanedioic acid	1,18-Octadecanedicarboxylic acid	$C_{20}H_{38}O_4$	2424-92-2	342.514	cry (bz,al)	125.5	233^{2}			s eth
4683	Eicosanoic acid	Arachidic acid	$C_{20}H_{40}O_2$	506-30-9	312.531	pl (al)	76.5	dec 328; 204^{1}	0.8240^{100}	1.425^{100}	i H_2O; sl EtOH; vs eth; s bz, chl
4684	1-Eicosanol	Arachic alcohol	$C_{20}H_{42}O$	629-96-9	298.546	wax (al), cry (chl)	65.4	356; 222^{3}	0.8405^{20}	1.4350^{20}	i H_2O; sl EtOH, chl; vs ace; s bz, peth
4685	5,8,11,14-Eicosatetraenoic acid, (all-*cis*)	Arachidonic acid	$C_{20}H_{32}O_2$	506-32-1	304.467		-49.5	163^{1}	0.9082^{20}	1.4824^{20}	i H_2O; vs ace, eth, EtOH, peth
4686	1-Eicosene		$C_{20}H_{40}$	3452-07-1	280.532		28.5	341; 151^{2}	0.7882^{30}	1.4440^{30}	i H_2O; s bz, peth
4687	*cis*-9-Eicosenoic acid		$C_{20}H_{38}O_2$	29204-02-2	310.515		24.5	220^{6}	0.8882^{25}		
4688	*trans*-9-Eicosenoic acid		$C_{20}H_{38}O_2$	506-31-0	310.515		54				
4689	11-Eicosenoic acid		$C_{20}H_{38}O_2$	2462-94-4	310.515		24	267^{15}	0.8826^{25}		vs EtOH, MeOH
4690	Elaidic acid	*trans*-9-Octadecenoic acid	$C_{18}H_{34}O_2$	112-79-8	282.462	pl (al)	45	288^{100}, 234^{15}	0.8734^{45}	1.4499^{45}	i H_2O; s EtOH, eth, bz, chl
4691	Elaiomycin		$C_{13}H_{26}N_2O_3$	23315-05-1	258.356	ye oil				1.4798^{25}	sl H_2O; s os
4692	1,3-Elemadien-11-ol	Elemol	$C_{15}H_{26}O$	639-99-6	222.366	cry (al)	52.5	142^{12}	0.9345^{18}	1.4980^{18}	
4693	β-Elemene		$C_{15}H_{24}$	33880-83-0	204.352			120^{16}, 104^{11}	0.8749^{20}	1.4935^{20}	
4694	Embelin	2,5-Dihydroxy-3-undecyl-2,5-cyclohexadiene-1,4-dione	$C_{17}H_{26}O_4$	550-24-3	294.386	oran pl (al)	142.5				vs bz, eth, EtOH
4695	Emetine	6',7',10,11-Tetramethoxyemetan	$C_{29}H_{40}N_2O_4$	483-18-1	480.639	amor pow	74				i H_2O; s EtOH, eth, ace; sl bz, chl
4696	Emylcamate	3-Methyl-3-pentanol, carbamate	$C_7H_{15}NO_2$	78-28-4	145.200	nd	57	35^{1}			sl H_2O; vs bz, eth, EtOH
4697	Enallylpropymal		$C_{11}H_{16}N_2O_3$	1861-21-8	224.256	cry (w, dil al)	56.5	177^{12}			vs bz, eth, EtOH, chl
4698	Endosulfan		$C_9H_6Cl_6O_3S$	115-29-7	406.925		106	$106^{0.7}$	1.745^{20}		
4699	Endosulfan sulfate		$C_9H_6Cl_6O_4S$	1031-07-8	422.925	cry (cyhex)	181				
4700	Endothall disodium		$C_8H_{10}Na_2O_5$	145-73-3	232.142		144		1.431^{20}		
4701	Endrin		$C_{12}H_8Cl_6O$	72-20-8	380.909	cry	dec 245				vs ace, bz, xyl; s ctc, hx
4702	Enflurane		$C_3H_2ClF_5O$	13838-16-9	184.492	liq		56.5	1.5121^{25}	1.3025^{20}	vs os
4703	Ephedrine, (±)	α-[1-(Methylamino)ethyl] benzenemethanol, (*R**,*S**)-(±)-	$C_{10}H_{15}NO$	90-81-3	165.232	nd (eth, peth)	76.5	135^{12}	1.1220^{20}		s H_2O, EtOH, eth, bz, chl
4704	*d*-Ephedrine	α-[1-(Methylamino)ethyl] benzenemethanol, [*S*-(*R**,*S**)]-	$C_{10}H_{15}NO$	321-98-2	165.232	pl (w)	40	225			s H_2O, EtOH, eth, bz, chl
4705	*l*-Ephedrine	α-[1-(Methylamino)ethyl] benzenemethanol, [*R*-(*R**,*S**)]-	$C_{10}H_{15}NO$	299-42-3	165.232	pl (w + 1)	40	225	1.0085^{22}		s H_2O, EtOH, eth, bz, chl
4706	Ephedrine hydrochloride	2-(Methylamino)-1-phenyl-1-propanol, hydrochloride	$C_{10}H_{16}ClNO$	50-98-6	201.693	orth nd	219		1.0208^{20}		
4707	Epichlorohydrin	(Chloromethyl)oxirane	C_3H_5ClO	13403-37-7	92.524	liq	-26	118; 62^{100}	1.1812^{20}	1.4358^{25}	sl H_2O; msc EtOH, eth; s bz, ctc
4708	Epinephrine	*D*-Adrenaline	$C_9H_{13}NO_3$	51-43-4	183.204	br (in air)	211.5				sl H_2O; i EtOH; s HOAc, acid
4709	Epiquinidine		$C_{20}H_{24}N_2O_2$	572-59-8	324.417	cry (AcOEt) lf (eth)	113				vs EtOH; s eth
4710	1,2-Epoxybutane	Ethyloxirane	C_4H_8O	106-88-7	72.106	liq	-150	63.4	0.8297^{20}	1.3851^{20}	vs EtOH, ace; msc eth
4711	1,2-Epoxy-4-(epoxyethyl) cyclohexane	4-Vinyl-1-cyclohexene dioxide	$C_8H_{12}O_2$	106-87-6	140.180		<-55	227	1.0966^{20}	1.4787^{20}	vs H_2O
4712	1,2-Epoxyhexadecane	Tetradecyloxirane	$C_{16}H_{32}O$	7320-37-8	240.424	hyg cry or liq	24.1	178^{12}	0.846	1.2240	
4713	1,2-Epoxyoctadecane	Hexadecyloxirane	$C_{18}H_{36}O$	7390-81-0	268.478	hyg cry	26.1	$137^{0.5}$			
4714	2,3-Epoxy-α-pinane		$C_{10}H_{16}O$	1686-14-2	152.233			85^{24}			
4715	2,3-Epoxypropyl acrylate	Glycidyl acrylate	$C_6H_8O_3$	106-90-1	128.126			53^{10}	1.1109^{20}	1.4490^{20}	vs bz
4716	2,3-Epoxypropyl methacrylate	Glycidol methacrylate	$C_7H_{10}O_3$	106-91-2	142.152			189; 75^{10}	1.042^{20}	1.448^{25}	vs bz, eth, EtOH
4717	Equol		$C_{14}H_{14}O_3$	531-95-3	230.259	cry (aq, al)	189.5				
4718	Ergocornine		$C_{31}H_{39}N_5O_5$	564-36-3	561.673	cry (MeOH)	183 dec				i H_2O; s EtOH, ace, bz, chl, AcOEt
4719	Ergocorninine		$C_{31}H_{39}N_5O_5$	564-37-4	561.673	lo pr (al)	228 dec				vs ace, bz, EtOH, chl
4720	Ergocristine		$C_{35}H_{39}N_5O_5$	511-08-0	609.716	orth (bz)	175 dec				i H_2O; s EtOH, ace, chl
4721	Ergocristinine		$C_{35}H_{39}N_5O_5$	511-07-9	609.716	pr (al)	237 dec				i H_2O; sl EtOH, ace, chl
4722	Ergocryptine		$C_{32}H_{41}N_5O_5$	511-09-1	575.699	pr (al)	213 dec				i H_2O; s EtOH, chl
4723	Ergocryptinine		$C_{33}H_{41}N_5O_5$	511-10-4	587.710	lo pr (al)	245 dec				vs ace, chl



Eicosane



Eicosanedioic acid



Eicosanoic acid



1-Eicosanol



5,8,11,14-Eicosatetraenoic acid, (all-*cis*)



1-Eicosene



cis-9-Eicosenoic acid



trans-9-Eicosenoic acid



11-Eicosenoic acid



Elaidic acid



Elaiomycin



1,3-Elemadien-11-ol



β-Elemene



Embelin



Emetine



Emylcamate



Enallylpropymal



Endosulfan



Endosulfan sulfate



Endothall disodium



Endrin



Enflurane



Ephedrine, (±)



d-Ephedrine


l-Ephedrine



Ephedrine hydrochloride



Epichlorohydrin



Epinephrine


Epiquinidine



1,2-Epoxybutane



1,2-Epoxy-4-(epoxyethyl)cyclohexane



1,2-Epoxyhexadecane



1,2-Epoxyoctadecane



2,3-Epoxy-α-pinane



2,3-Epoxypropyl acrylate



2,3-Epoxypropyl methacrylate



Equol



Ergocornine


Ergocorninine



Ergocristine



Ergocristinine



Ergocryptine



Ergocryptinine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4724	Ergometrinine		$C_{19}H_{23}N_3O_2$	479-00-5	325.405	pr (ace)	196 dec				vs chl
4725	Ergonovine	Ergometrine	$C_{19}H_{23}N_3O_2$	60-79-7	325.405	pl or nd	162 dec				s H_2O, ace; vs EtOH; sl chl
4726	Ergosine		$C_{30}H_{37}N_5O_5$	561-94-4	547.646	pr (MeOH, AcOEt)	228 dec				s ace, chl; sl MeOH
4727	Ergostane, (5α)		$C_{28}H_{50}$	511-20-6	386.697	lf or pl (ace, eth- MeOH)	85				vs ace, eth, chl
4728	Ergostane, (5β)	Coproergostane	$C_{28}H_{50}$	511-21-7	386.697	nd (ace)	64				vs eth, chl
4729	Ergostan-3-ol, (3β,5α)	Ergostanol	$C_{28}H_{50}O$	6538-02-9	402.696	nd (MeOH-eth)	144.5				i H_2O; s eth, chl
4730	Ergosta-5,7,9(11),22-tetraen-3-ol, (3β,22*E*)	Dehydroergosterol	$C_{28}H_{42}O$	516-85-8	394.632	lf (al) nd (eth),pl (al)	146	$230^{0.5}$			vs ace, bz, eth, EtOH
4731	Ergosta-5,7,22-trien-3-ol, (3β,22*E*)	Ergosterol	$C_{28}H_{44}O$	57-87-4	396.648	pl (+w, al) nd (eth)	170	$250^{0.01}$			i H_2O; sl EtOH, eth, peth; s bz, chl
4732	Ergosta-5,7,22-trien-3-ol, (3β,10α,22*E*)	Pyrocalciferol	$C_{28}H_{44}O$	128-27-8	396.648	nd (MeOH)	94				i H_2O; s EtOH, chl, MeOH
4733	Ergosta-5,7,22-trien-3-ol, (3β,9β,10α,22*E*)	Lumisterol	$C_{28}H_{44}O$	474-69-1	396.648	nd (ace-MeOH)	118				i H_2O; s EtOH, HOAc; vs eth, ace, chl
4734	Ergost-5-en-3-ol, (3β,24*R*)	Campesterol	$C_{28}H_{48}O$	474-62-4	400.680	cry (ace)	157.5				
4735	Ergost-7-en-3-ol, (3β,5α)	γ-Ergostenol	$C_{28}H_{48}O$	516-78-9	400.680	nd (MeOH) cry (PrOH	146				s eth
4736	Ergost-8(14)-en-3-ol, (3β,5α)	α-Ergostenol	$C_{28}H_{48}O$	632-32-6	400.680	lf or nd (MeOH)	131				sl EtOH; s eth, bz, chl
4737	Ergotamine		$C_{33}H_{55}N_5O_5$	113-15-5	601.821	nd (al), pr (bz) pl (ace)	213 dec				vs bz, eth, chl
4738	Ergotamine tartrate (2:1)	Gynergen	$C_{35}H_{39}N_5O_8$	379-79-3	656.706		192 dec				
4739	Ergotaminine		$C_{33}H_{35}N_5O_5$	639-81-6	581.662	orth pl (MeOH) pl (al)	252 dec				i H_2O; sl EtOH, ace, bz; s chl; vs py
4740	Ergothioneine		$C_9H_{15}N_3O_2S$	497-30-3	229.299	nd or lf (dil EtOH)	290 dec				vs H_2O; sl EtOH, ace; i eth, bz, chl
4741	Eriochrome Black T		$C_{20}H_{12}N_3NaO_7S$	1787-61-7	461.380	br-blk pow					s H_2O, EtOH, MeOH
4742	Eriodictyol	3',4',5,7-Tetrahydroxyflavanone, (*S*)	$C_{15}H_{12}O_6$	552-58-9	288.252	pl or nd (EtOH)	267 dec				vs EtOH, HOAc
4743	Erythorbic acid	Isoascorbic acid	$C_6H_8O_6$	89-65-6	176.124	gran cry	168				s H_2O, py; sl ace
4744	β-Erythroidine		$C_{16}H_{19}NO_3$	466-81-9	273.327	cry (al)	99.5				s H_2O, eth, chl; vs EtOH, bz
4745	Erythromycin	Propiocine	$C_{37}H_{67}NO_{13}$	114-07-8	733.927	cry (w)	191				vs ace, eth, EtOH, chl
4746	Erythromycin ethyl succinate		$C_{43}H_{75}NO_{16}$	1264-62-6	862.053	cry (ace aq)	222				
4747	Erythromycin stearate		$C_{55}H_{103}NO_{15}$	643-22-1	1018.405	cry	92				i H_2O; sl EtOH, eth, chl
4748	Erythrophleine	Norcassamidine	$C_{24}H_{39}NO_5$	36150-73-9	421.571	glass	115				s H_2O, EtOH
4749	*D*-Erythrose		$C_4H_8O_4$	583-50-6	120.105	syr					s H_2O; vs EtOH
4750	*L*-Erythrose		$C_4H_8O_4$	533-49-3	120.105	syr					vs H_2O, EtOH
4751	*D*-Erythrose 4-phosphate	2,3-Dihydroxy-4-(phosphonooxy)butanal	$C_4H_9O_7P$	585-18-2	200.084	stab in aq soln only					s H_2O
4752	Erythrosine		$C_{20}H_8I_4O_5$	15905-32-5	835.893	br pow (Na salt)					s H_2; vs eth, EtOH
4753	*L*-Erythrulose		$C_4H_8O_4$	533-50-6	120.105	syr	dec	dec			vs H_2O, EtOH
4754	Esaprazole	*N*-Cyclohexyl-1-piperazineacetamide	$C_{12}H_{23}N_3O$	64204-55-3	225.330		112	$190^{0.5}$			
4755	Esculin	6-(β-*D*-Glucopyranosyloxy)-7-hydroxy-2*H*-1-benzopyran-2-one	$C_{15}H_{16}O_9$	531-75-9	340.283	pr (w+2)	205 (pentahydrate)				sl H_2O, EtOH, eth; s chl, py, HOAc
4756	Eserine sulfate	Physostigmine sulfate	$C_{30}H_{44}N_6O_8S$	64-47-1	648.770	hyg cry (ace-eth)	141				vs ace, EtOH
4757	Estra-1,3,5(10)-triene-3,17-diol, (17α)	α-Estradiol	$C_{18}H_{24}O_2$	57-91-0	272.383	nd (+1/2 w) (80% al)	221.5				i H_2O; s EtOH, ace; sl eth, bz
4758	Estra-1,3,5(10)-triene-3,17-diol (17β)	β-Estradiol	$C_{18}H_{24}O_2$	50-28-2	272.383	pr (80% al),	178.5				vs ace, EtOH, Diox
4759	Estra-1,3,5(10)-triene-3,17-diol, (8α,17β)	Isoestradiol	$C_{18}H_{24}O_2$	517-04-4	272.383	cry (dil MeOH-chl)	181				s EtOH, diox
4760	Estra-1,3,5(10)-triene-3,17-diol 3-benzoate, (17β)	Estradiol benzoate	$C_{25}H_{28}O_3$	50-50-0	376.488		196				
4761	Estra-1,3,5(10)-triene-3,16,17-triol, (16α,17β)	Estriol	$C_{18}H_{24}O_3$	50-27-1	288.382	lf (al), mcl (dil al)	288 dec		1.27^{25}		s EtOH; sl eth, bz, tfa; vs py
4762	Estra-1,3,5(10)-triene-3,16,17-triol, (16β,17β)	16-Epiestriol	$C_{18}H_{24}O_3$	547-81-9	288.382	cry (MeOH-bz)	290				



Ergometrinine



Ergonovine



Ergosine



Ergostane, (5α)



Ergostane, (5β)



Ergostan-3-ol, (3β,5α)



Ergosta-5,7,9(11),22-tetraen-3-ol, (3β,22*E*)



Ergosta-5,7,22-trien-3-ol, (3β,22*E*)



Ergosta-5,7,22-trien-3-ol, (3β,10α,22*E*)



Ergosta-5,7,22-trien-3-ol, (3β,9β,10α,22*E*)



Ergost-5-en-3-ol, (3β,24*R*)



Ergost-7-en-3-ol, (3β,5α)



Ergost-8(14)-en-3-ol, (3β,5α)



Ergotamine



Ergotamine tartrate (2:1)



Ergotaminine



Ergothioneine



Eriochrome Black T



Eriodictyol



Erythorbic acid



β-Erythroidine



Erythromycin



Erythromycin ethyl succinate



Erythromycin stearate





Erythrophleine



D-Erythrose / *L*-Erythrose



D-Erythrose 4-phosphate



Erythrosine



L-Erythrulose



Esaprazole



Esculin



Eserine sulfate



Estra-1,3,5(10)-triene-3,17-diol, (17α)


Estra-1,3,5(10)-triene-3,17-diol (17β)



Estra-1,3,5(10)-triene-3,17-diol, (8α,17β)



Estra-1,3,5(10)-triene-3,17-diol 3-benzoate, (17β)



Estra-1,3,5(10)-triene-3,16,17-triol, (16α,17β)



Estra-1,3,5(10)-triene-3,16,17-triol, (16β,17β)

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4763	Estrone		$C_{18}H_{22}O_2$	53-16-7	270.367	mcl, orth (al)	260.2		1.236^{25}		i H_2O; sl EtOH, eth, bz; s ace, diox
4764	Ethacrynic acid		$C_{13}H_{12}Cl_2O_4$	58-54-8	303.138		122.5				
4765	Ethalfluralin		$C_{13}H_{14}F_3N_3O_4$	55283-68-6	333.263		57	dec 256			
4766	Ethambutol		$C_{10}H_{24}N_2O_2$	74-55-5	204.310	cry	89				sl H_2O; s bz, chl
4767	Ethane		C_2H_6	74-84-0	30.069	col gas	-182.79	-88.6	0.5446^{-89}		i H_2O; vs bz
4768	Ethanearsonic acid		$C_2H_7AsO_3$	507-32-4	153.997	nd (al), orth nd (w)	99.5	210^{12}			vs H_2O, EtOH
4769	Ethanedial dioxime		$C_2H_4N_2O_2$	557-30-2	88.065	orth pl (w)	178 dec	sub			vs H_2O, EtOH, eth
4770	1,2-Ethanediamine	Ethylenediamine	$C_2H_8N_2$	107-15-3	60.098		11.14	117	0.8979^{20}	1.4565^{20}	vs H_2O; msc EtOH; i eth, bz; s ctc
4771	1,2-Ethanediamine, dihydrochloride	Ethylenediamine dihydrochloride	$C_2H_{10}Cl_2N_2$	333-18-6	133.019					1.633	vs H_2O
4772	1,2-Ethanediol	Ethylene glycol	$C_2H_6O_2$	107-21-1	62.068	liq	-12.69	197.3	1.1135^{20}	1.4318^{20}	msc H_2O, EtOH, ace; s eth, chl; sl bz
4773	1,2-Ethanediol, bis(4-methylbenzenesulfonate)		$C_{16}H_{18}O_6S_2$	6315-52-2	370.440	cry (bz)	128				
4774	1,1-Ethanediol, diacetate	Ethylidene diacetate	$C_6H_{10}O_4$	542-10-9	146.141		18.9	169	1.070^{25}	1.3985^{25}	vs eth, EtOH
4775	1,2-Ethanediol, diacetate	Ethylene glycol diacetate	$C_6H_{10}O_4$	111-55-7	146.141	liq	-31	190	1.1043^{20}	1.4159^{20}	vs H_2O; msc EtOH, eth, ace, bz, CS_2
4776	1,2-Ethanediol, diacrylate	Ethylene glycol diacrylate	$C_8H_{10}O_4$	2274-11-5	170.163	liq		$55^{0.6}$	1.0935^{26}		
4777	1,2-Ethanediol, dibenzoate	Ethylene glycol dibenzoate	$C_{16}H_{14}O_4$	94-49-5	270.280	orth pr (eth)	73.5	dec 360			i H_2O; s eth, chl
4778	1,2-Ethanediol, didodecanoate	Ethylene glycol didodecanoate	$C_{26}H_{50}O_4$	624-04-4	426.673	pl (al)	56.6	188^{20}			vs eth, EtOH
4779	1,2-Ethanediol, diformate	Ethylene glycol diformate	$C_4H_6O_4$	629-15-2	118.089			174	1.193^{0}	1.3580	sl H_2O; s EtOH, eth
4780	1,2-Ethanediol, dihexadecanoate	Ethylene glycol dipalmitate	$C_{34}H_{66}O_4$	624-03-3	538.886	lf or nd (al-chl)	72		0.8594^{78}		i H_2O, EtOH; s eth; vs ace
4781	1,2-Ethanediol, dimethacrylate	Ethylene glycol dimethacrylate	$C_{10}H_{14}O_4$	97-90-5	198.216	liq	-40	260	1.053^{20}	1.4532^{25}	vs bz, EtOH, lig
4782	1,2-Ethanediol, dinitrate	Ethylene glycol dinitrate	$C_2H_4N_2O_6$	628-96-6	152.062	ye liq	-22.3	198.5	1.4918^{20}		vs eth, EtOH
4783	1,2-Ethanediol, distearate	Ethylene glycol distearate	$C_{38}H_{74}O_4$	627-83-8	594.993	lf	79	241^{20}	0.8581^{78}		i H_2O, EtOH; vs eth, ace
4784	1,2-Ethanediol, ditetradecanoate	Ethylene glycol ditetradecanoate	$C_{30}H_{58}O_4$	627-84-9	482.780	cry (eth, ace)	65	208^{20}	0.8600^{80}		i H_2O, EtOH; s eth; vs ace, bz, ctc
4785	1,2-Ethanediol, dithiocyanate	Ethylene glycol dithiocyanate	$C_4H_4N_2S_2$	629-17-4	144.218	orth pl or nd (w)	90	dec	1.4200^{0}		sl H_2O, bz; s EtOH, eth; vs ace
4786	1,2-Ethanediol, monoacetate	Ethylene glycol monoacetate	$C_4H_8O_3$	542-59-6	104.105			188	1.108^{15}		msc H_2O, EtOH, eth
4787	1,2-Ethanediol, monobenzoate	Ethylene glycol monobenzoate	$C_9H_{10}O_3$	94-33-7	166.173		45	150^{10}	1.1101^{30}		vs EtOH
4788	1,2-Ethanediol, monostearate	Ethylene glycol monostearate	$C_{20}H_{40}O_3$	111-60-4	328.530	cry (peth)	60.5	190^{3}	0.8780^{60}	1.4310^{60}	sl EtOH; s eth
4789	1,2-Ethanediol, monosulfite	Ethylene glycol monosulfite	$C_2H_4O_3S$	3741-38-6	108.116	liq	-11	173	1.4402^{20}	1.4463^{20}	vs H_2O, EtOH, eth, ace, bz, AcOEt; sl chl
4790	1,2-Ethanediphosphonic acid	1,2-Diphosphonoethane	$C_2H_8O_6P_2$	6145-31-9	190.029	nd (EtOH/eth)	223				
4791	1,2-Ethanedisulfonic acid	Ethylene disulfonic acid	$C_2H_6O_6S_2$	110-04-3	190.195		173				vs diox
4792	Ethanedithioamide	Rubeanic acid	$C_2H_4N_2S_2$	79-40-3	120.196	red cry	170 dec				sl H_2O, EtOH; s con sulf
4793	1,2-Ethanedithiol	Ethylene dimercaptan	$C_2H_6S_2$	540-63-6	94.199	liq	-41.2	146.1	1.234^{20}	1.5590^{20}	i H_2O; s EtOH, eth, ace, bz; vs alk
4794	1,2-Ethanediyl mercaptoacetate		$C_6H_{10}O_4S_2$	123-81-9	210.271			$138^{1.5}$			
4795	Ethanesulfonic acid	Ethylsulfonic acid	$C_2H_6O_3S$	594-45-6	110.132	hyg	-17	123^{1}	1.3341^{25}	1.4335^{20}	vs H_2O, EtOH
4796	Ethanesulfonyl chloride		$C_2H_5ClO_2S$	594-44-5	128.578	pa ye		174	1.357^{22}	1.4531^{20}	vs eth; s CS_2
4797	Ethanethiol	Ethyl mercaptan	C_2H_6S	75-08-1	62.134	liq	-147.88	35.0	0.8315^{25}	1.4310^{20}	sl H_2O; s EtOH, eth, ace, dil alk
4798	Ethanimidamide		$C_2H_6N_2$	143-37-3	58.082		-35				sl H_2O; s EtOH, acid
4799	Ethanimidamide monohydrochloride	Acetamidine hydrochloride	$C_2H_7ClN_2$	124-42-5	94.543	nd or pr (al) hyg lo pr (al)	177.5				vs H_2O, EtOH
4800	Ethanol	Ethyl alcohol	C_2H_6O	64-17-5	46.068	liq	-114.14	78.29	0.7893^{20}	1.3611^{20}	msc H_2O, EtOH, eth, ace, chl; s bz
4801	Ethanolamine	Glycinol	C_2H_7NO	141-43-5	61.083		10.5	171	1.0180^{20}	1.4541^{20}	msc H_2O, EtOH; sl eth, lig, bz; s chl
4802	Ethanolamine hydrochloride	2-Aminoethanol hydrochloride	C_2H_8ClNO	2002-24-6	97.544	hyg cry (EtOH)	85				


Estrone



Ethacrynic acid



Ethalfluralin



Ethambutol



Ethane



Ethanearsonic acid



Ethanedial dioxime



1,2-Ethanediamine



1,2-Ethanediamine, dihydrochloride



1,2-Ethanediol



1,2-Ethanediol, bis(4-methylbenzenesulfonate)



1,1-Ethanediol, diacetate



1,2-Ethanediol, diacetate



1,2-Ethanediol, diacrylate



1,2-Ethanediol, dibenzoate



1,2-Ethanediol, didodecanoate



1,2-Ethanediol, diformate



1,2-Ethanediol, dihexadecanoate



1,2-Ethanediol, dimethacrylate



1,2-Ethanediol, dinitrate



1,2-Ethanediol, distearate


1,2-Ethanediol, ditetradecanoate



1,2-Ethanediol, dithiocyanate



1,2-Ethanediol, monoacetate



1,2-Ethanediol, monobenzoate



1,2-Ethanediol, monostearate



1,2-Ethanediol, monosulfite



1,2-Ethanediphosphonic acid



1,2-Ethanedisulfonic acid


Ethanedithioamide


1,2-Ethanedithiol



1,2-Ethanediyl mercaptoacetate


Ethanesulfonic acid



Ethanesulfonyl chloride



Ethanethiol


Ethanimidamide



Ethanimidamide monohydrochloride



Ethanol



Ethanolamine



Ethanolamine hydrochloride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4803	Ethanolamine *O*-sulfate	2-Aminoethyl sulfate	$C_2H_7NO_4S$	926-39-6	141.147		230 dec				s H_2O; i EtOH
4804	Ethaverine	1-[(3,4-Diethoxyphenyl)methyl]-6,7-diethoxyisoquinoline	$C_{24}H_{29}NO_4$	486-47-5	395.492		100				i H_2O; s EtOH; sl eth, chl
4805	Ethchlorvynol	1-Chloro-3-ethyl-1-penten-4-yn-ol	C_7H_9ClO	113-18-8	144.598	liq		181; $30^{0.1}$	1.07^{25}	1.474^{25}	i H_2O; s os
4806	Ethephon	Phosphonic acid, (2-chloroethyl)-	$C_2H_6ClO_3P$	16672-87-0	144.494		74		1.2		
4807	Ethinylestradiol	19-Norpregna-1,3,5(10)-trien-20-yne-3,17-diol, (17α)-	$C_{20}H_{24}O_2$	57-63-6	296.404						sl chl
4808	Ethion		$C_9H_{22}O_4P_2S_4$	563-12-2	384.476		-13	$165^{0.3}$	1.22^{20}		
4809	*D*-Ethionine	3-Ethylhomocysteine, (*R*)	$C_6H_{13}NO_2S$	535-32-0	163.238	cry (H_2O)	278 dec				
4810	*L*-Ethionine	3-Ethylhomocysteine, (*S*)	$C_6H_{13}NO_2S$	13073-35-3	163.238	cry (H_2O)	273 dec				
4811	Ethirimol	4(1*H*)-Pyrimidinone, 5-butyl-2-(ethylamino)-6-methyl-	$C_{11}H_{19}N_3O$	23947-60-6	209.288		160		1.21^{25}		
4812	Ethisterone		$C_{21}H_{28}O_2$	434-03-7	312.446		272				
4813	Ethoate-methyl		$C_6H_{14}NO_3PS_2$	116-01-8	243.284	cry (tol/hp)	67				
4814	Ethofumesate		$C_{13}H_{18}O_5S$	26225-79-6	286.344		71		1.14		
4815	Ethoheptazine	4-Carbethoxymethyl-4-phenylazacycloheptane	$C_{16}H_{23}NO_2$	77-15-6	261.360	liq		134^{1}	1.038^{26}	1.5210^{26}	
4816	Ethoprop	Phosphorodithioic acid, *O*-ethyl *S,S*-dipropyl ester	$C_8H_{19}O_2PS_2$	13194-48-4	242.340			$88^{0.2}$	1.094^{20}		
4817	Ethotoin		$C_{11}H_{12}N_2O_2$	86-35-1	204.225	pr (w)	94				s hot H_2O; vs EtOH, bz, eth
4818	Ethoxyacetic acid		$C_4H_8O_3$	627-03-2	104.105			206.5	1.1021^{20}	1.4194^{20}	vs H_2O, EtOH, eth; s chl
4819	4'-Ethoxyacetophenone		$C_{10}H_{12}O_2$	1676-63-7	164.201	pl (eth)	39	268			vs eth, EtOH
4820	Ethoxyacetylene		C_4H_6O	927-80-0	70.090			50	0.8000^{20}	1.3796^{20}	
4821	7-Ethoxy-3,9-acridinediamine	Ethacridine	$C_{15}H_{15}N_3O$	442-16-0	253.299	ye nd	226				
4822	2-Ethoxyaniline	*o*-Phenetidine	$C_8H_{11}NO$	94-70-2	137.179		<-21	232.5		1.5560^{20}	sl H_2O, ctc; s EtOH, eth
4823	3-Ethoxyaniline	*m*-Phenetidine	$C_8H_{11}NO$	621-33-0	137.179			248			vs eth, EtOH
4824	4-Ethoxyaniline	*p*-Phenetidine	$C_8H_{11}NO$	156-43-4	137.179		1.2	254	1.0652^{16}	1.5528^{20}	sl H_2O; s EtOH, eth, chl
4825	2-Ethoxybenzaldehyde		$C_9H_{10}O_2$	613-69-4	150.174		21	248			msc EtOH, eth; sl chl
4826	4-Ethoxybenzaldehyde		$C_9H_{10}O_2$	10031-82-0	150.174		13.5	249	1.08^{21}		vs EtOH, eth, bz
4827	2-Ethoxybenzamide	Ethenzamide	$C_9H_{11}NO_2$	938-73-8	165.189	nd (w, al)	133				sl H_2O, chl; vs EtOH, eth
4828	Ethoxybenzene	Phenetole	$C_8H_{10}O$	103-73-1	122.164	liq	-29.43	169.81	0.9651^{20}	1.5076^{20}	i H_2O; s EtOH, eth, ctc
4829	4-Ethoxy-1,2-benzenediamine		$C_8H_{12}N_2O$	1197-37-1	152.193		71.5	295			vs H_2O; s EtOH, eth, chl
4830	2-Ethoxybenzoic acid		$C_9H_{10}O_3$	134-11-2	166.173		20.7	211^{39}			sl H_2O, EtOH, ctc
4831	4-Ethoxybenzoic acid		$C_9H_{10}O_3$	619-86-3	166.173	nd (w)	198.5				sl H_2O, tfa; s EtOH, eth, bz
4832	6-Ethoxy-2-benzothiazolesulfonamide	Ethoxzolamide	$C_9H_{10}N_2O_3S_2$	452-35-7	258.316		189				
4833	3-Ethoxy-*N,N*-diethylaniline		$C_{12}H_{19}NO$	1864-92-2	193.285			286; $97^{0.6}$		1.5325^{25}	s EtOH, bz, HOAc
4834	2-Ethoxy-3,4-dihydro-2*H*-pyran		$C_7H_{12}O_2$	103-75-3	128.169			132; 42^{16}	0.9658^{25}	1.4394^{20}	
4835	6-Ethoxy-1,2-dihydro-2,2,4-trimethylquinoline	Ethoxyquin	$C_{14}H_{19}NO$	91-53-2	217.307			124^{2}	1.026^{25}	1.569^{25}	
4836	Ethoxydimethylsilane	Dimethylethoxysilane	$C_4H_{12}OSi$	14857-34-2	104.223	liq		54	0.76^{20}		
4837	2-Ethoxy-1,2-diphenylethanone		$C_{16}H_{16}O_2$	574-09-4	240.297	nd (lig)	62	194^{20}	1.1016^{17}	1.5727^{17}	vs bz, eth, EtOH, lig
4838	2-Ethoxyethanamine		$C_4H_{11}NO$	110-76-9	89.136			107	0.8512^{20}	1.4101^{20}	msc H_2O, EtOH, eth; s ace, bz; sl chl
4839	2-Ethoxyethanol	Ethylene glycol monoethyl ether	$C_4H_{10}O_2$	110-80-5	90.121	liq	-70	135	0.9253^{25}	1.4054^{25}	vs H_2O, ace, eth, EtOH
4840	2-(2-Ethoxyethoxy)ethyl 2-propenoate	Diethylene glycol ethyl ether acrylate	$C_9H_{16}O_4$	7328-17-8	188.221				1.13^{25}		
4841	2-Ethoxyethyl acetate	Ethylene glycol monoethyl ether acetate	$C_6H_{12}O_3$	111-15-9	132.157	liq	-61.7	156.4	0.9740^{20}	1.4054^{20}	vs H_2O, ace, eth, EtOH
4842	2-Ethoxyethyl acrylate	Ethylene glycol monoethyl ether acrylate	$C_7H_{12}O_3$	106-74-1	144.168	liq	-47	174	0.983^{20}	1.4274^{20}	
4843	3-Ethoxy-2-hydroxybenzaldehyde		$C_9H_{10}O_3$	492-88-6	166.173		65.3	264			
4844	3-Ethoxy-4-hydroxybenzaldehyde	Ethyl vanillin	$C_9H_{10}O_3$	121-32-4	166.173		77.5	285			sl H_2O; s EtOH, eth, bz, chl
4845	4-Ethoxy-3-methoxybenzaldehyde		$C_{10}H_{12}O_3$	120-25-2	180.200	mcl pr	64.5	168^{13}			sl H_2O; s EtOH, eth, bz, chl, HOAc
4846	1-Ethoxy-2-methoxyethane		$C_5H_{12}O_2$	5137-45-1	104.148	liq		103.5	0.8460^{25}	1.3843^{25}	



Ethanolamine *O*-sulfate



Ethaverine



Ethchlorvynol



Ethephon



Ethinylestradiol



Ethion



D-Ethionine



L-Ethionine



Ethirimol



Ethisterone



Ethoate-methyl



Ethofumesate



Ethoheptazine



Ethoprop



Ethotoin



Ethoxyacetic acid



4'-Ethoxyacetophenone



Ethoxyacetylene



7-Ethoxy-3,9-acridinediamine



2-Ethoxyaniline



3-Ethoxyaniline



4-Ethoxyaniline



2-Ethoxybenzaldehyde



4-Ethoxybenzaldehyde



2-Ethoxybenzamide



Ethoxybenzene



4-Ethoxy-1,2-benzenediamine



2-Ethoxybenzoic acid



4-Ethoxybenzoic acid



6-Ethoxy-2-benzothiazolesulfonamide



3-Ethoxy-*N*,*N*-diethylaniline



2-Ethoxy-3,4-dihydro-2*H*-pyran



6-Ethoxy-1,2-dihydro-2,2,4-trimethylquinoline



Ethoxydimethylsilane



2-Ethoxy-1,2-diphenylethanone



2-Ethoxyethanamine



2-Ethoxyethanol



2-(2-Ethoxyethoxy)ethyl 2-propenoate



2-Ethoxyethyl acetate


2-Ethoxyethyl acrylate



3-Ethoxy-2-hydroxybenzaldehyde



3-Ethoxy-4-hydroxybenzaldehyde



4-Ethoxy-3-methoxybenzaldehyde



1-Ethoxy-2-methoxyethane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4847	1-Ethoxy-3-methylbenzene		$C_9H_{12}O$	621-32-9	136.190			192	0.949^{20}	1.513^{20}	i H_2O; s EtOH, eth
4848	1-Ethoxy-4-methylbenzene		$C_9H_{12}O$	622-60-6	136.190			188.5	0.9509^{18}	1.5058^{18}	i H_2O; s EtOH, eth; sl ctc
4849	2-Ethoxy-2-methylbutane	Ethyl *tert*-pentyl ether	$C_7H_{16}O$	919-94-8	116.201			102	0.751^{18}		vs eth, EtOH
4850	(Ethoxymethylene)propanedinitrile		$C_6H_6N_2O$	123-06-8	122.124		66	160^{12}			s EtOH, eth; sl chl
4851	(Ethoxymethyl)oxirane	2,3-Epoxypropyl ethyl ether	$C_5H_{10}O_2$	4016-11-9	102.132			128	0.9700^{20}	1.4320^{20}	s H_2O, EtOH, eth; sl ctc
4852	1-Ethoxynaphthalene		$C_{12}H_{12}O$	5328-01-8	172.222	nd	5.5	280.5	1.060^{20}	1.5953^{25}	i H_2O; vs EtOH, eth
4853	2-Ethoxynaphthalene		$C_{12}H_{12}O$	93-18-5	172.222	pl (al)	37.5	282	1.0640^{20}	1.5975^{36}	i H_2O; s EtOH, eth, tol, lig, CS_2
4854	2-Ethoxy-5-nitroaniline	5-Nitro-*o*-phenetidine	$C_8H_{10}N_2O_3$	136-79-8	182.176	ye nd (dil al)	96.5	205^{14}			vs eth, EtOH
4855	1-Ethoxy-2-nitrobenzene		$C_8H_9NO_3$	610-67-3	167.162	br ye	1.1	267	1.1903^{15}	1.5425^{20}	vs eth, EtOH
4856	1-Ethoxy-4-nitrobenzene		$C_8H_9NO_3$	100-29-8	167.162	pr (dil al, eth)	60	283	1.1176^{100}		sl H_2O, EtOH; vs eth; msc ace, bz; s peth
4857	*N*-(4-Ethoxy-3-nitrophenyl) acetamide		$C_{10}H_{12}N_2O_4$	1777-84-0	224.213	nd (dil al)	124.0				vs ace, bz, EtOH
4858	2-Ethoxyphenol	Catechol monoethyl ether	$C_8H_{10}O_2$	94-71-3	138.164		29	217	1.0903^{25}		sl H_2O, ctc; msc EtOH, eth
4859	3-Ethoxyphenol	Resorcinol monoethyl ether	$C_8H_{10}O_2$	621-34-1	138.164			246; 131^{10}	1.105^{15}		i H_2O; s EtOH, eth, bz; sl chl
4860	4-Ethoxyphenol	Hydroquinone monoethyl ether	$C_8H_{10}O_2$	622-62-8	138.164	pr or lf (w)	66.5	246.5			sl H_2O; vs EtOH, eth; s chl
4861	*N*-(2-Ethoxyphenyl)acetamide		$C_{10}H_{13}NO_2$	581-08-8	179.216	lf(dil al)	79	>240			i H_2O; s EtOH, eth, chl
4862	*N*-(4-Ethoxyphenyl)acetamide	Phenacetin	$C_{10}H_{13}NO_2$	62-44-2	179.216	mcl pr	137.5			1.571	sl H_2O, eth, bz; s EtOH, ace; vs py
4863	*N*-(4-Ethoxyphenyl)-2-hydroxypropanamide	*p*-Lactophenetide	$C_{11}H_{15}NO_3$	539-08-2	209.242		118				s H_2O; vs EtOH; sl eth, bz, chl, peth
4864	(4-Ethoxyphenyl)urea	Dulcin	$C_9H_{12}N_2O_2$	150-69-6	180.203	lf (dil al), pl (w)	173.5	dec			sl H_2O; s EtOH; vs AcOEt
4865	3-Ethoxypropanal		$C_5H_{10}O_2$	2806-85-1	102.132			135.2	0.9165^{20}		
4866	3-Ethoxypropanenitrile		C_5H_9NO	2141-62-0	99.131			171	0.9285^{15}	1.4068^{20}	vs eth, EtOH
4867	8-Ethoxy-5-quinolinesulfonic acid	Actinoquinol	$C_{11}H_{11}NO_4S$	15301-40-3	253.275	br nd (w)	286 dec				s alk
4868	Ethoxytrimethylsilane		$C_5H_{14}OSi$	1825-62-3	118.250			76	0.7573^{20}	1.3741^{20}	i H_2O; s EtOH, eth, ace
4869	Ethoxytriphenylsilane		$C_{20}H_{20}OSi$	1516-80-9	304.458		65	344			s chl
4870	*N*-Ethylacetamide		C_4H_9NO	625-50-3	87.120			205; 104^{18}	0.942^{4}	1.4338^{20}	msc H_2O, EtOH; s chl, HOAc
4871	Ethyl acetate		$C_4H_8O_2$	141-78-6	88.106	liq	-83.8	77.11	0.9003^{20}	1.3723^{20}	s H_2O; msc EtOH, eth; vs ace, bz
4872	Ethyl acetoacetate		$C_6H_{10}O_3$	141-97-9	130.141	liq	-45	180.8	1.0368^{10}	1.4171^{20}	s H_2O; msc EtOH, eth; s bz, chl
4873	4'-Ethylacetophenone		$C_{10}H_{12}O$	937-30-4	148.201			114^{11}			
4874	Ethyl 2-acetylhexanoate		$C_{10}H_{18}O_3$	1540-29-0	186.248			221.5	0.9523^{20}	1.4301^{20}	vs ace, eth
4875	Ethyl 2-acetyl-3-methylbutanoate		$C_9H_{16}O_3$	1522-46-9	172.221			201; 97^{20}	0.9648^{18}	1.4256^{18}	i H_2O; msc EtOH, eth
4876	Ethyl 2-acetylpentanoate		$C_9H_{16}O_3$	1540-28-9	172.221			224; 90^{15}	0.9661^{20}	1.4255^{20}	vs eth, EtOH
4877	Ethyl 2-acetyl-4-pentenoate	Ethyl 2-allylacetoacetate	$C_9H_{14}O_3$	610-89-9	170.205			208	0.9898^{20}	1.4388^{18}	msc EtOH, eth, bz
4878	Ethyl acrylate	Ethyl propenoate	$C_5H_8O_2$	140-88-5	100.117	liq	-71.2	99.4	0.9234^{20}	1.4068^{20}	sl H_2O, DMSO; msc EtOH, eth; s chl
4879	Ethylamine	Ethanamine	C_2H_7N	75-04-7	45.084	vol liq or gas	-80.5	16.5	0.677^{25} (p>1 atm)	1.3663^{20}	msc H_2O, EtOH, eth
4880	Ethylamine hydrochloride	Ethanamine hydrochloride	C_2H_8ClN	557-66-4	81.545	mcl pl (al)	109.5		1.2160^{20}		vs H_2O, EtOH
4881	Ethyl 2-aminoacetate	Glycine, ethyl ester	$C_4H_9NO_2$	459-73-4	103.120			149; 58^{18}	1.0275^{10}	1.4242^{10}	msc H_2O, EtOH, eth, ace, bz; vs lig
4882	Ethyl 2-aminobenzoate		$C_9H_{11}NO_2$	87-25-2	165.189		13	268	1.1174^{20}	1.5646^{20}	vs eth, EtOH
4883	Ethyl 3-aminobenzoate		$C_9H_{11}NO_2$	582-33-2	165.189			294; 160^{5}	1.171^{20}	1.5600^{22}	sl H_2O; vs EtOH, eth; s ctc
4884	Ethyl 4-aminobenzoate	Ethyl aminobenzoate	$C_9H_{11}NO_2$	94-09-7	165.189	nd (w), orth (eth)	92	310			i H_2O; vs EtOH, eth; s chl, acid
4885	Ethyl (aminocarbonyl)carbamate		$C_4H_8N_2O_3$	626-36-8	132.118	nd (w, bz)	196.5	dec			i H_2O, eth; sl EtOH, bz, tfa



1-Ethoxy-3-methylbenzene



1-Ethoxy-4-methylbenzene



2-Ethoxy-2-methylbutane



(Ethoxymethylene)propanedinitrile



(Ethoxymethyl)oxirane



1-Ethoxynaphthalene



2-Ethoxynaphthalene



2-Ethoxy-5-nitroaniline



1-Ethoxy-2-nitrobenzene



1-Ethoxy-4-nitrobenzene



N-(4-Ethoxy-3-nitrophenyl)acetamide



2-Ethoxyphenol



3-Ethoxyphenol


4-Ethoxyphenol



N-(2-Ethoxyphenyl)acetamide



N-(4-Ethoxyphenyl)acetamide


N-(4-Ethoxyphenyl)-2-hydroxypropanamide



(4-Ethoxyphenyl)urea



3-Ethoxypropanal



3-Ethoxypropanenitrile



8-Ethoxy-5-quinolinesulfonic acid



Ethoxytrimethylsilane



Ethoxytriphenylsilane



N-Ethylacetamide



Ethyl acetate



Ethyl acetoacetate



4'-Ethylacetophenone


Ethyl 2-acetylhexanoate



Ethyl 2-acetyl-3-methylbutanoate



Ethyl 2-acetylpentanoate



Ethyl 2-acetyl-4-pentenoate



Ethyl acrylate



Ethylamine



Ethylamine hydrochloride


Ethyl 2-aminoacetate



Ethyl 2-aminobenzoate



Ethyl 3-aminobenzoate



Ethyl 4-aminobenzoate



Ethyl (aminocarbonyl)carbamate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4886	2-(Ethylamino)ethanol		$C_4H_{11}NO$	110-73-6	89.136			169.5	0.914^{20}	1.444^{20}	vs H_2O, EtOH, eth; s chl
4887	2-Ethylaniline		$C_8H_{11}N$	578-54-1	121.180	liq	-43	209.5	0.983^{22}	1.5584^{22}	sl H_2O, chl; vs EtOH, eth
4888	3-Ethylaniline		$C_8H_{11}N$	587-02-0	121.180	liq	-64	214; 94^{6}	0.9896^{25}		vs eth, EtOH
4889	4-Ethylaniline		$C_8H_{11}N$	589-16-2	121.180	liq	-2.4	217.5	0.9679^{20}	1.5554^{20}	sl H_2O, ctc; vs EtOH, eth
4890	*N*-Ethylaniline		$C_8H_{11}N$	103-69-5	121.180	liq	-63.5	203.0	0.9625^{20}	1.5559^{20}	i H_2O; msc EtOH, eth; vs ace, bz; s ctc
4891	2-Ethyl-9,10-anthracenedione		$C_{16}H_{12}O_2$	84-51-5	236.265		108.8				
4892	4-Ethylbenzaldehyde		$C_9H_{10}O$	4748-78-1	134.174			221	0.9790^{20}		
4893	*N*-Ethylbenzamide		$C_9H_{11}NO$	614-17-5	149.189	nd (w)	70.5				
4894	Ethylbenzene	Phenylethane	C_8H_{10}	100-41-4	106.165	liq	-94.96	136.19	0.8626^{25}	1.4959^{20}	i H_2O; msc EtOH, eth; sl chl
4895	α-Ethylbenzeneacetamide	α-Phenylbutyramide	$C_{10}H_{13}NO$	90-26-6	163.216	cry	86	185^{16}			s H_2O, ctc; sl ace
4896	α-Ethylbenzeneacetic acid		$C_{10}H_{12}O_2$	90-27-7	164.201	pl (eth)	47.5	271			s eth, bz, ctc
4897	α-Ethylbenzeneacetonitrile		$C_{10}H_{11}N$	769-68-6	145.201			241	0.977^{14}		i H_2O; s EtOH, eth, bz
4898	4-Ethyl-1,3-benzenediol		$C_8H_{10}O_2$	2896-60-8	138.164	pr (chl, bz)	98.5	160^{24}, 131^{15}			sl H_2O, EtOH, eth
4899	α-Ethylbenzenemethanol	α-Ethylbenzyl alcohol	$C_9H_{12}O$	93-54-9	136.190			219	0.9915^{25}	1.5169^{23}	vs bz, eth, EtOH, MeOH
4900	Ethyl benzenesulfonate		$C_8H_{10}O_3S$	515-46-8	186.228			156^{15}	1.2167^{20}	1.5081^{20}	sl H_2O; s EtOH; vs eth, chl
4901	4-Ethylbenzenesulfonic acid		$C_8H_{10}O_3S$	98-69-1	186.228				1.23		
4902	2-Ethyl-1*H*-benzimidazole		$C_9H_{10}N_2$	1848-84-6	146.188		176.5				sl chl
4903	Ethyl benzoate		$C_9H_{10}O_2$	93-89-0	150.174	liq	-34	212	1.0415^{25}	1.5007^{20}	i H_2O; s EtOH, ace, bz; msc eth; sl ctc
4904	Ethyl 1,3-benzodioxole-5-carboxylate		$C_{10}H_{10}O_4$	6951-08-2	194.184	pr	18.5	285.5; 135^{6}			vs eth, EtOH, peth
4905	Ethyl benzoylacetate		$C_{11}H_{12}O_3$	94-02-0	192.211		<0	dec 267; 167^{20}	1.1202^{15}	1.5317^{15}	sl H_2O; s EtOH, eth
4906	Ethyl *N*-benzylglycinate		$C_{11}H_{15}NO_2$	6436-90-4	193.243			177^{50}		1.5041^{20}	vs EtOH, eth, bz
4907	Ethyl 2-benzylideneacetoacetate		$C_{13}H_{14}O_3$	620-80-4	218.248	orth pl (dil al)	60.5	296; 180^{17}			i H_2O; sl EtOH, eth, bz; vs chl
4908	Ethyl bromoacetate		$C_4H_7BrO_2$	105-36-2	167.002			168.5	1.5032^{20}	1.4489^{20}	i H_2O; msc EtOH, eth; s ace; sl ctc
4909	Ethyl 4-bromoacetoacetate		$C_6H_9BrO_3$	13176-46-0	209.037			115^{14}, 110^{10}	1.5278^{18}	1.5281^{20}	vs eth, EtOH
4910	Ethyl 4-bromobenzoate		$C_9H_9BrO_2$	5798-75-4	229.070	liq	-18	263; 125^{15}	1.4332^{17}	1.5438^{17}	sl H_2O; s EtOH, eth, ace, bz
4911	Ethyl 2-bromobutanoate		$C_6H_{11}BrO_2$	533-68-6	195.054			177; 43^{5}	1.3273^{20}	1.4475^{20}	i H_2O; msc EtOH, eth; s chl
4912	Ethyl 4-bromobutanoate		$C_6H_{11}BrO_2$	2969-81-5	195.054			192; 82^{10}	1.3540^{20}	1.4559^{20}	
4913	Ethyl *trans*-4-bromo-2-butenoate		$C_6H_9BrO_2$	37746-78-4	193.038			100^{14}	1.402^{16}	1.4925^{20}	vs EtOH
4914	Ethyl 6-bromohexanoate	Ethyl 6-bromocaproate	$C_8H_{15}BrO_2$	25542-62-5	223.108	cry (peth)	33	126^{21}	1.238^{23}	1.4566^{21}	
4915	Ethyl 2-bromo-3-methylbutanoate		$C_7H_{13}BrO_2$	609-12-1	209.081			186	1.2760^{20}	1.4496^{20}	vs eth, EtOH
4916	Ethyl 2-bromo-2-methylpropanoate		$C_6H_{11}BrO_2$	600-00-0	195.054			163	1.3263^{20}	1.4446^{20}	i H_2O; s EtOH; msc eth
4917	Ethyl 3-bromo-2-oxopropanoate	Ethyl 3-bromopyruvate	$C_5H_7BrO_3$	70-23-5	195.012			87^{9}			
4918	Ethyl 2-bromopentanoate		$C_7H_{13}BrO_2$	615-83-8	209.081			191	1.226^{18}	1.4496^{20}	i H_2O; s EtOH, eth
4919	Ethyl 5-bromopentanoate		$C_7H_{13}BrO_2$	14660-52-7	209.081			129^{35}, 107^{20}	1.3085^{20}	1.4543^{20}	sl ctc
4920	Ethyl 2-bromopropanoate	Ethyl α-bromopropionate	$C_5H_9BrO_2$	535-11-5	181.028			dec 160; 71^{26}	1.4135^{20}	1.4490^{20}	i H_2O; msc EtOH, eth; s chl
4921	Ethyl 3-bromopropanoate		$C_5H_9BrO_2$	539-74-2	181.028			179; 65^{15}	1.4123^{18}	1.4516^{20}	s EtOH, eth, ace; sl ctc
4922	2-Ethylbutanal	Diethylacetaldehyde	$C_6H_{12}O$	97-96-1	100.158			118^{160}	0.8110^{20}	1.4025^{20}	sl H_2O, ctc; msc EtOH, eth
4923	Ethyl butanoate		$C_6H_{12}O_2$	105-54-4	116.158	liq	-98	121.3	0.8735^{25}	1.3898^{25}	sl H_2O, ctc; s EtOH, eth
4924	2-Ethylbutanoic acid	Diethylacetic acid	$C_6H_{12}O_2$	88-09-5	116.158	liq	-31.8	194	0.9239^{20}	1.4132^{20}	sl H_2O, ctc; msc EtOH, eth
4925	2-Ethylbutanoic acid, triethyleneglycol diester		$C_{18}H_{34}O_6$	95-08-9	346.459			$181^{3.5}$			
4926	2-Ethyl-1-butanol		$C_6H_{14}O$	97-95-0	102.174		<-15	147	0.8326^{20}	1.4220^{20}	sl H_2O; s EtOH, eth, chl
4927	2-Ethylbutanoyl chloride		$C_6H_{11}ClO$	2736-40-5	134.603			140	0.9825^{20}	1.4234^{20}	vs eth



2-(Ethylamino)ethanol



2-Ethylaniline



3-Ethylaniline



4-Ethylaniline



N-Ethylaniline



2-Ethyl-9,10-anthracenedione



4-Ethylbenzaldehyde



N-Ethylbenzamide



Ethylbenzene



α-Ethylbenzeneacetamide



α-Ethylbenzeneacetic acid



α-Ethylbenzeneacetonitrile



4-Ethyl-1,3-benzenediol



α-Ethylbenzenemethanol



Ethyl benzenesulfonate



4-Ethylbenzenesulfonic acid



2-Ethyl-1*H*-benzimidazole



Ethyl benzoate



Ethyl 1,3-benzodioxole-5-carboxylate



Ethyl benzoylacetate



Ethyl *N*-benzylglycinate



Ethyl 2-benzylideneacetoacetate



Ethyl bromoacetate



Ethyl 4-bromoacetoacetate



Ethyl 4-bromobenzoate



Ethyl 2-bromobutanoate



Ethyl 4-bromobutanoate



Ethyl *trans*-4-bromo-2-butenoate



Ethyl 6-bromohexanoate



Ethyl 2-bromo-3-methylbutanoate



Ethyl 2-bromo-2-methylpropanoate



Ethyl 3-bromo-2-oxopropanoate



Ethyl 2-bromopentanoate



Ethyl 5-bromopentanoate



Ethyl 2-bromopropanoate



Ethyl 3-bromopropanoate



2-Ethylbutanal


Ethyl butanoate



2-Ethylbutanoic acid



2-Ethylbutanoic acid, triethyleneglycol diester



2-Ethyl-1-butanol



2-Ethylbutanoyl chloride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4928	2-Ethyl-1-butene		C_6H_{12}	760-21-4	84.159	liq	-131.5	64.7	0.6894^{20}	1.3969^{20}	i H_2O; s eth, ace, bz, chl
4929	Ethyl *cis*-2-butenoate	Ethyl isocrotonate	$C_6H_{10}O_2$	6776-19-8	114.142			136	0.9182^{20}	1.4242^{20}	vs ace, eth, EtOH
4930	Ethyl *trans*-2-butenoate	Ethyl crotonate	$C_6H_{10}O_2$	623-70-1	114.142			138	0.9175^{20}	1.4243^{20}	i H_2O; s EtOH, eth
4931	Ethyl 3-butenoate		$C_6H_{10}O_2$	1617-18-1	114.142			119	0.9122^{20}	1.4105^{20}	s EtOH
4932	2-Ethylbutyl acetate		$C_8H_{16}O_2$	10031-87-5	144.212		<-100	162.5	0.8790^{20}	1.4109^{20}	i H_2O; s EtOH, eth, ctc
4933	2-Ethylbutyl acrylate		$C_9H_{16}O_2$	3953-10-4	156.222	liq		80^{20}			
4934	2-Ethylbutylamine	2-Ethyl-1-butanamine	$C_6H_{15}N$	617-79-8	101.190	liq	125				
4935	Ethyl *N*-butylcarbamate		$C_7H_{15}NO_2$	591-62-8	145.200	liq	-22	202; 100^{15}	0.9434^{26}	1.4278^{26}	
4936	Ethyl 2-butynoate		$C_6H_8O_2$	4341-76-8	112.127			163	0.9641^{20}	1.4372^{20}	
4937	Ethyl carbamate	Urethane	$C_3H_7NO_2$	51-79-6	89.094	pr (bz, to)	49	185	0.9862^{21}	1.4144^{51}	vs H_2O, EtOH, eth, bz, chl, py; sl lig
4938	9-Ethyl-9*H*-carbazol-3-amine		$C_{14}H_{14}N_2$	132-32-1	210.274		99				
4939	9-Ethyl-9*H*-carbazole		$C_{14}H_{13}N$	86-28-2	195.260	nd (al)	68	190^{10}	1.059^{80}	1.6394^{80}	i H_2O; vs EtOH, eth
4940	Ethyl chloroacetate		$C_4H_7ClO_2$	105-39-5	122.551	liq	-21	144.3	1.1585^{20}	1.4215^{20}	i H_2O; msc EtOH, eth, ace; s bz
4941	Ethyl 4-chloroacetoacetate		$C_6H_9ClO_3$	638-07-3	164.586		-8	dec 220; 115^{14}	1.218^{25}	1.4520^{20}	
4942	Ethyl 4-chlorobenzoate		$C_9H_9ClO_2$	7335-27-5	184.619			237.5	1.1873^{14}		vs EtOH
4943	Ethyl 4-chlorobutanoate		$C_6H_{11}ClO_2$	3153-36-4	150.603			184	1.0756^{20}	1.4311^{20}	vs ace, eth, EtOH
4944	Ethyl chlorofluoroacetate		$C_4H_6ClFO_2$	401-56-9	140.541			129	1.225^{20}	1.3927^{20}	
4945	Ethyl chloroformate		$C_3H_5ClO_2$	541-41-3	108.524	liq	-80.6	95	1.1352^{20}	1.3974^{20}	vs bz, eth, chl
4946	Ethyl 2-chloro-2-oxoacetate	Ethyl oxalyl chloride	$C_4H_5ClO_3$	4755-77-5	136.534	hyg		137	1.2226^{20}		vs bz, eth
4947	Ethyl 2-chloropropanoate	Ethyl α-chloropropionate	$C_5H_9ClO_2$	535-13-7	136.577			147	1.0793^{20}	1.4178^{20}	i H_2O; msc EtOH, eth; sl ctc
4948	Ethyl 3-chloropropanoate		$C_5H_9ClO_2$	623-71-2	136.577			162	1.1086^{20}	1.4254^{20}	sl H_2O; msc EtOH, eth
4949	Ethyl chlorosulfinate		$C_2H_5ClO_2S$	6378-11-6	128.578			52.5^{44}, 32^{16}	1.2837^{20}	1.4550^{25}	vs eth
4950	Ethyl chlorosulfonate		$C_2H_5ClO_3S$	625-01-4	144.577			152.5; 93^{100}	1.3502^{25}	1.416^{20}	vs eth, chl, lig
4951	*S*-Ethyl chlorothioformate		C_3H_5ClOS	2941-64-2	124.589	liq		136	1.195^{20}	1.4820^{20}	
4952	Ethyl *trans*-cinnamate	Ethyl *trans*-3-phenyl-2-propenoate	$C_{11}H_{12}O_2$	4192-77-2	176.212		10	271.5	1.0491^{20}	1.5598^{20}	i H_2O; vs EtOH, eth, ace; s bz, ctc
4953	Ethyl cyanate		C_3H_5NO	627-48-5	71.078			dec 162; 30^{12}	0.89^{20}	1.3788^{25}	vs eth, EtOH
4954	Ethyl cyanoacetate		$C_5H_7NO_2$	105-56-6	113.116	liq	-22.5	205	1.0654^{20}	1.4175^{20}	s H_2O; vs eth, EtOH
4955	Ethyl 2-cyanoacrylate	Ethyl 2-cyano-2-propenoate	$C_6H_7NO_2$	7085-85-0	125.126	liq		55^{3}			
4956	Ethyl 2-cyano-3,3-diphenyl-2-propenoate	Etocrilene	$C_{18}H_{15}NO_2$	5232-99-5	277.318		110.5	195^{3}			
4957	Ethyl 2-cyano-3-ethoxyacrylate		$C_8H_{11}NO_3$	94-05-3	169.178		52	190.5			
4958	Ethyl cyanoformate		$C_4H_5NO_2$	623-49-4	99.089			115.5	1.003^{25}	1.3820^{20}	i H_2O; s EtOH, eth, ctc
4959	Ethyl 2-cyano-2-phenylacetate		$C_{11}H_{11}NO_2$	4553-07-5	189.211	oil		dec 275; 165^{20}	1.091^{20}	1.5012^{25}	vs ace, bz, eth, EtOH
4960	Ethyl 2-cyano-3-phenyl-2-propenoate	Ethyl 2-benzylidene-2-cyanoacetate	$C_{12}H_{11}NO_2$	2025-40-3	201.221	(i) nd (al) (ii) oil	51	188^{15}	1.1076^{25}	1.5033	vs ace, chl
4961	Ethylcyclobutane		C_6H_{12}	4806-61-5	84.159	liq	-142.9	70.8	0.7284^{20}	1.4020^{20}	i H_2O; msc EtOH, eth; s ace, bz, peth
4962	Ethylcyclohexane		C_8H_{16}	1678-91-7	112.213	liq	-111.3	131.9	0.7880^{20}	1.4330^{20}	i H_2O; s EtOH, ace, bz; vs lig; msc ctc
4963	Ethyl cyclohexanecarboxylate		$C_9H_{16}O_2$	3289-28-9	156.222			196	0.9362^{20}	1.4501^{15}	vs ace, eth, EtOH, chl
4964	1-Ethylcyclohexene		C_8H_{14}	1453-24-3	110.197	liq	-109.9	137	0.8176^{25}	1.4567^{20}	
4965	Ethyl 3-cyclohexene-1-carboxylate		$C_9H_{14}O_2$	15111-56-5	154.206			194.5	0.9688^{20}	1.4578^{20}	
4966	Ethyl cyclohexylacetate		$C_{10}H_{18}O_2$	5452-75-5	170.249			211	0.9537^{14}	1.451^{14}	
4967	Ethylcyclopentane		C_7H_{14}	1640-89-7	98.186	liq	-138.4	103.5	0.7665^{20}	1.4198^{20}	i H_2O; msc EtOH, eth, ace; s bz, tol
4968	Ethyl 2-cyclopentanone-1-carboxylate		$C_8H_{12}O_3$	611-10-9	156.179			221; 110^{16}	1.0781^{21}	1.4519^{20}	s eth, bz
4969	1-Ethylcyclopentene		C_7H_{12}	2146-38-5	96.170	liq	-118.5	106.3	0.7936^{25}	1.4412^{20}	
4970	Ethylcyclopropane		C_5H_{10}	1191-96-4	70.133	liq	-149.2	35.9	0.6790^{25}	1.3786^{20}	
4971	Ethyl cyclopropanecarboxylate		$C_6H_{10}O_2$	4606-07-9	114.142			134	0.9608^{15}	1.4190^{20}	
4972	Ethyl decanoate	Ethyl caprate	$C_{12}H_{24}O_2$	110-38-3	200.318	liq	-20	241.5	0.8650^{20}	1.4256^{20}	i H_2O; vs eth, EtOH, chl



2-Ethyl-1-butene



Ethyl *cis*-2-butenoate



Ethyl *trans*-2-butenoate



Ethyl 3-butenoate



2-Ethylbutyl acetate



2-Ethylbutyl acrylate



2-Ethylbutylamine



Ethyl *N*-butylcarbamate



Ethyl 2-butynoate



Ethyl carbamate



9-Ethyl-9*H*-carbazol-3-amine



9-Ethyl-9*H*-carbazole



Ethyl chloroacetate



Ethyl 4-chloroacetoacetate



Ethyl 4-chlorobenzoate



Ethyl 4-chlorobutanoate



Ethyl chlorofluoroacetate



Ethyl chloroformate



Ethyl 2-chloro-2-oxoacetate



Ethyl 2-chloropropanoate



Ethyl 3-chloropropanoate



Ethyl chlorosulfinate



Ethyl chlorosulfonate



S-Ethyl chlorothioformate



Ethyl *trans*-cinnamate



Ethyl cyanate



Ethyl cyanoacetate



Ethyl 2-cyanoacrylate


Ethyl 2-cyano-3,3-diphenyl-2-propenoate



Ethyl 2-cyano-3-ethoxyacrylate



Ethyl cyanoformate



Ethyl 2-cyano-2-phenylacetate



Ethyl 2-cyano-3-phenyl-2-propenoate



Ethylcyclobutane


Ethylcyclohexane



Ethyl cyclohexanecarboxylate


1-Ethylcyclohexene


Ethyl 3-cyclohexene-1-carboxylate



Ethyl cyclohexylacetate



Ethylcyclopentane


Ethyl 2-cyclopentanone-1-carboxylate



1-Ethylcyclopentene



Ethylcyclopropane



Ethyl cyclopropanecarboxylate



Ethyl decanoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
4973	Ethyl diazoacetate	Diazoacetic ester	$C_4H_6N_2O_2$	623-73-4	114.103	ye orth cry	-22	dec 140	1.0852^{18}	1.4605^{20}	sl H_2O; msc EtOH, eth, bz, lig
4974	Ethyl dibromoacetate		$C_4H_6Br_2O_2$	617-33-4	245.898			194	1.8991^{20}	1.5017^{13}	i H_2O; msc EtOH, eth
4975	Ethyl 2,3-dibromobutanoate		$C_6H_{10}Br_2O_2$	609-11-0	273.950	nd	58.5	113^{30}	1.6800^{20}		sl H_2O, ctc; s EtOH, eth
4976	Ethyl 2,4-dibromobutanoate		$C_6H_{10}Br_2O_2$	36847-51-5	273.950			149^{52}	1.6987^{20}	1.4960^{20}	i H_2O; s EtOH, eth
4977	Ethyl 2,3-dibromopropanoate		$C_5H_8Br_2O_2$	3674-13-3	259.925			214.5	1.7966^{20}	1.5007^{20}	s EtOH, eth
4978	Ethyl 3,6-di(*tert*-butyl)-1-naphthalenesulfonate	Ethyl dibunate	$C_{20}H_{28}O_3S$	5560-69-0	348.499						s chl
4979	Ethyl dichloroacetate		$C_4H_6Cl_2O_2$	535-15-9	156.996			155; 56^{10}	1.2827^{20}	1.4386^{20}	sl H_2O; msc EtOH, eth; s ace, chl
4980	Ethyldichloroarsine	Dichloroethylarsine	$C_2H_5AsCl_2$	598-14-1	174.889			155.3; 74^{50}	1.66^{20}		s H_2O; misc EtOH, bz
4981	Ethyl dichlorocarbamate		$C_3H_5Cl_2NO_2$	13698-16-3	157.984			66^{18}, 55^{15}	1.304^{30}	1.4595^{20}	
4982	Ethyl 2,3-dichloropropanoate		$C_5H_8Cl_2O_2$	6628-21-3	171.022			183.5	1.2401^{20}	1.4482^{20}	vs eth, EtOH
4983	Ethyl diethoxyacetate		$C_8H_{16}O_4$	6065-82-3	176.211			199	0.985^{25}	1.4100^{20}	
4984	Ethyl diethylmalonate		$C_{11}H_{20}O_4$	77-25-8	216.275			230	0.9643^{30}	1.4240^{20}	i H_2O; msc EtOH, eth; s ctc
4985	Ethyl difluoroacetate		$C_4H_6F_2O_2$	454-31-9	124.087			100	1.1765^{20}		i H_2O
4986	Ethyldifluoroarsine		$C_2H_5AsF_2$	430-40-0	141.980	liq, fumes in air	-38.7	94.3	1.708^{17}		
4987	5-Ethyldihydro-5-*sec*-butyl-2-thioxo-4,6(1*H*,5*H*)-pyrimidinedione	Thiobutabarbital	$C_{10}H_{16}N_2O_2S$	2095-57-0	228.311		169				
4988	5-Ethyldihydro-2(3*H*)-furanone		$C_6H_{10}O_2$	695-06-7	114.142	liq	-18	215.5	1.0261^{20}	1.4495^{20}	vs H_2O, EtOH
4989	Ethyl dihydrogen phosphate		$C_2H_7O_4P$	1623-14-9	126.048	hyg cry		dec	1.430^{25}	1.427	vs H_2O, ace, eth, EtOH
4990	5-Ethyldihydro-5-phenyl-4,6(1*H*,5*H*)-pyrimidinedione	Primidone	$C_{12}H_{14}N_2O_2$	125-33-7	218.251		281.5				
4991	Ethyl 2,4-dihydroxy-6-methylbenzoate		$C_{10}H_{12}O_4$	2524-37-0	196.200	lf (HOAc), pr (al)	132	sub			vs eth, EtOH
4992	*O*-Ethyl *S*-[2-(diisopropylamino) ethyl] methylphosphonothioate	VX Nerve agent	$C_{11}H_{26}NO_2PS$	50782-69-9	267.369	very toxic liq					
4993	Ethyldimethylamine	*N,N*-Dimethylethanamine	$C_4H_{11}N$	598-56-1	73.137	liq	-140	36.5	0.675^{20}	1.3705^{25}	
4994	Ethyl 4-(dimethylamino)benzoate		$C_{11}H_{15}NO_2$	10287-53-3	193.243		66.5	190^{14}	1.0099^{100}		
4995	1-Ethyl-2,4-dimethylbenzene		$C_{10}H_{14}$	874-41-9	134.218	liq	-62.9	188.4	0.8763^{20}	1.5038^{20}	vs ace, bz, eth, EtOH
4996	1-Ethyl-3,5-dimethylbenzene		$C_{10}H_{14}$	934-74-7	134.218	liq	-84.3	183.6	0.8608^{25}	1.4981^{20}	i H_2O; msc EtOH, eth, ace, bz; s peth, ctc
4997	2-Ethyl-1,3-dimethylbenzene		$C_{10}H_{14}$	2870-04-4	134.218	liq	-16.2	190	0.8864^{25}	1.5107^{20}	
4998	2-Ethyl-1,4-dimethylbenzene		$C_{10}H_{14}$	1758-88-9	134.218	liq	-53.7	186.9	0.8732^{25}	1.5043^{20}	i H_2O; msc EtOH, eth, ace, bz; s peth, ctc
4999	3-Ethyl-1,2-dimethylbenzene		$C_{10}H_{14}$	933-98-2	134.218	liq	-49.5	194	0.8881^{25}	1.5117^{20}	
5000	4-Ethyl-1,2-dimethylbenzene		$C_{10}H_{14}$	934-80-5	134.218	liq	-66.9	189.5	0.8706^{25}	1.5031^{20}	i H_2O; msc EtOH, eth, ace, bz; s peth, ctc
5001	*N'*-Ethyl-*N,N*-dimethyl-1,2-ethanediamine		$C_6H_{16}N_2$	123-83-1	116.204			134.5	0.738^{25}	1.4222^{20}	
5002	Ethyl 4,4-dimethyl-3-oxopentanoate	Ethyl pivaloylacetate	$C_9H_{16}O_3$	17094-34-7	172.221	liq		83^{17}	0.97^{18}		
5003	3-Ethyl-2,2-dimethylpentane		C_9H_{20}	16747-32-3	128.255	liq	-99.3	133.8	0.7438^{20}	1.4123^{20}	
5004	3-Ethyl-2,3-dimethylpentane		C_9H_{20}	16747-33-4	128.255			144.7	0.7508^{25}	1.4221^{20}	
5005	3-Ethyl-2,4-dimethylpentane		C_9H_{20}	1068-87-7	128.255	liq	-122.4	136.7	0.7365^{20}	1.4131^{20}	
5006	Ethyl 2,2-dimethylpropanoate	Ethyl 2,2-dimethylpropionate	$C_7H_{14}O_2$	3938-95-2	130.185	liq	-89.5	118.4	0.856^{20}	1.3906^{20}	s EtOH, eth
5007	3-Ethyl-2,5-dimethylpyrazine		$C_8H_{12}N_2$	13360-65-1	136.194			180.5	0.9657^{24}	1.5014^{24}	sl H_2O, EtOH, eth
5008	3-Ethyl-2,4-dimethyl-1*H*-pyrrole		$C_8H_{13}N$	517-22-6	123.196	pr	0	199; 96^{16}	0.913^{20}	1.4961^{20}	sl H_2O; s EtOH, eth, bz, chl
5009	Ethyl 3,5-dimethylpyrrole-2-carboxylate		$C_9H_{13}NO_2$	2199-44-2	167.205	cry (al)	125	$135^{10.5}$			s EtOH, ace
5010	Ethyl 2,4-dimethylpyrrole-3-carboxylate		$C_9H_{13}NO_2$	2199-51-1	167.205	cry (eth-lig, peth)	78.5	291			vs eth, EtOH
5011	Ethyl 2,5-dimethylpyrrole-3-carboxylate		$C_9H_{13}NO_2$	2199-52-2	167.205	orth (al)	117.5	291; 130^{15}			vs EtOH
5012	Ethyl 4,5-dimethylpyrrole-3-carboxylate		$C_9H_{13}NO_2$	2199-53-3	167.205	cry (dil al)	111.3				vs eth, EtOH, chl
5013	Ethyl 2,4-dioxopentanoate		$C_7H_{10}O_4$	615-79-2	158.152		18	214	1.1251^{20}	1.4757^{17}	vs eth, EtOH



Ethyl diazoacetate



Ethyl dibromoacetate


Ethyl 2,3-dibromobutanoate



Ethyl 2,4-dibromobutanoate



Ethyl 2,3-dibromopropanoate



Ethyl 3,6-di(*tert*-butyl)-1-naphthalenesulfonate



Ethyl dichloroacetate



Ethyldichloroarsine


Ethyl dichlorocarbamate



Ethyl 2,3-dichloropropanoate



Ethyl diethoxyacetate



Ethyl diethylmalonate



Ethyl difluoroacetate



Ethyldifluoroarsine



5-Ethyldihydro-5-*sec*-butyl-2-thioxo-4,6(1*H*,5*H*)-pyrimidinedione


5-Ethyldihydro-2(3*H*)-furanone



Ethyl dihydrogen phosphate



5-Ethyldihydro-5-phenyl-4,6(1*H*,5*H*)-pyrimidinedione



Ethyl 2,4-dihydroxy-6-methylbenzoate



O-Ethyl *S*-[2-(diisopropylamino)ethyl] methylphosphonothioate



Ethyldimethylamine



Ethyl 4-(dimethylamino)benzoate



1-Ethyl-2,4-dimethylbenzene



1-Ethyl-3,5-dimethylbenzene



2-Ethyl-1,3-dimethylbenzene



2-Ethyl-1,4-dimethylbenzene



3-Ethyl-1,2-dimethylbenzene



4-Ethyl-1,2-dimethylbenzene



N'-Ethyl-*N*,*N*-dimethyl-1,2-ethanediamine



Ethyl 4,4-dimethyl-3-oxopentanoate


3-Ethyl-2,2-dimethylpentane



3-Ethyl-2,3-dimethylpentane



3-Ethyl-2,4-dimethylpentane



Ethyl 2,2-dimethylpropanoate



3-Ethyl-2,5-dimethylpyrazine



3-Ethyl-2,4-dimethyl-1*H*-pyrrole


Ethyl 3,5-dimethylpyrrole-2-carboxylate



Ethyl 2,4-dimethylpyrrole-3-carboxylate


Ethyl 2,5-dimethylpyrrole-3-carboxylate



Ethyl 4,5-dimethylpyrrole-3-carboxylate


Ethyl 2,4-dioxopentanoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5014	*O*-Ethyl dithiocarbonate	Xanthogenic acid	$C_3H_6OS_2$	151-01-9	122.209	unstab liq	-53	25			
5015	Ethylene	Ethene	C_2H_4	74-85-1	28.053	col gas	-169.15	-103.77	0.5678^{-104}	1.363^{-100}	i H_2O; sl EtOH, bz, ace; s eth
5016	Ethylenebisdithiocarbamic acid		$C_4H_8N_2S_4$	111-54-6	212.380	unstab liq					
5017	Ethylene carbonate	Vinylene carbonate	$C_3H_4O_3$	96-49-1	88.062	mcl pl (al)	36.4	248	1.3214^{39}	1.4148^{50}	msc H_2O, EtOH, eth, bz, chl, AcOEt
5018	Ethylenediaminetetraacetic acid	EDTA	$C_{10}H_{16}N_2O_8$	60-00-4	292.242	cry (w)	245 dec				
5019	Ethylenediaminetetraacetic acid, disodium salt, dihydrate	EDTA disodium	$C_{10}H_{18}N_2Na_2O_{10}$	6381-92-6	372.237		242 dec				
5020	*N,N'*-Ethylene distearylamide	*N,N'*-Dioctadecanoylethanediamine	$C_{38}H_{76}N_2O_2$	110-30-5	593.022	cry (EtOH)	149				
5021	Ethyleneimine	Aziridine	C_2H_5N	151-56-4	43.068	liq	-77.9	56	0.832^{25}		msc H_2O; s EtOH; vs eth; sl chl
5022	Ethylestrenol		$C_{20}H_{32}O$	965-90-2	288.467	cry	77				
5023	*N*-Ethyl-1,2-ethanediamine		$C_4H_{12}N_2$	110-72-5	88.151			129	0.837^{25}	1.4385^{20}	
5024	Ethyl ethoxyacetate		$C_6H_{12}O_3$	817-95-8	132.157			158	0.9702^{20}	1.4039^{20}	s EtOH, eth, ace
5025	Ethyl 3-ethoxypropanoate		$C_7H_{14}O_3$	763-69-9	146.184			166; 48^{5}	0.9490^{20}	1.4065^{20}	
5026	Ethyl 2-ethoxy-1(2*H*)-quinolinecarboxylate	EEDQ	$C_{14}H_{17}NO_3$	16357-59-8	247.290		56.5	$126^{0.1}$			s chl
5027	Ethyl 2-ethylacetoacetate		$C_8H_{14}O_3$	607-97-6	158.195			198.0; 80^{10}	0.9847^{16}	1.4214^{25}	msc EtOH, eth
5028	Ethyl ethylcarbamate		$C_5H_{11}NO_2$	623-78-9	117.147			176	0.9813^{20}	1.4215^{20}	vs H_2O, eth, EtOH
5029	Ethyl 2-ethylhexanoate	Ethyl 2-ethylcaproate	$C_{10}H_{20}O_2$	2983-37-1	172.265			90^{28}	0.8586^{25}	1.4123^{25}	
5030	2-Ethyl-*N*-(2-ethylphenyl)aniline		$C_{16}H_{19}N$	64653-59-4	225.329		29	336^{603}, 173^{10}		1.5550^{25}	i H_2O; vs EtOH, eth; sl chl; s acid
5031	*O*-Ethyl ethylthiophosphonyl chloride		$C_4H_{10}ClOPS$	1497-68-3	172.613	liq		$35^{0.7}$	1.15^{20}		
5032	Ethyl fluoroacetate		$C_4H_7FO_2$	459-72-3	106.096			120	1.0912^{20}	1.3755^{20}	vs H_2O
5033	Ethyl 4-fluorobenzoate		$C_9H_9FO_2$	451-46-7	168.164	mcl pr (w)	26	210	1.146^{25}	1.4864^{20}	vs eth, EtOH
5034	*N*-Ethylformamide		C_3H_7NO	627-45-2	73.094			198	0.9552^{20}	1.4320^{20}	msc H_2O, EtOH, eth
5035	Ethyl formate		$C_3H_6O_2$	109-94-4	74.079	liq	-79.6	54.4	0.9208^{20}	1.3609^{20}	s H_2O; msc EtOH, eth; vs ace; sl ctc
5036	2-Ethylfuran		C_6H_8O	3208-16-0	96.127			92.5	0.9018^{20}	1.4403^{20}	s EtOH, eth, ace, bz
5037	Ethyl 2-furancarboxylate	Ethyl 2-furanoate	$C_7H_8O_3$	614-99-3	140.137	lf or pr	34.5	196.8	1.1174^{21}	1.4797^{21}	i H_2O; msc EtOH, eth, ace; s bz
5038	γ-Ethyl *L*-glutamate		$C_7H_{13}NO_4$	1119-33-1	175.183		191				sl H_2O
5039	Ethyl heptafluorobutanoate		$C_6H_5F_7O_2$	356-27-4	242.092			95	1.394^{20}	1.3011^{20}	sl H_2O; s eth, ace
5040	3-Ethylheptane		C_9H_{20}	15869-80-4	128.255	liq	-114.9	143.0	0.7225^{25}	1.4093^{20}	
5041	4-Ethylheptane		C_9H_{20}	2216-32-2	128.255			141.2	0.7241^{25}	1.4096^{20}	i H_2O; s eth; msc EtOH, ace, bz
5042	Ethyl heptanoate	Ethyl oenanthate	$C_9H_{18}O_2$	106-30-9	158.238	liq	-66.1	187	0.8817^{20}	1.4100^{20}	sl H_2O, ctc; s EtOH, eth
5043	2-Ethylheptanoic acid		$C_9H_{18}O_2$	3274-29-1	158.238	liq		153^{31}		1.4255^{27}	
5044	4-Ethyl-4-heptanol		$C_9H_{20}O$	597-90-0	144.254			182	0.8350^{20}	1.4332^{20}	vs eth, EtOH
5045	Ethyl *trans,trans*-2,4-hexadienoate	Ethyl sorbate	$C_8H_{12}O_2$	2396-84-1	140.180			195.5	0.9506^{20}	1.4951^{20}	vs eth, EtOH, chl
5046	2-Ethylhexanal		$C_8H_{16}O$	123-05-7	128.212		<-100	163	0.8540^{20}	1.4142^{20}	i H_2O; s EtOH, eth; sl ctc
5047	3-Ethylhexane		C_8H_{18}	619-99-8	114.229			118.6	0.7136^{20}	1.4018^{20}	i H_2O; msc EtOH, eth, ace, bz, chl; s ctc
5048	2-Ethyl-1,3-hexanediol	Ethohexadiol	$C_8H_{18}O_2$	94-96-2	146.228	liq	-40	244	0.9325^{22}	1.4497^{20}	sl H_2O; s EtOH, eth
5049	Ethyl hexanoate		$C_8H_{16}O_2$	123-66-0	144.212	liq	-67	167	0.873^{20}	1.4073^{20}	sl H_2O; vs eth, EtOH
5050	2-Ethylhexanoic acid		$C_8H_{16}O_2$	149-57-5	144.212			228; 120^{13}	0.9031^{25}	1.4241^{20}	s H_2O, eth, ctc; sl EtOH
5051	2-Ethyl-1-hexanol		$C_8H_{18}O$	104-76-7	130.228	liq	-70	184.6	0.8319^{25}	1.4300^{20}	i H_2O; s EtOH, eth, ace, bz, chl
5052	2-Ethylhexanoyl chloride		$C_8H_{15}ClO$	760-67-8	162.657			101^{40}, 67^{11}	0.939^{25}	1.4335^{20}	
5053	2-Ethyl-2-hexenal		$C_8H_{14}O$	645-62-5	126.196			175	0.8554^{20}		
5054	Ethyl 3-hexenoate	Ethyl hydrosorbate	$C_8H_{14}O_2$	2396-83-0	142.196			166.5	0.8957^{20}	1.4255^{20}	
5055	2-Ethylhexyl acetate		$C_{10}H_{20}O_2$	103-09-3	172.265	liq	-80	199	0.8718^{20}	1.4204^{20}	i H_2O; s EtOH, eth



O-Ethyl dithiocarbonate



Ethylene


Ethylenebisdithiocarbamic acid



Ethylene carbonate



Ethylenediaminetetraacetic acid



Ethylenediaminetetraacetic acid, disodium salt, dihydrate



N,N'-Ethylene distearylamide



Ethyleneimine



Ethylestrenol



N-Ethyl-1,2-ethanediamine



Ethyl ethoxyacetate



Ethyl 3-ethoxypropanoate



Ethyl 2-ethoxy-1(2*H*)-quinolinecarboxylate



Ethyl 2-ethylacetoacetate



Ethyl ethylcarbamate



Ethyl 2-ethylhexanoate



2-Ethyl-*N*-(2-ethylphenyl)aniline


O-Ethyl ethylthiophosphonyl chloride



Ethyl fluoroacetate



Ethyl 4-fluorobenzoate



N-Ethylformamide



Ethyl formate



2-Ethylfuran



Ethyl 2-furancarboxylate



γ-Ethyl *L*-glutamate



Ethyl heptafluorobutanoate



3-Ethylheptane



4-Ethylheptane



Ethyl heptanoate



2-Ethylheptanoic acid



4-Ethyl-4-heptanol



Ethyl *trans,trans*-2,4-hexadienoate



2-Ethylhexanal



3-Ethylhexane



2-Ethyl-1,3-hexanediol



Ethyl hexanoate



2-Ethylhexanoic acid


2-Ethyl-1-hexanol



2-Ethylhexanoyl chloride



2-Ethyl-2-hexenal



Ethyl 3-hexenoate



2-Ethylhexyl acetate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5056	2-Ethylhexyl acrylate		$C_{11}H_{20}O_2$	103-11-7	184.276		-90	125^{60}	0.880^{25}	1.4332^{25}	
5057	2-Ethylhexylamine	2-Ethyl-1-hexanamine	$C_8H_{19}N$	104-75-6	129.244			169.2			sl H_2O
5058	2-Ethylhexyl butyl phthalate	Butyl 2-ethylhexyl phthalate	$C_{20}H_{30}O_4$	85-69-8	334.450	col liq					sl H_2O
5059	2-Ethylhexyl dihydrogen phosphate	Mono(2-ethylhexyl) phosphate	$C_8H_{19}O_4P$	1070-03-7	210.208	liq					s H_2O, bz
5060	2-Ethylhexyl diphenyl phosphite	Forstab	$C_{20}H_{27}O_3P$	15647-08-2	346.400			$152^{0.15}$	1.054^{20}	1.5207^{27}	
5061	Ethyl hexyl ether	1-Ethoxyhexane	$C_8H_{18}O$	5756-43-4	130.228			143	0.7722^{20}	1.4008^{20}	vs eth, EtOH
5062	2-Ethylhexyl 2-hydroxybenzoate	Octisalate	$C_{15}H_{22}O_3$	118-60-5	250.334	liq		190^{21}	1.01		
5063	2-Ethylhexyl methacrylate		$C_{12}H_{22}O_2$	688-84-6	198.302			120^{18}, 110^{14}	0.880^{25}	1.436^{25}	
5064	2-[(2-Ethylhexyl)oxy]ethanol	Ethylene glycol mono(2-ethylhexyl) ether	$C_{10}H_{22}O_2$	1559-35-9	174.281			227.7			
5065	Ethylhydrazine		$C_2H_8N_2$	624-80-6	60.098			101			vs H_2O, ace, eth, EtOH
5066	Ethyl hydrazinecarboxylate	Ethyl carbazate	$C_3H_8N_2O_2$	4114-31-2	104.108	cry	46	dec 198; 93^{9}			s EtOH, eth; sl chl
5067	Ethyl hydrogen adipate		$C_8H_{14}O_4$	626-86-8	174.195	hyg cry (eth, peth)	29	285	0.9796^{20}	1.4311^{20}	s EtOH, eth, peth
5068	Ethyl hydrogen fumarate		$C_6H_8O_4$	2459-05-4	144.126		70	147^{16}	1.1109^{87}		s EtOH, ace; sl chl
5069	Ethyl hydrogen succinate	Butanedioic acid, monoethyl ester	$C_6H_{10}O_4$	1070-34-4	146.141	pr or nd	8	172^{42}, 119^{3}	1.1466^{20}	1.4327^{20}	vs H_2O, eth, EtOH
5070	Ethyl hydroperoxide	Ethyl hydrogen peroxide	$C_2H_6O_2$	3031-74-1	62.068	liq	-100	95	0.9332^{20}	1.3800^{20}	vs H_2O, bz, eth, EtOH
5071	Ethyl hydroxyacetate		$C_4H_8O_3$	623-50-7	104.105			160	1.0826^{23}	1.4180^{20}	vs eth, EtOH
5072	Ethyl 3-hydroxybenzoate		$C_9H_{10}O_3$	7781-98-8	166.173	pl (bz)	74		1.0680^{131}		sl H_2O, chl; s EtOH, eth
5073	Ethyl 4-hydroxybenzoate	Ethylparaben	$C_9H_{10}O_3$	120-47-8	166.173	cry (dil al)	117	297.5			sl H_2O, chl, tfa; vs EtOH, eth; i CS_2
5074	Ethyl 3-hydroxybutanoate, (±)		$C_6H_{12}O_3$	35608-64-1	132.157			$185; 76^{15}$	1.017^{20}	1.4182^{20}	s H_2O, EtOH; sl ctc
5075	Ethyl 2-hydroxy-3-butenoate		$C_6H_{10}O_3$	91890-87-8	130.141			dec 173; 68^{15}	1.0470^{15}	1.436^{13}	vs H_2O, eth, EtOH
5076	α-Ethyl-1-hydroxycyclohexaneacetic acid	Cyclobutyrol	$C_{10}H_{18}O_3$	512-16-3	186.248	cry (eth-peth)	81.5	164^{24}	1.0010^{18}	1.4680^{18}	vs ace, eth, EtOH, chl
5077	*N*-Ethyl-*N*-hydroxyethanamine	*N,N*-Diethylhydroxylamine	$C_4H_{11}NO$	3710-84-7	89.136		10	133	0.8669^{20}	1.4195^{20}	
5078	2-Ethyl-3-hydroxyhexanal		$C_8H_{16}O_2$	496-03-7	144.212			138^{50}, 101^{9}			
5079	Ethyl 4-hydroxy-3-methoxybenzoate		$C_{10}H_{12}O_4$	617-05-0	196.200	nd (dil al)	44	292			i H_2O; vs EtOH, eth; s chl
5080	Ethyl *cis*-12-hydroxy-9-octadecenoate, (*R*)	Ethyl ricinoleate	$C_{20}H_{38}O_3$	55066-53-0	326.514			258^{13}	0.9180^{20}	1.4618^{22}	
5081	Ethylidenecyclohexane		C_8H_{14}	1003-64-1	110.197			136	0.822^{25}	1.4618^{20}	
5082	5-Ethylidene-2-norbornene	5-Ethylidenebicyclo[2.2.1]hept-2-ene	C_9H_{12}	16219-75-3	120.191	liq		146	0.893	1.4900^{20}	
5083	1-Ethyl-1*H*-imidazole		$C_5H_8N_2$	7098-07-9	96.131			208	0.999^{25}		msc H_2O
5084	Ethyl iodoacetate		$C_4H_7IO_2$	623-48-3	214.002	oil		179	1.8173^{13}	1.5079^{13}	s EtOH, eth
5085	Ethyl isobutylcarbamate	Isobutyl urethane	$C_7H_{15}NO_2$	539-89-9	145.200		<-65	110^{30}	0.9432^{20}	1.4288^{20}	vs eth, EtOH
5086	Ethyl isocyanate		C_3H_5NO	109-90-0	71.078			60	0.9031^{20}	1.3808^{20}	i H_2O; msc EtOH, eth
5087	Ethyl isocyanide		C_3H_5N	624-79-3	55.079		<-66	79	0.7402^{20}	1.3622^{20}	vs H_2O; msc EtOH, eth; s ace
5088	*N*-Ethyl-1*H*-isoindole-1,3(2*H*)-dione		$C_{10}H_9NO_2$	5022-29-7	175.184	nd (al)	79	285.5			s EtOH, eth
5089	Ethyl isopentyl ether		$C_7H_{16}O$	628-04-6	116.201			112.5	0.7688^{21}		vs eth, EtOH
5090	Ethylisopropylamine	*N*-Ethyl-2-propanamine	$C_5H_{13}N$	19961-27-4	87.164			69.6		1.3872^{25}	
5091	1-Ethyl-2-isopropylbenzene		$C_{11}H_{16}$	18970-44-0	148.245			193	0.888^{20}	1.508^{20}	vs ace, bz, eth, EtOH
5092	Ethyl isopropyl ether		$C_5H_{12}O$	625-54-7	88.148			54.1	0.720^{25}	1.3698^{25}	s H_2O, ace, chl; msc EtOH, eth
5093	*N*-Ethyl-*N*-isopropyl-2-propanamine		$C_8H_{19}N$	7087-68-5	129.244			126.5	0.742^{25}	1.4138^{20}	s ctc
5094	Ethyl isopropyl sulfide		$C_5H_{12}S$	5145-99-3	104.214	liq	-122.2	107.5	0.8246^{20}		
5095	Ethyl isothiocyanate		C_3H_5NS	542-85-8	87.144	liq	-5.9	131.5	0.9990^{20}	1.5130^{20}	i H_2O; msc EtOH, eth
5096	Ethyl lactate	Ethyl 2-hydroxypropionate	$C_5H_{10}O_3$	2676-33-7	118.131	liq	-26	154.5	1.0328^{20}	1.4124^{20}	vs H_2O, eth, EtOH
5097	Ethyl laurate		$C_{14}H_{28}O_2$	106-33-2	228.371	liq	-10	$271; 154^{15}$	0.8618^{20}	1.4311^{20}	i H_2O; vs EtOH; msc eth; sl ctc
5098	Ethyl levulinate		$C_7H_{12}O_3$	539-88-8	144.168			205.8	1.0111^{20}	1.4229^{20}	vs H_2O, EtOH
5099	Ethyl mercaptoacetate		$C_4H_8O_2S$	623-51-8	120.171			157	1.0964^{15}	1.4582^{20}	s EtOH, eth; sl ctc
5100	Ethyl methacrylate		$C_6H_{10}O_2$	97-63-2	114.142			117	0.9135^{20}	1.4147^{20}	sl H_2O, chl; msc EtOH, eth


2-Ethylhexyl acrylate



2-Ethylhexylamine



2-Ethylhexyl butyl phthalate



2-Ethylhexyl dihydrogen phosphate



2-Ethylhexyl diphenyl phosphite



Ethyl hexyl ether



2-Ethylhexyl 2-hydroxybenzoate



2-Ethylhexyl methacrylate



2-[(2-Ethylhexyl)oxy]ethanol



Ethylhydrazine



Ethyl hydrazinecarboxylate



Ethyl hydrogen adipate



Ethyl hydrogen fumarate



Ethyl hydrogen succinate



Ethyl hydroperoxide



Ethyl hydroxyacetate



Ethyl 3-hydroxybenzoate



Ethyl 4-hydroxybenzoate



Ethyl 3-hydroxybutanoate, (±)



Ethyl 2-hydroxy-3-butenoate



α-Ethyl-1-hydroxycyclohexaneacetic acid



N-Ethyl-*N*-hydroxyethanamine


2-Ethyl-3-hydroxyhexanal



Ethyl 4-hydroxy-3-methoxybenzoate



Ethyl *cis*-12-hydroxy-9-octadecenoate, (*R*)



Ethylidenecyclohexane


5-Ethylidene-2-norbornene



1-Ethyl-1*H*-imidazole



Ethyl iodoacetate



Ethyl isobutylcarbamate



Ethyl isocyanate



Ethyl isocyanide



N-Ethyl-1*H*-isoindole-1,3(2*H*)-dione



Ethyl isopentyl ether



Ethylisopropylamine



1-Ethyl-2-isopropylbenzene



Ethyl isopropyl ether



N-Ethyl-*N*-isopropyl-2-propanamine



Ethyl isopropyl sulfide



Ethyl isothiocyanate


Ethyl lactate



Ethyl laurate



Ethyl levulinate



Ethyl mercaptoacetate



Ethyl methacrylate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5101	Ethyl methanesulfonate		$C_3H_8O_3S$	62-50-0	124.159			86[10]			
5102	1-Ethyl-4-methoxybenzene		$C_9H_{12}O$	1515-95-3	136.190			198	0.9624[15]	1.5120[20]	vs bz, eth
5103	α-Ethyl-4-methoxybenzenemethanol		$C_{10}H_{14}O_2$	5349-60-0	166.217			143[20]		1.5277[20]	s ctc
5104	Ethyl 2-methoxybenzoate		$C_{10}H_{12}O_3$	7335-26-4	180.200			261	1.1124[20]	1.5224[20]	vs eth, EtOH
5105	Ethyl 4-methoxybenzoate		$C_{10}H_{12}O_3$	94-30-4	180.200		7.5	269.5	1.1038[20]	1.5254[20]	i H_2O; s EtOH, eth
5106	4-Ethyl-2-methoxyphenol		$C_9H_{12}O_2$	2785-89-9	152.190	liq	-7	236.5	1.0931[18]		
5107	Ethyl (4-methoxyphenyl)acetate		$C_{11}H_{14}O_3$	14062-18-1	194.227			139[70]	1.097[25]	1.5075[20]	
5108	Ethyl 2-methylacetoacetate		$C_7H_{12}O_3$	609-14-3	144.168			187	0.9941[20]	1.4185[20]	sl H_2O; s EtOH, eth; vs ace
5109	*N*-Ethyl-2-methylallylamine	*N*-Ethyl-2-methyl-2-propen-1-amine	$C_6H_{13}N$	18328-90-0	99.174	liq		104.7	0.753	1.4221[20]	msc H_2O
5110	5-Ethyl-5-(2-methylallyl)-2-thiobarbituric acid	Methallatal	$C_{10}H_{14}N_2O_2S$	115-56-0	226.295		160.5				
5111	Ethylmethylamine	*N*-Methylethanamine	C_3H_9N	624-78-2	59.110			36.7			vs H_2O, ace, eth, EtOH
5112	Ethylmethylamine hydrochloride	*N*-Methylethanamine hydrochloride	$C_3H_{10}ClN$	624-60-2	95.571	pl (al-eth)	128		1.0874[20]		vs H_2O, EtOH; i eth; s chl
5113	2-Ethyl-6-methylaniline		$C_9H_{13}N$	24549-06-2	135.206	liq	-33	231	0.968[25]	1.5525[20]	
5114	*N*-Ethyl-2-methylaniline		$C_9H_{13}N$	94-68-8	135.206		<-15	216	0.948[25]	1.5456[20]	s EtOH, eth
5115	*N*-Ethyl-3-methylaniline		$C_9H_{13}N$	102-27-2	135.206			221	0.9263[15]	1.5451[20]	s EtOH, eth
5116	*N*-Ethyl-4-methylaniline	*N*-Ethyl-4-toluidine	$C_9H_{13}N$	622-57-1	135.206			217	0.9391[16]		s EtOH, eth
5117	*N*-Ethyl-*N*-methylaniline		$C_9H_{13}N$	613-97-8	135.206			204	0.92[55]		i H_2O; msc EtOH, eth; s ctc
5118	*N*-Ethyl-α-methylbenzeneethanamine	*N*-Ethylamphetamine	$C_{11}H_{17}N$	457-87-4	163.260			105[14]		1.4986[25]	
5119	*N*-Ethyl-4-methylbenzenesulfonamide		$C_9H_{13}NO_2S$	80-39-7	199.270		64				s EtOH
5120	1-Ethyl-2-methyl-1*H*-benzimidazole		$C_{10}H_{12}N_2$	5805-76-5	160.215		51	296	1.073[25]		
5121	Ethyl 2-methylbenzoate		$C_{10}H_{12}O_2$	87-24-1	164.201		<-10	227; 113[18]	1.0325[21]	1.507[22]	i H_2O; msc EtOH, eth
5122	Ethyl 4-methylbenzoate		$C_{10}H_{12}O_2$	94-08-6	164.201			232	1.0269[18]	1.5089[18]	i H_2O; msc EtOH, eth
5123	Ethyl 3-methylbutanoate	Ethyl isovalerate	$C_7H_{14}O_2$	108-64-5	130.185	liq	-99.3	135.0	0.8656[20]	1.3962[20]	sl H_2O; vs EtOH, eth
5124	2-Ethyl-2-methylbutanoic acid		$C_7H_{14}O_2$	19889-37-3	130.185		<-20	207		1.4250[20]	vs EtOH
5125	2-Ethyl-3-methyl-1-butene		C_7H_{14}	7357-93-9	98.186			89	0.7150[20]	1.410[20]	i H_2O; s eth, ace, bz, chl
5126	Ethyl *trans*-2-methyl-2-butenoate		$C_7H_{12}O_2$	5837-78-5	128.169			156	0.9200[20]	1.4340[20]	
5127	Ethyl 3-methyl-2-butenoate		$C_7H_{12}O_2$	638-10-8	128.169			153.5	0.9199[21]	1.4345[20]	
5128	5-Ethyl-5-(1-methylbutyl)-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione		$C_{11}H_{18}N_2O_3$	76-74-4	226.272		130				sl H_2O; s EtOH, eth
5129	Ethyl *N*-methylcarbamate		$C_4H_9NO_2$	105-40-8	103.120			170	1.0115[20]	1.4183[20]	vs H_2O, EtOH
5130	Ethyl methyl carbonate		$C_4H_8O_3$	623-53-0	104.105	liq	-14	107.5	1.012[20]	1.3778[20]	vs eth, EtOH
5131	*trans*-1-Ethyl-4-methylcyclohexane		C_9H_{18}	6236-88-0	126.239	liq	-80.8	149	0.7798[20]	1.4304[20]	
5132	1-Ethyl-1-methylcyclopentane		C_8H_{16}	16747-50-5	112.213	liq	-143.8	121.6	0.7767[25]	1.4272[20]	vs ace, bz, eth, EtOH
5133	*cis*-1-Ethyl-2-methylcyclopentane		C_8H_{16}	930-89-2	112.213	liq	-106	128	0.7852[20]	1.4293[20]	
5134	*trans*-1-Ethyl-2-methylcyclopentane		C_8H_{16}	930-90-5	112.213	liq	-105.9	121.2	0.7649[25]	1.4219[20]	
5135	*cis*-1-Ethyl-3-methylcyclopentane		C_8H_{16}	2613-66-3	112.213			121	0.7724[20]	1.4203[20]	vs ace, bz, eth, EtOH
5136	*trans*-1-Ethyl-3-methylcyclopentane		C_8H_{16}	2613-65-2	112.213	liq	-108	121	0.7619[20]	1.4186[20]	
5137	1-Ethyl-1-methylcyclopropane		C_6H_{12}	53778-43-1	84.159	liq	-130.2	56.8	0.6968[25]	1.3887[20]	
5138	2-Ethyl-2-methyl-1,3-dioxolane		$C_6H_{12}O_2$	126-39-6	116.158			118	0.9360[20]		
5139	Ethyl methyl ether		C_3H_8O	540-67-0	60.095	col gas	-113	7.4	0.7251[0]	1.3420[4]	s H_2O, ace, chl; msc EtOH, eth
5140	3-Ethyl-2-methylhexane		C_9H_{20}	16789-46-1	128.255			138	0.7310[20]	1.4106[20]	
5141	3-Ethyl-3-methylhexane		C_9H_{20}	3074-76-8	128.255			140.6	0.7371[25]	1.4140[20]	
5142	3-Ethyl-4-methylhexane	2,3-Diethylpentane	C_9H_{20}	3074-77-9	128.255			140	0.7420[20]	1.4134[20]	
5143	4-Ethyl-2-methylhexane		C_9H_{20}	3074-75-7	128.255			133.8	0.7195[25]	1.4063[20]	
5144	Ethyl 4-methylhexanoate	Ethyl 4-methylcaproate	$C_9H_{18}O_2$	1561-10-0	158.238			180	0.8708[20]	1.4051[20]	
5145	Ethyl 4-methyl-3-oxopentanoate		$C_8H_{14}O_3$	7152-15-0	158.195	liq	-9	173	0.98[25]	1.250[20]	
5146	3-Ethyl-2-methylpentane		C_8H_{18}	609-26-7	114.229	liq	-114.9	115.66	0.7193[20]	1.4040[20]	i H_2O; s eth; msc EtOH, ace, bz



Ethyl methanesulfonate



1-Ethyl-4-methoxybenzene



α-Ethyl-4-methoxybenzenemethanol



Ethyl 2-methoxybenzoate



Ethyl 4-methoxybenzoate


4-Ethyl-2-methoxyphenol



Ethyl (4-methoxyphenyl)acetate



Ethyl 2-methylacetoacetate



N-Ethyl-2-methylallylamine



5-Ethyl-5-(2-methylallyl)-2-thiobarbituric acid



Ethylmethylamine



Ethylmethylamine hydrochloride



2-Ethyl-6-methylaniline



N-Ethyl-2-methylaniline



N-Ethyl-3-methylaniline



N-Ethyl-4-methylaniline



N-Ethyl-*N*-methylaniline



N-Ethyl-α-methylbenzeneethanamine



N-Ethyl-4-methylbenzenesulfonamide



1-Ethyl-2-methyl-1*H*-benzimidazole



Ethyl 2-methylbenzoate



Ethyl 4-methylbenzoate



Ethyl 3-methylbutanoate



2-Ethyl-2-methylbutanoic acid



2-Ethyl-3-methyl-1-butene



Ethyl *trans*-2-methyl-2-butenoate


Ethyl 3-methyl-2-butenoate


5-Ethyl-5-(1-methylbutyl)-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione


Ethyl *N*-methylcarbamate



Ethyl methyl carbonate



trans-1-Ethyl-4-methylcyclohexane


1-Ethyl-1-methylcyclopentane


cis-1-Ethyl-2-methylcyclopentane


trans-1-Ethyl-2-methylcyclopentane



cis-1-Ethyl-3-methylcyclopentane



trans-1-Ethyl-3-methylcyclopentane



1-Ethyl-1-methylcyclopropane



2-Ethyl-2-methyl-1,3-dioxolane



Ethyl methyl ether



3-Ethyl-2-methylhexane



3-Ethyl-3-methylhexane


3-Ethyl-4-methylhexane



4-Ethyl-2-methylhexane



Ethyl 4-methylhexanoate



Ethyl 4-methyl-3-oxopentanoate



3-Ethyl-2-methylpentane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5147	3-Ethyl-3-methylpentane		C_8H_{18}	1067-08-9	114.229	liq	-90.9	118.27	0.7274^{20}	1.4078^{20}	i H_2O; s eth; msc EtOH, ace, bz
5148	Ethyl 4-methylpentanoate		$C_8H_{16}O_2$	25415-67-2	144.212			163; 52^{10}	0.8705^{20}	1.4050^{20}	
5149	3-Ethyl-2-methyl-1-pentene		C_8H_{16}	19780-66-6	112.213	liq	-112.9	109.5	0.7262^{20}	1.4140^{20}	
5150	2-[Ethyl(3-methylphenyl)amino] ethanol		$C_{11}H_{17}NO$	91-88-3	179.259			$118^{1.5}$		1.5540^{20}	s ctc
5151	Ethyl 3-methyl-3-phenyloxiranecarboxylate	Ethyl 3-methyl-3-phenylglycidate	$C_{12}H_{14}O_3$	77-83-8	206.237			273.5	1.044^{20}	1.5182^{20}	
5152	4-Ethyl-4-methyl-2,6-piperidinedione	Bemegride	$C_8H_{13}NO_2$	64-65-3	155.195	pl (w, ace-eth)	126.5	sub 100			s chl
5153	Ethyl 2-methylpropanoate	Ethyl isobutanoate	$C_6H_{12}O_2$	97-62-1	116.158	liq	-88.2	110.1	0.868^{20}	1.3869^{18}	sl H_2O, ctc; msc EtOH, eth; s ace
5154	2-Ethyl-5-methylpyrazine		$C_7H_{10}N_2$	13360-64-0	122.167	liq		79^{56}			
5155	3-Ethyl-4-methylpyridine	3-Ethyl-4-picoline	$C_8H_{11}N$	529-21-5	121.180			198	0.9286^{17}		sl H_2O; s EtOH, eth, chl; vs ace
5156	4-Ethyl-2-methylpyridine	4-Ethyl-2-picoline	$C_8H_{11}N$	536-88-9	121.180			179	0.9130^{25}		vs ace, bz, eth, EtOH
5157	3-Ethyl-3-methyl-2,5-pyrrolidinedione	Ethosuximide	$C_7H_{11}NO_2$	77-67-8	141.168	cry (ace-eth)	64.5				vs H_2O
5158	Ethyl methyl sulfide		C_3H_8S	624-89-5	76.161	liq	-105.93	66.7	0.8422^{20}	1.4404^{20}	i H_2O; msc EtOH; s eth, chl
5159	*N*-Ethylmorpholine		$C_6H_{13}NO$	100-74-3	115.173			138.5	0.8996^{20}	1.4400^{20}	msc H_2O, EtOH, eth; s ace, bz
5160	Ethyl myristate		$C_{16}H_{32}O_2$	124-06-1	256.424		12.3	295	0.8573^{25}	1.4362^{20}	i H_2O; s EtOH, ctc, lig; sl eth
5161	*N*-Ethyl-1-naphthalenamine		$C_{12}H_{13}N$	118-44-5	171.238			305; 191^{16}	1.0652^{15}	1.6477^{15}	vs eth, EtOH
5162	1-Ethylnaphthalene		$C_{12}H_{12}$	1127-76-0	156.223	liq	-13.9	258.6	1.0082^{20}	1.6062^{20}	i H_2O; msc EtOH, eth
5163	2-Ethylnaphthalene		$C_{12}H_{12}$	939-27-5	156.223	liq	-7.4	258	0.9922^{20}	1.5999^{20}	i H_2O; msc EtOH, eth; sl chl
5164	Ethyl 1-naphthylacetate		$C_{14}H_{14}O_2$	2122-70-5	214.260	oil	88.5	222^{20}, 118^{13}			s EtOH, eth
5165	Ethyl nitrate		$C_2H_5NO_3$	625-58-1	91.066	liq	-94.6	87.2	1.1084^{20}	1.3852^{20}	s H_2O; msc EtOH, eth
5166	Ethyl nitrite		$C_2H_5NO_2$	109-95-5	75.067	ye vol liq or gas		18	0.899^{15}	1.3418^{10}	msc EtOH, eth
5167	Ethyl nitroacetate		$C_4H_7NO_4$	626-35-7	133.104			106^{25}, 83^{6}	1.1953^{20}	1.4250^{20}	sl H_2O; msc EtOH; vs eth; s dil alk
5168	1-Ethyl-2-nitrobenzene		$C_8H_9NO_2$	612-22-6	151.163	liq	-12.3	232.5	1.1207^{20}	1.5356^{20}	i H_2O; vs EtOH, eth; s ace; sl ctc
5169	1-Ethyl-4-nitrobenzene		$C_8H_9NO_2$	100-12-9	151.163	liq	-12.3	245.5	1.1192^{20}	1.5455^{20}	i H_2O; vs EtOH, eth; s ace; sl ctc
5170	Ethyl 3-nitrobenzoate		$C_9H_9NO_4$	618-98-4	195.172		47	297			i H_2O; vs EtOH, eth
5171	Ethyl 4-nitrobenzoate		$C_9H_9NO_4$	99-77-4	195.172		57	186.3; 153^{8}			i H_2O; s EtOH, eth
5172	Ethyl *p*-nitrophenyl benzenethiophosphate		$C_{14}H_{14}NO_4PS$	2104-64-5	323.304		36		1.27^{25}	1.5978^{30}	vs bz, eth, EtOH
5173	2-Ethyl-2-nitro-1,3-propanediol		$C_5H_{11}NO_4$	597-09-1	149.146	nd (w)	57.5	dec			vs H_2O, eth, EtOH
5174	Ethyl 2-nitropropanoate		$C_5H_9NO_4$	2531-80-8	147.130			190.5		1.4210^{20}	vs bz, eth, EtOH
5175	*N*-Ethyl-*N*-nitrosourea	*N*-Nitroso-*N*-ethylurea	$C_3H_7N_3O_2$	759-73-9	117.107		100 dec				s chl
5176	Ethyl nonanoate		$C_{11}H_{22}O_2$	123-29-5	186.292	liq	-36.7	227.0	0.8657^{20}	1.4220^{20}	i H_2O; s EtOH, eth, ace, ctc
5177	5-Ethyl-2-norbornene		C_9H_{14}	15403-89-1	122.207	liq		143.6	0.86	1.4630^{20}	
5178	Ethyl *cis,cis*-9,12-octadecadienoate	Ethyl linoleate	$C_{20}H_{36}O_2$	544-35-4	308.499	ye or col		272^{180}, 212^{12}	0.8865^{20}		vs eth, EtOH
5179	Ethyl *cis,cis,cis*-9,12,15-octadecatrienoate	Ethyl linolenate	$C_{20}H_{34}O_2$	1191-41-9	306.483			218^{15}	0.8919^{20}	1.4694^{20}	vs eth, EtOH
5180	Ethyl *trans*-9-octadecenoate		$C_{20}H_{38}O_2$	6114-18-7	310.515		5.8	218^{15}	0.8664^{25}	1.4480^{25}	vs eth, EtOH
5181	3-Ethyloctane		$C_{10}H_{22}$	5881-17-4	142.282			166.5	0.7359^{25}	1.4156^{20}	
5182	4-Ethyloctane		$C_{10}H_{22}$	15869-86-0	142.282			163.7	0.7343^{25}	1.4151^{20}	
5183	Ethyl octanoate		$C_{10}H_{20}O_2$	106-32-1	172.265	liq	-43.1	208.5	0.866^{18}	1.4178^{20}	i H_2O; vs EtOH, eth; sl ctc
5184	Ethyl 1-octyl sulfide	1-(Ethylthio)octane	$C_{10}H_{22}S$	3698-94-0	174.347	liq		109^{14}			
5185	Ethyl oleate	Ethyl *cis*-9-octadecenoate	$C_{20}H_{38}O_2$	111-62-6	310.515			216^{15}, 207^{13}	0.8720^{20}	1.4515^{20}	vs eth, EtOH
5186	Ethyl 5-oxohexanoate		$C_8H_{14}O_3$	13984-57-1	158.195			221.5	0.989^{25}	1.4277^{20}	
5187	Ethyl 3-oxopentanoate		$C_7H_{12}O_3$	4949-44-4	144.168			191	1.0120^{20}	1.4230^{20}	vs bz, eth, EtOH



3-Ethyl-3-methylpentane



Ethyl 4-methylpentanoate



3-Ethyl-2-methyl-1-pentene



2-[Ethyl(3-methylphenyl)amino]ethanol



Ethyl 3-methyl-3-phenyloxiranecarboxylate



4-Ethyl-4-methyl-2,6-piperidinedione


Ethyl 2-methylpropanoate



2-Ethyl-5-methylpyrazine



3-Ethyl-4-methylpyridine



4-Ethyl-2-methylpyridine



3-Ethyl-3-methyl-2,5-pyrrolidinedione



Ethyl methyl sulfide



N-Ethylmorpholine



Ethyl myristate



N-Ethyl-1-naphthalenamine



1-Ethylnaphthalene



2-Ethylnaphthalene



Ethyl 1-naphthylacetate



Ethyl nitrate



Ethyl nitrite



Ethyl nitroacetate



1-Ethyl-2-nitrobenzene



1-Ethyl-4-nitrobenzene



Ethyl 3-nitrobenzoate



Ethyl 4-nitrobenzoate



Ethyl *p*-nitrophenyl benzenethiophosphate



2-Ethyl-2-nitro-1,3-propanediol



Ethyl 2-nitropropanoate



N-Ethyl-*N*-nitrosourea



Ethyl nonanoate



5-Ethyl-2-norbornene



Ethyl *cis,cis*-9,12-octadecadienoate



Ethyl *cis,cis,cis*-9,12,15-octadecatrienoate



Ethyl *trans*-9-octadecenoate



3-Ethyloctane



4-Ethyloctane


Ethyl octanoate



Ethyl 1-octyl sulfide



Ethyl oleate



Ethyl 5-oxohexanoate



Ethyl 3-oxopentanoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5188	Ethyl 2-oxo-2-phenylacetate	Ethyl phenylglyoxylate	$C_{10}H_{10}O_3$	1603-79-8	178.184			256.5	1.1222^{25}	1.5190^{25}	
5189	Ethyl 2-oxopropanoate	Ethyl pyruvate	$C_5H_8O_3$	617-35-6	116.116	liq	-50	155	1.0596^{15}	1.4052^{20}	sl H_2O; s ace; msc EtOH, eth
5190	Ethyl palmitate		$C_{18}H_{36}O_2$	628-97-7	284.478	nd	24	191^{10}	0.8577^{25}	1.4347^{34}	i H_2O; s EtOH, eth, ace, bz, chl
5191	3-Ethylpentane		C_7H_{16}	617-78-7	100.202	liq	-118.55	93.5	0.6982^{20}	1.3934^{20}	i H_2O; s EtOH, eth; msc ace, bz, hp, chl
5192	3-Ethyl-2,4-pentanedione		$C_7H_{12}O_2$	1540-34-7	128.169			178.5	0.9531^{19}	1.4408^{19}	vs eth, EtOH, chl
5193	Ethyl pentanoate	Ethyl valerate	$C_7H_{14}O_2$	539-82-2	130.185	liq	-91.2	146.1	0.8770^{20}	1.4120^{20}	i H_2O; msc EtOH, eth; sl ctc
5194	3-Ethyl-3-pentanol		$C_7H_{16}O$	597-49-9	116.201	liq	-12.5	142	0.8407^{22}	1.4294^{20}	sl H_2O; s EtOH, eth
5195	2-Ethyl-1-pentene		C_7H_{14}	3404-71-5	98.186			94	0.7079^{20}	1.405^{20}	vs bz, eth, EtOH
5196	3-Ethyl-1-pentene		C_7H_{14}	4038-04-4	98.186	liq	-127.5	84.1	0.6917^{25}	1.3982^{20}	
5197	3-Ethyl-2-pentene		C_7H_{14}	816-79-5	98.186			96	0.7204^{20}	1.4148^{20}	i H_2O; s EtOH, eth, bz, chl
5198	Ethyl pentyl ether		$C_7H_{16}O$	17952-11-3	116.201			117.6	0.7622^{20}	1.3927^{20}	vs eth, EtOH
5199	Ethyl 2-pentynoate		$C_7H_{10}O_2$	55314-57-3	126.153			67^{18}	0.962^{25}		
5200	2-Ethylphenol		$C_8H_{10}O$	90-00-6	122.164		18	204.5	1.0146^{25}	1.5367^{20}	vs ace, bz, eth, EtOH
5201	3-Ethylphenol		$C_8H_{10}O$	620-17-7	122.164	liq	-4	218.4	1.0283^{20}		sl H_2O, chl; vs EtOH, eth
5202	4-Ethylphenol		$C_8H_{10}O$	123-07-9	122.164	nd	45.0	217.9		1.5239^{25}	sl H_2O, chl; vs EtOH, eth, bz; s ace
5203	Ethyl phenoxyacetate		$C_{10}H_{12}O_3$	2555-49-9	180.200			$247; 110^{3}$	1.0958^{30}	1.5080^{20}	
5204	*N*-Ethyl-*N*-phenylacetamide		$C_{10}H_{13}NO$	529-65-7	163.216		55	260	0.9938^{60}		s H_2O, eth, ctc
5205	Ethyl phenylacetate	Benzeneacetic acid, ethyl ester	$C_{10}H_{12}O_2$	101-97-3	164.201	liq	-29.4	227	1.0333^{20}	1.4980^{20}	vs eth, EtOH
5206	2-(Ethylphenylamino)ethanol		$C_{10}H_{15}NO$	92-50-2	165.232						s chl
5207	Ethyl phenylcarbamate	Phenylurethane	$C_9H_{11}NO_2$	101-99-5	165.189	wh nd (w) pl (dil al)	53	dec 237	1.1064^{30}	1.5376^{30}	i H_2O; vs EtOH, eth; s bz; sl ctc
5208	Ethyl *N*-phenylformimidate		$C_9H_{11}NO$	6780-49-0	149.189			$214; 87^{10}$	1.0051^{20}	1.5279^{20}	s eth, bz
5209	Ethyl *N*-phenylglycinate		$C_{10}H_{13}NO_2$	2216-92-4	179.216	lf (dil al)	58	273.5			vs eth, EtOH
5210	1-(4-Ethylphenyl)-2-phenylethane		$C_{16}H_{18}$	7439-15-8	210.314	cry		294	1.028^{50}		
5211	Ethyl 3-phenylpropanoate		$C_{11}H_{14}O_2$	2021-28-5	178.228			247.2	1.0147^{20}	1.4954^{20}	vs eth, EtOH
5212	Ethyl 3-phenylpropynoate	Ethyl phenylacetylenecarboxylate	$C_{11}H_{10}O_2$	2216-94-6	174.196			$265; 128^{1.6}$	1.055^{25}	1.5520^{20}	s eth
5213	Ethyl phenyl sulfone		$C_8H_{10}O_2S$	599-70-2	170.229	lf (dil al)	42	160^{12}	1.1410^{20}		vs bz, eth, EtOH, chl
5214	Ethylphosphonic acid		$C_2H_7O_3P$	6779-09-5	110.049	hyg pl or nd	61.5	335^{8}			vs H_2O, eth, EtOH
5215	Ethyl phosphorodichloridate	Ethylphosphoric acid dichloride	$C_2H_5Cl_2O_2P$	1498-51-7	162.940			62^{10}		1.4338^{20}	
5216	5-Ethyl-2-picoline		$C_8H_{11}N$	104-90-5	121.180			178.3	0.9202^{20}	1.4971^{20}	sl H_2O; s EtOH, eth, bz; vs ace
5217	Ethyl 1-piperazinecarboxylate	1-Carbethoxypiperazine	$C_7H_{14}N_2O_2$	120-43-4	158.198			237		1.4760^{25}	vs H_2O, eth, EtOH
5218	1-Ethylpiperidine		$C_7H_{15}N$	766-09-6	113.201			130.8	0.8237^{20}	1.4480^{20}	
5219	Ethyl 4-piperidinecarboxylate		$C_8H_{15}NO_2$	1126-09-6	157.211	col oil		100^{10}		1.4591^{20}	vs H_2O, bz, eth, EtOH
5220	Ethyl 1-piperidinepropanoate		$C_{10}H_{19}NO_2$	19653-33-9	185.264			$217; 139^{50}$	0.9627^{25}	1.4525^{25}	vs H_2O
5221	1-Ethyl-3-piperidinol		$C_7H_{15}NO$	13444-24-1	129.200			94^{15}		1.4777^{14}	
5222	*N*-Ethyl-1-propanamine		$C_5H_{13}N$	20193-20-8	87.164			81	0.7204^{17}	1.3858^{25}	sl H_2O; vs ace, EtOH
5223	Ethylpropanedioic acid		$C_5H_8O_4$	601-75-2	132.116	pr (w+1)	114	$180^{0.05}$			vs H_2O; s EtOH, eth, bz; i ace; sl tfa
5224	Ethyl propanoate	Ethyl propionate	$C_5H_{10}O_2$	105-37-3	102.132	liq	-73.9	99.1	0.8843^{25}	1.3839^{20}	sl H_2O, ctc; msc EtOH, eth; s ace
5225	Ethyl propyl ether		$C_5H_{12}O$	628-32-0	88.148	liq	-127.5	63.21	0.7386^{20}	1.3695^{20}	vs eth, EtOH, HOAc
5226	2-(1-Ethylpropyl)pyridine		$C_{10}H_{15}N$	7399-50-0	149.233			195.4	0.8981^{20}	1.4850^{25}	
5227	4-(1-Ethylpropyl)pyridine		$C_{10}H_{15}N$	35182-51-5	149.233		125.5	$217; 80^{12}$	0.9085^{25}	1.40905^{25}	
5228	Ethyl propyl sulfide		$C_5H_{12}S$	4110-50-3	104.214	liq	-117	118.6	0.8370^{20}	1.4462^{20}	s EtOH
5229	Ethyl 2-propynoate	(Ethoxycarbonyl)acetylene	$C_5H_6O_2$	623-47-2	98.101			120	0.9645^{16}	1.4105^{20}	i H_2O; vs EtOH, eth, chl
5230	2-Ethylpyrazine		$C_6H_8N_2$	13925-00-3	108.141			112^{200}			
5231	2-Ethylpyridine		C_7H_9N	100-71-0	107.153	liq	-63.1	148.6	0.9502^{25}	1.4964^{20}	s H_2O; msc EtOH; vs eth, ace; sl ctc



Ethyl 2-oxo-2-phenylacetate



Ethyl 2-oxopropanoate



Ethyl palmitate



3-Ethylpentane



3-Ethyl-2,4-pentanedione



Ethyl pentanoate



3-Ethyl-3-pentanol



2-Ethyl-1-pentene



3-Ethyl-1-pentene



3-Ethyl-2-pentene



Ethyl pentyl ether



Ethyl 2-pentynoate



2-Ethylphenol



3-Ethylphenol



4-Ethylphenol



Ethyl phenoxyacetate



N-Ethyl-*N*-phenylacetamide



Ethyl phenylacetate



2-(Ethylphenylamino)ethanol



Ethyl phenylcarbamate



Ethyl *N*-phenylformimidate



Ethyl *N*-phenylglycinate



1-(4-Ethylphenyl)-2-phenylethane



Ethyl 3-phenylpropanoate



Ethyl 3-phenylpropynoate



Ethyl phenyl sulfone



Ethylphosphonic acid



Ethyl phosphorodichloridate



5-Ethyl-2-picoline



Ethyl 1-piperazinecarboxylate



1-Ethylpiperidine



Ethyl 4-piperidinecarboxylate



Ethyl 1-piperidinepropanoate



1-Ethyl-3-piperidinol



N-Ethyl-1-propanamine



Ethylpropanedioic acid



Ethyl propanoate



Ethyl propyl ether



2-(1-Ethylpropyl)pyridine


4-(1-Ethylpropyl)pyridine



Ethyl propyl sulfide



Ethyl 2-propynoate



2-Ethylpyrazine



2-Ethylpyridine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5232	3-Ethylpyridine		C_7H_9N	536-78-7	107.153	liq	-76.9	165	0.9539^{25}	1.5021^{20}	s H_2O, EtOH, eth; vs ace; sl ctc
5233	4-Ethylpyridine		C_7H_9N	536-75-4	107.153	liq	-90.5	168.3	0.9417^{20}	1.5009^{20}	s H_2O, EtOH, eth; vs ace; sl ctc
5234	2-Ethyl-4-pyridinecarbothioamide	Ethionamide	$C_8H_{10}N_2S$	536-33-4	166.243		163				
5235	Ethyl 2-pyridinecarboxylate	Ethyl 2-picolinate	$C_8H_9NO_2$	2524-52-9	151.163	ye cry in air	1	243	1.1194^{20}	1.5104^{20}	vs H_2O, eth, EtOH
5236	Ethyl 3-pyridinecarboxylate	Ethyl nicotinate	$C_8H_9NO_2$	614-18-6	151.163		8.5	224	1.1070^{20}	1.5024^{20}	vs H_2O, EtOH, eth, bz; sl ctc
5237	Ethyl 4-pyridinecarboxylate		$C_8H_9NO_2$	1570-45-2	151.163		23	219.5	1.0091^{15}	1.5017^{20}	sl H_2O; s EtOH, bz; vs eth, chl
5238	*N*-Ethylpyridinium bromide		$C_7H_{10}BrN$	1906-79-2	188.065	cry (al)	111.5				s H_2O, EtOH; i eth
5239	1-Ethyl-1*H*-pyrrole		C_6H_9N	617-92-5	95.142			129.5	0.9009^{20}	1.4841^{20}	vs EtOH
5240	1-Ethyl-1*H*-pyrrole-2,5-dione	*N*-Ethylmaleimide	$C_6H_7NO_2$	128-53-0	125.126	cry (bz)	45.5				sl H_2O; vs EtOH, eth; s chl
5241	1-Ethyl-2-pyrrolidinemethanamine		$C_7H_{16}N_2$	26116-12-1	128.215			59^{16}, 40^{10}	0.887^{25}	1.4665^{20}	
5242	Ethyl Red	2-(4-Diethylaminophenylazo) benzoic acid	$C_{17}H_{19}N_3O_2$	76058-33-8	297.352		135				
5243	Ethyl salicylate		$C_9H_{10}O_3$	118-61-6	166.173		45	150^{10}	1.1326^{20}	1.5296^{20}	i H_2O; msc EtOH; vs eth; s ctc
5244	Ethyl silicate		$C_8H_{20}O_4Si$	78-10-4	208.329	liq	-82.5	168.8	0.9320^{20}	1.3928^{20}	dec H_2O
5245	Ethyl stearate	Ethyl octadecanoate	$C_{20}H_{40}O_2$	111-61-5	312.531		33	199^{10}	1.057^{20}	1.4349^{40}	i H_2O; s EtOH, eth, chl; vs ace
5246	2-Ethylstyrene		$C_{10}H_{12}$	7564-63-8	132.202	liq	-75.5	187.3; 68^{12}	0.9017^{25}	1.5380^{20}	
5247	3-Ethylstyrene		$C_{10}H_{12}$	7525-62-4	132.202	liq	-101	190.0	0.8945^{20}	1.5351^{20}	
5248	4-Ethylstyrene		$C_{10}H_{12}$	3454-07-7	132.202	liq	-49.7	192.3; 86^{20}	0.8884^{25}	1.5376^{20}	
5249	Ethyl sulfate		$C_2H_6O_4S$	540-82-9	126.132			dec 280	1.3657^{20}	1.4105^{20}	vs H_2O
5250	2-(Ethylsulfonyl)ethanol	Ethylsulfonylethyl alcohol	$C_4H_{10}O_3S$	513-12-2	138.185						sl chl
5251	2-Ethyl-5-(3-sulfophenyl) isoxazolium hydroxide, inner salt	Woodward's Reagent K	$C_{11}H_{11}NO_4S$	4156-16-5	253.275		dec 207				
5252	Ethyl tartrate	Ethyl tartrate, acid	$C_6H_{10}O_6$	608-89-9	178.139		90				vs H_2O, EtOH
5253	2-Ethyltetrahydrofuran		$C_6H_{12}O$	1003-30-1	100.158			109	0.8570^{19}	1.4147^{19}	vs ace, bz, eth, EtOH
5254	5-Ethyl-1,3,4-thiadiazol-2-amine		$C_4H_7N_3S$	14068-53-2	129.184		200.8				
5255	*S*-Ethyl thioacetate		C_4H_8OS	625-60-5	104.171			116.4	0.9792^{20}	1.4583^{21}	i H_2O; vs EtOH, eth
5256	(Ethylthio)acetic acid		$C_4H_8O_2S$	627-04-3	120.171		-8.5	164^{83}, 109^{5}	1.1497^{20}		vs H_2O, EtOH, eth
5257	(Ethylthio)benzene	Thiophenetole	$C_8H_{10}S$	622-38-8	138.230			205	1.0211^{20}	1.5670^{20}	s EtOH
5258	Ethyl thiocyanate		C_3H_5NS	542-90-5	87.144	liq	-85.5	146	1.007^{23}	1.4684^{15}	i H_2O; msc EtOH, eth; s chl
5259	2-(Ethylthio)ethanol		$C_4H_{10}OS$	110-77-0	106.186	liq	-100	184	1.0166^{20}	1.4867^{20}	sl H_2O; s EtOH; vs ace
5260	1-(Ethylthio)-4-methylbenzene		$C_9H_{12}S$	622-63-9	152.256			220	0.9996^{20}	1.555^{20}	
5261	2-Ethylthiophene		C_6H_8S	872-55-9	112.193			134	0.9930^{20}	1.5122^{20}	i H_2O; vs EtOH, eth
5262	Ethyl thiophene-2-carboxylate		$C_7H_8O_2S$	2810-04-0	156.203			218	1.1623^{16}	1.5248^{20}	s EtOH, ace; sl ctc
5263	3-Ethyl-2-thioxo-4-thiazolidinone	3-Ethylrhodanine	$C_5H_7NOS_2$	7648-01-3	161.246		35.5				
5264	2-Ethyltoluene		C_9H_{12}	611-14-3	120.191	liq	-79.83	165.2	0.8807^{20}	1.5046^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
5265	3-Ethyltoluene		C_9H_{12}	620-14-4	120.191	liq	-95.6	161.3	0.8645^{20}	1.4966^{20}	i H_2O; vs EtOH, eth; msc ace, bz
5266	4-Ethyltoluene		C_9H_{12}	622-96-8	120.191	liq	-62.35	162	0.8614^{20}	1.4959^{20}	i H_2O; vs EtOH, eth; msc ace, bz
5267	Ethyl *p*-toluenesulfonate		$C_9H_{12}O_3S$	80-40-0	200.254		34.5	173^{15}	1.166^{48}		i H_2O; s EtOH, eth, AcOEt; sl ctc
5268	Ethyl trichloroacetate		$C_4H_5Cl_3O_2$	515-84-4	191.441			167.5	1.3836^{20}	1.4505^{20}	i H_2O; s EtOH, eth, bz; sl chl
5269	Ethyl trifluoroacetate		$C_4H_5F_3O_2$	383-63-1	142.077			61	1.194^{20}	1.308^{20}	
5270	Ethyl 4,4,4-trifluoroacetoacetate		$C_6H_7F_3O_3$	372-31-6	184.113	liq	-39.1	132	1.2586^{15}	1.3783^{15}	s EtOH, eth
5271	Ethyl trifluoromethanesulfonate		$C_3H_5F_3O_3S$	425-75-2	178.130			115	1.3740^{0}		s eth
5272	Ethyl 3,4,5-trihydroxybenzoate		$C_9H_{10}O_5$	831-61-8	198.172	mcl pr (w+2 1/2) nd (chl)	163.0				sl H_2O, chl; s EtOH, eth, AcOEt



3-Ethylpyridine



4-Ethylpyridine


2-Ethyl-4-pyridinecarbothioamide



Ethyl 2-pyridinecarboxylate



Ethyl 3-pyridinecarboxylate



Ethyl 4-pyridinecarboxylate



N-Ethylpyridinium bromide



1-Ethyl-1*H*-pyrrole



1-Ethyl-1*H*-pyrrole-2,5-dione



1-Ethyl-2-pyrrolidinemethanamine



Ethyl Red



Ethyl salicylate



Ethyl silicate



Ethyl stearate



2-Ethylstyrene



3-Ethylstyrene



4-Ethylstyrene



Ethyl sulfate



2-(Ethylsulfonyl)ethanol



2-Ethyl-5-(3-sulfophenyl)isoxazolium hydroxide, inner salt



Ethyl tartrate



2-Ethyltetrahydrofuran



5-Ethyl-1,3,4-thiadiazol-2-amine



S-Ethyl thioacetate



(Ethylthio)acetic acid



(Ethylthio)benzene



Ethyl thiocyanate



2-(Ethylthio)ethanol



1-(Ethylthio)-4-methylbenzene



2-Ethylthiophene



Ethyl thiophene-2-carboxylate



3-Ethyl-2-thioxo-4-thiazolidinone



2-Ethyltoluene



3-Ethyltoluene



4-Ethyltoluene



Ethyl *p*-toluenesulfonate


Ethyl trichloroacetate



Ethyl trifluoroacetate



Ethyl 4,4,4-trifluoroacetoacetate



Ethyl trifluoromethanesulfonate


Ethyl 3,4,5-trihydroxybenzoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5273	Ethyltrimethoxysilane		$C_5H_{14}O_3Si$	5314-55-6	150.249			124.3	0.9488^{20}	1.3838^{20}	vs EtOH
5274	1-Ethyl-2,4,5-trimethylbenzene		$C_{11}H_{16}$	17851-27-3	148.245	liq	-13.5	213	0.883^{20}	1.5075^{20}	vs ace, bz, eth, EtOH
5275	2-Ethyl-1,3,5-trimethylbenzene		$C_{11}H_{16}$	3982-67-0	148.245	liq	-15.5	212.4	0.883^{20}	1.5074^{20}	vs ace, bz, eth, EtOH
5276	Ethyltrimethyllead	Ethyltrimethylplumbane	$C_5H_{14}Pb$	1762-26-1	281.4	col liq		$27^{10.5}$	1.88^{20}		
5277	3-Ethyl-2,4,5-trimethylpyrrole		$C_9H_{15}N$	520-69-4	137.222	lf (eth)	66.5	214; 110^{35}			
5278	4-Ethyl-2,6,7-trioxa-1-phosphabicyclo[2.2.2]octane	Trimethylolpropane phosphite	$C_6H_{11}O_3P$	824-11-3	162.123		53.7				s chl
5279	Ethyl undecanoate	Ethyl undecylate	$C_{13}H_{26}O_2$	627-90-7	214.344		-15	131^{14}	0.8633^{20}	1.4285^{20}	i H_2O; s EtOH, eth, ace, bz
5280	Ethyl 10-undecenoate		$C_{13}H_{24}O_2$	692-86-4	212.329	liq	-38	264.5	0.8827^{15}	1.4449^{25}	i H_2O; s EtOH, eth, HOAc; sl ctc
5281	*N*-Ethylurea		$C_3H_8N_2O$	625-52-5	88.108	nd (bz, al-eth)	92.5	dec	1.2130^{18}		vs H_2O, EtOH, bz; s eth; i CS_2
5282	Ethyl vinyl ether		C_4H_8O	109-92-2	72.106	liq	-115.8	35.5	0.7589^{20}	1.3767^{20}	sl H_2O, ctc; s EtOH; msc eth
5283	Ethyl Violet		$C_{31}H_{42}ClN_3$	2390-59-2	492.138	gray-viol cry					s H_2O, EtOH
5284	α-Ethynylbenzenemethanol	1-Phenylpropargyl alcohol	C_9H_8O	4187-87-5	132.159	pr	22	114^{12}	1.0655^{20}	1.5508^{20}	
5285	α-Ethynylbenzenemethanol carbamate	Carfimate	$C_{10}H_9NO_2$	3567-38-2	175.184	cry (al)	86.5				
5286	1-Ethynylcyclohexanamine		$C_8H_{13}N$	30389-18-5	123.196			65^{20}	0.913^{25}	1.4817^{20}	
5287	1-Ethynylcyclohexanol		$C_8H_{12}O$	78-27-3	124.180	cry (peth)	31.5	174	0.9873^{20}	1.4822^{20}	i H_2O; s EtOH, bz, peth; sl chl
5288	1-Ethynylcyclohexanol, carbamate	Ethinamate	$C_9H_{13}NO_2$	126-52-3	167.205	nd	97	120^{3}		1.4441^{21}	sl H_2O; vs EtOH; s hx
5289	1-Ethynylcyclopentanol		$C_7H_{10}O$	17356-19-3	110.153		27	157.5	0.962^{25}	1.4751^{20}	
5290	α-Ethynyl-α-methylbenzenemethanol		$C_{10}H_{10}O$	127-66-2	146.185		52.3	217.5; 102^{12}	1.0314^{20}		
5291	Ethynylsilane	Silylacetylene	C_2H_4Si	1066-27-9	56.139	col gas		-22.5			
5292	Etioporphyrin		$C_{32}H_{38}N_4$	448-71-5	478.671		362				
5293	Etofylline		$C_9H_{12}N_4O_3$	519-37-9	224.216		158				vs H_2O; s EtOH; sl eth, bz
5294	Etoglucid	Oxirane, 2,2'-(2,5,8,11-tetraoxadodecane-1,12-diyl) bis-	$C_{12}H_{22}O_6$	1954-28-5	262.299	col liq	-13	196^{2}	1.1312^{20}	1.4622^{20}	
5295	Etoposide		$C_{29}H_{32}O_{13}$	33419-42-0	588.556	cry (MeOH)	≈243				s MeOH
5296	Etrimfos		$C_{10}H_{17}N_2O_4PS$	38260-54-7	292.291		-1.7		1.195^{20}		
5297	Eucalyptol	Cineole	$C_{10}H_{18}O$	470-82-6	154.249		0.8	176.4	0.9267^{20}	1.4586^{20}	i H_2O; s EtOH, eth, chl; sl ctc
5298	Euparin	1-[6-Hydroxy-2-(1-methylvinyl) -5-benzofuranyl]ethanone	$C_{13}H_{12}O_3$	532-48-9	216.232		121.5				s eth, bz, chl; sl NaOH
5299	Evan's Blue		$C_{34}H_{24}N_6Na_4O_{14}S_4$	314-13-6	960.806						s H_2O, EtOH, acid
5300	Evodiamine		$C_{19}H_{17}N_3O$	518-17-2	303.357	ye lf (al)	28				
5301	Famotidine		$C_8H_{15}N_7O_2S_3$	76824-35-6	337.446	cry	163				i EtOH, chl; vs DMF; s HOAc; sl MeOH
5302	Famphur		$C_{10}H_{16}NO_5PS_2$	52-85-7	325.342		53				
5303	α-Farnesene		$C_{15}H_{24}$	502-61-4	204.352			130^{12}	0.8410^{20}	1.4836^{20}	i H_2O; s eth, ace; msc peth, lig
5304	β-Farnesene		$C_{15}H_{24}$	18794-84-8	204.352			121^{9}	0.8363^{20}	1.4899^{20}	vs ace, eth, chl
5305	Farnesic acid		$C_{15}H_{24}O_2$	7548-13-2	236.351	oil		204^{16}			
5306	2-*cis*,6-*trans*-Farnesol		$C_{15}H_{26}O$	3790-71-4	222.366	oil		156^{12}, $120^{0.3}$	0.8908^{20}	1.4877^{20}	vs ace, eth, EtOH
5307	2-*trans*,6-*trans*-Farnesol		$C_{15}H_{26}O$	106-28-5	222.366	oil		160^{10}, 137^{3}	0.888^{20}	1.4877^{20}	i H_2O; vs EtOH; s eth, ace
5308	Farnesol acetate		$C_{17}H_{28}O_2$	29548-30-9	264.403			168^{10}			
5309	Fenadiazole	2-(1,2,4-Oxadiazol-2-yl)phenol	$C_8H_6N_2O_4$	1008-65-7	194.145	cry	112	$180^{0.1}$			
5310	Fenamiphos		$C_{13}H_{22}NO_3PS$	22224-92-6	303.358		49		1.15^{20}		
5311	Fenarimol		$C_{17}H_{12}Cl_2N_2O$	60168-88-9	331.195		118				
5312	Fenbuconazole		$C_{20}H_{17}ClN_4$	114369-43-6	350.845		125				
5313	Fenbutatin oxide	Distannoxane, hexakis(2-methyl-2-phenylpropyl)-	$C_{60}H_{78}OSn_2$	13356-08-6	1052.680		138				
5314	α-Fenchol, (±)	1,3,3-Trimethylbicyclo[2.2.1] heptan-2-ol, *endo*-(±)	$C_{10}H_{18}O$	36386-49-9	154.249		39	199.5	0.9420^{40}		vs eth, EtOH
5315	(±)-Fenchone		$C_{10}H_{16}O$	18492-37-0	152.233	oily liq	6.1	193.5	0.9492^{15}	1.4702^{20}	i H_2O; vs EtOH; s eth, ace
5316	Fenfluramine		$C_{12}H_{16}F_3N$	458-24-2	231.257	cry (AcOEt)		110^{12}			
5317	Fenitrothion		$C_9H_{12}NO_5PS$	122-14-5	277.234			$118^{0.05}$, 164^{1}	1.3227^{25}		
5318	Fenoxaprop-ethyl		$C_{18}H_{16}ClNO_5$	82110-72-3	361.777		85	$200^{0.001}$			sl H_2O, hx; s eth; vs ace, tol



Ethyltrimethoxysilane



1-Ethyl-2,4,5-trimethylbenzene



2-Ethyl-1,3,5-trimethylbenzene



Ethyltrimethyllead



3-Ethyl-2,4,5-trimethylpyrrole



4-Ethyl-2,6,7-trioxa-1-phosphabicyclo[2.2.2]octane



Ethyl undecanoate



Ethyl 10-undecenoate



N-Ethylurea



Ethyl vinyl ether



Ethyl Violet


α-Ethynylbenzenemethanol



α-Ethynylbenzenemethanol carbamate


1-Ethynylcyclohexanamine



1-Ethynylcyclohexanol



1-Ethynylcyclohexanol, carbamate



1-Ethynylcyclopentanol



α-Ethynyl-α-methylbenzenemethanol


Ethynylsilane



Etioporphyrin



Etofylline



Etoglucid



Etoposide



Etrimfos



Eucalyptol



Euparin



Evan's Blue



Evodiamine



Famotidine



Famphur



α-Farnesene



β-Farnesene



Farnesic acid



2-*cis*,6-*trans*-Farnesol



2-*trans*,6-*trans*-Farnesol



Farnesol acetate



Fenadiazole



Fenamiphos



Fenarimol



Fenbuconazole



Fenbutatin oxide


α-Fenchol, (±)



(±)-Fenchone



Fenfluramine



Fenitrothion



Fenoxaprop-ethyl


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5319	Fenoxycarb	Ethyl 2-(4-phenoxyphenoxy) ethylcarbamate	$C_{17}H_{19}NO_4$	79127-80-3	301.338		53				
5320	Fenpropathrin		$C_{22}H_{23}NO_3$	64257-84-7	349.423		47		1.15^{25}		
5321	Fensulfothion		$C_{11}H_{17}O_4PS_2$	115-90-2	308.354			$140^{0.01}$	1.202^{20}		
5322	Fentanyl		$C_{22}H_{28}N_2O$	437-38-7	336.469		87.5				
5323	Fenthion		$C_{10}H_{15}O_3PS_2$	55-38-9	278.328		7.5	$87^{0.01}$	1.246^{20}		
5324	Fenvalerate		$C_{25}H_{22}ClNO_3$	51630-58-1	419.901			dec	1.15^{25}		
5325	Ferbam	Iron, tris(dimethylcarbamodithioato-*S,S'*)-, (OC-6-11)-	$C_9H_{18}FeN_3S_6$	14484-64-1	416.494		180 dec				
5326	Ferrocene	Dicyclopentadienyl iron	$C_{10}H_{10}Fe$	102-54-5	186.031		172.5	249			i H_2O
5327	Ferrous gluconate		$C_{12}H_{22}FeO_{14}$	299-29-6	446.140	ye-gray pow (w)					s H_2O; i EtOH
5328	Ferrous lactate		$C_6H_{10}FeO_6$	5905-52-2	233.984	grn-wh pow (hyd)					s H_2O; i EtOH
5329	Fichtelite	18-Norabietane	$C_{19}H_{34}$	2221-95-6	262.473	cry	46	236^{43}	0.9380^{22}	1.5052^{20}	
5330	Finasteride	Proscar	$C_{23}H_{36}N_2O_2$	98319-26-7	372.544	wh cry	252				sl H_2O; s chl, EtOH, MeOH, DMSO
5331	Fisetin		$C_{15}H_{10}O_6$	528-48-3	286.236	lt ye nd (dil al, + 1 w)	330				i H_2O; s EtOH, ace; sl eth, bz, peth
5332	Flavine adenine dinucleotide	FAD	$C_{27}H_{33}N_9O_{15}P_2$	146-14-5	785.550	ye cry (w)					
5333	Florantyrone		$C_{20}H_{14}O_3$	519-95-9	302.323	ye cry (HOAc)	208				s EtOH, MeOH
5334	Fluazipop-butyl		$C_{19}H_{20}F_3NO_4$	79241-46-6	383.362	pale ye liq	5				
5335	Flubenzimine		$C_{17}H_{10}F_6N_4S$	37893-02-0	416.343	ye cry	119				sl H_2O
5336	Fluchloralin		$C_{12}H_{13}ClF_3N_3O_4$	33245-39-5	355.697		42				
5337	Flucythrinate	Cythrin	$C_{26}H_{23}F_2NO_4$	70124-77-5	451.463			$108^{0.35}$	1.189^{22}		
5338	Fludrocortisone		$C_{21}H_{29}FO_5$	127-31-1	380.450	cry (EtOH)	261 dec				
5339	Flumethiazide	Trifluoromethylthiazide	$C_8H_6F_3N_3O_4S_2$	148-56-1	329.277	cry	306				sl H_2O; i bz, tol; s MeOH, EtOH, DMF
5340	Fluocinolone acetonide		$C_{24}H_{30}F_2O_6$	67-73-2	452.488	cry (ace/hx)	266 dec				
5341	Fluoranthene	1,2-(1,8-Naphthylene)benzene	$C_{16}H_{10}$	206-44-0	202.250	pa ye nd or pl (al)	110.19	384	1.252^{0}		i H_2O; s EtOH, eth, bz, chl, CS_2
5342	9*H*-Fluoren-2-amine		$C_{13}H_{11}N$	153-78-6	181.233	pl or nd (dil al)	130.3				i H_2O; s EtOH, eth, ctc, CS_2
5343	9*H*-Fluorene	2,2'-Methylenebiphenyl	$C_{13}H_{10}$	86-73-7	166.218	lf (al)	114.77	295	1.203^{0}		i H_2O; sl EtOH; s eth, ace, bz, CS_2
5344	9*H*-Fluorene-9-carboxylic acid		$C_{14}H_{10}O_2$	1989-33-9	210.228		226				
5345	9*H*-Fluorene-2,7-diamine	2,7-Diaminofluorene	$C_{13}H_{12}N_2$	525-64-4	196.247	nd (w), pr (bz), pl (eth)	166				i H_2O; s EtOH, chl
5346	9*H*-Fluorene-9-methanol		$C_{14}H_{12}O$	24324-17-2	196.244		105.0				
5347	9*H*-Fluoren-9-ol		$C_{13}H_{10}O$	1689-64-1	182.217	hex nd (w, peth)	156.0				sl H_2O, peth, EtOH; s eth, ace; vs bz
5348	9*H*-Fluoren-9-one		$C_{13}H_8O$	486-25-9	180.202	ye orth bipym (al, bz-peth)	84	341.5	1.1300^{99}	1.6309^{99}	i H_2O; s EtOH, ace, bz; vs tol; sl ctc
5349	Fluorescein		$C_{20}H_{12}O_5$	2321-07-5	332.306	red orth pr	315 dec				sl H_2O, EtOH, eth; vs ace; s py, MeOH
5350	Fluorescein sodium	CI Acid Yellow 73	$C_{20}H_{10}Na_2O_5$	518-47-8	376.270	ye pow					s H_2O, EtOH, glycerol, dil acid
5351	2-Fluoroacetamide	Fluoroacetic acid amide	C_2H_4FNO	640-19-7	77.057		108	sub			s H_2O, ace; sl chl
5352	Fluoroacetic acid	Fluoroethanoic acid	$C_2H_3FO_2$	144-49-0	78.042	nd	35.2	168	1.3693^{36}		s H_2O, EtOH
5353	Fluoroacetyl chloride		C_2H_2ClFO	359-06-8	96.487	liq		$72; 23^{105}$			
5354	Fluoroacetylene	Fluoroethyne	C_2HF	2713-09-9	44.027	gas	-196	-105 exp			
5355	2-Fluoroaniline		C_6H_6FN	348-54-9	111.117	pa ye liq	-34.6	$175; 55^{12}$	1.1513^{21}	1.5421^{20}	i H_2O; s EtOH, eth; sl ctc
5356	3-Fluoroaniline		C_6H_6FN	372-19-0	111.117			188	1.1561^{19}	1.5436^{20}	sl H_2O, chl; s EtOH, eth
5357	4-Fluoroaniline		C_6H_6FN	371-40-4	111.117	pa ye liq	-0.8	$182; 85^{19}$	1.1725^{20}	1.5195^{20}	sl H_2O, ctc; s EtOH, eth
5358	2-Fluorobenzaldehyde		C_7H_5FO	446-52-6	124.112	liq	-44.5	175	1.178^{25}	1.5234^{20}	
5359	3-Fluorobenzaldehyde		C_7H_5FO	456-48-4	124.112			173	1.17^{25}	1.5206^{20}	
5360	4-Fluorobenzaldehyde		C_7H_5FO	459-57-4	124.112	liq	-10	181.5	1.1810^{19}		



Fenoxycarb



Fenpropathrin



Fensulfothion



Fentanyl



Fenthion



Fenvalerate



Ferbam



Ferrocene



Ferrous gluconate



Ferrous lactate



Fichtelite



Finasteride



Fisetin



Flavine adenine dinucleotide



Florantyrone



Fluazipop-butyl



Flubenzimine



Fluchloralin



Flucythrinate



Fludrocortisone



Flumethiazide



Fluocinolone acetonide



Fluoranthene



9*H*-Fluoren-2-amine



9*H*-Fluorene



9*H*-Fluorene-9-carboxylic acid



9*H*-Fluorene-2,7-diamine



9*H*-Fluorene-9-methanol



9*H*-Fluoren-9-ol



9*H*-Fluoren-9-one


Fluorescein



Fluorescein sodium



2-Fluoroacetamide



Fluoroacetic acid



Fluoroacetyl chloride


Fluoroacetylene



2-Fluoroaniline


3-Fluoroaniline


4-Fluoroaniline



2-Fluorobenzaldehyde



3-Fluorobenzaldehyde



4-Fluorobenzaldehyde


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5361	Fluorobenzene		C_6H_5F	462-06-6	96.102	liq	-42.18	84.73	1.0225^{20}	1.4684^{30}	sl H_2O; vs bz, eth, EtOH, lig
5362	4-Fluorobenzeneacetic acid		$C_8H_7FO_2$	405-50-5	154.139	cry (chl)	86	164^{2}			
5363	2-Fluorobenzeneacetonitrile		C_8H_6FN	326-62-5	135.139			232; 102^{10}	1.059^{25}	1.5009^{20}	
5364	4-Fluorobenzeneacetonitrile		C_8H_6FN	459-22-3	135.139		86.0	228; 119^{18}	1.1390^{20}	1.5002^{20}	
5365	4-Fluorobenzenemethanamine		C_7H_8FN	140-75-0	125.144			183		1.5139^{20}	
5366	4-Fluorobenzenemethanol		C_7H_7FO	459-56-3	126.128		23	210		1.5080^{20}	
5367	4-Fluorobenzenesulfonyl chloride		$C_6H_4ClFO_2S$	349-88-2	194.611	pl or nd	30	106^{9}			vs bz, eth, chl
5368	2-Fluorobenzoic acid		$C_7H_5FO_2$	445-29-4	140.112	nd (a)	126.5		1.460^{25}		sl H_2O; vs EtOH, eth; i bz; s chl
5369	3-Fluorobenzoic acid		$C_7H_5FO_2$	455-38-9	140.112	lf (w)	124		1.474^{25}		sl H_2O; s eth
5370	4-Fluorobenzoic acid		$C_7H_5FO_2$	456-22-4	140.112	pr (w), mcl pr (w)	185		1.479^{25}		sl H_2O, ace; s EtOH, eth
5371	2-Fluorobenzonitrile		C_7H_4FN	394-47-8	121.112			93^{22}			
5372	4-Fluorobenzonitrile		C_7H_4FN	1194-02-1	121.112	nd (peth)	34.8	188.8	1.1070^{55}	1.4925^{55}	sl chl; s peth
5373	2-Fluorobenzoyl chloride		C_7H_4ClFO	393-52-2	158.557		2.0	91^{15}	1.328^{25}	1.5365^{20}	
5374	3-Fluorobenzoyl chloride		C_7H_4ClFO	1711-07-5	158.557	liq	-30	189	1.304^{25}	1.5285^{20}	
5375	4-Fluorobenzoyl chloride		C_7H_4ClFO	403-43-0	158.557		9	82^{20}	1.342^{25}	1.5296^{20}	
5376	2-Fluoro-1,1'-biphenyl		$C_{12}H_9F$	321-60-8	172.197		73.5	248	1.2452^{25}		s EtOH, eth, chl, peth; sl lig
5377	4-Fluoro-1,1'-biphenyl		$C_{12}H_9F$	324-74-3	172.197	pr	74.2	253	1.247^{25}		sl EtOH; s eth, gl HOAc
5378	1-Fluorobutane	Butyl fluoride	C_4H_9F	2366-52-1	76.112	liq	-134	32.5	0.7789^{20}	1.3396^{20}	vs EtOH
5379	2-Fluorobutane	*sec*-Butyl fluoride	C_4H_9F	359-01-3	76.112	vol liq or gas	-121.4	25.1	0.7559^{25}		
5380	Fluorocyclohexane	Cyclohexyl fluoride	$C_6H_{11}F$	372-46-3	102.149		13	101	0.9279^{20}	1.4146^{20}	i H_2O; s py
5381	1-Fluorocyclohexene		C_6H_9F	694-51-9	100.133			96.5		1.4441^{25}	
5382	5-Fluorocytosine	4-Amino-5-fluoro-2-hydroxypyrimidine	$C_4H_4FN_3O$	2022-85-7	129.092	wh cry	296 dec				
5383	1-Fluorodecane	Decyl fluoride	$C_{10}H_{21}F$	334-56-5	160.272	liq	-35	186.2	0.8194^{20}	1.4085	vs eth
5384	Fluorodifen	2-Nitro-1-(4-nitrophenoxy)-4-(trifluoromethyl)benzene	$C_{13}H_7F_3N_2O_5$	15457-05-3	328.200		94				
5385	1-Fluoro-2,4-dinitrobenzene	2,4-Dinitrophenyl fluoride	$C_6H_3FN_2O_4$	70-34-8	186.097		25.8	296	1.4718^{54}	1.5690^{20}	s EtOH; sl chl
5386	Fluoroethane	Ethyl fluoride	C_2H_5F	353-36-6	48.059	col gas	-143.2	-37.7	0.7182^{20} (p>1 atm	1.2656^{20}	sl H_2O; vs EtOH, eth
5387	2-Fluoroethanol	Ethylene fluorohydrin	C_2H_5FO	371-62-0	64.058	liq	-26.4	103.5	1.1040^{20}	1.3647^{18}	msc H_2O, EtOH, eth; vs ace; sl chl
5388	Fluoroethene	Vinyl fluoride	C_2H_3F	75-02-5	46.043	col gas	-160.5	-72			i H_2O; s EtOH, ace
5389	1-Fluoroheptane		$C_7H_{15}F$	661-11-0	118.192	liq	-73	117.9	0.8062^{20}	1.3854^{20}	i H_2O; s eth, ace, bz; vs peth
5390	1-Fluorohexane	Hexyl fluoride	$C_6H_{13}F$	373-14-8	104.165	liq	-103	91.5	0.7995^{20}	1.3738^{20}	s eth, bz
5391	1-Fluoro-2-iodobenzene		C_6H_4FI	348-52-7	221.998	liq	-41.5	188.6		1.5910^{20}	s ace, bz, chl
5392	1-Fluoro-4-iodobenzene		C_6H_4FI	352-34-1	221.998	liq	-27	183	1.9523^{15}	1.5270^{22}	i H_2O; s EtOH, eth, ace
5393	1-Fluoro-3-isothiocyanatobenzene		C_7H_4FNS	404-72-8	153.177			227	1.27^{25}	1.6186^{20}	
5394	1-Fluoro-4-isothiocyanatobenzene		C_7H_4FNS	1544-68-9	153.177		27	228			
5395	Fluoromethane	Methyl fluoride	CH_3F	593-53-3	34.033	col gas	-141.8	-78.4	0.557^{25} (p>1 atm)	1.1674^{25}	sl H_2O, bz, chl; vs EtOH, eth
5396	1-Fluoro-2-methoxybenzene		C_7H_7FO	321-28-8	126.128	liq	-39	154.5	1.5489^{17}	1.4969^{17}	i H_2O; s eth, ctc
5397	1-Fluoro-3-methoxybenzene		C_7H_7FO	456-49-5	126.128	liq	-35	159; 51^{14}	1.104^{25}	1.4876^{20}	
5398	1-Fluoro-4-methoxybenzene		C_7H_7FO	459-60-9	126.128	liq	-45	157	1.1781^{18}	1.4886^{18}	s eth
5399	4-Fluoro-2-methylaniline		C_7H_8FN	452-71-1	125.144		14.2	94^{16}	1.1263^{18}	1.5363^{18}	s eth, ace, bz, ctc
5400	(Fluoromethyl)benzene		C_7H_7F	350-50-5	110.129	liq	-35	140; 40^{14}	1.0228^{25}	1.4892^{25}	s ctc
5401	2-Fluoro-4-methyl-1-nitrobenzene	3-Fluoro-4-nitrotoluene	$C_7H_6FNO_2$	446-34-4	155.127	nd (al)	53.2	97^{3}	1.4380^{25}		
5402	2-Fluoro-2-methylpropane	*tert*-Butyl fluoride	C_4H_9F	353-61-7	76.112	col gas		12.1			
5403	1-Fluoronaphthalene		$C_{10}H_7F$	321-38-0	146.161	liq	-9	215; 80^{11}	1.1322^{20}	1.5939^{20}	i H_2O; s EtOH, eth, bz, chl, HOAc
5404	2-Fluoronaphthalene		$C_{10}H_7F$	323-09-1	146.161	nd (al)	61	212; 90^{16}			i H_2O; s EtOH, eth, bz, chl, HOAc
5405	1-Fluoro-2-nitrobenzene	*o*-Fluoronitrobenzene	$C_6H_4FNO_2$	1493-27-2	141.100	ye liq	-6	dec 215	1.3285^{18}	1.5489^{17}	vs eth, EtOH
5406	1-Fluoro-3-nitrobenzene	*m*-Fluoronitrobenzene	$C_6H_4FNO_2$	402-67-5	141.100	ye cry	41	199; 86^{19}	1.3254^{19}	1.5262^{15}	i H_2O; s EtOH, eth; sl bz
5407	1-Fluoro-4-nitrobenzene	*p*-Fluoronitrobenzene	$C_6H_4FNO_2$	350-46-9	141.100	ye nd	21	205	1.3300^{20}	1.5316^{20}	i H_2O; s EtOH, eth; sl ctc
5408	1-Fluorooctane	Octyl fluoride	$C_8H_{17}F$	463-11-6	132.219	liq	-64	142.3	0.8116^{20}	1.3946^{20}	
5409	1-Fluoropentane	Pentyl fluoride	$C_5H_{11}F$	592-50-7	90.139	liq	-120	62.8	0.7907^{20}	1.3591^{2-}	vs eth, EtOH
5410	2-Fluorophenol		C_6H_5FO	367-12-4	112.101		16.1	151.5	1.120^{25}	1.5144^{20}	s H_2O



Fluorobenzene



4-Fluorobenzeneacetic acid



2-Fluorobenzeneacetonitrile



4-Fluorobenzeneacetonitrile



4-Fluorobenzenemethanamine



4-Fluorobenzenemethanol



4-Fluorobenzenesulfonyl chloride



2-Fluorobenzoic acid



3-Fluorobenzoic acid



4-Fluorobenzoic acid



2-Fluorobenzonitrile



4-Fluorobenzonitrile



2-Fluorobenzoyl chloride


3-Fluorobenzoyl chloride


4-Fluorobenzoyl chloride


2-Fluoro-1,1'-biphenyl



4-Fluoro-1,1'-biphenyl



1-Fluorobutane



2-Fluorobutane



Fluorocyclohexane


1-Fluorocyclohexene



5-Fluorocytosine


1-Fluorodecane



Fluorodifen



1-Fluoro-2,4-dinitrobenzene


Fluoroethane



2-Fluoroethanol



Fluoroethene



1-Fluoroheptane


1-Fluorohexane



1-Fluoro-2-iodobenzene



1-Fluoro-4-iodobenzene



1-Fluoro-3-isothiocyanatobenzene



1-Fluoro-4-isothiocyanatobenzene



Fluoromethane



1-Fluoro-2-methoxybenzene


1-Fluoro-3-methoxybenzene



1-Fluoro-4-methoxybenzene



4-Fluoro-2-methylaniline



(Fluoromethyl)benzene



2-Fluoro-4-methyl-1-nitrobenzene



2-Fluoro-2-methylpropane


1-Fluoronaphthalene



2-Fluoronaphthalene


1-Fluoro-2-nitrobenzene


1-Fluoro-3-nitrobenzene



1-Fluoro-4-nitrobenzene



1-Fluorooctane



1-Fluoropentane



2-Fluorophenol

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5411	3-Fluorophenol		C_6H_5FO	372-20-3	112.101		13.7	178	1.238^{25}	1.5140^{20}	
5412	4-Fluorophenol		C_6H_5FO	371-41-5	112.101		48	185.5	1.1889^{56}		sl H_2O; s ace, peth
5413	2-Fluoro-1-phenylethanone		C_8H_7FO	450-95-3	138.139	pl	29	90^{12}	1.152^{20}	1.5200^{20}	
5414	1-(4-Fluorophenyl)ethanone		C_8H_7FO	403-42-9	138.139	liq	-45	196	1.1382^{25}	1.5081^{25}	i H_2O; s bz, chl
5415	1-Fluoropropane	Propyl fluoride	C_3H_7F	460-13-9	62.086	col gas	-159	-2.5	0.7596^{20} (p>1 atm	1.3115^{20}	sl H_2O; vs EtOH, eth
5416	2-Fluoropropane	Isopropyl fluoride	C_3H_7F	420-26-8	62.086	gas		-9.4			sl H_2O
5417	1-Fluoro-2-propanone	Fluoroacetone	C_3H_5FO	430-51-3	76.069			77	1.0288^{20}	1.3700^{20}	
5418	*cis*-1-Fluoropropene		C_3H_5F	19184-10-2	60.070	col gas		≈-20			
5419	*trans*-1-Fluoropropene		C_3H_5F	20327-65-5	60.070	col gas	≈-20				
5420	2-Fluoropropene		C_3H_5F	1184-60-7	60.070	col gas		-24			
5421	3-Fluoropropene		C_3H_5F	818-92-8	60.070	col gas		-3			sl H_2O; vs EtOH, eth; s chl
5422	2-Fluoropyridine		C_5H_4FN	372-48-5	97.091			125	1.1280^{20}	1.4574^{20}	
5423	3-Fluoropyridine		C_5H_4FN	372-47-4	97.091	liq		107	1.130	1.4720^{20}	
5424	2-Fluorotoluene		C_7H_7F	95-52-3	110.129	liq	-62	115	1.0041^{13}	1.4704^{20}	i H_2O; vs EtOH, eth
5425	3-Fluorotoluene		C_7H_7F	352-70-5	110.129	liq	-87	115	0.9974^{20}	1.4691^{20}	i H_2O; vs EtOH, eth
5426	4-Fluorotoluene		C_7H_7F	352-32-9	110.129	liq	-56	116.6	0.9975^{20}	1.4699^{20}	i H_2O; vs EtOH, eth
5427	1-Fluoro-2-(trichloromethyl) benzene		$C_7H_4Cl_3F$	488-98-2	213.464			95^{12}, 75^{5}	1.453^{25}	1.5432^{20}	
5428	1-Fluoro-2-(trifluoromethyl) benzene		$C_7H_4F_4$	392-85-8	164.101			114.5	1.293^{25}	1.4040^{25}	
5429	1-Fluoro-3-(trifluoromethyl) benzene		$C_7H_4F_4$	401-80-9	164.101	liq	-81.5	101.5	1.3021^{17}		
5430	1-Fluoro-4-(trifluoromethyl) benzene		$C_7H_4F_4$	402-44-8	164.101	liq	-41.7	103.5	1.293^{25}	1.4025^{20}	
5431	Fluorotrimethylsilane		C_3H_9FSi	420-56-4	92.187	vol liq or gas		16.4			
5432	5-Fluorouracil	5-Fluoro-2,4(1*H*,3*H*)-Pyrimidinedione	$C_4H_3FN_2O_2$	51-21-8	130.077	cry (w, MeOH-eth)	283	sub 190			
5433	Fluoxetine		$C_{17}H_{18}F_3NO$	54910-89-3	309.326	oil					
5434	Fluoxymesterone		$C_{20}H_{29}FO_3$	76-43-7	336.440		270				
5435	Fluphenazine		$C_{22}H_{26}F_3N_3OS$	69-23-8	437.520			$251^{0.3}$			
5436	Fluprednisolone		$C_{21}H_{27}FO_5$	53-34-9	378.434		210				
5437	Flurandrenolide	Fludroxycortide	$C_{24}H_{33}FO_6$	1524-88-5	436.513	cry (ace/hx)	251				
5438	Flurazepam		$C_{21}H_{23}ClFN_3O$	17617-23-1	387.878	wh rods (eth/peth)	80				
5439	Fluridone		$C_{19}H_{14}F_3NO$	59756-60-4	329.315		155				
5440	Fluroxypyr	[(4-Amino-3,5-dichloro-6-fluoro-2-pyridyl)oxy]acetic acid	$C_7H_5Cl_2FN_2O_3$	69377-81-7	255.030		232				
5441	Fluvalinate		$C_{26}H_{22}ClF_3N_2O_3$	102851-06-9	502.912			>450	1.29^{25}		
5442	Folic acid	Vitamin Bc	$C_{19}H_{19}N_7O_6$	59-30-3	441.397	ye-oran nd (w)	250 dec				vs py, EtOH, HOAc
5443	Folinic acid	5-Formyl-5,6,7,8-tetrahydrofolic acid	$C_{20}H_{23}N_7O_7$	58-05-9	473.440	cry (w + 3)	245 dec				sl H_2O
5444	Folpet	1*H*-Isoindole-1,3(2*H*)-dione, 2-[(trichloromethyl)thio]-	$C_9H_4Cl_3NO_2S$	133-07-3	296.558		177				
5445	Fomesafen		$C_{15}H_{10}ClF_3N_2O_6S$	72178-02-0	438.762		220		1.28^{20}		
5446	Fomocaine	4-[3-[4-(Phenoxymethyl)phenyl] propyl]morpholine	$C_{20}H_{25}NO_2$	17692-39-6	311.419	col cry	53	$239^{1.1}$			
5447	Fonofos	Phosphonodithioic acid, ethyl-, *O*-ethyl *S*-phenyl ester	$C_{10}H_{15}OPS_2$	944-22-9	246.329			$130^{0.1}$	1.16^{25}		
5448	Formaldehyde	Methanal	CH_2O	50-00-0	30.026	col gas	-92	-19.1	0.815^{-20}		s H_2O, EtOH, chl; msc eth, ace, bz
5449	Formaldehyde oxime		CH_3NO	75-17-2	45.041		1.3	109^{15}	1.133^{25}		s H_2O; vs EtOH, eth
5450	Formamide	Methanamide	CH_3NO	75-12-7	45.041		2.49	220	1.1334^{20}	1.4472^{20}	msc H_2O, EtOH; sl eth; s ace; i bz, chl
5451	Formamidinesulfinic acid	Aminoiminomethanesulfinic acid	$CH_4N_2O_2S$	1758-73-2	108.120	nd (al)	144 dec				vs H_2O; i eth, bz
5452	Formetanate hydrochloride		$C_{11}H_{16}ClN_3O_2$	23422-53-9	257.717	pow	201 dec				vs H_2O; s MeOH; sl ace, hx, chl
5453	Formic acid	Methanoic acid	CH_2O_2	64-18-6	46.026		8.3	101	1.220^{20}	1.3714^{20}	msc H_2O, EtOH, eth; vs ace; s bz, tol
5454	*N*-Formimidoyl-*L*-glutamic acid	*N*-(Iminomethyl)-*L*-glutamic acid	$C_6H_{10}N_2O_4$	816-90-0	174.154		90				
5455	Formononetin	7-Hydroxy-3-(4-methoxyphenyl) -4*H*-1-benzopyran-4-one	$C_{16}H_{12}O_4$	485-72-3	268.264		256.5				


3-Fluorophenol


4-Fluorophenol


2-Fluoro-1-phenylethanone


1-(4-Fluorophenyl)ethanone


1-Fluoropropane


2-Fluoropropane


1-Fluoro-2-propanone


cis-1-Fluoropropene


trans-1-Fluoropropene


2-Fluoropropene



3-Fluoropropene



2-Fluoropyridine



3-Fluoropyridine



2-Fluorotoluene



3-Fluorotoluene


4-Fluorotoluene



1-Fluoro-2-(trichloromethyl)benzene



1-Fluoro-2-(trifluoromethyl)benzene



1-Fluoro-3-(trifluoromethyl)benzene



1-Fluoro-4-(trifluoromethyl)benzene



Fluorotrimethylsilane



5-Fluorouracil



Fluoxetine



Fluoxymesterone



Fluphenazine



Fluprednisolone



Flurandrenolide



Flurazepam



Fluridone



Fluroxypyr



Fluvalinate



Folic acid


Folinic acid


Folpet


Fomesafen



Fomocaine



Fonofos


Formaldehyde



Formaldehyde oxime



Formamide


Formamidinesulfinic acid



Formetanate hydrochloride



Formic acid



N-Formimidoyl-*L*-glutamic acid



Formononetin


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5456	Formothion		$C_6H_{12}NO_4PS_2$	2540-82-1	257.267	visc ye oil	25.5	dec	1.361^{20}	1.5541^{20}	sl H_2O; misc os
5457	2-Formylbenzoic acid		$C_8H_6O_3$	119-67-5	150.132		98		1.404^{25}		s H_2O; vs EtOH, eth
5458	3-Formylbenzoic acid		$C_8H_6O_3$	619-21-6	150.132	nd (w)	175				vs H_2O, eth, EtOH
5459	4-Formylbenzoic acid		$C_8H_6O_3$	619-66-9	150.132		247				sl H_2O; vs EtOH; s eth, chl
5460	3-Formylbenzonitrile		C_8H_5NO	24964-64-5	131.132		76.5	210			vs H_2O, EtOH, eth, chl
5461	4-Formylbenzonitrile		C_8H_5NO	105-07-7	131.132		100.5	133^{12}			s H_2O; vs EtOH, eth, chl
5462	6-Formyl-2,3-dimethoxybenzoic acid	Opianic acid	$C_{10}H_{10}O_5$	519-05-1	210.183	nd (w)	150				s EtOH, eth
5463	Formylferrocene		$C_{11}H_{10}FeO$	12093-10-6	214.041		118.5	$70^{0.1}$			
5464	Formyl fluoride	Fluoroformaldehyde	CHFO	1493-02-3	48.016	col gas	-142.2	-26.5	1.1950^{-30}		
5465	*N*-(4-Formylphenyl)acetamide		$C_9H_9NO_2$	122-85-0	163.173	pr (w)	158.0				vs H_2O, bz
5466	Fosetyl-Al	Aluminum tris(*O*-ethylphosphonate)	$C_6H_{18}AlO_9P_3$	39148-24-8	354.105		>300				
5467	Fosthietan		$C_6H_{12}NO_3PS_2$	21548-32-3	241.268	ye oil			1.3^{25}	1.5348^{25}	s ace, chl, MeOH, tol
5468	Fraxin		$C_{16}H_{18}O_{10}$	524-30-1	370.308	ye nd (al)	205				
5469	*DL*-Fructose	α-Acrose	$C_6H_{12}O_6$	6035-50-3	180.155	nd	130		1.665^{16}		
5470	*L*-Fructose		$C_6H_{12}O_6$	7776-48-9	180.155	wh cry	102				s H_2O
5471	β-*D*-Fructose	β-Levulose	$C_6H_{12}O_6$	53188-23-1	180.155	pr or nd (w) orth pr (al)	103 dec		1.60^{20}		vs H_2O, ace; s EtOH, MeOH, py
5472	*D*-Fructose 6-phosphate	Hexose monophosphate	$C_6H_{13}O_9P$	643-13-0	260.135						vs H_2O
5473	Fucoxanthin		$C_{42}H_{58}O_6$	3351-86-8	658.905	red pl (eth) hex pl (dil al)	168				vs eth, EtOH
5474	Fulminic acid	Carbyloxime	CHNO	506-85-4	43.025		unstable in pure form				s eth
5475	Fulvene		C_6H_6	497-20-1	78.112			7^{56}	0.8241^{20}	1.4920^{20}	i H_2O; s bz, chl
5476	Fumaric acid	*trans*-2-Butenedioic acid	$C_4H_4O_4$	110-17-8	116.073	nd, mcl pr or lf (w)	287 dec	sub 165	1.635^{20}		sl H_2O, eth, ace; s EtOH, con sulf
5477	Fumigatin	3-Hydroxy-2-methoxy-5-methyl-2,5-cyclohexadiene-1,4-dione	$C_8H_8O_4$	484-89-9	168.148	br nd or pl (peth)	116				vs ace, bz, eth, EtOH
5478	Furan	Oxacyclopentadiene	C_4H_4O	110-00-9	68.074	liq	-85.61	31.5	0.9514^{20}	1.4214^{20}	sl H_2O, chl; vs EtOH, eth; s ace, bz
5479	2-Furanacetic acid		$C_6H_6O_3$	2745-26-8	126.110	lf(peth)	68.5	$102^{0.4}$			s H_2O, bz, MeOH, peth
5480	2-Furancarbonitrile		C_5H_3NO	617-90-3	93.084			147	1.0822^{20}	1.4798^{20}	s EtOH, eth
5481	2-Furancarbonyl chloride		$C_5H_3ClO_2$	527-69-5	130.530	liq	-1.0	173	1.324^{25}	1.5310^{20}	i H_2O; s eth, chl; sl ctc
5482	3-Furancarboxaldehyde		$C_5H_4O_2$	498-60-2	96.085			145; 71^{43}	1.110^{20}	1.4945^{20}	
5483	2-Furancarboxylic acid	2-Furoic acid	$C_5H_4O_3$	88-14-2	112.084	mcl nd or lf (w)	133.5	231			s H_2O, EtOH; vs eth; sl ace
5484	3-Furancarboxylic acid		$C_5H_4O_3$	488-93-7	112.084	nd (w)	122.5	sub 105			sl H_2O; s EtOH, AcOEt; vs eth
5485	2,5-Furandicarboxylic acid	Dehydromucic acid	$C_6H_4O_5$	3238-40-2	156.093	nd (w), lf (al)	342	sub	1.7400^{20}		sl H_2O, EtOH
5486	2-Furanmethanamine	Furfurylamine	C_5H_7NO	617-89-0	97.116			145.5	1.0995^{20}	1.4908^{20}	msc H_2O, EtOH; s eth, chl
5487	2-Furanmethanediol diacetate		$C_9H_{10}O_5$	613-75-2	198.172	nd or pl (eth-peth)	53.3	220			vs bz, eth, EtOH
5488	2-Furanmethanethiol		C_5H_6OS	98-02-2	114.166			157	1.1319^{20}	1.5329^{20}	i H_2O; sl chl
5489	2-Furanmethanol acetate		$C_7H_8O_3$	623-17-6	140.137			179	1.1175^{20}	1.4327^{20}	i H_2O; s EtOH, eth
5490	4-(2-Furanyl)-2-butanone		$C_8H_{10}O_2$	699-17-2	138.164	oil		203	1.0361^{19}	1.4696^{17}	
5491	4-(2-Furanyl)-3-buten-2-one		$C_8H_8O_2$	623-15-4	136.149		39.5	dec 229; 113^{10}	1.0496^{57}	1.5788^{45}	i H_2O; vs EtOH, eth, chl; s peth
5492	1-(2-Furanyl)ethanone		$C_6H_6O_2$	1192-62-7	110.111	cry (lig)	33	175	1.098^{20}	1.5017^{20}	i H_2O; s EtOH, eth
5493	2-Furanylmethyl pentanoate	Furfuryl valerate	$C_{10}H_{14}O_3$	36701-01-6	182.216			228; 82^{1}	1.0284^{20}		vs eth, EtOH
5494	3-(2-Furanyl)-1-phenyl-2-propen-1-one		$C_{13}H_{10}O_2$	717-21-5	198.217		47	317	1.1140^{20}		s EtOH, eth
5495	1-(2-Furanyl)-1-propanone		$C_7H_8O_2$	3194-15-8	124.138	cry	28	88^{14}	1.0626^{28}	1.4922^{25}	s eth; sl ctc
5496	1-(2-Furanyl)-2-propanone	2-Furfuryl methyl ketone	$C_7H_8O_2$	6975-60-6	124.138		29	179.5	1.104^{20}	1.5035^{20}	
5497	3-(2-Furanyl)-2-propenal		$C_7H_6O_2$	623-30-3	122.122		54	135^{14}			i H_2O; msc EtOH; s eth; sl chl
5498	3-(2-Furanyl)-2-propenenitrile	2-Furanacrylonitrile	C_7H_5NO	7187-01-1	119.121		38	96		1.5824^{25}	vs tol



Formothion



2-Formylbenzoic acid



3-Formylbenzoic acid


4-Formylbenzoic acid



3-Formylbenzonitrile



4-Formylbenzonitrile



6-Formyl-2,3-dimethoxybenzoic acid



Formylferrocene



Formyl fluoride



N-(4-Formylphenyl)acetamide



Fosetyl-Al



Fosthietan



Fraxin


DL-Fructose


L-Fructose



β-*D*-Fructose



D-Fructose 6-phosphate


Fucoxanthin



Fulminic acid



Fulvene



Fumaric acid



Fumigatin



Furan



2-Furanacetic acid



2-Furancarbonitrile



2-Furancarbonyl chloride



3-Furancarboxaldehyde



2-Furancarboxylic acid



3-Furancarboxylic acid



2,5-Furandicarboxylic acid



2-Furanmethanamine


2-Furanmethanediol diacetate



2-Furanmethanethiol



2-Furanmethanol acetate



4-(2-Furanyl)-2-butanone



4-(2-Furanyl)-3-buten-2-one



1-(2-Furanyl)ethanone



2-Furanylmethyl pentanoate


3-(2-Furanyl)-1-phenyl-2-propen-1-one



1-(2-Furanyl)-1-propanone



1-(2-Furanyl)-2-propanone



3-(2-Furanyl)-2-propenal



3-(2-Furanyl)-2-propenenitrile


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5499	3-(2-Furanyl)-2-propenoic acid	2-Furanacrylic acid	$C_7H_6O_3$	539-47-9	138.121	nd (w)	141	286			vs eth, EtOH
5500	Furazolidone	3-[[(5-Nitro-2-furanyl) methylene]amino]-2-oxazolidinone	$C_8H_7N_3O_5$	67-45-8	225.159		255				
5501	Furethidine		$C_{21}H_{31}NO_4$	2385-81-1	361.476		28	$210^{0.5}$		1.5219^{20}	
5502	Furfural	2-Furaldehyde	$C_5H_4O_2$	98-01-1	96.085	liq	-38.1	161.7	1.1594^{20}	1.5261^{20}	s H_2O, bz, chl; vs EtOH, ace; msc eth
5503	Furfuryl alcohol	2-Furanmethanol	$C_5H_6O_2$	98-00-0	98.101	col-ye liq	-14.6	171	1.1296^{20}	1.4869^{20}	msc H_2O; vs EtOH, eth; s chl
5504	Furfuryl propanoate	2-Furanmethanol, propanoate	$C_8H_{10}O_3$	623-19-8	154.163			195	1.1085^{20}		sl H_2O; s EtOH, ace; msc eth
5505	Furoin	1,2-Di-2-furanyl-2-hydroxyethanone	$C_{10}H_8O_4$	552-86-3	192.169	nd (al)	138.5				sl H_2O, EtOH, chl; s eth, MeOH
5506	Furonazide		$C_{12}H_{11}N_3O_2$	3460-67-1	229.234		202.3				
5507	Furosemide		$C_{12}H_{11}ClN_2O_5S$	54-31-9	330.743		204 dec				
5508	Fursultiamine		$C_{17}H_{26}N_4O_3S_2$	804-30-8	398.543	col pr	132 dec		1.29		sl H_2O
5509	Furylfuramide, (*E*)	2-(2-Furanyl)-3-(5-nitro-2-furanyl)-2-propenamide	$C_{11}H_8N_2O_5$	18819-45-9	248.192	cry	154				
5510	Fusarenon X		$C_{17}H_{22}O_8$	23255-69-8	354.352	cry	182				
5511	Galactaric acid	Mucic acid	$C_6H_{10}O_8$	526-99-8	210.138	pr (w)	255 dec				
5512	Galactitol	Dulcose	$C_6H_{14}O_6$	608-66-2	182.171	cry (dil MeOH)	189.5	277^{1}	1.47^{20}		s H_2O; sl EtOH, py; i eth, bz
5513	*D*-Galactonic acid, γ-lactone		$C_6H_{10}O_6$	2782-07-2	178.139	nd (w+1), nd (al)	112				vs H_2O
5514	α-*D*-Galactopyranose		$C_6H_{12}O_6$	3646-73-9	180.155		167				
5515	4-*O*-β-*D*-Galactopyranosyl-*D*-gluconic acid	Lactobionic acid	$C_{12}H_{22}O_{12}$	96-82-2	358.296	syr					vs H_2O; sl EtOH, MeOH, HOAc; i eth
5516	*D*-Galactose		$C_6H_{12}O_6$	59-23-4	180.155	pl or pr (al)pr or nd (w+1)	170				vs H_2O; sl EtOH; i eth, bz; s py
5517	*D*-Galacturonic acid		$C_6H_{10}O_7$	685-73-4	194.139	nd (w)	166 (β)				s H_2O, EtOH; i eth
5518	Galanthamine	Lycoremine	$C_{17}H_{21}NO_3$	357-70-0	287.354	cry (bz)	126.5				vs ace, EtOH, chl
5519	Galipine	2-[2-(3,4-Dimethoxyphenyl) ethyl]-4-methoxyquinoline	$C_{20}H_{21}NO_3$	525-68-8	323.386	pr (al, eth) nd (peth)	115.5				vs ace, bz, eth, EtOH
5520	Gallamine triethiodide		$C_{30}H_{60}I_3N_3O_3$	65-29-2	891.528		147.5				vs H_2O, EtOH; sl eth, ace, bz, chl
5521	Gallein		$C_{20}H_{12}O_5$	2103-64-2	332.306	br-red pow (+1.5w) red (anh)	>300				vs ace, EtOH
5522	Ganciclovir		$C_9H_{13}N_5O_4$	82410-32-0	255.231	cry (MeOH)	250 dec				
5523	Gardol		$C_{15}H_{28}NNaO_3$	137-16-6	293.378						sl H_2O
5524	Gelsemine		$C_{20}H_{22}N_2O_2$	509-15-9	322.401	cry (ace)	178				vs ace, bz, eth, EtOH
5525	Gelsemine, monohydrochloride		$C_{20}H_{23}ClN_2O_2$	35306-33-3	358.862		326				s H_2O; sl EtOH
5526	Genistein	5,7-Dihydroxy-3-(4-hydroxyphenyl)-4*H*-1-benzopyran-4-one	$C_{15}H_{10}O_5$	446-72-0	270.237	nd(eth), pr(dil al)	301 dec				
5527	β-Gentiobiose	6-*O*-β-*D*-Glucopyranosyl-*D*-glucose	$C_{12}H_{22}O_{11}$	554-91-6	342.296	cry (EtOH)	192				s hot H_2O, hot MeOH
5528	*trans*-Geraniol		$C_{10}H_{18}O$	106-24-1	154.249		<-15	230	0.8894^{20}	1.4766^{20}	i H_2O; s EtOH, eth, ace, chl
5529	Geranyl 2-methylpropanoate		$C_{14}H_{24}O_2$	2345-26-8	224.340			136^{13}	0.8997^{15}	1.4576^{20}	
5530	Geranyl acetate		$C_{12}H_{20}O_2$	16409-44-2	196.286			115^{12}	0.9163^{15}	1.4624^{20}	
5531	Germine		$C_{27}H_{43}NO_8$	508-65-6	509.632	pr or cry (MeOH)	220				s bz, MeOH, alk, acid
5532	Gibberellic acid		$C_{19}H_{22}O_6$	77-06-5	346.374	cry (EtOAc)	234				vs ace, EtOH, MeOH
5533	Gitoxigenin		$C_{23}H_{34}O_5$	545-26-6	390.513	pr (AcOEt) pr (+w, dil al)	234				i H_2O; sl eth; s chl
5534	Gitoxin		$C_{41}H_{64}O_{14}$	4562-36-1	780.939	pr (chl-MeOH)	285 dec				
5535	*d*-Glaucine		$C_{21}H_{25}NO_4$	475-81-0	355.429	pl, pr (eth, AcOEt)	120				vs ace, EtOH, chl
5536	*D*-Glucaric acid	*D*-Tetrahydroxyadipic acid	$C_6H_{10}O_8$	87-73-0	210.138	nd (45% al)	125.5				vs H_2O, EtOH; sl eth, chl
5537	*D*-Glucitol	Sorbitol	$C_6H_{14}O_6$	50-70-4	182.171	nd (w)	111	$295^{3.5}$	1.489^{20}	1.3330^{20}	vs H_2O, ace
5538	*D*-Glucitol, hexaacetate	Sorbitol hexaacetate	$C_{18}H_{26}O_{12}$	7208-47-1	434.392	pr (w)	100.8		1.30^{20}		sl H_2O, eth; vs EtOH; s chl, AcOEt



3-(2-Furanyl)-2-propenoic acid



Furazolidone



Furethidine



Furfural



Furfuryl alcohol



Furfuryl propanoate



Furoin



Furonazide



Furosemide



Fursultiamine



Furylfuramide, (*E*)



Fusarenon X



Galactaric acid



Galactitol



D-Galactonic acid, γ-lactone



α-*D*-Galactopyranose



4-*O*-β-*D*-Galactopyranosyl-*D*-gluconic acid



D-Galactose



D-Galacturonic acid



Galanthamine



Galipine



Gallamine triethiodide



Gallein



Ganciclovir



Gardol



Gelsemine



Gelsemine, monohydrochloride



Genistein



β-Gentiobiose



trans-Geraniol



Geranyl 2-methylpropanoate



Geranyl acetate



Germine



Gibberellic acid



Gitoxigenin


Gitoxin



d-Glaucine



D-Glucaric acid



D-Glucitol



D-Glucitol, hexaacetate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5539	*D*-Gluconic acid		$C_6H_{12}O_7$	526-95-4	196.155	nd (al-eth)	131				s H_2O; sl EtOH; i eth, bz
5540	β-*D*-Glucopyranose		$C_6H_{12}O_6$	492-61-5	180.155	cry (hot EtOH)	149				
5541	6-*O*-α-*D*-Glucopyranosyl-*D*-fructose	Palatinose	$C_{12}H_{22}O_{11}$	13718-94-0	342.296						s H_2O
5542	2-(β-*D*-Glucopyranosyloxy) benzaldehyde	Helicin	$C_{13}H_{16}O_7$	618-65-5	284.262	nd (w)	175				vs H_2O, EtOH
5543	7-(β-*D*-Glucopyranosyloxy)-2*H*-1-benzopyran-2-one	Skimmin	$C_{15}H_{16}O_8$	93-39-0	324.283	cry (w + 1)	220				s H_2O, EtOH; i eth, chl
5544	2-(β-*D*-Glucopyranosyloxy)-2-methylpropanenitrile	Linamarin	$C_{10}H_{17}NO_6$	554-35-8	247.245	nd (w, al)	145				vs ace
5545	1-[4-(β-*D*-Glucopyranosyloxy) phenyl]ethanone	Picein	$C_{14}H_{18}O_7$	530-14-3	298.289	nd (w+1), nd (MeOH)	195.5				sl H_2O; s EtOH, eth, HOAc; i chl
5546	α-*D*-Glucose		$C_6H_{12}O_6$	26655-34-5	180.155		146 dec		1.5620^{18}		vs H_2O; sl EtOH; i ace, AcOEt; s py
5547	α-*D*-Glucose pentaacetate		$C_{16}H_{22}O_{11}$	604-68-2	390.339	pl or nd (al)	113.3	sub			sl H_2O, EtOH, CS_2; s eth, chl, HOAc
5548	β-*D*-Glucose pentaacetate		$C_{16}H_{22}O_{11}$	604-69-3	390.339	nd (al)	134	sub	1.2740^{20}		i H_2O; sl EtOH, peth, eth; s bz; msc chl
5549	α-*D*-Glucose 1-phosphate		$C_6H_{13}O_9P$	59-56-3	260.135						vs H_2O
5550	*D*-Glucuronic acid		$C_6H_{10}O_7$	6556-12-3	194.139	nd (al)	165				vs H_2O, EtOH
5551	*D*-Glucuronic acid γ-lactone	*D*-Glucuronolactone	$C_6H_8O_6$	32449-92-6	176.124	mcl pl (w) cry (al)	177.5		1.76^{20}		s H_2O; sl EtOH, DMSO, MeOH; i bz
5552	*DL*-Glutamic acid		$C_5H_9NO_4$	617-65-2	147.130	orth (al,w)	199 dec		1.4601^{20}		sl H_2O, eth; i EtOH, CS_2, lig
5553	*D*-Glutamic acid		$C_5H_9NO_4$	6893-26-1	147.130	lf (w)	213 dec		1.538^{20}		sl H_2O; i EtOH, eth, ace, bz, HOAc, MeOH
5554	*L*-Glutamic acid	(*S*)-2-Aminopentanedioic acid	$C_5H_9NO_4$	56-86-0	147.130	orth (dil al)	160 dec	sub 175	1.538^{20}		sl H_2O
5555	*L*-Glutamic acid, hydrochloride		$C_5H_{10}ClNO_4$	138-15-8	183.591	orth pl (w)	214 dec				vs H_2O, EtOH
5556	*L*-Glutamine	2-Aminoglutaramic acid	$C_5H_{10}N_2O_3$	56-85-9	146.144	nd (w, dil al)	185 dec				s H_2O; i EtOH, eth, bz, MeOH
5557	Glutaric acid	Pentanedioic acid	$C_5H_8O_4$	110-94-1	132.116	nd (bz)	97.8	dec 303	1.429^{15}	1.4188^{106}	vs H_2O, EtOH, eth; i bz; s chl, lig
5558	Glutathione	*L*-γ-Glutamyl-*L*-cysteinylglycine	$C_{10}H_{17}N_3O_6S$	70-18-8	307.323	cry (50% al)	195				vs H_2O; i EtOH, eth; s DMF
5559	Glutathione disulfide	*L*-γ-Glutamyl-*L*-cysteinylglycine disulfide	$C_{20}H_{32}N_6O_{12}S_2$	27025-41-8	612.631	cry (EtOH aq)	179				
5560	Glutethimide		$C_{13}H_{15}NO_2$	77-21-4	217.264	cry (eth)	84				i H_2O; s EtOH; vs eth, ace
5561	Glycerol	1,2,3-Propanetriol	$C_3H_8O_3$	56-81-5	92.094	syr, orth pl	18.1	290	1.2613^{20}	1.4746^{20}	msc H_2O, EtOH; sl eth; i bz, ctc, chl
5562	Glycerol 1-acetate, (*DL*)	1,2,3-Propanetriol 1-acetate, (±)	$C_5H_{10}O_4$	93713-40-7	134.131			158^{165}, 130^{3}	1.2060^{20}	1.4157^{20}	s H_2O, EtOH; sl eth; i bz
5563	Glycerol 1-butanoate		$C_7H_{14}O_4$	557-25-5	162.184			280; 117^{10}	1.129^{18}	1.4531^{20}	vs H_2O, EtOH
5564	Glycerol 1,3-dinitrate	1,2,3-Propanetriol, 1,3-dinitrate	$C_3H_6N_2O_7$	623-87-0	182.089	pr (w), cry (eth)	26	148^{15}, 116$^{0.6}$	1.523^{20}	1.4715^{20}	vs H_2O, eth, EtOH
5565	Glycerol 1,3-di-9-octadecenoate, *cis,cis*		$C_{39}H_{72}O_5$	2465-32-9	620.986	cry (eth/ EtOH)	50.1				
5566	Glycerol 1-oleate	1-Monoolein	$C_{21}H_{40}O_4$	111-03-5	356.541	pl (al)	35	239^{3}	0.9420^{20}	1.4626^{20}	i H_2O; s EtOH, eth, chl
5567	*L*-Glycerol 1-phosphate	α-Glycerophosphoric acid	$C_3H_9O_6P$	5746-57-6	172.073	syr		dec			dec H_2O
5568	Glycerol tridecanoate	Decanoic acid glycerol triester	$C_{33}H_{62}O_6$	621-71-6	554.841	cry (peth)	32				
5569	Glycerol trielaidate	Trielaidin	$C_{57}H_{104}O_6$	537-39-3	885.432						vs bz, eth, chl
5570	Glycerol trilaurate	Trilaurin	$C_{39}H_{74}O_6$	538-24-9	639.001	nd (al)			0.8986^{55}	1.4404^{60}	i H_2O; s EtOH, eth, peth; vs ace, bz
5571	Glycerol tri-3-methylbutanoate	Triisovalerin	$C_{18}H_{32}O_6$	620-63-3	344.443			332.5	0.9984^{20}	1.4354^{20}	vs eth, EtOH
5572	Glycerol trioleate	Triolein	$C_{57}H_{104}O_6$	122-32-7	885.432	col-ye oil	-4	237^{18}	0.915^{15}	1.4676^{15}	i H_2O; sl EtOH; vs eth; s chl, peth
5573	Glycerol tripalmitate	Tripalmitin	$C_{51}H_{98}O_6$	555-44-2	807.320	nd (eth)	66.5	315	0.8752^{70}	1.4381^{80}	i H_2O; sl EtOH; vs eth; s bz, chl
5574	Glycerol tristearate	Tristearin	$C_{57}H_{110}O_6$	555-43-1	891.479				0.8559^{90}	1.4395^{80}	i H_2O, EtOH; sl bz, ctc; s ace, chl



D-Gluconic acid



β-*D*-Glucopyranose



6-*O*-α-*D*-Glucopyranosyl-*D*-fructose



2-(β-*D*-Glucopyranosyloxy)benzaldehyde



7-(β-*D*-Glucopyranosyloxy)-2*H*-1-benzopyran-2-one



2-(β-*D*-Glucopyranosyloxy)-2-methylpropanenitrile



1-[4-(β-*D*-Glucopyranosyloxy)phenyl]ethanone



α-*D*-Glucose



α-*D*-Glucose pentaacetate



β-*D*-Glucose pentaacetate



α-*D*-Glucose 1-phosphate



D-Glucuronic acid



D-Glucuronic acid γ-lactone



DL-Glutamic acid



D-Glutamic acid



L-Glutamic acid



L-Glutamic acid, hydrochloride



L-Glutamine



Glutaric acid



Glutathione



Glutathione disulfide



Glutethimide



Glycerol



Glycerol 1-acetate, (*DL*)



Glycerol 1-butanoate



Glycerol 1,3-dinitrate



Glycerol 1,3-di-9-octadecenoate, *cis,cis*



Glycerol 1-oleate



L-Glycerol 1-phosphate



Glycerol tridecanoate



Glycerol trielaidate


Glycerol trilaurate



Glycerol tri-3-methylbutanoate



Glycerol trioleate



Glycerol tripalmitate



Glycerol tristearate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5575	Glycerol tritetradecanoate	Trimyristin	$C_{45}H_{86}O_6$	555-45-3	723.161	wh-ye solid	58.5	311	0.8848^{60}	1.4428^{60}	i H_2O; sl EtOH, lig; s eth, ace, bz
5576	Glycerone phosphate	1-Hydroxy-3-(phosphonooxy)-2-propanone	$C_3H_7O_6P$	57-04-5	170.058						dec H_2O
5577	Glycine	Aminoacetic acid	$C_2H_5NO_2$	56-40-6	75.067	mcl or trg pr (dil al)	290 dec		1.161^{20}		vs H_2O; i EtOH, eth; sl ace, py
5578	Glycine, ethyl ester, hydrochloride	Ethyl aminoacetate hydrochloride	$C_4H_{10}ClNO_2$	623-33-6	139.581		144				vs H_2O, EtOH
5579	Glycine, hydrochloride		$C_2H_6ClNO_2$	6000-43-7	111.528	hyg orth nd (w)	200.5				vs H_2O
5580	Glycocholic acid		$C_{26}H_{43}NO_6$	475-31-0	465.622	nd (w)	166.5				sl H_2O, eth; vs EtOH
5581	Glycocyamine		$C_3H_7N_3O_2$	352-97-6	117.107	pl or nd (w)	282				sl H_2O, EtOH, eth
5582	Glycogen		$(C_6H_{10}O_5)_x$	9005-79-2	162.140	wh pow					vs H_2O; i EtOH, eth
5583	Glycolaldehyde		$C_2H_4O_2$	141-46-8	60.052	pl	97		1.366^{100}	1.4772^{19}	s chl
5584	Glycolic acid		$C_2H_4O_3$	79-14-1	76.051	orth nd (w) lf (eth)	79.5	100			s H_2O, EtOH, eth
5585	*N*-Glycolylneuraminic acid	*N*-(Hydroxyacetyl)neuraminic acid	$C_{11}H_{19}NO_{10}$	1113-83-3	325.270		186				
5586	Glycopyrrolate		$C_{19}H_{28}BrNO_3$	596-51-0	398.334		192.5				
5587	Glycylalanine	*N*-Alanylglycine	$C_5H_{10}N_2O_3$	1188-01-8	146.144		237 dec				s H_2O; i EtOH, eth
5588	*L*-Glycylasparagine		$C_6H_{11}N_3O_4$	1999-33-3	189.169	nd (EtOH aq)	216				s H_2O; sl EtOH
5589	*N*-Glycylglycine	2-(Aminoacetamido)acetic acid	$C_4H_8N_2O_3$	556-50-3	132.118		263 dec				s H_2O
5590	*N*-(*N*-Glycylglycyl)glycine		$C_6H_{11}N_3O_4$	556-33-2	189.169	nd (dil al)	246 dec				s H_2O; i EtOH, eth
5591	*N*-Glycyl-*L*-leucine		$C_8H_{16}N_2O_3$	869-19-2	188.224	pl (dil al) pl (dil al)	256 dec				vs H_2O; i EtOH
5592	*N*-Glycyl-*L*-phenylalanine		$C_{11}H_{14}N_2O_3$	3321-03-7	222.240		266				s H_2O
5593	*N*-Glycylserine, (*DL*)		$C_5H_{10}N_2O_4$	687-38-7	162.144		198 dec				
5594	Glycyrrhizic acid		$C_{42}H_{62}O_{16}$	1405-86-3	822.931	pl or pr (HOAc)	220 dec				vs H_2O, EtOH; i eth
5595	Glyodin	1*H*-Imidazole, 2-heptadecyl-4,5-dihydro-, monoacetate	$C_{22}H_{44}N_2O_2$	556-22-9	368.596				1.035^{20}		
5596	Glyoxal		$C_2H_2O_2$	107-22-2	58.036	ye pr	15	50.4	1.14^{20}	1.3826^{20}	vs H_2O; s EtOH, eth
5597	Glyoxal bis(2-hydroxyanil)	2,2'-Benzoxazoline	$C_{14}H_{12}N_2O_2$	1149-16-2	240.257		202				s DMSO
5598	Glyoxylic acid		$C_2H_2O_3$	298-12-4	74.035	orth pr (w+1/2)	98				vs H_2O; sl EtOH, eth, bz
5599	Glyphosate	Glycine, *N*-(phosphonomethyl)-	$C_3H_8NO_5P$	1071-83-6	169.074		230 dec				
5600	Glyphosate isopropylamine salt		$C_6H_{17}N_2O_5P$	38641-94-0	228.183	cry					vs H_2O
5601	Glyphosine	Glycine, *N,N*-bis(phosphonomethyl)-	$C_4H_{11}NO_8P_2$	2439-99-8	263.080	wh cry					s H_2O
5602	Grayanotoxin I		$C_{22}H_{36}O_7$	4720-09-6	412.517	cry (AcOEt/C_5H_{12})	268				
5603	Griseofulvin, (+)		$C_{17}H_{17}ClO_6$	126-07-8	352.766	oct or orth cry (bz)	220				i H_2O; sl EtOH, eth, ace, bz, AcOEt, chl
5604	Guaiol		$C_{15}H_{26}O$	489-86-1	222.366	trg pr (al)	91	dec 288; 165^{17}	0.9074^{100}	1.4716^{100}	i H_2O; s EtOH, eth
5605	Guanabenz		$C_8H_8Cl_2N_4$	5051-62-7	231.083	wh solid	228 dec				
5606	Guanadrel sulfate (2:1)		$C_{20}H_{40}N_6O_8S$	22195-34-2	524.632	cry (MeOH/EtOH)	214				
5607	Guanethidine		$C_{10}H_{22}N_4$	55-65-2	198.309	wh cry (MeOH)	226				
5608	Guanidine	Aminomethanamidine	CH_5N_3	113-00-8	59.071	cry	50				vs H_2O, EtOH
5609	Guanidine monohydrochloride		CH_6ClN_3	50-01-1	95.532	orth bipym (al)	182.3		1.354^{20}		vs H_2O, EtOH
5610	Guanidine mononitrate		$CH_6N_4O_3$	506-93-4	122.084	lf (w)	217	dec			vs H_2O, EtOH
5611	Guanidine, sulfate (2:1)		$C_2H_{12}N_6O_4S$	594-14-9	216.219		292 dec				
5612	2-Guanidinoethanesulfonic acid	Taurocyamine	$C_3H_9N_3O_3S$	543-18-0	167.186	cry (EtOH, ace)	227				
5613	3-Guanidinopropanoic acid	*N*-Amidino-β-alanine	$C_4H_9N_3O_2$	353-09-3	131.133	cry (EtOH)	210				
5614	Guanine		$C_5H_5N_5O$	73-40-5	151.127	nd or pl (aq NH_3)	360 dec	sub			i H_2O, HOAc; sl EtOH, eth; s alk, acid
5615	Guanosine	2-Amino-1,9-dihydro-9-β-*D*-ribofuranosyl-6*H*-purin-6-one	$C_{10}H_{13}N_5O_5$	118-00-3	283.241	nd (w)	239 dec				sl H_2O; i EtOH, eth; vs HOAc
5616	Guanosine 5'-diphosphate	Guanosine 5'-(trihydrogen diphosphate)	$C_{10}H_{15}N_5O_{11}P_2$	146-91-8	443.201	amorp solid					
5617	Guanosine 5'-monophosphate	5'-Guanylic acid	$C_{10}H_{14}N_5O_8P$	85-32-5	363.221	hyg cry	190 dec				sl H_2O



Glycerol tritetradecanoate



Glycerone phosphate



Glycine



Glycine, ethyl ester, hydrochloride



Glycine, hydrochloride



Glycocholic acid



Glycocyamine



Glycogen



Glycolaldehyde



Glycolic acid



N-Glycolylneuraminic acid



Glycopyrrolate



Glycylalanine



L-Glycylasparagine



N-Glycylglycine



N-(*N*-Glycylglycyl)glycine


N-Glycyl-*L*-leucine



N-Glycyl-*L*-phenylalanine


N-Glycylserine, (*DL*)



Glycyrrhizic acid



Glyodin


Glyoxal



Glyoxal bis(2-hydroxyanil)



Glyoxylic acid



Glyphosate



Glyphosate isopropylamine salt



Glyphosine



Grayanotoxin I



Griseofulvin, (+)



Guaiol



Guanabenz



Guanadrel sulfate (2:1)



Guanethidine



Guanidine



Guanidine monohydrochloride



Guanidine mononitrate



Guanidine, sulfate (2:1)



2-Guanidinoethanesulfonic acid


3-Guanidinopropanoic acid



Guanine



Guanosine



Guanosine 5′-diphosphate



Guanosine 5′-monophosphate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5618	Guanosine 5'-monophosphate, disodium salt	5'-Guanylic acid, disodium salt	$C_{10}H_{12}N_5Na_2O_8P$	5550-12-9	407.185		195 dec				sl H_2O
5619	Guinea Green B	C.I. Acid Green 3	$C_{37}H_{35}N_2NaO_6S_2$	4680-78-8	690.803	dk grn pow					s H_2O; sl EtOH
5620	*D*-Gulose		$C_6H_{12}O_6$	4205-23-6	180.155	syr		dec			vs H_2O
5621	*L*-Gulose		$C_6H_{12}O_6$	6027-89-0	180.155	syr		dec			vs H_2O
5622	Haloperidol		$C_{21}H_{23}ClFNO_2$	52-86-8	375.865		151.5				
5623	Harmaline	4,9-Dihydro-7-methoxy-1-methyl-3*H*-pyrido[3,4-b]indole	$C_{13}H_{14}N_2O$	304-21-2	214.262	tab (MeOH) orth pr (al)	230				sl H_2O, EtOH, eth; s chl, py
5624	Harman	1-Methyl-9*H*-pyrido[3,4-b] indole	$C_{12}H_{10}N_2$	486-84-0	182.220	bl flr orth cry (hp)	236.5				
5625	Harmine	7-Methoxy-1-methyl-9*H*-pyrido[3,4-b]indole	$C_{13}H_{12}N_2O$	442-51-3	212.246	orth (al), pr (MeOH)	273	sub			sl H_2O, chl, EtOH, eth; s py
5626	HC Blue No. 1		$C_{11}H_{17}N_3O_4$	2784-94-3	255.271	blk cry	100				
5627	HC Blue No. 2		$C_{12}H_{19}N_3O_5$	33229-34-4	285.296	dk bl-blk cry	110				
5628	Hectane		$C_{100}H_{202}$	6703-98-6	1404.67		117				
5629	Hederagenin		$C_{30}H_{48}O_4$	465-99-6	472.700	pr (al)	333				
5630	Helenalin		$C_{15}H_{18}O_4$	6754-13-8	262.302	cry (EtOH)	226				sl H_2O; s EtOH, chl
5631	Helminthosporal		$C_{15}H_{22}O_2$	723-61-5	234.335		58	$117^{0.015}$			
5632	Helvolic acid		$C_{33}H_{44}O_8$	29400-42-8	568.697	nd (dil HOAc)	212 dec				sl H_2O, EtOH; s eth, ace, bz, diox
5633	Hematein		$C_{16}H_{12}O_6$	475-25-2	300.262	red-br cry	250 dec				i H_2O, eth, bz, chl; sl EtOH, HOAc
5634	Hematin		$C_{34}H_{33}FeN_4O_5$	15489-90-4	633.495	br pow (py)	>200				i H_2O, eth; s EtOH, alk; sl py, HOAc
5635	Hematoporphyrin		$C_{34}H_{38}N_4O_6$	14459-29-1	598.689	deep red cry	172.5				i H_2O; s EtOH; sl eth, chl
5636	Hematoxylin		$C_{16}H_{14}O_6$	517-28-2	302.278	ye cry	140				sl H_2O, eth; s alk, EtOH
5637	Hemin		$C_{34}H_{32}ClFeN_4O_4$	16009-13-5	651.941	long blades (gl HOAc)	>300				
5638	Heneicosane		$C_{21}H_{44}$	629-94-7	296.574	cry (w)	40.01	356.5	0.7919^{20}	1.4441^{20}	i H_2O; sl EtOH; s peth
5639	Hentriacontane	Untriacontane	$C_{31}H_{64}$	630-04-6	436.840	lf (AcOEt)	67.9	458	0.781^{68}	1.4278^{90}	sl EtOH, eth, bz, chl; s peth
5640	Heptachlor		$C_{10}H_5Cl_7$	76-44-8	373.318	wh cry	95.5		1.57^{9}		vs bz, eth, EtOH, lig
5641	Heptachlor epoxide		$C_{10}H_5Cl_7O$	1024-57-3	389.317		160				
5642	2,2',3,3',4,4',6-Heptachlorobiphenyl		$C_{12}H_3Cl_7$	52663-71-5	395.323	cry	117.5				i H_2O
5643	1,1,1,2,3,3,3-Heptachloropropane		C_3HCl_7	3849-33-0	285.211		11	249	1.7921^{34}	1.5427^{21}	vs chl
5644	Heptacontane		$C_{70}H_{142}$	7719-93-9	983.876		107	647			
5645	Heptacosane		$C_{27}H_{56}$	593-49-7	380.734	cry (al, bz) lf (AcOEt)	59.23	442	0.7796^{60}	1.4345^{65}	i H_2O, EtOH; sl eth
5646	Heptadecanal	Margaric aldehyde	$C_{17}H_{34}O$	629-90-3	254.451	nd (peth), cry (al)	36	204^{26}			vs bz, eth
5647	1-Heptadecanamine		$C_{17}H_{37}N$	4200-95-7	255.483		49	336	0.8510^{20}	1.4510^{20}	i H_2O; s EtOH, eth
5648	Heptadecane		$C_{17}H_{36}$	629-78-7	240.468	hex lf	22.0	302.0	0.7780^{20}	1.4369^{20}	i H_2O; sl EtOH, ctc; s eth
5649	Heptadecanenitrile		$C_{17}H_{33}N$	5399-02-0	251.451	cry (al)	34	349	0.8315^{20}	1.4467^{20}	i H_2O; sl EtOH, chl; vs eth
5650	Heptadecanoic acid	Margaric acid	$C_{17}H_{34}O_2$	506-12-7	270.451	pl (peth)	61.3	227^{100}	0.8532^{60}	1.4342^{60}	i H_2O; sl EtOH; s eth, ace, bz, chl
5651	1-Heptadecanol	Margaryl alcohol	$C_{17}H_{36}O$	1454-85-9	256.467	lf (al), cry (ace)	53.9	324	0.8475^{20}		i H_2O; s EtOH, eth
5652	2-Heptadecanone	Pentadecyl methyl ketone	$C_{17}H_{34}O$	2922-51-2	254.451	pl (dil al)	48	320	0.8049^{48}		i H_2O; sl EtOH; s ace, peth; vs bz, eth
5653	9-Heptadecanone		$C_{17}H_{34}O$	540-08-9	254.451	pl (MeOH)	53	$251.5; 142^{1.5}$	0.8140^{48}		sl EtOH; s MeOH
5654	1-Heptadecene	Hexahydroaplotaxene	$C_{17}H_{34}$	6765-39-5	238.452		11.5	300	0.7852^{20}	1.4432^{20}	i H_2O; vs eth; s bz; msc lig
5655	Heptadecylbenzene	1-Phenylheptadecane	$C_{23}H_{40}$	14752-75-1	316.564		32	397	0.8546^{20}	1.4810^{20}	
5656	*trans,trans*-2,4-Heptadienal		$C_7H_{10}O$	4313-03-5	110.153			84.5	0.881^{25}	1.5315^{20}	
5657	1,6-Heptadiene		C_7H_{12}	3070-53-9	96.170	liq		90			
5658	1,6-Heptadiyne		C_7H_8	2396-63-6	92.139	liq	-85	112	0.8164^{17}	1.451^{17}	i H_2O; s bz, HOAc
5659	Heptafluorobutanoic acid		$C_4HF_7O_2$	375-22-4	214.039	liq	-17.5	121	1.651^{20}	1.295^{25}	s H_2O, eth, tol; i peth



Guanosine 5'-monophosphate, disodium salt



Guinea Green B



D-Gulose



L-Gulose



Haloperidol



Harmaline



Harman



Harmine



HC Blue No. 1



HC Blue No. 2



Hectane



Hederagenin



Helenalin



Helminthosporal



Helvolic acid



Hematein



Hematin



Hematoporphyrin



Hematoxylin



Hemin



Heneicosane



Hentriacontane



Heptachlor


Heptachlor epoxide



2,2',3,3',4,4',6-Heptachlorobiphenyl


1,1,1,2,3,3,3-Heptachloropropane



Heptacontane



Heptacosane



Heptadecanal



1-Heptadecanamine



Heptadecane



Heptadecanenitrile



Heptadecanoic acid



1-Heptadecanol



2-Heptadecanone



9-Heptadecanone



1-Heptadecene


Heptadecylbenzene



trans,*trans*-2,4-Heptadienal



1,6-Heptadiene



1,6-Heptadiyne



Heptafluorobutanoic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5660	Heptafluorobutanoic anhydride		$C_8F_{14}O_3$	336-59-4	410.062	liq	-43	106.5	1.665^{20}	1.285^{20}	
5661	2,2,3,3,4,4,4-Heptafluoro-1-butanol		$C_4H_3F_7O$	375-01-9	200.055			95	1.600^{20}	1.294^{20}	s EtOH, ace
5662	Heptafluorobutanoyl chloride		C_4ClF_7O	375-16-6	232.484			38.5	1.55^{20}	1.288^{20}	
5663	6,6,7,7,8,8,8-Heptafluoro-2,2-dimethyl-3,5-octanedione		$C_{10}H_{11}F_7O_2$	17587-22-3	296.182		38	46^{5}	1.273^{25}	1.3766^{20}	
5664	Heptafluoro-2-iodopropane	Perfluoroisopropyl iodide	C_3F_7I	677-69-0	295.925			38	1.3298^{20}		
5665	1,1,1,2,3,3,3-Heptafluoropropane	Refrigerant 227ea	C_3HF_7	431-89-0	170.029	col gas	-131	-16.4			
5666	2,2,4,4,6,8,8-Heptamethylnonane		$C_{16}H_{34}$	4390-04-9	226.441			246.3			
5667	1,1,1,3,5,5,5-Heptamethyltrisiloxane		$C_7H_{22}O_2Si_3$	1873-88-7	222.506			142	0.8194^{20}	1.3818^{20}	
5668	Heptanal	Heptaldehyde	$C_7H_{14}O$	111-71-7	114.185	liq	-43.4	152.8	0.8132^{25}	1.4113^{20}	sl H_2O, ctc; msc EtOH, eth
5669	Heptanal oxime	Enanthaldoxime	$C_7H_{15}NO$	629-31-2	129.200	pl (al)	57.5	195	0.8583^{55}	1.4210^{20}	sl H_2O; s EtOH, eth
5670	2-Heptanamine	Tuaminoheptane	$C_7H_{17}N$	123-82-0	115.217			142	0.7665^{19}	1.4199^{19}	sl H_2O, chl; s EtOH, eth, peth
5671	4-Heptanamine		$C_7H_{17}N$	16751-59-0	115.217			139.5	0.767^{20}	1.4172^{20}	
5672	Heptane		C_7H_{16}	142-82-5	100.202	liq	-90.55	98.4	0.6795^{25}	1.3855^{25}	i H_2O; vs EtOH; msc eth, bz, chl; s ctc
5673	1,7-Heptanediamine		$C_7H_{18}N_2$	646-19-5	130.231		25.32	224			s EtOH, eth, ace
5674	Heptanedinitrile		$C_7H_{10}N_2$	646-20-8	122.167		-31.4	155^{14}	0.949^{18}	1.4472^{20}	i H_2O; msc EtOH, eth, chl
5675	Heptanedioic acid	Pimelic acid	$C_7H_{12}O_4$	111-16-0	160.168	pr (w)	106	272^{100}, 212^{10}	1.329^{15}		s H_2O, EtOH, eth; i bz
5676	1,7-Heptanediol		$C_7H_{16}O_2$	629-30-1	132.201		22.5	262	0.9569^{25}	1.4520^{25}	vs eth, EtOH
5677	2,3-Heptanedione	Acetyl valeryl	$C_7H_{12}O_2$	96-04-8	128.169			144; 46^{13}	0.919^{18}	1.4150^{18}	
5678	3,5-Heptanedione	Dipropionylmethane	$C_7H_{12}O_2$	7424-54-6	128.169			175; 79^{30}	0.945^{20}		
5679	Heptanedioyl dichloride		$C_7H_{10}Cl_2O_2$	142-79-0	197.059			137^{15}			
5680	Heptanenitrile		$C_7H_{13}N$	629-08-3	111.185	liq	-64	183; 71^{10}	0.8106^{20}	1.4104^{30}	i H_2O; s eth, ace, bz, HOAc
5681	1-Heptanethiol	Heptyl mercaptan	$C_7H_{16}S$	1639-09-4	132.267	liq	-43	176.9	0.8427^{20}	1.4521^{20}	i H_2O; msc EtOH, eth; s chl
5682	2,4,6-Heptanetrione		$C_7H_{10}O_3$	626-53-9	142.152	lf	49	121^{10}	1.0599^{40}	1.4930^{20}	vs H_2O, eth, EtOH
5683	Heptanoic acid	Enanthic acid	$C_7H_{14}O_2$	111-14-8	130.185	liq	-7.17	222.2	0.9124^{25}	1.4170^{20}	sl H_2O, ctc; s EtOH, eth, ace
5684	Heptanoic anhydride		$C_{14}H_{26}O_3$	626-27-7	242.354	liq	-12.4	269.5	0.9321^{20}	1.4335^{15}	i H_2O; s EtOH, eth
5685	1-Heptanol	Heptyl alcohol	$C_7H_{16}O$	111-70-6	116.201	liq	-33.2	176.45	0.8219^{20}	1.4249^{20}	sl H_2O, ctc; msc EtOH, eth
5686	2-Heptanol, (±)		$C_7H_{16}O$	52390-72-4	116.201			159	0.8167^{20}	1.4210^{20}	sl H_2O, ctc; s EtOH, eth
5687	3-Heptanol, (*S*)		$C_7H_{16}O$	26549-25-7	116.201	liq	-70	157; 66^{18}	0.8227^{20}	1.4201^{20}	sl H_2O, ctc; s EtOH, eth
5688	4-Heptanol	Dipropylcarbinol	$C_7H_{16}O$	589-55-9	116.201	liq	-41.2	156	0.8183^{20}	1.4205^{20}	sl H_2O; s EtOH, eth
5689	2-Heptanone	Methyl pentyl ketone	$C_7H_{14}O$	110-43-0	114.185	liq	-35	151.05	0.8111^{20}	1.4088^{20}	vs H_2O; s EtOH, eth
5690	3-Heptanone	Ethyl butyl ketone	$C_7H_{14}O$	106-35-4	114.185	liq	-39	147	0.8183^{20}	1.4057^{20}	sl H_2O, ctc; msc EtOH, eth
5691	4-Heptanone	Dipropyl ketone	$C_7H_{14}O$	123-19-3	114.185	liq	-33	144	0.8174^{20}	1.4069^{20}	i H_2O; msc EtOH, eth; s ctc
5692	Heptanoyl chloride		$C_7H_{13}ClO$	2528-61-2	148.630	liq	-83.8	125.2	0.9590^{20}	1.4345^{18}	s eth; sl ctc; vs lig
5693	2-Heptenal	Butylacrolein	$C_7H_{12}O$	2463-63-0	112.169			166	0.864^{17}	1.4468^{17}	
5694	1-Heptene		C_7H_{14}	592-76-7	98.186	liq	-118.9	93.64	0.6970^{20}	1.3998^{20}	i H_2O; s EtOH, eth; sl ctc
5695	*cis*-2-Heptene		C_7H_{14}	6443-92-1	98.186			98.4	0.708^{20}	1.406^{20}	i H_2O; s EtOH, eth, ace, bz, chl; sl ctc
5696	*trans*-2-Heptene		C_7H_{14}	14686-13-6	98.186	liq	-109.5	98	0.7012^{20}	1.4045^{20}	i H_2O; s EtOH, eth, ace, bz, peth, chl
5697	*cis*-3-Heptene		C_7H_{14}	7642-10-6	98.186	liq	-136.6	95.8	0.7030^{20}	1.4059^{20}	i H_2O; s EtOH, eth, ace, bz, peth, chl
5698	*trans*-3-Heptene		C_7H_{14}	14686-14-7	98.186	liq	-136.6	95.7	0.6981^{20}	1.4043^{20}	i H_2O; s EtOH, eth, ace, bz, chl; sl ctc
5699	6-Heptenoic acid		$C_7H_{12}O_2$	1119-60-4	128.169	liq	-6.5	226	0.9515^{14}	1.4404^{14}	
5700	1-Hepten-4-ol		$C_7H_{14}O$	3521-91-3	114.185			152.1	0.8384^{22}	1.4347^{20}	



Heptafluorobutanoic anhydride



2,2,3,3,4,4,4-Heptafluoro-1-butanol



Heptafluorobutanoyl chloride



6,6,7,7,8,8,8-Heptafluoro-2,2-dimethyl-3,5-octanedione



Heptafluoro-2-iodopropane



1,1,1,2,3,3,3-Heptafluoropropane



2,2,4,4,6,8,8-Heptamethylnonane



1,1,1,3,5,5,5-Heptamethyltrisiloxane



Heptanal



Heptanal oxime



2-Heptanamine


4-Heptanamine



Heptane



1,7-Heptanediamine



Heptanedinitrile



Heptanedioic acid


1,7-Heptanediol



2,3-Heptanedione



3,5-Heptanedione



Heptanedioyl dichloride



Heptanenitrile



1-Heptanethiol



2,4,6-Heptanetrione



Heptanoic acid



Heptanoic anhydride



1-Heptanol



2-Heptanol, (±)



3-Heptanol, (*S*)



4-Heptanol



2-Heptanone



3-Heptanone



4-Heptanone



Heptanoyl chloride



2-Heptenal



1-Heptene



cis-2-Heptene


trans-2-Heptene



cis-3-Heptene



trans-3-Heptene



6-Heptenoic acid



1-Hepten-4-ol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5701	*trans*-2-Hepten-1-ol		$C_7H_{14}O$	33467-76-4	114.185			178; 75^{10}	0.8516^{20}	1.4460^{20}	s EtOH, ace
5702	Heptyl acetate		$C_9H_{18}O_2$	112-06-1	158.238	liq	-50.2	193	0.8750^{15}	1.4150^{20}	i H_2O; s EtOH, eth, ctc
5703	Heptylamine	1-Heptanamine	$C_7H_{17}N$	111-68-2	115.217	liq	-18	156	0.7754^{20}	1.4251^{20}	sl H_2O, chl; msc EtOH, eth
5704	Heptylbenzene		$C_{13}H_{20}$	1078-71-3	176.298	liq	-48	240; 109^{10}	0.8567^{20}	1.4865^{20}	i H_2O; s bz, chl
5705	Heptyl butanoate		$C_{11}H_{22}O_2$	5870-93-9	186.292	liq	-57.5	225.8	0.8637^{20}	1.4231^{20}	vs EtOH
5706	Heptylcyclohexane		$C_{13}H_{26}$	5617-41-4	182.345	liq	-30	244	0.8109^{20}	1.4484^{20}	
5707	Heptylcyclopentane		$C_{12}H_{24}$	5617-42-5	168.319	liq	-53	224	0.8010^{20}	1.4421^{20}	vs ace, bz, eth, EtOH
5708	5-Heptyldihydro-2(3*H*)-furanone	4-Hydroxyundecanoic acid lactone	$C_{11}H_{20}O_2$	104-67-6	184.276			286	0.9494^{20}	1.4512^{20}	vs EtOH
5709	Heptyl formate		$C_8H_{16}O_2$	112-23-2	144.212			178.1	0.8784^{20}	1.4140^{20}	i H_2O; msc EtOH, eth
5710	Heptyl pentanoate		$C_{12}H_{24}O_2$	5451-80-9	200.318	liq	-46.4	245.2	0.8623^{20}	1.4254^{15}	vs ace, eth, EtOH
5711	6-Heptyltetrahydro-2*H*-pyran-2-one	5-Dodecanolide	$C_{12}H_{22}O_2$	713-95-1	198.302	liq	-12	101$^{0.03}$			
5712	1-Heptyne		C_7H_{12}	628-71-7	96.170	liq	-81	99.7	0.7328^{20}	1.4087^{20}	sl H_2O; msc EtOH, eth; s bz, chl, peth
5713	2-Heptyne	1-Methyl-2-butylacetylene	C_7H_{12}	1119-65-9	96.170			112	0.744^{25}	1.4230^{20}	i H_2O; msc EtOH, eth; s bz, chl, peth
5714	3-Heptyne	1-Ethyl-2-propylacetylene	C_7H_{12}	2586-89-2	96.170	liq	-130.5	107.2	0.7336^{25}	1.4189^{20}	i H_2O; msc EtOH, eth; s bz, chl, peth
5715	Hesperetin		$C_{16}H_{14}O_6$	520-33-2	302.278	pl (dil al + 1/2 w)	227.5	sub 205			vs eth, EtOH
5716	Hesperidin		$C_{28}H_{34}O_{15}$	520-26-3	610.561	wh nd (dil MeOH, HOAc)	262				vs py, EtOH, HOAc
5717	Hexabromobenzene		C_6Br_6	87-82-1	551.488	mcl nd (bz)	327				i H_2O; sl EtOH, eth; s bz, chl
5718	2,2',4,4',5,5'-Hexabromobiphenyl		$C_{12}H_4Br_6$	59080-40-9	627.584	cry (ctc)	160				
5719	1,2,5,6,9,10-Hexabromocyclododecane		$C_{12}H_{18}Br_6$	3194-55-6	641.695	cry	167				
5720	Hexabromoethane		C_2Br_6	594-73-0	503.445	orth pr (bz)		dec 200	3.823^{20}	1.863	sl EtOH, eth, CS_2
5721	Hexabutyldistannoxane	Bis(tributyltin) oxide	$C_{24}H_{54}OSn_2$	56-35-9	596.105		45	180^{2}			
5722	Hexacene		$C_{26}H_{16}$	258-31-1	328.405	dk bl-grn cry (sub)	380	sub			i H_2O, EtOH
5723	Hexachloroacetone		C_3Cl_6O	116-16-5	264.749	liq	-1.0	203	1.7434^{12}	1.5112^{20}	sl H_2O; s ace
5724	Hexachlorobenzene	Perchlorobenzene	C_6Cl_6	118-74-1	284.782	nd (sub)	228.83	325	2.044^{23}	1.5691^{23}	i H_2O; sl EtOH; s eth, chl; vs bz
5725	2,2',3,3',4,4'-Hexachlorobiphenyl		$C_{12}H_4Cl_6$	38380-07-3	360.878	cry	151				i H_2O
5726	2,2',4,4',6,6'-Hexachlorobiphenyl		$C_{12}H_4Cl_6$	33979-03-2	360.878	cry	112.5				i H_2O
5727	2,2',3,3',6,6'-Hexachlorobiphenyl		$C_{12}H_4Cl_6$	38411-22-2	360.878	cry (hx)	114.2				i H_2O
5728	2,2',4,4',5,5'-Hexachlorobiphenyl		$C_{12}H_4Cl_6$	35065-27-1	360.878	cry	103.5				
5729	Hexachloro-1,3-butadiene		C_4Cl_6	87-68-3	260.761	liq	-21	215	1.556^{25}	1.5542^{20}	i H_2O; s EtOH, eth
5730	1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2α,3β,4α,5α,6β)	Lindane	$C_6H_6Cl_6$	58-89-9	290.830	nd (al)	112.5	323.4			vs ace, bz
5731	1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2α,3β,4α,5β,6β)	α-Hexachlorocyclohexane	$C_6H_6Cl_6$	319-84-6	290.830	cry	158				
5732	1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2β,3α,4β,5α,6β)	β-Hexachlorocyclohexane	$C_6H_6Cl_6$	319-85-7	290.830	cry (bz, al, xyl)		60$^{0.50}$	1.89^{19}		i H_2O; sl EtOH, bz, chl, HOAc
5733	1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2α,3α,4β,5α,6β)	δ-Lindane	$C_6H_6Cl_6$	319-86-8	290.830	pl	141.5	60$^{0.36}$			
5734	Hexachloro-1,3-cyclopentadiene	Perchlorocyclopentadiene	C_5Cl_6	77-47-4	272.772	ye grn liq	-9	239; 48$^{0.3}$	1.7019^{25}	1.5658^{20}	
5735	1,2,3,6,7,8-Hexachlorodibenzo-*p*-dioxin		$C_{12}H_2Cl_6O_2$	57653-85-7	390.861	cry	285				
5736	1,2,3,7,8,9-Hexachlorodibenzo-*p*-dioxin		$C_{12}H_2Cl_6O_2$	19408-74-3	390.861	cry	243				
5737	Hexachloroethane	Perchloroethane	C_2Cl_6	67-72-1	236.739	orth (al-eth)	186.8 tp	184.7 sp	2.091^{20}		i H_2O; vs EtOH, eth; s bz; sl liq HF
5738	Hexachlorophene		$C_{13}H_6Cl_6O_2$	70-30-4	406.904	nd (bz)	166.5				i H_2O; s EtOH, eth, ace, chl, dil alk



trans-2-Hepten-1-ol



Heptyl acetate



Heptylamine



Heptylbenzene



Heptyl butanoate



Heptylcyclohexane



Heptylcyclopentane



5-Heptyldihydro-2(3*H*)-furanone


Heptyl formate



Heptyl pentanoate



6-Heptyltetrahydro-2*H*-pyran-2-one



1-Heptyne



2-Heptyne



3-Heptyne



Hesperetin



Hesperidin



Hexabromobenzene



2,2',4,4',5,5'-Hexabromobiphenyl



1,2,5,6,9,10-Hexabromocyclododecane



Hexabromoethane



Hexabutyldistannoxane



Hexacene



Hexachloroacetone



Hexachlorobenzene



2,2',3,3',4,4'-Hexachlorobiphenyl



2,2',4,4',6,6'-Hexachlorobiphenyl



2,2',3,3',6,6'-Hexachlorobiphenyl



2,2',4,4',5,5'-Hexachlorobiphenyl



Hexachloro-1,3-butadiene



1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2α,3β,4α,5α,6β)



1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2α,3β,4α,5β,6β)



1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2β,3α,4β,5α,6β)



1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2α,3α,4β,5α,6β)


Hexachloro-1,3-cyclopentadiene



1,2,3,6,7,8-Hexachlorodibenzo-*p*-dioxin



1,2,3,7,8,9-Hexachlorodibenzo-*p*-dioxin



Hexachloroethane



Hexachlorophene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5739	Hexachloropropene		C_3Cl_6	1888-71-7	248.750	liq	-72.9	209.5	1.7632^{20}	1.5091^{20}	i H_2O; s ctc, chl
5740	Hexacontane		$C_{60}H_{122}$	7667-80-3	843.611		99.3				
5741	Hexacosane		$C_{26}H_{54}$	630-01-3	366.707	mcl, tcl or orth (bz) cry (eth)	56.1	412.2	0.7783^{60}	1.4357^{60}	vs bz, lig, chl
5742	Hexacosanoic acid	Cerotic acid	$C_{26}H_{52}O_2$	506-46-7	396.690		88.5		0.8198^{100}	1.4301^{100}	i H_2O; vs EtOH, eth
5743	1-Hexacosanol		$C_{26}H_{54}O$	506-52-5	382.706	orth pl (dil al)	80	305^{20} dec			i H_2O; s EtOH, eth
5744	Hexadecamethylheptasiloxane		$C_{16}H_{48}O_6Si_7$	541-01-5	533.147	liq	-78	270	0.9012^{20}	1.3965^{20}	vs bz, lig
5745	Hexadecanal		$C_{16}H_{32}O$	629-80-1	240.424	pl (eth), nd (peth)	35	200^{29}			i H_2O; s EtOH, eth, ace, bz
5746	Hexadecanamide		$C_{16}H_{33}NO$	629-54-9	255.439	lf	107	236^{12}	1.0000^{20}		i H_2O; sl EtOH, bz, ace, eth
5747	Hexadecane	Cetane	$C_{16}H_{34}$	544-76-3	226.441	lf (HOAc)	18.12	286.86	0.7701^{25}	1.4329^{25}	i H_2O; sl EtOH; msc eth; s ctc
5748	Hexadecanedioic acid		$C_{16}H_{30}O_4$	505-54-4	286.407	pl (al)	126.6				vs ace, EtOH
5749	Hexadecanenitrile		$C_{16}H_{31}N$	629-79-8	237.424	hex	31	333	0.8303^{20}	1.4450^{20}	i H_2O; vs EtOH, eth, ace, bz, chl
5750	1-Hexadecanethiol	Cetyl mercaptan	$C_{16}H_{34}S$	2917-26-2	258.506	cry (lig)	19	$125^{0.5}$			i H_2O; sl EtOH, ctc; s eth
5751	Hexadecanoic acid	Palmitic acid	$C_{16}H_{32}O_2$	57-10-3	256.424	nd (al)	62.5	351.5	0.8527^{62}	1.43345^{60}	i H_2O; s EtOH, ace, bz; msc eth; vs chl
5752	Hexadecanoic anhydride		$C_{32}H_{62}O_3$	623-65-4	494.832	lf (peth)	64		0.8388^{83}	1.4364^{68}	vs eth
5753	1-Hexadecanol	Cetyl alcohol	$C_{16}H_{34}O$	36653-82-4	242.440	fl (AcOEt)	49.2	312	0.8187^{50}	1.4283^{79}	i H_2O; sl EtOH; vs eth, bz, chl; s ace
5754	3-Hexadecanone		$C_{16}H_{32}O$	18787-64-9	240.424	lf (peth)	43	184^{17}, 140^{2}			s chl
5755	Hexadecanoyl chloride		$C_{16}H_{31}ClO$	112-67-4	274.869		12	199^{20}	0.9016^{25}	1.4514^{20}	vs eth
5756	1-Hexadecene	1-Cetene	$C_{16}H_{32}$	629-73-2	224.425	lf	2.1	284.9	0.7811^{20}	1.4412^{20}	i H_2O; s EtOH, eth, ctc, peth
5757	*cis*-9-Hexadecenoic acid	Palmitoleic acid	$C_{16}H_{30}O_2$	373-49-9	254.408		0.5	182^{1}			
5758	Hexadecyl acetate		$C_{18}H_{36}O_2$	629-70-9	284.478		-18.5	222^{205}	0.8574^{25}	1.4438^{20}	i H_2O; sl EtOH; s ctc
5759	Hexadecylamine	1-Hexadecanamine	$C_{16}H_{35}N$	143-27-1	241.456	lf	46.8	322.5	0.8129^{20}	1.4496^{20}	i H_2O; vs EtOH, eth, bz; s ace
5760	Hexadecylbenzene		$C_{22}H_{38}$	1459-09-2	302.537		27	385	0.8547^{20}	1.4813^{20}	i H_2O; sl EtOH; vs eth, bz, CS_2
5761	Hexadecyldimethylamine	*N,N*-Dimethyl-1-hexadecanamine	$C_{18}H_{39}N$	112-69-6	269.510			330.0			
5762	Hexadecyl hexadecanoate	Cetyl palmitate	$C_{32}H_{64}O_2$	540-10-3	480.849	mcl lf	54		0.989^{20}	1.4398^{70}	vs eth, EtOH
5763	Hexadecyl 3-hydroxy-2-naphthalenecarboxylate	Hexadecyl 3-hydroxy-2-naphthoate	$C_{27}H_{40}O_3$	531-84-0	412.605	grn-wh fl	72.5				vs bz, HOAc
5764	Hexadecyl 2-hydroxypropanoate	Cetyl lactate	$C_{19}H_{38}O_3$	35274-05-6	314.503	wax	41	219^{10}, 170^{1}		1.4410^{40}	
5765	Hexadecyl 2-methyl-2-propenoate		$C_{20}H_{38}O_2$	2495-27-4	310.515		24	183^{2}	0.87^{20}		
5766	3-(Hexadecyloxy)-1,2-propanediol, (*S*)	Chimyl alcohol	$C_{19}H_{40}O_3$	506-03-6	316.519	lf (hx)	64	$120^{0.005}$			vs ace, peth, chl
5767	1-Hexadecylpyridinium bromide		$C_{21}H_{38}BrN$	140-72-7	384.438		61				
5768	1-Hexadecylpyridinium chloride	Cetylpyridinium chloride	$C_{21}H_{38}ClN$	123-03-5	339.987	wh pow	80				vs H_2O, chl
5769	Hexadecyl stearate	Cetyl stearate	$C_{34}H_{68}O_2$	1190-63-2	508.903	lf or pl (eth, HOAc)	57			1.4410^{70}	vs ace, eth, chl
5770	Hexadecyltrichlorosilane		$C_{16}H_{33}Cl_3Si$	5894-60-0	359.878			269			
5771	Hexadecyl vinyl ether	1-(Ethenyloxy)hexadecane	$C_{18}H_{36}O$	822-28-6	268.478		16	160^{2}	0.821^{27}	1.4444^{25}	
5772	1-Hexadecyne		$C_{16}H_{30}$	629-74-3	222.409		15	284	0.7965^{20}	1.4440^{20}	vs bz
5773	*trans,trans*-2,4-Hexadienal	Sorbinaldehyde	C_6H_8O	142-83-6	96.127	liq	-16.5	174; 76^{30}	0.898^{20}	1.5384^{20}	
5774	1,2-Hexadiene	Propylallene	C_6H_{10}	592-44-9	82.143			76	0.7149^{20}	1.4282^{20}	vs eth, chl
5775	*cis*-1,3-Hexadiene		C_6H_{10}	14596-92-0	82.143			73.1	0.7033^{25}	1.4379^{20}	
5776	*trans*-1,3-Hexadiene		C_6H_{10}	20237-34-7	82.143	liq	-102.4	73.2	0.6995^{25}	1.4406^{20}	
5777	*cis*-1,4-Hexadiene		C_6H_{10}	7318-67-4	82.143			66.3	0.695^{25}	1.4049^{20}	vs eth
5778	*trans*-1,4-Hexadiene		C_6H_{10}	7319-00-8	82.143	liq	-138.7	65.0	0.695^{25}	1.4104^{20}	
5779	1,5-Hexadiene	Biallyl	C_6H_{10}	592-42-7	82.143	liq	-140.7	59.4	0.6878^{25}	1.4042^{20}	i H_2O; s EtOH, eth, bz, chl; sl ctc
5780	*cis,cis*-2,4-Hexadiene		C_6H_{10}	6108-61-8	82.143	liq		85	0.7298^{25}	1.4606^{20}	i H_2O; s EtOH, eth, chl
5781	*trans,cis*-2,4-Hexadiene		C_6H_{10}	5194-50-3	82.143	liq	-96.1	83.5	0.7185^{25}	1.4560^{20}	i H_2O; s EtOH, eth, chl
5782	*trans,trans*-2,4-Hexadiene		C_6H_{10}	5194-51-4	82.143	liq	-44.9	82.2	0.7101^{25}	1.4510^{20}	i H_2O; s EtOH, eth, chl
5783	2,4-Hexadienoic acid	Sorbic acid	$C_6H_8O_2$	110-44-1	112.127	nd (dil al) nd (w)	134.5	dec 228; 153^{50}	1.204^{19}		s H_2O, EtOH, chl; vs eth



Hexachloropropene



Hexacontane



Hexacosane



Hexacosanoic acid



1-Hexacosanol



Hexadecamethylheptasiloxane



Hexadecanal



Hexadecanamide



Hexadecane



Hexadecanedioic acid



Hexadecanenitrile



1-Hexadecanethiol



Hexadecanoic acid



Hexadecanoic anhydride



1-Hexadecanol



3-Hexadecanone



Hexadecanoyl chloride



1-Hexadecene



cis-9-Hexadecenoic acid



Hexadecyl acetate



Hexadecylamine



Hexadecylbenzene



Hexadecyldimethylamine



Hexadecyl hexadecanoate



Hexadecyl 3-hydroxy-2-naphthalenecarboxylate



Hexadecyl 2-hydroxypropanoate



Hexadecyl 2-methyl-2-propenoate



3-(Hexadecyloxy)-1,2-propanediol, (*S*)



1-Hexadecylpyridinium bromide



1-Hexadecylpyridinium chloride



Hexadecyl stearate



Hexadecyltrichlorosilane



Hexadecyl vinyl ether



1-Hexadecyne



trans,trans-2,4-Hexadienal



1,2-Hexadiene



cis-1,3-Hexadiene



trans-1,3-Hexadiene



cis-1,4-Hexadiene



trans-1,4-Hexadiene


1,5-Hexadiene



cis,cis-2,4-Hexadiene



trans,cis-2,4-Hexadiene



trans,trans-2,4-Hexadiene



2,4-Hexadienoic acid

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5784	2,4-Hexadien-1-ol	Sorbic alcohol	$C_6H_{10}O$	111-28-4	98.142	nd	30.5	76^{12}	0.8967^{23}	1.4981^{20}	i H_2O; s EtOH, eth
5785	*trans,trans*-2,4-Hexadienoyl chloride		C_6H_7ClO	2614-88-2	130.572			82^{22}	1.0666^{19}	1.5545^{20}	vs ace
5786	1,5-Hexadien-3-yne	Divinylacetylene	C_6H_6	821-08-9	78.112	liq	-88	85	0.7851^{20}	1.5035^{20}	i H_2O; s bz
5787	1,5-Hexadiyne	Bipropargyl	C_6H_6	628-16-0	78.112	liq	-6	86	0.8049^{20}	1.4380^{23}	i H_2O; s EtOH, eth, ace, bz
5788	2,4-Hexadiyne	Dimethyldiacetylene	C_6H_6	2809-69-0	78.112	pr (sub)	67.8	129.5			vs EtOH, eth
5789	Hexaethylbenzene		$C_{18}H_{30}$	604-88-6	246.431	mcl pr (al or bz)	129	298	0.8305^{130}	1.4736^{130}	i H_2O; s EtOH, sulf; vs eth, bz
5790	Hexaethyldisiloxane		$C_{12}H_{30}OSi_2$	994-49-0	246.536			233; 129^{30}	0.8457^{20}	1.4340^{20}	
5791	Hexaethyl tetraphosphate	Ethyl tetraphosphate	$C_{12}H_{30}O_{13}P_4$	757-58-4	506.253	hyg	-40	dec 150	1.2917^{27}	1.4273^{27}	vs ace, bz, EtOH
5792	Hexafluorenium bromide		$C_{36}H_{42}Br_2N_2$	317-52-2	662.539	cry (PrOH)	188				
5793	Hexafluoroacetylacetone		$C_5H_2F_6O_2$	1522-22-1	208.059			54.15	1.485^{20}	1.3333^{20}	
5794	Hexafluorobenzene	Perfluorobenzene	C_6F_6	392-56-3	186.054		5.03	80.26	1.6184^{20}	1.3777^{20}	
5795	1,1,2,3,4,4-Hexafluoro-1,3-butadiene		C_4F_6	685-63-2	162.033	col gas	-132	6	1.553^{-20}	1.378^{-20}	
5796	1,1,1,4,4,4-Hexafluoro-2-butyne		C_4F_6	692-50-2	162.033	col gas	-117.4	-24.6			s EtOH, eth, ace, ctc, HOAc
5797	Hexafluorocyclobutene		C_4F_6	697-11-0	162.033	col gas	-60	5.5	1.602^{-20}	1.298^{-20}	
5798	Hexafluoroethane	Perfluoroethane	C_2F_6	76-16-4	138.011	col gas	-100.05	-78.1	1.590^{-78}		i H_2O; sl EtOH, eth
5799	1,1,1,2,3,3-Hexafluoropropane	Refrigerant 236ea	$C_3H_2F_6$	431-63-0	152.038	col gas		6.1	1.5026^{0}		
5800	1,1,1,3,3,3-Hexafluoropropane	Refrigerant 236fa	$C_3H_2F_6$	690-39-1	152.038	col gas	-93.6	-1.0	1.4343^{0}		
5801	1,1,1,3,3,3-Hexafluoro-2-propanol		$C_3H_2F_6O$	920-66-1	168.037	liq	-2.0	59	1.4600^{21}		
5802	Hexahydro-1*H*-azepine	Hexamethylenimine	$C_6H_{13}N$	111-49-9	99.174			138	0.8643^{22}	1.4631^{20}	s H_2O; vs EtOH, eth
5803	Hexahydro-1*H*-1,4-diazepine		$C_5H_{12}N_2$	505-66-8	100.162	hyg	40.5	169			
5804	1,5a,6,9,9a,9b-Hexahydro-4a(4*H*)-dibenzofurancarboxaldehyde		$C_{13}H_{16}O_2$	126-15-8	204.265	liq	-80	307	1.10^{20}	1.5254^{20}	i H_2O
5805	*cis*-1,2,3,5,6,8a-Hexahydro-4,7-dimethyl-1-isopropylnaphthalene, (1*S*)		$C_{15}H_{24}$	483-76-1	204.352			125^{12}	0.9160^{15}	1.5089^{15}	
5806	1,2,4a,5,8,8a-Hexahydro-4,7-dimethyl-1-isopropylnaphthalene, [1*S*-(1α,4aβ,8aα)]		$C_{15}H_{24}$	523-47-7	204.352			274; 136^{11}	0.9230^{20}	1.5059^{20}	vs eth, lig
5807	Hexahydro-1,3-isobenzofurandione	Hexahydrophthalic anhydride	$C_8H_{10}O_3$	85-42-7	154.163		32	145^{18}			
5808	Hexahydro-1-methyl-1*H*-1,4-diazepine		$C_6H_{14}N_2$	4318-37-0	114.188			154	0.9111^{20}	1.4769^{20}	
5809	2,3,4,6,7,8-Hexahydropyrrolo[1,2-a]pyrimidine		$C_7H_{12}N_2$	3001-72-7	124.183			96^{7}, 81^{2}	1.005^{25}	1.5190^{20}	
5810	Hexahydro-1,3,5-trinitro-1,3,5-triazine	Cyclonite	$C_3H_6N_6O_6$	121-82-4	222.116	orth cry (ace)	205.5		1.82^{20}		i H_2O, EtOH, bz; sl eth, MeOH; s ace, HOAc
5811	Hexahydro-1,3,5-triphenyl-1,3,5-triazine		$C_{21}H_{21}N_3$	91-78-1	315.412		144	185; 60^{29}			i H_2O; sl EtOH; s eth, ace, bz, tol
5812	1,2,3,5,6,7-Hexahydroxy-9,10-anthracenedione	Rufigallol	$C_{14}H_8O_8$	82-12-2	304.209	red rhom, red-ye nd (sub)		sub			i H_2O; sl EtOH, eth; s ace, alk
5813	Hexamethylbenzene	Mellitene	$C_{12}H_{18}$	87-85-4	162.271	orth pr or nd (al)	165.5	263.4	1.0630^{25}		i H_2O; s EtOH, eth, ace, bz, HOAc, chl
5814	2,2,4,4,6,6-Hexamethylcyclotrisilazane		$C_6H_{21}N_3Si_3$	1009-93-4	219.508	liq	-10	188	0.9196^{20}	1.448^{20}	
5815	Hexamethylcyclotrisiloxane	Dimethylsiloxane cyclic trimer	$C_6H_{18}O_3Si_3$	541-05-9	222.462		64.5	134	1.1200^{20}		i H_2O
5816	Hexamethyldisilane		$C_6H_{18}Si_2$	1450-14-2	146.378		13.5	113.5	0.7247^{22}	1.4229^{20}	i H_2O; s eth, ace, bz; dec alk
5817	Hexamethyldisilathiane		$C_6H_{18}SSi_2$	3385-94-2	178.443			162.5	0.851^{20}		
5818	Hexamethyldisilazane		$C_6H_{19}NSi_2$	999-97-3	161.393			125	0.7741^{25}	1.4090^{20}	
5819	Hexamethyldisiloxane		$C_6H_{18}OSi_2$	107-46-0	162.377	liq	-66	99	0.7638^{20}	1.3774^{20}	i H_2O
5820	Hexamethylenediamine carbamate	(6-Aminohexyl)carbamic acid	$C_7H_{16}N_2O_2$	143-06-6	160.214	cry	150				
5821	Hexamethylene diisocyanate		$C_8H_{12}N_2O_2$	822-06-0	168.193			122^{10}, 94^{1}	1.0528^{20}	1.4585^{20}	
5822	Hexamethylenetetramine	Methenamine	$C_6H_{12}N_4$	100-97-0	140.186	orth (al)	>250	sub	1.331^{-5}		vs H_2O; s EtOH, ace, chl; sl eth, bz
5823	Hexamethylolmelamine		$C_9H_{18}N_6O_6$	531-18-0	306.275		137				vs H_2O
5824	Hexamethylphosphoric triamide	Tris(dimethylamino)phosphine oxide	$C_6H_{18}N_3OP$	680-31-9	179.200			232.5	1.03^{20}	1.4579^{20}	s EtOH, eth
5825	Hexamethylphosphorous triamide	Tris(dimethylamino)phosphine	$C_6H_{18}N_3P$	1608-26-0	163.201						s chl



2,4-Hexadien-1-ol



trans,trans-2,4-Hexadienoyl chloride



1,5-Hexadien-3-yne



1,5-Hexadiyne


2,4-Hexadiyne



Hexaethylbenzene



Hexaethyldisiloxane



Hexaethyl tetraphosphate



Hexafluorenium bromide


Hexafluoroacetylacetone



Hexafluorobenzene



1,1,2,3,4,4-Hexafluoro-1,3-butadiene



1,1,1,4,4,4-Hexafluoro-2-butyne


Hexafluorocyclobutene


Hexafluoroethane



1,1,1,2,3,3-Hexafluoropropane



1,1,1,3,3,3-Hexafluoropropane



1,1,1,3,3,3-Hexafluoro-2-propanol



Hexahydro-1*H*-azepine



Hexahydro-1*H*-1,4-diazepine



1,5a,6,9,9a,9b-Hexahydro-4a(4*H*)-dibenzofurancarboxaldehyde



cis-1,2,3,5,6,8a-Hexahydro-4,7-dimethyl-1-isopropylnaphthalene, (1*S*)



1,2,4a,5,8,8a-Hexahydro-4,7-dimethyl-1-isopropylnaphthalene, [1*S*-(1α,4aβ,8aα)]



Hexahydro-1,3-isobenzofurandione



Hexahydro-1-methyl-1*H*-1,4-diazepine



2,3,4,6,7,8-Hexahydropyrrolo[1,2-a]pyrimidine



Hexahydro-1,3,5-trinitro-1,3,5-triazine



Hexahydro-1,3,5-triphenyl-1,3,5-triazine



1,2,3,5,6,7-Hexahydroxy-9,10-anthracenedione



Hexamethylbenzene



2,2,4,4,6,6-Hexamethylcyclotrisilazane



Hexamethylcyclotrisiloxane



Hexamethyldisilane


Hexamethyldisilathiane



Hexamethyldisilazane



Hexamethyldisiloxane



Hexamethylenediamine carbamate


Hexamethylene diisocyanate



Hexamethylenetetramine



Hexamethylolmelamine



Hexamethylphosphoric triamide


Hexamethylphosphorous triamide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5826	2,6,10,15,19,23-Hexamethyltetracosane	Squalane	$C_{30}H_{62}$	111-01-3	422.813	liq	-38	350	0.8115^{15}	1.4530^{15}	i H_2O; sl EtOH, ace; s eth, chl; msc bz
5827	Hexanal	Caproaldehyde	$C_6H_{12}O$	66-25-1	100.158	liq	-56	131	0.8335^{20}	1.4039^{20}	sl H_2O; vs EtOH, eth; s ace, bz
5828	Hexanamide		$C_6H_{13}NO$	628-02-4	115.173	cry (ace)	101	255	0.999^{20}	1.4200^{110}	vs bz, eth, EtOH, chl
5829	Hexane		C_6H_{14}	110-54-3	86.175	liq	-95.35	68.73	0.6606^{25}	1.3727^{25}	i H_2O; vs EtOH; s eth, chl
5830	Hexanedial		$C_6H_{10}O_2$	1072-21-5	114.142		-8	93^{9}	1.003^{19}	1.4350^{20}	vs bz, eth, EtOH
5831	Hexanediamide		$C_6H_{12}N_2O_2$	628-94-4	144.171	pl	220				vs EtOH
5832	1,6-Hexanediamine	Hexamethylenediamine	$C_6H_{16}N_2$	124-09-4	116.204	orth bipym pl	39.13	205			vs H_2O; s EtOH, bz
5833	Hexanedioic acid, dihydrazide		$C_6H_{14}N_4O_2$	1071-93-8	174.201		181.8				
5834	1,2-Hexanediol		$C_6H_{14}O_2$	6920-22-5	118.174		45	$224; 87^{1.5}$		1.4431^{20}	
5835	1,6-Hexanediol	Hexamethylene glycol	$C_6H_{14}O_2$	629-11-8	118.174		41.5	208		1.4579^{25}	s H_2O, EtOH, ace; sl eth; i bz
5836	2,5-Hexanediol	Diisopropanol	$C_6H_{14}O_2$	2935-44-6	118.174	cry (eth)	43	$218; 86^{1}$	0.9610^{20}	1.4475^{20}	s H_2O, EtOH, eth; sl ctc
5837	1,6-Hexanediol dimethacrylate	Hexamethylene methacrylate	$C_{14}H_{22}O_4$	6606-59-3	254.323				0.998^{25}		
5838	2,3-Hexanedione	Acetylbutyryl	$C_6H_{10}O_2$	3848-24-6	114.142			128	0.934^{19}		
5839	2,4-Hexanedione	Propionylacetone	$C_6H_{10}O_2$	3002-24-2	114.142	oil		160	0.959^{20}	1.4516^{20}	
5840	2,5-Hexanedione	Acetonylacetone	$C_6H_{10}O_2$	110-13-4	114.142	liq	-5.5	194	0.7370^{20}	1.4232^{20}	vs H_2O, bz, eth, EtOH
5841	3,4-Hexanedione	Bipropionyl	$C_6H_{10}O_2$	4437-51-8	114.142	liq	-10	130	0.941^{21}	1.4130^{21}	
5842	Hexanedioyl dichloride		$C_6H_8Cl_2O_2$	111-50-2	183.033			126^{12}			sl chl
5843	1,6-Hexanedithiol		$C_6H_{14}S_2$	1191-43-1	150.305	liq	-21	$237; 118^{15}$	0.9886^{25}	1.5110^{20}	
5844	Hexanenitrile	Capronitrile	$C_6H_{11}N$	628-73-9	97.158	liq	-80.3	163.65	0.8051^{20}	1.4068^{20}	i H_2O; s EtOH, eth; sl chl
5845	1-Hexanethiol	Hexyl mercaptan	$C_6H_{14}S$	111-31-9	118.240	liq	-81	152.7	0.8424^{20}	1.4496^{20}	i H_2O; vs EtOH, eth
5846	2-Hexanethiol		$C_6H_{14}S$	1679-06-7	118.240	liq	-147	142	0.8345^{20}	1.4451^{20}	i H_2O; s EtOH, eth, bz
5847	1,2,6-Hexanetriol	1,2,6-Trihydroxyhexane	$C_6H_{14}O_3$	106-69-4	134.173			$170^{3}, 161^{1}$	1.1049^{20}	1.58^{20}	
5848	Hexanoic acid	Caproic acid	$C_6H_{12}O_2$	142-62-1	116.158	liq	-3	205.2	0.9212^{25}	1.4163^{20}	sl H_2O; s EtOH, eth, chl
5849	Hexanoic anhydride		$C_{12}H_{22}O_3$	2051-49-2	214.301		-41	dec 255	0.9240^{15}	1.4297^{20}	vs eth, EtOH
5850	1-Hexanol	Caproyl alcohol	$C_6H_{14}O$	111-27-3	102.174	liq	-47.4	157.6	0.8136^{20}	1.4178^{20}	sl H_2O; s EtOH, ace, chl; msc eth, bz
5851	2-Hexanol		$C_6H_{14}O$	20281-86-1	102.174			140	0.8159^{20}	1.4144^{20}	sl H_2O, ctc; s EtOH, eth
5852	3-Hexanol		$C_6H_{14}O$	17015-11-1	102.174			135	0.8182^{20}	1.4167^{20}	sl H_2O; s EtOH, ace; msc eth
5853	2-Hexanone	Butyl methyl ketone	$C_6H_{12}O$	591-78-6	100.158	liq	-55.5	127.6	0.8113^{20}	1.4007^{20}	sl H_2O; s ace; msc EtOH, eth
5854	3-Hexanone	Ethyl propyl ketone	$C_6H_{12}O$	589-38-8	100.158	liq	-55.4	123.5	0.8118^{20}	1.4004^{20}	sl H_2O; s ace; msc EtOH, eth
5855	Hexanoyl chloride	Caproyl chloride	$C_6H_{11}ClO$	142-61-0	134.603	liq	-87	153	0.9784^{20}	1.4264^{20}	s eth, ace
5856	Hexatriacontane		$C_{36}H_{74}$	630-06-8	506.973		75.8	298.4^{3}	0.7803^{80}	1.4397^{80}	
5857	*cis*-1,3,5-Hexatriene		C_6H_8	2612-46-6	80.128	liq	-12	78	0.7175^{20}	1.4577^{20}	i H_2O; s EtOH, ace, chl, peth
5858	*trans*-1,3,5-Hexatriene		C_6H_8	821-07-8	80.128	liq	-12	78.5	0.7369^{15}	1.5135^{20}	i H_2O; s EtOH, ace, chl, peth
5859	Hexazinone		$C_{12}H_{20}N_4O_2$	51235-04-2	252.313		99	dec	1.25		
5860	*trans*-2-Hexenal		$C_6H_{10}O$	6728-26-3	98.142			$146.5; 50^{20}$	0.8491^{20}	1.4480^{20}	
5861	*cis*-3-Hexenal		$C_6H_{10}O$	6789-80-6	98.142			121	0.8533^{22}	1.4300^{21}	
5862	1-Hexene		C_6H_{12}	592-41-6	84.159	liq	-139.76	63.48	0.6685^{25}	1.3852^{25}	i H_2O; vs bz, eth, EtOH, peth
5863	*cis*-2-Hexene		C_6H_{12}	7688-21-3	84.159	liq	-141.11	68.8	0.6824^{25}	1.3979^{20}	i H_2O; s EtOH, eth, bz, chl, lig
5864	*trans*-2-Hexene		C_6H_{12}	4050-45-7	84.159	liq	-133	67.9	0.6733^{25}	1.3936^{20}	i H_2O; s EtOH, eth, bz, chl, lig
5865	*cis*-3-Hexene		C_6H_{12}	7642-09-3	84.159	liq	-137.8	66.4	0.6778^{20}	1.3947^{20}	i H_2O; s EtOH, eth, bz, chl, lig
5866	*trans*-3-Hexene		C_6H_{12}	13269-52-8	84.159	liq	-115.4	67.1	0.6772^{20}	1.3943^{20}	i H_2O; s EtOH, eth, bz, chl, lig
5867	*trans*-3-Hexenedinitrile	*trans*-1,4-Dicyano-2-butene	$C_6H_6N_2$	1119-85-3	106.125	cry	76				
5868	2-Hexenoic acid		$C_6H_{10}O_2$	1191-04-4	114.142	nd (w, al)	36.5	216.5	0.965^{20}	1.4460^{40}	vs eth
5869	3-Hexenoic acid	Hydrosorbic acid	$C_6H_{10}O_2$	4219-24-3	114.142		12	208	0.9640^{23}	1.4935^{20}	
5870	5-Hexenoic acid		$C_6H_{10}O_2$	1577-22-6	114.142	liq	-37	203	0.9610^{20}	1.4343^{20}	vs eth, EtOH
5871	1-Hexen-3-ol		$C_6H_{12}O$	4798-44-1	100.158			134	0.834^{22}	1.4297^{18}	sl H_2O; vs ace, eth, EtOH



2,6,10,15,19,23-Hexamethyltetracosane



Hexanal



Hexanamide



Hexane



Hexanedial



Hexanediamide



1,6-Hexanediamine



Hexanedioic acid, dihydrazide



1,2-Hexanediol



1,6-Hexanediol



2,5-Hexanediol



1,6-Hexanediol dimethacrylate



2,3-Hexanedione



2,4-Hexanedione



2,5-Hexanedione



3,4-Hexanedione



Hexanedioyl dichloride



1,6-Hexanedithiol



Hexanenitrile



1-Hexanethiol



2-Hexanethiol



1,2,6-Hexanetriol



Hexanoic acid



Hexanoic anhydride



1-Hexanol



2-Hexanol



3-Hexanol



2-Hexanone



3-Hexanone



Hexanoyl chloride



Hexatriacontane



cis-1,3,5-Hexatriene



trans-1,3,5-Hexatriene



Hexazinone



trans-2-Hexenal



cis-3-Hexenal



1-Hexene



cis-2-Hexene



trans-2-Hexene



cis-3-Hexene



trans-3-Hexene


trans-3-Hexenedinitrile



2-Hexenoic acid



3-Hexenoic acid



5-Hexenoic acid



1-Hexen-3-ol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5872	*cis*-2-Hexen-1-ol		$C_6H_{12}O$	928-94-9	100.158			157	0.8472^{20}	1.4397^{20}	s H_2O; vs EtOH; s eth, ace; sl ctc
5873	*trans*-2-Hexen-1-ol		$C_6H_{12}O$	928-95-0	100.158			157	0.8490^{16}	1.4340^{20}	
5874	*cis*-3-Hexen-1-ol		$C_6H_{12}O$	928-96-1	100.158			156.5	0.8478^{22}	1.4380^{20}	s H_2O; vs EtOH, eth
5875	*trans*-3-Hexen-1-ol		$C_6H_{12}O$	928-97-2	100.158			154.5		1.4374^{20}	
5876	*trans*-4-Hexen-1-ol		$C_6H_{12}O$	928-92-7	100.158			159	0.8513^{20}	1.4402^{20}	
5877	4-Hexen-2-ol		$C_6H_{12}O$	52387-50-5	100.158			137.5	0.8405^{18}	1.4392^{20}	sl H_2O
5878	5-Hexen-2-ol		$C_6H_{12}O$	626-94-8	100.158			139	0.842^{16}		sl H_2O
5879	*cis*-3-Hexen-1-ol, acetate		$C_8H_{14}O_2$	3681-71-8	142.196	liq		66^{12}			
5880	*trans*-2-Hexen-1-ol, acetate		$C_8H_{14}O_2$	2497-18-9	142.196	liq		166; 68^{15}	0.898	1.4270^{20}	
5881	5-Hexen-2-one		$C_6H_{10}O$	109-49-9	98.142			129.5	0.833^{27}	1.4178^{27}	
5882	4-Hexen-3-one		$C_6H_{10}O$	2497-21-4	98.142			138.5	0.8559^{20}	1.4388^{20}	s EtOH, eth; vs ace
5883	Hexestrol		$C_{18}H_{22}O_2$	84-16-2	270.367	nd (bz)	186.5				vs ace, eth, EtOH
5884	Hexobarbital		$C_{12}H_{16}N_2O_3$	56-29-1	236.266		146.5				
5885	Hexocyclium methyl sulfate		$C_{21}H_{36}N_2O_5S$	115-63-9	428.586	cry	205				sl chl; i eth
5886	Hexyl acetate		$C_8H_{16}O_2$	142-92-7	144.212	liq	-80.9	171.5	0.8779^{15}	1.4092^{20}	i H_2O; vs eth, EtOH
5887	*sec*-Hexyl acetate		$C_8H_{16}O_2$	108-84-9	144.212			147.5	0.8805^{25}	1.3980^{20}	sl H_2O; vs eth, EtOH
5888	Hexyl acrylate		$C_9H_{16}O_2$	2499-95-8	156.222		-45	40^{1}	0.878^{20}		
5889	Hexylamine	1-Hexanamine	$C_6H_{15}N$	111-26-2	101.190	liq	-22.9	132.8	0.7660^{20}	1.4180^{20}	sl H_2O; msc EtOH, eth; s chl
5890	Hexylbenzene		$C_{12}H_{18}$	1077-16-3	162.271	liq	-61	226.1	0.8575^{20}	1.4864^{20}	i H_2O; msc eth; s bz, peth
5891	4-Hexyl-1,3-benzenediol	4-Hexylresorcinol	$C_{12}H_{18}O_2$	136-77-6	194.270	nd (bz)	68	334			vs ace, eth, EtOH, chl
5892	Hexyl benzoate		$C_{13}H_{18}O_2$	6789-88-4	206.281			272; 139^{8}	0.9793^{20}		i H_2O; s EtOH, ace
5893	Hexyl butanoate		$C_{10}H_{20}O_2$	2639-63-6	172.265	liq	-78	208	0.8652^{20}	1.4160^{15}	i H_2O; s EtOH; sl chl
5894	Hexylcyclohexane		$C_{12}H_{24}$	4292-75-5	168.319	liq	-43	224	0.8076^{20}	1.4462^{20}	
5895	Hexylcyclopentane		$C_{11}H_{22}$	4457-00-5	154.293	liq	-73	203	0.7965^{20}	1.4392^{20}	vs ace, bz, eth, EtOH
5896	2-Hexyldecanoic acid		$C_{16}H_{32}O_2$	25354-97-6	256.424	visc oil		$145^{0.02}$		1.4432^{24}	
5897	Hexyl formate		$C_7H_{14}O_2$	629-33-4	130.185	liq	-62.6	155.5	0.8813^{20}	1.4071^{20}	i H_2O; msc EtOH, eth
5898	Hexyl hexanoate	Hexyl caproate	$C_{12}H_{24}O_2$	6378-65-0	200.318	liq	-55	246	0.865^{18}	1.4264^{15}	vs ace, bz, eth, EtOH
5899	Hexyl isocyanate		$C_7H_{13}NO$	2525-62-4	127.184			44^{7}			
5900	Hexyl methacrylate		$C_{10}H_{18}O_2$	142-09-6	170.249			162; 86^{17}	0.880^{25}	1.429^{25}	vs ace, bz, eth, EtOH
5901	Hexyl methyl ether		$C_7H_{16}O$	4747-07-3	116.201			126.1			
5902	1-Hexylnaphthalene		$C_{16}H_{20}$	2876-53-1	212.330	liq	-18	322	0.9566^{20}	1.5647^{20}	
5903	Hexyl octanoate		$C_{14}H_{28}O_2$	1117-55-1	228.371	liq	-30.6	277.4	0.8603^{20}	1.4323^{25}	i H_2O; s EtOH, eth, ace
5904	4-(Hexyloxy)benzoic acid		$C_{13}H_{18}O_3$	1142-39-8	222.280	cry	106				
5905	2-(Hexyloxy)ethanol	Ethylene glycol monohexyl ether	$C_8H_{18}O_2$	112-25-4	146.228	liq	-45.1	208	0.8878^{20}	1.4291^{20}	sl H_2O; vs EtOH, eth
5906	Hexyl pentanoate		$C_{11}H_{22}O_2$	1117-59-5	186.292	liq	-63.1	226.3	0.8635^{20}	1.4228^{15}	vs ace, eth, EtOH
5907	4-Hexylphenol		$C_{12}H_{18}O$	2446-69-7	178.270			148^{9}			
5908	1-Hexyl propanoate		$C_9H_{18}O_2$	2445-76-3	158.238	liq	-57.5	190	0.8698^{20}	1.4162^{15}	i H_2O; s EtOH, eth, ace, AcOEt
5909	1-Hexyl-1,2,3,4-tetrahydronaphthalene		$C_{16}H_{24}$	66325-11-9	216.362	liq		305	0.9176^{25}	1.5127^{25}	
5910	1-Hexyne	Butylacetylene	C_6H_{10}	693-02-7	82.143	liq	-131.9	71.3	0.7155^{25}	1.3989^{20}	i H_2O; s EtOH, eth, bz, chl; sl ctc
5911	2-Hexyne	1-Methyl-2-propylacetylene	C_6H_{10}	764-35-2	82.143	liq	-89.6	84.5	0.7315^{20}	1.4138^{20}	i H_2O; msc EtOH, eth; s bz, chl, peth
5912	3-Hexyne	Diethylacetylene	C_6H_{10}	928-49-4	82.143	liq	-103	81	0.7231^{20}	1.4115^{20}	i H_2O; s EtOH, eth, bz, chl, peth
5913	3-Hexyne-2,5-diol		$C_6H_{10}O_2$	3031-66-1	114.142			121^{15}	1.0180^{20}	1.4691^{20}	
5914	3-Hexyn-1-ol	3-Hexynol	$C_6H_{10}O$	1002-28-4	98.142			162; 65^{12}	0.8982^{20}	1.4530^{20}	
5915	1-Hexyn-3-ol		$C_6H_{10}O$	105-31-7	98.142	liq	-80	142	0.8704^{20}	1.4340^{25}	s ctc
5916	5-Hexyn-2-one		C_6H_8O	2550-28-9	96.127			149	0.9065^{20}	1.4366^{20}	



cis-2-Hexen-1-ol



trans-2-Hexen-1-ol



cis-3-Hexen-1-ol



trans-3-Hexen-1-ol



trans-4-Hexen-1-ol



4-Hexen-2-ol



5-Hexen-2-ol



cis-3-Hexen-1-ol, acetate



trans-2-Hexen-1-ol, acetate



5-Hexen-2-one



4-Hexen-3-one



Hexestrol



Hexobarbital



Hexocyclium methyl sulfate



Hexyl acetate



sec-Hexyl acetate



Hexyl acrylate



Hexylamine



Hexylbenzene



4-Hexyl-1,3-benzenediol


Hexyl benzoate



Hexyl butanoate



Hexylcyclohexane



Hexylcyclopentane



2-Hexyldecanoic acid



Hexyl formate



Hexyl hexanoate



Hexyl isocyanate



Hexyl methacrylate



Hexyl methyl ether



1-Hexylnaphthalene



Hexyl octanoate



4-(Hexyloxy)benzoic acid



2-(Hexyloxy)ethanol



Hexyl pentanoate



4-Hexylphenol



1-Hexyl propanoate



1-Hexyl-1,2,3,4-tetrahydronaphthalene



1-Hexyne



2-Hexyne


3-Hexyne



3-Hexyne-2,5-diol



3-Hexyn-1-ol



1-Hexyn-3-ol



5-Hexyn-2-one


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5917	Histamine		$C_5H_9N_3$	51-45-6	111.145	wh nd (chl)	83	209^{18}			s H_2O, EtOH, chl; sl eth
5918	*L*-Histidine	Glyoxaline-5-alanine	$C_6H_9N_3O_2$	71-00-1	155.154	nd or pl (dil al)	287 dec				s H_2O; sl EtOH; i eth, ace, bz, chl
5919	*L*-Histidine, monohydrochloride		$C_6H_{10}ClN_3O_2$	645-35-2	191.615		245 dec				s H_2O
5920	Homatropine		$C_{16}H_{21}NO_3$	87-00-3	275.343	pr (al, eth)	99.5				sl H_2O, bz; s EtOH, eth, ace, chl
5921	Homatropine hydrobromide	Tropanol mandelate	$C_{16}H_{22}BrNO_3$	51-56-9	356.255	orth pym or pl (w)	217 dec				vs H_2O, EtOH
5922	Homochlorocyclizine		$C_{19}H_{23}ClN_2$	848-53-3	314.852	oil		$177^{0.8}$			
5923	*DL*-Homocysteine	*DL*-2-Amino-4-mercaptobutanoic acid	$C_4H_9NO_2S$	454-29-5	135.185		272 dec				s H_2O; i eth, bz
5924	*L*-Homocysteine	*L*-2-Amino-4-mercaptobutanoic acid	$C_4H_9NO_2S$	6027-13-0	135.185	platelets	232				
5925	Homocystine		$C_8H_{16}N_2O_4S_2$	870-93-9	268.354		264				sl H_2O; i eth, bz
5926	*L*-Homoserine	2-Amino-4-hydroxybutanoic acid, (*S*)	$C_4H_9NO_3$	672-15-1	119.119	pr (90% al)	203 dec				vs H_2O; sl EtOH; i eth, bz
5927	Humulene		$C_{15}H_{24}$	6753-98-6	204.352			123^{10}	0.8905^{20}	1.5038^{20}	
5928	Humulon		$C_{21}H_{30}O_5$	26472-41-3	362.460	ye cry (eth)	66.5				sl H_2O; s EtOH, eth, ace, bz, alk
5929	Hydralazine	1-Hydrazinophthalazine	$C_8H_8N_4$	86-54-4	160.177	ye cry (MeOH)	172				s acid
5930	Hydramethylnon		$C_{25}H_{24}F_6N_4$	67485-29-4	494.476		190				
5931	Hydrastine		$C_{21}H_{21}NO_6$	118-08-1	383.395	ye pr (al)	132				i H_2O; s ace, bz
5932	Hydrastinine		$C_{11}H_{13}NO_3$	6592-85-4	207.226	nd (lig), cry (eth)	116.5				s H_2O; vs EtOH, eth, chl
5933	Hydrazinecarbothioamide	Thiosemicarbazide	CH_5N_3S	79-19-6	91.136	lo nd (w)	183				vs H_2O, EtOH
5934	Hydrazinecarboxaldehyde		CH_4N_2O	624-84-0	60.055	ye lf or nd (al)	54				vs bz, eth, EtOH, chl
5935	Hydrazinecarboxamide		CH_5N_3O	57-56-7	75.070	pr (al)	96		1.484^{8}		vs H_2O; s EtOH; i eth, bz, chl
5936	Hydrazinecarboximidamide	Aminoguanidine	CH_6N_4	79-17-4	74.086	cry	dec				vs H_2O, EtOH
5937	1,2-Hydrazinedicarboxaldehyde		$C_2H_4N_2O_2$	628-36-4	88.065	pr (al)	161.0				vs H_2O; sl EtOH, DMSO; i eth
5938	1,2-Hydrazinedicarboxamide		$C_2H_6N_4O_2$	110-21-4	118.095	pl (w)	258		1.604^{17}		
5939	4-Hydrazinobenzenesulfonic acid	Phenylhydrazine-4-sulfonic acid	$C_6H_8N_2O_3S$	98-71-5	188.204	nd, lf (w)	286				sl H_2O, EtOH
5940	4-Hydrazinobenzoic acid		$C_7H_8N_2O_2$	619-67-0	152.151	ye nd or pl (w)	221 dec				sl H_2O; i eth
5941	2-Hydrazinoethanol		$C_2H_8N_2O$	109-84-2	76.097	liq	-70	$219; 120^{17.5}$	1.119^{25}		vs H_2O, EtOH, MeOH
5942	Hydrindantin		$C_{18}H_{10}O_6$	5103-42-4	322.268	pr (ace)	250 dec				
5943	Hydrochlorothiazide		$C_7H_8ClN_3O_4S_2$	58-93-5	297.740		274				
5944	Hydrocinchonidine		$C_{19}H_{24}N_2O$	485-64-3	296.406	lf (al)	229				vs EtOH
5945	Hydrocinchonine		$C_{19}H_{24}N_2O$	485-65-4	296.406	pr	268.5				s H_2O; sl EtOH; i eth
5946	Hydrocodone		$C_{18}H_{21}NO_3$	125-29-1	299.365		198				i H_2O; s EtOH
5947	Hydrocortisone		$C_{21}H_{30}O_5$	50-23-7	362.460	pl (al or i-PrOH)	220				sl H_2O; s EtOH, diox, HOAc
5948	Hydrocortisone 21-acetate	Cortisol acetate	$C_{23}H_{32}O_6$	50-03-3	404.496		223 dec		1.289^{20}		
5949	Hydrocotarnine		$C_{12}H_{15}NO_3$	550-10-7	221.252		56				i H_2O; s EtOH, eth, ace, bz, chl
5950	Hydroflumethiazide		$C_8H_8F_3N_3O_4S_2$	135-09-1	331.293		270.5				
5951	Hydrofuramide		$C_{15}H_{12}N_2O_3$	494-47-3	268.267	nd (al)	117				i H_2O; vs EtOH, eth
5952	Hydrogen cyanide	Hydrocyanic acid	CHN	74-90-8	27.026	vol liq or gas	-13.29	26	0.6876^{20}	1.2614^{20}	msc H_2O, EtOH, eth
5953	Hydrohydrastinine		$C_{11}H_{13}NO_2$	494-55-3	191.227	nd (lig), cry (peth)	66	303			vs ace, bz, eth, EtOH
5954	Hydromorphone	7,8-Dihydromorphin-6-one	$C_{17}H_{19}NO_3$	466-99-9	285.338	cry (EtOH)	266.5				
5955	Hydroprene		$C_{17}H_{30}O_2$	41096-46-2	266.419			174^{19}	0.8955^{20}		
5956	Hydroquinidine		$C_{20}H_{26}N_2O_2$	1435-55-8	326.432	nd (al)	168.5				s EtOH, eth, ace, chl
5957	Hydroquinine		$C_{20}H_{26}N_2O_2$	522-66-7	326.432	nd (eth, chl)	172.5				vs ace, eth, EtOH, chl
5958	*p*-Hydroquinone	1,4-Benzenediol	$C_6H_6O_2$	123-31-9	110.111	mcl pr (sub) nd(w) pr (MeOH)	172.4	285	1.330^{20}	1.632^{25}	s H_2O, eth; vs EtOH, ace; i bz
5959	Hydroxocobalamin	Vitamin B-12a	$C_{62}H_{89}CoN_{13}O_{15}P$	13422-51-0	1346.355	red cry (ace aq)	200 dec				s H_2O, EtOH; i ace, eth, bz



Histamine



L-Histidine



L-Histidine, monohydrochloride



Homatropine



Homatropine hydrobromide



Homochlorocyclizine



DL-Homocysteine



L-Homocysteine



Homocystine



L-Homoserine



Humulene



Humulon



Hydralazine



Hydramethylnon



Hydrastine



Hydrastinine



Hydrazinecarbothioamide



Hydrazinecarboxaldehyde



Hydrazinecarboxamide



Hydrazinecarboximidamide



1,2-Hydrazinedicarboxaldehyde



1,2-Hydrazinedicarboxamide



4-Hydrazinobenzenesulfonic acid



4-Hydrazinobenzoic acid



2-Hydrazinoethanol



Hydrindantin



Hydrochlorothiazide



Hydrocinchonidine



Hydrocinchonine



Hydrocodone


Hydrocortisone



Hydrocortisone 21-acetate



Hydrocotarnine



Hydroflumethiazide



Hydrofuramide


Hydrogen cyanide



Hydrohydrastinine



Hydromorphone


Hydroprene



Hydroquinidine



Hydroquinine



p-Hydroquinone



Hydroxocobalamin


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5960	Hydroxyacetonitrile	Glyconitrile	C_2H_3NO	107-16-4	57.051		<-72	dec 183; 119[24]		1.4117[19]	vs H_2O, EtOH, eth; i bz, chl
5961	(Hydroxyacetyl)benzene		$C_8H_8O_2$	582-24-1	136.149	hex pl (al), pl (w or dil al)	90	125[12], 56[1]	1.0963[99]		s H_2O, EtOH, eth, chl; sl lig
5962	17-Hydroxyandrostan-3-one, (5α,17β)	Stanolone	$C_{19}H_{30}O_2$	521-18-6	290.440		181	sub 135			
5963	3-Hydroxyandrostan-17-one, (3α,5α)	Androsterone	$C_{19}H_{30}O_2$	53-41-8	290.440	lf or nd (al, ace)	185				sl H_2O, chl; s EtOH, eth, ace, bz
5964	3-Hydroxyandrostan-17-one, (3β,5α)	Epiandrosterone	$C_{19}H_{30}O_2$	481-29-8	290.440	cry (bz-peth, ace)	178				
5965	17-Hydroxyandrost-4-en-3-one, (17β)	Testosterone	$C_{19}H_{28}O_2$	58-22-0	288.424	nd (dil ace)	155				i H_2O; s EtOH, eth, ace
5966	1-Hydroxy-9,10-anthracenedione		$C_{14}H_8O_3$	129-43-1	224.212	red-oran nd (al)	193.8	sub			i H_2O; s EtOH, eth, bz; sl liq NH_3
5967	2-Hydroxy-9,10-anthracenedione		$C_{14}H_8O_3$	605-32-3	224.212	ye pl or nd (al or HOAc)	306	sub			i H_2O; s EtOH, eth, aq NH_3, KOH
5968	3-Hydroxybenzaldehyde	3-Formylphenol	$C_7H_6O_2$	100-83-4	122.122	nd (w)	108	240	1.1179[130]		sl H_2O; s EtOH, eth, ace, bz; i lig
5969	4-Hydroxybenzaldehyde	4-Formylphenol	$C_7H_6O_2$	123-08-0	122.122	nd (w)	117		1.129[130]	1.5705[130]	sl H_2O, ace; vs EtOH, eth; s bz
5970	2-Hydroxybenzaldehyde, [(2-hydroxyphenyl)methylene] hydrazone		$C_{14}H_{12}N_2O_2$	959-36-4	240.257		214				i H_2O; s EtOH, chl; vs bz, alk
5971	2-Hydroxybenzamide	Salicylamide	$C_7H_7NO_2$	65-45-2	137.137		142	181.5[14]	1.175[140]		sl H_2O, eth, DMSO; s EtOH
5972	*N*-Hydroxybenzamide		$C_7H_7NO_2$	495-18-1	137.137	orth ta, lf (eth)	131 exp				s H_2O, EtOH; sl eth, bz
5973	α-Hydroxybenzeneacetic acid, (±)	*DL*-Mandelic acid	$C_8H_8O_3$	611-72-3	152.148	orth pl	119		1.2890[20]		s H_2O, eth, EtOH, i-PrOH
5974	2-Hydroxybenzeneacetic acid		$C_8H_8O_3$	614-75-5	152.148		148	240			sl H_2O, chl; s eth
5975	3-Hydroxybenzeneacetic acid		$C_8H_8O_3$	621-37-4	152.148	nd (bz-lig)	132	190[11]			vs H_2O, EtOH, eth; s bz; sl lig
5976	4-Hydroxybenzeneacetic acid		$C_8H_8O_3$	156-38-7	152.148	nd (w)	152	sub			sl H_2O; vs EtOH, eth
5977	α-Hydroxybenzeneacetonitrile	Mandelonitrile	C_8H_7NO	532-28-5	133.148	ye oily liq	-10		1.12		i H_2O; vs chl, eth, EtOH
5978	2-Hydroxybenzenecarbodithioic acid	Dithiosalicylic acid	$C_7H_6OS_2$	527-89-9	170.252	oran-ye nd	49				vs bz, eth, EtOH
5979	4-Hydroxy-1,3-benzenedicarboxylic acid	4-Hydroxyisophthalic acid	$C_8H_6O_5$	636-46-4	182.131	nd(w), lf (dil al)	310				i H_2O, chl; vs EtOH, eth; s HOAc
5980	5-Hydroxy-1,3-benzenedicarboxylic acid		$C_8H_6O_5$	618-83-7	182.131	nd(w+2) cr(aq-al)		sub			vs bz, eth, EtOH
5981	4-Hydroxy-1,3-benzenedisulfonic acid	Phenoldisulfonic acid	$C_6H_6O_7S_2$	96-77-5	254.238	nd (w)	>100 dec				vs H_2O, EtOH
5982	4-Hydroxybenzeneethanol		$C_8H_{10}O_2$	501-94-0	138.164		91.8	310.0			
5983	2-Hydroxybenzenemethanol	Salicyl alcohol	$C_7H_8O_2$	90-01-7	124.138	lf (bz), nd or pl (w, eth)	87	sub	1.1613[25]		s H_2O, EtOH, eth, bz; vs chl
5984	3-Hydroxybenzenemethanol	3-Hydroxybenzyl alcohol	$C_7H_8O_2$	620-24-6	124.138	nd (bz), cry (CCl_4)	73	dec 300	1.161[25]		vs H_2O, EtOH, eth; sl chl
5985	4-Hydroxybenzenemethanol	4-Hydroxybenzyl alcohol	$C_7H_8O_2$	623-05-2	124.138	pr or nd (w)	124.5	252			vs H_2O, EtOH, bz, chl; s eth; sl DMSO
5986	4-Hydroxybenzenepropanoic acid	*p*-Hydroxyhydrocinnamic acid	$C_9H_{10}O_3$	501-97-3	166.173		130.8	209[14]			s H_2O, EtOH, eth, bz; i CS_2
5987	α-Hydroxybenzenepropanoic acid, (±)	(±)-3-Phenyllactic acid	$C_9H_{10}O_3$	828-01-3	166.173	cry (chl, bz), pr (w)	98	149[15]			vs H_2O, ace, eth, EtOH
5988	3-Hydroxybenzenesulfonic acid	*m*-Phenolsulfonic acid	$C_6H_6O_4S$	585-38-6	174.175	nd (w+2)					
5989	4-Hydroxybenzenesulfonic acid	*p*-Phenolsulfonic acid	$C_6H_6O_4S$	98-67-9	174.175	nd					vs H_2O, EtOH
5990	2-Hydroxybenzoic acid	Salicylic acid	$C_7H_6O_3$	69-72-7	138.121	nd (w), mcl pr (al)	159.0	211[20]	1.443[20]	1.565	sl H_2O, bz, chl, ctc; vs EtOH, eth, ace
5991	3-Hydroxybenzoic acid		$C_7H_6O_3$	99-06-9	138.121	nd (w) pl, pr (al)	202.5		1.485[25]		sl H_2O; s EtOH, eth, ace; i bz
5992	4-Hydroxybenzoic acid		$C_7H_6O_3$	99-96-7	138.121	pr or pl (w, al) cry (ace)	214.5		1.46[25]		sl H_2O, bz; vs EtOH; s eth, ace
5993	2-Hydroxybenzoic acid, hydrazide		$C_7H_8N_2O_2$	936-02-7	152.151		148				vs bz, EtOH
5994	2-Hydroxybenzonitrile		C_7H_5NO	611-20-1	119.121		98	149[14]	1.1052[100]	1.5372[100]	sl H_2O; vs EtOH, eth, bz, chl



Hydroxyacetonitrile



(Hydroxyacetyl)benzene



17-Hydroxyandrostan-3-one, (5α,17β)



3-Hydroxyandrostan-17-one, (3α,5α)



3-Hydroxyandrostan-17-one, (3β,5α)



17-Hydroxyandrost-4-en-3-one, (17β)



1-Hydroxy-9,10-anthracenedione



2-Hydroxy-9,10-anthracenedione



3-Hydroxybenzaldehyde



4-Hydroxybenzaldehyde



2-Hydroxybenzaldehyde, [(2-hydroxyphenyl)methylene]hydrazone



2-Hydroxybenzamide



N-Hydroxybenzamide



α-Hydroxybenzeneacetic acid, (±)



2-Hydroxybenzeneacetic acid



3-Hydroxybenzeneacetic acid



4-Hydroxybenzeneacetic acid



α-Hydroxybenzeneacetonitrile



2-Hydroxybenzenecarbodithioic acid



4-Hydroxy-1,3-benzenedicarboxylic acid



5-Hydroxy-1,3-benzenedicarboxylic acid



4-Hydroxy-1,3-benzenedisulfonic acid



4-Hydroxybenzeneethanol



2-Hydroxybenzenemethanol



3-Hydroxybenzenemethanol



4-Hydroxybenzenemethanol



4-Hydroxybenzenepropanoic acid



α-Hydroxybenzenepropanoic acid, (±)



3-Hydroxybenzenesulfonic acid



4-Hydroxybenzenesulfonic acid


2-Hydroxybenzoic acid



3-Hydroxybenzoic acid



4-Hydroxybenzoic acid



2-Hydroxybenzoic acid, hydrazide



2-Hydroxybenzonitrile


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
5995	3-Hydroxybenzonitrile		C_7H_5NO	873-62-1	119.121	pr (al, eth) lf (w)	82.8				vs H_2O, EtOH, eth, bz, chl
5996	4-Hydroxybenzonitrile		C_7H_5NO	767-00-0	119.121	lf (w)	113	148[1]			sl H_2O, DMSO; vs EtOH, eth, chl
5997	4-Hydroxybenzophenone	4-Hydroxyphenyl phenyl ketone	$C_{13}H_{10}O_2$	1137-42-4	198.217	nd (al), pr (dil al)	135		1.133[172]		sl H_2O; vs EtOH, eth, HOAc
5998	4-Hydroxy-2*H*-1-benzopyran-2-one		$C_9H_6O_3$	1076-38-6	162.142	nd (w)	213.5				s H_2O, EtOH, eth; sl DMSO
5999	7-Hydroxy-2*H*-1-benzopyran-2-one	Umbelliferone	$C_9H_6O_3$	93-35-6	162.142	nd (w)	230.5	sub			vs EtOH, HOAc, chl
6000	1-Hydroxy-1*H*-benzotriazole		$C_6H_5N_3O$	2592-95-2	135.123		157.8				
6001	2-Hydroxybenzoyl chloride		$C_7H_5ClO_2$	1441-87-8	156.567		19	92[15]	1.3112[20]	1.5812[20]	vs eth
6002	4-(2-Hydroxybenzoyl)morpholine	4-Salicyloylmorpholine	$C_{11}H_{10}NO_3$	3202-84-4	204.202						s DMSO
6003	2-Hydroxybiphenyl	[1,1'-Biphenyl]-2-ol	$C_{12}H_{10}O$	90-43-7	170.206		57.5	286	1.213[25]		i H_2O; s EtOH, ace, bz; vs eth, py
6004	3-Hydroxybiphenyl	[1,1'-Biphenyl]-3-ol	$C_{12}H_{10}O$	580-51-8	170.206		78	>300			sl H_2O; vs EtOH, eth, bz, py; s chl
6005	4-Hydroxybiphenyl	[1,1'-Biphenyl]-4-ol	$C_{12}H_{10}O$	92-69-3	170.206		166	305			sl H_2O, DMSO; vs EtOH, eth, chl, py
6006	3-Hydroxybutanal	Aldol	$C_4H_8O_2$	107-89-1	88.106			83[20]	1.103[20]	1.4238[20]	msc H_2O, EtOH; s eth; vs ace
6007	2-Hydroxybutanoic acid, (±)		$C_4H_8O_3$	600-15-7	104.105		44.2	dec 260; 140[14]	1.125[20]		s H_2O, EtOH, eth
6008	3-Hydroxybutanoic acid, (±)		$C_4H_8O_3$	625-71-8	104.105		49	130[12], 94[0.1]		1.4424[20]	vs H_2O, EtOH, eth; i bz
6009	4-Hydroxybutanoic acid		$C_4H_8O_3$	591-81-1	104.105		<-17	dec 180			
6010	1-Hydroxy-2-butanone		$C_4H_8O_2$	5077-67-8	88.106			160; 78[60]	1.0272[20]	1.4189[20]	vs H_2O, EtOH, eth
6011	3-Hydroxy-2-butanone, (±)	Acetoin	$C_4H_8O_2$	52217-02-4	88.106		15	148	1.0044[20]	1.4171[20]	msc H_2O; sl EtOH, eth; s ace, chl; i lig
6012	4-Hydroxy-2-butanone		$C_4H_8O_2$	590-90-9	88.106			182; 90[11]	1.0233[20]	1.4585[14]	msc H_2O, EtOH, eth; vs ace
6013	2-Hydroxy-3-butenenitrile		C_4H_5NO	5809-59-6	83.089	liq		94[17]			
6014	4-Hydroxybutyramide		$C_4H_9NO_2$	927-60-6	103.120		52				
6015	3-Hydroxycamphor	3-Hydroxy-1,7,7-trimethylbicyclo[2.2.1]heptan-2-one	$C_{10}H_{16}O_2$	10373-81-6	168.233	nd (bz-peth)	205.5				vs eth, EtOH, chl
6016	3-Hydroxycholan-24-oic acid, (3α,5β)	Lithocholic acid	$C_{24}H_{40}O_3$	434-13-9	376.573	hex lf (al) pr (dil al)	186				i H_2O, lig; s EtOH, chl, HOAc; sl eth
6017	Hydroxycodeinone		$C_{18}H_{19}NO_4$	508-54-3	313.349		275 dec				
6018	2-Hydroxycyclodecanone	Sebacoin	$C_{10}H_{18}O_2$	96-00-4	170.249	cry (peth)	38.5	136[14]			
6019	2-Hydroxy-2,4,6-cycloheptatrien-1-one		$C_7H_6O_2$	533-75-5	122.122	nd	50.8	sub 40			s H_2O, eth, ace
6020	1-Hydroxycyclohexanecarbonitrile		$C_7H_{11}NO$	931-97-5	125.168		35	132[20]	1.0172[20]	1.4693[20]	vs H_2O, eth
6021	2-Hydroxycyclohexanone		$C_6H_{10}O_2$	533-60-8	114.142	nd (al)				1.4785[21]	vs H_2O, EtOH; i eth, bz, peth
6022	1-(1-Hydroxycyclohexyl)ethanone		$C_8H_{14}O_2$	1123-27-9	142.196			125.5; 91[11]	1.0248[25]	1.4670[25]	vs eth, EtOH
6023	4-Hydroxydecanoic acid γ-lactone	5-Hexyldihydro-2(3*H*)-furanone	$C_{10}H_{18}O_2$	706-14-9	170.249	liq		281			
6024	2-Hydroxy-3,5-diiodobenzoic acid	3,5-Diiodosalicylic acid	$C_7H_4I_2O_3$	133-91-5	389.914	nd (al)	235.5				sl H_2O; vs EtOH, eth; i bz, chl
6025	4-Hydroxy-3,5-diiodobenzoic acid		$C_7H_4I_2O_3$	618-76-8	389.914		237	dec 260			i H_2O; vs EtOH, eth; sl bz, chl, lig
6026	4-Hydroxy-3,5-diiodobenzonitrile		$C_7H_3I_2NO$	1689-83-4	370.914		201 dec				
6027	4-Hydroxy-3,5-diiodo-α-phenylbenzenepropanoic acid	Iodoalphionic acid	$C_{15}H_{12}I_2O_3$	577-91-3	494.063		164				i H_2O; s EtOH, eth; sl bz, chl
6028	2-Hydroxy-4,6-dimethoxybenzaldehyde		$C_9H_{10}O_4$	708-76-9	182.173		70	193[25], 165[10]			i H_2O; vs EtOH, eth, bz, chl, HOAc
6029	4-Hydroxy-3,5-dimethoxybenzaldehyde	Syringaldehyde	$C_9H_{10}O_4$	134-96-3	182.173	br nd (lig)	113	192[14]			sl H_2O, lig; vs EtOH, eth, bz, chl
6030	4-Hydroxy-3,5-dimethoxybenzoic acid		$C_9H_{10}O_5$	530-57-4	198.172	nd (w)	204.5				sl H_2O; vs EtOH
6031	7-Hydroxy-3,7-dimethyloctanal		$C_{10}H_{20}O_2$	107-75-5	172.265			103[3]	0.9220[20]	1.4494[20]	sl H_2O; s EtOH, ace
6032	3-Hydroxy-2,2-dimethylpropanal	Hydroxypivaldehyde	$C_5H_{10}O_2$	597-31-9	102.132	nd (w)	89.5	173; 68[14]			
6033	2-Hydroxy-3,5-dinitrobenzoic acid		$C_7H_4N_2O_7$	609-99-4	228.116	ye nd or pl (+1w)	182				s H_2O, EtOH, eth, bz



3-Hydroxybenzonitrile



4-Hydroxybenzonitrile



4-Hydroxybenzophenone



4-Hydroxy-2*H*-1-benzopyran-2-one



7-Hydroxy-2*H*-1-benzopyran-2-one



1-Hydroxy-1*H*-benzotriazole



2-Hydroxybenzoyl chloride



4-(2-Hydroxybenzoyl)morpholine



2-Hydroxybiphenyl



3-Hydroxybiphenyl



4-Hydroxybiphenyl


3-Hydroxybutanal



2-Hydroxybutanoic acid, (±)



3-Hydroxybutanoic acid, (±)



4-Hydroxybutanoic acid



1-Hydroxy-2-butanone



3-Hydroxy-2-butanone, (±)



4-Hydroxy-2-butanone



2-Hydroxy-3-butenenitrile



4-Hydroxybutyramide



3-Hydroxycamphor



3-Hydroxycholan-24-oic acid, (3α,5β)



Hydroxycodeinone



2-Hydroxycyclodecanone



2-Hydroxy-2,4,6-cycloheptatrien-1-one



1-Hydroxycyclohexanecarbonitrile



2-Hydroxycyclohexanone



1-(1-Hydroxycyclohexyl)ethanone



4-Hydroxydecanoic acid γ-lactone



2-Hydroxy-3,5-diiodobenzoic acid



4-Hydroxy-3,5-diiodobenzoic acid



4-Hydroxy-3,5-diiodobenzonitrile


4-Hydroxy-3,5-diiodo-α-phenylbenzenepropanoic acid



2-Hydroxy-4,6-dimethoxybenzaldehyde


4-Hydroxy-3,5-dimethoxybenzaldehyde



4-Hydroxy-3,5-dimethoxybenzoic acid



7-Hydroxy-3,7-dimethyloctanal



3-Hydroxy-2,2-dimethylpropanal



2-Hydroxy-3,5-dinitrobenzoic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6034	11-Hydroxy-9,15-dioxoprosta-5,13-dien-1-oic acid, (5*Z*,11α,13*E*)	15-Oxo-prostaglandin E2	$C_{20}H_{30}O_5$	26441-05-4	350.449	cry					
6035	1-Hydroxy-1,1-diphosphonoethane	Etidronic acid	$C_2H_8O_7P_2$	2809-21-4	206.028	cry (w)	105				s H_2O, EtOH, MeOH
6036	3-Hydroxyestra-1,3,5,7,9-pentaen-17-one	Equilenin	$C_{18}H_{18}O_2$	517-09-9	266.335		258.5	sub 170			sl EtOH, ace, chl
6037	3-Hydroxyestra-1,3,5(10),7-tetraen-17-one	Equilin	$C_{18}H_{20}O_2$	474-86-2	268.351	pl (AcOEt)	239	sub 170			sl H_2O; s EtOH, ace, diox, AcOEt
6038	2-Hydroxyethyl acrylate	2-Hydroxyethyl 2-propenoate	$C_5H_8O_3$	818-61-1	116.116	liq		191; 91^{12}	1.011^{23}		
6039	*N*-(2-Hydroxyethyl)dodecanamide		$C_{14}H_{29}NO_2$	142-78-9	243.386		88.5				
6040	*N*-(2-Hydroxyethyl) ethylenediaminetriacetic acid		$C_{10}H_{18}N_2O_7$	150-39-0	278.259	cry	165 dec				
6041	2-Hydroxyethyl 2-hydroxybenzoate	Glycol salicylate	$C_9H_{10}O_4$	87-28-5	182.173		37	173^{15}	1.2526^{15}		sl H_2O; vs EtOH, eth, bz, chl
6042	2-Hydroxyethyl methacrylate	Ethylene glycol monomethacrylate	$C_6H_{10}O_3$	868-77-9	130.141			103^{13}, 67^{3}	1.079^{20}	1.4515^{20}	
6043	*N*-(2-Hydroxyethyl)phthalimide		$C_{10}H_9NO_3$	3891-07-4	191.183	nd (al), lf (w)	130.3				sl H_2O
6044	1-(2-Hydroxyethyl)-2-pyrrolidinone		$C_6H_{11}NO_2$	3445-11-2	129.157		20	295	1.1435^{20}		
6045	4-Hydroxy-4*H*-furo[3,2-c]pyran-2(6*H*)-one	Patulin	$C_7H_6O_4$	149-29-1	154.121	pl or pr (eth, chl)	111				s H_2O, EtOH, eth, ace, bz; i peth
6046	16-Hydroxyhexadecanoic acid	16-Hydroxypalmitic acid	$C_{16}H_{32}O_3$	506-13-8	272.423		96.5				i H_2O; s EtOH, ace; sl eth, bz
6047	2-Hydroxyhexanoic acid		$C_6H_{12}O_3$	6064-63-7	132.157	pr (eth)	60				vs H_2O
6048	6-Hydroxyhexanoic acid		$C_6H_{12}O_3$	1191-25-9	132.157	liq					
6049	3-Hydroxy-2-(hydroxymethyl)-2-methylpropanoic acid	Dimethylolpropionic acid	$C_5H_{10}O_4$	4767-03-7	134.131		190				
6050	5-Hydroxy-2-(hydroxymethyl)-4*H*-pyran-4-one	Kojic acid	$C_6H_6O_4$	501-30-4	142.110	pr nd (ace)	153.5				sl H_2O, bz; s EtOH, eth, ace, DMSO
6051	8-Hydroxy-7-iodo-5-quinolinesulfonic acid	Ferron	$C_9H_6INO_4S$	547-91-1	351.118	ye pr, lf (al)	260 dec				sl H_2O, EtOH; i eth, bz, chl; s con sulf
6052	2-Hydroxy-1*H*-isoindole-1,3(2*H*)-dione		$C_8H_5NO_3$	524-38-9	163.131		232				s DMSO
6053	2-Hydroxy-4-isopropyl-2,4,6-cycloheptatrien-1-one		$C_{10}H_{12}O_2$	499-44-5	164.201	pa ye (peth)	51.5	137^{10}	1.0606^{65}		sl H_2O, bz, lig; s ctc
6054	Hydroxylupanine		$C_{15}H_{24}N_2O_2$	15358-48-2	264.364	cry (ace)	169.5				vs H_2O, EtOH, chl
6055	*N*-Hydroxymethanamine	*N*-Methylhydroxylamine	CH_5NO	593-77-1	47.057	hyg nd	87.5	62.5^{15}	1.0003^{20}	1.4164^{20}	vs H_2O, EtOH
6056	2-Hydroxy-3-methoxybenzaldehyde		$C_8H_8O_3$	148-53-8	152.148	lt ye lf, grn nd (w, lig)	44.5	265.5			sl H_2O, lig; vs EtOH, eth, ctc
6057	2-Hydroxy-4-methoxybenzaldehyde		$C_8H_8O_3$	673-22-3	152.148	nd (w), cry (al)	42.0				s EtOH, eth, bz, lig
6058	2-Hydroxy-5-methoxybenzaldehyde		$C_8H_8O_3$	672-13-9	152.148	ye liq (w)	4	247.5			vs eth, EtOH
6059	3-Hydroxy-4-methoxybenzaldehyde		$C_8H_8O_3$	621-59-0	152.148		114	179^{15}	1.196^{25}		sl H_2O; s EtOH, eth, bz, HOAc; vs chl
6060	4-Hydroxy-3-methoxybenzaldehyde	Vanillin	$C_8H_8O_3$	121-33-5	152.148	tetr (w, lig)	81.5	285	1.056^{25}		sl H_2O; vs EtOH, eth, ace; s bz, lig
6061	4-Hydroxy-3-methoxybenzeneacetic acid	Homovanillic acid	$C_9H_{10}O_4$	306-08-1	182.173		143.5				
6062	4-Hydroxy-3-methoxybenzenemethanol		$C_8H_{10}O_3$	498-00-0	154.163	pr (w), nd (bz)	115	dec			s H_2O, EtOH, eth, bz
6063	4-Hydroxy-3-methoxybenzenepropanol		$C_{10}H_{14}O_3$	2305-13-7	182.216		65	197^{15}		1.5545^{25}	vs eth, EtOH
6064	2-Hydroxy-5-methoxybenzoic acid		$C_8H_8O_4$	2612-02-4	168.148		142				
6065	4-Hydroxy-3-methoxybenzoic acid	Vanillic acid	$C_8H_8O_4$	121-34-6	168.148	wh nd	211.5	sub			sl H_2O; vs EtOH; s eth, DMSO
6066	7-Hydroxy-6-methoxy-2*H*-1-benzopyran-2-one	Scopoletin	$C_{10}H_8O_4$	92-61-5	192.169	nd or pr (al)	204				sl H_2O, EtOH; s chl; i bz, CS_2
6067	4-(4-Hydroxy-3-methoxyphenyl)-2-butanone	Zingerone	$C_{11}H_{14}O_3$	122-48-5	194.227	cry (ace, eth)	40.5	187^{14}			vs eth
6068	1-(2-Hydroxy-4-methoxyphenyl) ethanone		$C_9H_{10}O_3$	552-41-0	166.173	nd (al)	52.5	158^{20}	1.3102^{81}	1.5452^{81}	vs bz, eth, EtOH, chl
6069	1-(4-Hydroxy-3-methoxyphenyl) ethanone	Apocynin	$C_9H_{10}O_3$	498-02-2	166.173	pr (w)	115	297; 234^{15}			sl H_2O; s EtOH, ace, bz; vs eth, chl
6070	(2-Hydroxy-4-methoxyphenyl) phenylmethanone	Oxybenzone	$C_{14}H_{12}O_3$	131-57-7	228.243		65.5				s ctc



11-Hydroxy-9,15-dioxoprosta-5,13-dien-1-oic acid, (5*Z*,11α,13*E*)



1-Hydroxy-1,1-diphosphonoethane



3-Hydroxyestra-1,3,5,7,9-pentaen-17-one



3-Hydroxyestra-1,3,5(10),7-tetraen-17-one



2-Hydroxyethyl acrylate



N-(2-Hydroxyethyl)dodecanamide



N-(2-Hydroxyethyl)ethylenediaminetriacetic acid



2-Hydroxyethyl 2-hydroxybenzoate



2-Hydroxyethyl methacrylate



N-(2-Hydroxyethyl)phthalimide



1-(2-Hydroxyethyl)-2-pyrrolidinone



4-Hydroxy-4*H*-furo[3,2-c]pyran-2(6*H*)-one



16-Hydroxyhexadecanoic acid



2-Hydroxyhexanoic acid



6-Hydroxyhexanoic acid



3-Hydroxy-2-(hydroxymethyl)-2-methylpropanoic acid


5-Hydroxy-2-(hydroxymethyl)-4*H*-pyran-4-one



8-Hydroxy-7-iodo-5-quinolinesulfonic acid



2-Hydroxy-1*H*-isoindole-1,3(2*H*)-dione



2-Hydroxy-4-isopropyl-2,4,6-cycloheptatrien-1-one



Hydroxylupanine



N-Hydroxymethanamine



2-Hydroxy-3-methoxybenzaldehyde



2-Hydroxy-4-methoxybenzaldehyde



2-Hydroxy-5-methoxybenzaldehyde



3-Hydroxy-4-methoxybenzaldehyde



4-Hydroxy-3-methoxybenzaldehyde



4-Hydroxy-3-methoxybenzeneacetic acid



4-Hydroxy-3-methoxybenzenemethanol



4-Hydroxy-3-methoxybenzenepropanol



2-Hydroxy-5-methoxybenzoic acid



4-Hydroxy-3-methoxybenzoic acid


7-Hydroxy-6-methoxy-2*H*-1-benzopyran-2-one



4-(4-Hydroxy-3-methoxyphenyl)-2-butanone



1-(2-Hydroxy-4-methoxyphenyl)ethanone



1-(4-Hydroxy-3-methoxyphenyl)ethanone



(2-Hydroxy-4-methoxyphenyl)phenylmethanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6071	3-(4-Hydroxy-3-methoxyphenyl)-2-propenal		$C_{10}H_{10}O_3$	458-36-6	178.184	cry (bz)	84		1.1562^{102}		vs bz, eth, EtOH
6072	*N*-Hydroxymethylamine hydrochloride	*N*-Methylhydroxylamine hydrochloride	CH_6ClNO	4229-44-1	83.518		83.5				
6073	4-Hydroxy-α-[(methylamino) methyl]benzenemethanol	Synephrine	$C_9H_{13}NO_2$	94-07-5	167.205		184.5				
6074	17-Hydroxy-17-methylandrostan-3-one, (5α,17β)	Mestanolone	$C_{20}H_{32}O_2$	521-11-9	304.467		192.5				sl AcOEt
6075	*N*-Hydroxy-4-methylaniline		C_7H_9NO	623-10-9	123.152	lf (bz)	96	dec 117			vs eth, EtOH, chl
6076	2-Hydroxy-5-methylbenzaldehyde		$C_8H_8O_2$	613-84-3	136.149	pl (aq, al)	56	217.5	1.0913^{59}	1.547^{59}	vs eth, EtOH, chl
6077	α-(Hydroxymethyl)benzeneacetic acid, (±)	Tropic acid	$C_9H_{10}O_3$	552-63-6	166.173	nd, pl (al, bz, w)	118	dec			vs H_2O, eth, EtOH
6078	α-Hydroxy-α-methylbenzeneacetic acid, (±)	Atrolactic acid	$C_9H_{10}O_3$	4607-38-9	166.173	nd, pl (lig)	94				vs ace, bz
6079	2-Hydroxy-5-methyl-1,3-benzenedimethanol		$C_9H_{12}O_3$	91-04-3	168.189		130.5				
6080	2-(Hydroxymethyl)-1,4-benzenediol	Gentisyl alcohol	$C_7H_8O_3$	495-08-9	140.137	nd (chl)	100	sub 75			vs H_2O, EtOH, chl
6081	2-Hydroxy-5-methylbenzoic acid	*p*-Cresotic acid	$C_8H_8O_3$	89-56-5	152.148		151				sl H_2O; s EtOH, eth, bz, chl; i CS_2
6082	2-Hydroxy-3-methylbenzoic acid	*o*-Cresotic acid	$C_8H_8O_3$	83-40-9	152.148		165.5				sl H_2O; s EtOH, eth, bz, chl
6083	2-Hydroxy-4-methylbenzoic acid	*m*-Cresotic acid	$C_8H_8O_3$	50-85-1	152.148	cry, lf	177				sl H_2O; s EtOH, bz, chl; vs eth
6084	7-Hydroxy-4-methyl-2*H*-1-benzopyran-2-one	Hymecromone	$C_{10}H_8O_3$	90-33-5	176.169	nd (al)	194.5				sl H_2O, eth, chl; s EtOH, alk, HOAc
6085	3-Hydroxy-3-methylbutanoic acid		$C_5H_{10}O_3$	625-08-1	118.131		<-32	162^{12}	0.9384^{20}	1.5081^{20}	vs H_2O, eth, EtOH
6086	3-Hydroxy-3-methyl-2-butanone		$C_5H_{10}O_2$	115-22-0	102.132			140	0.9526^{20}		s chl
6087	2-Hydroxy-3-methyl-2-cyclopenten-1-one		$C_6H_8O_2$	80-71-7	112.127		104.8				
6088	5-(Hydroxymethyl)-2-furancarboxaldehyde	5-(Hydroxymethyl)-2-furaldehyde	$C_6H_6O_3$	67-47-0	126.110	nd (eth-peth)	31.5	115^{1}	1.2062^{25}	1.5627^{18}	s H_2O, EtOH, bz, chl; sl eth, ctc
6089	2-Hydroxy-6-methyl-3-isopropylbenzoic acid	*o*-Thymotic acid	$C_{11}H_{14}O_3$	548-51-6	194.227	nd (w, bz, lig)	127	sub			vs bz, eth, EtOH
6090	2-Hydroxy-3-methyl-6-isopropyl-2-cyclohexen-1-one	Diosphenol	$C_{10}H_{16}O_2$	490-03-9	168.233		83	109^{10}			
6091	2-(Hydroxymethyl)-2-methyl-1,3-propanediol		$C_5H_{12}O_3$	77-85-0	120.147	wh pow or nd (al)	204	136^{15}			msc H_2O, EtOH; i eth, bz; vs HOAc
6092	2-Hydroxy-3-methyl-1,4-naphthalenedione	Phthiocol	$C_{11}H_8O_3$	483-55-6	188.180	ye pr (eth-peth)	173.5	sub			vs ace, eth
6093	5-Hydroxy-2-methyl-1,4-naphthalenedione	Plumbagin	$C_{11}H_8O_3$	481-42-5	188.180	gold pr or oran-ye nd (dil al)	78.5	sub			vs ace, bz, eth, EtOH
6094	2-(Hydroxymethyl)-2-nitro-1,3-propanediol	Tris(hydroxymethyl) nitromethane	$C_4H_9NO_5$	126-11-4	151.118	nd or pr	165	dec			vs H_2O, eth, EtOH
6095	2-Hydroxy-4-methylpentanoic acid, (*S*)	*L*-Leucic acid	$C_6H_{12}O_3$	13748-90-8	132.157	orth (eth)	81.5				vs H_2O, eth, EtOH
6096	1-(2-Hydroxy-4-methylphenyl) ethanone		$C_9H_{10}O_2$	6921-64-8	150.174		21	245	1.1012^{10}	1.5527^{13}	
6097	1-(2-Hydroxy-5-methylphenyl) ethanone		$C_9H_{10}O_2$	1450-72-2	150.174	pr (lig)	50	210; 120^{20}	1.0797^{53}		vs bz, eth, EtOH, chl
6098	2-(Hydroxymethyl)phenyl-β-*D*-glucopyranoside	Salicin	$C_{13}H_{18}O_7$	138-52-3	286.278	orth nd or lf (w)	207	dec 240	1.434^{20}		vs H_2O, EtOH, HOAc
6099	1-(2-Hydroxy-5-methylphenyl)-1-propanone		$C_{10}H_{12}O_2$	938-45-4	164.201		1.0	129$^{16.5}$	1.0841^{14}	1.549^{13}	s chl
6100	*N*-(Hydroxymethyl)phthalimide		$C_9H_7NO_3$	118-29-6	177.157	lf, pr (to)	141.5				i H_2O, eth, ctc; sl EtOH, bz; s tol
6101	3-Hydroxy-2-methylpropanal		$C_4H_8O_2$	38433-80-6	88.106	oil					
6102	2-Hydroxy-2-methylpropanoic acid		$C_4H_8O_3$	594-61-6	104.105	hyg pr (eth) nd (bz)	82.5	212			vs H_2O, EtOH, eth; sl bz
6103	3-Hydroxy-2-methylpropanoic acid		$C_4H_8O_3$	2068-83-9	104.105	oil					
6104	*N*-(Hydroxymethyl)-2-propenamide	*N*-(Hydroxymethyl)acrylamide	$C_4H_7NO_2$	924-42-5	101.105	cry	76				
6105	4-Hydroxy-6-methyl-2*H*-pyran-2-one	Triacetic acid lactone	$C_6H_6O_3$	675-10-5	126.110		189 dec				
6106	3-Hydroxy-2-methyl-4*H*-pyran-4-one	Maltol	$C_6H_6O_3$	118-71-8	126.110	mcl pr (chl)	161.5	sub 93			sl H_2O, eth, bz; vs chl; s alk; peth



3-(4-Hydroxy-3-methoxyphenyl)-2-propenal



N-Hydroxymethylamine hydrochloride



4-Hydroxy-α-[(methylamino)methyl]benzenemethanol



17-Hydroxy-17-methylandrostan-3-one, (5α,17β)



N-Hydroxy-4-methylaniline


2-Hydroxy-5-methylbenzaldehyde



α-(Hydroxymethyl)benzeneacetic acid, (±)



α-Hydroxy-α-methylbenzeneacetic acid, (±)



2-Hydroxy-5-methyl-1,3-benzenedimethanol



2-(Hydroxymethyl)-1,4-benzenediol


2-Hydroxy-5-methylbenzoic acid



2-Hydroxy-3-methylbenzoic acid



2-Hydroxy-4-methylbenzoic acid



7-Hydroxy-4-methyl-2*H*-1-benzopyran-2-one



3-Hydroxy-3-methylbutanoic acid



3-Hydroxy-3-methyl-2-butanone



2-Hydroxy-3-methyl-2-cyclopenten-1-one



5-(Hydroxymethyl)-2-furancarboxaldehyde



2-Hydroxy-6-methyl-3-isopropylbenzoic acid



2-Hydroxy-3-methyl-6-isopropyl-2-cyclohexen-1-one



2-(Hydroxymethyl)-2-methyl-1,3-propanediol



2-Hydroxy-3-methyl-1,4-naphthalenedione



5-Hydroxy-2-methyl-1,4-naphthalenedione



2-(Hydroxymethyl)-2-nitro-1,3-propanediol



2-Hydroxy-4-methylpentanoic acid, (*S*)



1-(2-Hydroxy-4-methylphenyl)ethanone



1-(2-Hydroxy-5-methylphenyl)ethanone



2-(Hydroxymethyl)phenyl-β-*D*-glucopyranoside



1-(2-Hydroxy-5-methylphenyl)-1-propanone



N-(Hydroxymethyl)phthalimide



3-Hydroxy-2-methylpropanal


2-Hydroxy-2-methylpropanoic acid



3-Hydroxy-2-methylpropanoic acid



N-(Hydroxymethyl)-2-propenamide



4-Hydroxy-6-methyl-2*H*-pyran-2-one



3-Hydroxy-2-methyl-4*H*-pyran-4-one


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6107	5-Hydroxy-6-methyl-3,4-pyridinedimethanol	Pyridoxin	$C_8H_{11}NO_3$	65-23-6	169.178	nd (HOAc)	160	$140^{0.0001}$			
6108	4-Hydroxy-1-methyl-2-quinolinone	4-Hydroxy-*N*-methylcarbostyril	$C_{10}H_9NO_2$	1677-46-9	175.184		265				sl DMSO
6109	2-Hydroxy-4-(methylthio)butanoic acid	Methionine hydroxy analog	$C_5H_{10}O_3S$	583-91-5	150.196	oil					
6110	3-Hydroxy-α-methyl-*L*-tyrosine	Methyldopa	$C_{10}H_{13}NO_4$	555-30-6	211.215	cry (MeOH)	300 dec				
6111	(Hydroxymethyl)urea		$C_2H_6N_2O_2$	1000-82-4	90.081	pr (al)	111				vs H_2O; s EtOH, MeOH, HOAc; i eth
6112	2-Hydroxy-1-naphthalenecarboxaldehyde		$C_{11}H_8O_2$	708-06-5	172.181	pr (al), nd (AcOEt)	83	192^{27}			i H_2O; s EtOH, eth, aq alk, sulf, peth
6113	2-Hydroxy-1-naphthalenecarboxylic acid	2-Hydroxy-1-naphthoic acid	$C_{11}H_8O_3$	2283-08-1	188.180		157.3				sl H_2O; vs EtOH; s eth, ace, bz, lig, chl
6114	1-Hydroxy-2-naphthalenecarboxylic acid	1-Hydroxy-2-naphthoic acid	$C_{11}H_8O_3$	86-48-6	188.180	cry (al) nd (al, eth, bz)	195				sl H_2O; vs EtOH, eth; s bz
6115	3-Hydroxy-2-naphthalenecarboxylic acid	3-Hydroxy-2-naphthoic acid	$C_{11}H_8O_3$	92-70-6	188.180	nd (dil al) ye lf (dil al)	222.5				sl H_2O; vs EtOH, eth; s bz, chl, tol
6116	2-Hydroxy-1,4-naphthalenedione	Lawsone	$C_{10}H_6O_3$	83-72-7	174.153	ye pr (HOAc)	195 dec				vs EtOH; i eth, bz, chl; s HOAc
6117	5-Hydroxy-1,4-naphthalenedione	Juglone	$C_{10}H_6O_3$	481-39-0	174.153	ye nd (bz) peth)	155	sub			i H_2O; s EtOH, eth, bz; vs chl; sl lig
6118	7-Hydroxy-1,3-naphthalenedisulfonic acid	2-Naphthol-6,8-disulfonic acid	$C_{10}H_8O_7S_2$	118-32-1	304.297						s H_2O
6119	3-Hydroxy-2,7-naphthalenedisulfonic acid	2-Naphthol-3,6-disulfonic acid	$C_{10}H_8O_7S_2$	148-75-4	304.297	hyg nd	dec				vs H_2O, EtOH
6120	6-Hydroxy-2-naphthalenepropanoic acid	Allenolic acid	$C_{13}H_{12}O_3$	553-39-9	216.232	cry (dil MeOH)	180.5				vs py, EtOH, MeOH
6121	4-Hydroxy-1-naphthalenesulfonic acid	1-Naphthol-4-sulfonic acid	$C_{10}H_8O_4S$	84-87-7	224.234	tab or pl (w)	170 dec				vs H_2O; i eth
6122	7-Hydroxy-1-naphthalenesulfonic acid	Croceic acid	$C_{10}H_8O_4S$	132-57-0	224.234						s H_2O
6123	1-Hydroxy-2-naphthalenesulfonic acid	1-Naphthol-2-sulfonic acid	$C_{10}H_8O_4S$	567-18-0	224.234	pl (w)	>250				sl H_2O, dil HCl; s EtOH; i eth
6124	6-Hydroxy-2-naphthalenesulfonic acid	2-Naphthol-6-sulfonic acid	$C_{10}H_8O_4S$	93-01-6	224.234	lf, cry (w+1)	125				vs H_2O, EtOH; i eth; s HOAc
6125	Hydroxynaphthol blue, trisodium salt		$C_{20}H_{14}N_2Na_3O_{11}S_3$	63451-35-4	623.495	dk red cry					
6126	*N*-(2-Hydroxy-1-naphthyl) acetamide		$C_{12}H_{11}NO_2$	117-93-1	201.221	lf (w, dil al)	235 dec	sub			vs ace, bz, eth, EtOH
6127	1-(1-Hydroxy-2-naphthyl) ethanone		$C_{12}H_{10}O_2$	711-79-5	186.206	pr (bz, lig) grn-ye nd (al)	101	dec 325			vs bz, HOAc
6128	2-Hydroxy-3-nitrobenzaldehyde		$C_7H_5NO_4$	5274-70-4	167.120	nd (HOAc)	109.5				vs bz, EtOH
6129	2-Hydroxy-5-nitrobenzaldehyde		$C_7H_5NO_4$	97-51-8	167.120	cry (dil HOAc)	127.0				s ace
6130	2-Hydroxy-3-nitrobenzoic acid	3-Nitrosalicylic acid	$C_7H_5NO_5$	85-38-1	183.119	ye nd (HOAc, w+1)	148				sl H_2O; vs EtOH, eth; s ace, bz, chl
6131	2-Hydroxy-5-nitrobenzoic acid	5-Nitrosalicylic acid	$C_7H_5NO_5$	96-97-9	183.119	nd (w)	229.5		1.650^{20}		sl H_2O; vs EtOH, eth, ace, bz; s chl
6132	2-Hydroxy-1,2,3-nonadecanetricarboxylic acid	Agaricic acid	$C_{22}H_{40}O_7$	666-99-9	416.549	cry pow	142 dec				s H_2O; sl EtOH, eth; i bz, chl
6133	12-Hydroxyoctadecanoic acid	12-Hydroxysteric acid	$C_{18}H_{36}O_3$	106-14-9	300.477	cry (al)	82				i H_2O; s EtOH, eth, chl
6134	*cis*-12-Hydroxy-9-octadecenoic acid, (*R*)	Ricinoleic acid	$C_{18}H_{34}O_3$	141-22-0	298.461	visc liq	5.5	227^{10}	0.9450^{21}	1.4716^{21}	i H_2O; vs eth, EtOH
6135	2-Hydroxyoctanoic acid		$C_8H_{16}O_3$	617-73-2	160.211	pl	70	162^{10}			sl H_2O, chl; vs EtOH, eth
6136	5-Hydroxy-4-octanone	Butyroin	$C_8H_{16}O_2$	496-77-5	144.212	liq	-10	185	0.9107^{16}	1.4345^{16}	
6137	[2-Hydroxy-4-(octyloxy)phenyl] phenylmethanone	Octabenzone	$C_{21}H_{26}O_3$	1843-05-6	326.429		48.5				
6138	3-Hydroxy-2-oxopropanoic acid	Hydroxypyruvic acid	$C_3H_4O_4$	1113-60-6	104.062		81 dec				
6139	3-Hydroxy-4-oxo-4*H*-pyran-2,6-dicarboxylic acid	Meconic acid	$C_7H_4O_7$	497-59-6	200.103	orth pl (w, dil HCl) (+3w)	120 dec				sl H_2O, MeOH, ace, eth; s EtOH, bz
6140	2-Hydroxypentanoic acid		$C_5H_{10}O_3$	617-31-2	118.131	hyg pl	34	sub			s H_2O, EtOH, eth
6141	5-Hydroxy-2-pentanone		$C_5H_{10}O_2$	1071-73-4	102.132			$209; 117^{33}$	1.0071^{20}	1.4390^{20}	msc H_2O; s EtOH, eth



5-Hydroxy-6-methyl-3,4-pyridinedimethanol



4-Hydroxy-1-methyl-2-quinolinone



2-Hydroxy-4-(methylthio)butanoic acid



3-Hydroxy-α-methyl-*L*-tyrosine



(Hydroxymethyl)urea



2-Hydroxy-1-naphthalenecarboxaldehyde



2-Hydroxy-1-naphthalenecarboxylic acid



1-Hydroxy-2-naphthalenecarboxylic acid



3-Hydroxy-2-naphthalenecarboxylic acid



2-Hydroxy-1,4-naphthalenedione



5-Hydroxy-1,4-naphthalenedione



7-Hydroxy-1,3-naphthalenedisulfonic acid



3-Hydroxy-2,7-naphthalenedisulfonic acid



6-Hydroxy-2-naphthalenepropanoic acid



4-Hydroxy-1-naphthalenesulfonic acid



7-Hydroxy-1-naphthalenesulfonic acid



1-Hydroxy-2-naphthalenesulfonic acid



6-Hydroxy-2-naphthalenesulfonic acid



Hydroxynaphthol blue, trisodium salt



N-(2-Hydroxy-1-naphthyl)acetamide



1-(1-Hydroxy-2-naphthyl)ethanone



2-Hydroxy-3-nitrobenzaldehyde



2-Hydroxy-5-nitrobenzaldehyde



2-Hydroxy-3-nitrobenzoic acid



2-Hydroxy-5-nitrobenzoic acid



2-Hydroxy-1,2,3-nonadecanetricarboxylic acid



12-Hydroxyoctadecanoic acid



cis-12-Hydroxy-9-octadecenoic acid, (*R*)



2-Hydroxyoctanoic acid



5-Hydroxy-4-octanone


[2-Hydroxy-4-(octyloxy)phenyl]phenylmethanone



3-Hydroxy-2-oxopropanoic acid



3-Hydroxy-4-oxo-4*H*-pyran-2,6-dicarboxylic acid



2-Hydroxypentanoic acid



5-Hydroxy-2-pentanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6142	7-Hydroxy-3*H*-phenoxazin-3-one	Resorufine	$C_{12}H_7NO_3$	635-78-9	213.189	br nd ($PhNO_2$) pr (HCl)					i H_2O; sl EtOH; i eth; vs alk
6143	*N*-(2-Hydroxyphenyl)acetamide		$C_8H_9NO_2$	614-80-2	151.163	pl (dil al)	209				sl H_2O; vs EtOH, eth, bz; s DMSO
6144	*N*-(3-Hydroxyphenyl)acetamide		$C_8H_9NO_2$	621-42-1	151.163	nd (w)	148.5				vs H_2O, EtOH; sl eth, bz, chl, DMSO
6145	*N*-(4-Hydroxyphenyl)acetamide	Acetaminophen	$C_8H_9NO_2$	103-90-2	151.163	mcl pr (w)	170		1.293^{21}		i H_2O; vs EtOH
6146	2-[(4-Hydroxyphenyl)azo]benzoic acid		$C_{13}H_{10}N_2O_3$	1634-82-8	242.229		206				sl DMSO
6147	2-Hydroxy-*N*-phenylbenzamide	Salicylanilide	$C_{13}H_{11}NO_2$	87-17-2	213.232	pr (w, al)	136.5				s H_2O; sl EtOH, eth, bz, chl
6148	*N*-Hydroxy-*N*-phenylbenzamide		$C_{13}H_{11}NO_2$	304-88-1	213.232		120.3				
6149	α-Hydroxy-α-phenylbenzeneacetic acid	Benzilic acid	$C_{14}H_{12}O_3$	76-93-7	228.243	mcl nd (w)	150	dec 180			sl H_2O, ace; vs EtOH, eth; s con sulf
6150	3-Hydroxy-2-phenyl-4*H*-1-benzopyran-4-one		$C_{15}H_{10}O_3$	577-85-5	238.238	pa ye nd (al)	169.5				s EtOH
6151	*N*-(4-Hydroxyphenyl)butanamide	4'-Hydroxybutyranilide	$C_{10}H_{13}NO_2$	101-91-7	179.216	nd (w)	139.5				vs H_2O, EtOH
6152	4-(4-Hydroxyphenyl)-2-butanone		$C_{10}H_{12}O_2$	5471-51-2	164.201		82.5				
6153	1-(2-Hydroxyphenyl)ethanone		$C_8H_8O_2$	118-93-4	136.149		2.5	218	1.1307^{20}	1.5584^{20}	vs eth, EtOH, HOAc
6154	1-(3-Hydroxyphenyl)ethanone		$C_8H_8O_2$	121-71-1	136.149	nd or lf	96	296; 153^{5}	1.0992^{109}	1.5348^{109}	sl H_2O; vs EtOH, eth, bz, chl; i lig
6155	1-(4-Hydroxyphenyl)ethanone		$C_8H_8O_2$	99-93-4	136.149	nd (eth, dil al)	109.5	147^{3}	1.1090^{109}	1.5577^{109}	sl H_2O, DMSO; vs EtOH, eth
6156	4-Hydroxyphenyl-β-*D*-glucopyranoside	Arbutin	$C_{12}H_{16}O_7$	497-76-7	272.251	nd (w+1)	199.5				vs H_2O; s EtOH; sl eth; i bz, chl, CS_2
6157	2-(4-Hydroxyphenyl)-*D*-glycine	Oxfenicine	$C_8H_9NO_3$	22818-40-2	167.162	cry	240 dec				
6158	*N*-(4-Hydroxyphenyl)glycine		$C_8H_9NO_3$	122-87-2	167.162	lf (w) pl (w)	246 dec				sl H_2O, EtOH; i eth; s AcOEt, chl
6159	2(2-Hydroxyphenyl)-2(4-hydroxyphenyl)propane	2,4'-Isopropylidenediphenol	$C_{15}H_{16}O_2$	837-08-1	228.287	cry (bz)	111				
6160	2-[[(2-Hydroxyphenyl)imino]methyl]phenol	*N*-Salicylidene-*o*-aminophenol	$C_{13}H_{11}NO_2$	1761-56-4	213.232		185				
6161	*N*-Hydroxy-*N*-(phenylmethyl)benzenemethanamine		$C_{14}H_{15}NO$	621-07-8	213.275		122.5				s chl
6162	*N*-(4-Hydroxyphenyl)octadecanamide		$C_{24}H_{41}NO_2$	103-99-1	375.589		133.8	239.5^{10}			i H_2O; sl eth, bz, chl; s ace
6163	3-(4-Hydroxyphenyl)-2-oxopropanoic acid	4-Hydroxy-α-oxobenzenepropanoic acid	$C_9H_8O_4$	156-39-8	180.158	cry (w)	220 dec				s H_2O; dec alk
6164	(2-Hydroxyphenyl)phenylmethanone		$C_{13}H_{10}O_2$	117-99-7	198.217	pl (dil al)	40	250^{560}			i H_2O; vs EtOH, eth, bz; sl chl, peth
6165	1-(2-Hydroxyphenyl)-3-phenyl-2-propen-1-one	2'-Hydroxychalcone	$C_{15}H_{12}O_2$	1214-47-7	224.255		90				
6166	2-Hydroxy-1-phenyl-1-propanone		$C_9H_{10}O_2$	5650-40-8	150.174	ye oil		251	1.1085^{18}	1.536^{23}	
6167	1-(2-Hydroxyphenyl)-1-propanone		$C_9H_{10}O_2$	610-99-1	150.174			150^{80}, 115^{15}		1.5501^{20}	sl H_2O; s EtOH, eth, ctc, alk
6168	1-(4-Hydroxyphenyl)-1-propanone	Paroxypropione	$C_9H_{10}O_2$	70-70-2	150.174	wh nd or pl (w)	149				sl H_2O, ace; s EtOH, eth, alk
6169	3-(4-Hydroxyphenyl)-2-propenoic acid	*p*-Coumaric acid	$C_9H_8O_3$	7400-08-0	164.158	nd	211.5				vs eth, EtOH
6170	3-Hydroxy-2-phenyl-4-quinolinecarboxylic acid	Oxycinchophen	$C_{16}H_{11}NO_3$	485-89-2	265.263	ye pr (al)	206 dec				vs bz, EtOH, HOAc
6171	*N*-Hydroxypiperidine	1-Piperidinol	$C_5H_{11}NO$	4801-58-5	101.147	hyg	39.3	110^{55}			
6172	3-Hydroxypregnan-20-one, (3α,5α)	Allopregnan-3α-ol-20-one	$C_{21}H_{34}O_2$	516-54-1	318.494	cry (al)	177				
6173	3-Hydroxypregnan-20-one, (3β,5α)	Allopregnan-3β-ol-20-one	$C_{21}H_{34}O_2$	516-55-2	318.494		189.5				
6174	17-Hydroxypregn-4-ene-3,20-dione	17α-Hydroxyprogesterone	$C_{21}H_{30}O_3$	68-96-2	330.461						sl chl
6175	21-Hydroxypregn-4-ene-3,20-dione	Deoxycorticosterone	$C_{21}H_{30}O_3$	64-85-7	330.461	pl (eth)	141.5				sl H_2O, eth; vs EtOH, ace; s chl
6176	21-Hydroxypregn-4-ene-3,11,20-trione	11-Dehydrocorticosterone	$C_{21}H_{28}O_4$	72-23-1	344.445	pr (ace-w, al, ace-eth)	183.5				i H_2O; s EtOH, ace, bz
6177	*cis*-4-Hydroxy-*L*-proline		$C_5H_9NO_3$	618-27-9	131.130	nd (w+1)	239.5				vs H_2O
6178	*trans*-4-Hydroxy-*L*-proline		$C_5H_9NO_3$	51-35-4	131.130	lf (dil al) pr (w)	274				vs H_2O; sl EtOH



7-Hydroxy-3*H*-phenoxazin-3-one



N-(2-Hydroxyphenyl)acetamide



N-(3-Hydroxyphenyl)acetamide



N-(4-Hydroxyphenyl)acetamide



2-[(4-Hydroxyphenyl)azo]benzoic acid



2-Hydroxy-*N*-phenylbenzamide



N-Hydroxy-*N*-phenylbenzamide



α-Hydroxy-α-phenylbenzeneacetic acid



3-Hydroxy-2-phenyl-4*H*-1-benzopyran-4-one



N-(4-Hydroxyphenyl)butanamide



4-(4-Hydroxyphenyl)-2-butanone



1-(2-Hydroxyphenyl)ethanone



1-(3-Hydroxyphenyl)ethanone



1-(4-Hydroxyphenyl)ethanone



4-Hydroxyphenyl-β-*D*-glucopyranoside



2-(4-Hydroxyphenyl)-*D*-glycine



N-(4-Hydroxyphenyl)glycine



2(2-Hydroxyphenyl)-2(4-hydroxyphenyl)propane



2-[[(2-Hydroxyphenyl)imino]methyl]phenol



N-Hydroxy-*N*-(phenylmethyl)benzenemethanamine



N-(4-Hydroxyphenyl)octadecanamide



3-(4-Hydroxyphenyl)-2-oxopropanoic acid



(2-Hydroxyphenyl)phenylmethanone



1-(2-Hydroxyphenyl)-3-phenyl-2-propen-1-one


2-Hydroxy-1-phenyl-1-propanone



1-(2-Hydroxyphenyl)-1-propanone



1-(4-Hydroxyphenyl)-1-propanone



3-(4-Hydroxyphenyl)-2-propenoic acid



3-Hydroxy-2-phenyl-4-quinolinecarboxylic acid



N-Hydroxypiperidine



3-Hydroxypregnan-20-one, (3α,5α)



3-Hydroxypregnan-20-one, (3β,5α)


17-Hydroxypregn-4-ene-3,20-dione



21-Hydroxypregn-4-ene-3,20-dione



21-Hydroxypregn-4-ene-3,11,20-trione


cis-4-Hydroxy-*L*-proline



trans-4-Hydroxy-*L*-proline


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6179	3-Hydroxypropanal	Hydracrolein	$C_3H_6O_2$	2134-29-4	74.079			90^{18}, $38^{0.2}$			vs ace, eth, EtOH
6180	Hydroxypropanedioic acid	Tartronic acid	$C_3H_4O_5$	80-69-3	120.061	pr (w+1)	157	sub			s H_2O, EtOH; sl eth
6181	2-Hydroxypropanenitrile	Acetaldehyde cyanohydrin	C_3H_5NO	78-97-7	71.078	liq	-40	183	0.9877^{20}	1.4058^{18}	msc H_2O, EtOH; s eth, chl; i CS_2, peth
6182	3-Hydroxypropanenitrile	Hydracrylonitrile	C_3H_5NO	109-78-4	71.078	liq	-46	221	1.0404^{25}	1.4248^{20}	msc H_2O, EtOH; sl eth; s chl; i CS_2
6183	3-Hydroxypropanoic acid	Hydracrylic acid	$C_3H_6O_3$	503-66-2	90.078	syr		dec		1.4489^{20}	vs H_2O; s EtOH; msc eth
6184	1-Hydroxy-2-propanone	Acetone alcohol	$C_3H_6O_2$	116-09-6	74.079	hyg liq	-17	145.5	1.0805^{20}	1.4295^{20}	vs H_2O, EtOH, eth
6185	4-(3-Hydroxy-1-propenyl)-2-methoxyphenol	Coniferyl alcohol	$C_{10}H_{12}O_3$	458-35-5	180.200	pr (eth-lig)	74	164^{3}			i H_2O; s EtOH, alk; vs eth
6186	2-Hydroxypropyl acrylate		$C_6H_{10}O_3$	999-61-1	130.141	liq		70^{2}			
6187	(2-Hydroxypropyl) trimethylammonium chloride		$C_6H_{16}ClNO$	2382-43-6	153.650	pr (Bu OH)	165	dec			vs H_2O, EtOH
6188	3-Hydroxy-1*H*-pyridin-2-one		$C_5H_5NO_2$	16867-04-2	111.100		245 dec				
6189	1-Hydroxy-2,5-pyrrolidinedione	*N*-Hydroxysuccinimide	$C_4H_5NO_3$	6066-82-6	115.088	hyg	96.3				sl DMSO
6190	4-Hydroxy-2-quinolinecarboxylic acid	Kynurenic acid	$C_{10}H_7NO_3$	492-27-3	189.168	ye nd (+w, dil al)	282.5				sl H_2O; s EtOH; i eth; vs alk
6191	8-Hydroxy-5-quinolinesulfonic acid		$C_9H_7NO_4S$	84-88-8	225.222	ye lf, nd (+ 1w) (dil HCl)	322.5				sl H_2O
6192	4-Hydroxy-2-quinolinone	2,4-Quinolinediol	$C_9H_7NO_2$	86-95-3	161.158		360 dec				sl EtOH, $PhNO_2$, gl HOAc
6193	3-Hydroxyspirostan-12-one, (3β,5α,25*R*)	Hecogenin	$C_{27}H_{42}O_4$	467-55-0	430.620	pl (eth)	266.5				vs ace, eth, EtOH
6194	4-Hydroxystyrene	4-Vinylphenol	C_8H_8O	2628-17-3	120.149		73.5				
6195	2-Hydroxy-5-sulfobenzoic acid	5-Sulfosalicylic acid	$C_7H_6O_6S$	97-05-2	218.184	hyg nd	120				vs H_2O; vs EtOH, eth
6196	2-Hydroxy-5-sulfobenzoic acid dihydrate	5-Sulfosalicylic acid dihydrate	$C_7H_{10}O_8S$	5965-83-3	254.214	wh cry (w)					vs H_2O; vs EtOH, eth
6197	4-Hydroxy-2,2,6,6-tetramethylpiperidine	2,2,6,6-Tetramethyl-4-piperidinol	$C_9H_{19}NO$	2403-88-5	157.253		130	213.5			
6198	5-Hydroxytryptamine	3-(2-Aminoethyl)indol-5-ol	$C_{10}H_{12}N_2O$	50-67-9	176.214						s H_2O
6199	5-Hydroxy-*DL*-tryptophan		$C_{11}H_{12}N_2O_3$	114-03-4	220.224	rod or nd (al)	300 dec				
6200	Hydroxyurea		$CH_4N_2O_2$	127-07-1	76.055	nd (al)	141	dec			vs H_2O
6201	Hydroxyzine		$C_{21}H_{27}ClN_2O_2$	68-88-2	374.904	oil		$220^{0.5}$			
6202	Hymecromone O,O-diethyl phosphorothioate		$C_{14}H_{17}O_5PS$	299-45-6	328.321	nd	38	$210^{1.0}$ dec	1.260^{38}	1.5685^{37}	vs H_2O; sl peth
6203	Hymenoxone		$C_{15}H_{22}O_5$	57377-32-9	282.333	cry					
6204	Hyoscyamine		$C_{17}H_{23}NO_3$	101-31-5	289.370	tetr nd (dil al)	108.5				sl H_2O, eth, bz; vs EtOH, chl
6205	Hypoglycin A		$C_7H_{11}NO_2$	156-56-9	141.168	ye pl (Me aq)	282				
6206	Hypoxanthine		$C_5H_4N_4O$	68-94-0	136.112	oct nd (w)	150 dec				sl H_2O; s alk, dil acid
6207	Ibuprofen	2-(4-Isobutylphenyl)propanoic acid	$C_{13}H_{18}O_2$	15687-27-1	206.281	col cry	76				sl H_2O; s os
6208	Icosylamine	1-Eicosanamine	$C_{20}H_{43}N$	10525-37-8	297.562			372.4			
6209	*D*-Idose		$C_6H_{12}O_6$	5978-95-0	180.155	syr					vs H_2O
6210	*L*-Idose		$C_6H_{12}O_6$	5934-56-5	180.155	syr					vs H_2O
6211	Imazalil		$C_{14}H_{14}Cl_2N_2O$	35554-44-0	297.179		50	dec	1.243^{23}		
6212	Imazapyr		$C_{13}H_{15}N_3O_3$	81334-34-1	261.276		171				
6213	Imazaquin		$C_{17}H_{17}N_3O_3$	81335-37-7	311.335		221				
6214	Imazethapyr		$C_{15}H_{19}N_3O_3$	81335-77-5	289.330		173				
6215	Imidazole	1,3-Diazole	$C_3H_4N_2$	288-32-4	68.077	mcl pr (bz)	89.5	257	1.0303^{101}	1.4801^{101}	vs H_2O, EtOH; s eth, ace, py; sl bz
6216	1*H*-Imidazole-4,5-dicarboxylic acid		$C_5H_4N_2O_4$	570-22-9	156.097	pr	290 dec		1.749^{25}		sl H_2O, py; i EtOH, eth, bz
6217	1*H*-Imidazole-4-ethanamine, dihydrochloride		$C_5H_{11}Cl_2N_3$	56-92-8	184.066	pl (eth-HOAc), pr (w)	251.3		1.43^{20}		vs H_2O, MeOH
6218	2,4-Imidazolidinedione	Hydantoin	$C_3H_4N_2O_2$	461-72-3	100.076	nd (MeOH), lf (w)	220				s H_2O, EtOH, alk; sl eth; i peth
6219	2-Imidazolidinethione	Ethylene thiourea	$C_3H_6N_2S$	96-45-7	102.158	nd (al), pr (al)	203				vs H_2O; s EtOH; i eth, bz, chl; sl DMSO
6220	Imidazolidinetrione	Parabanic acid	$C_3H_2N_2O_3$	120-89-8	114.059	mcl nd (w)	244 dec	sub 100			s H_2O; vs EtOH



3-Hydroxypropanal



Hydroxypropanedioic acid



2-Hydroxypropanenitrile



3-Hydroxypropanenitrile



3-Hydroxypropanoic acid



1-Hydroxy-2-propanone



4-(3-Hydroxy-1-propenyl)-2-methoxyphenol



2-Hydroxypropyl acrylate



(2-Hydroxypropyl)trimethylammonium chloride



3-Hydroxy-1*H*-pyridin-2-one



1-Hydroxy-2,5-pyrrolidinedione



4-Hydroxy-2-quinolinecarboxylic acid



8-Hydroxy-5-quinolinesulfonic acid



4-Hydroxy-2-quinolinone



3-Hydroxyspirostan-12-one, (3β,5α,25*R*)



4-Hydroxystyrene



2-Hydroxy-5-sulfobenzoic acid



2-Hydroxy-5-sulfobenzoic acid dihydrate



4-Hydroxy-2,2,6,6-tetramethylpiperidine



5-Hydroxytryptamine



5-Hydroxy-*DL*-tryptophan



Hydroxyurea



Hydroxyzine



Hymecromone O,O-diethyl phosphorothioate


Hymenoxone



Hyoscyamine



Hypoglycin A



Hypoxanthine



Ibuprofen


Icosylamine



D-Idose


L-Idose



Imazalil



Imazapyr



Imazaquin



Imazethapyr



Imidazole


1*H*-Imidazole-4,5-dicarboxylic acid



1*H*-Imidazole-4-ethanamine, dihydrochloride



2,4-Imidazolidinedione



2-Imidazolidinethione



Imidazolidinetrione


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6221	2-Imidazolidinone	Ethylene urea	$C_3H_6N_2O$	120-93-4	86.092		131				vs H_2O, EtOH; sl eth, chl
6222	Imidodicarbonic diamide	Biuret	$C_2H_5N_3O_2$	108-19-0	103.080	pl (al), nd (w+1)	190 dec				sl H_2O; vs EtOH; i eth
6223	3,3'-Iminobispropanenitrile	Bis(2-cyanoethyl)amine	$C_6H_9N_3$	111-94-4	123.155		-6	162^{5}	1.0165^{20}		
6224	Iminodiacetic acid		$C_4H_7NO_4$	142-73-4	133.104	orth pr	247.5				sl H_2O; i EtOH, eth
6225	Iminodiacetic acid, dinitrile	2,2'-Iminobisacetonitrile	$C_4H_5N_3$	628-87-5	95.103		78				s H_2O, EtOH; sl eth, bz, chl
6226	Imipramine		$C_{19}H_{24}N_2$	50-49-7	280.407			$160^{0.1}$			
6227	Imipramine hydrochloride	Tofranil	$C_{19}H_{25}ClN_2$	113-52-0	316.868		174.5				vs H_2O; s EtOH; sl ace
6228	Imperatorin		$C_{16}H_{14}O_4$	482-44-0	270.280	cry (al)	102				sl H_2O; s EtOH, eth, bz, peth; vs chl
6229	Indaconitine		$C_{34}H_{47}NO_{10}$	4491-19-4	629.738	cry	202 dec				vs eth, EtOH, chl
6230	Indalone	Butopyronoxyl	$C_{12}H_{18}O_4$	532-34-3	226.269	ye-red liq		263	1.057^{20}	1.475^{25}	i H_2O; vs EtOH, eth, chl
6231	Indan		C_9H_{10}	496-11-7	118.175	liq	-51.38	177.97	0.9639^{20}	1.5378^{20}	i H_2O; msc EtOH, eth; sl chl
6232	1-Indanamine	1-Aminoindane	$C_9H_{11}N$	34698-41-4	133.190			$221; 96^{8}$	1.038^{15}	1.5613^{20}	sl H_2O; s eth, ace, bz
6233	1*H*-Indazole	1*H*-Benzopyrazole	$C_7H_6N_2$	271-44-3	118.136	nd (al, w)	148	269			s H_2O, EtOH, eth
6234	1*H*-Indazol-3-ol	1,2-Dihydro-3*H*-indazol-3-one	$C_7H_6N_2O$	7364-25-2	134.135	nd or lf (MeOH) pl or nd (al)	252.5				sl H_2O, eth; s MeOH, EtOH
6235	Indene	Indonaphthene	C_9H_8	95-13-6	116.160	liq	-1.5	182	0.9960^{25}	1.5768^{20}	i H_2O; msc EtOH, eth; s ace, bz, py; sl chl
6236	1*H*-Indene-1,3(2*H*)-dione		$C_9H_6O_2$	606-23-5	146.143	nd (eth, lig)	131 dec		1.37^{21}		sl H_2O, ctc; vs EtOH; s eth, bz, alk
6237	1*H*-Indene-1,2,3-trione monohydrate	Ninhydrin	$C_9H_6O_4$	485-47-2	178.142	pa ye pr (w, al)	242 dec				vs H_2O; s EtOH, alk; sl eth
6238	Indeno[1,2,3-cd]pyrene	1,10-(1,2-Phenylene)pyrene	$C_{22}H_{12}$	193-39-5	276.330	ye cry (cy)	162				
6239	Indigo		$C_{16}H_{10}N_2O_2$	482-89-3	262.262	dk bl pow	390 dec	sub 300			
6240	5,5'-Indigodisulfonic acid, disodium salt	Indigo Carmine	$C_{16}H_8N_2Na_2O_8S_2$	860-22-0	466.353	dk-bl pow					sl H_2O, EtOH; i os
6241	Indocyanine green		$C_{43}H_{47}N_2NaO_6S_2$	3599-32-4	774.962	grn pow	244 dec				
6242	1*H*-Indol-5-amine		$C_8H_8N_2$	5192-03-0	132.163		132				
6243	1*H*-Indole	2,3-Benzopyrrole	C_8H_7N	120-72-9	117.149	lf (w, peth) cry (eth)	52.5	253.6	1.22^{25}		s H_2O, bz; vs EtOH, eth, tol; sl ctc
6244	1*H*-Indole-3-acetic acid	Indoleacetic acid	$C_{10}H_9NO_2$	87-51-4	175.184	lf (bz), pl (chl)	168.5				i H_2O; vs EtOH; s eth, ace, bz; sl chl
6245	1*H*-Indole-3-acetonitrile		$C_{10}H_8N_2$	771-51-7	156.184		36	$160^{0.2}$			
6246	1*H*-Indole-3-butanoic acid	Indolebutyric acid	$C_{12}H_{13}NO_2$	133-32-4	203.237		124.5				vs bz; s DMSO; i peth
6247	1*H*-Indole-3-carboxaldehyde		C_9H_7NO	487-89-8	145.158		197.8				
6248	1*H*-Indole-2,3-dione	Isatin	$C_8H_5NO_2$	91-56-5	147.132	oran mcl pr	203 dec				s H_2O, ace, bz; vs EtOH; sl eth
6249	1*H*-Indole-2,3-dione, 3-thiosemicarbazone	Isatin, 3-thiosemicarbazone	$C_9H_8N_4OS$	487-16-1	220.251		283				
6250	1*H*-Indole-3-ethanamine, monohydrochloride	Tryptamine hydrochloride	$C_{10}H_{13}ClN_2$	343-94-2	196.676	nd (al-bz or lig)	255				vs ace, EtOH
6251	1*H*-Indole-3-ethanol	Tryptophol	$C_{10}H_{11}NO$	526-55-6	161.200	pr (bz-peth)	59	174^{2}			vs ace, eth, EtOH, chl
6252	1*H*-Indole-3-lactic acid, (*S*)	α-Hydroxy-1*H*-indole-3-propanoic acid	$C_{11}H_{11}NO_3$	7417-65-4	205.210	cry (peth)	100				
6253	1*H*-Indole-3-propanoic acid		$C_{11}H_{11}NO_2$	830-96-6	189.211		134.5				sl H_2O, DMSO; vs EtOH, eth, ace, bz
6254	Indolizine		C_8H_7N	274-40-8	117.149	pl	75	205			i H_2O; s EtOH
6255	1*H*-Indol-3-ol, acetate		$C_{10}H_9NO_2$	608-08-2	175.184		129				
6256	1-(1*H*-Indol-3-yl)ethanone		$C_{10}H_9NO$	703-80-0	159.184	nd (bz)	192.3	144^{10}			vs EtOH
6257	1-(1*H*-Indol-3-yl)-2-propanone	3-Indolylacetone	$C_{11}H_{11}NO$	1201-26-9	173.211	br orth (bz), nd (aq MeOH)	116				
6258	3-(1*H*-Indol-3-yl)-2-propenoic acid	3-Indolylacrylic acid	$C_{11}H_9NO_2$	1204-06-4	187.195		185 dec				



2-Imidazolidinone



Imidodicarbonic diamide



3,3'-Iminobispropanenitrile



Iminodiacetic acid



Iminodiacetic acid, dinitrile


Imipramine



Imipramine hydrochloride



Imperatorin



Indaconitine


Indalone



Indan



1-Indanamine



1*H*-Indazole



1*H*-Indazol-3-ol



Indene



1*H*-Indene-1,3(2*H*)-dione



1*H*-Indene-1,2,3-trione monohydrate


Indeno[1,2,3-cd]pyrene



Indigo



5,5'-Indigodisulfonic acid, disodium salt



Indocyanine green



1*H*-Indol-5-amine



1*H*-Indole



1*H*-Indole-3-acetic acid



1*H*-Indole-3-acetonitrile



1*H*-Indole-3-butanoic acid



1*H*-Indole-3-carboxaldehyde



1*H*-Indole-2,3-dione


1*H*-Indole-2,3-dione, 3-thiosemicarbazone



1*H*-Indole-3-ethanamine, monohydrochloride



1*H*-Indole-3-ethanol



1*H*-Indole-3-lactic acid, (*S*)



1*H*-Indole-3-propanoic acid


Indolizine



1*H*-Indol-3-ol, acetate



1-(1*H*-Indol-3-yl)ethanone



1-(1*H*-Indol-3-yl)-2-propanone



3-(1*H*-Indol-3-yl)-2-propenoic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6259	Indomethacin		$C_{19}H_{16}ClNO_4$	53-86-1	357.788		155 (form a); 162 (form b				
6260	Inosine	Hypoxanthine riboside	$C_{10}H_{12}N_4O_5$	58-63-9	268.226	pl (w + 2), nd (80% al)	218 dec				sl H_2O; vs EtOH
6261	Inosine 5'-monophosphate	5'-Inosinic acid	$C_{10}H_{13}N_4O_8P$	131-99-7	348.206	visc liq or glass					vs H_2O; sl EtOH, eth
6262	*myo*-Inositol	(1α,2α,3α,4β,5α,6β)-Cyclohexanehexol	$C_6H_{12}O_6$	87-89-8	180.155	cry (w)	225		1.752		s H_2O
6263	Iocetamic acid		$C_{12}H_{13}I_3N_2O_3$	16034-77-8	613.955	wh-ye pow	225				i H_2O; sl EtOH, bz, eth, ace
6264	Iodipamide		$C_{20}H_{14}I_6N_2O_6$	606-17-7	1139.761		307 dec				i H_2O, bz; sl EtOH, eth, ace
6265	2-Iodoacetamide		C_2H_4INO	144-48-9	184.963		93.0				s H_2O; sl tfa
6266	Iodoacetic acid		$C_2H_3IO_2$	64-69-7	185.948		82.5	dec			s H_2O, EtOH, peth; sl eth, chl
6267	Iodoacetone		C_3H_5IO	3019-04-3	183.975			62[12]	2.17[15]		s EtOH
6268	Iodoacetonitrile		C_2H_2IN	624-75-9	166.948			185	2.307[25]	1.5744[20]	
6269	Iodoacetylene		C_2HI	14545-08-5	151.933			32			
6270	2-Iodoaniline		C_6H_6IN	615-43-0	219.023	nd (dil al)	60.5				sl H_2O; vs EtOH, eth, ace
6271	3-Iodoaniline		C_6H_6IN	626-01-7	219.023	lf	33	145[15]		1.6811[20]	i H_2O; s EtOH, chl
6272	4-Iodoaniline		C_6H_6IN	540-37-4	219.023	nd (w)	67.5				sl H_2O, peth; s EtOH, eth
6273	2-Iodobenzaldehyde		C_7H_5IO	26260-02-6	232.018		37	129[14]			sl H_2O; s ace
6274	4-Iodobenzaldehyde		C_7H_5IO	15164-44-0	232.018		77.5	265			sl H_2O; s EtOH, bz
6275	Iodobenzene		C_6H_5I	591-50-4	204.008	liq	-31.3	188.4	1.8308[20]	1.6200[20]	i H_2O; s EtOH; msc eth, ace, bz, ctc
6276	2-Iodobenzenemethanol		C_7H_7IO	5159-41-1	234.034		92	148[32]		1.6349[20]	
6277	4-Iodobenzenesulfonyl chloride	Pipsyl chloride	$C_6H_4ClIO_2S$	98-61-3	302.517		85				
6278	2-Iodobenzoic acid		$C_7H_5IO_2$	88-67-5	248.018	nd (w)	163	exp 233	2.25[25]		sl H_2O, ace; vs EtOH, eth
6279	3-Iodobenzoic acid		$C_7H_5IO_2$	618-51-9	248.018	mcl pr (ace)	188.3	sub			sl H_2O, eth; vs EtOH
6280	4-Iodobenzoic acid		$C_7H_5IO_2$	619-58-9	248.018	mcl pr (dil al) lf (sub)	270	sub	2.184[20]		i H_2O; sl EtOH; s eth, DMSO
6281	4-Iodobenzonitrile		C_7H_4IN	3058-39-7	229.018		127.5				
6282	2-Iodobenzoyl chloride		C_7H_4ClIO	609-67-6	266.463		38.3	159[27], 135[19]			
6283	4-Iodobenzoyl chloride		C_7H_4ClIO	1711-02-0	266.463		65.5	164[32]			
6284	2-Iodo-1,1'-biphenyl		$C_{12}H_9I$	2113-51-1	280.103			190[36], 169[17]	1.5511[25]	1.6620[20]	i H_2O; s EtOH, eth, bz, HOAc
6285	3-Iodo-1,1'-biphenyl		$C_{12}H_9I$	20442-79-9	280.103		26.5	188[16]	1.5967[25]		
6286	4-Iodo-1,1'-biphenyl		$C_{12}H_9I$	1591-31-7	280.103	nd (al, HOAc)	113.5	320; 183[11]			i H_2O; s EtOH, eth, bz, HOAc
6287	1-Iodobutane	Butyl iodide	C_4H_9I	542-69-8	184.018	liq	-103	130.5	1.6154[20]	1.5001[20]	i H_2O; msc EtOH, eth; vs chl
6288	2-Iodobutane, (±)	(±)-*sec*-Butyl iodide	C_4H_9I	52152-71-3	184.018	liq	-104.2	120.1	1.5920[20]	1.4991[20]	i H_2O; msc EtOH, eth; vs chl
6289	Iodocyclohexane	Cyclohexyl iodide	$C_6H_{11}I$	626-62-0	210.055			dec 180; 81[20]	1.6244[20]	1.5477[20]	i H_2O; s EtOH, eth, ace, bz
6290	Iodocyclopentane	Cyclopentyl iodide	C_5H_9I	1556-18-9	196.029			166.5	1.7096[20]	1.5447[20]	i H_2O; s eth, bz; sl ctc
6291	1-Iododecane		$C_{10}H_{21}I$	2050-77-3	268.178	liq	-16.3	263.7; 132[15]	1.2546[20]	1.4858[20]	i H_2O; s EtOH, eth, ctc
6292	1-Iodo-2,4-dimethylbenzene		C_8H_9I	4214-28-2	232.061			dec 231; 111[14]	1.6282[16]	1.6008[16]	i H_2O; s ace, bz
6293	2-Iodo-1,3-dimethylbenzene		C_8H_9I	608-28-6	232.061	oil	11.2	229.5	1.6158[20]	1.6035[20]	i H_2O; s ace, bz
6294	2-Iodo-1,4-dimethylbenzene		C_8H_9I	1122-42-5	232.061			dec 227	1.6168[17]	1.5992[17]	i H_2O; s ace, bz
6295	1-Iodo-2,2-dimethylpropane		$C_5H_{11}I$	15501-33-4	198.045			dec 128	1.4940[20]	1.4890[20]	i H_2O; s EtOH, eth
6296	1-Iodododecane	Lauryl iodide	$C_{12}H_{25}I$	4292-19-7	296.231		0.3	298.2	1.1999[20]	1.4840[20]	i H_2O; s EtOH, MeOH; msc eth, ace, ctc
6297	Iodoethane	Ethyl iodide	C_2H_5I	75-03-6	155.965	liq	-111.1	72.3	1.9357[20]	1.5133[20]	sl H_2O; msc EtOH; s eth, chl
6298	2-Iodoethanol		C_2H_5IO	624-76-0	171.964			dec 176	2.1967[20]	1.5713[20]	vs H_2O, eth, EtOH
6299	Iodoethene	Vinyl iodide	C_2H_3I	593-66-8	153.949			56	2.037[20]	1.5385[20]	vs eth, EtOH
6300	(2-Iodoethyl)benzene		C_8H_9I	17376-04-4	232.061	liq		122[13]	1.603	1.6010[20]	



Indomethacin



Inosine



Inosine 5'-monophosphate


myo-Inositol


Iocetamic acid


Iodipamide


2-Iodoacetamide



Iodoacetic acid



Iodoacetone



Iodoacetonitrile


Iodoacetylene


2-Iodoaniline



3-Iodoaniline



4-Iodoaniline



2-Iodobenzaldehyde



4-Iodobenzaldehyde



Iodobenzene



2-Iodobenzenemethanol



4-Iodobenzenesulfonyl chloride



2-Iodobenzoic acid



3-Iodobenzoic acid



4-Iodobenzoic acid



4-Iodobenzonitrile



2-Iodobenzoyl chloride


4-Iodobenzoyl chloride


2-Iodo-1,1'-biphenyl


3-Iodo-1,1'-biphenyl



4-Iodo-1,1'-biphenyl



1-Iodobutane


2-Iodobutane, (±)



Iodocyclohexane



Iodocyclopentane



1-Iododecane


1-Iodo-2,4-dimethylbenzene



2-Iodo-1,3-dimethylbenzene


2-Iodo-1,4-dimethylbenzene



1-Iodo-2,2-dimethylpropane


1-Iodododecane



Iodoethane



2-Iodoethanol



Iodoethene



(2-Iodoethyl)benzene

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6301	2-(1-Iodoethyl)-1,3-dioxolane-4-methanol	Iodinated glycerol	$C_6H_{11}IO_3$	5634-39-9	258.053	pale ye liq			1.797	1.547	s eth, chl, thf, AcOEt
6302	Iodofenphos		$C_8H_8Cl_2IO_3PS$	18181-70-9	412.997	wh cry	76				i H_2O; s ace, xyl; sl EtOH
6303	1-Iodoheptane		$C_7H_{15}I$	4282-40-0	226.098	liq	-48.2	204.0	1.3791^{20}	1.4904^{20}	i H_2O; s EtOH, eth, ace, chl; sl ctc
6304	3-Iodoheptane		$C_7H_{15}I$	31294-92-5	226.098			89^{30}	1.3676^{20}		
6305	1-Iodohexadecane		$C_{16}H_{33}I$	544-77-4	352.337	pa ye liq	24.7	357; 212^{15}	1.1213^{25}	1.4797^{20}	i H_2O; sl EtOH; s eth, ace; msc bz; vs chl
6306	1-Iodohexane	Hexyl iodide	$C_6H_{13}I$	638-45-9	212.071	liq	-74.2	181.3	1.4397^{20}	1.4928^{20}	i H_2O
6307	Iodomethane	Methyl iodide	CH_3I	74-88-4	141.939	liq	-66.4	42.43	2.2789^{20}	1.5308^{20}	sl H_2O; s ace, bz, chl; msc EtOH, eth
6308	1-Iodo-2-methoxybenzene	*o*-Iodoanisole	C_7H_7IO	529-28-2	234.034			241; 91^{2}	1.8^{20}		vs EtOH, eth, ace, bz, chl, lig
6309	1-Iodo-3-methoxybenzene	*m*-Iodoanisole	C_7H_7IO	766-85-8	234.034			244.5	1.9650^{20}		vs EtOH, eth
6310	1-Iodo-4-methoxybenzene	*p*-Iodoanisole	C_7H_7IO	696-62-8	234.034	lf (al), nd (MeOH)	53	238; 138^{25}			s EtOH, eth, chl
6311	1-Iodo-2-methylbenzene		C_7H_7I	615-37-2	218.035			211.5	1.713^{20}	1.6079^{20}	i H_2O; msc EtOH, eth
6312	1-Iodo-3-methylbenzene		C_7H_7I	625-95-6	218.035	liq	-27.2	213	1.705^{20}	1.6053^{20}	i H_2O; msc EtOH, eth
6313	(Iodomethyl)benzene		C_7H_7I	620-05-3	218.035	col or ye nd (MeOH)	24.5	93^{10}	1.7335^{25}	1.6334^{25}	vs bz, eth, EtOH
6314	1-Iodo-3-methylbutane	Isopentyl iodide	$C_5H_{11}I$	541-28-6	198.045			147	1.5118^{20}	1.4939^{20}	sl H_2O, ctc; msc EtOH, eth
6315	2-Iodo-2-methylbutane		$C_5H_{11}I$	594-38-7	198.045			124.5	1.4937^{20}	1.4981^{20}	i H_2O; msc EtOH, eth
6316	1-Iodo-2-methylpropane	Isobutyl iodide	C_4H_9I	513-38-2	184.018			121.1	1.6035^{20}	1.4959^{20}	
6317	2-Iodo-2-methylpropane	*tert*-Butyl iodide	C_4H_9I	558-17-8	184.018	liq	-38.2	100.1	1.571^{25}	1.4918^{20}	msc EtOH, eth
6318	Iodomethylsilane		CH_5ISi	18089-64-0	172.041	col liq	-109.5	71.8			
6319	1-Iodonaphthalene		$C_{10}H_7I$	90-14-2	254.067		2.1	302	1.7399^{20}	1.7026^{20}	i H_2O; msc EtOH, eth, bz, CS_2
6320	2-Iodonaphthalene		$C_{10}H_7I$	612-55-5	254.067	lf (dil al)	54.5	308	1.6319^{99}	1.6662^{99}	i H_2O; vs EtOH, eth, HOAc
6321	1-Iodo-2-nitrobenzene		$C_6H_4INO_2$	609-73-4	249.006	ye orth nd (al)	54	290; 162^{18}	1.9186^{75}		i H_2O; s EtOH, eth
6322	1-Iodo-3-nitrobenzene		$C_6H_4INO_2$	645-00-1	249.006	mcl pr	38.5	280	1.9477^{50}		i H_2O; s EtOH, eth
6323	1-Iodo-4-nitrobenzene		$C_6H_4INO_2$	636-98-6	249.006	ye nd (al)	174.7	288	1.8090^{155}		i H_2O; s EtOH, HOAc; sl DMSO
6324	1-Iodononane		$C_9H_{19}I$	4282-42-2	254.151	col liq	-20	245.0	1.2836^{25}	1.4848^{25}	
6325	1-Iodooctadecane		$C_{18}H_{37}I$	629-93-6	380.391	lf (lig), nd (ace, al-ace)	34.0	383	1.0994^{20}	1.4810^{20}	i H_2O; sl EtOH, eth
6326	1-Iodooctane		$C_8H_{17}I$	629-27-6	240.125	liq	-45.7	225.1	1.3298^{20}	1.4885^{20}	s EtOH, eth
6327	2-Iodooctane, (±)	2-Octyl iodide, (±)	$C_8H_{17}I$	36049-78-2	240.125			210; 95^{16}	1.3251^{20}	1.4896^{20}	i H_2O; s EtOH, eth, lig
6328	1-Iodopentane	Pentyl iodide	$C_5H_{11}I$	628-17-1	198.045	liq	-85.6	157.0	1.5161^{20}	1.4959^{20}	s chl
6329	3-Iodopentane		$C_5H_{11}I$	1809-05-8	198.045			145.5	1.5176^{20}	1.4974^{20}	vs ace, bz, eth
6330	2-Iodophenol		C_6H_5IO	533-58-4	220.007	nd	43	186^{160}, 91^{2}	1.8757^{80}		s H_2O; vs EtOH, eth, CS_2
6331	3-Iodophenol		C_6H_5IO	626-02-8	220.007	nd (lig)	118	186^{100}			sl H_2O; s EtOH, eth
6332	4-Iodophenol		C_6H_5IO	540-38-5	220.007	nd (w or sub)	93.5	139^{5} dec	1.8573^{112}		sl H_2O; vs EtOH, eth
6333	1-(3-Iodophenyl)ethanone	3-Iodoacetophenone	C_8H_7IO	14452-30-3	246.045			129^{8}, 117^{4}		1.622^{20}	s bz
6334	1-(4-Iodophenyl)ethanone	4-Iodoacetophenone	C_8H_7IO	13329-40-3	246.045		86	153^{18}			s EtOH, bz, CS_2, HOAc; sl lig, eth
6335	1-Iodopropane	Propyl iodide	C_3H_7I	107-08-4	169.992	liq	-101.3	102.5	1.7489^{20}	1.5058^{20}	sl H_2O, ctc; msc EtOH, eth
6336	2-Iodopropane	Isopropyl iodide	C_3H_7I	75-30-9	169.992	liq	-90	89.5	1.7042^{20}	1.5028^{20}	sl H_2O; msc EtOH, eth, bz, chl
6337	3-Iodopropanoic acid		$C_3H_5IO_2$	141-76-4	199.975	lf (w)	85				sl H_2O, chl; vs EtOH; s eth, ace
6338	3-Iodo-1-propanol		C_3H_7IO	627-32-7	185.991	visc oil		226; 115^{38}	1.9976^{20}	1.5585^{20}	
6339	3-Iodopropene	Allyl iodide	C_3H_5I	556-56-9	167.976	ye liq	-99.3	103	1.848^{12}	1.5540^{21}	i H_2O; s EtOH, eth, chl



2-(1-Iodoethyl)-1,3-dioxolane-4-methanol


Iodofenphos



1-Iodoheptane



3-Iodoheptane



1-Iodohexadecane


1-Iodohexane


Iodomethane



1-Iodo-2-methoxybenzene



1-Iodo-3-methoxybenzene


1-Iodo-4-methoxybenzene



1-Iodo-2-methylbenzene


1-Iodo-3-methylbenzene


(Iodomethyl)benzene



1-Iodo-3-methylbutane



2-Iodo-2-methylbutane



1-Iodo-2-methylpropane



2-Iodo-2-methylpropane



Iodomethylsilane



1-Iodonaphthalene



2-Iodonaphthalene



1-Iodo-2-nitrobenzene



1-Iodo-3-nitrobenzene


1-Iodo-4-nitrobenzene



1-Iodononane


1-Iodooctadecane



1-Iodooctane



2-Iodooctane, (±)


1-Iodopentane



3-Iodopentane


2-Iodophenol


3-Iodophenol



4-Iodophenol


1-(3-Iodophenyl)ethanone


1-(4-Iodophenyl)ethanone

1-Iodopropane


2-Iodopropane



3-Iodopropanoic acid


3-Iodo-1-propanol



3-Iodopropene

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6340	2-Iodopyridine		C_5H_4IN	5029-67-4	204.997			100^{15}, 93^{13}	1.928^{25}	1.6366^{20}	s EtOH, eth, ace, bz
6341	5-Iodo-2,4(1*H*,3*H*)-pyrimidinedione	5-Iodouracil	$C_4H_3IN_2O_2$	696-07-1	237.983		275 dec				
6342	1-Iodo-2,5-pyrrolidinedione	*N*-Iodosuccinimide	$C_4H_4INO_2$	516-12-1	224.985	cry (ace)	200.5		2.245^{25}		vs H_2O; s EtOH, ace; sl eth, DMSO
6343	Iodosylbenzene		C_6H_5IO	536-80-1	220.007	ye pow	210 exp				s H_2O, EtOH; i eth, ace, bz, peth
6344	2-Iodothiophene		C_4H_3IS	3437-95-4	210.036	liq	-40	181	2.0595^{25}	1.6465^{25}	vs EtOH, eth; sl chl
6345	4-Iodotoluene		C_7H_7I	624-31-7	218.035	lf (al)	36.5	211	1.678^{20}		i H_2O; s EtOH, eth, CS_2; sl chl
6346	*L*-3-Iodotyrosine		$C_9H_{10}INO_3$	70-78-0	307.084	cry (w)	205 dec				
6347	*trans*-α-Ionone, (±)		$C_{13}H_{20}O$	30685-95-1	192.297			146^{28}	0.9298^{21}	1.5041^{20}	vs ace, eth, EtOH
6348	*trans*-β-Ionone		$C_{13}H_{20}O$	79-77-6	192.297			124^{10}, $73^{0.1}$	0.945^{20}	1.5198^{20}	sl H_2O; msc EtOH, eth; s chl
6349	Iopanoic acid		$C_{11}H_{12}I_3NO_2$	96-83-3	570.932	wh solid	156				i H_2O; s dil alk, EtOH
6350	Iophendylate	Ethyl 10-(4-iodophenyl) undecanoate	$C_{19}H_{29}IO_2$	99-79-6	416.336	visc liq		197^{1}	1.25^{20}	1.525^{25}	sl H_2O; s EtOH, bz, chl
6351	Iopodic acid	Ipodate	$C_{12}H_{13}I_3N_2O_2$	5587-89-3	597.956	cry	168				i H_2O; vs EtOH, MeOH, chl, ace
6352	Iprodione		$C_{13}H_{13}Cl_2N_3O_3$	36734-19-7	330.166		136				
6353	Iridomyrmecin	Hexahydro-4,7-dimethylcyclopenta[c]pyran-3(1*H*)-one	$C_{10}H_{16}O_2$	485-43-8	168.233	pr	61	$106^{1.5}$		1.4607^{65}	sl H_2O; s eth
6354	α-Irone	4-(2,5,6,6-Tetramethyl-2-cyclohexen-1-yl)-3-buten-2-one	$C_{14}H_{22}O$	79-69-6	206.324			$90^{0.4}$	0.9362^{20}	1.5002^{20}	
6355	β-Irone	4-(2,5,6,6-Tetramethyl-1-cyclohexen-1-yl)-3-buten-2-one	$C_{14}H_{22}O$	79-70-9	206.324			125^{11}	0.9434^{21}	1.5162^{25}	sl H_2O; vs EtOH, eth, bz, chl
6356	Iron hydrocarbonyl	Hydrogen tetracarbonylferrate(II)	$C_4H_2FeO_4$	17440-90-3	169.902	col liq; unstab	-70	dec			s alk
6357	Iron nonacarbonyl	Diiron nonacarbonyl	$C_9Fe_2O_9$	15321-51-4	363.781	oran-ye cry	100 dec		2.85		
6358	Iron(III) NTA	Nitrilotriacetatoiron(III)	$C_6H_6FeNO_6$	16448-54-7	243.960	solid					s H_2O
6359	Iron pentacarbonyl		C_5FeO_5	13463-40-6	195.896	col to ye oily liq	-20	103	1.5^{20}	1.453^{22}	i H_2O; sl EtOH; s bz, ace, ctc
6360	Iron(III) 2,4-pentanedioate	Ferric acetylacetonate	$C_{15}H_{21}FeO_6$	14024-18-1	353.169		179		5.24		
6361	Isanic acid	17-Octadecene-9,11-diynoic acid	$C_{18}H_{26}O_2$	506-25-2	274.398	cry	39.5		0.9309^{45}	1.49148^{50}	s ace, EtOH, i-PrOH; sl peth
6362	Isatidine	Retrorsine *N*-oxide	$C_{18}H_{25}NO_7$	15503-86-3	367.395	cry	145				
6363	Isaxonine	*N*-Isopropyl-2-pyrimidineamine	$C_7H_{11}N_3$	4214-72-6	137.182		28	93^{12}			
6364	Isazophos		$C_9H_{17}ClN_3O_3PS$	67329-04-8	313.741			170; $100^{0.001}$	1.22^{20}		
6365	Isobenzan		$C_9H_4Cl_8O$	297-78-9	411.751	cry (hp)	121				s eth, bz, xyl, tol
6366	1(3*H*)-Isobenzofuranone		$C_8H_6O_2$	87-41-2	134.133	nd or pl (w)	75	290	1.1636^{99}	1.536^{99}	s H_2O; vs EtOH, eth; sl chl
6367	Isoborneol	1,7,7-Trimethylbicyclo[2.2.1] heptan-2-ol, *exo*-(±)	$C_{10}H_{18}O$	24393-70-2	154.249	tab (peth)	212	sub	1.10^{20}		i H_2O; vs EtOH, eth, chl; sl bz
6368	Isobornyl thiocyanoacetate		$C_{13}H_{19}NO_2S$	115-31-1	253.361	ye oily liq		$95^{0.06}$	1.1465^{25}	1.512^{25}	i H_2O; vs EtOH, bz, chl, peth
6369	6-Isobornyl-3,4-xylenol	Xibornol	$C_{18}H_{26}O$	13741-18-9	258.398	cry	95	167^{3}	1.0240^{20}	1.5382^{20}	
6370	Isobutanal	2-Methyl-1-propanal	C_4H_8O	78-84-2	72.106	liq	-65.9	64.5	0.7891^{20}	1.3730^{20}	s H_2O, eth, ace, chl; sl ctc
6371	Isobutane	2-Methylpropane	C_4H_{10}	75-28-5	58.122	col gas	-159.4	-11.73	0.5510^{25} (p>1 atm	1.3518^{-25}	sl H_2O; s EtOH, eth, chl
6372	Isobutene		C_4H_8	115-11-7	56.107	col gas	-140.7	-6.9	0.589^{25} (p>1 atm)	1.3926^{-25}	i H_2O; vs EtOH, eth; s bz, sulf
6373	Isobutyl acetate		$C_6H_{12}O_2$	110-19-0	116.158	liq	-98.8	116.5	0.8712^{20}	1.3902^{20}	sl H_2O, ctc; msc EtOH, eth; s ace
6374	Isobutyl acrylate		$C_7H_{12}O_2$	106-63-8	128.169	liq	-61	132	0.8896^{20}	1.4150^{20}	sl H_2O; s EtOH, eth, MeOH
6375	5-Isobutyl-3-allyl-2-thioxo-4-imidazolidinone	Albutoin	$C_{10}H_{16}N_2OS$	830-89-7	212.311		210.5				
6376	Isobutylamine	2-Methyl-1-propanamine	$C_4H_{11}N$	78-81-9	73.137	liq	-86.7	67.75	0.724^{25}	1.3988^{19}	
6377	Isobutyl 4-aminobenzoate	Isobutyl *p*-aminobenzoate	$C_{11}H_{15}NO_2$	94-14-4	193.243		64.5				



2-Iodopyridine



5-Iodo-2,4(1*H*,3*H*)-pyrimidinedione



1-Iodo-2,5-pyrrolidinedione



Iodosylbenzene



2-Iodothiophene



4-Iodotoluene



L-3-Iodotyrosine



trans-α-Ionone, (±)



trans-β-Ionone



Iopanoic acid



Iophendylate


Iopodic acid



Iprodione



Iridomyrmecin



α-Irone



β-Irone



$H_2Fe(CO)_4$
Iron hydrocarbonyl



Iron nonacarbonyl



Iron(III) NTA



Iron pentacarbonyl



Iron(III) 2,4-pentanedioate



Isanic acid



Isatidine



Isaxonine



Isazophos


Isobenzan


1(3*H*)-Isobenzofuranone


Isoborneol



Isobornyl thiocyanoacetate



6-Isobornyl-3,4-xylenol



Isobutanal



Isobutane



Isobutene


Isobutyl acetate



Isobutyl acrylate



5-Isobutyl-3-allyl-2-thioxo-4-imidazolidinone



Isobutylamine



Isobutyl 4-aminobenzoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6378	Isobutylbenzene		$C_{10}H_{14}$	538-93-2	134.218	liq	-51.4	172.79	0.8532^{20}	1.4866^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
6379	Isobutyl benzoate		$C_{11}H_{14}O_2$	120-50-3	178.228			242	0.9990^{20}		i H_2O; msc EtOH, eth; s ace, chl
6380	Isobutyl butanoate		$C_8H_{16}O_2$	539-90-2	144.212			156.9	0.8364^{18}	1.4032^{20}	sl H_2O; msc EtOH, eth
6381	Isobutyl carbamate		$C_5H_{11}NO_2$	543-28-2	117.147	lf	67	207		1.4098^{76}	vs eth, EtOH
6382	Isobutyl chlorocarbonate		$C_5H_9ClO_2$	543-27-1	136.577			128.8	1.0426^{18}	1.4071^{18}	s EtOH, bz, chl; msc eth
6383	Isobutyl 2-chloropropanoate		$C_7H_{13}ClO_2$	114489-96-2	164.630			176	1.0312^{20}	1.4247^{20}	
6384	Isobutyl 3-chloropropanoate		$C_7H_{13}ClO_2$	62108-68-3	164.630			191.3	1.0323^{20}	1.4295^{20}	vs eth, EtOH
6385	Isobutylcyclohexane		$C_{10}H_{20}$	1678-98-4	140.266	liq	-95	171.3	0.7952^{20}	1.4386^{20}	i H_2O; s EtOH, ace, chl; vs eth, bz
6386	Isobutylcyclopentane		C_9H_{18}	3788-32-7	126.239	liq	-115.2	148	0.7769^{25}	1.4298^{20}	
6387	Isobutyldimethylamine	*N,N*,2-Trimethyl-1-propanamine	$C_6H_{15}N$	7239-24-9	101.190			80.5	0.7097^{20}	1.3907^{20}	vs H_2O
6388	Isobutyl formate		$C_5H_{10}O_2$	542-55-2	102.132	liq	-95.8	98.2	0.8776^{20}	1.3857^{20}	sl H_2O, chl; msc EtOH, eth; vs ace
6389	Isobutyl heptanoate	Isobutyl enanthate	$C_{11}H_{22}O_2$	7779-80-8	186.292			208	0.8593^{20}		vs ace, bz, eth, EtOH
6390	Isobutyl 2-hydroxybenzoate	Isobutyl salicylate	$C_{11}H_{14}O_3$	87-19-4	194.227		5.9	261	1.0639^{20}	1.5087^{20}	i H_2O; s EtOH, eth, ctc
6391	Isobutyl isobutanoate		$C_8H_{16}O_2$	97-85-8	144.212	liq	-80.7	148.6	0.8542^{20}	1.3999^{20}	sl H_2O, ctc; s EtOH, ace; msc eth
6392	Isobutyl isocyanate		C_5H_9NO	1873-29-6	99.131			106			
6393	Isobutyl isothiocyanate	1-Isothiocyanato-2-methylpropane	C_5H_9NS	591-82-2	115.197			160	0.9631^{14}	1.5005^{14}	
6394	Isobutyl methacrylate		$C_8H_{14}O_2$	97-86-9	142.196			155	0.8858^{20}	1.4199^{20}	i H_2O; msc EtOH, eth
6395	Isobutyl 3-methylbutanoate	Isobutyl isovalerate	$C_9H_{18}O_2$	589-59-3	158.238			168.5	0.853^{20}	1.4057^{20}	i H_2O; msc EtOH, eth; vs ace; s chl
6396	Isobutyl methyl ether		$C_5H_{12}O$	625-44-5	88.148			58.6	0.7311^{20}		vs eth, EtOH
6397	Isobutyl nitrate		$C_4H_9NO_3$	543-29-3	119.119			123.4	1.0152^{20}	1.4028^{20}	
6398	Isobutyl nitrite		$C_4H_9NO_2$	542-56-3	103.120	col liq		67	0.8699^{22}	1.3715^{22}	sl H_2O; s EtOH, eth
6399	Isobutyl pentanoate		$C_9H_{18}O_2$	10588-10-0	158.238			179	0.8625^{25}	1.4046^{20}	i H_2O; msc EtOH; s eth, ace
6400	Isobutyl phenylacetate		$C_{12}H_{16}O_2$	102-13-6	192.254			247	0.999^{18}		i H_2O; s EtOH, eth
6401	Isobutyl propanoate	Isobutyl propionate	$C_7H_{14}O_2$	540-42-1	130.185	liq	-71.4	137	0.888^{0}	1.3973^{20}	sl H_2O; vs EtOH, eth; s ace, bz, chl, ctc
6402	Isobutyl stearate		$C_{22}H_{44}O_2$	646-13-9	340.583	wax	28.9	223^{15}	0.8498^{20}		vs eth
6403	Isobutyl thiocyanate		C_5H_9NS	591-84-4	115.197	liq	-59	175.4			vs eth, EtOH
6404	Isobutyl trichloroacetate		$C_6H_9Cl_3O_2$	33560-15-5	219.493			188	1.2636^{20}	1.4483^{20}	vs bz, eth, EtOH
6405	Isobutyl vinyl ether		$C_6H_{12}O$	109-53-5	100.158	liq	-112	83	0.7645^{20}	1.3966^{20}	sl H_2O; vs EtOH, ace, bz; msc eth
6406	Isocitric acid		$C_6H_8O_7$	320-77-4	192.124	ye syr	105				
6407	Isocorybulbine		$C_{21}H_{25}NO_4$	22672-74-8	355.429	lf (al)	187.5		1.045^{20}		i H_2O; s EtOH, chl, acid
6408	Isocorydine		$C_{20}H_{23}NO_4$	475-67-2	341.402	pl	185				vs chl
6409	2-Isocyanato-1,3-dimethylbenzene	2,6-Dimethylphenyl isocyanate	C_9H_9NO	28556-81-2	147.173	liq		100^{13}			
6410	1-Isocyanato-2-methoxybenzene		$C_8H_7NO_2$	700-87-8	149.148			94^{17}			
6411	1-Isocyanato-3-methoxybenzene		$C_8H_7NO_2$	18908-07-1	149.148			102^{15}			
6412	1-Isocyanato-2-methylbenzene	2-Tolyl isocyanate	C_8H_7NO	614-68-6	133.148			185		1.5282^{20}	i H_2O; s eth
6413	1-Isocyanato-3-methylbenzene	3-Tolyl isocyanate	C_8H_7NO	621-29-4	133.148			196.5	1.0330^{20}		vs bz, eth
6414	1-Isocyanato-4-methylbenzene	4-Tolyl isocyanate	C_8H_7NO	622-58-2	133.148			187			vs bz, eth
6415	2-Isocyanato-2-methylpropane	*tert*-Butyl isocyanate	C_5H_9NO	1609-86-5	99.131		85.5		0.8670^{7}	1.4061^{20}	
6416	1-Isocyanatonaphthalene	1-Naphthyl isocyanate	$C_{11}H_7NO$	86-84-0	169.180			269	1.1774^{20}		s eth, bz
6417	1-Isocyanato-2-nitrobenzene	2-Nitrophenyl isocyanate	$C_7H_4N_2O_3$	3320-86-3	164.118	wh nd (peth)	41	137^{18}			vs bz, eth, chl
6418	1-Isocyanato-3-nitrobenzene	3-Nitrophenyl isocyanate	$C_7H_4N_2O_3$	3320-87-4	164.118	wh lf (lig)	51	130^{11}			vs bz, eth, chl
6419	1-Isocyanato-4-nitrobenzene	4-Nitrophenyl isocyanate	$C_7H_4N_2O_3$	100-28-7	164.118	pa ye nd	57	162^{20}, 137^{11}			vs bz, eth, chl
6420	2-Isocyanatopropane	Isopropyl isocyanate	C_4H_7NO	1795-48-8	85.105			74.5	0.866^{25}	1.3825^{20}	
6421	1-Isocyanato-3-(trifluoromethyl) benzene	3-(Trifluoromethyl)phenyl isocyanate	$C_8H_4F_3NO$	329-01-1	187.119			54^{11}	1.3455^{20}	1.4690^{20}	
6422	Isocyanobenzene	Phenyl isocyanide	C_7H_5N	931-54-4	103.122	unstab liq		80^{40}	0.98^{15}		



Isobutylbenzene



Isobutyl benzoate



Isobutyl butanoate



Isobutyl carbamate



Isobutyl chlorocarbonate



Isobutyl 2-chloropropanoate



Isobutyl 3-chloropropanoate



Isobutylcyclohexane



Isobutylcyclopentane



Isobutyldimethylamine



Isobutyl formate



Isobutyl heptanoate



Isobutyl 2-hydroxybenzoate



Isobutyl isobutanoate



Isobutyl isocyanate



Isobutyl isothiocyanate



Isobutyl methacrylate



Isobutyl 3-methylbutanoate



Isobutyl methyl ether



Isobutyl nitrate



Isobutyl nitrite



Isobutyl pentanoate



Isobutyl phenylacetate



Isobutyl propanoate



Isobutyl stearate



Isobutyl thiocyanate



Isobutyl trichloroacetate



Isobutyl vinyl ether



Isocitric acid



Isocorybulbine



Isocorydine



2-Isocyanato-1,3-dimethylbenzene



1-Isocyanato-2-methoxybenzene



1-Isocyanato-3-methoxybenzene



1-Isocyanato-2-methylbenzene



1-Isocyanato-3-methylbenzene



1-Isocyanato-4-methylbenzene



2-Isocyanato-2-methylpropane



1-Isocyanatonaphthalene



1-Isocyanato-2-nitrobenzene


1-Isocyanato-3-nitrobenzene


1-Isocyanato-4-nitrobenzene



2-Isocyanatopropane


1-Isocyanato-3-(trifluoromethyl)benzene



Isocyanobenzene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6423	Isocyanomethane	Methyl isocyanide	C_2H_3N	593-75-9	41.052		-45	exp 59.6	0.756^{4}		
6424	(Isocyanomethyl)benzene	Benzyl isocyanide	C_8H_7N	10340-91-7	117.149			dec 199; 93^{55}	0.972^{15}	1.5193^{20}	
6425	2-Isocyanopropane	Isopropyl isocyanide	C_4H_7N	598-45-8	69.106			87	0.7596^{25}		i H_2O; msc EtOH, eth
6426	Isodecyl acrylate		$C_{13}H_{24}O_2$	1330-61-6	212.329		-100	158^{50}	0.885^{20}	1.4416^{20}	
6427	Isodecyl diphenyl phosphate		$C_{22}H_{31}O_4P$	29761-21-5	390.452			249^{10} dec			
6428	Isodecyl methacrylate		$C_{14}H_{26}O_2$	29964-84-9	226.355			126^{10}	0.876^{20}		
6429	8-Isoestrone		$C_{18}H_{22}O_2$	517-06-6	270.367	pr (MeOH)	254				vs eth, Diox
6430	Isoeugenol		$C_{10}H_{12}O_2$	97-54-1	164.201			266	1.080^{25}	1.5739^{19}	vs eth, EtOH
6431	Isofenphos		$C_{15}H_{24}NO_4PS$	25311-71-1	345.395		<-12	$120^{0.01}$	1.134^{20}		
6432	Isoflurophate		$C_6H_{14}FO_3P$	55-91-4	184.145			62^{9}	1.055^{25}	1.3830^{25}	sl H_2O, lig; s eth; vs oils
6433	1*H*-Isoindole-1,3(2*H*)-dione	Phthalimide	$C_8H_5NO_2$	85-41-6	147.132	nd (w), pr (HOAc) lf (sub)	238				vs bz
6434	Isolan		$C_{10}H_{17}N_3O_2$	119-38-0	211.261	col liq		$118^{2.5}$	1.07^{20}		msc H_2O; s EtOH, xyl
6435	*DL*-Isoleucine		$C_6H_{13}NO_2$	443-79-8	131.173		292 dec				
6436	*L*-Isoleucine	2-Amino-3-methylpentanoic acid	$C_6H_{13}NO_2$	73-32-5	131.173		284 dec				s H_2O; i EtOH
6437	Isolongifolene		$C_{15}H_{24}$	1135-66-6	204.352	liq		$82^{0.4}$			
6438	Isolysergic acid		$C_{16}H_{16}N_2O_2$	478-95-5	268.310	cry (w+2)	218 dec				sl H_2O, EtOH; s py
6439	α-Isomaltose	6-*O*-α-*D*-Glucopyranosyl-*D*-glucose	$C_{12}H_{22}O_{11}$	499-40-1	342.296		120				
6440	Isoniazid	4-Pyridinecarboxylic acid hydrazide	$C_6H_7N_3O$	54-85-3	137.139	cry (al)	171.4				vs H_2O, EtOH
6441	Isopentane	2-Methylbutane	C_5H_{12}	78-78-4	72.149	vol liq or gas	-159.77	27.88	0.6201^{20}	1.3537^{20}	i H_2O; msc EtOH, eth
6442	Isopentyl acetate		$C_7H_{14}O_2$	123-92-2	130.185	liq	-78.5	142.5	0.876^{15}	1.4000^{20}	sl H_2O; msc EtOH, eth; s ace, chl
6443	Isopentylbenzene		$C_{11}H_{16}$	2049-94-7	148.245			195	0.856^{20}	1.4867^{10}	i H_2O; s EtOH, eth; vs bz
6444	Isopentyl butanoate		$C_9H_{18}O_2$	106-27-4	158.238			179	0.865^{19}	1.4110^{20}	i H_2O; vs EtOH, eth
6445	Isopentyl formate		$C_6H_{12}O_2$	110-45-2	116.158	liq	-93.5	123.5	0.877^{20}	1.3967^{20}	sl H_2O, ctc; s EtOH; msc eth
6446	Isopentyl hexanoate	Isopentyl caproate	$C_{11}H_{22}O_2$	2198-61-0	186.292			225.5	0.861^{20}		i H_2O; s EtOH, eth
6447	Isopentyl α-hydroxybenzeneacetate	Isopentyl mandelate	$C_{13}H_{18}O_3$	5421-04-5	222.280	oily liq		172^{11}			
6448	Isopentyl isopentanoate	Isoamyl isovalerate	$C_{10}H_{20}O_2$	659-70-1	172.265			190.4	0.8583^{19}	1.4130^{19}	
6449	Isopentyl lactate		$C_8H_{16}O_3$	19329-89-6	160.211			202.4	0.9589^{25}	1.4240^{25}	vs eth, EtOH
6450	Isopentyl 2-methylpropanoate	Isopentyl isobutyrate	$C_9H_{18}O_2$	2050-01-3	158.238			168.5	0.8627^{20}		sl H_2O; s EtOH, eth, ace
6451	Isopentyl nitrite	Isoamyl nitrite	$C_5H_{11}NO_2$	110-46-3	117.147			99.2	0.8828^{20}	1.3918^{20}	sl H_2O; msc EtOH, eth
6452	Isopentyl pentanoate		$C_{10}H_{20}O_2$	2050-09-1	172.265			193			
6453	Isopentyl propanoate		$C_8H_{16}O_2$	105-68-0	144.212			160.2	0.8697^{20}	1.4069^{20}	vs eth, EtOH
6454	Isopentyl salicylate		$C_{12}H_{16}O_3$	87-20-7	208.253			$278; 151^{15}$	1.0535^{20}	1.5080^{20}	i H_2O; vs EtOH; s eth, chl; sl ctc
6455	Isopentyl trichloroacetate		$C_7H_{11}Cl_3O_2$	57392-55-9	233.520			217	1.2314^{20}	1.4521^{20}	vs eth, EtOH
6456	Isophorone	3,5,5-Trimethyl-2-cyclohexen-1-one	$C_9H_{14}O$	78-59-1	138.206	liq	-8.1	215.2	0.9255^{20}	1.4766^{18}	
6457	Isophorone diisocyanate		$C_{12}H_{18}N_2O_2$	4098-71-9	222.283		60	217^{100}	1.062^{20}		
6458	Isophthalic acid	1,3-Benzenedicarboxylic acid	$C_8H_6O_4$	121-91-5	166.132	nd (w, al)	347	sub			sl H_2O; s EtOH, HOAc; i eth, bz, lig
6459	Isopilosine		$C_{16}H_{18}N_2O_3$	491-88-3	286.325	pl (al), pr (w, dil al)	187				vs EtOH
6460	Isopropalin	Benzenamine, 4-(1-methylethyl) -2,6-dinitro-*N*,*N*-dipropyl-	$C_{15}H_{23}N_3O_4$	33820-53-0	309.362	red-oran liq					i H_2O; s os
6461	Isopropamide iodide		$C_{23}H_{33}IN_2O$	71-81-8	480.424	cry or pow	190				s H_2O, EtOH, MeOH; i chl
6462	Isopropenyl acetate		$C_5H_8O_2$	108-22-5	100.117	liq	-92.9	94	0.9090^{20}	1.4033^{20}	sl H_2O; s EtOH, chl, ace; vs eth
6463	Isopropenylbenzene	α-Methyl styrene	C_9H_{10}	98-83-9	118.175	liq	-23.2	165.4	0.9106^{20}	1.5386^{20}	i H_2O; s EtOH, eth; msc ace, bz, ctc
6464	*p*-Isopropenylisopropylbenzene		$C_{12}H_{16}$	2388-14-9	160.255	liq	-30.6	220.8	0.8936^{20}	1.5238^{20}	vs ace, bz, eth, EtOH
6465	*p*-Isopropenylstyrene		$C_{11}H_{12}$	16262-48-9	144.213	liq		242	0.93	1.5684^{20}	



Isocyanomethane



(Isocyanomethyl)benzene



2-Isocyanopropane



Isodecyl acrylate



Isodecyl diphenyl phosphate



Isodecyl methacrylate



8-Isoestrone



Isoeugenol



Isofenphos



Isoflurophate



1*H*-Isoindole-1,3(2*H*)-dione



Isolan



DL-Isoleucine


L-Isoleucine



Isolongifolene



Isolysergic acid



α-Isomaltose



Isoniazid



Isopentane



Isopentyl acetate



Isopentylbenzene



Isopentyl butanoate



Isopentyl formate



Isopentyl hexanoate



Isopentyl α-hydroxybenzeneacetate



Isopentyl isopentanoate



Isopentyl lactate



Isopentyl 2-methylpropanoate



Isopentyl nitrite



Isopentyl pentanoate



Isopentyl propanoate



Isopentyl salicylate



Isopentyl trichloroacetate



Isophorone



Isophorone diisocyanate



Isophthalic acid



Isopilosine



Isopropalin


Isopropamide iodide



Isopropenyl acetate



Isopropenylbenzene



p-Isopropenylisopropylbenzene



p-Isopropenylstyrene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6466	4-Isopropoxydiphenylamine	4-Isopropoxy-*N*-phenylaniline	$C_{15}H_{17}NO$	101-73-5	227.302		83				
6467	2-Isopropoxyethanol		$C_5H_{12}O_2$	109-59-1	104.148			145	0.9030^{20}	1.4095^{20}	msc H_2O, EtOH, eth; s ace
6468	3-Isopropoxypropanenitrile	1-Cyano-2-isopropoxyethane	$C_6H_{11}NO$	110-47-4	113.157			65^{10}			s chl
6469	Isopropyl acetate		$C_5H_{10}O_2$	108-21-4	102.132	liq	-73.4	88.6	0.8718^{20}	1.3773^{20}	s H_2O, EtOH, ace, chl; msc eth
6470	Isopropyl acrylate	Isopropyl 2-propenoate	$C_6H_{10}O_2$	689-12-3	114.142	liq		51^{103}			
6471	Isopropylamine	2-Propanamine	C_3H_9N	75-31-0	59.110	liq	-95.13	31.76	0.6891^{20}	1.3742^{20}	msc H_2O, EtOH, eth; vs ace; s bz, chl
6472	Isopropylamine hydrochloride	2-Propanamine hydrochloride	$C_3H_{10}ClN$	15572-56-2	95.571		164				s DMSO
6473	2-(Isopropylamino)ethanol		$C_5H_{13}NO$	109-56-8	103.163		128.5	173	0.8970^{20}	1.4395^{20}	msc H_2O, EtOH, eth
6474	2-Isopropylaniline		$C_9H_{13}N$	643-28-7	135.206			$221; 95^{13}$	0.9760^{12}		i H_2O; s eth, bz, ctc
6475	4-Isopropylaniline	Cumidine	$C_9H_{13}N$	99-88-7	135.206			225	0.953^{20}		
6476	*N*-Isopropylaniline		$C_9H_{13}N$	768-52-5	135.206			203	0.9526^{25}	1.5380^{20}	s EtOH, eth, ace, bz
6477	4-Isopropylbenzaldehyde	Cuminaldehyde	$C_{10}H_{12}O$	122-03-2	148.201			235.5	0.9755^{20}	1.5301^{20}	i H_2O; s EtOH, eth; sl ctc
6478	Isopropylbenzene	Cumene	C_9H_{12}	98-82-8	120.191	liq	-96.02	152.41	0.8640^{25}	1.4915^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
6479	Isopropylbenzene hydroperoxide	Cumene hydroperoxide	$C_9H_{12}O_2$	80-15-9	152.190	liq		$153; 84^{8}$	1.03^{20}		
6480	4-Isopropylbenzenemethanol	Cumic alcohol	$C_{10}H_{14}O$	536-60-7	150.217		28	249	0.9818^{20}	1.5210^{20}	i H_2O; msc EtOH, eth; vs bz
6481	α-Isopropylbenzenemethanol	1-Phenyl-2-methylpropyl alcohol	$C_{10}H_{14}O$	611-69-8	150.217			223	0.9869^{14}	1.5193^{14}	i H_2O; s EtOH, ace
6482	Isopropyl benzoate		$C_{10}H_{12}O_2$	939-48-0	164.201			216	1.0163^{15}	1.4890^{20}	i H_2O; s EtOH, eth, ace
6483	4-Isopropylbenzoic acid	Cumic acid	$C_{10}H_{12}O_2$	536-66-3	164.201	tcl pl (al)	117.5	sub	1.162^{4}		sl H_2O; vs EtOH, eth; s peth
6484	Isopropyl butanoate		$C_7H_{14}O_2$	638-11-9	130.185			130.5	0.8588^{20}	1.3936^{20}	i H_2O; s EtOH
6485	Isopropyl carbamate		$C_4H_9NO_2$	1746-77-6	103.120	nd	93	183	0.9951^{66}		
6486	Isopropyl chloroacetate		$C_5H_9ClO_2$	105-48-6	136.577			150.5	1.0888^{20}	1.4382^{20}	vs eth
6487	Isopropyl chloroformate		$C_4H_7ClO_2$	108-23-6	122.551			105		1.4013^{20}	vs eth
6488	Isopropyl 2-chloropropanoate		$C_6H_{11}ClO_2$	40058-87-5	150.603			151.5	1.0315^{20}	1.4149^{20}	i H_2O; s EtOH, eth
6489	Isopropylcyclohexane		C_9H_{18}	696-29-7	126.239	liq	-89.4	154.8	0.8023^{20}	1.4410^{20}	i H_2O; vs EtOH, eth; msc ace, bz
6490	4-Isopropylcyclohexanone		$C_9H_{16}O$	5432-85-9	140.222			$214; 139^{100}$	0.9099^{30}	1.4552^{25}	
6491	Isopropylcyclopentane		C_8H_{16}	3875-51-2	112.213	liq	-111.4	126.5	0.7765^{20}	1.4258^{20}	i H_2O; msc EtOH, ace, ctc; s eth, bz
6492	Isopropylcyclopropane		C_6H_{12}	3638-35-5	84.159	liq	-112.9	58.3	0.6936^{25}	1.3865^{20}	
6493	Isopropyl (2,4-dichlorophenoxy) acetate		$C_{11}H_{12}Cl_2O_3$	94-11-1	263.117		5	140^{1}	1.26^{25}	1.5209^{25}	
6494	*N*-Isopropyl-4,4-diphenylcyclohexanamine	Pramiverin	$C_{21}H_{27}N$	14334-40-8	293.446		70	$165^{0.05}$			
6495	Isopropyl dodecanoate	Isopropyl laurate	$C_{15}H_{30}O_2$	10233-13-3	242.398			$196^{60}, 105^{0.8}$	0.8536^{20}	1.4280^{25}	vs eth, EtOH
6496	Isopropyl formate		$C_4H_8O_2$	625-55-8	88.106			68.2	0.8728^{20}	1.3678^{20}	sl H_2O; msc EtOH, eth; vs ace; s chl
6497	Isopropyl 2-furancarboxylate	Isopropyl 2-furanoate	$C_8H_{10}O_3$	6270-34-4	154.163			198.5	1.0655^{24}	1.4682^{24}	i H_2O; s EtOH, eth, ace, bz
6498	Isopropyl glycidyl ether	(1-Methylethoxy)methyloxirane	$C_6H_{12}O_2$	4016-14-2	116.158			137	0.9186^{20}		s H_2O, ace, EtOH
6499	4-Isopropylheptane		$C_{10}H_{22}$	52896-87-4	142.282			158.9	0.7354^{25}	1.4153^{20}	
6500	Isopropylhydrazine		$C_3H_{10}N_2$	2257-52-5	74.124	liq		107			s H_2O, bz, EtOH; sl eth
6501	Isopropyl 2-hydroxybenzoate	Isopropyl salicylate	$C_{10}H_{12}O_3$	607-85-2	180.200			238	1.0729^{20}	1.5065^{20}	i H_2O; msc EtOH, eth
6502	Isopropyl isobutanoate	Isopropyl isobutyrate	$C_7H_{14}O_2$	617-50-5	130.185			120.7	0.8471^{21}		i H_2O; s EtOH, eth, ace
6503	Isopropyl lactate		$C_6H_{12}O_3$	617-51-6	132.157			167	0.9980^{20}	1.4082^{25}	vs H_2O, bz, eth, EtOH
6504	Isopropyl methacrylate	Isopropyl 2-methyl-2-propenoate	$C_7H_{12}O_2$	4655-34-9	128.169			125	0.8847^{20}	1.4122^{20}	vs ace, bz, eth, EtOH
6505	Isopropyl methanesulfonate		$C_4H_{10}O_3S$	926-06-7	138.185			82^{6}			
6506	Isopropylmethylamine	Methylisopropylamine	$C_4H_{11}N$	4747-21-1	73.137			50.4			


4-Isopropoxydiphenylamine



2-Isopropoxyethanol



3-Isopropoxypropanenitrile



Isopropyl acetate



Isopropyl acrylate



Isopropylamine



Isopropylamine hydrochloride



2-(Isopropylamino)ethanol



2-Isopropylaniline



4-Isopropylaniline



N-Isopropylaniline



4-Isopropylbenzaldehyde



Isopropylbenzene



Isopropylbenzene hydroperoxide



4-Isopropylbenzenemethanol



α-Isopropylbenzenemethanol



Isopropyl benzoate



4-Isopropylbenzoic acid



Isopropyl butanoate



Isopropyl carbamate


Isopropyl chloroacetate


Isopropyl chloroformate



Isopropyl 2-chloropropanoate



Isopropylcyclohexane



4-Isopropylcyclohexanone



Isopropylcyclopentane



Isopropylcyclopropane



Isopropyl (2,4-dichlorophenoxy)acetate



N-Isopropyl-4,4-diphenylcyclohexanamine


Isopropyl dodecanoate



Isopropyl formate



Isopropyl 2-furancarboxylate



Isopropyl glycidyl ether



4-Isopropylheptane



Isopropylhydrazine



Isopropyl 2-hydroxybenzoate


Isopropyl isobutanoate



Isopropyl lactate



Isopropyl methacrylate



Isopropyl methanesulfonate



Isopropylmethylamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6507	1-Isopropyl-2-methylbenzene	*o*-Cymene	$C_{10}H_{14}$	527-84-4	134.218	liq	-71.5	178.1	0.8766^{20}	1.5006^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
6508	1-Isopropyl-3-methylbenzene	*m*-Cymene	$C_{10}H_{14}$	535-77-3	134.218	liq	-63.7	175.1	0.8610^{20}	1.4930^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
6509	1-Isopropyl-4-methylbenzene	*p*-Cymene	$C_{10}H_{14}$	99-87-6	134.218	liq	-67.94	177.1	0.8573^{20}	1.4909^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
6510	Isopropyl 3-methylbutanoate		$C_8H_{16}O_2$	32665-23-9	144.212			142; 70^{55}	0.8538^{17}	1.3960^{20}	vs ace, eth, EtOH
6511	5-Isopropyl-2-methyl-1,3-cyclohexadiene, (*R*)		$C_{10}H_{16}$	4221-98-1	136.234			173	0.8421^{20}	1.4772^{19}	
6512	5-Isopropyl-3-methyl-2-cyclohexen-1-one, (±)	Homocamfin	$C_{10}H_{16}O$	535-86-4	152.233	pa ye		244; 121^{15}	0.9340^{21}	1.4865^{21}	vs ace, EtOH
6513	6-Isopropyl-3-methyl-2-cyclohexen-1-one, (±)	(±)-Piperitone	$C_{10}H_{16}O$	6091-52-7	152.233	liq	-19	232.5	0.9331^{20}	1.4845^{20}	vs ace, EtOH
6514	Isopropyl methyl ether	2-Methoxypropane	$C_4H_{10}O$	598-53-8	74.121			30.77	0.7237^{15}	1.3576^{20}	sl H_2O; msc EtOH, eth
6515	5-Isopropyl-2-methylphenol	Carvacrol	$C_{10}H_{14}O$	499-75-2	150.217	nd	1	237.7	0.9772^{20}	1.5230^{20}	sl H_2O; s EtOH, eth, ctc; vs ace
6516	2-Isopropyl-6-methyl-4-pyrimidinol		$C_8H_{12}N_2O$	2814-20-2	152.193	cry	173				
6517	Isopropyl methyl sulfide		$C_4H_{10}S$	1551-21-9	90.187	liq	-101.5	84.8	0.8291^{20}	1.4932^{20}	s EtOH, eth, ace
6518	1-Isopropylnaphthalene		$C_{13}H_{14}$	6158-45-8	170.250	liq	-16	268	0.9956^{20}	1.5952^{20}	
6519	2-Isopropylnaphthalene		$C_{13}H_{14}$	2027-17-0	170.250		14.5	268.2	0.9753^{20}	1.5848^{20}	i H_2O; vs EtOH, eth; s bz
6520	Isopropyl nitrate		$C_3H_7NO_3$	1712-64-7	105.093			100	1.034^{19}	1.3912^{16}	s EtOH, eth
6521	Isopropyl nitrite		$C_3H_7NO_2$	541-42-4	89.094	pa ye oil		40	0.8684^{15}		i H_2O; s EtOH, eth
6522	1-Isopropyl-4-nitrobenzene		$C_9H_{11}NO_2$	1817-47-6	165.189	pa ye oil		122^{9}	1.084^{20}	1.5367^{20}	i H_2O; s ace, bz, lig
6523	*N*-Isopropyl-*N*-nitroso-2-propanamine		$C_6H_{14}N_2O$	601-77-4	130.187	cry (eth,w)	48	194.5	0.9422^{20}		sl H_2O; s EtOH, eth, bz
6524	Isopropyl 3-oxobutanoate	Isopropyl acetoacetate	$C_7H_{12}O_3$	542-08-5	144.168	liq	-27.3	186	0.9835^{20}	1.4173^{20}	vs eth, EtOH, lig
6525	Isopropyl palmitate	Isopropyl hexadecanoate	$C_{19}H_{38}O_2$	142-91-6	298.504		13.5	160^{2}	0.8404^{38}	1.4364^{25}	vs ace, bz, eth, EtOH
6526	Isopropyl pentanoate		$C_8H_{16}O_2$	18362-97-5	144.212				0.8579^{20}	1.4061^{20}	i H_2O; s EtOH, eth, ace
6527	2-Isopropylphenol		$C_9H_{12}O$	88-69-7	136.190		15.5	213.5	1.012^{20}	1.5315^{20}	sl H_2O; s EtOH, eth, bz, ctc
6528	3-Isopropylphenol		$C_9H_{12}O$	618-45-1	136.190		26	228		1.5261^{20}	vs eth
6529	4-Isopropylphenol		$C_9H_{12}O$	99-89-8	136.190	nd (peth)	62.3	230; 110^{10}	0.990^{20}	1.5228^{20}	sl H_2O; s EtOH, chl
6530	*N*-Isopropyl-*N*'-phenyl-1,4-benzenediamine		$C_{15}H_{18}N_2$	101-72-4	226.317		72.5	148^{2}			
6531	Isopropyl phenylcarbamate	Propham	$C_{10}H_{13}NO_2$	122-42-9	179.216	wh nd (al)	90		1.09^{20}	1.4989^{91}	vs bz, EtOH
6532	1-(4-Isopropylphenyl)ethanone		$C_{11}H_{14}O$	645-13-6	162.228			254	0.9753^{15}	1.5235^{20}	
6533	Isopropyl propanoate		$C_6H_{12}O_2$	637-78-5	116.158			109.5	0.8660^{20}	1.3872^{20}	sl H_2O; msc EtOH, eth
6534	*N*-Isopropyl-2-propenamide		$C_6H_{11}NO$	2210-25-5	113.157		64.5	110^{15}			
6535	Isopropylpropylamine	*N*-Propyl-2-propanamine	$C_6H_{15}N$	21968-17-2	101.190			96.9			
6536	Isopropyl propyl sulfide		$C_6H_{14}S$	5008-73-1	118.240			132.1	0.8269^{20}		
6537	4-Isopropylpyridine		$C_8H_{11}N$	696-30-0	121.180	liq	-54.9	178	0.9382^{25}	1.4962^{20}	sl H_2O; msc EtOH, eth; vs ace
6538	Isopropyl 3-pyridinecarboxylate	Isopropyl nicotinate	$C_9H_{11}NO_2$	553-60-6	165.189			126^{30}, 92.5^{5}	1.0624^{20}	1.4926^{20}	
6539	Isopropyl silicate	Tetra(isopropoxy)silane	$C_{12}H_{28}O_4Si$	1992-48-9	264.434			184	0.8770^{20}		s ctc, CS_2
6540	Isopropyl stearate		$C_{21}H_{42}O_2$	112-10-7	326.557		28	207^{6}	0.8403^{38}		vs ace, eth, EtOH, chl
6541	4-Isopropylstyrene		$C_{11}H_{14}$	2055-40-5	146.229	liq	-44.7	204.1	0.8850^{20}	1.5289^{20}	vs ace, bz, eth, EtOH
6542	Isopropyl tetradecanoate	Isopropyl myristate	$C_{17}H_{34}O_2$	110-27-0	270.451			193^{20}, 140^{2}	0.8532^{20}	1.4325^{25}	i H_2O; s EtOH, eth, chl; vs ace, bz
6543	(Isopropylthio)benzene		$C_9H_{12}S$	3019-20-3	152.256			208	0.9852^{20}	1.5464^{20}	
6544	Isopropyl trichloroacetate		$C_5H_7Cl_3O_2$	3974-99-0	205.468			175; 66^{15}	1.2911^{25}	1.4428^{20}	vs bz, eth, EtOH
6545	Isopropylurea		$C_4H_{10}N_2O$	691-60-1	102.134	nd		$103^{0.1}$			s H_2O, EtOH, chl, ace; sl eth
6546	Isopropyl vinyl ether	2-(Ethenyloxy)propane	$C_5H_{10}O$	926-65-8	86.132	liq	-140	55.5	0.7534^{20}	1.3840^{20}	vs ace, bz, eth, EtOH
6547	Isoproterenol	4-[1-Hydroxy-2-[isopropylamino]ethyl]-1,2-benzenediol	$C_{11}H_{17}NO_3$	7683-59-2	211.258		170.5				



1-Isopropyl-2-methylbenzene



1-Isopropyl-3-methylbenzene


1-Isopropyl-4-methylbenzene



Isopropyl 3-methylbutanoate



5-Isopropyl-2-methyl-1,3-cyclohexadiene, (*R*)


5-Isopropyl-3-methyl-2-cyclohexen-1-one, (±)



6-Isopropyl-3-methyl-2-cyclohexen-1-one, (±)



Isopropyl methyl ether



5-Isopropyl-2-methylphenol



2-Isopropyl-6-methyl-4-pyrimidinol



Isopropyl methyl sulfide



1-Isopropylnaphthalene



2-Isopropylnaphthalene



Isopropyl nitrate



Isopropyl nitrite



1-Isopropyl-4-nitrobenzene



N-Isopropyl-*N*-nitroso-2-propanamine



Isopropyl 3-oxobutanoate



Isopropyl palmitate



Isopropyl pentanoate



2-Isopropylphenol



3-Isopropylphenol



4-Isopropylphenol



N-Isopropyl-*N*′-phenyl-1,4-benzenediamine



Isopropyl phenylcarbamate



1-(4-Isopropylphenyl)ethanone



Isopropyl propanoate



N-Isopropyl-2-propenamide



Isopropylpropylamine



Isopropyl propyl sulfide



4-Isopropylpyridine



Isopropyl 3-pyridinecarboxylate



Isopropyl silicate



Isopropyl stearate



4-Isopropylstyrene



Isopropyl tetradecanoate


(Isopropylthio)benzene



Isopropyl trichloroacetate



Isopropylurea



Isopropyl vinyl ether



Isoproterenol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6548	Isopsoralen		$C_{11}H_6O_3$	523-50-2	186.164		139				
6549	1-Isoquinolinamine		$C_9H_8N_2$	1532-84-9	144.173	pl(w)	123	164^{8}			sl H_2O, eth; vs EtOH
6550	3-Isoquinolinamine		$C_9H_8N_2$	25475-67-6	144.173		178.5				
6551	Isoquinoline	Benzo[c]pyridine	C_9H_7N	119-65-3	129.159	hyg pl	26.47	243.22	1.0910^{30}	1.6148^{20}	i H_2O; vs EtOH, chl; msc eth, bz
6552	7-Isoquinolinol		C_9H_7NO	7651-83-4	145.158		230				sl H_2O, eth; s EtOH
6553	Isosorbide		$C_6H_{10}O_4$	652-67-5	146.141		63	170^{2}			
6554	Isosorbide dinitrate	1,4:3,6-Dianhydroglucitol	$C_6H_8N_2O_8$	87-33-2	236.136	col cry	52				vs EtOH, eth, ace
6555	Isosystox	Demeton-S	$C_8H_{19}O_3PS_2$	126-75-0	258.339	liq		133^{2}	1.132^{21}		s H_2O
6556	Isothebaine		$C_{19}H_{21}NO_3$	568-21-8	311.375	orth cry (al)	203.5				i H_2O; msc EtOH, chl; sl eth; s MeOH
6557	Isothiocyanic acid		CHNS	3129-90-6	59.091	unstab gas					
6558	*L*-Isovaline	2-Amino-2-methylbutyric acid	$C_5H_{11}NO_2$	595-40-4	117.147	nd (w)	≈300				s EtOH; sl eth
6559	Isoxaben		$C_{18}H_{24}N_2O_4$	82558-50-7	332.395	wh cry	173				s EtOAc, MeCN, MeOH
6560	Isoxazole	1-Oxa-2-azacyclopentadiene	C_3H_3NO	288-14-2	69.062			95	1.078^{20}	1.4298^{17}	s H_2O
6561	Isoxsuprine		$C_{18}H_{23}NO_3$	395-28-8	301.381	cry	103.0				
6562	Jacobine		$C_{18}H_{25}NO_6$	6870-67-3	351.395	pl (EtOH)	228				
6563	Javanicin		$C_{15}H_{14}O_6$	476-45-9	290.268	red cry (al)	208 dec				s alk
6564	Jervine		$C_{27}H_{39}NO_3$	469-59-0	425.604		243 dec				i H_2O; s EtOH, ace, chl; sl eth
6565	Kaempferol		$C_{15}H_{10}O_6$	520-18-3	286.236	ye nd (al, + 1 w)	277				sl H_2O, chl; vs EtOH, eth, ace; i bz
6566	Kainic acid		$C_{10}H_{15}NO_4$	487-79-6	213.231	cry (EtOH aq)	253 dec				s H_2O; i EtOH
6567	Kanamycin A		$C_{18}H_{36}N_4O_{11}$	59-01-8	484.499	cry (EtOH)					
6568	Kepone	Chlordecone	$C_{10}Cl_{10}O$	143-50-0	490.636		350 dec		1.61^{25}		
6569	Ketamine	2-(2-Chlorophenyl)-2-(methylamino)cyclohexanone, (±)	$C_{13}H_{16}ClNO$	6740-88-1	237.725	cry (eth-pentane)	92.5				
6570	Ketene		C_2H_2O	463-51-4	42.036	col gas	-151	-49.8			sl eth, ace
6571	Khellin	4,9-Dimethoxy-7-methyl-5*H*-furo[3,2-g][1]benzopyran-5-one	$C_{14}H_{12}O_5$	82-02-0	260.242	eth, al	154 dec	190$^{0.05}$			i H_2O; s EtOH, ace; sl eth, chl
6572	*L*-Kynurenine	Benzenebutanoic acid, α,2-diamino-γ-oxo-	$C_{10}H_{12}N_2O_3$	343-65-7	208.213	lf (+l/2w)	191 dec				sl H_2O
6573	Labetalol		$C_{19}H_{24}N_2O_3$	36894-69-6	328.405	cry (MeOH)	164				
6574	*DL*-Lactic acid	2-Hydroxypropanoic acid, (±)	$C_3H_6O_3$	598-82-3	90.078	ye cry	16.8	122^{15}	1.2060^{21}	1.4392^{20}	vs H_2O, EtOH; sl eth
6575	*D*-Lactic acid	*D*-2-Hydroxypropanoic acid	$C_3H_6O_3$	10326-41-7	90.078	pl (chl)	53	103^{2}			vs H_2O, EtOH
6576	*L*-Lactic acid	*L*-2-Hydroxypropanoic acid	$C_3H_6O_3$	79-33-4	90.078	hyg pr (eth)	25.5				vs H_2O, EtOH
6577	Lactofen		$C_{19}H_{15}ClF_3NO_7$	77501-63-4	461.773	ye pow (bz)	93				
6578	δ-Lactone-*D*-gluconic acid	δ-*D*-Gluconolactone	$C_6H_{10}O_6$	90-80-2	178.139	nd (al)					
6579	α-Lactose		$C_{12}H_{22}O_{11}$	14641-93-1	342.296	wh pow	222.8				vs H_2O; sl EtOH; i eth, chl
6580	β-*D*-Lactose		$C_{12}H_{22}O_{11}$	5965-66-2	342.296		254		1.59^{20}		vs H_2O; sl EtOH; i eth, chl
6581	α-Lactose monohydrate		$C_{12}H_{24}O_{12}$	5989-81-1	360.312	mcl (w)	201 dec		1.547^{20}		vs H_2O; i EtOH, eth, chl, MeOH
6582	Lactulose	4-*O*-β-*D*-Galactopyranosyl-*D*-fructose	$C_{12}H_{22}O_{11}$	4618-18-2	342.296	hx pl (MeOH)	169				vs H_2O
6583	Laminaribiose	3-*O*-β-*D*-Glucopyranosyl-*D*-glucose	$C_{12}H_{22}O_{11}$	34980-39-7	342.296		205				
6584	Lanosta-8,24-dien-3-ol, (3β)	Lanosterol	$C_{30}H_{50}O$	79-63-0	426.717	nd (eth), cry (MeOH-ace)	140.5				vs eth, EtOH, chl
6585	Lantadene A	Rehmannic acid	$C_{35}H_{52}O_5$	467-81-2	552.785	cry (MeOH)	297				
6586	Lantadene B		$C_{35}H_{52}O_5$	467-82-3	552.785	cry (EtOH)	302				
6587	*L*-Lanthionine	*L*-Cysteine, *S*-(2-amino-2-carboxyethyl)-, (*R*)-	$C_6H_{12}N_2O_4S$	922-55-4	208.235	hex pl	294 dec				sl H_2O
6588	Lapachol	2-Hydroxy-3-(3-methyl-2-butenyl)-1,4-naphthalenedione	$C_{15}H_{14}O_3$	84-79-7	242.270	ye pr (eth, bz) pl (al)	139.5				i H_2O; s EtOH, eth, bz, chl; vs HOAc
6589	Lappaconitine		$C_{32}H_{44}N_2O_8$	32854-75-4	584.699	hex pl (al)	217.5				i H_2O; sl EtOH, eth; s bz, chl
6590	Lasiocarpine		$C_{21}H_{33}NO_7$	303-34-4	411.490	col pl (peth)	95.5				sl H_2O; s EtOH, bz, eth
6591	Laudanidine		$C_{20}H_{25}NO_4$	301-21-3	343.418	hex pr (al)	184.5				vs H_2O, bz



Isopsoralen



1-Isoquinolinamine



3-Isoquinolinamine



Isoquinoline


7-Isoquinolinol



Isosorbide



Isosorbide dinitrate


Isosystox



Isothebaine



Isothiocyanic acid



L-Isovaline



Isoxaben



Isoxazole



Isoxsuprine



Jacobine



Javanicin



Jervine


Kaempferol


Kainic acid



Kanamycin A



Kepone



Ketamine



Ketene



Khellin



L-Kynurenine



Labetalol



DL-Lactic acid



D-Lactic acid



L-Lactic acid



Lactofen



δ-Lactone-*D*-gluconic acid



α-Lactose



β-*D*-Lactose



α-Lactose monohydrate



Lactulose



Laminaribiose



Lanosta-8,24-dien-3-ol, (3β)



Lantadene A



Lantadene B


L-Lanthionine



Lapachol



Lappaconitine



Lasiocarpine



Laudanidine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6592	Laudanine		$C_{20}H_{25}NO_4$	85-64-3	343.418	ye wh pr (dil al, al-chl)	167		1.26^{20}		sl H_2O, EtOH, eth; s bz, chl
6593	Laudanosine		$C_{21}H_{27}NO_4$	2688-77-9	357.444	nd (peth), pr (al)	89				vs ace, eth, EtOH, chl
6594	Laureline		$C_{19}H_{19}NO_3$	81-38-9	309.359	tab (al) cubes (peth)	114				i H_2O; s EtOH, eth, dil acid, con sulf
6595	Laurocapram	1-Dodecylhexahydro-2*H*-azepin-2-one	$C_{18}H_{35}NO$	59227-89-3	281.477	col liq	-7	160^{50}	0.91	1.4701	i H_2O
6596	Lead bis(dimethyldithiocarbamate)		$C_6H_{12}N_2PbS_4$	19010-66-3	447.6	pale ye nd	258				
6597	Ledol		$C_{15}H_{26}O$	577-27-5	222.366	nd (al)	105	292	0.9078^{100}	1.4667^{110}	vs ace, eth, EtOH
6598	Lenacil		$C_{13}H_{18}N_2O_2$	2164-08-1	234.294		290		1.32^{25}		vs py
6599	Leptophos		$C_{13}H_{10}BrCl_2O_2PS$	21609-90-5	412.066	tan waxy solid	71		1.53^{25}		i H_2O; vs bz; s ace, 2-PrOH, xyl
6600	*DL*-Leucine		$C_6H_{13}NO_2$	328-39-2	131.173	lf (w)	293	sub	1.293^{18}		s H_2O; sl EtOH; i eth
6601	*D*-Leucine		$C_6H_{13}NO_2$	328-38-1	131.173	pl (al)	293	sub			sl H_2O
6602	*L*-Leucine	2-Amino-4-methylpentanoic acid	$C_6H_{13}NO_2$	61-90-5	131.173	hex pl (dil al)	293	sub	1.293^{18}		sl H_2O; i EtOH, eth
6603	*N*-Leucylglycine		$C_8H_{16}N_2O_3$	686-50-0	188.224		248 dec				s H_2O; sl EtOH, eth; i ace, bz, chl
6604	Leuprolide		$C_{59}H_{84}N_{16}O_{12}$	53714-56-0	1209.398	fluffy solid					
6605	Leurosine		$C_{46}H_{56}N_4O_9$	23360-92-1	808.959	cry	203				
6606	Levallorphan	17-Allylmorphinan-3-ol	$C_{19}H_{25}NO$	152-02-3	283.408	cry (EtOH aq)	181				
6607	Levodopa	*L*-3,4-Dihydroxyphenylalanine	$C_9H_{11}NO_4$	59-92-7	197.188	pl (dil al) pr or nd (w+SO_2)	277 dec				s H_2O; i EtOH, eth, ace, bz; s alk, MeOH
6608	Levopimaric acid		$C_{20}H_{30}O_2$	79-54-9	302.451	orth cry	150				
6609	Levorphanol	17-Methylmorphinan-3-ol	$C_{17}H_{23}NO$	77-07-6	257.371	cry	198				
6610	*d*-Limonene	*p*-Mentha-1,8-diene, (*R*)	$C_{10}H_{16}$	5989-27-5	136.234	oil	-74.0	178	0.8411^{20}	1.4730^{20}	i H_2O; msc EtOH, eth; s ctc
6611	*l*-Limonene	*p*-Mentha-1,8-diene, (*S*)	$C_{10}H_{16}$	5989-54-8	136.234	oil		178; 64.4^{15}	0.843^{20}	1.4746^{20}	i H_2O; vs eth, EtOH
6612	Linalol	3,7-Dimethyl-1,6-octadien-3-ol, (±)-	$C_{10}H_{18}O$	22564-99-4	154.249			198; 86^{13}	0.870^{15}	1.4627	
6613	Linalyl acetate	3,7-Dimethyl-1,6-octadien-3-yl acetate	$C_{12}H_{20}O_2$	115-95-7	196.286	liq		220; $44^{0.2}$	0.895^{20}	1.4460^{20}	i H_2O; misc EtOH, eth
6614	Lincomycin		$C_{18}H_{34}N_2O_6S$	154-21-2	406.537	amor solid					sl H_2O; s EtOH, ace, chl
6615	Linoleic acid	*cis,cis*-9,12-Octadecadienoic acid	$C_{18}H_{32}O_2$	60-33-3	280.446		-7	229^{16}	0.9022^{20}	1.4699^{20}	vs ace, bz, eth, EtOH
6616	Linolenic acid	*cis,cis,cis*-9,12,15-Octadecatrienoic acid	$C_{18}H_{30}O_2$	463-40-1	278.430		-11	231^{17}, $129^{0.05}$	0.9164^{20}	1.4800^{20}	i H_2O; s EtOH, eth; sl bz
6617	Linuron	*N*-(3,4-Dichlorophenyl)-*N'*-methoxy-*N'*-methylurea	$C_9H_{10}Cl_2N_2O_2$	330-55-2	249.093		93				
6618	Liothyronine		$C_{15}H_{12}I_3NO_4$	6893-02-3	650.974	cry	236 dec				i H_2O, EtOH; s dil alk
6619	Lipoamide	1,2-Dithiolane-3-pentanamide	$C_8H_{15}NOS_2$	940-69-2	205.341	cry	128				
6620	α-Lipoic acid	1,2-Dithiolane-3-pentanoic acid	$C_8H_{14}O_2S_2$	1077-28-7	206.326	ye pl (cy)	60	87^{25}			i H_2O
6621	Lisinopril		$C_{21}H_{35}N_3O_7$	83915-83-7	441.519	wh cry pow	159				i EtOH, chl, ace; sl MeOH
6622	Lithium oxalate		$C_2Li_2O_4$	30903-87-8	101.901		dec		2.121^{17}		s H_2O; i EtOH, eth
6623	Lobelanidine		$C_{22}H_{29}NO_2$	552-72-7	339.471	sc (al, eth)	150				i H_2O; s EtOH; sl eth; vs ace, bz, py
6624	Lobelanine		$C_{22}H_{25}NO_2$	579-21-5	335.440	nd (eth, peth)	99				vs ace, bz, EtOH, chl
6625	Lobeline		$C_{22}H_{27}NO_2$	90-69-7	337.455	nd (al, bz)	130.5				sl H_2O; s EtOH, eth, bz, chl; vs ace
6626	Loflucarban		$C_{13}H_9Cl_2FN_2S$	790-69-2	315.192		163.5				
6627	Longifolene	Kuromatsuene	$C_{15}H_{24}$	475-20-7	204.352			258; 126^{15}	0.9319^{18}	1.5040^{20}	i H_2O; s bz
6628	Loratadine	Claritin	$C_{22}H_{23}ClN_2O_2$	79794-75-5	382.883	cry (MeCN)	132				
6629	Lovastatin	Mevacor	$C_{24}H_{36}O_5$	75330-75-5	404.540	wh cry (ace aq)	174				i H_2O; vs chl; s DMF; sl ace, EtOH
6630	Lovozal		$C_{15}H_7Cl_2F_3N_2O_2$	14255-88-0	375.130	ye cry	103				s ace, diox
6631	Loxapine		$C_{18}H_{18}ClN_3O$	1977-10-2	327.808	ye cry (peth)	109.5				



Laudanine



Laudanosine



Laureline



Laurocapram



Lead bis(dimethyldithiocarbamate)



Ledol



Lenacil


Leptophos



DL-Leucine



D-Leucine



L-Leucine



N-Leucylglycine


H-5-oxoPro-His-Trp-Ser-Tyr-D-Leu-Leu-Arg-Pro-NHEt
Leuprolide



Leurosine



Levallorphan



Levodopa



Levopimaric acid



Levorphanol



d-Limonene



l-Limonene



Linalol



Linalyl acetate



Lincomycin



Linoleic acid



Linolenic acid



Linuron



Liothyronine



Lipoamide



α-Lipoic acid



Lisinopril



Lithium oxalate



Lobelanidine



Lobelanine



Lobeline



Loflucarban


Longifolene



Loratadine



Lovastatin



Lovozal



Loxapine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6632	Loxoprofen	α-Methyl-4-[(2-oxocyclopentyl) methyl]benzeneacetic acid	$C_{15}H_{18}O_3$	68767-14-6	246.302	col oil	110	$192^{0.3}$			
6633	Luciculine	Napelline	$C_{22}H_{33}NO_3$	5008-52-6	361.518	cry (+1w, ace)	149	$165^{0.02}$			vs EtOH
6634	Lunacrine		$C_{16}H_{19}NO_3$	82-40-6	273.327						s chl
6635	Lup-20(29)-ene-3,28-diol, (3β)	Betulin	$C_{30}H_{50}O_2$	473-98-3	442.717	nd (al +1)	250	sub 240			i H_2O; sl EtOH, bz; s eth, AcOEt, lig
6636	Lup-20(29)-en-3-ol, (3β)	Lupeol	$C_{30}H_{50}O$	545-47-1	426.717	nd (al, ace)	216		0.9457^{218}	1.4910^{218}	i H_2O; vs EtOH, eth, ace, bz, chl
6637	Lupulon		$C_{26}H_{38}O_4$	468-28-0	414.578	pr (MeOH)	93				i H_2O; s EtOH, peth, hx
6638	Luteolin		$C_{15}H_{10}O_6$	491-70-3	286.236	ye nd (dil al, + 1 w)	329 dec				sl H_2O; s EtOH, eth, alk, con sulf
6639	Luteoskyrin	8,8'-Dihydroxyrugulosin	$C_{30}H_{22}O_{12}$	21884-44-6	574.489	ye nd (EtOH)	278 dec				
6640	Lycodine		$C_{16}H_{22}N_2$	20316-18-1	242.359	orth pr	99	$190^{1.0}$			s H_2O, chl, eth, EtOH; i peth
6641	Lycomarasmine		$C_9H_{15}N_3O_7$	7611-43-0	277.231		228 dec				
6642	Lycorine		$C_{16}H_{17}NO_4$	476-28-8	287.311	pr (al, py)	280	sub			i H_2O; sl EtOH, eth, chl
6643	Lysergamide		$C_{16}H_{17}N_3O$	478-94-4	267.325	cry (MeOH), pr (aq, ace)	137.5				sl EtOH, ace, os
6644	Lysergic acid		$C_{16}H_{16}N_2O_2$	82-58-6	268.310	lf or hex sc (w)	240 dec				sl H_2O, eth, bz; s EtOH, py
6645	Lysergide		$C_{20}H_{25}N_3O$	50-37-3	323.432		82				
6646	*DL*-Lysine	2,6-Diaminohexanoic acid, (±)	$C_6H_{14}N_2O_2$	70-54-2	146.187		224				sl H_2O
6647	*D*-Lysine	2,6-Diaminohexanoic acid, (*D*)	$C_6H_{14}N_2O_2$	923-27-3	146.187		218 dec				s H_2O
6648	*L*-Lysine	2,6-Diaminohexanoic acid, (*L*)	$C_6H_{14}N_2O_2$	56-87-1	146.187	nd (w, dil al)	224 dec				s H_2O; i EtOH, eth, ace, bz
6649	*L*-Lysine, hydrochloride		$C_6H_{15}ClN_2O_2$	10098-89-2	182.648		263 dec				
6650	*D*-Lyxose		$C_5H_{10}O_5$	1114-34-7	150.130		108		1.545^{20}		
6651	*L*-Lyxose		$C_5H_{10}O_5$	1949-78-6	150.130		110				
6652	Maclurin	(3,4-Dihydroxyphenyl)(2,4,6-trihydroxyphenyl)methanone	$C_{13}H_{10}O_6$	519-34-6	262.214	ye nd (al)	222.5				vs eth, EtOH
6653	Magenta base	Rosaniline	$C_{20}H_{19}N_3$	3248-93-9	301.385	br-red cry	186 dec				
6654	Magenta I	Rosaniline hydrochloride	$C_{20}H_{20}ClN_3$	632-99-5	337.846	grn cry	200 dec				sl H_2O, EtOH; i eth
6655	Magnesium stearate	Magnesium octadecanoate	$C_{36}H_{70}MgO_4$	557-04-0	591.244	wh pow	132				i H_2O; reac acid
6656	Malachite Green		$C_{23}H_{25}ClN_2$	569-64-2	364.911	grn cry					vs H_2O, EtOH, MeOH
6657	Malaoxon	(Dimethoxyphosphinylthio) butanedioic acid	$C_{10}H_{19}O_7PS$	1634-78-2	314.293	liq		$132^{0.1}$			
6658	Malathion		$C_{10}H_{19}O_6PS_2$	121-75-5	330.358	ye-br liq	1.4	$156^{0.7}$ dec	1.2076^{20}	1.4960^{20}	sl H_2O; s EtOH, eth, bz
6659	Maleic acid	*cis*-2-Butenedioic acid	$C_4H_4O_4$	110-16-7	116.073	mcl pr (w)	139		1.590^{20}		vs H_2O, EtOH, ace; s eth; i bz, chl
6660	Maleic anhydride		$C_4H_2O_3$	108-31-6	98.057	nd (chl, eth)	52.56	202	1.314^{60}		s H_2O; s eth, ace, chl; sl lig
6661	Maleonitrile	*cis*-Butenedinitrile	$C_4H_2N_2$	928-53-0	78.072	pr (EtOH)	31.5	111^{20}			
6662	Malic acid	Hydroxybutanedioic acid	$C_4H_6O_5$	617-48-1	134.088		132		1.601^{20}		s H_2O; vs eth, EtOH, MeOH
6663	Malonaldehyde	1,3-Propanedial	$C_3H_4O_2$	542-78-9	72.063	hyg nd	73				
6664	Malonic acid		$C_3H_4O_4$	141-82-2	104.062	tcl (al)	135 dec	sub	1.619^{10}		vs H_2O, py; s EtOH, eth; i bz
6665	Malononitrile		$C_3H_2N_2$	109-77-3	66.061		32	218.5	1.1910^{20}	1.4146^{34}	s H_2O, ace, bz, chl; vs EtOH, eth
6666	Maltopentaose		$C_{30}H_{52}O_{26}$	34620-76-3	828.718	cry (w)	78 (hyd)				
6667	α-Maltose		$C_{12}H_{22}O_{11}$	4482-75-1	342.296	nd (al)	162.5		1.546^{20}		vs H_2O
6668	6-*O*-α-Maltosyl-β-cyclodextrin		$C_{54}H_{90}O_{45}$	104723-60-6	1459.266	cry (MeOH)					
6669	Maltotetraose		$C_{24}H_{42}O_{21}$	34612-38-9	666.577	amorp solid	170 dec				
6670	Malvidin chloride		$C_{17}H_{15}ClO_7$	643-84-5	366.750		>300				sl H_2O; s EtOH, MeOH
6671	Mandelic acid	α-Hydroxybenzeneacetic acid	$C_8H_8O_3$	90-64-2	152.148	orth pl	119		1.2890^{20}		s H_2O, eth, EtOH, i-PrOH
6672	Mandelonitrile glucoside		$C_{14}H_{17}NO_6$	138-53-4	295.288	wh nd or pl (al)	122				vs H_2O, EtOH
6673	Maneb	Manganese, [[1,2-ethanediylbis[carbamodithioato]](2-)]-	$C_4H_6MnN_2S_4$	12427-38-2	265.302		dec 200				



Loxoprofen



Luciculine



Lunacrine



Lup-20(29)-ene-3,28-diol, (3β)



Lup-20(29)-en-3-ol, (3β)



Lupulon



Luteolin



Luteoskyrin



Lycodine



Lycomarasmine



Lycorine



Lysergamide



Lysergic acid



Lysergide



DL-Lysine



D-Lysine



L-Lysine



L-Lysine, hydrochloride



D-Lyxose



L-Lyxose



Maclurin



Magenta base



Magenta I



Magnesium stearate


Malachite Green



Malaoxon



Malathion



Maleic acid



Maleic anhydride



Maleonitrile



Malic acid



Malonaldehyde



Malonic acid



Malononitrile



Maltopentaose



α-Maltose



6-*O*-α-Maltosyl-β-cyclodextrin


Maltotetraose



Malvidin chloride



Mandelic acid



Mandelonitrile glucoside



Maneb


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6674	Manganese(II) acetate		$C_4H_6O_4Mn$	638-38-0	173.027	red cry (w)	210				s H_2O, MeOH, HOAc; i ace
6675	Manganese carbonyl	Dimanganese decacarbonyl	$C_{10}Mn_2O_{10}$	10170-69-1	389.977	ye mcl cry	154		1.75		i H_2O; s os
6676	Manganese cyclopentadienyl tricarbonyl		$C_8H_5MnO_3$	12079-65-1	204.062	pale ye cry	77.0	subl			s os
6677	Manganese 2-methylcyclopentadienyl tricarbonyl		$C_9H_7MnO_3$	12108-13-3	218.088	ye liq	1.5	233; 102^{10}	1.388^{20}		i H_2O; misc bz
6678	*D*-Mannitol	Cordycepic acid	$C_6H_{14}O_6$	69-65-8	182.171	orth nd or pr (w)	168	295$^{3.5}$	1.489^{20}	1.3330	vs H_2O; sl EtOH, py; i eth
6679	*D*-Mannitol hexanitrate		$C_6H_8N_6O_{18}$	15825-70-4	452.157	nd (al)	107	exp	1.8^{20}		vs bz, eth, EtOH
6680	*D*-Mannose	Seminose	$C_6H_{12}O_6$	3458-28-4	180.155	nd or orth pr (al)	132 dec		1.539^{20}		vs H_2O; sl EtOH, MeOH; i eth, bz
6681	*L*-Mannose		$C_6H_{12}O_6$	10030-80-5	180.155	cry (al)	132				vs H_2O
6682	Matridin-15-one	Matrine	$C_{15}H_{24}N_2O$	519-02-8	248.364	α-nd or pl; β-orth pr,		223^{6}		1.5286^{25}	s H_2O, eth, ace; vs EtOH, bz; sl peth
6683	Mazindol		$C_{16}H_{13}ClN_2O$	22232-71-9	284.739	cry (ace/hx)	198				i H_2O; s EtOH
6684	Mebendazole		$C_{16}H_{13}N_3O_3$	31431-39-7	295.292	cry (HOAc/ MeOH)	288.5				i H_2O, EtOH, eth, chl
6685	Mebhydroline		$C_{19}H_{20}N_2$	524-81-2	276.375	cry	95	211^{1}			i H_2O; sl eth; vs EtOH, ace, MeOH
6686	Mecarbam		$C_{10}H_{20}NO_5PS_2$	2595-54-2	329.374	ye oil		144$^{0.02}$	1.223^{20}		sl H_2O
6687	Meclizine		$C_{25}H_{27}ClN_2$	569-65-3	390.948			230			s CS_2
6688	Medroxyprogesterone		$C_{22}H_{32}O_3$	520-85-4	344.487		214.5				vs chl
6689	Mefenamic acid	2-[(2,3-Dimethylphenyl)amino] benzoic acid	$C_{15}H_{15}NO_2$	61-68-7	241.286	hyg cry	230 dec				s alk; sl eth, chl
6690	Mefloquine		$C_{17}H_{16}F_6N_2O$	53230-10-7	378.311	cry (MeOH aq)	178.2				
6691	Mefluidide		$C_{11}H_{13}F_3N_2O_3S$	53780-34-0	310.292		184				
6692	Melezitose		$C_{18}H_{32}O_{16}$	597-12-6	504.437	cry (w+2)	153		1.5565^{25}		vs H_2O
6693	α-*D*-Melibiose	6-*O*-α-*D*-Galactopyranosyl-*D*-glucose	$C_{12}H_{22}O_{11}$	585-99-9	342.296						vs H_2O; sl EtOH; dec acid
6694	Melinamide	*N*-(1-Phenylethyl)-9,12-octadecadieneamide, (*Z,Z*)-	$C_{26}H_{41}NO$	14417-88-0	383.610	oil	<4	202$^{0.07}$		1.5050^{23}	
6695	Melphalan	*L*-Phenylalanine, 4-[bis(2-chloroethyl)amino]-	$C_{13}H_{18}Cl_2N_2O_2$	148-82-3	305.200	nd	183 dec				i H_2O; s EtOH
6696	Menaquinone 7	Vitamin K_2(35)	$C_{46}H_{64}O_2$	2124-57-4	648.999	cry	54				
6697	Menazon		$C_6H_{12}N_5O_2PS_2$	78-57-9	281.296	cry (MeOH)	160				sl H_2O; s thf
6698	*p*-Menthane hydroperoxide	1-Methyl-1-(4-methylcyclohexyl)ethyl hydroperoxide	$C_{10}H_{20}O_2$	80-47-7	172.265			259	0.92		
6699	*p*-Menth-8-en-2-one	2-Methyl-5-(1-methylethenyl) cyclohexanone	$C_{10}H_{16}O$	7764-50-3	152.233			223.0			
6700	Menthol 3-methylbutanoate	Menthol, isovalerate	$C_{15}H_{28}O_2$	16409-46-4	240.382			129^{9}	0.908^{15}	1.4486^{20}	i H_2O; s EtOH, ace
6701	Meperidine	Pethidine	$C_{15}H_{21}NO_2$	57-42-1	247.334		30	155^{5}			
6702	Mephenytoin		$C_{12}H_{14}N_2O_2$	50-12-4	218.251		136				
6703	Mephobarbital		$C_{13}H_{14}N_2O_3$	115-38-8	246.261	wh cry (w)	176				sl H_2O, eth, chl; vs EtOH
6704	Mephosfolan		$C_8H_{16}NO_3PS_2$	950-10-7	269.322	ye liq		120$^{0.001}$		1.5354^{26}	s ace, EtOH, bz
6705	Mepiquat chloride	Piperidinium, 1,1-dimethyl-, chloride	$C_7H_{16}ClN$	24307-26-4	149.662		223				
6706	Mepivacaine	*N*-(2,6-Dimethylphenyl)-1-methyl-2-piperidinecarboxamide	$C_{15}H_{22}N_2O$	96-88-8	246.348	cry (eth)	150.5				s CS_2
6707	Mepivacaine monohydrochloride	Carbocaine hydrochloride	$C_{15}H_{23}ClN_2O$	1722-62-9	282.809	cry	263				s H_2O
6708	Mercaptoacetic acid, 2-ethylhexyl ester		$C_{10}H_{20}O_2S$	7659-86-1	204.330			133.5	0.97^{20}		
6709	2-Mercaptobenzoic acid	*o*-Thiosalicylic acid	$C_7H_6O_2S$	147-93-3	154.187	lf or nd (al, w, HOAc)	168.5	sub			s H_2O, EtOH, eth; sl DMSO, lig
6710	Mercaptobenzthiazyl ether	2,2'-Dithiobis[benzothiazole]	$C_{14}H_8N_2S_4$	120-78-5	332.487	ye nd	180		1.50		i H_2O; sl EtOH, bz, ctc, ace
6711	2-Mercaptoethanol		C_2H_6OS	60-24-2	78.133			158; 55^{13}	1.1143^{20}	1.4996^{20}	s H_2O, EtOH, eth, bz
6712	2-Mercapto-2-methylpropanoic acid		$C_4H_8O_2S$	4695-31-2	120.171		47	101^{15}			vs H_2O
6713	2-Mercapto-*N*-2-naphthylacetamide	Thionalide	$C_{12}H_{11}NOS$	93-42-5	217.286		111.5				i H_2O; vs EtOH, os
6714	2-Mercaptophenol		C_6H_6OS	1121-24-0	126.176	oil	5.5	217; 89^{8}	1.2371^{0}		vs bz, eth, EtOH



Manganese(II) acetate



Manganese carbonyl



Manganese cyclopentadienyl tricarbonyl



Manganese 2-methylcyclopentadienyl tricarbonyl



D-Mannitol



D-Mannitol hexanitrate



D-Mannose



L-Mannose



Matridin-15-one



Mazindol



Mebendazole



Mebhydroline



Mecarbam



Meclizine



Medroxyprogesterone



Mefenamic acid



Mefloquine



Mefluidide



Melezitose



α-*D*-Melibiose



Melinamide



Melphalan



Menaquinone 7



Menazon



p-Menthane hydroperoxide



p-Menth-8-en-2-one



Menthol 3-methylbutanoate



Meperidine



Mephenytoin



Mephobarbital



Mephosfolan



Mepiquat chloride



Mepivacaine



Mepivacaine monohydrochloride



Mercaptoacetic acid, 2-ethylhexyl ester



2-Mercaptobenzoic acid


Mercaptobenzthiazyl ether



2-Mercaptoethanol



2-Mercapto-2-methylpropanoic acid



2-Mercapto-*N*-2-naphthylacetamide



2-Mercaptophenol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6715	4-Mercaptophenol		C_6H_6OS	637-89-8	126.176	cry	29.5	167^{45}, 135^{11}	1.1285^{25}	1.5101^{25}	s H_2O, EtOH, alk, con sulf
6716	3-Mercapto-1,2-propanediol	Thioglycerol	$C_3H_8O_2S$	96-27-5	108.160	visc		100^{1}	1.2455^{20}	1.5268^{20}	sl H_2O, eth, bz, chl; msc EtOH; vs ace
6717	3-Mercaptopropanoic acid		$C_3H_6O_2S$	107-96-0	106.144	amor	18	111^{15}, 86^{3}	1.218^{21}	1.494^{20}	s H_2O, EtOH, eth, ctc
6718	3-Mercapto-*D*-valine	Penicillamine	$C_5H_{11}NO_2S$	52-67-5	149.212		198.5				
6719	Mercury(II) benzoate	Mercuric benzoate	$C_{14}H_{10}HgO_4$	583-15-3	442.81	cry pow (w)	≈125				i EtOH
6720	Mercury(II) oleate	Mercuric oleate	$C_{36}H_{66}HgO_4$	1191-80-6	763.35	ye-br solid					i H_2O; sl EtOH, eth
6721	Mercury(II) phenyl acetate	Phenylmercuric acetate	$C_8H_8HgO_2$	62-38-4	336.74		153				i H_2O; s chl
6722	Merphos	Phosphorotrithious acid, *S,S,S*-tributyl ester	$C_{12}H_{27}PS_3$	150-50-5	298.511		100	$137^{0.7}$, 176^{15}	1.02^{20}		
6723	Mesityl oxide	Isobutenyl methyl ketone	$C_6H_{10}O$	141-79-7	98.142	liq	-59	130	0.8653^{20}	1.4440^{20}	s H_2O, ace; msc EtOH, eth
6724	Mesoridazine		$C_{21}H_{26}N_2OS_2$	5588-33-0	386.573	oil					
6725	Mestranol		$C_{21}H_{26}O_2$	72-33-3	310.430	cry	151				i H_2O; s diox, eth, EtOH, chl
6726	[2.2]Metacyclophane	Tricyclo[9.3.1.1]hexadeca-1(15),4,6,8(16),11,13-hexaene	$C_{16}H_{16}$	2319-97-3	208.298	orth pr	132.5	290			sl EtOH; s bz, eth
6727	Metalaxyl		$C_{15}H_{21}NO_4$	57837-19-1	279.333		71				
6728	Metaldehyde	Metacetaldehyde (polymer)	$(C_2H_4O)_x$	37273-91-9		tetr nd or pr (al)	246	sub 115			i H_2O, ace; sl EtOH, eth, bz, chl
6729	Metanil Yellow		$C_{18}H_{14}N_3NaO_3S$	587-98-4	375.377	br-ye pow					vs H_2O, EtOH; s bz, eth; sl ace
6730	Metaraminol	2-Amino-1-(3-hydroxyphenyl)-1-propanol, (1*R*,2*S*)	$C_9H_{13}NO_2$	54-49-9	167.205	hyg cry (HCl)					s H_2O
6731	Metaxalone		$C_{12}H_{15}NO_3$	1665-48-1	221.252	cry (AcOEt)	122	$223^{1.5}$			
6732	Methacholine chloride		$C_8H_{18}ClNO_2$	62-51-1	195.688	hyg cry	172				vs H_2O, EtOH, chl
6733	Methacrylic acid	2-Methylpropenoic acid	$C_4H_6O_2$	79-41-4	86.090	pr	16	162.5	1.0153^{20}	1.4314^{20}	s H_2O, chl; msc EtOH, eth
6734	Methacycline		$C_{22}H_{22}N_2O_8$	914-00-1	442.418	cry	205 dec				
6735	Methadone hydrochloride	6-(Dimethylamino)-4,4-diphenyl-3-heptanone hydrochloride	$C_{21}H_{28}ClNO$	1095-90-5	345.906	pl (al-eth)	235				vs H_2O, EtOH
6736	Methallenestril		$C_{18}H_{22}O_3$	517-18-0	286.366	cry (MeOH aq)	139				s eth
6737	Methamidophos	Phosphoramidothioic acid, *O,S*-dimethyl ester	$C_2H_8NO_2PS$	10265-92-6	141.130		46		1.31^{20}		
6738	Methamphetamine		$C_{10}H_{15}N$	537-46-2	149.233			212			
6739	Methamphetamine hydrochloride	*N*,α-Dimethylbenzeneethanamine, hydrochloride, (*S*)-	$C_{10}H_{16}ClN$	51-57-0	185.694		173.8				vs H_2O, EtOH, chl
6740	Methandrostenolone		$C_{20}H_{28}O_2$	72-63-9	300.435		166				
6741	Methane		CH_4	74-82-8	16.043	col gas	-182.47	-161.48	0.4228^{-162}		sl H_2O, ace; s EtOH, eth, bz, tol, MeOH
6742	Methanearsonic acid		CH_5AsO_3	124-58-3	139.971		160.5				s H_2O, EtOH
6743	Methanedisulfonic acid	Methionic acid	$CH_4O_6S_2$	503-40-2	176.169		98				i H_2O; s HNO_3
6744	Methanesulfonic acid	Methylsulfonic acid	CH_4O_3S	75-75-2	96.106		20	167^{10}	1.4812^{18}	1.4317^{18}	s H_2O
6745	Methanesulfonyl chloride		CH_3ClO_2S	124-63-0	114.552			162; 55^{11}	1.4805^{18}	1.4573^{20}	i H_2O; s EtOH, eth
6746	Methanesulfonyl fluoride		CH_3FO_2S	558-25-8	98.097			123.5			
6747	Methanethiol	Methyl mercaptan	CH_4S	74-93-1	48.108	col gas	-123	5.9	0.8665^{20}		sl H_2O, chl; vs EtOH, eth
6748	Methanimidamide	Formamidine	CH_4N_2	463-52-5	44.056	pr	81	dec			vs H_2O, EtOH
6749	Methanimidamide, monoacetate	Formamidine acetate	$C_3H_8N_2O_2$	3473-63-0	104.108		161.5				vs H_2O
6750	Methanol	Methyl alcohol	CH_4O	67-56-1	32.042	liq	-97.53	64.6	0.7914^{20}	1.3288^{20}	msc H_2O, EtOH, eth, ace; vs bz; s chl
6751	Methantheline bromide		$C_{21}H_{26}BrNO_3$	53-46-3	420.340	cry (i-PrOH)	174.5				s H_2O, EtOH, chl; i eth
6752	Methapyrilene		$C_{14}H_{19}N_3S$	91-80-5	261.386			174^{3}		1.5915^{20}	
6753	Metharbital	5,5-Diethyl-1-methyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	$C_9H_{14}N_2O_3$	50-11-3	198.218	nd	150.5				s H_2O; sl chl
6754	Methazolamide		$C_5H_8N_4O_3S_2$	554-57-4	236.273	cry (w)	213 dec				
6755	Methazole		$C_9H_6Cl_2N_2O_3$	20354-26-1	261.061		123		1.24^{25}		
6756	Methenamine allyl iodide	Allylhexamethylenetetramine iodide	$C_9H_{17}IN_4$	36895-62-2	308.162	cry	148 dec				vs H_2O; i chl, eth



4-Mercaptophenol



3-Mercapto-1,2-propanediol



3-Mercaptopropanoic acid



3-Mercapto-*D*-valine



Mercury(II) benzoate



Mercury(II) oleate



Mercury(II) phenyl acetate



Merphos



Mesityl oxide



Mesoridazine



Mestranol



[2.2]Metacyclophane



Metalaxyl



Metaldehyde



Metanil Yellow



Metaraminol



Metaxalone



Methacholine chloride



Methacrylic acid



Methacycline



Methadone hydrochloride


Methallenestril



Methamidophos



Methamphetamine



Methamphetamine hydrochloride



Methandrostenolone



Methane


Methanearsonic acid


Methanedisulfonic acid



Methanesulfonic acid


Methanesulfonyl chloride



Methanesulfonyl fluoride



Methanethiol



Methanimidamide



Methanimidamide, monoacetate



Methanol



Methantheline bromide


Methapyrilene



Metharbital



Methazolamide



Methazole



Methenamine allyl iodide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6757	Methestrol		$C_{20}H_{26}O_2$	130-73-4	298.419	cry (dil HOAc)	145				
6758	Methidathion		$C_6H_{11}N_2O_4PS_3$	950-37-8	302.330		39				
6759	Methiocarb	Phenol, 3,5-dimethyl-4-(methylthio)-, methylcarbamate	$C_{11}H_{15}NO_2S$	2032-65-7	225.308		120				
6760	*L*-Methionine		$C_5H_{11}NO_2S$	63-68-3	149.212	hex pl (dil al)	281 dec				s H_2O; i EtOH, eth, ace, bz, peth; sl HOAc
6761	Methocarbamol	Guaifenesin-1-carbamate	$C_{11}H_{15}NO_5$	532-03-6	241.241	cry (bz)	93				s EtOH
6762	Methomyl		$C_5H_{10}N_2O_2S$	16752-77-5	162.210		78		1.2946^{24}		
6763	Methoprene		$C_{19}H_{34}O_3$	40596-69-8	310.471			100$^{0.05}$	0.926^{20}		
6764	Methoprotryne		$C_{11}H_{21}N_5OS$	841-06-5	271.383	cry	69				sl H_2O; s os
6765	Methotrexate		$C_{20}H_{22}N_8O_5$	59-05-2	454.440	ye cry (w)	190 dec				
6766	Methoxamine hydrochloride		$C_{11}H_{18}ClNO_3$	61-16-5	247.719	cry	214				vs H_2O; i eth, bz, chl
6767	Methoxsalen	9-Methoxy-7*H*-furo[3,2-g][1]benzopyran-7-one	$C_{12}H_8O_4$	298-81-7	216.190	pr (dil al) nd (peth)	148				sl H_2O, eth, ace, peth; vs EtOH
6768	Methoxyacetaldehyde		$C_3H_6O_2$	10312-83-1	74.079			92	1.005^{25}	1.3950^{20}	vs H_2O, ace, eth, EtOH
6769	Methoxyacetic acid		$C_3H_6O_3$	625-45-6	90.078	hyg		203.5	1.1768^{20}	1.4168^{20}	s H_2O, EtOH, eth
6770	Methoxyacetonitrile		C_3H_5NO	1738-36-9	71.078			119	0.9492^{20}	1.3831^{20}	sl H_2O; s EtOH, eth, ace, chl, alk, acid
6771	Methoxyacetyl chloride		$C_3H_5ClO_2$	38870-89-2	108.524			112.5	1.1871^{20}	1.4199^{20}	s eth, ace, ctc; vs chl
6772	2-Methoxyaniline	*o*-Anisidine	C_7H_9NO	90-04-0	123.152		6.2	224	1.0923^{20}	1.5715^{10}	sl H_2O; s EtOH, eth, ace, bz
6773	3-Methoxyaniline	*m*-Anisidine	C_7H_9NO	536-90-3	123.152	liq	-1	251	1.096^{20}	1.5794^{20}	sl H_2O, ctc; s EtOH, eth, ace, bz
6774	4-Methoxyaniline	*p*-Anisidine	C_7H_9NO	104-94-9	123.152	orth pl	57.2	243	1.071^{57}	1.5559^{60}	s H_2O, ace, bz; vs EtOH, eth
6775	2-Methoxyaniline hydrochloride	*o*-Anisidine hydrochloride	$C_7H_{10}ClNO$	134-29-2	159.613	nd	225				
6776	1-Methoxy-9,10-anthracenedione		$C_{15}H_{10}O_3$	82-39-3	238.238		170.3				sl EtOH; vs bz, chl
6777	2-Methoxybenzaldehyde		$C_8H_8O_2$	135-02-4	136.149	pr	37.5	243.5	1.1326^{20}	1.5600^{20}	i H_2O; s EtOH, bz, ctc; vs eth, ace, chl
6778	3-Methoxybenzaldehyde		$C_8H_8O_2$	591-31-1	136.149			231	1.1187^{20}	1.5530^{20}	i H_2O; s EtOH, bz; vs eth, ace, chl
6779	4-Methoxybenzaldehyde	*p*-Anisaldehyde	$C_8H_8O_2$	123-11-5	136.149		0	248; 134^{12}	1.119^{15}	1.5730^{20}	i H_2O; msc EtOH, eth; vs ace, chl; s bz
6780	4-Methoxybenzamide		$C_8H_9NO_2$	3424-93-9	151.163	nd or tab (w)	166.5	295			vs H_2O, EtOH
6781	4-Methoxybenzeneacetaldehyde		$C_9H_{10}O_2$	5703-26-4	150.174			255.5	1.096^{20}	1.5359^{20}	
6782	2-Methoxybenzeneacetic acid		$C_9H_{10}O_3$	93-25-4	166.173	nd (w)	124	100^{2}			s H_2O; vs EtOH, eth, ace, bz, chl
6783	4-Methoxybenzeneacetic acid		$C_9H_{10}O_3$	104-01-8	166.173	pl (w)	87	138^{2}			i H_2O; vs EtOH; s eth, bz; sl chl, lig
6784	4-Methoxybenzeneacetonitrile		C_9H_9NO	104-47-2	147.173			286.5	1.0845^{20}	1.5309^{20}	s EtOH, eth, chl
6785	4-Methoxy-1,2-benzenediamine	4-Methoxy-*o*-phenylenediamine	$C_7H_{10}N_2O$	102-51-2	138.166	grn pl	51	200^{21}, 168^{11}			vs eth
6786	4-Methoxy-1,3-benzenediamine	4-Methoxy-*m*-phenylenediamine	$C_7H_{10}N_2O$	615-05-4	138.166	nd (eth)	67.5				s EtOH, eth; sl DMSO
6787	2-Methoxy-1,4-benzenediamine	2,5-Diaminoanisole	$C_7H_{10}N_2O$	5307-02-8	138.166	cry	107				
6788	3-Methoxy-1,2-benzenediol		$C_7H_8O_3$	934-00-9	140.137	nd	42.8	163^{48}, 129^{10}			s chl
6789	4-Methoxybenzeneethanamine		$C_9H_{13}NO$	55-81-2	151.205			139^{20}		1.5379^{20}	
6790	4-Methoxybenzeneethanol		$C_9H_{12}O_2$	702-23-8	152.190		29	335			
6791	2-Methoxybenzenemethanamine		$C_8H_{11}NO$	6850-57-3	137.179			228	1.051^{25}	1.5475^{20}	
6792	4-Methoxybenzenemethanamine		$C_8H_{11}NO$	2393-23-9	137.179			236.5	1.050^{15}	1.5462^{20}	sl H_2O, EtOH, eth
6793	2-Methoxybenzenemethanol		$C_8H_{10}O_2$	612-16-8	138.164			249	1.0386^{25}	1.5455^{20}	i H_2O; s EtOH; msc eth
6794	3-Methoxybenzenemethanol		$C_8H_{10}O_2$	6971-51-3	138.164		30	252	1.112^{25}	1.5440^{20}	
6795	4-Methoxybenzenemethanol	Anise alcohol	$C_8H_{10}O_2$	105-13-5	138.164	nd	25	259.1	1.109^{26}	1.5420^{25}	s H_2O, ctc; vs EtOH, eth
6796	4-Methoxybenzenesulfonyl chloride		$C_7H_7ClO_3S$	98-68-0	206.647	nd or pr (bz)	42.5	103$^{0.25}$			s EtOH, eth, bz
6797	3-Methoxybenzenethiol		C_7H_8OS	15570-12-4	140.203			224.5; 114^{20}		1.5874^{20}	s chl
6798	4-Methoxybenzenethiol		C_7H_8OS	696-63-9	140.203			228	1.1313^{25}	1.5801^{25}	s EtOH, eth, bz; sl chl



Methestrol



Methidathion



Methiocarb



L-Methionine



Methocarbamol



Methomyl



Methoprene



Methoprotryne



Methotrexate



Methoxamine hydrochloride



Methoxsalen



Methoxyacetaldehyde



Methoxyacetic acid



Methoxyacetonitrile



Methoxyacetyl chloride



2-Methoxyaniline



3-Methoxyaniline



4-Methoxyaniline



2-Methoxyaniline hydrochloride



1-Methoxy-9,10-anthracenedione



2-Methoxybenzaldehyde



3-Methoxybenzaldehyde



4-Methoxybenzaldehyde



4-Methoxybenzamide



4-Methoxybenzeneacetaldehyde



2-Methoxybenzeneacetic acid



4-Methoxybenzeneacetic acid



4-Methoxybenzeneacetonitrile



4-Methoxy-1,2-benzenediamine



4-Methoxy-1,3-benzenediamine



2-Methoxy-1,4-benzenediamine



3-Methoxy-1,2-benzenediol



4-Methoxybenzeneethanamine



4-Methoxybenzeneethanol



2-Methoxybenzenemethanamine



4-Methoxybenzenemethanamine



2-Methoxybenzenemethanol


3-Methoxybenzenemethanol



4-Methoxybenzenemethanol



4-Methoxybenzenesulfonyl chloride



3-Methoxybenzenethiol



4-Methoxybenzenethiol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6799	2-Methoxybenzoic acid		$C_8H_8O_3$	579-75-9	152.148	pl (w)	101	200			sl H_2O; vs EtOH, eth, chl; s bz, ctc
6800	3-Methoxybenzoic acid		$C_8H_8O_3$	586-38-9	152.148	nd (w)	107	170^{10}			sl H_2O, ctc; s EtOH, eth, bz; vs chl
6801	4-Methoxybenzoic acid	*p*-Anisic acid	$C_8H_8O_3$	100-09-4	152.148		185	276.5			i H_2O; vs EtOH, MeOH, eth; s chl
6802	2-Methoxybenzonitrile		C_8H_7NO	6609-56-9	133.148		24.5	255.5	1.1063^{20}		s EtOH; vs eth
6803	3-Methoxybenzonitrile		C_8H_7NO	1527-89-5	133.148			140^{34}, 111^{13}	1.089^{25}	1.5402^{20}	
6804	4-Methoxybenzonitrile		C_8H_7NO	874-90-8	133.148	nd (w) lf (al)	61.5	256.5			i H_2O; vs EtOH, eth; s bz
6805	7-Methoxy-2*H*-1-benzopyran-2-one		$C_{10}H_8O_3$	531-59-9	176.169	lf (w, MeOH)	118.3				sl H_2O; s EtOH, eth, con sulf, alk
6806	6-Methoxy-2-benzothiazolamine		$C_8H_8N_2OS$	1747-60-0	180.227		166				
6807	2-(4-Methoxybenzoyl)benzoic acid	*o*-(*p*-Anisoyl)benzoic acid	$C_{15}H_{12}O_4$	1151-15-1	256.254	lf (w), cry (al, to)	146				vs eth, EtOH, tol
6808	2-Methoxybenzoyl chloride		$C_8H_7ClO_2$	21615-34-9	170.594			254			
6809	4-Methoxybenzoyl chloride	*p*-Anisoyl chloride	$C_8H_7ClO_2$	100-07-2	170.594	nd	24.5	262.5	1.261^{20}	1.580^{20}	s eth, ace; vs bz; sl ctc
6810	4-Methoxybenzyl acetate		$C_{10}H_{12}O_3$	104-21-2	180.200		84	270; 150^{23}	1.105^{25}		s ctc
6811	2-Methoxy-1,1'-biphenyl		$C_{13}H_{12}O$	86-26-0	184.233	pr (peth)	29	274	1.0233^{99}	1.5641^{99}	i H_2O; s EtOH, peth; sl ctc
6812	4-Methoxy-1,1'-biphenyl		$C_{13}H_{12}O$	613-37-6	184.233	pl (al)	90	157^{10}	1.0278^{100}	1.5744^{100}	i H_2O; s EtOH, eth
6813	1-Methoxy-1,3-butadiene		C_5H_8O	3036-66-6	84.117			91.5	0.8296^{20}	1.4594^{20}	s H_2O, EtOH
6814	2-Methoxy-1,3-butadiene		C_5H_8O	3588-30-5	84.117			75	0.8272^{20}	1.4442^{20}	vs ace, bz, eth, EtOH
6815	3-Methoxy-1-butanol		$C_5H_{12}O_2$	2517-43-3	104.148			157	0.923^{23}	1.4148^{25}	vs EtOH, ace; s eth; sl chl
6816	1-Methoxy-1-buten-3-yne		C_5H_6O	2798-73-4	82.101			dec 123; 39^{23}	0.906^{20}	1.4818^{20}	i H_2O; s chl
6817	Methoxychlor		$C_{16}H_{15}Cl_3O_2$	72-43-5	345.648	cry (dil al)	87		1.41^{25}		i H_2O; s EtOH, ctc; vs eth, bz
6818	Methoxycyclohexane		$C_7H_{14}O$	931-56-6	114.185	liq	-74.4	133	0.8756^{20}	1.4355^{20}	vs eth, EtOH
6819	1-Methoxy-2,4-dinitrobenzene		$C_7H_6N_2O_5$	119-27-7	198.133	nd (al or w)	94.5	206^{12}	1.3364^{131}	1.546^{15}	sl H_2O; s EtOH, eth, ace, bz; vs py
6820	1-Methoxy-3,5-dinitrobenzene	3,5-Dinitroanisole	$C_7H_6N_2O_5$	5327-44-6	198.133	nd (al)	105.3		1.558^{12}		vs ace, bz, MeOH
6821	2-Methoxy-1,2-diphenylethanone		$C_{15}H_{14}O_2$	3524-62-7	226.271	nd (lig)	49.5	188^{15}	1.1278^{14}		vs bz, eth, EtOH
6822	2-Methoxyethanol	Ethylene glycol monomethyl ether	$C_3H_8O_2$	109-86-4	76.095	liq	-85.1	124.1	0.9647^{20}	1.4024^{20}	msc H_2O, eth, bz; vs EtOH; s ace; sl chl
6823	(2-Methoxyethoxy)ethene		$C_5H_{10}O_2$	1663-35-0	102.132			107			
6824	2-[2-(2-Methoxyethoxy)ethoxy] ethanol	Triethyleneglycol monomethyl ether	$C_7H_{16}O_4$	112-35-6	164.200			246			
6825	2-Methoxyethyl acetate	Ethylene glycol monomethyl ether acetate	$C_5H_{10}O_3$	110-49-6	118.131	liq	-70	143	1.0074^{19}	1.4002^{20}	s H_2O, EtOH, eth; sl ctc
6826	2-Methoxyethyl acrylate	2-Methoxyethyl 2-propenoate	$C_6H_{10}O_3$	3121-61-7	130.141			67^{16}, 56^{12}	1.012^{20}		
6827	2-Methoxyethylamine	1-Amino-2-methoxyethane	C_3H_9NO	109-85-3	75.109			95			vs H_2O, EtOH; sl chl
6828	Methoxyethylmercuric acetate		$C_5H_{10}HgO_3$	151-38-2	318.72	nd (peth)	42				
6829	2-(2-Methoxyethyl)pyridine	Metyridine	$C_8H_{11}NO$	114-91-0	137.179			203; 96^{17}	0.988^{20}	1.4975^{20}	vs H_2O, EtOH
6830	2-Methoxyfuran		$C_5H_6O_2$	25414-22-6	98.101			110.5	1.0646^{25}	1.4468^{25}	
6831	4-Methoxyfuro[2,3-b]quinoline	Dictamnine	$C_{12}H_9NO_2$	484-29-7	199.205	pr (al)	133.5				sl H_2O; vs EtOH; s eth, chl, AcOEt
6832	12-Methoxyibogamine	Ibogaine	$C_{20}H_{26}N_2O$	83-74-9	310.432		148				s chl
6833	5-Methoxy-1*H*-indole-3-ethanamine	5-Methoxytryptamine	$C_{11}H_{14}N_2O$	608-07-1	190.241	cry (al)	121.5				
6834	*N*-[2-(5-Methoxy-1*H*-indol-3-yl) ethyl]acetamide	Melatonin	$C_{13}H_{16}N_2O_2$	73-31-4	232.278	pa ye lf (bz)	117				
6835	3-Methoxyisopropylamine	1-Methoxy-2-propanamine	$C_4H_{11}NO$	37143-54-7	89.136			97		1.4031^{25}	
6836	4-Methoxy-*N*-(4-methoxyphenyl) aniline	4,4'-Dimethoxydiphenylamine	$C_{14}H_{15}NO_2$	101-70-2	229.275	lf (EtOH)	103				
6837	*N*-Methoxymethylamine	*N*-Methoxymethanamine	C_2H_7NO	1117-97-1	61.083	liq		42.4			
6838	2-Methoxy-5-methylaniline	5-Methyl-*o*-anisidine	$C_8H_{11}NO$	120-71-8	137.179		53	235			sl H_2O, chl; s EtOH, eth, bz, peth
6839	4-Methoxy-2-methylaniline		$C_8H_{11}NO$	102-50-1	137.179	cry (lig)	29.5	248.5	1.065^{25}	1.5647^{20}	vs EtOH
6840	4-Methoxy-α-methylbenzenemethanol		$C_9H_{12}O_2$	3319-15-1	152.190			dec 310; 140^{17}	1.0794^{20}	1.5310^{25}	s ctc



2-Methoxybenzoic acid



3-Methoxybenzoic acid



4-Methoxybenzoic acid



2-Methoxybenzonitrile



3-Methoxybenzonitrile



4-Methoxybenzonitrile



7-Methoxy-2*H*-1-benzopyran-2-one



6-Methoxy-2-benzothiazolamine



2-(4-Methoxybenzoyl)benzoic acid



2-Methoxybenzoyl chloride



4-Methoxybenzoyl chloride



4-Methoxybenzyl acetate



2-Methoxy-1,1'-biphenyl



4-Methoxy-1,1'-biphenyl



1-Methoxy-1,3-butadiene



2-Methoxy-1,3-butadiene



3-Methoxy-1-butanol



1-Methoxy-1-buten-3-yne



Methoxychlor



Methoxycyclohexane



1-Methoxy-2,4-dinitrobenzene



1-Methoxy-3,5-dinitrobenzene



2-Methoxy-1,2-diphenylethanone



2-Methoxyethanol



(2-Methoxyethoxy)ethene



2-[2-(2-Methoxyethoxy)ethoxy]ethanol


2-Methoxyethyl acetate



2-Methoxyethyl acrylate



2-Methoxyethylamine



Methoxyethylmercuric acetate



2-(2-Methoxyethyl)pyridine



2-Methoxyfuran



4-Methoxyfuro[2,3-b]quinoline


12-Methoxyibogamine



5-Methoxy-1*H*-indole-3-ethanamine



N-[2-(5-Methoxy-1*H*-indol-3-yl)ethyl]acetamide



3-Methoxyisopropylamine


4-Methoxy-*N*-(4-methoxyphenyl)aniline



N-Methoxymethylamine



2-Methoxy-5-methylaniline



4-Methoxy-2-methylaniline



4-Methoxy-α-methylbenzenemethanol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6841	2-Methoxy-2-methylbutane	Methyl *tert*-pentyl ether	$C_6H_{14}O$	994-05-8	102.174			86.1	0.7660^{25}	1.3862^{25}	sl H_2O; vs eth, EtOH
6842	2-(Methoxymethyl)furan		$C_6H_8O_2$	13679-46-4	112.127			132	1.0163^{20}	1.4570^{20}	i H_2O; s EtOH; vs eth
6843	2-(Methoxymethyl)-5-nitrofuran		$C_6H_7NO_4$	586-84-5	157.125			104^{3}	1.281^{20}	1.5325^{20}	vs EtOH
6844	(Methoxymethyl)oxirane		$C_4H_8O_2$	930-37-0	88.106			113	0.9890^{20}	1.4320^{20}	vs H_2O, ace, eth, EtOH
6845	3-Methoxy-5-methyl-4-oxo-2,5-hexadienoic acid	Penicillic acid	$C_8H_{10}O_4$	90-65-3	170.163	orth or hex pl (+ 1w)	83				s H_2O, ace; vs EtOH, eth, bz; sl peth
6846	4-Methoxy-4-methyl-2-pentanone	Pentoxone	$C_7H_{14}O_2$	107-70-0	130.185			160	0.8980^{25}	1.418^{20}	
6847	2-Methoxy-4-methylphenol	Creosol	$C_8H_{10}O_2$	93-51-6	138.164	pr	5.5	221	1.098^{20}	1.5353^{25}	vs eth, EtOH
6848	1-Methoxynaphthalene		$C_{11}H_{10}O$	2216-69-5	158.196		<-10	269	1.0963^{14}	1.6940^{25}	i H_2O; s EtOH, eth, bz, chl; vs CS_2
6849	2-Methoxynaphthalene		$C_{11}H_{10}O$	93-04-9	158.196	lf (eth), pl (peth)	73.5	274			vs bz, eth, chl
6850	2-Methoxy-1,4-naphthalenedione		$C_{11}H_8O_3$	2348-82-5	188.180		183.0				
6851	4-Methoxy-1-naphthol		$C_{11}H_{10}O_2$	84-85-5	174.196		129.8				
6852	2-Methoxy-4-nitroaniline		$C_7H_8N_2O_3$	97-52-9	168.150		141.0				s DMSO
6853	2-Methoxy-5-nitroaniline	5-Nitro-*o*-anisidine	$C_7H_8N_2O_3$	99-59-2	168.150		118		1.2068^{15}		s H_2O, eth; vs EtOH, ace, bz; sl lig
6854	4-Methoxy-2-nitroaniline		$C_7H_8N_2O_3$	96-96-8	168.150	dk red pr (w or al)	129				vs H_2O, ace, eth, EtOH
6855	2-Methoxyphenol	Guaiacol	$C_7H_8O_2$	90-05-1	124.138	hex pr	32	205	1.1287^{21}	1.5429^{20}	sl H_2O; s EtOH, eth, ctc, chl
6856	3-Methoxyphenol		$C_7H_8O_2$	150-19-6	124.138		<-17	114^{5}	1.131^{25}	1.5510^{20}	sl H_2O, chl; msc EtOH, eth
6857	4-Methoxyphenol		$C_7H_8O_2$	150-76-5	124.138	pl	57	243			s H_2O, bz, ctc; vs EtOH, eth
6858	2-Methoxyphenol benzoate	Guaiacol benzoate	$C_{14}H_{12}O_3$	531-37-3	228.243		57.5				vs eth, chl
6859	2-Methoxyphenol carbonate (2:1)	Guaiacol carbonate	$C_{15}H_{14}O_5$	553-17-3	274.269	cry (al)	89				i H_2O; sl EtOH; s eth; vs chl
6860	2-Methoxyphenol phosphate (3:1)	Guaiacol phosphate	$C_{21}H_{21}O_7P$	563-03-1	416.362		91	277^{3}			vs ace, tol, chl
6861	5-[(2-Methoxyphenoxy)methyl]-2-oxazolidinone	Mephenoxalone	$C_{11}H_{13}NO_4$	70-07-5	223.226		144				
6862	3-(2-Methoxyphenoxy)-1,2-propanediol	Guaifenesin	$C_{10}H_{14}O_4$	93-14-1	198.216	orth pr (eth, eth-peth)	78.5	215^{19}, $127^{0.2}$			s H_2O, bz, chl; vs EtOH; i peth
6863	*N*-(2-Methoxyphenyl)acetamide	*o*-Acetanisidine	$C_9H_{11}NO_2$	93-26-5	165.189	nd (w)	87.5	304			vs H_2O, EtOH; s eth, ace, HOAc
6864	*N*-(3-Methoxyphenyl)acetamide	*m*-Acetanisidine	$C_9H_{11}NO_2$	588-16-9	165.189	nd or pl (w)	81				vs H_2O, EtOH; s eth, ace
6865	*N*-(4-Methoxyphenyl)acetamide	*p*-Acetanisidine	$C_9H_{11}NO_2$	51-66-1	165.189	pl (w)	131				vs ace, EtOH, chl
6866	2-Methoxyphenyl acetate	2-Acetoxyanisole	$C_9H_{10}O_3$	613-70-7	166.173		31.5	123^{13}	1.1285^{25}	1.5101^{25}	i H_2O; s EtOH, eth
6867	4-(4-Methoxyphenyl)-3-buten-2-one		$C_{11}H_{12}O_2$	943-88-4	176.212	lf (al, eth, HOAc)	74.0	187.5^{19}			i H_2O; vs EtOH, eth; s bz, HOAc, sulf
6868	2-Methoxy-1-phenylethanone		$C_9H_{10}O_2$	4079-52-1	150.174	ye liq	8	245; 125^{19}	1.0897^{20}	1.5393^{20}	sl H_2O; s EtOH, ace
6869	1-(3-Methoxyphenyl)ethanone		$C_9H_{10}O_2$	586-37-8	150.174		95.5	240	1.0343^{19}	1.5410^{20}	s H_2O, EtOH, ace, ctc
6870	2-(4-Methoxyphenyl)-1*H*-indene-1,3(2*H*)-dione	Anisindione	$C_{16}H_{12}O_3$	117-37-3	252.264	pa ye cry (HOAc, al)	156.5				
6871	4-Methoxyphenyl isocyanate		$C_8H_7NO_2$	5416-93-3	149.148			110^{10}			
6872	2-Methoxyphenyl isothiocyanate	1-Isothiocyanato-2-methoxybenzene	C_8H_7NOS	3288-04-8	165.213			264; 131^{11}	1.1878^{20}	1.6458^{20}	
6873	*N*-(4-Methoxyphenyl)-3-oxobutanamide		$C_{11}H_{13}NO_3$	5437-98-9	207.226		117.3				s EtOH, chl; sl eth
6874	2-Methoxyphenyl pentanoate	Guaiacol valerate	$C_{12}H_{16}O_3$	531-39-5	208.253			265	1.05^{25}		vs bz, eth, EtOH
6875	(4-Methoxyphenyl)phenyldiazene		$C_{13}H_{12}N_2O$	2396-60-3	212.246	oran-red pl, lf (al, peth)	56	340	1.12^{75}		i H_2O; s EtOH, eth, ace
6876	*N*-(*p*-Methoxyphenyl)-*p*-phenylenediamine	*N*-(4-Methoxyphenyl)-1,4-benzenediamine	$C_{13}H_{14}N_2O$	101-64-4	214.262	nd	102	238^{12}			sl H_2O, peth; vs bz, eth, EtOH
6877	*N*-(4-Methoxyphenyl)-*p*-phenylenediamine hydrochloride		$C_{13}H_{15}ClN_2O$	3566-44-7	250.723	cry	245 dec				
6878	(4-Methoxyphenyl) phenylmethanone		$C_{14}H_{12}O_2$	611-94-9	212.244	pr (eth)	61.5	355; 168^{12}			i H_2O; vs EtOH, eth; s ace, bz, HOAc
6879	3-(4-Methoxyphenyl)-1-phenyl-2-propen-1-one		$C_{16}H_{14}O_2$	959-33-1	238.281	ye nd (al)	79	187^{19}			i H_2O; vs EtOH; s eth, ctc, chl, HOAc



2-Methoxy-2-methylbutane



2-(Methoxymethyl)furan



2-(Methoxymethyl)-5-nitrofuran



(Methoxymethyl)oxirane



3-Methoxy-5-methyl-4-oxo-2,5-hexadienoic acid



4-Methoxy-4-methyl-2-pentanone



2-Methoxy-4-methylphenol



1-Methoxynaphthalene



2-Methoxynaphthalene



2-Methoxy-1,4-naphthalenedione



4-Methoxy-1-naphthol



2-Methoxy-4-nitroaniline



2-Methoxy-5-nitroaniline



4-Methoxy-2-nitroaniline



2-Methoxyphenol



3-Methoxyphenol



4-Methoxyphenol



2-Methoxyphenol benzoate



2-Methoxyphenol carbonate (2:1)



2-Methoxyphenol phosphate (3:1)



5-[(2-Methoxyphenoxy)methyl]-2-oxazolidinone



3-(2-Methoxyphenoxy)-1,2-propanediol



N-(2-Methoxyphenyl)acetamide



N-(3-Methoxyphenyl)acetamide



N-(4-Methoxyphenyl)acetamide



2-Methoxyphenyl acetate



4-(4-Methoxyphenyl)-3-buten-2-one



2-Methoxy-1-phenylethanone



1-(3-Methoxyphenyl)ethanone



2-(4-Methoxyphenyl)-1*H*-indene-1,3(2*H*)-dione



4-Methoxyphenyl isocyanate



2-Methoxyphenyl isothiocyanate



N-(4-Methoxyphenyl)-3-oxobutanamide



2-Methoxyphenyl pentanoate


(4-Methoxyphenyl)phenyldiazene



N-(*p*-Methoxyphenyl)-*p*-phenylenediamine



N-(4-Methoxyphenyl)-*p*-phenylenediamine hydrochloride



(4-Methoxyphenyl)phenylmethanone



3-(4-Methoxyphenyl)-1-phenyl-2-propen-1-one


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6880	1-(4-Methoxyphenyl)-1-propanone	Ethyl 4-methoxyphenyl ketone	$C_{10}H_{12}O_2$	121-97-1	164.201		25.5	266	1.0798^{16}		s ctc
6881	1-(4-Methoxyphenyl)-2-propanone	Anisyl methyl ketone	$C_{10}H_{12}O_2$	122-84-9	164.201		<-15	268	1.0694^{17}	1.5253^{20}	vs eth, EtOH
6882	*trans*-3-(4-Methoxyphenyl)-2-propenoic acid	*trans*-4-Methoxycinnamic acid	$C_{10}H_{10}O_3$	943-89-5	178.184		173.5				sl H_2O, EtOH, bz, DMSO; s ctc, HOAc
6883	*trans*-1-Methoxy-4-(2-phenylvinyl)benzene		$C_{15}H_{14}O$	1694-19-5	210.271		136.5	142.5^{15}			i H_2O; vs EtOH, eth, ace, bz; s peth
6884	1-Methoxy-1,2-propadiene	Methoxyallene	C_4H_6O	13169-00-1	70.090	oil		51.5			
6885	3-Methoxy-1-propanamine		$C_4H_{11}NO$	5332-73-0	89.136			117.5	0.8727^{20}	1.4391^{20}	s H_2O, ace, bz, ctc, chl, MeOH
6886	3-Methoxy-1,2-propanediol	Glycerol 3-methyl ether	$C_4H_{10}O_3$	623-39-2	106.120	hyg liq		220	1.114^{20}	1.442^{25}	vs H_2O, EtOH, ace; s eth
6887	3-Methoxypropanenitrile		C_4H_7NO	110-67-8	85.105			163	0.9379^{20}	1.4043^{20}	s EtOH, eth, chl
6888	2-Methoxy-1-propanol		$C_4H_{10}O_2$	1589-47-5	90.121			130	0.938^{20}	1.4070^{20}	
6889	1-Methoxy-2-propanone	Methoxyacetone	$C_4H_8O_2$	5878-19-3	88.106			116	0.957^{25}	1.3970^{20}	
6890	2-Methoxy-1-propene		C_4H_8O	116-11-0	72.106			38	0.7372^{20}		
6891	3-Methoxy-1-propene		C_4H_8O	627-40-7	72.106			44	0.77^{11}	1.3778^{20}	i H_2O; msc EtOH, eth; s ace
6892	*trans*-1-Methoxy-4-(1-propenyl) benzene	Anethole	$C_{10}H_{12}O$	4180-23-8	148.201	col oily liq	22.5	235; 81$^{2.3}$	0.9882^{20}	1.5615^{20}	sl H_2O; msc EtOH, eth; s ace; vs bz
6893	1-Methoxy-4-(2-propenyl)benzene	Estragole	$C_{10}H_{12}O$	140-67-0	148.201			215.5	0.965^{25}	1.5195^{20}	vs EtOH, chl
6894	*cis*-2-Methoxy-4-(1-propenyl) phenol		$C_{10}H_{12}O_2$	5912-86-7	164.201			134^{13}	1.0837^{20}	1.5726^{20}	sl H_2O; s EtOH, eth
6895	*trans*-2-Methoxy-4-(1-propenyl) phenol		$C_{10}H_{12}O_2$	5932-68-3	164.201		33.5	141^{13}	1.0852^{20}	1.5784^{20}	sl H_2O; s EtOH, eth, chl
6896	1-Methoxy-4-propylbenzene		$C_{10}H_{14}O$	104-45-0	150.217			211.5	0.9472^{20}	1.5045^{20}	sl H_2O; s EtOH, ace, bz, chl; vs eth
6897	2-Methoxy-4-propylphenol		$C_{10}H_{14}O_2$	2785-87-7	166.217			121^{10}			
6898	3-Methoxy-1-propyne		C_4H_6O	627-41-8	70.090			63	0.83^{12}	1.5035^{20}	vs eth, EtOH
6899	5-Methoxypsoralen	Bergaptene	$C_{12}H_8O_4$	484-20-8	216.190	nd (EtOH)	188				i H_2O; sl EtOH, bz, chl
6900	6-Methoxy-3-pyridinamine		$C_6H_8N_2O$	6628-77-9	124.140		30	125^{10}, 87^{1}		1.5745^{20}	
6901	2-Methoxypyridine		C_6H_7NO	1628-89-3	109.126			142.5	1.0457^{20}	1.5042^{20}	
6902	3-Methoxypyridine		C_6H_7NO	7295-76-3	109.126	liq		178.5; 65^{15}	1.083	1.5180^{20}	
6903	4-Methoxypyridine		C_6H_7NO	620-08-6	109.126			192; 95^{45}			msc H_2O
6904	6-Methoxyquinoline		$C_{10}H_9NO$	5263-87-6	159.184	hyg lf	26.5	306; 153^{12}	1.152^{20}		s EtOH, eth, chl, dil HCl
6905	6-Methoxy-4-quinolinecarboxylic acid	Quininic acid	$C_{11}H_9NO_3$	86-68-0	203.194	pa ye pr (dil al)	285 dec	sub			sl H_2O, eth, bz, tfa; i chl; s EtOH
6906	2-Methoxy-1,3,5-trinitrobenzene	Methyl picrate	$C_7H_5N_3O_7$	606-35-9	243.131	nd (dil MeOH)	69		1.4947^{80}		i H_2O; vs EtOH, chl, bz; s eth
6907	(2-Methoxyvinyl)benzene		$C_9H_{10}O$	4747-15-3	134.174			211.5	0.9894^{23}	1.5620^{24}	
6908	Methscopolamine bromide	Scopolamine methobromide	$C_{18}H_{24}BrNO_4$	155-41-9	398.293	cry (EtOH)	215 dec				s H_2O; sl EtOH
6909	Methyl abietate		$C_{21}H_{32}O_2$	127-25-3	316.478	pa ye lf (liq)		225^{16}	1.049^{20}	1.5344	i H_2O; s EtOH, HOAc
6910	*N*-Methylacetamide		C_3H_7NO	79-16-3	73.094		28	205	0.9371^{25}	1.4301^{20}	vs ace, bz, eth, EtOH
6911	4-Methylacetanilide		$C_9H_{11}NO$	103-89-9	149.189	mcl cry or nd (dil al)	152	307	1.2120^{15}		vs eth, EtOH
6912	Methyl acetate		$C_3H_6O_2$	79-20-9	74.079	liq	-98.25	56.87	0.9342^{20}	1.3614^{20}	vs H_2O, eth, EtOH
6913	Methyl acetoacetate		$C_5H_8O_3$	105-45-3	116.116		27.5	171.7	1.0762^{20}	1.4184^{20}	vs H_2O; msc EtOH, eth; s ctc
6914	4-Methylacetophenone		$C_9H_{10}O$	122-00-9	134.174	nd	28	226; 93.5^{7}	1.0051^{20}	1.5335^{20}	vs bz, eth, EtOH, chl
6915	Methyl 2-(acetyloxy)benzoate	Methyl *o*-acetylsalicylate	$C_{10}H_{10}O_4$	580-02-9	194.184	pl (peth)	51.5	135^{9}			vs eth, EtOH, chl
6916	Methyl acrylate	Methyl propenoate	$C_4H_6O_2$	96-33-3	86.090	liq	<-75	80.7	0.9535^{20}	1.4040^{20}	sl H_2O; s EtOH, eth, ace, bz, chl
6917	2-Methylacrylonitrile	2-Methylpropenenitrile	C_4H_5N	126-98-7	67.090	liq	-35.8	90.3	0.8001^{20}	1.4003^{20}	sl H_2O, chl; msc EtOH, eth, ace, tol
6918	2-Methylalanine	α-Aminoisobutyric acid	$C_4H_9NO_2$	62-57-7	103.120	mcl pr	335	sub 280			vs H_2O; sl EtOH; i eth
6919	5-Methyl-3-allyl-2,4-oxazolidinedione	Aloxidone	$C_7H_9NO_3$	526-35-2	155.151			138^{35}, 86$^{0.5}$		1.4688^{25}	



1-(4-Methoxyphenyl)-1-propanone



1-(4-Methoxyphenyl)-2-propanone



trans-3-(4-Methoxyphenyl)-2-propenoic acid


trans-1-Methoxy-4-(2-phenylvinyl)benzene



1-Methoxy-1,2-propadiene


3-Methoxy-1-propanamine



3-Methoxy-1,2-propanediol



3-Methoxypropanenitrile



2-Methoxy-1-propanol



1-Methoxy-2-propanone



2-Methoxy-1-propene



3-Methoxy-1-propene



trans-1-Methoxy-4-(1-propenyl)benzene



1-Methoxy-4-(2-propenyl)benzene



cis-2-Methoxy-4-(1-propenyl)phenol



trans-2-Methoxy-4-(1-propenyl)phenol



1-Methoxy-4-propylbenzene



2-Methoxy-4-propylphenol



3-Methoxy-1-propyne



5-Methoxypsoralen



6-Methoxy-3-pyridinamine



2-Methoxypyridine



3-Methoxypyridine



4-Methoxypyridine



6-Methoxyquinoline


6-Methoxy-4-quinolinecarboxylic acid



2-Methoxy-1,3,5-trinitrobenzene


(2-Methoxyvinyl)benzene



Methscopolamine bromide



Methyl abietate



N-Methylacetamide



4-Methylacetanilide



Methyl acetate



Methyl acetoacetate



4-Methylacetophenone


Methyl 2-(acetyloxy)benzoate


Methyl acrylate



2-Methylacrylonitrile



2-Methylalanine



5-Methyl-3-allyl-2,4-oxazolidinedione


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6920	Methylamine	Methanamine	CH_5N	74-89-5	31.058	col gas	-93.5	-6.32	0.656^{25} (p>1 atm)		vs H_2O; s EtOH, ace, bz; msc eth
6921	Methylamine hydrochloride	Methanamine hydrochloride	CH_6ClN	593-51-1	67.519	hyg tetr tab (al)	227.5	227^{15}			s H_2O, EtOH; i chl, ace
6922	1-(Methylamino)-9,10-anthracenedione		$C_{15}H_{11}NO_2$	82-38-2	237.254	ye-red nd	171.0				s EtOH, bz, chl, HOAc
6923	Methyl 2-aminobenzoate	Methyl anthranilate	$C_8H_9NO_2$	134-20-3	151.163		24.5	256	1.1682^{10}	1.5810	sl H_2O; vs EtOH, eth
6924	Methyl 3-aminobenzoate		$C_8H_9NO_2$	4518-10-9	151.163		39	152^{11}	1.232^{20}		vs EtOH, eth, bz, chl; s lig; sl peth
6925	Methyl 4-aminobenzoate		$C_8H_9NO_2$	619-45-4	151.163	lf or nd (aq MeOH)	113.0				s chl
6926	2-(Methylamino)benzoic acid		$C_8H_9NO_2$	119-68-6	151.163	pl (al or lig)	180.5	$80^{0.01}$			sl H_2O; vs EtOH, eth, bz, chl
6927	3-(Methylamino)benzoic acid		$C_8H_9NO_2$	51524-84-6	151.163	pl (peth)	127				vs ace, bz, EtOH, chl
6928	4-(Methylamino)benzoic acid		$C_8H_9NO_2$	10541-83-0	151.163	nd (bz, w, dil al)	168				s H_2O, bz, AcOEt; vs EtOH, eth; sl tfa
6929	Methyl 3-amino-2-butenoate		$C_5H_9NO_2$	14205-39-1	115.131						s chl
6930	*N*-[(Methylamino)carbonyl] acetamide		$C_4H_8N_2O_2$	623-59-6	116.119	tcl (w, al), pr (w)	180.5	dec			s H_2O, chl; sl EtOH, eth
6931	2-(Methylamino)-2-deoxy-α-*L*-glucopyranose	*N*-Methyl-α-*L*-glucosamine	$C_7H_{15}NO_5$	42852-95-9	193.198	glass					s MeOH
6932	2-(Methylamino)ethanesulfonic acid	*N*-Methyltaurine	$C_3H_9NO_3S$	107-68-6	139.173		241.5				vs H_2O; i EtOH, eth
6933	4-[2-(Methylamino)ethyl]-1,2-benzenediol	Deoxyepinephrine	$C_9H_{13}NO_2$	501-15-5	167.205		188.5				
6934	Methyl 3-amino-4-hydroxybenzoate	Orthocaine	$C_8H_9NO_3$	536-25-4	167.162	nd (bz or HOAc)	143				i H_2O; vs EtOH; s eth, alk; sl bz
6935	4-(Methylamino)phenol sulfate		$C_{14}H_{20}N_2O_6S$	1936-57-8	344.383	cry	260 dec				sl EtOH; i eth
6936	3-(Methylamino)propanenitrile		$C_4H_8N_2$	693-05-0	84.120			102^{49}, 74^{16}	0.8992^{20}	1.4320^{20}	s H_2O, ace, bz, chl, MeOH
6937	4-[2-(Methylamino)propyl]phenol	Pholedrine	$C_{10}H_{15}NO$	370-14-9	165.232	cry (MeOH)	161				vs eth, EtOH
6938	2-Methylaniline	*o*-Toluidine	C_7H_9N	95-53-4	107.153	liq	-14.41	200.3	0.9984^{20}	1.5725^{20}	sl H_2O; msc EtOH, eth, ctc
6939	3-Methylaniline	*m*-Toluidine	C_7H_9N	108-44-1	107.153	liq	-31.3	203.3	0.9889^{20}	1.5681^{20}	vs ace, bz, eth, EtOH
6940	4-Methylaniline	*p*-Toluidine	C_7H_9N	106-49-0	107.153	lf (w+1)	43.6	200.4	0.9619^{20}	1.5534^{45}	sl H_2O; vs EtOH, py; s eth, ace, ctc
6941	*N*-Methylaniline		C_7H_9N	100-61-8	107.153	liq	-57	196.2	0.9891^{20}	1.5684^{20}	i H_2O; s EtOH, eth, ctc, chl
6942	2-Methylaniline, hydrochloride	*o*-Toluidine, hydrochloride	$C_7H_{10}ClN$	636-21-5	143.614	mcl pr (w)	215				vs H_2O, EtOH
6943	4-Methylaniline, hydrochloride		$C_7H_{10}ClN$	540-23-8	143.614	mcl nd (eth-HOAc)	244.5	258	1.1930^{18}		vs H_2O, EtOH, HOAc
6944	2-Methylanisole		$C_8H_{10}O$	578-58-5	122.164	liq	-34.1	171	0.985^{25}	1.5161^{20}	i H_2O; s EtOH, eth, ace, ctc
6945	3-Methylanisole		$C_8H_{10}O$	100-84-5	122.164	liq	-47	175.5	0.969^{25}	1.5130^{20}	i H_2O; s EtOH, eth, ace, bz; sl ctc
6946	4-Methylanisole		$C_8H_{10}O$	104-93-8	122.164	liq	-32	175.5	0.969^{25}	1.5112^{20}	i H_2O; s EtOH, eth, chl
6947	1-Methylanthracene		$C_{15}H_{12}$	610-48-0	192.256	bl nd (MeOH) lf (al)	85.5	199.5	1.0471^{99}	1.6802^{99}	i H_2O; s EtOH, eth, bz, chl, sulf
6948	2-Methylanthracene		$C_{15}H_{12}$	613-12-7	192.256	grn bl flr lf (sub)	209	sub	1.80^{0}		i H_2O, ace; sl EtOH, eth; s bz, CS_2
6949	9-Methylanthracene		$C_{15}H_{12}$	779-02-2	192.256	ye nd (dil al) pr (bz, al)	81.5	196^{12}	1.065^{99}	1.6959^{99}	s EtOH, eth, ace, bz, chl
6950	2-Methyl-9,10-anthracenedione	2-Methylanthraquinone	$C_{15}H_{10}O_2$	84-54-8	222.239	ye nd (al, HOAc)	177	sub			vs bz, EtOH, HOAc
6951	Methylarsine		CH_5As	593-52-2	91.973	col gas	-143	2			vs ace, eth, EtOH
6952	9-Methyl-9-azabicyclo[3.3.1] nonan-3-one	Pseudopelletierine	$C_9H_{15}NO$	552-70-5	153.221	orth pr (peth)	54	246	1.001^{100}	1.4760^{100}	vs H_2O, eth, EtOH
6953	8-Methyl-8-azabicyclo[3.2.1] octane	Tropane	$C_8H_{15}N$	529-17-9	125.212			166	0.9251^{15}		
6954	8-Methyl-8-azabicyclo[3.2.1] octan-3-one		$C_8H_{13}NO$	532-24-1	139.195		43	227; 113^{25}	1.9872^{100}	1.4598^{100}	s EtOH, eth, ace, bz, peth; sl chl
6955	Methyl azide		CH_3N_3	624-90-8	57.055			exp 20.5	0.869^{15}		
6956	Methylazoxymethanol acetate		$C_4H_8N_2O_3$	592-62-1	132.118			191; $49^{0.45}$			



Methylamine



Methylamine hydrochloride



1-(Methylamino)-9,10-anthracenedione



Methyl 2-aminobenzoate



Methyl 3-aminobenzoate



Methyl 4-aminobenzoate



2-(Methylamino)benzoic acid



3-(Methylamino)benzoic acid



4-(Methylamino)benzoic acid



Methyl 3-amino-2-butenoate



N-[(Methylamino)carbonyl]acetamide



2-(Methylamino)-2-deoxy-α-*L*-glucopyranose



2-(Methylamino)ethanesulfonic acid


4-[2-(Methylamino)ethyl]-1,2-benzenediol


Methyl 3-amino-4-hydroxybenzoate



4-(Methylamino)phenol sulfate



3-(Methylamino)propanenitrile



4-[2-(Methylamino)propyl]phenol



2-Methylaniline



3-Methylaniline



4-Methylaniline



N-Methylaniline



2-Methylaniline, hydrochloride



4-Methylaniline, hydrochloride



2-Methylanisole



3-Methylanisole


4-Methylanisole



1-Methylanthracene



2-Methylanthracene



9-Methylanthracene


2-Methyl-9,10-anthracenedione



Methylarsine


9-Methyl-9-azabicyclo[3.3.1]nonan-3-one



8-Methyl-8-azabicyclo[3.2.1]octane



8-Methyl-8-azabicyclo[3.2.1]octan-3-one



Methyl azide



Methylazoxymethanol acetate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6957	2-Methylbenzaldehyde	*o*-Tolualdehyde	C_8H_8O	529-20-4	120.149			200; 94[10]	1.0328[20]	1.5462[20]	sl H_2O, ctc; s EtOH, eth, bz; vs ace
6958	3-Methylbenzaldehyde	*m*-Tolualdehyde	C_8H_8O	620-23-5	120.149			199	1.0189[21]	1.5413[21]	sl H_2O; msc EtOH, eth; vs ace; s bz, chl
6959	4-Methylbenzaldehyde	*p*-Tolualdehyde	C_8H_8O	104-87-0	120.149			204; 106[10]	1.0194[17]	1.5454[20]	sl H_2O; msc EtOH, eth, ace; vs chl
6960	2-Methylbenzamide	*o*-Toluamide	C_8H_9NO	527-85-5	135.163		147				sl H_2O, eth, tfa, bz; vs EtOH
6961	4-Methylbenzamide	*p*-Toluamide	C_8H_9NO	619-55-6	135.163		162.5				sl H_2O, bz, chl; vs EtOH, eth; s tfa
6962	*N*-Methylbenzamide		C_8H_9NO	613-93-4	135.163		82	291; 167[12]			s EtOH, ace
6963	7-Methylbenz[a]anthracene		$C_{19}H_{14}$	2541-69-7	242.314	ye pl (al)	141				i H_2O; s EtOH, eth, ace, ctc, HOAc, CS_2
6964	8-Methylbenz[a]anthracene		$C_{19}H_{14}$	2381-31-9	242.314	pl (bz-al), nd (bz-lig)	156.5	272[3], 160[0.1]	1.2310[0]		i H_2O; s EtOH, eth, bz, xyl
6965	9-Methylbenz[a]anthracene		$C_{19}H_{14}$	2381-16-0	242.314	nd (al)	152.5				i H_2O; s EtOH, eth, ctc, chl, CS_2, xyl
6966	10-Methylbenz[a]anthracene		$C_{19}H_{14}$	2381-15-9	242.314		184				i H_2O; s EtOH, HOAc
6967	12-Methylbenz[a]anthracene		$C_{19}H_{14}$	2422-79-9	242.314	pl (al)	150.5				i H_2O; s EtOH, CS_2, HOAc
6968	2-Methylbenzeneacetaldehyde		$C_9H_{10}O$	10166-08-2	134.174			221; 92[10]	1.0241[10]		vs eth, EtOH, chl
6969	4-Methylbenzeneacetaldehyde		$C_9H_{10}O$	104-09-6	134.174		40	221.5	1.0052[20]	1.5255[20]	vs eth, EtOH, chl
6970	α-Methylbenzeneacetaldehyde		$C_9H_{10}O$	93-53-8	134.174			203.5	1.0089[20]	1.5176[20]	vs EtOH
6971	2-Methylbenzeneacetic acid		$C_9H_{10}O_2$	644-36-0	150.174	nd (w)	89				s H_2O, chl
6972	3-Methylbenzeneacetic acid		$C_9H_{10}O_2$	621-36-3	150.174	nd (w)	62	121[26]			s H_2O, chl
6973	4-Methylbenzeneacetic acid		$C_9H_{10}O_2$	622-47-9	150.174	nd or pl (al, w)	93	265			vs bz, eth, EtOH
6974	α-Methylbenzeneacetic acid, (±)		$C_9H_{10}O_2$	2328-24-7	150.174		<-20	263	1.1[0]	1.5237[20]	
6975	4-Methylbenzeneacetonitrile		C_9H_9N	2947-61-7	131.174		18	242.5	0.992[25]	1.5190[20]	i H_2O; s EtOH, eth, bz, ctc
6976	α-Methylbenzeneacetonitrile		C_9H_9N	1823-91-2	131.174			231	0.9854[20]	1.5095[25]	vs eth, EtOH
6977	3-Methyl-1,2-benzenediamine	Toluene-2,3-diamine	$C_7H_{10}N_2$	2687-25-4	122.167		63.5	255			vs ace, bz, EtOH
6978	4-Methyl-1,2-benzenediamine	Toluene-3,4-diamine	$C_7H_{10}N_2$	496-72-0	122.167	pl (lig)	89.5	265			vs H_2O; s lig
6979	2-Methyl-1,3-benzenediamine	Toluene-2,6-diamine	$C_7H_{10}N_2$	823-40-5	122.167	pr (bz, w)	106				s H_2O, EtOH, bz
6980	2-Methyl-1,4-benzenediamine	Toluene-2,5-diamine	$C_7H_{10}N_2$	95-70-5	122.167	pl (bz)	64	273.5			s H_2O, EtOH, eth; sl bz, HOAc
6981	3-Methyl-1,2-benzenediol		$C_7H_8O_2$	488-17-5	124.138	lf (bz)	68	248			s H_2O, EtOH, bz, chl
6982	4-Methyl-1,2-benzenediol		$C_7H_8O_2$	452-86-8	124.138	lf (bz-lig), pr (bz)	65	258	1.1287[74]	1.5425[74]	s H_2O, EtOH, eth, ace, chl; sl lig
6983	2-Methyl-1,3-benzenediol		$C_7H_8O_2$	608-25-3	124.138	pr (bz)	120	265			vs H_2O, bz, eth, EtOH
6984	4-Methyl-1,3-benzenediol		$C_7H_8O_2$	496-73-1	124.138	cry (bz-peth)	105	270			s H_2O, EtOH, eth; sl bz, peth
6985	5-Methyl-1,3-benzenediol	Orcinol	$C_7H_8O_2$	504-15-4	124.138	pr(w+1), lf(chl)	107	287	1.290[4]		s H_2O, EtOH, eth, bz; sl lig, peth
6986	2-Methyl-1,4-benzenediol		$C_7H_8O_2$	95-71-6	124.138		125	283; 163[11]			vs H_2O, EtOH, eth; s ace; sl bz, lig
6987	4-Methyl-1,2-benzenedithiol	Toluene-3,4-dithiol	$C_7H_8S_2$	496-74-2	156.269		29				s chl
6988	β-Methylbenzeneethanamine		$C_9H_{13}N$	582-22-9	135.206			210	0.9433[4]	1.5255[20]	vs bz, eth, EtOH
6989	*N*-Methylbenzeneethanamine		$C_9H_{13}N$	589-08-2	135.206			206	0.93[25]	1.5162[20]	
6990	2-Methylbenzeneethanol		$C_9H_{12}O$	19819-98-8	136.190		1.0	243.5	1.016[25]	1.5355[20]	
6991	4-Methylbenzeneethanol		$C_9H_{12}O$	699-02-5	136.190			244.5; 94[6]	1.0028[20]	1.5267[20]	
6992	2-Methylbenzenemethanamine		$C_8H_{11}N$	89-93-0	121.180	liq	-30	206; 81[15]	0.9766[19]	1.5436[19]	
6993	3-Methylbenzenemethanamine		$C_8H_{11}N$	100-81-2	121.180			203.5	0.966[25]	1.5360[20]	
6994	4-Methylbenzenemethanamine		$C_8H_{11}N$	104-84-7	121.180		12.5	195	0.952[20]	1.5340[20]	
6995	*N*-Methylbenzenemethanamine		$C_8H_{11}N$	103-67-3	121.180			180.5	0.9442[18]		vs H_2O
6996	α-Methylbenzenemethanol	1-Phenylethanol	$C_8H_{10}O$	98-85-1	122.164		20	205	1.013[25]	1.5265[20]	i H_2O; vs EtOH, eth
6997	2-Methylbenzenemethanol	*o*-Tolyl alcohol	$C_8H_{10}O$	89-95-2	122.164	nd (peth-eth)	38	224; 118[20]	1.023[40]		vs eth, EtOH, chl



2-Methylbenzaldehyde



3-Methylbenzaldehyde



4-Methylbenzaldehyde



2-Methylbenzamide



4-Methylbenzamide



N-Methylbenzamide



7-Methylbenz[a]anthracene



8-Methylbenz[a]anthracene



9-Methylbenz[a]anthracene



10-Methylbenz[a]anthracene



12-Methylbenz[a]anthracene



2-Methylbenzeneacetaldehyde



4-Methylbenzeneacetaldehyde



α-Methylbenzeneacetaldehyde



2-Methylbenzeneacetic acid



3-Methylbenzeneacetic acid



4-Methylbenzeneacetic acid



α-Methylbenzeneacetic acid, (±)



4-Methylbenzeneacetonitrile



α-Methylbenzeneacetonitrile



3-Methyl-1,2-benzenediamine



4-Methyl-1,2-benzenediamine



2-Methyl-1,3-benzenediamine



2-Methyl-1,4-benzenediamine



3-Methyl-1,2-benzenediol



4-Methyl-1,2-benzenediol



2-Methyl-1,3-benzenediol



4-Methyl-1,3-benzenediol



5-Methyl-1,3-benzenediol



2-Methyl-1,4-benzenediol



4-Methyl-1,2-benzenedithiol



β-Methylbenzeneethanamine



N-Methylbenzeneethanamine



2-Methylbenzeneethanol



4-Methylbenzeneethanol



2-Methylbenzenemethanamine


3-Methylbenzenemethanamine



4-Methylbenzenemethanamine



N-Methylbenzenemethanamine



α-Methylbenzenemethanol



2-Methylbenzenemethanol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
6998	3-Methylbenzenemethanol	*m*-Tolyl alcohol	$C_8H_{10}O$	587-03-1	122.164		<-20	215.5	0.9157[17]		sl H_2O; vs EtOH, eth; s chl
6999	4-Methylbenzenemethanol	*p*-Tolyl alcohol	$C_8H_{10}O$	589-18-4	122.164	nd (lig)	61.5	217	0.978[22]		vs eth, EtOH
7000	α-Methylbenzenemethanol, acetate		$C_{10}H_{12}O_2$	93-92-5	164.201	oil		109[18]			
7001	4-Methylbenzenepropanal		$C_{10}H_{12}O$	5406-12-2	148.201			223	0.999[14]	1.525[14]	
7002	α-Methylbenzenepropanamine	1-Methyl-3-phenylpropylamine	$C_{10}H_{15}N$	22374-89-6	149.233		143	223; 101[14]	0.9289[15]	1.5152[20]	vs EtOH
7003	β-Methylbenzenepropanoic acid, (±)		$C_{10}H_{12}O_2$	772-17-8	164.201		46.5	168[14]	1.0701[20]	1.5155[20]	sl H_2O; s peth
7004	α-Methylbenzenepropanol		$C_{10}H_{14}O$	2344-70-9	150.217			239; 123[15]	0.9899[16]	1.517[16]	
7005	4-Methylbenzenesulfinic acid	*p*-Toluenesulfinic acid	$C_7H_8O_2S$	536-57-2	156.203	orth pl or nd (w)	86.5				s H_2O; vs EtOH, eth; sl bz
7006	4-Methylbenzenesulfinyl chloride		C_7H_7ClOS	10439-23-3	174.648	nd	57	113[3.5]			vs chl
7007	2-Methylbenzenesulfonamide		$C_7H_9NO_2S$	88-19-7	171.217	oct cry (al), pr (w)	158.7	214[10]			sl H_2O, eth, DMSO; s EtOH
7008	4-Methylbenzenesulfonamide	*p*-Toluenesulfonamide	$C_7H_9NO_2S$	70-55-3	171.217	mcl pl (w+2)	138	214[10]			sl H_2O, eth; s EtOH
7009	Methyl benzenesulfonate		$C_7H_8O_3S$	80-18-2	172.202		4.5	150[15]	1.2730[17]	1.5151[20]	sl H_2O; vs EtOH, eth, chl
7010	2-Methylbenzenesulfonic acid		$C_7H_8O_3S$	88-20-0	172.202	hyg pl (w+2)	67.5	128.8[25]			vs H_2O; s EtOH; i eth
7011	2-Methylbenzenesulfonyl chloride	*o*-Toluenesulfonyl chloride	$C_7H_7ClO_2S$	133-59-5	190.648		10.2	154[36]	1.3383[20]	1.5565[20]	i H_2O; s EtOH, eth, bz, ctc
7012	2-Methylbenzenethiol		C_7H_8S	137-06-4	124.204		15	195	1.041[20]	1.570[20]	i H_2O; s EtOH; vs eth
7013	3-Methylbenzenethiol		C_7H_8S	108-40-7	124.204	liq	-20	195	1.044[20]	1.572[20]	i H_2O; s EtOH; msc eth
7014	4-Methylbenzenethiol		C_7H_8S	106-45-6	124.204		43	195	1.0220[51]		i H_2O; s EtOH, chl; vs eth
7015	1-Methyl-1*H*-benzimidazole		$C_8H_8N_2$	1632-83-3	132.163	nd (peth), pl (al)	66	286	1.1254[20]	1.6013[7]	s peth
7016	2-Methyl-1*H*-benzimidazole		$C_8H_8N_2$	615-15-6	132.163	pr or nd (w)	177.8				s H_2O; sl EtOH, eth; i bz
7017	Methyl benzoate		$C_8H_8O_2$	93-58-3	136.149	liq	-12.4	199	1.0837[25]	1.5164[20]	i H_2O; s EtOH, ctc, MeOH; msc eth
7018	Methyl 1,3-benzodioxole-5-carboxylate		$C_9H_8O_4$	326-56-7	180.158	nd or lf (peth)	53	dec 273			vs eth, EtOH
7019	2-Methylbenzofuran		C_9H_8O	4265-25-2	132.159			197.5	1.0540[20]	1.5495[22]	vs eth, EtOH
7020	2-Methylbenzonitrile	*o*-Tolunitrile	C_8H_7N	529-19-1	117.149	liq	-13.5	205	0.9955[20]	1.5279[20]	i H_2O; msc EtOH, eth; sl ctc
7021	3-Methylbenzonitrile	*m*-Tolunitrile	C_8H_7N	620-22-4	117.149	liq	-23	213	1.0316[20]	1.5252[20]	i H_2O; msc EtOH, eth; sl ctc
7022	4-Methylbenzonitrile	*p*-Tolunitrile	C_8H_7N	104-85-8	117.149		29.5	217.0	0.9762[30]		i H_2O; vs EtOH, eth; sl ctc
7023	6-Methyl-2*H*-1-benzopyran-2-one		$C_{10}H_8O_2$	92-48-8	160.170		76.5	304; 174[14]			vs EtOH, eth, bz; sl chl, peth
7024	7-Methyl-2*H*-1-benzopyran-2-one	7-Methylcoumarin	$C_{10}H_8O_2$	2445-83-2	160.170	nd, (pl) (aq al)	128	171.5[11]			sl H_2O; vs EtOH, HOAc; s eth
7025	3-Methyl-4*H*-1-benzopyran-4-one	Tricromyl	$C_{10}H_8O_2$	85-90-5	160.170						s chl
7026	6-Methyl-2-benzothiazolamine		$C_8H_8N_2S$	2536-91-6	164.228	nd (w) pr (dil al)	142				sl H_2O; s EtOH
7027	2-Methylbenzothiazole		C_8H_7NS	120-75-2	149.214		14	238	1.1763[19]	1.6092[19]	i H_2O; s EtOH, chl
7028	3-Methyl-2(3*H*)-benzothiazolethione		$C_8H_7NS_2$	2254-94-6	181.279	nd (al), pr (HOAc)	90	335			i H_2O; sl EtOH, eth; vs bz, chl
7029	4-(6-Methyl-2-benzothiazolyl) aniline		$C_{14}H_{12}N_2S$	92-36-4	240.323		194.8	434			sl EtOH, eth, bz, HOAc
7030	1-Methyl-1*H*-benzotriazole		$C_7H_7N_3$	13351-73-0	133.151	pl (bz-lig)	64.5	270.5			vs bz, EtOH, HOAc
7031	1-Methyl-2*H*-3,1-benzoxazine-2,4(1*H*)-dione		$C_9H_7NO_3$	10328-92-4	177.157		180				
7032	2-Methylbenzoxazole		C_8H_7NO	95-21-6	133.148		9.5	200.5	1.1211[20]	1.5497[20]	i H_2O; vs EtOH; msc eth
7033	Methyl benzoylacetate		$C_{10}H_{10}O_3$	614-27-7	178.184	pa ye		dec 265; 151[12]	1.158[29]	1.537[20]	vs ace, eth, EtOH
7034	Methyl 2-benzoylbenzoate		$C_{15}H_{12}O_3$	606-28-0	240.254	pl or mcl pr (dil al)	52	351	1.1903[19]	1.591[20]	i H_2O; vs EtOH, eth; s sulf
7035	2-(4-Methylbenzoyl)benzoic acid	2-(*p*-Toluoyl)benzoic acid	$C_{15}H_{12}O_3$	85-55-2	240.254		146				sl H_2O, DMSO; vs EtOH, eth, ace, bz
7036	2-Methylbenzoyl chloride		C_8H_7ClO	933-88-0	154.594			213.5		1.5549[20]	vs eth, EtOH
7037	3-Methylbenzoyl chloride		C_8H_7ClO	1711-06-4	154.594	liq	-23	219.5	1.0265[21]	1.505[22]	vs eth, EtOH



3-Methylbenzenemethanol



4-Methylbenzenemethanol



α-Methylbenzenemethanol, acetate



4-Methylbenzenepropanal



α-Methylbenzenepropanamine



β-Methylbenzenepropanoic acid, (±)



α-Methylbenzenepropanol



4-Methylbenzenesulfinic acid



4-Methylbenzenesulfinyl chloride


2-Methylbenzenesulfonamide


4-Methylbenzenesulfonamide



Methyl benzenesulfonate


2-Methylbenzenesulfonic acid



2-Methylbenzenesulfonyl chloride



2-Methylbenzenethiol



3-Methylbenzenethiol



4-Methylbenzenethiol



1-Methyl-1*H*-benzimidazole



2-Methyl-1*H*-benzimidazole



Methyl benzoate



Methyl 1,3-benzodioxole-5-carboxylate



2-Methylbenzofuran



2-Methylbenzonitrile



3-Methylbenzonitrile



4-Methylbenzonitrile



6-Methyl-2*H*-1-benzopyran-2-one



7-Methyl-2*H*-1-benzopyran-2-one



3-Methyl-4*H*-1-benzopyran-4-one



6-Methyl-2-benzothiazolamine



2-Methylbenzothiazole



3-Methyl-2(3*H*)-benzothiazolethione



4-(6-Methyl-2-benzothiazolyl)aniline



1-Methyl-1*H*-benzotriazole



1-Methyl-2*H*-3,1-benzoxazine-2,4(1*H*)-dione



2-Methylbenzoxazole


Methyl benzoylacetate



Methyl 2-benzoylbenzoate



2-(4-Methylbenzoyl)benzoic acid



2-Methylbenzoyl chloride



3-Methylbenzoyl chloride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7038	4-Methylbenzoyl chloride		C_8H_7ClO	874-60-2	154.594	liq	-1.5	226	1.1686^{20}	1.5547^{20}	s ctc
7039	Methyl benzoylsalicylate	2-(Benzoyloxy)benzoic acid, methyl ester	$C_{15}H_{12}O_4$	610-60-6	256.254	cry	85	385			i H_2O; s bz, chl, eth, EtOH
7040	α-Methylbenzylamine, (±)	1-Amino-1-phenylethane	$C_8H_{11}N$	618-36-0	121.180		32	187	0.9395^{15}	1.5238^{25}	s H_2O, chl; msc EtOH, eth
7041	1-Methyl-2-benzylbenzene		$C_{14}H_{14}$	713-36-0	182.261		6.6	280.5	1.0020^{20}	1.5763^{20}	
7042	1-Methyl-4-benzylbenzene		$C_{14}H_{14}$	620-83-7	182.261	liq	-30	286	0.9976^{20}	1.5712^{20}	vs eth, bz, EtOH, chl
7043	α-Methylbenzyl formate		$C_9H_{10}O_2$	7775-38-4	150.174	liq					
7044	1-Methyl-2-benzyl-4(1*H*)-quinazolinone	Glycosine	$C_{16}H_{14}N_2O$	6873-15-0	250.294		161.5				
7045	1-Methylbicyclo[3.1.0]hexane		C_7H_{12}	4625-24-5	96.170			93.1			
7046	2-Methylbiphenyl		$C_{13}H_{12}$	643-58-3	168.234	liq	-0.2	255.3	1.0113^{20}	1.5914^{20}	i H_2O; s EtOH, eth
7047	3-Methylbiphenyl		$C_{13}H_{12}$	643-93-6	168.234		2.3	272.7	1.0182^{17}	1.5972^{20}	i H_2O; s EtOH, eth, ctc
7048	4-Methylbiphenyl		$C_{13}H_{12}$	644-08-6	168.234	pl (lig, MeOH)	49.5	267.5	1.015^{27}		i H_2O; s EtOH, eth; sl ctc
7049	4-Methyl-*N,N*-bis(4-methylphenyl)aniline		$C_{21}H_{21}N$	1159-53-1	287.399	cry (HOAc)	117				vs ace, bz, eth, chl
7050	Methyl bromoacetate		$C_3H_5BrO_2$	96-32-2	152.975			132	1.6350^{20}	1.4520^{20}	i H_2O; s EtOH, eth, ace, bz
7051	Methyl 2-bromobenzoate		$C_8H_7BrO_2$	610-94-6	215.045			244			i H_2O; s EtOH
7052	Methyl 3-bromobenzoate		$C_8H_7BrO_2$	618-89-3	215.045	pl	32	125^{15}			sl H_2O; s EtOH, eth
7053	Methyl 4-bromobenzoate		$C_8H_7BrO_2$	619-42-1	215.045	lf (dil al), nd (eth)	81		1.689^{25}		s EtOH, eth, ace, peth; vs bz, chl
7054	Methyl 2-bromobutanoate		$C_5H_9BrO_2$	3196-15-4	181.028			168	1.4528^{20}	1.4029^{25}	vs EtOH
7055	Methyl 4-bromobutanoate		$C_5H_9BrO_2$	4897-84-1	181.028			186.5	1.4^{25}	1.4567^{25}	vs EtOH
7056	Methyl 4-bromo-2-butenoate		$C_5H_7BrO_2$	1117-71-1	179.013			84^{12}	1.490^{19}	1.498^{19}	
7057	Methyl 5-bromopentanoate		$C_6H_{11}BrO_2$	5454-83-1	195.054	liq		101^{14}	1.363	1.4630^{20}	
7058	Methyl 3-bromopropanoate		$C_4H_7BrO_2$	3395-91-3	167.002			105^{60}, 62^{12}	1.4123^{18}	1.4542^{20}	s EtOH, eth, ace
7059	3-Methyl-1,2-butadiene		C_5H_8	598-25-4	68.118	liq	-113.6	40.83	0.6806^{25}	1.4203^{20}	vs ace, bz, eth, EtOH
7060	2-Methyl-1,3-butadiene	Isoprene	C_5H_8	78-79-5	68.118	liq	-145.9	34.0	0.679^{20}	1.4219^{20}	i H_2O; msc EtOH, eth, ace, bz
7061	3-Methylbutanal	Isovaleraldehyde	$C_5H_{10}O$	590-86-3	86.132	liq	-51	92.5	0.7977^{20}	1.3902^{20}	sl H_2O; s EtOH, eth
7062	3-Methylbutanamide	Isovaleramide	$C_5H_{11}NO$	541-46-8	101.147	mcl lf (al)	137	226			s H_2O, EtOH, eth; vs peth
7063	3-Methyl-1-butanamine	Isopentylamine	$C_5H_{13}N$	107-85-7	87.164			96	0.7505^{20}	1.4083^{20}	msc H_2O, EtOH, eth; s ace, chl
7064	2-Methyl-2-butanamine		$C_5H_{13}N$	594-39-8	87.164	liq	-105	77	0.731^{25}	1.3954^{25}	vs H_2O, ace, eth, EtOH
7065	3-Methyl-2-butanamine		$C_5H_{13}N$	598-74-3	87.164	liq	-50	85.5	0.7574^{19}	1.4096^{18}	vs H_2O; s EtOH
7066	3-Methyl-1,3-butanediol		$C_5H_{12}O_2$	2568-33-4	104.148			202.5	0.9448^{20}	1.4452^{20}	s H_2O, EtOH
7067	2-Methylbutanenitrile		C_5H_9N	18936-17-9	83.132			125	0.7913^{15}	1.3933^{20}	vs eth, EtOH
7068	3-Methylbutanenitrile	Isobutyl cyanide	C_5H_9N	625-28-5	83.132	liq	-101	127.5	0.7914^{20}	1.3927^{20}	sl H_2O; msc EtOH, eth; vs ace
7069	2-Methyl-1-butanethiol, (+)		$C_5H_{12}S$	20089-07-0	104.214	liq		119.1	0.8420^{20}	1.4440^{20}	
7070	3-Methyl-1-butanethiol	Isopentyl mercaptan	$C_5H_{12}S$	541-31-1	104.214	liq		116	0.8350^{20}	1.4412^{20}	i H_2O; msc EtOH, eth; s ctc
7071	2-Methyl-2-butanethiol		$C_5H_{12}S$	1679-09-0	104.214	liq		99.1	0.8120^{20}	1.4385^{20}	
7072	3-Methyl-2-butanethiol		$C_5H_{12}S$	2084-18-6	104.214	liq	-127.1	109.8			
7073	Methyl butanoate		$C_5H_{10}O_2$	623-42-7	102.132	liq	-85.8	102.8	0.8984^{20}	1.3878^{20}	sl H_2O, ctc; msc EtOH, eth
7074	2-Methylbutanoic acid	(±)-2-Methylbutyric acid	$C_5H_{10}O_2$	600-07-7	102.132		<-80	177	0.934^{20}	1.4051^{20}	sl H_2O; msc EtOH, eth; s chl
7075	3-Methylbutanoic acid	Isovaleric acid	$C_5H_{10}O_2$	503-74-2	102.132	liq	-29.3	176.5	0.931^{20}	1.4033^{20}	s H_2O; msc EtOH, eth, chl
7076	3-Methylbutanoic anhydride		$C_{10}H_{18}O_3$	1468-39-9	186.248			215	0.9327^{20}	1.4043^{20}	vs eth
7077	2-Methyl-1-butanol, (±)		$C_5H_{12}O$	34713-94-5	88.148			127.5	0.8152^{25}	1.4092^{20}	sl H_2O; msc EtOH, eth; vs ace
7078	3-Methyl-1-butanol	Isopentyl alcohol	$C_5H_{12}O$	123-51-3	88.148	liq	-117.2	131.1	0.8104^{20}	1.4053^{20}	sl H_2O; vs ace, eth, EtOH
7079	2-Methyl-2-butanol	*tert*-Pentyl alcohol	$C_5H_{12}O$	75-85-4	88.148	liq	-9.1	102.4	0.8096^{20}	1.4052^{20}	s H_2O, bz, chl; msc EtOH, eth; vs ace



4-Methylbenzoyl chloride



Methyl benzoylsalicylate


α-Methylbenzylamine, (±)



1-Methyl-2-benzylbenzene



1-Methyl-4-benzylbenzene



α-Methylbenzyl formate



1-Methyl-2-benzyl-4(1*H*)-quinazolinone



1-Methylbicyclo[3.1.0]hexane


2-Methylbiphenyl



3-Methylbiphenyl



4-Methylbiphenyl



4-Methyl-*N*,*N*-bis(4-methylphenyl)aniline



Methyl bromoacetate



Methyl 2-bromobenzoate



Methyl 3-bromobenzoate



Methyl 4-bromobenzoate



Methyl 2-bromobutanoate


Methyl 4-bromobutanoate



Methyl 4-bromo-2-butenoate



Methyl 5-bromopentanoate



Methyl 3-bromopropanoate


3-Methyl-1,2-butadiene


2-Methyl-1,3-butadiene



3-Methylbutanal


3-Methylbutanamide



3-Methyl-1-butanamine


2-Methyl-2-butanamine



3-Methyl-2-butanamine


3-Methyl-1,3-butanediol


2-Methylbutanenitrile



3-Methylbutanenitrile



2-Methyl-1-butanethiol, (+)



3-Methyl-1-butanethiol



2-Methyl-2-butanethiol



3-Methyl-2-butanethiol



Methyl butanoate


2-Methylbutanoic acid


3-Methylbutanoic acid


3-Methylbutanoic anhydride



2-Methyl-1-butanol, (±)


3-Methyl-1-butanol



2-Methyl-2-butanol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7080	3-Methyl-2-butanol, (±)		$C_5H_{12}O$	70116-68-6	88.148			112.9	0.8180^{20}	1.4089^{20}	sl H_2O; msc EtOH, eth; vs ace; s bz, ctc
7081	2-Methyl-1-butanol acetate		$C_7H_{14}O_2$	624-41-9	130.185			140	0.8740^{20}	1.4040^{20}	vs ace, eth, EtOH
7082	3-Methyl-2-butanone	Methyl isopropyl ketone	$C_5H_{10}O$	563-80-4	86.132	liq	-93.1	94.33	0.8051^{20}	1.3880^{20}	sl H_2O; msc EtOH, eth; vs ace; s ctc
7083	2-Methylbutanoyl chloride, (±)		C_5H_9ClO	57526-28-0	120.577			116	0.9917^{20}	1.4170^{20}	
7084	3-Methylbutanoyl chloride	Isovaleryl chloride	C_5H_9ClO	108-12-3	120.577			114	0.9844^{20}	1.4149^{20}	s eth
7085	*trans*-2-Methyl-2-butenal	Tiglic aldehyde	C_5H_8O	497-03-0	84.117	liq		117; 64^{119}	0.8710^{20}	1.4475^{20}	sl H_2O; vs EtOH
7086	3-Methyl-2-butenal	Senecialdehyde	C_5H_8O	107-86-8	84.117			134	0.8722^{20}	1.4528^{20}	s H_2O, EtOH, eth
7087	2-Methyl-1-butene		C_5H_{10}	563-46-2	70.133	liq	-137.53	31.2	0.6504^{20}	1.3778^{20}	i H_2O; s EtOH, eth, bz, ctc
7088	3-Methyl-1-butene		C_5H_{10}	563-45-1	70.133	vol liq or gas	-168.43	20.1	0.6213^{25}	1.3643^{20}	i H_2O; msc EtOH, eth; s bz
7089	2-Methyl-2-butene		C_5H_{10}	513-35-9	70.133	liq	-133.72	38.56	0.6623^{20}	1.3874^{20}	i H_2O; s EtOH, eth, bz, ctc; vs lig
7090	*cis*-2-Methyl-2-butenedioic acid	Citraconic acid	$C_5H_6O_4$	498-23-7	130.100	nd (eth-lig) tcl pr (eth-bz)	93.5		1.617^{25}		vs H_2O; sl eth, chl; i bz, CS_2
7091	3-Methyl-2-butenenitrile		C_5H_7N	4786-24-7	81.117	liq		141			
7092	Methyl *cis*-2-butenoate	Methyl isocrotonate	$C_5H_8O_2$	4358-59-2	100.117			118		1.4175^{20}	
7093	Methyl *trans*-2-butenoate	Methyl crotonate	$C_5H_8O_2$	623-43-8	100.117	liq	-42	121	0.9444^{20}	1.4242^{20}	i H_2O; vs EtOH, eth
7094	*cis*-2-Methyl-2-butenoic acid	Angelic acid	$C_5H_8O_2$	565-63-9	100.117	mcl pr or nd	45.5	185	0.9834^{49}	1.4434^{47}	sl H_2O; s EtOH; vs eth
7095	*trans*-2-Methyl-2-butenoic acid	Tiglic acid	$C_5H_8O_2$	80-59-1	100.117	tab (w)	64.5	198.5	0.9641^{76}	1.4330^{76}	s H_2O; vs EtOH, eth
7096	3-Methyl-2-butenoic acid		$C_5H_8O_2$	541-47-9	100.117		69.5	197	1.0062^{24}		
7097	3-Methyl-2-buten-1-ol		$C_5H_{10}O$	556-82-1	86.132			140	0.848^{25}	1.4412^{20}	
7098	3-Methyl-3-buten-1-ol		$C_5H_{10}O$	763-32-6	86.132			129.9			
7099	2-Methyl-3-buten-2-ol		$C_5H_{10}O$	115-18-4	86.132	liq	-28	97	0.82^{20}		
7100	3-Methyl-3-buten-2-ol		$C_5H_{10}O$	10473-14-0	86.132			114	0.8531^{17}	1.4288^{17}	
7101	3-Methyl-3-buten-2-one	Isopropenyl methyl ketone	C_5H_8O	814-78-8	84.117	liq	-54	98	0.8527^{20}	1.4220^{20}	vs EtOH
7102	3-Methyl-2-butenoyl chloride		C_5H_7ClO	3350-78-5	118.562			146	1.065^{25}	1.4770^{20}	
7103	(3-Methyl-2-butenyl)guanidine	Galegine	$C_6H_{13}N_3$	543-83-9	127.187	hyg	62.5	dec			vs H_2O, EtOH
7104	2-Methyl-1-buten-3-yne	Isopropenylacetylene	C_5H_6	78-80-8	66.102	liq	-113	32	0.6801^{11}	1.4140^{20}	s chl
7105	[(3-Methylbutoxy)methyl]benzene		$C_{12}H_{18}O$	122-73-6	178.270			236; 118^{19}	0.909^{20}	1.4792^{20}	vs eth, EtOH
7106	1-[2-(3-Methylbutoxy)-2-phenylethyl]pyrrolidine	Amixetrine	$C_{17}H_{27}NO$	24622-72-8	261.402			121^{2}		1.4978^{22}	
7107	2-Methylbutyl acrylate		$C_8H_{14}O_2$	44914-03-6	142.196			160; 45^{10}	0.8936^{20}	1.4240^{20}	vs eth, EtOH
7108	3-Methylbutyl benzoate	Isopentyl benzoate	$C_{12}H_{16}O_2$	94-46-2	192.254			261	0.993^{15}		vs EtOH
7109	3-Methylbutyl 2-chloropropanoate		$C_8H_{15}ClO_2$	62108-69-4	178.657			208	1.0050^{20}	1.4289^{20}	
7110	3-Methylbutyl 3-chloropropanoate		$C_8H_{15}ClO_2$	62108-70-7	178.657			208; 87^{12}	1.0171^{20}	1.4343^{20}	vs eth, EtOH
7111	Methyl *tert*-butyl ether	*tert*-Butyl methyl ether	$C_5H_{12}O$	1634-04-4	88.148	liq	-108.6	55.0	0.7353^{25}	1.3664^{25}	s H_2O; vs EtOH, eth
7112	3-Methylbutyl nitrate	Isopentyl nitrate	$C_5H_{11}NO_3$	543-87-3	133.146			148	0.996^{22}	1.4122^{21}	
7113	2-Methyl-3-butyn-2-amine		C_5H_9N	2978-58-7	83.132		18	79.5	0.79^{25}	1.4235^{20}	
7114	3-Methyl-1-butyne		C_5H_8	598-23-2	68.118	vol liq or gas	-89.7	26.3	0.6660^{20}	1.3723^{20}	i H_2O; msc EtOH, eth
7115	2-Methyl-3-butyn-2-ol	1,1-Dimethylpropargyl alcohol	C_5H_8O	115-19-5	84.117		1.5	104	0.8618^{20}	1.4207^{20}	
7116	Methyl carbamate		$C_2H_5NO_2$	598-55-0	75.067	nd	54	177	1.1361^{56}	1.4125^{56}	vs H_2O; vs EtOH, eth
7117	3-Methyl-9*H*-carbazole		$C_{13}H_{11}N$	4630-20-0	181.233	pl (HOAc)	208.5	365			vs bz, eth
7118	9-Methyl-9*H*-carbazole		$C_{13}H_{11}N$	1484-12-4	181.233	nd, lf (al)	89.34	343.64; 195^{12}			vs eth
7119	Methyl chloroacetate		$C_3H_5ClO_2$	96-34-4	108.524	liq	-32.1	129.5	1.236^{20}	1.4218^{20}	vs ace, bz, eth, EtOH
7120	Methyl 2-chloroacrylate		$C_4H_5ClO_2$	80-63-7	120.535			52^{51}	1.189^{20}	1.4420^{20}	vs eth
7121	Methyl 2-chlorobenzoate		$C_8H_7ClO_2$	610-96-8	170.594			234			s EtOH
7122	Methyl 3-chlorobenzoate		$C_8H_7ClO_2$	2905-65-9	170.594		21	229			
7123	Methyl 4-chlorobenzoate		$C_8H_7ClO_2$	1126-46-1	170.594	nd or mcl pr	43.5		1.382^{20}		vs EtOH
7124	Methyl 4-chlorobutanoate		$C_5H_9ClO_2$	3153-37-5	136.577			174; 55^{4}	1.1293^{20}	1.4321^{20}	i H_2O; vs EtOH, eth; s ace
7125	Methyl chlorocarbonate		$C_2H_3ClO_2$	79-22-1	94.497			70.5	1.2231^{20}	1.3868^{20}	msc EtOH, eth; s bz, ctc, chl
7126	Methyl 5-chloro-2-hydroxybenzoate		$C_8H_7ClO_3$	4068-78-4	186.593	nd (al)	50	dec 249; 120^{12}			vs EtOH
7127	Methyl 5-chloro-2-nitrobenzoate		$C_8H_6ClNO_4$	51282-49-6	215.592	pl (MeOH)	48.5		1.453^{18}		vs MeOH
7128	Methyl chlorooxoacetate		$C_3H_3ClO_3$	5781-53-3	122.507			119	1.3316^{20}	1.4189^{20}	
7129	Methyl 2-chloropropanoate		$C_4H_7ClO_2$	17639-93-9	122.551			132.5	1.0750^{25}		



3-Methyl-2-butanol, (±)



2-Methyl-1-butanol acetate


3-Methyl-2-butanone


2-Methylbutanoyl chloride, (±)


3-Methylbutanoyl chloride



trans-2-Methyl-2-butenal



3-Methyl-2-butenal



2-Methyl-1-butene



3-Methyl-1-butene


2-Methyl-2-butene



cis-2-Methyl-2-butenedioic acid



3-Methyl-2-butenenitrile



Methyl *cis*-2-butenoate



Methyl *trans*-2-butenoate


cis-2-Methyl-2-butenoic acid


trans-2-Methyl-2-butenoic acid


3-Methyl-2-butenoic acid



3-Methyl-2-buten-1-ol



3-Methyl-3-buten-1-ol


2-Methyl-3-buten-2-ol



3-Methyl-3-buten-2-ol



3-Methyl-3-buten-2-one



3-Methyl-2-butenoyl chloride



(3-Methyl-2-butenyl)guanidine



2-Methyl-1-buten-3-yne



[(3-Methylbutoxy)methyl]benzene


1-[2-(3-Methylbutoxy)-2-phenylethyl]pyrrolidine



2-Methylbutyl acrylate


3-Methylbutyl benzoate


3-Methylbutyl 2-chloropropanoate



3-Methylbutyl 3-chloropropanoate



Methyl *tert*-butyl ether



3-Methylbutyl nitrate



2-Methyl-3-butyn-2-amine



3-Methyl-1-butyne



2-Methyl-3-butyn-2-ol



Methyl carbamate



3-Methyl-9*H*-carbazole



9-Methyl-9*H*-carbazole



Methyl chloroacetate



Methyl 2-chloroacrylate



Methyl 2-chlorobenzoate



Methyl 3-chlorobenzoate



Methyl 4-chlorobenzoate



Methyl 4-chlorobutanoate


Methyl chlorocarbonate



Methyl 5-chloro-2-hydroxybenzoate



Methyl 5-chloro-2-nitrobenzoate



Methyl chlorooxoacetate



Methyl 2-chloropropanoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7130	3-Methylchrysene		$C_{19}H_{14}$	3351-31-3	242.314	lf (bz-peth)	173.3				vs EtOH
7131	5-Methylchrysene		$C_{19}H_{14}$	3697-24-3	242.314		118.3				i H_2O
7132	6-Methylchrysene		$C_{19}H_{14}$	1705-85-7	242.314		161				
7133	Methyl *trans*-cinnamate	Methyl *trans*-3-phenyl-2-propenoate	$C_{10}H_{10}O_2$	1754-62-7	162.185	cry (peth, dil al)	36.5	261.9	1.042^{36}	1.5766^{22}	i H_2O; vs EtOH, eth; s ace, bz; sl chl
7134	*trans-o*-Methylcinnamic acid		$C_{10}H_{10}O_2$	2373-76-4	162.185	cry (EtOH)	175				
7135	*trans-m*-Methylcinnamic acid		$C_{10}H_{10}O_2$	3029-79-6	162.185	cry (w)	115				
7136	*trans-p*-Methylcinnamic acid		$C_{10}H_{10}O_2$	1866-39-3	162.185		198.5				
7137	Methyclothiazide		$C_9H_{11}Cl_2N_3O_4S_2$	135-07-9	360.237	cry (EtOH aq)	225				i H_2O, bz, chl; sl MeOH; vs ace, py
7138	Methyl cyanate		C_2H_3NO	1768-34-9	57.051	unstab gas	-30	exp			
7139	Methyl cyanoacetate		$C_4H_5NO_2$	105-34-0	99.089	liq	-22.5	200.5	1.1225^{25}	1.4176^{20}	vs eth, EtOH
7140	Methyl 2-cyanoacrylate	Mecrylate	$C_5H_5NO_2$	137-05-3	111.100			47^{2}	1.1012^{20}	1.4430	
7141	Methylcyclobutane		C_5H_{10}	598-61-8	70.133	liq	-161.5	36.3	0.6884^{20}	1.3866^{20}	i H_2O; msc EtOH, eth; s ace, bz, peth
7142	Methyl cyclobutanecarboxylate		$C_6H_{10}O_2$	765-85-5	114.142			135.5			
7143	2-Methyl-1,3-cyclohexadiene	4,5-Dihydrotoluene	C_7H_{10}	1489-57-2	94.154			107.5	0.8260^{18}	1.4662^{18}	
7144	2-Methyl-2,5-cyclohexadiene-1,4-dione		$C_7H_6O_2$	553-97-9	122.122	ye pl or nd	69	sub	1.08^{75}		sl H_2O; s EtOH, eth
7145	Methylcyclohexane		C_7H_{14}	108-87-2	98.186	liq	-126.6	100.93	0.7694^{20}	1.4231^{20}	i H_2O; s EtOH, eth; msc ace, bz, lig
7146	Methyl cyclohexanecarboxylate		$C_8H_{14}O_2$	4630-82-4	142.196			183	0.9954^{15}	1.4433^{20}	i H_2O; s EtOH, eth, ace, chl
7147	α-Methylcyclohexanemethanol		$C_8H_{16}O$	1193-81-3	128.212			189	0.928^{25}	1.4656^{20}	vs EtOH, eth; sl ctc
7148	4-Methylcyclohexanemethanol		$C_8H_{16}O$	34885-03-5	128.212			$75^{2.5}$	0.9074^{20}	1.4617^{20}	
7149	1-Methylcyclohexanol		$C_7H_{14}O$	590-67-0	114.185		25	155; 70^{25}	0.9194^{20}	1.4595^{20}	i H_2O; s EtOH, bz, chl
7150	*cis*-2-Methylcyclohexanol		$C_7H_{14}O$	615-38-3	114.185		7	165	0.9360^{20}	1.4640^{20}	vs EtOH
7151	*trans*-2-Methylcyclohexanol, (±)		$C_7H_{14}O$	615-39-4	114.185	liq	-2.0	167.5	0.9247^{20}	1.4616^{20}	vs eth, EtOH
7152	*cis*-3-Methylcyclohexanol, (±)		$C_7H_{14}O$	5454-79-5	114.185	liq	-5.5	168; 94^{12}	0.9155^{20}	1.4752^{20}	vs eth, EtOH
7153	*trans*-3-Methylcyclohexanol, (±)		$C_7H_{14}O$	7443-55-2	114.185	liq	-0.5	167; 84^{13}	0.9214^{30}	1.4580^{20}	vs eth, EtOH
7154	*cis*-4-Methylcyclohexanol		$C_7H_{14}O$	7731-28-4	114.185	liq	-9.2	173	0.9170^{20}	1.4614^{20}	vs eth, EtOH
7155	*trans*-4-Methylcyclohexanol		$C_7H_{14}O$	7731-29-5	114.185			174	0.9118^{21}	1.4561^{20}	sl H_2O; msc EtOH; s eth
7156	2-Methylcyclohexanone, (±)		$C_7H_{12}O$	24965-84-2	112.169	liq	-13.9	165	0.9250^{20}	1.4483^{25}	i H_2O; s EtOH, eth
7157	3-Methylcyclohexanone, (±)		$C_7H_{12}O$	625-96-7	112.169	liq	-73.5	169; 65^{15}	0.9136^{20}	1.4456^{20}	i H_2O; s EtOH, eth
7158	4-Methylcyclohexanone		$C_7H_{12}O$	589-92-4	112.169	liq	-40.6	170	0.9138^{20}	1.4451^{20}	i H_2O; s EtOH, eth; sl ctc
7159	1-Methylcyclohexene		C_7H_{12}	591-49-1	96.170	liq	-120.4	110.3	0.8102^{20}	1.4503^{20}	i H_2O; s eth, bz, ctc
7160	3-Methylcyclohexene, (±)		C_7H_{12}	56688-75-6	96.170	liq	-115.5	104	0.7990^{20}	1.4414^{20}	vs bz, eth, chl, peth
7161	4-Methylcyclohexene		C_7H_{12}	591-47-9	96.170	liq	-115.5	102.7	0.7991^{20}	1.4414^{20}	i H_2O; s EtOH, eth
7162	Methyl 3-cyclohexene-1-carboxylate		$C_8H_{12}O_2$	6493-77-2	140.180			182; 80^{20}	1.0130^{20}	1.4610^{20}	
7163	2-Methyl-2-cyclohexen-1-one		$C_7H_{10}O$	1121-18-2	110.153			178.5	0.966^{20}	1.4833^{20}	s bz
7164	3-Methyl-2-cyclohexen-1-one		$C_7H_{10}O$	1193-18-6	110.153	liq	-21	201	0.9693^{20}	1.49475^{20}	msc H_2O; s bz
7165	3-Methylcyclopentadecanone	Muscone	$C_{16}H_{30}O$	541-91-3	238.408	oily liq		329; $130^{0.5}$	0.9221^{17}	1.4802^{17}	vs ace, eth, EtOH
7166	1-Methyl-1,3-cyclopentadiene		C_6H_8	96-39-9	80.128	liq		73	0.81^{20}	1.4512^{20}	
7167	Methylcyclopentane		C_6H_{12}	96-37-7	84.159	liq	-142.42	71.8	0.7486^{20}	1.4097^{20}	i H_2O; msc EtOH, eth, ace, bz, lig, ctc
7168	1-Methylcyclopentanol		$C_6H_{12}O$	1462-03-9	100.158	nd	36	136; 53^{30}	0.9044^{23}	1.4429^{23}	
7169	*cis*-2-Methylcyclopentanol		$C_6H_{12}O$	25144-05-2	100.158			148.5	0.9379^{16}	1.4504^{16}	
7170	2-Methylcyclopentanone		$C_6H_{10}O$	1120-72-5	98.142	liq	-75	139.5	0.9139^{20}	1.4364^{20}	s H_2O; vs EtOH, eth, ace
7171	3-Methylcyclopentanone, (±)		$C_6H_{10}O$	6195-92-2	98.142	liq	-58.4	144	0.913^{22}	1.4329^{20}	s H_2O; vs EtOH, eth, ace, HOAc
7172	1-Methylcyclopentene		C_6H_{10}	693-89-0	82.143	liq	-126.5	75.5	0.7748^{25}	1.4322^{20}	
7173	3-Methylcyclopentene		C_6H_{10}	1120-62-3	82.143			64.9	0.7572^{25}	1.4216^{20}	
7174	4-Methylcyclopentene		C_6H_{10}	1759-81-5	82.143	liq	-160.8	65.7	0.7634^{25}	1.4209^{20}	
7175	2-Methyl-2-cyclopenten-1-one		C_6H_8O	1120-73-6	96.127			157	0.9808^{16}	1.4762^{15}	
7176	3-Methyl-2-cyclopenten-1-one		C_6H_8O	2758-18-1	96.127			157.5	0.9712^{20}	1.4714^{20}	



3-Methylchrysene



5-Methylchrysene



6-Methylchrysene


Methyl *trans*-cinnamate



trans-o-Methylcinnamic acid



trans-m-Methylcinnamic acid


trans-p-Methylcinnamic acid



Methyclothiazide


Methyl cyanate



Methyl cyanoacetate


Methyl 2-cyanoacrylate



Methylcyclobutane



Methyl cyclobutanecarboxylate



2-Methyl-1,3-cyclohexadiene


2-Methyl-2,5-cyclohexadiene-1,4-dione


Methylcyclohexane


Methyl cyclohexanecarboxylate


α-Methylcyclohexanemethanol


4-Methylcyclohexanemethanol



1-Methylcyclohexanol



cis-2-Methylcyclohexanol


trans-2-Methylcyclohexanol, (±)


cis-3-Methylcyclohexanol, (±)



trans-3-Methylcyclohexanol, (±)


cis-4-Methylcyclohexanol


trans-4-Methylcyclohexanol


2-Methylcyclohexanone, (±)



3-Methylcyclohexanone, (±)


4-Methylcyclohexanone


1-Methylcyclohexene



3-Methylcyclohexene, (±)


4-Methylcyclohexene


Methyl 3-cyclohexene-1-carboxylate


2-Methyl-2-cyclohexen-1-one


3-Methyl-2-cyclohexen-1-one


3-Methylcyclopentadecanone



1-Methyl-1,3-cyclopentadiene


Methylcyclopentane


1-Methylcyclopentanol


cis-2-Methylcyclopentanol



2-Methylcyclopentanone



3-Methylcyclopentanone, (±)


1-Methylcyclopentene


3-Methylcyclopentene


4-Methylcyclopentene


2-Methyl-2-cyclopenten-1-one



3-Methyl-2-cyclopenten-1-one


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7177	Methylcyclopropane		C_4H_8	594-11-6	56.107	col gas	-177.6	0.7	0.6912^{-20}		vs eth, EtOH
7178	Methyl cyclopropanecarboxylate		$C_5H_8O_2$	2868-37-3	100.117			114.9	0.9848^{20}	1.4144^{19}	s ace, chl
7179	α-Methylcyclopropanemethanol		$C_5H_{10}O$	765-42-4	86.132	liq	-32.1	123.5	0.8805^{20}	1.4316^{20}	
7180	Methyl *L*-cysteine hydrochloride		$C_4H_{10}ClNO_2S$	18598-63-5	171.646	cry (MeOH)	140.5				
7181	Methyl *trans*-2,*cis*-4-decadienoate		$C_{11}H_{18}O_2$	4493-42-9	182.260			$71^{0.15}$	0.9128^{22}	1.4874^{22}	
7182	Methyl *trans*-2,*trans*-4-decadienoate		$C_{11}H_{18}O_2$	7328-33-8	182.260			87^{13}, $70^{0.2}$	0.9082^{22}	1.4918^{22}	
7183	2-Methyldecane		$C_{11}H_{24}$	6975-98-0	156.309	liq	-48.9	189.3	0.7368^{20}	1.4154^{20}	
7184	3-Methyldecane		$C_{11}H_{24}$	13151-34-3	156.309	liq	-92.9	188.1	0.7422^{20}	1.4177^{20}	
7185	4-Methyldecane		$C_{11}H_{24}$	2847-72-5	156.309	liq	-77.5	187		1.4352^{20}	
7186	Methyl decanoate		$C_{11}H_{22}O_2$	110-42-9	186.292	liq	-18	224	0.8730^{20}	1.4259^{20}	i H_2O; vs EtOH, eth; sl ctc; msc chl
7187	Methyl demeton		$C_6H_{15}O_3PS_2$	8022-00-2	230.285	ye liq		$89^{0.15}$, 118^{1}	1.20^{20}	1.5063^{20}	i H_2O; s os
7188	Methyldiborane(6)		CH_8B_2	23777-55-1	41.697	unstab gas					s eth
7189	Methyl 2,3-dibromopropanoate		$C_4H_6Br_2O_2$	1729-67-5	245.898			206	1.9333^{20}	1.5127^{20}	s EtOH
7190	Methyl dichloroacetate		$C_3H_4Cl_2O_2$	116-54-1	142.969	liq	-51.9	142.9	1.3774^{20}	1.4429^{20}	i H_2O; s EtOH, ctc
7191	Methyl 2,5-dichlorobenzoate		$C_8H_6Cl_2O_2$	2905-69-3	205.039	cry	38				
7192	Methyl (2,4-dichlorophenoxy) acetate	2,4-D methyl ester	$C_9H_8Cl_2O_3$	1928-38-7	235.064		119	141^{18}			
7193	Methyl (3,4-dichlorophenyl) carbamate	Swep	$C_8H_7Cl_2NO_2$	1918-18-9	220.054	nd	114				
7194	Methyl 2,3-dichloropropanoate		$C_4H_6Cl_2O_2$	3674-09-7	156.996			92^{50}, 63^{10}	1.3282^{20}		vs ace, eth, EtOH
7195	Methyldifluoroarsine		CH_3AsF_2	420-24-6	127.954	liq, fumes in air	-29.7	76.5	1.924^{18}		
7196	Methyldifluorophosphine	(Difluoro)methylphosphine	CH_3F_2P	753-59-3	84.006	gas	-110	-28			
7197	Methyl 2,4-dihydroxybenzoate		$C_8H_8O_4$	2150-47-2	168.148		116.5				sl EtOH, ace
7198	Methyl 3,5-dihydroxybenzoate		$C_8H_8O_4$	2150-44-9	168.148		165				
7199	Methyl 3,4-dimethoxybenzoate		$C_{10}H_{12}O_4$	2150-38-1	196.200	nd (dil al)	60.8	283			vs bz, eth, EtOH
7200	Methyldimethoxysilane		$C_3H_{10}O_2Si$	16881-77-9	106.196			61			
7201	3-Methyl-4'-(dimethylamino) azobenzene		$C_{15}H_{17}N_3$	55-80-1	239.316	oran cry	122				
7202	2-Methyl-*N*,*N*-dimethylaniline	*N*,*N*-Dimethyl-*o*-toluidine	$C_9H_{13}N$	609-72-3	135.206	liq	-60	194.1	0.9286^{20}	1.5152^{20}	vs eth, EtOH
7203	3-Methyl-*N*,*N*-dimethylaniline	*N*,*N*-Dimethyl-*m*-toluidine	$C_9H_{13}N$	121-72-2	135.206			212	0.9410^{20}	1.5492^{20}	msc EtOH, eth
7204	4-Methyl-*N*,*N*-dimethylaniline	*N*,*N*-Dimethyl-*p*-toluidine	$C_9H_{13}N$	99-97-8	135.206			211	0.9366^{20}	1.5366^{20}	i H_2O; msc EtOH, eth; s ctc
7205	Methyl 2,2-dimethylpropanoate	Methyl 2,2-dimethylpropionate	$C_6H_{12}O_2$	598-98-1	116.158			101.1	0.891^{0}	1.3905^{20}	vs eth, EtOH
7206	Methyl dimethylthioborane	Dimethyl(methylthio)borane	C_3H_9BS	19163-05-4	87.979	liq	-84	71			vs ace, eth
7207	2-Methyl-3,5-dinitrobenzamide	Dinitolmide	$C_8H_7N_3O_5$	148-01-6	225.159	cry	181				
7208	1-Methyl-2,3-dinitrobenzene	2,3-Dinitrotoluene	$C_7H_6N_2O_4$	602-01-7	182.134		63				i H_2O; s EtOH, eth; sl chl
7209	1-Methyl-2,4-dinitrobenzene	2,4-Dinitrotoluene	$C_7H_6N_2O_4$	121-14-2	182.134	ye nd or mcl pr (CS_2)	70.5	dec 300	1.3208^{71}	1.442	i H_2O; s EtOH, eth, chl, bz; vs ace, py
7210	1-Methyl-3,5-dinitrobenzene	3,5-Dinitrotoluene	$C_7H_6N_2O_4$	618-85-9	182.134	ye orth nd (HOAc)	93	sub	1.2772^{111}		sl H_2O; s EtOH, eth, bz, chl, CS_2
7211	2-Methyl-1,3-dinitrobenzene	2,6-Dinitrotoluene	$C_7H_6N_2O_4$	606-20-2	182.134	orth nd (al)	66.0	285	1.2833^{111}	1.479	s EtOH, chl
7212	2-Methyl-1,4-dinitrobenzene	2,5-Dinitrotoluene	$C_7H_6N_2O_4$	619-15-8	182.134	nd (al)	52.5		1.282^{111}		s EtOH, bz; vs CS_2
7213	4-Methyl-1,2-dinitrobenzene	3,4-Dinitrotoluene	$C_7H_6N_2O_4$	610-39-9	182.134	ye nd (CS_2)	59.0		1.2594^{111}		i H_2O; s EtOH, CS_2; sl chl
7214	2-Methyl-4,6-dinitrophenol	4,6-Dinitro-*o*-cresol	$C_7H_6N_2O_5$	534-52-1	198.133	ye pr or nd (al)	86.5				sl H_2O, peth; s EtOH, eth, ace, chl
7215	4-Methyl-2,6-dinitrophenol	2,6-Dinitro-*p*-cresol	$C_7H_6N_2O_5$	609-93-8	198.133	ye nd (eth, peth)	85				i H_2O; s EtOH, eth, bz
7216	Methyldioctylamine	*N*-Methyl-*N*-octyl-1-octanamine	$C_{17}H_{37}N$	4455-26-9	255.483		-30.1	158^{10}		1.4424^{20}	
7217	4-Methyl-1,3-dioxane		$C_5H_{10}O_2$	1120-97-4	102.132	liq	-44.5	114	0.9758^{20}	1.4159^{20}	sl H_2O; vs os
7218	2-Methyl-1,3-dioxolane		$C_4H_8O_2$	497-26-7	88.106			81.5	0.9811^{20}	1.4035^{17}	vs H_2O; msc EtOH, eth
7219	4-Methyl-1,3-dioxolane		$C_4H_8O_2$	1072-47-5	88.106	liq		85	0.99^{20}	1.3980^{20}	
7220	Methyldiphenylamine	*N*-Methyl-*N*-phenylbenzenamine	$C_{13}H_{13}N$	552-82-9	183.249	liq	-7.5	293.5	1.0476^{20}	1.6193^{20}	i H_2O; sl EtOH, MeOH; s ctc
7221	4-Methyl-2,4-diphenyl-1-pentene		$C_{18}H_{20}$	6362-80-7	236.352	liq		172^{8}, $102^{0.2}$	0.99^{25}		
7222	Methyldiphenylsilane		$C_{13}H_{14}Si$	776-76-1	198.336			93.5^{1}	0.996^{20}	1.5694^{20}	s ctc
7223	Methyldiphenylsilanol		$C_{13}H_{14}OSi$	778-25-6	214.335		167	184^{24}, 148^{3}	1.0840^{25}		s ctc, CS_2
7224	2-Methyl-1,2-di-3-pyridinyl-1-propanone	Metyrapone	$C_{14}H_{14}N_2O$	54-36-4	226.273		50.5				
7225	Methyl docosanoate	Methyl behenate	$C_{23}H_{46}O_2$	929-77-1	354.610	nd (ace)	54			1.4339^{60}	vs eth, EtOH



Methylcyclopropane



Methyl cyclopropanecarboxylate



α-Methylcyclopropanemethanol



Methyl *L*-cysteine hydrochloride



Methyl *trans*-2,*cis*-4-decadienoate



Methyl *trans*-2,*trans*-4-decadienoate



2-Methyldecane



3-Methyldecane



4-Methyldecane



Methyl decanoate



Methyl demeton



Methyldiborane(6)



Methyl 2,3-dibromopropanoate


Methyl dichloroacetate


Methyl 2,5-dichlorobenzoate



Methyl (2,4-dichlorophenoxy)acetate



Methyl (3,4-dichlorophenyl)carbamate



Methyl 2,3-dichloropropanoate


Methyldifluoroarsine



Methyldifluorophosphine



Methyl 2,4-dihydroxybenzoate



Methyl 3,5-dihydroxybenzoate



Methyl 3,4-dimethoxybenzoate



Methyldimethoxysilane


3-Methyl-4'-(dimethylamino)azobenzene



2-Methyl-*N*,*N*-dimethylaniline



3-Methyl-*N*,*N*-dimethylaniline



4-Methyl-*N*,*N*-dimethylaniline



Methyl 2,2-dimethylpropanoate



Methyl dimethylthioborane



2-Methyl-3,5-dinitrobenzamide



1-Methyl-2,3-dinitrobenzene



1-Methyl-2,4-dinitrobenzene



1-Methyl-3,5-dinitrobenzene



2-Methyl-1,3-dinitrobenzene



2-Methyl-1,4-dinitrobenzene


4-Methyl-1,2-dinitrobenzene


2-Methyl-4,6-dinitrophenol



4-Methyl-2,6-dinitrophenol



Methyldioctylamine



4-Methyl-1,3-dioxane



2-Methyl-1,3-dioxolane



4-Methyl-1,3-dioxolane



Methyldiphenylamine


4-Methyl-2,4-diphenyl-1-pentene



Methyldiphenylsilane



Methyldiphenylsilanol



2-Methyl-1,2-di-3-pyridinyl-1-propanone



Methyl docosanoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7226	Methyl *cis*-13-docosenoate		$C_{23}H_{44}O_2$	1120-34-9	352.594		-1.2	220^{5}			
7227	Methyl dodecanoate	Methyl laurate	$C_{13}H_{26}O_2$	111-82-0	214.344		5.2	267	0.8702^{20}	1.4319^{20}	i H_2O; msc EtOH, eth, ace, bz; s chl, ctc
7228	2-Methyldodecanoic acid		$C_{13}H_{26}O_2$	2874-74-0	214.344	pl	22	153^{1}	0.890^{18}		
7229	Methyl eicosanoate	Methyl arachidate	$C_{21}H_{42}O_2$	1120-28-1	326.557	lf (MeOH)	54.5	215^{10}		1.4317^{60}	vs bz, eth, EtOH, chl
7230	(Methyleneamino)acetonitrile		$C_3H_4N_2$	109-82-0	68.077		129				
7231	α-Methylenebenzeneacetic acid	Atropic acid	$C_9H_8O_2$	492-38-6	148.159	lf (al), nd (w)	106.5	dec 267			sl H_2O; s EtOH, eth, bz, chl, CS_2
7232	Methylenebis(4-cyclohexylisocyanate)		$C_{15}H_{22}N_2O_2$	5124-30-1	262.348	liq			1.066	1.4970^{20}	
7233	4,4'-Methylenebis[2,6-di-*tert*-butylphenol]	Bis(3,5-di-*tert*-butyl-4-hydroxyphenyl)methane	$C_{29}H_{44}O_2$	118-82-1	424.658		154	289^{40}, 250^{10}			
7234	4,4'-Methylenebis(*N*-methylaniline)	*N,N*'-Dimethyl-4,4'-diaminodiphenylmethane	$C_{15}H_{18}N_2$	1807-55-2	226.317						s ctc, CS_2
7235	Methylene blue		$C_{16}H_{18}ClN_3S$	61-73-4	319.852	dk grn cry or pow (chl-eth)					s H_2O, EtOH, chl; i eth; sl py
7236	Methylenecyclobutane		C_5H_8	1120-56-5	68.118	liq	-134.7	42.2	0.7401^{20}	1.4210^{20}	
7237	Methylenecyclohexane		C_7H_{12}	1192-37-6	96.170	liq	-106.7	102.5	0.8074^{20}	1.4523^{20}	i H_2O; s eth, bz, chl
7238	2-Methylenecyclohexanol		$C_7H_{12}O$	4065-80-9	112.169			83^{13}	0.955^{20}	1.4843^{20}	
7239	Methylenecyclopentane		C_6H_{10}	1528-30-9	82.143			75.5	0.7787^{20}	1.4355^{20}	s bz, chl
7240	Methylenecyclopropene		C_4H_4	4095-06-1	52.075	solid stab at -196					
7241	2,4'-Methylenedianiline	2,4'-Diaminodiphenylmethane	$C_{13}H_{14}N_2$	1208-52-2	198.263	lf (bz)	88.5	222^{9}			
7242	5,5'-Methylenedisalicylic acid		$C_{15}H_{12}O_6$	122-25-8	288.252	nd (bz)	243.5				vs ace, eth, EtOH
7243	5-Methylene-2(5*H*)-furanone	Protoanemonin	$C_5H_4O_2$	108-28-1	96.085	pa ye oil		73^{11}			sl H_2O; s chl
7244	3-Methyleneheptane		C_8H_{16}	1632-16-2	112.213			120	0.7270^{20}	1.4157^{20}	i H_2O; vs eth, bz, peth
7245	4-Methylene-1-isopropylbicyclo[3.1.0]hexan-3-ol, [1*S*-(1α,3β,5α)]	4(10)-Thujene-3-ol	$C_{10}H_{16}O$	471-16-9	152.233			208	0.9488^{19}	1.4871^{25}	s eth
7246	4-Methylene-1-isopropylcyclohexene		$C_{10}H_{16}$	99-84-3	136.234			173.5	0.838^{22}	1.4754^{22}	
7247	2-Methylenepentanedinitrile	2,4-Dicyano-1-butene	$C_6H_6N_2$	1572-52-7	106.125			103^{5}		1.4561^{20}	s chl
7248	Methylene thiocyanate	Dithiocyanatomethane	$C_3H_2N_2S_2$	6317-18-6	130.191	solid	102				
7249	2-Methylene-1,3,3-trimethylindoline	Fischer's base	$C_{12}H_{15}N$	118-12-7	173.254			244			sl H_2O; s EtOH, eth, bz, chl
7250	*N*-Methylephedrine, [*R*-(*R**,*S**)]	(1*R*,2*S*)-*N*-Methylephedrine	$C_{11}H_{17}NO$	552-79-4	179.259	nd or pl (al, eth)	87.5				i H_2O; s EtOH, eth, MeOH
7251	Methylergonovine	Methylergometrine	$C_{20}H_{25}N_3O_2$	113-42-8	339.432	pr (MeOH,ace)	172				i H_2O; s EtOH, ace
7252	*N*-Methyl-1,2-ethanediamine		$C_3H_{10}N_2$	109-81-9	74.124			115	0.841^{25}	1.4395^{20}	
7253	*N*-Methyl-2-ethanolamine		C_3H_9NO	109-83-1	75.109			158	0.937^{20}	1.4385^{20}	msc H_2O, EtOH, eth
7254	1-(1-Methylethoxy)butane	Butyl isopropyl ether	$C_7H_{16}O$	1860-27-1	116.201			108	0.7594^{15}	1.3870^{15}	i H_2O; s EtOH, eth, ace, con sulf
7255	2-[2-(1-Methylethoxy)ethyl] pyridine		$C_{10}H_{15}NO$	70715-19-4	165.232			133^{50}	0.9502^{25}	1.4820^{25}	vs H_2O
7256	1-(1-Methylethoxy)propane		$C_6H_{14}O$	627-08-7	102.174			83	0.7370^{20}	1.376^{21}	sl H_2O; vs EtOH; s eth, ace
7257	1-(1-Methylethoxy)-2-propanol	1-Isopropoxy-2-propanol	$C_6H_{14}O_2$	3944-36-3	118.174			137.5	0.879^{20}	1.4070^{20}	
7258	Methyl 2-ethylacetoacetate		$C_7H_{12}O_3$	51756-08-2	144.168			182	0.995^{14}		vs ace, eth, EtOH
7259	5-(1-Methylethylidene)-1,3-cyclopentadiene		C_8H_{10}	2175-91-9	106.165		1.4	155; 49^{11}	0.881^{20}	1.5474^{20}	
7260	1-Methyl-9*H*-fluorene		$C_{14}H_{12}$	1730-37-6	180.245		87				
7261	9-Methyl-9*H*-fluorene		$C_{14}H_{12}$	2523-37-7	180.245	pr	46.5	155^{15}	1.0263^{66}	1.610^{66}	i H_2O; s EtOH, eth, ace, bz, chl
7262	Methyl fluorosulfonate		CH_3FO_3S	421-20-5	114.096	col liq	-95	93	1.412	1.3326^{20}	
7263	*N*-Methylformamide		C_2H_5NO	123-39-7	59.067	liq	-3.8	199.51	1.011^{19}	1.4319^{20}	vs H_2O, ace, EtOH
7264	Methyl formate		$C_2H_4O_2$	107-31-3	60.052	liq	-99	31.7	0.9713^{20}	1.3419^{20}	vs H_2O; msc EtOH; s eth, chl, MeOH
7265	Methyl 4-formylbenzoate		$C_9H_8O_3$	1571-08-0	164.158	nd (w)	63	265			
7266	2-Methylfuran		C_5H_6O	534-22-5	82.101	liq	-91.3	64.7	0.9132^{20}	1.4342^{20}	sl H_2O, ctc; s EtOH, eth



Methyl *cis*-13-docosenoate



Methyl dodecanoate



2-Methyldodecanoic acid



Methyl eicosanoate



(Methyleneamino)acetonitrile


α-Methylenebenzeneacetic acid


Methylenebis(4-cyclohexylisocyanate)


4,4'-Methylenebis[2,6-di-*tert*-butylphenol]


4,4'-Methylenebis(*N*-methylaniline)


Methylene blue



Methylenecyclobutane



Methylenecyclohexane



2-Methylenecyclohexanol



Methylenecyclopentane



Methylenecyclopropene



2,4'-Methylenedianiline



5,5'-Methylenedisalicylic acid



5-Methylene-2(5*H*)-furanone



3-Methyleneheptane



4-Methylene-1-isopropylbicyclo[3.1.0]hexan-3-ol, [1*S*-(1α,3β,5α)]



4-Methylene-1-isopropylcyclohexene



2-Methylenepentanedinitrile



Methylene thiocyanate



2-Methylene-1,3,3-trimethylindoline



N-Methylephedrine, [*R*-(*R**,*S**)]



Methylergonovine



N-Methyl-1,2-ethanediamine



N-Methyl-2-ethanolamine



1-(1-Methylethoxy)butane



2-[2-(1-Methylethoxy)ethyl]pyridine



1-(1-Methylethoxy)propane


1-(1-Methylethoxy)-2-propanol


Methyl 2-ethylacetoacetate


5-(1-Methylethylidene)-1,3-cyclopentadiene



1-Methyl-9*H*-fluorene


9-Methyl-9*H*-fluorene


Methyl fluorosulfonate


N-Methylformamide



Methyl formate



Methyl 4-formylbenzoate



2-Methylfuran


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7267	3-Methylfuran		C_5H_6O	930-27-8	82.101			65.5	0.923^{18}	1.4330^{19}	i H_2O; s EtOH, eth
7268	5-Methyl-2-furancarboxaldehyde		$C_6H_6O_2$	620-02-0	110.111			187; 89^{26}	1.1072^{18}	1.5264^{20}	s H_2O; vs EtOH; msc eth; sl ctc
7269	Methyl 2-furancarboxylate	Methyl 2-furanoate	$C_6H_6O_3$	611-13-2	126.110			181.3	1.1786^{21}	1.4860^{20}	i H_2O; s EtOH, eth, bz, chl
7270	3-Methyl-2,5-furandione		$C_5H_4O_3$	616-02-4	112.084		7.5	213.5	1.2469^{16}	1.4710^{21}	vs ace, eth, EtOH
7271	*N*-Methyl-2-furanmethanamine		C_6H_9NO	4753-75-7	111.141			149	0.989^{25}	1.4729^{20}	
7272	5-Methyl-2-furanmethanol		$C_6H_8O_2$	3857-25-8	112.127			dec 195; 81^{23}	1.0769^{20}	1.4853^{20}	vs eth, EtOH
7273	α-Methyl-2-furanmethanol		$C_6H_8O_2$	4208-64-4	112.127			162.5	1.0739^{25}	1.4827^{15}	
7274	5-Methyl-2(3*H*)-furanone		$C_5H_6O_2$	591-12-8	98.101	nd	18	56^{12}	1.084^{20}	1.4476^{20}	s H_2O, EtOH, eth, CS_2; sl ctc
7275	5-Methyl-2(5*H*)-furanone		$C_5H_6O_2$	591-11-7	98.101		<-17	209; 98^{15}	1.0810^{20}	1.4454^{20}	msc H_2O; s EtOH, eth
7276	Methylgermane		CH_6Ge	1449-65-6	90.70	col gas	-158	-23			
7277	Methyl β-*D*-glucopyranoside		$C_7H_{14}O_6$	709-50-2	194.182		109				s H_2O
7278	Methyl α-*D*-glucopyranoside	α-Methylglucoside	$C_7H_{14}O_6$	97-30-3	194.182	orth nd (al)	168	200$^{0.2}$	1.46^{30}		vs H_2O
7279	3-Methylglutaric acid	3-Methylpentanedioic acid	$C_6H_{10}O_4$	626-51-7	146.141		87	166$^{0.5}$			s H_2O, EtOH, eth; sl bz, chl; i lig
7280	Methyl Green		$C_{27}H_{35}BrClN_3$	14855-76-6	516.944	grn pow (al)					vs H_2O
7281	Methyl heptadecanoate		$C_{18}H_{36}O_2$	1731-92-6	284.478	pl (al)	30	185^{9}, 152$^{0.05}$			i H_2O; s EtOH, ace, ctc; vs eth, bz
7282	Methyl heptafluorobutanoate		$C_5H_3F_7O_2$	356-24-1	228.066	liq	-86	80	1.483^{20}	1.295^{20}	sl H_2O; s eth, ace
7283	6-Methyl-2-heptanamine, (±)	Octodrine	$C_8H_{19}N$	5984-58-7	129.244	visc liq		155	0.767^{25}	1.4209^{20}	
7284	*N*-Methyl-2-heptanamine		$C_8H_{19}N$	540-43-2	129.244			155			
7285	2-Methylheptane		C_8H_{18}	592-27-8	114.229	liq	-109.02	117.66	0.6980^{20}	1.3949^{20}	i H_2O; msc EtOH, ace, bz; s eth, ctc
7286	3-Methylheptane		C_8H_{18}	589-81-1	114.229	col liq	-120.48	118.9	0.7017^{25}	1.3961^{25}	i H_2O; s EtOH, eth; msc ace, bz, chl
7287	4-Methylheptane		C_8H_{18}	589-53-7	114.229	liq	-121.0	117.72	0.7046^{20}	1.3979^{20}	i H_2O; s eth; msc EtOH, ace, bz
7288	Methyl heptanoate		$C_8H_{16}O_2$	106-73-0	144.212	liq	-56	174	0.8815^{20}	1.4152^{20}	sl H_2O, ctc, ace; s EtOH, eth
7289	2-Methyl-1-heptanol, (±)		$C_8H_{18}O$	111675-77-5	130.228	col liq	-112	175.6	0.8022^{20}	1.424^{20}	
7290	3-Methyl-1-heptanol		$C_8H_{18}O$	1070-32-2	130.228	liq	-90	186; 101^{20}	0.824^{24}	1.4295^{25}	
7291	4-Methyl-1-heptanol		$C_8H_{18}O$	817-91-4	130.228			188	0.8065^{25}	1.4253^{25}	vs EtOH
7292	5-Methyl-1-heptanol, (±)		$C_8H_{18}O$	111767-95-4	130.228	col liq	-104	186.6	0.8153^{25}	1.4272^{25}	
7293	6-Methyl-1-heptanol	Isooctyl alcohol	$C_8H_{18}O$	1653-40-3	130.228	liq	-106	188; 95.8^{20}	0.8176^{25}	1.4251^{25}	i H_2O; s EtOH, eth
7294	2-Methyl-2-heptanol		$C_8H_{18}O$	625-25-2	130.228	liq	-50.4	156	0.8142^{20}	1.4250^{20}	i H_2O; s EtOH, eth
7295	3-Methyl-2-heptanol		$C_8H_{18}O$	31367-46-1	130.228			166.1	0.8177^{25}	1.4199^{25}	i H_2O; s EtOH, eth, ctc
7296	4-Methyl-2-heptanol		$C_8H_{18}O$	56298-90-9	130.228	col liq	-102	171.6	0.8027^{20}	1.424^{20}	
7297	5-Methyl-2-heptanol		$C_8H_{18}O$	54630-50-1	130.228	liq	-61	170	0.8174^{21}		
7298	6-Methyl-2-heptanol		$C_8H_{18}O$	4730-22-7	130.228	liq	-105	174	0.8218^{20}	1.4238^{10}	
7299	2-Methyl-3-heptanol, (±)		$C_8H_{18}O$	100296-26-2	130.228	liq	-85	167.5	0.8235^{20}	1.4265^{20}	sl H_2O; s EtOH, eth, ctc
7300	3-Methyl-3-heptanol	2-Ethyl-2-hexanol	$C_8H_{18}O$	5582-82-1	130.228	liq	-83	163	0.8282^{20}	1.4279^{20}	i H_2O; s EtOH, eth, ctc
7301	4-Methyl-3-heptanol		$C_8H_{18}O$	14979-39-6	130.228	liq	-123	170	0.827^{25}	1.4300^{20}	
7302	5-Methyl-3-heptanol		$C_8H_{18}O$	18720-65-5	130.228	liq	-91.2	172	0.8425^{25}	1.433^{24}	
7303	6-Methyl-3-heptanol, (±)		$C_8H_{18}O$	100295-85-0	130.228	col liq	-61	169	0.8220^{20}	1.4254^{20}	
7304	2-Methyl-4-heptanol		$C_8H_{18}O$	21570-35-4	130.228	liq	-81	164	0.8207^{20}	1.4203	vs eth, EtOH
7305	3-Methyl-4-heptanol		$C_8H_{18}O$	1838-73-9	130.228	liq		164.7	0.8329^{25}	1.4211^{25}	sl H_2O; s EtOH, eth, ctc
7306	4-Methyl-4-heptanol		$C_8H_{18}O$	598-01-6	130.228	liq	-82	161	0.8248^{20}	1.4258^{20}	i H_2O; s EtOH, eth, ctc
7307	6-Methyl-2-heptanol acetate		$C_{10}H_{20}O_2$	67952-57-2	172.265			187	0.8474^{20}	1.413^{20}	vs EtOH
7308	6-Methyl-2-heptanone		$C_8H_{16}O$	928-68-7	128.212			167	0.8151^{20}	1.4162^{20}	sl H_2O; vs EtOH, eth; msc ace, bz, chl
7309	5-Methyl-3-heptanone		$C_8H_{16}O$	541-85-5	128.212	liq		161			
7310	6-Methyl-3-heptanone		$C_8H_{16}O$	624-42-0	128.212			164	0.8304^{20}	1.4209^{20}	i H_2O; s EtOH, eth, bz, ctc
7311	2-Methyl-4-heptanone	Isobutyl propyl ketone	$C_8H_{16}O$	626-33-5	128.212			154	0.813^{22}		i H_2O; s EtOH, eth



3-Methylfuran


5-Methyl-2-furancarboxaldehyde



Methyl 2-furancarboxylate



3-Methyl-2,5-furandione


N-Methyl-2-furanmethanamine



5-Methyl-2-furanmethanol



α-Methyl-2-furanmethanol



5-Methyl-2(3*H*)-furanone



5-Methyl-2(5*H*)-furanone



Methylgermane



Methyl β-*D*-glucopyranoside



Methyl α-*D*-glucopyranoside



3-Methylglutaric acid



Methyl Green



Methyl heptadecanoate



Methyl heptafluorobutanoate



6-Methyl-2-heptanamine, (±)



N-Methyl-2-heptanamine



2-Methylheptane



3-Methylheptane



4-Methylheptane



Methyl heptanoate



2-Methyl-1-heptanol, (±)



3-Methyl-1-heptanol



4-Methyl-1-heptanol



5-Methyl-1-heptanol, (±)



6-Methyl-1-heptanol



2-Methyl-2-heptanol



3-Methyl-2-heptanol



4-Methyl-2-heptanol



5-Methyl-2-heptanol



6-Methyl-2-heptanol



2-Methyl-3-heptanol, (±)



3-Methyl-3-heptanol



4-Methyl-3-heptanol



5-Methyl-3-heptanol



6-Methyl-3-heptanol, (±)



2-Methyl-4-heptanol



3-Methyl-4-heptanol



4-Methyl-4-heptanol


6-Methyl-2-heptanol acetate



6-Methyl-2-heptanone



5-Methyl-3-heptanone



6-Methyl-3-heptanone



2-Methyl-4-heptanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7312	2-Methyl-1-heptene		C_8H_{16}	15870-10-7	112.213	liq	-90	119.3	0.7104^{25}	1.4123^{20}	
7313	6-Methyl-1-heptene		C_8H_{16}	5026-76-6	112.213			113.2	0.7079^{25}	1.4070^{20}	
7314	2-Methyl-2-heptene		C_8H_{16}	627-97-4	112.213			122.6	0.7200^{25}	1.4170^{20}	i H_2O; s eth, bz, ctc, chl
7315	*cis*-3-Methyl-2-heptene		C_8H_{16}	22768-19-0	112.213			122	0.725^{25}	1.419^{20}	
7316	6-Methyl-5-hepten-2-ol		$C_8H_{16}O$	1569-60-4	128.212			175	0.8545^{20}	1.4505^{20}	
7317	3-Methyl-5-hepten-2-one		$C_8H_{14}O$	38552-72-6	126.196			63^{20}	0.8463^{18}	1.4345^{18}	
7318	6-Methyl-5-hepten-2-one		$C_8H_{14}O$	110-93-0	126.196		173.5		0.8546^{16}	1.4445^{20}	vs eth, EtOH
7319	2-Methylheptyl acetate, (±)		$C_{10}H_{20}O_2$	74112-36-0	172.265			195	0.8626^{14}	1.4146^{20}	vs eth, EtOH
7320	2-Methyl-1,5-hexadiene		C_7H_{12}	4049-81-4	96.170	liq	-128.8	88.1	0.7153^{25}	1.4183^{20}	
7321	Methyl *trans,trans*-2,4-hexadienoate	Methyl sorbate	$C_7H_{10}O_2$	689-89-4	126.153	lf	15	180; 70^{20}	0.9777^{20}	1.5025^{22}	i H_2O; s EtOH, eth
7322	2-Methylhexanal		$C_7H_{14}O$	925-54-2	114.185	liq		141; 132^{60}			
7323	3-Methylhexanal	3-Methylcaproaldehyde	$C_7H_{14}O$	19269-28-4	114.185			143	0.8203^{20}	1.4122^{20}	i H_2O; s EtOH, eth
7324	3-Methyl-1-hexanamine		$C_7H_{17}N$	65530-93-0	115.217			149; 67^{45}	0.772^{26}	1.4249^{25}	
7325	4-Methyl-2-hexanamine		$C_7H_{17}N$	105-41-9	115.217			132.5	0.7655^{20}	1.4150^{25}	sl H_2O; vs EtOH, eth, chl, dil acid
7326	2-Methylhexane		C_7H_{16}	591-76-4	100.202	liq	-118.2	90.04	0.6787^{20}	1.3848^{20}	i H_2O; s EtOH; msc eth, ace, bz, lig, chl
7327	3-Methylhexane		C_7H_{16}	78918-91-9	100.202	liq	-119.4	92	0.687^{21}	1.3854^{25}	i H_2O; s EtOH; msc eth, ace, bz, lig, chl
7328	5-Methyl-2,3-hexanedione	2-Methylhexa-4,5-dione	$C_7H_{12}O_2$	13706-86-0	128.169			138	0.908^{22}	1.4119^{20}	
7329	Methyl hexanoate	Methyl caproate	$C_7H_{14}O_2$	106-70-7	130.185	liq	-71	149.5	0.8846^{20}	1.4049^{20}	i H_2O; vs EtOH, eth; s ace, bz, ctc
7330	2-Methylhexanoic acid		$C_7H_{14}O_2$	4536-23-6	130.185			215.5	0.918^{20}	1.4193^{20}	vs ace, bz, eth, EtOH
7331	2-Methyl-1-hexanol, (±)		$C_7H_{16}O$	111768-04-8	116.201			164; 71^{15}	0.826^{20}	1.4226^{20}	vs eth, EtOH
7332	5-Methyl-1-hexanol		$C_7H_{16}O$	627-98-5	116.201			169; 54^{15}	0.8192^{24}	1.4175^{20}	vs eth, EtOH
7333	2-Methyl-2-hexanol		$C_7H_{16}O$	625-23-0	116.201			143	0.8119^{20}	1.4175^{20}	sl H_2O; msc EtOH, eth
7334	3-Methyl-2-hexanol		$C_7H_{16}O$	2313-65-7	116.201			151; 80^{52}	0.8220^{25}	1.4198^{18}	i H_2O; vs EtOH, eth; s ace
7335	5-Methyl-2-hexanol		$C_7H_{16}O$	627-59-8	116.201			151; 78^{28}	0.814^{20}	1.4180^{20}	sl H_2O; s EtOH, eth
7336	3-Methyl-3-hexanol		$C_7H_{16}O$	597-96-6	116.201			143	0.8233^{20}	1.4231^{20}	sl H_2O; s EtOH, eth, ctc
7337	5-Methyl-2-hexanone	Methyl isopentyl ketone	$C_7H_{14}O$	110-12-3	114.185			144	0.888^{20}	1.4062^{20}	sl H_2O; msc EtOH; vs ace, bz; s ctc
7338	2-Methyl-3-hexanone	Propyl isopropyl ketone	$C_7H_{14}O$	7379-12-6	114.185			135	0.8091^{20}	1.4042^{20}	s EtOH, eth, chl; vs ace
7339	5-Methyl-2-hexanone oxime		$C_7H_{15}NO$	624-44-2	129.200			195.5	0.8881^{20}	1.4448^{20}	sl chl
7340	2-Methyl-1-hexene		C_7H_{14}	6094-02-6	98.186	liq	-102.8	92	0.7000^{20}	1.4035^{20}	
7341	3-Methyl-1-hexene		C_7H_{14}	3404-61-3	98.186			83.9	0.6871^{25}	1.3965^{20}	
7342	4-Methyl-1-hexene		C_7H_{14}	3769-23-1	98.186	liq	-141.5	86.7	0.6942^{25}	1.4000^{20}	
7343	5-Methyl-1-hexene		C_7H_{14}	3524-73-0	98.186			85.3	0.6877^{25}	1.3967^{20}	
7344	2-Methyl-2-hexene		C_7H_{14}	2738-19-4	98.186	liq	-130.4	95.4	0.7038^{25}	1.4106^{20}	
7345	*cis*-3-Methyl-2-hexene		C_7H_{14}	10574-36-4	98.186	liq	-118.5	95.6	0.712^{20}	1.4126^{20}	
7346	*cis*-4-Methyl-2-hexene		C_7H_{14}	3683-19-0	98.186			86.3	0.6952^{25}	1.4026^{20}	
7347	*trans*-4-Methyl-2-hexene		C_7H_{14}	3683-22-5	98.186	liq	-125.7	87.6	0.6925^{25}	1.4025^{20}	
7348	*cis*-5-Methyl-2-hexene		C_7H_{14}	13151-17-2	98.186			89.5	0.697^{25}	1.404^{20}	
7349	*trans*-5-Methyl-2-hexene		C_7H_{14}	7385-82-2	98.186	liq	-124.3	88.1	0.6883^{25}	1.4006^{20}	
7350	*cis*-2-Methyl-3-hexene		C_7H_{14}	15840-60-5	98.186			86	0.690^{25}	1.401^{20}	
7351	*trans*-2-Methyl-3-hexene		C_7H_{14}	692-24-0	98.186	liq	-141.6	85.9	0.6853^{25}	1.4001^{20}	
7352	*cis*-3-Methyl-3-hexene		C_7H_{14}	4914-89-0	98.186			95.4	0.7079^{25}	1.4126^{20}	
7353	*trans*-3-Methyl-3-hexene		C_7H_{14}	3899-36-3	98.186			93.5	0.7050^{25}	1.4109^{20}	
7354	Methyl 3-hexenoate		$C_7H_{12}O_2$	2396-78-3	128.169			67^{34}	0.9132^{25}	1.4240^{23}	
7355	5-Methyl-3-hexen-2-one	2-Oxo-5-methylhex-3-ene	$C_7H_{12}O$	5166-53-0	112.169			77^{50}, 65^{13}	0.8549^{28}	1.4395^{22}	
7356	5-Methyl-5-hexen-2-one		$C_7H_{12}O$	3240-09-3	112.169			150	0.8460^{20}	1.4348^{20}	vs ace, eth, EtOH
7357	5-Methyl-1-hexyne		C_7H_{12}	2203-80-7	96.170	liq	-125	92	0.7274^{20}	1.4059^{-20}	i H_2O; s EtOH, eth, bz, chl, peth
7358	5-Methyl-2-hexyne		C_7H_{12}	53566-37-3	96.170	liq	-92.9	102.5	0.7378^{20}	1.4176^{20}	i H_2O; s eth, ace, bz, chl, peth
7359	2-Methyl-3-hexyne		C_7H_{12}	36566-80-0	96.170	liq	-116.7	95.2	0.7263^{20}	1.4120^{20}	vs bz, eth, chl, peth
7360	Methyl 2-hexynoate		$C_7H_{10}O_2$	18937-79-6	126.153			80^{23}	0.9648^{25}		


2-Methyl-1-heptene



6-Methyl-1-heptene


2-Methyl-2-heptene



cis-3-Methyl-2-heptene




6-Methyl-5-hepten-2-ol




3-Methyl-5-hepten-2-one




6-Methyl-5-hepten-2-one




2-Methylheptyl acetate, (±)



2-Methyl-1,5-hexadiene




Methyl *trans*,*trans*-2,4-hexadienoate




2-Methylhexanal




3-Methylhexanal





3-Methyl-1-hexanamine




4-Methyl-2-hexanamine


2-Methylhexane



3-Methylhexane




5-Methyl-2,3-hexanedione




Methyl hexanoate




2-Methylhexanoic acid




2-Methyl-1-hexanol, (±)




5-Methyl-1-hexanol




2-Methyl-2-hexanol




3-Methyl-2-hexanol




5-Methyl-2-hexanol




3-Methyl-3-hexanol




5-Methyl-2-hexanone





2-Methyl-3-hexanone





5-Methyl-2-hexanone oxime



2-Methyl-1-hexene



3-Methyl-1-hexene



4-Methyl-1-hexene



5-Methyl-1-hexene



2-Methyl-2-hexene



cis-3-Methyl-2-hexene



cis-4-Methyl-2-hexene



trans-4-Methyl-2-hexene



cis-5-Methyl-2-hexene



trans-5-Methyl-2-hexene


cis-2-Methyl-3-hexene



trans-2-Methyl-3-hexene


cis-3-Methyl-3-hexene



trans-3-Methyl-3-hexene




Methyl 3-hexenoate





5-Methyl-3-hexen-2-one




5-Methyl-5-hexen-2-one


5-Methyl-1-hexyne



5-Methyl-2-hexyne



2-Methyl-3-hexyne




Methyl 2-hexynoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7361	*L*-1-Methylhistidine		$C_7H_{11}N_3O_2$	332-80-9	169.181	pl (DMF aq)	249				
7362	*L*-3-Methylhistidine		$C_7H_{11}N_3O_2$	368-16-1	169.181		250				
7363	Methylhydrazine		CH_6N_2	60-34-4	46.072	liq	-52.36	87.5		1.4325^{20}	s H_2O, eth, ctc; msc EtOH; i lig
7364	Methyl hydrazinecarboxylate	Methyl carbazate	$C_2H_6N_2O_2$	6294-89-9	90.081		73	108^{12}			s H_2O, EtOH; sl bz; i peth
7365	Methyl hydrogen succinate	Monomethyl succinate	$C_5H_8O_4$	3878-55-5	132.116		58	151^{20}, 122^{4}			s H_2O
7366	Methyl hydroperoxide	Methyl hydrogen peroxide	CH_4O_2	3031-73-0	48.042	liq	-72	86; 39^{65}	1.9967^{15}	1.3641^{15}	vs H_2O, bz, eth, EtOH
7367	Methyl hydroxyacetate		$C_3H_6O_3$	96-35-5	90.078			149; 52^{17}	1.1677^{18}		s H_2O; msc EtOH, eth
7368	Methyl 3-hydroxybenzoate		$C_8H_8O_3$	19438-10-9	152.148	nd (bz-peth)	73	281; 178^{17}	1.1528^{100}		s EtOH, bz, peth; sl chl
7369	Methyl 4-hydroxybenzoate	Methylparaben	$C_8H_8O_3$	99-76-3	152.148	nd (dil al)	131	dec 275			sl H_2O; vs EtOH, eth, ace; s tfa
7370	Methyl α-hydroxydiphenylacetate	Methyl diphenylglycolate	$C_{15}H_{14}O_3$	76-89-1	242.270	mcl or tcl cry (al)	75.8	187^{13}			vs eth, EtOH
7371	*O*-Methylhydroxylamine	Methoxyamine	CH_5NO	67-62-9	47.057			49			
7372	*O*-Methylhydroxylamine hydrochloride	Methoxyamine hydrochloride	CH_6ClNO	593-56-6	83.518	pr	150.0				vs H_2O, EtOH
7373	Methyl 4-hydroxy-3-methoxybenzoate		$C_9H_{10}O_4$	3943-74-6	182.173	nd (dil al)	64	286			s EtOH, peth; sl chl
7374	Methyl 2-hydroxy-3-methylbenzoate		$C_9H_{10}O_3$	23287-26-5	166.173		29	235	1.1683^{25}	1.5354^{16}	
7375	Methyl 2-hydroxy-5-methylbenzoate		$C_9H_{10}O_3$	22717-57-3	166.173	liq	-1	244.5	1.1673^{25}	1.5351^{15}	
7376	Methyl 2-hydroxy-2-methylpropanoate	Methyl 2-methyllactate	$C_5H_{10}O_3$	2110-78-3	118.131			137		1.4056^{20}	vs H_2O, EtOH
7377	Methyl 3-hydroxy-2-naphthalenecarboxylate	Methyl 3-hydroxy-2-naphthoate	$C_{12}H_{10}O_3$	883-99-8	202.205	pa ye orth nd (dil MeOH)	75.5	206			i H_2O; s EtOH
7378	Methyl α-hydroxyphenylacetate, (±)	(±)-Methyl mandelate	$C_9H_{10}O_3$	4358-87-6	166.173	pl (bz-lig)	58	dec 250; 144^{20}	1.1756^{20}		vs EtOH, chl
7379	1-Methylimidazol		$C_4H_6N_2$	616-47-7	82.104	liq	-6	195.5	1.0325^{20}	1.4970^{20}	vs H_2O, ace, eth, EtOH
7380	2-Methyl-1*H*-imidazole		$C_4H_6N_2$	693-98-1	82.104		144	267			vs H_2O, EtOH
7381	4-Methyl-1*H*-imidazole		$C_4H_6N_2$	822-36-6	82.104		56	263	1.0416^{14}	1.5037^{14}	vs H_2O, EtOH
7382	*N*-Methyliminodiacetic acid	*N*-(Carboxymethyl)-*N*-methylglycine	$C_5H_9NO_4$	4408-64-4	147.130	cry (w)	226				s H_2O; i EtOH, eth
7383	1-Methyl-1*H*-indene		$C_{10}H_{10}$	767-59-9	130.186			199; 82^{15}	0.970^{25}	1.5616^{20}	
7384	2-Methyl-1*H*-indene		$C_{10}H_{10}$	2177-47-1	130.186		80	208	0.974^{25}	1.5652^{20}	i H_2O; s eth, ace, bz
7385	3-Methyl-1*H*-indene		$C_{10}H_{10}$	767-60-2	130.186			198	0.972^{25}	1.5621^{20}	i H_2O; s eth, ace, bz
7386	1-Methyl-1*H*-indole		C_9H_9N	603-76-9	131.174			237	1.0707^{25}		i H_2O; s EtOH, eth, bz
7387	2-Methyl-1*H*-indole		C_9H_9N	95-20-5	131.174	pl (dil al) nd or lf (w)	61	272	1.07^{20}		sl H_2O; vs EtOH, eth; s ace, bz
7388	3-Methyl-1*H*-indole	Skatole	C_9H_9N	83-34-1	131.174	lf (lig)	97.5	266			s H_2O, EtOH, eth, ace, bz, chl
7389	5-Methyl-1*H*-indole		C_9H_9N	614-96-0	131.174		60	267	1.0202^{78}		s H_2O, EtOH, eth, bz, lig
7390	7-Methyl-1*H*-indole		C_9H_9N	933-67-5	131.174		85	266	1.0202^{100}		
7391	Methyl 2-iodobenzoate		$C_8H_7IO_2$	610-97-9	262.045			280; 146^{16}		1.6052^{20}	s EtOH
7392	Methyl 3-iodobenzoate		$C_8H_7IO_2$	618-91-7	262.045	nd (dil al)	54.5	277; 150^{18}			i H_2O, lig; s EtOH; vs eth, ace
7393	Methyl 4-iodobenzoate		$C_8H_7IO_2$	619-44-3	262.045	nd (eth-al)	114.8	sub	2.0200^{10}		s EtOH, eth
7394	5-Methyl-1,3-isobenzofurandione		$C_9H_6O_3$	19438-61-0	162.142		93.0	295			
7395	Methyl isobutanoate		$C_5H_{10}O_2$	547-63-7	102.132	liq	-84.7	92.5	0.8906^{20}	1.3840^{20}	sl H_2O; msc EtOH, eth; s ace, ctc
7396	Methyl isocyanate		C_2H_3NO	624-83-9	57.051	liq	-45	39.5	0.9230^{27}	1.3419^{18}	vs H_2O
7397	2-Methyl-1*H*-isoindole-1,3(2*H*)-dione		$C_9H_7NO_2$	550-44-7	161.158	nd (al), lf (sub)	134	286			i H_2O; sl EtOH
7398	Methyl isopentanoate	Methyl isovalerate	$C_6H_{12}O_2$	556-24-1	116.158			116.5	0.8808^{20}	1.3927^{20}	i H_2O; vs EtOH, eth, ace
7399	6-Methyl-*N*-isopentyl-2-heptanamine	Octamylamine	$C_{13}H_{29}N$	502-59-0	199.376			100^{7}			
7400	2-Methyl-5-isopropylaniline		$C_{10}H_{15}N$	2051-53-8	149.233	liq	-16	241	0.9942^{20}	1.5387^{20}	s ctc, CS_2
7401	α-Methyl-4-isopropylbenzenepropanal	3-*p*-Cumenyl-2-methylpropionaldehyde	$C_{13}H_{18}O$	103-95-7	190.281			270; 135^{99}	0.9459^{20}	1.5068^{20}	vs bz, eth, EtOH
7402	2-Methyl-5-isopropylbicyclo[3.1.0]hex-2-ene		$C_{10}H_{16}$	2867-05-2	136.234			151	0.8301^{20}	1.4515^{20}	


L-1-Methylhistidine



L-3-Methylhistidine



Methylhydrazine



Methyl hydrazinecarboxylate



Methyl hydrogen succinate


Methyl hydroperoxide



Methyl hydroxyacetate



Methyl 3-hydroxybenzoate



Methyl 4-hydroxybenzoate



Methyl α-hydroxydiphenylacetate



O-Methylhydroxylamine



O-Methylhydroxylamine hydrochloride



Methyl 4-hydroxy-3-methoxybenzoate


Methyl 2-hydroxy-3-methylbenzoate


Methyl 2-hydroxy-5-methylbenzoate



Methyl 2-hydroxy-2-methylpropanoate



Methyl 3-hydroxy-2-naphthalenecarboxylate


Methyl α-hydroxyphenylacetate, (±)



1-Methylimidazol



2-Methyl-1*H*-imidazole



4-Methyl-1*H*-imidazole



N-Methyliminodiacetic acid



1-Methyl-1*H*-indene



2-Methyl-1*H*-indene


3-Methyl-1*H*-indene



1-Methyl-1*H*-indole



2-Methyl-1*H*-indole



3-Methyl-1*H*-indole



5-Methyl-1*H*-indole



7-Methyl-1*H*-indole



Methyl 2-iodobenzoate



Methyl 3-iodobenzoate



Methyl 4-iodobenzoate



5-Methyl-1,3-isobenzofurandione



Methyl isobutanoate



Methyl isocyanate



2-Methyl-1*H*-isoindole-1,3(2*H*)-dione


Methyl isopentanoate



6-Methyl-*N*-isopentyl-2-heptanamine



2-Methyl-5-isopropylaniline



α-Methyl-4-isopropylbenzenepropanal



2-Methyl-5-isopropylbicyclo[3.1.0]hex-2-ene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7403	2-Methyl-5-isopropyl-2,5-cyclohexadiene-1,4-dione		$C_{10}H_{12}O_2$	490-91-5	164.201		45.5	232			s chl
7404	*cis*-1-Methyl-4-isopropylcyclohexane		$C_{10}H_{20}$	6069-98-3	140.266	liq	-89.9	172	0.8039^{20}	1.4431^{20}	i H_2O; vs EtOH, eth; s bz, peth
7405	*trans*-1-Methyl-4-isopropylcyclohexane	*trans-p*-Menthane	$C_{10}H_{20}$	1678-82-6	140.266	oil	-86.3	170.6	0.7928^{20}	1.4366^{20}	vs bz, eth, EtOH, lig
7406	1-Methyl-4-isopropylcyclohexanol		$C_{10}H_{20}O$	21129-27-1	156.265			208.5	0.90^{20}	1.4619^{20}	
7407	5-Methyl-2-isopropylcyclohexanol, [1*S*-(1α,2β,5α)]-	(+)-Menthol	$C_{10}H_{20}O$	15356-60-2	156.265		39	103^{9}			vs ace, bz, eth, EtOH
7408	5-Methyl-2-isopropylcyclohexanol, [1*R*-(1α,2β,5α)]-	(-)-Menthol	$C_{10}H_{20}O$	2216-51-5	156.265	nd (MeOH)	43	216	0.903^{15}	1.460^{22}	sl H_2O; vs EtOH, eth, ace, bz; s peth
7409	5-Methyl-2-isopropylcyclohexanol, [1*S*-(1α,2α,5β)]-	(+)-Neomenthol	$C_{10}H_{20}O$	2216-52-6	156.265	oil	-22	211.7	0.897^{22}	1.4600^{20}	vs ace, EtOH
7410	5-Methyl-2-isopropylcyclohexanol, [1*S*-(1α,2β,5β)]-	(+)-Isomenthol	$C_{10}H_{20}O$	23283-97-8	156.265	nd(dil al)	82.5	218			vs eth, EtOH
7411	5-Methyl-2-isopropylcyclohexanol acetate, [1*R*-(1α,2α,5β)]		$C_{12}H_{22}O_2$	2623-23-6	198.302			222; 109^{10}	0.9244^{20}	1.4469^{20}	
7412	*cis*-5-Methyl-2-isopropylcyclohexanone	Menthone	$C_{10}H_{18}O$	491-07-6	154.249			205; 89^{15}	0.8995^{20}	1.4527^{20}	
7413	*trans*-5-Methyl-2-isopropylcyclohexanone, (2*S*)	*l*-Menthone	$C_{10}H_{18}O$	14073-97-3	154.249	liq	-6	207	0.8954^{20}	1.4505^{20}	sl H_2O; msc EtOH, eth, bz, CS_2; s ace
7414	1-Methyl-4-isopropylcyclohexene		$C_{10}H_{18}$	5502-88-5	138.250			174.5	0.8457^{15}	1.4735^{20}	
7415	3-Methyl-6-isopropyl-2-cyclohexen-1-ol		$C_{10}H_{18}O$	491-04-3	154.249			$97^{15.5}$	0.9119^{25}	1.4729^{25}	
7416	4-Methyl-1-isopropyl-3-cyclohexen-1-ol		$C_{10}H_{18}O$	562-74-3	154.249			209	0.926^{20}	1.4785^{19}	
7417	5-Methyl-2-isopropylcyclohexyl ethoxyacetate, (1α,2β,5α)		$C_{14}H_{26}O_3$	579-94-2	242.354			155^{20}, 144^{14}	0.9545^{20}		vs eth, EtOH, chl
7418	1-Methyl-4-isopropyl-2-nitrobenzene		$C_{10}H_{13}NO_2$	943-15-7	179.216			126^{10}	1.0744^{20}	1.5301^{20}	vs eth, EtOH
7419	1-Methyl-4-isopropyl-7-oxabicyclo[2.2.1]heptane		$C_{10}H_{18}O$	470-67-7	154.249		1	173.5	0.8997^{20}	1.4562^{20}	sl H_2O; msc EtOH, eth; s bz, lig
7420	1-Methyl-7-isopropylphenanthrene	Retene	$C_{18}H_{18}$	483-65-8	234.336		101	390	1.035^{25}		i H_2O; s EtOH, eth, bz, CS_2, HOAc
7421	4-Methyl-2-isopropylphenol		$C_{10}H_{14}O$	4427-56-9	150.217	nd (HOAc)	36.5	228.5	0.9910^{20}	1.5275^{20}	sl H_2O; s EtOH, bz, chl
7422	5-Methyl-2-isopropylphenyl acetate	Thymol, acetate	$C_{12}H_{16}O_2$	528-79-0	192.254			245	1.009^{9}		vs bz, eth, EtOH, chl
7423	1-Methylisoquinoline	Isoquinaldine	$C_{10}H_9N$	1721-93-3	143.185		10	248	1.0777^{20}	1.6095^{20}	sl H_2O; s eth, ace, bz
7424	3-Methylisoquinoline		$C_{10}H_9N$	1125-80-0	143.185	cry (eth)	68	249			sl H_2O, chl; s eth, ace
7425	Methyl isothiocyanate		C_2H_3NS	556-61-6	73.117		36	119	1.0691^{37}	1.5258	sl H_2O; msc EtOH; vs eth
7426	5-Methyl-3-isoxazolamine		$C_4H_6N_2O$	1072-67-9	98.103		62				
7427	4-Methylisoxazole		C_4H_5NO	6454-84-8	83.089	liq		127			
7428	5-Methylisoxazole		C_4H_5NO	5765-44-6	83.089			122	1.023^{20}	1.4386^{20}	s DMSO
7429	Methyl lactate, (±)	Methyl 2-hydroxypropanoate, (±)	$C_4H_8O_3$	2155-30-8	104.105	oil		144.8	1.0928^{20}	1.4141^{20}	vs H_2O, eth, EtOH
7430	Methyl linoleate		$C_{19}H_{34}O_2$	112-63-0	294.472		-35	215^{20}	0.8886^{10}	1.4638^{20}	vs eth, EtOH
7431	Methyl linolenate		$C_{19}H_{32}O_2$	301-00-8	292.456		-45.5	207^{14}, 182^{3}	0.895^{25}	1.4709^{20}	
7432	Methyl magnesium bromide	Bromomethylmagnesium	CH_3BrMg	75-16-1	119.244						s eth, thf; i hx, bz
7433	Methylmagnesium chloride	Chloromethylmagnesium	CH_3ClMg	676-58-4	74.793	stab in thf soln					i peth, bz
7434	Methylmalonic acid		$C_4H_6O_4$	516-05-2	118.089	nd (bz-AcOEt) pr (eth-bz)	135 dec		1.455^{20}		vs H_2O, EtOH, eth; sl bz, tfa; s AcOEt
7435	Methyl mercaptoacetate		$C_3H_6O_2S$	2365-48-2	106.144			42^{10}		1.4657^{20}	vs eth, EtOH
7436	Methyl 3-mercaptopropanoate		$C_4H_8O_2S$	2935-90-2	120.171			54^{14}	1.085^{25}	1.4640^{20}	
7437	Methylmercuric dicyanamide	1-Cyano-3-(methylmercurio) guanidine	$C_3H_6HgN_4$	502-39-6	298.70		157				
7438	Methyl methacrylate		$C_5H_8O_2$	80-62-6	100.117	liq	-47.55	100.5	0.9377^{25}	1.4142^{20}	sl H_2O; msc EtOH, eth, ace; s chl
7439	Methyl methanesulfonate		$C_2H_6O_3S$	66-27-3	110.132		20	202.5	1.2943^{20}	1.4138^{20}	
7440	Methyl methoxyacetate		$C_4H_8O_3$	6290-49-9	104.105			131	1.0511^{20}	1.3962^{20}	sl H_2O; vs EtOH, eth, ace



2-Methyl-5-isopropyl-2,5-cyclohexadiene-1,4-dione



cis-1-Methyl-4-isopropylcyclohexane



trans-1-Methyl-4-isopropylcyclohexane



1-Methyl-4-isopropylcyclohexanol



5-Methyl-2-isopropylcyclohexanol, [1*S*-(1α,2β,5α)]-



5-Methyl-2-isopropylcyclohexanol, [1*R*-(1α,2β,5α)]-



5-Methyl-2-isopropylcyclohexanol, [1*S*-(1α,2α,5β)]-



5-Methyl-2-isopropylcyclohexanol, [1*S*-(1α,2β,5β)]-



5-Methyl-2-isopropylcyclohexanol acetate, [1*R*-(1α,2α,5β)]



cis-5-Methyl-2-isopropylcyclohexanone



trans-5-Methyl-2-isopropylcyclohexanone, (2*S*)


1-Methyl-4-isopropylcyclohexene



3-Methyl-6-isopropyl-2-cyclohexen-1-ol



4-Methyl-1-isopropyl-3-cyclohexen-1-ol



5-Methyl-2-isopropylcyclohexyl ethoxyacetate, (1α,2β,5α)



1-Methyl-4-isopropyl-2-nitrobenzene



1-Methyl-4-isopropyl-7-oxabicyclo[2.2.1]heptane



1-Methyl-7-isopropylphenanthrene



4-Methyl-2-isopropylphenol


5-Methyl-2-isopropylphenyl acetate


1-Methylisoquinoline



3-Methylisoquinoline



Methyl isothiocyanate



5-Methyl-3-isoxazolamine


4-Methylisoxazole



5-Methylisoxazole



Methyl lactate, (±)



Methyl linoleate



Methyl linolenate



Methyl magnesium bromide



Methylmagnesium chloride



Methylmalonic acid



Methyl mercaptoacetate


Methyl 3-mercaptopropanoate



Methylmercuric dicyanamide



Methyl methacrylate



Methyl methanesulfonate



Methyl methoxyacetate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7441	Methyl 2-methoxybenzoate		$C_9H_{10}O_3$	606-45-1	166.173			246.5	1.1571^{19}	1.534^{19}	i H_2O; s EtOH
7442	Methyl 3-methoxybenzoate		$C_9H_{10}O_3$	5368-81-0	166.173			248	1.1310^{20}	1.5224^{20}	i H_2O; s EtOH
7443	Methyl 4-methoxybenzoate		$C_9H_{10}O_3$	121-98-2	166.173	lf (al or eth)	49	244			i H_2O; s EtOH, eth, chl
7444	Methyl 3-methoxy-2-(methylamino)benzoate	Damascenine	$C_{10}H_{13}NO_3$	483-64-7	195.215	pr (al)	28	271; 147^{10}			vs bz, eth, EtOH, lig
7445	Methyl 3-methoxypropanoate		$C_5H_{10}O_3$	3852-09-3	118.131			142.8	1.0139^{15}	1.4030^{20}	
7446	Methyl 2-methylacetoacetate		$C_6H_{10}O_3$	17094-21-2	130.141			177.4	1.0217^{25}	1.416^{24}	vs eth, EtOH
7447	Methyl 2-(methylamino)benzoate		$C_9H_{11}NO_2$	85-91-6	165.189	cry (peth)	19	255	1.120^{15}	1.5839^{15}	i H_2O; s EtOH, eth
7448	Methyl 2-methylbenzoate		$C_9H_{10}O_2$	89-71-4	150.174		<-50	215	1.068^{20}		i H_2O; msc EtOH, eth
7449	Methyl 3-methylbenzoate		$C_9H_{10}O_2$	99-36-5	150.174			221	1.061^{20}		i H_2O; s EtOH; sl ctc
7450	Methyl 4-methylbenzoate		$C_9H_{10}O_2$	99-75-2	150.174	cry (aq MeOH, peth)	33.2	220			i H_2O; vs EtOH, eth
7451	Methyl 2-methyl-2-butenoate, (*E*)		$C_6H_{10}O_2$	6622-76-0	114.142			139	0.9349^{12}	1.4370^{20}	
7452	Methyl 3-methyl-2-butenoate		$C_6H_{10}O_2$	924-50-5	114.142		114	136.5	0.9337^{20}	1.432^{20}	
7453	3-Methyl-4-methylenehexane		C_8H_{16}	3404-67-9	112.213			112.5	0.725^{25}	1.4142^{20}	
7454	2-Methyl-5-(1-methylethenyl) cyclohexanone, (2*R*-*trans*)		$C_{10}H_{16}O$	5524-05-0	152.233			221.5	0.928^{19}	1.4724	vs ace, eth
7455	5-Methyl-2-(1-methylethylidene) cyclohexanone		$C_{10}H_{16}O$	15932-80-6	152.233			93^{10}	0.9367^{20}	1.4869^{20}	
7456	3-Methyl-6-(1-methylethylidene)-2-cyclohexen-1-one	Piperitenone	$C_{10}H_{14}O$	491-09-8	150.217			120^{14}	0.9774^{20}	1.5294^{20}	vs EtOH, eth
7457	1-Methyl-4-(5-methyl-1-methylene-4-hexenyl) cyclohexene, (*S*)		$C_{15}H_{24}$	495-61-4	204.352			129^{10}	0.8673^{20}	1.4880^{20}	
7458	*N*-Methyl-*N*-(2-methylphenyl) acetamide		$C_{10}H_{13}NO$	573-26-2	163.216		55.5	260			s EtOH, chl
7459	4-Methyl-*N*-(4-methylphenyl) aniline		$C_{14}H_{15}N$	620-93-9	197.276	nd (peth)	79.8	330.5			vs eth, peth
7460	2-Methyl-3-(2-methylphenyl)-4(3*H*)-quinazolinone	Methaqualone	$C_{16}H_{14}N_2O$	72-44-6	250.294		120				vs eth, EtOH, chl
7461	Methyl 3-(methylthio)propanoate	2-Methoxycarbonylethyl methyl sulfide	$C_5H_{10}O_2S$	13532-18-8	134.197			75^{13}, 69^{11}	1.077^{25}	1.4650^{20}	
7462	1-Methyl-4-(1-methylvinyl) benzene		$C_{10}H_{12}$	1195-32-0	132.202	liq	-20	185.3	0.8936^{23}	1.5283^{23}	
7463	1-Methyl-4-(1-methylvinyl) cyclohexanol	β-Terpineol	$C_{10}H_{18}O$	138-87-4	154.249	nd	32.5	210; 90^{10}	0.917^{20}	1.4747^{20}	
7464	5-Methyl-2-(1-methylvinyl) cyclohexanol, [1*R*-(1α,2β,5α)]		$C_{10}H_{18}O$	89-79-2	154.249		78	93^{14}	0.911^{20}	1.4723^{20}	sl H_2O; s EtOH, eth
7465	5-Methyl-2-(1-methylvinyl) cyclohexanol acetate, [1*R*-(1α,2β,5α)]		$C_{12}H_{20}O_2$	57576-09-7	196.286		85	113^{8}	0.925^{25}	1.4566^{20}	
7466	*trans*-5-Methyl-2-(1-methylvinyl) cyclohexanone		$C_{10}H_{16}O$	29606-79-9	152.233			100^{18}	0.9198^{20}	1.4675^{20}	
7467	2-Methyl-5-(1-methylvinyl)-2-cyclohexen-1-ol		$C_{10}H_{16}O$	99-48-9	152.233			228	0.9484^{25}	1.4942^{25}	
7468	4-Methylmorpholine		$C_5H_{11}NO$	109-02-4	101.147	liq	-64.40	116	0.9051^{20}	1.4332^{20}	s H_2O, EtOH, eth
7469	α-Methyl-4-morpholineethanol		$C_7H_{15}NO_2$	2109-66-2	145.200			121^{18}, 93^{13}	1.0174^{20}	1.4638^{20}	vs H_2O, ace, bz, EtOH
7470	1-Methylnaphthalene		$C_{11}H_{10}$	90-12-0	142.197	liq	-30.43	244.7	1.0202^{20}	1.6170^{20}	i H_2O; vs EtOH, eth; s bz
7471	2-Methylnaphthalene		$C_{11}H_{10}$	91-57-6	142.197	mcl (al)	34.6	241.1	1.0058^{20}	1.6015^{40}	i H_2O; vs EtOH, eth; s bz, chl
7472	Methyl 1-naphthalenecarboxylate	Methyl 1-naphthoate	$C_{12}H_{10}O_2$	2459-24-7	186.206		59.5	168^{20}, 101$^{0.04}$	1.1290^{20}	1.6086^{20}	vs bz, EtOH
7473	Methyl 2-naphthalenecarboxylate	Methyl 2-naphthoate	$C_{12}H_{10}O_2$	2459-25-8	186.206	lf (MeOH)	77	290			vs bz, eth, EtOH, chl
7474	2-Methyl-1,4-naphthalenediol diacetate	Menadiol diacetate	$C_{15}H_{14}O_4$	573-20-6	258.270	pr (al)	113				vs EtOH
7475	2-Methyl-1,4-naphthalenedione	Menadione	$C_{11}H_8O_2$	58-27-5	172.181	ye nd (al, peth)	107				i H_2O; sl EtOH, HOAc; s eth, bz, chl
7476	Methyl-1-naphthylamine	*N*-Methyl-1-naphthalenamine	$C_{11}H_{11}N$	2216-68-4	157.212	oil	174	294.5		1.6722^{20}	vs eth, EtOH
7477	Methyl nitrate		CH_3NO_3	598-58-3	77.040	exp gas	-83.0	exp 64.6	1.2075^{20}	1.3748^{20}	sl H_2O; s EtOH, eth
7478	Methyl nitrite		CH_3NO_2	624-91-9	61.041	ye gas	-16	-12	0.991^{15}		s EtOH, eth
7479	Methyl nitroacetate		$C_3H_5NO_4$	2483-57-0	119.077			107^{28}	1.320^{0}		
7480	2-Methyl-3-nitroaniline		$C_7H_8N_2O_2$	603-83-8	152.151	ye orth nd (w), ye lf (al)	92	305	1.3780^{15}		sl H_2O; s EtOH, eth, bz, chl



Methyl 2-methoxybenzoate



Methyl 3-methoxybenzoate



Methyl 4-methoxybenzoate



Methyl 3-methoxy-2-(methylamino)benzoate



Methyl 3-methoxypropanoate



Methyl 2-methylacetoacetate



Methyl 2-(methylamino)benzoate



Methyl 2-methylbenzoate



Methyl 3-methylbenzoate



Methyl 4-methylbenzoate



Methyl 2-methyl-2-butenoate, (*E*)



Methyl 3-methyl-2-butenoate



3-Methyl-4-methylenehexane



2-Methyl-5-(1-methylethenyl)cyclohexanone, (2*R*-*trans*)



5-Methyl-2-(1-methylethylidene)cyclohexanone



3-Methyl-6-(1-methylethylidene)-2-cyclohexen-1-one



1-Methyl-4-(5-methyl-1-methylene-4-hexenyl)cyclohexene, (*S*)



N-Methyl-*N*-(2-methylphenyl)acetamide



4-Methyl-*N*-(4-methylphenyl)aniline



2-Methyl-3-(2-methylphenyl)-4(3*H*)-quinazolinone



Methyl 3-(methylthio)propanoate



1-Methyl-4-(1-methylvinyl)benzene



1-Methyl-4-(1-methylvinyl)cyclohexanol



5-Methyl-2-(1-methylvinyl)cyclohexanol, [1*R*-(1α,2β,5α)]



5-Methyl-2-(1-methylvinyl)cyclohexanol acetate, [1*R*-(1α,2β,5α)]



trans-5-Methyl-2-(1-methylvinyl)cyclohexanone



2-Methyl-5-(1-methylvinyl)-2-cyclohexen-1-ol



4-Methylmorpholine



α-Methyl-4-morpholineethanol



1-Methylnaphthalene



2-Methylnaphthalene


Methyl 1-naphthalenecarboxylate


Methyl 2-naphthalenecarboxylate



2-Methyl-1,4-naphthalenediol diacetate



2-Methyl-1,4-naphthalenedione


Methyl-1-naphthylamine



Methyl nitrate



Methyl nitrite



Methyl nitroacetate



2-Methyl-3-nitroaniline


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7481	2-Methyl-4-nitroaniline		$C_7H_8N_2O_2$	99-52-5	152.151		133.5		1.1586^{140}		sl H_2O, DMSO; s EtOH, bz, HOAc
7482	2-Methyl-5-nitroaniline		$C_7H_8N_2O_2$	99-55-8	152.151		105.5				sl H_2O; s EtOH, eth, ace, bz, chl
7483	2-Methyl-6-nitroaniline		$C_7H_8N_2O_2$	570-24-1	152.151		96		1.1900^{100}		sl H_2O; s EtOH, eth, bz, chl
7484	4-Methyl-2-nitroaniline		$C_7H_8N_2O_2$	89-62-3	152.151		116.3		1.16^{121}		sl H_2O; s EtOH, chl
7485	4-Methyl-3-nitroaniline		$C_7H_8N_2O_2$	119-32-4	152.151		79.8				sl H_2O, CS_2; s EtOH, eth, bz
7486	*N*-Methyl-2-nitroaniline		$C_7H_8N_2O_2$	612-28-2	152.151	red or oran nd (peth)	38	158^{18}			sl H_2O, lig; s EtOH, eth, ace, bz
7487	*N*-Methyl-4-nitroaniline		$C_7H_8N_2O_2$	100-15-2	152.151	br-ye pr (al) cry (eth)	152	dec	1.201^{155}		i H_2O; s EtOH, bz, chl; sl eth, lig
7488	2-Methyl-1-nitro-9,10-anthracenedione		$C_{15}H_9NO_4$	129-15-7	267.237	pa ye nd (HOAc)	273.0				i H_2O, EtOH; sl eth, bz, chl; s $PhNO_2$
7489	2-Methyl-5-nitrobenzenesulfonic acid		$C_7H_7NO_5S$	121-03-9	217.200		135.8				vs H_2O, EtOH, eth, chl
7490	Methyl 2-nitrobenzoate		$C_8H_7NO_4$	606-27-9	181.147	liq	-13	275	1.2855^{20}		i H_2O; s EtOH, eth, bz, chl; i lig
7491	Methyl 3-nitrobenzoate		$C_8H_7NO_4$	618-95-1	181.147		78	279^{60}			i H_2O; sl EtOH, eth, MeOH
7492	Methyl 4-nitrobenzoate		$C_8H_7NO_4$	619-50-1	181.147		96				i H_2O; s EtOH, eth, chl
7493	2-Methyl-4-nitro-1*H*-imidazole		$C_4H_5N_3O_2$	696-23-1	127.102		253				
7494	*N*-Methyl-*N*-nitromethanamine		$C_2H_6N_2O_2$	4164-28-7	90.081	nd(eth)	58	187	1.1090^{72}	1.4462^{72}	vs H_2O, ace, eth, EtOH
7495	2-Methyl-1-nitronaphthalene		$C_{11}H_9NO_2$	881-03-8	187.195	ye pr or nd (al)	81.5	188^{20}			i H_2O; s EtOH; vs ace
7496	*N*-Methyl-*N'*-nitro-*N*-nitrosoguanidine		$C_2H_5N_5O_3$	70-25-7	147.093						s DMSO
7497	3-Methyl-4-nitrophenol		$C_7H_7NO_3$	2581-34-2	153.136	nd or pr (w)	129				sl H_2O; s EtOH, eth, bz, chl
7498	4-Methyl-2-nitrophenol		$C_7H_7NO_3$	119-33-5	153.136	ye nd (al, w)	36.5	125^{22}	1.2399^{20}	1.5744^{40}	vs ace, bz, eth, EtOH
7499	1-Methyl-2-(4-nitrophenoxy) benzene	2-Methylphenyl 4-nitrophenyl ether	$C_{13}H_{11}NO_3$	2444-29-3	229.231	ye cry (peth)		220^{27}			vs bz, eth, EtOH
7500	2-Methyl-2-nitro-1,3-propanediol		$C_4H_9NO_4$	77-49-6	135.119	mcl	150.1	dec			vs H_2O, EtOH; sl DMSO
7501	2-Methyl-2-nitro-1-propanol		$C_4H_9NO_3$	76-39-1	119.119	nd or pl (MeOH)	89.5	94^{10}			sl H_2O; vs EtOH, eth; s chl
7502	3-Methyl-4-nitroquinoline-*N*-oxide		$C_{10}H_8N_2O_3$	14073-00-8	204.182	cry (MeOH)	179				
7503	*N*-Methyl-*N*-nitrosoaniline		$C_7H_8N_2O$	614-00-6	136.151	ye cry	14.7	dec 225; 121^{13}	1.1240^{20}	1.5769^{20}	i H_2O; s EtOH, eth
7504	*N*-Methyl-*N*-nitrosourea	*N*-Nitroso-*N*-methylurea	$C_2H_5N_3O_2$	684-93-5	103.080	col or ye pl (eth)	123 dec				sl H_2O, EtOH, eth
7505	Methyl nonadecanoate		$C_{20}H_{40}O_2$	1731-94-8	312.531		41.3	190^{4}			
7506	2-Methylnonane		$C_{10}H_{22}$	871-83-0	142.282	liq	-74.6	167.1	0.7281^{20}	1.4099^{20}	i H_2O; s eth, bz, chl
7507	3-Methylnonane		$C_{10}H_{22}$	5911-04-6	142.282	liq	-84.8	167.9	0.7354^{20}	1.4125^{20}	vs bz, eth, chl
7508	4-Methylnonane		$C_{10}H_{22}$	17301-94-9	142.282	liq	-99	165.7	0.7323^{20}	1.4123^{20}	vs bz, eth, chl
7509	5-Methylnonane		$C_{10}H_{22}$	15869-85-9	142.282	liq	-87.7	165.1	0.7326^{20}	1.4116^{20}	i H_2O; s eth, bz, chl
7510	Methyl nonanoate		$C_{10}H_{20}O_2$	1731-84-6	172.265			213.5	0.8799^{15}	1.4214^{20}	i H_2O; s EtOH, eth; sl ctc
7511	8-Methyl-1-nonanol		$C_{10}H_{22}O$	55505-26-5	158.281			108^{10}			
7512	2-Methyl-1-nonene		$C_{10}H_{20}$	2980-71-4	140.266	liq	-64.2	168.4	0.7412^{25}	1.4241^{20}	
7513	2-Methyl-2-norbornene	2-Methylbicyclo[2.2.1]hept-2-ene	C_8H_{12}	694-92-8	108.181	liq		122			
7514	Methyl *trans*-9-octadecenoate		$C_{19}H_{36}O_2$	1937-62-8	296.488	liq	13.5	218^{24}	0.8730^{20}	1.4513^{20}	vs eth, EtOH
7515	2-Methyloctane		C_9H_{20}	3221-61-2	128.255	liq	-80.3	143.2	0.7095^{25}	1.4031^{20}	i H_2O; s EtOH, eth; sl ctc; vs peth
7516	3-Methyloctane		C_9H_{20}	2216-33-3	128.255	liq	-107.6	144.2	0.717^{25}	1.4040^{25}	
7517	4-Methyloctane		C_9H_{20}	2216-34-4	128.255	liq	-113.3	142.4	0.716^{25}	1.4039^{25}	i H_2O
7518	Methyl octanoate	Methyl caprylate	$C_9H_{18}O_2$	111-11-5	158.238	liq	-40	192.9	0.8775^{20}	1.4170^{20}	i H_2O; vs EtOH, eth; sl ctc
7519	2-Methyloctanoic acid		$C_9H_{18}O_2$	3004-93-1	158.238			138^{14}, 88^{4}		1.4281^{25}	



2-Methyl-4-nitroaniline



2-Methyl-5-nitroaniline



2-Methyl-6-nitroaniline



4-Methyl-2-nitroaniline



4-Methyl-3-nitroaniline



N-Methyl-2-nitroaniline



N-Methyl-4-nitroaniline



2-Methyl-1-nitro-9,10-anthracenedione


2-Methyl-5-nitrobenzenesulfonic acid



Methyl 2-nitrobenzoate



Methyl 3-nitrobenzoate



Methyl 4-nitrobenzoate



2-Methyl-4-nitro-1*H*-imidazole



N-Methyl-*N*-nitromethanamine



2-Methyl-1-nitronaphthalene


N-Methyl-*N*′-nitro-*N*-nitrosoguanidine



3-Methyl-4-nitrophenol



4-Methyl-2-nitrophenol



1-Methyl-2-(4-nitrophenoxy)benzene



2-Methyl-2-nitro-1,3-propanediol



2-Methyl-2-nitro-1-propanol



3-Methyl-4-nitroquinoline-*N*-oxide



N-Methyl-*N*-nitrosoaniline



N-Methyl-*N*-nitrosourea



Methyl nonadecanoate



2-Methylnonane



3-Methylnonane



4-Methylnonane



5-Methylnonane



Methyl nonanoate



8-Methyl-1-nonanol



2-Methyl-1-nonene



2-Methyl-2-norbornene



Methyl *trans*-9-octadecenoate


2-Methyloctane



3-Methyloctane



4-Methyloctane



Methyl octanoate



2-Methyloctanoic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7520	2-Methyl-2-octanol		$C_9H_{20}O$	628-44-4	144.254			178	0.8210^{20}	1.4280^{20}	i H_2O; s EtOH, eth
7521	3-Methyl-3-octanol		$C_9H_{20}O$	5340-36-3	144.254			83^{18}, 36^{3}	0.8108^{25}	1.4257^{25}	
7522	5-Methyl-2-octanone		$C_9H_{18}O$	58654-67-4	142.238			101^{50}			
7523	2-Methyl-1-octene		C_9H_{18}	4588-18-5	126.239	liq	-77.8	144.8	0.7343^{20}	1.4184^{20}	
7524	7-Methyl-1-octene		C_9H_{18}	13151-06-9	126.239	liq		138.9			
7525	Methyloctylamine	*N*-Methyl-1-octanamine	$C_9H_{21}N$	2439-54-5	143.270			68^{8}			
7526	Methyl 2-octynoate		$C_9H_{14}O_2$	111-12-6	154.206			217; 107^{20}	0.926^{20}	1.4464^{20}	
7527	3-Methyl-1-octyn-3-ol		$C_9H_{16}O$	23580-51-0	140.222			174; 75^{10}	0.8547^{20}	1.443^{10}	
7528	Methyl oleate		$C_{19}H_{36}O_2$	112-62-9	296.488		-19.9	218.5^{20}	0.8739^{20}	1.4522^{20}	i H_2O; msc EtOH, eth; s chl
7529	Methyl Orange	Sodium *p*-dimethylaminoazobenzenesulfonate	$C_{14}H_{14}N_3NaO_3S$	547-58-0	327.334	oran, ye pl or sc (w)	dec				sl H_2O, EtOH, py; i eth
7530	2-Methyloxazole		C_4H_5NO	23012-10-4	83.089	liq		87.5			
7531	4-Methyloxazole		C_4H_5NO	693-93-6	83.089			88	1.015^{25}	1.4317^{20}	
7532	5-Methyloxazole		C_4H_5NO	66333-88-8	83.089	liq		88			
7533	2-Methyl-2-oxazoline		C_4H_7NO	1120-64-5	85.105			111	1.005^{25}	1.4340^{20}	
7534	2-Methyloxetane		C_4H_8O	2167-39-7	72.106	hyg		59	0.841^{25}	1.3885^{20}	
7535	4-Methyl-2-oxetanone	3-Hydroxybutyric acid lactone	$C_4H_6O_2$	3068-88-0	86.090			86^{50}, 57^{9}	1.0555^{20}		
7536	Methyloxirane	1,2-Propylene oxide	C_3H_6O	16033-71-9	58.079	liq	-111.9	35	0.859^{0}	1.3660^{20}	vs H_2O, EtOH, eth; s chl
7537	3-Methyl-2-oxobutanoic acid		$C_5H_8O_3$	759-05-7	116.116		31.5	170.5	0.9968^{20}	1.3850^{16}	s H_2O, EtOH, eth
7538	*N*-Methyl-*N*-(1-oxododecyl) glycine	*N*-Dodecanoylsarcosine	$C_{15}H_{29}NO_3$	97-78-9	271.396		44.5				s chl
7539	Methyl 4-oxopentanoate	Methyl levulinate	$C_6H_{10}O_3$	624-45-3	130.141			196	1.0511^{20}	1.4233^{20}	sl H_2O; s EtOH, ace, bz, ctc; msc eth
7540	4-Methyl-2-oxopentanoic acid		$C_6H_{10}O_3$	816-66-0	130.141	liq	10	84^{15}			
7541	Methyl 2-oxopropanoate	Methyl pyruvate	$C_4H_6O_3$	600-22-6	102.089			135.5	1.154^{0}	1.4046^{25}	sl H_2O; s ace; msc EtOH, eth
7542	Methyl palmitate	Methyl hexadecanoate	$C_{17}H_{34}O_2$	112-39-0	270.451		30	417; 148^{2}	0.8247^{75}		i H_2O; vs EtOH, ace, bz; s eth
7543	Methyl parathion		$C_8H_{10}NO_5PS$	298-00-0	263.208	cry	38		1.358^{20}	1.5367^{25}	i H_2O; s os
7544	Methyl pentachlorophenyl sulfide	*S*-Methyl pentachlorobenzenethiol	$C_7H_3Cl_5S$	1825-19-0	296.429	cry (EtOH)	95.5				
7545	Methyl pentadecanoate		$C_{16}H_{32}O_2$	7132-64-1	256.424	nd (dil al)	18.5	153.5	0.8618^{25}	1.4390^{25}	s EtOH, eth
7546	*cis*-2-Methyl-1,3-pentadiene		C_6H_{10}	1501-60-6	82.143	liq	-117.6	75.8	0.714^{25}	1.446^{20}	
7547	3-Methyl-1,3-pentadiene		C_6H_{10}	4549-74-0	82.143			77	0.730^{25}	1.452^{20}	
7548	4-Methyl-1,3-pentadiene	1,1-Dimethyl-1,3-butadiene	C_6H_{10}	926-56-7	82.143			76.5	0.7181^{20}	1.4532^{20}	
7549	Methyl pentafluoroethyl ether	1-Methoxyperfluoroethane	$C_3H_3F_5O$	22410-44-2	150.047	col gas		5.59			
7550	Methyl pentafluoropropanoate		$C_4H_3F_5O_2$	378-75-6	178.058			59.5	1.390^{25}	1.2869^{25}	
7551	2-Methylpentanal	2-Methylvaleraldehyde	$C_6H_{12}O$	123-15-9	100.158			117			s H_2O; s eth, ace; sl ctc
7552	2-Methylpentane	Isohexane	C_6H_{14}	107-83-5	86.175	liq	-153.6	60.26	0.650^{25}	1.3715^{20}	i H_2O; s EtOH, eth; msc ace, bz, chl
7553	3-Methylpentane		C_6H_{14}	96-14-0	86.175	liq	-162.90	63.27	0.6598^{25}	1.3765^{20}	i H_2O; s EtOH, ctc; msc eth, ace, bz, hp
7554	2-Methylpentanedinitrile	2-Methylglutaronitrile	$C_6H_8N_2$	4553-62-2	108.141	liq	-45	270; 134^{13}	0.950	1.4340^{20}	s H_2O
7555	2-Methyl-2,4-pentanediol	Hexylene glycol	$C_6H_{14}O_2$	107-41-5	118.174	liq	-50	197.1	0.923^{15}	1.4276^{20}	s H_2O, EtOH, eth; sl ctc
7556	4-Methylpentanenitrile	Isopentyl cyanide	$C_6H_{11}N$	542-54-1	97.158	liq	-51	156.5	0.8030^{20}	1.4059^{20}	i H_2O; s EtOH; msc eth; sl ctc
7557	2-Methyl-2-pentanethiol		$C_6H_{14}S$	1633-97-2	118.240	liq		125.0; 36^{30}			
7558	Methyl pentanoate	Methyl valerate	$C_6H_{12}O_2$	624-24-8	116.158			127.4	0.8947^{20}	1.4003^{20}	sl H_2O, ctc; msc EtOH, eth; s ace
7559	2-Methylpentanoic acid, (±)		$C_6H_{12}O_2$	22160-39-0	116.158			195.6	0.9230^{20}	1.413^{20}	s H_2O, EtOH, eth; sl ctc
7560	3-Methylpentanoic acid, (±)		$C_6H_{12}O_2$	22160-40-3	116.158	liq	-41.6	197.5	0.9262^{20}	1.4159^{20}	vs eth, EtOH
7561	4-Methylpentanoic acid		$C_6H_{12}O_2$	646-07-1	116.158	liq	-33	200.5	0.9225^{20}	1.4144^{20}	sl H_2O; s EtOH, eth, chl
7562	2-Methyl-1-pentanol		$C_6H_{14}O$	105-30-6	102.174			149	0.8263^{20}	1.4182^{20}	sl H_2O; s EtOH, eth, ace, ctc
7563	3-Methyl-1-pentanol, (±)		$C_6H_{14}O$	20281-83-8	102.174			153	0.8242^{20}	1.4112^{23}	i H_2O; s EtOH, eth
7564	4-Methyl-1-pentanol	Isohexyl alcohol	$C_6H_{14}O$	626-89-1	102.174			151.9	0.8131^{20}	1.4134^{25}	i H_2O; s EtOH, eth
7565	2-Methyl-2-pentanol		$C_6H_{14}O$	590-36-3	102.174	liq	-103	121.1	0.8350^{16}	1.4100^{20}	sl H_2O; s EtOH, eth



2-Methyl-2-octanol



3-Methyl-3-octanol



5-Methyl-2-octanone



2-Methyl-1-octene



7-Methyl-1-octene


Methyloctylamine


Methyl 2-octynoate


3-Methyl-1-octyn-3-ol


Methyl oleate


Methyl Orange


2-Methyloxazole


4-Methyloxazole



5-Methyloxazole



2-Methyl-2-oxazoline



2-Methyloxetane



4-Methyl-2-oxetanone



Methyloxirane



3-Methyl-2-oxobutanoic acid



N-Methyl-*N*-(1-oxododecyl)glycine



Methyl 4-oxopentanoate



4-Methyl-2-oxopentanoic acid


Methyl 2-oxopropanoate



Methyl palmitate



Methyl parathion



Methyl pentachlorophenyl sulfide



Methyl pentadecanoate



cis-2-Methyl-1,3-pentadiene



3-Methyl-1,3-pentadiene



4-Methyl-1,3-pentadiene



Methyl pentafluoroethyl ether



Methyl pentafluoropropanoate



2-Methylpentanal



2-Methylpentane



3-Methylpentane



2-Methylpentanedinitrile



2-Methyl-2,4-pentanediol



4-Methylpentanenitrile



2-Methyl-2-pentanethiol



Methyl pentanoate



2-Methylpentanoic acid, (±)



3-Methylpentanoic acid, (±)


4-Methylpentanoic acid



2-Methyl-1-pentanol



3-Methyl-1-pentanol, (±)



4-Methyl-1-pentanol



2-Methyl-2-pentanol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7566	3-Methyl-2-pentanol		$C_6H_{14}O$	565-60-6	102.174			134.3	0.8307^{20}	1.4182^{20}	sl H_2O; s EtOH, eth
7567	4-Methyl-2-pentanol		$C_6H_{14}O$	108-11-2	102.174	liq	-90	131.6	0.8075^{20}	1.4100^{20}	sl H_2O, ctc; s EtOH, eth
7568	2-Methyl-3-pentanol		$C_6H_{14}O$	565-67-3	102.174			126.5	0.8243^{20}	1.4175^{20}	sl H_2O; msc EtOH, eth
7569	3-Methyl-3-pentanol		$C_6H_{14}O$	77-74-7	102.174	liq	-23.6	122.4	0.8286^{20}	1.4186^{20}	sl H_2O, ctc; msc EtOH, eth
7570	2-Methyl-1-pentanol acetate		$C_8H_{16}O_2$	7789-99-3	144.212			163	0.870^{25}		vs eth, EtOH
7571	3-Methyl-2-pentanone, (±)	(±)-*sec*-Butyl methyl ketone	$C_6H_{12}O$	55156-16-6	100.158			117.5	0.8130^{20}	1.4002^{20}	sl H_2O; msc EtOH, eth; s chl
7572	4-Methyl-2-pentanone	Isobutyl methyl ketone	$C_6H_{12}O$	108-10-1	100.158	liq	-84	116.5	0.7965^{25}	1.3962^{20}	sl H_2O; msc EtOH, eth, ace, bz; s chl
7573	2-Methyl-3-pentanone	Ethyl isopropyl ketone	$C_6H_{12}O$	565-69-5	100.158			113.5	0.814^{18}	1.3975^{20}	sl H_2O; vs EtOH, bz; msc eth, ace; s chl
7574	4-Methylpentanoyl chloride		$C_6H_{11}ClO$	38136-29-7	134.603			143	0.9725^{20}		
7575	2-Methyl-2-pentenal		$C_6H_{10}O$	623-36-9	98.142			136.5	0.8581^{20}	1.4488^{20}	i H_2O; s EtOH, eth, bz, MeOH
7576	2-Methyl-1-pentene		C_6H_{12}	763-29-1	84.159	liq	-135.7	62.1	0.6799^{20}	1.3920^{20}	i H_2O; s EtOH, bz, chl; sl ctc
7577	3-Methyl-1-pentene		C_6H_{12}	760-20-3	84.159	liq	-153	54.2	0.6675^{20}	1.3841^{20}	i H_2O; s EtOH, bz, chl, peth
7578	4-Methyl-1-pentene		C_6H_{12}	691-37-2	84.159	liq	-153.6	53.9	0.6642^{20}	1.3828^{20}	i H_2O; s EtOH, bz, chl, peth
7579	2-Methyl-2-pentene		C_6H_{12}	625-27-4	84.159	liq	-135	67.3	0.6863^{20}	1.4004^{20}	i H_2O; s EtOH, bz, ctc, chl
7580	3-Methyl-*cis*-2-pentene		C_6H_{12}	922-62-3	84.159	liq	-134.8	67.7	0.6886^{25}	1.4016^{20}	i H_2O; s EtOH, bz, chl, peth
7581	3-Methyl-*trans*-2-pentene		C_6H_{12}	616-12-6	84.159	liq	-138.5	70.4	0.6930^{25}	1.4045^{20}	i H_2O; s EtOH, bz, ctc, chl, peth
7582	4-Methyl-*cis*-2-pentene		C_6H_{12}	691-38-3	84.159	liq	-134.8	56.3	0.6690^{20}	1.3800^{20}	i H_2O; s EtOH, bz, chl, peth
7583	4-Methyl-*trans*-2-pentene		C_6H_{12}	674-76-0	84.159	liq	-140.8	58.6	0.6686^{20}	1.3889^{20}	i H_2O; s EtOH, bz, chl; sl ctc
7584	*trans*-2-Methyl-2-pentenoic acid		$C_6H_{10}O_2$	16957-70-3	114.142	pr	24.4	214; 112^{12}	0.9751^{20}	1.4513^{20}	sl H_2O; s eth, chl, CS_2
7585	4-Methyl-2-pentenoic acid	4,4-Dimethyl-2-butenoic acid	$C_6H_{10}O_2$	10321-71-8	114.142		35	217	0.9529^{21}	1.4489^{21}	vs ace, eth, EtOH
7586	2-Methyl-3-pentenoic acid		$C_6H_{10}O_2$	37674-63-8	114.142			199	0.966^{15}	1.4402^{25}	
7587	4-Methyl-3-penten-2-ol		$C_6H_{12}O$	4325-82-0	100.158			134	0.840^{15}	1.9377^{15}	
7588	3-Methyl-2-penten-4-one		$C_6H_{10}O$	565-62-8	98.142			138		1.4508^{20}	
7589	4-Methyl-4-penten-2-one		$C_6H_{10}O$	3744-02-3	98.142	liq	-72.6	124.2	0.8411^{20}		
7590	*cis*-3-Methyl-2-(2-pentenyl)-2-cyclopenten-1-one	Jasmone	$C_{11}H_{16}O$	488-10-8	164.244	ye oil		$258; 134^{12}$	0.9437^{22}	1.4979^{22}	sl H_2O; s EtOH, eth, ctc, lig
7591	3-(4-Methyl-3-pentenyl)furan		$C_{10}H_{14}O$	539-52-6	150.217			185.5	0.9017^{20}	1.4705^{21}	
7592	3-Methyl-3-penten-1-yne		C_6H_8	1574-33-0	80.128			66.5	0.739^{20}	1.4332^{20}	s eth, bz
7593	3-Methyl-2-pentyl-2-cyclopenten-1-one		$C_{11}H_{18}O$	1128-08-1	166.260			$143^{22}, 116^{12}$	0.9165^{18}	1.4767^{20}	
7594	Methyl pentyl ether		$C_6H_{14}O$	628-80-8	102.174			99	0.759^{22}	1.3862^{22}	vs ace, eth, EtOH
7595	5-Methyl-2-pentylphenol	6-Pentyl-*m*-cresol	$C_{12}H_{18}O$	1300-94-3	178.270		24	138^{15}			vs ace, eth, EtOH
7596	Methyl pentyl sulfide		$C_6H_{14}S$	1741-83-9	118.240	liq	-94	145.1	0.8431^{20}	1.4506^{20}	s EtOH, eth, ace, bz, chl
7597	Methyl *tert*-pentyl sulfide	2-Methyl-2-(methylthio)butane	$C_6H_{14}S$	13286-92-5	118.240	liq		150	0.84	1.4570^{20}	
7598	4-Methyl-1-pentyne		C_6H_{10}	7154-75-8	82.143	liq	-104.6	61.2	0.7000^{25}	1.3936^{20}	i H_2O; s bz, chl
7599	4-Methyl-2-pentyne		C_6H_{10}	21020-27-9	82.143	liq	-110.3	73.1	0.7112^{25}	1.4057^{20}	vs bz, chl
7600	3-Methyl-1-pentyn-3-ol	Meparfynol	$C_6H_{10}O$	77-75-8	98.142		30.5	120.5	0.8688^{20}	1.4310^{20}	
7601	Methyl perfluorooctanoate		$C_9H_3F_{15}O_2$	376-27-2	428.095			158	1.684^{20}	1.304^{27}	
7602	1-Methylphenanthrene		$C_{15}H_{12}$	832-69-9	192.256	lf, pl (dil al)	123	354			i H_2O; s EtOH
7603	3-Methylphenanthrene		$C_{15}H_{12}$	832-71-3	192.256	pr or nd (al)	65	$350; 145^{6}$			i H_2O; s EtOH, ace; sl chl
7604	4-Methylphenanthrene		$C_{15}H_{12}$	832-64-4	192.256	pl (90% al)	53.5	177^{10}			i H_2O; s EtOH, ctc
7605	Methylphenidate		$C_{14}H_{19}NO_2$	113-45-1	233.307			$136^{0.6}$			i H_2O, peth; s chl, EtOH, eth, AcOEt
7606	10-Methyl-10*H*-phenothiazine		$C_{13}H_{11}NS$	1207-72-3	213.298		101				
7607	10-Methyl-10*H*-phenothiazine-2-acetic acid	Metiazinic acid	$C_{15}H_{13}NO_2S$	13993-65-2	271.335		144				s chl



3-Methyl-2-pentanol



4-Methyl-2-pentanol



2-Methyl-3-pentanol



3-Methyl-3-pentanol



2-Methyl-1-pentanol acetate



3-Methyl-2-pentanone, (±)



4-Methyl-2-pentanone



2-Methyl-3-pentanone



4-Methylpentanoyl chloride


2-Methyl-2-pentenal



2-Methyl-1-pentene


3-Methyl-1-pentene



4-Methyl-1-pentene



2-Methyl-2-pentene



3-Methyl-*cis*-2-pentene



3-Methyl-*trans*-2-pentene



4-Methyl-*cis*-2-pentene



4-Methyl-*trans*-2-pentene



trans-2-Methyl-2-pentenoic acid



4-Methyl-2-pentenoic acid



2-Methyl-3-pentenoic acid



4-Methyl-3-penten-2-ol



3-Methyl-2-penten-4-one



4-Methyl-4-penten-2-one



cis-3-Methyl-2-(2-pentenyl)-2-cyclopenten-1-one



3-(4-Methyl-3-pentenyl)furan



3-Methyl-3-penten-1-yne



3-Methyl-2-pentyl-2-cyclopenten-1-one



Methyl pentyl ether



5-Methyl-2-pentylphenol



Methyl pentyl sulfide



Methyl *tert*-pentyl sulfide



4-Methyl-1-pentyne



4-Methyl-2-pentyne



3-Methyl-1-pentyn-3-ol



Methyl perfluorooctanoate



1-Methylphenanthrene


3-Methylphenanthrene



4-Methylphenanthrene



Methylphenidate



10-Methyl-10*H*-phenothiazine



10-Methyl-10*H*-phenothiazine-2-acetic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7608	Methyl phenoxyacetate		$C_9H_{10}O_3$	2065-23-8	166.173			245	1.1493^{20}	1.5155^{20}	vs eth, EtOH
7609	1-Methyl-3-phenoxybenzene		$C_{13}H_{12}O$	3586-14-9	184.233			272	1.051^{25}	1.5727^{20}	
7610	[(2-Methylphenoxy)methyl]oxirane		$C_{10}H_{12}O_2$	2210-79-9	164.201			123^{2}	1.0884^{20}		
7611	3-(2-Methylphenoxy)-1,2-propanediol	Mephenesin	$C_{10}H_{14}O_3$	59-47-2	182.216		70 dec				sl H_2O, eth; s EtOH
7612	*N*-(2-Methylphenyl)acetamide		$C_9H_{11}NO$	120-66-1	149.189	nd (al)	110	296	1.168^{15}		sl H_2O, bz; s EtOH, eth, ace, HOAc
7613	*N*-(3-Methylphenyl)acetamide		$C_9H_{11}NO$	537-92-8	149.189	nd (w)	65.5	303	1.141^{15}		sl H_2O; vs EtOH, eth; s chl
7614	*N*-Methyl-*N*-phenylacetamide	*N*-Methylacetanilide	$C_9H_{11}NO$	579-10-2	149.189	nd (eth), pr (al)	103	256	1.0036^{105}	1.576	s H_2O, EtOH, eth, chl, lig
7615	2-Methylphenyl acetate	*o*-Cresyl acetate	$C_9H_{10}O_2$	533-18-6	150.174			208	1.0533^{15}	1.5002^{20}	vs eth, EtOH
7616	3-Methylphenyl acetate	*m*-Cresyl acetate	$C_9H_{10}O_2$	122-46-3	150.174		12	212	1.043^{20}	1.4978^{20}	vs bz, eth, EtOH
7617	4-Methylphenyl acetate	*p*-Cresyl acetate	$C_9H_{10}O_2$	140-39-6	150.174			212.5	1.0512^{17}	1.5163^{22}	sl H_2O, ctc; s EtOH, eth, chl
7618	Methyl 2-phenylacetate		$C_9H_{10}O_2$	101-41-7	150.174			216.5	1.0622^{16}	1.5075^{20}	i H_2O; msc EtOH, eth; s ace, ctc
7619	2-(Methylphenylamino)ethanol		$C_9H_{13}NO$	93-90-3	151.205			218^{110}, 150^{14}	1.0143^{0}		s H_2O; vs EtOH, eth, ace, bz
7620	2-[(2-Methylphenyl)amino]ethanol		$C_9H_{13}NO$	136-80-1	151.205			285.5	1.0794^{20}	1.5675^{20}	vs eth, EtOH
7621	3-Methyl-*N*-phenylaniline		$C_{13}H_{13}N$	1205-64-7	183.249		30	316; 183^{17}		1.6350^{20}	vs bz, eth, EtOH
7622	*N*-(4-Methylphenyl)benzamide		$C_{14}H_{13}NO$	582-78-5	211.259	orth nd (al)	158		1.202^{15}		vs eth, EtOH
7623	*N*-Methyl-*N*-phenylbenzenemethanamine		$C_{14}H_{15}N$	614-30-2	197.276						s ctc
7624	4-Methyl-α-phenylbenzenemethanol		$C_{14}H_{14}O$	1517-63-1	198.260		52				
7625	α-Methyl-α-phenylbenzenemethanol		$C_{14}H_{14}O$	599-67-7	198.260			285; 190^{12}	1.1059^{15}		
7626	4-Methyl-*N*-phenylbenzenesulfonamide		$C_{13}H_{13}NO_2S$	68-34-8	247.313	(α) tcl, (β) mcl pr (al, bz)	103.5				i H_2O; vs EtOH; s bz, HOAc
7627	4-Methylphenyl benzoate		$C_{14}H_{12}O_2$	614-34-6	212.244	pl (eth-al)	71.5	316			vs eth, EtOH
7628	1-Methyl-*N*-phenyl-*N*-benzyl-4-piperidinamine	Bamipine	$C_{19}H_{24}N_2$	4945-47-5	280.407	cry (MeOH)	115				
7629	Methyl 2-phenylbutanoate		$C_{11}H_{14}O_2$	2294-71-5	178.228	nd (dil al)	77.5	228			vs eth, EtOH
7630	3-Methyl-1-phenyl-1-butanone		$C_{11}H_{14}O$	582-62-7	162.228			236.5	0.9701^{16}	1.5139^{15}	i H_2O; msc EtOH, eth; vs ace
7631	3-Methyl-4-phenyl-3-butenamide	β-Benzalbutyramide	$C_{11}H_{13}NO$	7236-47-7	175.227		133				
7632	Methylphenylcarbamic chloride		C_8H_8ClNO	4285-42-1	169.609	pl (al)	88.5	280			vs eth, EtOH
7633	1-(2-Methylphenyl)ethanone		$C_9H_{10}O$	577-16-2	134.174			214	1.026^{20}	1.5276^{20}	
7634	1-(3-Methylphenyl)ethanone		$C_9H_{10}O$	585-74-0	134.174			220	1.0165^{0}	1.533^{15}	s EtOH, eth, ace; sl ctc
7635	4-(1-Methyl-1-phenylethyl)phenol		$C_{15}H_{16}O$	599-64-4	212.287	pr (peth)	74.5	335			
7636	*N*-Methyl-*N*-phenylformamide		C_8H_9NO	93-61-8	135.163		14.5	243	1.0948^{20}	1.5589^{20}	sl H_2O, ctc; s EtOH, ace
7637	*N*-(2-Methylphenyl)formamide		C_8H_9NO	94-69-9	135.163	lf (al)	62	288	1.086^{55}		s H_2O; vs EtOH
7638	5-Methyl-1-phenyl-1-hexen-3-one		$C_{13}H_{16}O$	2892-18-4	188.265	cry	43	154^{25}	0.9509^{46}	1.5523^{25}	sl H_2O; s EtOH, bz, chl
7639	1-Methyl-1-phenylhydrazine		$C_7H_{10}N_2$	618-40-6	122.167			228; 131^{35}	1.0404^{20}	1.5691^{20}	sl H_2O; msc EtOH, eth, bz, chl
7640	3-Methyl-5-phenyl-2,4-imidazolidinedione	3-Methyl-5-phenylhydantoin	$C_{10}H_{10}N_2O_2$	6846-11-3	190.198		164.5				s chl
7641	1-Methyl-6-phenylimidazo[4,5-b]pyridin-2-amine	PhIP	$C_{13}H_{12}N_4$	105650-23-5	224.261	solid	327				
7642	2-[Methyl(phenylmethyl)amino]ethanol		$C_{10}H_{15}NO$	101-98-4	165.232			134^{14}			
7643	4-Methyl-*N*-(phenylmethylene)aniline		$C_{14}H_{13}N$	2272-45-9	195.260	ye cry	35	318; 178^{11}			vs ace
7644	3-Methyl-2-phenylmorpholine	Phenmetrazine	$C_{11}H_{15}NO$	134-49-6	177.243			139^{12}, 104^{1}			
7645	2-Methyl-2-phenyloxirane		$C_9H_{10}O$	2085-88-3	134.174			84^{17}	1.0228^{20}	1.5232^{20}	
7646	*N*-(2-Methylphenyl)-3-oxobutanamide		$C_{11}H_{13}NO_2$	93-68-5	191.227	pr (AcOEt)	107.5				vs bz, EtOH
7647	*N*-(4-Methylphenyl)-3-oxobutanamide		$C_{11}H_{13}NO_2$	2415-85-2	191.227	pr (AcOEt)	95				sl H_2O, lig; s EtOH, bz
7648	(2-Methylphenyl) phenylmethanone		$C_{14}H_{12}O$	131-58-8	196.244		<-18	308; 128^{12}	1.1098^{20}		i H_2O; vs EtOH
7649	(3-Methylphenyl) phenylmethanone		$C_{14}H_{12}O$	643-65-2	196.244	oil	2	317; 170^{9}	1.095^{20}		i H_2O; s EtOH, eth, bz, chl, HOAc



Methyl phenoxyacetate



1-Methyl-3-phenoxybenzene



[(2-Methylphenoxy)methyl]oxirane



3-(2-Methylphenoxy)-1,2-propanediol



N-(2-Methylphenyl)acetamide



N-(3-Methylphenyl)acetamide



N-Methyl-*N*-phenylacetamide



2-Methylphenyl acetate



3-Methylphenyl acetate



4-Methylphenyl acetate



Methyl 2-phenylacetate



2-(Methylphenylamino)ethanol



2-[(2-Methylphenyl)amino]ethanol



3-Methyl-*N*-phenylaniline



N-(4-Methylphenyl)benzamide



N-Methyl-*N*-phenylbenzenemethanamine



4-Methyl-α-phenylbenzenemethanol



α-Methyl-α-phenylbenzenemethanol



4-Methyl-*N*-phenylbenzenesulfonamide



4-Methylphenyl benzoate



1-Methyl-*N*-phenyl-*N*-benzyl-4-piperidinamine



Methyl 2-phenylbutanoate



3-Methyl-1-phenyl-1-butanone



3-Methyl-4-phenyl-3-butenamide



Methylphenylcarbamic chloride



1-(2-Methylphenyl)ethanone



1-(3-Methylphenyl)ethanone



4-(1-Methyl-1-phenylethyl)phenol



N-Methyl-*N*-phenylformamide



N-(2-Methylphenyl)formamide



5-Methyl-1-phenyl-1-hexen-3-one



1-Methyl-1-phenylhydrazine



3-Methyl-5-phenyl-2,4-imidazolidinedione



1-Methyl-6-phenylimidazo[4,5-b]pyridin-2-amine



2-[Methyl(phenylmethyl)amino]ethanol



4-Methyl-*N*-(phenylmethylene)aniline



3-Methyl-2-phenylmorpholine


2-Methyl-2-phenyloxirane



N-(2-Methylphenyl)-3-oxo-butanamide



N-(4-Methylphenyl)-3-oxobutanamide



(2-Methylphenyl)phenylmethanone



(3-Methylphenyl)phenylmethanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7650	(4-Methylphenyl) phenylmethanone		$C_{14}H_{12}O$	134-84-9	196.244	mcl pr	59.5	228^{70}	0.9926^{0}		i H_2O; sl EtOH, lig; s eth, bz, chl
7651	Methyl 3-phenylpropanoate	Methyl dihydrocinnamate	$C_{10}H_{12}O_2$	103-25-3	164.201			238.5; 91^{4}	1.0455^{25}		i H_2O; s EtOH, eth, bz, AcOEt
7652	1-(4-Methylphenyl)-1-propanone		$C_{10}H_{12}O$	5337-93-9	148.201		7.2	236	0.9926^{20}	1.5278^{20}	i H_2O; s EtOH, eth, ace, bz, CS_2
7653	2-Methyl-1-phenyl-1-propanone		$C_{10}H_{12}O$	611-70-1	148.201	liq	-0.7	220	0.9863^{11}	1.5172^{20}	vs eth, EtOH
7654	2-Methyl-3-phenyl-2-propenal		$C_{10}H_{10}O$	101-39-3	146.185			248; 150^{100}	1.0407^{17}	1.6057^{17}	
7655	Methyl 3-phenyl-2-propynoate		$C_{10}H_8O_2$	4891-38-7	160.170		26	158^{48}, 132^{16}	1.0830^{25}	1.5618^{25}	
7656	3-Methyl-1-phenyl-1*H*-pyrazol-5-amine		$C_{10}H_{11}N_3$	1131-18-6	173.214		116	333			s H_2O, EtOH, chl; sl bz
7657	2-Methyl-5-phenylpyridine		$C_{12}H_{11}N$	3256-88-0	169.222			189^{50}	1.0590^{25}	1.6055^{25}	
7658	5-Methyl-5-phenyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	Phenylmethylbarbituric acid	$C_{11}H_{10}N_2O_3$	76-94-8	218.208	cry	220				i H_2O; s EtOH, eth, alk
7659	1-Methyl-3-phenyl-2,5-pyrrolidinedione	Phensuximide	$C_{11}H_{11}NO_2$	86-34-0	189.211	cry (hot al)	72				vs EtOH, MeOH
7660	Methylphenylsilane		$C_7H_{10}Si$	766-08-5	122.240			140	0.8895^{20}	1.5058^{20}	
7661	Methyl phenyl sulfone		$C_7H_8O_2S$	3112-85-4	156.203		88				i H_2O; s EtOH, bz, chl; sl ctc
7662	1-Methyl-4-(phenylthio)benzene		$C_{13}H_{12}S$	3699-01-2	200.299		15.7	317	1.0986^{25}	1.6225^{25}	i H_2O; s ace, bz
7663	(2-Methylphenyl)thiourea	*o*-Tolylthiourea	$C_8H_{10}N_2S$	614-78-8	166.243	nd (dil al, w)	162				vs H_2O, EtOH; sl eth
7664	*N*-Methyl-*N*′-phenylthiourea		$C_8H_{10}N_2S$	2724-69-8	166.243	ta, pl	112.5				vs EtOH
7665	Methyl phosphate	Methyl dihydrogen phosphate	CH_5O_4P	812-00-0	112.022	oil					
7666	Methylphosphine		CH_5P	593-54-4	48.025	col gas		-16			vs eth
7667	Methylphosphonic acid		CH_5O_3P	993-13-5	96.023	hyg pl	108.5	dec			vs H_2O, EtOH, eth; i bz, peth
7668	Methylphosphonic difluoride		CH_3F_2OP	676-99-3	100.005	liq		98; 22^{27}	1.3314^{20}		
7669	Methylphosphonofluoridic acid, isopropyl ester	Sarin	$C_4H_{10}FO_2P$	107-44-8	140.093	liq	-57	147	1.10^{20}		dec H_2O
7670	Methyl phosphorodichloridite	Methyl dichlorophosphite	CH_3Cl_2OP	3279-26-3	132.914	hyg liq	-91	93	1.406	1.4740^{20}	
7671	1-Methylpiperazine		$C_5H_{12}N_2$	109-01-3	100.162			138		1.4378^{20}	vs H_2O, eth, EtOH
7672	2-Methylpiperazine		$C_5H_{12}N_2$	109-07-9	100.162	hyg lf (al)	62	153			vs H_2O; s EtOH, eth, bz, chl
7673	1-Methylpiperidine		$C_6H_{13}N$	626-67-5	99.174	liq	-102.7	107	0.8159^{20}	1.4355^{20}	vs H_2O; msc EtOH, eth; s ctc
7674	2-Methylpiperidine, (±)		$C_6H_{13}N$	3000-79-1	99.174	liq	-2.5	118	0.8436^{24}	1.4459^{20}	vs H_2O; s EtOH, eth; sl chl; i dil KOH
7675	3-Methylpiperidine, (±)		$C_6H_{13}N$	53152-98-0	99.174	liq	-24	125.5	0.8446^{26}	1.4470^{20}	vs H_2O; sl chl
7676	4-Methylpiperidine		$C_6H_{13}N$	626-58-4	99.174			130	0.8674^{25}	1.4458^{20}	vs H_2O; sl chl
7677	1-Methyl-3-piperidinol		$C_6H_{13}NO$	3554-74-3	115.173			93^{26}, 77^{11}	0.9635^{16}	1.4735^{20}	
7678	1-Methyl-4-piperidinol		$C_6H_{13}NO$	106-52-5	115.173		29	200		1.4775^{20}	
7679	1-Methyl-2-piperidinone		$C_6H_{11}NO$	931-20-4	113.157			221; 105^{12}	1.0263^{25}	1.4820^{20}	
7680	1-Methyl-4-piperidinone		$C_6H_{11}NO$	1445-73-4	113.157			85^{45}, 57^{11}	0.971^{25}	1.4580^{25}	
7681	Methylprednisolone		$C_{22}H_{30}O_5$	83-43-2	374.470	cry	232				
7682	2-Methylpropanamide		C_4H_9NO	563-83-7	87.120		129.0	217	1.013^{20}		s chl
7683	*N*-Methylpropanamide		C_4H_9NO	1187-58-2	87.120	liq	-30.9	148	0.9305^{25}	1.4345^{25}	
7684	2-Methyl-1,2-propanediamine		$C_4H_{12}N_2$	811-93-8	88.151			123	0.841^{25}	1.4410^{20}	s ctc
7685	2-Methyl-1,2-propanediol		$C_4H_{10}O_2$	558-43-0	90.121			176	1.0024^{20}	1.4350^{20}	vs H_2O, eth, EtOH
7686	2-Methyl-1,3-propanediol		$C_4H_{10}O_2$	2163-42-0	90.121	liq	-91	211.6; 124^{20}	1.015^{20}	1.4450^{20}	
7687	2-Methylpropanenitrile	Isobutyronitrile	C_4H_7N	78-82-0	69.106	liq	-71.5	103.9	0.7704^{20}	1.3720^{20}	sl H_2O; vs EtOH, eth, ace, chl
7688	2-Methyl-1-propanethiol	Isobutyl mercaptan	$C_4H_{10}S$	513-44-0	90.187		<-70	88.5	0.8357^{20}	1.4387^{20}	sl H_2O; vs EtOH, eth, ace; s ctc
7689	2-Methyl-2-propanethiol	*tert*-Butyl mercaptan	$C_4H_{10}S$	75-66-1	90.187	liq	-0.5	64.2	0.7943^{25}	1.4232^{20}	i H_2O; s ctc, hp
7690	Methyl propanoate	Methyl propionate	$C_4H_8O_2$	554-12-1	88.106	liq	-87.5	79.8	0.9150^{20}	1.3775^{20}	sl H_2O; msc EtOH, eth; s ace, ctc
7691	2-Methylpropanoic acid	Isobutyric acid	$C_4H_8O_2$	79-31-2	88.106	liq	-46	154.45	0.9681^{20}	1.3930^{20}	vs H_2O; msc EtOH, eth; sl ctc
7692	2-Methylpropanoic anhydride	Isobutryic anhydride	$C_8H_{14}O_3$	97-72-3	158.195	liq	-53.5	183; 89^{32}	0.9535^{20}	1.4061^{19}	msc eth; s chl
7693	2-Methyl-1-propanol	Isobutyl alcohol	$C_4H_{10}O$	78-83-1	74.121	liq	-101.9	107.89	0.8018^{20}	1.3955^{20}	s H_2O, EtOH, eth, ace, ctc
7694	2-Methyl-2-propanol	*tert*-Butyl alcohol	$C_4H_{10}O$	75-65-0	74.121		25.69	82.4	0.7887^{20}	1.3878^{20}	msc H_2O, EtOH, eth; s chl



(4-Methylphenyl)phenylmethanone



Methyl 3-phenylpropanoate



1-(4-Methylphenyl)-1-propanone



2-Methyl-1-phenyl-1-propanone



2-Methyl-3-phenyl-2-propenal



Methyl 3-phenyl-2-propynoate



3-Methyl-1-phenyl-1*H*-pyrazol-5-amine



2-Methyl-5-phenylpyridine



5-Methyl-5-phenyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione



1-Methyl-3-phenyl-2,5-pyrrolidinedione


Methylphenylsilane


Methyl phenyl sulfone


1-Methyl-4-(phenylthio)benzene


(2-Methylphenyl)thiourea



N-Methyl-*N*′-phenylthiourea


Methyl phosphate



Methylphosphine



Methylphosphonic acid


Methylphosphonic difluoride


Methylphosphonofluoridic acid, isopropyl ester


Methyl phosphorodichloridite



1-Methylpiperazine



2-Methylpiperazine



1-Methylpiperidine


2-Methylpiperidine, (±)



3-Methylpiperidine, (±)



4-Methylpiperidine



1-Methyl-3-piperidinol



1-Methyl-4-piperidinol



1-Methyl-2-piperidinone



1-Methyl-4-piperidinone



Methylprednisolone


2-Methylpropanamide


N-Methylpropanamide



2-Methyl-1,2-propanediamine



2-Methyl-1,2-propanediol



2-Methyl-1,3-propanediol



2-Methylpropanenitrile



2-Methyl-1-propanethiol


2-Methyl-2-propanethiol


Methyl propanoate


2-Methylpropanoic acid


2-Methylpropanoic anhydride



2-Methyl-1-propanol



2-Methyl-2-propanol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7695	2-Methylpropanoyl chloride	Isobutyric acid chloride	C_4H_7ClO	79-30-1	106.551	liq	-90	92		1.4079^{20}	s eth
7696	2-Methylpropenal	Methacrolein	C_4H_6O	78-85-3	70.090			68.4	0.840^{25}	1.4144^{20}	msc H_2O, EtOH, eth
7697	2-Methyl-2-propenamide		C_4H_7NO	79-39-0	85.105	cry (bz)	110.5				sl eth, chl; s EtOH, CH_2Cl_2
7698	*N*-Methyl-2-propen-1-amine		C_4H_9N	627-37-2	71.121			64		1.4065^{20}	vs H_2O, ace, eth, EtOH
7699	2-Methyl-2-propene-1,1-diol diacetate	Methacrolein diacetate	$C_8H_{12}O_4$	10476-95-6	172.179			191		1.4241^{20}	
7700	2-Methyl-1-propene, tetramer		$C_{16}H_{32}$	15220-85-6	224.425	liq	-98	244; 109^{15}	0.7944^{20}	1.4482^{20}	
7701	2-Methyl-2-propenoic anhydride	Methacrylic acid anhydride	$C_8H_{10}O_3$	760-93-0	154.163			89^{5}		1.4540^{20}	msc EtOH, eth
7702	2-Methyl-2-propenol	Methallyl alcohol	C_4H_8O	513-42-8	72.106			114.5	0.8515^{20}	1.4255^{20}	vs H_2O; msc EtOH, eth
7703	2-Methyl-2-propenoyl chloride	Methacrylic acid chloride	C_4H_5ClO	920-46-7	104.535	liq	-60	96	1.0871^{20}	1.4435^{20}	s eth, ace, chl
7704	*cis*-(1-Methyl-1-propenyl)benzene		$C_{10}H_{12}$	767-99-7	132.202			194.7; 177^{500}	0.9191^{25}	1.5402^{25}	i H_2O; s bz, chl
7705	*trans*-(1-Methyl-1-propenyl) benzene		$C_{10}H_{12}$	768-00-3	132.202	liq	-23.5	194.7	0.9138^{25}	1.5425^{20}	i H_2O; s bz, chl
7706	(2-Methyl-1-propenyl)benzene		$C_{10}H_{12}$	768-49-0	132.202	liq	-48.0	183; 99^{43}	0.900^{20}	1.5388^{20}	
7707	4-(2-Methylpropenyl)morpholine	1-Morpholinoisobutene	$C_8H_{15}NO$	2403-55-6	141.211		120	89^{20}		1.4663^{20}	
7708	2-(2-Methylpropoxy)ethanol		$C_6H_{14}O_2$	4439-24-1	118.174			160	0.8900^{20}	1.4143^{20}	
7709	Methylpropylamine	*N*-Methyl-1-propanamine	$C_4H_{11}N$	627-35-0	73.137			63	0.7204^{17}		
7710	1-Methyl-2-propylbenzene		$C_{10}H_{14}$	1074-17-5	134.218	liq	-60.3	185	0.8697^{25}	1.4996^{20}	
7711	1-Methyl-3-propylbenzene		$C_{10}H_{14}$	1074-43-7	134.218	liq	-82.5	182	0.8569^{25}	1.4935^{20}	
7712	1-Methyl-4-propylbenzene		$C_{10}H_{14}$	1074-55-1	134.218	liq	-63.6	183.4	0.8544^{25}	1.4922^{20}	i H_2O; s EtOH, eth
7713	*cis*-1-Methyl-2-propylcyclopentane		C_9H_{18}	932-43-4	126.239	liq	-104	152.6	0.7881^{25}	1.4343^{20}	
7714	*trans*-1-Methyl-2-propylcyclopentane		C_9H_{18}	932-44-5	126.239	liq	-123	146.4	0.7735^{25}	1.4274^{20}	
7715	Methyl propyl disulfide		$C_4H_{10}S_2$	2179-60-4	122.252	liq		70^{43}	0.980	1.5080^{20}	
7716	Methyl propyl ether	1-Methoxypropane	$C_4H_{10}O$	557-17-5	74.121			39.1	0.7356^{13}	1.3579^{25}	s H_2O, ace; msc EtOH, eth
7717	1-Methyl-2-propylpiperidine, (*S*)	Methylconiine	$C_9H_{19}N$	35305-13-6	141.254			174	0.8326^{22}	1.4538^{12}	vs ace, EtOH
7718	2-Methyl-2-propyl-1,3-propanediol		$C_7H_{16}O_2$	78-26-2	132.201	cry (hx)	62.5	234; 121^{10}			s H_2O, hx; sl chl
7719	2-Methyl-2-propyl-1,3-propanediol dicarbamate	Meprobamate	$C_9H_{18}N_2O_4$	57-53-4	218.250	cry (w)	105				vs bz, eth, EtOH
7720	Methyl propyl sulfide		$C_4H_{10}S$	3877-15-4	90.187	liq	-113	95.6	0.8424^{20}	1.4442^{20}	s H_2O, EtOH, eth, ace
7721	*N*-Methyl-2-propyn-1-amine		C_4H_7N	35161-71-8	69.106			83	0.819^{25}	1.4332^{20}	
7722	*N*-Methyl-*N*-2-propynylbenzenemethanamine	Pargyline	$C_{11}H_{13}N$	555-57-7	159.228			96^{11}	0.944^{25}	1.5213^{20}	
7723	3-Methylpyrazinamine	2-Amino-3-methylpyrazine	$C_5H_7N_3$	19838-08-5	109.130	nd (hx/ AcOEt)	174				
7724	2-Methylpyrazine		$C_5H_6N_2$	109-08-0	94.115	liq	-29	137	1.03^{20}	1.5042^{20}	msc H_2O, EtOH, eth; s ace; sl ctc
7725	1-Methyl-1*H*-pyrazole		$C_4H_6N_2$	930-36-9	82.104			127	0.9929^{13}	1.4787^{13}	
7726	3-Methyl-1*H*-pyrazole		$C_4H_6N_2$	1453-58-3	82.104		36.5	204; 108^{25}	1.0203^{16}	1.4915^{20}	msc H_2O, EtOH, eth
7727	4-Methyl-1*H*-pyrazole	Fomepizole	$C_4H_6N_2$	7554-65-6	82.104			206; 95^{13}	1.015^{20}		
7728	3-Methyl-2-pyrazolin-5-one		$C_4H_6N_2O$	108-26-9	98.103		215				vs H_2O; sl EtOH
7729	1-Methylpyrene		$C_{17}H_{12}$	2381-21-7	216.277		71.3	410			
7730	2-Methylpyrene		$C_{17}H_{12}$	3442-78-2	216.277	fl (EtOH)	143	409.8			
7731	3-Methylpyridazine	3-Methyl-1,2-diazine	$C_5H_6N_2$	1632-76-4	94.115		184	214	1.0450^{26}	1.5145^{20}	
7732	3-Methyl-2-pyridinamine	2-Amino-3-picoline	$C_6H_8N_2$	1603-40-3	108.141	hyg	33.5	222; 95^{8}			vs H_2O; s EtOH, eth, ace, bz, ctc; sl lig
7733	4-Methyl-2-pyridinamine	2-Amino-4-picoline	$C_6H_8N_2$	695-34-1	108.141	lf or pl (lig)	100	116^{11}			vs H_2O; s EtOH, eth, ace, bz; i lig; sl chl
7734	5-Methyl-2-pyridinamine		$C_6H_8N_2$	1603-41-4	108.141		76.5	227			
7735	6-Methyl-2-pyridinamine	2-Amino-6-picoline	$C_6H_8N_2$	1824-81-3	108.141	hyg (lig)	41	208.5			vs H_2O; s EtOH, eth, ace, bz, lig
7736	*N*-Methyl-2-pyridinamine		$C_6H_8N_2$	4597-87-9	108.141		15	200.5	1.048^{29}		s H_2O, bz; vs EtOH, eth, HOAc
7737	*N*-Methyl-4-pyridinamine		$C_6H_8N_2$	1121-58-0	108.141	pl (eth)	118.8				vs H_2O, ace, eth, EtOH
7738	2-Methylpyridine	2-Picoline	C_6H_7N	109-06-8	93.127	liq	-66.68	129.38	0.9443^{20}	1.4957^{20}	vs H_2O, ace; msc EtOH, eth; s ctc


2-Methylpropanoyl chloride



2-Methylpropenal



2-Methyl-2-propenamide


N-Methyl-2-propen-1-amine



2-Methyl-2-propene-1,1-diol diacetate



2-Methyl-1-propene, tetramer



2-Methyl-2-propenoic anhydride



2-Methyl-2-propenol



2-Methyl-2-propenoyl chloride



cis-(1-Methyl-1-propenyl)benzene



trans-(1-Methyl-1-propenyl)benzene



(2-Methyl-1-propenyl)benzene



4-(2-Methylpropenyl)morpholine



2-(2-Methylpropoxy)ethanol



Methylpropylamine



1-Methyl-2-propylbenzene



1-Methyl-3-propylbenzene



1-Methyl-4-propylbenzene



cis-1-Methyl-2-propylcyclopentane



trans-1-Methyl-2-propylcyclopentane



Methyl propyl disulfide



Methyl propyl ether



1-Methyl-2-propylpiperidine, (*S*)



2-Methyl-2-propyl-1,3-propanediol



2-Methyl-2-propyl-1,3-propanediol dicarbamate



Methyl propyl sulfide



N-Methyl-2-propyn-1-amine



N-Methyl-*N*-2-propynylbenzenemethanamine



3-Methylpyrazinamine



2-Methylpyrazine



1-Methyl-1*H*-pyrazole


3-Methyl-1*H*-pyrazole



4-Methyl-1*H*-pyrazole



3-Methyl-2-pyrazolin-5-one



1-Methylpyrene



2-Methylpyrene



3-Methylpyridazine



3-Methyl-2-pyridinamine


4-Methyl-2-pyridinamine


5-Methyl-2-pyridinamine



6-Methyl-2-pyridinamine



N-Methyl-2-pyridinamine



N-Methyl-4-pyridinamine



2-Methylpyridine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7739	3-Methylpyridine	3-Picoline	C_6H_7N	108-99-6	93.127	liq	-18.14	144.14	0.9566^{20}	1.5040^{20}	msc H_2O, EtOH, eth; vs ace; s ctc
7740	4-Methylpyridine	4-Picoline	C_6H_7N	108-89-4	93.127		3.67	145.36	0.9548^{20}	1.5037^{20}	msc H_2O, EtOH, eth; s ace, ctc
7741	6-Methyl-2-pyridinecarboxaldehyde		C_7H_7NO	1122-72-1	121.137		32	77^{12}			
7742	Methyl 3-pyridinecarboxylate	Methyl nicotinate	$C_7H_7NO_2$	93-60-7	137.137	cry	42.5	204			s H_2O, EtOH, bz
7743	Methyl 4-pyridinecarboxylate	Methyl isonicotinate	$C_7H_7NO_2$	2459-09-8	137.137		16.1	208	1.1599^{20}	1.5135^{20}	sl H_2O, ctc; s EtOH, eth, bz
7744	2-Methylpyridine-1-oxide		C_6H_7NO	931-19-1	109.126		49	260			
7745	3-Methylpyridine-1-oxide		C_6H_7NO	1003-73-2	109.126		39	148^{15}			s chl
7746	4-Methylpyridine-1-oxide		C_6H_7NO	1003-67-4	109.126		185.8				
7747	1-Methyl-2(1*H*)-pyridinone		C_6H_7NO	694-85-9	109.126	nd	31	250	1.1120^{20}		msc H_2O; sl peth, lig
7748	1-(6-Methyl-3-pyridinyl)ethanone		C_8H_9NO	36357-38-7	135.163		17.6	144^{50}	1.0168^{25}	1.5302^{25}	vs H_2O
7749	4-Methyl-2-pyrimidinamine		$C_5H_7N_3$	108-52-1	109.130	pl (w), nd (sub)	160.3	sub			s H_2O, EtOH; sl chl
7750	2-Methylpyrimidine	2-Methyl-1,3-diazine	$C_5H_6N_2$	5053-43-0	94.115	liq	-4	138			msc H_2O
7751	4-Methylpyrimidine	4-Methyl-1,3-diazine	$C_5H_6N_2$	3438-46-8	94.115		32	142	1.030^{16}	1.500^{20}	msc H_2O
7752	5-Methylpyrimidine	5-Methyl-1,3-diazine	$C_5H_6N_2$	2036-41-1	94.115		30.5	153			vs H_2O
7753	6-Methyl-2,4(1*H*,3*H*)-pyrimidinedione	6-Methyluracil	$C_5H_6N_2O_2$	626-48-2	126.114	oct pr or nd (w, al)	275 dec				s H_2O, EtOH; sl eth, tfa; vs NH_3
7754	1-Methylpyrrole		C_5H_7N	96-54-8	81.117	liq	-56.32	112.81	0.9145^{15}	1.4875^{20}	i H_2O; msc EtOH, eth
7755	2-Methylpyrrole		C_5H_7N	636-41-9	81.117	liq	-35.6	147.6	0.9446^{15}	1.5035^{16}	i H_2O; msc EtOH, eth
7756	3-Methylpyrrole		C_5H_7N	616-43-3	81.117	liq	-48.4	142.9; 45^{11}		1.4970^{20}	msc EtOH, eth
7757	*N*-Methylpyrrolidine		$C_5H_{11}N$	120-94-5	85.148			81	0.8188^{20}	1.4247^{20}	vs H_2O, eth
7758	1-Methyl-2,5-pyrrolidinedione		$C_5H_7NO_2$	1121-07-9	113.116	nd (eth-peth, al, ace)	71	234			s H_2O, EtOH; vs eth
7759	*N*-Methyl-2-pyrrolidinethione		C_5H_9NS	10441-57-3	115.197	oil		$100^{0.08}$			
7760	5-Methyl-2-pyrrolidinone		C_5H_9NO	108-27-0	99.131		43	248	1.0458^{20}		
7761	1-(1-Methyl-2-pyrrolidinyl)-2-propanone, (*R*)	Hygrine	$C_8H_{15}NO$	496-49-1	141.211			76.5^{11}		1.4555^{20}	vs EtOH, chl
7762	3-(1-Methyl-2-pyrrolidinyl) pyridine, (±)		$C_{10}H_{14}N_2$	22083-74-5	162.231			244	1.0082^{20}	1.5289^{20}	msc H_2O; vs EtOH, eth, chl; s lig
7763	*N*-Methyl-2-pyrrolidinone		C_5H_9NO	872-50-4	99.131	liq	-23.09	202	1.0230^{25}	1.4684^{20}	vs H_2O; s eth, ace, chl
7764	1-(1-Methyl-1*H*-pyrrol-2-yl) ethanone		C_7H_9NO	932-16-1	123.152			201^{252}, 93^{22}	1.0445^{15}	1.5403^{15}	s EtOH, bz, chl
7765	6-Methyl-8-quinolinamine	8-Amino-6-methylquinoline	$C_{10}H_{10}N_2$	68420-93-9	158.199	nd	73	sub			vs ace, bz, eth, EtOH
7766	2-Methylquinoline	Quinaldine	$C_{10}H_9N$	91-63-4	143.185	col oily liq	-0.8	246.5	1.06^{25}	1.6116^{20}	sl H_2O; s EtOH, eth, ace, ctc, chl
7767	3-Methylquinoline		$C_{10}H_9N$	612-58-8	143.185	pr	16.5	259.8	1.0673^{20}	1.6171^{20}	vs ace, eth, EtOH
7768	4-Methylquinoline	Lepidine	$C_{10}H_9N$	491-35-0	143.185	col oily liq	9.5	262	1.083^{20}	1.6200^{20}	sl H_2O; s EtOH, eth, ace; i alk
7769	5-Methylquinoline		$C_{10}H_9N$	7661-55-4	143.185	col cry	19	262.7	1.0832^{20}	1.6219^{20}	sl H_2O; s ace; msc EtOH, eth
7770	6-Methylquinoline		$C_{10}H_9N$	91-62-3	143.185	col oily liq	-22	258.6	1.0654^{20}	1.6157^{20}	sl H_2O; s EtOH, eth, ace
7771	7-Methylquinoline	*m*-Toluquinoline	$C_{10}H_9N$	612-60-2	143.185	ye cry	39	257.6	1.0609^{20}	1.6150^{20}	sl H_2O; s EtOH, eth, ace
7772	8-Methylquinoline		$C_{10}H_9N$	611-32-5	143.185	col liq	-80	247.5	1.0719^{20}	1.6164^{20}	sl H_2O; s ace; msc EtOH, eth
7773	2-Methyl-8-quinolinol		$C_{10}H_9NO$	826-81-3	159.184		73.8	267			i H_2O; s EtOH, eth, bz, ctc
7774	1-Methyl-2(1*H*)-quinolinone		$C_{10}H_9NO$	606-43-9	159.184	nd (lig)	74	325			sl H_2O, lig; s EtOH, eth, ace; vs bz
7775	1-Methyl-4(1*H*)-quinolinone	Echinopsine	$C_{10}H_9NO$	83-54-5	159.184	α-nd (bz); β-cry (al)					s H_2O; vs EtOH, bz, chl; sl eth
7776	2-Methylquinoxaline		$C_9H_8N_2$	7251-61-8	144.173	ye cry	180.5	244			msc H_2O, eth, ace, bz; vs EtOH; s ctc
7777	Methyl Red	Benzoic acid, 2-[[4-(dimethylamino)phenyl]azo]-	$C_{15}H_{15}N_3O_2$	493-52-7	269.299	viol or red pr (to, bz)	183				sl H_2O, lig; s EtOH; vs ace, bz, chl
7778	Methyl β-*D*-ribofuranoside		$C_6H_{12}O_5$	7473-45-2	164.156		80				


3-Methylpyridine


4-Methylpyridine



6-Methyl-2-pyridinecarboxaldehyde


Methyl 3-pyridinecarboxylate



Methyl 4-pyridinecarboxylate



2-Methylpyridine-1-oxide


3-Methylpyridine-1-oxide


4-Methylpyridine-1-oxide


1-Methyl-2(1*H*)-pyridinone



1-(6-Methyl-3-pyridinyl)ethanone


4-Methyl-2-pyrimidinamine


2-Methylpyrimidine



4-Methylpyrimidine


5-Methylpyrimidine



6-Methyl-2,4(1*H*,3*H*)-pyrimidinedione


1-Methylpyrrole



2-Methylpyrrole



3-Methylpyrrole



N-Methylpyrrolidine


1-Methyl-2,5-pyrrolidinedione


N-Methyl-2-pyrrolidinethione



5-Methyl-2-pyrrolidinone



1-(1-Methyl-2-pyrrolidinyl)-2-propanone, (*R*)



3-(1-Methyl-2-pyrrolidinyl)pyridine, (±)



N-Methyl-2-pyrrolidinone



1-(1-Methyl-1*H*-pyrrol-2-yl)ethanone



6-Methyl-8-quinolinamine



2-Methylquinoline



3-Methylquinoline



4-Methylquinoline



5-Methylquinoline



6-Methylquinoline



7-Methylquinoline



8-Methylquinoline



2-Methyl-8-quinolinol


1-Methyl-2(1*H*)-quinolinone



1-Methyl-4(1*H*)-quinolinone


2-Methylquinoxaline


Methyl Red


Methyl β-*D*-ribofuranoside


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7779	Methyl salicylate	Methyl 2-hydroxybenzoate	$C_8H_8O_3$	119-36-8	152.148	liq	-8	222.9	1.181^{25}	1.535^{20}	sl H_2O; vs eth, EtOH, chl
7780	Methylsilane		CH_6Si	992-94-9	46.145	col gas	-156.5	-57.5			
7781	Methyl silyl ether		CH_6OSi	2171-96-2	62.144	col gas	-98.5	-21; -87[10]			
7782	Methylstannane		CH_6Sn	1631-78-3	136.769	col gas		0			dec H_2O
7783	Methyl stearate		$C_{19}H_{38}O_2$	112-61-8	298.504		39.1	443; 215^{15}	0.8498^{40}	1.4367^{40}	vs eth, chl
7784	2-Methylstyrene		C_9H_{10}	611-15-4	118.175	liq	-68.5	169.8	0.9077^{25}	1.5437^{20}	i H_2O; s bz, chl
7785	3-Methylstyrene		C_9H_{10}	100-80-1	118.175	liq	-86.3	164	0.9076^{25}	1.5411^{20}	i H_2O; s EtOH, eth, bz
7786	4-Methylstyrene		C_9H_{10}	622-97-9	118.175	liq	-34.1	172.8	0.9173^{25}	1.5420	i H_2O; s bz
7787	Methylsuccinic acid		$C_5H_8O_4$	636-60-2	132.116	pr	115	dec	1.4200^{0}	1.4303	vs H_2O, EtOH, MeOH; s eth; sl chl
7788	Methyl sulfate		CH_4O_4S	75-93-4	112.106		<-30	dec 135			vs H_2O, eth, EtOH
7789	(Methylsulfinyl)benzene		C_7H_8OS	1193-82-4	140.203		32.0	263.5; 140[13]		1.5885^{20}	
7790	1-(Methylsulfinyl)decane	Decyl methyl sulfoxide	$C_{11}H_{24}OS$	3079-28-5	204.373	cry	52.5				
7791	3-Methyl sulfolane		$C_5H_{10}O_2S$	872-93-5	134.197		1	276	1.188^{25}	1.4772^{20}	
7792	(Methylsulfonyl)ethene		$C_3H_6O_2S$	3680-02-2	106.144			122^{24}	1.2117^{20}	1.4636^{20}	s eth, ace
7793	Methyl terephthalate	Methyl 1,4-benzenedicarboxylate	$C_9H_8O_4$	1679-64-7	180.158	nd (w)	222	subl ≈ 230			
7794	17-Methyltestosterone	17-Hydroxy-17-methylandrost-4-en-3-one, (17β)	$C_{20}H_{30}O_2$	58-18-4	302.451		163.5				vs eth, EtOH
7795	Methyl tetradecanoate		$C_{15}H_{30}O_2$	124-10-7	242.398		19	295; 155^{7}	0.8671^{20}	1.425^{45}	i H_2O; msc EtOH, eth, ace, bz, chl, ctc
7796	5-*N*-Methyl-5,6,7,8-tetrahydrofolic acid		$C_{20}H_{25}N_7O_6$	134-35-0	459.456	cry (w)					
7797	2-Methyltetrahydrofuran		$C_5H_{10}O$	96-47-9	86.132			78	0.8552^{20}	1.4059^{21}	s H_2O; vs EtOH, eth, ace, bz; sl ctc
7798	*N*-Methyl-*N*,2,4,6-tetranitroaniline	Tetryl	$C_7H_5N_5O_8$	479-45-8	287.144	ye pr (al)	131.5	exp 180	1.57^{10}		i H_2O; sl EtOH, eth, chl; s ace, bz, py
7799	4-Methyl-2-thiazolamine	2-Amino-4-methylthiazole	$C_4H_6N_2S$	1603-91-4	114.169		45.5	125^{20}, $70^{0.4}$			vs H_2O, EtOH, eth
7800	2-Methylthiazole		C_4H_5NS	3581-87-1	99.155			128		1.510	msc H_2O; s EtOH, ace
7801	4-Methylthiazole		C_4H_5NS	693-95-8	99.155			133.3	1.112^{25}		s H_2O, EtOH, eth
7802	4-Methyl-5-thiazoleethanol		C_6H_9NOS	137-00-8	143.206	col to pa ye		135^{7}	1.196^{24}		vs H_2O; s EtOH, eth, bz, chl
7803	4-Methyl-2(3*H*)-thiazolethione		$C_4H_5NS_2$	5685-06-3	131.220	ye cry (dil al)	89.3	188^{3}			vs EtOH
7804	Methylthiirane		C_3H_6S	1072-43-1	74.145	liq	-91	72.5	0.941^{20}	1.472^{20}	s chl
7805	(Methylthio)acetic acid		$C_3H_6O_2S$	2444-37-3	106.144		13.0	130^{27}	1.221^{20}	1.495^{20}	
7806	2-(Methylthio)aniline		C_7H_9NS	2987-53-3	139.218			234	1.111^{25}	1.6239^{20}	
7807	4-(Methylthio)aniline		C_7H_9NS	104-96-1	139.218			272.5	1.1379^{20}	1.6395^{20}	s EtOH, eth, ace, bz
7808	(Methylthio)benzene	Methyl phenyl sulfide	C_7H_8S	100-68-5	124.204			193	1.0579^{20}	1.5868^{20}	i H_2O; s EtOH; vs ace
7809	2-(Methylthio)benzothiazole		$C_8H_7NS_2$	615-22-5	181.279	pr (dil al)	52	174^{22}			s EtOH, chl
7810	Methyl thiocyanate		C_2H_3NS	556-64-9	73.117	col liq	-2.5	132.9	1.0678^{25}	1.4669^{25}	sl H_2O; msc EtOH, eth; s ctc
7811	2-(Methylthio)ethanol		C_3H_8OS	5271-38-5	92.160			70^{20}	1.063^{20}	1.4861^{30}	vs H_2O, eth, EtOH
7812	(Methylthio)ethene		C_3H_6S	1822-74-8	74.145			69.5	0.9026^{20}	1.4837^{20}	s eth, ace, chl
7813	[(Methylthio)methyl]benzene		$C_8H_{10}S$	766-92-7	138.230	liq	-30	210; 120^{48}	1.0274^{20}	1.5620^{20}	
7814	4-(Methylthio)-2-oxobutanoic acid		$C_5H_8O_3S$	583-92-6	148.181	oil					
7815	2-Methylthiophene		C_5H_6S	554-14-3	98.167	liq	-63.4	112.6	1.0193^{20}	1.5203^{20}	i H_2O; msc EtOH, eth, ace, bz, hp, ctc
7816	3-Methylthiophene		C_5H_6S	616-44-4	98.167	liq	-69	115.5	1.0218^{20}	1.5204^{20}	i H_2O; msc EtOH, eth, ace, bz; vs chl
7817	5-Methyl-2-thiophenecarboxaldehyde		C_6H_6OS	13679-70-4	126.176			114^{25}		1.5825^{20}	s chl
7818	4-(Methylthio)phenol		C_7H_8OS	1073-72-9	140.203		84	154^{20}, 113^{6}			
7819	3-(Methylthio)propanal		C_4H_8OS	3268-49-3	104.171			62^{11}			
7820	3-(Methylthio)propanoic acid	*S*-Methylpropiothetin	$C_4H_8O_2S$	646-01-5	120.171	ye oil or fl (hx)	21	132^{13}			
7821	3-(Methylthio)-1-propene		C_4H_8S	10152-76-8	88.172			92	0.8767^{20}	1.4714^{20}	
7822	*N*-Methylthiosemicarbazide	*N*-Methylhydrazinecarbothioamide	$C_2H_7N_3S$	6610-29-3	105.162		136.5				s H_2O, EtOH, DMSO; i eth, bz, lig



Methyl salicylate



Methylsilane



Methyl silyl ether



Methylstannane


Methyl stearate



2-Methylstyrene



3-Methylstyrene



4-Methylstyrene


Methylsuccinic acid



Methyl sulfate



(Methylsulfinyl)benzene



1-(Methylsulfinyl)decane



3-Methyl sulfolane


(Methylsulfonyl)ethene



Methyl terephthalate



17-Methyltestosterone


Methyl tetradecanoate


5-*N*-Methyl-5,6,7,8-tetrahydrofolic acid



2-Methyltetrahydrofuran


N-Methyl-*N*,2,4,6-tetranitroaniline


4-Methyl-2-thiazolamine



2-Methylthiazole



4-Methylthiazole



4-Methyl-5-thiazoleethanol



4-Methyl-2(3*H*)-thiazolethione



Methylthiirane


(Methylthio)acetic acid



2-(Methylthio)aniline


4-(Methylthio)aniline



(Methylthio)benzene



2-(Methylthio)benzothiazole


Methyl thiocyanate


2-(Methylthio)ethanol



(Methylthio)ethene



[(Methylthio)methyl]benzene


4-(Methylthio)-2-oxobutanoic acid



2-Methylthiophene


3-Methylthiophene



5-Methyl-2-thiophenecarboxaldehyde


4-(Methylthio)phenol


3-(Methylthio)propanal


3-(Methylthio)propanoic acid


3-(Methylthio)-1-propene



N-Methylthiosemicarbazide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7823	Methylthiouracil		$C_5H_6N_2OS$	56-04-2	142.179		330 dec	sub			i H_2O; sl EtOH, eth, MeOH, bz
7824	Methylthiourea		$C_2H_6N_2S$	598-52-7	90.147	pr (EtOH)	121				vs H_2O, EtOH; sl eth; s ace
7825	1-Methylthymine	1,5-Dimethyl-2,4(1*H*,3*H*)-pyrimidinedione	$C_6H_8N_2O_2$	4160-72-9	140.140	nd (w)	295				s H_2O
7826	Methylthymol blue, sodium salt		$C_{37}H_{40}N_2O_{13}Na_4S$	1945-77-3	844.743	bl-viol cry					s H_2O
7827	Methyl 4-toluenesulfonate		$C_8H_{10}O_3S$	80-48-8	186.228		28.5	292; 186^{22}	1.2087^{40}		i H_2O; vs EtOH, bz; s eth, ctc; sl lig
7828	Methyltriacetoxysilane	Methylsilanetriol, triacetate	$C_7H_{12}O_6Si$	4253-34-3	220.252		40.5	111^{17}	1.1750^{20}	1.4083^{20}	
7829	6-Methyl-1,2,4-triazine-3,5(2*H*,4*H*)-dione	6-Azathymine	$C_4H_5N_3O_2$	932-53-6	127.102	cry (w)	211				s H_2O, EtOH, ace
7830	5-Methyl-[1,2,4]triazolo[1,5-a] pyrimidin-7-ol		$C_6H_6N_4O$	2503-56-2	150.138		>245				
7831	Methyl trichloroacetate		$C_3H_3Cl_3O_2$	598-99-2	177.414	liq	-17.5	153.8	1.4874^{20}	1.4572^{20}	i H_2O; vs EtOH, eth; s ctc
7832	Methyltrichlorosilane		CH_3Cl_3Si	75-79-6	149.480	liq	-90	65.6	1.273^{20}	1.4106^{20}	dec H_2O, EtOH
7833	Methyl tridecanoate		$C_{14}H_{28}O_2$	1731-88-0	228.371		6.5	92^{1}		1.4405^{20}	msc EtOH; s ctc
7834	Methyltriethyllead	Triethylmethylplumbane	$C_7H_{18}Pb$	1762-28-3	309.4	col liq		70^{16}	1.71^{20}		
7835	Methyl trifluoroacetate		$C_3H_3F_3O_2$	431-47-0	128.050			43.0	1.28^{20}		
7836	Methyl trifluoromethyl ether		$C_2H_3F_3O$	421-14-7	100.039	col gas	-149	-23.66			
7837	Methyl 3,4,5-trihydroxybenzoate		$C_8H_8O_5$	99-24-1	184.147	mcl pr (MeOH)	202				sl H_2O; vs EtOH, MeOH
7838	Methyl 3,4,5-trimethoxybenzoate		$C_{11}H_{14}O_5$	1916-07-0	226.226		83	274.5			
7839	Methyltriphenoxysilane		$C_{19}H_{18}O_3Si$	3439-97-2	322.430			269^{100}, 179^{2}	1.135^{20}	1.5599^{20}	
7840	Methyl trithion		$C_9H_{12}ClO_2PS_3$	953-17-3	314.812	ye liq	-18				sl H_2O; misc os
7841	*N*-Methyl-*L*-tryptophan	*L*-Abrine	$C_{12}H_{14}N_2O_2$	526-31-8	218.251	pr (w)	295 dec				sl H_2O, MeOH; i eth; s alk
7842	*N*-Methyl-*L*-tyrosine	Surinamine	$C_{10}H_{13}NO_3$	537-49-5	195.215	nd	293				
7843	α-Methyl-*DL*-tyrosine, methyl ester, hydrochloride		$C_{11}H_{16}ClNO_3$	7361-31-1	245.703		190 dec				s H_2O
7844	2-Methylundecanal		$C_{12}H_{24}O$	110-41-8	184.318			119^{16}, 114^{10}	0.832^{15}	1.4321^{20}	sl H_2O; s EtOH, eth
7845	2-Methylundecane		$C_{12}H_{26}$	7045-71-8	170.334	liq	-45.6	210.2		1.4191^{20}	
7846	3-Methylundecane		$C_{12}H_{26}$	1002-43-3	170.334	col liq	-58.0	211.2	0.7485^{25}	1.4208^{25}	
7847	Methyl undecanoate		$C_{12}H_{24}O_2$	1731-86-8	200.318			123^{10}			
7848	2-Methyl-1-undecanol		$C_{12}H_{26}O$	10522-26-6	186.333			129^{12}	0.8300^{15}	1.4382^{20}	vs eth, EtOH
7849	Methyl 10-undecenoate		$C_{12}H_{22}O_2$	111-81-9	198.302	liq	-27.5	248	0.889^{15}	1.4393^{20}	i H_2O; s EtOH, eth, HOAc; sl ctc
7850	*N*-Methylurea		$C_2H_6N_2O$	598-50-5	74.081	orth pr (w, al)	104.9	dec	1.2040^{0}		vs H_2O, EtOH; i eth, bz; s CS_2, lig
7851	5-Methyluridine	Thymine riboside	$C_{10}H_{14}N_2O_6$	1463-10-1	258.227	cry (EtOH)	184				
7852	3-Methyl-*L*-valine	*L*-*tert*-Leucine	$C_6H_{13}NO_2$	20859-02-3	131.173		248 dec				
7853	2-(1-Methylvinyl)aniline		$C_9H_{11}N$	52562-19-3	133.190			115^{20}, 95^{13}	0.977^{25}	1.5722^{20}	
7854	1-Methyl-4-vinylcyclohexene		C_9H_{14}	17699-86-4	122.207	liq		152	0.85	1.4701^{20}	
7855	4-(1-Methylvinyl)-1-cyclohexene-1-carboxaldehyde, (*R*)	*d*-Perillaldehyde	$C_{10}H_{14}O$	5503-12-8	150.217	oil		238; 99^{7}	0.953^{20}	1.5058^{20}	s ctc
7856	4-(1-Methylvinyl)-1-cyclohexene-1-carboxaldehyde, (*S*)	*l*-Perillaldehyde	$C_{10}H_{14}O$	18031-40-8	150.217	oil		104^{10}	0.9645^{20}	1.5072^{20}	
7857	4-(1-Methylvinyl)-1-cyclohexene-1-methanol		$C_{10}H_{16}O$	536-59-4	152.233			244; 12.5^{12}	0.9690^{20}	1.5005^{20}	
7858	(1-Methylvinyl)cyclopropane		C_6H_{10}	4663-22-3	82.143	liq	-102.3	70	0.751^{20}	1.4252^{20}	
7859	Methyl vinyl ether		C_3H_6O	107-25-5	58.079	col gas	-122	5.5	0.7725^{0}	1.3730^{0}	sl H_2O; vs EtOH, eth, ace, bz
7860	Methyl Violet	C.I. Basic Violet 1	$C_{24}H_{28}ClN_3$	8004-87-3	393.952	bl-viol pow	137 dec				s H_2O, EtOH
7861	Methysergide		$C_{21}H_{27}N_3O_2$	361-37-5	353.458	cry	195				
7862	Methysticin		$C_{15}H_{14}O_5$	495-85-2	274.269	nd (MeOH), pr (ace)	137				
7863	Metobromuron	3-(*p*-Bromophenyl)-1-methoxy-1-methylurea	$C_9H_{11}BrN_2O_2$	3060-89-7	259.099		95		1.60^{20}		
7864	Metolachlor		$C_{15}H_{22}ClNO_2$	51218-45-2	283.795			$100^{0.001}$	1.12^{20}		
7865	Metolazone		$C_{16}H_{16}ClN_3O_3S$	17560-51-9	365.834	cry (EtOH)	254				
7866	Metoprolol tartrate		$C_{34}H_{56}N_2O_{12}$	56392-17-7	684.815	cry	121				
7867	Metribuzin		$C_8H_{14}N_4OS$	21087-64-9	214.288		126		1.31^{20}		
7868	Metronidazole	2-Methyl-5-nitro-1*H*-imidazole-1-ethanol	$C_6H_9N_3O_3$	443-48-1	171.153		160.5				
7869	Metsulfuron-methyl		$C_{14}H_{15}N_5O_6S$	74223-64-6	381.364	wh cry	163				sl H_2O
7870	Mevinphos		$C_7H_{13}O_6P$	7786-34-7	224.148		21 (*E*), 6.9 (*Z*)	$101^{0.3}$			
7871	Mexacarbate	4-(Dimethylamino)-3,5-xylyl methylcarbamate	$C_{12}H_{18}N_2O_2$	315-18-4	222.283	cry	85				vs EtOH, bz, ace



Methylthiouracil



Methylthiourea



1-Methylthymine



Methylthymol blue, sodium salt


Methyl 4-toluenesulfonate



Methyltriacetoxysilane


6-Methyl-1,2,4-triazine-3,5(2*H*,4*H*)-dione


5-Methyl-[1,2,4]triazolo[1,5-a]pyrimidin-7-ol


Methyl trichloroacetate



Methyltrichlorosilane



Methyl tridecanoate



Methyltriethyllead



Methyl trifluoroacetate



Methyl trifluoromethyl ether



Methyl 3,4,5-trihydroxybenzoate



Methyl 3,4,5-trimethoxybenzoate



Methyltriphenoxysilane



Methyl trithion



N-Methyl-*L*-tryptophan



N-Methyl-*L*-tyrosine



α-Methyl-*DL*-tyrosine, methyl ester, hydrochloride



2-Methylundecanal



2-Methylundecane



3-Methylundecane



Methyl undecanoate



2-Methyl-1-undecanol



Methyl 10-undecenoate



N-Methylurea



5-Methyluridine



3-Methyl-*L*-valine



2-(1-Methylvinyl)aniline


1-Methyl-4-vinylcyclohexene



4-(1-Methylvinyl)-1-cyclohexene-1-carboxaldehyde, (*R*)



4-(1-Methylvinyl)-1-cyclohexene-1-carboxaldehyde, (*S*)



4-(1-Methylvinyl)-1-cyclohexene-1-methanol



(1-Methylvinyl)cyclopropane



Methyl vinyl ether



Methyl Violet



Methysergide



Methysticin



Metobromuron



Metolachlor



Metolazone



Metoprolol tartrate


Metribuzin



Metronidazole



Metsulfuron-methyl



Mevinphos



Mexacarbate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7872	MGK 264		$C_{17}H_{25}NO_2$	113-48-4	275.387		<-20	157	1.04		
7873	Mifepristone	RU-486	$C_{29}H_{35}NO_2$	84371-65-3	429.594	cry	150				
7874	Mimosine		$C_8H_{10}N_2O_4$	500-44-7	198.176	tab (w)	228 dec				sl H_2O; i EtOH, eth, ace, bz; s dil alk
7875	Minocycline		$C_{23}H_{27}N_3O_7$	10118-90-8	457.476	ye-oran amorp solid					
7876	Minoxidil		$C_9H_{15}N_5O$	38304-91-5	209.248	cry	248				i ace, bz, chl, sl; EtOH, MeOH
7877	Mipafox	Bis(isopropylamido) fluorophosphate	$C_6H_{16}FN_2OP$	371-86-8	182.175	cry (peth)	65	125^{2}			sl H_2O
7878	Mirex	Hexachloropentadiene dimer	$C_{10}Cl_{12}$	2385-85-5	545.543	cry (bz)	485 dec				vs bz, diox
7879	Misoprostol		$C_{22}H_{38}O_5$	59122-46-2	382.534	ye oil					s H_2O
7880	Mithramycin	Plicamycin	$C_{52}H_{76}O_{24}$	18378-89-7	1085.145	ye cry (ace)	182				s H_2O, EtOH, AcOEt; sl bz, eth
7881	Mitomycin A		$C_{16}H_{19}N_3O_6$	4055-39-4	349.338	purp nd	160 dec				
7882	Mitomycin B		$C_{16}H_{19}N_3O_6$	4055-40-7	349.338	purp-bl nd	dec				
7883	Mitomycin C		$C_{15}H_{18}N_4O_5$	50-07-7	334.328	bl-viol cry	360				s H_2O, MeOH, ace
7884	Mitotane		$C_{14}H_{10}Cl_4$	53-19-0	320.041		77				
7885	Mitragynine	9-Methoxycorynantheidine	$C_{23}H_{30}N_2O_4$	4098-40-2	398.495	wh amor pow	104	235^{5}			s EtOH, chl, HOAc
7886	Molinate	Ethyl 1-hexamethyleneiminecarbothiolate	$C_9H_{17}NOS$	2212-67-1	187.302			202^{10}	1.063^{20}		
7887	Molindone		$C_{16}H_{24}N_2O_2$	7416-34-4	276.374	cry	180				
7888	Molybdenum hexacarbonyl		C_6MoO_6	13939-06-5	264.00		dec 150				s os
7889	Monobutyl phthalate	1,2-Benzenedicarboxylic acid, monobutyl ester	$C_{12}H_{14}O_4$	131-70-4	222.237	pl (ace, al)	73.5				vs EtOH, chl
7890	Monobutyltin trichloride		$C_4H_9Cl_3Sn$	1118-46-3	282.183	hyg liq	-63	93^{10}	0.85^{20}		s bz, CH_2Cl_2
7891	Monocrotaline		$C_{16}H_{23}NO_6$	315-22-0	325.357	wh pr (EtOH)	198 dec				
7892	Monocrotophos		$C_7H_{14}NO_5P$	6923-22-4	223.164		55	$125^{0.0005}$	1.33^{20}		
7893	Monolinuron	*N'*-(4-Chlorophenyl)-*N*-methoxy-*N*-methylurea	$C_9H_{11}ClN_2O_2$	1746-81-2	214.648	solid	77				
7894	Monomethyl adipate		$C_7H_{12}O_4$	627-91-8	160.168	lf (Me_2N-MeOH)	9	158^{10}	1.0623^{20}	1.4283^{20}	s EtOH
7895	Monomethyl glutarate		$C_6H_{10}O_4$	1501-27-5	146.141			158^{27}, 150^{10}	1.169^{25}	1.4381^{20}	
7896	Monosodium *L*-glutamate		$C_5H_8NNaO_4$	142-47-2	169.113						s H_2O
7897	Moquizone		$C_{20}H_{21}N_3O_3$	19395-58-5	351.399		136				s chl
7898	Morin		$C_{15}H_{10}O_7$	480-16-0	302.236	pa ye nd (+ 1 w, dil al)	303.5				sl H_2O, eth; vs EtOH; s bz, alk; i CS_2
7899	Morphine		$C_{17}H_{19}NO_3$	57-27-2	285.338	pr	255	sub 190			i H_2O, eth, ace; s MeOH, py; sl EtOH
7900	4-Morpholinamine		$C_4H_{10}N_2O$	4319-49-7	102.134			166	1.059^{25}	1.4772^{20}	
7901	Morpholine	Tetrahydro-1,4-oxazine	C_4H_9NO	110-91-8	87.120	hyg liq	-4.8	128	1.0005^{20}	1.4548^{20}	msc H_2O; s EtOH, eth, ace, bz; sl chl
7902	4-Morpholinecarboxaldehyde		$C_5H_9NO_2$	4394-85-8	115.131		21	239	1.1520^{20}	1.4845^{20}	
7903	4-Morpholineethanamine		$C_6H_{14}N_2O$	2038-03-1	130.187		25.6	205	0.9897^{20}	1.4715^{20}	msc H_2O, EtOH, bz, lig; s ace
7904	4-Morpholineethanol		$C_6H_{13}NO_2$	622-40-2	131.173	liq	-0.8	227	1.0710^{20}	1.4763^{20}	s H_2O, EtOH; sl ctc
7905	4-Morpholinepropanamine	4-(3-Aminopropyl)morpholine	$C_7H_{16}N_2O$	123-00-2	144.214	liq	-15	220; 134^{50}	0.9854^{20}	1.4762^{20}	msc H_2O, EtOH, bz, lig; s ace; sl ctc
7906	2-(4-Morpholinothio) benzothiazole	4-(2-Benzothiazolylthio) morpholine	$C_{11}H_{12}N_2OS_2$	102-77-2	252.355	cry (EtOH)	85				
7907	4-(4-Morpholinyl)aniline		$C_{10}H_{14}N_2O$	2524-67-6	178.230		131.6				
7908	2-(4-Morpholinyldithio) benzothiazole		$C_{11}H_{12}N_2OS_3$	95-32-9	284.420		135				
7909	Muldamine		$C_{29}H_{47}NO_3$	36069-45-1	457.688		210				
7910	Murexide	5,5'-Nitrilobarbituric acid, ammonium salt	$C_8H_{10}N_6O_7$	3051-09-0	302.201						sl H_2O; i EtOH, eth; s alk
7911	Muscimol	5-(Aminomethyl)-3(2*H*)-isoxazolone	$C_4H_6N_2O_2$	2763-96-4	114.103	cry (EtOH)	175 dec				
7912	Myclobutanil		$C_{15}H_{17}ClN_4$	88671-89-0	288.776	ye cry	65	$205^{1.0}$			i H_2O, peth; s EtOH
7913	Mycophenolic acid		$C_{17}H_{20}O_6$	24280-93-1	320.337	nd (w)	141				i H_2O; vs EtOH, eth, chl; sl bz, tol



MGK 264



Mifepristone



Mimosine



Minocycline



Minoxidil



Mipafox



Mithramycin



Mirex



Misoprostol



Mitomycin A



Mitomycin B



Mitomycin C



Mitotane



Mitragynine



Molinate



Molindone



Molybdenum hexacarbonyl



Monobutyl phthalate



Monobutyltin trichloride



Monocrotaline



Monocrotophos



Monolinuron



Monomethyl adipate



Monomethyl glutarate



Monosodium *L*-glutamate



Moquizone



Morin



Morphine



4-Morpholinamine



Morpholine



4-Morpholinecarboxaldehyde



4-Morpholineethanamine



4-Morpholineethanol



4-Morpholinepropanamine



2-(4-Morpholinothio)benzothiazole



4-(4-Morpholinyl)aniline



2-(4-Morpholinyldithio)benzothiazole


Muldamine



Murexide



Muscimol



Myclobutanil



Mycophenolic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7914	β-Myrcene	7-Methyl-3-methylene-1,6-octadiene	$C_{10}H_{16}$	123-35-3	136.234			167	0.8013^{15}	1.4722^{20}	i H_2O; s EtOH, eth, bz, chl, HOAc
7915	Myristicin		$C_{11}H_{12}O_3$	607-91-0	192.211		<-20	276.5	1.1416^{20}	1.5403^{20}	i H_2O; sl EtOH; s eth, bz
7916	Nabam	Sodium ethylenebisdithiocarbamic acid	$C_4H_6N_2Na_2S_4$	142-59-6	256.344	cry (w)					s H_2O
7917	Nadolol		$C_{17}H_{27}NO_4$	42200-33-9	309.401	cry (bz)	≈130				s EtOH; sl chl; i ace, eth, hx
7918	Naled	1,2-Dibromo-2,2-dichloroethylphosphoric acid, dimethyl ester	$C_4H_7Br_2Cl_2O_4P$	300-76-5	380.784		27	$110^{0.5}$	1.96^{20}		
7919	Nalidixic acid		$C_{12}H_{12}N_2O_3$	389-08-2	232.234		229.5				sl EtOH, eth; s chl
7920	Nalmefene		$C_{21}H_{25}NO_3$	55096-26-9	339.429	cry (AcOEt)	189				
7921	Nalorphine	Acetorphin	$C_{19}H_{21}NO_3$	62-67-9	311.375	cry (eth)	208				sl H_2O; s alk, ace, EtOH
7922	Naloxone		$C_{19}H_{21}NO_4$	465-65-6	327.375	cry (AcOEt)	178				i peth; s chl
7923	Naltrexone		$C_{20}H_{23}NO_4$	16590-41-3	341.402	cry (ace)	169				
7924	Nandrolone	17-Hydroxyestr-4-en-3-one	$C_{18}H_{26}O_2$	434-22-0	274.398	cry	112				s EtOH, eth, chl
7925	Naphazoline hydrochloride		$C_{14}H_{14}ClN_2$	550-99-2	245.727						sl H_2O
7926	Naphthacene	2,3-Benzanthracene	$C_{18}H_{12}$	92-24-0	228.288	oran-ye lf (bz, xyl)	357	sub			i H_2O; sl bz; s con sulf
7927	5,12-Naphthacenedione		$C_{18}H_{10}O_2$	1090-13-7	258.271		285 dec				sl ace, bz, gl HOAc
7928	Naphthalene		$C_{10}H_8$	91-20-3	128.171	mcl pl (al)	80.26	217.9	1.0253^{20}	1.5898^{25}	i H_2O; s EtOH; vs eth, ace, bz, CS_2
7929	1-Naphthaleneacetamide		$C_{12}H_{11}NO$	86-86-2	185.221	nd(w, al)		sub 180			i H_2O; s eth, bz, CS_2, HOAc
7930	1-Naphthaleneacetic acid	1-Naphthylacetic acid	$C_{12}H_{10}O_2$	86-87-3	186.206	nd (w)	133	dec			sl H_2O, EtOH; vs eth, ace, chl; s bz
7931	2-Naphthaleneacetic acid	2-Naphthylacetic acid	$C_{12}H_{10}O_2$	581-96-4	186.206	lf(w) cry (bz)	143				vs eth, lig, chl
7932	1-Naphthaleneacetonitrile		$C_{12}H_9N$	132-75-2	167.206		32.5	192^{18}, 163^{12}		1.6192^{20}	s EtOH
7933	1-Naphthalenecarbonitrile		$C_{11}H_7N$	86-53-3	153.181	nd (lig)	37.5	299	1.1080^{25}	1.6298^{18}	i H_2O; vs EtOH, eth; s lig
7934	2-Naphthalenecarbonitrile		$C_{11}H_7N$	613-46-7	153.181	lf (lig)	66	306.5	1.0755^{60}		sl H_2O, chl; s EtOH, eth, lig
7935	1-Naphthalenecarbonyl chloride		$C_{11}H_7ClO$	879-18-5	190.626		20	297.5			
7936	2-Naphthalenecarbonyl chloride		$C_{11}H_7ClO$	2243-83-6	190.626	cry (peth)	51	305			vs bz, eth, chl
7937	1-Naphthalenecarboxaldehyde		$C_{11}H_8O$	66-77-3	156.181	pa ye	33.5	292	1.1503^{20}	1.6507^{20}	i H_2O; s EtOH, eth, ace, bz, sulf
7938	2-Naphthalenecarboxaldehyde		$C_{11}H_8O$	66-99-9	156.181	lf (w)	62	160^{19}	1.0775^{99}	1.6211^{99}	sl H_2O; vs EtOH, eth; s ace
7939	1-Naphthalenecarboxylic acid	1-Naphthoic acid	$C_{11}H_8O_2$	86-55-5	172.181	nd (HOAc-w, w, al)	161	>300	1.398^{25}	1.46	i H_2O; vs eth, EtOH, chl
7940	2-Naphthalenecarboxylic acid	2-Naphthoic acid	$C_{11}H_8O_2$	93-09-4	172.181	nd (lig, chl, sub) pl (ace)	185.5	>300	1.077^{100}		sl H_2O, DMSO, lig; s EtOH, eth, chl
7941	1,5-Naphthalenediamine	1,5-Diaminonaphthalene	$C_{10}H_{10}N_2$	2243-62-1	158.199	pr (eth, al, w)	190	sub	1.4^{25}		s H_2O, EtOH, eth; vs chl
7942	1,8-Naphthalenediamine	1,8-Diaminonaphthalene	$C_{10}H_{10}N_2$	479-27-6	158.199		66.5	205^{12}	1.1265^{90}	1.6828^{99}	vs eth, EtOH
7943	2,3-Naphthalenediamine	2,3-Diaminonaphthalene	$C_{10}H_{10}N_2$	771-97-1	158.199	lf (eth, w)	199		1.0968^{26}	1.6392^{26}	sl H_2O, DMSO; vs EtOH; s eth
7944	1,8-Naphthalenedicarboxylic acid	Naphthalic acid	$C_{12}H_8O_4$	518-05-8	216.190		260				i H_2O; sl EtOH, eth
7945	2,3-Naphthalenedicarboxylic acid		$C_{12}H_8O_4$	2169-87-1	216.190	pr (HOAc, w, sub)	244.5				i H_2O, bz, chl; sl EtOH, eth, DMSO
7946	2,6-Naphthalenedicarboxylic acid		$C_{12}H_8O_4$	1141-38-4	216.190	nd (al or sub)	>300 dec				vs EtOH
7947	2,6-Naphthalenedicarboxylic acid, dimethyl ester		$C_{14}H_{12}O_4$	840-65-3	244.243		190.0				
7948	1,5-Naphthalene diisocyanate	1,5-Diisocyanatonaphthalene	$C_{12}H_6N_2O_2$	3173-72-6	210.188	cry	127	183^{10}			
7949	1,3-Naphthalenediol	Naphthoresorcinol	$C_{10}H_8O_2$	132-86-5	160.170	lf (w)	123.5				s H_2O, EtOH, eth; sl ace, bz, lig
7950	1,4-Naphthalenediol		$C_{10}H_8O_2$	571-60-8	160.170	mcl nd (bz, w)	192				s H_2O, EtOH, eth; sl ace; i bz
7951	1,5-Naphthalenediol		$C_{10}H_8O_2$	83-56-7	160.170	pr (w), nd (sub)	262 dec	sub			sl H_2O, EtOH; vs eth, ace; i bz; s HOAc



β-Myrcene



Myristicin



Nabam



Nadolol



Naled



Nalidixic acid



Nalmefene



Nalorphine



Naloxone



Naltrexone



Nandrolone



Naphazoline hydrochloride



Naphthacene



5,12-Naphthacenedione



Naphthalene



1-Naphthaleneacetamide



1-Naphthaleneacetic acid



2-Naphthaleneacetic acid



1-Naphthaleneacetonitrile



1-Naphthalenecarbonitrile



2-Naphthalenecarbonitrile



1-Naphthalenecarbonyl chloride



2-Naphthalenecarbonyl chloride



1-Naphthalenecarboxaldehyde



2-Naphthalenecarboxaldehyde



1-Naphthalenecarboxylic acid



2-Naphthalenecarboxylic acid



1,5-Naphthalenediamine



1,8-Naphthalenediamine



2,3-Naphthalenediamine



1,8-Naphthalenedicarboxylic acid



2,3-Naphthalenedicarboxylic acid



2,6-Naphthalenedicarboxylic acid


2,6-Naphthalenedicarboxylic acid, dimethyl ester



1,5-Naphthalene diisocyanate



1,3-Naphthalenediol



1,4-Naphthalenediol



1,5-Naphthalenediol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7952	1,6-Naphthalenediol		$C_{10}H_8O_2$	575-44-0	160.170	pr (bz)	138	sub			sl H_2O, EtOH; s eth, ace, bz, DMSO
7953	1,7-Naphthalenediol		$C_{10}H_8O_2$	575-38-2	160.170	nd (bz or sub)	180.5	sub			sl H_2O; vs EtOH, eth; s bz, HOAc
7954	2,3-Naphthalenediol		$C_{10}H_8O_2$	92-44-4	160.170	lf (w)	163.5				s H_2O, EtOH, eth, ace, bz, lig, HOAc
7955	2,6-Naphthalenediol		$C_{10}H_8O_2$	581-43-1	160.170	orth pl (w)	220	sub			sl H_2O, bz; s EtOH, eth, ace; i lig
7956	2,7-Naphthalenediol		$C_{10}H_8O_2$	582-17-2	160.170	nd, (w, dil al), pl (dil al)	193	sub			s H_2O, EtOH, eth, bz, chl; sl ace; i lig
7957	1,2-Naphthalenedione	1,2-Naphthoquinone	$C_{10}H_6O_2$	524-42-5	158.154	ye-red nd (eth) oran lf (bz)	146		1.450^{25}		s H_2O, EtOH, eth, sulf; sl lig
7958	1,4-Naphthalenedione	1,4-Naphthoquinone	$C_{10}H_6O_2$	130-15-4	158.154	bt ye nd (al, peth) ye (sub)	128.5	sub			sl H_2O; vs EtOH; s eth, bz, chl, CS_2
7959	1,5-Naphthalenedisulfonic acid	Armstrong's acid	$C_{10}H_8O_6S_2$	81-04-9	288.297	pl (+4w, dil HOAc)	242 dec		1.493^{25}		vs H_2O; s EtOH; i eth
7960	1,6-Naphthalenedisulfonic acid	Naphthalene-1,6-disulfonic acid	$C_{10}H_8O_6S_2$	525-37-1	288.297	oran pr (+4w, HOAc or w)	125 dec				vs H_2O; s EtOH; i eth
7961	2,7-Naphthalenedisulfonic acid	Naphthalene-2,7-disulfonic acid	$C_{10}H_8O_6S_2$	92-41-1	288.297	hyg nd (conc HCl)	199				s H_2O; sl con HCl
7962	1-Naphthalenemethanamine		$C_{11}H_{11}N$	118-31-0	157.212			292	1.0958^{20}		s EtOH, eth, sulf, CS_2
7963	1-Naphthalenemethanol		$C_{11}H_{10}O$	4780-79-4	158.196	nd (w, al), cry (bz-lig)	64	304; 163^{12}	1.1039^{80}		sl H_2O; vs EtOH, eth
7964	2-Naphthalenemethanol		$C_{11}H_{10}O$	1592-38-7	158.196	lf	81.3	178^{12}			sl H_2O; s EtOH, eth
7965	1-Naphthalenesulfonic acid	α-Naphthylsulfonic acid	$C_{10}H_8O_3S$	85-47-2	208.234	pr (+2 w, dil HCl)	140				s H_2O, EtOH; sl eth
7966	2-Naphthalenesulfonic acid	β-Naphthylsulfonic acid	$C_{10}H_8O_3S$	120-18-3	208.234	hyg pl (+1w), cry (+3w, HCl)	91	dec	1.441^{25}		vs H_2O, EtOH; s eth; sl bz
7967	1-Naphthalenesulfonyl chloride		$C_{10}H_7ClO_2S$	85-46-1	226.680	lf (eth)	68	209^{20}, 147$^{0.9}$			vs bz, eth, EtOH
7968	2-Naphthalenesulfonyl chloride		$C_{10}H_7ClO_2S$	93-11-8	226.680	pow or lf (bz-peth)	81	201^{13}, 148$^{0.5}$			i H_2O; s EtOH, bz, chl; sl peth; vs eth
7969	1,4,5,8-Naphthalenetetracarboxylic acid		$C_{14}H_8O_8$	128-97-2	304.209	lf or nd (w, dil HCl)	320				sl H_2O, bz, chl, EtOH; vs ace
7970	1-Naphthalenethiol	1-Naphthyl mercaptan	$C_{10}H_8S$	529-36-2	160.236			dec 285; 161^{20}	1.1607^{20}	1.6802^{20}	sl H_2O, dil alk; vs EtOH, eth
7971	2-Naphthalenethiol	2-Naphthyl mercaptan	$C_{10}H_8S$	91-60-1	160.236	pl (al)	81	288	1.550^{25}		sl H_2O; vs EtOH, eth, lig
7972	*N*-(1-Naphthalenyl)-1,2-ethanediamine, dihydrochloride		$C_{12}H_{16}Cl_2N_2$	1465-25-4	259.174	hex pr	189				vs H_2O, EtOH
7973	1-Naphthalenylthiourea	ANTU	$C_{11}H_{10}N_2S$	86-88-4	202.275	pr (al)	198				i H_2O; sl EtOH, eth, ace
7974	Naphtho[2,3-c]furan-1,3-dione	2,3-Naphthalenedicarboxylic acid anhydride	$C_{12}H_6O_3$	716-39-2	198.174		246				sl EtOH, chl; s eth, bz
7975	1-Naphthol	1-Naphthalenol	$C_{10}H_8O$	90-15-3	144.170	ye nd (w)	95.0	288; 184^{40}	1.0989^{99}	1.6224^{99}	i H_2O; vs EtOH, eth; s ace, bz; sl ctc
7976	2-Naphthol	2-Naphthalenol	$C_{10}H_8O$	135-19-3	144.170	mcl lf (w)	121.5	285	1.28^{20}		i H_2O; vs EtOH, eth; s bz, chl; sl lig
7977	1-Naphthol, acetate	1-Naphthyl acetate	$C_{12}H_{10}O_2$	830-81-9	186.206	nd or pl (al)	49	114^{1}			i H_2O; s EtOH, eth
7978	2-Naphthol, acetate	2-Naphthyl acetate	$C_{12}H_{10}O_2$	1523-11-1	186.206	nd (al)	71.0	132^{2}			i H_2O; s EtOH, eth, chl
7979	*p*-Naphtholbenzein		$C_{27}H_{18}O_2$	145-50-6	374.431		123				
7980	1*H*,3*H*-Naphtho[1,8-cd]pyran-1,3-dione		$C_{12}H_6O_3$	81-84-5	198.174		275.0				i H_2O, eth, bz; sl EtOH; s HOAc
7981	1-Naphthylamine	α-Naphthylamine	$C_{10}H_9N$	134-32-7	143.185		49.2	300.7	1.0228^{20}	1.6140^{20}	s chl
7982	2-Naphthylamine	β-Naphthylamine	$C_{10}H_9N$	91-59-8	143.185		113	306.2	1.6414^{98}	1.6493^{98}	s H_2O, EtOH, eth
7983	2-[(1-Naphthylamino)carbonyl] benzoic acid	Naptalam	$C_{18}H_{13}NO_3$	132-66-1	291.301		185		1.4^{20}		i H_2O; sl EtOH, ace, bz, tfa
7984	2-Naphthyl benzoate	2-Naphthalenol benzoate	$C_{17}H_{12}O_2$	93-44-7	248.276	nd or pr (al)	107				i H_2O; s EtOH; sl eth, HOAc
7985	*N*-1-Naphthalenylacetamide		$C_{12}H_{11}NO$	575-36-0	185.221		160				s H_2O, EtOH; sl eth
7986	*N*-1-Naphthyl-1,2-ethanediamine	*N*-(1-Naphthyl)ethylenediamine	$C_{12}H_{14}N_2$	551-09-7	186.252	visc lig		204^{9}	1.114^{25}	1.6648^{25}	



1,6-Naphthalenediol



1,7-Naphthalenediol



2,3-Naphthalenediol



2,6-Naphthalenediol



2,7-Naphthalenediol



1,2-Naphthalenedione



1,4-Naphthalenedione



1,5-Naphthalenedisulfonic acid



1,6-Naphthalenedisulfonic acid



2,7-Naphthalenedisulfonic acid



1-Naphthalenemethanamine



1-Naphthalenemethanol



2-Naphthalenemethanol



1-Naphthalenesulfonic acid



2-Naphthalenesulfonic acid



1-Naphthalenesulfonyl chloride



2-Naphthalenesulfonyl chloride



1,4,5,8-Naphthalenetetracarboxylic acid



1-Naphthalenethiol



2-Naphthalenethiol



N-(1-Naphthalenyl)-1,2-ethanediamine, dihydrochloride



1-Naphthalenylthiourea



Naphtho[2,3-c]furan-1,3-dione



1-Naphthol



2-Naphthol



1-Naphthol, acetate



2-Naphthol, acetate



p-Naphtholbenzein



1*H*,3*H*-Naphtho[1,8-cd]pyran-1,3-dione



1-Naphthylamine


2-Naphthylamine



2-[(1-Naphthylamino)carbonyl]benzoic acid



2-Naphthyl benzoate



N-1-Naphthalenylacetamide



N-1-Naphthyl-1,2-ethanediamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
7987	1-Naphthyl 2-hydroxybenzoate	1-Naphthyl salicylate	$C_{17}H_{12}O_3$	550-97-0	264.275		83				vs eth
7988	1-Naphthylhydroxylamine	*N*-Hydroxyl-1-naphthalenamine	$C_{10}H_9NO$	607-30-7	159.184		79				
7989	1-Naphthyl isothiocyanate	1-Isothiocyanatonaphthalene	$C_{11}H_7NS$	551-06-4	185.246	wh nd (al)	58				vs bz, eth, EtOH, chl
7990	*N*-2-Naphthyl-2-naphthalenamine	β,β'-Dinaphthylamine	$C_{20}H_{15}N$	532-18-3	269.340	lf(bz)	172.2	471			i H_2O; sl EtOH, bz, DMSO; s eth, HOAc
7991	(2-Naphthyloxy)acetic acid	2-Naphthoxyacetic acid	$C_{12}H_{10}O_3$	120-23-0	202.205	pr(w)	156				s H_2O, EtOH, eth; sl DMSO
7992	1-Naphthyl phosphate	1-Naphthalenol, dihydrogen phosphate	$C_{10}H_9O_4P$	1136-89-6	224.149	cry	160				
7993	2-Naphthyl salicylate	2-Naphthyl 2-hydroxybenzoate	$C_{17}H_{12}O_3$	613-78-5	264.275	cry (al)	95.5		1.11^{116}		i H_2O; sl EtOH; s eth, bz
7994	1,5-Naphthyridine	1,5-Diazanaphthalene	$C_8H_6N_2$	254-79-5	130.147	ye nd (peth)	75	112^{12}	1.2100^{20}		
7995	1,6-Naphthyridine		$C_8H_6N_2$	253-72-5	130.147		29.5				
7996	Napropamide	Propanamide, *N,N*-diethyl-2-(1-naphthalenyloxy)-	$C_{17}H_{21}NO_2$	15299-99-7	271.355		75				
7997	Naproxen	6-Methoxy-α-methyl-2-naphthaleneacetic acid	$C_{14}H_{14}O_3$	22204-53-1	230.259	cry (ace/hx)	155				i H_2O; sl eth; s MeOH, chl
7998	Narceine		$C_{23}H_{27}NO_8$	131-28-2	445.462		138				i H_2O
7999	Narcobarbital		$C_{11}H_{15}BrN_2O_3$	125-55-3	303.152		115				sl H_2O; s EtOH, py
8000	Naringenin		$C_{15}H_{12}O_5$	480-41-1	272.253	nd (dil al)	251				vs bz, eth, EtOH
8001	Naringin		$C_{27}H_{32}O_{14}$	10236-47-2	580.535	nd (w+8)					sl H_2O, EtOH; i eth, bz, chl; s HOAc
8002	Nealbarbital		$C_{12}H_{18}N_2O_3$	561-83-1	238.282		156				vs ace, eth, EtOH
8003	Nellite	Diamidafos	$C_8H_{13}N_2O_2P$	1754-58-1	200.175	cry (ctc)	103.5				sl AcOEt, bz
8004	Neoabietic acid	8(14),13(15)-Abietadien-18-oic acid	$C_{20}H_{30}O_2$	471-77-2	302.451	cry (EtOH aq)	173				
8005	Neobornylamine		$C_{10}H_{19}N$	2223-67-8	153.265	pow	184				vs ace, eth
8006	Neopentane	2,2-Dimethylpropane	C_5H_{12}	463-82-1	72.149	col gas	-16.4	9.48	0.5852^{25} (p>1 atm	1.3476^6	i H_2O; s EtOH, eth, ctc
8007	Neopine		$C_{18}H_{21}NO_3$	467-14-1	299.365	nd (peth)	127.5				s H_2O, EtOH, eth, bz; vs chl; sl lig
8008	Neostigmine bromide		$C_{12}H_{19}BrN_2O_2$	114-80-7	303.195	cry (al-eth)	167 dec				vs H_2O; s EtOH
8009	Nepetalactone		$C_{10}H_{14}O_2$	490-10-8	166.217			71$^{0.05}$	1.0663^{25}	1.4859^{25}	
8010	*cis*-Nerolidol		$C_{15}H_{26}O$	142-50-7	222.366			276; 70$^{0.1}$	0.8778^{20}	1.4898^{20}	vs EtOH; s eth, ace, HOAc
8011	Neurine		$C_5H_{13}NO$	463-88-7	103.163	syr					vs H_2O, eth, EtOH
8012	Neutral Red		$C_{15}H_{17}ClN_4$	553-24-2	288.776	grn pow					s H_2O, ethylene glycol, EtOH; i xyl
8013	Nialamide		$C_{16}H_{18}N_4O_2$	51-12-7	298.340		151.6				
8014	Nickel(II) acetate		$C_4H_6NiO_4$	373-02-4	176.782						vs H_2O; s EtOH
8015	Nickel bis(dibutyldithiocarbamate)		$C_{18}H_{36}N_2NiS_4$	13927-77-0	467.445	grn cry (bz/ EtOH)	91				s bz, ace
8016	Nickel bis(2,4-pentanedioate)	Nickel acetylacetonate	$C_{10}H_{14}NiO_4$	3264-82-2	256.909	grn orth cry	230	227^{11}			s H_2O, bz, chl, EtOH; i eth
8017	Nickel carbonyl	Nickel tetracarbonyl	C_4NiO_4	13463-39-3	170.734	col liq	-19.3	43 (exp 60)	1.31^{25}		
8018	Nickelocene	Bis(η5-2,4-cyclopentadien-1-yl)nickel	$C_{10}H_{10}Ni$	1271-28-9	188.879		172				
8019	Niclosamide		$C_{13}H_8Cl_2N_2O_4$	50-65-7	327.120		227				
8020	Nicofibrate		$C_{16}H_{16}ClNO_3$	31980-29-7	305.756		49	180$^{0.4}$			
8021	Nicosulfuron		$C_{15}H_{18}N_6O_6S$	111991-09-4	410.405		172				
8022	Nicotelline	3,2':4',3"-Terpyridine	$C_{15}H_{11}N_3$	494-04-2	233.268	prismatic nd	148	>300			sl H_2O, eth; s bz, chl, EtOH
8023	Nicotinamide hypoxanthine dinucleotide	Nicotinic acid adenine dinucleotide	$C_{21}H_{26}N_6O_{15}P_2$	1851-07-6	664.410	pow					
8024	β-Nicotinamide mononucleotide	NMN	$C_{11}H_{15}N_2O_8P$	1094-61-7	334.219	amor pow					vs H_2O; i ace
8025	*L*-Nicotine	3-(1-Methyl-2-pyrrolidinyl) pyridine, (*S*)-	$C_{10}H_{14}N_2$	54-11-5	162.231	hyg liq	-79	247; 125^{18}	1.0097^{20}	1.5282^{20}	msc H_2O; vs EtOH, eth, chl; s lig
8026	Nifurthiazole		$C_8H_6N_4O_4S$	3570-75-0	254.224	cry	215 dec				
8027	Nitralin	4-(Methylsulfonyl)-2,6-dinitro-*N,N*-dipropylaniline	$C_{13}H_{19}N_3O_6S$	4726-14-1	345.371		150				
8028	Nitranilic acid	2,5-Dihydroxy-3,6-dinitro-2,5-cyclohexadiene-1,4-dione	$C_6H_2N_2O_8$	479-22-1	230.088	gold-ye pl (+w, dil HNO_3	170 dec				vs H_2O, EtOH; i eth
8029	Nitrapyrin	Pyridine, 2-chloro-6-(trichloromethyl)-	$C_6H_3Cl_4N$	1929-82-4	230.907		63	136^{11}			



1-Naphthyl 2-hydroxybenzoate



1-Naphthylhydroxylamine



1-Naphthyl isothiocyanate



N-2-Naphthyl-2-naphthalenamine



(2-Naphthyloxy)acetic acid



1-Naphthyl phosphate



2-Naphthyl salicylate



1,5-Naphthyridine



1,6-Naphthyridine



Napropamide



Naproxen



Narceine



Narcobarbital



Naringenin


Naringin



Nealbarbital



Nellite



Neoabietic acid



Neobornylamine



Neopentane



Neopine



Neostigmine bromide



Nepetalactone



cis-Nerolidol



Neurine



Neutral Red



Nialamide



Nickel(II) acetate



Nickel bis(dibutyldithiocarbamate)



Nickel bis(2,4-pentanedioate)



Nickel carbonyl



Nickelocene



Niclosamide



Nicofibrate



Nicosulfuron



Nicotelline



Nicotinamide hypoxanthine dinucleotide



β-Nicotinamide mononucleotide


L-Nicotine



Nifurthiazole



Nitralin



Nitranilic acid



Nitrapyrin


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8030	Nitrilotriacetic acid	*N,N*-Bis(carboxymethyl)glycine	$C_6H_9NO_6$	139-13-9	191.138	pr cry (w)	242 dec				sl H_2O, DMSO; s EtOH
8031	2,2',2"-Nitrilotriacetonitrile	Tricyanotrimethylamine	$C_6H_6N_4$	7327-60-8	134.139	nd (EtOH)	125.5				
8032	Nitroacetic acid		$C_2H_3NO_4$	625-75-2	105.050	nd (chl)	92 dec				vs bz, eth, EtOH, chl
8033	Nitroacetone		$C_3H_5NO_3$	10230-68-9	103.077	pl, nd (eth, bz)	50.3	103^{24}			vs bz, eth, EtOH
8034	2-Nitroaniline		$C_6H_6N_2O_2$	88-74-4	138.124		71.0	284	0.9015^{25}		sl H_2O; s EtOH; vs eth, ace, bz, chl
8035	3-Nitroaniline		$C_6H_6N_2O_2$	99-09-2	138.124		113.4	dec 306	0.9011^{25}		sl H_2O, bz; s EtOH, eth, ace; vs MeOH
8036	4-Nitroaniline		$C_6H_6N_2O_2$	100-01-6	138.124	pa ye mcl nd (w)	147.5	332	1.424^{20}		i H_2O; s EtOH, eth, ace; sl bz, DMSO
8037	2-Nitroanisole	1-Methoxy-2-nitrobenzene	$C_7H_7NO_3$	91-23-6	153.136		10.5	277; 144^{4}	1.2540^{20}	1.5161^{20}	i H_2O; msc EtOH, eth; s ctc
8038	3-Nitroanisole	1-Methoxy-3-nitrobenzene	$C_7H_7NO_3$	555-03-3	153.136	nd (al), pl (bz-lig)	38.5	258	1.373^{18}		i H_2O; s EtOH; vs eth
8039	4-Nitroanisole	1-Methoxy-4-nitrobenzene	$C_7H_7NO_3$	100-17-4	153.136	pr (al), nd (dil al)	54	274	1.2192^{60}	1.5070^{60}	i H_2O; vs EtOH, eth; s ctc; sl peth
8040	9-Nitroanthracene		$C_{14}H_9NO_2$	602-60-8	223.227	ye nd (al) pr (HOAc or xyl)	146	275^{17}			i H_2O; sl EtOH, chl; vs ace, CS_2
8041	1-Nitro-9,10-anthracenedione		$C_{14}H_7NO_4$	82-34-8	253.211	nd (HOAc) ye pr (ace)	231.5	270^{7}			i H_2O; sl EtOH, eth; s ace, bz
8042	2-Nitrobenzaldehyde		$C_7H_5NO_3$	552-89-6	151.120	ye nd (w)	43.5	153^{23}	1.2844^{20}		sl H_2O, chl; vs EtOH, eth, ace, bz
8043	3-Nitrobenzaldehyde		$C_7H_5NO_3$	99-61-6	151.120	lt ye nd (w)	58.5	164^{23}	1.2792^{20}		sl H_2O; s EtOH, eth, chl; vs ace, bz
8044	4-Nitrobenzaldehyde		$C_7H_5NO_3$	555-16-8	151.120	lf, pr (w)	107	sub	1.496^{25}		sl H_2O, lig; vs EtOH; s bz, chl, HOAc
8045	3-Nitrobenzamide		$C_7H_6N_2O_3$	645-09-0	166.134		142.7	312.5			s H_2O, EtOH, eth
8046	4-Nitrobenzamide		$C_7H_6N_2O_3$	619-80-7	166.134	nd (w)	200.7				i H_2O; s EtOH, eth
8047	Nitrobenzene		$C_6H_5NO_2$	98-95-3	123.110		5.7	210.8	1.2037^{20}	1.5562^{20}	sl H_2O, ctc; vs EtOH, eth, ace, bz
8048	2-Nitrobenzeneacetic acid	*o*-Nitrophenylacetic acid	$C_8H_7NO_4$	3740-52-1	181.147	nd (w, pl (dil al)	141.5				s H_2O, EtOH
8049	3-Nitrobenzeneacetic acid	*m*-Nitrophenylacetic acid	$C_8H_7NO_4$	1877-73-2	181.147	nd (w)	122				vs EtOH
8050	4-Nitrobenzeneacetic acid	*p*-Nitrophenylacetic acid	$C_8H_7NO_4$	104-03-0	181.147	pa ye nd (w)	154				sl H_2O; s EtOH, eth, bz
8051	2-Nitrobenzeneacetonitrile	2-Nitrobenzyl cyanide	$C_8H_6N_2O_2$	610-66-2	162.146	nd (dil al), pr (HOAc, al)	84	178^{12}, 138^{1}			vs ace, bz, eth, EtOH
8052	4-Nitrobenzeneacetonitrile	4-Nitrobenzyl cyanide	$C_8H_6N_2O_2$	555-21-5	162.146	pr (al)	117	196^{12}			sl H_2O; s EtOH, eth, bz, chl
8053	4-Nitro-1,2-benzenediamine	4-Nitro-*o*-phenylenediamine	$C_6H_7N_3O_2$	99-56-9	153.139	dk red nd (dil al)	199.5				s acid
8054	4-Nitro-1,3-benzenediamine		$C_6H_7N_3O_2$	5131-58-8	153.139	oran pr (w)	161				
8055	5-Nitro-1,3-benzenediamine		$C_6H_7N_3O_2$	5042-55-7	153.139	red cry (w)	143				
8056	2-Nitro-1,4-benzenediamine		$C_6H_7N_3O_2$	5307-14-2	153.139		140.0				
8057	3-Nitro-1,2-benzenedicarboxylic acid		$C_8H_5NO_6$	603-11-2	211.129	pa ye pr (w)	218				sl H_2O, ace; s EtOH; i bz, peth, chl
8058	4-Nitro-1,2-benzenedicarboxylic acid		$C_8H_5NO_6$	610-27-5	211.129	pa ye nd (w, eth)	164.8				s H_2O, EtOH; i bz, chl, CS_2, peth
8059	2-Nitrobenzeneethanol		$C_8H_9NO_3$	15121-84-3	167.162		1.0	267	1.19^{25}	1.5637^{20}	
8060	4-Nitrobenzeneethanol		$C_8H_9NO_3$	100-27-6	167.162		63	148^{2}			
8061	2-Nitrobenzenemethanol	2-Nitrobenzyl alcohol	$C_7H_7NO_3$	612-25-9	153.136	nd (w)	74	270; 168^{20}			sl H_2O; s EtOH, eth
8062	3-Nitrobenzenemethanol	3-Nitrobenzyl alcohol	$C_7H_7NO_3$	619-25-0	153.136	orth nd (w)	30.5	177^{3}	1.296^{19}		s H_2O, EtOH, eth; sl chl
8063	4-Nitrobenzenemethanol	4-Nitrobenzyl alcohol	$C_7H_7NO_3$	619-73-8	153.136	nd (w)	96.5	dec 255; 185^{12}			sl H_2O, ace; s EtOH, eth
8064	2-Nitrobenzenesulfenyl chloride		$C_6H_4ClNO_2S$	7669-54-7	189.620	ye nd (bz)	75				vs eth, bz, chl
8065	4-Nitrobenzenesulfenyl chloride		$C_6H_4ClNO_2S$	937-32-6	189.620	ye lf (peth)	52	125$^{0.1}$			vs bz
8066	4-Nitrobenzenesulfonamide		$C_6H_6N_2O_4S$	6325-93-5	202.188		180 dec				



Nitrilotriacetic acid



2,2',2"-Nitrilotriacetonitrile



Nitroacetic acid



Nitroacetone



2-Nitroaniline



3-Nitroaniline



4-Nitroaniline



2-Nitroanisole



3-Nitroanisole



4-Nitroanisole



9-Nitroanthracene



1-Nitro-9,10-anthracenedione



2-Nitrobenzaldehyde



3-Nitrobenzaldehyde



4-Nitrobenzaldehyde



3-Nitrobenzamide



4-Nitrobenzamide



Nitrobenzene



2-Nitrobenzeneacetic acid



3-Nitrobenzeneacetic acid



4-Nitrobenzeneacetic acid



2-Nitrobenzeneacetonitrile



4-Nitrobenzeneacetonitrile



4-Nitro-1,2-benzenediamine



4-Nitro-1,3-benzenediamine



5-Nitro-1,3-benzenediamine



2-Nitro-1,4-benzenediamine



3-Nitro-1,2-benzenedicarboxylic acid



4-Nitro-1,2-benzenedicarboxylic acid



2-Nitrobenzeneethanol



4-Nitrobenzeneethanol



2-Nitrobenzenemethanol


3-Nitrobenzenemethanol



4-Nitrobenzenemethanol



2-Nitrobenzenesulfenyl chloride



4-Nitrobenzenesulfenyl chloride



4-Nitrobenzenesulfonamide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8067	3-Nitrobenzenesulfonic acid		$C_6H_5NO_5S$	98-47-5	203.173	pl	48				vs H_2O; s EtOH; i eth, bz
8068	4-Nitrobenzenesulfonic acid		$C_6H_5NO_5S$	138-42-1	203.173		95				vs H_2O
8069	2-Nitrobenzenesulfonyl chloride		$C_6H_4ClNO_4S$	1694-92-4	221.619	pr (lig, eth-peth)	68.5				s eth; sl peth
8070	3-Nitrobenzenesulfonyl chloride		$C_6H_4ClNO_4S$	121-51-7	221.619	mcl pr (eth) nd (lig)	64				i H_2O; s EtOH
8071	4-Nitrobenzenesulfonyl chloride		$C_6H_4ClNO_4S$	98-74-8	221.619	mcl pr (peth)	79.5	143$^{1.5}$			s peth
8072	5-Nitro-1*H*-benzimidazole		$C_7H_5N_3O_2$	94-52-0	163.134	nd (w)	207.8				i H_2O, eth, bz, chl; s acid; vs EtOH
8073	2-Nitrobenzoic acid		$C_7H_5NO_4$	552-16-9	167.120	tcl nd (w)	147.5		1.575^{20}		s H_2O, eth; vs EtOH, ace; sl bz, lig
8074	3-Nitrobenzoic acid		$C_7H_5NO_4$	121-92-6	167.120	mcl pr (w)	141.1		1.494^{20}		sl H_2O, bz; vs EtOH, eth, ace; s chl
8075	4-Nitrobenzoic acid		$C_7H_5NO_4$	62-23-7	167.120	mcl lf (w)	242	sub	1.610^{20}		vs ace, eth, EtOH, chl, MeOH
8076	3-Nitrobenzoic acid, hydrazide		$C_7H_7N_3O_3$	618-94-0	181.149		153.5				sl H_2O, EtOH; i eth, bz, chl
8077	4-Nitrobenzoic acid, hydrazide		$C_7H_7N_3O_3$	636-97-5	181.149		215.5				sl H_2O, EtOH; i eth, bz, chl
8078	3-Nitrobenzonitrile		$C_7H_4N_2O_2$	619-24-9	148.119		118	165^{16}			s H_2O, EtOH, bz; vs eth, ace; i peth
8079	4-Nitrobenzonitrile		$C_7H_4N_2O_2$	619-72-7	148.119		150.0				sl H_2O, EtOH, eth; s chl, HOAc
8080	5-Nitro-1*H*-benzotriazole		$C_6H_4N_4O_2$	2338-12-7	164.122		217				
8081	2-Nitrobenzoyl chloride		$C_7H_4ClNO_3$	610-14-0	185.565		20				vs eth; sl ctc
8082	3-Nitrobenzoyl chloride		$C_7H_4ClNO_3$	121-90-4	185.565		36	276.5			vs eth
8083	4-Nitrobenzoyl chloride		$C_7H_4ClNO_3$	122-04-3	185.565	ye nd (lig)	75	203^{105}, 151^{15}			s eth
8084	2-Nitrobiphenyl	2-Nitro-1,1'-biphenyl	$C_{12}H_9NO_2$	86-00-0	199.205	pl (al, MeOH)	37.2	320	1.44^{25}		i H_2O; s EtOH, eth, chl
8085	3-Nitrobiphenyl	3-Nitro-1,1'-biphenyl	$C_{12}H_9NO_2$	2113-58-8	199.205	ye pl or nd (dil al)	62	227^{35}, 143^{9}			i H_2O; s EtOH, eth, HOAc, lig
8086	4-Nitrobiphenyl	4-Nitro-1,1'-biphenyl	$C_{12}H_9NO_2$	92-93-3	199.205	ye nd (al)	114	340			i H_2O; sl EtOH; s eth, bz, chl, HOAc
8087	2-Nitro-1,1-bis(*p*-chlorophenyl) propane		$C_{15}H_{13}Cl_2NO_2$	117-27-1	310.176	cry	81	180$^{0.16}$			
8088	1-Nitrobutane		$C_4H_9NO_2$	627-05-4	103.120			153	0.970^{25}	1.4303^{20}	sl H_2O; msc EtOH, eth; s alk
8089	2-Nitro-1-butanol		$C_4H_9NO_3$	609-31-4	119.119		-47	105^{10}	1.1332^{25}	1.4390^{20}	s H_2O, ace; msc EtOH, eth; sl ctc
8090	3-Nitro-2-butanol		$C_4H_9NO_3$	6270-16-2	119.119			91^{9}, 55$^{0.5}$	1.1260^{20}	1.4414^{20}	
8091	6-Nitrochrysene		$C_{18}H_{11}NO_2$	7496-02-8	273.286	ye nd (bz)	≈215 dec				
8092	Nitrocyclohexane		$C_6H_{11}NO_2$	1122-60-7	129.157	liq	-34	205; 95^{22}	1.0610^{20}	1.4612^{19}	i H_2O; s EtOH, lig
8093	1-Nitrodecane		$C_{10}H_{21}NO_2$	4609-87-4	187.280			86^{1}		1.4337^{20}	
8094	*N*-Nitrodiethylamine	*N*-Ethyl-*N*-nitroethanamine	$C_4H_{10}N_2O_2$	7119-92-8	118.134			206.5	1.057^{15}		vs eth, EtOH
8095	Nitroethane		$C_2H_5NO_2$	79-24-3	75.067	liq	-89.5	114.0	1.0448^{25}	1.3917^{20}	sl H_2O; msc EtOH, eth; s ace, chl
8096	2-Nitroethanol		$C_2H_5NO_3$	625-48-9	91.066	liq	-80	194; 102^{10}	1.270^{15}	1.4438^{19}	msc H_2O, EtOH, eth; i bz
8097	Nitroethene		$C_2H_3NO_2$	3638-64-0	73.051	liq	-55.5	98.5	1.2212^{14}	1.4282^{20}	vs EtOH, eth, ace, bz, chl
8098	(2-Nitroethyl)benzene		$C_8H_9NO_2$	6125-24-2	151.163	liq	-23	250; 137^{16}	1.126^{24}	1.5407^{19}	
8099	Nitrofen	2,4-Dichloro-1-(4-nitrophenoxy)benzene	$C_{12}H_7Cl_2NO_3$	1836-75-5	284.095		70				
8100	2-Nitro-9*H*-fluorene		$C_{13}H_9NO_2$	607-57-8	211.216	nd (50% HOAc ace)	159.3				i H_2O; s ace, bz
8101	2-Nitro-9*H*-fluoren-9-one		$C_{13}H_7NO_3$	3096-52-4	225.200	ye nd or lf (HOAc)	224.3	sub			sl EtOH; s ace, sulf, HOAc
8102	5-Nitro-2-furaldehyde diacetate		$C_9H_9NO_7$	92-55-7	243.170		92.0				s chl
8103	2-Nitrofuran		$C_4H_3NO_3$	609-39-2	113.072	ye mcl cry (peth)	30	134^{123}, 84^{13}			s H_2O, EtOH, eth
8104	5-Nitro-2-furancarboxaldehyde		$C_5H_3NO_4$	698-63-5	141.083	pa ye (peth)	35.5	130^{10}			sl H_2O; s peth



3-Nitrobenzenesulfonic acid



4-Nitrobenzenesulfonic acid



2-Nitrobenzenesulfonyl chloride



3-Nitrobenzenesulfonyl chloride



4-Nitrobenzenesulfonyl chloride



5-Nitro-1*H*-benzimidazole



2-Nitrobenzoic acid



3-Nitrobenzoic acid



4-Nitrobenzoic acid



3-Nitrobenzoic acid, hydrazide



4-Nitrobenzoic acid, hydrazide



3-Nitrobenzonitrile



4-Nitrobenzonitrile



5-Nitro-1*H*-benzotriazole



2-Nitrobenzoyl chloride



3-Nitrobenzoyl chloride



4-Nitrobenzoyl chloride



2-Nitrobiphenyl



3-Nitrobiphenyl



4-Nitrobiphenyl



2-Nitro-1,1-bis(*p*-chlorophenyl)propane



1-Nitrobutane



2-Nitro-1-butanol


3-Nitro-2-butanol



6-Nitrochrysene


Nitrocyclohexane



1-Nitrodecane



N-Nitrodiethylamine



Nitroethane



2-Nitroethanol



Nitroethene



(2-Nitroethyl)benzene



Nitrofen


2-Nitro-9*H*-fluorene



2-Nitro-9*H*-fluoren-9-one



5-Nitro-2-furaldehyde diacetate



2-Nitrofuran



5-Nitro-2-furancarboxaldehyde


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8105	5-Nitro-2-furancarboxylic acid		$C_5H_3NO_5$	645-12-5	157.082	pa ye pl (w)	186	sub			s H_2O, EtOH, eth; sl ace, bz; i chl
8106	Nitrofurantoin		$C_8H_6N_4O_5$	67-20-9	238.158		263				
8107	Nitrofurazone	2-[(5-Nitro-2-furanyl) methylene] hydrazinecarboxamide	$C_6H_6N_4O_4$	59-87-0	198.137	pa ye nd	238 dec				i H_2O, eth; sl EtOH, DMSO; s alk
8108	Nitrogen mustard *N*-oxide hydrochloride	Mechlorethamine oxide hydrochloride	$C_5H_{12}Cl_3NO$	302-70-5	208.514	pr (ace)	110				s H_2O
8109	Nitroguanidine		$CH_4N_4O_2$	556-88-7	104.069	nd or pr (w)	239 dec				sl H_2O, EtOH; i eth; vs alk
8110	1-Nitrohexane		$C_6H_{13}NO_2$	646-14-0	131.173			193; 84^{21}	0.9396^{20}	1.4270^{20}	i H_2O; s EtOH, eth, ace, bz, alk
8111	3-Nitro-4-hydroxyphenylarsonic acid	Roxarsone	$C_6H_6AsNO_6$	121-19-7	263.037	ye nd or pl (w)	300				sl hot H_2O; i eth, EtOAc; vs MeOH, EtOH
8112	2-Nitro-1*H*-imidazole	Azomycin	$C_3H_3N_3O_2$	527-73-1	113.075	cry (MeOH)	287 dec				
8113	4-Nitro-1*H*-imidazole		$C_3H_3N_3O_2$	3034-38-6	113.075		303 dec				
8114	5-Nitro-1*H*-indazole		$C_7H_5N_3O_2$	5401-94-5	163.134	ye nd or col nd (al)	208				s EtOH, eth, bz; vs ace, HOAc; i lig
8115	6-Nitro-1*H*-indazole		$C_7H_5N_3O_2$	7597-18-4	163.134	nd (w, al, ace)	181 dec				s H_2O, EtOH, eth, bz; vs ace; i lig
8116	4-Nitro-1,3-isobenzofurandione		$C_8H_3NO_5$	641-70-3	193.114	nd (ace, al)	164				i H_2O; s EtOH, ace, HOAc; sl bz
8117	5-Nitro-1,3-isobenzofurandione		$C_8H_3NO_5$	5466-84-2	193.114		120.3	196^{8}			i H_2O, peth; s EtOH, ace; sl eth
8118	2-Nitroisobutane		$C_4H_9NO_2$	594-70-7	103.120		26.23	127.16	0.9501^{28}	1.4015^{20}	msc EtOH, eth, ace, bz; vs chl; i alk
8119	5-Nitro-1*H*-isoindole-1,3(2*H*)-dione		$C_8H_4N_2O_4$	89-40-7	192.129	col nd (w), ye lf (al-ace)	202				vs ace
8120	Nitromersol		$C_7H_5HgNO_3$	133-58-4	351.71						i H_2O; sl ace, EtOH; s alk
8121	*N*-Nitromethanamine		$CH_4N_2O_2$	598-57-2	76.055		38	82^{10}	1.2433^{49}	1.4616^{49}	vs H_2O, EtOH, bz, chl; s eth; sl peth
8122	Nitromethane		CH_3NO_2	75-52-5	61.041	liq	-28.38	101.19	1.1371^{20}	1.3817^{20}	s H_2O, EtOH, eth, ace, ctc, alk
8123	(Nitromethyl)benzene		$C_7H_7NO_2$	622-42-4	137.137	ye liq		226; 135^{25}	1.1596^{20}	1.5323^{20}	vs ace, eth
8124	Nitron		$C_{20}H_{16}N_4$	2218-94-2	312.368	ye lf (al), nd (chl)	189 dec				vs ace, bz, EtOH, chl
8125	1-Nitronaphthalene		$C_{10}H_7NO_2$	86-57-7	173.169	ye nd (al)	61	180^{14}	1.332^{20}		i H_2O; vs EtOH, eth, bz, chl, py
8126	2-Nitronaphthalene		$C_{10}H_7NO_2$	581-89-5	173.169	ye orth nd or pl (al)	79	314; 165^{15}			i H_2O; vs EtOH, eth
8127	1-Nitro-2-naphthol		$C_{10}H_7NO_3$	550-60-7	189.168	ye nd, lf or pr (al)	104	115$^{0.05}$			s H_2O, EtOH; vs eth; sl chl
8128	1-Nitrooctane		$C_8H_{17}NO_2$	629-37-8	159.227		15	208.5	0.9346^{20}	1.4322^{20}	
8129	1-Nitropentane		$C_5H_{11}NO_2$	628-05-7	117.147			172.5	0.9525^{20}	1.4175^{20}	s EtOH, eth, bz
8130	3-Nitropentane		$C_5H_{11}NO_2$	551-88-2	117.147			154	0.957^{0}		vs ace, eth, EtOH
8131	5-Nitro-1,10-phenanthroline		$C_{12}H_7N_3O_2$	4199-88-6	225.203		202.3				
8132	2-Nitrophenol		$C_6H_5NO_3$	88-75-5	139.109	ye nd or pr (eth, al)	44.8	216	1.2942^{40}	1.5723^{50}	sl H_2O; vs EtOH, eth, ace, bz, py
8133	3-Nitrophenol		$C_6H_5NO_3$	554-84-7	139.109	ye mcl (eth, aq Hcl)	96.8	194^{70}	1.2797^{100}		sl H_2O, DMSO; vs EtOH, eth, ace, bz
8134	4-Nitrophenol		$C_6H_5NO_3$	100-02-7	139.109	ye mcl pr (to)	113.6		1.479^{20}		sl H_2O; vs EtOH, eth, ace; s tol, py
8135	1-Nitro-2-phenoxybenzene		$C_{12}H_9NO_3$	2216-12-8	215.204	ye liq	<-20	235^{60}, 184^{8}	1.2539^{22}	1.575^{20}	vs bz, eth, EtOH, chl
8136	1-Nitro-4-phenoxybenzene		$C_{12}H_9NO_3$	620-88-2	215.204	pl (peth), MeOH)	61	320; 225^{30}			i H_2O; sl EtOH, ctc; s eth, bz
8137	*N*-(2-Nitrophenyl)acetamide		$C_8H_8N_2O_3$	552-32-9	180.161		94	100$^{0.1}$	1.419^{15}		s H_2O, EtOH, bz, chl, lig; vs eth
8138	*N*-(3-Nitrophenyl)acetamide		$C_8H_8N_2O_3$	122-28-1	180.161	wh lf (al)	155	100$^{0.0074}$			s H_2O, EtOH, chl; i eth; sl tfa



5-Nitro-2-furancarboxylic acid



Nitrofurantoin



Nitrofurazone



Nitrogen mustard *N*-oxide hydrochloride



Nitroguanidine



1-Nitrohexane



3-Nitro-4-hydroxyphenylarsonic acid



2-Nitro-1*H*-imidazole


4-Nitro-1*H*-imidazole



5-Nitro-1*H*-indazole



6-Nitro-1*H*-indazole


4-Nitro-1,3-isobenzofurandione


5-Nitro-1,3-isobenzofurandione



2-Nitroisobutane



5-Nitro-1*H*-isoindole-1,3(2*H*)-dione



Nitromersol



N-Nitromethanamine



Nitromethane



(Nitromethyl)benzene



Nitron



1-Nitronaphthalene



2-Nitronaphthalene



1-Nitro-2-naphthol



1-Nitrooctane



1-Nitropentane



3-Nitropentane



5-Nitro-1,10-phenanthroline



2-Nitrophenol



3-Nitrophenol


4-Nitrophenol



1-Nitro-2-phenoxybenzene



1-Nitro-4-phenoxybenzene



N-(2-Nitrophenyl)acetamide



N-(3-Nitrophenyl)acetamide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8139	*N*-(4-Nitrophenyl)acetamide		$C_8H_8N_2O_3$	104-04-1	180.161	ye pr (w)	216	$100^{0.008}$			sl H_2O, eth, chl; s EtOH, tfa, alk
8140	2-Nitrophenyl acetate		$C_8H_7NO_4$	610-69-5	181.147	nd or pr (lig)	40.5	dec 253; 141^{11}			s H_2O; vs EtOH, eth, ace, bz; sl lig
8141	4-Nitrophenyl acetate		$C_8H_7NO_4$	830-03-5	181.147	lf (dil al)	82.3				vs H_2O, bz; s EtOH, chl, lig
8142	2-Nitro-*N*-phenylaniline		$C_{12}H_{10}N_2O_2$	119-75-5	214.219		75.5	215^{15}	1.3660^{20}		i H_2O; s EtOH; sl ctc
8143	4-Nitro-*N*-phenylaniline		$C_{12}H_{10}N_2O_2$	836-30-6	214.219		135.3	211^{30}			i H_2O; vs EtOH; sl ace; s con sulf
8144	(4-Nitrophenyl)arsonic acid	Nitarsone	$C_6H_6AsNO_5$	98-72-6	247.038	lf or nd (w)	>310 dec				sl H_2O, EtOH, DMSO
8145	4-[(4-Nitrophenyl)azo]-1,3-benzenediol	Magneson	$C_{12}H_9N_3O_4$	74-39-5	259.217	red pow (al or MeOH)	200				i H_2O; sl EtOH, bz, HOAc, tol
8146	1-[(4-Nitrophenyl)azo]-2-naphthol		$C_{16}H_{11}N_3O_3$	6410-10-2	293.276	br-oran pl (to or bz)	257				vs bz, EtOH
8147	(3-Nitrophenyl)boronic acid		$C_6H_6BNO_4$	13331-27-6	166.928		274.5				
8148	1-(2-Nitrophenyl)ethanone	2-Nitroacetophenone	$C_8H_7NO_3$	577-59-3	165.147		28.5	178^{32}, 158^{16}	1.2370^{25}	1.5468^{20}	i H_2O; vs EtOH, eth, chl
8149	1-(3-Nitrophenyl)ethanone	3-Nitroacetophenone	$C_8H_7NO_3$	121-89-1	165.147	nd (al)	81	202; 167^{18}			vs H_2O, eth; sl EtOH, chl
8150	1-(4-Nitrophenyl)ethanone	4-Nitroacetophenone	$C_8H_7NO_3$	100-19-6	165.147	ye pr (al)	81.8	165^{5}			vs eth, EtOH
8151	2-Nitro-1-phenylethanone		$C_8H_7NO_3$	614-21-1	165.147		106	158^{16}, 142^{10}		1.5468^{30}	vs eth, EtOH
8152	(4-Nitrophenyl)hydrazine		$C_6H_7N_3O_2$	100-16-3	153.139	oran-red lf or nd (al)	158 dec				sl H_2O; s EtOH, eth, bz, chl, AcOEt
8153	(4-Nitrophenyl)phenylmethanone		$C_{13}H_9NO_3$	1144-74-7	227.215	nd or lf (al)	138		1.406^{9}		vs bz
8154	3-(4-Nitrophenyl)-1-phenyl-2-propen-1-one	Nitrochalcone	$C_{15}H_{11}NO_3$	1222-98-6	253.253	pa ye nd (al) pl (bz)	164				s EtOH, chl; i eth, lig
8155	4-Nitrophenyl phosphate	4-Nitrophenyl dihydrogen phosphate	$C_6H_6NO_6P$	330-13-2	219.089	ye-wh nd	155				i cold H_2O; s EtOH, chl, bz
8156	3-(2-Nitrophenyl)propanoic acid	2-Nitrobeazenepropanoic acid	$C_9H_9NO_4$	2001-32-3	195.172	ye cry	115				
8157	3-(4-Nitrophenyl)propanoic acid	4-Nitrobenzenepropanoic acid	$C_9H_9NO_4$	16642-79-8	195.172	nd (w)	163				
8158	3-(4-Nitrophenyl)-2-propenal	4-Nitrocinnamaldehyde	$C_9H_7NO_3$	1734-79-8	177.157	nd (w, al)	141.5				s H_2O, eth, ace, bz; vs EtOH
8159	3-(2-Nitrophenyl)-2-propynoic acid	*o*-Nitrophenylpropiolic acid	$C_9H_5NO_4$	530-85-8	191.141		≈157 dec; may explode				sl H_2O; vs EtOH, eth; i CS_2O
8160	1-Nitro-4-(phenylthio)benzene		$C_{12}H_9NO_2S$	952-97-6	231.270	pa ye mcl pr (lig)	56	288^{100}, 240^{25}			vs eth, EtOH
8161	(4-Nitrophenyl)urea	*p*-Nitrophenylurea	$C_7H_7N_3O_3$	556-10-5	181.149	pr (al), nd (dil al)	238				vs H_2O, EtOH
8162	*N*-Nitropiperidine		$C_5H_{10}N_2O_2$	7119-94-0	130.145	liq	-5.5	245; 121^{20}	1.1519^{26}	1.4954^{26}	
8163	1-Nitropropane		$C_3H_7NO_2$	108-03-2	89.094	liq	-108	131.1	0.9961^{25}	1.4018^{20}	sl H_2O; msc EtOH, eth; s chl
8164	2-Nitropropane		$C_3H_7NO_2$	79-46-9	89.094	liq	-91.3	120.2	0.9821^{25}	1.3944^{20}	sl H_2O; s chl
8165	3-Nitropropanoic acid		$C_3H_5NO_4$	504-88-1	119.077		62		1.59^{20}		vs H_2O, EtOH, eth; s chl; i lig
8166	2-Nitro-1-propanol		$C_3H_7NO_3$	2902-96-7	105.093			120^{32}, 100^{12}	1.1841^{25}	1.4379^{20}	s H_2O, EtOH, eth; sl chl
8167	1-Nitro-1-propene		$C_3H_5NO_2$	3156-70-5	87.078			60^{34}, 37^{10}	1.0661^{20}	1.4527^{20}	s eth, ace, chl
8168	2-Nitro-1-propene		$C_3H_5NO_2$	4749-28-4	87.078	ye-grn liq		52^{80}, 32^{30}	1.0559^{25}	1.4358^{20}	s eth, ace, chl
8169	5-Nitro-2-propoxyaniline		$C_9H_{12}N_2O_3$	553-79-7	196.202	oran (PrOH-peth)	49				vs EtOH
8170	*N*-(5-Nitro-2-propoxyphenyl) acetamide	5'-Nitro-2'-propoxyacetanilide	$C_{11}H_{14}N_2O_4$	553-20-8	238.240	cry (PrOH)	102.5				
8171	1-Nitropyrene		$C_{16}H_9NO_2$	5522-43-0	247.248	ye nd (MeCN)	152				
8172	5-Nitro-2-pyridinamine		$C_5H_5N_3O_2$	4214-76-0	139.113	ye lf (dil al)	188				sl H_2O, eth, bz, lig; s EtOH
8173	4-Nitropyridine		$C_5H_4N_2O_2$	1122-61-8	124.098	pl (aq al)	50				
8174	4-Nitropyridine 1-oxide		$C_5H_4N_2O_3$	1124-33-0	140.097		160.5				
8175	5-Nitropyrimidinamine		$C_4H_4N_4O_2$	3073-77-6	140.101	nd (al)	236.5				sl H_2O, DMSO; s EtOH, ace; i eth, bz
8176	5-Nitro-2,4(1*H*,3*H*)-pyrimidinedione	5-Nitrouracil	$C_4H_3N_3O_4$	611-08-5	157.085	gold nd (al)	>300 exp				sl H_2O; s EtOH
8177	5-Nitro-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	5-Nitrobarbituric acid	$C_4H_3N_3O_5$	480-68-2	173.084	pr, lf (w+3)	180.5				s H_2O, EtOH; i eth
8178	5-Nitroquinoline		$C_9H_6N_2O_2$	607-34-1	174.156	pl (w, al) nd (+w)	74	sub			sl H_2O, chl; s EtOH, bz



N-(4-Nitrophenyl)acetamide



2-Nitrophenyl acetate



4-Nitrophenyl acetate



2-Nitro-*N*-phenylaniline



4-Nitro-*N*-phenylaniline



(4-Nitrophenyl)arsonic acid



4-[(4-Nitrophenyl)azo]-1,3-benzenediol



1-[(4-Nitrophenyl)azo]-2-naphthol



(3-Nitrophenyl)boronic acid



1-(2-Nitrophenyl)ethanone



1-(3-Nitrophenyl)ethanone



1-(4-Nitrophenyl)ethanone



2-Nitro-1-phenylethanone



(4-Nitrophenyl)hydrazine



(4-Nitrophenyl)phenylmethanone



3-(4-Nitrophenyl)-1-phenyl-2-propen-1-one



4-Nitrophenyl phosphate



3-(2-Nitrophenyl)propanoic acid



3-(4-Nitrophenyl)propanoic acid



3-(4-Nitrophenyl)-2-propenal


3-(2-Nitrophenyl)-2-propynoic acid



1-Nitro-4-(phenylthio)benzene



(4-Nitrophenyl)urea



N-Nitropiperidine



1-Nitropropane



2-Nitropropane



3-Nitropropanoic acid



2-Nitro-1-propanol



1-Nitro-1-propene



2-Nitro-1-propene



5-Nitro-2-propoxyaniline



N-(5-Nitro-2-propoxyphenyl)acetamide



1-Nitropyrene



5-Nitro-2-pyridinamine



4-Nitropyridine


4-Nitropyridine 1-oxide



5-Nitropyrimidinamine



5-Nitro-2,4(1*H*,3*H*)-pyrimidinedione



5-Nitro-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione



5-Nitroquinoline


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8179	6-Nitroquinoline		$C_9H_6N_2O_2$	613-50-3	174.156	ye pl (HCl-HOAc)	153.5	$170^{0.2}$			s H_2O, EtOH; sl eth, chl; vs bz
8180	8-Nitroquinoline		$C_9H_6N_2O_2$	607-35-2	174.156	mcl pr (al)	91.5				sl H_2O, chl; s EtOH, eth, bz, acid
8181	4-Nitroquinoline 1-oxide		$C_9H_6N_2O_3$	56-57-5	190.155	ye nd, pl (ace)	154				
8182	5-Nitro-8-quinolinol	Nitroxoline	$C_9H_6N_2O_3$	4008-48-4	190.155		180				
8183	Nitrosobenzene		C_6H_5NO	586-96-9	107.110	orth or mcl (al-eth)	67	58^{18}			i H_2O; s EtOH, eth, bz, lig
8184	*N*-Nitrosodibutylamine	Dibutylnitrosamine	$C_8H_{18}N_2O$	924-16-3	158.241			105^{8}			
8185	*N*-Nitrosodiethanolamine	2,2'-(Nitrosoimino)ethanol	$C_4H_{10}N_2O_3$	1116-54-7	134.133	wh-ye oil		$125^{0.01}$		1.4849^{20}	
8186	*N*-Nitrosodiethylamine	Diethylnitrosamine	$C_4H_{10}N_2O$	55-18-5	102.134	ye oil		176.9	0.9422^{20}	1.4386^{20}	s H_2O, EtOH, eth; sl chl
8187	*N*-Nitrosodimethylamine	Dimethylnitrosamine	$C_2H_6N_2O$	62-75-9	74.081	ye liq		152	1.0048^{20}	1.4368^{20}	vs H_2O, EtOH, eth; s chl
8188	*p*-Nitroso-*N*,*N*-dimethylaniline		$C_8H_{10}N_2O$	138-89-6	150.177	grn pl (eth)	92.5		1.145^{20}		sl H_2O; s EtOH, eth, chl, $HCONH_2$
8189	*N*-Nitrosodiphenylamine	*N*,*N*-Diphenylnitrosamine	$C_{12}H_{10}N_2O$	86-30-6	198.219	ye pl(lig)	66.5				i H_2O; sl EtOH, chl; s bz
8190	4-(*N*-Nitrosomethylamino)-1-(3-pyridyl)-1-butanone	Ketone, 3-pyridyl-3-(*N*-methyl-*N*-nitrosamino)propyl	$C_{10}H_{13}N_3O_2$	64091-91-4	207.229		63				sl H_2O
8191	*N*-Nitrosomethylethylamine		$C_3H_8N_2O$	10595-95-6	88.108	ye liq		67^{40}			
8192	*N*-Nitroso-*N*-methylvinylamine	*N*-Methyl-*N*-nitrosoethenamine	$C_3H_6N_2O$	4549-40-0	86.092	ye liq		47			sl H_2O
8193	4-Nitrosomorpholine	*N*-Nitrosomorpholine	$C_4H_8N_2O_2$	59-89-2	116.119		29	225; 140^{25}			s H_2O
8194	2-Nitroso-1-naphthol		$C_{10}H_7NO_2$	132-53-6	173.169		157 dec				sl H_2O, eth, bz, chl; s EtOH, ace, HOAc
8195	1-Nitroso-2-naphthol	1-Nitroso-β-naphthol	$C_{10}H_7NO_2$	131-91-9	173.169	ye-br nd (peth)	109.5				vs bz, eth
8196	*N*-Nitrosonornicotine	*N*'-Nitroso-3-(2-pyrrolidinyl) pyridine	$C_9H_{11}N_3O$	16543-55-8	177.202			$155^{0.2}$			
8197	4-Nitrosophenol		$C_6H_5NO_2$	104-91-6	123.110	pa ye orth nd (ace, bz)	144 dec				sl H_2O; s EtOH, eth, ace, bz, dil alk
8198	4-Nitroso-*N*-phenylaniline	*p*-Nitrosodiphenylamine	$C_{12}H_{10}N_2O$	156-10-5	198.219		143				sl H_2O, lig; vs EtOH, eth, bz
8199	*N*-Nitrosopiperidine	1-Nitrosopiperidine	$C_5H_{10}N_2O$	100-75-4	114.145	pa ye		219; 109^{20}	1.0631^{18}	1.4933^{18}	s H_2O, HCl
8200	*N*-Nitroso-*N*-propyl-1-propanamine	*N*-Nitrosodipropylamine	$C_6H_{14}N_2O$	621-64-7	130.187	gold		206; 113^{40}	0.9163^{20}	1.4437^{20}	sl H_2O; msc EtOH, eth
8201	*N*-Nitrosopyrrolidine		$C_4H_8N_2O$	930-55-2	100.119			214	1.085^{25}	1.4880^{25}	
8202	5-Nitro-2-thiazolamine	2-Amino-5-nitrothiazole	$C_3H_3N_3O_2S$	121-66-4	145.140	oran-ye pow	202 dec				
8203	*N*-(5-Nitro-2-thiazolyl)acetamide	Aminitrozole	$C_5H_5N_3O_3S$	140-40-9	187.177	nd (al), pl (HOAc)	264.5				s alk
8204	4-Nitrothioanisole		$C_7H_7NO_2S$	701-57-5	169.202		72	137^{2}	1.2391^{80}	1.6401^{20}	i H_2O; s ace, bz
8205	2-Nitrothiophene		$C_4H_3NO_2S$	609-40-5	129.138	lt ye mcl nd (peth)	46.5	224.5	1.3644^{43}		i H_2O; vs EtOH; s alk; sl peth
8206	2-Nitrotoluene		$C_7H_7NO_2$	88-72-2	137.137	liq	-10.4	222	1.1611^{19}	1.5450^{20}	i H_2O; msc EtOH, eth; s ctc
8207	3-Nitrotoluene		$C_7H_7NO_2$	99-08-1	137.137	pa ye	15.5	232	1.1581^{20}	1.5466^{20}	i H_2O; s EtOH, bz, ctc; msc eth
8208	4-Nitrotoluene		$C_7H_7NO_2$	99-99-0	137.137	orth cry (al, eth)	51.63	238.3	1.1038^{75}		i H_2O; s EtOH; vs eth, ace, bz, chl
8209	1-Nitro-2-(trifluoromethyl)benzene		$C_7H_4F_3NO_2$	384-22-5	191.108	cry (al)	32.5	217; 105^{20}			i H_2O; vs EtOH, HOAc, bz; sl ctc
8210	1-Nitro-3-(trifluoromethyl)benzene		$C_7H_4F_3NO_2$	98-46-4	191.108	liq	-2.4	202.8; 103^{40}	1.4357^{15}	1.4719^{20}	i H_2O; s EtOH, eth; sl ctc
8211	Nitrourea		$CH_3N_3O_3$	556-89-8	105.053	pl (al-peth)	158 dec				vs ace, EtOH
8212	*trans*-(2-Nitrovinyl)benzene		$C_8H_7NO_2$	5153-67-3	149.148	ye pr (peth, al)	60	255			i H_2O; s EtOH, ace; vs eth, chl, CS_2
8213	Nivalenol		$C_{15}H_{20}O_7$	23282-20-4	312.316	cry (MeOH)	224 dec				sl H_2O; s EtOH, MeOH
8214	Nizatidine		$C_{12}H_{21}N_5O_2S_2$	76963-41-2	331.458	cry (EtOH/AcOEt)	131				sl H_2O; s MeOH; vs chl; i bz, eth
8215	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl		$C_{12}HCl_9$	52663-77-1	464.213	cry	180.5				i H_2O
8216	Nonacontane		$C_{90}H_{182}$	7667-51-8	1264.408			612^{200}			



6-Nitroquinoline



8-Nitroquinoline



4-Nitroquinoline 1-oxide


5-Nitro-8-quinolinol



Nitrosobenzene



N-Nitrosodibutylamine



N-Nitrosodiethanolamine


N-Nitrosodiethylamine


N-Nitrosodimethylamine



p-Nitroso-*N*,*N*-dimethylaniline



N-Nitrosodiphenylamine



4-(*N*-Nitrosomethylamino)-1-(3-pyridyl)-1-butanone



N-Nitrosomethylethylamine



N-Nitroso-*N*-methylvinylamine



4-Nitrosomorpholine



2-Nitroso-1-naphthol



1-Nitroso-2-naphthol



N-Nitrosonornicotine



4-Nitrosophenol



4-Nitroso-*N*-phenylaniline



N-Nitrosopiperidine



N-Nitroso-*N*-propyl-1-propanamine



N-Nitrosopyrrolidine



5-Nitro-2-thiazolamine



N-(5-Nitro-2-thiazolyl)acetamide



4-Nitrothioanisole



2-Nitrothiophene



2-Nitrotoluene



3-Nitrotoluene



4-Nitrotoluene



1-Nitro-2-(trifluoromethyl)benzene



1-Nitro-3-(trifluoromethyl)benzene



Nitrourea


trans-(2-Nitrovinyl)benzene



Nivalenol



Nizatidine



2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl



Nonacontane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8217	Nonacosane		$C_{29}H_{60}$	630-03-5	408.786	orth cry (peth)	63.7	440.8	0.8083^{20}	1.4529^{20}	i H_2O; vs EtOH, eth, ace; s bz; sl chl
8218	Nonadecafluorodecanoic acid		$C_{10}HF_{19}O_2$	335-76-2	514.084			219			
8219	Nonadecane		$C_{19}H_{40}$	629-92-5	268.521	wax	32.0	329.9	0.7855^{20}	1.4409^{20}	i H_2O; sl EtOH; s eth, ace, ctc
8220	Nonadecanoic acid		$C_{19}H_{38}O_2$	646-30-0	298.504	lf (al)	69.4	297^{100}, 228^{10}	0.8468^{70}		i H_2O; vs EtOH, eth, bz, chl, lig
8221	1-Nonadecanol		$C_{19}H_{40}O$	1454-84-8	284.520	cry (ace)	61.7	345; $166^{0.3}$		1.4328^{75}	s eth, ace
8222	2-Nonadecanone		$C_{19}H_{38}O$	629-66-3	282.504	pr (al)	57	266^{110}, 165^{2}	0.8108^{56}		i H_2O; sl EtOH; s ace, bz; vs eth, ctc
8223	10-Nonadecanone		$C_{19}H_{38}O$	504-57-4	282.504	lf(al)	65.5	>350; $156^{1.1}$			i H_2O; sl EtOH; s eth, ace, lig; vs bz
8224	1-Nonadecene		$C_{19}H_{38}$	18435-45-5	266.505		23.4	329.0	0.7886^{25}	1.4445^{25}	
8225	Nonadecylbenzene		$C_{25}H_{44}$	29136-19-4	344.617		40	419	0.8545^{20}	1.4807^{20}	
8226	*trans,trans*-2,4-Nonadienal		$C_9H_{14}O$	5910-87-2	138.206			98^{10}	0.862^{25}	1.5207^{20}	
8227	1,8-Nonadiene		C_9H_{16}	4900-30-5	124.223			142.5	0.7511^{20}	1.4302^{20}	
8228	2,6-Nonadien-1-ol		$C_9H_{16}O$	7786-44-9	140.222			108^{24}, 98^{11}	0.8604^{25}	1.4598^{25}	
8229	1,8-Nonadiyne		C_9H_{12}	2396-65-8	120.191	liq	-27.3	162	0.8158^{20}	1.4490^{20}	i H_2O; s eth, ace
8230	Nonanal	Nonaldehyde	$C_9H_{18}O$	124-19-6	142.238		-19.3	191	0.8264^{22}	1.4273^{20}	s eth, chl
8231	Nonane		C_9H_{20}	111-84-2	128.255	liq	-53.46	150.82	0.7192^{20}	1.4058^{20}	i H_2O; vs EtOH, eth; msc ace, bz, hp
8232	Nonanedioic acid	Azelaic acid	$C_9H_{16}O_4$	123-99-9	188.221	lf or nd	106.5	287^{100}, 225^{10}	1.225^{25}	1.4303^{111}	sl H_2O, eth, bz, DMSO; s EtOH
8233	1,9-Nonanediol		$C_9H_{20}O_2$	3937-56-2	160.254	cry (bz)	45.8	173^{20}, 150^{3}			sl H_2O; vs EtOH, eth; s bz; i lig
8234	Nonanedioyl dichloride		$C_9H_{14}Cl_2O_2$	123-98-8	225.112			166^{18}	1.143	1.4680^{20}	s eth; vs bz
8235	Nonanenitrile		$C_9H_{17}N$	2243-27-8	139.238	liq	-34.2	224.4	0.8178^{20}	1.4255^{20}	i H_2O; s EtOH, eth; sl ctc
8236	1-Nonanethiol	Nonyl mercaptan	$C_9H_{20}S$	1455-21-6	160.320	liq	-20.1	220	0.842^{25}	1.4548^{20}	
8237	Nonanoic acid	Pelargonic acid	$C_9H_{18}O_2$	112-05-0	158.238		12.4	254.5	0.9052^{20}	1.4343^{19}	i H_2O; s EtOH, eth, chl
8238	1-Nonanol	Nonyl alcohol	$C_9H_{20}O$	143-08-8	144.254	liq	-5	213.37	0.8280^{20}	1.4333^{20}	i H_2O; s EtOH, eth; sl ctc
8239	2-Nonanol, (±)		$C_9H_{20}O$	74683-66-2	144.254	liq	-35	193.5	0.8471^{20}	1.4353^{20}	i H_2O; vs eth, EtOH
8240	3-Nonanol, (±)		$C_9H_{20}O$	74742-08-8	144.254		22	195; 93^{18}	0.8250^{20}	1.4289^{20}	i H_2O; s EtOH, eth
8241	4-Nonanol		$C_9H_{20}O$	52708-03-9	144.254			192.5; 94^{18}	0.8282^{20}	1.4197^{20}	i H_2O; s EtOH, eth
8242	5-Nonanol	Dibutylcarbinol	$C_9H_{20}O$	623-93-8	144.254		5.6	193; 97^{20}	0.8220^{20}	1.4289^{20}	i H_2O; s EtOH
8243	2-Nonanone	Heptyl methyl ketone	$C_9H_{18}O$	821-55-6	142.238	liq	-7.5	195.3	0.8208^{20}	1.4210^{20}	i H_2O; s EtOH, eth, bz; vs ace, chl
8244	3-Nonanone	Ethyl hexyl ketone	$C_9H_{18}O$	925-78-0	142.238	liq	-8	190; 86^{20}	0.8241^{20}	1.4208^{20}	i H_2O; s EtOH, eth, bz, chl; vs ace
8245	4-Nonanone	Pentyl propyl ketone	$C_9H_{18}O$	4485-09-0	142.238			187.5	0.8190^{25}	1.4189^{20}	i H_2O; s EtOH, eth, chl; vs ace
8246	5-Nonanone	Dibutyl ketone	$C_9H_{18}O$	502-56-7	142.238	liq	-3.8	188.45	0.8217^{20}	1.4195^{20}	i H_2O; s EtOH; vs eth, chl
8247	Nonanoyl chloride		$C_9H_{17}ClO$	764-85-2	176.683	liq	-60.5	215.3	0.9463^{15}		s eth, ace
8248	*trans*-2-Nonenal		$C_9H_{16}O$	18829-56-6	140.222	liq		101^{16}, 89^{12}	0.846	1.4531^{20}	
8249	1-Nonene		C_9H_{18}	124-11-8	126.239	liq	-81.3	146.9	0.7253^{25}	1.4257^{20}	
8250	2-Nonenoic acid		$C_9H_{16}O_2$	3760-11-0	156.222			173^{20}, 136^{5}			
8251	3-Nonenoic acid		$C_9H_{16}O_2$	4124-88-3	156.222		-4.4	156^{18}, 106^{1}	0.9254^{20}	1.4454^{25}	
8252	1-Nonen-3-ol	1-Vinylheptanol	$C_9H_{18}O$	21964-44-3	142.238			193.5	0.824^{21}	1.4382^{15}	
8253	Nonyl acetate		$C_{11}H_{22}O_2$	143-13-5	186.292	liq	-26	210	0.8785^{15}	1.426^{20}	
8254	Nonylamine	1-Nonanamine	$C_9H_{21}N$	112-20-9	143.270	liq	-1	202.2	0.7886^{20}	1.4336^{20}	sl H_2O, chl; s EtOH, eth
8255	Nonylbenzene		$C_{15}H_{24}$	1081-77-2	204.352	liq	-24	280.5	0.8584^{20}	1.4816^{20}	
8256	Nonylcyclohexane		$C_{15}H_{30}$	2883-02-5	210.399	liq	-10	282	0.8163^{20}	1.4519^{20}	
8257	Nonylcyclopentane		$C_{14}H_{28}$	2882-98-6	196.372	liq	-29	262	0.8081^{20}	1.4467^{20}	vs ace, bz, eth, EtOH
8258	Nonyl formate		$C_{10}H_{20}O_2$	5451-92-3	172.265	liq	-33	214	0.86	1.4216^{20}	
8259	1-Nonylnaphthalene		$C_{19}H_{26}$	26438-26-6	254.409		8	366	0.9371^{20}	1.5477^{20}	
8260	4-Nonylphenol		$C_{15}H_{24}O$	104-40-5	220.351	visc ye liq	42	≈295; 180^{10}	0.950^{20}	1.513^{20}	i H_2O; s bz, ctc, hp
8261	1-Nonyne	Heptylacetylene	C_9H_{16}	3452-09-3	124.223	liq	-50	150.8	0.7658^{20}	1.4217^{20}	i H_2O; s eth, bz, ctc



Nonacosane



Nonadecafluorodecanoic acid



Nonadecane



Nonadecanoic acid



1-Nonadecanol



2-Nonadecanone



10-Nonadecanone



1-Nonadecene



Nonadecylbenzene


trans,trans-2,4-Nonadienal



1,8-Nonadiene



2,6-Nonadien-1-ol



1,8-Nonadiyne



Nonanal


Nonane



Nonanedioic acid



1,9-Nonanediol



Nonanedioyl dichloride



Nonanenitrile



1-Nonanethiol



Nonanoic acid



1-Nonanol



2-Nonanol, (±)



3-Nonanol, (±)



4-Nonanol



5-Nonanol



2-Nonanone


3-Nonanone



4-Nonanone



5-Nonanone



Nonanoyl chloride



trans-2-Nonenal



1-Nonene



2-Nonenoic acid



3-Nonenoic acid



1-Nonen-3-ol



Nonyl acetate



Nonylamine



Nonylbenzene



Nonylcyclohexane


Nonylcyclopentane



Nonyl formate


1-Nonylnaphthalene



4-Nonylphenol



1-Nonyne


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8262	Norbormide		$C_{33}H_{25}N_3O_3$	991-42-4	511.570	cry (eth)	194				
8263	2,5-Norbornadiene	Bicyclo[2.2.1]hepta-2,5-diene	C_7H_8	121-46-0	92.139	liq	-19.1	89.5	0.9064^{20}	1.4702^{20}	i H_2O; s EtOH, eth, ace, bz; msc tol
8264	5-Norbornene-2,3-dicarboxylic acid anhydride		$C_9H_8O_3$	826-62-0	164.158		166				
8265	5-Norbornene-2-methylolacrylate		$C_{11}H_{14}O_2$	95-39-6	178.228	col liq		104	1.029^{25}		s os
8266	24-Norcholan-23-oic acid, (5β)	Norcholanic acid	$C_{23}H_{38}O_2$	511-18-2	346.547	nd(HOAc)	177				
8267	Nordazepam	7-Chloro-1,3-dihydro-5-phenyl-2*H*-1,4-benzodiazepin-2-one	$C_{15}H_{11}ClN_2O$	1088-11-5	270.713		216.5				
8268	Nordihydroguaiaretic acid		$C_{18}H_{22}O_4$	500-38-9	302.366	nd(w, al, HOAc)	185.5				sl H_2O; s EtOH, eth, ace, alk; i bz
8269	Norea		$C_{13}H_{22}N_2O$	18530-56-8	222.326		177				
8270	Norepinephrine	Noradrenaline	$C_8H_{11}NO_3$	51-41-2	169.178		217 dec				sl H_2O, EtOH, eth; vs alk, dil HCl
8271	Norethisterone	19-Norpregn-4-en-20-yn-3-one, 17-hydroxy-, (17 α)-	$C_{20}H_{26}O_2$	68-22-4	298.419	cry	204				
8272	Norethynodrel		$C_{20}H_{26}O_2$	68-23-5	298.419	cry (MeOH)	170				
8273	Norflurazon		$C_{12}H_9ClF_3N_3O$	27314-13-2	303.666		184				
8274	Norhyoscyamine		$C_{16}H_{21}NO_3$	537-29-1	275.343	nd	140.5				vs EtOH, chl
8275	*DL*-Norleucine	2-Aminohexanoic acid, (*DL*)	$C_6H_{13}NO_2$	616-06-8	131.173	lf(w)	327 dec		1.172^{25}		s H_2O; sl EtOH; i eth
8276	*L*-Norleucine	2-Aminohexanoic acid, (*L*)	$C_6H_{13}NO_2$	327-57-1	131.173		301 dec				sl H_2O
8277	Normorphine		$C_{16}H_{17}NO_3$	466-97-7	271.311		273				
8278	Norplant	Norgestrel, (-)	$C_{21}H_{28}O_2$	797-63-7	312.446	cry (MeOH)	206				
8279	19-Nortestosterone phenylpropionate	Nandrolone phenpropionate	$C_{27}H_{34}O_3$	62-90-8	406.557	cry	95				
8280	Nortriptyline hydrochloride		$C_{19}H_{22}ClN$	894-71-3	299.838	cry (eth)	214				s H_2O, EtOH; i bz, eth, ace
8281	*DL*-Norvaline	2-Aminopentanoic acid, (±)	$C_5H_{11}NO_2$	760-78-1	117.147	lf(al, w)	303	sub			s H_2O; i EtOH, eth, chl, AcOEt, lig
8282	*L*-Norvaline	2-Aminopentanoic acid, (*S*)	$C_5H_{11}NO_2$	6600-40-4	117.147	cry (dil al)	307				s H_2O
8283	Noscapine		$C_{22}H_{23}NO_7$	128-62-1	413.421	pr or nd (al)	176				i H_2O; s EtOH, bz, chl; sl eth; vs ace
8284	Novobiocin	Streptonivicin	$C_{31}H_{36}N_2O_{11}$	303-81-1	612.624	wh-ye orth cry	154		1.3448		i H_2O; s EtOH, EtOAc, ace, py
8285	Nuarimol		$C_{17}H_{12}ClFN_2O$	63284-71-9	314.740		126				
8286	Nylidrin	Buphenine	$C_{19}H_{25}NO_2$	447-41-6	299.408	cry (MeOH)	111				
8287	Ochratoxin A		$C_{20}H_{18}ClNO_6$	303-47-9	403.813	cry (xyl)	169				
8288	Ochratoxin B		$C_{20}H_{19}NO_6$	4825-86-9	369.368	cry (MeOH)	221				
8289	Ochratoxin C		$C_{22}H_{22}ClNO_6$	4865-85-4	431.866	amorp solid					
8290	Octacaine	3-(Diethylamino)-*N*-phenylbutanamide	$C_{14}H_{22}N_2O$	13912-77-1	234.337	cry	47	200^{1}			vs EtOH, bz, eth
8291	2,2',3,3',5,5',6,6'-Octachlorobiphenyl		$C_{12}H_2Cl_8$	2136-99-4	429.768	cry	161				i H_2O
8292	Octachlorocyclopentene	Perchlorocyclopentene	C_5Cl_8	706-78-5	343.678	nd	40	283	1.8200^{50}	1.5660^{50}	i H_2O; vs EtOH
8293	Octachlorodibenzo-*p*-dioxin		$C_{12}Cl_8O_2$	3268-87-9	459.751	nd	331				
8294	Octachloronaphthalene	Perchloronaphthalene	$C_{10}Cl_8$	2234-13-1	403.731	nd (bz-CCl_4)	197.5	441^{7}, $248^{0.5}$			sl EtOH; vs bz, chl, lig
8295	Octachlorostyrene	Perchlorostyrene	C_8Cl_8	29082-74-4	379.710	cry (ace/ EtOH)	99				
8296	Octacontane		$C_{80}H_{162}$	7667-88-1	1124.142		112	672			
8297	Octacosane		$C_{28}H_{58}$	630-02-4	394.761	mcl or orth (bz-al)	61.1	431.6	0.8067^{20}	1.4330^{70}	i H_2O; msc ace; s bz, chl
8298	Octacosanoic acid	Montanic acid	$C_{28}H_{56}O_2$	506-48-9	424.744		90.9		0.8191^{100}	1.4313^{100}	vs bz, chl
8299	1-Octacosanol	Montanyl alcohol	$C_{28}H_{58}O$	557-61-9	410.760	cry (ace, peth)	83.4	200^{1}			i H_2O; s CS_2
8300	*trans, trans*-9,12-Octadecadienoic acid	Linolelaidic acid	$C_{18}H_{32}O_2$	506-21-8	280.446	cry (MeOH)	28.5	$181^{0.8}$			sl H_2O; s ace, hx
8301	Octadecahydrochrysene		$C_{18}H_{30}$	2090-14-4	246.431		115	353			vs EtOH
8302	Octadecamethyloctasiloxane		$C_{18}H_{54}O_7Si_8$	556-69-4	607.302		-63	186^{20}, 153^{5}	0.913^{25}	1.3970^{20}	vs bz, peth, lig
8303	Octadecanamide		$C_{18}H_{37}NO$	124-26-5	283.493	lf (al)	109	250^{12}			vs eth, chl
8304	Octadecane		$C_{18}H_{38}$	593-45-3	254.495	nd (al, eth-MeOH)	28.2	316.3	0.7768^{28}	1.4390^{20}	i H_2O; sl EtOH; s eth, ace, chl, lig
8305	Octadecanenitrile		$C_{18}H_{35}N$	638-65-3	265.478		41	362	0.8325^{20}	1.4389^{45}	i H_2O; s EtOH; vs eth, ace, chl
8306	1-Octadecanethiol	Stearyl mercaptan	$C_{18}H_{38}S$	2885-00-9	286.560		30	207^{11}	0.8475^{20}	1.4645^{20}	vs eth



Norbormide



2,5-Norbornadiene



5-Norbornene-2,3-dicarboxylic acid anhydride



5-Norbornene-2-methylolacrylate



24-Norcholan-23-oic acid, (5β)



Nordazepam



Nordihydroguaiaretic acid



Norea



Norepinephrine



Norethisterone



Norethynodrel



Norflurazon



Norhyoscyamine



DL-Norleucine



L-Norleucine



Normorphine



Norplant



19-Nortestosterone phenylpropionate



Nortriptyline hydrochloride



DL-Norvaline



L-Norvaline



Noscapine



Novobiocin



Nuarimol



Nylidrin



Ochratoxin A



Ochratoxin B



Ochratoxin C



Octacaine



2,2',3,3',5,5',6,6'-Octachlorobiphenyl



Octachlorocyclopentene



Octachlorodibenzo-*p*-dioxin



Octachloronaphthalene



Octachlorostyrene



Octacontane



Octacosane



Octacosanoic acid



1-Octacosanol



trans, trans-9,12-Octadecadienoic acid



Octadecahydrochrysene


Octadecamethyloctasiloxane



Octadecanamide



Octadecane



Octadecanenitrile



1-Octadecanethiol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8307	1-Octadecanol	Stearyl alcohol	$C_{18}H_{38}O$	112-92-5	270.494	lf (al)	57.9	335; 210.5^{15}	0.8124^{59}		i H_2O; s EtOH, eth; sl ace, bz
8308	Octadecanoyl chloride		$C_{18}H_{35}ClO$	112-76-5	302.923		23	215^{15}	0.8969^{0}	1.4523^{24}	sl EtOH
8309	*trans,cis,trans*-9,11,13-Octadecatrienoic acid	*cis*-Eleostearic acid	$C_{18}H_{30}O_2$	506-23-0	278.430	nd (al)	49	235^{12} dec, 170^{1}	0.9028^{50}	1.5112^{50}	vs eth, EtOH
8310	*trans,trans,trans*-9,11,13-Octadecatrienoic acid	*trans*-Eleostearic acid	$C_{18}H_{30}O_2$	544-73-0	278.430	lf (al)	71.5	188^{1}	0.8839^{80}	1.5000^{80}	vs EtOH
8311	*cis*-9-Octadecenamide		$C_{18}H_{35}NO$	301-02-0	281.477		76				vs eth
8312	1-Octadecene		$C_{18}H_{36}$	112-88-9	252.479		17.5	179^{15}, 145^{8}	0.7891^{20}	1.4448^{20}	i H_2O; s ace, ctc
8313	*cis*-9-Octadecenenitrile		$C_{18}H_{33}N$	112-91-4	263.462		-1	dec 332	0.847^{17}	1.4566^{20}	vs EtOH
8314	*cis*-6-Octadecenoic acid	Petroselinic acid	$C_{18}H_{34}O_2$	593-39-5	282.462	lf	29.8	238^{18}	0.8700^{40}	1.4533^{40}	s eth; sl hp, MeOH
8315	*trans*-11-Octadecenoic acid	Vaccenic acid	$C_{18}H_{34}O_2$	693-72-1	282.462		44			1.4499^{60}	s ace
8316	*cis*-9-Octadecen-1-ol	Oleyl alcohol	$C_{18}H_{36}O$	143-28-2	268.478		6.5	207^{15}	0.8489^{20}	1.4606^{20}	i H_2O; s EtOH, eth; sl ctc
8317	*cis*-9-Octadecenylamine	Oleylamine	$C_{18}H_{37}N$	112-90-3	267.494	oil	25	147^{2}			
8318	Octadecyl acetate		$C_{20}H_{40}O_2$	822-23-1	312.531		34.5	208^{9}	0.8510^{30}		vs EtOH
8319	Octadecyl acrylate	Stearyl 2-propenoate	$C_{21}H_{40}O_2$	4813-57-4	324.542						s ctc, CS_2
8320	Octadecylamine	1-Octadecanamine	$C_{18}H_{39}N$	124-30-1	269.510	cry (w)	52.9	346.8	0.8618^{20}	1.4522^{20}	i H_2O; s EtOH, eth, bz; sl ace
8321	Octadecylbenzene		$C_{24}H_{42}$	4445-07-2	330.590		36	400	0.85^{36}	1.479^{36}	
8322	Octadecylcyclohexane		$C_{24}H_{48}$	4445-06-1	336.638		41.6	409; 175^{1}	0.8300^{20}	1.4610^{20}	
8323	Octadecyl 3-(3,5-di-*tert*-butyl-4-hydroxyphenyl)propanoate	Irganox 1076	$C_{35}H_{62}O_3$	2082-79-3	530.865	cry (MeOH/ AcOEt)	50				
8324	Octadecyl isocyanate	1-Isocyanatooctadecane	$C_{19}H_{37}NO$	112-96-9	295.503		15.5	172^{5}			
8325	Octadecyl methacrylate	Stearyl methacrylate	$C_{22}H_{42}O_2$	32360-05-7	338.567			195^{6}	0.880^{25}	1.429^{25}	
8326	Octadecyl octadecanoate	Octadecyl stearate	$C_{36}H_{72}O_2$	2778-96-3	536.956	cry (EtOH)	60				
8327	3-(Octadecyloxy)-1,2-propanediol	Batyl alcohol	$C_{21}H_{44}O_3$	544-62-7	344.572		70.5	217^{2}			vs eth
8328	Octadecyl vinyl ether	1-(Ethenyloxy)octadecane	$C_{20}H_{40}O$	930-02-9	296.531		30	182^{3}	0.8138^{40}		sl chl
8329	1,7-Octadiene		C_8H_{14}	3710-30-3	110.197			115.5	0.734^{20}	1.4245^{20}	
8330	1,7-Octadiyne		C_8H_{10}	871-84-1	106.165			135.5; 59^{35}	0.8169^{21}	1.4521^{18}	s eth
8331	2,2,3,3,4,4,5,5-Octafluoro-1-pentanol		$C_5H_4F_8O$	355-80-6	232.072			140.5	1.6647^{20}	1.3178^{20}	
8332	1,2,3,4,5,6,7,8-Octahydroanthracene		$C_{14}H_{18}$	1079-71-6	186.293	pl (al)	78	294	0.9703^{80}	1.5372^{80}	i H_2O; s EtOH, HOAc; vs bz; sl ctc
8333	Octahydroazocine		$C_7H_{15}N$	1121-92-2	113.201		29	52^{15}	0.896^{25}	1.4720^{20}	
8334	Octahydroindene		C_9H_{16}	496-10-6	124.223	liq	-53	167	0.876^{25}	1.4702^{20}	
8335	Octahydroindolizine		$C_8H_{15}N$	13618-93-4	125.212			75^{43}	0.9074^{10}	1.4748	vs eth, EtOH
8336	*trans*-Octahydro-1(2*H*)-naphthalenone		$C_{10}H_{16}O$	21370-71-8	152.233		33	122^{20}	0.986^{20}	1.4849^{21}	
8337	1,2,3,4,5,6,7,8-Octahydrophenanthrene		$C_{14}H_{18}$	5325-97-3	186.293		16.7	295	1.026^{20}	1.5569^{17}	i H_2O; s ace, bz, CS_2, HOAc
8338	*trans*-Octahydro-2*H*-quinolizine-1-methanol, (1*R*)	Lupinine	$C_{10}H_{19}NO$	486-70-4	169.264	orth (peth)	70	270			s H_2O, EtOH, eth, bz, chl; sl peth
8339	2,2,4,4,6,6,8,8-Octamethylcyclotetrasilazane		$C_8H_{28}N_4Si_4$	1020-84-4	292.677		97				
8340	Octamethylcyclotetrasiloxane		$C_8H_{24}O_4Si_4$	556-67-2	296.617		17.5	175.8	0.9561^{20}	1.3968^{20}	i H_2O; s ctc
8341	1,1,1,3,5,7,7,7-Octamethyltetrasiloxane		$C_8H_{26}O_3Si_4$	16066-09-4	282.632			170	0.8559^{20}	1.3854^{20}	
8342	Octamethyltrisiloxane		$C_8H_{24}O_2Si_3$	107-51-7	236.533	liq	-80	153; 51^{17}	0.8200^{20}	1.3840^{20}	sl EtOH; s bz, peth
8343	Octanal	Caprylic aldehyde	$C_8H_{16}O$	124-13-0	128.212			171	0.8211^{20}	1.4217^{20}	vs ace, bz, eth, EtOH
8344	Octanamide		$C_8H_{17}NO$	629-01-6	143.227	lf, pl	108	239	0.8450^{110}		sl H_2O, bz, chl; vs EtOH; s eth, ace
8345	2-Octanamine, (±)		$C_8H_{19}N$	44855-57-4	129.244		97	164	0.7744^{20}	1.4232^{25}	vs eth, EtOH
8346	Octane		C_8H_{18}	111-65-9	114.229	liq	-56.82	125.67	0.6986^{25}	1.3944^{25}	i H_2O; s eth; msc EtOH, ace, bz
8347	1,8-Octanediamine		$C_8H_{20}N_2$	373-44-4	144.258	pl	51.64	225			vs H_2O, eth, EtOH
8348	Octanedinitrile	Suberonitrile	$C_8H_{12}N_2$	629-40-3	136.194		-1.8	185^{15}	0.954^{25}	1.4436^{20}	
8349	Octanedioic acid	Suberic acid	$C_8H_{14}O_4$	505-48-6	174.195	lo nd or pl (w)	144	219^{20}			i H_2O; msc eth, bz; sl DMSO
8350	1,2-Octanediol		$C_8H_{18}O_2$	1117-86-8	146.228		30	131^{10}, 104$^{0.2}$			
8351	1,8-Octanediol		$C_8H_{18}O_2$	629-41-4	146.228	nd (bz-lig), pr	63	172^{20}			sl H_2O, eth, chl, lig; vs EtOH; s bz
8352	Octanenitrile	Caprylnitrile	$C_8H_{15}N$	124-12-9	125.212	liq	-45.6	205.25	0.8136^{20}	1.4203^{20}	vs eth
8353	1-Octanethiol	Octyl mercaptan	$C_8H_{18}S$	111-88-6	146.294	liq	-49.2	199.1	0.8433^{20}	1.4540^{20}	s EtOH; sl ctc



1-Octadecanol



Octadecanoyl chloride



trans,cis,trans-9,11,13-Octadecatrienoic acid



trans,trans,trans-9,11,13-Octadecatrienoic acid



cis-9-Octadecenamide



1-Octadecene



cis-9-Octadecenenitrile



cis-6-Octadecenoic acid



trans-11-Octadecenoic acid



cis-9-Octadecen-1-ol



cis-9-Octadecenylamine



Octadecyl acetate



Octadecyl acrylate



Octadecylamine



Octadecylbenzene



Octadecylcyclohexane



Octadecyl 3-(3,5-di-*tert*-butyl-4-hydroxyphenyl)propanoate



Octadecyl isocyanate



Octadecyl methacrylate



Octadecyl octadecanoate



3-(Octadecyloxy)-1,2-propanediol



Octadecyl vinyl ether



1,7-Octadiene



1,7-Octadiyne



2,2,3,3,4,4,5,5-Octafluoro-1-pentanol



1,2,3,4,5,6,7,8-Octahydroanthracene



Octahydroazocine



Octahydroindene



Octahydroindolizine



trans-Octahydro-1(2*H*)-naphthalenone



1,2,3,4,5,6,7,8-Octahydrophenanthrene



trans-Octahydro-2*H*-quinolizine-1-methanol, (1*R*)



2,2,4,4,6,6,8,8-Octamethylcyclotetrasilazane



Octamethylcyclotetrasiloxane



1,1,1,3,5,7,7,7-Octamethyltetrasiloxane



Octamethyltrisiloxane



Octanal



Octanamide



2-Octanamine, (±)



Octane



1,8-Octanediamine



Octanedinitrile


Octanedioic acid



1,2-Octanediol



1,8-Octanediol



Octanenitrile



1-Octanethiol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8354	Octanoic acid	Caprylic acid	$C_8H_{16}O_2$	124-07-2	144.212		16.5	239	0.9073^{25}	1.4285^{20}	sl H_2O; msc EtOH, chl, CH_3CN
8355	Octanoic anhydride		$C_{16}H_{30}O_3$	623-66-5	270.407	liq	-1	282.5	0.9065^{18}	1.4358^{18}	vs ace, eth, EtOH
8356	1-Octanol	Capryl alcohol	$C_8H_{18}O$	111-87-5	130.228	liq	-14.8	195.16	0.8262^{25}	1.4295^{20}	i H_2O; msc EtOH, eth; s ctc
8357	2-Octanol	(±)-*sec*-Caprylic alcohol	$C_8H_{18}O$	4128-31-8	130.228	liq	-31.6	179.3	0.8193^{20}	1.4203^{20}	sl H_2O; s EtOH, eth, ace
8358	3-Octanol		$C_8H_{18}O$	589-98-0	130.228	liq	-45	171	0.8258^{20}		
8359	4-Octanol		$C_8H_{18}O$	74778-22-6	130.228	liq	-40.7	176.3	0.8186^{20}	1.4248^{20}	sl H_2O, ctc; s EtOH
8360	2-Octanone	Hexyl methyl ketone	$C_8H_{16}O$	111-13-7	128.212	liq	-16	172.5	0.820^{20}	1.4151^{20}	sl H_2O; msc EtOH, eth
8361	3-Octanone	Ethyl pentyl ketone	$C_8H_{16}O$	106-68-3	128.212			167.5	0.822^{25}	1.4150^{20}	i H_2O; msc EtOH, eth
8362	4-Octanone	Butyl propyl ketone	$C_8H_{16}O$	589-63-9	128.212			163	0.8146^{25}	1.4173^{14}	i H_2O; msc EtOH, eth; s ctc
8363	Octanoyl chloride		$C_8H_{15}ClO$	111-64-8	162.657	liq	-63	195.6	0.9535^{15}	1.4335^{20}	s eth
8364	Octaphenylcyclotetrasiloxane		$C_{48}H_{40}O_4Si_4$	546-56-5	793.172	nd (bz-al, HOAc)	200.5	330[1]			i H_2O; sl EtOH; s bz, chl, HOAc
8365	1,3,5,7-Octatetraene		C_8H_{10}	1482-91-3	106.165	cry (bz)	50	sub			s peth, HOAc
8366	*trans*-2-Octenal		$C_8H_{14}O$	2548-87-0	126.196	liq		85[19]	0.846	1.4500^{20}	
8367	1-Octene	Caprylene	C_8H_{16}	111-66-0	112.213	liq	-101.7	121.29	0.7149^{20}	1.4087^{20}	i H_2O; msc EtOH; s eth, ace; sl ctc
8368	*cis*-2-Octene		C_8H_{16}	7642-04-8	112.213	liq	-100.2	125.6	0.7243^{20}	1.4150^{20}	i H_2O; s EtOH, eth, ace, bz, chl
8369	*trans*-2-Octene		C_8H_{16}	13389-42-9	112.213	liq	-87.7	125	0.7199^{20}	1.4132^{20}	i H_2O; s EtOH, eth, ace, bz; vs chl
8370	*cis*-3-Octene		C_8H_{16}	14850-22-7	112.213	liq	-126	122.9	0.7159^{20}	1.4135^{20}	vs ace, bz, eth, EtOH
8371	*trans*-3-Octene		C_8H_{16}	14919-01-8	112.213	liq	-110	123.3	0.7152^{20}	1.4126^{20}	i H_2O; s EtOH, eth, ace, bz, lig, ctc
8372	*cis*-4-Octene		C_8H_{16}	7642-15-1	112.213	liq	-118.7	122.5	0.7212^{20}	1.4148^{20}	vs ace, bz, eth, EtOH
8373	*trans*-4-Octene		C_8H_{16}	14850-23-8	112.213	liq	-93.8	122.3	0.7141^{20}	1.4114^{20}	i H_2O; s EtOH, eth, ace, bz, lig; sl ctc
8374	1-Octen-3-ol		$C_8H_{16}O$	3391-86-4	128.212			174; 69[12]	0.8395^{13}	1.4391^{12}	
8375	2-Octen-1-ol		$C_8H_{16}O$	22104-78-5	128.212			88[11]	0.850^{20}	1.4470^{20}	
8376	1-Octen-3-yne		C_8H_{12}	17679-92-4	108.181			134; 62[60]	0.7749^{20}	1.4592^{20}	vs eth
8377	Octhilinone	2-Octyl-3(2*H*)-isothiazolone	$C_{11}H_{19}NOS$	26530-20-1	213.340			120[0.01]			
8378	Octyl acetate		$C_{10}H_{20}O_2$	112-14-1	172.265	liq	-38.5	210	0.8705^{20}	1.4150^{20}	i H_2O; s EtOH, eth; sl ctc
8379	Octyl acrylate	Octyl 2-propenoate	$C_{11}H_{20}O_2$	2499-59-4	184.276			229; 57[0.05]	0.8810^{20}		
8380	Octylamine	1-Octanamine	$C_8H_{19}N$	111-86-4	129.244		0	179.6	0.7826^{20}	1.4292^{20}	sl H_2O; vs EtOH, eth; s ctc
8381	Octylamine hydrochloride	1-Octanamine hydrochloride	$C_8H_{20}ClN$	142-95-0	165.705		196.5				s H_2O
8382	4-Octylaniline		$C_{14}H_{23}N$	16245-79-7	205.340		20	310; 138[5]	0.9128^{20}		vs eth
8383	Octylbenzene		$C_{14}H_{22}$	2189-60-8	190.325	liq	-36	264	0.8562^{20}	1.4845^{20}	i H_2O; msc eth, bz
8384	Octyl butanoate		$C_{12}H_{24}O_2$	110-39-4	200.318	liq	-55.6	244.1	0.8629^{20}	1.4267^{15}	vs EtOH
8385	Octylcyclohexane		$C_{14}H_{28}$	1795-15-9	196.372	liq	-20	264	0.8138^{20}	1.4503^{20}	
8386	Octylcyclopentane		$C_{13}H_{26}$	1795-20-6	182.345	liq	-44	243	0.8048^{20}	1.4446^{20}	
8387	2-Octyldecanoic acid		$C_{18}H_{36}O_2$	619-39-6	284.478	nd or lf (al)	38.5	215[13]	0.8447^{70}		vs eth, EtOH
8388	Octyldimethylamine	*N,N*-Dimethyl-1-octanamine	$C_{10}H_{23}N$	7378-99-6	157.297			194			
8389	Octyl diphenyl phosphate		$C_{20}H_{27}O_4P$	115-88-8	362.399				1.09^{25}		
8390	Octyl formate		$C_9H_{18}O_2$	112-32-3	158.238	liq	-39.1	198.8	0.8744^{20}	1.4208^{15}	i H_2O; s EtOH; msc eth; sl ctc
8391	Octyl isocyanate		$C_9H_{17}NO$	3158-26-7	155.237			78[6]			
8392	Octyl methacrylate		$C_{12}H_{22}O_2$	2157-01-9	198.302			239.5			
8393	Octyl nitrate		$C_8H_{17}NO_3$	629-39-0	175.226			110[20]	0.975[0]		sl H_2O; s EtOH, eth
8394	Octyl nitrite		$C_8H_{17}NO_2$	629-46-9	159.227			174.5	0.862^{17}	1.4127^{20}	sl H_2O; vs EtOH, eth
8395	Octyl octanoate		$C_{16}H_{32}O_2$	2306-88-9	256.424	liq	-18.1	306.8	0.8554^{20}	1.4352^{20}	vs ace, eth, EtOH



Octanoic acid



Octanoic anhydride



1-Octanol



2-Octanol



3-Octanol



4-Octanol



2-Octanone



3-Octanone


4-Octanone



Octanoyl chloride



Octaphenylcyclotetrasiloxane



1,3,5,7-Octatetraene


trans-2-Octenal


1-Octene



cis-2-Octene



trans-2-Octene



cis-3-Octene


trans-3-Octene



cis-4-Octene



trans-4-Octene



1-Octen-3-ol



2-Octen-1-ol



1-Octen-3-yne



Octhilinone



Octyl acetate



Octyl acrylate



Octylamine



Octylamine hydrochloride



4-Octylaniline



Octylbenzene



Octyl butanoate



Octylcyclohexane



Octylcyclopentane



2-Octyldecanoic acid



Octyldimethylamine



Octyl diphenyl phosphate



Octyl formate


Octyl isocyanate



Octyl methacrylate



Octyl nitrate



Octyl nitrite



Octyl octanoate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8396	Octyloxirane		$C_{10}H_{20}O$	2404-44-6	156.265	liq		128^{35}, 97^{30}			
8397	4-(Octyloxy)benzaldehyde		$C_{15}H_{22}O_2$	24083-13-4	234.335			$131^{0.5}$			
8398	4-Octylphenol		$C_{14}H_{22}O$	1806-26-4	206.324		43.0	169^{10}, 150^{4}			
8399	Octyl phenyl ether	(Octyloxy)benzene	$C_{14}H_{22}O$	1818-07-1	206.324		8	285	0.9131^{15}	1.4875^{20}	i H_2O; s EtOH, eth
8400	4-Octylphenyl salicylate	2-Hydroxybenzoic acid, 4-octylphenyl ester	$C_{21}H_{26}O_3$	2512-56-3	326.429	wh cry	73				
8401	Octyl propanoate		$C_{11}H_{22}O_2$	142-60-9	186.292	liq	-42.6	228	0.8663^{20}	1.4221^{15}	i H_2O; s EtOH, eth, bz; sl ctc
8402	1-Octyne	Hexylacetylene	C_8H_{14}	629-05-0	110.197	liq	-79.3	126.3	0.7461^{20}	1.4159^{20}	i H_2O; s EtOH, eth
8403	2-Octyne	Methylpentylacetylene	C_8H_{14}	2809-67-8	110.197	liq	-61.6	137.6	0.7596^{20}	1.4278^{20}	i H_2O; s EtOH, eth
8404	3-Octyne		C_8H_{14}	15232-76-5	110.197	liq	-103.9	133.1	0.7529^{20}	1.4250^{20}	i H_2O; s EtOH, eth
8405	4-Octyne	Dipropylacetylene	C_8H_{14}	1942-45-6	110.197	liq	-101	131.6	0.7509^{20}	1.4248^{20}	i H_2O; s EtOH, eth
8406	2-Octyn-1-ol	2-Octynol	$C_8H_{14}O$	20739-58-6	126.196		-18	98^{15}	0.8805^{20}	1.4556^{20}	vs eth
8407	Oleandrin		$C_{32}H_{48}O_9$	465-16-7	576.718	cry (EtOH)	250 dec				i H_2O; s EtOH, chl
8408	Olean-12-en-3-ol, (3β)	β-Amyrin	$C_{30}H_{50}O$	559-70-6	426.717	nd (lig or al)	197	260^{05}			i H_2O; sl EtOH, chl, lig; s eth, bz
8409	Oleanolic acid		$C_{30}H_{48}O_3$	508-02-1	456.700	nd or pr (al)	310 dec	sub 280			i H_2O; sl EtOH, eth, ace; vs py, HOAc
8410	Oleic acid	*cis*-9-Octadecenoic acid	$C_{18}H_{34}O_2$	112-80-1	282.462		13.4	360; 286^{100}	0.8935^{20}	1.4582^{20}	i H_2O; msc EtOH, eth, ace, bz, chl, ctc
8411	Omeprazole		$C_{17}H_{19}N_3O_3S$	73590-58-6	345.416	cry (MeCN)	156				
8412	Omethoate		$C_5H_{12}NO_4PS$	1113-02-6	213.192	oil	≈135 dec		1.32^{20}	1.4987^{20}	msc H_2O; i hx
8413	Orange I	1-Naphthol Orange	$C_{16}H_{11}N_2NaO_4S$	523-44-4	350.324	red-br pow					s H_2O; sl EtOH; i bz
8414	Orange IV	Tropaeolin OO	$C_{18}H_{14}N_3NaO_3S$	554-73-4	375.377	ye pow					s H_2O
8415	Orcein			1400-62-0		br-red pow					
8416	*L*-Ornithine	2,5-Diaminopentanoic acid, (*S*)	$C_5H_{12}N_2O_2$	70-26-8	132.161	micro cry (al-eth)	140				vs H_2O, EtOH
8417	*L*-Ornithine, monohydrochloride		$C_5H_{13}ClN_2O_2$	3184-13-2	168.622	nd	215				vs H_2O
8418	Orotic acid	1,2,3,6-Tetrahydro-2,6-dioxo-4-pyrimidinecarboxylic acid	$C_5H_4N_2O_4$	65-86-1	156.097	cry (w)	345.5				sl H_2O; i os
8419	Oroxylin A	5,7-Dihydroxy-6-methoxy-2-phenyl-4*H*-1-benzopyran-4-one	$C_{16}H_{12}O_5$	480-11-5	284.263	ye nd (al)	231.5				vs ace, eth, EtOH
8420	Orphenadrine		$C_{18}H_{23}NO$	83-98-7	269.382			195^{12}			
8421	Oryzalin	Benzenesulfonamide, 4-(dipropylamino)-3,5-dinitro-	$C_{12}H_{18}N_4O_6S$	19044-88-3	346.359		141				
8422	Ouabain		$C_{29}H_{44}O_{12}$	630-60-4	584.652	hyg pl (+9w)	200				sl H_2O; vs EtOH
8423	7-Oxabicyclo[4.1.0]heptane		$C_6H_{10}O$	286-20-4	98.142		<-10	131.5	0.9663^{20}	1.4519^{20}	i H_2O; vs EtOH, eth, ace, bz; s chl; sl ctc
8424	6-Oxabicyclo[3.1.0]hexane		C_5H_8O	285-67-6	84.117			102	0.964^{25}	1.4336^{20}	
8425	Oxacyclohexadecan-2-one	Exaltolide	$C_{15}H_{28}O_2$	106-02-5	240.382	thick oil		176^{15}	0.9549^{20}	1.4708^{20}	
8426	1,3,4-Oxadiazole	1-Oxa-3,4-diazacyclopentadiene	$C_2H_2N_2O$	288-99-3	70.049			150		1.4300^{25}	
8427	Oxadiazon		$C_{15}H_{18}Cl_2N_2O_3$	19666-30-9	345.221		90				
8428	Oxadixyl		$C_{14}H_{18}N_2O_4$	77732-09-3	278.304		104				
8429	Oxalic acid		$C_2H_2O_4$	144-62-7	90.035	orth pym or oct	189.5 dec	sub 157	1.900^{17}		s H_2O; vs EtOH; sl eth; i bz, chl, peth
8430	Oxalic acid dihydrate		$C_2H_6O_6$	6153-56-6	126.065	mcl tab or pr	101.5		1.653^{18}		s H_2O, EtOH; sl eth
8431	Oxaloacetic acid	Oxalacetic acid	$C_4H_4O_5$	328-42-7	132.072		161 dec				
8432	Oxalyl chloride	Oxalyl dichloride	$C_2Cl_2O_2$	79-37-8	126.926	liq	-16	63.5	1.4785^{20}	1.4316^{20}	s eth
8433	Oxalyl dihydrazide		$C_2H_6N_4O_2$	996-98-5	118.095	nd (w)	244.0		1.458^{22}		s H_2O; sl EtOH, eth, bz, chl
8434	Oxamic acid		$C_2H_3NO_3$	471-47-6	89.050	cry (w)	210 dec				sl H_2O; i EtOH, eth
8435	Oxamide		$C_2H_4N_2O_2$	471-46-5	88.065	nd (w)	350 dec		1.667^{20}		sl H_2O, EtOH; i eth
8436	Oxamniquine		$C_{14}H_{21}N_3O_3$	21738-42-1	279.335	ye-oran cry	149				s ace, chl, MeOH
8437	Oxamyl		$C_7H_{13}N_3O_3S$	23135-22-0	219.261		109	dec	0.97^{25}		
8438	Oxandrolone		$C_{19}H_{30}O_3$	53-39-4	306.439		236				
8439	1,4-Oxathiane		C_4H_8OS	15980-15-1	104.171	liq	-17	147	1.1174^{20}		sl H_2O



Octyloxirane



4-(Octyloxy)benzaldehyde



4-Octylphenol



Octyl phenyl ether



4-Octylphenyl salicylate



Octyl propanoate



1-Octyne



2-Octyne



3-Octyne



4-Octyne



2-Octyn-1-ol



Oleandrin



Olean-12-en-3-ol, (3β)



Oleanolic acid



Oleic acid



Omeprazole



Omethoate



Orange I



Orange IV



L-Ornithine



L-Ornithine, monohydrochloride



Orotic acid


Oroxylin A



Orphenadrine


Oryzalin



Ouabain



7-Oxabicyclo[4.1.0]heptane



6-Oxabicyclo[3.1.0]hexane



Oxacyclohexadecan-2-one



1,3,4-Oxadiazole



Oxadiazon



Oxadixyl



Oxalic acid



Oxalic acid dihydrate



Oxaloacetic acid



Oxalyl chloride



Oxalyl dihydrazide


Oxamic acid


Oxamide



Oxamniquine


Oxamyl


Oxandrolone


1,4-Oxathiane

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8440	Oxazepam		$C_{15}H_{11}ClN_2O_2$	604-75-1	286.713	cry (EtOH)	205.5				i H_2O; s EtOH, chl, diox
8441	Oxazole		C_3H_3NO	288-42-6	69.062			69.5		1.4285^{17}	
8442	Oxepane		$C_6H_{12}O$	592-90-5	100.158			119	0.89^{25}	1.4400^{20}	
8443	2-Oxepanone	Caprolactone	$C_6H_{10}O_2$	502-44-3	114.142	liq	-1.0	215	1.0761^{20}	1.4611^{20}	s EtOH, eth, ace
8444	Oxetane	Trimethylene oxide	C_3H_6O	503-30-0	58.079	liq	-97	47.6	0.8930^{25}	1.3961^{20}	msc H_2O, EtOH; s eth; vs ace
8445	2-Oxetanone	β-Propiolactone	$C_3H_4O_2$	57-57-8	72.063	liq	-33.4	162	1.1460^{20}	1.4105^{20}	msc eth; s chl
8446	3-Oxetanone		$C_3H_4O_2$	6704-31-0	72.063	unstab liq		106	1.137		
8447	Oxirane	Ethylene oxide	C_2H_4O	75-21-8	44.052	vol liq or gas	-112.5	10.6	0.8821^{10}	1.3597^{7}	s H_2O, EtOH, eth, ace, bz
8448	Oxiranecarboxaldehyde	Glycidaldehyde	$C_3H_4O_2$	765-34-4	72.063	liq	-62	112.5	1.1403^{20}	1.4265^{20}	
8449	Oxiranemethanol, (±)	Glycidol	$C_3H_6O_2$	61915-27-3	74.079		-45	dec 167; 66$^{2.5}$	1.1143^{25}	1.4287^{20}	vs H_2O, ace, eth, EtOH; s bz, chl
8450	α-Oxobenzeneacetaldehyde aldoxime	Isonitrosoacetophenone	$C_8H_7NO_2$	532-54-7	149.148		129				sl H_2O; s chl
8451	α-Oxobenzeneacetic acid		$C_8H_6O_3$	611-73-4	150.132	pr (CCl_4)	66	163^{15}			vs H_2O; s EtOH, eth; sl ctc; i CS_2
8452	α-Oxobenzeneacetic acid, methyl ester		$C_9H_8O_3$	15206-55-0	164.158			247		1.5268^{20}	
8453	α-Oxobenzeneacetonitrile		C_8H_5NO	613-90-1	131.132		32.5	206			i H_2O; vs EtOH, eth; sl chl
8454	γ-Oxobenzenebutanoic acid		$C_{10}H_{10}O_3$	2051-95-8	178.184	lf (dil al)	116.5				s H_2O, EtOH, eth, bz, chl, CS_2
8455	β-Oxobenzenepropanenitrile	Benzoylacetonitrile	C_9H_7NO	614-16-4	145.158		80.5	160^{10}			sl H_2O; s EtOH, eth, bz, chl, alk, aq KCN
8456	α-Oxobenzenepropanoic acid	3-Phenylpyruvic acid	$C_9H_8O_3$	156-06-9	164.158	lf (bz, chl)	157.5				sl H_2O; vs EtOH, eth; s bz, chl; i lig
8457	2-Oxo-2*H*-1-benzopyran-3-carboxylic acid	Coumarin-3-carboxylic acid	$C_9H_6O_3$	531-81-7	162.142	nd (w, bz)	190 dec				vs EtOH
8458	Oxobis(2,4-pentanedione) vanadium	Vanadyl acetylacetonate	$C_{10}H_{14}O_5V$	3153-26-2	265.157	bl cry	258	174$^{0.2}$			i H_2O; s EtOH, MeOH, bz, chl
8459	2-Oxobutanoic acid		$C_4H_6O_3$	600-18-0	102.089		33	81^{16}	1.200^{17}	1.3972^{20}	vs H_2O, EtOH; sl eth
8460	4-Oxobutanoic acid		$C_4H_6O_3$	692-29-5	102.089	oil		135^{14}			s H_2O, EtOH, eth, bz
8461	2-Oxoglutaric acid	α-Ketoglutaric acid	$C_5H_6O_5$	328-50-7	146.099	cry (ace-bz)	115.5				vs H_2O, EtOH, eth; s ace
8462	6-Oxoheptanoic acid		$C_7H_{12}O_3$	3128-07-2	144.168		40.2	251^{280}, 135^{1}		1.4306^{25}	vs H_2O, ace, eth, EtOH
8463	5-Oxohexanoic acid		$C_6H_{10}O_3$	3128-06-1	130.141		13.5	274.5	1.09^{25}	1.4451^{20}	s H_2O, EtOH, eth; sl ctc
8464	α-Oxo-1*H*-indole-3-propanoic acid	Indole-3-pyruvic acid	$C_{11}H_9NO_3$	392-12-1	203.194	gray cry	211				
8465	Oxolinic acid		$C_{13}H_{11}NO_5$	14698-29-4	261.230	cry (DMF)	313 dec				
8466	4-Oxopentanal		$C_5H_8O_2$	626-96-0	100.117		<-21	dec 187	1.0134^{21}	1.4257^{22}	vs H_2O, ace, eth, EtOH
8467	3-Oxopentanedioic acid	Acetonedicarboxylic acid	$C_5H_6O_5$	542-05-2	146.099	nd (AcOEt)	138 dec				s H_2O, EtOH; sl eth; i bz, chl, lig
8468	2-Oxopentanoic acid		$C_5H_8O_3$	1821-02-9	116.116		6.5	179	1.0970^{14}		sl H_2O; s eth, bz, chl, lig, CS_2
8469	4-Oxopentanoic acid	Levulinic acid	$C_5H_8O_3$	123-76-2	116.116	lf or pl	33	dec 245	1.1335^{20}	1.4396^{20}	vs H_2O, EtOH, eth; s chl
8470	4-Oxo-4-(phenylamino)butanoic acid	Succinanilic acid	$C_{10}H_{11}NO_3$	102-14-7	193.199	nd (w)	148.5				sl H_2O; s EtOH; vs eth
8471	*cis*-4-Oxo-4-(phenylamino)-2-butenoic acid	Maleanilic acid	$C_{10}H_9NO_3$	555-59-9	191.183	mcl ye cry	192 dec		1.418^{30}		
8472	Oxophenylarsine	Phenylarsine oxide	C_6H_5AsO	637-03-6	168.025	cry (bz-eth) or (chl-eth)	145				i H_2O, eth; sl EtOH; vs bz, chl
8473	4-Oxo-4-phenyl-2-butenoic acid		$C_{10}H_8O_3$	583-06-2	176.169	nd or pr (tol)	99				sl H_2O, chl, lig; s EtOH, eth, tol
8474	2-Oxopropanal oxime	Isonitrosoacetone	$C_3H_5NO_2$	306-44-5	87.078	nd(CCl_4) lf (eth-peth)	69	sub	1.0744^{67}		s H_2O, eth; sl bz, ctc, chl
8475	2-Oxopropanenitrile		C_3H_3NO	631-57-2	69.062			92.3	0.9745^{20}	1.3764^{20}	s eth, ace, CH_3CN
8476	17-(1-Oxopropoxy)-androst-4-en-3-one, (17β)	Testosterone-17-propionate	$C_{22}H_{32}O_3$	57-85-2	344.487		120				vs eth, py, EtOH


Oxazepam


Oxazole


Oxepane


2-Oxepanone



Oxetane



2-Oxetanone



3-Oxetanone



Oxirane



Oxiranecarboxaldehyde



Oxiranemethanol, (±)



α-Oxobenzeneacetaldehyde aldoxime



α-Oxobenzeneacetic acid



α-Oxobenzeneacetic acid, methyl ester



α-Oxobenzeneacetonitrile



γ-Oxobenzenebutanoic acid



β-Oxobenzenepropanenitrile



α-Oxobenzenepropanoic acid



2-Oxo-2*H*-1-benzopyran-3-carboxylic acid



Oxobis(2,4-pentanedione)vanadium



2-Oxobutanoic acid



4-Oxobutanoic acid



2-Oxoglutaric acid



6-Oxoheptanoic acid



5-Oxohexanoic acid



α-Oxo-1*H*-indole-3-propanoic acid



Oxolinic acid



4-Oxopentanal



3-Oxopentanedioic acid



2-Oxopentanoic acid



4-Oxopentanoic acid


4-Oxo-4-(phenylamino)butanoic acid



cis-4-Oxo-4-(phenylamino)-2-butenoic acid


Oxophenylarsine



4-Oxo-4-phenyl-2-butenoic acid



2-Oxopropanal oxime



2-Oxopropanenitrile



17-(1-Oxopropoxy)-androst-4-en-3-one, (17β)


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8477	2-Oxo-2*H*-pyran-5-carboxylic acid	Coumalic acid	$C_6H_4O_4$	500-05-0	140.094	pr (MeOH)	207 dec	218^{120}			sl H_2O, eth, ace; i bz, chl; s EtOH, HOAc
8478	4-Oxo-4*H*-pyran-2,6-dicarboxylic acid	Chelidonic acid	$C_7H_4O_6$	99-32-1	184.103	rose mcl nd (al-w,+1w)	262				sl H_2O, EtOH
8479	17-Oxosparteine		$C_{15}H_{24}N_2O$	489-72-5	248.364	ye to col hyg nd (peth)	84	209^{12}			vs H_2O, EtOH, eth; s chl
8480	4,4'-Oxybis(benzenesulfonyl chloride)	Diphenyl ether 4,4'-disulfonyl chloride	$C_{12}H_8Cl_2O_5S_2$	121-63-1	367.225	cry (peth)	128				
8481	4,4'-Oxybis(benzenesulfonyl hydrazide)		$C_{12}H_{14}N_4O_5S_2$	80-51-3	358.393	cry (H_2O)	164 dec				
8482	Oxybutynin		$C_{22}H_{31}NO_3$	5633-20-5	357.486	cry	114				
8483	Oxycarboxin	Carboxin *S,S*-dioxide	$C_{12}H_{13}NO_4S$	5259-88-1	267.301	pr (EtOH)	129				sl H_2O; s bz, EtOH; vs ace
8484	Oxychlordane		$C_{10}H_4Cl_8O$	27304-13-8	423.762	cry (pentane)	100				
8485	Oxycodone	Dihydro-14-hydroxycodeinone	$C_{18}H_{21}NO_4$	76-42-6	315.365	rods (EtOH)	219				i H_2O, eth; s EtOH, chl
8486	Oxydemeton-methyl		$C_6H_{15}O_4PS_2$	301-12-2	246.284		<-20	$106^{0.01}$	1.289^{20}		
8487	10,10'-Oxydiphenoxarsine	10,10'-Oxybis[10*H*-phenoxarsine]	$C_{24}H_{16}As_2O_3$	58-36-6	502.225	col mcl cry	185		1.41		i H_2O; s EtOH, chl; i CH_2Cl_2
8488	Oxyfluorfen		$C_{15}H_{11}ClF_3NO_4$	42874-03-3	361.701		84	dec 358	1.35^{73}		
8489	Oxymetazoline		$C_{16}H_{24}N_2O$	1491-59-4	260.374	cry (bz)	182				i eth, chl
8490	Oxymetholone		$C_{21}H_{32}O_3$	434-07-1	332.477	cry	179				
8491	Oxymethurea		$C_3H_8N_2O_3$	140-95-4	120.107	pr(al)	126	149^{25}			s H_2O, EtOH, MeOH; i eth; sl DMSO
8492	Oxyphenbutazone		$C_{19}H_{20}N_2O_3$	129-20-4	324.373	cry (eth/ peth)	124				s EtOH, MeOH, chl, bz, eth
8493	Oxyphenonium bromide		$C_{21}H_{34}BrNO_3$	50-10-2	428.404		191.5				vs H_2O; sl EtOH
8494	Oxytetracycline		$C_{22}H_{24}N_2O_9$	79-57-2	460.434		184.5		1.634^{20}		
8495	Oxytocin		$C_{43}H_{66}N_{12}O_{12}S_2$	50-56-6	1007.187	wh pow					s H_2O, BuOH
8496	Paclobutrazol		$C_{15}H_{20}ClN_3O$	76738-62-0	293.792	wh cry	166		1.22		i H_2O; vs ace, MeOH; s xyl, hx
8497	Palustric acid		$C_{20}H_{30}O_2$	1945-53-5	302.451	cry (MeOH)	164.5				
8498	Pamoic acid		$C_{23}H_{16}O_6$	130-85-8	388.369		315				
8499	Pancuronium dibromide		$C_{35}H_{60}Br_2N_2O_4$	15500-66-0	732.670	cry	215				sl chl
8500	Panose	4-α-Isomaltosylglucose	$C_{18}H_{32}O_{16}$	33401-87-5	504.437		223 dec				
8501	Panthesin		$C_{18}H_{32}N_2O_5S$	135-44-4	388.522	pa ye pow (al)	158				vs H_2O, EtOH
8502	Pantolactone		$C_6H_{10}O_3$	599-04-2	130.141		92				
8503	Pantothenic acid		$C_9H_{17}NO_5$	79-83-4	219.235	ye visc oil					vs H_2O, bz, eth
8504	Papaveraldine		$C_{20}H_{19}NO_5$	522-57-6	353.369	nd (al),cry (bz, peth)	210.5				i H_2O; sl EtOH, eth; s bz, chl
8505	Papaverine		$C_{20}H_{21}NO_4$	58-74-2	339.386	wh pr (al-eth), nd (chl-peth)	147.5	sub 135	1.337^{20}	1.625	sl H_2O; vs EtOH, chl; s ace, bz, py
8506	Papaverine hydrochloride	Cerespan	$C_{20}H_{22}ClNO_4$	61-25-6	375.847	wh mcl pr (w)	224.5				vs H_2O, EtOH
8507	Paraformaldehyde		$(CH_2O)_x$	30525-89-4	30.026		164 dec				
8508	Paraldehyde	2,4,6-Trimethyl-1,3,5-trioxane	$C_6H_{12}O_3$	123-63-7	132.157		12.6	124.3	0.9943^{20}	1.4049^{20}	sl H_2O; msc EtOH, eth, chl
8509	Paramethadione		$C_7H_{11}NO_3$	115-67-3	157.167	liq			1.121^{25}	1.449^{25}	sl H_2O; s EtOH, chl, bz, eth
8510	Paraoxon	*O,O*-Diethyl *O*-(4-nitrophenyl) phosphate	$C_{10}H_{14}NO_6P$	311-45-5	275.195	oily liq		$161^{0.5}$	1.2683^{25}	1.5096	s eth
8511	Paraquat		$C_{12}H_{14}N_2$	4685-14-7	186.252	cation					
8512	Pararosaniline hydrochloride	Basic fuchsin	$C_{19}H_{18}ClN_3$	569-61-9	323.819	pale viol pow	269 dec				
8513	Parasorbic acid		$C_6H_8O_2$	10048-32-5	112.127	oily lig		100^{15}	1.079^{18}	1.4736^{20}	vs H_2O, eth, EtOH
8514	Parathion		$C_{10}H_{14}NO_5PS$	56-38-2	291.261	ye liq	6.1	375	1.2681^{20}	1.5370^{25}	i H_2O; s eth, ace; sl ctc; vs EtOH, AcOEt
8515	Patchouli alcohol		$C_{15}H_{26}O$	5986-55-0	222.366		56		0.9906^{65}	1.5029^{65}	i H_2O; s EtOH, eth
8516	Pebulate		$C_{10}H_{21}NOS$	1114-71-2	203.345			142^{20}	0.9458^{20}	1.4752^{20}	vs ace, bz, MeOH
8517	Pelargonidin chloride		$C_{15}H_{11}ClO_5$	134-04-3	306.698	red br hyg (anh) pr or pl	>350				s H_2O; vs EtOH; sl chl, MeOH
8518	Pellotine		$C_{13}H_{19}NO_3$	83-14-7	237.295	pl (al, peth)	111.5				vs ace, eth, EtOH, peth
8519	Pemoline	2-Amino-5-phenyl-4(5*H*)-oxazolone	$C_9H_8N_2O_2$	2152-34-3	176.172	cry	256 dec				i H_2O, eth, ace; sl hot EtOH



2-Oxo-2*H*-pyran-5-carboxylic acid



4-Oxo-4*H*-pyran-2,6-dicarboxylic acid



17-Oxosparteine



4,4'-Oxybis(benzenesulfonyl chloride)



4,4'-Oxybis(benzenesulfonyl hydrazide)



Oxybutynin



Oxycarboxin



Oxychlordane



Oxycodone



Oxydemeton-methyl



10,10'-Oxydiphenoxarsine



Oxyfluorfen



Oxymetazoline



Oxymetholone



Oxymethurea



Oxyphenbutazone



Oxyphenonium bromide



Oxytetracycline



Oxytocin



Paclobutrazol



Palustric acid



Pamoic acid



Pancuronium dibromide



Panose



Panthesin


Pantolactone



Pantothenic acid



Papaveraldine



Papaverine



Papaverine hydrochloride



Paraformaldehyde



Paraldehyde



Paramethadione



Paraoxon



Paraquat



Pararosaniline hydrochloride



Parasorbic acid



Parathion


Patchouli alcohol



Pebulate



Pelargonidin chloride



Pellotine



Pemoline


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8520	Pendimethalin	*N*-(1-Ethylpropyl)-3,4-dimethyl-2,6-dinitroaniline	$C_{13}H_{19}N_3O_4$	40487-42-1	281.308		56	dec	1.19^{25}		
8521	Penicillamine cysteine disulfide		$C_8H_{16}N_2O_4S_2$	18840-45-4	268.354		195				
8522	Penicillin G	Benzylpenicillinic acid	$C_{16}H_{18}N_2O_4S$	61-33-6	334.390	amor wh pow					sl H_2O; s MeOH, EtOH, eth, chl, bz, ace
8523	Penicillin G procaine		$C_{29}H_{38}N_4O_6S$	54-35-3	570.700		108 dec		1.2555^{25}		s H_2O, EtOH, chl
8524	Penicillin V	Phenoxymethylpenicillin	$C_{16}H_{18}N_2O_5S$	87-08-1	350.389	cry	124 dec				sl H_2O; s os
8525	1,2,3,4,5-Pentabromo-6-chlorocyclohexane		$C_6H_6Br_5Cl$	87-84-3	513.085	cry	204				
8526	Pentabromomethylbenzene		$C_7H_3Br_5$	87-83-2	486.619		288		2.97^{17}		i H_2O; sl EtOH, HOAc; s bz
8527	Pentabromophenol		C_6HBr_5O	608-71-9	488.591	mcl pr (HOAc) nd (al)	229.5	sub			i H_2O; s EtOH, bz, HOAc; sl eth
8528	1,1,1,3,3-Pentabromo-2-propanone	Pentabromoacetone	C_3HBr_5O	79-49-2	452.559	nd (w, al) pr (eth)	79.5	sub			i H_2O; vs EtOH, eth, ace, chl
8529	Pentac	Dienochlor	$C_{10}Cl_{10}$	2227-17-0	474.637	tan cry (peth)	122				
8530	Pentacene	Benzo[b]naphthacene	$C_{22}H_{14}$	135-48-8	278.346	ye grn nd or lf (xyl)	>300 dec				i H_2O; sl bz; s $PhNO_2$
8531	2,3,4,5,6-Pentachloroaniline		$C_6H_2Cl_5N$	527-20-8	265.352	nd (al)	233.0				vs eth, EtOH, lig
8532	2,3,4,5,6-Pentachloroanisole	Methyl pentachlorophenyl ether	$C_7H_3Cl_5O$	1825-21-4	280.363	nd MeOH	108.5				
8533	Pentachlorobenzene		C_6HCl_5	608-93-5	250.337	nd (al)	86	277	1.8342^{16}		i H_2O, EtOH; sl eth, bz, chl, CS_2
8534	Pentachlorobenzenethiol	Pentachlorophenyl mercaptan	C_6HCl_5S	133-49-3	282.402		231.5				
8535	2,3,4,5,6-Pentachlorobiphenyl		$C_{12}H_5Cl_5$	18259-05-7	326.433	nd (peth)	123.5				i H_2O
8536	2,2',4,5,5'-Pentachlorobiphenyl		$C_{12}H_5Cl_5$	37680-73-2	326.433	cry (EtOH)	78.5				i H_2O
8537	1,2,3,4,7-Pentachlorodibenzo-*p*-dioxin		$C_{12}H_3Cl_5O_2$	39227-61-7	356.416	cry (bz/ MeOH)	195				
8538	Pentachloroethane	Refrigerant 120	C_2HCl_5	76-01-7	202.294	liq	-28.78	162.0	1.6796^{20}	1.5025^{20}	i H_2O; msc EtOH, eth
8539	Pentachlorofluoroethane		C_2Cl_5F	354-56-3	220.284	col liq	101.3	138	1.74^{25}		i H_2O; s EtOH, eth
8540	Pentachloronitrobenzene	Quintozene	$C_6Cl_5NO_2$	82-68-8	295.335	cry (al)	144	dec 328	1.718^{25}		i H_2O; sl EtOH; s bz, chl
8541	Pentachlorophenol		C_6HCl_5O	87-86-5	266.336	mcl pr (al + 1w) nd (bz)	174	dec 310	1.978^{22}		i H_2O; sl lig; vs EtOH, eth; s bz
8542	1,1,2,2,3-Pentachloropropane		$C_3H_3Cl_5$	16714-68-4	216.321			181^{500}	1.633^{25}	1.5098^{25}	
8543	1,1,2,3,3-Pentachloro-1-propene		C_3HCl_5	1600-37-9	214.305			185	1.6317^{34}	1.5313^{20}	vs eth
8544	Pentachloropyridine		C_5Cl_5N	2176-62-7	251.326		125.5	280			vs bz, EtOH, lig
8545	2,3,4,5,6-Pentachlorotoluene		$C_7H_3Cl_5$	877-11-2	264.364	nd (bz, peth)	224.8	301			sl EtOH, eth, CS_2; s bz, tol, peth
8546	Pentacontane		$C_{50}H_{102}$	6596-40-3	703.345		92.1	575.0			
8547	Pentacosane		$C_{25}H_{52}$	629-99-2	352.681		53.93	401.9; 282^{40}	0.8012^{20}	1.4491^{20}	s bz, chl
8548	1*H*-Pentadecafluoroheptane		C_7HF_{15}	375-83-7	370.059			96.0	1.725^{25}	1.2690^{25}	
8549	Pentadecafluorooctanoic acid		$C_8HF_{15}O_2$	335-67-1	414.069		54.3	188			
8550	2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-Pentadecafluoro-1-octanol	1,1-Dihydroperfluorooctanol	$C_8H_3F_{15}O$	307-30-2	400.085	waxy solid	47	164; 68^{8}			
8551	Pentadecanal		$C_{15}H_{30}O$	2765-11-9	226.398	nd	24.5	185^{25}			vs ace, eth, EtOH
8552	Pentadecane		$C_{15}H_{32}$	629-62-9	212.415		9.95	270.6	0.7685^{20}	1.4315^{20}	i H_2O; vs EtOH, eth
8553	Pentadecanoic acid	Pentadecylic acid	$C_{15}H_{30}O_2$	1002-84-2	242.398	pl (dil al, HOAc) cry (peth)	52.3	257^{100}, 158^{1}	0.8423^{80}	1.4254^{80}	i H_2O; vs EtOH, ace; s eth; sl tfa
8554	1-Pentadecanol		$C_{15}H_{32}O$	629-76-5	228.414		43.9	300	0.8347^{25}		i H_2O
8555	2-Pentadecanone		$C_{15}H_{30}O$	2345-28-0	226.398		39.5	294	0.8182^{39}		
8556	8-Pentadecanone		$C_{15}H_{30}O$	818-23-5	226.398	cry (al)	43	291	0.8180^{39}		s EtOH, eth, bz, ctc, chl
8557	1-Pentadecene		$C_{15}H_{30}$	13360-61-7	210.399	liq	-1.4	268.2	0.7764^{20}	1.4389^{20}	i H_2O; s ace
8558	Pentadecylamine	Pentadecanamine	$C_{15}H_{33}N$	2570-26-5	227.430		37.3	307.6	0.8104^{20}	1.4480^{20}	vs eth, EtOH
8559	Pentadecylbenzene		$C_{21}H_{36}$	2131-18-2	288.511		22	373	0.8548^{20}	1.4815^{20}	
8560	3-Pentadecyl-1,2-benzenediol	3-Pentadecylcatechol	$C_{21}H_{36}O_2$	492-89-7	320.510	nd (to, peth)	59.5				vs bz, eth, EtOH
8561	Pentadecylcyclohexane		$C_{21}H_{42}$	6006-95-7	294.558		29	373	0.8267^{20}	1.4588^{20}	
8562	3-Pentadecylphenol		$C_{21}H_{36}O$	501-24-6	304.510	nd (peth)	53.5	230^{8}, $197^{1.5}$			vs ace, bz, EtOH
8563	1-Pentadecyne		$C_{15}H_{28}$	765-13-9	208.383		10	268	0.7928^{20}	1.4419^{20}	vs ace
8564	1,2-Pentadiene	Ethylallene	C_5H_8	591-95-7	68.118	liq	-137.3	44.9	0.6926^{20}	1.4209^{20}	msc EtOH, eth, ace, bz, ctc, hp
8565	*cis*-1,3-Pentadiene	*cis*-Piperylene	C_5H_8	1574-41-0	68.118	liq	-140.8	44.1	0.6910^{20}	1.4363^{20}	msc EtOH, eth, ace, bz, ctc, hp
8566	*trans*-1,3-Pentadiene	*trans*-Piperylene	C_5H_8	2004-70-8	68.118	liq	-87.4	42	0.6710^{25}	1.4301^{20}	



Pendimethalin



Penicillamine cysteine disulfide



Penicillin G



Penicillin G procaine



Penicillin V



1,2,3,4,5-Pentabromo-6-chlorocyclohexane



Pentabromomethylbenzene



Pentabromophenol



1,1,1,3,3-Pentabromo-2-propanone



Pentac



Pentacene



2,3,4,5,6-Pentachloroaniline



2,3,4,5,6-Pentachloroanisole



Pentachlorobenzene



Pentachlorobenzenethiol



2,3,4,5,6-Pentachlorobiphenyl



2,2',4,5,5'-Pentachlorobiphenyl



1,2,3,4,7-Pentachlorodibenzo-*p*-dioxin



Pentachloroethane



Pentachlorofluoroethane



Pentachloronitrobenzene



Pentachlorophenol



1,1,2,2,3-Pentachloropropane



1,1,2,3,3-Pentachloro-1-propene



Pentachloropyridine



2,3,4,5,6-Pentachlorotoluene



Pentacontane



Pentacosane



1*H*-Pentadecafluoroheptane



Pentadecafluorooctanoic acid



2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-Pentadecafluoro-1-octanol



Pentadecanal



Pentadecane



Pentadecanoic acid



1-Pentadecanol



2-Pentadecanone



8-Pentadecanone



1-Pentadecene



Pentadecylamine



Pentadecylbenzene



3-Pentadecyl-1,2-benzenediol



Pentadecylcyclohexane


3-Pentadecylphenol



1-Pentadecyne


1,2-Pentadiene



cis-1,3-Pentadiene


trans-1,3-Pentadiene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8567	1,4-Pentadiene		C_5H_8	591-93-5	68.118	vol liq or gas	-148.2	26	0.6608^{20}	1.3888^{20}	i H_2O; vs EtOH, eth, ace, bz
8568	2,3-Pentadiene	1,3-Dimethylallene	C_5H_8	591-96-8	68.118	liq	-125.6	48.2	0.6950^{20}	1.4284^{20}	i H_2O; msc EtOH, eth, ace, bz, hp, ctc
8569	1,4-Pentadien-3-ol		C_5H_8O	922-65-6	84.117			115.5	0.860^{23}	1.4400^{17}	
8570	1,3-Pentadiyne	Methyldiacetylene	C_5H_4	4911-55-1	64.086	liq	-38.5	55	0.7909^{20}	1.4431^{21}	i H_2O; s eth, bz, chl
8571	Pentaerythritol		$C_5H_{12}O_4$	115-77-5	136.147	cry (dil HCl)	258	sub		1.548	s H_2O; i eth, bz
8572	Pentaerythritol tetraacetate	2,2-Bis[(acetyloxy)methyl]-1,3-propanediol diacetate	$C_{13}H_{20}O_8$	597-71-7	304.293	tetr nd (w, bz)	83.5		1.273^{18}		s H_2O; vs EtOH, eth
8573	Pentaerythritol tetrakis(2-mercaptoacetate)		$C_{13}H_{20}O_8S_4$	10193-99-4	432.553	liq		250^{1}	1.385^{25}	1.5470^{20}	
8574	Pentaerythritol tetramethacrylate	Tetramethylolmethane tetramethacrylate	$C_{21}H_{28}O_8$	3253-41-6	408.442		53.5				
8575	Pentaerythritol tetranitrate		$C_5H_8N_4O_{12}$	78-11-5	316.138	tetr (ace) pr (ace-al)	140.5		1.773^{20}		sl H_2O, EtOH, eth; vs ace; s bz, py
8576	Pentaethylbenzene		$C_{16}H_{26}$	605-01-6	218.377		<-20	277	0.8971^{19}	1.5127^{20}	
8577	Pentaethyl tantalate	Ethanol, tantalum(5+) salt	$C_{10}H_{25}O_5Ta$	6074-84-6	406.251			151^{1}			
8578	2,3,4,5,6-Pentafluoroaniline		$C_6H_2F_5N$	771-60-8	183.079		34	153.5			
8579	Pentafluorobenzaldehyde		C_7HF_5O	653-37-2	196.074		20	167		1.4506^{20}	
8580	Pentafluorobenzene		C_6HF_5	363-72-4	168.064	liq	-47.4	85.74	1.514^{25}	1.3905^{20}	
8581	Pentafluorobenzenethiol		C_6HF_5S	771-62-0	200.129	liq	-24	143	1.501^{25}	1.4645^{20}	
8582	Pentafluorobenzoic acid		$C_7HF_5O_2$	602-94-8	212.074		101	220			
8583	Pentafluorobenzonitrile		C_7F_5N	773-82-0	193.074		1.2	162	1.563^{20}	1.4402^{25}	
8584	Pentafluoroethane		C_2HF_5	354-33-6	120.021	col gas	-103	-48.1			
8585	Pentafluoroiodobenzene		C_6F_5I	827-15-6	293.960	liq	-29	166	2.212^{20}	1.4950^{25}	
8586	Pentafluoromethoxybenzene	Methyl pentafluorophenyl ether	$C_7H_3F_5O$	389-40-2	198.090	liq	-37	138.5	1.493^{20}	1.4087^{20}	
8587	Pentafluorophenol		C_6HF_5O	771-61-9	184.063		37.5	145.6		1.4263^{20}	
8588	1,1,1,2,2-Pentafluoropropane	Refrigerant 245cb	$C_3H_3F_5$	1814-88-6	134.048	col gas		-17.4			
8589	2,2,3,3,3-Pentafluoro-1-propanol		$C_3H_3F_5O$	422-05-9	150.047			26^{50}			
8590	2,3,4,5,6-Pentafluorotoluene		$C_7H_3F_5$	771-56-2	182.091	liq	-29.78	117.5	1.440^{20}	1.4016^{25}	
8591	1,1,2,4,4-Pentafluoro-3-(trifluoromethyl)-1,3-butadiene		C_5F_8	384-04-3	212.041			39	1.527^{0}	1.3000^{0}	vs ace, bz, eth
8592	Pentagastrin		$C_{37}H_{49}N_7O_9S$	5534-95-2	767.892	col nd	230 dec				i H_2O, bz, EtOH, eth
8593	*trans*-3,3',4',5,7-Pentahydroxyflavanone, (±)	Taxifolin	$C_{15}H_{12}O_7$	480-18-2	304.252		227 dec				s chl
8594	Pentamethonium bromide		$C_{11}H_{28}Br_2N_2$	541-20-8	348.161		301				sl H_2O
8595	Pentamethylbenzene		$C_{11}H_{16}$	700-12-9	148.245	pr (al)	54.5	232	0.917^{20}	1.527^{20}	i H_2O; vs EtOH, bz; s chl
8596	2,4,6,8,10-Pentamethylcyclopentasiloxane		$C_5H_{20}O_5Si_5$	6166-86-5	300.638	liq	-108	169	0.9985^{20}	1.3912^{20}	
8597	2,2,4,6,6-Pentamethylheptane		$C_{12}H_{26}$	13475-82-6	170.334	liq	-67	177.8	0.7463^{20}	1.4440^{20}	
8598	2,2,4,6,6-Pentamethyl-3-heptene		$C_{12}H_{24}$	123-48-8	168.319	liq		180.5			
8599	2,2,3,3,4-Pentamethylpentane		$C_{10}H_{22}$	16747-44-7	142.282	liq	-36.4	166.1	0.7767^{25}	1.4361^{20}	
8600	2,2,3,4,4-Pentamethylpentane		$C_{10}H_{22}$	16747-45-8	142.282	liq	-38.7	159.3	0.7636^{25}	1.4307^{20}	
8601	Pentamethylphenol		$C_{11}H_{16}O$	2819-86-5	164.244	nd (al, peth, ace)	128	267			i H_2O; s EtOH
8602	1,2,2,6,6-Pentamethylpiperidine	Pempidine	$C_{10}H_{21}N$	79-55-0	155.281			147	0.8580^{0}	1.4550^{21}	
8603	Pentamethylsilanamine		$C_5H_{15}NSi$	2083-91-2	117.266			86	0.7400^{20}	1.4379^{24}	
8604	Pentanal	Valeraldehyde	$C_5H_{10}O$	110-62-3	86.132	liq	-91.5	103	0.8095^{20}	1.3944^{20}	sl H_2O; s EtOH, eth
8605	Pentanamide		$C_5H_{11}NO$	626-97-1	101.147	mcl pl (peth, al)	106	225	0.8735^{110}	1.4183^{110}	vs H_2O, EtOH, eth; sl chl
8606	3-Pentanamine		$C_5H_{13}N$	616-24-0	87.164			89	0.7487^{20}	1.4063^{20}	s EtOH; sl chl
8607	Pentane		C_5H_{12}	109-66-0	72.149	liq	-129.67	36.06	0.6262^{20}	1.3575^{20}	sl H_2O; msc EtOH, eth, ace, bz, chl; s ctc
8608	Pentanedial	Glutaraldehyde	$C_5H_8O_2$	111-30-8	100.117			dec 188			msc H_2O, EtOH; s bz
8609	1,5-Pentanediamine	Cadaverine	$C_5H_{14}N_2$	462-94-2	102.178		11.83	179	0.873^{25}	1.463^{20}	s H_2O, EtOH; sl eth
8610	Pentanedinitrile	Glutaronitrile	$C_5H_6N_2$	544-13-8	94.115	liq	-29	286	0.9911^{15}	1.4295^{20}	vs EtOH, chl
8611	1,2-Pentanediol, (±)		$C_5H_{12}O_2$	91049-43-3	104.148			209	0.9723^{20}	1.4397^{19}	
8612	1,4-Pentanediol		$C_5H_{12}O_2$	626-95-9	104.148			$202; 125^{10}$	0.9883^{20}	1.4452^{23}	vs H_2O, EtOH, chl
8613	1,5-Pentanediol	Pentamethylene glycol	$C_5H_{12}O_2$	111-29-5	104.148	liq	-18	239	0.9914^{20}	1.4494^{20}	s H_2O, EtOH; sl eth, bz
8614	2,3-Pentanediol		$C_5H_{12}O_2$	42027-23-6	104.148			$187.5; 100^{17}$	0.9798^{19}	1.4412^{25}	s H_2O, EtOH; sl eth
8615	2,4-Pentanediol	2,4-Amylene glycol	$C_5H_{12}O_2$	625-69-4	104.148			$199; 97^{13}$	0.9635^{20}	1.4349^{20}	vs H_2O, EtOH



1,4-Pentadiene



2,3-Pentadiene



1,4-Pentadien-3-ol


1,3-Pentadiyne



Pentaerythritol



Pentaerythritol tetraacetate



Pentaerythritol tetrakis(2-mercaptoacetate)



Pentaerythritol tetramethacrylate


Pentaerythritol tetranitrate


Pentaethylbenzene



Pentaethyl tantalate



2,3,4,5,6-Pentafluoroaniline


Pentafluorobenzaldehyde



Pentafluorobenzene



Pentafluorobenzenethiol



Pentafluorobenzoic acid


Pentafluorobenzonitrile



Pentafluoroethane



Pentafluoroiodobenzene



Pentafluoromethoxybenzene



Pentafluorophenol



1,1,1,2,2-Pentafluoropropane



2,2,3,3,3-Pentafluoro-1-propanol



2,3,4,5,6-Pentafluorotoluene



1,1,2,4,4-Pentafluoro-3-(trifluoromethyl)-1,3-butadiene



Pentagastrin



trans-3,3',4',5,7-Pentahydroxyflavanone, (±)



Pentamethonium bromide



Pentamethylbenzene



2,4,6,8,10-Pentamethylcyclopentasiloxane



2,2,4,6,6-Pentamethylheptane


2,2,4,6,6-Pentamethyl-3-heptene


2,2,3,3,4-Pentamethylpentane



2,2,3,4,4-Pentamethylpentane



Pentamethylphenol


1,2,2,6,6-Pentamethylpiperidine


Pentamethylsilanamine


Pentanal



Pentanamide



3-Pentanamine


Pentane


Pentanedial



1,5-Pentanediamine



Pentanedinitrile


1,2-Pentanediol, (±)



1,4-Pentanediol



1,5-Pentanediol



2,3-Pentanediol



2,4-Pentanediol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8616	1,5-Pentanediol diacetate	Pentamethylene acetate	$C_9H_{16}O_4$	6963-44-6	188.221		2	241; 123^{3}	1.0296^{20}	1.4261^{19}	
8617	2,3-Pentanedione	Acetylpropionyl	$C_5H_8O_2$	600-14-6	100.117	dk ye liq		108	0.9565^{19}	1.4014^{19}	s H_2O; msc EtOH, eth, ace
8618	2,4-Pentanedione	Acetylacetone	$C_5H_8O_2$	123-54-6	100.117	liq	-23	138	0.9721^{25}	1.4494^{20}	vs H_2O; msc EtOH, eth, ace, chl
8619	Pentanedioyl dichloride		$C_5H_6Cl_2O_2$	2873-74-7	169.006			217	1.324^{20}	1.4728^{20}	s eth; sl chl
8620	Pentanenitrile	Valeronitrile	C_5H_9N	110-59-8	83.132	liq	-96.2	141.3	0.8008^{20}	1.3971^{20}	s eth, ace, bz; sl ctc
8621	1-Pentanethiol	Pentyl mercaptan	$C_5H_{12}S$	110-66-7	104.214	liq	-75.65	126.6	0.850^{20}	1.4469^{20}	i H_2O; msc EtOH, eth
8622	2-Pentanethiol	*sec*-Pentyl mercaptan	$C_5H_{12}S$	2084-19-7	104.214	liq	-169	112.9	0.8327^{20}	1.4412^{20}	s EtOH, lig
8623	3-Pentanethiol	3-Pentyl mercaptan	$C_5H_{12}S$	616-31-9	104.214	liq	-110.8	105	0.8410^{20}	1.4447^{20}	s EtOH; sl DMSO
8624	Pentanoic acid	Valeric acid	$C_5H_{10}O_2$	109-52-4	102.132	liq	-33.6	186.1	0.9339^{25}	1.4085^{20}	s H_2O, EtOH, eth; sl ctc
8625	Pentanoic anhydride		$C_{10}H_{18}O_3$	2082-59-9	186.248	liq	-56.1	227	0.924^{20}	1.4171^{26}	vs eth, EtOH
8626	1-Pentanol	Amyl alcohol	$C_5H_{12}O$	71-41-0	88.148	liq	-77.6	137.98	0.8144^{20}	1.4101^{20}	sl H_2O; msc EtOH, eth; s ace, chl
8627	2-Pentanol	*sec*-Amyl alcohol	$C_5H_{12}O$	6032-29-7	88.148	liq	-73	119.3	0.8094^{20}	1.4053^{20}	sl H_2O; s EtOH, eth, ctc, chl
8628	3-Pentanol	Diethyl carbinol	$C_5H_{12}O$	584-02-1	88.148	liq	-69	116.25	0.8203^{20}	1.4104^{20}	sl H_2O; s EtOH, eth, ace, ctc
8629	2-Pentanone	Methyl propyl ketone	$C_5H_{10}O$	107-87-9	86.132	liq	-76.8	102.26	0.809^{20}	1.3895^{20}	sl H_2O, ctc; msc EtOH, eth
8630	3-Pentanone	Diethyl ketone	$C_5H_{10}O$	96-22-0	86.132	liq	-39	101.7	0.8098^{25}	1.3905^{25}	s H_2O, ctc; msc EtOH, eth
8631	2-Pentanone oxime	Methyl propyl ketone oxime	$C_5H_{11}NO$	623-40-5	101.147			168	0.9095^{20}	1.4450^{20}	vs H_2O, eth, EtOH
8632	Pentanoyl chloride	Valeroyl chloride	C_5H_9ClO	638-29-9	120.577	liq	-110	109	1.0155^{15}	1.4200^{20}	
8633	Pentaphene	2,3:6,7-Dibenzphenanthrene	$C_{22}H_{14}$	222-93-5	278.346	ye grn lf(xyl)	257				i H_2O; sl EtOH, xyl, eth; s bz
8634	1,2,3,5,6-Pentathiepane	Lenthionine	$C_2H_4S_5$	292-46-6	188.378		60.5				
8635	Pentatriacontane		$C_{35}H_{72}$	630-07-9	492.947	cry (al)	74.6	490	0.8157^{20}	1.4568^{20}	i H_2O; sl eth; s ace
8636	18-Pentatriacontanone		$C_{35}H_{70}O$	504-53-0	506.930	lf (lig)	89.0	270$^{0.1}$	0.793^{95}		i H_2O; sl EtOH, eth, ace, bz, lig, chl
8637	Pentazocine		$C_{19}H_{27}NO$	359-83-1	285.423	cry (MeOH aq)	147				
8638	4-Pentenal		C_5H_8O	2100-17-6	84.117			99	0.852^{20}	1.4191^{20}	i H_2O; s eth, ace
8639	1-Pentene	α-Amylene	C_5H_{10}	109-67-1	70.133	vol liq or gas	-165.12	29.96	0.6405^{20}	1.3715^{20}	i H_2O; msc EtOH, eth; s bz; sl ctc
8640	*cis*-2-Pentene	*cis*-β-Amylene	C_5H_{10}	627-20-3	70.133	liq	-151.36	36.93	0.6556^{20}	1.3830^{20}	i H_2O; msc EtOH, eth; s bz, dil sulf
8641	*trans*-2-Pentene	*trans*-β-Amylene	C_5H_{10}	646-04-8	70.133	liq	-140.21	36.34	0.6431^{25}	1.3793^{20}	i H_2O; msc EtOH, eth; s bz; vs dil sulf
8642	*trans*-3-Pentenenitrile		C_5H_7N	16529-66-1	81.117	liq		144	0.837	1.4220^{20}	
8643	4-Pentenenitrile		C_5H_7N	592-51-8	81.117			140	0.8239^{24}	1.4213^{14}	i H_2O; msc EtOH, eth
8644	*trans*-3-Pentenoic acid		$C_5H_8O_2$	1617-32-9	100.117			193.2	0.989^{19}		
8645	4-Pentenoic acid	Allylacetic acid	$C_5H_8O_2$	591-80-0	100.117	liq	-22.5	188.5	0.9809^{20}	1.4281^{20}	sl H_2O; vs EtOH, eth
8646	1-Penten-3-ol		$C_5H_{10}O$	616-25-1	86.132			115	0.839^{20}	1.4239^{20}	sl H_2O; msc EtOH, eth
8647	*cis*-2-Penten-1-ol		$C_5H_{10}O$	1576-95-0	86.132			138	0.8529^{20}	1.4354^{20}	s EtOH, eth, ace
8648	*trans*-2-Penten-1-ol		$C_5H_{10}O$	1576-96-1	86.132			138	0.8471^{20}	1.4341^{20}	s EtOH, eth, ace
8649	3-Penten-2-ol, (±)		$C_5H_{10}O$	42569-16-4	86.132			121.6; 65^{70}	0.8328^{25}	1.4280^{20}	vs ace, eth, EtOH
8650	4-Penten-1-ol		$C_5H_{10}O$	821-09-0	86.132			141	0.8457^{20}	1.4309^{20}	sl H_2O, ctc; s eth
8651	4-Penten-2-ol		$C_5H_{10}O$	625-31-0	86.132			116	0.8367^{20}	1.4225^{20}	vs H_2O; msc EtOH, eth
8652	1-Penten-3-one	Ethyl vinyl ketone	C_5H_8O	1629-58-9	84.117			103; 44^{90}	0.8468^{20}	1.4195^{20}	i H_2O; s EtOH, eth, ace, bz, chl
8653	*trans*-3-Penten-2-one		C_5H_8O	3102-33-8	84.117			122	0.8624^{20}	1.4350^{20}	s H_2O, eth, ace, ctc
8654	2-(3-Pentenyl)pyridine		$C_{10}H_{13}N$	2057-43-4	147.217			216; 93^{12}	0.9234^{25}	1.5076^{25}	
8655	1-Penten-3-yne	Methylvinylacetylene	C_5H_6	646-05-9	66.102			59.5	0.7401^{20}	1.4496^{20}	vs bz, eth
8656	1-Penten-4-yne		C_5H_6	871-28-3	66.102			42.5	0.738^{16}	1.4125^{16}	i H_2O; s eth, bz



1,5-Pentanediol diacetate



2,3-Pentanedione



2,4-Pentanedione



Pentanedioyl dichloride



Pentanenitrile



1-Pentanethiol



2-Pentanethiol



3-Pentanethiol



Pentanoic acid



Pentanoic anhydride



1-Pentanol



2-Pentanol



3-Pentanol


2-Pentanone



3-Pentanone



2-Pentanone oxime



Pentanoyl chloride



Pentaphene


1,2,3,5,6-Pentathiepane


Pentatriacontane



18-Pentatriacontanone



Pentazocine



4-Pentenal



1-Pentene



cis-2-Pentene



trans-2-Pentene



trans-3-Pentenenitrile



4-Pentenenitrile



trans-3-Pentenoic acid



4-Pentenoic acid



1-Penten-3-ol



cis-2-Penten-1-ol



trans-2-Penten-1-ol



3-Penten-2-ol, (±)



4-Penten-1-ol



4-Penten-2-ol


1-Penten-3-one


trans-3-Penten-2-one


2-(3-Pentenyl)pyridine



1-Penten-3-yne



1-Penten-4-yne


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8657	*cis*-3-Penten-1-yne		C_5H_6	1574-40-9	66.102			44.6			
8658	*trans*-3-Penten-1-yne		C_5H_6	2004-69-5	66.102			52.2			
8659	Pentetic acid	Diethylenetriaminepentaacetic acid	$C_{14}H_{23}N_3O_{10}$	67-43-6	393.347	cry (w)	219				s H_2O, alk
8660	Pentostatin		$C_{11}H_{16}N_4O_4$	53910-25-1	268.270	wh cry (MeOH aq)	222				
8661	Pentryl	2-(*N*,2,4,6-Tetranitroanilino) ethanol	$C_8H_8N_6O_{11}$	4481-55-4	362.167	wh-ye cry	129		1.82		i H_2O, ctc; s chl; vs eth, bz
8662	Pentyl acetate	Amyl acetate	$C_7H_{14}O_2$	628-63-7	130.185	liq	-70.8	149.2	0.8756^{20}	1.4023^{20}	sl H_2O; msc EtOH, eth; s ctc
8663	*sec*-Pentyl acetate (*R*)	*sec*-Amyl acetate (*R*)	$C_7H_{14}O_2$	54638-10-7	130.185			142	0.8803^{18}	1.4012^{20}	vs eth, EtOH
8664	Pentylamine	Amylamine	$C_5H_{13}N$	110-58-7	87.164	liq	-55	104.3	0.7544^{20}	1.448^{20}	msc H_2O, EtOH, eth; vs ace, bz; sl chl
8665	4-*tert*-Pentylaniline		$C_{11}H_{17}N$	2049-92-5	163.260			260.5			
8666	Pentylbenzene	Amylbenzene	$C_{11}H_{16}$	538-68-1	148.245	liq	-75	205.4	0.8585^{20}	1.4878^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
8667	Pentyl benzoate		$C_{12}H_{16}O_2$	2049-96-9	192.254			137^{15}			
8668	4-Pentylbenzoyl chloride		$C_{12}H_{15}ClO$	49763-65-7	210.699			144^{10}, 121^{8}	1.036^{25}	1.5300^{20}	
8669	Pentyl butanoate	Amyl butyrate	$C_9H_{18}O_2$	540-18-1	158.238	liq	-73.2	186.4	0.8713^{15}	1.4123^{20}	i H_2O; vs EtOH, eth
8670	*tert*-Pentyl carbamate	*tert*-Amyl carbamate	$C_6H_{13}NO_2$	590-60-3	131.173	nd (dil al)	86				vs ace, bz
8671	Pentyl chloroformate		$C_6H_{11}ClO_2$	638-41-5	150.603			61^{15}		1.4181^{18}	s eth
8672	Pentylcyclohexane		$C_{11}H_{22}$	4292-92-6	154.293	liq	-57.5	203.7	0.8037^{20}	1.4437^{20}	vs ace, bz, eth, EtOH
8673	Pentylcyclopentane		$C_{10}H_{20}$	3741-00-2	140.266	liq	-83	180	0.7912^{20}	1.4356^{20}	i H_2O; vs ace, bz, eth, EtOH
8674	Pentyl formate	Amyl formate	$C_6H_{12}O_2$	638-49-3	116.158	liq	-73.5	130.4	0.8853^{20}	1.3992^{20}	sl H_2O; msc EtOH, eth
8675	Pentyl heptanoate	Amyl enanthate	$C_{12}H_{24}O_2$	7493-82-5	200.318	liq	-50	245.4	0.8623^{20}	1.4263^{15}	vs ace, bz, eth, EtOH
8676	Pentyl hexanoate	Amyl caproate	$C_{11}H_{22}O_2$	540-07-8	186.292	liq	-47	226	0.8612^{25}	1.4202^{25}	s EtOH, eth, ace; sl ctc
8677	1-Pentylnaphthalene		$C_{15}H_{18}$	86-89-5	198.304	liq	-22	307	0.9656^{20}	1.5725^{20}	
8678	Pentyl nitrite	Amyl nitrite	$C_5H_{11}NO_2$	463-04-7	117.147			104.5	0.8817^{20}	1.3851^{20}	sl H_2O; msc EtOH, eth
8679	Pentyl nonanoate	Pentyl pelargonate	$C_{14}H_{28}O_2$	61531-45-1	228.371		-27	131^{20}	0.8506^{25}	1.4318^{20}	
8680	Pentyl octanoate	Amyl octanoate	$C_{13}H_{26}O_2$	638-25-5	214.344	liq	-34.8	260.2	0.8613^{20}	1.4262^{25}	i H_2O; s EtOH, eth, ace
8681	4-(Pentyloxy)benzoyl chloride		$C_{12}H_{15}ClO_2$	36823-84-4	226.699			198^{30}, 182^{25}	1.087^{25}	1.5434^{20}	
8682	Pentyl pentanoate		$C_{10}H_{20}O_2$	2173-56-0	172.265	liq	-78.8	203.7	0.8638^{20}	1.4164^{20}	sl H_2O; msc EtOH, eth
8683	4-Pentylphenol		$C_{11}H_{16}O$	14938-35-3	164.244		23	250.5	0.960^{20}	1.5272^{25}	vs eth, EtOH
8684	Pentyl propanoate		$C_8H_{16}O_2$	624-54-4	144.212	liq	-73.1	168.6	0.8761^{25}	1.4096^{15}	i H_2O; msc EtOH, eth; s bz; sl ctc
8685	Pentyl salicylate		$C_{12}H_{16}O_3$	2050-08-0	208.253			270	1.064^{15}	1.506^{20}	sl H_2O; msc EtOH, eth
8686	Pentyl stearate		$C_{23}H_{46}O_2$	6382-13-4	354.610	pl	30			1.4342^{50}	vs eth, EtOH
8687	1-Pentyne	Propylacetylene	C_5H_8	627-19-0	68.118	liq	-90	40.1	0.6901^{20}	1.3852^{20}	i H_2O; vs EtOH; msc eth; s bz, chl; sl ctc
8688	2-Pentyne		C_5H_8	627-21-4	68.118	liq	-109.3	56.1	0.7058^{25}	1.4039^{20}	i H_2O; vs EtOH; msc eth; s bz, chl
8689	4-Pentynoic acid	Propargylacetic acid	$C_5H_6O_2$	6089-09-4	98.101		57.7	110^{30}, 102^{17}			vs eth, EtOH
8690	2-Pentyn-1-ol		C_5H_8O	6261-22-9	84.117	liq	-49.7	154; 61^{15}	0.909^{20}	1.4518^{17}	
8691	3-Pentyn-1-ol		C_5H_8O	10229-10-4	84.117			154	0.9002^{20}	1.4454^{20}	
8692	4-Pentyn-1-ol		C_5H_8O	5390-04-5	84.117			154	0.913^{20}	1.4414^{20}	
8693	Perazine	10-[3-(4-Methyl-1-piperazinyl) propyl]-10*H*-phenothiazine	$C_{20}H_{25}N_3S$	84-97-9	339.498	cry	52	$165^{0.001}$			
8694	Perfluidone		$C_{14}H_{12}F_3NO_4S_2$	37924-13-3	379.375		143				
8695	Perfluoroacetone	Hexafluoroacetone	C_3F_6O	684-16-2	166.021	col gas	-125.45	-27.4			
8696	Perfluorobutane	Decafluorobutane	C_4F_{10}	355-25-9	238.027	col gas	-129.1	-1.9	1.6484^{25}		s bz, chl
8697	Perfluoro-2-butene		C_4F_8	360-89-4	200.030	col gas	-129	1.5	1.5297^{25}		
8698	Perfluoro-2-butyltetrahydrofuran		$C_8F_{16}O$	335-36-4	416.059			102.6			
8699	Perfluorocyclobutane	Octafluorocyclobutane	C_4F_8	115-25-3	200.030	col gas	-40.19	-5.9	1.500^{25} (p>1 atm)		i H_2O; s eth
8700	Perfluorocyclohexane		C_6F_{12}	355-68-0	300.045		62.5 (triple point)	52.8 sp			
8701	Perfluorocyclohexene		C_6F_{10}	355-75-9	262.048			52.0	1.6650^{25}	1.293^{20}	



cis-3-Penten-1-yne


trans-3-Penten-1-yne



Pentetic acid



Pentostatin



Pentryl



Pentyl acetate



sec-Pentyl acetate (*R*)



Pentylamine



4-*tert*-Pentylaniline



Pentylbenzene



Pentyl benzoate



4-Pentylbenzoyl chloride



Pentyl butanoate



tert-Pentyl carbamate



Pentyl chloroformate



Pentylcyclohexane



Pentylcyclopentane



Pentyl formate



Pentyl heptanoate



Pentyl hexanoate



1-Pentylnaphthalene



Pentyl nitrite



Pentyl nonanoate



Pentyl octanoate



4-(Pentyloxy)benzoyl chloride



Pentyl pentanoate



4-Pentylphenol



Pentyl propanoate



Pentyl salicylate



Pentyl stearate



1-Pentyne



2-Pentyne



4-Pentynoic acid



2-Pentyn-1-ol



3-Pentyn-1-ol



4-Pentyn-1-ol



Perazine



Perfluidone



Perfluoroacetone



Perfluorobutane


Perfluoro-2-butene



Perfluoro-2-butyltetrahydrofuran



Perfluorocyclobutane



Perfluorocyclohexane



Perfluorocyclohexene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8702	Perfluorodecalin		$C_{10}F_{18}$	306-94-5	462.078	liq	-10	142			
8703	Perfluorodecane		$C_{10}F_{22}$	307-45-9	538.072			144.2			i H_2O
8704	Perfluorodimethoxymethane		$C_3F_8O_2$	53772-78-4	220.018	col gas	-161	-10			
8705	Perfluoro-2,3-dimethylbutane		C_6F_{14}	354-96-1	338.042	liq	-15	59.8			
8706	Perfluoroethyl ethyl ether		$C_4H_5F_5O$	22052-81-9	164.074	vol liq or gas		28.11			
8707	Perfluoroethyl 2,2,2-trifluoroethyl ether		$C_4H_2F_8O$	156053-88-2	218.045	vol liq or gas		27.89			
8708	Perfluoroheptane		C_7F_{16}	335-57-9	388.049	liq	-51.2	82.5	1.7333^{20}	1.2618^{20}	i H_2O; vs ace, eth, EtOH, chl
8709	Perfluoro-1-heptene		C_7F_{14}	355-63-5	350.053			81.0			
8710	Perfluorohexane		C_6F_{14}	355-42-0	338.042	liq	-88.2	56.6	1.6995^{20}	1.2515^{20}	i H_2O; s eth, bz, chl
8711	Perfluoro-1-hexene		C_6F_{12}	755-25-9	300.045			57.0			vs chl
8712	Perfluoroisobutane		C_4F_{10}	354-92-7	238.027	col gas		0			
8713	Perfluoroisobutene	Perfluoroisobutylene	C_4F_8	382-21-8	200.030	col gas	-130	7	1.5922^{0}		
8714	Perfluoroisopropyl methyl ether		$C_4H_3F_7O$	22052-84-2	200.055	vol liq or gas		29.34	1.4205^{20}		
8715	Perfluoromethylcyclohexane		C_7F_{14}	355-02-2	350.053	liq	-44.7	76.3	1.7878^{25}	1.285^{17}	s ace, bz, ctc, tol, AcOEt
8716	Perfluoro-2-methylpentane		C_6F_{14}	355-04-4	338.042			57.6	1.7326^{20}	1.2564^{22}	i H_2O; s bz
8717	Perfluoro-3-methylpentane		C_6F_{14}	865-71-4	338.042	liq	-115	58.4			s bz
8718	Perfluoronaphthalene		$C_{10}F_8$	313-72-4	272.094		87.5	209			
8719	Perfluorononane		C_9F_{20}	375-96-2	488.064			125.3	1.800^{25}		
8720	Perfluorooctane		C_8F_{18}	307-34-6	438.057			105.9	1.73^{20}	1.282^{20}	i H_2O
8721	Perfluorooctylsulfonyl fluoride		$C_8F_{18}O_2S$	307-35-7	502.121	liq		154			
8722	Perfluorooxetane		C_3F_6O	425-82-1	166.021	col gas	-117	-28.4			
8723	Perfluoropentane		C_5F_{12}	678-26-2	288.035	vol liq or gas	-10	29.2			i H_2O
8724	Perfluoropropane		C_3F_8	76-19-7	188.019	col gas	-147.70	-36.6			i H_2O
8725	Perfluoropropene		C_3F_6	116-15-4	150.022	col gas	-156.5	-29.6		1.583^{-40}	i H_2O
8726	Perfluoropropyl methyl ether		$C_4H_3F_7O$	375-03-1	200.055			34.23	1.4092^{20}		
8727	Perfluoropyridine	Pentafluoropyridine	C_5F_5N	700-16-3	169.053			83.7			
8728	Perfluorotoluene		C_7F_8	434-64-0	236.062	liq	-65.49	104.5		1.3670^{20}	
8729	Perfluorotripropylamine		$C_9F_{21}N$	338-83-0	521.069			130	1.822^{4}	1.279^{25}	
8730	1*H*-Perimidine		$C_{11}H_8N_2$	204-02-4	168.195	grn cry (dil al)	223.0				i H_2O; s EtOH, eth, ace, bz; sl DMSO
8731	Permethrin		$C_{21}H_{20}Cl_2O_3$	52645-53-1	391.288	cry or ye liq	34	$200^{0.01}$	1.23^{20}		i H_2O; s os
8732	Peroxyacetic acid	Ethaneperoxoic acid	$C_2H_4O_3$	79-21-0	76.051	liq	-0.2	110	1.226^{15}	1.3974^{20}	vs H_2O, eth, sulf; s EtOH
8733	Peroxypropanoic acid	Propaneperoxoic acid	$C_3H_6O_3$	4212-43-5	90.078			exp 119.7		1.4148^{15}	
8734	Perphenazine		$C_{21}H_{26}ClN_3OS$	58-39-9	403.968		97				
8735	Perthane	Ethane, 1,1-dichloro-2,2-bis(*p*-ethylphenyl)-	$C_{18}H_{20}Cl_2$	72-56-0	307.258		56				
8736	Perylene	Dibenz[de,kl]anthracene	$C_{20}H_{12}$	198-55-0	252.309	gold-br, ye pl (bz, HOAc)	277.76		1.35^{25}		i H_2O; sl EtOH, eth; vs ace, chl; s bz
8737	Peucedanin	3-Methoxy-2-isopropyl-7*H*-furo[3,2-g][1]benzopyran-7-one	$C_{15}H_{14}O_4$	133-26-6	258.270	pr or pl (bz-peth)	85	278^{17}			sl H_2O, bz; s EtOH, eth; vs chl, CS_2
8738	Phalloidin		$C_{35}H_{48}N_8O_{11}S$	17466-45-4	788.868	nd (w)	281 (hyd)				s EtOH, MeOH, py
8739	Phalloin		$C_{35}H_{48}N_8O_{10}S$	28227-92-1	772.869	cry (w)	250 dec				
8740	α-Phellandrene	2-Methyl-5-(1-methylethyl)-1,3-cyclohexadiene	$C_{10}H_{16}$	99-83-2	136.234		238	174.9	0.8410^{20}	1.471^{25}	i H_2O; s eth
8741	β-Phellandrene	*p*-Mentha-1(7),2-diene	$C_{10}H_{16}$	555-10-2	136.234			171.5	0.8520^{20}	1.4788^{20}	i H_2O, EtOH; s eth
8742	9-Phenanthrenamine		$C_{14}H_{11}N$	947-73-9	193.244	lt ye cry (al)	138.3	sub			sl eth, bz, chl
8743	Phenanthrene		$C_{14}H_{10}$	85-01-8	178.229	mcl pl (al), lf (sub)	99.24	340	0.9800^{4}	1.5943	i H_2O; s EtOH, eth, ace, bz, CS_2
8744	9,10-Phenanthrenedione	Phenanthrenequinone	$C_{14}H_8O_2$	84-11-7	208.213	oran nd (to) oran-red pl (sub)	209		1.405^{22}		i H_2O; sl EtOH, bz; s eth
8745	Phenanthridine		$C_{13}H_9N$	229-87-8	179.217	nd (dil al)	107.4	348.9			sl H_2O; vs EtOH, eth, bz, CS_2; s ace
8746	1,7-Phenanthroline		$C_{12}H_8N_2$	230-46-6	180.205	pl (anh), nd (w+2)	78	360			s H_2O; vs EtOH; i eth, bz, lig
8747	1,10-Phenanthroline	*o*-Phenanthroline	$C_{12}H_8N_2$	66-71-7	180.205	wh nd (bz) cry (w+1)	117	>300			vs H_2O; s EtOH, ace, bz; i peth
8748	4,7-Phenanthroline		$C_{12}H_8N_2$	230-07-9	180.205	nd (w)	177	sub 100			s H_2O, lig; vs EtOH; sl eth, bz, CS_2



Perfluorodecalin



Perfluorodecane



Perfluorodimethoxymethane



Perfluoro-2,3-dimethylbutane



Perfluoroethyl ethyl ether



Perfluoroethyl 2,2,2-trifluoroethyl ether



Perfluoroheptane



Perfluoro-1-heptene



Perfluorohexane



Perfluoro-1-hexene



Perfluoroisobutane



Perfluoroisobutene



Perfluoroisopropyl methyl ether



Perfluoromethylcyclohexane



Perfluoro-2-methylpentane



Perfluoro-3-methylpentane



Perfluoronaphthalene



Perfluorononane



Perfluorooctane



Perfluorooctylsulfonyl fluoride



Perfluorooxetane



Perfluoropentane



Perfluoropropane



Perfluoropropene



Perfluoropropyl methyl ether



Perfluoropyridine



Perfluorotoluene



Perfluorotripropylamine



1*H*-Perimidine



Permethrin



Peroxyacetic acid



Peroxypropanoic acid



Perphenazine



Perthane



Perylene



Peucedanin



Phalloidin



Phalloin



α-Phellandrene



β-Phellandrene



9-Phenanthrenamine



Phenanthrene


9,10-Phenanthrenedione



Phenanthridine



1,7-Phenanthroline



1,10-Phenanthroline



4,7-Phenanthroline


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8749	1,10-Phenanthroline monohydrate	*o*-Phenanthroline monohydrate	$C_{12}H_{10}N_2O$	5144-89-8	198.219	wh cry pow	93				s EtOH, ace; sl bz
8750	Phenazine	Dibenzopyrazine	$C_{12}H_8N_2$	92-82-0	180.205	ye-red nd (HOAc)	176.5				sl H_2O, eth; s bz, EtOH
8751	2,3-Phenazinediamine	2,3-Diaminophenazine	$C_{12}H_{10}N_4$	655-86-7	210.234	ye nd	264	sub			vs bz, EtOH
8752	1-Phenazinol	Hemipyocyanine	$C_{12}H_8N_2O$	528-71-2	196.204	ye nd (bz, dil MeOH)	158	sub			sl H_2O, EtOH; s bz, py, dil alk
8753	Phenazopyridine	2,6-Diamino-3-phenylazopyridine	$C_{11}H_{11}N_5$	94-78-0	213.239	red cry	139				
8754	Phenazopyridine hydrochloride	3-(Phenylazo)-2,6-pyridinediamine, monohydrochloride	$C_{11}H_{12}ClN_5$	136-40-3	249.700	ye-red cry					sl H_2O, EtOH; i bz, ace; s HOAc
8755	Phencarbamide		$C_{19}H_{24}N_2OS$	3735-90-8	328.471		48.5	$121^{0.01}$			vs eth, chl, MeOH, peth
8756	Phendimetrazine	3,4-Dimethyl-2-phenylmorpholine	$C_{12}H_{17}NO$	634-03-7	191.269			134^{12}, $78^{0.35}$			
8757	Phenethicillin potassium		$C_{17}H_{19}KN_2O_5S$	132-93-4	402.506	cry (ace)	235				s H_2O
8758	Phenicin		$C_{14}H_{10}O_6$	128-68-7	274.225	ye-br (al)	230.5				sl H_2O; vs EtOH, chl, HOAc
8759	Phenindamine		$C_{19}H_{19}N$	82-88-2	261.361	cry	91		1.17		
8760	Phenmedipham		$C_{16}H_{16}N_2O_4$	13684-63-4	300.309		143				
8761	Phenobarbital	5-Ethyl-5-phenyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	$C_{12}H_{12}N_2O_3$	50-06-6	232.234	pl (w)	174				i H_2O, bz; s EtOH, eth; sl DMSO
8762	Phenol	Hydroxybenzene	C_6H_6O	108-95-2	94.111		40.89	181.87	1.0545^{45}	1.5408^{41}	s H_2O, EtOH; vs eth; msc ace, bz
8763	Phenolphthalein	3,3-Bis(4-hydroxyphenyl)-1(3*H*)-isobenzofuranone	$C_{20}H_{14}O_4$	77-09-8	318.323	wh orth nd	262.5		1.277^{32}		i H_2O, bz; vs EtOH, ace; s eth, chl
8764	Phenolphthalin	2-[Bis(4-hydroxyphenyl)methyl] benzoic acid	$C_{20}H_{16}O_4$	81-90-3	320.339	nd (w)	230.5				vs eth, EtOH
8765	Phenolphthalol		$C_{20}H_{18}O_3$	81-92-5	306.355	cry (dil al)	201.5				
8766	Phenol Red	Phenolsulfonphthalein	$C_{19}H_{14}O_5S$	143-74-8	354.376	dk red nd or pl	>300				sl H_2O, EtOH, ace, bz; i eth, chl
8767	10*H*-Phenothiazine	Thiodiphenylamine	$C_{12}H_9NS$	92-84-2	199.271	ye pr (al) ye lf or pl (tol)	187.5	371			vs ace, bz, eth, EtOH
8768	Phenothrin		$C_{23}H_{26}O_3$	26002-80-2	350.450	col liq			1.061^{25}	1.5483^{25}	i H_2O; s ace, xyl
8769	10*H*-Phenoxazine		$C_{12}H_9NO$	135-67-1	183.205	lf (dil al, bz)	156	dec			vs bz, eth, EtOH
8770	Phenoxyacetic acid		$C_8H_8O_3$	122-59-8	152.148	nd or pl (w)	98.5	dec 285			s H_2O; vs EtOH, eth, bz, CS_2
8771	Phenoxyacetyl chloride		$C_8H_7ClO_2$	701-99-5	170.594			225.5			s eth
8772	Phenoxyacetylene		C_8H_6O	4279-76-9	118.133		-36	61^{25}	1.0614^{20}	1.5125^{20}	vs eth, EtOH
8773	2-Phenoxyaniline		$C_{12}H_{11}NO$	2688-84-8	185.221	cry (lig)	45.8	308; 172^{14}			s EtOH; s eth, ace, bz
8774	3-Phenoxyaniline		$C_{12}H_{11}NO$	3586-12-7	185.221	pr (lig)	37	315; 180^{10}	1.1583^{25}		s EtOH, eth, ace, bz; sl lig
8775	4-Phenoxyaniline		$C_{12}H_{11}NO$	139-59-3	185.221	nd (w), cry (dil al)	85.5				s H_2O; vs EtOH, eth; sl lig
8776	3-Phenoxybenzaldehyde		$C_{13}H_{10}O_2$	39515-51-0	198.217		14.0	169^{11}, $140^{0.1}$	1.147^{25}	1.5954^{20}	
8777	Phenoxybenzamine		$C_{18}H_{22}ClNO$	59-96-1	303.827		39				s bz
8778	Phenoxybenzamine hydrochloride		$C_{18}H_{23}Cl_2NO$	63-92-3	340.288		139				sl H_2O; s EtOH
8779	2-Phenoxybenzoic acid		$C_{13}H_{10}O_3$	2243-42-7	214.216	lf (dil al)	113	355	1.1553^{50}		i H_2O; vs EtOH, eth; s chl
8780	3-Phenoxybenzoic acid		$C_{13}H_{10}O_3$	3739-38-6	214.216	nd (aq al)	145.8				i H_2O; s EtOH, eth
8781	4-Phenoxybenzoic acid		$C_{13}H_{10}O_3$	2215-77-2	214.216	pr (chl)	161				sl H_2O; s EtOH, eth, chl
8782	2-Phenoxyethanol		$C_8H_{10}O_2$	122-99-6	138.164	oil	14	245	1.102^{22}	1.534^{20}	i H_2O; s EtOH, eth, chl, alk
8783	2-Phenoxyethyl acrylate	Phenyl Cellosolve acrylate	$C_{11}H_{12}O_3$	48145-04-6	192.211			110^2	1.090^{25}		vs ace, eth, chl
8784	2-Phenoxyethyl butanoate		$C_{12}H_{16}O_3$	23511-70-8	208.253			$251; 88^2$	1.0388^{21}		vs ace, eth, EtOH
8785	3-Phenoxyphenol		$C_{12}H_{10}O_2$	713-68-8	186.206			175^7			
8786	4-Phenoxyphenol		$C_{12}H_{10}O_2$	831-82-3	186.206		84.0				
8787	2-(3-Phenoxyphenyl)propanoic acid, (±)	Fenoprofen	$C_{15}H_{14}O_3$	31879-05-7	242.270	visc oil		$170^{0.11}$		1.5742^{25}	
8788	3-Phenoxy-1,2-propanediol	Phenylglyceryl ether	$C_9H_{12}O_3$	538-43-2	168.189	nd (eth, peth)	67.5	200^{22}	1.225^{20}		vs H_2O, bz, eth, EtOH
8789	2-Phenoxypropanoic acid		$C_9H_{10}O_3$	940-31-8	166.173	nd (w)	115.5	$266; 105^5$	1.1865^{20}	1.5184^{20}	
8790	2-Phenoxy-1-propanol		$C_9H_{12}O_2$	4169-04-4	152.190			244	0.9801^{25}	1.4760^{25}	s EtOH, eth
8791	1-Phenoxy-2-propanol		$C_9H_{12}O_2$	770-35-4	152.190			$233; 134^{20}$	1.0622^{20}	1.5232^{20}	
8792	1-Phenoxy-2-propanone	Phenoxyacetone	$C_9H_{10}O_2$	621-87-4	150.174			229.5	1.0903^{20}	1.5228^{20}	s eth, ace



H_2O
1,10-Phenanthroline monohydrate



Phenazine



2,3-Phenazinediamine



1-Phenazinol



Phenazopyridine



Phenazopyridine hydrochloride



Phencarbamide



Phendimetrazine



Phenethicillin potassium



Phenicin



Phenindamine



Phenmedipham



Phenobarbital



Phenol



Phenolphthalein



Phenolphthalin



Phenolphthalol



Phenol Red



10*H*-Phenothiazine



Phenothrin



10*H*-Phenoxazine



Phenoxyacetic acid



Phenoxyacetyl chloride



Phenoxyacetylene



2-Phenoxyaniline



3-Phenoxyaniline



4-Phenoxyaniline



3-Phenoxybenzaldehyde



Phenoxybenzamine



Phenoxybenzamine hydrochloride



2-Phenoxybenzoic acid



3-Phenoxybenzoic acid



4-Phenoxybenzoic acid



2-Phenoxyethanol



2-Phenoxyethyl acrylate



2-Phenoxyethyl butanoate



3-Phenoxyphenol



4-Phenoxyphenol



2-(3-Phenoxyphenyl)propanoic acid, (±)


3-Phenoxy-1,2-propanediol



2-Phenoxypropanoic acid



2-Phenoxy-1-propanol



1-Phenoxy-2-propanol



1-Phenoxy-2-propanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8793	2-Phenoxypropanoyl chloride		$C_9H_9ClO_2$	122-35-0	184.619			147; 116[10]	1.1865[20]	1.5178[20]	s eth
8794	Phenprocoumon	3-(α-Ethylbenzyl)-4-hydroxycoumarin	$C_{18}H_{16}O_3$	435-97-2	280.318	pr (MeOH aq)	179				
8795	Phenthoate		$C_{12}H_{17}O_4PS_2$	2597-03-7	320.364	ye oil		123[0.01]			sl H_2O; s hx
8796	Phentolamine		$C_{17}H_{19}N_3O$	50-60-2	281.352		175				
8797	Phenyl acetate		$C_8H_8O_2$	122-79-2	136.149			196; 75[8]	1.0780[20]	1.5035[20]	sl H_2O; msc EtOH, eth, chl; s ctc
8798	2-Phenylacetophenone		$C_{14}H_{12}O$	451-40-1	196.244	pl (al)	60	320	1.201[0]		sl H_2O; s EtOH, eth, ctc, chl
8799	*N*-(Phenylacetyl)-7-aminodeacetoxycephalosporanic acid	7-Phenylacetamidodeacetoxycephalosporanic acid	$C_{16}H_{16}N_2O_4S$	27255-72-7	332.374	cry (2-PrOH/peth)	200				
8800	Phenylacetylene	Ethynylbenzene	C_8H_6	536-74-3	102.134	liq	-44.8	143	0.9300[20]	1.5470[20]	i H_2O; msc EtOH, eth; s ace; sl chl
8801	(*N*-Phenylacetyl)glycine	Phenaceturic acid	$C_{10}H_{11}NO_3$	500-98-1	193.199	lf (EtOH)	143				
8802	Phenyl 2-(acetyloxy)benzoate	Phenyl acetylsalicylate	$C_{15}H_{12}O_4$	134-55-4	256.254		96				
8803	(Phenylacetyl)urea	Phenacemide	$C_9H_{10}N_2O_2$	63-98-9	178.187	cry (al)	215				vs bz, eth, EtOH
8804	9-Phenylacridine		$C_{19}H_{13}N$	602-56-2	255.313	ye nd, lf (al)	184	404			i H_2O; sl EtOH; s eth; vs bz
8805	*L*-Phenylalaninamide	α-Aminobenzenepropanamide, (*S*)-	$C_9H_{12}N_2O$	5241-58-7	164.203		82				
8806	*L*-Phenylalanine	α-Aminobenzenepropanoic acid, (*S*)	$C_9H_{11}NO_2$	63-91-2	165.189	pr (w)	283 dec				sl H_2O; i EtOH, eth, bz, acid
8807	*L*-Phenylalanine, ethyl ester	Ethyl 2-amino-3-phenylpropionate	$C_{11}H_{15}NO_2$	3081-24-1	193.243		136	148[13]	1.065[15]		sl H_2O
8808	*L*-Phenylalanylglycine		$C_{11}H_{14}N_2O_3$	721-90-4	222.240		262 dec				s H_2O
8809	3-Phenylallyl acetate		$C_{11}H_{12}O_2$	103-54-8	176.212			123[5]			
8810	5-Phenyl-5-allyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione	Phenallymal	$C_{13}H_{12}N_2O_3$	115-43-5	244.245		156.5				sl H_2O, bz, DMSO; vs EtOH, eth; i lig
8811	4-(Phenylamino)benzenesulfonic acid	*N*-Phenylsulfanilic acid	$C_{12}H_{11}NO_3S$	101-57-5	249.285	pl (al-eth)	206				vs H_2O, EtOH
8812	2-(Phenylamino)benzoic acid	*N*-Phenylanthranilic acid	$C_{13}H_{11}NO_2$	91-40-7	213.232	lf (al)	183.5				i H_2O; vs EtOH; sl eth, bz
8813	Phenyl 4-amino-3-hydroxybenzoate	Phenyl *p*-aminosalicylate	$C_{13}H_{11}NO_3$	133-11-9	229.231		153				
8814	3-(Phenylamino)phenol		$C_{12}H_{11}NO$	101-18-8	185.221	lf (w)	81.5	340			sl H_2O; vs EtOH, eth, ace; s bz, acid
8815	4-(Phenylamino)phenol		$C_{12}H_{11}NO$	122-37-2	185.221	lf (w)	73	330			sl H_2O; vs EtOH, eth, bz, chl; s acid
8816	9-Phenylanthracene		$C_{20}H_{14}$	602-55-1	254.325	bl lf (al) (HOAc)	156	417			i H_2O; s EtOH, eth, bz, chl, CS_2
8817	Phenylarsonous diiodide		$C_6H_5AsI_2$	6380-34-3	405.835		15	205[14], 185[10]	1.6264[15]		
8818	4-(Phenylazo)-1,3-benzenediamine monohydrochloride	Chrysoidine hydrochloride	$C_{12}H_{13}ClN_4$	532-82-1	248.711	red-br cry pow	118.5				vs ace
8819	4-(Phenylazo)-1,3-benzenediol		$C_{12}H_{10}N_2O_2$	2051-85-6	214.219	dk red nd (dil al)	170				i H_2O; vs EtOH, eth, bz, HOAc
8820	4-Phenylazodiphenylamine	*N*-Phenyl-4-(phenylazo) benzenamine	$C_{18}H_{15}N_3$	101-75-7	273.332	ye pl or pr	84.0				i H_2O; vs EtOH, eth, lig
8821	4-(Phenylazo)-1-naphthalenamine	α-Naphthyl Red	$C_{16}H_{13}N_3$	131-22-6	247.294	red-viol cry (EtOH)	123				s EtOH, dil HCl, bz
8822	1-(Phenylazo)-2-naphthalenamine	Yellow AB	$C_{16}H_{13}N_3$	85-84-7	247.294	red pl (al)	103				vs EtOH, HOAc
8823	1-(Phenylazo)-2-naphthol	Sudan I	$C_{16}H_{12}N_2O$	842-07-9	248.278	ye cry	132				
8824	4-(Phenylazo)phenol		$C_{12}H_{10}N_2O$	1689-82-3	198.219	ye lf (bz) oran pr (al)	155	225[20] dec			i H_2O; vs EtOH, eth; s bz, con sulf
8825	1-[[4-(Phenylazo)phenyl]azo]-2-naphthol	Sudan III	$C_{22}H_{16}N_4O$	85-86-9	352.388	br lf (grn lustre) (HOAc)	195				i H_2O; s EtOH, eth, ace, bz, xyl, chl
8826	*N*-Phenylbenzamide	Benzanilide	$C_{13}H_{11}NO$	93-98-1	197.232	lf (al)	163	sub 117	1.315[25]		i H_2O; sl EtOH, eth, HOAc
8827	α-Phenylbenzeneacetaldehyde		$C_{14}H_{12}O$	947-91-1	196.244			dec 315; 157[7]	1.1061[21]	1.5920[21]	i H_2O; vs EtOH, eth, bz
8828	α-Phenylbenzeneacetic acid	Diphenylacetic acid	$C_{14}H_{12}O_2$	117-34-0	212.244	nd (w), lf (al)	147.29	194[25]	1.257[15]		sl H_2O; vs EtOH; s eth, chl
8829	α-Phenylbenzeneacetonitrile		$C_{14}H_{11}N$	86-29-3	193.244	pr (eth), lf (dil al)	74.3	184[16]			s EtOH, chl; vs eth; sl lig
8830	α-Phenylbenzeneacetyl chloride		$C_{14}H_{11}ClO$	1871-76-7	230.689		56.5	170[16]			s lig



2-Phenoxypropanoyl chloride



Phenprocoumon



Phenthoate



Phentolamine



Phenyl acetate



2-Phenylacetophenone



N-(Phenylacetyl)-7-aminodeacetoxycephalosporanic acid



Phenylacetylene



(*N*-Phenylacetyl)glycine



Phenyl 2-(acetyloxy)benzoate



(Phenylacetyl)urea



9-Phenylacridine



L-Phenylalaninamide



L-Phenylalanine



L-Phenylalanine, ethyl ester



L-Phenylalanylglycine



3-Phenylallyl acetate



5-Phenyl-5-allyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione



4-(Phenylamino)benzenesulfonic acid



2-(Phenylamino)benzoic acid



Phenyl 4-amino-3-hydroxybenzoate



3-(Phenylamino)phenol



4-(Phenylamino)phenol



9-Phenylanthracene



Phenylarsonous diiodide



4-(Phenylazo)-1,3-benzenediamine monohydrochloride



4-(Phenylazo)-1,3-benzenediol



4-Phenylazodiphenylamine



4-(Phenylazo)-1-naphthalenamine



1-(Phenylazo)-2-naphthalenamine



1-(Phenylazo)-2-naphthol



4-(Phenylazo)phenol



1-[[4-(Phenylazo)phenyl]azo]-2-naphthol


N-Phenylbenzamide



α-Phenylbenzeneacetaldehyde



α-Phenylbenzeneacetic acid



α-Phenylbenzeneacetonitrile



α-Phenylbenzeneacetyl chloride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8831	*N*-Phenylbenzenecarbothioamide		$C_{13}H_{11}NS$	636-04-4	213.298	ye pl or pr (al)	102	dec			i H_2O; vs EtOH; s eth, bz, chl; sl lig
8832	*N*-Phenyl-1,2-benzenediamine		$C_{12}H_{12}N_2$	534-85-0	184.236	nd(w)	79.5	313			sl H_2O, lig; s ace, bz, chl
8833	*N*-Phenyl-1,4-benzenediamine	*p*-Aminodiphenylamine	$C_{12}H_{12}N_2$	101-54-2	184.236	nd(al)	66	354			sl H_2O, chl; vs EtOH; s eth, lig
8834	α-Phenylbenzeneethanamine		$C_{14}H_{15}N$	25611-78-3	197.276			311; 175[15]	1.031[15]		vs eth, EtOH
8835	α-Phenylbenzeneethanol		$C_{14}H_{14}O$	614-29-9	198.260	nd (peth-bz)	67	177[15]	1.0360[70]		
8836	α-Phenylbenzenemethanamine	Benzhydrylamine	$C_{13}H_{13}N$	91-00-9	183.249	hex pl	34	304; 176[23]	1.0633[20]	1.5963	sl H_2O; s ace
8837	α-Phenylbenzenemethanimine		$C_{13}H_{11}N$	1013-88-3	181.233			282	1.0847[19]	1.6191[19]	vs eth
8838	β-Phenylbenzenepropanoic acid		$C_{15}H_{14}O_2$	606-83-7	226.271	nd (dil al)	156.0				sl H_2O; vs EtOH; s eth, ace
8839	2-Phenylbenzimidazole	Phenzidole	$C_{13}H_{10}N_2$	716-79-0	194.231	pl (HOAc) (al-w) nd (bz, w)	293				sl H_2O, bz; s EtOH, chl, HOAc
8840	Phenyl benzoate		$C_{13}H_{10}O_2$	93-99-2	198.217	mcl pr (eth-al)	71	314	1.235[20]		i H_2O; s EtOH, eth, chl
8841	2-Phenylbenzoic acid		$C_{13}H_{10}O_2$	947-84-2	198.217	lf (dil al)	114.3	343.5			i H_2O; vs EtOH, bz, HOAc
8842	4-Phenylbenzoic acid		$C_{13}H_{10}O_2$	92-92-2	198.217	nd (bz, al)	228	sub			i H_2O; s EtOH, eth, bz
8843	2-Phenyl-4*H*-1-benzopyran-4-one	Flavone	$C_{15}H_{10}O_2$	525-82-6	222.239	nd (lig), cry (30% al)	100				i H_2O; s EtOH, eth, ace, bz
8844	3-Phenyl-4*H*-1-benzopyran-4-one	Isoflavone	$C_{15}H_{10}O_2$	574-12-9	222.239		148				
8845	2-Phenylbenzothiazole		$C_{13}H_9NS$	883-93-2	211.282	nd (dil al)	115	371			i H_2O; s EtOH, eth, CS_2
8846	*N*-Phenyl-*N*-benzylbenzenemethanamine		$C_{20}H_{19}N$	91-73-6	273.372		69	226[10]	1.0444[80]	1.6065[80]	i H_2O; sl EtOH, HOAc; s eth, bz
8847	Phenyl biguanide	*N*-Phenylimidodicarbonimidic diamide	$C_8H_{11}N_5$	102-02-3	177.207		143				
8848	2-Phenyl-1,3-butadiene		$C_{10}H_{10}$	2288-18-8	130.186			60[17]	0.925[20]	1.5489[20]	i H_2O; s eth, bz, chl
8849	*N*-Phenylbutanamide		$C_{10}H_{13}NO$	1129-50-6	163.216	mcl pr (al, bz, eth)	97	189[15]	1.134[25]		i H_2O; vs EtOH, eth; sl chl
8850	Phenylbutanedioic acid, (±)		$C_{10}H_{10}O_4$	10424-29-0	194.184	lf or nd (w)	168	dec			sl H_2O, chl; vs EtOH, eth, ace; i bz
8851	1-Phenyl-1,3-butanedione		$C_{10}H_{10}O_2$	93-91-4	162.185	pr	56	261.5	1.0599[74]	1.5678[78]	i H_2O; s eth; sl chl
8852	Phenyl butanoate	Phenyl butyrate	$C_{10}H_{12}O_2$	4346-18-3	164.201			225	1.0382[15]		i H_2O; s EtOH, eth
8853	1-Phenyl-1-butanone		$C_{10}H_{12}O$	495-40-9	148.201		12	228.5	0.988[20]	1.5203[20]	i H_2O; msc EtOH, eth; vs ace; s ctc
8854	1-Phenyl-2-butanone		$C_{10}H_{12}O$	1007-32-5	148.201			228; 111[16]	0.9877[20]		i H_2O; s EtOH, ctc; msc eth; vs ace
8855	4-Phenyl-2-butanone		$C_{10}H_{12}O$	2550-26-7	148.201	liq	-13	233.5	0.9849[22]	1.511[22]	i H_2O; s EtOH, eth, ctc; vs ace
8856	Phenylbutazone		$C_{19}H_{20}N_2O_2$	50-33-9	308.374		105				
8857	2-Phenyl-1-butene	α-Ethylstyrene	$C_{10}H_{12}$	2039-93-2	132.202			182	0.887[25]	1.5288[20]	
8858	1-Phenyl-2-buten-1-one		$C_{10}H_{10}O$	495-41-0	146.185		20.5	111[9]	1.025[15]	1.5626[18]	
8859	*trans*-4-Phenyl-3-buten-2-one	Benzilideneacetone	$C_{10}H_{10}O$	1896-62-4	146.185	pl	41.5	261	1.0097[45]	1.5836[45]	i H_2O; vs EtOH; s eth, ace, bz; sl peth
8860	4-Phenyl-3-butyn-2-one		$C_{10}H_8O$	1817-57-8	144.170		4.5	79[2]	1.0215[20]	1.5762[20]	
8861	Phenyl chloroacetate		$C_8H_7ClO_2$	620-73-5	170.594	nd or pl (al)	44.5	232.5	1.2202[44]	1.5146[44]	i H_2O; vs EtOH, eth
8862	Phenyl chloroformate		$C_7H_5ClO_2$	1885-14-9	156.567			71[9]			
8863	4-Phenyl-2-chlorophenol	3-Chloro-(1,1'-biphenyl)-4-ol	$C_{12}H_9ClO$	92-04-6	204.651	wh-ye cry	77	161[7]			
8864	2-Phenyl-2,5-cyclohexadiene-1,4-dione		$C_{12}H_8O_2$	363-03-1	184.191	ye lf (peth, al)	114				sl H_2O; s EtOH, bz, peth; vs chl
8865	4-Phenylcyclohexanone		$C_{12}H_{14}O$	4894-75-1	174.238	cry (peth)	79	158[12]			
8866	1-(1-Phenylcyclohexyl)piperidine	Phencyclidine	$C_{17}H_{25}N$	77-10-1	243.388		46.5	136[1.0]			
8867	3-Phenyl-2-cyclopenten-1-one		$C_{11}H_{10}O$	3810-26-2	158.196	liq	-23	234.2	0.9711[20]	1.5440[20]	s EtOH, ace, chl; sl eth
8868	*N*-Phenyl-*N*,*N*-diethanolamine		$C_{10}H_{15}NO_2$	120-07-0	181.232		57	200[10]	1.201[60]		vs ace, bz, eth, EtOH
8869	2-Phenyl-1,3-dioxane		$C_{10}H_{12}O_2$	772-01-0	164.201	nd (peth)	41	253	1.6053[60]		vs EtOH, eth
8870	4-Phenyl-1,3-dioxane		$C_{10}H_{12}O_2$	772-00-9	164.201			247	1.1038[20]	1.5306[18]	i H_2O; s os
8871	1-Phenyl-1-dodecanone		$C_{18}H_{28}O$	1674-38-0	260.414		47	201[9], 181[5]	0.8794[18]	1.4700[18]	i H_2O; s ace; sl ctc



N-Phenylbenzenecarbothioamide



N-Phenyl-1,2-benzenediamine



N-Phenyl-1,4-benzenediamine



α-Phenylbenzeneethanamine



α-Phenylbenzeneethanol



α-Phenylbenzenemethanamine



α-Phenylbenzenemethanimine



β-Phenylbenzenepropanoic acid



2-Phenylbenzimidazole



Phenyl benzoate



2-Phenylbenzoic acid



4-Phenylbenzoic acid



2-Phenyl-4*H*-1-benzopyran-4-one



3-Phenyl-4*H*-1-benzopyran-4-one



2-Phenylbenzothiazole



N-Phenyl-*N*-benzylbenzenemethanamine



Phenyl biguanide



2-Phenyl-1,3-butadiene



N-Phenylbutanamide



Phenylbutanedioic acid, (±)



1-Phenyl-1,3-butanedione



Phenyl butanoate



1-Phenyl-1-butanone



1-Phenyl-2-butanone



4-Phenyl-2-butanone



Phenylbutazone



2-Phenyl-1-butene



1-Phenyl-2-buten-1-one



trans-4-Phenyl-3-buten-2-one



4-Phenyl-3-butyn-2-one



Phenyl chloroacetate



Phenyl chloroformate



4-Phenyl-2-chlorophenol



2-Phenyl-2,5-cyclohexadiene-1,4-dione



4-Phenylcyclohexanone



1-(1-Phenylcyclohexyl)piperidine


3-Phenyl-2-cyclopenten-1-one



N-Phenyl-*N*,*N*-diethanolamine



2-Phenyl-1,3-dioxane



4-Phenyl-1,3-dioxane



1-Phenyl-1-dodecanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8872	1-Phenyl-1,2-ethanediol	Styrene glycol	$C_8H_{10}O_2$	93-56-1	138.164	nd (lig)	67.5	273			vs H_2O, eth, bz, EtOH; sl lig
8873	*N*-Phenylethanolamine		$C_8H_{11}NO$	122-98-5	137.179			279.5; 150^{10}	1.0945^{20}	1.5760^{20}	sl H_2O; vs EtOH, eth, chl
8874	1-Phenylethanone oxime		C_8H_9NO	613-91-2	135.163	nd (w)	60	245	1.0515^{78}		sl H_2O; vs EtOH, eth, ace, bz; s ctc
8875	2-Phenylethyl acetate		$C_{10}H_{12}O_2$	103-45-7	164.201	liq	-31.1	232.6	1.0883^{20}	1.5171^{20}	vs eth, EtOH
8876	1-Phenylethyl hydroperoxide		$C_8H_{10}O_2$	3071-32-7	138.164	liq		$50^{0.01}$			
8877	*N*-(2-Phenylethyl) imidodicarbonimidic diamide, monohydrochloride	Phenformin hydrochloride	$C_{10}H_{16}ClN_5$	834-28-6	241.721	cry	177.3				s H_2O
8878	2-Phenylethyl 2-methylpropanoate	Benzylcarbinol isobutyrate	$C_{12}H_{16}O_2$	103-48-0	192.254			250; 123^{15}	0.9950^{15}	1.4871^{20}	
8879	2-Phenylethyl phenylacetate		$C_{16}H_{16}O_2$	102-20-5	240.297		26.5	$177^{4.5}$	1.077^{25}		vs EtOH
8880	2-Phenylethyl propanoate	Phenethyl propionate	$C_{11}H_{14}O_2$	122-70-3	178.228	liq		244	1.02^{25}	1.4950^{20}	
8881	2-(2-Phenylethyl)pyridine		$C_{13}H_{13}N$	2116-62-3	183.249	liq	-1.5	289	1.0465^{0}		
8882	*N*-Phenylformamide	Formanilide	C_7H_7NO	103-70-8	121.137	mcl pr (lig-xyl)	46	271	1.1186^{50}		s H_2O, eth, bz; vs EtOH
8883	Phenyl formate		$C_7H_6O_2$	1864-94-4	122.122	liq		178; 82^{15}			
8884	2-Phenylfuran		$C_{10}H_8O$	17113-33-6	144.170			108^{18}, 82^{5}	1.083^{20}	1.5920^{20}	vs ace, bz
8885	Phenyl α-*D*-glucopyranoside		$C_{12}H_{16}O_6$	4630-62-0	256.251		174				
8886	Phenyl glycidyl ether		$C_9H_{10}O_2$	122-60-1	150.174			243	1.1109^{21}	1.5307^{21}	
8887	*N*-Phenylglycine	Phenylaminoacetic acid	$C_8H_9NO_2$	103-01-5	151.163		127.5				vs H_2O, EtOH
8888	1-Phenyl-1-heptanone		$C_{13}H_{18}O$	1671-75-6	190.281	lf	16.4	283.3	0.9516^{20}	1.5060^{20}	vs ace, eth, EtOH
8889	1-Phenyl-1-hexanone		$C_{12}H_{16}O$	942-92-7	176.254	fl	27	265	0.9576^{20}	1.5027^{25}	sl H_2O, ctc; s EtOH, eth, ace
8890	Phenylhydrazine		$C_6H_8N_2$	100-63-0	108.141	mcl pr or pl	20.6	243.5	1.0986^{20}	1.6084^{10}	s H_2O; msc EtOH, eth, bz; vs ace
8891	2-Phenylhydrazinecarboxamide	Phenicarbazide	$C_7H_9N_3O$	103-03-7	151.165		172				sl H_2O, eth, bz, lig; s EtOH, ace
8892	*N*-Phenylhydrazinecarboxamide	4-Phenylsemicarbazide	$C_7H_9N_3O$	537-47-3	151.165	nd (bz), pl (w)	128				sl H_2O; vs EtOH, chl; i eth
8893	Phenylhydrazine monohydrochloride		$C_6H_9ClN_2$	59-88-1	144.601	lf (al)	244 dec	sub			vs H_2O, EtOH
8894	Phenylhydroxylamine	*N*-Hydroxybenzenamine	C_6H_7NO	100-65-2	109.126	nd (w, bz, peth)	83.5				vs bz, eth, EtOH, chl
8895	Phenyl 1-hydroxy-2-naphthalenecarboxylate		$C_{17}H_{12}O_3$	132-54-7	264.275		96				vs bz, EtOH
8896	1-Phenyl-1*H*-imidazole		$C_9H_8N_2$	7164-98-9	144.173		13	276	1.1397^{15}	1.6025^{25}	i H_2O; vs eth, ace, chl
8897	2-Phenyl-1*H*-imidazole		$C_9H_8N_2$	670-96-2	144.173	lf (bz)	149.3	340			vs EtOH
8898	5-Phenyl-2,4-imidazolidinedione	5-Phenylhydantoin	$C_9H_8N_2O_2$	89-24-7	176.172		184.5				
8899	Phenylimidocarbonyl chloride		$C_7H_5Cl_2N$	622-44-6	174.028	liq		210; 105^{30}	1.28^{15}		
8900	2-[(Phenylimino)methyl]phenol		$C_{13}H_{11}NO$	779-84-0	197.232		49.5		1.087^{25}		i H_2O; s EtOH
8901	4-[(Phenylimino)methyl]phenol	*N*-(4-Hydroxybenzilidene)aniline	$C_{13}H_{11}NO$	1689-73-2	197.232		196.0				i H_2O; s EtOH, eth; sl bz, chl
8902	1-Phenyl-1*H*-indene		$C_{15}H_{12}$	1961-96-2	192.256	oil		158^{7}			
8903	2-Phenyl-1*H*-indene-1,3(2*H*)-dione	Phenindione	$C_{15}H_{10}O_2$	83-12-5	222.239	lf (al, bz)	150				i H_2O; s EtOH, eth, ace, bz, MeOH, chl
8904	2-Phenyl-1*H*-indole		$C_{14}H_{11}N$	948-65-2	193.244		190.5	250^{10}			sl H_2O; s eth, bz, chl, HOAc, CS_2
8905	Phenyliodine diacetate	Iodobenzene diacetate	$C_{10}H_{11}IO_4$	3240-34-4	322.096	cry	161				
8906	Phenyl isocyanate		C_7H_5NO	103-71-9	119.121			163; 55^{13}	1.0956^{20}	1.5368^{20}	vs eth; sl chl
8907	2-Phenyl-1*H*-isoindole-1,3(2*H*)-dione		$C_{14}H_9NO_2$	520-03-6	223.227	wh nd (al)	210	sub			i H_2O; sl EtOH; msc chl
8908	Phenyl isopropyl ether	Isopropoxybenzene	$C_9H_{12}O$	2741-16-4	136.190	liq	-33	176.8	0.9408^{25}	1.4975^{20}	s H_2O, EtOH, ace, bz
8909	Phenyl isothiocyanate		C_7H_5NS	103-72-0	135.187	liq	-21	221	1.1303^{20}	1.6492^{23}	i H_2O; s EtOH, eth, ctc
8910	3-Phenyl-2-isoxazolin-5-one		$C_9H_7NO_2$	1076-59-1	161.158		151				sl chl
8911	Phenyl laurate	Phenyl dodecanoate	$C_{18}H_{28}O_2$	4228-00-6	276.414	lf (al)	24.5	210^{15}	0.9354^{30}		vs ace, eth, EtOH
8912	Phenylmagnesium chloride	Chlorophenylmagnesium	C_6H_5ClMg	100-59-4	136.862	cry					reac H_2O; s thf, eth
8913	Phenylmercuric chloride	Chlorophenylmercury	C_6H_5ClHg	100-56-1	313.15	pl (bz)	251				i H_2O; sl EtOH, bz
8914	Phenylmercuric nitrate		$C_6H_5HgNO_3$	55-68-5	339.70		≈181				
8915	4-(Phenylmethoxy)benzaldehyde		$C_{14}H_{12}O_2$	4397-53-9	212.244		73	217^{13}			



1-Phenyl-1,2-ethanediol



N-Phenylethanolamine



1-Phenylethanone oxime



2-Phenylethyl acetate



1-Phenylethyl hydroperoxide



N-(2-Phenylethyl)imidodicarbonimidic diamide, monohydrochloride



2-Phenylethyl 2-methylpropanoate



2-Phenylethyl phenylacetate



2-Phenylethyl propanoate



2-(2-Phenylethyl)pyridine



N-Phenylformamide



Phenyl formate



2-Phenylfuran



Phenyl α-*D*-glucopyranoside



Phenyl glycidyl ether



N-Phenylglycine



1-Phenyl-1-heptanone



1-Phenyl-1-hexanone



Phenylhydrazine



2-Phenylhydrazinecarboxamide



N-Phenylhydrazinecarboxamide



Phenylhydrazine monohydrochloride



Phenylhydroxylamine



Phenyl 1-hydroxy-2-naphthalenecarboxylate



1-Phenyl-1*H*-imidazole



2-Phenyl-1*H*-imidazole



5-Phenyl-2,4-imidazolidinedione



Phenylimidocarbonyl chloride



2-[(Phenylimino)methyl]phenol



4-[(Phenylimino)methyl]phenol



1-Phenyl-1*H*-indene



2-Phenyl-1*H*-indene-1,3(2*H*)-dione



2-Phenyl-1*H*-indole



Phenyliodine diacetate



Phenyl isocyanate



2-Phenyl-1*H*-isoindole-1,3(2*H*)-dione



Phenyl isopropyl ether



Phenyl isothiocyanate



3-Phenyl-2-isoxazolin-5-one


Phenyl laurate



Phenylmagnesium chloride



Phenylmercuric chloride



Phenylmercuric nitrate



4-(Phenylmethoxy)benzaldehyde


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8916	*N*2-[(Phenylmethoxy)carbonyl]-*L*-arginine		$C_{14}H_{20}N_4O_4$	1234-35-1	308.334		174				
8917	*N*-[(Phenylmethoxy)carbonyl]-*L*-aspartic acid		$C_{12}H_{13}NO_6$	1152-61-0	267.234		117.0				
8918	2-(Phenylmethoxy)phenol		$C_{13}H_{12}O_2$	6272-38-4	200.233			205[20], 173[13]	1.154[22]	1.5906[18]	vs eth, EtOH
8919	4-(Phenylmethoxy)phenol	Monobenzone	$C_{13}H_{12}O_2$	103-16-2	200.233	pl (w)	122				sl H_2O; vs EtOH, bz, eth; s ace
8920	*N*-(Phenylmethylene)aniline	Benzylideneaniline	$C_{13}H_{11}N$	538-51-2	181.233	pa ye nd (CS_2) pl (dil al)	54	310	1.038[55]	1.600[100]	i H_2O; s EtOH, eth, NH_3; sl chl
8921	*cis*-α-(Phenylmethylene) benzeneacetic acid	*cis*-α-Phenylcinnamic acid	$C_{15}H_{12}O_2$	91-47-4	224.255	silky needles	174				s H_2O, EtOH, MeOH, eth, bz
8922	*trans*-α-(Phenylmethylene) benzeneacetic acid	*trans*-α-Phenylcinnamic acid	$C_{15}H_{12}O_2$	91-48-5	224.255	prisms	138				vs H_2O; s EtOH, MeOH, eth, bz
8923	*N*-(Phenylmethylene) benzenemethanamine		$C_{14}H_{13}N$	780-25-6	195.260			205[20]			
8924	2-(Phenylmethylene)butanal		$C_{11}H_{12}O$	28467-92-7	160.212		18	243; 157[5]	1.0201[22]	1.578[20]	
8925	*N*-(Phenylmethylene)ethanamine		$C_9H_{11}N$	6852-54-6	133.190			195	0.937[20]	1.5378[15]	i H_2O; s EtOH, eth
8926	2-(Phenylmethylene)heptanal		$C_{14}H_{18}O$	122-40-7	202.292	ye oil	80	174[20]	0.9711[20]	1.5381[20]	i H_2O; s ace, ctc
8927	*N*-(Phenylmethylene)methanamine	Benzylidenemethylamine	C_8H_9N	622-29-7	119.164			185; 92[34]	0.9671[14]	1.5526[20]	s EtOH, eth, ace, chl
8928	2-(Phenylmethylene)octanal	2-Hexyl-3-phenyl-2-propenal	$C_{15}H_{20}O$	101-86-0	216.319	liq	4	252; 169[20]			
8929	3-(Phenylmethylene)-2-pentanone	Methyl α-ethylstyryl ketone	$C_{12}H_{14}O$	3437-89-6	174.238			137[12]	1.0005[22]	1.5650[22]	
8930	*N*-(Phenylmethyl)-1,2-ethanediamine		$C_9H_{14}N_2$	4152-09-4	150.220			130[11]			
8931	Phenylmethyl 4-hydroxybenzoate		$C_{14}H_{12}O_3$	94-18-8	228.243						sl chl
8932	1-Phenyl-2-methyl-2-propanol		$C_{10}H_{14}O$	100-86-7	150.217	nd	24	215	0.9787[16]	1.5173[16]	
8933	*N*-(Phenylmethyl)-1*H*-purin-6-amine		$C_{12}H_{11}N_5$	1214-39-7	225.249		232.8				
8934	4-Phenylmorpholine		$C_{10}H_{13}NO$	92-53-5	163.216	cry (al-eth)	58.3				i H_2O, EtOH; vs eth
8935	*N*-Phenyl-1-naphthalenamine	1-Naphthylphenylamine	$C_{16}H_{13}N$	90-30-2	219.281		61				sl H_2O, ctc; s EtOH, eth, bz, HOAc
8936	*N*-Phenyl-2-naphthalenamine	*N*-Phenyl-β-naphthylamine	$C_{16}H_{13}N$	135-88-6	219.281		108	395.5			i H_2O; s EtOH, eth, bz, HOAc; sl chl
8937	1-Phenylnaphthalene		$C_{16}H_{12}$	605-02-7	204.266	cry	45	334	1.096[20]	1.6664[20]	i H_2O; vs EtOH, eth, bz, HOAc; s ctc
8938	2-Phenylnaphthalene		$C_{16}H_{12}$	612-94-2	204.266	lf (al)	103.5	345.5	1.2180[20]		s EtOH, bz, chl, HOAc; vs eth
8939	1-Phenyl-1-octanone		$C_{14}H_{20}O$	1674-37-9	204.308		22.8	285; 164[15]	0.9360[30]		s EtOH, eth
8940	Phenyloxirane	Styrene-7,8-oxide	C_8H_8O	96-09-3	120.149	colorless liq	-35.6	194.1	1.0490[25]	1.5342[20]	i H_2O; s EtOH, eth, chl
8941	3-Phenyloxiranecarboxylic acid, ethyl ester		$C_{11}H_{12}O_3$	121-39-1	192.211			136[5]			
8942	5-Phenyl-2,4-pentadienal		$C_{11}H_{10}O$	13466-40-5	158.196		42.5	160[3], 133[1.0]			i H_2O; msc EtOH, bz; vs eth
8943	1-Phenyl-1,4-pentanedione		$C_{11}H_{12}O_2$	583-05-1	176.212	ye oil		162[12]		1.5250[30]	vs ace
8944	1-Phenyl-1-pentanol		$C_{11}H_{16}O$	583-03-9	164.244			141[25], 102[3]	0.9655[20]	1.4086[25]	vs ace, eth, EtOH
8945	1-Phenyl-1-pentanone		$C_{11}H_{14}O$	1009-14-9	162.228	liq	-9.4	245	0.986[20]	1.5158[20]	i H_2O; vs EtOH, eth; sl ctc
8946	1-Phenyl-1-penten-3-one		$C_{11}H_{12}O$	3152-68-9	160.212	lf (lig)	38.5	142[12]	0.8697[20]	1.5684[20]	sl H_2O, chl; vs EtOH, eth, bz
8947	Phenylphosphine	Monophenylphosphine	C_6H_7P	638-21-1	110.094			160.5	1.001[15]	1.5796[20]	
8948	Phenylphosphinic acid	Benzenephosphinic acid	$C_6H_7O_2P$	1779-48-2	142.093		83.8				s H_2O; vs EtOH; sl eth, chl
8949	Phenylphosphonic acid	Benzenephosphonic acid	$C_6H_7O_3P$	1571-33-1	158.092	lf (w)	160				vs H_2O; s EtOH, eth, ace; i bz
8950	Phenylphosphonic dichloride		$C_6H_5Cl_2OP$	824-72-6	194.983		1	258	1.197[25]	1.5581[25]	sl DMSO
8951	Phenylphosphonothioic dichloride	Dichlorophenylphosphine sulfide	$C_6H_5Cl_2PS$	3497-00-5	211.049			205[130]	1.376[13]		
8952	Phenylphosphonous dichloride	Dichlorophenylphosphine	$C_6H_5Cl_2P$	644-97-3	178.984	liq	-51	225; 142[57]	1.356[20]	1.6030[20]	vs bz
8953	Phenyl phosphorodichloridate	Phenyl dichlorophosphate	$C_6H_5Cl_2O_2P$	770-12-7	210.983	hyg liq		242; 100[5]	1.412[20]	1.5230[20]	
8954	1-Phenylpiperazine		$C_{10}H_{14}N_2$	92-54-6	162.231	pa ye oil		286.5; 161[15]	1.0621[20]	1.5875[20]	i H_2O; msc EtOH, eth; s chl
8955	1-Phenylpiperidine		$C_{11}H_{15}N$	4096-20-2	161.244		4.7	258	0.9944[25]	1.5598[25]	vs EtOH, eth, bz, chl
8956	4-Phenylpiperidine		$C_{11}H_{15}N$	771-99-3	161.244		60.5	257	0.9996[16]		s chl



*N*2-[(Phenylmethoxy)carbonyl]-*L*-arginine



N-[(Phenylmethoxy)carbonyl]-*L*-aspartic acid



2-(Phenylmethoxy)phenol



4-(Phenylmethoxy)phenol



N-(Phenylmethylene)aniline



cis-α-(Phenylmethylene)benzeneacetic acid



trans-α-(Phenylmethylene)benzeneacetic acid



N-(Phenylmethylene)benzenemethanamine



2-(Phenylmethylene)butanal



N-(Phenylmethylene)ethanamine



2-(Phenylmethylene)heptanal



N-(Phenylmethylene)methanamine



2-(Phenylmethylene)octanal



3-(Phenylmethylene)-2-pentanone



N-(Phenylmethyl)-1,2-ethanediamine



Phenylmethyl 4-hydroxybenzoate



1-Phenyl-2-methyl-2-propanol



N-(Phenylmethyl)-1*H*-purin-6-amine



4-Phenylmorpholine



N-Phenyl-1-naphthalenamine



N-Phenyl-2-naphthalenamine



1-Phenylnaphthalene



2-Phenylnaphthalene



1-Phenyl-1-octanone



Phenyloxirane



3-Phenyloxiranecarboxylic acid, ethyl ester



5-Phenyl-2,4-pentadienal



1-Phenyl-1,4-pentanedione



1-Phenyl-1-pentanol



1-Phenyl-1-pentanone



1-Phenyl-1-penten-3-one



Phenylphosphine



Phenylphosphinic acid



Phenylphosphonic acid



Phenylphosphonic dichloride



Phenylphosphonothioic dichloride


Phenylphosphonous dichloride



Phenyl phosphorodichloridate



1-Phenylpiperazine



1-Phenylpiperidine



4-Phenylpiperidine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8957	*N*-Phenylpropanamide		$C_9H_{11}NO$	620-71-3	149.189	pl (eth, al, bz)	105.5	222.2	1.175^{25}		sl H_2O; vs EtOH, eth
8958	1-Phenyl-1,2-propanedione		$C_9H_8O_2$	579-07-7	148.159	ye oil	<20	222; 102^{12}	1.1006^{20}	1.537^{10}	s H_2O, EtOH, eth
8959	1-Phenyl-1,2-propanedione, 2-oxime		$C_9H_9NO_2$	119-51-7	163.173	wh nd (w)	115				
8960	Phenyl propanoate		$C_9H_{10}O_2$	637-27-4	150.174	pr	20	211	1.0436^{25}	1.4980^{20}	i H_2O; vs EtOH, eth; s bz
8961	2-Phenyl-1-propanol		$C_9H_{12}O$	1123-85-9	136.190			121^{26}, 105^{11}	0.975^{25}	1.5582^{2}	i H_2O; s EtOH
8962	1-Phenyl-2-propanol		$C_9H_{12}O$	698-87-3	136.190			125^{25}, 120^{20}	0.991^{20}	1.5190^{20}	
8963	Phenylpropanolamine hydrochloride		$C_9H_{14}ClNO$	154-41-6	187.666		194				vs H_2O; s EtOH; i eth, bz, chl
8964	1-Phenyl-1-propanone	Propiophenone	$C_9H_{10}O$	93-55-0	134.174		18.6	217.5	1.0096^{20}	1.5269^{20}	i H_2O; s EtOH, eth, chl
8965	1-Phenyl-2-propanone	Phenylacetone	$C_9H_{10}O$	103-79-7	134.174	liq	-15	216.5	1.0157^{20}	1.5168^{20}	i H_2O; vs EtOH, eth; msc bz, xyl; s chl
8966	*cis*-3-Phenyl-2-propenenitrile		C_9H_7N	24840-05-9	129.159	liq	-4.4	249; 139^{30}	1.0289^{20}	1.5843^{20}	i H_2O; s EtOH; vs bz
8967	*trans*-3-Phenyl-2-propenenitrile		C_9H_7N	1885-38-7	129.159		22	263.8	1.0304^{20}	1.6013^{20}	i H_2O; s EtOH, ace, ctc
8968	3-Phenyl-2-propenoic anhydride	Cinnamic anhydride	$C_{18}H_{14}O_3$	538-56-7	278.302	nd (bz or al) pt (al)	136				vs bz
8969	*cis*-3-Phenyl-2-propen-1-ol		$C_9H_{10}O$	4510-34-3	134.174	wh nd (eth-peth)	34	257.5	1.0440^{20}	1.5819^{20}	vs eth, EtOH
8970	*trans*-3-Phenyl-2-propen-1-ol		$C_9H_{10}O$	4407-36-7	134.174	wh nd (eth-peth)	34	257.5	1.0440^{20}	1.5819^{20}	sl H_2O, chl; vs EtOH, eth
8971	*trans*-3-Phenyl-2-propen-1-ol acetate	*trans*-Cinnamyl acetate	$C_{11}H_{12}O_2$	21040-45-9	176.212			265; 145^{15}	1.0567^{20}	1.5425^{20}	i H_2O; s EtOH, eth, ace, bz, chl
8972	*trans*-3-Phenyl-2-propenoyl chloride	Cinnamoyl chloride	C_9H_7ClO	17082-09-6	166.604	ye cry	37.5	257.5	1.1617^{45}	1.614^{42}	i H_2O; s EtOH, ctc, lig
8973	3-Phenylpropyl acetate	Benzenepropanol, acetate	$C_{11}H_{14}O_2$	122-72-5	178.228	col liq	-40	69^{1}			
8974	1-Phenyl-2-propylamine, (±)	Amphetamine	$C_9H_{13}N$	300-62-9	135.206	oil		203	0.9306^{25}	1.518^{26}	sl H_2O, eth; s chl, EtOH
8975	1-Phenyl-2-propylamine, (*S*)	Dexamphetamine	$C_9H_{13}N$	51-64-9	135.206	oil	27.5	203.5; 80^{12}	0.949^{15}	1.4704^{20}	sl H_2O; s EtOH, eth
8976	Phenyl propyl ether	Propoxybenzene	$C_9H_{12}O$	622-85-5	136.190	liq	-27	189.9	0.9474^{20}	1.5014^{20}	s EtOH, eth
8977	4-(3-Phenylpropyl)pyridine		$C_{14}H_{15}N$	2057-49-0	197.276			322; 150^{5}	1.024^{25}	1.5616^{25}	vs bz, eth, py, EtOH
8978	3-Phenyl-2-propynal		C_9H_6O	2579-22-8	130.143			127^{28}, 104^{11}	1.0622^{20}	1.6079^{12}	
8979	3-Phenyl-2-propynoic acid	Phenylacetylenecarboxylic acid	$C_9H_6O_2$	637-44-5	146.143	nd (w)	137.5		1.28^{20}		sl H_2O; vs EtOH, eth
8980	3-Phenyl-2-propyn-1-ol		C_9H_8O	1504-58-1	132.159			137^{15}	1.078^{20}	1.5873^{28}	s eth, ace, bz
8981	6-Phenyl-2,4,7-pteridinetriamine	Triamterene	$C_{12}H_{11}N_7$	396-01-0	253.262	ye pl (BuOH)	316				i eth; sl EtOH, chl
8982	1-Phenyl-3-pyrazolidinone		$C_9H_{10}N_2O$	92-43-3	162.187		126				i eth, lig
8983	2-Phenylpyridine		$C_{11}H_9N$	1008-89-5	155.196			271	1.0833^{25}	1.6210^{20}	sl H_2O; msc EtOH, eth
8984	3-Phenylpyridine		$C_{11}H_9N$	1008-88-4	155.196	pa ye oil	164	272		1.6123^{25}	sl H_2O; s EtOH, eth
8985	4-Phenylpyridine		$C_{11}H_9N$	939-23-1	155.196	pl (w)	77.5	281			s H_2O, EtOH, eth
8986	Phenyl-2-pyridinylmethanone		$C_{12}H_9NO$	91-02-1	183.205		42	317	1.1556^{20}		s chl
8987	Phenyl-4-pyridinylmethanone		$C_{12}H_9NO$	14548-46-0	183.205	nd (peth), pl (w)	72	315; 170^{10}			sl H_2O; s EtOH, eth, bz
8988	1-Phenyl-1*H*-pyrrole		$C_{10}H_9N$	635-90-5	143.185	pl (sub), red in air	62	234			i H_2O; s EtOH, eth, ace, bz; vs peth
8989	2-Phenyl-1*H*-pyrrole		$C_{10}H_9N$	3042-22-6	143.185	pl (al, sub)	129	272			i H_2O; vs EtOH, eth, bz, chl; sl lig
8990	1-Phenyl-1*H*-pyrrole-2,5-dione	*N*-Phenylmaleimide	$C_{10}H_7NO_2$	941-69-5	173.169	ye nd (bz-lig)	90.5	162^{12}			vs bz, eth, EtOH
8991	1-Phenylpyrrolidine		$C_{10}H_{13}N$	4096-21-3	147.217		11	119^{12}, 102^{5}	1.018^{20}	1.5813^{20}	s eth
8992	1-Phenyl-2,5-pyrrolidinedione	Succinanil	$C_{10}H_9NO_2$	83-25-0	175.184	mcl pr or nd (w, al)	156	400	1.356^{25}		i H_2O; s EtOH, eth
8993	2-Phenylquinoline		$C_{15}H_{11}N$	612-96-4	205.255	nd (dil al)	86	363; 194^{6}			sl H_2O, peth; vs EtOH, eth, ace, bz
8994	2-Phenyl-4-quinolinecarboxylic acid	Cinchophen	$C_{16}H_{11}NO_2$	132-60-5	249.264	nd	214.5				i H_2O; s EtOH, eth, alk; sl ace, bz
8995	Phenyl salicylate		$C_{13}H_{10}O_3$	118-55-8	214.216		43	173^{12}	1.2614^{30}		i H_2O; vs EtOH, ace, bz; s eth, HOAc
8996	Phenylsilane		C_6H_8Si	694-53-1	108.214			119	0.8681^{20}	1.5125^{20}	i H_2O



N-Phenylpropanamide



1-Phenyl-1,2-propanedione



1-Phenyl-1,2-propanedione, 2-oxime



Phenyl propanoate



2-Phenyl-1-propanol



1-Phenyl-2-propanol



Phenylpropanolamine hydrochloride



1-Phenyl-1-propanone



1-Phenyl-2-propanone



cis-3-Phenyl-2-propenenitrile



trans-3-Phenyl-2-propenenitrile



3-Phenyl-2-propenoic anhydride



cis-3-Phenyl-2-propen-1-ol



trans-3-Phenyl-2-propen-1-ol



trans-3-Phenyl-2-propen-1-ol acetate



trans-3-Phenyl-2-propenoyl chloride



3-Phenylpropyl acetate



1-Phenyl-2-propylamine, (±)



1-Phenyl-2-propylamine, (*S*)



Phenyl propyl ether



4-(3-Phenylpropyl)pyridine



3-Phenyl-2-propynal



3-Phenyl-2-propynoic acid



3-Phenyl-2-propyn-1-ol



6-Phenyl-2,4,7-pteridinetriamine



1-Phenyl-3-pyrazolidinone



2-Phenylpyridine



3-Phenylpyridine



4-Phenylpyridine



Phenyl-2-pyridinylmethanone



Phenyl-4-pyridinylmethanone



1-Phenyl-1*H*-pyrrole



2-Phenyl-1*H*-pyrrole



1-Phenyl-1*H*-pyrrole-2,5-dione



1-Phenylpyrrolidine


1-Phenyl-2,5-pyrrolidinedione



2-Phenylquinoline



2-Phenyl-4-quinolinecarboxylic acid



Phenyl salicylate



Phenylsilane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
8997	1-Phenylsilatrane		$C_{12}H_{17}NO_3Si$	2097-19-0	251.354	pr or nd (ace)	209				
8998	Phenyl stearate		$C_{24}H_{40}O_2$	637-55-8	360.574		52	267^{15}			i H_2O; s EtOH, eth
8999	5'-Phenyl-1,1':3',1''-terphenyl		$C_{24}H_{18}$	612-71-5	306.400	orth nd (al or HOAc)	176	462	1.199^{30}		i H_2O; s EtOH, eth, HOAc; vs bz; sl chl
9000	5-Phenyl-2,4-thiazolediamine	Amiphenazole	$C_9H_9N_3S$	490-55-1	191.252	fl (dil al) br in air	163 dec				
9001	Phenyl-2-thienylmethanone		$C_{11}H_8OS$	135-00-2	188.246	nd (dil al)	56.5	300	1.1890^{54}	1.6181^{54}	i H_2O; s EtOH, eth
9002	*N*-Phenylthioacetamide	Thioacetanilide	C_8H_9NS	637-53-6	151.229	nd (w)	75.5	dec			
9003	Phenyl thiocyanate		C_7H_5NS	5285-87-0	135.187			232.5	1.153^{18}		i H_2O; s EtOH, eth
9004	2-Phenylthiosemicarbazide	2-Phenylhydrazinecarbothioamide	$C_7H_9N_3S$	645-48-7	167.231	pr (al)	200 dec				
9005	4-Phenyl-3-thiosemicarbazide	*N*-Phenylhydrazinecarbothioamide	$C_7H_9N_3S$	5351-69-9	167.231	pl (al)	140 dec				i EtOH, lig; sl bz
9006	Phenylthiourea		$C_7H_8N_2S$	103-85-5	152.217	nd (w), pr (al)	154				sl H_2O; s EtOH, NaOH
9007	3-Phenyl-2-thioxo-4-thiazolidinone	3-Phenylrhodanine	$C_9H_7NOS_2$	1457-46-1	209.288	ye pr (HOAc) nd or pr (al)	194.5				i H_2O; sl EtOH, eth; s ace, chl, HOAc
9008	6-Phenyl-1,3,5-triazine-2,4-diamine	Benzoguanamine	$C_9H_9N_5$	91-76-9	187.201	nd, pl (al)	226.5				s EtOH, eth; sl tfa
9009	*N*-Phenyl-1,3,5-triazine-2,4-diamine	Amanozine	$C_9H_9N_5$	537-17-7	187.201	cry (diox, 50% al)	235.5				
9010	4-Phenyl-1,2,4-triazolidine-3,5-dione		$C_8H_7N_3O_2$	15988-11-1	177.161		205.5				
9011	Phenyltrimethylammonium iodide		$C_9H_{14}IN$	98-04-4	263.118	lf (al)	224				vs H_2O; s EtOH, HOAc; sl ace; i chl
9012	Phenyl(triphenylmethyl)diazene		$C_{25}H_{20}N_2$	981-18-0	348.440		111 dec				
9013	Phenylurea		$C_7H_8N_2O$	64-10-8	136.151	mcl pr (w, al)	147	238	1.302^{25}		sl H_2O, eth, DMSO; s EtOH, AcOEt
9014	*trans*-5-(2-Phenylvinyl)-1,3-benzenediol	Pinosylvin	$C_{14}H_{12}O_2$	22139-77-1	212.244	nd (HOAc)	156				vs ace, bz, chl, HOAc
9015	Phenyl vinyl ether		C_8H_8O	766-94-9	120.149			155.5	0.9770^{20}	1.5224^{20}	i H_2O; vs eth
9016	Phenytoin	5,5-Diphenyl-2,4-imidazolidinedione	$C_{15}H_{12}N_2O_2$	57-41-0	252.268	nd (al)	286				i H_2O; s EtOH, ace; sl eth, bz
9017	Phloretin		$C_{15}H_{14}O_5$	60-82-2	274.269	nd (dil al), cry (ace)	263 dec				sl H_2O, chl; msc EtOH, bz; i eth; s ace
9018	Phorate		$C_7H_{17}O_2PS_3$	298-02-2	260.378		<-15	119$^{0.8}$	1.16^{25}		
9019	Phorbol		$C_{20}H_{28}O_6$	17673-25-5	364.432	cry (EtOH)	250 dec				s H_2O, ace
9020	Phorone		$C_9H_{14}O$	504-20-1	138.206	ye-grn pr	28	197.5	0.8850^{20}	1.4998^{20}	sl H_2O; s EtOH, eth, ace, ctc
9021	Phosalone		$C_{12}H_{15}ClNO_4PS_2$	2310-17-0	367.808		46				
9022	Phosfolan		$C_7H_{14}NO_3PS_2$	947-02-4	255.295		36.5	117$^{0.001}$			vs H_2O, bz, ace; sl eth; s hx
9023	Phosmet		$C_{11}H_{12}NO_4PS_2$	732-11-6	317.321		72	dec			
9024	Phosphamidon		$C_{10}H_{19}ClNO_5P$	13171-21-6	299.689	oil	-45	162$^{1.5}$	1.2132^{25}	1.4718^{25}	msc H_2O; s hx
9025	*N*-Phospho-*L*-arginine		$C_6H_{15}N_4O_5P$	1189-11-3	254.181	cry (ace aq)	177				
9026	*O*-Phosphorylethanolamine	Ethanolamine *O*-phosphate	$C_2H_8NO_4P$	1071-23-4	141.063	cry (EtOH aq)	242				
9027	*O*-Phosphoserine		$C_3H_8NO_6P$	407-41-0	185.073	cry	166 dec				
9028	Phthalazine	2,3-Benzodiazine	$C_8H_6N_2$	253-52-1	130.147		90.5	316			s H_2O, EtOH, bz; sl eth; i lig
9029	Phthalic acid	1,2-Benzenedicarboxylic acid	$C_8H_6O_4$	88-99-3	166.132	pl (w)	230 dec	dec	2.18^{191}		sl H_2O, eth; i chl; s EtOH
9030	Phthalic anhydride		$C_8H_4O_3$	85-44-9	148.116	wh nd (al, bz)	130.8	295	1.527^{4}		sl H_2O, eth; s EtOH, ace, bz
9031	29*H*,31*H*-Phthalocyanine		$C_{32}H_{18}N_8$	574-93-6	514.539	grsh-bl mcl (quinoline)		sub 550			i H_2O, EtOH, eth; s $PhNH_2$
9032	Phthalylsulphathiazole		$C_{17}H_{13}N_3O_5S_2$	85-73-4	403.432		273				i H_2O, eth, chl; sl EtOH; s acid, alk
9033	Physostigmine		$C_{15}H_{21}N_3O_2$	57-47-6	275.347	orth pr (eth, bz)	105.5				sl H_2O; s EtOH, eth, bz, chl
9034	Phytol	3,7,11,15-Tetramethyl-2-hexadecen-1-ol, [*R*-[*R**,*R**-(*E*)]]	$C_{20}H_{40}O$	150-86-7	296.531	oily liq		203^{10}	0.8497^{25}	1.4595^{25}	



1-Phenylsilatrane



Phenyl stearate



5'-Phenyl-1,1':3',1''-terphenyl



5-Phenyl-2,4-thiazolediamine



Phenyl-2-thienylmethanone



N-Phenylthioacetamide



Phenyl thiocyanate



2-Phenylthiosemicarbazide



4-Phenyl-3-thiosemicarbazide



Phenylthiourea



3-Phenyl-2-thioxo-4-thiazolidinone



6-Phenyl-1,3,5-triazine-2,4-diamine



N-Phenyl-1,3,5-triazine-2,4-diamine



4-Phenyl-1,2,4-triazolidine-3,5-dione



Phenyltrimethylammonium iodide



Phenyl(triphenylmethyl)diazene



Phenylurea



trans-5-(2-Phenylvinyl)-1,3-benzenediol



Phenyl vinyl ether



Phenytoin



Phloretin



Phorate



Phorbol



Phorone



Phosalone



Phosfolan



Phosmet



Phosphamidon



N-Phospho-*L*-arginine



O-Phosphorylethanolamine



O-Phosphoserine



Phthalazine



Phthalic acid


Phthalic anhydride



29*H*,31*H*-Phthalocyanine



Phthalylsulphathiazole



Physostigmine



Phytol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9035	Picene	Benzo[a]chrysene	$C_{22}H_{14}$	213-46-7	278.346	lf, pl (xyl, py, sub)	368	519			i H_2O; sl EtOH, bz, chl; s con sulf
9036	Picrolonic acid		$C_{10}H_8N_4O_5$	550-74-3	264.195	ye nd (al)	116	dec			sl H_2O; s EtOH, eth, MeOH
9037	Picropodophyllin		$C_{22}H_{22}O_8$	477-47-4	414.405	col nd (al, bz)	228				vs ace, bz, eth, EtOH
9038	Picrotoxin		$C_{30}H_{34}O_{13}$	124-87-8	602.583	orth lf	203.5				vs py, EtOH
9039	Pilocarpine		$C_{11}H_{16}N_2O_2$	92-13-7	208.257	nd	34	260^{5}			s H_2O, EtOH; sl eth, bz; vs chl; i peth
9040	Pilocarpine, monohydrochloride		$C_{11}H_{17}ClN_2O_2$	54-71-7	244.718	hyg cry	204.5				vs H_2O, EtOH
9041	Pilocarpine, mononitrate		$C_{11}H_{17}N_3O_5$	148-72-1	271.270	wh pow or cry (al)	178				vs H_2O
9042	Pilosine		$C_{16}H_{18}N_2O_3$	13640-28-3	286.325	nd (al)	179				
9043	Pimaric acid	Dextropimaric acid	$C_{20}H_{30}O_2$	127-27-5	302.451	orth (ace) pr (al)	218.5	282^{18}			vs eth, py, EtOH
9044	Pinane	2,6,6-Trimethylbicyclo[3.1.1] heptane	$C_{10}H_{18}$	473-55-2	138.250	oil	-53	169	0.8467^{21}	1.4605^{21}	
9045	*trans*-2-Pinanol	Pinene hydrate	$C_{10}H_{18}O$	35408-04-9	154.249		60	81^{10}			
9046	Pindolol		$C_{14}H_{20}N_2O_2$	13523-86-9	248.321	cry (EtOH)	172				
9047	α-Pinene	2-Pinene	$C_{10}H_{16}$	80-56-8	136.234	liq	-64	156.2	0.8539^{25}	1.4632^{25}	i H_2O; msc EtOH, eth, chl
9048	β-Pinene	Nopinene	$C_{10}H_{16}$	127-91-3	136.234	liq	-61.5	166	0.860^{25}	1.4768^{25}	i H_2O; s bz, EtOH, eth, chl
9049	Piperazine	Diethylenediamine	$C_4H_{10}N_2$	110-85-0	86.135	hyg pl or lf (al)	106	146		1.446^{113}	vs H_2O; s EtOH, chl; i eth
9050	1-Piperazinecarboxaldehyde		$C_5H_{10}N_2O$	7755-92-2	114.145			95$^{0.5}$		1.5094^{20}	
9051	1,4-Piperazinediethanol		$C_8H_{18}N_2O_2$	122-96-3	174.241		135	217^{30}			
9052	Piperazine dihydrochloride	Diethylenediamine dihydrochloride	$C_4H_{12}Cl_2N_2$	142-64-3	159.057						sl H_2O; i EtOH
9053	2,5-Piperazinedione		$C_4H_6N_2O_2$	106-57-0	114.103	tab or pl (w)	312 dec	sub 260			sl H_2O, EtOH; s HCl
9054	1,4-Piperazinedipropanamine	1,4-Bis(3-aminopropyl) piperazine	$C_{10}H_{24}N_4$	7209-38-3	200.325		15	151^{2}	0.973^{25}	1.5015^{20}	
9055	1-Piperazineethanamine	1-(2-Aminoethyl)piperazine	$C_6H_{15}N_3$	140-31-8	129.203			220	0.985^{25}	1.4983^{20}	
9056	1-Piperazineethanol		$C_6H_{14}N_2O$	103-76-4	130.187			246	1.061^{25}	1.5065^{20}	
9057	1-Piperidinamine		$C_5H_{12}N_2$	2213-43-6	100.162			147	0.928^{25}	1.4750^{20}	
9058	Piperidine	Azacyclohexane	$C_5H_{11}N$	110-89-4	85.148	liq	-11.02	106.22	0.8606^{20}	1.4530^{20}	msc H_2O, EtOH; s eth, ace, bz, chl
9059	1-Piperidinecarboxaldehyde		$C_6H_{11}NO$	2591-86-8	113.157	liq	-30.8	222.5	1.0158^{25}	1.4805^{25}	msc H_2O, EtOH, eth, bz, chl, lig
9060	4-Piperidinecarboxamide		$C_6H_{12}N_2O$	39546-32-2	128.171		138.5				
9061	2-Piperidinecarboxylic acid, (*S*)	*L*-Pipecolic acid	$C_6H_{11}NO_2$	3105-95-1	129.157	nd (MeOH/ eth)	260				
9062	3-Piperidinecarboxylic acid	Nipecotic acid	$C_6H_{11}NO_2$	498-95-3	129.157		261 dec				vs H_2O
9063	4-Piperidinecarboxylic acid	Isonipecotic acid	$C_6H_{11}NO_2$	498-94-2	129.157	nd	336				
9064	1-Piperidineethanol		$C_7H_{15}NO$	3040-44-6	129.200		17.9	202; 90^{12}	0.9703^{25}	1.4749^{20}	msc H_2O; vs EtOH
9065	2-Piperidineethanol	2-(2-Hydroxyethyl)piperidine	$C_7H_{15}NO$	1484-84-0	129.200		69	202; 145^{36}	1.01^{27}		vs H_2O
9066	4-Piperidineethanol	4-(2-Hydroxyethyl)piperidine	$C_7H_{15}NO$	622-26-4	129.200	syr	132.5	227.5	1.0059^{15}	1.4907^{20}	vs H_2O, eth, EtOH
9067	Piperidine, hydrochloride	Piperidinium chloride	$C_5H_{12}ClN$	6091-44-7	121.609		142 dec				vs H_2O, chl
9068	4-Piperidinemethanamine	4-(Aminomethyl)piperidine	$C_6H_{14}N_2$	7144-05-0	114.188		25	200; 31^{10}		1.4900^{20}	
9069	2-Piperidinemethanol		$C_6H_{13}NO$	3433-37-2	115.173		69	104^{10}, 80^{1}			sl chl
9070	3-Piperidinemethanol		$C_6H_{13}NO$	4606-65-9	115.173		61	106$^{3.5}$	1.0263^{20}	1.4964^{20}	sl chl
9071	1-Piperidinepropanenitrile		$C_8H_{14}N_2$	3088-41-3	138.210		-6.8	145^{50}	0.9403^{25}	1.4676^{25}	
9072	2-Piperidinone		C_5H_9NO	675-20-7	99.131	hyg	39.5	256			vs H_2O, EtOH, eth; s dil acid; i con alk
9073	2-(1-Piperidinylmethyl) cyclohexanone	Pimeclone	$C_{12}H_{21}NO$	534-84-9	195.301			119^{14}			
9074	1-(2-Piperidinyl)-2-propanone, (±)		$C_8H_{15}NO$	539-00-4	141.211	oil		91^{14}	0.9624^{20}	1.4683^{20}	vs EtOH, chl
9075	3-(2-Piperidinyl)pyridine, (*S*)	Anabasine	$C_{10}H_{14}N_2$	494-52-0	162.231	liq	9	276; 146^{14}	1.0455^{20}	1.5430^{20}	msc H_2O; s EtOH, eth, bz
9076	Piperine		$C_{17}H_{19}NO_3$	94-62-2	285.338	pr (AcOEt) pl or mcl pr (al), cry	131.5				i H_2O; s EtOH, bz, py; sl eth; vs chl
9077	Piperonyl butoxide		$C_{19}H_{30}O_5$	51-03-6	338.438			180^{1}	1.05^{25}		
9078	Piperonyl sulfoxide	Isosafrole octyl sulfoxide	$C_{18}H_{28}O_3S$	120-62-7	324.478	ye-br liq		dec		1.530^{25}	sl H_2O; misc os
9079	Pipobroman		$C_{10}H_{16}Br_2N_2O_2$	54-91-1	356.054		106				
9080	Piprotal	Tropital	$C_{24}H_{40}O_8$	5281-13-0	456.570	liq		215$^{0.04}$			



Picene



Picrolonic acid



Picropodophyllin



Picrotoxin



Pilocarpine


Pilocarpine, monohydrochloride



Pilocarpine, mononitrate


Pilosine


Pimaric acid



Pinane



trans-2-Pinanol



Pindolol



α-Pinene



β-Pinene



Piperazine



1-Piperazinecarboxaldehyde



1,4-Piperazinediethanol


Piperazine dihydrochloride


2,5-Piperazinedione



1,4-Piperazinedipropanamine



1-Piperazineethanamine



1-Piperazineethanol



1-Piperidinamine



Piperidine



1-Piperidinecarboxaldehyde



4-Piperidinecarboxamide



2-Piperidinecarboxylic acid, (*S*)



3-Piperidinecarboxylic acid



4-Piperidinecarboxylic acid



1-Piperidineethanol



2-Piperidineethanol



4-Piperidineethanol


Piperidine, hydrochloride



4-Piperidinemethanamine



2-Piperidinemethanol



3-Piperidinemethanol



1-Piperidinepropanenitrile



2-Piperidinone



2-(1-Piperidinylmethyl)cyclohexanone



1-(2-Piperidinyl)-2-propanone, (±)



3-(2-Piperidinyl)pyridine, (*S*)


Piperine



Piperonyl butoxide



Piperonyl sulfoxide



Pipobroman



Piprotal


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9081	Pirimicarb		$C_{11}H_{18}N_4O_2$	23103-98-2	238.287		90.5				
9082	Pirimiphos-ethyl		$C_{13}H_{24}N_3O_3PS$	23505-41-1	333.387			dec >130	1.14^{20}		
9083	Pirimiphos-methyl		$C_{11}H_{20}N_3O_3PS$	29232-93-7	305.334		15	dec	1.17^{20}		
9084	Pithecolobine		$C_{22}H_{46}N_4O_2$	22368-82-7	398.626	cry	68	$230^{0.007}$			s H_2O, chl, eth, EtOH, peth
9085	2-Pivaloyl-1,3-indandione	Pindone	$C_{14}H_{14}O_3$	83-26-1	230.259	ye cry	109				
9086	Plasmocid		$C_{17}H_{25}N_3O$	551-01-9	287.400			$182^{1.0}$	1.0569^{24}	1.5855^{24}	
9087	Plumericin		$C_{15}H_{14}O_6$	77-16-7	290.268						s chl
9088	Podophyllotoxin		$C_{22}H_{22}O_8$	518-28-5	414.405		183				sl H_2O; vs EtOH; i eth; s ace, bz, HOAc
9089	Polythiazide		$C_{11}H_{13}ClF_3N_3O_4S_3$	346-18-9	439.882		214				
9090	Ponceau 3R	C.I. Food Red 6	$C_{19}H_{16}N_2Na_2O_7S_2$	3564-09-8	494.449	dk red pow					s H_2O; sl EtOH
9091	Populin		$C_{20}H_{22}O_8$	99-17-2	390.384	nd (w+2), pr (al)	180				
9092	21*H*,23*H*-Porphine		$C_{20}H_{14}N_4$	101-60-0	310.352	red or oran lf (chl-MeOH)	360	sub 300	1.336^{25}		i H_2O, eth, ace, bz; sl EtOH; s diox
9093	Potassium benzoate		$C_7H_5KO_2$	582-25-2	160.212	hyg cry					
9094	Potassium dichloroisocyanurate	Troclosene potassium	$C_3Cl_2KN_3O_3$	2244-21-5	236.054	hyg cry	250 dec				
9095	Potassium *D*-gluconate		$C_6H_{11}KO_7$	299-27-4	234.245	ye-wh cry	183 dec				vs H_2O; i EtOH, eth, bz, chl
9096	Potassium *trans,trans*-2,4-hexadienoate	Potassium sorbate	$C_6H_7KO_2$	24634-61-5	150.217		>270 dec		1.361^{25}		vs H_2O; s EtOH
9097	Potassium hydrogen phthalate	Potassium biphthalate	$C_8H_5KO_4$	877-24-7	204.222				1.636^{25}		s H_2O; sl EtOH
9098	Potassium *cis*-9-octadecenoate	Potassium oleate	$C_{18}H_{33}KO_2$	143-18-0	320.552	ye-br solid					s H_2O, EtOH
9099	Prazosin		$C_{19}H_{21}N_5O_4$	19216-56-9	383.402	cry	279				
9100	Prednisolone		$C_{21}H_{28}O_5$	50-24-8	360.444		235				
9101	5α-Pregnane	Allopregnane	$C_{21}H_{36}$	641-85-0	288.511		84.5				
9102	5β-Pregnane	17β-Ethyletiocholane	$C_{21}H_{36}$	481-26-5	288.511	mcl sc or pl (MeOH)	83.5		1.032^{15}		i H_2O; s chl, MeOH
9103	5α-Pregnane-3α,20α-diol	Allopregnane-3α,20α-diol	$C_{21}H_{36}O_2$	566-58-5	320.510	cry (MeOH)	244				
9104	5β-Pregnane-3α,20S-diol	Pregnanediol	$C_{21}H_{36}O_2$	80-92-2	320.510	pl (ace)	243.5		1.15^{25}		sl EtOH, eth; s ace
9105	5α-Pregnane-3,20-dione	3,20-Allopregnanedione	$C_{21}H_{32}O_2$	566-65-4	316.478	cry	200				
9106	5β-Pregnane-3,20-dione		$C_{21}H_{32}O_2$	128-23-4	316.478	nd (dil al) cry (dil ace)	123				i H_2O; vs EtOH; s eth, ace
9107	5-Pregnane-3,17,21-triol-20-one	3,17,21-Trihydroxypregnan-20-one, (3α,5β)	$C_{21}H_{34}O_4$	68-60-0	350.493	cry (EtOAc)	226				
9108	Pregnan-3α-ol-20-one		$C_{21}H_{34}O_2$	128-20-1	318.494	nd (bz), cry (dil al)	149.5				vs EtOH
9109	Pregnenolone		$C_{21}H_{32}O_2$	145-13-1	316.478	nd (dil al)	192				
9110	Prenoxdiazine hydrochloride		$C_{23}H_{28}ClN_3O$	982-43-4	397.940		186.5				
9111	Prephenic acid		$C_{10}H_{10}O_6$	126-49-8	226.182	free acid unstab					
9112	Pridinol	1,1-Diphenyl-3-(1-piperidinyl)-1-propanol	$C_{20}H_{25}NO$	511-45-5	295.419	cry	120				s ace
9113	Prilocaine	*N*-(2-Methylphenyl)-2-(propylamino)propanamide	$C_{13}H_{20}N_2O$	721-50-6	220.310	nd	38	160^{1}		1.5299^{20}	
9114	Procainamide	4-Amino-*N*-[2-(diethylamino) ethyl]benzamide	$C_{13}H_{21}N_3O$	51-06-9	235.325		47	212^{2}			
9115	Procainamide hydrochloride		$C_{13}H_{22}ClN_3O$	614-39-1	271.786		166				vs H_2O; s EtOH; i eth, bz; sl chl
9116	Procarbazine hydrochloride		$C_{12}H_{20}ClN_3O$	366-70-1	257.759	cry (MeOH)	225				
9117	Prochlorperazine		$C_{20}H_{24}ClN_3S$	58-38-8	373.943		228				
9118	Procymidone		$C_{13}H_{11}Cl_2NO_2$	32809-16-8	284.138		166		1.452^{25}		
9119	Prodiamine		$C_{13}H_{17}F_3N_4O_4$	29091-21-2	350.294		124		1.47^{25}		
9120	Profenofos		$C_{11}H_{15}BrClO_3PS$	41198-08-7	373.631			$110^{0.001}$	1.455^{20}		
9121	Profluralin		$C_{14}H_{16}F_3N_3O_4$	26399-36-0	347.290		34				
9122	Progesterone	Pregn-4-ene-3,20-dione	$C_{21}H_{30}O_2$	57-83-0	314.462	pr	129		1.166^{23}		i H_2O; s EtOH, diox, ace
9123	*DL*-Proline		$C_5H_9NO_2$	609-36-9	115.131	hyg nd (al-eth) cry (+w)	205 dec				vs H_2O, EtOH
9124	*L*-Proline	2-Pyrrolidinecarboxylic acid	$C_5H_9NO_2$	147-85-3	115.131	nd (al-eth) pr (w)	221 dec				vs H_2O; sl EtOH, ace, bz; i eth, PrOH
9125	Promazine		$C_{17}H_{20}N_2S$	58-40-2	284.419			$206^{0.3}$			
9126	Promecarb	Phenol, 3-methyl-5-(1-methylethyl)-, methylcarbamate	$C_{12}H_{17}NO_2$	2631-37-0	207.269		87	$117^{0.01}$			
9127	Promethazine	*N,N*,α-Trimethyl-10*H*-phenothiazine-10-ethanamine	$C_{17}H_{20}N_2S$	60-87-7	284.419		60	$191^{0.5}$			i H_2O; vs dil HCl



Pirimicarb



Pirimiphos-ethyl



Pirimiphos-methyl



Pithecolobine



2-Pivaloyl-1,3-indandione



Plasmocid



Plumericin



Podophyllotoxin



Polythiazide



Ponceau 3R



Populin



21*H*,23*H*-Porphine



Potassium benzoate



Potassium dichloroisocyanurate



Potassium *D*-gluconate



Potassium *trans,trans*-2,4-hexadienoate



Potassium hydrogen phthalate



Potassium *cis*-9-octadecenoate



Prazosin



Prednisolone



5α-Pregnane



5β-Pregnane



5α-Pregnane-3α,20α-diol



5β-Pregnane-3α,20S-diol



5α-Pregnane-3,20-dione



5β-Pregnane-3,20-dione



5-Pregnane-3,17,21-triol-20-one



Pregnan-3α-ol-20-one



Pregnenolone



Prenoxdiazine hydrochloride



Prephenic acid



Pridinol



Prilocaine



Procainamide



Procainamide hydrochloride



Procarbazine hydrochloride



Prochlorperazine



Procymidone



Prodiamine



Profenofos



Profluralin



Progesterone


DL-Proline



L-Proline



Promazine



Promecarb



Promethazine

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9128	Promethazine hydrochloride	Diprazin	$C_{17}H_{21}ClN_2S$	58-33-3	320.880		231				vs H_2O, EtOH, chl
9129	Prometone		$C_{10}H_{19}N_5O$	1610-18-0	225.291	solid	91.5				
9130	Prometryn	*N,N'*-Diisopropyl-6-(methylthio) -1,3,5-triazine-2,4-diamine	$C_{10}H_{19}N_5S$	7287-19-6	241.357		119		1.157^{20}		
9131	Propachlor	Acetamide, 2-chloro-*N*-(1-methylethyl)-*N*-phenyl-	$C_{11}H_{14}ClNO$	1918-16-7	211.688		77	110$^{0.03}$	1.242^{25}		
9132	Propanal	Propionaldehyde	C_3H_6O	123-38-6	58.079	liq	-80	48	0.8657^{25}	1.3636^{20}	s H_2O; msc EtOH, eth
9133	Propanal oxime		C_3H_7NO	627-39-4	73.094		40	131.5	0.9258^{20}	1.4287^{20}	
9134	Propanamide	Propionamide	C_3H_7NO	79-05-0	73.094	rhom, pl (bz)	81.3	213	0.9262^{110}	1.4180^{110}	vs H_2O, EtOH, eth, chl
9135	Propane		C_3H_8	74-98-6	44.096	col gas	-187.63	-42.1	0.493^{25} (p>1 atm)		s H_2O, EtOH; vs eth, bz; sl ace
9136	Propanediamide		$C_3H_6N_2O_2$	108-13-4	102.092	mcl pr(w)	170.8				s H_2O; i EtOH, eth, bz; sl DMSO
9137	1,2-Propanediamine, (±)	Propylenediamine	$C_3H_{10}N_2$	10424-38-1	74.124	hyg		119.5	0.878^{15}	1.4460^{20}	vs H_2O; i eth; vs chl
9138	1,3-Propanediamine	1,3-Diaminopropane	$C_3H_{10}N_2$	109-76-2	74.124	liq	-10.8	139.8	0.884^{25}	1.4600^{20}	s H_2O; msc EtOH, eth
9139	1,2-Propanediol diacetate		$C_7H_{12}O_4$	623-84-7	160.168			190.5	1.059^{20}	1.4173^{20}	vs H_2O; s EtOH, eth
9140	1,3-Propanediol diacetate		$C_7H_{12}O_4$	628-66-0	160.168			209.5	1.070^{14}	1.4192	vs H_2O; s EtOH
9141	1,2-Propanediol 1-methacrylate	2-Hydroxypropyl methacrylate	$C_7H_{12}O_3$	923-26-2	144.168			90^{9}, 57$^{0.5}$	1.066^{25}	1.4458^{20}	
9142	1,2-Propanedione	Pyruvaldehyde	$C_3H_4O_2$	78-98-8	72.063	ye hyg liq		72	1.0455^{20}	1.4002^{18}	s EtOH, eth, bz
9143	Propanedioyl dichloride		$C_3H_2Cl_2O_2$	1663-67-8	140.953			57^{28}	1.4509^{20}	1.4639^{20}	s eth, AcOEt
9144	1,2-Propanedithiol		$C_3H_8S_2$	814-67-5	108.226			152	1.08^{20}	1.532^{20}	s chl
9145	1,3-Propanedithiol	Trimethylene dimercaptan	$C_3H_8S_2$	109-80-8	108.226	liq	-79	172.9	1.0772^{20}	1.5392^{20}	sl H_2O, ctc; msc EtOH, eth, bz
9146	2,2'-[1,3-Propanediylbis(nitrilomethylidyne)]bisphenol	Disalicylidene-1,3-propanediamine	$C_{17}H_{18}N_2O_2$	120-70-7	282.337		54.3				
9147	Propanenitrile	Ethyl cyanide	C_3H_5N	107-12-0	55.079	liq	-92.78	97.14	0.7818^{20}	1.3655^{20}	vs H_2O; s EtOH, eth, ace, bz, ctc
9148	1-Propanesulfonic acid		$C_3H_8O_3S$	5284-66-2	124.159		8	136^{1}	1.2516^{25}		
9149	1-Propanesulfonyl chloride		$C_3H_7ClO_2S$	10147-36-1	142.605			dec 180; 77^{12}	1.267^{20}	1.452^{20}	
9150	1,3-Propane sultone	1,2-Oxathiolane, 2,2-dioxide	$C_3H_6O_3S$	1120-71-4	122.143						s chl
9151	1-Propanethiol	Propyl mercaptan	C_3H_8S	107-03-9	76.161	liq	-113.13	67.8	0.8411^{20}	1.4380^{20}	sl H_2O; s EtOH, eth, ace, bz
9152	2-Propanethiol	Isopropyl mercaptan	C_3H_8S	75-33-2	76.161	liq	-130.5	52.6	0.8143^{20}	1.4255^{20}	sl H_2O; msc EtOH, eth; vs ace; s chl
9153	1,2,3-Propanetriamine	1,2,3-Triaminopropane	$C_3H_{11}N_3$	21291-99-6	89.139	visc oil		190; 92^{9}			s H_2O
9154	1,2,3-Propanetricarboxylic acid	Tricarballylic acid	$C_6H_8O_6$	99-14-9	176.124	orth (eth)	166				vs H_2O, EtOH; sl eth
9155	1,2,3-Propanetriol-1-acetate		$C_5H_{10}O_4$	106-61-6	134.131			158^{165}, 129^{3}	1.2060^{20}	1.4157^{20}	vs H_2O, EtOH
9156	1,2,3-Propanetriol 1-(4-aminobenzoate)	Glyceryl *p*-aminobenzoate	$C_{10}H_{13}NO_4$	136-44-7	211.215						i H_2O; s EtOH
9157	1,2,3-Propanetriol-1,3-diacetate	1,3-Diacetin	$C_7H_{12}O_5$	105-70-4	176.167	hyg liq		260; 149^{12}	1.179^{15}	1.4395^{20}	vs H_2O, EtOH; sl eth; i CS_2
9158	1,2,3-Propanetriol tribenzoate		$C_{24}H_{20}O_6$	614-33-5	404.412	nd (MeOH)	76		1.228^{12}		i H_2O; s EtOH; vs eth, ace, bz, chl
9159	1,2,3-Propanetriol tripropanoate		$C_{12}H_{20}O_6$	139-45-7	260.283			175^{20}, 157^{13}	1.108^{15}	1.4318^{19}	i H_2O; s EtOH, chl; vs eth
9160	1,2,3-Propanetriyl hexanoate		$C_{21}H_{38}O_6$	621-70-5	386.523		-60	>200	0.9867^{20}	1.4427^{20}	i H_2O; msc EtOH, eth, bz; vs ace
9161	1,2,3-Propanetriyl octanoate		$C_{27}H_{50}O_6$	538-23-8	470.682		10	233	0.9540^{20}	1.4482^{20}	i H_2O; msc EtOH; vs eth, bz, chl, lig
9162	Propanidid		$C_{18}H_{27}NO_5$	1421-14-3	337.411			211$^{0.7}$			i H_2O; s EtOH, chl
9163	Propanil	Propanamide, *N*-(3,4-dichlorophenyl)-	$C_9H_9Cl_2NO$	709-98-8	218.079		92		1.25^{25}		
9164	Propanoic acid	Propionic acid	$C_3H_6O_2$	79-09-4	74.079	liq	-20.5	141.15	0.9882^{25}	1.3809^{20}	msc H_2O, EtOH; s eth; sl chl
9165	Propanoic anhydride	Propionic anhydride	$C_6H_{10}O_3$	123-62-6	130.141	liq	-45	170; 67.5^{18}	1.0110^{20}	1.4038^{20}	msc eth; sl ctc
9166	1-Propanol	Propyl alcohol	C_3H_8O	71-23-8	60.095	liq	-124.39	97.2	0.7997^{25}	1.3850^{20}	msc H_2O, EtOH, eth; s ace, chl; vs bz



Promethazine hydrochloride



Prometone


Prometryn



Propachlor



Propanal



Propanal oxime



Propanamide


Propane



Propanediamide


1,2-Propanediamine, (±)



1,3-Propanediamine



1,2-Propanediol diacetate



1,3-Propanediol diacetate



1,2-Propanediol 1-methacrylate



1,2-Propanedione



Propanedioyl dichloride



1,2-Propanedithiol


1,3-Propanedithiol


2,2'-[1,3-Propanediylbis(nitrilomethylidyne)]bisphenol


Propanenitrile



1-Propanesulfonic acid



1-Propanesulfonyl chloride



1,3-Propane sultone



1-Propanethiol



2-Propanethiol



1,2,3-Propanetriamine



1,2,3-Propanetricarboxylic acid



1,2,3-Propanetriol-1-acetate



1,2,3-Propanetriol 1-(4-aminobenzoate)



1,2,3-Propanetriol-1,3-diacetate



1,2,3-Propanetriol tribenzoate



1,2,3-Propanetriol tripropanoate



1,2,3-Propanetriyl hexanoate


1,2,3-Propanetriyl octanoate


Propanidid


Propanil



Propanoic acid



Propanoic anhydride


1-Propanol

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9167	2-Propanol	Isopropyl alcohol	C_3H_8O	67-63-0	60.095	liq	-87.9	82.3	0.7809^{25}	1.3776^{20}	msc H_2O, EtOH, eth; s ace, chl; vs bz
9168	2-Propanone oxime	Acetoxime	C_3H_7NO	127-06-0	73.094	pr (al)	61	136; 61^{20}	0.9113^{62}	1.4156^{20}	s H_2O, EtOH, eth, chl, lig
9169	2-Propanone phenylhydrazone	Acetone, phenylhydrazone	$C_9H_{12}N_2$	103-02-6	148.204	orth	42	163^{50}			s EtOH, eth, dil acid
9170	Propanoyl chloride	Propionyl chloride	C_3H_5ClO	79-03-8	92.524	liq	-94	80	1.0646^{20}	1.4032^{20}	s eth
9171	Propanoyl fluoride	Propionyl fluoride	C_3H_5FO	430-71-7	76.069			44	0.972^{15}	1.329^{13}	
9172	Propantheline bromide		$C_{23}H_{30}BrNO_3$	50-34-0	448.393	cry	160				vs H_2O, EtOH, chl; i eth, bz
9173	Propargite		$C_{19}H_{26}O_4S$	2312-35-8	350.472				1.10^{25}		
9174	Propargyl acetate		$C_5H_6O_2$	627-09-8	98.101			121.5	0.9982^{20}	1.4187^{20}	sl H_2O; s EtOH, eth
9175	Propargyl alcohol	3-Hydroxy-1-propyne	C_3H_4O	107-19-7	56.063	liq	-51.8	113.6	0.9478^{20}	1.4322^{20}	s H_2O, chl; msc EtOH, eth
9176	Propatyl nitrate	2-Ethyl-2-[(nitrooxy)methyl]-1,3-propanediol, dinitrate	$C_6H_{11}N_3O_9$	2921-92-8	269.166	wh pow	52		1.49		i H_2O; s EtOH, ace
9177	Propazine	6-Chloro-*N,N'*-diisopropyl-1,3,5-triazine-2,4-diamine	$C_9H_{16}ClN_5$	139-40-2	229.710		213		1.162^{20}		
9178	Propene	Propylene	C_3H_6	115-07-1	42.080	col gas	-185.24	-47.69	0.505^{25} (p>1 atm)	1.3567^{-70}	sl H_2O; vs EtOH, HOAc
9179	*trans*-1-Propene-1,2-dicarboxylic acid	Mesaconic acid	$C_5H_6O_4$	498-24-8	130.100	orth nd or mcl pr (eth)	204.5	sub	1.466^{20}		sl H_2O, bz, CS_2; vs EtOH; s eth, tfa
9180	1-Propene-2,3-dicarboxylic acid	Itaconic acid	$C_5H_6O_4$	97-65-4	130.100	rhom (bz)	175	dec	1.632^{25}		s H_2O, EtOH, ace; sl eth, bz, peth
9181	2-Propene-1-thiol		C_3H_6S	870-23-5	74.145			65	0.925^{23}	1.4832^{20}	i H_2O; msc EtOH, eth; s chl
9182	*cis*-1-Propene-1,2,3-tricarboxylic acid	*cis*-Aconitic acid	$C_6H_6O_6$	585-84-2	174.108	nd (w)	125				s H_2O; sl eth
9183	*trans*-1-Propene-1,2,3-tricarboxylic acid	*trans*-Aconitic acid	$C_6H_6O_6$	4023-65-8	174.108	lf (w) nd (w, eth)	196 dec				vs H_2O, EtOH
9184	1-Propen-1-one	Methylketene	C_3H_4O	6004-44-0	56.063	col gas	-80	-23			vs eth
9185	2-Propenoyl chloride	Acrylic acid chloride	C_3H_3ClO	814-68-6	90.508			75.5	1.1136^{20}	1.4343^{20}	vs chl
9186	*cis*-1-Propenylbenzene		C_9H_{10}	766-90-5	118.175	liq	-61.6	167.5	0.9088^{20}	1.5420^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
9187	*trans*-1-Propenylbenzene		C_9H_{10}	873-66-5	118.175	liq	-29.3	178.3	0.9023^{25}	1.5506^{20}	i H_2O; msc EtOH, eth, ace, bz
9188	*trans*-5-(1-Propenyl)-1,3-benzodioxole		$C_{10}H_{10}O_2$	4043-71-4	162.185		6.8	253	1.1224^{20}	1.5782^{20}	i H_2O; msc EtOH, eth; vs ace; s chl
9189	4-(1-Propenyl)phenol	*p*-Anol	$C_9H_{10}O$	539-12-8	134.174	lf	94	dec 250			sl H_2O; vs DMF
9190	2-(1-Propenyl)piperidine	β-Coniceine	$C_8H_{15}N$	538-90-9	125.212		8	168	0.8716^{15}		
9191	Propetamphos		$C_{10}H_{20}NO_4PS$	31218-83-4	281.309			$88^{0.005}$	1.1294^{20}		
9192	Propiconazole		$C_{15}H_{17}Cl_2N_3O_2$	60207-90-1	342.221			$180^{0.1}$	1.27^{20}		
9193	Propiomazine		$C_{20}H_{24}N_2OS$	362-29-8	340.482			$240^{0.5}$			
9194	Propionyl-*L*-carnitine	Carnitine, *O*-propanoyl	$C_{10}H_{19}NO_4$	20064-19-1	217.263	hyg pr (2-PrOH)	147 dec				
9195	Propofol		$C_{12}H_{18}O$	2078-54-8	178.270		19	256; 136^{30}	0.955^{20}	1.5140^{20}	
9196	Propoxur	Phenol, 2-(1-methylethoxy)-, methylcarbamate	$C_{11}H_{15}NO_3$	114-26-1	209.242		87	dec	1.12^{20}		
9197	2-Propoxyethanol	Ethylene glycol monopropyl ether	$C_5H_{12}O_2$	2807-30-9	104.148			149.8	0.9112^{20}	1.4133^{20}	s H_2O; vs EtOH, eth
9198	*D*-Propoxyphene	Dextropropoxyphene	$C_{22}H_{29}NO_2$	469-62-5	339.471	cry (peth)	75.5				
9199	*L*-Propoxyphene	Levopropoxyphene	$C_{22}H_{29}NO_2$	2338-37-6	339.471	cry (peth)	75.5				
9200	1-Propoxy-2-propanol	1,2-Propylene glycol 1-propyl ether	$C_6H_{14}O_2$	1569-01-3	118.174			150	0.8886^{20}	1.4130^{20}	
9201	3-Propoxy-1-propene		$C_6H_{12}O$	1471-03-0	100.158			91	0.7764^{20}	1.3919^{20}	vs ace, eth, EtOH
9202	Propranolol		$C_{16}H_{21}NO_2$	525-66-6	259.344	cry (cyhex)	96				
9203	Propyl acetate		$C_5H_{10}O_2$	109-60-4	102.132	liq	-93	101.54	0.8878^{20}	1.3842^{20}	sl H_2O; msc EtOH, eth; s ctc
9204	Propyl acrylate	2-Propenoic acid, propyl ester	$C_6H_{10}O_2$	925-60-0	114.142			$122; 63^{100}$			
9205	Propylamine	1-Propanamine	C_3H_9N	107-10-8	59.110	liq	-84.75	47.22	0.7173^{20}	1.3870^{20}	msc H_2O; vs EtOH, ace; s bz, chl; sl ctc
9206	Propylamine hydrochloride	1-Propanamine hydrochloride	$C_3H_{10}ClN$	556-53-6	95.571		163.5				s DMSO



2-Propanol



2-Propanone oxime



2-Propanone phenylhydrazone



Propanoyl chloride



Propanoyl fluoride



Propantheline bromide


Propargite



Propargyl acetate



Propargyl alcohol



Propatyl nitrate



Propazine



Propene


trans-1-Propene-1,2-dicarboxylic acid


1-Propene-2,3-dicarboxylic acid



2-Propene-1-thiol



cis-1-Propene-1,2,3-tricarboxylic acid



trans-1-Propene-1,2,3-tricarboxylic acid



1-Propen-1-one



2-Propenoyl chloride



cis-1-Propenylbenzene



trans-1-Propenylbenzene



trans-5-(1-Propenyl)-1,3-benzodioxole



4-(1-Propenyl)phenol



2-(1-Propenyl)piperidine



Propetamphos



Propiconazole



Propiomazine



Propionyl-*L*-carnitine



Propofol



Propoxur



2-Propoxyethanol



D-Propoxyphene



L-Propoxyphene



1-Propoxy-2-propanol



3-Propoxy-1-propene


Propranolol



Propyl acetate



Propyl acrylate



Propylamine



Propylamine hydrochloride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9207	Propyl 4-aminobenzoate	Risocaine	$C_{10}H_{13}NO_2$	94-12-2	179.216	pr	75				vs bz, eth, EtOH, chl
9208	2-(Propylamino)ethanol		$C_5H_{13}NO$	16369-21-4	103.163			182	0.9005^{20}	1.4428^{20}	
9209	4-Propylaniline		$C_9H_{13}N$	2696-84-6	135.206			227			
9210	*N*-Propylaniline		$C_9H_{13}N$	622-80-0	135.206			222; 98^{11}	0.9443^{20}	1.5428^{20}	vs eth, EtOH
9211	Propylarsonic acid	1-Propanearsonic acid	$C_3H_9AsO_3$	107-34-6	168.023	nd (al), pl (w)	134.5				vs H_2O, EtOH; i eth
9212	Propylbenzene	Isocumene	C_9H_{12}	103-65-1	120.191	liq	-99.6	159.24	0.8593^{25}	1.4895^{25}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
9213	α-Propylbenzenemethanol, (*R*)		$C_{10}H_{14}O$	22144-60-1	150.217		16	232	0.9740^{20}	1.5139^{20}	vs eth, EtOH
9214	Propyl benzenesulfonate		$C_9H_{12}O_3S$	80-42-2	200.254			162^{15}	1.1804^{17}	1.5035^{25}	sl H_2O; s EtOH; vs eth, chl
9215	Propyl benzoate		$C_{10}H_{12}O_2$	2315-68-6	164.201	liq	-51.6	211	1.0230^{20}	1.5000^{20}	i H_2O; msc EtOH, eth
9216	5-Propyl-1,3-benzodioxole	Dihydrosafrole	$C_{10}H_{12}O_2$	94-58-6	164.201			228			s ctc
9217	Propyl butanoate		$C_7H_{14}O_2$	105-66-8	130.185	liq	-95.2	143.0	0.8730^{20}	1.4001^{20}	sl H_2O; msc EtOH, eth
9218	Propyl carbamate		$C_4H_9NO_2$	627-12-3	103.120	pr	60	196			vs ace, eth, EtOH
9219	Propyl chloroacetate		$C_5H_9ClO_2$	5396-24-7	136.577			161	1.104^{20}	1.4261^{20}	vs eth
9220	Propyl 2-chlorobutanoate		$C_7H_{13}ClO_2$	62108-71-8	164.630			183	1.0252^{20}		
9221	Propyl chlorocarbonate		$C_4H_7ClO_2$	109-61-5	122.551			115.2	1.0901^{20}	1.4035^{20}	msc EtOH, eth
9222	Propyl 3-chloropropanoate		$C_6H_{11}ClO_2$	62108-66-1	150.603			180	1.0656^{20}	1.4290^{20}	vs eth, EtOH
9223	*S*-Propyl chlorothioformate	*S*-Propyl carbonochloridothioate	C_4H_7ClOS	13889-92-4	138.616	liq		59^{26}			
9224	Propyl *trans*-cinnamate	Propyl *trans*-3-phenyl-2-propenoate	$C_{12}H_{14}O_2$	74513-58-9	190.238			285	1.0433^{0}		i H_2O
9225	Propylcyclohexane		C_9H_{18}	1678-92-8	126.239	liq	-94.9	156.7	0.7936^{20}	1.4370^{20}	i H_2O; msc EtOH, ace, ctc; s eth, bz
9226	2-Propylcyclohexanone		$C_9H_{16}O$	94-65-5	140.222			197	0.927^{20}	1.4538^{20}	i H_2O; s EtOH, ace; vs eth, bz
9227	Propylcyclopentane		C_8H_{16}	2040-96-2	112.213	liq	-117.3	131	0.7763^{20}	1.4266^{20}	i H_2O; msc EtOH, eth, ace; s bz; vs ctc
9228	1-Propylcyclopentanol		$C_8H_{16}O$	1604-02-0	128.212	liq	-37.5	173.5	0.9040^{25}	1.4502^{25}	
9229	Propylene carbonate	4-Methyl-1,3-dioxolan-2-one	$C_4H_6O_3$	108-32-7	102.089	liq	-48.8	242	1.2047^{20}	1.4189^{20}	vs H_2O, EtOH, eth, ace, bz
9230	1,2-Propylene glycol	1,2-Propanediol	$C_3H_8O_2$	57-55-6	76.095	liq	-60	187.6	1.0361^{20}	1.4324^{20}	msc H_2O, EtOH; s eth, bz, chl
9231	1,3-Propylene glycol	Trimethylene glycol	$C_3H_8O_2$	504-63-2	76.095	liq	-27.7	214.4	1.0538^{20}	1.4398^{20}	msc H_2O, EtOH; vs eth; sl bz
9232	1,2-Propylene glycol 2-*tert*-butyl ether	2-(1,1-Dimethylethoxy)-1-propanol	$C_7H_{16}O_2$	94023-15-1	132.201	liq		152	0.87		
9233	1,2-Propylene glycol dinitrate		$C_3H_6N_2O_6$	6423-43-4	166.089	liq	exp	92^{10}			
9234	1,2-Propylene glycol monomethyl ether	1-Methoxy-2-propanol	$C_4H_{10}O_2$	107-98-2	90.121			119	0.9620^{20}	1.4034^{20}	
9235	1,2-Propylene glycol monomethyl ether acetate	2-Acetoxy-1-methoxypropane	$C_6H_{12}O_3$	108-65-6	132.157	liq		147			
9236	Propyleneimine	2-Methylaziridine	C_3H_7N	75-55-8	57.095			67	0.812^{16}		
9237	Propyl formate		$C_4H_8O_2$	110-74-7	88.106	liq	-92.9	80.9	0.9073^{20}	1.377^{20}	sl H_2O, ctc; msc EtOH, eth
9238	Propyl 3-(2-furyl)acrylate		$C_{10}H_{12}O_3$	623-22-3	180.200			113^{16}, 92^{3}	1.0744^{20}	1.5392^{24}	vs bz, eth, EtOH
9239	4-Propylheptane		$C_{10}H_{22}$	3178-29-8	142.282			157.5	0.7321^{25}	1.4135^{20}	
9240	Propyl hexanoate		$C_9H_{18}O_2$	626-77-7	158.238	liq	-68.7	187	0.8672^{20}	1.4170^{20}	vs eth, EtOH
9241	Propyl 2-hydroxybenzoate		$C_{10}H_{12}O_3$	607-90-9	180.200		97	239	1.0979^{20}	1.5161^{20}	s ctc, CS_2
9242	Propyl 4-hydroxybenzoate	Propylparaben	$C_{10}H_{12}O_3$	94-13-3	180.200	pr (eth)	97		1.0630^{102}	1.5050^{102}	i H_2O; s EtOH, eth; sl chl
9243	Propyliodone		$C_{10}H_{11}I_2NO_3$	587-61-1	447.008		186				
9244	Propyl isobutanoate		$C_7H_{14}O_2$	644-49-5	130.185			135.4	0.8843^{0}	1.3955^{20}	sl H_2O; s EtOH, ace; vs eth
9245	Propyl isocyanate	1-Isocyanatopropane	C_4H_7NO	110-78-1	85.105			83.5	0.908^{25}	1.3970^{20}	
9246	Propyl isothiocyanate	1-Isothiocyanatopropane	C_4H_7NS	628-30-8	101.171			153	0.9781^{16}	1.5085^{16}	sl H_2O; msc EtOH, eth
9247	Propyl methacrylate		$C_7H_{12}O_2$	2210-28-8	128.169			141	0.9022^{20}	1.4190^{20}	i H_2O; msc EtOH, eth
9248	Propyl 3-methylbutanoate	Propyl isopentanoate	$C_8H_{16}O_2$	557-00-6	144.212			155.9	0.8617^{20}	1.4031^{20}	vs eth, EtOH
9249	1-Propylnaphthalene		$C_{13}H_{14}$	2765-18-6	170.250	liq	-8.6	274.5	0.9897^{20}	1.5923^{20}	
9250	Propyl nitrate		$C_3H_7NO_3$	627-13-4	105.093			110	1.0538^{20}	1.3973^{20}	sl H_2O; s EtOH, eth, ctc
9251	Propyl nitrite		$C_3H_7NO_2$	543-67-9	89.094	liq		48	0.886^{20}	1.3604^{20}	sl H_2O; s EtOH, eth



Propyl 4-aminobenzoate



2-(Propylamino)ethanol



4-Propylaniline



N-Propylaniline



Propylarsonic acid



Propylbenzene



α-Propylbenzenemethanol, (*R*)



Propyl benzenesulfonate



Propyl benzoate



5-Propyl-1,3-benzodioxole



Propyl butanoate



Propyl carbamate



Propyl chloroacetate



Propyl 2-chlorobutanoate



Propyl chlorocarbonate



Propyl 3-chloropropanoate



S-Propyl chlorothioformate



Propyl *trans*-cinnamate



Propylcyclohexane



2-Propylcyclohexanone



Propylcyclopentane



1-Propylcyclopentanol



Propylene carbonate



1,2-Propylene glycol


1,3-Propylene glycol



1,2-Propylene glycol 2-*tert*-butyl ether



1,2-Propylene glycol dinitrate



1,2-Propylene glycol monomethyl ether



1,2-Propylene glycol monomethyl ether acetate



Propyleneimine



Propyl formate



Propyl 3-(2-furyl)acrylate



4-Propylheptane



Propyl hexanoate



Propyl 2-hydroxybenzoate



Propyl 4-hydroxybenzoate



Propyliodone



Propyl isobutanoate



Propyl isocyanate



Propyl isothiocyanate


Propyl methacrylate



Propyl 3-methylbutanoate



1-Propylnaphthalene



Propyl nitrate



Propyl nitrite


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9252	Propyl octanoate		$C_{11}H_{22}O_2$	624-13-5	186.292	liq	-46.2	226.4	0.8659^{20}	1.4191^{25}	vs ace, eth, EtOH
9253	Propyl pentanoate		$C_8H_{16}O_2$	141-06-0	144.212	liq	-70.7	167.5	0.8699^{20}	1.4065^{20}	i H_2O; s EtOH, eth, chl
9254	2-Propylpentanoic acid	Valproic acid	$C_8H_{16}O_2$	99-66-1	144.212	col liq		221; 120^{14}	0.904^{25}	1.425^{25}	sl H_2O
9255	2-Propylphenol		$C_9H_{12}O$	644-35-9	136.190		7	220	1.015^{20}		vs eth, EtOH
9256	4-Propylphenol		$C_9H_{12}O$	645-56-7	136.190		22	232.6	1.009^{20}	1.5379^{25}	sl H_2O, ctc; s EtOH
9257	2-Propylpiperidine, (*S*)	Coniine	$C_8H_{17}N$	458-88-8	127.228	liq	-1.0	166.5	0.8440^{20}	1.4512^{22}	sl H_2O, chl; msc EtOH; vs eth; s bz
9258	*trans*-6-Propyl-3-piperidinol, (3*S*)	Pseudoconhydrine	$C_8H_{17}NO$	140-55-6	143.227	hyg nd (eth)	106	236			vs H_2O, eth, EtOH
9259	*N*-Propylpropanamide		$C_6H_{13}NO$	3217-86-5	115.173		154	215; 108^{9}	0.8985^{25}		sl H_2O, eth
9260	Propyl propanoate	Propyl propionate	$C_6H_{12}O_2$	106-36-5	116.158	liq	-75.9	122.5	0.8809^{20}	1.3935^{20}	sl H_2O, ctc; msc EtOH, eth; s ace
9261	2-Propylpyridine		$C_8H_{11}N$	622-39-9	121.180		1.0	167	0.9119^{20}	1.4925^{20}	sl H_2O; msc EtOH, eth; vs ace
9262	4-Propylpyridine		$C_8H_{11}N$	1122-81-2	121.180			185	0.9381^{15}	1.4966^{20}	vs eth, EtOH
9263	2-Propyl-4-pyridinecarbothioamide	Protionamide	$C_9H_{12}N_2S$	14222-60-7	180.269		136.7				
9264	Propyl Red	Benzoic acid, 2-[[4-(dipropylamino)phenyl]azo]-	$C_{19}H_{23}N_3O_2$	2641-01-2	325.405	viol-bl or purp red cry (al)					s EtOH, KOH
9265	(Propylthio)benzene		$C_9H_{12}S$	874-79-3	152.256	liq	-45	220	0.9995^{20}	1.5571^{20}	
9266	Propyl 4-toluenesulfonate		$C_{10}H_{14}O_3S$	599-91-7	214.281		<-20	189^{9}	1.144^{20}	1.4998^{20}	
9267	Propyl trichloroacetate		$C_5H_7Cl_3O_2$	13313-91-2	205.468			187	1.3221^{20}	1.4501^{20}	vs eth, EtOH
9268	Propyl 3,4,5-trihydroxybenzoate	Propyl gallate	$C_{10}H_{12}O_5$	121-79-9	212.199	nd (w)	130				sl H_2O
9269	Propylurea		$C_4H_{10}N_2O$	627-06-5	102.134	pr (al)	108.5				sl H_2O, DMSO; s EtOH
9270	Propyl vinyl ether	1-(Ethenyloxy)propane	$C_5H_{10}O$	764-47-6	86.132			65	0.7674^{20}	1.3908^{20}	
9271	2-Propynal	Propargyl aldehyde	C_3H_2O	624-67-9	54.047			60	0.9152^{20}	1.4033^{25}	msc H_2O; s EtOH, eth, ace, bz, tol
9272	2-Propyn-1-amine		C_3H_5N	2450-71-7	55.079			83	0.803^{25}	1.4480^{20}	
9273	Propyne	Methylacetylene	C_3H_4	74-99-7	40.064	col gas	-102.7	-23.2	0.607^{25} (p>1 atm)	1.3863^{-40}	sl H_2O; vs EtOH; s bz, chl
9274	2-Propynoic acid	Propiolic acid	$C_3H_2O_2$	471-25-0	70.047	cry (CS_2)	9	dec 144; 72^{50}	1.1380^{20}	1.4306^{20}	vs H_2O, eth, EtOH, chl
9275	1-Propynylbenzene		C_9H_8	673-32-5	116.160			183	0.942^{15}	1.563^{15}	
9276	Propyzamide	*N*-(1,1-Dimethyl-2-propynyl)-3,5-dichlorobenzamide	$C_{12}H_{11}Cl_2NO$	23950-58-5	256.127		155				
9277	Prostaglandin E_1	11,15-Dihydroxy-9-oxo-13-prostenoic acid	$C_{20}H_{34}O_5$	745-65-3	354.481	cry (EtOAc)	115				s H_2O
9278	Prostaglandin E_2	11,15-Dihydroxy-9-oxo-5,13-prostadienoic acid	$C_{20}H_{32}O_5$	363-24-6	352.465	col cry	67				s H_2O, thf
9279	Prostaglandin $F_{2\alpha}$	9,11,15-Trihydroxyprosta-5,13-dienoic acid	$C_{20}H_{34}O_5$	551-11-1	354.481	oil or solid	≈30				sl H_2O; s EtOH, MeOH, chl, AcOEt
9280	Protopine	Fumarine	$C_{20}H_{19}NO_5$	130-86-9	353.369	mcl pr (al-chl)	208				i H_2O; sl EtOH, eth, bz, peth; s chl
9281	Protoverine		$C_{27}H_{43}NO_9$	76-45-9	525.632	nd (MeOH)	221				i H_2O; s EtOH, bz, aq acid, MeOH
9282	Protriptyline hydrochloride	Triptil	$C_{19}H_{22}ClN$	1225-55-4	299.838	cry (2-PrOH/eth)	170				
9283	Prunetin		$C_{16}H_{12}O_5$	552-59-0	284.263		239.5				
9284	Pseudoaconitine		$C_{36}H_{51}NO_{12}$	127-29-7	689.790	tcl (MeOH)	214				vs eth, EtOH
9285	Pseudocodeine		$C_{18}H_{21}NO_3$	466-96-6	299.365	wh nd	181.5		1.290^{80}	1.574	
9286	Pseudojervine		$C_{33}H_{49}NO_8$	36069-05-3	587.744	wh nd or hex cry	304 dec				i H_2O, eth, bz, chl, tol, peth; s EtOH
9287	Pseudomorphine		$C_{34}H_{36}N_2O_6$	125-24-6	568.659	cry (aq NH_3, + 3 w)	282.5				i H_2O, EtOH, eth, chl, sulf; s py, NH_3
9288	Pseudotropine	8-Methyl-8-azabicyclo[3.2.1]octan-3-ol, *exo*	$C_8H_{15}NO$	135-97-7	141.211	orth cry (eth), orth bipym (peth-bz)	109	241			vs H_2O, EtOH; sl eth; s bz, chl
9289	Psoralen		$C_{11}H_6O_3$	66-97-7	186.164	nd (w, EtOH)	171				



Propyl octanoate



Propyl pentanoate



2-Propylpentanoic acid



2-Propylphenol



4-Propylphenol



2-Propylpiperidine, (*S*)



trans-6-Propyl-3-piperidinol, (3*S*)



N-Propylpropanamide



Propyl propanoate



2-Propylpyridine



4-Propylpyridine



2-Propyl-4-pyridinecarbothioamide



Propyl Red



(Propylthio)benzene


Propyl 4-toluenesulfonate



Propyl trichloroacetate


Propyl 3,4,5-trihydroxybenzoate



Propylurea



Propyl vinyl ether



2-Propynal



2-Propyn-1-amine


Propyne



2-Propynoic acid



1-Propynylbenzene



Propyzamide



Prostaglandin E_1



Prostaglandin E_2



Prostaglandin $F_{2\alpha}$



Protopine



Protoverine



Protriptyline hydrochloride



Prunetin



Pseudoaconitine


Pseudocodeine



Pseudojervine



Pseudomorphine



Pseudotropine



Psoralen


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9290	Pteridine	Pyrazino[2,3-d]pyrimidine	$C_6H_4N_4$	91-18-9	132.123	ye pl (bz, sub)	139.5	sub 125			vs H_2O; s EtOH; sl eth, bz
9291	2,4(1*H*,3*H*)-Pteridinedione	Lumazine	$C_6H_4N_4O_2$	487-21-8	164.122	ye-oran nd (w)	348.5				vs HOAc
9292	Pulegone		$C_{10}H_{16}O$	89-82-7	152.233			224	0.9346^{45}	1.4894^{20}	i H_2O; msc EtOH, eth, chl; s ctc
9293	1*H*-Purine	6*H*-Imidazo[4,5-d]pyrimidine	$C_5H_4N_4$	120-73-0	120.113		216.5				vs H_2O, EtOH; sl eth, chl; s ace
9294	1*H*-Purine-2,6-diamine	2,6-Diaminopurine	$C_5H_6N_6$	1904-98-9	150.142	cry (dil al)	302				
9295	Pyocyanine		$C_{13}H_{10}N_2O$	85-66-5	210.230	dk bl nd (w + 1) (chl-peth)	133 dec				sl H_2O, bz; s EtOH, ace; i eth; vs chl
9296	4*H*-Pyran	1,4-Pyran	C_5H_6O	289-65-6	82.101	unstab oil		80		1.4559^{20}	s EtOH, eth, bz
9297	2*H*-Pyran-2-one		$C_5H_4O_2$	504-31-4	96.085		8.5	207.5	1.200^{20}	1.5270^{25}	msc H_2O; vs ace
9298	4*H*-Pyran-4-one		$C_5H_4O_2$	108-97-4	96.085		32.5	212.5	1.190^{25}	1.5238	vs H_2O, chl, eth; s EtOH, bz; sl CS_2
9299	Pyrantel		$C_{11}H_{14}N_2S$	15686-83-6	206.307	cry (MeOH)	178				
9300	4*H*-Pyran-4-thione		C_5H_4OS	1120-93-0	112.150		49				s H_2O
9301	8,16-Pyranthrenedione		$C_{30}H_{14}O_2$	128-70-1	406.431	red-ye or red-br nd ($PhNO_2$)	dec	sub			
9302	Pyrazine	1,4-Diazine	$C_4H_4N_2$	290-37-9	80.088	pr (w)	51.0	115	1.0311^{61}	1.4953^{61}	s H_2O, EtOH, eth, ace; sl ctc
9303	Pyrazinecarboxamide	Pyrazinamide	$C_5H_5N_3O$	98-96-4	123.113	wh nd (w, al)	192	sub			s H_2O, EtOH
9304	Pyrazinecarboxylic acid	Pyrazinoic acid	$C_5H_4N_2O_2$	98-97-5	124.098	wh nd (w)	225 dec	sub			
9305	2,3-Pyrazinedicarboxylic acid	2,3-Dicarboxypyrazine	$C_6H_4N_2O_4$	89-01-0	168.107	pr (w+2)	193 dec				vs H_2O; sl EtOH, eth, bz; s ace, MeOH
9306	1*H*-Pyrazole	1,2-Diazole	$C_3H_4N_2$	288-13-1	68.077	nd or pr (lig)	70.7	187		1.4203	s H_2O, EtOH, eth, bz; sl chl
9307	1-Pyrenamine		$C_{16}H_{11}N$	1606-67-3	217.265	ye nd (hx) lf (dil al)	117.5				s EtOH, ace, hx, acid; sl chl
9308	Pyrene	Benzo[def]phenanthrene	$C_{16}H_{10}$	129-00-0	202.250	pa ye pl (to, sub)	150.62	404	1.271^{23}		i H_2O; s EtOH, eth, bz, tol; sl ctc
9309	Pyrethrin I		$C_{21}H_{28}O_3$	121-21-1	328.445	visc liq		170$^{0.1}$ dec	1.5192^{18}	1.5192^{18}	i H_2O; s EtOH, eth, ctc, peth
9310	Pyrethrin II		$C_{22}H_{28}O_5$	121-29-9	372.454	visc liq		200$^{0.1}$ dec		1.5258^{20}	i H_2O; s EtOH, eth, ctc, peth
9311	Pyridate		$C_{19}H_{23}ClN_2O_2S$	55512-33-9	378.916	br oil	27	220$^{0.1}$	1.555^{20}	1.568^{20}	i H_2O
9312	Pyridazine	1,2-Diazabenzene	$C_4H_4N_2$	289-80-5	80.088	liq	-8	208	1.1035^{23}	1.5218^{20}	msc H_2O, EtOH; vs eth, ace, bz; i peth
9313	2-Pyridinamine	2-Aminopyridine	$C_5H_6N_2$	504-29-0	94.115	lf (lig)	57.5	105^{20}			s EtOH, eth, ace, bz; sl chl
9314	3-Pyridinamine	3-Aminopyridine	$C_5H_6N_2$	462-08-8	94.115	lf (bz-lig)	64.5	252			s H_2O, EtOH, eth; sl lig
9315	4-Pyridinamine	4-Aminopyridine	$C_5H_6N_2$	504-24-5	94.115	nd (bz)	158.5	273			s H_2O, eth, bz; vs EtOH; sl lig
9316	Pyridine	Azine	C_5H_5N	110-86-1	79.101	liq	-41.70	115.23	0.9819^{20}	1.5095^{20}	msc H_2O, EtOH, eth, ace, bz, chl
9317	2-Pyridinecarbonitrile		$C_6H_4N_2$	100-70-9	104.109	nd or pr (eth)	29	224.5	1.0810^{25}	1.5242^{25}	s H_2O, chl; vs EtOH, eth, bz; sl ctc
9318	3-Pyridinecarbonitrile		$C_6H_4N_2$	100-54-9	104.109	nd (lig), peth-eth)	51	206.9; 170^{300}	1.1590^{25}		vs H_2O, EtOH, eth, bz; s chl; sl lig
9319	4-Pyridinecarbonitrile		$C_6H_4N_2$	100-48-1	104.109	nd(lig-eth)	83	186			s H_2O, EtOH, eth, bz, chl; sl lig
9320	3-Pyridinecarbothioamide		$C_6H_6N_2S$	4621-66-3	138.190		192				
9321	4-Pyridinecarbothioamide		$C_6H_6N_2S$	2196-13-6	138.190		198 dec				
9322	2-Pyridinecarboxaldehyde		C_6H_5NO	1121-60-4	107.110			180; 62^{13}	1.1181^{25}	1.5389^{18}	s H_2O, EtOH, eth, AcOEt; sl ctc
9323	3-Pyridinecarboxaldehyde	Nicotinaldehyde	C_6H_5NO	500-22-1	107.110			92^{23}	1.1394^{25}		s H_2O, EtOH, ace, chl; sl eth, peth
9324	4-Pyridinecarboxaldehyde		C_6H_5NO	872-85-5	107.110			77^{12}		1.5423^{20}	s H_2O, eth, ctc
9325	2-Pyridinecarboxaldehyde oxime		$C_6H_6N_2O$	873-69-8	122.124		112.5				
9326	2-Pyridinecarboxamide		$C_6H_6N_2O$	1452-77-3	122.124	mcl pr (w)	108.3				sl H_2O, chl; s EtOH, bz



Pteridine


2,4(1*H*,3*H*)-Pteridinedione


Pulegone



1*H*-Purine



1*H*-Purine-2,6-diamine



Pyocyanine



4*H*-Pyran


2*H*-Pyran-2-one



4*H*-Pyran-4-one



Pyrantel



4*H*-Pyran-4-thione


8,16-Pyranthrenedione



Pyrazine



Pyrazinecarboxamide



Pyrazinecarboxylic acid



2,3-Pyrazinedicarboxylic acid



1*H*-Pyrazole


1-Pyrenamine



Pyrene



Pyrethrin I



Pyrethrin II


Pyridate



Pyridazine



2-Pyridinamine



3-Pyridinamine



4-Pyridinamine



Pyridine



2-Pyridinecarbonitrile



3-Pyridinecarbonitrile



4-Pyridinecarbonitrile



3-Pyridinecarbothioamide



4-Pyridinecarbothioamide


2-Pyridinecarboxaldehyde



3-Pyridinecarboxaldehyde



4-Pyridinecarboxaldehyde



2-Pyridinecarboxaldehyde oxime



2-Pyridinecarboxamide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9327	3-Pyridinecarboxamide	Niacinamide	$C_6H_6N_2O$	98-92-0	122.124	wh pw, nd (bz)	130	$157^{0.0005}$	1.400^{25}	1.466	vs H_2O, EtOH, glycerol; sl chl
9328	4-Pyridinecarboxamide		$C_6H_6N_2O$	1453-82-3	122.124		157.5				
9329	2-Pyridinecarboxylic acid	Picolinic acid	$C_6H_5NO_2$	98-98-6	123.110	nd (w, al, bz)	136.5	sub			sl H_2O, bz; s EtOH; i eth, chl, CS_2
9330	3-Pyridinecarboxylic acid	Nicotinic acid	$C_6H_5NO_2$	59-67-6	123.110	nd (al, w)	236.6	sub	1.473^{25}		sl H_2O, EtOH, eth
9331	4-Pyridinecarboxylic acid	Isonicotinic acid	$C_6H_5NO_2$	55-22-1	123.110	nd(w)	315	sub 260			sl H_2O, EtOH, eth, bz
9332	3-Pyridinecarboxylic acid 1-oxide	Oxiniacic acid	$C_6H_5NO_3$	2398-81-4	139.109	nd	254 dec				vs H_2O, MeOH
9333	4-Pyridinecarboxylic acid 1-oxide		$C_6H_5NO_3$	13602-12-5	139.109		273 dec				
9334	2,3-Pyridinediamine		$C_5H_7N_3$	452-58-4	109.130	lf or pl (dil al)	120.8	149^{5}			s H_2O, EtOH, bz
9335	2,5-Pyridinediamine	2,5-Diaminopyridine	$C_5H_7N_3$	4318-76-7	109.130	nd	110.3	182^{12}			vs H_2O, EtOH
9336	2,6-Pyridinediamine		$C_5H_7N_3$	141-86-6	109.130		121.5	285; 148^{5}			sl H_2O, ace
9337	3,4-Pyridinediamine		$C_5H_7N_3$	54-96-6	109.130	nd or lf	219.3				
9338	2,3-Pyridinedicarboxylic acid	Quinolinic acid	$C_7H_5NO_4$	89-00-9	167.120	mcl pr (w)	228.5				sl H_2O, tfa; i EtOH, eth, bz
9339	2,4-Pyridinedicarboxylic acid	Lutidinic acid	$C_7H_5NO_4$	499-80-9	167.120	lf (w+1)	249		0.942^{25}		sl H_2O; s EtOH; i eth, bz, CS_2
9340	2,5-Pyridinedicarboxylic acid	Isocinchomeronic acid	$C_7H_5NO_4$	100-26-5	167.120	lf or pr (dil HCl)	254				s H_2O, HCl; sl EtOH; i eth, bz
9341	2,6-Pyridinedicarboxylic acid	Dipicolinic acid	$C_7H_5NO_4$	499-83-2	167.120	nd (w+3/2)	252				sl H_2O, EtOH, HOAc
9342	3,4-Pyridinedicarboxylic acid	Cinchomeronic acid	$C_7H_5NO_4$	490-11-9	167.120	cry (w)	256	sub			sl H_2O, EtOH, bz; i eth, i chl
9343	3,5-Pyridinedicarboxylic acid	Dinicotinic acid	$C_7H_5NO_4$	499-81-0	167.120	cry (w)	324	sub			i H_2O; sl eth, HOAc; s DMSO, HCl
9344	2,3-Pyridinedicarboxylic acid anhydride	Furo[3,4-b]pyridine-5,7-dione	$C_7H_3NO_3$	699-98-9	149.104		138				
9345	2-Pyridineethanamine		$C_7H_{10}N_2$	2706-56-1	122.167			213; 131^{50}	1.0220^{25}	1.5335^{25}	
9346	4-Pyridineethanamine		$C_7H_{10}N_2$	13258-63-4	122.167			121^{10}	1.0302^{25}	1.5381^{25}	vs H_2O
9347	2-Pyridineethanol		C_7H_9NO	103-74-2	123.152		-7.8	190^{200}, 170^{100}	1.091^{25}	1.5366^{20}	vs H_2O, EtOH, chl; sl eth
9348	Pyridine hydrochloride		C_5H_6ClN	628-13-7	115.562	hyg pl or sc (al)	146	222			vs H_2O, EtOH, chl
9349	2-Pyridinemethanamine		$C_6H_8N_2$	3731-51-9	108.141			203; 91^{17}	1.0525^{25}	1.5431^{25}	vs H_2O
9350	3-Pyridinemethanamine		$C_6H_8N_2$	3731-52-0	108.141	liq	-21.1	226	1.064^{20}	1.552^{20}	vs H_2O, eth, EtOH
9351	4-Pyridinemethanamine		$C_6H_8N_2$	3731-53-1	108.141	liq	-7.6	230; 103^{11}	1.072^{20}	1.5495^{25}	vs H_2O
9352	2-Pyridinemethanol		C_6H_7NO	586-98-1	109.126			112^{16}, 102.5^{8}	1.1317^{20}	1.5444^{20}	msc H_2O; vs EtOH, eth, ace, bz
9353	3-Pyridinemethanol	Nicotinyl alcohol	C_6H_7NO	100-55-0	109.126	liq	-6.5	266	1.131^{20}	1.5455^{20}	vs H_2O, eth
9354	4-Pyridinemethanol	4-Picolyl alcohol	C_6H_7NO	586-95-8	109.126		53	141^{12}			s chl
9355	Pyridine-1-oxide	Pyridine *N*-oxide	C_5H_5NO	694-59-7	95.100		65.5	146^{13}			
9356	2-Pyridinepropanol		$C_8H_{11}NO$	2859-68-9	137.179		34	260.2; 116^{4}	1.060^{25}	1.5298^{20}	vs H_2O
9357	3-Pyridinepropanol		$C_8H_{11}NO$	2859-67-8	137.179			284; 130^{3}	1.063^{25}	1.5313^{20}	vs H_2O
9358	3-Pyridinesulfonic acid	3-Pyridylsulfonic acid	$C_5H_5NO_3S$	636-73-7	159.164	orth	357 dec		1.713^{25}		vs H_2O; sl EtOH; i eth
9359	2-Pyridinethiol, 1-oxide		C_5H_5NOS	1121-31-9	127.165		70.5				
9360	2(1*H*)-Pyridinethione		C_5H_5NS	2637-34-5	111.166		130.0				s H_2O, EtOH, bz, chl
9361	2-Pyridinol		C_5H_5NO	72762-00-6	95.100	nd (bz)	107.8		1.3910^{20}		vs H_2O, bz, EtOH
9362	3-Pyridinol		C_5H_5NO	109-00-2	95.100	nd (bz)	129				s H_2O, EtOH; sl eth, chl
9363	4-Pyridinol		C_5H_5NO	626-64-2	95.100	pr or nd (w+1)	149.8	>350; 257^{10}			s H_2O, EtOH; i eth, bz
9364	2(1*H*)-Pyridinone		C_5H_5NO	142-08-5	95.100	nd (bz)	107.8	280	1.3910^{20}		s H_2O, EtOH, bz, chl; sl eth, DMSO
9365	2(1*H*)-Pyridinone hydrazone	2-Pyridinylhydrazine	$C_5H_7N_3$	4930-98-7	109.130		46.6	185^{140}, 90^{1}			s chl
9366	α-[(2-Pyridinylamino)methyl] benzenemethanol	Phenyramidol	$C_{13}H_{14}N_2O$	553-69-5	214.262	cry (dil MeOH)	83.5				
9367	1-(2-Pyridinyl)ethanone		C_7H_7NO	1122-62-9	121.137	ye in air		192	1.077^{25}	1.5203^{20}	s EtOH, eth, HOAc; sl ctc
9368	1-(3-Pyridinyl)ethanone	Methyl pyridyl ketone	C_7H_7NO	350-03-8	121.137		13.5	220		1.5341^{20}	s H_2O, EtOH, eth, acid
9369	1-(4-Pyridinyl)ethanone		C_7H_7NO	1122-54-9	121.137		16	212	1.097^{25}	1.5282^{25}	sl EtOH, eth, acid



3-Pyridinecarboxamide



4-Pyridinecarboxamide



2-Pyridinecarboxylic acid



3-Pyridinecarboxylic acid



4-Pyridinecarboxylic acid



3-Pyridinecarboxylic acid 1-oxide



4-Pyridinecarboxylic acid 1-oxide



2,3-Pyridinediamine



2,5-Pyridinediamine



2,6-Pyridinediamine



3,4-Pyridinediamine



2,3-Pyridinedicarboxylic acid



2,4-Pyridinedicarboxylic acid



2,5-Pyridinedicarboxylic acid



2,6-Pyridinedicarboxylic acid



3,4-Pyridinedicarboxylic acid



3,5-Pyridinedicarboxylic acid



2,3-Pyridinedicarboxylic acid anhydride



2-Pyridineethanamine



4-Pyridineethanamine



2-Pyridineethanol



Pyridine hydrochloride



2-Pyridinemethanamine



3-Pyridinemethanamine



4-Pyridinemethanamine



2-Pyridinemethanol



3-Pyridinemethanol


4-Pyridinemethanol


Pyridine-1-oxide


2-Pyridinepropanol


3-Pyridinepropanol



3-Pyridinesulfonic acid


2-Pyridinethiol, 1-oxide



2(1*H*)-Pyridinethione



2-Pyridinol



3-Pyridinol



4-Pyridinol



2(1*H*)-Pyridinone


2(1*H*)-Pyridinone hydrazone



α-[(2-Pyridinylamino)methyl]benzenemethanol



1-(2-Pyridinyl)ethanone



1-(3-Pyridinyl)ethanone



1-(4-Pyridinyl)ethanone


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9370	*N*-(2-Pyridinylmethyl)-2-pyridinemethanamine		$C_{12}H_{13}N_3$	1539-42-0	199.251			200^{10}, 139^{1}	1.1074^{25}	1.5757^{25}	
9371	*N*-2-Pyridinyl-2-pyridinamine		$C_{10}H_9N_3$	1202-34-2	171.198		90.5	307.5			sl H_2O, chl; vs EtOH, eth, ace, bz
9372	Pyridoxal hydrochloride	Vitamin B6	$C_8H_{10}ClNO_3$	65-22-5	203.623	orth	165 dec				vs H_2O; sl EtOH
9373	Pyridoxal 5-phosphate	Pyridoxal 5-(dihydrogen phosphate)	$C_8H_{10}NO_6P$	54-47-7	247.142	wh-ye pow or cry	141				
9374	Pyridoxamine	4-(Aminomethyl)-5-hydroxy-6-methyl-3-pyridinemethanol	$C_8H_{12}N_2O_2$	85-87-0	168.193	cry	198				s EtOH, acid
9375	Pyridoxamine dihydrochloride		$C_8H_{14}Cl_2N_2O_2$	524-36-7	241.115	pl (al)	226 dec				vs H_2O; sl EtOH
9376	Pyridoxine hydrochloride	5-Hydroxy-6-methyl-3,4-pyridinedimethanol hydrochloride	$C_8H_{12}ClNO_3$	58-56-0	205.639	pl (al, ace)	207	sub			vs H_2O
9377	1-(2-Pyridylazo)-2-naphthol	PAN	$C_{15}H_{11}N_3O$	85-85-8	249.267	red-br cry	130				i H_2O; s EtOH, eth, chl
9378	4-(2'-Pyridylazo)resorcinol	PAR	$C_{11}H_9N_3O_2$	1141-59-9	215.208	red-br cry	187 dec				
9379	Pyrilamine		$C_{17}H_{23}N_3O$	91-84-9	285.384			201^{5}			
9380	2-Pyrimidinamine		$C_4H_5N_3$	109-12-6	95.103	nd (AcOEt)	127.5	sub			s H_2O; sl chl
9381	4-Pyrimidinamine		$C_4H_5N_3$	591-54-8	95.103	pl (AcOEt)	151.5				vs H_2O, EtOH
9382	Pyrimidine	1,3-Diazine	$C_4H_4N_2$	289-95-2	80.088		22	123.8		1.4998^{20}	msc H_2O; s EtOH
9383	2,4,5,6(1*H*,3*H*)-Pyrimidinetetrone	Alloxan	$C_4H_2N_2O_4$	50-71-5	142.070		256 dec	sub			vs H_2O; s EtOH, ace, bz, HOAc
9384	2,4,5,6(1*H*,3*H*)-Pyrimidinetetrone 5-oxime	Violuric acid	$C_4H_3N_3O_4$	87-39-8	157.085	pa ye orth	203 dec				sl H_2O; s EtOH
9385	2,4,6-Pyrimidinetriamine		$C_4H_7N_5$	1004-38-2	125.133		248 dec				
9386	Pyriminil		$C_{13}H_{12}N_4O_3$	53558-25-1	272.259	solid	224 dec				
9387	Pyrithione zinc		$C_{10}H_8N_2O_2S_2Zn$	13463-41-7	317.722	wh solid	262				s chl, DMSO, DMF
9388	Pyrocatechol	1,2-Benzenediol	$C_6H_6O_2$	120-80-9	110.111	cry	104.6	245	1.344^{20}	1.604^{25}	vs H_2O, bz, eth, EtOH
9389	*L*-Pyroglutamic acid	5-Oxo-*L*-proline	$C_5H_7NO_3$	98-79-3	129.115		162				s DMSO
9390	Pyrolan		$C_{13}H_{15}N_3O_2$	87-47-8	245.277		50	$161^{0.2}$			s ctc, CS_2
9391	Pyrrobutamine	1-[4-(4-Chlorophenyl)-3-phenyl-2-butenyl]pyrrolidine	$C_{20}H_{22}ClN$	91-82-7	311.849	cry	49	$192^{0.3}$			
9392	Pyrrole	Imidole	C_4H_5N	109-97-7	67.090	liq	-23.39	129.79	0.9698^{20}	1.5085^{20}	sl H_2O; s EtOH, eth, ace, bz, chl
9393	1*H*-Pyrrole-2-carboxaldehyde		C_5H_5NO	1003-29-8	95.100	orth pr (peth)	46.5	218		1.5939^{16}	sl chl, lig
9394	1*H*-Pyrrole-2-carboxylic acid		$C_5H_5NO_2$	634-97-9	111.100	lf (w)	208 dec				s H_2O, EtOH, eth
9395	1*H*-Pyrrole-3-carboxylic acid	3-Pyrrolecarboxylic acid	$C_5H_5NO_2$	931-03-3	111.100	nd (lig)	161.5				
9396	1*H*-Pyrrole-2,5-dione		$C_4H_3NO_2$	541-59-3	97.073	pl (bz)	94	sub	1.2493^{106}		s H_2O, EtOH, eth
9397	Pyrrolidine	Azacyclopentane	C_4H_9N	123-75-1	71.121	col liq	-57.79	86.56	0.8586^{20}	1.4431^{20}	msc H_2O; s EtOH, eth; sl bz, chl
9398	1-Pyrrolidineethanamine		$C_6H_{14}N_2$	7154-73-6	114.188			166; 68^{23}	0.901^{25}	1.4687^{20}	
9399	1-Pyrrolidineethanol		$C_6H_{13}NO$	2955-88-6	115.173			187; 80^{13}	0.9750^{20}	1.4713^{20}	
9400	1-[4-(1-Pyrrolidinyl)-2-butynyl]-2-pyrrolidinone	Oxotremorine	$C_{12}H_{18}N_2O$	70-22-4	206.283	pa ye liq		$124^{0.1}$	0.991^{25}	1.5160^{20}	
9401	3-(2-Pyrrolidinyl)pyridine, (*S*)	Nornicotine	$C_9H_{12}N_2$	494-97-3	148.204	hyg		270	1.0737^{19}	1.5378^{18}	vs H_2O, ace, eth, EtOH
9402	2-Pyrrolidone	γ-Butyrolactam	C_4H_7NO	616-45-5	85.105	cry (peth)	25	251; 133^{12}	1.120^{20}	1.4806^{30}	vs H_2O, EtOH, eth, bz, chl, CS_2
9403	1-(1*H*-Pyrrol-2-yl)ethanone		C_6H_7NO	1072-83-9	109.126	mcl nd (w)	90	220			s H_2O, EtOH, eth
9404	Pyruvic acid		$C_3H_4O_3$	127-17-3	88.062		13.8	dec 165; 54^{10}	1.2272^{20}	1.4280^{20}	msc H_2O, EtOH, eth; s ace
9405	Pyrvinium chloride		$C_{26}H_{28}ClN_3$	548-84-5	417.973	red pow (w)	250 dec				
9406	1,1':4',1":4",1"'-Quaterphenyl		$C_{24}H_{18}$	135-70-6	306.400		320	428^{18}			i H_2O, EtOH, eth, chl; s bz, $PhNO_2$, HOAc
9407	Quercetin		$C_{15}H_{10}O_7$	117-39-5	302.236	ye nd (dil al, + 2 w)	316.5	sub			sl H_2O, eth, MeOH; s EtOH, ace, py
9408	Quercitrin	Quercetin-3-*L*-rhamnoside	$C_{21}H_{20}O_{11}$	522-12-3	448.377	pa ye nd or pl (+2w, dil al)	170				i H_2O, eth; s EtOH, HOAc, MeOH, alk
9409	Quillaic acid		$C_{30}H_{46}O_5$	631-01-6	486.683	nd (dil al)	294				vs ace, eth, py, EtOH
9410	Quinacrine	Mepacrine	$C_{23}H_{30}ClN_3O$	83-89-6	399.956	ye oil	87				
9411	Quinaldine Red		$C_{21}H_{23}IN_2$	117-92-0	430.325	dk red pow					s H_2O; vs EtOH
9412	Quinamine		$C_{19}H_{24}N_2O_2$	464-85-7	312.406	pr (bz), nd (80% al)	185.5				i H_2O; vs EtOH, bz; s eth, ace



N-(2-Pyridinylmethyl)-2-pyridinemethanamine



N-2-Pyridinyl-2-pyridinamine



Pyridoxal hydrochloride



Pyridoxal 5-phosphate



Pyridoxamine



Pyridoxamine dihydrochloride



Pyridoxine hydrochloride


1-(2-Pyridylazo)-2-naphthol



4-(2'-Pyridylazo)resorcinol



Pyrilamine



2-Pyrimidinamine



4-Pyrimidinamine



Pyrimidine


2,4,5,6(1*H*,3*H*)-Pyrimidinetetrone



2,4,5,6(1*H*,3*H*)-Pyrimidinetetrone 5-oxime



2,4,6-Pyrimidinetriamine



Pyriminil


Pyrithione zinc



Pyrocatechol



L-Pyroglutamic acid



Pyrolan



Pyrrobutamine


Pyrrole



1*H*-Pyrrole-2-carboxaldehyde


1*H*-Pyrrole-2-carboxylic acid



1*H*-Pyrrole-3-carboxylic acid



1*H*-Pyrrole-2,5-dione


Pyrrolidine


1-Pyrrolidineethanamine


1-Pyrrolidineethanol



1-[4-(1-Pyrrolidinyl)-2-butynyl]-2-pyrrolidinone



3-(2-Pyrrolidinyl)pyridine, (*S*)



2-Pyrrolidone



1-(1*H*-Pyrrol-2-yl)ethanone



Pyruvic acid



Pyrvinium chloride



1,1':4',1":4",1"'-Quaterphenyl



Quercetin


Quercitrin



Quillaic acid



Quinacrine



Quinaldine Red



Quinamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9413	Quinazoline	1,3-Benzodiazine	$C_8H_6N_2$	253-82-7	130.147	ye pl (peth)	48	241			vs H_2O; s EtOH, eth, ace, bz; sl chl
9414	Quinclorac	3,7-Dichloroquinoline-8-carboxylic acid	$C_{10}H_5Cl_2NO_2$	84087-01-4	242.059		274		1.75		
9415	Quinethazone		$C_{10}H_{12}ClN_3O_3S$	73-49-4	289.738						s tfa
9416	Quinic acid		$C_7H_{12}O_6$	77-95-2	192.166		162.5		1.64^{25}		vs H_2O, EtOH, HOAc
9417	Quinidine		$C_{20}H_{24}N_2O_2$	56-54-2	324.417	cry (+2.5w, dil al)	174				sl H_2O, eth; s EtOH, bz; vs chl; i peth
9418	Quinine	6'-Methoxycinchonan-9-ol, (8α,9*R*)	$C_{20}H_{24}N_2O_2$	130-95-0	324.417		57			1.625^{15}	sl H_2O, ace; vs EtOH, py; s eth, chl
9419	Quinine hydrochloride	6'-Methoxycinchonan-9-ol monohydrochloride, (8α,9*R*)	$C_{20}H_{25}ClN_2O_2$	130-89-2	360.878	silky efflor nd (w)	159				vs H_2O, EtOH, chl
9420	Quinine sulfate		$C_{40}H_{50}N_4O_8S$	804-63-7	746.912	silky nd (w)	235.2				vs EtOH
9421	Quininone		$C_{20}H_{22}N_2O_2$	84-31-1	322.401	nd, lf (eth)	108				vs bz, eth, EtOH
9422	2-Quinolinamine	2-Aminoquinoline	$C_9H_8N_2$	580-22-3	144.173	lf (w)	131.5	sub			vs H_2O; s EtOH, eth, ace, chl; sl bz
9423	3-Quinolinamine	3-Aminoquinoline	$C_9H_8N_2$	580-17-6	144.173	orth (w, dil al)	94				vs eth, EtOH, chl
9424	4-Quinolinamine	4-Aminoquinoline	$C_9H_8N_2$	578-68-7	144.173	nd (bz, dil al)	154.8	180^{12}			s H_2O, bz, chl; vs EtOH, eth
9425	5-Quinolinamine	5-Aminoquinoline	$C_9H_8N_2$	611-34-7	144.173	ye nd (al) lf (eth)	110	310; 184^{10}			sl H_2O; vs EtOH, eth; s bz; i lig
9426	6-Quinolinamine	6-Aminoquinoline	$C_9H_8N_2$	580-15-4	144.173	cry (w+2), pr (eth)	114	187^{12}			sl H_2O, eth; s NH_3, EtOH
9427	8-Quinolinamine	8-Aminoquinoline	$C_9H_8N_2$	578-66-5	144.173	pa ye nd (sub) cry (al, lig)	70	157^{19}			vs H_2O, EtOH
9428	Quinoline	1-Azanaphthalene	C_9H_7N	91-22-5	129.159	liq	-14.78	237.16	1.0977^{15}	1.6268^{20}	sl H_2O; msc EtOH, eth, ace, bz, CS_2; s ctc
9429	4-Quinolinecarboxaldehyde	Cinchoninaldehyde	$C_{10}H_7NO$	4363-93-3	157.169	nd (to-peth)	51	122^{4}			vs eth, tol
9430	2-Quinolinecarboxylic acid	Quinaldic acid	$C_{10}H_7NO_2$	93-10-7	173.169		156				s H_2O; vs bz
9431	8-Quinolinecarboxylic acid	8-Carboxyquinoline	$C_{10}H_7NO_2$	86-59-9	173.169	nd (w)	187	sub			vs EtOH
9432	2(1*H*)-Quinolinethione		C_9H_7NS	2637-37-8	161.224		187				i H_2O; vs EtOH, eth, bz; sl DMSO
9433	2-Quinolinol	2-Hydroxyquinoline	C_9H_7NO	59-31-4	145.158	pr (MeOH)	199.5	sub			sl H_2O, DMSO; vs EtOH, eth; s dil HCl
9434	3-Quinolinol	3-Hydroxyquinoline	C_9H_7NO	580-18-7	145.158	cry (bz, dil al)	201.3				i H_2O; s EtOH; sl eth, chl; vs bz
9435	4-Quinolinol	4-Hydroxyquinoline	C_9H_7NO	611-36-9	145.158	nd (w+3)	210				vs H_2O, EtOH; sl eth, bz, peth
9436	5-Quinolinol	5-Hydroxyquinoline	C_9H_7NO	578-67-6	145.158	nd (al), pl	226 dec	sub			s H_2O, bz, chl; sl EtOH; vs MeOH; i lig
9437	6-Quinolinol	6-Hydroxyquinoline	C_9H_7NO	580-16-5	145.158	pr (al, eth)	195	360			i H_2O, bz, chl; sl EtOH, eth; s alk
9438	7-Quinolinol	7-Hydroxyquinoline	C_9H_7NO	580-20-1	145.158	pr (al), nd (dil al-eth)	239	sub			vs EtOH
9439	8-Quinolinol	8-Hydroxyquinoline	C_9H_7NO	148-24-3	145.158	nd (dil al)	75.5	267	1.034^{20}		i H_2O, eth; vs EtOH, bz, chl; s ace
9440	8-Quinolinol benzoate	Benzoxiquine	$C_{16}H_{11}NO_2$	86-75-9	249.264						sl chl
9441	8-Quinolinol sulfate (2:1)	8-Hydroxyquinoline sulfate	$C_{18}H_{16}N_2O_6S$	134-31-6	388.934		177.5				vs H_2O; s EtOH; i eth
9442	Quinovic acid		$C_{30}H_{46}O_5$	465-74-7	486.683	pl or nd	298 dec				
9443	Quinovose		$C_6H_{12}O_5$	7658-08-4	164.156	cry (AcOEt)	139.5				vs H_2O, EtOH
9444	Quinoxaline	1,4-Benzodiazine	$C_8H_6N_2$	91-19-0	130.147	cry (peth)	28	229.5	1.1334^{48}	1.6231^{48}	s H_2O; msc EtOH, eth, ace, bz; sl chl
9445	2(1*H*)-Quinoxalinone		$C_8H_6N_2O$	1196-57-2	146.146	lf (al)	271	sub 200			
9446	Quizalofop-Ethyl		$C_{19}H_{17}ClN_2O_4$	76578-14-8	372.802	wh cry	93	220$^{0.2}$			i H_2O; s bz, EtOH, ace, xyl
9447	Radicinin		$C_{12}H_{12}O_5$	10088-95-6	236.220		221.5				sl chl
9448	Raffinose		$C_{18}H_{32}O_{16}$	512-69-6	504.437		80		1.465^{25}		s H_2O, py; vs MeOH; sl EtOH; i eth
9449	Ranitidine		$C_{13}H_{22}N_4O_3S$	66357-35-5	314.404	solid	69.5				



Quinazoline



Quinclorac



Quinethazone



Quinic acid



Quinidine



Quinine



Quinine hydrochloride



Quinine sulfate



Quininone



2-Quinolinamine



3-Quinolinamine



4-Quinolinamine



5-Quinolinamine



6-Quinolinamine



8-Quinolinamine



Quinoline



4-Quinolinecarboxaldehyde



2-Quinolinecarboxylic acid



8-Quinolinecarboxylic acid



2(1*H*)-Quinolinethione



2-Quinolinol



3-Quinolinol



4-Quinolinol



5-Quinolinol



6-Quinolinol



7-Quinolinol



8-Quinolinol



8-Quinolinol benzoate



8-Quinolinol sulfate (2:1)



Quinovic acid



Quinovose



Quinoxaline


2(1*H*)-Quinoxalinone



Quizalofop-Ethyl



Radicinin



Raffinose



Ranitidine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9450	Raubasine		$C_{21}H_{24}N_2O_3$	483-04-5	352.427		258 dec				i H_2O; s MeOH
9451	Raunescine		$C_{31}H_{36}N_2O_8$	117-73-7	564.626		165				i H_2O; s EtOH, chl, HOAc
9452	Reinecke salt		$C_4H_{12}CrN_7OS_4$	13573-16-5	354.440	red cry (w)	270 dec				s H_2O, EtOH, ace; i bz
9453	Resazurin	7-Hydroxy-3*H*-phenoxazin-3-one, 10-oxide	$C_{12}H_7NO_4$	550-82-3	229.189	dk red to gr pr or pl (HOAc)		sub			i H_2O, eth; sl EtOH, HOAc; s alk
9454	Rescinnamine		$C_{35}H_{42}N_2O_9$	24815-24-5	634.716	nd (bz)	238.5				i H_2O; sl EtOH; s ace, chl, AcOEt
9455	Reserpic acid		$C_{22}H_{28}N_2O_5$	83-60-3	400.467	cry (MeOH)	242				
9456	Reserpine		$C_{33}H_{40}N_2O_9$	50-55-5	608.679	lo pr (dil ace)	264.5				sl H_2O, eth, ace; s EtOH, bz, AcOEt
9457	*cis*-Resmethrin, (-)		$C_{22}H_{26}O_3$	10453-86-8	338.439		75				
9458	Resorcinol	1,3-Benzenediol	$C_6H_6O_2$	108-46-3	110.111	nd (bz), pl (w)	109.4	276.5; 178^{16}	1.278^{20}	1.578^{25}	vs H_2O, ctc; s EtOH, eth; sl bz, chl
9459	11-*cis*-Retinal	Vitamin A_1 aldehyde	$C_{20}H_{28}O$	564-87-4	284.435	cry					
9460	Retinal (all *trans*)		$C_{20}H_{28}O$	116-31-4	284.435	oran cry	64				i H_2O; s EtOH, chl, cy, peth
9461	13-*cis*-Retinoic acid	Accutane	$C_{20}H_{28}O_2$	4759-48-2	300.435	cry (EtOH)	189				
9462	13-*trans*-Retinoic acid		$C_{20}H_{28}O_2$	302-79-4	300.435	cry (MeOH)	181.5				
9463	Retinol	Vitamin A	$C_{20}H_{30}O$	68-26-8	286.451	ye pr (peth)	63.5	$137^{0.000001}$			i H_2O; s EtOH, eth, ace, bz
9464	Retinyl palmitate	Retinol, hexadecanoate	$C_{36}H_{60}O_2$	79-81-2	524.860		28				
9465	Retronecine, (+)		$C_8H_{13}NO_2$	480-85-3	155.195	cry (ace)	121				s H_2O, EtOH; sl eth
9466	Retrorsine		$C_{18}H_{25}NO_6$	480-54-6	351.395	cry (AcOEt)	212				sl H_2O, ace; s EtOH, chl; i eth
9467	Rhamnetin		$C_{16}H_{12}O_7$	90-19-7	316.262	ye nd (al)	295				sl H_2O; s EtOH, ace, PhOH; vs dil alk
9468	*DL*-α-Rhamnose		$C_6H_{12}O_5$	116908-82-8	164.156	cry (w)	151				vs H_2O, EtOH
9469	*D*-Rhamnose	6-Deoxy-*D*-mannose	$C_6H_{12}O_5$	634-74-2	164.156						s H_2O
9470	Rheadine		$C_{21}H_{21}NO_6$	2718-25-4	383.395	nd (chl, eth, al)	257	sub			
9471	Rhein		$C_{15}H_8O_6$	478-43-3	284.221	ye or oran nd (MeOH, py)	321	sub			sl H_2O, EtOH, eth, ace, bz; vs py
9472	Rhenium carbonyl	Dirhenium decacarbonyl	$C_{10}O_{10}Re_2$	14285-68-8	652.515	ye-wh cry	170 dec		2.87		s os
9473	Rhizopterin		$C_{15}H_{12}N_6O_4$	119-20-0	340.294	lt ye pl (w)	>300				i H_2O, EtOH, eth; s aq alk, aq NH_3, py
9474	Rhodamine B		$C_{28}H_{32}ClN_2O_3$	81-88-9	480.018		165				s H_2O, EtOH, eth, bz, xyl
9475	Rhodium carbonyl chloride	Dirhodium tetracarbonyl dichloride	$C_4Cl_2O_4Rh_2$	14523-22-9	388.758	red-oran cry	124				s os
9476	Ribavirin	Tribavirin	$C_8H_{12}N_4O_5$	36791-04-5	244.205	col cry (EtOH)	175				s H_2O
9477	Ribitol	Adonitol	$C_5H_{12}O_5$	488-81-3	152.146	pr (w), nd (al)	104				s H_2O, EtOH; i eth, lig
9478	Riboflavin		$C_{17}H_{20}N_4O_6$	83-88-5	376.364	ye or oran-ye nd (w)	280 dec				i H_2O, eth, ace, chl; sl EtOH
9479	Riboflavin-5'-phosphate		$C_{17}H_{20}N_4O_9P$	146-17-8	455.336	ye cry (w)					
9480	*D*-Ribose		$C_5H_{10}O_5$	50-69-1	150.130	pl (al)	88				s H_2O; sl EtOH
9481	*L*-Ribose		$C_5H_{10}O_5$	24259-59-4	150.130		81				
9482	*D*-Ribulose	*erythro*-2-Pentulose	$C_5H_{10}O_5$	488-84-6	150.130	syrup					vs H_2O
9483	Ricinine	1,2-Dihydro-4-methoxy-1-methyl-2-oxo-3-pyridinecarbonitrile	$C_8H_8N_2O_2$	524-40-3	164.162	pr or lf (w, al)	201.5	sub 170			s H_2O, chl; sl EtOH, bz; vs py; i peth
9484	Rifabutin		$C_{46}H_{62}N_4O_{11}$	72559-06-9	847.004	viol-red cry					i H_2O; vs chl; s MeOH; sl EtOH
9485	Rifampin		$C_{43}H_{58}N_4O_{12}$	13292-46-1	822.941	red-oran pl (ace)	185 dec				
9486	Rinderine	Echinatine-3'-epimer	$C_{15}H_{25}NO_5$	6029-84-1	299.364	cry (ace)	100.5				
9487	Ronnel		$C_8H_8Cl_3O_3PS$	299-84-3	321.546		41	$152^{0.4}$	1.44^{32}	1.5335^{35}	
9488	Rotenone		$C_{23}H_{22}O_6$	83-79-4	394.417	nd or lf (al, aq-ace)	176	$215^{0.5}$			i H_2O; s EtOH, ace, bz; sl eth; vs chl
9489	Rubijervine		$C_{27}H_{43}NO_2$	79-58-3	413.636	nd (+1w, dil al)	242				vs bz, EtOH, chl
9490	Rubratoxin B		$C_{26}H_{30}O_{11}$	21794-01-4	518.509	cry (MeCN)	169 dec				



Raubasine



Raunescine



Reinecke salt


Resazurin



Rescinnamine



Reserpic acid



Reserpine



cis-Resmethrin, (-)



Resorcinol



11-*cis*-Retinal



Retinal (all *trans*)



13-*cis*-Retinoic acid



13-*trans*-Retinoic acid



Retinol



Retinyl palmitate



Retronecine, (+)



Retrorsine



Rhamnetin



DL-α-Rhamnose



D-Rhamnose



Rheadine



Rhein



Rhenium carbonyl



Rhizopterin



Rhodamine B



Rhodium carbonyl chloride



Ribavirin



Ribitol



Riboflavin



Riboflavin-5'-phosphate



D-Ribose



L-Ribose



D-Ribulose



Ricinine



Rifabutin



Rifampin


Rinderine



Ronnel



Rotenone



Rubijervine



Rubratoxin B


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9491	Rutecarpine		$C_{18}H_{13}N_3O$	84-26-4	287.315	ye nd (al, AcOEt)	259.5				sl EtOH, ace, bz
9492	Ruthenium dodecacarbonyl	Triruthenium dodecacarbonyl	$C_{12}O_{12}Ru_3$	15243-33-1	639.33	oran cry	dec 150				
9493	Ruthenium(III) 2,4-pentanedioate	Ruthenium(III) acetylacetonate	$C_{15}H_{21}O_6Ru$	14284-93-6	398.39		230				
9494	Rutinose		$C_{12}H_{22}O_{10}$	90-74-4	326.297	hyg pow (al, eth)	190 dec				vs H_2O, EtOH
9495	Sabadine		$C_{29}H_{47}NO_8$	124-80-1	537.685	nd (eth)	258				vs ace, EtOH
9496	Saccharin		$C_7H_5NO_3S$	81-07-2	183.185	nd (ace) pr (al), lf (w)	228 dec	sub	0.828^{25}		sl H_2O, bz, eth, chl; s ace, EtOH
9497	Saccharin sodium	1,2-Benzisothiazolin-3-one, 1,1-dioxide, sodium salt	$C_7H_4NNaO_3S$	128-44-9	205.168	wh cry	229				s H_2O
9498	Safranal	2,6,6-Trimethyl-1,3-cyclohexadiene-1-carboxaldehyde	$C_{10}H_{14}O$	116-26-7	150.217			70^{1}	0.9734^{19}	1.5281^{19}	vs EtOH, peth
9499	Safrole	5-(2-Propenyl)-1,3-benzodioxole	$C_{10}H_{10}O_2$	94-59-7	162.185	mcl	11.2	234.5	1.1000^{20}	1.5381^{20}	i H_2O; vs EtOH; msc eth, chl
9500	Salcomine	*N,N'*-Bis(salicylidene) ethylenediaminocobalt(II)	$C_{16}H_{14}CoN_2O_2$	14167-18-1	325.227	red cry (DMF)					s bz, chl, py
9501	Salicylaldehyde	2-Hydroxybenzaldehyde	$C_7H_6O_2$	90-02-8	122.122	liq	-7	197	1.1674^{20}	1.5740^{20}	sl H_2O, chl; msc EtOH; vs ace, bz
9502	Salicylaldoxime		$C_7H_7NO_2$	94-67-7	137.137		57				sl H_2O; vs EtOH, eth, bz; s chl; i lig
9503	Salsoline		$C_{11}H_{15}NO_2$	89-31-6	193.243	pow or cry (al)	221.5				sl H_2O, EtOH; i eth, peth; s chl, alk
9504	Salvarsan dihydrochloride	Arsphenamine	$C_{12}H_{14}As_2Cl_2N_2O_2$	139-93-5	439.001	ye hyg pow	190 dec				vs H_2O
9505	Sanguinarine		$C_{20}H_{13}NO_5$	2447-54-3	349.337	cry (eth, al)	266				vs ace, bz, eth, EtOH
9506	α-Santalol		$C_{15}H_{24}O$	115-71-9	220.351			301.5	0.9679^{20}	1.5023^{20}	i H_2O; s EtOH
9507	β-Santalol		$C_{15}H_{24}O$	77-42-9	220.351			167^{10}	0.9750^{20}	1.5115^{20}	
9508	Santonic acid		$C_{15}H_{20}O_4$	510-35-0	264.318	cry	171	285^{15}			sl H_2O; s chl, eth, HOAc, EtOH
9509	α-Santonin		$C_{15}H_{18}O_3$	481-06-1	246.302	orth (w, eth)	175		1.590^{25}		sl H_2O, EtOH, eth; s bz, chl; i peth
9510	Sarcosine	*N*-Methylglycine	$C_3H_7NO_2$	107-97-1	89.094	cry (al)	212 dec				s H_2O
9511	Sarmentogenin		$C_{23}H_{34}O_5$	76-28-8	390.513	pr (95% al, MeOH-eth)	280				i H_2O, eth, bz; s EtOH; sl ace, chl
9512	Sarpagan-17-al	Vellosimine	$C_{19}H_{20}N_2O$	6874-98-2	292.374	cry (MeOH)	305.5	sub 180			
9513	Sarpagan-10,17-diol	Sarpagine	$C_{19}H_{22}N_2O_2$	482-68-8	310.390	nd	320				i H_2O; s EtOH
9514	Saxitoxin dihydrochloride		$C_{10}H_{19}Cl_2N_7O_4$	35554-08-6	372.209	hyg wh solid					vs H_2O, MeOH, EtOH
9515	Scarlet red		$C_{24}H_{20}N_4O$	85-83-6	380.442	dk br pow or nd	185; dec 260				i H_2O; sl ace, bz; vs chl, peth
9516	Schradan		$C_8H_{24}N_4O_3P_2$	152-16-9	286.250		17	154$^{2.0}$	1.09^{25}	1.462^{25}	vs H_2O, EtOH, chl
9517	Scilliroside		$C_{32}H_{44}O_{12}$	507-60-8	620.684	lo pr (dil MeOH)	169	dec			sl H_2O, ace, chl; vs EtOH, diox; i eth
9518	Scopolamine		$C_{17}H_{21}NO_4$	51-34-3	303.354	visc liq					vs hot H_2O, EtOH, ace; sl bz
9519	Scopoline		$C_8H_{13}NO_2$	487-27-4	155.195	hyg nd (lig, eth, chl, peth)	108.5	248	1.0891^{134}		s H_2O
9520	Sebacic acid		$C_{10}H_{18}O_4$	111-20-6	202.248	lf	130.9	295^{100}, 232^{10}	1.2705^{20}	1.422^{133}	sl H_2O; s EtOH, eth; i bz
9521	Selenium methionine	Selenomethionine	$C_5H_{11}NO_2Se$	1464-42-2	196.11	hex pl (MeOH aq)	265 dec				
9522	Selenoformaldehyde		CH_2Se	6596-50-5	92.99	unstab gas					
9523	Selenourea	Carbamimidoselenoic acid	CH_4N_2Se	630-10-4	123.02	pr or nd (w)		dec 200			vs H_2O
9524	Semicarbazide hydrochloride		CH_6ClN_3O	563-41-7	111.531	pr (dil al)	176 dec				vs H_2O
9525	Senecionine		$C_{18}H_{25}NO_5$	130-01-8	335.396	pl	232				i H_2O; sl EtOH, eth; s chl
9526	Seneciphylline		$C_{18}H_{23}NO_5$	480-81-9	333.380	pl (AcOEt)	217 dec				s chl; sl EtOH, ace; i eth
9527	Senkirkin		$C_{19}H_{27}NO_6$	2318-18-5	365.420	pl (ace)	197				
9528	*L*-Sepiapterin	6-Lactoyl-7,8-dihydropterin	$C_9H_{11}N_5O_3$	17094-01-8	237.215	ye pow or cry					
9529	*DL*-Serine		$C_3H_7NO_3$	302-84-1	105.093	mcl pr or lf (w)	246 dec		1.603^{22}		s H_2O; i EtOH, eth, bz, HOAc



Rutecarpine



Ruthenium dodecacarbonyl



Ruthenium(III) 2,4-pentanedioate



Rutinose



Sabadine



Saccharin



Saccharin sodium



Safranal



Safrole



Salcomine



Salicylaldehyde



Salicylaldoxime



Salsoline



Salvarsan dihydrochloride



Sanguinarine



α-Santalol



β-Santalol



Santonic acid



α-Santonin



Sarcosine



Sarmentogenin



Sarpagan-17-al



Sarpagan-10,17-diol



Saxitoxin dihydrochloride



Scarlet red



Schradan


Scilliroside



Scopolamine



Scopoline



Sebacic acid



Selenium methionine



Selenoformaldehyde



Selenourea



Semicarbazide hydrochloride


Senecionine



Seneciphylline



Senkirkin



L-Sepiapterin



DL-Serine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9530	*D*-Serine		$C_3H_7NO_3$	312-84-5	105.093	nd or hex pr (w)	229 dec	dec			vs H_2O; i EtOH, eth, bz, HOAc
9531	*L*-Serine	2-Amino-3-hydroxypropanoic acid, (*S*)	$C_3H_7NO_3$	56-45-1	105.093	hex pl or pr (w)	228 dec	sub 150	1.6^{22}		s H_2O; i EtOH, eth, bz, HOAc
9532	Serpentine alkaloid		$C_{21}H_{20}N_2O_3$	18786-24-8	348.395		175				i H_2O; s EtOH, eth, ace
9533	Sesin	2,4-Dichlorophenoxyethyl benzoate	$C_{15}H_{12}Cl_2O_3$	94-83-7	311.160	cry	66	$185^{1.5}$			
9534	Sesone	Sodium 2-(2,4-dichlorophenoxy)ethyl sulfate	$C_8H_7Cl_2NaO_5S$	136-78-7	309.100		245 dec				
9535	Sethoxydim		$C_{17}H_{29}NO_3S$	74051-80-2	327.482			$>90^{0.00003}$	1.043^{25}		
9536	Shikimic acid		$C_7H_{10}O_5$	138-59-0	174.151	nd	184	subl			sl EtOH; i eth, bz, chl
9537	Siduron		$C_{14}H_{20}N_2O$	1982-49-6	232.321	cry solid	135				s EtOH, DMF, CH_2Cl_2
9538	Silvex	Propanoic acid, 2-(2,4,5-trichlorophenoxy)-	$C_9H_7Cl_3O_3$	93-72-1	269.509		181.6				
9539	Simazine	1,3,5-Triazine-2,4-diamine, 6-chloro-*N,N'*-diethyl-	$C_7H_{12}ClN_5$	122-34-9	201.657		226		1.302^{20}		
9540	Simfibrate		$C_{23}H_{26}Cl_2O_6$	14929-11-4	469.354	cry	52	$225^{0.15}$			
9541	Sinapinic acid	3-(4-Hydroxy-3,5-dimethoxyphenyl)-2-propenoic acid	$C_{11}H_{12}O_5$	530-59-6	224.210	wh pow					i H_2O; s MeOH, ace
9542	Sinomenine		$C_{19}H_{23}NO_4$	115-53-7	329.391	nd (bz)	162				sl H_2O, eth, bz; s EtOH, ace, dil alk
9543	α_1-Sitosterol	4-Methylstigmasta-7,24(28)-dien-3-ol, (3β,4α,5α,24Z)	$C_{30}H_{50}O$	474-40-8	426.717	nd (al)	166				vs EtOH, chl
9544	Sodium arsanilate	Sodium (4-aminophenyl) arsonate	$C_6H_7AsNNaO_3$	127-85-5	239.037	wh cry					s H_2O
9545	Sodium ascorbate		$C_6H_7NaO_6$	134-03-2	198.106	cry	218 dec				
9546	Sodium benzenesulfinate		$C_6H_5NaO_2S$	873-55-2	164.158	cry	300				
9547	Sodium benzenesulfonate	Monosodium benzenesulfonate	$C_6H_5NaO_3S$	515-42-4	180.157		>300				s H_2O; sl EtOH
9548	Sodium benzoate		$C_7H_5NaO_2$	532-32-1	144.104		>300				s H_2O
9549	Sodium cacodylate	Sodium dimethylarsonate	$C_2H_6AsNaO_2$	124-65-2	159.980	gran cry	60 (hyd)				vs H_2O; s EtOH
9550	Sodium 2,2-dichloropropanoate		$C_3H_3Cl_2NaO_2$	127-20-8	164.951	hyg pow	166 dec				
9551	Sodium diethyldithiocarbamate	Dithiocarb sodium	$C_5H_{10}NNaS_2$	148-18-5	171.260	cry (EtOH)	95				s H_2O, EtOH, MeOH, ace; i eth, bz
9552	Sodium diethyldithiocarbamate trihydrate	Diethyldithiocarbamate sodium salt trihydrate	$C_5H_{16}NNaO_3S_2$	20624-25-3	225.306	orth cry (ace)	95				vs H_2O; s EtOH, ace; i bz, eth
9553	Sodium 4,5-dihydroxy-2,7-naphthalenedisulfonic acid	Chromotropic acid disodium salt	$C_{10}H_6Na_2O_8S_2$	129-96-4	364.260	wh nd or lf (w)					vs H_2O
9554	Sodium dimethyldithiocarbamate		$C_3H_7NNaS_2$	128-04-1	144.215	col cry (w)	121 (hyd)				
9555	Sodium 4-dodecylbenzenesulfonate		$C_{18}H_{29}NaO_3S$	2211-98-5	348.476	cry	144				
9556	Sodium dodecyl sulfate	Sodium lauryl sulfate	$C_{12}H_{25}NaO_4S$	151-21-3	288.379	wh pow	205				
9557	Sodium ethanolate	Sodium ethoxide	C_2H_5NaO	141-52-6	68.050	hyg wh pow	260 dec				reac H_2O; s EtOH
9558	Sodium fluoroacetate		$C_2H_2FNaO_2$	62-74-8	100.024	wh mcl cry	200				i ace, chl; sl EtOH, MeOH
9559	Sodium formaldehyde bisulfite	Sodium hydroxymethanesulfonate	CH_3NaO_4S	870-72-4	134.088	cry (EtOH aq)					
9560	Sodium formaldehydesulfoxylate	Sodium hydroxymethanesulfinate	CH_3NaO_3S	149-44-0	118.088	cry (w)	63 (hyd)				s H_2O; i EtOH, bz, eth
9561	Sodium gluconate		$C_6H_{11}NaO_7$	527-07-1	218.137						s H_2O
9562	Sodium 2-hydroxyethanesulfonate	Monosodium 2-hydroxyethanesulfonate	$C_2H_5NaO_4S$	1562-00-1	148.114						s H_2O
9563	Sodium 2-hydroxy-2-propanesulfonate	Monosodium 2-hydroxy-2-propanesulfonate	$C_3H_7NaO_4S$	540-92-1	162.141	cry					s H_2O; sl EtOH
9564	Sodium iodomethanesulfonate	Methiodal sodium	CH_2INaO_3S	126-31-8	243.984	cry					sl EtOH, ace, bz
9565	Sodium *O*-isopropyl xanthate		$C_4H_7NaOS_2$	140-93-2	158.218	hyg wh-ye pow	150 dec				
9566	Sodium methanolate	Sodium methoxide	CH_3NaO	124-41-4	54.024	wh hyg tetr cry	300				reac H_2O; s MeOH, EtOH
9567	Sodium methylarsonate		CH_4AsNaO_3	2163-80-6	161.953	cry (w)	115				vs H_2O; s MeOH; i os
9568	Sodium methyldithiocarbamate	Metham sodium	$C_2H_4NNaS_2$	137-42-8	129.180	cry (w)					vs H_2O
9569	Sodium β-naphthoquinone-4-sulfonate	Sodium 3,4-dihydro-3,4-dioxo-1-naphthalenesulfonate	$C_{10}H_5NaO_5S$	521-24-4	260.199		287 dec				
9570	Sodium 2-oxopropanoate		$C_3H_3NaO_3$	113-24-6	110.044						s H_2O; sl abs EtOH
9571	Sodium phenolate	Sodium phenoxide	C_6H_5NaO	139-02-6	116.093	hyg cry	384				vs H_2O; s EtOH, thf



D-Serine



L-Serine



Serpentine alkaloid



Sesin



Sesone



Sethoxydim



Shikimic acid



Siduron



Silvex



Simazine



Simfibrate



Sinapinic acid



Sinomenine



α_1-Sitosterol


Sodium arsanilate



Sodium ascorbate



Sodium benzenesulfinate



Sodium benzenesulfonate



Sodium benzoate



Sodium cacodylate



Sodium 2,2-dichloropropanoate



Sodium diethyldithiocarbamate


Sodium diethyldithiocarbamate trihydrate



Sodium 4,5-dihydroxy-2,7-naphthalenedisulfonic acid



Sodium dimethyldithiocarbamate



Sodium 4-dodecylbenzenesulfonate



Sodium dodecyl sulfate



Sodium ethanolate



Sodium fluoroacetate



Sodium formaldehyde bisulfite



Sodium formaldehydesulfoxylate



Sodium gluconate



Sodium 2-hydroxyethanesulfonate



Sodium 2-hydroxy-2-propanesulfonate



Sodium iodomethanesulfonate



Sodium *O*-isopropyl xanthate



Sodium methanolate


Sodium methylarsonate



Sodium methyldithiocarbamate



Sodium β-naphthoquinone-4-sulfonate



Sodium 2-oxopropanoate



Sodium phenolate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9572	Sodium propanoate		$C_3H_5NaO_2$	137-40-6	96.061						sl H_2O
9573	Sodium sulfobromophthalein	Sulfobromophthalein sodium	$C_{20}H_8Br_4Na_2O_{10}S_2$	71-67-0	837.998	hyg cry					s H_2O; i EtOH, ace
9574	Sodium tartrate		$C_4H_4Na_2O_6$	868-18-8	194.051						s H_2O
9575	Sodium tartrate dihydrate		$C_4H_8Na_2O_8$	6106-24-7	230.082				1.545^{25}		s H_2O; i EtOH
9576	Sodium tetraphenylborate		$C_{24}H_{20}BNa$	143-66-8	342.217	nd	300				s H_2O, EtOH, ace; sl eth, chl; i peth
9577	Sodium trichloroacetate		$C_2Cl_3NaO_2$	650-51-1	185.369	ye-wh pow	300				s H_2O, EtOH
9578	Sodium trifluoroacetate		$C_2F_3NaO_2$	2923-18-4	136.005	cry	207 dec				
9579	Solanid-5-ene-3,18-diol, (3β)	Isorubijervine	$C_{27}H_{43}NO_2$	468-45-1	413.636	pr(al)	242.5				vs bz, chl
9580	Solanine		$C_{45}H_{73}NO_{15}$	20562-02-1	868.060	nd (EtOH aq)	286 dec				i H_2O, eth, chl; s hot EtOH
9581	Solanone		$C_{13}H_{22}O$	1937-54-8	194.313			60^{1}	0.870^{20}	1.4755^{20}	
9582	Soman		$C_7H_{16}FO_2P$	96-64-0	182.173	liq					
9583	Sophoricoside		$C_{21}H_{20}O_{10}$	152-95-4	432.378		274				
9584	Sorbitan oleate		$C_{24}H_{44}O_6$	1338-43-8	428.602	ye oil			0.986	1.4800^{20}	i H_2O; s EtOH
9585	*L*-Sorbose	*L*-Sorbinose	$C_6H_{12}O_6$	87-79-6	180.155	orth (al)	165		1.612^{17}		s H_2O; sl EtOH, eth, MeOH
9586	Sparteine		$C_{15}H_{26}N_2$	90-39-1	234.380		30.5	325; 173^{8}	1.0196^{20}	1.5312^{20}	vs eth, EtOH, chl
9587	Spinulosin		$C_8H_8O_5$	85-23-4	184.147	red-bl	202.5	sub 120			sl H_2O; s alk
9588	Spironolactone		$C_{24}H_{32}O_4S$	52-01-7	416.574			134			
9589	Spiro[2.2]pentane		C_5H_8	157-40-4	68.118	liq	-107.0	39	0.7266^{20}	1.4120^{20}	
9590	Spirosolan-3-ol, (3β,5α,22β,25*S*)	Tomatidine	$C_{27}H_{45}NO_2$	77-59-8	415.652	pl	210.5				s EtOH, eth
9591	Spirosol-5-en-3-ol, (3β,22α,25*R*)	Solasodine	$C_{27}H_{43}NO_2$	126-17-0	413.636	hex pl (sub)	202				s EtOH, ace, bz, diox, py; sl eth; vs chl
9592	Spirostan-2,3-diol, (2α,3β,5α,25*R*)	Gitogenin	$C_{27}H_{44}O_4$	511-96-6	432.636	lf (bz), nd (eth)	271.5				i H_2O; s EtOH, chl; sl eth
9593	Spirostan-3-ol, (3β,5α,25*R*)	Tigogenin	$C_{27}H_{44}O_3$	77-60-1	416.636	lf (al +1w) pr (ace)	205.5				s EtOH, eth, ace, ctc, MeOH, peth
9594	Spirostan-3-ol, (3β,5β,25*R*)	Smilagenin	$C_{27}H_{44}O_3$	126-18-1	416.636	nd (ace)	185				vs ace, bz, EtOH
9595	Spirostan-3-ol, (3β,5β,25*S*)	Sarsasapogenin	$C_{27}H_{44}O_3$	126-19-2	416.636	lo pr, nd (ace)	200.5				s EtOH, ace, bz, chl
9596	Spirostan-2,3,15-triol, (2α,3β,5α,15β,25*R*)	Digitogenin	$C_{27}H_{44}O_5$	511-34-2	448.635	nd (al)	281.5				vs chl
9597	Spirost-5-en-3-ol, (3β,25*R*)	Diosgenin	$C_{27}H_{42}O_3$	512-04-9	414.620	cry (ace)	205.5				vs EtOH
9598	Spiro[5.5]undecane		$C_{11}H_{20}$	180-43-8	152.277			208	0.8783^{20}	1.4731	
9599	S-Propyl thioacetate		$C_5H_{10}OS$	2307-10-0	118.197			137.9	0.9535^{25}		
9600	Squalene		$C_{30}H_{50}$	111-02-4	410.718	oil	-4.8	421.3; 280^{17}	0.8584^{20}	1.4990^{20}	i H_2O; sl EtOH; s eth, ace, ctc
9601	Stachydrine		$C_7H_{13}NO_2$	471-87-4	143.184	cry (w+1)	235				vs H_2O, EtOH
9602	Stanozolol		$C_{21}H_{32}N_2O$	10418-03-8	328.491	cry (EtOH)	≈236				
9603	Stearaldehyde		$C_{18}H_{36}O$	638-66-4	268.478	nd (peth)		261			
9604	Stearic acid	Octadecanoic acid	$C_{18}H_{36}O_2$	57-11-4	284.478	mcl lf (al)	69.3	dec 350; 232^{15}	0.9408^{20}	1.4299^{80}	i H_2O; sl EtOH, bz; s ace, chl, CS_2
9605	Stearic acid anhydride	Octadecanoic anhydride	$C_{36}H_{70}O_3$	638-08-4	550.939		72		0.8365^{82}	1.4362^{80}	i H_2O, EtOH; sl eth, bz
9606	Sterigmatocystin		$C_{18}H_{12}O_6$	10048-13-2	324.284	ye nd	246 dec				
9607	Stigmasta-5,7-dien-3-ol, (3β)	7-Dehydrositosterol	$C_{29}H_{48}O$	521-04-0	412.690		144.5				vs bz, eth, EtOH
9608	Stigmasta-5,22-dien-3-ol, (3β,22*E*)	Stigmasterol	$C_{29}H_{48}O$	83-48-7	412.690		170				vs bz, eth, EtOH
9609	Stigmastan-3-ol, (3β,5α)		$C_{29}H_{52}O$	83-45-4	416.722		144				
9610	Stigmast-5-en-3-ol, (3β,24*R*)	β-Sitosterol	$C_{29}H_{50}O$	83-46-5	414.706	pl (al)	137				s EtOH, eth, HOAc
9611	Stigmast-5-en-3-ol, (3β,24*S*)	γ-Sitosterol	$C_{29}H_{50}O$	83-47-6	414.706	cry (EtOH)	148				s EtOH
9612	*cis*-Stilbene	*cis*-1,2-Diphenylethene	$C_{14}H_{12}$	645-49-8	180.245		-5	141^{12}	1.0143^{20}	1.6130^{20}	i H_2O; s EtOH, eth, ace, bz, peth, chl
9613	*trans*-Stilbene	*trans*-1,2-Diphenylethene	$C_{14}H_{12}$	103-30-0	180.245	cry (al)	124.2	307; 166^{12}	0.9707^{20}	1.6264^{17}	i H_2O; sl EtOH, chl; vs eth, bz
9614	Streptomycin	*N*-Methyl-*L*-glucosamidinostreptosidostreptidine	$C_{21}H_{39}N_7O_{12}$	57-92-1	581.575	hyg pow					s H_2O
9615	Streptomycin sulfate		$C_{42}H_{84}N_{14}O_{36}S_3$	3810-74-0	1457.383	pow	≈230 dec				
9616	Streptozotocin		$C_8H_{15}N_3O_7$	18883-66-4	265.221	pl	115 dec				s H_2O, EtOH
9617	Strophanthidin		$C_{23}H_{32}O_6$	66-28-4	404.496	orth tab (MeOH-w) lf (w+2)	173 dec				i H_2O, eth; s EtOH, ace, bz, HOAc, chl



Sodium propanoate



Sodium sulfobromophthalein



Sodium tartrate



Sodium tartrate dihydrate



Sodium tetraphenylborate



Sodium trichloroacetate



Sodium trifluoroacetate



Solanid-5-ene-3,18-diol, (3β)



Solanine



Solanone



Soman



Sophoricoside


Sorbitan oleate



L-Sorbose



Sparteine



Spinulosin



Spironolactone



Spiro[2.2]pentane



Spirosolan-3-ol, (3β,5α,22β,25*S*)



Spirosol-5-en-3-ol, (3β,22α,25*R*)



Spirostan-2,3-diol, (2α,3β,5α,25*R*)


Spirostan-3-ol, (3β,5α,25*R*)



Spirostan-3-ol, (3β,5β,25*R*)



Spirostan-3-ol, (3β,5β,25*S*)



Spirostan-2,3,15-triol, (2α,3β,5α,15β,25*R*)



Spirost-5-en-3-ol, (3β,25*R*)



Spiro[5.5]undecane



S-Propyl thioacetate



Squalene


Stachydrine



Stanozolol



Stearaldehyde



Stearic acid



Stearic acid anhydride



Sterigmatocystin


Stigmasta-5,7-dien-3-ol, (3β)



Stigmasta-5,22-dien-3-ol, (3β,22*E*)



Stigmastan-3-ol, (3β,5α)



Stigmast-5-en-3-ol, (3β,24*R*)


Stigmast-5-en-3-ol, (3β,24*S*)



cis-Stilbene


trans-Stilbene



Streptomycin


Streptomycin sulfate



Streptozotocin


Strophanthidin


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9618	Strychnidin-10-one mononitrate	Strychnine nitrate	$C_{21}H_{23}N_3O_5$	66-32-0	397.425	nd (w)	295		1.627^{25}		vs H_2O, MeOH; sl bz; s chl, EtOH
9619	Strychnidin-10-one sulfate (2:1)	Strychnine sulfate	$C_{42}H_{46}N_4O_8S$	60-41-3	766.901		200 dec				s H_2O, EtOH, MeOH; i eth; sl chl
9620	Strychnine		$C_{21}H_{22}N_2O_2$	57-24-9	334.412	orth pr (al)	287	270^{5}	1.36^{20}		sl H_2O, EtOH, ace, bz; i eth; s chl
9621	Styrene	Vinylbenzene	C_8H_8	100-42-5	104.150	liq	-30.65	145	0.9016^{25}	1.5440^{25}	i H_2O; s EtOH, eth, ace; msc bz; sl ctc
9622	Succimer	2,3-Dimercaptobutanedioic acid, (*R**,*S**)	$C_4H_6O_4S_2$	304-55-2	182.219	wh cry (MeOH)	193				
9623	Succinamide		$C_4H_8N_2O_2$	110-14-5	116.119	orth nd (w)	268 dec	sub 125			s H_2O
9624	Succinic acid		$C_4H_6O_4$	110-15-6	118.089	tcl or mcl pr	187.9	dec 235	1.572^{25}	1.450	sl H_2O, DMSO; s EtOH, eth, ace; i bz
9625	Succinic anhydride		$C_4H_4O_3$	108-30-5	100.073	nd (al), orth pym (chl)	119	261	1.2^{20}		i H_2O; s EtOH, chl; sl eth
9626	Succinimide		$C_4H_5NO_2$	123-56-8	99.089	pl (+1w, al) orth (ace)	126.5	dec 287	1.418^{25}		s H_2O; sl EtOH, eth, ace
9627	Succinonitrile	Butanedinitrile	$C_4H_4N_2$	110-61-2	80.088		57.98	266	0.9867^{60}	1.4173^{60}	vs H_2O; s EtOH, ace, bz, chl; sl eth
9628	Succinylcholine chloride	Suxamethonium chloride	$C_{14}H_{30}Cl_2N_2O_4$	71-27-2	361.305	cry (w)	190				sl EtOH, bz, chl; i eth
9629	Succinylsulphathiazole		$C_{13}H_{13}N_3O_5S_2$	116-43-8	355.389	cry	193.5				i H_2O, eth, chl; sl EtOH, ace; s alk
9630	Sucralfate		$C_{12}H_{54}Al_{16}O_{75}S_8$	54182-58-0	2086.737	wh amorp pow					i H_2O, EtOH, chl; s dil HCl, alk
9631	Sucrose		$C_{12}H_{22}O_{11}$	57-50-1	342.296	mcl	185.5		1.5805^{17}	1.5376	s H_2O, py; sl EtOH; i eth
9632	Sucrose monohexadecanoate	Sucrose palmitate	$C_{28}H_{52}O_{12}$	26446-38-8	580.706	cry	61				s H_2O
9633	Sucrose octaacetate		$C_{28}H_{38}O_{19}$	126-14-7	678.591	nd (al)	86.5	250^{1}	1.27^{16}	1.4660	sl H_2O; s EtOH, eth, ace, bz, chl
9634	Sufentanil		$C_{22}H_{30}N_2O_2S$	56030-54-7	386.550	cry (peth)	96.6				
9635	Sulfabenzamide	*N*-[(4-Aminophenyl)sulfonyl] benzamide	$C_{13}H_{12}N_2O_3S$	127-71-9	276.310	hex pr (60% al)	181.5				
9636	Sulfachlorpyridazine		$C_{10}H_9ClN_4O_2S$	80-32-0	284.722		187				
9637	Sulfacytine		$C_{12}H_{14}N_4O_3S$	17784-12-2	294.329	cry (MeOH/ BuOH)	167				i H_2O; s alk
9638	Sulfadimethoxine		$C_{12}H_{14}N_4O_4S$	122-11-2	310.329		203.5				
9639	Sulfaguanidine		$C_7H_{10}N_4O_2S$	57-67-0	214.245	nd (w)	191.5				
9640	Sulfallate	Carbamodithioic acid, diethyl-, 2-chloro-2-propenyl ester	$C_8H_{14}ClNS_2$	95-06-7	223.787			129^{1}	1.088		
9641	Sulfamerazine		$C_{11}H_{12}N_4O_2S$	127-79-7	264.304	cry	236				sl H_2O, EtOH, ace, DMSO; i eth, chl
9642	Sulfamethazine		$C_{12}H_{14}N_4O_2S$	57-68-1	278.330	pa ye (w+1/ 2) cry (diox-w)	198.5				s H_2O, acid, alk; sl DMSO
9643	Sulfamethiazole		$C_9H_{10}N_4O_2S_2$	144-82-1	270.331	cry (w)	210				sl hot H_2O
9644	Sulfamethoxazole		$C_{10}H_{11}N_3O_3S$	723-46-6	253.277	ye-wh pow	171				i eth
9645	Sulfamethoxypyridazine		$C_{11}H_{12}N_4O_3S$	80-35-3	280.303		182.5				
9646	Sulfamethylthiazole		$C_{10}H_{11}N_3O_2S_2$	515-59-3	269.343		237				vs EtOH
9647	*N*^{4}-Sulfanilylsulfanilamide	4-Amino-*N*-[4-(aminosulfonyl) phenyl]benzenesulfonamide	$C_{12}H_{13}N_3O_4S_2$	547-52-4	327.379		137				sl H_2O; s EtOH, eth, ace; i chl, peth
9648	Sulfanilylurea		$C_7H_9N_3O_3S$	547-44-4	215.229	cry (w)	147 dec				
9649	Sulfaphenazole		$C_{15}H_{14}N_4O_2S$	526-08-9	314.363	cry (EtOH)	181				sl EtOH, MeOH, gl HOAc
9650	Sulfasalazine		$C_{18}H_{14}N_4O_5S$	599-79-1	398.393		220 dec				
9651	Sulfathiazole	4-Amino-*N*-2-thiazolylbenzenesulfonamide	$C_9H_9N_3O_2S_2$	72-14-0	255.316	br pl, rods or pow (45% al)	175(form a); 202(form b)				sl H_2O, EtOH, DMSO
9652	Sulfathiourea		$C_7H_9N_3O_2S_2$	515-49-1	231.295		182				i H_2O; sl EtOH
9653	Sulfinpyrazone		$C_{23}H_{20}N_2O_3S$	57-96-5	404.481		137				
9654	*N*-Sulfinylaniline		C_6H_5NOS	1122-83-4	139.175			200	1.236^{25}	1.6270^{20}	
9655	Sulfisoxazole		$C_{11}H_{13}N_3O_3S$	127-69-5	267.304		191				
9656	Sulfoacetic acid		$C_2H_4O_5S$	123-43-3	140.115	hyg tab (w+1)	85	dec 245			vs H_2O, ace, EtOH



Strychnidin-10-one mononitrate


HNO_3



Strychnidin-10-one sulfate (2:1)


H_2SO_4



Strychnine



Styrene



Succimer



Succinamide



Succinic acid



Succinic anhydride


Succinimide



Succinonitrile



Succinylcholine chloride



Succinylsulphathiazole



$R = SO_3[Al_2(OH)_5]$


Sucralfate



Sucrose



Sucrose octaacetate



Sufentanil



Sulfabenzamide



Sulfachlorpyridazine



Sulfacytine



Sulfadimethoxine



Sulfaguanidine



Sulfallate



Sulfamerazine



Sulfamethazine



Sulfamethiazole



Sulfamethoxazole



Sulfamethoxypyridazine



Sulfamethylthiazole



*N*⁴-Sulfanilylsulfanilamide



Sulfanilylurea



Sulfaphenazole



Sulfasalazine



Sulfathiazole


Sulfathiourea



Sulfinpyrazone



N-Sulfinylaniline



Sulfisoxazole



Sulfoacetic acid


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9657	2-Sulfobenzoic acid		$C_7H_6O_5S$	632-25-7	202.185	nd (w+3)	141				vs H_2O, EtOH
9658	Sulfolane	Tetrahydrothiophene, 1-1-dioxide	$C_4H_8O_2S$	126-33-0	120.171		27.6	287.3	1.2723^{18}	1.4833^{18}	s chl
9659	Sulfometuron methyl		$C_{15}H_{16}N_4O_5S$	74222-97-2	364.377	wh solid	202				
9660	Sulfonmethane	2,2-Bis(ethylsulfonyl)propane	$C_7H_{16}O_4S_2$	115-24-2	228.330	mcl (w), pr (al)	125.8	dec 300			vs bz, EtOH, chl
9661	Sulfonyldiacetic acid		$C_4H_6O_6S$	123-45-5	182.152		187				vs H_2O, EtOH; s eth, sulf
9662	4-Sulfophthalic acid	4-Sulfo-1,2-benzenedicarboxylic acid	$C_8H_6O_7S$	89-08-7	246.195	cry	139				
9663	Sulfotep		$C_8H_{20}O_5P_2S_2$	3689-24-5	322.320			137^{2}	1.196^{25}	1.4753^{25}	i H_2O; s EtOH
9664	Sulfuryl chloride isocyanate		$CClNO_3S$	1189-71-5	141.534	liq	-44	107	1.626^{25}	1.4467^{20}	
9665	Sulphan Blue		$C_{27}H_{31}N_2NaO_6S_2$	129-17-9	566.664	viol pow					s EtOH
9666	Sulprofos		$C_{12}H_{19}O_2PS_3$	35400-43-2	322.447			156$^{0.1}$	1.20^{20}	1.5859	sl H_2O
9667	Sunset Yellow FCF	C.I. Food Yellow 3	$C_{16}H_{10}N_2Na_2O_7S_2$	2783-94-0	452.369	cry	>300				s H_2O; sl EtOH
9668	Suprasterol II		$C_{28}H_{44}O$	562-71-0	396.648	pr	110	190$^{0.005}$			s MeOH
9669	Sutan	Carbamothioic acid, bis(2-methylpropyl)-, *S*-ethyl ester	$C_{11}H_{23}NOS$	2008-41-5	217.372			138^{21}	0.9402^{25}		
9670	Symclosene	1,3,5-Trichloro-1,3,5-triazine-2,4,6(1*H*,3*H*,5*H*)-trione	$C_3Cl_3N_3O_3$	87-90-1	232.409		246.7 dec				
9671	Syringin		$C_{17}H_{24}O_9$	118-34-3	372.368	cry (w), nd (al)	192				vs EtOH
9672	Tabun	Dimethylphosphoroamidocyanidic acid, ethyl ester	$C_5H_{11}N_2O_2P$	77-81-6	162.127	liq	-50	240	1.077	1.4250^{20}	msc H_2O
9673	Tachysterol	9,10-Secoergosta-5(10),6,8,22-tetraen-3-ol, (3β,6*E*,22*E*)-	$C_{28}H_{44}O$	115-61-7	396.648						i H_2O, MeOH; s EtOH, eth, ace, bz
9674	*D*-Tagatose		$C_6H_{12}O_6$	87-81-0	180.155	cry (dil al)	134.5				vs H_2O
9675	Talbutal		$C_{11}H_{16}N_2O_3$	115-44-6	224.256	cry	109				i H_2O, peth; s EtOH, ace, eth, chl
9676	Tamoxifen		$C_{26}H_{29}NO$	10540-29-1	371.514	cry (peth)	97				
9677	Tannic acid	Tannin	$C_{76}H_{52}O_{46}$	1401-55-4	1701.198	ye-br amorp pow	≈210 dec				vs EtOH, ace; i bz, chl, eth, ctc
9678	*DL*-Tartaric acid	2,3-Dihydroxybutanedioic acid, (*R**, *R**)-(±)-	$C_4H_6O_6$	133-37-9	150.087	mcl pr (w, al +1w)	206		1.788^{25}		s H_2O, EtOH; sl eth; i bz
9679	*meso*-Tartaric acid		$C_4H_6O_6$	147-73-9	150.087	tcl pl (w)	147		1.666^{20}		vs H_2O, EtOH
9680	*D*-Tartaric acid	2,3-Dihydroxybutanedioic acid, [*S*-(*R**,*R**)]-	$C_4H_6O_6$	147-71-7	150.087	mcl, orth pr (w+1)	172.5		1.7598^{20}	1.4955^{20}	sl DMSO
9681	*L*-Tartaric acid	2,3-Dihydroxybutanedioic acid, [*R*-(*R**,*R**)]-	$C_4H_6O_6$	87-69-4	150.087		169				
9682	Taurocholic acid	Cholaic acid	$C_{26}H_{45}NO_7S$	81-24-3	515.703	pr (al-eth)	125 dec				vs H_2O, EtOH; sl eth, AcOEt
9683	Taxine A		$C_{35}H_{47}NO_{10}$	1361-49-5	641.749	cry (ace)	205				i H_2O; s EtOH, eth, chl
9684	Taxol	Paclitaxel	$C_{47}H_{51}NO_{14}$	33069-62-4	853.907	nd (MeOH aq)	214 dec				
9685	Tebuconazole		$C_{16}H_{23}ClN_3O$	107534-96-3	308.826		102.4				
9686	Tebuthiuron		$C_9H_{16}N_4OS$	34014-18-1	228.314		163 dec				
9687	Teniposide		$C_{32}H_{32}O_{13}S$	29767-20-2	656.653	cry (EtOH)	244				
9688	Tephrosin		$C_{23}H_{22}O_7$	76-80-2	410.417	pr (chl-MeOH)	198				vs ace, eth, chl
9689	Terbacil	5-Chloro-3-*tert*-butyl-6-methyl-2,4(1*H*,3*H*)-pyrimidinedione	$C_9H_{13}ClN_2O_2$	5902-51-2	216.664		176	sub 175	1.34^{25}		
9690	Terbufos		$C_9H_{21}O_2PS_3$	13071-79-9	288.431		-29.2	69$^{0.01}$	1.105^{24}		
9691	Terbuthylazine	6-Chloro-*N*-*tert*-butyl-*N*′-ethyl-1,3,5-triazine-2,4-diamine	$C_9H_{16}ClN_5$	5915-41-3	229.710		178		1.188^{20}		
9692	Terbutryn		$C_{10}H_{19}N_5S$	886-50-0	241.357		104	157$^{0.06}$	1.115^{20}		
9693	Terebic acid	Tetrahydro-2,2-dimethyl-5-oxo-3-furancarboxylic acid	$C_7H_{10}O_4$	79-91-4	158.152	cry	175		0.815		sl H_2O; s EtOH
9694	Terephthalic acid	1,4-Benzenedicarboxylic acid	$C_8H_6O_4$	100-21-0	166.132	nd (sub)		sub 300			i H_2O, EtOH, eth, chl, HOAc; sl ctc
9695	Terfenadine	Seldane	$C_{32}H_{41}NO_2$	50679-08-8	471.674		147				i H_2O; s EtOH; sl hx
9696	*o*-Terphenyl		$C_{18}H_{14}$	84-15-1	230.304	mcl pr (MeOH)	56.20	332			i H_2O; s ace, bz, chl, MeOH
9697	*m*-Terphenyl		$C_{18}H_{14}$	92-06-8	230.304	ye nd (al)	87	363	1.199^{20}		i H_2O; s EtOH, eth, bz, HOAc; sl chl
9698	*p*-Terphenyl		$C_{18}H_{14}$	92-94-4	230.304		213.9	376			i H_2O; sl EtOH; s eth, bz, CS_2
9699	α-Terpinene	4-Isopropyl-1-methyl-1,3-cyclohexadiene	$C_{10}H_{16}$	99-86-5	136.234			174	0.8375^{19}	1.477^{19}	i H_2O; msc EtOH, eth



2-Sulfobenzoic acid



Sulfolane



Sulfometuron methyl



Sulfonmethane



Sulfonyldiacetic acid



4-Sulfophthalic acid



Sulfotep



Sulfuryl chloride isocyanate



Sulphan Blue



Sulprofos



Sunset Yellow FCF



Suprasterol II



Sutan



Symclosene



Syringin


Tabun



Tachysterol



D-Tagatose



Talbutal



Tamoxifen


R =



Tannic acid



DL-Tartaric acid



meso-Tartaric acid



D-Tartaric acid



L-Tartaric acid



Taurocholic acid



Taxine A



Taxol



Tebuconazole



Tebuthiuron



Teniposide



Tephrosin



Terbacil



Terbufos



Terbuthylazine



Terbutryn



Terebic acid



Terephthalic acid


Terfenadine



o-Terphenyl



m-Terphenyl



p-Terphenyl



α-Terpinene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9700	γ-Terpinene		$C_{10}H_{16}$	99-85-4	136.234			183	0.849^{20}	1.4765^{14}	
9701	α-Terpineol		$C_{10}H_{18}O$	2438-12-2	154.249	cry (peth)	40.5	220	0.9337^{20}	1.4831^{20}	sl H_2O; vs ace, bz, eth, EtOH
9702	α-Terpineol acetate		$C_{12}H_{20}O_2$	80-26-2	196.286			140^{40}, 105^{11}	0.9659^{21}	1.4689^{21}	i H_2O; s EtOH, eth, bz
9703	Terpinolene	*p*-Mentha-1,4(8)-diene	$C_{10}H_{16}$	586-62-9	136.234			186	0.8632^{15}	1.4883^{20}	i H_2O; msc EtOH, eth; s bz, ctc
9704	2,2':6',2"-Terpyridine		$C_{15}H_{11}N_3$	1148-79-4	233.268		88.0	370			
9705	Terrazole	1,2,4-Thiadiazole, 5-ethoxy-3-(trichloromethyl)-	$C_5H_5Cl_3N_2OS$	2593-15-9	247.530		19.9	95^{1}	1.503^{25}		
9706	2,2':5',2"-Terthiophene	α-Terthienyl	$C_{12}H_8S_3$	1081-34-1	248.387	ye-oran pl (MeOH)	93				i H_2O; sl EtOH; s bz, eth, ace, peth
9707	Testolactone		$C_{19}H_{24}O_3$	968-93-4	300.392	cry (ace)	218				
9708	3,6,9,12-Tetraazatetradecane-1,14-diamine	Pentaethylenehexamine	$C_{10}H_{28}N_6$	4067-16-7	232.369	liq			0.950	1.5096^{20}	
9709	Tetrabenazine		$C_{19}H_{27}NO_3$	58-46-8	317.422		128				s chl
9710	1,2,4,5-Tetrabromobenzene		$C_6H_2Br_4$	636-28-2	393.696	mcl pr (CS_2)	182	3.1^{20}	3.072^{20}		i H_2O; vs eth
9711	1,1,2,2-Tetrabromoethane	Acetylene tetrabromide	$C_2H_2Br_4$	79-27-6	345.653	ye visc liq	0	243.5; 151^{54}	2.9655^{20}	1.6353^{20}	i H_2O; msc EtOH, eth; s ace, bz; sl ctc
9712	Tetrabromoethene	Tetrabromoethylene	C_2Br_4	79-28-7	343.637	pl (dil al), nd (al)	56.5	226			i H_2O; s EtOH, eth, ace; vs chl
9713	2',4',5',7'-Tetrabromofluorescein, disodium salt	Eosine YS	$C_{20}H_6Br_4Na_2O_5$	17372-87-1	691.855	ye-red cry	295.5				vs EtOH
9714	4,5,6,7-Tetrabromo-1,3-isobenzofurandione		$C_8Br_4O_3$	632-79-1	463.700	nd (xyl, HOAc)	280				i H_2O, EtOH; sl bz; s $PhNO_2$
9715	Tetrabromomethane	Carbon tetrabromide	CBr_4	558-13-4	331.627	mcl tab (dil al)	92.3	189.5	2.9608^{100}	1.5942^{100}	i H_2O; s EtOH, eth, chl; vs CS_2
9716	2,3,4,5-Tetrabromo-6-methylphenol	3,4,5,6-Tetrabromo-*o*-cresol	$C_7H_4Br_4O$	576-55-6	423.722	ye nd (chl, HOAc)	208	dec			i H_2O; s EtOH, eth, bz, chl; sl lig, HOAc
9717	3',3",5',5"-Tetrabromophenolphthalein		$C_{20}H_{10}Br_4O_4$	76-62-0	633.907	nd (al, eth)	296				i H_2O; sl EtOH; vs eth; s alk, HOAc
9718	3',3",5',5"-Tetrabromophenolphthalein ethyl ester		$C_{22}H_{14}Br_4O_4$	1176-74-5	661.960	ye cry (bz)	210				
9719	3',3",5',5"-Tetrabromophenolphthalein ethyl ester, potassium salt		$C_{22}H_{13}Br_4KO_4$	62637-91-6	700.050		210				
9720	Tetrabutylammonium bromide	TMAB	$C_{16}H_{36}BrN$	1643-19-2	322.368		99				s chl
9721	Tetrabutylammonium chloride		$C_{16}H_{36}ClN$	1112-67-0	277.917	cry	74				
9722	Tetrabutylammonium fluoride		$C_{16}H_{36}FN$	429-41-4	261.462	cry (w)	37				
9723	Tetrabutylammonium hydroxide		$C_{16}H_{37}NO$	2052-49-5	259.471	stab in soln					s H_2O, MeOH
9724	Tetrabutylammonium iodide		$C_{16}H_{36}IN$	311-28-4	369.368	lf (w, bz)	148				sl H_2O, chl; vs EtOH
9725	Tetrabutylammonium sulfate		$C_{32}H_{72}N_2O_4S$	32503-27-8	580.990		170				sl chl
9726	Tetrabutylphosphonium bromide		$C_{16}H_{36}BrP$	3115-68-2	339.335	cry (ace/eth)	102				
9727	Tetrabutyl silicate	Silicic acid, tetrabutyl ester	$C_{16}H_{36}O_4Si$	4766-57-8	320.541			256; 120^{3}	0.8990^{20}	1.4128^{20}	
9728	Tetrabutylstannane		$C_{16}H_{36}Sn$	1461-25-2	347.167	liq	-97	145^{10}, 95$^{0.28}$	1.06^{20}		
9729	*N,N,N',N'*-Tetrabutylthioperoxydicarbonic diamide	Bis(dibutylthiocarbamoyl) disulfide	$C_{18}H_{36}N_2S_4$	1634-02-2	408.752		39.5		1.03^{20}		i H_2O; sl EtOH; s eth
9730	Tetrabutyl titanate	Titanium(IV) butoxide	$C_{16}H_{36}O_4Ti$	5593-70-4	340.322			292.4			
9731	Tetracaine hydrochloride		$C_{15}H_{25}ClN_2O_2$	136-47-0	300.825		147				
9732	1,2,3,4-Tetrachlorobenzene		$C_6H_2Cl_4$	634-66-2	215.892	nd (al)	47.5	254			i H_2O; sl EtOH; vs eth, CS_2
9733	1,2,3,5-Tetrachlorobenzene		$C_6H_2Cl_4$	634-90-2	215.892	nd (al)	54.5	246			i H_2O
9734	1,2,4,5-Tetrachlorobenzene		$C_6H_2Cl_4$	95-94-3	215.892	nd, mcl pr (eth, al or bz)	139.5	244.5	1.858^{22}		i H_2O; sl EtOH; s eth, bz, chl, CS_2
9735	3,4,5,6-Tetrachloro-1,2-benzenediol		$C_6H_2Cl_4O_2$	1198-55-6	247.891	cry (dil al, bz)	194				sl H_2O
9736	2,3,5,6-Tetrachloro-1,4-benzenediol		$C_6H_2Cl_4O_2$	87-87-6	247.891	nd (HOAc)		sub			i H_2O, bz, ctc; vs EtOH, eth; sl HOAc
9737	2,2',4',5-Tetrachlorobiphenyl		$C_{12}H_6Cl_4$	41464-40-8	291.988	cry (MeOH)	66.5				i H_2O
9738	2,3,4,5-Tetrachlorobiphenyl		$C_{12}H_6Cl_4$	33284-53-6	291.988	cry	92.2				i H_2O
9739	3,3',4',4'-Tetrachlorobiphenyl		$C_{12}H_6Cl_4$	32598-13-3	291.988	cry (EtOH)	180				
9740	2,2',6,6'-Tetrachlorobisphenol A		$C_{15}H_{12}Cl_4O_2$	79-95-8	366.067	cry (HOAc)	136				



γ-Terpinene



α-Terpineol



α-Terpineol acetate



Terpinolene



2,2':6',2"-Terpyridine



Terrazole



2,2':5',2"-Terthiophene



Testolactone



3,6,9,12-Tetraazatetradecane-1,14-diamine



Tetrabenazine


1,2,4,5-Tetrabromobenzene



1,1,2,2-Tetrabromoethane



Tetrabromoethene



2',4',5',7'-Tetrabromofluorescein, disodium salt



4,5,6,7-Tetrabromo-1,3-isobenzofurandione



Tetrabromomethane



2,3,4,5-Tetrabromo-6-methylphenol



3',3",5',5"-Tetrabromophenolphthalein



3',3",5',5"-Tetrabromophenolphthalein ethyl ester



3',3",5',5"-Tetrabromophenolphthalein ethyl ester, potassium salt



Tetrabutylammonium bromide



Tetrabutylammonium chloride



Tetrabutylammonium fluoride



Tetrabutylammonium hydroxide



Tetrabutylammonium iodide



Tetrabutylammonium sulfate



Tetrabutylphosphonium bromide



Tetrabutyl silicate



Tetrabutylstannane



N,N,N',N'-Tetrabutylthioperoxydicarbonic diamide



Tetrabutyl titanate



Tetracaine hydrochloride



1,2,3,4-Tetrachlorobenzene



1,2,3,5-Tetrachlorobenzene



1,2,4,5-Tetrachlorobenzene



3,4,5,6-Tetrachloro-1,2-benzenediol


2,3,5,6-Tetrachloro-1,4-benzenediol



2,2',4',5-Tetrachlorobiphenyl



2,3,4,5-Tetrachlorobiphenyl



3,3',4',4'-Tetrachlorobiphenyl



2,2',6,6'-Tetrachlorobisphenol A


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9741	2,3,5,6-Tetrachloro-2,5-cyclohexadiene-1,4-dione	Chloranil	$C_6Cl_4O_2$	118-75-2	245.875	ye mcl, pr (bz) ye lf (HOAc)	290	sub			i H_2O, liq; sl EtOH, chl; s eth
9742	3,4,5,6-Tetrachloro-3,5-cyclohexadiene-1,2-dione		$C_6Cl_4O_2$	2435-53-2	245.875		130.5				
9743	2,3,7,8-Tetrachlorodibenzo-*p*-dioxin	Dioxin	$C_{12}H_4Cl_4O_2$	1746-01-6	321.971	nd	295				
9744	2,3,7,8-Tetrachlorodibenzofuran		$C_{12}H_4Cl_4O$	51207-31-9	305.971	cry	227				
9745	1,1,1,2-Tetrachloro-2,2-difluoroethane		$C_2Cl_4F_2$	76-11-9	203.830		41.0	92.8	1.649^{25}		i H_2O; s EtOH, eth, chl
9746	1,1,2,2-Tetrachloro-1,2-difluoroethane		$C_2Cl_4F_2$	76-12-0	203.830		24.8	92.8	1.5951^{50}	1.4130^{25}	i H_2O; s EtOH, eth, chl
9747	1,2,3,4-Tetrachloro-5,5-dimethoxy-1,3-cyclopentadiene		$C_7H_6Cl_4O_2$	2207-27-4	263.934			109	1.501^{25}	1.5282^{20}	
9748	1,2,3,4-Tetrachloro-5,6-dimethylbenzene		$C_8H_6Cl_4$	877-08-7	243.946		228				i H_2O; s EtOH, eth, bz
9749	1,2,3,5-Tetrachloro-4,6-dimethylbenzene		$C_8H_6Cl_4$	877-09-8	243.946		223		1.703^{25}		i H_2O, EtOH, eth, bz, chl
9750	1,1,2,2-Tetrachloro-1,2-dimethyldisilane		$C_2H_6Cl_4Si_2$	4518-98-3	228.052			154			
9751	1,1,1,2-Tetrachloroethane		$C_2H_2Cl_4$	630-20-6	167.849	liq	-70.2	130.2	1.5406^{20}	1.4821^{20}	sl H_2O; s ace, bz, chl; msc EtOH, eth
9752	1,1,2,2-Tetrachloroethane	Acetylene tetrachloride	$C_2H_2Cl_4$	79-34-5	167.849	liq	-42.4	145.2	1.5953^{20}	1.4940^{20}	sl H_2O; s ace, bz, chl; msc EtOH, eth
9753	Tetrachloroethene	Perchloroethylene	C_2Cl_4	127-18-4	165.833	liq	-22.3	121.3	1.6230^{20}	1.5059^{20}	i H_2O; msc EtOH, eth, bz
9754	1,1,1,2-Tetrachloro-2-fluoroethane		C_2HCl_4F	354-11-0	185.839	liq	-95.3	117.1			
9755	1,1,2,2-Tetrachloro-1-fluoroethane		C_2HCl_4F	354-14-3	185.839	liq	-82.6	116.7	1.5497^{17}	1.4390^{20}	
9756	Tetrachloromethane	Carbon tetrachloride	CCl_4	56-23-5	153.823	liq	-22.62	76.8	1.5940^{20}	1.4601^{20}	i H_2O; s EtOH, ace; msc eth, bz, chl
9757	2,3,5,6-Tetrachloro-4-methoxyphenol	Drosophilin A	$C_7H_4Cl_4O_2$	484-67-3	261.918		116				
9758	2,3,4,6-Tetrachloro-5-methylphenol		$C_7H_4Cl_4O$	10460-33-0	245.918	nd (peth)	189.5				i H_2O; s EtOH, eth, ace, bz, KOH
9759	1,2,3,4-Tetrachloronaphthalene		$C_{10}H_4Cl_4$	20020-02-4	265.951		199				
9760	1,2,3,4-Tetrachloro-5-nitrobenzene		$C_6HCl_4NO_2$	879-39-0	260.890		66				
9761	1,2,4,5-Tetrachloro-3-nitrobenzene		$C_6HCl_4NO_2$	117-18-0	260.890		99.5	304	1.744^{25}		i H_2O; s EtOH, bz, chl
9762	2,3,4,5-Tetrachlorophenol		$C_6H_2Cl_4O$	4901-51-3	231.891	nd (peth, sub)	116.5	sub			vs EtOH
9763	2,3,4,6-Tetrachlorophenol		$C_6H_2Cl_4O$	58-90-2	231.891	nd (lig)	70	150^{15}			i H_2O; s EtOH, bz, chl, HOAc; vs NaOH
9764	2,3,5,6-Tetrachlorophenol		$C_6H_2Cl_4O$	935-95-5	231.891	lf (lig)	115				sl H_2O; vs bz; s lig
9765	Tetrachlorophthalic anhydride		$C_8Cl_4O_3$	117-08-8	285.896		254.5	sub	1.49^{275}		sl eth
9766	1,1,1,2-Tetrachloropropane		$C_3H_4Cl_4$	812-03-3	181.876	liq	-64	152.5	1.473^{20}	1.4867^{20}	i H_2O; vs EtOH; s eth, chl
9767	1,1,1,3-Tetrachloropropane		$C_3H_4Cl_4$	1070-78-6	181.876			157	1.4509^{20}	1.4825^{20}	i H_2O; vs EtOH, eth, bz, chl
9768	1,1,2,3-Tetrachloropropane		$C_3H_4Cl_4$	18495-30-2	181.876			179.5	1.513^{17}	1.5037^{17}	i H_2O; s EtOH, chl; vs eth
9769	1,2,2,3-Tetrachloropropane		$C_3H_4Cl_4$	13116-53-5	181.876			165	1.500^{18}	1.4940^{18}	i H_2O; vs EtOH, eth; s chl
9770	1,1,2,3-Tetrachloropropene		$C_3H_2Cl_4$	10436-39-2	179.860	liq		167.2; 59^{17}	1.55^{20}		
9771	2,3,5,6-Tetrachloropyridine		C_5HCl_4N	2402-79-1	216.881	cry (aq al)	90.5	250.5			vs eth, EtOH, peth
9772	Tetrachloropyrimidine		$C_4Cl_4N_2$	1780-40-1	217.868		69.0				
9773	3,3',4',5-Tetrachlorosalicylanilide	3,5-Dichloro-*N*-(3,4-dichlorophenyl)-2-hydroxybenzamide	$C_{13}H_7Cl_4NO_2$	1154-59-2	351.013		161				
9774	2,3,5,6-Tetrachloroterphthaloyl dichloride		$C_8Cl_6O_2$	719-32-4	340.803	cry (ctc)	146.5				
9775	Tetrachlorothiophene		C_4Cl_4S	6012-97-1	221.920	nd (dil al)	30.5	233.4	1.7036^{30}	1.5915^{30}	i H_2O; vs EtOH; msc eth
9776	Tetrachlorovinphos		$C_{10}H_9Cl_4O_4P$	961-11-5	365.961		97				
9777	Tetracontane		$C_{40}H_{82}$	4181-95-7	563.079		81.5	522; 400^{50}	0.8171^{25}	1.4572^{25}	
9778	Tetracosamethylundecasiloxane	Tetracosamethylhendecasiloxane	$C_{24}H_{72}O_{10}Si_{11}$	107-53-9	829.764			322.8; 202^{47}	0.9247^{25}	1.3994^{20}	vs bz
9779	Tetracosane		$C_{24}H_{50}$	646-31-1	338.654	cry (eth)	50.4	391.3	0.7991^{20}	1.4283^{70}	i H_2O; sl EtOH; vs eth



2,3,5,6-Tetrachloro-2,5-cyclohexadiene-1,4-dione



3,4,5,6-Tetrachloro-3,5-cyclohexadiene-1,2-dione



2,3,7,8-Tetrachlorodibenzo-*p*-dioxin



2,3,7,8-Tetrachlorodibenzofuran


1,1,1,2-Tetrachloro-2,2-difluoroethane



1,1,2,2-Tetrachloro-1,2-difluoroethane


1,2,3,4-Tetrachloro-5,5-dimethoxy-1,3-cyclopentadiene


1,2,3,4-Tetrachloro-5,6-dimethylbenzene



1,2,3,5-Tetrachloro-4,6-dimethylbenzene



1,1,2,2-Tetrachloro-1,2-dimethyldisilane


1,1,1,2-Tetrachloroethane



1,1,2,2-Tetrachloroethane



Tetrachloroethene



1,1,1,2-Tetrachloro-2-fluoroethane



1,1,2,2-Tetrachloro-1-fluoroethane



Tetrachloromethane



2,3,5,6-Tetrachloro-4-methoxyphenol



2,3,4,6-Tetrachloro-5-methylphenol



1,2,3,4-Tetrachloronaphthalene



1,2,3,4-Tetrachloro-5-nitrobenzene


1,2,4,5-Tetrachloro-3-nitrobenzene



2,3,4,5-Tetrachlorophenol



2,3,4,6-Tetrachlorophenol



2,3,5,6-Tetrachlorophenol



Tetrachlorophthalic anhydride



1,1,1,2-Tetrachloropropane



1,1,1,3-Tetrachloropropane



1,1,2,3-Tetrachloropropane



1,2,2,3-Tetrachloropropane



1,1,2,3-Tetrachloropropene



2,3,5,6-Tetrachloropyridine



Tetrachloropyrimidine



3,3',4',5-Tetrachlorosalicylanilide



2,3,5,6-Tetrachloroterphthaloyl dichloride


Tetrachlorothiophene



Tetrachlorovinphos



Tetracontane



Tetracosamethylundecasiloxane



Tetracosane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9780	Tetracosanoic acid	Lignoceric acid	$C_{24}H_{48}O_2$	557-59-5	368.637		87.5	272^{10}	0.8207^{100}	1.4287^{100}	vs bz, eth
9781	1-Tetracosanol		$C_{24}H_{50}O$	506-51-4	354.653		77	210$^{0.4}$			
9782	*cis*-15-Tetracosenoic acid	Nervonic acid	$C_{24}H_{46}O_2$	506-37-6	366.621		43				
9783	Tetracyanoethene	Tetracyanoethylene	C_6N_4	670-54-2	128.091		199	223	1.348^{25}	1.560^{25}	sl eth, bz, ctc, chl; s ace
9784	Tetracycline		$C_{22}H_{24}N_2O_8$	60-54-8	444.434	cry (+3w)	172 dec				
9785	Tetracycline hydrochloride		$C_{22}H_{25}ClN_2O_8$	64-75-5	480.895		214				
9786	Tetradecahydrophenanthrene		$C_{14}H_{24}$	5743-97-5	192.341	liq	-3	270; 87^{2}	0.944^{20}	1.5011^{20}	i H_2O; s eth, ace, bz
9787	Tetradecamethylhexasiloxane		$C_{14}H_{42}O_5Si_6$	107-52-8	458.993	liq	-59	245.5	0.8910^{20}	1.3948^{20}	vs bz
9788	Tetradecanal		$C_{14}H_{28}O$	124-25-4	212.371	lf	30				i H_2O; s EtOH, eth, ace
9789	Tetradecanamide		$C_{14}H_{29}NO$	638-58-4	227.386	lf (ace)	104	217^{12}			vs EtOH
9790	Tetradecane		$C_{14}H_{30}$	629-59-4	198.388		5.82	253.58	0.7596^{20}	1.4290^{20}	i H_2O; vs EtOH, eth; s ctc
9791	Tetradecanedioic acid		$C_{14}H_{26}O_4$	821-38-5	258.354		125.5				
9792	1,14-Tetradecanediol		$C_{14}H_{30}O_2$	19812-64-7	230.387	nd (bz)	85.8	200^{9}			vs eth, EtOH
9793	Tetradecanenitrile	Myristonitrile	$C_{14}H_{27}N$	629-63-0	209.371		19	226^{100}, 119^{1}	0.8281^{19}	1.4392^{23}	i H_2O; msc EtOH, eth, ace, bz; sl ctc
9794	1-Tetradecanethiol		$C_{14}H_{30}S$	2079-95-0	230.453		7	310; 178^{22}	0.8641^{20}	1.4597^{20}	i H_2O; s EtOH, eth, ctc
9795	Tetradecanoic acid	Myristic acid	$C_{14}H_{28}O_2$	544-63-8	228.371	lf (eth)	54.2	250^{100}	0.8622^{54}	1.4723^{70}	i H_2O; s EtOH, ace, chl; sl eth; vs bz
9796	Tetradecanoic anhydride		$C_{28}H_{54}O_3$	626-29-9	438.727	lf (peth)	53.4		0.8502^{70}	1.4335^{70}	vs eth, EtOH
9797	1-Tetradecanol	Tetradecyl alcohol	$C_{14}H_{30}O$	112-72-1	214.387	lf	38.2	287	0.8236^{38}		i H_2O; vs EtOH, eth, ace, bz, chl
9798	2-Tetradecanone	Dodecyl methyl ketone	$C_{14}H_{28}O$	2345-27-9	212.371	cry (dil al)	33.5	205^{100}, 134^{13}			i H_2O; s EtOH, ace
9799	Tetradecanoyl chloride	Myristoyl chloride	$C_{14}H_{27}ClO$	112-64-1	246.816		-1	171^{16}	0.9078^{25}		s eth
9800	12-*O*-Tetradecanoylphorbol-13-acetate	Cocarcinogen A1	$C_{36}H_{56}O_8$	16561-29-8	616.825	oil					
9801	1-Tetradecene		$C_{14}H_{28}$	1120-36-1	196.372	liq	-12	233	0.7745^{25}	1.4351^{20}	i H_2O; vs EtOH, eth; s bz; sl ctc
9802	Tetradecyl acetate	1-Tetradecanol, acetate	$C_{16}H_{32}O_2$	638-59-5	256.424			173^{10}			
9803	Tetradecylamine	1-Tetradecanamine	$C_{14}H_{31}N$	2016-42-4	213.403		83.1	291.2	0.8079^{20}	1.4463^{20}	i H_2O; vs EtOH, eth, bz, chl; s ace
9804	Tetradecylbenzene		$C_{20}H_{34}$	1459-10-5	274.484		16	359	0.8549^{20}	1.4818^{20}	
9805	Tetradecylcyclohexane		$C_{20}H_{40}$	1795-18-2	280.532		24	360	0.8254^{20}	1.4579^{20}	
9806	Tetradifon	1,2,4-Trichloro-5-[(4-chlorophenyl)sulfonyl]benzene	$C_{12}H_6Cl_4O_2S$	116-29-0	356.052		146		1.151^{20}		
9807	Tetraethoxygermane	Ethanol, germanium(4+) salt	$C_8H_{20}GeO_4$	14165-55-0	252.88			139^{200}			
9808	Tetraethoxymethane	Tetraethyl orthocarbonate	$C_9H_{20}O_4$	78-09-1	192.253			159.5	0.9186^{20}	1.3905^{25}	msc EtOH, eth; s ctc
9809	Tetraethylammonium bromide		$C_8H_{20}BrN$	71-91-0	210.156	hyg (al)	286 dec		1.3970^{20}		vs H_2O, EtOH, chl, MeOH
9810	Tetraethylammonium chloride		$C_8H_{20}ClN$	56-34-8	165.705	hyg cry					vs H_2O, EtOH, ace, chl
9811	Tetraethylammonium iodide		$C_8H_{20}IN$	68-05-3	257.156	cry (w)	300 dec				s H_2O
9812	1,2,3,5-Tetraethylbenzene		$C_{14}H_{22}$	38842-05-6	190.325			249.0			
9813	*N,N,N′,N′*-Tetraethyl-1,2-benzenedicarboxamide	*N,N,N′,N′*-Tetraethylphthalamide	$C_{16}H_{24}N_2O_2$	83-81-8	276.374		36	204^{16}			
9814	Tetra(2-ethylbutyl) silicate	Silicic acid, tetrakis(2-ethylbutyl) ester	$C_{24}H_{52}O_4Si$	78-13-7	432.754	liq			0.8920^{20}	1.4307^{20}	i H_2O; sl EtOH, ctc; s eth, bz
9815	Tetraethylene glycol	3,6,9-Trioxaundecane-1,11-diol	$C_8H_{18}O_5$	112-60-7	194.226	liq	-6.2	328	1.1285^{15}	1.4577^{20}	vs H_2O; s EtOH, eth, ctc, diox
9816	Tetraethylene glycol diacrylate		$C_{14}H_{22}O_7$	17831-71-9	302.321				1.125^{25}		
9817	Tetraethylene glycol dimethacrylate		$C_{16}H_{26}O_7$	109-17-1	330.373			220^{1}		1.4610^{25}	
9818	Tetraethylene glycol dimethyl ether		$C_{10}H_{22}O_5$	143-24-8	222.279			275.3	1.0114^{20}		msc H_2O; s EtOH, eth, ctc
9819	Tetraethylene glycol monostearate		$C_{26}H_{52}O_6$	106-07-0	460.687		40	328	1.1285^{15}	1.4593^{20}	
9820	Tetraethylenepentamine		$C_8H_{23}N_5$	112-57-2	189.303			341.5		1.5042^{20}	s H_2O
9821	*N,N,N′,N′*-Tetraethyl-1,2-ethanediamine		$C_{10}H_{24}N_2$	150-77-6	172.311			192	0.808^{25}	1.4343^{20}	
9822	Tetraethylgermane		$C_8H_{20}Ge$	597-63-7	188.89			164.5	1.199		
9823	Tetraethyl lead		$C_8H_{20}Pb$	78-00-2	323.4			dec 200	1.653^{20}	1.5198^{20}	i H_2O; s bz; sl EtOH
9824	*N,N,N′,N′*-Tetraethylmethanediamine		$C_9H_{22}N_2$	102-53-4	158.284			165.8	0.8000^{20}	1.4420^{25}	



Tetracosanoic acid


1-Tetracosanol



cis-15-Tetracosenoic acid



Tetracyanoethene



Tetracycline



Tetracycline hydrochloride


HCl



Tetradecahydrophenanthrene



Tetradecamethylhexasiloxane



Tetradecanal



Tetradecanamide



Tetradecane



Tetradecanedioic acid



1,14-Tetradecanediol



Tetradecanenitrile



1-Tetradecanethiol



Tetradecanoic acid



Tetradecanoic anhydride



1-Tetradecanol



2-Tetradecanone



12-*O*-Tetradecanoylphorbol-13-acetate



Tetradecanoyl chloride



1-Tetradecene



Tetradecyl acetate



Tetradecylamine



Tetradecylbenzene



Tetradecylcyclohexane



Tetradifon



Tetraethoxygermane



Tetraethoxymethane



Tetraethylammonium bromide



Tetraethylammonium chloride



Tetraethylammonium iodide



1,2,3,5-Tetraethylbenzene



N,N,N',N'-Tetraethyl-1,2-benzenedicarboxamide



Tetra(2-ethylbutyl) silicate



Tetraethylene glycol



Tetraethylene glycol diacrylate


Tetraethylene glycol dimethacrylate


Tetraethylene glycol dimethyl ether



Tetraethylene glycol monostearate


Tetraethylenepentamine



N,N,N',N'-Tetraethyl-1,2-ethanediamine


Tetraethylgermane


Tetraethyl lead



N,N,N',N'-Tetraethylmethanediamine


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9825	Tetraethyl pyrophosphate		$C_8H_{20}O_7P_2$	107-49-3	290.188		170 dec	155^{3}	1.1847^{20}	1.4180^{20}	msc H_2O, EtOH, eth, ace, xyl, chl; sl ctc
9826	Tetraethylsilane		$C_8H_{20}Si$	631-36-7	144.331			154.7	0.7658^{20}	1.4268^{20}	i H_2O
9827	Tetraethylstannane	Tin tetraethyl	$C_8H_{20}Sn$	597-64-8	234.955	liq	-112	181; 64^{12}	1.187^{25}	1.4730^{20}	
9828	Tetraethylthiodicarbonic diamide	Sulfiram	$C_{10}H_{20}N_2S_3$	95-05-6	264.474			232^{3}	1.12^{20}		s chl
9829	Tetraethylurea		$C_9H_{20}N_2O$	1187-03-7	172.267			209	0.919^{20}	1.4474^{20}	i H_2O, alk, acid
9830	1,2,3,4-Tetrafluorobenzene		$C_6H_2F_4$	551-62-2	150.074			94.3		1.4054^{20}	
9831	1,2,3,5-Tetrafluorobenzene		$C_6H_2F_4$	2367-82-0	150.074	liq	-46.25	84.4	1.319^{25}	1.4035^{20}	
9832	1,2,4,5-Tetrafluorobenzene		$C_6H_2F_4$	327-54-8	150.074		3.88	90.2	1.4255^{20}	1.4075^{20}	
9833	3,3,4,4-Tetrafluorodihydro-2,5-furandione		$C_4F_4O_3$	699-30-9	172.035			54.5	1.6209^{20}	1.3240^{20}	
9834	1,1,2,2-Tetrafluoro-1,2-dinitroethane		$C_2F_4N_2O_4$	356-16-1	192.026	liq	-41.5	58.5	1.6024^{25}	1.3265^{25}	i H_2O; s ace
9835	1,1,1,2-Tetrafluoroethane		$C_2H_2F_4$	811-97-2	102.031	col gas	-103.3	-26.08	1.2072^{25}		i H_2O; s eth
9836	1,1,2,2-Tetrafluoroethane		$C_2H_2F_4$	359-35-3	102.031	col gas	-89	-19.9			
9837	Tetrafluoroethene	Tetrafluoroethylene	C_2F_4	116-14-3	100.015	col gas	-131.15	-75.9	1.519^{-76}		i H_2O
9838	1,2,2,2-Tetrafluoroethyl difluoromethyl ether	Refrigerant 236me	$C_3H_2F_6O$	57041-67-5	168.037	vol liq or gas		23.35	1.4540^{23}		
9839	Tetrafluoromethane	Carbon tetrafluoride	CF_4	75-73-0	88.005	col gas	-183.60	-128.0	3.034^{25}		i H_2O; s bz, chl
9840	2,2,3,3-Tetrafluoro-1-propanol		$C_3H_4F_4O$	76-37-9	132.057	liq	-15	109.5	1.4853^{20}	1.3197^{20}	s EtOH, ace, chl
9841	6,7,8,9-Tetrahydro-5*H*-benzocyclohepten-5-one		$C_{11}H_{12}O$	826-73-3	160.212			175^{40}, 124^{7}	1.080^{20}	1.5698^{20}	s EtOH
9842	2,3,6,7-Tetrahydro-1*H*,5*H*-benzo[ij]quinolizine	Julolidine	$C_{12}H_{15}N$	479-59-4	173.254		40	dec 280; 155^{17}	1.003^{20}	1.568^{25}	
9843	1,2,3,6-Tetrahydro-2,3'-bipyridine, (*S*)	Anatabine	$C_{10}H_{12}N_2$	581-49-7	160.215			145^{10}	1.091^{19}	1.5676^{20}	msc H_2O; s EtOH, eth, bz
9844	2,3,4,9-Tetrahydro-1*H*-carbazole		$C_{12}H_{13}N$	942-01-8	171.238	lf (dil al)	120	327.5			i H_2O; s EtOH; vs eth, bz, MeOH
9845	Tetrahydrocortisone		$C_{21}H_{32}O_5$	53-05-4	364.476	cry (EtOAc)	190				
9846	1,2,3,4-Tetrahydro-6,7-dimethoxy-1,2-dimethylisoquinoline, (±)	Carnegine	$C_{13}H_{19}NO_2$	490-53-9	221.296	pa br syr		170^{1}			vs H_2O, eth, EtOH
9847	Tetrahydro-2,5-dimethoxyfuran		$C_6H_{12}O_3$	696-59-3	132.157			145.7	1.02^{25}	1.4180^{20}	
9848	4,5,6,7-Tetrahydro-3,6-dimethylbenzofuran		$C_{10}H_{14}O$	494-90-6	150.217		86	80^{18}	0.972^{15}		
9849	1,2,3,4-Tetrahydro-1,5-dimethylnaphthalene		$C_{12}H_{16}$	21564-91-0	160.255			239	0.941^{20}	1.526^{20}	
9850	Tetrahydro-2,2-dimethyl-5-oxo-3-furanacetic acid	Terpenylic acid	$C_8H_{12}O_4$	26754-48-3	172.179	lf or pr (w+1)	90				vs H_2O
9851	*cis*-Tetrahydro-2,5-dimethylthiophene		$C_6H_{12}S$	5161-13-7	116.224	liq	-89	142.3	0.9222^{20}	1.4799^{20}	vs ace, bz, eth, EtOH
9852	1,2,3,4-Tetrahydro-9*H*-fluoren-9-one	Phentydrone	$C_{13}H_{12}O$	634-19-5	184.233	lt ye nd or pr (pentane)	81.5	$139^{0.05}$			
9853	5,6,7,8-Tetrahydrofolic acid		$C_{19}H_{23}N_7O_6$	135-16-0	445.429	pow					s H_2O
9854	Tetrahydrofuran	Tetramethylene oxide	C_4H_8O	109-99-9	72.106	liq	-108.44	65	0.8833^{25}	1.4050^{25}	s H_2O, chl; vs EtOH, eth, ace, bz
9855	Tetrahydro-2-furanmethanamine	Tetrahydrofurfurylamine	$C_5H_{11}NO$	4795-29-3	101.147			153	0.9752^{20}	1.4551^{20}	vs H_2O, eth, EtOH
9856	Tetrahydro-2-furanmethanol propanoate		$C_8H_{14}O_3$	637-65-0	158.195			205.5	1.044^{20}		vs eth, EtOH, chl
9857	Tetrahydro-3-furanol		$C_4H_8O_2$	453-20-3	88.106			181	1.09^{25}	1.4500^{20}	
9858	Tetrahydrofurfuryl acetate		$C_7H_{12}O_3$	637-64-9	144.168			193; 89^{18}	1.0624^{20}	1.4350^{25}	vs H_2O, eth, EtOH, chl
9859	Tetrahydrofurfuryl acrylate		$C_8H_{12}O_3$	2399-48-6	156.179		<-60	96^{6}	1.061^{20}		
9860	Tetrahydrofurfuryl alcohol	Tetrahydro-2-furancarbinol	$C_5H_{10}O_2$	97-99-4	102.132		<-80	178	1.0524^{20}	1.4520^{20}	vs ace, eth
9861	Tetrahydrofurfuryl methacrylate		$C_9H_{14}O_3$	2455-24-5	170.205			265; 81^{4}	1.040^{25}	1.4554^{25}	
9862	Tetrahydroimidazo[4,5-d] imidazole-2,5(1*H*,3*H*)-dione	Acetyleneurea	$C_4H_6N_4O_2$	496-46-8	142.117	nd or pr (w)	300 dec				sl H_2O; i EtOH, HOAc; s eth, HCl, alk
9863	*cis*-3a,4,7,7a-Tetrahydro-1,3-isobenzofurandione	4-Cyclohexene-1,2-dicarboxylic acid, anhydride	$C_8H_8O_3$	935-79-5	152.148	cry (peth)	103.5				s EtOH, ace, chl, bz; sl peth
9864	4,5,6,7-Tetrahydro-1,3-isobenzofurandione	1-Cyclohexene-1,2-dicarboxylic acid, anhydride	$C_8H_8O_3$	2426-02-0	152.148	pl (EtOH)	74		1.2^{105}		s EtOH, ace, chl; vs eth
9865	1,2,3,4-Tetrahydroisoquinoline		$C_9H_{11}N$	91-21-4	133.190		<-15	232.5	1.0642^{24}	1.5668^{20}	i H_2O; s EtOH, bz, acid, xyl
9866	3,4,5,6-Tetrahydro-7-methoxy-2*H*-azepine		$C_7H_{13}NO$	2525-16-8	127.184	liq		49^{16}, 66^{24}	0.887	1.4630^{20}	
9867	1,2,3,4-Tetrahydro-6-methoxyquinoline		$C_{10}H_{13}NO$	120-15-0	163.216	pr (peth, al) orth pym (w)	42.5	284; 128^{1}		1.5718^{20}	s chl
9868	1,2,3,4-Tetrahydro-1-methylnaphthalene		$C_{11}H_{14}$	1559-81-5	146.229			220.6	0.9583^{20}	1.5353^{20}	



Tetraethyl pyrophosphate



Tetraethylsilane



Tetraethylstannane



Tetraethylthiodicarbonic diamide



Tetraethylurea


1,2,3,4-Tetrafluorobenzene


1,2,3,5-Tetrafluorobenzene


1,2,4,5-Tetrafluorobenzene



3,3,4,4-Tetrafluorodihydro-2,5-furandione


1,1,2,2-Tetrafluoro-1,2-dinitroethane



1,1,1,2-Tetrafluoroethane



1,1,2,2-Tetrafluoroethane



Tetrafluoroethene



1,2,2,2-Tetrafluoroethyl difluoromethyl ether



Tetrafluoromethane



2,2,3,3-Tetrafluoro-1-propanol



6,7,8,9-Tetrahydro-5*H*-benzocyclohepten-5-one



2,3,6,7-Tetrahydro-1*H*,5*H*-benzo[ij]quinolizine



1,2,3,6-Tetrahydro-2,3'-bipyridine, (*S*)



2,3,4,9-Tetrahydro-1*H*-carbazole



Tetrahydrocortisone



1,2,3,4-Tetrahydro-6,7-dimethoxy-1,2-dimethylisoquinoline, (±)



Tetrahydro-2,5-dimethoxyfuran



4,5,6,7-Tetrahydro-3,6-dimethylbenzofuran


1,2,3,4-Tetrahydro-1,5-dimethylnaphthalene



Tetrahydro-2,2-dimethyl-5-oxo-3-furanacetic acid



cis-Tetrahydro-2,5-dimethylthiophene


1,2,3,4-Tetrahydro-9*H*-fluoren-9-one



5,6,7,8-Tetrahydrofolic acid



Tetrahydrofuran



Tetrahydro-2-furanmethanamine



Tetrahydro-2-furanmethanol propanoate



Tetrahydro-3-furanol



Tetrahydrofurfuryl acetate



Tetrahydrofurfuryl acrylate



Tetrahydrofurfuryl alcohol



Tetrahydrofurfuryl methacrylate



Tetrahydroimidazo[4,5-d]imidazole-2,5(1*H*,3*H*)-dione



cis-3a,4,7,7a-Tetrahydro-1,3-isobenzofurandione


4,5,6,7-Tetrahydro-1,3-isobenzofurandione



1,2,3,4-Tetrahydroisoquinoline



3,4,5,6-Tetrahydro-7-methoxy-2*H*-azepine



1,2,3,4-Tetrahydro-6-methoxyquinoline


1,2,3,4-Tetrahydro-1-methylnaphthalene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9869	1,2,3,4-Tetrahydro-5-methylnaphthalene		$C_{11}H_{14}$	2809-64-5	146.229	liq	-23	234	0.9720^{20}	1.5439^{20}	
9870	1,2,3,4-Tetrahydro-6-methylnaphthalene		$C_{11}H_{14}$	1680-51-9	146.229	liq	-40	229	0.9537^{20}	1.5357^{20}	
9871	1,2,3,6-Tetrahydro-1-methyl-4-phenylpyridine	MPTP	$C_{12}H_{15}N$	28289-54-5	173.254	cry	41	$87^{0.8}$			
9872	Tetrahydro-3-methyl-2*H*-thiopyran		$C_6H_{12}S$	5258-50-4	116.224	liq	-60	158	0.9473^{20}	1.4922^{20}	
9873	5,6,7,8-Tetrahydro-1-naphthalenamine		$C_{10}H_{13}N$	2217-41-6	147.217		38	279	1.0625^{16}	1.5900^{20}	sl H_2O; s EtOH, eth, acid
9874	1,2,3,4-Tetrahydronaphthalene	Tetralin	$C_{10}H_{12}$	119-64-2	132.202	liq	-35.7	207.6	0.9645^{25}	1.5413^{20}	i H_2O; vs EtOH, eth; s chl, $PhNH_2$
9875	1,2,3,4-Tetrahydro-1-naphthol	1,2,3,4-Tetrahydro-α-naphthol	$C_{10}H_{12}O$	529-33-9	148.201		34.5	$255; 103^{2}$	1.0996^{20}	1.5638^{20}	
9876	5,6,7,8-Tetrahydro-1-naphthol	5,6,7,8-Tetrahydro-α-naphthol	$C_{10}H_{12}O$	529-35-1	148.201		70	$266; 143^{11}$	1.0556^{75}		
9877	1,2,3,4-Tetrahydro-2-naphthol	Tetralol	$C_{10}H_{12}O$	530-91-6	148.201		15.5	140^{12}			
9878	5,6,7,8-Tetrahydro-2-naphthol	5,6,7,8-Tetrahydro-β-naphthol	$C_{10}H_{12}O$	1125-78-6	148.201		57	275.5	1.0552^{65}		
9879	Tetrahydro-6-pentyl-2*H*-pyran-2-one	5-Hydroxydecanoic acid lactone	$C_{10}H_{18}O_2$	705-86-2	170.249	liq	-27	121^{3}			
9880	1,2,3,4-Tetrahydrophenanthrene		$C_{14}H_{14}$	1013-08-7	182.261	lf (MeOH)	33.5	173^{11}	1.0601^{40}		i H_2O; s EtOH, eth, ace, bz, HOAc, chl, lig
9881	1,2,3,6-Tetrahydrophthalimide		$C_8H_9NO_2$	85-40-5	151.163	cry (EtOH)	137				
9882	Tetrahydro-6-propyl-2*H*-pyran-2-one	5-Hydroxyoctanoic acid lactone	$C_8H_{14}O_2$	698-76-0	142.196	liq	-13	126^{15}			
9883	2,3,4,5-Tetrahydro-6-propylpyridine	γ-Coniceine	$C_8H_{15}N$	1604-01-9	125.212			174	0.8753^{15}	1.4661^{16}	
9884	Tetrahydropyran	Oxane	$C_5H_{10}O$	142-68-7	86.132	liq	-49.1	88	0.8814^{20}	1.4200^{20}	s EtOH, eth, bz, ctc
9885	Tetrahydro-2*H*-pyran-2-methanol		$C_6H_{12}O_2$	100-72-1	116.158			185	1.027^{25}	1.458^{20}	
9886	Tetrahydro-2*H*-pyran-2-one		$C_5H_8O_2$	542-28-9	100.117	liq	-12.5	219	1.1082^{20}	1.4503^{20}	s H_2O; msc EtOH, eth; sl ctc
9887	Tetrahydro-4*H*-pyran-4-one		$C_5H_8O_2$	29943-42-8	100.117			166.5	1.084^{25}	1.4520^{20}	
9888	1,2,5,6-Tetrahydropyridine	Δ^3-Piperidine	C_5H_9N	694-05-3	83.132	liq	-48	108	0.911^{25}	1.4800^{20}	s chl
9889	1,2,5,6-Tetrahydro-3-pyridinecarboxylic acid	Guvacine	$C_6H_9NO_2$	498-96-4	127.141	pr (w), rods (+1w dil al)	295 dec				vs H_2O
9890	3,4,5,6-Tetrahydro-2(1*H*)-pyrimidinethione	Hexahydropyrimidine-2-thione	$C_4H_8N_2S$	2055-46-1	116.185		211		1.33^{20}		
9891	1,2,3,4-Tetrahydroquinoline		$C_9H_{11}N$	635-46-1	133.190	nd	20	251	1.0588^{20}	1.6062^{19}	s H_2O, chl; msc EtOH, eth
9892	5,6,7,8-Tetrahydroquinoline	2,3-Cyclohexenopyridine	$C_9H_{11}N$	10500-57-9	133.190			222	1.0304^{13}	1.5435^{20}	sl H_2O; s EtOH, eth, ace, bz
9893	1,2,3,4-Tetrahydroquinoxaline		$C_8H_{10}N_2$	3476-89-9	134.178	lf (w, eth, peth)	99	289			s H_2O, chl; vs EtOH, eth, bz; sl peth
9894	6,7,8,9-Tetrahydro-5*H*-tetrazolo[1,5-a]azepine	Pentylenetetrazole	$C_6H_{10}N_4$	54-95-5	138.170	cry (bz-lig)	59.5	194^{12}			vs H_2O, EtOH, ace; s eth, bz; sl chl
9895	Tetrahydrothiophene	Thiacyclopentane	C_4H_8S	110-01-0	88.172	liq	-96.2	121.1	0.9987^{20}	1.4871^{18}	i H_2O; msc EtOH, eth, ace, bz; s chl
9896	1,2,3,4-Tetrahydro-1,1,6-trimethylnaphthalene		$C_{13}H_{18}$	475-03-6	174.282			$240; 90^{4}$	0.9303^{20}	1.5257^{20}	s EtOH, eth, bz, chl
9897	1,2,5,8-Tetrahydroxy-9,10-anthracenedione	Quinalizarin	$C_{14}H_8O_6$	81-61-8	272.210	oran nd	>275				sl H_2O, ace, bz, EtOH, eth
9898	2,3,4,6-Tetrahydroxy-5*H*-benzocycloheptен-5-one	Purpurogallin	$C_{11}H_8O_5$	569-77-7	220.179	red nd (gl HOAc)	274 dec				
9899	2,2',4,4'-Tetrahydroxybenzophenone		$C_{13}H_{10}O_5$	131-55-5	246.215	ye nd (w+1)	197				vs H_2O, ace, eth, EtOH
9900	2,3,5,6-Tetrahydroxy-2,5-cyclohexadiene-1,4-dione	Tetroquinone	$C_6H_4O_6$	319-89-1	172.092	bl-blk cry					sl H_2O, eth, ctc; vs EtOH
9901	11,17,20,21-Tetrahydroxypregn-4-en-3-one, (11β,20*R*)	4-Pregnene-11β,17α,20β,21-tetrol-3-on	$C_{21}H_{32}O_5$	116-58-5	364.476	cry (aq ace)	125 dec				vs ace, EtOH
9902	*N,N,N',N'*-Tetra(2-hydroxypropyl) ethylenediamine	ENTPROL	$C_{14}H_{32}N_2O_4$	102-60-3	292.415				1.030^{25}	1.478^{25}	sl chl
9903	Tetraiodoethene	Tetraiodoethylene	C_2I_4	513-92-8	531.639	ye lf, pr (eth)	187	sub	2.983^{20}		vs bz, chl
9904	4,5,6,7-Tetraiodo-1,3-isobenzofurandione		$C_8I_4O_3$	632-80-4	651.702	ye pr, nd (HOAc) nd (sub)	327.5	sub			i H_2O, EtOH, bz; sl HOAc
9905	Tetraiodomethane	Carbon tetraiodide	CI_4	507-25-5	519.629	red lf (bz, chl)	171	$135^{1.5}$	4.23^{20}		vs py, chl
9906	2,3,4,5-Tetraiodo-1*H*-pyrrole	Iodopyrrole	C_4HI_4N	87-58-1	570.676	ye nd (al)	150 dec				vs ace, eth, chl
9907	Tetraisobutyl titanate	2-Methyl-1-propanol, titanium(4+) salt	$C_{16}H_{36}O_4Ti$	7425-80-1	340.322			256^{500}	0.960^{50}		dec H_2O



1,2,3,4-Tetrahydro-5-methylnaphthalene



1,2,3,4-Tetrahydro-6-methylnaphthalene



1,2,3,6-Tetrahydro-1-methyl-4-phenylpyridine



Tetrahydro-3-methyl-2*H*-thiopyran



5,6,7,8-Tetrahydro-1-naphthalenamine



1,2,3,4-Tetrahydronaphthalene



1,2,3,4-Tetrahydro-1-naphthol



5,6,7,8-Tetrahydro-1-naphthol



1,2,3,4-Tetrahydro-2-naphthol



5,6,7,8-Tetrahydro-2-naphthol


Tetrahydro-6-pentyl-2*H*-pyran-2-one



1,2,3,4-Tetrahydrophenanthrene


1,2,3,6-Tetrahydrophthalimide



Tetrahydro-6-propyl-2*H*-pyran-2-one


2,3,4,5-Tetrahydro-6-propylpyridine



Tetrahydropyran



Tetrahydro-2*H*-pyran-2-methanol



Tetrahydro-2*H*-pyran-2-one



Tetrahydro-4*H*-pyran-4-one



1,2,5,6-Tetrahydropyridine



1,2,5,6-Tetrahydro-3-pyridinecarboxylic acid


3,4,5,6-Tetrahydro-2(1*H*)-pyrimidinethione



1,2,3,4-Tetrahydroquinoline



5,6,7,8-Tetrahydroquinoline



1,2,3,4-Tetrahydroquinoxaline



6,7,8,9-Tetrahydro-5*H*-tetrazolo[1,5-a]azepine



Tetrahydrothiophene



1,2,3,4-Tetrahydro-1,1,6-trimethylnaphthalene



1,2,5,8-Tetrahydroxy-9,10-anthracenedione


2,3,4,6-Tetrahydroxy-5*H*-benzocyclohepten-5-one



2,2',4,4'-Tetrahydroxybenzophenone


2,3,5,6-Tetrahydroxy-2,5-cyclohexadiene-1,4-dione



11,17,20,21-Tetrahydroxypregn-4-en-3-one, (11β,20*R*)



N,N,N',N'-Tetra(2-hydroxypropyl)ethylenediamine


Tetraiodoethene



4,5,6,7-Tetraiodo-1,3-isobenzofurandione



Tetraiodomethane



2,3,4,5-Tetraiodo-1*H*-pyrrole



Tetraisobutyl titanate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9908	Tetraisopropyl titanate	2-Propanol, titanium(4+) salt	$C_{12}H_{28}O_4Ti$	546-68-9	284.215			227.5	0.9711^{20}		dec H_2O; s EtOH, eth, bz, chl
9909	*N,N,N′,N′*-Tetrakis(2-hydroxyethyl) -1,2-ethanediamine		$C_{10}H_{24}N_2O_4$	140-07-8	236.309						sl H_2O, EtOH
9910	Tetrakis(hydroxymethyl) phosphonium chloride		$C_4H_{12}ClO_4P$	124-64-1	190.562		152.5				s H_2O
9911	Tetrakis(methylthio)methane		$C_5H_{12}S_4$	6156-25-8	200.409						s chl
9912	1-Tetralone		$C_{10}H_{10}O$	529-34-0	146.185		8	115^{6}	1.0988^{16}	1.5672^{20}	
9913	Tetramethoxymethane		$C_5H_{12}O_4$	1850-14-2	136.147	liq	-2.5	114	1.023^{25}	1.3845^{20}	
9914	1,1,3,3-Tetramethoxypropane		$C_7H_{16}O_4$	102-52-3	164.200			183; 66^{12}	0.997^{25}	1.4081^{20}	
9915	Tetramethrin		$C_{19}H_{25}NO_4$	7696-12-0	331.407	wh cry	≈65-80		1.108^{20}	1.5175^{21}	
9916	*N,N,N′,N′*-Tetramethyl-3,6-acridinediamine, monohydrochloride	Acridine Orange	$C_{17}H_{20}ClN_3$	65-61-2	301.814	oran-ye soln					s H_2O, EtOH
9917	Tetramethylammonium bromide		$C_4H_{12}BrN$	64-20-0	154.049	hyg bipym	230 dec		1.56^{25}		vs H_2O; sl EtOH; i eth, bz, chl; s MeOH
9918	Tetramethylammonium chloride		$C_4H_{12}ClN$	75-57-0	109.598	hyg bipym (dil al)	420 dec		1.169^{20}		s H_2O; sl EtOH; i eth, bz, chl; vs MeOH
9919	Tetramethylammonium iodide		$C_4H_{12}IN$	75-58-1	201.049		>230 dec		1.829^{25}		sl H_2O, alk, EtOH, ace; i eth, chl
9920	*N,N*,2,6-Tetramethylaniline		$C_{10}H_{15}N$	769-06-2	149.233	liq	-36	196; 88^{20}	0.9147^{20}		
9921	1,2,3,4-Tetramethylbenzene		$C_{10}H_{14}$	488-23-3	134.218	liq	-6.2	205	0.9052^{20}	1.5203^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
9922	1,2,3,5-Tetramethylbenzene	Isodurene	$C_{10}H_{14}$	527-53-7	134.218	liq	-23.7	198	0.8903^{20}	1.5130^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
9923	1,2,4,5-Tetramethylbenzene	Durene	$C_{10}H_{14}$	95-93-2	134.218		79.3	196.8	0.8380^{81}	1.4790^{81}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
9924	*N,N,N′,N′*-Tetramethyl-1,2-benzenediamine		$C_{10}H_{16}N_2$	704-01-8	164.247		8.9	215.5	0.9560^{20}		
9925	*N,N,N′,N′*-Tetramethyl-1,4-benzenediamine	Tetramethyl-*p*-phenylenediamine	$C_{10}H_{16}N_2$	100-22-1	164.247	lf (dil al or lig)	51	260			sl H_2O; vs EtOH, eth, bz, chl
9926	2,3,5,6-Tetramethyl-1,4-benzenediol	Durohydroquinone	$C_{10}H_{14}O_2$	527-18-4	166.217	nd (al)	233				s EtOH; sl eth
9927	Tetramethyl 1,2,4,5-benzenetetracarboxylate		$C_{14}H_{14}O_8$	635-10-9	310.256	nd (al)	144	sub			vs EtOH
9928	3,3′,5,5′-Tetramethyl-[1,1′-biphenyl]-4,4′-diamine		$C_{16}H_{20}N_2$	54827-17-7	240.343		168.5				
9929	*N,N,N′,N′*-Tetramethyl-[1,1′-biphenyl]-4,4′-diamine		$C_{16}H_{20}N_2$	366-29-0	240.343		196.0				
9930	3,3′,5,5′-Tetramethyl-[1,1′-biphenyl]-4,4′-diol		$C_{16}H_{18}O_2$	2417-04-1	242.313	pa ye nd or pr (HOAc)	221.8	sub			sl EtOH, bz, gl HOAc, tol; i lig
9931	2,2,3,3-Tetramethylbutane		C_8H_{18}	594-82-1	114.229	lf (eth)	100.7	106.45	0.8242^{20}	1.4695^{20}	i H_2O; s eth, chl
9932	*N,N,N′,N′*-Tetramethyl-1,4-butanediamine		$C_8H_{20}N_2$	111-51-3	144.258			168	0.7942^{15}	1.4621^{25}	msc H_2O; s EtOH, eth
9933	4-(1,1,3,3-Tetramethylbutyl) phenol		$C_{14}H_{22}O$	140-66-9	206.324		85.8	279			
9934	2,2,4,4-Tetramethyl-1,3-cyclobutanedione		$C_8H_{12}O_2$	933-52-8	140.180						s chl
9935	2,3,5,6-Tetramethyl-2,5-cyclohexadiene-1,4-dione	Duroquinone	$C_{10}H_{12}O_2$	527-17-3	164.201	ye nd (al or lig)	111.5				i H_2O; s EtOH, eth, ace, bz, sulf, chl
9936	1,2,3,4-Tetramethylcyclohexane		$C_{10}H_{20}$	3726-45-2	140.266				0.8219^{20}	1.4531^{20}	
9937	1,1,3,3-Tetramethylcyclopentane		C_9H_{18}	50876-33-0	126.239	liq	-88.4	118	0.7469^{25}	1.4125^{20}	
9938	1,1,2,2-Tetramethylcyclopropane		C_7H_{14}	4127-47-3	98.186	liq	-81	76			
9939	2,4,6,8-Tetramethylcyclotetrasiloxane		$C_4H_{16}O_4Si_4$	2370-88-9	240.510	liq	-65	134.5	0.9912^{20}	1.3870^{20}	i H_2O
9940	2,4,7,9-Tetramethyl-5-decyne-4,7-diol		$C_{14}H_{26}O_2$	126-86-3	226.355		47	165^{40}			
9941	*N,N,N′,N′*-Tetramethyl-4,4′-diaminobenzophenone	Michler's ketone	$C_{17}H_{20}N_2O$	90-94-8	268.353	lf (al), nd (bz)	179	dec 360			i H_2O, eth; sl EtOH; vs bz; s chl
9942	Tetramethyldiarsine	Cacodyl	$C_4H_{12}As_2$	471-35-2	209.981	liq	-6	165	1.447^{15}		vs eth, EtOH
9943	1,1,3,3-Tetramethyl-1,3-diphenyldisiloxane		$C_{16}H_{22}OSi_2$	56-33-7	286.516	liq	-80	292; 156^{13}	0.9763^{20}	1.5176^{20}	s ctc
9944	1,1,3,3-Tetramethyldisiloxane		$C_4H_{14}OSi_2$	3277-26-7	134.324			71	0.756^{20}	1.3700^{20}	
9945	1,1,3,3-Tetramethyl-1,3-disiloxanediol		$C_4H_{14}O_3Si_2$	1118-15-6	166.323		66		1.095^{25}		


Tetraisopropyl titanate



N,N,N',N'-Tetrakis(2-hydroxyethyl)-1,2-ethanediamine



Tetrakis(hydroxymethyl)phosphonium chloride



Tetrakis(methylthio)methane



1-Tetralone



Tetramethoxymethane



1,1,3,3-Tetramethoxypropane



Tetramethrin



N,N,N',N'-Tetramethyl-3,6-acridinediamine, monohydrochloride



Tetramethylammonium bromide



Tetramethylammonium chloride



Tetramethylammonium iodide



N,N,2,6-Tetramethylaniline



1,2,3,4-Tetramethylbenzene



1,2,3,5-Tetramethylbenzene



1,2,4,5-Tetramethylbenzene



N,N,N',N'-Tetramethyl-1,2-benzenediamine



N,N,N',N'-Tetramethyl-1,4-benzenediamine


2,3,5,6-Tetramethyl-1,4-benzenediol



Tetramethyl 1,2,4,5-benzenetetracarboxylate



3,3',5,5'-Tetramethyl-[1,1'-biphenyl]-4,4'-diamine



N,N,N',N'-Tetramethyl-[1,1'-biphenyl]-4,4'-diamine



3,3',5,5'-Tetramethyl-[1,1'-biphenyl]-4,4'-diol



2,2,3,3-Tetramethylbutane



N,N,N',N'-Tetramethyl-1,4-butanediamine


4-(1,1,3,3-Tetramethylbutyl)phenol



2,2,4,4-Tetramethyl-1,3-cyclobutanedione



2,3,5,6-Tetramethyl-2,5-cyclohexadiene-1,4-dione



1,2,3,4-Tetramethylcyclohexane


1,1,3,3-Tetramethylcyclopentane



1,1,2,2-Tetramethylcyclopropane



2,4,6,8-Tetramethylcyclotetrasiloxane



2,4,7,9-Tetramethyl-5-decyne-4,7-diol


N,N,N',N'-Tetramethyl-4,4'-diaminobenzophenone



Tetramethyldiarsine


1,1,3,3-Tetramethyl-1,3-diphenyldisiloxane



1,1,3,3-Tetramethyldisiloxane



1,1,3,3-Tetramethyl-1,3-disiloxanediol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9946	*N,N,N′,N′*-Tetramethyl-1,2-ethanediamine	1,2-Dimethylaminoethane	$C_6H_{16}N_2$	110-18-9	116.204	liq	-55	121	0.77^{25}	1.4179^{20}	
9947	Tetramethylgermane	Germanium tetramethyl	$C_4H_{12}Ge$	865-52-1	132.78			32^{500}	1.006		
9948	1,1,3,3-Tetramethylguanidine		$C_5H_{13}N_3$	80-70-6	115.177						s ctc
9949	2,2,6,6-Tetramethyl-3,5-heptanedione	Dipivaloylmethane	$C_{11}H_{20}O_2$	1118-71-4	184.276			93^{35}, 72^{6}	0.883^{25}	1.4589^{20}	sl ctc
9950	3,7,11,15-Tetramethylhexadecanoic acid	Phytanic acid	$C_{20}H_{40}O_2$	14721-66-5	312.531		-65				
9951	3,7,11,15-Tetramethyl-1-hexadecen-3-ol	Isophytol	$C_{20}H_{40}O$	505-32-8	296.531	oil		$108^{0.01}$	0.8519^{20}	1.4571^{20}	vs bz, eth, EtOH
9952	2,2,3,3-Tetramethylhexane		$C_{10}H_{22}$	13475-81-5	142.282	liq	-54	160.3	0.7609^{25}	1.4282^{20}	
9953	2,2,5,5-Tetramethylhexane		$C_{10}H_{22}$	1071-81-4	142.282	liq	-12.6	137.4	0.7148^{25}	1.4055^{20}	
9954	3,3,4,4-Tetramethylhexane		$C_{10}H_{22}$	5171-84-6	142.282			170.0	0.7789^{25}	1.4368^{20}	
9955	*N,N,N′,N′*-Tetramethyl-1,6-hexanediamine		$C_{10}H_{24}N_2$	111-18-2	172.311			209.5	0.806^{25}	1.4359^{20}	
9956	Tetramethyl lead		$C_4H_{12}Pb$	75-74-1	267.3	liq	-30.2	110	1.995^{20}		
9957	*N,N,N′,N′*-Tetramethylmethanediamine		$C_5H_{14}N_2$	51-80-9	102.178			83	0.7491^{18}		s H_2O
9958	Tetramethyloxirane		$C_6H_{12}O$	5076-20-0	100.158			90.4	0.8156^{16}	1.3984^{16}	s H_2O
9959	2,6,10,14-Tetramethylpentadecane	Pristane	$C_{19}H_{40}$	1921-70-6	268.521			296	0.7791^{25}	1.4370^{25}	vs bz, eth, chl, peth
9960	2,2,3,3-Tetramethylpentane		C_9H_{20}	7154-79-2	128.255	liq	-9.75	140.2	0.7530^{25}	1.4236^{20}	
9961	2,2,3,4-Tetramethylpentane		C_9H_{20}	1186-53-4	128.255	liq	-121.0	133.0	0.7389^{20}	1.4147^{20}	
9962	2,2,4,4-Tetramethylpentane	Di-*tert*-butylmethane	C_9H_{20}	1070-87-7	128.255	liq	-66.54	122.29	0.7195^{20}	1.4069^{20}	i H_2O; vs EtOH, bz
9963	2,3,3,4-Tetramethylpentane		C_9H_{20}	16747-38-9	128.255	liq	-102.1	141.5	0.7547^{20}	1.4222^{20}	
9964	2,2,4,4-Tetramethyl-3-pentanol		$C_9H_{20}O$	14609-79-1	144.254		52	165.5			
9965	2,3,4,5-Tetramethylphenol	Prehnitenol	$C_{10}H_{14}O$	488-70-0	150.217	nd (lig, aq al)	85.3	266			sl H_2O, lig; vs EtOH, eth
9966	2,3,4,6-Tetramethylphenol		$C_{10}H_{14}O$	3238-38-8	150.217	cry (peth)	80.5	240			s EtOH
9967	2,3,5,6-Tetramethylphenol		$C_{10}H_{14}O$	527-35-5	150.217	nd (lig), pr (al)	118.5	247			s chl, peth, HOAc
9968	2,2,6,6-Tetramethyl-4-piperidinamine		$C_9H_{20}N_2$	36768-62-4	156.268		17	188.5	0.912^{25}	1.4706^{20}	
9969	2,2,6,6-Tetramethylpiperidine	Norpempidine	$C_9H_{19}N$	768-66-1	141.254		28	156	0.8367^{16}	1.4455^{20}	vs eth
9970	2,2,6,6-Tetramethyl-4-piperidinone		$C_9H_{17}NO$	826-36-8	155.237	orth pl (eth-w) nd (eth)	36	205			s H_2O, EtOH, eth; sl chl
9971	*N,N,N′,N′*-Tetramethyl-1,3-propanediamine		$C_7H_{18}N_2$	110-95-2	130.231			144	0.7837^{18}		msc H_2O, EtOH, eth
9972	Tetramethylpyrazine		$C_8H_{12}N_2$	1124-11-4	136.194	cry (w)	86	190			
9973	Tetramethylsilane	TMS	$C_4H_{12}Si$	75-76-3	88.224	vol liq or gas	-99.06	26.6	0.648^{19}	1.3587^{20}	i H_2O; vs EtOH, eth; i sulf
9974	Tetramethyl silicate	Methyl silicate	$C_4H_{12}O_4Si$	681-84-5	152.222	liq	-1.0	121	1.0232^{20}	1.3683^{20}	vs EtOH
9975	Tetramethylstannane		$C_4H_{12}Sn$	594-27-4	178.848	liq	-55.1	78	1.314^{25}	1.4386	i H_2O; s ctc, CS_2
9976	Tetramethylsuccinonitrile	Tetramethylbutanedinitrile	$C_8H_{12}N_2$	3333-52-6	136.194	mcl pl, lf, pr (dil al)	170.5		1.070^{25}		s EtOH
9977	2,4,6,8-Tetramethyl-2,4,6,8-tetraphenylcyclotetrasiloxane		$C_{28}H_{32}O_4Si_4$	77-63-4	544.894	cry (HOAc)	99	237^{115}	1.1183^{20}	1.5461^{20}	i H_2O; msc ace, hp
9978	Tetramethylthiodicarbonic diamide		$C_6H_{12}N_2S_3$	97-74-5	208.367		109.5		1.37^{25}		i H_2O; s EtOH, ace, bz, chl; sl eth
9979	Tetramethylthiourea		$C_5H_{12}N_2S$	2782-91-4	132.227		79.3	245			s H_2O, EtOH, chl; sl eth
9980	Tetramethylurea		$C_5H_{12}N_2O$	632-22-4	116.161	liq	-0.6	176.5	0.9687^{20}	1.4496^{23}	sl EtOH, eth, ctc
9981	Tetranitromethane		CN_4O_8	509-14-8	196.033		13.8	126.1	1.6380^{20}	1.4384^{20}	i H_2O; s EtOH, eth
9982	2,4,8,10-Tetraoxaspiro[5.5]undecane		$C_7H_{12}O_4$	126-54-5	160.168		48.3	147^{53}, 68^{1}			vs H_2O, ace, eth, EtOH
9983	2,5,8,11-Tetraoxatridecan-13-ol		$C_9H_{20}O_5$	23783-42-8	208.252			164^{11}	0.987^{25}	1.4453^{20}	
9984	Tetraphenoxysilane		$C_{24}H_{20}O_4Si$	1174-72-7	400.500		49	417; 236^{1}	1.1412^{60}		
9985	1,1,4,4-Tetraphenyl-1,3-butadiene		$C_{28}H_{22}$	1450-63-1	358.475		203.5				s EtOH, bz, chl, HOAc
9986	2,3,4,5-Tetraphenyl-2,4-cyclopentadien-1-one		$C_{29}H_{20}O$	479-33-4	384.468	blk-viol lf (HOAc, xyl)	222.3				s EtOH, bz, xyl, HOAc
9987	1,1,2,2-Tetraphenylethane		$C_{26}H_{22}$	632-50-8	334.453	cry (bz), orth nd (chl)	214.5	360			sl EtOH; s bz, HOAc
9988	1,1,2,2-Tetraphenyl-1,2-ethanediol	Benzopinacol	$C_{26}H_{22}O_2$	464-72-2	366.452	pr (bz), cry (ace)	182				i H_2O, peth; sl EtOH; s eth, ace, CS_2
9989	1,1,2,2-Tetraphenylethene		$C_{26}H_{20}$	632-51-9	332.437	mcl or orth (bz-eth or chl-al)	225	420	1.155^{0}		i H_2O; sl EtOH, chl, eth; vs bz
9990	Tetraphenylgermane	Germanium tetraphenyl	$C_{24}H_{20}Ge$	1048-05-1	381.06		229.0				



N,N,N′,N′-Tetramethyl-1,2-ethanediamine



Tetramethylgermane



1,1,3,3-Tetramethylguanidine



2,2,6,6-Tetramethyl-3,5-heptanedione



3,7,11,15-Tetramethylhexadecanoic acid


3,7,11,15-Tetramethyl-1-hexadecen-3-ol



2,2,3,3-Tetramethylhexane



2,2,5,5-Tetramethylhexane



3,3,4,4-Tetramethylhexane


N,N,N′,N′-Tetramethyl-1,6-hexanediamine



Tetramethyl lead



N,N,N′,N′-Tetramethylmethanediamine



Tetramethyloxirane



2,6,10,14-Tetramethylpentadecane



2,2,3,3-Tetramethylpentane



2,2,3,4-Tetramethylpentane



2,2,4,4-Tetramethylpentane



2,3,3,4-Tetramethylpentane



2,2,4,4-Tetramethyl-3-pentanol



2,3,4,5-Tetramethylphenol



2,3,4,6-Tetramethylphenol



2,3,5,6-Tetramethylphenol


2,2,6,6-Tetramethyl-4-piperidinamine


2,2,6,6-Tetramethylpiperidine


2,2,6,6-Tetramethyl-4-piperidinone



N,N,N′,N′-Tetramethyl-1,3-propanediamine



Tetramethylpyrazine



Tetramethylsilane



Tetramethyl silicate



Tetramethylstannane



Tetramethylsuccinonitrile



2,4,6,8-Tetramethyl-2,4,6,8-tetraphenylcyclotetrasiloxane



Tetramethylthiodicarbonic diamide



Tetramethylthiourea



Tetramethylurea



Tetranitromethane



2,4,8,10-Tetraoxaspiro[5.5]undecane



2,5,8,11-Tetraoxatridecan-13-ol



Tetraphenoxysilane



1,1,4,4-Tetraphenyl-1,3-butadiene


2,3,4,5-Tetraphenyl-2,4-cyclopentadien-1-one



1,1,2,2-Tetraphenylethane



1,1,2,2-Tetraphenyl-1,2-ethanediol



1,1,2,2-Tetraphenylethene



Tetraphenylgermane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
9991	Tetraphenylmethane		$C_{25}H_{20}$	630-76-2	320.427	orth nd (bz, sub)	282	431			i H_2O, EtOH, eth, lig, HOAc; s bz, tol
9992	5,6,11,12-Tetraphenylnaphthacene	Rubrene	$C_{42}H_{28}$	517-51-1	532.671	oran-red (bz-lig)	332.5				i H_2O; sl EtOH, eth, ace, py; s bz
9993	Tetraphenylplumbane		$C_{24}H_{20}Pb$	595-89-1	515.6		228.3	126^{13}	1.5298^{20}		s chl
9994	Tetraphenylsilane		$C_{24}H_{20}Si$	1048-08-4	336.502		236.5	228^{3}	1.078^{20}		s ctc, CS_2
9995	Tetraphenylstannane		$C_{24}H_{20}Sn$	595-90-4	427.126		228	420			sl chl
9996	Tetrapropoxysilane		$C_{12}H_{28}O_4Si$	682-01-9	264.434			226	0.9158^{20}	1.4012^{20}	s ctc, CS_2
9997	Tetrapropylammonium bromide	*N,N,N*-Tripropyl-1-propanaminium bromide	$C_{12}H_{28}BrN$	1941-30-6	266.261		252				vs H_2O, chl
9998	Tetrapropylammonium iodide		$C_{12}H_{28}IN$	631-40-3	313.261	orth bipym	280 dec		1.3138^{25}		vs H_2O, chl; s EtOH, HOAc; sl eth
9999	Tetrapropylstannane		$C_{12}H_{28}Sn$	2176-98-9	291.060	liq	-109.1	228	1.1065^{20}	1.4745^{20}	
10000	Tetrapropyl thiodiphosphate	Aspon	$C_{12}H_{28}O_5P_2S_2$	3244-90-4	378.425	amber liq		$104^{0.1}$	1.12^{25}	1.4710^{21}	sl H_2O, peth
10001	Tetrapropyl titanate	1-Propanol, titanium(4+) salt	$C_{12}H_{28}O_4Ti$	3087-37-4	284.215			206^{100}			
10002	Tetrasodium EDTA	Edetate sodium	$C_{10}H_{12}N_2Na_4O_8$	64-02-8	380.169	amorp pow	300 (dihydrate)				sl EtOH
10003	Tetratetracontane		$C_{44}H_{90}$	7098-22-8	619.186		85.6				
10004	Tetratriacontane		$C_{34}H_{70}$	14167-59-0	478.920	pl (eth)	72.5	285.4^{3}	0.7728^{90}	1.4296^{90}	
10005	Tetravinylsilane		$C_8H_{12}Si$	1112-55-6	136.267			130.2	0.7999^{20}	1.4625^{20}	
10006	2,4,6,8-Tetravinyl-2,4,6,8-tetramethylcyclotetrasiloxane		$C_{12}H_{24}O_4Si_4$	2554-06-5	344.659	liq	-43.5	$224; 111^{12}$	0.9875^{20}		s ctc, CS_2
10007	1,2,4,5-Tetrazine	*sym*-Tetrazine	$C_2H_2N_4$	290-96-0	82.064	dk red pr	99	sub			s H_2O, EtOH, eth, sulf
10008	1*H*-Tetrazol-5-amine		CH_3N_5	4418-61-5	85.069		204 dec				
10009	1*H*-Tetrazole		CH_2N_4	288-94-8	70.054	pl (al)	157.3	sub	1.4060^{20}		sl H_2O
10010	Tetrodotoxin		$C_{11}H_{17}N_3O_8$	4368-28-9	319.268	cry	225 dec				sl H_2O,eth, EtOH; s dil HOAc
10011	Thalidomide	2-(2,6-Dioxo-3-piperidinyl)-1*H*-isoindole-1,3(2*H*)-dione	$C_{13}H_{10}N_2O_4$	50-35-1	258.229	nd	270				vs py, diox
10012	Thallium(I) ethanolate	Thallous ethoxide	C_2H_5OTl	20398-06-5	249.443	cloudy liq	-3	dec 130	3.49		dec H_2O
10013	Thebaine		$C_{19}H_{21}NO_3$	115-37-7	311.375	pl (eth), pr (dil al)	193	sub 91	1.305^{20}		i H_2O; vs EtOH, chl; sl eth; s bz
10014	Thebainone		$C_{18}H_{21}NO_3$	467-98-1	299.365	nd or pr (al)	151.5				sl H_2O, EtOH, eth; s ace, bz, AcOEt
10015	Thenaldine	1-Methyl-*N*-phenyl-*N*-(2-thienylmethyl)-4-piperidinamine	$C_{17}H_{22}N_2S$	86-12-4	286.435		96	$159^{0.02}$			
10016	Thenyldiamine		$C_{14}H_{19}N_3S$	91-79-2	261.386			170^{1}		1.5915^{20}	
10017	Theobromine		$C_7H_8N_4O_2$	83-67-0	180.165	orth or mcl nd (w)	357	sub 290			sl H_2O, EtOH; i eth, bz, ctc, lig, chl
10018	Theophylline	3,7-Dihydro-1,3-dimethyl-1*H*-purine-2,6-dione	$C_7H_8N_4O_2$	58-55-9	180.165	nd or pl (w+1)	273				s H_2O; sl EtOH, eth, chl
10019	Thiabendazole	1*H*-Benzimidazole, 2-(4-thiazolyl)-	$C_{10}H_7N_3S$	148-79-8	201.248			sub 305			
10020	Thiacetazone		$C_{10}H_{12}N_4OS$	104-06-3	236.293		225 dec				i H_2O, os, CS_2
10021	Thiacyclohexane		$C_5H_{10}S$	1613-51-0	102.198		19	141.8	0.9861^{20}	1.5067^{20}	i H_2O; s EtOH, eth, ace, bz
10022	1,2,5-Thiadiazole	Piazthiole	$C_2H_2N_2S$	288-39-1	86.115	liq	-50.1	94	1.268^{25}	1.5150^{25}	
10023	1,3,4-Thiadiazole		$C_2H_2N_2S$	289-06-5	86.115	cry (sub)	42.5	204			
10024	1,3,4-Thiadiazolidine-2,5-dithione		$C_2H_2N_2S_3$	1072-71-5	150.245	ye cry (MeOH)	168				s H_2O
10025	Thiamine chloride		$C_{12}H_{17}ClN_4OS$	59-43-8	300.807	cry	164				s H_2O
10026	Thiamine hydrochloride		$C_{12}H_{18}Cl_2N_4OS$	67-03-8	337.268	mcl pl	248 dec				vs H_2O; sl EtOH; i eth, bz, chl
10027	Thiamine *O*-phosphate, chloride		$C_{12}H_{18}ClN_4O_4PS$	532-40-1	380.787		200				
10028	Thianthrene		$C_{12}H_8S_2$	92-85-3	216.322	mcl pr or pl (al)	159.3	365	1.4420^{20}		i H_2O; sl EtOH; s eth, bz, CS_2
10029	2-Thiazolamine	2-Aminothiazole	$C_3H_4N_2S$	96-50-4	100.142	ye pl (al)	93	140^{11}			sl H_2O, EtOH, eth, chl; vs dil HCl
10030	Thiazole		C_3H_3NS	288-47-1	85.128		-33.62	118	1.1998^{17}	1.5969^{20}	sl H_2O; s EtOH, eth, ace
10031	Thiazolidine		C_3H_7NS	504-78-9	89.160			164.5	1.131^{25}	1.551^{20}	msc H_2O; s EtOH, ctc; vs eth, ace
10032	4-Thiazolidinecarboxylic acid	Timonacic	$C_4H_7NO_2S$	444-27-9	133.170	cry (w)	196.5				vs H_2O
10033	2,4-Thiazolidinedione		$C_3H_3NO_2S$	2295-31-0	117.127	pl (w), pr (al)	128	179^{19}			vs eth



Tetraphenylmethane



5,6,11,12-Tetraphenylnaphthacene



Tetraphenylplumbane



Tetraphenylsilane



Tetraphenylstannane



Tetrapropoxysilane



Tetrapropylammonium bromide



Tetrapropylammonium iodide



Tetrapropylstannane


Tetrapropyl thiodiphosphate



Tetrapropyl titanate


Tetrasodium EDTA



Tetratetracontane


Tetratriacontane



Tetravinylsilane



2,4,6,8-Tetravinyl-2,4,6,8-tetramethylcyclotetrasiloxane



1,2,4,5-Tetrazine



1*H*-Tetrazol-5-amine



1*H*-Tetrazole



Tetrodotoxin



Thalidomide



Thallium(I) ethanolate



Thebaine



Thebainone



Thenaldine


Thenyldiamine


Theobromine


Theophylline



Thiabendazole



Thiacetazone



Thiacyclohexane



1,2,5-Thiadiazole



1,3,4-Thiadiazole



1,3,4-Thiadiazolidine-2,5-dithione


Thiamine chloride



Thiamine hydrochloride



Thiamine *O*-phosphate, chloride



Thianthrene


2-Thiazolamine


Thiazole



Thiazolidine


4-Thiazolidinecarboxylic acid


2,4-Thiazolidinedione

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10034	2-Thiazolidinethione		$C_3H_5NS_2$	96-53-7	119.209	nd (w, MeOH)	107.3				s H_2O, bz, chl; sl EtOH; i eth, CS_2
10035	Thidiazuron	*N*-Phenyl-*N'*-1,2,3-thiadiazol-5-yl-urea	$C_9H_8N_4OS$	51707-55-2	220.251		211 dec				
10036	1-(2-Thienyl)ethanone		C_6H_6OS	88-15-3	126.176		10.5	213.5	1.1679^{20}	1.5667^{20}	sl H_2O; msc EtOH, eth; s ctc
10037	Thiepane	Hexamethylene sulfide	$C_6H_{12}S$	4753-80-4	116.224	liq	0.5	173.5	0.991^{20}	1.5044^{18}	i H_2O; s eth, ace, chl
10038	Thietane	Trimethylene sulfide	C_3H_6S	287-27-4	74.145	liq	-73.24	95.0	1.0200^{20}	1.5102^{20}	i H_2O; vs EtOH, bz; s ace
10039	Thietane 1,1-dioxide	Trimethylene sulfone	$C_3H_6O_2S$	5687-92-3	106.144		75.5	91.2^{14}		1.5156^{20}	s H_2O, EtOH; sl eth, peth
10040	Thiethylperazine		$C_{22}H_{29}N_3S_2$	1420-55-9	399.615	cry	63	$227^{0.01}$			sl ace
10041	Thiirane	Ethylene sulfide	C_2H_4S	420-12-2	60.118		-109	dec 57	1.0130^{20}	1.4935^{20}	sl EtOH, eth; s ace, chl
10042	Thioacetaldehyde trimer	2,4,6-Trimethyl-1,3,5-trithiane	$C_6H_{12}S_3$	2765-04-0	180.354	α-mcl pl; β-nd (ace)	101	246.5			i H_2O; s EtOH, eth, ace; vs bz, chl
10043	Thioacetamide	Ethanethioamide	C_2H_5NS	62-55-5	75.133		115.5				vs H_2O, EtOH; sl eth, bz; s DMSO
10044	Thioacetic acid		C_2H_4OS	507-09-5	76.117	ye fuming liq	<-17	93; 26^{35}	1.064^{20}	1.4648^{20}	s H_2O, chl; vs EtOH, ace; msc eth
10045	Thiobencarb		$C_{12}H_{16}ClNOS$	28249-77-6	257.779		1.7	$127^{0.008}$	1.16^{20}		
10046	4,4'-Thiobis(6-*tert*-butyl-*m*-cresol)	Bis(5-*tert*-butyl-4-hydroxy-2-methylphenyl) sulfide	$C_{22}H_{30}O_2S$	96-69-5	358.537	cry	163				
10047	2,2'-Thiobisethanamine	Bis(2-aminoethyl) sulfide	$C_4H_{12}N_2S$	871-76-1	120.216	ye cry		232; 119^{17}			
10048	3,3'-Thiobispropanoic acid, didodecyl ester	Didodecyl thiobispropanoate	$C_{30}H_{58}O_4S$	123-28-4	514.845		39				
10049	Thioctic acid	1,2-Dithiolane-3-pentanoic acid	$C_8H_{14}O_2S_2$	62-46-4	206.326	ye nd	61	162			i H_2O
10050	Thiocyanic acid		CHNS	463-56-9	59.091		dec 0				vs H_2O; s os
10051	Thiodicarb		$C_{10}H_{18}N_4O_4S_3$	59669-26-0	354.470		173		1.4^{20}		
10052	Thiodiglycolic acid	Thiodiacetic acid	$C_4H_6O_4S$	123-93-3	150.154	cry (w)	129				sl H_2O; vs EtOH; s bz
10053	3,3'-Thiodipropionic acid		$C_6H_{10}O_4S$	111-17-1	178.206	cry wh pow	129				vs H_2O, EtOH
10054	Thiofanox		$C_9H_{18}N_2O_2S$	39196-18-4	218.316		57				
10055	Thioformaldehyde	Methanethial	CH_2S	865-36-1	46.092	unstab gas					
10056	Thioglycolic acid		$C_2H_4O_2S$	68-11-1	92.117		-16.5	120^{20}	1.3253^{20}	1.5080^{20}	msc H_2O, EtOH, eth; sl chl
10057	Thioimidodicarbonic diamide	2,4-Dithiobiuret	$C_2H_5N_3S_2$	541-53-7	135.211	mcl cry	181 dec				vs ace
10058	Thiolactic acid		$C_3H_6O_2S$	71563-86-5	106.144		12	106^{15}	1.1938^{20}	1.4810^{20}	s H_2O, EtOH, eth; sl chl
10059	Thiometon		$C_6H_{15}O_2PS_3$	640-15-3	246.351	oil		$110^{0.1}$, $77^{0.01}$	1.209^{20}		sl H_2O; s os
10060	Thiomorpholine	Thiamorpholine	C_4H_9NS	123-90-0	103.186			175; 110^{100}	1.0882^{20}	1.5386^{20}	vs H_2O, ace, eth, EtOH
10061	Thionazin	Phosphorothioic acid, *O,O*-diethyl *O*-pyrazinyl ester	$C_8H_{13}N_2O_3PS$	297-97-2	248.239	liq	-0.9	80			
10062	Thiophanate-methyl		$C_{12}H_{14}N_4O_4S_2$	23564-05-8	342.394		172 dec				
10063	Thiophene	Thiofuran	C_4H_4S	110-02-1	84.140	liq	-38.21	84.0	1.0649^{20}	1.5289^{20}	msc EtOH, eth, ace, bz, ctc, diox, py; sl chl
10064	2-Thiopheneacetic acid		$C_6H_6O_2S$	1918-77-0	142.176	cry (w)	76				vs H_2O, eth, EtOH
10065	2-Thiopheneacetonitrile		C_6H_5NS	20893-30-5	123.176			120^{23}	1.155^{25}	1.5425^{20}	
10066	2-Thiophenecarbonitrile	2-Cyanothiophene	C_5H_3NS	1003-31-2	109.150			192	1.172^{25}	1.5629^{20}	s chl
10067	3-Thiophenecarbonitrile	3-Cyanothiophene	C_5H_3NS	1641-09-4	109.150	oil		204; 85^{15}			
10068	2-Thiophenecarbonyl chloride		C_5H_3ClOS	5271-67-0	146.595			280			
10069	2-Thiophenecarboxaldehyde		C_5H_4OS	98-03-3	112.150	pa ye liq		197; 85^{16}	1.2127^{21}	1.5920^{20}	i H_2O; vs EtOH; s eth; sl chl
10070	3-Thiophenecarboxaldehyde	3-Formylthiophene	C_5H_4OS	498-62-4	112.150			86.7^{20}		1.5855^{20}	i H_2O; vs EtOH, eth
10071	2-Thiophenecarboxylic acid	2-Carboxythiophene	$C_5H_4O_2S$	527-72-0	128.150	nd (w)	129.5	dec 260			vs H_2O, EtOH, eth; s chl; sl peth
10072	3-Thiophenecarboxylic acid	3-Thenoic acid	$C_5H_4O_2S$	88-13-1	128.150		138				s H_2O
10073	2,5-Thiophenedicarboxylic acid	2,5-Dicarboxythiophene	$C_6H_4O_4S$	4282-31-9	172.159		359	sub 150			sl H_2O; s EtOH, eth
10074	2-Thiophenemethanol		C_5H_6OS	636-72-6	114.166			207; 86^{10}	1.2053^{16}	1.5280^{20}	s EtOH, ace
10075	2-Thiophenesulfonyl chloride		$C_4H_3ClO_2S_2$	16629-19-9	182.649		28	100^{6}			s eth
10076	Thiopropazate		$C_{23}H_{28}ClN_3O_2S$	84-06-0	446.005			$216^{0.1}$			
10077	4*H*-Thiopyran-4-thione		$C_5H_4S_2$	1120-94-1	128.216		47				


2-Thiazolidinethione



Thidiazuron


1-(2-Thienyl)ethanone



Thiepane


Thietane


Thietane 1,1-dioxide



Thiethylperazine



Thiirane



Thioacetaldehyde trimer



Thioacetamide



Thioacetic acid


Thiobencarb



4,4'-Thiobis(6-*tert*-butyl-*m*-cresol)



2,2'-Thiobisethanamine



3,3'-Thiobispropanoic acid, didodecyl ester



Thioctic acid


Thiocyanic acid



Thiodicarb



Thiodiglycolic acid


3,3'-Thiodipropionic acid



Thiofanox


Thioformaldehyde



Thioglycolic acid



Thioimidodicarbonic diamide


Thiolactic acid



Thiometon



Thiomorpholine



Thionazin



Thiophanate-methyl



Thiophene



2-Thiopheneacetic acid


2-Thiopheneacetonitrile



2-Thiophenecarbonitrile



3-Thiophenecarbonitrile



2-Thiophenecarbonyl chloride



2-Thiophenecarboxaldehyde



3-Thiophenecarboxaldehyde



2-Thiophenecarboxylic acid



3-Thiophenecarboxylic acid


2,5-Thiophenedicarboxylic acid



2-Thiophenemethanol



2-Thiophenesulfonyl chloride



Thiopropazate



4*H*-Thiopyran-4-thione


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10078	Thioquinox		$C_9H_4N_2S_3$	93-75-4	236.336	br-ye pow	180				i H_2O; sl ace, EtOH, peth
10079	Thioridazine		$C_{12}H_{26}N_2S_2$	50-52-2	262.477	cry	73	$230^{0.02}$			sl ace
10080	*cis*-Thiothixene		$C_{23}H_{29}N_3O_2S_2$	3313-26-6	443.625	cry	148				
10081	Thiourea	Thiocarbamide	CH_4N_2S	62-56-6	76.121	orth (al)	178		1.405^{25}		s H_2O, EtOH; i eth
10082	9*H*-Thioxanthene	Dibenzothiapyran	$C_{13}H_{10}S$	261-31-4	198.283	nd (al-chl)	128.5	341			s chl
10083	9*H*-Thioxanthen-9-one	Thioxanthone	$C_{13}H_8OS$	492-22-8	212.267	ye nd (chl)	209	373			i H_2O, peth; sl EtOH; s bz, chl, CS_2
10084	2-Thioxo-4-imidazolidinone	2-Thiohydantoin	$C_3H_4N_2OS$	503-87-7	116.141	wh nd (w)	230 dec				vs H_2O, EtOH; s eth, alk
10085	2-Thioxo-4-thiazolidinone	Rhodanine	$C_3H_3NOS_2$	141-84-4	133.192	lt ye pr (al, w)	170		0.868^{25}		sl H_2O, DMSO; vs EtOH, eth
10086	Thiram		$C_6H_{12}N_2S_4$	137-26-8	240.432	wh or ye mcl (chl-al)	155.6	129^{20}			vs chl
10087	*L*-Threonine	2-Amino-3-hydroxybutanoic acid, [*R*-(*R**,*S**)]	$C_4H_9NO_3$	72-19-5	119.119		256 dec				s H_2O; i EtOH, eth, chl
10088	*D*-Threose		$C_4H_8O_4$	95-43-2	120.105	hyg-syr or nd (w)	129				
10089	*L*-Threose		$C_4H_8O_4$	95-44-3	120.105						vs H_2O
10090	Thujic acid	5,5-Dimethyl-1,3,6-cycloheptatriene-1-carboxylic acid	$C_{10}H_{12}O_2$	499-89-8	164.201	cry (peth)	88.5				
10091	α-Thujone	4-Methyl-1-(1-methylethyl)-bicyclo[3.1.0]hexan-3-one, (*l*)	$C_{10}H_{16}O$	546-80-5	152.233			201.2	0.9109^{25}	1.4490^{15}	i H_2O; s EtOH
10092	3-Thujopsene	Widdrene	$C_{15}H_{24}$	470-40-6	204.352	liq		122^{12}	0.932^{24}	1.5031^{25}	
10093	Thymidine	Thymine 2-desoxyriboside	$C_{10}H_{14}N_2O_5$	50-89-5	242.228	nd (AcOEt)	186.5				s H_2O, EtOH, ace, py, HOAc; sl chl
10094	Thymine		$C_5H_6N_2O_2$	65-71-4	126.114		316				sl H_2O, EtOH, eth, DMSO
10095	Thymol	2-Isopropyl-5-methylphenol	$C_{10}H_{14}O$	89-83-8	150.217		49.5	232.5	0.970^{25}	1.5227^{20}	i H_2O; vs EtOH, eth, chl, AcOEt
10096	Thymol Blue		$C_{27}H_{30}O_5S$	76-61-9	466.589	grn-red (al, eth)	222 dec				sl H_2O, ace, bz; s EtOH, HOAc, $PhNH_2$
10097	Thymol iodide		$C_{20}H_{24}I_2O_2$	552-22-7	550.213	amorp					i H_2O; s eth; vs EtOH
10098	Thymolphthalein		$C_{28}H_{30}O_4$	125-20-2	430.536	pr or nd (al)	253				i H_2O; s EtOH, eth, ace; sl DMSO
10099	*L*-Thyroxine		$C_{15}H_{11}I_4NO_4$	51-48-9	776.871	nd	235				sl H_2O; i EtOH, bz
10100	Timolol		$C_{13}H_{24}N_4O_3S$	26839-75-8	316.420	oil					
10101	Tiocarlide		$C_{23}H_{32}N_2O_2S$	910-86-1	400.577		146				
10102	Tipepidine	3-(Di-2-thienylmethylene)-1-methylpiperidine	$C_{15}H_{17}NS_2$	5169-78-8	275.433	ye cry	65	$181^{4.5}$			
10103	Tobramycin		$C_{18}H_{37}N_5O_9$	32986-56-4	467.516	cry					s H_2O
10104	β-Tocopherol	5,8-Dimethyltocol	$C_{28}H_{48}O_2$	148-03-8	416.680	pa ye visc oil		$205^{0.1}$			vs ace, eth, EtOH, chl
10105	γ-Tocopherol	7,8-Dimethyltocol	$C_{28}H_{48}O_2$	7616-22-0	416.680	pa ye visc oil	-1.5	$205^{0.1}$			i H_2O; msc EtOH, eth, ace, chl
10106	δ-Tocopherol	8-Methyltocol	$C_{27}H_{46}O_2$	119-13-1	402.653	pa ye visc oil		$150^{0.001}$			i H_2O; vs EtOH, eth, ace, chl
10107	Tolazamide		$C_{14}H_{21}N_3O_3S$	1156-19-0	311.400	cry	172				
10108	Tolbutamide	*N*-[(Butylamino)carbonyl]-4-methylbenzenesulfonamide	$C_{12}H_{18}N_2O_3S$	64-77-7	270.347	orth cry	128.5		1.245^{25}		sl H_2O; s EtOH, eth, chl
10109	*o*-Tolidine	3,3'-Dimethylbenzidine	$C_{14}H_{16}N_2$	119-93-7	212.290	wh-red lf (EtOH aq)	131				sl H_2O, chl; vs EtOH, eth
10110	Tolmetin		$C_{15}H_{15}NO_3$	26171-23-3	257.285	cry (MeCN)	156 dec				
10111	Toluene	Methylbenzene	C_7H_8	108-88-3	92.139	liq	-94.95	110.63	0.8668^{20}	1.4961^{20}	i H_2O; msc EtOH, eth; s ace, CS_2
10112	Toluene-2,4-diamine	4-Methyl-1,3-benzenediamine	$C_7H_{10}N_2$	95-80-7	122.167	nd (w), cry (al)	99	292			vs H_2O, EtOH, eth, bz; s chl
10113	Toluene-3,5-diamine	5-Methyl-1,3-benzenediamine	$C_7H_{10}N_2$	108-71-4	122.167	oil		284			
10114	Toluene-2,4-diisocyanate		$C_9H_6N_2O_2$	584-84-9	174.156		20.5	251	1.2244^{20}		vs ace, bz, eth
10115	Toluene-2,6-diisocyanate		$C_9H_6N_2O_2$	91-08-7	174.156		18.3				dec H_2O; s ace, bz
10116	*p*-Toluenesulfonic acid		$C_7H_8O_3S$	104-15-4	172.202	hyg pl (w+1) mcl lf or pl	104.5	140^{20}			vs H_2O; s EtOH, eth
10117	*p*-Toluenesulfonic acid monohydrate	4-Methylbenzenesulfonic acid, monohydrate	$C_7H_{10}O_4S$	6192-52-5	190.217		105.3				s H_2O



Thioquinox



Thioridazine


cis-Thiothixene



Thiourea



9*H*-Thioxanthene



9*H*-Thioxanthen-9-one



2-Thioxo-4-imidazolidinone



2-Thioxo-4-thiazolidinone



Thiram



L-Threonine



D-Threose



L-Threose



Thujic acid



α-Thujone



3-Thujopsene



Thymidine



Thymine



Thymol



Thymol Blue



Thymol iodide



Thymolphthalein



L-Thyroxine



Timolol



Tiocarlide



Tipepidine



Tobramycin



β-Tocopherol



γ-Tocopherol



δ-Tocopherol



Tolazamide



Tolbutamide



o-Tolidine



Tolmetin



Toluene



Toluene-2,4-diamine


Toluene-3,5-diamine



Toluene-2,4-diisocyanate



Toluene-2,6-diisocyanate



p-Toluenesulfonic acid



p-Toluenesulfonic acid monohydrate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10118	*p*-Toluenesulfonyl chloride		$C_7H_7ClO_2S$	98-59-9	190.648	tcl (eth, peth)	71	145^{15}			i H_2O; s EtOH, eth, chl; vs bz
10119	*o*-Toluic acid		$C_8H_8O_2$	118-90-1	136.149	pr or nd (w)	103.5	259	1.062^{115}	1.512^{115}	i H_2O; vs EtOH, eth; s chl
10120	*m*-Toluic acid		$C_8H_8O_2$	99-04-7	136.149		109.9		1.054^{112}	1.509	sl H_2O, chl; vs EtOH, eth
10121	*p*-Toluic acid		$C_8H_8O_2$	99-94-5	136.149		179.6				i H_2O; vs EtOH, eth, MeOH; sl tfa
10122	*N*-*o*-Tolylbiguanide	*N*-(2-Methylphenyl) imidodicarbonimidic diamide	$C_9H_{13}N_5$	93-69-6	191.233	nd or pl (w+1)	145.0				sl H_2O; vs EtOH, ace; i bz, chl, eth
10123	Tomatine		$C_{50}H_{83}NO_{21}$	17406-45-0	1034.188	nd (MeOH)	270				vs EtOH, diox
10124	Tralomethrin		$C_{22}H_{19}Br_4NO_3$	66841-25-6	665.007	oran-ye solid					
10125	Tranylcypromine	2-Phenylcyclopropylamine	$C_9H_{11}N$	155-09-9	133.190	cry	44	127^{32}			
10126	Trehalose		$C_{12}H_{22}O_{11}$	99-20-7	342.296	orth cry	203		1.58^{24}		vs H_2O; s EtOH; i eth, bz
10127	Triacetamide		$C_6H_9NO_3$	641-06-5	143.140	nd (eth)	79				vs eth
10128	Triacetin	Glycerol triacetate	$C_9H_{14}O_6$	102-76-1	218.203	col oily liq	-78	259	1.1583^{20}	1.4301^{20}	sl H_2O; msc EtOH, eth, bz; vs ace
10129	Triacontane		$C_{30}H_{62}$	638-68-6	422.813	orth (eth, bz)	65.1	449.7	0.8097^{20}	1.4352^{70}	i H_2O; sl EtOH; s eth; vs bz
10130	Triacontanoic acid		$C_{30}H_{60}O_2$	506-50-3	452.796	sc, nd (al, ace)	93.6			1.4323^{100}	vs bz, CS_2, chl
10131	1-Triacontanol	Myricyl alcohol	$C_{30}H_{62}O$	593-50-0	438.812	nd (eth),pl (bz)	88		0.777^{95}		vs bz, eth, EtOH
10132	Triadimenol	Mercury, chloro(2-methoxyethyl)-	C_3H_7ClHgO	123-88-6	295.13	cry	115				i H_2O; s EtOH, ace
10133	Triallate		$C_{10}H_{16}Cl_3NOS$	2303-17-5	304.664		29	$117^{0.0003}$	1.273^{25}		
10134	Triallyl phosphate		$C_9H_{15}O_4P$	1623-19-4	218.186		-50	108^{7}	1.0815^{20}		sl chl
10135	1,3,5-Triallyl-1,3,5-triazine-2,4,6(1*H*,3*H*,5*H*)-trione		$C_{12}H_{15}N_3O_3$	1025-15-6	249.265		20.5	149^{4}, $105^{0.5}$	1.1590^{20}		
10136	Triamcinolone	Fluoxiprednisolone	$C_{21}H_{27}FO_6$	124-94-7	394.433	cry	270				
10137	Triamiphos		$C_{12}H_{19}N_6OP$	1031-47-6	294.292	cry (EtOH aq)	167				sl H_2O; s os
10138	Triasulfuron		$C_{14}H_{16}ClN_5O_5S$	82097-50-5	401.826		186				
10139	1,2,4-Triazine		$C_3H_3N_3$	290-38-0	81.076	pa ye oil	16.5	157		1.5149^{25}	
10140	1,3,5-Triazine		$C_3H_3N_3$	290-87-9	81.076		80.3	114	1.38^{25}		s EtOH, eth
10141	1,2,4-Triazine-3,5(2*H*,4*H*)-dione		$C_3H_3N_3O_2$	461-89-2	113.075		276.8				
10142	1,3,5-Triazine-2,4,6-triamine	Melamine	$C_3H_6N_6$	108-78-1	126.120	mcl pr (w)	345 dec	sub	1.573^{16}	1.872^{20}	sl H_2O, EtOH; i eth
10143	1,3,5-Triazine-2,4,6(1*H*,3*H*,5*H*)-trithione	Trithiocyanuric acid	$C_3H_3N_3S_3$	638-16-4	177.271	ye pr	>300	100^{22}			
10144	Triazofos		$C_{12}H_{16}N_3O_3PS$	24017-47-8	313.312	ye-br oil	5		1.2514^{20}		i H2O; s os
10145	Triazolam		$C_{17}H_{12}Cl_2N_4$	28911-01-5	343.210	tan cry (2-PrOH)	234				
10146	1*H*-1,2,4-Triazol-3-amine	Amitrole	$C_2H_4N_4$	61-82-5	84.080	cry (w, al)	159				vs H_2O, EtOH; i eth, ace; s chl; sl AcOEt
10147	1*H*-1,2,3-Triazole		$C_2H_3N_3$	288-36-8	69.065	hyg cry	23	204	1.1861^{25}	1.4854^{25}	s H_2O; s eth, ace; i lig
10148	1*H*-1,2,4-Triazole	Pyrrodiazole	$C_2H_3N_3$	288-88-0	69.065	nd (bz/EtOH)	120.5	260 dec			s H_2O, EtOH
10149	1*H*-1,2,4-Triazole-3,5-diamine		$C_2H_5N_5$	1455-77-2	99.095		211.5				s H_2O, EtOH; i eth, bz
10150	Tribenuron-methyl		$C_{15}H_{17}N_5O_6S$	101200-48-0	395.391	solid	141				
10151	Tribenzylamine	*N*,*N*-Bis(phenylmethyl) benzenemethanamine	$C_{21}H_{21}N$	620-40-6	287.399	pl (eth), mcl (al)	91.5	385	0.9912^{95}		sl H_2O, EtOH; s eth, ctc
10152	Tribromoacetaldehyde	Bromal	C_2HBr_3O	115-17-3	280.740			174	2.6649^{25}	1.5939^{20}	vs ace, eth, EtOH
10153	Tribromoacetic acid		$C_2HBr_3O_2$	75-96-7	296.740	mcl	132	dec 245			s H_2O, EtOH, eth
10154	2,4,6-Tribromoaniline		$C_6H_4Br_3N$	147-82-0	329.815	nd (al, bz)	122	300	2.35^{20}		i H_2O; sl EtOH; s eth, chl
10155	1,2,4-Tribromobenzene		$C_6H_3Br_3$	615-54-3	314.800		44.5	275			i H_2O; s EtOH; vs eth, ace; sl bz
10156	1,3,5-Tribromobenzene		$C_6H_3Br_3$	626-39-1	314.800	nd or pr (al)	122.8	271			i H_2O; sl EtOH; s eth, bz, chl
10157	1,1,2-Tribromobutane		$C_4H_7Br_3$	3675-68-1	294.811			216.2	2.1835^{20}	1.5626^{17}	vs eth, EtOH, chl
10158	1,2,2-Tribromobutane		$C_4H_7Br_3$	3675-69-2	294.811			213.8	2.1692^{20}	1.568^{20}	vs eth, EtOH, chl



p-Toluenesulfonyl chloride



o-Toluic acid



m-Toluic acid



p-Toluic acid


N-*o*-Tolylbiguanide



Tomatine



Tralomethrin



Tranylcypromine



Trehalose



Triacetamide



Triacetin



Triacontane



Triacontanoic acid



1-Triacontanol



Triadimenol



Triallate


Triallyl phosphate


1,3,5-Triallyl-1,3,5-triazine-2,4,6(1*H*,3*H*,5*H*)-trione



Triamcinolone



Triamiphos



Triasulfuron



1,2,4-Triazine



1,3,5-Triazine



1,2,4-Triazine-3,5(2*H*,4*H*)-dione


1,3,5-Triazine-2,4,6-triamine


1,3,5-Triazine-2,4,6(1*H*,3*H*,5*H*)-trithione



Triazofos



Triazolam



1*H*-1,2,4-Triazol-3-amine



1*H*-1,2,3-Triazole



1*H*-1,2,4-Triazole



1*H*-1,2,4-Triazole-3,5-diamine



Tribenuron-methyl



Tribenzylamine



Tribromoacetaldehyde



Tribromoacetic acid


2,4,6-Tribromoaniline



1,2,4-Tribromobenzene



1,3,5-Tribromobenzene


1,1,2-Tribromobutane


1,2,2-Tribromobutane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10159	1,2,3-Tribromobutane		$C_4H_7Br_3$	632-05-3	294.811	liq	-19	220	2.1907^{20}	1.5680^{20}	vs eth, EtOH, chl
10160	1,2,4-Tribromobutane		$C_4H_7Br_3$	38300-67-3	294.811	liq	-18	215	2.170^{20}	1.5608^{20}	vs eth, EtOH, chl
10161	2,2,3-Tribromobutane		$C_4H_7Br_3$	62127-47-3	294.811		0.9	206	2.1723^{20}	1.5602^{20}	i H_2O; s EtOH, eth, chl; sl ctc
10162	Tribromochloromethane		CBr_3Cl	594-15-0	287.176	lf (eth)	55	158.5	2.71^{15}		vs eth
10163	1,1,2-Tribromoethane		$C_2H_3Br_3$	78-74-0	266.757	liq	-29.3	188.93	2.6210^{20}	1.5933^{20}	i H_2O; s EtOH, eth, bz, ctc
10164	2,2,2-Tribromoethanol		$C_2H_3Br_3O$	75-80-9	282.756	nd or pr (peth)	81	92^{10}			vs bz, eth, EtOH
10165	Tribromoethene		C_2HBr_3	598-16-3	264.741			164	2.708^{20}	1.6045^{16}	sl H_2O; vs EtOH; s eth, ace, chl
10166	Tribromofluoromethane		CBr_3F	353-54-8	270.721	liq	-73.6	108			i H_2O; s EtOH
10167	Tribromomethane	Bromoform	$CHBr_3$	75-25-2	252.731		8.69	149.1	2.8788^{25}	1.5948^{25}	sl H_2O; msc EtOH, eth; s bz, lig, chl
10168	1,3,5-Tribromo-2-methoxybenzene		$C_7H_5Br_3O$	607-99-8	344.826	nd (al)	88	298	2.491^{25}		sl H_2O, EtOH; vs ace, bz; s ctc
10169	2,4,6-Tribromo-3-methylphenol	2,4,6-Tribromo-*m*-cresol	$C_7H_5Br_3O$	4619-74-3	344.826		84				s EtOH, eth, bz, HOAc; sl chl, peth
10170	1,1,1-Tribromo-2-methyl-2-propanol	1,1,1-Tribromo-*tert*-butyl alcohol	$C_4H_7Br_3O$	76-08-4	310.810	nd (lig) cry (dil al)	169	sub			sl H_2O, chl; s EtOH, eth
10171	Tribromonitromethane		CBr_3NO_2	464-10-8	297.729	pr	10	127^{18}	2.811^{12}	1.5790^{20}	i H_2O; s EtOH, eth; vs ace, bz
10172	2,4,6-Tribromophenol		$C_6H_3Br_3O$	118-79-6	330.799	nd (al), pr (bz)	95.5	286	2.55^{20}		i H_2O; vs EtOH; s eth, bz, HOAc, chl
10173	1,1,2-Tribromopropane		$C_3H_5Br_3$	14602-62-1	280.784			200.5	2.3547^{20}	1.5790^{20}	i H_2O; s EtOH, chl, HOAc; vs eth
10174	1,2,2-Tribromopropane		$C_3H_5Br_3$	14476-30-3	280.784			190.5	2.2984^{20}	1.5670^{20}	vs eth, EtOH, chl
10175	1,2,3-Tribromopropane		$C_3H_5Br_3$	96-11-7	280.784		16.9	222.1	2.4208^{20}	1.5862^{20}	i H_2O; vs EtOH, eth; sl ctc
10176	2,3,5-Tribromothiophene		C_4HBr_3S	3141-24-0	320.828	nd (al)	29	260			s chl
10177	Tribromotrimethyldialuminum	Methyl aluminum sesquibromide	$C_3H_9Al_2Br_3$	12263-85-3	338.778	hyg col liq		110^{50}			
10178	Tributyl 2-(acetyloxy)-1,2,3-propanetricarboxylate		$C_{20}H_{34}O_8$	77-90-7	402.479			173^{1}			sl chl
10179	Tributyl aluminate	1-Butanol, aluminum salt	$C_{12}H_{27}AlO_3$	3085-30-1	246.322			260^{5}			
10180	Tributylaluminum		$C_{12}H_{27}Al$	1116-70-7	198.324			102^{2}			
10181	Tributylamine	*N,N*-Dibutyl-1-butanamine	$C_{12}H_{27}N$	102-82-9	185.349	liq	-70	216.5	0.7770^{20}	1.4299^{20}	sl H_2O, ctc; vs EtOH, eth; s ace, bz
10182	Tributyl borate		$C_{12}H_{27}BO_3$	688-74-4	230.151	oil	<-70	234	0.8567^{20}	1.4106^{18}	s EtOH, bz; vs eth, MeOH
10183	Tributylfluorostannane	Tributyltin fluoride	$C_{12}H_{27}FSn$	1983-10-4	309.050	nd	≈260	sub >200			
10184	2,4,6-Tri-*tert*-butylphenol		$C_{18}H_{30}O$	732-26-3	262.430	cry (al, peth)	131	278	0.864^{27}		i H_2O, alk; s EtOH, ace, ctc
10185	Tributyl phosphate		$C_{12}H_{27}O_4P$	126-73-8	266.313			289	0.9727^{25}	1.4224^{25}	s H_2O, eth, bz, CS_2; msc EtOH
10186	Tributylphosphine		$C_{12}H_{27}P$	998-40-3	202.316			240; 150^{50}	0.812^{25}	1.4619^{20}	
10187	Tributyl phosphite	Tributoxyphosphine	$C_{12}H_{27}O_3P$	102-85-2	250.314			137^{26}, 122^{12}	0.9259^{20}	1.4321^{19}	s EtOH; sl ctc; vs eth
10188	*S,S,S*-Tributyl phosphorotrithioate	*S,S,S*-Tributyl trithiophosphate	$C_{12}H_{27}OPS_3$	78-48-8	314.510		<-25	150$^{0.3}$	1.057^{20}		
10189	Tributylsilane		$C_{12}H_{28}Si$	998-41-4	200.436			221	0.7794^{20}	1.4380^{20}	
10190	Tributylstannane	Tributyltin hydride	$C_{12}H_{28}Sn$	688-73-3	291.060	liq		113^{8}, 76$^{0.7}$	1.103^{20}		
10191	Tributyrin	Butanoic acid, 1,2,3-propanetriyl ester	$C_{15}H_{26}O_6$	60-01-5	302.363	liq	-75	307.5	1.0350^{20}	1.4359^{20}	i H_2O; s EtOH, ace, bz; sl ctc; vs eth
10192	Tricalcium citrate	Calcium citrate	$C_{12}H_{10}Ca_3O_{14}$	813-94-5	498.433	cry (w)	≈100 dec (hyd)				sl H_2O; i EtOH
10193	Trichlorfon		$C_4H_8Cl_3O_4P$	52-68-6	257.437		77	100$^{0.1}$	1.73^{20}		
10194	Trichloroacetaldehyde	Chloral	C_2HCl_3O	75-87-6	147.387	liq	-57.5	97.8	1.512^{20}	1.4580^{20}	vs H_2O; s EtOH, eth
10195	2,2,2-Trichloroacetamide		$C_2H_2Cl_3NO$	594-65-0	162.402		142	240			sl H_2O; vs EtOH, eth
10196	Trichloroacetic acid		$C_2HCl_3O_2$	76-03-9	163.387	hyg cry	59.2	196.5	1.6126^{64}	1.4603^{61}	vs H_2O; s EtOH, eth; sl ctc
10197	Trichloroacetic anhydride		$C_4Cl_6O_3$	4124-31-6	308.759			dec 223; 139^{60}	1.6908^{20}		vs eth, HOAc
10198	Trichloroacetonitrile		C_2Cl_3N	545-06-2	144.387	liq	-42	85.7	1.4403^{25}	1.4409^{20}	i H_2O
10199	Trichloroacetyl chloride		C_2Cl_4O	76-02-8	181.832			117.9	1.6202^{20}	1.4695^{20}	msc eth
10200	2,3,4-Trichloroaniline		$C_6H_4Cl_3N$	634-67-3	196.462	nd (lig)	73	292			vs EtOH



1,2,3-Tribromobutane


1,2,4-Tribromobutane


2,2,3-Tribromobutane


Tribromochloromethane



1,1,2-Tribromoethane



2,2,2-Tribromoethanol



Tribromoethene


Tribromofluoromethane



Tribromomethane


1,3,5-Tribromo-2-methoxybenzene


2,4,6-Tribromo-3-methylphenol



1,1,1-Tribromo-2-methyl-2-propanol



Tribromonitromethane


2,4,6-Tribromophenol



1,1,2-Tribromopropane



1,2,2-Tribromopropane



1,2,3-Tribromopropane



2,3,5-Tribromothiophene



Tribromotrimethyldialuminum



Tributyl 2-(acetyloxy)-1,2,3-propanetricarboxylate



Tributyl aluminate



Tributylaluminum



Tributylamine



Tributyl borate



Tributylfluorostannane



2,4,6-Tri-*tert*-butylphenol



Tributyl phosphate



Tributylphosphine



Tributyl phosphite



S,S,S-Tributyl phosphorotrithioate



Tributylsilane



Tributylstannane



Tributyrin



Tricalcium citrate



Trichlorfon



Trichloroacetaldehyde



2,2,2-Trichloroacetamide


Trichloroacetic acid



Trichloroacetic anhydride



Trichloroacetonitrile



Trichloroacetyl chloride



2,3,4-Trichloroaniline


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10201	2,4,5-Trichloroaniline		$C_6H_4Cl_3N$	636-30-6	196.462	nd (lig)	96.5	270			s EtOH, eth; vs CS_2; sl lig
10202	2,4,6-Trichloroaniline		$C_6H_4Cl_3N$	634-93-5	196.462	cry (al), nd (lig or peth)	78.5	262			i H_2O; s EtOH, eth, chl; vs CS_2
10203	2,3,6-Trichlorobenzaldehyde		$C_7H_3Cl_3O$	4659-47-6	209.457	nd (lig)	87.3				vs ace, bz, eth
10204	1,2,3-Trichlorobenzene		$C_6H_3Cl_3$	87-61-6	181.447	pl (al)	51.3	218.5	1.4533^{25}		i H_2O; sl EtOH, chl; vs eth, bz
10205	1,2,4-Trichlorobenzene		$C_6H_3Cl_3$	120-82-1	181.447	orth	16.92	213.5	1.459^{25}	1.5717^{20}	i H_2O; sl EtOH, chl; vs eth
10206	1,3,5-Trichlorobenzene		$C_6H_3Cl_3$	108-70-3	181.447	nd	62.8	208			i H_2O; sl EtOH; vs eth, bz; s chl
10207	2,3,6-Trichlorobenzeneacetic acid	Chlorfenac	$C_8H_5Cl_3O_2$	85-34-7	239.484		161				
10208	3,4,5-Trichloro-1,2-benzenediol		$C_6H_3Cl_3O_2$	56961-20-7	213.446	(i) pr (HOAc) (ii) pr (bz)	115(form a); 134(form b)				sl H_2O; vs eth, EtOH, HOAc
10209	2,3,6-Trichlorobenzoic acid		$C_7H_3Cl_3O_2$	50-31-7	225.457		124.5				sl H_2O; s eth
10210	2,4,5-Trichlorobiphenyl		$C_{12}H_7Cl_3$	15862-07-4	257.543	cry	78.5				i H_2O
10211	2,4,6-Trichlorobiphenyl		$C_{12}H_7Cl_3$	35693-92-6	257.543	cry (EtOH aq)	62.5	172^{15}			i H_2O
10212	1,1,1-Trichloro-2,2-bis(4-chlorophenyl)ethane	Dichlorodiphenyltrichloroethane (DDT)	$C_{14}H_9Cl_5$	50-29-3	354.486	nd (al)	108.5	260; $186^{0.05}$			i H_2O; sl EtOH; vs eth, ace, bz, py
10213	2,2,3-Trichlorobutanal	2,2,3-Trichlorobutyraldehyde	$C_4H_5Cl_3O$	76-36-8	175.441			164	1.3956^{20}	1.4755^{20}	vs H_2O, eth, EtOH
10214	2,3,4-Trichloro-1-butene		$C_4H_5Cl_3$	2431-50-7	159.442			60^{20}, 40^{10}	1.3430^{20}	1.4944^{20}	vs ace, chl
10215	3,4,4'-Trichlorocarbanilide	Triclocarban	$C_{13}H_9Cl_3N_2O$	101-20-2	315.581	fine pl	256				
10216	1,2,4-Trichloro-5-(chloromethyl) benzene		$C_7H_4Cl_4$	3955-26-8	229.919			273	1.547^{20}		vs ace, eth, EtOH
10217	Trichloro(chloromethyl)silane	(Chloromethyl)trichlorosilane	CH_2Cl_4Si	1558-25-4	183.925			118	1.4650^{20}	1.4555^{20}	
10218	Trichloro(4-chlorophenyl)silane		$C_6H_4Cl_4Si$	825-94-5	245.994			233; 116^{20}	1.4062^{20}	1.5418^{20}	
10219	Trichloro(3-chloropropyl)silane		$C_3H_6Cl_4Si$	2550-06-3	211.978			181.5	1.3590^{20}	1.4668^{20}	
10220	Trichloro(dichloromethyl)silane	(Dichloromethyl)trichlorosilane	$CHCl_5Si$	1558-24-3	218.370			145	1.5518^{20}	1.4714^{20}	
10221	1,1,1-Trichloro-2,2-difluoroethane		$C_2HCl_3F_2$	354-12-1	169.385			73			
10222	1,2,2-Trichloro-1,1-difluoroethane		$C_2HCl_3F_2$	354-21-2	169.385		-140	71.9	1.5447^{20}	1.3889^{20}	
10223	1,2,2-Trichloro-1,2-difluoroethane		$C_2HCl_3F_2$	354-15-4	169.385		-174	72.5			
10224	2,4,6-Trichloro-3,5-dimethylphenol		$C_8H_7Cl_3O$	6972-47-0	225.500	ye nd (peth)	175				i H_2O; s chl; vs peth
10225	1,1,1-Trichloro-2,2-diphenylethane		$C_{14}H_{11}Cl_3$	2971-22-4	285.596		65				s EtOH; sl chl
10226	Trichlorododecylsilane	Dodecyltrichlorosilane	$C_{12}H_{25}Cl_3Si$	4484-72-4	303.772			155^{10}		1.4581^{20}	
10227	1,1,1-Trichloro-3,4-epoxybutane	(2,2,2-Trichloroethyl)oxirane	$C_4H_5Cl_3O$	3083-25-8	175.441	liq		110^{100}			
10228	1,1,1-Trichloroethane	Methyl chloroform	$C_2H_3Cl_3$	71-55-6	133.404	liq	-30.01	74.09	1.3390^{20}	1.4379^{20}	sl H_2O; s EtOH, chl; msc eth
10229	1,1,2-Trichloroethane	Vinyl trichloride	$C_2H_3Cl_3$	79-00-5	133.404	liq	-36.3	113.8	1.4397^{20}	1.4714^{20}	i H_2O; s EtOH, eth, chl
10230	2,2,2-Trichloroethanol		$C_2H_3Cl_3O$	115-20-8	149.403	hyg orth tab or pl	19	152; 52^{11}		1.4861^{20}	sl H_2O, ctc; msc EtOH, eth; s alk
10231	Trichloroethene	Trichloroethylene	C_2HCl_3	79-01-6	131.388	liq	-84.7	87.21	1.4642^{20}	1.4773^{20}	sl H_2O, ctc; msc EtOH, eth; s ace
10232	2,2,2-Trichloro-1-ethoxyethanol	Chloral alcoholate	$C_4H_7Cl_3O_2$	515-83-3	193.457		56.5	115.5	1.143^{40}		s H_2O, EtOH, eth
10233	Trichloroethoxysilane		$C_2H_5Cl_3OSi$	1825-82-7	179.505	liq	-135	101.9	1.2274^{20}	1.4045^{20}	vs EtOH
10234	2,2,2-Trichloroethyl-β-*D*-glucopyranosiduronic acid	Urochloralic acid	$C_8H_{11}Cl_3O_7$	97-25-6	325.528	nd	142				vs H_2O, EtOH
10235	Trichloroethylsilane	Ethyltrichlorosilane	$C_2H_5Cl_3Si$	115-21-9	163.506	liq	-105.6	100.5	1.2373^{20}	1.4256^{20}	s ctc
10236	1,1,1-Trichloro-2-fluoroethane	Refrigerant 131b	$C_2H_2Cl_3F$	2366-36-1	151.394	liq		86.5			
10237	1,1,2-Trichloro-1-fluoroethane	Refrigerant 131a	$C_2H_2Cl_3F$	811-95-0	151.394		-104.7	88.0	1.492^{20}		
10238	1,1,2-Trichloro-2-fluoroethane		$C_2H_2Cl_3F$	359-28-4	151.394			102.4	1.5393^{20}	1.4390^{20}	i H_2O
10239	Trichlorofluoromethane	Refrigerant 11	CCl_3F	75-69-4	137.368	vol liq or gas	-110.44	23.7			i H_2O
10240	2,2,3-Trichloro-1,1,1,3,4,4,4-heptafluorobutane		$C_4Cl_3F_7$	335-44-4	287.391		2.0	98	1.7484^{20}	1.3530^{20}	
10241	Trichlorohexylsilane	Hexyltrichlorosilane	$C_6H_{13}Cl_3Si$	928-65-4	219.612			190	1.1100^{20}		dec H_2O
10242	*N*-(2,2,2-Trichloro-1-hydroxyethyl)formamide	Chloral formamide	$C_3H_4Cl_3NO_2$	515-82-2	192.429	cry	120				vs ace, eth, EtOH
10243	3,3,3-Trichloro-2-hydroxypropanenitrile	Chlorocyanohydrin	$C_3H_2Cl_3NO$	513-96-2	174.413	pl (w)	61	dec 217			vs H_2O, eth, EtOH
10244	Trichloroisobutylsilane		$C_4H_9Cl_3Si$	18169-57-8	191.559			143.3	1.154^{20}		dec H_2O
10245	Trichloromethane	Chloroform	$CHCl_3$	67-66-3	119.378	liq	-63.41	61.17	1.4788^{25}	1.4459^{20}	sl H_2O; msc EtOH, eth, bz; s ace, ctc
10246	Trichloromethanesulfenyl chloride	Perchloromethyl mercaptan	CCl_4S	594-42-3	185.888	ye oil		149	1.6947^{20}	1.5484^{20}	s eth



2,4,5-Trichloroaniline



2,4,6-Trichloroaniline



2,3,6-Trichlorobenzaldehyde



1,2,3-Trichlorobenzene



1,2,4-Trichlorobenzene



1,3,5-Trichlorobenzene



2,3,6-Trichlorobenzeneacetic acid



3,4,5-Trichloro-1,2-benzenediol



2,3,6-Trichlorobenzoic acid



2,4,5-Trichlorobiphenyl



2,4,6-Trichlorobiphenyl



1,1,1-Trichloro-2,2-bis(4-chlorophenyl)ethane



2,2,3-Trichlorobutanal



2,3,4-Trichloro-1-butene



3,4,4′-Trichlorocarbanilide


1,2,4-Trichloro-5-(chloromethyl)benzene



Trichloro(chloromethyl)silane



Trichloro(4-chlorophenyl)silane



Trichloro(3-chloropropyl)silane



Trichloro(dichloromethyl)silane



1,1,1-Trichloro-2,2-difluoroethane



1,2,2-Trichloro-1,1-difluoroethane



1,2,2-Trichloro-1,2-difluoroethane



2,4,6-Trichloro-3,5-dimethylphenol



1,1,1-Trichloro-2,2-diphenylethane


Trichlorododecylsilane



1,1,1-Trichloro-3,4-epoxybutane



1,1,1-Trichloroethane



1,1,2-Trichloroethane


2,2,2-Trichloroethanol


Trichloroethene



2,2,2-Trichloro-1-ethoxyethanol



Trichloroethoxysilane


2,2,2-Trichloroethyl-β-*D*-glucopyranosiduronic acid



Trichloroethylsilane



1,1,1-Trichloro-2-fluoroethane



1,1,2-Trichloro-1-fluoroethane



1,1,2-Trichloro-2-fluoroethane



Trichlorofluoromethane


2,2,3-Trichloro-1,1,1,3,4,4,4-heptafluorobutane



Trichlorohexylsilane


N-(2,2,2-Trichloro-1-hydroxyethyl)formamide



3,3,3-Trichloro-2-hydroxypropanenitrile


Trichloroisobutylsilane



Trichloromethane



Trichloromethanesulfenyl chloride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10247	Trichloromethanesulfonyl chloride		CCl_4O_2S	2547-61-7	217.887	cry (al-w)	140.5	170			i H_2O; s EtOH, eth, CS_2
10248	Trichloromethanethiol	Trichloromethyl mercaptan	$CHCl_3S$	75-70-7	151.443	oran oil		125^{15}			
10249	Trichloromethiazide		$C_8H_8Cl_3N_3O_4S_2$	133-67-5	380.657		270 dec				sl H_2O; s EtOH
10250	1,2,4-Trichloro-5-methoxybenzene		$C_7H_5Cl_3O$	6130-75-2	211.473	nd (dil al)	77.5	254			vs EtOH, ace
10251	1,3,5-Trichloro-2-methoxybenzene	2,4,6-Trichloroanisole	$C_7H_5Cl_3O$	87-40-1	211.473	mcl nd (al)	61.5	241	1.640^{25}		s EtOH, bz, chl; vs ace
10252	1,2,4-Trichloro-5-methylbenzene	2,4,5-Trichlorotoluene	$C_7H_5Cl_3$	6639-30-1	195.474	nd or lf (al)	82.4	231			i H_2O; s EtOH, ace
10253	(Trichloromethyl)benzene	Benzotrichloride	$C_7H_5Cl_3$	98-07-7	195.474	liq	-4.42	221	1.3723^{20}	1.5580^{20}	i H_2O; s EtOH, eth, bz
10254	(Trichloromethyl)oxirane		$C_3H_3Cl_3O$	3083-23-6	161.414			$149; 44^{13}$	1.495^{20}	1.4737^{25}	vs eth; s chl
10255	2,3,4-Trichloro-6-methylphenol	4,5,6-Trichloro-*o*-cresol	$C_7H_5Cl_3O$	551-78-0	211.473	nd (peth)	77				
10256	2,3,6-Trichloro-4-methylphenol	2,3,6-Trichloro-*p*-cresol	$C_7H_5Cl_3O$	551-77-9	211.473	nd (HOAc, peth)	66.5				vs EtOH
10257	2,4,6-Trichloro-3-methylphenol	2,4,6-Trichloro-*m*-cresol	$C_7H_5Cl_3O$	551-76-8	211.473	nd or pl (w, peth)	46	265			i H_2O; vs EtOH, MeOH, chl
10258	1,1,1-Trichloro-2-methyl-2-propanol	1,1,1-Trichloro-*tert*-butyl alcohol	$C_4H_7Cl_3O$	57-15-8	177.457	hyg nd (w + 1)	97	167			i H_2O; s EtOH, eth, ace, bz, lig, chl
10259	Trichloronate		$C_{10}H_{12}Cl_3O_2PS$	327-98-0	333.599	ye liq		$108^{0.01}$	1.365^{20}		
10260	1,2,4-Trichloro-5-nitrobenzene		$C_6H_2Cl_3NO_2$	89-69-0	226.445	pr (al), nd (al)	57.5	288	1.790^{23}		i H_2O; sl EtOH; s eth, bz, chl, CS_2
10261	Trichloronitromethane	Chloropicrin	CCl_3NO_2	76-06-2	164.376	liq	-64	112	1.6558^{20}	1.4611^{20}	s H_2O; msc EtOH, ace, bz, MeOH, HOAc
10262	3,4,6-Trichloro-2-nitrophenol		$C_6H_2Cl_3NO_3$	82-62-2	242.444	pa ye cry (peth)	92.5				
10263	Trichlorooctadecylsilane	Octadecyltrichlorosilane	$C_{18}H_{37}Cl_3Si$	112-04-9	387.932			223^{10}	0.984^{25}	1.4602^{20}	
10264	Trichlorooctylsilane	Octyltrichlorosilane	$C_8H_{17}Cl_3Si$	5283-66-9	247.666			232		1.4480^{20}	dec H_2O, EtOH; s ctc
10265	1,2,3-Trichloro-1,1,2,3,3-pentafluoropropane		$C_3Cl_3F_5$	76-17-5	237.383	liq	-72	73.7	1.6631^{20}	1.3512^{20}	
10266	Trichloropentylsilane	Amyltrichlorosilane	$C_5H_{11}Cl_3Si$	107-72-2	205.586			$172; 60.5^{15}$	1.1330^{20}	1.4503^{20}	
10267	2,3,4-Trichlorophenol		$C_6H_3Cl_3O$	15950-66-0	197.446	nd (bz, lig, sub)	83.5	sub			s EtOH, eth, bz, alk, HOAc
10268	2,3,5-Trichlorophenol		$C_6H_3Cl_3O$	933-78-8	197.446	nd (al)	62	248^{250}			vs eth, EtOH
10269	2,3,6-Trichlorophenol		$C_6H_3Cl_3O$	933-75-5	197.446	nd (dil al, lig)	58				sl H_2O; vs EtOH, eth, bz; s HOAc
10270	2,4,5-Trichlorophenol		$C_6H_3Cl_3O$	95-95-4	197.446	nd (al, peth)	69	247			sl H_2O; vs EtOH, eth, bz; s HOAc
10271	2,4,6-Trichlorophenol		$C_6H_3Cl_3O$	88-06-2	197.446	orth nd (HOAc)	69	246	1.4901^{75}		sl H_2O; s EtOH, eth, HOAc
10272	3,4,5-Trichlorophenol		$C_6H_3Cl_3O$	609-19-8	197.446	nd (lig)	101	275			sl H_2O, lig; s eth
10273	2,4,5-Trichlorophenoxyacetic acid	2,4,5-T	$C_8H_5Cl_3O_3$	93-76-5	255.483	cry (bz)	153	dec			i H_2O; s EtOH; vs bz
10274	2-(2,4,5-Trichlorophenoxy)ethyl 2,2-dichloropropanoate	Pentanate	$C_{11}H_9Cl_5O_3$	136-25-4	366.452		49	$162^{0.5}$	1.55^{50}		i H_2O; s EtOH, ace, xyl
10275	Trichloro(2-phenylethyl)silane		$C_8H_9Cl_3Si$	940-41-0	239.602			$242; 98^{5}$	1.2397^{20}	1.5185^{20}	
10276	(2,4,6-Trichlorophenyl)hydrazine		$C_6H_5Cl_3N_2$	5329-12-4	211.476	cry (bz)	143				s H_2O, bz
10277	Trichlorophenylsilane		$C_6H_5Cl_3Si$	98-13-5	211.549			201	1.321^{20}	1.5230^{20}	s ctc, chl, CS_2
10278	1,1,2-Trichloropropane		$C_3H_5Cl_3$	598-77-6	147.431			$132.0; 117^{500}$	1.372^{15}		i H_2O; s EtOH, chl; vs eth; sl ctc
10279	1,1,3-Trichloropropane		$C_3H_5Cl_3$	20395-25-9	147.431	liq	-59	145.5	1.3557^{20}	1.4718^{20}	vs eth, EtOH, chl
10280	1,2,2-Trichloropropane		$C_3H_5Cl_3$	3175-23-3	147.431			124	1.318^{25}	1.4609^{20}	i H_2O; s EtOH, eth; vs chl
10281	1,2,3-Trichloropropane		$C_3H_5Cl_3$	96-18-4	147.431	liq	-14.7	157	1.3889^{20}	1.4852^{20}	sl H_2O, ctc; s EtOH, eth; vs chl
10282	1,1,1-Trichloro-2-propanol		$C_3H_5Cl_3O$	76-00-6	163.430		50.5	$163; 54^{12}$			vs ace, bz, eth, EtOH
10283	1,1,1-Trichloro-2-propanone	1,1,1-Trichloroacetone	$C_3H_3Cl_3O$	918-00-3	161.414			$149; 28^{10}$	1.435^{20}	1.4635^{17}	i H_2O; vs EtOH, eth
10284	1,2,3-Trichloro-1-propene		$C_3H_3Cl_3$	96-19-5	145.415			142	1.412^{20}	1.5030^{20}	i H_2O; vs EtOH, eth; s bz, chl
10285	3,3,3-Trichloro-1-propene		$C_3H_3Cl_3$	2233-00-3	145.415	liq	-30	114.5	1.367^{20}	1.4827^{20}	i H_2O; s EtOH, eth, bz, chl
10286	2,3,3-Trichloro-2-propenoyl chloride		C_3Cl_4O	815-58-7	193.843			158		1.5271^{18}	vs bz
10287	Trichloropropylsilane	Propyltrichlorosilane	$C_3H_7Cl_3Si$	141-57-1	177.533			123.5	1.195^{20}	1.4310^{20}	



Trichloromethanesulfonyl chloride



Trichloromethanethiol



Trichloromethiazide



1,2,4-Trichloro-5-methoxybenzene



1,3,5-Trichloro-2-methoxybenzene



1,2,4-Trichloro-5-methylbenzene



(Trichloromethyl)benzene



(Trichloromethyl)oxirane



2,3,4-Trichloro-6-methylphenol


2,3,6-Trichloro-4-methylphenol



2,4,6-Trichloro-3-methylphenol



1,1,1-Trichloro-2-methyl-2-propanol



Trichloronate



1,2,4-Trichloro-5-nitrobenzene



Trichloronitromethane



3,4,6-Trichloro-2-nitrophenol



Trichlorooctadecylsilane



Trichlorooctylsilane



1,2,3-Trichloro-1,1,2,3,3-pentafluoropropane



Trichloropentylsilane



2,3,4-Trichlorophenol



2,3,5-Trichlorophenol



2,3,6-Trichlorophenol



2,4,5-Trichlorophenol



2,4,6-Trichlorophenol



3,4,5-Trichlorophenol


2,4,5-Trichlorophenoxyacetic acid



2-(2,4,5-Trichlorophenoxy)ethyl 2,2-dichloropropanoate


Trichloro(2-phenylethyl)silane



(2,4,6-Trichlorophenyl)hydrazine


Trichlorophenylsilane



1,1,2-Trichloropropane



1,1,3-Trichloropropane


1,2,2-Trichloropropane



1,2,3-Trichloropropane



1,1,1-Trichloro-2-propanol


1,1,1-Trichloro-2-propanone



1,2,3-Trichloro-1-propene



3,3,3-Trichloro-1-propene



2,3,3-Trichloro-2-propenoyl chloride



Trichloropropylsilane

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10288	2,4,6-Trichloropyrimidine		$C_4HCl_3N_2$	3764-01-0	183.423		22.5	212.5		1.5700^{20}	
10289	3-(Trichlorosilyl)propanenitrile		$C_3H_4Cl_3NSi$	1071-22-3	188.516			109^{30}			
10290	2,4,6-Trichloro-1,3,5-triazine	Cyanuric acic trichloride	$C_3Cl_3N_3$	108-77-0	184.411	cry (eth, bz)	154	192			vs EtOH
10291	2,2',2"-Trichlorotriethylamine		$C_6H_{12}Cl_3N$	555-77-1	204.525	pa ye	-2.0	143^{15}			vs bz, eth, EtOH
10292	Trichlorotriethyldialuminum	Ethylaluminum sesquichloride	$C_6H_{15}Al_2Cl_3$	12075-68-2	247.505	ye liq		115.5^{50}, 36.2$^{0.2}$			
10293	1,3,5-Trichloro-2,4,6-trifluorobenzene		$C_6Cl_3F_3$	319-88-0	235.418			198.4			
10294	1,1,1-Trichloro-2,2,2-trifluoroethane		$C_2Cl_3F_3$	354-58-5	187.375		14.37	45.5	1.5790^{20}	1.3610^{35}	i H_2O; s EtOH, eth, chl
10295	1,1,2-Trichloro-1,2,2-trifluoroethane		$C_2Cl_3F_3$	76-13-1	187.375	liq	-36.22	47.7	1.5635^{25}	1.3557^{25}	i H_2O; s EtOH; msc eth, bz
10296	Trichlorovinylsilane	Vinyltrichlorosilane	$C_2H_3Cl_3Si$	75-94-5	161.490	liq	-95	91.5	1.2426^{20}	1.4295^{20}	vs chl
10297	Trichodermin	12,13-Epoxytrichothec-9-en-4-ol acetate	$C_{17}H_{24}O_4$	4682-50-2	292.371	cry	59	111$^{0.05}$			sl H_2O; s EtOH, chl
10298	Triclofos	2,2,2-Trichloroethanol dihydrogen phosphate	$C_2H_4Cl_3O_4P$	306-52-5	229.383	cry (bz)	120.5				
10299	Triclopyr	Acetic acid, [(3,5,6-trichloro-2-pyridinyl)oxy]-	$C_7H_4Cl_3NO_3$	55335-06-3	256.471		149	dec 290			
10300	Tricosane		$C_{23}H_{48}$	638-67-5	324.627	lf (eth-al)	47.76	380	0.7785^{48}	1.4468^{20}	i H_2O; sl EtOH; s eth, ctc
10301	12-Tricosanone	Diundecyl ketone	$C_{23}H_{46}O$	540-09-0	338.610	lf (al)	70.2		0.8086^{69}	1.4283^{80}	vs bz, eth, chl
10302	Tri-*o*-cresyl phosphate	Tri-*o*-tolyl phosphate	$C_{21}H_{21}O_4P$	78-30-8	368.363	col or pa ye	11	410	1.1955^{20}	1.5575^{20}	i H_2O; vs EtOH, eth, ctc, tol; s HOAc
10303	Tri-*m*-cresyl phosphate	Tri-*m*-tolyl phosphate	$C_{21}H_{21}O_4P$	563-04-2	368.363	wax	25.5	260^{15}	1.150^{25}	1.5575^{20}	i H_2O; sl EtOH; s eth; vs ctc, tol
10304	Tri-*p*-cresyl phosphate	Tri-*p*-tolyl phosphate	$C_{21}H_{21}O_4P$	78-32-0	368.363	nd (al), tab (eth)	77.5	224^{35}	1.247^{25}		s EtOH, eth, bz, chl, HOAc
10305	1,3,6-Tricyanohexane		$C_9H_{11}N_3$	1772-25-4	161.203	br liq		257^{2}	1.040	1.4660^{20}	
10306	Tricyclazole	1,2,4-Triazolo[3,4-b] benzothiazole, 5-methyl-	$C_9H_7N_3S$	41814-78-2	189.237		187				
10307	Tricyclene	1,7,7-Trimethyltricyclo[2.2.1.0^{2,6}] heptane	$C_{10}H_{16}$	508-32-7	136.234	cry (al)	67.5	152.5	0.8668^{80}	1.4296^{80}	
10308	Tricyclo[3.3.1.1^{3,7}]decan-1-amine	Amantadine	$C_{10}H_{17}N$	768-94-5	151.249		180				sl H_2O
10309	Tricyclo[3.3.1.1^{3,7}]decane	Adamantane	$C_{10}H_{16}$	281-23-2	136.234	nd (sub)	268	sub	1.07^{25}	1.568	s bz, ctc
10310	Tridecanal		$C_{13}H_{26}O$	10486-19-8	198.344		14	156^{13}	0.8356^{18}	1.4384^{18}	i H_2O; s EtOH
10311	Tridecane		$C_{13}H_{28}$	629-50-5	184.361	liq	-5.4	235.47	0.7564^{20}	1.4256^{20}	i H_2O; vs EtOH, eth; s ctc
10312	Tridecanedioic acid		$C_{13}H_{24}O_4$	505-52-2	244.328		114				sl H_2O, bz, tfa; s EtOH, eth, chl
10313	Tridecanenitrile		$C_{13}H_{25}N$	629-60-7	195.345		9.7	293	0.8257^{20}	1.4378^{20}	vs EtOH, eth
10314	Tridecanoic acid	Tridecylic acid	$C_{13}H_{26}O_2$	638-53-9	214.344	cry (peth ace)	41.5	236^{100}, 140^{1}	0.8458^{80}	1.4286^{60}	i H_2O; vs EtOH, eth, HOAc; s ace
10315	1-Tridecanol	Tridecyl alcohol	$C_{13}H_{28}O$	112-70-9	200.360	cry (al)	31.7	274; 152^{14}	0.8223^{31}		i H_2O; s EtOH, eth
10316	2-Tridecanone	Methyl undecyl ketone	$C_{13}H_{26}O$	593-08-8	198.344		30.5	263	0.8217^{30}	1.4318^{20}	i H_2O; vs EtOH, eth, ace, bz, chl
10317	7-Tridecanone	Dihexyl ketone	$C_{13}H_{26}O$	462-18-0	198.344	lf (al)	33	261	0.825^{30}		s EtOH, chl, lig; vs eth
10318	1-Tridecene		$C_{13}H_{26}$	2437-56-1	182.345	liq	-13	232.8	0.7658^{20}	1.4340^{20}	i H_2O; vs EtOH, eth; s bz
10319	Tridecyl acrylate		$C_{16}H_{30}O_2$	3076-04-8	254.408	liq		150^{10}	0.88^{20}		
10320	Tridecylaluminum		$C_{30}H_{63}Al$	1726-66-5	450.803	hyg visc liq	-38				
10321	Tridecylamine	*N,N*-Didecyl-1-decanamine	$C_{30}H_{63}N$	1070-01-5	437.828			406			
10322	(Tridecyl)amine	1-Tridecanamine	$C_{13}H_{29}N$	2869-34-3	199.376		27.4	275.8	0.8049^{20}	1.4443^{20}	sl H_2O; s EtOH, eth
10323	Tridecylbenzene	1-Phenyltridecane	$C_{19}H_{32}$	123-02-4	260.457		10	346	0.8550^{20}	1.4821^{20}	
10324	Tridecylcyclohexane		$C_{19}H_{38}$	6006-33-3	266.505		18.5	346	0.8239^{20}	1.4570^{20}	
10325	Tridecyl methacrylate		$C_{17}H_{32}O_2$	2495-25-2	268.435			118^{1}	0.881^{20}	1.448^{25}	
10326	Tri(decyl) phosphite		$C_{30}H_{63}O_3P$	2929-86-4	502.793	liq		255^{3}, 180$^{0.1}$			
10327	1-Tridecyne		$C_{13}H_{24}$	26186-02-7	180.330		2.5	234; 94^{25}	0.7842^{20}	1.4309^{20}	vs bz, eth
10328	Tridiphane	2-(3,5-Dichlorophenyl)-2-(2,2,2-trichloroethyl)oxirane, (±)	$C_{10}H_7Cl_5O$	58138-08-2	320.427		42.8				
10329	Tridodecylamine	*N,N*-Didodecyl-1-dodecanamine	$C_{36}H_{75}N$	102-87-4	521.988		16.4	220$^{0.03}$			
10330	Triethanolamine	Tris(2-hydroxyethyl)amine	$C_6H_{15}NO_3$	102-71-6	149.188	hyg cry	20.5	335.4	1.1242^{20}	1.4852^{20}	msc H_2O, EtOH; sl eth, bz; s chl
10331	1,3,5-Triethoxybenzene		$C_{12}H_{18}O_3$	2437-88-9	210.269	cry (al, dil al)	43.5	170^{24}			vs eth, EtOH
10332	Triethoxy(3-chloropropyl)silane	(3-Chloropropyl)triethoxysilane	$C_9H_{21}ClO_3Si$	5089-70-3	240.800	col gas		-149			



2,4,6-Trichloropyrimidine



3-(Trichlorosilyl)propanenitrile



2,4,6-Trichloro-1,3,5-triazine


2,2',2"-Trichlorotriethylamine



Trichlorotriethyldialuminum



1,3,5-Trichloro-2,4,6-trifluorobenzene



1,1,1-Trichloro-2,2,2-trifluoroethane



1,1,2-Trichloro-1,2,2-trifluoroethane



Trichlorovinylsilane



Trichodermin



Triclofos



Triclopyr



Tricosane



12-Tricosanone



Tri-*o*-cresyl phosphate



Tri-*m*-cresyl phosphate


Tri-*p*-cresyl phosphate



1,3,6-Tricyanohexane



Tricyclazole



Tricyclene



Tricyclo[3.3.1.1^{3,7}]decan-1-amine



Tricyclo[3.3.1.1^{3,7}]decane



Tridecanal



Tridecane



Tridecanedioic acid


Tridecanenitrile



Tridecanoic acid



1-Tridecanol



2-Tridecanone



7-Tridecanone



1-Tridecene



Tridecyl acrylate



Tridecylaluminum



Tridecylamine



(Tridecyl)amine



Tridecylbenzene



Tridecylcyclohexane



Tridecyl methacrylate



Tri(decyl) phosphite



1-Tridecyne


Tridiphane



Tridodecylamine



Triethanolamine



1,3,5-Triethoxybenzene



Triethoxy(3-chloropropyl)silane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10333	1,1,1-Triethoxyethane		$C_8H_{18}O_3$	78-39-7	162.227			145	0.8847^{25}	1.3980^{20}	i H_2O; msc EtOH, eth, ctc, chl
10334	Triethoxyethylsilane		$C_8H_{20}O_3Si$	78-07-9	192.329			158.5	0.8963^{20}	1.3955^{20}	i H_2O; msc EtOH, eth; s chl
10335	Triethoxymethane		$C_7H_{16}O_3$	122-51-0	148.200			143; 60^{20}	0.8909^{20}	1.3922^{20}	s EtOH, eth
10336	Triethoxymethylsilane		$C_7H_{18}O_3Si$	2031-67-6	178.302			142	0.8948^{25}	1.3832^{20}	
10337	Triethoxypentylsilane		$C_{11}H_{26}O_3Si$	2761-24-2	234.408			100^{30}, 95^{13}	0.8862^{20}	1.4059^{20}	
10338	Triethoxyphenylsilane		$C_{12}H_{20}O_3Si$	780-69-8	240.371			232; 113^{10}	0.996^{25}	1.4604^{20}	
10339	1,1,1-Triethoxypropane		$C_9H_{20}O_3$	115-80-0	176.253			171		1.4000^{25}	vs eth, EtOH
10340	Triethoxysilane		$C_6H_{16}O_3Si$	998-30-1	164.275			133.5	0.8745^{20}		
10341	3-(Triethoxysilyl)-1-propanamine		$C_9H_{23}NO_3Si$	919-30-2	221.370			119^{29}	0.9506^{20}	1.4225^{20}	
10342	3-(Triethoxysilyl)propanenitrile		$C_9H_{19}NO_3Si$	919-31-3	217.338	liq		109^{10}	0.974^{20}		
10343	Triethyl 2-acetoxy-1,2,3-propanetricarboxylate	Triethyl acetylcitrate	$C_{14}H_{22}O_8$	77-89-4	318.320			214^{40}	1.135^{25}	1.4380	
10344	Triethylaluminum	Hexaethyldialuminum	$C_6H_{15}Al$	97-93-8	114.165	col hyg liq	-46	194; 100^{13}	0.832^{25}		
10345	Triethylamine	*N,N*-Diethylethanamine	$C_6H_{15}N$	121-44-8	101.190	liq	-114.7	89	0.7275^{20}	1.4010^{20}	s H_2O, EtOH, eth, ctc; vs ace, bz, chl
10346	Triethylamine hydrochloride	*N,N*-Diethylethanamine hydrochloride	$C_6H_{16}ClN$	554-68-7	137.651	hex (al)	260 dec	sub 245	1.0689^{21}		vs H_2O, EtOH, chl
10347	Triethylarsine		$C_6H_{15}As$	617-75-4	162.105			138.5	1.150^{20}	1.467^{20}	vs ace, eth, EtOH
10348	1,2,3-Triethylbenzene		$C_{12}H_{18}$	42205-08-3	162.271	col liq	-26	172			
10349	1,2,4-Triethylbenzene		$C_{12}H_{18}$	877-44-1	162.271			218; 99^{15}	0.8738^{20}	1.5024^{20}	i H_2O; s EtOH, eth
10350	1,3,5-Triethylbenzene		$C_{12}H_{18}$	102-25-0	162.271	liq	-66.5	215.9	0.8631^{20}	1.4969^{20}	i H_2O; vs EtOH, eth
10351	Triethylborane		$C_6H_{15}B$	97-94-9	97.994	liq	-93	95	0.70^{23}	1.3971	s EtOH, eth
10352	Triethyl borate	Boric acid, triethyl ester	$C_6H_{15}BO_3$	150-46-9	145.992	liq	-84.8	120	0.8546^{20}	1.3749^{20}	msc EtOH, eth
10353	Triethyl citrate		$C_{12}H_{20}O_7$	77-93-0	276.283			294	1.1369^{20}	1.4455^{20}	i H_2O; s EtOH, eth; sl ctc
10354	Triethylenediamine		$C_6H_{12}N_2$	280-57-9	112.172		159				s chl
10355	Triethylene glycol	Triglycol	$C_6H_{14}O_4$	112-27-6	150.173	hyg liq	-7	285	1.1274^{15}	1.4531^{20}	msc H_2O, EtOH, bz; sl eth, chl; i peth
10356	Triethylene glycol bis(2-ethylhexanoate)		$C_{22}H_{42}O_6$	94-28-0	402.564						s chl
10357	Triethylene glycol diacetate		$C_{10}H_{18}O_6$	111-21-7	234.246	liq	-50	286	1.1153^{20}		vs H_2O, eth, EtOH
10358	Triethylene glycol dimethacrylate		$C_{14}H_{22}O_6$	109-16-0	286.321			170^{5}	1.092^{20}	1.4595^{25}	vs ace, eth, EtOH, peth
10359	Triethylene glycol dimethyl ether	Triglyme	$C_8H_{18}O_4$	112-49-2	178.227	liq	-45	216	0.986^{20}	1.4224^{20}	vs H_2O, bz
10360	Triethylene glycol dinitrate	Ethanol, 2,2'-[1,2-ethanediylbis(oxy)]bis-, dinitrate	$C_6H_{12}N_2O_8$	111-22-8	240.167			$82^{0.03}$			
10361	Triethylene glycol monoethyl ether	2-[2-(2-Ethoxyethoxy)ethoxy] ethanol	$C_8H_{18}O_4$	112-50-5	178.227			256	1.0209^{20}		
10362	Triethylenephosphoramide	Tris(1-aziridinyl)phosphine, oxide	$C_6H_{12}N_3OP$	545-55-1	173.152	cry	41	91^{23}			vs H_2O, EtOH, eth, ace
10363	Triethylenethiophosphoramide	Thiotepa	$C_6H_{12}N_3PS$	52-24-4	189.218	cry	51.5				vs H_2O; s bz, chl, eth, EtOH
10364	1,3,5-Triethylhexahydro-1,3,5-triazine		$C_9H_{21}N_3$	7779-27-3	171.283			78^{6}		1.4580^{25}	
10365	Triethyl phosphate	Ethyl phosphate	$C_6H_{15}O_4P$	78-40-0	182.154	liq	-56.4	215.5	1.0695^{20}	1.4053^{20}	s H_2O, eth, bz; vs EtOH; sl chl
10366	Triethylphosphine		$C_6H_{15}P$	554-70-1	118.157	liq	-88	129	0.8006^{19}	1.458^{15}	i H_2O; msc EtOH, eth
10367	Triethylphosphine oxide		$C_6H_{15}OP$	597-50-2	134.156	wh hyg nd	48	243			vs H_2O, eth, EtOH
10368	Triethylphosphine sulfide		$C_6H_{15}PS$	597-51-3	150.222	cry (al)	94				s H_2O; sl ctc
10369	Triethyl phosphite	Triethoxyphosphine	$C_6H_{15}O_3P$	122-52-1	166.155			157.9	0.9629^{20}	1.4127^{20}	i H_2O; vs EtOH, eth
10370	*O,O,O*-Triethyl phosphorothioate	*O,O,O*-Triethyl thiophosphate	$C_6H_{15}O_3PS$	126-68-1	198.220			217; 100^{16}	1.0768^{20}	1.4480^{20}	
10371	Triethylsilane		$C_6H_{16}Si$	617-86-7	116.277	liq	-156.9	109	0.7302^{20}	1.447^{20}	i H_2O, sulf
10372	Triethylsilanol		$C_6H_{16}OSi$	597-52-4	132.276			154	0.8647^{20}	1.4329^{20}	i H_2O; msc EtOH, eth
10373	Triethylstibine		$C_6H_{15}Sb$	617-85-6	208.943	liq	-98	161.4	1.3224^{15}		i H_2O; s EtOH, eth
10374	Trifenmorph	4-(Triphenylmethyl)morpholine	$C_{23}H_{23}NO$	1420-06-0	329.435	cry (EtOH)	176				i H_2O; s chl, ctc
10375	Triflumizole		$C_{15}H_{15}ClF_3N_3O$	68694-11-1	345.747		63.5				
10376	Trifluoperazine		$C_{21}H_{24}F_3N_3S$	117-89-5	407.496	cry		$206^{0.7}$			
10377	Trifluoperazine dihydrochloride	Stelazine	$C_{21}H_{26}Cl_2F_3N_3S$	440-17-5	480.417		241.5				



1,1,1-Triethoxyethane



Triethoxyethylsilane



Triethoxymethane



Triethoxymethylsilane



Triethoxypentylsilane



Triethoxyphenylsilane



1,1,1-Triethoxypropane



Triethoxysilane



3-(Triethoxysilyl)-1-propanamine



3-(Triethoxysilyl)propanenitrile



Triethyl 2-acetoxy-1,2,3-propanetricarboxylate



Triethylaluminum



Triethylamine



Triethylamine hydrochloride



Triethylarsine



1,2,3-Triethylbenzene



1,2,4-Triethylbenzene



1,3,5-Triethylbenzene



Triethylborane



Triethyl borate



Triethyl citrate



Triethylenediamine



Triethylene glycol



Triethylene glycol bis(2-ethylhexanoate)



Triethylene glycol diacetate



Triethylene glycol dimethacrylate



Triethylene glycol dimethyl ether



Triethylene glycol dinitrate



Triethylene glycol monoethyl ether


Triethylenephosphoramide


Triethylenethiophosphoramide



1,3,5-Triethylhexahydro-1,3,5-triazine



Triethyl phosphate


Triethylphosphine


Triethylphosphine oxide



Triethylphosphine sulfide



Triethyl phosphite



O,O,O-Triethyl phosphorothioate



Triethylsilane



Triethylsilanol


Triethylstibine



Trifenmorph



Triflumizole



Trifluoperazine


Trifluoperazine dihydrochloride


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10378	2,2,2-Trifluoroacetamide		$C_2H_2F_3NO$	354-38-1	113.038		73.8	162.5			
10379	Trifluoroacetic acid		$C_2HF_3O_2$	76-05-1	114.023	liq	-15.2	73	1.5351^{25}		s H_2O, EtOH, eth, ace
10380	Trifluoroacetic acid anhydride		$C_4F_6O_3$	407-25-0	210.031	liq	-65	39.5	1.490^{25}	1.269^{25}	
10381	1,1,1-Trifluoroacetone	Methyl trifluoromethyl ketone	$C_3H_3F_3O$	421-50-1	112.050	vol liq or gas		21.5	1.252^{25}		
10382	Trifluoroacetonitrile		C_2F_3N	353-85-5	95.023	col gas		-68.8			
10383	Trifluoroacetyl chloride		C_2ClF_3O	354-32-5	132.468	col gas	-146	-18			
10384	1,2,4-Trifluorobenzene		$C_6H_3F_3$	367-23-7	132.083			90	1.264^{25}	1.4171^{20}	
10385	1,3,5-Trifluorobenzene		$C_6H_3F_3$	372-38-3	132.083	liq	-5.5	75.5	1.277^{25}	1.4140^{20}	
10386	1,1,1-Trifluoroethane	Methyl fluoroform	$C_2H_3F_3$	420-46-2	84.040	col gas	-111.3	-47.25			s eth, chl
10387	1,1,2-Trifluoroethane		$C_2H_3F_3$	430-66-0	84.040	col gas	-84	3.7			
10388	2,2,2-Trifluoroethanol		$C_2H_3F_3O$	75-89-8	100.039	liq	-43.5	74	1.3842^{20}	1.2907^{22}	vs EtOH; s eth, ace, bz, chl
10389	Trifluoroethene	Trifluoroethylene	C_2HF_3	359-11-5	82.024	col gas		-51	1.26^{-70}		i H_2O; sl EtOH; s eth
10390	2,2,2-Trifluoroethylamine	2,2,2-Trifluoroethanamine	$C_2H_4F_3N$	753-90-2	99.055			36	1.245^{25}		
10391	2,2,2-Trifluoroethyl methyl ether		$C_3H_5F_3O$	460-43-5	114.066			31.62			
10392	1,1,1-Trifluoro-2-iodoethane		$C_2H_2F_3I$	353-83-3	209.936			54.5	2.13^{25}	1.4009^{20}	
10393	Trifluoroiodomethane		CF_3I	2314-97-8	195.910	col gas		-22.5	2.3607^{-32}	1.3790^{-32}	
10394	Trifluoroisocyanomethane	Trifluoromethyl isocyanide	C_2F_3N	19480-01-4	95.023	col gas		-80			
10395	Trifluoromethane	Fluoroform	CHF_3	75-46-7	70.014	col gas	-155.2	-82.1	0.673^{25} (p>1 atm)		s H_2O, ace, bz; vs EtOH; sl chl
10396	Trifluoromethanesulfenyl chloride		$CClF_3S$	421-17-0	136.524	col gas		-0.7			i H_2O
10397	Trifluoromethanesulfonic acid		CHF_3O_3S	1493-13-6	150.077	hyg liq	45	162			vs eth
10398	Trifluoromethanesulfonyl chloride		$CClF_3O_2S$	421-83-0	168.523			162; 62^{18}		1.3344^{20}	i H_2O
10399	Trifluoromethanesulfonyl fluoride		CF_4O_2S	335-05-7	152.069	col gas		-21.7			
10400	2-(Trifluoromethyl)aniline		$C_7H_6F_3N$	88-17-5	161.125		35.5	68^{15}	1.282^{25}	1.4810^{20}	
10401	3-(Trifluoromethyl)aniline		$C_7H_6F_3N$	98-16-8	161.125		5.5	187; 74^{10}	1.3047^{12}	1.4787^{20}	sl H_2O; s EtOH, eth
10402	4-(Trifluoromethyl)aniline		$C_7H_6F_3N$	455-14-1	161.125		38	117.5^{60}	1.283^{27}	1.4815^{25}	
10403	4-(Trifluoromethyl)benzaldehyde		$C_8H_5F_3O$	455-19-6	174.120			80^{25}		1.4630^{20}	
10404	(Trifluoromethyl)benzene	Benzotrifluoride	$C_7H_5F_3$	98-08-8	146.110	liq	-28.95	102.1	1.1884^{20}	1.4146^{20}	msc EtOH, eth, ace, bz, ctc
10405	3-(Trifluoromethyl)benzonitrile		$C_8H_4F_3N$	368-77-4	171.120		14.5	189	1.2813^{20}	1.4508^{20}	
10406	4-(Trifluoromethyl)benzonitrile		$C_8H_4F_3N$	455-18-5	171.120		37.5				
10407	3-(Trifluoromethyl)benzoyl chloride		$C_8H_4ClF_3O$	2251-65-2	208.565	oil		186; 80^{16}	1.383	1.4770^{20}	
10408	Trifluoromethyl difluoromethyl ether		C_2HF_5O	3822-68-2	136.020	col gas	-157	-38			
10409	2-(Trifluoromethyl)phenol		$C_7H_5F_3O$	444-30-4	162.109		45.5	147.5			
10410	3-(Trifluoromethyl)phenol		$C_7H_5F_3O$	98-17-9	162.109	liq	-0.9	178	1.3418^{25}		
10411	2-[[3-(Trifluoromethyl)phenyl] amino]benzoic acid	Flufenamic acid	$C_{14}H_{10}F_3NO_2$	530-78-9	281.230		133.5				s DMSO
10412	Trifluoromethylsilane		CH_3F_3Si	373-74-0	100.116	col gas	-73	-30			
10413	(Trifluoromethyl)silane		CH_3F_3Si	10112-11-5	100.116	col gas	-124	-38.3			
10414	Trifluoromethyl 1,1,2,2-tetrafluoroethyl ether		C_3HF_7O	2356-61-8	186.028	col gas	-141	-3			
10415	1,1,1-Trifluoro-2,4-pentanedione	1,1,1-Trifluoroacetylacetone	$C_5H_5F_3O_2$	367-57-7	154.088	liq		107			s os
10416	4,4,4-Trifluoro-1-phenyl-1,3-butanedione		$C_{10}H_7F_3O_2$	326-06-7	216.157	cry	39	224			i H_2O; s EtOH, ace
10417	2,2,2-Trifluoro-1-phenylethanone		$C_8H_5F_3O$	434-45-7	174.120	liq	-40	153	1.279^{20}	1.4583^{20}	
10418	Trifluorophenylsilane		$C_6H_5F_3Si$	368-47-8	162.185	liq	-18	101.5	1.2169^{20}	1.4110^{20}	vs bz, EtOH
10419	1,1,1-Trifluoropropane		$C_3H_5F_3$	421-07-8	98.067	col gas		-13			
10420	1,1,1-Trifluoro-2-propanol, (±)		$C_3H_5F_3O$	17556-48-8	114.066	liq	-52	78	1.2632^{25}	1.3130^{25}	vs EtOH, eth; s ace, bz; sl ctc
10421	3,3,3-Trifluoropropene		$C_3H_3F_3$	677-21-4	96.051	col gas		-17			
10422	3,3,3-Trifluoro-1-propyne	(Trifluoromethyl)acetylene	C_3HF_3	661-54-1	94.035	col gas		-48.3			
10423	4,4,4-Trifluoro-1-(2-thienyl)-1,3-butanedione	Thenoyltrifluoroacetone	$C_8H_5F_3O_2S$	326-91-0	222.185		42.8	97^{8}			
10424	Trifluoro(trifluoromethyl)oxirane	Perfluoropropylene oxide	C_3F_6O	428-59-1	166.021	gas		-27.4			
10425	Triflupromazine	Fluopromazine	$C_{18}H_{19}F_3N_2S$	146-54-3	352.417	visc oil		176$^{0.7}$		1.5780^{23}	
10426	Trifluralin	2,6-Dinitro-*N,N*-dipropyl-4-(trifluoromethyl)aniline	$C_{13}H_{16}F_3N_3O_4$	1582-09-8	335.279		49	140$^{4.2}$			
10427	Triforine		$C_{10}H_{14}Cl_6N_4O_2$	26644-46-2	434.962		155 dec				
10428	Trigonelline		$C_7H_7NO_2$	535-83-1	137.137	pr (aq, al, +1w)					vs H_2O
10429	Trihexylamine	*N,N*-Dihexyl-1-hexanamine	$C_{18}H_{39}N$	102-86-3	269.510			261.7	0.7976^{21}		i H_2O; vs EtOH, eth; s acid
10430	Trihexyl borate		$C_{18}H_{39}BO_3$	5337-36-0	314.312			143^{2}			sl ctc



2,2,2-Trifluoroacetamide



Trifluoroacetic acid



Trifluoroacetic acid anhydride


1,1,1-Trifluoroacetone


Trifluoroacetonitrile



Trifluoroacetyl chloride


1,2,4-Trifluorobenzene



1,3,5-Trifluorobenzene



1,1,1-Trifluoroethane


1,1,2-Trifluoroethane


2,2,2-Trifluoroethanol


Trifluoroethene


2,2,2-Trifluoroethylamine


2,2,2-Trifluoroethyl methyl ether



1,1,1-Trifluoro-2-iodoethane


Trifluoroiodomethane


Trifluoroisocyanomethane



Trifluoromethane



Trifluoromethanesulfenyl chloride



Trifluoromethanesulfonic acid



Trifluoromethanesulfonyl chloride



Trifluoromethanesulfonyl fluoride



2-(Trifluoromethyl)aniline



3-(Trifluoromethyl)aniline



4-(Trifluoromethyl)aniline



4-(Trifluoromethyl)benzaldehyde



(Trifluoromethyl)benzene



3-(Trifluoromethyl)benzonitrile



4-(Trifluoromethyl)benzonitrile


3-(Trifluoromethyl)benzoyl chloride



Trifluoromethyl difluoromethyl ether



2-(Trifluoromethyl)phenol



3-(Trifluoromethyl)phenol



2-[[3-(Trifluoromethyl)phenyl]amino]benzoic acid



Trifluoromethylsilane



(Trifluoromethyl)silane


Trifluoromethyl 1,1,2,2-tetrafluoroethyl ether


1,1,1-Trifluoro-2,4-pentanedione


4,4,4-Trifluoro-1-phenyl-1,3-butanedione


2,2,2-Trifluoro-1-phenylethanone



Trifluorophenylsilane



1,1,1-Trifluoropropane



1,1,1-Trifluoro-2-propanol, (±)



3,3,3-Trifluoropropene



3,3,3-Trifluoro-1-propyne



4,4,4-Trifluoro-1-(2-thienyl)-1,3-butanedione



Trifluoro(trifluoromethyl)oxirane



Triflupromazine


Trifluralin



Triforine



Trigonelline



Trihexylamine



Trihexyl borate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10431	Trihexyphenidyl hydrochloride	α-Cyclohexyl-α-phenyl-1-piperidinepropanol hydrochloride	$C_{20}H_{32}ClNO$	52-49-3	337.927		258.5				
10432	Trihydro(pyridine)boron	Borane pyridine	C_5H_8BN	110-51-0	92.936		10.5		0.920^{20}	1.5280^{25}	i H_2O; dec acid
10433	1,2,3-Trihydroxy-9,10-anthracenedione	Anthragallol	$C_{14}H_8O_5$	602-64-2	256.211	ye nd (dil al)	313	sub 290			sl H_2O; s EtOH, eth, HOAc, CS_2
10434	1,2,4-Trihydroxy-9,10-anthracenedione	Purpurin	$C_{14}H_8O_5$	81-54-9	256.211	oran red or oran-ye nd (al)	259	sub			sl H_2O; vs EtOH, bz, HOAc; s eth
10435	2,3,4-Trihydroxybenzoic acid		$C_7H_6O_5$	610-02-6	170.120	nd (+w)	221	sub			sl H_2O; s EtOH, eth, ace; i bz, CS_2
10436	2,4,6-Trihydroxybenzoic acid		$C_7H_6O_5$	83-30-7	170.120	cry (w+1)	100 dec				sl H_2O; s EtOH; vs eth; i bz
10437	3,4,5-Trihydroxybenzoic acid	Gallic acid	$C_7H_6O_5$	149-91-7	170.120	pr (w+1)	253 dec		1.694^{6}		sl H_2O, eth; vs EtOH; s ace; i bz, chl
10438	2,3,4-Trihydroxybenzophenone	Alizarin Yellow A	$C_{13}H_{10}O_4$	1143-72-2	230.216	ye nd (dil al)	140.5				sl H_2O, bz; s EtOH, eth, ace, HOAc
10439	2',4,4'-Trihydroxychalcone	Isoliquiritigenin	$C_{15}H_{12}O_4$	961-29-5	256.254	ye nd (EtOH-w)	200				
10440	9,10,16-Trihydroxyhexadecanoic acid	Aleuritic acid	$C_{16}H_{32}O_5$	6949-98-0	304.422	lf (dil al), nd (w)	102				sl H_2O
10441	1,3,8-Trihydroxy-6-methyl-9,10-anthracenedione	Emodin	$C_{15}H_{10}O_5$	518-82-1	270.237	oran-red mcl nd (HOAc)	257	sub			vs eth, EtOH
10442	9,10,18-Trihydroxyoctadecanoic acid, (*R**,*R**)	Phloionolic acid	$C_{18}H_{36}O_5$	583-86-8	332.476	cry (dil al)	101.5				
10443	5,6,7-Trihydroxy-2-phenyl-4*H*-1-benzopyran-4-one	Baicalein	$C_{15}H_{10}O_5$	491-67-8	270.237	ye pr (al)	264 dec				sl H_2O, bz; s EtOH, eth, ace, HOAc
10444	1-(2,4,5-Trihydroxyphenyl)-1-butanone		$C_{10}H_{12}O_4$	1421-63-2	196.200		153.8				
10445	1-(2,3,4-Trihydroxyphenyl) ethanone	Gallacetophenone	$C_8H_8O_4$	528-21-2	168.148		173				s H_2O, eth; vs EtOH, ace; sl bz, chl
10446	1-(2,4,6-Trihydroxyphenyl) ethanone	2',4',6'-Trihydroxyacetophenone	$C_8H_8O_4$	480-66-0	168.148		221.0				sl H_2O, chl, bz; vs EtOH, eth, ace
10447	1-(2,4,6-Trihydroxyphenyl)-1-propanone	Flopropione	$C_9H_{10}O_4$	2295-58-1	182.173	nd (w, +1w)	175.5				vs eth, EtOH
10448	2,6,7-Trihydroxy-9-phenyl-3*H*-xanthen-3-one	Phenylfluorone	$C_{19}H_{12}O_5$	975-17-7	320.295	oran red (al-HCl)	>300				
10449	2,3,5-Triiodobenzoic acid		$C_7H_3I_3O_2$	88-82-4	499.811	pr (al)	225				i H_2O; vs EtOH, eth; sl bz
10450	Triiodomethane	Iodoform	CHI_3	75-47-8	393.732	ye cry	121.2	218	4.008^{25}		i H_2O, bz; s EtOH, eth, ace; sl DMSO
10451	2,4,6-Triiodophenol		$C_6H_3I_3O$	609-23-4	471.800	nd (dil al)	159.8	sub			i H_2O; sl EtOH; s eth, ace
10452	3,3',5-Triiodothyropropanoic acid		$C_{15}H_{11}I_3O_4$	51-26-3	635.959	cry (EtOH)	200				sl EtOH
10453	Triisobutyl aluminate	2-Methyl-1-propanol, aluminum salt	$C_{12}H_{27}AlO_3$	3453-79-0	246.322			275^{50}			
10454	Triisobutylaluminum		$C_{12}H_{27}Al$	100-99-2	198.324	liq	6	86^{10}			
10455	Triisobutylamine	2-Methyl-*N*,*N*-bis(2-methylpropyl)-1-propanamine	$C_{12}H_{27}N$	1116-40-1	185.349	liq	-21.8	191.5	0.7684^{20}	1.4252^{17}	vs eth, EtOH
10456	Triisobutylborane		$C_{12}H_{27}B$	1116-39-8	182.153			188; 86^{20}	0.7380^{25}	1.4188^{23}	vs bz, eth, EtOH
10457	Triisobutyl phosphate		$C_{12}H_{27}O_4P$	126-71-6	266.313			264	0.9681^{20}	1.4193^{20}	vs H_2O, bz, eth, EtOH
10458	Triisopentylamine	3-Methyl-*N*,*N*-bis(3-methylbutyl)-1-butanamine	$C_{15}H_{33}N$	645-41-0	227.430			235	0.7848^{20}	1.4331^{20}	i H_2O; vs EtOH; msc eth, bz, ctc
10459	Triisopropanolamine		$C_9H_{21}NO_3$	122-20-3	191.268		45	175^{10}	1.0^{20}		s H_2O, EtOH; sl chl
10460	Triisopropoxymethane	Isopropyl orthoformate	$C_{10}H_{22}O_3$	4447-60-3	190.280			167	0.8621^{20}	1.4000^{20}	vs eth, EtOH
10461	Triisopropoxyvinylsilane		$C_{11}H_{24}O_3Si$	18023-33-1	232.393			179.5; 77^{20}	0.8627^{25}	1.3981^{20}	s ctc
10462	1,2,4-Triisopropylbenzene		$C_{15}H_{24}$	948-32-3	204.352			244	0.8574^{25}	1.4896^{25}	
10463	1,3,5-Triisopropylbenzene		$C_{15}H_{24}$	717-74-8	204.352	liq	-7.4	238	0.8545^{20}	1.4882^{20}	s ace, bz, chl
10464	Triisopropyl borate		$C_9H_{21}BO_3$	5419-55-6	188.072			140; 75^{76}	0.8251^{20}	1.3777^{20}	vs EtOH, eth, bz, PrOH
10465	Triisopropyl phosphate		$C_9H_{21}O_4P$	513-02-0	224.234			219	0.9867^{20}	1.4057^{20}	vs EtOH
10466	Triisopropyl phosphite		$C_9H_{21}O_3P$	116-17-6	208.235			74^{20}, 60^{10}	0.9063^{20}	1.4085^{25}	s EtOH, eth, chl
10467	Triisopropyl vanadate	Vanadium, oxotris(2-propanolato)-, (T-4)-	$C_9H_{21}O_4V$	5588-84-1	244.203			104^{10}			



Trihexyphenidyl hydrochloride



Trihydro(pyridine)boron



1,2,3-Trihydroxy-9,10-anthracenedione



1,2,4-Trihydroxy-9,10-anthracenedione



2,3,4-Trihydroxybenzoic acid



2,4,6-Trihydroxybenzoic acid



3,4,5-Trihydroxybenzoic acid



2,3,4-Trihydroxybenzophenone



2',4,4'-Trihydroxychalcone



9,10,16-Trihydroxyhexadecanoic acid



1,3,8-Trihydroxy-6-methyl-9,10-anthracenedione



9,10,18-Trihydroxyoctadecanoic acid, (*R**,*R**)



5,6,7-Trihydroxy-2-phenyl-4*H*-1-benzopyran-4-one



1-(2,4,5-Trihydroxyphenyl)-1-butanone


1-(2,3,4-Trihydroxyphenyl)ethanone



1-(2,4,6-Trihydroxyphenyl)ethanone



1-(2,4,6-Trihydroxyphenyl)-1-propanone



2,6,7-Trihydroxy-9-phenyl-3*H*-xanthen-3-one



2,3,5-Triiodobenzoic acid



Triiodomethane



2,4,6-Triiodophenol



3,3',5-Triiodothyropropanoic acid



Triisobutyl aluminate



Triisobutylaluminum



Triisobutylamine



Triisobutylborane



Triisobutyl phosphate



Triisopentylamine



Triisopropanolamine



Triisopropoxymethane



Triisopropoxyvinylsilane



1,2,4-Triisopropylbenzene


1,3,5-Triisopropylbenzene



Triisopropyl borate



Triisopropyl phosphate



Triisopropyl phosphite



Triisopropyl vanadate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10468	Trimecaine	2-Diethylamino-2',4',6'-trimethylacetanilide	$C_{15}H_{24}N_2O$	616-68-2	248.364	cry	44	187^{6}			
10469	Trimellitic anhydride		$C_9H_4O_5$	552-30-7	192.125		162	241^{14}			
10470	Trimeprazine	*N,N*,β-Trimethyl-10*H*-phenothiazine-10-propanamine	$C_{18}H_{22}N_2S$	84-96-8	298.446	cry	68	$162^{0.3}$			
10471	Trimethoate		$C_9H_{20}NO_3PS_2$	2275-18-5	285.364	solid	28.5	$135^{0.1}$			sl H_2O
10472	Trimethobenzamide hydrochloride		$C_{21}H_{29}ClN_2O_5$	554-92-7	424.918	cry	188				vs H_2O
10473	Trimethoprim		$C_{14}H_{18}N_4O_3$	738-70-5	290.318	ye cry	201				sl chl, MeOH; i eth, bz
10474	3,4,5-Trimethoxyaniline		$C_9H_{13}NO_3$	24313-88-0	183.204		112.8				
10475	2,3,4-Trimethoxybenzaldehyde		$C_{10}H_{12}O_4$	2103-57-3	196.200			$122^{0.5}$		1.5547^{20}	
10476	2,4,5-Trimethoxybenzaldehyde		$C_{10}H_{12}O_4$	4460-86-0	196.200		114				s H_2O, eth, chl, lig
10477	3,4,5-Trimethoxybenzaldehyde		$C_{10}H_{12}O_4$	86-81-7	196.200		72.5	148^{5}			s chl
10478	1,2,3-Trimethoxybenzene		$C_9H_{12}O_3$	634-36-6	168.189	orth nd (al)	48.5	235	1.1009^{45}		i H_2O; s EtOH, eth, bz
10479	1,3,5-Trimethoxybenzene		$C_9H_{12}O_3$	621-23-8	168.189	pr (al), lf (peth)	54.5	255.5			i H_2O; s EtOH, eth, bz
10480	3,4,5-Trimethoxybenzeneethanamine	Mescaline	$C_{11}H_{17}NO_3$	54-04-6	211.258	cry	35.5	180^{12}			s H_2O, EtOH, bz, chl; i eth, peth
10481	3,4,5-Trimethoxybenzenemethanol	3,4,5-Trimethoxybenzyl alcohol	$C_{10}H_{14}O_4$	3840-31-1	198.216		3	228^{25}	1.1427^{20}	1.5439^{20}	
10482	2,4,5-Trimethoxybenzoic acid		$C_{10}H_{12}O_5$	490-64-2	212.199	nd (al or bz-peth)	145	300			vs H_2O, bz, EtOH, peth
10483	3,4,5-Trimethoxybenzoic acid		$C_{10}H_{12}O_5$	118-41-2	212.199	mcl nd (w)	172.3	226^{10}			sl H_2O; vs EtOH, eth, chl
10484	3,4,5-Trimethoxybenzoyl chloride		$C_{10}H_{11}ClO_4$	4521-61-3	230.645		82	185^{18}			
10485	Trimethoxyboroxin		$C_3H_9B_3O_6$	102-24-9	173.532					1.40^{25}	
10486	6,6',7-Trimethoxy-2,2'-dimethylberbaman-12-ol	Berbamine	$C_{37}H_{40}N_2O_6$	478-61-5	608.723	lf (+2w, al) cry (peth)	198.5				sl H_2O; s EtOH, eth, chl, peth
10487	6,6',7-Trimethoxy-2,2'-dimethyloxyacanthan-12'-ol	Oxyacanthine	$C_{37}H_{40}N_2O_6$	548-40-3	608.723	nd (al, eth)	216.5				i H_2O; s EtOH, eth, bz, chl; i lig
10488	7',10,11-Trimethoxyemetan-6'-ol	Cephaeline	$C_{28}H_{38}N_2O_4$	483-17-0	466.613	nd (eth)	115.5				vs ace, EtOH, MeOH, chl
10489	1,1,1-Trimethoxyethane		$C_5H_{12}O_3$	1445-45-0	120.147			108	0.9438^{25}	1.3859^{25}	vs eth, EtOH
10490	4,7,8-Trimethoxyfuro[2,3-b] quinoline	Skimmianine	$C_{14}H_{13}NO_4$	83-95-4	259.258	pym (al)	177				i H_2O, peth; s EtOH, chl; sl eth, CS_2
10491	Trimethoxymethane		$C_4H_{10}O_3$	149-73-5	106.120		15	104	0.9676^{20}	1.3793^{20}	s EtOH, eth
10492	Trimethoxymethylsilane		$C_4H_{12}O_3Si$	1185-55-3	136.222			102.5	0.9548^{20}	1.3696^{20}	s chl
10493	Trimethoxyphenylsilane		$C_9H_{14}O_3Si$	2996-92-1	198.291			130^{45}, 110^{20}	1.064^{20}	1.4734^{20}	s ctc, CS_2
10494	Trimethoxysilane		$C_3H_{10}O_3Si$	2487-90-3	122.195			32^{100}			
10495	3-(Trimethoxysilyl)-1-propanethiol	(3-Mercaptopropyl) trimethoxysilane	$C_6H_{16}O_3SSi$	4420-74-0	196.340			128^{50}, 93^{10}	1.015^{25}	1.4420^{25}	
10496	*N*-[3-(Trimethoxysilyl)propyl]-1,2-ethanediamine		$C_8H_{22}N_2O_3Si$	1760-24-3	222.358			140.5^{15}	1.01^{25}	1.4416^{25}	
10497	3-(Trimethoxysilyl)propyl methacrylate		$C_{10}H_{20}O_5Si$	2530-85-0	248.349	liq		107^{5}, 95^{1}			
10498	Trimethyl aluminum		C_3H_9Al	75-24-1	72.085		15.4	130; 20^{8}	0.752^{20}		
10499	Trimethylamine	*N,N*-Dimethylmethanamine	C_3H_9N	75-50-3	59.110	col gas	-117.1	2.87	0.627^{25} (p>1 atm)	1.3631^{0}	vs H_2O, chl, tol; s EtOH, eth, bz
10500	Trimethylamine borane	*N,N*-Dimethylmethanamine borane	$C_3H_{12}BN$	75-22-9	72.945		94	172	0.792^{25}		vs eth, EtOH
10501	Trimethylamine hydrochloride	*N,N*-Dimethylmethanamine hydrochloride	$C_3H_{10}ClN$	593-81-7	95.571	mcl hyg nd (al)	277.5	sub 200			vs H_2O, EtOH, chl
10502	Trimethylamine oxide	*N,N*-Dimethylmethanamine oxide	C_3H_9NO	1184-78-7	75.109	hyg nd (w+2)	256				vs H_2O, EtOH
10503	2,4,5-Trimethylaniline		$C_9H_{13}N$	137-17-7	135.206	nd (w)	68	234.5	0.957^{25}		vs EtOH
10504	2,4,6-Trimethylaniline	Mesitylamine	$C_9H_{13}N$	88-05-1	135.206	liq	-2.5	232.5	0.9633^{25}	1.5495^{20}	sl ctc
10505	Trimethylarsine		C_3H_9As	593-88-4	120.025	liq	-87.3	52	1.144^{15}		vs bz, eth, EtOH
10506	2,4,6-Trimethylbenzaldehyde		$C_{10}H_{12}O$	487-68-3	148.201		14	238.5	1.0154^{25}		i H_2O; s EtOH, eth, ace, bz
10507	1,2,3-Trimethylbenzene	Hemimellitene	C_9H_{12}	526-73-8	120.191	liq	-25.4	176.12	0.8944^{20}	1.5139^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
10508	1,2,4-Trimethylbenzene	Pseudocumene	C_9H_{12}	95-63-6	120.191	liq	-43.77	169.38	0.8758^{20}	1.5048^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
10509	1,3,5-Trimethylbenzene	Mesitylene	C_9H_{12}	108-67-8	120.191	liq	-44.72	164.74	0.8615^{25}	1.4994^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
10510	2,3,5-Trimethyl-1,4-benzenediol		$C_9H_{12}O_2$	700-13-0	152.190	nd (w)	169 dec				sl H_2O; vs EtOH, eth, bz



Trimecaine



Trimellitic anhydride



Trimeprazine



Trimethoate



Trimethobenzamide hydrochloride



Trimethoprim



3,4,5-Trimethoxyaniline



2,3,4-Trimethoxybenzaldehyde



2,4,5-Trimethoxybenzaldehyde



3,4,5-Trimethoxybenzaldehyde



1,2,3-Trimethoxybenzene



1,3,5-Trimethoxybenzene



3,4,5-Trimethoxybenzeneethanamine



3,4,5-Trimethoxybenzenemethanol



2,4,5-Trimethoxybenzoic acid



3,4,5-Trimethoxybenzoic acid



3,4,5-Trimethoxybenzoyl chloride



Trimethoxyboroxin



6,6',7-Trimethoxy-2,2'-dimethylberbaman-12-ol



6,6',7-Trimethoxy-2,2'-dimethyloxyacanthan-12'-ol



7',10,11-Trimethoxyemetan-6'-ol



1,1,1-Trimethoxyethane



4,7,8-Trimethoxyfuro[2,3-b]quinoline



Trimethoxymethane



Trimethoxymethylsilane


Trimethoxyphenylsilane


Trimethoxysilane


3-(Trimethoxysilyl)-1-propanethiol



N-[3-(Trimethoxysilyl)propyl]-1,2-ethanediamine


3-(Trimethoxysilyl)propyl methacrylate



Trimethyl aluminum



Trimethylamine


Trimethylamine borane



Trimethylamine hydrochloride


Trimethylamine oxide



2,4,5-Trimethylaniline



2,4,6-Trimethylaniline



Trimethylarsine


2,4,6-Trimethylbenzaldehyde



1,2,3-Trimethylbenzene



1,2,4-Trimethylbenzene



1,3,5-Trimethylbenzene



2,3,5-Trimethyl-1,4-benzenediol


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10511	*N*,α,α-Trimethylbenzeneethanamine	Mephentermine	$C_{11}H_{17}N$	100-92-5	163.260	liq		95^{9}			i H_2O; s eth; vs EtOH
10512	Trimethyl 1,2,4-benzenetricarboxylate	Trimethyl trimellitate	$C_{12}H_{12}O_6$	2459-10-1	252.219	visc oil	-13	194^{12}	1.261	1.5230^{20}	
10513	2,4,6-Trimethylbenzoic acid		$C_{10}H_{12}O_2$	480-63-7	164.201	pr (lig)	156.5				sl H_2O; s EtOH, eth, ace, chl
10514	Trimethylbenzylsilane		$C_{10}H_{16}Si$	770-09-2	164.320			190.5	0.8933^{20}	1.4941^{20}	
10515	1,7,7-Trimethylbicyclo[2.2.1] heptane		$C_{10}H_{18}$	464-15-3	138.250	hex pl(al), pr(MeOH)		161			i H_2O; s EtOH, eth, AcOEt, MeOH
10516	1,3,3-Trimethylbicyclo[2.2.1] heptan-2-ol, (1*S*-*endo*)	α-Fenchyl alcohol, (*l*)	$C_{10}H_{18}O$	512-13-0	154.249	pr	48	94^{20}	0.9034^{84}		
10517	1,7,7-Trimethylbicyclo[2.2.1] heptan-2-ol acetate, *endo*	Bornyl acetate	$C_{12}H_{20}O_2$	76-49-3	196.286		29	221			
10518	1,7,7-Trimethylbicyclo[2.2.1]hept-2-ene		$C_{10}H_{16}$	464-17-5	136.234	cry (al)	113	146			vs bz, eth, EtOH
10519	4,6,6-Trimethylbicyclo[3.1.1]hept-3-en-2-ol, (1α,2α,5α)		$C_{10}H_{16}O$	1820-09-3	152.233		24	92^{10}	0.9657^{25}	1.4908^{25}	
10520	4,6,6-Trimethylbicyclo[3.1.1]hept-3-en-2-ol, (1α,2β,5α)		$C_{10}H_{16}O$	1845-30-3	152.233		15.5	90^{10}	0.9684^{25}	1.4912^{25}	
10521	2,7,7-Trimethylbicyclo[3.1.1]hept-2-en-6-one	Chrysanthenone	$C_{10}H_{14}O$	473-06-3	150.217			88^{12}		1.4720^{22}	vs EtOH
10522	Trimethylborane		C_3H_9B	593-90-8	55.914	col gas	-161.5	-20.2			
10523	Trimethyl borate		$C_3H_9BO_3$	121-43-7	103.912	liq	-29.3	67.5	0.915^{25}	1.3568^{20}	vs eth, MeOH
10524	2,2,3-Trimethylbutane	Triptane	C_7H_{16}	464-06-2	100.202	liq	-24.6	80.86	0.6901^{20}	1.3864^{20}	i H_2O; s EtOH, eth; vs ace, bz, peth, ctc
10525	2,3,3-Trimethyl-2-butanol		$C_7H_{16}O$	594-83-2	116.201	cry (dil al +1/2w)	17	131	0.8380^{25}	1.4233^{22}	sl H_2O; vs ace, eth, EtOH
10526	2,3,3-Trimethyl-1-butene		C_7H_{14}	594-56-9	98.186	liq	-109.9	77.9	0.7050^{20}	1.4025^{20}	i H_2O; s eth, bz, chl, MeOH
10527	Trimethylchlorosilane		C_3H_9ClSi	75-77-4	108.642	liq	-40	60	0.856^{25}	1.3870^{20}	
10528	Trimethyl citrate		$C_9H_{14}O_7$	1587-20-8	234.203	tcl	79.3	285; 176^{16}			vs eth, EtOH
10529	2,6,6-Trimethyl-2,4-cycloheptadien-1-one	Eucarvone	$C_{10}H_{14}O$	503-93-5	150.217			210; 105^{22}	0.9490^{20}	1.5087^{20}	s eth, ace
10530	1,1,2-Trimethylcyclohexane		C_9H_{18}	7094-26-0	126.239	liq	-29	145.2	0.7963^{25}	1.4382^{20}	
10531	1,1,3-Trimethylcyclohexane		C_9H_{18}	3073-66-3	126.239	liq	-65.7	136.6	0.7749^{25}	1.4295^{20}	i H_2O
10532	1α,2β,4β-1,2,4-Trimethylcyclohexane		C_9H_{18}	7667-60-9	126.239	liq	-83.5	142.9	0.7870^{25}	1.4341^{20}	
10533	1α,3α,5β-1,3,5-Trimethylcyclohexane	*trans*-1,3,5-Trimethylcyclohexane	C_9H_{18}	1795-26-2	126.239	liq	-107.4	140.5	0.7794^{20}	1.4307^{20}	vs bz, eth, lig
10534	*cis*-3,3,5-Trimethylcyclohexanol		$C_9H_{18}O$	933-48-2	142.238		37.3	202; 92^{12}	0.9006^{16}	1.4550^{16}	i H_2O; s EtOH, eth, chl
10535	*trans*-3,3,5-Trimethylcyclohexanol		$C_9H_{18}O$	767-54-4	142.238	cry (eth)	55.8	189.2	0.8631^{60}		i H_2O; s EtOH, eth, chl
10536	2,2,6-Trimethylcyclohexanone		$C_9H_{16}O$	2408-37-9	140.222	liq	-31.8	178.5	0.9043^{18}	1.4470^{20}	
10537	2,4,4-Trimethylcyclohexanone		$C_9H_{16}O$	2230-70-8	140.222			191	0.902^{20}	1.4493^{20}	
10538	3,3,5-Trimethylcyclohexanone	Dihydroisophorone	$C_9H_{16}O$	873-94-9	140.222	ye oil		189	0.8919^{19}	1.4454^{15}	
10539	2,6,6-Trimethyl-1-cyclohexene-1-carboxaldehyde	β-Cyclocitral	$C_{10}H_{16}O$	432-25-7	152.233			112^{29}, 97^{15}	0.959^{15}	1.4971^{15}	
10540	3,5,5-Trimethyl-2-cyclohexen-1-ol	Isophorol	$C_9H_{16}O$	470-99-5	140.222			69^{5}	0.914^{20}	1.4717^{20}	
10541	4-(2,6,6-Trimethyl-1-cyclohexen-1-yl)-3-buten-2-ol	β-Ionol	$C_{13}H_{22}O$	22029-76-1	194.313			130^{14}	0.9243^{20}	1.4969^{20}	s EtOH, eth, ace
10542	4-(2,6,6-Trimethyl-2-cyclohexen-1-yl)-3-buten-2-ol	α-Ionol	$C_{13}H_{22}O$	25312-34-9	194.313	oil		127^{14}	0.9189^{20}	1.4735^{20}	
10543	1,1,2-Trimethylcyclopentane		C_8H_{16}	4259-00-1	112.213	liq	-21.6	114; 53^{100}	0.7660^{20}	1.4199^{20}	
10544	1,1,3-Trimethylcyclopentane		C_8H_{16}	4516-69-2	112.213	liq	-142.4	104.9	0.7439^{25}	1.4112^{20}	i H_2O
10545	1α,2α,4β-1,2,4-Trimethylcyclopentane		C_8H_{16}	4850-28-6	112.213	liq	-132.6	116.7	0.7592^{25}	1.4186^{20}	
10546	1α,2β,4α-1,2,4-Trimethylcyclopentane		C_8H_{16}	16883-48-0	112.213	liq	-130.8	109.3	0.7430^{25}	1.4106^{20}	
10547	1,2,2-Trimethyl-1,3-cyclopentanedicarboxylic acid, (1*R*, 3*S*)	(+)-Camphoric acid	$C_{10}H_{16}O_4$	124-83-4	200.232	pr, lf (w)	187		1.186^{20}		sl H_2O; vs EtOH, eth; s ace; i bz, chl
10548	2,2,4-Trimethylcyclopentanone		$C_8H_{14}O$	28056-54-4	126.196	liq	-40.6	158	0.877^{25}	1.4300^{20}	
10549	2,4,4-Trimethylcyclopentanone		$C_8H_{14}O$	4694-12-6	126.196	liq	-25.6	160.5	0.8785^{18}	1.433^{18}	
10550	1,1,2-Trimethylcyclopropane		C_6H_{12}	4127-45-1	84.159	liq	-138.2	54	0.6897^{25}	1.3864^{20}	
10551	3,7,11-Trimethyl-2,6,10-dodecatrienal		$C_{15}H_{24}O$	19317-11-4	220.351			172^{14}	0.893^{18}	1.4995	
10552	Trimethylgallium		C_3H_9Ga	1445-79-0	114.826			55.7			dec H_2O (exp)
10553	2,2,6-Trimethylheptane		$C_{10}H_{22}$	1190-83-6	142.282	liq	-105	148.9	0.7200^{25}	1.4078^{20}	
10554	2,5,5-Trimethylheptane		$C_{10}H_{22}$	1189-99-7	142.282			152.8	0.7362^{25}	1.4149^{20}	
10555	3,3,5-Trimethylheptane		$C_{10}H_{22}$	7154-80-5	142.282			155.7	0.7248^{20}	1.4170^{20}	i H_2O; s bz, ctc, chl



N,α,α-Trimethylbenzeneethanamine



Trimethyl 1,2,4-benzenetricarboxylate



2,4,6-Trimethylbenzoic acid



Trimethylbenzylsilane



1,7,7-Trimethylbicyclo[2.2.1]heptane


1,3,3-Trimethylbicyclo[2.2.1]heptan-2-ol, (1*S*-*endo*)


1,7,7-Trimethylbicyclo[2.2.1]heptan-2-ol acetate, *endo*



1,7,7-Trimethylbicyclo[2.2.1]hept-2-ene


4,6,6-Trimethylbicyclo[3.1.1]hept-3-en-2-ol, (1α,2α,5α)


4,6,6-Trimethylbicyclo[3.1.1]hept-3-en-2-ol, (1α,2β,5α)


2,7,7-Trimethylbicyclo[3.1.1]hept-2-en-6-one


Trimethylborane



Trimethyl borate



2,2,3-Trimethylbutane



2,3,3-Trimethyl-2-butanol



2,3,3-Trimethyl-1-butene



Trimethylchlorosilane



Trimethyl citrate



2,6,6-Trimethyl-2,4-cycloheptadien-1-one



1,1,2-Trimethylcyclohexane



1,1,3-Trimethylcyclohexane



1α,2β,4β-1,2,4-Trimethylcyclohexane



1α,3α,5β-1,3,5-Trimethylcyclohexane



cis-3,3,5-Trimethylcyclohexanol



trans-3,3,5-Trimethylcyclohexanol



2,2,6-Trimethylcyclohexanone



2,4,4-Trimethylcyclohexanone


3,3,5-Trimethylcyclohexanone


2,6,6-Trimethyl-1-cyclohexene-1-carboxaldehyde



3,5,5-Trimethyl-2-cyclohexen-1-ol



4-(2,6,6-Trimethyl-1-cyclohexen-1-yl)-3-buten-2-ol



4-(2,6,6-Trimethyl-2-cyclohexen-1-yl)-3-buten-2-ol



1,1,2-Trimethylcyclopentane



1,1,3-Trimethylcyclopentane


1α,2α,4β-1,2,4-Trimethylcyclopentane



1α,2β,4α-1,2,4-Trimethylcyclopentane


1,2,2-Trimethyl-1,3-cyclopentanedicarboxylic acid, (1*R*, 3*S*)



2,2,4-Trimethylcyclopentanone



2,4,4-Trimethylcyclopentanone



1,1,2-Trimethylcyclopropane


3,7,11-Trimethyl-2,6,10-dodecatrienal



Trimethylgallium



2,2,6-Trimethylheptane



2,5,5-Trimethylheptane



3,3,5-Trimethylheptane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10556	3,4,5-Trimethylheptane		$C_{10}H_{22}$	20278-89-1	142.282			162.5	0.7519^{25}	1.4229^{20}	
10557	2,2,3-Trimethylhexane		C_9H_{20}	16747-25-4	128.255			133.6	0.7257^{25}	1.4106^{20}	
10558	2,2,4-Trimethylhexane		C_9H_{20}	16747-26-5	128.255	liq	-120	126.5	0.711^{20}	1.4033^{20}	
10559	2,2,5-Trimethylhexane		C_9H_{20}	3522-94-9	128.255	liq	-105.7	124.09	0.7072^{20}	1.3997^{20}	i H_2O; vs EtOH, eth, ace, bz; s ctc
10560	2,3,3-Trimethylhexane		C_9H_{20}	16747-28-7	128.255	liq	-116.8	137.7	0.7345^{25}	1.4141^{20}	
10561	2,3,4-Trimethylhexane		C_9H_{20}	921-47-1	128.255			139.1	0.7354^{25}	1.4144^{20}	
10562	2,3,5-Trimethylhexane		C_9H_{20}	1069-53-0	128.255	liq	-127.9	131.4	0.7218^{20}	1.4051^{20}	
10563	2,4,4-Trimethylhexane		C_9H_{20}	16747-30-1	128.255	liq	-113.4	130.7	0.7201^{25}	1.4074^{20}	
10564	3,3,4-Trimethylhexane		C_9H_{20}	16747-31-2	128.255	liq	-101.2	140.5	0.7414^{25}	1.4178^{20}	
10565	3,5,5-Trimethylhexanoic acid	Isononanoic acid	$C_9H_{18}O_2$	3302-10-1	158.238	liq		121^{10}, 85^{4}			
10566	3,5,5-Trimethyl-1-hexanol		$C_9H_{20}O$	3452-97-9	144.254			194	0.8236^{25}	1.4300^{25}	
10567	1,2,3-Trimethylindene		$C_{12}H_{14}$	4773-83-5	158.239	liq		100.5^{10}	0.9714^{20}	1.5521^{20}	
10568	Trimethylindium	Indium trimethyl	C_3H_9In	3385-78-2	159.921			135.7	1.568^{19}		
10569	2,3,3-Trimethyl-3*H*-indole		$C_{11}H_{13}N$	1640-39-7	159.228			107^{11}			
10570	Trimethyl(4-methylphenyl)silane		$C_{10}H_{16}Si$	3728-43-6	164.320		38	192; 73^{10}	0.8666^{20}	1.4900^{20}	
10571	1,4,5-Trimethylnaphthalene		$C_{13}H_{14}$	2131-41-1	170.250	lf (MeOH)	63	145^{12}			i H_2O
10572	1,3,5-Trimethyl-2-nitrobenzene		$C_9H_{11}NO_2$	603-71-4	165.189	orth pr (al)	44	255	1.51^{25}		vs EtOH
10573	2,6,8-Trimethyl-4-nonanol		$C_{12}H_{26}O$	123-17-1	186.333			225.4	0.8178^{20}		sl ctc
10574	2,4,7-Trimethyloctane		$C_{11}H_{24}$	62016-38-0	156.309			168.1			
10575	Trimethylolpropane		$C_6H_{14}O_3$	77-99-6	134.173	wh pow or pl	58	160^{5}			vs H_2O, EtOH
10576	3,5,5-Trimethyl-2,4-oxazolidinedione	Trimethadione	$C_6H_9NO_3$	127-48-0	143.140		46	79^{5}			s H_2O; vs EtOH, eth, ace, bz; i peth
10577	Trimethyloxonium fluoborate		$C_3H_9BF_4O$	420-37-1	147.907	hyg nd	148 dec				vs ace, chl
10578	2,4,4-Trimethyl-2-pentanamine		$C_8H_{19}N$	107-45-9	129.244						s chl
10579	2,2,3-Trimethylpentane		C_8H_{18}	564-02-3	114.229	liq	-112.2	110	0.7161^{20}	1.4030^{20}	i H_2O; msc EtOH, eth, ace, hp; s bz
10580	2,2,4-Trimethylpentane	Isooctane	C_8H_{18}	540-84-1	114.229	liq	-107.3	99.22	0.6878^{25}	1.3884^{25}	i H_2O; msc EtOH, ace, hp; s eth, ctc
10581	2,3,3-Trimethylpentane		C_8H_{18}	560-21-4	114.229	liq	-100.9	114.8	0.7262^{20}	1.4075^{20}	i H_2O; vs EtOH; msc eth, ace, bz, hp
10582	2,3,4-Trimethylpentane		C_8H_{18}	565-75-3	114.229	liq	-109.2	113.5	0.7191^{20}	1.4042^{20}	i H_2O; vs EtOH; msc eth, ace, bz; sl ctc
10583	2,2,4-Trimethyl-1,3-pentanediol		$C_8H_{18}O_2$	144-19-4	146.228	pl (bz)	51.5	235; 81^{1}	0.936^{15}	1.4513^{15}	sl H_2O; vs EtOH, eth; s bz, chl
10584	2,4,4-Trimethyl-2-pentanethiol		$C_8H_{18}S$	141-59-3	146.294	liq		76^{50}			
10585	2,4,4-Trimethyl-2-pentanol		$C_8H_{18}O$	690-37-9	130.228	liq	-20	147.5	0.8225^{20}	1.4284^{20}	i H_2O; sl EtOH; s eth
10586	2,2,4-Trimethyl-3-pentanol		$C_8H_{18}O$	5162-48-1	130.228	liq	-13	150.5	0.8297^{20}	1.4288^{20}	
10587	2,2,4-Trimethyl-3-pentanone	*tert*-Butyl isopropyl ketone	$C_8H_{16}O$	5857-36-3	128.212			135.1	0.8065^{20}	1.4060	i H_2O; s eth, ace
10588	2,3,3-Trimethyl-1-pentene		C_8H_{16}	560-23-6	112.213	liq	-69	108.3	0.7308^{25}	1.4174^{20}	
10589	2,4,4-Trimethyl-1-pentene		C_8H_{16}	107-39-1	112.213	liq	-93.5	101.4	0.7150^{20}	1.4086^{20}	i H_2O; s eth, bz, ctc, chl, lig
10590	2,3,4-Trimethyl-2-pentene		C_8H_{16}	565-77-5	112.213	liq	-113.4	116.5	0.7434^{20}	1.4274^{20}	
10591	2,4,4-Trimethyl-2-pentene		C_8H_{16}	107-40-4	112.213	liq	-106.3	104.9	0.7218^{20}	1.4160^{20}	i H_2O; s eth, bz, ctc, chl; vs lig
10592	2,3,4-Trimethylphenol		$C_9H_{12}O$	526-85-2	136.190	nd (peth)	81	236			vs bz, eth, EtOH
10593	2,3,5-Trimethylphenol		$C_9H_{12}O$	697-82-5	136.190		94.5	233			
10594	2,3,6-Trimethylphenol		$C_9H_{12}O$	2416-94-6	136.190		63				
10595	2,4,5-Trimethylphenol		$C_9H_{12}O$	496-78-6	136.190	nd (lig)	72	232			i H_2O; vs EtOH, eth
10596	2,4,6-Trimethylphenol		$C_9H_{12}O$	527-60-6	136.190	nd (peth, MeOH)	73	220			vs eth, EtOH
10597	3,4,5-Trimethylphenol		$C_9H_{12}O$	527-54-8	136.190	nd (peth)	108	248.5			
10598	Trimethylphenoxysilane		$C_9H_{14}OSi$	1529-17-5	166.292	liq	-55	119	0.8681^{20}	1.5125^{20}	
10599	Trimethylphenylammonium chloride	Phenyltrimethylammonium chloride	$C_9H_{14}ClN$	138-24-9	171.667						vs H_2O, EtOH
10600	1-(2,4,6-Trimethylphenyl)ethanone		$C_{11}H_{14}O$	1667-01-2	162.228			241; 120^{12}	0.9754^{20}	1.5175^{20}	i H_2O; s EtOH, eth, ace, bz, ctc
10601	1,1,1-Trimethyl-*N*-phenylsilanamine	Phenyl(trimethylsilyl)amine	$C_9H_{15}NSi$	3768-55-6	165.308			206	0.940^{20}		
10602	Trimethylphenylsilane		$C_9H_{14}Si$	768-32-1	150.293			169.5	0.8722^{20}	1.4907^{20}	s ctc, CS_2
10603	Trimethyl phosphate	Methyl phosphate	$C_3H_9O_4P$	512-56-1	140.074	liq	-46	197.2	1.2144^{20}	1.3967^{20}	vs H_2O; sl EtOH; s eth
10604	Trimethylphosphine		C_3H_9P	594-09-2	76.077	liq	-85	37.5			i H_2O; s eth



3,4,5-Trimethylheptane



2,2,3-Trimethylhexane



2,2,4-Trimethylhexane



2,2,5-Trimethylhexane



2,3,3-Trimethylhexane


2,3,4-Trimethylhexane



2,3,5-Trimethylhexane


2,4,4-Trimethylhexane



3,3,4-Trimethylhexane



3,5,5-Trimethylhexanoic acid




3,5,5-Trimethyl-1-hexanol



1,2,3-Trimethylindene




Trimethylindium




2,3,3-Trimethyl-3*H*-indole




Trimethyl(4-methylphenyl)silane



1,4,5-Trimethylnaphthalene




1,3,5-Trimethyl-2-nitrobenzene




2,6,8-Trimethyl-4-nonanol



2,4,7-Trimethyloctane




Trimethylolpropane




3,5,5-Trimethyl-2,4-oxazolidinedione





Trimethyloxonium fluoborate





2,4,4-Trimethyl-2-pentanamine


2,2,3-Trimethylpentane



2,2,4-Trimethylpentane


2,3,3-Trimethylpentane



2,3,4-Trimethylpentane




2,2,4-Trimethyl-1,3-pentanediol




2,4,4-Trimethyl-2-pentanethiol




2,4,4-Trimethyl-2-pentanol





2,2,4-Trimethyl-3-pentanol





2,2,4-Trimethyl-3-pentanone


2,3,3-Trimethyl-1-pentene



2,4,4-Trimethyl-1-pentene


2,3,4-Trimethyl-2-pentene



2,4,4-Trimethyl-2-pentene




2,3,4-Trimethylphenol




2,3,5-Trimethylphenol




2,3,6-Trimethylphenol




2,4,5-Trimethylphenol




2,4,6-Trimethylphenol




3,4,5-Trimethylphenol




Trimethylphenoxysilane




Trimethylphenylammonium chloride



1-(2,4,6-Trimethylphenyl)ethanone



1,1,1-Trimethyl-*N*-phenylsilanamine



Trimethylphenylsilane





Trimethyl phosphate





Trimethylphosphine

No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10605	Trimethyl phosphite		$C_3H_9O_3P$	121-45-9	124.075			111.5	1.0518^{20}	1.4095^{20}	vs EtOH, eth; sl ctc
10606	1,2,4-Trimethylpiperazine		$C_7H_{16}N_2$	120-85-4	128.215			149.5		1.4433^{20}	s ctc
10607	2,2,4-Trimethylpiperidine		$C_8H_{17}N$	101257-71-0	127.228			148	0.832^{15}	1.4458^{20}	vs eth, EtOH
10608	Trimethylpyrazine		$C_7H_{10}N_2$	14667-55-1	122.167			87^{35}			
10609	1,3,5-Trimethyl-1*H*-pyrazole		$C_6H_{10}N_2$	1072-91-9	110.156		37	170	0.9269^{40}	1.4589^{57}	
10610	2,3,6-Trimethylpyridine	2,3,6-Collidine	$C_8H_{11}N$	1462-84-6	121.180			171.6	0.9220^{25}	1.5053^{20}	s H_2O, EtOH, eth, ace, bz
10611	2,4,6-Trimethylpyridine	2,4,6-Collidine	$C_8H_{11}N$	108-75-8	121.180	liq	-46	170.6	0.9166^{22}	1.4959^{25}	s H_2O, EtOH, eth, ace, ctc
10612	1,2,5-Trimethyl-1*H*-pyrrole		$C_7H_{11}N$	930-87-0	109.169			171	0.807^{25}	1.4969^{20}	
10613	*N,N*,2-Trimethyl-6-quinolinamine		$C_{12}H_{14}N_2$	92-99-9	186.252	ye pr (HOAc, AcOEt)	101	319			s ctc, CS_2
10614	Trimethylsilane		$C_3H_{10}Si$	993-07-7	74.197	col gas	-135.9	6.7			
10615	1-(Trimethylsilyl)-1*H*-imidazole		$C_6H_{12}N_2Si$	18156-74-6	140.258						s chl
10616	3-(Trimethylsilyl)-1-propanol		$C_6H_{16}OSi$	2917-47-7	132.276			141; 82^{24}	0.822^{25}	1.4298^{20}	
10617	Trimethylstibine		C_3H_9Sb	594-10-5	166.863	liq	-62	80.6	1.523^{15}	1.42^{15}	i H_2O; s EtOH, eth, CS_2
10618	Trimethylsulfonium iodide		C_3H_9IS	2181-42-2	204.072	cry (eth)	211 dec				
10619	Trimethylthiourea		$C_4H_{10}N_2S$	2489-77-2	118.200	pr (bz-lig)	87.5				vs bz, EtOH, chl
10620	2,4,6-Trimethyl-2,4,6-triphenylcyclotrisiloxane		$C_{21}H_{24}O_3Si_3$	546-45-2	408.671		100	$190^{1.5}$	1.1062^{20}	1.5397^{20}	
10621	Trimethylurea		$C_4H_{10}N_2O$	632-14-4	102.134	pr (eth)	75.5	232.5	1.1900^{20}		s H_2O, EtOH; sl eth, bz
10622	Trinitroacetonitrile		$C_2N_4O_6$	630-72-8	176.044	wax	41.5	exp 220			vs eth
10623	2,4,6-Trinitroaniline		$C_6H_4N_4O_6$	489-98-5	228.119	dk ye pr (HOAc)	193.5	exp	1.762^{10}		i H_2O; sl EtOH, eth; s ace, bz, AcOEt
10624	1,3,5-Trinitrobenzene	*sym*-Trinitrobenzene	$C_6H_3N_3O_6$	99-35-4	213.104	orth pl (bz) lf (w)	122.9	315	1.4775^{152}		sl H_2O, EtOH, eth; vs ace; s bz, py
10625	2,4,6-Trinitro-1,3-benzenediol	Styphnic acid	$C_6H_3N_3O_8$	82-71-3	245.103	hex ye cry (dil al)	175.5	sub			vs eth, EtOH
10626	2,4,6-Trinitrobenzoic acid		$C_7H_3N_3O_8$	129-66-8	257.114	orth (w)	228 dec				sl H_2O, bz; vs EtOH; s eth, ace
10627	2,4,7-Trinitro-9*H*-fluoren-9-one		$C_{13}H_5N_3O_7$	129-79-3	315.195	pa ye nd (bz, HOAc)	175.8				sl H_2O; vs ace, bz, chl
10628	Trinitrofluoromethane	Fluorotrinitromethane	CFN_3O_6	1840-42-2	169.025			86.3	1.59^{20}		
10629	Trinitroglycerol	Nitroglycerin	$C_3H_5N_3O_9$	55-63-0	227.087	pa ye tcl or orth	13.5	exp 218; $93^{0.31}$	1.5931^{20}	1.4786^{12}	sl H_2O; s EtOH, bz; msc eth; vs ace, chl
10630	Trinitromethane		CHN_3O_6	517-25-9	151.035		15	exp	1.479^{20}	1.4451^{24}	vs ace, EtOH
10631	2,4,6-Trinitrophenol	Picric acid	$C_6H_3N_3O_7$	88-89-1	229.104	ye lf (w), pr (eth) pl (al)	122.5	exp 300		1.763	sl H_2O; s EtOH, eth, bz, chl; vs ace
10632	2,4,6-Trinitrophenol, sodium salt	Sodium picrate	$C_6H_2N_3NaO_7$	3324-58-1	251.086	nd (w)	270.4				
10633	2,4,6-Trinitrotoluene	2-Methyl-1,3,5-trinitrobenzene	$C_7H_5N_3O_6$	118-96-7	227.131	orth (al)	80.5	exp 240	1.654^{25}		i H_2O; sl EtOH; s eth; vs ace, bz
10634	2,4,6-Trinitro-*N*-(2,4,6-trinitrophenyl)aniline	Dipicrylamine	$C_{12}H_5N_7O_{12}$	131-73-7	439.208	pa ye pr(HOAc)	244 dec				i H_2O, EtOH, bz, ctc; sl eth, ace; vs py
10635	Trioctylaluminum		$C_{24}H_{51}Al$	1070-00-4	366.644	hyg visc liq	-62		0.701		
10636	Trioctylamine	*N,N*-Dioctyl-1-octanamine	$C_{24}H_{51}N$	1116-76-3	353.669	liq	-34.6	366	0.8110^{20}	1.4510^{19}	
10637	Trioctylphosphine oxide	TOPO	$C_{24}H_{51}OP$	78-50-2	386.635		52	201^{2}			
10638	1,3,5-Trioxane	Formaldehyde, trimer	$C_3H_6O_3$	110-88-3	90.078	orth nd (eth)	60.29	114.5	1.17^{65}		vs H_2O; s EtOH, eth, bz, CS_2; i peth
10639	1,3,5-Trioxane-2,4,6-triimine	Cyamelide	$C_3H_3N_3O_3$	462-02-2	129.074	amor pow	dec	dec	1.127^{15}		vs eth, EtOH
10640	4,7,10-Trioxatridecane-1,13-diamine	Diethyleneglycol diaminopropyl ether	$C_{10}H_{24}N_2O_3$	4246-51-9	220.309	liq		147^{4}	1.005	1.4640^{20}	
10641	3,7,12-Trioxocholan-24-oic acid, (5β)	Dehydrocholic acid	$C_{24}H_{34}O_5$	81-23-2	402.524		237				i H_2O, eth; sl EtOH, bz; s ace, AcOEt
10642	Tripentylamine	*N,N*-Dipentyl-1-pentanamine	$C_{15}H_{33}N$	621-77-2	227.430			242.5	0.7907^{20}	1.4366^{20}	i H_2O; s EtOH, eth, acid
10643	Triphenylamine	*N,N*-Diphenylbenzenamine	$C_{18}H_{15}N$	603-34-9	245.319	mcl (MeOH, bz)	126.5	365	0.774^{0}	1.353^{16}	i H_2O; sl EtOH; s eth, bz, MeOH
10644	Triphenylarsine		$C_{18}H_{15}As$	603-32-7	306.234		61	360	1.2634^{18}	1.6888^{21}	i H_2O; sl EtOH; vs eth, bz; s chl
10645	Triphenylarsine oxide		$C_{18}H_{15}AsO$	1153-05-5	322.233		192	324.0			



Trimethyl phosphite



1,2,4-Trimethylpiperazine



2,2,4-Trimethylpiperidine



Trimethylpyrazine


1,3,5-Trimethyl-1*H*-pyrazole



2,3,6-Trimethylpyridine



2,4,6-Trimethylpyridine


1,2,5-Trimethyl-1*H*-pyrrole


N,*N*,2-Trimethyl-6-quinolinamine



Trimethylsilane



1-(Trimethylsilyl)-1*H*-imidazole



3-(Trimethylsilyl)-1-propanol



Trimethylstibine



Trimethylsulfonium iodide



Trimethylthiourea



2,4,6-Trimethyl-2,4,6-triphenylcyclotrisiloxane



Trimethylurea



Trinitroacetonitrile



2,4,6-Trinitroaniline



1,3,5-Trinitrobenzene



2,4,6-Trinitro-1,3-benzenediol



2,4,6-Trinitrobenzoic acid



2,4,7-Trinitro-9*H*-fluoren-9-one



Trinitrofluoromethane



Trinitroglycerol



Trinitromethane



2,4,6-Trinitrophenol



2,4,6-Trinitrophenol, sodium salt


2,4,6-Trinitrotoluene



2,4,6-Trinitro-*N*-(2,4,6-trinitrophenyl)aniline



Trioctylaluminum



Trioctylamine



Trioctylphosphine oxide



1,3,5-Trioxane



1,3,5-Trioxane-2,4,6-triimine



4,7,10-Trioxatridecane-1,13-diamine


3,7,12-Trioxocholan-24-oic acid, (5β)



Tripentylamine



Triphenylamine



Triphenylarsine



Triphenylarsine oxide


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10646	Triphenylbismuthine		$C_{18}H_{15}Bi$	603-33-8	440.292		77.6	242^{14}	1.715^{75}	1.7040^{75}	sl EtOH, chl; s eth, ace, bz, CS_2
10647	Triphenylborane		$C_{18}H_{15}B$	960-71-4	242.123	wh cry	142				i H_2O; sl eth; s bz, lig
10648	Triphenylene	Benzo[1]phenanthrene	$C_{18}H_{12}$	217-59-4	228.288	nd (al, chl, bz)	197.8	425			i H_2O; s EtOH, HOAc; vs bz, chl
10649	1,1,2-Triphenylethane		$C_{20}H_{18}$	1520-42-9	258.357	mcl lf (dil al) , nd (al)	57				i H_2O; vs EtOH, eth, bz; sl MeOH
10650	1,1,2-Triphenylethene		$C_{20}H_{16}$	58-72-0	256.341	lf (al)	72.5	220^{14}	1.0373^{78}	1.6292^{78}	i H_2O; s EtOH, chl, MeOH; vs eth
10651	*N,N',N''*-Triphenylguanidine		$C_{19}H_{17}N_3$	101-01-9	287.358	nd or pr (al)	146.5	dec	1.163^{20}		sl H_2O; s EtOH
10652	2,4,5-Triphenyl-1*H*-imidazole		$C_{21}H_{16}N_2$	484-47-9	296.365	nd (al)	275	sub			i H_2O; s EtOH, eth
10653	Triphenylmethane		$C_{19}H_{16}$	519-73-3	244.330	orth (al)	93.4	359; 200^{10}	1.014^{99}	1.5839^{99}	i H_2O; sl EtOH; vs eth, py, chl; s bz
10654	Triphenylmethanol		$C_{19}H_{16}O$	76-84-6	260.329	pl (al), trg (bz)	164.2	380	1.199^{0}		i H_2O, peth; vs EtOH, eth; s ace, bz
10655	Triphenyl phosphate		$C_{18}H_{15}O_4P$	115-86-6	326.283	cry (lig), pr (al) nd (eth)	50.5	245^{11}	1.2055^{50}		i H_2O; s EtOH; vs eth, bz, ctc, chl
10656	Triphenylphosphine		$C_{18}H_{15}P$	603-35-0	262.286		80	188^{1}	1.0749^{80}	1.6358^{80}	i H_2O; s EtOH, bz, chl; vs eth
10657	Triphenylphosphine oxide		$C_{18}H_{15}OP$	791-28-6	278.285	pr	156.5	>360	1.2124^{23}		sl H_2O, eth, chl; vs EtOH, bz
10658	Triphenyl phosphite		$C_{18}H_{15}O_3P$	101-02-0	310.284		25	360	1.1842^{20}	1.5900^{20}	i H_2O; vs EtOH
10659	Triphenylsilane		$C_{18}H_{16}Si$	789-25-3	260.406						s ctc, CS_2
10660	Triphenylsilanol		$C_{18}H_{16}OSi$	791-31-1	276.405		154.8		1.1777^{20}		s ctc, CS_2
10661	Triphenylstibine		$C_{18}H_{15}Sb$	603-36-1	353.072	pr (peth)	53.5	>360	1.4343^{25}	1.6948^{42}	i H_2O; s EtOH; vs eth, ace, bz, chl
10662	Triphenyltetrazolium chloride		$C_{19}H_{15}ClN_4$	298-96-4	334.802	nd (al,chl)	243 dec				s H_2O, EtOH, ace, chl; i eth
10663	Triphenyltin hydroxide	Stannane, hydroxytriphenyl-	$C_{18}H_{16}OSn$	76-87-9	367.029		119		1.54^{20}		
10664	2,4,6-Triphenyl-1,3,5-triazine		$C_{21}H_{15}N_3$	493-77-6	309.364		257				
10665	Tripotassium citrate	Potassium citrate	$C_6H_5K_3O_7$	866-84-2	306.395	wh cry (w)	275 dec				vs H_2O; i EtOH
10666	Triprolidine		$C_{19}H_{22}N_2$	486-12-4	278.391	cry (peth)	60				
10667	Tri-2-propenoyl-2-ethyl-2-(hydroxymethyl)-1,3-propanediol	Trimethylolpropane triacrylate	$C_{15}H_{20}O_6$	15625-89-5	296.316			>200^{1}		1.4735^{20}	
10668	Tripropylamine	*N,N*-Dipropyl-1-propanamine	$C_9H_{21}N$	102-69-2	143.270	liq	-93.5	156	0.7558^{20}	1.4181^{20}	vs eth, EtOH
10669	Tripropylborane		$C_9H_{21}B$	1116-61-6	140.074	liq	-56	159	0.7204^{25}	1.4135^{22}	
10670	Tripropyl borate	Boric acid, tripropyl ester	$C_9H_{21}BO_3$	688-71-1	188.072			179.5	0.8576^{20}	1.3948^{20}	vs EtOH; msc eth; s PrOH
10671	Tripropylene glycol	[(1-Methyl-1,2-ethanediyl) bis(oxy)]bispropanol	$C_9H_{20}O_4$	24800-44-0	192.253	liq		268; 115^{2}	1.02^{20}	1.4440^{20}	
10672	Tripropylene glycol diacrylate		$C_{15}H_{24}O_6$	42978-66-5	300.348			>120^{1}			
10673	Tripropylene glycol monomethyl ether	1-[2-(2-Methoxy-1-methylethoxy)-1-methylethoxy] -2-propanol	$C_{10}H_{22}O_4$	20324-33-8	206.280			241.3			
10674	Tripropyl phosphate		$C_9H_{21}O_4P$	513-08-6	224.234			252	1.0121^{20}	1.4165^{20}	sl H_2O, chl; s EtOH, eth, tol, CS_2
10675	Tripropyl phosphite	Tripropoxyphosphine	$C_9H_{21}O_3P$	923-99-9	208.235			206.5	0.9417^{20}	1.4282^{20}	vs eth, EtOH
10676	Tripropylsilane		$C_9H_{22}Si$	998-29-8	158.357			172	0.7723^{0}	1.4280^{20}	i H_2O
10677	Tris(4-aminophenyl)methanol	C.I. Basic Red 9	$C_{19}H_{19}N_3O$	467-62-9	305.373	purp cry	205				
10678	2,4,6-Tris(1-aziridinyl)-1,3,5-triazine	Triethylenemelamine	$C_9H_{12}N_6$	51-18-3	204.231	cry pow	139 dec				s H_2O
10679	Tris(2-butoxyethyl) phosphate		$C_{18}H_{39}O_7P$	78-51-3	398.473	liq		255^{10}	1.02^{25}		i H_2O
10680	Tris(2-chloroethyl) phosphate		$C_6H_{12}Cl_3O_4P$	115-96-8	285.489			330; 194^{10}	1.39^{25}	1.4721^{20}	s ctc
10681	Tris(2-chloroethyl) phosphite		$C_6H_{12}Cl_3O_3P$	140-08-9	269.490			120^{3}	1.3443^{26}	1.4868^{20}	
10682	Tris(1,3-dichloro-2-propyl) phosphate	Fyrol FR-2	$C_9H_{15}Cl_6O_4P$	13674-87-8	430.904	visc liq		236^{5}		1.5022^{20}	i H_2O
10683	Tris(4-dimethylaminophenyl) methane	Paraleucaniline	$C_{25}H_{31}N_3$	603-48-5	373.534	lf (al), nd (bz)	176.5				vs bz, eth, chl
10684	Tris(2,4-dimethylphenyl) phosphate	2,4-Xylenol, phosphate (3:1)	$C_{24}H_{27}O_4P$	3862-12-2	410.442			233.5	1.142^{38}	1.5550^{20}	i H_2O; s bz, chl, hx
10685	Tris(2,5-dimethylphenyl) phosphate	2,5-Xylenol, phosphate (3:1)	$C_{24}H_{27}O_4P$	19074-59-0	410.442		79.8	262^{8}	1.197^{25}		i H_2O; sl EtOH, hx; s eth, bz, ctc



Triphenylbismuthine



Triphenylborane



Triphenylene



1,1,2-Triphenylethane



1,1,2-Triphenylethene



N,N',N''-Triphenylguanidine



2,4,5-Triphenyl-1*H*-imidazole



Triphenylmethane



Triphenylmethanol



Triphenyl phosphate



Triphenylphosphine



Triphenylphosphine oxide



Triphenyl phosphite



Triphenylsilane



Triphenylsilanol



Triphenylstibine



Triphenyltetrazolium chloride



Triphenyltin hydroxide



2,4,6-Triphenyl-1,3,5-triazine



Tripotassium citrate



Triprolidine



Tri-2-propenoyl-2-ethyl-2-(hydroxymethyl)-1,3-propanediol



Tripropylamine



Tripropylborane



Tripropyl borate



Tripropylene glycol



Tripropylene glycol diacrylate



Tripropylene glycol monomethyl ether



Tripropyl phosphate



Tripropyl phosphite



Tripropylsilane



Tris(4-aminophenyl)methanol



2,4,6-Tris(1-aziridinyl)-1,3,5-triazine



Tris(2-butoxyethyl) phosphate



Tris(2-chloroethyl) phosphate


Tris(2-chloroethyl) phosphite



Tris(1,3-dichloro-2-propyl) phosphate



Tris(4-dimethylaminophenyl)methane



Tris(2,4-dimethylphenyl) phosphate



Tris(2,5-dimethylphenyl) phosphate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10686	Tris(2,6-dimethylphenyl) phosphate	2,6-Xylenol, phosphate (3:1)	$C_{24}H_{27}O_4P$	121-06-2	410.442	wax	137.8	263^{6}			i H_2O; sl EtOH, hx; s bz
10687	Tris(3,5-dimethylphenyl) phosphate		$C_{24}H_{27}O_4P$	25653-16-1	410.442		46.2	290^{10}			i H_2O; sl EtOH, chl, hx; s HOAc
10688	Tris(2-ethylhexyl) phosphate		$C_{24}H_{51}O_4P$	78-42-2	434.633	liq		215^{5}	0.99^{20}		
10689	Tris(ethylthio)methane	Triethyl orthothioformate	$C_7H_{16}S_3$	6267-24-9	196.397			dec 235; 127^{12}	1.053^{20}	1.5410^{15}	vs eth, EtOH
10690	1,3,5-Tris(2-hydroxyethyl) isocyanuric acid		$C_9H_{15}N_3O_6$	839-90-7	261.231	cry	136				
10691	1,1,1-Tris(hydroxymethyl)ethane trinitrate	2-Methyl-2-[(nitrooxy)methyl]-1,3-propanediol, dinitrate	$C_5H_9N_3O_9$	3032-55-1	255.140			83$^{0.05}$			
10692	*N,N′,N″*-Tris(hydroxymethyl) melamine	Trimethylolmelamine	$C_6H_{12}N_6O_3$	1017-56-7	216.197	cry	148				
10693	Tris(hydroxymethyl)methylamine	2-Amino-2-(hydroxymethyl)-1,3-propanediol	$C_4H_{11}NO_3$	77-86-1	121.135		171.5	219^{10}			vs H_2O; s MeOH
10694	Tris(methoxyethoxy)vinylsilane		$C_{11}H_{24}O_6Si$	1067-53-4	280.391						s ctc
10695	Tris(4-methoxyphenyl) chloroethene	Chlorotrianisene	$C_{23}H_{21}ClO_3$	569-57-3	380.864		115				
10696	Tris(2-methylphenyl)phosphine		$C_{21}H_{21}P$	6163-58-2	304.366		127.0				
10697	Tris(3-methylphenyl)phosphine		$C_{21}H_{21}P$	6224-63-1	304.366		101.0				
10698	Tris(4-methylphenyl)phosphine		$C_{21}H_{21}P$	1038-95-5	304.366		147.0				
10699	Tris(2-methyl-2-propenoyl)-2-ethyl-2-hydroxymethyl-1,3-propanediol	1,1,1-Trimethylolpropane trimethacrylate	$C_{18}H_{26}O_6$	3290-92-4	338.395			>200^{1}		1.470^{25}	
10700	Trisodium citrate	Sodium citrate	$C_6H_5Na_3O_7$	68-04-2	258.069	wh cry (w)	300				vs H_2O; i EtOH
10701	Trisodium *N*-hydroxyethylethylenediaminetriacetate	Versen-Ol	$C_{10}H_{15}N_2Na_3O_7$	139-89-9	344.204		288 (hyd)				
10702	Tris(perfluorobutyl)amine	Trinonafluorobutylamine	$C_{12}F_{27}N$	311-89-7	671.092			178	1.884^{25}	1.291^{25}	s ace
10703	2,4,6-Tris(2-pyridinyl)-1,3,5-triazine	2,4,6-Tripyridyl-*s*-triazine	$C_{18}H_{12}N_6$	3682-35-7	312.328		210				
10704	Tris(*o*-tolyl) phosphite		$C_{21}H_{21}O_3P$	2622-08-4	352.364		11	238^{11}, 197^{2}	1.1423^{20}	1.5740^{28}	s eth; sl chl
10705	Tris(*p*-tolyl) phosphite		$C_{21}H_{21}O_3P$	620-42-8	352.364	pa ye	52	252^{10}	1.1280^{25}	1.5703^{28}	vs eth
10706	Tris(triphenylphosphine) rhodium carbonyl hydride	Carbonylhydrotris(triphenylphosphine)rhodium	$C_{55}H_{46}OP_3Rh$	17185-29-4	918.781	ye cry	121		1.33		sl bz, chl
10707	1,3,5-Trithiane		$C_3H_6S_3$	291-21-4	138.275	hex (bz), pr (w) nd (al)	220	sub	1.6374^{24}		sl H_2O, EtOH, eth; s bz
10708	Trithiocarbonic acid		CH_2S_3	594-08-1	110.222	red oil	-26.9	57.8	1.476^{25}	1.8225^{20}	dec H_2O, EtOH; vs tol, chl
10709	Tritriacontane		$C_{33}H_{68}$	630-05-7	464.893		71.2				
10710	Tropacocaine		$C_{15}H_{19}NO_2$	537-26-8	245.318	pl or tab	49	dec	1.0426^{100}	1.5080^{100}	vs bz, eth, EtOH, peth
10711	Tropine	8-Methyl-8-azabicyclo[3.2.1] octan-3-ol, *endo*	$C_8H_{15}NO$	120-29-6	141.211	hyg pl (eth)	64	233	1.016^{100}	1.4811^{100}	vs H_2O, eth, EtOH
10712	Trypan blue		$C_{34}H_{24}N_6Na_4O_{14}S_4$	72-57-1	960.805	dk bl cry	300				s H_2O, acid; i EtOH
10713	Tryptamine		$C_{10}H_{12}N_2$	61-54-1	160.215	nd (al-bz, lig)	118	137$^{0.15}$			i H_2O, eth, bz, chl; s EtOH, ace
10714	*L*-Tryptophan	α-Aminoindole-3-propionic acid, (*l*)	$C_{11}H_{12}N_2O_2$	73-22-3	204.225	lf or pl (dil al)	289 dec				sl H_2O, HOAc; s EtOH; i eth, chl
10715	Tsuduranine		$C_{18}H_{19}NO_3$	517-97-5	297.349	nd (eth)	204				vs ace, eth, EtOH
10716	T-2 Toxin	Mycotoxin T2	$C_{24}H_{34}O_9$	21259-20-1	466.522	nd	151				sl H_2O, peth; s EtOH, chl, DMSO
10717	Tubocurarine dichloride		$C_{37}H_{42}Cl_2N_2O_6$	57-94-3	681.644	hyg cry	275 dec				s MeOH; i py, bz, ace, eth
10718	Tungsten carbonyl	Tungsten hexacarbonyl	C_6O_6W	14040-11-0	351.90	wh cry	dec 170	sub	2.65		i H_2O; s os
10719	Turanose		$C_{12}H_{22}O_{11}$	547-25-1	342.296	pr (w-al, MeOH)	168				vs H_2O; s EtOH, MeOH
10720	Tybamate		$C_{13}H_{26}N_2O_4$	4268-36-4	274.356	cry	50	151$^{0.06}$			
10721	*L*-Tyrosine	4-Hydroxy-*L*-phenylalanine	$C_9H_{11}NO_3$	60-18-4	181.188	nd (w)	343 dec	sub			sl H_2O, HOAc; i EtOH, eth
10722	Tyrosineamide		$C_9H_{12}N_2O_2$	4985-46-0	180.203	pl or pl (al)	153.5				vs H_2O, EtOH
10723	*L*-Tyrosine, ethyl ester		$C_{11}H_{15}NO_3$	949-67-7	209.242	pr (AcOEt)	108.5				vs bz, EtOH, AcOEt
10724	*L*-Tyrosine, methyl ester, hydrochloride		$C_{10}H_{14}ClNO_3$	3417-91-2	231.676		191.0				s H_2O
10725	1,10-Undecadiyne		$C_{11}H_{16}$	4117-15-1	148.245		-17	83^{12}	0.8182^{21}	1.453^{21}	vs ace, bz
10726	Undecafluorocyclohexane		C_6HF_{11}	308-24-7	282.054			62.0			
10727	Undecanal		$C_{11}H_{22}O$	112-44-7	170.292		-2.0	117^{18}	0.8251^{23}	1.4520^{20}	i H_2O; s EtOH, eth



Tris(2,6-dimethylphenyl) phosphate



Tris(3,5-dimethylphenyl) phosphate



Tris(2-ethylhexyl) phosphate



Tris(ethylthio)methane



1,3,5-Tris(2-hydroxyethyl) isocyanuric acid



1,1,1-Tris(hydroxymethyl)ethane trinitrate



N,N',N''-Tris(hydroxymethyl)melamine



Tris(hydroxymethyl)methylamine



Tris(methoxyethoxy)vinylsilane



Tris(4-methoxyphenyl)chloroethene



Tris(2-methylphenyl)phosphine



Tris(3-methylphenyl)phosphine



Tris(4-methylphenyl)phosphine



Tris(2-methyl-2-propenoyl)-2-ethyl-2-hydroxymethyl-1,3-propanediol



Trisodium citrate



Trisodium *N*-hydroxyethylethylenediaminetriacetate


Tris(perfluorobutyl)amine


2,4,6-Tris(2-pyridinyl)-1,3,5-triazine



Tris(*o*-tolyl) phosphite



Tris(*p*-tolyl) phosphite


Tris(triphenylphosphine) rhodium carbonyl hydride



1,3,5-Trithiane



Trithiocarbonic acid



Tritriacontane



Tropacocaine



Tropine



Trypan blue



Tryptamine



L-Tryptophan



Tsuduranine



T-2 Toxin



Tubocurarine dichloride



Tungsten carbonyl



Turanose



Tybamate



L-Tyrosine



Tyrosineamide


L-Tyrosine, ethyl ester



L-Tyrosine, methyl ester, hydrochloride



1,10-Undecadiyne



Undecafluorocyclohexane



Undecanal


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10728	Undecane	Hendecane	$C_{11}H_{24}$	1120-21-4	156.309	liq	-25.5	195.9	0.7402^{20}	1.4164^{20}	i H_2O; msc EtOH, eth
10729	Undecanenitrile	Decyl cyanide	$C_{11}H_{21}N$	2244-07-7	167.292			253	0.8254^{30}	1.4293^{30}	i H_2O; s EtOH, eth, ctc
10730	1-Undecanethiol	Undecyl mercaptan	$C_{11}H_{24}S$	5332-52-5	188.374	liq	-1.5	257.4	0.8448^{20}	1.4585^{20}	
10731	Undecanoic acid		$C_{11}H_{22}O_2$	112-37-8	186.292	cry (ace)	28.6	280	0.8907^{20}	1.4294^{45}	i H_2O; vs EtOH, ace; s eth; msc bz
10732	1-Undecanol	Undecyl alcohol	$C_{11}H_{24}O$	112-42-5	172.308		15.9	245	0.8298^{20}	1.4392^{20}	i H_2O; s EtOH; vs eth
10733	2-Undecanol	*sec*-Undecyl alcohol	$C_{11}H_{24}O$	1653-30-1	172.308	col liq	0	229.7	0.8234^{25}	1.4352^{25}	
10734	2-Undecanone	Methyl nonyl ketone	$C_{11}H_{22}O$	112-12-9	170.292		15	231.5	0.8250^{20}	1.4291^{20}	i H_2O; s EtOH, eth, ace, bz, chl
10735	6-Undecanone	Butyl hexyl ketone	$C_{11}H_{22}O$	927-49-1	170.292		14.5	228	0.8308^{20}	1.4270^{20}	i H_2O; vs EtOH, eth
10736	Undecanoyl chloride		$C_{11}H_{21}ClO$	17746-05-3	204.737						sl ctc
10737	10-Undecenal		$C_{11}H_{20}O$	112-45-8	168.276						sl ctc
10738	1-Undecene		$C_{11}H_{22}$	821-95-4	154.293	liq	-49.2	192.7	0.7503^{20}	1.4261^{20}	i H_2O; s eth, chl, lig
10739	*cis*-2-Undecene		$C_{11}H_{22}$	821-96-5	154.293	liq	-66.5	196.1	0.7576^{20}		
10740	*trans*-2-Undecene		$C_{11}H_{22}$	693-61-8	154.293	liq	-48.3	192.5	0.7528^{20}	1.4292^{20}	
10741	*cis*-4-Undecene		$C_{11}H_{22}$	821-98-7	154.293	liq	-97	192.6	0.7541^{20}	1.4302^{20}	
10742	*trans*-4-Undecene		$C_{11}H_{22}$	693-62-9	154.293	liq	-63.7	193	0.7508^{20}	1.4285^{20}	
10743	*cis*-5-Undecene		$C_{11}H_{22}$	764-96-5	154.293	liq	-106.5	192.3	0.7537^{20}	1.4302^{20}	
10744	*trans*-5-Undecene		$C_{11}H_{22}$	764-97-6	154.293	liq	-61.1	192	0.7497^{20}	1.4285^{20}	vs eth, chl, lig
10745	10-Undecenoic acid	Undecylenic acid	$C_{11}H_{20}O_2$	112-38-9	184.276	cry	24.5	275	0.9072^{24}	1.4486^{24}	i H_2O; s EtOH, eth; sl ctc
10746	10-Undecen-1-ol		$C_{11}H_{22}O$	112-43-6	170.292	liq	-1.0	250	0.8495^{15}	1.4500^{20}	i H_2O; s EtOH, eth; sl ctc
10747	10-Undecenoyl chloride		$C_{11}H_{19}ClO$	38460-95-6	202.721			127^{13}	0.944^{20}	1.454^{20}	
10748	Undecylamine	1-Undecanamine	$C_{11}H_{23}N$	7307-55-3	171.324	cry (eth, al)	17	242	0.7979^{20}	1.4398^{20}	s H_2O, EtOH; i eth; sl ctc
10749	Undecylbenzene		$C_{17}H_{28}$	6742-54-7	232.404	liq	-5	316	0.8553^{20}	1.4828^{20}	
10750	1-Undecyne		$C_{11}H_{20}$	2243-98-3	152.277	liq	-25	196	0.7728^{20}	1.4306^{20}	vs ace, bz, eth, EtOH
10751	2-Undecyne		$C_{11}H_{20}$	60212-29-5	152.277	liq	-30.1	204.2	0.7827^{20}	1.4391^{20}	
10752	Uracil		$C_4H_4N_2O_2$	66-22-8	112.087	nd (w)	338				sl H_2O; vs EtOH, eth; s dil NH_3
10753	Uracil mustard		$C_8H_{11}Cl_2N_3O_2$	66-75-1	252.098		206 dec				sl H_2O
10754	Uranyl acetate dihydrate		$C_4H_{10}O_8U$	6159-44-0	424.146	ye cry (HOAc)	80 dec		2.89		sl EtOH
10755	Urazole		$C_2H_3N_3O_2$	3232-84-6	101.064	lf (w)	249 dec				
10756	Urea	Carbamide	CH_4N_2O	57-13-6	60.055	tetr pr (al)	133.3	dec	1.3230^{20}	1.484	vs H_2O, EtOH; i eth, bz; s HOAc, py
10757	Urea hydrochloride		CH_5ClN_2O	506-89-8	96.516		145 dec				s H_2O
10758	Urea nitrate		$CH_5N_3O_4$	124-47-0	123.069	mcl lf (w)	152 dec		1.690^{20}		vs EtOH
10759	Uric acid		$C_5H_4N_4O_3$	69-93-2	168.111	orth pr or pl	dec	dec	1.89^{25}		i H_2O, EtOH, eth; s alk, glycerol; sl acid
10760	Uridine	1-β-*D*-Ribofuranosyluracil	$C_9H_{12}N_2O_6$	58-96-8	244.200	nd (aq al)	165				s H_2O, EtOH, py
10761	5'-Uridylic acid	Uridine 5'-phosphoric acid	$C_9H_{13}N_2O_9P$	58-97-9	324.180	pr (MeOH)	202 dec				vs H_2O; s MeOH
10762	Urocanic acid	Imidazole-4-acrylic acid	$C_6H_6N_2O_2$	104-98-3	138.124		227				s H_2O, ace; i EtOH, eth
10763	Urs-12-en-3-ol, (3β)	α-Amyrin	$C_{30}H_{50}O$	638-95-9	426.717	nd (al)	186	$243^{0.5}$			s EtOH, eth, bz, chl, HOAc; sl peth
10764	Ursolic acid		$C_{30}H_{48}O_3$	77-52-1	456.700	pl (al)	284				vs ace, eth, chl
10765	Uzarin		$C_{35}H_{54}O_{14}$	20231-81-6	698.796	pr	269				
10766	Vacciniin	*D*-Glucose, 6-benzoate	$C_{13}H_{16}O_7$	14200-76-1	284.262	amor (aq ace, +1w)	122				vs H_2O, ace, EtOH, eth
10767	Validamycin A		$C_{20}H_{35}NO_{13}$	37248-47-8	497.491	amorp pow	95 dec				
10768	*L*-Valine	2-Aminoisovaleric acid	$C_5H_{11}NO_2$	72-18-4	117.147	lf (w-al)	315	sub	1.23^{25}		s H_2O
10769	Valinomycin		$C_{54}H_{90}N_6O_{18}$	2001-95-8	1111.322	cry	187				
10770	Valium		$C_{16}H_{13}ClN_2O$	439-14-5	284.739		132				
10771	Vamidothion		$C_8H_{18}NO_4PS_2$	2275-23-2	287.337	oil					i peth; s os
10772	Vanadium carbonyl	Vanadium hexacarbonyl	C_6O_6V	14024-00-1	219.002	bl-grn cry	dec 60	sub			
10773	Vanadium(III) 2,4-pentanedioate	Vanadium(III) acetylacetonate	$C_{15}H_{21}O_6V$	13476-99-8	348.266	brn cry	≈185	sub	≈1.0		s MeOH, ace, bz, chl



Undecane



Undecanenitrile



1-Undecanethiol



Undecanoic acid



1-Undecanol


2-Undecanol



2-Undecanone



6-Undecanone



Undecanoyl chloride



10-Undecenal



1-Undecene



cis-2-Undecene



trans-2-Undecene



cis-4-Undecene



trans-4-Undecene



cis-5-Undecene



trans-5-Undecene



10-Undecenoic acid



10-Undecen-1-ol



10-Undecenoyl chloride



Undecylamine



Undecylbenzene



1-Undecyne



2-Undecyne



Uracil



Uracil mustard



Uranyl acetate dihydrate



Urazole



Urea



Urea hydrochloride



Urea nitrate



Uric acid



Uridine



5'-Uridylic acid



Urocanic acid



Urs-12-en-3-ol, (3β)



Ursolic acid



Uzarin



Vacciniin



Validamycin A



L-Valine


Valinomycin



Valium



Vamidothion



Vanadium carbonyl



Vanadium(III) 2,4-pentanedioate


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10774	*DL*-Vasicine	*DL*-Peganine	$C_{11}H_{12}N_2O$	6159-56-4	188.225	nd (al)	210.8				sl H_2O, eth, bz; s EtOH, ace, chl
10775	*L*-Vasicine	*L*-Peganine	$C_{11}H_{12}N_2O$	6159-55-3	188.225	nd (al)	211.5				sl H_2O, eth, bz; s EtOH, ace, chl
10776	Verapamil		$C_{27}H_{38}N_2O_4$	52-53-9	454.602	ye oil		$245^{0.01}$		1.5448^{25}	i H_2O; vs EtOH, ace; sl bz, hx
10777	Veratramine		$C_{27}H_{39}NO_2$	60-70-8	409.605	nd	206				s EtOH, bz, chl, dil acid; i dil alk
10778	Veratramine, 3-glucoside		$C_{33}H_{49}NO_7$	475-00-3	571.745	nd (aq. MeOH)	242 dec				
10779	Veratridine		$C_{36}H_{51}NO_{11}$	71-62-5	673.790	ye amorp pow	180				i H_2O; sl eth
10780	*d*-Verbenone		$C_{10}H_{14}O$	18309-32-5	150.217		9.8	227.5	0.9978^{20}	1.4993^{18}	s H_2O, EtOH, ace, bz
10781	Vernolate	Carbamothioic acid, dipropyl-, *S*-propyl ester	$C_{10}H_{21}NOS$	1929-77-7	203.345			150^{30}	0.952^{20}		
10782	Versalide		$C_{18}H_{26}O$	88-29-9	258.398	cry	46.5	130^{2}			s EtOH
10783	α-Vetivone	Isonootkatone	$C_{15}H_{22}O$	15764-04-2	218.335	cry (peth)	51.5	144^{2}	1.0035^{20}	1.5370^{20}	vs ace
10784	β-Vetivone		$C_{15}H_{22}O$	18444-79-6	218.335	cry (peth)	44.5	141^{2}	1.0001^{20}	1.5309^{20}	s ace
10785	Vicine	2,6-Diamino-5-(β-*D*-glucopyranosyloxy)-4(1*H*)-pyrimidinone	$C_{10}H_{16}N_4O_7$	152-93-2	304.257	nd (w, dil al, +1 w)	240 dec				sl H_2O, EtOH; vs acid, alk
10786	Vidarabine	β-*D*-9-Arabinofuranosyladenine	$C_{10}H_{13}N_5O_5$	5536-17-4	285.257	nd (w)	257				
10787	Vinblastine		$C_{46}H_{58}N_4O_9$	865-21-4	810.975	nd (MeOH)	216				i H_2O; s EtOH, ace, chl, AcOEt
10788	Vincamine		$C_{21}H_{26}N_2O_3$	1617-90-9	354.442		231.5				
10789	Vinclozolin		$C_{12}H_9Cl_2NO_3$	50471-44-8	286.110		108	$131^{0.05}$	1.51		
10790	Vincristine		$C_{46}H_{56}N_4O_{10}$	57-22-7	824.958		219				
10791	Vinyl acetate		$C_4H_6O_2$	108-05-4	86.090	liq	-93.2	72.8	0.9256^{25}	1.3926^{25}	sl H_2O; msc EtOH; s eth, ace, bz, chl
10792	4-Vinylaniline		C_8H_9N	1520-21-4	119.164		23.5	116^{9}	1.010^{20}	1.6250^{22}	s ace, bz
10793	α-Vinylbenzenemethanol	1-Phenylallyl alcohol	$C_9H_{10}O$	4393-06-0	134.174				1.0249^{21}	1.5406^{20}	sl H_2O; s EtOH, eth, bz, chl
10794	Vinyl butanoate		$C_6H_{10}O_2$	123-20-6	114.142			$116.7; 64^{130}$	0.9006^{20}		
10795	Vinyl *trans*-2-butenoate	Vinyl crotonate	$C_6H_8O_2$	3234-54-6	112.127						s ctc
10796	9-Vinyl-9*H*-carbazole		$C_{14}H_{11}N$	1484-13-5	193.244	cry (al)	66				i H_2O; sl EtOH; vs eth
10797	Vinylcyclohexane		C_8H_{14}	695-12-5	110.197			128	0.8166^{19}	1.455^{19}	
10798	1-Vinylcyclohexene		C_8H_{12}	2622-21-1	108.181			145	0.8623^{15}	1.4915^{20}	i H_2O; s eth, bz; vs MeOH
10799	4-Vinylcyclohexene		C_8H_{12}	100-40-3	108.181	liq	-108.9	128	0.8299^{20}	1.4639^{20}	i H_2O; s eth, bz, peth
10800	Vinylcyclopentane		C_7H_{12}	3742-34-5	96.170	liq	-126.5	97	0.7834^{20}	1.4360^{20}	
10801	Vinyldiethoxymethylsilane		$C_7H_{16}O_2Si$	5507-44-8	160.287			133	0.8620^{20}	1.4001^{20}	
10802	Vinylethoxydimethylsilane		$C_6H_{14}OSi$	5356-83-2	130.260			99	0.790^{20}	1.3983^{20}	
10803	1-Vinyl-4-fluorobenzene		C_8H_7F	405-99-2	122.140		-34.5	$67.4^{50}, 30^{4}$	1.0220^{20}	1.5150^{20}	i H_2O; s EtOH, eth, bz
10804	Vinyl formate		$C_3H_4O_2$	692-45-5	72.063	visc liq	-78	46	0.965^{20}	1.3842^{20}	
10805	2-Vinylfuran		C_6H_6O	1487-18-9	94.111	liq	-94	99.5	0.9445^{19}	1.4992^{19}	
10806	1-Vinyl-2-methoxybenzene		$C_9H_{10}O$	612-15-7	134.174	nd	29	$197; 83^{12}$	1.0049^{17}	1.5388^{20}	vs ace, bz, eth, EtOH
10807	1-Vinyl-3-methoxybenzene		$C_9H_{10}O$	626-20-0	134.174			$91^{15}, 70^{5}$	0.9919^{20}	1.5586^{23}	i H_2O; s EtOH, eth, bz
10808	1-Vinyl-4-methoxybenzene		$C_9H_{10}O$	637-69-4	134.174		2.0	$205; 91^{13}$	1.0001^{13}	1.5642^{13}	i H_2O; s EtOH, eth, bz; sl ctc
10809	6-Vinyl-6-methyl-1-isopropyl-3-(1-methylethylidene) cyclohexene, (*S*)		$C_{15}H_{24}$	5951-67-7	204.352			125^{8}	0.8782^{20}	1.5130^{26}	vs ace, bz
10810	1-Vinylnaphthalene		$C_{12}H_{10}$	826-74-4	154.207			124^{15}	1.0656^{20}	1.644^{20}	
10811	2-Vinylnaphthalene		$C_{12}H_{10}$	827-54-3	154.207		66	$135^{18}, 95^{2}$			i H_2O; s EtOH, ace, bz
10812	1-Vinyl-3-nitrobenzene		$C_8H_7NO_2$	586-39-0	149.148		-10	120^{11}	1.1552^{32}	1.5836^{20}	i H_2O; s EtOH, eth, bz, chl, lig, HOAc
10813	1-Vinyl-4-nitrobenzene		$C_8H_7NO_2$	100-13-0	149.148	pr (lig)	29	dec			vs EtOH, eth; s chl, HOAc, lig
10814	2-Vinyl-5-norbornene	5-Vinylbicyclo[2.2.1]hept-2-ene	C_9H_{12}	3048-64-4	120.191	liq	-80	139	0.841	1.4810^{20}	
10815	Vinyl octadecanoate	Vinyl stearate	$C_{20}H_{38}O_2$	111-63-7	310.515		29	167^{2}	0.8517^{20}		sl chl
10816	3-Vinyl-7-oxabicyclo[4.1.0] heptane		$C_8H_{12}O$	106-86-5	124.180		<-100	$169; 70^{20}$	0.9581^{20}	1.4700^{20}	



DL-Vasicine


L-Vasicine



Verapamil



Veratramine



Veratramine, 3-glucoside



Veratridine



d-Verbenone



Vernolate



Versalide



α-Vetivone



β-Vetivone



Vicine



Vidarabine



Vinblastine



Vincamine



Vinclozolin



Vincristine



Vinyl acetate



4-Vinylaniline



α-Vinylbenzenemethanol



Vinyl butanoate


Vinyl *trans*-2-butenoate



9-Vinyl-9*H*-carbazole


Vinylcyclohexane



1-Vinylcyclohexene



4-Vinylcyclohexene



Vinylcyclopentane



Vinyldiethoxymethylsilane



Vinylethoxydimethylsilane



1-Vinyl-4-fluorobenzene



Vinyl formate



2-Vinylfuran



1-Vinyl-2-methoxybenzene



1-Vinyl-3-methoxybenzene



1-Vinyl-4-methoxybenzene



6-Vinyl-6-methyl-1-isopropyl-3-(1-methylethylidene)cyclohexene, (*S*)



1-Vinylnaphthalene



2-Vinylnaphthalene


1-Vinyl-3-nitrobenzene



1-Vinyl-4-nitrobenzene



2-Vinyl-5-norbornene



Vinyl octadecanoate



3-Vinyl-7-oxabicyclo[4.1.0]heptane


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10817	Vinyloxirane		C_4H_6O	930-22-3	70.090			68	0.9006^{25}	1.4168^{20}	s EtOH, eth, bz
10818	2-(Vinyloxy)ethanol	Ethylene glycol monovinyl ether	$C_4H_8O_2$	764-48-7	88.106			141.6	0.9821^{20}	1.4564^{17}	s H_2O, EtOH, eth, bz; i lig
10819	Vinyl propanoate	Vinyl propionate	$C_5H_8O_2$	105-38-4	100.117			91.2			
10820	2-Vinylpyridine		C_7H_7N	100-69-6	105.138			159.5	0.9983^{20}	1.5495^{20}	sl H_2O; vs EtOH, eth, ace, chl
10821	3-Vinylpyridine		C_7H_7N	1121-55-7	105.138			162	0.9879^{20}	1.5530^{20}	sl H_2O; s EtOH, eth
10822	4-Vinylpyridine		C_7H_7N	100-43-6	105.138	red to dk-br		121^{150}, 79^{33}	0.9879^{20}	1.5449^{20}	s H_2O, EtOH, chl; sl eth
10823	1-Vinyl-2-pyrrolidinone		C_6H_9NO	88-12-0	111.141		13.5	193^{400}, 93^{11}	1.04^{20}		
10824	Vinylsilane		C_2H_6Si	7291-09-0	58.155	col gas	-171.6	-22.8			
10825	Vinyl sulfoxide		C_4H_6OS	1115-15-7	102.155	liq		86^{18}			
10826	Vinyltriacetoxysilane	Vinylsilanetriol, triacetate	$C_8H_{12}O_6Si$	4130-08-9	232.263			115^{10}	1.169^{20}	1.4226^{20}	
10827	Vinyltriethoxysilane		$C_8H_{18}O_3Si$	78-08-0	190.313			160; 62^{20}	0.901^{20}	1.3960^{25}	s chl
10828	Vinyltrimethylsilane		$C_5H_{12}Si$	754-05-2	100.235			55	0.65^{20}	1.3914^{20}	i H_2O
10829	Violaxanthin		$C_{40}H_{56}O_4$	126-29-4	600.871	red pr (MeOH, al-eth)	208				s EtOH, eth, CS_2; i peth
10830	Viquidil		$C_{20}H_{24}N_2O_2$	84-55-9	324.417	red ye amor	60				vs eth, EtOH, chl
10831	Visnadine		$C_{21}H_{24}O_7$	477-32-7	388.412	nd	85.5				i H_2O; s EtOH, eth
10832	Visnagin	4-Methoxy-7-methyl-5*H*-furo[3,2-g][1]benzopyran-5-one	$C_{13}H_{10}O_4$	82-57-5	230.216	nd (w, MeOH)	144.5				sl H_2O, EtOH; vs chl
10833	Vitamin B12	Cyanocobalamin	$C_{63}H_{88}CoN_{14}O_{14}P$	68-19-9	1355.365		>300				
10834	Vitamin D2		$C_{28}H_{44}O$	50-14-6	396.648	pr (ace)	116.5	sub			i H_2O; s EtOH, eth, ace, chl
10835	Vitamin D3	9,10-Secocholesta-5,7,10(19)-trien-3-ol, (3β,5*Z*,7*E*)-	$C_{27}H_{44}O$	67-97-0	384.637		84.5				i H_2O; s os
10836	Vitamin E	α-Tocopherol	$C_{29}H_{50}O_2$	59-02-9	430.706	pale ye oil	3.0	210$^{0.1}$	0.950^{25}	1.5045^{25}	i H_2O; s EtOH, eth, ace, chl
10837	Vitamin E acetate		$C_{31}H_{52}O_3$	58-95-7	472.743		-27.5	184$^{0.01}$	0.9533^{21}	1.497^{20}	i H_2O; sl EtOH; s eth, ace, chl
10838	Vitamin K1		$C_{31}H_{46}O_2$	84-80-0	450.696		-20	142$^{0.001}$	0.964^{25}	1.5250^{25}	i H_2O; s EtOH, eth, ace, bz, peth, chl
10839	Vomicine	4-Hydroxy-19-methyl-16,19-secostrychnidine-10,16-dione	$C_{22}H_{24}N_2O_4$	125-15-5	380.437	nd (80% al) pr (ace)	282				sl EtOH, eth, ace; vs chl; s AcOEt
10840	Warfarin	Coumadin	$C_{19}H_{16}O_4$	81-81-2	308.328	cry (al)	161				i H_2O; s EtOH, ace, diox
10841	9*H*-Xanthene	10*H*-9-Oxaanthracene	$C_{13}H_{10}O$	92-83-1	182.217	ye lf (al)	100.5	311			i H_2O; sl EtOH, ctc; s eth, bz, chl
10842	9*H*-Xanthen-9-ol		$C_{13}H_{10}O_2$	90-46-0	198.217	nd (aq al)	125				sl H_2O; s EtOH, eth, chl
10843	Xanthine		$C_5H_4N_4O_2$	69-89-6	152.112	ye pl (w)	dec	sub			i H_2O
10844	Xanthone		$C_{13}H_8O_2$	90-47-1	196.202	nd (al)	174	351; 146^{3}			i H_2O; s EtOH, eth, bz, chl; sl peth
10845	Xanthopterin		$C_6H_5N_5O_2$	119-44-8	179.137	hyg ye amor or oran pow (HOAc)	>410 dec	99^{18}	1.559^{25}		i H_2O; sl EtOH, eth; vs acid, alk
10846	Xanthosine		$C_{10}H_{12}N_4O_6$	146-80-5	284.225	pr cry (w)					sl cold H_2O; vs hot H_2O; dec acid
10847	Xanthoxyletin		$C_{15}H_{14}O_4$	84-99-1	258.270	pr (MeOH, peth)	133				i H_2O; s EtOH, ace; sl eth; vs bz, alk
10848	Xanthyletin	8,8-Dimethyl-2*H*,8*H*-benzo[1,2-b:5,4-b']dipyran-2-one	$C_{14}H_{12}O_3$	553-19-5	228.243	pr (MeOH)	131.5	142$^{0.1}$			s EtOH, peth
10849	*p*-Xenylcarbimide	4-Isocyanato-1,1'-biphenyl	$C_{13}H_9NO$	92-95-5	195.216	nd	56	dec 283			vs eth
10850	Xibenolol		$C_{15}H_{25}NO_2$	81584-06-7	251.366	cry	57	135$^{0.7}$			s EtOH
10851	*o*-Xylene	1,2-Dimethylbenzene	C_8H_{10}	95-47-6	106.165	liq	-25.2	144.5	0.8802^{10}	1.5055^{20}	i H_2O; msc EtOH, eth, ace, bz, peth, ctc
10852	*m*-Xylene	1,3-Dimethylbenzene	C_8H_{10}	108-38-3	106.165	liq	-47.8	139.12	0.8596^{25}	1.4972^{10}	i H_2O; msc EtOH, eth, ace, bz; s chl
10853	*p*-Xylene	1,4-Dimethylbenzene	C_8H_{10}	106-42-3	106.165	mcl pr (al)	13.25	138.37	0.8566^{25}	1.4958^{20}	i H_2O; msc EtOH, eth, ace, bz; s chl



Vinyloxirane


2-(Vinyloxy)ethanol


Vinyl propanoate



2-Vinylpyridine



3-Vinylpyridine



4-Vinylpyridine


1-Vinyl-2-pyrrolidinone



Vinylsilane



Vinyl sulfoxide


Vinyltriacetoxysilane



Vinyltriethoxysilane



Vinyltrimethylsilane



Violaxanthin



Vitamin B12


R = CN



Viquidil



Visnadine



Visnagin



Vitamin D2



Vitamin D3



Vitamin E



Vitamin E acetate



Vitamin K1



Vomicine



Warfarin



9*H*-Xanthene



9*H*-Xanthen-9-ol



Xanthine



Xanthone



Xanthopterin


Xanthosine


Xanthoxyletin



Xanthyletin


p-Xenylcarbimide



Xibenolol



o-Xylene



m-Xylene



p-Xylene


No.	Name	Synonym	Mol. Form.	CAS RN	Mol. Wt.	Physical Form	mp/°C	bp/°C	den/ g cm^{-3}	n_D	Solubility
10854	2,3-Xylenol	2,3-Dimethylphenol	$C_8H_{10}O$	526-75-0	122.164	nd (w, dil al)	72.5	216.9		1.5420^{20}	sl H_2O; s EtOH, eth
10855	2,4-Xylenol	2,4-Dimethylphenol	$C_8H_{10}O$	105-67-9	122.164	nd (w)	24.5	210.98	0.9650^{20}	1.5420^{14}	sl H_2O; msc EtOH, eth; s ctc
10856	2,5-Xylenol	2,5-Dimethylphenol	$C_8H_{10}O$	95-87-4	122.164	nd (w), pr (al-eth)	74.8	211.1			s H_2O, EtOH; vs eth; sl chl
10857	2,6-Xylenol	2,6-Dimethylphenol	$C_8H_{10}O$	576-26-1	122.164	lf or nd (al)	45.8	201.07			s H_2O, EtOH, eth, ctc
10858	3,4-Xylenol	3,4-Dimethylphenol	$C_8H_{10}O$	95-65-8	122.164		65.1	227	0.9830^{20}		sl H_2O; s EtOH, ctc; msc eth
10859	3,5-Xylenol	3,5-Dimethylphenol	$C_8H_{10}O$	108-68-9	122.164	nd (w, peth)	63.4	221.74	0.9680^{20}		s H_2O, EtOH, ctc
10860	Xylenol orange		$C_{31}H_{32}N_2O_{13}S$	1611-35-4	672.656	dk red cry	286 dec				s H_2O
10861	Xylitol	Xylite	$C_5H_{12}O_5$	87-99-0	152.146	mcl (al)	93.5	216			vs H_2O, py, EtOH
10862	6-*O*-β-*D*-Xylopyranosyl-*D*-glucose	Primeverose	$C_{11}H_{20}O_{10}$	26531-85-1	312.271	cry (MeOH)	210				vs H_2O, MeOH
10863	*D*-Xylose		$C_5H_{10}O_5$	58-86-6	150.130	mcl nd	90.5		1.525^{20}		vs H_2O; s EtOH; sl eth
10864	*D*-Xylulose	*D-threo*-2-Pentulose	$C_5H_{10}O_5$	551-84-8	150.130	visc liq					s H_2O
10865	*L*-Xylulose	*L-threo*-2-Pentulose	$C_5H_{10}O_5$	527-50-4	150.130	syrup					vs H_2O
10866	3,5-Xylyl methylcarbamate	3,5-Dimethylphenyl methylcarbamate	$C_{10}H_{13}NO_2$	2655-14-3	179.216	cry	99				sl H_2O; s os
10867	Yohimbine		$C_{21}H_{26}N_2O_3$	146-48-5	354.442	nd (dil al)	241	sub 160			sl H_2O, bz; s EtOH, eth, chl
10868	Yohimbine hydrochloride	Tosanpin	$C_{21}H_{27}ClN_2O_3$	65-19-0	390.903	orth nd or pl (w, dil HCl)	302				vs H_2O
10869	Zearalenone		$C_{18}H_{22}O_5$	17924-92-4	318.365	cry	164				i H_2O; s alk, bz, EtOH, eth
10870	Zidovudine	3'-Azido-3'-deoxythymidine	$C_{10}H_{13}N_5O_4$	30516-87-1	267.242	cry (w)	121				
10871	Zinc benzoate		$C_{14}H_{10}O_4Zn$	553-72-0	307.636						sl H_2O
10872	Zinc bis(dibutyldithiocarbamate)		$C_{18}H_{36}N_2S_4Zn$	136-23-2	474.161	cry	138				
10873	Zinc *N,N'*-ethylenebisdithiocarbamate	Zineb	$C_4H_6N_2S_4Zn$	12122-67-7	275.773		157 dec				
10874	Zinc gluconate		$C_{12}H_{22}O_{14}Zn$	4468-02-4	455.704	pow					
10875	Zinc 2,4-pentanedioate	Zinc acetylacetonate	$C_{10}H_{14}O_4Zn$	14024-63-6	263.625						s DMSO
10876	Zinc propanoate		$C_6H_{10}O_4Zn$	557-28-8	211.550	hyg pl or nd					sl EtOH
10877	Ziram	Zinc, bis(dimethylcarbamodithioato-*S,S'*)-, (T-4)-	$C_6H_{12}N_2S_4Zn$	137-30-4	305.841	cry	250		1.66^{25}		i H_2O; sl bz; s chl



2,3-Xylenol



2,4-Xylenol



2,5-Xylenol



2,6-Xylenol



3,4-Xylenol



3,5-Xylenol



Xylenol orange



Xylitol



6-*O*-β-*D*-Xylopyranosyl-*D*-glucose



D-Xylose



D-Xylulose



L-Xylulose



3,5-Xylyl methylcarbamate



Yohimbine



Yohimbine hydrochloride



Zearalenone



Zidovudine



Zinc benzoate


Zinc bis(dibutyldithiocarbamate)


Zinc *N*,*N*′-ethylenebisdithiocarbamate


Zinc gluconate


Zinc 2,4-pentanedioate


Zinc propanoate


Ziram

DIAMAGNETIC SUSCEPTIBILITY OF SELECTED ORGANIC COMPOUNDS

When a material is placed in a magnetic field ***H***, a magnetization ***M*** is induced in the material which is related to ***H*** by $\boldsymbol{M} = \kappa \boldsymbol{H}$, where κ is called the volume susceptibility. Since ***H*** and ***M*** have the same dimensions, κ is dimensionless. A more useful parameter is the molar susceptibility χ_m, defined by

$$\chi_m = \kappa V_m = \kappa M/\rho$$

where V_m is the molar volume of the substance, M the molar mass, and ρ the mass density. When the cgs system is used, the customary unit for χ_m is $cm^3\ mol^{-1}$; the corresponding SI unit is $m^3\ mol^{-1}$. Substances with no unpaired electrons are called diamagnetic; they have negative values of χ_m.

This table gives values of the diamagnetic susceptibility for about 400 common organic compounds. All values refer to room temperature and atmospheric pressure and to the physical form that is stable under these conditions. Substances are arranged by molecular formula in Hill order. A more extensive table may be found in Reference 1.

In keeping with customary practice, the molar susceptibility is given here in units appropriate to the cgs system. These values should be multiplied by 4π to obtain values for use in SI equations (where the magnetic field strength ***H*** has units of $A\ m^{-1}$).

References

1. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series,* II/16, *Diamagnetic Susceptibility,* Gupta, R. R., Ed., Springer-Verlag, Heidelberg, 1986.
2. Barter, C., Meisenheimer, R. G., and Stevenson, D. P., *J. Phys. Chem.* 64, 1312, 1960.
3. Broersma, S., *J. Chem. Phys.* 17, 873, 1949.

Molecular formula	Compound	$-\chi_m/10^{-6}\ cm^3\ mol^{-1}$
$CBrCl_3$	Bromotrichloromethane	73.2
CBr_4	Tetrabromomethane	93.7
$CClF_3$	Chlorotrifluoromethane	45.3
CClN	Cyanogen chloride	32.4
CCl_2F_2	Dichlorodifluoromethane	52.2
CCl_2O	Carbonyl chloride	47.9
CCl_3F	Trichlorofluoromethane	58.7
CCl_3NO_2	Trichloronitromethane	75.3
CCl_4	Tetrachloromethane	66.8
$CHBrCl_2$	Bromodichloromethane	66.3
$CHBr_3$	Tribromomethane	82.6
$CHCl_3$	Trichloromethane	58.9
CHI_3	Triiodomethane	117.1
CH_2BrCl	Bromochloromethane	55.1
CH_2Br_2	Dibromomethane	65.1
CH_2Cl_2	Dichloromethane	46.6
CH_2I_2	Diiodomethane	93.1
CH_2N_2	Cyanamide	24.8
CH_2O	Formaldehyde	18.6
CH_2O_2	Formic acid	19.9
CH_3Br	Bromomethane	42.8
CH_3Cl	Chloromethane	32.0
CH_3F	Fluoromethane	17.8
CH_3I	Iodomethane	57.2
CH_3NO	Formamide	23.0
CH_3NO_2	Nitromethane	21.0
CH_4	Methane	17.4
CH_4N_2O	Urea	33.5
CH_4O	Methanol	21.4
CH_5N	Methylamine	27.0
CI_4	Tetraiodomethane	136
CN_4O_8	Tetranitromethane	43.0
C_2ClF_3	Chlorotrifluoroethylene	49.1
C_2Cl_4	Tetrachloroethylene	81.6
C_2Cl_6	Hexachloroethane	112.8
C_2HCl_3	Trichloroethylene	65.8
C_2HCl_3O	Trichloroacetaldehyde	73.0
C_2HCl_3O	Dichloroacetyl chloride	69.0
$C_2HCl_3O_2$	Trichloroacetic acid	73.0
C_2HCl_5	Pentachloroethane	99.1
$C_2HF_3O_2$	Trifluoroacetic acid	43.3
C_2H_2	Acetylene	20.8
$C_2H_2Br_4$	1,1,2,2-Tetrabromoethane	123.4
$C_2H_2Cl_2$	1,1-Dichloroethylene	49.2
$C_2H_2Cl_2$	*cis*-1,2-Dichloroethylene	51.0
$C_2H_2Cl_2$	*trans*-1,2-Dichloroethylene	48.9
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane	89.8
C_2H_3Cl	Chloroethylene	35.9
C_2H_3ClO	Acetyl chloride	39.3
C_2H_3N	Acetonitrile	27.8
C_2H_4	Ethylene	18.8
$C_2H_4Br_2$	1,2-Dibromoethane	78.9
$C_2H_4Cl_2$	1,1-Dichloroethane	57.4
$C_2H_4Cl_2$	1,2-Dichloroethane	59.6
C_2H_4O	Acetaldehyde	22.2
C_2H_4O	Ethylene oxide	30.5
$C_2H_4O_2$	Acetic acid	31.8
$C_2H_4O_2$	Methyl formate	31.1
C_2H_5Br	Bromoethane	78.8
C_2H_5Cl	Chloroethane	69.9
C_2H_5I	Iodoethane	69.1
C_2H_5NO	Acetamide	33.9

Molecular formula	Compound	$-\chi_m/10^{-6}$ cm^3 mol^{-1}
$C_2H_5NO_2$	Nitroethane	35.4
$C_2H_5NO_2$	Glycine	39.6
C_2H_6	Ethane	26.8
C_2H_6O	Ethanol	33.7
C_2H_6O	Dimethyl ether	26.3
$C_2H_6O_2$	Ethylene glycol	38.9
C_2H_6S	Ethanethiol	47.0
C_2H_6S	Dimethyl sulfide	44.9
$C_2H_8N_2$	1,2-Ethanediamine	46.5
C_2N_2	Cyanogen	21.6
C_3H_4	Allene	25.3
$C_3H_4O_2$	Vinyl formate	34.7
C_3H_5Br	3-Bromopropene	58.6
C_3H_5Cl	2-Chloropropene	47.8
C_3H_5Cl	3-Chloropropene	47.8
C_3H_5N	Propanenitrile	38.6
C_3H_6	Propene	30.7
C_3H_6	Cyclopropane	39.2
C_3H_6O	Allyl alcohol	36.7
C_3H_6O	Propanal	34.2
C_3H_6O	Acetone	33.8
C_3H_6O	Methyloxirane	42.5
$C_3H_6O_2$	Propanoic acid	43.2
$C_3H_6O_2$	Ethyl formate	42.4
C_3H_7Br	1-Bromopropane	65.6
C_3H_7Br	2-Bromopropane	65.1
C_3H_7Cl	1-Chloropropane	56.0
C_3H_7I	1-Iodopropane	84.3
C_3H_7N	Allylamine	40.1
$C_3H_7NO_2$	1-Nitropropane	45.0
$C_3H_7NO_2$	2-Nitropropane	45.4
$C_3H_7NO_2$	Ethyl carbamate	57.0
C_3H_8	Propane	38.6
C_3H_8O	1-Propanol	44.8
C_3H_8O	2-Propanol	45.7
$C_3H_8O_2$	1,3-Propylene glycol	50.2
$C_3H_8O_2$	Dimethoxymethane	47.3
$C_3H_8O_3$	Glycerol	57.1
$C_4H_2O_3$	Maleic anhydride	35.8
$C_4H_4N_2$	Pyrazine	37.8
$C_4H_4N_2$	Pyrimidine	43.1
C_4H_4O	Furan	43.1
$C_4H_4O_3$	Succinic anhydride	47.5
$C_4H_4O_4$	Maleic acid	49.6
$C_4H_4O_4$	Fumaric acid	49.1
C_4H_4S	Thiophene	57.3
C_4H_5N	Pyrrole	48.6

Molecular formula	Compound	$-\chi_m/10^{-6}$ cm^3 mol^{-1}
C_4H_6	1,2-Butadiene	35.6
C_4H_6	1,3-Butadiene	32.1
$C_4H_6O_2$	Vinyl acetate	46.4
$C_4H_6O_3$	Acetic anhydride	52.8
$C_4H_6O_4$	Succinic acid	58.0
$C_4H_6O_4$	Dimethyl oxalate	55.7
C_4H_7N	Butanenitrile	50.4
C_4H_8	1-Butene	41.0
C_4H_8	*cis*-2-Butene	42.6
C_4H_8	*trans*-2-Butene	43.3
C_4H_8	Isobutene	40.8
C_4H_8	Cyclobutane	40.0
C_4H_8O	Ethyl vinyl ether	47.9
C_4H_8O	1,2-Epoxybutane	54.8
C_4H_8O	Butanal	45.9
C_4H_8O	2-Butanone	45.6
$C_4H_8O_2$	Butanoic acid	55.2
$C_4H_8O_2$	2-Methylpropanoic acid	56.1
$C_4H_8O_2$	Propyl formate	55.0
$C_4H_8O_2$	Ethyl acetate	54.1
$C_4H_8O_2$	Methyl propanoate	54.5
$C_4H_8O_2$	1,4-Dioxane	52.2
C_4H_9Br	1-Bromobutane	77.1
C_4H_9Br	1-Bromo-2-methylpropane	79.9
C_4H_9Cl	1-Chlorobutane	67.1
C_4H_9Cl	2-Chlorobutane	67.4
C_4H_9I	1-Iodobutane	93.6
C_4H_9N	Pyrrolidine	54.8
C_4H_9NO	Morpholine	55.0
C_4H_{10}	Butane	50.3
C_4H_{10}	Isobutane	50.5
$C_4H_{10}O$	1-Butanol	56.4
$C_4H_{10}O$	2-Butanol	57.6
$C_4H_{10}O$	2-Methyl-1-propanol	57.6
$C_4H_{10}O$	2-Methyl-2-propanol	56.6
$C_4H_{10}O$	Diethyl ether	55.5
$C_4H_{10}O_2$	1,3-Butanediol	61.8
$C_4H_{10}O_2$	1,4-Butanediol	61.8
$C_4H_{10}S$	1-Butanethiol	70.2
$C_4H_{11}N$	Butylamine	58.9
$C_4H_{11}N$	Isobutylamine	59.8
$C_4H_{11}N$	Diethylamine	56.8
$C_5H_4O_2$	Furfural	47.2
C_5H_5N	Pyridine	48.7
$C_5H_6O_2$	Furfuryl alcohol	61.0
$C_5H_7NO_2$	Ethyl cyanoacetate	67.3
C_5H_8	2-Methyl-1,3-butadiene	46.0

Molecular formula	Compound	$-\chi_m/10^{-6}$ cm^3 mol^{-1}
C_5H_8O	Cyclopentanone	51.6
$C_5H_8O_2$	Methyl methacrylate	57.3
$C_5H_8O_2$	2,4-Pentanedione	54.9
C_5H_{10}	1-Pentene	54.6
C_5H_{10}	2-Methyl-2-butene	54.7
C_5H_{10}	Cyclopentane	56.2
$C_5H_{10}O$	Cyclopentanol	64.0
$C_5H_{10}O$	Pentanal	57.5
$C_5H_{10}O$	2-Pentanone	57.5
$C_5H_{10}O$	3-Pentanone	57.7
$C_5H_{10}O_2$	Pentanoic acid	66.5
$C_5H_{10}O_2$	3-Methylbutanoic acid	67.7
$C_5H_{10}O_2$	Butyl formate	65.8
$C_5H_{10}O_2$	Isobutyl formate	66.8
$C_5H_{10}O_2$	Propyl acetate	65.9
$C_5H_{10}O_2$	Isopropyl acetate	67.0
$C_5H_{10}O_2$	Ethyl propanoate	66.3
$C_5H_{10}O_2$	Tetrahydrofurfuryl alcohol	69.4
$C_5H_{10}O_3$	Diethyl carbonate	75.4
$C_5H_{11}N$	Piperidine	64.2
C_5H_{12}	Pentane	61.5
C_5H_{12}	Isopentane	63.0
C_5H_{12}	Neopentane	63.0
$C_5H_{12}O$	1-Pentanol	67.0
$C_5H_{12}O$	2-Pentanol	69.1
$C_5H_{12}O_2$	1,5-Pentanediol	73.5
$C_5H_{13}N$	Pentylamine	69.3
C_6Cl_6	Hexachlorobenzene	147.0
$C_6H_4ClNO_2$	1-Chloro-2-nitrobenzene	75.5
$C_6H_4ClNO_2$	1-Chloro-3-nitrobenzene	77.2
$C_6H_4ClNO_2$	1-Chloro-4-nitrobenzene	74.7
$C_6H_4Cl_2$	*o*-Dichlorobenzene	84.4
$C_6H_4Cl_2$	*m*-Dichlorobenzene	84.1
$C_6H_4Cl_2$	*p*-Dichlorobenzene	81.7
$C_6H_4O_2$	*p*-Benzoquinone	36
C_6H_5Br	Bromobenzene	78.4
C_6H_5Cl	Chlorobenzene	69.5
C_6H_5ClO	*o*-Chlorophenol	77.3
C_6H_5ClO	*m*-Chlorophenol	77.6
C_6H_5ClO	*p*-Chlorophenol	77.7
C_6H_5F	Fluorobenzene	58.4
C_6H_5I	Iodobenzene	92.0
$C_6H_5NO_2$	Nitrobenzene	61.9
$C_6H_5NO_3$	*o*-Nitrophenol	68.9
$C_6H_5NO_3$	*m*-Nitrophenol	65.9
$C_6H_5NO_3$	*p*-Nitrophenol	66.9
C_6H_6	Benzene	54.8

Molecular formula	Compound	$-\chi_m/10^{-6}$ cm^3 mol^{-1}
C_6H_6ClN	*o*-Chloroaniline	79.5
C_6H_6ClN	*m*-Chloroaniline	76.6
C_6H_6ClN	*p*-Chloroaniline	76.7
$C_6H_6N_2O_2$	*o*-Nitroaniline	67.4
$C_6H_6N_2O_2$	*m*-Nitroaniline	69.7
$C_6H_6N_2O_2$	*p*-Nitroaniline	68.0
C_6H_6O	Phenol	60.6
$C_6H_6O_2$	*p*-Hydroquinone	64.7
$C_6H_6O_2$	Pyrocatechol	68.2
$C_6H_6O_2$	Resorcinol	67.2
C_6H_7N	Aniline	62.4
C_6H_7N	4-Methylpyridine	59.8
C_6H_8	1,4-Cyclohexadiene	48.7
$C_6H_8N_2$	*o*-Phenylenediamine	72.5
$C_6H_8N_2$	*m*-Phenylenediamine	70.4
$C_6H_8N_2$	*p*-Phenylenediamine	70.7
C_6H_{10}	1,5-Hexadiene	55.1
C_6H_{10}	1-Hexyne	64.5
C_6H_{10}	Cyclohexene	58.0
$C_6H_{10}O$	Cyclohexanone	62.0
$C_6H_{10}O_3$	Ethyl acetoacetate	71.7
$C_6H_{10}O_4$	Diethyl oxalate	81.7
C_6H_{12}	1-Hexene	66.4
C_6H_{12}	2,3-Dimethyl-2-butene	65.9
C_6H_{12}	Cyclohexane	68
C_6H_{12}	Methylcyclopentane	70.2
$C_6H_{12}O$	Hexanal	69.4
$C_6H_{12}O$	2-Hexanone	69.2
$C_6H_{12}O$	3-Hexanone	69.0
$C_6H_{12}O$	4-Methyl-2-pentanone	69.7
$C_6H_{12}O$	Cyclohexanol	73.4
$C_6H_{12}O_2$	Hexanoic acid	78.1
$C_6H_{12}O_2$	Isopentyl formate	78.4
$C_6H_{12}O_2$	Isobutyl acetate	78.7
$C_6H_{12}O_2$	Propyl propanoate	77.7
$C_6H_{12}O_3$	Paraldehyde	86.1
C_6H_{14}	Hexane	74.1
C_6H_{14}	2-Methylpentane	75.3
C_6H_{14}	3-Methylpentane	75.5
C_6H_{14}	2,2-Dimethylbutane	76.2
C_6H_{14}	2,3-Dimethylbutane	76.2
$C_6H_{14}O$	1-Hexanol	79.5
$C_6H_{14}O$	4-Methyl-2-pentanol	80.4
$C_6H_{14}O$	Dipropyl ether	79.4
$C_6H_{14}O_2$	1,6-Hexanediol	84.3
$C_6H_{14}O_2$	1,1-Diethoxyethane	81.4
$C_6H_{14}O_6$	*D*-Glucitol	107.8

Molecular formula	Compound	$-\chi_m/10^{-6}$ cm^3 mol^{-1}
$C_6H_{15}N$	Triethylamine	83.3
C_7H_5N	Benzonitrile	65.2
C_7H_6O	Benzaldehyde	60.7
$C_7H_6O_2$	Salicylaldehyde	66.8
$C_7H_6O_3$	Salicylic acid	75
C_7H_7Br	*p*-Bromotoluene	88.7
C_7H_7Cl	*o*-Chlorotoluene	82.4
C_7H_7Cl	*m*-Chlorotoluene	79.7
C_7H_7Cl	*p*-Chlorotoluene	80.3
C_7H_7Cl	(Chloromethyl)benzene	81.6
C_7H_7NO	Benzamide	72.0
$C_7H_7NO_2$	*o*-Nitrotoluene	72.2
$C_7H_7NO_2$	*m*-Nitrotoluene	72.7
$C_7H_7NO_2$	*p*-Nitrotoluene	73.3
C_7H_8	Toluene	65.6
C_7H_8O	*o*-Cresol	73.3
C_7H_8O	*m*-Cresol	72.2
C_7H_8O	*p*-Cresol	72.4
C_7H_8O	Benzyl alcohol	71.8
C_7H_8O	Anisole	72.2
C_7H_9N	*o*-Methylaniline	74.9
C_7H_9N	*m*-Methylaniline	74.6
C_7H_9N	*p*-Methylaniline	72.5
C_7H_9N	*N*-Methylaniline	74.1
C_7H_9N	2,4-Dimethylpyridine	71.3
C_7H_9N	2,6-Dimethylpyridine	72.5
C_7H_9NO	*o*-Methoxyaniline [*o*-Anisidine]	79.1
$C_7H_{12}O_4$	Diethyl malonate	92.6
C_7H_{14}	1-Heptene	77.8
C_7H_{14}	Cycloheptane	73.9
C_7H_{14}	Methylcyclohexane	78.9
$C_7H_{14}O$	1-Heptanal	81.0
$C_7H_{14}O$	2-Heptanone	80.5
$C_7H_{14}O$	3-Heptanone	80.7
$C_7H_{14}O$	4-Heptanone	80.5
$C_7H_{14}O$	2,4-Dimethyl-3-pentanone	81.1
$C_7H_{14}O_2$	Heptanoic acid	89.0
$C_7H_{14}O_2$	Pentyl acetate	88.9
$C_7H_{14}O_2$	Isopentyl acetate	89.4
$C_7H_{14}O_2$	Butyl propanoate	89.1
$C_7H_{14}O_2$	Ethyl 3-methylbutanoate	91.1
C_7H_{16}	Heptane	85.2
C_7H_{16}	3-Ethylpentane	86.2
C_7H_{16}	2,2-Dimethylpentane	87.0
C_7H_{16}	2,3-Dimethylpentane	87.5
C_7H_{16}	2,4-Dimethylpentane	87.5

Molecular formula	Compound	$-\chi_m/10^{-6}$ cm^3 mol^{-1}
C_7H_{16}	3,3-Dimethylpentane	89.5
$C_7H_{16}O$	1-Heptanol	91.7
$C_7H_{16}O$	4-Heptanol	92.1
$C_8H_4O_3$	Phthalic anhydride	66.7
$C_8H_6O_4$	Phthalic acid	83.6
$C_8H_6O_4$	Isophthalic acid	84.6
$C_8H_6O_4$	Terephthalic acid	83.5
C_8H_7N	Benzeneacetonitrile	76.9
C_8H_7N	Indole	85.0
C_8H_8	Styrene	68.2
C_8H_8O	Acetophenone	72.5
$C_8H_8O_2$	*o*-Toluic acid	84.3
$C_8H_8O_2$	*m*-Toluic acid	83.0
$C_8H_8O_2$	*p*-Toluic acid	82.4
$C_8H_8O_2$	Benzeneacetic acid	82.4
$C_8H_8O_2$	Methyl benzoate	81.6
$C_8H_8O_3$	Methyl salicylate	86.6
C_8H_{10}	Ethylbenzene	77.3
C_8H_{10}	*o*-Xylene	77.7
C_8H_{10}	*m*-Xylene	76.4
C_8H_{10}	*p*-Xylene	77.0
$C_8H_{10}O$	Phenetole	84.5
$C_8H_{11}N$	*N*-Ethylaniline	85.6
$C_8H_{11}N$	*N,N*-Dimethylaniline	85.1
$C_8H_{11}N$	2,4,6-Trimethylpyridine	83.1
$C_8H_{14}O_4$	Ethyl succinate	105.0
C_8H_{16}	1-Octene	88.8
C_8H_{16}	Cyclooctane	85.3
$C_8H_{16}O_2$	Octanoic acid	99.5
$C_8H_{16}O_2$	Hexyl acetate	100.9
$C_8H_{17}Cl$	1-Chlorooctane	114.9
C_8H_{18}	Octane	96.6
C_8H_{18}	4-Methylheptane	97.3
C_8H_{18}	3-Ethylhexane	97.8
C_8H_{18}	3,4-Dimethylhexane	99.1
C_8H_{18}	2,2,4-Trimethylpentane	99.1
C_8H_{18}	2,3,4-Trimethylpentane	99.8
$C_8H_{18}O$	1-Octanol	101.6
$C_8H_{19}N$	Dibutylamine	103.7
C_9H_7N	Quinoline	86.1
C_9H_7N	Isoquinoline	83.9
C_9H_8	Indene	83
C_9H_{10}	Isopropenylbenzene	80.0
$C_9H_{10}O_2$	Ethyl benzoate	93.8
$C_9H_{10}O_2$	Benzyl acetate	93.2
C_9H_{12}	Propylbenzene	89.1

Molecular formula	Compound	$-\chi_m/10^{-6}$ cm^3 mol^{-1}
C_9H_{12}	Isopropylbenzene [Cumene]	89.5
C_9H_{12}	1,3,5-Trimethylbenzene [Mesitylene]	92.3
C_9H_{18}	1-Nonene	100.1
$C_9H_{18}O$	2,6-Dimethyl-4-heptanone	104.3
C_9H_{20}	Nonane	108.1
$C_{10}H_7Br$	1-Bromonaphthalene	123.6
$C_{10}H_7Cl$	1-Chloronaphthalene	107.6
$C_{10}H_8$	Naphthalene	91.6
$C_{10}H_8$	Azulene	123.7
$C_{10}H_8O$	1-Naphthol	96.2
$C_{10}H_8O$	2-Naphthol	96.8
$C_{10}H_9N$	1-Naphthalenamine	92.5
$C_{10}H_9N$	2-Naphthalenamine	98.0
$C_{10}H_{10}O_2$	Safrole	97.5
$C_{10}H_{10}O_4$	Dimethyl terephthalate	101.6
$C_{10}H_{14}$	Butylbenzene	100.7
$C_{10}H_{14}$	*tert*-Butylbenzene	101.8
$C_{10}H_{14}$	Isobutylbenzene	101.7
$C_{10}H_{14}$	*p*-Cymene	102.8
$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	101.2
$C_{10}H_{14}O$	*p-tert*-Butylphenol	108.0
$C_{10}H_{15}N$	*N,N*-Diethylaniline	107.9
$C_{10}H_{16}$	*d*-Limonene	98.0
$C_{10}H_{16}$	α-Pinene	100.7
$C_{10}H_{16}$	β-Pinene	101.9
$C_{10}H_{16}O$	Camphor, (+)	103.0
$C_{10}H_{18}$	*cis*-Decahydronaphthalene	107.0
$C_{10}H_{18}$	*trans*-Decahydronaphthalene	107.6
$C_{10}H_{22}$	Decane	119.5
$C_{11}H_{10}$	1-Methylnaphthalene	102.9
$C_{11}H_{10}$	2-Methylnaphthalene	102.7
$C_{11}H_{24}$	Undecane	131.8
$C_{12}H_8$	Acenaphthylene	111.6
$C_{12}H_9N$	Carbazole	119.9
$C_{12}H_{10}$	Acenaphthene	109.9
$C_{12}H_{10}$	Biphenyl	103.3
$C_{12}H_{10}N_2$	Azobenzene	106.8
$C_{12}H_{11}N$	Diphenylamine	108.4
$C_{12}H_{14}O_4$	Diethyl phthalate	127.5
$C_{12}H_{18}$	Hexamethylbenzene	122.5
$C_{12}H_{24}O_2$	Dodecanoic acid	113.0
$C_{13}H_9N$	Acridine	118.8
$C_{13}H_{10}O$	Benzophenone	109.6
$C_{13}H_{12}$	Diphenylmethane	116.0
$C_{13}H_{28}$	Tridecane	153.7
$C_{14}H_8O_2$	9,10-Anthracenedione	113.0
$C_{14}H_{10}$	Anthracene	129.8
$C_{14}H_{10}$	Phenanthrene	127.6
$C_{14}H_{10}$	Diphenylacetylene	116
$C_{14}H_{10}O_2$	Benzil	106.8
$C_{14}H_{12}O_2$	Benzyl benzoate	132.2
$C_{14}H_{14}$	1,2-Diphenylethane	127.8
$C_{14}H_{28}O_2$	Tetradecanoic acid [Myristic acid]	176.0
$C_{14}H_{30}$	Tetradecane	166.2
$C_{16}H_{10}$	Pyrene	147
$C_{16}H_{32}O_2$	Hexadecanoic acid [Palmitic acid]	198.6
$C_{16}H_{34}$	Hexadecane	187.6
$C_{16}H_{34}O$	1-Hexadecanol	183.5
$C_{18}H_{12}$	Chrysene	148.0
$C_{18}H_{14}$	*o*-Terphenyl	150.4
$C_{18}H_{14}$	*m*-Terphenyl	155.5
$C_{18}H_{14}$	*p*-Terphenyl	156.0
$C_{18}H_{34}O_2$	*cis*-9-Octadecenoic acid [Oleic acid]	208.5
$C_{18}H_{36}O_2$	Octadecanoic acid [Stearic acid]	220.8
$C_{20}H_{12}$	Perylene	167.5

THE ELEMENTS

C. R. Hammond

One of the most striking facts about the elements is their unequal distribution and occurrence in nature. Present knowledge of the chemical composition of the universe, obtained from the study of the spectra of stars and nebulae, indicates that hydrogen is by far the most abundant element and may account for more than 90% of the atoms or about 75% of the mass of the universe. Helium atoms make up most of the remainder. All of the other elements together contribute only slightly to the total mass.

The chemical composition of the universe is undergoing continuous change. Hydrogen is being converted into helium, and helium is being changed into heavier elements. As time goes on, the ratio of heavier elements increases relative to hydrogen. Presumably, the process is not reversible.

Burbidge, Burbidge, Fowler, and Hoyle, and more recently, Peebles, Penzias, and others have studied the synthesis of elements in stars. To explain all of the features of the nuclear abundance curve — obtained by studies of the composition of the earth, meteorites, stars, etc. — it is necessary to postulate that the elements were originally formed by at least eight different processes: (1) hydrogen burning, (2) helium burning, (3) χ process, (4) *e* process, (5) *s* process, (6) *r* process, (7) *p* process, and (8) the X process. The X process is thought to account for the existence of light nuclei such as D, Li, Be, and B. Common metals such as Fe, Cr, Ni, Cu, Ti, Zn, etc. were likely produced early in the history of our galaxy. It is also probable that most of the heavy elements on earth and elsewhere in the universe were originally formed in supernovae, or in the hot interior of stars.

Studies of the solar spectrum have led to the identification of 67 elements in the sun's atmosphere; however, all elements cannot be identified with the same degree of certainty. Other elements may be present in the sun, although they have not yet been detected spectroscopically. The element helium was discovered on the sun before it was found on earth. Some elements such as scandium are relatively more plentiful in the sun and stars than here on earth.

Minerals in lunar rocks brought back from the moon on the Apollo missions consist predominantly of *plagioclase* $\{(Ca,Na)(Al,Si)O_4O_8\}$ and *pyroxene* $\{(Ca,Mg,Fe)_2Si_2O_6\}$ — two minerals common in terrestrial volcanic rock. No new elements have been found on the moon that cannot be accounted for on earth; however, three minerals, *armalcolite* $\{(Fe,Mg)Ti_2O_5\}$, *pyroxferroite* $\{CaFe_6(SiO_3)_7\}$, and *tranquillityite* $\{Fe_8(Zr,Y)Ti_3Si_3O_2\}$, are new. The oldest known terrestrial rocks are about 4 billion years old. One rock, known as the "Genesis Rock," brought back from the Apollo 15 Mission, is about 4.15 billion years old. This is only about one-half billion years younger than the supposed age of the moon and solar system. Lunar rocks appear to be relatively enriched in refractory elements such as chromium, titanium, zirconium, and the rare earths, and impoverished in volatile elements such as the alkali metals, in chlorine, and in noble metals such as nickel, platinum, and gold.

Even older than the "Genesis Rock" are *carbonaceous chondrites,* a type of meteorite that has fallen to earth and has been studied. These are some of the most primitive objects of the solar system yet found. The grains making up these objects probably condensed directly out the gaseous nebula from which the sun and planets were born. Most of the condensation of the grains probably was completed within 50,000 years of the time the disk of the nebula was first formed — about 4.6 billion years ago. It is now thought that this type of meteorite may contain a small percentage of presolar dust grains. The relative abundances of the elements of these meteorites are about the same as the abundances found in the solar chromosphere.

The X-ray fluorescent spectrometer sent with the Viking I spacecraft to Mars shows that the Martian soil contains about 12 to 16% iron, 14 to 15% silicon, 3 to 8% calcium, 2 to 7% aluminum, and one-half to 2% titanium. The gas chromatograph — mass spectrometer on Viking II found no trace of organic compounds that should be present if life ever existed there.

F. W. Clarke and others have carefully studied the composition of rocks making up the crust of the earth. Oxygen accounts for about 47% of the crust, by weight, while silicon comprises about 28% and aluminum about 8%. These elements, plus iron, calcium, sodium, potassium, and magnesium, account for about 99% of the composition of the crust.

Many elements such as tin, copper, zinc, lead, mercury, silver, platinum, antimony, arsenic, and gold, which are so essential to our needs and civilization, are among some of the rarest elements in the earth's crust. These are made available to us only by the processes of concentration in ore bodies. Some of the so-called *rare-earth* elements have been found to be much more plentiful than originally thought and are about as abundant as uranium, mercury, lead, or bismuth. The least abundant rare-earth or *lanthanide* element, thulium, is now believed to be more plentiful on earth than silver, cadmium, gold, or iodine, for example. Rubidium, the 16th most abundant element, is more plentiful than chlorine while its compounds are little known in chemistry and commerce.

It is now thought that at least 24 elements are essential to living matter. The four most abundant in the human body are hydrogen, oxygen, carbon, and nitrogen. The seven next most common, in order of abundance, are calcium, phosphorus, chlorine, potassium, sulfur, sodium, and magnesium. Iron, copper, zinc, silicon, iodine, cobalt, manganese, molybdenum, fluorine, tin, chromium, selenium, and vanadium are needed and play a role in living matter. Boron is also thought essential for some plants, and it is possible that aluminum, nickel, and germanium may turn out to be necessary.

Ninety-one elements occur naturally on earth. Minute traces of plutonium-244 have been discovered in rocks mined in Southern California. This discovery supports the theory that heavy elements were produced during creation of the solar system. While technetium and promethium have not yet been found naturally on earth, they have been found to be present in stars. Technetium has been identified in the spectra of certain "late" type stars, and promethium lines have been identified in the spectra of a faintly visible star HR465 in Andromeda. Promethium must have been made very recently near the star's surface for no known isotope of this element has a half-life longer than 17.7 years.

It has been suggested that californium is present in certain stellar explosions known as supernovae; however, this has not been proved. At present no elements are found elsewhere in the universe that cannot be accounted for here on earth.

All atomic mass numbers from 1 to 238 are found naturally on earth except for masses 5 and 8. About 285 relatively stable and 67 naturally radioactive isotopes occur on earth totaling 352. In addition, the neutron, technetium, promethium, and the transuranic elements (lying beyond uranium) have now been produced artificially. In June 1999, scientists at the Lawrence Berkeley National Laboratory reported that they had found evidence of an isotope

of Element 118 and its immediate decay products of Elements 116, 114, and 112. This sequence of events tended to reinforce the theory that was predicted since the 1970s that an "island of stability" existed for nuclei with approximately 114 protons and 184 neutrons. This "island" refers to nuclei in which the decay lasts for a period of time instead of a decay that occurs instantaneously. However, on July 27, 2001, researchers at LBNL reported that their laboratory and the facilities at the GSI Laboratory in Germany and at Japanese laboratories failed to confirm the results of their earlier experiments where the fusion of a krypton atom with a lead target resulted in Element 118, with chains of decay leading to Elements 116, 114, and 112, and on down to Element 106. Therefore, the discovery was reported to be spurious. However, with the announcement it was said that different experiments at the Livermore Laboratory and Joint Institute for Nuclear Research in Dubna, Russia indicated that Element 116 had since been created directly. (See also under Elements 116 and 118.)

Laboratory processes have now extended the radioactive element mass numbers beyond 238 to about 280. Each element from atomic numbers 1 to 110 is known to have at least one radioactive isotope. As of December 2001, about 3286 isotopes and isomers were thought to be known and recognized. Many stable and radioactive isotopes are now produced and distributed by the Oak Ridge National Laboratory, Oak Ridge, Tenn., U.S.A., to customers licensed by the U.S. Department of Energy.

The nucleus of an atom is characterized by the number of protons it contains, denoted by *Z*, and by the number of neutrons, *N*. Isotopes of an element have the same value of *Z*, but different values of *N*. The *mass number A*, is the sum of *Z* and *N*. For example, Uranium-238 has a mass number of 238, and contains 92 protons and 146 neutrons.

There is evidence that the definition of chemical elements must be broadened to include the electron. Several compounds known as *electrides,* have recently been made of alkaline metal elements and electrons. A relatively stable combination of a positron and electron, known as *positronium,* has also been studied.

The well-known proton, neutron, and electron are now thought to be members of a group that includes other fundamental particles that have been discovered or hypothesized by physicists. These very elemental particles, of which all matter is made, are now thought to belong to one of two families: namely, **quarks** or **leptons**. Each of these two families consists of six particles. Also, there are four different force carriers that lead to interactions between particles. The six members or "flavors" of the quark family are called **up**, **charm**, **top**, **down**, **strange**, and **bottom**. The force carriers for the quarks are the **gluon** and the **photon**. The six members of the lepton family are the **e neutrino**, the **mu neutrino**, the **tau neutrino**, the **electron**, the **muon particle**, and the **tau particle**. The force carriers for these are the **w boson** and the **z boson**. Furthermore, it appears that each of these particles has an anti-particle that has an opposite electrical charge from the above particles.

Quarks are not found individually, but are found with other quarks arranged to form composites known as **hadrons**. There are two basic types of hadrons: **baryons**, composed of three quarks, and **mesons**, composed of a quark and an anti-quark. Examples of baryons are the neutron and the proton. Neutrons are made of two down quarks and one up quark. Protons are made of two up quarks and one down quark. An example of the meson is the **pion**. This particle is made of an up quark and a down anti-quark. Such particles are unstable and tend to decay rapidly. The anti-particle of the proton is the anti-proton. The exception to the rule is the electron, whose anti-particle is the **positron**.

In recent years a search has been made for a hypothetical particle known as the **Higgs particle** or **Higgs boson**, suggested in 1966 by Peter Higgs of the University of Edinburgh, which could possibly explain why the carriers of the "electro-weak" field (w and z bosons) have mass. The Higgs particle is thought to be responsible possibly for the mass of objects throughout the universe.

Many physicists now hold that all matter and energy in the universe is controlled by four fundamental forces: the **electromagnetic force**, **gravity**, a **weak nuclear force**, and a **strong nuclear force**. The **gluon** binds quarks together by carrying the strong nuclear force. Each of these natural forces is passed back and forth among the basic particles of matter by the force carriers mentioned above. The electromagnetic force is carried by the photon, the weak nuclear force by the **intermediate vector boson**, and the gravity by the **graviton**.

For more complete information on these fundamental particles, please consult recent articles and books on nuclear or particle physics.

The available evidence leads to the conclusion that elements 89 (actinium) through 103 (lawrencium) are chemically similar to the rare-earth or lanthanide elements (elements 57 to 71, inclusive). These elements therefore have been named *actinides* after the first member of this series. Those elements beyond uranium that have been produced artificially have the following names and symbols: neptunium, 93 (Np); plutonium, 94 (Pu); americium, 95 (Am); curium, 96 (Cm); berkelium, 97 (Bk); californium, 98 (Cf); einsteinium, 99 (Es); fermium, 100 (Fm); mendelevium, 101 (Md); nobelium, 102 (No); and lawrencium, 103 (Lr). It is now claimed that Elements 104 through 112 have been produced and identified. More recently, Elements 118, 116, and 114 were reported found (see Element 118). In August 1997, the International Union of Pure and Applied Chemistry (IUPAC) gave final approval to the following names for Elements 104 to 109: Element 104 — rutherfordium (Rf); Element 105 — dubnium (Db); Element 106 — seaborgium (Sg); Element 107 — bohrium (Bh); Element 108 — hassium (Hs); and Element 109 — meitnerium (Mt). The recently discovered elements 110, 111, 112, 114, etc. have not yet been named, but may carry temporary names as designated by the International Union of Pure and Applied Chemistry. IUPAC recommends that until the existence of a new element is proven to their satisfaction, the elements are to have names and symbols derived according to these precise and simple rules: The name is based on the digits in the element's atomic number. Each digit is replaced with these expressions, with the end using the usual –ium suffix as follows: **0 nil, 1 un, 2 bi, 3 tri, 4 quad, 5 pent, 6 hex, 7 sept, 8 oct, 9 enn**. Double letter i's are not used, as for example Ununbiium, but would be Ununbium. The symbol used would be the first letter of the three main syllables. For example, Element 126 would be Unbihexium, with the symbol Ubh. It is thought there is a possibility of producing elements beyond Element 116 and discovering Elements 117, 115, and 113 by altering the beams of ions and the targets from those now being used.

There are many claims in the literature of the existence of various allotropic modifications of the elements, some of which are based on doubtful or incomplete evidence. Also, the physical properties of an element may change drastically by the presence of small amounts of impurities. With new methods of purification, which are now able to produce elements with 99.9999% purity, it has been necessary to restudy the properties of the elements. For example, the melting point of thorium changes by several hundred degrees by the presence of a small percentage of ThO_2 as an impurity. Ordinary commercial tungsten is brittle and can be worked only with difficulty. Pure tungsten, however, can be cut with a

hacksaw, forged, spun, drawn, or extruded. In general, the value of a physical property given here applies to the pure element, when it is known.

Many of the chemical elements and their compounds are toxic and should be handled with due respect and care. In recent years there has been a greatly increased knowledge and awareness of the health hazards associated with chemicals, radioactive materials, and other agents. Anyone working with the elements and certain of their compounds should become thoroughly familiar with the proper safeguards to be taken. Information on specific hazards and recommended exposure limits may also be found in Section 16. Reference should also be made to publications such as the following:

1. *Code of Federal Regulations, Title 29, Labor.* With additions found in issues of the *Federal Register*.
2. *Code of Federal Regulations, Title 10, Energy.* With additions found in issues of the *Federal Register*. (Published by the U.S. Government Printing Office. Supt. of Documents.)
3. *Occupational Safety and Health Reporter* (latest edition with amendments and corrections), Bureau of National Affairs, Washington, D.C.
4. *Atomic Energy Law Reporter,* Commerce Clearing House, Chicago, IL.
5. *Nuclear Regulation Reporter,* Commerce Clearing House, Chicago, IL.
6. *TLVs® Threshold Limit Values for Chemical Substances and Physical Agents* is issued annually be the American Conference of Governmental Industrial Hygienists, Cincinnati, Ohio.
7. *The Sigma Aldrich Library of Regulatory and Safety Data. Vol. 3,* Robert E. Lenga and Kristine L. Volonpal, Sigma Chemical Co. and Aldrich Chemical Co., Inc. 1993.
8. *Hazardous Chemicals Desk Reference,* Richard J. Lewis, Sr., 4th ed., John Wiley & Sons, New York, Dec. 1997.
9. *Sittig's Handbook of Toxic and Hazardous Chemicals and Carcinogens,* 3rd ed., Noyes Publications, 2001/2.
10. *Sax's Dangerous Properties of Industrial Materials*, Richard J. Lewis and N. Irving Sax, John Wiley & Sons, New York, 1999.
11. *World Wide Limits for Toxic and Hazardous Chemicals in Air, Water, and Soil,* Marshall Sittig, Noyes Publishers.

The prices of elements as indicated in this article are intended to be only a rough guide. Prices may vary, over time, widely with supplier, quantity, and purity.

Actinium — (Gr. *aktis, aktinos,* beam or ray), Ac; at. wt. (227); at. no. 89; m.p. 1051°C, b.p. 3200 ± 300°C (est.); sp. gr. 10.07 (calc.). Discovered by Andre Debierne in 1899 and independently by F. Giesel in 1902. Occurs naturally in association with uranium minerals. Thirty four isotopes and isomers are now recognized. All are radioactive. Actinium-227, a decay product of uranium-235, is an alpha and beta emitter with a 21.77-year half-life. Its principal decay products are thorium-227 (18.72-day half-life), radium-223 (11.4-day half-life), and a number of short-lived products including radon, bismuth, polonium, and lead isotopes. In equilibrium with its decay products, it is a powerful source of alpha rays. Actinium metal has been prepared by the reduction of actinium fluoride with lithium vapor at about 1100 to 1300°C. The chemical behavior of actinium is similar to that of the rare earths, particularly lanthanum. Purified actinium comes into equilibrium with its decay products at the end of 185 days, and then decays according to its 21.77-year half-life. It is about 150 times as active as radium, making it of value in the production of neutrons. Actinium-225, with a purity of 99%, is available from the Oak Ridge National Laboratory to holders of a permit for about $500/millicurie, plus packing charges.

Aluminum — (L. *alumen, alum*), Al; at. wt. 26.981539(5); at. no. 13; f.p. 660.323°C; b.p. 2519°C; sp. gr. 2.6989 (20°C); valence 3. The ancient Greeks and Romans used *alum* in medicine as an astringent, and as a mordant in dyeing. In 1761 de Morveau proposed the name *alumine* for the base in alum, and Lavoisier, in 1787, thought this to be the oxide of a still undiscovered metal. Wohler is generally credited with having isolated the metal in 1827, although an impure form was prepared by Oersted two years earlier. In 1807, Davy proposed the name *alumium* for the metal, undiscovered at that time, and later agreed to change it to *aluminum*. Shortly thereafter, the name *aluminium* was adopted to conform with the "ium" ending of most elements, and this spelling is now in use elsewhere in the world. *Aluminium* was also the accepted spelling in the U.S. until 1925, at which time the American Chemical Society officially decided to use the name *aluminum* thereafter in their publications. The method of obtaining aluminum metal by the electrolysis of alumina dissolved in *cryolite* was discovered in 1886 by Hall in the U.S. and at about the same time by Heroult in France. Cryolite, a natural ore found in Greenland, is no longer widely used in commercial production, but has been replaced by an artificial mixture of sodium, aluminum, and calcium fluorides. *Bauxite,* an impure hydrated oxide ore, is found in large deposits in Jamaica, Australia, Suriname, Guyana, Russia, Arkansas, and elsewhere. The Bayer process is most commonly used today to refine bauxite so it can be accommodated in the Hall-Heroult refining process, used to make most aluminum. Aluminum can now be produced from clay, but the process is not economically feasible at present. Aluminum is the most abundant metal to be found in the earth's crust (8.1%), but is never found free in nature. In addition to the minerals mentioned above, it is found in feldspars, granite, and in many other common minerals. Twenty-two isotopes and isomers are known. Natural aluminum is made of one isotope, ^{27}Al. Pure aluminum, a silvery-white metal, possesses many desirable characteristics. It is light, nontoxic, has a pleasing appearance, can easily be formed, machined, or cast, has a high thermal conductivity, and has excellent corrosion resistance. It is nonmagnetic and nonsparking, stands second among metals in the scale of malleability, and sixth in ductility. It is extensively used for kitchen utensils, outside building decoration, and in thousands of industrial applications where a strong, light, easily constructed material is needed. Although its electrical conductivity is only about 60% that of copper, it is used in electrical transmission lines because of its light weight. Pure aluminum is soft and lacks strength, but it can be alloyed with small amounts of copper, magnesium, silicon, manganese, and other elements to impart a variety of useful properties. These alloys are of vital importance in the construction of modern aircraft and rockets. Aluminum, evaporated in a vacuum, forms a highly reflective coating for both visible light and radiant heat. These coatings soon form a thin layer of the protective oxide and do not deteriorate as do silver coatings. They have found application in coatings for telescope mirrors, in making decorative paper, packages, toys, and in many other uses. The compounds of greatest importance are aluminum oxide, the sulfate, and

the soluble sulfate with potassium (alum). The oxide, alumina, occurs naturally as ruby, sapphire, corundum, and emery, and is used in glassmaking and refractories. Synthetic ruby and sapphire have found application in the construction of lasers for producing coherent light. In 1852, the price of aluminum was about $1200/kg, and just before Hall's discovery in 1886, about $25/kg. The price rapidly dropped to 60¢ and has been as low as 33¢/kg. The price in December 2001 was about 64¢/lb or $1.40/kg.

Americium — (the Americas), Am; at. wt. 243; at. no. 95; m.p. 1176°C; b.p. 2011°C; sp. gr. 13.67 (20°C); valence 2, 3, 4, 5, or 6. Americium was the fourth transuranium element to be discovered; the isotope ^{241} Am was identified by Seaborg, James, Morgan, and Ghiorso late in 1944 at the wartime Metallurgical Laboratory of the University of Chicago as the result of successive neutron capture reactions by plutonium isotopes in a nuclear reactor:

$$^{239}\text{Pu(n,}\gamma) \rightarrow ^{240}\text{Pu(n,}\gamma) \rightarrow ^{241}\text{Pu} \xrightarrow{\beta} ^{241}\text{Am}$$

Since the isotope ^{241}Am can be prepared in relatively pure form by extraction as a decay product over a period of years from strongly neutron-bombarded plutonium, ^{241}Pu, this isotope is used for much of the chemical investigation of this element. Better suited is the isotope ^{243}Am due to its longer half-life (7.37×10^3 years as compared to 432.2 years for ^{241}Am). A mixture of the isotopes ^{241}Am, ^{242}Am, and ^{243}Am can be prepared by intense neutron irradiation of ^{241}Am according to the reactions ^{241}Am (n, γ) → ^{242}Am (n, γ) → ^{243}Am. Nearly isotopically pure ^{243}Am can be prepared by a sequence of neutron bombardments and chemical separations as follows: neutron bombardment of ^{241}Am yields ^{242}Pu by the reactions ^{241}Am (n, γ) → ^{242}Am → ^{242}Pu, after chemical separation the ^{242}Pu can be transformed to ^{243}Am via the reactions ^{242}Pu (n, γ) → ^{243}Pu → ^{243}Am, and the ^{243}Am can be chemically separated. Fairly pure ^{242}Pu can be prepared more simply by very intense neutron irradiation of ^{239}Pu as the result of successive neutron-capture reactions. Seventeen radioactive isotopes and isomers are now recognized. Americium metal has been prepared by reducing the trifluoride with barium vapor at 1000 to 1200°C or the dioxide by lanthanum metal. The luster of freshly prepared americium metal is white and more silvery than plutonium or neptunium prepared in the same manner. It appears to be more malleable than uranium or neptunium and tarnishes slowly in dry air at room temperature. Americium is thought to exist in two forms: an alpha form which has a double hexagonal close-packed structure and a loose-packed cubic beta form. Americium must be handled with great care to avoid personal contamination. As little as 0.03 μCi of ^{241}Am is the maximum permissible total body burden. The alpha activity from ^{241}Am is about three times that of radium. When gram quantities of ^{241}Am are handled, the intense gamma activity makes exposure a serious problem. Americium dioxide, AmO_2, is the most important oxide. AmF_3, AmF_4, $AmCl_3$, $AmBr_3$, AmI_3, and other compounds have been prepared. The isotope ^{241}Am has been used as a portable source for gamma radiography. It has also been used as a radioactive glass thickness gage for the flat glass industry, and as a source of ionization for smoke detectors. Americum-243 (99%) is available from the Oak Ridge National Laboratory at a cost of about $750/g plus packing charges.

Antimony — (Gr. *anti* plus *monos* - a metal not found alone), Sb; at. wt. 121.760(1); at. no. 51; m.p. 630.63°C; b.p. 1587°C; sp. gr. 6.691 (20°C); valence 0, −3, +3, or +5. Antimony was recognized in compounds by the ancients and was known as a metal at the beginning of the 17th century and possibly much earlier. It is not abundant, but is found in over 100 mineral species. It is sometimes found native, but more frequently as the sulfide, *stibnite* (Sb_2S_3); it is also found as antimonides of the heavy metals, and as oxides. It is extracted from the sulfide by roasting to the oxide, which is reduced by salt and scrap iron; from its oxides it is also prepared by reduction with carbon. Two allotropic forms of antimony exist: the normal stable, metallic form, and the amorphous gray form. The so-called explosive antimony is an ill-defined material always containing an appreciable amount of halogen; therefore, it no longer warrants consideration as a separate allotrope. The yellow form, obtained by oxidation of *stibine,* SbH_3, is probably impure, and is not a distinct form. Natural antimony is made of two stable isotopes, ^{121}Sb and ^{123}Sb. Forty five other radioactive isotopes and isomers are now recognized. Metallic antimony is an extremely brittle metal of a flaky, crystalline texture. It is bluish white and has a metallic luster. It is not acted on by air at room temperature, but burns brilliantly when heated with the formation of white fumes of Sb_2O_3. It is a poor conductor of heat and electricity, and has a hardness of 3 to 3.5. Antimony, available commercially with a purity of 99.999 + %, is finding use in semiconductor technology for making infrared detectors, diodes, and Hall-effect devices. Commercial-grade antimony is widely used in alloys with percentages ranging from 1 to 20. It greatly increases the hardness and mechanical strength of lead. Batteries, antifriction alloys, type metal, small arms and tracer bullets, cable sheathing, and minor products use about half the metal produced. Compounds taking up the other half are oxides, sulfides, sodium antimonate, and antimony trichloride. These are used in manufacturing flame-proofing compounds, paints, ceramic enamels, glass, and pottery. Tartar emetic (hydrated potassium antimonyl tartate) has been used in medicine. Antimony and many of its compounds are toxic. Antimony costs about $1.30/kg or about $12/g (99.999%).

Argon — (Gr. *argos,* inactive), Ar; at. wt. 39.948(1); at. no. 18; m.p. −189.35°C; b.p. −185.85°C; t_c −122.28; density 1.7837 g/l. Its presence in air was suspected by Cavendish in 1785, discovered by Lord Rayleigh and Sir William Ramsay in 1894. The gas is prepared by fractionation of liquid air, the atmosphere containing 0.94% argon. The atmosphere of Mars contains 1.6% of ^{40}Ar and 5 p.p.m. of ^{36}Ar. Argon is two and one half times as soluble in water as nitrogen, having about the same solubility as oxygen. It is recognized by the characteristic lines in the red end of the spectrum. It is used in electric light bulbs and in fluorescent tubes at a pressure of about 400 Pa, and in filling photo tubes, glow tubes, etc. Argon is also used as an inert gas shield for arc welding and cutting, as a blanket for the production of titanium and other reactive elements, and as a protective atmosphere for growing silicon and germanium crystals. Argon is colorless and odorless, both as a gas and liquid. It is available in high-purity form. Commercial argon is available at a cost of about 3¢ per cubic foot. Argon is considered to be a very inert gas and is not known to form true chemical compounds, as do krypton, xenon, and radon. However, it does form a hydrate having a dissociation pressure of 105 atm at 0°C. Ion molecules such as $(ArKr)^+$, $(ArXe)^+$, $(NeAr)^+$ have been observed spectroscopically. Argon also forms a clathrate with β-hydroquinone. This clathrate is stable

and can be stored for a considerable time, but a true chemical bond does not exist. Van der Waals' forces act to hold the argon. In August 2000, researchers at the University of Helsinki, Finland reported they made a new argon compound HArF by shining UV light on frozen argon that contained a small amount of HF. Naturally occurring argon is a mixture of three isotopes. Seventeen other radioactive isotopes are now known to exist. Commercial argon is priced at about $70/300 cu. ft. or 8.5 cu. meters.

Arsenic — (L. *arsenicum,* Gr. *arsenikon,* yellow orpiment, identified with *arsenikos,* male, from the belief that metals were different sexes; Arabic, *Az-zernikh,* the orpiment from Persian *zerni-zar*, gold), As; at. wt. 74.92160(2); at. no. 33; valence –3, 0, +3 or +5. Elemental arsenic occurs in two solid modifications: yellow, and gray or metallic, with specific gravities of 1.97, and 5.73, respectively. Gray arsenic, the ordinary stable form, has a triple point of 817°C and sublimes at 614°C and has a critical temperature of 1400°C. Several other allotropic forms of arsenic are reported in the literature. It is believed that Albertus Magnus obtained the element in 1250 A.D. In 1649 Schroeder published two methods of preparing the element. It is found native, in the sulfides *realgar* and *orpiment,* as arsenides and sulfarsenides of heavy metals, as the oxide, and as arsenates. *Mispickel,* arsenopyrite, (FeSAs) is the most common mineral, from which on heating the arsenic sublimes leaving ferrous sulfide. The element is a steel gray, very brittle, crystalline, semimetallic solid; it tarnishes in air, and when heated is rapidly oxidized to arsenous oxide (As_2O_3) with the odor of garlic. Arsenic and its compounds are poisonous. Exposure to arsenic and its compounds should not exceed 0.2 mg/m^3 as elemental As during an 8-h work day. These values, however, are being studied, and may be lowered. Arsenic is also used in bronzing, pyrotechny, and for hardening and improving the sphericity of shot. The most important compounds are white arsenic (As_2O_3), the sulfide, Paris green $3Cu(AsO_2)_2 \cdot Cu(C_2H_3O_2)_2$, calcium arsenate, and lead arsenate; the last three have been used as agricultural insecticides and poisons. Marsh's test makes use of the formation and ready decomposition of arsine (AsH_3). Arsenic is available in high-purity form. It is finding increasing uses as a doping agent in solid-state devices such as transistors. Gallium arsenide is used as a laser material to convert electricity directly into coherent light. Natural arsenic is made of one isotope ^{75}As. Thirty other radioactive isotopes and isomers are known. Arsenic (99%) costs about $75/50g. Purified arsenic (99.9995%) costs about $50/g.

Astatine — (Gr. *astatos,* unstable), At; at. wt. (210); at. no. 85; m.p. 300°C (est.); valence probably 1, 3, 5, or 7. Synthesized in 1940 by D. R. Corson, K. R. MacKenzie, and E. Segre at the University of California by bombarding bismuth with alpha particles. The longest-lived isotope, ^{210}At, has a half-life of only 8.1 hours. Thirty-six other isotopes and isomers are now known. Minute quantities of ^{215}At, ^{218}At, and ^{219}At exist in equilibrium in nature with naturally occurring uranium and thorium isotopes, and traces of ^{217}At are equilibrium with ^{233}U and ^{239}Np resulting from interaction of thorium and uranium with naturally produced neutrons. The total amount of astatine present in the earth's crust, however, is probably less than 1 oz. Astatine can be produced by bombarding bismuth with energetic alpha particles to obtain the relatively long-lived $^{209–211}At$, which can be distilled from the target by heating it in air. Only about 0.05 μg of astatine has been prepared to date. The "time of flight" mass spectrometer has been used to confirm that this highly radioactive halogen behaves chemically very much like other halogens, particularly iodine. The interhalogen compounds AtI, AtBr, and AtCl are known to form, but it is not yet known if astatine forms diatomic astatine molecules. HAt and CH_3At (methyl astatide) have been detected. Astatine is said to be more metallic that iodine, and, like iodine, it probably accumulates in the thyroid gland. Workers at the Brookhaven National Laboratory have recently used reactive scattering in crossed molecular beams to identify and measure elementary reactions involving astatine.

Barium — (Gr. *barys,* heavy), Ba; at. wt. 137.327(7), at. no. 56; m.p. 727°C; b.p. 1897°C; sp. gr. 3.5 (20°C); valence 2. Baryta was distinguished from lime by Scheele in 1774; the element was discovered by Sir Humphrey Davy in 1808. It is found only in combination with other elements, chiefly in *barite* or *heavy spar* (sulfate) and *witherite* (carbonate) and is prepared by electrolysis of the chloride. Large deposits of barite are found in China, Germany, India, Morocco, and in the U.S. Barium is a metallic element, soft, and when pure is silvery white like lead; it belongs to the alkaline earth group, resembling calcium chemically. The metal oxidizes very easily and should be kept under petroleum or other suitable oxygen-free liquids to exclude air. It is decomposed by water or alcohol. The metal is used as a "getter" in vacuum tubes. The most important compounds are the peroxide (BaO_2), chloride, sulfate, carbonate, nitrate, and chlorate. Lithopone, a pigment containing barium sulfate and zinc sulfide, has good covering power, and does not darken in the presence of sulfides. The sulfate, as permanent white or *blanc fixe,* is also used in paint, in X-ray diagnostic work, and in glassmaking. *Barite* is extensively used as a weighting agent in oilwell drilling fluids, and also in making rubber. The carbonate has been used as a rat poison, while the nitrate and chlorate give green colors in pyrotechny. The impure sulfide phosphoresces after exposure to the light. The compounds and the metal are not expensive. Barium metal (99.2 + % pure) costs about $3/g. All barium compounds that are water or acid soluble are poisonous. Naturally occurring barium is a mixture of seven stable isotopes. Thirty six other radioactive isotopes and isomers are known to exist.

Berkelium — (*Berkeley,* home of the University of California), Bk; at. wt. (247); at. no. 97; m.p. 1050°C; valence 3 or 4; sp. gr. 14 (est.). Berkelium, the eighth member of the actinide transition series, was discovered in December 1949 by Thompson, Ghiorso, and Seaborg, and was the fifth transuranium element synthesized. It was produced by cyclotron bombardment of milligram amounts of ^{241}Am with helium ions at Berkeley, California. The first isotope produced had a mass number of 243 and decayed with a half-life of 4.5 hours. Thirteen isotopes are now known and have been synthesized. The existence of ^{249}Bk, with a half-life of 320 days, makes it feasible to isolate berkelium in weighable amounts so that its properties can be investigated with macroscopic quantities. One of the first visible amounts of a pure berkelium compound, berkelium chloride, was produced in 1962. It weighed 3 billionth of a gram. Berkelium probably has not yet been prepared in elemental form, but it is expected to be a silvery metal, easily soluble in dilute mineral acids, and readily oxidized by air or oxygen at elevated temperatures to form the oxide. X-ray diffraction methods have been used to identify the following compounds: BkO_2, BkO_3, BkF_3, BkCl, and BkOCl. As with other actinide elements, berkelium tends to accumulate in the

skeletal system. The maximum permissible body burden of ^{249}Bk in the human skeleton is about 0.0004 μg. Because of its rarity, berkelium presently has no commercial or technological use. Berkelium most likely resembles terbium with respect to chemical properties. Berkelium-249 is available from O.R.N.L. at a cost of $185/μg plus packing charges.

Beryllium — (Gr. *beryllos, beryl;* also called Glucinium or Glucinum, Gr. *glykys,* sweet), Be; at. wt. 9.012182(3); at no. 4; m.p. 1287°C; b.p. 2471°C; sp. gr. 1.848 (20°C); valence 2. Discovered as the oxide by Vauquelin in beryl and in emeralds in 1798. The metal was isolated in 1828 by Wohler and by Bussy independently by the action of potassium on beryllium chloride. Beryllium is found in some 30 mineral species, the most important of which are *bertrandite, beryl, chrysoberyl,* and *phenacite. Aquamarine* and *emerald* are precious forms of *beryl.* Beryllium minerals are found in the U.S., Brazil, Russia, Kazakhstan, and elsewhere. Colombia is known for its emeralds. *Beryl* ($3BeO \cdot Al_2O_3 \cdot 6SiO_2$) and *bertrandite* ($4BeO \cdot 2SiO_2 \cdot H_2O$) are the most important commercial sources of the element and its compounds. Most of the metal is now prepared by reducing beryllium fluoride with magnesium metal. Beryllium metal did not become readily available to industry until 1957. The metal, steel gray in color, has many desirable properties. It is one of the lightest of all metals, and has one of the highest melting points of the light metals. Its modulus of elasticity is about one third greater than that of steel. It resists attack by concentrated nitric acid, has excellent thermal conductivity, and is nonmagnetic. It has a high permeability to X-rays, and when bombarded by alpha particles, as from radium or polonium, neutrons are produced in the ratio of about 30 neutrons/million alpha particles. At ordinary temperatures beryllium resists oxidation in air, although its ability to scratch glass is probably due to the formation of a thin layer of the oxide. Beryllium is used as an alloying agent in producing beryllium copper which is extensively used for springs, electrical contacts, spot-welding electrodes, and nonsparking tools. It has found application as a structural material for high-speed aircraft, missiles, spacecraft, and communication satellites. It is being used in the windshield frame, brake discs, support beams, and other structural components of the space shuttle. Because beryllium is relatively transparent to X-rays, ultra-thin Be-foil is finding use in X-ray lithography for reproduction of microminiature integrated circuits. Natural beryllium is made of ^{9}Be and is stable. Eight other radioactive isotopes are known.

Beryllium is used in nuclear reactors as a reflector or moderator for it has a low thermal neutron absorption cross section. It is used in gyroscopes, computer parts, and instruments where lightness, stiffness, and dimensional stability are required. The oxide has a very high melting point and is also used in nuclear work and ceramic applications. Beryllium and its salts are toxic and should be handled with the greatest of care. Beryllium and its compounds should not be tasted to verify the sweetish nature of beryllium (as did early experimenters). The metal, its alloys, and its salts can be handled safely if certain work codes are observed, but no attempt should be made to work with beryllium before becoming familiar with proper safeguards. Beryllium metal is available at a cost of about $5/g (99.5% pure).

Bismuth — (Ger. *Weisse Masse,* white mass; later *Wisuth* and *Bisemutum*), Bi; at. wt. 208.98038(2); at. no. 83; m.p. 271.4°C; b.p. 1564°C; sp. gr. 9.747 (20°C); valence 3 or 5. In early times bismuth was confused with tin and lead. Claude Geoffroy the Younger showed it to be distinct from lead in 1753. It is a white crystalline, brittle metal with a pinkish tinge. It occurs native. The most important ores are *bismuthinite* or bismuth glance (Bi_2S_3) and *bismite* (Bi_2O_3). Peru, Japan, Mexico, Bolivia, and Canada are major bismuth producers. Much of the bismuth produced in the U.S. is obtained as a by-product in refining lead, copper, tin, silver, and gold ores. Bismuth is the most diamagnetic of all metals, and the thermal conductivity is lower than any metal, except mercury. It has a high electrical resistance, and has the highest Hall effect of any metal (i.e., greatest increase in electrical resistance when placed in a magnetic field). "Bismanol" is a permanent magnet of high coercive force, made of MnBi, by the U.S. Naval Surface Weapons Center. Bismuth expands 3.32% on solidification. This property makes bismuth alloys particularly suited to the making of sharp castings of objects subject to damage by high temperatures. With other metals such as tin, cadmium, etc., bismuth forms low-melting alloys which are extensively used for safety devices in fire detection and extinguishing systems. Bismuth is used in producing malleable irons and is finding use as a catalyst for making acrylic fibers. When bismuth is heated in air it burns with a blue flame, forming yellow fumes of the oxide. The metal is also used as a thermocouple material, and has found application as a carrier for U^{235} or U^{233} fuel in atomic reactors. Its soluble salts are characterized by forming insoluble basic salts on the addition of water, a property sometimes used in detection work. Bismuth oxychloride is used extensively in cosmetics. Bismuth subnitrate and subcarbonate are used in medicine. Natural bismuth contains only one isotope ^{209}Bi. Forty-four isotopes and isomers of bismuth are known. Bismuth metal (99.5%) costs about $250/kg.

Bohrium — (Named after Niels Bohr [1885–1962], Danish atomic and nuclear physicist.) Bh; at.wt. [262]. at.no. 107. Bohrium is expected to have chemical properties similar to rhenium. This element was synthesized and unambiguously identified in 1981 using the Universal Linear Accelerator (UNILAC) at the Gesellschaft für Schwerionenforschung (G.S.I.) in Darmstadt, Germany. The discovery team was led by Armbruster and Münzenberg. The reaction producing the element was proposed and applied earlier by a Dubna Group led by Oganessian in 1976. A target of ^{209}Bi was bombarded by a beam of ^{54}Cr ions. In 1983 experiments at Dubna using the 157-inch cyclotron, produced ^{262}107 by the reaction ^{209}Bi + ^{54}Cr. The alpha decay of ^{246}Cf, the sixth member in the decay chain of ^{262}107, served to establish a 1-neutron reaction channel. The IUPAC adopted the name ***Bohrium*** with the symbol Bh for Element 107 in August 1997. Five isotopes of bohrium are now recognized. One isotope of bohrium appears to have a relatively long life of 15 seconds. Work on this relatively long-lived isotope has been performed with the 88-inch cyclotron at the Lawrence-Berkeley National Laboratory.

Boron — (Ar. *Buraq,* Pers. *Burah*), B; at. wt. 10.811(7); at. no. 5; m.p. 2075°C; b.p. 4000°C; sp. gr. of crystals 2.34, of amorphous variety 2.37; valence 3. Boron compounds have been known for thousands of years, but the element was not discovered until 1808 by Sir Humphry Davy and by Gay-Lussac and Thenard. The element is not found free in nature, but occurs as orthoboric acid usually in certain volcanic spring waters and as borates in *borax* and *colemanite. Ulexite,* another boron mineral, is interesting as it is nature's own version of "fiber optics." Important sources of boron are the ores *rasorite (kern-*

ite) and *tincal (borax ore).* Both of these ores are found in the Mojave Desert. *Tincal* is the most important source of boron from the Mojave. Extensive *borax* deposits are also found in Turkey. Boron exists naturally as 19.9% ^{10}B isotope and 80.1% ^{11}B isotope. Ten other isotopes of boron are known. High-purity crystalline boron may be prepared by the vapor phase reduction of boron trichloride or tribromide with hydrogen on electrically heated filaments. The impure, or amorphous, boron, a brownish-black powder, can be obtained by heating the trioxide with magnesium powder. Boron of 99.9999% purity has been produced and is available commercially. Elemental boron has an energy band gap of 1.50 to 1.56 eV, which is higher than that of either silicon or germanium. It has interesting optical characteristics, transmitting portions of the infrared, and is a poor conductor of electricity at room temperature, but a good conductor at high temperature. Amorphous boron is used in pyrotechnic flares to provide a distinctive green color, and in rockets as an igniter. By far the most commercially important boron compound in terms of dollar sales is $Na_2B_4O_7 \cdot 5H_2O$. This pentahydrate is used in very large quantities in the manufacture of insulation fiberglass and sodium perborate bleach. Boric acid is also an important boron compound with major markets in textile fiberglass and in cellulose insulation as a flame retardant. Next in order of importance is borax ($Na_2B_4O_7 \cdot 10H_2O$) which is used principally in laundry products. Use of borax as a mild antiseptic is minor in terms of dollars and tons. Boron compounds are also extensively used in the manufacture of borosilicate glasses. The isotope boron-10 is used as a control for nuclear reactors, as a shield for nuclear radiation, and in instruments used for detecting neutrons. Boron nitride has remarkable properties and can be used to make a material as hard as diamond. The nitride also behaves like an electrical insulator but conducts heat like a metal. It also has lubricating properties similar to graphite. The hydrides are easily oxidized with considerable energy liberation, and have been studied for use as rocket fuels. Demand is increasing for boron filaments, a high-strength, lightweight material chiefly employed for advanced aerospace structures. Boron is similar to carbon in that it has a capacity to form stable covalently bonded molecular networks. Carboranes, metalloboranes, phosphacarboranes, and other families comprise thousands of compounds. Crystalline boron (99.5%) costs about $6/g. Amorphous boron (94–96%) costs about $1.50/g. Elemental boron and the borates are not considered to be toxic, and they do not require special care in handling. However, some of the more exotic boron hydrogen compounds are definitely toxic and do require care.

Bromine — (Gr. *bromos,* stench), Br; at. wt. 79.904(1); at. no. 35; m.p. –7.2°C; b.p. 58.8°C; t_c 315°C; density of gas 7.59 g/l, liquid 3.12 (20°C); valence 1, 3, 5, or 7. Discovered by Balard in 1826, but not prepared in quantity until 1860. A member of the halogen group of elements, it is obtained from natural brines from wells in Michigan and Arkansas. Little bromine is extracted today from seawater, which contains only about 85 ppm. Bromine is the only liquid nonmetallic element. It is a heavy, mobile, reddish-brown liquid, volatilizing readily at room temperature to a red vapor with a strong disagreeable odor, resembling chlorine, and having a very irritating effect on the eyes and throat; it is readily soluble in water or carbon disulfide, forming a red solution, is less active than chlorine but more so than iodine; it unites readily with many elements and has a bleaching action; when spilled on the skin it produces painful sores. It presents a serious health hazard, and maximum safety precautions should be taken when handling it. Much of the bromine output in the U.S. was used in the production of ethylene dibromide, a lead scavenger used in making gasoline antiknock compounds. Lead in gasoline, however, has been drastically reduced, due to environmental considerations. This will greatly affect future production of bromine. Bromine is also used in making fumigants, flameproofing agents, water purification compounds, dyes, medicinals, sanitizers, inorganic bromides for photography, etc. Organic bromides are also important. Natural bromine is made of two isotopes, ^{79}Br and ^{81}Br. Thirty-four isotopes and isomers are known. Bromine (99.8%) costs about $70/kg.

Cadmium — (L. *cadmia;* Gr. *kadmeia* - ancient name for calamine, zinc carbonate), Cd; at. wt. 112.411(8); at. no. 48; m.p. 321.07°C; b.p. 767°C; sp. gr. 8.65 (20°C); valence 2. Discovered by Stromeyer in 1817 from an impurity in zinc carbonate. Cadmium most often occurs in small quantities associated with zinc ores, such as *sphalerite* (ZnS). *Greenockite* (CdS) is the only mineral of any consequence bearing cadmium. Almost all cadmium is obtained as a by-product in the treatment of zinc, copper, and lead ores. It is a soft, bluish-white metal which is easily cut with a knife. It is similar in many respects to zinc. It is a component of some of the lowest melting alloys; it is used in bearing alloys with low coefficients of friction and great resistance to fatigue; it is used extensively in electroplating, which accounts for about 60% of its use. It is also used in many types of solder, for standard E.M.F. cells, for Ni-Cd batteries, and as a barrier to control atomic fission. The market for Ni-Cd batteries is expected to grow significantly in the next few years. Cadmium compounds are used in black and white television phosphors and in blue and green phosphors for color TV tubes. It forms a number of salts, of which the sulfate is most common; the sulfide is used as a yellow pigment. Cadmium and solutions of its compounds are toxic. Failure to appreciate the toxic properties of cadmium may cause workers to be unwittingly exposed to dangerous fumes. Some silver solders, for example, contain cadmium and should be handled with care. Serious toxicity problems have been found from long-term exposure and work with cadmium plating baths. Cadmium is present in certain phosphate rocks. This has raised concerns that the long-term use of certain phosphate fertilizers might pose a health hazard from levels of cadmium that might enter the food chain. In 1927 the International Conference on Weights and Measures redefined the meter in terms of the wavelength of the red cadmium spectral line (i.e., 1 m = 1,553,164.13 wavelengths). This definition has been changed (see under Krypton). The current price of cadmium is about 50¢/g (99.5%). It is available in high purity form for about $550/kg. Natural cadmium is made of eight isotopes. Thirty four other isotopes and isomers are now known and recognized.

Calcium — (L. *calx,* lime), Ca; at. wt. 40.078(4); at. no. 20; m.p. 842°C; b.p. 1484°C; sp. gr. 1.55 (20°C); valence 2. Though lime was prepared by the Romans in the first century under the name calx, the metal was not discovered until 1808. After learning that Berzelius and Pontin prepared calcium amalgam by electrolyzing lime in mercury, Davy was able to isolate the impure metal. Calcium is a metallic element, fifth in abundance in the earth's crust, of which it forms more than 3%. It is an essential constituent of leaves, bones, teeth, and shells. Never found in nature uncombined, it occurs abundantly as *limestone* ($CaCO_3$), *gypsum* ($CaSO_4 \cdot 2H_2O$), and *fluorite*

(CaF_2); *apatite* is the fluorophosphate or chlorophosphate of calcium. The metal has a silvery color, is rather hard, and is prepared by electrolysis of the fused chloride to which calcium fluoride is added to lower the melting point. Chemically it is one of the alkaline earth elements; it readily forms a white coating of oxide in air, reacts with water, burns with a yellow-red flame, forming largely the oxide. The metal is used as a reducing agent in preparing other metals such as thorium, uranium, zirconium, etc., and is used as a deoxidizer, desulfurizer, and inclusion modifier for various ferrous and nonferrous alloys. It is also used as an alloying agent for aluminum, beryllium, copper, lead, and magnesium alloys, and serves as a "getter" for residual gases in vacuum tubes, etc. Its natural and prepared compounds are widely used. Quicklime (CaO), made by heating limestone and changed into slaked lime by the careful addition of water, is the great cheap base of chemical industry with countless uses. Mixed with sand it hardens as mortar and plaster by taking up carbon dioxide from the air. Calcium from limestone is an important element in Portland cement. The solubility of the carbonate in water containing carbon dioxide causes the formation of caves with stalactites and stalagmites and is responsible for hardness in water. Other important compounds are the carbide (CaC_2), chloride ($CaCl_2$), cyanamide ($CaCN_2$), hypochlorite ($Ca(OCl)_2$), nitrate ($Ca(NO_3)_2$), and sulfide (CaS). Calcium sulfide is phosphorescent after being exposed to light. Natural calcium contains six isotopes. Sixteen other radioactive isotopes are known. Metallic calcium (99.5%) costs about $200/kg.

Californium — (State and University of California), Cf; at. wt. (251); m.p. 900°C; at. no. 98. Californium, the sixth transuranium element to be discovered, was produced by Thompson, Street, Ghioirso, and Seaborg in 1950 by bombarding microgram quantities of ^{242}Cm with 35 MeV helium ions in the Berkeley 60-inch cyclotron. Californium (III) is the only ion stable in aqueous solutions, all attempts to reduce or oxidize californium (III) having failed. The isotope ^{249}Cf results from the beta decay of ^{249}Bk while the heavier isotopes are produced by intense neutron irradiation by the reactions:

$$^{249}Bk(n,\gamma) \rightarrow ^{250}Bk \xrightarrow{\beta} ^{250}Cf \text{ and } ^{249}Cf(n,\gamma) \rightarrow ^{250}Cf$$

followed by

$$^{250}Cf(n,\gamma) \rightarrow ^{251}Cf(n,\gamma) \rightarrow ^{252}Cf$$

The existence of the isotopes ^{249}Cf, ^{250}Cf, ^{251}Cf, and ^{252}Cf makes it feasible to isolate californium in weighable amounts so that its properties can be investigated with macroscopic quantities. Californium-252 is a very strong neutron emitter. One microgram releases 170 million neutrons per minute, which presents biological hazards. Proper safeguards should be used in handling californium. Twenty isotopes of californium are now recognized. ^{249}Cf and ^{252}Cf have half-lives of 351 years and 900 years, respectively. In 1960 a few tenths of a microgram of californium trichloride, $CfCl_3$, californium oxychloride, CfOCl, and californium oxide, Cf_2O_3, were first prepared. Reduction of californium to its metallic state has not yet been accomplished. Because californium is a very efficient source of neutrons, many new uses are expected for it. It has already found use in neutron moisture gages and in well-logging (the determination of water and oil-bearing layers). It is also being used as a portable neutron source for discovery of metals such as gold or silver by on-the-spot activation analysis. ^{252}Cf is now being offered for sale by the Oak Ridge National Laboratory (O.R.N.L.) at a cost of $60/μg and ^{249}Cf at a cost of $185/μg plus packing charges. It has been suggested that californium may be produced in certain stellar explosions, called *supernovae,* for the radioactive decay of ^{254}Cf (55-day half-life) agrees with the characteristics of the light curves of such explosions observed through telescopes. This suggestion, however, is questioned. Californium is expected to have chemical properties similar to dysprosium.

Carbon — (L. *carbo,* charcoal), C; at. wt. 12.0107(8); at. no. 6; sublimes at 3642°C; triple point (graphite-liquid-gas), 4492°C at a pressure of 101.325 kPa; sp. gr. amorphous 1.8 to 2.1, graphite 1.9 to 2.3, diamond 3.15 to 3.53 (depending on variety); gem diamond 3.513 (25°C); valence 2, 3, or 4. Carbon, an element of prehistoric discovery, is very widely distributed in nature. It is found in abundance in the sun, stars, comets, and atmospheres of most planets. Carbon in the form of microscopic diamonds is found in some meteorites. Natural diamonds are found in *kimberlite* or *lamporite* of ancient formations called "pipes," such as found in South Africa, Arkansas, and elsewhere. Diamonds are now also being recovered from the ocean floor off the Cape of Good Hope. About 30% of all industrial diamonds used in the U.S. are now made synthetically. The energy of the sun and stars can be attributed at least in part to the well-known carbon-nitrogen cycle. Carbon is found free in nature in three allotropic forms: amorphous, graphite, and diamond. A fourth form, known as "white" carbon, is now thought to exist. Graphite is one of the softest known materials while diamond is one of the hardest. Graphite exists in two forms: alpha and beta. These have identical physical properties, except for their crystal structure. Naturally occurring graphites are reported to contain as much as 30% of the rhombohedral (beta) form, whereas synthetic materials contain only the alpha form. The hexagonal alpha type can be converted to the beta by mechanical treatment, and the beta form reverts to the alpha on heating it above 1000°C. In 1969 a new allotropic form of carbon was produced during the sublimation of pyrolytic graphite at low pressures. Under free-vaporization conditions above ~2550 K, "white" carbon forms as small transparent crystals on the edges of the basal planes of graphite. The interplanar spacings of "white" carbon are identical to those of carbon form noted in the graphitic gneiss from the Ries (meteoritic) Crater of Germany. "White" carbon is a transparent birefringent material. Little information is presently available about this allotrope. Of recent interest is the discovery of all-carbon molecules, known as "buckyballs" or fullerenes, which have a number of unusual properties. These interesting molecules, consisting of 60 or 70 carbon atoms linked together, seem capable of withstanding great pressure and trapping foreign atoms inside their network of carbon. They are said to be capable of magnetism and superconductivity and have potential as a nonlinear optical material. Buckyball films are reported to remain superconductive at temperatures as high as 45 K. In combination, carbon is found as carbon dioxide in the atmosphere of the earth and dissolved in all natural waters. It is a component of great rock masses in the form of carbonates of calcium (limestone), magnesium, and iron. Coal, petroleum, and natural gas are chiefly hydrocarbons. Carbon is unique among the elements in the vast number and variety of compounds it can form. With hydrogen, oxygen, nitrogen, and other elements, it forms a very large number of compounds, carbon atom often

being linked to carbon atom. There are close to ten million known carbon compounds, many thousands of which are vital to organic and life processes. Without carbon, the basis for life would be impossible. While it has been thought that silicon might take the place of carbon in forming a host of similar compounds, it is now not possible to form stable compounds with very long chains of silicon atoms. The atmosphere of Mars contains 96.2% CO_2. Some of the most important compounds of carbon are carbon dioxide (CO_2), carbon monoxide (CO), carbon disulfide (CS_2), chloroform ($CHCl_3$), carbon tetrachloride (CCl_4), methane (CH_4), ethylene (C_2H_4), acetylene (C_2H_2), benzene (C_6H_6), ethyl alcohol (C_2H_5OH), acetic acid (CH_3COOH), and their derivatives. Carbon has fifteen isotopes. Natural carbon consists of 98.89% ^{12}C and 1.11% ^{13}C. In 1961 the International Union of Pure and Applied Chemistry adopted the isotope carbon-12 as the basis for atomic weights. Carbon-14, an isotope with a half-life of 5715 years, has been widely used to date such materials as wood, archeological specimens, etc. A new brittle form of carbon, known as "glassy carbon", has been developed. It can be obtained with high purity. It has a high resistance to corrosion, has good thermal stability, and is structurally impermeable to both gases and liquids. It has a randomized structure, making it useful in ultra-high technology applications, such as crystal growing, crucibles for high-temperature use, etc. Glassy carbon is available at a cost of about $35/10gms. Fullerene powder is available at a cost of about $55/10mg (99%$C_{10}$). Diamond powder (99.9%) costs about $40/g.

Cerium — (named for the asteroid *Ceres,* which was discovered in 1801 only 2 years before the element), Ce; at. wt. 140.115(4); at. no. 58; m.p. 798°C; b.p. 3424°C; sp. gr. 6.770 (25°C); valence 3 or 4. Discovered in 1803 by Klaproth and by Berzelius and Hisinger; metal prepared by Hillebrand and Norton in 1875. Cerium is the most abundant of the metals of the so-called rare earths. It is found in a number of minerals including *allanite* (also known as *orthite*), *monazite, bastnasite, cerite,* and *samarskite.* Monazite and bastnasite are presently the two most important sources of cerium. Large deposits of monazite found on the beaches of Travancore, India, in river sands in Brazil, and deposits of *allanite* in the western United States, and *bastnasite* in Southern California will supply cerium, thorium, and the other rare-earth metals for many years to come. Metallic cerium is prepared by metallothermic reduction techniques, such as by reducing cerous fluoride with calcium, or by electrolysis of molten cerous chloride or other cerous halides. The metallothermic technique is used to produce high-purity cerium. Cerium is especially interesting because of its variable electronic structure. The energy of the inner 4f level is nearly the same as that of the outer or valence electrons, and only small amounts of energy are required to change the relative occupancy of these electronic levels. This gives rise to dual valency states. For example, a volume change of about 10% occurs when cerium is subjected to high pressures or low temperatures. It appears that the valence changes from about 3 to 4 when it is cooled or compressed. The low temperature behavior of cerium is complex. Four allotropic modifications are thought to exist: cerium at room temperature and at atmospheric pressure is known as γ cerium. Upon cooling to −16°C, γ cerium changes to β cerium. The remaining γ cerium starts to change to α cerium when cooled to −172°C, and the transformation is complete at −269°C. α Cerium has a density of 8.16; δ cerium exists above 726°C. At atmospheric pressure, liquid cerium is more dense than its solid form at the melting point. Cerium is an iron-gray lustrous metal. It is malleable, and oxidizes very readily at room temperature, especially in moist air. Except for europium, cerium is the most reactive of the "rare-earth" metals. It slowly decomposes in cold water, and rapidly in hot water. Alkali solutions and dilute and concentrated acids attack the metal rapidly. The pure metal is likely to ignite if scratched with a knife. Ceric salts are orange red or yellowish; cerous salts are usually white. Cerium is a component of misch metal, which is extensively used in the manufacture of pyrophoric alloys for cigarette lighters, etc. Natural cerium is stable and contains four isotopes. Thirty-two other radioactive isotopes and isomers are known. While cerium is not radioactive, the impure commercial grade may contain traces of thorium, which is radioactive. The oxide is an important constituent of incandescent gas mantles and it is emerging as a hydrocarbon catalyst in "self-cleaning" ovens. In this application it can be incorporated into oven walls to prevent the collection of cooking residues. As ceric sulfate it finds extensive use as a volumetric oxidizing agent in quantitative analysis. Cerium compounds are used in the manufacture of glass, both as a component and as a decolorizer. The oxide is finding increased use as a glass polishing agent instead of rouge, for it is much faster than rouge in polishing glass surfaces. Cerium compounds are finding use in automobile exhaust catalysts. Cerium is also finding use in making permanent magnets. Cerium, with other rare earths, is used in carbon-arc lighting, especially in the motion picture industry. It is also finding use as an important catalyst in petroleum refining and in metallurgical and nuclear applications. In small lots, cerium costs about $5/g (99.9%).

Cesium — (L. *caesius,* sky blue), Cs; at. wt. 132.90545(2); at. no. 55; m.p. 28.44°C; b.p. 671°C; sp. gr. 1.873 (20°C); valence 1. Cesium was discovered spectroscopically by Bunsen and Kirchhoff in 1860 in mineral water from Durkheim. Cesium, an alkali metal, occurs in *lepidolite, pollucite* (a hydrated silicate of aluminum and cesium), and in other sources. One of the world's richest sources of cesium is located at Bernic Lake, Manitoba. The deposits are estimated to contain 300,000 tons of pollucite, averaging 20% cesium. It can be isolated by electrolysis of the fused cyanide and by a number of other methods. Very pure, gas-free cesium can be prepared by thermal decomposition of cesium azide. The metal is characterized by a spectrum containing two bright lines in the blue along with several others in the red, yellow, and green. It is silvery white, soft, and ductile. It is the most electropositive and most alkaline element. Cesium, gallium, and mercury are the only three metals that are liquid at room temperature. Cesium reacts explosively with cold water, and reacts with ice at temperatures above −116°C. Cesium hydroxide, the strongest base known, attacks glass. Because of its great affinity for oxygen the metal is used as a "getter" in electron tubes. It is also used in photoelectric cells, as well as a catalyst in the hydrogenation of certain organic compounds. The metal has recently found application in ion propulsion systems. Cesium is used in atomic clocks, which are accurate to 5 s in 300 years. A second of time is now defined as being the duration of 9,192,631,770 periods of the radiation corresponding to the transition between the two hyper-fine levels of the ground state of the cesium-133 atom. Its chief compounds are the chloride and the nitrate. Cesium has 52 isotopes and isomers with masses ranging from 112 to 148. The present price of cesium is about $50/g (99.98%) sealed in a glass ampoule.

Chlorine — (Gr. *chloros,* greenish yellow), Cl; at. wt. 35.4527(9); at. no. 17; m.p. –101.5°C; b.p. –34.04°C; t_c 143.8°C; density 3.214 g/l; sp. gr. 1.56 (–33.6°C); valence 1, 3, 5, or 7. Discovered in 1774 by Scheele, who thought it contained oxygen; named in 1810 by Davy, who insisted it was an element. In nature it is found in the combined state only, chiefly with sodium as common salt (NaCl), *carnallite* ($KMgCl_3 \cdot 6H_2O$), and *sylvite* (KCl). It is a member of the halogen (salt-forming) group of elements and is obtained from chlorides by the action of oxidizing agents and more often by electrolysis; it is a greenish-yellow gas, combining directly with nearly all elements. At 10°C one volume of water dissolves 3.10 volumes of chlorine, at 30°C only 1.77 volumes. Chlorine is widely used in making many everyday products. It is used for producing safe drinking water the world over. Even the smallest water supplies are now usually chlorinated. It is also extensively used in the production of paper products, dyestuffs, textiles, petroleum products, medicines, antiseptics, insecticides, foodstuffs, solvents, paints, plastics, and many other consumer products. Most of the chlorine produced is used in the manufacture of chlorinated compounds for sanitation, pulp bleaching, disinfectants, and textile processing. Further use is in the manufacture of chlorates, chloroform, carbon tetrachloride, and in the extraction of bromine. Organic chemistry demands much from chlorine, both as an oxidizing agent and in substitution, since it often brings desired properties in an organic compound when substituted for hydrogen, as in one form of synthetic rubber. Chlorine is a respiratory irritant. The gas irritates the mucous membranes and the liquid burns the skin. As little as 3.5 ppm can be detected as an odor, and 1000 ppm is likely to be fatal after a few deep breaths. It was used as a war gas in 1915. Natural chlorine contains two isotopes. Twenty other isotopes and isomers are known.

Chromium — (Gr. *chroma,* color), Cr; at. wt. 51.9961(6); at. no. 24; m.p. 1907°C; b.p. 2671°C; sp. gr. 7.18 to 7.20 (20°C); valence chiefly 2, 3, or 6. Discovered in 1797 by Vauquelin, who prepared the metal the next year, chromium is a steel-gray, lustrous, hard metal that takes a high polish. The principal ore is *chromite* ($FeCr_2O_4$), which is found in Zimbabwe, Russia, South Africa, Turkey, Iran, Albania, Finland, Democratic Republic of Madagascar, the Philippines, and elsewhere. The U.S. has no appreciable chromite ore reserves. The metal is usually produced by reducing the oxide with aluminum. Chromium is used to harden steel, to manufacture stainless steel, and to form many useful alloys. Much is used in plating to produce a hard, beautiful surface and to prevent corrosion. Chromium is used to give glass an emerald green color. It finds wide use as a catalyst. All compounds of chromium are colored; the most important are the chromates of sodium and potassium (K_2CrO_4) and the dichromates ($K_2Cr_2O_7$) and the potassium and ammonium chrome alums, as $KCr(SO_4)_2 \cdot 12H_2O$. The dichromates are used as oxidizing agents in quantitative analysis, also in tanning leather. Other compounds are of industrial value; lead chromate is chrome yellow, a valued pigment. Chromium compounds are used in the textile industry as mordants, and by the aircraft and other industries for anodizing aluminum. The refractory industry has found chromite useful for forming bricks and shapes, as it has a high melting point, moderate thermal expansion, and stability of crystalline structure. Chromium is an essential trace element for human health. Many chromium compounds, however, are acutely toxic, chronically toxic, and may be carcinogenic. They should be handled with proper safeguards. Natural chromium contains four isotopes. Twenty other isotopes are known. Chromium metal (99.95%) costs about $1000/kg. Commercial grade chromium (99%) costs about $75/kg.

Cobalt — (*Kobald,* from the German, goblin or evil spirit, *cobalos,* Greek, mine), Co; at. wt. 58.93320(1); at. no. 27; m.p. 1495°C; b.p. 2927°C; sp. gr. 8.9 (20°C); valence 2 or 3. Discovered by Brandt about 1735. Cobalt occurs in the mineral *cobaltite, smaltite,* and *erythrite,* and is often associated with nickel, silver, lead, copper, and iron ores, from which it is most frequently obtained as a by-product. It is also present in meteorites. Important ore deposits are found in Congo-Kinshasa, Australia, Zambia, Russia, Canada, and elsewhere. The U.S. Geological Survey has announced that the bottom of the north central Pacific Ocean may have cobalt-rich deposits at relatively shallow depths in waters close to the Hawaiian Islands and other U.S. Pacific territories. Cobalt is a brittle, hard metal, closely resembling iron and nickel in appearance. It has a magnetic permeability of about two thirds that of iron. Cobalt tends to exist as a mixture of two allotropes over a wide temperature range; the β-form predominates below 400°C, and the α above that temperature. The transformation is sluggish and accounts in part for the wide variation in reported data on physical properties of cobalt. It is alloyed with iron, nickel and other metals to make Alnico, an alloy of unusual magnetic strength with many important uses. Stellite alloys, containing cobalt, chromium, and tungsten, are used for high-speed, heavy-duty, high temperature cutting tools, and for dies. Cobalt is also used in other magnet steels and stainless steels, and in alloys used in jet turbines and gas turbine generators. The metal is used in electroplating because of its appearance, hardness, and resistance to oxidation. The salts have been used for centuries for the production of brilliant and permanent blue colors in porcelain, glass, pottery, tiles, and enamels. It is the principal ingredient in Sevre's and Thenard's blue. A solution of the chloride ($CoCl_2 \cdot 6H_2O$) is used as sympathetic ink. The cobalt ammines are of interest; the oxide and the nitrate are important. Cobalt carefully used in the form of the chloride, sulfate, acetate, or nitrate has been found effective in correcting a certain mineral deficiency disease in animals. Soils should contain 0.13 to 0.30 ppm of cobalt for proper animal nutrition.Cobalt is found in Vitamin B-12, which is essential for human nutrition. Cobalt of 99.9+% purity is priced at about $250/kg. Cobalt-60, an artificial isotope, is an important gamma ray source, and is extensively used as a tracer and a radiotherapeutic agent. Single compact sources of Cobalt-60 vary from about $1 to $10/curie, depending on quantity and specific activity. Thirty isotopes and isomers of cobalt are known.

Columbium — See Niobium.

Copper — (L. *cuprum,* from the island of Cyprus), Cu; at. wt. 63.546(3); at. no. 29; f.p. 1084.62 °C; b.p. 2562°C; sp. gr. 8.96 (20°C); valence 1 or 2. The discovery of copper dates from prehistoric times. It is said to have been mined for more than 5000 years. It is one of man's most important metals. Copper is reddish colored, takes on a bright metallic luster, and is malleable, ductile, and a good conductor of heat and electricity (second only to silver in electrical conductivity). The electrical industry is one of the greatest users of copper. Copper occasionally occurs native, and is found in many minerals such as *cuprite, malachite, azurite, chalcopyrite,* and *bornite.* Large copper ore deposits are found in the U.S., Chile, Zambia, Zaire, Peru, and Canada. The most important copper ores are the sulfides, oxides, and carbonates. From these, copper

is obtained by smelting, leaching, and by electrolysis. Its alloys, brass and bronze, long used, are still very important; all American coins are now copper alloys; monel and gun metals also contain copper. The most important compounds are the oxide and the sulfate, blue vitriol; the latter has wide use as an agricultural poison and as an algicide in water purification. Copper compounds such as Fehling's solution are widely used in analytical chemistry in tests for sugar. High-purity copper (99.999 + %) is readily available commercially. The price of commercial copper has fluctuated widely. The price of copper in December 2001 was about $1.50/kg. Natural copper contains two isotopes. Twenty-six other radioactive isotopes and isomers are known.

Curium — (Pierre and Marie Curie), Cm; at. wt. (247); at. no. 96; m.p. 1345°C; sp. gr. 13.51 (calc.); valence 3 and 4. Although curium follows americium in the periodic system, it was actually known before americium and was the third transuranium element to be discovered. It was identified by Seaborg, James, and Ghiorso in 1944 at the wartime Metallurgical Laboratory in Chicago as a result of helium-ion bombardment of ^{239}Pu in the Berkeley, California, 60-inch cyclotron. Visible amounts (30 μg) of ^{242}Cm, in the form of the hydroxide, were first isolated by Werner and Perlman of the University of California in 1947. In 1950, Crane, Wallmann, and Cunningham found that the magnetic susceptibility of microgram samples of CmF_3 was of the same magnitude as that of GdF_3. This provided direct experimental evidence for assigning an electronic configuration to Cm^{+3}. In 1951, the same workers prepared curium in its elemental form for the first time. Sixteen isotopes of curium are now known. The most stable, ^{247}Cm, with a half-life of 16 million years, is so short compared to the earth's age that any primordial curium must have disappeared long ago from the natural scene. Minute amounts of curium probably exist in natural deposits of uranium, as a result of a sequence of neutron captures and β decays sustained by the very low flux of neutrons naturally present in uranium ores. The presence of natural curium, however, has never been detected. ^{242}Cm and ^{244}Cm are available in multigram quantities. ^{248}Cm has been produced only in milligram amounts. Curium is similar in some regards to gadolinium, its rare-earth homolog, but it has a more complex crystal structure. Curium is silver in color, is chemically reactive, and is more electropositive than aluminum. CmO_2, Cm_2O_3, CmF_3, CmF_4, $CmCl_3$, $CmBr_3$, and CmI_3 have been prepared. Most compounds of trivalent curium are faintly yellow in color. ^{242}Cm generates about three watts of thermal energy per gram. This compares to one-half watt per gram of ^{238}Pu. This suggests use for curium as a power source. ^{244}Cm is now offered for sale by the O.R.N.L. at $185/mg plus packing charges. ^{248}Cm is available at a cost of $160/μg, plus packing charges, from the O.R.N.L. Curium absorbed into the body accumulates in the bones, and is therefore very toxic as its radiation destroys the red-cell forming mechanism. The maximum permissible total body burden of ^{244}Cm (soluble) in a human being is 0.3 μCi (microcurie).

Deuterium — an isotope of hydrogen — see Hydrogen.

Dubnium — (named after the Joint Institute of Nuclear Research in Dubna, Russia). Db; at.wt. [262]; at.no. 105. In 1967 G. N. Flerov reported that a Soviet team working at the Joint Institute for Nuclear Research at Dubna may have produced a few atoms of ^{260}105 and ^{261}105 by bombarding ^{243}Am with ^{22}Ne. Their evidence was based on time-coincidence measurements of alpha energies. More recently, it was reported that early in 1970 Dubna scientists synthesized Element 105 and that by the end of April 1970 "had investigated all the types of decay of the new element and had determined its chemical properties." In late April 1970, it was announced that Ghiorso, Nurmia, Harris, K. A. Y. Eskola, and P. L. Eskola, working at the University of California at Berkeley, had positively identified Element 105. The discovery was made by bombarding a target of ^{249}Cf with a beam of 84 MeV nitrogen nuclei in the Heavy Ion Linear Accelerator (HILAC). When a ^{15}N nuclear is absorbed by a ^{249}Cf nucleus, four neutrons are emitted and a new atom of ^{260}105 with a half-life of 1.6 s is formed. While the first atoms of Element 105 are said to have been detected conclusively on March 5, 1970, there is evidence that Element 105 had been formed in Berkeley experiments a year earlier by the method described. Ghiorso and his associates have attempted to confirm Soviet findings by more sophisticated methods without success.

In October 1971, it was announced that two new isotopes of Element 105 were synthesized with the heavy ion linear accelerator by A. Ghiorso and co-workers at Berkeley. Element ^{261}105 was produced both by bombarding ^{250}Cf with ^{15}N and by bombarding ^{249}Bk with ^{16}O. The isotope emits 8.93-MeV α particles and decays to ^{257}Lr with a half-life of about 1.8 s. Element ^{262}105 was produced by bombarding ^{249}Bk with ^{18}O. It emits 8.45 MeV α particles and decays to ^{258}Lr with a half-life of about 40 s. Nine isotopes of Dubnium are now recognized. Soon after the discovery the names ***Hahnium*** and ***Joliotium,*** named after Otto Hahn and Jean-Frederic Joliot and Mme. Joliot-Curie, were suggested as names for Element 105. The IUPAC in August 1997 finally resolved the issue, naming Element 105 Dubnium with the symbol Db. Dubnium is thought to have properties similar to tantalum.

Dysprosium — (Gr. *dysprositos,* hard to get at), Dy; at. wt. 162.50(3); at. no. 66; m.p. 1412°C; b.p. 2567°C; sp. gr. 8.551 (25°C); valence 3. Dysprosium was discovered in 1886 by Lecoq de Boisbaudran, but not isolated. Neither the oxide nor the metal was available in relatively pure form until the development of ion-exchange separation and metallographic reduction techniques by Spedding and associates about 1950. Dysprosium occurs along with other so-called rare-earth or lanthanide elements in a variety of minerals such as *xenotime, fergusonite, gadolinite, euxenite, polycrase,* and *blomstrandine.* The most important sources, however, are from *monazite* and *bastnasite.* Dysprosium can be prepared by reduction of the trifluoride with calcium. The element has a metallic, bright silver luster. It is relatively stable in air at room temperature, and is readily attacked and dissolved, with the evolution of hydrogen, by dilute and concentrated mineral acids. The metal is soft enough to be cut with a knife and can be machined without sparking if overheating is avoided. Small amounts of impurities can greatly affect its physical properties. While dysprosium has not yet found many applications, its thermal neutron absorption cross-section and high melting point suggest metallurgical uses in nuclear control applications and for alloying with special stainless steels. A dysprosium oxide-nickel cermet has found use in cooling nuclear reactor rods. This cermet absorbs neutrons readily without swelling or contracting under prolonged neutron bombardment. In combination with vanadium and other rare earths, dysprosium has been used in making laser materials. Dysprosium-cadmium chalcogenides, as sources of infrared radiation, have been used for studying chemical reactions. The cost of dysprosium metal has dropped in recent years since the development of ion-

exchange and solvent extraction techniques, and the discovery of large ore bodies. Thirty two isotopes and isomers are now known. The metal costs about $6/g (99.9% purity).

Einsteinium — (Albert Einstein [1879–1955]), Es; at. wt. (252); m.p. 860°C (est.); at. no. 99. Einsteinium, the seventh transuranic element of the actinide series to be discovered, was identified by Ghiorso and co-workers at Berkeley in December 1952 in debris from the first large thermonuclear explosion, which took place in the Pacific in November 1952. The isotope produced was the 20-day ^{253}Es isotope. In 1961, a sufficient amount of einsteinium was produced to permit separation of a macroscopic amount of ^{253}Es. This sample weighed about 0.01 μg. A special magnetic-type balance was used in making this determination. ^{253}Es so produced was used to produce mendelevium. About 3 μg of einsteinium has been produced at Oak Ridge National Laboratories by irradiating for several years kilogram quantities of ^{239}Pu in a reactor to produce ^{242}Pu. This was then fabricated into pellets of plutonium oxide and aluminum powder, and loaded into target rods for an initial 1-year irradiation at the Savannah River Plant, followed by irradiation in a HFIR (High Flux Isotopic Reactor). After 4 months in the HFIR the targets were removed for chemical separation of the einsteinium from californium. Nineteen isotopes and isomers of einsteinium are now recognized. ^{254}Es has the longest half-life (276 days). Tracer studies using ^{253}Es show that einsteinium has chemical properties typical of a heavy trivalent, actinide element. Einsteinium is extremely radioactive. Great care must be taken when handling it.

Element 93 — See Neptunium.

Element 94 — See Plutonium.

Element 95 — See Americium.

Element 96 — See Curium.

Element 97 — See Berkelium.

Element 98 — See Californium.

Element 99 — See Einsteinium.

Element 100 — See Fermium (unnilnilium).

Element 101 — See Mendelevium (unnilunium).

Element 102 — See Nobelium (unnilbium).

Element 103 — See Lawrencium (unniltrium).

Element 104 — See Rutherfordium (unnilquadium).

Element 105 — See Dubnium (unnilpentium).

Element 106 — See Seaborgium (unnilhexium).

Element 107 — See Bohrium (unnilseptium).

Element 108 — See Hassium (unniloctium).

Element 109 — See Meitnerium (unnilennium).

Element 110 — In 1987 Oganessian, et al., at Dubna, claimed discovery of this element. Their experiments indicated the spontaneous fissioning nuclide ^{272}110 with a half-life of 10 ms. More recently a group led by Armbruster at G.S.I. in Darmstadt, Germany, reported evidence of ^{269}110, which was produced by bombarding lead for many days with more than 10^{18} nickel atoms. A detector searched each collision for Element 110's distinct decay sequence. On November 9, 1994, evidence of 110 was detected. In 2003 IUPAC approved the name darmstadtium, symbol Ds, for Element 110. Seven isotopes of Element 110 are now recognized.

Element 111 — On December 20, 1994, scientists at GSI Darmstadt, Germany announced they had detected three atoms of a new element with 111 protons and 161 neutrons. This element was made by bombarding ^{83}Bi with ^{28}Ni. Signals of Element 111 appeared for less than 0.002 sec, then decayed into lighter elements including Element ^{268}109 and Element ^{264}107. These isotopes had not previously been observed. A name for Element 111 has not been suggested although IUPAC has suggested a temporary name of Unununium, with the symbol Uuu. Element 111 is expected to have properties similar to gold. Also see element 115.

Element 112 — In late February 1996, Siguard Hofmann and his collaborators at GSI Darmstadt announced their discovery of Element 112, having 112 protons and 165 neutrons, with an atomic mass of 277. This element was made by bombarding a lead target with high-energy zinc ions. A single nucleus of Element 112 was detected, which decayed after less than 0.001 sec by emitting an α particle, consisting of two protons and two neutrons. This created Element 110_{273}, which in turn decayed by emitting an α particle to form a new isotope of Element 108 and so on. Evidence indicates that nuclei with 162 neutrons are held together more strongly than nuclei with a smaller or larger number of neutrons. This suggests a narrow "peninsula" of relatively stable isotopes around Element 114. GSI scientists are experimenting to bombard targets with ions heavier than zinc to produce Elements 113 and 114. A name has not yet been suggested for Element 112, although the IUPAC suggested the temporary name of ununbium, with the symbol of Uub, when the element was discovered. Element 112 is expected to have properties similar to mercury.

Element 113 — (Ununtrium) See Element 115.

Element 114 — (Ununquadium) Symbol Uuq. Element 114 is the first new element to be discovered since 1996. This element was found by a Russian–American team, including Livermore researchers, by bombarding a sheet of plutonium with a rare form of calcium hoping to make the atoms stick together in a new element. Radiation showed that the new element broke into smaller pieces. Data of radiation collected at the Russian Joint Institute for Nuclear Research in November and December 1998, were analyzed in January 1999. It was found that some of the heavy atoms created when 114 decayed lived up to 30 seconds, which was longer than ever seen before, for such a heavy element. This isotope decayed into a previously unknown isotope of Element 112, which itself lasted 15 minutes. That isotope, in turn, decayed to a previously undiscovered isotope of Element 108, which survived 17 minutes. Isotopes of these and those with longer life-times have been predicted for some time by theorists. It appears that these isotopes are on the edge of the "island of stability", and that some of the isotopes in this region might last long enough for studies of their nuclear behavior and for a chemical evaluation to be made. No name has yet been suggested for Element 114; however, the temporary name of ununquadium with symbol Uuq may be used.

Element 115— (Ununpentium) On February 2, 2004, it was reported that Element 115 had been discovered at the Joint Institute for Nuclear Research (JINR) in Dubna, Russia. Four

atoms of this element were produced by JINR physicists and collaborators from the Lawrence Livermore (California) Laboratory using a 248-MeV beam of calcium-48 ions striking a target of americium-243 atoms. The nuclei of these atoms are said to have a life of 90 milliseconds. The relatively long lifetime of Element 115 suggests that these experiments might be getting closer to the "island of stability" long sought to exist by some nuclear physicists. These atoms were thought to decay first to Element 113 by the emission of an alpha particle, then decaying further to Element 111 by alpha emission again, and then by three more alpha decay processes to Element 105 (dubnium), which after a long delay from the time of the initial interaciton, fissioned. This experiment entailed separating four atoms from trillions of other atoms. A gas-filled separator, employing chemistry, was important in this experiment. Names for Elements 115, Element 113, and Element 111 have not yet been chosen.

Element 116 — (Ununhexium) Symbol Uuh. As of January 2004 it is questionable if this element has been discovered.

Element 117 — (Ununseptium) Symbol Uus. As of January 2004, this element remains undiscovered.

Element 118 — (Ununoctium) Symbol Uuo. In June 1999 it was announced that Elements 118 and 116 had been discovered at the Lawrence Berkeley National Laboratory. A lead target was bombarded for more than 10 days with roughly 1 quintillion krypton ions. The team reported that three atoms of Element 118 were made, which quickly decayed into Elements 116, 114, and elements of lower atomic mass. It was said that the isotopes of Element 118 lasted only about 200 milliseconds, while the isotope of Element 116 lasted only 1.2 milliseconds. It was hoped that these elements might be members of "an island of stability", which had long been sought. At that time it was hoped that a target of bismuth might be bombarded with krypton ions to make Element 119, which, in turn, would decay into Elements 117, 115, and 113.

On July 27, 2001 researchers at the Lawrence Berkeley Laboratory announced that their discovery of Element 118 was being retracted because workers at the GSI Laboratory in Germany and at Japanese laboratories failed to confirm their results. However, it was reported that different experiments at the Livermore Laboratory and Joint Institute from Nuclear Research in Dubna, Russia indicated that Element 116 had since been created.

Researchers at the Australian National Laboratory suggest that super-heavy elements may be more difficult to make than previously thought. Their data suggest the best way to encourage fusion in making super-heavy elements is to combine the lightest projectiles possible with the heaviest possible targets. This would minimize a so-called "quasi-fission process" in which a projectile nucleus steals protons and neutrons froma target nucleus. In this process the two nuclei are said to fly apart without ever having actually combined.

Erbium — (*Ytterby*, a town in Sweden), Er; at. wt. 167.26(3); at. no. 68; m.p. 1529°C; b.p. 2868°C; sp. gr. 9.066 (25°C); valence 3, Erbium, one of the so-called rare-earth elements of the lanthanide series, is found in the minerals mentioned under dysprosium above. In 1842 Mosander separated "yttria," found in the mineral *gadolinite,* into three fractions which he called *yttria, erbia,* and *terbia.* The names *erbia* and *terbia* became confused in this early period. After 1860, Mosander's *terbia* was known as *erbia,* and after 1877, the earlier known *erbia* became *terbia.* The *erbia* of this period was later shown to consist of five oxides, now known as *erbia, scandia, holmia, thulia* and *ytterbia.* By 1905 Urbain and James independently succeeded in isolating fairly pure Er_2O_3. Klemm and Bommer first produced reasonably pure erbium metal in 1934 by reducing the anhydrous chloride with potassium vapor. The pure metal is soft and malleable and has a bright, silvery, metallic luster. As with other rare-earth metals, its properties depend to a certain extent on the impurities present. The metal is fairly stable in air and does not oxidize as rapidly as some of the other rare-earth metals. Naturally occurring erbium is a mixture of six isotopes, all of which are stable. Twenty-seven radioactive isotopes of erbium are also recognized. Recent production techniques, using ion-exchange reactions, have resulted in much lower prices of the rare-earth metals and their compounds in recent years. The cost of 99.9% erbium metal is about $21/g. Erbium is finding nuclear and metallurgical uses. Added to vanadium, for example, erbium lowers the hardness and improves workability. Most of the rare-earth oxides have sharp absorption bands in the visible, ultraviolet, and near infrared. This property, associated with the electronic structure, gives beautiful pastel colors to many of the rare-earth salts. Erbium oxide gives a pink color and has been used as a colorant in glasses and porcelain enamel glazes.

Europium — (Europe), Eu; at. wt. 151.964(1); at. no. 63; m.p. 822°C; b.p. 1596°C; sp. gr. 5.244 (25°C); valence 2 or 3. In 1890 Boisbaudran obtained basic fractions from samarium-gadolinium concentrates which had spark spectral lines not accounted for by samarium or gadolinium. These lines subsequently have been shown to belong to europium. The discovery of europium is generally credited to Demarcay, who separated the rare earth in reasonably pure form in 1901. The pure metal was not isolated until recent years. Europium is now prepared by mixing Eu_2O_3 with a 10%-excess of lanthanum metal and heating the mixture in a tantalum crucible under high vacuum. The element is collected as a silvery-white metallic deposit on the walls of the crucible. As with other rare-earth metals, except for lanthanum, europium ignites in air at about 150 to 180°C. Europium is about as hard as lead and is quite ductile. It is the most reactive of the rare-earth metals, quickly oxidizing in air. It resembles calcium in its reaction with water. *Bastnasite* and *monazite* are the principal ores containing europium. Europium has been identified spectroscopically in the sun and certain stars. Europium isotopes are good neutron absorbers and are being studied for use in nuclear control applications. Europium oxide is now widely used as a phosphor activator and europium-activated yttrium vanadate is in commercial use as the red phosphor in color TV tubes. Europium-doped plastic has been used as a laser material. With the development of ion-exchange techniques and special processes, the cost of the metal has been greatly reduced in recent years. Natural europium contains two stable isotopes. Thirty five other radioactive isotopes and isomers are known. Europium is one of the rarest and most costly of the rare-earth metals. It is priced at about $60/g (99.9% pure).

Fermium — (Enrico Fermi [1901–1954], nuclear physicist), Fm; at. wt. [257]; at. no. 100; m.p. 1527°C. Fermium, the eighth transuranium element of the actinide series to be discovered, was identified by Ghiorso and co-workers in 1952 in the debris from a thermonuclear explosion in the Pacific in work involving the University of California Radiation Laboratory, the Argonne National Laboratory, and the Los Alamos Scientific

Laboratory. The isotope produced was the 20-hour ^{255}Fm. During 1953 and early 1954, while discovery of elements 99 and 100 was withheld from publication for security reasons, a group from the Nobel Institute of Physics in Stockholm bombarded ^{238}U with ^{16}O ions, and isolated a 30-min α-emitter, which they ascribed to ^{250}100, without claiming discovery of the element. This isotope has since been identified positively, and the 30-min half-life confirmed. The chemical properties of fermium have been studied solely with tracer amounts, and in normal aqueous media only the (III) oxidation state appears to exist. The isotope ^{254}Fm and heavier isotopes can be produced by intense neutron irradiation of lower elements such as plutonium by a process of successive neutron capture interspersed with beta decays until these mass numbers and atomic numbers are reached. Twenty isotopes and isomers of fermium are known to exist. ^{257}Fm, with a half-life of about 100.5 days, is the longest lived. ^{250}Fm, with a half-life of 30 min, has been shown to be a product of decay of Element ^{254}102. It was by chemical identification of ^{250}Fm that production of Element 102 (nobelium) was confirmed. Fermium would probably have chemical properties resembling erbium.

Fluorine — (L. and F. *fluere,* flow, or flux), F; at. wt. 18.9984032(5); at. no. 9; m.p. –219.62°C (1 atm); b.p. –188.12°C (1 atm); t_c –129.02°C; density 1.696 g/L (0°C, 1 atm); liq. den. at b.p. 1.50 g/cm^3; valence 1. In 1529, Georgius Agricola described the use of fluorspar as a flux, and as early as 1670 Schwandhard found that glass was etched when exposed to fluorspar treated with acid. Scheele and many later investigators, including Davy, Gay-Lussac, Lavoisier, and Thenard, experimented with hydrofluoric acid, some experiments ending in tragedy. The element was finally isolated in 1886 by Moisson after nearly 74 years of continuous effort. Fluorine occurs chiefly in *fluorspar* (CaF_2) and *cryolite* (Na_2AlF_6), and is in *topaz* and other minerals. It is a member of the halogen family of elements, and is obtained by electrolyzing a solution of potassium hydrogen fluoride in anhydrous hydrogen fluoride in a vessel of metal or transparent fluorspar. Modern commercial production methods are essentially variations on the procedures first used by Moisson. Fluorine is the most electronegative and reactive of all elements. It is a pale yellow, corrosive gas, which reacts with practically all organic and inorganic substances. Finely divided metals, glass, ceramics, carbon, and even water burn in fluorine with a bright flame. Until World War II, there was no commercial production of elemental fluorine. The atom bomb project and nuclear energy applications, however, made it necessary to produce large quantities. Safe handling techniques have now been developed and it is possible at present to transport liquid fluorine by the ton. Fluorine and its compounds are used in producing uranium (from the hexafluoride) and more than 100 commercial fluorochemicals, including many well-known high-temperature plastics. Hydrofluoric acid is extensively used for etching the glass of light bulbs, etc. Fluorochloro hydrocarbons have been extensively used in air conditioning and refrigeration. However, in recent years the U.S. and other countries have been phasing out ozone-depleting substances, such as the fluorochloro hydrocarbons that have been used in these applications. It has been suggested that fluorine might be substituted for hydrogen wherever it occurs in organic compounds, which could lead to an astronomical number of new fluorine compounds. The presence of fluorine as a soluble fluoride in drinking water to the extent of 2 ppm may cause mottled enamel in teeth, when used by children acquiring permanent teeth; in smaller amounts, however, fluorides are said to be beneficial and used in water supplies to prevent dental cavities. Elemental fluorine has been studied as a rocket propellant as it has an exceptionally high specific impulse value. Compounds of fluorine with rare gases have now been confirmed. Fluorides of xenon, radon, and krypton are among those known. Elemental fluorine and the fluoride ion are highly toxic. The free element has a characteristic pungent odor, detectable in concentrations as low as 20 ppb, which is below the safe working level. The recommended maximum allowable concentration for a daily 8-hour time-weighted exposure is 1 ppm. Fluorine is known to have fourteen isotopes.

Francium — (France), Fr; at. no. 87; at. wt. [223]; m.p. 27°C; valence 1. Discovered in 1939 by Mlle. Marguerite Perey of the Curie Institute, Paris. Francium, the heaviest known member of the alkali metal series, occurs as a result of an alpha disintegration of actinium. It can also be made artificially by bombarding thorium with protons. While it occurs naturally in uranium minerals, there is probably less than an ounce of francium at any time in the total crust of the earth. It has the highest equivalent weight of any element, and is the most unstable of the first 101 elements of the periodic system. Thirty-six isotopes and isomers of francium are recognized. The longest lived ^{223}Fr(Ac, K), a daughter of ^{227}Ac, has a half-life of 21.8 min. This is the only isotope of francium occurring in nature. Because all known isotopes of francium are highly unstable, knowledge of the chemical properties of this element comes from radiochemical techniques. No weighable quantity of the element has been prepared or isolated. The chemical properties of francium most closely resemble cesium. In 1996, researchers Orozco, Sprouse, and co-workers at the State University of New York, Stony Brook, reported that they had produced francium atoms by bombarding ^{18}O atoms at a gold target heated almost to its melting point. Collisions between gold and oxygen nuclei created atoms of francium-210 which had 87 protons and 123 neutrons. This team reported they had generated about 1 million francium-210 ions per second and held 1000 or more atoms at a time for about 20 secs. in a magnetic trap they had devised before the atoms decayed or escaped. Enough francium was trapped so that a video camera could capture the light given off by the atoms as they fluoresced. A cluster of about 10,000 francium atoms appeared as a glowing sphere about 1 mm in diameter. It is thought that the francium atoms could serve as miniature laboratoires for probing interactions between electrons and quarks.

Gadolinium — (*gadolinite,* a mineral named for Gadolin, a Finnish chemist), Gd; at. wt. 157.25(3); at. no. 64; m.p. 1313°C; b.p. 3273°C; sp. gr. 7.901 (25°C); valence 3. Gadolinia, the oxide of gadolinium, was separated by Marignac in 1880 and Lecoq de Boisbaudran independently isolated the element from Mosander's "yttria" in 1886. The element was named for the mineral *gadolinite* from which this rare earth was originally obtained. Gadolinium is found in several other minerals, including *monazite* and *bastnasite,* which are of commercial importance. The element has been isolated only in recent years. With the development of ion-exchange and solvent extraction techniques, the availability and price of gadolinium and the other rare-earth metals have greatly improved. Thirty-one isotopes and isomers of gadolinium are now recognized; seven are stable and occur naturally. The metal can be prepared by the reduction of the anhydrous fluoride with metallic calcium. As with other related rare-earth metals, it is silvery

white, has a metallic luster, and is malleable and ductile. At room temperature, gadolinium crystallizes in the hexagonal, close-packed α form. Upon heating to 1235°C, α gadolinium transforms into the β form, which has a body-centered cubic structure. The metal is relatively stable in dry air, but in moist air it tarnishes with the formation of a loosely adhering oxide film which spalls off and exposes more surface to oxidation. The metal reacts slowly with water and is soluble in dilute acid. Gadolinium has the highest thermal neutron capture cross-section of any known element (49,000 barns). Natural gadolinium is a mixture of seven isotopes. Two of these, ^{155}Gd and ^{157}Gd, have excellent capture characteristics, but they are present naturally in low concentrations. As a result, gadolinium has a very fast burnout rate and has limited use as a nuclear control rod material. It has been used in making gadolinium yttrium garnets, which have microwave applications. Compounds of gadolinium are used in making phosphors for color TV tubes. The metal has unusual superconductive properties. As little as 1% gadolinium has been found to improve the workability and resistance of iron, chromium, and related alloys to high temperatures and oxidation. Gadolinium ethyl sulfate has extremely low noise characteristics and may find use in duplicating the performance of amplifiers, such as the maser. The metal is ferromagnetic. Gadolinium is unique for its high magnetic moment and for its special Curie temperature (above which ferromagnetism vanishes) lying just at room temperature. This suggests uses as a magnetic component that senses hot and cold. The price of the metal is about $5/g (99.9% purity).

Gallium — (L. *Gallia,* France; also from Latin, *gallus,* a translation of Lecoq, a cock), Ga; at. wt. 69.723(1); at. no. 31; m.p. 29.76°C; b.p. 2204°C; sp. gr. 5.904 (29.6°C) solid; sp. gr. 6.095 (29.6°C) liquid; valence 2 or 3. Predicted and described by Mendeleev as ekaaluminum, and discovered spectroscopically by Lecoq de Boisbaudran in 1875, who in the same year obtained the free metal by electrolysis of a solution of the hydroxide in KOH. Gallium is often found as a trace element in *diaspore, sphalerite, germanite, bauxite,* and *coal.* Some flue dusts from burning coal have been shown to contain as much as 1.5% gallium. It is the only metal, except for mercury, cesium, and rubidium, which can be liquid near room temperatures; this makes possible its use in high-temperature thermometers. It has one of the longest liquid ranges of any metal and has a low vapor pressure even at high temperatures. There is a strong tendency for gallium to supercool below its freezing point. Therefore, seeding may be necessary to initiate solidification. Ultra-pure gallium has a beautiful, silvery appearance, and the solid metal exhibits a conchoidal fracture similar to glass. The metal expands 3.1% on solidifying; therefore, it should not be stored in glass or metal containers, as they may break as the metal solidifies. Gallium wets glass or porcelain, and forms a brilliant mirror when it is painted on glass. It is widely used in doping semiconductors and producing solid-state devices such as transistors. High-purity gallium is attacked only slowly by mineral acids. Magnesium gallate containing divalent impurities such as Mn^{+2} is finding use in commercial ultraviolet activated powder phosphors. Gallium nitride has been used to produce blue light-emitting diodes. Blue LED's used in compact disc applications can be used to store a 2-hr movie, for example, on one 5-in. diameter disc. Extensive use of gallium has found recent application in the **Gallex Detector Experiment** located in the Gran Sasso Underground Laboratory in Italy. This underground facility has been built by the Italian Istituto Nazionale di Fisica Nucleare in the middle of a highway tunnel through the Abruzzese mountains, about 150 km east of Rome. The experiment is shielded by a 3300-m water-equivalent of rock. In this experiment, 30.3 tons of gallium in the form of 110 tons of $GaCl_3$-HCl solution are being used to detect solar neutrinos. The production of ^{71}Ge from gallium is being measured.Gallium arsenide is capable of converting electricity directly into coherent light. Gallium readily alloys with most metals, and has been used as a component in low-melting alloys. Its toxicity appears to be of a low order, but should be handled with care until more data are forthcoming. Natural gallium contains two stable isotopes. Twenty-six other isotopes, one of which is an isomer, are known. The metal can be supplied in ultrapure form (99.99999+%). The cost is about $5/g (99.999%).

Germanium — (L. *Germania,* Germany), Ge; at. wt. 72.61(2); at. no. 32; m.p. 938.25°C; b.p. 2833°C; sp. gr. 5.323 (25°C); valence 2 and 4. Predicted by Mendeleev in 1871 as ekasilicon, and discovered by Winkler in 1886. The metal is found in *argyrodite,* a sulfide of germanium and silver; in *germanite,* which contains 8% of the element; in zinc ores; in coal; and in other minerals. The element is frequently obtained commercially from flue dusts of smelters processing zinc ores, and has been recovered from the by-products of combustion of certain coals. Its presence in coal insures a large reserve of the element in the years to come. Germanium can be separated from other metals by fractional distillation of its volatile tetrachloride. The tetrachloride may then be hydrolyzed to give GeO_2; the dioxide can be reduced with hydrogen to give the metal. Recently developed zone-refining techniques permit the production of germanium of ultra-high purity. The element is a gray-white metalloid, and in its pure state is crystalline and brittle, retaining its luster in air at room temperature. It is a very important semiconductor material. Zone-refining techniques have led to production of crystalline germanium for semiconductor use with an impurity of only one part in 10^{10}. Doped with arsenic, gallium, or other elements, it is used as a transistor element in thousands of electronic applications. Its application in fiber optics and infra-red optical systems now provides the largest use for germanium. Germanium is also finding many other applications including use as an alloying agent, as a phosphor in fluorescent lamps, and as a catalyst. Germanium and germanium oxide are transparent to the infrared and are used in infrared spectroscopes and other optical equipment, including extremely sensitive infrared detectors. Germanium oxide's high index of refraction and dispersion has made it useful as a component of glasses used in wide-angle camera lenses and microscope objectives. The field of organogermanium chemistry is becoming increasingly important. Certain germanium compounds have a low mammalian toxicity, but a marked activity against certain bacteria, which makes them of interest as chemotherapeutic agents. The cost of germanium is about $10/g (99.999% purity). Thirty isotopes and isomers are known, five of which occur naturally.

Gold — (Sanskrit *Jval;* Anglo-Saxon *gold*), Au (L. *aurum,* gold); at. wt. 196.96654(3); at. no. 79; m.p. 1064.18°C; b.p. 2856°C; sp. gr. ~19.3 (20°C); valence 1 or 3. Known and highly valued from earliest times, gold is found in nature as the free metal and in tellurides; it is very widely distributed and is almost always associated with quartz or pyrite. It occurs in veins and alluvial deposits, and is often separated from rocks and other minerals by sluicing and panning operations. About 25% of

the world's gold output comes from South Africa, and about two thirds of the total U.S. production now comes from South Dakota and Nevada. The metal is recovered from its ores by cyaniding, amalgamating, and smelting processes. Refining is also frequently done by electrolysis. Gold occurs in sea water to the extent of 0.1 to 2 mg/ton, depending on the location where the sample is taken. As yet, no method has been found for recovering gold from sea water profitably. It is estimated that all the gold in the world, so far refined, could be placed in a single cube 60 ft on a side. Of all the elements, gold in its pure state is undoubtedly the most beautiful. It is metallic, having a yellow color when in a mass, but when finely divided it may be black, ruby, or purple. The Purple of Cassius is a delicate test for auric gold. It is the most malleable and ductile metal; 1 oz. of gold can be beaten out to 300 ft^2. It is a soft metal and is usually alloyed to give it more strength. It is a good conductor of heat and electricity, and is unaffected by air and most reagents. It is used in coinage and is a standard for monetary systems in many countries. It is also extensively used for jewelry, decoration, dental work, and for plating. It is used for coating certain space satellites, as it is a good reflector of infrared and is inert. Gold, like other precious metals, is measured in troy weight; when alloyed with other metals, the term *carat* is used to express the amount of gold present, 24 carats being pure gold. For many years the value of gold was set by the U.S. at $20.67/troy ounce; in 1934 this value was fixed by law at $35.00/troy ounce, 9/10th fine. On March 17, 1968, because of a gold crisis, a two-tiered pricing system was established whereby gold was still used to settle international accounts at the old $35.00/troy ounce price while the price of gold on the private market would be allowed to fluctuate. Since this time, the price of gold on the free market has fluctuated widely. The price of gold on the free market reached a price of $620/troy oz. in January 1980. More recently, the U.K. and other nations, including the I.M.F. have sold or threatened to sell a sizeable portion of their gold reserves. This has caused wide fluctuations in the price of gold. Because this has damaged the economy of some countries, a moratorium for a few years has been declared. This has tended to stabilize temporarily the price of gold. The most common gold compounds are auric chloride ($AuCl_3$) and chlorauric acid ($HAuCl_4$), the latter being used in photography for toning the silver image. Gold has forty-eight recognized isotopes and isomers; ^{198}Au, with a half-life of 2.7 days, is used for treating cancer and other diseases. Disodium aurothiomalate is administered intramuscularly as a treatment for arthritis. A mixture of one part nitric acid with three of hydrochloric acid is called *aqua regia* (because it dissolved gold, the King of Metals). Gold is available commercially with a purity of 99.999+%. For many years the temperature assigned to the freezing point of gold has been 1063.0°C; this has served as a calibration point for the International Temperature Scales (ITS-27 and ITS-48) and the International Practical Temperature Scale (IPTS-48). In 1968, a new International Practical Temperature Scale (IPTS-68) was adopted, which demanded that the freezing point of gold be changed to 1064.43°C. In 1990 a new International Temperature Scale (ITS-90) was adopted bringing the t.p. (triple point) of H_2O (t_{90} (°C)) to 0.01°C and the freezing point of gold to 1064.18°C. The specific gravity of gold has been found to vary considerably depending on temperature, how the metal is precipitated, and cold-worked. As of December 2001, gold was priced at about $275/troy oz. ($8.50/g).

Hafnium — (*Hafnia,* Latin name for Copenhagen), Hf; at. wt. 178.49(2); at. no. 72; m.p. 2233°C; b.p. 4603°C; sp. gr. 13.31 (20°C); valence 4. Hafnium was thought to be present in various minerals and concentrations many years prior to its discovery, in 1923, credited to D. Coster and G. von Hevesey. On the basis of the Bohr theory, the new element was expected to be associated with zirconium. It was finally identified in *zircon* from Norway, by means of X-ray spectroscopic analysis. It was named in honor of the city in which the discovery was made. Most zirconium minerals contain 1 to 5% hafnium. It was originally separated from zirconium by repeated recrystallization of the double ammonium or potassium fluorides by von Hevesey and Jantzen. Metallic hafnium was first prepared by van Arkel and deBoer by passing the vapor of the tetraiodide over a heated tungsten filament. Almost all hafnium metal now produced is made by reducing the tetrachloride with magnesium or with sodium (Kroll Process). Hafnium is a ductile metal with a brilliant silver luster. Its properties are considerably influenced by the impurities of zirconium present. Of all the elements, zirconium and hafnium are two of the most difficult to separate. Their chemistry is almost identical, however, the density of zirconium is about half that of hafnium. Very pure hafnium has been produced, with zirconium being the major impurity. Natural hafnium contains six isotopes, one of which is slightly radioactive. Hafnium has a total of 41 recognized isotopes and isomers. Because hafnium has a good absorption cross section for thermal neutrons (almost 600 times that of zirconium), has excellent mechanical properties, and is extremely corrosion resistant, it is used for reactor control rods. Such rods are used in nuclear submarines. Hafnium has been successfully alloyed with iron, titanium, niobium, tantalum, and other metals. Hafnium carbide is the most refractory binary composition known, and the nitride is the most refractory of all known metal nitrides (m.p. 3310°C). Hafnium is used in gas-filled and incandescent lamps, and is an efficient "getter" for scavenging oxygen and nitrogen. Finely divided hafnium is pyrophoric and can ignite spontaneously in air. Care should be taken when machining the metal or when handling hot sponge hafnium. At 700°C hafnium rapidly absorbs hydrogen to form the composition $HfH_{1.86}$. Hafnium is resistant to concentrated alkalis, but at elevated temperatures reacts with oxygen, nitrogen, carbon, boron, sulfur, and silicon. Halogens react directly to form tetrahalides. The price of the metal is about $2/g. The yearly demand for hafnium in the U.S. is now in excess of 50,000 kg.

Hahnium — A name previously used for Element 105, now named *dubnium*.

Hassium — (named for the German state, Hesse) Hs; at.wt. [265]; at.no. 108. This element was first synthesized and identified in 1964 by the same G.S.I. Darmstadt Group who first identified *Bohrium* and *Meitnerium.* Presumably this element has chemical properties similar to osmium. Isotope $^{265}108$ was produced using a beam of ^{58}Fe projectiles, produced by the Universal Linear Accelerator (UNILAC) to bombard a ^{208}Pb target. Discovery of *Bohrium* and *Meitnerium* was made using detection of isotopes with odd proton and neutron numbers. Elements having even atomic numbers have been thought to be less stable against spontaneous fusion than odd elements. The production of $^{265}108$ in the same reaction as was used at G.S.I. was confirmed at Dubna with detection of the seventh member of the decay chain ^{253}Es. Isotopes of *Hassium* are believed to decay by spontaneous fission, explaining why 109 was

produced before 108. Isotope $^{265}108$ and $^{266}108$ are thought to decay to $^{261}106$, which in turn decay to $^{257}104$ and $^{253}102$. The IUPAC adopted the name *Hassium* after the German state of Hesse in September 1997. In June 2001 it was announced that hassium is now the heaviest element to have its chemical properties analyzed. A research team at the UNILAC heavy-ion accelerator in Darmstadt, Germany built an instrument to detect and analyze hassium. Atoms of curium-248 were collided with atoms of magnesium-26, producing about 6 atoms of hassium with a half-life of 9 sec. This was sufficiently long to obtain data showing that hassium atoms react with oxygen to form hassium oxide molecules. These condensed at a temperature consistent with the behavior of Group 8 elements. This experiment appears to confirm hassium's location under osmium in the periodic table.

Helium — (Gr. *helios*, the sun), He; at. wt. 4.002602(2); at. no. 2; m.p. below — 272.2°C (26 atm); b.p. — 268.93°C; t_c -267.96°C; density 0.1785 g/l (0°C, 1 atm); liquid density 7.62 lb/ft^3 at. b.p.; valence usually 0. Evidence of the existence of helium was first obtained by Janssen during the solar eclipse of 1868 when he detected a new line in the solar spectrum; Lockyer and Frankland suggested the name *helium* for the new element; in 1895, Ramsay discovered helium in the uranium mineral *cleveite*, and it was independently discovered in cleveite by the Swedish chemists Cleve and Langlet about the same time. Rutherford and Royds in 1907 demonstrated that α particles are helium nuclei. Except for hydrogen, helium is the most abundant element found throughout the universe. Helium is extracted from natural gas; all natural gas contains at least trace quantities of helium. It has been detected spectroscopically in great abundance, especially in the hotter stars, and it is an important component in both the proton-proton reaction and the carbon cycle, which account for the energy of the sun and stars. The fusion of hydrogen into helium provides the energy of the hydrogen bomb. The helium content of the atmosphere is about 1 part in 200,000. It is present in various radioactive minerals as a decay product. Much of the world's supply of helium is obtained from wells in Texas, Colorado, and Kansas. The only other known helium extraction plants, outside the United States, in 1999 were in Poland, Russia, China, Algeria, and India. The cost of helium has fallen from $2500/ft^3 in 1915 to about 2.5¢/cu.ft. (.028 cu meters) in 1999. Helium has the lowest melting point of any element and has found wide use in cryogenic research, as its boiling point is close to absolute zero. Its use in the study of superconductivity is vital. Using liquid helium, Kurti and co-workers, and others, have succeeded in obtaining temperatures of a few microkelvins by the adiabatic demagnetization of copper nuclei, starting from about 0.01 K. Liquid helium (He^4) exists in two forms: He^4I and He^4II, with a sharp transition point at 2.174 K (3.83 cm Hg). He^4I (above this temperature) is a normal liquid, but He^4II (below it) is unlike any other known substance. It expands on cooling; its conductivity for heat is enormous; and neither its heat conduction nor viscosity obeys normal rules. It has other peculiar properties. Helium is the only liquid that cannot be solidified by lowering the temperature. It remains liquid down to absolute zero at ordinary pressures, but it can readily be solidified by increasing the pressure. Solid ^{3}He and ^{4}He are unusual in that both can readily be changed in volume by more than 30% by application of pressure. The specific heat of helium gas is unusually high. The density of helium vapor at the normal boiling point is also very high, with the vapor expanding greatly when heated to room temperature. Containers filled with helium gas at 5 to 10 K should be treated as though they contained liquid helium due to the large increase in pressure resulting from warming the gas to room temperature. While helium normally has a 0 valence, it seems to have a weak tendency to combine with certain other elements. Means of preparing helium diflouride have been studied, and species such as HeNe and the molecular ions He^+ and He^{++} have been investigated. Helium is widely used as an inert gas shield for arc welding; as a protective gas in growing silicon and germanium crystals, and in titanium and zirconium production; as a cooling medium for nuclear reactors, and as a gas for supersonic wind tunnels. A mixture of helium and oxygen is used as an artificial atmosphere for divers and others working under pressure. Different ratios of He/O_2 are used for different depths at which the diver is operating. Helium is extensively used for filling balloons as it is a much safer gas than hydrogen. One of the recent largest uses for helium has been for pressuring liquid fuel rockets. A Saturn booster such as used on the Apollo lunar missions required about 13 million ft^{3}of helium for a firing, plus more for checkouts. Liquid helium's use in magnetic resonance imaging (MRI) continues to increase as the medical profession accepts and develops new uses for the equipment. This equipment is providing accurate diagnoses of problems where exploratory surgery has previously been required to determine problems. Another medical application that is being developed uses MRI to determine by blood analysis whether a patient has any form of cancer. Lifting gas applications are increasing. Various companies in addition to Goodyear, are now using "blimps" for advertising. The Navy and the Air Force are investigating the use of airships to provide early warning systems to detect low-flying cruise missiles. The Drug Enforcement Agency has used radar-equipped blimps to detect drug smugglers along the southern border of the U.S. In addition, NASA is currently using helium-filled balloons to sample the atmosphere in Antarctica to determine what is depleting the ozone layer that protects Earth from harmful U.V. radiation. Research on and development of materials which become superconductive at temperatures well above the boiling point of helium could have a major impact on the demand for helium. Less costly refrigerants having boiling points considerably higher could replace the present need to cool such superconductive materials to the boiling point of helium. Natural helium contains two stable isotopes ^{3}He and ^{4}He. ^{3}He is present in very small quantities. Six other isotopes of helium are now recognized.

Holmium — (L. *Holmia* , for Stockholm), Ho; at. wt. 164.93032(2); at. no 67; m.p. 1474°C; b.p. 2700°C; sp. gr. 8.795 (25°C); valence + 3. The spectral absorption bands of holmium were noticed in 1878 by the Swiss chemists Delafontaine and Soret, who announced the existence of an "Element X". Cleve, of Sweden, later independently discovered the element while working on erbia earth. The element is named after Cleve's native city. Pure holmia, the yellow oxide, was prepared by Homberg in 1911. Holmium occurs in *gadolinite, monazite,* and in other rare-earth minerals. It is commercially obtained from monazite, occurring in that mineral to the extent of about 0.05%. It has been isolated by the reduction of its anhydrous chloride or fluoride with calcium metal. Pure holmium has a metallic to bright silver luster. It is relatively soft and malleable, and is stable in dry air at room temperature, but rapidly oxidizes in moist air and at elevated temperatures. The metal has unusual magnetic properties. Few uses have yet been found for the element. The element, as with other rare earths, seems

to have a low acute toxic rating. Natural holmium consists of one isotope ^{165}Ho, which is not radioactive. Holmium has 49 other isotopes known, all of which are radioactive. The price of 99.9% holmium metal is about $20/g.

Hydrogen — (Gr. *hydro*, water, and *genes,* forming), H; at. wt. 1.00794(7); at. no. 1; m.p. –259.34°C; b.p. –252.87°C; t_c –240.18; density 0.08988 g/l; density (liquid) 70.8 g/l (–253°C); density (solid) 70.6 g/l (–262°C); valence 1. Hydrogen was prepared many years before it was recognized as a distinct substance by Cavendish in 1766. It was named by Lavoisier. Hydrogen is the most abundant of all elements in the universe, and it is thought that the heavier elements were, and still are, being built from hydrogen and helium. It has been estimated that hydrogen makes up more than 90% of all the atoms or three quarters of the mass of the universe. It is found in the sun and most stars, and plays an important part in the proton-proton reaction and carbon-nitrogen cycle, which accounts for the energy of the sun and stars. It is thought that hydrogen is a major component of the planet Jupiter and that at some depth in the planet's interior the pressure is so great that solid molecular hydrogen is converted into solid metallic hydrogen. In 1973, it was reported that a group of Russian experimenters may have produced metallic hydrogen at a pressure of 2.8 Mbar. At the transition the density changed from 1.08 to 1.3 g/cm^3. Earlier, in 1972, a Livermore (California) group also reported on a similar experiment in which they observed a pressure-volume point centered at 2 Mbar. It has been predicted that metallic hydrogen may be metastable; others have predicted it would be a superconductor at room temperature. On earth, hydrogen occurs chiefly in combination with oxygen in water, but it is also present in organic matter such as living plants, petroleum, coal, etc. It is present as the free element in the atmosphere, but only to the extent of less than 1 ppm by volume. It is the lightest of all gases, and combines with other elements, sometimes explosively, to form compounds. Great quantities of hydrogen are required commercially for the fixation of nitrogen from the air in the Haber ammonia process and for the hydrogenation of fats and oils. It is also used in large quantities in methanol production, in hydrodealkylation, hydrocracking, and hydrodesulfurization. It is also used as a rocket fuel, for welding, for production of hydrochloric acid, for the reduction of metallic ores, and for filling balloons. The lifting power of 1 ft^3 of hydrogen gas is about 0.076 lb at 0°C, 760 mm pressure. Production of hydrogen in the U.S. alone now amounts to about 3 billion cubic feet per year. It is prepared by the action of steam on heated carbon, by decomposition of certain hydrocarbons with heat, by the electrolysis of water, or by the displacement from acids by certain metals. It is also produced by the action of sodium or potassium hydroxide on aluminum. Liquid hydrogen is important in cryogenics and in the study of superconductivity, as its melting point is only a 20°C above absolute zero. Hydrogen consists of three isotopes, most of which is ^{1}H. The ordinary isotope of hydrogen, H, is known as *protium*. In 1932, Urey announced the discovery of a stable isotope, deuterium (^{2}H or D) with an atomic weight of 2. Deuterium is present in natural hydrogen to the extent of 0.015%. Two years later an unstable isotope, tritium (^{3}H), with an atomic weight of 3 was discovered. Tritium has a half-life of about 12.32 years. Tritium atoms are also present in natural hydrogen but in much smaller proportion. Tritium is readily produced in nuclear reactors and is used in the production of the hydrogen bomb. It is also used as a radioactive agent in making luminous paints, and as a tracer. On August 27, 2001 Russian, French, and Japanese physicists working at the Joint Institute for Nuclear Research near Moscow reported they had made "super-heavy hydrogen", which had a nucleus with one proton and four neutrons. Using an accelerator, they used a beam of helium-6 nuclei to strike a hydrogen target, which resulted in the occasional production of a hydrogen-5 nucleus plus a helium-2 nucleus. These unstable particles quickly disintegrated. This resulted in two protons from the He-2, a triton, and two neutrons from the H-5 breakup. Deuterium gas is readily available, without permit, at about $1/l. Heavy water, deuterium oxide (D_2O), which is used as a moderator to slow down neutrons, is available without permit at a cost of 6c to $1/g, depending on quantity and purity. About 1000 tons (4,400,000 kg) of deuterium oxide (heavy water) are now in use at the Sudbury (Ontario) Neutrino Observatory. This observatory is taking data to provide new revolutionary insight into the properties of neutrinos and into the core of the sun. The heavy water is on loan from Atomic Energy of Canada, Ltd. (AECL). The observatory and detectors are located 6800 ft (2072 m) deep in the Creighton mine of the International Nickel Co., near Sudbury. The heavy water is contained in an acrylic vessel, 12 m in diameter. Neutrinos react with the heavy water to produce Cherenkov radiation. This light is then detected with 9600 photomultiplier tubes surrounding the vessel. The detector laboratory is immensely clean to reduce background radiation, which otherwise hide the very weak signals from neutrinos. Quite apart from isotopes, it has been shown that hydrogen gas under ordinary conditions is a mixture of two kinds of molecules, known as *ortho-* and *para-*hydrogen, which differ from one another by the spins of their electrons and nuclei. Normal hydrogen at room temperature contains 25% of the *para* form and 75% of the *ortho* form. The *ortho* form cannot be prepared in the pure state. Since the two forms differ in energy, the physical properties also differ. The melting and boiling points of *para*hydrogen are about 0.1°C lower than those of normal hydrogen. Consideration is being given to an entire economy based on solar- and nuclear-generated hydrogen. Located in remote regions, power plants would electrolyze sea water; the hydrogen produced would travel to distant cities by pipelines. Pollution-free hydrogen could replace natural gas, gasoline, etc., and could serve as a reducing agent in metallurgy, chemical processing, refining, etc. It could also be used to convert trash into methane and ethylene. Public acceptance, high capital investment, and the high present cost of hydrogen with respect to present fuels are but a few of the problems facing establishment of such an economy. Hydrogen is being investigated as a substitute for deep-sea diving applications below 300 m. Hydrogen is readily available from air product suppliers.

Indium — (from the brilliant indigo line in its spectrum), In; at. wt. 114.818(3); at. no. 49; m.p. 156.60°C; b.p. 2072°C; sp. gr. 7.31 (20°C); valence 1, 2, or 3. Discovered by Reich and Richter, who later isolated the metal. Indium is most frequently associated with zinc materials, and it is from these that most commercial indium is now obtained; however, it is also found in iron, lead, and copper ores. Until 1924, a gram or so constituted the world's supply of this element in isolated form. It is probably about as abundant as silver. About 4 million troy ounces of indium are now produced annually in the Free World. Canada is presently producing more than 1,000,000 troy ounces annually. The present cost of indium is about $2 to $10/g, depending on quantity and purity. It is available in ultrapure form. Indium is a very soft, silvery-white metal with a brilliant lus-

ter. The pure metal gives a high-pitched "cry" when bent. It wets glass, as does gallium. It has found application in making low-melting alloys; an alloy of 24% indium-76% gallium is liquid at room temperature. Indium is used in making bearing alloys, germanium transistors, rectifiers, thermistors, liquid crystal displays, high definition television, batteries, and photoconductors. It can be plated onto metal and evaporated onto glass, forming a mirror as good as that made with silver but with more resistance to atmospheric corrosion. There is evidence that indium has a low order of toxicity; however, care should be taken until further information is available. Seventy isotopes and isomers are now recognized (more than any other element). Natural indium contains two isotopes. One is stable. The other, ^{115}In, comprising 95.71% of natural indium is slightly radioactive with a very long half-life.

Iodine — (Gr. *iodes,* violet), I; at. wt. 126.90447(3); at. no. 53; m.p. 113.7°C; b.p. 184.4°C; t_c 546°C; density of the gas 11.27 g/l; sp. gr. solid 4.93 (20°C); valence 1, 3, 5, or 7. Discovered by Courtois in 1811. Iodine, a halogen, occurs sparingly in the form of iodides in sea water from which it is assimilated by seaweeds, in Chilean saltpeter and nitrate-bearing earth, known as *caliche* in brines from old sea deposits, and in brackish waters from oil and salt wells. Ultrapure iodine can be obtained from the reaction of potassium iodide with copper sulfate. Several other methods of isolating the element are known. Iodine is a bluish-black, lustrous solid, volatilizing at ordinary temperatures into a blue-violet gas with an irritating odor; it forms compounds with many elements, but is less active than the other halogens, which displace it from iodides. Iodine exhibits some metallic-like properties. It dissolves readily in chloroform, carbon tetrachloride, or carbon disulfide to form beautiful purple solutions. It is only slightly soluble in water. Iodine compounds are important in organic chemistry and very useful in medicine. Forty two isotopes and isomers are recognized. Only one stable isotope, ^{127}I is found in nature. The artificial radioisotope ^{131}I, with a half-life of 8 days, has been used in treating the thyroid gland. The most common compounds are the iodides of sodium and potassium (KI) and the iodates (KIO_3). Lack of iodine is the cause of goiter. Iodides, and thyroxin which contains iodine, are used internally in medicine, and a solution of KI and iodine in alcohol is used for external wounds. Potassium iodide finds use in photography. The deep blue color with starch solution is characteristic of the free element. Care should be taken in handling and using iodine, as contact with the skin can cause lesions; iodine vapor is intensely irritating to the eyes and mucous membranes. Elemental iodine costs about 25 to 75¢/g depending on purity and quantity.

Iridium — (L. *iris*, rainbow), Ir; at. wt. 192.217(3); at. no. 77; m.p. 2446°C; b.p. 4428°C; sp. gr. 22.42 (17°C); valence 3 or 4. Discovered in 1803 by Tennant in the residue left when crude platinum is dissolved by aqua regia. The name iridium is appropriate, for its salts are highly colored. Iridium, a metal of the platinum family, is white, similar to platinum, but with a slight yellowish cast. It is very hard and brittle, making it very hard to machine, form, or work. It is the most corrosion-resistant metal known, and was used in making the standard meter bar of Paris, which is a 90% platinum-10% iridium alloy. This meter bar was replaced in 1960 as a fundamental unit of length (see under Krypton). Iridium is not attacked by any of the acids nor by aqua regia, but is attacked by molten salts, such as NaCl and NaCN. Iridium occurs uncombined in nature with platinum and other metals of this family in alluvial deposits. It is recovered as a by-product from the nickel mining industry. The largest reserves and production of the platinum group of metals, which includes iridium, is in South Africa, followed by Russia and Canada. The U.S. has only one active mine, located at Nye, MT. The presence of iridium has recently been used in examining the Cretaceous-Tertiary (K-T) boundary. Meteorites contain small amounts of iridium. Because iridium is found widely distributed at the K-T boundary, it has been suggested that a large meteorite or asteroid collided with the earth, killing the dinosaurs, and creating a large dust cloud and crater. Searches for such a crater point to one in the Yucatan, known as Chicxulub. Iridium has found use in making crucibles and apparatus for use at high temperatures. It is also used for electrical contacts. Its principal use is as a hardening agent for platinum. With osmium, it forms an alloy which is used for tipping pens and compass bearings. The specific gravity of iridium is only very slightly lower than that of osmium, which has been generally credited as being the heaviest known element. Calculations of the densities of iridium and osmium from the space lattices gives values of 22.65 and 22.61 g/cm^3, respectively. These values may be more reliable than actual physical measurements. At present, therefore, we know that either iridium or osmium is the densest known element, but the data do not yet allow selection between the two. Natural iridium contains two stable isotopes. Forty-five other isotopes, all radioactive, are now recognized. Iridium (99.9%) costs about $100/g.

Iron — (Anglo-Saxon, *iron*), Fe (L. *ferrum*); at. wt. 55.845(2); at. no. 26; m.p. 1538°C; b.p. 2861°C; sp. gr. 7.874 (20°C); valence 2, 3, 4, or 6. The use of iron is prehistoric. Genesis mentions that Tubal-Cain, seven generations from Adam, was "an instructor of every artificer in brass and iron." A remarkable iron pillar, dating to about A.D. 400, remains standing today in Delhi, India. This solid shaft of wrought iron is about $7^1/_4$ m high by 40 cm in diameter. Corrosion to the pillar has been minimal although it has been exposed to the weather since its erection. Iron is a relatively abundant element in the universe. It is found in the sun and many types of stars in considerable quantity. Its nuclei are very stable. It has been suggested that the iron we have here on earth may have originated in a supernova. Iron is a very difficult element to produce in ordinary nuclear reactions, such as would take place in the sun. Iron is found native as a principal component of a class of iron-nickel meteorites known as *siderites*, and is a minor constituent of the other two classes of meteorites. The core of the earth, 2150 miles in radius, is thought to be largely composed of iron with about 10% occluded hydrogen. The metal is the fourth most abundant element, by weight, making up the crust of the earth. The most common ore is *hematite* (Fe_2O_3). Magnetite (Fe_3O_4) is frequently seen as *black sands* along beaches and banks of streams. *Lodestone* is another form of magnetite. *Taconite* is becoming increasingly important as a commercial ore. Iron is a vital constituent of plant and animal life, and appears in hemoglobin. The pure metal is not often encountered in commerce, but is usually alloyed with carbon or other metals. The pure metal is very reactive chemically, and rapidly corrodes, especially in moist air or at elevated temperatures. It has four allotropic forms, or ferrites, known as α, β, γ, and δ, with transition points at 700, 928, and 1530°C. The α form is magnetic, but when transformed into the β form, the magnetism disappears although the lattice remains unchanged. The relations of these forms are peculiar. Pig iron is an alloy

containing about 3% carbon with varying amounts of S, Si, Mn, and P. It is hard, brittle, fairly fusible, and is used to produce other alloys, including steel. Wrought iron contains only a few tenths of a percent of carbon, is tough, malleable, less fusible, and has usually a "fibrous" structure. Carbon steel is an alloy of iron with carbon, with small amounts of Mn, S, P, and Si. Alloy steels are carbon steels with other additives such as nickel, chromium, vanadium, etc. Iron is the cheapest and most abundant, useful, and important of all metals. Natural iron contains four isotopes and isomers. Twenty-six other isotopes and isomers, all radioactive, are now recognized.

Krypton — (Gr. *kryptos*, hidden), Kr; at. wt. 83.80(1); at. no. 36; m.p. –157.36°C; b.p. –153.22 ± 0.10°C; t_c –63.74°C; density 3.733 g/l (0°C); valence usually 0. Discovered in 1898 by Ramsay and Travers in the residue left after liquid air had nearly boiled away. Krypton is present in the air to the extent of about 1 ppm. The atmosphere of Mars has been found to contain 0.3 ppm of krypton. It is one of the "noble" gases. It is characterized by its brilliant green and orange spectral lines. Naturally occurring krypton contains six stable isotopes. Thirty other unstable isotopes and isomers are now recognized. The spectral lines of krypton are easily produced and some are very sharp. In 1960 it was internationally agreed that the fundamental unit of length, the meter, should be defined in terms of the orange-red spectral line of ^{86}Kr. This replaced the standard meter of Paris, which was defined in terms of a bar made of a platinum-iridium alloy. In October 1983 the meter, which originally was defined as being one ten millionth of a quadrant of the earth's polar circumference, was again redefined by the International Bureau of Weights and Measures as being the length of path traveled by light in a vacuum during a time interval of 1/299,792,458 of a second. Solid krypton is a white crystalline substance with a face-centered cubic structure which is common to all the "rare gases". While krypton is generally thought of as a rare gas that normally does not combine with other elements to form compounds, it now appears that the existence of some krypton compounds is established. Krypton difluoride has been prepared in gram quantities and can be made by several methods. A higher fluoride of krypton and a salt of an oxyacid of krypton also have been reported. Molecule-ions of $ArKr^+$ and KrH^+ have been identified and investigated, and evidence is provided for the formation of KrXe or $KrXe^+$. Krypton clathrates have been prepared with hydroquinone and phenol. ^{85}Kr has found recent application in chemical analysis. By imbedding the isotope in various solids, *kryptonates* are formed. The activity of these kryptonates is sensitive to chemical reactions at the surface. Estimates of the concentration of reactants are therefore made possible. Krypton is used in certain photographic flash lamps for high-speed photography. Uses thus far have been limited because of its high cost. Krypton gas presently costs about $690/100 L.

Kurchatovium — See Rutherfordium.

Lanthanum — (Gr. *lanthanein*, to lie hidden), La; at. wt. 138.9055(2); at. no. 57; m.p. 918°C; b.p. 3464°C; sp. gr. 6.145 (25°C); valence 3. Mosander in 1839 extracted a new earth *lanthana*, from impure cerium nitrate, and recognized the new element. Lanthanum is found in rare-earth minerals such as *cerite, monazite, allanite,* and *bastnasite*. Monazite and bastnasite are principal ores in which lanthanum occurs in percentages up to 25 and 38%, respectively. Misch metal, used in making lighter flints, contains about 25% lanthanum. Lanthanum was isolated in relatively pure form in 1923. Ion-exchange and solvent extraction techniques have led to much easier isolation of the so-called "rare-earth" elements. The availability of lanthanum and other rare earths has improved greatly in recent years. The metal can be produced by reducing the anhydrous fluoride with calcium. Lanthanum is silvery white, malleable, ductile, and soft enough to be cut with a knife. It is one of the most reactive of the rare-earth metals. It oxidizes rapidly when exposed to air. Cold water attacks lanthanum slowly, and hot water attacks it much more rapidly. The metal reacts directly with elemental carbon, nitrogen, boron, selenium, silicon, phosphorus, sulfur, and with halogens. At 310°C, lanthanum changes from a hexagonal to a face-centered cubic structure, and at 865°C it again transforms into a body-centered cubic structure. Natural lanthanum is mixture of two isotopes, one of which is stable and one of which is radioactive with a very long half-life. Thirty other radioactive isotopes are recognized. Rare-earth compounds containing lanthanum are extensively used in carbon lighting applications, especially by the motion picture industry for studio lighting and projection. This application consumes about 25% of the rare-earth compounds produced. La_2O_3 improves the alkali resistance of glass, and is used in making special optical glasses. Small amounts of lanthanum, as an additive, can be used to produce nodular cast iron. There is current interest in hydrogen sponge alloys containing lanthanum. These alloys take up to 400 times their own volume of hydrogen gas, and the process is reversible. Heat energy is released every time they do so; therefore these alloys have possibilities in energy conservation systems. Lanthanum and its compounds have a low to moderate acute toxicity rating; therefore, care should be taken in handling them. The metal costs about $2/g (99.9%).

Lawrencium — (Ernest O. Lawrence [1901–1958], inventor of the cyclotron), Lr; at. no. 103; at. mass no. [262]; valence + 3(?). This member of the 5f transition elements (actinide series) was discovered in March 1961 by A. Ghiorso, T. Sikkeland, A. E. Larsh, and R. M. Latimer. A 3-μg californium target, consisting of a mixture of isotopes of mass number 249, 250, 251, and 252, was bombarded with either ^{10}B or ^{11}B. The electrically charged transmutation nuclei recoiled with an atmosphere of helium and were collected on a thin copper conveyor tape which was then moved to place collected atoms in front of a series of solid-state detectors. The isotope of element 103 produced in this way decayed by emitting an 8.6-MeV alpha particle with a half-life of 8 s. In 1967, Flerov and associates of the Dubna Laboratory reported their inability to detect an alpha emitter with a half-life of 8 s which was assigned by the Berkeley group to ^{257}103. This assignment has been changed to ^{258}Lr or ^{259}Lr. In 1965, the Dubna workers found a longer-lived lawrencium isotope, ^{256}Lr, with a half-life of 35 s. In 1968, Ghiorso and associates at Berkeley were able to use a few atoms of this isotope to study the oxidation behavior of lawrencium. Using solvent extraction techniques and working very rapidly, they extracted lawrencium ions from a buffered aqueous solution into an organic solvent, completing each extraction in about 30 s. It was found that lawrencium behaves differently from dipositive nobelium and more like the tripositive elements earlier in the actinide series. Ten isotopes of lawrencium are now recognized.

Lead — (Anglo-Saxon *lead*), Pb (L. *plumbum*); at. wt. 207.2(1); at. no. 82; m.p. 327.46°C; b.p. 1749°C; sp. gr. 11.35 (20°C); valence 2 or 4. Long known, mentioned in Exodus. The alchemists believed lead to be the oldest metal and associated it with the

planet Saturn. Native lead occurs in nature, but it is rare. Lead is obtained chiefly from *galena* (PbS) by a roasting process. *Anglesite* ($PbSO_4$), *cerussite* ($PbCO_3$), and *minim* (Pb_3O_4) are other common lead minerals. Lead is a bluish-white metal of bright luster, is very soft, highly malleable, ductile, and a poor conductor of electricity. It is very resistant to corrosion; lead pipes bearing the insignia of Roman emperors, used as drains from the baths, are still in service. It is used in containers for corrosive liquids (such as sulfuric acid) and may be toughened by the addition of a small percentage of antimony or other metals. Natural lead is a mixture of four stable isotopes: ^{204}Pb (1.4%), ^{206}Pb (24.1%), ^{207}Pb (22.1%), and ^{208}Pb (52.4%). Lead isotopes are the end products of each of the three series of naturally occurring radioactive elements: ^{206}Pb for the uranium series, ^{207}Pb for the actinium series, and ^{208}Pb for the thorium series. Forty-three other isotopes of lead, all of which are radioactive, are recognized. Its alloys include solder, type metal, and various antifriction metals. Great quantities of lead, both as the metal and as the dioxide, are used in storage batteries. Lead is also used for cable covering, plumbing, and ammunition. The metal is very effective as a sound absorber, is used as a radiation shield around X-ray equipment and nuclear reactors, and is used to absorb vibration. Lead, alloyed with tin, is used in making organ pipes. White lead, the basic carbonate, sublimed white lead ($PbSO_4$), chrome yellow ($PbCrO_4$), red lead (Pb_3O_4), and other lead compounds are used extensively in paints, although in recent years the use of lead in paints has been drastically curtailed to eliminate or reduce health hazards. Lead oxide is used in producing fine "crystal glass" and "flint glass" of a high index of refraction for achromatic lenses. The nitrate and the acetate are soluble salts. Lead salts such as lead arsenate have been used as insecticides, but their use in recent years has been practically eliminated in favor of less harmful organic compounds. Care must be used in handling lead as it is a cumulative poison. Environmental concern with lead poisoning has resulted in a national program to eliminate the lead tetraethyl in gasoline. The U.S. Occupational Safety and Health Administration (OSHA) has recommended that industries limit airborne lead to 50 μgms/cu. meter. Lead is priced at about 90¢/kg (99.9%).

Lithium — (Gr. *lithos*, stone), Li; at. wt. 6.941(2); at. no. 3; m.p. 180.5°C; b.p. 1342°C; sp. gr. 0.534 (20°C); valence 1. Discovered by Arfvedson in 1817. Lithium is the lightest of all metals, with a density only about half that of water. It does not occur free in nature; combined it is found in small amounts in nearly all igneous rocks and in the waters of many mineral springs. *Lepidolite, spodumene, petalite,* and *amblygonite* are the more important minerals containing it. Lithium is presently being recovered from brines of Searles Lake, in California, and from Nevada, Chile, and Argentina. Large deposits of spodumene are found in North Carolina. The metal is produced electrolytically from the fused chloride. Lithium is silvery in appearance, much like Na and K, other members of the alkali metal series. It reacts with water, but not as vigorously as sodium. Lithium imparts a beautiful crimson color to a flame, but when the metal burns strongly the flame is a dazzling white. Since World War II, the production of lithium metal and its compounds has increased greatly. Because the metal has the highest specific heat of any solid element, it has found use in heat transfer applications; however, it is corrosive and requires special handling. The metal has been used as an alloying agent, is of interest in synthesis of organic compounds, and has nuclear applications. It ranks as a leading contender as a battery anode material as it has a high electrochemical potential. Lithium is used in special glasses and ceramics. The glass for the 200-inch telescope at Mt. Palomar contains lithium as a minor ingredient. Lithium chloride is one of the most hygroscopic materials known, and it, as well as lithium bromide, is used in air conditioning and industrial drying systems. Lithium stearate is used as an all-purpose and high-temperature lubricant. Other lithium compounds are used in dry cells and storage batteries. Seven isotopes of lithium are recognized. Natural lithium contains two isotopes. The metal is priced at about $1.50/g (99.9%).

Lutetium — (Lutetia, ancient name for Paris, sometimes called *cassiopeium* by the Germans), Lu; at. wt. 174.967(1); at. no. 71; m.p. 1663°C; b.p. 3402°C; sp. gr. 9.841 (25°C); valence 3. In 1907, Urbain described a process by which Marignac's ytterbium (1879) could be separated into the two elements, ytterbium (neoytterbium)and lutetium. These elements were identical with "aldebaranium" and "cassiopeium," independently discovered by von Welsbach about the same time. Charles James of the University of New Hampshire also independently prepared the very pure oxide, *lutecia*, at this time. The spelling of the element was changed from *lutecium* to *lutetium* in 1949. Lutetium occurs in very small amounts in nearly all minerals containing yttrium, and is present in *monazite* to the extent of about 0.003%, which is a commercial source. The pure metal has been isolated only in recent years and is one of the most difficult to prepare. It can be prepared by the reduction of anhydrous $LuCl_3$ or LuF_3 by an alkali or alkaline earth metal. The metal is silvery white and relatively stable in air. While new techniques, including ion-exchange reactions, have been developed to separate the various rare-earth elements, lutetium is still the most costly of all rare earths. It is priced at about $100/g (99.9%). ^{176}Lu occurs naturally (97.41%) with ^{175}Lu (2.59%), which is radioactive with a very long half-life. It is radioactive with a half-life of about 4×10^{10} years. Lutetium has 50 isotopes and isomers that are now recognized. Stable lutetium nuclides, which emit pure beta radiation after thermal neutron activation, can be used as catalysts in cracking, alkylation, hydrogenation, and polymerization. Virtually no other commercial uses have been found yet for lutetium. While lutetium, like other rare-earth metals, is thought to have a low toxicity rating, it should be handled with care until more information is available.

Magnesium — (*Magnesia,* district in Thessaly) Mg; at. wt. 24.3050(6); at. no. 12; m.p. 650°C; b.p. 1090°C; sp. gr. 1.738 (20°C); valence 2. Compounds of magnesium have long been known. Black recognized magnesium as an element in 1755. It was isolated by Davy in 1808, and prepared in coherent form by Bussy in 1831. Magnesium is the eighth most abundant element in the earth's crust. It does not occur uncombined, but is found in large deposits in the form of *magnesite, dolomite,* and other minerals. The metal is now principally obtained in the U.S. by electrolysis of fused magnesium chloride derived from brines, wells, and sea water. Magnesium is a light, silvery-white, and fairly tough metal. It tarnishes slightly in air, and finely divided magnesium readily ignites upon heating in air and burns with a dazzling white flame. It is used in flashlight photography, flares, and pyrotechnics, including incendiary bombs. It is one third lighter than aluminium, and in alloys is essential for airplane and missile contruction. The metal improves the mechanical, fabrication, and welding characteristics of aluminum when used as an alloying agent.

Magnesium is used in producing nodular graphite in cast iron,and is used as an additive to conventional propellants. It is also used as a reducing agent in the production of pure uranium and other metals from their salts. The hydroxide (*milk of magnesia*), chloride, sulfate (*Epsom salts*), and citrate are used in medicine. Dead-burned magnesite is employed for refractory purposes such as brick and liners in furnaces and converters. Calcined magnesia is also used for water treatment and in the manufacture of rubber, paper, etc. Organic magnesium compounds (Grignard's reagents) are important. Magnesium is an important element in both plant and animal life. Chlorophylls are magnesium-centered porphyrins. The adult daily requirement of magnesium is about 300 mg/day, but this is affected by various factors. Great care should be taken in handling magnesium metal, especially in the finely divided state, as serious fires can occur. Water should not be used on burning magnesium or on magnesium fires. Natural magnesium contains three isotopes. Twelve other isotopes are recognized. Magnesium metal costs about $100/kg (99.8%).

Manganese — (L. *magnes*, magnet, from magnetic properties of pyrolusite; It. *manganese*, corrupt form of *magnesia*), Mn; at. wt. 54.938049(9); at. no. 25; m.p. 1246°C; b.p. 2061°C; sp. gr. 7.21 to 7.44, depending on allotropic form; valence 1, 2, 3, 4, 6, or 7. Recognized by Scheele, Bergman, and others as an element and isolated by Gahn in 1774 by reduction of the dioxide with carbon. Manganese minerals are widely distributed; oxides, silicates, and carbonates are the most common. The discovery of large quantities of manganese nodules on the floor of the oceans holds promise as a source of manganese. These nodules contain about 24% manganese together with many other elements in lesser abundance. Most manganese today is obtained from ores found in the Ukraine, Brazil, Australia, Republic of So. Africa, Gabon, China, and India. *Pyrolusite* (MnO_2) and *rhodochrosite* ($MnCO_3$) are among the most common manganese minerals. The metal is obtained by reduction of the oxide with sodium, magnesium, aluminum, or by electrolysis. It is gray-white, resembling iron, but is harder and very brittle. The metal is reactive chemically, and decomposes cold water slowly. Manganese is used to form many important alloys. In steel, manganese improves the rolling and forging qualities, strength, toughness, stiffness, wear resistance, hardness, and hardenability. With aluminum and antimony, especially with small amounts of copper, it forms highly ferromagnetic alloys. Manganese metal is ferromagnetic only after special treatment. The pure metal exists in four allotropic forms. The alpha form is stable at ordinary temperature; gamma manganese, which changes to alpha at ordinary temperatures, is said to be flexible, soft, easily cut, and capable of being bent. The dioxide (pyrolusite) is used as a depolarizer in dry cells, and is used to "decolorize" glass that is colored green by impurities of iron. Manganese by itself colors glass an amethyst color, and is responsible for the color of true amethyst. The dioxide is also used in the preparation of oxygen and chlorine, and in drying black paints. The permanganate is a powerful oxidizing agent and is used in quantitative analysis and in medicine. Manganese is widely distributed throughout the animal kingdom. It is an important trace element and may be essential for utilization of vitamin B_1. Twenty-seven isotopes and isomers are known. Manganese metal (99.95%) is priced at about $800/kg. Metal of 99.6% purity is priced at about $80/kg.

Meitnerium — (Lise Meitner [1878–1968], Austrian–Swedish physicist and mathematician), Mt; at. wt [266]; at. no. 109. On August 29, 1992, Element 109 was made and identified by physicists at the Heavy Ion Research Laboratory (G.S.I.), Darmstadt, Germany, by bombarding a target of ^{209}Bi with accelerated nuclei of ^{58}Fe. The production of Element 109 has been extremely small. It took a week of target bombardment (10^{11} nuclear encounters) to produce a single atom of 109. Oganessian and his team at Dubna in 1994 repeated the Darmstadt experiment using a tenfold irradiation dose. One fission event from seven alpha decays of 109 was observed, thus indirectly confirming the existence of isotope $^{266}109$. In August 1997, the IUPAC adopted the name *meitnerium* for this element, honoring L. Meitner. Four isotopes of *meitnerium* are now recognized.

Mendelevium — (Dmitri Mendeleev [1834–1907]), Md; at. wt. (258); at. no. 101; m.p. 827°C; valence +2, +3. Mendelevium, the ninth transuranium element of the actinide series to be discovered, was first identified by Ghiorso, Harvey, Choppin, Thompson, and Seaborg early in 1955 as a result of the bombardment of the isotope ^{253}Es with helium ions in the Berkeley 60-inch cyclotron. The isotope produced was ^{256}Md, which has a half-life of 78 min. This first identification was notable in that ^{256}Md was synthesized on a one-atom-at-a-time basis. Nineteen isotopes and isomers are now recognized. ^{258}Md has a half-life of 51.5 days. This isotope has been produced by the bombardment of an isotope of einsteinium with ions of helium. It now appears possible that eventually enough ^{258}Md can be made so that some of its physical properties can be determined. ^{256}Md has been used to elucidate some of the chemical properties of mendelevium in aqueous solution. Experiments seem to show that the element possesses a moderately stable dipositive (II) oxidation state in addition to the tripositive (III) oxidation state,which is characteristic of actinide elements.

Mercury — (Planet *Mercury*), Hg (*hydrargyrum*, liquid silver); at. wt. 200.59(2); at. no. 80; t.p. –38.83°C; b.p. 356.73°C; t_c 1447°C; sp. gr. 13.546 (20°C); valence 1 or 2. Known to ancient Chinese and Hindus; found in Egyptian tombs of 1500 B.C. Mercury is the only common metal liquid at ordinary temperatures. It only rarely occurs free in nature. The chief ore is *cinnabar* (HgS). Spain and China produce about 75% of the world's supply of the metal. The commercial unit for handling mercury is the "flask," which weighs 76 lb (34.46 kg). The metal is obtained by heating cinnabar in a current of air and by condensing the vapor. It is a heavy, silvery-white metal; a rather poor conductor of heat, as compared with other metals, and a fair conductor of electricity. It easily forms alloys with many metals, such as gold, silver, and tin, which are called *amalgams*. Its ease in amalgamating with gold is made use of in the recovery of gold from its ores. The metal is widely used in laboratory work for making thermometers, barometers, diffusion pumps, and many other instruments. It is used in making mercury-vapor lamps and advertising signs, etc. and is used in mercury switches and other electrical apparatus. Other uses are in making pesticides, mercury cells for caustic soda and chlorine production, dental preparations, antifouling paint, batteries, and catalysts. The most important salts are mercuric chloride $HgCl_2$ (corrosive sublimate — a violent poison), mercurous chloride Hg_2Cl_2(calomel, occasionally still used in medicine), mercury fulminate ($Hg(ONC)_2$), a detonator widely used in explosives, and mercuric sulfide (HgS, vermillion, a high-grade paint pigment). Organic mercury compounds are important. It has been found that an electrical discharge causes mercury vapor to combine with neon, argon, krypton, and xenon. These products, held together with van der Waals' forces,

correspond to HgNe, HgAr, HgKr, and HgXe. Mercury is a virulent poison and is readily absorbed through the respiratory tract, the gastrointestinal tract, or through unbroken skin. It acts as a cumulative poison and dangerous levels are readily attained in air. Air saturated with mercury vapor at 20°C contains a concentration that exceeds the toxic limit many times. The danger increases at higher temperatures. *It is therefore important that mercury be handled with care.* Containers of mercury should be securely covered and spillage should be avoided. If it is necessary to heat mercury or mercury compounds, it should be done in a well-ventilated hood. Methyl mercury is a dangerous pollutant and is now widely found in water and streams. The triple point of mercury, –38.8344°C, is a fixed point on the International Temperature Scale (ITS-90). Mercury (99.98%) is priced at about $110/kg. Native mercury contains seven isotopes. Thirty-six other isotopes and isomers are known.

Molybdenum — (Gr. *molybdos*, lead), Mo; at. wt. 95.94(1); at. no. 42; m.p. 2623°C; b.p. 4639°C; sp. gr. 10.22 (20°C); valence 2, 3, 4?, 5?, or 6. Before Scheele recognized molybdenite as a distinct ore of a new element in 1778, it was confused with graphite and lead ore. The metal was prepared in an impure form in 1782 by Hjelm. Molybdenum does not occur native, but is obtained principally from *molybdenite* (MoS_2). *Wulfenite* ($PbMoO_4$) and *powellite* ($Ca(MoW)O_4$) are also minor commercial ores. Molybdenum is also recovered as a by-product of copper and tungsten mining operations. The U.S., Canada, Chile, and China produce most of the world's molybdenum ores. The metal is prepared from the powder made by the hydrogen reduction of purified molybdic trioxide or ammonium molybdate. The metal is silvery white, very hard, but is softer and more ductile than tungsten. It has a high elastic modulus, and only tungsten and tantalum, of the more readily available metals, have higher melting points. It is a valuable alloying agent, as it contributes to the hardenability and toughness of quenched and tempered steels. It also improves the strength of steel at high temperatures. It is used in certain nickel-based alloys, such as the "Hastelloys®" which are heat-resistant and corrosion-resistant to chemical solutions. Molybdenum oxidizes at elevated temperatures. The metal has found recent application as electrodes for electrically heated glass furnaces and forehearths. The metal is also used in nuclear energy applications and for missile and aircraft parts. Molybdenum is valuable as a catalyst in the refining of petroleum. It has found application as a filament material in electronic and electrical applications. Molybdenum is an essential trace element in plant nutrition. Some lands are barren for lack of this element in the soil. Molybdenum sulfide is useful as a lubricant, especially at high temperatures where oils would decompose. Almost all ultra-high strength steels with minimum yield points up to 300,000 psi(lb/in.^{2}) contain molybdenum in amounts from 0.25 to 8%. Natural molybdenum contains seven isotopes. Thirty other isotopes and isomers are known, all of which are radioactive. Molybdenum metal costs about $1/g (99.999% purity). Molybdenum metal (99.9%) costs about $160/kg.

Neodymium — (Gr. *neos*, new, and *didymos*, twin), Nd; at. wt. 144.24(3); at. no. 60; m.p. 1021°C; b.p. 3074°C; sp. gr. 7.008 (25°C); valence 3. In 1841, Mosander, extracted from *cerite* a new rose-colored oxide, which he believed contained a new element. He named the element *didymium*, as it was *an inseparable twin brother of lanthanum*. In 1885 von Welsbach separated didymium into two new elemental components, *neodymia* and *praseodymia*, by repeated fractionation of ammonium didymium nitrate. While the free metal is in *misch metal*, long known and used as a pyrophoric alloy for light flints, the element was not isolated in relatively pure form until 1925. Neodymium is present in misch metal to the extent of about 18%. It is present in the minerals *monazite* and *bastnasite*, which are principal sources of rare-earth metals. The element may be obtained by separating neodymium salts from other rare earths by ion-exchange or solvent extraction techniques, and by reducing anhydrous halides such as NdF_3 with calcium metal. Other separation techniques are possible. The metal has a bright silvery metallic luster. Neodymium is one of the more reactive rare-earth metals and quickly tarnishes in air, forming an oxide that spalls off and exposes metal to oxidation. The metal, therefore, should be kept under light mineral oil or sealed in a plastic material. Neodymium exists in two allotropic forms, with a transformation from a double hexagonal to a body-centered cubic structure taking place at 863°C. Natural neodymium is a mixture of seven isotopes, one of which has a very long half-life. Twenty seven other radioactive isotopes and isomers are recognized. Didymium, of which neodymium is a component, is used for coloring glass to make welder's goggles. By itself, neodymium colors glass delicate shades ranging from pure violet through wine-red and warm gray. Light transmitted through such glass shows unusually sharp absorption bands. The glass has been used in astronomical work to produce sharp bands by which spectral lines may be calibrated. Glass containing neodymium can be used as a laser material to produce coherent light. Neodymium salts are also used as a colorant for enamels. The element is also being used with iron and boron to produce extremely strong magnets having energy densities as high as 27 to 35 million gauss oersteds. These are the most compact magnets commercially available. The price of the metal is about $4/g. Neodymium has a low-to-moderate acute toxic rating. As with other rare earths, neodymium should be handled with care.

Neon — (Gr. *neos*, new), Ne; at. wt. 20.1797(6); at. no. 10; t.p. –248.59°C; b.p. –246.08°C; t_c –228.7°C (1 atm); density of gas 0.89990 g/l (1 atm, 0°C); density of liquid at b.p. 1.207 g/cm^3; valence 0. Discovered by Ramsay and Travers in 1898. Neon is a rare gaseous element present in the atmosphere to the extent of 1 part in 65,000 of air. It is obtained by liquefaction of air and separated from the other gases by fractional distillation. Natural neon is a mixture of three isotopes. Fourteen other unstable isotopes are known. It is very inert element; however, it is said to form a compound with fluorine. It is still questionable if true compounds of neon exist, but evidence is mounting in favor of their existence. The following ions are known from optical and mass spectrometric studies: Ne^+, $(NeAr)^+$, $(NeH)^+$, and $(HeNe^+)$. Neon also forms an unstable hydrate. In a vacuum discharge tube, neon glows reddish orange. Of all the rare gases, the discharge of neon is the most intense at ordinary voltages and currents. Neon is used in making the common neon advertising signs, which accounts for its largest use. It is also used to make high-voltage indicators, lightning arrestors, wave meter tubes, and TV tubes. Neon and helium are used in making gas lasers. Liquid neon is now commercially available and is finding important application as an economical cryogenic refrigerant. It has over 40 times more refrigerating capacity per unit volume than liquid helium and more than three times that of liquid hydrogen. It is compact, inert, and is less expensive than helium when it

meets refrigeration requirements. Neon costs about $800/80 cu. ft. (2265 l).

Neptunium — (Planet *Neptune*), Np; at. wt. (237); at. no. 93; m.p. 644°C; sp. gr. 20.25 (20°C); valence 3, 4, 5, and 6. Neptunium was the first synthetic transuranium element of the actinide series discovered; the isotope ^{239}Np was produced by McMillan and Abelson in 1940 at Berkeley, California, as the result of bombarding uranium with cyclotron-produced neutrons. The isotope ^{237}Np (half-life of 2.14×10^6 years) is currently obtained in gram quantities as a by-product from nuclear reactors in the production of plutonium. Twenty-three isotopes and isomers of neptunium are now recognized. Trace quantities of the element are actually found in nature due to transmutation reactions in uranium ores produced by the neutrons which are present. Neptunium is prepared by the reduction of NpF_3 with barium or lithium vapor at about 1200°C. Neptunium metal has a silvery appearance, is chemically reactive, and exists in at least three structural modifications: α-neptunium, orthorhombic, density 20.25 g/cm^3, β-neptunium (above 280°C), tetragonal, density (313°C) 19.36 g/cm^3; γ-neptunium (above 577°C), cubic, density (600°C) 18.0 g/cm^3. Neptunium has four ionic oxidation states in solution: Np^{+3} (pale purple), analogous to the rare earth ion Pm^{+3}, Np^{+4} (yellow green); NpO^{+} (green blue); and NpO^{++} (pale pink). These latter oxygenated species are in contrast to the rare earths which exhibit only simple ions of the (II), (III), and (IV) oxidation states in aqueous solution. The element forms tri- and tetrahalides such as NpF_3, NpF_4, $NpCl_4$, $NpBr_3$, NpI_3, and oxides of various compositions such as are found in the uranium-oxygen system, including Np_3O_8 and NpO_2.

Nickel — (Ger. *Nickel,* Satan or Old Nick's and from *kupfernickel*, Old Nick's copper), Ni; at. wt. 58.6934(2); at. no. 28; m.p. 1455°C; b.p. 2913°C; sp. gr. 8.902 (25°C); valence 0, 1, 2, 3. Discovered by Cronstedt in 1751 in kupfernickel (*niccolite*). Nickel is found as a constituent in most meteorites and often serves as one of the criteria for distinguishing a meteorite from other minerals. Iron meteorites, or *siderites*, may contain iron alloyed with from 5 to nearly 20% nickel. Nickel is obtained commercially from *pentlandite* and *pyrrhotite* of the Sudbury region of Ontario, a district that produces much of the world's nickel. It is now thought that the Sudbury deposit is the result of an ancient meteorite impact. Large deposits of nickel, cobalt, and copper have recently been developed at Voisey's Bay, Laborador. Other deposits of nickel are found in Russia, New Caledonia, Australia, Cuba, Indonesia, and elsewhere. Nickel is silvery white and takes on a high polish. It is hard, malleable, ductile, somewhat ferromagnetic, and a fair conductor of heat and electricity. It belongs to the iron-cobalt group of metals and is chiefly valuable for the alloys it forms. It is extensively used for making stainless steel and other corrosion-resistant alloys such as Invar®, Monel®, Inconel®, and the Hastelloys®. Tubing made of a copper-nickel alloy is extensively used in making desalination plants for converting sea water into fresh water. Nickel is also now used extensively in coinage and in making nickel steel for armor plate and burglar-proof vaults, and is a component in Nichrome®, Permalloy®, and constantan. Nickel added to glass gives a green color. Nickel plating is often used to provide a protective coating for other metals, and finely divided nickel is a catalyst for hydrogenating vegetable oils. It is also used in ceramics, in the manufacture of Alnico magnets, and in the Edison® storage battery. The sulfate and the oxides are important compounds. Natural nickel is a mixture of five stable isotopes; twenty-five other unstable isotopes are known. Nickel sulfide fume and dust is recognized as having carcinogenic potential. Nickel metal (99.9%) is priced at about $2/g or less in larger quantities.

Nielsbohrium — See Bohrium.

Niobium — (*Niobe*, daughter of Tantalus), Nb; or Columbium (*Columbia*, name for America); at. wt. 92.90638(2); at. no. 41; m.p. 2477°C; b.p. 4744°C, sp. gr. 8.57 (20°C); valence 2, 3, 4?, 5. Discovered in 1801 by Hatchett in an ore sent to England more that a century before by John Winthrop the Younger, first governor of Connecticut. The metal was first prepared in 1864 by Blomstrand, who reduced the chloride by heating it in a hydrogen atmosphere. The name *niobium* was adopted by the International Union of Pure and Applied Chemistry in 1950 after 100 years of controversy. Many leading chemical societies and government organizations refer to it by this name. Most metallurgists, leading metal societies, and all but one of the leading U.S. commercial producers, however, still refer to the metal as "columbium". The element is found in *niobite*(or *columbite), niobite-tantalite, pyrochlore,* and *euxenite*. Large deposits of niobium have been found associated with *carbonatites* (carbon-silicate rocks), as a constituent of *pyrochlore*. Extensive ore reserves are found in Canada, Brazil, Congo-Kinshasa, Rwanda, and Australia. The metal can be isolated from tantalum, and prepared in several ways. It is a shiny, white, soft, and ductile metal, and takes on a bluish cast when exposed to air at room temperatures for a long time. The metal starts to oxidize in air at 200°C, and when processed at even moderate temperatures must be placed in a protective atmosphere. It is used in arc-welding rods for stabilized grades of stainless steel. Thousands of pounds of niobium have been used in advance air frame systems such as were used in the Gemini space program. It has also found use in super-alloys for applications such as jet engine components, rocket subassemblies, and heat-resisting equipment. The element has superconductive properties; superconductive magnets have been made with Nb-Zr wire, which retains its superconductivity in strong magnetic fields. This type of application offers hope of direct large-scale generation of electric power. Natural niobium is composed of only one isotope, ^{93}Nb. Forty-seven other isotopes and isomers of niobium are now recognized. Niobium metal (99.9% pure) is priced at about 50¢/g.

Nitrogen — (L. *nitrum*, Gr. *nitron*, native soda; genes, *forming,* N; at. wt. 14.00674(7); at. no. 7; m.p. –210.00°C; b.p. –198.79°C; t_c –146.94°C; density 1.2506 g/l; sp. gr. liquid 0.808 (–195.8°C), solid 1.026 (–252°C); valence 3 or 5. Discovered by Daniel Rutherford in 1772, but Scheele, Cavendish, Priestley, and others about the same time studied "burnt or dephlogisticated air," as air without oxygen was then called. Nitrogen makes up 78% of the air, by volume. The atmosphere of Mars, by comparison, is 2.6% nitrogen. The estimated amount of this element in our atmosphere is more than 4000 trillion tons. From this inexhaustible source it can be obtained by liquefaction and fractional distillation. Nitrogen molecules give the orange-red, blue-green, blue-violet, and deep violet shades to the aurora. The element is so inert that Lavoisier named it *azote*, meaning without life, yet its compounds are so active as to be most important in foods, poisons, fertilizers, and explosives. Nitrogen can be also easily prepared by heating a water solution of ammonium nitrite. Nitrogen, as a gas, is colorless, odorless, and a generally inert element. As a liquid it is also colorless and odorless, and is similar in appearance to water. Two allotropic

forms of solid nitrogen exist, with the transition from the α to the β form taking place at –237°C. When nitrogen is heated, it combines directly with magnesium, lithium, or calcium; when mixed with oxygen and subjected to electric sparks, it forms first nitric oxide (NO) and then the dioxide (NO_2); when heated under pressure with a catalyst with hydrogen, ammonia is formed (Haber process). The ammonia thus formed is of the utmost importance as it is used in fertilizers, and it can be oxidized to nitric acid (Ostwald process). The ammonia industryis the largest consumer of nitrogen. Large amounts of gas are also used by the electronics industry, which uses the gas as a blanketing medium during production of such components as transistors, diodes, etc. Large quantities of nitrogen are used in annealing stainless steel and other steel mill products. The drug industry also uses large quantities. Nitrogen is used as a refrigerant both for the immersion freezing of food products and for transportation of foods. Liquid nitrogen is also used in missile work as a purge for components, insulators for space chambers, etc., and by the oil industry to build up great pressures in wells to force crude oil upward. Sodium and potassium nitrates are formed by the decomposition of organic matter with compounds of the metals present. In certain dry areas of the world these saltpeters are found in quantity. Ammonia, nitric acid, the nitrates, the five oxides (N_2O, NO, N_2O_3, NO_2, and N_2O_5), TNT, the cyanides, etc. are but a few of the important compounds. Nitrogen gas prices vary from 2¢ to $2.75 per 100 ft^3 (2.83 cu. meters), depending on purity, etc. Production of elemental nitrogen in the U.S. is more than 9 million short tons per year. Natural nitrogen contains two isotopes, ^{14}N and ^{15}N. Ten other isotopes are known.

Nobelium — (Alfred Nobel [1833–1896], inventor of dynamite), No; at. wt. [259]; at. no. 102; valence +2, +3. Nobelium was unambiguously discovered and identified in April 1958 at Berkeley by A. Ghiorso, T. Sikkeland, J. R. Walton, and G. T. Seaborg, who used a new double-recoil technique. A heavy-ion linear accelerator (HILAC) was used to bombard a thin target of curium (95% ^{244}Cm and 4.5% ^{246}Cm) with ^{12}C ions to produce 102^{254} according to the ^{246}Cm (^{12}C, 4*n*) reaction. Earlier in 1957 workers of the U.S., Britain, and Sweden announced the discovery of an isotope of Element 102 with a 10-min half-life at 8.5 MeV, as a result of bombarding ^{244}Cm with ^{13}C nuclei. On the basis of this experiment the name *nobelium* was assigned and accepted by the Commission on Atomic Weights of the International Union of Pure and Applied Chemistry. The acceptance of the name was premature, for both Russian and American efforts now completely rule out the possibility of any isotope of Element 102 having a half-life of 10 min in the vicinity of 8.5 MeV. Early work in 1957 on the search for this element, in Russia at the Kurchatov Institute, was marred by the assignment of 8.9 ± 0.4 MeV alpha radiation with a half-life of 2 to 40 sec, which was too indefinite to support claim to discovery. Confirmatory experiments at Berkeley in 1966 have shown the existence of $^{254}102$ with a 55-s half-life, $^{252}102$ with a 2.3-s half-life, and $^{257}102$ with a 25-s half-life. Twelve isotopes are now recognized, one of which — $^{255}102$ — has a half-life of 3.1 min. In view of the discover's traditional right to name an element, the Berkeley group, in 1967, suggested that the hastily given name *nobelium,* along with the symbol No, be retained.

Osmium — (Gr. *osme*, a smell), Os; at. wt. 190.23(3); at. no. 76; m.p. 3033°C; b.p. 5012°C; sp. gr. 22.57; valence 0 to +8, more usually +3, +4, +6, and +8. Discovered in 1803 by Tennant in the residue left when crude platinum is dissolved by *aqua regia.* Osmium occurs in *iridosmine* and in platinum-bearing river sands of the Urals, North America, and South America. It is also found in the nickel-bearing ores of Sudbury, Ontario, region along with other platinum metals. While the quantity of platinum metals in these ores is very small, the large tonnages of nickel ores processed make commercial recovery possible. The metal is lustrous, bluish white, extremely hard, and brittle even at high temperatures. It has the highest melting point and the lowest vapor pressure of the platinum group. The metal is very difficult to fabricate, but the powder can be sintered in a hydrogen atmosphere at a temperature of 2000°C. The solid metal is not affected by air at room temperature, but the powdered or spongy metal slowly gives off osmium tetroxide, which is a powerful oxidizing agent and has a strong smell. The tetroxide is highly toxic, and boils at 130°C (760 mm). Concentrations in air as low as 10^{-7} g/m^3 can cause lung congestion, skin damage, or eye damage. The tetroxide has been used to detect fingerprints and to stain fatty tissue for microscope slides. The metal is almost entirely used to produce very hard alloys, with other metals of the platinum group, for fountain pen tips, instrument pivots, phonograph needles, and electrical contacts. The price of 99.9% pure osmium powder — the form usually supplied commercially — is about $100/g, depending on quantity and supplier. Natural osmium contains seven isotopes, one of which, ^{186}Os, is radioactive with a very long half-life. Thirty four other isotopes and isomers are known, all of which are radioactive.The measured densities of iridium and osmium seem to indicate that osmium is slightly more dense than iridium, so osmium has generally been credited with being the heaviest known element. Calculations of the density from the space lattice, which may be more reliable for these elements than actual measurements, however, give a density of 22.65 for iridium compared to 22.61 for osmium. At present, therefore, we know either iridium or osmium is the heaviest element, but the data do not allow selection between the two.

Oxygen — (Gr. *oxys*, sharp, acid, and *genes*, forming; acid former), O; at. wt. 15.9994(3); at. no. 8; t.p. –218.79°C; t_c –118.56°C; valence 2. For many centuries, workers occasionally realized air was composed of more than one component. The behavior of oxygen and nitrogen as components of air led to the advancement of the phlogiston theory of combustion, which captured the minds of chemists for a century. Oxygen was prepared by several workers, including Bayen and Borch, but they did not know how to collect it, did not study its properties, and did not recognize it as an elementary substance. Priestley is generally credited with its discovery, although Scheele also discovered it independently. Oxygen is the third most abundant element found in the sun, and it plays a part in the carbon-nitrogen cycle, one process thought to give the sun and stars their energy. Oxygen under excited conditions is responsible for the bright red and yellow-green colors of the aurora. Oxygen, as a gaseous element, forms 21% of the atmosphere by volume from which it can be obtained by liquefaction and fractional distillation. The atmosphere of Mars contains about 0.15% oxygen. The element and its compounds make up 49.2%, by weight, of the earth's crust. About two thirds of the human body and nine tenths of water is oxygen. In the laboratory it can be prepared by the electrolysis of water or by heating potassium chlorate with manganese dioxide as a catalyst. The gas is colorless, odorless, and tasteless. The liquid and solid forms are a pale blue color and are strongly paramagnetic. Ozone

(O_3), a highly active compound, is formed by the action of an electrical discharge or ultraviolet light on oxygen. Ozone's presence in the atmosphere (amounting to the equivalent of a layer 3 mm thick at ordinary pressures and temperatures) is of vital importance in preventing harmful ultraviolet rays of the sun from reaching the earth's surface. There has been recent concern that pollutants in the atmosphere may have a detrimental effect on this ozone layer. Ozone is toxic and exposure should not exceed 0.2 mg/m^3 (8-hour time-weighted average — 40-hour work week). Undiluted ozone has a bluish color. Liquid ozone is bluish black, and solid ozone is violet-black. Oxygen is very reactive and capable of combining with most elements. It is a component of hundreds of thousands of organic compounds. It is essential for respiration of all plants and animals and for practically all combustion. In hospitals it is frequently used to aid respiration of patients. Its atomic weight was used as a standard of comparison for each of the other elements until 1961 when the International Union of Pure and Applied Chemistry adopted carbon 12 as the new basis. Oxygen has thirteen recognized isotopes. Natural oxygen is a mixture of three isotopes. Oxygen 18 occurs naturally, is stable, and is available commercially. Water (H_2O with 1.5% ^{18}O) is also available. Commercial oxygen consumption in the U.S. is estimated to be 20 million short tons per year and the demand is expected to increase substantially in the next few years. Oxygen enrichment of steel blast furnaces accounts for the greatest use of the gas. Large quantities are also used in making synthesis gas for ammonia and methanol, ethylene oxide, and for oxy-acetylene welding. Air separation plants produce about 99% of the gas, electrolysis plants about 1%. The gas costs 5¢/ft^3 ($1.75/cu. meter) in small quantities.

Palladium — (named after the asteroid *Pallas*, discovered about the same time; Gr. *Pallas*, goddess of wisdom), Pd; at. wt. 106.42(1) at. no. 46; m.p. 1554.9°C; b.p. 2963°C; sp. gr. 12.02 (20°C); valence 2, 3, or 4. Discovered in 1803 by Wollaston. Palladium is found along with platinum and other metals of the platinum group in deposits of Russia, South Africa, Canada (Ontario), and elsewhere. Natural palladium contains six stable isotopes. Twenty-nine other isotopes are recognized, all of which are radioactive. It is frequently found associated with the nickel-copper deposits such as those found in Ontario. Its separation from the platinum metals depends upon the type of ore in which it is found. It is a steel-white metal, does not tarnish in air, and is the least dense and lowest melting of the platinum group of metals. When annealed, it is soft and ductile; cold working greatly increases its strength and hardness. Palladium is attacked by nitric and sulfuric acid. At room temperatures the metal has the unusual property of absorbing up to 900 times its own volume of hydrogen, possibly forming Pd_2H. It is not yet clear if this a true compound. Hydrogen readily diffuses through heated palladium and this provides a means of purifying the gas. Finely divided palladium is a good catalyst and is used for hydrogenation and dehydrogenation reactions. It is alloyed and used in jewelry trades. White gold is an alloy of gold decolorized by the addition of palladium. Like gold, palladium can be beaten into leaf as thin as 1/250,000 in. The metal is used in dentistry, watchmaking, and in making surgical instruments and electrical contacts. Palladium recently has been substituted for higher priced platinum in catalytic converters by some automobile companies. This has caused a large increase in the cost of palladium. The price of the two metals are now, in 2002, about the same. Palladium, however, is less resistant to poisoning by sulfur and lead, than platinum, but it may prove useful in controlling emissions from diesel vehicles. The metal sells for about $350/tr. oz. ($11/g).

Phosphorus — (Gr. *phosphoros*, light bearing; ancient name for the planet Venus when appearing before sunrise), P; at. wt. 30.973762(4); at. no. 15; m.p. (white) 44.15°C; b.p. 280.5°C; sp. gr. (white) 1.82, (red) 2.20, (black) 2.25 to 2.69; valence 3 or 5. Discovered in 1669 by Brand, who prepared it from urine. Phosphorus exists in four or more allotropic forms: white (or yellow), red, and black (or violet). White phosphorus has two modifications: α and β with a transition temperature at −3.8°C. Never found free in nature, it is widely distributed in combination with minerals. Twenty-one isotopes of phosphorus are recognized. *Phosphate* rock, which contains the mineral *apatite*, an impure tri-calcium phosphate, is an important source of the element. Large deposits are found in the Russia,China, Morocco, and in Florida, Tennessee, Utah, Idaho, and elsewhere. Phosphorus in an essential ingredient of all cell protoplasm, nervous tissue, and bones. Ordinary phosphorus is a waxy white solid; when pure it is colorless and transparent. It is insoluble in water, but soluble in carbon disulfide. It takes fire spontaneously in air, burning to the pentoxide. It is very poisonous, 50 mg constituting an approximate fatal dose. Exposure to white phosphorus should not exceed 0.1 mg/m^3 (8-hour time-weighted average — 40-hour work week). White phosphorus should be kept under water, as it is dangerously reactive in air, and it should be handled with forceps, as contact with the skin may cause severe burns. When exposed to sunlight or when heated in its own vapor to 250°C, it is converted to the red variety, which does not phosphoresce in air as does the white variety. This form does not ignite spontaneously and it is not as dangerous as white phosphorus. It should, however, be handled with care as it does convert to the white form at some temperatures and it emits highly toxic fumes of the oxides of phosphorus when heated. The red modification is fairly stable, sublimes with a vapor pressure of 1 atm at 417°C,and is used in the manufacture of safety matches, pyrotechnics, pesticides, incendiary shells, smoke bombs, tracer bullets, etc. White phosphorus may be made by several methods. By one process, tri-calcium phosphate, the essential ingredient of phosphate rock, is heated in the presence of carbon and silica in an electric furnace or fuel-fired furnace. Elementary phosphorus is liberated as vapor and may be collected under water. If desired, the phosphorus vapor and carbon monoxide produced by the reaction can be oxidized at once in the presence of moisture to produce phosphoric acid, an important compound in making super-phosphate fertilizers. In recent years, concentrated phosphoric acids, which may contain as much as 70 to 75% P_2O_5 content, have become of great importance to agriculture and farm production. World-wide demand for fertilizers has caused record phosphate production. Phosphates are used in the production of special glasses, such as those used for sodium lamps. Bone-ash, calcium phosphate, is also used to produce fine chinaware and to produce mono-calcium phosphate used in baking powder. Phosphorus is also important in the production of steels, phosphor bronze, and many other products. Trisodium phosphate is important as a cleaning agent, as a water softener, and for preventing boiler scale and corrosion of pipes and boiler tubes. Organic compounds of phosphorus are important. Amorphous (red) phosphorus costs about $70/kg (99%).

Platinum — (It. *platina*, silver), Pt; at. wt. 195.078(2); at. no. 78; m.p. 1768.4°C; b.p. 3825°C; sp. gr. 21.45 (20°C); valence 1?, 2, 3, or 4. Discovered in South America by Ulloa in 1735 and by Wood in 1741. The metal was used by pre-Columbian Indians. Platinum occurs native, accompanied by small quantities of iridium, osmium, palladium, ruthenium, and rhodium, all belonging to the same group of metals. These are found in the alluvial deposits of the Ural mountains and in Columbia. *Sperrylite* ($PtAs_2$), occurring with the nickel-bearing deposits of Sudbury, Ontario, is a source of a considerable amount of metal. The large production of nickel offsets there being only one part of the platinum metals in two million parts of ore. The largest supplier of the platinum group of metals is now South Africa, followed by Russia and Canada. Platinum is a beautiful silvery-white metal, when pure, and is malleable and ductile. It has a coefficient of expansion almost equal to that of soda-lime-silica glass, and is therefore used to make sealed electrodes in glass systems. The metal does not oxidize in air at any temperature, but is corroded by halogens, cyanides, sulfur, and caustic alkalis. It is insoluble in hydrochloric and nitric acid, but dissolves when they are mixed as *aqua regia*, forming chloroplatinic acid (H_2PtCl_6), an important compound. Natural platinum contains six isotopes, one of which, ^{190}Pt, is radioactive with a long half-life. Thirty-seven other radioactive isotopes and isomers are recognized. The metal is extensively used in jewelry, wire, and vessels for laboratory use, and in many valuable instruments including thermocouple elements. It is also used for electrical contacts, corrosion-resistant apparatus, and in dentistry. Platinum-cobalt alloys have magnetic properties. One such alloy made of 76.7% Pt and 23.3% Co, by weight, is an extremely powerful magnet that offers a B-H (max) almost twice that of Alnico V. Platinum resistance wires are used for constructing high-temperature electric furnaces. The metal is used for coating missile nose cones, jet engine fuel nozzles, etc., which must perform reliably for long periods of time at high temperatures. The metal, like palladium, absorbs large volumes, of hydrogen, retaining it at ordinary temperatures but giving it up at red heat. In the finely divided state platinum is an excellent catalyst, having long been used in the contact process for producing sulfuric acid. It is also used as a catalyst in cracking petroleum products. There is also much current interest in the use of platinum as a catalyst in fuel cells and in its use as antipollution devices for automobiles. Platinum anodes are extensively used in cathodic protection systems for large ships and ocean-going vessels, pipelines, steel piers, etc. Pure platinum wire will glow red hot when placed in the vapor of methyl alcohol. It acts here as a catalyst, converting the alcohol to formaldehyde. This phenomenon has been used commercially to produce cigarette lighters and hand warmers. Hydrogen and oxygen explode in the presence of platinum. The price of platinum has varied widely; more than a century ago it was used to adulterate gold. It was nearly eight times as valuable as gold in 1920. The price in January 2002 was about $430/troy oz. ($15/g), higher than the price of gold.

Plutonium — (planet *Pluto*), Pu; at. wt. (244); at. no. 94; sp. gr. (α modification) 19.84 (25°C); m.p. 640°C; b.p. 3228°C; valence 3, 4, 5, or 6. Plutonium was the second transuranium element of the actinide series to be discovered. The isotope ^{238}Pu was produced in 1940 by Seaborg, McMillan, Kennedy, and Wahl by deuteron bombardment of uranium in the 60-inch cyclotron at Berkeley, California. Plutonium also exists in trace quantities in naturally occurring uranium ores. It is formed in much the same manner as neptunium, by irradiation of natural uranium with the neutrons which are present. By far of greatest importance is the isotope Pu^{239}, with a half-life of 24,100 years, produced in extensive quantities in nuclear reactors from natural uranium:

$$^{238}U(n,\gamma) \rightarrow {}^{239}U \xrightarrow{\beta} {}^{239}Np \xrightarrow{\beta} {}^{239}Pu$$

Nineteen isotopes of plutonium are now known. Plutonium has assumed the position of dominant importance among the transuranium elements because of its successful use as an explosive ingredient in nuclear weapons and the place which it holds as a key material in the development of industrial use of nuclear power. One kilogram is equivalent to about 22 million kilowatt hours of heat energy. The complete detonation of a kilogram of plutonium produces an explosion equal to about 20,000 tons of chemical explosive. Its importance depends on the nuclear property of being readily fissionable with neutrons and its availability in quantity. The world's nuclear-power reactors are now producing about 20,000 kg of plutonium/yr. By 1982 it was estimated that about 300,000 kg had accumulated. The various nuclear applications of plutonium are well known. ^{238}Pu has been used in the Apollo lunar missions to power seismic and other equipment on the lunar surface. As with neptunium and uranium, plutonium metal can be prepared by reduction of the trifluoride with alkaline-earth metals. The metal has a silvery appearance and takes on a yellow tarnish when slightly oxidized. It is chemically reactive. A relatively large piece of plutonium is warm to the touch because of the energy given off in alpha decay. Larger pieces will produce enough heat to boil water. The metal readily dissolves in concentrated hydrochloric acid, hydroiodic acid, or perchloric acid with formation of the Pu^{+3} ion. The metal exhibits six allotropic modifications having various crystalline structures. The densities of these vary from 16.00 to 19.86 g/cm^3. Plutonium also exhibits four ionic valence states in aqueous solutions: Pu^{+3}(blue lavender), Pu^{+4} (yellow brown), PuO^+ (pink?), and PuO^{+2} (pink orange). The ion PuO^+ is unstable in aqueous solutions, disproportionating into Pu^{+4} and PuO^{+2}. The Pu^{+4} thus formed, however, oxidizes the PuO^+ into PuO^{+2}, itself being reduced to Pu^{+3}, giving finally Pu^{+3} and PuO^{+2}. Plutonium forms binary compounds with oxygen: PuO, PuO_2, and intermediate oxides of variable composition; with the halides: PuF_3, PuF_4, $PuCl_3$, $PuBr_3$, PuI_3; with carbon, nitrogen, and silicon: PuC, PuN, $PuSi_2$. Oxyhalides are also well known: PuOCl, PuOBr, PuOI. Because of the high rate of emission of alpha particles and the element being specifically absorbed by bone marrow, plutonium, as well as all of the other transuranium elements except neptunium, are radiological poisons and must be handled with very special equipment and precautions. Plutonium is a very dangerous radiological hazard. Precautions must also be taken to prevent the unintentional formation of a critical mass. Plutonium in liquid solution is more likely to become critical than solid plutonium. The shape of the mass must also be considered where criticality is concerned. Plutonium-239 is available to authorized users from the O.R.N.L. at a cost of about $4.80/mg (99.9%) plus packing costs.

Polonium — (Poland, native country of Mme. Curie [1867–1934]), Po; at. wt. (209); at. no. 84; m.p. 254°C; b.p. 962°C; sp. gr. (alpha modification) 9.32; valence –2, 0, +2, +3(?), +4, and +6. Polonium was the first element discovered by Mme. Curie in

1898, while seeking the cause of radioactivity of pitchblende from Joachimsthal, Bohemia. The electroscope showed it separating with bismuth. Polonium is also called Radium F. Polonium is a very rare natural element. Uranium ores contain only about 100 μg of the element per ton. Its abundance is only about 0.2% of that of radium. In 1934, it was found that when natural bismuth (^{209}Bi) was bombarded by neutrons, ^{210}Bi, the parent of polonium, was obtained. Milligram amounts of polonium may now be prepared this way, by using the high neutron fluxes of nuclear reactors. Polonium-210 is a low-melting, fairly volatile metal, 50% of which is vaporized in air in 45 hours at 55°C. It is an alpha emitter with a half-life of 138.39 days. A milligram emits as many alpha particles as 5 g of radium. The energy released by its decay is so large (140 W/g) that a capsule containing about half a gram reaches a temperature above 500°C. The capsule also presents a contact gamma-ray dose rate of 0.012 Gy/h. A few curies (1 curie = 3.7×10^{10} Bq) of polonium exhibit a blue glow, caused by excitation of the surrounding gas. Because almost all alpha radiation is stopped within the solid source and its container, giving up its energy, polonium has attracted attention for uses as a lightweight heat source for thermoelectric power in space satellites. Thirty-eight isotopes and isomers of polonium are known, with atomic masses ranging from 192 to 218. All are radioactive. Polonium-210 is the most readily available. Isotopes of mass 209 (half-life 102 years) and mass 208 (half-life 2.9 years) can be prepared by alpha, proton, or deuteron bombardment of lead or bismuth in a cyclotron, but these are expensive to produce. Metallic polonium has been prepared from polonium hydroxide and some other polonium compounds in the presence of concentrated aqueous or anhydrous liquid ammonia. Two allotropic modifications are known to exist. Polonium is readily dissolved in dilute acids, but is only slightly soluble in alkalis. Polonium salts of organic acids char rapidly; halide amines are reduced to the metal. Polonium can be mixed or alloyed with beryllium to provide a source of neutrons. It has been used in devices for eliminating static charges in textile mills, etc.; however, beta sources are more commonly used and are less dangerous. It is also used on brushes for removing dust from photographic films. The polonium for these is carefully sealed and controlled, minimizing hazards to the user. Polonium-210 is very dangerous to handle in even milligram or microgram amounts, and special equipment and strict control is necessary. Damage arises from the complete absorption of the energy of the alpha particle into tissue. The maximum permissible body burden for ingested polonium is only 0.03 μCi, which represents a particle weighing only 6.8×10^{-12} g. Weight for weight it is about 2.5×10^{11} times as toxic as hydrocyanic acid. The maximum allowable concentration for soluble polonium compounds in air is about 2×10^{11} μCi/cm^3. Polonium-209 is available on special order from the Oak Ridge National Laboratory at a cost of $3600/μCi plus packing costs.

Potassium — (English, *potash* — pot ashes; L. *kalium*, Arab. *qali*, alkali), K; at. wt. 39.0983(1); at. no. 19; m.p. 63.38°C; b.p. 759°C; sp. gr. 0.862 (20°C); valence 1. Discovered in 1807 by Davy, who obtained it from caustic potash (KOH); this was the first metal isolated by electrolysis. The metal is the seventh most abundant and makes up about 2.4% by weight of the earth's crust. Most potassium minerals are insoluble and the metal is obtained from them only with great difficulty. Certain minerals, however, such as *sylvite, carnallite, langbeinite,* and *polyhalite* are found in ancient lake and sea beds and form rather extensive deposits from which potassium and its salts can readily be obtained. Potash is mined in Germany, New Mexico, California, Utah, and elsewhere. Large deposits of potash, found at a depth of some 1000 m in Saskatchewan, promise to be important in coming years. Potassium is also found in the ocean, but is present only in relatively small amounts, compared to sodium. The greatest demand for potash has been in its use for fertilizers. Potassium is an essential constituent for plant growth and it is found in most soils. Potassium is never found free in nature, but is obtained by electrolysis of the hydroxide, much in the same manner as prepared by Davy. Thermal methods also are commonly used to produce potassium (such as by reduction of potassium compounds with CaC_2, C, Si, or Na). It is one of the most reactive and electropositive of metals. Except for lithium, it is the lightest known metal. It is soft, easily cut with a knife, and is silvery in appearance immediately after a fresh surface is exposed. It rapidly oxidizes in air and should be preserved in a mineral oil. As with other metals of the alkali group, it decomposes in water with the evolution of hydrogen. It catches fire spontaneously on water. Potassium and its salts impart a violet color to flames. Twenty one isotopes, one of which is an isomer, of potassium are known. Ordinary potassium is composed of three isotopes, one of which is ^{40}K (0.0117%), a radioactive isotope with a half-life of 1.26×10^9 years. The radioactivity presents no appreciable hazard. An alloy of sodium and potassium (NaK) is used as a heat-transfer medium. Many potassium salts are of utmost importance, including the hydroxide, nitrate, carbonate, chloride, chlorate, bromide, iodide, cyanide, sulfate, chromate, and dichromate. Metallic potassium is available commercially for about $1200/kg (98% purity) or $75/g (99.95% purity).

Praseodymium — (Gr. *prasios,* green, and *didymos*, twin), Pr; at. wt. 140.90765(2); at. no. 59; m.p. 931°C; b.p. 3520°C; sp. gr. 6.773; valence 3. In 1841 Mosander extracted the rare earth *didymia* from *lanthana*; in 1879, Lecoq de Boisbaudran isolated a new earth, *samaria*, from didymia obtained from the mineral *samarskite*. Six years later, in 1885, von Welsbach separated didymia into two others, *praseodymia* and *neodymia*, which gave salts of different colors. As with other rare earths, compounds of these elements in solution have distinctive sharp spectral absorption bands or lines, some of which are only a few Angstroms wide. The element occurs along with other rare-earth elements in a variety of minerals. *Monazite* and *bastnasite* are the two principal commercial sources of the rare-earth metals. Ion-exchange and solvent extraction techniques have led to much easier isolation of the rare earths and the cost has dropped greatly in the past few years. Thirty-seven isotopes and isomers are now recognized. Praseodymium can be prepared by several methods, such as by calcium reduction of the anhydrous chloride of fluoride. Misch metal, used in making cigarette lighters, contains about 5% praseodymium metal. Praseodymium is soft, silvery, malleable, and ductile. It was prepared in relatively pure form in 1931. It is somewhat more resistant to corrosion in air than europium, lanthanum, cerium, or neodymium, but it does develop a green oxide coating that spalls off when exposed to air. As with other rare-earth metals it should be kept under a light mineral oil or sealed in plastic. The rare-earth oxides, including Pr_2O_3, are among the most refractory substances known. Along with other rare earths, it is widely used as a core material for carbon arcs used by the motion picture industry for studio lighting and projection. Salts of praseodymium are used to color

glasses and enamels; when mixed with certain other materials, praseodymium produces an intense and unusually clean yellow color in glass. Didymium glass, of which praseodymium is a component, is a colorant for welder's goggles. The metal (99.9% pure) is priced at about $4/g.

Promethium — (*Prometheus*, who, according to mythology, stole fire from heaven), Pm; at. no. 61; at. wt. (145); m.p. 1042°C; b.p. 3000°C (est.); sp. gr. 7.264 (25°C); valence 3. In 1902 Branner predicted the existence of an element between neodymium and samarium, and this was confirmed by Moseley in 1914. Unsuccessful searches were made for this predicted element over two decades, and various investigators proposed the names "illinium", "florentium", and "cyclonium" for this element. In 1941, workers at Ohio State University irradiated neodymium and praseodymium with neutrons, deuterons, and alpha particles, resp., and produced several new radioactivities, which most likely were those of element 61. Wu and Segre, and Bethe, in 1942, confirmed the formation; however, chemical proof of the production of element 61 was lacking because of the difficulty in separating the rare earths from each other at that time. In 1945, Marinsky, Glendenin, and Coryell made the first chemical identification by use of ion-exchange chromatography. Their work was done by fission of uranium and by neutron bombardment of neodymium. These investigators named the newly discovered element. Searches for the element on earth have been fruitless, and it now appears that promethium is completely missing from the earth's crust. Promethium, however, has been reported to be in the spectrum of the star HR^{465} in Andromeda. This element is being formed recently near the star's surface, for no known isotope of promethium has a half-life longer than 17.7 years. Thirty five isotopes and isomers of promethium, with atomic masses from 130 to 158 are now known. Promethium-145,with a half-life of 17.7 years, is the most useful. Promethium-145 has a specific activity of 940 Ci/g. It is a soft beta emitter; although no gamma rays are emitted, X-radiation can be generated when beta particles impinge on elements of a high atomic number, and great care must be taken in handling it. Promethium salts luminesce in the dark with a pale blue or greenish glow, due to their high radioactivity. Ion-exchange methods led to the preparation of about 10 g of promethium from atomic reactor fuel processing wastes in early 1963. Little is yet generally known about the properties of metallic promethium. Two allotropic modifications exist. The element has applications as a beta source for thickness gages, and it can be absorbed by a phosphor to produce light. Light produced in this manner can be used for signs or signals that require dependable operation; it can be used as a nuclear-powered battery by capturing light in photocells which convert it into electric current. Such a battery, using ^{147}Pm, would have a useful life of about 5 years. It is being used for fluorescent lighting starters and coatings for self-luminous watch dials. Promethium shows promise as a portable X-ray source, and it may become useful as a heat source to provide auxiliary power for space probes and satellites. More than 30 promethium compounds have been prepared. Most are colored. Promethium-147 is available upon special order from the Idaho National Engineering Laboratory, Idaho Falls, ID, or from the Westinghouse Hanford Co., Richland, WA.

Protactinium — (Gr. *protos*, first), Pa; at. wt. 231.03588(2); at. no. 91; m.p. 1572°C; sp. gr. 15.37 (calc.); valence 4 or 5. The first isotope of element 91 to be discovered was ^{234}Pa, also known as UX_2, a short-lived member of the naturally occurring ^{238}U decay series. It was identified by K. Fajans and O. H. Gohring in 1913 and they named the new element *brevium*. When the longer-lived isotope ^{231}Pa was identified by Hahn and Meitner in 1918, the name protoactinium was adopted as being more consistent with the characteristics of the most abundant isotope. Soddy, Cranson, and Fleck were also active in this work. The name *protoactinium* was shortened to *protactinium* in 1949. In 1927, Grosse prepared 2 mg of a white powder, which was shown to be Pa_2O_5. Later, in 1934, from 0.1 g of pure Pa_2O_5 he isolated the element by two methods, one of which was by converting the oxide to an iodide and "cracking" it in a high vacuum by an electrically heated filament by the reaction

$$2PaI_5 \rightarrow 2Pa + 5I_2$$

Protactinium has a bright metallic luster which it retains for some time in air. The element occurs in *pitchblende* to the extent of about 1 part ^{231}Pa to 10 million of ore. Ores from Congo-Kinshasa have about 3 ppm. Protactinium has twenty-eight isotopes and isomers, the most common of which is ^{231}Pr with a half-life of 32,500 years. A number of protactinium compounds are known, some of which are colored. The element is superconductive below 1.4 K. The element is a dangerous toxic material and requires precautions similar to those used when handling plutonium. In 1959 and 1961, it was announced that the Great Britain Atomic Energy Authority extracted by a 12-stage process 125 g of 99.9% protactinium, the world's only stock of the metal for many years to come. The extraction was made from 60 tons of waste material at a cost of about $500,000. Protactinium is one of the rarest and most expensive naturally occurring elements.

Radium — (L. *radius*, ray), Ra; at. wt. (226); at. no. 88; m.p. 700°C; sp. gr. 5; valence 2. Radium was discovered in 1898 by M. and Mme. Curie in the *pitchblende* or *uraninite* of North Bohemia (Czech Republic), where it occurs. There is about 1 g of radium in 7 tons of pitchblende. The element was isolated in 1911 by Mme. Curie and Debierne by the electrolysis of a solution of pure radium chloride, employing a mercury cathode; on distillation in an atmosphere of hydrogen this amalgam yielded the pure metal. Originally, radium was obtained from the rich pitchblende ore found at Joachimsthal, Bohemia. The *carnotite* sands of Colorado furnish some radium, but richer ores are found in the Republic of Congo-Kinshasa and the Great Bear Lake region of Canada. Radium is present in all uranium minerals, and could be extracted, if desired, from the extensive wastes of uranium processing. Large uranium deposits are located in Ontario, New Mexico, Utah, Australia, and elsewhere. Radium is obtained commercially as the bromide or chloride; it is doubtful if any appreciable stock of the isolated element now exists. The pure metal is brilliant white when freshly prepared, but blackens on exposure to air, probably due to formation of the nitride. It exhibits luminescence, as do its salts; it decomposes in water and is somewhat more volatile than barium. It is a member of the alkaline-earth group of metals. Radium imparts a carmine red color to a flame. Radium emits alpha, beta, and gamma rays and when mixed with beryllium produce neutrons. One gram of ^{226}Ra undergoes 3.7×10^{10} disintegrations per s. The *curie (Ci)* is defined as that amount of radioactivity which has the same disintegration rate as 1 g of ^{226}Ra. Thirty-six isotopes are now known; radium 226, the common isotope, has a half-life of 1599 years.

One gram of radium produces about 0.0001 ml (stp) of emanation, or radon gas, per day. This is pumped from the radium and sealed in minute tubes, which are used in the treatment of cancer and other diseases. One gram of radium yields about 4186 kJ per year. Radium is used in producing self-luminous paints, neutron sources, and in medicine for the treatment of disease. Some of the more recently discovered radioisotopes, such as ^{60}Co, are now being used in place of radium. Some of these sources are much more powerful, and others are safer to use. Radium loses about 1% of its activity in 25 years, being transformed into elements of lower atomic weight. Lead is a final product of disintegration. Stored radium should be ventilated to prevent build-up of radon. Inhalation, injection, or body exposure to radium can cause cancer and other body disorders. The maximum permissible burden in the total body for ^{226}Ra is 7400 becquerel.

Radon — (from *radium*; called *niton* at first, L. *nitens*, shining), Rn; at. wt. (222); at. no. 86; m.p. –71°C; b.p. –61.7°C; t_c 104°C; density of gas 9.73 g/l; sp. gr. liquid 4.4 at –62°C, solid 4; valence usually 0. The element was discovered in 1900 by Dorn, who called it *radium emanation*. In 1908 Ramsay and Gray, who named it *niton*, isolated the element and determined its density, finding it to be the heaviest known gas. It is essentially inert and occupies the last place in the zero group of gases in the Periodic Table. Since 1923, it has been called radon. Thirty-seven isotopes and isomers are known. Radon-222, coming from radium, has a half-life of 3.823 days and is an alpha emitter; Radon-220, emanating naturally from thorium and called *thoron*, has a half-life of 55.6 s and is also an alpha emitter. Radon-219 emanates from actinium and is called *actinon*. It has a half-life of 3.9 s and is also an alpha emitter. It is estimated that every square mile of soil to a depth of 6 inches contains about 1 g of radium, which releases radon in tiny amounts to the atmosphere. Radon is present in some spring waters, such as those at Hot Springs, Arkansas. On the average, one part of radon is present to 1×10^{21} part of air. At ordinary temperatures radon is a colorless gas; when cooled below the freezing point, radon exhibits a brilliant phosphorescence which becomes yellow as the temperature is lowered and orange-red at the temperature of liquid air. It has been reported that fluorine reacts with radon, forming radon fluoride. Radon clathrates have also been reported. Radon is still produced for therapeutic use by a few hospitals by pumping it from a radium source and sealing it in minute tubes, called seeds or needles, for application to patients. This practice has now been largely discontinued as hospitals can order the seeds directly from suppliers, who make up the seeds with the desired activity for the day of use. Care must be taken in handling radon, as with other radioactive materials. The main hazard is from inhalation of the element and its solid daughters, which are collected on dust in the air. Good ventilation should be provided where radium, thorium, or actinium is stored to prevent build-up of this element. Radon build-up is a health consideration in uranium mines. Recently radon build-up in homes has been a concern. Many deaths from lung cancer are caused by radon exposure. In the U.S. it is recommended that remedial action be taken if the air from radon in homes exceeds 4 pCi/l.

Rhenium — (L. *Rhenus,* Rhine), Re; at. wt. 186.207(1); at. no. 75; m.p. 3186°C; b.p. 5596°C; sp. gr. 21.02 (20°C); valence –1, +1, 2, 3, 4, 5, 6, 7. Discovery of rhenium is generally attributed to Noddack, Tacke, and Berg, who announced in 1925 they had detected the element in platinum ores and *columbite*. They also found the element in *gadolinite* and *molybdenite*. By working up 660 kg of molybdenite they were able in 1928 to extract 1 g of rhenium. The price in 1928 was $10,000/g. Rhenium does not occur free in nature or as a compound in a distinct mineral species. It is, however, widely spread throughout the earth's crust to the extent of about 0.001 ppm. Commercial rhenium in the U.S. today is obtained from molybdenite roaster-flue dusts obtained from copper-sulfide ores mined in the vicinity of Miami, Arizona, and elsewhere in Arizona and Utah. Some molybdenites contain from 0.002 to 0.2% rhenium. It is estimated that in 1999 about 16,000 kg of rhenium was being produced. The total estimated world reserves of rhenium is 11,000,000 kg. The total estimated Free World reserve of rhenium metal is 3500 tons. Natural rhenium is a mixture of two isotopes, one of which has a very long half-life. Thirty nine other unstable isotopes are recognized. Rhenium metal is prepared by reducing ammonium perrhenate with hydrogen at elevated temperatures. The element is silvery white with a metallic luster; its density is exceeded only by that of platinum, iridium, and osmium, and its melting point is exceeded only by that of tungsten and carbon. It has other useful properties. The usual commercial form of the element is a powder, but it can be consolidated by pressing and resistance-sintering in a vacuum or hydrogen atmosphere. This produces a compact shape in excess of 90% of the density of the metal. Annealed rhenium is very ductile, and can be bent, coiled, or rolled. Rhenium is used as an additive to tungsten and molybdenum-based alloys to impart useful properties. It is widely used for filaments for mass spectrographs and ion gages. Rhenium-molybdenum alloys are superconductive at 10 K. Rhenium is also used as an electrical contact material as it has good wear resistance and withstands arc corrosion. Thermocouples made of Re-W are used for measuring temperatures up to 2200°C, and rhenium wire has been used in photoflash lamps for photography. Rhenium catalysts are exceptionally resistant to poisoning from nitrogen, sulfur, and phosphorus, and are used for hydrogenation of fine chemicals, hydrocracking, reforming, and disproportionation of olefins. Rhenium has recently become especially important as a catalyst for petroleum refining and in making super-alloys for jet engines. Rhenium costs about $16/g (99.99% pure). Little is known of its toxicity; therefore, it should be handled with care until more data are available.

Rhodium — (Gr. *rhodon*, rose), Rh; at. wt. 102.90550(3); at. no. 45; m.p. 1964°C; b.p. 3695°C; sp. gr. 12.41 (20°C); valence 2, 3, 4, 5, and 6. Wollaston discovered rhodium in 1803-4 in crude platinum ore he presumably obtained from South America. Rhodium occurs native with other platinum metals in river sands of the Urals and in North and South America. It is also found with other platinum metals in the copper-nickel sulfide ores of the Sudbury, Ontario region. Although the quantity occurring here is very small, the large tonnages of nickel processed make the recovery commercially feasible. The annual world production of rhodium in 1999 was only about 9000 kg. The metal is silvery white and at red heat slowly changes in air to the sesquioxide. At higher temperatures it converts back to the element. Rhodium has a higher melting point and lower density than platinum. Its major use is as an alloying agent to harden platinum and palladium. Such alloys are used for furnace windings, thermocouple elements, bushings for glass fiber production, electrodes for aircraft spark plugs, and laboratory crucibles. It is useful as an electrical contact

material as it has a low electrical resistance, a low and stable contact resistance, and is highly resistant to corrosion. Plated rhodium, produced by electroplating or evaporation, is exceptionally hard and is used for optical instruments. It has a high reflectance and is hard and durable. Rhodium is also used for jewelry, for decoration, and as a catalyst. Fifty-two isotopes and isomers are now known. Rhodium metal (powder) costs about $180/g (99.9%).

Rubidium — (L. *rubidus*, deepest red), Rb; at. wt. 85.4678(3); at. no. 37; m.p. 39.31°C; b.p. 688°C; sp. gr. (solid) 1.532 (20°C), (liquid) 1.475 (39°C); valence 1, 2, 3, 4. Discovered in 1861 by Bunsen and Kirchoff in the mineral *lepidolite* by use of the spectroscope. The element is much more abundant than was thought several years ago. It is now considered to be the 16th most abundant element in the earth's crust. Rubidium occurs in *pollucite, carnallite, leucite,* and *zinnwaldite*, which contains traces up to 1%, in the form of the oxide. It is found in lepidolite to the extent of about 1.5%, and is recovered commercially from this source. Potassium minerals, such as those found at Searles Lake, California, and potassium chloride recovered from brines in Michigan also contain the element and are commercial sources. It is also found along with cesium in the extensive deposits of *pollucite* at Bernic Lake, Manitoba. Rubidium can be liquid at room temperature. It is a soft, silvery-white metallic element of the alkali group and is the second most electropositive and alkaline element. It ignites spontaneously in air and reacts violently in water, setting fire to the liberated hydrogen. As with other alkali metals, it forms amalgams with mercury and it alloys with gold, cesium, sodium, and potassium. It colors a flame yellowish violet. Rubidium metal can be prepared by reducing rubidium chloride with calcium, and by a number of other methods. It must be kept under a dry mineral oil or in a vacuum or inert atmosphere. Thirty five isotopes and isomers of rubidium are known. Naturally occurring rubidium is made of two isotopes, ^{85}Rb and ^{87}Rb. Rubidium-87 is present to the extent of 27.83% in natural rubidium and is a beta emitter with a half-life of 4.9×10^{10} years. Ordinary rubidium is sufficiently radioactive to expose a photographic film in about 30 to 60 days. Rubidium forms four oxides: Rb_2O, Rb_2O_2, Rb_2O_3, Rb_2O_4. Because rubidium can be easily ionized, it has been considered for use in "ion engines" for space vehicles; however, cesium is somewhat more efficient for this purpose. It is also proposed for use as a working fluid for vapor turbines and for use in a thermoelectric generator using the magnetohydrodynamic principle where rubidium ions are formed by heat at high temperature and passed through a magnetic field. These conduct electricity and act like an armature of a generator thereby generating an electric current. Rubidium is used as a getter in vacuum tubes and as a photocell component. It has been used in making special glasses. $RbAg_4I_5$ is important, as it has the highest room conductivity of any known ionic crystal. At 20°C its conductivity is about the same as dilute sulfuric acid. This suggests use in thin film batteries and other applications. The present cost in small quantities is about $50/g (99.8% pure).

Ruthenium — (L. *Ruthenia*, Russia), Ru; at. wt. 101.07(2); at. no. 44, m.p. 2334°C; b.p. 4150°C; sp. gr. 12.41 (20°C); valence 0, 1, 2, 3, 4, 5, 6, 7, 8. Berzelius and Osann in 1827 examined the residues left after dissolving crude platinum from the Ural mountains in *aqua regia*. While Berzelius found no unusual metals, Osann thought he found three new metals, one of which he named ruthenium. In 1844 Klaus, generally recognized as the discoverer, showed that Osann's ruthenium oxide was very impure and that it contained a new metal. Klaus obtained 6 g of ruthenium from the portion of crude platinum that is insoluble in *aqua regia*. A member of the platinum group, ruthenium occurs native with other members of the group in ores found in the Ural mountains and in North and South America. It is also found along with other platinum metals in small but commercial quantities in *pentlandite* of the Sudbury, Ontario, nickel-mining region, and in *pyroxinite* deposits of South Africa. Natural ruthenium contains seven isotopes. Twenty-eight other isotopes and isomers are known, all of which are radioactive. The metal is isolated commercially by a complex chemical process, the final stage of which is the hydrogen reduction of ammonium ruthenium chloride, which yields a powder. The powder is consolidated by powder metallurgy techniques or by argon-arc welding. Ruthenium is a hard, white metal and has four crystal modifications. It does not tarnish at room temperatures, but oxidizes in air at about 800°C. The metal is not attacked by hot or cold acids or *aqua regia*, but when potassium chlorate is added to the solution, it oxidizes explosively. It is attacked by halogens, hydroxides, etc. Ruthenium can be plated by electrodeposition or by thermal decomposition methods. The metal is one of the most effective hardeners for platinum and palladium, and is alloyed with these metals to make electrical contacts for severe wear resistance. A ruthenium-molybdenum alloy is said to be superconductive at 10.6 K. The corrosion resistance of titanium is improved a hundredfold by addition of 0.1% ruthenium. It is a versatile catalyst. Hydrogen sulfide can be split catalytically by light using an aqueous suspension of CdS particles loaded with ruthenium dioxide. It is thought this may have application to removal of H_2S from oil refining and other industrial processes. Compounds in at least eight oxidation states have been found, but of these, the +2. +3. and +4 states are the most common. Ruthenium tetroxide, like osmium tetroxide, is highly toxic. In addition, it may explode. Ruthenium compounds show a marked resemblance to those of osmium. The metal is priced at about $25/g (99.95% pure).

Rutherfordium — (Ernest Rutherford [1871–1937], New Zealand, Canadian, and British physicist); Rf; at. wt. [261]; at. no. 104. In 1964, workers of the Joint Nuclear Research Institute at Dubna (Russia) bombarded plutonium with accelerated 113 to 115 MeV neon ions. By measuring fission tracks in a special glass with a microscope, they detected an isotope that decays by spontaneous fission. They suggested that this isotope, which has a half-life of 0.3 ± 0.1 s, might be ^{260}104, produced by the following reaction:

$$^{242}_{94}\mathrm{Pu} + ^{22}_{10}\mathrm{Ne} \rightarrow ^{260}104 + 4\mathrm{n}$$

Element 104, the first *transactinide* element, is expected to have chemical properties similar to those of hafnium. It would, for example, form a relatively volatile compound with chlorine (a tetrachloride). The Soviet scientists have performed experiments aimed at chemical identification, and have attempted to show that the 0.3-s activity is more volatile than that of the relatively nonvolatile actinide trichlorides. This experiment does not fulfill the test of chemically separating the new element from all others, but it provides important evidence for evaluation. New data, reportedly issued by Soviet scientists, have reduced the half-life of the isotope they worked with from 0.3 to 0.15 s. The Dubna scientists suggest the name *kurchatovium* and symbol *Ku* for Element 104, in honor of

Igor Vasilevich Kurchatov (1903–1960), late Head of Soviet Nuclear Research. The Dubna Group also has proposed the name *dubnium* for Element 104. In 1969, Ghiorso, Nurmia, Harris, K. A. Y. Eskola, and P. L. Eskola of the University of California at Berkeley reported they had positively identified two, and possibly three, isotopes of Element 104. The group also indicated that after repeated attempts so far they have been unable to produce isotope ^{260}104 reported by the Dubna groups in 1964. The discoveries at Berkeley were made by bombarding a target of ^{249}Cf with ^{12}C nuclei of 71 MeV, and ^{13}C nuclei of 69 MeV. The combination of ^{12}C with ^{249}Cf followed by instant emission of four neutrons produced Element ^{257}104. This isotope has a half-life of 4 to 5 s, decaying by emitting an alpha particle into ^{253}No, with a half-life of 105 s. The same reaction, except with the emission of three neutrons, was thought to have produced ^{258}104 with a half-life of about 1/100 s. Element ^{259}104 is formed by the merging of a ^{13}C nuclei with ^{249}Cf, followed by emission of three neutrons. This isotope has a half-life of 3 to 4 s, and decays by emitting an alpha particle into ^{255}No, which has a half-life of 185 s. Thousands of atoms of ^{257}104 and ^{259}104 have been detected. The Berkeley group believe their identification of ^{258}104 was correct. Eleven isotopes of Element 104 have now been identified. The Berkeley group proposed for the new element the name *rutherfordium* (symbol Rf), in honor of Ernest Rutherford. This name was formally adapted by IUPAC in August 1997.

Samarium — (*Samarskite,* a mineral), Sm; at. wt. 150.36(3); at. no. 62; m.p. 1074°C; b.p. 1794°C; sp. gr (α) 7.520 (25°C); valence 2 or 3. Discovered spectroscopically by its sharp absorption lines in 1879 by Lecoq de Boisbaudran in the mineral *samarskite*, named in honor of a Russian mine official, Col. Samarski. Samarium is found along with other members of the rare-earth elements in many minerals, including *monazite* and *bastnasite*, which are commercial sources. The largest producer of rare earth minerals is now China, followed by the U.S., India, and Russia. It occurs in monazite to the extent of 2.8%. While *misch metal* containing about 1% of samarium metal, has long been used, samarium has not been isolated in relatively pure form until recent years. Ion-exchange and solvent extraction techniques have recently simplified separation of the rare earths from one another; more recently, electrochemical deposition, using an electrolytic solution of lithium citrate and a mercury electrode, is said to be a simple, fast, and highly specific way to separate the rare earths. Samarium metal can be produced by reducing the oxide with barium or lanthanum. Samarium has a bright silver luster and is reasonably stable in air. Three crystal modifications of the metal exist, with transformations at 734 and 922°C. The metal ignites in air at about 150°C. Thirty-three isotopes and isomers of samarium are now recognized. Natural samarium is a mixture of seven isotopes, three of which are unstable but have long half-lives. Samarium, along with other rare earths, is used for carbon-arc lighting for the motion picture industry. The sulfide has excellent high-temperature stability and good thermoelectric efficiencies up to 1100°C. $SmCo_5$ has been used in making a new permanent magnet material with the highest resistance to demagnetization of any known material. It is said to have an intrinsic coercive force as high as 2200 kA/m. Samarium oxide has been used in optical glass to absorb the infrared. Samarium is used to dope calcium fluoride crystals for use in optical masers or lasers. Compounds of the metal act as sensitizers for phosphors excited in the infrared; the oxide exhibits catalytic properties in the dehydration and dehydrogenation of ethyl alcohol. It is used in infrared absorbing glass and as a neutron absorber in nuclear reactors. The metal is priced at about $3.50/g (99.9%). Little is known of the toxicity of samarium; therefore, it should be handled carefully.

Scandium — (L. *Scandia*, Scandinavia), Sc; at. wt. 44.955910(8); at. no. 21; m.p. 1541°C; b.p. 2836°C; sp. gr. 2.989 (25°C); valence 3. On the basis of the Periodic System, Mendeleev predicted the existence of *ekaboron*, which would have an atomic weight between 40 of calcium and 48 of titanium. The element was discovered by Nilson in 1878 in the minerals *euxenite* and *gadolinite*, which had not yet been found anywhere except in Scandinavia. By processing 10 kg of euxenite and other residues of rare-earth minerals, Nilson was able to prepare about 2 g of scandium oxide of high purity. Cleve later pointed out that Nilson's scandium was identical with Mendeleev's ekaboron. Scandium is apparently a much more abundant element in the sun and certain stars than here on earth. It is about the 23rd most abundant element in the sun, compared to the 50th most abundant on earth. It is widely distributed on earth, occurring in very minute quantities in over 800 mineral species. The blue color of beryl (aquamarine variety) is said to be due to scandium. It occurs as a principal component in the rare mineral *thortveitite*, found in Scandinavia and Malagasy. It is also found in the residues remaining after the extraction of tungsten from Zinnwald *wolframite*, and in *wiikite* and *bazzite*. Most scandium is presently being recovered from *thortveitite* or is extracted as a by-product from uranium mill tailings. Metallic scandium was first prepared in 1937 by Fischer, Brunger, and Grieneisen, who electrolyzed a eutectic melt of potassium, lithium, and scandium chlorides at 700 to 800°C. Tungsten wire and a pool of molten zinc served as the electrodes in a graphite crucible. Pure scandium is now produced by reducing scandium fluoride with calcium metal. The production of the first pound of 99% pure scandium metal was announced in 1960. Scandium is a silver-white metal which develops a slightly yellowish or pinkish cast upon exposure to air. It is relatively soft, and resembles yttrium and the rare-earth metals more than it resembles aluminum or titanium. It is a very light metal and has a much higher melting point than aluminum, making it of interest to designers of spacecraft. Scandium is not attacked by a 1:1 mixture of conc. HNO_3 and 48% HF. Scandium reacts rapidly with many acids. Twenty-three isotopes and isomers of scandium are recognized. The metal is expensive, costing about $200/g with a purity of about 99.9%. About 20 kg of scandium (as Sc_2O_3) are now being used yearly in the U.S. to produce high-intensity lights, and the radioactive isotope ^{46}Sc is used as a tracing agent in refinery crackers for crude oil, etc. Scandium iodide added to mercury vapor lamps produces a highly efficient light source resembling sunlight, which is important for indoor or night-time color TV. Little is yet known about the toxicity of scandium; therefore, it should be handled with care.

Seaborgium — (Glenn T. Seaborg [1912–1999], American chemist and nuclear physicist). Sg; at. wt. [263]; at no. 106. The discovery of *Seaborgium*, Element 106, took place in 1974 almost simultaneously at the Lawrence-Berkeley Laboratory and at the Joint Institute for Nuclear Research at Dubna, Russia. The Berkeley Group, under direction of Ghiorso, used the Super-Heavy Ion Linear Accelerator (Super HILAC) as a source of heavy ^{18}O ions to bombard a 259-μg target of ^{249}Cf. This resulted in the production and positive identification of ^{263}106,

which decayed with a half-life of 0.9 ± 0.2 s by the emission of alpha particles as follows:

$$^{263}106 \xrightarrow{\alpha} {}^{259}104 \xrightarrow{\alpha} {}^{255}\text{No} \xrightarrow{\alpha}.$$

The Dubna Team, directed by Flerov and Organessian, produced heavy ions of ^{54}Cr with their 310-cm heavy-ion cyclotron to bombard ^{207}Pb and ^{208}Pb and found a product that decayed with a half-life of 7 ms. They assigned ^{259}106 to this isotope. It is now thought seven isotopes of *Seaborgium* have been identified. Two of the isotopes are believed to have half-lives of about 30 s. *Seaborgium* most likely would have properties resembling tungsten. The IUPAC adopted the name *Seaborgium* in August 1997. Normally the naming of an element is not given until after the death of the person for which the element is named; however, in this case, it was named while Dr. Seaborg was still alive.

Selenium — (Gr. *Selene*, moon), Se; at. wt. 78.96(3); at. no. 34; m.p. (gray) 221°C; b.p. (gray) 685°C; sp. gr. (gray) 4.79, (vitreous) 4.28; valence –2, +4, or +6. Discovered by Berzelius in 1817, who found it associated with tellurium, named for the earth. Selenium is found in a few rare minerals, such as *crooksite* and *clausthalite*. In years past it has been obtained from flue dusts remaining from processing copper sulfide ores, but the anode muds from electrolytic copper refineries now provide the source of most of the world's selenium. Selenium is recovered by roasting the muds with soda or sulfuric acid, or by smelting them with soda and niter. Selenium exists in several allotropic forms. Three are generally recognized, but as many as six have been claimed. Selenium can be prepared with either an amorphous or crystalline structure. The color of amorphous selenium is either red, in powder form, or black, in vitreous form. Crystalline monoclinic selenium is a deep red; crystalline hexagonal selenium, the most stable variety, is a metallic gray. Natural selenium contains six stable isotopes. Twenty-nine other isotopes and isomers have been characterized. The element is a member of the sulfur family and resembles sulfur both in its various forms and in its compounds. Selenium exhibits both photovoltaic action, where light is converted directly into electricity, and photoconductive action, where the electrical resistance decreases with increased illumination. These properties make selenium useful in the production of photocells and exposure meters for photographic use, as well as solar cells. Selenium is also able to convert a.c. electricity to d.c., and is extensively used in rectifiers. Below its melting point selenium is a p-type semiconductor and is finding many uses in electronic and solid-state applications. It is used in Xerography for reproducing and copying documents, letters, etc., but recently its use in this application has been decreasing in favor of certain organic compounds. It is used by the glass industry to decolorize glass and to make ruby-colored glasses and enamels. It is also used as a photographic toner, and as an additive to stainless steel. Elemental selenium has been said to be practically nontoxic and is considered to be an essential trace element; however, hydrogen selenide and other selenium compounds are extremely toxic, and resemble arsenic in their physiological reactions. Hydrogen selenide in a concentration of 1.5 ppm is intolerable to man. Selenium occurs in some soils in amounts sufficient to produce serious effects on animals feeding on plants, such as locoweed, grown in such soils. Selenium (99.5%) is priced at about $250/kg. It is also available in high-purity form at a cost of about $350/kg (99.999%).

Silicon — (L. *silex, silicis*, flint), Si; at. wt. 28.0855(3); at. no. 14; m.p. 1414°C; b.p. 3265°C; sp. gr. 2.33 (25°C); valence 4. Davy in 1800 thought silica to be a compound and not an element; later in 1811, Gay Lussac and Thenard probably prepared impure amorphous silicon by heating potassium with silicon tetrafluoride. Berzelius, generally credited with the discovery, in 1824 succeeded in preparing amorphous silicon by the same general method as used earlier, but he purified the product by removing the fluosilicates by repeated washings. Deville in 1854 first prepared crystalline silicon, the second allotropic form of the element. Silicon is present in the sun and stars and is a principal component of a class of meteorites known as "aerolites". It is also a component of *tektites*, a natural glass of uncertain origin. Natural silicon contains three isotopes. Twenty-four other radioactive isotopes are recognized. Silicon makes up 25.7% of the earth's crust, by weight, and is the second most abundant element, being exceeded only by oxygen. Silicon is not found free in nature, but occurs chiefly as the oxide and as silicates. *Sand, quartz, rock crystal, amethyst, agate, flint, jasper,* and *opal* are some of the forms in which the oxide appears. *Granite, hornblende, asbestos, feldspar, clay mica,* etc. are but a few of the numerous silicate minerals. Silicon is prepared commercially by heating silica and carbon in an electric furnace, using carbon electrodes. Several other methods can be used for preparing the element. Amorphous silicon can be prepared as a brown powder, which can be easily melted or vaporized. Crystalline silicon has a metallic luster and grayish color. The Czochralski process is commonly used to produce single crystals of silicon used for solid-state or semiconductor devices. Hyperpure silicon can be prepared by the thermal decomposition of ultra-pure trichlorosilane in a hydrogen atmosphere, and by a vacuum float zone process. This product can be doped with boron, gallium, phosphorus, or arsenic to produce silicon for use in transistors, solar cells, rectifiers, and other solid-state devices which are used extensively in the electronics and space-age industries. Hydrogenated amorphous silicon has shown promise in producing economical cells for converting solar energy into electricity. Silicon is a relatively inert element, but it is attacked by halogens and dilute alkali. Most acids except hydrofluoric, do not affect it. Silicones are important products of silicon. They may be prepared by hydrolyzing a silicon organic chloride, such as dimethyl silicon chloride. Hydrolysis and condensation of various substituted chlorosilanes can be used to produce a very great number of polymeric products, or silicones, ranging from liquids to hard, glasslike solids with many useful properties. Elemental silicon transmits more than 95% of all wavelengths of infrared, from 1.3 to 6.7 μm. Silicon is one of man's most useful elements. In the form of sand and clay it is used to make concrete and brick; it is a useful refractory material for high-temperature work, and in the form of silicates it is used in making enamels, pottery, etc. Silica, as sand, is a principal ingredient of glass, one of the most inexpensive of materials with excellent mechanical, optical, thermal, and electrical properties. Glass can be made in a very great variety of shapes, and is used as containers, window glass, insulators, and thousands of other uses. Silicon tetrachloride can be used to iridize glass. Silicon is important in plant and animal life. Diatoms in both fresh and salt water extract silica from the water to build up their cell walls. Silica is present in ashes of plants and in the human skeleton. Silicon is an important ingredient in steel; silicon carbide is one of the most important abrasives and has been used in lasers to produce coherent light of 4560 Å. A remark-

able material, first discovered in 1930, is *Aerogel,* developed and now used by NASA in their *Stardust* mission, which is expected to encounter Comet Wild 2 in 2004, returning cometary and interplanet dust to Earth in 2006. *Aerogel* is a highly insulative material that has the lowest density of any known solid. One form of *Aerogel* is 99.9% air and 0.1% SiO_2, by volume. It is 1000 times less dense than glass. It has been called "blue smoke" or "solid smoke". A block of *Aerogel* as large as a person may weigh less than a pound and yet support the weight of 1000 lbs (455 kg). This material is expected to trap cometary particles traveling at speeds of 32 km/sec. *Aerogel* is said to be non-toxic and non-inflammable. It has high thermal insulating qualities that could be used in home insulation. Its light weight may have aircraft applications. Regular grade silicon (99.5%) costs about $160/kg. Silicon (99.9999%) pure costs about $200/kg; hyperpure silicon is available at a higher cost. Miners, stonecutters, and other engaged in work where siliceous dust is breathed in large quantities often develop a serious lung disease known as *silicosis*.

Silver — (Anglo-Saxon, *Seolfor siolfur*), Ag (L. *argentum*), at. wt. 107.8682(2); at. no. 47; m.p. 961.78°C; b.p. 2162°C; sp. gr. 10.50 (20°C); valence 1, 2. Silver has been known since ancient times. It is mentioned in Genesis. Slag dumps in Asia Minor and on islands in the Aegean Sea indicate that man learned to separate silver from lead as early as 3000 B.C. Silver occurs native and in ores such as *argentite* (Ag_2S) and *horn silver* (AgCl); lead, lead-zinc, copper, gold, and copper-nickel ores are principal sources. Mexico, Canada, Peru, and the U.S. are the principal silver producers in the western hemisphere. Silver is also recovered during electrolytic refining of copper. Commercial fine silver contains at least 99.9% silver. Purities of 99.999+% are available commercially. Pure silver has a brilliant white metallic luster. It is a little harder than gold and is very ductile and malleable, being exceeded only by gold and perhaps palladium. Pure silver has the highest electrical and thermal conductivity of all metals, and possesses the lowest contact resistance. It is stable in pure air and water, but tarnishes when exposed to ozone, hydrogen sulfide, or air containing sulfur. The alloys of silver are important. Sterling silver is used for jewelry, silverware, etc. where appearance is paramount. This alloy contains 92.5% silver, the remainder being copper or some other metal. Silver is of utmost importance in photography, about 30% of the U.S. industrial consumption going into this application. It is used for dental alloys. Silver is used in making solder and brazing alloys, electrical contacts, and high capacity silver-zinc and silver-cadmium batteries. Silver paints are used for making printed circuits. It is used in mirror production and may be deposited on glass or metals by chemical deposition, electrodeposition, or by evaporation. When freshly deposited, it is the best reflector of visible light known, but is rapidly tarnishes and loses much of its reflectance. It is a poor reflector of ultraviolet. Silver fulminate ($Ag_2C_2N_2O_2$), a powerful explosive, is sometimes formed during the silvering process. Silver iodide is used in seeding clouds to produce rain. Silver chloride has interesting optical properties as it can be made transparent; it also is a cement for glass. Silver nitrate, or *lunar caustic*, the most important silver compound, is used extensively in photography. While silver itself is not considered to be toxic, most of its salts are poisonous. Natural silver contains two stable isotopes. Fifty-six other radioactive isotopes and isomers are known. Silver compounds can be absorbed in the circulatory system and reduced silver deposited in the various tissues of the body. A condition, known as *argyria*, results with a greyish pigmentation of the skin and mucous membranes. Silver has germicidal effects and kills many lower organisms effectively without harm to higher animals. Silver for centuries has been used traditionally for coinage by many countries of the world. In recent times, however, consumption of silver has at times greatly exceeded the output. In 1939, the price of silver was fixed by the U.S. Treasury at 71¢/troy oz., and at 90.5¢/troy oz. in 1946. In November 1961 the U.S. Treasury suspended sales of nonmonetized silver, and the price stabilized for a time at about $1.29, the melt-down value of silver U.S. coins. The Coinage Act of 1965 authorized a change in the metallic composition of the three U.S. subsidiary denominations to clad or composite type coins. This was the first change in U.S. coinage since the monetary system was established in 1792. Clad dimes and quarters are made of an outer layer of 75% Cu and 25% Ni bonded to a central core of pure Cu. The composition of the one- and five-cent pieces remains unchanged. One-cent coins are 95% Cu and 5% Zn. Five-cent coins are 75% Cu and 25% Ni. Old silver dollars are 90% Ag and 10% Cu. Earlier subsidiary coins of 90% Ag and 10% Cu officially were to circulate alongside the clad coins; however, in practice they have largely disappeared (Gresham's Law), as the value of the silver is now greater than their exchange value. Silver coins of other countries have largely been replaced with coins made of other metals. On June 24, 1968, the U.S. Government ceased to redeem U.S. Silver Certificates with silver. Since that time, the price of silver has fluctuated widely. As of January 2002, the price of silver was about $4.10/troy oz. (13¢/g); however the price has fluctuated considerably due to market instability. The price of silver in 2001 was only about four times the cost of the metal about 150 years ago. This has largely been caused by Central Banks disposing of some of their silver reserves and the development of more productive mines with better refining methods. Also, silver has been displaced by other metals or processes, such as digital photography.

Sodium — (English, *soda*; Medieval Latin, *sodanum,* headache remedy), Na (L. *natrium*); at. wt. 22.989770(2); at. no. 11; m.p. 97.80°C; b.p. 883°C; sp. gr. 0.971 (20°C); valence 1. Long recognized in compounds, sodium was first isolated by Davy in 1807 by electrolysis of caustic soda. Sodium is present in fair abundance in the sun and stars. The D lines of sodium are among the most prominent in the solar spectrum. Sodium is the sixth most abundant element on earth, comprising about 2.6% of the earth's crust; it is the most abundant of the alkali group of metals of which it is a member. The most common compound is sodium chloride, but it occurs in many other minerals, such as *soda niter, cryolite, amphibole, zeolite, sodalite,*etc. It is a very reactive element and is never found free in nature. It is now obtained commercially by the electrolysis of absolutely dry fused sodium chloride. This method is much cheaper than that of electrolyzing sodium hydroxide, as was used several years ago. Sodium is a soft, bright, silvery metal which floats on water, decomposing it with the evolution of hydrogen and the formation of the hydroxide. It may or may not ignite spontaneously on water, depending on the amount of oxide and metal exposed to the water. It normally does not ignite in air at temperatures below 115°C. Sodium should be handled with respect, as it can be dangerous when improperly handled. Metallic sodium is vital in the manufacture of sodamide and esters, and in the preparation of organic compounds. The metal may be used to improve the structure of certain alloys, to descale metal, to purify molten metals,

and as a heat transfer agent. An alloy of sodium with potassium, NaK, is also an important heat transfer agent. Sodium compounds are important to the paper, glass, soap, textile, petroleum, chemical, and metal industries. Soap is generally a sodium salt of certain fatty acids. The importance of common salt to animal nutrition has been recognized since prehistoric times. Among the many compounds that are of the greatest industrial importance are common salt (NaCl), soda ash (Na_2CO_3), baking soda ($NaHCO_3$), caustic soda (NaOH), Chile saltpeter ($NaNO_3$), di- and tri-sodium phosphates, sodium thiosulfate (hypo, $Na_2S_2O_3 \cdot 5H_2O$), and borax ($Na_2B_4O_7 \cdot 10H_2O$). Seventeen isotopes of sodium are recognized. Metallic sodium is priced at about $575/kg (99.95%). On a volume basis, it is the cheapest of all metals. Sodium metal should be handled with great care. It should be kept in an inert atmosphere and contact with water and other substances with which sodium reacts should be avoided.

Strontium — (*Strontian*, town in Scotland), Sr; at. wt. 87.62(1); at. no. 38; m.p. 777°C; b.p. 1382°C; sp. gr. 2.54; valence 2. Isolated by Davey by electrolysis in 1808; however, Adair Crawford in 1790 recognized a new mineral (strontianite) as differing from other barium minerals (baryta). Strontium is found chiefly as *celestite* ($SrSO_4$) and *strontianite* ($SrCO_3$). *Celestite* is found in Mexico, Turkey, Iran, Spain, Algeria, and in the U.K. The U.S. has no active *celestite* mines. The metal can be prepared by electrolysis of the fused chloride mixed with potassium chloride, or is made by reducing strontium oxide with aluminum in a vacuum at a temperature at which strontium distills off. Three allotropic forms of the metal exist, with transition points at 235 and 540°C. Strontium is softer than calcium and decomposes water more vigorously. It does not absorb nitrogen below 380°C. It should be kept under mineral oil to prevent oxidation. Freshly cut strontium has a silvery appearance, but rapidly turns a yellowish color with the formation of the oxide. The finely divided metal ignites spontaneously in air. Volatile strontium salts impart a beautiful crimson color to flames, and these salts are used in pyrotechnics and in the production of flares. Natural strontium is a mixture of four stable isotopes. Thirty-two other unstable isotopes and isomers are known to exist. Of greatest importance is ^{90}Sr with a half-life of 29 years. It is a product of nuclear fallout and presents a health problem. This isotope is one of the best long-lived high-energy beta emitters known, and is used in SNAP (Systems for Nuclear Auxiliary Power) devices. These devices hold promise for use in space vehicles, remote weather stations, navigational buoys, etc., where a lightweight, long-lived, nuclear-electric power source is needed. The major use for strontium at present is in producing glass for color television picture tubes. All color TV and cathode ray tubes sold in the U.S. are required by law to contain strontium in the face plate glass to block X-ray emission. Strontium also improves the brilliance of the glass and the quality of the picture. It has also found use in producing ferrite magnets and in refining zinc. Strontium titanate is an interesting optical material as it has an extremely high refractive index and an optical dispersion greater than that of diamond. It has been used as a gemstone, but it is very soft. It does not occur naturally. Strontium metal (99% pure) costs about $220/kg.

Sulfur — (Sanskrit, *sulvere*; L. *sulphurium*), S; at. wt. 32.066(6); at. no. 16; m.p. 115.21°C; b.p. 444.60°C; t_c 1041°C; sp. gr. (rhombic) 2.07, (monoclinic) 1.957 (20°C); valence 2, 4, or 6. Known to the ancients; referred to in Genesis as *brimstone*. Sulfur is found in meteorites. A dark area near the crater Aristarchus on the moon has been studied by R. W. Wood with ultraviolet light. This study suggests strongly that it is a sulfur deposit. Sulfur occurs native in the vicinity of volcanoes and hot springs. It is widely distributed in nature as *iron pyrites, galena, sphalerite, cinnabar, stibnite, gypsum, Epsom salts, celestite, barite,*etc. Sulfur is commercially recovered from wells sunk into the salt domes along the Gulf Coast of the U.S. It is obtained from these wells by the Frasch process, which forces heated water into the wells to melt the sulfur, which is then brought to the surface. Sulfur also occurs in natural gas and petroleum crudes and must be removed from these products. Formerly this was done chemically, which wasted the sulfur. New processes now permit recovery, and these sources promise to be very important. Large amounts of sulfur are being recovered from Alberta gas fields. Sulfur is a pale yellow, odorless, brittle solid, which is insoluble in water but soluble in carbon disulfide. In every state, whether gas, liquid or solid, elemental sulfur occurs in more than one allotropic form or modification; these present a confusing multitude of forms whose relations are not yet fully understood. Amorphous or "plastic" sulfur is obtained by fast cooling of the crystalline form. X-ray studies indicate that amorphous sulfur may have a helical structure with eight atoms per spiral. Crystalline sulfur seems to be made of rings, each containing eight sulfur atoms, which fit together to give a normal X-ray pattern. Twenty-one isotopes of sulfur are now recognized. Four occur in natural sulfur, none of which is radioactive. A finely divided form of sulfur, known as *flowers of sulfur*, is obtained by sublimation. Sulfur readily forms sulfides with many elements. Sulfur is a component of black gunpowder, and is used in the vulcanization of natural rubber and a fungicide. It is also used extensively is making phosphatic fertilizers. A tremendous tonnage is used to produce sulfuric acid, the most important manufactured chemical. It is used in making sulfite paper and other papers, as a fumigant, and in the bleaching of dried fruits. The element is a good electrical insulator. Organic compounds containing sulfur are very important. Calcium sulfate, ammonium sulfate, carbon disulfide, sulfur dioxide, and hydrogen sulfide are but a few of the many other important compounds of sulfur. Sulfur is essential to life. It is a minor constituent of fats, body fluids, and skeletal minerals. Carbon disulfide, hydrogen sulfide, and sulfur dioxide should be handled carefully. Hydrogen sulfide in small concentrations can be metabolized, but in higher concentrations it quickly can cause death by respiratory paralysis. It is insidious in that it quickly deadens the sense of smell. Sulfur dioxide is a dangerous component in atmospheric air pollution. In 1975, University of Pennsylvania scientists reported synthesis of polymeric sulfur nitride, which has the properties of a metal, although it contains no metal atoms. The material has unusual optical and electrical properties. Sulfur (99.999%) costs about $575/kg.

Tantalum — (Gr. *Tantalos*, mythological character, father of *Niobe*), Ta; at. wt. 180.9479(1); at. no. 73; m.p. 3017°C; b.p. 5458°C; sp. gr. 16.654; valence 2?, 3, 4?, or 5. Discovered in 1802 by Ekeberg, but many chemists thought niobium and tantalum were identical elements until Rose, in 1844, and Marignac, in1866, showed that niobic and tantalic acids were two different acids. The early investigators only isolated the impure metal. The first relatively pure ductile tantalum was produced by von Bolton in 1903. Tantalum occurs principally in the mineral *columbite-tantalite* (Fe, Mn)$(Nb, Ta)_2O_6$. Tantalum ores are found in Australia, Brazil, Rwanda, Zimbabwe, Congo-Kinshasa, Nigeria, and Canada. Separation

of tantalum from niobium requires several complicated steps. Several methods are used to commercially produce the element, including electrolysis of molten potassium fluorotantalate, reduction of potassium fluorotantalate with sodium, or reacting tantalum carbide with tantalum oxide. Thirty four isotopes and isomers of tantalum are known to exist. Natural tantalum contains two isotopes, one of which is radioactive with a very long half-life. Tantalum is a gray, heavy, and very hard metal. When pure, it is ductile and can be drawn into fine wire, which is used as a filament for evaporating metals such as aluminum. Tantalum is almost completely immune to chemical attack at temperatures below 150°C, and is attacked only by hydrofluoric acid, acidic solutions containing the fluoride ion, and free sulfur trioxide. Alkalis attack it only slowly. At high temperatures, tantalum becomes much more reactive. The element has a melting point exceeded only by tungsten and rhenium. Tantalum is used to make a variety of alloys with desirable properties such as high melting point, high strength, good ductility, etc. Scientists at Los Alamos have produced a tantalum carbide graphite composite material, which is said to be one of the hardest materials ever made. The compound has a melting point of 3738°C. Tantalum has good "gettering" ability at high temperatures, and tantalum oxide films are stable and have good rectifying and dielectric properties. Tantalum is used to make electrolytic capacitors and vacuum furnace parts, which account for about 60% of its use. The metal is also widely used to fabricate chemical process equipment, nuclear reactors, and aircraft and missile parts. Tantalum is completely immune to body liquids and is a nonirritating metal. It has, therefore, found wide use in making surgical appliances. Tantalum oxide is used to make special glass with high index of refraction for camera lenses. The metal has many other uses. The price of (99.9%) tantalum is about $2/g.

Technetium — (Gr. *technetos*, artificial), Tc; at. wt. (98); at. no. 43; m.p. 2157°C; b.p. 4265°C; sp. gr. 11.50 (calc.); valence 0, +2, +4, +5, +6, and +7. Element 43 was predicted on the basis of the periodic table, and was erroneously reported as having been discovered in 1925, at which time it was named *masurium*. The element was actually discovered by Perrier and Segre in Italy in 1937. It was found in a sample of molybdenum, which was bombarded by deuterons in the Berkeley cyclotron, and which E. Lawrence sent to these investigators. Technetium was the first element to be produced artificially. Since its discovery, searches for the element in terrestrial materials have been made without success. If it does exist, the concentration must be very small. Technetium has been found in the spectrum of S-, M-, and N-type stars, and its presence in stellar matter is leading to new theories of the production of heavy elements in the stars. Forty-three isotopes and isomers of technetium, with atomic masses ranging from 86 to 113, are known. ^{97}Tc has a half-life of 2.6×10^6 years. ^{98}Tc has a half-life of 4.2×10^6 years. The isomeric isotope ^{95m}Tc, with a half-life of 61 days, is useful for tracer work, as it produces energetic gamma rays. Technetium metal has been produced in kilogram quantities. The metal was first prepared by passing hydrogen gas at 1100°C over Tc_2S_7. It is now conveniently prepared by the reduction of ammonium pertechnetate with hydrogen. Technetium is a silvery-gray metal that tarnishes slowly in moist air. Until 1960, technetium was available only in small amounts and the price was as high as $2800/g. ^{99}Tc is now commercially available to holders of O.R.N.L. permits at a price of $83/g plus packing charges. ^{99}Tc is available at a cost of $1.56/μCi. The chemistry of technetium is said to be similar to that of rhenium. Technetium dissolves in nitric acid, aqua regia, and conc. sulfuric acid, but is not soluble in hydrochloric acid of any strength. The element is a remarkable corrosion inhibitor for steel. It is reported that mild carbon steels may be effectively protected by as little as 55 ppm of $KTcO_4$ in aerated distilled water at temperatures up to 250°C. This corrosion protection is limited to closed systems, since technetium is radioactive and must be confined. ^{99}Tc has a specific activity of 6.2×10^8 Bq/g. Activity of this level must not be allowed to spread. ^{99}Tc is a contamination hazard and should be handled in a glove box. The metal is an excellent superconductor at 11°K and below.

Tellurium — (L. *tellus,* earth), Te; at. wt. 127.60(3); at. no. 52; m.p. 449.51°C; b.p. 988°C; sp. gr. 6.24 (20°C); valence 2, 4, or 6. Discovered by Muller von Reichenstein in 1782; named by Klaproth, who isolated it in 1798. Tellurium is occasionally found native, but is more often found as the telluride of gold (*calaverite*), and combined with other metals. It is recovered commercially from the anode muds produced during the electrolytic refining of blister copper. The U.S., Canada, Peru, and Japan are the largest Free World producers of the element. Crystalline tellurium has a silvery-white appearance, and when pure exhibits a metallic luster. It is brittle and easily pulverized. Amorphous tellurium is formed by precipitating tellurium from a solution of telluric or tellurous acid. Whether this form is truly amorphous, or made of minute crystals, is open to question. Tellurium is a p-type semiconductor, and shows greater conductivity in certain directions, depending on alignment of the atoms. Its conductivity increases slightly with exposure to light. It can be doped with silver, copper, gold, tin, or other elements. In air, tellurium burns with a greenish-blue flame, forming the dioxide. Molten tellurium corrodes iron, copper, and stainless steel. Tellurium and its compounds are probably toxic and should be handled with care. Workmen exposed to as little as 0.01 mg/m^3 of air, or less, develop "tellurium breath," which has a garlic-like odor. Forty-two isotopes and isomers of tellurium are known, with atomic masses ranging from 106 to 138. Natural tellurium consists of eight isotopes, two of which are radioactive with very long half-lives. Tellurium improves the machinability of copper and stainless steel, and its addition to lead decreases the corrosive action of sulfuric acid on lead and improves its strength and hardness. Tellurium catalysts are used in the oxidation of organic compounds and are used in hydrogenation and halogenation reactions. Tellurium is also used in electronic and semi-conductor devices. It is also used as a basic ingredient in blasting caps, and is added to cast iron for chill control. Tellurium is used in ceramics. Bismuth telluride has been used in thermoelectric devices. Tellurium costs about 50¢/g, with a purity of about 99.5%. The metal with a purity of 99.9999% costs about $5/g.

Terbium — (*Ytterby*, village in Sweden), Tb; at. wt. 158.92534(2); at. no. 65; m.p. 1356°C; b.p. 3230°C; sp. gr. 8.230; valence 3, 4. Discovered by Mosander in 1843. Terbium is a member of the lanthanide or "rare earth" group of elements. It is found in *cerite, gadolinite*, and other minerals along with other rare earths. It is recovered commercially from *monazite* in which it is present to the extent of 0.03%, from *xenotime*, and from *euxenite*, a complex oxide containing 1% of more of terbia. Terbium has been isolated only in recent years with the development of ion-exchange techniques for separating the rare-earth elements. As with other rare earths, it can be produced

by reducing the anhydrous chloride or fluoride with calcium metal in a tantalum crucible. Calcium and tantalum impurities can be removed by vacuum remelting. Other methods of isolation are possible. Terbium is reasonably stable in air. It is a silver-gray metal, and is malleable, ductile, and soft enough to be cut with a knife. Two crystal modifications exist, with a transformation temperature of 1289°C. Forty-two isotopes and isomers are recognized. The oxide is a chocolate or dark maroon color. Sodium terbium borate is used as a laser material and emits coherent light at 0.546 μm. Terbium is used to dope calcium fluoride, calcium tungstate, and strontium molybdate, used in solid-state devices. The oxide has potential application as an activator for green phosphors used in color TV tubes. It can be used with ZrO_2 as a crystal stabilizer of fuel cells which operate at elevated temperature. Few other uses have been found. The element is priced at about $40/g (99.9%). Little is known of the toxicity of terbium. It should be handled with care as with other lanthanide elements.

Thallium — (Gr. *thallos*, a green shoot or twig), Tl; at. wt. 204.3833(2); at. no. 81; m.p. 304°C; b.p. 1473°C; sp. gr. 11.85 (20°C); valence 1, or 3. Thallium was discovered spectroscopically in 1861 by Crookes. The element was named after the beautiful green spectral line, which identified the element. The metal was isolated both by Crookes and Lamy in 1862 about the same time. Thallium occurs in *crooksite, lorandite*, and *hutchinsonite*. It is also present in *pyrites* and is recovered from the roasting of this ore in connection with the production of sulfuric acid. It is also obtained from the smelting of lead and zinc ores. Extraction is somewhat complex and depends on the source of the thallium. Manganese nodules, found on the ocean floor, contain thallium. When freshly exposed to air, thallium exhibits a metallic luster, but soon develops a bluish-gray tinge, resembling lead in appearance. A heavy oxide builds up on thallium if left in air, and in the presence of water the hydroxide is formed. The metal is very soft and malleable. It can be cut with a knife. Forty-seven isotopes of thallium, with atomic masses ranging from 179 to 210 are recognized. Natural thallium is a mixture of two isotopes. The element and its compounds are toxic and should be handled carefully. Contact of the metal with skin is dangerous, and when melting the metal adequate ventilation should be provided. Thallium is suspected of carcinogenic potential for man. Thallium sulfate has been widely employed as a rodenticide and ant killer. It is odorless and tasteless, giving no warning of its presence. Its use, however, has been prohibited in the U.S. since 1975 as a household insecticide and rodenticide. The electrical conductivity of thallium sulfide changes with exposure to infrared light, and this compound is used in photocells. Thallium bromide-iodide crystals have been used as infrared optical materials. Thallium has been used, with sulfur or selenium and arsenic, to produce low melting glasses which become fluid between 125 and 150°C. These glasses have properties at room temperatures similar to ordinary glasses and are said to be durable and insoluble in water. Thallium oxide has been used to produce glasses with a high index of refraction. Thallium has been used in treating ringworm and other skin infections; however, its use has been limited because of the narrow margin between toxicity and therapeutic benefits. A mercury-thallium alloy, which forms a eutectic at 8.5% thallium, is reported to freeze at −60°C, some 20° below the freezing point of mercury. Thallium metal (99.999%) costs about $2/g.

Thorium — (*Thor*, Scandinavian god of war), Th; at. wt. 232.0381(1); at. no. 90; m.p. 1750°C; b.p. 4788°C; sp. gr. 11.72; valence +2(?), +3(?), +4. Discovered by Berzelius in 1828. Thorium occurs in *thorite* ($ThSiO_4$) and in *thorianite* (ThO_2 + UO_2). Large deposits of thorium minerals have been reported in New England and elsewhere, but these have not yet been exploited. Thorium is now thought to be about three times as abundant as uranium and about as abundant as lead or molybdenum. The metal is a source of nuclear power. There is probably more energy available for use from thorium in the minerals of the earth's crust than from both uranium and fossil fuels. Any sizable demand for thorium as a nuclear fuel is still several years in the future. Work has been done in developing thorium cycle converter-reactor systems. Several prototypes, including the HTGR (high-temperature gas-cooled reactor) and MSRE (molten salt converter reactor experiment), have operated. While the HTGR reactors are efficient, they are not expected to become important commercially for many years because of certain operating difficulties. Thorium is recovered commercially from the mineral *monazite*, which contains from 3 to 9% ThO_2 along with rare-earth minerals. Much of the internal heat the earth produces has been attributed to thorium and uranium. Several methods are available for producing thorium metal: it can be obtained by reducing thorium oxide with calcium, by electrolysis of anhydrous thorium chloride in a fused mixture of sodium and potassium chlorides, by calcium reduction of thorium tetrachloride mixed with anhydrous zinc chloride, and by reduction of thorium tetrachloride with an alkali metal. Thorium was originally assigned a position in Group IV of the periodic table. Because of its atomic weight, valence, etc., it is now considered to be the second member of the *actinide* series of elements. When pure, thorium is a silvery-white metal which is air-stable and retains its luster for several months. When contaminated with the oxide, thorium slowly tarnishes in air, becoming gray and finally black. The physical properties of thorium are greatly influenced by the degree of contamination with the oxide. The purest specimens often contain several tenths of a percent of the oxide. High-purity thorium has been made. Pure thorium is soft, very ductile, and can be cold-rolled, swaged, and drawn. Thorium is dimorphic, changing at 1400°C from a cubic to a body-centered cubic structure. Thorium oxide has a melting point of 3300°C, which is the highest of all oxides. Only a few elements, such as tungsten, and a few compounds, such as tantalum carbide, have higher melting points. Thorium is slowly attacked by water, but does not dissolve readily in most common acids, except hydrochloric. Powdered thorium metal is often pyrophoric and should be carefully handled. When heated in air, thorium turnings ignite and burn brilliantly with a white light. The principal use of thorium has been in the preparation of the Welsbach mantle, used for portable gas lights. These mantles, consisting of thorium oxide with about 1% cerium oxide and other ingredients, glow with a dazzling light when heated in a gas flame. Thorium is an important alloying element in magnesium, imparting high strength and creep resistance at elevated temperatures. Because thorium has a low work-function and high electron emission, it is used to coat tungsten wire used in electronic equipment. The oxide is also used to control the grain size of tungsten used for electric lamps; it is also used for high-temperature laboratory crucibles. Glasses containing thorium oxide have a high refractive index and low dispersion. Consequently, they find application in high quality lenses for cameras and scientific instruments. Thorium oxide

has also found use as a catalyst in the conversion of ammonia to nitric acid, in petroleum cracking, and in producing sulfuric acid. Thorium has not found many uses due to its radioactive nature and its handling and disposal problems. Thirty isotopes of thorium are known with atomic masses ranging from 210 to 237. All are unstable. ^{232}Th occurs naturally and has a half-life of 1.4×10^{10} years. It is an alpha emitter. ^{232}Th goes through six alpha and four beta decay steps before becoming the stable isotope ^{208}Pb. ^{232}Th is sufficiently radioactive to expose a photographic plate in a few hours. Thorium disintegrates with the production of "thoron" (^{220}Rn), which is an alpha emitter and presents a radiation hazard. Good ventilation of areas where thorium is stored or handled is therefore essential. Thorium metal (99.8%) costs about $25/g.

Thulium — (*Thule*, the earliest name for Scandinavia), Tm; at. wt. 168.93421(3); at. no. 69; m.p. 1545°C; b.p. 1950°C; sp. gr. 9.321 (25°C); valence 3. Discovered in 1879 by Cleve. Thulium occurs in small quantities along with other rare earths in a number of minerals. It is obtained commercially from *monazite*, which contains about 0.007% of the element. Thulium is the least abundant of the rare earth elements, but with new sources recently discovered, it is now considered to be about as rare as silver, gold, or cadmium. Ion-exchange and solvent extraction techniques have recently permitted much easier separation of the rare earths, with much lower costs. Only a few years ago, thulium metal was not obtainable at any cost; in 1996 the oxide cost $20/g. Thulium metal powder now costs $70/g (99.9%). Thulium can be isolated by reduction of the oxide with lanthanum metal or by calcium reduction of the anhydrous fluoride. The pure metal has a bright, silvery luster. It is reasonably stable in air, but the metal should be protected from moisture in a closed container. The element is silver-gray, soft, malleable, and ductile, and can be cut with a knife. Forty-one isotopes and isomers are known, with atomic masses ranging from 146 to 176. Natural thulium, which is 100% ^{169}Tm, is stable. Because of the relatively high price of the metal, thulium has not yet found many practical applications. ^{169}Tm bombarded in a nuclear reactor can be used as a radiation source in portable X-ray equipment. ^{171}Tm is potentially useful as an energy source. Natural thulium also has possible use in *ferrites* (ceramic magnetic materials) used in microwave equipment. As with other lanthanides, thulium has a low-to-moderate acute toxic rating. It should be handled with care.

Tin — (Anglo-Saxon, *tin*), Sn (L. *stannum*); at. wt. 118.710(7); at. no. 50; m.p. 231.93°C; b.p. 2602°C; sp. gr. (gray) 5.75, (white) 7.31; valence 2, 4. Known to the ancients. Tin is found chiefly in *cassiterite* (SnO_2). Most of the world's supply comes from China, Indonesia, Peru, Brazil, and Bolivia. The U.S. produces almost none, although occurrences have been found in Alaska and Colorado. Tin is obtained by reducing the ore with coal in a reverberatory furnace. Ordinary tin is composed of ten stable isotopes; thirty-six unstable isotopes and isomers are also known. Ordinary tin is a silver-white metal, is malleable, somewhat ductile, and has a highly crystalline structure. Due to the breaking of these crystals, a "tin cry" is heard when a bar is bent. The element has two allotropic forms at normal pressure. On warming, gray, or α tin, with a cubic structure, changes at 13.2°C into white, or β tin, the ordinary form of the metal. White tin has a tetragonal structure. When tin is cooled below 13.2°C, it changes slowly from white to gray. This change is affected by impurities such as aluminum and zinc, and can be prevented by small additions of antimony or bismuth. This change from the α to β form is called the tin pest. Tin-lead alloys are used to make organ pipes. There are few if any uses for gray tin. Tin takes a high polish and is used to coat other metals to prevent corrosion or other chemical action. Such tin plate over steel is used in the so-called tin can for preserving food. Alloys of tin are very important. Soft solder, type metal, fusible metal, pewter, bronze, bell metal, Babbitt metal, White metal, die casting alloy, and phosphor bronze are some of the important alloys using tin. Tin resists distilled sea and soft tap water, but is attacked by strong acids, alkalis, and acid salts. Oxygen in solution accelerates the attack. When heated in air, tin forms SnO_2, which is feebly acid, forming stannate salts with basic oxides. The most important salt is the chloride ($SnCl_2 \cdot H_2O$), which is used as a reducing agent and as a mordant in calico printing. Tin salts sprayed onto glass are used to produce electrically conductive coatings. These have been used for panel lighting and for frost-free windshields. Most window glass is now made by floating molten glass on molten tin (float glass) to produce a flat surface (Pilkington process). Of recent interest is a crystalline tin-niobium alloy that is superconductive at very low temperatures. This promises to be important in the construction of superconductive magnets that generate enormous field strengths but use practically no power. Such magnets, made of tin-niobium wire, weigh but a few pounds and produce magnetic fields that, when started with a small battery, are comparable to that of a 100 ton electromagnet operated continuously with a large power supply. The small amount of tin found in canned foods is quite harmless. The agreed limit of tin content in U.S. foods is 300 mg/kg. The trialkyl and triaryl tin compounds are used as biocides and must be handled carefully. Over the past 25 years the price of commercial tin has varied from 50¢/lb ($1.10/kg) to its present price of about $6/kg in January 2002. Tin (99.99% pure) costs about $260/kg.

Titanium — (L. *Titans*, the first sons of the Earth, myth.), Ti; at. wt. 47.867(1); at. no. 22; m.p. 1668°C; b.p. 3287°C; sp. gr. 4.54; valence 2, 3, or 4. Discovered by Gregor in 1791; named by Klaproth in 1795. Impure titanium was prepared by Nilson and Pettersson in 1887; however, the pure metal (99.9%) was not made until 1910 by Hunter by heating $TiCl_4$ with sodium in a steel bomb. Titanium is present in meteorites and in the sun. Rocks obtained during the Apollo 17 lunar mission showed presence of 12.1% TiO_2. Analyses of rocks obtained during earlier Apollo missions show lower percentages. Titanium oxide bands are prominent in the spectra of M-type stars. The element is the ninth most abundant in the crust of the earth. Titanium is almost always present in igneous rocks and in the sediments derived from them. It occurs in the minerals *rutile, ilmenite,* and *sphene*, and is present in titanates and in many iron ores. Deposits of ilmenite and rutile are found in Florida, California, Tennessee, and New York. Australia, Norway, Malaysia, India, and China are also large suppliers of titanium minerals. Titanium is present in the ash of coal, in plants, and in the human body. The metal was a laboratory curiosity until Kroll, in 1946, showed that titanium could be produced commercially by reducing titanium tetrachloride with magnesium. This method is largely used for producing the metal today. The metal can be purified by decomposing the iodide. Titanium, when pure, is a lustrous, white metal. It has a low density, good strength, is easily fabricated, and has excellent corrosion resistance. It is ductile only when it is free of oxygen. The metal burns in air and is the only element that burns in nitrogen. Titanium is resistant to dilute sulfuric and

hydrochloric acid, most organic acids, moist chlorine gas, and chloride solutions. Natural titanium consists of five isotopes with atomic masses from 46 to 50. All are stable. Eighteen other unstable isotopes are known. The metal is dimorphic. The hexagonal α form changes to the cubic β form very slowly at about 880°C. The metal combines with oxygen at red heat, and with chlorine at 550°C. Titanium is important as an alloying agent with aluminum, molybdenum, manganese, iron, and other metals. Alloys of titanium are principally used for aircraft and missiles where lightweight strength and ability to withstand extremes of temperature are important. Titanium is as strong as steel, but 45% lighter. It is 60% heavier than aluminum, but twice as strong. Titanium has potential use in desalination plants for converting sea water into fresh water. The metal has excellent resistance to sea water and is used for propeller shafts, rigging, and other parts of ships exposed to salt water. A titanium anode coated with platinum has been used to provide cathodic protection from corrosion by salt water. Titanium metal is considered to be physiologically inert; however, titanium powder may be a carcinogenic hazard. When pure, titanium dioxide is relatively clear and has an extremely high index of refraction with an optical dispersion higher than diamond. It is produced artificially for use as a gemstone, but it is relatively soft. Star sapphires and rubies exhibit their asterism as a result of the presence of TiO_2. Titanium dioxide is extensively used for both house paint and artist's paint, as it is permanent and has good covering power. Titanium oxide pigment accounts for the largest use of the element. Titanium paint is an excellent reflector of infrared, and is extensively used in solar observatories where heat causes poor seeing conditions. Titanium tetrachloride is used to iridize glass. This compound fumes strongly in air and has been used to produce smoke screens. The price of titanium metal (99.9%) is about $1100/kg.

Tungsten — (Swedish, *tung sten*, heavy stone); also known as *wolfram* (from *wolframite*, said to be named from *wolf rahm* or *spumi lupi*, because the ore interfered with the smelting of tin and was supposed to devour the tin), W; at. wt. 183.84(1); at. no. 74; m.p. 3422°C; b.p. 5555°C; sp. gr. 19.3 (20°C); valence 2, 3, 4, 5, or 6. In 1779 Peter Woulfe examined the mineral now known as *wolframite* and concluded it must contain a new substance. Scheele, in 1781, found that a new acid could be made from *tung sten* (a name first applied about 1758 to a mineral now known as *scheelite*). Scheele and Berman suggested the possibility of obtaining a new metal by reducing this acid. The de Elhuyar brothers found an acid in *wolframite* in 1783 that was identical to the acid of *tungsten*(tungstic acid) of Scheele, and in that year they succeeded in obtaining the element by reduction of this acid with charcoal. Tungsten occurs in *wolframite*, (Fe, Mn)WO_4; *scheelite*, $CaWO_4$; *huebnerite*, $MnWO_4$; and *ferberite*, $FeWO_4$. Important deposits of tungsten occur in California, Colorado, Bolivia, Russia, and Portugal. China is reported to have about 75% of the world's tungsten resources. Natural tungsten contains five stable isotopes. Thirty two other unstable isotopes and isomers are recognized. The metal is obtained commercially by reducing tungsten oxide with hydrogen or carbon. Pure tungsten is a steel-gray to tin-white metal. Very pure tungsten can be cut with a hacksaw, and can be forged, spun, drawn, and extruded. The impure metal is brittle and can be worked only with difficulty. Tungsten has the highest melting point of all metals, and at temperatures over 1650°C has the highest tensile strength. The metal oxidizes in air and must be protected at elevated temperatures. It has excellent corrosion resistance and is attacked only slightly by most mineral acids. The thermal expansion is about the same as borosilicate glass, which makes the metal useful for glass-to-metal seals. Tungsten and its alloys are used extensively for filaments for electric lamps, electron and television tubes, and for metal evaporation work; for electrical contact points for automobile distributors; X-ray targets; windings and heating elements for electrical furnaces; and for numerous spacecraft and high-temperature applications. High-speed tool steels, Hastelloy®, Stellite®, and many other alloys contain tungsten. Tungsten carbide is of great importance to the metal-working, mining, and petroleum industries.Calcium and magnesium tungstates are widely used in fluorescent lighting; other salts of tungsten are used in the chemical and tanning industries. Tungsten disulfide is a dry, high-temperature lubricant, stable to 500°C. Tungsten bronzes and other tungsten compounds are used in paints. Zirconium tungstate has found recent applications (see under Zirconium). Tungsten powder (99.999%) costs about $2900/kg.

Uranium — (Planet *Uranus*), U; at. wt. 238.0289(1); at. no. 92; m.p. 1135°C; b.p. 4131°C; sp. gr. ~18.95; valence 2, 3, 4, 5, or 6. Yellow-colored glass, containing more than 1% uranium oxide and dating back to 79 A.D., has been found near Naples, Italy. Klaproth recognized an unknown element in *pitchblende* and attempted to isolate the metal in 1789. The metal apparently was first isolated in 1841 by Peligot, who reduced the anhydrous chloride with potassium. Uranium is not as rare as it was once thought. It is now considered to be more plentiful than mercury, antimony, silver, or cadmium, and is about as abundant as molybdenum or arsenic. It occurs in numerous minerals such as *pitchblende, uraninite, carnotite, autunite, uranophane, davidite,* and *tobernite*. It is also found in *phosphate rock, lignite, monazite sands*, and can be recovered commercially from these sources. Large deposits of uranium ore occur in Utah, Colorado, New Mexico, Canada, and elsewhere. Uranium can be made by reducing uranium halides with alkali or alkaline earth metals or by reducing uranium oxides by calcium, aluminum, or carbon at high temperatures. The metal can also be produced by electrolysis of KUF_5 or UF_4, dissolved in a molten mixture of $CaCl_2$ and NaCl. High-purity uranium can be prepared by the thermal decomposition of uranium halides on a hot filament. Uranium exhibits three crystallographic modifications as follows:

$$\alpha \xrightarrow{688^\circ C} \beta \xrightarrow{776^\circ C} \gamma$$

Uranium is a heavy, silvery-white metal which is pyrophoric when finely divided. It is a little softer than steel, and is attacked by cold water in a finely divided state. It is malleable, ductile, and slightly paramagnetic. In air, the metal becomes coated with a layer of oxide. Acids dissolve the metal, but it is unaffected by alkalis. Uranium has twenty three isotopes, one of which is an isomer and all of which are radioactive. Naturally occurring uranium contains 99.2745% by weight ^{238}U, 0.720% ^{235}U, and 0.0055% ^{234}U. Studies show that the percentage weight of ^{235}U in natural uranium varies by as much as 0.1%, depending on the source. The U.S.D.O.E. has adopted the value of 0.711 as being their "official" percentage of ^{235}U in natural uranium. Natural uranium is sufficiently radioactive to expose a photographic plate in an hour or so. Much of the internal heat of the earth is thought to be attributable to the presence of uranium and thorium. ^{238}U with a half-life of

4.46×10^9 years, has been used to estimate the age of igneous rocks. The origin of uranium, the highest member of the naturally occurring elements — except perhaps for traces of neptunium or plutonium — is not clearly understood, although it has been thought that uranium might be a decay product of elements of higher atomic weight, which may have once been present on earth or elsewhere in the universe. These original elements may have been formed as a result of a primordial "creation," known as "the big bang," in a supernova, or in some other stellar processes. The fact that recent studies show that most trans-uranic elements are extremely rare with very short half-lives indicates that it may be necessary to find some alternative explanation for the very large quantities of radioactive uranium we find on earth. Studies of meteorites from other parts of the solar system show a relatively low radioactive content, compared to terrestrial rocks. Uranium is of great importance as a nuclear fuel. ^{238}U can be converted into fissionable plutonium by the following reactions:

$$^{238}U(n,\gamma) \rightarrow {}^{239}U \xrightarrow{\beta} {}^{239}Np \xrightarrow{\beta} {}^{239}Pu$$

This nuclear conversion can be brought about in "breeder" reactors where it is possible to produce more new fissionable material than the fissionable material used in maintaining the chain reaction. ^{235}U is of even greater importance, for it is the key to the utilization of uranium. ^{235}U, while occurring in natural uranium to the extent of only 0.72%, is so fissionable with slow neutrons that a self-sustaining fission chain reaction can be made to occur in a reactor constructed from natural uranium and a suitable moderator, such as heavy water or graphite, alone. ^{235}U can be concentrated by gaseous diffusion and other physical processes, if desired, and used directly as a nuclear fuel, instead of natural uranium, or used as an explosive. Natural uranium, slightly enriched with ^{235}U by a small percentage, is used to fuel nuclear power reactors for the generation of electricity. Natural thorium can be irradiated with neutrons as follows to produce the important isotope ^{233}U.

$$^{232}Th(n,\gamma) \rightarrow {}^{233}Th \xrightarrow{\beta} {}^{233}Pa \xrightarrow{\beta} {}^{233}U$$

While thorium itself is not fissionable, ^{233}U is, and in this way may be used as a nuclear fuel. One pound of completely fissioned uranium has the fuel value of over 1500 tons of coal. The uses of nuclear fuels to generate electrical power, to make isotopes for peaceful purposes, and to make explosives are well known. The estimated world-wide production of the 437 nuclear power reactors in operation in 1998 amounted to about 352,000 Megawatt hours. In 1998 the U.S. had about 107 commercial reactors with an output of about 100,000 Megawatt-hours. Some nuclear-powered electric generating plants have recently been closed because of safety concerns. There are also serious problems with nuclear waste disposal that have not been completely resolved. Uranium in the U.S.A. is controlled by the U.S. Nuclear Regulatory Commission, under the Department of Energy. Uses are being found for the large quantities of "depleted" uranium, now available, where uranium-235 has been lowered to about 0.2%. Depleted uranium has been used for inertial guidance devices, gyrocompasses, counterweights for aircraft control surfaces, ballast for missile reentry vehicles, and as a shielding material for tanks, etc. Concerns, however, have been raised over its low radioactive properties. Uranium metal is used for X-ray targets for production of high-energy X-rays. The nitrate has been used as photographic toner, and the acetate is used in analytical chemistry. Crystals of uranium nitrate are triboluminescent. Uranium salts have also been used for producing yellow "vaseline" glass and glazes. Uranium and its compounds are highly toxic, both from a chemical and radiological standpoint. Finely divided uranium metal, being pyrophoric, presents a fire hazard. The maximum permissible total body burden of natural uranium (based on radiotoxicity) is 0.2 μCi for soluble compounds. Recently, the natural presence of uranium and thorium in many soils has become of concern to homeowners because of the generation of radon and its daughters (see under Radon). Uranium metal is available commercially at a cost of about $6/g (99.7%) in air-tight glass under argon.

Unnilnilium etc. — See under the opening paragraphs of this article and also under Elements 110 to 118.

Vanadium — (Scandinavian goddess, *Vanadis*), V; at. wt. 50.9415(1); at. no. 23; m.p. 1910°C; b.p. 3407°C; sp. gr. 6.11 (18.7°C); valence 2, 3, 4, or 5. Vanadium was first discovered by del Rio in 1801. Unfortunately, a French chemist incorrectly declared del Rio's new element was only impure chromium; del Rio thought himself to be mistaken and accepted the French chemist's statement. The element was rediscovered in 1830 by Sefstrom, who named the element in honor of the Scandinavian goddess *Vanadis* because of its beautiful multicolored compounds. It was isolated in nearly pure form by Roscoe, in 1867, who reduced the chloride with hydrogen. Vanadium of 99.3 to 99.8% purity was not produced until 1927. Vanadium is found in about 65 different minerals among which are *carnotite, roscoelite, vanadinite,* and *patronite* important sources of the metal. Vanadium is also found in phosphate rock and certain iron ores, and is present in some crude oils in the form of organic complexes. It is also found in small percentages in meteorites. Commercial production from petroleum ash holds promise as an important source of the element. China, South Africa, and Russia supply much of the world's vanadium ores. High-purity ductile vanadium can be obtained by reduction of vanadium trichloride with magnesium or with magnesium-sodium mixtures. Much of the vanadium metal being produced is now made by calcium reduction of V_2O_5 in a pressure vessel, an adaption of a process developed by McKechnie and Seybolt. Natural vanadium is a mixture of two isotopes, ^{50}V (0.25%) and ^{51}V (99.75%). ^{50}V is slightly radioactive, having a long half-life. Twenty other unstable isotopes are recognized. Pure vanadium is a bright white metal, and is soft and ductile. It has good corrosion resistance to alkalis, sulfuric and hydrochloric acid, and salt water, but the metal oxidizes readily above 660°C. The metal has good structural strength and a low fission neutron cross section, making it useful in nuclear applications. Vanadium is used in producing rust resistant, spring, and highspeed tool steels. It is an important carbide stabilizer in making steels. About 80% of the vanadium now produced is used as ferrovanadium or as a steel additive. Vanadium foil is used as a bonding agent in cladding titanium to steel. Vanadium pentoxide is used in ceramics and as a catalyst. It is also used in producing a superconductive magnet with a field of 175,000 gauss. Vanadium and its compounds are toxic and should be handled with care. Ductile vanadium is commercially available. Vanadium metal (99.7%) costs about $3/g.

Wolfram — see Tungsten.

Xenon — (Gr. *xenon*, stranger), Xe; at. wt. 131.29(2); at. no. 54; m.p. –111.79°C; b.p. –108.12°C; t_c 16.62°C; density (gas) 5.887 ± 0.009 g/l, sp. gr (liquid) 3.52 (–109°C); valence usually 0. Discovered by Ramsay and Travers in 1898 in the residue left after evaporating liquid air components. Xenon is a member of the so-called noble or "inert" gases. It is present in the atmosphere to the extent of about one part in twenty million. Xenon is present in the Martian atmosphere to the extent of 0.08 ppm. The element is found in the gases evolved from certain mineral springs, and is commercially obtained by extraction from liquid air. Natural xenon is composed of nine stable isotopes. In addition to these, thirty five unstable isotopes and isomers have been characterized. Before 1962, it had generally been assumed that xenon and other noble gases were unable to form compounds. Evidence has been mounting in the past few years that xenon, as well as other members of the zero valence elements, do form compounds. Among the "compounds" of xenon now reported are xenon hydrate, sodium perxenate, xenon deuterate, difluoride, tetrafluoride, hexafluoride, and $XePtF_6$ and $XeRhF_6$. Xenon trioxide, which is highly explosive, has been prepared. More than 80 xenon compounds have been made with xenon chemically bonded to fluorine and oxygen. Some xenon compounds are colored. Metallic xenon has been produced, using several hundred kilobars of pressure. Xenon in a vacuum tube produces a beautiful blue glow when excited by an electrical discharge. The gas is used in making electron tubes, stroboscopic lamps, bactericidal lamps, and lamps used to excite ruby lasers for generating coherent light. Xenon is used in the atomic energy field in bubble chambers, probes, and other applications where its high molecular weight is of value. The perxenates are used in analytical chemistry as oxidizing agents. ^{133}Xe and ^{135}Xe are produced by neutron irradiation in air cooled nuclear reactors. ^{133}Xe has useful applications as a radioisotope. The element is available in sealed glass containers for about $20/l of gas at standard pressure. Xenon is not toxic, but its compounds are highly toxic because of their strong oxidizing characteristics.

Ytterbium — (*Ytterby*, village in Sweden), Yb; at. wt. 173.04(3); at. no. 70; m.p. 819°C; b.p. 1196°C; sp. gr (α) 6.903 (β) 6.966; valence 2, 3. Marignac in 1878 discovered a new component, which he called *ytterbia*, in the earth then known as *erbia*. In 1907, Urbain separated ytterbia into two components, which he called *neoytterbia* and *lutecia*. The elements in these earths are now known as *ytterbium* and *lutetium*, respectively. These elements are identical with *aldebaranium* and *cassiopeium*, discovered independently and at about the same time by von Welsbach. Ytterbium occurs along with other rare earths in a number of rare minerals. It is commercially recovered principally from *monazite sand*, which contains about 0.03%. Ion-exchange and solvent extraction techniques developed in recent years have greatly simplified the separation of the rare earths from one another. The element was first prepared by Klemm and Bonner in 1937 by reducing ytterbium trichloride with potassium. Their metal was mixed, however, with KCl. Daane, Dennison, and Spedding prepared a much purer form in 1953 from which the chemical and physical properties of the element could be determined. Ytterbium has a bright silvery luster, is soft, malleable, and quite ductile. While the element is fairly stable, it should be kept in closed containers to protect it from air and moisture. Ytterbium is readily attacked and dissolved by dilute and concentrated mineral acids and reacts slowly with water. Ytterbium has three allotropic forms with transformation points at –13° and 795°C. The beta form is a room-temperature, face-centered, cubic modification, while the high-temperature gamma form is a body-centered cubic form. Another body-centered cubic phase has recently been found to be stable at high pressures at room temperatures. The beta form ordinarily has metallic-type conductivity, but becomes a semiconductor when the pressure is increased above 16,000 atm. The electrical resistance increases tenfold as the pressure is increased to 39,000 atm and drops to about 80% of its standard temperature-pressure resistivity at a pressure of 40,000 atm. Natural ytterbium is a mixture of seven stable isotopes. Twenty six other unstable isotopes and isomers are known. Ytterbium metal has possible use in improving the grain refinement, strength, and other mechanical properties of stainless steel. One isotope is reported to have been used as a radiation source as a substitute for a portable X-ray machine where electricity is unavailable. Few other uses have been found. Ytterbium metal is available with a purity of about 99.9% for about $10/g. Ytterbium has a low acute toxic rating, but may present a carcinogenic hazard.

Yttrium — (*Ytterby*, village in Sweden near Vauxholm), Y; at. wt. 88.90585(2); at. no. 39; m.p. 1522°C; b.p. 3345°C; sp. gr. 4.469 (25°C); valence 3. *Yttria*, which is an earth containing yttrium, was discovered by Gadolin in 1794. *Ytterby* is the site of a quarry which yielded many unusually minerals containing rare earths and other elements. This small town, near Stockholm, bears the honor of giving names to *erbium, terbium*, and *ytterbium* as well as *yttrium*. In 1843 Mosander showed that yttria could be resolved into the oxides (or earths) of three elements. The name yttria was reserved for the most basic one; the others were named *erbia* and *terbia*. Yttrium occurs in nearly all of the rare-earth minerals. Analysis of lunar rock samples obtained during the Apollo missions show a relatively high yttrium content. It is recovered commercially from *monazite sand*, which contains about 3%, and from *bastnasite*, which contains about 0.2%. Wohler obtained the impure element in 1828 by reduction of the anhydrous chloride with potassium. The metal is now produced commercially by reduction of the fluoride with calcium metal. It can also be prepared by other techniques. Yttrium has a silver-metallic luster and is relatively stable in air. Turnings of the metal, however, ignite in air if their temperature exceeds 400°C, and finely divided yttrium is very unstable in air. Yttrium oxide is one of the most important compounds of yttrium and accounts for the largest use. It is widely used in making YVO_4 europium, and Y_2O_3 europium phosphors to give the red color in color television tubes. Many hundreds of thousands of pounds are now used in this application. Yttrium oxide also is used to produce yttrium-iron-garnets, which are very effective microwave filters. Yttrium iron, aluminum, and gadolinium garnets, with formulas such as $Y_3Fe_5O_{12}$ and $Y_3Al_5O_{12}$, have interesting magnetic properties. Yttrium iron garnet is also exceptionally efficient as both a transmitter and transducer of acoustic energy. Yttrium aluminum garnet, with a hardness of 8.5, is also finding use as a gemstone (simulated diamond). Small amounts of yttrium (0.1 to 0.2%) can be used to reduce the grain size in chromium, molybdenum, zirconium, and titanium, and to increase strength of aluminum and magnesium alloys. Alloys with other useful properties can be obtained by using yttrium as an additive. The metal can be used as a deoxidizer for vanadium and other nonferrous metals. The metal has a low cross section for nuclear capture. ^{90}Y, one of the isotopes of yttrium, exists in equilibrium with its parent ^{90}Sr, a product of atomic explosions. Yttrium has been considered for use as a nodulizer

for producing nodular cast iron, in which the graphite forms compact nodules instead of the usual flakes. Such iron has increased ductility. Yttrium is also finding application in laser systems and as a catalyst for ethylene polymerization. It has also potential use in ceramic and glass formulas, as the oxide has a high melting point and imparts shock resistance and low expansion characteristics to glass. Natural yttrium contains but one isotope, ^{89}Y. Forty-three other unstable isotopes and isomers have been characterized. Yttrium metal of 99.9% purity is commercially available at a cost of about $5/g.

Zinc — (Ger. *Zink*, of obscure origin), Zn; at. wt. 65.39(2); at. no. 30; m.p. 419.53°C; b.p. 907°C; sp. gr. 7.133 (25°C); valence 2. Centuries before zinc was recognized as a distinct element, zinc ores were used for making brass. Tubal-Cain, seven generations from Adam, is mentioned as being an "instructor in every artificer in brass and iron." An alloy containing 87% zinc has been found in prehistoric ruins in Transylvania. Metallic zinc was produced in the 13th century A.D. in India by reducing calamine with organic substances such as wool. The metal was rediscovered in Europe by Marggraf in 1746, who showed that it could be obtained by reducing *calamine* with charcoal. The principal ores of zinc are *sphalerite* or *blende* (sulfide), *smithsonite* (carbonate), *calamine* (silicate), and *franklinite* (zinc, manganese, iron oxide). Canada, Japan, Belgium, Germany, and The Netherlands are suppliers of zinc ores. Zinc is also mined in Alaska, Tennessee, Missouri, and elsewhere in the U.S. Zinc can be obtained by roasting its ores to form the oxide and by reduction of the oxide with coal or carbon, with subsequent distillation of the metal. Other methods of extraction are possible. Naturally occurring zinc contains five stable isotopes. Twenty-five other unstable isotopes and isomers are recognized. Zinc is a bluish-white, lustrous metal. It is brittle at ordinary temperatures but malleable at 100 to 150°C. It is a fair conductor of electricity, and burns in air at high red heat with evolution of white clouds of the oxide. The metal is employed to form numerous alloys with other metals. Brass, nickel silver, typewriter metal, commercial bronze, spring brass, German silver, soft solder, and aluminum solder are some of the more important alloys. Large quantities of zinc are used to produce die castings, used extensively by the automotive, electrical, and hardware industries. An alloy called *Prestal*™, consisting of 78% zinc and 22% aluminum is reported to be almost as strong as steel but as easy to mold as plastic. It is said to be so plastic that it can be molded into form by relatively inexpensive die casts made of ceramics and cement. It exhibits superplasticity. Zinc is also extensively used to galvanize other metals such as iron to prevent corrosion. Neither zinc nor zirconium is ferromagnetic; but $ZrZn_2$ exhibits ferromagnetism at temperatures below 35 K. Zinc oxide is a unique and very useful material to modern civilization. It is widely used in the manufacture of paints, rubber products, cosmetics, pharmaceuticals, floor coverings, plastics, printing inks, soap, storage batteries, textiles, electrical equipment, and other products. It has unusual electrical, thermal, optical, and solid-state properties that have not yet been fully investigated. Lithopone, a mixture of zinc sulfide and barium sulfate, is an important pigment. Zinc sulfide is used in making luminous dials, X-ray and TV screens, and fluorescent lights. The chloride and chromate are also important compounds. Zinc is an essential element in the growth of human beings and animals. Tests show that zinc-deficient animals require 50% more food to gain the same weight as an animal supplied with sufficient zinc. Zinc is not considered to be toxic, but when freshly formed ZnO is inhaled a disorder known as the *oxide shakes* or *zinc chills* sometimes occurs. It is recommended that where zinc oxide is encountered good ventilation be provided. The commercial price of zinc in January 2002 was roughly 40¢/lb ($90 kg). Zinc metal with a purity of 99.9999% is priced at about $5/g.

Zirconium — (Syriac, *zargun*, color of gold), Zr; at. wt. 91.224(2); at. no. 40; m.p. 1855°C; b.p. 4409°C; sp. gr. 6.506 (20°C); valence +2, +3, and +4. The name *zircon* may have originated from the Syriac word *zargono,* which describes the color of certain gemstones now known as *zircon, jargon, hyacinth, jacinth,* or *ligure.* This mineral, or its variations, is mentioned in biblical writings. These minerals were not known to contain this element until Klaproth, in 1789, analyzed a *jargon* from Sri Lanka and found a new earth, which Werner named zircon (*silex circonius*), and Klaproth called *Zirkonerde (zirconia).* The impure metal was first isolated by Berzelius in 1824 by heating a mixture of potassium and potassium zirconium fluoride in a small iron tube. Pure zirconium was first prepared in 1914. Very pure zirconium was first produced in 1925 by van Arkel and de Boer by an iodide decomposition process they developed. Zirconium is found in abundance in S-type stars, and has been identified in the sun and meteorites. Analyses of lunar rock samples obtained during the various Apollo missions to the moon show a surprisingly high zirconium oxide content, compared with terrestial rocks. Naturally occurring zirconium contains five isotopes. Thirty-one other radioactive isotopes and isomers are known to exist. *Zircon*, $ZrSiO_4$, the principal ore, is found in deposits in Florida, South Carolina, Australia, South Africa, and elsewhere. *Baddeleyite*, found in Brazil, is an important zirconium mineral. It is principally pure ZrO_2 in crystalline form having a hafnium content of about 1%. Zirconium also occurs in some 30 other recognized mineral species. Zirconium is produced commercially by reduction of the chloride with magnesium (the Kroll Process), and by other methods. It is a grayish-white lustrous metal. When finely divided, the metal may ignite spontaneously in air, especially at elevated temperatures. The solid metal is much more difficult to ignite. The inherent toxicity of zirconium compounds is low. Hafnium is invariably found in zirconium ores, and the separation is difficult. Commercial-grade zirconium contains from 1 to 3% hafnium. Zirconium has a low absorption cross section for neutrons, and is therefore used for nuclear energy applications, such as for cladding fuel elements. Commercial nuclear power generation now takes more than 90% of zirconium metal production. Reactors of the size now being made may use as much as a half-million lineal feet of zirconium alloy tubing. Reactor-grade zirconium is essentially free of hafnium. *Zircaloy*® is an important alloy developed specifically for nuclear applications. Zirconium is exceptionally resistant to corrosion by many common acids and alkalis, by sea water, and by other agents. It is used extensively by the chemical industry where corrosive agents are employed. Zirconium is used as a getter in vacuum tubes, as an alloying agent in steel, in surgical appliances, photoflash bulbs, explosive primers, rayon spinnerets, lamp filaments, etc. It is used in poison ivy lotions in the form of the carbonate as it combines with *urushiol*. With niobium, zirconium is superconductive at low temperatures and is used to make superconductive magnets, which offer hope of direct large-scale generation of electric power. Alloyed with zinc, zirconium becomes magnetic at temperatures below 35 K. Zirconium oxide (zircon) has a high index of refraction and is used as a gem material. The impure

oxide, zirconia, is used for laboratory crucibles that will withstand heat shock, for linings of metallurgical furnaces, and by the glass and ceramic industries as a refractory material. Its use as a refractory material accounts for a large share of all zirconium consumed. Zirconium tungstate is an unusual material that shrinks, rather than expands, when heated. While this compound has been known for more than 30 years, it is only now that it is being studied to determine the nature of this unusual behavior. A few other compounds are known to possess this property, but they tend to shrink in one direction, while they stretch out in others in order to maintain an overall volume. Zirconium tungstate shrinks in all directions over a wide temperature range of from near absolute zero to +777°C. This material is being considered for use in very small computer chips, which are subject to severe temperature changes. It is also being considered for use in composite materials where thermal expansion may be a problem. Zirconium of about 99.5% purity is available at a cost of about $2000/kg or about $4/g.

PHYSICAL CONSTANTS OF INORGANIC COMPOUNDS

The compounds in this table were selected on the basis of their laboratory and industrial importance, as well as their value in illustrating trends in the variation of physical properties with position in the periodic table. An effort has been made to include the most frequently encountered inorganic substances; a limited number of organometallics are also covered. Many, if not most, of the compounds that are solids at ambient temperature can exist in more than one crystalline modification. The information given here applies to the most stable or common crystalline form. In cases where two or more forms are of practical importance, separate entries will be found in the table.

Compounds are arranged primarily in alphabetical order by the most commonly used name. However, adjustments are made in many instances in order to bring closely related compounds together. For example, hydrides of elements such as boron, silicon, and germanium are grouped together immediately following the entry for the parent element, since they would otherwise be scattered throughout the table. Likewise, the oxoacids of an element are given in one group whenever a strict alphabetical order would separate them (e.g., sulfuric acid and fluorosulfuric acid). The Formula Index following the table provides another means of locating a compound. There is also an index to CAS Registry Numbers.

The following data fields appear in the table:

- **Name:** Systematic name for the substance. The valence state of a metallic element is indicated by a Roman numeral, e.g., copper in the +1 state is written as copper(I) rather than cuprous, iron in the +3 state is iron(III) rather than ferric.
- **Formula:** The simplest descriptive formula is given, but this does not necessarily specify the actual structure of the compound. For example, aluminum chloride is designated as $AlCl_3$, even though a more accurate representation of the structure in the solid phase (and, under some conditions, in the gas phase) is Al_2Cl_6. A few exceptions are made, such as the use of Hg_2^{+2} for the mercury(I) ion.
- **CAS Registry Number:** Chemical Abstracts Service Registry Number. An asterisk (*) following the CAS RN for a hydrate indicates that the number refers to the anhydrous compound. In most cases the generic CAS RN for the compound is given rather than the number for a specific crystalline form or mineral.
- **Mol. Weight:** Molecular weight (relative molar mass) as calculated with the 1997 IUPAC Recommended Atomic Weights. The number of decimal places corresponds to the number of places in the atomic weight of the least accurately known element (e.g., one place for lead compounds, two places for compounds of selenium, germanium, etc.); a maximum of three places is given. For compounds of radioactive elements for which IUPAC makes no recommendation, the mass number of the isotope with longest half-life is used, and the result is rounded to the nearest integer.
- **Physical Form:** The crystal system is given, when available, for compounds that are solid at room temperature, together with color and other descriptive features. Abbreviations are listed below.
- **mp:** Normal melting point in °C. The notation "tp" indicates the temperature at which solid, liquid, and gas are in equilibrium at a pressure greater than one atmosphere (i.e., the normal melting point does not exist). When available, the triple point pressure is listed.
- **bp:** Normal boiling point in °C (referred to 101.325 kPa or 760 mmHg pressure). The notation "sp" following the number indicates the temperature where the pressure of the vapor in equilibrium with the solid reaches as 101.325 kPa. See Reference 8, p. 23, for further discussion of sublimation points and triple points. A notation "sublimes" without a temperature being given indicates that there is a perceptible sublimation pressure above the solid at ambient temperatures.
- **Density:** Density values for solids and liquids are always in units of grams per cubic centimeter and can be assumed to refer to temperatures near room temperature unless otherwise stated. Values for gases are the calculated ideal gas densities in grams per liter at 25°C and 101.325 kPa; the unit is always specified for a gas value.
- **Aqueous Solubility:** Solubility is expressed as the number of grams of the compound (excluding any water of hydration) that will dissolve in 100 g of water. The temperature in °C is given as a superscript. Solubility at other temperatures can be found for many compounds in the table "Aqueous Solubility of Inorganic Compounds at Various Temperatures" in Section 8.
- **Qualitative Solubility:** Qualitative information on the solubility in other solvents (and in water, if quantitative data are unavailable) is given here. The abbreviations are:
  - i insoluble
  - sl slightly soluble
  - s soluble
  - vs very soluble

Data were taken from a wide variety of reliable sources, including monographs, treatises, review articles, evaluated compilations and databases, and in some cases the primary literature. Some of the most useful references for the properties covered here are listed below.

List of Abbreviations

Ac - acetyl
ace - acetone
acid - acid solutions
alk - alkaline solutions
amorp - amorphous
anh - anhydrous
aq - aqueous
blk - black
brn - brown
bz - benzene
chl - chloroform
col - colorless
conc - concentrated
cry - crystals, crystalline
cub - cubic
cyhex - cyclohexane
dec - decomposes
dil - dilute
diox - dioxane
eth - ethyl ether
EtOH - ethanol
exp - explodes, explosive
flam - flammable
gl - glass, glassy
grn - green
hc - hydrocarbon solvents
hex - hexagonal
hp - heptane

hex - hexane
hyd - hydrate
hyg - hygroscopic
i - insoluble in
liq - liquid
MeOH - methanol
mono - monoclinic
octahed - octahedral
oran - orange
orth - orthorhombic
os - organic solvents
peth - petroleum ether
pow - powder
prec - precipitate
pur - purple
py - pyridine
reac - reacts with
refrac - refractory
rhom - rhombohedral
s - soluble in
silv - silvery
sl - slightly soluble in
soln - solution
sp - sublimation point
stab - stable
subl - sublimes
temp - temperature
tetr - tetragonal
thf - tetrahydrofuran
tol - toluene
tp - triple point
trans - transition, transformation
tricl - triclinic
trig - trigonal
unstab - unstable
viol - violet
visc - viscous
vs - very soluble in
wh - white
xyl - xylene
yel - yellow

References

1. Phillips, S. L., and Perry, D.L., *Handbook of Inorganic Compounds*, CRC Press, Boca Raton, FL, 1995.
2. Trotman-Dickenson, A. F., Executive Editor, *Comprehensive Inorganic Chemistry*, Vol. 1-5, Pergamon Press, Oxford, 1973.
3. Greenwood, N. N., and Earnshaw, A., *Chemistry of the Elements, Second Edition*, Butterworth-Heinemann, Oxford, 1997.
4. Budavari, S., Ed., *The Merck Index, Twelfth Edition*, Merck & Co., Rahway, NJ, 1996.
5. *GMELIN Handbook of Inorganic and Organometallic Chemistry*, Springer-Verlag, Heidelberg.
6. Chase, M.W., Davies, C.A., Downey, J.R., Frurip, D. J., McDonald, R.A., and Syverud, A.N., *JANAF Thermochemical Tables, Third Edition, J. Phys. Chem. Ref. Data*, Vol. 14, Suppl. 1, 1985; Chase, M. W., *NIST-JANAF Thermochemical Tables, Fourth Edition, J. Phys. Chem. Ref. Data*, Monograph No. 9, 1998.
7. Donnay, J.D.H., and Ondik, H.M., *Crystal Data Determinative Tables, Third Edition*, Volumes 2 and 4, Inorganic Compounds, Joint Committee on Powder Diffraction Standards, Swarthmore, PA, 1973.
8. Lide, D. R., and Kehiaian, H.V., *CRC Handbook of Thermophysical and Thermochemical Data*, CRC Press, Boca Raton, FL, 1994.
9. *Kirk-Othmer Concise Encyclopedia of Chemical Technology*, Wiley-Interscience, New York, 1985.
10. *Dictionary of Inorganic Compounds*, Chapman & Hall, New York, 1992.
11. Massalski, T. B., Ed., *Binary Alloy Phase Diagrams, 2nd Edition*, ASM International, Metals Park, Ohio, 1990.
12. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, Sixth Edition*, II/4, Caloric Quantities of State, Springer-Verlag, Heidelberg, 1961.
13. Deer, W. A., Howie, R.A., and Zussman, J., *An Introduction to the Rock-Forming Minerals*, 2nd Edition, Longman Scientific & Technical, Harlow, Essex, 1992.
14. Carmichael, R. S., *Practical Handbook of Physical Properties of Rocks and Minerals*, CRC Press, Boca Raton, FL, 1989.
15. Dinsdale, A.T., "SGTE Data for Pure Elements", *CALPHAD*, 15, 317-425, 1991.
16. Madelung, O., *Semiconductors: Group IV Elements and III-IV Compounds*, Springer-Verlag, Heidelberg, 1991.
17. Daubert, T.E., Danner, R. P., Sibul, H.M., and Stebbins, C.C., *Physical and Thermodynamic Properties of Pure Compounds: Data Compilation*, extant 1994 (core with 4 supplements), Taylor & Francis, Bristol, PA.
18. Lidin, R. A., Andreeva, L. L., and Molochko, V. A., *Constants of Inorganic Substances*, Begell House, New York, 1995.
19. Gurvich, L. V., Veyts, I. V., and Alcock, C. B., *Thermodynamic Properties of Individual Substances, Fourth Edition*, Hemisphere Publishing Corp., New York, 1989.
20. *The Combined Chemical Dictionary on CDROM*, Chapman & Hall/CRC Press, Boca Raton, FL, 2000.

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1	Actinium	Ac	7440-34-8	227	silv metal; cub	1051	3198	10		
2	Actinium bromide	$AcBr_3$	33689-81-5	467	wh hex cry		800 subl	5.85		s H_2O
3	Actinium chloride	$AcCl_3$	22986-54-5	333	wh hex cry		960 subl	4.81		
4	Actinium fluoride	AcF_3	33689-80-4	284	wh hex cry			7.88		i H_2O
5	Actinium iodide	AcI_3	33689-82-6	608	wh cry					s H_2O
6	Actinium oxide	Ac_2O_3	12002-61-8	502	wh hex cry	1977		9.19		i H_2O
7	Aluminum	Al	7429-90-5	26.982	silv-wh metal; cub cry	660.32	2519	2.70		i H_2O; s acid, alk
8	Aluminum ammonium sulfate	$AlNH_4(SO_4)_2$	7784-25-0	237.148	wh powder					sl H_2O; i EtOH
9	Aluminum ammonium sulfate dodecahydrate	$AlNH_4(SO_4)_2 \cdot 12H_2O$	7784-26-1	453.331	col cry or powder	94.5	>280 dec	1.65		s H_2O; i EtOH
10	Aluminum antimonide	AlSb	25152-52-7	148.742	cub cry	1065		4.26		
11	Aluminum arsenide	AlAs	22831-42-1	101.903	oran cub cry; hyg	1740		3.76		
12	Aluminum borate	$2Al_2O_3 \cdot B_2O_3$	11121-16-7	273.543	needles	≈1050				i H_2O
13	Aluminum boride	AlB_2	12041-50-8	48.604	powder	>920 dec		3.19		s dil HCl
14	Aluminum borohydride	$Al(BH_4)_3$	16962-07-5	71.510	flam liq	–64.5	44.5			reac H_2O
15	Aluminum bromate nonahydrate	$Al(BrO_3)_3 \cdot 9H_2O$	11126-81-1*	572.826	wh hyg cry	62	>100 dec			s H_2O
16	Aluminum bromide	$AlBr_3$	7727-15-3	266.694	wh-yel monocl cry; hyg	97.5	255	3.2		reac H_2O; s bz, tol
17	Aluminum bromide hexahydrate	$AlBr_3 \cdot 6H_2O$	7784-11-4	374.785	col-yel hyg cry	93		2.54		s H_2O, EtOH, CS_2
18	Aluminum carbide	Al_4C_3	1299-86-1	143.958	yel hex cry	2100	>2200 dec	2.36		reac H_2O
19	Aluminum chlorate nonahydrate	$Al(ClO_3)_3 \cdot 9H_2O$	15477-33-5	439.472	hyg cry					vs H_2O; s EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
20	Aluminum chloride	$AlCl_3$	7446-70-0	133.340	wh hex cry or powder; hyg	192.6	180 sp	2.48	45.1^{25}	s bz, ctc, chl
21	Aluminum chloride hexahydrate	$AlCl_3 \cdot 6H_2O$	7784-13-6	241.431	col hyg cry	100 dec		2.398	45.1^{25}	s EtOH, eth
22	Aluminum diacetate	$Al(OH)(C_2H_3O_2)_2$	142-03-0	162.078	wh amorp powder					i H_2O
23	Aluminum ethanolate	$Al(C_2H_5O)_3$	555-75-9	162.163	liq, condenses to wh solid	140				reac H_2O; sl xyl
24	Aluminum fluoride	AlF_3	7784-18-1	83.977	wh hex cry	≈2250 tp (220 MPa)	1276 sp	3.10	0.50^{25}	
25	Aluminum fluoride monohydrate	$AlF_3 \cdot H_2O$	32287-65-3	101.992	orth cry			2.17	0.50^{25}	
26	Aluminum fluoride trihydrate	$AlF_3 \cdot 3H_2O$	15098-87-0	138.023	wh hyg cry			1.914	0.50^{25}	
27	Aluminum hexafluorosilicate nonahydrate	$Al_2(SiF_6)_3 \cdot 9H_2O$	17099-70-6	642.329	hex prisms	>500 dec				s H_2O
28	Aluminum hydride	AlH_3	7784-21-6	30.006	col hex cry	>150 dec				reac H_2O
29	Aluminum hydroxide	$Al(OH)_3$	21645-51-2	78.004	wh amorp powder			2.42		i H_2O; s alk, acid
30	Aluminum hydroxychloride	$Al_2(OH)_5Cl \cdot 2H_2O$	1327-41-9	210.483	gl solid					s H_2O
31	Aluminum hypophosphite	$Al(H_2PO_2)_3$	7784-22-7	221.948	cry powder	220 dec				i H_2O; s alk, acid
32	Aluminum iodide	AlI_3	7784-23-8	407.695	wh leaflets	188.28	382	3.98		reac H_2O
33	Aluminum iodide hexahydrate	$AlI_3 \cdot 6H_2O$	10090-53-6	515.786	yel hyg cry powder					vs H_2O; s EtOH, eth
34	Aluminum lactate	$Al(C_3H_5O_3)_3$	18917-91-4	294.192	powder					vs H_2O
35	Aluminum nitrate	$Al(NO_3)_3$	13473-90-0	212.997	wh hyg solid	dec			68.9^{25}	vs EtOH; sl ace
36	Aluminum nitrate nonahydrate	$Al(NO_3)_3 \cdot 9H_2O$	7784-27-2	375.134	wh hyg mono cry	73	135 dec	1.72	68.9^{25}	vs EtOH; i pyr
37	Aluminum nitride	AlN	24304-00-5	40.989	blue-wh hex cry	3000		3.255		reac H_2O
38	Aluminum oleate	$Al(C_{18}H_{33}O_2)_3$	688-37-9	871.342	yel solid					i H_2O; s EtOH, bz
39	Aluminum phosphate	$AlPO_4$	7784-30-7	121.953	wh rhomb plates	>1460		2.56		i H_2O; sl acid
40	Aluminum metaphosphate	$Al(PO_3)_3$	32823-06-6	263.898	col powder; tetr	≈1525		2.78		i H_2O
41	Aluminum oxide (corundum)	Al_2O_3	1344-28-1	101.961	wh powder; hex	2053	≈3000	3.97		i H_2O, os; sl alk
42	Aluminum oxyhydroxide	AlO(OH)	14457-84-2	59.989	ortho cry			3.44		i H_2O; s acid, alk
43	Aluminum palmitate	$Al(C_{15}H_{31}COO)_3$	555-35-1	793.230	wh-yel powder					i H_2O, EtOH; s peth
44	Aluminum perchlorate nonahydrate	$Al(ClO_4)_3 \cdot 9H_2O$	14452-39-2	487.470	wh hyg cry	82 dec		2.0	182.4^{0}	
45	Aluminum phosphide	AlP	20859-73-8	57.956	grn or yel cub cry	2550		2.40		reac H_2O
46	Aluminum selenide	Al_2Se_3	1302-82-5	290.84	yel-brown powder	960		3.437		reac H_2O
47	Aluminum silicate	Al_2SiO_5	12183-80-1	162.046	gray-grn cry			3.145		
48	Aluminum silicate dihydrate	$Al_2O_3 \cdot 2SiO_2 \cdot 2H_2O$	1332-58-7	258.161	wh-yel powder; tricl			2.59		i H_2O, acid, alk
49	Aluminum stearate	$Al(C_{18}H_{35}O_2)_3$	637-12-7	877.390	wh powder	115		1.070		i H_2O, EtOH, eth; s alk
50	Aluminum sulfate	$Al_2(SO_4)_3$	10043-01-3	342.154	wh cry	1040 dec			38.5^{25}	i EtOH
51	Aluminum sulfate octadecahydrate	$Al_2(SO_4)_3 \cdot 18H_2O$	7784-31-8	666.429	col monocl cry	86 dec		1.69	38.5^{25}	
52	Aluminum sulfide	Al_2S_3	1302-81-4	150.161	yel-gray powder	1100		2.02		
53	Aluminum telluride	Al_2Te_3	12043-29-7	436.76	gray-blk hex cry	≈895		4.5		
54	Aluminum thiocyanate	$Al(SCN)_3$	538-17-0	201.232	yel powder					s H_2O; i EtOH, eth
55	Americium	Am	7440-35-9	243	silv metal; hex or cub	1176	2011	12		s acid
56	Americium(III) oxide	Am_2O_3	12254-64-7	534	tan hex cry			11.77		s acid
57	Americium(III) bromide	$AmBr_3$	14933-38-1	483	wh orth cry			6.85		s H_2O
58	Americium(III) chloride	$AmCl_3$	13464-46-5	349	pink hex cry	500		5.87		
59	Americium(III) fluoride	AmF_3	13708-80-0	300	pink hex cry	1393		9.53		
60	Americium(III) iodide	AmI_3	13813-47-3	624	yel ortho cry	≈950		6.9		
61	Americium(IV) fluoride	AmF_4	15947-41-8	319	tan monocl cry			7.23		
62	Americium(IV) oxide	AmO_2	12005-67-3	275	blk cub cry	>1000 dec		11.68		s acid
63	Ammonia	NH_3	7664-41-7	17.031	col gas	-77.73	-33.33	0.696 g/L		vs H_2O; s EtOH, eth
64	Ammonium acetate	$NH_4C_2H_3O_2$	631-61-8	77.083	wh hyg cry	114		1.073	148^{4}	s EtOH; sl ace
65	Ammonium azide	NH_4N_3	12164-94-2	60.059	ortho cry; flam	160	exp	1.346	20.2^{30}	
66	Ammonium benzoate	$NH_4C_7H_5O_2$	1863-63-4	139.152	wh cry or powder	198		1.26		s H_2O; sl EtOH
67	Ammonium hydrogen malate	$NH_4C_4H_4O_5$	5972-71-4	151.118	ortho cry	160		1.15		s H_2O; sl EtOH
68	Ammonium borate tetrahydrate	$(NH_4)_2B_4O_7 \cdot 4H_2O$	12228-87-4	263.377	tetr cry					s H_2O; i EtOH
69	Ammonium bromate	NH_4BrO_3	13843-59-9	145.941	col hex cry	exp				vs H_2O
70	Ammonium bromide	NH_4Br	12124-97-9	97.943	wh hyg tetr cry	542 dec	396 sp	2.429	78.3^{25}	s EtOH, ace; sl eth
71	Ammonium caprylate	$NH_4C_8H_{15}O_2$	5972-76-9	161.243	hyg monocl cry	≈75				reac H_2O; s EtOH; i chl, bz
72	Ammonium carbamate	NH_2COONH_4	1111-78-0	78.071	cry powder					vs H_2O; s EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
73	Ammonium carbonate	$(NH_4)_2CO_3$	506-87-6	96.086	col cry powder	58 dec			100^{15}	
74	Ammonium cerium(III) sulfate tetrahydrate	$NH_4Ce(SO_4)_2 \cdot 4H_2O$	21995-38-0*	422.343	monocl cry					s H_2O
75	Ammonium cerium(IV) nitrate	$(NH_4)_2Ce(NO_3)_6$	16774-21-3	548.223	red-oran cry					vs H_2O
76	Ammonium chlorate	NH_4ClO_3	10192-29-7	101.490	wh cry	102 exp		1.80	28.7^{0}	
77	Ammonium chloride	NH_4Cl	12125-02-9	53.492	col cub cry	520 tp (dec)	338 sp	1.519	39.5^{25}	
78	Ammonium chromate	$(NH_4)_2CrO_4$	7788-98-9	152.071	yel cry	185 dec		1.90	37^{25}	sl ace, MeOH; i EtOH
79	Ammonium chromic sulfate dodecahydrate	$NH_4Cr(SO_4)_2 \cdot 12H_2O$	10022-47-6	478.345	blue-viol cry	94 dec		1.72		s H_2O; sl EtOH
80	Ammonium cobalt(II) phosphate	$CoNH_4PO_4$	14590-13-7	171.943	red-viol powder (hyd)					i H_2O; s acid
81	Ammonium cobalt(II) sulfate hexahydrate	$(NH_4)_2Co(SO_4)_2 \cdot 6H_2O$	13586-38-4	395.229	red monocl prisms			1.90		s H_2O; i EtOH
82	Ammonium copper(II) chloride	$CuCl_2 \cdot 2NH_4Cl$	10060-13-6*	241.434	yel hyg orth cry					s H_2O
83	Ammonium copper(II) chloride dihydrate	$CuCl_2 \cdot 2NH_4Cl \cdot 2H_2O$	10060-13-6	277.464	blue-grn tetr cry	110 dec		1.993		s H_2O, EtOH
84	Ammonium cyanide	NH_4CN	12211-52-8	44.056	col tetr cry	dec		1.10		vs H_2O
85	Ammonium dichromate	$(NH_4)_2Cr_2O_7$	7789-09-5	252.065	oran-red monocl cry; hyg	180 dec		2.155	35.6^{20}	
86	Ammonium dihydrogen arsenate	$NH_4H_2AsO_4$	13462-93-6	158.975	tetr cry	300 dec		2.311	52.7^{25}	
87	Ammonium dihydrogen phosphate	$NH_4H_2PO_4$	7722-76-1	115.026	wh tetr cry	190		1.80	40.4^{25}	sl EtOH; i ace
88	Ammonium dithiocarbamate	NH_4NH_2CSS	513-74-6	110.204	yel ortho cry	99 dec		1.45		s H_2O
89	Ammonium ferric chromate	$NH_4Fe(CrO_4)_2$	7789-08-4	305.871	red powder					i H_2O
90	Ammonium ferric oxalate trihydrate	$(NH_4)_3Fe(C_2O_4)_3 \cdot 3H_2O$	13268-42-3	428.063	grn monocl cry; hyg	≈160 dec		1.780		vs H_2O; i EtOH
91	Ammonium ferric sulfate dodecahydrate	$NH_4Fe(SO_4)_2 \cdot 12H_2O$	10138-04-2	482.194	col to viol cry	≈37		1.71		vs H_2O; i EtOH
92	Ammonium ferricyanide trihydrate	$(NH_4)_3Fe(CN)_6 \cdot 3H_2O$	14221-48-8*	320.111	red cry					s H_2O; i EtOH
93	Ammonium ferrocyanide trihydrate	$(NH_4)_4Fe(CN)_6 \cdot 3H_2O$	14481-29-9*	338.149	yel cry	dec				s H_2O; i EtOH
94	Ammonium ferrous sulfate hexahydrate	$(NH_4)_2Fe(SO_4)_2 \cdot 6H_2O$	10045-89-3	392.141	blue-grn monocl cry	≈100 dec		1.86		s H_2O; i EtOH
95	Ammonium fluoride	NH_4F	12125-01-8	37.037	wh hex cry; hyg	dec		1.015	83.5^{25}	sl EtOH
96	Ammonium tetrafluoroborate	NH_4BF_4	13826-83-0	104.844	wh powder; orth	487 dec		1.871	25^{20}	
97	Ammonium fluorosulfonate	NH_4SO_3F	13446-08-7	117.101	col needles	245				s H_2O, EtOH, MeOH
98	Ammonium formate	NH_4CHO_2	540-69-2	63.057	hyg cry	116		1.27	143^{20}	s EtOH
99	Ammonium hexachloroiridate(IV)	$(NH_4)_2IrCl_6$	16940-92-4	441.010	blk cry powder	dec		2.856	1.09^{25}	
100	Ammonium hexachloroosmiate(IV)	$(NH_4)_2OsCl_6$	12125-08-5	439.02	red cry or powder		subl	2.93		s H_2O, EtOH
101	Ammonium hexachloropalladate(IV)	$(NH_4)_2PdCl_6$	19168-23-1	355.21	red-brn hyg cry	dec		2.418		
102	Ammonium hexabromoplatinate(IV)	$(NH_4)_2PtBr_6$	17363-02-9	710.58	powder	145 dec			0.59^{20}	
103	Ammonium hexachloroplatinate(IV)	$(NH_4)_2PtCl_6$	16919-58-7	443.87	red-oran cub cry	380 dec		3.065	0.5^{20}	i EtOH
104	Ammonium hexafluoroaluminate	$(NH_4)_3AlF_6$	7784-19-2	195.087	cub cry			1.78		s H_2O
105	Ammonium hexafluorogallate	$(NH_4)_3GaF_6$	14639-94-2	237.828	col cub cry	>200 dec		2.10		
106	Ammonium hexafluorogermanate	$(NH_4)_2GeF_6$	16962-47-3	222.68	wh cry	380	subl	2.564		s H_2O; i EtOH
107	Ammonium hexafluorophosphate	NH_4PF_6	16941-11-0	163.003	wh cub cry	58 dec		2.180		vs H_2O; s ace, EtOH, MeOH
108	Ammonium hexafluorosilicate	$(NH_4)_2SiF_6$	16919-19-0	178.153	wh cub or trig cry	dec		2.011	22.7^{25}	i EtOH, ace
109	Ammonium hexafluorozirconate(IV)	$(NH_4)_2ZrF_6$	16919-31-6	241.291	wh hex cry			1.154		s H_2O
110	Ammonium hydrogen arsenate	$(NH_4)_2HAsO_4$	7784-44-3	176.004	wh powder			1.99		s H_2O
111	Ammonium hydrogen borate trihydrate	$NH_4HB_4O_7 \cdot 3H_2O$	10135-84-9	228.332	col cry			≈2.5		s H_2O
112	Ammonium hydrogen carbonate	NH_4HCO_3	1066-33-7	79.056	col or wh prisms	107 dec		1.586	24.8^{25}	i EtOH, bz
113	Ammonium hydrogen citrate	$(NH_4)_2HC_6H_5O_7$	3012-65-5	226.184	col cry			1.48		vs H_2O; sl EtOH
114	Ammonium hydrogen fluoride	NH_4HF_2	1341-49-7	57.044	wh orth cry	125	240 dec	1.50	60.2^{20}	

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
115	Ammonium hydrogen oxalate monohydrate	$NH_4HC_2O_4 \cdot H_2O$	5972-72-5*	125.081	col rhomb cry	dec		1.56		sl H_2O, EtOH
116	Ammonium hydrogen phosphate	$(NH_4)_2HPO_4$	7783-28-0	132.055	wh cry	155 dec		1.619	69.5^{25}	i EtOH, ace
117	Ammonium hydrogen selenate	NH_4HSeO_4	10294-60-7	162.01	rhom cry	dec		2.162		
118	Ammonium hydrogen sulfate	NH_4HSO_4	7803-63-6	115.111	wh hyg cry	147		1.78	100^{20}	i EtOH, ace, py
119	Ammonium hydrogen sulfide	NH_4HS	12124-99-1	51.113	wh tetr or orth cry	dec		1.17	128^{0}	sl ace; i bz, eth
120	Ammonium hydrogen sulfite	NH_4HSO_3	10192-30-0	99.111	col cry	dec		2.03	71.8^{0}	
121	Ammonium hydrogen tartrate	$NH_4C_4H_4O_6$	3095-65-6	167.117	wh cry			1.68		sl H_2O; s alk; i EtOH
122	Ammonium hydroxide	NH_4OH	1336-21-6	35.046	exists only in soln					
123	Ammonium hypophosphite	$NH_4H_2PO_2$	7803-65-8	83.028	wh hyg cry	dec				vs H_2O; sl EtOH; i ace
124	Ammonium iodate	NH_4IO_3	13446-09-8	192.941	wh powder	150		3.3	3.84^{25}	
125	Ammonium iodide	NH_4I	12027-06-4	144.943	wh tetr cry; hyg	551 dec	405 sp	2.514	178^{25}	sl EtOH, MeOH
126	Ammonium lactate	$NH_4C_3H_5O_3$	52003-58-4	107.108	col cry	92				s H_2O, EtOH; sl MeOH; i ace, eth
127	Ammonium metatungstate hexahydrate	$(NH_4)_6W_7O_{24} \cdot 6H_2O$	12028-48-7	1887.19	wh cry					s H_2O; i EtOH
128	Ammonium metavanadate	NH_4VO_3	7803-55-6	116.979	wh-yel cry	200 dec		2.326	4.8^{20}	
129	Ammonium molybdate(VI) tetrahydrate	$(NH_4)_6Mo_7O_{24} \cdot 4H_2O$	12054-85-2	1235.86	col or grn-yel cry	90 dec		2.498	43	i EtOH
130	Ammonium molybdophosphate	$(NH_4)_3PO_4 \cdot 12MoO_3$	54723-94-3*	1876.35	yel cry pow	dec			0.02	s alk; i acid
131	Ammonium nickel chloride hexahydrate	$NH_4NiCl_3 \cdot 6H_2O$	16122-03-5*	291.181	grn hyg cry			1.65		s H_2O
132	Ammonium nickel sulfate hexahydrate	$(NH_4)_2Ni(SO_4)_2 \cdot 6H_2O$	7785-20-8	394.989	blue-grn cry	dec		1.923		sl H_2O; i EtOH
133	Ammonium nitrate	NH_4NO_3	6484-52-2	80.043	wh hyg cry; orth	169.7	dec 200-260	1.72	213^{25}	sl MeOH
134	Ammonium nitrite	NH_4NO_2	13446-48-5	64.044	wh-yel cry	60 exp		1.69	221^{25}	i eth
135	Ammonium nitroferricyanide	$(NH_4)_2Fe(CN)_5NO$	14402-70-1	252.016	red-brn cry					s H_2O, EtOH
136	Ammonium oleate	$NH_4C_{18}H_{33}O_2$	544-60-5	299.493	yel-brn paste	21				s H_2O; sl ace
137	Ammonium oxalate	$(NH_4)_2C_2O_4$	1113-38-8	124.096	col sol			1.5	5.20^{25}	
138	Ammonium oxalate monohydrate	$(NH_4)_2C_2O_4 \cdot H_2O$	6009-70-7	142.110	wh orth cry	dec		1.50	5.20^{25}	sl EtOH
139	Ammonium palmitate	$NH_4C_{15}H_{31}CO_2$	593-26-0	273.455	yel-wh powder	22				s H_2O; sl bz, xyl; i ace, EtOH, ctc
140	Ammonium pentaborate tetrahydrate	$NH_4B_5O_8 \cdot 4H_2O$	12007-89-5	272.150	wh cry				7.03^{18}	
141	Ammonium pentachlorozincate	$(NH_4)_3ZnCl_5$	14639-98-6	296.77	hyg orth cry			1.81		vs H_2O
142	Ammonium perchlorate	NH_4ClO_4	7790-98-9	117.490	wh orth cry	dec, exp		1.95	24.5^{25}	s MeOH; sl EtOH, ace; i eth
143	Ammonium permanganate	NH_4MnO_4	13446-10-1	136.975	purp rhomb cry	70 dec		2.22	7.9^{15}	
144	Ammonium peroxydisulfate	$(NH_4)_2S_2O_8$	7727-54-0	228.204	monocl cry or wh powder	dec		1.982	83.5^{25}	
145	Ammonium perrhenate	NH_4ReO_4	13598-65-7	268.244	col powder			3.97	6.23^{20}	
146	Ammonium phosphate trihydrate	$(NH_4)_3PO_4 \cdot 3H_2O$	10361-65-6*	203.133	wh prisms				25.0^{25}	i ace
147	Ammonium phosphite, dibasic, monohydrate	$(NH_4)_2HPO_3 \cdot H_2O$	51503-61-8	134.071	hyg cry					s H_2O
148	Ammonium phosphomolybdate monohydrate	$(NH_4)_3PO_4 \cdot 12MoO_3 \cdot H_2O$	54723-94-3	1894.36	yel cry or powder	dec			0.02	
149	Ammonium phosphotungstate dihydrate	$(NH_4)_3PO_4 \cdot 12WO_3 \cdot 2H_2O$	1311-90-6	2967.18	cry powder					sl H_2O
150	Ammonium picrate	$NH_4C_6H_2N_3O_7$	131-74-8	246.135	yel orth cry	exp		1.72		sl H_2O
151	Ammonium salicylate	$NH_4C_7H_5O_3$	528-94-9	155.151	wh cry powder					vs H_2O; s EtOH
152	Ammonium selenate	$(NH_4)_2SeO_4$	7783-21-3	179.04	wh monocl cry	dec		2.194	117^{25}	i EtOH, ace
153	Ammonium selenite	$(NH_4)_2SeO_3$	7783-19-9	163.04	wh or red hyg cry	dec			121^{25}	
154	Ammonium stearate	$NH_4C_{18}H_{35}O_2$	1002-89-7	301.509	yel-wh powder	22		0.89		sl H_2O, bz; s EtOH, MeOH; i ace
155	Ammonium sulfamate	$NH_4NH_2SO_3$	7773-06-0	114.125	wh hyg cry	131	160 dec			vs H_2O; sl EtOH
156	Ammonium sulfate	$(NH_4)_2SO_4$	7783-20-2	132.141	wh or brn orth cry	280 dec		1.77	76.4^{25}	i EtOH, ace
157	Ammonium sulfide	$(NH_4)_2S$	12135-76-1	68.143	yel-oran cry	≈0 dec				s H_2O, EtOH, alk
158	Ammonium sulfite	$(NH_4)_2SO_3$	17026-44-7	116.141	wh hyg cry				64.2^{25}	
159	Ammonium sulfite monohydrate	$(NH_4)_2SO_3 \cdot H_2O$	7783-11-1	134.156	col cry	dec		1.41	64.2^{25}	i EtOH, ace

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
160	Ammonium tartrate	$(NH_4)_2C_4H_4O_6$	3164-29-2	184.147	wh cry	dec		1.601		s H_2O
161	Ammonium tellurate	$(NH_4)_2TeO_4$	13453-06-0	227.68	wh powder	dec		3.024		
162	Ammonium tetrachloroaluminate	NH_4AlCl_4	7784-14-7	186.832	wh hyg solid	304				s H_2O, eth
163	Ammonium tetrachloroplatinate(II)	$(NH_4)_2PtCl_4$	13820-41-2	372.97	red cry	dec		2.936		s H_2O; i EtOH
164	Ammonium tetrachlorozincate	$(NH_4)_2ZnCl_4$	14639-97-5	243.28	wh orth plates; hyg	150 dec		1.879		vs H_2O
165	Ammonium tetrathiotungstate	$(NH_4)_2WS_4$	13862-78-7	348.18	oran cry	dec		2.71		s H_2O
166	Ammonium thiocyanate	NH_4SCN	1762-95-4	76.122	col hyg cry	≈149	dec	1.30	181^{25}	vs EtOH; s ace; i chl
167	Ammonium thiosulfate	$(NH_4)_2S_2O_3$	7783-18-8	148.207	wh cry	150 dec		1.678		vs H_2O; i EtOH, eth
168	Ammonium titanium oxalate monohydrate	$(NH_4)_2TiO(C_2O_4)_2 \cdot H_2O$	10580-03-7	293.996	hyg cry					vs H_2O
169	Ammonium tungstate(VI)	$(NH_4)_{10}W_{12}O_{41}$	11120-25-5	3042.44	cry pow			2.3		s H_2O; i EtOH
170	Ammonium uranate(VI)	$(NH_4)_2U_2O_7$	7783-22-4	624.131	red-yel amorp powder					i H_2O, alk; s acid
171	Ammonium uranium fluoride	$UO_2(NH_4)_3F_5$	18433-40-4	419.135	grn-yel monocl cry					s H_2O; i EtOH
172	Ammonium valerate	$NH_4C_4H_9CO_2$	42739-38-8	119.163	hyg cry	108				vs H_2O, EtOH; s eth
173	Ammonium zirconyl carbonate dihydrate	$(NH_4)_3ZrOH(CO_3)_3 \cdot 2H_2O$	12616-24-9*	362.404	prisms; unstable					s H_2O
174	Antimony	Sb	7440-36-0	121.760	silv metal; hex	630.628	1587	6.68		i dil acid
175	Stibine	SbH_3	7803-52-3	124.784	col gas; flam	-88	-17	5.100 g/L		sl H_2O; s EtOH
176	Antimony arsenide	SbAs	12322-34-8	196.682	hex cry	≈680		6.0		
177	Antimony(III) bromide	$SbBr_3$	7789-61-9	361.472	yel orth cry; hyg	96.6	280	4.35		reac H_2O; s ace, bz, chl
178	Antimony(III) chloride	$SbCl_3$	10025-91-9	228.118	col orth cry; hyg	73.4	220.3	3.14	987^{25}	s acid, EtOH, bz, ace
179	Antimony(III) fluoride	SbF_3	7783-56-4	178.755	wh orth cry; hyg	292	≈345	4.38	492^{25}	
180	Antimony(III) iodide	SbI_3	7790-44-5	502.473	red rhomb cry	168	401	4.92		reac H_2O; s EtOH, ace; i ctc
181	Antimony(III) oxide (senarmontite)	Sb_2O_3	1309-64-4	291.518	col cub cry	570 trans	1425	5.58		sl H_2O; i os
182	Antimony(III) oxide (valentinite)	Sb_2O_3	1309-64-4	291.518	wh orth cry	655	1425	5.7		sl H_2O; i os
183	Antimony(III) oxychloride	SbOCl	7791-08-4	173.212	wh momo cry	170 dec				reac H_2O; i EtOH, eth
184	Antimony(III) selenide	Sb_2Se_3	1315-05-5	480.40	grn orth cry	611		5.81		sl H_2O
185	Antimony(III) sulfate	$Sb_2(SO_4)_3$	7446-32-4	531.711	wh cry powder; hyg	dec		3.62		sl H_2O
186	Antimony(III) sulfide	Sb_2S_3	1345-04-6	339.718	gray-blk orth cry	550		4.562		i H_2O; s conc HCl
187	Antimony(III) teluride	Sb_2Te_3	1327-50-0	626.32	gray cry	620		6.5		
188	Antimony(III,V) oxide	Sb_2O_4	1332-81-6	307.518	yel orth cry			6.64		
189	Antimony(V) chloride	$SbCl_5$	7647-18-9	299.024	col or yel liq	4	140 dec	2.34		reac H_2O; s chl, ctc
190	Antimony(V) fluoride	SbF_5	7783-70-2	216.752	hyg visc liq	8.3	141	3.10		reac H_2O
191	Antimony(V) dichlorotrifluoride	$SbCl_2F_3$	7791-16-4	249.660	visc liq					reac H_2O
192	Antimony(V) oxide	Sb_2O_5	1314-60-9	323.517	yel powder; cub	dec		3.78	0.3^{20}	
193	Antimony(V) sulfide	Sb_2S_5	1315-04-4	403.850	oran-yel powder	75 dec		4.120		i H_2O; s acid, alk
194	Argon	Ar	7440-37-1	39.948	col gas	-189.36 tp (69 kPa)	-185.847	1.633 g/L		sl H_2O
195	Arsenic (gray)	As	7440-38-2	74.922	gray metal; rhomb	817 tp (3.70 MPa)	603 sp	5.75		i H_2O
196	Arsine	AsH_3	7784-42-1	77.946	col gas	-116	-62.5	3.186 g/L		sl H_2O
197	Diarsine	As_2H_4	15942-63-9	153.875	unstable liq		≈100			
198	Arsenic acid	H_3AsO_4	7778-39-4	141.944	exists only in soln					
199	Arsenic acid hemihydrate	$H_3AsO_4 \cdot 0.5H_2O$	7778-39-4*	150.951	wh hyg cry	35.5		≈2		vs H_2O, EtOH
200	Arsenious acid	H_3AsO_3	13464-58-9	125.944	exists only in soln					
201	Arsenic diiodide	As_2I_4	13770-56-4	657.461	red cry	137				reac H_2O; s os
202	Arsenic hemiselenide	As_2Se	1303-35-1	228.80	blk cry					i H_2O, os; dec acid, alk
203	Arsenic sulfide	As_4S_4	12279-90-2	427.950	red monocl cry	320	565	3.5		i H_2O; sl bz; s alk
204	Arsenic(III) bromide	$AsBr_3$	7784-33-0	314.634	yel orth cry; hyg	31.1	221	3.40		reac H_2O; s hc, ctc; vs eth, bz
205	Arsenic(III) chloride	$AsCl_3$	7784-34-1	181.280	col liq	-16	130	2.150		reac H_2O; vs chl, ctc, eth
206	Arsenic(III) fluoride	AsF_3	7784-35-2	131.917	col liq	-5.9	57.8	2.7		reac H_2O; s EtOH, eth, bz
207	Arsenic(III) iodide	AsI_3	7784-45-4	455.635	red hex cry	140.9	424	4.73		sl H_2O, EtOH, eth; s bz. tol

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
208	Arsenic(III) oxide (arsenolite)	As_2O_3	1327-53-3	197.841	wh cub cry	274	460	3.86	2.05^{25}	
209	Arsenic(III) oxide (claudetite)	As_2O_3	1327-53-3	197.841	wh monocl cry	313	460	3.74	2.05^{25}	s dil acid, alk; i EtOH
210	Arsenic(III) selenide	As_2Se_3	1303-36-2	386.72	brn-blk solid	260		4.75		i H_2O; s alk
211	Arsenic(III) sulfide	As_2S_3	1303-33-9	246.041	yel-oran monocl cry	310	707	3.46		i H_2O; s alk
212	Arsenic(III) telluride	As_2Te_3	12044-54-1	532.64	blk monocl cry	621		6.50		
213	Arsenic(V) chloride	$AsCl_5$	22441-45-8	252.186	stable at low temp	≈-50 dec				
214	Arsenic(V) fluoride	AsF_5	7784-36-3	169.914	col gas	-79.8	-52.8	6.945 g/L		reac H_2O; s EtOH, bz, eth
215	Arsenic(V) oxide	As_2O_5	1303-28-2	229.840	wh amorp powder	315		4.32	65.8^{20}	vs EtOH
216	Arsenic(V) selenide	As_2Se_5	1303-37-3	544.64	blk solid	dec				i H_2O, EtOH, eth; s alk
217	Arsenic(V) sulfide	As_2S_5	1303-34-0	310.173	brn-yel amorp solid	dec				i H_2O; s alk
218	Triethyl arsenite	$As(OC_2H_5)_3$	3141-12-6	210.103	liq		166	1.21		
219	Astatine	At	7440-68-8	210	cry	302				s HNO_3, os
220	Barium	Ba	7440-39-3	137.327	silv-yel metal; cub	727	1897	3.62		reac H_2O; sl EtOH
221	Barium acetate	$Ba(C_2H_3O_2)_2$	543-80-6	255.416	wh powder			2.47	79.2^{25}	
222	Barium acetate monohydrate	$Ba(C_2H_3O_2)_2 \cdot H_2O$	5908-64-5	273.431	wh cry	110 dec		2.19	79.2^{25}	sl EtOH
223	Barium aluminate	$BaAl_2O_4$	12004-04-5	255.288	hex cry	1827				
224	Barium azide	$Ba(N_3)_2$	18810-58-7	221.367	monocl cry; exp	≈120 dec		2.936	17.3^{20}	sl EtOH; i eth
225	Barium bromate monohydrate	$Ba(BrO_3)_2 \cdot H_2O$	10326-26-8	411.147	wh monocl cry	260 dec		3.99	0.831^{25}	i EtOH
226	Barium bromide	$BaBr_2$	10553-31-8	297.135	wh orth cry	857	1835	4.781	100^{25}	
227	Barium bromide dihydrate	$BaBr_2 \cdot 2H_2O$	7791-28-8	333.166	wh cry	75 dec		3.7	100^{25}	s MeOH; i EtOH, ace, diox
228	Barium carbide	BaC_2	50813-65-5	161.348	gray tetr cry	dec		3.74		reac H_2O
229	Barium carbonate	$BaCO_3$	513-77-9	197.336	wh orth cry	1555		4.2865	0.0014^{20}	s acid
230	Barium chlorate	$Ba(ClO_3)_2$	13477-00-4	304.228	wh cry	414			37.9^{25}	sl EtOH, ace
231	Barium chlorate monohydrate	$Ba(ClO_3)_2 \cdot H_2O$	10294-38-9	322.244	wh monocl cry	120 dec		3.179	37.9^{25}	s acid; sl EtOH, ace
232	Barium chloride	$BaCl_2$	10361-37-2	208.232	wh orth cry; hyg	962	1560	3.9	37.0^{25}	
233	Barium chloride dihydrate	$BaCl_2 \cdot 2H_2O$	10326-27-9	244.263	wh monocl cry	≈120 dec		3.097	37.0^{25}	i EtOH
234	Barium chromate(V)	$Ba_3(CrO_4)_2$	12345-14-1	643.968	grn-blk hex cry			5.25		s H_2O
235	Barium chromate(VI)	$BaCrO_4$	10294-40-3	253.321	yel orth cry	1380		4.50	0.00026^{20}	reac acid
236	Barium citrate monohydrate	$Ba_3(C_6H_5O_7)_2 \cdot H_2O$	512-25-4*	808.195	gray-wh cry					s H_2O, acid
237	Barium copper yttrium oxide	$BaCuY_2O_5$	82642-06-6	458.682	grn cry; not superconductor					
238	Barium copper yttrium oxide	$Ba_2Cu_3YO_7$	109064-29-1	666.194	blk solid; HT superconductor					
239	Barium copper yttrium oxide	$Ba_2Cu_4YO_8$	114104-80-2	745.739	HT superconductor					
240	Barium copper yttrium oxide	$Ba_4Cu_7Y_2O_{15}$	124365-83-9	1411.933	HT superconductor					
241	Barium cyanide	$Ba(CN)_2$	542-62-1	189.361	wh cry powder					vs H_2O; s EtOH
242	Barium dichromate dihydrate	$BaCr_2O_7 \cdot 2H_2O$	10031-16-0	389.346	brn-red needles	dec				reac H_2O
243	Barium dithionate dihydrate	$BaS_2O_6 \cdot 2H_2O$	13845-17-5	333.486	wh cry	140 dec		4.54	22.1^{20}	sl EtOH
244	Barium ferrocyanide hexahydrate	$Ba_2Fe(CN)_6 \cdot 6H_2O$	13821-06-2*	594.694	yel monocl cry	80 dec				i H_2O, EtOH
245	Barium fluoride	BaF_2	7787-32-8	175.324	wh cub cry	1368	2260	4.893	0.161^{25}	
246	Barium formate	$Ba(CHO_2)_2$	541-43-5	227.362	cry			3.21		s H_2O; i EtOH
247	Barium hexaboride	BaB_6	12046-08-1	202.193	blk cub cry	2070		4.36		i H_2O; s acid; i EtOH
248	Barium hexafluorosilicate	$BaSiF_6$	17125-80-3	279.403	wh orth needles	300 dec		4.29		i H_2O, EtOH; sl acid
249	Barium hydride	BaH_2	13477-09-3	139.343	gray orth cry	1200		4.16		reac H_2O
250	Barium hydrogen phosphate	$BaHPO_4$	10048-98-3	233.306	wh cry powder	400 dec		4.16	0.015^{20}	s dil acid
251	Barium hydrosulfide	$Ba(HS)_2$	25417-81-6	203.475	yel hyg cry					s H_2O
252	Barium hydrosulfide tetrahydrate	$Ba(HS)_2 \cdot 4H_2O$	12230-74-9	275.536	yel rhomb cry	50 dec				s H_2O
253	Barium hydroxide	$Ba(OH)_2$	17194-00-2	171.342	wh powder	408			4.91^{25}	
254	Barium hydroxide monohydrate	$Ba(OH)_2 \cdot H_2O$	22326-55-2	189.357	wh powder			3.743	4.91^{25}	s acid
255	Barium hydroxide octahydrate	$Ba(OH)_2 \cdot 8H_2O$	12230-71-6	315.464	wh monocl cry	78 dec		2.18	4.91^{25}	
256	Barium hypophosphite monohydrate	$Ba(H_2PO_2)_2 \cdot H_2O$	14871-79-5*	285.320	monocl plates			2.90		s H_2O; i EtOH
257	Barium iodate	$Ba(IO_3)_2$	10567-69-8	487.132	wh cry powder	476 dec		5.23	0.0396^{25}	
258	Barium iodate monohydrate	$Ba(IO_3)_2 \cdot H_2O$	7787-34-0	505.148	cry	130 dec		5.00	0.0396^{25}	s acid; i EtOH
259	Barium iodide	BaI_2	13718-50-8	391.136	wh orth cry	711		5.15	221^{25}	
260	Barium iodide dihydrate	$BaI_2 \cdot 2H_2O$	7787-33-9	427.167	col cry	740 dec		5.0	221^{25}	s EtOH, ace

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
261	Barium manganate(VI)	$BaMnO_4$	7787-35-1	256.263	grn-gray hyg cry			4.85	0.00041^{20}	
262	Barium metaborate monohydrate	$Ba(BO_2)_2 \cdot H_2O$	26124-86-7	240.962	wh powder	>900		3.3		sl H_2O
263	Barium molybdate	$BaMoO_4$	7787-37-3	297.27	wh powder	1450		4.975	0.0021^{20}	
264	Barium niobate	$Ba(NbO_3)_2$	12009-14-2	419.136	yel orth cry	1455		5.44		i H_2O
265	Barium nitrate	$Ba(NO_3)_2$	10022-31-8	261.336	wh cub cry	590		3.24	10.3^{25}	sl EtOH, ace
266	Barium nitride	Ba_3N_2	12047-79-9	439.994	yel-brn cry	>500 dec		4.78		reac H_2O
267	Barium nitrite	$Ba(NO_2)_2$	13465-94-6	229.338	col hex cry	267		3.234	79.5^{25}	
268	Barium nitrite monohydrate	$Ba(NO_2)_2 \cdot H_2O$	7787-38-4	247.353	yel-wh hex cry	217 dec		3.18	79.5^{25}	i EtOH
269	Barium oxalate	BaC_2O_4	516-02-9	225.346	wh powder	400 dec		2.658	0.0075	
270	Barium oxalate monohydrate	$BaC_2O_4 \cdot H_2O$	13463-22-4	243.361	wh cry powder			2.66	0.0075^{20}	s acid
271	Barium oxide	BaO	1304-28-5	153.326	wh-yel powder; cub and hex	1972		5.72(cub)	1.5^{20}	s dil acid, EtOH; i ace
272	Barium perchlorate	$Ba(ClO_4)_2$	13465-95-7	336.227	col hex cry	505		3.20	312^{25}	vs EtOH
273	Barium perchlorate trihydrate	$Ba(ClO_4)_2 \cdot 3H_2O$	10294-39-0	390.273	col cry			2.74	312^{25}	s MeOH; sl EtOH, ace; i eth
274	Barium permanganate	$Ba(MnO_4)_2$	7787-36-2	375.198	brn-viol cry	200 dec		3.77	62.5^{20}	reac EtOH
275	Barium peroxide	BaO_2	1304-29-6	169.326	gray-wh tetr cry	450 dec		4.96	0.091^{20}	reac dil acid
276	Barium metaphosphate	$Ba(PO_3)_2$	13466-20-1	295.271	wh powder	1560				i H_2O; sl acid
277	Barium potassium chromate	$BaK_2(CrO_4)_2$	27133-66-0	447.511	yel hex cry			3.63		vs H_2O
278	Barium pyrophosphate	$Ba_2P_2O_7$	13466-21-2	448.597	wh powder	1430		3.9	0.0088^{20}	s acid
279	Barium selenate	$BaSeO_4$	7787-41-9	280.29	wh rhomb cry	dec		4.75	0.015^{20}	
280	Barium selenide	BaSe	1304-39-8	216.29	cub cry powder	1780		5.02		reac H_2O
281	Barium selenite	$BaSeO_3$	13718-59-7	264.29	solid					i H_2O
282	Barium disilicate	$BaSi_2O_5$	12650-28-1	273.495	wh orth cry	1420		3.70		
283	Barium metasilicate	$BaSiO_3$	13255-26-0	213.411	col rhomb powder	1605		4.40		i H_2O; s acid
284	Barium silicide	$BaSi_2$	1304-40-1	193.498	gray lumps	1180				reac H_2O
285	Barium sodium niobate	$Ba_2Na(NbO_3)_5$	12323-03-4	1002.167	wh orth cry	1437		5.40		i H_2O
286	Barium stannate	$BaSnO_3$	12009-18-6	304.035	cub cry			7.24		sl H_2O
287	Barium stannate trihydrate	$BaSnO_3 \cdot 3H_2O$	12009-18-6*	358.081	wh cry powder					sl H_2O; s acid
288	Barium stearate	$Ba(C_{18}H_{35}O_2)_2$	6865-35-6	704.266	wh powder	160		1.145		i H_2O, EtOH
289	Barium sulfate	$BaSO_4$	7727-43-7	233.391	wh orth cry	1580		4.49	0.00031^{20}	i EtOH
290	Barium sulfide	BaS	21109-95-5	169.393	col cub cry or gray powder	2229		4.3	8.94^{25}	
291	Barium sulfite	$BaSO_3$	7787-39-5	217.391	wh monocl cry	dec		4.44	0.0011^{25}	i EtOH
292	Barium tartrate	$BaC_4H_4O_6$	5908-81-6	285.398	wh cry			2.98		s H_2O; i EtOH
293	Barium tetracyanoplatinate(II) tetrahydrate	$BaPt(CN)_4 \cdot 4H_2O$	13755-32-3	508.54	yel powder or cry			2.076		sl H_2O; i EtOH
294	Barium tetraiodomercurate(II)	$BaHgI_4$	10048-99-4	845.54	yel-red hyg cry					vs H_2O, EtOH
295	Barium thiocyanate	$Ba(SCN)_2$	2092-17-3	253.493	hyg cry				167^{25}	s ace, MeOH, EtOH
296	Barium thiocyanate dihydrate	$Ba(SCN)_2 \cdot 2H_2O$	2092-17-3*	289.524	hyg wh cry				167^{25}	s EtOH
297	Barium thiocyanate trihydrate	$Ba(SCN)_2 \cdot 3H_2O$	68016-36-4	307.539	wh needles; hyg			2.286	167^{25}	s EtOH
298	Barium thiosulfate	BaS_2O_3	35112-53-9	249.457	wh cry powder	220 dec			0.2^{20}	i EtOH
299	Barium thiosulfate monohydrate	$BaS_2O_3 \cdot H_2O$	7787-40-8	267.473	wh cry powder	dec		3.5	0.2	i EtOH
300	Barium titanate	$BaTiO_3$	12047-27-7	233.192	wh tetr cry	1625		6.02		i H_2O
301	Barium tungstate	$BaWO_4$	7787-42-0	385.17	wh tetr cry	1475	1730	5.04	0.0016^{20}	
302	Barium uranium oxide	BaU_2O_7	10380-31-1	725.381	oran-yel powder					i H_2O; s acid
303	Barium orthovanadate	$Ba_3(VO_4)_2$	39416-30-3	641.859	hex cry	707		5.14		
304	Barium zirconate	$BaZrO_3$	12009-21-1	276.549	gray-wh cub cry	2500		5.52		i H_2O, alk; sl acid
305	Berkelium (α form)	Bk	7440-40-6	247	hex	1050		14.78		
306	Berkelium (β form)	Bk	7440-40-6	247	cub cry	986		13.25		
307	Beryllium	Be	7440-41-7	9.012	hex	1287	2471	1.85		s acid, alk
308	Beryllium acetate	$Be(C_2H_3O_2)_2$	543-81-7	127.101	wh cry	60 dec				i H_2O, EtOH
309	Beryllium 2,4-pentanedioate	$Be(CH_3COCHCOCH_3)_2$	10210-64-7	207.228	monocl cry powder	108	270	1.168		i H_2O; vs EtOH, eth
310	Beryllium aluminate	$BeAl_2O_4$	12004-06-7	126.973	orth cry			3.65		
311	Beryllium aluminum metasilicate	$Be_3Al_2(SiO_3)_6$	1302-52-9	537.502	col or grn-yel cry; hex			2.64		
312	Beryllium basic acetate	$Be_4O(C_2H_3O_2)_6$	1332-52-1	406.312	wh cry	285	330	1.25		i H_2O; s eth, os
313	Beryllium boride	BeB_2	12228-40-9	30.634	refrac solid	>1970				
314	Beryllium borohydride	$Be(BH_4)_2$	17440-85-6	36.682	solid	125 dec	subl			reac H_2O
315	Beryllium bromide	$BeBr_2$	7787-46-4	168.820	orth cry; hyg	508	520	3.465		vs H_2O; s EtOH, pyr
316	Beryllium carbide	Be_2C	506-66-1	30.035	red cub cry	>2100 dec		1.90		reac H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
317	Beryllium carbonate tetrahydrate	$BeCO_3 \cdot 4H_2O$	60883-64-9	93.085	wh solid	100 dec			0.36^0	
318	Beryllium carbonate, basic	$Be_3(OH)_2(CO_3)_2$	66104-24-3	181.069	wh pow					i H_2O; s acid, alk
319	Beryllium chloride	$BeCl_2$	7787-47-5	79.917	wh-yel orth cry; hyg	415	482	1.90	71.5^{25}	s EtOH, eth, py; i bz, tol
320	Beryllium fluoride	BeF_2	7787-49-7	47.009	tetr cry or gl; hyg	552	1169	2.1		vs H_2O; sl EtOH
321	Beryllium formate	$Be(CHO_2)_2$	1111-71-3	99.047	powder	>250 dec				reac H_2O; i os
322	Beryllium hydride	BeH_2	7787-52-2	11.028	wh amorp solid	250 dec		0.65		reac H_2O; i eth, tol
323	Beryllium hydrogen phosphate	$BeHPO_4$	13598-15-7	104.991	cry					i H_2O
324	Beryllium hydroxide	$Be(OH)_2$	13327-32-7	43.027	wh powder or cry	≈200 dec		1.92		sl H_2O, alk; s acid
325	Beryllium iodide	BeI_2	7787-53-3	262.821	hyg needles	470	487	4.32		reac H_2O; s EtOH
326	Beryllium nitrate trihydrate	$Be(NO_3)_2 \cdot 3H_2O$	13597-99-4	187.068	yel-wh hyg cry	≈30	dec		107^{20}	s EtOH
327	Beryllium nitride	Be_3N_2	1304-54-7	55.050	gray refrac cry; cub	2200		2.71		reac acid, alk
328	Beryllium oxide	BeO	1304-56-9	25.011	wh hex cry	2577		3.01		i H_2O; sl acid, alk
329	Beryllium perchlorate tetrahydrate	$Be(ClO_4)_2 \cdot 4H_2O$	7787-48-6	279.974	hyg cry	250 dec			198^{25}	
330	Beryllium selenate tetrahydrate	$BeSeO_4 \cdot 4H_2O$	10039-31-3	224.03	orth cry	100 dec		2.03		vs H_2O
331	Beryllium sulfate	$BeSO_4$	13510-49-1	105.076	col tetr cry; hyg	1127		2.5	41.3^{25}	
332	Beryllium sulfate tetrahydrate	$BeSO_4 \cdot 4H_2O$	7787-56-6	177.137	col tetr cry	≈100 dec		1.71	41.3^{25}	i EtOH
333	Beryllium sulfide	BeS	13598-22-6	41.078	col cub cry	dec		2.36		reac hot H_2O
334	Bismuth	Bi	7440-69-9	208.980	gray-wh soft metal	271.406	1564	9.79		s acid
335	Bismuth arsenate	$BiAsO_4$	13702-38-0	347.900	wh mono cry			7.14		i H_2O; sl conc HNO_3
336	Bismuth basic carbonate	$(BiO)_2CO_3$	5892-10-4	509.969	wh powder			6.86		i H_2O; s acid
337	Bismuth tribromide	$BiBr_3$	7787-58-8	448.692	yel cub cry	218	453	5.72		reac H_2O; s dil acid, ace; i EtOH
338	Bismuth trichloride	$BiCl_3$	7787-60-2	315.338	yel-wh cub cry; hyg	230	447	4.75		reac H_2O; s acid, EtOH, ace
339	Bismuth citrate	$BiC_6H_5O_7$	813-93-4	398.080	wh powder			3.458		i H_2O; sl EtOH
340	Bismuth trifluoride	BiF_3	7787-61-3	265.975	wh-gray cub cry	725	900	8.3		i H_2O
341	Bismuth pentafluoride	BiF_5	7787-62-4	303.972	wh tetr needles; hyg	154	230	5.55		reac H_2O
342	Bismuth hydride	BiH_3	18288-22-7	212.004	col gas; unstable	-67	≈17	8.665 g/L		
343	Bismuth hydroxide	$Bi(OH)_3$	10361-43-0	260.002	wh-yel amorp powder			4.962		i H_2O; s acid
344	Bismuth triiodide	BiI_3	7787-64-6	589.693	blk hex cry	408.6	542	5.778	0.00078^{20}	s EtOH
345	Bismuth hexafluoro-2,4-pentanedioate	$Bi(CF_3COCHCOCF_3)_3$		830.132	pow	96				
346	Bismuth molybdate	$Bi_2(MoO_4)_3$	51898-99-8	897.77	monocl cry			5.95		
347	Bismuth nitrate pentahydrate	$Bi(NO_3)_3 \cdot 5H_2O$	10035-06-0	485.071	col tricl cry; hyg	≈75 dec		2.83		reac H_2O; s ace; i EtOH
348	Bismuth oleate	$Bi(C_{18}H_{33}O_2)_3$	52951-38-9	1053.340	soft yel-brn solid					i H_2O; s eth; sl bz
349	Bismuth oxalate	$Bi_2(C_2O_4)_3$	6591-55-5	682.018	wh powder					i H_2O, EtOH; s dil acid
350	Bismuth oxide	Bi_2O_3	1304-76-3	465.959	yel monocl cry or powder	817	1890	8.9		i H_2O; s acid
351	Bismuth oxybromide	BiOBr	7787-57-7	304.883	col tetr cry			8.08		i H_2O, EtOH; s acid
352	Bismuth oxychloride	BiOCl	7787-59-9	260.432	wh tetr cry			7.72		i H_2O
353	Bismuth oxyiodide	BiOI	7787-63-5	351.883	red tetr cry	>300 dec		7.92		i H_2O, EtOH, chl; s HCl
354	Bismuth oxynitrate	$BiONO_3$	10361-46-3	286.985	wh powder	260 dec		4.93		i H_2O, EtOH; s acid
355	Bismuth phosphate	$BiPO_4$	10049-01-1	303.951	monocl cry			6.32		sl H_2O, dil acid; i EtOH
356	Bismuth potassium iodide	K_4BiI_7	41944-01-8	1253.704	red cry					reac H_2O; s alk iodide soln
357	Bismuth selenide	Bi_2Se_3	12068-69-8	654.84	blk hex cry	710 dec		7.5		i H_2O
358	Bismuth stannate pentahydrate	$Bi_2(SnO_3)_3 \cdot 5H_2O$	12777-45-6	1008.162	wh cry					i H_2O
359	Bismuth subnitrate	$Bi_5O(OH)_9(NO_3)_4$	1304-85-4	1461.987	hyg cry pow	260 dec		4.928		i H_2O, EtOH; s dil acid
360	Bismuth sulfate	$Bi_2(SO_4)_3$	7787-68-0	706.152	wh needles or powder	405 dec		5.08		reac H_2O, EtOH
361	Bismuth sulfide	Bi_2S_3	1345-07-9	514.159	blk-brn orth cry	850		6.78		i H_2O; s acid
362	Bismuth telluride	Bi_2Te_3	1304-82-1	800.76	gray hex plates	580		7.74		i H_2O; s EtOH
363	Bismuth tetroxide	Bi_2O_4	12048-50-9	481.959	red-oran powder	305		5.6		reac H_2O
364	Bismuth titanate	$Bi_4(TiO_4)_3$	12048-51-0	1171.516	wh orth cry			7.85		

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
365	Bismuth tungstate	$Bi_2(WO_4)_3$	13595-87-4	1161.47	wh pow					
366	Bismuth vanadate	$BiVO_4$	14059-33-7	323.920	orth cry	trans 500		6.25		i H_2O; s acid
367	Boron	B	7440-42-8	10.811	blk rhomb cry	2075	4000	2.34		i H_2O
368	Diborane	B_2H_6	19287-45-7	27.670	col gas; flam	-165.5	-92.4	1.131 g/L		reac H_2O
369	Tetraborane(10)	B_4H_{10}	18283-93-7	53.323	col gas	-121	18	2.180 g/L		reac H_2O
370	Pentaborane(9)	B_5H_9	19624-22-7	63.126	flam liq	-46.6	60	0.60		reac hot H_2O
371	Pentaborane(11)	B_5H_{11}	18433-84-6	65.142	col liq; unstable	-122	65			reac H_2O
372	Hexaborane(10)	B_6H_{10}	23777-80-2	74.945	col liq	-62.3	108 dec	0.67		reac hot H_2O
373	Hexaborane(12)	B_6H_{12}	12008-19-4	76.961	col liq; unstable	-82.3	≈80			reac H_2O
374	Nonaborane(15)	B_9H_{15}	19465-30-6	112.418	col liq	2.6				
375	Decaborane(14)	$B_{10}H_{14}$	17702-41-9	122.221	wh orth cry	99.6	≈213	0.94		sl H_2O; s EtOH, bz, CS_2, ctc
376	Borane carbonyl	BH_3CO	13205-44-2	41.845	col gas	-137	-64	1.710 g/L		reac H_2O
377	Borazine	$B_3N_3H_6$	6569-51-3	80.501	col liq	-58	53	0.824		reac H_2O
378	Boric acid (orthoboric acid)	H_3BO_3	10043-35-3	61.833	col tricl cry	170.9		1.5	5.80^{25}	sl EtOH
379	Metaboric acid (α form)	HBO_2	13460-50-9	43.818	col orth cry; hyg	176		1.784		s H_2O
380	Metaboric acid (β form)	HBO_2	13460-50-9	43.818	col monocl cry; hyg	201		2.045		s H_2O
381	Metaboric acid (γ form)	HBO_2	13460-50-9	43.818	col cub cry	236		2.487		s H_2O
382	Tetrafluoroboric acid	HBF_4	16872-11-0	87.813	col liq		130 dec	≈1.8		vs H_2O, EtOH
383	Boron arsenide	BAs	12005-69-5	85.733	cub cry	920 dec		5.22		
384	Boron tribromide	BBr_3	10294-33-4	250.523	col liq; hyg	-45	91	2.6		reac H_2O, EtOH
385	Boron carbide	B_4C	12069-32-8	55.255	hard blk cry	2350	>3500	2.50		i H_2O, acid
386	Boron trichloride	BCl_3	10294-34-5	117.169	col liq or gas	-107	12.65	4.789 g/L		reac H_2O, EtOH
387	Tetrachlorodiborane	B_2Cl_4	13701-67-2	163.433	col liq; flam	-92.6	65			reac H_2O
388	Boron trifluoride	BF_3	7637-07-2	67.806	col gas	-126.8	-101	2.772 g/L		s H_2O
389	Tetrafluorodiborane	B_2F_4	13965-73-6	97.616	col gas; flam	-56	-34	3.990 g/L		reac H_2O
390	Boron triiodide	BI_3	13517-10-7	391.524	wh needles	49.7	209.5	3.35		i H_2O
391	Boron nitride	BN	10043-11-5	24.818	wh powder; hex or cub cry	2966		2.18		i H_2O, acid
392	Boron oxide	B_2O_3	1303-86-2	69.620	col gl or hex cry; hyg	450		2.55	2.2^{20}	s EtOH
393	Boron phosphide	BP	20205-91-8	41.785	red cub cry or powder	1125 dec				reac H_2O, acid
394	Boron sulfide	B_2S_3	12007-33-9	117.820	yel amorp solid	softens ≈320		≈1.7		
395	Bromine	Br_2	7726-95-6	159.808	red liq	-7.2	58.8	3.1028		sl H_2O
396	Bromic acid	$HBrO_3$	7789-31-3	128.910	stable only in aq soln					s H_2O
397	Bromine oxide	Br_2O	21308-80-5	175.807	brn solid	-17.5 dec				
398	Bromine dioxide	BrO_2	21255-83-4	111.903	unstable yel cry	≈0 dec				
399	Bromine azide	BrN_3	13973-87-0	121.924	red cry; exp	≈45	exp			
400	Bromine chloride	BrCl	13863-41-7	115.357	unstable red-brn gas	≈-66	≈5 dec	4.715 g/L		reac H_2O; s eth, CS_2
401	Bromine fluoride	BrF	13863-59-7	98.902	unstable red-brn gas	≈-33	≈20 dec	4.043 g/L		
402	Bromine trifluoride	BrF_3	7787-71-5	136.899	col hyg liq	8.77	125.8	2.803		reac H_2O
403	Bromine pentafluoride	BrF_5	7789-30-2	174.896	col liq	-60.5	40.76	2.460		reac H_2O (exp)
404	Bromyl fluoride	BrO_2F	22585-64-4	130.901	col liq	-9	50 dec			reac H_2O
405	Cadmium	Cd	7440-43-9	112.411	silv-wh metal	321.069	767	8.69		i H_2O; reac acid
406	Cadmium acetate	$Cd(C_2H_3O_2)_2$	543-90-8	230.500	col cry	255		2.34		s H_2O, EtOH
407	Cadmium acetate dihydrate	$Cd(C_2H_3O_2)_2 \cdot 2H_2O$	5743-04-4	266.529	wh cry	130 dec		2.01		vs H_2O; s EtOH
408	Cadmium antimonide	CdSb	12014-29-8	234.171	orth cry	456		6.92		
409	Cadmium arsenide	Cd_3As_2	12006-15-4	487.076	gray tetr cry	721		6.25		
410	Cadmium azide	$Cd(N_3)_2$	14215-29-3	196.451	yel-wh orth cry; exp	exp		3.24		
411	Cadmium bromide	$CdBr_2$	7789-42-6	272.219	wh hex powder or flakes; hyg	568	844	5.19	115^{25}	sl ace, eth
412	Cadmium bromide tetrahydrate	$CdBr_2 \cdot 4H_2O$	13464-92-1	344.281	wh-yel cry				115^{25}	s ace, EtOH
413	Cadmium carbonate	$CdCO_3$	513-78-0	172.420	wh hex cry	500 dec		4.258		i H_2O; s acid
414	Cadmium chlorate dihydrate	$Cd(ClO_3)_2 \cdot 2H_2O$	22750-54-5*	315.343	col hyg cry	80 dec		2.28	2.64^{0}	
415	Cadmium chloride	$CdCl_2$	10108-64-2	183.316	rhomb cry; hyg	564	960	4.08	120^{25}	s ace; sl EtOH; i eth
416	Cadmium chloride hemipentahydrate	$CdCl_2 \cdot 2.5H_2O$	7790-78-5	228.354	wh rhomb leaflets			3.327	120^{25}	s ace
417	Cadmium chloride monohydrate	$CdCl_2 \cdot H_2O$	34330-64-8	201.331	wh cry				120^{25}	

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
418	Cadmium chromate	$CdCrO_4$	14312-00-6	228.405	yel orth cry			4.5		i H_2O
419	Cadmium cyanide	$Cd(CN)_2$	542-83-6	164.445	wh cub cry			2.23	1.7^{15}	
420	Cadmium 2-ethylhexanoate	$Cd(C_8H_{15}O_2)_2$	2420-98-6	398.818	pow					
421	Cadmium fluoride	CdF_2	7790-79-6	150.408	cub cry	1110	1748	6.33	4.36^{25}	s acid; i EtOH
422	Cadmium hydroxide	$Cd(OH)_2$	21041-95-2	146.426	wh trig or hex cry	130 dec		4.79	0.00015^{20}	s dil acid
423	Cadmium iodate	$Cd(IO_3)_2$	7790-81-0	462.216	wh powder			6.48	0.091^{25}	s HNO_3
424	Cadmium iodide	CdI_2	7790-80-9	366.220	hex flakes	387	742	5.64	86.2^{25}	s EtOH, eth, ace
425	Cadmium metasilicate	$CdSiO_3$	13477-19-5	188.495	grn monocl cry	1252		5.10		
426	Cadmium molybdate	$CdMoO_4$	13972-68-4	272.35	col tetr cry	≈900 dec		5.4		i H_2O; s acid
427	Cadmium niobate	$Cd_2Nb_2O_7$	12187-14-3	522.631	cub cry	≈1410		6.28		i H_2O
428	Cadmium nitrate	$Cd(NO_3)_2$	10325-94-7	236.420	wh cub cry; hyg	350		3.6	156^{25}	s EtOH
429	Cadmium nitrate tetrahydrate	$Cd(NO_3)_2 \cdot 4H_2O$	10022-68-1	308.482	col orth cry; hyg	59.5		2.45	156^{25}	s EtOH, ace
430	Cadmium oxalate	CdC_2O_4	814-88-0	200.430	wh solid			3.32	0.0060^{25}	
431	Cadmium oxalate trihydrate	$CdC_2O_4 \cdot 3H_2O$	20712-42-9	254.476	wh amorp powder	340 dec			0.0060^{25}	i EtOH; s dil acid
432	Cadmium oxide	CdO	1306-19-0	128.410	brn cub cry		1559 sp	8.15		i H_2O; s dil acid
433	Cadmium perchlorate hexahydrate	$Cd(ClO_4)_2 \cdot 6H_2O$	10326-28-0	419.403	wh hex cry			2.37	191.5^{25}	
434	Cadmium phosphate	$Cd_3(PO_4)_2$	13477-17-3	527.176	pow	≈1500				i H_2O
435	Cadmium phosphide	Cd_3P_2	12014-28-7	399.181	gr tetr needles	700		5.96		s dil HCl
436	Cadmium selenate dihydrate	$CdSeO_4 \cdot 2H_2O$	10060-09-0	291.40	orth cry	100 dec		3.62	70.5^{25}	
437	Cadmium selenide	CdSe	1306-24-7	191.37	wh cub cry	1240		5.81		i H_2O
438	Cadmium sulfate	$CdSO_4$	10124-36-4	208.475	col orth cry	1000		4.69	76.7^{25}	i EtOH
439	Cadmium sulfate monohydrate	$CdSO_4 \cdot H_2O$	7790-84-3	226.490	monocl cry	105		3.79	76.7^{25}	
440	Cadmium sulfate octahydrate	$CdSO_4 \cdot 8H_2O$	15244-35-6	352.597	col monocl cry	40 dec		3.08	76.7^{25}	
441	Cadmium sulfide	CdS	1306-23-6	144.477	yel-oran cub cry	1750		4.83		i H_2O; s acid
442	Cadmium telluride	CdTe	1306-25-8	240.01	brn-blk cub cry	1042		6.2		i H_2O, dil acid
443	Cadmium tetrafluoroborate	$Cd(BF_4)_2$	14486-19-2	286.020	col hyg liq			1.6		vs H_2O, EtOH
444	Cadmium titanate	$CdTiO_3$	12014-14-1	208.276	orth cry			6.5		
445	Cadmium tungstate	$CdWO_4$	7790-85-4	360.25	wh monocl cry			8.0		i H_2O, acid; s NH_4OH
446	Calcium	Ca	7440-70-2	40.078	silv-wh metal	842	1484	1.54		reac H_2O; i bz
447	Calcium acetate	$Ca(C_2H_3O_2)_2$	62-54-4	158.167	wh hyg cry	160 dec		1.50		s H_2O; sl EtOH
448	Calcium acetate monohydrate	$Ca(C_2H_3O_2)_2 \cdot H_2O$	5743-26-0	176.182	wh needles or powder	≈150 dec				s H_2O; sl EtOH
449	Calcium aluminate	$CaAl_2O_4$	12042-68-1	158.039	wh monocl cry	1605		2.98		reac H_2O
450	Calcium aluminate (β form)	$Ca_3Al_2O_6$	12042-78-3	270.193	wh cub cry; refr	1535		3.04		i H_2O
451	Calcium arsenate	$Ca_3(AsO_4)_2$	7778-44-1	398.072	wh powder	dec		3.6	0.0036^{20}	s dil acid
452	Calcium arsenite	$CaAsO_3$	52740-16-6	162.998	wh pow					sl H_2O; s acid
453	Calcium boride	CaB_6	12007-99-7	104.944	refrac solid	2235		2.49		
454	Calcium bromide	$CaBr_2$	7789-41-5	199.886	rhomb cry; hyg	742	1815	3.38	156^{25}	s EtOH, ace
455	Calcium bromide hexahydrate	$CaBr_2 \cdot 6H_2O$	13477-28-6	307.977	wh hyg powder	38 dec		2.29	156^{25}	
456	Calcium carbide	CaC_2	75-20-7	64.099	gray-blk orth cry	2300		2.22		reac H_2O
457	Calcium carbonate (aragonite)	$CaCO_3$	471-34-1	100.087	wh orth cry or powder	825 dec		2.83	0.00066^{20}	s dil acid
458	Calcium carbonate (calcite)	$CaCO_3$	471-34-1	100.087	wh hex cry or powder	1330		2.71	0.00066^{20}	s dil acid
459	Calcium chlorate	$Ca(ClO_3)_2$	10137-74-3	206.979	wh cry	340			197^{25}	
460	Calcium chlorate dihydrate	$Ca(ClO_3)_2 \cdot 2H_2O$	10035-05-9	243.010	wh monocl cry; hyg	100 dec		2.711	197^{25}	s EtOH
461	Calcium chloride	$CaCl_2$	10043-52-4	110.983	wh cub cry or powder; hyg	775	1935.5	2.15	81.3^{25}	vs EtOH
462	Calcium chloride dihydrate	$CaCl_2 \cdot 2H_2O$	10035-04-8	147.014	hyg flakes or powder	175 dec		1.85	81.3^{25}	vs EtOH
463	Calcium chloride hexahydrate	$CaCl_2 \cdot 6H_2O$	7774-34-7	219.074	wh hex cry; hyg	30 dec		1.71	81.3^{25}	
464	Calcium chloride monohydrate	$CaCl_2 \cdot H_2O$	13477-29-7	128.998	wh hyg cry	260 dec		2.24	81.3^{25}	s EtOH
465	Calcium chromate dihydrate	$CaCrO_4 \cdot 2H_2O$	13765-19-0	192.102	yel orth cry			2.50	13.2^{20}	
466	Calcium cyanamide	$CaCN_2$	156-62-7	80.102	col hex cry	≈1340	subl	2.29		reac H_2O
467	Calcium cyanide	$Ca(CN)_2$	592-01-8	92.112	wh rhomb cry; hyg					s H_2O, EtOH
468	Calcium dichromate trihydrate	$CaCr_2O_7 \cdot 3H_2O$	14307-33-6*	310.112	red-oran cry	100 dec		2.37		vs H_2O; reac EtOH; i eth, ctc
469	Calcium 2-ethylhexanoate	$Ca(C_8H_{15}O_2)_2$	136-51-6	326.485	pow					
470	Calcium fluoride	CaF_2	7789-75-5	78.075	wh cub cry or powder	1418	2533.4	3.18	0.0016^{25}	sl acid
471	Calcium formate	$Ca(CHO_2)_2$	544-17-2	130.113	orth cry	300 dec		2.02	16.6^{20}	i EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
472	Calcium hexafluoro-2,4-pentanedioate	$Ca(CF_3COCHCOCF_3)_2$	121012-90-6	454.180	pow	135				
473	Calcium hexafluorosilicate dihydrate	$CaSiF_6 \cdot 2H_2O$	16925-39-6	218.185	col tetr cry			2.25	0.52^{20}	i ace; reac hot H_2O
474	Calcium hydride	CaH_2	7789-78-8	42.094	gray orth cry or powder	1000		1.7		reac H_2O, EtOH
475	Calcium hydrogen phosphate	$CaHPO_4$	7757-93-9	136.057	wh tricl cry	dec		2.92	0.02^{25}	i EtOH
476	Calcium hydrogen phosphate dihydrate	$CaHPO_4 \cdot 2H_2O$	7789-77-7	172.088	monocl cry	≈100 dec		2.31	0.02^{25}	i EtOH; s dil acid
477	Calcium hydroxide	$Ca(OH)_2$	1305-62-0	74.093	soft hex cry			≈2.2	0.160^{20}	s acid
478	Calcium hypochlorite	$Ca(OCl)_2$	7778-54-3	142.982	pow	100		2.350		
479	Calcium hypophosphite	$Ca(H_2PO_2)_2$	7789-79-9	170.055	wh monocl cry	300 dec				s H_2O; i EtOH
480	Calcium iodate	$Ca(IO_3)_2$	7789-80-2	389.883	wh monocl cry			4.52	0.306^{25}	s HNO_3; i EtOH
481	Calcium iodide	CaI_2	10102-68-8	293.887	hyg hex cry	783		3.96	215^{25}	s MeOH, EtOH, ace; i eth
482	Calcium iodide hexahydrate	$CaI_2 \cdot 6H_2O$	71626-98-7	401.978	wh hex needles or powder	42 dec		2.55	215^{25}	vs EtOH
483	Calcium metaborate	$Ca(BO_2)_2$	13701-64-9	125.698	pow				0.13^{20}	
484	Calcium molybdate	$CaMoO_4$	7789-82-4	200.02	wh tetr cry	965 dec		4.35	0.0011^{20}	i EtOH; s conc acid
485	Calcium nitrate	$Ca(NO_3)_2$	10124-37-5	164.087	wh cub cry; hyg	561		2.5	144^{25}	s EtOH, MeOH, ace
486	Calcium nitrate tetrahydrate	$Ca(NO_3)_2 \cdot 4H_2O$	13477-34-4	236.149	wh cry	≈40 dec		1.82	144^{25}	s EtOH, ace
487	Calcium nitride	Ca_3N_2	12013-82-0	148.247	red-brn cub cry	1195		2.67		s H_2O, acid; i EtOH
488	Calcium nitrite	$Ca(NO_2)_2$	13780-06-8	132.089	wh-yel hex cry; hyg			2.23	94.6^{25}	sl EtOH
489	Calcium oxalate	CaC_2O_4	563-72-4	128.097	wh cry powder			2.2	0.00061^{20}	
490	Calcium oxalate monohydrate	$CaC_2O_4 \cdot H_2O$	5794-28-5	146.112	cub cry	200 dec		2.2	0.00061^{20}	s dil acid
491	Calcium oxide	CaO	1305-78-8	56.077	gray-wh cub cry	2898		3.34		reac H_2O; s acid
492	Calcium oxide silicate	Ca_3OSiO_4	12168-85-3	228.317	refrac solid	2150				
493	Calcium 2,4-pentanedioate	$Ca(CH_3COCHCOCH_3)_2$	19372-44-2	238.294	cry	175 dec				
494	Calcium perchlorate	$Ca(ClO_4)_2$	13477-36-6	238.978	wh cry	270 dec		2.65	188^{25}	s EtOH
495	Calcium permanganate	$Ca(MnO_4)_2$	10118-76-0	277.949	purp hyg cry			2.4	331^{20}	reac EtOH
496	Calcium peroxide	CaO_2	1305-79-9	72.077	wh-yel tetr cry; hyg	≈200 dec		2.9		sl H_2O; s acid
497	Calcium phosphate	$Ca_3(PO_4)_2$	7758-87-4	310.177	wh amorp powder	1670		3.14	0.00012^{20}	i EtOH; s dil acid
498	Calcium dihydrogen phosphate monohydrate	$Ca(H_2PO_4)_2 \cdot H_2O$	10031-30-8	252.068	col tricl plates	100 dec		2.220		sl H_2O; s dil acid
499	Calcium phosphide	Ca_3P_2	1305-99-3	182.182	red-brn hyg cry	≈1600		2.51		reac H_2O; i EtOH, eth
500	Calcium propanoate	$Ca(C_3H_5O_2)_2$	4075-81-4	186.219	mono cry, pow					s H_2O; sl MeOH, EtOH; i ace, bz
501	Calcium pyrophosphate	$Ca_2P_2O_7$	7790-76-3	254.099	wh powder	1353		3.09		i H_2O; s dil acid
502	Calcium selenate dihydrate	$CaSeO_4 \cdot 2H_2O$	7790-74-1	219.07	wh monocl cry			2.75	8.3^{18}	
503	Calcium selenide	CaSe	1305-84-6	119.04	wh-brn cub cry	1400 dec		3.8		reac H_2O
504	Calcium metasilicate	$CaSiO_3$	1344-95-2	116.162	wh monocl cry	1540		2.92		i H_2O
505	Calcium silicide	$CaSi_2$	12013-56-8	96.249	gray hex cry	1040		2.50		i cold H_2O; reac hot H_2O; s acid
506	Calcium silicide	CaSi	12013-55-7	68.164	orth cry	1324		2.39		
507	Calcium stearate	$Ca(C_{18}H_{35}O_2)_2$	1592-23-0	607.017	granular pow	180				i H_2O, EtOH
508	Calcium sulfate	$CaSO_4$	7778-18-9	136.142	orth cry	1460		2.96	0.205^{25}	
509	Calcium sulfate dihydrate	$CaSO_4 \cdot 2H_2O$	10101-41-4	172.172	monocl cry or powder	150 dec		2.32	0.205^{20}	i os
510	Calcium sulfate hemihydrate	$CaSO_4 \cdot 0.5H_2O$	10034-76-1	145.149	wh powder				0.205^{25}	
511	Calcium sulfide	CaS	20548-54-3	72.144	wh-yel cub cry; hyg	2524		2.59		sl H_2O; i EtOH
512	Calcium sulfite dihydrate	$CaSO_3 \cdot 2H_2O$	10257-55-3	156.173	wh powder				0.0070^{25}	sl EtOH; s acid
513	Calcium telluride	CaTe	12013-57-9	167.68	wh cub cry	1600 dec		4.87		
514	Calcium tetrahydroaluminate	$Ca(AlH_4)_2$	16941-10-9	102.105	gray powder; flam					reac H_2O; s thf; i eth, bz
515	Calcium thiocyanate tetrahydrate	$Ca(SCN)_2 \cdot 4H_2O$	2092-16-2	228.306	hygr cry	160 dec				vs H_2O; s EtOH, ace
516	Calcium thiosulfate hexahydrate	$CaS_2O_3 \cdot 6H_2O$	10124-41-1	260.300	tricl cry	45 dec		1.87		s H_2O; i EtOH
517	Calcium titanate	$CaTiO_3$	12049-50-2	135.943	cub cry	1980		3.98		
518	Calcium tungstate	$CaWO_4$	7790-75-2	287.92	wh tetr cry	1620		6.06	0.2^{18}	s hot acid
519	Calcium zirconate	$CaZrO_3$	12013-47-7	179.300	pow	2550				
520	Californium	Cf	7440-71-3	251	hex or cub metal	900		15.1		
521	Carbon (diamond)	C	7782-40-3	12.011	col cub cry	4440 (12.4 GPa)		3.513		i H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
522	Carbon (graphite)	C	7782-42-5	12.011	soft blk hex cry	4489 tp (10.3 MPa)	3825 sp	2.2		i H_2O
523	Carbon (fullerene-C_{60})	C_{60}	99685-96-8	720.642	yel needles or plates	>280				s os
524	Carbon (fullerene-C_{70})	C_{70}	115383-22-7	840.749	red-brn solid	>280				s bz, tol
525	Fullerene fluoride	$C_{60}F_{60}$	134929-59-2	1860.546	col plates	287				vs ace; s thf; i chl
526	Carbon monoxide	CO	630-08-0	28.010	col gas	-205.02	-191.5	1.145 g/L		sl H_2O; s chl, EtOH
527	Carbon dioxide	CO_2	124-38-9	44.010	col gas	-56.56 tp	-78.4 sp	1.799 g/L		s H_2O
528	Carbon diselenide	CSe_2	506-80-9	169.93	yel liq	-43.7	125.5	2.6626		i H_2O; vs ctc, tol
529	Carbon disulfide	CS_2	75-15-0	76.143	col or yel liq	-112.1	46	1.2555		i H_2O; vs EtOH, bz, os
530	Carbon oxyselenide	COSe	1603-84-5	106.97	col gas; unstable	-124.4	-21.7	4.372 g/L		reac H_2O
531	Carbon oxysulfide	COS	463-58-1	60.076	col gas	-138.8	-50	2.456 g/L		s H_2O, EtOH
532	Carbon sulfide selenide	CSSe	5951-19-9	123.04	yel liq	-85	84.5	1.99		i H_2O
533	Carbon sulfide telluride	CSTe	10340-06-4	171.68	red-yel liq; unstable	-54	20 dec			reac H_2O
534	Carbon suboxide	C_3O_2	504-64-3	68.031	col gas	-111.3	6.8	2.781 g/L		reac H_2O
535	Carbon subsulfide	C_3S_2	627-34-9	100.164	red liq	-1	90 dec	1.27		reac H_2O
536	Carbonyl bromide	$COBr_2$	593-95-3	187.818	col liq		64.5	2.5		reac H_2O
537	Carbonyl chloride	$COCl_2$	75-44-5	98.915	col gas	-127.78	8	4.043 g/L		sl H_2O; s bz, tol
538	Carbonyl fluoride	COF_2	353-50-4	66.007	col gas	-111.26	-84.57	2.698 g/L		reac H_2O
539	Cyanogen	C_2N_2	460-19-5	52.034	col gas	-27.83	-21.1	2.127 g/L		sl H_2O, eth; s EtOH
540	Cyanogen bromide	BrCN	506-68-3	105.922	wh hyg needles	52	61.5	2.005		s H_2O, EtOH, eth
541	Cyanogen chloride	ClCN	506-77-4	61.470	col gas	-6.55	13	2.513 g/L		s H_2O, EtOH, eth
542	Cyanogen fluoride	FCN	1495-50-7	45.016	col gas	-82	-46	1.840 g/L		
543	Cyanogen iodide	ICN	506-78-5	152.922	col needles	146.7		1.84		s H_2O, EtOH, eth
544	Cerium	Ce	7440-45-1	140.116	silv metal; cub or hex	798	3443	6.770		s dil acid
545	Cerium boride	CeB_6	12008-02-5	204.982	blue refrac solid; hex	2550		4.87		i H_2O, HCl
546	Cerium carbide	CeC_2	12012-32-7	164.137	red hex cry	2250		5.47		reac H_2O
547	Cerium nitride	CeN	25764-08-3	154.123	refrac cub cry	2557		7.89		
548	Cerium silicide	$CeSi_2$	12014-85-6	196.287	tetr cry	1620		5.31		i H_2O
549	Cerium(II) hydride	CeH_2	13569-50-1	142.132	cub cry			5.45		reac H_2O
550	Cerium(II) iodide	CeI_2	19139-47-0	393.925	bronze cry	808				
551	Cerium(II) sulfide	CeS	12014-82-3	172.182	yel cub cry	2445		5.9		
552	Cerium(III) bromide	$CeBr_3$	14457-87-5	379.828	wh hex cry; hyg	733	1457			s H_2O
553	Cerium(III) bromide heptahydrate	$CeBr_3 \cdot 7H_2O$	7789-56-2	505.935	col hyg needles	732				s H_2O, EtOH
554	Cerium(III) carbide	Ce_2C_3	12115-63-8	316.264	yel-brn cub cry	1505		6.9		
555	Cerium(III) carbonate hydrate	$Ce_2(CO_3)_3 \cdot 5H_2O$	72520-94-6	550.335	wh powder					i H_2O; s dil acid
556	Cerium(III) chloride	$CeCl_3$	7790-86-5	246.474	wh hex cry	817		3.97		s H_2O, EtOH
557	Cerium(III) chloride heptahydrate	$CeCl_3 \cdot 7H_2O$	18618-55-8	372.581	yel orth cry; hyg	90 dec				vs H_2O, EtOH
558	Cerium(III) fluoride	CeF_3	7758-88-5	197.111	wh hex cry; hyg	1430		6.157		i H_2O
559	Cerium(III) iodide	CeI_3	7790-87-6	520.829	yel orth cry; hyg	766				s H_2O
560	Cerium(III) iodide nonahydrate	$CeI_3 \cdot 9H_2O$	7790-87-6*	682.967	wh-red cry					vs H_2O; s EtOH
561	Cerium(III) nitrate hexahydrate	$Ce(NO_3)_3 \cdot 6H_2O$	10108-73-3*	434.222	col-red cry	150 dec			176^{25}	s ace
562	Cerium(III) oxide	Ce_2O_3	1345-13-7	328.230	yel-grn cub cry	2210	3730	6.2		i H_2O; s acid
563	Cerium(III) sulfate octahydrate	$Ce_2(SO_4)_3 \cdot 8H_2O$	13454-94-9	712.545	wh orth cry	≈250 dec		2.87		s H_2O
564	Cerium(III) sulfide	Ce_2S_3	12014-93-6	376.430	red cub cry	2450		5.02		i H_2O
565	Cerium(IV) fluoride	CeF_4	10060-10-3	216.110	wh hyg powder	≈600 dec		4.77		i H_2O
566	Cerium(IV) oxide	CeO_2	1306-38-3	172.115	wh-yel powder; cub	2400		7.65		i H_2O, dil acid
567	Cerium(IV) sulfate tetrahydrate	$Ce(SO_4)_2 \cdot 4H_2O$	10294-42-5	404.305	yel-oran orth cry	180 dec		3.91	9.66^{20}	
568	Cesium	Cs	7440-46-2	132.905	silv-wh metal	28.5	671	1.93		reac H_2O
569	Cesium acetate	$CsC_2H_3O_2$	3396-11-0	191.949	hyg lumps	194			10^{11}	
570	Cesium amide	$CsNH_2$	22205-57-8	148.928	wh tetr cry			3.70		
571	Cesium azide	CsN_3	22750-57-8	174.925	hyg tetr cry; exp	326		≈3.5	22^{40}	
572	Cesium bromate	$CsBrO_3$	13454-75-6	260.807	col hex cry			4.11	3.83^{25}	
573	Cesium bromide	CsBr	7787-69-1	212.809	wh cub cry; hyg	636	≈1300	4.43	123^{25}	s EtOH; i ace
574	Cesium carbonate	Cs_2CO_3	534-17-8	325.820	wh monocl cry; hyg	792		4.24	261^{15}	s EtOH, eth

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
575	Cesium chlorate	$CsClO_3$	13763-67-2	216.356	col hex cry			3.57	7.78^{25}	
576	Cesium chloride	CsCl	7647-17-8	168.358	wh cub cry; hyg	645	1297	3.988	191^{25}	s EtOH
577	Cesium cyanide	CsCN	21159-32-0	158.923	wh cub cry; hyg	350		3.34		vs H_2O
578	Cesium fluoride	CsF	13400-13-0	151.903	wh cub cry; hyg	703		4.64	573^{25}	s MeOH; i diox, py
579	Cesium formate	$CsCHO_2$	3495-36-1	177.923	wh cry			1.017		vs H_2O
580	Cesium hydride	CsH	58724-12-2	133.913	wh cub cry; flam	≈170 dec		3.42		reac H_2O
581	Cesium hydrogen carbonate	$CsHCO_3$	15519-28-5	193.922	rhom cry	175 dec			209^{15}	s EtOH
582	Cesium hydrogen fluoride	$CsHF_2$	12280-52-3	171.910	tetr cry	170		3.86		
583	Cesium hydrogen sulfate	$CsHSO_4$	7789-16-4	229.977	col rhom prisms	dec		3.352		s H_2O
584	Cesium hydroxide	CsOH	21351-79-1	149.912	wh-yel hyg cry	342.3		3.68	300^{30}	s EtOH
585	Cesium iodate	$CsIO_3$	13454-81-4	307.807	wh mono cry			4.85	2.6^{25}	
586	Cesium iodide	CsI	7789-17-5	259.809	col cub cry; hyg	621	≈1280	4.51	84.8^{25}	s EtOH, MeOH, ace
587	Cesium metaborate	$CsBO_2$	92141-86-1	175.715	cub cry	732		≈3.7		
588	Cesium nitrate	$CsNO_3$	7789-18-6	194.910	wh hex or cub cry	414		3.66	27.9^{25}	s ace; sl EtOH
589	Cesium oxide	Cs_2O	20281-00-9	281.810	yel-oran hex cry	490		4.65		vs H_2O
590	Cesium superoxide	CsO_2	12018-61-0	164.904	yel tetr cry	432		3.77		reac H_2O
591	Cesium perchlorate	$CsClO_4$	13454-84-7	232.356	wh orth cry; hyg	250		3.327	2.00^{25}	
592	Cesium periodate	$CsIO_4$	13478-04-1	323.807	wh rhom prisms			4.26	2.2^{15}	
593	Cesium sulfate	Cs_2SO_4	10294-54-9	361.875	wh orth cry or hex prisms; hyg	1005		4.24	182^{25}	i EtOH, ace, py
594	Cesium sulfide tetrahydrate	$Cs_2S \cdot 4H_2O$	12214-16-3	369.939	wh hyg cry					vs H_2O
595	Chlorine	Cl_2	7782-50-5	70.905	grn-yel gas	-101.5	-34.04	2.898 g/L		sl H_2O
596	Hypochlorous acid	HOCl	7790-92-3	52.460	grn-yel; stable only in aq soln					s H_2O
597	Perchloric acid	$HClO_4$	7601-90-3	100.459	col hyg liq	-112	≈90 dec	1.77		s H_2O
598	Chlorine monoxide	Cl_2O	7791-21-1	86.904	yel-brn gas	-120.6	2.2	3.552 g/L		vs H_2O
599	Chlorine dioxide	ClO_2	10049-04-4	67.452	oran-grn gas	-59	11	2.757 g/L		sl H_2O
600	Chlorine trioxide	Cl_2O_3	17496-59-2	118.903	dark brn solid	exp <25				
601	Chlorine hexoxide	Cl_2O_6	12442-63-6	166.901	red liq	3.5	≈200			reac H_2O
602	Chlorine heptoxide	Cl_2O_7	10294-48-1	182.901	col oily liq; exp	-91.5	82	1.9		reac H_2O
603	Chlorine fluoride	ClF	7790-89-8	54.451	col gas	-155.6	-101.1	2.226 g/L		reac H_2O
604	Chlorine trifluoride	ClF_3	7790-91-2	92.448	gas	-76.34	11.75	3.779 g/L		reac H_2O
605	Chlorine trifluoride oxide	$ClOF_3$	30708-80-6	108.447	col liq	-42	29			reac H_2O
606	Chlorine pentafluoride	ClF_5	13637-63-3	130.445	col gas	-103	-13.1	5.332 g/L		
607	Chloryl fluoride	ClO_2F	13637-83-7	86.450	col gas	-15	-6	3.534 g/L		reac H_2O
608	Chloryl trifluoride	ClO_2F_3	38680-84-1	124.447	col gas	-81	-22	5.087 g/L		reac H_2O
609	Perchloryl fluoride	ClO_3F	7616-94-6	102.449	col gas	-147	-46.75	4.187 g/L		
610	Chlorine perchlorate	$ClOClO_3$	27218-16-2	134.903	unstable liq	-117	≈25 dec	1.81^{0}		
611	Chromium	Cr	7440-47-3	51.996	blue-wh metal; cub	1907	2671	7.15		reac dil acid
612	Chromium antimonide	CrSb	12053-12-2	173.756	hex cry	1110		7.11		
613	Chromium arsenide	Cr_2As	12254-85-2	178.914	tetr cry			7.04		
614	Chromium boride	CrB	12006-79-0	62.807	refrac orth cry	2100		6.1		
615	Chromium boride	CrB_2	12007-16-8	73.618	refrac solid; hex	2200		5.22		
616	Chromium boride	Cr_5B_3	12007-38-4	292.414	tetr cry	1900		6.10		
617	Chromium carbide	Cr_3C_2	12012-35-0	180.009	gray orth cry	1895		6.68		
618	Chromium carbonyl	$Cr(CO)_6$	13007-92-6	220.056	col orth cry	130 dec	subl	1.77		i H_2O, EtOH; s eth, chl
619	Chromium nitride	Cr_2N	12053-27-9	117.999	hex cry	1650		6.8		
620	Chromium nitride	CrN	24094-93-7	66.003	gray cub cry	1080 dec		5.9		
621	Chromium phosphide	CrP	26342-61-0	82.970	orth cry			5.25		
622	Chromium selenide	CrSe	12053-13-3	130.96	hex cry	≈1500		6.1		
623	Chromium silicide	Cr_3Si	12018-36-9	184.074	cub cry	1770		6.4		
624	Chromium silicide	$CrSi_2$	12018-09-6	108.167	gray hex cry	1490		4.91		
625	Chromium(II) acetate monohydrate	$Cr(C_2H_3O_2)_2 \cdot H_2O$	628-52-4*	188.100	red monocl cry			1.79		sl H_2O
626	Chromium(II) bromide	$CrBr_2$	10049-25-9	211.804	wh monocl cry; aq soln blue	842		4.236		s H_2O, EtOH
627	Chromium(II) chloride	$CrCl_2$	10049-05-5	122.901	hyg needles; aq soln blue	814	1300	2.88		s H_2O
628	Chromium(II) chloride tetrahydrate	$Cr(H_2O)_4Cl_2 \cdot 4H_2O$	13931-94-7	267.023	blue hyg cry	51 dec				s H_2O
629	Chromium(II) fluoride	CrF_2	10049-10-2	89.993	blue-grn monocl cry	894		3.79		sl H_2O; i EtOH
630	Chromium(II) iodide	CrI_2	13478-28-9	305.805	red-brn cry; hyg	868		5.1		

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
631	Chromium(II) oxalate monohydrate	$CrC_2O_4 \cdot H_2O$	814-90-4*	158.030	yel-grn powder			2.468		sl H_2O
632	Chromium(II) sulfate pentahydrate	$CrSO_4 \cdot 5H_2O$	13825-86-0	238.136	blue cry				21^0	s dil acid; sl EtOH; i ace
633	Chromium(II,III) oxide	Cr_3O_4	12018-34-7	219.986	cub cry			6.1		
634	Chromium(III) acetate	$Cr(C_2H_3O_2)_3$	1066-30-4	229.127	bl-grn pwd					sl H_2O
635	Chromium(III) acetate hexahydrate	$Cr(C_2H_3O_2)_3 \cdot 6H_2O$	1066-30-4*	337.220	blue needles					s H_2O
636	Chromium(III) bromide	$CrBr_3$	10031-25-1	291.708	dark grn hex cry	1130		4.68		s hot H_2O
637	Chromium(III) bromide hexahydrate (β)	$Cr(H_2O)_6Br_3$	10031-25-1*	399.799	viol hyg cry					s H_2O; i EtOH, eth
638	Chromium(III) bromide hexahydrate (α)	$CrBr_3(H_2O)_4 \cdot 2H_2O$	18721-05-6	399.799	grn hyg cry					s H_2O, EtOH
639	Chromium(III) chloride	$CrCl_3$	10025-73-7	158.354	purp hex plates	1152	1300 dec	2.87		sl H_2O
640	Chromium(III) chloride hexahydrate	$[CrCl_2(H_2O)_4]Cl \cdot 2H_2O$	10060-12-5	266.445	grn monocl cry; hyg					s H_2O, EtOH; sl ace; i eth
641	Chromium(III) fluoride	CrF_3	7788-97-8	108.991	grn needles	1400		3.8		i H_2O, EtOH
642	Chromium(III) fluoride trihydrate	$CrF_3 \cdot 3H_2O$	16671-27-5	163.037	grn hex cry			2.2		sl H_2O
643	Chromium(III) hydroxide trihydrate	$Cr(OH)_3 \cdot 3H_2O$	1308-14-1	157.063	blue-grn powder					i H_2O; s acid
644	Chromium(III) iodide	CrI_3	13569-75-0	432.709	dark grn hex cry	500 dec		5.32		sl H_2O
645	Chromium(III) nitrate	$Cr(NO_3)_3$	13548-38-4	238.011	grn hyg powder	>60 dec				vs H_2O
646	Chromium(III) nitrate nonahydrate	$Cr(NO_3)_3 \cdot 9H_2O$	7789-02-8	400.148	grn-blk monocl cry	66.3	>100 dec	1.80		vs H_2O
647	Chromium(III) oxide	Cr_2O_3	1308-38-9	151.990	grn hex cry	2329	≈3000	5.22		i H_2O, EtOH; sl acid, alk
648	Chromium(III) 2,4-pentanedioate	$Cr(CH_3COCHCOCH_3)_3$	21679-31-2	349.320	red monocl cry	208	345	1.34		i H_2O; s bz
649	Chromium(III) phosphate	$CrPO_4$	7789-04-0	146.967	blue orth cry	>1800		4.6		i H_2O, acid, aqua regia
650	Chromium(III) phosphate hemiheptahydrate	$CrPO_4 \cdot 3.5H_2O$	84359-31-9	210.021	blue-grn powder			2.15		i H_2O; s acid
651	Chromium(III) phosphate hexahydrate	$CrPO_4 \cdot 6H_2O$	84359-31-9	255.059	viol cry	>500 dec		2.121		i H_2O; s acid, alk
652	Chromium(III) potassium sulfate dodecahydrate	$CrK(SO_4)_2 \cdot 12H_2O$	7788-99-0	499.405	viol-blk cub cry	89 dec		1.83		s H_2O; i EtOH
653	Chromium(III) sulfate	$Cr_2(SO_4)_3$	10101-53-8	392.183	red-brn hex cry			3.1	64^{25}	vs acid
654	Chromium(III) sulfide	Cr_2S_3	12018-22-3	200.190	brn-blk hex cry			3.8		
655	Chromium(III) telluride	Cr_2Te_3	12053-39-3	486.79	hex cry	≈1300		7.0		
656	Chromium(IV) chloride	$CrCl_4$	15597-88-3	193.807	gas, stable at high temp		>600 dec	7.922 g/L		
657	Chromium(IV) fluoride	CrF_4	10049-11-3	127.990	grn cry	277				
658	Chromium(IV) oxide	CrO_2	12018-01-8	83.995	brn-blk tetr powder	≈400 dec		4.89		i H_2O; s acid
659	Chromium(V) fluoride	CrF_5	14884-42-5	146.988	red orth cry	34	117			
660	Chromium(VI) fluoride	CrF_6	13843-28-2	165.986	yel solid; stable at low temp	-100 dec				
661	Chromium(VI) oxide	CrO_3	1333-82-0	99.994	red orth cry	197	≈250 dec	2.7	169^{25}	
662	Chromic acid	H_2CrO_4	7738-94-5	118.010	aq soln only					s H_2O
663	Chromyl chloride	CrO_2Cl_2	14977-61-8	154.900	red liq	-96.5	117	1.91		reac H_2O; s ctc, chl, bz
664	Cobalt	Co	7440-48-4	58.933	gray metal; hex or cub	1495	2927	8.86		s dil acid
665	Cobalt antimonide	CoSb	12052-42-5	180.693	hex cry	1202		8.8		
666	Cobalt arsenic sulfide	CoAsS	12254-82-9	165.921	silv-wh solid			≈6.1		
667	Cobalt arsenide	CoAs	27016-73-5	133.855	orth cry	1180		8.22		
668	Cobalt arsenide	$CoAs_2$	12044-42-7	208.776	monocl cry			7.2		
669	Cobalt arsenide	$CoAs_3$	12256-04-1	283.698	cub cry	942		6.84		
670	Cobalt boride	Co_2B	12045-01-1	128.677	refrac solid	1280		8.1		
671	Cobalt boride	CoB	12006-77-8	69.744	refrac solid	1460		7.25		reac H_2O, HNO_3
672	Cobalt carbonyl	$Co_2(CO)_8$	10210-68-1	341.947	oran cry	51 dec		1.78		i H_2O; s EtOH, eth, CS_2
673	Cobalt phosphide	Co_2P	12134-02-0	148.840	gray needles	1386		6.4		i H_2O; s HNO_3
674	Cobalt silicide	$CoSi_2$	12017-12-8	115.104	gray cub cry	1326		4.9		s hot HCl
675	Cobalt disulfide	CoS_2	12013-10-4	123.065	cub cry			4.3		
676	Cobalt dodecacarbonyl	$Co_4(CO)_{12}$	17786-31-1	571.854	blk cry	60 dec		2.09		
677	Cobalt(II) acetate	$Co(C_2H_3O_2)_2$	71-48-7	177.022	pink cry					vs H_2O; s EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
678	Cobalt(II) acetate tetrahydrate	$Co(C_2H_3O_2)_2 \cdot 4H_2O$	6147-53-1	249.082	red monocl cry			1.705		s H_2O, EtOH, dil acid
679	Cobalt(II) aluminate	$CoAl_2O_4$	13820-62-7	176.894	blue cub cry			4.37		i H_2O
680	Cobalt(II) arsenate octahydrate	$Co_3(AsO_4)_2 \cdot 8H_2O$	24719-19-5	598.760	red monocl needles	400 dec	1000 dec	3.0		i H_2O; s dil acid
681	Cobalt(II) bromate hexahydrate	$Co(BrO_3)_2 \cdot 6H_2O$	13476-01-2	422.829	viol cry			≈2.5		vs H_2O
682	Cobalt(II) bromide	$CoBr_2$	7789-43-7	218.741	grn hex cry; hyg	678		4.91	113.2^{20}	s MeOH, EtOH, ace
683	Cobalt(II) bromide hexahydrate	$CoBr_2 \cdot 6H_2O$	13762-12-4	326.832	red hyg cry	47 dec	100 dec	2.46	113.2	
684	Cobalt(II) carbonate	$CoCO_3$	513-79-1	118.942	pink rhomb cry			4.2	0.00014^{20}	i EtOH
685	Cobalt(II) chloride	$CoCl_2$	7646-79-9	129.838	blue hyg leaflets	740	1049	3.36	56.2^{25}	s EtOH, eth, ace, py
686	Cobalt(II) chloride dihydrate	$CoCl_2 \cdot 2H_2O$	16544-92-6	165.869	viol-blue cry			2.477	56.2^{25}	
687	Cobalt(II) chloride hexahydrate	$CoCl_2 \cdot 6H_2O$	7791-13-1	237.929	pink-red monocl cry	87 dec		1.924	56.2^{25}	s EtOH, ace, eth
688	Cobalt(II) chromate	$CoCrO_4$	24613-38-5	174.927	yel-brn orth cry			≈4.0		i H_2O; s acid
689	Cobalt(II) chromite	$CoCr_2O_4$	13455-25-9	226.923	blue-grn cub cry			5.14		i H_2O, conc acid
690	Cobalt(II) cyanide	$Co(CN)_2$	542-84-7	110.967	blue hyg cry			1.872		i H_2O
691	Cobalt(II) cyanide dihydrate	$Co(CN)_2 \cdot 2H_2O$	20427-11-6	146.998	pink-brn needles					i H_2O, acid
692	Cobalt(II) ferricyanide	$Co_3[Fe(CN)_6]_2$	14049-81-1	600.699	red needles					i H_2O, HCl; s NH_4OH
693	Cobalt(II) fluoride	CoF_2	10026-17-2	96.930	red tetr cry	1127	≈1400	4.46	1.4^{25}	s acid
694	Cobalt(II) fluoride tetrahydrate	$CoF_2 \cdot 4H_2O$	13817-37-3	168.992	red orth cry	dec		2.22	1.4^{25}	
695	Cobalt(II) formate dihydrate	$Co(CHO_2)_2 \cdot 2H_2O$	6424-20-0	184.998	red cry powder	140 dec		2.13	5.03^{20}	i EtOH
696	Cobalt(II) hexafluoro-2,4-pentanedioate	$Co(CF_3COCHCOCF_3)_2$	19648-83-0	473.035	pow	197				
697	Cobalt(II) hexafluorosilicate hexahydrate	$CoSiF_6 \cdot 6H_2O$	12021-68-0	309.100	pale red cry			2.087	76.8^{22}	
698	Cobalt(II) hydroxide	$Co(OH)_2$	21041-93-0	92.948	blue-grn cry	≈160 dec		3.60		sl H_2O; s acid
699	Cobalt(II) iodate	$Co(IO_3)_2$	13455-28-2	408.738	blk-viol needles	200 dec		5.09	0.46^{20}	
700	Cobalt(II) iodide	CoI_2	15238-00-3	312.742	blk hex cry; hyg	520		5.60	203^{25}	
701	Cobalt(II) iodide hexahydrate	$CoI_2 \cdot 6H_2O$	15238-00-3*	420.833	red hex prisms	130 dec		2.90	203^{25}	s EtOH, eth, ace
702	Cobalt(II) titanate	$CoTiO_3$	12017-01-5	154.798	grn rhomb cry			5.0		
703	Cobalt(II) molybdate	$CoMoO_4$	13762-14-6	218.87	blk monocl cry	1040		4.7		
704	Cobalt(II) nitrate	$Co(NO_3)_2$	10141-05-6	182.942	pale red powder	100 dec		2.49	103^{25}	
705	Cobalt(II) nitrate hexahydrate	$Co(NO_3)_2 \cdot 6H_2O$	10026-22-9	291.034	red monocl cry; hyg	≈55		1.88	103^{25}	s EtOH
706	Cobalt(II) oxalate	CoC_2O_4	814-89-1	146.952	pink powder	250 dec		3.02	0.0037^{20}	s acid, NH_4OH
707	Cobalt(II) oxalate dihydrate	$CoC_2O_4 \cdot 2H_2O$	5965-38-8	182.982	pink needles	dec			0.0037	sl acid; s NH_4OH
708	Cobalt(II) oxide	CoO	1307-96-6	74.932	gray cub cry	1830		6.44		i H_2O; s acid
709	Cobalt(II) perchlorate	$Co(ClO_4)_2$	13455-31-7	257.833	red needles			3.33	113^{25}	i EtOH, ace
710	Cobalt(II) phosphate octahydrate	$Co_3(PO_4)_2 \cdot 8H_2O$	10294-50-5	510.865	pink amorp powder			2.77		i H_2O; s acid
711	Cobalt(II) potassium sulfate hexahydrate	$CoK_2(SO_4)_2 \cdot 6H_2O$	10026-20-7	437.349	red monocl cry	75 dec		2.22		vs H_2O
712	Cobalt(II) selenate pentahydrate	$CoSeO_4 \cdot 5H_2O$	14590-19-3	291.97	red tricl cry	dec		2.51	55^{15}	
713	Cobalt(II) selenide	CoSe	1307-99-9	137.89	yel hex cry	1055		7.65		i H_2O, alk; s aqua regia
714	Cobalt(II) selenite dihydrate	$CoSeO_3 \cdot 2H_2O$	19034-13-0	221.92	blue-red powder					i H_2O
715	Cobalt(II) orthosilicate	Co_2SiO_4	12017-08-2	209.950	red-viol orth cry	1345		4.63		i H_2O; s dil HCl
716	Cobalt(II) stannate	Co_2SnO_4	12139-93-4	300.574	grn-blue cub cry			6.30		i H_2O; s alk
717	Cobalt(II) sulfate	$CoSO_4$	10124-43-3	154.997	red orth cry	>700		3.71	38.3^{25}	
718	Cobalt(II) sulfate heptahydrate	$CoSO_4 \cdot 7H_2O$	10026-24-1	281.103	pink monocl cry	41 dec		2.03	38.3^{25}	sl EtOH, MeOH
719	Cobalt(II) sulfate monohydrate	$CoSO_4 \cdot H_2O$	13455-34-0	173.012	red monocl cry			3.08	38.3^{25}	
720	Cobalt(II) sulfide	CoS	1317-42-6	90.999	blk amorp powder	1182		5.45		i H_2O; s acid
721	Cobalt(II) telluride	CoTe	12017-13-9	186.53	hex cry			≈8.8		
722	Cobalt(II) thiocyanate	$Co(SCN)_2$	3017-60-5	175.099	yel-brn pow				103^{25}	s EtOH, MeOH, ace, eth
723	Cobalt(II) thiocyanate trihydrate	$Co(SCN)_2 \cdot 3H_2O$	97126-35-7	229.145	viol rhomb cry				103^{25}	s EtOH, eth, ace
724	Cobalt(II) tungstate	$CoWO_4$	12640-47-0	306.77	blue monocl cry			≈7.8		i H_2O; s hot conc acid
725	Cobalt(II,III) oxide	Co_3O_4	1308-06-1	240.798	blk cub cry	900 dec		6.11		i H_2O; s acid, alk
726	Cobalt(III) acetate	$Co(C_2H_3O_2)_3$	917-69-1	236.064	grn hyg cry	100 dec				s H_2O, EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
727	Cobalt(III) ammonium tetranitrodiammine	$NH_4[Co(NH_3)_2(NO_2)_4]$	13600-89-0	295.054	red-brn orth cry			1.97		s H_2O
728	Cobalt(III) fluoride	CoF_3	10026-18-3	115.928	brn hex cry	927		3.88		reac H_2O
729	Cobalt(III) hexammine chloride	$Co(NH_3)_6Cl_3$	10534-89-1	267.474	red monocl cry			1.71		s H_2O; i EtOH
730	Cobalt(III) hydroxide	$Co(OH)_3$	1307-86-4	109.955	brn powder	dec		≈4		i H_2O; s acid
731	Cobalt(III) nitrate	$Co(NO_3)_3$	15520-84-0	244.948	grn cub cry; hyg			≈3.0		s H_2O; reac os
732	Cobalt(III) oxide	Co_2O_3	1308-04-9	165.864	gray-blk powder	895 dec		5.18		i H_2O; s conc acid
733	Cobalt(III) oxide monohydrate	$Co_2O_3 \cdot H_2O$	12016-80-7	183.880	brn-blk hex cry	150 dec				i H_2O; s acid
734	Cobalt(III) potassium nitrite sesquihydrate	$CoK_3(NO_2)_6 \cdot 1.5H_2O$	13782-01-9*	479.284	yel cub cry			2.6		sl H_2O; reac acid; i EtOH
735	Cobalt(III) sulfide	Co_2S_3	1332-71-4	214.064	blk cub cry			4.8		reac acid
736	Cobalt(III) titanate	Co_2TiO_4	12017-38-8	229.731	grn-blk cub cry			5.1		s conc HCl
737	Copper	Cu	7440-50-8	63.546	red metal; cub	1084.62	2562	8.96		sl dil acid
738	Copper(II) 2,4-pentanedioate	$Cu(CH_3COCHCOCH_3)_2$	13395-16-9	261.762	blue powder	284 dec	subl			sl H_2O; s chl
739	Copper nitride	Cu_3N	1308-80-1	204.645	cub cry	300 dec		5.84		
740	Copper(II) 2-ethylhexanoate	$Cu(C_8H_{15}O_2)_2$	149-11-1	349.953	pow	252 dec				
741	Copper phosphide	CuP_2	12019-11-3	125.494	monocl cry	≈900		4.20		
742	Copper silicide	Cu_5Si	12159-07-8	345.816	solid	825				
743	Copper(I) acetate	$CuC_2H_3O_2$	598-54-9	122.590	col cry	dec	subl			reac H_2O
744	Copper(I) acetylide	Cu_2C_2	1117-94-8	151.113	red amorp powder; exp					
745	Copper(I) azide	CuN_3	14336-80-2	105.566	tetr cry; exp					
746	Copper(I) bromide	CuBr	7787-70-4	143.450	wh cub cry; hyg	497	1345	4.98	0.0012^{20}	i ace
747	Copper(I) chloride	CuCl	7758-89-6	98.999	wh cub cry	430	≈1400	4.14	0.0047^{20}	i EtOH, ace
748	Copper(I) cyanide	CuCN	544-92-3	89.564	wh powder or grn orth cry	474	dec	2.9		i H_2O, EtOH; s KCN soln
749	Copper(I) fluoride	CuF	13478-41-6	82.544	cub cry			7.1		
750	Copper(I) hydride	CuH	13517-00-5	64.554	red-brn solid	60 dec				
751	Copper(I) iodide	CuI	7681-65-4	190.450	wh cub cry	606	≈1290	5.67	0.000020^{20}	i dil acid
752	Copper(I) mercury iodide	Cu_2HgI_4	13876-85-2	835.30	red cry powder	trans ≈60 (brn)				i H_2O, EtOH
753	Copper(I) oxide	Cu_2O	1317-39-1	143.091	red-brn cub cry	1235	1800 dec	6.0		i H_2O
754	Copper(I) selenide	Cu_2Se	20405-64-5	206.05	blue-blk tetr cry	1113		6.84		i H_2O; s acid
755	Copper(I) sulfide	Cu_2S	22205-45-4	159.158	blue-blk orth cry	≈1100		5.6		i H_2O; sl acid
756	Copper(I) sulfite monohydrate	$Cu_2SO_3 \cdot H_2O$		225.172	cry			3.83		sl H_2O; s HCl
757	Copper(I) sulfite hemihydrate	$Cu_2SO_3 \cdot 0.5H_2O$	13982-53-1*	216.164	wh-yel hex cry					sl H_2O; s acid, alk; i EtOH, eth
758	Copper(I) telluride	Cu_2Te	12019-52-2	254.69	blue hex cry	1127		4.6		
759	Copper(I) thiocyanate	CuSCN	1111-67-7	121.630	wh-yel amorp powder	1084		2.85		i H_2O, dil acid, EtOH, ace; s eth
760	Copper(I,II) sulfite dihydrate	$Cu_2SO_3 \cdot CuSO_3 \cdot 2H_2O$	13814-81-8	386.797	red prisms or powder					i H_2O, EtOH; s HCl
761	Copper(II) acetate	$Cu(C_2H_3O_2)_2$	142-71-2	181.635	blue-grn hyg powder					
762	Copper(II) acetate metaarsenite	$Cu(C_2H_3O_2)_2 \cdot 3Cu(AsO_2)_2$	12002-03-8	1013.795	grn cry powder					i H_2O; reac acid
763	Copper(II) acetate monohydrate	$Cu(C_2H_3O_2)_2 \cdot H_2O$	6046-93-1	199.650	grn monocl cry	115	240 dec	1.88		s H_2O, EtOH; sl eth
764	Copper(II) acetylide	CuC_2	12540-13-5	87.567	brn-blk solid; exp	exp 100				
765	Copper(II) arsenate	$Cu_3(AsO_4)_2$	10103-61-4	468.476	blue-grn cry					i H_2O, EtOH; s dil acid
766	Copper(II) arsenite	$CuHAsO_3$	10290-12-7	187.474	yel-grn powder					i H_2O, EtOH; s acid
767	Copper(II) azide	$Cu(N_3)_2$	14215-30-6	147.586	brn orth cry; exp			≈2.6		
768	Copper(II) basic acetate	$Cu(C_2H_3O_2)_2 \cdot CuO \cdot 6H_2O$	52503-64-7	369.271	blue-grn cry or powder					sl H_2O, EtOH; s dil acid, NH_4OH
769	Copper(II) borate	$Cu(BO_2)_2$	39290-85-2	149.166	blue-grn powder			3.859		i H_2O; s acid
770	Copper(II) bromide	$CuBr_2$	7789-45-9	223.354	blk monocl cry; hyg	498	900	4.710	126^{25}	s EtOH, ace; i bz, eth
771	Copper(II) butanoate monohydrate	$Cu(C_4H_7O_2)_2 \cdot H_2O$	540-16-9	255.756	grn monocl plates					s H_2O, diox, bz; sl EtOH
772	Copper(II) carbonate hydroxide	$CuCO_3 \cdot Cu(OH)_2$	12069-69-1	221.116	grn monocl cry	200 dec		4.0		i H_2O, EtOH; s dil acid
773	Copper(II) chlorate hexahydrate	$Cu(ClO_3)_2 \cdot 6H_2O$	14721-21-2	338.539	blue-grn hyg cry	65	100 dec		164^{18}	vs EtOH
774	Copper(II) chloride	$CuCl_2$	7447-39-4	134.451	yel-brn monocl cry; hyg	630 dec		3.4	75.7^{25}	s EtOH, ace

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
775	Copper(II) chloride dihydrate	$CuCl_2 \cdot 2H_2O$	10125-13-0	170.482	grn-blue orth cry; hyg	100 dec		2.51	75.7^{20}	vs EtOH, MeOH; s ace; i eth
776	Copper(II) chloride hydroxide	$Cu_2(OH)_3Cl$	1332-65-6	213.567	pale grn cry					i H_2O; s acid
777	Copper(II) chromate	$CuCrO_4$	13548-42-0	179.540	red-brn cry					i H_2O; s EtOH
778	Copper(II) chromite	$CuCr_2O_4$	12018-10-9	231.536	gray-blk tetr cry			5.4		i H_2O, dil acid
779	Copper(II) citrate hemipentahydrate	$Cu_2C_6H_4O_7 \cdot 2.5H_2O$	10402-15-0	360.221	blue-grn cry	100 dec				sl H_2O; s dil acid
780	Copper(II) cyanide	$Cu(CN)_2$	14763-77-0	115.580	grn powder					i H_2O; s acid, alk
781	Copper(II) cyclohexanebutanoate	$Cu(C_{10}H_{17}O_2)_2$	2218-80-6	402.028	pow	126 dec				
782	Copper(II) dichromate dihydrate	$CuCr_2O_7 \cdot 2H_2O$	13675-47-3	315.565	red-brn tricl cry			2.286		vs H_2O
783	Copper(II) ethanolate	$Cu(C_2H_5O)_2$	2850-65-9	153.667	blue hyg solid	120 dec				i os
784	Copper(II) ethylacetoacetate	$Cu(C_2H_5CO_2CHCOCH_3)_2$	14284-06-1	321.813	pow	192				s EtOH
785	Copper(II) ferrocyanide	$Cu_2Fe(CN)_6$	13601-13-3	339.041	red-br cub cry or powder			2.2		i H_2O, acid, os
786	Copper(II) ferrous sulfide	$CuFeS_2$	1308-56-1	183.523	yel tetr cry	950		4.2		i H_2O, HCl; s HNO_3
787	Copper(II) fluoride	CuF_2	7789-19-7	101.543	wh monocl cry	836	1676	4.23	0.075^{25}	
788	Copper(II) fluoride dihydrate	$CuF_2 \cdot 2H_2O$	13454-88-1	137.574	blue monocl cry	130 dec		2.934	0.075^{25}	
789	Copper(II) formate	$Cu(CHO_2)_2$	544-19-4	153.581	blue cry				12.5^{20}	i os
790	Copper(II) formate tetrahydrate	$Cu(CHO_2)_2 \cdot 4H_2O$	5893-61-8	225.641	blue monocl cry				12.5	sl EtOH; i os
791	Copper(II) hexafluoro-2,4-pentanedioate	$Cu(CF_3COCHCOCF_3)_2$	14781-45-4	477.648	cry	98	220 dec			s MeOH, ace, tol
792	Copper(II) hexafluorosilicate tetrahydrate	$CuSiF_6 \cdot 4H_2O$	12062-24-7	277.684	blue monocl cry	dec		2.56	99.7^{17}	sl EtOH
793	Copper(II) hydroxide	$Cu(OH)_2$	20427-59-2	97.561	blue-grn powder			3.37		i H_2O; s acid, conc alk
794	Copper(II) iodate	$Cu(IO_3)_2$	13454-89-2	413.351	grn mono cry	dec		5.241	0.15^{20}	s dil acid
795	Copper(II) iodate monohydrate	$Cu(IO_3)_2 \cdot H_2O$	13454-90-5	431.367	blue tricl cry	248 dec		4.872	0.15^{20}	s dil H_2SO_4
796	Copper(II) molybdate	$CuMoO_4$	13767-34-5	223.48	grn cry	≈500		3.4	0.038	
797	Copper(II) nitrate	$Cu(NO_3)_2$	3251-23-8	187.555	blue-grn orth cry; hyg	255	subl		145^{25}	s diox; reac eth
798	Copper(II) nitrate hexahydrate	$Cu(NO_3)_2 \cdot 6H_2O$	13478-38-1	295.647	blue rhomb cry; hyg			2.07	145^{25}	s EtOH
799	Copper(II) nitrate trihydrate	$Cu(NO_3)_2 \cdot 3H_2O$	10031-43-3	241.602	blue rhomb cry	114	170 dec	2.32	145^{25}	vs EtOH
800	Copper(II) oleate	$Cu(C_{18}H_{33}O_2)_2$	1120-44-1	626.453	blue-grn solid					i H_2O; sl EtOH; s eth
801	Copper(II) oxalate	CuC_2O_4	814-91-5	151.565	blue-wh powder	310 dec			0.0026^{20}	i EtOH, eth; s NH_4OH
802	Copper(II) oxalate hemihydrate	$CuC_2O_4 \cdot 0.5H_2O$	814-91-5*	144.573	blue-wh cry	200 dec			0.0026^{20}	s NH_4OH
803	Copper(II) oxide	CuO	1317-38-0	79.545	blk powder or monocl cry	1446		6.31		i H_2O, EtOH; s dil acid
804	Copper(II) perchlorate	$Cu(ClO_4)_2$	13770-18-8	262.446	grn hyg cry	130 dec			146^{30}	s eth, diox; i bz, ctc
805	Copper(II) perchlorate hexahydrate	$Cu(ClO_4)_2 \cdot 6H_2O$	10294-46-9	370.538	blue monocl cry; hyg	82	120 dec	2.22	146^{30}	vs EtOH, HOAc, ace; sl eth
806	Copper(II) phosphate	$Cu_3(PO_4)_2$	7798-23-4	380.581	blue-grn tricl cry					i H_2O; s acid, NH_4OH
807	Copper(II) phosphate trihydrate	$Cu_3(PO_4)_2 \cdot 3H_2O$	10031-48-8	434.627	blue-grn orth cry					i H_2O; s acid, NH_4OH
808	Copper(II) selenate pentahydrate	$CuSeO_4 \cdot 5H_2O$	10031-45-5	296.58	blue tricl cry	80 dec		2.56	27.4^{25}	s acid, NH_4OH; sl ace; i EtOH
809	Copper(II) selenide	CuSe	1317-41-5	142.51	blue-blk needles or plates	550 dec		5.99		reac acid
810	Copper(II) selenite dihydrate	$CuSeO_3 \cdot 2H_2O$	15168-20-4	226.54	blue orth cry			3.31		i H_2O; s acid, NH_4OH
811	Copper(II) stearate	$Cu(C_{18}H_{35}O_2)_2$	660-60-6	630.485	blue-grn amorp powder	≈250				i H_2O, EtOH, eth; s py
812	Copper(II) sulfate	$CuSO_4$	7758-98-7	159.610	wh-grn amorp powder or rhomb cry	560 dec		3.60	22.0^{25}	i EtOH
813	Copper(II) sulfate pentahydrate	$CuSO_4 \cdot 5H_2O$	7758-99-8	249.686	blue tricl cry	110 dec		2.286	22.0^{25}	s MeOH; sl EtOH
814	Copper(II) sulfate, basic	$Cu_3(OH)_4SO_4$	1332-14-5	354.731	grn rhomb cry			3.88		i H_2O
815	Copper(II) sulfide	CuS	1317-40-4	95.612	blk hex cry	trans 507		4.76		i H_2O, EtOH, dil acid, alk
816	Copper(II) tartrate trihydrate	$CuC_4H_4O_6 \cdot 3H_2O$	815-82-7	265.663	blue-grn powder					sl H_2O; s acid, alk
817	Copper(II) telluride	CuTe	12019-23-7	191.15	yel orth cry	trans ≈400		7.09		
818	Copper(II) tetrafluoroborate	$Cu(BF_4)_2$	14735-84-3	237.155	solid					s H_2O
819	Copper(II) tungstate	$CuWO_4$	13587-35-4	311.38	yel-brn powder			7.5		

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
820	Copper(II) tungstate dihydrate	$CuWO_4 \cdot 2H_2O$	13587-35-4*	347.41	grn powder					i H_2O; sl HOAc; reac conc acid
821	Copper(II) vanadate	$Cu(VO_3)_2$	12789-09-2	261.425	pow					
822	Curium	Cm	7440-51-9	247	silv metal; hex or cub	1345	≈3100	13.51		
823	Dysprosium	Dy	7429-91-6	162.50	silv metal; hex	1412	2567	8.55		s dil acid
824	Dysprosium boride	DyB_4	12310-43-9	205.74	tetr cry	2500		6.98		
825	Dysprosium nitride	DyN	12019-88-4	176.51	cub cry			9.93		
826	Dysprosium silicide	$DySi_2$	12133-07-2	218.67	orth cry			5.2		
827	Dysprosium(II) chloride	$DyCl_2$	13767-31-2	233.41	blk cry	721 dec				reac H_2O
828	Dysprosium(II) iodide	DyI_2	36377-94-3	416.31	purp cry	659				reac H_2O
829	Dysprosium(III) bromide	$DyBr_3$	14456-48-5	402.21	wh hyg cry	879				s H_2O
830	Dysprosium(III) chloride	$DyCl_3$	10025-74-8	268.86	yel cry	680		3.67		s H_2O
831	Dysprosium(III) fluoride	DyF_3	13569-80-7	219.50	grn cry	1154				
832	Dysprosium(III) hydride	DyH_3	13537-09-2	165.52	hex cry			7.1		
833	Dysprosium(III) iodide	DyI_3	15474-63-2	543.21	grn cry	978				
834	Dysprosium(III) nitrate pentahydrate	$Dy(NO_3)_3 \cdot 5H_2O$	10143-38-1*	438.59	yel cry	88.6			208.4^{25}	
835	Dysprosium(III) oxide	Dy_2O_3	1308-87-8	373.00	wh cub cry	2228	3900	7.81		s acid
836	Dysprosium(III) sulfide	Dy_2S_3	12133-10-7	421.20	red-brn monocl cry			6.08		
837	Einsteinium	Es	7429-92-7	252	metal; cub	860				
838	Erbium	Er	7440-52-0	167.26	silv metal; hex	1529	2868	9.07		i H_2O; s acid
839	Erbium boride	ErB_4	12310-44-0	210.50	tetr cry	2450		7.0		
840	Erbium bromide	$ErBr_3$	13536-73-7	406.97	viol hyg cry	923				s H_2O
841	Erbium chloride	$ErCl_3$	10138-41-7	273.62	viol monocl cry; hyg	776		4.1		s H_2O
842	Erbium chloride hexahydrate	$ErCl_3 \cdot 6H_2O$	10025-75-9	381.71	pink hyg cry	dec				s H_2O; sl EtOH
843	Erbium fluoride	ErF_3	13760-83-3	224.26	pink orth cry	1147		7.8		i H_2O
844	Erbium hydride	ErH_3	13550-53-3	170.28	hex cry			≈7.6		
845	Erbium iodide	ErI_3	13813-42-8	547.97	viol hex cry; hyg	1014		≈5.5		s H_2O
846	Erbium nitrate pentahydrate	$Er(NO_3)_3 \cdot 5H_2O$	10168-80-6*	443.35	red cry	130 dec			240.8^{25}	s EtOH, ace
847	Erbium nitride	ErN	12020-21-2	181.27	cub cry			10.6		
848	Erbium oxide	Er_2O_3	12061-16-4	382.52	pink powder	2344	3920	8.64		i H_2O; s acid
849	Erbium silicide	$ErSi_2$	12020-28-9	223.43	orth cry			7.26		
850	Erbium sulfate	$Er_2(SO_4)_3$	13478-49-4	622.71	hyg powder	dec		3.68	13^{20}	
851	Erbium sulfate octahydrate	$Er_2(SO_4)_3 \cdot 8H_2O$	10031-52-4	766.83	pink monocl cry	dec		3.20	13^{20}	
852	Erbium sulfide	Er_2S_3	12159-66-9	430.72	red-brn monocl cry	1730		6.07		
853	Erbium telluride	Er_2Te_3	12020-39-2	717.32	orth cry	1213		7.11		
854	Europium	Eu	7440-53-1	151.964	soft silv metal; cub	822	1529	5.24		reac H_2O
855	Europium boride	EuB_6	12008-05-8	216.830	cub cry	≈2600		4.91		
856	Europium nitride	EuN	12020-58-5	165.971	cub cry			8.7		
857	Europium silicide	$EuSi_2$	12434-24-1	208.135	tetr cry	1500		5.46		
858	Europium(II) bromide	$EuBr_2$	13780-48-8	311.772	wh cry	683				s H_2O
859	Europium(II) chloride	$EuCl_2$	13769-20-5	222.869	wh orth cry	731		4.9		s H_2O
860	Europium(II) fluoride	EuF_2	14077-39-5	189.961	grn-yel cub cry	≈1380		6.5		
861	Europium(II) iodide	EuI_2	22015-35-6	405.773	grn cry	580				s H_2O
862	Europium(II) selenide	EuSe	12020-66-5	230.92	brn cub cry			6.45		
863	Europium(II) sulfate	$EuSO_4$	10031-54-6	248.028	col orth cry			4.99		i H_2O
864	Europium(II) sulfide	EuS	12020-65-4	184.030	cub cry			5.7		
865	Europium(II) telluride	EuTe	12020-69-8	279.56	blk cub cry	1526		6.48		
866	Europium(III) bromide	$EuBr_3$	13759-88-1	391.676	gray cry	dec				s H_2O
867	Europium(III) chloride	$EuCl_3$	10025-76-0	258.322	grn-yel needles	623		4.89		
868	Europium(III) chloride hexahydrate	$EuCl_3 \cdot 6H_2O$	13759-92-7	366.413	wh-yel hyg cry	850		4.89		s H_2O
869	Europium(III) fluoride	EuF_3	13765-25-8	208.959	wh hyg cry	1276				i H_2O
870	Europium(III) nitrate hexahydrate	$Eu(NO_3)_3 \cdot 6H_2O$	10031-53-5	446.070	wh-pink hyg cry	85 dec			193^{25}	
871	Europium(III) oxide	Eu_2O_3	1308-96-9	351.926	pink powder	2291	3790	7.42		i H_2O; s acid
872	Europium(III) sulfate	$Eu_2(SO_4)_3$	13537-15-0	592.119	pale pink cry			4.99	2.1^{20}	
873	Europium(III) sulfate octahydrate	$Eu_2(SO_4)_3 \cdot 8H_2O$	10031-52-4	736.241	pink cry	375 dec			2.1^{20}	
874	Fermium	Fm	7440-72-4	257	metal	1527				
875	Fluorine	F_2	7782-41-4	37.997	pale yel gas	-219.67 tp	-188.12	1.553 g/L		reac H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
876	Fluorine monoxide	F_2O	7783-41-7	53.996	col gas	-223.8	-144.75	2.207 g/L		sl H_2O
877	Fluorine dioxide	F_2O_2	7783-44-0	69.996	gas, stable only at low temp	-154	-57	2.861 g/L		
878	Fluorine nitrate	FNO_3	7789-26-6	81.003	col gas	-175	-46	3.311 g/L		reac H_2O, EtOH, eth; s ace
879	Fluorine perchlorate	$FOClO_3$	10049-03-3	118.449	col gas; exp	-167.3	-16	4.841 g/L		reac H_2O
880	Francium	Fr	7440-73-5	223	short-lived alkali metal	27				
881	Gadolinium	Gd	7440-54-2	157.25	silv metal; hex	1313	3273	7.90		s dil acid
882	Gadolinium boride	GdB_6	12008-06-9	222.12	blk-brn cub cry	2510		5.31		
883	Gadolinium nitride	GdN	25764-15-2	171.26	cub cry			9.10		
884	Gadolinium silicide	$GdSi_2$	12134-75-7	213.42	orth cry			5.9		
885	Gadolinium(II) iodide	GdI_2	13814-72-7	411.06	bronze cry	831				
886	Gadolinium(II) selenide	GdSe	12024-81-6	236.21	cub cry	2170		8.1		
887	Gadolinium(III) bromide	$GdBr_3$	13818-75-2	396.96	wh monocl cry; hyg	770		4.56		
888	Gadolinium(III) chloride	$GdCl_3$	10138-52-0	263.61	wh monocl cry; hyg	609		4.52		s H_2O
889	Gadolinium(III) chloride hexahydrate	$GdCl_3 \cdot 6H_2O$	19423-81-5	371.70	col hyg cry			2.424		s H_2O
890	Gadolinium(III) fluoride	GdF_3	13765-26-9	214.25	wh cry	1231				
891	Gadolinium(III) iodide	GdI_3	13572-98-0	537.96	yel cry	925				
892	Gadolinium(III) nitrate hexahydrate	$Gd(NO_3)_3 \cdot 6H_2O$	19598-90-4	451.36	hyg tricl cry	91 dec		2.33	190^{25}	s EtOH
893	Gadolinium(III) nitrate pentahydrate	$Gd(NO_3)_3 \cdot 5H_2O$	52788-53-1	433.34	wh cry	92 dec		2.41	190^{25}	
894	Gadolinium(III) oxide	Gd_2O_3	12064-62-9	362.50	wh hyg powder	2339	3900	7.07		i H_2O; s acid
895	Gadolinium(III) sulfate octahydrate	$Gd_2(SO_4)_3 \cdot 8H_2O$	13450-87-8	746.81	col monocl cry	400 dec		4.14	2.3^{20}	
896	Gadolinium(III) sulfide	Gd_2S_3	12134-77-9	410.70	yel cub cry			6.1		
897	Gadolinium(III) telluride	Gd_2Te_3	12160-99-5	697.30	orth cry	1255		7.7		
898	Gallium	Ga	7440-55-3	69.723	silv liq or gray orth cry	29.7666 tp	2204	5.91		reac alk
899	Gallium antimonide	GaSb	12064-03-8	191.483	cub cry	712		5.6137		
900	Gallium arsenide	GaAs	1303-00-0	144.645	gray cub cry	1238		5.3176		
901	Gallium nitride	GaN	25617-97-4	83.730	gray hex cry	>2500		6.1		
902	Gallium phosphide	GaP	12063-98-8	100.697	yel cub cry	1457		4.138		
903	Gallium suboxide	Ga_2O	12024-20-3	155.445	brn powder	>660	>800 dec	4.77		
904	Gallium(II) chloride	$GaCl_2$	24597-12-4	140.628	wh orth cry	172.4	535	2.74		
905	Gallium(II) selenide	GaSe	12024-11-2	148.68	hex cry	960		5.03		
906	Gallium(II) sulfide	GaS	12024-10-1	101.789	hex cry	965		3.86		
907	Gallium(II) telluride	GaTe	12024-14-5	197.32	monocl cry	824		5.44		
908	Gallium(III) 2,4-pentanedioate	$Ga(CH_3COCHCOCH_3)_3$	14405-43-7	367.047	wh powder	193	subl	1.42		
909	Gallium(III) bromide	$GaBr_3$	13450-88-9	309.435	wh orth cry	121.5	279	3.69		
910	Gallium(III) chloride	$GaCl_3$	13450-90-3	176.081	col needles or gl solid	77.9	201	2.47		
911	Gallium(III) fluoride	GaF_3	7783-51-9	126.718	wh powder or col needles	>1000		4.47		i H_2O
912	Gallium(III) fluoride trihydrate	$GaF_3 \cdot 3H_2O$	22886-66-4	180.764	wh cry	>140 dec				sl H_2O
913	Gallium(III) hydride	GaH_3	13572-93-5	72.747	visc liq	-15	≈0 dec			
914	Gallium(III) hydroxide	$Ga(OH)_3$	12023-99-3	120.745	unstable prec					
915	Gallium(III) iodide	GaI_3	13450-91-4	450.436	monocl cry	212	340	4.5		
916	Gallium(III) nitrate	$Ga(NO_3)_3$	13494-90-1	255.738	wh cry powder					s H_2O, EtOH, eth
917	Gallium(III) oxide	Ga_2O_3	12024-21-4	187.444	wh cry	1806		≈6.0		s hot acid
918	Gallium(III) oxide hydroxide	GaOOH	20665-52-5	102.730	orth cry			5.23		
919	Gallium(III) selenide	Ga_2Se_3	12024-24-7	376.33	cub cry	937		4.92		
920	Gallium(III) sulfate	$Ga_2(SO_4)_3$	13494-91-2	427.637	hex cry					
921	Gallium(III) sulfate octadecahydrate	$Ga_2(SO_4)_3 \cdot 18H_2O$	13780-42-2	751.912	octahed cry					s H_2O, EtOH
922	Gallium(III) sulfide	Ga_2S_3	12024-22-5	235.644	monocl cry	1090		3.7		
923	Gallium(III) telluride	Ga_2Te_3	12024-27-0	522.25	cub cry	790		5.57		
924	Germanium	Ge	7440-56-4	72.61	gray-wh cub cry	938.25	2833	5.3234		i H_2O, dil acid, alk
925	Germane	GeH_4	7782-65-2	76.64	col gas; flam	-165	-88.1	3.133 g/L		i H_2O
926	Digermane	Ge_2H_6	13818-89-8	151.27	col liq; flam	-109	29	1.98^{-109}		
927	Trigermane	Ge_3H_8	14691-44-2	225.89	col liq	-105.6	110.5	2.20^{-105}		i H_2O
928	Tetragermane	Ge_4H_{10}	14691-47-5	300.52	col liq		176.9			i H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
929	Pentagermane	Ge_5H_{12}	15587-39-0	375.15	col liq		234			i H_2O
930	Bromogermane	GeH_3Br	13569-43-2	155.54	col liq	-32	52	2.34		reac H_2O
931	Chlorogermane	GeH_3Cl	13637-65-5	111.09	col liq	-52	28	1.75		reac H_2O
932	Chlorotrifluorogermane	GeF_3Cl	14188-40-0	165.06	gas	-66.2	-20.3	6.747 g/L		
933	Dibromogermane	GeH_2Br_2	13769-36-3	234.43	col liq	-15	89	2.80		reac H_2O
934	Dichlorogermane	GeH_2Cl_2	15230-48-5	145.53	col liq	-68	69.5	1.90		reac H_2O
935	Dichlorodifluorogermane	GeF_2Cl_2	24422-21-7	181.51	col gas	-51.8	-2.8	7.419 g/L		
936	Fluorogermane	GeH_3F	13537-30-9	94.63	col gas			3.868 g/L		reac H_2O
937	Iodogermane	GeH_3I	13573-02-9	202.54	liq	-15	≈90			reac H_2O
938	Tribromogermane	$GeHBr_3$	14779-70-5	313.33	col liq	-25	dec			reac H_2O
939	Trichlorogermane	$GeHCl_3$	1184-65-2	179.98	liq	-71	75.3	1.93		reac H_2O
940	Trichlorofluorogermane	$GeCl_3F$	24422-20-6	197.97	liq	-49.8	37.5			
941	Methylgermane	GeH_3CH_3	1449-65-6	90.67	col gas	-158	-23	3.706 g/L		
942	Germanium(II) bromide	$GeBr_2$	24415-00-7	232.42	yel monocl cry	122	150 dec			reac H_2O
943	Germanium(II) chloride	$GeCl_2$	10060-11-4	143.51	wh-yel hyg powder	dec				reac H_2O; s eth, bz
944	Germanium(II) fluoride	GeF_2	13940-63-1	110.61	wh orth cry; hyg	110	130 dec	3.64		reac H_2O
945	Germanium(II) iodide	GeI_2	13573-08-5	326.42	oran-yel hex cry	550 dec		5.4		reac H_2O
946	Germanium(II) oxide	GeO	20619-16-3	88.61	blk solid	700 dec				
947	Germanium(II) selenide	GeSe	12065-10-0	151.57	gray orth cry or brn powder	667		5.6		
948	Germanium(II) sulfide	GeS	12025-32-0	104.68	gray orth cry	615		4.1		
949	Germanium(II) telluride	GeTe	12025-39-7	200.21	cub cry	725		6.16		i H_2O; s conc HNO_3
950	Germanium(IV) bromide	$GeBr_4$	13450-92-5	392.23	wh cry	26.1	186.35	3.132		reac H_2O
951	Germanium(IV) chloride	$GeCl_4$	10038-98-9	214.42	col liq	-51.50	86.55	1.88		reac H_2O; s bz, eth, EtOH, ctc
952	Germanium(IV) fluoride	GeF_4	7783-58-6	148.60	col gas	-15 tp	-36.5 sp	6.074 g/L		reac H_2O
953	Germanium(IV) iodide	GeI_4	13450-95-8	580.23	red-oran cub cry	146	377	4.322		reac H_2O
954	Germanium(IV) nitride	Ge_3N_4	12065-36-0	273.86	orth cry	900 dec				i H_2O, acid, aqua regia
955	Germanium(IV) oxide	GeO_2	1310-53-8	104.61	wh hex cry	1115		4.25		i H_2O
956	Germanium(IV) selenide	$GeSe_2$	12065-11-1	230.53	yel-oran orth ccry	707 dec		4.56		
957	Germanium(IV) sulfide	GeS_2	12025-34-2	136.74	blk orth cry	530		3.01		
958	Gold	Au	7440-57-5	196.967	soft yel metal	1064.18	2856	19.3		s aqua regia
959	Bromoauric acid pentahydrate	$HAuBr_4 \cdot 5H_2O$	17083-68-0	607.667	red-brn hyg cry	27				s H_2O, EtOH
960	Chloroauric acid tetrahydrate	$HAuCl_4 \cdot 4H_2O$	16903-35-8	411.847	yel monocl cry; hyg			≈3.9		vs H_2O, EtOH; s eth
961	Gold(I) bromide	AuBr	10294-27-6	276.871	yel-gray tetr cry	165 dec		8.20		i H_2O
962	Gold(I) chloride	AuCl	10294-29-8	232.420	yel orth cry	289 dec		7.6	0.000031^{20}	
963	Gold(I) cyanide	AuCN	506-65-0	222.985	yel hex cry	dec		7.2		i H_2O, EtOH, eth, dil acid
964	Gold(I) iodide	AuI	10294-31-2	323.871	yel-grn powder; tetr	120 dec		8.25		i H_2O; s CN soln
965	Gold(I) sulfide	Au_2S	1303-60-2	425.999	brn-blk cub cry; unstable	240 dec		≈11		i H_2O, acid; s aqua regia
966	Gold(III) bromide	$AuBr_3$	10294-28-7	436.679	red-br monocl cry	≈160 dec				s H_2O, EtOH
967	Gold(III) chloride	$AuCl_3$	13453-07-1	303.325	red monocl cry	>160 dec		4.7	68^{20}	
968	Gold(III) cyanide trihydrate	$Au(CN)_3 \cdot 3H_2O$	535-37-5*	329.065	wh hyg cry	50 dec				vs H_2O; sl EtOH
969	Gold(III) fluoride	AuF_3	14720-21-9	253.962	oran-yel hex cry	>300	subl	6.75		
970	Gold(III) hydroxide	$Au(OH)_3$	1303-52-2	247.989	brn powder	≈100 dec				i H_2O; s acid
971	Gold(III) iodide	AuI_3	31032-13-0	577.680	unstable grn powder	20 dec				
972	Gold(III) oxide	Au_2O_3	1303-58-8	441.931	brn powder	≈150 dec				i H_2O; s acid
973	Gold(III) selenate	$Au_2(SeO_4)_3$	10294-32-3	822.81	yel cry					i H_2O; s acid
974	Gold(III) selenide	Au_2Se_3	1303-62-4	630.81	blk amorp solid	dec		4.65		s aqua regia
975	Gold(III) sulfide	Au_2S_3	1303-61-3	490.131	unstable blk powder	200 dec				
976	Hafnium	Hf	7440-58-6	178.49	gray metal; hex	2233	4603	13.3		s HF
977	Hafnium boride	HfB_2	12007-23-7	200.11	gray hex cry	3100		10.5		
978	Hafnium(IV) bromide	$HfBr_4$	13777-22-5	498.11	wh cub cry	424 tp	323 sp	4.90		
979	Hafnium carbide	HfC	12069-85-1	190.50	refrac cub cry	≈3000		12.2		
980	Hafnium(IV) chloride	$HfCl_4$	13499-05-3	320.30	wh monocl cry	432 tp	317 sp			reac H_2O
981	Hafnium fluoride	HfF_4	13709-52-9	254.48	wh monocl cry	>970	970 sp	7.1		
982	Hafnium hydride	HfH_2	12770-26-2	180.51	refrac tetr cry			11.4		
983	Hafnium iodide	HfI_4	13777-23-6	686.11	yel-oran cub cry	449 tp	394 sp	5.6		
984	Hafnium nitride	HfN	25817-87-2	192.50	yel-brn cub cry	3305		13.8		

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
985	Hafnium oxide	HfO_2	12055-23-1	210.49	wh cub cry	2774		9.68		i H_2O
986	Hafnium oxychloride octahydrate	$HfOCl_2 \cdot 8H_2O$	14456-34-9	409.52	wh tetr cry	dec				s H_2O
987	Hafnium phosphide	HfP	12325-59-6	209.46	hex cry			9.78		
988	Hafnium selenide	$HfSe_2$	12162-21-9	336.41	brn hex cry			7.46		
989	Hafnium orthosilicate	$HfSiO_4$	13870-13-8	270.57	tetr cry			7.0		
990	Hafnium silicide	$HfSi_2$	12401-56-8	234.66	gray orth cry	≈1700		7.6		
991	Hafnium sulfate	$Hf(SO_4)_2$	15823-43-5	370.62	wh cry	>500 dec				
992	Hafnium sulfide	HfS_2	18855-94-2	242.62	purp-brn hex cry			6.03		
993	Helium	He	7440-59-7	4.003	col gas		-268.93	0.164 g/L		sl H_2O; i EtOH
994	Holmium	Ho	7440-60-0	164.930	silv metal; hex	1474	2700	8.80		s dil acid
995	Holmium bromide	$HoBr_3$	13825-76-8	404.642	yel hyg cry	919	1470			
996	Holmium chloride	$HoCl_3$	10138-62-2	271.288	yel monocl cry; hyg	718	1500	3.7		s H_2O
997	Holmium fluoride	HoF_3	13760-78-6	221.925	pink-yel orth cry; hyg	1143	>2200	7.664		s H_2O
998	Holmium iodide	HoI_3	13813-41-7	545.643	yel hex cry	994		5.4		
999	Holmium nitride	HoN	12029-81-1	178.937	cub cry			10.6		
1000	Holmium oxide	Ho_2O_3	12055-62-8	377.859	yel cub cry	2330	3900	8.41		s acid
1001	Holmium silicide	$HoSi_2$	12136-24-2	221.101	hex cry			7.1		
1002	Holmium sulfide	Ho_2S_3	12162-59-3	426.059	yel-oran monocl cry			5.92		
1003	Hydrazine	N_2H_4	302-01-2	32.045	col oily liq	1.4	113.55	1.0036		vs H_2O, EtOH, MeOH
1004	Hydrazine hydrate	$N_2H_4 \cdot H_2O$	7803-57-8	50.060	fuming liq	-51.7	119	1.030		vs H_2O, EtOH; i chl, eth
1005	Hydrazine hydrobromide	$N_2H_4 \cdot HBr$	13775-80-9	112.957	wh monocl cry flakes	84	≈190 dec	2.3		s H_2O, EtOH
1006	Hydrazine hydrochloride	$N_2H_4 \cdot HCl$	2644-70-4	68.506	wh orth cry	89	240 dec	1.5		s H_2O; i os
1007	Hydrazine dihydrochloride	$N_2H_4 \cdot 2HCl$	5341-61-7	104.966	wh orth cry	198 dec		1.42		s H_2O; sl EtOH
1008	Hydrazine hydroiodide	$N_2H_4 \cdot HI$	10039-55-1	159.957	hyg cry	125				s H_2O
1009	Hydrazine nitrate	$N_2H_4 \cdot HNO_3$	13464-97-6	95.058	monocl cry; exp	70				vs H_2O
1010	Hydrazine sulfate	$N_2H_4 \cdot H_2SO_4$	10034-93-2	130.125	col orth cry	254		1.378		sl H_2O; i EtOH
1011	Hydrazoic acid	HN_3	7782-79-8	43.028	col liq; exp	-80	35.7			s H_2O
1012	Hydroxylamine	H_2NOH	7803-49-8	33.030	wh orth flakes or needles	33.1	58	1.21		vs H_2O, MeOH
1013	Hydroxylamine sulfate	$(H_2NOH)_2 \cdot H_2SO_4$	10039-54-0	164.139	cry	170				vs H_2O
1014	Hydrogen	H_2	1333-74-0	2.016	col gas; flam	-259.198 tp	-252.762	0.082 g/L		sl H_2O
1015	Hydrogen bromide	HBr	10035-10-6	80.912	col gas	-86.80	-66.38	3.307 g/L		vs H_2O; s EtOH
1016	Hydrogen chloride	HCl	7647-01-0	36.461	col gas	-114.17	-85	1.490 g/L		vs H_2O
1017	Hydrogen chloride dihydrate	$HCl \cdot 2H_2O$	13465-05-9	72.492	col liq	-17.7		1.46		
1018	Hydrogen cyanide	HCN	74-90-8	27.026	col liq	-13.29	26	0.684		vs H_2O, EtOH; sl eth
1019	Hydrogen fluoride	HF	7664-39-3	20.006	col gas	-83.35	20	0.818 g/L		vs H_2O, EtOH; sl eth
1020	Hydrogen iodide	HI	10034-85-2	127.912	col or yel gas	-50.76	-35.55	5.228 g/L		vs H_2O; s os
1021	Hydrogen peroxide	H_2O_2	7722-84-1	34.015	col liq	-0.43	150.2	1.44		vs H_2O
1022	Hydrogen selenide	H_2Se	7783-07-5	80.98	col gas; flam	-65.73	-41.25	3.310 g/L		s H_2O
1023	Hydrogen sulfide	H_2S	7783-06-4	34.082	col gas; flam	-85.5	-59.55	1.393 g/L		s H_2O
1024	Hydrogen disulfide	H_2S_2	13465-07-1	66.148	col liq		70.7	1.334		
1025	Hydrogen telluride	H_2Te	7783-09-7	129.62	col gas	-49	-2	5.298 g/L		s H_2O, EtOH, alk
1026	Indium	In	7440-74-6	114.818	soft wh metal	156.60	2072	7.31		s acid
1027	Indium antimonide	InSb	1312-41-0	236.578	blk cub cry	525		5.7747		
1028	Indium arsenide	InAs	1303-11-3	189.740	gray cub cry	942		5.67		i acid
1029	Indium nitride	InN	25617-98-5	128.825	hex cry	1100		6.88		
1030	Indium phosphide	InP	22398-80-7	145.792	blk cub cry	1062		4.81		sl acid
1031	Indium(I) bromide	InBr	14280-53-6	194.722	oran-red orth cry	290	656	4.96		reac H_2O
1032	Indium(I) chloride	InCl	13465-10-6	150.271	yel cub cry	211	608	4.19		reac H_2O
1033	Indium(I) iodide	InI	13966-94-4	241.722	orth cry	364.4	712	5.32		
1034	Indium(II) bromide	$InBr_2$	21264-43-7	274.626	orth cry			4.22		reac H_2O
1035	Indium(II) chloride	$InCl_2$	13465-11-7	185.723	col orth cry	235		3.64		reac H_2O
1036	Indium(II) sulfide	InS	12030-14-7	146.884	red-brn orth cry	692		5.2		
1037	Indium(III) bromide	$InBr_3$	13465-09-3	354.530	hyg yel-wh monocl cry	420		4.74	414[20]	
1038	Indium(III) chloride	$InCl_3$	10025-82-8	221.176	yel monocl cry; hyg	583		4.0	195.1[22]	s EtOH
1039	Indium(III) fluoride	InF_3	7783-52-0	171.813	wh hex cry; hyg	1170	>1200	4.39		sl H_2O; s dil acid
1040	Indium(III) fluoride trihydrate	$InF_3 \cdot 3H_2O$	14166-78-0	225.859	wh cry	100 dec				s H_2O
1041	Indium(III) hydroxide	$In(OH)_3$	20661-21-6	165.840	cub cry			4.4		

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1042	Indium(III) iodide	InI_3	13510-35-5	495.531	yel-red monocl cry; hyg	207		4.69	1308^{22}	
1043	Indium(III) oxide	In_2O_3	1312-43-2	277.634	yel cub cry	1912		7.18		i H_2O; s hot acid
1044	Indium(III) perchlorate octahydrate	$In(ClO_4)_3 \cdot 8H_2O$	13465-15-1	557.291	wh cry	≈80	200 dec			
1045	Indium(III) phosphate	$InPO_4$	14693-82-4	209.789	wh orth cry			4.9		i H_2O
1046	Indium(III) selenide	In_2Se_3	1312-42-1	466.52	blk hex cry	660		5.8		
1047	Indium(III) sulfate	$In_2(SO_4)_3$	13464-82-9	517.827	hyg wh powder			3.44	117^{20}	
1048	Indium(III) sulfide	In_2S_3	12030-24-9	325.834	oran cub cry	1050		4.45		
1049	Indium(III) telluride	In_2Te_3	1312-45-4	612.44	blk cub cry	667		5.75		
1050	Iodine	I_2	7553-56-2	253.809	blue-blk plates	113.7	184.4	4.933	0.03^{20}	s bz, EtOH, eth, ctc, chl
1051	Iodic acid	HIO_3	7782-68-5	175.910	col orth cry	110 dec		4.63	308^{25}	i EtOH, eth
1052	Periodic acid dihydrate	$HIO_4 \cdot 2H_2O$	10450-60-9	227.940	monocl hyg cry	122 dec				s H_2O, EtOH; sl eth
1053	Iodine tetroxide	I_2O_4	12399-08-5	317.807	yel cry	85 dec		4.2		sl H_2O
1054	Iodine pentoxide	I_2O_5	12029-98-0	333.806	hyg wh cry	≈300 dec		4.98	253.4^{20}	i EtOH, eth, CS_2
1055	Iodine nonaoxide	I_4O_9	73560-00-6	651.613	hyg yel powder	75 dec				
1056	Iodine bromide	IBr	7789-33-5	206.808	blk orth cry	40	116 dec	4.3		s H_2O, EtOH, eth
1057	Iodine chloride	ICl	7790-99-0	162.357	red cry or oily liq	27.39	100 dec	3.24		reac H_2O; s EtOH
1058	Iodine trichloride	ICl_3	865-44-1	233.262	yel tricl cry; hyg	101 tp (16 atm)	64 sp dec	3.2		reac H_2O; s EtOH, bz
1059	Iodine fluoride	IF	13873-84-2	145.902	disproportionates at room temp					
1060	Iodine trifluoride	IF_3	22520-96-3	183.899	yel solid, stable at low temp	-28 dec				
1061	Iodine pentafluoride	IF_5	7783-66-6	221.896	yel liq	9.43	100.5	3.19		reac H_2O
1062	Iodine heptafluoride	IF_7	16921-96-3	259.893	col gas	6.5 tp	4.8 sp	10.62 g/L		s H_2O
1063	Iridium	Ir	7439-88-5	192.217	silv-wh metal; cub	2446	4428	22.56		s aqua regia
1064	Iridium(III) sulfide	Ir_2S_3	12136-42-4	480.632	orth cry			10.2		
1065	Iridium(III) bromide	$IrBr_3$	10049-24-8	431.929	red-brn monocl cry			6.82		i H_2O, acid, alk
1066	Iridium(III) bromide tetrahydrate	$IrBr_3 \cdot 4H_2O$	10049-24-8*	503.991	grn-brn cry					s H_2O; i EtOH
1067	Iridium(III) chloride	$IrCl_3$	10025-83-9	298.575	brn monocl cry	763 dec		5.30		i H_2O, acid, alk
1068	Iridium(III) fluoride	IrF_3	23370-59-4	249.212	blk hex cry	250 dec		≈8.0		i H_2O, dil acid
1069	Iridium(III) iodide	IrI_3	7790-41-2	572.930	dark brn monocl cry			≈7.4		i H_2O, acid, bz, chl; s alk
1070	Iridium(III) oxide	Ir_2O_3	1312-46-5	432.432	blue-blk cry	1000 dec				i H_2O; sl hot HCl
1071	Iridium(IV) chloride	$IrCl_4$	10025-97-5	334.028	brn hyg solid	≈700 dec				s H_2O, EtOH
1072	Iridium(IV) oxide	IrO_2	12030-49-8	224.216	brn tetr cry	1100 dec		11.7		
1073	Iridium(IV) sulfide	IrS_2	12030-51-2	256.349	orth cry			9.3		
1074	Iridium(VI) fluoride	IrF_6	7783-75-7	306.207	yel cub cry; hyg	44	53.6	4.8		reac H_2O
1075	Iron	Fe	7439-89-6	55.845	silv-wh or gray met	1538	2861	7.87		s dil acid
1076	Ferrocene	$Fe(C_5H_5)_2$	102-54-5	186.031	oran needles	172.5	249			i H_2O; s EtOH, eth, bz, dil HNO_3
1077	Iron pentacarbonyl	$Fe(CO)_5$	13463-40-6	195.896	yel oily liq; flam	-20	103	1.490		i H_2O; s eth, bz, ace
1078	Iron nonacarbonyl	$Fe_2(CO)_9$	15321-51-4	363.781	oran-yel cry	100 dec		2.85		
1079	Iron dodecacarbonyl	$Fe_3(CO)_{12}$	12088-65-2	503.656	blk cry	140		2.00		
1080	Iron hydrocarbonyl	$FeH_2(CO)_4$	17440-90-3	169.902	col liq; unstable	-70	dec			s alk
1081	Iron arsenide	FeAs	12044-16-5	130.767	gray orth cry	1030		7.85		
1082	Iron boride	FeB	12006-84-7	66.656	refr solid; orth	1650		≈7		
1083	Iron boride	Fe_2B	12006-86-9	122.501	refr solid; tetr	1389		7.3		
1084	Iron carbide	Fe_3C	12011-67-5	179.546	gray cub cry	1227		7.694		
1085	Iron phosphide	FeP	26508-33-8	86.819	rhom cry			6.07		
1086	Iron phosphide	Fe_2P	1310-43-6	142.664	gray hex needles	1370		6.8		i H_2O, dil acid, alk
1087	Iron phosphide	Fe_3P	12023-53-9	198.509	gray solid	1100		6.74		i H_2O
1088	Iron disulfide	FeS_2	1317-66-4	119.977	blk cub cry	>600 dec		5.02		i H_2O
1089	Iron silicide	FeSi	12022-95-6	83.931	gray cub cry	1410		6.1		
1090	Iron silicide	$FeSi_2$	12022-99-0	112.016	gray tetr cry	1220		4.74		
1091	Iron(II) aluminate	$Fe(AlO_2)_2$	12068-49-4	173.806	blk cub cry			4.3		
1092	Iron(II) arsenate	$Fe_3(AsO_4)_2$	10102-50-8	445.373	grn pow					i H_2O
1093	Iron(II) arsenate hexahydrate	$Fe_3(AsO_4)_2 \cdot 6H_2O$	10102-50-8*	553.465	grn amorp pow	dec				i H_2O; s acid
1094	Iron(II) bromide	$FeBr_2$	7789-46-0	215.653	yel-brn hex cry; hyg	691	dec	4.636	120^{25}	vs EtOH
1095	Iron(II) bromide hexahydrate	$FeBr_2 \cdot 6H_2O$	13463-12-2	323.744	grn hyg cry	27 dec		4.64	120^{25}	s EtOH
1096	Iron(II) carbonate	$FeCO_3$	563-71-3	115.854	gray-brn hex cry			3.9	0.000062^{20}	

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1097	Iron(II) chloride	$FeCl_2$	7758-94-3	126.750	wh hex cry; hyg	677	1023	3.16	65.0^{25}	vs EtOH, ace; sl bz
1098	Iron(II) chloride dihydrate	$FeCl_2 \cdot 2H_2O$	16399-77-2	162.781	wh-grn monocl cry	120 dec		2.39	65.0^{25}	
1099	Iron(II) chloride tetrahydrate	$FeCl_2 \cdot 4H_2O$	13478-10-9	198.812	grn monocl cry	105 dec		1.93	65.0^{25}	s EtOH
1100	Iron(II) chromite	$FeCr_2O_4$	1308-31-2	223.835	blk cub cry			5.0		
1101	Iron(II) fluoride	FeF_2	7789-28-8	93.842	wh tetr cry	1100		4.09		sl H_2O; s dil HF; i EtOH, eth
1102	Iron(II) fluoride tetrahydrate	$FeF_2 \cdot 4H_2O$	13940-89-1	165.904	col hex cry			2.20		
1103	Iron(II) hydroxide	$Fe(OH)_2$	18624-44-7	89.860	wh-grn hex cry			3.4	0.000052^{20}	
1104	Iron(II) iodide	FeI_2	7783-86-0	309.654	red-viol hex cry; hyg	587		5.3		s H_2O, EtOH, eth
1105	Iron(II) iodide tetrahydrate	$FeI_2 \cdot 4H_2O$	7783-86-0*	381.716	blk hyg leaflets	90 dec		2.87		s H_2O, EtOH
1106	Iron(II) molybdate	$FeMoO_4$	13718-70-2	215.78	brn-yel monocl cry	1115		5.6		i H_2O
1107	Iron(II) nitrate	$Fe(NO_3)_2$	14013-86-6	179.854	grn solid				87.5^{25}	
1108	Iron(II) nitrate hexahydrate	$Fe(NO_3)_2 \cdot 6H_2O$	14013-86-6*	287.946	grn solid	60 dec			87.5^{25}	
1109	Iron(II) oxalate dihydrate	$FeC_2O_4 \cdot 2H_2O$	6047-25-2	179.894	yel cry	150 dec		2.28	0.078^{25}	s acid
1110	Iron(II) oxide	FeO	1345-25-1	71.844	blk cub cry	1377		6.0		i H_2O, alk; s acid
1111	Iron(II) perchlorate	$Fe(ClO_4)_2$	13933-23-8	254.745	grn-wh hyg needles	>100 dec			210^{25}	
1112	Iron(II) phosphate octahydrate	$Fe_3(PO_4)_2 \cdot 8H_2O$	14940-41-1	501.600	gray-blue monocl cry; hyg			2.58		i H_2O; s acid
1113	Iron(II) selenide	FeSe	1310-32-3	134.81	blk hex cry			6.7		i H_2O
1114	Iron(II) orthosilicate	Fe_2SiO_4	10179-73-4	203.774	brn orth cry			4.30		
1115	Iron(II) sulfate	$FeSO_4$	7720-78-7	151.909	wh orth cry; hyg			3.65	29.5^{25}	
1116	Iron(II) sulfate monohydrate	$FeSO_4 \cdot H_2O$	17375-41-6	169.924	wh-yel monocl cry	300 dec		3.0	29.5^{25}	
1117	Iron(II) sulfate heptahydrate	$FeSO_4 \cdot 7H_2O$	7782-63-0	278.015	blue-grn monocl cry	≈60 dec		1.895	29.5^{25}	i EtOH
1118	Iron(II) sulfide	FeS	1317-37-9	87.911	col hex or tetr cry; hyg	1188	dec	4.7		i H_2O; reac acid
1119	Iron(II) tantalate	$Fe(TaO_3)_2$		513.737	brn tetr cry			7.33		
1120	Iron(II) tartrate	$FeC_4H_4O_6$		203.916	wh cry				0.88	vs acid; s NH_4OH
1121	Iron(II) telluride	FeTe	12125-63-2	183.45	tetr cry	914		6.8		
1122	Iron(II) thiocyanate trihydrate	$Fe(SCN)_2 \cdot 3H_2O$	6010-09-9	226.057	grn monocl cry					s H_2O, EtOH, eth
1123	Iron(II) titanate	$FeTiO_3$	12168-52-4	151.710	blk rhomb cry	≈1470		4.72		
1124	Iron(II) tungstate	$FeWO_4$	13870-24-1	303.68	monocl cry			7.51		
1125	Iron(II,III) oxide	Fe_3O_4	1317-61-9	231.533	blk cub cry or amorp powder	1597		5.17		i H_2O; s acid
1126	Iron(III) acetate, basic	$FeOH(C_2H_3O_2)_2$	10450-55-2	190.941	brn-red amorp powder					i H_2O; s EtOH, acid
1127	Iron(III) 2,4-pentanedioate	$Fe(CH_3COCHCOCH_3)_3$	14024-18-1	353.169	red-oran cry	179		5.24		sl H_2O; s os
1128	Iron(III) arsenate dihydrate	$FeAsO_4 \cdot 2H_2O$	10102-49-5	230.795	grn-brn powder	dec		3.18		i H_2O; s dil acid
1129	Iron(III) bromide	$FeBr_3$	10031-26-2	295.557	dark red hex cry; hyg	dec		4.5	455^{25}	s EtOH, eth
1130	Iron(III) chloride	$FeCl_3$	7705-08-0	162.203	grn hex cry; hyg	304	≈316	2.90	91.2^{25}	s EtOH, eth, ace
1131	Iron(III) chloride hexahydrate	$FeCl_3 \cdot 6H_2O$	10025-77-1	270.294	yel-oran monocl cry; hyg	37 dec		1.82	91.2^{25}	s EtOH, eth, ace
1132	Iron(III) chromate	$Fe_2(CrO_4)_3$	10294-52-7	459.671	yel powder					i H_2O, EtOH; s acid
1133	Iron(III) citrate pentahydrate	$FeC_6H_5O_7 \cdot 5H_2O$	3522-50-7	335.021	red-brn cry					s H_2O; i EtOH
1134	Iron(III) dichromate	$Fe_2(Cr_2O_7)_3$	10294-53-8	759.654	red-brn solid					s H_2O, acid
1135	Iron(III) ferrocyanide	$Fe_4[Fe(CN)_6]_3$	14038-43-8	859.229	dark blue powder			1.80		i H_2O, dil acid, os
1136	Iron(III) fluoride	FeF_3	7783-50-8	112.840	grn hex cry	>1000		3.87	5.92^{25}	i EtOH, eth, bz
1137	Iron(III) fluoride trihydrate	$FeF_3 \cdot 3H_2O$	15469-38-2	166.886	yel-brn tetr cry			2.3	5.92^{25}	
1138	Iron(III) formate	$Fe(CHO_2)_3$	555-76-0	190.897	red-yel cry pow					s H_2O; sl EtOH
1139	Iron(III) hydroxide	$Fe(OH)_3$	1309-33-7	106.867	yel monocl cry			3.12		
1140	Iron(III) hydroxide oxide	FeO(OH)	20344-49-4	88.852	red-brn orth cry			4.26		i H_2O; s acid
1141	Iron(III) nitrate	$Fe(NO_3)_3$	10421-48-4	241.860	cry				82.5^{20}	
1142	Iron(III) nitrate hexahydrate	$Fe(NO_3)_3 \cdot 6H_2O$	13476-08-9	349.951	viol cub cry	35 dec			82.5^{20}	
1143	Iron(III) nitrate nonahydrate	$Fe(NO_3)_3 \cdot 9H_2O$	7782-61-8	403.997	viol-gray hyg cry	47 dec		1.68	82.5^{20}	vs EtOH, ace
1144	Iron(III) oxalate	$Fe_2(C_2O_4)_3$	19469-07-9	375.747	yel amorp powder	100 dec				s H_2O, acid; i alk
1145	Iron(III) oxide	Fe_2O_3	1309-37-1	159.688	red-brn hex cry	1565		5.25		i H_2O; s acid
1146	Iron(III) phosphate dihydrate	$FePO_4 \cdot 2H_2O$	10045-86-0	186.847	gray-wh orth cry			2.87		i H_2O; s HCl
1147	Iron(III) pyrophosphate nonahydrate	$Fe_4(P_2O_7)_3 \cdot 9H_2O$	10058-44-3	907.348	yel powder					i H_2O; s acid
1148	Iron(III) hypophosphite	$Fe(H_2PO_2)_3$	7783-84-8	250.811	wh-gray powder					i H_2O
1149	Iron(III) sodium pyrophosphate	$FeNaP_2O_7$	10045-87-1	252.778	wh pow			1.5		i H_2O; s HCl

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1150	Iron(III) sulfate	$Fe_2(SO_4)_3$	10028-22-5	399.881	gray-wh rhomb cry; hyg			3.10	440^{20}	sl EtOH; i ace
1151	Iron(III) sulfate nonahydrate	$Fe_2(SO_4)_3 \cdot 9H_2O$	13520-56-4	562.018	yel hex cry	400 dec		2.1	440^{20}	
1152	Iron(III) thiocyanate monohydrate	$Fe(SCN)_3 \cdot H_2O$	4119-52-2	248.110	red hyg cry	dec				s H_2O, EtOH, ace; i tol, chl
1153	Iron(III) metavanadate	$Fe(VO_3)_3$	65842-03-7	352.665	gray-brn powder					i H_2O, EtOH; s acid
1154	Krypton	Kr	7439-90-9	83.80	col gas	-157.375 tp (73.2 kPa)	-153.34	3.425 g/L		sl H_2O
1155	Krypton difluoride	KrF_2	13773-81-4	121.80	col tetr cry	≈25 dec		3.24		reac H_2O
1156	Lanthanum	La	7439-91-0	138.906	silv metal; hex	918	3464	6.15		s dil acid
1157	Lanthanum boride	LaB_6	12008-21-8	203.772	blk cub cry; refrac	2715		4.76		
1158	Lanthanum bromide	$LaBr_3$	13536-79-3	378.618	wh hex cry; hyg	788		5.1		s H_2O
1159	Lanthanum carbide	LaC_2	12071-15-7	162.927	tetr cry	2360		5.29		
1160	Lanthanum carbonate octahydrate	$La_2(CO_3)_3 \cdot 8H_2O$	6487-39-4	601.960	wh cry powder			2.6		i H_2O; s dil acid
1161	Lanthanum chloride	$LaCl_3$	10099-58-8	245.264	wh hex cry; hyg	859		3.84	95.7^{25}	
1162	Lanthanum chloride heptahydrate	$LaCl_3 \cdot 7H_2O$	20211-76-1	371.371	wh tricl cry; hyg	91 dec			95.7^{25}	s EtOH
1163	Lanthanum fluoride	LaF_3	13709-38-1	195.901	wh hex cry; hyg	1493		5.9		i H_2O, acid
1164	Lanthanum hydride	LaH_3	13864-01-2	141.930	blk cub cry			5.36		
1165	Lanthanum hydroxide	$La(OH)_3$	14507-19-8	189.928	wh amorp solid	dec			0.000020^{20}	
1166	Lanthanum iodate	$La(IO_3)_3$	13870-19-4	663.614	col cry				1.7	
1167	Lanthanum iodide	LaI_3	13813-22-4	519.619	wh orth cry; hyg	778		5.6		s H_2O
1168	Lanthanum nitrate hexahydrate	$La(NO_3)_3 \cdot 6H_2O$	10277-43-7	433.012	wh hyg tricl cry	≈40 dec			200^{25}	vs EtOH; s ace
1169	Lanthanum nitride	LaN	25764-10-7	152.913	cub cry			6.73		
1170	Lanthanum oxide	La_2O_3	1312-81-8	325.809	wh amorp powder	2304	3620	6.51		i H_2O; s dil acid
1171	Lanthanum silicide	$LaSi_2$	12056-90-5	195.077	gray tetr cry			5.0		
1172	Lanthanum sulfate nonahydrate	$La_2(SO_4)_3 \cdot 9H_2O$	10294-62-9	728.139	hex cry			2.82	2.7^{20}	i EtOH
1173	Lanthanum sulfide	La_2S_3	12031-49-1	374.009	red cub cry	2110		4.9		
1174	Lanthanum sulfide	LaS	12031-30-0	170.972	yel cub cry	2300		5.61		
1175	Lawrencium	Lr	22537-19-5	262	metal	1627				
1176	Lead	Pb	7439-92-1	207.2	soft silv-gray metal; cub	327.462	1749	11.3		s conc acid
1177	Lead(II) acetate	$Pb(C_2H_3O_2)_2$	301-04-2	325.3	wh cry	280	dec	3.25	44.3^{20}	
1178	Lead(II) acetate trihydrate	$Pb(C_2H_3O_2)_2 \cdot 3H_2O$	6080-56-4	427.3	col cry	75 dec		2.55		vs H_2O; sl EtOH
1179	Lead(II) acetate, basic	$Pb(C_2H_3O_2)2 \cdot 2Pb(OH)_2$	1335-32-6	807.7	wh pow	dec			6.3^{0}	
1180	Lead(II) antimonate	$Pb_3(SbO_4)_2$	13510-89-9	993.1	oran-yel powder			6.58		i H_2O, dil acid
1181	Lead(II) arsenate	$Pb_3(AsO_4)_2$	3687-31-8	899.4	wh cry	1042 dec		5.8		i H_2O; s HNO_3
1182	Lead(II) arsenite	$Pb(AsO_2)_2$	10031-13-7	421.0	wh powder			5.85		i H_2O; s dil HNO_3
1183	Lead(II) azide	$Pb(N_3)_2$	13424-46-9	291.2	col orth needles; exp	exp ≈350		4.7	0.023^{18}	vs HOAc
1184	Lead(II) borate monohydrate	$Pb(BO_2)_2 \cdot H_2O$	10214-39-8	310.8	wh powder	500 dec		5.6		i H_2O; s dil HNO_3
1185	Lead(II) bromate monohydrate	$Pb(BrO_3)_2 \cdot H_2O$	10031-21-7	481.0	col cry	≈180 dec		5.53	1.33^{20}	
1186	Lead(II) bromide	$PbBr_2$	10031-22-8	367.0	wh orth cry	371	892	6.69	0.975^{25}	i EtOH
1187	Lead(II) butanoate	$Pb(C_4H_7O_2)_2$	819-73-8	381.4	col solid	≈90				i H_2O; s dil HNO_3
1188	Lead(II) carbonate	$PbCO_3$	598-63-0	267.2	col orth cry	≈315 dec		6.6		i H_2O
1189	Lead(II) carbonate, basic	$Pb(OH)_2 \cdot 2PbCO_3$	1319-46-6	775.6	wh hex cry	400 dec		≈6.5		i H_2O, EtOH; s acid
1190	Lead(II) chlorate	$Pb(ClO_3)_2$	10294-47-0	374.1	col hyg cry	230 dec		3.9	144^{18}	vs EtOH
1191	Lead(II) chloride	$PbCl_2$	7758-95-4	278.1	wh orth needles or powder	501	951	5.98	1.08^{25}	s alk
1192	Lead(II) chloride fluoride	PbClF	13847-57-9	261.7	tetr cry			7.05	0.035^{20}	
1193	Lead(II) chromate	$PbCrO_4$	7758-97-6	323.2	yel-oran monocl cry	844		6.12	0.000017^{20}	s alk, dil acid
1194	Lead(II) chromate(VI) oxide	$PbCrO_4 \cdot PbO$	18454-12-1	546.4	red powder					i H_2O
1195	Lead(II) citrate trihydrate	$Pb_3(C_6H_5O_7)_2 \cdot 3H_2O$	512-26-5	1053.8	wh cry powder					s H_2O; sl EtOH
1196	Lead(II) cyanide	$Pb(CN)_2$	592-05-2	259.2	wh-yel powder					sl H_2O; reac acid
1197	Lead(II) 2-ethylhexanoate	$Pb(C_7H_{15}CO_2)_2$	301-08-6	493.6	visc liq			1.56		
1198	Lead(II) fluoride	PbF_2	7783-46-2	245.2	wh orth cry	830	1293	8.44	0.0670^{25}	
1199	Lead(II) fluoroborate	$Pb(BF_4)_2$	13814-96-5	380.8	stable only in aq soln					s H_2O
1200	Lead(II) formate	$Pb(CHO_2)_2$	811-54-1	297.2	wh prisms or needles	190 dec		4.63	1.6^{16}	i EtOH
1201	Lead(II) hexafluoro-2,4-pentanedioate	$Pb(CF_3COCHCOCF_3)_2$	19648-88-5	621.3	cry	155	210			

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1202	Lead(II) hydrogen arsenate	$PbHAsO_4$	7784-40-9	347.1	wh monocl cry	280 dec		5.943		i H_2O; s HNO_3, alk
1203	Lead(II) hydrogen phosphate	$PbHPO_4$	15845-52-0	303.2	wh monocl cry	dec		5.66		
1204	Lead(II) hydroxide	$Pb(OH)_2$	19783-14-3	241.2	wh powder	145 dec		7.59	0.00012^{20}	s acid
1205	Lead(II) iodate	$Pb(IO_3)_2$	25659-31-8	557.0	wh orth cry			6.50	0.0025^{25}	
1206	Lead(II) iodide	PbI_2	10101-63-0	461.0	yel hex cry or powder	410	872 dec	6.16	0.076^{25}	i EtOH
1207	Lead(II) lactate	$Pb(C_3H_5O_3)_2$	18917-82-3	385.3	wh cry powder					s H_2O, hot EtOH
1208	Lead(II) molybdate	$PbMoO_4$	10190-55-3	367.1	yel tetr cry	≈1060		6.7		i H_2O; s HNO_3, NaOH
1209	Lead(II) niobate	$Pb(NbO_3)_2$	12034-88-7	489.0	rhomb or tetr cry	1343		6.6		i H_2O
1210	Lead(II) nitrate	$Pb(NO_3)_2$	10099-74-8	331.2	col cub cry	470		4.53	59.7^{25}	sl EtOH
1211	Lead(II) oleate	$Pb(C_{18}H_{33}O_2)_2$	1120-46-3	770.1	wax-like solid					i H_2O; s EtOH, bz, eth
1212	Lead(II) oxalate	PbC_2O_4	814-93-7	295.2	wh powder	300 dec		5.28	0.00025^{20}	s dil HNO_3
1213	Lead(II) oxide (litharge)	PbO	1317-36-8	223.2	red tetr cry	trans to massicot 489		9.35		i H_2O, EtOH; s dil HNO_3
1214	Lead(II) oxide (massicot)	PbO	1317-36-8	223.2	yel orth cry	897		9.64		i H_2O, EtOH; s dil HNO_3
1215	Lead(II) oxide hydrate	$3PbO \cdot H_2O$	1311-11-1	687.6	wh powder			7.41		i H_2O; s dil acid
1216	Lead(II) 2,4-pentanedioate	$Pb(CH_3COCHCOCH_3)_2$	15282-88-9	405.4	cry	143				
1217	Lead(II) perchlorate	$Pb(ClO_4)_2$	13453-62-8	406.1	wh cry				441^{25}	
1218	Lead(II) perchlorate trihydrate	$Pb(ClO_4)_2 \cdot 3H_2O$	13637-76-8	460.1	wh cry	100 dec		2.6	441^{25}	s EtOH
1219	Lead(II) phosphate	$Pb_3(PO_4)_2$	7446-27-7	811.5	wh hex cry	1014		7.01		i H_2O, EtOH
1220	Lead(II) hypophosphite	$Pb(H_2PO_2)_2$	10294-58-3	337.2	hyg cry powder	dec				sl H_2O; i EtOH
1221	Lead(II) metasilicate	$PbSiO_3$	10099-76-0	283.3	wh monocl cry powder	764		6.49		i H_2O, os
1222	Lead(II) orthosilicate	Pb_2SiO_4	13566-17-1	506.5	monocl cry	743		7.60		
1223	Lead(II) hexafluorosilicate dihydrate	$PbSiF_6 \cdot 2H_2O$	1310-03-8	385.3	col cry	dec				vs H_2O
1224	Lead(II) selenate	$PbSeO_4$	7446-15-3	350.2	orth cry			6.37	0.013^{25}	s conc acid
1225	Lead(II) selenide	PbSe	12069-00-0	286.2	gray cub cry	1078		8.1		i H_2O; s HNO_3
1226	Lead(II) selenite	$PbSeO_3$	7488-51-9	334.2	wh monocl cry	≈500		7.0		i H_2O
1227	Lead(II) sodium thiosulfate	$Na_4Pb(S_2O_3)_3$	10101-94-7	635.6	wh cry					sl H_2O
1228	Lead(II) stearate	$Pb(C_{18}H_{35}O_2)_2$	1072-35-1	774.1	wh powder	≈100		1.4		i H_2O; s hot EtOH
1229	Lead(II) sulfate	$PbSO_4$	7446-14-2	303.3	orth cry	1087		6.29	0.0044^{25}	i acid; sl alk
1230	Lead(II) sulfide	PbS	1314-87-0	239.3	blk powder or silv cub cry	1113		7.60		i H_2O; s acid
1231	Lead(II) sulfite	$PbSO_3$	7446-10-8	287.3	wh powder	dec				i H_2O; s HNO_3
1232	Lead(II) tantalate	$Pb(TaO_3)_2$	12065-68-8	665.1	orth cry			7.9		i H_2O
1233	Lead(II) telluride	PbTe	1314-91-6	334.8	gray cub cry	924		8.164		i H_2O, acid
1234	Lead(II) thiocyanate	$Pb(SCN)_2$	592-87-0	323.4	wh-yel powder			3.82	0.05^{20}	
1235	Lead(II) thiosulfate	PbS_2O_3	13478-50-7	319.3	wh cry	dec		5.18		i H_2O; s acid
1236	Lead(II) titanate	$PbTiO_3$	12060-00-3	303.1	yel tetr cry			7.9		i H_2O; reac HCl
1237	Lead(II) tungstate (stolzite)	$PbWO_4$	7759-01-5	455.0	yel tetr cry	1130		8.24	0.03^{20}	s alk
1238	Lead(II) tungstate (raspite)	$PbWO_4$	7759-01-5	455.0	monocl cry	trans 400		8.46	0.03^{20}	s alk
1239	Lead(II) metavanadate	$Pb(VO_3)_2$	10099-79-3	405.1	yel powder					i H_2O; reac HNO_3
1240	Lead(II) zirconate	$PbZrO_3$	12060-01-4	346.4	col orth cry			≈8		i H_2O, alk; s acid
1241	Lead(II,IV) oxide	Pb_2O_3	1314-27-8	462.4	blk monocl cry or red amorp powder	530 dec		10.05		i H_2O; s alk; reac conc HCl
1242	Lead(II,II,IV) oxide	Pb_3O_4	1314-41-6	685.6	red tetr cry	830		8.92		i H_2O, EtOH; s hot HCl
1243	Lead(IV) acetate	$Pb(C_2H_3O_2)_4$	546-67-8	443.4	col monocl cry	≈175		2.23		reac H_2O, EtOH; s bz, chl
1244	Lead(IV) bromide	$PbBr_4$	13701-91-2	526.8	unstable liq					
1245	Lead(IV) chloride	$PbCl_4$	13463-30-4	349.0	yel oily liq	-15	≈50 dec			
1246	Lead(IV) fluoride	PbF_4	7783-59-7	283.2	wh tetr cry; hyg	≈600		6.7		
1247	Lead(IV) oxide	PbO_2	1309-60-0	239.2	red tetr cry or brn powder	290 dec		9.64		
1248	Lithium	Li	7439-93-2	6.941	soft silv-wh metal	180.50	1342	0.534		reac H_2O
1249	Lithium acetate	$LiC_2H_3O_2$	546-89-4	65.985	cry	286			45.0^{25}	vs EtOH
1250	Lithium acetate dihydrate	$LiC_2H_3O_2 \cdot 2H_2O$	6108-17-4	102.016	wh rhomb cry	58 dec		1.3	45.0^{25}	s EtOH
1251	Lithium aluminum hydride	$LiAlH_4$	16853-85-3	37.955	gray-wh monocl cry	>125 dec		0.917		reac H_2O, EtOH; s eth, thf
1252	Lithium amide	$LiNH_2$	7782-89-0	22.964	tetr cry	380		1.18		reac H_2O
1253	Lithium arsenate	Li_3AsO_4	13478-14-3	159.743	col orth cry			3.07		sl H_2O; s HOAc

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1254	Lithium azide	LiN_3	19597-69-4	48.961	hyg monocl cry; exp			1.83		vs H_2O
1255	Lithium metaborate	$LiBO_2$	13453-69-5	49.751	wh monocl cry; hyg	849		2.18		vs H_2O; s EtOH
1256	Lithium borohydride	$LiBH_4$	16949-15-8	21.784	wh-gray orth cry or powder	268	380 dec	0.66		s alk, eth, thf
1257	Lithium bromide	LiBr	7550-35-8	86.845	wh cub cry; hyg	552	≈1300	3.464	181^{25}	s EtOH, eth
1258	Lithium carbonate	Li_2CO_3	554-13-2	73.891	wh monocl cry	723	1300 dec	2.11	1.30^{25}	s acid; i EtOH
1259	Lithium chlorate	$LiClO_3$	13453-71-9	90.392	col hyg rhom needles	127.6	300 dec	1.119	459^{25}	vs EtOH; sl ace
1260	Lithium chloride	LiCl	7447-41-8	42.394	wh cub cry or powder; hyg	610	1383	2.07	84.5^{25}	s EtOH, ace, py
1261	Lithium chromate dihydrate	$Li_2CrO_4 \cdot 2H_2O$	7789-01-7	165.906	yel orth cry; hyg	75 dec		2.15		vs H_2O; s EtOH
1262	Lithium dichromate dihydrate	$Li_2Cr_2O_7 \cdot 2H_2O$	10022-48-7	265.901	yel-red hyg cry	130 dec		2.34		vs H_2O
1263	Lithium dihydrogen phosphate	LiH_2PO_4	13453-80-0	103.928	col hyg cry	>100		2.461	126^{0}	
1264	Lithium ferrosilicon	LiFeSi	64082-35-5	90.872	dark brittle cry					reac H_2O
1265	Lithium fluoride	LiF	7789-24-4	25.939	wh cub cry or powder	848.2	1673	2.640	0.134^{25}	s acid
1266	Lithium formate monohydrate	$Li(CHO_2) \cdot H_2O$	6108-23-2	69.974	col-wh cry			1.46		s H_2O
1267	Lithium hydride	LiH	7580-67-8	7.949	gray cub cry or powder; hyg	688.7		0.78		reac H_2O, EtOH
1268	Lithium hydroxide	LiOH	1310-65-2	23.948	col tetr cry	471.1	1626	1.45	12.5^{25}	sl EtOH
1269	Lithium hydroxide monohydrate	$LiOH \cdot H_2O$	1310-66-3	41.964	wh monocl cry or powder			1.51	12.5^{25}	sl EtOH
1270	Lithium iodate	$LiIO_3$	13765-03-2	181.843	wh hyg hex cry			4.502	77.9^{25}	i EtOH
1271	Lithium iodide	LiI	10377-51-2	133.845	wh cub cry; hyg	469	1171	4.06	165^{25}	
1272	Lithium iodide trihydrate	$LiI \cdot 3H_2O$	7790-22-9	187.891	wh hyg cry	73		3.48	165^{25}	vs EtOH, ace
1273	Lithium niobate	$LiNbO_3$	12031-63-9	147.845	wh hex cry	≈1240		4.30		
1274	Lithium nitrate	$LiNO_3$	7790-69-4	68.946	col hex cry; hyg	253		2.38	102^{25}	s EtOH
1275	Lithium nitride	Li_3N	26134-62-3	34.830	red hex cry	813		1.27		reac H_2O
1276	Lithium nitrite monohydrate	$LiNO_2 \cdot H_2O$	13568-33-7*	70.962	col needles	>100		1.615	139.5^{25}	vs EtOH
1277	Lithium phosphate	Li_3PO_4	10377-52-3	115.794	wh orth cry	1205		2.46	0.027^{25}	
1278	Lithium oxide	Li_2O	12057-24-8	29.881	wh cub cry	1570		2.013		
1279	Lithium perchlorate	$LiClO_4$	7791-03-9	106.392	wh orth cry or powder	236	430 dec	2.428	58.7^{25}	s EtOH, ace, eth
1280	Lithium peroxide	Li_2O_2	12031-80-0	45.881	wh hex cry			2.31		s H_2O; i EtOH
1281	Lithium selenate monohydrate	$Li_2SeO_4 \cdot H_2O$	7790-71-8	174.86	monocl cry			2.56		vs H_2O
1282	Lithium metasilicate	Li_2SiO_3	10102-24-6	89.966	wh orth needles	1201		2.52		i cold H_2O; reac dil acid
1283	Lithium sulfate	Li_2SO_4	10377-48-7	109.946	wh monocl cry; hyg	859		2.21	34.2^{25}	
1284	Lithium sulfate monohydrate	$Li_2SO_4 \cdot H_2O$	10102-25-7	127.961	col cry	130 dec		2.06	34.2^{25}	sl EtOH
1285	Lithium sulfide	Li_2S	12136-58-2	45.948	wh cub cry; hyg	1372		1.64		
1286	Lithium thiocyanate	LiSCN	556-65-0	65.025	wh hyg cry				120^{25}	
1287	Lutetium	Lu	7439-94-3	174.967	silv metal; hex	1663	3402	9.84		s dil acid
1288	Lutetium boride	LuB_4	12688-52-7	218.211	tetr cry	2600		≈7.0		
1289	Lutetium bromide	$LuBr_3$	14456-53-2	414.679	wh hyg cry	1025				vs H_2O
1290	Lutetium chloride	$LuCl_3$	10099-66-8	281.325	wh monocl cry; hyg	925		3.98		s H_2O
1291	Lutetium fluoride	LuF_3	13760-81-1	231.962	orth cry	1182	2200	8.3		i H_2O
1292	Lutetium iodide	LuI_3	13813-45-1	555.680	brn hex cry; hyg	1050		≈5.6		vs H_2O
1293	Lutetium nitride	LuN	12125-25-6	188.974	cub cry			11.6		
1294	Lutetium oxide	Lu_2O_3	12032-20-1	397.932	wh cub cry or powder	2427	3980	9.41		
1295	Lutetium sulfate octahydrate	$Lu_2(SO_4)_3 \cdot 8H_2O$	13473-77-3	782.247	wh cry					vs H_2O
1296	Lutetium sulfide	Lu_2S_3	12163-20-1	446.132	gray rhomb cry	1750 dec		6.26		
1297	Lutetium telluride	Lu_2Te_3	12163-22-3	732.73	orth cry			7.8		
1298	Magnesium	Mg	7439-95-4	24.305	silv-wh metal	650	1090	1.74		s dil acid
1299	Magnesium acetate	$Mg(C_2H_3O_2)_2$	142-72-3	142.394	wh orth/mcl cry	323 dec		1.50	65.6^{25}	
1300	Magnesium acetate tetrahydrate	$Mg(C_2H_3O_2)_2 \cdot 4H_2O$	16674-78-5	214.454	col monocl cry; hyg	80 dec		1.45	65.6^{25}	vs EtOH
1301	Magnesium amide	$Mg(NH_2)_2$	7803-54-5	56.350	wh powder; flam	dec		1.39		reac H_2O
1302	Magnesium antimonide	Mg_3Sb_2	12057-75-9	316.435	hex cry	1245		3.99		
1303	Magnesium boride	MgB_2	12007-25-9	45.927	hex cry	800 dec		2.57		

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1304	Magnesium bromate hexahydrate	$Mg(BrO_3)_2 \cdot 6H_2O$	7789-36-8	388.201	col cub cry	200 dec		2.29	98^{25}	
1305	Magnesium bromide	$MgBr_2$	7789-48-2	184.113	wh hex cry; hyg	711		3.72	102^{25}	
1306	Magnesium bromide hexahydrate	$MgBr_2 \cdot 6H_2O$	13446-53-2	292.204	col monocl cry	165 dec		2.0	102^{25}	s EtOH
1307	Magnesium carbonate	$MgCO_3$	546-93-0	84.314	wh hex cry	990		3.05	0.18^{20}	i EtOH; s acid
1308	Magnesium chlorate hexahydrate	$Mg(ClO_3)_2 \cdot 6H_2O$	13446-19-0	299.298	wh hyg cry	≈35 dec		1.80	142^{25}	sl EtOH
1309	Magnesium chloride	$MgCl_2$	7786-30-3	95.210	wh hex leaflets; hyg	714	1412	2.325	56.0^{25}	
1310	Magnesium chloride hexahydrate	$MgCl_2 \cdot 6H_2O$	7791-18-6	203.301	wh hyg cry	≈100 dec		1.56	56.0^{25}	s EtOH
1311	Magnesium chromate heptahydrate	$MgCrO_4 \cdot 7H_2O$	13423-61-5*	266.405	yel rhom cry			1.695	54.8^{25}	
1312	Magnesium fluoride	MgF_2	7783-40-6	62.302	wh tetr cry	1263	2227	3.148	0.013^{25}	
1313	Magnesium formate dihydrate	$Mg(CHO_2)_2 \cdot 2H_2O$	6150-82-9	150.370	wh cry	dec				s H_2O; i EtOH
1314	Magnesium germanide	Mg_2Ge	1310-52-7	121.22	cub cry	1117		3.09		
1315	Magnesium hydride	MgH_2	7693-27-8	26.321	wh tetr cry	327		1.45		reac H_2O
1316	Magnesium hydrogen phosphate trihydrate	$MgHPO_4 \cdot 3H_2O$	7757-86-0	174.331	wh powder	550 dec		2.13		sl H_2O; s dil acid
1317	Magnesium hydroxide	$Mg(OH)_2$	1309-42-8	58.320	wh hex cry	350		2.37	0.00069^{20}	s dil acid
1318	Magnesium iodate tetrahydrate	$Mg(IO_3)_2 \cdot 4H_2O$	7790-32-1*	446.172	col mono cry	210 dec		3.3	11.1^{25}	
1319	Magnesium iodide	MgI_2	10377-58-9	278.114	wh hex cry; hyg	634		4.43	146^{25}	
1320	Magnesium iodide octahydrate	$MgI_2 \cdot 8H_2O$	7790-31-0	422.236	wh orth cry; hyg	41 dec		2.10	146^{25}	s EtOH
1321	Magnesium nitrate	$Mg(NO_3)_2$	10377-60-3	148.314	wh cub cry			≈2.3	71.2^{25}	
1322	Magnesium nitrate dihydrate	$Mg(NO_3)_2 \cdot 2H_2O$	15750-45-5	184.345	wh cry	≈100 dec		1.45	71.2^{25}	s EtOH
1323	Magnesium nitrate hexahydrate	$Mg(NO_3)_2 \cdot 6H_2O$	13446-18-9	256.406	col monocl cry; hyg	≈95 dec		1.46	71.2^{25}	s EtOH
1324	Magnesium nitride	Mg_3N_2	12057-71-5	100.928	yel cub cry	≈1500 dec		2.71		
1325	Magnesium nitrite trihydrate	$Mg(NO_2)_2 \cdot 3H_2O$	15070-34-5	170.362	wh hyg prisms	100 dec			129.9^{25}	s EtOH
1326	Magnesium oxalate	MgC_2O_4	547-66-0	112.324	wh pdw				0.038^{25}	
1327	Magnesium oxalate dihydrate	$MgC_2O_4 \cdot 2H_2O$	6150-88-5	148.354	wh powder				0.038^{25}	i EtOH; s dil acid
1328	Magnesium oxide	MgO	1309-48-4	40.304	wh cub cry	2825	3600	3.6		sl H_2O; i EtOH
1329	Magnesium perchlorate	$Mg(ClO_4)_2$	10034-81-8	223.205	wh hyg powder	250 dec		2.2	100^{25}	
1330	Magnesium perchlorate hexahydrate	$Mg(ClO_4)_2 \cdot 6H_2O$	13446-19-0	331.297	wh hyg cry	190 dec		1.98	100^{25}	s EtOH
1331	Magnesium permanganate hexahydrate	$Mg(MnO_4)_2 \cdot 6H_2O$	10377-62-5	370.268	blue-blk cry	dec		2.18		s H_2O
1332	Magnesium peroxide	MgO_2	1335-26-8	56.304	wh cub cry	100 dec		≈3.0		i H_2O; s dil acid
1333	Magnesium phosphate pentahydrate	$Mg_3(PO_4)_2 \cdot 5H_2O$	7757-87-1*	352.934	wh cry	400 dec			0.00009^{20}	s dil acid
1334	Magnesium phosphate octahydrate	$Mg_3(PO_4)_2 \cdot 8H_2O$	13446-23-6	406.980	wh monocl cry			2.17	0.00009^{20}	s acid
1335	Magnesium pyrophosphate trihydrate	$Mg_2P_2O_7 \cdot 3H_2O$	10102-34-8	276.600	wh powder	100 dec		2.56		i H_2O; s acid
1336	Magnesium phosphide	Mg_3P_2	12057-74-8	134.863	yel cub cry			2.06		reac H_2O
1337	Magnesium selenate hexahydrate	$MgSeO_4 \cdot 6H_2O$	13446-28-1	275.35	wh monocl cry			1.928	55.5^{25}	
1338	Magnesium selenide	MgSe	1313-04-8	103.27	brn cub cry			4.2		reac H_2O
1339	Magnesium selenite hexahydrate	$MgSeO_3 \cdot 6H_2O$	15593-61-0	259.36	col hex cry			2.09		i H_2O; s dil acid
1340	Magnesium metasilicate	$MgSiO_3$	13776-74-4	100.389	wh monocl cry	≈1550 dec		3.19		i H_2O; sl HF
1341	Magnesium orthosilicate	Mg_2SiO_4	26686-77-1	140.694	wh orth cry	1897		3.21		i H_2O
1342	Magnesium trisilicate	$Mg_2Si_3O_8$	14987-04-3	260.862	wh pow					i H_2O, EtOH
1343	Magnesium hexafluorosilicate hexahydrate	$MgSiF_6 \cdot 6H_2O$	60950-56-3	274.472	wh cry	120 dec		1.79	39.3^{18}	i EtOH
1344	Magnesium silicide	Mg_2Si	22831-39-6	76.696	gray cub cry	1102		1.99		reac H_2O
1345	Magnesium stannide	Mg_2Sn	1313-08-2	167.320	blue cub cry	771		3.60		s H_2O, dil HCl
1346	Magnesium sulfate	$MgSO_4$	7487-88-9	120.369	col orth cry	1127		2.66	35.7^{25}	
1347	Magnesium sulfate monohydrate	$MgSO_4 \cdot H_2O$	14168-73-1	138.384	col monocl cry	150 dec		2.57	35.7^{25}	
1348	Magnesium sulfate heptahydrate	$MgSO_4 \cdot 7H_2O$	10034-99-8	246.475	col orth cry	150 dec		1.67	35.7^{25}	sl EtOH
1349	Magnesium sulfide	MgS	12032-36-9	56.371	red-brn cub cry	2226		2.68		reac H_2O
1350	Magnesium sulfite trihydrate	$MgSO_3 \cdot 3H_2O$	19086-20-5	158.415	col orth cry			2.12	0.79^{25}	

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1351	Magnesium sulfite hexahydrate	$MgSO_3 \cdot 6H_2O$	13446-29-2	212.461	wh hex cry	200 dec		1.72	0.79^{25}	i EtOH
1352	Magnesium thiosulfate hexahydrate	$MgS_2O_3 \cdot 6H_2O$	13446-30-5	244.527	col cry	170 dec		1.82	93^{25}	i EtOH
1353	Magnesium titanate	$MgTiO_3$	1312-99-8	120.170	col hex cry	1565		3.85		
1354	Magnesium tungstate	$MgWO_4$	13573-11-0	272.14	wh monocl cry			6.89	0.016^{20}	i EtOH
1355	Manganese	Mn	7439-96-5	54.938	hard gray metal	1246	2061	7.3		s dil acids
1356	Manganese antimonide	MnSb	12032-82-5	176.698	hex cry	840		6.9		
1357	Manganese antimonide	Mn_2Sb	12032-97-2	231.636	tetr cry	948		7.0		
1358	Manganese boride	MnB	12045-15-7	65.749	orth cry	1890		6.45		
1359	Manganese boride	MnB_2	12228-50-1	76.560	hex cry	1827		5.3		
1360	Manganese boride	Mn_2B	12045-16-8	120.687	red-brn tetr cry	1580		7.20		
1361	Manganese carbide	Mn_3C	12266-65-8	176.825	refrac solid	1520		6.89		
1362	Manganese carbonyl	$Mn_2(CO)_{10}$	10170-69-1	389.977	yel monocl cry	154		1.75		i H_2O; s os
1363	Manganese phosphide	MnP	12032-78-9	85.912	orth cry	1147		5.49		
1364	Manganese phosphide	Mn_2P	12333-54-9	140.850	hex cry	1327		6.0		
1365	Manganese(II) acetate tetrahydrate	$Mn(C_2H_3O_2)_2 \cdot 4H_2O$	6156-78-1	245.087	red monocl cry	80		1.59		s H_2O, EtOH
1366	Manganese(II) tetraborate octahydrate	$MnB_4O_7 \cdot 8H_2O$	12228-91-0	354.300	red solid					i H_2O, EtOH; s dil acid
1367	Manganese(II) bromide	$MnBr_2$	13446-03-2	214.746	pink hex cry	698		4.385	151^{25}	
1368	Manganese(II) bromide tetrahydrate	$MnBr_2 \cdot 4H_2O$	10031-20-6	286.808	red hyg cry	64 dec			151^{25}	
1369	Manganese(II) carbonate	$MnCO_3$	598-62-9	114.947	pink hex cry	>200 dec		3.70	0.00008^{20}	s dil acid
1370	Manganese(II) chloride	$MnCl_2$	7773-01-5	125.843	pink trig cry; hyg	650	1190	2.977	77.3^{25}	s py, EtOH; i eth
1371	Manganese(II) chloride tetrahydrate	$MnCl_2 \cdot 4H_2O$	13446-34-9	197.905	red monocl cry; hyg	87.5		1.913	77.3^{25}	s EtOH; i eth
1372	Manganese(II) dihydrogen phosphate dihydrate	$Mn(H_2PO_4)_2 \cdot 2H_2O$	18718-07-5	284.944	col hyg cry					s H_2O; i EtOH
1373	Manganese(II) fluoride	MnF_2	7782-64-1	92.935	red tetr cry	930		3.98	1.02^{25}	i EtOH
1374	Manganese(II) hydroxide	$Mn(OH)_2$	18933-05-6	88.953	pink hex cry	dec		3.26	0.00034^{20}	
1375	Manganese(II) iodide	MnI_2	7790-33-2	308.747	wh hex cry; hyg	638		5.04		s H_2O, EtOH
1376	Manganese(II) iodide tetrahydrate	$MnI_2 \cdot 4H_2O$	7790-33-2*	380.809	red cry					vs H_2O; s EtOH
1377	Manganese(II) molybdate	$MnMoO_4$	14013-15-1	214.88	yel monocl cry			4.05		
1378	Manganese(II) nitrate	$Mn(NO_3)_2$	10377-93-2	178.948	col orth cry; hyg			2.2	161^{25}	s diox, thf
1379	Manganese(II) nitrate hexahydrate	$Mn(NO_3)_2 \cdot 6H_2O$	10377-66-9	287.040	rose monocl cry	28 dec		1.8	161^{25}	vs EtOH
1380	Manganese(II) nitrate tetrahydrate	$Mn(NO_3)_2 \cdot 4H_2O$	20694-39-7	251.010	pink hyg cry	37.1 dec		2.13	161^{25}	s EtOH
1381	Manganese(II) oxalate dihydrate	$MnC_2O_4 \cdot 2H_2O$	6556-16-7	178.987	wh cry powder	150 dec		2.45	0.032^{20}	s acid
1382	Manganese(II) oxide	MnO	1344-43-0	70.937	gr cub cry or powder	1839		5.37		i H_2O; s acid
1383	Manganese(II) perchlorate hexahydrate	$Mn(ClO_4)_2 \cdot 6H_2O$	15364-94-0	361.930	pink hex cry			2.10		
1384	Manganese(II) pyrophosphate	$Mn_2P_2O_7$	53731-35-4	283.819	wh monocl cry	1196		3.71		i H_2O
1385	Manganese(II) metasilicate	$MnSiO_3$	7759-00-4	131.022	red orth cry	1291		3.48		i H_2O
1386	Manganese(II) orthosilicate	Mn_2SiO_4	13568-32-6	201.960	orth cry			4.11		i H_2O
1387	Manganese(II) selenide	MnSe	1313-22-0	133.90	gray cub cry	1460		5.45		i H_2O
1388	Manganese(II) sulfate	$MnSO_4$	7785-87-7	151.002	wh orth cry	700	850 dec	3.25	63.7^{25}	
1389	Manganese(II) sulfate monohydrate	$MnSO_4 \cdot H_2O$	10034-96-5	169.017	red monocl cry			2.95	63.7^{25}	i EtOH
1390	Manganese(II) sulfate tetrahydrate	$MnSO_4 \cdot 4H_2O$	10101-68-5	223.063	red monocl cry	38 dec		2.26	63.7^{25}	i EtOH
1391	Manganese(II) sulfide (α form)	MnS	18820-29-6	87.004	grn cub cry	1610		4.0		i H_2O; s dil acid
1392	Manganese(II) sulfide (β form)	MnS	18820-29-6	87.004	red cub cry			3.3		i H_2O; s dil acid
1393	Manganese(II) sulfide (γ form)	MnS	18820-29-6	87.004	red hex cry			≈3.3		i H_2O; s dil acid
1394	Manganese(II) telluride	MnTe	12032-88-1	182.54	hex cry	≈1150		6.0		
1395	Manganese(II) titanate	$MnTiO_3$	12032-74-5	150.803	red hex cry	1360		4.55		
1396	Manganese(II) tungstate	$MnWO_4$	13918-22-4	302.78	wh monocl cry			7.2	0.0054^{20}	
1397	Manganese(II,III) oxide	Mn_3O_4	1317-35-7	228.812	brn tetr cry	1567		4.84		i H_2O; s HCl
1398	Manganese(III) fluoride	MnF_3	7783-53-1	111.933	red monocl cry; hyg	>600 dec		3.54		reac H_2O
1399	Manganese(III) hydroxide	MnO(OH)	1332-63-4	87.945	blk monocl cry	250 dec		≈4.3		i H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1400	Manganese(III) oxide	Mn_2O_3	1317-34-6	157.874	blk cub cry	1080 dec		≈5.0		i H_2O
1401	Manganese(IV) oxide	MnO_2	1313-13-9	86.937	blk tetr cry	535 dec		5.08		i H_2O, HNO_3
1402	Manganese(VII) oxide	Mn_2O_7	12057-92-0	221.872	grn oil; exp	5.9	95 exp	2.40		vs H_2O
1403	Mendelevium	Md	7440-11-1	258	Metal	827				
1404	Mercury	Hg	7439-97-6	200.59	heavy silv liq	-38.837 tp	356.62	13.5336		i H_2O
1405	Mercury(I) acetate	$Hg_2(C_2H_3O_2)_2$	631-60-7	519.27	col scales	dec				sl H_2O; i EtOH, eth
1406	Mercury(I) bromate	$Hg_2(BrO_3)_2$	13465-33-3	656.98	col cry	dec				i H_2O; sl acid
1407	Mercury(I) bromide	Hg_2Br_2	15385-58-7	560.99	wh tetr cry or powder	407		7.307		i H_2O, EtOH, eth
1408	Mercury(I) carbonate	Hg_2CO_3	6824-78-8	461.19	yel-brn cry	130 dec			0.0000045	i EtOH
1409	Mercury(I) chlorate	$Hg_2(ClO_3)_2$	10294-44-7	568.08	wh rhom cry	≈250 dec		6.409		sl H_2O; s EtOH
1410	Mercury(I) chloride	Hg_2Cl_2	10112-91-1	472.09	wh tetr cry	525 tp	383 sp	7.16	0.0004^{25}	i EtOH, eth
1411	Mercury(I) fluoride	Hg_2F_2	13967-25-4	439.18	yel cub cry	570 dec	subl	8.73		reac H_2O
1412	Mercury(I) iodide	Hg_2I_2	15385-57-6	654.99	yel amorp powder	290		7.70		i H_2O, EtOH, eth
1413	Mercury(I) nitrate	$Hg_2(NO_3)_2$	10415-75-5	525.19	cry					sl H_2O
1414	Mercury(I) nitrate dihydrate	$Hg_2(NO_3)_2 \cdot 2H_2O$	7782-86-7	561.22	col cry	70 dec		4.8		sl H_2O
1415	Mercury(I) nitrite	$Hg_2(NO_2)_2$	13492-25-6	493.19	yel cry	100 dec		7.3		reac H_2O
1416	Mercury(I) oxalate	$Hg_2C_2O_4$	2949-11-3	489.20	cry					i H_2O; sl HNO_3
1417	Mercury(I) oxide	Hg_2O	15829-53-5	417.18	prob mixture of HgO+Hg	100 dec		9.8		i H_2O; s HNO_3
1418	Mercury(I) perchlorate tetrahydrate	$Hg_2(ClO_4)_2 \cdot 4H_2O$	65202-12-2	672.14	cry	64			442^{25}	
1419	Mercury(I) sulfate	Hg_2SO_4	7783-36-0	497.24	wh-yel cry powder			7.56	0.051^{25}	s dil HNO_3
1420	Mercury(I) thiocyanate	$Hg_2(SCN)_2$		517.35	col pow	dec			0.03^{25}	s HCl, KCNS
1421	Mercury(I) tungstate	Hg_2WO_4	38705-19-0	649.02	yel amorp solid	dec				i H_2O, EtOH
1422	Mercury(II) acetate	$Hg(C_2H_3O_2)_2$	1600-27-7	318.68	wh-yel cry or powder	179 dec		3.28	25^{10}	s EtOH
1423	Mercury(II) amide chloride	$Hg(NH_2)Cl$	10124-48-8	252.07	wh solid		subl	5.38		i H_2O, EtOH; s warm acid
1424	Mercury(II) bromate	$Hg(BrO_3)_2$	26522-91-8	456.39	cry	130 dec			0.15	s acid
1425	Mercury(II) bromide	$HgBr_2$	7789-47-1	360.40	wh rhomb cry or powder	236	322	6.05	0.61^{25}	sl chl; s EtOH, MeOH
1426	Mercury(II) chlorate	$Hg(ClO_3)_2$		367.49	wh needles	dec		4.998	25	
1427	Mercury(II) chloride	$HgCl_2$	7487-94-7	271.50	wh orth cry	276	304	5.6	7.31^{25}	sl bz; s EtOH, MeOH, ace, eth
1428	Mercury(II) chromate	$HgCrO_4$	13444-75-2	316.58	red monocl cry			6.06		sl H_2O
1429	Mercury(II) cyanide	$Hg(CN)_2$	592-04-1	252.62	col tetr cry	320 dec		4.00	11.4^{25}	s EtOH; sl eth
1430	Mercury(II) dichromate	$HgCr_2O_7$	7789-10-8	416.58	red cry powder					i H_2O; s acid
1431	Mercury(II) fluoride	HgF_2	7783-39-3	238.59	wh cub cry; hyg	645 dec		8.95		reac H_2O
1432	Mercury(II) fulminate	$Hg(CNO)_2$	628-86-4	284.62	gray cry	exp		4.42		sl H_2O; s EtOH, NH_4OH
1433	Mercury(II) hydrogen arsenate	$HgHAsO_4$	7784-37-4	340.52	yel powder					i H_2O; s acid
1434	Mercury(II) iodate	$Hg(IO_3)_2$	7783-32-6	550.40	wh powder	175 dec				i H_2O
1435	Mercury(II) iodide	HgI_2	7774-29-0	454.40	red tetr cry or powder	259	354	6.28	0.0055^{25}	sl EtOH, ace, eth
1436	Mercury(II) nitrate	$Hg(NO_3)_2$	10045-94-0	324.60	col hyg cry	79		4.3		s H_2O; i EtOH
1437	Mercury(II) nitrate dihydrate	$Hg(NO_3)_2 \cdot 2H_2O$	10045-94-0*	360.63	monocl cry			4.78		s H_2O
1438	Mercury(II) nitrate monohydrate	$Hg(NO_3)_2 \cdot H_2O$	7783-34-8	342.62	wh-yel hyg cry			4.3		s H_2O, dil acid
1439	Mercury(II) oxalate	HgC_2O_4	3444-13-1	288.61	pwd	165 dec				i H_2O
1440	Mercury(II) oxide	HgO	21908-53-2	216.59	red or yel orth cry	500 dec		11.14		i H_2O, EtOH; s dil acid
1441	Mercury(II) oxide sulfate	$(Hg_3O_2)SO_4$	1312-03-4	729.83	yel pow					i H_2O; s acid
1442	Mercury(II) oxycyanide	$Hg(CN)_2 \cdot HgO$	1335-31-5	469.21	wh orth cry	exp		4.44	11.4^{25}	
1443	Mercury(II) perchlorate trihydrate	$Hg(ClO_4)_2 \cdot 3H_2O$	7616-83-3	453.54	cry					
1444	Mercury(II) phosphate	$Hg_3(PO_4)_2$	7782-66-3	791.71	wh-yel powder					i H_2O, EtOH; s acid
1445	Mercury(II) selenide	HgSe	20601-83-6	279.55	gray cub cry		subl	8.21		i H_2O
1446	Mercury(II) sulfate	$HgSO_4$	7783-35-9	296.65	wh monocl cry			6.47		reac H_2O
1447	Mercury(II) sulfide (black)	HgS	1344-48-5	232.66	blk cub cry or powder	850		7.70		i H_2O; s acid, EtOH
1448	Mercury(II) sulfide (red)	HgS	1344-48-5	232.66	red hex cry	trans to blk HgS 344		8.17		i H_2O, acid; s aqua regia
1449	Mercury(II) telluride	HgTe	12068-90-5	328.19	gray cub cry	673		8.63		
1450	Mercury(II) thiocyanate	$Hg(SCN)_2$	592-85-8	316.76	monocl cry	≈165 dec		3.71	0.070^{25}	s dil HCl
1451	Mercury(II) tungstate	$HgWO_4$	37913-38-5	448.43	yel cry	dec				i H_2O, EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1452	Molybdenum	Mo	7439-98-7	95.94	gray-blk metal; cub	2622	4639	10.2		i H_2O, dil acid, alk
1453	Molybdenum boride	Mo_2B	12006-99-4	202.69	refrac tetr cry	2000		9.2		
1454	Molybdenum boride	Mo_2B_5	12007-97-5	245.94	refrac hex cry	1600		≈7.2		
1455	Molybdenum carbide	MoC	12011-97-1	107.95	refrac solid; cub	2577				
1456	Molybdenum carbide	Mo_2C	12069-89-5	203.89	gray orth cry	2687		9.18		
1457	Molybdenum hexacarbonyl	$Mo(CO)_6$	13939-06-5	264.00	wh orth cry	148	155 dec	1.96		i H_2O; s bz; sl eth
1458	Molybdenum nitride	MoN	12033-19-1	109.95	hex cry	1750		9.20		
1459	Molybdenum nitride	Mo_2N	12033-31-7	205.89	gray cub cry	790 dec		9.46		
1460	Molybdenum phosphide	MoP	12163-69-8	126.91	blk hex cry			7.34		
1461	Molybdenum silicide	$MoSi_2$	12136-78-6	152.11	gray tetr cry	≈1900		6.2		i H_2O; s HF
1462	Molybdenum(II) bromide	$MoBr_2$	13446-56-5	255.75	yel-red cry	900 dec				
1463	Molybdenum(II) chloride	$MoCl_2$	13478-17-6	166.85	yel cry	530 dec				
1464	Molybdenum(II) iodide	MoI_2	14055-74-4	349.75	blk hyg cry			5.278		
1465	Molybdenum(III) bromide	$MoBr_3$	13446-57-6	335.65	grn hex cry	977		4.89		i H_2O
1466	Molybdenum(III) chloride	$MoCl_3$	13478-18-7	202.30	dark red monocl cry	1027		3.74		i H_2O
1467	Molybdenum(III) fluoride	MoF_3	20193-58-2	152.94	brn hex cry	>600		4.64		i H_2O
1468	Molybdenum(III) iodide	MoI_3	14055-75-5	476.65	blk solid	927				i H_2O
1469	Molybdenum(III) oxide	Mo_2O_3	1313-29-7	239.88	gray-blk powder					i H_2O; sl acid
1470	Molybdenum(IV) bromide	$MoBr_4$	13520-59-7	415.56	blk cry	dec				reac H_2O
1471	Molybdenum(IV) chloride	$MoCl_4$	13320-71-3	237.75	blk cry	>170 dec				reac H_2O
1472	Molybdenum(IV) fluoride	MoF_4	23412-45-5	171.93	grn cry	dec				reac H_2O
1473	Molybdenum(IV) oxide	MoO_2	18868-43-4	127.94	brn-viol tetr cry	≈1100 dec		6.47		sl H_2O
1474	Molybdenum(IV) selenide	$MoSe_2$	12058-18-3	253.86	gray hex cry	>1200		6.90		
1475	Molybdenum(IV) sulfide	MoS_2	1317-33-5	160.07	blk powder or hex cry	1750		5.06		i H_2O; s conc acid
1476	Molybdenum(IV) telluride	$MoTe_2$	12058-20-7	351.14	gray hex cry			7.7		
1477	Molybdenum(V) chloride	$MoCl_5$	10241-05-1	273.20	gr-blk monocl cry; hyg	194	268	2.93		s EtOH, eth
1478	Molybdenum(V) fluoride	MoF_5	13819-84-6	190.93	yel monocl cry	67	213.6	3.5		
1479	Molybdenum(V) oxytrichloride	$MoOCl_3$	13814-74-9	218.30	blk monocl cry	297	subl			reac H_2O
1480	Molybdenum(VI) acid monohydrate	$H_2MoO_4 \cdot H_2O$	7782-91-4	179.97	wh powder			3.1		sl H_2O; s alk
1481	Molybdenum(VI) fluoride	MoF_6	7783-77-9	209.93	wh cub cry or col liq; hyg	17.5	34.0	2.54		reac H_2O
1482	Molybdenum(VI) oxytetrafluoride	$MoOF_4$	14459-59-7	187.93	volatile solid	98	186.0			
1483	Molybdenum(VI) oxytetrachloride	$MoOCl_4$	13814-75-0	253.75	grn hyg powder	101				
1484	Molybdenum(VI) dioxydichloride	MoO_2Cl_2	13637-68-8	198.84	yel-oran solid	≈175		3.31		reac H_2O
1485	Molybdenum(VI) oxide	MoO_3	1313-27-5	143.94	wh-yel rhomb cry	801	1155	4.70	0.14^{20}	s conc acid
1486	Molybdenum(VI) metaphosphate	$Mo(PO_3)_6$	133863-98-6	569.77	yel powder			3.28		i H_2O, acid
1487	Neodymium	Nd	7440-00-8	144.24	silv metal; hex	1021	3074	7.01		
1488	Neodymium boride	NdB_6	12008-23-0	209.11	blk cub cry	2610		4.93		
1489	Neodymium bromide	$NdBr_3$	13536-80-6	383.95	viol orth cry; hyg	682	1540	5.3		s H_2O
1490	Neodymium chloride	$NdCl_3$	10024-93-8	250.60	viol hex cry	758	1600	4.13	100^{25}	vs EtOH; i eth, chl
1491	Neodymium chloride hexahydrate	$NdCl_3 \cdot 6H_2O$	13477-89-9	358.69	purp cry	124 dec		2.3	100^{25}	s EtOH
1492	Neodymium fluoride	NdF_3	13709-42-7	201.24	viol hex cry; hyg	1377	2300	6.51		i H_2O
1493	Neodymium iodide	NdI_3	13813-24-6	524.95	grn orth cry; hyg	784		5.85		s H_2O
1494	Neodymium nitrate	$Nd(NO_3)_3$	10045-95-1	330.26	viol hyg. cry				152^{25}	s EtOH
1495	Neodymium nitrate hexahydrate	$Nd(NO_3)_3 \cdot 6H_2O$	14517-29-4	438.35	purp hyg cry				152^{25}	s EtOH, ace
1496	Neodymium nitride	NdN	25764-11-8	158.25	blk cub cry			7.69		
1497	Neodymium oxide	Nd_2O_3	1313-97-9	336.48	blue hex cry; hyg	2233	3760	7.24		i H_2O; s dil acid
1498	Neodymium sulfate	$Nd_2(SO_4)_3$	13477-91-3	576.67	pink needles	≈700 dec			7.1^{20}	
1499	Nickel(II) perchlorate hexahydrate	$Ni(ClO_4)_2 \cdot 6H_2O$	13637-71-3*	365.685	grn hex needles	140			158.8^{25}	s EtOH, ace
1500	Neodymium sulfide	Nd_2S_3	12035-32-4	384.68	orth cry	2207		5.46		
1501	Nickel(II) phosphate octahydrate	$Ni_3(PO_4)_2 \cdot 8H_2O$	10381-36-9*	510.145	grn plates					s acid
1502	Nickel(II) selenate hexahydrate	$NiSeO_4 \cdot 6H_2O$	15060-62-5*	309.74	grn tetr cry			2.314	35.5^{20}	

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1503	Neodymium telluride	Nd_2Te_3	12035-35-7	671.28	gray orth cry	1377		7.0		
1504	Neon	Ne	7440-01-9	20.180	col gas	-248.609 tp (43 kPa)	-246.053	0.825 g/L		sl H_2O
1505	Neptunium	Np	7439-99-8	237	silv metal	644		20.2		s HCl
1506	Neptunium(IV) oxide	NpO_2	12035-79-9	269	grn cub cry	2547		11.1		
1507	Nickel	Ni	7440-02-0	58.693	wh metal; cub	1455	2913	8.90		i H_2O; sl dil acid
1508	Nickel antimonide	NiSb	12035-52-8	180.453	hex cry	1147		8.74		
1509	Nickel arsenide	NiAs	27016-75-7	133.615	hex cry	967		7.77		
1510	Nickel boride	Ni_3B	12007-02-2	186.891	refrac solid	1156		8.17		
1511	Nickel boride	NiB	12007-00-0	69.504	grn refrac solid	1035		7.13		
1512	Nickel boride	Ni_2B	12007-01-1	128.198	refrac solid	1125		7.90		
1513	Nickel carbonyl	$Ni(CO)_4$	13463-39-3	170.734	col liq	-19.3	43 (exp ≈60)	1.31		i H_2O; s EtOH, bz, ace, ctc
1514	Nickel phosphide	Ni_2P	12035-64-2	148.361	hex cry	1100		7.33		
1515	Nickel silicide	Ni_2Si	12059-14-2	145.473	orth cry	1255		7.40		
1516	Nickel silicide	$NiSi_2$	12201-89-7	114.864	cub cry	993		4.83		
1517	Nickel(II) ammonium sulfate hexahydrate	$Ni(NH_4)_2(SO4)_2 \cdot 6H_2O$	15699-18-0	394.989	blue-grn cry			1.923	6.5^{20}	i EtOH
1518	Nickel(II) arsenate octahydrate	$Ni_3(AsO_4)_2 \cdot 8H_2O$	7784-48-7	598.040	yel-grn powder	dec		4.98		i H_2O; s acid
1519	Nickel(II) bromide	$NiBr_2$	13462-88-9	218.501	yel hex cry; hyg	963	subl	5.10	131^{20}	
1520	Nickel(II) bromide trihydrate	$NiBr_2 \cdot 3H_2O$	13462-88-9*	272.547	yel-grn hyg cry	200 dec				vs H_2O; s EtOH, eth
1521	Nickel(II) carbonate	$NiCO_3$	3333-67-3	118.702	grn rhomb cry			4.39	0.0043^{20}	s dil acid
1522	Nickel(II) chloride	$NiCl_2$	7718-54-9	129.598	yel hex cry; hyg	1009 tp	985 sp	3.51	67.5^{25}	s EtOH
1523	Nickel(II) chloride hexahydrate	$NiCl_2 \cdot 6H_2O$	7791-20-0	237.689	grn monocl cry				67.5^{25}	s EtOH
1524	Nickel(II) cyanide tetrahydrate	$Ni(CN)_2 \cdot 4H_2O$	13477-95-7	182.789	grn plates	200 dec				i H_2O; sl dil acid; s NH_4OH
1525	Nickel(II) fluoride	NiF_2	10028-18-9	96.690	yel tetr cry	1474		4.7	2.56^{25}	i EtOH, eth
1526	Nickel(II) hydroxide	$Ni(OH)_2$	12054-48-7	92.708	grn hex cry	230 dec		4.1	0.00015^{20}	
1527	Nickel(II) hydroxide monohydrate	$Ni(OH)_2 \cdot H_2O$	36897-37-7	110.723	grn powder				0.00015^{20}	s dil acid
1528	Nickel(II) iodate	$Ni(IO_3)_2$	13477-98-0	408.498	yel needles			5.07	1.1^{30}	
1529	Nickel(II) iodide	NiI_2	13462-90-3	312.502	blk hex cry; hyg	780	subl	5.22	154^{25}	
1530	Nickel(II) iodide hexahydrate	$NiI_2 \cdot 6H_2O$	7790-34-3	420.593	grn monocl cry; hyg				154^{25}	vs EtOH
1531	Nickel(II) nitrate	$Ni(NO_3)_2$	13138-45-9	182.702	grn cry				99.2^{25}	s EtOH
1532	Nickel(II) nitrate hexahydrate	$Ni(NO_3)_2 \cdot 6H_2O$	13478-00-7	290.794	grn monocl cry; hyg	56 dec		2.05	99.2^{25}	s EtOH
1533	Nickel(II) oxide	NiO	1313-99-1	74.692	grn cub cry	1955		6.72		i H_2O; s acid
1534	Nickel(II) selenide	NiSe	1314-05-2	137.65	yel-grn hex cry	980		7.2		
1535	Nickel(II) sulfate	$NiSO_4$	7786-81-4	154.757	grn-yel orth cry	840 dec		4.01	40.4^{25}	
1536	Nickel(II) sulfate heptahydrate	$NiSO_4 \cdot 7H_2O$	10101-98-1	280.863	grn orth cry			1.98	40.4^{25}	s EtOH
1537	Nickel(II) sulfate hexahydrate	$NiSO_4 \cdot 6H_2O$	10101-97-0	262.848	blue-grn tetr cry	≈100 dec		2.07	40.4^{25}	sl EtOH
1538	Nickel(II) sulfide	NiS	16812-54-7	90.759	yel hex cry	976		5.5		i H_2O
1539	Nickel(II) thiocyanate	$Ni(SCN)_2$	13689-92-4	174.859	grn pwd				55.0^{25}	
1540	Nickel(II) titanate	$NiTiO_3$	12035-39-1	154.558	brn hex cry			5.0		
1541	Nickel(II,III) sulfide	Ni_3S_4	12137-12-1	304.344	cub cry	995		4.77		
1542	Nickel(III) oxide	Ni_2O_3	1314-06-3	165.385	gray-blk cub cry	≈600 dec				i H_2O; s hot acid
1543	Nickel(III) sulfide	Ni_3S_2	12035-72-2	240.212	hex cry	787		5.87		
1544	Niobium	Nb	7440-03-1	92.906	gray metal; cub	2477	4744	8.57		i acid
1545	Niobium boride	NbB	12045-19-1	103.717	gray orth cry	2270		7.5		
1546	Niobium boride	NbB_2	12007-29-3	114.528	gray hex cry	3050		6.97		
1547	Niobium carbide	NbC	12069-94-2	104.917	gray cub cry	3608	4300	7.82		i H_2O, acid
1548	Niobium carbide	Nb_2C	12011-99-3	197.824	refrac hex cry	3080		7.8		i H_2O
1549	Niobium nitride	NbN	24621-21-4	106.913	gray cry; cub	2300		8.47		i HCl, acid
1550	Niobium phosphide	NbP	12034-66-1	123.880	tetr cry			6.5		
1551	Niobium silicide	$NbSi_2$	12034-80-9	149.077	gray hex cry	1950		5.7		
1552	Niobium(II) oxide	NbO	12034-57-0	108.905	gray cub cry	1936		7.30		
1553	Niobium(III) bromide	$NbBr_3$	15752-41-7	332.618	dark brn solid		subl			
1554	Niobium(III) chloride	$NbCl_3$	13569-59-0	199.264	blk solid					
1555	Niobium(III) fluoride	NbF_3	15195-53-6	149.901	blue cub cry			4.2		
1556	Niobium(IV) chloride	$NbCl_4$	13569-70-5	234.717	viol-blk monocl cry		275 subl	3.2		
1557	Niobium(IV) fluoride	NbF_4	13842-88-1	168.900	blk tetr cry; hyg	>350 dec		4.01		
1558	Niobium(IV) iodide	NbI_4	13870-21-8	600.524	gray orth cry	503		5.6		

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1559	Niobium(IV) oxide	NbO_2	12034-59-2	124.905	wh tetr cry or powder	1901		5.9		
1560	Niobium(IV) selenide	$NbSe_2$	12034-77-4	250.83	gray hex cry	>1300		6.3		
1561	Niobium(IV) sulfide	NbS_2	12136-97-9	157.038	blk rhomb cry			4.4		
1562	Niobium(IV) telluride	$NbTe_2$	12034-83-2	348.11	hex cry			7.6		
1563	Niobium(V) bromide	$NbBr_5$	13478-45-0	492.426	oran orth cry	254	360	4.36		s H_2O, EtOH
1564	Niobium(V) chloride	$NbCl_5$	10026-12-7	270.170	yel monocl cry; hyg	204.7	254.0	2.78		reac H_2O; s HCl, ctc
1565	Niobium(V) fluoride	NbF_5	7783-68-8	187.898	col monocl cry; hyg	80	229	2.70		reac H_2O; sl CS_2, chl
1566	Niobium(V) iodide	NbI_5	13779-92-5	727.428	yel-blk monocl cry	≈200 dec		5.32		
1567	Niobium(V) oxide	Nb_2O_5	1313-96-8	265.810	wh orth cry	1512		4.6		i H_2O; s HF
1568	Niobium(V) oxybromide	$NbOBr_3$	14459-75-7	348.617	yel-brn cry	≈320 dec	subl			
1569	Niobium(V) oxychloride	$NbOCl_3$	13597-20-1	215.263	wh tetr cry		subl	3.72		
1570	Niobium(V) dioxyfluoride	NbO_2F	15195-33-2	143.903	wh cub cry			4.0		
1571	Nitrogen	N_2	7727-37-9	28.013	col gas	-210.0	-195.798	1.145 g/L		sl H_2O; i EtOH
1572	Nitramide	NO_2NH_2	7782-94-7	62.028	unstable wh cry	72 dec				s H_2O, EtOH, ace, eth; i chl
1573	Nitric acid	HNO_3	7697-37-2	63.013	col liq; hyg	-41.6	83	1.5129^{20}		vs H_2O
1574	Nitrous acid	HNO_2	7782-77-6	47.014	stable only in soln					
1575	Nitrous oxide	N_2O	10024-97-2	44.012	col gas	-90.8	-88.48	1.799 g/L		sl H_2O; s EtOH, eth
1576	Nitric oxide	NO	10102-43-9	30.006	col gas	-163.6	-151.74	1.226 g/L		sl H_2O
1577	Nitrogen dioxide	NO_2	10102-44-0	46.006	brn gas; equil with N_2O_4		see N_2O_4	1.880 g/L		reac H_2O
1578	Nitrogen trioxide	N_2O_3	10544-73-7	76.011	blue solid or liq (low temp)	-101.1	≈3 dec	1.4^{2}		reac H_2O
1579	Nitrogen tetroxide	N_2O_4	10544-72-6	92.011	col liq; equil with NO_2	-9.3	21.15	1.45^{20}		reac H_2O
1580	Nitrogen pentoxide	N_2O_5	10102-03-1	108.010	col hex cry		33 sp	2.0		s chl; sl ctc
1581	Nitrogen tribromide	NBr_3	15162-90-0	253.719	unstable solid	exp -100				
1582	Nitrogen trichloride	NCl_3	10025-85-1	120.365	yel oily liq; exp	-40	71	1.653		i H_2O; s CS_2, bz, ctc
1583	Nitrogen trifluoride	NF_3	7783-54-2	71.002	col gas	-206.79	-128.75	2.902 g/L		i H_2O
1584	Nitrogen triiodide	NI_3	13444-85-4	394.720	unstable blk cry; exp					
1585	Nitrogen chloride difluoride	$NClF_2$	13637-87-1	87.457	col gas	-195	-67	3.575 g/L		
1586	Chloramine	NH_2Cl	10599-90-3	51.476	yel liq	-66				s H_2O, EtOH, eth; sl bz, CCl_4
1587	Fluoramine	NH_2F	15861-05-9	35.021	unstable gas			1.431 g/L		
1588	Difluoramine	NHF_2	10405-27-3	53.012	col gas	-116	-23	2.167 g/L		
1589	cis-Difluorodiazine	N_2F_2	13812-43-6	66.010	col gas	<-195	-105.75	2.698 g/L		
1590	trans-Difluorodiazine	N_2F_2	13776-62-0	66.010	col gas	-172	-111.45	2.698 g/L		
1591	Tetrafluorohydrazine	N_2F_4	10036-47-2	104.007	col gas	-164.5	-74	4.251 g/L		
1592	Nitrosyl bromide	NOBr	13444-87-6	109.910	red gas	-56	≈0	4.492 g/L		reac H_2O
1593	Nitrosyl chloride	NOCl	2696-92-6	65.459	yel gas	-59.6	-5.5	2.676 g/L		reac H_2O
1594	Nitrosyl fluoride	NOF	7789-25-5	49.004	col gas	-132.5	-59.9	2.003 g/L		
1595	Trifluoramine oxide	NOF_3	13847-65-9	87.001	col gas	-161	-87.5	3.556 g/L		
1596	Nitryl chloride	NO_2Cl	13444-90-1	81.459	col gas	-145	-15	3.330 g/L		
1597	Nitryl fluoride	NO_2F	10022-50-1	65.004	col gas	-166	-72.4	2.657 g/L		reac H_2O
1598	Nitrogen selenide	N_4Se_4	12033-88-4	371.87	red monocl cry; hyg	exp		4.2		i H_2O, eth, EtOH; sl bz, CS_2
1599	Nobelium	No	10028-14-5	259	metal	827				
1600	Osmium	Os	7440-04-2	190.23	blue-wh metal; hex	3033	5012	22.59		s aqua regia
1601	Osmium carbonyl	$Os_3(CO)_{12}$	15696-40-9	906.81	yel cry			3.48		
1602	Osmium(III) bromide	$OsBr_3$	59201-51-3	429.94	dark gray cry	340 dec				
1603	Osmium(III) chloride	$OsCl_3$	13444-93-4	296.59	gray cub cry	>450 dec				i H_2O; s HNO_3
1604	Osmium(IV) chloride	$OsCl_4$	10026-01-4	332.04	red-blk orth cry		450 sp	4.38		reac H_2O
1605	Osmium(IV) fluoride	OsF_4	54120-05-7	266.22	yel cry	230				
1606	Osmium(IV) oxide	OsO_2	12036-02-1	222.23	yel-brn tetr cry			11.4		i H_2O, acid
1607	Osmium(V) fluoride	OsF_5	31576-40-6	285.22	blue cry	70	225.9			reac H_2O
1608	Osmium(VI) fluoride	OsF_6	13768-38-2	304.22	yel cub cry	33.2	47.5	4.1		reac H_2O
1609	Osmium(VIII) oxide	OsO_4	20816-12-0	254.23	yel monocl cry	41	135	5.1	6.44^{20}	
1610	Oxygen	O_2	7782-44-7	31.999	col gas	-218.79	-182.953	1.308 g/L		sl H_2O, EtOH, os
1611	Ozone	O_3	10028-15-6	47.998	blue gas	-193	-111.35	1.962 g/L		sl H_2O
1612	Palladium	Pd	7440-05-3	106.42	silv-wh metal; cub	1554.8	2963	12.0		s aqua regia
1613	Palladium(II) sulfide	PdS	12125-22-3	138.49	gray tetr cry			6.7		

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1614	Palladium(II) bromide	$PdBr_2$	13444-94-5	266.23	red-blk monocl cry; hyg	250 dec		≈5.2		i H_2O
1615	Palladium(II) chloride	$PdCl_2$	7647-10-1	177.33	red rhomb cry; hyg	679		4.0		s H_2O, EtOH, ace
1616	Palladium(II) fluoride	PdF_2	13444-96-7	144.42	viol tetr cry; hyg	952		5.76		reac H_2O
1617	Palladium(II) iodide	PdI_2	7790-38-7	360.23	blk cry	360 dec		6.0		i H_2O, EtOH, eth
1618	Palladium(II) nitrate	$Pd(NO_3)_2$	10102-05-3	230.43	brn hyg cry	dec				sl H_2O; s dil HNO_3
1619	Palladium(II) oxide	PdO	1314-08-5	122.42	grn-blk tetr cry	750 dec		8.3		i H_2O, acid; sl aqua regia
1620	Phosphorus (white)	P	7723-14-0	30.974	col waxlike cub cry	44.15	280.5	1.823		i H_2O; sl bz, EtOH, chl; s CS_2
1621	Phosphorus (red)	P	7723-14-0	30.974	red-viol amorp powder	590 tp	431 sp	2.16		i H_2O, os
1622	Phosphorus (black)	P	7723-14-0	30.974	blk orth cry or amorp solid	610		2.69		i os
1623	Phosphine	PH_3	7803-51-2	33.998	col gas; flam	-133.8	-87.75	1.390 g/L		i H_2O; sl EtOH, eth
1624	Diphosphine	P_2H_4	13445-50-6	65.980	col liq	-99	63.5 dec			reac H_2O
1625	Diphosphorus tetrachloride	P_2Cl_4	13497-91-1	203.759	col oily liq	-28	≈180 dec			
1626	Diphosphorus tetrafluoride	P_2F_4	13824-74-3	137.942	col gas	-86.5	-6.2	5.638 g/L		
1627	Diphosphorus tetraiodide	P_2I_4	13455-00-0	569.566	red tricl needles	125.5	dec	3.89		
1628	Phosphonium chloride	PH_4Cl	24567-53-1	70.459	gas		-27 sp	2.880 g/L		reac H_2O
1629	Phosphonium iodide	PH_4I	12125-09-6	161.910	col tetr cry	18.5	62.5	2.86		reac H_2O, EtOH
1630	Phosphoric acid (orthophosphoric acid)	H_3PO_4	7664-38-2	97.995	col visc liq	42.4	407		548^{20}	s EtOH
1631	Phosphonic acid (phosphorous acid)	H_3PO_3	13598-36-2	81.996	wh hyg cry	74.4	200	1.65	309^{0}	vs EtOH
1632	Phosphinic acid (hypophosphorous acid)	HPH_2O_2	6303-21-5	65.997	hyg cry or col oily liq	26.5	130	1.49		vs H_2O, EtOH, eth
1633	Metaphosphoric acid	HPO_3	37267-86-0	79.980	gl solid; hyg					sl H_2O; s EtOH
1634	Hypophosphoric acid	$H_4P_2O_6$	7803-60-3	161.976	col orth cry	73 dec				vs H_2O
1635	Diphosphoric acid (pyrophosphoric acid)	$H_4P_2O_7$	2466-09-3	177.975	wh cry	71.5			709^{23}	
1636	Difluorophosphoric acid	HPO_2F_2	13779-41-4	101.978	col liq	≈-94	110 dec	1.583		reac H_2O
1637	Hexafluorophosphoric acid	HPF_6	16940-81-1	145.972	col oily liq	25 dec				reac H_2O
1638	Fluorophosphonic acid	H_2PFO_3	13537-32-1	99.986	col visc liq	<-70		1.82		vs H_2O
1639	Phosphorus nitride	P_3N_5	12136-91-3	162.955	yel-brn solid	800 dec				i H_2O; s os
1640	Phosphorus sesquisulfide	P_4S_3	1314-85-8	220.093	yel-grn orth cry	172.5	407	2.03		i H_2O; s bz; vs CS_2
1641	Phosphorus heptasulfide	P_4S_7	12037-82-0	348.357	pale yel monocl cry	312	523	2.19		sl CS_2
1642	Phosphonitrilic chloride trimer	$(PNCl_2)_3$	940-71-6	347.657	wh hyg cry	128.8		1.98		reac H_2O
1643	Phosphorus(III) bromide	PBr_3	7789-60-8	270.686	col liq	-41.5	173.2	2.8		reac H_2O, EtOH; s ace, CS_2
1644	Phosphorus(III) dibromide fluoride	PBr_2F	15597-39-4	209.780	col liq	-115	78.5			
1645	Phosphorus(III) bromide difluoride	$PBrF_2$	15597-40-7	148.875	col gas	-133.8	-16.1	6.085 g/L		
1646	Phosphorus(III) chloride	PCl_3	7719-12-2	137.332	col liq	-93.6	76.1	1.574		reac H_2O, EtOH; s bz, chl, eth
1647	Phosphorus(III) dichloride fluoride	PCl_2F	15597-63-4	120.877	col gas	-144	13.85	4.941 g/L		
1648	Phosphorus(III) chloride difluoride	$PClF_2$	14335-40-1	104.424	col gas	-164.8	-47.3	4.268 g/L		
1649	Phosphorus(III) fluoride	PF_3	7783-55-3	87.969	col gas	-151.5	-101.8	3.596 g/L		reac H_2O
1650	Phosphorus(III) iodide	PI_3	13455-01-1	411.687	red-oran hex cry; hyg	61.2	227 dec	4.18		reac H_2O; s EtOH
1651	Phosphorus(III) oxide	P_2O_3	1314-24-5	109.946	col monocl cry or liq	23.8	173	2.13		reac H_2O
1652	Tetraphosphorus(III) hexoxide	P_4O_6	12440-00-5	219.891	soft wh cry	23.8	175.4			
1653	Phosphorus(III) selenide	P_2Se_3	1314-86-9	298.83	oran-red cry	245	≈380	1.31		reac H_2O; s bz, ctc, CS_2, ace
1654	Phosphorus(III) sulfide	P_2S_3	12165-69-4	158.146	yel solid	290	490			reac H_2O; s EtOH, eth, CS_2
1655	Phosphorus(V) bromide	PBr_5	7789-69-7	430.494	yel orth cry, Donnay	≈100 dec		3.61		reac H_2O, EtOH; s CS_2, ctc
1656	Phosphorus(V) tetrabromide fluoride	PBr_4F		369.588	pale yel cry	87 dec				
1657	Phosphorus(V) dibromide trifluoride	PBr_2F_3	13445-58-4	247.777	yel-red liq	-20	15 dec			

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1658	Phosphorus(V) chloride	PCl_5	10026-13-8	208.238	wh-yel tetr cry; hyg	167 tp	160 sp	2.1		reac H_2O; s CS_2, ctc
1659	Phosphorus(V) tetrachloride fluoride	PCl_4F	13498-11-8	191.783	col liq	-59	30 dec			
1660	Phosphorus(V) trichloride difluoride	PCl_3F_2	158704-27-9	175.329	col liq	-63				
1661	Phosphorus(V) dichloride trifluoride	PCl_2F_3	13454-99-4	158.874	col gas	-125	7.1	6.494 g/L		
1662	Phosphorus(V) chloride tetrafluoride	$PClF_4$		142.421	col gas	-132	-43.4	5.821 g/L		
1663	Phosphorus(V) fluoride	PF_5	7647-19-0	125.966	col gas	-93.8	-84.6	5.149 g/L		reac H_2O
1664	Phosphorus(V) oxide	P_2O_5	1314-56-3	141.945	wh orth cry; hyg	562	605	2.30		reac H_2O, EtOH
1665	Phosphorus(V) selenide	P_2Se_5	1314-82-5	456.75	blk-purp amorp solid					reac hot H_2O, ctc; i CS_2
1666	Phosphorus(V) sulfide	P_2S_5	1314-80-3	222.278	grn-yel hyg cry	285	515	2.03		reac H_2O; s CS_2
1667	Phosphonic difluoride	POF_2H	14939-34-5	85.978	volatile liq	>-120	≈60 (gas unstab)			
1668	Phosphoric tribromide (phosphoryl bromide)	$POBr_3$	7789-59-5	286.685	faint oran plates	55	191.7	2.822		reac H_2O; s bz, eth, chl
1669	Phosphoric dibromide chloride	$POBr_2Cl$	13550-31-7	242.234	yel solid	31	165			
1670	Phosphoric dibromide fluoride	$POBr_2F$	14014-19-8	225.779	col liq	-117.2	110.1			
1671	Phosphoric bromide dichloride	$POBrCl_2$	13455-03-3	197.782	col liq	11	136.5	2.104[14]		
1672	Phosphoric bromide difluoride	$POBrF_2$	14014-18-7	164.874	col liq	-84.8	31.6			
1673	Phosphoric bromide chloride fluoride	POBrClF	14518-81-1	181.328	col liq		79			
1674	Phosphoric trichloride (phosphoryl chloride)	$POCl_3$	10025-87-3	153.331	col liq	1.18	105.5	1.645		reac H_2O, EtOH
1675	Phosphoric dichloride fluoride	$POCl_2F$	13769-76-1	136.876	col liq	-80.1	52.9			
1676	Phosphoric chloride difluoride	$POClF_2$	13769-75-0	120.423	col gas	-96.4	3.1	4.922 g/L		
1677	Phosphoric trifluoride (phosphoryl fluoride)	POF_3	13478-20-1	103.968	col gas	-39.1 tp	-39.7 sp	4.250 g/L		reac H_2O
1678	Phosphoric triodide (phosphoryl iodide)	POI_3	13455-04-4	427.686	viol cry	53				
1679	Phosphorothioc tribromide	$PSBr_3$	3931-89-3	302.752	yel cry	37.8	212 dec	2.85		
1680	Phosphorothioc dibromide fluoride	$PSBr_2F$	13706-10-0	241.846	yel liq	-75.2	125.3			
1681	Phosphorothioc bromide difluoride	$PSBrF_2$	13706-09-7	180.941	yel liq	-136.9	35.5			
1682	Phosphorothioc trichloride	$PSCl_3$	3982-91-0	169.398	fuming liq	-36.2	125	1.635		reac H_2O; s bz, ctc, chl, CS_2
1683	Phosphorothioc dichloride fluoride	$PSCl_2F$	155698-29-6	152.943	col liq	-96.0	64.7			
1684	Phosphorothioc chloride difluoride	$PSClF_2$	2524-02-9	136.490	col gas	-155.2	6.3	5.579 g/L		
1685	Phosphorothioc trifluoride	PSF_3	2404-52-6	120.035	col gas	-148.8	-52.25	4.906 g/L		
1686	Phosphorothioc triiodide	PSI_3	63972-04-3	443.753	yel cry	48	dec			
1687	Platinum	Pt	7440-06-4	195.08	silv-gray metal; cub	1768.2	3825	21.5		i acid; s aqua regia
1688	Platinum(II) bromide	$PtBr_2$	13455-12-4	354.89	red-brn powder	250 dec		6.65		i H_2O
1689	Platinum(II) chloride	$PtCl_2$	10025-65-7	265.98	grn hex cry	581 dec		6.0		i H_2O, EtOH, eth; s HCl
1690	Platinum(II) iodide	PtI_2	7790-39-8	448.89	blk powder	325 dec		6.4		i H_2O
1691	Platinum(II) oxide	PtO	12035-82-4	211.08	blk tetr cry	325 dec		14.1		i H_2O, EtOH; s aqua regia
1692	Platinum(II) sulfide	PtS	12038-20-9	227.14	tetr cry			10.25		
1693	Platinum(III) bromide	$PtBr_3$	25985-07-3	434.79	grn-blk cry	200 dec				
1694	Platinum(III) chloride	$PtCl_3$	25909-39-1	301.44	grn-blk cry	435 dec		5.26		
1695	Platinum(IV) bromide	$PtBr_4$	68938-92-1	514.69	brn-blk cry	180 dec			0.41[20]	sl EtOH, eth
1696	Platinum(IV) chloride	$PtCl_4$	37773-49-2	336.89	red-brn cub cry	327 dec		4.30	142[25]	
1697	Platinum(IV) chloride pentahydrate	$PtCl_4 \cdot 5H_2O$	13454-96-1	426.97	red cry			2.43		s H_2O, EtOH
1698	Platinum(IV) fluoride	PtF_4	13455-15-7	271.07	red cry	600				
1699	Platinum(IV) iodide	PtI_4	7790-46-7	702.70	brn-blk powder	130 dec				s H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1700	Platinum(IV) oxide	PtO_2	1314-15-4	227.08	blk hex cry	450		11.8		i H_2O; s conc acid, dil alk
1701	Platinum(IV) sulfide	PtS_2	12038-21-0	259.21	hex cry			7.85		
1702	Platinum(VI) fluoride	PtF_6	13693-05-5	309.07	red cub cry	61.3	69.1	≈4.0		
1703	cis-Diamminedichloroplatinum	$Pt(NH_3)_2Cl_2$	15663-27-1	300.04	yel solid	270 dec			0.253^{25}	
1704	trans-Diamminedichloroplatinum	$Pt(NH_3)_2Cl_2$	14913-33-8	300.04	pale yel solid	270 dec			0.036^{25}	s DMF, DMSO
1705	Hexachloroplatinic acid hexahydrate	$H_2PtCl_6 \cdot 6H_2O$	16941-12-1	517.90	brn-yel hyg cry	60		2.43	140^{18}	vs EtOH
1706	Platinum silicide	PtSi	12137-83-6	223.16	orth cry	1229		12.4		
1707	Plutonium	Pu	7440-07-5	244	silv-wh metal; monocl	640	3228	19.7		
1708	Plutonium nitride	PuN	12033-54-4	258	gray cub cry	2550		14.4		
1709	Plutonium(II) oxide	PuO	12035-83-5	260	cub cry			14.0		
1710	Plutonium(III) bromide	$PuBr_3$	15752-46-2	484	grn orth cry	681		6.75		s H_2O
1711	Plutonium(III) chloride	$PuCl_3$	13569-62-5	350	grn hex cry	760		5.71		s H_2O
1712	Plutonium(III) fluoride	PuF_3	13842-83-6	301	purp hex cry	1396		9.33		i H_2O; sl acid
1713	Plutonium(III) iodide	PuI_3	13813-46-2	625	grn orth cry; hyg	777		6.92		s H_2O
1714	Plutonium(III) oxide	Pu_2O_3	12036-34-9	536	blk cub cry			10.5		
1715	Plutonium(IV) fluoride	PuF_4	13709-56-3	320	red-brn monocl cry	1027		7.1		
1716	Plutonium(IV) oxide	PuO_2	12059-95-9	276	yel-brn cub cry	2400		11.5		
1717	Plutonium(VI) fluoride	PuF_6	13693-06-6	358	red-brn orth cry	52		5.08		
1718	Polonium	Po	7440-08-6	209	silv metal; cub	254	962	9.20		
1719	Polonium(IV) chloride	$PoCl_4$	10026-02-5	351	yel hyg cry	≈300	390			s H_2O, EtOH, ace
1720	Polonium(IV) oxide	PoO_2	7446-06-2	241	yel cub cry	500 dec		8.9		
1721	Potassium	K	7440-09-7	39.098	soft silv-wh metal; cub	63.5	759	0.89		reac H_2O
1722	Potassium acetate	$KC_2H_3O_2$	127-08-2	98.142	wh hyg cry	309		1.57	269^{25}	s EtOH; i eth
1723	Potassium aluminate trihydrate	$K_2Al_2O_4 \cdot 3H_2O$	12003-63-3*	250.204	wh orth cry			2.13		vs H_2O; i EtOH
1724	Potassium aluminum silicate	$KAlSi_3O_8$	1327-44-2	278.332	col monocl cry			2.56		i H_2O
1725	Potassium aluminum sulfate	$KAl(SO_4)_2$	10043-67-1	258.207	wh hyg powder				5.9^{20}	
1726	Potassium aluminum sulfate dodecahydrate	$KAl(SO_4)_2 \cdot 12H_2O$	7784-24-9	474.391	col cry	≈100 dec		1.72	5.9^{20}	
1727	Potassium amide	KNH_2	17242-52-3	55.121	wh/yel-grn hyg cry	335				reac H_2O, EtOH
1728	Potassium arsenate	K_3AsO_4	13464-36-3	256.215	col cry			2.8	125^{25}	
1729	Potassium arsenite	$KAsO_2$	13464-35-2	146.019	wh hyg pow					s H_2O; sl EtOH
1730	Potassium azide	KN_3	20762-60-1	81.118	tetr cry; exp			2.04	49.7^{17}	
1731	Potassium borohydride	KBH_4	13762-51-1	53.941	wh cub cry	≈500 dec		1.11		s H_2O
1732	Potassium bromate	$KBrO_3$	7758-01-2	167.000	wh hex cry	434 dec		3.27	8.17^{25}	i EtOH
1733	Potassium bromide	KBr	7758-02-3	119.002	col cub cry; hyg	734	1435	2.74	67.8^{25}	sl EtOH
1734	Potassium carbonate	K_2CO_3	584-08-7	138.206	wh monocl cry; hyg	898	dec	2.29	111^{25}	i EtOH
1735	Potassium carbonate sesquihydrate	$K_2CO_3 \cdot 1.5H_2O$	6381-79-9	165.229	granular cry				111^{20}	
1736	Potassium chlorate	$KClO_3$	3811-04-9	122.549	wh monocl cry	368	dec	2.32	8.61^{25}	
1737	Potassium chloride	KCl	7447-40-7	74.551	wh cub cry	771		1.988	35.5^{25}	i eth, ace
1738	Potassium chromate	K_2CrO_4	7789-00-6	194.191	yel orth cry	975		2.73	65.0^{25}	
1739	Potassium cyanate	KCNO	590-28-3	81.115	wh tetr cry	≈700 dec		2.05	75^{25}	sl EtOH
1740	Potassium cyanide	KCN	151-50-8	65.116	wh cub cry; hyg	634		1.55	69.9^{20}	sl EtOH
1741	Potassium dichromate	$K_2Cr_2O_7$	7778-50-9	294.185	oran-red tricl cry	398	≈500 dec	2.68	15.1^{25}	
1742	Potassium dihydrogen arsenate	KH_2AsO_4	7784-41-0	180.034	col cry	288		2.87	19^{6}	i EtOH
1743	Potassium dihydrogen phosphate	KH_2PO_4	7778-77-0	136.085	wh tetr cry	253		2.34	25.0^{25}	sl EtOH
1744	Potassium ferricyanide	$K_3Fe(CN)_6$	13746-66-2	329.244	red cry	dec		1.89	48.8^{25}	
1745	Potassium ferrocyanide trihydrate	$K_4Fe(CN)_6 \cdot 3H_2O$	14459-95-1	422.388	yel monocl cry	60 dec		1.85	36.0^{25}	i EtOH, eth
1746	Potassium fluoride	KF	7789-23-3	58.096	wh cub cry	858	1502	2.48	102^{25}	
1747	Potassium fluoride dihydrate	$KF \cdot 2H_2O$	13455-21-5	94.127	monocl cry	41 dec		2.5	102^{25}	
1748	Potassium fluoroborate	KBF_4	14075-53-7	125.903	col orth cry	530		2.505	0.55^{25}	sl EtOH
1749	Potassium fluorotantalate	K_2TaF_7	16924-00-8	392.134	col cry	730		5.24	0.5^{0}	
1750	Potassium formate	$KCHO_2$	590-29-4	84.116	col hyg cry	167		1.91	331^{18}	
1751	Potassium hexachloroosmate(IV)	K_2OsCl_6	16871-60-6	481.14	red cub cry					vs H_2O; sl EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1752	Potassium hexachloroplatinate	K_2PtCl_6	16921-30-5	485.99	yel-oran cub cry	250 dec		3.50	0.77^{20}	i EtOH
1753	Potassium hexacyanocobaltate	$K_3Co(CN)_6$	13963-58-1	332.332	yel monocl cry	dec		1.91		vs H_2O; i EtOH
1754	Potassium hexafluoromanganate(IV)	K_2MnF_6	16962-31-5	247.125	yel hex cry					reac H_2O
1755	Potassium hexafluorosilicate	K_2SiF_6	16871-90-2	220.273	wh cry	dec		2.27	0.084^{20}	i EtOH
1756	Potassium hexafluorozirconate(IV)	K_2ZrF_6	16923-95-8	283.411	col mono cry			3.48	0.78^{2}	
1757	Potassium hydride	KH	7693-26-7	40.106	cub cry			1.43		reac H_2O
1758	Potassium hydrogen arsenate	K_2HAsO_4	21093-83-4	218.125	col mono prisms	300 dec			18.7^{6}	i EtOH
1759	Potassium hydrogen arsenite	$KAsO_2 \cdot HAsO_2$	10124-50-2	253.947	wh hyg powder					s H_2O
1760	Potassium hydrogen carbonate	$KHCO_3$	298-14-6	100.115	col monocl cry	≈100 dec		2.17	36.2^{25}	i EtOH
1761	Potassium hydrogen fluoride	KHF_2	7789-29-9	78.103	col tetr cry	238.9		2.37	39.2^{20}	i EtOH
1762	Potassium hydrogen phosphate	K_2HPO_4	7758-11-4	174.176	wh hyg cry	dec			168^{25}	s EtOH
1763	Potassium hydrogen phosphite	K_2HPO_3	13492-26-7	158.177	wh hyg powder	dec			170^{20}	i EtOH
1764	Potassium hydrogen selenite	$KHSeO_3$	7782-70-9	167.06	hyg orth cry	>100 dec				s H_2O; sl EtOH
1765	Potassium hydrogen sulfate	$KHSO_4$	7646-93-7	136.170	wh monocl cry; hyg	≈200		2.32	50.6^{25}	
1766	Potassium hydrogen sulfide	KHS	1310-61-8	72.172	wh hex cry; hyg	≈450		1.69		s H_2O, EtOH
1767	Potassium hydrogen sulfide hemihydrate	$KHS \cdot 0.5H_2O$	1310-61-8*	81.179	wh-yel hyg cry	≈175		1.7		vs H_2O, EtOH
1768	Potassium hydrogen sulfite	$KHSO_3$	7773-03-7	120.170	wh cry powder	190 dec			49^{20}	i EtOH
1769	Potassium hydrogen tartrate	$KHC_4H_4O_6$	868-14-4	188.177	wh cry			1.98	0.57^{20}	s acid, alk; i EtOH
1770	Potassium hydroxide	KOH	1310-58-3	56.105	wh rhomb cry; hyg	406	1327	2.044	121^{25}	s EtOH; s MeOH
1771	Potassium hypophosphite	KH_2PO_2	7782-87-8	104.087	wh hyg cry	dec				vs H_2O; s EtOH
1772	Potassium iodate	KIO_3	7758-05-6	214.001	wh monocl cry	560 dec		3.89	9.22^{25}	
1773	Potassium iodide	KI	7681-11-0	166.003	col cub cry	681	1323	3.12	148^{25}	sl EtOH
1774	Potassium iron(III) oxalate trihydrate	$K_3Fe(C_2O_4)3 \cdot 3H_2O$		491.243	grn mono cry	100	230 dec	2.133	4.7^{0}	i EtOH
1775	Potassium manganate	K_2MnO_4	10294-64-1	197.133	grn cry	190 dec				s H_2O; reac HCl
1776	Potassium metaarsenate	$KAsO_3$	19197-73-0	162.018	wh solid	660				
1777	Potassium metabisulfite	$K_2S_2O_5$	16731-55-8	222.326	wh powder	≈150 dec		2.3	49.5^{25}	reac acid; i EtOH
1778	Potassium metaborate	KBO_2	13709-94-9	81.908	wh hex cry			≈2.3		
1779	Potassium molybdate	K_2MoO_4	13446-49-6	238.14	wh hyg cry	919		2.3	183^{25}	i EtOH
1780	Potassium niobate	$KNbO_3$	12030-85-2	180.002	wh rhomb cry	≈1100		4.64		i H_2O
1781	Potassium nitrate	KNO_3	7757-79-1	101.103	col rhomb cry or powder	337	400 dec	2.11	38.3^{25}	i EtOH
1782	Potassium nitrite	KNO_2	7758-09-0	85.104	wh hyg cry	441	537 exp	1.915	312^{25}	sl EtOH
1783	Potassium oxalate	$K_2C_2O_4$	583-52-8	166.216	wh pwd					sl H_2O
1784	Potassium oxalate monohydrate	$K_2C_2O_4 \cdot H_2O$	6487-48-5	184.231	col cry	160 dec		2.13	36.4^{20}	
1785	Potassium oxide	K_2O	12136-45-7	94.196	gray cub cry	350 dec		2.35		s H_2O, EtOH, eth
1786	Potassium perbromate	$KBrO_4$	22207-96-1	183.000	wh cry	275 dec			4.21^{25}	
1787	Potassium perchlorate	$KClO_4$	7778-74-7	138.549	col orth cry; hyg	525		2.52	2.08^{25}	
1788	Potassium periodate	KIO_4	7790-21-8	230.001	col tetr cry	582	exp	3.618	0.51^{25}	
1789	Potassium permanganate	$KMnO_4$	7722-64-7	158.034	purp orth cry	dec		2.7	7.60^{25}	reac EtOH
1790	Potassium peroxide	K_2O_2	17014-71-0	110.196	yel amorp solid	490				reac H_2O
1791	Potassium persulfate	$K_2S_2O_8$	7727-21-1	270.324	col cry	≈100 dec		2.48	4.7^{20}	
1792	Potassium phosphate	K_3PO_4	7778-53-2	212.266	wh orth cry; hyg	1340		2.564	106^{25}	i EtOH
1793	Potassium pyrophosphate trihydrate	$K_4P_2O_7 \cdot 3H_2O$	7320-34-5*	384.383	col hyg cry	1090		2.33		vs H_2O; i EtOH
1794	Potassium pyrosulfate	$K_2S_2O_7$	7790-62-7	254.325	col needles	≈325		2.28		s H_2O
1795	Potassium selenate	K_2SeO_4	7790-59-2	221.16	wh powder			3.07	114^{25}	
1796	Potassium selenide	K_2Se	1312-74-9	157.16	red cub cry; hyg	800		2.29		s H_2O
1797	Potassium selenite	K_2SeO_3	10431-47-7	205.16	wh hyg cry	875 dec			217^{25}	sl EtOH
1798	Potassium silver cyanide	$KAg(CN)_2$	506-61-6	199.000	wh cry					s H_2O
1799	Potassium stannate trihydrate	$K_2SnO_3 \cdot 3H_2O$	12142-33-5*	298.951	col cry			3.20		vs H_2O; i EtOH
1800	Potassium sulfate	K_2SO_4	7778-80-5	174.261	wh orth cry	1069		2.66	12.0^{25}	i EtOH
1801	Potassium sulfide	K_2S	1312-73-8	110.263	red-yel cub cry; hyg	948		1.74		s H_2O, EtOH; i eth
1802	Potassium sulfide pentahydrate	$K_2S \cdot 5H_2O$	37248-34-3	200.339	col rhomb cry	60				vs H_2O, EtOH; i eth
1803	Potassium sulfite	K_2SO_3	10117-38-1	158.261	col hex cry				106^{25}	sl EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1804	Potassium sulfite dihydrate	$K_2SO_3 \cdot 2H_2O$	7790-56-9	194.292	wh monocl cry	dec			107^{20}	sl EtOH; dec dil acid
1805	Potassium superoxide	KO_2	12030-88-5	71.097	yel tetr cry; hyg	380		2.16		reac H_2O
1806	Potassium tellurate(VI) trihydrate	$K_2TeO_4 \cdot 3H_2O$	15571-91-2*	323.84	wh cry powder					s H_2O
1807	Potassium tellurite	K_2TeO_3	7790-58-1	253.80	wh hyg cry	≈460 dec				vs H_2O
1808	Potassium tetraborate pentahydrate	$K_2B_4O_7 \cdot 5H_2O$	1332-77-0	323.513	wh cry powder				16.5^{30}	sl EtOH
1809	Potassium tetrachloroaurate dihydrate	$KAuCl_4 \cdot 2H_2O$	13682-61-6	413.907	yel monocl cry					s H_2O, EtOH, eth
1810	Potassium tetrachloroplatinate	K_2PtCl_4	10025-99-7	415.09	pink-red tetr cry	500 dec		3.38		s H_2O; i EtOH
1811	Potassium tetracyanoplatinate(II) trihydrate	$K_2Pt(CN)_4 \cdot 3H_2O$	562-76-5*	431.39	col rhomb prisms					s H_2O
1812	Potassium tetraiodomercurate(II)	K_2HgI_4	7783-33-7	786.40	yel hyg cry			4.29		vs H_2O; s EtOH, eth, ace
1813	Potassium thiocyanate	KSCN	333-20-0	97.182	col tetr cry; hyg	173	500 dec	1.88	238^{25}	s EtOH
1814	Potassium thiosulfate	$K_2S_2O_3$	10294-66-3	190.327	col hyg cry				165^{25}	i EtOH
1815	Potassium titanate	K_2TiO_3	12030-97-6	174.062	wh orth cry	1515		3.1		reac H_2O
1816	Potassium triiodide monohydrate	$KI_3 \cdot H_2O$	7790-42-3	437.827	brn monocl cry; hyg	225 dec		3.5		s H_2O; reac EtOH, eth
1817	Potassium thiocarbonate	K_2CS_3	26750-66-3	186.406	yel-red hyg cry					vs H_2O
1818	Potassium tungstate	K_2WO_4	7790-60-5	326.04	hyg cry	921		3.12		vs H_2O; i EtOH
1819	Potassium uranate	$K_2U_2O_7$	7790-63-8	666.251	oran cub cry			6.12		i H_2O; s acid
1820	Praseodymium	Pr	7440-10-0	140.908	silv metal; hex	931	3520	6.77		
1821	Praseodymium boride	PrB_6	12008-27-4	205.774	blk cub cry	2610		4.84		
1822	Praseodymium bromide	$PrBr_3$	13536-53-3	380.620	grn hex cry; hyg	693		5.28		s H_2O
1823	Praseodymium chloride	$PrCl_3$	10361-79-2	247.266	grn hex needles; hyg	786		4.0	96.1^{25}	s EtOH
1824	Praseodymium chloride heptahydrate	$PrCl_3 \cdot 7H_2O$	10025-90-8	373.373	grn cry	110 dec			96.1^{25}	s EtOH
1825	Praseodymium fluoride	PrF_3	13709-46-1	197.903	grn hex cry	1395		6.3		
1826	Praseodymium iodide	PrI_3	13813-23-5	521.621	orth hyg cry	737		≈5.8		s H_2O
1827	Praseodymium nitrate	$Pr(NO_3)_3$	10361-80-5	326.923	pale grn hyg cry				165^{25}	s EtOH
1828	Praseodymium nitrate hexahydrate	$Pr(NO_3)_3 \cdot 6H_2O$	15878-77-0	435.014	grn needles				165^{25}	s EtOH, ace
1829	Praseodymium nitride	PrN	25764-09-4	154.915	cub cry			7.46		
1830	Praseodymium oxide	Pr_2O_3	12036-32-7	329.813	wh hex cry	2183	3760	6.9		
1831	Praseodymium silicide	$PrSi_2$	12066-83-0	197.079	tetr cry	1712		5.46		
1832	Praseodymium sulfide	Pr_2S_3	12038-13-0	378.013	cub cry	1765		5.1		
1833	Praseodymium telluride	Pr_2Te_3	12038-12-9	664.62	cub cry	1500		≈7.0		
1834	Promethium	Pm	7440-12-2	145	silv metal; hex	1042	3000	7.26		
1835	Protactinium	Pa	7440-13-3	231.036	shiny metal; tetr or cub	1572		15.4		
1836	Protactinium(V) chloride	$PaCl_5$	13760-41-3	408.300	yel monocl cry	306		3.74		
1837	Radium	Ra	7440-14-4	226	wh metal; cub	700		5		
1838	Radium bromide	$RaBr_2$	10031-23-9	386	wh orth cry	728		5.79	70.6^{20}	s EtOH
1839	Radium chloride	$RaCl_2$	10025-66-8	297	wh orth cry	1000		4.9	24.5^{20}	s EtOH
1840	Radium fluoride	RaF_2	20610-49-5	264	wh cub cry			6.7		
1841	Radium nitrate	$Ra(NO_3)_2$	10213-12-4	350	cry				13.9	
1842	Radium sulfate	$RaSO_4$	7446-16-4	322	wh cry					i H_2O, acid
1843	Radon	Rn	10043-92-2	222	col gas	-71	-61.7	9.074 g/L		sl H_2O
1844	Rhenium	Re	7440-15-5	186.207	silv-gray metal	3186	5596	20.8		i HCl
1845	Perrhenic acid	$HReO_4$	13768-11-1	251.213	exists only in soln					vs H_2O, os
1846	Rhenium carbonyl	$Re_2(CO)_{10}$	14285-68-8	652.515	yel-wh cry	170 dec		2.87		s os
1847	Rhenium(III) bromide	$ReBr_3$	13569-49-8	425.919	red-brn monocl cry		500 subl	6.10		s ace, MeOH, EtOH
1848	Rhenium(III) chloride	$ReCl_3$	13569-63-6	292.565	red-blk hyg cry	500 dec		4.81		s H_2O
1849	Rhenium(III) iodide	ReI_3	15622-42-1	566.920	blk solid	dec				
1850	Rhenium(IV) chloride	$ReCl_4$	13569-71-6	328.018	purp-blk cry; hyg	300 dec		4.9		
1851	Rhenium(IV) fluoride	ReF_4	15192-42-4	262.201	blue tetr cry		>300 subl	7.49		
1852	Rhenium(IV) oxide	ReO_2	12036-09-8	218.206	gray orth cry	900 dec		11.4		
1853	Rhenium(IV) sulfide	ReS_2	12038-63-0	250.339	tricl cry			7.6		
1854	Rhenium(IV) telluride	$ReTe_2$	12067-00-4	441.41	orth cry			8.50		
1855	Rhenium(V) bromide	$ReBr_5$	30937-53-2	585.727	brn solid	110 dec				
1856	Rhenium(V) chloride	$ReCl_5$	39368-69-9	363.471	brn-blk solid	220		4.9		reac H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1857	Rhenium(V) fluoride	ReF_5	30937-52-1	281.199	yel-grn solid	48	221.3			
1858	Rhenium(V) oxide	Re_2O_5	12165-05-8	452.411	blue-blk tetr cry			≈7		
1859	Rhenium(VI) chloride	$ReCl_6$	31234-26-1	398.923	red-grn solid	29				
1860	Rhenium(VI) dioxydifluoride	ReO_2F_2	81155-18-2	256.203	col cry	156				
1861	Rhenium(VI) fluoride	ReF_6	10049-17-9	300.197	yel liq or cub cry	18.5	33.8	4.06(cry)		s HNO_3
1862	Rhenium(VI) oxide	ReO_3	1314-28-9	234.205	redcub cry	400 dec		6.9		i H_2O, acid, alk
1863	Rhenium(VI) oxytetrachloride	$ReOCl_4$	13814-76-1	344.017	brn cry	29.3	223			reac H_2O
1864	Rhenium(VI) oxytetrafluoride	$ReOF_4$	17026-29-8	278.200	blue solid	108	171.7			
1865	Rhenium(VII) fluoride	ReF_7	17029-21-9	319.196	yel cub cry	48.3	73.7	4.32		
1866	Rhenium(VII) oxide	Re_2O_7	1314-68-7	484.410	yel hyg cry	297	360	6.10		s H_2O, EtOH, eth, diox, py
1867	Rhenium(VII) trioxychloride	ReO_3Cl	7791-09-5	269.658	col liq	4.5	128	3.87		reac H_2O
1868	Rhenium(VII) trioxyfluoride	ReO_3F	42246-24-2	253.203	yel solid	147	164			
1869	Rhenium(VII) dioxytrifluoride	ReO_2F_3	57246-89-6	275.201	yel solid	90	185.4			reac H_2O
1870	Rhenium(VII) oxypentafluoride	$ReOF_5$	23377-53-9	297.198	cream solid	43.8	73.0			
1871	Rhenium(VII) sulfide	Re_2S_7	12038-67-4	596.876	brn-blk tetr cry			4.87		i H_2O
1872	Rhodium	Rh	7440-16-6	102.906	silv-wh metal; cub	1963	3695	12.4		i acid, sl aqua regia
1873	Rhodium carbonyl chloride	$[Rh(CO)_2Cl]_2$	14523-22-9	388.757	red-oran cry	124				s os
1874	Rhodium dodecacarbonyl	$Rh_4(CO)_{12}$	19584-30-6	747.743	red hyg cry			2.52		reac H_2O
1875	Rhodium(III) chloride	$RhCl_3$	10049-07-7	209.264	red monocl cry		717	5.38		i H_2O; s alk
1876	Rhodium(III) fluoride	RhF_3	60804-25-3	159.901	red hex cry			5.4		
1877	Rhodium(III) iodide	RhI_3	15492-38-3	483.619	blk monocl cry; hyg			6.4		
1878	Rhodium(III) oxide	Rh_2O_3	12036-35-0	253.809	gray hex cry	1100 dec		8.2		
1879	Rhodium(III) sulfate	$Rh_2(SO_4)_3$	10489-46-0	494.002	red-yel solid	>500 dec				
1880	Rhodium(IV) oxide	RhO_2	12137-27-8	134.905	blk tetr cry			7.2		
1881	Rhodium(VI) fluoride	RhF_6	13693-07-7	216.896	blk cub cry	≈70		3.1		
1882	Rubidium	Rb	7440-17-7	85.468	soft silv metal; cub	39.30	688	1.53		reac H_2O
1883	Rubidium acetate	$RbC_2H_3O_2$	563-67-7	144.512	wh hyg cry	246				vs H_2O
1884	Rubidium aluminum sulfate	$RbAl(SO_4)_2$	13530-57-9	304.577	hex cry			≈3.1	1.60^{20}	i EtOH
1885	Rubidium aluminum sulfate dodecahydrate	$RbAl(SO_4)_2 \cdot 12H_2O$	7784-29-4	520.761	col cub cry	≈100 dec		≈1.9		s H_2O; i EtOH
1886	Rubidium azide	RbN_3	22756-36-1	127.488	tetr cry; exp	317		2.79	107^{16}	
1887	Rubidium bromate	$RbBrO_3$	13446-70-3	213.370	cub cry	430		3.68	2.95^{25}	
1888	Rubidium bromide	RbBr	7789-39-1	165.372	wh cub cry; hyg	682	1340	3.35	116^{25}	
1889	Rubidium carbonate	Rb_2CO_3	584-09-8	230.945	col monocl cry; hyg	837			223^{20}	
1890	Rubidium chlorate	$RbClO_3$	13446-71-4	168.919	col cry			3.19	6.63^{25}	
1891	Rubidium chloride	RbCl	7791-11-9	120.921	wh cub cry; hyg	715	1390	2.76	93.9^{25}	sl EtOH
1892	Rubidium chromate	Rb_2CrO_4	13446-72-5	286.930	yel rhom cry			3.518	76.2^{25}	
1893	Rubidium cyanide	RbCN	19073-56-4	111.486	wh cub cry			2.3		s H_2O; i EtOH, eth
1894	Rubidium fluoride	RbF	13446-74-7	104.466	wh cub cry; hyg	833	1410	3.2	300^{20}	i EtOH
1895	Rubidium hydrogen fluoride	$RbHF_2$	12280-64-7	124.473	tetr cry	188		3.3		
1896	Rubidium formate	$RbCHO_2$	3495-35-0	130.486	wh hyg cry	dec				
1897	Rubidium hydride	RbH	13446-75-8	86.476	wh cub cry; flam	≈170 dec		2.60		reac H_2O
1898	Rubidium hydrogen carbonate	$RbHCO_3$	19088-74-5	146.485	wh rhomb cry	175 dec			116^{20}	
1899	Rubidium hydrogen sulfate	$RbHSO_4$	15587-72-1	182.540	col monocl cry	208		2.9		s H_2O
1900	Rubidium hydroxide	RbOH	1310-82-3	102.475	gray-wh orth cry; hyg	382		3.2	173^{30}	s EtOH
1901	Rubidium iodate	$RbIO_3$	13446-76-9	260.370	mono or cub cry	dec		4.33	2.44^{25}	vs HCl
1902	Rubidium iodide	RbI	7790-29-6	212.372	wh cub cry	642	1300	3.55	165^{25}	s EtOH
1903	Rubidium nitrate	$RbNO_3$	13126-12-0	147.473	wh hex cry; hyg	305		3.11	65.0^{25}	
1904	Rubidium oxide	Rb_2O	18088-11-4	186.935	yel-brn cub cry; hyg	400 dec		4.0		reac H_2O
1905	Rubidium perchlorate	$RbClO_4$	13510-42-4	184.919	wh hyg cry	281	600 dec	2.8	1.5^{25}	
1906	Rubidium peroxide	Rb_2O_2	23611-30-5	202.935	wh orth cry			3.8		reac H_2O
1907	Rubidium selenide	Rb_2Se	31052-43-4	249.90	wh cub cry	733		3.22		reac H_2O
1908	Rubidium sulfate	Rb_2SO_4	7488-54-2	267.000	wh orth cry	1050		3.6	50.8^{25}	
1909	Rubidium sulfide	Rb_2S	31083-74-6	203.002	wh cub cry	425		2.91		s H_2O
1910	Rubidium superoxide	RbO_2	12137-25-6	117.467	tetr cry	412		≈3.0		
1911	Ruthenium	Ru	7440-18-8	101.07	silv-wh metal; hex	2333	4150	12.1		i acid, aqua regia
1912	Ruthenium dodecacarbonyl	$Ru_3(CO)_{12}$	15243-33-1	639.33	oran cry	150 dec				

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1913	Ruthenium(III) 2,4-pentanedioate	$Ru(CH_3COCHCOCH_3)_3$	14284-93-6	398.39	red-brn cry	230				
1914	Ruthenium(III) bromide	$RuBr_3$	14014-88-1	340.78	brn hex cry	>400 dec		5.3		
1915	Ruthenium(III) chloride	$RuCl_3$	10049-08-8	207.43	brn hex cry	>500 dec		3.1		i H_2O; s EtOH
1916	Ruthenium(III) fluoride	RuF_3	51621-05-7	158.07	brn rhomb cry	>600 dec		5.36		
1917	Ruthenium(III) iodide	RuI_3	13896-65-6	481.78	blk hex cry			6.0		
1918	Ruthenium(IV) fluoride	RuF_4	71500-16-8	177.06	yel cry					reac H_2O
1919	Ruthenium(IV) oxide	RuO_2	12036-10-1	133.07	gray-blk tetr cry			7.05		i H_2O, acid
1920	Ruthenium(V) fluoride	RuF_5	14521-18-7	196.06	grn monocl cry	86.5	227	3.90		
1921	Ruthenium(VI) fluoride	RuF_6	13693-08-8	215.06	dark brn orth cry	54		3.54		reac H_2O
1922	Ruthenium(VIII) oxide	RuO_4	20427-56-9	165.07	yel monocl prisms	25.4	40	3.29	171^{0}	vs ctc; reac EtOH
1923	Samarium	Sm	7440-19-9	150.36	silv metal; rhomb	1074	1794	7.52		
1924	Samarium boride	SmB_6	12008-29-6	215.23	refrac solid	2580		5.07		
1925	Samarium silicide	$SmSi_2$	12300-22-0	206.53	orth cry			5.14		
1926	Samarium(II) bromide	$SmBr_2$	50801-97-3	310.17	brn cry	669				reac H_2O
1927	Samarium(II) chloride	$SmCl_2$	13874-75-4	221.27	brn cry	855		3.69		reac H_2O
1928	Samarium(II) fluoride	SmF_2	15192-17-3	188.36	purp cry					reac H_2O
1929	Samarium(II) iodide	SmI_2	32248-43-4	404.17	grn cry	520				reac H_2O
1930	Samarium(III) bromide	$SmBr_3$	13759-87-0	390.07	yel cry	640				reac H_2O
1931	Samarium(III) chloride	$SmCl_3$	10361-82-7	256.72	yel cry	682		4.46	93.8^{25}	
1932	Samarium(III) chloride hexahydrate	$SmCl_3 \cdot 6H_2O$	13465-55-9	364.81	yel cry	dec		2.38	93.8^{25}	
1933	Samarium(III) fluoride	SmF_3	13765-24-7	207.36	wh cry	1306				reac H_2O
1934	Samarium(III) iodide	SmI_3	13813-25-7	531.07	oran cry	850				reac H_2O
1935	Samarium(III) nitrate	$Sm(NO_3)_3$	10361-83-8	336.38	yel-wh hyg solid				144^{25}	s EtOH
1936	Samarium(III) nitrate hexahydrate	$Sm(NO_3)_3 \cdot 6H_2O$	13759-83-6	444.47	pale yel cry	78				s H_2O, MeOH, ace
1937	Samarium(III) oxide	Sm_2O_3	12060-58-1	348.72	yel-wh cub cry	2269	3780	7.6		
1938	Samarium(III) sulfate octahydrate	$Sm_2(SO_4)_3 \cdot 8H_2O$	13465-58-2	733.03	yel cry			2.93	2.67^{20}	
1939	Samarium(III) sulfide	Sm_2S_3	12067-22-0	396.92	gray-brn cub cry	1720		5.87		
1940	Samarium(III) telluride	Sm_2Te_3	12040-00-5	683.52	orth cry			7.31		
1941	Scandium	Sc	7440-20-2	44.956	silv metal; hex	1541	2836	2.99		
1942	Scandium boride	ScB_2	12007-34-0	66.578	refrac solid	2250		3.17		
1943	Scandium bromide	$ScBr_3$	13465-59-3	284.668	wh hyg cry	969		9.33		s H_2O
1944	Scandium chloride	$ScCl_3$	10361-84-9	151.314	wh hyg cry	967		2.4		s H_2O; i EtOH
1945	Scandium fluoride	ScF_3	13709-47-2	101.951	wh powder	1515				sl H_2O
1946	Scandium hydroxide	$Sc(OH)_3$	17674-34-9	95.978	col amorp sol					i H_2O; s dil acid
1947	Scandium nitrate	$Sc(NO_3)_3$	13465-60-6	230.971	wh cry				169^{25}	s EtOH
1948	Scandium oxide	Sc_2O_3	12060-08-1	137.910	wh cub cry	2485		3.864		s conc acid
1949	Scandium sulfide	Sc_2S_3	12166-29-9	186.110	yel orth cry	1775		2.91		
1950	Scandium telluride	Sc_2Te_3	12166-44-8	472.71	blk hex cry			5.29		
1951	Selenium (α form)	Se	7782-49-2	78.96	red monocl cry	221	685	4.39		i H_2O, EtOH; sl eth
1952	Selenium (gray)	Se	7782-49-2	78.96	gray metallic cry; hex	220.5	685	4.81		i H_2O, CS_2
1953	Selenium (vitreous)	Se	7782-49-2	78.96	blk amorp solid	trans to gray Se 180	685	4.28		i H_2O; sl CS_2
1954	Selenic acid	H_2SeO_4	7783-08-6	144.97	wh hyg solid	58	260 dec	2.95		vs H_2O; reac EtOH
1955	Selenous acid	H_2SeO_3	7783-00-8	128.97	wh hyg cry	70 dec		3.0		vs H_2O; s EtOH
1956	Selenium dioxide	SeO_2	7446-08-4	110.96	wh tetr needles or powder	340 tp	315 sp	3.95	264^{22}	s EtOH, MeOH; sl ace
1957	Selenium trioxide	SeO_3	13768-86-0	126.96	wh tetr cry; hyg	118	subl	3.44		s H_2O, os
1958	Selenium bromide	Se_2Br_2	7789-52-8	317.73	red liq		225 dec	3.60		reac H_2O; s CS_2, chl
1959	Selenium chloride	Se_2Cl_2	10025-68-0	228.83	yel-brn oily liq	-85	130 dec	2.774		reac H_2O; s CS_2, bz, ctc, chl
1960	Selenium tetrabromide	$SeBr_4$	7789-65-3	398.58	oran-red cry	123				reac H_2O; s CS_2, chl
1961	Selenium tetrachloride	$SeCl_4$	10026-03-6	220.77	wh-yel cry	305 tp	191.4 sp	2.6		reac H_2O
1962	Selenium tetrafluoride	SeF_4	13465-66-2	154.95	col liq	-10	106	2.75		reac H_2O; vs EtOH, eth
1963	Selenium hexafluoride	SeF_6	7783-79-1	192.95	col gas	-34.6 tp	-46.6 sp	7.887 g/L		i H_2O
1964	Selenium oxybromide	$SeOBr_2$	7789-51-7	254.77	red-yel solid	41.6	220 dec	3.38		reac H_2O; s CS_2, bz, ctc
1965	Selenium oxychloride	$SeOCl_2$	7791-23-3	165.86	col or yel liq	8.5	177	2.44		reac H_2O; s ctc, chl, bz, tol
1966	Selenium oxyfluoride	$SeOF_2$	7783-43-9	132.96	col liq	15	125	2.8		reac H_2O
1967	Selenium dioxydifluoride	SeO_2F_2	14984-81-7	148.96	col gas	-99.5	-8.4	6.089 g/L		reac H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
1968	Selenium sulfide	SeS_2	7488-56-4	143.09	red-yel cry	100				i H_2O; s acid
1969	Selenium sulfide	Se_2S_6	75926-26-0	350.32	oran needles	121.5		2.44		s CS_2; sl bz
1970	Selenium sulfide	Se_4S_4	75926-28-2	444.10	red cry	113 dec		3.29		s bz; sl CS_2
1971	Selenium sulfide	Se_6S_2	75926-30-6	537.89	oran cry	121.5				s CS_2
1972	Silicon	Si	7440-21-3	28.086	gray cry or brn amorp solid	1414	3265	2.3290		i H_2O, acid; s alk
1973	Silane	SiH_4	7803-62-5	32.118	col gas; flam	-185	-111.9	1.313 g/L		reac H_2O; i EtOH, bz
1974	Disilane	Si_2H_6	1590-87-0	62.219	col gas; flam	-132.5	-14.3	2.543 g/L		reac H_2O, ctc, chl; s EtOH, bz
1975	Trisilane	Si_3H_8	7783-26-8	92.321	flam liq	-117.4	52.9	0.739		reac H_2O
1976	Tetrasilane	Si_4H_{10}	7783-29-1	122.421	col liq; flam	-89.9	108.1	0.792		reac H_2O
1977	2-Silyltrisilane	Si_4H_{10}	13597-87-0	122.421	col liq	-99.4	101.7	0.792		reac H_2O
1978	Pentasilane	Si_5H_{12}	14868-53-2	152.523	col liq	-72.8	153.2	0.827		reac H_2O
1979	2-Silyltetrasilane	Si_5H_{12}	14868-54-3	152.523	col liq	-109.9	146.2	0.820		reac H_2O
1980	2,2-Disilyltrisilane	Si_5H_{12}	15947-57-6	152.523	col liq	-57.8	134.3	0.815		reac H_2O
1981	Hexasilane	Si_6H_{14}	14693-61-9	182.624	col liq	-44.7	193.6	0.847		reac H_2O
1982	2-Silylpentasilane	Si_6H_{14}	14868-55-4	182.624	col liq	-78.4	185.2	0.840		
1983	3-Silylpentasilane	Si_6H_{14}	14868-55-4	182.624	col liq	-69	179.5	0.843		reac H_2O
1984	Heptasilane	Si_7H_{16}	14693-65-3	212.726	col liq	-30.1	226.8	0.859		reac H_2O
1985	Cyclopentasilane	Si_5H_{10}	289-22-5	150.507	col liq	-10.5	194.3	0.963		reac H_2O
1986	Cyclohexasilane	Si_6H_{12}	291-59-8	180.608	col liq	16.5	226			reac H_2O
1987	Bromosilane	SiH_3Br	13465-73-1	111.014	col gas	-94	1.9	4.538 g/L		
1988	Bromotrichlorosilane	$SiCl_3Br$	13465-74-2	214.348	col liq	-62	80.3	1.826		reac H_2O
1989	Chlorosilane	SiH_3Cl	13465-78-6	66.563	col gas	-118	-30.4	2.721 g/L		
1990	Chlorotrifluorosilane	$SiClF_3$	14049-36-6	120.534	col gas	-138	-70.0	4.927 g/L		reac H_2O
1991	Dibromodichlorosilane	$SiBr_2Cl_2$	13465-75-3	258.799	col liq	-45.5	104	2.172		reac H_2O
1992	Dibromosilane	SiH_2Br_2	13768-94-0	189.910	liq	-70.1	66			
1993	Dichlorosilane	SiH_2Cl_2	4109-96-0	101.007	col gas; flam	-122	8.3	4.129 g/L		reac H_2O
1994	Dichlorodifluorosilane	$SiCl_2F_2$	18356-71-3	136.988	col gas	-44	-32	5.599 g/L		reac H_2O
1995	Difluorosilane	SiH_2F_2	13824-36-7	68.099	col gas	-122	-77.8	2.783 g/L		
1996	Diiodosilane	SiH_2I_2	13760-02-6	283.911	col liq	-1	150			
1997	Fluorosilane	SiH_3F	13537-33-2	50.108	col gas		-98.6	2.048 g/L		
1998	Iodosilane	SiH_3I	13598-42-0	158.014	col liq	-57	45.6			
1999	Tetrabromosilane	$SiBr_4$	7789-66-4	347.702	col fuming liq	5.39	154	2.8		reac H_2O
2000	Tetrachlorosilane	$SiCl_4$	10026-04-7	169.897	col fuming liq	-68.74	57.65	1.5		reac H_2O
2001	Tetrafluorosilane	SiF_4	7783-61-1	104.080	col gas	-90.2	-86	4.254 g/L		reac H_2O
2002	Tetraiodosilane	SiI_4	13465-84-4	535.704	wh powder	120.5	287.35	4.1		
2003	Tribromosilane	$SiHBr_3$	7789-57-3	268.806	flam liq	-73	109	2.7		reac H_2O
2004	Tribromochlorosilane	$SiBr_3Cl$	13465-76-4	303.251	col liq	-20.8	127	2.497		reac H_2O
2005	Trichlorosilane	$SiHCl_3$	10025-78-2	135.452	fuming liq	-128.2	33	1.331		reac H_2O
2006	Trichlorofluorosilane	$SiCl_3F$	14965-52-7	153.442	col gas		12.25	6.272 g/L		
2007	Trichloroiodosilane	$SiCl_3I$	13465-85-5	261.348	col liq	-60	113.5			reac H_2O
2008	Trifluorosilane	$SiHF_3$	13465-71-9	86.089	col gas	-131	-95	3.519 g/L		
2009	Triiodosilane	$SiHI_3$	13465-72-0	409.807	liq	8	220 dec			
2010	Disiloxane	$(SiH_3)_2O$	13597-73-4	78.218	gas	-144	-15.2	3.197 g/L		
2011	Metasilicic acid	H_2SiO_3	7699-41-4	78.100	wh amorp powder					i H_2O; s HF
2012	Orthosilicic acid	H_4SiO_4	10193-36-9	96.116	exists only in soln					
2013	Fluorosilicic acid	H_2SiF_6	16961-83-4	144.092	stable only in aq soln					s H_2O
2014	Silicon carbide (hexagonal)	SiC	409-21-2	40.097	hard grn-black hex cry	2830		3.16		i H_2O, EtOH
2015	Silicon nitride	Si_3N_4	12033-89-5	140.284	gray refrac solid; hex	1900		3.17		
2016	Silicon monoxide	SiO	10097-28-6	44.085	blk cub cry, stable >1200			2.18		
2017	Silicon dioxide (α-quartz)	SiO_2	14808-60-7	60.085	col hex cry	trans to beta quartz 573	2950	2.648		i H_2O, acid; s HF
2018	Silicon dioxide (β-quartz)	SiO_2	14808-60-7	60.085	col hex cry	trans to tridymite 867	2950	2.533^{600}		i H_2O, acid; s HF
2019	Silicon dioxide (tridymite)	SiO_2	15468-32-3	60.085	col hex cry	trans cristobalite 1470	2950	2.265		i H_2O, acid; s HF
2020	Silicon dioxide (cristobalite)	SiO_2	14464-46-1	60.085	col hex cry	1722	2950	2.334		i H_2O, acid; s HF
2021	Silicon dioxide (vitreous)	SiO_2	60676-86-0	60.085	col amorp solid	1713	2950	2.196		i H_2O, acid; s HF
2022	Silicon monosulfide	SiS	12504-41-5	60.152	yel-red hyg powder	≈900	940	1.85		reac H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2023	Silicon disulfide	SiS_2	13759-10-9	92.218	wh rhomb cry	1090	subl	2.04		reac H_2O, EtOH; i bz
2024	Silver	Ag	7440-22-4	107.868	silv metal; cub	961.78	2162	10.5		
2025	Silver azide	AgN_3	13863-88-2	149.888	orth cry; exp	exp ≈250		4.9	0.00081^{20}	
2026	Silver subfluoride	Ag_2F	1302-01-8	234.734	yel hex cry	100 dec		8.6		reac H_2O
2027	Silver(I) acetate	$AgC_2H_3O_2$	563-63-3	166.912	wh needles or powder	dec		3.26	1.04^{20}	
2028	Silver(I) acetylide	Ag_2C_2	7659-31-6	239.757	wh powder; exp					
2029	Silver(I) arsenate	Ag_3AsO_4	13510-44-6	462.524	red cub cry	dec		6.657	0.00085	s NH_4OH
2030	Silver(I) acetylide	AgC_2H	13092-75-6	132.897	wh powder; exp					
2031	Silver(I) bromate	$AgBrO_3$	7783-89-3	235.770	wh tetr cry	360 dec		5.21	0.193^{25}	
2032	Silver(I) bromide	AgBr	7785-23-1	187.772	yel cub cry	432	1502	6.47	0.000014^{25}	i acid
2033	Silver(I) carbonate	Ag_2CO_3	534-16-7	275.745	yel monocl cry	218		6.077	0.0036^{20}	s acid
2034	Silver(I) chlorate	$AgClO_3$	7783-92-8	191.319	wh tetr cry	230	270 dec	4.430	17.6^{25}	sl EtOH
2035	Silver(I) chloride	AgCl	7783-90-6	143.321	wh cub cry	455	1547	5.56	0.00019^{25}	
2036	Silver(I) chlorite	$AgClO_2$	7783-91-7	175.320	yel cry	105 exp			0.55^{25}	
2037	Silver(I) chromate	Ag_2CrO_4	7784-01-2	331.730	brn-red monocl cry			5.625	0.000014^{0}	
2038	Silver(I) citrate	$Ag_3C_6H_5O_7$	126-45-4	512.705	wh cry powder					i H_2O; s HNO_3
2039	Silver(I) cyanide	AgCN	506-64-9	133.886	wh-gray hex cry	320 dec		3.95	0.0000011	i EtOH, dil acid
2040	Silver(I) dichromate	$Ag_2Cr_2O_7$	7784-02-3	431.724	red cry			4.770		sl H_2O
2041	Silver(I) diethyldithiocarbamate	$Ag(C_2H_5)_2NCS_2$	1470-61-7	256.140	pow	173				s py
2042	Silver(I) fluoride	AgF	7775-41-9	126.866	yel-brn cub cry; hyg	435	1159	5.852	172^{20}	
2043	Silver(I) hexafluoroantimonate	$AgSbF_6$	26042-64-8	343.618	pow					
2044	Silver(I) hexafluoroarsenate	$AgAsF_6$	12005-82-2	296.780	pow					
2045	Silver(I) hexafluorophosphate	$AgPF_6$	26042-63-7	252.832	pow	102 dec				
2046	Silver(I) hydrogen fluoride	$AgHF_2$	12249-52-4	146.873	hyg cry	dec				
2047	Silver(I) iodate	$AgIO_3$	7783-97-3	282.770	wh orth cry	>200		5.53	0.053^{25}	
2048	Silver(I) iodide	AgI	7783-96-2	234.772	yel powder; hex	558	1506	5.68	0.000003	i acid
2049	Silver(I) lactate monohydrate	$AgC_3H_5O_3 \cdot H_2O$	128-00-7	214.954	gray cry powder					sl H_2O, EtOH
2050	Silver(I) metaphosphate	$AgPO_3$	13465-96-8	186.840	grn glass	490		6.37		i H_2O; s HNO_3, NH_4OH
2051	Silver(I) molybdate	Ag_2MoO_4	13765-74-7	375.67	yel cub cry	483		6.18		sl H_2O
2052	Silver(I) nitrate	$AgNO_3$	7761-88-8	169.873	col rhomb cry	212	440 dec	4.35	234^{25}	sl EtOH, ace
2053	Silver(I) nitrite	$AgNO_2$	7783-99-5	153.874	yel needles	140 dec		4.453	0.415^{25}	i EtOH; reac acid
2054	Silver(I) oxalate	$Ag_2C_2O_4$	533-51-7	303.755	wh cry powder	exp 140		5.03	0.0043^{20}	
2055	Silver(I) oxide	Ag_2O	20667-12-3	231.735	brn-blk cub cry	≈200 dec		7.2	0.0025	i EtOH; s acid, alk
2056	Silver(I) perchlorate	$AgClO_4$	7783-93-9	207.319	col cub cry; hyg	486 dec		2.806	558^{25}	s bz, py, os
2057	Silver(I) perchlorate monohydrate	$AgClO_4 \cdot H_2O$	14242-05-8	225.334	hyg wh cry	43 dec			558^{25}	
2058	Silver(I) permanganate	$AgMnO_4$	7783-98-4	226.804	viol monocl cry	dec		4.49	0.91^{18}	reac EtOH
2059	Silver(I) phosphate	Ag_3PO_4	7784-09-0	418.576	yel powder	849		6.37	0.0064	sl dil acid
2060	Silver(I) picrate monohydrate	$AgC_6H_2N_3O_7 \cdot H_2O$	146-84-9	353.979	yel cry					sl H_2O, EtOH; i chl, eth
2061	Silver(I) selenate	Ag_2SeO_4	7784-07-8	358.69	orth cry			5.72	0.118^{20}	
2062	Silver(I) selenide	Ag_2Se	1302-09-6	294.70	gray hex needles	880		8.216		i H_2O
2063	Silver(I) selenite	Ag_2SeO_3	7784-05-6	342.69	needles	530	>550 dec	5.930		sl H_2O; s acid
2064	Silver(I) sulfate	Ag_2SO_4	10294-26-5	311.800	col cry or powder	652		5.45	0.84^{25}	
2065	Silver(I) sulfide	Ag_2S	21548-73-2	247.802	gray-blk orth powder	825		7.23		i H_2O; s acid
2066	Silver(I) sulfite	Ag_2SO_3	13465-98-0	295.800	wh cry	100 dec			0.00046^{20}	s acid, NH_4OH
2067	Silver(I) telluride	Ag_2Te	12002-99-2	343.34	blk orth cry	955		8.4		
2068	Silver(I) tetraiodomercurate(II)	Ag_2HgI_4	7784-03-4	923.94	yel tetr cry	trans to red cub ≈40		6.1		i H_2O, dil acid
2069	Silver(I) thiocyanate	AgSCN	1701-93-5	165.952	wh powder	dec				i H_2O
2070	Silver(I) thiosulfate	$Ag_2S_2O_3$	23149-52-2	327.866	wh cry	dec				sl H_2O; s NH_4OH
2071	Silver(II) oxide	AgO	1301-96-8	123.867	gray powder; monocl or cub	>100 dec		7.5	0.0027^{25}	s alk; reac acid
2072	Silver(I) tungstate	Ag_2WO_4	13465-93-5	463.57	yel cry	620			0.015	s HNO_3, NH_4OH
2073	Silver(II) fluoride	AgF_2	7783-95-1	145.865	wh or gray hyg cry	690		4.58		reac H_2O
2074	Silver(II) oxide (Ag2O2)	Ag_2O_2	25455-73-6	247.735	gray-blk cub cry	>100		7.44		i H_2O; s acid, NH_4OH
2075	Sodium	Na	7440-23-5	22.990	soft silv met; cub	97.794	882.940	0.97		reac H_2O
2076	Sodium acetate	$NaC_2H_3O_2$	127-09-3	82.034	col cry	328.2		1.528	50.4^{25}	
2077	Sodium acetate trihydrate	$NaC_2H_3O_2 \cdot 3H_2O$	6131-90-4	136.079	col cry	58 dec		1.45	50.4^{25}	sl EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2078	Sodium aluminate	$NaAlO_2$	1302-42-7	81.971	wh orth cry; hyg	1650		4.63		vs H_2O; i EtOH
2079	Sodium aluminum hydride	$NaAlH_4$	13770-96-2	54.004	wh hyg solid	174 dec		1.24		i eth; s thf
2080	Sodium aluminum sulfate dodecahydrate	$NaAl(SO_4)_2 \cdot 12H_2O$	10102-71-3	458.283	col cry	≈60		1.61	39.7^{20}	i EtOH
2081	Sodium amide	$NaNH_2$	7782-92-5	39.013	wh-grn orth cry	210	500 dec	1.39		reac H_2O
2082	Sodium ammonium phosphate tetrahydrate	$NaNH_4HPO_4 \cdot 4H_2O$	13011-54-6	209.069	monocl cry	≈80 dec		1.54		s H_2O; i EtOH
2083	Sodium arsenite	$NaAsO_2$	7784-46-5	129.911	wh-gray hyg powder			1.87		vs H_2O; i EtOH
2084	Sodium azide	NaN_3	26628-22-8	65.010	col hex cry	300 dec		1.846	40.8^{20}	sl EtOH; i eth
2085	Sodium borohydride	$NaBH_4$	16940-66-2	37.833	wh cub cry; hyg	≈400 dec		1.07	55^{20}	reac EtOH
2086	Sodium bromate	$NaBrO_3$	7789-38-0	150.892	col cub cry	381		3.34	39.4^{25}	i EtOH
2087	Sodium bromide	NaBr	7647-15-6	102.894	wh cub cry	747	1390	3.200	94.6^{25}	s EtOH
2088	Sodium bromide dihydrate	$NaBr \cdot 2H_2O$	13466-08-5	138.925	wh cry	36 dec		2.18	94.6^{25}	sl EtOH
2089	Sodium carbonate	Na_2CO_3	497-19-8	105.989	wh hyg powder	858.1		2.54	30.7^{25}	i EtOH
2090	Sodium carbonate decahydrate	$Na_2CO_3 \cdot 10H_2O$	6132-02-1	286.142	col cry	34 dec		1.46	30.7^{25}	i EtOH
2091	Sodium carbonate monohydrate	$Na_2CO_3 \cdot H_2O$	5968-11-6	124.005	col orth cry	100 dec		2.25	30.7^{25}	i EtOH
2092	Sodium chlorate	$NaClO_3$	7775-09-9	106.441	col cub cry	248	>300 dec	2.5	100^{25}	sl EtOH
2093	Sodium chloride	NaCl	7647-14-5	58.443	col cub cry	800.7	1465	2.17	36.0^{25}	sl EtOH
2094	Sodium chlorite	$NaClO_2$	7758-19-2	90.442	wh hyg cry	≈180 dec			64^{17}	
2095	Sodium chromate	Na_2CrO_4	7775-11-3	161.974	yel orth cry	792		2.72	87.6^{25}	sl EtOH
2096	Sodium chromate tetrahydrate	$Na_2CrO_4 \cdot 4H_2O$	10034-82-9	234.035	yel hyg cry	dec			87.6^{25}	sl EtOH
2097	Sodium citrate dihydrate	$Na_3C_6H_5O_7 \cdot 2H_2O$	6132-04-3	294.099	wh cry	150 dec				vs H_2O; i EtOH, eth
2098	Sodium cyanate	NaCNO	917-61-3	65.007	col needles	550		1.89		s H_2O; sl EtOH; i eth
2099	Sodium cyanide	NaCN	143-33-9	49.008	wh cub cry; hyg	563		1.6	58.2^{20}	sl EtOH
2100	Sodium cyanoborohydride	$NaBH_3(CN)$	25895-60-7	62.843	wh hyg powder	240 dec		1.12		vs H_2O; s thf; sl EtOH; i bz, eth
2101	Sodium dichromate	$Na_2Cr_2O_7$	10588-01-9	261.968	red hyg cry	357	400 dec		187^{25}	
2102	Sodium dihydrogen phosphate	NaH_2PO_4	7558-80-7	119.977	col mono cry	200 dec			94.9^{25}	
2103	Sodium dihydrogen phosphate monohydrate	$NaH_2PO_4 \cdot H_2O$	10049-21-5	137.993	wh hyg cry	100 dec			94.9^{25}	i EtOH
2104	Sodium dihydrogen phosphate dihydrate	$NaH_2PO_4 \cdot 2H_2O$	13472-35-0	156.008	col orth cry	60 dec		1.91	94.9^{25}	i EtOH
2105	Sodium dihydrogen hypophosphate hexahydrate	$Na_2H_2P_2O_6 \cdot 6H_2O$	7782-95-8*	314.031	mono plates	110 dec		1.849	2.0^{25}	i EtOH
2106	Sodium dihydrogen pyrophosphate	$Na_2H_2P_2O_7$	7758-16-9	221.939	wh powder	220 dec		≈1.9		s H_2O
2107	Sodium dithionate	$Na_2S_2O_4$	7775-14-6	174.110	gray-wh pow	52 dec			24.1^{20}	sl EtOH
2108	Sodium dithionate dihydrate	$Na_2S_2O_6 \cdot 2H_2O$	7631-94-9*	242.139	col orth cry	110 dec		2.19	15.1^{20}	i EtOH
2109	Sodium ethanolate	NaC_2H_5O	141-52-6	68.050	wh-yel hyg pow					reac H_2O; s EtOH
2110	Sodium ferricyanide monohydrate	$Na_3Fe(CN)_6 \cdot H_2O$	14217-21-1*	298.933	red hyg cry					s H_2O; i EtOH
2111	Sodium ferrocyanide decahydrate	$Na_4Fe(CN)_6 \cdot 10H_2O$	13601-19-9	484.061	yel monocl cry	≈50 dec		1.46	20^{20}	i os
2112	Sodium fluoride	NaF	7681-49-4	41.988	col cub or tetr cry	996	1704	2.78	4.13^{25}	i EtOH
2113	Sodium tetrafluoroborate	$NaBF_4$	13755-29-8	109.795	wh orth prisms	384		2.47	108^{20}	sl EtOH
2114	Sodium fluorophosphate	Na_2PO_3F	10163-15-2	143.950	pow					
2115	Sodium formate	$NaCHO_2$	141-53-7	68.008	wh hyg cry	257.3	dec	1.92	94.9^{25}	sl EtOH
2116	Sodium germanate	Na_2GeO_3	12025-19-3	166.59	wh mono hyg cry	1083		3.31		
2117	Sodium hexabromoplatinate(IV) hexahydrate	$Na_2PtBr_6 \cdot 6H_2O$	39277-13-9	828.57	cry					
2118	Sodium hexachloroiridate(IV) hexahydrate	$Na_2IrCl_6 \cdot 6H_2O$	19567-78-3	559.004	cry	600 dec				
2119	Sodium hexachloroplatinate(IV)	Na_2PtCl_6	16923-58-3	453.77	yel hyg cry				53^{16}	s EtOH
2120	Sodium hexachloroplatinate(IV) hexahydrate	$Na_2PtCl_6 \cdot 6H_2O$	16923-58-3	561.87	yel cry	110 dec		2.50	53^{16}	s EtOH; i eth
2121	Sodium hexafluoroaluminate	Na_3AlF_6	13775-53-6	209.941	col monocl cry; trans cub 560	1009		2.97		i H_2O
2122	Sodium hexafluoroantimonate	$NaSbF_6$	16925-25-0	258.740	wh cub cry			3.375	129^{20}	s EtOH, ace
2123	Sodium hexafluorophosphate monohydrate	$NaPF_6 \cdot H_2O$	20644-15-9	185.969	col orth cry			2.369	103^{0}	s EtOH, MeOH, ace

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2124	Sodium hexafluorosilicate	Na_2SiF_6	16893-85-9	188.056	wh hex cry	dec		2.7	0.67^{20}	i EtOH
2125	Sodium hexanitrocobaltate(III)	$Na_3Co(NO_2)_6$	14649-73-1	403.935	yel-brn cry pow					vs H_2O; sl EtOH
2126	Sodium hydride	NaH	7646-69-7	23.998	silv cub cry; flam	425 dec		1.39		reac H_2O, EtOH
2127	Sodium hydrogen arsenate	Na_2HAsO_4	7778-43-0	185.908	wh pow	≈195 dec			51^{20}	sl EtOH
2128	Sodium hydrogen arsenate heptahydrate	$Na_2HAsO_4 \cdot 7H_2O$	10048-95-0	312.014	wh monocl cry	≈50 dec		1.87	51^{20}	sl EtOH
2129	Sodium hydrogen carbonate	$NaHCO_3$	144-55-8	84.007	wh monocl cry	≈50 dec		2.20	10.3^{25}	i EtOH
2130	Sodium hydrogen fluoride	$NaHF_2$	1333-83-1	61.995	wh hex cry	>160 dec		2.08	3.25^{20}	
2131	Sodium hydrogen phosphate	Na_2HPO_4	7558-79-4	141.959	wh hyg powder			1.7	11.8^{25}	
2132	Sodium hydrogen phosphate dodecahydrate	$Na_2HPO_4 \cdot 12H_2O$	10039-32-4	358.143	col cry	≈35 dec		≈1.5	11.8^{25}	i EtOH
2133	Sodium hydrogen phosphate heptahydrate	$Na_2HPO_4 \cdot 7H_2O$	7782-85-6	268.066	col cry			≈1.7	11.8^{25}	i EtOH
2134	Sodium hydrogen sulfate	$NaHSO_4$	7681-38-1	120.062	wh hyg cry	≈315		2.43	28.5^{25}	
2135	Sodium hydrogen sulfate monohydrate	$NaHSO_4 \cdot H_2O$	10034-88-5	138.077	wh monocl cry			2.10	28.5^{25}	reac EtOH
2136	Sodium hydrogen sulfide	NaHS	16721-80-5	56.064	col rhomb cry	350		1.79		s H_2O, EtOh, eth
2137	Sodium hydrogen sulfide dihydrate	$NaHS \cdot 2H_2O$	16721-80-5	92.095	yel hyg needles	55 dec				vs H_2O, EtOH, eth
2138	Sodium hydrogen sulfite	$NaHSO_3$	7631-90-5	104.062	wh cry			1.48		s H_2O; sl EtOH
2139	Sodium hydroxide	NaOH	1310-73-2	39.997	wh orth cry; hyg	323	1388	2.13	100^{25}	s EtOH, MeOH
2140	Sodium hypochlorite	NaClO	7681-52-9	74.442	stable in aq soln	anh form exp			79.9^{25}	
2141	Sodium hypochlorite pentahydrate	$NaOCl \cdot 5H_2O$	10022-70-5	164.518	pale grn orth cry	18		1.6		s H_2O
2142	Sodium iodate	$NaIO_3$	7681-55-2	197.892	wh orth cry	dec		4.28	9.47^{25}	i EtOH
2143	Sodium iodide	NaI	7681-82-5	149.894	wh cub cry; hyg	660	1304	3.67	184^{25}	s EtOH, ace
2144	Sodium bismuthate	$NaBiO_3$	12232-99-4	279.968	yel-brn hyg cry					i cold H_2O, reac acid
2145	Sodium metabisulfite	$Na_2S_2O_5$	7681-57-4	190.109	wh cry				66.7^{25}	sl EtOH
2146	Sodium metaborate	$NaBO_2$	7775-19-1	65.800	wh hex cry	966	1434	2.46		s H_2O
2147	Sodium metasilicate	Na_2SiO_3	6834-92-0	122.064	wh amorp solid; hyg	1089		2.61		s cold H_2O; reac hot H_2O
2148	Sodium molybdate	Na_2MoO_4	7631-95-0	205.92	col cub cry	687		≈3.5	65.0^{25}	
2149	Sodium molybdate dihydrate	$Na_2MoO_4 \cdot 2H_2O$	10102-40-6	241.95	cry powder	100 dec		≈3.5	65.0^{25}	
2150	Sodium niobate	$NaNbO_3$	12034-09-2	163.894	rhomb cry	1422		4.55		i H_2O
2151	Sodium nitrate	$NaNO_3$	7631-99-4	84.995	col hex cry; hyg	307		2.26	91.2^{25}	sl EtOH, MeOH
2152	Sodium nitrite	$NaNO_2$	7632-00-0	68.996	wh orth cry; hyg	271	>320 dec	2.17	84.8^{25}	sl EtOH; reac acid
2153	Sodium nitroprusside dihydrate	$Na_2[Fe(CN)_5NO] \cdot 2H_2O$	13755-38-9	297.949	red cry			1.72	40^{16}	sl EtOH
2154	Sodium orthovanadate	Na_3VO_4	13721-39-6	183.909	col hex prisms	860				s H_2O; i EtOH
2155	Sodium oxalate	$Na_2C_2O_4$	62-76-0	133.999	wh powder	≈250 dec		2.34	3.61^{25}	i EtOH
2156	Sodium oxide	Na_2O	1313-59-3	61.979	wh amorp powder	1132 dec		2.27		reac H_2O
2157	Sodium perborate tetrahydrate	$NaBO_3 \cdot 4H_2O$	7632-04-4	153.861	wh cry	60 dec				reac H_2O
2158	Sodium perchlorate	$NaClO_4$	7601-89-0	122.441	wh orth cry; hyg	480 dec		2.52	205^{25}	
2159	Sodium perchlorate monohydrate	$NaClO_4 \cdot H_2O$	7791-07-3	140.456	wh hyg cry	≈130 dec		2.02	205^{25}	
2160	Sodium periodate	$NaIO_4$	7790-28-5	213.892	wh tetr cry	≈300 dec		3.86	14.4^{25}	s acid
2161	Sodium periodate trihydrate	$NaIO_4 \cdot 3H_2O$	13472-31-6	267.938	wh hex cry	175 dec		3.22	14.4^{25}	
2162	Sodium permanganate trihydrate	$NaMnO_4 \cdot 3H_2O$	10101-50-5*	195.972	red-blk hyg cry	170 dec		2.47	144^{20}	reac EtOH
2163	Sodium peroxide	Na_2O_2	1313-60-6	77.979	yel hyg powder	675		2.805		reac H_2O
2164	Sodium perrhenate	$NaReO_4$	13472-33-8	273.195	cry	300		5.39		
2165	Sodium persulfate	$Na_2S_2O_8$	7775-27-1	238.107	wh hyg cry					vs H_2O; reac EtOH
2166	Sodium phosphate dodecahydrate	$Na_3PO_4 \cdot 12H_2O$	10101-89-0	380.124	col hex cry	≈75		1.62	14.4^{25}	i EtOH
2167	Chlorinated trisodium phosphate	$Na_3PO_4 \cdot NaOCl$	56802-99-4	238.383	wh cry				25^{25}	
2168	Sodium phosphinate	NaH_2PO_2	7681-53-0	87.979	wh cry				100^{25}	
2169	Sodium phosphinate monohydrate	$NaH_2PO_2 \cdot H_2O$	10039-56-2	105.994	col hyg cry	310 dec			100^{25}	s EtOH
2170	Sodium potassium tartrate tetrahydrate	$NaKC_4H_4O_6 \cdot 4H_2O$	304-59-6	282.220	wh cry	≈70 dec	anh at 130	1.79		vs H_2O; i EtOH
2171	Sodium pyrophosphate	$Na_4P_2O_7$	7722-88-5	265.902	col cry	988		2.53	7.09^{25}	
2172	Sodium selenate	Na_2SeO_4	13410-01-0	188.94	col orth cry				58.5^{25}	
2173	Sodium selenate decahydrate	$Na_2SeO_4 \cdot 10H_2O$	10102-23-5	369.09	wh cry			1.61	58.5^{25}	
2174	Sodium selenide	Na_2Se	1313-85-5	124.94	amorp solid	>875		2.62		reac H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2175	Sodium selenite	Na_2SeO_3	10102-18-8	172.94	wh tetr cry				89.8^{25}	i EtOH
2176	Sodium stearate	$NaC_{18}H_{35}O_2$	822-16-2	306.460	wh pow					sl H_2O, EtOH; vs hot H_2O
2177	Sodium succinate hexahydrate	$Na_2C_4H_4O_4 \cdot 6H_2O$	150-90-3	270.144	cry pow	120 dec			20	i EtOH
2178	Sodium sulfate	Na_2SO_4	7757-82-6	142.044	wh orth cry or powder	884		2.7	28.1^{25}	i EtOH
2179	Sodium sulfate decahydrate	$Na_2SO_4 \cdot 10H_2O$	7727-73-3	322.197	col monocl cry	32 dec		1.46	28.1^{25}	i EtOH
2180	Sodium sulfide	Na_2S	1313-82-2	78.046	wh cub cry; hyg	1172		1.856	20.6^{25}	sl EtOH; i eth
2181	Sodium sulfide nonahydrate	$Na_2S \cdot 9H_2O$	1313-84-4	240.184	wh-yel hyg cry	≈50 dec		1.43	20.6^{25}	sl EtOH; i eth
2182	Sodium sulfide pentahydrate	$Na_2S \cdot 5H_2O$	1313-83-3	168.122	col orth cry	120 dec		1.58	20.6^{25}	s EtOH; i eth
2183	Sodium sulfite	Na_2SO_3	7757-83-7	126.044	wh hex cry	dec		2.63	30.7^{25}	i EtOH
2184	Sodium sulfite heptahydrate	$Na_2SO_3 \cdot 7H_2O$	10102-15-5	252.151	wh monocl cry; unstable			1.56	30.7^{25}	sl EtOH
2185	Sodium superoxide	NaO_2	12034-12-7	54.989	yel cub cry	552		2.2		reac H_2O
2186	Sodium tellurate	Na_2TeO_4	10101-83-4	237.58	wh powder				0.8	
2187	Sodium tellurite	Na_2TeO_3	10102-20-2	221.58	wh rhomb prisms					sl H_2O
2188	Sodium tetraborate	$Na_2B_4O_7$	1330-43-4	201.220	col gl solid; hyg	743	1575	2.4	3.17^{25}	sl MeOH
2189	Sodium tetraborate decahydrate	$Na_2B_4O_7 \cdot 10H_2O$	1303-96-4	381.373	wh monocl cry	75 dec		1.73	3.17^{25}	i EtOH
2190	Sodium tetraborate pentahydrate	$Na_2B_4O_7 \cdot 5H_2O$	12045-88-4	291.296	hex cry	dec		1.88	3.17^{25}	
2191	Sodium tetraborate tetrahydrate	$Na_2B_4O_7 \cdot 4H_2O$	12045-87-3	273.281	wh monocl cry			1.95	3.17^{25}	
2192	Sodium tetrachloroaluminate	$NaAlCl_4$	7784-16-9	191.783	orth cry			2.01		s H_2O
2193	Sodium tetrachloroaurate(III) dihydrate	$NaAuCl_4 \cdot 2H_2O$	13874-02-7	397.799	oran-yel rhom cry	100 dec			150^{10}	s EtOH, eth
2194	Sodium tetrachloropalladate(II) trihydrate	$Na_2PdCl_4 \cdot 3H_2O$	13820-53-6	348.26	brn-red hyg cry					vs H_2O; s EtOH
2195	Sodium tetrachloroplatinate(II) tetrahydrate	$Na_2PtCl_4 \cdot 4H_2O$	10026-00-3	454.93	red prisms	100				s H_2O, EtOH
2196	Sodium tetrafluoroberyllate	Na_2BeF_4	13871-27-7	130.986	orth cry	575		2.47		sl H_2O
2197	Sodium thiocyanate	NaSCN	540-72-7	81.074	col hyg cry	287			151^{25}	
2198	Sodium thiophosphate dodecahydrate	$Na_3PO_3S \cdot 12H_2O$	10101-88-9	396.191	hex hyg leaflets	60				vs hot H_2O
2199	Sodium thiosulfate	$Na_2S_2O_3$	7772-98-7	158.110	col mono cry	100 dec		1.69	76.4^{25}	i EtOH
2200	Sodium thiosulfate pentahydrate	$Na_2S_2O_3 \cdot 5H_2O$	10102-17-7	248.186	col cry	≈50 dec		1.69	76.4^{25}	i EtOH
2201	Sodium trimetaphosphate	$Na_3(PO_3)_3$	7785-84-4	305.885	wh cry			2.49	22	
2202	Sodium trimetaphosphate hexahydrate	$Na_3(PO_3)_3 \cdot 6H_2O$	7785-84-4	413.976	tricl-rhom hyg prisms	53		1.786	22	i EtOH
2203	Sodium tripolyphosphate	$Na_5P_3O_{10}$	7758-29-4	367.864	wh hyg pow	622			20^{25}	
2204	Sodium tungstate	Na_2WO_4	13472-45-2	293.82	wh rhom cry	695		4.18	74.2^{25}	
2205	Sodium tungstate dihydrate	$Na_2WO_4 \cdot 2H_2O$	10213-10-2	329.85	wh orth cry	100 dec		3.25	74.2^{25}	i EtOH
2206	Sodium uranate(VI) monohydrate	$Na_2U_2O_7 \cdot H_2O$	13721-34-1	652.049	yel pow					i H_2O; s acid
2207	Sodium vanadate(V)	$NaVO_3$	13718-26-8	121.930	col mono prisms	630			21^{25}	
2208	Sodium vanadate(V) tetrahydrate	$NaVO_3 \cdot 4H_2O$	13718-26-8	193.992	yel-wh cry pow				21^{25}	
2209	Strontium	Sr	7440-24-6	87.62	silv-wh metal; cub	777	1382	2.64		reac H_2O; s EtOH
2210	Strontium arsenite tetrahydrate	$Sr(AsO_2)_2 \cdot 4H_2O$	10378-48-0	373.52	wh pow					sl H_2O, EtOH; sol dil acid
2211	Strontium bromate monohydrate	$Sr(BrO_3)_2 \cdot H_2O$	14519-18-7	361.44	yel hyg mono cry	120 dec		3.773	39.0^{25}	
2212	Strontium bromide	$SrBr_2$	10476-81-0	247.43	wh tetr cry	657		4.216	107^{25}	
2213	Strontium bromide hexahydrate	$SrBr_2 \cdot 6H_2O$	7789-53-9	355.52	col hyg cry	88 dec			107^{25}	s EtOH; i eth
2214	Strontium carbide	SrC_2	12071-29-3	111.64	blk tetr cry	>1700		3.19		i H_2O
2215	Strontium carbonate	$SrCO_3$	1633-05-2	147.63	wh orth cry; hyg	1494		3.5	0.00034^{20}	s dil acid
2216	Strontium chlorate	$Sr(ClO_3)_2$	7791-10-8	254.52	col cry	120 dec		3.15	176^{25}	sl EtOH
2217	Strontium chloride	$SrCl_2$	10476-85-4	158.53	wh cub cry; hyg	874	1250	3.052	54.7^{25}	
2218	Strontium chloride hexahydrate	$SrCl_2 \cdot 6H_2O$	10025-70-4	266.62	col hyg cry	100 dec		1.96	54.7^{25}	s EtOH
2219	Strontium chromate	$SrCrO_4$	7789-06-2	203.61	yel monocl cry	dec		3.9	0.106^{20}	s dil acid
2220	Strontium cyanide dihydrate	$Sr(CN)_2 \cdot 4H_2O$		211.72	wh hyg cry	dec				vs H_2O

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2221	Strontium ferrocyanide pentadecahydrate	$SrFe(CN)_6 \cdot 15H_2O$		569.80	yel mono cry				50	
2222	Strontium fluoride	SrF_2	7783-48-4	125.62	wh cub cry or powder	1477	2460	4.24	0.021^{25}	s dil acid
2223	Strontium formate	$Sr(CHO_2)_2$	592-89-2	177.66	wh cry	71.9		2.693	9.1^{0}	
2224	Strontium formate dihydrate	$Sr(CHO_2)_2 \cdot 2H_2O$	6160-34-5	213.69	col rhom cry	100 dec		2.25	9.1^{37}	i EtOH, eth
2225	Strontium hexaboride	SrB_6	12046-54-7	152.49	blk cub cry	2235		3.39		i H_2O; s HNO_3
2226	Strontium hydride	SrH_2	13598-33-9	89.64	orth cry	1050		3.26		reac H_2O
2227	Strontium hydroxide	$Sr(OH)_2$	18480-07-4	121.64	col orth cry; hyg	535	710 dec	3.625	2.25^{25}	
2228	Strontium iodate	$Sr(IO_3)_2$	13470-01-4	437.43	tricl cry			5.045	0.165^{25}	
2229	Strontium iodide	SrI_2	10476-86-5	341.43	wh hyg cry	538	1773 dec	4.55	177^{25}	
2230	Strontium iodide hexahydrate	$SrI_2 \cdot 6H_2O$	73796-25-5	449.52	wh-yel hex cry; hyg	120 dec		4.4	177^{25}	s EtOH
2231	Strontium niobate	$SrNb_2O_6$	12034-89-8	369.43	monocl cry	1225		5.11		i H_2O
2232	Strontium nitrate	$Sr(NO_3)_2$	10042-76-9	211.63	wh cub cry	570	645	2.99	80.2^{25}	sl EtOH, ace
2233	Strontium nitride	Sr_3N_2	12033-82-8	290.87	refrac solid	1200				reac H_2O; s HCl
2234	Strontium nitrite	$Sr(NO_2)_2$	13470-06-9	179.63	wh-yel hyg needles	240 dec		2.8	72.1^{30}	
2235	Strontium oxide	SrO	1314-11-0	103.62	col cub cry	2531		5.1		reac H_2O
2236	Strontium perchlorate	$Sr(ClO_4)_2$	13450-97-0	286.52	col hyg cry				306^{25}	s EtOH, MeOH
2237	Strontium permanganate trihydrate	$Sr(MnO_4)_2 \cdot 3H_2O$		379.54	pur cub cry	175 dec		2.75	250^{18}	
2238	Strontium peroxide	SrO_2	1314-18-7	119.62	wh tetr cry; unstable	215 dec		4.78		reac H_2O
2239	Strontium phosphate	$Sr_3(PO_4)_2$	7446-28-8	452.80	wh powder				0.000011^{20}	s acid
2240	Strontium selenate	$SrSeO_4$	7446-21-1	230.58	orth cry			4.25	0.115^{20}	s hot HCl
2241	Strontium selenide	SrSe	1315-07-7	166.58	wh cub cry	1600		4.54		
2242	Strontium orthosilicate	Sr_2SiO_4	13597-55-2	267.32	orth cry			4.5		
2243	Strontium silicide	$SrSi_2$	12138-28-2	143.79	silv-gray cub cry	1100		3.35		
2244	Strontium sulfate	$SrSO_4$	7759-02-6	183.68	wh orth cry	1606		3.96	0.0135^{25}	i EtOH; sl acid
2245	Strontium sulfide	SrS	1314-96-1	119.69	gray cub cry	2226		3.70		sl H_2O; s acid
2246	Strontium sulfite	$SrSO_3$	13451-02-0	167.68	col cry	dec			0.0015^{25}	s H_2SO_4, HCl
2247	Strontium telluride	SrTe	12040-08-3	215.22	wh cub cry			4.83		
2248	Strontium thiosulfate pentahydrate	$SrS_2O_3 \cdot 5H_2O$	15123-90-7	289.83	mono needles	100 dec		2.17	36.3^{25}	i EtOH
2249	Strontium titanate	$SrTiO_3$	12060-59-2	183.49	wh cub cry	2080		5.1		i H_2O
2250	Strontium tungstate	$SrWO_4$	13451-05-3	335.46	col tetr cry	dec		6.187	0.14^{15}	i EtOH
2251	Sulfur (rhombic)	S	7704-34-9	32.066	yel orth cry	95.3 (trans to monocl)	444.60	2.07		i H_2O; sl EtOH, bz, eth; s CS_2
2252	Sulfur (monoclinic)	S	7704-34-9	32.066	yel monocl needles, stable 95.3-120	115.21	444.60	2.07		i H_2O; sl EtOH, bz, eth; s CS_2
2253	Sulfuric acid	H_2SO_4	7664-93-9	98.080	col oily liq	10.31	337	1.8302^{20}		vs H_2O
2254	Peroxysulfuric acid	H_2SO_5	7722-86-3	114.079	wh cry; unstable	45 dec				vs H_2O
2255	Nitrosylsulfuric acid	$HNOSO_4$	7782-78-7	127.078	prisms	73 dec				reac H_2O; s H_2SO_4
2256	Chlorosulfonic acid	$SO_2(OH)Cl$	7790-94-5	116.525	col-yel liq	-80	152	1.75		reac H_2O; s py
2257	Fluorosulfonic acid	$SO_2(OH)F$	7789-21-1	100.070	col liq	-89	163	1.726		reac H_2O
2258	Sulfurous acid	H_2SO_3	7782-99-2	82.080	exists only in soln					soln of SO_2 in H_2O
2259	Sulfamic acid	H_2NSO_3H	5329-14-6	97.095	orth cry	≈205 dec		2.15	14.7^{0}	sl ace; i eth
2260	Sulfur dioxide	SO_2	7446-09-5	64.065	col gas	-75.5	-10.05	2.619 g/L		s H_2O, EtOh, eth, chl
2261	Sulfur trioxide	SO_3	7446-11-9	80.064	col liq	16.8	45	1.92		reac H_2O
2262	Sulfur bromide	$SSBr_2$	13172-31-1	223.940	red oily liq	-46	>25 dec	2.63		reac H_2O
2263	Sulfur chloride	$SSCl_2$	10025-67-9	135.037	yel-red oily liq	-77	137	1.69		reac H_2O; s EtOH, bz, eth, ctc
2264	Sulfur fluoride	SSF_2	16860-99-4	102.129	col gas	-164.6	-10.6	4.174 g/L		reac H_2O
2265	Sulfur fluoride	FSSF	13709-35-8	102.129	col gas	-133	15	4.174 g/L		reac H_2O
2266	Sulfur dichloride	SCl_2	10545-99-0	102.971	red visc liq	-122	59.6	1.62		reac H_2O
2267	Sulfur tetrafluoride	SF_4	7783-60-0	108.060	col gas	-125	-40.45	4.417 g/L		reac H_2O
2268	Sulfur hexafluoride	SF_6	2551-62-4	146.056	col gas	-50.7 tp	-63.8 sp	5.970 g/L		sl H_2O; s EtOH
2269	Sulfur bromide pentafluoride	SF_5Br	15607-89-3	206.962	col gas	-79	3.1	8.459 g/L		
2270	Sulfur chloride pentafluoride	SF_5Cl	13780-57-9	162.511	col gas	-64	-19.05	6.642 g/L		
2271	Sulfur decafluoride	S_2F_{10}	5714-22-7	254.116	liq	-52.7	30; dec 150	2.08		i H_2O
2272	Sulfuryl amide	$(NH_2)_2SO_2$	7803-58-9	96.110	orth plates	93	250 dec			vs H_2O; sl EtOH
2273	Sulfuryl chloride	SO_2Cl_2	7791-25-5	134.970	col liq	-51	69.4	1.680		reac H_2O; s bz, tol, eth

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2274	Sulfuryl fluoride	SO_2F_2	2699-79-8	102.062	col gas	-135.8	-55.4	4.172 g/L		sl H_2O, EtOH; s tol, ctc
2275	Pyrosulfuryl chloride	$S_2O_5Cl_2$	7791-27-7	215.034	col fuming liq	-37	151	1.837		reac H_2O
2276	Thionyl bromide	$SOBr_2$	507-16-4	207.873	yel liq	-50	140			reac H_2O
2277	Thionyl chloride	$SOCl_2$	7719-09-7	118.970	yel fuming liq	-101	75.6	1.631		reac H_2O; s bz, ctc, chl
2278	Thionyl fluoride	SOF_2	7783-42-8	86.062	col gas	-129.5	-43.8	3.518 g/L		reac H_2O; s bz, eth
2279	Sulfur fluoride hypofluorite	F_2SOF	15179-32-5	162.055	col gas	-86	-35.1	6.624 g/L		
2280	Tantalum	Ta	7440-25-7	180.948	gray metal; cub	3007	5458	16.4		reac HF
2281	Tantalum aluminide	$TaAl_3$	12004-76-1	261.893	gray refrac powder	≈1400		7.02		i H_2O, acid, alk
2282	Tantalum boride	TaB	12007-07-7	191.759	refrac orth cry	2040		14.2		
2283	Tantalum boride	TaB_2	12007-35-1	202.570	blk hex cry	3140		11.2		i H_2O, acid, alk
2284	Tantalum carbide	TaC	12070-06-3	192.959	gold-brown powder; cub	3880	4780	14.3		s HF-HNO_3 mixture
2285	Tantalum carbide	Ta_2C	12070-07-4	373.907	refrac hex cry	3327		15.1		
2286	Tantalum nitride	TaN	12033-62-4	194.955	blk hex cry	3090		13.7		i H_2O; sl aqua regia; reac alk
2287	Tantalum silicide	$TaSi_2$	12039-79-1	237.119	gray powder	2200		9.14		
2288	Tantalum(IV) oxide	TaO_2	12036-14-5	212.947	tetr cry			10.0		
2289	Tantalum(IV) selenide	$TaSe_2$	12039-55-3	338.87	hex cry			6.7		
2290	Tantalum(IV) sulfide	TaS_2	12143-72-5	245.080	blk hex cry	>3000		6.86		i H_2O
2291	Tantalum(IV) telluride	$TaTe_2$	12067-66-2	436.15	monocl cry			9.4		
2292	Tantalum(V) bromide	$TaBr_5$	13451-11-1	580.468	yel cry powder	265	349	4.99		
2293	Tantalum(V) chloride	$TaCl_5$	7721-01-9	358.212	yel monocl cry; hyg	216	239.35	3.68		reac H_2O; s EtOH
2294	Tantalum(V) fluoride	TaF_5	7783-71-3	275.940	wh monocl cry; hyg	95.1	229.2	5.0		s H_2O, eth; sl CS_2, ctc
2295	Tantalum(V) iodide	TaI_5	14693-81-3	815.470	blk hex cry; hyg	496	543	5.80		
2296	Tantalum(V) oxide	Ta_2O_5	1314-61-0	441.893	wh rhomb cry or powder	1784		8.2		i H_2O, EtOH, acid; s HF
2297	Technetium	Tc	7440-26-8	98	hex cry	2157	4265	11		
2298	Technetium(V) fluoride	TcF_5	31052-14-9	193	yel solid	50	dec			
2299	Technetium(VI) fluoride	TcF_6	13842-93-8	212	yel cub cry	37.4	55.3	3.0		
2300	Tellurium	Te	13494-80-9	127.60	gray-wh rhomb cry	449.51	988	6.24		i H_2O, bz, CS_2
2301	Telluric(VI) acid	H_6TeO_6	7803-68-1	229.64	wh monocl cry	136		3.07	50.1[30]	
2302	Tellurous acid	H_2TeO_3	10049-23-7	177.61	wh cry	40 dec		3.0		sl H_2O; s dil acid, alk
2303	Tellurium dioxide	TeO_2	7446-07-3	159.60	wh orth cry	733	1245	5.9		i H_2O; s alk, acid
2304	Tellurium trioxide	TeO_3	13451-18-8	175.60	yel-oran cry	430		5.07		i H_2O
2305	Tellurium dibromide	$TeBr_2$	7789-54-0	287.41	grn-brn hyg cry	210	339			reac H_2O; s eth; sl chl
2306	Tellurium dichloride	$TeCl_2$	10025-71-5	198.51	blk amorp solid; hyg	208	328	6.9		reac H_2O; i ctc
2307	Tellurium tetrabromide	$TeBr_4$	10031-27-3	447.22	yel-oran monocl cry	388	≈420 dec	4.3		reac H_2O; s eth
2308	Tellurium tetrachloride	$TeCl_4$	10026-07-0	269.41	wh monocl cry; hyg	224	387	3.0		reac H_2O; s EtOH, tol
2309	Tellurium tetrafluoride	TeF_4	15192-26-4	203.59	col cry	129	195 dec			reac H_2O
2310	Tellurium tetraiodide	TeI_4	7790-48-9	635.22	blk orth cry	280		5.05		reac H_2O; sl ace
2311	Tellurium hexafluoride	TeF_6	7783-80-4	241.59	col gas	-37.6 tp	-38.9 sp	9.875 g/L		reac H_2O
2312	Terbium	Tb	7440-27-9	158.925	silv metal; hex	1356	3230	8.23		
2313	Terbium chloride	$TbCl_3$	10042-88-3	265.283	wh orth cry; hyg	588		4.35		s H_2O
2314	Terbium chloride hexahydrate	$TbCl_3 \cdot 6H_2O$	13798-24-8	373.374	hyg cry			4.35		vs H_2O
2315	Terbium iodide	TbI_3	13813-40-6	539.638	hex cry; hyg	957		≈5.2		s H_2O
2316	Terbium nitrate	$Tb(NO_3)_3$	10043-27-3	344.940	pink hyg solid				157[25]	s EtOH
2317	Terbium nitrate hexahydrate	$Tb(NO_3)_3 \cdot 6H_2O$	13451-19-9	453.031	col needles	89				s H_2O, EtOH, ace
2318	Terbium nitride	TbN	12033-64-6	172.932	cub cry			9.55		
2319	Terbium oxide	Tb_2O_3	12036-41-8	365.849	wh cub cry	2303		7.91		
2320	Terbium silicide	$TbSi_2$	12039-80-4	215.096	orth cry			6.66		
2321	Terbium sulfide	Tb_2S_3	12138-11-3	414.049	cub cry			6.35		
2322	Thallium	Tl	7440-28-0	204.383	soft blue-wh metal	304	1473	11.8		i H_2O; reac acid
2323	Thallium(I) acetate	$TlC_2H_3O_2$	563-68-8	263.427	hyg wh cry	131		3.68		s H_2O, EtOH
2324	Thallium(I) bromate	$TlBrO_3$	14550-84-6	332.285	col needles	120 dec			0.49[30]	s EtOH
2325	Thallium(I) bromide	TlBr	7789-40-4	284.287	yel cub cry	460	819	7.5	0.059[20]	
2326	Thallium(I) carbonate	Tl_2CO_3	6533-73-9	468.776	wh monocl cry	272		7.11	4.69[20]	i EtOH
2327	Thallium(I) chlorate	$TlClO_3$	13453-30-0	287.834	col hex cry			5.5	3.92[20]	

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2328	Thallium(I) chloride	TlCl	7791-12-0	239.836	wh cub cry	430	720	7.0	0.33^{20}	i EtOH
2329	Thallium(I) chromate	Tl_2CrO_4		524.761	yel cry				0.003^{20}	sl acid, alk
2330	Thallium(I) cyanide	TlCN	13453-34-4	230.401	wh hex plates			6.523		s H_2O, acid, EtOH
2331	Thallium(I) ethanolate	TlC_2H_5O	20398-06-5	249.443	cloudy liq	-3	130 dec	3.49		reac H_2O
2332	Thallium(I) fluoride	TlF	7789-27-7	223.381	wh orth cry	326	826	8.36	245^{25}	
2333	Thallium(I) formate	$TlCHO_2$	992-98-3	249.401	hyg col needles	101		4.97		vs H_2O; s MeOH
2334	Thallium(I) hexafluorophosphate	$TlPF_6$	60969-19-9	349.347	wh cub cry			4.6		
2335	Thallium(I) hydroxide	TlOH	12026-06-1	221.390	yel needles	139 dec		7.44	34.3^{18}	
2336	Thallium(I) iodate	$TlIO_3$	14767-09-0	379.285	wh needles				0.058	sl HNO_3
2337	Thallium(I) iodide	TlI	7790-30-9	331.287	yel cry powder	441.7	824	7.1	0.0085^{20}	i EtOH
2338	Thallium(I) molybdate	Tl_2MoO_4	34128-09-1	568.71	yel-wh cub cry					i H_2O
2339	Thallium(I) nitrate	$TlNO_3$	10102-45-1	266.388	wh cry	206	450 dec	5.55	9.55^{20}	i EtOH
2340	Thallium(I) nitrite	$TlNO_2$	13826-63-6	250.389	cub cry			5.7	32.1^{25}	
2341	Thallium(I) oxalate	$Tl_2C_2O_4$	30737-24-7	496.786	wh powder			6.31	1.83^{20}	
2342	Thallium(I) oxide	Tl_2O	1314-12-1	424.766	blk rhomb cry; hyg	579	≈1080	9.52		s H_2O, EtOH
2343	Thallium(I) perchlorate	$TlClO_4$	13453-40-2	303.834	col orth cry			4.8	19.7^{30}	
2344	Thallium(I) selenate	Tl_2SeO_4	7446-22-2	551.73	orth cry	>400		6.875	2.8^{20}	i EtOH, eth
2345	Thallium(I) selenide	Tl_2Se	15572-25-5	487.73	gray plates	340				i H_2O, acid
2346	Thallium(I) sulfate	Tl_2SO_4	7446-18-6	504.831	wh rhomb prisms	632		6.77	5.47^{25}	
2347	Thallium(I) sulfide	Tl_2S	1314-97-2	440.833	blue-blk cry	448	1367	8.39	0.02^{20}	sl alk; s acid
2348	Thallium(III) bromide tetrahydrate	$TlBr_3 \cdot 4H_2O$	13701-90-1	516.157	yel orth cry			3.65		s H_2O, EtOH
2349	Thallium(III) chloride	$TlCl_3$	13453-32-2	310.741	monocl cry	155		4.7		vs H_2O, EtOH, eth
2350	Thallium(III) chloride tetrahydrate	$TlCl_3 \cdot 4H_2O$	13453-32-2*	382.803	orth cry			3.00		s H_2O
2351	Thallium(III) fluoride	TlF_3	7783-57-5	261.378	wh orth cry; hyg	550 dec		8.65		reac H_2O
2352	Thallium(III) nitrate	$Tl(NO_3)_3$	13746-98-0	390.398	col cry					reac H_2O
2353	Thallium(III) oxide	Tl_2O_3	1314-32-5	456.765	brn cub cry	834		10.2		i H_2O; reac acid
2354	Thallium(III) sulfate	$Tl_2(SO_4)_3$	16222-66-5	696.958	col leaflets					reac H_2O
2355	Thallium selenide	TlSe	12039-52-0	283.34	blk solid	330				i H_2O, acid
2356	Thorium	Th	7440-29-1	232.038	soft gray-wh metal; cub	1750	4788	11.7		s acid
2357	Thorium hydride	ThH_2	16689-88-6	234.054	tetr cry			9.5		
2358	Thorium boride	ThB_6	12229-63-9	296.904	refrac solid	2450		6.99		
2359	Thorium(IV) bromide	$ThBr_4$	13453-49-1	551.654	wh hyg cry	679			65^{20}	
2360	Thorium carbide	ThC	12012-16-7	244.049	cub cry	2500		10.6		reac H_2O
2361	Thorium dicarbide	ThC_2	12071-31-7	256.059	yel monocl cry	≈2650		9.0		reac H_2O
2362	Thorium(IV) chloride	$ThCl_4$	10026-08-1	373.849	gray-wh tetr needles; hyg	770	921	4.59		s H_2O, EtOH
2363	Thorium(IV) fluoride	ThF_4	13709-59-6	308.032	wh monocl cry; hyg	1110	1680	6.1		
2364	Thorium(IV) iodide	ThI_4	7790-49-0	739.656	wh-yel monocl cry	570	837			
2365	Thorium(IV) nitrate tetrahydrate	$Th(NO_3)_4 \cdot 4H_2O$	33088-16-3	552.119	wh hyg cry	500 dec			191^{20}	s EtOH
2366	Thorium nitride	ThN	12033-65-7	246.045	refrac cub cry	2820		11.6		reac H_2O
2367	Thorium(IV) oxide	ThO_2	1314-20-1	264.037	wh cub cry	3390	4400	10.0		i H_2O, alk; sl acid
2368	Thorium(IV) selenide	$ThSe_2$	60763-24-8	389.96	orth cry			8.5		
2369	Thorium orthosilicate	$ThSiO_4$	14553-44-7	324.122	brn tetr cry			6.7		
2370	Thorium silicide	$ThSi_2$	12067-54-8	288.209	tetr cry	1850		7.9		
2371	Thorium(IV) sulfate nonahydrate	$Th(SO_4)_2 \cdot 9H_2O$	10381-37-0	586.303	wh monocl cry	dec		2.8	4.2^{20}	
2372	Thorium(IV) sulfide	ThS_2	12138-07-7	296.170	dark brn cry	1905		7.30		i H_2O; s acid
2373	Thulium	Tm	7440-30-4	168.934	silv metal; hex	1545	1950	9.32		s dil acid
2374	Thulium bromide	$TmBr_3$	14456-51-0	408.646	wh hyg cry	954				s H_2O
2375	Thulium chloride	$TmCl_3$	13537-18-3	275.292	yel hyg cry	824				s H_2O
2376	Thulium chloride heptahydrate	$TmCl_3 \cdot 7H_2O$	13778-39-7	401.399	hyg cry					s H_2O, EtOH
2377	Thulium fluoride	TmF_3	13760-79-7	225.929	wh cry	1158				s H_2O
2378	Thulium iodide	TmI_3	13813-43-9	549.647	yel hyg cry	1021				
2379	Thulium nitrate	$Tm(NO_3)_3$	14985-19-4	354.949	grn hyg solid				212^{25}	s EtOH
2380	Thulium nitrate pentahydrate	$Tm(NO_3)_3 \cdot 5H_2O$	36548-87-5	445.025	grn hyg cry					s H_2O, EtOH, ace
2381	Thulium oxide	Tm_2O_3	12036-44-1	385.866	grn-wh cub cry	2341	3945	8.6		sl acid
2382	Tin (gray)	Sn	7440-31-5	118.710	cub cry	trans to wh Sn 13.2	2602	5.769		
2383	Tin (white)	Sn	7440-31-5	118.710	silv tetr cry	231.93	2602	7.265		

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2384	Stannane	SnH_4	2406-52-2	122.742	unstable col gas	-146	-51.8	5.017 g/L		
2385	Methylstannane	SnH_3CH_3	1631-78-3	136.769	col gas		0	5.590 g/L		reac H_2O
2386	Tin(II) acetate	$Sn(C_2H_3O_2)_2$	638-39-1	236.799	wh orth cry	183	subl	2.31		s dil HCl
2387	Tin(II) bromide	$SnBr_2$	10031-24-0	278.518	yel powder	215	639	5.12	85^0	s EtOH, eth, ace
2388	Tin(II) chloride	$SnCl_2$	7772-99-8	189.615	wh orth cry	247.1	623	3.90	178^{10}	s EtOH, ace, eth; i xyl
2389	Tin(II) chloride dihydrate	$SnCl_2 \cdot 2H_2O$	10025-69-1	225.646	wh monocl cry	37 dec		2.71	178^{10}	s EtOH, NaOH; vs HCl
2390	Tin(II) fluoride	SnF_2	7783-47-3	156.707	wh monocl cry; hyg	213	850	4.57		s H_2O; i EtOH, eth, chl
2391	Tin(II) hexafluorozirconate	$SnZrF_6$	12419-43-1	323.924	cry			4.21		s H_2O
2392	Tin(II) hydroxide	$Sn(OH)_2$	12026-24-3	152.725	wh amorp solid					
2393	Tin(II) iodide	SnI_2	10294-70-9	372.519	red-oran powder	320	714	5.28	0.98^{20}	s bz, chl, CS_2
2394	Tin(II) oxalate	SnC_2O_4	814-94-8	206.729	wh powder	280 dec		3.56		i H_2O; s dil HCl
2395	Tin(II) oxide	SnO	21651-19-4	134.709	blue-blk tetr cry	1080 dec		6.45		i H_2O, EtOH; s acid
2396	Tin(II) pyrophosphate	$Sn_2P_2O_7$	15578-26-4	411.363	wh amorp powder	400 dec		4.009		i H_2O; s conc acid
2397	Tin(II) selenide	SnSe	1315-06-6	197.67	gray orth cry	861		6.18		i H_2O; s aqua regia
2398	Tin(II) sulfate	$SnSO_4$	7488-55-3	214.774	wh orth cry	378 dec		4.15	18.8^{19}	
2399	Tin(II) sulfide	SnS	1314-95-0	150.776	gray orth cry	880	1210	5.08		i H_2O; s conc acid
2400	Tin(II) tartrate	$SnC_4H_4O_6$	815-85-0	266.781	wh cry powder					s H_2O, dil HCl
2401	Tin(II) telluride	SnTe	12040-02-7	246.31	gray cub cry	790		6.5		
2402	Tin(IV) bromide	$SnBr_4$	7789-67-5	438.326	wh cry	29.1	205	3.34		vs H_2O; s EtOH
2403	Tin(IV) chloride	$SnCl_4$	7646-78-8	260.521	col fuming liq	-34.07	114.15	2.234		reac H_2O; s EtOH, ctc, bz, ace
2404	Tin(IV) chloride pentahydrate	$SnCl_4 \cdot 5H_2O$	10026-06-9	350.597	wh-yel cry	56 dec		2.04		vs H_2O; s EtOH
2405	Tin(IV) chromate	$Sn(CrO_4)_2$	38455-77-5	350.697	brn-yel cry powder	dec				s H_2O
2406	Tin(IV) fluoride	SnF_4	7783-62-2	194.704	wh tetr cry		705 subl	4.78		reac H_2O
2407	Tin(IV) iodide	SnI_4	7790-47-8	626.328	yel-brn cub cry	143	364.35	4.46		reac H_2O; s EtOH, bz, chl, eth
2408	Tin(IV) oxide	SnO_2	18282-10-5	150.709	gray tetr cry	1630		6.85		i H_2O, EtOH; s hot conc alk
2409	Tin(IV) selenide	$SnSe_2$	20770-09-6	276.63	red-brn cry	650		≈5.0		i H_2O; s alk, conc acid
2410	Tin(IV) selenite	$Sn(SeO_3)_2$	7446-25-5	372.63	cry powder					i H_2O; s hot HCl
2411	Tin(IV) sulfide	SnS_2	1315-01-1	182.842	gold-yel hex cry	600 dec		4.5		i H_2O; s alk, aqua regia
2412	Titanium	Ti	7440-32-6	47.867	gray metal; hex	1670	3287	4.506		
2413	Titanium hydride	TiH_2	7704-98-5	49.883	gray-blk powder	≈450 dec		3.75		i H_2O
2414	Titanium boride	TiB_2	12045-63-5	69.489	gray refrac solid; hex	3225		4.38		
2415	Titanium carbide	TiC	12070-08-5	59.878	cub cry	3067		4.93		i H_2O; s HNO_3
2416	Titanium nitride	TiN	25583-20-4	61.874	yel-brn cub cry	2950		5.21		i H_2O; s aqua regia
2417	Titanium phosphide	TiP	12037-65-9	78.841	gray hex cry	1990		4.08		
2418	Titanium silicide	$TiSi_2$	12039-83-7	104.038	blk orth cry	1500		4.0		i H_2O, acid, alk; s HF
2419	Titanium(II) bromide	$TiBr_2$	13783-04-5	207.675	blk powder			4.0		reac H_2O
2420	Titanium(II) chloride	$TiCl_2$	10049-06-6	118.772	blk hex cryc	1035	1500	3.13		reac H_2O; s EtOH; i chl, eth
2421	Titanium(II) iodide	TiI_2	13783-07-8	301.676	blk hex cry			5.02		reac H_2O
2422	Titanium(II) oxide	TiO	12137-20-1	63.866	cub cry	1750		4.95		
2423	Titanium(II) sulfide	TiS	12039-07-5	79.933	brn hex cry	1780		3.85		s conc acid
2424	Titanium(III) bromide	$TiBr_3$	13135-31-4	287.579	blue-blk hex cry					s H_2O
2425	Titanium(III) chloride	$TiCl_3$	7705-07-9	154.225	red-viol hex cry; hyg	425 dec	960	2.64		reac H_2O
2426	Titanium(III) fluoride	TiF_3	13470-08-1	104.862	viol hex cry	1200	1400	2.98		i H_2O, dil acid, alk
2427	Titanium(III) oxide	Ti_2O_3	1344-54-3	143.732	viol hex cry	1842		4.486		s hot HF
2428	Titanium(III) sulfate	$Ti_2(SO_4)_3$	10343-61-0	383.925	grn cry					i H_2O, EtOH; s dil HCl
2429	Titanium(III) sulfide	Ti_2S_3	12039-16-6	191.932	blk hex cry			3.56		
2430	Titanium(III,IV) oxide	Ti_3O_5	12065-65-5	223.598	blk monocl cry	1777		4.24		
2431	Titanium(IV) bromide	$TiBr_4$	7789-68-6	367.483	yel-oran cub cry; hyg	39	230	3.37		reac H_2O
2432	Titanium(IV) chloride	$TiCl_4$	7550-45-0	189.678	col or yel liq	-24.12	136.45	1.73		reac H_2O; s EtOH
2433	Titanium(IV) fluoride	TiF_4	7783-63-3	123.861	wh hyg powder	284	subl	2.798		reac H_2O; s EtOH, py
2434	Titanium(IV) iodide	TiI_4	7720-83-4	555.485	red hyg powder	150	377	4.3		reac H_2O
2435	Titanium(IV) oxide	TiO_2	13463-67-7	79.866	wh tetr cry	1843		4.23		i H_2O, dil acid; s conc acid

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2436	Titanium(IV) oxysulfate monohydrate	$TiOSO_4 \cdot H_2O$	13825-74-6*	177.945	col orth cry			2.71		reac H_2O
2437	Titanium(IV) sulfate	$Ti(SO_4)_2$	13693-11-3	239.994	wh-yel hyg cry	150 dec				s H_2O
2438	Titanium(IV) sulfide	TiS_2	12039-13-3	111.999	yel-brn hex cry; hyg			3.37		s H_2SO_4
2439	Tungsten	W	7440-33-7	183.84	gray-wh metal; cub	3414	5555	19.3		
2440	Tungstic acid	H_2WO_4	7783-03-1	249.85	yel amorp powder	100 dec		5.5		i H_2O, acid; s alk
2441	Tungsten boride	W_2B	12007-10-2	378.49	refrac blk powder	2670		16.0		i H_2O
2442	Tungsten boride	WB	12007-09-9	194.65	blk refrac powder	2665		15.2		i H_2O
2443	Tungsten boride	W_2B_5	12007-98-6	421.74	refrac solid	2365		11.0		i H_2O
2444	Tungsten carbide	W_2C	12070-13-2	379.69	refrac hex cry	≈2800		14.8		i H_2O
2445	Tungsten carbide	WC	12070-12-1	195.85	gray hex cry	2785		15.6		i H_2O; s HNO_3/HF
2446	Tungsten carbonyl	$W(CO)_6$	14040-11-0	351.90	wh cry	170 dec	subl	2.65		i H_2O; s os
2447	Tungsten nitride	WN_2	60922-26-1	211.85	hex cry	600 dec		7.7		
2448	Tungsten nitride	W_2N	12033-72-6	381.69	gray cub cry	dec		17.8		
2449	Tungsten silicide	WSi_2	12039-88-2	240.01	blue-gray tetr cry	2160		9.3		i H_2O
2450	Tungsten silicide	W_5Si_3	12039-95-1	1003.46	blue-gray refrac solid	2320		14.4		
2451	Tungsten(II) bromide	WBr_2	13470-10-5	343.65	yel powder	400 dec				
2452	Tungsten(II) chloride	WCl_2	13470-12-7	254.75	yel solid	>500 dec				s H_2O
2453	Tungsten(II) iodide	WI_2	13470-17-2	437.65	oran cry			6.79		
2454	Tungsten(III) bromide	WBr_3	15163-24-3	423.55	blk hex cry	>80 dec				i H_2O
2455	Tungsten(III) chloride	WCl_3	20193-56-0	290.20	red solid	550 dec	subl			reac H_2O
2456	Tungsten(IV) bromide	WBr_4	14055-81-3	503.46	blk orth cry		240 subl			reac H_2O
2457	Tungsten(IV) chloride	WCl_4	13470-13-8	325.65	blk hyg powder	450 dec		4.62		reac H_2O
2458	Tungsten(IV) fluoride	WF_4	13766-47-7	259.83	red-brn cry	>800 dec				
2459	Tungsten(IV) iodide	WI_4	14055-84-6	691.46	blk powder	dec				reac H_2O; s EtOH; i eth chl
2460	Tungsten(IV) oxide	WO_2	12036-22-5	215.84	blue monocl cry	≈1500 dec		10.8		i H_2O, os
2461	Tungsten(IV) selenide	WSe_2	12067-46-8	341.76	gray hex cry			9.2		
2462	Tungsten(IV) sulfide	WS_2	12138-09-9	247.97	gray hex cry	1250 dec		7.6		i H_2O, HCl, alk
2463	Tungsten(IV) telluride	WTe_2	12067-76-4	439.04	gray orth cry	1020		9.43		
2464	Tungsten(V) bromide	WBr_5	13470-11-6	583.36	brn-blk hyg solid	286	333			
2465	Tungsten(V) chloride	WCl_5	13470-14-9	361.10	blk hyg cry	242	286			reac H_2O
2466	Tungsten(V) ethanolate	$W(C_2H_5O)_5$	62571-53-3	409.14	pow		105(0.05 mmHg)			s EtAc
2467	Tungsten(V) fluoride	WF_5	19357-83-6	278.83	yel solid	>80 dec				
2468	Tungsten(V) oxytribromide	$WOBr_3$	20213-56-3	439.55	dark brn tetr cry			≈5.9		
2469	Tungsten(V) oxytrichloride	$WOCl_3$	14249-98-0	306.20	grn tetr cry			≈4.6		
2470	Tungsten(VI) bromide	WBr_6	13701-86-5	663.26	blue-blk cry	309				
2471	Tungsten(VI) chloride	WCl_6	13283-01-7	396.56	purp hex cry; hyg	275	346.75	3.52		s EtOH, os
2472	Tungsten(VI) dioxydibromide	WO_2Br_2	13520-75-7	375.65	red cry		440 subl			
2473	Tungsten(VI) dioxydichloride	WO_2Cl_2	13520-76-8	286.74	yel orth cry	265		4.67		i H_2O
2474	Tungsten(VI) dioxydiiodide	WO_2I_2	14447-89-3	469.65	grn monocl cry	400 dec		6.39		
2475	Tungsten(VI) fluoride	WF_6	7783-82-6	297.83	col gas	2.3	17.1	12.17 g/L		reac H_2O
2476	Tungsten(VI) oxide	WO_3	1314-35-8	231.84	yel powder	1472		7.2		i H_2O; sl acid; s alk
2477	Tungsten(VI) oxytetrabromide	$WOBr_4$	13520-77-9	519.46	red tetr cry	277	327	≈5.5		reac H_2O
2478	Tungsten(VI) oxytetrachloride	$WOCl_4$	13520-78-0	341.65	red hyg cry	211	227.55	11.92		reac H_2O; s bz, CS_2
2479	Tungsten(VI) oxytetrafluoride	WOF_4	13520-79-1	275.83	wh monocl cry	106	185.9	5.07		reac H_2O
2480	Tungsten(VI) sulfide	WS_3	12125-19-8	280.04	brn powder					sl H_2O; s alk
2481	Uranium	U	7440-61-1	238.029	silv-wh orth cry	1135	4131	19.1		
2482	Uranium boride	UB_2	12007-36-2	259.651	refrac solid	2430		12.7		
2483	Uranium boride	UB_4	12007-84-0	281.273	refrac solid	2530		9.32		i H_2O
2484	Uranium carbide	UC	12070-09-6	250.040	gray cub cry	2790				
2485	Uranium carbide	UC_2	12071-33-9	262.050	gray tetr cry	2350	4370	11.3		reac H_2O; sl EtOH
2486	Uranium carbide	U_2C_3	12076-62-9	512.090	gray cub cry	≈1700 dec		12.7		
2487	Uranium nitride	UN	25658-43-9	252.036	gray cub cry	2805		14.3		i H_2O
2488	Uranium nitride	U_2N_3	12033-83-9	518.078	cub cry	dec		11.3		
2489	Uranium(III) bromide	UBr_3	13470-19-4	477.741	red hyg cry	727				s H_2O
2490	Uranium(III) chloride	UCl_3	10025-93-1	344.387	grn hyg cry	837		5.51		vs H_2O; i bz, ctc
2491	Uranium(III) fluoride	UF_3	13775-06-9	295.024	blk hex cry	dec		8.9		i H_2O; s acid
2492	Uranium(III) hydride	UH_3	13598-56-6	241.053	gray-blk cub cry			11.1		
2493	Uranium(III) iodide	UI_3	13775-18-3	618.742	blk hyg cry	766				s H_2O
2494	Uranium(IV) bromide	UBr_4	13470-20-7	557.645	brn hyg cry	519				s H_2O, EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2495	Uranium(IV) chloride	UCl_4	10026-10-5	379.840	grn octahed cry	590	791	4.72		reac H_2O; s EtOH
2496	Uranium(IV) fluoride	UF_4	10049-14-6	314.023	grn monocl cry	1036	1417	6.7	0.01^{25}	s conc acid, alk
2497	Uranium(IV) iodide	UI_4	13470-22-9	745.647	blk hyg cry	506				s H_2O, EtOH
2498	Uranium(IV) oxide	UO_2	1344-57-6	270.028	brn cub cry	2827		10.97		i H_2O, dil acid; s conc acid
2499	Uranium(IV,V) oxide	U_4O_9	12037-15-9	1096.111	cub cry			11.2		
2500	Uranium(V) bromide	UBr_5	13775-16-1	637.549	brn hyg cry					reac H_2O
2501	Uranium(V) chloride	UCl_5	13470-21-8	415.293	brn hyg cry	287				reac H_2O
2502	Uranium(V) fluoride	UF_5	13775-07-0	333.021	pale blue tetr cry; hyg	348		5.81		s H_2O
2503	Uranium(V,VI) oxide	U_3O_8	1344-59-8	842.082	grn-blk orth cry	1300 dec		8.38		
2504	Uranium(VI) chloride	UCl_6	13763-23-0	450.745	green hex cry	177		3.6		
2505	Uranium(VI) fluoride	UF_6	7783-81-5	352.019	wh monocl solid	64.0 tp	56.5 sp	5.09		reac H_2O; s ctc, chl
2506	Uranium(VI) oxide	UO_3	1344-58-7	286.027	oran-yel cry			≈7.3		i H_2O; s acid
2507	Uranium(VI) oxide monohydrate	$UO_3 \cdot H_2O$	12326-21-5	304.043	yel orth cry	570 dec		7.05		
2508	Uranium peroxide dihydrate	$UO_4 \cdot 2H_2O$	19525-15-6	338.057	yel hyg cry	115 dec				i H_2O
2509	Uranyl chloride	UO_2Cl_2	7791-26-6	340.933	yel orth cry; hyg	577				vs H_2O; s EtOH, ace; i bz
2510	Uranyl fluoride	UO_2F_2	13536-84-0	308.025	yel hyg solid				64.4^{20}	i bz
2511	Uranyl nitrate	$UO_2(NO_3)_2$	10102-06-4	394.037	yel cry				127^{25}	s eth
2512	Uranyl nitrate hexahydrate	$UO_2(NO_3)_2 \cdot 6H_2O$	13520-83-7	502.129	yel orth cry; hyg	60	118 dec	2.81	127^{25}	s EtOH, eth
2513	Uranyl sulfate	UO_2SO_4	1314-64-3	366.091	yel cry					
2514	Uranyl sulfate trihydrate	$UO_2SO_4 \cdot 3H_2O$	20910-28-5	420.138	yel cry			3.28	152^{16}	sl EtOH
2515	Vanadium	V	7440-62-2	50.942	gray-wh metal; cub	1910	3407	6.0		i H_2O; s acid
2516	Vanadium boride	VB	12045-27-1	61.753	refrac solid	2250				i H_2O
2517	Vanadium boride	VB_2	12007-37-3	72.564	refrac solid	2450				
2518	Vanadium carbide	VC	12070-10-9	62.953	refrac blk cry; cub	2810		5.77		i H_2O
2519	Vanadium carbide	V_2C	12012-17-8	113.894	hex cry	2167				
2520	Vanadium carbonyl	$V(CO)_6$	14024-00-1	219.002	blue-grn cry; flam	60 dec	subl			
2521	Vanadium nitride	VN	24646-85-3	64.949	blk powder; cub	2050		6.13		i H_2O; s aqua regia
2522	Vanadium silicide	VSi_2	12039-87-1	107.113	metallic prisms			4.42		s HF
2523	Vanadium silicide	V_3Si	12039-76-8	180.911	cub cry	1935		5.70		
2524	Vanadium(II) bromide	VBr_2	14890-41-6	210.750	oran-brn hex cry		800 subl	4.58		reac H_2O
2525	Vanadium(II) chloride	VCl_2	10580-52-6	121.847	grn hex plates	≈1350	910 subl	3.23		reac H_2O; s EtOH, eth
2526	Vanadium(II) fluoride	VF_2	13842-80-3	88.939	blue hyg cry					reac H_2O
2527	Vanadium(II) iodide	VI_2	15513-84-5	304.751	red-viol hex cry		800 subl	5.44		reac H_2O
2528	Vanadium(II) oxide	VO	12035-98-2	66.941	grn cry	1789		5.758		s acid
2529	Vanadium(II) sulfate heptahydrate	$VSO_4 \cdot 7H_2O$	36907-42-3	273.112	viol cry					
2530	Vanadium(III) 2,4-pentanedioate	$V(CH_3COCHCOCH_3)_3$	13476-99-8	348.266	brn cry	≈185	subl	≈1.0		s MeOH, ace, bz chl
2531	Vanadium(III) bromide	VBr_3	13470-26-3	290.654	gray-brn hyg cry			4.00		reac H_2O
2532	Vanadium(III) chloride	VCl_3	7718-98-1	157.300	red-viol hex cry; hyg	500 dec		3.00		reac H_2O; s EtOH, eth
2533	Vanadium(III) fluoride	VF_3	10049-12-4	107.937	yel-grn hex cry	≈1400	subl	3.363		i H_2O, EtOH
2534	Vanadium(III) fluoride trihydrate	$VF_3 \cdot 3H_2O$	10049-12-4*	161.983	grn rhomb cry	≈100 dec				sl H_2O
2535	Vanadium(III) iodide	VI_3	15513-94-7	431.655	brn-blk rhomb cry; hyg			5.21		reac H_2O
2536	Vanadium(III) oxide	V_2O_3	1314-34-7	149.881	blk powder	2067		4.87		i H_2O
2537	Vanadium(III) sulfate	$V_2(SO_4)_3$	13701-70-7	390.074	yel powder	≈400 dec				sl H_2O
2538	Vanadium(III) sulfide	V_2S_3	1315-03-3	198.081	grn-blk powder	dec		4.7		i H_2O; s hot HCl
2539	Vanadium(IV) bromide	VBr_4	13595-30-7	370.558	unstable magenta cry	-23 dec				
2540	Vanadium(IV) chloride	VCl_4	7632-51-1	192.753	unstable red liq	-25.7	148	1.816		reac H_2O; s EtOH, eth
2541	Vanadium(IV) fluoride	VF_4	10049-16-8	126.936	grn hyg powder	325 dec	subl	3.15		vs H_2O
2542	Vanadium(IV) oxide	VO_2	12036-21-4	82.941	blue-blk powder	1967		4.339		i H_2O; s acid, alk
2543	Vanadium(V) fluoride	VF_5	7783-72-4	145.934	col liq	19.5	48.3	2.50		reac H_2O
2544	Vanadium(V) oxide	V_2O_5	1314-62-1	181.880	yel-brn orth cry	670	1800 dec	3.35	0.07^{25}	s conc acid, alk; i EtOH
2545	Vanadyl bromide	VOBr	13520-88-2	146.845	viol cry	480 dec				
2546	Vanadyl chloride	VOCl	13520-87-1	102.394	brn orth cry		127	1.72		
2547	Vanadyl dibromide	$VOBr_2$	13520-89-3	226.749	yel-brn cry	180 dec				

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2548	Vanadyl dichloride	$VOCl_2$	10213-09-9	137.846	grn hyg cry	380 dec		2.88		reac H_2O; s EtOH
2549	Vanadyl difluoride	VOF_2	13814-83-0	104.938	yel cry					
2550	Vanadyl selenite hydrate	$VOSeO_3 \cdot H_2O$	133578-89-9	211.92	grn tricl plates			3.506		
2551	Vanadyl sulfate dihydrate	$VOSO_4 \cdot 2H_2O$	27774-13-6	199.036	blue cry powder					s H_2O
2552	Vanadyl tribromide	$VOBr_3$	13520-90-6	306.653	deep red liq		180 dec			reac H_2O
2553	Vanadyl trichloride	$VOCl_3$	7727-18-6	173.299	fuming red liq	-79	127	1.829		reac H_2O; s MeOH, eth, ace
2554	Vanadyl trifluoride	VOF_3	13709-31-4	123.936	yel hyg powder	300	480	2.459		reac H_2O
2555	Water	H_2O	7732-18-5	18.015	col liq	0.00	100.0	0.9970		s EtOH, MeOH, ace
2556	Xenon	Xe	7440-63-3	131.29	col gas	-111.745 tp (81.6 kPa)	-108.09	5.366 g/L		sl H_2O
2557	Xenon trioxide	XeO_3	13776-58-4	179.29	col orth cry	exp ≈25		4.55		s H_2O
2558	Xenon tetroxide	XeO_4	12340-14-6	195.29	yel solid; exp	-35.9	≈0 dec			
2559	Xenon difluoride	XeF_2	13709-36-9	169.29	col tetr cry	129.03 tp	114.35 sp	4.32		sl H_2O
2560	Xenon tetrafluoride	XeF_4	13709-61-0	207.28	col monocl cry	117.10 tp	115.75 sp	4.04		reac H_2O
2561	Xenon hexafluoride	XeF_6	13693-09-9	245.28	col monocl cry	49.5	75.6	3.56		reac H_2O
2562	Xenon dioxydifluoride	XeO_2F_2	13875-06-4	201.29	col orth cry	30.8 exp		4.10		
2563	Xenon oxytetrafluoride	$XeOF_4$	13774-85-1	223.28	col liq	-46.2		3.17^{0}		reac H_2O
2564	Xenon fluoride hexafluororuthenate	$XeFRuF_6$	22527-13-5	365.35	yel-grn monocl cry	110		3.78		
2565	Xenon fluoride undecafluoroantimonate	$XeFSb_2F_{11}$	15364-10-0	602.79	yel monocl cry	63		3.69		
2566	Xenon fluoride hexafluoroarsenate	$Xe_2F_3AsF_6$	50432-32-1	508.49	yel-grn monocl cry	99		3.62		reac H_2O
2567	Xenon fluoride hexafluoroantimonate	XeF_3SbF_6	39797-63-2	424.04	yel-grn monocl cry	≈110		3.92		
2568	Xenon trifluoride undecafluoroantimonate	$XeF_3Sb_2F_{11}$	35718-37-7	640.79	yel-grn tricl cry	82		3.98		
2569	Xenon pentafluoride hexafluoroarsenate	XeF_5AsF_6	20328-94-3	415.19	wh monocl cry	130.5		3.51		
2570	Xenon pentafluoride hexafluororuthenate	XeF_5RuF_6	39796-98-0	441.34	grn orth cry	152		3.79		
2571	Ytterbium	Yb	7440-64-4	173.04	silv metal; cub	819	1196	6.90		s dil acid
2572	Ytterbium silicide	$YbSi_2$	12039-89-3	229.21	hex cry			7.54		
2573	Ytterbium(II) bromide	$YbBr_2$	25502-05-0	332.85	yel cry	673				reac H_2O
2574	Ytterbium(II) chloride	$YbCl_2$	13874-77-6	243.95	grn cry	721		5.27		reac H_2O
2575	Ytterbium(II) iodide	YbI_2	19357-86-9	426.85	blk cry	772				reac H_2O
2576	Ytterbium(III) chloride	$YbCl_3$	10361-91-8	279.40	wh hyg powder	875				s H_2O
2577	Ytterbium(III) chloride hexahydrate	$YbCl_3 \cdot 6H_2O$	19423-87-1	387.49	grn hyg cry	150 dec		2.57		vs H_2O
2578	Ytterbium(III) fluoride	YbF_3	13760-80-0	230.04	wh cry	1157		8.2		i H_2O
2579	Ytterbium(III) nitrate	$Yb(NO_3)_3$	13768-67-7	359.06	col hyg solid				239^{25}	s EtOH
2580	Ytterbium(III) oxide	Yb_2O_3	1314-37-0	394.08	col cub cry	2355	4070	9.2		s dil acid
2581	Ytterbium(III) sulfate octahydrate	$Yb_2(SO_4)_3 \cdot 8H_2O$	10034-98-7	778.39	col cry			3.3	38.4^{20}	
2582	Yttrium	Y	7440-65-5	88.906	silv metal; hex	1522	3345	4.47		reac H_2O; s dil acid
2583	Yttrium aluminum oxide	$Y_3Al_5O_{12}$	12005-21-9	593.619	grn cub cry			≈4.5		
2584	Yttrium antimonide	YSb	12186-97-9	210.666	cub cry	2310		5.97		
2585	Yttrium arsenide	YAs	12255-48-0	163.828	cub cry			5.59		
2586	Yttrium boride	YB_6	12008-32-1	153.772	refrac solid	2600		3.72		
2587	Yttrium bromide	YBr_3	13469-98-2	328.618	col hyg cry	904			83.3^{30}	
2588	Yttrium carbide	YC_2	12071-35-1	112.927	refrac solid	≈2400		4.13		
2589	Yttrium carbonate trihydrate	$Y_2(CO_3)_3 \cdot 3H_2O$	5970-44-5	411.885	red-brn powder					i H_2O; s dil acid
2590	Yttrium chloride	YCl_3	10361-92-9	195.264	wh monocl cry; hyg	721		2.61	75.1^{20}	
2591	Yttrium fluoride	YF_3	13709-49-4	145.901	wh hyg powder	≈1150		4.0		i H_2O
2592	Yttrium nitrate	$Y(NO_3)_3$	10361-93-0	274.921	wh hyg solid				149^{25}	s EtOH
2593	Yttrium nitrate tetrahydrate	$Y(NO_3)_3 \cdot 4H_2O$	13773-69-8	346.982	red-wh prisms			2.68	149^{25}	
2594	Yttrium nitrate hexahydrate	$Y(NO_3)_3 \cdot 6H_2O$	13494-98-9	383.012	hyg cry				149^{25}	
2595	Yttrium oxide	Y_2O_3	1314-36-9	225.810	wh cry; cub	2438		5.03		s dil acid
2596	Yttrium phosphide	YP	12294-01-8	119.880	cub cry			≈4.4		
2597	Yttrium sulfate octahydrate	$Y_2(SO_4)_3 \cdot 8H_2O$	7446-33-5	610.125	red monocl cry			2.6	7.47^{16}	
2598	Yttrium sulfide	Y_2S_3	12039-19-9	274.010	yel cub cry	1925		3.87		
2599	Zinc	Zn	7440-66-6	65.39	blue-wh metal; hex	419.53	907	7.14		s acid, alk
2600	Zinc acetate dihydrate	$Zn(C_2H_3O_2)_2 \cdot 2H_2O$	5970-45-6	219.51	wh powder	237 dec		1.735	30.0^{20}	s EtOH

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2601	Zinc ammonium sulfate	$Zn(NH_4)_2(SO_4)_2$	7783-24-6	293.59	wh cry				9.2^{20}	
2602	Zinc antimonide	ZnSb	12039-35-9	187.15	silv-wh orth cry	565		6.33		reac H_2O
2603	Zinc arsenate	$Zn_3(AsO_4)_2$	13464-44-3	474.01	wh powder				0.000078^{20}	s acid, alk
2604	Zinc arsenate octahydrate	$Zn_3(AsO_4)_2 \cdot 8H_2O$	13464-45-4	618.13	wh monocl cry			3.33	0.000078^{20}	s acid, alk
2605	Zinc arsenide	Zn_3As_2	12006-40-5	346.01	pow	1015		5.528		
2606	Zinc arsenite	$Zn(AsO_2)_2$	10326-24-6	279.23	col powder					i H_2O; s acid
2607	Zinc borate	$3ZnO \cdot 2B_2O_3$	27043-84-1	383.41	wh amorp powder			3.64		sl H_2O; s dil acid
2608	Zinc borate hemiheptahydrate	$2ZnO \cdot 3B_2O_3 \cdot 3.5H_2O$	12513-27-8	434.69	wh cry	980		4.22		i H_2O
2609	Zinc borate pentahydrate	$2ZnO \cdot 3B_2O_3 \cdot 5H_2O$	12536-65-1	461.72	wh pow			3.64	0.007^{25}	sl HCl
2610	Zinc bromate hexahydrate	$Zn(BrO_3)_2 \cdot 6H_2O$	13517-27-6	429.29	wh hyg solid	100		2.57		vs H_2O
2611	Zinc bromide	$ZnBr_2$	7699-45-8	225.20	wh hex cry; hyg	394	697	4.5	488^{25}	vs EtOH; s eth
2612	Zinc caprylate	$Zn(C_8H_{15}O_2)_2$	557-09-5	351.80	wh hyg cry	136				sl H_2O
2613	Zinc carbonate	$ZnCO_3$	3486-35-9	125.40	wh rhomb cry	140 dec		4.4	0.000091^{20}	s dil acid, alk
2614	Zinc carbonate hydroxide	$3Zn(OH)_2 \cdot 2ZnCO_3$	12070-69-8	549.01	wh pow					
2615	Zinc chlorate	$Zn(ClO_3)_2$	10361-95-2	232.29	yel hyg cry	60 dec		2.15	200^{20}	
2616	Zinc chloride	$ZnCl_2$	7646-85-7	136.29	wh hyg cry	290	732	2.907	408^{25}	s EtOH, ace
2617	Zinc chromate	$ZnCrO_4$	13530-65-9	181.38	yel prisms	316		3.40	3.08	s acid; i ace
2618	Zinc chromite	$ZnCr_2O_4$	12018-19-8	233.38	grn cub cry			5.29		
2619	Zinc citrate dihydrate	$Zn_3(C_6H_5O_7)_2 \cdot 2H_2O$	546-46-3	610.40	col powder					sl H_2O; s dil acid, alk
2620	Zinc cyanide	$Zn(CN)_2$	557-21-1	117.42	wh powder			1.852	0.00047^{20}	reac acid
2621	Zinc dithionate	ZnS_2O_4	7779-86-4	193.52	wh amorp solid	200 dec			40^{20}	
2622	Zinc fluoride	ZnF_2	7783-49-5	103.39	wh tetr needles; hyg	872	1500	4.9	1.55^{25}	
2623	Zinc fluoride tetrahydrate	$ZnF_2 \cdot 4H_2O$	13986-18-0	175.45	wh orth cry			2.30	1.55^{25}	
2624	Zinc fluoroborate hexahydrate	$Zn(BF_4)_2 \cdot 6H_2O$	27860-83-9	347.09	hex cry			2.12		vs H_2O; s EtOH
2625	Zinc formate dihydrate	$Zn(CHO_2)_2 \cdot 2H_2O$	5970-62-7	191.46	wh cry			2.207	5.2^{20}	i EtOH
2626	Zinc hexafluorosilicate hexahydrate	$ZnSiF_6 \cdot 6H_2O$	16871-71-9	315.56	wh cry					s H_2O
2627	Zinc hydroxide	$Zn(OH)_2$	20427-58-1	99.41	col orth cry	125 dec		3.05	0.000042^{20}	
2628	Zinc iodate	$Zn(IO_3)_2$	7790-37-6	415.20	wh cry powder				0.64^{25}	
2629	Zinc iodide	ZnI_2	10139-47-6	319.20	wh hyg cry	446	625	4.74	438^{25}	s EtOH, eth
2630	Zinc laurate	$Zn(C_{12}H_{23}O_2)_2$	2452-01-9	464.01	wh powder	128				sl H_2O
2631	Zinc molybdate	$ZnMoO_4$	13767-32-3	225.33	wh tetr cry	>700		4.3		i H_2O
2632	Zinc nitrate	$Zn(NO_3)_2$	7779-88-6	189.40	wh powder				120^{25}	
2633	Zinc nitrate hexahydrate	$Zn(NO_3)_2 \cdot 6H_2O$	10196-18-6	297.49	col orth cry	36 dec		2.067	120^{25}	vs EtOH
2634	Zinc nitride	Zn_3N_2	1313-49-1	224.18	blue-gray cub cry	700 dec		6.22		i H_2O
2635	Zinc nitrite	$Zn(NO_2)_2$	10102-02-0	157.40	hyg solid					reac H_2O
2636	Zinc oleate	$Zn(C_{18}H_{33}O_2)_2$	557-07-3	628.30	wh powder	70 dec				i H_2O; s EtOH, eth, bz
2637	Zinc oxalate	ZnC_2O_4	547-68-2	153.41	wh pwd				0.0026^{25}	
2638	Zinc oxalate dihydrate	$ZnC_2O_4 \cdot 2H_2O$	4255-07-6	189.44	wh powder	100 dec		2.56	0.0026^{25}	s dil acid
2639	Zinc oxide	ZnO	1314-13-2	81.39	wh powder; hex	1974		5.6		i H_2O; s dil acid
2640	Zinc 2,4-pentanedioate	$Zn(CH_3COCHCOCH_3)_2$	14024-63-6	263.61	cry	137 dec				sl H_2O; s EtOH
2641	Zinc perchlorate hexahydrate	$Zn(ClO_4)_2 \cdot 6H_2O$	10025-64-6	372.38	wh cub cry; hyg	106 dec		2.2	121.3^{25}	s EtOH
2642	Zinc permanganate hexahydrate	$Zn(MnO_4)_2 \cdot 6H_2O$	23414-72-4	411.35	blk orth cry; hyg			2.45		s H_2O; reac EtOH
2643	Zinc peroxide	ZnO_2	1314-22-3	97.39	yel-wh powder	>150 dec	212 exp	1.57		i H_2O; reac acid, EtOH, ace
2644	Zinc phosphate	$Zn_3(PO_4)_2$	7779-90-0	386.11	wh monocl cry	900		4.0		i H_2O
2645	Zinc phosphate tetrahydrate	$Zn_3(PO_4)_2 \cdot 4H_2O$	7543-51-3	458.17	col orth cry			3.04		i H_2O, EtOH; s dil acid, alk
2646	Zinc phosphide	Zn_3P_2	1314-84-7	258.12	gray tetr cry	1160		4.55		i H_2O, EtOH; reac acid; s bz
2647	Zinc pyrophosphate	$Zn_2P_2O_7$	7446-26-6	304.72	wh cry powder			3.75		i H_2O; s dil acid
2648	Zinc selenate pentahydrate	$ZnSeO_4 \cdot 5H_2O$	13597-54-1	298.42	tricl cry	50 dec		2.59	63.4^{25}	
2649	Zinc selenide	ZnSe	1315-09-9	144.35	yel-red cub cry	>1100	subl	5.65		i H_2O; s dil acid
2650	Zinc orthosilicate	Zn_2SiO_4	13597-65-4	222.86	wh hex cry	1509		4.1		i H_2O, dil acid
2651	Zinc selenite	$ZnSeO_3$	13597-46-1	192.35	wh pow					
2652	Zinc stearate	$Zn(C_{18}H_{35}O_2)_2$	557-05-1	632.33	wh powder	130		1.095		i H_2O, EtOH, eth; s bz
2653	Zinc sulfate	$ZnSO_4$	7733-02-0	161.45	col orth cry	680 dec		3.8	57.7^{25}	
2654	Zinc sulfate monohydrate	$ZnSO_4 \cdot H_2O$	7446-19-7	179.47	wh monocl cry	238 dec		3.20	57.7^{25}	i EtOH
2655	Zinc sulfate heptahydrate	$ZnSO_4 \cdot 7H_2O$	7446-20-0	287.56	col orth cry	100 dec		1.97	57.7^{25}	i EtOH
2656	Zinc sulfide (sphalerite)	ZnS	1314-98-3	97.46	gray-wh cub cry	1700		4.04		i H_2O, EtOH; s dil acid
2657	Zinc sulfide (wurtzite)	ZnS	1314-98-3	97.46	wh hex cry	1700		4.09		i H_2O; s dil acid

No.	Name	Formula	CAS Reg No.	Mol. weight	Physical form	mp/°C	bp/°C	Density g cm^{-3}	Solubility g/100 g H_2O	Qualitative solubility
2658	Zinc sulfite dihydrate	$ZnSO_3 \cdot 2H_2O$	7488-52-0	181.49	wh powder	200 dec			0.224^{25}	i EtOH
2659	Zinc telluride	ZnTe	1315-11-3	192.99	red cub cry	1239		5.9		i H_2O
2660	Zinc thiocyanate	$Zn(SCN)_2$	557-42-6	181.56	wh hyg cry					sl H_2O; s EtOH
2661	Zirconium	Zr	7440-67-7	91.224	gray-wh metal; hex	1854	4409	6.52		s hot conc acid
2662	Zirconium boride	ZrB_2	12045-64-6	112.846	gray refrac solid; hex	3245		6.17		
2663	Zirconium carbide	ZrC	12020-14-3	103.235	gray refrac solid; cub	3532		6.73		s HF
2664	Zirconium(II) chloride	$ZrCl_2$	13762-26-0	162.129	blk cry	772 dec		3.16		reac H_2O
2665	Zirconium(II) hydride	ZrH_2	7704-99-6	93.240	gray tetr cry	800 dec		5.6		i H_2O
2666	Zirconium(IV) bromide	$ZrBr_4$	13777-25-8	410.840	wh cub cry	450 tp	360 sp	3.98		
2667	Zirconium(IV) chloride	$ZrCl_4$	10026-11-6	233.035	wh monocl cry; hyg	437 tp	331 sp	2.80		reac H_2O; s EtOH, eth
2668	Zirconium(IV) fluoride	ZrF_4	7783-64-4	167.218	wh monocl cry	932 tp	912 sp	4.43	1.5^{25}	
2669	Zirconium(IV) hydroxide	$Zr(OH)_4$	14475-63-9	159.254	wh amorp powder	dec		3.25		i H_2O; s acid
2670	Zirconium(IV) iodide	ZrI_4	13986-26-0	598.842	oran cub cry; hyg	499 tp	431 sp	4.85		vs H_2O
2671	Zirconium(IV) nitrate pentahydrate	$Zr(NO_3)_4 \cdot 5H_2O$	13746-89-9	429.320	wh hyg cry	100 dec				vs H_2O; s EtOH
2672	Zirconium(IV) oxide	ZrO_2	1314-23-4	123.223	wh amorp powder	2709		5.68		i H_2O; sl acid
2673	Zirconium(IV) orthosilicate	$ZrSiO_4$	10101-52-7	183.308	wh tetr cry	1540 dec		4.6		i H_2O, acid
2674	Zirconium(IV) sulfate	$Zr(SO_4)_2$	14644-61-2	283.351	wh hyg cry	410 dec		3.22		s H_2O; sl EtOH
2675	Zirconium(IV) sulfate tetrahydrate	$Zr(SO_4)_2 \cdot 4H_2O$	7446-31-3	355.413	wh tetr cry	100 dec		2.80		vs H_2O
2676	Zirconium(IV) sulfide	ZrS_2	12039-15-5	155.356	red-brn hex cry	1480		3.82		i H_2O
2677	Zirconium nitride	ZrN	25658-42-8	105.231	yel cub cry	2960		7.09		s conc HF; sl dil acid
2678	Zirconium phosphide	ZrP_2	12037-80-8	153.172	orth cry			≈5.1		
2679	Zirconium silicide	$ZrSi_2$	12039-90-6	147.395	gray powder	1620		4.88		i H_2O, aqua regia; s HF
2680	Zirconyl chloride	$ZrOCl_2$	7699-43-6	178.128	wh solid	250 dec				s H_2O, EtOH
2681	Zirconyl chloride octahydrate	$ZrOCl_2 \cdot 8H_2O$	13520-92-8	322.251	tetr cry	400 dec		1.91		vs H_2O, EtOH

PHYSICAL PROPERTIES OF THE RARE EARTH METALS

K.A. Gschneidner, Jr.

TABLE 1. Data for the Trivalent Ions of the Rare Earth Elements

				Electronic configuration for R^{3+}				
Rare earth	**Symbol**	**Atomic no.**	**Atomic wt.[a]**	**No. 4f electrons**	***S***	***L***	***J***	**Spectroscopic ground state symbol**
Scandium	Sc	21	44.955910	0	—	—	—	—
Yttrium	Y	39	88.90585	0	—	—	—	—
Lanthanum	La	57	138.9055	0	—	—	—	—
Cerium	Ce	58	140.115	1	1/2	3	5/2	$^2F_{5/2}$
Praseodymium	Pr	59	140.90765	2	1	5	4	$^3H_4$
Neodymium	Nd	60	144.24	3	3/2	6	9/2	$^4I_{9/2}$
Promethium	Pm	61	(145)	4	2	6	4	$^5I_4$
Samarium	Sm	62	150.36	5	5/2	5	5/2	$^6H_{5/2}$
Europium	Eu	63	151.965	6	3	3	0	$^7F_0$
Gadolinium	Gd	64	157.25	7	7/2	0	7/2	$^8S_{7/2}$
Terbium	Tb	65	158.92534	8	3	3	6	$^7F_6$
Dysprosium	Dy	66	162.50	9	5/2	5	15/2	$^6H_{15/2}$
Holmium	Ho	67	164.93032	10	2	6	8	$^5I_8$
Erbium	Er	68	167.26	11	3/2	6	15/2	$^4I_{15/2}$
Thulium	Tm	69	168.93421	12	1	5	6	$^3H_6$
Ytterbium	Yb	70	173.04	13	1/2	3	7/2	$^2F_{7/2}$
Lutetium	Lu	71	174.967	14	—	—	—	—

Note: For additional information, see Goldschmidt, Z.B., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978; DeLaeter, J.R., and Heumann, K.G., *J. Phys. Chem. Ref. Data,* 20, 1313 , 1991; *Pure Appl. Chem.,* 66, 2423, 1994.

[a] 1993 standard atomic weights.

TABLE 2. Crystallographic Data for the Rare Earth Metals at 24°C (297 K) or Below

Rare earth metal	**Crystal structure[a]**	**Lattice constants (Å)**			**Metallic radius CN = 12 (Å)**	**Atomic volume (cm^3/mol)**	**Density (g/cm^3)**
		a_o	b_o	c_o			
αSc	hcp	3.3088	—	5.2680	1.6406	15.039	2.989
αY	hcp	3.6482	—	5.7318	1.8012	19.893	4.469
αLa	dhcp	3.7740	—	12.171	1.8791	22.602	6.146
αCe[b]	fcc	4.85[b]	—	—	1.72[b]	17.2[b]	8.16[b]
βCe	dhcp	3.6810	—	11.857	1.8321	20.947	6.689
γCe[c]	fcc	5.1610	—	—	1.8247	20.696	6.770
αPr	dhcp	3.6721	—	11.8326	1.8279	20.803	6.773
αNd	dhcp	3.6582	—	11.7966	1.8214	20.583	7.008
αPm	dhcp	3.65	—	11.65	1.811	20.24	7.264
αSm	rhomb[d]	3.6290[d]	—	26.207	1.8041	20.000	7.520
Eu	bcc	4.5827	—	—	2.0418	28.979	5.244
αGd	hcp	3.6336	—	5.7810	1.8013	19.903	7.901
α′Tb[e]	ortho	3.605[e]	6.244[e]	5.706[e]	1.784[e]	19.34[e]	8.219[e]
αTb	hcp	3.6055	—	5.6966	1.7833	19.310	8.230
α′Dy[f]	ortho	3.595[f]	6.184[f]	5.678[f]	1.774[f]	19.00[f]	8.551[f]
αDy	hcp	3.5915	—	5.6501	1.7740	19.004	8.551
Ho	hcp	3.5778	—	5.6178	1.7661	18.752	8.795
Er	hcp	3.5592	—	5.5850	1.7566	18.449	9.066
Tm	hcp	3.5375	—	5.5540	1.7462	18.124	9.321
αYb[g]	hcp	3.8799[g]	—	6.3859[g]	1.9451[g]	25.067[g]	6.903[g]
βYb	fcc	5.4848	—	—	1.9392	24.841	6.966
Lu	hcp	3.5052	—	5.5494	1.7349	17.779	9.841

Note: For additional information, see Gschneidner, K.A., Jr. and Calderwood, F.W., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 8, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1986; Gschneidner, K.A., Jr., Pecharsky, V.K., Cho, Jaephil and Martin, S.W., *Scripta Mater.*, 1996, to be published.

[a] hcp = hexagonal close-packed; $P6_3/mmc$, hP2, A3, Mg-type; dhcp = double-c hexagonal close-packed; $P6_3/mmc$, hP4, A3´, αLa-type; fcc = face-centered cubic; $Fm\bar{3}m$, cF4, A1, Cu-type; rhomb = rhombohedral; $R\bar{3}m$, hR3, αSm-type; bcc = body-centered cubic; $Im\bar{3}m$, cI2, A2, W-type; ortho = orthorhombic; Cmcm, oC4, α´ Dy-type.

[b] At 77 K (–196°C).

[c] Equilibrium room temperature (standard state) phase.

[d] Rhombohedral is the primitive cell. Lattice parameters given are for the nonprimitive hexagonal cell.

[d] At 220 K (–53°C).

[f] At 86 K (–187°C).

[g] At 23°C.

TABLE 3. Crystallographic Data for Rare Earth Metals at High Temperature

Rare earth metal	Structure	Lattice parameter (Å)	Temp. (°C)	Metallic radius CN = 8 (Å)	Metallic radius CN = 12 (Å)	Atomic volume (cm^3/mol)	Density (g/cm^3)
βSc	bcc	3.73 (est.)	1337	1.62	1.66	15.6	2.88
βY	bcc	4.10[a]	1478	1.78	1.83	20.8	4.28
βLa	fcc	5.303	325	—	1.875	22.45	6.187
γLa	bcc	4.26	887	1.84	1.90	23.3	5.97
δCe	bcc	4.12	757	1.78	1.84	21.1	6.65
βPr	bcc	4.13	821	1.79	1.84	21.2	6.64
βNd	bcc	4.13	883	1.79	1.84	21.2	6.80
βPm	bcc	4.10 (est.)	890	1.78	1.83	20.8	6.99
βSm	hcp	a = 3.6630 c = 5.8448	450[b]	—	1.8176	20.450	7.353
γSm	bcc	4.10 (est.)	922	1.77	1.82	20.8	7.25
βGd	bcc	4.06	1265	1.76	1.81	20.2	7.80
βTb	bcc	4.07[a]	1289	1.76	1.81	20.3	7.82
βDy	bcc	4.03[a]	1381	1.75	1.80	19.7	8.23
γYb	bcc	4.44	763[c]	1.92	1.98	26.4	6.57

Note: The rare earths Eu, Ho, Er, Tm, and Lu are monomorphic. For additional information, see Gschneidner, K.A., Jr. and Calderwood, F.W., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 8, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1986, 1.

[a] Determined by extrapolation to 0% solute of a vs. composition data for R-Mg alloys at 24°C and corrected for thermal expansion to temperature given.

[b] The hcp phase was stabilized by impurities and the temperature of measurement was below the equilibrium transition temperature (see Table 4).

[c] The bcc phase was stabilized by impurities and the temperature of measurement was below the equilibrium transition temperature (see Table 4).

TABLE 4. High Temperature Transition Temperatures and Melting Point of Rare Earth Metals

Rare earth metal	Transition I (α – β)[a] Temp. (°C)	Transition I (α – β)[a] Phases	Transition II (β – γ)[a] Temp. (C°)	Transition II (β – γ)[a] Phases	Melting point (C°)
Sc	1337	hcp ⇌ bcc	—	—	1541
Y	1478	hcp ⇌ bcc	—	—	1522
La[b]	310	dhcp ⇌ fcc	865	fcc ⇌ bcc	918
Ce[c,d]	139	dhcp ⇌ fcc (β - γ)	726	fcc ⇌ bcc (γ - δ)	798
Pr	795	dhcp ⇌ bcc	—	—	931
Nd	863	dhcp ⇌ bcc	—	—	1021
Pm	890	dhcp ⇌ bcc	—	—	1042
Sm[e]	734	rhom ⇌ hcp	922	hcp ⇌ bcc	1074
Eu	—	—	—	—	822
Gd	1235	hcp ⇌ bcc	—	—	1313
Tb	1289	hcp ⇌ bcc	—	—	1356
Dy	1381	hcp ⇌ bcc	—	—	1412
Ho	—	—	—	—	1474
Er	—	—	—	—	1529
Tm	—	—	—	—	1545
Yb	795	fcc ⇌ bcc (β - γ)	—	—	819
Lu	—	—	—	—	1663

Note: For additional information, see Gschneidner, K.A., Jr. and Calderwood, F.W., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 8, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1986; Gschneidner, K.A., Jr., Pecharsky, V.K., Cho, Jaephil and Martin, S.W., *Scripta Mater.*, 34, 1717, 1996.

[a] For all the transformations listed, unless otherwise noted.

[b] On cooling, fcc → dhcp (β → α), 260°C.

[c] The β ⇌ γ equilibrium transition temperature is 10 ± 5°C.

[d] On cooling, fcc → dhcp (γ → β), –16°C.

[e] On cooling, hcp → rhomb (β → α), 727°C.

TABLE 5. Low Temperature Transition Temperatures of the Rare Earth Metals

Rare earth metal	Cooling Transformation	Cooling °C	Cooling K	Rare earth metal	Heating Transformation	Heating °C	Heating K
Ce	γ → β[a]	–16	257	Ce	α → β	–148	125
	γ → α	–172	101		α → β + γ	–104	169
	β → α	–228	45		β → γ[a]	139	412
Tb	α → α′	–53	220	Yb	α → β	7	280
Dy	α → α′	–187	86				
Yb	β → α	–13	260				

Note: For additional information, see Beaudry, B.J. and Gschneidner, K.A., Jr., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978, 173; Koskenmaki, D.C. and Gschneidner, K.A., Jr., 1978, in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978, 337; Gschneidner, K.A., Jr., Pecharsky, V.K., Cho, Jaephil and Martin, S.W., *Scripta Mater.*, 34, 1717, 1996.

[a] The β ⇌ γ equilibrium transition temperature is 10 ± 5°C (283 ± 5K).

TABLE 6. Heat Capacity, Standard Entropy, Heats of Transformation, and Fusion of the Rare Earth Metals

Rare earth metal	Heat capacity at 298 K (J/mol K)	Standard entropy $S°_{298}$ (J/mol K)	Heat of transformation (kJ/mol)				Heat of fusion (kJ/mol)
			trans. 1	ΔH_{tr}^{1}	trans. 2	ΔH_{tr}^{2}	
Sc	25.5	34.6	$\alpha \rightleftharpoons \beta$	4.00	—	—	14.1
Y	26.5	44.4	$\alpha \rightleftharpoons \beta$	4.99	—	—	11.4
La	27.1	56.9	$\alpha \rightleftharpoons \beta$	0.36	$\beta \rightleftharpoons \gamma$	3.12	6.20
Ce	26.9	72.0	$\beta \rightleftharpoons \gamma$	0.05	$\gamma \rightleftharpoons \delta$	2.99	5.46
Pr	27.2	73.2	$\alpha \rightleftharpoons \beta$	3.17	—	—	6.89
Nd	27.5	71.5	$\alpha \rightleftharpoons \beta$	3.03	—	—	7.14
Pm	27.3[a]	71.6[a]	$\alpha \rightleftharpoons \beta$	3.0[a]	—	—	7.7[a]
Sm	29.5	69.6	$\alpha \rightleftharpoons \beta$	0.2[a]	$\beta \rightleftharpoons \gamma$	3.11	8.62
Eu	27.7	77.8	—	—	—	—	9.21
Gd	37.0	68.1	$\alpha \rightleftharpoons \beta$	3.91	—	—	10.0
Tb	28.9	73.2	$\alpha \rightleftharpoons \beta$	5.02	—	—	10.79
Dy	27.7	75.6	$\alpha \rightleftharpoons \beta$	4.16	—	—	11.06
Ho	27.2	75.3	—	—	—	—	17.0[a]
Er	28.1	73.2	—	—	—	—	19.9
Tm	27.0	74.0	—	—	—	—	16.8
Yb	26.7	59.9	$\beta \rightleftharpoons \gamma$	1.75	—	—	7.66
Lu	26.9	51.0	—	—	—	—	22[a]

Note: For additional information, see Hultgren, R., Desai, P.D., Hawkins, D.T., Gleiser, M., Kelley, K.K., and Wagman, D.D., *Selected Values of the Thermodynamic Properties of the Elements,* ASM International, Metals Park, Ohio, 1973; Wagman, D.D., Evans, W.H., Parker, V.B., Schumm, R.H., Halow, I., Bailey, S.M., Churney, K.L., and Nuttall, R.L., *The NBS Tables of Chemical Thermodynamic Properties, J. Phys. Chem. Ref. Data*, Vol. 11, Suppl 2, 1982; Amitin, E.B., Bessergenev, W.G., Kovalevskaya, Yu. A., and Paukov, I.E., *J. Chem. Thermodyn.*, 15, 181, 1983; Amitin, E.B., Bessergenev, W.G., Kovalevskaya, Yu. A., and Paukov, I.E., *J. Chem. Thermodyn.*, 15, 181, 1983.

[a] Estimated.

TABLE 7. Vapor Pressures, Boiling Points, and Heats of Sublimation of Rare Earth Metals

Rare earth metal	Temperature in °C[a] for a vapor pressure of				Boiling point[a] (°C)	Heat of sublimation at 25°C (kJ/mol)
	10^{-8} atm (0.001 Pa)	10^{-6} atm (0.101 Pa)	10^{-4} atm (10.1Pa)	10^{-2} atm (1013 Pa)		
Sc	1036	1243	1533	1999	2836	377.8
Y	1222	1460	1812	2360	3345	424.7
La	1301	1566	1938	2506	3464	431.0
Ce	1290	1554	1926	2487	3443	422.6
Pr	1083	1333	1701	2305	3520	355.6
Nd	955	1175	1500	2029	3074	327.6
Pm	—	—	—	—	3000[b]	348[b]
Sm	508	642	835	1150	1794	206.7
Eu	399	515	685	964	1529	175.3
Gd	1167	1408	1760	2306	3273	397.5
Tb	1124	1354	1698	2237	3230	388.7
Dy	804	988	1252	1685	2567	290.4
Ho	845	1036	1313	1771	2700	300.8
Er	908	1113	1405	1896	2868	317.1
Tm	599	748	964	1300	1950	232.2
Yb	301	400	541	776	1196	152.1
Lu	1241	1483	1832	2387	3402	427.6

Note: For additional information, see Hultgren, R., Desai, P.D., Hawkins, D.T., Gleiser, M., Kelley, K.K., and Wagman, D.D., *Selected Values of the Thermodynamic Properties of the Elements,* ASM International, Metals Park, Ohio, 1973; Beaudry, B.J. and Gschneidner, K.A., Jr., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978, 173.

[a] International Temperature Scale of 1990 (ITS-90) values.

[b] Estimated.

TABLE 8. Magnetic Properties of the Rare Earth Metals

Rare earth metal	$\chi_A \times 10^6$ at 298 K (emu/mol)	Effective magnetic moment: Paramagnetic at ~298 K: Theory[a]	Paramagnetic at ~298 K: Obs.	Ferromagnetic at ~0 K: Theory[b]	Ferromagnetic at ~0 K: Obs.	Easy axis	Néel temp. T_N (K): Hex sites	Néel temp. T_N (K): Cubic sites	Curie temp. T_C (K)	θ_p (K): ‖c	θ_p (K): ⊥c	θ_p (K): Polycryst. or avg.
αSc	295.2	—	—	—	—	—	—	—	—	—	—	—
αY	187.7	—	—	—	—	—	—	—	—	—	—	—
αLa	95.9	—	—	—	—	—	—	—	—	—	—	—
βLa	105	—	—	—	—	—	—	—	—	—	—	—
γCe	2,270	2.54	2.52	2.14	—	—	—	14.4	—	—	—	–50
βCe	2,500	2.54	2.61	2.14	—	—	13.7	12.5	—	—	—	–41
αPr	5,530	3.58	3.56	3.20	2.7[c]	**a**	0.03	—	—	—	—	0
αNd	5,930	3.62	3.45	3.27	2.2[c]	**b**	19.9	7.5	—	0	5	3.3
αPm	—	2.68	—	2.40	—	—	—	—	—	—	—	—
αSm	1,278[d]	0.85	1.74	0.71	0.5[c]	**a**	109	14.0	—	—	—	—
Eu	30,900	7.94	8.48	7.0	5.9	<110>	—	90.4	—	—	—	100
αGd	185,000[e]	7.94	7.98	7.0	7.63	30° to **c**	—	—	293.4	317	317	317
αTb	170,000	9.72	9.77	—	—	—	230.0	—	—	195	239	224
α′Tb	—	—	—	9.0	9.34	**b**	—	—	219.5	—	—	—
αDy	98,000	10.64	10.83	—	—	—	180.2	—	—	121	169	153
α′Dy	—	—	—	10.0	10.33	**a**	—	—	90.5[g]	—	—	—
Ho	72,900	10.60	11.2	10.0	10.34	**b**	132	—	19.5	73.0	88.0	83.0
Er	48,000	9.58	9.9	9.0	9.1	30° to **c**	85	—	18.7	61.7	32.5	42.2
Tm	24,700	7.56	7.61	7.0	7.14	**c**	58	—	32.0	41.0	–17.0	2.3
βYb	67[d]	—	—	—	—	—	—	—	—	—	—	—
Lu	182.9	—	—	—	—	—	—	—	—	—	—	—

Note: For additional information, see McEwen, K.A., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978, 411; Legvold, S., in *Ferromagnetic Materials,* Vol. 1, Wohlfarth, E.P., Ed., North-Holland Physics, Amsterdam, 1980, 183; Pecharsky, V.K., Gschneidner, K.A., Jr. and Fort, D., *Phys. Rev. B,* 47, 5063, 1993; Pecharsky, V.K., Gschneidner, K.A., Jr. and Fort, D., 1996, to be published; Steward, A.M. and Collocott, S.J., *J. Phys.: Condens. Matter,* 1, 677, 1988.

[a] $g[J(J+1)]^{1/2}$.
[b] gJ.
[c] At 38 T and 4.2 K.
[d] At 290 K.
[e] At 350 K.
[g] On cooling T_C = 89.6 K and on warming T_C = 91.5 K.

TABLE 9. Room Temperature Coefficient of Thermal Expansion, Thermal Conductivity, Electrical Resistance, and Hall Coefficient

Rare earth metal	Expansion ($\alpha_i \times 10^6$) ($°C^{-1}$): α_a	α_c	α_{poly}	Thermal conductivity (W/cm K)	Electrical resistance (μΩ·cm): ρ_a	ρ_c	ρ_{poly}	Hall coefficient ($R_i \times 10^{12}$) (V·cm/A·Oe): R_a	R_c	R_{poly}
αSc	7.6	15.3	10.2	0.158	70.9	26.9	56.2[a]	—	—	–0.13
αY	6.0	19.7	10.6	0.172	72.5	35.5	59.6	–0.27	–1.6	—
aLa	4.5	27.2	12.1	0.134	—	—	61.5	—	—	–0.35
bCe	—	—	—	—	—	—	82.8	—	—	—
γCe	6.3	—	6.3	0.113	—	—	74.4	—	—	+1.81
αPr	4.5	11.2	6.7	0.125	—	—	70.0	—	—	+0.709
αNd	7.6	13.5	9.6	0.165	—	—	64.3	—	—	+0.971
αPm	9[b]	16[b]	11[b]	0.15[b]	—	—	75[b]	—	—	—
αSm	9.6	19.0	12.7	0.133	—	—	94.0	—	—	–0.21
Eu	35.0	—	35.0	0.139[b]	—	—	90.0	—	—	+24.4
αGd	9.1[c]	10.0[c]	9.4[c]	0.105	135.1	121.7	131.0	–10	–54	–4.48[d]
αTb	9.3	12.4	10.3	0.111	123.5	101.5	115.0	–1.0	–3.7	—
αDy	7.1	15.6	9.9	0.107	111.0	76.6	92.6	–0.3	–3.7	—
Ho	7.0	19.5	11.2	0.162	101.5	60.5	81.4	+0.2	–3.2	—
Er	7.9	20.9	12.2	0.145	94.5	60.3	86.0	+0.3	–3.6	—
Tm	8.8	22.2	13.3	0.169	88.0	47.2	67.6	—	—	–1.8
βYb	26.3	—	26.3	0.385	—	—	25.0	—	—	+3.77
Lu	4.8	20.0	9.9	0.164	76.6	34.7	58.2	+0.45	–2.6	–0.535

Note: For additional information, see Beaudry, B. J. and Gschneidner, K.A., Jr., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978, 173; McEwen, K.A., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978, 411.

[a] Calculated from single crystal values.
[b] Estimated.
[c] At 100°C.
[d] At 77°C.

TABLE 10. Electronic Specific Heat Constant (γ), Electron-Electron (Coulomb) Coupling Constant (μ*), Electron-Phonon Coupling Constant (λ), Debye Temperature at 0 K(θ_D), and Superconducting Transition Temperature

Rare earth metal	γ (mJ/mol·K²)	μ*	λ	θ_D (K) from Heat capacity	θ_D (K) from Elastic constants	Superconducting temperature (K)
αSc	10.334	0.16	0.30	345.3	—	0.050[a]
αY	7.878	0.15	0.30	244.4	258	1.3[b]
αLa	9.45	0.08	0.76	150	154	5.10
βLa	11.5	—	—	140	—	6.00
αCe	12.8	—	—	179	—	0.022[c]
αPr	20	—	1.07[d]	155[e]	153	—
αNd	f	—	0.86[d]	157[e]	163	—
αPm	—	—	—	159[e]	—	—
αSm	8.1 ± 1.5[g]	—	0.81[d]	162[e,f]	169	—
Eu	f	—	—	f	118	—
αGd	4.48	—	0.30	169	182	—
α′Tb	3.71	—	0.34[d]	169.6	177	—
α′Dy	4.9	—	0.32[d]	192	183	—
Ho	2.1	—	0.30[d]	175[e]	190	—
Er	8.7	—	0.33[d]	176.9	188	—
Tm	f	—	0.36[d]	179[e]	200	—
αYb	3.30	—	—	117.6	118	—
βYb	8.36	—	—	109	—	—
Lu	8.194	0.14	0.31	183.2	185	0.022[h]

Note: For additional information, see Sundström, L.J., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr., and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978, 379; Scott, T., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978, 591; Probst, C. and Wittig, J., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978, 749; Tsang, T.-W.E., Gschneidner, K.A., Jr., Schmidt, F.A., and Thome, D.K., *Phys. Rev.,* B, 31, 235, 1985; Collocott, S.J., Hill, R.W. and Stewart, A.M., *J. Phys. F,* 18, L223, 1988; Hill, R.W. and Gschneidner, K.A., Jr., *J. Phys. F,* 18, 2545, 1988; Skriver, H.L. and Mertig, I., *Phys. Rev. B,* 41, 6553, 1990. Collocott, S.J. and Stewart, A.M., *J. Phys.: Condens. Matter,* 4, 6743, 1992; Pecharsky, V.K., Gschneidner, K.A., Jr. and Fort, D., *Phys. Rev. B,* 47, 5063, 1993.

[a] At 18.6 GPa.
[b] At 11 GPa.
[c] At 2.2 GPa.
[d] Calculated value.
[e] Estimated.
[f] Heat capacity results have been reported, but the resultant γ and θ_D values are unreliable because of the presence of impurities and/or there was no reliable procedure or model to correct for the magnetic contribution to the heat capacity.
[g] Based on the values reported for the purer Sm sample (IV).
[h] At 4.5 GPa.

TABLE 11. Room Temperature Elastic Moduli and Mechanical Properties

Rare earth metal	Elastic moduli (GPa): Young's (elastic) modulus	Shear modulus	Bulk modulus	Poisson's ratio	Mechanical properties (MPa): Yield strength 0.2% offset	Ultimate tensile strength	Uniform elongation (%)	Reduction in area (%)	Recryst. temp. (°C)
Sc	74.4	29.1	56.6	0.279	173[a]	255[a]	5.0[a]	8.0[a]	550
Y	63.5	25.6	41.2	0.243	42	129	34.0	—	550
αLa	36.6	14.3	27.9	0.280	126[a]	130	7.9[a]	—	300
βCe	—	—	—	—	86	138	—	24.0	—
γCe	33.6	13.5	21.5	0.24	28	117	22.0	30.0	325
αPr	37.3	14.8	28.8	0.281	73	147	15.4	67.0	400
αNd	41.4	16.3	31.8	0.281	71	164	25.0	72.0	400
αPm	46[b]	18[b]	33[b]	0.28[b]	—	—	—	—	400[b]
αSm	49.7	19.5	37.8	0.274	68	156	17.0	29.5	440
Eu	18.2	7.9	8.3	0.152	—	—	—	—	300
αGd	54.8	21.8	37.9	0.259	15	118	37.0	56.0	500
αTb	55.7	22.1	38.7	0.261	—	—	—	—	500
αDy	61.4	24.7	40.5	0.247	43	139	30.0	30.0	550
Ho	64.8	26.3	40.2	0.231	—	—	—	—	520
Er	69.9	28.3	44.4	0.237	60	136	11.5	11.9	520
Tm	74.0	30.5	44.5	0.213	—	—	—	—	600
βYb	23.9	9.9	30.5	0.207	7	58	43.0	92.0	300
Lu	68.6	27.2	47.6	0.261	—	—	—	—	600

Note: For additional information, see Scott, T., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 1, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1978, 591.

[a] Value is questionable.
[b] Estimated.

TABLE 12. Liquid Metal Properties Near the Melting Point

Rare earth metal	Density (g/cm^3)	Surface tension (N/m)	Viscosity (centipoise)	Heat capacity (J/mol K)	Thermal conductivity (W/cm K)	Magnetic susceptibility $\chi \times 10^4$ (emu/mol)	Electrical resistivity (μΩ·cm)	ΔV (l→s)[a] (%)	Spectral emittance at λ = 645 nm	
									ε (%)	Temp.
Sc	2.80	0.954	—	44.2[b]	—	—	—	—	—	—
Y	4.24	0.871	—	43.1	—	—	—	—	36.8	1522–1647
La	5.96	0.718	2.65	34.3	0.238	1.20	133	−0.6	25.4	920–1287
Ce	6.68	0.706	3.20	37.7	0.210	9.37	130	+1.1	32.2	877–1547
Pr	6.59	0.707	2.85	43.0	0.251	17.3	139	−0.02	28.4	931–1537
Nd	6.72	0.687	—	48.8	0.195	18.7	151	−0.9	39.4	1021–1567
Pm	6.9[b]	0.680[b]	—	50[b]	—	—	160[b]	—	—	—
Sm	7.16	0.431	—	50.2[b]	—	18.3	182	−3.6	43.7	1075
Eu	4.87	0.264	—	38.1	—	97	242	−4.8	—	—
Gd	7.4	0.664	—	37.2	0.149	67	195	−2.0	34.2	1313–1600
Tb	7.65	0.669	—	46.5	—	82	193	−3.1	—	—
Dy	8.2	0.648	—	49.9	0.187	95	210	−4.5	29.7	1412–1437
Ho	8.34	0.650	—	43.9	—	88	221	−7.4	—	—
Er	8.6	0.637	—	38.7	—	69	226	−9.0	37.2	1529–1587
Tm	9.0[b]	—	—	41.4	—	41	235[b]	−6.9	—	—
Yb	6.21	0.320	2.67	36.8	—	—	113	−5.1	—	—
Lu	9.3	0.940	—	47.9[b]	—	—	224	−3.6	—	—

Note: For additional information, see Van Zytveld, J., in *Handbook on the Physics and Chemistry of Rare Earths,* Vol. 12, Gschneidner, K.A., Jr. and Eyring, L., Eds., North-Holland Physics, Amsterdam, 1989, 357. Stretz, L.A. and Bautista, R.G., in *Temperature, Its Measurement and Control in Science and Industry,* Vol. 4, part I, H.H. Plumb, Ed., Instrument Society of America, Pittsburgh, 1972, 489. King, T.S., Baria, D.N., and Bautista, R.G., *Met. Trans. B,* 7, 411, 1976; Baria, D.N., King, T.S., and Bautista, R.G., *Met. Trans. B,* 7, 577, 1976.

[a] Volume change on freezing.

[b] Estimated.

TABLE 13. Ionization Potentials (Electronvolts)

Rare earth	I Neutral atom	II Singly ionized	III Doubly ionized	IV Triply ionized	V Quadruply ionized
Sc	6.56144	12.79967	24.75666	73.4894	91.65
Y	6.217	12.24	20.52	60.597	77.0
La	5.5770	11.060	19.1773	49.95	61.6
Ce	5.5387	10.85	20.198	36.758	65.55
Pr	5.464	10.55	21.624	38.98	57.53
Nd	5.5250	10.73	22.1	40.41	—
Pm	5.554	10.90	22.3	41.1	—
Sm	5.6437	11.07	23.4	41.4	—
Eu	5.6704	11.241	24.92	42.7	—
Gd	6.1500	12.09	20.63	44.0	—
Tb	5.8639	11.52	21.91	39.79	—
Dy	5.9389	11.67	22.8	41.47	—
Ho	6.0216	11.80	22.84	42.5	—
Er	6.1078	11.93	22.74	42.7	—
Tm	6.18431	12.05	23.68	42.7	—
Yb	6.25416	12.1761	25.05	43.56	—
Lu	5.42585	13.9	20.9594	45.25	66.8

Note: For references, see the table "Ionization Potentials of Atoms and Atomic Ions" in Section 10.

TABLE 14. Effective Ionic Radii (Å)[A]

Rare earth ion	R^{2+}		R^{3+}			R^{4+}	
	CN = 6	CN = 8	CN = 6	CN = 8	CN = 12	CN = 6	CN = 8
Sc	—	—	0.745	0.87	1.116	—	—
Y	—	—	0.900	1.015	1.220	—	—
La	—	—	1.045	1.18	1.320	—	—
Ce	—	—	1.010	1.14	1.290	0.80	0.97
Pr	—	—	0.997	1.14	1.286	0.78	0.96
Nd	—	—	0.983	1.12	1.276	—	—
Pm	—	—	0.97	1.10	1.267	—	—
Sm	1.19	1.27	0.958	1.09	1.260	—	—
Eu	1.17	1.25	0.947	1.07	1.252	—	—
Gd	—	—	0.938	1.06	1.246	—	—
Tb	—	—	0.923	1.04	1.236	0.76	0.88
Dy	—	—	0.912	1.03	1.228	—	—
Ho	—	—	0.901	1.02	1.221	—	—
Er	—	—	0.890	1.00	1.214	—	—
Tm	—	—	0.880	0.99	1.207	—	—
Yb	1.00	1.07	0.868	0.98	1.199	—	—
Lu	—	—	0.861	0.97	1.194	—	—

Note: For additional information, see Shannon, R.D. and Prewitt, C.T., *Acta Cryst.,* 25, 925, 1969 and Shannon, R.D. and Prewitt, C.T., *Acta Cryst.,* 26, 1046, 1970.

[a] Radius of O^{2-} is 1.40 Å for a coordination number (CN) of 6.

MELTING, BOILING, TRIPLE, AND CRITICAL POINT TEMPERATURES OF THE ELEMENTS

This table summarizes the significant points on the phase diagrams for the elements for which data are available. Values are given for the solid-liquid-gas triple point t_{tp}, normal melting point t_m, normal boiling point t_b, and critical temperature t_c; all are on the ITS-90 scale. An "sp" notation indicates a sublimation point, where the vapor pressure of the solid phase reaches 101.325 kPa (1 atm). Transition temperatures between allotropic forms are included for several elements. The major data sources are listed below; values from Reference 1, which deals with reference points on the ITS-90 scale, were adopted when applicable.

References

1. Bedford, R. E., Bonnier, G., Maas, H., and Pavese, F., *Metrologia* 33, 133, 1996.
2. Dinsdale, A.T., "SGTE Data for Pure Elements," *CALPHAD*, 15, 317-425, 1991.
3. Chase, M.W., Davies, C.A., Downey, J.R., Frurip, D.J., McDonald, R.A., and Syverud, A.N., *JANAF Thermochemical Tables, Third Edition, J. Phys. Chem. Ref. Data*, Vol. 14, Suppl. 1, 1985.
4. Gurvich, L.V., Veyts, I.V., and Alcock, C.B., *Thermodynamic Properties of Individual Substances, Fourth Edition,* Hemisphere Publishing Corp., New York, 1989.
5. Greenwood, N. N., and Earnshaw, A., *Chemistry of the Elements, Second Edition*, Butterworth-Heinemann, Oxford, 1997.

Element	t_{tp}/°C	t_m/°C	t_b/°C	t_c/°C
Actinium		1051	3198	
Aluminum		660.32	2519	
Americium		1176	2011	
Antimony		630.628	1587	
Argon	-189.36 (69 kPa)		-185.847	-122.28
Arsenic (gray)	817 (3.70 MPa)		603 sp	1400
Astatine		302		
Barium		727	1897	
Berkelium (α form)		1050		
Berkelium (β form)		986		
Beryllium		1287	2471	
Bismuth		271.402	1564	
Boron		2075	4000	
Bromine		-7.2	58.8	315
Cadmium		321.069	767	
Calcium		842	1484	
Californium		900		
Carbon (graphite)	4489 (10.3 MPa)		3825 sp	
Carbon (diamond)		4440 (12.4 GPa)		
Cerium		798	3443	
Cesium		28.5	671	1665
Chlorine		-101.5	-34.04	143.8
Chromium		1907	2671	
Cobalt		1495	2927	
Copper		1084.62	2562	
Curium		1345	~3100	
Dysprosium		1412	2567	
Einsteinium		860		
Erbium		1529	2868	
Europium		822	1529	
Fermium		1527		
Fluorine	-219.67		-188.12	-129.02
Francium		27		
Gadolinium		1313	3273	
Gallium	29.7666		2204	
Germanium		938.25	2833	
Gold		1064.18	2856	
Hafnium		2233	4603	
Helium			-268.93	-267.96
Holmium		1474	2700	
Hydrogen	-259.198 (7.2 kPa)	-259.1	-252.762	-240.18
Indium	156.5936	156.60	2072	
Iodine		113.7	184.4	546
Iridium		2446	4428	
Iron		1538	2861	
Krypton	-157.375 (73.2 kPa)		-153.34	-63.74
Lanthanum		918	3464	
Lawrencium		1627		

Element	t_{tp}/°C	t_m/°C	t_b/°C	t_c/°C
Lead		327.462	1749	
Lithium		180.50	1342	2950
Lutetium		1663	3402	
Magnesium		650	1090	
Manganese		1246	2061	
Mendelevium		827		
Mercury	-38.837	-38.8290	356.62	1477
Molybdenum		2622	4639	
Neodymium		1021	3074	
Neon	-248.609 (43 kPa)		-246.053	-228.7
Neptunium		644		
Nickel		1455	2913	
Niobium		2477	4744	
Nitrogen	-209.999	-210.0	-195.798	-146.94
Nobelium		827		
Osmium		3033	5012	
Oxygen		-218.79	-182.953	-118.56
Palladium		1554.8	2963	
Phosphorus (white)		44.15	280.5	721
Phosphorus (red)	590		431 sp	721
Phosphorus (black)		610		
Platinum		1768.2	3825	
Plutonium		640	3228	
Polonium		254	962	
Potassium		63.5	759	1950
Praseodymium		931	3520	
Promethium		1042	3000	
Protactinium		1572		
Radium		700		
Radon		-71	-61.7	104
Rhenium		3186	5596	
Rhodium		1963	3695	
Rubidium	39.26	39.30	688	1820
Ruthenium		2333	4150	
Samarium		1074	1794	
Scandium		1541	2836	
Selenium (vitreous)		180 (trans to gray)	685	1493
Selenium (gray)		220.5	685	1493
Silicon		1414	3265	
Silver		961.78	2162	
Sodium		97.794	882.940	2300
Strontium		777	1382	
Sulfur (rhombic)		95.3 (trans to monocl)	444.61	1041
Sulfur (monoclinic)		115.21	444.61	1041
Tantalum		3007	5458	
Technetium		2157	4265	
Tellurium		449.51	988	
Terbium		1356	3230	
Thallium		304	1473	
Thorium		1750	4788	
Thulium		1545	1950	
Tin (gray)		13.2 (trans to white)	2602	
Tin (white)		231.93	2602	
Titanium		1670	3287	
Tungsten		3414	5555	
Uranium		1135	4131	
Vanadium		1910	3407	
Xenon	-111.745 (81.6 kPa)		-108.09	16.62
Ytterbium		819	1196	
Yttrium		1522	3345	
Zinc		419.53	907	
Zirconium		1854	4409	

HEAT CAPACITY OF THE ELEMENTS AT 25°C

This table gives the specific heat capacity (c_p) in J/g K and the molar heat capacity (C_p) in J/mol K at a temperature of 25°C and a pressure of 100 kPa (1 bar or 0.987 standard atmospheres) for all the elements for which reliable data are available.

Name	c_p J/g K	C_p J/mol K
Actinium	0.120	27.2
Aluminum	0.897	24.20
Antimony	0.207	25.23
Argon	0.520	20.786
Arsenic	0.329	24.64
Barium	0.204	28.07
Beryllium	1.825	16.443
Bismuth	0.122	25.52
Boron	1.026	11.087
Bromine (Br_2)	0.474	75.69
Cadmium	0.232	26.020
Calcium	0.647	25.929
Carbon (graphite)	0.709	8.517
Cerium	0.192	26.94
Cesium	0.242	32.210
Chlorine (Cl_2)	0.479	33.949
Chromium	0.449	23.35
Cobalt	0.421	24.81
Copper	0.385	24.440
Dysprosium	0.173	28.16
Erbium	0.168	28.12
Europium	0.182	27.66
Fluorine (F_2)	0.824	31.304
Gadolinium	0.236	37.03
Gallium	0.373	26.03
Germanium	0.320	23.222
Gold	0.129	25.418
Hafnium	0.144	25.73
Helium	5.193	20.786
Holmium	0.165	27.15
Hydrogen (H_2)	14.304	28.836
Indium	0.233	26.74
Iodine (I_2)	0.214	54.43
Iridium	0.131	25.10
Iron	0.449	25.10
Krypton	0.248	20.786
Lanthanum	0.195	27.11
Lead	0.130	26.84
Lithium	3.582	24.860
Lutetium	0.154	26.86
Magnesium	1.023	24.869
Manganese	0.479	26.32
Mercury	0.140	27.983
Molybdenum	0.251	24.06
Neodymium	0.190	27.45
Neon	1.030	20.786
Nickel	0.444	26.07
Niobium	0.265	24.60
Nitrogen (N_2)	1.040	29.124
Osmium	0.130	24.7
Oxygen (O_2)	0.918	29.378
Palladium	0.246	25.98
Phosphorus (white)	0.769	23.824
Platinum	0.133	25.86
Potassium	0.757	29.600
Praseodymium	0.193	27.20
Radon	0.094	20.786
Rhenium	0.137	25.48
Rhodium	0.243	24.98
Rubidium	0.363	31.060
Ruthenium	0.238	24.06
Samarium	0.197	29.54
Scandium	0.568	25.52
Selenium	0.321	25.363
Silicon	0.712	19.99
Silver	0.235	25.350
Sodium	1.228	28.230
Strontium	0.306	26.79
Sulfur (rhombic)	0.708	22.70
Tantalum	0.140	25.36
Tellurium	0.202	25.73
Terbium	0.182	28.91
Thallium	0.129	26.32
Thorium	0.118	27.32
Thulium	0.160	27.03
Tin (white)	0.227	26.99
Titanium	0.523	25.060
Tungsten	0.132	24.27
Uranium	0.116	27.665
Vanadium	0.489	24.89
Xenon	0.158	20.786
Ytterbium	0.155	26.74
Yttrium	0.298	26.53
Zinc	0.388	25.390
Zirconium	0.278	25.36

VAPOR PRESSURE OF THE METALLIC ELEMENTS — EQUATIONS

C. B. Alcock

This table gives coefficients in an equation for the vapor pressure of 65 metallic elements in both the solid and liquid state. Vapor pressures in the range 10^{-10} to 10^{2} Pa (10^{-15} to 10^{-3} atm) are covered. The equation is:

for p in atmospheres: $\log(p/\text{atm}) = A + BT^{-1} + C\log T + DT^{-3}$
for p in pascals: $\log(p/\text{Pa}) = 5.006 + A + BT^{-1} + C\log T + DT^{-3}$
for p in torr (mmHg): $\log(p/\text{torr}) = 2.881 + A + BT^{-1} + C\log T + DT^{-3}$

where T is the temperature in K.

This equation reproduces the observed vapor pressures to an accuracy of 5% or better. The metals are listed alphabetically by name, and the melting point is included.

The table following this one gives values of the vapor pressure at several temperatures in the 400 K to 2400 K range, as calculated from these equations.

Reprinted with permission of the publisher, Pergamon Press.

Reference

Alcock, C. B., Itkin, V. P., and Horrigan, M. K., *Canadian Metallurgical Quarterly*, 23, 309, 1984.

Element	Phase	*A*	*B*	*C*	*D*	Range/k	mp/k
Aluminum	Solid	9.459	-17342	-0.7927		298-mp	933
Aluminum	Liquid	5.911	-16211			mp-1800	
Americium	Solid	11.311	-15059	-1.3449		298-mp	1449
Barium	Solid	12.405	-9690	-2.2890		298-mp	1000
Barium	Liquid	4.007	-8163			mp-1200	
Beryllium	Solid	8.042	-17020	-0.4440		298-mp	1560
Beryllium	Liquid	5.786	-15731			mp-1800	
Cadmium	Solid	5.939	-5799			298-mp	594
Cadmium	Liquid	5.242	-5392			mp-650	
Calcium	Solid	10.127	-9517	-1.4030		298-mp	1115
Cerium	Solid	6.139	-21752			298-mp	1071
Cerium	Liquid	5.611	-21200			mp-2450	
Cesium	Solid	4.711	-3999			298-mp	302
Cesium	Liquid	4.165	-3830			mp-550	
Chromium	Solid	6.800	-20733	0.4391	-0.4094	298-2000	2180
Cobalt	Solid	10.976	-22576	-1.0280		298-mp	1768
Cobalt	Liquid	6.488	-20578			mp-2150	
Copper	Solid	9.123	-17748	-0.7317		298-mp	1358
Copper	Liquid	5.849	-16415			mp-1850	
Curium	Solid	8.369	-20364	-0.5770		298-mp	1618
Curium	Liquid	5.223	-18292			mp-2200	
Dysprosium	Solid	9.579	-15336	-1.1114		298-mp	1685
Erbium	Solid	9.916	-16642	-1.2154		298-mp	1802
Erbium	Liquid	4.668	-14380			mp-1900	
Europium	Solid	9.240	-9459	-1.1661		298-mp	1095
Gadolinium	Solid	8.344	-20861	-0.5775		298-mp	1586
Gadolinium	Liquid	5.557	-19389			mp-2250	
Gallium	Solid	6.657	-14208			298-mp	303
Gallium	Liquid	6.754	-13984	-0.3413		mp-1600	
Gold	Solid	9.152	-19343	-0.7479		298-mp	1337
Gold	Liquid	5.832	-18024			mp-2050	
Hafnium	Solid	9.445	-32482	-0.6735		298-mp	2506
Holmium	Solid	9.785	-15899	-1.1753		298-mp	1747
Indium	Solid	5.991	-12548			298-mp	430
Indium	Liquid	5.374	-12276			mp-1500	
Iridium	Solid	10.506	-35099	-0.7500		298-2500	2719
Iron	Solid	7.100	-21723	0.4536	-0.5846	298-mp	1811
Iron	Liquid	6.347	-19574			mp-2100	
Lanthanum	Solid	7.463	-22551	-0.3142		298-mp	1191
Lanthanum	Liquid	5.911	-21855			mp-2450	
Lead	Solid	5.643	-10143			298-mp	600
Lead	Liquid	4.911	-9701			mp-1200	
Lithium	Solid	5.667	-8310			298-mp	454
Lithium	Liquid	5.055	-8023			mp-1000	
Lutetium	Solid	8.793	-22423	-0.6200		298-mp	1936
Lutetium	Liquid	5.648	-20302			mp-2350	

Element	Phase	*A*	*B*	*C*	*D*	Range/k	mp/k
Magnesium	Solid	8.489	-7813	-0.8253		298-mp	923
Manganese	Solid	12.805	-15097	-1.7896		298-mp	1519
Mercury	Liquid	5.116	-3190			298-400	234
Molybdenum	Solid	11.529	-34626	-1.1331		298-2500	2895
Neodymium	Solid	8.996	-17264	-0.9519		298-mp	1294
Neodymium	Liquid	4.912	-15824			mp-2000	
Neptunium	Solid	19.643	-24886	-3.9991		298-mp	917
Neptunium	Liquid	10.076	-23378	-1.3250		mp-2500	
Nickel	Solid	10.557	-22606	-0.8717		298-mp	1728
Nickel	Liquid	6.666	-20765			mp-2150	
Niobium	Solid	8.882	-37818	-0.2575		298-2500	2750
Osmium	Solid	9.419	-41198	-0.3896		298-2500	3306
Palladium	Solid	9.502	-19813	-0.9258		298-mp	1828
Palladium	Liquid	5.426	-17899			mp-2100	
Platinum	Solid	4.882	-29387	1.1039	-0.4527	298-mp	2041
Platinum	Liquid	6.386	-26856			mp-2500	
Plutonium	Solid	26.160	-19162	-6.6675		298-600	913
Plutonium	Solid	18.858	-18460	-4.4720		500-mp	
Plutonium	Liquid	3.666	-16658			mp-2450	
Potassium	Solid	4.961	-4646			298-mp	337
Potassium	Liquid	4.402	-4453			mp-600	
Praseodymium	Solid	8.859	-18720	-0.9512		298-mp	1204
Praseodymium	Liquid	4.772	-17315			mp-2200	
Protactinium	Solid	10.552	-34869	-1.0075		298-mp	1845
Protactinium	Liquid	6.177	-32874			mp-2500	
Rhenium	Solid	11.543	-40726	-1.1629		298-2500	3459
Rhodium	Solid	10.168	-29010	-0.7068		298-mp	2236
Rhodium	Liquid	6.802	-26792			mp-2500	
Rubidium	Solid	4.857	-4215			298-mp	312
Rubidium	Liquid	4.312	-4040			mp-550	
Ruthenium	Solid	9.755	-34154	-0.4723		298-mp	2606
Samarium	Solid	9.988	-11034	-1.3287		298-mp	1347
Scandium	Solid	6.650	-19721	0.2885	-0.3663	298-mp	1814
Scandium	Liquid	5.795	-17681			mp-2000	
Silver	Solid	9.127	-14999	-0.7845		298-mp	1235
Silver	Liquid	5.752	-13827			mp-1600	
Sodium	Solid	5.298	-5603			298-mp	371
Sodium	Liquid	4.704	-5377			mp-700	
Strontium	Solid	9.226	-8572	-1.1926		298-mp	1050
Tantalum	Solid	16.807	-41346	-3.2152	0.7437	298-2500	3280
Terbium	Solid	9.510	-20457	-0.9247		298-mp	1629
Terbium	Liquid	5.411	-18639			mp-2200	
Thallium	Solid	5.971	-9447			298-mp	577
Thallium	Liquid	5.259	-9037			mp-1100	
Thorium	Solid	8.668	-31483	-0.5288		298-mp	2023
Thorium	Liquid	-18.453	-24569	6.6473		mp-2500	
Thulium	Solid	8.882	-12270	-0.9564		298-1400	1818
Tin	Solid	6.036	-15710			298-mp	505
Tin	Liquid	5.262	-15332			mp-1850	
Titanium	Solid	11.925	-24991	-1.3376		298-mp	1943
Titanium	Liquid	6.358	-22747			mp-2400	
Tungsten	Solid	2.945	-44094	1.3677		298-2350	3687
Tungsten	Solid	54.527	-57687	-12.2231		2200-2500	
Uranium	Solid	0.770	-27729	2.6982	-1.5471	298-mp	1408
Uranium	Liquid	20.735	-28776	-4.0962		mp-2500	
Vanadium	Solid	9.744	-27132	-0.5501		298-mp	2183
Vanadium	Liquid	6.929	-25011			mp-2500	
Ytterbium	Solid	9.111	-8111	-1.0849		298-900	1092
Yttrium	Solid	9.735	-22306	-0.8705		298-mp	1795
Yttrium	Liquid	5.795	-20341			mp-2300	
Zinc	Solid	6.102	-6776			298-mp	693
Zinc	Liquid	5.378	-6286			mp-750	
Zirconium	Solid	10.008	-31512	-0.7890		298-m.p	2127
Zirconium	Liquid	6.806	-30295			mp-2500	

DENSITY OF MOLTEN ELEMENTS AND REPRESENTATIVE SALTS

This table lists the liquid density at the melting point, ρ_m, for elements that are solid at room temperature, as well as for some representative salts of these elements. Densities at higher temperatures (up to the t_{max} given in the last column) may be estimated from the equation

$$\rho(t) = \rho_m - k(t - t_m)$$

where t_m is the melting point and k is given in the fifth column of the table. If a value of t_{max} is not given, the equation should not be used to extrapolate more than about 20°C beyond the melting point.

Data for the elements were selected from the primary literature; the assistance of Gernot Lang in compiling these data is gratefully acknowledged. The molten salt data were derived from Reference 1.

References

1. Janz, G. J., Thermodynamic and Transport Properties of Molten Salts: Correlation Equations for Critically Evaluated Density, Surface Tension, Electrical Conductance, and Viscosity Data, *J. Phys. Chem. Ref. Data*, 17, Suppl. 2, 1988.
2. Nasch, P. M., and Steinemann, S. G., *Phys. Chem. Liq.*, 29, 43, 1995.

Formula	Name	t_m/°C	ρ_m/g cm^{-3}	k/g cm^{-3} °C^{-1}	t_{max}
Ag	Silver	961.78	9.320	0.0009	1500
AgBr	Silver(I) bromide	432	5.577	0.001035	667
AgCl	Silver(I) chloride	455	4.83	0.00094	627
AgI	Silver(I) iodide	558	5.58	0.00101	802
$AgNO_3$	Silver(I) nitrate	212	3.970	0.001098	360
Ag_2SO_4	Silver(I) sulfate	652	4.84	0.001089	770
Al	Aluminum	660.32	2.375	0.000233	1340
$AlBr_3$	Aluminum bromide	97.5	2.647	0.002435	267
$AlCl_3$	Aluminum chloride	192.6	1.302	0.002711	296
AlI_3	Aluminum iodide	188.32	3.223	0.0025	240
As	Arsenic	817	5.22	0.000544	
Au	Gold	1064.18	17.31	0.001343	1200
B	Boron	2075	2.08		
Ba	Barium	727	3.338	0.000299	1550
$BaBr_2$	Barium bromide	857	3.991	0.000924	900
$BaCl_2$	Barium chloride	962	3.174	0.000681	1081
BaF_2	Barium fluoride	1368	4.14	0.000999	1727
BaI_2	Barium iodide	711	4.26	0.000977	975
Be	Beryllium	1287	1.690	0.00011	
$BeCl_2$	Beryllium chloride	415	1.54	0.0011	473
BeF_2	Beryllium fluoride	552	1.96	0.000015	850
Bi	Bismuth	271.40	10.05	0.00135	800
$BiBr_3$	Bismuth bromide	218	4.76	0.002637	927
$BiCl_3$	Bismuth chloride	230	3.916	0.0023	350
Ca	Calcium	842	1.378	0.000230	1484
$CaBr_2$	Calcium bromide	742	3.111	0.0005	791
$CaCl_2$	Calcium chloride	775	2.085	0.000422	950
CaF_2	Calcium fluoride	1418	2.52	0.000391	2027
CaI_2	Calcium iodide	783	3.443	0.000751	1028
Cd	Cadmium	321.07	7.996	0.001218	500
$CdBr_2$	Cadmium bromide	568	4.075	0.00108	720
$CdCl_2$	Cadmium chloride	564	3.392	0.00082	807
CdI_2	Cadmium iodide	387	4.396	0.001117	700
Ce	Cerium	799	6.55	0.000710	1460
$CeCl_3$	Cerium(III) chloride	817	3.25	0.00092	950
CeF_3	Cerium(III) fluoride	1430	4.659	0.000936	1927
Co	Cobalt	1495	7.75	0.00165	1580
Cr	Chromium	1907	6.3	0.0011	2100
Cs	Cesium	28.44	1.843	0.000556	510
CsBr	Cesium bromide	636	3.133	0.001223	860
CsCl	Cesium chloride	645	2.79	0.001065	906
CsF	Cesium fluoride	703	3.649	0.001282	912
CsI	Cesium iodide	621	3.197	0.001183	907
$CsNO_3$	Cesium nitrate	414	2.820	0.001166	491
Cs_2SO_4	Cesium sulfate	1005	3.1	0.00095	1530
Cu	Copper	1084.62	8.02	0.000609	1630
CuCl	Copper(I) chloride	430	3.692	0.00076	585

Formula	Name	t_m/°C	ρ_m/g cm^{-3}	k/g cm^{-3} °C^{-1}	t_{max}
Dy	Dysprosium	1411	8.37	0.00143	1540
$DyCl_3$	Dysprosium(III) chloride	680	3.62	0.00068	987
Er	Erbium	1529	8.86	0.00157	1700
Eu	Europium	822	5.13	0.0028	980
Fe	Iron	1538	6.98	0.000572	1680
$FeCl_2$	Iron(II) chloride	677	2.348	0.000555	877
Ga	Gallium	29.76	6.08	0.00062	400
$GaBr_3$	Gallium(III) bromide	121.5	3.116	0.00246	135
$GaCl_3$	Gallium(III) chloride	77.9	2.053	0.002083	141
GaI_3	Gallium(III) iodide	212	3.630	0.002377	252
Gd	Gadolinium	1314	7.4		
$GdCl_3$	Gadolinium(III) chloride	609	3.56	0.000671	1007
GdI_3	Gadolinium(III) iodide	925	4.12	0.000908	1032
Ge	Germanium	938.25	5.60	0.00055	1600
Hf	Hafnium	2233	12		
$HgBr_2$	Mercury(II) bromide	236	5.126	0.003233	319
$HgCl_2$	Mercury(II) chloride	276	4.368	0.002862	304
HgI_2	Mercury(II) iodide	259	5.222	0.003235	354
Ho	Holmium	1472	8.34		
In	Indium	156.60	7.02	0.000836	500
$InBr_3$	Indium(III) bromide	420	3.121	0.0015	528
$InCl_3$	Indium(III) chloride	583	2.140	0.0021	666
InI_3	Indium(III) iodide	207	3.820	0.0015	360
Ir	Iridium	2446	19		
K	Potassium	63.38	0.828	0.000232	500
KBr	Potassium bromide	734	2.127	0.000825	930
KCl	Potassium chloride	771	1.527	0.000583	939
KF	Potassium fluoride	858	1.910	0.000651	1037
KI	Potassium iodide	681	2.448	0.000956	904
KNO_3	Potassium nitrate	337	1.865	0.000723	457
La	Lanthanum	920	5.94	0.00061	1600
$LaBr_3$	Lanthanum bromide	788	4.933	0.000096	912
$LaCl_3$	Lanthanum chloride	859	3.209	0.000777	973
LaF_3	Lanthanum fluoride	1493	4.589	0.000682	2177
LaI_3	Lanthanum iodide	778	4.29	0.001110	907
Li	Lithium	180.5	0.512	0.00052	285
LiBr	Lithium bromide	552	2.528	0.000652	739
LiCl	Lithium chloride	610	1.502	0.000432	781
LiF	Lithium fluoride	848.2	1.81	0.000490	1047
LiI	Lithium iodide	469	3.109	0.000917	667
$LiNO_3$	Lithium nitrate	253	1.781	0.000546	441
Li_2SO_4	Lithium sulfate	859	2.003	0.000407	1214
Lu	Lutetium	1663	9.3		
Mg	Magnesium	650	1.584	0.000234	900
$MgBr_2$	Magnesium bromide	711	2.62	0.000478	935
$MgCl_2$	Magnesium chloride	714	1.68	0.000271	826
MgI_2	Magnesium iodide	634	3.05	0.000651	888
Mn	Manganese	1246	5.95	0.00105	1590
$MnCl_2$	Manganese(II) chloride	650	2.353	0.000437	850
Mo	Molybdenum	2623	9.33		
Na	Sodium	97.80	0.927	0.00023	600
NaBr	Sodium bromide	747	2.342	0.000816	945
Na_2CO_3	Sodium carbonate	858.1	1.972	0.000448	1004
NaCl	Sodium chloride	800.7	1.556	0.000543	1027
NaF	Sodium fluoride	996	1.948	0.000636	1097
NaI	Sodium iodide	660	2.742	0.000949	912
$NaNO_3$	Sodium nitrate	307	1.90	0.000715	370
Na_2SO_4	Sodium sulfate	884	2.069	0.000483	1077
Nd	Neodymium	1016	6.89	0.00076	1350
Ni	Nickel	1455	7.81	0.000726	1700
$NiCl_2$	Nickel(II) chloride	1009	2.653	0.00066	1057
Os	Osmium	3033	20		
Pb	Lead	327.46	10.66	0.00122	700
$PbBr_2$	Lead(II) bromide	371	5.73	0.00165	600
$PbCl_2$	Lead(II) chloride	501	4.951	0.0015	710

Formula	Name	t_m/°C	ρ_m/g cm^{-3}	k/g cm^{-3} °C^{-1}	t_{max}
PbI_2	Lead(II) iodide	410	5.691	0.001594	697
Pd	Palladium	1554.9	10.38	0.001169	1700
Pr	Praseodymium	931	6.50	0.00093	1460
$PrCl_3$	Praseodymium chloride	786	3.23	0.00074	977
Pt	Platinum	1768.4	19.77	0.0024	2200
Pu	Plutonium	640	16.63	0.001419	950
Rb	Rubidium	39.31	1.46	0.000451	800
RbBr	Rubidium bromide	682	2.715	0.001072	907
Rb_2CO_3	Rubidium carbonate	837	2.84	0.000640	1007
RbCl	Rubidium chloride	715	2.248	0.000883	923
RbF	Rubidium fluoride	833	2.87	0.00102	1067
RbI	Rubidium iodide	642	2.904	0.001143	902
$RbNO_3$	Rubidium nitrate	305	2.519	0.001068	417
Rb_2SO_4	Rubidium sulfate	1050	2.56	0.000665	1545
Re	Rhenium	3186	18.9		
Rh	Rhodium	1964	10.7	0.000895	2200
Ru	Ruthenium	2334	10.65		
S	Sulfur	115.21	1.819	0.00080	160
Sb	Antimony	630.63	6.53	0.00067	745
$SbCl_3$	Antimony(III) chloride	73.4	2.681	0.002293	77
$SbCl_5$	Antimony(V) chloride	4	2.37	0.001869	77
SbI_3	Antimony(III) iodide	168	4.171	0.002483	322
Sc	Scandium	1541	2.80		
Se	Selenium	221	3.99		
Si	Silicon	1414	2.57	0.00036	1500
Sm	Samarium	1072	7.16		
Sn	Tin	231.93	6.99	0.000601	1200
$SnCl_2$	Tin(II) chloride	247	3.36	0.001253	480
$SnCl_4$	Tin(IV) chloride	−33	2.37	0.002687	138
Sr	Strontium	777	6.980		
$SrBr_2$	Strontium bromide	657	3.70	0.000745	1004
$SrCl_2$	Strontium chloride	874	2.727	0.000578	1037
SrF_2	Strontium fluoride	1477	3.470	0.000751	1927
SrI_2	Strontium iodide	538	4.085	0.000885	1026
Ta	Tantalum	3017	15		
$TaCl_5$	Tantalum(V) chloride	216	2.700	0.004316	457
Tb	Terbium	1359	7.65		
Te	Tellurium	449.51	5.70	0.00035	600
$ThCl_4$	Thorium chloride	770	3.363	0.0014	847
ThF_4	Thorium fluoride	1110	6.058	0.000759	1378
Ti	Titanium	1668	4.11		
$TiCl_4$	Titanium(IV) chloride	-25	1.807	0.001735	137
Tl	Thallium	304	11.22	0.00144	600
TlBr	Thallium(I) bromide	460	5.98	0.001755	647
TlCl	Thallium(I) chloride	430	5.628	0.0018	642
TlI	Thallium(I) iodide	441.8	6.15	0.001761	737
$TlNO_3$	Thallium(I) nitrate	206	4.91	0.001873	279
Tl_2SO_4	Thallium(I) sulfate	632	5.62	0.00130	927
Tm	Thulium	1545	8.56	0.00050	1675
U	Uranium	1135	17.3		
UCl_3	Uranium(III) chloride	837	4.84	0.007943	1057
UCl_4	Uranium(IV) chloride	590	3.572	0.001945	667
UF_4	Uranium(IV) fluoride	1036	6.485	0.000992	1341
V	Vanadium	1910	5.5		
W	Tungsten	3422	17.6		
Y	Yttrium	1526	4.24		
YCl_3	Yttrium chloride	721	2.510	0.0005	845
Yb	Ytterbium	824	6.21		
Zn	Zinc	419.53	6.57	0.0011	700
$ZnBr_2$	Zinc bromide	394	3.47	0.000959	602
$ZnCl_2$	Zinc chloride	290	2.54	0.00053	557
ZnI_2	Zinc iodide	446	3.878	0.00136	588
$ZnSO_4$	Zinc sulfate	680	3.14	0.00047	987
Zr	Zirconium	1855	5.8		
$ZrCl_4$	Zirconium chloride	437	1.643	0.007464	492

MAGNETIC SUSCEPTIBILITY OF THE ELEMENTS AND INORGANIC COMPOUNDS

When a material is placed in a magnetic field $\boldsymbol{H}$, a magnetization (magnetic moment per unit volume) $\boldsymbol{M}$ is induced in the material which is related to $\boldsymbol{H}$ by $\boldsymbol{M} = \kappa\boldsymbol{H}$, where κ is called the volume susceptibility. Since $\boldsymbol{H}$ and $\boldsymbol{M}$ have the same dimensions, κ is dimensionless. A more useful parameter is the molar susceptibility χ_m , defined by

$$\chi_m = \kappa V_m = \kappa\, M / \rho$$

where V_m is the molar volume of the substance, M the molar mass, and ρ the mass density. When the cgs system is used, the customary units for χ_m are $cm^3\ mol^{-1}$; the corresponding SI units are $m^3\ mol^{-1}$.

Substances that have no unpaired electron orbital or spin angular momentum generally have negative values of χ_m and are called diamagnetic. Their molar susceptibility varies only slightly with temperature. Substances with unpaired electrons, which are termed paramagnetic, have positive χ_m and show a much stronger temperature dependence, varying roughly as $1/T$. The net susceptibility of a paramagnetic substance is the sum of the paramagnetic and diamagnetic contributions, but the former almost always dominates.

This table gives values of χ_m for the elements and selected inorganic compounds. All values refer to nominal room temperature (285 to 300 K) unless otherwise indicated. When the physical state (s = solid, l = liquid, g = gas, aq = aqueous solution) is not given, the most common crystalline form is understood. An entry of Ferro. indicates a ferromagnetic substance.

Substances are arranged in alphabetical order by the most common name, except that compounds such as hydrides, oxides, and acids are grouped with the parent element (the same ordering used in the table "Physical Constants of Inorganic Compounds").

In keeping with customary practice, the molar susceptibility is given here in units appropriate to the cgs system. These values should be multiplied by 4π to obtain values for use in SI equations (where the magnetic field strength $\boldsymbol{H}$ has units of $A\ m^{-1}$).

References

1. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series,* II/16, *Diamagnetic Susceptibility,* Springer-Verlag, Heidelberg, 1986.
2. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series*, III/19, Subvolumes a to i2, *Magnetic Properties of Metals*, Springer-Verlag, Heidelberg, 1986-1992.
3. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series*, II/2, II/8, II/10, II/11,and II/12a, *Coordination and Organometallic Transition Metal Compounds*, Springer-Verlag, Heidelberg, 1966-1984.
4. *Tables de Constantes et Données Numérique, Volume 7, Relaxation Paramagnetique*, Masson, Paris, 1957.

Name	Formula	$\chi_m/10^{-6}\ cm^3\ mol^{-1}$
Aluminum	Al	+16.5
Aluminum trifluoride	AlF_3	−13.9
Aluminum oxide	Al_2O_3	−37
Aluminum sulfate	$Al_2(SO_4)_3$	−93
Ammonia (g)	NH_3	−16.3
Ammonia (aq)	NH_3	−18.3
Ammonium acetate	$NH_4C_2H_3O_2$	−41.1
Ammonium bromide	NH_4Br	−47
Ammonium carbonate	$(NH_4)_2CO_3$	−42.5
Ammonium chlorate	NH_4ClO_3	−42.1
Ammonium chloride	NH_4Cl	−36.7
Ammonium fluoride	NH_4F	−23
Ammonium iodate	NH_4IO_3	−62.3
Ammonium iodide	NH_4I	−66
Ammonium nitrate	NH_4NO_3	−33
Ammonium sulfate	$(NH_4)_2SO_4$	−67
Ammonium thiocyanate	NH_4SCN	−48.1
Antimony	Sb	−99
Stibine (g)	SbH_3	−34.6
Antimony(III) bromide	$SbBr_3$	−111.4
Antimony(III) chloride	$SbCl_3$	−86.7
Antimony(III) fluoride	SbF_3	−46
Antimony(III) iodide	SbI_3	−147.2
Antimony(III) oxide	Sb_2O_3	−69.4
Antimony(III) sulfide	Sb_2S_3	−86
Antimony(V) chloride	$SbCl_5$	−120.5
Argon (g)	Ar	−19.32
Arsenic (gray)	As	−5.6
Arsenic (yellow)	As	−23.2
Arsine (g)	AsH_3	−35.2

Name	Formula	$\chi_m/10^{-6}\ cm^3\ mol^{-1}$
Arsenic(III) bromide	$AsBr_3$	−106
Arsenic(III) chloride	$AsCl_3$	−72.5
Arsenic(III) iodide	AsI_3	−142.2
Arsenic(III) oxide	As_2O_3	−30.34
Arsenic(III) sulfide	As_2S_3	−70
Barium	Ba	+20.6
Barium bromide	$BaBr_2$	−92
Barium bromide dihydrate	$BaBr_2{\cdot}2H_2O$	−119.3
Barium carbonate	$BaCO_3$	−58.9
Barium chloride	$BaCl_2$	−72.6
Barium chloride dihydrate	$BaCl_2{\cdot}2H_2O$	−100
Barium fluoride	BaF_2	−51
Barium hydroxide	$Ba(OH)_2$	−53.2
Barium iodate	$Ba(IO_3)_2$	−122.5
Barium iodide	BaI_2	−124.4
Barium iodide dihydrate	$BaI_2{\cdot}2H_2O$	−163
Barium nitrate	$Ba(NO_3)_2$	−66.5
Barium oxide	BaO	−29.1
Barium peroxide	BaO_2	−40.6
Barium sulfate	$BaSO_4$	−65.8
Beryllium	Be	−9.0
Beryllium chloride	$BeCl_2$	−26.5
Beryllium hydroxide	$Be(OH)_2$	−23.1
Beryllium oxide	BeO	−11.9
Beryllium sulfate	$BeSO_4$	−37
Bismuth	Bi	−280.1
Bismuth tribromide	$BiBr_3$	−147
Bismuth trichloride	$BiCl_3$	−26.5
Bismuth fluoride	BiF_3	−61.2
Bismuth hydroxide	$Bi(OH)_3$	−65.8

Name	Formula	$\chi_m/10^{-6}$ cm^3 mol^{-1}
Bismuth triiodide	BiI_3	−200.5
Bismuth nitrate pentahydrate	$Bi(NO_3)_3{\cdot}5H_2O$	−159
Bismuth oxide	Bi_2O_3	−83
Bismuth phosphate	$BiPO_4$	−77
Bismuth sulfate	$Bi_2(SO_4)_3$	−199
Bismuth sulfide	Bi_2S_3	−123
Boron	B	−6.7
Diborane (g)	B_2H_6	−21.0
Boric acid (orthoboric acid)	H_3BO_3	−34.1
Boron trichloride	BCl_3	−59.9
Boron oxide	B_2O_3	−38.7
Bromine (l)	Br_2	−56.4
Bromine (g)	Br_2	−73.5
Bromine trifluoride	BrF_3	−33.9
Bromine pentafluoride	BrF_5	−45.1
Cadmium	Cd	−19.7
Cadmium bromide	$CdBr_2$	−87.3
Cadmium bromide tetrahydrate	$CdBr_2{\cdot}4H_2O$	−131.5
Cadmium carbonate	$CdCO_3$	−46.7
Cadmium chloride	$CdCl_2$	−68.7
Cadmium chromate	$CdCrO_4$	−16.8
Cadmium cyanide	$Cd(CN)_2$	−54
Cadmium fluoride	CdF_2	−40.6
Cadmium hydroxide	$Cd(OH)_2$	−41
Cadmium iodate	$Cd(IO_3)_2$	−108.4
Cadmium iodide	CdI_2	−117.2
Cadmium nitrate	$Cd(NO_3)_2$	−55.1
Cadmium nitrate tetrahydrate	$Cd(NO_3)_2{\cdot}4H_2O$	−140
Cadmium oxide	CdO	−30
Cadmium sulfate	$CdSO_4$	−59.2
Cadmium sulfide	CdS	−50
Calcium	Ca	+40
Calcium bromide	$CaBr_2$	−73.8
Calcium carbonate	$CaCO_3$	−38.2
Calcium chloride	$CaCl_2$	−54.7
Calcium fluoride	CaF_2	−28
Calcium hydroxide	$Ca(OH)_2$	−22
Calcium iodate	$Ca(IO_3)_2$	−101.4
Calcium iodide	CaI_2	−109
Calcium oxide	CaO	−15.0
Calcium sulfate	$CaSO_4$	−49.7
Calcium sulfate dihydrate	$CaSO_4{\cdot}2H_2O$	−74
Carbon (diamond)	C	−5.9
Carbon (graphite)	C	−6.0
Carbon monoxide (g)	CO	−11.8
Carbon dioxide (g)	CO_2	−21.0
Cerium (β)	Ce	+2500
Cerium(II) sulfide	CeS	+2110
Cerium(III) chloride	$CeCl_3$	+2490
Cerium(III) fluoride	CeF_3	+2190
Cerium(III) sulfide	Ce_2S_3	+5080
Cerium(IV) oxide	CeO_2	+26
Cerium(IV) sulfate tetrahydrate	$Ce(SO_4)_2{\cdot}4H_2O$	−97
Cesium	Cs	+29
Cesium bromate	$CsBrO_3$	−75.1
Cesium bromide	CsBr	−67.2
Cesium carbonate	Cs_2CO_3	−103.6
Cesium chlorate	$CsClO_3$	−65
Cesium chloride	CsCl	−56.7
Cesium fluoride	CsF	−44.5
Cesium iodide	CsI	−82.6
Cesium superoxide	CsO_2	+1534
Cesium sulfate	Cs_2SO_4	−116
Chlorine (l)	Cl_2	−40.4
Chlorine trifluoride (g)	ClF_3	−26.5
Chromium	Cr	+167
Chromium(II) chloride	$CrCl_2$	+7230
Chromium(III) chloride	$CrCl_3$	+6350
Chromium(III) fluoride	CrF_3	+4370
Chromium(III) oxide	Cr_2O_3	+1960
Chromium(III) sulfate	$Cr_2(SO_4)_3$	+11800
Chromium(VI) oxide	CrO_3	+40
Cobalt	Co	Ferro.
Cobalt(II) bromide	$CoBr_2$	+13000
Cobalt(II) chloride	$CoCl_2$	+12660
Cobalt(II) chloride hexahydrate	$CoCl_2{\cdot}6H_2O$	+9710
Cobalt(II) cyanide	$Co(CN)_2$	+3825
Cobalt(II) fluoride	CoF_2	+9490
Cobalt(II) iodide	CoI_2	+10760
Cobalt(II) sulfate	$CoSO_4$	+10000
Cobalt(II) sulfide	CoS	+225
Cobalt(II,III) oxide	Co_3O_4	+7380
Cobalt(III) fluoride	CoF_3	+1900
Cobalt(III) oxide	Co_2O_3	+4560
Copper	Cu	−5.46
Copper(I) bromide	CuBr	−49
Copper(I) chloride	CuCl	−40
Copper(I) cyanide	CuCN	−24
Copper(I) iodide	CuI	−63
Copper(I) oxide	Cu_2O	−20
Copper(II) bromide	$CuBr_2$	+685
Copper(II) chloride	$CuCl_2$	+1080
Copper(II) chloride dihydrate	$CuCl_2{\cdot}2H_2O$	+1420
Copper(II) fluoride	CuF_2	+1050
Copper(II) fluoride dihydrate	$CuF_2{\cdot}2H_2O$	+1600
Copper(II) hydroxide	$Cu(OH)_2$	+1170
Copper(II) nitrate trihydrate	$Cu(NO_3)_2{\cdot}3H_2O$	+1570
Copper(II) nitrate hexahydrate	$Cu(NO_3)_2{\cdot}6H_2O$	+1625
Copper(II) oxide	CuO	+238
Copper(II) sulfate	$CuSO_4$	+1330
Copper(II) sulfate pentahydrate	$CuSO_4{\cdot}5H_2O$	+1460
Copper(II) sulfide	CuS	−2.0
Dysprosium (α)	Dy	+98000
Dysprosium(III) oxide	Dy_2O_3	+89600
Dysprosium(III) sulfide	Dy_2S_3	+95200
Erbium	Er	+48000
Erbium oxide	Er_2O_3	+73920
Erbium sulfate octahydrate	$Er_2(SO_4)_3{\cdot}8H_2O$	+74600
Erbium sulfide	Er_2S_3	+77200
Europium	Eu	+30900
Europium(II) bromide	$EuBr_2$	+26800
Europium(II) chloride	$EuCl_2$	+26500
Europium(II) fluoride	EuF_2	+23750
Europium(II) iodide	EuI_2	+26000
Europium(II) sulfide	EuS	+23800
Europium(III) oxide	Eu_2O_3	+10100
Europium(III) sulfate	$Eu_2(SO_4)_3$	+10400
Fluorine	F_2	−9.63
Gadolinium (350 K)	Gd	+185000
Gadolinium(III) chloride	$GdCl_3$	+27930

Name	Formula	$\chi_m/10^{-6}$ cm^3 mol^{-1}
Gadolinium(III) oxide	Gd_2O_3	+53200
Gadolinium(III) sulfate octahydrate	$Gd_2(SO_4)_3 \cdot 8H_2O$	+53280
Gadolinium(III) sulfide	Gd_2S_3	+55500
Gallium	Ga	−21.6
Gallium suboxide	Ga_2O	−34
Gallium(II) sulfide	GaS	−23
Gallium(III) chloride	$GaCl_3$	−63
Gallium(III) sulfide	Ga_2S_3	−80
Germanium	Ge	−11.6
Germane (g)	GeH_4	−29.7
Germanium(II) oxide	GeO	−28.8
Germanium(II) sulfide	GeS	−40.9
Germanium(IV) chloride	$GeCl_4$	−72
Germanium(IV) fluoride	GeF_4	−50
Germanium(IV) iodide	GeI_4	−171
Germanium(IV) oxide	GeO_2	−34.3
Germanium(IV) sulfide	GeS_2	−53.9
Gold	Au	−28
Gold(I) bromide	AuBr	−61
Gold(I) chloride	AuCl	−67
Gold(I) iodide	AuI	−91
Gold(III) chloride	$AuCl_3$	−112
Hafnium	Hf	+71
Hafnium oxide	HfO_2	−23
Helium (g)	He	−2.02
Holmium	Ho	+72900
Holmium oxide	Ho_2O_3	+88100
Hydrazine (l)	N_2H_4	−201
Hydrogen (l, 20.3 K)	H_2	−5.44
Hydrogen (g)	H_2	−3.99
Hydrogen chloride (l)	HCl	−22.6
Hydrogen chloride (aq)	HCl	−22
Hydrogen fluoride (l)	HF	−8.6
Hydrogen fluoride (aq)	HF	−9.3
Hydrogen iodide (s, 195 K)	HI	−47.3
Hydrogen iodide (l, 233 K)	HI	−48.3
Hydrogen iodide (aq)	HI	−50.2
Hydrogen peroxide (l)	H_2O_2	−17.3
Hydrogen sulfide (g)	H_2S	−25.5
Indium	In	−10.2
Indium(I) chloride	InCl	−30
Indium(II) chloride	$InCl_2$	−56
Indium(II) sulfide	InS	−28
Indium(III) bromide	$InBr_3$	−107
Indium(III) chloride	$InCl_3$	−86
Indium(III) oxide	In_2O_3	−56
Indium(III) sulfide	In_2S_3	−98
Iodine	I_2	−90
Iodic acid	HIO_3	−48
Iodine pentoxide	I_2O_5	−79.4
Iodine chloride	ICl	−54.6
Iodine trichloride	ICl_3	−90.2
Iodine pentafluoride	IF_5	−58.1
Iridium	Ir	+25
Iridium(III) chloride	$IrCl_3$	−14.4
Iridium(IV) oxide	IrO_2	+224
Iron	Fe	Ferro.
Iron(II) bromide	$FeBr_2$	+13600
Iron(II) carbonate	$FeCO_3$	+11300
Iron(II) chloride	$FeCl_2$	+14750
Iron(II) chloride tetrahydrate	$FeCl_2 \cdot 4H_2O$	+12900
Iron(II) fluoride	FeF_2	+9500
Iron(II) iodide	FeI_2	+13600
Iron(II) oxide	FeO	+7200
Iron(II) sulfate	$FeSO_4$	+12400
Iron(II) sulfate monohydrate	$FeSO_4 \cdot H_2O$	+10500
Iron(II) sulfate heptahydrate	$FeSO_4 \cdot 7H_2O$	+11200
Iron(II) sulfide	FeS	+1074
Iron(III) chloride	$FeCl_3$	+13450
Iron(III) chloride hexahydrate	$FeCl_3 \cdot 6H_2O$	+15250
Iron(III) fluoride	FeF_3	+13760
Iron(III) fluoride trihydrate	$FeF_3 \cdot 3H_2O$	+7870
Iron(III) nitrate nonahydrate	$Fe(NO_3)_3 \cdot 9H_2O$	+15200
Krypton (g)	Kr	−29.0
Lanthanum (α)	La	+95.9
Lanthanum oxide	La_2O_3	−78
Lanthanum sulfate nonahydrate	$La_2(SO_4)_3 \cdot 9H_2O$	−262
Lanthanum sulfide	La_2S_3	−37
Lead	Pb	−23
Lead(II) acetate	$Pb(C_2H_3O_2)_2$	−89.1
Lead(II) bromide	$PbBr_2$	−90.6
Lead(II) carbonate	$PbCO_3$	−61.2
Lead(II) chloride	$PbCl_2$	−73.8
Lead(II) chromate	$PbCrO_4$	−18
Lead(II) fluoride	PbF_2	−58.1
Lead(II) iodate	$Pb(IO_3)_2$	−131
Lead(II) iodide	PbI_2	−126.5
Lead(II) nitrate	$Pb(NO_3)_2$	−74
Lead(II) oxide	PbO	−42
Lead(II) phosphate	$Pb_3(PO_4)_2$	−182
Lead(II) sulfate	$PbSO_4$	−69.7
Lead(II) sulfide	PbS	−83.6
Lithium	Li	+14.2
Lithium bromide	LiBr	−34.3
Lithium carbonate	Li_2CO_3	−27
Lithium chloride	LiCl	−24.3
Lithium fluoride	LiF	−10.1
Lithium hydride	LiH	−4.6
Lithium hydroxide (aq)	LiOH	−12.3
Lithium iodide	LiI	−50
Lithium sulfate	Li_2SO_4	−41.6
Lutetium	Lu	+182.9
Magnesium	Mg	+13.1
Magnesium bromide	$MgBr_2$	−72
Magnesium carbonate	$MgCO_3$	−32.4
Magnesium chloride	$MgCl_2$	−47.4
Magnesium fluoride	MgF_2	−22.7
Magnesium hydroxide	$Mg(OH)_2$	−22.1
Magnesium iodide	MgI_2	−111
Magnesium oxide	MgO	−10.2
Magnesium sulfate	$MgSO_4$	−42
Magnesium sulfate monohydrate	$MgSO_4 \cdot H_2O$	−61
Magnesium sulfate heptahydrate	$MgSO_4 \cdot 7H_2O$	−135.7
Manganese	Mn	+511
Manganese(II) bromide	$MnBr_2$	+13900
Manganese(II) carbonate	$MnCO_3$	+11400
Manganese(II) chloride	$MnCl_2$	+14350
Manganese(II) chloride tetrahydrate	$MnCl_2 \cdot 4H_2O$	+14600
Manganese(II) fluoride	MnF_2	+10700
Manganese(II) hydroxide	$Mn(OH)_2$	+13500

Name	Formula	$\chi_m/10^{-6}$ cm^3 mol^{-1}
Manganese(II) iodide	MnI_2	+14400
Manganese(II) oxide	MnO	+4850
Manganese(II) sulfate	$MnSO_4$	+13660
Manganese(II) sulfate monohydrate	$MnSO_4 \cdot H_2O$	+14200
Manganese(II) sulfate tetrahydrate	$MnSO_4 \cdot 4H_2O$	+14600
Manganese(II) sulfide (α form)	MnS	+5630
Manganese(II) sulfide (β form)	MnS	+3850
Manganese(II,III) oxide	Mn_3O_4	+12400
Manganese(III) fluoride	MnF_3	+10500
Manganese(III) oxide	Mn_2O_3	+14100
Manganese(IV) oxide	MnO_2	+2280
Mercury (s, 234 K)	Hg	−24.1
Mercury (l)	Hg	−33.5
Mercury(I) bromide	Hg_2Br_2	−105
Mercury(I) chloride	Hg_2Cl_2	−120
Mercury(I) fluoride	Hg_2F_2	−106
Mercury(I) iodide	Hg_2I_2	−166
Mercury(I) nitrate	$Hg_2(NO_3)_2$	−121
Mercury(I) oxide	Hg_2O	−76.3
Mercury(I) sulfate	Hg_2SO_4	−123
Mercury(II) bromide	$HgBr_2$	−94.2
Mercury(II) chloride	$HgCl_2$	−82
Mercury(II) cyanide	$Hg(CN)_2$	−67
Mercury(II) fluoride	HgF_2	−57.3
Mercury(II) iodide	HgI_2	−165
Mercury(II) nitrate	$Hg(NO_3)_2$	−74
Mercury(II) oxide	HgO	−46
Mercury(II) sulfate	$HgSO_4$	−78.1
Mercury(II) sulfide	HgS	−55.4
Mercury(II) thiocyanate	$Hg(SCN)_2$	−96.5
Molybdenum	Mo	+72
Molybdenum(III) bromide	$MoBr_3$	+525
Molybdenum(III) chloride	$MoCl_3$	+43
Molybdenum(III) oxide	Mo_2O_3	-42.0
Molybdenum(IV) bromide	$MoBr_4$	+520
Molybdenum(IV) chloride	$MoCl_4$	+1750
Molybdenum(IV) oxide	MoO_2	+41
Molybdenum(V) chloride	$MoCl_5$	+990
Molybdenum(VI) fluoride	MoF_6	−26.0
Molybdenum(VI) oxide	MoO_3	+3
Neodymium (α)	Nd	+5930
Neodymium fluoride	NdF_3	+4980
Neodymium oxide	Nd_2O_3	+10200
Neodymium sulfate	$Nd_2(SO_4)_3$	+9990
Neodymium sulfide	Nd_2S_3	+5550
Neon (g)	Ne	−6.96
Neptunium	Np	+575
Nickel	Ni	Ferro.
Nickel(II) bromide	$NiBr_2$	+5600
Nickel(II) chloride	$NiCl_2$	+6145
Nickel(II) chloride hexahydrate	$NiCl_2 \cdot 6H_2O$	+4240
Nickel(II) fluoride	NiF_2	+2410
Nickel(II) hydroxide	$Ni(OH)_2$	+4500
Nickel(II) iodide	NiI_2	+3875
Nickel(II) nitrate hexahydrate	$Ni(NO_3)_2 \cdot 6H_2O$	+4300
Nickel(II) oxide	NiO	+660
Nickel(II) sulfate	$NiSO_4$	+4005
Nickel(II) sulfide	NiS	+190
Nickel(III) sulfide	Ni_3S_2	+1030
Niobium	Nb	+208
Niobium(V) oxide	Nb_2O_5	−10
Nitrogen (g)	N_2	−12.0
Nitric acid (l)	HNO_3	−19.9
Nitrous oxide (g)	N_2O	−18.9
Nitric oxide (s, 90 K)	NO	+19.8
Nitric oxide (l, 118 K)	NO	+114.2
Nitric oxide (g)	NO	+1461
Nitrogen dioxide (g, 408 K)	NO_2	+150
Nitrogen trioxide (g)	N_2O_3	−16
Nitrogen tetroxide (g)	N_2O_4	−23.0
Osmium	Os	+11
Oxygen (s, 54 K)	O_2	+10200
Oxygen (l, 90 K)	O_2	+7699
Oxygen (g)	O_2	+3449
Ozone (l)	O_3	+6.7
Palladium	Pd	+540
Palladium(II) chloride	$PdCl_2$	−38
Phosphorus (white)	P	−26.66
Phosphorus (red)	P	−20.77
Phosphine (g)	PH_3	−26.2
Phosphoric acid (aq)	H_3PO_4	−43.8
Phosphorous acid (aq)	H_3PO_3	−42.5
Phosphorus(III) chloride (l)	PCl_3	−63.4
Platinum	Pt	+193
Platinum(II) chloride	$PtCl_2$	−54
Platinum(III) chloride	$PtCl_3$	−66.7
Platinum(IV) chloride	$PtCl_4$	−93
Platinum(IV) fluoride	PtF_4	+445
Plutonium	Pu	+525
Plutonium(IV) fluoride	PuF_4	+1760
Plutonium(IV) oxide	PuO_2	+730
Plutonium(VI) fluoride	PuF_6	+173
Potassium	K	+20.8
Potassium bromate	$KBrO_3$	−52.6
Potassium bromide	KBr	−49.1
Potassium carbonate	K_2CO_3	−59
Potassium chlorate	$KClO_3$	−42.8
Potassium chloride	KCl	−38.8
Potassium chromate	K_2CrO_4	−3.9
Potassium cyanide	KCN	−37
Potassium ferricyanide	$K_3Fe(CN)_6$	+2290
Potassium ferrocyanide trihydrate		−172.3
Potassium fluoride	KF	−23.6
Potassium hydrogen sulfate	$KHSO_4$	−49.8
Potassium hydroxide (aq)	KOH	−22
Potassium iodate	KIO_3	−63.1
Potassium iodide	KI	−63.8
Potassium nitrate	KNO_3	−33.7
Potassium nitrite	KNO_2	−23.3
Potassium permanganate	$KMnO_4$	+20
Potassium sulfate	K_2SO_4	−67
Potassium sulfide	K_2S	−60
Potassium superoxide	KO_2	+3230
Potassium thiocyanate	KSCN	−48
Praseodymium (α)	Pr	+5530
Praseodymium chloride	$PrCl_3$	+44.5
Praseodymium oxide	Pr_2O_3	+8994
Praseodymium sulfide	Pr_2S_3	+10770
Protactinium	Pa	+277
Rhenium	Re	+67

Name	Formula	$\chi_m/10^{-6}$ cm^3 mol^{-1}
Rhenium(IV) oxide	ReO_2	+44
Rhenium(IV) sulfide	ReS_2	+38
Rhenium(V) chloride	$ReCl_5$	+1225
Rhenium(VI) oxide	ReO_3	+16
Rhenium(VII) oxide	Re_2O_7	−16
Rhodium	Rh	+102
Rhodium(III) chloride	$RhCl_3$	−7.5
Rhodium(III) oxide	Rh_2O_3	+104
Rubidium	Rb	+17
Rubidium bromide	RbBr	−56.4
Rubidium carbonate	Rb_2CO_3	−75.4
Rubidium chloride	RbCl	−46
Rubidium fluoride	RbF	−31.9
Rubidium iodide	RbI	−72.2
Rubidium nitrate	$RbNO_3$	−41
Rubidium sulfate	Rb_2SO_4	−88.4
Rubidium superoxide	RbO_2	+1527
Ruthenium	Ru	+39
Ruthenium(III) chloride	$RuCl_3$	+1998
Ruthenium(IV) oxide	RuO_2	+162
Samarium (α)	Sm	+1278
Samarium(II) bromide	$SmBr_2$	+5337
Samarium(III) bromide	$SmBr_3$	+972
Samarium(III) oxide	Sm_2O_3	+1988
Samarium(III) sulfate octahydrate	$Sm_2(SO_4)_3{\cdot}8H_2O$	+1710
Samarium(III) sulfide	Sm_2S_3	+3300
Scandium (α)	Sc	+295.2
Selenium	Se	−25
Selenium dioxide	SeO_2	−27.2
Selenium bromide	Se_2Br_2	−113
Selenium chloride (l)	Se_2Cl_2	−94.8
Selenium hexafluoride (g)	SeF_6	−51
Silicon	Si	−3.12
Silane (g)	SiH_4	−20.4
Disilane (g)	Si_2H_6	−37.3
Tetramethylsilane (l)	$(CH_3)_4Si$	−74.80
Tetraethylsilane (l)	$(C_2H_5)_4Si$	−120.2
Tetrabromosilane (l)	$SiBr_4$	−126
Tetrachlorosilane (l)	$SiCl_4$	−87.5
Silicon carbide	SiC	−12.8
Silicon dioxide	SiO_2	−29.6
Silver	Ag	−19.5
Silver(I) bromide	AgBr	−61
Silver(I) carbonate	Ag_2CO_3	−80.90
Silver(I) chloride	AgCl	−49
Silver(I) chromate	Ag_2CrO_4	−40
Silver(I) cyanide	AgCN	−43.2
Silver(I) fluoride	AgF	−36.5
Silver(I) iodide	AgI	−80
Silver(I) nitrate	$AgNO_3$	−45.7
Silver(I) nitrite	$AgNO_2$	−42
Silver(I) oxide	Ag_2O	−134
Silver(I) phosphate	Ag_3PO_4	−120
Silver(I) sulfate	Ag_2SO_4	−92.90
Silver(I) thiocyanate	AgSCN	−61.8
Silver(II) oxide	AgO	−19.6
Sodium	Na	+16
Sodium acetate	$NaC_2H_3O_2$	−37.6
Sodium bromate	$NaBrO_3$	−44.2
Sodium bromide	NaBr	−41
Sodium carbonate	Na_2CO_3	−41
Sodium chlorate	$NaClO_3$	−34.7
Sodium chloride	NaCl	−30.2
Sodium dichromate	$Na_2Cr_2O_7$	+55
Sodium fluoride	NaF	−15.6
Sodium hydrogen phosphate	Na_2HPO_4	−56.6
Sodium hydroxide (aq)	NaOH	−15.8
Sodium iodate	$NaIO_3$	−53
Sodium iodide	NaI	−57
Sodium nitrate	$NaNO_3$	−25.6
Sodium nitrite	$NaNO_2$	−14.5
Sodium oxide	Na_2O	−19.8
Sodium peroxide	Na_2O_2	−28.10
Sodium sulfate	Na_2SO_4	−52
Sodium sulfate decahydrate	$Na_2SO_4{\cdot}10H_2O$	−184
Sodium sulfide	Na_2S	−39
Sodium tetraborate	$Na_2B_4O_7$	−85
Strontium	Sr	+92
Strontium bromide	$SrBr_2$	−86.6
Strontium bromide hexahydrate	$SrBr_2{\cdot}6H_2O$	−160
Strontium carbonate	$SrCO_3$	−47
Strontium chlorate	$Sr(ClO_3)_2$	−73
Strontium chloride	$SrCl_2$	−61.5
Strontium chloride hexahydrate	$SrCl_2{\cdot}6H_2O$	−145
Strontium chromate	$SrCrO_4$	−5.1
Strontium fluoride	SrF_2	−37.2
Strontium hydroxide	$Sr(OH)_2$	−40
Strontium iodate	$Sr(IO_3)_2$	−108
Strontium iodide	SrI_2	−112
Strontium nitrate	$Sr(NO_3)_2$	−57.2
Strontium oxide	SrO	−35
Strontium peroxide	SrO_2	−32.3
Strontium sulfate	$SrSO_4$	−57.9
Sulfur (rhombic)	S	−15.5
Sulfur (monoclinic)	S	−14.9
Sulfuric acid (l)	H_2SO_4	−39
Sulfur dioxide (g)	SO_2	−18.2
Sulfur trioxide (l)	SO_3	−28.54
Sulfur chloride (l)	$SSCl_2$	−62.2
Sulfur dichloride (l)	SCl_2	−49.4
Sulfur hexafluoride (g)	SF_6	−44
Thionyl chloride (l)	$SOCl_2$	−44.3
Tantalum	Ta	+154
Tantalum(V) chloride	$TaCl_5$	+140
Tantalum(V) oxide	Ta_2O_5	−32
Technetium	Tc	+115
Tellurium	Te	−38
Tellurium dibromide	$TeBr_2$	−106
Tellurium dichloride	$TeCl_2$	−94
Tellurium hexafluoride (g)	TeF_6	−66
Terbium (α)	Tb	+170000
Terbium oxide	Tb_2O_3	+78340
Thallium	Tl	−50
Thallium(I) bromate	$TlBrO_3$	−75.9
Thallium(I) bromide	TlBr	−63.9
Thallium(I) carbonate	Tl_2CO_3	−101.6
Thallium(I) chlorate	$TlClO_3$	−65.5
Thallium(I) chloride	TlCl	−57.8
Thallium(I) chromate	Tl_2CrO_4	−39.3
Thallium(I) cyanide	TlCN	−49

Name	Formula	$\chi_m/10^{-6}$ cm^3 mol^{-1}
Thallium(I) fluoride	TlF	−44.4
Thallium(I) iodate	$TlIO_3$	−86.8
Thallium(I) iodide	TlI	−82.2
Thallium(I) nitrate	$TlNO_3$	−56.5
Thallium(I) nitrite	$TlNO_2$	−50.8
Thallium(I) sulfate	Tl_2SO_4	−112.6
Thallium(I) sulfide	Tl_2S	−88.8
Thorium	Th	+97
Thorium(IV) oxide	ThO_2	−16
Thulium	Tm	+24700
Thulium oxide	Tm_2O_3	+51444
Tin (gray)	Sn	−37.4
Tin(II) chloride	$SnCl_2$	−69
Tin(II) chloride dihydrate	$SnCl_2{\cdot}2H_2O$	−91.4
Tin(II) oxide	SnO	−19
Tin(IV) bromide	$SnBr_4$	−149
Tin(IV) chloride (l)	$SnCl_4$	−115
Tin(IV) oxide	SnO_2	−41
Titanium	Ti	+151
Titanium(II) bromide	$TiBr_2$	+720
Titanium(II) chloride	$TiCl_2$	+484
Titanium(II) iodide	TiI_2	+1790
Titanium(II) sulfide	TiS	+432
Titanium(III) bromide	$TiBr_3$	+660
Titanium(III) chloride	$TiCl_3$	+1110
Titanium(III) fluoride	TiF_3	+1300
Titanium(III) oxide	Ti_2O_3	+132
Titanium(IV) chloride	$TiCl_4$	−54
Titanium(IV) oxide	TiO_2	+5.9
Tungsten	W	+53
Tungsten carbide	WC	+10
Tungsten(II) chloride	WCl_2	−25
Tungsten(IV) oxide	WO_2	+57
Tungsten(IV) sulfide	WS_2	+5850
Tungsten(V) bromide	WBr_5	+270
Tungsten(V) chloride	WCl_5	+387
Tungsten(VI) chloride	WCl_6	−71
Tungsten(VI) fluoride (g)	WF_6	−53
Tungsten(VI) oxide	WO_3	−15.8
Uranium	U	+409
Uranium(III) bromide	UBr_3	+4740
Uranium(III) chloride	UCl_3	+3460
Uranium(III) hydride	UH_3	+6244
Uranium(III) iodide	UI_3	+4460
Uranium(IV) bromide	UBr_4	+3530
Uranium(IV) chloride	UCl_4	+3680
Uranium(IV) fluoride	UF_4	+3530
Uranium(IV) oxide	UO_2	+2360
Uranium(VI) fluoride	UF_6	+43
Uranium(VI) oxide	UO_3	+128
Vanadium	V	+285
Vanadium(II) bromide	VBr_2	+3230
Vanadium(II) chloride	VCl_2	+2410
Vanadium(III) bromide	VBr_3	+2910
Vanadium(III) chloride	VCl_3	+3030
Vanadium(III) fluoride	VF_3	+2757
Vanadium(III) oxide	V_2O_3	+1976
Vanadium(III) sulfide	V_2S_3	+1560
Vanadium(IV) chloride	VCl_4	+1215
Vanadium(IV) oxide	VO_2	+99
Vanadium(V) oxide	V_2O_5	+128
Water (s, 273 K)	H_2O	−12.63
Water (l, 293 K)	H_2O	−12.96
Water (l, 373 K)	H_2O	−13.09
Water (g, 373 K))	H_2O	−13.1
Xenon (g)	Xe	−45.5
Ytterbium (β)	Yb	+67
Yttrium (α)	Y	+187.7
Yttrium oxide	Y_2O_3	+44.4
Yttrium sulfide	Y_2S_3	+100
Zinc	Zn	−9.15
Zinc carbonate	$ZnCO_3$	−34
Zinc chloride	$ZnCl_2$	−55.33
Zinc cyanide	$Zn(CN)_2$	−46
Zinc fluoride	ZnF_2	−34.3
Zinc hydroxide	$Zn(OH)_2$	−67
Zinc iodide	ZnI_2	−108
Zinc oxide	ZnO	−27.2
Zinc phosphate	$Zn_3(PO_4)_2$	−141
Zinc sulfate	$ZnSO_4$	−47.8
Zinc sulfate monohydrate	$ZnSO_4{\cdot}H_2O$	−63
Zinc sulfate heptahydrate	$ZnSO_4{\cdot}7H_2O$	−138
Zinc sulfide	ZnS	−25
Zirconium	Zr	+120
Zirconium carbide	ZrC	−26
Zirconium nitrate pentahydrate	$Zr(NO_3)_4{\cdot}5H_2O$	−77
Zirconium(IV) oxide	ZrO_2	−13.8

INDEX OF REFRACTION OF INORGANIC LIQUIDS

This table gives the index of refraction n of several inorganic substances in the liquid state at specified temperatures. The measurements refer to ambient atmospheric pressure except for substances whose normal boiling points are greater than the indicated temperature; in this case the pressure is the saturated vapor pressure of the substance. All values refer to a wavelength of 589 nm unless otherwise indicated. Entries are arranged in alphabetical order by chemical formula as normally written.

Data on the index of refraction at other temperatures and wavelengths may be found in Reference 1.

References

1. Wohlfarth, C., and Wohlfarth, B., *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series*, III/38A, Martienssen, W., Editor, Springer-Verlag, Heidelberg, 1996.
2. Francis, A.W., *J. Chem. Eng. Data*, 5, 534, 1960.

Formula	Name	t/°C	n
Ar	Argon	−188	1.2312
$AsCl_3$	Arsenic(III) chloride	16	1.604
BBr_3	Boron tribromide	16	1.312
BrF_3	Bromine trifluoride	25	1.4536
BrF_5	Bromine pentafluoride	25	1.3529
Br_2	Bromine	15	1.659
COS	Carbon oxysulfide	25	1.3506
CO_2	Carbon dioxide	24	1.6630
CS_2	Carbon disulfide	20	1.62774
C_3O_2	Carbon suboxide	0	1.453
Cl_2	Chlorine	20	1.3834
CrO_2Cl_2	Chromyl chloride	23	1.524
$Fe(CO)_5$	Iron pentacarbonyl	14	1.523
$GeBr_4$	Germanium(IV) bromide	26	1.6269
$GeCl_4$	Germanium(IV) chloride	25	1.4614
HBr	Hydrogen bromide	10	1.325
HCN	Hydrogen cyanide	20	1.26136
HCl	Hydrogen chloride	18	1.3287 [a]
$HClO_4$	Perchloric acid	50	1.3819
HF	Hydrogen fluoride	25	1.1574
HI	Hydrogen iodide	16	1.466
HNO_3	Nitric acid	25	1.393
H_2	Hydrogen	−253	1.1096
H_2O	Water	20	1.33336
H_2O_2	Hydrogen peroxide	28	1.4061
H_2S	Hydrogen sulfide	−80	1.460
		20	1.3682
H_2SO_4	Sulfuric acid	20	1.4183
H_2S_2	Hydrogen disulfide	20	1.630
He	Helium	−269	1.02451 [c]
Kr	Krypton	−157	1.3032 [c]
NH_3	Ammonia	−77	1.3944 [b]
		20	1.3327
NO	Nitric oxide	−90	1.330
N_2	Nitrogen	−196	1.19876 [b]
N_2H_4	Hydrazine	22	1.470
N_2O	Nitrous oxide	25	1.238
O_2	Oxygen	−183	1.2243 [c]
PBr_3	Phosphorus(III) bromide	25	1.687
PCl_3	Phosphorus(III) chloride	21	1.5122
PH_3	Phosphine	17	1.317
P_2O_3	Phosphorus(III) oxide	27	1.540
S	Sulfur	125	1.9170
SCl_2	Sulfur dichloride	14	1.557
SF_6	Sulfur hexafluoride	25	1.167
$SOCl_2$	Thionyl chloride	10	1.527
SO_2	Sulfur dioxide	25	1.3396
SO_2Cl_2	Sulfuryl chloride	12	1.444
SO_3	Sulfur trioxide	20	1.40965
$SSCl_2$	Sulfur chloride	20	1.671
$SbCl_5$	Antimony(V) chloride	22	1.5925
$SiBr_4$	Tetrabromosilane	31	1.5685
$SiCl_4$	Tetrachlorosilane	25	1.41156
$SnBr_4$	Tin(IV) bromide	31	1.6628
$SnCl_4$	Tin(IV) chloride	25	1.5086
$TiCl_4$	Titanium(IV) chloride	18	1.6076
Xe	Xenon	−112	1.3918 [c]

[a] At 581 nm
[b] At 578 nm
[c] At 546 nm

PHYSICAL AND OPTICAL PROPERTIES OF MINERALS

The chemical formula, crystal system, density, hardness, and index of refraction of some common minerals are given in this table. Entries are arranged alphabetically by mineral name. The columns are:

- **Formula:** Chemical formula for a typical sample of the mineral. Composition often varies considerably with the origin of the sample.
- **Crystal system:** tricl = triclinic; monocl = monoclinic; orth = orthorhombic; tetr = tetragonal; hex = hexagonal; rhomb = rhombohedral; cub = cubic.
- **Density:** Typical density in g/cm^3. Individual samples may vary by a few percent.
- **Hardness:** On the Mohs' scale (range of 1 to 10, with talc = 1 and diamond = 10).
- **Index of refraction:** Values are given for the three coordinate axes in the order of least, intermediate, and greatest index. For cubic crystals there is only a single value. See Reference 1 for details on the axis systems. Variations of several percent, depending on the origin and exact composition of the sample, are common.

References

1. Deer, W. A., Howie, R. A., and Zussman, J., *An Introduction to the Rock-Forming Minerals*, 2nd Edition, Longman Scientific & Technical, Harlow, Essex, 1992.
2. Carmichael, R. S., *Practical Handbook of Physical Properties of Rocks and Minerals*, CRC Press, Boca Raton, FL, 1989.
3. Donnay, J. D. H., and Ondik, H. M., *Crystal Data Determinative Tables, Third Edition, Volume 2, Inorganic Compounds*, Joint Committee on Powder Diffraction Standards, Swarthmore, PA, 1973.

Name	Formula	Crystal system	Density g/cm^3	Hardness	Index of refraction n_α	n_β	n_γ
Acanthite	Ag_2S	orth	7.2	2.3			
Actinolite	$Ca_2(Mg,Fe)_5Si_8O_{22}(OH,F)_2$	monocl	3.23	5.5	1.624	1.655	1.664
Aegirine	$NaFe(SiO_3)_2$	monocl	3.58	6	1.763	1.800	1.815
Akermanite	$Ca_2MgSi_2O_7$	tetr	2.94	5.5	1.632	1.640	
Alabandite	MnS	cub	4.0	3.8			
Albite	$NaAlSi_3O_8$	tricl	2.63	6.3	1.527	1.531	1.538
Allanite	$(Ca,Mn,Ce,La,Y,Th)_2(Fe,Ti)(Al,Fe)O{\cdot}OH(Si_2O_7)(SiO_4)$	monocl	3.8	5.8	1.75	1.78	1.80
Allemontite	SbAs	hex	6.0	3.5			
Almandine	$Fe_3Al_2Si_3O_{12}$	cub	4.32	6.8	1.830		
Altaite	PbTe	cub	8.16	3			
Aluminite	$Al_2(SO_4)(OH)_4{\cdot}7H_2O$	monocl	1.74	1.5	1.459	1.464	1.470
Alunite	$(K,Na)Al_3(SO_4)_2(OH)_6$	rhomb	2.8	3.8	1.572	1.592	
Alunogen	$Al_2(SO_4)_3{\cdot}18H_2O$	monocl	1.69	1.8	1.467	1.47	1.478
Amblygonite	$(Li,Na)Al(PO_4)(F,OH)$	tricl	3.1	5.8	1.591	1.604	1.613
Analcite	$NaAlSi_2O_6{\cdot}H_20$	cub	2.27	5.5	1.486		
Anatase	TiO_2	tetr	4.23	5.8	2.488	2.561	
Andalusite	Al_2OSiO_4	orth	3.15	7.5	1.635	1.639	1.644
Andesine	$NaAlSi_3O_8{\cdot}CaAl_2Si_2O_8$	tricl	2.67	6.3	1.550	1.553	1.557
Andorite	$PbAgSb_3S_6$	rhomb	5.35	3.3			
Andradite	$Ca_3(Fe,Ti)_2Si_3O_{12}$	cub	3.86	6.8	1.887		
Anglesite	$PbSO_4$	orth	6.29	2.8	1.877	1.883	1.894
Anhydrite	$CaSO_4$	orth	2.96	3.5	1.570	1.575	1.614
Ankerite	$Ca(Fe,Mg,Mn)(CO_3)_2$	rhomb	3.0	3.8	1.529	1.720	
Anorthite	$CaAl_2Si_2O_8$	tricl	2.76	6.3	1.577	1.585	1.590
Anorthoclase	$(Na,K)AlSi_3O_8$	tricl	2.58	6	1.523	1.528	1.529
Anthophyllite	$(Mg,Fe)_7Si_8O_{22}(OH,F)_2$	rhomb	3.21	5.8	1.645	1.658	1.668
Apatite	$Ca_5(PO_4)_3(OH,F,Cl)$	hex	3.2	5	1.645	1.648	
Apophyllite	$KFCa_4Si_8O_{20}{\cdot}8H_2O$	tetr	2.35	4.8	1.535	1.536	
Aragonite	$CaCO_3$	orth	2.83	3.5	1.531	1.680	1.686
Arcanite	K_2SO_4	orth	2.66		1.494	1.494	1.497
Argentite	Ag_2S	orth	7.2	2.3			
Arsenolite	As_2O_3	cub	3.86	1.5	1.755		
Arsenopyrite	FeAsS	monocl	6.1	5.8			
Atacamite	$Cu_2(OH)_3Cl$	rhomb	3.76	3.3	1.831	1.861	1.880
Augelite	$Al_2(PO_4)(OH)_3$	monocl	2.70	4.8	1.574	1.576	1.588
Augite	$(Ca,Mg,Fe,Ti,Al)_2(Si,Al)_2O_6$	monocl	3.38	6	1.703	1.707	1.738
Autunite	$Ca(UO_{22})(PO_4)_2{\cdot}10H20$	tetr	3.2	2.3	1.553	1.577	
Axinite	$(Ca,Mn,Fe)_3Al_2BO_3Si_4O_{12}(OH)$	tricl	3.31	6.8	1.684	1.691	1.694

Name	Formula	Crystal system	Density g/cm^3	Hardness	Index of refraction n_α	n_β	n_γ
Azurite	$Cu_3(OH)_2(CO_3)_2$	monocl	3.77	3.8	1.730	1.758	1.838
Baddeleyite	ZrO_2	monocl	5.7	6.5	2.13	2.19	2.20
Barite	$BaSO_4$	orth	4.49	3.3	1.636	1.637	1.648
Benitoite	$BaTi(SiO_3)_3$	rhomb	3.65	6.3	1.757	1.804	
Bertrandite	$Be_4Si_2O_7(OH)_2$	rhomb	2.6	6	1.589	1.602	1.613
Beryl	$Be_3Al_2(SiO_3)_6$	hex	2.64	7.8	1.582	1.589	
Beryllonite	$NaBe(PO)_4$	monocl	2.81	5.8	1.552	1.558	1.561
Biotite	$K(Mg,Fe)_3AlSi_3O_{10}(OH,F)_2$	monocl	3.0	2.8	1.595	1.651	1.651
Bismuthinite	Bi_2S_3	orth	6.78	2			
Bixbyite	$(Mn,Fe)_2O_3$	cub	4.95	6.3			
Bloedite	$Na_2Mg(SO_4)_2{\cdot}4H_2O$	monocl	2.25	2.8	1.483	1.486	1.487
Boehmite	$AlO(OH)$	orth	3.44	3.8	1.64	1.65	1.66
Boracite	$Mg_3B_7O_{13}Cl$	rhomb	2.94	7.3	1.66	1.66	1.67
Borax	$Na_2B_4O_7{\cdot}10H_2O$	monocl	1.73	2.3	1.447	1.469	1.472
Bornite	Cu_5FeS_4	cub	5.07	3			
Boulangerite	$Pb_5Sb_4S_{11}$	monocl	6.1	2.8			
Bournonite	$PbCuSbS_3$	rhomb	5.83	2.8			
Braggite	PtS	tetr	10.2				
Braunite	$(Mn,Si)_2O_3$	tetr	4.78	6.3			
Bravoite	$(Ni,Fe)S_2$	cub	4.62	5.8			
Breithauptite	$NiSb$	hex	≈8.7	5.5			
Brochantite	$Cu_4(SO_4)(OH)_6$	monocl	3.79	3.8	1.728	1.771	1.800
Bromyrite	$AgBr$	cub	6.47	2.5	2.253		
Brookite	TiO_2	orth	4.23	5.8	2.583	2.584	2.700
Brucite	$Mg(OH)_2$	hex	2.37	2.5	1.575	1.59	
Bunsenite	NiO	cub	6.72	5.5			
Cacoxenite	$Fe_4(PO_4)_3(OH)_3{\cdot}12H_20$	hex	2.3	3.5	1.580	1.646	
Calcite	$CaCO_3$	hex	2.71	3	1.486	1.658	
Caledonite	$Cu_2Pb_5(SO_4)_3(CO_3)(OH)_6$	rhomb	5.76	2.8	1.818	1.866	1.909
Calomel	Hg_2Cl_2	tetr	7.16	1.5	1.973	2.656	
Cancrinite	$(Na,Ca,K)_7[Al_6Si_6O_{24}](CO_3,SO_4,Cl,OH)_2{\cdot}H_20$	hex	2.42	5.5	1.495	1.509	
Carnalite	$KMgCl_3{\cdot}6H_20$	rhomb	1.60	2.5	1.466	1.475	1.494
Carnotite	$K_2(UO_2)_2(VO_4)_2{\cdot}3H_2O$	rhomb		1.5	1.75	1.92	1.95
Cassiterite	SnO_2	tetr	6.85	6.5	2.006	2.097	
Celestite	$SrSO_4$	orth	3.96	3.3	1.622	1.624	1.631
Celsian	$BaAl_2Si_2O_8$	monocl	3.25	6.3	1.583	1.588	1.594
Cerargyrite	$AgCl$	cub	5.56	2.5	2.071		
Cerussite	$PbCO_3$	orth	6.6	3.3	1.804	2.076	2.079
Cervantite	Sb_2O_4	orth	6.64	4.5			
Chabazite	$Ca[Al_2Si_4O_{12}]{\cdot}6H_2O$	trig	2.08	4.5	1.482		
Chalcanthite	$CuSO_4{\cdot}5H_2O$	tricl	2.29	2.5	1.514	1.537	1.543
Chalcocite	Cu_2S	orth	5.6	2.8			
Chalcopyrite	$CuFeS_2$	tetr	4.2	3.8			
Chiolite	$Na_5Al_3F_{14}$	tetr	3.00	3.8	1.342	1.349	
Chlorite	$(Mg,Al,Fe)_{12}(Si,Al)_8O_{20}(OH)_{16}$	monocl	3.0	2.5	1.61	1.62	1.62
Chloritoid	$FeAl_4O_2(SiO_4)_2(OH)_4$	monocl	3.66	6.5	1.717	1.721	1.726
Chondrodite	$Mg(OH,F)_2{\cdot}2Mg_2SiO_4$	monocl	3.21	6.5	1.604	1.615	1.634
Chromite	$FeCr_2O_4$	cub	5.0	5.5	2.16		
Chrysoberyl	$BeAl_2O_4$	orth	3.65	8.5	1.746	1.748	1.756
Chrysocolla	$CuSiO_3{\cdot}2H_2O$	rhomb	2.4	2	1.575	1.597	1.598
Cinnabar	HgS	hex	8.17	2.3	2.814	3.143	
Claudetite	As_2O_3	monocl	3.74	2.5	1.87	1.92	2.01
Clinohumite	$Mg(OH,F)_2{\cdot}4Mg_2SiO_4$	monocl	3.21	6	1.633	1.647	1.668
Clinozoisite	$Ca_2Al_3Si_3O_{12}(OH)$	monocl	3.30	6.5	1.693	1.700	1.712
Cobaltite	$CoAsS$	cub	≈6.1	5.5			
Colemanite	$Ca_2B_6O_{11}{\cdot}5H_2O$	monocl	2.42	4.5	1.586	1.592	1.614
Columbite	$(Fe,Mn)(Nb,Ta)_2O_6$	rhomb	5.20	6			
Connellite	$Cu_{19}(SO_4)Cl_4(OH)_{32}{\cdot}3H_2O$	hex	3.36	3	1.731	1.752	
Copiapite	$(Fe,Mg)Fe_4(SO_4)_6(OH)_2{\cdot}20H_2O$	tricl	2.13	2.8	1.52	1.54	1.59
Coquimbite	$Fe_2(SO_4)_3{\cdot}9H_2O$	hex	2.1	2.5	1.54	1.56	

Name	Formula	Crystal system	Density g/cm^3	Hardness	Index of refraction n_α	n_β	n_γ
Cordierite	$Al_3(Mg,Fe)_2Si_5AlO_{18}$	rhomb	2.66	7	1.540	1.549	1.553
Corundum	Al_2O_3	hex	3.97	9	1.761	1.769	
Cotunnite	$PbCl_2$	orth	5.98	2.5	2.199	2.217	2.260
Covellite	CuS	hex	4.8	1.8			
Cristobalite	SiO_2	hex	2.33	6.5	1.484	1.487	
Crocoite	$PbCrO_4$	monocl	6.12	2.8	2.29	2.36	2.66
Cryolite	Na_3AlF_6	monocl	2.97	2.5	1.338	1.338	1.339
Cryolithionite	$Na_3Li_3Al_2F_{12}$	cub	2.77	2.8	1.340		
Cubanite	$CuFe_2S_3$	rhomb	4.11	3.5			
Cummingtonite	$(Mg,Fe)_7Si_8O_{22}(OH)_2$	monocl	3.4	5.5	1.650	1.660	1.676
Cuprite	Cu_2O	cub	6.0	3.8			
Danburite	$CaSi_2B_2O_8$	rhomb	3.0	7	1.63	1.63	1.63
Datolite	$CaBSiO_4(OH)$	monocl	2.98	5.3	1.624	1.652	1.668
Daubreelite	Cr_2FeS_4	cub	3.81				
Derbylite	$Fe_6Ti_6Sb_2O_{23}$	rhomb	4.53	5	2.45	2.45	2.51
Diamond	C	cub	3.51	10	2.418		
Diaspore	AlO(OH)	orth	3.4	6.8	1.694	1.715	1.741
Digenite	$Cu_{2-x}S$	cub	5.55	2.8			
Diopside	$CaMgSi_2O_6$	monocl	3.30	6	1.680	1.687	1.708
Dioptase	$CuSiO_2(OH)_2$	rhomb	3.5	5	1.65	1.70	
Dolomite	$CaMg(CO_3)_2$	rhomb	2.86	3.5	1.500	1.679	
Douglasite	$K_2FeCl_4{\cdot}2H_2O$	orth	2.16		1.488	1.500	
Dyscrasite	Ag_3Sb	rhomb	9.74	3.8			
Eddingtonite	$BaAl_2Si_3O_{10}{\cdot}4H_2O$	rhomb	2.8		1.541	1.553	1.557
Eglestonite	Hg_4OCl_2	cub	8.4	2.5	2.49		
Emplectite	$CuBiS_2$	rhomb	6.38	2			
Enargite	Cu_3AsS_4	rhomb	4.5	3			
Enstatite	$MgSiO_3$	monocl	3.19	5.5	1.656	1.662	1.669
Epidote	$Ca_2Al_2(Al,Fe)OH(SiO_4)_3$	monocl	3.44	6	1.733	1.755	1.765
Epsomite	$MgSO_4{\cdot}7H_2O$	orth	1.67	2.3	1.433	1.455	1.461
Erythrite	$(Co,Ni)_3(AsO_4)_2{\cdot}8H_2O$	monocl	3.06	2	1.626	1.661	1.699
Eucairite	CuAgSe	orth	7.7	2.5			
Euclasite	$BeAlSiO_4(OH)$	monocl	3.1	7.5	1.651	1.655	1.671
Eudialite	$(Na,Ca,Ce)_5(Fe,Mn)(Zr,Ti)(Si_3O_9)_2$ (OH,Cl)	hex	3.0	5.5	1.623	1.600	1.615
Eulytite	$Bi_4Si_3O_{12}$	cub	6.6	4.5	2.05		
Euxenite	$(Y,Ca,Ce,U,Th)(Nb,Ta,Ti)_2O_6$	rhomb	5.5	6	2.2		
Fayalite	Fe_2SiO_4	orth	4.30	6.5	1.827	1.869	1.879
Ferberite	$FeWO_4$	monocl	7.51	4.3			
Fergussonite	$(Y,Er,Ce,Fe)(Nb,Ta,Ti)O_4$	tetr	5.7	6	2.1		
Fluorite	CaF_2	cub	3.18	4	1.434		
Forsterite	Mg_2SiO_4	orth	3.21	7	1.635	1.651	1.670
Franklinite	$ZnFe_2O_4$	cub	5.21	6	2.36		
Gahnite	$ZnAl_2O_4$	cub	4.62	7.8	1.805		
Galaxite	$MnAl_2O_4$	cub	4.04	7.8	1.92		
Galena	PbS	cub	7.60	2.5	3.91		
Galenabismuthite	$PbBi_2S_4$	rhomb	7.04	3			
Ganomalite	$(Ca,Pb)_{10}(OH,Cl)_2(Si_2O_7)_3$	hex	5.6	3.5	1.910	1.945	
Gaylussite	$Na_2Ca(CO_3)_2{\cdot}5H_2O$	monocl	1.99	2.8	1.444	1.516	1.523
Gehlenite	$Ca_2Al_2SiO_7$	tetr	3.04	5.5	1.658	1.669	
Geikielite	$MgTiO_3$	hex	3.85	5.5	1.95	2.31	
Gibbsite	$Al(OH)_3$	monocl	2.42	3	1.57	1.57	1.59
Glauberite	$Na_2Ca(SO_4)_2$	monocl	2.80	2.8	1.515	1.535	1.536
Glauconite	$(K,Na,Ca)_{1.6}(Fe,Al,Mg)_{4.0}Si_{7.3}Al_{0.7}O_{20}(OH)_4$	monocl	2.7	2	1.60	1.63	1.63
Glaucophane	$Na_2Mg_3Al_2Si_8O_{22}(OH)_2$	monocl	3.19	6	1.634	1.645	1.648
Gmelinite	$(Ca,Na_2)[Al_2Si_4O_{12}]{\cdot}6H_2O$	hex	2.10	4.5	1.477	1.485	
Goethite	FeO(OH)	orth	4.3	5.3	2.268	2.401	2.457
Goslarite	$ZnSO_4{\cdot}7H_2O$	orth	1.97	2.3	1.457	1.480	1.484
Greenockite	CdS	hex	4.8	3.3	2.506	2.529	
Grossularite	$Ca_3Al_2Si_3O_{12}$	cub	3.59	6.8	1.734		
Gummite	$UO_3{\cdot}H_2O$	orth	7.05	3.8			

Name	Formula	Crystal system	Density g/cm^3	Hardness	Index of refraction n_α	n_β	n_γ
Gypsum	$CaSO_4{\cdot}2H_2O$	monocl	2.32	2	1.520	1.525	1.530
Halite	$NaCl$	cub	2.17	2	1.544		
Hambergite	$Be_2(OH)(BO_3)$	rhomb	2.36	7.5	1.56	1.59	1.63
Hanksite	$Na_{22}K(SO_4)_9(CO_3)_2Cl$	hex	2.56	3.3	1.461	1.481	
Harmotome	$Ba[Al_2Si_6O_{16}]{\cdot}6H_2O$	monocl	2.44	4.5	1.506	1.507	1.511
Hausmannite	Mn_3O_4	tetr	4.84	5.5	2.15	2.46	
Haüyne	$(Na,Ca)_{4\text{-}8}Al_6Si_6O_{24}(SO_4,S)_{1\text{-}2}$	cub	2.47	5.8	1.502		
Hedenbergite	$CaFeSi_2O_6$	monocl	3.53	6	1.721	1.727	1.746
Helvite	$Mn_4Be_3Si_3O_{12}S$	cub	3.32	6	1.739		
Hematite	Fe_2O_3	hex	5.25	6	2.91	3.19	
Hemimorphite	$Zn_4Si_2O_7(OH)_2{\cdot}H_2O$	rhomb	3.45	5	1.614	1.617	1.636
Hercynite	$Fe(AlO_2)_2$	cub	4.3	7.8	1.835		
Herderite	$CaBe(PO_4)(Fe,OH)$	monocl	2.98	5.3	1.592	1.612	1.621
Hessite	Ag_2Te	orth	8.4	2.5			
Heulandite	$(Ca,Na_2,K_2)[Al_2Si_7O_{18}]{\cdot}6H_2O$	monocl	2.2	3.8	1.498	1.498	1.506
Hopeite	$Zn_3(PO_4)_2{\cdot}4H_2O$	orth	3.0	3.2	1.58	1.59	1.59
Hornblende	$Ca_2(Mg,Fe)_4Al(Si_7AlO_{22})(OH)_2$	monocl	3.24	5.5	1.67	1.67	1.69
Huebnerite	$MnWO_4$	monocl	7.2	4.3	2.17	2.22	2.32
Humite	$Mg(OH,F)_2{\cdot}3Mg_2SiO_4$	orth	3.3	6	1.625	1.636	1.657
Huntite	$Mg_3Ca(CO_3)_4$	trig	2.70				
Hydrogrossularite	$Ca_3Al_2Si_2O_8(SiO_4)_{1\text{-}m}(OH)_{4m}$	cub	3.4	6.8	1.70		
Hydromagnesite	$3MgCO_3{\cdot}Mg(OH)_2{\cdot}3H_2O$	monocl	2.24	3.5	1.523	1.527	1.545
Illite	$KAl_4[Si_7AlO_{20}](OH)_4$	monocl	2.8	1.5	1.56	1.59	1.59
Ilmenite	$FeTiO_3$	rhomb	4.72	5.5			
Iodyrite	AgI	hex	5.68	1.5	2.21	2.22	
Jacobsite	$MnFe_2O_4$	cub	4.87	7.8	2.3		
Jadeite	$NaAlSi_2O_6$	monocl	3.34	6	1.649	1.654	1.663
Jamesonite	$Pb_4FeSb_6S_{14}$	monocl	5.63	2.5			
Jarosite	$KFe_3(SO_4)_2(OH)_6$	rhomb	3.09	3	1.715	1.820	
Kainite	$KMg(SO_4)Cl{\cdot}3H_2O$	monocl	2.15	2.8	1.494	1.505	1.516
Kaliophylite	$KAlSiO_4$	hex	2.61	6	1.532	1.537	
Kaolinite	$Al_4Si_4O_{10}(OH)_8$	tricl	2.65	2.3	1.549	1.564	1.565
Kernite	$Na_2B_4O_7{\cdot}4H_2O$	monocl	1.95	2.5	1.454	1.472	1.488
Kieserite	$MgSO_4{\cdot}H_2O$	monocl	2.57	3.5	1.520	1.533	1.584
Kyanite	Al_2OSiO_4	tricl	3.59	6.3	1.715	1.722	1.731
Lanarkite	$Pb_2(SO_4)O$	monocl	6.92	2.3	1.928	2.007	2.036
Lanthanite	$(La,Ce)_2(CO_3)_3{\cdot}8H_2O$	rhomb	2.72	2.8	1.52	1.587	1.613
Laumontite	$Ca_4[Al_8Si_{16}O_{48}]{\cdot}16H_2O$	monocl	2.3	3.3	1.508	1.517	1.519
Laurionite	$Pb(OH)Cl$	rhomb	6.24	3.3	2.08	2.12	2.16
Lawsonite	$CaAl_2(OH)_2Si_2O_7{\cdot}H_2O$	rhomb	3.08	6	1.655	1.675	1.685
Lazulite	$(Mg,Fe)Al_2(PO_4)_2(OH)_2$	monocl	3.23	5.8	1.615	1.64	1.650
Lazurite	$Na_4SSi_3Al_3O_{12}$	cub	2.42	5.3	1.500		
Leadhillite	$Pb_4(SO_4)(CO_3)_2(OH)_2$	monocl	6.55	2.8	1.87	2.00	2.01
Lepidocrocite	$FeO(OH)$	orth	4.26	5	1.94	2.20	2.51
Lepidolite	$K_2(Li,Al)_{5\text{-}6}[Si_{6\text{-}7}Al_{2\text{-}1}O_{20}](OH,F)_4$	monocl	2.85	3.3	1.536	1.565	1.566
Leucite	$KAlSi_2O_6$	tetr	2.49	5.8	1.510		
Levyne	$(Ca,Na_2)Al_2Si_4O_{12}{\cdot}6H_2O$	rhomb	2.10	4.5	1.496	1.501	
Litharge	PbO	tetr	9.35	2	2.535	2.665	
Loellingite	$FeAs_2$	rhomb	7.40	5.3			
Maghemite	Fe_2O_3	cub	4.88	7.8	2.63		
Magnesite	$MgCO_3$	hex	3.05	4	1.536	1.741	
Magnetite	Fe_3O_4	cub	5.17	6	2.42		
Malachite	$Cu_2(OH)_2(CO_3)$	monocl	4.05	3.8	1.655	1.875	1.909
Manganite	$MnO(OH)$	monocl	≈4.3	4	2.25	2.25	2.53
Manganosite	MnO	cub	5.37	5.5			
Marcasite	FeS_2	cub	5.02	6.3			
Marialite	$Na_4Al_3Si_9O_{24}Cl$	tetr	2.56	5.5	1.541	1.548	
Marshite	CuI	cub	5.67	2.5	2.346		
Mascagnite	$(NH_4)_2SO_4$	orth	1.77	2.3	1.520	1.523	1.533
Matlockite	$PbClF$	tetr	7.05	2.8	2.006	2.145	

Name	Formula	Crystal system	Density g/cm^3	Hardness	Index of refraction n_α	n_β	n_γ
Meionite	$Ca_4Al_6Si_6O_{24}CO_3$	tetr	2.78	5.5	1.559	1.595	
Melanterite	$FeSO_4{\cdot}7H_2O$	monocl	1.89	2	1.47	1.48	1.49
Melilite	$(Ca,Na)_2(Mg,Fe,Al,Si)_3O_7$	tetr	3.00	5.5	1.639	1.645	
Mellite	$Al_2C_{12}O_{12}{\cdot}18H_2O$	tetr	1.64	2.3	1.511	1.539	
Mendipite	$Pb_3O_2Cl_2$	rhomb	7.24	2.5	2.24	2.27	2.31
Mesolite	$Na_2Ca_2(Al_2Si_3O_{10})_3{\cdot}8H_2O$	orth	2.26	5	1.506		
Metacinnabar	HgS	cub	7.70	3			
Microcline	$KAlSi_3O_8$	monocl	2.56	6.3	1.522	1.526	1.530
Miersite	AgI	hex	5.68	2.5	2.20		
Millerite	NiS	hex	5.5	3.3			
Mimetite	$Pb_5(AsO_4,PO_4)_3Cl$	hex	7.24	3.8	2.128	2.147	
Minium	Pb_3O_4	tetr	8.9	2.5			
Mirabilite	$Na_2SO_4{\cdot}10H_2O$	monocl	1.46	1.8	1.394	1.396	1.398
Moissanite	SiC	hex	3.16	9.5	2.648	2.691	
Molybdenite	MoS_2	hex	5.06	1.3			
Monazite	$(Ce,La,Th)PO_4$	monocl	5.2	5	1.787	1.789	1.840
Monetite	$CaHPO_4$	tricl	2.92	3.5	1.587	1.61	1.640
Monticellite	$Ca(Mg,Fe)SiO_4$	orth	3.18	5.5	1.647	1.655	1.664
Montmorillonite	$(0.5Ca,Na)_{0.7}(Al,Mg,Fe)_4[(Si,Al)_8O_{20}](OH)_4{\cdot}nH_2O$	monocl	2.5	1.5	1.55	1.57	1.57
Montroydite	HgO	orth	11.14	2.5	2.37	2.50	2.65
Mordenite	$(Na,K,Ca)[Al_2Si_{10}O_{24}]{\cdot}7H_2O$	orth	2.13	3.5	1.478	1.480	1.482
Muscovite	$KAl_2Si_3AlO_{10}(OH,F)_2$	monocl	2.83	2.8	1.563	1.596	1.602
Nantokite	CuCl	cub	4.14	2.5	1.930		
Natrolite	$Na_2Al_2Si_3O_{10}{\cdot}2H_2O$	orth	2.23	5	1.478	1.481	1.491
Nepheline	$Na_3KAl_4Si_4O_{16}$	hex	2.61	5.8	1.534	1.538	
Newberyite	$MgHPO_4{\cdot}3H_2O$	orth	2.13	3.3	1.514	1.517	1.533
Niccolite	NiAs	hex	7.77	5.3			
Norbergite	$Mg(OH,F)_2{\cdot}Mg_2SiO_4$	orth	3.21	6.5	1.565	1.573	1.592
Nosean	$Na_8Al_6Si_6O_{24}SO_4$	cub	2.35	5.5	1.495		
Oldhamite	CaS	cub	2.59	4	2.137		
Oligoclase	$([NaSi]_{0.9\text{-}0.7}[CaAl]_{0.1\text{-}0.3})AlSi_2O_8$	tricl	2.64	6.3	1.539	1.543	1.547
Olivenite	$Cu_2(AsO_4)(OH)$	rhomb	4.2	3	1.77	1.80	1.85
Olivine	$(Mg,Fe)SiO_4$	rhomb	3.81	6.8	1.73	1.76	1.78
Opal	$SiO_2{\cdot}nH_2O$	amorp	1.9	5	1.44		
Orpiment	As_2S_3	monocl	3.46	1.8	2.40	2.81	3.02
Orthoclase	$KAlSi_3O_8$	monocl	2.56	6	1.523	1.527	1.531
Orthopyroxene	$(Mg,Fe)SiO_3$	rhomb	3.6	5.5	1.709	1.712	1.723
Paragonite	$NaAl_2Si_3AlO_{10}(OH)_2$	monocl	2.85	2.5	1.572	1.602	1.605
Parisite	$(Ce,La,Na)FCO_3{\cdot}CaCO_3$	hex	4.42	4.5	1.672	1.771	
Pectolite	$Ca_2NaH(SiO_3)_3$	tricl	2.88	4.8	1.603	1.610	1.639
Penfieldite	$Pb_4Cl_6(OH)_2$	hex	6.6		2.13	2.21	
Pentlandite	$(Fe,Ni)_9S_8$	cub	4.8	3.8			
Percylite	$PbCuCl_2(OH)_2$	cub		2.5	2.05		
Periclase	MgO	cub	3.6	5.5	1.735		
Perovskite	$CaTiO_3$	cub	3.98	5.5	2.34		
Petalite	$LiAlSi_4O_{10}$	monocl	2.42	6.5	1.506	1.511	1.519
Pharmacosiderite	$Fe_3(AsO_4)_2(OH)_3{\cdot}5H_2O$	cub	2.80	2.5	1.690		
Phenakite	Be_2SiO_4	rhomb	2.98	7.5	1.654	1.670	
Phillipsite	$K(Ca_{0.5},Na)_2[Al_3Si_5O_{16}]{\cdot}6H_2O$	monocl	2.2	4.3	1.494	1.497	1.505
Phlogopite	$KMg_3AlSi_3O_{10}(OH,F)_2$	monocl	2.83	2.3	1.560	1.597	1.598
Phosgenite	$Pb_2(CO_3)Cl_2$	tetr	6.13	2.5	2.118	2.145	
Piemontite	$Ca_2(Mn,Fe,Al)_3O(Si_2O_7)(SiO_4)(OH)$	monocl	3.49	6	1.762	1.773	1.796
Pigeonite	$(Mg,Fe,Ca)(Mg,Fe)Si_2O_6$	monocl	3.38	6	1.702	1.703	1.728
Pollucite	$CsAlSi_2O_6$	tetr	2.9	6.5	1.517		
Polybasite	$(Ag,Cu)_{16}Sb_2S_{11}$	monocl	6.1	2.5			
Powellite	$Ca(Mo,W)O_4$	tetr	4.35	3.8	1.971	1.980	
Prehnite	$Ca_2Al_2Si_3O_{10}(OH)_2$	rhomb	2.93	6.3	1.622	1.628	1.648
Proustite	Ag_3AsS_3	rhomb	5.57	2.3	2.792	3.088	
Pseudobrookite	Fe_2TiO_5	rhomb	4.36	6	2.38	2.39	2.42
Psilomelane	$BaMn_9O_{16}(OH)_4$	rhomb	4.71	5.5			

Name	Formula	Crystal system	Density g/cm^3	Hardness	Index of refraction n_α	n_β	n_γ
Pumpellyite	$Ca_2Al_2(Al,Fe,Mg)[Si_2(O,OH)_7]$ $(SiO_4)(OH,O)_3$	monocl	3.21	5.5	1.688	1.695	1.705
Pyrargyrite	Ag_3SbS_3	rhomb	5.85	2.5	2.88	3.08	
Pyrite	FeS_2	cub	5.02	6.3			
Pyrochlore	$NaCaNb_2O_6F$	cub	5.3	5.3			
Pyrochroite	$Mn(OH)_2$	hex	3.26	2.5	1.68	1.72	
Pyrolusite	MnO_2	tetr	5.08	6.3			
Pyromorphite	$Pb_5(PO_4,AsO_4)_3Cl$	hex	7.04	3.8	2.048	2.058	
Pyrope	$Mg_3Al_2Si_3O_{12}$	cub	3.58	6.8	1.714		
Pyrophyllite	$Al_2Si_4O_{10}(OH)_2$	monocl	2.78	1.5	1.545	1.579	1.599
Pyrrhotite	Fe_7S_8	hex	4.62	4			
Quartz	SiO_2	hex	2.65	7	1.544	1.553	
Rammelsbergite	$NiAs_2$	orth	7.1	5.8			
Raspite	$PbWO_4$	monocl	8.46	2.8	1.27	1.27	1.30
Realgar	As_4S_4	monocl	3.5	1.8	2.538	2.684	2.704
Rhodochrosite	$MnCO_3$	hex	3.70	3.8	1.597	1.816	
Rhodonite	$(Mn,Fe,Ca)SiO_3$	orth	3.48	6	1.725	1.729	1.737
Riebeckite	$Na_2Fe_5(Si_8O_{22})(OH)_2$	monocl	3.3	5	1.675	1.683	1.694
Rutile	TiO_2	tetr	4.23	6.2	2.609	2.900	
Safflorite	$(Co,Fe)As_2$	rhomb	7.3	4.8			
Samarskite	(Y,Er,Ce,U,Ca,Fe,Pb,Th) $(Nb,Ta,Ti,Sn)_2O_6$	rhomb	5.69	5.5	2.200		
Sapphirine	$(Mg,Fe)_2Al_4O_6SiO_4$	monocl	3.49	7.5	1.709	1.712	1.715
Scapolite	$(Na,Ca)_4Al_3(Al,Si)_3Si_6O_{24}$ (Cl,F,OH,CO_3,SO_4)	tetr	2.64	5.5	1.551	1.573	
Scheelite	$CaWO_4$	tetr	6.06	4.8	1.920	1.936	
Scolecite	$CaAl_2Si_3O_{10}\cdot 3H_2O$	monocl	2.27	5	1.510	1.518	1.519
Scorodite	$Fe(AsO_4)\cdot 2H_2O$	rhomb	3.28	3.8	1.784	1.795	1.814
Sellaite	MgF_2	tetr	3.15	5	1.378	1.390	
Senarmontite	Sb_2O_3	cub	5.58	2.3	2.087		
Serpentine	$Mg_3Si_2O_5(OH)_4$	monocl	2.55	3	1.55	1.56	1.56
Siderite	$FeCO_3$	hex	3.9	4.3	1.635	1.875	
Sillimanite	Al_2OSiO_4	rhomb	3.25	7	1.658	1.660	1.660
Skutterudite	$(Co,Ni)As_3$	cub	6.8	5.8			
Smithsonite	$ZnCO_3$	rhomb	4.4	4.3	1.621	1.848	
Sodalite	$Na_8Al_6Si_6O_{24}Cl_2$	cub	2.30	5.8	1.485		
Sperrylite	$PtAs_2$	cub	10.58	6.5			
Spessartite	$Mn_3Al_2Si_3O_{12}$	cub	4.19	6.8	1.800		
Sphalerite	ZnS	cub	4.0	3.8	2.369		
Sphene	$CaTiSiO_4(O,OH,F)$	monocl	3.50	5	1.90	1.95	2.03
Spinel	$MgAl_2O_4$	cub	3.55	7.8	1.719		
Spodumene	$LiAlSi_2O_6$	monocl	3.13	6.8	1.656	1.662	1.671
Stannite	Cu_2FeSn_4	tetr	4.4	4			
Staurolite	$(Fe,Mg,Zn)_2(Al,Fe,Ti)_9O_6$ $[(Si,Al)O_4]_4(O,OH)_2$	monocl	3.79	7.5	1.743	1.747	1.755
Stercorite	$Na(NH_4)H(PO_4)\cdot 4H_2O$	tricl	1.62	2	1.439	1.442	1.469
Stibiotantalite	$Sb(Ta,Nb)O_4$	rhomb	6.6	5.5	2.38	2.41	2.46
Stibnite	Sb_2S_3	orth	4.56	2			
Stilbite	$NaCa_2[Al_5Si_{13}O_{36}]\cdot 14H_2O$	monocl	2.2	3.8	1.492	1.499	1.503
Stilpnomelane	$(K,Na,Ca)_{0.6}(Fe,Mg)_6Si_8Al$ $(O,OH)_{27}\cdot 2H_2O$	monocl	2.8	3.5	1.585	1.665	1.665
Stolzite	$PbWO_4$	tetr	8.2	2.8	2.19	2.27	
Strengite	$FePO_4\cdot 2H_2O$	orth	2.87	4	1.707	1.719	1.741
Strontianite	$SrCO_3$	orth	3.5	3.5	1.518	1.666	1.668
Struvite	$Mg(NH_4)(PO_4)\cdot 6H_2O$	rhomb	1.71	2	1.495	1.496	1.504
Sulfur	S	orth	2.07	2	1.958	2.038	2.245
Sylvanite	$(Ag,Au)Te_2$	monocl	8.16	1.8			
Sylvite	KCl	cub	1.99	2	1.490		
Talc	$Mg_3Si_4O_{10}(OH)_2$	monocl	2.71	1	1.545	1.592	1.595
Tantalite	$(Fe,Mn)(Ta,Nb)_2O_6$	rhomb	7.95	6.5	2.26	2.32	2.43
Tapiolite	$FeTa_2O_6$	tetr	7.9	6.3	2.27	2.42	
Tellurobismuthite	Bi_2Te_3	hex	7.74	1.8			
Terlinguaite	Hg_2OCl	monocl	8.73	2.5	2.35	2.64	2.66
Tetrahedrite	$(Cu,Fe)_{12}Sb_4S_{13}$	cub	4.9	3.8			
Thenardite	Na_2SO_4	orth	2.7	2.8	1.468	1.475	1.483

Name	Formula	Crystal system	Density g/cm^3	Hardness	Index of refraction n_α	n_β	n_γ
Thermonatrite	$Na_2CO_3 \cdot H_2O$	orth	2.25	1.3	1.420	1.506	1.524
Thomsenolite	$NaCaAlF_6 \cdot H_2O$	monocl	2.98	2	1.407	1.414	1.415
Thorianite	ThO_2	cub	10.0	6.5	2.200		
Thorite	$ThSiO_4$	tetr	6.7	4.8	1.8		
Topaz	$Al_2SiO_4(OH,F)_2$	rhomb	3.53	8	1.618	1.620	1.627
Torbernite	$Cu(UO_2)_2(PO_4)_2 \cdot 8H_2O$	tetr	3.22	2.3	1.582	1.592	
Tourmaline	$Na(Mg,Fe,Mn,Li,Al)_3Al_6Si_6O_{18}(BO_3)_3$	rhomb	3.14	7	1.62	1.65	
Tremolite	$Ca_2Mg_5Si_8O_{22}(OH,F)_2$	monocl	3.0	5.5	1.599	1.612	1.622
Trevorite	$NiFe_2O_4$	cub	5.33	7.8	2.3		
Tridymite	SiO_2	hex	2.27	7	1.475	1.476	1.479
Triphyllite-Lithiophyllite	$Li(Fe,Mn)PO_4$	rhomb	3.46	4.5	1.68	1.68	1.69
Troegerite	$(UO_2)_3(AsO_4)_2 \cdot 12H_2O$	tetr		2.5	1.59	1.630	
Troilite	FeS	hex	4.7	4			
Trona	$Na_3H(CO_3)_2 \cdot 2H_2O$	monocl	2.14	2.8	1.412	1.492	1.540
Turquois	$Cu(Al,Fe)_6(PO_4)_4(OH)_8 \cdot 4H_2O$	tricl	2.9	5.3	1.70	1.73	1.75
Ullmannite	NiSbS	cub	6.65	5.3			
Uraninite	UO_2	cub	11.0	5.5			
Uvarovite	$Ca_3Cr_2Si_3O_{12}$	cub	3.83	6.8	1.865		
Valentinite	Sb_2O_3	orth	5.7	2.8	2.18	2.35	2.35
Vanadinite	$Pb_5(VO_4)_3Cl$	hex	6.8	2.9	2.350	2.416	
Variseite-Strengite	$(Al,Fe)(PO_4) \cdot 2H_2O$	rhomb	2.72	4	1.635	1.654	1.668
Vaterite	$CaCO_3$	hex	2.71		1.550	1.645	
Vermiculite	$(Mg,Ca)_{0.7}(Mg,Fe,Al)_6[(Al,Si)_8O_{20}](OH)_4 \cdot 8H_2O$	monocl	2.3	1.5	1.542	1.556	1.556
Vesuvianite	$Ca_{10}(Mg,Fe)_2Al_4(Si_2O_7)_2(SiO_4)_5(OH,F)_4$	tetr	3.33	6.5	1.72	1.73	
Villiaumite	NaF	cub	2.78	2.3	1.327		
Vivianite	$Fe_3(PO_4)_2 \cdot 8H_2O$	monocl	2.58	1.8	1.598	1.629	1.652
Wagnerite	$Mg_2(PO_4)F$	monocl	3.15	5.3	1.568	1.572	1.582
Wavellite	$Al_3(OH)_3(PO_4)_2 \cdot 5H_2O$	rhomb	2.36	3.6	1.527	1.535	1.553
Whewellite	$CaC_2O_4 \cdot H_2O$	cub	2.2	2.8	1.491	1.554	1.650
Willemite	Zn_2SiO_4	hex	4.1	5.5	1.691	1.719	
Witherite	$BaCO_3$	orth	4.29	3.5	1.529	1.676	1.677
Wolframite	$(Fe,Mn)WO_4$	monocl	7.3	4.3	2.26	2.32	2.42
Wollastonite	$CaSiO_3$	monocl	2.92	4.8	1.628	1.639	1.642
Wulfenite	$PbMoO_4$	tetr	6.7	2.9	2.283	2.403	
Wurtzite	ZnS	hex	4.09	3.8	2.356	2.378	
Xenotime	YPO_4	tetr	4.8	4.5	1.721	1.816	
Zeunerite	$Cu(UO_2)_2(AsO_4)_2 \cdot 10H_2O$	tetr			1.606		
Zincite	ZnO	hex	5.6	4	2.013	2.029	
Zircon	$ZrSiO_4$	tetr	4.6	7.5	1.94	1.99	
Zoisite	$Ca_2Al_3Si_3O_{12}(OH)$	rhomb	3.26	6	1.695	1.699	1.711

CRYSTALLOGRAPHIC DATA ON MINERALS

This table contains x-ray crystallographic data on about 400 common minerals, as well as selected crystalline elements. Entries are arranged alphabetically by mineral name. The columns are:

Name: Common name of the mineral.
Formula: Chemical formula for a typical sample of the mineral. Composition often varies considerably with the origin of the sample.
Crystal system: tricl = triclinic; monocl = monoclinic; orth = orthorhombic; tetr = tetragonal; hex = hexagonal; rhomb = rhombohedral; cubic = cubic.
Structure type: Prototype for the structural arrangement of the crystallographic cell.
Z: Number of formula units per the unit cell.
a, *b*, *c*: Lengths of the cell edges in Å (1Å = 10^{-8} cm).
α, β, γ : Angles between cell axes.

References

1. Robie, R.A., Bethke, P.M., and Beardsley, K.M., *U. S. Geological Survey Bulletin 1248*, U. S. Government Printing Office, Washington, D.C.
2. Donnay, J.D.H., and Ondik, H.M., *Crystal Data Determinative Tables, Third Edition, Volume 2, Inorganic Compounds*, Joint Committee on Powder Diffraction Standards, Swarthmore, PA, 1973.
3. Deer, W.A., Howie, R.A., and Zussman, J., *An Introduction to the Rock-Forming Minerals*, *2nd Edition*, Longman Scientific & Technical, Harlow, Essex, 1992.

Name	Formula	Crystal system	Structure type	*Z*	*a*/Å	*b*/Å	*c*/Å	α	β	γ
Acanthite	Ag_2S	monocl		4	4.228	6.928	7.862		99.58°	
Acmite (Aegirine)	$NaFe(SiO_3)_2$	monocl	diopside	4	9.658	8.795	5.294		107.42°	
Akermanite	$Ca_2MgSi_2O_7$	tetr	melilite	2	7.8435		5.010			
Alabandite	MnS	cubic	rock salt	4	5.223					
Almandine (Almandite)	$Fe_3Al_2Si_3O_{12}$	cubic	garnet	8	11.526					
Altaite	PbTe	cubic	rock salt	4	6.4606					
Aluminum	Al	cubic	copper	4	4.049					
Alunite	$KAl_3(SO_4)_2(OH)_6$	rhomb		3	6.982		17.32			
Analcite	$NaAlSi_2O_6{\cdot}H_20$	cubic		16	13.733					
Anatase	TiO_2	tetr		4	3.785		9.514			
Andalusite	Al_2OSiO_4	orth		4	7.7959	7.8983	5.5583			
Andradite	$Ca_3Fe_2Si_3O_{12}$	cubic	garnet	8	12.048					
Anglesite	$PbSO_4$	orth	barite	4	8.480	5.398	6.958			
Anhydrite	$CaSO_4$	orth	anhydrite	4	6.991	6.996	6.238			
Annite	$KFe_3[AlSi_3O_{10}](OH)_2$	monocl	1M mica	2	10.29	9.33	5.39		105.1°	
Anorthite	$CaAl_2Si_2O_8$	tricl	primitive cell	8	8.177	12.877	14.169	93.17°	115.85°	91.22°
Anthophyllite	$Mg_7Si_8O_{22}(OH)_2$	orth		4	18.61	18.01	5.24			
Antimony	Sb	rhomb	arsenic	6	4.2996		11.2516			
Aragonite	$CaCO_3$	orth	aragonite	4	5.741	7.968	4.959			
Arcanite	K_2SO_4	orth	arcanite	4	5.772	10.072	7.483			
Argentite	Ag_2S	cubic		2	4.870					
Argentopyrite	$AgFe_2S_3$	orth		4	6.64	11.47	6.45			
Arsenic	As	rhomb	arsenic	6	3.760		10.555			
Arsenolite	As_2O_3	cubic	diamond	16	11.074					
Arsenopyrite	FeAsS	tricl		4	5.760	5.690	5.785	90.00°	112.23°	90.00°
Azurite	$Cu_3(OH)_2(CO_3)_2$	monocl		2	5.008	5.844	10.336		92.45°	
Baddeleyite	ZrO_2	monocl	baddeleyite	4	5.1454	5.2075	5.3107		99.23°	
Banalsite	$BaNa_2Al_4Si_4O_{16}$	orth		4	8.50	9.97	16.72			
Barite	$BaSO_4$	orth	barite	4	8.878	5.450	7.152			
Berlinite	$AlPO_4$	hex	α-quartz	3	4.942		10.97			
Beryl	$Be_3Al_2(SiO_3)_6$	hex	beryl	2	9.215		9.192			
Berzelianite	Cu_2Se	cubic		4	5.85					
Bismite	Bi_2O_3	monocl	pseudo-orth	4	7.48	8.14	5.83		112.9°	
Bismuth	Bi	rhomb	arsenic	6	4.5367		11.8383			
Bismuthinite	Bi_2S_3	orth	stibnite	4	11.150	11.300	3.981			
Bixbyite	Mn_2O_3	cubic	thallium trioxide	16	9.411					
Boehmite	AlO(OH)	orth	lepidocrocite	4	2.868	12.227	3.700			
Borax	$Na_2B_4O_7{\cdot}10H_2O$	monocl		4	11.858	10.674	12.197		106.68°	

Name	Formula	Crystal system	Structure type	*Z*	*a*/Å	*b*/Å	*c*/Å	α	β	γ
Bornite (metastable)	Cu_5FeS_4	cubic		8	10.94					
Breithauptite	NiSb	hex	niccolite	2	3.942		5.155			
Brochantite	$Cu_4SO_4(OH)_6$	monocl		4	13.066	9.85	6.022		103.27°	
Bromargyrite	AgBr	cubic	rock salt	4	5.7745					
Bromellite	BeO	hex	zincite	2	2.6979		4.3772			
Brookite	TiO_2	orth		8	5.456	9.182	5.143			
Brucite	$Mg(OH)_2$	hex	cadmium iodide	1	3.147		4.769			
Bunsenite	NiO	cubic	rock salt	4	4.177					
Bustamite	$CaMn(SiO_3)_2$	tricl		6	7.736	7.157	13.824	90.52°	94.58°	103.87°
Cadmium telluride	CdTe	cubic	sphalerite	4	6.4805					
Cadmoselite	CdSe	hex	zincite	2	4.2977		7.0021			
Calcite	$CaCO_3$	rhomb	calcite	6	4.9899		17.064			
Calomel	Hg_2Cl_2	tetr		4	4.478		10.910			
Carbonate-apatite	$Ca_{10}(PO_4)_6CO_3{\cdot}H_2O$	hex	apatite	1	9.436		6.883			
Cassiterite	SnO_2	tetr	rutile	2	4.738		3.188			
Cattierite	CoS_2	cubic	pyrite	4	5.5345					
Celestite	$SrSO_4$	orth	barite	4	8.359	5.352	6.866			
Celsian	$BaAl_2Si_2O_8$	monocl		8	8.627	13.045	14.408		115.20°	
Cerianite	CeO_2	cubic	fluorite	4	5.4110					
Cerussite	$PbCO_3$	orth	aragonite	4	6.152	8.436	5.195			
Cervantite	Sb_2O_4	orth		4	5.424	11.76	4.804			
Chalcanthite	$CuSO_4{\cdot}5H_2O$	tricl		2	6.1045	10.72	5.949	97.57°	107.28°	77.43°
Chalcocite	Cu_2S	orth		96	11.881	27.323	13.491			
Chalcopyrite	$CuFeS_2$	tetr		4	5.2988		10.434			
Chlorapatite	$Ca_5(PO_4)_3Cl$	hex	apatite	2	9.629		6.777			
Chlorargyrite	AgCl	cubic	rock salt	4	5.5491					
Chloritoid	$FeAl_4O_2(SiO_4)_2(OH)_4$	monocl		8	9.48	5.48	18.18		101.77°	
Chloromagnesite	$MgCl_2$	rhomb		3	3.632		17.795			
Chondrodite	$2Mg_2SiO_4{\cdot}MgF_2$	monocl		2	7.89	4.743	10.29		109.03°	
Chrysoberyl	$BeAl_2O_4$	orth	olivine	4	5.4756	9.4041	4.4267			
Cinnabar	HgS	hex	cinnabar	3	4.149		9.495			
Claudetite	As_2O_3	monocl		4	5.339	12.984	4.5405		94.27°	
Clausthalite	PbSe	cubic	rock salt	4	6.1255					
Clinoenstatite	$MgSiO_3$	monocl		8	9.620	8.825	5.188		108.33°	
Clinoferrosilite	$FeSiO_3$	monocl		8	9.7085	9.0872	5.2284		108.43°	
Clinohumite	$4Mg_2SiO_4{\cdot}MgF_2$	monocl		2	13.68	4.75	10.27		100.83°	
Clinozoisite	$Ca_2Al_3(SiO_4)_3OH$	monocl		2	8.887	5.581	10.14		115.93°	
Cobalt olivine	Co_2SiO_4	orth	olivine	4	4.782	10.301	6.003			
Cobalt oxide	CoO	cubic	rock salt	4	4.260					
Cobalt sulfide	CoS	cubic	sphalerite	4	5.339					
Cobalt titanate	$CoTiO_3$	rhomb	ilmenite	6	5.066		13.918			
Cobalticalcite	$CoCO_3$	rhomb	calcite	6	4.6581		14.958			
Cobaltite	CoAsS	cubic	NiSbS	4	5.60					
Coesite	SiO_2	monocl		16	7.152	12.379	7.152		120.00°	
Coffinite	$USiO_4$	tetr	zircon	4	6.995		6.263			
Colemanite	$Ca_2B_6O_{11}{\cdot}5H_2O$	monocl		4	8.743	11.264	6.102		110.12°	
Coloradoite	HgTe	cubic	sphalerite	4	6.4600					
Cooperite	PtS	tetr		2	3.4699		6.1098			
Copper	Cu	cubic	face-centered cubic	4	3.6150					
Corundum	Al_2O_3	rhomb	corundum	6	4.7591		12.9894			
Cotunnite	$PbCl_2$	orth		4	4.535	7.62	9.05			
Covellite	CuS	hex		6	3.792		16.34			
Cristobalite (α)	SiO_2	tetr		4	4.971		6.918			
Cristobalite (β)	SiO_2	cubic		8	7.1382					
Cryolite	Na_3AlF_6	monocl		2	5.40	5.60	7.776		90.18°	
Cubanite	$CuFe_2S_3$	orth		4	6.46	11.12	6.23			
Cummingtonite	$(Mg,Fe,Mn)_7(Si_4O_{11})_2(OH)_2$	monocl	tremolite	2	9.522	18.223	5.332		101.92°	
Cuprite	Cu_2O	cubic		2	4.2696					
Danburite	$CaB_2Si_2O_8$	orth		4	8.04	8.77	7.74			

Name	Formula	Crystal system	Structure type	*Z*	*a*/Å	*b*/Å	*c*/Å	α	β	γ
Datolite	$CaBSiO_4(OH)$	monocl		4	9.62	7.60	4.84		90.15°	
Daubreeite	$FeCr_2S_4$	cubic	spinel	8	9.966					
Diamond	C	cubic	diamond	8	3.5670					
Diaspore	AlO(OH)	orth		4	4.401	9.421	2.845			
Dickite	$Al_2Si_2O_5(OH)_4$	monocl		4	5.150	8.940	14.736		103.58°	
Digenite	$Cu_{1.79}S$	cubic	deformed fluorite	4	5.5695					
Diopside	$CaMg(SiO_3)_2$	monocl	diopside	4	9.743	8.923	5.251		105.93°	
Dioptase	$CuSiO_2(OH)_2$	rhomb	phenacite	18	14.61		7.80			
Dolerophanite	$Cu_2O(SO_4)$	monocl		4	8.334	6.312	7.628		108.4°	
Dolomite	$CaMg(CO_3)_2$	rhomb	calcite	3	4.8079		16.010			
Dravite	$NaMg_3Al_6B_3Si_6O_{27}(OH)_4$	rhomb	tourmaline	3	15.942		7.224			
Elbaite	$NaLiAl_{7.67}B_3Si_6O_{27}(OH)_4$	rhomb	tourmaline	3	15.842		7.009			
Enargite	Cu_3AsS_4	orth		2	6.426	7.422	6.144			
Enstatite	$MgSiO_3$	orth		16	8.829	18.22	5.192			
Epidote	$Ca_2Al_2(Al,Fe)OH(SiO_4)_3$	monocl		2	8.89	5.63	10.19		115.40°	
Epsomite	$MgSO_4{\cdot}7H_2O$	orth		4	11.86	11.99	6.858			
Eskolaite	Cr_2O_3	rhomb	corundum	6	4.9607		13.599			
Eucairite	AgCuSe	orth		10	4.105	20.35	6.31			
Euclase	$AlBeSiO_4(OH)$	monocl		4	4.763	14.29	4.618		100.25°	
Famatimite	Cu_3SbS_4	tetr		2	5.384		10.770			
Fayalite	Fe_2SiO_4	orth	olivine	4	4.817	10.477	6.105			
Fe-Cordierite	$Fe_2Al_3(AlSi_5O_{18})$	orth	cordierite	4	9.726	17.065	9.287			
Fe-Gehlenite	$Ca_2Fe_2SiO_7$	tetr	melilite	2	7.54		4.855			
Fe-Indialite	$Fe_2Al_3(AlSi_5O_{18})$	hex	beryl	2	9.860		9.285			
Fe-Leucite	$KFeSi_2O_6$	tetr		16	13.205		13.970			
Fe-Microcline	$KFeSi_3O_8$	tricl		4	8.68	13.10	7.340	90.75°	116.05°	86.23°
Fe-Sanidine	$KFeSi_3O_8$	monocl		4	8.689	13.12	7.319		116.10°	
Fe-Skutterudite	$FeAs_{2.95}$	cubic		8	8.1814					
Ferberite	$FeWO_4$	monocl	wolframite	2	4.732	5.708	4.965		90.00°	
Ferriannite	$KFe_3[FeSi_3O_{10}](OH)_2$	monocl		2	5.430	9.404	10.341		100.07°	
Ferroselite	$FeSe_2$	orth	marcasite	2	4.801	5.778	3.587			
Ferrotremolite	$Ca_2Fe_5[Si_8O_{22}](OH)_2$	monocl	tremolite	2	9.97	18.34	5.30		104.50°	
Fluor-edenite	$NaCa_2Mg_5[AlSi_7O_{22}]F_2$	monocl	tremolite	2	9.847	18.00	5.282		104.83°	
Fluor-humite	$3Mg_2SiO_4{\cdot}MgF_2$	orth		4	10.243	20.72	4.735			
Fluor-norbergite	$Mg_2SiO_4{\cdot}MgF_2$	orth		4	8.727	10.271	4.709			
Fluor-phlogopite	$KMg_3[AlSi_3O_{10}]F_2$	monocl	1M mica	2	5.299	9.188	10.135		99.92°	
Fluor-richterite	$Na_2CaMg_5[Si_8O_{22}]F_2$	monocl	tremolite	2	9.823	17.96	5.268		104.33°	
Fluor-tremolite	$Ca_2Mg_5[Si_8O_{22}]F_2$	monocl	tremolite	2	9.781	18.01	5.267		104.52°	
Fluorapatite	$Ca_5(PO_4)_3F$	hex	apatite	2	9.3684		6.8841			
Fluorite	CaF_2	cubic	fluorite	4	5.4638					
Forsterite	Mg_2SiO_4	orth	olivine	4	4.758	10.214	5.984			
Frohbergite	$FeTe_2$	orth	marcasite	2	5.265	6.265	3.869			
Gahnite	$ZnAl_2O_4$	cubic	spinel	8	8.0848					
Galaxite	$MnAl_2O_4$	cubic	spinel	8	8.258					
Galena	PbS	cubic	rock salt	4	5.9360					
Gallium oxide	Ga_2O_3	rhomb	corundum	6	4.9793		13.429			
Gehlenite	$Ca_2Al_2SiO_7$	tetr	melilite	2	7.690		5.0675			
Geikielite	$MgTiO_3$	rhomb	ilmenite	6	5.054		13.898			
Gerhardite	$Cu_2(NO_3)(OH)_3$	orth		4	6.075	13.812	5.592			
Gersdorfite	NiAsS	cubic		4	5.693					
Gibbsite	$Al(OH)_3$	monocl		8	9.719	5.0705	8.6412		94.57°	
Glauchroite	$CaMnSiO_4$	orth	olivine	4	4.944	11.19	6.529			
Glaucodot	(Co,Fe)AsS	orth		24	6.64	28.39	5.64			
Glaucophane I	$Na_2Mg_3Al_2[Si_8O_{22}](OH)_2$	monocl	tremolite	2	9.748	17.915	5.273		102.78°	
Glaucophane II	$Na_2Mg_3Al_2[Si_8O_{22}](OH)_2$	monocl	tremolite	2	9.663	17.696	5.277		103.67°	
Goethite	FeO(OH)	orth		4	4.596	9.957	3.021			
Gold	Au	cubic	face-centered cubic	4	4.0786					
Goldmanite	$Ca_3V_2Si_3O_{12}$	cubic	garnet	8	12.070					
Goslarite	$ZnSO_4{\cdot}7H_2O$	orth	epsomite	4	11.779	12.050	6.822			

Name	Formula	Crystal system	Structure type	*Z*	*a*/Å	*b*/Å	*c*/Å	α	β	γ
Graphite	C	hex	graphite	4	2.4612		6.7079			
Greenockite	CdS	hex	zincite	2	4.1354		6.7120			
Greigite	Fe_3S_4	cubic	spinel	8	9.876					
Grossularite	$Ca_3Al_2Si_3O_{12}$	cubic	garnet	8	11.851					
Grunerite	$Fe_7[Si_8O_{22}](OH)_2$	monocl	tremolite	2	9.572	18.44	5.342		101.77°	
Gudmundite	FeSbS	monocl		8	10.00	5.93	6.73		90.00°	
Gypsum	$CaSO_4{\cdot}2H_2O$	monocl		4	5.68	15.18	6.29		113.83°	
Hafnia	HfO_2	monocl	baddeleyite	4	5.1156	5.1722	5.2948		99.18°	
Halite	NaCl	cubic	rock salt	4	5.6402					
Hambergite	$Be_2(OH,F)BO_3$	orth		8	9.755	12.201	4.426			
Hardystonite	$Ca_2ZnSi_2O_7$	tetr	melilite	2	7.87		5.01			
Hauerite	MnS_2	cubic	pyrite	4	6.1014					
Hausmannite	Mn_3O_4	tetr		8	8.136		9.422			
Hawleyite	CdS	cubic	sphalerite	4	5.833					
Heazelwoodite	Ni_3S_2	rhomb		3	5.746		7.134			
Hedenbergite	$CaFe(SiO_3)_2$	monocl	diopside	4	9.854	9.024	5.263		104.23°	
Hematite	Fe_2O_3	rhomb	corundum	6	5.025		13.735			
Hemimorphite	$Zn_4(OH)_2Si_2O_7{\cdot}H_2O$	orth		2	8.370	10.719	5.120			
Hercynite	$Fe(AlO_2)_2$	cubic	spinel	8	8.150					
Herzenbergite	SnS	orth	germanium sulfide	4	4.328	11.190	3.978			
Hessite	Ag_2Te	monocl		4	8.13	4.48	8.09		111.9°	
Hexahydrite	$MgSO_4{\cdot}6H_2O$	monocl		8	10.110	7.212	24.41		98.30°	
High albite (Analbite)	$NaAlSi_3O_8$	tricl		4	8.160	12.870	7.106	93.54°	116.36°	90.19°
High argentite	Ag_2S	cubic		4	6.269					
High bornite	Cu_5FeS_4	cubic		1	5.50					
High carnegeite	$NaAlSiO_4$	cubic		4	7.325					
High chalcocite	Cu_2S	hex		2	3.961		6.722			
High clinoenstatite	$MgSiO_3$	tricl		8	10.000	8.934	5.170	88.27°	70.03°	91.01°
High digenite	Cu_2S	cubic		4	5.725					
High germania	GeO_2	hex	α–quartz	3	4.987		5.652			
High leucite	$KAlSi_2O_6$	cubic		16	13.43					
High naumanite	Ag_2Se	cubic		2	4.993					
High sanidine	$KAlSi_3O_8$	monocl		4	8.615	13.031	7.177		115.98°	
Huebnerite	$MnWO_4$	monocl	wolframite	2	4.834	5.758	4.999		91.18°	
Huntite	$Mg_3Ca(CO_3)_4$	rhomb	calcite	3	9.498		7.816			
Hydroxylapatite	$Ca_5(PO_4)_3OH$	hex	apatite	2	9.418		6.883			
Ice	H_2O	hex		4	4.5212		7.3666			
Ilmenite	$FeTiO_3$	rhomb	ilmenite	6	5.093		14.055			
Indialite (Cordierite)	$Mg_2Al_3(AlSi_5O_{18})$	hex	beryl	2	9.7698		9.3517			
Iodargyrite	AgI	hex	zincite	2	4.5955		7.5005			
Iron (α)	Fe	cubic	body-centered cubic	2	2.8664					
Jacobsite	$MnFe_2O_4$	cubic	spinel	8	8.499					
Jadeite	$NaAl(SiO_3)_2$	monocl	diopside	4	9.409	8.564	5.220		107.50°	
Jalpaite	$Ag_{1.55}Cu_{0.45}S$	tetr		16	8.673		11.756			
Johannsenite	$CaMn(SiO_3)_2$	monocl	diopside	4	9.83	9.04	5.27		105.00°	
Kaliophilite	$KAlSiO_4$	hex		54	26.930		8.522			
Kalsilite	$KAlSiO_4$	hex		2	5.1597		8.7032			
Kaolinite	$Al_2Si_2O_5(OH)_4$	tricl		2	5.155	8.959	7.407	91.68°	104.87°	89.93°
Karelianite	V_2O_3	rhomb	corundum	6	4.952		14.002			
Keatite	SiO_2	tetr		12	7.456		8.604			
Kernite	$Na_2B_4O_7{\cdot}4H_2O$	monocl		4	7.022	9.151	15.676		108.83°	
Kerschsteinite	$CaFeSiO_4$	orth	olivine	4	4.886	11.146	6.434			
Klockmannite	CuSe	hex	deformed covellite	78	14.206		17.25			
Knebelite	$MnFeSiO_4$	orth	olivine	4	4.854	10.602	6.162			
Kyanite	Al_2OSiO_4	tricl		4	7.123	7.848	5.564	89.92°	101.25°	105.97°
Larnite	Ca_2SiO_4	monocl		4	5.48	6.76	9.28		94.55°	
Laurite	RuS_2	cubic	pyrite	4	5.60					

Name	Formula	Crystal system	Structure type	*Z*	*a*/Å	*b*/Å	*c*/Å	α	β	γ
Lawrencite	$FeCl_2$	rhomb		3	3.593		17.58			
Lawsonite	$CaAl_2Si_2O_7(OH)_2{\cdot}H_2O$	orth		4	8.787	5.836	13.123			
Lead	Pb	cubic	face-centered cubic	4	4.9505					
Leonhardtite	$MgSO_4{\cdot}4H_2O$	monocl		4	5.922	13.604	7.905		90.85°	
Lepidocrocite	FeO(OH)	orth		4	3.868	12.525	3.066			
Lepidolite	$K_2Al_3Li_2AlSi_7O_{20}(OH)_4$	monocl	2M2 mica	2	9.2	5.3	20.0		98.00°	
Leucite	$KAlSi_2O_6$	tetr		16	13.074		13.738			
Lime	CaO	cubic	rock salt	4	4.8108					
Lime olivine	Ca_2SiO_4	orth	olivine	4	5.091	11.371	6.782			
Linnaeite	Co_3S_4	cubic	spinel	8	9.401					
Litharge	PbO	tetr		2	3.9759		5.023			
Loellingite	$FeAs_2$	orth	marcasite	2	5.300	5.981	2.882			
Low albite	$NaAlSi_3O_8$	tricl		4	8.139	12.788	7.160	94.27°	116.57°	87.68°
Low bornite	Cu_5FeS_4	tetr		16	10.94		21.88			
Low cordierite	$Mg_2Al_3(AlSi_5O_{18})$	orth		4	9.721	17.062	9.339			
Low germania	GeO_2	tetr	rutile	2	4.3963		2.8626			
Low nepheline	$NaAlSiO_4$	hex		8	9.986		8.330			
Luzonite	Cu_3AsS_4	tetr		2	5.289		10.440			
Mackinawite	FeS	tetr		2	3.675		5.030			
Magnesioriebeckite	$Na_2Mg_3Fe_2[Si_8O_{22}](OH)_2$	monocl	tremolite	2	9.733	17.946	5.299		103.30°	
Magnesite	$MgCO_3$	rhomb	calcite	6	4.6330		15.016			
Magnetite	Fe_3O_4	cubic	spinel	8	8.3940					
Malachite	$Cu_2(OH)_2CO_3$	monocl		4	9.502	11.974	3.240		98.75°	
Maldonite	Au_2Bi	cubic		8	7.958					
Manganese sulfide (γ)	MnS	hex	zincite	2	3.976		6.432			
Manganese sulfide (β)	MnS	cubic	sphalerite	4	5.611					
Manganosite	MnO	cubic	rock salt	4	4.4448					
Marcasite	FeS_2	orth	marcasite	2	4.443	5.423	3.3876			
Margarite	$CaAl_2[AlSi_2O_{10}](OH)_2$	monocl	2M mica	4	5.13	8.92	19.50		95.00°	
Marialite	$Na_4Al_3Si_9O_{24}Cl$	tetr		2	12.064		7.514			
Marshite	CuI	cubic	sphalerite	4	6.0507					
Mascagnite	$(NH_4)_2SO_4$	orth	arcanite	4	7.782	5.993	10.636			
Massicot	PbO	orth		4	5.489	4.755	5.891			
Matlockite	PbClF	tetr		2	4.106		7.23			
Maucherite	$Ni_{11}As_8$	tetr		4	6.870		21.81			
Meionite	$Ca_4Al_6Si_6O_{24}CO_3$	tetr		2	12.174		7.652			
Melanophlogite	SiO_2	cubic	clathrate type	46	13.402					
Melanterite	$FeSO_4{\cdot}7H_2O$	monocl		4	14.072	6.503	11.041		105.57°	
Melonite	$NiTe_2$	hex	cadmium iodide	1	3.869		5.308			
Metacinnabar	HgS	cubic	sphalerite	4	5.8517					
Miargyrite	$AgSbS_2$	monocl		8	12.862	4.111	13.220		98.63°	
Microcline	$KAlSi_3O_8$	tricl		4	8.582	12.964	7.222	90.62°	115.92°	87.68°
Miersite	AgI	cubic	sphalerite	4	6.4963					
Millerite	NiS	rhomb		9	9.616		3.152			
Minium	Pb_3O_4	tetr		4	8.815		6.565			
Minnesotaite	$Fe_3Si_4O_{10}(OH)_2$	monocl		4	5.4	9.42	19.4		100.00°	
Mirabilite	$Na_2SO_4{\cdot}10H_2O$	monocl		4	11.51	10.38	12.83		107.75°	
Mn-Indialite	$Mn_2Al_3(AlSi_5O_{18})$	hex	beryl	2	9.925		9.297			
Molybdenite	MoS_2	hex	molybdenite	2	3.1604		12.295			
Molybdenum	Mo	cubic		2	3.1653					
Molybdite	MoO_3	orth		4	3.962	13.858	3.697			
Monteponite	CdO	cubic	rock salt	4	4.6953					
Monticellite	$CaMgSiO_4$	orth	olivine	4	4.827	11.084	6.376			
Montroydite	HgO	orth		4	6.608	5.518	3.519			
Mullite (2:1)	$2Al_2O_3{\cdot}SiO_2$	orth		6	7.5788	7.6909	2.8883			
Mullite (3:2)	$3Al_2O_3{\cdot}2SiO_2$	orth		3	7.557	7.6876	2.8842			
Muscovite	$KAl_2AlSi_3O_{10}(OH)_2$	monocl	2M2 mica	4	5.203	8.995	20.030		94.47°	

Name	Formula	Crystal system	Structure type	*Z*	*a*/Å	*b*/Å	*c*/Å	α	β	γ
Nacrite	$Al_2Si_2O_5(OH)_4$	monocl		4	8.909	5.146	15.697		113.70°	
Nantokite	CuCl	cubic	sphalerite	4	5.416					
Natroalunite	$NaAl_3(SO_4)_2(OH)_6$	rhomb		3	6.974		16.69			
Natrolite	$Na_2Al_2Si_3O_{10}{\cdot}2H_2O$	orth		8	18.30	18.63	6.60			
Neighborite	$NaMgF_3$	orth	perovskite	4	5.363	7.676	5.503			
Ni-Skutterudite	$NiAs_{2.95}$	cubic		8	8.3300					
Niccolite	NiAs	hex	niccolite	2	3.618		5.034			
Nickel	Ni	cubic	face-centered cubic	4	3.5238					
Nickel carbonate	$NiCO_3$	rhomb	calcite	6	4.5975		14.723			
Nickel olivine	Ni_2SiO_4	orth	olivine	4	4.727	10.121	5.915			
Nickel selenide	$NiSe_2$	cubic	pyrite	4	5.9604					
Niter	KNO_3	orth	aragonite	4	6.431	9.164	5.414			
Norsethite	$BaMg(CO_3)_2$	rhomb	calcite	3	5.020		16.75			
Oldhamite	CaS	cubic	rock salt	4	5.689					
Orpiment	As_2S_3	monocl		4	11.49	9.59	4.25		90.45°	
Orthoclase	$KAlSi_3O_8$	monocl		4	8.562	12.996	7.193		116.02°	
Orthoferrosilite	$FeSiO_3$	orth	enstatite	16	9.080	18.431	5.238			
Otavite	$CdCO_3$	rhomb	calcite	6	4.9204		16.298			
Paracelsian	$BaAl_2Si_2O_8$	monocl		4	8.58	9.583	9.08		90.00°	
Paragonite	$NaAl_2AlSi_3O_{10}(OH)_2$	monocl	2M1 mica	4	5.13	8.89	19.32		95.17°	
Pararammelsbergite	$NiAs_2$	orth		8	5.75	5.82	11.428			
Paratellurite	TeO_2	tetr		4	4.810		7.613			
Parawollastonite	$CaSiO_3$	monocl		12	15.417	7.321	7.066		95.40°	
Pectolite	$Ca_2NaH(SiO_3)_3$	tricl		2	7.99	7.04	7.02	90.05°	95.27°	102.47°
Pentlandite	$Fe_{5.25}Ni_{3.75}S_8$	cubic		4	10.196					
Pentlandite	$Fe_{4.75}Ni_{5.25}S_8$	cubic		4	10.095					
Periclase	MgO	cubic	rock salt	4	4.2117					
Perovskite	$CaTiO_3$	orth	perovskite	4	5.3670	7.6438	5.4439			
Petalite	$LiAlSi_4O_{10}$	monocl		2	11.32	5.14	7.62		105.90°	
Petzite	Ag_3AuTe_2	cubic		8	10.38					
Phenacite	Be_2SiO_4	rhomb	phenacite	18	12.472		8.252			
Phlogopite	$KMg_3AlSi_3O_{10}(OH)_2$	monocl	1M mica	2	5.326	9.210	10.311		100.17°	
Picrochromite	$MgCr_2O_4$	cubic	spinel	8	8.333					
Piemontite	$Ca_2Al_{1.5}Mn_{1.5}(SiO_4)_3OH$	monocl		2	8.95	5.70	9.41		115.70°	
Platinum	Pt	cubic	face-centered cubic	4	3.9231					
Polymidite	Ni_3S_4	cubic	spinel	8	9.480					
Portlandite	$Ca(OH)_2$	hex	cadmium iodide	1	3.5933		4.9086			
Powellite	$CaMoO_4$	tetr	scheelite	4	5.226		11.43			
Protoenstatite	$MgSiO_3$	orth		8	9.25	8.74	5.32			
Proustite	Ag_3AsS_3	rhomb		6	10.816		8.6948			
Pseudowollastonite	$CaSiO_3$	tricl		24	6.90	11.78	19.65	90.00°	90.80°	90.00°
Pyrargyrite	Ag_3SbS_3	rhomb		6	11.052		8.7177			
Pyrite	FeS_2	cubic	pyrite	4	5.4175					
Pyrolusite	MnO_2	tetr	rutile	2	4.388		2.865			
Pyrope	$Mg_3Al_2Si_3O_{12}$	cubic	garnet	8	11.459					
Pyrophanite	$MnTiO_3$	rhomb	ilmenite	6	5.155		14.18			
Pyrophyllite	$Al_2Si_4O_{10}(OH)_2$	monocl	2M1 mica	4	5.14	8.90	18.55		99.92°	
Pyroxmangite	$MnFe(SiO_3)_2$	tricl		7	7.56	17.45	6.67	84.00°	94.30°	113.70°
Pyrrhotite	$Fe_{0.980}S$	hex	defect niccolite	2	3.446		5.848			
Pyrrhotite	$Fe_{0.885}S$	hex	defect niccolite	2	3.440		5.709			
Quartz (α)	SiO_2	hex		3	4.9136		5.4051			
Quartz (β)	SiO_2	hex		3	4.999		5.4592			
Rammelsbergite	$NiAs_2$	orth	marcasite	2	4.757	5.797	3.542			
Realgar	AsS	monocl		16	9.29	13.53	6.57		106.55°	
Retgersite	$NiSO_4{\cdot}4H_2O$	tetr		4	6.782		18.28			
Rhodochrosite	$MnCO_3$	rhomb	calcite	6	4.7771		15.664			

Name	Formula	Crystal system	Structure type	*Z*	*a*/Å	*b*/Å	*c*/Å	α	β	γ
Rhodonite	$MnSiO_3$	tricl		10	7.682	11.818	6.707	92.36°	93.95°	105.66°
Riebeckite	$Na_2Fe_5FSi_8O_{22}(OH)_2$	monocl	tremolite	2	9.729	18.065	5.334		103.31°	
Rutile	TiO_2	tetr		2	4.5937		2.9618			
Safflorite	$Co_{0.5}Fe_{0.5}As_2$	orth	marcasite	2	5.231	5.953	2.962			
Sanmartinite	$ZnWO_4$	monocl	wolframite	2	4.691	5.720	4.925		89.36°	
Sapphirine	$Mg_2Al_4O_6SiO_4$	monocl		8	9.96	28.60	9.85		110.5°	
Scacchite	$MnCl_2$	rhomb		3	3.711		17.59			
Scheelite	$CaWO_4$	tetr	scheelite	4	5.242		11.372			
Schorl	$NaFe_3Al_6B_3Si_6O_{27}(OH)_4$	rhomb	tourmaline	3	16.032		7.149			
Selenium	Se	hex		3	4.3642		4.9588			
Selenolite	SeO_2	tetr		8	8.35		5.05			
Sellaite	MgF_2	tetr	rutile	2	4.621		3.050			
Senarmontite	Sb_2O_3	cubic	arsenic trioxide	16	11.152					
Shandite	$Ni_3Pb_2S_2$	rhomb		3	5.576		13.658			
Shortite	$Na_2Ca_2(CO_3)_3$	orth		2	4.961	11.03	7.12			
Siderite	$FeCO_3$	rhomb	calcite	6	4.6887		15.373			
Silicon	Si	cubic	diamond	8	5.4305					
Sillimanite	Al_2OSiO_4	orth		4	7.4843	7.6730	5.7711			
Silver	Ag	cubic	face-centered cubic	4	4.0862					
Silver telluride I	Ag_2Te	cubic		2	5.29					
Silver telluride II	Ag_2Te	cubic		4	6.585					
Smithsonite	$ZnCO_3$	rhomb	calcite	6	4.6528		15.025			
Soda niter	$NaNO_3$	rhomb	calcite	6	5.0696		16.829			
Sodium melilite	$NaCaAlSi_2O_7$	tetr	melilite	2	8.511		4.809			
Sperrylite	$PtAs_2$	cubic	pyrite	4	5.968					
Spessartite	$Mn_3Al_2Si_3O_{12}$	cubic	garnet	8	11.621					
Sphalerite	ZnS	cubic	sphalerite	4	5.4093					
Sphene	$CaTiSiO_5$	monocl		4	7.07	8.72	6.56		113.95°	
Spinel	$MgAl_2O_4$	cubic	spinel	8	8.080					
Spodumene	$LiAl(SiO_3)_2$	monocl	diopside	4	9.451	8.387	5.208		110.07°	
Spodumene (β)	$LiAl(SiO_3)_2$	tetr		4	7.5332		9.1540			
Staurolite	$Fe_2Al_9Si_4O_{22}(OH)_2$	monocl		2	7.90	16.65	5.63		90.00°	
Sternbergite	$AgFe_2S_3$	orth		8	11.60	12.675	6.63			
Stibnite	Sb_2S_3	orth	stibnite	4	11.229	11.310	3.8389			
Stilleite	ZnSe	cubic	sphalerite	4	5.6685					
Stishovite	SiO_2	tetr	rutile	2	4.1790		2.6649			
Stolzite	$PbWO_4$	tetr	scheelite	4	5.4616		12.046			
Stromeyerite	$Ag_{0.93}Cu_{1.07}S$	orth		4	4.066	6.628	7.972			
Strontianite	$SrCO_3$	orth	aragonite	4	6.029	8.414	5.107			
Sulfur (monoclinic)	S	monocl	S8 ring molecules	48	11.04	10.98	10.92		96.73°	
Sulfur (orthorhombic)	S	orth	S8 ring molecules	128	10.4646	12.8660	24.4860			
Sulfur (rhombohedral)	S	rhomb	S6 ring molecules	18	10.818		4.280			
Sylvite	KCl	cubic	rock salt	4	6.2931					
Syngenite	$K_2Ca(SO_4)_2{\cdot}H_2O$	monocl		2	9.775	7.156	6.251		104.00°	
Synthetic anorthite	$CaAl_2Si_2O_8$	hex		2	5.10		14.72			
Synthetic anorthite	$CaAl_2Si_2O_8$	orth		2	8.22	8.60	4.83			
Talc	$Mg_3Si_4O_{10}(OH)_2$	monocl	2M1 mica	4	5.287	9.158	18.95		99.50°	
Tantalum	Ta	cubic	tungsten	2	3.3058					
Teallite	$PbSnS_2$	orth	germanium sulfide	2	4.266	11.419	4.090			
Tellurite	TeO_2	orth	tellurite	8	5.607	12.034	5.463			
Tellurium	Te	hex	selenium	3	4.4570		5.9290			
Tellurobismuthite	Bi_2Te_3	rhomb		3	4.3835		30.487			
Tennantite	$Cu_{12}As_4S_{13}$	cubic	tetrahedrite	2	10.190					
Tenorite	CuO	monocl		4	4.684	3.425	5.129		99.47°	
Tephroite	Mn_2SiO_4	orth	olivine	4	4.871	10.636	6.232			

Name	Formula	Crystal system	Structure type	*Z*	*a*/Å	*b*/Å	*c*/Å	α	β	γ
Tetrahedrite	$Cu_{12}Sb_4S_{13}$	cubic	tetrahedrite	2	10.327					
Thenardite	Na_2SO_4	orth	thenardite	8	5.863	12.304	9.821			
Thorianite	ThO_2	cubic	fluorite	4	5.5952					
Thorite	$ThSiO_4$	tetr	zircon	4	7.143		6.327			
Tiemannite	HgSe	cubic	sphalerite	4	6.0853					
Tin	Sn	tetr		4	5.8315		3.1813			
Titanium	Ti	hex		2	2.953		4.729			
Titanium(III) oxide	Ti_2O_3	rhomb	corundum	6	5.149		13.642			
Topaz	$Al_2SiO_4(OH,F)_2$	orth		4	8.394	8.792	4.649			
Tremolite	$Ca_2Mg_5Si_8O_{22}(OH)_2$	monocl	tremolite	2	9.840	18.052	5.275		104.70°	
Trevorite	$NiFe_2O_4$	cubic	spinel	8	8.339					
Tridymite (β)	SiO_2	hex		4	5.0463		8.2563			
Trogtalite	$CoSe_2$	cubic	pyrite	4	5.8588					
Troilite	FeS	hex	niccolite	2	3.446		5.877			
Tschermakite	$CaAl_2SiO_6$	monocl	diopside	4	9.615	8.661	5.272		106.12°	
Tungsten	W	cubic		2	3.1653					
Tungstenite	WS_2	hex	molybdenite	2	3.154		12.362			
Turquois	$CuAl_6(PO_4)_4(OH)_8{\cdot}4H_2O$	tricl		1	7.424	7.629	9.910	68.61°	69.71°	65.08°
Umangite	Cu_3Se_2	tetr		2	6.402		4.276			
Uraninite	UO_2	cubic	fluorite	4	5.4682					
Ureyite	$NaCr(SiO_3)_2$	monocl	diopside	4	9.550	8.712	5.273		107.44°	
Uvarovite	$Ca_3Cr_2Si_3O_{12}$	cubic	garnet	8	11.999					
Uvite	$CaMg_4Al_5B_3Si_6O_{27}(OH)_4$	rhomb	tourmaline	3	15.86		7.19			
Vaesite	NiS_2	cubic	pyrite	4	5.6873					
Valentinite	Sb_2O_3	orth	antimony trioxide	4	4.914	12.468	5.421			
Vanthoffite	$MgSO_4{\cdot}3Na_2SO_4$	monocl		2	9.797	9.217	8.199		113.50°	
Vaterite	$CaCO_3$	hex		6	7.135		8.524			
Villiaumite	NaF	cubic	rock salt	4	4.6342					
Violarite	$FeNi_2S_4$	cubic	spinel	8	9.464					
Willemite	Zn_2SiO_4	rhomb	phenacite	18	13.94		9.309			
Witherite	$BaCO_3$	orth	aragonite	4	6.430	8.904	5.314			
Wolframite	$Fe_{0.5}Mn_{0.5}WO_4$	monocl	wolframite	2	4.782	5.731	4.982		90.57°	
Wollastonite	$CaSiO_3$	tricl		6	7.94	7.32	7.07	90.03°	95.37°	103.43°
Wulfenite	$PbMoO_4$	tetr	scheelite	4	5.435		12.110			
Wurtzite	ZnS	hex	zincite	2	3.8230		6.2565			
Wustite	$Fe_{0.953}O$	cubic	defect rock salt	4	4.3088					
Xenotime	YPO_4	tetr	zircon	4	6.885		5.982			
Zinc	Zn	hex	hexagonal close pack	2	2.665		4.947			
Zinc telluride	ZnTe	cubic	sphalerite	4	6.1020					
Zincite	ZnO	hex	zincite	2	3.2495		5.2069			
Zinkosite	$ZnSO_4$	orth	barite	4	8.588	6.740	4.770			
Zircon	$ZrSiO_4$	tetr	zircon	4	6.604		5.979			
Zoisite	$Ca_2Al_3(SiO_4)_3OH$	orth		4	16.15	5.581	10.06			

VAPOR PRESSURE OF THE METALLIC ELEMENTS — DATA

The following values of the vapor pressure of metallic elements are calculated from the equations in the preceding table. All values are given in pascals. For conversion, note that 1 Pa = 7.50 μmHg = $9.87 \cdot 10^{-6}$ atm.

		Vapor Pressure in Pa										
Metal	**mp/K**	**400 K**	**600 K**	**800 K**	**1000 K**	**1200 K**	**1400 K**	**1600 K**	**1800 K**	**2000 K**	**2200 K**	**2400 K**
Aluminum	933			3.06×10^{-10}	5.08×10^{-6}	0.00256	0.218	6.10	81.4			
Americium	1449			3.88×10^{-7}	0.00167	0.423	21.35					
Barium	1000		7.97×10^{-6}	0.0450	7.11	162						
Beryllium	1560			3.04×10^{-10}	4.96×10^{-6}	0.00314	0.312	9.12	113			
Cadmium	594	0.000280	18.2									
Calcium	1115		2.36×10^{-5}	0.146	25.5							
Cerium	1071				2.47×10^{-11}	8.91×10^{-8}	2.97×10^{-5}	0.00233	0.0691	1.04	9.56	60.8
Cesium	302	0.394										
Chromium	2180				2.45×10^{-8}	7.59×10^{-5}	0.0239	1.80	52.1	774		
Cobalt	1768				2.09×10^{-10}	1.00×10^{-6}	0.000419	0.0379	1.15	16.0		
Copper	1358			6.60×10^{-11}	1.53×10^{-6}	0.00122	0.135	3.94	54.4			
Curium	1618				1.90×10^{-9}	4.24×10^{-6}	0.00103	0.0629	1.17	12.1	82.1	
Dysprosium	1685			1.54×10^{-8}	8.21×10^{-5}	0.0241	1.362	27.5				
Erbium	1802			3.90×10^{-10}	4.30×10^{-6}	0.00205	0.163	4.23	52.5			
Europium	1095		1.74×10^{-5}	0.109	19.4							
Gadolinium	1586				5.70×10^{-10}	1.54×10^{-6}	0.000429	0.0279	0.618	7.39	56.2	
Gallium	303			1.94×10^{-7}	0.000565	0.114	4.98	84.4				
Gold	1337				3.72×10^{-8}	5.44×10^{-5}	0.00920	0.374	6.68	67.0		
Hafnium	2506						1.35×10^{-11}	9.81×10^{-9}	1.63×10^{-6}	9.69×10^{-5}	0.00272	0.0437
Holmium	1747			3.20×10^{-9}	2.32×10^{-5}	0.00837	0.546	12.3				
Indium	430		8.31×10^{-11}	1.08×10^{-5}	0.0127	1.413	40.9					
Iridium	2719							1.48×10^{-9}	3.72×10^{-7}	3.06×10^{-5}	0.00112	0.0225
Iron	1811				5.54×10^{-9}	2.51×10^{-5}	0.0104	0.961	32.7	36.8		
Lanthanum	1191					5.09×10^{-8}	2.02×10^{-5}	0.00181	0.0596	0.976	9.61	64.7
Lead	601		5.54×10^{-7}	0.00618	1.64	68.1						
Lithium	454	7.90×10^{-11}	0.000489	1.08	109							
Lutetium	1936				3.28×10^{-11}	1.59×10^{-7}	6.79×10^{-5}	0.00628	0.211	3.18	26.7	
Magnesium	923	6.53×10^{-9}	0.0152	21.5								
Manganese	1519			5.55×10^{-7}	0.00221	0.524	24.9					
Mercury	234	140										
Molybdenum	2895							1.83×10^{-9}	4.07×10^{-7}	3.03×10^{-5}	0.00102	0.0189
Neodymium	1294			4.55×10^{-11}	7.62×10^{-7}	0.000483	0.0412	1.07	13.4	101		
Neptunium	917					3.31×10^{-9}	1.63×10^{-6}	0.000168	0.00604	0.105	1.06	7.28
Nickel	1728				2.19×10^{-10}	1.09×10^{-6}	0.000471	0.0438	1.37	19.5		
Niobium	2750							2.32×10^{-11}	9.54×10^{-9}	1.17×10^{-6}	5.98×10^{-5}	0.00158
Osmium	3306								1.85×10^{-10}	3.46×10^{-8}	2.49×10^{-6}	8.75×10^{-5}
Palladium	1828				8.27×10^{-9}	1.40×10^{-5}	0.00277	0.144	3.07	30.4		
Platinum	2041						2.34×10^{-8}	1.14×10^{-5}	0.00143	0.0689	0.153	1.59
Plutonium	913				1.03×10^{-8}	6.17×10^{-6}	0.000594	0.0182	0.262	2.20	12.6	53.8
Potassium	337	0.0188	96.9									
Praseodymium	1204				1.95×10^{-8}	2.16×10^{-5}	0.00257	0.0904	1.44	13.2	80.8	
Protactinium	1845							3.44×10^{-10}	8.06×10^{-8}	5.57×10^{-6}	0.000174	0.00306
Rhenium	3459								1.37×10^{-10}	2.22×10^{-8}	1.41×10^{-6}	4.45×10^{-5}
Rhodium	2236						1.69×10^{-8}	5.99×10^{-6}	0.000571	0.0217	0.422	4.41
Rubidium	312	0.165										
Ruthenium	2606							7.96×10^{-9}	1.77×10^{-6}	0.000133	0.00455	0.0858
Samarium	1347		8.17×10^{-8}	0.00221	0.942	51.0						
Scandium	1814				6.31×10^{-8}	0.000129	0.0300	1.80	43.6	91.3		
Silver	1235			1.27×10^{-7}	0.000603	0.165	7.61	131				
Sodium	371	0.000185	5.60									
Strontium	1050	4.99×10^{-11}	0.000429	1.134	121							
Tantalum	3280									3.36×10^{-10}	1.87×10^{-8}	5.21×10^{-7}
Terbium	1629				1.92×10^{-9}	4.18×10^{-6}	0.000988	0.0585	1.15	12.5	88.0	
Thallium	577		1.59×10^{-5}	0.0931	16.9							
Thorium	2023						3.33×10^{-11}	2.00×10^{-8}	2.89×10^{-6}	0.000154	0.00401	0.0610
Thulium	1818		6.03×10^{-10}	5.94×10^{-5}	0.0561	5.22	130					
Tin	505			1.26×10^{-9}	8.62×10^{-6}	0.00310	0.207	4.85	56.3			
Titanium	1943					9.69×10^{-9}	7.44×10^{-6}	0.00106	0.0493	0.978	10.6	76.9
Tungsten	3687									2.62×10^{-10}	3.01×10^{-8}	1.59×10^{-6}
Uranium	1408					9.47×10^{-10}	2.87×10^{-6}	4.27×10^{-6}	0.000263	0.00678	0.0933	0.803
Vanadium	2183					2.79×10^{-10}	4.35×10^{-7}	0.000107	0.00769	0.233	3.68	32.6
Ytterbium	1092	1.03×10^{-9}	0.00384	6.74								
Yttrium	1795				6.66×10^{-11}	2.96×10^{-7}	0.000117	0.0102	0.316	4.27	35.9	
Zinc	693	1.47×10^{-6}	0.653									
Zirconium	2127						1.05×10^{-10}	6.17×10^{-8}	8.68×10^{-6}	0.000450	0.0110	0.155

CODATA KEY VALUES FOR THERMODYNAMICS

The Committee on Data for Science and Technology (CODATA) has conducted a project to establish internationally agreed values for the thermodynamic properties of key chemical substances. This table presents the final results of the project. Use of these recommended, internally consistent values is encouraged in the analysis of thermodynamic measurements, data reduction, and preparation of other thermodynamic tables.

The table includes the standard enthalpy of formation at 298.15 K, the entropy at 298.15 K, and the quantity $H°$ (298.15 K)–$H°$ (0). A value of 0 in the $\Delta_f H°$ column for an element indicates the reference state for that element. The standard state pressure is 100000 Pa (1 bar). See the reference for information on the dependence of gas-phase entropy on the choice of standard state pressure.

Substances are listed in alphabetical order of their chemical formulas when written in the most common form.

The table is reprinted with permission of CODATA.

Reference

Cox, J. D., Wagman, D. D., and Medvedev, V. A., *CODATA Key Values for Thermodynamics,* Hemisphere Publishing Corp., New York, 1989.

Substance	State	$\Delta_f H°$ (298.15 K) kJ·mol^{-1}	$S°$ (298.15 K) J·K^{-1}·mol^{-1}	$H°$ (298.15 K) – $H°$ (0) kJ·mol^{-1}
Ag	cr	0	42.55 ± 0.20	5.745 ± 0.020
Ag	g	284.9 ± 0.8	172.997 ± 0.004	6.197 ± 0.001
Ag^+	aq	105.79 ± 0.08	73.45 ± 0.40	
AgCl	cr	–127.01 ± 0.05	96.25 ± 0.20	12.033 ± 0.020
Al	cr	0	28.30 ± 0.10	4.540 ± 0.020
Al	g	330.0 ± 4.0	164.554 ± 0.004	6.919 ± 0.001
Al^{+3}	aq	–538.4 ± 1.5	–325 ± 10	
AlF_3	cr	–1510.4 ± 1.3	66.5 ± 0.5	11.62 ± 0.04
Al_2O_3	cr, corundum	–1675.7 ± 1.3	50.92 ± 0.10	10.016 ± 0.020
Ar	g	0	154.846 ± 0.003	6.197 ± 0.001
B	cr, rhombic	0	5.90 ± 0.08	1.222 ± 0.008
B	g	565 ± 5	153.436 ± 0.015	6.316 ± 0.002
BF_3	g	–1136.0 ± 0.8	254.42 ± 0.20	11.650 ± 0.020
B_2O_3	cr	–1273.5 ± 1.4	53.97 ± 0.30	9.301 ± 0.040
Be	cr	0	9.50 ± 0.08	1.950 ± 0.020
Be	g	324 ± 5	136.275 ± 0.003	6.197 ± 0.001
BeO	cr	–609.4 ± 2.5	13.77 ± 0.04	2.837 ± 0.008
Br	g	111.87 ± 0.12	175.018 ± 0.004	6.197 ± 0.001
Br^-	aq	–121.41 ± 0.15	82.55 ± 0.20	
Br_2	l	0	152.21 ± 0.30	24.52 ± 0.01
Br_2	g	30.91 ± 0.11	245.468 ± 0.005	9.725 ± 0.001
C	cr, graphite	0	5.74 ± 0.10	1.050 ± 0.020
C	g	716.68 ± 0.45	158.100 ± 0.003	6.536 ± 0.001
CO	g	–110.53 ± 0.17	197.660 ± 0.004	8.671 ± 0.001
CO_2	g	–393.51 ± 0.13	213.785 ± 0.010	9.365 ± 0.003
CO_2	aq, undissoc.	–413.26 ± 0.20	119.36 ± 0.60	
CO_3^{-2}	aq	–675.23 ± 0.25	–50.0 ± 1.0	
Ca	cr	0	41.59 ± 0.40	5.736 ± 0.040
Ca	g	177.8 ± 0.8	154.887 ± 0.004	6.197 ± 0.001
Ca^{+2}	aq	–543.0 ± 1.0	–56.2 ± 1.0	
CaO	cr	–634.92 ± 0.90	38.1 ± 0.4	6.75 ± 0.06
Cd	cr	0	51.80 ± 0.15	6.247 ± 0.015
Cd	g	111.80 ± 0.20	167.749 ± 0.004	6.197 ± 0.001
Cd^{+2}	aq	–75.92 ± 0.60	–72.8 ± 1.5	
CdO	cr	–258.35 ± 0.40	54.8 ± 1.5	8.41 ± 0.08
$CdSO_4 \cdot 8/3H_2O$	cr	–1729.30 ± 0.80	229.65 ± 0.40	35.56 ± 0.04
Cl	g	121.301 ± 0.008	165.190 ± 0.004	6.272 ± 0.001
Cl^-	aq	–167.080 ± 0.10	56.60 ± 0.20	
ClO_4^-	aq	–128.10 ± 0.40	184.0 ± 1.5	
Cl_2	g	0	223.081 ± 0.010	9.181 ± 0.001
Cs	cr	0	85.23 ± 0.40	7.711 ± 0.020
Cs	g	76.5 ± 1.0	175.601 ± 0.003	6.197 ± 0.001
Cs^+	aq	–258.00 ± 0.50	132.1 ± 0.5	
Cu	cr	0	33.15 ± 0.08	5.004 ± 0.008

Substance	State	$\Delta_f H^\circ$ (298.15 K) kJ·mol^{-1}	S° (298.15 K) J·K^{-1}·mol^{-1}	H° (298.15 K) − H° (0) kJ·mol^{-1}
Cu	g	337.4 ± 1.2	166.398 ± 0.004	6.197 ± 0.001
Cu^{+2}	aq	64.9 ± 1.0	−98 ± 4	
$CuSO_4$	cr	−771.4 ± 1.2	109.2 ± 0.4	16.86 ± 0.08
F	g	79.38 ± 0.30	158.751 ± 0.004	6.518 ± 0.001
F^-	aq	−335.35 ± 0.65	−13.8 ± 0.8	
F_2	g	0	202.791 ± 0.005	8.825 ± 0.001
Ge	cr	0	31.09 ± 0.15	4.636 ± 0.020
Ge	g	372 ± 3	167.904 ± 0.005	7.398 ± 0.001
GeF_4	g	−1190.20 ± 0.50	301.9 ± 1.0	17.29 ± 0.10
GeO_2	cr, tetragonal	−580.0 ± 1.0	39.71 ± 0.15	7.230 ± 0.020
H	g	217.998 ± 0.006	114.717 ± 0.002	6.197 ± 0.001
H^+	aq	0	0	
HBr	g	−36.29 ± 0.16	198.700 ± 0.004	8.648 ± 0.001
HCO_3^-	aq	−689.93 ± 0.20	98.4 ± 0.5	
HCl	g	−92.31 ± 0.10	186.902 ± 0.005	8.640 ± 0.001
HF	g	−273.30 ± 0.70	173.779 ± 0.003	8.599 ± 0.001
HI	g	26.50 ± 0.10	206.590 ± 0.004	8.657 ± 0.001
HPO_4^{-2}	aq	−1299.0 ± 1.5	−33.5 ± 1.5	
HS^-	aq	−16.3 ± 1.5	67 ± 5	
HSO_4^-	aq	−886.9 ± 1.0	131.7 ± 3.0	
H_2	g	0	130.680 ± 0.003	8.468 ± 0.001
H_2O	l	−285.830 ± 0.040	69.95 ± 0.03	13.273 ± 0.020
H_2O	g	−241.826 ± 0.040	188.835 ± 0.010	9.905 ± 0.005
$H_2PO_4^-$	aq	−1302.6 ± 1.5	92.5 ± 1.5	
H_2S	g	−20.6 ± 0.5	205.81 ± 0.05	9.957 ± 0.010
H_2S	aq, undissoc.	−38.6 ± 1.5	126 ± 5	
H_3BO_3	cr	−1094.8 ± 0.8	89.95 ± 0.60	13.52 ± 0.04
H_3BO_3	aq, undissoc.	−1072.8 ± 0.8	162.4 ± 0.6	
He	g	0	126.153 ± 0.002	6.197 ± 0.001
Hg	l	0	75.90 ± 0.12	9.342 ± 0.008
Hg	g	61.38 ± 0.04	174.971 ± 0.005	6.197 ± 0.001
Hg^{+2}	aq	170.21 ± 0.20	−36.19 ± 0.80	
HgO	cr, red	−90.79 ± 0.12	70.25 ± 0.30	9.117 ± 0.025
Hg_2^{+2}	aq	166.87 ± 0.50	65.74 ± 0.80	
Hg_2Cl_2	cr	−265.37 ± 0.40	191.6 ± 0.8	23.35 ± 0.20
Hg_2SO_4	cr	−743.09 ± 0.40	200.70 ± 0.20	26.070 ± 0.030
I	g	106.76 ± 0.04	180.787 ± 0.004	6.197 ± 0.001
I^-	aq	−56.78 ± 0.05	106.45 ± 0.30	
I_2	cr	0	116.14 ± 0.30	13.196 ± 0.040
I_2	g	62.42 ± 0.08	260.687 ± 0.005	10.116 ± 0.001
K	cr	0	64.68 ± 0.20	7.088 ± 0.020
K	g	89.0 ± 0.8	160.341 ± 0.003	6.197 ± 0.001
K^+	aq	−252.14 ± 0.08	101.20 ± 0.20	
Kr	g	0	164.085 ± 0.003	6.197 ± 0.001
Li	cr	0	29.12 ± 0.20	4.632 ± 0.040
Li	g	159.3 ± 1.0	138.782 ± 0.010	6.197 ± 0.001
Li^+	aq	−278.47 ± 0.08	12.24 ± 0.15	
Mg	cr	0	32.67 ± 0.10	4.998 ± 0.030
Mg	g	147.1 ± 0.8	148.648 ± 0.003	6.197 ± 0.001
Mg^{+2}	aq	−467.0 ± 0.6	−137 ± 4	
MgF_2	cr	−1124.2 ± 1.2	57.2 ± 0.5	9.91 ± 0.06
MgO	cr	−601.60 ± 0.30	26.95 ± 0.15	5.160 ± 0.020
N	g	472.68 ± 0.40	153.301 ± 0.003	6.197 ± 0.001
NH_3	g	−45.94 ± 0.35	192.77 ± 0.05	10.043 ± 0.010
NH_4^+	aq	−133.26 ± 0.25	111.17 ± 0.40	
NO_3^-	aq	−206.85 ± 0.40	146.70 ± 0.40	
N_2	g	0	191.609 ± 0.004	8.670 ± 0.001
Na	cr	0	51.30 ± 0.20	6.460 ± 0.020
Na	g	107.5 ± 0.7	153.718 ± 0.003	6.197 ± 0.001
Na^+	aq	−240.34 ± 0.06	58.45 ± 0.15	

Substance	State	$\Delta_f H^\circ$ (298.15 K) / kJ·mol^{-1}	S° (298.15 K) / J·K^{-1}·mol^{-1}	H° (298.15 K) − H° (0) / kJ·mol^{-1}
Ne	g	0	146.328 ± 0.003	6.197 ± 0.001
O	g	249.18 ± 0.10	161.059 ± 0.003	6.725 ± 0.001
OH^-	aq	−230.015 ± 0.040	−10.90 ± 0.20	
O_2	g	0	205.152 ± 0.005	8.680 ± 0.002
P	cr, white	0	41.09 ± 0.25	5.360 ± 0.015
P	g	316.5 ± 1.0	163.199 ± 0.003	6.197 ± 0.001
P_2	g	144.0 ± 2.0	218.123 ± 0.004	8.904 ± 0.001
P_4	g	58.9 ± 0.3	280.01 ± 0.50	14.10 ± 0.20
Pb	cr	0	64.80 ± 0.30	6.870 ± 0.030
Pb	g	195.2 ± 0.8	175.375 ± 0.005	6.197 ± 0.001
Pb^{+2}	aq	0.92 ± 0.25	18.5 ± 1.0	
$PbSO_4$	cr	−919.97 ± 0.40	148.50 ± 0.60	20.050 ± 0.040
Rb	cr	0	76.78 ± 0.30	7.489 ± 0.020
Rb	g	80.9 ± 0.8	170.094 ± 0.003	6.197 ± 0.001
Rb^+	aq	−251.12 ± 0.10	121.75 ± 0.25	
S	cr, rhombic	0	32.054 ± 0.050	4.412 ± 0.006
S	g	277.17 ± 0.15	167.829 ± 0.006	6.657 ± 0.001
SO_2	g	−296.81 ± 0.20	248.223 ± 0.050	10.549 ± 0.010
SO_4^{-2}	aq	−909.34 ± 0.40	18.50 ± 0.40	
S_2	g	128.60 ± 0.30	228.167 ± 0.010	9.132 ± 0.002
Si	cr	0	18.81 ± 0.08	3.217 ± 0.008
Si	g	450 ± 8	167.981 ± 0.004	7.550 ± 0.001
SiF_4	g	−1615.0 ± 0.8	282.76 ± 0.50	15.36 ± 0.05
SiO_2	cr, alpha quartz	−910.7 ± 1.0	41.46 ± 0.20	6.916 ± 0.020
Sn	cr, white	0	51.18 ± 0.08	6.323 ± 0.008
Sn	g	301.2 ± 1.5	168.492 ± 0.004	6.215 ± 0.001
Sn^{+2}	aq	−8.9 ± 1.0	−16.7 ± 4.0	
SnO	cr, tetragonal	−280.71 ± 0.20	57.17 ± 0.30	8.736 ± 0.020
SnO_2	cr, tetragonal	−577.63 ± 0.20	49.04 ± 0.10	8.384 ± 0.020
Th	cr	0	51.8 ± 0.5	6.35 ± 0.05
Th	g	602 ± 6	190.17 ± 0.05	6.197 ± 0.003
ThO_2	cr	−1226.4 ± 3.5	65.23 ± 0.20	10.560 ± 0.020
Ti	cr	0	30.72 ± 0.10	4.824 ± 0.015
Ti	g	473 ± 3	180.298 ± 0.010	7.539 ± 0.002
$TiCl_4$	g	−763.2 ± 3.0	353.2 ± 4.0	21.5 ± 0.5
TiO_2	cr, rutile	−944.0 ± 0.8	50.62 ± 0.30	8.68 ± 0.05
U	cr	0	50.20 ± 0.20	6.364 ± 0.020
U	g	533 ± 8	199.79 ± 0.10	6.499 ± 0.020
UO_2	cr	−1085.0 ± 1.0	77.03 ± 0.20	11.280 ± 0.020
UO_2^{+2}	aq	−1019.0 ± 1.5	−98.2 ± 3.0	
UO_3	cr, gamma	−1223.8 ± 1.2	96.11 ± 0.40	14.585 ± 0.050
U_3O_8	cr	−3574.8 ± 2.5	282.55 ± 0.50	42.74 ± 0.10
Xe	g	0	169.685 ± 0.003	6.197 ± 0.001
Zn	cr	0	41.63 ± 0.15	5.657 ± 0.020
Zn	g	130.40 ± 0.40	160.990 ± 0.004	6.197 ± 0.001
Zn^{+2}	aq	−153.39 ± 0.20	−109.8 ± 0.5	
ZnO	cr	−350.46 ± 0.27	43.65 ± 0.40	6.933 ± 0.040

STANDARD THERMODYNAMIC PROPERTIES OF CHEMICAL SUBSTANCES

This table gives the standard state chemical thermodynamic properties of about 2500 individual substances in the crystalline, liquid, and gaseous states. Substances are listed by molecular formula in a modified Hill order; all substances not containing carbon appear first, followed by those that contain carbon. The properties tabulated are:

- $\Delta_f H°$ Standard molar enthalpy (heat) of formation at 298.15 K in kJ/mol
- $\Delta_f G°$ Standard molar Gibbs energy of formation at 298.15 K in kJ/mol
- $S°$ Standard molar entropy at 298.15 K in J/mol K
- C_p Molar heat capacity at constant pressure at 298.15 K in J/mol K

The standard state pressure is 100 kPa (1 bar). The standard states are defined for different phases by:

- The standard state of a pure gaseous substance is that of the substance as a (hypothetical) ideal gas at the standard state pressure.
- The standard state of a pure liquid substance is that of the liquid under the standard state pressure.
- The standard state of a pure crystalline substance is that of the crystalline substance under the standard state pressure.

An entry of 0.0 for $\Delta_f H°$ for an element indicates the reference state of that element. See References 1 and 2 for further information on reference states. A blank means no value is available.

The data are derived from the sources listed in the references, from other papers appearing in the *Journal of Physical and Chemical Reference Data*, and from the primary research literature. We are indebted to M. V. Korobov for providing data on fullerene compounds.

References

1. Cox, J. D., Wagman, D. D., and Medvedev, V. A., *CODATA Key Values for Thermodynamics,* Hemisphere Publishing Corp., New York, 1989.
2. Wagman, D. D., Evans, W. H., Parker, V. B., Schumm, R. H., Halow, I., Bailey, S. M., Churney, K. L., and Nuttall, R. L., *The NBS Tables of Chemical Thermodynamic Properties, J. Phys. Chem. Ref. Data,* Vol. 11, Suppl. 2, 1982.
3. Chase, M. W., Davies, C. A., Downey, J. R., Frurip, D. J., McDonald, R. A., and Syverud, A. N., *JANAF Thermochemical Tables, Third Edition, J. Phys. Chem. Ref. Data*, Vol. 14, Suppl.1, 1985.
4. Chase, M. W., *NIST-JANAF Thermochemical Tables, Fourth Edition*, *J. Phys. Chem. Ref. Data*, Monograph 9, 1998.
5. Daubert, T. E., Danner, R. P., Sibul, H. M., and Stebbins, C. C., *Physical and Thermodynamic Properties of Pure Compounds: Data Compilation*, extant 1994 (core with 4 supplements), Taylor & Francis, Bristol, PA.
6. Pedley, J. B., Naylor, R. D., and Kirby, S. P., *Thermochemical Data of Organic Compounds, Second Edition*, Chapman & Hall, London, 1986.
7. Pedley, J. B., *Thermochemical Data and Structures of Organic Compounds,* Thermodynamic Research Center, Texas A & M University, College Station, TX, 1994.
8. Domalski, E. S., and Hearing, E. D., Heat Capacities and Entropies of Organic Compounds in the Condensed Phase, Volume III, *J. Phys. Chem. Ref. Data*, 25, 1-525, 1996.
9. Zabransky, M., Ruzicka , V., Majer, V., and Domalski, E. S., *Heat Capacity of Liquids*, *J. Phys. Chem. Ref. Data,* Monograph No. 6, 1996.
10. Gurvich, L. V., Veyts, I.V., and Alcock, C. B., *Thermodynamic Properties of Individual Substances, Fourth Edition*, *Vol. 1,* Hemisphere Publishing Corp., New York, 1989.
11. Gurvich, L. V., Veyts, I.V., and Alcock, C. B., *Thermodynamic Properties of Individual Substances, Fourth Edition, Vol. 3,* CRC Press, Boca Raton, FL, 1994.
12. *NIST Chemistry Webbook*, <webbook.nist.gov>

Molecular formula	Name	Crystal $\Delta_f H°$ kJ/mol	Crystal $\Delta_f G°$ kJ/mol	Crystal $S°$ J/mol K	Crystal C_p J/mol K	Liquid $\Delta_f H°$ kJ/mol	Liquid $\Delta_f G°$ kJ/mol	Liquid $S°$ J/mol K	Liquid C_p J/mol K	Gas $\Delta_f H°$ kJ/mol	Gas $\Delta_f G°$ kJ/mol	Gas $S°$ J/mol K	Gas C_p J/mol K
Substances not containing carbon:													
Ac	Actinium	0.0		56.5	27.2					406.0	366.0	188.1	20.8
Ag	Silver	0.0		42.6	25.4					284.9	246.0	173.0	20.8
AgBr	Silver(I) bromide	-100.4	-96.9	107.1	52.4								
$AgBrO_3$	Silver(I) bromate	-10.5	71.3	151.9									
AgCl	Silver(I) chloride	-127.0	-109.8	96.3	50.8								
$AgClO_3$	Silver(I) chlorate	-30.3	64.5	142.0									
$AgClO_4$	Silver(I) perchlorate	-31.1											
AgF	Silver(I) fluoride	-204.6											
AgF_2	Silver(II) fluoride	-360.0											
AgI	Silver(I) iodide	-61.8	-66.2	115.5	56.8								
$AgIO_3$	Silver(I) iodate	-171.1	-93.7	149.4	102.9								
$AgNO_3$	Silver(I) nitrate	-124.4	-33.4	140.9	93.1								
Ag_2	Disilver									410.0	358.8	257.1	37.0
Ag_2CrO_4	Silver(I) chromate	-731.7	-641.8	217.6	142.3								
Ag_2O	Silver(I) oxide	-31.1	-11.2	121.3	65.9								
Ag_2O_2	Silver(II) oxide	-24.3	27.6	117.0	88.0								
Ag_2O_3	Silver(III) oxide	33.9	121.4	100.0									
Ag_2O_4S	Silver(I) sulfate	-715.9	-618.4	200.4	131.4								
Ag_2S	Silver(I) sulfide (argentite)	-32.6	-40.7	144.0	76.5								
Al	Aluminum	0.0		28.3	24.4					330.0	289.4	164.6	21.4

Molecular formula	Name	Crystal				Liquid				Gas			
		$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
AlB_3H_{12}	Aluminum borohydride					-16.3	145.0	289.1	194.6	13.0	147.0	379.2	
AlBr	Aluminum monobromide									-4.0	-42.0	239.5	35.6
$AlBr_3$	Aluminum bromide	-527.2		180.2	100.6					-425.1			
AlCl	Aluminum monochloride									-47.7	-74.1	228.1	35.0
$AlCl_2$	Aluminum dichloride									-331.0			
$AlCl_3$	Aluminum chloride	-704.2	-628.8	109.3	91.1					-583.2			
AlF	Aluminum monofluoride									-258.2	-283.7	215.0	31.9
AlF_3	Aluminum fluoride	-1510.4	-1431.1	66.5	75.1					-1204.6	-1188.2	277.1	62.6
AlF_4Na	Sodium tetrafluoroaluminate									-1869.0	-1827.5	345.7	105.9
AlH	Aluminum monohydride									259.2	231.2	187.9	29.4
AlH_3	Aluminum hydride	-46.0		30.0	40.2								
AlH_4K	Potassium aluminum hydride	-183.7											
AlH_4Li	Lithium aluminum hydride	-116.3	-44.7	78.7	83.2								
AlH_4Na	Sodium aluminum hydride	-115.5											
AlI	Aluminum monoiodide									65.5			36.0
AlI_3	Aluminum iodide	-313.8	-300.8	159.0	98.7					-207.5			
AlN	Aluminum nitride	-318.0	-287.0	20.2	30.1								
AlO	Aluminum monoxide									91.2	65.3	218.4	30.9
AlO_4P	Aluminum phosphate	-1733.8	-1617.9	90.8	93.2								
AlP	Aluminum phosphide	-166.5											
AlS	Aluminum monosulfide									200.9	150.1	230.6	33.4
Al_2	Dialuminum									485.9	433.3	233.2	36.4
Al_2Br_6	Aluminum hexabromide									-970.7			
Al_2Cl_6	Aluminum hexachloride									-1290.8	-1220.4	490.0	
Al_2F_6	Aluminum hexafluoride									-2628.0			
Al_2I_6	Aluminum hexaiodide									-516.7			
Al_2O	Aluminum oxide (Al_2O)									-130.0	-159.0	259.4	45.7
Al_2O_3	Aluminum oxide (corundum)	-1675.7	-1582.3	50.9	79.0								
Al_2S_3	Aluminum sulfide	-724.0		116.9	105.1								
Am	Americium	0.0											
Ar	Argon									0.0		154.8	20.8
As	Arsenic (gray)	0.0		35.1	24.6					302.5	261.0	174.2	20.8
As	Arsenic (yellow)	14.6											
$AsBr_3$	Arsenic(III) bromide	-197.5								-130.0	-159.0	363.9	79.2
$AsCl_3$	Arsenic(III) chloride					-305.0	-259.4	216.3		-261.5	-248.9	327.2	75.7
AsF_3	Arsenic(III) fluoride					-821.3	-774.2	181.2	126.6	-785.8	-770.8	289.1	65.6
AsGa	Gallium arsenide	-71.0	-67.8	64.2	46.2								
AsH_3	Arsine									66.4	68.9	222.8	38.1
AsH_3O_4	Arsenic acid	-906.3											
AsI_3	Arsenic(III) iodide	-58.2	-59.4	213.1	105.8							388.3	80.6
AsIn	Indium arsenide	-58.6	-53.6	75.7	47.8								
AsO	Arsenic monoxide									70.0			
As_2	Diarsenic									222.2	171.9	239.4	35.0
As_2O_5	Arsenic(V) oxide	-924.9	-782.3	105.4	116.5								
As_2S_3	Arsenic(III) sulfide	-169.0	-168.6	163.6	116.3								
At	Astatine	0.0											
Au	Gold	0.0		47.4	25.4					366.1	326.3	180.5	20.8
AuBr	Gold(I) bromide	-14.0											
$AuBr_3$	Gold(III) bromide	-53.3											
AuCl	Gold(I) chloride	-34.7											
$AuCl_3$	Gold(III) chloride	-117.6											
AuF_3	Gold(III) fluoride	-363.6											
AuH	Gold hydride									295.0	265.7	211.2	29.2
AuI	Gold(I) iodide	0.0											
Au_2	Digold									515.1			36.9
B	Boron (β-rhombohedral)	0.0		5.9	11.1					565.0	521.0	153.4	20.8
BBr	Bromoborane(1)									238.1	195.4	225.0	32.9
BBr_3	Boron tribromide					-239.7	-238.5	229.7		-205.6	-232.5	324.2	67.8
BCl	Chloroborane(1)									149.5	120.9	213.2	31.7
BClO	Chloroxyborane									-314.0			
BCl_3	Boron trichloride					-427.2	-387.4	206.3	106.7	-403.8	-388.7	290.1	62.7
$BCsO_2$	Cesium metaborate	-972.0	-915.0	104.4	80.6								
BF	Fluoroborane(1)									-122.2	-149.8	200.5	29.6
BFO	Fluorooxyborane									-607.0			
BF_3	Boron trifluoride									-1136.0	-1119.4	254.4	
BF_3H_3N	Aminetrifluoroboron	-1353.9											

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
BF_3H_3P	Trihydro(phosphorus trifluoride)boron									-854.0			
BF_4Na	Sodium tetrafluoroborate	-1844.7	-1750.1	145.3	120.3								
BH	Borane(1)									442.7	412.7	171.8	29.2
BHO_2	Metaboric acid (β, monoclinic)	-794.3	-723.4	38.0						-561.9	-551.0	240.1	42.2
BH_3	Borane(3)									89.2	93.3	188.2	36.0
BH_3O_3	Boric acid	-1094.3	-968.9	90.0	86.1					-994.1			
BH_4K	Potassium borohydride	-227.4	-160.3	106.3	96.1								
BH_4Li	Lithium borohydride	-190.8	-125.0	75.9	82.6								
BH_4Na	Sodium borohydride	-188.6	-123.9	101.3	86.8								
BI_3	Boron triiodide									71.1	20.7	349.2	70.8
BKO_2	Potassium metaborate	-981.6	-923.4	80.0	66.7								
$BLiO_2$	Lithium metaborate	-1032.2	-976.1	51.5	59.8								
BN	Boron nitride	-254.4	-228.4	14.8	19.7					647.5	614.5	212.3	29.5
$BNaO_2$	Sodium metaborate	-977.0	-920.7	73.5	65.9								
BO	Boron monoxide									25.0	-4.0	203.5	29.2
BO_2	Boron dioxide									-300.4	-305.9	229.6	43.0
BO_2Rb	Rubidium metaborate	-971.0	-913.0	94.3	74.1								
BS	Boron monosulfide									342.0	288.8	216.2	30.0
B_2	Diboron									830.5	774.0	201.9	30.5
B_2Cl_4	Tetrachlorodiborane					-523.0	-464.8	262.3	137.7	-490.4	-460.6	357.4	95.4
B_2F_4	Tetrafluorodiborane									-1440.1	-1410.4	317.3	79.1
B_2H_6	Diborane									36.4	87.6	232.1	56.7
B_2O_2	Diboron dioxide									-454.8	-462.3	242.5	57.3
B_2O_3	Boron oxide	-1273.5	-1194.3	54.0	62.8					-843.8	-832.0	279.8	66.9
B_2S_3	Boron sulfide	-240.6		100.0	111.7					67.0			
$B_3H_6N_3$	Borazine					-541.0	-392.7	199.6					
B_4H_{10}	Tetraborane(10)									66.1	184.3	280.3	93.2
$B_4Na_2O_7$	Sodium tetraborate	-3291.1	-3096.0	189.5	186.8								
B_5H_9	Pentaborane(9)					42.7	171.8	184.2	151.1	73.2	173.6	280.6	99.6
B_5H_{11}	Pentaborane(11)					73.2				103.3	230.6	321.0	130.3
B_6H_{10}	Hexaborane(10)					56.3				94.6	211.3	296.8	125.7
B_9H_{15}	Nonaborane(15)									158.4	357.5	364.9	187.0
$B_{10}H_{14}$	Decaborane(14)									47.3	232.8	350.7	186.1
Ba	Barium	0.0		62.5	28.1					180.0	146.0	170.2	20.8
$BaBr_2$	Barium bromide	-757.3	-736.8	146.0									
$BaCl_2$	Barium chloride	-855.0	-806.7	123.7	75.1								
$BaCl_2H_4O_2$	Barium chloride dihydrate	-1456.9	-1293.2	203.0									
BaF_2	Barium fluoride	-1207.1	-1156.8	96.4	71.2								
BaH_2	Barium hydride	-177.0	-138.2	63.0	46.0								
BaH_2O_2	Barium hydroxide	-944.7											
BaI_2	Barium iodide	-602.1											
BaN_2O_4	Barium nitrite	-768.2											
BaN_2O_6	Barium nitrate	-988.0	-792.6	214.0	151.4								
BaO	Barium oxide	-548.0	-520.3	72.1	47.3					-112.0			
BaO_4S	Barium sulfate	-1473.2	-1362.2	132.2	101.8								
BaS	Barium sulfide	-460.0	-456.0	78.2	49.4								
Be	Beryllium	0.0		9.5	16.4					324.0	286.6	136.3	20.8
$BeBr_2$	Beryllium bromide	-353.5		108.0	69.4								
$BeCl_2$	Beryllium chloride	-490.4	-445.6	75.8	62.4								
BeF_2	Beryllium fluoride	-1026.8	-979.4	53.4	51.8								
BeH_2O_2	Beryllium hydroxide	-902.5	-815.0	45.5	62.1								
BeI_2	Beryllium iodide	-192.5		121.0	71.1								
BeO	Beryllium oxide	-609.4	-580.1	13.8	25.6								
BeO_4S	Beryllium sulfate	-1205.2	-1093.8	77.9	85.7								
BeS	Beryllium sulfide	-234.3		34.0	34.0								
Bi	Bismuth	0.0		56.7	25.5					207.1	168.2	187.0	20.8
BiClO	Bismuth oxychloride	-366.9	-322.1	120.5									
$BiCl_3$	Bismuth trichloride	-379.1	-315.0	177.0	105.0					-265.7	-256.0	358.9	79.7
BiH_3O_3	Bismuth hydroxide	-711.3											
BiI_3	Bismuth triiodide		-175.3										
Bi_2	Dibismuth									219.7			36.9
Bi_2O_3	Bismuth oxide	-573.9	-493.7	151.5	113.5								
$Bi_2O_{12}S_3$	Bismuth sulfate	-2544.3											
Bi_2S_3	Bismuth sulfide	-143.1	-140.6	200.4	122.2								
Bk	Berkelium	0.0											

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
Br	Bromine (atomic)									111.9	82.4	175.0	20.8
BrCl	Bromine chloride									14.6	-1.0	240.1	35.0
$BrCl_3Si$	Bromotrichlorosilane											350.1	90.9
BrCs	Cesium bromide	-405.8	-391.4	113.1	52.9								
BrCu	Copper(I) bromide	-104.6	-100.8	96.1	54.7								
BrF	Bromine fluoride									-93.8	-109.2	229.0	33.0
BrF_3	Bromine trifluoride					-300.8	-240.5	178.2	124.6	-255.6	-229.4	292.5	66.6
BrF_5	Bromine pentafluoride					-458.6	-351.8	225.1		-428.9	-350.6	320.2	99.6
BrGe	Germanium monobromide									235.6			37.1
$BrGeH_3$	Bromogermane											274.8	56.4
BrH	Hydrogen bromide									-36.3	-53.4	198.7	29.1
BrHSi	Bromosilylene									-464.4			
BrH_3Si	Bromosilane											262.4	52.8
BrH_4N	Ammonium bromide	-270.8	-175.2	113.0	96.0								
BrI	Iodine bromide									40.8	3.7	258.8	36.4
BrIn	Indium(I) bromide	-175.3	-169.0	113.0						-56.9	-94.3	259.5	36.7
BrK	Potassium bromide	-393.8	-380.7	95.9	52.3								
$BrKO_3$	Potassium bromate	-360.2	-271.2	149.2	105.2								
$BrKO_4$	Potassium perbromate	-287.9	-174.4	170.1	120.2								
BrLi	Lithium bromide	-351.2	-342.0	74.3									
BrNO	Nitrosyl bromide									82.2	82.4	273.7	45.5
BrNa	Sodium bromide	-361.1	-349.0	86.8	51.4					-143.1	-177.1	241.2	36.3
$BrNaO_3$	Sodium bromate	-334.1	-242.6	128.9									
BrO	Bromine monoxide									125.8	109.6	233.0	34.2
BrO_2	Bromine dioxide									152.0	155.0	271.1	45.4
BrRb	Rubidium bromide	-394.6	-381.8	110.0	52.8								
BrSi	Bromosilyldyne									209.0			38.6
BrTl	Thallium(I) bromide	-173.2	-167.4	120.5						-37.7			
Br_2	Bromine					0.0		152.2	75.7	30.9	3.1	245.5	36.0
Br_2Ca	Calcium bromide	-682.8	-663.6	130.0									
Br_2Cd	Cadmium bromide	-316.2	-296.3	137.2	76.7								
Br_2Co	Cobalt(II) bromide	-220.9			79.5								
Br_2Cr	Chromium(II) bromide	-302.1											
Br_2Cu	Copper(II) bromide	-141.8											
Br_2Fe	Iron(II) bromide	-249.8	-238.1	140.6									
Br_2H_2Si	Dibromosilane											309.7	65.5
Br_2Hg	Mercury(II) bromide	-170.7	-153.1	172.0									
Br_2Hg_2	Mercury(I) bromide	-206.9	-181.1	218.0									
Br_2Mg	Magnesium bromide	-524.3	-503.8	117.2									
Br_2Mn	Manganese(II) bromide	-384.9											
Br_2Ni	Nickel(II) bromide	-212.1											
Br_2Pb	Lead(II) bromide	-278.7	-261.9	161.5	80.1								
Br_2Pt	Platinum(II) bromide	-82.0											
Br_2S_2	Sulfur bromide					-13.0							
Br_2Se	Selenium dibromide									-21.0			
Br_2Sn	Tin(II) bromide	-243.5											
Br_2Sr	Strontium bromide	-717.6	-697.1	135.1	75.3								
Br_2Ti	Titanium(II) bromide	-402.0											
Br_2Zn	Zinc bromide	-328.7	-312.1	138.5									
Br_3Ce	Cerium(III) bromide	-891.4											
Br_3ClSi	Tribromochlorosilane											377.1	95.3
Br_3Dy	Dysprosium(III) bromide	-836.2											
Br_3Fe	Iron(III) bromide	-268.2											
Br_3Ga	Gallium(III) bromide	-386.6	-359.8	180.0									
Br_3HSi	Tribromosilane					-355.6	-336.4	248.1		-317.6	-328.5	348.6	80.8
Br_3In	Indium(III) bromide	-428.9								-282.0			
Br_3OP	Phosphoric tribromide	-458.6										359.8	89.9
Br_3P	Phosphorus(III) bromide					-184.5	-175.7	240.2		-139.3	-162.8	348.1	76.0
Br_3Pt	Platinum(III) bromide	-120.9											
Br_3Re	Rhenium(III) bromide	-167.0											
Br_3Ru	Ruthenium(III) bromide	-138.0											
Br_3Sb	Antimony(III) bromide	-259.4	-239.3	207.1						-194.6	-223.9	372.9	80.2
Br_3Sc	Scandium bromide	-743.1											
Br_3Ti	Titanium(III) bromide	-548.5	-523.8	176.6	101.7								
Br_4Ge	Germanium(IV) bromide					-347.7	-331.4	280.7		-300.0	-318.0	396.2	101.8
Br_4Pa	Protactinium(IV) bromide	-824.0	-787.8	234.0									

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
Br_4Pt	Platinum(IV) bromide	-156.5											
Br_4Si	Tetrabromosilane					-457.3	-443.9	277.8		-415.5	-431.8	377.9	97.1
Br_4Sn	Tin(IV) bromide	-377.4	-350.2	264.4						-314.6	-331.4	411.9	103.4
Br_4Te	Tellurium tetrabromide	-190.4											
Br_4Ti	Titanium(IV) bromide	-616.7	-589.5	243.5	131.5					-549.4	-568.2	398.4	100.8
Br_4V	Vanadium(IV) bromide									-336.8			
Br_4Zr	Zirconium(IV) bromide	-760.7											
Br_5P	Phosphorus(V) bromide	-269.9											
Br_5Ta	Tantalum(V) bromide	-598.3											
Br_6W	Tungsten(VI) bromide	-348.5											
Ca	Calcium	0.0		41.6	25.9					177.8	144.0	154.9	20.8
$CaCl_2$	Calcium chloride	-795.4	-748.8	108.4	72.9								
CaF_2	Calcium fluoride	-1228.0	-1175.6	68.5	67.0								
CaH_2	Calcium hydride	-181.5	-142.5	41.4	41.0								
CaH_2O_2	Calcium hydroxide	-985.2	-897.5	83.4	87.5								
CaI_2	Calcium iodide	-533.5	-528.9	142.0									
CaN_2O_6	Calcium nitrate	-938.2	-742.8	193.2	149.4								
CaO	Calcium oxide	-634.9	-603.3	38.1	42.0								
CaO_4S	Calcium sulfate	-1434.5	-1322.0	106.5	99.7								
CaS	Calcium sulfide	-482.4	-477.4	56.5	47.4								
$Ca_3O_8P_2$	Calcium phosphate	-4120.8	-3884.7	236.0	227.8								
Cd	Cadmium	0.0		51.8	26.0					111.8		167.7	20.8
$CdCl_2$	Cadmium chloride	-391.5	-343.9	115.3	74.7								
CdF_2	Cadmium fluoride	-700.4	-647.7	77.4									
CdH_2O_2	Cadmium hydroxide	-560.7	-473.6	96.0									
CdI_2	Cadmium iodide	-203.3	-201.4	161.1	80.0								
CdO	Cadmium oxide	-258.4	-228.7	54.8	43.4								
CdO_4S	Cadmium sulfate	-933.3	-822.7	123.0	99.6								
CdS	Cadmium sulfide	-161.9	-156.5	64.9									
CdTe	Cadmium telluride	-92.5	-92.0	100.0									
Ce	Cerium (γ, fcc)	0.0		72.0	26.9					423.0	385.0	191.8	23.1
$CeCl_3$	Cerium(III) chloride	-1060.5	-984.8	151.0	87.4								
CeI_3	Cerium(III) iodide	-669.3											
CeO_2	Cerium(IV) oxide	-1088.7	-1024.6	62.3	61.6								
CeS	Cerium(II) sulfide	-459.4	-451.5	78.2	50.0								
Ce_2O_3	Cerium(III) oxide	-1796.2	-1706.2	150.6	114.6								
Cf	Californium	0.0											
Cl	Chlorine (atomic)									121.3	105.3	165.2	21.8
ClCs	Cesium chloride	-443.0	-414.5	101.2	52.5								
$ClCsO_4$	Cesium perchlorate	-443.1	-314.3	175.1	108.3								
ClCu	Copper(I) chloride	-137.2	-119.9	86.2	48.5								
ClF	Chlorine fluoride									-50.3	-51.8	217.9	32.1
$ClFO_3$	Perchloryl fluoride									-23.8	48.2	279.0	64.9
ClF_3	Chlorine trifluoride					-189.5				-163.2	-123.0	281.6	63.9
ClF_5S	Sulfur chloride pentafluoride					-1065.7							
ClGe	Germanium monochloride									155.2	124.2	247.0	36.9
$ClGeH_3$	Chlorogermane											263.7	54.7
ClH	Hydrogen chloride									-92.3	-95.3	186.9	29.1
ClHO	Hypochlorous acid									-78.7	-66.1	236.7	37.2
$ClHO_4$	Perchloric acid					-40.6							
ClH_3Si	Chlorosilane											250.7	51.0
ClH_4N	Ammonium chloride	-314.4	-202.9	94.6	84.1								
ClH_4NO_4	Ammonium perchlorate	-295.3	-88.8	186.2									
ClH_4P	Phosphonium chloride	-145.2											
ClI	Iodine chloride					-23.9	-13.6	135.1		17.8	-5.5	247.6	35.6
ClIn	Indium(I) chloride	-186.2								-75.0			
ClK	Potassium chloride	-436.5	-408.5	82.6	51.3					-214.6	-233.3	239.1	36.5
$ClKO_3$	Potassium chlorate	-397.7	-296.3	143.1	100.3								
$ClKO_4$	Potassium perchlorate	-432.8	-303.1	151.0	112.4								
ClLi	Lithium chloride	-408.6	-384.4	59.3	48.0								
$ClLiO_4$	Lithium perchlorate	-381.0											
ClNO	Nitrosyl chloride									51.7	66.1	261.7	44.7
$ClNO_2$	Nitryl chloride									12.6	54.4	272.2	53.2
ClNa	Sodium chloride	-411.2	-384.1	72.1	50.5								
$ClNaO_2$	Sodium chlorite	-307.0											
$ClNaO_3$	Sodium chlorate	-365.8	-262.3	123.4									

Molecular formula	Name	Crystal $\Delta_f H°$ kJ/mol	Crystal $\Delta_f G°$ kJ/mol	Crystal $S°$ J/mol K	Crystal C_p J/mol K	Liquid $\Delta_f H°$ kJ/mol	Liquid $\Delta_f G°$ kJ/mol	Liquid $S°$ J/mol K	Liquid C_p J/mol K	Gas $\Delta_f H°$ kJ/mol	Gas $\Delta_f G°$ kJ/mol	Gas $S°$ J/mol K	Gas C_p J/mol K
$ClNaO_4$	Sodium perchlorate	-383.3	-254.9	142.3									
ClO	Chlorine oxide									101.8	98.1	226.6	31.5
ClOV	Vanadyl chloride	-607.0	-556.0	75.0									
ClO_2	Chlorine dioxide									102.5	120.5	256.8	42.0
ClO_2	Chlorine superoxide (ClOO)									89.1	105.0	263.7	46.0
ClO_4Rb	Rubidium perchlorate	-437.2	-306.9	161.1									
ClRb	Rubidium chloride	-435.4	-407.8	95.9	52.4								
ClSi	Chlorosilylidyne									189.9			36.9
ClTl	Thallium(I) chloride	-204.1	-184.9	111.3	50.9					-67.8			
Cl_2	Chlorine									0.0		223.1	33.9
Cl_2Co	Cobalt(II) chloride	-312.5	-269.8	109.2	78.5								
Cl_2Cr	Chromium(II) chloride	-395.4	-356.0	115.3	71.2								
Cl_2CrO_2	Chromyl chloride					-579.5	-510.8	221.8		-538.1	-501.6	329.8	84.5
Cl_2Cu	Copper(II) chloride	-220.1	-175.7	108.1	71.9								
Cl_2Fe	Iron(II) chloride	-341.8	-302.3	118.0	76.7								
Cl_2H_2Si	Dichlorosilane											285.7	60.5
Cl_2Hg	Mercury(II) chloride	-224.3	-178.6	146.0									
Cl_2Hg_2	Mercury(I) chloride	-265.4	-210.7	191.6									
Cl_2Mg	Magnesium chloride	-641.3	-591.8	89.6	71.4								
Cl_2Mn	Manganese(II) chloride	-481.3	-440.5	118.2	72.9								
Cl_2Ni	Nickel(II) chloride	-305.3	-259.0	97.7	71.7								
Cl_2O	Chlorine monoxide									80.3	97.9	266.2	45.4
Cl_2OS	Thionyl chloride					-245.6			121.0	-212.5	-198.3	309.8	66.5
Cl_2O_2S	Sulfuryl chloride					-394.1			134.0	-364.0	-320.0	311.9	77.0
Cl_2O_2U	Uranyl chloride	-1243.9	-1146.4	150.5	107.9								
Cl_2Pb	Lead(II) chloride	-359.4	-314.1	136.0									
Cl_2Pt	Platinum(II) chloride	-123.4											
Cl_2S	Sulfur dichloride					-50.0							
Cl_2S_2	Sulfur chloride					-59.4							
Cl_2Sn	Tin(II) chloride	-325.1											
Cl_2Sr	Strontium chloride	-828.9	-781.1	114.9	75.6								
Cl_2Ti	Titanium(II) chloride	-513.8	-464.4	87.4	69.8								
Cl_2Zn	Zinc chloride	-415.1	-369.4	111.5	71.3					-266.1			
Cl_2Zr	Zirconium(II) chloride	-502.0											
Cl_3Cr	Chromium(III) chloride	-556.5	-486.1	123.0	91.8								
Cl_3Dy	Dysprosium(III) chloride	-1000.0											
Cl_3Er	Erbium chloride	-998.7			100.0								
Cl_3Eu	Europium(III) chloride	-936.0											
Cl_3Fe	Iron(III) chloride	-399.5	-334.0	142.3	96.7								
Cl_3Ga	Gallium(III) chloride	-524.7	-454.8	142.0									
Cl_3Gd	Gadolinium(III) chloride	-1008.0			88.0								
Cl_3HSi	Trichlorosilane					-539.3	-482.5	227.6		-513.0	-482.0	313.9	75.8
Cl_3Ho	Holmium chloride	-1005.4			88.0								
Cl_3In	Indium(III) chloride	-537.2								-374.0			
Cl_3Ir	Iridium(III) chloride	-245.6											
Cl_3La	Lanthanum chloride	-1072.2			108.8								
Cl_3Lu	Lutetium chloride	-945.6								-649.0			
Cl_3N	Nitrogen trichloride					230.0							
Cl_3Nd	Neodymium chloride	-1041.0			113.0								
Cl_3OP	Phosphoric trichloride					-597.1	-520.8	222.5	138.8	-558.5	-512.9	325.5	84.9
Cl_3OV	Vanadyl trichloride					-734.7	-668.5	244.3		-695.6	-659.3	344.3	89.9
Cl_3Os	Osmium(III) chloride	-190.4											
Cl_3P	Phosphorus(III) chloride					-319.7	-272.3	217.1		-287.0	-267.8	311.8	71.8
Cl_3Pr	Praseodymium chloride	-1056.9			100.0								
Cl_3Pt	Platinum(III) chloride	-182.0											
Cl_3Re	Rhenium(III) chloride	-264.0	-188.0	123.8	92.4								
Cl_3Rh	Rhodium(III) chloride	-299.2											
Cl_3Ru	Ruthenium(III) chloride	-205.0											
Cl_3Sb	Antimony(III) chloride	-382.2	-323.7	184.1	107.9								
Cl_3Sc	Scandium chloride	-925.1											
Cl_3Sm	Samarium(III) chloride	-1025.9											
Cl_3Tb	Terbium chloride	-997.0											
Cl_3Ti	Titanium(III) chloride	-720.9	-653.5	139.7	97.2								
Cl_3Tl	Thallium(III) chloride	-315.1											
Cl_3Tm	Thulium chloride	-986.6											
Cl_3U	Uranium(III) chloride	-866.5	-799.1	159.0	102.5								

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
Cl_3V	Vanadium(III) chloride	-580.7	-511.2	131.0	93.2								
Cl_3Y	Yttrium chloride	-1000.0								-750.2			75.0
Cl_3Yb	Ytterbium(III) chloride	-959.8											
Cl_4Ge	Germanium(IV) chloride					-531.8	-462.7	245.6		-495.8	-457.3	347.7	96.1
Cl_4Hf	Hafnium(IV) chloride	-990.4	-901.3	190.8	120.5					-884.5			
Cl_4Pa	Protactinium(IV) chloride	-1043.0	-953.0	192.0									
Cl_4Pb	Lead(IV) chloride					-329.3							
Cl_4Pt	Platinum(IV) chloride	-231.8											
Cl_4Si	Tetrachlorosilane					-687.0	-619.8	239.7	145.3	-657.0	-617.0	330.7	90.3
Cl_4Sn	Tin(IV) chloride					-511.3	-440.1	258.6	165.3	-471.5	-432.2	365.8	98.3
Cl_4Te	Tellurium tetrachloride	-326.4			138.5								
Cl_4Th	Thorium(IV) chloride	-1186.2	-1094.1	190.4	120.3					-964.4	-932.0	390.7	107.5
Cl_4Ti	Titanium(IV) chloride					-804.2	-737.2	252.3	145.2	-763.2	-726.3	353.2	95.4
Cl_4U	Uranium(IV) chloride	-1019.2	-930.0	197.1	122.0					-809.6	-786.6	419.0	
Cl_4V	Vanadium(IV) chloride					-569.4	-503.7	255.0		-525.5	-492.0	362.4	96.2
Cl_4Zr	Zirconium(IV) chloride	-980.5	-889.9	181.6	119.8								
Cl_5Nb	Niobium(V) chloride	-797.5	-683.2	210.5	148.1					-703.7	-646.0	400.6	120.8
Cl_5P	Phosphorus(V) chloride	-443.5								-374.9	-305.0	364.6	112.8
Cl_5Pa	Protactinium(V) chloride	-1145.0	-1034.0	238.0									
Cl_5Ta	Tantalum(V) chloride	-859.0											
Cl_6U	Uranium(VI) chloride	-1092.0	-962.0	285.8	175.7					-1013.0	-928.0	431.0	
Cl_6W	Tungsten(VI) chloride	-602.5								-513.8			
Cm	Curium	0.0											
Co	Cobalt	0.0		30.0	24.8					424.7	380.3	179.5	23.0
CoF_2	Cobalt(II) fluoride	-692.0	-647.2	82.0	68.8								
CoH_2O_2	Cobalt(II) hydroxide	-539.7	-454.3	79.0									
CoI_2	Cobalt(II) iodide	-88.7											
CoN_2O_6	Cobalt(II) nitrate	-420.5											
CoO	Cobalt(II) oxide	-237.9	-214.2	53.0	55.2								
CoO_4S	Cobalt(II) sulfate	-888.3	-782.3	118.0									
CoS	Cobalt(II) sulfide	-82.8											
Co_2S_3	Cobalt(III) sulfide	-147.3											
Co_3O_4	Cobalt(II,III) oxide	-891.0	-774.0	102.5	123.4								
Cr	Chromium	0.0		23.8	23.4					396.6	351.8	174.5	20.8
CrF_2	Chromium(II) fluoride	-778.0											
CrF_3	Chromium(III) fluoride	-1159.0	-1088.0	93.9	78.7								
CrI_2	Chromium(II) iodide	-156.9											
CrI_3	Chromium(III) iodide	-205.0											
CrO_2	Chromium(IV) oxide	-598.0											
CrO_3	Chromium(VI) oxide									-292.9		266.2	56.0
CrO_4Pb	Lead(II) chromate	-930.9											
Cr_2FeO_4	Chromium iron oxide	-1444.7	-1343.8	146.0	133.6								
Cr_2O_3	Chromium(III) oxide	-1139.7	-1058.1	81.2	118.7								
Cr_3O_4	Chromium(II,III) oxide	-1531.0											
Cs	Cesium	0.0		85.2	32.2					76.5	49.6	175.6	20.8
CsF	Cesium fluoride	-553.5	-525.5	92.8	51.1								
CsF_2H	Cesium hydrogen fluoride	-923.8	-858.9	135.2	87.3								
CsH	Cesium hydride	-54.2											
CsHO	Cesium hydroxide	-416.2	-371.8	104.2	69.9					-256.0	-256.5	254.8	49.7
$CsHO_4S$	Cesium hydrogen sulfate	-1158.1											
CsH_2N	Cesium amide	-118.4											
CsI	Cesium iodide	-346.6	-340.6	123.1	52.8								
$CsNO_3$	Cesium nitrate	-506.0	-406.5	155.2									
CsO_2	Cesium superoxide	-286.2											
Cs_2O	Cesium oxide	-345.8	-308.1	146.9	76.0								
Cs_2O_3S	Cesium sulfite	-1134.7											
Cs_2O_4S	Cesium sulfate	-1443.0	-1323.6	211.9	134.9								
Cs_2S	Cesium sulfide	-359.8											
Cu	Copper	0.0		33.2	24.4					337.4	297.7	166.4	20.8
CuF_2	Copper(II) fluoride	-542.7											
CuH_2O_2	Copper(II) hydroxide	-449.8											
CuI	Copper(I) iodide	-67.8	-69.5	96.7	54.1								
CuN_2O_6	Copper(II) nitrate	-302.9											
CuO	Copper(II) oxide	-157.3	-129.7	42.6	42.3								
CuO_4S	Copper(II) sulfate	-771.4	-662.2	109.2									
CuO_4W	Copper(II) tungstate	-1105.0											

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
CuS	Copper(II) sulfide	-53.1	-53.6	66.5	47.8								
CuSe	Copper(II) selenide	-39.5											
Cu_2	Dicopper									484.2	431.9	241.6	36.6
Cu_2O	Copper(I) oxide	-168.6	-146.0	93.1	63.6								
Cu_2S	Copper(I) sulfide	-79.5	-86.2	120.9	76.3								
Dy	Dysprosium	0.0		75.6	27.7					290.4	254.4	196.6	20.8
DyI_3	Dysprosium(III) iodide	-620.5											
Dy_2O_3	Dysprosium(III) oxide	-1863.1	-1771.5	149.8	116.3								
Er	Erbium	0.0		73.2	28.1					317.1	280.7	195.6	20.8
ErF_3	Erbium fluoride	-1711.0											
Er_2O_3	Erbium oxide	-1897.9	-1808.7	155.6	108.5								
Es	Einsteinium	0.0											
Eu	Europium	0.0		77.8	27.7					175.3	142.2	188.8	20.8
Eu_2O_3	Europium(III) oxide	-1651.4	-1556.8	146.0	122.2								
Eu_3O_4	Europium(II,III) oxide	-2272.0	-2142.0	205.0									
F	Fluorine (atomic)									79.4	62.3	158.8	22.7
FGa	Gallium monofluoride									-251.9			33.3
FGe	Germanium monofluoride									-33.4			34.7
$FGeH_3$	Fluorogermane											252.8	51.6
FH	Hydrogen fluoride					-299.8				-273.3	-275.4	173.8	
FH_3Si	Fluorosilane											238.4	47.4
FH_4N	Ammonium fluoride	-464.0	-348.7	72.0	65.3								
FI	Iodine fluoride									-95.7	-118.5	236.2	33.4
FIn	Indium(I) fluoride									-203.4			
FK	Potassium fluoride	-567.3	-537.8	66.6	49.0								
FLi	Lithium fluoride	-616.0	-587.7	35.7	41.6								
FNO	Nitrosyl fluoride									-66.5	-51.0	248.1	41.3
FNO_2	Nitryl fluoride											260.4	49.8
FNS	Thionitrosyl fluoride (NSF)											259.8	44.1
FNa	Sodium fluoride	-576.6	-546.3	51.1	46.9								
FO	Fluorine oxide									109.0	105.3	216.4	32.0
FO_2	Fluorine superoxide (FOO)									25.4	39.4	259.5	44.5
FRb	Rubidium fluoride	-557.7											
FSi	Fluorosilylidyne									7.1	-24.3	225.8	32.6
FTl	Thallium(I) fluoride	-324.7								-182.4			
F_2	Fluorine									0.0		202.8	31.3
F_2Fe	Iron(II) fluoride	-711.3	-668.6	87.0	68.1								
F_2HK	Potassium hydrogen fluoride	-927.7	-859.7	104.3	76.9								
F_2HN	Difluoramine											252.8	43.4
F_2HNa	Sodium hydrogen fluoride	-920.3	-852.2	90.9	75.0								
F_2HRb	Rubidium hydrogen fluoride	-922.6	-855.6	120.1	79.4								
F_2Mg	Magnesium fluoride	-1124.2	-1071.1	57.2	61.6								
F_2N	Difluoroamidogen									43.1	57.8	249.9	41.0
F_2N_2	*cis*-Difluorodiazine									69.5			
F_2N_2	*trans*-Difluorodiazine									82.0			
F_2Ni	Nickel(II) fluoride	-651.4	-604.1	73.6	64.1								
F_2O	Fluorine monoxide									24.5	41.8	247.5	43.3
F_2OS	Thionyl fluoride											278.7	56.8
F_2O_2	Fluorine dioxide									19.2	58.2	277.2	62.1
F_2O_2S	Sulfuryl fluoride											284.0	66.0
F_2O_2U	Uranyl fluoride	-1653.5	-1557.4	135.6	103.2								
F_2Pb	Lead(II) fluoride	-664.0	-617.1	110.5									
F_2Si	Difluorosilylene									-619.0	-628.0	252.7	43.9
F_2Sr	Strontium fluoride	-1216.3	-1164.8	82.1	70.0								
F_2Zn	Zinc fluoride	-764.4	-713.3	73.7	65.7								
F_3Ga	Gallium(III) fluoride	-1163.0	-1085.3	84.0									
F_3Gd	Gadolinium(III) fluoride									-1297.0			
F_3HSi	Trifluorosilane											271.9	60.5
F_3Ho	Holmium fluoride	-1707.0											
F_3N	Nitrogen trifluoride									-132.1	-90.6	260.8	53.4
F_3Nd	Neodymium fluoride	-1657.0											
F_3OP	Phosphoric trifluoride									-1254.3	-1205.8	285.4	68.8
F_3P	Phosphorus(III) fluoride									-958.4	-936.9	273.1	58.7
F_3Sb	Antimony(III) fluoride	-915.5											
F_3Sc	Scandium fluoride	-1629.2	-1555.6	92.0						-1247.0	-1234.0	300.5	67.8
F_3Sm	Samarium(III) fluoride	-1778.0											

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
F_3Th	Thorium(III) fluoride									-1166.1	-1160.6	339.2	73.3
F_3U	Uranium(III) fluoride	-1502.1	-1433.4	123.4	95.1					-1058.5	-1051.9	331.9	74.3
F_3Y	Yttrium fluoride	-1718.8	-1644.7	100.0						-1288.7	-1277.8	311.8	70.3
F_4Ge	Germanium(IV) fluoride									-1190.2	-1150.0	301.9	
F_4Hf	Hafnium fluoride	-1930.5	-1830.4	113.0						-1669.8			
F_4N_2	Tetrafluorohydrazine									-8.4	79.9	301.2	79.2
F_4Pb	Lead(IV) fluoride	-941.8											
F_4S	Sulfur tetrafluoride									-763.2	-722.0	299.6	77.6
F_4Si	Tetrafluorosilane									-1615.0	-1572.8	282.8	73.6
F_4Th	Thorium(IV) fluoride	-2097.8	-2003.4	142.0	110.7					-1759.0	-1724.0	341.7	93.0
F_4U	Uranium(IV) fluoride	-1914.2	-1823.3	151.7	116.0					-1598.7	-1572.7	368.0	91.2
F_4V	Vanadium(IV) fluoride	-1403.3											
F_4Xe	Xenon tetrafluoride	-261.5											
F_4Zr	Zirconium(IV) fluoride	-1911.3	-1809.9	104.6	103.7								
F_5I	Iodine pentafluoride					-864.8				-822.5	-751.7	327.7	99.2
F_5Nb	Niobium(V) fluoride	-1813.8	-1699.0	160.2	134.7					-1739.7	-1673.6	321.9	97.1
F_5P	Phosphorus(V) fluoride									-1594.4	-1520.7	300.8	84.8
F_5Ta	Tantalum(V) fluoride	-1903.6											
F_5V	Vanadium(V) fluoride					-1480.3	-1373.1	175.7		-1433.9	-1369.8	320.9	98.6
$F_6H_8N_2Si$	Ammonium hexafluorosilicate	-2681.7	-2365.3	280.2	228.1								
F_6Ir	Iridium(VI) fluoride	-579.7	-461.6	247.7						-544.0	-460.0	357.8	121.1
F_6K_2Si	Potassium hexafluorosilicate	-2956.0	-2798.6	226.0									
F_6Mo	Molybdenum(VI) fluoride					-1585.5	-1473.0	259.7	169.8	-1557.7	-1472.2	350.5	120.6
F_6Na_2Si	Sodium hexafluorosilicate	-2909.6	-2754.2	207.1	187.1								
F_6Os	Osmium(VI) fluoride			246.0								358.1	120.8
F_6Pt	Platinum(VI) fluoride			235.6								348.3	122.8
F_6S	Sulfur hexafluoride									-1220.5	-1116.5	291.5	97.0
F_6Se	Selenium hexafluoride									-1117.0	-1017.0	313.9	110.5
F_6Si_2	Hexafluorodisilane	-2427.0	-2299.7	219.1	129.5					-2383.3	-2307.3	391.0	129.9
F_6Te	Tellurium hexafluoride									-1318.0			
F_6U	Uranium(VI) fluoride	-2197.0	-2068.5	227.6	166.8					-2147.4	-2063.7	377.9	129.6
F_6W	Tungsten(VI) fluoride					-1747.7	-1631.4	251.5		-1721.7	-1632.1	341.1	119.0
Fe	Iron	0.0		27.3	25.1					416.3	370.7	180.5	25.7
FeI_2	Iron(II) iodide	-113.0											
FeI_3	Iron(III) iodide									71.0			
$FeMoO_4$	Iron(II) molybdate	-1075.0	-975.0	129.3	118.5								
FeO	Iron(II) oxide	-272.0											
FeO_4S	Iron(II) sulfate	-928.4	-820.8	107.5	100.6								
FeO_4W	Iron(II) tungstate	-1155.0	-1054.0	131.8	114.6								
FeS	Iron(II) sulfide	-100.0	-100.4	60.3	50.5								
FeS_2	Iron disulfide	-178.2	-166.9	52.9	62.2								
Fe_2O_3	Iron(III) oxide	-824.2	-742.2	87.4	103.9								
Fe_2O_4Si	Iron(II) orthosilicate	-1479.9	-1379.0	145.2	132.9								
Fe_3O_4	Iron(II,III) oxide	-1118.4	-1015.4	146.4	143.4								
Fm	Fermium	0.0											
Fr	Francium	0.0		95.4									
Ga	Gallium	0.0	0.0	40.8	26.1	5.6				272.0	233.7	169.0	25.3
GaH_3O_3	Gallium(III) hydroxide	-964.4	-831.3	100.0									
GaI_3	Gallium(III) iodide	-238.9		205.0	100.0								
GaN	Gallium nitride	-110.5											
GaO	Gallium monoxide									279.5	253.5	231.1	32.1
GaP	Gallium phosphide	-88.0											
GaSb	Gallium antimonide	-41.8	-38.9	76.1	48.5								
Ga_2	Digallium									438.5			
Ga_2O	Gallium suboxide	-356.0											
Ga_2O_3	Gallium(III) oxide	-1089.1	-998.3	85.0	92.1								
Gd	Gadolinium	0.0		68.1	37.0					397.5	359.8	194.3	27.5
Gd_2O_3	Gadolinium(III) oxide	-1819.6			106.7								
Ge	Germanium	0.0		31.1	23.3					372.0	331.2	167.9	30.7
GeH_3I	Iodogermane											283.2	57.5
GeH_4	Germane									90.8	113.4	217.1	45.0
GeI_4	Germanium(IV) iodide	-141.8	-144.3	271.1						-56.9	-106.3	428.9	104.1
GeO	Germanium(II) oxide	-261.9	-237.2	50.0						-46.2	-73.2	224.3	30.9
GeO_2	Germanium(IV) oxide	-580.0	-521.4	39.7	52.1								
GeP	Germanium phosphide	-21.0	-17.0	63.0									
GeS	Germanium(II) sulfide	-69.0	-71.5	71.0						92.0	42.0	234.0	33.7

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
GeTe	Germanium(II) telluride	20.0											
Ge_2	Digermanium									473.1	416.3	252.8	35.6
Ge_2H_6	Digermane					137.3				162.3			
Ge_3H_8	Trigermane					193.7				226.8			
H	Hydrogen (atomic)									218.0	203.3	114.7	20.8
HI	Hydrogen iodide									26.5	1.7	206.6	29.2
HIO_3	Iodic acid	-230.1											
HK	Potassium hydride	-57.7											
HKO	Potassium hydroxide	-424.6	-379.4	81.2	68.9					-232.0	-229.7	238.3	49.2
HKO_4S	Potassium hydrogen sulfate	-1160.6	-1031.3	138.1									
HLi	Lithium hydride	-90.5	-68.3	20.0	27.9								
HLiO	Lithium hydroxide	-487.5	-441.5	42.8	49.6					-229.0	-234.2	214.4	46.0
HN	Imidogen									351.5	345.6	181.2	29.2
HNO_2	Nitrous acid									-79.5	-46.0	254.1	45.6
HNO_3	Nitric acid					-174.1	-80.7	155.6	109.9	-133.9	-73.5	266.9	54.1
HN_3	Hydrazoic acid					264.0	327.3	140.6		294.1	328.1	239.0	43.7
HNa	Sodium hydride	-56.3	-33.5	40.0	36.4								
HNaO	Sodium hydroxide	-425.8	-379.7	64.4	59.5					-191.0	-193.9	229.0	48.0
$HNaO_4S$	Sodium hydrogen sulfate	-1125.5	-992.8	113.0									
HNa_2O_4P	Sodium hydrogen phosphate	-1748.1	-1608.2	150.5	135.3								
HO	Hydroxyl									39.0	34.2	183.7	29.9
HORb	Rubidium hydroxide	-418.8	-373.9	94.0	69.0					-238.0	-239.1	248.5	49.5
HOTl	Thallium(I) hydroxide	-238.9	-195.8	88.0									
HO_2	Hydroperoxy									10.5	22.6	229.0	34.9
HO_3P	Metaphosphoric acid	-948.5											
HO_4RbS	Rubidium hydrogen sulfate	-1159.0											
HO_4Re	Perrhenic acid	-762.3	-656.4	158.2									
HRb	Rubidium hydride	-52.3											
HS	Mercapto									142.7	113.3	195.7	32.3
HSi	Silylidyne									361.0			
HTa_2	Tantalum hydride	-32.6	-69.0	79.1	90.8								
H_2	Hydrogen									0.0		130.7	28.8
H_2KN	Potassium amide	-128.9											
H_2KO_4P	Potassium dihydrogen phosphate	-1568.3	-1415.9	134.9	116.6								
H_2LiN	Lithium amide	-179.5											
H_2Mg	Magnesium hydride	-75.3	-35.9	31.1	35.4								
H_2MgO_2	Magnesium hydroxide	-924.5	-833.5	63.2	77.0								
H_2N	Amidogen									184.9	194.6	195.0	33.9
H_2NNa	Sodium amide	-123.8	-64.0	76.9	66.2								
H_2NRb	Rubidium amide	-113.0											
$H_2N_2O_2$	Nitramide	-89.5											
H_2NiO_2	Nickel(II) hydroxide	-529.7	-447.2	88.0									
H_2O	Water					-285.8	-237.1	70.0	75.3	-241.8	-228.6	188.8	33.6
H_2O_2	Hydrogen peroxide					-187.8	-120.4	109.6	89.1	-136.3	-105.6	232.7	43.1
H_2O_2Sn	Tin(II) hydroxide	-561.1	-491.6	155.0									
H_2O_2Sr	Strontium hydroxide	-959.0											
H_2O_2Zn	Zinc hydroxide	-641.9	-553.5	81.2									
H_2O_3Si	Metasilicic acid	-1188.7	-1092.4	134.0									
H_2O_4S	Sulfuric acid					-814.0	-690.0	156.9	138.9				
H_2O_4Se	Selenic acid	-530.1											
H_2S	Hydrogen sulfide									-20.6	-33.4	205.8	34.2
H_2S_2	Hydrogen disulfide					-18.1			84.1	15.5			51.5
H_2Se	Hydrogen selenide									29.7	15.9	219.0	34.7
H_2Sr	Strontium hydride	-180.3											
H_2Te	Hydrogen telluride									99.6			
H_2Th	Thorium hydride	-139.7	-100.0	50.7	36.7								
H_2Zr	Zirconium(II) hydride	-169.0	-128.8	35.0	31.0								
H_3ISi	Iodosilane											270.9	54.4
H_3N	Ammonia									-45.9	-16.4	192.8	35.1
H_3NO	Hydroxylamine	-114.2											
H_3O_2P	Phosphinic acid	-604.6				-595.4							
H_3O_3P	Phosphonic acid	-964.4											
H_3O_4P	Phosphoric acid	-1284.4	-1124.3	110.5	106.1	-1271.7	-1123.6	150.8	145.0				
H_3P	Phosphine									5.4	13.5	210.2	37.1
H_3Sb	Stibine									145.1	147.8	232.8	41.1
H_3U	Uranium(III) hydride	-127.2	-72.8	63.7	49.3								

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
H_4IN	Ammonium iodide	-201.4	-112.5	117.0									
H_4N_2	Hydrazine					50.6	149.3	121.2	98.9	95.4	159.4	238.5	48.4
$H_4N_2O_2$	Ammonium nitrite	-256.5											
$H_4N_2O_3$	Ammonium nitrate	-365.6	-183.9	151.1	139.3								
H_4N_4	Ammonium azide	115.5	274.2	112.5									
H_4O_4Si	Orthosilicic acid	-1481.1	-1332.9	192.0									
$H_4O_7P_2$	Diphosphoric acid	-2241.0				-2231.7							
H_4P_2	Diphosphine					-5.0				20.9			
H_4Si	Silane									34.3	56.9	204.6	42.8
H_4Sn	Stannane									162.8	188.3	227.7	49.0
H_5NO	Ammonium hydroxide					-361.2	-254.0	165.6	154.9				
H_5NO_3S	Ammonium hydrogen sulfite	-768.6											
H_5NO_4S	Ammonium hydrogen sulfate	-1027.0											
H_6Si_2	Disilane									80.3	127.3	272.7	80.8
$H_8N_2O_4S$	Ammonium sulfate	-1180.9	-901.7	220.1	187.5								
H_8Si_3	Trisilane					92.5				120.9			
$H_9N_2O_4P$	Ammonium hydrogen phosphate	-1566.9			188.0								
$H_{12}N_3O_4P$	Ammonium phosphate	-1671.9											
He	Helium									0.0		126.2	20.8
Hf	Hafnium	0.0		43.6	25.7					619.2	576.5	186.9	20.8
HfO_2	Hafnium oxide	-1144.7	-1088.2	59.3	60.3								
Hg	Mercury					0.0		75.9	28.0	61.4	31.8	175.0	20.8
HgI_2	Mercury(II) iodide	-105.4	-101.7	180.0									
HgO	Mercury(II) oxide	-90.8	-58.5	70.3	44.1								
HgO_4S	Mercury(II) sulfate	-707.5											
HgS	Mercury(II) sulfide (red)	-58.2	-50.6	82.4	48.4								
HgTe	Mercury(II) telluride	-42.0											
Hg_2	Dimercury									108.8	68.2	288.1	37.4
Hg_2I_2	Mercury(I) iodide	-121.3	-111.0	233.5									
Hg_2O_4S	Mercury(I) sulfate	-743.1	-625.8	200.7	132.0								
Ho	Holmium	0.0		75.3	27.2					300.8	264.8	195.6	20.8
Ho_2O_3	Holmium oxide	-1880.7	-1791.1	158.2	115.0								
I	Iodine (atomic)									106.8	70.2	180.8	20.8
IIn	Indium(I) iodide	-116.3	-120.5	130.0						7.5	-37.7	267.3	36.8
IK	Potassium iodide	-327.9	-324.9	106.3	52.9								
IKO_3	Potassium iodate	-501.4	-418.4	151.5	106.5								
IKO_4	Potassium periodate	-467.2	-361.4	175.7									
ILi	Lithium iodide	-270.4	-270.3	86.8	51.0								
INa	Sodium iodide	-287.8	-286.1	98.5	52.1								
$INaO_3$	Sodium iodate	-481.8			92.0								
$INaO_4$	Sodium periodate	-429.3	-323.0	163.0									
IO	Iodine monoxide									126.0	102.5	239.6	32.9
IRb	Rubidium iodide	-333.8	-328.9	118.4	53.2								
ITl	Thallium(I) iodide	-123.8	-125.4	127.6						7.1			
I_2	Iodine (rhombic)	0.0		116.1	54.4					62.4	19.3	260.7	36.9
I_2Mg	Magnesium iodide	-364.0	-358.2	129.7									
I_2Ni	Nickel(II) iodide	-78.2											
I_2Pb	Lead(II) iodide	-175.5	-173.6	174.9	77.4								
I_2Sn	Tin(II) iodide	-143.5											
I_2Sr	Strontium iodide	-558.1			81.6								
I_2Zn	Zinc iodide	-208.0	-209.0	161.1									
I_3In	Indium(III) iodide	-238.0								-120.5			
I_3La	Lanthanum iodide	-668.9											
I_3Lu	Lutetium iodide	-548.0											
I_3P	Phosphorus(III) iodide	-45.6										374.4	78.4
I_3Ru	Ruthenium(III) iodide	-65.7											
I_3Sb	Antimony(III) iodide	-100.4											
I_4Pt	Platinum(IV) iodide	-72.8											
I_4Si	Tetraiodosilane	-189.5											
I_4Sn	Tin(IV) iodide				84.9							446.1	105.4
I_4Ti	Titanium(IV) iodide	-375.7	-371.5	249.4	125.7					-277.8			
I_4V	Vanadium(IV) iodide									-122.6			
I_4Zr	Zirconium(IV) iodide	-481.6											
In	Indium	0.0		57.8	26.7					243.3	208.7	173.8	20.8
InO	Indium monoxide									387.0	364.4	236.5	32.6
InP	Indium phosphide	-88.7	-77.0	59.8	45.4								

Molecular formula	Name	Crystal $\Delta_f H°$ kJ/mol	Crystal $\Delta_f G°$ kJ/mol	Crystal $S°$ J/mol K	Crystal C_p J/mol K	Liquid $\Delta_f H°$ kJ/mol	Liquid $\Delta_f G°$ kJ/mol	Liquid $S°$ J/mol K	Liquid C_p J/mol K	Gas $\Delta_f H°$ kJ/mol	Gas $\Delta_f G°$ kJ/mol	Gas $S°$ J/mol K	Gas C_p J/mol K
InS	Indium(II) sulfide	-138.1	-131.8	67.0						238.0			
InSb	Indium antimonide	-30.5	-25.5	86.2	49.5					344.3			
In_2	Diindium									380.9			
In_2O_3	Indium(III) oxide	-925.8	-830.7	104.2	92.0								
In_2S_3	Indium(III) sulfide	-427.0	-412.5	163.6	118.0								
In_2Te_5	Indium(IV) telluride	-175.3											
Ir	Iridium	0.0		35.5	25.1					665.3	617.9	193.6	20.8
IrO_2	Iridium(IV) oxide	-274.1			57.3								
IrS_2	Iridium(IV) sulfide	-138.0											
Ir_2S_3	Iridium(III) sulfide	-234.0											
K	Potassium	0.0		64.7	29.6					89.0	60.5	160.3	20.8
$KMnO_4$	Potassium permanganate	-837.2	-737.6	171.7	117.6								
KNO_2	Potassium nitrite	-369.8	-306.6	152.1	107.4								
KNO_3	Potassium nitrate	-494.6	-394.9	133.1	96.4								
KNa	Potassium sodium					6.3							
KO_2	Potassium superoxide	-284.9	-239.4	116.7	77.5								
K_2	Dipotassium									123.7	87.5	249.7	37.9
K_2O	Potassium oxide	-361.5											
K_2O_2	Potassium peroxide	-494.1	-425.1	102.1									
K_2O_4S	Potassium sulfate	-1437.8	-1321.4	175.6	131.5								
K_2S	Potassium sulfide	-380.7	-364.0	105.0									
K_3O_4P	Potassium phosphate	-1950.2											
Kr	Krypton									0.0		164.1	20.8
La	Lanthanum	0.0		56.9	27.1					431.0	393.6	182.4	22.8
LaS	Lanthanum monosulfide	-456.0	-451.5	73.2	59.0								
La_2O_3	Lanthanum oxide	-1793.7	-1705.8	127.3	108.8								
Li	Lithium	0.0		29.1	24.8					159.3	126.6	138.8	20.8
$LiNO_2$	Lithium nitrite	-372.4	-302.0	96.0									
$LiNO_3$	Lithium nitrate	-483.1	-381.1	90.0									
Li_2	Dilithium									215.9	174.4	197.0	36.1
Li_2O	Lithium oxide	-597.9	-561.2	37.6	54.1								
Li_2O_2	Lithium peroxide	-634.3											
Li_2O_3Si	Lithium metasilicate	-1648.1	-1557.2	79.8	99.1								
Li_2O_4S	Lithium sulfate	-1436.5	-1321.7	115.1	117.6								
Li_2S	Lithium sulfide	-441.4											
Li_3O_4P	Lithium phosphate	-2095.8											
Lr	Lawrencium	0.0											
Lu	Lutetium	0.0		51.0	26.9					427.6	387.8	184.8	20.9
Lu_2O_3	Lutetium oxide	-1878.2	-1789.0	110.0	101.8								
Md	Mendelevium	0.0											
Mg	Magnesium	0.0		32.7	24.9					147.1	112.5	148.6	20.8
MgN_2O_6	Magnesium nitrate	-790.7	-589.4	164.0	141.9								
MgO	Magnesium oxide	-601.6	-569.3	27.0	37.2								
MgO_4S	Magnesium sulfate	-1284.9	-1170.6	91.6	96.5								
MgO_4Se	Magnesium selenate	-968.5											
MgS	Magnesium sulfide	-346.0	-341.8	50.3	45.6								
Mg_2	Dimagnesium									287.7			
Mg_2O_4Si	Magnesium orthosilicate	-2174.0	-2055.1	95.1	118.5								
Mn	Manganese	0.0		32.0	26.3					280.7	238.5	173.7	20.8
MnN_2O_6	Manganese(II) nitrate	-576.3											
$MnNaO_4$	Sodium permanganate	-1156.0											
MnO	Manganese(II) oxide	-385.2	-362.9	59.7	45.4								
MnO_2	Manganese(IV) oxide	-520.0	-465.1	53.1	54.1								
MnO_3Si	Manganese(II) metasilicate	-1320.9	-1240.5	89.1	86.4								
MnS	Manganese(II) sulfide (α form)	-214.2	-218.4	78.2	50.0								
MnSe	Manganese(II) selenide	-106.7	-111.7	90.8	51.0								
Mn_2O_3	Manganese(III) oxide	-959.0	-881.1	110.5	107.7								
Mn_2O_4Si	Manganese(II) orthosilicate	-1730.5	-1632.1	163.2	129.9								
Mn_3O_4	Manganese(II,III) oxide	-1387.8	-1283.2	155.6	139.7								
Mo	Molybdenum	0.0		28.7	24.1					658.1	612.5	182.0	20.8
$MoNa_2O_4$	Sodium molybdate	-1468.1	-1354.3	159.7	141.7								
MoO_2	Molybdenum(IV) oxide	-588.9	-533.0	46.3	56.0								
MoO_3	Molybdenum(VI) oxide	-745.1	-668.0	77.7	75.0								
MoO_4Pb	Lead(II) molybdate	-1051.9	-951.4	166.1	119.7								
MoS_2	Molybdenum(IV) sulfide	-235.1	-225.9	62.6	63.6								
Mo_3Si	Molybdenum silicide	-125.2	-125.7	106.3	93.1								

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
N	Nitrogen (atomic)									472.7	455.5	153.3	20.8
$NNaO_2$	Sodium nitrite	-358.7	-284.6	103.8									
$NNaO_3$	Sodium nitrate	-467.9	-367.0	116.5	92.9								
NO	Nitric oxide									91.3	87.6	210.8	29.9
NO_2	Nitrogen dioxide									33.2	51.3	240.1	37.2
NO_2Rb	Rubidium nitrite	-367.4	-306.2	172.0									
NO_3Rb	Rubidium nitrate	-495.1	-395.8	147.3	102.1								
NO_3Tl	Thallium(I) nitrate	-243.9	-152.4	160.7	99.5								
NP	Phosphorus nitride	-63.0								171.5	149.4	211.1	29.7
N_2	Nitrogen									0.0		191.6	29.1
N_2O	Nitrous oxide									81.6	103.7	220.0	38.6
N_2O_3	Nitrogen trioxide					50.3				86.6	142.4	314.7	72.7
N_2O_4	Nitrogen tetroxide					-19.5	97.5	209.2	142.7	11.1	99.8	304.4	79.2
N_2O_4Sr	Strontium nitrite	-762.3											
N_2O_5	Nitrogen pentoxide	-43.1	113.9	178.2	143.1					13.3	117.1	355.7	95.3
N_2O_6Pb	Lead(II) nitrate	-451.9											
N_2O_6Ra	Radium nitrate	-992.0	-796.1	222.0									
N_2O_6Sr	Strontium nitrate	-978.2	-780.0	194.6	149.9								
N_2O_6Zn	Zinc nitrate	-483.7											
N_3Na	Sodium azide	21.7	93.8	96.9	76.6								
N_4Si_3	Silicon nitride	-743.5	-642.6	101.3									
Na	Sodium	0.0		51.3	28.2					107.5	77.0	153.7	20.8
NaO_2	Sodium superoxide	-260.2	-218.4	115.9	72.1								
Na_2	Disodium									142.1	103.9	230.2	37.6
Na_2O	Sodium oxide	-414.2	-375.5	75.1	69.1								
Na_2O_2	Sodium peroxide	-510.9	-447.7	95.0	89.2								
Na_2O_3S	Sodium sulfite	-1100.8	-1012.5	145.9	120.3								
Na_2O_3Si	Sodium metasilicate	-1554.9	-1462.8	113.9									
Na_2O_4S	Sodium sulfate	-1387.1	-1270.2	149.6	128.2								
Na_2S	Sodium sulfide	-364.8	-349.8	83.7									
Nb	Niobium	0.0		36.4	24.6					725.9	681.1	186.3	30.2
NbO	Niobium(II) oxide	-405.8	-378.6	48.1	41.3								
NbO_2	Niobium(IV) oxide	-796.2	-740.5	54.5	57.5								
Nb_2O_5	Niobium(V) oxide	-1899.5	-1766.0	137.2	132.1								
Nd	Neodymium	0.0		71.5	27.5					327.6	292.4	189.4	22.1
Nd_2O_3	Neodymium oxide	-1807.9	-1720.8	158.6	111.3								
Ne	Neon									0.0		146.3	20.8
Ni	Nickel	0.0		29.9	26.1					429.7	384.5	182.2	23.4
NiO_4S	Nickel(II) sulfate	-872.9	-759.7	92.0	138.0								
NiS	Nickel(II) sulfide	-82.0	-79.5	53.0	47.1								
Ni_2O_3	Nickel(III) oxide	-489.5											
No	Nobelium	0.0											
O	Oxygen (atomic)									249.2	231.7	161.1	21.9
OP	Phosphorus monoxide									-28.5	-51.9	222.8	31.8
OPb	Lead(II) oxide (massicot)	-217.3	-187.9	68.7	45.8								
OPb	Lead(II) oxide (litharge)	-219.0	-188.9	66.5	45.8								
OPd	Palladium(II) oxide	-85.4			31.4					348.9	325.9	218.0	
ORa	Radium oxide	-523.0											
ORb_2	Rubidium oxide	-339.0											
ORh	Rhodium monoxide									385.0			
OS	Sulfur monoxide									6.3	-19.9	222.0	30.2
OSe	Selenium monoxide									53.4	26.8	234.0	31.3
OSi	Silicon monoxide									-99.6	-126.4	211.6	29.9
OSn	Tin(II) oxide	-280.7	-251.9	57.2	44.3					15.1	-8.4	232.1	31.6
OSr	Strontium oxide	-592.0	-561.9	54.4	45.0					1.5			
OTi	Titanium(II) oxide	-519.7	-495.0	50.0	40.0								
OTl_2	Thallium(I) oxide	-178.7	-147.3	126.0									
OU	Uranium(II) oxide									21.0			
OV	Vanadium(II) oxide	-431.8	-404.2	38.9	45.4								
OZn	Zinc oxide	-350.5	-320.5	43.7	40.3								
O_2	Oxygen									0.0		205.2	29.4
O_2P	Phosphorus dioxide									-279.9	-281.6	252.1	39.5
O_2Pb	Lead(IV) oxide	-277.4	-217.3	68.6	64.6								
O_2Rb	Rubidium superoxide	-278.7											
O_2Rb_2	Rubidium peroxide	-472.0											
O_2Ru	Ruthenium(IV) oxide	-305.0											

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
O_2S	Sulfur dioxide					-320.5				-296.8	-300.1	248.2	39.9
O_2Se	Selenium dioxide	-225.4											
O_2Si	Silicon dioxide (α-quartz)	-910.7	-856.3	41.5	44.4					-322.0			
O_2Sn	Tin(IV) oxide	-577.6	-515.8	49.0	52.6								
O_2Te	Tellurium dioxide	-322.6	-270.3	79.5									
O_2Th	Thorium(IV) oxide	-1226.4	-1169.2	65.2	61.8								
O_2Ti	Titanium(IV) oxide	-944.0	-888.8	50.6	55.0								
O_2U	Uranium(IV) oxide	-1085.0	-1031.8	77.0	63.6					-465.7	-471.5	274.6	51.4
O_2W	Tungsten(IV) oxide	-589.7	-533.9	50.5	56.1								
O_2Zr	Zirconium(IV) oxide	-1100.6	-1042.8	50.4	56.2								
O_3	Ozone									142.7	163.2	238.9	39.2
O_3PbS	Lead(II) sulfite	-669.9											
O_3PbSi	Lead(II) metasilicate	-1145.7	-1062.1	109.6	90.0								
O_3Pr_2	Praseodymium oxide	-1809.6			117.4								
O_3Rh_2	Rhodium(III) oxide	-343.0			103.8								
O_3S	Sulfur trioxide	-454.5	-374.2	70.7		-441.0	-373.8	113.8		-395.7	-371.1	256.8	50.7
O_3Sc_2	Scandium oxide	-1908.8	-1819.4	77.0	94.2								
O_3SiSr	Strontium metasilicate	-1633.9	-1549.7	96.7	88.5								
O_3Sm_2	Samarium(III) oxide	-1823.0	-1734.6	151.0	114.5								
O_3Tb_2	Terbium oxide	-1865.2			115.9								
O_3Ti_2	Titanium(III) oxide	-1520.9	-1434.2	78.8	97.4								
O_3Tm_2	Thulium oxide	-1888.7	-1794.5	139.7	116.7								
O_3U	Uranium(VI) oxide	-1223.8	-1145.7	96.1	81.7								
O_3V_2	Vanadium(III) oxide	-1218.8	-1139.3	98.3	103.2								
O_3W	Tungsten(VI) oxide	-842.9	-764.0	75.9	73.8								
O_3Y_2	Yttrium oxide	-1905.3	-1816.6	99.1	102.5								
O_3Yb_2	Ytterbium(III) oxide	-1814.6	-1726.7	133.1	115.4								
O_4Os	Osmium(VIII) oxide	-394.1	-304.9	143.9						-337.2	-292.8	293.8	74.1
O_4PbS	Lead(II) sulfate	-920.0	-813.0	148.5	103.2								
O_4PbSe	Lead(II) selenate	-609.2	-504.9	167.8									
O_4Pb_2Si	Lead(II) orthosilicate	-1363.1	-1252.6	186.6	137.2								
O_4Pb_3	Lead(II,II,IV) oxide	-718.4	-601.2	211.3	146.9								
O_4RaS	Radium sulfate	-1471.1	-1365.6	138.0									
O_4Rb_2S	Rubidium sulfate	-1435.6	-1316.9	197.4	134.1								
O_4Ru	Ruthenium(VIII) oxide	-239.3	-152.2	146.4									
O_4SSr	Strontium sulfate	-1453.1	-1340.9	117.0									
O_4STl_2	Thallium(I) sulfate	-931.8	-830.4	230.5									
O_4SZn	Zinc sulfate	-982.8	-871.5	110.5	99.2								
O_4SiSr_2	Strontium orthosilicate	-2304.5	-2191.1	153.1	134.3								
O_4SiZn_2	Zinc orthosilicate	-1636.7	-1523.2	131.4	123.3								
O_4SiZr	Zirconium(IV) orthosilicate	-2033.4	-1919.1	84.1	98.7								
O_4TiZr	Zirconium titanate	-2024.1	-1915.8	116.7	114.0								
O_5Sb_2	Antimony(V) oxide	-971.9	-829.2	125.1									
O_5Ta_2	Tantalum(V) oxide	-2046.0	-1911.2	143.1	135.1								
O_5Ti_3	Titanium(III,IV) oxide	-2459.4	-2317.4	129.3	154.8								
O_5V_2	Vanadium(V) oxide	-1550.6	-1419.5	131.0	127.7								
O_5V_3	Vanadium(III,IV) oxide	-1933.0	-1803.0	163.0									
O_7Re_2	Rhenium(VII) oxide	-1240.1	-1066.0	207.1	166.1					-1100.0	-994.0	452.0	
O_7U_3	Uranium(IV,VI) oxide	-3427.1	-3242.9	250.5	215.5								
O_8S_2Zr	Zirconium(IV) sulfate	-2217.1			172.0								
O_8U_3	Uranium(V,VI) oxide	-3574.8	-3369.5	282.6	238.4								
O_9U_4	Uranium(IV,V) oxide	-4510.4	-4275.1	334.1	293.3								
Os	Osmium	0.0		32.6	24.7					791.0	745.0	192.6	20.8
P	Phosphorus (white)	0.0		41.1	23.8					316.5	280.1	163.2	20.8
P	Phosphorus (red)	-17.6		22.8	21.2								
P	Phosphorus (black)	-39.3											
P_2	Diphosphorus									144.0	103.5	218.1	32.1
P_4	Tetraphosphorus									58.9	24.4	280.0	67.2
Pa	Protactinium	0.0		51.9						607.0	563.0	198.1	22.9
Pb	Lead	0.0		64.8	26.4					195.2	162.2	175.4	20.8
PbS	Lead(II) sulfide	-100.4	-98.7	91.2	49.5								
PbSe	Lead(II) selenide	-102.9	-101.7	102.5	50.2								
PbTe	Lead(II) telluride	-70.7	-69.5	110.0	50.5								
Pd	Palladium	0.0		37.6	26.0					378.2	339.7	167.1	20.8
PdS	Palladium(II) sulfide	-75.0	-67.0	46.0									
Pm	Promethium	0.0										187.1	24.3

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
Po	Polonium	0.0											
Pr	Praseodymium	0.0		73.2	27.2					355.6	320.9	189.8	21.4
Pt	Platinum	0.0		41.6	25.9					565.3	520.5	192.4	25.5
PtS	Platinum(II) sulfide	-81.6	-76.1	55.1	43.4								
PtS_2	Platinum(IV) sulfide	-108.8	-99.6	74.7	65.9								
Pu	Plutonium	0.0											
Ra	Radium	0.0		71.0						159.0	130.0	176.5	20.8
Rb	Rubidium	0.0		76.8	31.1					80.9	53.1	170.1	20.8
Re	Rhenium	0.0		36.9	25.5					769.9	724.6	188.9	20.8
Rh	Rhodium	0.0		31.5	25.0					556.9	510.8	185.8	21.0
Rn	Radon									0.0		176.2	20.8
Ru	Ruthenium	0.0		28.5	24.1					642.7	595.8	186.5	21.5
S	Sulfur (rhombic)	0.0		32.1	22.6					277.2	236.7	167.8	23.7
S	Sulfur (monoclinic)	0.3											
SSi	Silicon monosulfide									112.5	60.9	223.7	32.3
SSn	Tin(II) sulfide	-100.0	-98.3	77.0	49.3								
SSr	Strontium sulfide	-472.4	-467.8	68.2	48.7								
STl_2	Thallium(I) sulfide	-97.1	-93.7	151.0									
SZn	Zinc sulfide (wurtzite)	-192.6											
SZn	Zinc sulfide (sphalerite)	-206.0	-201.3	57.7	46.0								
S_2	Disulfur									128.6	79.7	228.2	32.5
Sb	Antimony	0.0		45.7	25.2					262.3	222.1	180.3	20.8
Sb_2	Diantimony									235.6	187.0	254.9	36.4
Sc	Scandium	0.0		34.6	25.5					377.8	336.0	174.8	22.1
Se	Selenium (gray)	0.0		42.4	25.4					227.1	187.0	176.7	20.8
Se	Selenium (α form)	6.7								227.1			
Se	Selenium (vitreous)	5.0								227.1			
SeSr	Strontium selenide	-385.8											
$SeTl_2$	Thallium(I) selenide	-59.0	-59.0	172.0									
SeZn	Zinc selenide	-163.0	-163.0	84.0									
Se_2	Diselenium									146.0	96.2	252.0	35.4
Si	Silicon	0.0		18.8	20.0					450.0	405.5	168.0	22.3
Si_2	Disilicon									594.0	536.0	229.9	34.4
Sm	Samarium	0.0		69.6	29.5					206.7	172.8	183.0	30.4
Sn	Tin (white)	0.0		51.2	27.0					301.2	266.2	168.5	21.3
Sn	Tin (gray)	-2.1	0.1	44.1	25.8								
Sr	Strontium	0.0		55.0	26.8					164.4	130.9	164.6	20.8
Ta	Tantalum	0.0		41.5	25.4					782.0	739.3	185.2	20.9
Tb	Terbium	0.0		73.2	28.9					388.7	349.7	203.6	24.6
Tc	Technetium	0.0								678.0		181.1	20.8
Te	Tellurium	0.0		49.7	25.7					196.7	157.1	182.7	20.8
Te_2	Ditellurium									168.2	118.0	268.1	36.7
Th	Thorium	0.0		51.8	27.3					602.0	560.7	190.2	20.8
Ti	Titanium	0.0		30.7	25.0					473.0	428.4	180.3	24.4
Tl	Thallium	0.0		64.2	26.3					182.2	147.4	181.0	20.8
Tm	Thulium	0.0		74.0	27.0					232.2	197.5	190.1	20.8
U	Uranium	0.0		50.2	27.7					533.0	488.4	199.8	23.7
V	Vanadium	0.0		28.9	24.9					514.2	754.4	182.3	26.0
W	Tungsten	0.0		32.6	24.3					849.4	807.1	174.0	21.3
Xe	Xenon									0.0		169.7	20.8
Y	Yttrium	0.0		44.4	26.5					421.3	381.1	179.5	25.9
Yb	Ytterbium	0.0		59.9	26.7					152.3	118.4	173.1	20.8
Zn	Zinc	0.0		41.6	25.4					130.4	94.8	161.0	20.8
Zr	Zirconium	0.0		39.0	25.4					608.8	566.5	181.4	26.7
Substances containing carbon:													
C	Carbon (graphite)	0.0		5.7	8.5					716.7	671.3	158.1	20.8
C	Carbon (diamond)	1.9	2.9	2.4	6.1								
CAgN	Silver(I) cyanide	146.0	156.9	107.2	66.7								
CAg_2O_3	Silver(I) carbonate	-505.8	-436.8	167.4	112.3								
$CBaO_3$	Barium carbonate	-1213.0	-1134.4	112.1	86.0								
$CBeO_3$	Beryllium carbonate	-1025.0		52.0	65.0								
$CBrClF_2$	Bromochlorodifluoromethane											318.5	74.6
$CBrCl_2F$	Bromodichlorofluoromethane											330.6	80.0
$CBrCl_3$	Bromotrichloromethane									-41.1			85.3
$CBrF_3$	Bromotrifluoromethane									-648.3			69.3

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$CBrN$	Cyanogen bromide	140.5								186.2	165.3	248.3	46.9
$CBrN_3O_6$	Bromotrinitromethane					32.5				80.3			
CBr_2ClF	Dibromochlorofluoromethane											342.8	82.4
CBr_2Cl_2	Dibromodichloromethane											347.8	87.1
CBr_2F_2	Dibromodifluoromethane											325.3	77.0
CBr_2O	Carbonyl bromide					-127.2				-96.2	-110.9	309.1	61.8
CBr_3Cl	Tribromochloromethane											357.8	89.4
CBr_3F	Tribromofluoromethane											345.9	84.4
CBr_4	Tetrabromomethane	29.4	47.7	212.5	144.3					83.9	67.0	358.1	91.2
$CCaO_3$	Calcium carbonate (calcite)	-1207.6	-1129.1	91.7	83.5								
$CCaO_3$	Calcium carbonate (aragonite)	-1207.8	-1128.2	88.0	82.3								
$CCdO_3$	Cadmium carbonate	-750.6	-669.4	92.5									
$CClFO$	Carbonyl chloride fluoride											276.7	52.4
$CClF_3$	Chlorotrifluoromethane									-706.3			66.9
$CClN$	Cyanogen chloride					112.1				138.0	131.0	236.2	45.0
$CClN_3O_6$	Chlorotrinitromethane					-27.1				18.4			
CCl_2F_2	Dichlorodifluoromethane									-477.4	-439.4	300.8	72.3
CCl_2O	Carbonyl chloride									-219.1	-204.9	283.5	57.7
CCl_3	Trichloromethyl									59.0			
CCl_3F	Trichlorofluoromethane					-301.3	-236.8	225.4	121.6	-268.3			78.1
CCl_4	Tetrachloromethane					-128.2			130.7	-95.7			83.3
$CCoO_3$	Cobalt(II) carbonate	-713.0											
CCs_2O_3	Cesium carbonate	-1139.7	-1054.3	204.5	123.9								
$CCuN$	Copper(I) cyanide	96.2	111.3	84.5									
CFN	Cyanogen fluoride											224.7	41.8
CF_2O	Carbonyl fluoride									-639.8			46.8
CF_3	Trifluoromethyl									-477.0	-464.0	264.5	49.6
CF_3I	Trifluoroiodomethane									-587.8		307.4	70.9
CF_4	Tetrafluoromethane									-933.6		261.6	61.1
$CFeO_3$	Iron(II) carbonate	-740.6	-666.7	92.9	82.1								
CFe_3	Iron carbide	25.1	20.1	104.6	105.9								
CH	Methylidyne									595.8			
$CHBrClF$	Bromochlorofluoromethane											304.3	63.2
$CHBrCl_2$	Bromodichloromethane											316.4	67.4
$CHBrF_2$	Bromodifluoromethane									-424.9		295.1	58.7
$CHBr_2Cl$	Chlorodibromomethane											327.7	69.2
$CHBr_2F$	Dibromofluoromethane											316.8	65.1
$CHBr_3$	Tribromomethane					-22.3	-5.0	220.9	130.7	23.8	8.0	330.9	71.2
$CHClF_2$	Chlorodifluoromethane									-482.6		280.9	55.9
$CHCl_2F$	Dichlorofluoromethane											293.1	60.9
$CHCl_3$	Trichloromethane					-134.1	-73.7	201.7	114.2	-102.7	6.0	295.7	65.7
$CHCsO_3$	Cesium hydrogen carbonate	-966.1											
$CHFO$	Formyl fluoride											246.6	39.9
CHF_3	Trifluoromethane									-695.4		259.7	51.0
CHI_3	Triiodomethane	-181.1								251.0		356.2	75.0
$CHKO_2$	Potassium formate	-679.7											
$CHKO_3$	Potassium hydrogen carbonate	-963.2	-863.5	115.5									
CHN	Hydrogen cyanide					108.9	125.0	112.8	70.6	135.1	124.7	201.8	35.9
$CHNO$	Isocyanic acid (HNCO)											238.0	44.9
$CHNS$	Isothiocyanic acid									127.6	113.0	247.8	46.9
CHN_3O_6	Trinitromethane					-32.8				-13.4		435.6	134.1
$CHNaO_2$	Sodium formate	-666.5	-599.9	103.8	82.7								
$CHNaO_3$	Sodium hydrogen carbonate	-950.8	-851.0	101.7	87.6								
CHO	Oxomethyl (HCO)									43.1	28.0	224.7	34.6
CH_2	Methylene									390.4	372.9	194.9	33.8
CH_2BrCl	Bromochloromethane											287.6	52.7
CH_2BrF	Bromofluoromethane											276.3	49.2
CH_2Br_2	Dibromomethane											293.2	54.7
CH_2ClF	Chlorofluoromethane											264.4	47.0
CH_2Cl_2	Dichloromethane					-124.2		177.8	101.2	-95.4		270.2	51.0
CH_2F_2	Difluoromethane									-452.3		246.7	42.9
CH_2I_2	Diiodomethane					68.5	90.4	174.1	134.0	119.5	95.8	309.7	57.7
CH_2N_2	Diazomethane											242.9	52.5
CH_2N_2	Cyanamide	58.8											
$CH_2N_2O_4$	Dinitromethane					-104.9				-61.5		358.1	86.4
CH_2O	Formaldehyde									-108.6	-102.5	218.8	35.4

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$(CH_2O)_x$	Paraformaldehyde	-177.6											
CH_2O_2	Formic acid					-425.0	-361.4	129.0	99.0	-378.7			
CH_2S_3	Trithiocarbonic acid					24.0							
CH_3	Methyl									145.7	147.9	194.2	38.7
CH_3BO	Borane carbonyl									-111.2	-92.9	249.4	59.5
CH_3Br	Bromomethane					-59.8				-35.4	-26.3	246.4	42.4
CH_3Cl	Chloromethane									-81.9		234.6	40.8
CH_3Cl_3Si	Methyltrichlorosilane							262.8	163.1	-528.9		351.1	102.4
CH_3F	Fluoromethane											222.9	37.5
CH_3I	Iodomethane					-13.6		163.2	126.0	14.4		254.1	44.1
CH_3NO	Formamide					-254.0				-193.9			
CH_3NO_2	Nitromethane					-112.6	-14.4	171.8	106.6	-80.8		282.9	55.5
CH_3NO_2	Methyl nitrite									-66.1			
CH_3NO_3	Methyl nitrate					-156.3	-43.4	217.1	157.3	-122.0		305.8	76.6
CH_4	Methane									-74.6	-50.5	186.3	35.7
CH_4N_2	Ammonium cyanide	0.4			134.0								
CH_4N_2O	Urea	-333.1								-245.8			
CH_4N_2S	Thiourea	-89.1								22.9			
$CH_4N_4O_2$	Nitroguanidine	-92.4											
CH_4O	Methanol					-239.2	-166.6	126.8	81.1	-201.0	-162.3	239.9	44.1
CH_4S	Methanethiol					-46.7	-7.7	169.2	90.5	-22.9	-9.3	255.2	50.3
CH_5N	Methylamine					-47.3	35.7	150.2	102.1	-22.5	32.7	242.9	50.1
CH_5NO_3	Ammonium hydrogen carbonate	-849.4	-665.9	120.9									
CH_5N_3	Guanidine	-56.0											
CH_5N_3S	Hydrazinecarbothioamide	24.7											
$CH_5N_5O_2$	3-Amino-1-nitroguanidine	22.1											
CH_6ClN	Methylamine hydrochloride	-298.1											
CH_6N_2	Methylhydrazine					54.2	180.0	165.9	134.9	94.7	187.0	278.8	71.1
CH_6Si	Methylsilane											256.5	65.9
CHg_2O_3	Mercury(I) carbonate	-553.5	-468.1	180.0									
CIN	Cyanogen iodide	166.2	185.0	96.2						225.5	196.6	256.8	48.3
CI_4	Tetraiodomethane	-392.9								474.0		391.9	95.9
CKN	Potassium cyanide	-113.0	-101.9	128.5	66.3								
CKNS	Potassium thiocyanate	-200.2	-178.3	124.3	88.5								
CK_2O_3	Potassium carbonate	-1151.0	-1063.5	155.5	114.4								
CLi_2O_3	Lithium carbonate	-1215.9	-1132.1	90.4	99.1								
$CMgO_3$	Magnesium carbonate	-1095.8	-1012.1	65.7	75.5								
$CMnO_3$	Manganese(II) carbonate	-894.1	-816.7	85.8	81.5								
CN	Cyanide									437.6	407.5	202.6	29.2
CNNa	Sodium cyanide	-87.5	-76.4	115.6	70.4								
CNNaO	Sodium cyanate	-405.4	-358.1	96.7	86.6								
CN_4O_8	Tetranitromethane					38.4				82.4		503.7	176.1
CNa_2O_3	Sodium carbonate	-1130.7	-1044.4	135.0	112.3								
CO	Carbon monoxide									-110.5	-137.2	197.7	29.1
COS	Carbon oxysulfide									-142.0	-169.2	231.6	41.5
CO_2	Carbon dioxide									-393.5	-394.4	213.8	37.1
CO_3Pb	Lead(II) carbonate	-699.1	-625.5	131.0	87.4								
CO_3Rb_2	Rubidium carbonate	-1136.0	-1051.0	181.3	117.6								
CO_3Sr	Strontium carbonate	-1220.1	-1140.1	97.1	81.4								
CO_3Tl_2	Thallium(I) carbonate	-700.0	-614.6	155.2									
CO_3Zn	Zinc carbonate	-812.8	-731.5	82.4	79.7								
CS	Carbon monosulfide									280.3	228.8	210.6	29.8
CS_2	Carbon disulfide					89.0	64.6	151.3	76.4	116.7	67.1	237.8	45.4
CSe_2	Carbon diselenide					164.8							
CSi	Silicon carbide (cubic)	-65.3	-62.8	16.6	26.9								
CSi	Silicon carbide (hexagonal)	-62.8	-60.2	16.5	26.7								
C_2	Dicarbon									831.9	775.9	199.4	43.2
C_2BrF_5	Bromopentafluoroethane									-1064.4			
$C_2Br_2ClF_3$	1,2-Dibromo-1-chloro-1,2,2-trifluoroethane					-691.7				-656.6			
$C_2Br_2F_4$	1,2-Dibromotetrafluoroethane					-817.7				-789.1			
C_2Br_4	Tetrabromoethene											387.1	102.7
C_2Br_6	Hexabromoethane											441.9	139.3
C_2Ca	Calcium carbide	-59.8	-64.9	70.0	62.7								
C_2CaN_2	Calcium cyanide	-184.5											
C_2CaO_4	Calcium oxalate	-1360.6											

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
C_2ClF_3	Chlorotrifluoroethene					-522.7				-505.5	-523.8	322.1	83.9
C_2ClF_5	Chloropentafluoroethane									-1118.8			184.2
$C_2Cl_2F_4$	1,2-Dichloro-1,1,2,2-tetrafluoroethane					-960.2			111.7	-937.0			
$C_2Cl_2O_2$	Oxalyl chloride					-367.6				-335.8			
$C_2Cl_3F_3$	1,1,2-Trichloro-1,2,2-trifluoroethane					-745.0			170.1	-716.8			
C_2Cl_3N	Trichloroacetonitrile											336.6	96.1
C_2Cl_4	Tetrachloroethene					-50.6	3.0	266.9	143.4	-10.9			
$C_2Cl_4F_2$	1,1,1,2-Tetrachloro-2,2-difluoroethane									-489.9	-407.0	382.9	123.4
$C_2Cl_4F_2$	1,1,2,2-Tetrachloro-1,2-difluoroethane								173.6				
C_2Cl_4O	Trichloroacetyl chloride					-280.8				-239.8			
C_2Cl_6	Hexachloroethane	-202.8		237.3	198.2					-143.6			
C_2F_3N	Trifluoroacetonitrile									-497.9		298.1	77.9
C_2F_4	Tetrafluoroethene	-820.5								-658.9		300.1	80.5
C_2F_6	Hexafluoroethane									-1344.2		332.3	106.7
C_2HBr	Bromoacetylene											253.7	55.7
$C_2HBrClF_3$	1-Bromo-2-chloro-1,1,2-trifluoroethane					-675.3				-644.8			
$C_2HBrClF_3$	2-Bromo-2-chloro-1,1,1-trifluoroethane					-720.0				-690.4			
C_2HCl	Chloroacetylene											242.0	54.3
C_2HClF_2	1-Chloro-2,2-difluoroethene									-315.5	-289.1	303.0	72.1
C_2HCl_2F	1,1-Dichloro-2-fluoroethene											313.9	76.5
$C_2HCl_2F_3$	2,2-Dichloro-1,1,1-trifluoroethane											352.8	102.5
C_2HCl_3	Trichloroethene					-43.6		228.4	124.4	-9.0		324.8	80.3
C_2HCl_3O	Trichloroacetaldehyde					-234.5			151.0	-196.6			
C_2HCl_3O	Dichloroacetyl chloride					-280.4				-241.0			
$C_2HCl_3O_2$	Trichloroacetic acid	-503.3											
C_2HCl_5	Pentachloroethane					-187.6			173.8	-142.0			
C_2HF	Fluoroacetylene											231.7	52.4
C_2HF_3	Trifluoroethene									-490.5			
$C_2HF_3O_2$	Trifluoroacetic acid					-1069.9				-1031.4			
C_2HF_5	Pentafluoroethane									-1100.4			
C_2H_2	Acetylene									227.4	209.9	200.9	44.0
$C_2H_2BrF_3$	2-Bromo-1,1,1-trifluoroethane									-694.5			
$C_2H_2Br_2$	*cis*-1,2-Dibromoethene											311.3	68.8
$C_2H_2Br_2$	*trans*-1,2-Dibromoethene											313.5	70.3
$C_2H_2Br_2Cl_2$	1,2-Dibromo-1,2-dichloroethane									-36.9			
$C_2H_2Br_4$	1,1,2,2-Tetrabromoethane								165.7				
$C_2H_2ClF_3$	2-Chloro-1,1,1-trifluoroethane											326.5	89.1
$C_2H_2Cl_2$	1,1-Dichloroethene					-23.9	24.1	201.5	111.3	2.8	25.4	289.0	67.1
$C_2H_2Cl_2$	*cis*-1,2-Dichloroethene					-26.4		198.4	116.4	4.6		289.6	65.1
$C_2H_2Cl_2$	*trans*-1,2-Dichloroethene					-24.3	27.3	195.9	116.8	5.0	28.6	290.0	66.7
$C_2H_2Cl_2O$	Chloroacetyl chloride					-283.7				-244.8			
$C_2H_2Cl_2O_2$	Dichloroacetic acid					-496.3							
$C_2H_2Cl_3NO$	2,2,2-Trichloroacetamide	-358.0											
$C_2H_2Cl_4$	1,1,1,2-Tetrachloroethane											356.0	102.7
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane					-195.0		246.9	162.3	-149.2		362.8	100.8
$C_2H_2F_2$	1,1-Difluoroethene									-335.0		266.2	60.1
$C_2H_2F_2$	*cis*-1,2-Difluoroethene											268.3	58.2
$C_2H_2F_3I$	1,1,1-Trifluoro-2-iodoethane									-644.5			
$C_2H_2I_2$	*cis*-1,2-Diiodoethene									-207.4			
C_2H_2O	Ketene					-67.9				-47.5	-48.3	247.6	51.8
$C_2H_2O_2$	Glyoxal									-212.0	-189.7	272.5	60.6
$C_2H_2O_4$	Oxalic acid	-829.9		109.8	91.0					-731.8	-662.7	320.6	86.2
$C_2H_2O_4Sr$	Strontium formate	-1393.3											
C_2H_2S	Thiirene									300.0	275.8	255.3	54.7
C_2H_3Br	Bromoethene									79.2	81.8	275.8	55.5
C_2H_3BrO	Acetyl bromide					-223.5				-190.4			
$C_2H_3BrO_2$	Bromoacetic acid									-383.5	-338.3	337.0	80.5
C_2H_3Cl	Chloroethene	-94.1			59.4	14.6				37.2	53.6	264.0	53.7
$C_2H_3ClF_2$	1-Chloro-1,1-difluoroethane											307.2	82.5
C_2H_3ClO	Acetyl chloride					-272.9	-208.0	200.8	117.0	-242.8	-205.8	295.1	67.8
$C_2H_3ClO_2$	Chloroacetic acid	-509.7								-427.6	-368.5	325.9	78.8

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_2H_3Cl_2F$	1,1-Dichloro-1-fluoroethane											320.2	88.7
$C_2H_3Cl_3$	1,1,1-Trichloroethane					-177.4		227.4	144.3	-144.4		323.1	93.3
$C_2H_3Cl_3$	1,1,2-Trichloroethane					-190.8		232.6	150.9	-151.3		337.2	89.0
C_2H_3F	Fluoroethene									-138.8			
C_2H_3FO	Acetyl fluoride					-467.2				-442.1			
$C_2H_3F_3$	1,1,1-Trifluoroethane									-744.6		279.9	78.2
$C_2H_3F_3$	1,1,2-Trifluoroethane									-730.7			
$C_2H_3F_3O$	2,2,2-Trifluoroethanol					-932.4				-888.4			
C_2H_3I	Iodoethene											285.0	57.9
C_2H_3IO	Acetyl iodide					-163.5				-126.4			
$C_2H_3KO_2$	Potassium acetate	-723.0											
C_2H_3N	Acetonitrile					40.6	86.5	149.6	91.5	74.0	91.9	243.4	52.2
C_2H_3N	Isocyanomethane					130.8	159.5	159.0		163.5	165.7	246.9	52.9
C_2H_3NO	Methyl isocyanate					-92.0							
$C_2H_3NO_2$	Nitroethene									33.3		300.5	73.7
$C_2H_3NO_3$	Oxamic acid	-661.2								-552.3			
C_2H_3NS	Methyl isothiocyanate	79.4											
$C_2H_3NaO_2$	Sodium acetate	-708.8	-607.2	123.0	79.9								
C_2H_4	Ethylene									52.4	68.4	219.3	42.9
C_2H_4BrCl	1-Bromo-2-chloroethane								130.1				
$C_2H_4Br_2$	1,1-Dibromoethane					-66.2						327.7	80.8
$C_2H_4Br_2$	1,2-Dibromoethane					-79.2		223.3	136.0	-37.5			
C_2H_4ClF	1-Chloro-1-fluoroethane									-313.4			
$C_2H_4Cl_2$	1,1-Dichloroethane					-158.4	-73.8	211.8	126.3	-127.7	-70.8	305.1	76.2
$C_2H_4Cl_2$	1,2-Dichloroethane					-166.8			128.4	-126.4		308.4	78.7
$C_2H_4F_2$	1,1-Difluoroethane									-497.0		282.5	67.8
$C_2H_4I_2$	1,2-Diiodoethane	9.3								75.0			
$C_2H_4N_2O_2$	Oxamide	-504.4								-387.1			
$C_2H_4N_2O_2$	Ethanedial dioxime	-90.5											
$C_2H_4N_2O_4$	1,1-Dinitroethane					-148.2							
$C_2H_4N_2O_4$	1,2-Dinitroethane					-165.2							
$C_2H_4N_2S_2$	Ethanedithioamide	-20.8								83.0			
$C_2H_4N_4$	1*H*-1,2,4-Triazol-3-amine	76.8											
C_2H_4O	Acetaldehyde					-192.2	-127.6	160.2	89.0	-166.2	-133.0	263.8	55.3
C_2H_4O	Oxirane					-78.0	-11.8	153.9	88.0	-52.6	-13.0	242.5	47.9
C_2H_4OS	Thioacetic acid					-216.9				-175.1			
$C_2H_4O_2$	Acetic acid					-484.3	-389.9	159.8	123.3	-432.2	-374.2	283.5	63.4
$C_2H_4O_2$	Methyl formate					-386.1			119.1	-357.4		285.3	64.4
$C_2H_4O_3$	Peroxyacetic acid												82.4
$C_2H_4O_3$	Glycolic acid									-583.0	-504.9	318.6	87.1
C_2H_4S	Thiirane					51.6				82.0	96.8	255.2	53.3
C_2H_4Si	Ethynylsilane											269.4	72.6
C_2H_5Br	Bromoethane					-90.5	-25.8	198.7	100.8	-61.9	-23.9	286.7	64.5
C_2H_5Cl	Chloroethane					-136.8	-59.3	190.8	104.3	-112.1	-60.4	276.0	62.8
C_2H_5ClO	2-Chloroethanol					-295.4							
C_2H_5F	Fluoroethane											264.5	58.6
C_2H_5I	Iodoethane					-40.0	14.7	211.7	115.1	-8.1	19.2	306.0	66.9
C_2H_5N	Ethyleneimine					91.9				126.5			
C_2H_5NO	Acetamide	-317.0		115.0	91.3					-238.3			
C_2H_5NO	*N*-Methylformamide								123.8				
$C_2H_5NO_2$	Nitroethane					-143.9			134.4	-103.8		320.5	79.0
$C_2H_5NO_2$	Glycine	-528.5								-392.1			
$C_2H_5NO_3$	2-Nitroethanol					-350.7							
$C_2H_5NO_3$	Ethyl nitrate					-190.4				-154.1			
C_2H_5NS	Thioacetamide	-71.7								11.4			
C_2H_6	Ethane									-84.0	-32.0	229.2	52.5
C_2H_6Cd	Dimethyl cadmium					63.6	139.0	201.9	132.0	101.6	146.9	303.0	
C_2H_6Hg	Dimethyl mercury					59.8	140.3	209.0		94.4	146.1	306.0	83.3
$C_2H_6N_2O$	*N*-Methylurea	-332.8											
$C_2H_6N_4O_2$	1,2-Hydrazinedicarboxamide	-498.7											
$C_2H_6N_4O_2$	Oxalyl dihydrazide	-295.2											
C_2H_6O	Ethanol					-277.6	-174.8	160.7	112.3	-234.8	-167.9	281.6	65.6
C_2H_6O	Dimethyl ether					-203.3				-184.1	-112.6	266.4	64.4
C_2H_6OS	Dimethyl sulfoxide					-204.2	-99.9	188.3	153.0	-151.3			
$C_2H_6O_2$	Ethylene glycol					-460.0		163.2	148.6	-392.2		303.8	82.7
$C_2H_6O_2S$	Dimethyl sulfone	-450.1	-302.4	142.0						-373.1	-272.7	310.6	100.0

Molecular formula	Name	Crystal				Liquid				Gas			
		$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_2H_6O_3S$	Dimethyl sulfite					-523.6				-483.4			
$C_2H_6O_4S$	Dimethyl sulfate					-735.5				-687.0			
C_2H_6S	Ethanethiol					-73.6	-5.5	207.0	117.9	-46.1	-4.8	296.2	72.7
C_2H_6S	Dimethyl sulfide					-65.3		196.4	118.1	-37.4		286.0	74.1
$C_2H_6S_2$	1,2-Ethanedithiol					-54.3				-9.7			
$C_2H_6S_2$	Dimethyl disulfide					-62.6		235.4	146.1	-24.7			
C_2H_6Zn	Dimethyl zinc					23.4		201.6	129.2	53.0			
C_2H_7N	Ethylamine					-74.1			130.0	-47.5	36.3	283.8	71.5
C_2H_7N	Dimethylamine					-43.9	70.0	182.3	137.7	-18.8	68.5	273.1	70.7
C_2H_7NO	Ethanolamine								195.5				
C_2H_8ClN	Dimethylamine hydrochloride	-289.3											
$C_2H_8N_2$	1,2-Ethanediamine					-63.0			172.6	-18.0			
$C_2H_8N_2$	1,1-Dimethylhydrazine					48.9	206.4	198.0	164.1	84.1			
$C_2H_8N_2$	1,2-Dimethylhydrazine					52.7				92.2			
$C_2H_8N_2O_4$	Ammonium oxalate	-1123.0			226.0								
C_2HgO_4	Mercury(II) oxalate	-678.2											
C_2I_2	Diiodoacetylene											313.1	70.3
C_2I_4	Tetraiodoethene	305.0											
$C_2K_2O_4$	Potassium oxalate	-1346.0											
C_2MgO_4	Magnesium oxalate	-1269.0											
C_2N_2	Cyanogen					285.9				306.7		241.9	56.8
$C_2N_4O_6$	Trinitroacetonitrile					183.7							
$C_2Na_2O_4$	Sodium oxalate									-1318.0			
C_2O_4Pb	Lead(II) oxalate	-851.4	-750.1	146.0	105.4								
C_3F_8	Perfluoropropane									-1783.2			
$C_3H_2N_2$	Malononitrile	186.4								265.5			
$C_3H_2O_2$	2-Propynoic acid					-193.2							
$C_3H_2O_3$	1,3-Dioxol-2-one					-459.9				-418.6			
$C_3H_3Cl_3$	1,2,3-Trichloropropene					-101.8							
$C_3H_3F_3$	3,3,3-Trifluoropropene									-614.2			
C_3H_3N	Acrylonitrile					147.1				180.6			
C_3H_3NO	Oxazole					-48.0				-15.5			
C_3H_3NO	Isoxazole					42.1				78.6			
C_3H_4	Allene									190.5			
C_3H_4	Propyne									184.9			
C_3H_4	Cyclopropene									277.1			
$C_3H_4Cl_2$	2,3-Dichloropropene					-73.3							
$C_3H_4Cl_4$	1,1,1,3-Tetrachloropropane					-208.7							
$C_3H_4Cl_4$	1,2,2,3-Tetrachloropropane					-251.8							
$C_3H_4F_4O$	2,2,3,3-Tetrafluoro-1-propanol					-1114.9				-1061.3			
$C_3H_4N_2$	1*H*-Pyrazole	105.4			81.0					179.4			
$C_3H_4N_2$	Imidazole	49.8								132.9			
C_3H_4O	Acrolein												71.3
$C_3H_4O_2$	1,2-Propanedione					-309.1				-271.0			
$C_3H_4O_2$	Acrylic acid					-383.8			145.7				
$C_3H_4O_2$	2-Oxetanone					-329.9		175.3	122.1	-282.9			
$C_3H_4O_3$	Ethylene carbonate					-682.8			133.9	-508.4			
C_3H_5Br	*cis*-1-Bromopropene					7.9				40.8			
C_3H_5Br	3-Bromopropene					12.2				45.2			
C_3H_5BrO	Bromoacetone									-181.0			
C_3H_5Cl	2-Chloropropene									-21.0			
C_3H_5Cl	3-Chloropropene								125.1				
C_3H_5ClO	Epichlorohydrin					-148.4			131.6	-107.8			
$C_3H_5ClO_2$	2-Chloropropanoic acid					-522.5				-475.8			
$C_3H_5ClO_2$	3-Chloropropanoic acid	-549.3											
$C_3H_5ClO_2$	Ethyl chloroformate					-505.3				-462.9			
$C_3H_5ClO_2$	Methyl chloroacetate					-487.0				-444.0			
$C_3H_5Cl_3$	1,2,3-Trichloropropane					-230.6			183.6	-182.9			
C_3H_5I	3-Iodopropene					53.7				91.5			
C_3H_5IO	Iodoacetone									-130.5			
$C_3H_5IO_2$	3-Iodopropanoic acid	-460.0											
C_3H_5N	Propanenitrile					15.5			119.3	51.7			
C_3H_5N	2-Propyn-1-amine					205.7							
C_3H_5N	Ethyl isocyanide					108.6				141.7			
C_3H_5NO	Acrylamide	-212.1			110.6	-224.0				-130.2			
$C_3H_5NO_3$	Nitroacetone					-278.6							

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_3H_5NO_4$	Methyl nitroacetate					-464.0							
$C_3H_5N_3O_9$	Trinitroglycerol					-370.9				-279.1		545.9	234.2
C_3H_6	Propene					4.0				20.0			
C_3H_6	Cyclopropane					35.2				53.3	104.5	237.5	55.6
$C_3H_6Br_2$	1,2-Dibromopropane					-113.6				-71.6			
$C_3H_6Cl_2$	1,2-Dichloropropane, (±)					-198.8			149.1	-162.8			
$C_3H_6Cl_2$	1,3-Dichloropropane					-199.9				-159.2			
$C_3H_6Cl_2$	2,2-Dichloropropane					-205.8				-173.2			
$C_3H_6Cl_2O$	2,3-Dichloro-1-propanol					-381.5				-316.3			
$C_3H_6Cl_2O$	1,3-Dichloro-2-propanol					-385.3				-318.4			
$C_3H_6I_2$	1,2-Diiodopropane									35.6			
$C_3H_6I_2$	1,3-Diiodopropane					-9.0							
$C_3H_6N_2O_2$	Propanediamide	-546.1											
$C_3H_6N_2O_2$	*N*-(Aminocarbonyl)acetamide	-544.2								-441.2			
$C_3H_6N_2O_4$	1,1-Dinitropropane					-163.2				-100.7			
$C_3H_6N_2O_4$	1,3-Dinitropropane					-207.1							
$C_3H_6N_2O_4$	2,2-Dinitropropane					-181.2							
$C_3H_6N_6O_6$	Hexahydro-1,3,5-trinitro-1,3,5-triazine									192.0		482.4	230.2
C_3H_6O	Allyl alcohol					-171.8			138.9	-124.5			
C_3H_6O	Propanal					-215.6				-185.6		304.5	80.7
C_3H_6O	Acetone					-248.4		199.8	126.3	-217.1	-152.7	295.3	74.5
C_3H_6O	Methyloxirane					-123.0		196.5	120.4	-94.7		286.9	72.6
C_3H_6O	Oxetane					-110.8				-80.5			
$C_3H_6O_2$	Propanoic acid					-510.7		191.0	152.8	-455.7			
$C_3H_6O_2$	Ethyl formate								149.3				
$C_3H_6O_2$	Methyl acetate					-445.9			141.9	-413.3		324.4	86.0
$C_3H_6O_2$	1,3-Dioxolane					-333.5			118.0	-298.0			
$C_3H_6O_2S$	Thiolactic acid					-468.4							
$C_3H_6O_3$	1,3,5-Trioxane	-522.5		133.0	111.4					-465.9			
C_3H_6S	Thietane					24.7		184.9		60.6	107.1	285.0	68.3
C_3H_6S	Methylthiirane					11.3				45.8			
$C_3H_6S_2$	1,2-Dithiolane									0.0	47.7	313.5	86.5
$C_3H_6S_2$	1,3-Dithiolane									10.0	54.7	323.3	84.7
$C_3H_6S_3$	1,3,5-Trithiane									80.0	130.4	336.4	111.3
C_3H_7Br	1-Bromopropane					-121.9				-87.0			
C_3H_7Br	2-Bromopropane					-130.5				-99.4			
C_3H_7Cl	1-Chloropropane					-160.5				-131.9			
C_3H_7Cl	2-Chloropropane					-172.3				-144.9			
$C_3H_7ClO_2$	3-Chloro-1,2-propanediol					-525.3							
$C_3H_7ClO_2$	2-Chloro-1,3-propanediol					-517.5							
C_3H_7F	1-Fluoropropane									-285.9			
C_3H_7F	2-Fluoropropane									-293.5			
C_3H_7I	1-Iodopropane					-66.0				-30.0			
C_3H_7I	2-Iodopropane					-74.8				-40.3			
C_3H_7N	Allylamine					-10.0							
C_3H_7N	Cyclopropylamine					45.8		187.7	147.1	77.0			
C_3H_7NO	*N,N*-Dimethylformamide					-239.3			150.6	-192.4			
C_3H_7NO	Propanamide	-338.2								-259.0			
$C_3H_7NO_2$	1-Nitropropane					-167.2				-124.3		350.0	104.1
$C_3H_7NO_2$	2-Nitropropane					-180.3			170.3	-138.9			
$C_3H_7NO_2$	Ethyl carbamate	-517.1			156.4	-497.3				-446.3			
$C_3H_7NO_2$	*DL*-Alanine	-563.6											
$C_3H_7NO_2$	*D*-Alanine	-561.2											
$C_3H_7NO_2$	*L*-Alanine	-604.0								-465.9			
$C_3H_7NO_2$	β-Alanine	-558.0								-424.0			
$C_3H_7NO_2$	Sarcosine	-513.3								-367.3			
$C_3H_7NO_2S$	*L*-Cysteine	-534.1											
$C_3H_7NO_3$	Propyl nitrate					-214.5				-174.1		362.6	123.2
$C_3H_7NO_3$	Isopropyl nitrate					-229.7				-191.0			
$C_3H_7NO_3$	*DL*-Serine	-739.0											
$C_3H_7NO_3$	*L*-Serine	-732.7											
C_3H_8	Propane					-120.9				-103.8	-23.4	270.3	73.6
$C_3H_8N_2O$	*N*-Ethylurea	-357.8											
$C_3H_8N_2O$	*N,N*-Dimethylurea	-319.1											
$C_3H_8N_2O$	*N,N'*-Dimethylurea	-312.1											

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_3H_8N_2O_3$	Oxymethurea	-717.0											
C_3H_8O	1-Propanol					-302.6		193.6	143.9	-255.1		322.6	85.6
C_3H_8O	2-Propanol					-318.1		181.1	156.5	-272.6		309.2	89.3
C_3H_8O	Ethyl methyl ether									-216.4		309.2	93.3
$C_3H_8O_2$	1,2-Propylene glycol					-501.0			190.8	-429.8			
$C_3H_8O_2$	1,3-Propylene glycol					-480.8				-408.0			
$C_3H_8O_2$	Ethylene glycol monomethyl ether								171.1				
$C_3H_8O_2$	Dimethoxymethane					-377.8		244.0	162.0	-348.5			
$C_3H_8O_3$	Glycerol					-669.6		206.3	218.9	-577.9			
C_3H_8S	1-Propanethiol					-99.9		242.5	144.6	-67.8			
C_3H_8S	2-Propanethiol					-105.9		233.5	145.3	-76.2			
C_3H_8S	Ethyl methyl sulfide					-91.6		239.1	144.6	-59.6			
$C_3H_8S_2$	1,3-Propanedithiol					-79.4				-29.8			
C_3H_9Al	Trimethyl aluminum					-136.4	-9.9	209.4	155.6	-74.1			
C_3H_9B	Trimethylborane					-143.1	-32.1	238.9		-124.3	-35.9	314.7	88.5
$C_3H_9BO_3$	Trimethyl borate								189.9				
C_3H_9ClSi	Trimethylchlorosilane					-382.8	-246.4	278.2		-352.8	-243.5	369.1	
C_3H_9N	Propylamine					-101.5			164.1	-70.1	39.9	325.4	91.2
C_3H_9N	Isopropylamine					-112.3		218.3	163.8	-83.7	32.2	312.2	97.5
C_3H_9N	Trimethylamine					-45.7		208.5	137.9	-23.6		287.1	91.8
$C_3H_{10}ClN$	Propylamine hydrochloride	-354.7											
$C_3H_{10}ClN$	Trimethylamine hydrochloride	-282.9											
$C_3H_{10}N_2$	1,2-Propanediamine, (±)					-97.8				-53.6			
$C_3H_{10}Si$	Trimethylsilane											331.0	117.9
$C_3H_{12}BN$	Trimethylamine borane	-142.5	70.7	187.0									
$C_3H_{12}BN$	Aminetrimethylboron	-284.1	-79.3	218.0									
C_4Cl_6	Hexachloro-1,3-butadiene					-24.5							
C_4F_8	Perfluorocyclobutane									-1542.6			
C_4F_{10}	Perfluorobutane								127.2				
$C_4H_2N_2$	*trans*-2-Butenedinitrile	268.2								340.2			
$C_4H_2O_3$	Maleic anhydride	-469.8								-398.3			
$C_4H_2O_4$	2-Butynedioic acid	-577.3											
$C_4H_3NO_3$	2-Nitrofuran	-104.1								-28.8			
$C_4H_4BrNO_2$	*N*-Bromosuccinimide	-335.9											
$C_4H_4ClNO_2$	*N*-Chlorosuccinimide	-357.9											
$C_4H_4N_2$	Succinonitrile	139.7		191.6	145.6					209.7			
$C_4H_4N_2$	Pyrazine	139.8								196.1			
$C_4H_4N_2$	Pyrimidine					145.9				195.7			
$C_4H_4N_2$	Pyridazine					224.9				278.3			
$C_4H_4N_2O_2$	Uracil	-429.4			120.5					-302.9			
$C_4H_4N_2O_3$	Barbituric acid	-634.7											
C_4H_4O	Furan					-62.3		177.0	114.8	-34.8		267.2	65.4
$C_4H_4O_2$	Diketene					-233.1				-190.3			
$C_4H_4O_3$	Succinic anhydride	-608.6								-527.9			
$C_4H_4O_4$	Maleic acid	-789.4		160.8	137.0					-679.4			
$C_4H_4O_4$	Fumaric acid	-811.7		168.0	142.0					-675.8			
C_4H_4S	Thiophene					80.2		181.2	123.8	114.9	126.1	278.8	72.8
C_4H_5N	*trans*-2-Butenenitrile					95.1				134.3			
C_4H_5N	3-Butenenitrile					117.8				159.7			
C_4H_5N	2-Methylacrylonitrile								126.3				
C_4H_5N	Pyrrole					63.1		156.4	127.7	108.2			
C_4H_5N	Cyclopropanecarbonitrile					140.8				182.8			
$C_4H_5NO_2$	Succinimide	-459.0								-375.4			
C_4H_5NS	4-Methylthiazole					67.9				111.8			
$C_4H_5N_3O$	Cytosine	-221.3			132.6								
C_4H_6	1,2-Butadiene					138.6				162.3			
C_4H_6	1,3-Butadiene					88.5		199.0	123.6	110.0			
C_4H_6	1-Butyne					141.4				165.2			
C_4H_6	2-Butyne					119.1				145.7			
C_4H_6	Cyclobutene									156.7			
$C_4H_6N_2O_2$	2,5-Piperazinedione	-446.5											
C_4H_6O	Divinyl ether					-39.8				-13.6			
C_4H_6O	*trans*-2-Butenal					-138.7				-100.6			
$C_4H_6O_2$	*trans*-2-Butenoic acid												
$C_4H_6O_2$	Methacrylic acid								161.1				
$C_4H_6O_2$	Vinyl acetate					-349.2				-314.4			

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_4H_6O_2$	Methyl acrylate					-362.2		239.5	158.8	-333.0			
$C_4H_6O_2$	γ-Butyrolactone					-420.9			141.4	-366.5			
$C_4H_6O_3$	Acetic anhydride					-624.4				-572.5			
$C_4H_6O_3$	Propylene carbonate					-613.2			218.6	-582.5			
$C_4H_6O_4$	Succinic acid	-940.5		167.3	153.1					-823.0			
$C_4H_6O_4$	Dimethyl oxalate	-756.3								-708.9			
C_4H_6S	2,3-Dihydrothiophene					52.9				90.7	133.5	303.5	79.8
C_4H_6S	2,5-Dihydrothiophene					47.0				86.9	131.6	297.1	83.3
C_4H_7ClO	2-Chloroethyl vinyl ether					-208.1				-170.1			
$C_4H_7ClO_2$	2-Chlorobutanoic acid					-575.5							
$C_4H_7ClO_2$	3-Chlorobutanoic acid					-556.3							
$C_4H_7ClO_2$	4-Chlorobutanoic acid					-566.3							
$C_4H_7ClO_2$	Propyl chlorocarbonate					-533.4				-492.7			
C_4H_7N	Butanenitrile					-5.8				33.6			
C_4H_7N	2-Methylpropanenitrile					-13.8				23.4			
C_4H_7NO	Acetone cyanohydrin					-120.9							
C_4H_7NO	2-Pyrrolidone					-286.2							
C_4H_7NO	2-Methyl-2-oxazoline					-169.5				-130.5			
$C_4H_7NO_4$	Iminodiacetic acid	-932.6											
$C_4H_7NO_4$	Ethyl nitroacetate					-487.1							
$C_4H_7NO_4$	*L*-Aspartic acid	-973.3											
$C_4H_7N_3O$	Creatinine	-238.5											
C_4H_8	1-Butene					-20.8		227.0	118.0	0.1			
C_4H_8	*cis*-2-Butene					-29.8		219.9	127.0	-7.1			
C_4H_8	*trans*-2-Butene					-33.3				-11.4			
C_4H_8	Isobutene					-37.5				-16.9			
C_4H_8	Cyclobutane					3.7				27.7			
C_4H_8	Methylcyclopropane					1.7							
$C_4H_8Br_2$	1,2-Dibromobutane					-142.1				-91.6			
$C_4H_8Br_2$	1,3-Dibromobutane					-148.0							
$C_4H_8Br_2$	1,4-Dibromobutane					-140.3				-87.8			
$C_4H_8Br_2$	2,3-Dibromobutane					-139.6				-102.0			
$C_4H_8Br_2$	1,2-Dibromo-2-methylpropane					-156.6				-113.3			
$C_4H_8Cl_2$	1,3-Dichlorobutane					-237.3				-195.0			
$C_4H_8Cl_2$	1,4-Dichlorobutane					-229.8				-183.4			
$C_4H_8Cl_2O$	Bis(2-chloroethyl) ether								220.9				
$C_4H_8I_2$	1,4-Diiodobutane					-30.0							
$C_4H_8N_2O_2$	Succinamide	-581.2											
$C_4H_8N_2O_2$	Dimethylglyoxime	-199.7											
$C_4H_8N_2O_3$	*L*-Asparagine	-789.4											
$C_4H_8N_2O_3$	*N*-Glycylglycine	-747.7											
$C_4H_8N_2O_4$	1,4-Dinitrobutane					-237.5							
$C_4H_8N_8O_8$	Cyclotetramethylenetetranitramine									187.9		568.8	275.5
C_4H_8O	Ethyl vinyl ether					-167.4				-140.8			
C_4H_8O	1,2-Epoxybutane					-168.9		230.9	147.0				
C_4H_8O	Butanal					-239.2		246.6	163.7	-204.8		343.7	103.4
C_4H_8O	Isobutanal					-247.3				-215.7			
C_4H_8O	2-Butanone					-273.3		239.1	158.7	-238.5		339.9	101.7
C_4H_8O	Tetrahydrofuran					-216.2		204.3	124.0	-184.1		302.4	76.3
C_4H_8OS	*S*-Ethyl thioacetate					-268.2				-228.1			
$C_4H_8O_2$	Butanoic acid					-533.8		222.2	178.6	-475.9			
$C_4H_8O_2$	2-Methylpropanoic acid								173.0				
$C_4H_8O_2$	Propyl formate					-500.3				-462.7			
$C_4H_8O_2$	Ethyl acetate					-479.3		257.7	170.7	-443.6			
$C_4H_8O_2$	Methyl propanoate								171.2				
$C_4H_8O_2$	1,3-Dioxane					-379.7			143.9	-340.6			
$C_4H_8O_2$	1,4-Dioxane					-353.9		270.2	152.1	-315.3			
$C_4H_8O_2$	2-Methyl-1,3-dioxolane					-386.9				-352.0			
$C_4H_8O_2S$	Sulfolane								180.0				
C_4H_8S	Tetrahydrothiophene					-72.9				-34.1	45.8	309.6	92.5
$C_4H_8S_2$	1,3-Dithiane									-10.0	72.4	333.5	110.4
$C_4H_8S_2$	1,4-Dithiane									0.0	84.5	326.2	109.7
C_4H_9Br	1-Bromobutane					-143.8				-107.1			
C_4H_9Br	2-Bromobutane, (±)					-154.9				-120.3			
C_4H_9Br	2-Bromo-2-methylpropane					-164.4				-132.4			
C_4H_9Cl	1-Chlorobutane					-188.1				-154.4			

Molecular formula	Name	Crystal				Liquid				Gas			
		$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
C_4H_9Cl	2-Chlorobutane					-192.8				-161.1			
C_4H_9Cl	1-Chloro-2-methylpropane					-191.1				-159.3			
C_4H_9Cl	2-Chloro-2-methylpropane					-211.3				-182.2			
C_4H_9ClO	2-Chloroethyl ethyl ether					-335.6				-301.3			
C_4H_9I	1-Iodo-2-methylpropane								162.3				
C_4H_9I	2-Iodo-2-methylpropane					-107.5				-72.1			
C_4H_9N	Cyclobutanamine					5.6				41.2			
C_4H_9N	Pyrrolidine					-41.1		204.1	156.6	-3.6			
C_4H_9NO	Butanamide	-364.8								-282.0			
C_4H_9NO	*N*-Methylpropanamide								179.0				
C_4H_9NO	2-Methylpropanamide	-368.6								-282.6			
C_4H_9NO	*N,N*-Dimethylacetamide					-278.3			175.6	-228.0			
C_4H_9NO	Morpholine								164.8				
$C_4H_9NO_2$	1-Nitrobutane					-192.5				-143.9		369.9	115.1
$C_4H_9NO_2$	2-Nitroisobutane					-217.2				-177.1			
$C_4H_9NO_2$	Propyl carbamate	-552.6								-471.4			
$C_4H_9NO_2$	4-Aminobutanoic acid	-581.0								-441.0			
$C_4H_9NO_3$	3-Nitro-2-butanol					-390.0							
$C_4H_9NO_3$	2-Methyl-2-nitro-1-propanol	-410.1											
$C_4H_9NO_3$	*DL*-Threonine	-758.8											
$C_4H_9NO_3$	*L*-Threonine	-807.2											
$C_4H_9N_3O_2$	Creatine	-537.2											
C_4H_{10}	Butane					-147.3			140.9	-125.7			
C_4H_{10}	Isobutane					-154.2				-134.2			
$C_4H_{10}Hg$	Diethyl mercury					30.1			182.8	75.3			
$C_4H_{10}N_2$	Piperazine	-45.6											
$C_4H_{10}N_2O$	Trimethylurea	-330.5											
$C_4H_{10}N_2O_2$	*N*-Nitrodiethylamine					-106.2				-53.0			
$C_4H_{10}N_2O_4$	*L*-Asparagine, monohydrate	-1086.6											
$C_4H_{10}O$	1-Butanol					-327.3		225.8	177.2	-274.9			
$C_4H_{10}O$	2-Butanol					-342.6		214.9	196.9	-292.8		359.5	112.7
$C_4H_{10}O$	2-Methyl-1-propanol					-334.7		214.7	181.5	-283.8			
$C_4H_{10}O$	2-Methyl-2-propanol					-359.2		193.3	218.6	-312.5		326.7	113.6
$C_4H_{10}O$	Diethyl ether					-279.5		172.4	175.6	-252.1		342.7	119.5
$C_4H_{10}O$	Methyl propyl ether					-266.0		262.9	165.4	-238.1			
$C_4H_{10}O$	Isopropyl methyl ether					-278.8		253.8	161.9	-252.0			
$C_4H_{10}OS$	Diethyl sulfoxide					-268.0				-205.6			
$C_4H_{10}O_2$	1,2-Butanediol, (±)					-523.6							
$C_4H_{10}O_2$	1,3-Butanediol					-501.0				-433.2			
$C_4H_{10}O_2$	1,4-Butanediol					-505.3		223.4	200.1	-428.7			
$C_4H_{10}O_2$	2,3-Butanediol					-541.5			213.0	-482.3			
$C_4H_{10}O_2$	2-Methyl-1,2-propanediol					-539.7							
$C_4H_{10}O_2$	Ethylene glycol monoethyl ether								210.8				
$C_4H_{10}O_2$	Ethylene glycol dimethyl ether					-376.6			193.3				
$C_4H_{10}O_2$	Dimethylacetal					-420.6				-389.7			
$C_4H_{10}O_2$	*tert*-Butyl hydroperoxide					-293.6				-245.9			
$C_4H_{10}O_3$	Diethylene glycol					-628.5			244.8	-571.2			
$C_4H_{10}O_3S$	Diethyl sulfite					-600.7				-552.2			
$C_4H_{10}O_4S$	Diethyl sulfate					-813.2				-756.3			
$C_4H_{10}S$	1-Butanethiol					-124.7			171.2	-88.0			
$C_4H_{10}S$	2-Butanethiol					-131.0				-96.9			
$C_4H_{10}S$	2-Methyl-1-propanethiol					-132.0				-97.3			
$C_4H_{10}S$	2-Methyl-2-propanethiol					-140.5				-109.6			
$C_4H_{10}S$	Diethyl sulfide					-119.4		269.3	171.4	-83.5		368.1	117.0
$C_4H_{10}S$	Methyl propyl sulfide					-118.5		272.5	171.6	-82.2			
$C_4H_{10}S$	Isopropyl methyl sulfide					-124.7		263.1	172.4	-90.5			
$C_4H_{10}S_2$	1,4-Butanedithiol					-105.7				-50.6			
$C_4H_{10}S_2$	Diethyl disulfide					-120.1		269.3	171.4	-79.4			
$C_4H_{11}N$	Butylamine					-127.6			179.2	-91.9			
$C_4H_{11}N$	*sec*-Butylamine					-137.5				-104.6			
$C_4H_{11}N$	*tert*-Butylamine					-150.6			192.1	-121.0			
$C_4H_{11}N$	Isobutylamine					-132.6			183.2	-98.7			
$C_4H_{11}N$	Diethylamine					-103.7			169.2	-72.2			
$C_4H_{11}NO$	*N,N*-Dimethylethanolamine					-253.7				-203.6			
$C_4H_{11}NO_2$	Diethanolamine	-493.8			233.5					-397.1			
$C_4H_{11}NO_3$	Tris(hydroxymethyl)methylamine	-717.8											

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_4H_{12}BrN$	Tetramethylammonium bromide	-251.0											
$C_4H_{12}ClN$	Diethylamine hydrochloride	-358.6											
$C_4H_{12}ClN$	Tetramethylammonium chloride	-276.4											
$C_4H_{12}IN$	Tetramethylammonium iodide	-203.9											
$C_4H_{12}N_2$	2-Methyl-1,2-propanediamine					-133.9				-90.3			
$C_4H_{12}Pb$	Tetramethyl lead					97.9				135.9			
$C_4H_{12}Si$	Tetramethylsilane					-264.0	-100.0	277.3	204.1	-239.1	-99.9	359.0	143.9
$C_4H_{12}Sn$	Tetramethylstannane					-52.3				-18.8			
$C_4H_{13}N_3$	Bis(2-aminoethyl)amine								254.0				
C_4N_2	2-Butynedinitrile					500.4				529.2			
C_4NiO_4	Nickel carbonyl					-633.0	-588.2	313.4	204.6	-602.9	-587.2	410.6	145.2
C_5FeO_5	Iron pentacarbonyl					-774.0	-705.3	338.1	240.6				
$C_5H_2F_6O_2$	Hexafluoroacetylacetone	-2286.7											
$C_5H_3NO_5$	5-Nitro-2-furancarboxylic acid	-516.8											
$C_5H_4N_4$	1*H*-Purine	169.4											
$C_5H_4N_4O$	Hypoxanthine	-110.8		145.6	134.5								
$C_5H_4N_4O_2$	Xanthine	-379.6		161.1	151.3								
$C_5H_4N_4O_3$	Uric acid	-618.8		173.2	166.1								
$C_5H_4O_2$	Furfural					-201.6			163.2	-151.0			
$C_5H_4O_3$	2-Furancarboxylic acid	-498.4								-390.0			
$C_5H_4O_3$	3-Methyl-2,5-furandione					-504.5				-447.2			
$C_5H_5F_3O_2$	1,1,1-Trifluoro-2,4-pentanedione					-1040.2				-993.3			
C_5H_5N	Pyridine					100.2			132.7	140.4			
C_5H_5NO	1*H*-Pyrrole-2-carboxaldehyde	-106.4											
$C_5H_5N_5$	Adenine	96.9			147.0					205.7			
$C_5H_5N_5O$	Guanine	-183.9											
C_5H_6	*cis*-3-Penten-1-yne					226.5							
C_5H_6	*trans*-3-Penten-1-yne					228.2							
C_5H_6	1,3-Cyclopentadiene					105.9				134.3			
$C_5H_6N_2O_2$	Thymine	-462.8			150.8					-328.7			
$C_5H_6O_2$	Furfuryl alcohol					-276.2			204.0	-211.8			
$C_5H_6O_4$	*trans*-1-Propene-1,2-dicarboxylic acid	-824.4											
C_5H_6S	2-Methylthiophene					44.6		218.5	149.8	83.5			
C_5H_6S	3-Methylthiophene					43.1				82.5			
C_5H_7N	*trans*-3-Pentenenitrile					80.9				125.7			
C_5H_7N	Cyclobutanecarbonitrile					103.0				147.4			
C_5H_7N	1-Methylpyrrole					62.4				103.1			
C_5H_7N	2-Methylpyrrole					23.3				74.0			
C_5H_7N	3-Methylpyrrole					20.5				70.2			
$C_5H_7NO_2$	Ethyl cyanoacetate								220.2				
C_5H_8	1,2-Pentadiene									140.7			
C_5H_8	*cis*-1,3-Pentadiene									81.4			
C_5H_8	*trans*-1,3-Pentadiene									76.1			
C_5H_8	1,4-Pentadiene									105.7			
C_5H_8	2,3-Pentadiene									133.1			
C_5H_8	3-Methyl-1,2-butadiene					101.2							
C_5H_8	2-Methyl-1,3-butadiene					48.2		229.3	152.6	75.5			
C_5H_8	Cyclopentene					4.3		201.2	122.4	34.0			
C_5H_8	Spiropentane					157.5		193.7	134.5	185.2			
C_5H_8	Methylenecyclobutane					93.8				121.6			
$C_5H_8N_4O_{12}$	Pentaerythritol tetranitrate	-538.6								-387.0		614.7	294.8
C_5H_8O	Cyclopentanone					-235.9				-192.1			
$C_5H_8O_2$	4-Pentenoic acid					-430.6							
$C_5H_8O_2$	Allyl acetate								184.1				
$C_5H_8O_2$	Ethyl acrylate					-370.6				-354.2			
$C_5H_8O_2$	Methyl *trans*-2-butenoate					-382.9				-341.9			
$C_5H_8O_2$	Methyl methacrylate								191.2				
$C_5H_8O_2$	2,4-Pentanedione					-423.8				-382.0			
$C_5H_8O_2$	Dihydro-4-methyl-2(3*H*)-furanone					-461.3				-406.5			
$C_5H_8O_2$	Tetrahydro-2*H*-pyran-2-one					-436.7				-379.6			
$C_5H_8O_3$	Methyl acetoacetate					-623.2							
$C_5H_8O_4$	Glutaric acid	-960.0											
$C_5H_9ClO_2$	Propyl chloroacetate					-515.5				-467.0			
C_5H_9N	Pentanenitrile					-33.1				10.5			
C_5H_9N	2,2-Dimethylpropanenitrile					-39.8		232.0	179.4	-2.3			

Molecular formula	Name	Crystal				Liquid				Gas			
		$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
C_5H_9N	1,2,5,6-Tetrahydropyridine					33.5							
C_5H_9NO	2-Piperidinone	-306.6											
C_5H_9NO	*N*-Methyl-2-pyrrolidone					-262.2			307.8				
$C_5H_9NO_2$	*L*-Proline	-515.2								-366.2			
$C_5H_9NO_4$	*D*-Glutamic acid	-1005.3											
$C_5H_9NO_4$	*L*-Glutamic acid	-1009.7											
C_5H_{10}	1-Pentene					-46.9		262.6	154.0	-21.1			
C_5H_{10}	*cis*-2-Pentene					-53.7		258.6	151.7	-27.6			
C_5H_{10}	*trans*-2-Pentene					-58.2		256.5	157.0	-31.9			
C_5H_{10}	2-Methyl-1-butene					-61.1		254.0	157.2	-35.2			
C_5H_{10}	3-Methyl-1-butene					-51.5		253.3	156.1	-27.5			
C_5H_{10}	2-Methyl-2-butene					-68.6		251.0	152.8	-41.7			
C_5H_{10}	Cyclopentane					-105.1		204.5	128.8	-76.4			
C_5H_{10}	Methylcyclobutane					-44.5							
C_5H_{10}	Ethylcyclopropane					-24.8							
C_5H_{10}	1,1-Dimethylcyclopropane					-33.3				-8.2			
C_5H_{10}	*cis*-1,2-Dimethylcyclopropane					-26.3							
C_5H_{10}	*trans*-1,2-Dimethylcyclopropane					-30.7							
$C_5H_{10}Br_2$	2,3-Dibromo-2-methylbutane									-137.6			
$C_5H_{10}N_2O$	*N*-Nitrosopiperidine					-31.1				16.6			
$C_5H_{10}N_2O_2$	*N*-Nitropiperidine					-93.0				-44.5			
$C_5H_{10}N_2O_3$	*L*-Glutamine	-826.4											
$C_5H_{10}O$	Cyclopentanol					-300.1		204.1	182.5	-242.5		362.9	
$C_5H_{10}O$	Pentanal					-267.2				-228.4			
$C_5H_{10}O$	2-Pentanone					-297.3			184.1	-258.8			
$C_5H_{10}O$	3-Pentanone					-296.5		266.0	190.9	-257.9			
$C_5H_{10}O$	3-Methyl-2-butanone					-299.5		268.5	179.9	-262.6			
$C_5H_{10}O$	3,3-Dimethyloxetane					-182.2				-148.2			
$C_5H_{10}O$	Tetrahydropyran					-258.3				-223.4			
$C_5H_{10}OS$	S-Propyl thioacetate					-294.5				-250.4			
$C_5H_{10}O_2$	Pentanoic acid					-559.4		259.8	210.3	-491.9			
$C_5H_{10}O_2$	2-Methylbutanoic acid					-554.5							
$C_5H_{10}O_2$	3-Methylbutanoic acid					-561.6				-510.0			
$C_5H_{10}O_2$	2,2-Dimethylpropanoic acid	-564.5								-491.3			
$C_5H_{10}O_2$	Butyl formate								200.2				
$C_5H_{10}O_2$	Propyl acetate								196.2				
$C_5H_{10}O_2$	Isopropyl acetate					-518.9			199.4	-481.6			
$C_5H_{10}O_2$	Ethyl propanoate					-502.7				-463.4			
$C_5H_{10}O_2$	Methyl butanoate								198.2				
$C_5H_{10}O_2$	(Ethoxymethyl)oxirane					-296.5							
$C_5H_{10}O_2$	4-Methyl-1,3-dioxane					-416.1				-376.9			
$C_5H_{10}O_2$	*cis*-1,2-Cyclopentanediol	-485.0											
$C_5H_{10}O_2$	*trans*-1,2-Cyclopentanediol	-490.1											
$C_5H_{10}O_2$	Tetrahydrofurfuryl alcohol					-435.7				-369.1			
$C_5H_{10}O_3$	Diethyl carbonate					-681.5				-637.9			
$C_5H_{10}O_3$	Ethylene glycol monomethyl ether acetate								310.0				
$C_5H_{10}O_3$	Ethyl lactate								254.0				
$C_5H_{10}O_4$	Glycerol 1-acetate, (*DL*)					-909.2							
$C_5H_{10}O_5$	*D*-Ribose	-1047.2											
$C_5H_{10}O_5$	*D*-Xylose	-1057.8											
$C_5H_{10}O_5$	α-*D*-Arabinopyranose	-1057.9											
$C_5H_{10}S$	Thiacyclohexane					-106.3		218.2	163.3	-63.5	53.1	323.0	109.7
$C_5H_{10}S$	Cyclopentanethiol					-89.5		256.9	165.2	-48.1			
$C_5H_{11}Br$	1-Bromopentane					-170.2				-128.9			
$C_5H_{11}Cl$	1-Chloropentane					-213.2				-174.9			
$C_5H_{11}Cl$	1-Chloro-3-methylbutane					-216.0				-179.7			
$C_5H_{11}Cl$	2-Chloro-2-methylbutane					-235.7				-202.2			
$C_5H_{11}Cl$	2-Chloro-3-methylbutane					-226.6				-185.1			
$C_5H_{11}N$	Cyclopentylamine					-95.1		241.0	181.2	-54.9			
$C_5H_{11}N$	Piperidine					-86.4		210.0	179.9	-47.1			
$C_5H_{11}NO$	Pentanamide	-379.5								-290.2			
$C_5H_{11}NO$	2,2-Dimethylpropanamide	-399.7								-313.1			
$C_5H_{11}NO_2$	1-Nitropentane					-215.4				-164.4		390.9	137.1
$C_5H_{11}NO_2$	*DL*-Valine	-628.9											
$C_5H_{11}NO_2$	*L*-Valine	-617.9								-455.1			

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_5H_{11}NO_2$	5-Aminopentanoic acid	-604.1								-460.0			
$C_5H_{11}NO_2S$	*L*-Methionine	-577.5								-413.5			
$C_5H_{11}NO_4$	2-Ethyl-2-nitro-1,3-propanediol	-606.4											
C_5H_{12}	Pentane					-173.5			167.2	-146.9			
C_5H_{12}	Isopentane					-178.4		260.4	164.8	-153.6			
C_5H_{12}	Neopentane					-190.2				-168.0			
$C_5H_{12}N_2O$	Butylurea	-419.5											
$C_5H_{12}N_2O$	*tert*-Butylurea	-417.4											
$C_5H_{12}N_2O$	*N,N*-Diethylurea	-372.2											
$C_5H_{12}N_2O$	Tetramethylurea					-262.2							
$C_5H_{12}N_2S$	Tetramethylthiourea	-38.1								44.9			
$C_5H_{12}O$	1-Pentanol					-351.6			208.1	-294.6			
$C_5H_{12}O$	2-Pentanol					-365.2				-311.0			
$C_5H_{12}O$	3-Pentanol					-368.9			239.7	-314.9			
$C_5H_{12}O$	2-Methyl-1-butanol, (±)					-356.6				-301.4			
$C_5H_{12}O$	3-Methyl-1-butanol					-356.4				-300.7			
$C_5H_{12}O$	2-Methyl-2-butanol					-379.5			247.1	-329.3			
$C_5H_{12}O$	3-Methyl-2-butanol, (±)					-366.6				-313.5			
$C_5H_{12}O$	2,2-Dimethyl-1-propanol					-399.4							
$C_5H_{12}O$	Butyl methyl ether					-290.6		295.3	192.7	-258.1			
$C_5H_{12}O$	Methyl *tert*-butyl ether					-313.6		265.3	187.5	-283.7			
$C_5H_{12}O$	Ethyl propyl ether					-303.6		295.0	197.2	-272.0			
$C_5H_{12}O_2$	1,5-Pentanediol					-528.8				-450.8			
$C_5H_{12}O_2$	2,2-Dimethyl-1,3-propanediol	-551.2											
$C_5H_{12}O_2$	Diethoxymethane					-450.5				-414.7			
$C_5H_{12}O_2$	1,1-Dimethoxypropane					-443.6							
$C_5H_{12}O_2$	2,2-Dimethoxypropane					-459.4				-429.9			
$C_5H_{12}O_3$	Diethylene glycol monomethyl ether								271.1				
$C_5H_{12}O_3$	2-(Hydroxymethyl)-2-methyl-1,3-propanediol	-744.6											
$C_5H_{12}O_4$	Pentaerythritol	-920.6								-776.7			
$C_5H_{12}O_5$	Xylitol	-1118.5											
$C_5H_{12}S$	1-Pentanethiol					-151.3				-110.0			
$C_5H_{12}S$	2-Methyl-1-butanethiol, (+)					-154.4				-114.9			
$C_5H_{12}S$	3-Methyl-1-butanethiol					-154.4				-114.9			
$C_5H_{12}S$	2-Methyl-2-butanethiol					-162.8		290.1	198.1	-127.1			
$C_5H_{12}S$	3-Methyl-2-butanethiol					-158.8				-121.3			
$C_5H_{12}S$	2,2-Dimethyl-1-propanethiol					-165.4				-129.0			
$C_5H_{12}S$	Butyl methyl sulfide					-142.9		307.5	200.9	-102.4			
$C_5H_{12}S$	*tert*-Butyl methyl sulfide					-157.1		276.1	199.9	-121.3			
$C_5H_{12}S$	Ethyl propyl sulfide					-144.8		309.5	198.4	-104.8			
$C_5H_{12}S$	Ethyl isopropyl sulfide					-156.1				-118.3			
$C_5H_{13}N$	Pentylamine								218.0				
$C_5H_{14}N_2$	*N,N,N′,N′*-Tetramethylmethanediamine					-51.1				-18.2			
C_6ClF_5	Chloropentafluorobenzene	-858.4								-809.3			
C_6Cl_6	Hexachlorobenzene	-127.6		260.2	201.2					-35.5			
C_6F_6	Hexafluorobenzene					-991.3		280.8	221.6	-955.4			
C_6F_{10}	Perfluorocyclohexene					-1963.5				-1932.7			
C_6F_{12}	Perfluorocyclohexane					-2406.3				-2370.4			
C_6HCl_5O	Pentachlorophenol	-292.5		253.2	202.0								
C_6HF_5	Pentafluorobenzene	-852.7				-841.8				-806.5			
C_6HF_5O	Pentafluorophenol	-1024.1				-1007.7							
$C_6H_2F_4$	1,2,4,5-Tetrafluorobenzene					-683.8							
$C_6H_3Cl_3$	1,2,3-Trichlorobenzene	-70.8								3.8			
$C_6H_3Cl_3$	1,2,4-Trichlorobenzene					-63.1				-8.1			
$C_6H_3Cl_3$	1,3,5-Trichlorobenzene	-78.4								-13.4			
$C_6H_3N_3O_6$	1,3,5-Trinitrobenzene	-37.0			214.6								
$C_6H_3N_3O_7$	2,4,6-Trinitrophenol	-217.9			239.7								
$C_6H_3N_3O_8$	2,4,6-Trinitro-1,3-benzenediol	-467.5											
$C_6H_4ClNO_2$	1-Chloro-4-nitrobenzene	-48.7			250.2								
$C_6H_4Cl_2$	*o*-Dichlorobenzene					-17.5			162.4	30.2			
$C_6H_4Cl_2$	*m*-Dichlorobenzene					-20.7				25.7			
$C_6H_4Cl_2$	*p*-Dichlorobenzene	-42.3		175.4	147.8					22.5			
$C_6H_4Cl_2O$	2,4-Dichlorophenol	-226.4								-156.3			
$C_6H_4F_2$	*o*-Difluorobenzene					-330.0		222.6	159.0	-293.8			
$C_6H_4F_2$	*m*-Difluorobenzene					-343.9		223.8	159.1	-309.2			

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_6H_4F_2$	*p*-Difluorobenzene					-342.3			157.5	-306.7			
$C_6H_4N_2O_4$	1,2-Dinitrobenzene	-2.0			200.4								
$C_6H_4N_2O_4$	1,3-Dinitrobenzene	-27.0			197.5	-36.0							
$C_6H_4N_2O_4$	1,4-Dinitrobenzene	-38.0			200.0								
$C_6H_4N_2O_5$	2,4-Dinitrophenol	-232.7								-128.1			
$C_6H_4O_2$	*p*-Benzoquinone	-185.7			129.0					-122.9			
C_6H_5Br	Bromobenzene					60.9		219.2	154.3				
C_6H_5Cl	Chlorobenzene					11.1			150.1	52.0			
C_6H_5ClO	2-Chlorophenol								188.7				
C_6H_5ClO	3-Chlorophenol	-206.4				-189.3							
C_6H_5ClO	4-Chlorophenol	-197.7				-181.3							
$C_6H_5Cl_2N$	3,4-Dichloroaniline	-89.1											
C_6H_5F	Fluorobenzene					-150.6		205.9	146.4	-115.9			
C_6H_5I	Iodobenzene					117.2		205.4	158.7	164.9			
$C_6H_5NO_2$	Nitrobenzene					12.5			185.8	68.5		348.8	120.4
$C_6H_5NO_2$	3-Pyridinecarboxylic acid	-344.9								-221.5			
$C_6H_5NO_3$	2-Nitrophenol	-202.4											
$C_6H_5N_3$	1*H*-Benzotriazole	236.5								335.5			
$C_6H_5N_3O_4$	2,3-Dinitroaniline	-11.7											
$C_6H_5N_3O_4$	2,4-Dinitroaniline	-67.8											
$C_6H_5N_3O_4$	2,5-Dinitroaniline	-44.3											
$C_6H_5N_3O_4$	2,6-Dinitroaniline	-50.6											
$C_6H_5N_3O_4$	3,5-Dinitroaniline	-38.9											
C_6H_6	1,5-Hexadiyne					384.2							
C_6H_6	Benzene					49.1	124.5	173.4	136.0	82.9	129.7	269.2	82.4
C_6H_6ClN	2-Chloroaniline					-4.6							
C_6H_6ClN	3-Chloroaniline					-20.3			198.7				
C_6H_6ClN	4-Chloroaniline	-33.3			147.3								
$C_6H_6N_2O_2$	2-Nitroaniline	-26.1			166.0	-9.4				63.8			
$C_6H_6N_2O_2$	3-Nitroaniline	-38.3			158.8	-14.4				58.4			
$C_6H_6N_2O_2$	4-Nitroaniline	-42.0			167.0	-20.7				58.8			
C_6H_6O	Phenol	-165.1		144.0	127.4					-96.4			
C_6H_6O	2-Vinylfuran					-10.3				27.8			
$C_6H_6O_2$	*p*-Hydroquinone	-364.5			136.0					-265.3			
$C_6H_6O_2$	Pyrocatechol	-354.1								-267.5			
$C_6H_6O_2$	Resorcinol	-368.0								-274.7			
$C_6H_6O_3$	1,2,3-Benzenetriol	-551.1								-434.2			
$C_6H_6O_3$	1,2,4-Benzenetriol	-563.8								-444.0			
$C_6H_6O_3$	1,3,5-Benzenetriol	-584.6								-452.9			
$C_6H_6O_3$	3,4-Dimethyl-2,5-furandione	-581.4											
$C_6H_6O_6$	*cis*-1-Propene-1,2,3-tricarboxylic acid	-1224.4											
$C_6H_6O_6$	*trans*-1-Propene-1,2,3-tricarboxylic acid	-1232.7											
C_6H_6S	Benzenethiol					63.7		222.8	173.2	111.3			
C_6H_7N	Aniline					31.6			191.9	87.5	-7.0	317.9	107.9
C_6H_7N	2-Methylpyridine					56.7			158.6	99.2			
C_6H_7N	3-Methylpyridine					61.9		216.3	158.7	106.4			
C_6H_7N	4-Methylpyridine					59.2		209.1	159.0	103.8			
C_6H_7N	1-Cyclopentenecarbonitrile					111.5				156.5			
$C_6H_8N_2$	Adiponitrile					85.1			128.7	149.5			
$C_6H_8N_2$	1,2-Benzenediamine	-0.3											
$C_6H_8N_2$	1,3-Benzenediamine	-7.8		154.5	159.6								
$C_6H_8N_2$	1,4-Benzenediamine	3.0											
$C_6H_8N_2$	Phenylhydrazine					141.0			217.0	202.9			
$C_6H_8N_2S$	Bis(2-cyanoethyl) sulfide					96.3							
$C_6H_8O_4$	Dimethyl maleate								263.2				
$C_6H_8O_6$	*L*-Ascorbic acid	-1164.6											
$C_6H_8O_7$	Citric acid	-1543.8											
$C_6H_9Cl_3O_2$	Butyl trichloroacetate					-545.8				-492.3			
$C_6H_9Cl_3O_2$	Isobutyl trichloroacetate					-553.4				-500.2			
C_6H_9N	Cyclopentanecarbonitrile					0.7				44.1			
C_6H_9N	2,4-Dimethylpyrrole	-422.3											
C_6H_9N	2,5-Dimethylpyrrole					-16.7				39.8			
$C_6H_9NO_3$	Triacetamide					-610.5				-550.1			
$C_6H_9NO_6$	Nitrilotriacetic acid	-1311.9											
$C_6H_9N_3O_2$	*L*-Histidine	-466.7											

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
C_6H_{10}	1,5-Hexadiene					54.1				84.2			
C_6H_{10}	3,3-Dimethyl-1-butyne					78.4							
C_6H_{10}	Cyclohexene					-38.5		214.6	148.3	-5.0			
C_6H_{10}	1-Methylcyclopentene					-36.4				-3.8			
C_6H_{10}	3-Methylcyclopentene					-23.7				7.4			
C_6H_{10}	4-Methylcyclopentene					-17.6				14.6			
$C_6H_{10}Cl_2O_2$	Butyl dichloroacetate					-550.1				-497.8			
$C_6H_{10}O$	Cyclohexanone					-271.2			182.2	-226.1			
$C_6H_{10}O$	2-Methylcyclopentanone					-265.2							
$C_6H_{10}O$	Mesityl oxide								212.5				
$C_6H_{10}O_2$	Ethyl *trans*-2-butenoate					-420.0				-375.6			
$C_6H_{10}O_2$	Methyl cyclobutanecarboxylate					-395.0				-350.2			
$C_6H_{10}O_3$	Ethyl acetoacetate								248.0				
$C_6H_{10}O_3$	Propanoic anhydride					-679.1				-626.5			
$C_6H_{10}O_4$	Adipic acid	-994.3											
$C_6H_{10}O_4$	Diethyl oxalate					-805.5				-742.0			
$C_6H_{10}O_4$	Ethylene glycol diacetate								310.0				
$C_6H_{11}Cl$	Chlorocyclohexane					-207.2				-163.7			
$C_6H_{11}ClO_2$	Ethyl 4-chlorobutanoate					-566.5				-513.8			
$C_6H_{11}ClO_2$	Propyl 3-chloropropanoate					-537.6				-485.7			
$C_6H_{11}ClO_2$	Butyl chloroacetate					-538.4				-487.4			
$C_6H_{11}NO$	Caprolactam	-329.4			156.8					-239.6			
$C_6H_{11}NO$	1-Methyl-2-piperidinone					-293.0							
C_6H_{12}	1-Hexene					-74.2		295.2	183.3	-43.5			
C_6H_{12}	*cis*-2-Hexene					-83.9				-52.3			
C_6H_{12}	*trans*-2-Hexene					-85.5				-53.9			
C_6H_{12}	*cis*-3-Hexene					-78.9				-47.6			
C_6H_{12}	*trans*-3-Hexene					-86.1				-54.4			
C_6H_{12}	2-Methyl-1-pentene					-90.0				-59.4			
C_6H_{12}	3-Methyl-1-pentene					-78.2				-49.5			
C_6H_{12}	4-Methyl-1-pentene					-80.0				-51.3			
C_6H_{12}	2-Methyl-2-pentene					-98.5				-66.9			
C_6H_{12}	3-Methyl-*cis*-2-pentene					-94.5				-62.3			
C_6H_{12}	3-Methyl-*trans*-2-pentene					-94.6				-63.1			
C_6H_{12}	4-Methyl-*cis*-2-pentene					-87.0				-57.5			
C_6H_{12}	4-Methyl-*trans*-2-pentene					-91.6				-61.5			
C_6H_{12}	2-Ethyl-1-butene					-87.1				-56.0			
C_6H_{12}	2,3-Dimethyl-1-butene					-93.2				-62.4			
C_6H_{12}	3,3-Dimethyl-1-butene					-87.5				-60.3			
C_6H_{12}	2,3-Dimethyl-2-butene					-101.4		270.2	174.7	-68.1			
C_6H_{12}	Cyclohexane					-156.4			154.9	-123.4			
C_6H_{12}	Methylcyclopentane					-137.9				-106.2			
C_6H_{12}	Ethylcyclobutane					-59.0				-27.5			
C_6H_{12}	1,1,2-Trimethylcyclopropane					-96.2							
$C_6H_{12}N_2O_4S_2$	*L*-Cystine	-1032.7											
$C_6H_{12}N_2S_4$	Thiram	40.2			301.7								
$C_6H_{12}O$	Butyl vinyl ether					-218.8			232.0	-182.6			
$C_6H_{12}O$	Hexanal							280.3	210.4				
$C_6H_{12}O$	2-Hexanone					-322.0			213.3	-278.9			
$C_6H_{12}O$	3-Hexanone					-320.2		305.3	216.9	-277.6			
$C_6H_{12}O$	4-Methyl-2-pentanone								213.3				
$C_6H_{12}O$	2-Methyl-3-pentanone					-325.9				-286.0			
$C_6H_{12}O$	3,3-Dimethyl-2-butanone					-328.6				-290.6			
$C_6H_{12}O$	Cyclohexanol					-348.2			208.2	-286.2			
$C_6H_{12}O$	*cis*-2-Methylcyclopentanol					-345.5							
$C_6H_{12}O_2$	Hexanoic acid					-583.8				-511.9			
$C_6H_{12}O_2$	Butyl acetate					-529.2			227.8	-485.3			
$C_6H_{12}O_2$	*tert*-Butyl acetate					-554.5			231.0	-516.5			
$C_6H_{12}O_2$	Isobutyl acetate								233.8				
$C_6H_{12}O_2$	Ethyl butanoate								228.0				
$C_6H_{12}O_2$	Methyl pentanoate					-514.2			229.3	-471.1			
$C_6H_{12}O_2$	Methyl 2,2-dimethylpropanoate					-530.0			257.9	-491.2			
$C_6H_{12}O_2$	Diacetone alcohol								221.3				
$C_6H_{12}O_3$	Ethylene glycol monoethyl ether acetate								376.0				
$C_6H_{12}O_3$	Paraldehyde					-673.1				-631.7			

Molecular formula	Name	Crystal $\Delta_f H°$ kJ/mol	Crystal $\Delta_f G°$ kJ/mol	Crystal $S°$ J/mol K	Crystal C_p J/mol K	Liquid $\Delta_f H°$ kJ/mol	Liquid $\Delta_f G°$ kJ/mol	Liquid $S°$ J/mol K	Liquid C_p J/mol K	Gas $\Delta_f H°$ kJ/mol	Gas $\Delta_f G°$ kJ/mol	Gas $S°$ J/mol K	Gas C_p J/mol K
$C_6H_{12}O_6$	β-*D*-Fructose	-1265.6											
$C_6H_{12}O_6$	*D*-Galactose	-1286.3											
$C_6H_{12}O_6$	α-*D*-Glucose	-1273.3											
$C_6H_{12}O_6$	*D*-Mannose	-1263.0											
$C_6H_{12}O_6$	*L*-Sorbose	-1271.5											
$C_6H_{12}S$	Thiepane									-65.8	79.4	363.5	131.3
$C_6H_{12}S$	Cyclohexanethiol					-140.7		255.6	192.6	-96.2			
$C_6H_{12}S$	Cyclopentyl methyl sulfide					-109.8				-64.7			
$C_6H_{13}Br$	1-Bromohexane					-194.2		453.0	204.0	-148.3			
$C_6H_{13}Cl$	2-Chlorohexane					-246.1				-204.3			
$C_6H_{13}N$	Cyclohexylamine					-147.6				-104.0			
$C_6H_{13}N$	2-Methylpiperidine, (±)					-124.9				-84.4			
$C_6H_{13}NO$	Hexanamide	-423.0								-324.2			
$C_6H_{13}NO$	*N*-Butylacetamide					-380.9				-305.9			
$C_6H_{13}NO_2$	*DL*-Leucine	-640.6											
$C_6H_{13}NO_2$	*D*-Leucine	-637.3											
$C_6H_{13}NO_2$	*L*-Leucine	-637.4			200.1					-486.8			
$C_6H_{13}NO_2$	*DL*-Isoleucine	-635.3											
$C_6H_{13}NO_2$	*L*-Isoleucine	-637.8											
$C_6H_{13}NO_2$	*L*-Norleucine	-639.1											
$C_6H_{13}NO_2$	6-Aminohexanoic acid	-637.3											
C_6H_{14}	Hexane					-198.7			195.6	-166.9			
C_6H_{14}	2-Methylpentane					-204.6		290.6	193.7	-174.6			
C_6H_{14}	3-Methylpentane					-202.4		292.5	190.7	-171.9			
C_6H_{14}	2,2-Dimethylbutane					-213.8		272.5	191.9	-185.9			
C_6H_{14}	2,3-Dimethylbutane					-207.4		287.8	189.7	-178.1			
$C_6H_{14}N_2$	Azopropane					11.5				51.3			
$C_6H_{14}N_2O_2$	*DL*-Lysine	-678.7											
$C_6H_{14}N_4O_2$	*D*-Arginine	-623.5		250.6	232.0								
$C_6H_{14}O$	1-Hexanol					-377.5		287.4	240.4	-315.9			
$C_6H_{14}O$	2-Hexanol					-392.0				-333.5			
$C_6H_{14}O$	3-Hexanol					-392.4			286.2				
$C_6H_{14}O$	2-Methyl-1-pentanol								248.0				
$C_6H_{14}O$	3-Methyl-2-pentanol								275.9				
$C_6H_{14}O$	4-Methyl-2-pentanol					-394.7			273.0				
$C_6H_{14}O$	2-Methyl-3-pentanol					-396.4							
$C_6H_{14}O$	3-Methyl-3-pentanol								293.4				
$C_6H_{14}O$	Dipropyl ether					-328.8		323.9	221.6	-293.0			
$C_6H_{14}O$	Diisopropyl ether					-351.5			216.8	-319.2			
$C_6H_{14}O$	Butyl ethyl ether								159.0				
$C_6H_{14}O$	*tert*-Butyl ethyl ether									-313.9			
$C_6H_{14}OS$	Dipropyl sulfoxide					-329.4				-254.9			
$C_6H_{14}O_2$	1,2-Hexanediol					-577.1				-490.1			
$C_6H_{14}O_2$	1,6-Hexanediol	-569.9				-548.6				-461.2			
$C_6H_{14}O_2$	2-Methyl-2,4-pentanediol								336.0				
$C_6H_{14}O_2$	Ethylene glycol monobutyl ether								281.0				
$C_6H_{14}O_2$	1,1-Diethoxyethane					-491.4				-453.5			
$C_6H_{14}O_2$	Ethylene glycol diethyl ether					-451.4			259.4	-408.1			
$C_6H_{14}O_3$	Diethylene glycol monoethyl ether								301.0				
$C_6H_{14}O_3$	Diethylene glycol dimethyl ether								274.1				
$C_6H_{14}O_3$	Trimethylolpropane	-750.9											
$C_6H_{14}O_4$	Triethylene glycol					-804.3				-725.0			
$C_6H_{14}O_4S$	Dipropyl sulfate					-859.0				-792.0			
$C_6H_{14}O_6$	Galactitol					-1317.0							
$C_6H_{14}O_6$	*D*-Mannitol					-1314.5							
$C_6H_{14}S$	1-Hexanethiol					-175.7				-129.9			
$C_6H_{14}S$	2-Methyl-2-pentanethiol					-188.3				-148.3			
$C_6H_{14}S$	2,3-Dimethyl-2-butanethiol					-187.1				-147.9			
$C_6H_{14}S$	Diisopropyl sulfide					-181.6		313.0	232.0	-142.0			
$C_6H_{14}S$	Butyl ethyl sulfide					-172.3				-127.8			
$C_6H_{14}S$	Methyl pentyl sulfide					-167.1				-121.8			
$C_6H_{14}S_2$	Dipropyl disulfide					-171.5				-118.3			
$C_6H_{15}B$	Triethylborane					-194.6	9.4	336.7	241.2	-157.7	16.1	437.8	
$C_6H_{15}N$	Dipropylamine					-156.1				-116.0			
$C_6H_{15}N$	Diisopropylamine					-178.5				-143.8			
$C_6H_{15}N$	Triethylamine					-127.7			219.9	-92.7			

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_6H_{15}NO$	2-Diethylaminoethanol					-305.9							
$C_6H_{15}NO_3$	Triethanolamine	-664.2			389.0					-558.3			
$C_6H_{16}N_2$	1,6-Hexanediamine	-205.0											
$C_6H_{18}N_3OP$	Hexamethylphosphoric triamide								321.0				
$C_6H_{18}OSi_2$	Hexamethyldisiloxane					-815.0	-541.5	433.8	311.4	-777.7	-534.5	535.0	238.5
C_6MoO_6	Molybdenum hexacarbonyl	-982.8	-877.7	325.9	242.3					-912.1	-856.0	490.0	205.0
C_6N_4	Tetracyanoethene	623.8								705.0			
C_7F_8	Perfluorotoluene					-1311.1		355.5	262.3				
C_7F_{14}	Perfluoromethylcyclohexane					-2931.1			353.1	-2897.2			
C_7F_{16}	Perfluoroheptane					-3420.0		561.8	419.0	-3383.6			
$C_7H_3F_5$	2,3,4,5,6-Pentafluorotoluene					-883.8		306.4	225.8	-842.7			
$C_7H_4Cl_2O$	3-Chlorobenzoyl chloride					-189.7							
$C_7H_4N_2O_6$	3,5-Dinitrobenzoic acid	-409.8											
C_7H_5ClO	Benzoyl chloride					-158.0				-103.2			
$C_7H_5ClO_2$	2-Chlorobenzoic acid	-404.5								-325.0			
$C_7H_5ClO_2$	3-Chlorobenzoic acid	-424.3								-342.3			
$C_7H_5ClO_2$	4-Chlorobenzoic acid	-428.9			163.2					-341.0			
$C_7H_5F_3$	(Trifluoromethyl)benzene								188.4				
C_7H_5N	Benzonitrile					163.2		209.1	165.2	215.7			
C_7H_5NO	Benzoxazole	-24.2								44.8			
$C_7H_5NO_4$	2-Nitrobenzoic acid	-378.8											
$C_7H_5NO_4$	3-Nitrobenzoic acid	-394.7											
$C_7H_5NO_4$	4-Nitrobenzoic acid	-392.2											
$C_7H_5N_3O_6$	2,4,6-Trinitrotoluene	-63.2			243.3								
$C_7H_6N_2$	1*H*-Benzimidazole	79.5								181.7			
$C_7H_6N_2$	1*H*-Indazole	151.9								243.0			
$C_7H_6N_2O_4$	1-Methyl-2,4-dinitrobenzene	-66.4								33.2			
C_7H_6O	Benzaldehyde					-87.0		221.2	172.0	-36.7			
$C_7H_6O_2$	Benzoic acid	-385.2		167.6	146.8					-294.0			
$C_7H_6O_2$	Salicylaldehyde								222.0				
$C_7H_6O_2$	3-(2-Furanyl)-2-propenal	-182.0								-105.9			
$C_7H_6O_3$	2-Hydroxybenzoic acid	-589.9								-494.8			
C_7H_7Br	4-Bromotoluene					12.0							
C_7H_7Cl	2-Chlorotoluene								166.8				
C_7H_7Cl	(Chloromethyl)benzene					-32.5				18.9			
C_7H_7F	4-Fluorotoluene					-186.9			171.2	-147.4			
C_7H_7NO	Benzamide	-202.6								-100.9			
$C_7H_7NO_2$	Aniline-2-carboxylic acid	-401.1								-296.0			
$C_7H_7NO_2$	Aniline-3-carboxylic acid	-417.3								-283.6			
$C_7H_7NO_2$	Aniline-4-carboxylic acid	-410.0			177.8					-296.7			
$C_7H_7NO_2$	2-Nitrotoluene					-9.7							
$C_7H_7NO_2$	3-Nitrotoluene					-31.5							
$C_7H_7NO_2$	4-Nitrotoluene	-48.1			172.3					31.0			
$C_7H_7NO_2$	(Nitromethyl)benzene					-22.8				30.7			
$C_7H_7NO_2$	Salicylaldoxime	-183.7											
C_7H_8	Toluene					12.4			157.3	50.5			
$C_7H_8N_2O$	Phenylurea	-218.6											
C_7H_8O	*o*-Cresol	-204.6		165.4	154.6					-128.6			
C_7H_8O	*m*-Cresol					-194.0		212.6	224.9	-132.3			
C_7H_8O	*p*-Cresol	-199.3		167.3	150.2					-125.4			
C_7H_8O	Benzyl alcohol					-160.7		216.7	217.9	-100.4			
C_7H_8O	Anisole					-114.8				-67.9			
C_7H_9N	Benzylamine					34.2			207.2	94.4			
C_7H_9N	2-Methylaniline					-6.3				56.4	167.6	351.0	130.2
C_7H_9N	3-Methylaniline					-8.1				54.6	165.4	352.5	125.5
C_7H_9N	4-Methylaniline	-23.5								55.3	167.7	347.0	126.2
C_7H_9N	*N*-Methylaniline								207.1				
C_7H_9N	1-Cyclohexenecarbonitrile					48.1				101.6			
C_7H_9N	2,3-Dimethylpyridine					19.4		243.7	189.5	67.1			
C_7H_9N	2,4-Dimethylpyridine					16.1		248.5	184.8	63.6			
C_7H_9N	2,5-Dimethylpyridine					18.7		248.8	184.7	66.5			
C_7H_9N	2,6-Dimethylpyridine					12.7		244.2	185.2	58.1			
C_7H_9N	3,4-Dimethylpyridine					18.3		240.7	191.8	68.8			
C_7H_9N	3,5-Dimethylpyridine					22.5		241.7	184.5	72.0			
$C_7H_{10}O_2$	Ethyl 2-pentynoate					-301.8				-250.3			
$C_7H_{10}O_2$	Methyl 2-hexynoate					-242.7							

Molecular formula	Name	Crystal $\Delta_f H°$ kJ/mol	Crystal $\Delta_f G°$ kJ/mol	Crystal $S°$ J/mol K	Crystal C_p J/mol K	Liquid $\Delta_f H°$ kJ/mol	Liquid $\Delta_f G°$ kJ/mol	Liquid $S°$ J/mol K	Liquid C_p J/mol K	Gas $\Delta_f H°$ kJ/mol	Gas $\Delta_f G°$ kJ/mol	Gas $S°$ J/mol K	Gas C_p J/mol K
$C_7H_{11}Cl_3O_2$	Isopentyl trichloroacetate					-580.9				-523.1			
$C_7H_{11}N$	Cyclohexanecarbonitrile					-47.2				4.8			
C_7H_{12}	Bicyclo[2.2.1]heptane	-95.1			151.0					-54.8			
C_7H_{12}	1-Methylbicyclo(3,1,0)hexane					-33.2				1.7			
C_7H_{12}	Methylenecyclohexane					-61.3				-25.2			
C_7H_{12}	Vinylcyclopentane					-34.8							
C_7H_{12}	1-Ethylcyclopentene					-53.3				-19.8			
$C_7H_{12}O$	2-Methylenecyclohexanol					-277.6							
$C_7H_{12}O_2$	Butyl acrylate					-422.6			251.0	-375.3			
$C_7H_{12}O_4$	Diethyl malonate								285.0				
$C_7H_{13}ClO_2$	Butyl 2-chloropropanoate					-571.7				-517.3			
$C_7H_{13}ClO_2$	Isobutyl 2-chloropropanoate					-603.1				-549.6			
$C_7H_{13}ClO_2$	Butyl 3-chloropropanoate					-557.9				-502.3			
$C_7H_{13}ClO_2$	Isobutyl 3-chloropropanoate					-572.6				-517.3			
$C_7H_{13}ClO_2$	Propyl 2-chlorobutanoate					-630.7				-578.4			
$C_7H_{13}N$	Heptanenitrile					-82.8				-31.0			
C_7H_{14}	1-Heptene					-97.9		327.6	211.8	-62.3			
C_7H_{14}	*cis*-2-Heptene					-105.1							
C_7H_{14}	*trans*-2-Heptene					-109.5							
C_7H_{14}	*cis*-3-Heptene					-104.3							
C_7H_{14}	*trans*-3-Heptene					-109.3							
C_7H_{14}	5-Methyl-1-hexene					-100.0				-65.7			
C_7H_{14}	*cis*-3-Methyl-3-hexene					-115.9				-79.4			
C_7H_{14}	*trans*-3-Methyl-3-hexene					-112.7				-76.8			
C_7H_{14}	2,4-Dimethyl-1-pentene					-117.0				-83.8			
C_7H_{14}	4,4-Dimethyl-1-pentene					-110.6				-81.6			
C_7H_{14}	2,4-Dimethyl-2-pentene					-123.1				-88.7			
C_7H_{14}	*cis*-4,4-Dimethyl-2-pentene					-105.3				-72.6			
C_7H_{14}	*trans*-4,4-Dimethyl-2-pentene					-121.7				-88.8			
C_7H_{14}	2-Ethyl-3-methyl-1-butene					-114.1				-79.5			
C_7H_{14}	2,3,3-Trimethyl-1-butene					-117.7				-85.5			
C_7H_{14}	Cycloheptane					-156.6				-118.1			
C_7H_{14}	Methylcyclohexane					-190.1			184.8	-154.7			
C_7H_{14}	Ethylcyclopentane					-163.4		279.9		-126.9			
C_7H_{14}	1,1-Dimethylcyclopentane					-172.1				-138.2			
C_7H_{14}	*cis*-1,2-Dimethylcyclopentane					-165.3		269.2		-129.5			
C_7H_{14}	*trans*-1,2-Dimethylcyclopentane					-171.2				-136.6			
C_7H_{14}	*cis*-1,3-Dimethylcyclopentane					-170.1				-135.8			
C_7H_{14}	*trans*-1,3-Dimethylcyclopentane					-168.1				-133.6			
C_7H_{14}	1,1,2,2-Tetramethylcyclopropane					-119.8							
$C_7H_{14}Br_2$	1,2-Dibromoheptane					-212.3				-157.9			
$C_7H_{14}O$	1-Heptanal					-311.5		335.4	230.1	-263.8			
$C_7H_{14}O$	2-Heptanone								232.6				
$C_7H_{14}O$	3-Heptanone									-297.1			
$C_7H_{14}O$	4-Heptanone									-298.3			
$C_7H_{14}O$	2,2-Dimethyl-3-pentanone					-356.1				-313.6			
$C_7H_{14}O$	2,4-Dimethyl-3-pentanone					-352.9		318.0	233.7	-311.3			
$C_7H_{14}O$	*cis*-2-Methylcyclohexanol					-390.2				-327.0			
$C_7H_{14}O$	*trans*-2-Methylcyclohexanol, (±)					-415.7				-352.5			
$C_7H_{14}O$	*cis*-3-Methylcyclohexanol, (±)					-416.1				-350.9			
$C_7H_{14}O$	*trans*-3-Methylcyclohexanol, (±)					-394.4				-329.1			
$C_7H_{14}O$	*cis*-4-Methylcyclohexanol					-413.2				-347.5			
$C_7H_{14}O$	*trans*-4-Methylcyclohexanol					-433.3				-367.2			
$C_7H_{14}O_2$	Heptanoic acid					-610.2			265.4	-536.2			
$C_7H_{14}O_2$	Pentyl acetate								261.0				
$C_7H_{14}O_2$	Isopentyl acetate								248.5				
$C_7H_{14}O_2$	Ethyl pentanoate					-553.0				-505.9			
$C_7H_{14}O_2$	Ethyl 3-methylbutanoate					-571.0				-527.0			
$C_7H_{14}O_2$	Ethyl 2,2-dimethylpropanoate					-577.2				-536.0			
$C_7H_{14}O_2$	Methyl hexanoate					-540.2				-492.2			
$C_7H_{14}O_6$	α-Methylglucoside	-1233.3											
$C_7H_{15}Br$	1-Bromoheptane					-218.4				-167.8			
C_7H_{16}	Heptane					-224.2			224.7	-187.6			
C_7H_{16}	2-Methylhexane					-229.5		323.3	222.9	-194.5			
C_7H_{16}	3-Methylhexane					-226.4				-191.3			
C_7H_{16}	3-Ethylpentane					-224.9		314.5	219.6	-189.5			

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
C_7H_{16}	2,2-Dimethylpentane					-238.3		300.3	221.1	-205.7			
C_7H_{16}	2,3-Dimethylpentane					-233.1				-198.7			
C_7H_{16}	2,4-Dimethylpentane					-234.6		303.2	224.2	-201.6			
C_7H_{16}	3,3-Dimethylpentane					-234.2				-201.0			
C_7H_{16}	2,2,3-Trimethylbutane					-236.5		292.2	213.5	-204.4			
$C_7H_{16}O$	1-Heptanol					-403.3			272.1	-336.5			
$C_7H_{16}O$	*tert*-Butyl isopropyl ether					-392.8				-358.1			
$C_7H_{16}O_2$	1,7-Heptanediol					-574.2							
$C_7H_{16}O_2$	2,2-Diethoxypropane					-538.9				-506.9			
$C_7H_{16}S$	1-Heptanethiol					-200.5				-149.9			
$C_8H_4O_3$	Phthalic anhydride	-460.1		180.0	160.0					-371.4			
$C_8H_5NO_2$	1*H*-Indole-2,3-dione	-268.2											
$C_8H_6O_4$	Phthalic acid	-782.0		207.9	188.1								
$C_8H_6O_4$	Isophthalic acid	-803.0								-696.3			
$C_8H_6O_4$	Terephthalic acid	-816.1								-717.9			
C_8H_6S	Benzo[b]thiophene	100.6								166.3			
C_8H_7N	1*H*-Indole	86.6								156.5			
C_8H_8	Styrene					103.8			182.0	147.9			
C_8H_8O	Phenyl vinyl ether					-26.2				22.7			
C_8H_8O	Acetophenone					-142.5				-86.7			
$C_8H_8O_2$	*o*-Toluic acid	-416.5			174.9								
$C_8H_8O_2$	*m*-Toluic acid	-426.1			163.6								
$C_8H_8O_2$	*p*-Toluic acid	-429.2			169.0								
$C_8H_8O_2$	Methyl benzoate					-343.5			221.3	-287.9			
$C_8H_8O_3$	Methyl salicylate								249.0				
C_8H_9NO	Acetanilide	-209.4			179.3								
C_8H_{10}	1,7-Octadiyne					334.4							
C_8H_{10}	Ethylbenzene					-12.3			183.2	29.9			
C_8H_{10}	*o*-Xylene					-24.4			186.1	19.1			
C_8H_{10}	*m*-Xylene					-25.4			183.0	17.3			
C_8H_{10}	*p*-Xylene					-24.4			181.5	18.0			
$C_8H_{10}O$	2-Ethylphenol					-208.8				-145.2			
$C_8H_{10}O$	3-Ethylphenol					-214.3				-146.1			
$C_8H_{10}O$	4-Ethylphenol	-224.4			206.9					-144.1			
$C_8H_{10}O$	2,3-Xylenol	-241.1								-157.2			
$C_8H_{10}O$	2,4-Xylenol					-228.7				-163.8			
$C_8H_{10}O$	2,5-Xylenol	-246.6								-161.6			
$C_8H_{10}O$	2,6-Xylenol	-237.4								-162.1			
$C_8H_{10}O$	3,4-Xylenol	-242.3								-157.3			
$C_8H_{10}O$	3,5-Xylenol	-244.4								-162.4			
$C_8H_{10}O$	Benzeneethanol								252.6				
$C_8H_{10}O$	Ethoxybenzene					-152.6			228.5	-101.6			
$C_8H_{10}O_2$	1,2-Dimethoxybenzene					-290.3				-223.3			
$C_8H_{11}N$	*N*-Ethylaniline					8.2				56.3			
$C_8H_{11}N$	*N,N*-Dimethylaniline					46.0				100.5			
$C_8H_{11}N$	2,4-Dimethylaniline					-39.2							
$C_8H_{11}N$	2,5-Dimethylaniline					-38.9							
$C_8H_{11}N$	2,6-Dimethylaniline								238.9				
C_8H_{12}	1-Octen-3-yne					140.7							
C_8H_{12}	*cis*-1,2-Divinylcyclobutane					124.3				166.5			
C_8H_{12}	*trans*-1,2-Divinylcyclobutane					101.3				143.5			
$C_8H_{12}N_4$	2,2'-Azobis[isobutyronitrile]	246.0			237.6								
$C_8H_{12}O_2$	2,2,4,4-Tetramethyl-1,3-cyclobutanedione	-379.9								-307.6			
C_8H_{14}	Ethylidenecyclohexane					-103.5				-59.5			
C_8H_{14}	Allylcyclopentane					-64.5				-24.1			
$C_8H_{14}ClN_5$	Atrazine	-125.4											
$C_8H_{14}O_3$	Butanoic anhydride								283.7				
$C_8H_{15}ClO_2$	3-Methylbutyl 2-chloropropanoate					-627.3				-575.0			
$C_8H_{15}ClO_2$	3-Methylbutyl 3-chloropropanoate					-593.4				-539.4			
$C_8H_{15}N$	Octanenitrile					-107.3				-50.5			
C_8H_{16}	1-Octene					-124.5			241.0	-81.3			
C_8H_{16}	*cis*-2-Octene					-135.7			239.0				
C_8H_{16}	*trans*-2-Octene					-135.7			239.0				
C_8H_{16}	*cis*-2,2-Dimethyl-3-hexene					-126.4				-89.3			
C_8H_{16}	*trans*-2,2-Dimethyl-3-hexene					-144.9				-107.7			

Molecular formula	Name	Crystal				Liquid				Gas			
		$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
C_8H_{16}	3-Ethyl-2-methyl-1-pentene					-137.9				-100.3			
C_8H_{16}	2,4,4-Trimethyl-1-pentene					-145.9				-110.5			
C_8H_{16}	2,4,4-Trimethyl-2-pentene					-142.4				-104.9			
C_8H_{16}	Cyclooctane					-167.7				-124.4			
C_8H_{16}	Ethylcyclohexane					-212.1		280.9	211.8	-171.5			
C_8H_{16}	1,1-Dimethylcyclohexane					-218.7		267.2	209.2	-180.9			
C_8H_{16}	*cis*-1,2-Dimethylcyclohexane					-211.8		274.1	210.2	-172.1			
C_8H_{16}	*trans*-1,2-Dimethylcyclohexane					-218.2		273.2	209.4	-179.9			
C_8H_{16}	*cis*-1,3-Dimethylcyclohexane					-222.9		272.6	209.4	-184.6			
C_8H_{16}	*trans*-1,3-Dimethylcyclohexane					-215.7		276.3	212.8	-176.5			
C_8H_{16}	*cis*-1,4-Dimethylcyclohexane					-215.6		271.1	212.1	-176.6			
C_8H_{16}	*trans*-1,4-Dimethylcyclohexane					-222.4		268.0	210.2	-184.5			
C_8H_{16}	Propylcyclopentane					-188.8		310.8	216.3	-147.7			
C_8H_{16}	1-Ethyl-1-methylcyclopentane					-193.8							
C_8H_{16}	*cis*-1-Ethyl-2-methylcyclopentane					-190.8							
C_8H_{16}	*trans*-1-Ethyl-2-methylcyclopentane					-195.1				-156.2			
C_8H_{16}	*cis*-1-Ethyl-3-methylcyclopentane					-194.4							
C_8H_{16}	*trans*-1-Ethyl-3-methylcyclopentane					-196.0							
$C_8H_{16}O$	Octanal									-291.9		365.4	
$C_8H_{16}O$	2-Ethylhexanal					-348.5				-299.6			
$C_8H_{16}O$	2-Octanone								273.3				
$C_8H_{16}O$	2,2,4-Trimethyl-3-pentanone					-381.6				-338.3			
$C_8H_{16}O_2$	Octanoic acid					-636.0			297.9	-554.3			
$C_8H_{16}O_2$	2-Ethylhexanoic acid					-635.1				-559.5			
$C_8H_{16}O_2$	Hexyl acetate								282.8				
$C_8H_{16}O_2$	Isobutyl isobutanoate					-587.4				-542.9			
$C_8H_{16}O_2$	Propyl pentanoate					-583.0				-533.6			
$C_8H_{16}O_2$	Isopropyl pentanoate					-592.2				-544.9			
$C_8H_{16}O_2$	Methyl heptanoate					-567.1			285.1	-515.5			
$C_8H_{17}Br$	1-Bromooctane					-245.1				-189.3			
$C_8H_{17}Cl$	1-Chlorooctane					-291.3				-238.9			
$C_8H_{17}NO$	Octanamide	-473.2								-362.7			
C_8H_{18}	Octane					-250.1			254.6	-208.5			
C_8H_{18}	2-Methylheptane					-255.0		356.4	252.0	-215.3			
C_8H_{18}	3-Methylheptane, (*S*)					-252.3		362.6	250.2	-212.5			
C_8H_{18}	4-Methylheptane					-251.6			251.1	-211.9			
C_8H_{18}	3-Ethylhexane					-250.4				-210.7			
C_8H_{18}	2,2-Dimethylhexane					-261.9				-224.5			
C_8H_{18}	2,3-Dimethylhexane					-252.6				-213.8			
C_8H_{18}	2,4-Dimethylhexane					-257.0				-219.2			
C_8H_{18}	2,5-Dimethylhexane					-260.4			249.2	-222.5			
C_8H_{18}	3,3-Dimethylhexane					-257.5			246.6	-219.9			
C_8H_{18}	3,4-Dimethylhexane					-251.8				-212.8			
C_8H_{18}	3-Ethyl-2-methylpentane					-249.6				-211.0			
C_8H_{18}	3-Ethyl-3-methylpentane					-252.8				-214.8			
C_8H_{18}	2,2,3-Trimethylpentane					-256.9				-220.0			
C_8H_{18}	2,2,4-Trimethylpentane					-259.2			239.1	-224.0			
C_8H_{18}	2,3,3-Trimethylpentane					-253.5			245.6	-216.3			
C_8H_{18}	2,3,4-Trimethylpentane					-255.0		329.3	247.3	-217.3			
C_8H_{18}	2,2,3,3-Tetramethylbutane	-269.0		273.7	239.2					-226.0			
$C_8H_{18}N_2$	Azobutane					-40.1				9.2			
$C_8H_{18}O$	1-Octanol					-426.5			305.2	-355.6			
$C_8H_{18}O$	2-Octanol								330.1				
$C_8H_{18}O$	2-Ethyl-1-hexanol					-432.8		347.0	317.5	-365.3			
$C_8H_{18}O$	Dibutyl ether					-377.9			278.2	-332.8			
$C_8H_{18}O$	Di-*sec*-butyl ether					-401.5				-360.6			
$C_8H_{18}O$	Di-*tert*-butyl ether					-399.6			276.1	-362.0			
$C_8H_{18}O$	*tert*-Butyl isobutyl ether					-409.1				-369.0			
$C_8H_{18}O_2$	1,8-Octanediol	-626.6											
$C_8H_{18}O_2$	2,5-Dimethyl-2,5-hexanediol	-681.7											
$C_8H_{18}O_3$	Diethylene glycol monobutyl ether								354.9				
$C_8H_{18}O_3$	Diethylene glycol diethyl ether								341.4				
$C_8H_{18}O_3S$	Dibutyl sulfite					-693.1				-625.3			
$C_8H_{18}O_5$	Tetraethylene glycol					-981.7			428.8	-883.0			
$C_8H_{18}S$	Dibutyl sulfide					-220.7		405.1	284.3	-167.7			
$C_8H_{18}S$	Di-*sec*-butyl sulfide					-220.7				-167.7			

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_8H_{18}S$	Di-*tert*-butyl sulfide					-232.6				-188.8			
$C_8H_{18}S$	Diisobutyl sulfide					-229.2				-180.5			
$C_8H_{18}S_2$	Dibutyl disulfide					-222.9				-160.6			
$C_8H_{18}S_2$	Di-*tert*-butyl disulfide					-255.2				-201.0			
$C_8H_{19}N$	Dibutylamine					-206.0			292.9	-156.6			
$C_8H_{19}N$	Diisobutylamine					-218.5				-179.2			
$C_8H_{20}BrN$	Tetraethylammonium bromide	-342.7											
$C_8H_{20}O_4Si$	Ethyl silicate							533.1	364.4				
$C_8H_{20}Pb$	Tetraethyl lead					52.7		464.6	307.4	109.6			
$C_8H_{20}Si$	Tetraethylsilane								298.1				
$C_9H_6N_2O_2$	Toluene-2,4-diisocyanate								287.8				
C_9H_7N	Quinoline					141.2				200.5			
C_9H_7N	Isoquinoline					144.3		216.0	196.2	204.6			
C_9H_7NO	2-Quinolinol	-144.9								-25.5			
C_9H_7NO	8-Quinolinol	82.1											
C_9H_8	Indene					110.6		215.3	186.9	163.4			
$C_9H_8O_4$	2-(Acetyloxy)benzoic acid	-815.6											
C_9H_{10}	Cyclopropylbenzene					100.3				150.5			
C_9H_{10}	Indan					11.5		56.0	190.2	60.3			
$C_9H_{10}Cl_2N_2O$	Diuron	-329.0											
$C_9H_{10}N_2$	2,2'-Dipyrrolylmethane	126.2											
$C_9H_{10}O_2$	Ethyl benzoate								246.0				
$C_9H_{10}O_2$	Benzyl acetate								148.5				
$C_9H_{11}NO_2$	*L*-Phenylalanine	-466.9		213.6	203.0					-312.9			
$C_9H_{11}NO_3$	*L*-Tyrosine	-685.1		214.0	216.4								
C_9H_{12}	Propylbenzene					-38.3		287.8	214.7	7.9			
C_9H_{12}	Isopropylbenzene					-41.1			210.7	4.0			
C_9H_{12}	2-Ethyltoluene					-46.4				1.3			
C_9H_{12}	3-Ethyltoluene					-48.7				-1.8			
C_9H_{12}	4-Ethyltoluene					-49.8				-3.2			
C_9H_{12}	1,2,3-Trimethylbenzene					-58.5		267.9	216.4	-9.5			
C_9H_{12}	1,2,4-Trimethylbenzene					-61.8			215.0	-13.8			
C_9H_{12}	1,3,5-Trimethylbenzene					-63.4			209.3	-15.9			
$C_9H_{12}O$	2-Isopropylphenol					-233.7				-182.2			
$C_9H_{12}O$	3-Isopropylphenol					-252.5				-196.0			
$C_9H_{12}O$	4-Isopropylphenol	-270.0								-175.3			
$C_9H_{12}O_2$	Isopropylbenzene hydroperoxide					-148.3				-78.4			
$C_9H_{13}NO_2$	Ethyl 3,5-dimethylpyrrole-2-carboxylate	-474.5											
$C_9H_{13}NO_2$	Ethyl 2,4-dimethylpyrrole-3-carboxylate	-463.2											
$C_9H_{13}NO_2$	Ethyl 2,5-dimethylpyrrole-3-carboxylate	-478.7											
$C_9H_{13}NO_2$	Ethyl 4,5-dimethylpyrrole-3-carboxylate	-470.3											
$C_9H_{14}O$	Isophorone								253.5				
$C_9H_{14}O_6$	Triacetin					-1330.8		458.3	384.7	-1245.0			
$C_9H_{15}N$	3-Ethyl-2,4,5-trimethylpyrrole	-89.2											
C_9H_{16}	1-Nonyne					16.3				62.3			
$C_9H_{16}O_4$	Nonanedioic acid	-1054.3											
$C_9H_{17}NO$	2,2,6,6-Tetramethyl-4-piperidinone	-334.2								-273.4			
C_9H_{18}	Propylcyclohexane					-237.4		311.9	242.0	-192.3			
C_9H_{18}	1α,3α,5β-1,3,5-Trimethylcyclohexane									-212.1			
$C_9H_{18}O$	2-Nonanone					-397.2				-340.7			
$C_9H_{18}O$	5-Nonanone					-398.2		401.4	303.6	-344.9			
$C_9H_{18}O$	2,6-Dimethyl-4-heptanone					-408.5			297.3	-357.6			
$C_9H_{18}O_2$	Nonanoic acid					-659.7			362.4	-577.3			
$C_9H_{18}O_2$	Butyl pentanoate					-613.3				-560.2			
$C_9H_{18}O_2$	*sec*-Butyl pentanoate					-624.2				-573.2			
$C_9H_{18}O_2$	Isobutyl pentanoate					-620.0				-568.6			
$C_9H_{18}O_2$	Methyl octanoate					-590.3				-533.9			
$C_9H_{19}N$	*N*-Butylpiperidine					-171.8							
$C_9H_{19}N$	2,2,6,6-Tetramethylpiperidine					-206.9				-159.9			
C_9H_{20}	Nonane					-274.7			284.4	-228.2			
C_9H_{20}	2,2-Dimethylheptane					-288.1							
C_9H_{20}	2,2,3-Trimethylhexane					-282.7							

Molecular formula	Name	Crystal				Liquid				Gas			
		$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
C_9H_{20}	2,2,4-Trimethylhexane					-282.8							
C_9H_{20}	2,2,5-Trimethylhexane					-293.3							
C_9H_{20}	2,3,3-Trimethylhexane					-281.1							
C_9H_{20}	2,3,5-Trimethylhexane					-284.0				-242.6			
C_9H_{20}	2,4,4-Trimethylhexane					-280.2							
C_9H_{20}	3,3,4-Trimethylhexane					-277.5							
C_9H_{20}	3,3-Diethylpentane					-275.4			278.2	-233.3			
C_9H_{20}	3-Ethyl-2,2-dimethylpentane					-272.7							
C_9H_{20}	3-Ethyl-2,4-dimethylpentane					-269.7							
C_9H_{20}	2,2,3,3-Tetramethylpentane					-278.3			271.5	-237.1			
C_9H_{20}	2,2,3,4-Tetramethylpentane					-277.7				-236.9			
C_9H_{20}	2,2,4,4-Tetramethylpentane					-280.0			266.3	-241.6			
C_9H_{20}	2,3,3,4-Tetramethylpentane					-277.9				-236.1			
$C_9H_{20}N_2O$	Tetraethylurea					-380.0				-316.4			
$C_9H_{20}O$	1-Nonanol					-453.4				-376.5			
$C_9H_{20}O_2$	1,9-Nonanediol	-657.6											
$C_9H_{21}N$	Tripropylamine					-207.1				-161.0			
$C_{10}H_6N_2$	2-Quinolinecarbonitrile	246.5											
$C_{10}H_6N_2$	3-Quinolinecarbonitrile	242.3											
$C_{10}H_6N_2O_4$	1,5-Dinitronaphthalene	29.8											
$C_{10}H_6N_2O_4$	1,8-Dinitronaphthalene	39.7											
$C_{10}H_7Cl$	1-Chloronaphthalene					54.6			212.6	119.8			
$C_{10}H_7Cl$	2-Chloronaphthalene	55.4								137.4			
$C_{10}H_7I$	1-Iodonaphthalene					161.5				233.8			
$C_{10}H_7I$	2-Iodonaphthalene	144.3								235.1			
$C_{10}H_7NO_2$	1-Nitronaphthalene	42.6								111.2			
$C_{10}H_8$	Naphthalene	78.5	201.6	167.4	165.7					150.6	224.1	333.1	131.9
$C_{10}H_8$	Azulene	212.3								289.1			
$C_{10}H_8O$	1-Naphthol	-121.5			166.9					-30.4			149.4
$C_{10}H_8O$	2-Naphthol	-124.1		179.0	172.8					-29.9		366.6	147.8
$C_{10}H_9N$	1-Naphthylamine	67.8								132.8			
$C_{10}H_9N$	2-Naphthylamine	60.2								134.3			
$C_{10}H_{10}$	1,2-Dihydronaphthalene					71.6							
$C_{10}H_{10}$	1,4-Dihydronaphthalene					84.2							
$C_{10}H_{10}O$	1-Tetralone	-209.6											
$C_{10}H_{10}O_4$	Dimethyl phthalate								303.1				
$C_{10}H_{10}O_4$	Dimethyl isophthalate	-730.9											
$C_{10}H_{10}O_4$	Dimethyl terephthalate	-732.6			261.1								
$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene					-29.2			217.5	26.0			
$C_{10}H_{14}$	Butylbenzene					-63.2		321.2	243.4	-11.8			
$C_{10}H_{14}$	*sec*-Butylbenzene, (±)					-66.4				-18.4			
$C_{10}H_{14}$	*tert*-Butylbenzene					-71.9				-23.0			
$C_{10}H_{14}$	Isobutylbenzene					-69.8				-21.9			
$C_{10}H_{14}$	1-Isopropyl-2-methylbenzene					-73.3							
$C_{10}H_{14}$	1-Isopropyl-3-methylbenzene					-78.6							
$C_{10}H_{14}$	1-Isopropyl-4-methylbenzene					-78.0			236.4				
$C_{10}H_{14}$	*o*-Diethylbenzene					-68.5							
$C_{10}H_{14}$	*m*-Diethylbenzene					-73.5							
$C_{10}H_{14}$	*p*-Diethylbenzene					-72.8							
$C_{10}H_{14}$	3-Ethyl-1,2-dimethylbenzene					-80.5							
$C_{10}H_{14}$	4-Ethyl-1,2-dimethylbenzene					-86.0							
$C_{10}H_{14}$	2-Ethyl-1,3-dimethylbenzene					-80.1							
$C_{10}H_{14}$	2-Ethyl-1,4-dimethylbenzene					-84.8							
$C_{10}H_{14}$	1-Ethyl-2,4-dimethylbenzene					-84.1							
$C_{10}H_{14}$	1-Ethyl-3,5-dimethylbenzene					-87.8							
$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	-119.9		245.6	215.1								
$C_{10}H_{14}O$	Thymol	-309.7								-218.5			
$C_{10}H_{16}$	Dipentene					-50.8			249.4	-2.6			
$C_{10}H_{16}$	*d*-Limonene					-54.5			249.0				
$C_{10}H_{16}$	α-Pinene					-16.4				28.3			
$C_{10}H_{16}$	β-Pinene					-7.7				38.7			
$C_{10}H_{16}$	α-Terpinene									-20.6			
$C_{10}H_{16}$	β-Myrcene					14.5							
$C_{10}H_{16}$	*cis*, *cis*-2,6-Dimethyl-2,4,6-octatriene					-24.0							
$C_{10}H_{16}N_2O_8$	Ethylenediaminetetraacetic acid	-1759.5											

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_{10}H_{16}O$	Camphor, (±)	-319.4			271.2					-267.5			
$C_{10}H_{18}$	1,1'-Bicyclopentyl					-178.9							
$C_{10}H_{18}$	*cis*-Decahydronaphthalene					-219.4		265.0	232.0	-169.2			
$C_{10}H_{18}$	*trans*-Decahydronaphthalene					-230.6		264.9	228.5	-182.1			
$C_{10}H_{18}O_4$	Sebacic acid	-1082.6								-921.9			
$C_{10}H_{19}N$	Decanenitrile					-158.4				-91.5			
$C_{10}H_{20}$	1-Decene					-173.8		425.0	300.8	-123.3			
$C_{10}H_{20}$	*cis*-1,2-Di-*tert*-butylethene					-163.6							
$C_{10}H_{20}$	Butylcyclohexane					-263.1		345.0	271.0	-213.7			
$C_{10}H_{20}O_2$	Decanoic acid	-713.7				-684.3				-594.9			
$C_{10}H_{20}O_2$	Methyl nonanoate					-616.2				-554.2			
$C_{10}H_{21}NO_2$	1-Nitrodecane					-351.5							
$C_{10}H_{22}$	Decane					-300.9			314.4	-249.5			
$C_{10}H_{22}$	2-Methylnonane					-309.8		420.1	313.3	-260.2			
$C_{10}H_{22}$	5-Methylnonane					-307.9		423.8	314.4	-258.6			
$C_{10}H_{22}O$	1-Decanol					-478.1			370.6	-396.6			
$C_{10}H_{22}O$	Dipentyl ether								250.0				
$C_{10}H_{22}O$	Diisopentyl ether								379.0				
$C_{10}H_{22}O_2$	1,10-Decanediol	-678.9											
$C_{10}H_{22}O_2$	Ethylene glycol dibutyl ether								350.0				
$C_{10}H_{22}S$	1-Decanethiol	-309.9				-276.5		476.1	350.4	-211.5			
$C_{10}H_{22}S$	Dipentyl sulfide					-266.4				-204.9			
$C_{10}H_{22}S$	Diisopentyl sulfide					-281.8				-221.5			
$C_{10}H_{23}N$	Octyldimethylamine					-232.8							
$C_{11}H_8O_2$	1-Naphthalenecarboxylic acid	-333.5								-223.1			
$C_{11}H_8O_2$	2-Naphthalenecarboxylic acid	-346.1								-232.5			
$C_{11}H_{10}$	1-Methylnaphthalene					56.3		254.8	224.4				
$C_{11}H_{10}$	2-Methylnaphthalene	44.9		220.0	196.0					106.7			
$C_{11}H_{12}N_2O_2$	*L*-Tryptophan	-415.3		251.0	238.1								
$C_{11}H_{14}$	1,1-Dimethylindan					-53.6				-1.6			
$C_{11}H_{16}$	1-*tert*-Butyl-3-methylbenzene					-109.7							
$C_{11}H_{16}$	1-*tert*-Butyl-4-methylbenzene					-109.7				-57.0			
$C_{11}H_{16}$	Pentamethylbenzene	-144.6								-67.2			
$C_{11}H_{20}$	Spiro[5.5]undecane					-244.5				-188.3			
$C_{11}H_{22}$	1-Undecene								344.9				
$C_{11}H_{22}O_2$	Methyl decanoate					-640.5				-573.8			
$C_{11}H_{24}$	Undecane					-327.2			344.9	-270.8			
$C_{11}H_{24}O$	1-Undecanol					-504.8							
$C_{12}F_{27}N$	Tris(perfluorobutyl)amine								418.4				
$C_{12}H_8$	Acenaphthylene	186.7			166.4					259.7			
$C_{12}H_8N_2$	Phenazine	237.0								328.8			
$C_{12}H_8O$	Dibenzofuran	-5.3								83.4			
$C_{12}H_8S$	Dibenzothiophene	120.0								205.1			
$C_{12}H_8S_2$	Thianthrene	182.0								286.0			
$C_{12}H_9N$	Carbazole	101.7								200.7			
$C_{12}H_{10}$	Acenaphthene	70.3		188.9	190.4					156.0			
$C_{12}H_{10}$	Biphenyl	99.4		209.4	198.4					181.4			
$C_{12}H_{10}N_2O$	*trans*-Azoxybenzene	243.4								342.0			
$C_{12}H_{10}N_2O$	*N*-Nitrosodiphenylamine	227.2											
$C_{12}H_{10}O$	Diphenyl ether	-32.1		233.9	216.6	-14.9				52.0			
$C_{12}H_{10}O_2$	1-Naphthaleneacetic acid	-359.2											
$C_{12}H_{10}O_2$	2-Naphthaleneacetic acid	-371.9											
$C_{12}H_{11}N$	Diphenylamine	130.2								219.3			
$C_{12}H_{11}N$	2-Aminobiphenyl	93.8								184.4			
$C_{12}H_{11}N$	4-Aminobiphenyl	81.0											
$C_{12}H_{12}N_2$	*p*-Benzidine	70.7											
$C_{12}H_{14}O_4$	Diethyl phthalate					-776.6		425.1	366.1	-688.4			
$C_{12}H_{16}$	Cyclohexylbenzene					-76.6				-16.7			
$C_{12}H_{17}NO_4$	Diethyl 3,5-dimethylpyrrole-2,4-dicarboxylate	-916.7											
$C_{12}H_{18}$	3,9-Dodecadiyne					197.8							
$C_{12}H_{18}$	5,7-Dodecadiyne					181.5							
$C_{12}H_{18}$	1-*tert*-Butyl-3,5-dimethylbenzene					-146.5							
$C_{12}H_{18}$	Hexamethylbenzene	-162.4		306.3	245.6					-77.4			
$C_{12}H_{22}$	Cyclohexylcyclohexane					-273.7				-215.7			
$C_{12}H_{22}O_4$	Dodecanedioic acid	-1130.0								-976.9			

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_{12}H_{22}O_{11}$	Sucrose	-2226.1											
$C_{12}H_{22}O_{11}$	β-*D*-Lactose	-2236.7											
$C_{12}H_{24}$	1-Dodecene					-226.2		484.8	360.7	-165.4			
$C_{12}H_{24}O_2$	Dodecanoic acid	-774.6			404.3	-737.9				-642.0			
$C_{12}H_{24}O_2$	Methyl undecanoate					-665.2				-593.8			
$C_{12}H_{24}O_{12}$	α-Lactose monohydrate	-2484.1											
$C_{12}H_{25}Br$	1-Bromododecane					-344.7				-269.9			
$C_{12}H_{25}Cl$	1-Chlorododecane					-392.3				-321.1			
$C_{12}H_{26}$	Dodecane					-350.9			375.8	-289.4			
$C_{12}H_{26}O$	1-Dodecanol					-528.5			438.1	-436.6			
$C_{12}H_{26}O_3$	Diethylene glycol dibutyl ether								452.0				
$C_{12}H_{27}N$	Tributylamine					-281.6							
$C_{12}H_{27}O_4P$	Tributyl phosphate								379.4				
$C_{13}H_8O_2$	Xanthone	-191.5											
$C_{13}H_9N$	Acridine	179.4								273.9			
$C_{13}H_9N$	Phenanthridine	141.9								240.5			
$C_{13}H_9N$	Benzo[f]quinoline	150.6								233.7			
$C_{13}H_{10}$	9*H*-Fluorene	89.9		207.3	203.1					175.0			173.1
$C_{13}H_{10}N_2$	9-Acridinamine	159.2											
$C_{13}H_{10}O$	Benzophenone	-34.5			224.8					54.9			
$C_{13}H_{11}N$	9-Methyl-9*H*-carbazole	105.5								201.0			
$C_{13}H_{12}$	Diphenylmethane	71.5		239.3		89.7				139.0			
$C_{13}H_{13}N$	*N*-Benzylaniline	101.4											
$C_{13}H_{14}N_2$	4,4'-Diaminodiphenylmethane				270.9								
$C_{13}H_{24}O_4$	Tridecanedioic acid	-1148.3											
$C_{13}H_{26}$	1-Tridecene								391.8				
$C_{13}H_{26}O_2$	Methyl dodecanoate					-693.0				-614.9			
$C_{13}H_{28}$	Tridecane								406.7				
$C_{13}H_{28}O$	1-Tridecanol	-599.4											
$C_{14}H_8O_2$	9,10-Anthracenedione	-188.5								-75.7			
$C_{14}H_8O_2$	9,10-Phenanthrenedione	-154.7								-46.6			
$C_{14}H_8O_4$	1,4-Dihydroxy-9,10-anthracenedione	-595.8								-471.7			
$C_{14}H_{10}$	Anthracene	129.2		207.5	210.5					230.9			
$C_{14}H_{10}$	Phenanthrene	116.2		215.1	220.6					207.5			
$C_{14}H_{10}$	Diphenylacetylene	312.4			225.9								
$C_{14}H_{10}O_2$	Benzil	-153.9								-55.5			
$C_{14}H_{10}O_4$	Benzoyl peroxide	-369.4								-281.7			
$C_{14}H_{12}$	*cis*-Stilbene					183.3				252.3			
$C_{14}H_{12}$	*trans*-Stilbene	136.9								236.1			
$C_{14}H_{14}$	1,1-Diphenylethane					48.7							
$C_{14}H_{14}$	1,2-Diphenylethane	51.5								142.9			
$C_{14}H_{22}$	1,3-Di-*tert*-butylbenzene					-188.8							
$C_{14}H_{22}$	1,4-Di-*tert*-butylbenzene	-212.0											
$C_{14}H_{23}N_3O_{10}$	Pentetic acid	-2225.2											
$C_{14}H_{27}N$	Tetradecanenitrile					-260.2				-174.9			
$C_{14}H_{28}O_2$	Tetradecanoic acid	-833.5			432.0	-788.8				-693.7			
$C_{14}H_{28}O_2$	Methyl tridecanoate					-717.9				-635.3			
$C_{14}H_{30}O$	1-Tetradecanol	-629.6			388.0	-580.6							
$C_{15}H_{16}O_2$	2,2-Bis(4-hydroxyphenyl)propane	-368.6											
$C_{15}H_{24}$	1,3-Di-*tert*-butyl-5-methylbenzene	-245.8											
$C_{15}H_{24}O$	2,6-Di-*tert*-butyl-4-methylphenol	-410.0								-296.9			
$C_{15}H_{30}$	Decylcyclopentane					-367.3							
$C_{15}H_{30}O_2$	Pentadecanoic acid	-861.7			443.3	-811.7				-699.0			
$C_{15}H_{30}O_2$	Methyl tetradecanoate					-743.9				-656.9			
$C_{15}H_{32}O$	1-Pentadecanol	-658.2											
$C_{16}H_{10}$	Fluoranthene	189.9		230.6	230.2					289.0			
$C_{16}H_{10}$	Pyrene	125.5		224.9	229.7					225.7			
$C_{16}H_{22}O_4$	Dibutyl phthalate					-842.6				-750.9			
$C_{16}H_{22}O_{11}$	α-*D*-Glucose pentaacetate	-2249.4											
$C_{16}H_{22}O_{11}$	β-*D*-Glucose pentaacetate	-2232.6											
$C_{16}H_{26}$	Decylbenzene					-218.3				-138.6			
$C_{16}H_{32}$	1-Hexadecene					-328.7		587.9	488.9	-248.4			
$C_{16}H_{32}O_2$	Hexadecanoic acid	-891.5		452.4	460.7	-838.1				-737.1			
$C_{16}H_{32}O_2$	Methyl pentadecanoate					-771.0				-680.0			
$C_{16}H_{33}Br$	1-Bromohexadecane					-444.5				-350.2			

		Crystal				Liquid				Gas			
Molecular formula	**Name**	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K	$\Delta_f H°$ kJ/mol	$\Delta_f G°$ kJ/mol	$S°$ J/mol K	C_p J/mol K
$C_{16}H_{34}$	Hexadecane					-456.1			501.6	-374.8			
$C_{16}H_{34}O$	1-Hexadecanol	-686.5			422.0					-517.0			
$C_{16}H_{36}IN$	Tetrabutylammonium iodide	-498.6											
$C_{17}H_{34}O_2$	Heptadecanoic acid	-924.4			475.7	-865.6							
$C_{18}H_{12}$	Benz[a]anthracene	170.8								293.0			
$C_{18}H_{12}$	Chrysene	145.3								269.8			
$C_{18}H_{14}$	*o*-Terphenyl			298.8	274.8			337.1	369.1				
$C_{18}H_{14}$	*p*-Terphenyl	163.0		285.6	278.7					279.0			
$C_{18}H_{15}N$	Triphenylamine	234.7								326.8			
$C_{18}H_{15}O_4P$	Triphenyl phosphate			397.5	356.2								
$C_{18}H_{15}P$	Triphenylphosphine				312.5								
$C_{18}H_{30}$	1,3,5-Tri-*tert*-butylbenzene	-320.0											
$C_{18}H_{34}O_2$	Oleic acid								577.0				
$C_{18}H_{34}O_4$	Dibutyl sebacate								619.0				
$C_{18}H_{36}O_2$	Stearic acid	-947.7			501.5	-884.7				-781.2			
$C_{18}H_{37}Cl$	1-Chlorooctadecane					-544.1				-446.0			
$C_{18}H_{38}$	Octadecane	-567.4		480.2	485.6					-414.6			
$C_{18}H_{39}N$	Trihexylamine					-433.0							
$C_{19}H_{16}O$	Triphenylmethanol	-2.5											
$C_{19}H_{36}O_2$	Methyl oleate					-734.5				-649.9			
$C_{19}H_{36}O_2$	Methyl *trans*-9-octadecenoate					-737.0							
$C_{20}H_{12}$	Perylene	182.8		264.6	274.9								
$C_{20}H_{12}$	Benzo[a]pyrene												254.8
$C_{20}H_{14}O_4$	Diphenyl phthalate	-489.2											
$C_{20}H_{38}O_2$	Ethyl oleate					-775.8							
$C_{20}H_{38}O_2$	Ethyl *trans*-9-octadecenoate					-773.3							
$C_{20}H_{40}O_2$	Eicosanoic acid	-1011.9			545.1	-940.0				-812.4			
$C_{21}H_{21}O_4P$	Tri-*o*-cresyl phosphate			570.0	578.0								
$C_{22}H_{14}$	Dibenz[a,h]anthracene												283.9
$C_{22}H_{42}O_2$	*trans*-13-Docosenoic acid	-960.7											
$C_{22}H_{42}O_2$	Butyl oleate					-816.9							
$C_{22}H_{44}O_2$	Butyl stearate												
$C_{24}H_{38}O_4$	Bis(2-ethylhexyl) phthalate								704.7				
$C_{24}H_{51}N$	Trioctylamine					-585.0							
$C_{26}H_{18}$	9,10-Diphenylanthracene	308.7								465.6			
$C_{26}H_{54}$	5-Butyldocosane					-713.5				-587.6			
$C_{26}H_{54}$	11-Butyldocosane					-716.0				-593.4			
$C_{28}H_{18}$	9,9'-Bianthracene	326.2								454.3			
$C_{31}H_{64}$	11-Decylheneicosane					-848.0				-705.8			
$C_{32}H_{66}$	Dotriacontane	-968.3								-697.2			
C_{60}	Carbon (fullerene-C_{60})	2327.0	2302.0	426.0	520.0					2502.0	2442.0	544.0	512.0
C_{70}	Carbon (fullerene-C_{70})	2555.0	2537.0	464.0	650.0					2755.0	2692.0	614.0	585.0

THERMODYNAMIC PROPERTIES AS A FUNCTION OF TEMPERATURE

L. V. Gurvich, V. S. Iorish, V. S. Yungman, and O. V. Dorofeeva

The thermodynamic properties $C_p^\circ(T)$, $S^\circ(T)$, $H^\circ(T)$-$H^\circ(T_r)$, -[$G^\circ(T)$-$H^\circ(T_r)$]/T and formation properties $\Delta_f H^\circ(T)$, $\Delta_f G^\circ(T)$, log $K_f^\circ(T)$ are tabulated as functions of temperature in the range 298.15 to 1500 K for 80 substances in the standard state.The reference temperature, T_r, is equal to 298.15 K. The standard state pressure is taken as 1 bar (100,000 Pa). The tables are presented in the JANAF Thermochemical Tables format (Reference 2). The numerical data are extracted from IVTANTHERMO databases except for C_2H_4O, C_3H_6O, C_6H_6, C_6H_6O, $C_{10}H_8$, and CH_5N, which are based upon TRC Tables. See the references for information on standard states and other details.

References

1. Gurvich, L. V., Veyts, I. V., and Alcock, C. B., Eds., *Thermodynamic Properties of Individual Substances, 4th ed.*, Hemisphere Publishing Corp., New York, 1989.
2. Chase, M. W., et al., *JANAF Thermochemical Tables, 3rd ed., J. Phys. Chem. Ref. Data*, 14, Suppl. 1, 1985.

Order of Listing of Tables

No.	Formula	Name	State
1	Ar	Argon	g
2	Br	Bromine	g
3	Br_2	Dibromine	g
4	BrH	Hydrogen bromide	g
5	C	Carbon (graphite)	cr
6	C	Carbon (diamond)	cr
7	C_2	Dicarbon	g
8	C_3	Tricarbon	g
9	CO	Carbon oxide	g
10	CO_2	Carbon dioxide	g
11	CH_4	Methane	g
12	C_2H_2	Acetylene	g
13	C_2H_4	Ethylene	g
14	C_2H_6	Ethane	g
15	C_3H_6	Cyclopropane	g
16	C_3H_8	Propane	g
17	C_6H_6	Benzene	l
18	C_6H_6	Benzene	g
19	$C_{10}H_8$	Naphthalene	cr, l
20	$C_{10}H_8$	Naphthalene	g
21	CH_2O	Formaldehyde	g
22	CH_4O	Methanol	g
23	C_2H_4O	Acetaldehyde	g
24	C_2H_6O	Ethanol	g
25	$C_2H_4O_2$	Acetic acid	g
26	C_3H_6O	Acetone	g
27	C_6H_6O	Phenol	g
28	CF_4	Carbon tetrafluoride	g
29	CHF_3	Trifluoromethane	g
30	$CClF_3$	Chlorotrifluoromethane	g
31	CCl_2F_2	Dichlorodifluoromethane	g
32	$CHClF_2$	Chlorodifluoromethane	g
33	CH_5N	Methylamine	g
34	Cl	Chlorine	g
35	Cl_2	Dichlorine	g
36	ClH	Hydrogen chloride	g
37	Cu	Copper	cr, l
38	Cu	Copper	g
39	CuO	Copper oxide	cr
40	Cu_2O	Dicopper oxide	cr
41	$CuCl_2$	Copper dichloride	cr, l
42	$CuCl_2$	Copper dichloride	g
43	F	Fluorine	g
44	F_2	Difluorine	g
45	FH	Hydrogen fluoride	g
46	Ge	Germanium	cr, l
47	Ge	Germanium	g
48	GeO_2	Germanium dioxide	cr, l
49	$GeCl_4$	Germanium tetrachloride	g
50	H	Hydrogen	g
51	H_2	Dihydrogen	g
52	HO	Hydroxyl	g
53	H_2O	Water	l
54	H_2O	Water	g
55	I	Iodine	g
56	I_2	Diiodine	cr, l
57	I_2	Diiodine	g
58	IH	Hydrogen iodide	g
59	K	Potassium	cr, l
60	K	Potassium	g
61	K_2O	Dipotassium oxide	cr, l
62	KOH	Potassium hydroxide	cr, l
63	KOH	Potassium hydroxide	g
64	KCl	Potassium chloride	cr, l
65	KCl	Potassium chloride	g
66	N_2	Dinitrogen	g
67	NO	Nitric oxide	g
68	NO_2	Nitrogen dioxide	g
69	NH_3	Ammonia	g
70	O	Oxygen	g
71	O_2	Dioxygen	g
72	S	Sulfur	cr, l
73	S	Sulfur	g
74	S_2	Disulfur	g
75	S_8	Octasulfur	g
76	SO_2	Sulfur dioxide	g
77	Si	Silicon	cr
78	Si	Silicon	g
79	SiO_2	Silicon dioxide	cr
80	$SiCl_4$	Silicon tetrachloride	g

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
1. ARGON Ar (g)							
298.15	20.786	154.845	154.845	0.000	0.000	0.000	0.000
300	20.786	154.973	154.845	0.038	0.000	0.000	0.000
400	20.786	160.953	155.660	2.117	0.000	0.000	0.000
500	20.786	165.591	157.200	4.196	0.000	0.000	0.000
600	20.786	169.381	158.924	6.274	0.000	0.000	0.000
700	20.786	172.585	160.653	8.353	0.000	0.000	0.000
800	20.786	175.361	162.322	10.431	0.000	0.000	0.000
900	20.786	177.809	163.909	12.510	0.000	0.000	0.000
1000	20.786	179.999	165.410	14.589	0.000	0.000	0.000
1100	20.786	181.980	166.828	16.667	0.000	0.000	0.000
1200	20.786	183.789	168.167	18.746	0.000	0.000	0.000
1300	20.786	185.453	169.434	20.824	0.000	0.000	0.000
1400	20.786	186.993	170.634	22.903	0.000	0.000	0.000
1500	20.786	188.427	171.773	24.982	0.000	0.000	0.000
2. BROMINE Br (g)							
298.15	20.786	175.017	175.017	0.000	111.870	82.379	−14.432
300	20.786	175.146	175.018	0.038	111.838	82.196	−14.311
400	20.787	181.126	175.833	2.117	96.677	75.460	−9.854
500	20.798	185.765	177.373	4.196	96.910	70.129	−7.326
600	20.833	189.559	179.097	6.277	97.131	64.752	−5.637
700	20.908	192.776	180.827	8.364	97.348	59.338	−4.428
800	21.027	195.575	182.499	10.461	97.568	53.893	−3.519
900	21.184	198.061	184.093	12.571	97.796	48.420	−2.810
1000	21.365	200.302	185.604	14.698	98.036	42.921	−2.242
1100	21.559	202.347	187.034	16.844	98.291	37.397	−1.776
1200	21.752	204.231	188.390	19.010	98.560	31.850	−1.386
1300	21.937	205.980	189.676	21.195	98.844	26.279	−1.056
1400	22.107	207.612	190.900	23.397	99.141	20.686	−0.772
1500	22.258	209.142	192.065	25.615	99.449	15.072	−0.525
3. DIBROMINE Br_2 (g)							
298.15	36.057	245.467	245.467	0.000	30.910	3.105	−0.544
300	36.074	245.690	245.468	0.067	30.836	2.933	−0.511
332.25	36.340	249.387	245.671	1.235		pressure = 1 bar	
400	36.729	256.169	246.892	3.711	0.000	0.000	0.000
500	37.082	264.406	249.600	7.403	0.000	0.000	0.000
600	37.305	271.188	252.650	11.123	0.000	0.000	0.000
700	37.464	276.951	255.720	14.862	0.000	0.000	0.000
800	37.590	281.962	258.694	18.615	0.000	0.000	0.000
900	37.697	286.396	261.530	22.379	0.000	0.000	0.000
1000	37.793	290.373	264.219	26.154	0.000	0.000	0.000
1100	37.883	293.979	266.763	29.938	0.000	0.000	0.000
1200	37.970	297.279	269.170	33.730	0.000	0.000	0.000
1300	38.060	300.322	271.451	37.532	0.000	0.000	0.000
1400	38.158	303.146	273.615	41.343	0.000	0.000	0.000
1500	38.264	305.782	275.673	45.164	0.000	0.000	0.000
4. HYDROGEN BROMIDE HBr (g)							
298.15	29.141	198.697	198.697	0.000	−36.290	−53.360	9.348
300	29.141	198.878	198.698	0.054	−36.333	−53.466	9.309
400	29.220	207.269	199.842	2.971	−52.109	−55.940	7.305
500	29.454	213.811	202.005	5.903	−52.484	−56.854	5.939
600	29.872	219.216	204.436	8.868	−52.844	−57.694	5.023
700	30.431	223.861	206.886	11.882	−53.168	−58.476	4.363
800	31.063	227.965	209.269	14.957	−53.446	−59.214	3.866
900	31.709	231.661	211.555	18.095	−53.677	−59.921	3.478
1000	32.335	235.035	213.737	21.298	−53.864	−60.604	3.166
1100	32.919	238.145	215.816	24.561	−54.012	−61.271	2.909

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
1200	33.454	241.032	217.799	27.880	−54.129	−61.925	2.696
1300	33.938	243.729	219.691	31.250	−54.220	−62.571	2.514
1400	34.374	246.261	221.499	34.666	−54.291	−63.211	2.358
1500	34.766	248.646	223.230	38.123	−54.348	−63.846	2.223
5. CARBON (GRAPHITE) C (cr; graphite)							
298.15	8.536	5.740	5.740	0.000	0.000	0.000	0.000
300	8.610	5.793	5.740	0.016	0.000	0.000	0.000
400	11.974	8.757	6.122	1.054	0.000	0.000	0.000
500	14.537	11.715	6.946	2.385	0.000	0.000	0.000
600	16.607	14.555	7.979	3.945	0.000	0.000	0.000
700	18.306	17.247	9.113	5.694	0.000	0.000	0.000
800	19.699	19.785	10.290	7.596	0.000	0.000	0.000
900	20.832	22.173	11.479	9.625	0.000	0.000	0.000
1000	21.739	24.417	12.662	11.755	0.000	0.000	0.000
1100	22.452	26.524	13.827	13.966	0.000	0.000	0.000
1200	23.000	28.502	14.968	16.240	0.000	0.000	0.000
1300	23.409	30.360	16.082	18.562	0.000	0.000	0.000
1400	23.707	32.106	17.164	20.918	0.000	0.000	0.000
1500	23.919	33.749	18.216	23.300	0.000	0.000	0.000
6. CARBON (DIAMOND) C (cr; diamond)							
298.15	6.109	2.362	2.362	0.000	1.850	2.857	−0.501
300	6.201	2.400	2.362	0.011	1.846	2.863	−0.499
400	10.321	4.783	2.659	0.850	1.645	3.235	−0.422
500	13.404	7.431	3.347	2.042	1.507	3.649	−0.381
600	15.885	10.102	4.251	3.511	1.415	4.087	−0.356
700	17.930	12.709	5.274	5.205	1.361	4.537	−0.339
800	19.619	15.217	6.361	7.085	1.338	4.993	−0.326
900	21.006	17.611	7.479	9.118	1.343	5.450	−0.316
1000	22.129	19.884	8.607	11.277	1.372	5.905	−0.308
1100	23.020	22.037	9.731	13.536	1.420	6.356	−0.302
1200	23.709	24.071	10.842	15.874	1.484	6.802	−0.296
1300	24.222	25.990	11.934	18.272	1.561	7.242	−0.291
1400	24.585	27.799	13.003	20.714	1.646	7.675	−0.286
1500	24.824	29.504	14.047	23.185	1.735	8.103	−0.282
7. DICARBON C_2 (g)							
298.15	43.548	197.095	197.095	0.000	830.457	775.116	−135.795
300	43.575	197.365	197.096	0.081	830.506	774.772	−134.898
400	42.169	209.809	198.802	4.403	832.751	755.833	−98.700
500	39.529	218.924	201.959	8.483	834.170	736.423	−76.933
600	37.837	225.966	205.395	12.342	834.909	716.795	−62.402
700	36.984	231.726	208.758	16.078	835.148	697.085	−52.016
800	36.621	236.637	211.943	19.755	835.020	677.366	−44.227
900	36.524	240.943	214.931	23.411	834.618	657.681	−38.170
1000	36.569	244.793	217.728	27.065	834.012	638.052	−33.328
1100	36.696	248.284	220.349	30.728	833.252	618.492	−29.369
1200	36.874	251.484	222.812	34.406	832.383	599.006	−26.074
1300	37.089	254.444	225.133	38.104	831.437	579.596	−23.288
1400	37.329	257.201	227.326	41.824	830.445	560.261	−20.903
1500	37.589	259.785	229.405	45.570	829.427	540.997	−18.839
8. TRICARBON C_3 (g)							
298.15	42.202	237.611	237.611	0.000	839.958	774.249	−135.643
300	42.218	237.872	237.611	0.078	839.989	773.841	−134.736
400	43.383	250.164	239.280	4.354	841.149	751.592	−98.147
500	44.883	260.003	242.471	8.766	841.570	729.141	−76.172
600	46.406	268.322	246.104	13.331	841.453	706.659	−61.519
700	47.796	275.582	249.807	18.042	840.919	684.230	−51.057
800	48.997	282.045	253.440	22.884	840.053	661.901	−43.217

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
900	50.006	287.876	256.948	27.835	838.919	639.698	−37.127
1000	50.844	293.189	260.310	32.879	837.572	617.633	−32.261
1100	51.535	298.069	263.524	37.999	836.059	595.711	−28.288
1200	52.106	302.578	266.593	43.182	834.420	573.933	−24.982
1300	52.579	306.768	269.524	48.417	832.690	552.295	−22.191
1400	52.974	310.679	272.326	53.695	830.899	530.793	−19.804
1500	53.307	314.346	275.006	59.010	829.068	509.421	−17.739
9. CARBON OXIDE CO (g)							
298.15	29.141	197.658	197.658	0.000	−110.530	−137.168	24.031
300	29.142	197.838	197.659	0.054	−110.519	−137.333	23.912
400	29.340	206.243	198.803	2.976	−110.121	−146.341	19.110
500	29.792	212.834	200.973	5.930	−110.027	−155.412	16.236
600	30.440	218.321	203.419	8.941	−110.157	−164.480	14.319
700	31.170	223.067	205.895	12.021	−110.453	−173.513	12.948
800	31.898	227.277	208.309	15.175	−110.870	−182.494	11.915
900	32.573	231.074	210.631	18.399	−111.378	−191.417	11.109
1000	33.178	234.538	212.851	21.687	−111.952	−200.281	10.461
1100	33.709	237.726	214.969	25.032	−112.573	−209.084	9.928
1200	34.169	240.679	216.990	28.426	−113.228	−217.829	9.482
1300	34.568	243.430	218.920	31.864	−113.904	−226.518	9.101
1400	34.914	246.005	220.763	35.338	−114.594	−235.155	8.774
1500	35.213	248.424	222.527	38.845	−115.291	−243.742	8.488
10. CARBON DIOXIDE CO_2 (g)							
298.15	37.135	213.783	213.783	0.000	−393.510	−394.373	69.092
300	37.220	214.013	213.784	0.069	−393.511	−394.379	68.667
400	41.328	225.305	215.296	4.004	−393.586	−394.656	51.536
500	44.627	234.895	218.280	8.307	−393.672	−394.914	41.256
600	47.327	243.278	221.762	12.909	−393.791	−395.152	34.401
700	49.569	250.747	225.379	17.758	−393.946	−395.367	29.502
800	51.442	257.492	228.978	22.811	−394.133	−395.558	25.827
900	53.008	263.644	232.493	28.036	−394.343	−395.724	22.967
1000	54.320	269.299	235.895	33.404	−394.568	−395.865	20.678
1100	55.423	274.529	239.172	38.893	−394.801	−395.984	18.803
1200	56.354	279.393	242.324	44.483	−395.035	−396.081	17.241
1300	57.144	283.936	245.352	50.159	−395.265	−396.159	15.918
1400	57.818	288.196	248.261	55.908	−395.488	−396.219	14.783
1500	58.397	292.205	251.059	61.719	−395.702	−396.264	13.799
11. METHANE CH_4 (g)							
298.15	35.695	186.369	186.369	0.000	−74.600	−50.530	8.853
300	35.765	186.590	186.370	0.066	−74.656	−50.381	8.772
400	40.631	197.501	187.825	3.871	−77.703	−41.827	5.462
500	46.627	207.202	190.744	8.229	−80.520	−32.525	3.398
600	52.742	216.246	194.248	13.199	−82.969	−22.690	1.975
700	58.603	224.821	198.008	18.769	−85.023	−12.476	0.931
800	64.084	233.008	201.875	24.907	−86.693	−1.993	0.130
900	69.137	240.852	205.773	31.571	−88.006	8.677	−0.504
1000	73.746	248.379	209.660	38.719	−88.996	19.475	−1.017
1100	77.919	255.607	213.511	46.306	−89.698	30.358	−1.442
1200	81.682	262.551	217.310	54.289	−90.145	41.294	−1.797
1300	85.067	269.225	221.048	62.630	−90.367	52.258	−2.100
1400	88.112	275.643	224.720	71.291	−90.390	63.231	−2.359
1500	90.856	281.817	228.322	80.242	−90.237	74.200	−2.584
12. ACETYLENE C_2H_2 (g)							
298.15	44.036	200.927	200.927	0.000	227.400	209.879	−36.769
300	44.174	201.199	200.927	0.082	227.397	209.770	−36.524
400	50.388	214.814	202.741	4.829	227.161	203.928	−26.630
500	54.751	226.552	206.357	10.097	226.846	198.154	−20.701

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
600	58.121	236.842	210.598	15.747	226.445	192.452	−16.754
700	60.970	246.021	215.014	21.704	225.968	186.823	−13.941
800	63.511	254.331	219.418	27.931	225.436	181.267	−11.835
900	65.831	261.947	223.726	34.399	224.873	175.779	−10.202
1000	67.960	268.995	227.905	41.090	224.300	170.355	−8.898
1100	69.909	275.565	231.942	47.985	223.734	164.988	−7.835
1200	71.686	281.725	235.837	55.067	223.189	159.672	−6.950
1300	73.299	287.528	239.592	62.317	222.676	154.400	−6.204
1400	74.758	293.014	243.214	69.721	222.203	149.166	−5.565
1500	76.077	298.218	246.709	77.264	221.774	143.964	−5.013
13. ETHYLENE C_2H_4 (g)							
298.15	42.883	219.316	219.316	0.000	52.400	68.358	−11.976
300	43.059	219.582	219.317	0.079	52.341	68.457	−11.919
400	53.045	233.327	221.124	4.881	49.254	74.302	−9.703
500	62.479	246.198	224.864	10.667	46.533	80.887	−8.450
600	70.673	258.332	229.441	17.335	44.221	87.982	−7.659
700	77.733	269.770	234.393	24.764	42.278	95.434	−7.121
800	83.868	280.559	239.496	32.851	40.655	103.142	−6.734
900	89.234	290.754	244.630	41.512	39.310	111.036	−6.444
1000	93.939	300.405	249.730	50.675	38.205	119.067	−6.219
1100	98.061	309.556	254.756	60.280	37.310	127.198	−6.040
1200	101.670	318.247	259.688	70.271	36.596	135.402	−5.894
1300	104.829	326.512	264.513	80.599	36.041	143.660	−5.772
1400	107.594	334.384	269.225	91.223	35.623	151.955	−5.669
1500	110.018	341.892	273.821	102.107	35.327	160.275	−5.581
14. ETHANE C_2H_6 (g)							
298.15	52.487	229.161	229.161	0.000	−84.000	−32.015	5.609
300	52.711	229.487	229.162	0.097	−84.094	−31.692	5.518
400	65.459	246.378	231.379	5.999	−88.988	−13.473	1.759
500	77.941	262.344	235.989	13.177	−93.238	5.912	−0.618
600	89.188	277.568	241.660	21.545	−96.779	26.086	−2.271
700	99.136	292.080	247.835	30.972	−99.663	46.800	−3.492
800	107.936	305.904	254.236	41.334	−101.963	67.887	−4.433
900	115.709	319.075	260.715	52.525	−103.754	89.231	−5.179
1000	122.552	331.628	267.183	64.445	−105.105	110.750	−5.785
1100	128.553	343.597	273.590	77.007	−106.082	132.385	−6.286
1200	133.804	355.012	279.904	90.131	−106.741	154.096	−6.708
1300	138.391	365.908	286.103	103.746	−107.131	175.850	−7.066
1400	142.399	376.314	292.178	117.790	−107.292	197.625	−7.373
1500	145.905	386.260	298.121	132.209	−107.260	219.404	−7.640
15. CYCLOPROPANE C_3H_6 (g)							
298.15	55.571	237.488	237.488	0.000	53.300	104.514	−18.310
300	55.941	237.832	237.489	0.103	53.195	104.832	−18.253
400	76.052	256.695	239.924	6.708	47.967	122.857	−16.043
500	93.859	275.637	245.177	15.230	43.730	142.091	−14.844
600	108.542	294.092	251.801	25.374	40.405	162.089	−14.111
700	120.682	311.763	259.115	36.854	37.825	182.583	−13.624
800	130.910	328.564	266.755	49.447	35.854	203.404	−13.281
900	139.658	344.501	274.516	62.987	34.384	224.441	−13.026
1000	147.207	359.616	282.277	77.339	33.334	245.618	−12.830
1100	153.749	373.961	289.965	92.395	32.640	266.883	−12.673
1200	159.432	387.588	297.538	108.060	32.249	288.197	−12.545
1300	164.378	400.549	304.967	124.257	32.119	309.533	−12.437
1400	168.689	412.892	312.239	140.915	32.215	330.870	−12.345
1500	172.453	424.662	319.344	157.976	32.507	352.193	−12.264
16. PROPANE C_3H_8 (g)							
298.15	73.597	270.313	270.313	0.000	−103.847	−23.458	4.110

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
300	73.931	270.769	270.314	0.136	−103.972	−22.959	3.997
400	94.014	294.739	273.447	8.517	−110.33	15.029	−0.657
500	112.591	317.768	280.025	18.872	−115.658	34.507	−3.605
600	128.700	339.753	288.162	30.955	−119.973	64.961	−5.655
700	142.674	360.668	297.039	44.540	−123.384	96.065	−7.168
800	154.766	380.528	306.245	59.427	−126.016	127.603	−8.331
900	165.352	399.381	315.555	75.444	−127.982	159.430	−9.253
1000	174.598	417.293	324.841	92.452	−129.380	191.444	−10.000
1100	182.673	434.321	334.026	110.325	−130.296	223.574	−10.617
1200	189.745	450.526	343.064	128.954	−130.802	255.770	−11.133
1300	195.853	465.961	351.929	148.241	−130.961	287.993	−11.572
1400	201.209	480.675	360.604	168.100	−130.829	320.217	−11.947
1500	205.895	494.721	369.080	188.460	−130.445	352.422	−12.272
17. BENZENE C_6H_6 (l)							
298.15	135.950	173.450	173.450	0.000	49.080	124.521	−21.815
300	136.312	174.292	173.453	.252	49.077	124.989	−21.762
400	161.793	216.837	179.082	15.102	48.978	150.320	−19.630
500	207.599	257.048	190.639	33.204	50.330	175.559	−18.340
18. BENZENE C_6H_6 (g)							
298.15	82.430	269.190	269.190	0.000	82.880	129.750	−22.731
300	83.020	269.700	269.190	0.153	82.780	130.040	−22.641
400	113.510	297.840	272.823	10.007	77.780	146.570	−19.140
500	139.340	326.050	280.658	22.696	73.740	164.260	−17.160
600	160.090	353.360	290.517	37.706	70.490	182.680	−15.903
700	176.790	379.330	301.360	54.579	67.910	201.590	−15.042
800	190.460	403.860	312.658	72.962	65.910	220.820	−14.418
900	201.840	426.970	324.084	92.597	64.410	240.280	−13.945
1000	211.430	448.740	335.473	113.267	63.340	259.890	−13.575
1100	219.580	469.280	346.710	134.827	62.620	277.640	−13.184
1200	226.540	488.690	357.743	157.137	62.200	299.320	−13.029
1300	232.520	507.070	368.534	180.097	62.000	319.090	−12.821
1400	237.680	524.490	379.056	203.607	61.990	338.870	−12.643
1500	242.140	541.040	389.302	227.607	62.110	358.640	−12.489
19. NAPHTHALENE $C_{10}H_8$ (cr, l)							
298.15	165.720	167.390	167.390	0.000	78.530	201.585	−35.316
300	167.001	168.419	167.393	0.308	78.466	202.349	−35.232
353.43	208.722	198.948	169.833	10.290	96.099	224.543	−33.186
PHASE TRANSITION: $\Delta_{trs}H$ = 18.980 kJ/mol, $\Delta_{trs}S$ = 53.702 J/K·mol, cr–l							
353.43	217.200	252.650	169.833	29.270	96.099	224.543	−33.186
400	241.577	280.916	181.124	39.917	96.067	241.475	−31.533
470	276.409	322.712	199.114	58.091	97.012	266.859	−29.658
20. NAPHTHALENE $C_{10}H_8$ (g)							
298.15	131.920	333.150	333.150	0.000	150.580	224.100	−39.260
300	132.840	333.970	333.157	0.244	150.450	224.560	−39.098
400	180.070	378.800	338.950	15.940	144.190	250.270	−32.681
500	219.740	423.400	351.400	36.000	139.220	277.340	−28.973
600	251.530	466.380	367.007	59.624	135.350	305.330	−26.581
700	277.010	507.140	384.146	86.096	132.330	333.950	−24.919
800	297.730	545.520	401.935	114.868	130.050	362.920	−23.696
900	314.850	581.610	419.918	145.523	128.430	392.150	−22.759
1000	329.170	615.550	437.806	177.744	127.510	421.700	−22.027
1100	341.240	647.500	455.426	211.281	127.100	450.630	−21.398
1200	351.500	677.650	472.707	245.932	126.960	480.450	−20.913
1300	360.260	706.130	489.568	281.531	127.060	509.770	−20.482
1400	367.780	733.110	506.009	317.941	127.390	539.740	−20.137
1500	374.270	758.720	522.019	355.051	127.920	568.940	−19.812

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
21. FORMALDEHYDE H_2CO (g)							
298.15	35.387	218.760	218.760	0.000	−108.700	−102.667	17.987
300	35.443	218.979	218.761	0.066	−108.731	−102.630	17.869
400	39.240	229.665	220.192	3.789	−110.438	−100.340	13.103
500	43.736	238.900	223.028	7.936	−112.073	−97.623	10.198
600	48.181	247.270	226.381	12.534	−113.545	−94.592	8.235
700	52.280	255.011	229.924	17.560	−114.833	−91.328	6.815
800	55.941	262.236	233.517	22.975	−115.942	−87.893	5.739
900	59.156	269.014	237.088	28.734	−116.889	−84.328	4.894
1000	61.951	275.395	240.603	34.792	−117.696	−80.666	4.213
1100	64.368	281.416	244.042	41.111	−118.382	−76.929	3.653
1200	66.453	287.108	247.396	47.655	−118.966	−73.134	3.183
1300	68.251	292.500	250.660	54.392	−119.463	−69.294	2.784
1400	69.803	297.616	253.833	61.297	−119.887	−65.418	2.441
1500	71.146	302.479	256.915	68.346	−120.249	−61.514	2.142
22. METHANOL CH_3OH (g)							
298.15	44.101	239.865	239.865	0.000	−201.000	−162.298	28.434
300	44.219	240.139	239.866	0.082	−201.068	−162.057	28.216
400	51.713	253.845	241.685	4.864	−204.622	−148.509	19.393
500	59.800	266.257	245.374	10.442	−207.750	−134.109	14.010
600	67.294	277.835	249.830	16.803	−210.387	−119.125	10.371
700	73.958	288.719	254.616	23.873	−212.570	−103.737	7.741
800	79.838	298.987	259.526	31.569	−214.350	−88.063	5.750
900	85.025	308.696	264.455	39.817	−215.782	−72.188	4.190
1000	89.597	317.896	269.343	48.553	−216.916	−56.170	2.934
1100	93.624	326.629	274.158	57.718	−217.794	−40.050	1.902
1200	97.165	334.930	278.879	67.262	−218.457	−23.861	1.039
1300	100.277	342.833	283.497	77.137	−218.936	−7.624	0.306
1400	103.014	350.367	288.007	87.304	−219.261	8.644	−0.322
1500	105.422	357.558	292.405	97.729	−219.456	24.930	−0.868
23. ACETALDEHYDE C_2H_4O (g)							
298.15	55.318	263.840	263.840	0.000	−166.190	−133.010	23.302
300	55.510	264.180	263.837	0.103	−166.250	−132.800	23.122
400	66.282	281.620	266.147	6.189	−169.530	−121.130	15.818
500	76.675	297.540	270.850	13.345	−172.420	−108.700	11.356
600	85.942	312.360	276.550	21.486	−174.870	−95.720	8.334
700	94.035	326.230	282.667	30.494	−176.910	−82.350	6.145
800	101.070	339.260	288.938	40.258	−178.570	−68.730	4.487
900	107.190	351.520	295.189	50.698	−179.880	−54.920	3.187
1000	112.490	363.100	301.431	61.669	−180.850	−40.930	2.138
1100	117.080	374.040	307.537	73.153	−181.560	−27.010	1.283
1200	121.060	384.400	313.512	85.065	−182.070	−12.860	0.560
1300	124.500	394.230	319.350	97.344	−182.420	1.240	−0.050
1400	127.490	403.570	325.031	109.954	−182.640	15.470	−0.577
1500	130.090	412.460	330.571	122.834	−182.750	29.580	−1.030
24. ETHANOL C_2H_5OH (g)							
298.15	65.652	281.622	281.622	0.000	−234.800	−167.874	29.410
300	65.926	282.029	281.623	0.122	−234.897	−167.458	29.157
400	81.169	303.076	284.390	7.474	−239.826	−144.216	18.832
500	95.400	322.750	290.115	16.318	−243.940	−119.820	12.517
600	107.656	341.257	297.112	26.487	−247.260	−94.672	8.242
700	118.129	358.659	304.674	37.790	−249.895	−69.023	5.151
800	127.171	375.038	312.456	50.065	−251.951	−43.038	2.810
900	135.049	390.482	320.276	63.185	−253.515	−16.825	0.976
1000	141.934	405.075	328.033	77.042	−254.662	9.539	−0.498
1100	147.958	418.892	335.670	91.543	−255.454	36.000	−1.709
1200	153.232	431.997	343.156	106.609	−255.947	62.520	−2.721

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
1300	157.849	444.448	350.473	122.168	−256.184	89.070	−3.579
1400	161.896	456.298	357.612	138.160	−256.206	115.630	−4.314
1500	165.447	467.591	364.571	154.531	−256.044	142.185	−4.951
25. ACETIC ACID $C_2H_4O_2$ (g)							
298.15	63.438	283.470	283.470	0.000	−432.249	−374.254	65.567
300	63.739	283.863	283.471	0.118	−432.324	−373.893	65.100
400	79.665	304.404	286.164	7.296	−436.006	−353.840	46.206
500	93.926	323.751	291.765	15.993	−438.875	−332.950	34.783
600	106.181	341.988	298.631	26.014	−440.993	−311.554	27.123
700	116.627	359.162	306.064	37.169	−442.466	−289.856	21.629
800	125.501	375.331	313.722	49.287	−443.395	−267.985	17.497
900	132.989	390.558	321.422	62.223	−443.873	−246.026	14.279
1000	139.257	404.904	329.060	75.844	−443.982	−224.034	11.702
1100	144.462	418.429	336.576	90.039	−443.798	−202.046	9.594
1200	148.760	431.189	343.933	104.707	−443.385	−180.086	7.839
1300	152.302	443.240	351.113	119.765	−442.795	−158.167	6.355
1400	155.220	454.637	358.105	135.146	−442.071	−136.299	5.085
1500	157.631	465.432	364.903	150.793	−441.247	−114.486	3.987
26. ACETONE C_3H_6O (g)							
298.15	74.517	295.349	295.349	0.000	−217.150	−152.716	26.757
300	74.810	295.809	295.349	0.138	−217.233	−152.339	26.521
400	91.755	319.658	298.498	8.464	−222.212	−129.913	16.962
500	107.864	341.916	304.988	18.464	−226.522	−106.315	11.107
600	122.047	362.836	312.873	29.978	−230.120	−81.923	7.133
700	134.306	382.627	321.470	42.810	−233.049	−56.986	4.252
800	144.934	401.246	330.265	56.785	−235.350	−31.673	2.068
900	154.097	418.860	339.141	71.747	−237.149	−6.109	0.353
1000	162.046	435.513	347.950	87.563	−238.404	19.707	−1.030
1100	168.908	451.286	356.617	104.136	−239.283	45.396	−2.157
1200	174.891	466.265	365.155	121.332	−239.827	71.463	−3.110
1300	180.079	480.491	373.513	139.072	−240.120	97.362	−3.912
1400	184.556	493.963	381.596	157.314	−240.203	123.470	−4.607
1500	188.447	506.850	389.533	175.975	−240.120	149.369	−5.202
27. PHENOL C_6H_6O (g)							
298.15	103.220	314.810	314.810	0.000	−96.400	−32.630	5.720
300	103.860	315.450	314.810	0.192	−96.490	−32.230	5.610
400	135.790	349.820	319.278	12.217	−100.870	−10.180	1.330
500	161.910	383.040	328.736	27.152	−104.240	12.970	−1.360
600	182.480	414.450	340.430	44.412	−106.810	36.650	−3.190
700	198.840	443.860	353.134	63.508	−108.800	60.750	−4.530
800	212.140	471.310	366.211	84.079	−110.300	85.020	−5.550
900	223.190	496.950	379.327	105.861	−111.370	109.590	−6.360
1000	232.490	520.960	392.302	128.658	−111.990	134.280	−7.010
1100	240.410	543.500	405.033	152.314	−112.280	158.620	−7.530
1200	247.200	564.720	417.468	176.703	−112.390	183.350	−7.980
1300	253.060	584.740	429.568	201.723	−112.330	208.070	−8.360
1400	258.120	603.680	441.331	227.288	−112.120	233.050	−8.700
1500	262.520	621.650	452.767	253.325	−111.780	257.540	−8.970
28. CARBON TETRAFLUORIDE CF_4 (g)							
298.15	61.050	261.455	261.455	0.000	−933.200	−888.518	155.663
300	61.284	261.833	261.456	0.113	−933.219	−888.240	154.654
400	72.399	281.057	264.001	6.822	−933.986	−873.120	114.016
500	80.713	298.153	269.155	14.499	−934.372	−857.852	89.618
600	86.783	313.434	275.284	22.890	−934.490	−842.533	73.348
700	91.212	327.162	281.732	31.801	−934.431	−827.210	61.726
800	94.479	339.566	288.199	41.094	−934.261	−811.903	53.011
900	96.929	350.842	294.542	50.670	−934.024	−796.622	46.234

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
1000	98.798	361.156	300.695	60.460	−933.745	−781.369	40.814
1100	100.250	370.643	306.629	70.416	−933.442	−766.146	36.381
1200	101.396	379.417	312.334	80.500	−933.125	−750.952	32.688
1300	102.314	387.571	317.811	90.687	−932.800	−735.784	29.564
1400	103.059	395.181	323.069	100.957	−932.470	−720.641	26.887
1500	103.671	402.313	328.116	111.295	−932.137	−705.522	24.568
29. TRIFLUOROMETHANE CHF_3 (g)							
298.15	51.069	259.675	259.675	0.000	−696.700	−662.237	116.020
300	51.258	259.991	259.676	0.095	−696.735	−662.023	115.267
400	61.148	276.113	261.807	5.722	−698.427	−650.186	84.905
500	69.631	290.700	266.149	12.275	−699.715	−637.969	66.647
600	76.453	304.022	271.368	19.593	−700.634	−625.528	54.456
700	81.868	316.230	276.917	27.519	−701.253	−612.957	45.739
800	86.201	327.455	282.542	35.930	−701.636	−600.315	39.196
900	89.719	337.818	288.116	44.732	−701.832	−587.636	34.105
1000	92.617	347.426	293.572	53.854	−701.879	−574.944	30.032
1100	95.038	356.370	298.879	63.240	−701.805	−562.253	26.699
1200	97.084	364.730	304.022	72.849	−701.629	−549.574	23.922
1300	98.833	372.571	308.997	82.647	−701.368	−536.913	21.573
1400	100.344	379.952	313.804	92.607	−701.033	−524.274	19.561
1500	101.660	386.921	318.449	102.709	−700.635	−511.662	17.817
30. CHLOROTRIFLUOROMETHANE $CClF_3$ (g)							
298.15	66.886	285.419	285.419	0.000	−707.800	−667.238	116.896
300	67.111	285.834	285.421	0.124	−707.810	−666.986	116.131
400	77.528	306.646	288.187	7.383	−708.153	−653.316	85.313
500	85.013	324.797	293.734	15.532	−708.170	−639.599	66.818
600	90.329	340.794	300.271	24.314	−707.975	−625.901	54.489
700	94.132	355.020	307.096	33.547	−707.654	−612.246	45.686
800	96.899	367.780	313.897	43.106	−707.264	−598.642	39.087
900	98.951	379.317	320.536	52.903	−706.837	−585.090	33.957
1000	100.507	389.827	326.947	62.880	−706.396	−571.586	29.856
1100	101.708	399.465	333.108	72.993	−705.950	−558.126	26.503
1200	102.651	408.357	339.013	83.213	−705.505	−544.707	23.710
1300	103.404	416.604	344.668	93.517	−705.064	−531.326	21.349
1400	104.012	424.290	350.084	103.889	−704.628	−517.977	19.326
1500	104.512	431.484	355.273	114.316	−704.196	−504.660	17.574
31. DICHLORODIFLUOROMETHANE CCl_2F_2 (g)							
298.15	72.476	300.903	300.903	0.000	−486.000	−447.030	78.317
300	72.691	301.352	300.905	0.134	−486.002	−446.788	77.792
400	82.408	323.682	303.883	7.919	−485.945	−433.716	56.637
500	89.063	342.833	309.804	16.514	−485.618	−420.692	43.949
600	93.635	359.500	316.729	25.663	−485.136	−407.751	35.497
700	96.832	374.189	323.909	35.196	−484.576	−394.897	29.467
800	99.121	387.276	331.027	44.999	−483.984	−382.126	24.950
900	100.801	399.053	337.942	55.000	−483.388	−369.429	21.441
1000	102.062	409.742	344.596	65.146	−482.800	−356.799	18.637
1100	103.030	419.517	350.969	75.402	−482.226	−344.227	16.346
1200	103.786	428.515	357.061	85.745	−481.667	−331.706	14.439
1300	104.388	436.847	362.882	96.154	−481.121	−319.232	12.827
1400	104.874	444.602	368.445	106.618	−480.588	−306.799	11.447
1500	105.270	451.851	373.767	117.126	−480.065	−294.404	10.252
32. CHLORODIFLUOROMETHANE $CHClF_2$ (g)							
298.15	55.853	280.915	280.915	0.000	−475.000	−443.845	77.759
300	56.039	281.261	280.916	0.104	−475.028	−443.652	77.246
400	65.395	298.701	283.231	6.188	−476.390	−432.978	56.540
500	73.008	314.145	287.898	13.123	−477.398	−422.001	44.086
600	78.940	328.003	293.448	20.733	−478.103	−410.851	35.767

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
700	83.551	340.533	299.294	28.867	−478.574	−399.603	29.818
800	87.185	351.936	305.172	37.411	−478.870	−388.299	25.353
900	90.100	362.379	310.956	46.280	−479.031	−376.967	21.878
1000	92.475	371.999	316.586	55.413	−479.090	−365.622	19.098
1100	94.433	380.908	322.033	64.761	−479.068	−354.276	16.823
1200	96.066	389.196	327.289	74.289	−478.982	−342.935	14.927
1300	97.438	396.941	332.352	83.966	−478.843	−331.603	13.324
1400	98.601	404.206	337.228	93.769	−478.661	−320.283	11.950
1500	99.593	411.044	341.923	103.681	−478.443	−308.978	10.759
33. METHYLAMINE CH_5N (g)							
298.15	50.053	242.881	242.881	0.000	−22.529	32.734	−5.735
300	50.227	243.196	242.893	0.091	−22.614	33.077	−5.759
400	60.171	258.986	244.975	5.604	−26.846	52.294	−6.829
500	70.057	273.486	249.244	12.121	−30.431	72.510	−7.575
600	78.929	287.063	254.431	19.579	−33.364	93.382	−8.129
700	86.711	299.826	260.008	27.873	−35.712	114.702	−8.559
800	93.545	311.865	265.749	36.893	−37.548	136.316	−8.900
900	99.573	323.239	271.511	46.555	−38.949	158.138	−9.178
1000	104.886	334.006	277.220	56.786	−39.967	180.098	−9.407
1100	109.576	344.233	282.861	67.509	−40.681	201.822	−9.584
1200	113.708	353.944	288.374	78.685	−41.136	224.240	−9.761
1300	117.341	363.190	293.775	90.239	−41.376	246.364	−9.899
1400	120.542	372.012	299.061	102.131	−41.451	268.504	−10.018
1500	123.353	380.426	304.209	114.326	−41.381	290.639	−10.121
34. CHLORINE Cl (g)							
298.15	21.838	165.190	165.190	0.000	121.302	105.306	−18.449
300	21.852	165.325	165.190	0.040	121.311	105.207	−18.318
400	22.467	171.703	166.055	2.259	121.795	99.766	−13.028
500	22.744	176.752	167.708	4.522	122.272	94.203	−9.841
600	22.781	180.905	169.571	6.800	122.734	88.546	−7.709
700	22.692	184.411	171.448	9.074	123.172	82.813	−6.179
800	22.549	187.432	173.261	11.337	123.585	77.019	−5.029
900	22.389	190.079	174.986	13.584	123.971	71.175	−4.131
1000	22.233	192.430	176.615	15.815	124.334	65.289	−3.410
1100	22.089	194.542	178.150	18.031	124.675	59.368	−2.819
1200	21.959	196.458	179.597	20.233	124.996	53.416	−2.325
1300	21.843	198.211	180.963	22.423	125.299	47.439	−1.906
1400	21.742	199.826	182.253	24.602	125.587	41.439	−1.546
1500	21.652	201.323	183.475	26.772	125.861	35.418	−1.233
35. DICHLORINE Cl_2 (g)							
298.15	33.949	223.079	223.079	0.000	0.000	0.000	0.000
300	33.981	223.290	223.080	0.063	0.000	0.000	0.000
400	35.296	233.263	224.431	3.533	0.000	0.000	0.000
500	36.064	241.229	227.021	7.104	0.000	0.000	0.000
600	36.547	247.850	229.956	10.736	0.000	0.000	0.000
700	36.874	253.510	232.926	14.408	0.000	0.000	0.000
800	37.111	258.450	235.815	18.108	0.000	0.000	0.000
900	37.294	262.832	238.578	21.829	0.000	0.000	0.000
1000	37.442	266.769	241.203	25.566	0.000	0.000	0.000
1100	37.567	270.343	243.692	29.316	0.000	0.000	0.000
1200	37.678	273.617	246.052	33.079	0.000	0.000	0.000
1300	37.778	276.637	248.290	36.851	0.000	0.000	0.000
1400	37.872	279.440	250.416	40.634	0.000	0.000	0.000
1500	37.961	282.056	252.439	44.426	0.000	0.000	0.000
36. HYDROGEN CHLORIDE HCl (g)							
298.15	29.136	186.902	186.902	0.000	−92.310	−95.298	16.696
300	29.137	187.082	186.902	0.054	−92.314	−95.317	16.596

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
400	29.175	195.468	188.045	2.969	−92.587	−96.278	12.573
500	29.304	201.990	190.206	5.892	−92.911	−97.164	10.151
600	29.576	207.354	192.630	8.835	−93.249	−97.983	8.530
700	29.988	211.943	195.069	11.812	−93.577	−98.746	7.368
800	30.500	215.980	197.435	14.836	−93.879	−99.464	6.494
900	31.063	219.604	199.700	17.913	−94.149	−100.145	5.812
1000	31.639	222.907	201.858	21.049	−94.384	−100.798	5.265
1100	32.201	225.949	203.912	24.241	−94.587	−101.430	4.816
1200	32.734	228.774	205.867	27.488	−94.760	−102.044	4.442
1300	33.229	231.414	207.732	30.786	−94.908	−102.645	4.124
1400	33.684	233.893	209.513	34.132	−95.035	−103.235	3.852
1500	34.100	236.232	211.217	37.522	−95.146	−103.817	3.615
37. COPPER Cu (cr, l)							
298.15	24.440	33.150	33.150	0.000	0.000	0.000	0.000
300	24.460	33.301	33.150	0.045	0.000	0.000	0.000
400	25.339	40.467	34.122	2.538	0.000	0.000	0.000
500	25.966	46.192	35.982	5.105	0.000	0.000	0.000
600	26.479	50.973	38.093	7.728	0.000	0.000	0.000
700	26.953	55.090	40.234	10.399	0.000	0.000	0.000
800	27.448	58.721	42.322	13.119	0.000	0.000	0.000
900	28.014	61.986	44.328	15.891	0.000	0.000	0.000
1000	28.700	64.971	46.245	18.726	0.000	0.000	0.000
1100	29.553	67.745	48.075	21.637	0.000	0.000	0.000
1200	30.617	70.361	49.824	24.644	0.000	0.000	0.000
1300	31.940	72.862	51.501	27.769	0.000	0.000	0.000
1358	32.844	74.275	52.443	29.647	0.000	0.000	0.000
		PHASE TRANSITION: $\Delta_{trs}H$ = 13.141 kJ/mol, $\Delta_{trs}S$ = 9.676 J/K·mol, cr–l					
1358	32.800	83.951	52.443	42.788	0.000	0.000	0.000
1400	32.800	84.950	53.403	44.166	0.000	0.000	0.000
1500	32.800	87.213	55.583	47.446	0.000	0.000	0.000
38. COPPER Cu (g)							
298.15	20.786	166.397	166.397	0.000	337.600	297.873	−52.185
300	20.786	166.525	166.397	0.038	337.594	297.626	−51.821
400	20.786	172.505	167.213	2.117	337.179	284.364	−37.134
500	20.786	177.143	168.752	4.196	336.691	271.215	−28.333
600	20.786	180.933	170.476	6.274	336.147	258.170	−22.475
700	20.786	184.137	172.205	8.353	335.554	245.221	−18.298
800	20.786	186.913	173.874	10.431	334.913	232.359	−15.171
900	20.786	189.361	175.461	12.510	334.219	219.581	−12.744
1000	20.786	191.551	176.963	14.589	333.463	206.883	−10.806
1100	20.788	193.532	178.380	16.667	332.631	194.265	−9.225
1200	20.793	195.341	179.719	18.746	331.703	181.726	−7.910
1300	20.803	197.006	180.986	20.826	330.657	169.270	−6.801
1400	20.823	198.548	182.186	22.907	316.342	157.305	−5.869
1500	20.856	199.986	183.325	24.991	315.146	145.987	−5.084
39. COPPER OXIDE CuO (cr)							
298.15	42.300	42.740	42.740	0.000	−162.000	−134.277	23.524
300	42.417	43.002	42.741	0.078	−161.994	−134.105	23.349
400	46.783	55.878	44.467	4.564	−161.487	−124.876	16.307
500	49.190	66.596	47.852	9.372	−160.775	−115.803	12.098
600	50.827	75.717	51.755	14.377	−159.973	−106.883	9.305
700	52.099	83.651	55.757	19.526	−159.124	−98.102	7.320
800	53.178	90.680	59.691	24.791	−158.247	−89.444	5.840
900	54.144	97.000	63.491	30.158	−157.356	−80.897	4.695
1000	55.040	102.751	67.134	35.617	−156.462	−72.450	3.784
1100	55.890	108.037	70.615	41.164	−155.582	−64.091	3.043
1200	56.709	112.936	73.941	46.794	−154.733	−55.812	2.429

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
1300	57.507	117.507	77.118	52.505	−153.940	−47.601	1.913
1400	58.288	121.797	80.158	58.295	−166.354	−39.043	1.457
1500	59.057	125.845	83.070	64.163	−165.589	−29.975	1.044
40. DICOPPER OXIDE Cu_2O (cr)							
298.15	62.600	92.550	92.550	0.000	−173.100	−150.344	26.339
300	62.721	92.938	92.551	0.116	−173.102	−150.203	26.152
400	67.587	111.712	95.078	6.654	−173.036	−142.572	18.618
500	70.784	127.155	99.995	13.580	−172.772	−134.984	14.101
600	73.323	140.291	105.643	20.789	−172.389	−127.460	11.096
700	75.552	151.764	111.429	28.235	−171.914	−120.009	8.955
800	77.616	161.989	117.121	35.894	−171.363	−112.631	7.354
900	79.584	171.245	122.629	43.755	−170.750	−105.325	6.113
1000	81.492	179.729	127.920	51.809	−170.097	−98.091	5.124
1100	83.360	187.584	132.992	60.052	−169.431	−90.922	4.317
1200	85.202	194.917	137.850	68.480	−168.791	−83.814	3.648
1300	87.026	201.808	142.507	77.092	−168.223	−76.756	3.084
1400	88.836	208.324	146.978	85.885	−194.030	−68.926	2.572
1500	90.636	214.515	151.276	94.858	−193.438	−60.010	2.090
41. COPPER DICHLORIDE $CuCl_2$ (cr, l)							
298.15	71.880	108.070	108.070	0.000	−218.000	−173.826	30.453
300	71.998	108.515	108.071	0.133	−217.975	−173.552	30.218
400	76.338	129.899	110.957	7.577	−216.494	−158.962	20.758
500	78.654	147.204	116.532	15.336	−214.873	−144.765	15.123
600	80.175	161.687	122.884	23.282	−213.182	−130.901	11.396
675	81.056	171.183	127.732	29.329	−211.185	−120.693	9.340
		PHASE TRANSITION: $\Delta_{trs}H$ = 0.700 kJ/mol, $\Delta_{trs}S$ = 1.037 J/K·mol, crII–crI					
675	82.400	172.220	127.732	30.029	−211.185	−120.693	9.340
700	82.400	175.216	129.375	32.089	−210.719	−117.350	8.757
800	82.400	186.219	135.808	40.329	−208.898	−104.137	6.799
871	82.400	193.226	140.207	46.179	−192.649	−94.893	5.691
		PHASE TRANSITION: $\Delta_{trs}H$ = 15.001 kJ/mol, $\Delta_{trs}S$ = 17.221 J/K·mol, crI–l					
871	100.000	210.447	140.207	61.180	−192.649	−94.893	5.691
900	100.000	213.723	142.523	64.080	−191.640	−91.655	5.319
1000	100.000	224.259	150.179	74.080	−188.212	−80.730	4.217
1100	100.000	233.790	157.353	84.080	−184.873	−70.144	3.331
1130.75	100.000	236.547	159.470	87.155	−183.867	−66.951	3.093
42. COPPER DICHLORIDE $CuCl_2$ (g)							
298.15	56.814	278.418	278.418	0.000	−43.268	−49.883	8.739
300	56.869	278.769	278.419	0.105	−43.271	−49.924	8.692
400	58.992	295.456	280.679	5.911	−43.428	−52.119	6.806
500	60.111	308.752	285.010	11.871	−43.606	−54.271	5.670
600	60.761	319.774	289.911	17.918	−43.814	−56.385	4.909
700	61.168	329.173	294.865	24.015	−44.060	−58.462	4.362
800	61.439	337.360	299.677	30.147	−44.349	−60.500	3.950
900	61.630	344.608	304.274	36.301	−44.688	−62.499	3.627
1000	61.776	351.109	308.638	42.471	−45.088	−64.457	3.367
1100	61.900	357.003	312.771	48.655	−45.566	−66.372	3.152
1200	62.022	362.394	316.685	54.851	−46.139	−68.239	2.970
1300	62.159	367.364	320.395	61.060	−46.829	−70.053	2.815
1400	62.325	371.976	323.916	67.284	−60.784	−71.404	2.664
1500	62.531	376.283	327.265	73.526	−61.613	−72.133	2.512
43. FLUORINE F (g)							
298.15	22.746	158.750	158.750	0.000	79.380	62.280	−10.911
300	22.742	158.891	158.750	0.042	79.393	62.173	−10.825
400	22.432	165.394	159.639	2.302	80.043	56.332	−7.356
500	22.100	170.363	161.307	4.528	80.587	50.340	−5.259

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
600	21.832	174.368	163.161	6.724	81.046	44.246	−3.852
700	21.629	177.717	165.008	8.897	81.442	38.081	−2.842
800	21.475	180.595	166.780	11.052	81.792	31.862	−2.080
900	21.357	183.117	168.458	13.193	82.106	25.601	−1.486
1000	21.266	185.362	170.039	15.324	82.391	19.308	−1.009
1100	21.194	187.386	171.525	17.447	82.654	12.986	−0.617
1200	21.137	189.227	172.925	19.563	82.897	6.642	−0.289
1300	21.091	190.917	174.245	21.675	83.123	0.278	−0.011
1400	21.054	192.479	175.492	23.782	83.335	−6.103	0.228
1500	21.022	193.930	176.673	25.886	83.533	−12.498	0.435
44. DIFLUORINE F_2 (g)							
298.15	31.304	202.790	202.790	0.000	0.000	0.000	0.000
300	31.337	202.984	202.790	0.058	0.000	0.000	0.000
400	32.995	212.233	204.040	3.277	0.000	0.000	0.000
500	34.258	219.739	206.453	6.643	0.000	0.000	0.000
600	35.171	226.070	209.208	10.117	0.000	0.000	0.000
700	35.839	231.545	212.017	13.669	0.000	0.000	0.000
800	36.343	236.365	214.765	17.279	0.000	0.000	0.000
900	36.740	240.669	217.409	20.934	0.000	0.000	0.000
1000	37.065	244.557	219.932	24.625	0.000	0.000	0.000
1100	37.342	248.103	222.334	28.346	0.000	0.000	0.000
1200	37.588	251.363	224.619	32.093	0.000	0.000	0.000
1300	37.811	254.381	226.794	35.863	0.000	0.000	0.000
1400	38.019	257.191	228.866	39.654	0.000	0.000	0.000
1500	38.214	259.820	230.843	43.466	0.000	0.000	0.000
45. HYDROGEN FLUORIDE HF (g)							
298.15	29.137	173.776	173.776	0.000	−273.300	−275.399	48.248
300	29.137	173.956	173.776	0.054	−273.302	−275.412	47.953
400	29.149	182.340	174.919	2.968	−273.450	−276.096	36.054
500	29.172	188.846	177.078	5.884	−273.679	−276.733	28.910
600	29.230	194.169	179.496	8.804	−273.961	−277.318	24.142
700	29.350	198.683	181.923	11.732	−274.277	−277.852	20.733
800	29.549	202.614	184.269	14.676	−274.614	−278.340	18.174
900	29.827	206.110	186.505	17.645	−274.961	−278.785	16.180
1000	30.169	209.270	188.626	20.644	−275.309	−279.191	14.583
1100	30.558	212.163	190.636	23.680	−275.652	−279.563	13.275
1200	30.974	214.840	192.543	26.756	−275.988	−279.904	12.184
1300	31.403	217.336	194.355	29.875	−276.315	−280.217	11.259
1400	31.831	219.679	196.081	33.037	−276.631	−280.505	10.466
1500	32.250	221.889	197.729	36.241	−276.937	−280.771	9.777
46. GERMANIUM Ge (cr, l)							
298.15	23.222	31.090	31.090	0.000	0.000	0.000	0.000
300	23.249	31.234	31.090	0.043	0.000	0.000	0.000
400	24.310	38.083	32.017	2.426	0.000	0.000	0.000
500	24.962	43.582	33.798	4.892	0.000	0.000	0.000
600	25.452	48.178	35.822	7.414	0.000	0.000	0.000
700	25.867	52.133	37.876	9.980	0.000	0.000	0.000
800	26.240	55.612	39.880	12.586	0.000	0.000	0.000
900	26.591	58.723	41.804	15.227	0.000	0.000	0.000
1000	26.926	61.542	43.639	17.903	0.000	0.000	0.000
1100	27.252	64.124	45.386	20.612	0.000	0.000	0.000
1200	27.571	66.509	47.048	23.353	0.000	0.000	0.000
1211.4	27.608	66.770	47.232	23.668	0.000	0.000	0.000
		PHASE TRANSITION: $\Delta_{trs} H$ = 37.030 kJ/mol, $\Delta_{trs} S$ = 30.568 J/K·mol, cr–l					
1211.4	27.600	97.338	47.232	60.698	0.000	0.000	0.000
1300	27.600	99.286	50.714	63.143	0.000	0.000	0.000
1400	27.600	101.331	54.258	65.903	0.000	0.000	0.000
1500	27.600	103.236	57.460	68.663	0.000	0.000	0.000

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
47. GERMANIUM Ge (g)							
298.15	30.733	167.903	167.903	0.000	367.800	327.009	−57.290
300	30.757	168.094	167.904	0.057	367.814	326.756	−56.893
400	31.071	177.025	169.119	3.162	368.536	312.959	−40.868
500	30.360	183.893	171.415	6.239	369.147	298.991	−31.235
600	29.265	189.334	173.965	9.222	369.608	284.914	−24.804
700	28.102	193.758	176.487	12.090	369.910	270.773	−20.205
800	27.029	197.439	178.882	14.845	370.060	256.598	−16.754
900	26.108	200.567	181.122	17.501	370.073	242.414	−14.069
1000	25.349	203.277	183.205	20.072	369.969	228.234	−11.922
1100	24.741	205.664	185.141	22.575	369.763	214.069	−10.165
1200	24.264	207.795	186.941	25.025	369.471	199.928	−8.703
1300	23.898	209.722	188.621	27.432	332.088	188.521	−7.575
1400	23.624	211.483	190.192	29.807	331.704	177.492	−6.622
1500	23.426	213.105	191.666	32.159	331.296	166.491	−5.798
48. GERMANIUM DIOXIDE GeO_2 (cr, l)							
298.15	50.166	39.710	39.710	0.000	−580.200	−521.605	91.382
300	50.475	40.021	39.711	0.093	−580.204	−521.242	90.755
400	61.281	56.248	41.850	5.759	−579.893	−501.610	65.503
500	66.273	70.519	46.191	12.164	−579.013	−482.134	50.368
600	69.089	82.872	51.299	18.943	−577.915	−462.859	40.295
700	70.974	93.671	56.597	25.952	−576.729	−443.776	33.115
800	72.449	103.247	61.841	33.125	−575.498	−424.866	27.741
900	73.764	111.857	66.928	40.436	−574.235	−406.113	23.570
1000	75.049	119.696	71.819	47.877	−572.934	−387.502	20.241
1100	76.378	126.910	76.504	55.447	−571.582	−369.024	17.523
1200	77.796	133.616	80.987	63.155	−570.166	−350.671	15.264
1300	79.332	139.903	85.279	71.010	−605.685	−329.732	13.249
1308	79.460	140.390	85.615	71.646	−584.059	−328.034	13.100
	PHASE TRANSITION: $\Delta_{trs}H$ = 21.500 kJ/mol, $\Delta_{trs}S$ = 16.437 J/K·mol, crII–crI						
1308	80.075	156.827	85.615	93.146	−584.059	−328.034	13.100
1388	81.297	161.617	89.858	99.601	−565.504	−312.415	11.757
	PHASE TRANSITION: $\Delta_{trs}H$ = 17.200 kJ/mol, $\Delta_{trs}S$ = 12.392 J/K·mol, crI–l						
1388	78.500	174.009	89.858	116.801	−565.504	−312.415	11.757
1400	78.500	174.685	90.582	117.743	−565.328	−310.228	11.575
1500	78.500	180.100	96.372	125.593	−563.882	−292.057	10.170
49. GERMANIUM TETRACHLORIDE $GeCl_4$ (g)							
298.15	95.918	348.393	348.393	0.000	−500.000	−461.582	80.866
300	96.041	348.987	348.395	0.178	−499.991	−461.343	80.326
400	100.750	377.342	352.229	10.045	−499.447	−448.540	58.573
500	103.206	400.114	359.604	20.255	−498.845	−435.882	45.536
600	104.624	419.067	367.980	30.652	−498.234	−423.347	36.855
700	105.509	435.266	376.463	41.162	−497.634	−410.914	30.662
800	106.096	449.396	384.715	51.744	−497.057	−398.565	26.023
900	106.504	461.917	392.611	62.375	−496.509	−386.287	22.419
1000	106.799	473.155	400.113	73.041	−495.993	−374.068	19.539
1100	107.020	483.344	407.224	83.733	−495.512	−361.899	17.185
1200	107.189	492.664	413.961	94.444	−495.067	−349.772	15.225
1300	107.320	501.249	420.349	105.169	−531.677	−334.973	13.459
1400	107.425	509.206	426.416	115.907	−531.265	−319.857	11.934
1500	107.509	516.621	432.185	126.654	−530.861	−304.771	10.613
50. HYDROGEN H (g)							
298.15	20.786	114.716	114.716	0.000	217.998	203.276	−35.613
300	20.786	114.845	114.716	0.038	218.010	203.185	−35.377
400	20.786	120.824	115.532	2.117	218.635	198.149	−25.875
500	20.786	125.463	117.071	4.196	219.253	192.956	−20.158

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
600	20.786	129.252	118.795	6.274	219.867	187.639	−16.335
700	20.786	132.457	120.524	8.353	220.476	182.219	−13.597
800	20.786	135.232	122.193	10.431	221.079	176.712	−11.538
900	20.786	137.680	123.780	12.510	221.670	171.131	−9.932
1000	20.786	139.870	125.282	14.589	222.247	165.485	−8.644
1100	20.786	141.852	126.700	16.667	222.806	159.781	−7.587
1200	20.786	143.660	128.039	18.746	223.345	154.028	−6.705
1300	20.786	145.324	129.305	20.824	223.864	148.230	−5.956
1400	20.786	146.864	130.505	22.903	224.360	142.393	−5.313
1500	20.786	148.298	131.644	24.982	224.835	136.522	−4.754
51. DIHYDROGEN H_2 (g)							
298.15	28.836	130.680	130.680	0.000	0.000	0.000	0.000
300	28.849	130.858	130.680	0.053	0.000	0.000	0.000
400	29.181	139.217	131.818	2.960	0.000	0.000	0.000
500	29.260	145.738	133.974	5.882	0.000	0.000	0.000
600	29.327	151.078	136.393	8.811	0.000	0.000	0.000
700	29.440	155.607	138.822	11.749	0.000	0.000	0.000
800	29.623	159.549	141.172	14.702	0.000	0.000	0.000
900	29.880	163.052	143.412	17.676	0.000	0.000	0.000
1000	30.204	166.217	145.537	20.680	0.000	0.000	0.000
1100	30.580	169.113	147.550	23.719	0.000	0.000	0.000
1200	30.991	171.791	149.460	26.797	0.000	0.000	0.000
1300	31.422	174.288	151.275	29.918	0.000	0.000	0.000
1400	31.860	176.633	153.003	33.082	0.000	0.000	0.000
1500	32.296	178.846	154.653	36.290	0.000	0.000	0.000
52. HYDROXYL OH (g)							
298.15	29.886	183.737	183.737	0.000	39.349	34.631	−6.067
300	29.879	183.922	183.738	0.055	39.350	34.602	−6.025
400	29.604	192.476	184.906	3.028	39.384	33.012	−4.311
500	29.495	199.067	187.104	5.982	39.347	31.422	−3.283
600	29.513	204.445	189.560	8.931	39.252	29.845	−2.598
700	29.655	209.003	192.020	11.888	39.113	28.287	−2.111
800	29.914	212.979	194.396	14.866	38.945	26.752	−1.747
900	30.265	216.522	196.661	17.874	38.763	25.239	−1.465
1000	30.682	219.731	198.810	20.921	38.577	23.746	−1.240
1100	31.135	222.677	200.848	24.012	38.393	22.272	−1.058
1200	31.603	225.406	202.782	27.149	38.215	20.814	−0.906
1300	32.069	227.954	204.621	30.332	38.046	19.371	−0.778
1400	32.522	230.347	206.374	33.562	37.886	17.941	−0.669
1500	32.956	232.606	208.048	36.836	37.735	16.521	−0.575
53. WATER H_2O (l)							
298.15	75.300	69.950	69.950	0.000	−285.830	−237.141	41.546
300	75.281	70.416	69.951	0.139	−285.771	−236.839	41.237
373.21	76.079	86.896	71.715	5.666	−283.454	−225.160	31.513
54. WATER H_2O (g)							
298.15	33.598	188.832	188.832	0.000	−241.826	−228.582	40.046
300	33.606	189.040	188.833	0.062	−241.844	−228.500	39.785
400	34.283	198.791	190.158	3.453	−242.845	−223.900	29.238
500	35.259	206.542	192.685	6.929	−243.822	−219.050	22.884
600	36.371	213.067	195.552	10.509	−244.751	−214.008	18.631
700	37.557	218.762	198.469	14.205	−245.620	−208.814	15.582
800	38.800	223.858	201.329	18.023	−246.424	−203.501	13.287
900	40.084	228.501	204.094	21.966	−247.158	−198.091	11.497
1000	41.385	232.792	206.752	26.040	−247.820	−192.603	10.060
1100	42.675	236.797	209.303	30.243	−248.410	−187.052	8.882
1200	43.932	240.565	211.753	34.574	−248.933	−181.450	7.898
1300	45.138	244.129	214.108	39.028	−249.392	−175.807	7.064

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
1400	46.281	247.516	216.374	43.599	−249.792	−170.132	6.348
1500	47.356	250.746	218.559	48.282	−250.139	−164.429	5.726
55. IODINE I (g)							
298.15	20.786	180.787	180.787	0.000	106.760	70.172	−12.294
300	20.786	180.915	180.787	0.038	106.748	69.945	−12.178
400	20.786	186.895	181.602	2.117	97.974	58.060	−7.582
500	20.786	191.533	183.142	4.196	75.988	50.202	−5.244
600	20.786	195.323	184.866	6.274	76.190	45.025	−3.920
700	20.786	198.527	186.594	8.353	76.385	39.816	−2.971
800	20.787	201.303	188.263	10.432	76.574	34.579	−2.258
900	20.789	203.751	189.851	12.510	76.757	29.319	−1.702
1000	20.795	205.942	191.352	14.589	76.936	24.038	−1.256
1100	20.806	207.924	192.770	16.669	77.109	18.740	−0.890
1200	20.824	209.735	194.110	18.751	77.277	13.426	−0.584
1300	20.851	211.403	195.377	20.835	77.440	8.098	−0.325
1400	20.889	212.950	196.577	22.921	77.596	2.758	−0.103
1500	20.936	214.392	197.717	25.013	77.745	−2.592	0.090
56. DIIODINE I_2 (cr, l)							
298.15	54.440	116.139	116.139	0.000	0.000	0.000	0.000
300	54.518	116.476	116.140	0.101	0.000	0.000	0.000
386.75	61.531	131.039	117.884	5.088	0.000	0.000	0.000
		PHASE TRANSITION: $\Delta_{trs}H$ = 15.665 kJ/mol, $\Delta_{trs}S$ = 40.504 J/K·mol, cr–l					
386.75	79.555	171.543	117.884	20.753	0.000	0.000	0.000
400	79.555	174.223	119.706	21.807	0.000	0.000	0.000
457.67	79.555	184.938	127.266	26.395	0.000	0.000	0.000
57. DIIODINE I_2 (g)							
298.15	36.887	260.685	260.685	0.000	62.420	19.324	−3.385
300	36.897	260.913	260.685	0.068	62.387	19.056	−3.318
400	37.256	271.584	262.138	3.778	44.391	5.447	−0.711
457.67	37.385	276.610	263.652	5.931		pressure = 1 bar	
500	37.464	279.921	264.891	7.515	0.000	0.000	0.000
600	37.613	286.765	267.983	11.269	0.000	0.000	0.000
700	37.735	292.573	271.092	15.037	0.000	0.000	0.000
800	37.847	297.619	274.099	18.816	0.000	0.000	0.000
900	37.956	302.083	276.965	22.606	0.000	0.000	0.000
1000	38.070	306.088	279.681	26.407	0.000	0.000	0.000
1100	38.196	309.722	282.249	30.220	0.000	0.000	0.000
1200	38.341	313.052	284.679	34.047	0.000	0.000	0.000
1300	38.514	316.127	286.981	37.890	0.000	0.000	0.000
1400	38.719	318.989	289.166	41.751	0.000	0.000	0.000
1500	38.959	321.668	291.245	45.635	0.000	0.000	0.000
58. HYDROGEN IODIDE HI (g)							
298.15	29.157	206.589	206.589	0.000	26.500	1.700	−0.298
300	29.158	206.769	206.589	0.054	26.477	1.546	−0.269
400	29.329	215.176	207.734	2.977	17.093	−6.289	0.821
500	29.738	221.760	209.904	5.928	−5.481	−9.946	1.039
600	30.351	227.233	212.348	8.931	−5.819	−10.806	0.941
700	31.070	231.965	214.820	12.002	−6.101	−11.614	0.867
800	31.807	236.162	217.230	15.145	−6.323	−12.386	0.809
900	32.511	239.950	219.548	18.362	−6.489	−13.133	0.762
1000	33.156	243.409	221.763	21.646	−6.608	−13.865	0.724
1100	33.735	246.597	223.878	24.991	−6.689	−14.586	0.693
1200	34.249	249.555	225.896	28.391	−6.741	−15.302	0.666
1300	34.703	252.314	227.823	31.839	−6.775	−16.014	0.643
1400	35.106	254.901	229.666	35.330	−6.797	−16.723	0.624
1500	35.463	257.336	231.430	38.858	−6.814	−17.432	0.607

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
59. POTASSIUM K (cr, l)							
298.15	29.600	64.680	64.680	0.000	0.000	0.000	0.000
300	29.671	64.863	64.681	0.055	0.000	0.000	0.000
336.86	32.130	68.422	64.896	1.188	0.000	0.000	0.000
PHASE TRANSITION: $\Delta_{trs} H$ = 2.321 kJ/mol, $\Delta_{trs} S$ = 6.891 J/K·mol, cr–l							
336.86	32.129	75.313	64.896	3.509	0.000	0.000	0.000
400	31.552	80.784	66.986	5.519	0.000	0.000	0.000
500	30.741	87.734	70.469	8.632	0.000	0.000	0.000
600	30.158	93.283	73.824	11.675	0.000	0.000	0.000
700	29.851	97.905	76.943	14.673	0.000	0.000	0.000
800	29.838	101.887	79.818	17.655	0.000	0.000	0.000
900	30.130	105.415	82.470	20.651	0.000	0.000	0.000
1000	30.730	108.618	84.927	23.691	0.000	0.000	0.000
1039.4	31.053	109.812	85.847	24.908	0.000	0.000	0.000
60. POTASSIUM K (g)							
298.15	20.786	160.340	160.340	0.000	89.000	60.479	–10.596
300	20.786	160.468	160.340	0.038	88.984	60.302	–10.499
400	20.786	166.448	161.155	2.117	85.598	51.332	–6.703
500	20.786	171.086	162.695	4.196	84.563	42.887	–4.480
600	20.786	174.876	164.419	6.274	83.599	34.643	–3.016
700	20.786	178.080	166.148	8.353	82.680	26.557	–1.982
800	20.786	180.856	167.817	10.431	81.776	18.601	–1.215
900	20.786	183.304	169.404	12.510	80.859	10.759	–0.624
1000	20.786	185.494	170.905	14.589	79.897	3.021	–0.158
1039.4	20.786	186.297	171.474	15.408		pressure = 1 bar	
1100	20.786	187.475	172.323	16.667	0.000	0.000	0.000
1200	20.786	189.284	173.662	18.746	0.000	0.000	0.000
1300	20.789	190.948	174.929	20.825	0.000	0.000	0.000
1400	20.793	192.489	176.129	22.904	0.000	0.000	0.000
1500	20.801	193.923	177.268	24.983	0.000	0.000	0.000
61. DIPOTASSIUM OXIDE K_2O (cr, l)							
298.15	72.000	96.000	96.000	0.000	–361.700	–321.171	56.267
300	72.130	96.446	96.001	0.133	–361.704	–320.920	55.876
400	79.154	118.158	98.914	7.698	–366.554	–306.416	40.013
500	86.178	136.575	104.647	15.964	–366.043	–291.423	30.444
590	92.500	151.348	110.662	24.005	–364.204	–278.079	24.619
PHASE TRANSITION: $\Delta_{trs} H$ = 0.700 kJ/mol, $\Delta_{trs} S$ = 1.186 J/K·mol, crIII–crII							
590	100.000	152.534	110.662	24.705	–364.204	–278.079	24.619
600	100.000	154.215	111.374	25.705	–363.968	–276.621	24.082
645	100.000	161.447	114.618	30.205	–358.901	–270.109	21.874
PHASE TRANSITION: $\Delta_{trs} H$ = 4.000 kJ/mol, $\Delta_{trs} S$ = 6.202 J/K·mol, crII–crI							
645	100.000	167.649	114.618	34.205	–358.901	–270.109	21.874
700	100.000	175.832	119.111	39.705	–357.592	–262.592	19.595
800	100.000	189.185	127.054	49.705	–355.224	–249.183	16.270
900	100.000	200.963	134.625	59.705	–352.919	–236.067	13.701
1000	100.000	211.499	141.794	69.705	–350.732	–223.202	11.659
1013	100.000	212.791	142.697	71.005	–323.459	–221.546	11.424
PHASE TRANSITION: $\Delta_{trs} H$ = 27.000 kJ/mol, $\Delta_{trs} S$ =26.654 J/K·mol, crI–l							
1013	100.000	239.444	142.697	98.005	–323.459	–221.546	11.424
1100	100.000	247.684	150.679	106.705	–479.439	–203.633	9.670
1200	100.000	256.385	159.131	116.705	–475.371	–178.740	7.780
1300	100.000	264.389	166.924	126.705	–471.321	–154.185	6.195
1400	100.000	271.800	174.154	136.705	–467.287	–129.941	4.848
1500	100.000	278.699	180.896	146.705	–463.268	–105.986	3.691

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
62. POTASSIUM HYDROXIDE KOH (cr, l)							
298.15	64.900	78.870	78.870	0.000	−424.580	−378.747	66.354
300	65.038	79.272	78.871	0.120	−424.569	−378.463	65.895
400	72.519	99.007	81.512	6.998	−426.094	−362.765	47.372
500	80.000	115.993	86.745	14.624	−424.572	−347.093	36.260
520	81.496	119.159	87.931	16.239	−417.725	−344.002	34.555
PHASE TRANSITION: $\Delta_{trs}H$ = 6.450 kJ/mol, $\Delta_{trs}S$ = 12.404 J/K·mol, crII–crI							
520	79.000	131.563	87.931	22.689	−417.725	−344.002	34.555
600	79.000	142.868	94.520	29.009	−416.274	−332.766	28.969
678	79.000	152.523	100.649	35.171	−405.464	−321.998	24.807
PHASE TRANSITION: $\Delta_{trs}H$ = 9.400 kJ/mol, $\Delta_{trs}S$ = 13.865 J/K·mol, crI–l							
678	83.000	166.388	100.649	44.571	−405.464	−321.998	24.807
700	83.000	169.038	102.757	46.397	−404.981	−319.297	23.826
800	83.000	180.121	111.750	54.697	−402.808	−307.206	20.058
900	83.000	189.897	119.901	62.997	−400.694	−295.383	17.143
1000	83.000	198.642	127.345	71.297	−398.668	−283.791	14.824
1100	83.000	206.553	134.192	79.597	−475.618	−267.780	12.716
1200	83.000	213.775	140.527	87.897	−472.711	−249.014	10.839
1300	83.000	220.418	146.421	96.197	−469.843	−230.490	9.261
1400	83.000	226.569	151.929	104.497	−467.011	−212.184	7.917
1500	83.000	232.296	157.098	112.797	−464.217	−194.080	6.758
63. POTASSIUM HYDROXIDE KOH (g)							
298.15	49.184	238.283	238.283	0.000	−227.989	−229.685	40.239
300	49.236	238.588	238.284	0.091	−228.007	−229.696	39.993
400	51.178	253.053	240.243	5.124	−231.377	−229.667	29.991
500	52.178	264.591	243.998	10.296	−232.309	−229.129	23.937
600	52.804	274.163	248.251	15.547	−233.145	−228.413	19.885
700	53.296	282.340	252.551	20.853	−233.934	−227.562	16.981
800	53.758	289.487	256.730	26.206	−234.708	−226.599	14.795
900	54.229	295.846	260.730	31.605	−235.495	−225.538	13.090
1000	54.713	301.585	264.533	37.052	−236.322	−224.388	11.721
1100	55.203	306.823	268.143	42.548	−316.077	−218.535	10.377
1200	55.686	311.647	271.570	48.092	−315.925	−209.674	9.127
1300	56.153	316.122	274.827	53.684	−315.764	−200.826	8.069
1400	56.598	320.300	277.927	59.322	−315.595	−191.991	7.163
1500	57.016	324.220	280.884	65.003	−315.420	−183.169	6.378
64. POTASSIUM CHLORIDE KCl (cr, l)							
298.15	51.300	82.570	82.570	0.000	−436.490	−408.568	71.579
300	51.333	82.887	82.571	0.095	−436.481	−408.395	71.107
400	52.977	97.886	84.605	5.312	−438.463	−398.651	52.058
500	54.448	109.867	88.498	10.685	−437.990	−388.749	40.612
600	55.885	119.921	92.919	16.201	−437.332	−378.960	32.991
700	57.425	128.649	97.413	21.865	−436.502	−369.295	27.557
800	59.205	136.430	101.812	27.694	−435.505	−359.760	23.490
900	61.361	143.523	106.058	33.719	−434.337	−350.360	20.334
1000	64.032	150.121	110.138	39.983	−432.981	−341.100	17.817
1044	65.405	152.908	111.882	42.830	−485.450	−336.720	16.847
PHASE TRANSITION: $\Delta_{trs}H$ = 26.320 kJ/mol, $\Delta_{trs}S$ = 25.210 J/K·mol, cr–l							
1044	72.000	178.118	111.882	69.150	−485.450	−336.720	16.847
1100	72.000	181.880	115.351	73.182	−483.633	−328.790	15.613
1200	72.000	188.145	121.160	80.382	−480.393	−314.856	13.705
1300	72.000	193.908	126.537	87.582	−477.158	−301.192	12.102
1400	72.000	199.244	131.542	94.782	−473.928	−287.778	10.737
1500	72.000	204.211	136.223	101.982	−470.704	−274.594	9.562

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
65. POTASSIUM CHLORIDE KCl (g)							
298.15	36.505	239.091	239.091	0.000	−214.575	−233.320	40.876
300	36.518	239.317	239.092	0.068	−214.594	−233.436	40.644
400	37.066	249.904	240.532	3.749	−218.112	−239.107	31.224
500	37.384	258.212	243.267	7.473	−219.287	−244.219	25.513
600	37.597	265.048	246.344	11.222	−220.396	−249.100	21.686
700	37.769	270.857	249.441	14.991	−221.461	−253.799	18.938
800	37.907	275.910	252.441	18.775	−222.509	−258.347	16.868
900	38.041	280.382	255.302	22.572	−223.568	−262.764	15.250
1000	38.162	284.397	258.014	26.383	−224.667	−267.061	13.950
1100	38.279	288.039	260.581	30.205	−304.696	−266.627	12.661
1200	38.401	291.375	263.010	34.039	−304.821	−263.161	11.455
1300	38.518	294.454	265.312	37.885	−304.941	−259.684	10.434
1400	38.639	297.313	267.496	41.743	−305.053	−256.199	9.559
1500	38.761	299.983	269.574	45.613	−305.159	−252.706	8.800
66. DINITROGEN N_2 (g)							
298.15	29.124	191.608	191.608	0.000	0.000	0.000	0.000
300	29.125	191.788	191.608	0.054	0.000	0.000	0.000
400	29.249	200.180	192.752	2.971	0.000	0.000	0.000
500	29.580	206.738	194.916	5.911	0.000	0.000	0.000
600	30.109	212.175	197.352	8.894	0.000	0.000	0.000
700	30.754	216.864	199.812	11.936	0.000	0.000	0.000
800	31.433	221.015	202.208	15.046	0.000	0.000	0.000
900	32.090	224.756	204.509	18.222	0.000	0.000	0.000
1000	32.696	228.169	206.706	21.462	0.000	0.000	0.000
1100	33.241	231.311	208.802	24.759	0.000	0.000	0.000
1200	33.723	234.224	210.801	28.108	0.000	0.000	0.000
1300	34.147	236.941	212.708	31.502	0.000	0.000	0.000
1400	34.517	239.485	214.531	34.936	0.000	0.000	0.000
1500	34.842	241.878	216.275	38.404	0.000	0.000	0.000
67. NITRIC OXIDE NO (g)							
298.15	29.862	210.745	210.745	0.000	91.277	87.590	−15.345
300	29.858	210.930	210.746	0.055	91.278	87.567	−15.247
400	29.954	219.519	211.916	3.041	91.320	86.323	−11.272
500	30.493	226.255	214.133	6.061	91.340	85.071	−8.887
600	31.243	231.879	216.635	9.147	91.354	83.816	−7.297
700	32.031	236.754	219.168	12.310	91.369	82.558	−6.160
800	32.770	241.081	221.642	15.551	91.386	81.298	−5.308
900	33.425	244.979	224.022	18.862	91.405	80.036	−4.645
1000	33.990	248.531	226.298	22.233	91.426	78.772	−4.115
1100	34.473	251.794	228.469	25.657	91.445	77.505	−3.680
1200	34.883	254.811	230.540	29.125	91.464	76.237	−3.318
1300	35.234	257.618	232.516	32.632	91.481	74.967	−3.012
1400	35.533	260.240	234.404	36.170	91.495	73.697	−2.750
1500	35.792	262.700	236.209	39.737	91.506	72.425	−2.522
68. NITROGEN DIOXIDE NO_2 (g)							
298.15	37.178	240.166	240.166	0.000	34.193	52.316	−9.165
300	37.236	240.397	240.167	0.069	34.181	52.429	−9.129
400	40.513	251.554	241.666	3.955	33.637	58.600	−7.652
500	43.664	260.939	244.605	8.167	33.319	64.882	−6.778
600	46.383	269.147	248.026	12.673	33.174	71.211	−6.199
700	48.612	276.471	251.575	17.427	33.151	77.553	−5.787
800	50.405	283.083	255.107	22.381	33.213	83.893	−5.478
900	51.844	289.106	258.555	27.496	33.334	90.221	−5.236
1000	53.007	294.631	261.891	32.741	33.495	96.534	−5.042
1100	53.956	299.729	265.102	38.090	33.686	102.828	−4.883
1200	54.741	304.459	268.187	43.526	33.898	109.105	−4.749

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
1300	55.399	308.867	271.148	49.034	34.124	115.363	−4.635
1400	55.960	312.994	273.992	54.603	34.360	121.603	−4.537
1500	56.446	316.871	276.722	60.224	34.604	127.827	−4.451
69. AMMONIA NH_3 (g)							
298.15	35.630	192.768	192.768	0.000	−45.940	−16.407	2.874
300	35.678	192.989	192.769	0.066	−45.981	−16.223	2.825
400	38.674	203.647	194.202	3.778	−48.087	−5.980	0.781
500	41.994	212.633	197.011	7.811	−49.908	4.764	−0.498
600	45.229	220.578	200.289	12.174	−51.430	15.846	−1.379
700	48.269	227.781	203.709	16.850	−52.682	27.161	−2.027
800	51.112	234.414	207.138	21.821	−53.695	38.639	−2.523
900	53.769	240.589	210.516	27.066	−54.499	50.231	−2.915
1000	56.244	246.384	213.816	32.569	−55.122	61.903	−3.233
1100	58.535	251.854	217.027	38.309	−55.589	73.629	−3.496
1200	60.644	257.039	220.147	44.270	−55.920	85.392	−3.717
1300	62.576	261.970	223.176	50.432	−56.136	97.177	−3.905
1400	64.339	266.673	226.117	56.779	−56.251	108.975	−4.066
1500	65.945	271.168	228.971	63.295	−56.282	120.779	−4.206
70. OXYGEN O (g)							
298.15	21.911	161.058	161.058	0.000	249.180	231.743	−40.600
300	21.901	161.194	161.059	0.041	249.193	231.635	−40.331
400	21.482	167.430	161.912	2.207	249.874	225.677	−29.470
500	21.257	172.197	163.511	4.343	250.481	219.556	−22.937
600	21.124	176.060	165.290	6.462	251.019	213.319	−18.571
700	21.040	179.310	167.067	8.570	251.500	206.997	−15.446
800	20.984	182.115	168.777	10.671	251.932	200.610	−13.098
900	20.944	184.584	170.399	12.767	252.325	194.171	−11.269
1000	20.915	186.789	171.930	14.860	252.686	187.689	−9.804
1100	20.893	188.782	173.372	16.950	253.022	181.173	−8.603
1200	20.877	190.599	174.733	19.039	253.335	174.628	−7.601
1300	20.864	192.270	176.019	21.126	253.630	168.057	−6.753
1400	20.853	193.815	177.236	23.212	253.908	161.463	−6.024
1500	20.845	195.254	178.389	25.296	254.171	154.851	−5.392
71. DIOXYGEN O_2 (g)							
298.15	29.378	205.148	205.148	0.000	0.000	0.000	0.000
300	29.387	205.330	205.148	0.054	0.000	0.000	0.000
400	30.109	213.873	206.308	3.026	0.000	0.000	0.000
500	31.094	220.695	208.525	6.085	0.000	0.000	0.000
600	32.095	226.454	211.045	9.245	0.000	0.000	0.000
700	32.987	231.470	213.612	12.500	0.000	0.000	0.000
800	33.741	235.925	216.128	15.838	0.000	0.000	0.000
900	34.365	239.937	218.554	19.244	0.000	0.000	0.000
1000	34.881	243.585	220.878	22.707	0.000	0.000	0.000
1100	35.314	246.930	223.096	26.217	0.000	0.000	0.000
1200	35.683	250.019	225.213	29.768	0.000	0.000	0.000
1300	36.006	252.888	227.233	33.352	0.000	0.000	0.000
1400	36.297	255.568	229.162	36.968	0.000	0.000	0.000
1500	36.567	258.081	231.007	40.611	0.000	0.000	0.000
72. SULFUR S (cr, l)							
298.15	22.690	32.070	32.070	0.000	0.000	0.000	0.000
300	22.737	32.210	32.070	0.042	0.000	0.000	0.000
368.3	24.237	37.030	32.554	1.649	0.000	0.000	0.000
PHASE TRANSITION: $\Delta_{trs}H$ = 0.401 kJ/mol, $\Delta_{trs}S$ = 1.089 J/K·mol, crII–crI							
368.3	24.773	38.119	32.553	2.050	0.000	0.000	0.000
388.36	25.180	39.444	32.875	2.551	0.000	0.000	0.000

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
			PHASE TRANSITION: $\Delta_{trs}H$ = 1.722 kJ/mol, $\Delta_{trs}S$ = 4.431 J/K·mol, crI–l				
388.36	31.710	43.875	32.872	4.273	0.000	0.000	0.000
400	32.369	44.824	33.206	4.647	0.000	0.000	0.000
500	38.026	53.578	36.411	8.584	0.000	0.000	0.000
600	34.371	60.116	39.842	12.164	0.000	0.000	0.000
700	32.451	65.278	43.120	15.511	0.000	0.000	0.000
800	32.000	69.557	46.163	18.715	0.000	0.000	0.000
882.38	32.000	72.693	48.496	21.351	0.000	0.000	0.000
73. SULFUR S (g)							
298.15	23.673	167.828	167.828	0.000	277.180	236.704	–41.469
300	23.669	167.974	167.828	0.044	277.182	236.453	–41.170
400	23.233	174.730	168.752	2.391	274.924	222.962	–29.115
500	22.741	179.860	170.482	4.689	273.286	210.145	–21.953
600	22.338	183.969	172.398	6.942	271.958	197.646	–17.206
700	22.031	187.388	174.302	9.160	270.829	185.352	–13.831
800	21.800	190.314	176.125	11.351	269.816	173.210	–11.309
900	21.624	192.871	177.847	13.522	215.723	162.258	–9.417
1000	21.489	195.142	179.465	15.677	216.018	156.301	–8.164
1100	21.386	197.185	180.985	17.821	216.284	150.317	–7.138
1200	21.307	199.043	182.413	19.955	216.525	144.309	–6.282
1300	21.249	200.746	183.759	22.083	216.743	138.282	–5.556
1400	21.209	202.319	185.029	24.206	216.940	132.239	–4.934
1500	21.186	203.781	186.231	26.325	217.119	126.182	–4.394
74. DISULFUR S_2 (g)							
298.15	32.505	228.165	228.165	0.000	128.600	79.696	–13.962
300	32.540	228.366	228.165	0.060	128.576	79.393	–13.823
400	34.108	237.956	229.462	3.398	122.703	63.380	–8.276
500	35.133	245.686	231.959	6.863	118.296	49.031	–5.122
600	35.815	252.156	234.800	10.413	114.685	35.530	–3.093
700	36.305	257.715	237.686	14.020	111.599	22.588	–1.685
800	36.697	262.589	240.501	17.671	108.841	10.060	–0.657
882.38	36.985	266.200	242.734	20.706	pressure = 1 bar		
900	37.045	266.932	243.201	21.358	0.000	0.000	0.000
1000	37.377	270.852	245.773	25.079	0.000	0.000	0.000
1100	37.704	274.430	248.218	28.833	0.000	0.000	0.000
1200	38.030	277.725	250.541	32.620	0.000	0.000	0.000
1300	38.353	280.781	252.751	36.439	0.000	0.000	0.000
1400	38.669	283.635	254.856	40.290	0.000	0.000	0.000
1500	38.976	286.314	256.865	44.173	0.000	0.000	0.000
75. OCTASULFUR S_8 (g)							
298.15	156.500	432.536	432.536	0.000	101.277	48.810	–8.551
300	156.768	433.505	432.539	0.290	101.231	48.484	–8.442
400	167.125	480.190	438.834	16.542	80.642	32.003	–4.179
500	173.181	518.176	451.022	33.577	66.185	21.409	–2.237
600	177.936	550.180	464.951	51.137	55.101	13.549	–1.180
700	182.441	577.948	479.152	69.157	46.349	7.343	–0.548
800	186.764	602.596	493.071	87.620	39.177	2.263	–0.148
900	190.595	624.821	506.495	106.494	–392.062	6.554	–0.380
1000	193.618	645.067	519.355	125.712	–387.728	50.614	–2.644
1100	195.684	663.625	531.639	145.185	–383.272	94.233	–4.475
1200	196.825	680.707	543.359	164.817	–378.786	137.444	–5.983
1300	197.195	696.480	554.539	184.524	–374.356	180.283	–7.244
1400	196.988	711.089	565.206	204.237	–370.048	222.785	–8.312
1500	196.396	724.662	575.389	223.909	–365.905	264.984	–9.227
76. SULFUR DIOXIDE SO_2 (g)							
298.15	39.842	248.219	248.219	0.000	–296.810	–300.090	52.574
300	39.909	248.466	248.220	0.074	–296.833	–300.110	52.253

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
400	43.427	260.435	249.828	4.243	−300.240	−300.935	39.298
500	46.490	270.465	252.978	8.744	−302.735	−300.831	31.427
600	48.938	279.167	256.634	13.520	−304.699	−300.258	26.139
700	50.829	286.859	260.413	18.513	−306.308	−299.386	22.340
800	52.282	293.746	264.157	23.671	−307.691	−298.302	19.477
900	53.407	299.971	267.796	28.958	−362.075	−295.987	17.178
1000	54.290	305.646	271.301	34.345	−362.012	−288.647	15.077
1100	54.993	310.855	274.664	39.810	−361.934	−281.314	13.358
1200	55.564	315.665	277.882	45.339	−361.849	−273.989	11.926
1300	56.033	320.131	280.963	50.920	−361.763	−266.671	10.715
1400	56.426	324.299	283.911	56.543	−361.680	−259.359	9.677
1500	56.759	328.203	286.735	62.203	−361.605	−252.053	8.777
77. SILICON Si (cr)							
298.15	19.789	18.810	18.810	0.000	0.000	0.000	0.000
300	19.855	18.933	18.810	0.037	0.000	0.000	0.000
400	22.301	25.023	19.624	2.160	0.000	0.000	0.000
500	23.610	30.152	21.231	4.461	0.000	0.000	0.000
600	24.472	34.537	23.092	6.867	0.000	0.000	0.000
700	25.124	38.361	25.006	9.348	0.000	0.000	0.000
800	25.662	41.752	26.891	11.888	0.000	0.000	0.000
900	26.135	44.802	28.715	14.478	0.000	0.000	0.000
1000	26.568	47.578	30.464	17.114	0.000	0.000	0.000
1100	26.974	50.130	32.138	19.791	0.000	0.000	0.000
1200	27.362	52.493	33.737	22.508	0.000	0.000	0.000
1300	27.737	54.698	35.265	25.263	0.000	0.000	0.000
1400	28.103	56.767	36.728	28.055	0.000	0.000	0.000
1500	28.462	58.719	38.130	30.883	0.000	0.000	0.000
78. SILICON Si (g)							
298.15	22.251	167.980	167.980	0.000	450.000	405.525	−71.045
300	22.234	168.117	167.980	0.041	450.004	405.249	−70.559
400	21.613	174.416	168.843	2.229	450.070	390.312	−50.969
500	21.316	179.204	170.456	4.374	449.913	375.388	−39.216
600	21.153	183.074	172.246	6.497	449.630	360.508	−31.385
700	21.057	186.327	174.032	8.607	449.259	345.682	−25.795
800	21.000	189.135	175.748	10.709	448.821	330.915	−21.606
900	20.971	191.606	177.375	12.808	448.329	316.205	−18.352
1000	20.968	193.815	178.911	14.904	447.791	301.553	−15.751
1100	20.989	195.815	180.358	17.002	447.211	286.957	−13.626
1200	21.033	197.643	181.723	19.103	446.595	272.416	−11.858
1300	21.099	199.329	183.014	21.209	445.946	257.927	−10.364
1400	21.183	200.895	184.236	23.323	445.268	243.489	−9.085
1500	21.282	202.360	185.396	25.446	444.563	229.101	−7.978
79. SILICON DIOXIDE SiO_2 (cr)							
298.15	44.602	41.460	41.460	0.000	−910.700	−856.288	150.016
300	44.712	41.736	41.461	0.083	−910.708	−855.951	149.032
400	53.477	55.744	43.311	4.973	−910.912	−837.651	109.385
500	60.533	68.505	47.094	10.705	−910.540	−819.369	85.598
600	64.452	79.919	51.633	16.971	−909.841	−801.197	69.749
700	68.234	90.114	56.414	23.590	−908.958	−783.157	58.439
800	76.224	99.674	61.226	30.758	−907.668	−765.265	49.966
848	82.967	104.298	63.533	34.569	−906.310	−756.747	46.613
	PHASE TRANSITION: $\Delta_{trs}H$ = 0.411 kJ/mol, $\Delta_{trs}S$ = 0.484 J/K·mol, crII–crII′						
848	67.446	104.782	63.532	34.980	−906.310	−756.747	46.613
900	67.953	108.811	66.033	38.500	−905.922	−747.587	43.388
1000	68.941	116.021	70.676	45.345	−905.176	−730.034	38.133
1100	69.940	122.639	75.104	52.289	−904.420	−712.557	33.836
1200	70.947	128.768	79.323	59.333	−901.382	−695.148	30.259

	J/K·mol			kJ/mol			
T/K	C_p°	S°	$-(G^\circ-H^\circ(T_r))/T$	$H^\circ-H^\circ(T_r)$	$\Delta_f H^\circ$	$\Delta_f G^\circ$	Log K_f
	PHASE TRANSITION: $\Delta_{trs} H$ = 2.261 kJ/mol, $\Delta_{trs} S$ = 1.883 J/K·mol, crII′–crI						
1200	71.199	130.651	79.323	61.594	−901.382	−695.148	30.259
1300	71.743	136.372	83.494	68.742	−900.574	−677.994	27.242
1400	72.249	141.707	87.463	75.941	−899.782	−660.903	24.658
1500	72.739	146.709	91.248	83.191	−899.004	−643.867	22.421
80. SILICON TETRACHLORIDE $SiCl_4$ (g)							
298.15	90.404	331.446	331.446	0.000	−662.200	−622.390	109.039
300	90.562	332.006	331.448	0.167	−662.195	−622.143	108.323
400	96.893	359.019	335.088	9.572	−661.853	−608.841	79.505
500	100.449	381.058	342.147	19.456	−661.413	−595.637	62.225
600	102.587	399.576	350.216	29.616	−660.924	−582.527	50.713
700	103.954	415.500	358.432	39.948	−660.417	−569.501	42.496
800	104.875	429.445	366.455	50.392	−659.912	−556.548	36.338
900	105.523	441.837	374.155	60.914	−659.422	−543.657	31.553
1000	105.995	452.981	381.490	71.491	−658.954	−530.819	27.727
1100	106.349	463.101	388.456	82.109	−658.515	−518.027	24.599
1200	106.620	472.366	395.068	92.758	−658.107	−505.274	21.994
1300	106.834	480.909	401.347	103.431	−657.735	−492.553	19.791
1400	107.003	488.833	407.316	114.123	−657.400	−479.860	17.904
1500	107.141	496.220	413.000	124.830	−657.104	−467.189	16.269

THERMODYNAMIC PROPERTIES OF AQUEOUS SYSTEMS

This table contains standard state thermodynamic properties of ions and neutral species in aqueous solution. It includes enthalpy and Gibbs energy of formation, entropy, and heat capacity, and thus serves as a companion to the preceding table, "Standard Thermodynamic Properties of Chemical Substances". The standard state is the hypothetical ideal solution with molality m = 1 mol/kg (mean ionic molality $m_{\pm}$ in the case of a species which is assumed to dissociate at infinite dilution). Further details on conventions may be found in Reference 1.

Cations are listed by formula in the first part of the table, followed by anions and finally neutral species. All values refer to standard conditions of 25°C and 100 kPa pressure.

References

1. Wagman, D. D., Evans, W. H., Parker, V. B., Schumm, R. H., Halow, I., Bailey, S. M., Churney, K. L., and Nuttall, R. L., *The NBS Tables of Chemical Thermodynamic Properties, J. Phys. Chem. Ref. Data*, Vol. 11, Suppl. 2, 1982.
2. Zemaitis, J. F., Clark, D. M., Rafal, M., and Scrivner, N. C., *Handbook of Aqueous Electrolyte Thermodynamics*, American Institute of Chemical Engineers, New York, 1986.

Species	$\Delta_f H°$/ kJ mol^{-1}	$\Delta_f G°$/ kJ mol^{-1}	$S°$/ J mol^{-1}K^{-1}	C_p/ J mol^{-1}K^{-1}
Cations				
Ag^{+}	105.6	77.1	72.7	21.8
Al^{+3}	−531.0	−485.0	−321.7	
$AlOH^{+2}$		−694.1		
Ba^{+2}	−537.6	−560.8	9.6	
$BaOH^{+}$		−730.5		
Be^{+2}	−382.8	−379.7	−129.7	
Bi^{+3}		82.8		
$BiOH^{+2}$		−146.4		
Ca^{+2}	−542.8	−553.6	−53.1	
$CaOH^{+}$		−718.4		
Cd^{+2}	−75.9	−77.6	−73.2	
$CdOH^{+}$		−261.1		
Ce^{+3}	−696.2	−672.0	−205.0	
Ce^{+4}	−537.2	−503.8	−301.0	
Co^{+2}	−58.2	−54.4	−113.0	
Co^{+3}	92.0	134.0	−305.0	
Cr^{+2}	−143.5			
Cs^{+}	−258.3	−292.0	133.1	−10.5
Cu^{+}	71.7	50.0	40.6	
Cu^{+2}	64.8	65.5	−99.6	
Dy^{+3}	−699.0	−665.0	−231.0	21.0
Er^{+3}	−705.4	−669.1	−244.3	21.0
Eu^{+2}	−527.0	−540.2	−8.0	
Eu^{+3}	−605.0	−574.1	−222.0	8.0
Fe^{+2}	−89.1	−78.9	−137.7	
Fe^{+3}	−48.5	−4.7	−315.9	
$FeOH^{+}$	−324.7	−277.4	−29.0	
$FeOH^{+2}$	−290.8	−229.4	−142.0	
$Fe(OH)_2^{+}$		−438.0		
Ga^{+2}		−88.0		
Ga^{+3}	−211.7	−159.0	−331.0	
$GaOH^{+2}$		−380.3		
$Ga(OH)_2^{+}$		−597.4		
Gd^{+3}	−686.0	−661.0	−205.9	
H^{+}	0	0	0	0
Hg^{+2}	171.1	164.4	−32.2	
Hg_2^{+2}	172.4	153.5	84.5	
$HgOH^{+}$	−84.5	−52.3	71.0	
Ho^{+3}	−705.0	−673.7	−226.8	17.0
In^{+}		−12.1		
In^{+2}		−50.7		
In^{+3}	−105.0	−98.0	−151.0	
$InOH^{+2}$	−370.3	−313.0	−88.0	
$In(OH)_2^{+}$	−619.0	−525.0	25.0	
K^{+}	−252.4	−283.3	102.5	21.8
La^{+3}	−707.1	−683.7	−217.6	−13.0
Li^{+}	−278.5	−293.3	13.4	68.6
Lu^{+3}	−665.0	−628.0	−264.0	25.0
LuF^{+2}		−931.4		
Mg^{+2}	−466.9	−454.8	−138.1	
$MgOH^{+}$		−626.7		
Mn^{+2}	−220.8	−228.1	−73.6	50.0
$MnOH^{+}$	−450.6	−405.0	−17.0	
NH_4^{+}	−132.5	−79.3	113.4	79.9
$N_2H_5^{+}$	−7.5	82.5	151.0	70.3
Na^{+}	−240.1	−261.9	59.0	46.4
Nd^{+3}	−696.2	−671.6	−206.7	−21.0
Ni^{+2}	−54.0	−45.6	−128.9	
$NiOH^{+}$	−287.9	−227.6	−71.0	
PH_4^{+}		92.1		
Pa^{+4}	−619.0			
Pb^{+2}	−1.7	−24.4	10.5	
$PbOH^{+}$		−226.3		
Pd^{+2}	149.0	176.5	−184.0	
Po^{+2}		71.0		
Po^{+4}		293.0		
Pr^{+3}	−704.6	−679.1	−209.0	−29.0
Pt^{+2}		254.8		
Ra^{+2}	−527.6	−561.5	54.0	
Rb^{+}	−251.2	−284.0	121.5	
Re^{+}		−33.0		
Sc^{+3}	−614.2	−586.6	−255.0	
$ScOH^{+2}$	−861.5	−801.2	−134.0	
Sm^{+2}		−497.5		
Sm^{+3}	−691.6	−666.6	−211.7	−21.0
Sn^{+2}	−8.8	−27.2	−17.0	
$SnOH^{+}$	−286.2	−254.8	50.0	
Sr^{+2}	−545.8	−559.5	−32.6	
$SrOH^{+}$		−721.3		
Tb^{+3}	−682.8	−651.9	−226.0	17.0
$Te(OH)_3^{+}$	−608.4	−496.1	111.7	
Th^{+4}	−769.0	−705.1	−422.6	
$Th(OH)^{+3}$	−1030.1	−920.5	−343.0	
$Th(OH)_2^{+2}$	−1282.4	−1140.9	−218.0	
Tl^{+}	5.4	−32.4	125.5	

Species	$\Delta_f H°$/ kJ mol^{-1}	$\Delta_f G°$/ kJ mol^{-1}	$S°$/ J mol^{-1}K^{-1}	C_p/ J mol^{-1}K^{-1}
Tl^{+3}	196.6	214.6	−192.0	
$TlOH^{+2}$		−15.9		
$Tl(OH)_2^{+}$		−244.7		
Tm^{+3}	−697.9	−662.0	−243.0	25.0
U^{+3}	−489.1	−476.2	−188.0	
U^{+4}	−591.2	−531.9	−410.0	
Y^{+3}	−723.4	−693.8	−251.0	
$Y_2(OH)_2^{+4}$		−1780.3		
Yb^{+2}		−527.0		
Yb^{+3}	−674.5	−644.0	−238.0	25.0
$Y(OH)^{+2}$		−879.1		
Zn^{+2}	−153.9	−147.1	−112.1	46.0
$ZnOH^{+}$		−330.1		
Anions				
AlO_2^-	−930.9	−830.9	−36.8	
$Al(OH)_4^-$	−1502.5	−1305.3	102.9	
AsO_2^-	−429.0	−350.0	40.6	
AsO_4^{-3}	−888.1	−648.4	−162.8	
BF_4^-	−1574.9	−1486.9	180.0	
BH_4^-	48.2	114.4	110.5	
BO_2^-	−772.4	−678.9	−37.2	
$B_4O_7^{-2}$		−2604.8		
BeO_2^{-2}	−790.8	−640.1	−159.0	
Br^-	−121.6	−104.0	82.4	−141.8
BrO^-	−94.1	−33.4	42.0	
BrO_3^-	−67.1	18.6	161.7	
BrO_4^-	13.0	118.1	199.6	
$CHOO^-$	−425.6	−351.0	92.0	−87.9
CH_3COO^-	−486.0	−369.3	86.6	−6.3
$C_2O_4^{-2}$	−825.1	−673.9	45.6	
$C_2O_4H^-$	−818.4	−698.3	149.4	
Cl^-	−167.2	−131.2	56.5	−136.4
ClO^-	−107.1	−36.8	42.0	
ClO_2^-	−66.5	17.2	101.3	
ClO_3^-	−104.0	−8.0	162.3	
ClO_4^-	−129.3	−8.5	182.0	
CN^-	150.6	172.4	94.1	
CO_3^{-2}	−677.1	−527.8	−56.9	
CrO_4^{-2}	−881.2	−727.8	50.2	
$Cr_2O_7^{-2}$	−1490.3	−1301.1	261.9	
F^-	−332.6	−278.8	−13.8	−106.7
$Fe(CN)_6^{-3}$	561.9	729.4	270.3	
$Fe(CN)_6^{-4}$	455.6	695.1	95.0	
$HB_4O_7^-$		−2685.1		
HCO_3^-	−692.0	−586.8	91.2	
HF_2^-	−649.9	−578.1	92.5	
HPO_3F^-		−1198.2		
HPO_4^{-2}	−1292.1	−1089.2	−33.5	
$HP_2O_7^{-3}$	−2274.8	−1972.2	46.0	
HS^-	−17.6	12.1	62.8	
HSO_3^-	−626.2	−527.7	139.7	
HSO_4^-	−887.3	−755.9	131.8	−84.0
$HS_2O_4^-$		−614.5		
HSe^-	15.9	44.0	79.0	
$HSeO_3^-$	−514.6	−411.5	135.1	
$HSeO_4^-$	−581.6	−452.2	149.4	
$H_2AsO_3^-$	−714.8	−587.1	110.5	
$H_2AsO_4^-$	−909.6	−753.2	117.0	
$H_2PO_4^-$	−1296.3	−1130.2	90.4	
$H_2P_2O_7^{-2}$	−2278.6	−2010.2	163.0	
I^-	−55.2	−51.6	111.3	−142.3
IO^-	−107.5	−38.5	−5.4	
IO_3^-	−221.3	−128.0	118.4	
IO_4^-	−151.5	−58.5	222.0	
MnO_4^-	−541.4	−447.2	191.2	−82.0
MnO_4^{-2}	−653.0	−500.7	59.0	
MoO_4^{-2}	−997.9	−836.3	27.2	
NO_2^-	−104.6	−32.2	123.0	−97.5
NO_3^-	−207.4	−111.3	146.4	−86.6
N_3^-	275.1	348.2	107.9	
OCN^-	−146.0	−97.4	106.7	
OH^-	−230.0	−157.2	−10.8	−148.5
PO_4^{-3}	−1277.4	−1018.7	−220.5	
$P_2O_7^{-4}$	−2271.1	−1919.0	−117.0	
Re^-	46.0	10.1	230.0	
S^{-2}	33.1	85.8	−14.6	
SCN^-	76.4	92.7	144.3	−40.2
SO_3^{-2}	−635.5	−486.5	−29.0	
SO_4^{-2}	−909.3	−744.5	20.1	−293.0
S_2^{-2}	30.1	79.5	28.5	
$S_2O_3^{-2}$	−652.3	−522.5	67.0	
$S_2O_4^{-2}$	−753.5	−600.3	92.0	
$S_2O_8^{-2}$	−1344.7	−1114.9	244.3	
Se^{-2}		129.3		
SeO_3^{-2}	−509.2	−369.8	13.0	
SeO_4^{-2}	−599.1	−441.3	54.0	
VO_3^-	−888.3	−783.6	50.0	
VO_4^{-3}		−899.0		
WO_4^{-2}	−1075.7			
Neutral species				
AgBr	−16.0	−26.9	155.2	−120.1
AgCl	−61.6	−54.1	129.3	−114.6
AgF	−227.1	−201.7	59.0	−84.9
AgI	50.4	25.5	184.1	−120.5
$AgNO_3$	−101.8	−34.2	219.2	−64.9
Ag_2SO_4	−698.1	−590.3	165.7	−251.0
$AlBr_3$	−895.0	−799.0	−74.5	
$AlCl_3$	−1033.0	−879.0	−152.3	
AlF_3	−1531.0	−1322.0	−363.2	
AlI_3	−699.0	−640.0	12.1	
$Al_2(SO_4)_3$	−3791.0	−3205.0	−583.2	
$BaBr_2$	−780.7	−768.7	174.5	
$BaCO_3$	−1214.8	−1088.6	−47.3	
$BaCl_2$	−872.0	−823.2	122.6	
BaF_2	−1202.9	−1118.4	−18.0	
$Ba(HCO_3)_2$	−1921.6	−1734.3	192.0	
BaI_2	−648.0	−663.9	232.2	
$Ba(NO_3)_2$	−952.4	−783.3	302.5	
$BaSO_4$	−1446.9	−1305.3	29.7	
$BeSO_4$	−1292.0	−1124.3	−109.6	
CCl_3COOH	−516.3			
$CHCl_2COOH$	−512.1			
CHOOCs	−683.8	−643.0	226.0	
CHOOH	−425.6	−351.0	92.0	−87.9
CHOOK	−677.9	−634.2	192.0	−66.1
$CHOONH_4$	−558.1	−430.4	205.0	−7.9
CHOONa	−665.7	−612.9	151.0	−41.4
CHOORb	−676.7	−635.1	213.0	
$CH_2ClCOOH$	−501.3			
CH_3COOCs	−744.3	−661.3	219.7	

Species	$\Delta_f H°$/ kJ mol^{-1}	$\Delta_f G°$/ kJ mol^{-1}	$S°$/ J mol^{-1}K^{-1}	C_p/ J mol^{-1}K^{-1}
CH_3COOH	−486.0	−369.3	86.6	−6.3
CH_3COOK	−738.4	−652.6	189.1	15.5
CH_3COONH_4	−618.5	−448.6	200.0	73.6
CH_3COONa	−726.1	−631.2	145.6	40.2
CH_3COORb	−737.2	−653.3	207.9	
$(COOH)_2$	−825.1	−673.9	45.6	
$(CH_3)_3N$	−76.0	93.1	133.5	
$CaBr_2$	−785.9	−761.5	111.7	
$CaCO_3$	−1220.0	−1081.4	−110.0	
$CaCl_2$	−877.1	−816.0	59.8	
CaF_2	−1208.1	−1111.2	−80.8	
CaI_2	−653.2	−656.7	169.5	
$Ca(NO_3)_2$	−957.6	−776.1	239.7	
$CaSO_4$	−1452.1	−1298.1	−33.1	
$CdBr_2$	−319.0	−285.5	91.6	
$CdCl_2$	−410.2	−340.1	39.7	
CdF_2	−741.2	−635.2	−100.8	
CdI_2	−186.3	−180.8	149.4	
$Cd(NO_3)_2$	−490.6	−300.1	219.7	
$CdSO_4$	−985.2	−822.1	−53.1	
$CeCl_3$	−1197.5	−1065.6	−38.0	
$CoBr_2$	−301.2	−262.3	50.0	
$CoCl_2$	−392.5	−316.7		
CoI_2	−168.6	−157.7	109.0	
$Co(NO_3)_2$	−472.8	−276.9	180.0	
$CoSO_4$	−967.3	−799.1	−92.0	
$CsBr$	−379.8	−396.0	215.5	
$CsCl$	−425.4	−423.2	189.5	−146.9
CsF	−590.9	−570.8	119.2	
$CsHCO_3$	−950.3	−878.8	224.3	
$CsHSO_4$	−1145.6	−1047.9	264.8	
CsI	−313.5	−343.6	244.3	−152.7
$CsNO_3$	−465.6	−403.3	279.5	−99.0
Cs_2CO_3	−1193.7	−1111.9	209.2	
Cs_2S	−483.7	−498.3	251.0	
Cs_2SO_4	−1425.8	−1328.6	286.2	
Cs_2Se		−454.8		
$Cu(NO_3)_2$	−350.0	−157.0	193.3	
$CuSO_4$	−844.5	−679.0	−79.5	
$DyCl_3$	−1197.0	−1059.0	−61.9	−389.0
$ErCl_3$	−1207.1	−1062.7	−75.3	−389.0
$EuCl_2$	−862.0			
$EuCl_3$	−1106.2	−967.7	−54.0	−402.0
$FeBr_2$	−332.2	−286.8	27.2	
$FeBr_3$	−413.4	−316.7	−68.6	
$FeCl_2$	−423.4	−341.3	−24.7	
$FeCl_3$	−550.2	−398.3	−146.4	
FeF_2	−754.4	−636.5	−165.3	
FeF_3	−1046.4	−840.9	−357.3	
FeI_2	−199.6	−182.1	84.9	
FeI_3	−214.2	−159.4	18.0	
$Fe(NO_3)_3$	−670.7	−338.3	123.4	
$FeSO_4$	−998.3	−823.4	−117.6	
$Fe_2(SO_4)_3$	−2825.0	−2242.8	−571.5	
$GdCl_3$	−1188.0	−1059.0	−36.8	−410.0
HBr	−121.6	−104.0	82.4	−141.8
HCN	150.6	172.4	94.1	
HCl	−167.2	−131.2	56.5	−136.4
HF	−332.6	−278.8	−13.8	−106.7
HI	−55.2	−51.6	111.3	−142.3
HNO_3	−207.4	−111.3	146.4	−86.6
$HSCN$	76.4	92.7	144.3	−40.2
H_2SO_4	−909.3	−744.5	20.1	−293.0
$HoCl_3$	−1206.7	−1067.3	−57.7	−393.0
KBr	−373.9	−387.2	184.9	−120.1
KCl	−419.5	−414.5	159.0	−114.6
KF	−585.0	−562.1	88.7	−84.9
$KHCO_3$	−944.4	−870.0	193.7	
$KHSO_4$	−1139.7	−1039.2	234.3	−63.0
KI	−307.6	−334.9	213.8	−120.5
KNO_3	−459.7	−394.5	248.9	−64.9
K_2CO_3	−1181.9	−1094.4	148.1	
K_2S	−471.5	−480.7	190.4	
K_2SO_4	−1414.0	−1311.1	225.1	−251.0
K_2Se		−437.2		
$LaCl_3$	−1208.8	−1077.3	−50.0	−423.0
$LiBr$	−400.0	−397.3	95.8	−73.2
$LiCl$	−445.6	−424.6	69.9	−67.8
LiF	−611.1	−571.9	−0.4	−38.1
LiI	−333.7	−344.8	124.7	−73.6
$LiNO_3$	−485.9	−404.5	160.2	−18.0
Li_2CO_3	−1234.1	−1114.6	−29.7	
Li_2SO_4	−1466.2	−1331.2	47.3	−155.6
$LuCl_3$	−1167.0	−1021.0	−96.0	−385.0
$MgBr_2$	−709.9	−662.7	26.8	
$MgCl_2$	−801.2	−717.1	−25.1	
MgI_2	−577.2	−558.1	84.5	
$Mg(NO_3)_2$	−881.6	−677.3	154.8	
$MgSO_4$	−1376.1	−1199.5	−118.0	
$MnBr_2$	−464.0			
$MnCl_2$	−555.1	−490.8	38.9	−222.0
MnI_2	−331.0			
$Mn(NO_3)_2$	−635.5	−450.9	218.0	−121.0
$MnSO_4$	−1130.1	−972.7	−53.6	−243.0
NH_4Br	−254.1	−183.3	195.8	−61.9
NH_4BrO_3	−199.6	−60.7	275.1	
NH_4CN	18.0	93.0	207.5	
NH_4Cl	−299.7	−210.5	169.9	−56.5
NH_4ClO_3	−236.5	−87.3	275.7	
NH_4ClO_4	−261.8	−87.8	295.4	
NH_4F	−465.1	−358.1	99.6	−26.8
NH_4HCO_3	−824.5	−666.1	204.6	
NH_4HS	−150.2	−67.2	176.1	
NH_4HSO_3	−758.7	−607.0	253.1	
NH_4HSO_4	−1019.9	−835.2	245.2	−3.8
NH_4HSeO_4	−714.2	−531.6	262.8	
$NH_4H_2AsO_3$	−847.3	−666.4	223.8	
$NH_4H_2AsO_4$	−1042.1	−832.5	230.5	
$NH_4H_2PO_4$	−1428.8	−1209.6	203.8	
$NH_4H_3P_2O_7$	−2409.1	−2102.6	326.0	
NH_4I	−187.7	−130.9	224.7	−62.3
NH_4IO_3	−354.0	−207.4	231.8	
NH_4NO_2	−237.2	−111.6	236.4	−17.6
NH_4NO_3	−339.9	−190.6	259.8	−6.7
NH_4OH	−362.5	−236.5	102.5	−68.6
NH_4SCN	−56.1	13.4	257.7	39.7
$(NH_4)_2CO_3$	−942.2	−686.4	169.9	
$(NH_4)_2CrO_4$	−1146.2	−886.4	277.0	
$(NH_4)_2Cr_2O_7$	−1755.2	−1459.5	488.7	
$(NH_4)_2HAsO_4$	−1171.4	−873.2	225.1	

Species	$\Delta_f H°$/ kJ mol^{-1}	$\Delta_f G°$/ kJ mol^{-1}	$S°$/ J mol^{-1}K^{-1}	C_p/ J mol^{-1}K^{-1}
$(NH_4)_2HPO_4$	−1557.2	−1247.8	193.3	
$(NH_4)_2S$	−231.8	−72.6	212.1	
$(NH_4)_2SO_3$	−900.4	−645.0	197.5	
$(NH_4)_2SO_4$	−1174.3	−903.1	246.9	−133.1
$(NH_4)_2SeO_4$	−864.0	−599.8	280.7	
$(NH_4)_3PO_4$	−1674.9	−1256.6	117.0	
NaBr	−361.7	−365.8	141.4	−95.4
NaCl	−407.3	−393.1	115.5	−90.0
NaF	−572.8	−540.7	45.2	−60.2
$NaHCO_3$	−932.1	−848.7	150.2	
$NaHSO_4$	−1127.5	−1017.8	190.8	−38.0
NaI	−295.3	−313.5	170.3	−95.8
$NaNO_3$	−447.5	−373.2	205.4	−40.2
Na_2CO_3	−1157.4	−1051.6	61.1	
Na_2S	−447.3	−438.1	103.3	
Na_2SO_4	−1389.5	−1268.4	138.1	−201.0
Na_2Se		−394.6		
$NdCl_3$	−1197.9	−1065.6	−37.7	−431.0
$NiBr_2$	−297.1	−253.6	36.0	
$NiCl_2$	−388.3	−307.9	−15.1	
NiF_2	−719.2	−603.3	−156.5	
NiI_2	−164.4	−149.0	93.7	
$Ni(NO_3)_2$	−468.6	−268.5	164.0	
$NiSO_4$	−963.2	−790.3	−108.8	
$PbBr_2$	−244.8	−232.3	175.3	
$PbCl_2$	−336.0	−286.9	123.4	
PbF_2	−666.9	−582.0	−17.2	
PbI_2	−112.1	−127.6	233.0	
$Pb(NO_3)_2$	−416.3	−246.9	303.3	
$PrCl_3$	−1206.2	−1072.7	−42.0	−439.0
$RaCl_2$	−861.9	−823.8	167.0	
$Ra(NO_3)_2$	−942.2	−784.0	347.0	
$RaSO_4$	−1436.8	−1306.2	75.0	
RbBr	−372.7	−387.9	203.9	
RbCl	−418.3	−415.2	178.0	
RbF	−583.8	−562.8	107.5	
$RbHCO_3$	−943.2	−870.8	212.7	
$RbHSO_4$	−1138.5	−1039.9	253.1	
RbI	−306.4	−335.6	232.6	
$RbNO_3$	−458.5	−395.2	267.8	
Rb_2CO_3	−1179.5	−1095.8	186.2	
Rb_2S	−469.4	−482.0	228.4	
Rb_2SO_4	−1411.6	−1312.5	263.2	
$SmCl_3$	−1193.3	−1060.2	−42.7	−431.0
$SrBr_2$	−788.9	−767.4	132.2	
$SrCO_3$	−1222.9	−1087.3	−89.5	
$SrCl_2$	−880.1	−821.9	80.3	
SrI_2	−656.2	−662.6	190.0	
$Sr(NO_3)_2$	−960.5	−782.0	260.2	
$SrSO_4$	−1455.1	−1304.0	−12.6	
$TbCl_3$	−1184.1	−1045.5	−59.0	−393.0
TlBr	−116.2	−136.4	207.9	
$TlBr_3$	−168.2	−97.1	54.0	
TlCl	−161.8	−163.6	182.0	
$TlCl_3$	−305.0	−179.0	−23.0	
TlF	−327.3	−311.2	111.7	
TlI	−49.8	−84.0	236.8	
$TlNO_3$	−202.0	−143.7	272.0	
Tl_2SO_4	−898.6	−809.3	271.1	
$TmCl_3$	−1199.1	−1055.6	−75.0	−385.0
UCl_4	−1259.8	−1056.8	−184.0	
UO_2CO_3	−1696.6	−1481.5	−154.4	
$UO_2(NO_3)_2$	−1434.3	−1176.0	195.4	
UO_2SO_4	−1928.8	−1698.2	−77.4	
$YbCl_3$	−1176.1	−1037.6	−71.0	−385.0
$ZnBr_2$	−397.0	−355.0	52.7	−238.0
$ZnCl_2$	−488.2	−409.5	0.8	−226.0
ZnF_2	−819.1	−704.6	−139.7	−167.0
ZnI_2	−264.3	−250.2	110.5	−238.0
$Zn(NO_3)_2$	−568.6	−369.6	180.7	−126.0
$ZnSO_4$	−1063.2	−891.6	−92.0	−247.0

HEAT OF COMBUSTION

The heat of combustion of a substance at 25°C can be calculated from the enthalpy of formation ($\Delta_f H^\circ$) data in the table "Standard Thermodynamic Properties of Chemical Substances" in this Section. We can write the general combustion reaction as

$$X + O_2 \rightarrow CO_2\,(g) + H_2O\,(l) + \text{other products}$$

For a compound containing only carbon, hydrogen, and oxygen, the reaction is simply

$$C_aH_bO_c + \left(a + \frac{1}{4}b - \frac{1}{2}c\right)O_2 \rightarrow a\,CO_2\,(g) + \frac{1}{2}b\,H_2O\,(l)$$

and the standard heat of combustion $\Delta_c H^\circ$, which is defined as the negative of the enthalpy change for the reaction (i.e., the heat released in the combustion process), is given by

$$\Delta_c H^\circ = -a\Delta_f H^\circ(CO_2, g) - \frac{1}{2}b\Delta_f H^\circ(H_2O, l) + \Delta_f H^\circ(C_aH_bO_c)$$
$$= 393.51a + 142.915b + \Delta_f H^\circ(C_aH_bO_c)$$

This equation applies if the reactants start in their standard states (25°C and one atmosphere pressure) and the products return to the same conditions. The same equation applies to a compound containing another element if that element ends in its standard reference state (e.g., nitrogen, if the product is N_2); in general, however, the exact products containing the other elements must be known in order to calculate the heat of combustion.

The following table gives the standard heat of combustion calculated in this manner for a few representative substances.

Molecular formula	Name	$\Delta_c H^\circ$/kJ mol^{-1}
Inorganic substances		
C	Carbon (graphite)	393.5
CO	Carbon monoxide (g)	283.0
H_2	Hydrogen (g)	285.8
H_3N	Ammonia (g)	382.8
H_4N_2	Hydrazine (g)	667.1
N_2O	Nitrous oxide (g)	82.1
Hydrocarbons		
CH_4	Methane (g)	890.8
C_2H_2	Acetylene (g)	1301.1
C_2H_4	Ethylene (g)	1411.2
C_2H_6	Ethane (g)	1560.7
C_3H_6	Propylene (g)	2058.0
C_3H_6	Cyclopropane (g)	2091.3
C_3H_8	Propane (g)	2219.2
C_4H_6	1,3-Butadiene (g)	2541.5
C_4H_{10}	Butane (g)	2877.6
C_5H_{12}	Pentane (l)	3509.0
C_6H_6	Benzene (l)	3267.6
C_6H_{12}	Cyclohexane (l)	3919.6
C_6H_{14}	Hexane (l)	4163.2
C_7H_8	Toluene (l)	3910.3
C_7H_{16}	Heptane (l)	4817.0
$C_{10}H_8$	Naphthalene (s)	5156.3
Alcohols and ethers		
CH_4O	Methanol (l)	726.1
C_2H_6O	Ethanol (l)	1366.8
C_2H_6O	Dimethyl ether (g)	1460.4
$C_2H_6O_2$	Ethylene glycol (l)	1189.2
C_3H_8O	1-Propanol (l)	2021.3
$C_3H_8O_3$	Glycerol (l)	1655.4
$C_4H_{10}O$	Diethyl ether (l)	2723.9
$C_5H_{12}O$	1-Pentanol (l)	3330.9
C_6H_6O	Phenol (s)	3053.5
Carbonyl compounds		
CH_2O	Formaldehyde (g)	570.7
C_2H_2O	Ketene (g)	1025.4
C_2H_4O	Acetaldehyde (l)	1166.9
C_3H_6O	Acetone (l)	1789.9
C_3H_6O	Propanal (l)	1822.7
C_4H_8O	2-Butanone (l)	2444.1
Acids and esters		
CH_2O_2	Formic acid (l)	254.6
$C_2H_4O_2$	Acetic acid (l)	874.2
$C_2H_4O_2$	Methyl formate (l)	972.6
$C_3H_6O_2$	Methyl acetate (l)	1592.2
$C_4H_8O_2$	Ethyl acetate (l)	2238.1
$C_6H_5NO_2$	Nicotinic acid (s)	2731.1
$C_7H_6O_2$	Benzoic acid (s)	3228.2
Nitrogen compounds		
CHN	Hydrogen cyanide (g)	671.5
CH_3NO_2	Nitromethane (l)	709.2
CH_4N_2O	Urea (s)	632.7
CH_5N	Methylamine (g)	1085.6
C_2H_3N	Acetonitrile (l)	1247.2
C_2H_5NO	Acetamide (s)	1184.6
C_3H_9N	Trimethylamine (g)	2443.1
C_5H_5N	Pyridine (l)	2782.3
C_6H_7N	Aniline (l)	3392.8

MOLAR CONDUCTIVITY OF AQUEOUS HF, HCl, HBr, AND HI

The molar conductivity Λ of an electrolyte solution is defined as the conductivity divided by amount-of-substance concentration. The customary unit is S cm^2mol^{-1} (i.e., Ω^{-1} cm^2mol^{-1}). The first part of this table gives the molar conductivity of the hydrohalogen acids at 25°C as a function of the concentration in mol/L. The second part gives the temperature dependence of Λ for HCl and HBr. More extensive tables and mathematical representations may be found in the reference.

Reference

Hamer, W. J., and DeWane, H. J., *Electrolytic Conductance and the Conductances of the Hydrohalogen Acids in Water*, Natl. Stand. Ref. Data Sys.- Natl. Bur. Standards (U.S.), No. 33, 1970.

c/mol L^{-1}	HF	HCl	HBr	HI
Inf. dil.	405.1	426.1	427.7	426.4
0.0001		424.5	425.9	424.6
0.0005		422.6	424.3	423.0
0.001		421.2	422.9	421.7
0.005	128.1	415.7	417.6	416.4
0.01	96.1	411.9	413.7	412.8
0.05	50.1	398.9	400.4	400.8
0.10	39.1	391.1	391.9	394.0
0.5	26.3	360.7	361.9	369.8
1.0	24.3	332.2	334.5	343.9
1.5		305.8	307.6	316.4
2.0		281.4	281.7	288.9
2.5		258.9	257.8	262.5
3.0		237.6	236.8	237.9
3.5		218.3	217.5	215.4
4.0		200.0	199.4	195.1
4.5		183.1	182.4	176.8
5.0		167.4	166.5	160.4
5.5		152.9	151.8	145.5
6.0		139.7	138.2	131.7
6.5		127.7	125.7	118.6
7.0		116.9	114.2	105.7
7.5		107.0	103.8	
8.0		98.2	94.4	
8.5		90.3	85.8	
9.0		83.1		
9.5		76.6		
10.0		70.7		

c/mol L^{-1}	−20°C	−10°C	0°C	10°C	20°C	30°C	40°C	50°C
HCl								
0.5			228.7	283.0	336.4	386.8	436.9	482.4
1.0			211.7	261.6	312.2	359.0	402.9	445.3
1.5			196.2	241.5	287.5	331.1	371.6	410.8
2.0			182.0	222.7	262.9	303.3	342.4	378.2
2.5		131.7	168.5	205.1	239.8	277.0	315.2	347.6
3.0		120.8	154.6	188.5	219.3	253.3	289.3	319.0
3.5	85.5	111.3	139.6	172.2	201.6	232.9	263.9	292.1
4.0	79.3	102.7	129.2	158.1	185.6	214.2	242.2	268.2
4.5	73.7	94.9	119.5	145.4	170.6	196.6	222.5	246.7
5.0	68.5	87.8	110.3	133.5	156.6	180.2	204.1	226.5
5.5	63.6	81.1	101.7	122.5	143.6	165.0	187.1	207.7
6.0	58.9	74.9	93.7	112.3	131.5	151.0	171.3	190.3
6.5	54.4	69.1	86.2	103.0	120.4	138.2	156.9	174.3
7.0	50.2	63.7	79.3	94.4	110.2	126.4	143.3	159.7
7.5	46.3	58.6	73.0	86.5	100.9	115.7	131.6	146.2
8.0	42.7	54.0	67.1	79.4	92.4	106.1	120.6	134.0
8.5	39.4	49.8	61.7	72.9	84.7	97.3	110.7	123.0
9.0	36.4	45.9	56.8	67.1	77.8	89.4	101.7	112.9
9.5	33.6	42.3	52.3	61.8	71.5	82.3	93.6	103.9
10.0	31.2	39.1	48.2	57.0	65.8	75.9	86.3	95.7
10.5	28.9	36.1	44.5	52.7	60.7	70.1	79.6	88.4
11.0	26.8	33.4	41.1	48.8	56.1	64.9	73.6	81.7
11.5	24.9	31.0	38.0	45.3	51.9	60.1	68.0	75.6
12.0	23.1	28.7	35.3	42.0	48.0	55.6	62.8	70.0
12.5	21.4	26.7	32.7	39.0	44.4	51.4	57.9	64.8

c/mol L^{-1}	−20°C	−10°C	0°C	10°C	20°C	30°C	40°C	50°C
HBr								
0.5			240.9	295.9	347.0	398.9	453.6	496.8
1.0			229.6	276.0	329.0	380.4	418.6	465.2
1.5			209.5	254.9	298.9	340.6	381.8	421.4
2.0		150.8	188.6	231.3	271.8	314.1	350.5	387.4
2.5		136.8	171.7	208.3	244.8	281.7	316.0	349.1
3.0		125.7	157.2	189.5	222.2	255.0	287.8	318.6
3.5		116.1	144.1	174.6	203.2	234.4	263.7	291.9
4.0	84.0	107.5	132.3	160.2	186.8	214.2	239.7	266.9
4.5	78.0	99.0	123.0	146.4	171.2	195.1	218.8	242.6
5.0	72.3	91.4	112.6	134.0	155.7	178.2	199.6	221.3
5.5	67.0	84.2	103.1	122.7	142.1	162.8	181.4	201.8
6.0	61.8	77.2	94.3	112.0	129.6	148.0	165.4	183.4
6.5	56.8	70.7	86.0	102.0	118.0	134.1	150.5	166.3
7.0	51.9	64.6	78.4	92.6	107.1	121.4	136.3	150.8

STANDARD KCl SOLUTIONS FOR CALIBRATING CONDUCTIVITY CELLS

This table presents recommended electrolytic conductivity (κ) values for aqueous potassium chloride solutions with molalities of 0.01 mol/kg, 0.1 mol/kg and 1.0 mol/kg at temperatures from 0°C to 50°C. The values, which are based on measurements at the National Institute of Standards and Technology, provide primary standards for the calibration of conductivity cells. The measurements at 0.01 and 0.1 molal are described in Reference 1, while those at 1.0 molal are in Reference 2. Temperatures are given on the ITS-90 scale. The uncertainty in the conductivity is about 0.03% for the 0.01 molal values and about 0.04% for the 0.1 and 1.0 molal values. The conductivity of water saturated with atmospheric CO_2 is given in the last column. These values were subtracted from the original measurements to give the values in the second, third, and fourth columns. All κ values are given in units of 10^{-4} S/m (numerically equal to μS/cm).

The assistance of Kenneth W. Pratt is appreciated.

	10^4 κ/S m^{-1}			
***t*/°C**	**0.01 m KCl**	**0.1 m KCl**	**1.0 m KCl**	**H_2O (CO_2 sat.)**
0	772.92	7 116.85	63 488	0.58
5	890.96	8 183.70	72 030	0.68
10	1 013.95	9 291.72	80 844	0.79
15	1 141.45	10 437.1	89 900	0.89
18	1 219.93	11 140.6	—	0.95
20	1 273.03	11 615.9	99 170	0.99
25	1 408.23	12 824.6	108 620	1.10
30	1 546.63	14 059.2	118 240	1.20
35	1 687.79	15 316.0	127 970	1.30
40	1 831.27	16 591.0	137 810	1.40
45	1 976.62	17 880.6	147 720	1.51
50	2 123.43	19 180.9	157 670	1.61

References

1. Wu, Y. C., Koch, W. F., and Pratt, K. W., *J. Res. Natl. Inst. Stand. Technol.* 96, 191, 1991.
2. Wu, Y. C., Koch, W. F., Feng, D., Holland, L. A., Juhasz, E., Arvay, E., and Tomek, A., *J. Res. Natl. Inst. Stand. Technol.* 99, 241, 1994.
3. Pratt, K. W., Koch, W. F., Wu, Y. C., and Berezansky, P. A., *Pure Appl. Chem.* 73, 1783, 2001.

EQUIVALENT CONDUCTIVITY OF ELECTROLYTES IN AQUEOUS SOLUTION

Petr Vanýsek

This table gives the equivalent (molar) conductivity Λ at 25°C for some common electrolytes in aqueous solution at concentrations up to 0.1 mol/L. The units of Λ are 10^{-4} m^2 S mol^{-1}.

For very dilute solutions, the equivalent conductivity for any electrolyte of concentration c can be approximately calculated using the Debye-Hückel-Onsager equation, which can be written for a symmetrical (equal charge on cation and anion) electrolyte as

$$\Lambda = \Lambda^\circ - (A + B\Lambda^\circ)c^{1/2}$$

For a solution at 25°C and both cation and anion with charge |1|, the constants are A = 60.20 and B = 0.229. Λ° can be found from the next table, "Ionic Conductivity and Diffusion at Infinite Dilution". The equation is reliable for c < 0.001 mol/L; with higher concentration the error increases.

Compound	Infinite dilution	Concentration (mol/L)						
		0.0005	0.001	0.005	0.01	0.02	0.05	0.1
	Λ°	Λ						
$AgNO_3$	133.29	131.29	130.45	127.14	124.70	121.35	115.18	109.09
$1/2BaCl_2$	139.91	135.89	134.27	127.96	123.88	119.03	111.42	105.14
$1/2CaCl_2$	135.77	131.86	130.30	124.19	120.30	115.59	108.42	102.41
$1/2Ca(OH)_2$	258	—	—	233	226	214	—	—
$1/2CuSO_4$	133.6	121.6	115.20	94.02	83.08	72.16	59.02	50.55
HCl	425.95	422.53	421.15	415.59	411.80	407.04	398.89	391.13
KBr	151.9	149.8	148.9	146.02	143.36	140.41	135.61	131.32
KCl	149.79	147.74	146.88	143.48	141.20	138.27	133.30	128.90
$KClO_4$	139.97	138.69	137.80	134.09	131.39	127.86	121.56	115.14
$1/3K_3Fe(CN)_6$	174.5	166.4	163.1	150.7	—	—	—	—
$1/4K_4Fe(CN)_6$	184	—	167.16	146.02	134.76	122.76	107.65	97.82
$KHCO_3$	117.94	116.04	115.28	112.18	110.03	107.17	—	—
KI	150.31	148.2	143.32	144.30	142.11	139.38	134.90	131.05
KIO_4	127.86	125.74	124.88	121.18	118.45	114.08	106.67	98.2
KNO_3	144.89	142.70	141.77	138.41	132.75	132.34	126.25	120.34
$KMnO_4$	134.8	132.7	131.9	—	126.5	—	—	113
KOH	271.5	—	234	230	228	—	219	213
$KReO_4$	128.20	126.03	125.12	121.31	118.49	114.49	106.40	97.40
$1/3LaCl_3$	145.9	139.6	137.0	127.5	121.8	115.3	106.2	99.1
LiCl	114.97	113.09	112.34	109.35	107.27	104.60	100.06	95.81
$LiClO_4$	105.93	104.13	103.39	100.52	98.56	96.13	92.15	88.52
$1/2MgCl_2$	129.34	125.55	124.15	118.25	114.49	109.99	103.03	97.05
NH_4Cl	149.6	147.5	146.7	134.4	141.21	138.25	133.22	128.69
NaCl	126.39	124.44	123.68	120.59	118.45	115.70	111.01	106.69
$NaClO_4$	117.42	115.58	114.82	111.70	109.54	106.91	102.35	98.38
NaI	126.88	125.30	124.19	121.19	119.18	116.64	112.73	108.73
$NaOOCCH_3$	91.0	89.2	88.5	85.68	83.72	81.20	76.88	72.76
NaOH	247.7	245.5	244.6	240.7	237.9	—	—	—
Na picrate	80.45	78.7	78.6	75.7	73.7	—	66.3	61.8
$1/2Na_2SO_4$	129.8	125.68	124.09	117.09	112.38	106.73	97.70	89.94
$1/2SrCl_2$	135.73	131.84	130.27	124.18	120.23	115.48	108.20	102.14
$1/2ZnSO_4$	132.7	121.3	114.47	95.44	84.87	74.20	61.17	52.61

IONIC CONDUCTIVITY AND DIFFUSION AT INFINITE DILUTION

Petr Vanýsek

This table gives the molar (equivalent) conductivity λ for common ions at infinite dilution. All values refer to aqueous solutions at 25°C. It also lists the diffusion coefficient D of the ion in dilute aqueous solution, which is related to λ through the equation

$$D = (RT / F^2)(\lambda / |z|)$$

where R is the molar gas constant, T the temperature, F the Faraday constant, and z the charge on the ion. The variation with temperature is fairly sharp; for typical ions, λ and D increase by 2 to 3% per degree as the temperature increases from 25°C.

The diffusion coefficient for a salt, $D_{salt,}$ may be calculated from the D_+ and D_- values of the constituent ions by the relation

$$D_{salt} = \frac{(z_+ + |z_-|)D_+D_-}{z_+D_+ + |z_-|D_-}$$

For solutions of simple, pure electrolytes (one positive and one negative ionic species), such as NaCl, equivalent ionic conductivity Λ°, which is the molar conductivity per unit concentration of charge, is defined as

$$\Lambda^\circ = \Lambda_+ + \Lambda_-$$

where Λ_+ and Λ_- are equivalent ionic conductivities of the cation and anion. The more general formula is

$$\Lambda^\circ = \nu_+\Lambda_+ + \nu_-\Lambda_-$$

where ν_+ and ν_- refer to the number of moles of cations and anions to which one mole of the electrolyte gives a rise in the solution.

References

1. Gray, D. E., Ed., *American Institute of Physics Handbook,* McGraw-Hill, New York, 1972, 2–226.
2. Robinson, R. A., and Stokes, R. H., *Electrolyte Solutions*, Butterworths, London, 1959.
3. Lobo, V. M. M., and Quaresma, J. L., *Handbook of Electrolyte Solutions*, Physical Science Data Series 41, Elsevier, Amsterdam, 1989.
4. Conway, B. E., *Electrochemical Data,* Elsevier, Amsterdam, 1952.
5. Milazzo, G., *Electrochemistry: Theoretical Principles and Practical Applications,* Elsevier, Amsterdam, 1963.

Ion	$\Lambda_\pm$ 10^{-4} m² S mol⁻¹	D 10^{-5} cm² s⁻¹
Inorganic Cations		
Ag^+	61.9	1.648
$1/3Al^{3+}$	61	0.541
$1/2Ba^{2+}$	63.6	0.847
$1/2Be^{2+}$	45	0.599
$1/2Ca^{2+}$	59.47	0.792
$1/2Cd^{2+}$	54	0.719
$1/3Ce^{3+}$	69.8	0.620
$1/2Co^{2+}$	55	0.732
$1/3[Co(NH_3)_6]^{3+}$	101.9	0.904
$1/3[Co(en)_3]^{3+}$	74.7	0.663
$1/6[Co_2(trien)_3]^{6+}$	69	0.306
$1/3Cr^{3+}$	67	0.595
Cs^+	77.2	2.056
$1/2Cu^{2+}$	53.6	0.714
D^+	249.9	6.655
$1/3Dy^{3+}$	65.6	0.582
$1/3Er^{3+}$	65.9	0.585
$1/3Eu^{3+}$	67.8	0.602
$1/2Fe^{2+}$	54	0.719
$1/3Fe^{3+}$	68	0.604
$1/3Gd^{3+}$	67.3	0.597
H^+	349.65	9.311
$1/2Hg^{2+}$	68.6	0.913
$1/2Hg^{2+}$	63.6	0.847
$1/3Ho^{3+}$	66.3	0.589
K^+	73.48	1.957
$1/3La^{3+}$	69.7	0.619
Li^+	38.66	1.029
$1/2Mg^{2+}$	53.0	0.706
$1/2Mn^{2+}$	53.5	0.712
NH_4^+	73.5	1.957
$N_2H_5^+$	59	1.571
Na^+	50.08	1.334
$1/3Nd^{3+}$	69.4	0.616
$1/2Ni^{2+}$	49.6	0.661
$1/4[Ni_2(trien)_3]^{4+}$	52	0.346
$1/2Pb^{2+}$	71	0.945
$1/3Pr^{3+}$	69.5	0.617
$1/2Ra^{2+}$	66.8	0.889
Rb^+	77.8	2.072
$1/3Sc^{3+}$	64.7	0.574
$1/3Sm^{3+}$	68.5	0.608
$1/2Sr^{2+}$	59.4	0.791
Tl^+	74.7	1.989
$1/3Tm^{3+}$	65.4	0.581
$1/2UO_2^{2+}$	32	0.426
$1/3Y^{3+}$	62	0.550
$1/3Yb^{3+}$	65.6	0.582
$1/2Zn^{2+}$	52.8	0.703
Inorganic Anions		
$Au(CN)_2^-$	50	1.331
$Au(CN)_4^-$	36	0.959
$B(C_6H_5)_4^-$	21	0.559
Br^-	78.1	2.080
Br_3^-	43	1.145
BrO_3^-	55.7	1.483
CN^-	78	2.077
CNO^-	64.6	1.720
$1/2CO_3^{2-}$	69.3	0.923
Cl^-	76.31	2.032
ClO_2^-	52	1.385
ClO_3^-	64.6	1.720
ClO_4^-	67.3	1.792
$1/3[Co(CN)_6]^{3-}$	98.9	0.878
$1/2CrO_4^{2-}$	85	1.132

Ion	$\Lambda_\pm$ 10^{-4} m^2 S mol^{-1}	D 10^{-5} cm^2 s^{-1}
F^-	55.4	1.475
$1/4[Fe(CN)_6]^{4-}$	110.4	0.735
$1/3[Fe(CN)_6]^{3-}$	100.9	0.896
$H_2AsO_4^-$	34	0.905
HCO_3^-	44.5	1.185
HF_2^-	75	1.997
$1/2HPO_4^{2-}$	57	0.759
$H_2PO_4^-$	36	0.959
$H_2PO_2^-$	46	1.225
HS^-	65	1.731
HSO_3^-	58	1.545
HSO_4^-	52	1.385
$H_2SbO_4^-$	31	0.825
I^-	76.8	2.045
IO_3^-	40.5	1.078
IO_4^-	54.5	1.451
MnO_4^-	61.3	1.632
$1/2MoO_4^{2-}$	74.5	1.984
$N(CN)_2^-$	54.5	1.451
NO_2^-	71.8	1.912
NO_3^-	71.42	1.902
$NH_2SO_3^-$	48.3	1.286
N_3^-	69	1.837
OCN^-	64.6	1.720
OD^-	119	3.169
OH^-	198	5.273
PF_6^-	56.9	1.515
$1/2PO_3F^{2-}$	63.3	0.843
$1/3PO_4^{3-}$	92.8	0.824
$1/4P_2O_7^{4-}$	96	0.639
$1/3P_3O_9^{3-}$	83.6	0.742
$1/5P_3O_{10}^{5-}$	109	0.581
ReO_4^-	54.9	1.462
SCN^-	66	1.758
$1/2SO_3^{2-}$	72	0.959
$1/2SO_4^{2-}$	80.0	1.065
$1/2S_2O_3^{2-}$	85.0	1.132
$1/2S_2O_4^{2-}$	66.5	0.885
$1/2S_2O_6^{2-}$	93	1.238
$1/2S_2O_8^{2-}$	86	1.145
$Sb(OH)_6^-$	31.9	0.849
$SeCN^-$	64.7	1.723
$1/2SeO_4^{2-}$	75.7	1.008
$1/2WO_4^{2-}$	69	0.919
Organic Cations		
Benzyltrimethylammonium$^+$	34.6	0.921
Isobutylammonium$^+$	38	1.012
Butyltrimethylammonium$^+$	33.6	0.895
Decylpyridinium$^+$	29.5	0.786
Decyltrimethylammonium$^+$	24.4	0.650
Diethylammonium$^+$	42.0	1.118
Dimethylammonium$^+$	51.8	1.379
Dipropylammonium$^+$	30.1	0.802
Dodecylammonium$^+$	23.8	0.634
Dodecyltrimethylammonium$^+$	22.6	0.602
Ethanolammonium$^+$	42.2	1.124
Ethylammonium$^+$	47.2	1.257
Ethyltrimethylammonium$^+$	40.5	1.078
Hexadecyltrimethylammonium$^+$	20.9	0.557
Hexyltrimethylammonium$^+$	29.6	0.788
Histidyl$^+$	23.0	0.612
Hydroxyethyltrimethylarsonium$^+$	39.4	1.049
Methylammonium$^+$	58.7	1.563
Octadecylpyridinium$^+$	20	0.533
Octadecyltributylammonium$^+$	16.6	0.442
Octadecyltriethylammonium$^+$	17.9	0.477
Octadecyltrimethylammonium$^+$	19.9	0.530
Octadecyltripropylammonium$^+$	17.2	0.458
Octyltrimethylammonium$^+$	26.5	0.706
Pentylammonium$^+$	37	0.985
Piperidinium$^+$	37.2	0.991
Propylammonium$^+$	40.8	1.086
Pyrilammonium$^+$	24.3	0.647
Tetrabutylammonium$^+$	19.5	0.519
Tetradecyltrimethylammonium$^+$	21.5	0.573
Tetraethylammonium$^+$	32.6	0.868
Tetramethylammonium$^+$	44.9	1.196
Tetraisopentylammonium$^+$	17.9	0.477
Tetrapentylammmonium$^+$	17.5	0.466
Tetrapropylammonium$^+$	23.4	0.623
Triethylammonium$^+$	34.3	0.913
Triethylsulfonium$^+$	36.1	0.961
Trimethylammonium$^+$	47.23	1.258
Trimethylhexylammonium$^+$	34.6	0.921
Trimethylsulfonium$^+$	51.4	1.369
Tripropylammonium$^+$	26.1	0.695
Organic Anions		
Acetate$^-$	40.9	1.089
p–Anisate$^-$	29.0	0.772
1/2Azelate^{2-}	40.6	0.541
Benzoate$^-$	32.4	0.863
Bromoacetate$^-$	39.2	1.044
Bromobenzoate$^-$	30	0.799
Butyrate$^-$	32.6	0.868
Chloroacetate$^-$	39.8	1.060
m–Chlorobenzoate$^-$	31	0.825
o–Chlorobenzoate$^-$	30.2	0.804
1/3Citrate^{3-}	70.2	0.623
Crotonate$^-$	33.2	0.884
Cyanoacetate$^-$	43.4	1.156
Cyclohexane carboxylate$^-$	28.7	0.764
1/2 1,1–Cyclopropanedicarboxylate^{2-}	53.4	0.711
Decylsulfate$^-$	26	0.692
Dichloroacetate$^-$	38.3	1.020
1/2Diethylbarbiturate^{2-}	26.3	0.350
Dihydrogencitrate$^-$	30	0.799
1/2Dimethylmalonate^{2-}	49.4	0.658
3,5–Dinitrobenzoate$^-$	28.3	0.754
Dodecylsulfate$^-$	24	0.639
Ethylmalonate$^-$	49.3	1.313
Ethylsulfate$^-$	39.6	1.055
Fluoroacetate$^-$	44.4	1.182
Fluorobenzoate$^-$	33	0.879
Formate$^-$	54.6	1.454
1/2Fumarate^{2-}	61.8	0.823
1/2Glutarate^{2-}	52.6	0.700
Hydrogenoxalate$^-$	40.2	1.070
Isovalerate$^-$	32.7	0.871
Iodoacetate$^-$	40.6	1.081
Lactate$^-$	38.8	1.033

Ion	$\Lambda_{\pm}$ 10^{-4} m^2 S mol^{-1}	D 10^{-5} cm^2 s^{-1}
1/2Malate^{2-}	58.8	0.783
1/2Maleate^{2-}	61.9	0.824
1/2Malonate^{2-}	63.5	0.845
Methylsulfate^{-}	48.8	1.299
Naphthylacetate^{-}	28.4	0.756
1/2Oxalate^{2-}	74.11	0.987
Octylsulfate^{-}	29	0.772
Phenylacetate^{-}	30.6	0.815
1/2*o*–Phthalate^{2-}	52.3	0.696
1/2*m*–Phthalate^{2-}	54.7	0.728
Picrate^{-}	30.37	0.809
Pivalate^{-}	31.9	0.849
Propionate^{-}	35.8	0.953
Propylsulfate^{-}	37.1	0.988
Salicylate^{-}	36	0.959
1/2Suberate^{2-}	36	0.479
1/2Succinate^{2-}	58.8	0.783
p–Sulfonate	29.3	0.780
1/2Tartarate^{2-}	59.6	0.794
Trichloroacetate^{-}	35	0.932

ACTIVITY COEFFICIENTS OF ACIDS, BASES, AND SALTS

Petr Vanýsek

This table gives mean activity coefficients at 25°C for molalities in the range 0.1 to 1.0. See the following table for definitions, references, and data over a wider concentration range.

	0.1	**0.2**	**0.3**	**0.4**	**0.5**	**0.6**	**0.7**	**0.8**	**0.9**	**1.0**
$AgNO_3$	0.734	0.657	0.606	0.567	0.536	0.509	0.485	0.464	0.446	0.429
$AlCl_3$	0.337	0.305	0.302	0.313	0.331	0.356	0.388	0.429	0.479	0.539
$Al_2(SO_4)_3$	0.035	0.0225	0.0176	0.0153	0.0143	0.014	0.0142	0.0149	0.0159	0.0175
$BaCl_2$	0.500	0.444	0.419	0.405	0.397	0.391	0.391	0.391	0.392	0.395
$BeSO_4$	0.150	0.109	0.0885	0.0769	0.0692	0.0639	0.0600	0.0570	0.0546	0.0530
$CaCl_2$	0.518	0.472	0.455	0.448	0.448	0.453	0.460	0.470	0.484	0.500
$CdCl_2$	0.2280	0.1638	0.1329	0.1139	0.1006	0.0905	0.0827	0.0765	0.0713	0.0669
$Cd(NO_3)_2$	0.513	0.464	0.442	0.430	0.425	0.423	0.423	0.425	0.428	0.433
$CdSO_4$	0.150	0.103	0.0822	0.0699	0.0615	0.0553	0.0505	0.0468	0.0438	0.0415
$CoCl_2$	0.522	0.479	0.463	0.459	0.462	0.470	0.479	0.492	0.511	0.531
$CrCl_3$	0.331	0.298	0.294	0.300	0.314	0.335	0.362	0.397	0.436	0.481
$Cr(NO_3)_3$	0.319	0.285	0.279	0.281	0.291	0.304	0.322	0.344	0.371	0.401
$Cr_2(SO_4)_3$	0.0458	0.0300	0.0238	0.0207	0.0190	0.0182	0.0181	0.0185	0.0194	0.0208
CsBr	0.754	0.694	0.654	0.626	0.603	0.586	0.571	0.558	0.547	0.538
CsCl	0.756	0.694	0.656	0.628	0.606	0.589	0.575	0.563	0.553	0.544
CsI	0.754	0.692	0.651	0.621	0.599	0.581	0.567	0.554	0.543	0.533
$CsNO_3$	0.733	0.655	0.602	0.561	0.528	0.501	0.478	0.458	0.439	0.422
CsOH	0.795	0.761	0.744	0.739	0.739	0.742	0.748	0.754	0.762	0.771
CsOAc	0.799	0.771	0.761	0.759	0.762	0.768	0.776	0.783	0.792	0.802
Cs_2SO_4	0.456	0.382	0.338	0.311	0.291	0.274	0.262	0.251	0.242	0.235
$CuCl_2$	0.508	0.455	0.429	0.417	0.411	0.409	0.409	0.410	0.413	0.417
$Cu(NO_3)_2$	0.511	0.460	0.439	0.429	0.426	0.427	0.431	0.437	0.445	0.455
$CuSO_4$	0.150	0.104	0.0829	0.0704	0.0620	0.0559	0.0512	0.0475	0.0446	0.0423
$FeCl_2$	0.5185	0.473	0.454	0.448	0.450	0.454	0.463	0.473	0.488	0.506
HBr	0.805	0.782	0.777	0.781	0.789	0.801	0.815	0.832	0.850	0.871
HCl	0.796	0.767	0.756	0.755	0.757	0.763	0.772	0.783	0.795	0.809
$HClO_4$	0.803	0.778	0.768	0.766	0.769	0.776	0.785	0.795	0.808	0.823
HI	0.818	0.807	0.811	0.823	0.839	0.860	0.883	0.908	0.935	0.963
HNO_3	0.791	0.754	0.735	0.725	0.720	0.717	0.717	0.718	0.721	0.724
H_2SO_4	0.2655	0.2090	0.1826	—	0.1557	—	0.1417	—	—	0.1316
KBr	0.772	0.722	0.693	0.673	0.657	0.646	0.636	0.629	0.622	0.617
KCl	0.770	0.718	0.688	0.666	0.649	0.637	0.626	0.618	0.610	0.604
$KClO_3$	0.749	0.681	0.635	0.599	0.568	0.541	0.518	—	—	—
K_2CrO_4	0.456	0.382	0.340	0.313	0.292	0.276	0.263	0.253	0.243	0.235
KF	0.775	0.727	0.700	0.682	0.670	0.661	0.654	0.650	0.646	0.645
$K_3Fe(CN)_6$	0.268	0.212	0.184	0.167	0.155	0.146	0.140	0.135	0.131	0.128
$K_4Fe(CN)_6$	0.139	0.0993	0.0808	0.0693	0.0614	0.0556	0.0512	0.0479	0.0454	—
KH_2PO_4	0.731	0.653	0.602	0.561	0.529	0.501	0.477	0.456	0.438	0.421
KI	0.778	0.733	0.707	0.689	0.676	0.667	0.660	0.654	0.649	0.645
KNO_3	0.739	0.663	0.614	0.576	0.545	0.519	0.496	0.476	0.459	0.443
KOAc	0.796	0.766	0.754	0.750	0.751	0.754	0.759	0.766	0.774	0.783
KOH	0.798	0.760	0.742	0.734	0.732	0.733	0.736	0.742	0.749	0.756
KSCN	0.769	0.716	0.685	0.663	0.646	0.633	0.623	0.614	0.606	0.599
K_2SO_4	0.441	0.360	0.316	0.286	0.264	0.246	0.232	—	—	—
LiBr	0.796	0.766	0.756	0.752	0.753	0.758	0.767	0.777	0.789	0.803
LiCl	0.790	0.757	0.744	0.740	0.739	0.743	0.748	0.755	0.764	0.774
$LiClO_4$	0.812	0.794	0.792	0.798	0.808	0.820	0.834	0.852	0.869	0.887
LiI	0.815	0.802	0.804	0.813	0.824	0.838	0.852	0.870	0.888	0.910
$LiNO_3$	0.788	0.752	0.736	0.728	0.726	0.727	0.729	0.733	0.737	0.743
LiOH	0.760	0.702	0.665	0.638	0.617	0.599	0.585	0.573	0.563	0.554
LiOAc	0.784	0.742	0.721	0.709	0.700	0.691	0.689	0.688	0.688	0.689
Li_2SO_4	0.468	0.398	0.361	0.337	0.319	0.307	0.297	0.289	0.282	0.277
$MgCl_2$	0.529	0.489	0.477	0.475	0.481	0.491	0.506	0.522	0.544	0.570
$MgSO_4$	0.150	0.107	0.0874	0.0756	0.0675	0.0616	0.0571	0.0536	0.0508	0.0485

	0.1	**0.2**	**0.3**	**0.4**	**0.5**	**0.6**	**0.7**	**0.8**	**0.9**	**1.0**
$MnCl_2$	0.516	0.469	0.450	0.442	0.440	0.443	0.448	0.455	0.466	0.479
$MnSO_4$	0.150	0.105	0.0848	0.0725	0.0640	0.0578	0.0530	0.0493	0.0463	0.0439
NH_4Cl	0.770	0.718	0.687	0.665	0.649	0.636	0.625	0.617	0.609	0.603
NH_4NO_3	0.740	0.677	0.636	0.606	0.582	0.562	0.545	0.530	0.516	0.504
$(NH_4)_2SO_4$	0.439	0.356	0.311	0.280	0.257	0.240	0.226	0.214	0.205	0.196
NaBr	0.782	0.741	0.719	0.704	0.697	0.692	0.689	0.687	0.687	0.687
NaCl	0.778	0.735	0.710	0.693	0.681	0.673	0.667	0.662	0.659	0.657
$NaClO_3$	0.772	0.720	0.688	0.664	0.645	0.630	0.617	0.606	0.597	0.589
$NaClO_4$	0.775	0.729	0.701	0.683	0.668	0.656	0.648	0.641	0.635	0.629
Na_2CrO_4	0.464	0.394	0.353	0.327	0.307	0.292	0.280	0.269	0.261	0.253
NaF	0.765	0.710	0.676	0.651	0.632	0.616	0.603	0.592	0.582	0.573
NaH_2PO_4	0.744	0.675	0.629	0.593	0.563	0.539	0.517	0.499	0.483	0.468
NaI	0.787	0.751	0.735	0.727	0.723	0.723	0.724	0.727	0.731	0.736
$NaNO_3$	0.762	0.703	0.666	0.638	0.617	0.599	0.583	0.570	0.558	0.548
NaOAc	0.791	0.757	0.744	0.737	0.735	0.736	0.740	0.745	0.752	0.757
NaOH	0.766	0.727	0.708	0.697	0.690	0.685	0.681	0.679	0.678	0.678
NaSCN	0.787	0.750	—	0.720	0.715	0.712	0.710	0.710	0.711	0.712
Na_2SO_4	0.445	0.365	0.320	0.289	0.266	0.248	0.233	0.221	0.210	0.201
$NiCl_2$	0.522	0.479	0.463	0.460	0.464	0.471	0.482	0.496	0.515	0.563
$NiSO_4$	0.150	0.105	0.0841	0.0713	0.0627	0.0562	0.0515	0.0478	0.0448	0.0425
$Pb(NO_3)_2$	0.395	0.308	0.260	0.228	0.205	0.187	0.172	0.160	0.150	0.141
RbBr	0.763	0.706	0.673	0.650	0.632	0.617	0.605	0.595	0.586	0.578
RbCl	0.764	0.709	0.675	0.652	0.634	0.620	0.608	0.599	0.590	0.583
RbI	0.762	0.705	0.671	0.647	0.629	0.614	0.602	0.591	0.583	0.575
$RbNO_3$	0.734	0.658	0.606	0.565	0.534	0.508	0.485	0.465	0.446	0.430
RbOAc	0.796	0.767	0.756	0.753	0.755	0.759	0.766	0.773	0.782	0.792
Rb_2SO_4	0.451	0.374	0.331	0.301	0.279	0.263	0.249	0.238	0.228	0.219
$SrCl_2$	0.511	0.462	0.442	0.433	0.430	0.431	0.434	0.441	0.449	0.461
$TlClO_4$	0.730	0.652	0.599	0.559	0.527	—	—	—	—	—
$TlNO_3$	0.702	0.606	0.545	0.500	—	—	—	—	—	—
UO_2Cl_2	0.544	0.510	0.520	0.505	0.517	0.532	0.549	0.571	0.595	0.620
UO_2SO_4	0.150	0.102	0.0807	0.0689	0.0611	0.0566	0.0515	0.0483	0.0458	0.0439
$ZnCl_2$	0.515	0.462	0.432	0.411	0.394	0.380	0.369	0.357	0.348	0.339
$Zn(NO_3)_2$	0.531	0.489	0.474	0.469	0.473	0.480	0.489	0.501	0.518	0.535
$ZnSO_4$	0.150	0.140	0.0835	0.0714	0.0630	0.0569	0.0523	0.0487	0.0458	0.0435

MEAN ACTIVITY COEFFICIENTS OF ELECTROLYTES AS A FUNCTION OF CONCENTRATION

The mean activity coefficient γ of an electrolyte X_aY_b is defined as

$$\gamma = (\gamma_+^a \gamma_-^b)^{1/(a+b)}$$

where γ_+ and γ_- are activity coefficients of the individual ions (which cannot be directly measured). This table gives the mean activity coefficients of about 100 electrolytes in aqueous solution as a function of concentration, expressed in molality terms. All values refer to a temperature of 25°C. Substances are arranged in alphabetical order by formula.

References

1. Hamer,W. J., and Wu, Y. C., *J. Phys. Chem. Ref. Data,* 1, 1047, 1972.
2. Staples, B. R., *J. Phys. Chem. Ref. Data,* 6, 385, 1977; 10, 767, 1981; 10, 779, 1981.
3. Goldberg, R. N. et al., *J. Phys. Chem. Ref. Data,* 7, 263, 1978; 8, 923, 1979; 8, 1005, 1979; 10, 1, 1981; 10, 671, 1981.

Mean Activity Coefficient at 25°C

***m*/mol kg^{-1}**	**$AgNO_3$**	**$BaBr_2$**	**$BaCl_2$**	**BaI_2**	**$CaBr_2$**	**$CaCl_2$**	**CaI_2**
0.001	0.964	0.881	0.887	0.890	0.890	0.888	0.890
0.002	0.950	0.850	0.849	0.853	0.853	0.851	0.853
0.005	0.924	0.785	0.782	0.792	0.791	0.787	0.791
0.010	0.896	0.727	0.721	0.737	0.735	0.727	0.736
0.020	0.859	0.661	0.653	0.678	0.674	0.664	0.677
0.050	0.794	0.573	0.559	0.600	0.594	0.577	0.600
0.100	0.732	0.517	0.492	0.551	0.540	0.517	0.552
0.200	0.656	0.463	0.436	0.520	0.502	0.469	0.524
0.500	0.536	0.435	0.391	0.536	0.500	0.444	0.554
1.000	0.430	0.470	0.393	0.664	0.604	0.495	0.729
2.000	0.316	0.654		1.242	1.125	0.784	
5.000	0.181				18.7	5.907	
10.000	0.108					43.1	
15.000	0.085						

***m*/mol kg^{-1}**	**$Cd(NO_2)_2$**	**$Cd(NO_3)_2$**	**$CoBr_2$**	**$CoCl_2$**	**CoI_2**	**$Co(NO_3)_2$**	**CsBr**
0.001	0.881	0.888	0.890	0.889	0.887	0.888	0.965
0.002	0.837	0.851	0.854	0.852	0.849	0.850	0.951
0.005	0.759	0.787	0.794	0.789	0.783	0.786	0.925
0.010	0.681	0.728	0.740	0.732	0.724	0.728	0.898
0.020	0.589	0.664	0.681	0.670	0.661	0.663	0.864
0.050	0.451	0.576	0.605	0.586	0.582	0.576	0.806
0.100	0.344	0.515	0.556	0.528	0.540	0.516	0.752
0.200	0.247	0.465	0.523	0.483	0.527	0.469	0.691
0.500	0.148	0.428	0.538	0.465	0.596	0.446	0.605
1.000	0.098	0.437	0.685	0.532	0.845	0.492	0.540
2.000	0.069	0.517	1.421	0.864	2.287	0.722	0.485
5.000	0.054		13.9		55.3	3.338	0.454
10.000					196		

***m*/mol kg^{-1}**	**CsCl**	**CsF**	**CsI**	**$CsNO_3$**	**CsOH**	**Cs_2SO_4**	**$CuBr_2$**
0.001	0.965	0.965	0.965	0.964	0.966	0.885	0.889
0.002	0.951	0.952	0.951	0.951	0.953	0.845	0.853
0.005	0.925	0.929	0.925	0.924	0.930	0.775	0.791
0.010	0.898	0.905	0.898	0.897	0.906	0.709	0.735
0.020	0.864	0.876	0.863	0.860	0.878	0.634	0.674
0.050	0.805	0.830	0.804	0.796	0.836	0.526	0.594
0.100	0.751	0.792	0.749	0.733	0.802	0.444	0.541
0.200	0.691	0.755	0.688	0.655	0.772	0.369	0.504
0.500	0.607	0.721	0.601	0.529	0.755	0.285	0.503
1.000	0.546	0.726	0.534	0.421	0.782	0.233	0.591
2.000	0.496	0.803	0.470				0.859
5.000	0.474						
10.000	0.508						

m/mol kg^{-1}	$CuCl_2$	$Cu(ClO_4)_2$	$Cu(NO_3)_2$	$FeCl_2$	HBr	HCl	$HClO_4$
0.001	0.887	0.890	0.888	0.888	0.966	0.965	0.966
0.002	0.849	0.854	0.851	0.850	0.953	0.952	0.953
0.005	0.783	0.795	0.787	0.785	0.930	0.929	0.929
0.010	0.722	0.741	0.729	0.725	0.907	0.905	0.906
0.020	0.654	0.685	0.664	0.659	0.879	0.876	0.878
0.050	0.561	0.613	0.577	0.570	0.837	0.832	0.836
0.100	0.495	0.572	0.516	0.509	0.806	0.797	0.803
0.200	0.441	0.553	0.466	0.462	0.783	0.768	0.776
0.500	0.401	0.617	0.431	0.443	0.790	0.759	0.769
1.000	0.405	0.892	0.456	0.500	0.872	0.811	0.826
2.000	0.453	2.445	0.615	0.782	1.167	1.009	1.055
5.000	0.601		2.083		3.800	2.380	3.100
10.000					33.4	10.4	30.8
15.000							323

m/mol kg^{-1}	HF	HI	HNO_3	H_2SO_4	KBr	KCNS	KCl
0.001	0.551	0.966	0.965	0.804	0.965	0.965	0.965
0.002	0.429	0.953	0.952	0.740	0.952	0.951	0.951
0.005	0.302	0.931	0.929	0.634	0.927	0.927	0.927
0.010	0.225	0.909	0.905	0.542	0.902	0.901	0.901
0.020	0.163	0.884	0.875	0.445	0.870	0.869	0.869
0.050	0.106	0.847	0.829	0.325	0.817	0.815	0.816
0.100	0.0766	0.823	0.792	0.251	0.771	0.768	0.768
0.200	0.0550	0.811	0.756	0.195	0.772	0.716	0.717
0.500	0.0352	0.845	0.725	0.146	0.658	0.647	0.649
1.000	0.0249	0.969	0.730	0.125	0.617	0.598	0.604
2.000	0.0175	1.363	0.788	0.119	0.593	0.556	0.573
5.000	0.0110	4.760	1.063	0.197	0.626	0.525	0.593
10.000	0.0085	49.100	1.644	0.527			
15.000	0.0077		2.212	1.077			
20.000	0.0075		2.607	1.701			

m/mol kg^{-1}	$KClO_3$	K_2CrO_4	KF	KH_2PO_4*	K_2HPO_4**	KI	KNO_3
0.001	0.965	0.886	0.965	0.964	0.886	0.965	0.964
0.002	0.951	0.847	0.952	0.950	0.847	0.952	0.950
0.005	0.926	0.779	0.927	0.924	0.779	0.927	0.924
0.010	0.899	0.715	0.902	0.896	0.715	0.902	0.896
0.020	0.865	0.643	0.870	0.859	0.643	0.871	0.860
0.050	0.805	0.539	0.818	0.793	0.538	0.820	0.797
0.100	0.749	0.460	0.773	0.730	0.457	0.776	0.735
0.200	0.681	0.385	0.726	0.652	0.379	0.731	0.662
0.500	0.569	0.296	0.670	0.529	0.283	0.676	0.546
1.000		0.239	0.645	0.422		0.646	0.444
2.000		0.199	0.658			0.638	0.332
5.000			0.871				
10.000			1.715				
15.000			3.120				

m/mol kg^{-1}	KOH	K_2SO_4	LiBr	LiCl	$LiClO_4$	LiI	$LiNO_3$
0.001	0.965	0.885	0.965	0.965	0.966	0.966	0.965
0.002	0.952	0.844	0.952	0.952	0.953	0.953	0.952
0.005	0.927	0.772	0.929	0.928	0.931	0.930	0.928
0.010	0.902	0.704	0.905	0.904	0.908	0.908	0.904
0.020	0.871	0.625	0.877	0.874	0.882	0.882	0.874
0.050	0.821	0.511	0.832	0.827	0.843	0.843	0.827
0.100	0.779	0.424	0.797	0.789	0.815	0.817	0.788
0.200	0.740	0.343	0.767	0.756	0.795	0.802	0.753
0.500	0.710	0.251	0.754	0.739	0.806	0.824	0.726
1.000	0.733		0.803	0.775	0.887	0.912	0.743
2.000	0.860		1.012	0.924	1.161	1.197	0.837
5.000	1.697		2.696	2.000			1.298

m/mol kg^{-1}	KOH	K_2SO_4	LiBr	LiCl	$LiClO_4$	LiI	$LiNO_3$
10.000	6.110		20.0	9.600			2.500
15.000	19.9		147	30.9			3.960
20.000	46.4		486				4.970

m/mol kg^{-1}	LiOH	Li_2SO_4	$MgBr_2$	$MgCl_2$	MgI_2	$MnBr_2$	$MnCl_2$
0.001	0.964	0.887	0.889	0.889	0.889	0.889	0.888
0.002	0.950	0.847	0.852	0.852	0.853	0.853	0.850
0.005	0.923	0.780	0.790	0.790	0.791	0.791	0.786
0.010	0.895	0.716	0.733	0.734	0.736	0.735	0.727
0.020	0.858	0.645	0.672	0.672	0.677	0.674	0.662
0.050	0.794	0.544	0.593	0.590	0.602	0.595	0.574
0.100	0.735	0.469	0.543	0.535	0.556	0.543	0.513
0.200	0.668	0.400	0.512	0.493	0.535	0.508	0.464
0.500	0.579	0.325	0.540	0.485	0.594	0.519	0.437
1.000	0.522	0.284	0.715	0.577	0.858	0.650	0.477
2.000	0.484	0.270	1.590	1.065	2.326	1.224	0.661
5.000	0.493		36.1	14.40	109.8	6.697	1.539

m/mol kg^{-1}	$Mn(ClO_4)_2$	NH_4Cl	NH_4ClO_4	$(NH_4)_2HPO_4$**	NH_4NO_3	NaBr	$NaBrO_3$
0.001	0.892	0.965	0.964	0.882	0.964	0.965	0.965
0.002	0.858	0.952	0.950	0.839	0.951	0.952	0.951
0.005	0.801	0.927	0.924	0.763	0.925	0.928	0.926
0.010	0.752	0.901	0.895	0.688	0.897	0.903	0.900
0.020	0.700	0.869	0.859	0.600	0.862	0.873	0.867
0.050	0.637	0.816	0.794	0.469	0.801	0.824	0.811
0.100	0.604	0.769	0.734	0.367	0.744	0.783	0.759
0.200	0.596	0.718	0.663	0.273	0.678	0.742	0.698
0.500	0.686	0.649	0.560	0.171	0.582	0.697	0.605
1.000	1.030	0.603	0.479	0.114	0.502	0.687	0.528
2.000	3.072	0.569	0.399	0.074	0.419	0.730	0.449
5.000		0.563			0.303	1.083	
10.000					0.220		
15.000					0.179		
20.000					0.154		

m/mol kg^{-1}	Na_2CO_3	NaCl	$NaClO_3$	$NaClO_4$	Na_2CrO_4	NaF	Na_2HPO_4*
0.001	0.887	0.965	0.965	0.965	0.887	0.965	0.887
0.002	0.847	0.952	0.952	0.952	0.849	0.951	0.848
0.005	0.780	0.928	0.927	0.928	0.783	0.926	0.780
0.010	0.716	0.903	0.902	0.903	0.722	0.901	0.717
0.020	0.644	0.872	0.870	0.872	0.653	0.868	0.644
0.050	0.541	0.822	0.818	0.821	0.554	0.813	0.539
0.100	0.462	0.779	0.771	0.777	0.479	0.764	0.456
0.200	0.385	0.734	0.719	0.729	0.406	0.710	0.373
0.500	0.292	0.681	0.646	0.668	0.318	0.633	0.266
1.000	0.229	0.657	0.590	0.630	0.261	0.573	0.191
2.000	0.182	0.668	0.537	0.608	0.231		0.133
5.000		0.874		0.648			

m/mol kg^{-1}	NaI	$NaNO_3$	NaOH	Na_2SO_3	Na_2SO_4	Na_2WO_4	$NiBr_2$
0.001	0.965	0.965	0.965	0.887	0.886	0.886	0.889
0.002	0.952	0.951	0.952	0.847	0.846	0.846	0.853
0.005	0.928	0.926	0.927	0.779	0.777	0.777	0.791
0.010	0.904	0.900	0.902	0.716	0.712	0.712	0.735
0.020	0.874	0.866	0.870	0.644	0.637	0.638	0.675
0.050	0.827	0.810	0.819	0.540	0.529	0.534	0.596
0.100	0.789	0.759	0.775	0.462	0.446	0.457	0.546
0.200	0.753	0.701	0.731	0.386	0.366	0.388	0.514
0.500	0.722	0.617	0.685	0.296	0.268	0.320	0.535
1.000	0.734	0.550	0.674	0.237	0.204	0.291	0.692
2.000	0.823	0.480	0.714	0.196	0.155	0.291	1.476

m/mol kg^{-1}	NaI	$NaNO_3$	NaOH	Na_2SO_3	Na_2SO_4	Na_2WO_4	$NiBr_2$
5.000	1.402	0.388	1.076				
10.000	4.011	0.329	3.258				
15.000			9.796				
20.000			19.410				

m/mol kg^{-1}	$NiCl_2$	$Ni(ClO_4)_2$	$Ni(NO_3)_2$	$Pb(ClO_4)_2$	$Pb(NO_3)_2$	RbBr	RbCl
0.001	0.889	0.891	0.889	0.889	0.882	0.965	0.965
0.002	0.852	0.855	0.851	0.851	0.840	0.951	0.951
0.005	0.789	0.797	0.787	0.787	0.764	0.926	0.926
0.010	0.732	0.745	0.730	0.729	0.690	0.900	0.900
0.020	0.669	0.690	0.666	0.666	0.604	0.866	0.867
0.050	0.584	0.621	0.581	0.580	0.476	0.811	0.811
0.100	0.527	0.582	0.524	0.522	0.379	0.760	0.761
0.200	0.482	0.567	0.481	0.476	0.291	0.705	0.707
0.500	0.465	0.639	0.467	0.458	0.195	0.630	0.633
1.000	0.538	0.946	0.528	0.516	0.136	0.578	0.583
2.000	0.915	2.812	0.797	0.799		0.535	0.546
5.000	4.785			4.043		0.514	0.544
10.000				33.8			

m/mol kg^{-1}	RbF	RbI	$RbNO_3$	Rb_2SO_4	$SrBr_2$	$SrCl_2$	SrI_2
0.001	0.965	0.965	0.964	0.886	0.889	0.888	0.890
0.002	0.952	0.951	0.950	0.845	0.852	0.850	0.854
0.005	0.927	0.926	0.924	0.776	0.790	0.785	0.793
0.010	0.902	0.900	0.896	0.710	0.734	0.725	0.740
0.020	0.871	0.866	0.859	0.635	0.673	0.659	0.681
0.050	0.821	0.810	0.795	0.526	0.591	0.569	0.606
0.100	0.780	0.759	0.733	0.443	0.535	0.506	0.557
0.200	0.739	0.703	0.657	0.365	0.492	0.455	0.526
0.500	0.701	0.627	0.536	0.274	0.476	0.421	0.542
1.000	0.697	0.574	0.430	0.217	0.545	0.451	0.686
2.000	0.724	0.532	0.320		0.921	0.650	
5.000		0.517					

m/mol kg^{-1}	UO_2Cl_2	$UO_2(NO_3)_2$	$ZnBr_2$	$ZnCl_2$	ZnI_2
0.001	0.888	0.888	0.890	0.887	0.893
0.002	0.851	0.849	0.854	0.847	0.859
0.005	0.787	0.784	0.794	0.781	0.804
0.010	0.729	0.726	0.741	0.719	0.757
0.020	0.666	0.663	0.683	0.652	0.708
0.050	0.583	0.583	0.606	0.561	0.644
0.100	0.529	0.535	0.553	0.499	0.601
0.200	0.493	0.509	0.515	0.447	0.574
0.500	0.501	0.532	0.516	0.384	0.635
1.000	0.601	0.673	0.558	0.330	0.836
2.000	0.948	1.223	0.578	0.283	1.062
5.000		3.020	0.788	0.342	1.546
10.000			2.317	0.876	4.698
15.000			5.381	1.914	
20.000			7.965	2.968	

* The anion is $H_2PO_4^-$.

** The anion is HPO_4^{-2}.

ENTHALPY OF DILUTION OF ACIDS

The quantity given in this table is $-\Delta_{dil}H$, the negative of the enthalpy (heat) of dilution to infinite dilution for aqueous solutions of several common acids; i.e., the negative of the enthalpy change when a solution of molality m at a temperature of 25°C is diluted with an infinite amount of water. The tabulated numbers thus represent the heat produced (or, if the value is negative, the heat absorbed) when the acid is diluted. The initial molality m is given in the first column. The second column gives the dilution ratio, which is the number of moles of water that must be added to one mole of the acid to produce a solution of the molality in the first column.

Reference

Parker, V. B., *Thermal Properties of Aqueous Uni-Univalent Electrolytes,* Natl. Stand. Ref. Data Ser. - Natl. Bur. Stand. (U.S.) 2, U.S. Government Printing Office, 1965.

		$-\Delta_{dil}H$ in kJ/mol at 25°C							
m	**Dil. ratio**	**HF**	**HCl**	**$HClO_4$**	**HBr**	**HI**	**HNO_3**	**CH_2O_2**	**$C_2H_4O_2$**
55.506	1.0		45.61		48.83		19.73	0.046	2.167
20	2.775	14.88	19.87	13.81	19.92	21.71	9.498	0.038	2.075
15	3.700	14.34	15.40	7.920	14.29	14.02	6.883	0.109	1.962
10	5.551	13.87	10.24	2.013	8.694	7.615	3.933	0.205	1.824
9	6.167	13.81	9.213	1.280	7.719	6.569	3.368	0.230	1.782
8	6.938	13.77	8.201	0.611	6.786	5.607	2.791	0.255	1.724
7	7.929	13.73	7.217	0.046	5.925	4.728	2.251	0.272	1.648
6	9.251	13.69	6.268	-0.351	5.004	3.975	1.749	0.280	1.540
5.5506	10	13.66	5.841	-0.490	4.590	3.577	1.540	0.285	1.477
5	11.10	13.62	5.318	-0.628	4.113	3.197	1.310	0.289	1.393
4.5	12.33	13.58	4.899	-0.732	3.711	2.828	1.109	0.289	1.310
4	13.88	13.53	4.402	-0.787	3.330	2.460	0.958	0.289	1.218
3.5	15.86	13.47	3.958	-0.820	2.966	2.105	0.791	0.289	1.121
3	18.50	13.45	3.506	-0.782	2.611	1.787	0.665	0.289	1.025
2.5	22.20	13.43	3.063	-0.724	2.301	1.527	0.582	0.285	0.912
2	27.75	13.40	2.623	-0.623	1.996	1.318	0.527	0.276	0.803
1.5	37.00	13.36	2.167	-0.431	1.665	1.125	0.506	0.259	0.678
1	55.51	13.30	1.695	-0.201	1.314	0.933	0.506	0.226	0.544
0.5551	100	13.22	1.234	0.050	0.983	0.736	0.502	0.184	0.423
0.5	111.0	13.20	1.172	0.075	0.941	0.711	0.498	0.176	0.406
0.2	277.5	13.09	0.761	0.247	0.649	0.536	0.439	0.146	0.331
0.1	555.1	12.80	0.556	0.272	0.498	0.439	0.372	0.134	0.289
0.0925	600	12.79	0.540	0.272	0.481	0.427	0.368	0.134	0.285
0.0793	700	12.70	0.502	0.272	0.452	0.402	0.351	0.134	0.285
0.0694	800	12.61	0.473	0.268	0.427	0.385	0.339	0.130	0.280
0.0617	900	12.50	0.448	0.264	0.406	0.368	0.326	0.126	0.276
0.05551	1000	12.42	0.427	0.259	0.385	0.351	0.318	0.121	0.272
0.05	1110	12.24	0.406	0.259	0.372	0.339	0.305	0.121	0.272
0.02775	2000	11.29	0.310	0.226	0.285	0.264	0.247	0.117	0.264
0.01850	3000	10.66	0.251	0.197	0.234	0.218	0.213	0.117	0.259
0.01388	4000	10.25	0.226	0.180	0.205	0.192	0.192	0.113	0.259
0.01110	5000	9.874	0.197	0.167	0.184	0.172	0.176	0.109	0.255
0.00555	10000	8.912	0.142	0.126	0.130	0.121	0.130	0.105	0.243
0.00278	20000	7.531	0.105	0.092	0.092	0.084	0.096	0.096	0.230
0.00111	50000	5.439	0.067	0.059	0.054	0.050	0.063	0.084	0.222
0.000555	100000	3.766	0.042	0.042	0.038	0.038	0.046	0.054	0.209
0.000111	500000	1.255	0.021	0.021	0.021	0.021	0.021	0.038	0.167
0	∞	0	0	0	0	0	0	0	0

ENTHALPY OF SOLUTION OF ELECTROLYTES

This table gives the molar enthalpy (heat) of solution at infinite dilution for some common uni-univalent electrolytes. This is the enthalpy change when 1 mol of solute in its standard state is dissolved in an infinite amount of water. Values are given in kilojoules per mole at 25°C.

Reference

Parker, V. B., *Thermal Properties of Uni-Univalent Electrolytes,* Natl. Stand. Ref. Data Series — Natl. Bur. Stand.(U.S.), No.2, 1965.

Solute	State	$\Delta_{sol}H^\circ$ kJ/mol
HF	g	−61.50
HCl	g	−74.84
$HClO_4$	l	−88.76
$HClO_4 \cdot H_2O$	c	−32.95
HBr	g	−85.14
HI	g	−81.67
HIO_3	c	8.79
HNO_3	l	−33.28
HCOOH	l	−0.86
CH_3COOH	l	−1.51
NH_3	g	−30.50
NH_4Cl	c	14.78
NH_4ClO_4	c	33.47
NH_4Br	c	16.78
NH_4I	c	13.72
NH_4IO_3	c	31.80
NH_4NO_2	c	19.25
NH_4NO_3	c	25.69
$NH_4C_2H_3O_2$	c	−2.38
NH_4CN	c	17.57
NH_4CNS	c	22.59
CH_3NH_3Cl	c	5.77
$(CH_3)_3NHCl$	c	1.46
$N(CH_3)_4Cl$	c	4.08
$N(CH_3)_4Br$	c	24.27
$N(CH_3)_4I$	c	42.07
$AgClO_4$	c	7.36
$AgNO_2$	c	36.94
$AgNO_3$	c	22.59
LiOH	c	−23.56
$LiOH \cdot H_2O$	c	−6.69
LiF	c	4.73
LiCl	c	−37.03
$LiCl \cdot H_2O$	c	−19.08
$LiClO_4$	c	−26.55
$LiClO_4 \cdot 3H_2O$	c	32.61
LiBr	c	−48.83
$LiBr \cdot H_2O$	c	−23.26
$LiBr \cdot 2H_2O$	c	−9.41
$LiBrO_3$	c	1.42
LiI	c	−63.30
$LiI \cdot H_2O$	c	−29.66
$LiI \cdot 2H_2O$	c	−14.77
$LiI \cdot 3H_2O$	c	0.59
$LiNO_2$	c	−11.00
$LiNO_2 \cdot H_2O$	c	7.03
$LiNO_3$	c	−2.51
NaOH	c	−44.51
$NaOH \cdot H_2O$	c	−21.41
NaF	c	0.91
NaCl	c	3.88
$NaClO_2$	c	0.33
$NaClO_2 \cdot 3H_2O$	c	28.58
$NaClO_3$	c	21.72
$NaClO_4$	c	13.88
$NaClO_4 \cdot H_2O$	c	22.51
NaBr	c	−0.60
$NaBr \cdot 2H_2O$	c	18.64
$NaBrO_3$	c	26.90
NaI	c	−7.53
$NaI \cdot 2H_2O$	c	16.13
$NaIO_3$	c	20.29
$NaNO_2$	c	13.89
$NaNO_3$	c	20.50
$NaC_2H_3O_2$	c	−17.32
$NaC_2H_3O_2 \cdot 3H_2O$	c	19.66
NaCN	c	1.21
$NaCN \cdot 0.5H_2O$	c	3.31
$NaCN \cdot 2H_2O$	c	18.58
NaCNO	c	19.20
NaCNS	c	6.83
KOH	c	−57.61
$KOH \cdot H_2O$	c	−14.64
$KOH \cdot 1.5H_2O$	c	−10.46
KF	c	−17.73
$KF \cdot 2H_2O$	c	6.97
KCl	c	17.22
$KClO_3$	c	41.38
$KClO_4$	c	51.04
KBr	c	19.87
$KBrO_3$	c	41.13
KI	c	20.33
KIO_3	c	27.74
KNO_2	c	13.35
KNO_3	c	34.89
$KC_2H_3O_2$	c	−15.33
KCN	c	11.72
KCNO	c	20.25
KCNS	c	24.23
$KMnO_4$	c	43.56
RbOH	c	−62.34
$RbOH \cdot H_2O$	c	−17.99
$RbOH \cdot 2H_2O$	c	0.88
RbF	c	−26.11
$RbF \cdot H_2O$	c	−0.42
$RbF \cdot 1.5H_2O$	c	1.34
RbCl	c	17.28
$RbClO_3$	c	47.74
$RbClO_4$	c	56.74
RbBr	c	21.88
$RbBrO_3$	c	48.95
RbI	c	25.10
$RbNO_3$	c	36.48
CsOH	c	−71.55
$CsOH \cdot H_2O$	c	−20.50
CsF	c	−36.86
$CsF \cdot H_2O$	c	−10.46
$CsF \cdot 1.5H_2O$	c	−5.44
CsCl	c	17.78
$CsClO_4$	c	55.44
CsBr	c	25.98
$CsBrO_3$	c	50.46
CsI	c	33.35
$CsNO_3$	c	40.00

CHEMICAL KINETIC DATA FOR STRATOSPHERIC MODELING

The present compilation of kinetic data represents the 12th evaluation prepared by the NASA Panel for Data Evaluation. The Panel was established in 1977 by the NASA Upper Atmosphere Research Program Office for the purpose of providing a critical tabulation of the latest kinetic and photochemical data for use by modelers in computer simulations of stratospheric chemistry. The recommended rate data and cross sections are based on laboratory measurements. The major use of theoretical extrapolation of data is in connection with three–body reactions, in which the required pressure or temperature dependence is sometimes unavailable from laboratory measurements, and can be estimated by use of appropriate theoretical treatment. In the case of important rate constants for which no experimental data are available, the panel may provide estimates of rate constant parameters based on analogy to similar reactions for which data are available.

Rate constants are expressed in the form $k(T) = A \exp(-E/RT)$, where A is the pre–exponential factor, E the activation energy, R the gas constant, and T the absolute temperature. Uncertainties are expressed by the factor f, e.g., a value of 4.2×10^{-10} with $f = 2$ indicates that the true value is believed to lie between 2.1×10^{-10} and 8.4×10^{-10}. The value of f at other temperatures may be calculated from $f(298)$, given in the last column, by:

$$f(T) = f(298)\exp[(\Delta E/R)(1/T - 1/298)] ,$$

where $\Delta E/R$ is the uncertainty in E/R.

Table 1 covers rate constant data on second order reactions, grouped by class, while Table 2 covers association reactions. Relevant equilibrium constant data are given in Table 3. All concentrations are measured in molecules cm^{-3}. Notes on each reaction, as well as related photochemical data, may be found in the reference.

The assistance of Robert Hampson is gratefully acknowledged.

Reference

DeMore, W. B., Sander, S. P., Golden, D. M., Hampson, R. F., Kurylo, M. J., Howard, C. J., Ravishankara, A. R., Kolb, C. E., and Molina, M. J., *Chemical Kinetics and Photochemical Data for Use in Atmospheric Modeling. Evaluation Number 12*, Jet Propulsion Laboratory Publication 97–4, Pasadena CA, 1997.

The report is also available at the World Wide Web site < http://remus.jpl.nasa.gov/pub/jpl97>.

TABLE 1. Rate Constants for Second Order Reactions

Reaction	A cm^3 molecule^{-1} s^{-1}	E/R K	k (298 K) cm^3 molecule^{-1} s^{-1}	$f(298)$
O_x Reactions				
$O + O_3 \rightarrow O_2 + O_2$	8.0×10^{-12}	2060±250	8.0×10^{-15}	1.15
$O(^1D)$ Reactions				
$O(^1D) + O_2 \rightarrow O + O_2$	3.2×10^{-11}	–(70±100)	4.0×10^{-11}	1.2
$O(^1D) + O_3 \rightarrow O_2 + O_2$	1.2×10^{-10}	0±100	1.2×10^{-10}	1.3
$\rightarrow O_2 + O + O$	1.2×10^{-10}	0±100	1.2×10^{-10}	1.3
$O(^1D) + H_2 \rightarrow OH + H$	1.1×10^{-10}	0±100	1.1×10^{-10}	1.1
$O(^1D) + H_2O \rightarrow OH + OH$	2.2×10^{-10}	0±100	2.2×10^{-10}	1.2
$O(^1D) + N_2 \rightarrow O + N_2$	1.8×10^{-11}	–(110±100)	2.6×10^{-11}	1.2
$O(^1D) + N_2O \rightarrow N_2 + O_2$	4.9×10^{-11}	0±100	4.9×10^{-11}	1.3
$\rightarrow NO + NO$	6.7×10^{-11}	0±100	6.7×10^{-11}	1.3
$O(^1D) + NH_3 \rightarrow OH + NH_2$	2.5×10^{-10}	0±100	2.5×10^{-10}	1.3
$O(^1D) + CO_2 \rightarrow O + CO_2$	7.4×10^{-11}	–(120±100)	1.1×10^{-10}	1.2
$O(^1D) + CH_4 \rightarrow$ products	1.5×10^{-10}	0±100	1.5×10^{-10}	1.2
$O(^1D) + HCl \rightarrow$ products	1.5×10^{-10}	0±100	1.5×10^{-10}	1.2
$O(^1D) + HF \rightarrow OH + F$	1.4×10^{-10}	0±100	1.4×10^{-10}	2.0
$O(^1D) + HBr \rightarrow$ products	1.5×10^{-10}	0±100	1.5×10^{-10}	2.0
$O(^1D) + Cl_2 \rightarrow$ products	2.8×10^{-10}	0±100	2.8×10^{-10}	2.0
$O(^1D) + CCl_2O \rightarrow$ products	3.6×10^{-10}	0±100	3.6×10^{-10}	2.0
$O(^1D) + CClFO \rightarrow$ products	1.9×10^{-10}	0±100	1.9×10^{-10}	2.0
$O(^1D) + CF_2O \rightarrow$ products	7.4×10^{-11}	0±100	7.4×10^{-11}	2.0
$O(^1D) + CCl_4 \rightarrow$ products (CFC–10)	3.3×10^{-10}	0±100	3.3×10^{-10}	1.2
$O(^1D) + CH_3Br \rightarrow$ products	1.8×10^{-10}	0±100	1.8×10^{-10}	1.3
$O(^1D) + CH_2Br_2 \rightarrow$ products	2.7×10^{-10}	0±100	2.7×10^{-10}	1.3
$O(^1D) + CHBr_3 \rightarrow$ products	6.6×10^{-10}	0±100	6.6×10^{-10}	1.5
$O(^1D) + CH_3F \rightarrow$ products (HFC–41)	1.5×10^{-10}	0±100	1.5×10^{-10}	1.2
$O(^1D) + CH_2F_2 \rightarrow$ products (HFC–32)	5.1×10^{-11}	0±100	5.1×10^{-11}	1.3
$O(^1D) + CHF_3 \rightarrow$ products (HFC–23)	9.1×10^{-12}	0±100	9.1×10^{-12}	1.2

Reaction	*A* cm³ molecule⁻¹ s⁻¹	*E*/*R* K	*k* (298 K) cm³ molecule⁻¹ s⁻¹	*f*(298)
$O(^1D) + CHCl_2F \rightarrow$ products (HCFC–21)	1.9×10^{-10}	0±100	1.9×10^{-10}	1.3
$O(^1D) + CHClF_2 \rightarrow$ products (HCFC–22)	1.0×10^{-10}	0±100	1.0×10^{-10}	1.2
$O(^1D) + CCl_3F \rightarrow$ products (CFC–11)	2.3×10^{-10}	0±100	2.3×10^{-10}	1.2
$O(^1D) + CCl_2F_2 \rightarrow$ products (CFC–12)	1.4×10^{-10}	0±100	1.4×10^{-10}	1.3
$O(^1D) + CClF_3 \rightarrow$ products (CFC–13)	8.7×10^{-11}	0±100	8.7×10^{-11}	1.3
$O(^1D) + CClBrF_2 \rightarrow$ products (Halon–1211)	1.5×10^{-10}	0±100	1.5×10^{-10}	1.3
$O(^1D) + CBr_2F_2 \rightarrow$ products (Halon–1202)	2.2×10^{-10}	0±100	2.2×10^{-10}	1.3
$O(^1D) + CBrF_3 \rightarrow$ products (Halon–1301)	1.0×10^{-10}	0±100	1.0×10^{-10}	1.3
$O(^1D) + CF_4 \rightarrow CF_4 + O$ (CFC–14)	–	–	2.0×10^{-14}	1.5
$O(^1D) + CH_3CH_2F \rightarrow$ products (HFC–161)	2.6×10^{-10}	0±100	2.6×10^{-10}	1.3
$O(^1D) + CH_3CHF_2 \rightarrow$ products (HFC–152a)	2.0×10^{-10}	0±100	2.0×10^{-10}	1.3
$O(^1D) + CH_3CCl_2F \rightarrow$ products (HCFC–141b)	2.6×10^{-10}	0±100	2.6×10^{-10}	1.3
$O(^1D) + CH_3CClF_2 \rightarrow$ products (HCFC–142b)	2.2×10^{-10}	0±100	2.2×10^{-10}	1.3
$O(^1D) + CH_3CF_3 \rightarrow$ products (HFC–143a)	1.0×10^{-10}	0±100	1.0×10^{-10}	3.0
$O(^1D) + CH_2ClCCl_2F \rightarrow$ products (HCFC–132b)	1.6×10^{-10}	0±100	1.6×10^{-10}	2.0
$O(^1D) + CH_2ClCF_3 \rightarrow$ products (HCFC–133a)	1.2×10^{-10}	0±100	1.2×10^{-10}	1.3
$O(^1D) + CH_2FCF_3 \rightarrow$ products (HFC–134a)	4.9×10^{-11}	0±100	4.9×10^{-11}	1.3
$O(^1D) + CHCl_2CF_3 \rightarrow$ products (HCFC–123)	2.0×10^{-10}	0±100	2.0×10^{-10}	1.3
$O(^1D) + CHClFCF_3 \rightarrow$ products (HCFC–124)	8.6×10^{-11}	0±100	8.6×10^{-11}	1.3
$O(^1D) + CHF_2CF_3 \rightarrow$ products (HFC–125)	1.2×10^{-10}	0±100	1.2×10^{-10}	2.0
$O(^1D) + CCl_3CF_3 \rightarrow$ products (CFC–113a)	2×10^{-10}	0±100	2×10^{-10}	2.0
$O(^1D) + CCl_2FCClF_2 \rightarrow$ products (CFC–113)	2×10^{-10}	0±100	2×10^{-10}	2.0
$O(^1D) + CCl_2FCF_3 \rightarrow$ products (CFC–114a)	1×10^{-10}	0±100	1×10^{-10}	2.0
$O(^1D) + CClF_2CClF_2 \rightarrow$ products (CFC–114)	1.3×10^{-10}	0±100	1.3×10^{-10}	1.3
$O(^1D) + CClF_2CF_3 \rightarrow$ products (CFC–115)	5×10^{-11}	0±100	5×10^{-11}	1.3
$O(^1D) + CBrF_2CBrF_2 \rightarrow$ products (Halon–2402)	1.6×10^{-10}	0±100	1.6×10^{-10}	1.3
$O(^1D) + CF_3CF_3 \rightarrow O + CF_3CF_3$ (CFC–116)	–	–	1.5×10^{-13}	1.5
$O(^1D) + CHF_2CF_2CF_2CHF_2 \rightarrow$ products (HFC–338pcc)	1.8×10^{-11}	0±100	1.8×10^{-11}	1.5
$O(^1D) + c\text{–}C_4F_8 \rightarrow$ products	–	–	8×10^{-13}	1.3
$O(^1D) + CF_3CHFCHFCF_2CF_3 \rightarrow$ products (HFC–43–10mee)	2.1×10^{-10}	0±100	2.1×10^{-10}	4
$O(^1D) + C_5F_{12} \rightarrow$ products (CFC–41–12)	–	–	3.9×10^{-13}	2
$O(^1D) + C_6F_{14} \rightarrow$ products (CFC–51–14)	–	–	1×10^{-12}	2
$O(^1D) + 1,2\text{–}(CF_3)_2c\text{–}C_4F_6 \rightarrow$ products	–	–	2.8×10^{-13}	2
$O(^1D) + SF_6 \rightarrow$ products	–	–	1.8×10^{-14}	1.5
Singlet O_2 Reactions				
$O_2(^1\Delta) + O \rightarrow$ products	–	–	$<2\times10^{-16}$	–
$O_2(^1\Delta) + O_2 \rightarrow$ products	3.6×10^{-18}	220±100	1.7×10^{-18}	1.2
$O_2(^1\Delta) + O_3 \rightarrow O + 2O_2$	5.2×10^{-11}	2840±500	3.8×10^{-15}	1.2
$O_2(^1\Delta) + H_2O \rightarrow$ products	–	–	4.8×10^{-18}	1.5
$O_2(^1\Delta) + N \rightarrow NO + O$	–	–	$<9\times10^{-17}$	–
$O_2(^1\Delta) + N_2 \rightarrow$ products	–	–	$<10^{-20}$	–
$O_2(^1\Delta) + CO_2 \rightarrow$ products	–	–	$<2\times10^{-20}$	–
$O_2(^1\Sigma) + O \rightarrow$ products	–	–	8×10^{-14}	5.0
$O_2(^1\Sigma) + O_2 \rightarrow$ products	–	–	3.9×10^{-17}	1.5
$O_2(^1\Sigma) + O_3 \rightarrow$ products	2.2×10^{-11}	0±200	2.2×10^{-11}	1.2
$O_2(^1\Sigma) + H_2O \rightarrow$ products	–	–	5.4×10^{-12}	1.3
$O_2(^1\Sigma) + N \rightarrow$ products	–	–	$<10^{-13}$	–
$O_2(^1\Sigma) + N_2 \rightarrow$ products	2.1×10^{-15}	0±200	2.1×10^{-15}	1.2
$O_2(^1\Sigma) + CO_2 \rightarrow$ products	4.2×10^{-13}	0±200	4.2×10^{-13}	1.2
HO_x Reactions				
$O + OH \rightarrow O_2 + H$	2.2×10^{-11}	–(120±100)	3.3×10^{-11}	1.2
$O + HO_2 \rightarrow OH + O_2$	3.0×10^{-11}	–(200±100)	5.9×10^{-11}	1.2
$O + H_2O_2 \rightarrow OH + HO_2$	1.4×10^{-12}	2000±1000	1.7×10^{-15}	2.0
$H + O_3 \rightarrow OH + O_2$	1.4×10^{-10}	470±200	2.9×10^{-11}	1.25
$H + HO_2 \rightarrow$ products	8.1×10^{-11}	0±100	8.1×10^{-11}	1.3
$OH + O_3 \rightarrow HO_2 + O_2$	1.6×10^{-12}	940±300	6.8×10^{-14}	1.3
$OH + H_2 \rightarrow H_2O + H$	5.5×10^{-12}	2000±100	6.7×10^{-15}	1.1

Reaction	*A* cm³ molecule⁻¹ s⁻¹	*E*/*R* K	*k* (298 K) cm³ molecule⁻¹ s⁻¹	*f*(298)
$OH + HD \rightarrow$ products	5.0×10^{-12}	2130±200	4.0×10^{-15}	1.2
$OH + OH \rightarrow H_2O + O$	4.2×10^{-12}	240±240	1.9×10^{-12}	1.4
$OH + HO_2 \rightarrow H_2O + O_2$	4.8×10^{-11}	−(250±200)	1.1×10^{-10}	1.3
$OH + H_2O_2 \rightarrow H_2O + HO_2$	2.9×10^{-12}	160±100	1.7×10^{-12}	1.2
$HO_2 + O_3 \rightarrow OH + 2O_2$	1.1×10^{-14}	500±	2.0×10^{-15}	1.3
$HO_2 + HO_2 \rightarrow H_2O_2 + O_2$	2.3×10^{-13}	−(600±200)	1.7×10^{-12}	1.3
$H_2O_2 + O_2$	1.7×10^{-33}[M]	−(1000±400)	4.9×10^{-32}[M]	1.3
NO_x Reactions				
$O + NO_2 \rightarrow NO + O_2$	6.5×10^{-12}	−(120±120)	9.7×10^{-12}	1.1
$O + NO_3 \rightarrow O_2 + NO_2$	1.0×10^{-11}	0±150	1.0×10^{-11}	1.5
$O + N_2O_5 \rightarrow$ products			$<3.0\times10^{-16}$	
$O + HNO_3 \rightarrow OH + NO_3$			$<3.0\times10^{-17}$	
$O + HO_2NO_2 \rightarrow$ products	7.8×10^{-11}	3400±750	8.6×10^{-16}	3.0
$H + NO_2 \rightarrow OH + NO$	4.0×10^{-10}	340±300	1.3×10^{-10}	1.3
$OH + NO_3 \rightarrow$ products			2.2×10^{-11}	1.5
$OH + HONO \rightarrow H_2O + NO_2$	1.8×10^{-11}	390±	4.5×10^{-12}	1.5
$OH + HNO_3 \rightarrow H_2O + NO_3$	See reference	1.3		
$OH + HO_2NO_2 \rightarrow$ products	1.3×10^{-12}	−(380±)	4.6×10^{-12}	1.5
$OH + NH_3 \rightarrow H_2O + NH_2$	1.7×10^{-12}	710±200	1.6×10^{-13}	1.2
$HO_2 + NO \rightarrow NO_2 + OH$	3.5×10^{-12}	−(250±50)	8.1×10^{-12}	1.15
$HO_2 + NO_2 \rightarrow HONO + O_2$	See reference			
$HO_2 + NO_3 \rightarrow$ products			3.5×10^{-12}	1.5
$HO_2 + NH_2 \rightarrow$ products			3.4×10^{-11}	2.0
$N + O_2 \rightarrow NO + O$	1.5×10^{-11}	3600±400	8.5×10^{-17}	1.25
$N + O_3 \rightarrow NO + O_2$			$<2.0\times10^{-16}$	
$N + NO \rightarrow N_2 + O$	2.1×10^{-11}	−(100±100)	3.0×10^{-11}	1.3
$N + NO_2 \rightarrow N_2O + O$	5.8×10^{-12}	−(220±100)	1.2×10^{-11}	1.5
$NO + O_3 \rightarrow NO_2 + O_2$	2.0×10^{-12}	1400±200	1.8×10^{-14}	1.1
$NO + NO_3 \rightarrow 2NO_2$	1.5×10^{-11}	−(170±100)	2.6×10^{-11}	1.3
$NO_2 + O_3 \rightarrow NO_3 + O_2$	1.2×10^{-13}	2450±150	3.2×10^{-17}	1.15
$NO_2 + NO_3 \rightarrow NO + NO_2 + O_2$	See reference			
$NO_3 + NO_3 \rightarrow 2NO_2 + O_2$	8.5×10^{-13}	2450±500	2.3×10^{-16}	1.5
$NH_2 + O_2 \rightarrow$ products			$<6.0\times10^{-21}$	
$NH_2 + O_3 \rightarrow$ products	4.3×10^{-12}	930±500	1.9×10^{-13}	3.0
$NH_2 + NO \rightarrow$ products	4.0×10^{-12}	−(450±150)	1.8×10^{-11}	1.3
$NH_2 + NO_2 \rightarrow$ products	2.1×10^{-12}	−(650±250)	1.9×10^{-11}	3.0
$NH + NO \rightarrow$ products	4.9×10^{-11}	0±300	4.9×10^{-11}	1.5
$NH + NO_2 \rightarrow$ products	3.5×10^{-13}	−(1140±500)	1.6×10^{-11}	2.0
$O_3 + HNO_2 \rightarrow O_2 + HNO_3$			$<5.0\times10^{-19}$	
$N_2O_5 + H_2O \rightarrow 2HNO_3$			$<2.0\times10^{-21}$	
$N_2(A,v) + O_2 \rightarrow$ products			2.5×10^{-12}, v=0	1.5
$N_2(A,v) + O_3 \rightarrow$ products			4.1×10^{-11}, v=0	2.0
Reactions of Organic Compounds				
$O + CH_3 \rightarrow$ products	1.1×10^{-10}	0±250	1.1×10^{-10}	1.3
$O + HCN \rightarrow$ products	1.0×10^{-11}	4000±1000	1.5×10^{-17}	10
$O + C_2H_2 \rightarrow$ products	3.0×10^{-11}	1600±250	1.4×10^{-13}	1.3
$O + H_2CO \rightarrow$ products	3.4×10^{-11}	1600±250	1.6×10^{-13}	1.25
$O + CH_3CHO \rightarrow CH_3CO + OH$	1.8×10^{-11}	1100±200	4.5×10^{-13}	1.25
$O_3 + C_2H_2 \rightarrow$ products	1.0×10^{-14}	4100±500	1.0×10^{-20}	3
$O_3 + C_2H_4 \rightarrow$ products	1.2×10^{-14}	2630±100	1.7×10^{-18}	1.25
$O_3 + C_3H_6 \rightarrow$ products	6.5×10^{-15}	1900±200	1.1×10^{-17}	1.2
$OH + CO \rightarrow$ products	1.5×10^{-13} x $(1+0.6P_{atm})$	0±300	1.5×10^{-13} x $(1+0.6P_{atm})$	1.3
$OH + CH_4 \rightarrow CH_3 + H_2O$	2.45×10^{-12}	1775±100	6.3×10^{-15}	1.1
$OH + {}^{13}CH_4 \rightarrow {}^{13}CH_3 + H_2O$	See reference			
$OH + CH_3D \rightarrow$ products	3.5×10^{-12}	1950 ± 200	5.0×10^{-15}	1.15
$OH + H_2CO \rightarrow H_2O + HCO$	1.0×10^{-11}	0±200	1.0×10^{-11}	1.25

Reaction	*A* cm³ molecule⁻¹ s⁻¹	*E*/*R* K	*k* (298 K) cm³ molecule⁻¹ s⁻¹	*f*(298)
$OH + CH_3OH \rightarrow$ products	6.7×10^{-12}	600±300	8.9×10^{-13}	1.2
$OH + CH_3OOH \rightarrow$ products	3.8×10^{-12}	–(200±200)	7.4×10^{-12}	1.5
$OH + HC(O)OH \rightarrow$ products	4.0×10^{-13}	0±200	4.0×10^{-13}	1.3
$OH + HCN \rightarrow$ products	1.2×10^{-13}	400±150	3.1×10^{-14}	3
$OH + C_2H_6 \rightarrow H_2O + C_2H_5$	8.7×10^{-12}	1070±100	2.4×10^{-13}	1.1
$OH + C_3H_8 \rightarrow H_2O + C_3H_7$	1.0×10^{-11}	660±100	1.1×10^{-12}	1.2
$OH + CH_3CHO \rightarrow CH_3CO + H_2O$	5.6×10^{-12}	–(270±200)	1.4×10^{-11}	1.2
$OH + C_2H_5OH \rightarrow$ products	7.0×10^{-12}	235±100	3.2×10^{-12}	1.3
$OH + CH_3C(O)OH \rightarrow$ products	4.0×10^{-13}	–(200±400)	8.0×10^{-13}	1.3
$OH + CH_3C(O)CH_3 \rightarrow CH_3C(O)CH_2 + H_2O$	2.2×10^{-12}	685±100	2.2×10^{-13}	1.15
$OH + CH_3CN \rightarrow$ products	7.8×10^{-13}	1050±200	2.3×10^{-14}	1.5
$OH + CH_3ONO_2 \rightarrow$ products	5.0×10^{-13}	890±500	2.4×10^{-14}	3
$OH + CH_3C(O)O_2NO_2$ (PAN)→ products			$<4\times10^{-14}$	
$OH + C_2H_5ONO_2 \rightarrow$ products	8.2×10^{-13}	450±300	1.8×10^{-13}	3
$HO_2 + CH_2O \rightarrow$ adduct	6.7×10^{-15}	–(600±600)	5.0×10^{-14}	5
$HO_2 + CH_3O_2 \rightarrow CH_3OOH + O_2$	3.8×10^{-13}	–(800±400)	5.6×10^{-12}	2
$HO_2 + C_2H_5O_2 \rightarrow C_2H_5OOH + O_2$	7.5×10^{-13}	–(700±250)	8.0×10^{-12}	1.5
$HO_2 + CH_3C(O)O_2 \rightarrow$ products	4.5×10^{-13}	–(1000±600)	1.3×10^{-11}	2
$NO_3 + CO \rightarrow$ products			$<4.0\times10^{-19}$	
$NO_3 + CH_2O \rightarrow$ products			5.8×10^{-16}	1.3
$NO_3 + CH_3CHO \rightarrow$ products	1.4×10^{-12}	1900±300	2.4×10^{-15}	1.3
$CH_3 + O_2 \rightarrow$ products			$<3.0\times10^{-16}$	
$CH_3 + O_3 \rightarrow$ products	5.4×10^{-12}	220±150	2.6×10^{-12}	2
$HCO + O_2 \rightarrow CO + HO_2$	3.5×10^{-12}	–(140±140)	5.5×10^{-12}	1.3
$CH_2OH + O_2 \rightarrow CH_2O + HO_2$	9.1×10^{-12}	0±200	9.1×10^{-12}	1.3
$CH_3O + O_2 \rightarrow CH_2O + HO_2$	3.9×10^{-14}	900±300	1.9×10^{-15}	1.5
$CH_3O + NO \rightarrow CH_2O + HNO$	See reference			
$CH_3O + NO_2 \rightarrow CH_2O + HONO$	1.1×10^{-11}	1200±600	2.0×10^{-13}	5
$CH_3O_2 + O_3 \rightarrow$ products			$<3.0\times10^{-17}$	
$CH_3O_2 + CH_3O_2 \rightarrow$ products	2.5×10^{-13}	–(190±190)	4.7×10^{-13}	1.5
$CH_3O_2 + NO \rightarrow CH_3O + NO_2$	3.0×10^{-12}	–(280±60)	7.7×10^{-12}	1.15
$CH_3O_2 + CH_3C(O)O_2 \rightarrow$ products	1.3×10^{-12}	–(640±200)	1.1×10^{-11}	1.5
$C_2H_5 + O_2 \rightarrow C_2H_4 + HO_2$			$<2.0\times10^{-14}$	
$C_2H_5O + O_2 \rightarrow CH_3CHO + HO_2$	6.3×10^{-14}	550±200	1.0×10^{-14}	1.5
$C_2H_5O_2 + C_2H_5O_2 \rightarrow$ products	6.8×10^{-14}	0±300	6.8×10^{-14}	2
$C_2H_5O_2 + NO \rightarrow$ products	2.6×10^{-12}	–(365±150)	8.7×10^{-12}	1.2
$CH_3C(O)O_2 + CH_3C(O)O_2 \rightarrow$ products	2.9×10^{-12}	–(500±150)	1.5×10^{-11}	1.5
$CH_3C(O)O_2 + NO \rightarrow$ products	5.3×10^{-12}	–(360±150)	1.8×10^{-11}	1.4
FO_x Reactions				
$O + FO \rightarrow F + O_2$	2.7×10^{-11}	0±250	2.7×10^{-11}	3.0
$O + FO_2 \rightarrow FO + O_2$	5.0×10^{-11}	0±250	5.0×10^{-11}	5.0
$OH + CH_3F \rightarrow CH_2F + H_2O$ (HFC–41)	3.0×10^{-12}	1500±300	2.0×10^{-14}	1.1
$OH + CH_2F_2 \rightarrow CHF_2 + H_2O$ (HFC–32)	1.9×10^{-12}	1550±200	1.0×10^{-14}	1.2
$OH + CHF_3 \rightarrow CF_3 + H_2O$ (HFC–23)	1.0×10^{-12}	2440±200	2.8×10^{-16}	1.3
$OH + CF_3OH \rightarrow CF_3O + H_2O$			$<2\times10^{-17}$	
$OH + CH_3CH_2F \rightarrow$ products (HFC–161)	7.0×10^{-12}	1100±300	1.7×10^{-13}	1.4
$OH + CH_3CHF_2 \rightarrow$ products (HFC–152a)	2.4×10^{-12}	1260±200	3.5×10^{-14}	1.2
$OH + CH_2FCH_2F \rightarrow CHFCH_2F$ (HFC–152) + H_2O	1.7×10^{-11}	1500±500	1.1×10^{-13}	2.0
$OH + CH_3CF_3 \rightarrow CH_2CF_3 + H_2O$ (HFC–143a)	1.8×10^{-12}	2170±150	1.2×10^{-15}	1.1
$OH + CH_2FCHF_2 \rightarrow$ products (HFC–143)	4.0×10^{-12}	1650±300	1.6×10^{-14}	1.5
$OH + CH_2FCF_3 \rightarrow CHFCF_3 + H_2O$ (HFC–134a)	1.5×10^{-12}	1750±200	4.2×10^{-15}	1.1
$OH + CHF_2CHF_2 \rightarrow CF_2CHF_2$ (HFC–134) + H_2O	1.6×10^{-12}	1680±300	5.7×10^{-15}	2.0
$OH + CHF_2CF_3 \rightarrow CF_2CF_3 + H_2O$ (HFC–125)	5.6×10^{-13}	1700±300	1.9×10^{-15}	1.3
$OH + CH_3OCHF_2 \rightarrow$ products (HFOC–152a)	6.0×10^{-12}	1530±150	3.5×10^{-14}	1.2
$OH + CF_3OCH_3 \rightarrow CF_3OCH_2 + H_2O$ (HFOC–143a)	1.5×10^{-12}	1450±150	1.2×10^{-14}	1.1
$OH + CF_2HOCF_2H \rightarrow CF_2OCF_2H$ (HFOC–134) + H_2O	1.9×10^{-12}	2000±150	2.3×10^{-15}	1.2
$OH + CF_3OCHF_2 \rightarrow CF_3OCF_2 + H_2O$ (HFOC–125)	4.7×10^{-13}	2100±300	4.1×10^{-16}	1.2

Reaction	*A* cm³ molecule⁻¹ s⁻¹	*E*/*R* K	*k* (298 K) cm³ molecule⁻¹ s⁻¹	*f*(298)
OH + $CF_3CH_2CH_3$ → products (HFC–263fb)	–	–	4.2×10^{-14}	1.5
OH + $CH_2FCF_2CHF_2$ → products (HFC–245ca)	2.4×10^{-12}	1660±150	9.1×10^{-15}	1.3
OH + $CHF_2CHFCHF_2$ → products (HFC–245ea)	–	–	1.6×10^{-14}	2.0
OH + CF_3CHFCH_2F → products (HFC–245eb)	–	–	1.5×10^{-14}	2.0
OH + $CHF_2CH_2CF_3$ → products (HFC–245fa)	6.1×10^{-13}	1330±150	7.0×10^{-15}	1.2
OH + $CF_3CF_2CH_2F$ → CF_3CF_2CHF (HFC–236cb) +H_2O	1.5×10^{-12}	1750±500	4.2×10^{-15}	2.0
OH + $CF_3CHFCHF_2$ → products (HFC–236ea)	1.1×10^{-12}	1590±150	5.3×10^{-15}	1.1
OH + $CF_3CH_2CF_3$ → CF_3CHCF_3 (HFC–236fa) +H_2O	1.3×10^{-12}	2480±150	3.2×10^{-16}	1.1
OH + CF_3CHFCF_3 → CF_3CFCF_3+H_2O (HFC–227ea)	5.0×10^{-13}	1700±300	1.7×10^{-15}	1.1
OH + $CHF_2OCH_2CF_3$ → products (HFOC–245fa)	2.6×10^{-12}	1610±150	1.2×10^{-14}	2.0
OH + $CF_3CH_2CF_2CH_3$ → products (HFC–365mfc)	2.0×10^{-12}	1750±200	5.7×10^{-15}	1.3
OH + $CF_3CH_2CH_2CF_3$ → products (HFC–356mff)	3.0×10^{-12}	1800±300	7.1×10^{-15}	1.3
OH + $CF_3CF_2CH_2CH_2F$ → products (HFC–356mcf)	1.7×10^{-12}	1110±200	4.2×10^{-14}	2.0
OH + $CHF_2CF_2CF_2CF_2H$ → products (HFC–338pcc)	7.8×10^{-13}	1530±200	4.6×10^{-15}	1.5
OH + $CF_3CH_2CF_2CH_2CF_3$ → products (HFC–458mfcf)	1.2×10^{-12}	1830±200	2.6×10^{-15}	2.0
OH + $CF_3CHFCHFCF_2CF_3$ → products (HFC–43–10mee)	5.2×10^{-13}	1500±300	3.4×10^{-15}	1.3
OH + $CF_3CF_2CH_2CH_2CF_2CF_3$ → (HFC–55–10–mcff) products	–	–	8.3×10^{-15}	1.5
F + O_3 → FO + O_2	2.2×10^{-11}	230±200	1.0×10^{-11}	1.5
F + H_2 → HF + H	1.4×10^{-10}	500±200	2.6×10^{-11}	1.2
F + H_2O → HF + OH	1.4×10^{-11}	0±200	1.4×10^{-11}	1.3
F + HNO_3 → HF + NO_3	6.0×10^{-12}	–(400±200)	2.3×10^{-11}	1.3
F + CH_4 → HF + CH_3	1.6×10^{-10}	260±200	6.7×10^{-11}	1.4
FO + O_3 → products			$<1\times10^{-14}$	
FO + NO → NO_2 + F	8.2×10^{-12}	–(300±200)	2.2×10^{-11}	1.5
FO + FO → 2 F + O_2	1.0×10^{-11}	0±250	1.0×10^{-11}	1.5
FO_2 + O_3 → products			$<3.4\times10^{-16}$	
FO_2 + NO → FNO + O_2	7.5×10^{-12}	690±400	7.5×10^{-13}	2.0
FO_2 + NO_2 → products	3.8×10^{-11}	2040±500	4.0×10^{-14}	2.0
FO_2 + CO → products			$<5.1\times10^{-16}$	
FO_2 + CH_4 → products			$<2\times10^{-16}$	
CF_3O + O_2 → FO_2 + CF_2O	$<3\times10^{-11}$	5000	$<1.5\times10^{-18}$	
CF_3O + O_3 → CF_3O_2 + O_2	2×10^{-12}	1400±600	1.8×10^{-14}	1.3
CF_3O + H_2O → OH + CF_3OH	3×10^{-12}	>3600	$<2\times10^{-17}$	
CF_3O + NO → CF_2O + FNO	3.7×10^{-11}	–(110±70)	5.4×10^{-11}	1.2
CF_3O + NO_2 → products	See reference			
CF_3O + CO → products			$<2\times10^{-15}$	
CF_3O + CH_4 → CH_3 + CF_3OH	2.6×10^{-12}	1420±200	2.2×10^{-14}	1.1
CF_3O + C_2H_6 → C_2H_5 + CF_3OH	4.9×10^{-12}	400±100	1.3×10^{-12}	1.2
CF_3O_2 + O_3 → CF_3O + $2O_2$			$<3\times10^{-15}$	
CF_3O_2 + CO → CF_3O + CO_2			$<5\times10^{-16}$	
CF_3O_2 + NO → CF_3O + NO_2	5.4×10^{-12}	–(320±150)	1.6×10^{-11}	1.1
ClO_x Reactions				
O + ClO → Cl + O_2	3.0×10^{-11}	–(70±70)	3.8×10^{-11}	1.2
O + OClO → ClO + O_2	2.4×10^{-12}	960±300	1.0×10^{-13}	2.0
O + Cl_2O → ClO + ClO	2.7×10^{-11}	530±150	4.5×10^{-12}	1.3
O + HCl → OH + Cl	1.0×10^{-11}	3300±350	1.5×10^{-16}	2.0
O + HOCl → OH + ClO	1.7×10^{-13}	0±300	1.7×10^{-13}	3.0
O + $ClONO_2$ → products	2.9×10^{-12}	800±200	2.0×10^{-13}	1.5
O_3 + OClO → products	2.1×10^{-12}	4700±1000	3.0×10^{-19}	2.5
O_3 + Cl_2O_2 → products	–	–	$<1.0\times10^{-19}$	–
OH + Cl_2 → HOCl + Cl	1.4×10^{-12}	900±400	6.7×10^{-14}	1.2
OH + ClO → products	1.1×10^{-11}	–(120±150)	1.7×10^{-11}	1.5
OH + OClO → HOCl + O_2	4.5×10^{-13}	–(800±200)	6.8×10^{-12}	2.0
OH + HCl → H_2O + Cl	2.6×10^{-12}	350±100	8.0×10^{-13}	1.2
OH + HOCl → H_2O + ClO	3.0×10^{-12}	500±500	5.0×10^{-13}	3.0
OH + $ClNO_2$ → HOCl + NO_2	2.4×10^{-12}	1250±300	3.6×10^{-14}	2.0
OH + $ClONO_2$ → products	1.2×10^{-12}	330±200	3.9×10^{-13}	1.5

Reaction	*A* cm³ molecule⁻¹ s⁻¹	*E*/*R* K	*k* (298 K) cm³ molecule⁻¹ s⁻¹	*f*(298)
$OH + CH_3Cl \rightarrow CH_2Cl + H_2O$	4.0×10^{-12}	1400±250	3.6×10^{-14}	1.2
$OH + CH_2Cl_2 \rightarrow CHCl_2 + H_2O$	3.8×10^{-12}	1050±150	1.1×10^{-13}	1.4
$OH + CHCl_3 \rightarrow CCl_3 + H_2O$	2.0×10^{-12}	900±150	1.0×10^{-13}	1.2
$OH + CCl_4 \rightarrow$ products	$\sim1.0\times10^{-12}$	>2300	$<5.0\times10^{-16}$	–
$OH + CFCl_3 \rightarrow$ products (CFC–11)	$\sim1.0\times10^{-12}$	>3700	$<5.0\times10^{-18}$	–
$OH + CF_2Cl_2 \rightarrow$ products (CFC–12)	$\sim1.0\times10^{-12}$	>3600	$<6.0\times10^{-18}$	–
$OH + CH_2ClF \rightarrow CHClF + H_2O$ (HCFC–31)	2.8×10^{-12}	1270±200	3.9×10^{-14}	1.2
$OH + CHFCl_2 \rightarrow CFCl_2 + H_2O$ (HCFC–21)	1.7×10^{-12}	1250±150	2.6×10^{-14}	1.2
$OH + CHF_2Cl \rightarrow CF_2Cl + H_2O$ (HCFC–22)	1.0×10^{-12}	1600±150	4.7×10^{-15}	1.1
$OH + CH_3OCl \rightarrow$ products	2.4×10^{-12}	360±200	7.2×10^{-13}	3.0
$OH + CH_3CCl_3 \rightarrow CH_2CCl_3 + H_2O$ (HCC–140)	1.8×10^{-12}	1550±150	1.0×10^{-14}	1.1
$OH + C_2HCl_3 \rightarrow$ products	4.9×10^{-13}	–(450±200)	2.2×10^{-12}	1.25
$OH + C_2Cl_4 \rightarrow$ products	9.4×10^{-12}	1200±200	1.7×10^{-13}	1.25
$OH + CCl_3CHO \rightarrow H_2O + CCl_3CO$	8.2×10^{-12}	600±300	1.1×10^{-12}	1.5
$OH + CH_3CFCl_2 \rightarrow CH_2CFCl_2 + H_2O$ (HCFC–141b)	1.7×10^{-12}	1700±150	5.7×10^{-15}	1.2
$OH + CH_3CF_2Cl \rightarrow CH_2CF_2Cl + H_2O$ (HCFC–142b)	1.3×10^{-12}	1800±150	3.1×10^{-15}	1.2
$OH + CH_2ClCF_2Cl \rightarrow CHClCF_2Cl$ (HCFC–132b) $+ H_2O$	3.6×10^{-12}	1600±400	1.7×10^{-14}	2.0
$OH + CHCl_2CF_2Cl \rightarrow CCl_2CF_2Cl$ (HCFC–122) $+ H_2O$	1.0×10^{-12}	900±150	4.9×10^{-14}	1.2
$OH + CHFClCFCl_2 \rightarrow CFClCFCl_2$ (HCFC–122a) $+ H_2O$	1.0×10^{-12}	1250±150	1.5×10^{-14}	1.1
$OH + CH_2ClCF_3 \rightarrow CHClCF_3 + H_2O$ (HCFC–133a)	5.2×10^{-13}	1100±300	1.3×10^{-14}	1.3
$OH + CHCl_2CF_3 \rightarrow CCl_2CF_3 + H_2O$ (HCFC–123)	7.0×10^{-13}	900±150	3.4×10^{-14}	1.2
$OH + CHFClCF_2Cl \rightarrow CFClCF_2Cl$ (HCFC–123a) $+ H_2O$	9.2×10^{-13}	1280±150	1.3×10^{-14}	1.2
$OH + CHFClCF_3 \rightarrow CFClCF_3 + H_2O$ (HCFC–124)	8.0×10^{-13}	1350±150	8.6×10^{-15}	1.2
$OH + CH_3CF_2CFCl_2 \rightarrow$ products (HCFC–243cc)	7.7×10^{-13}	1700±300	2.6×10^{-15}	2.0
$OH + CF_3CF_2CHCl_2 \rightarrow$ products (HCFC–225ca)	1.0×10^{-12}	1100±200	2.5×10^{-14}	1.3
$OH + CF_2ClCF_2CHFCl \rightarrow$ products (HCFC–225cb)	5.5×10^{-13}	1250±200	8.3×10^{-15}	1.3
$HO_2 + Cl \rightarrow HCl + O_2$	1.8×10^{-11}	–(170±200)	3.2×10^{-11}	1.5
$\rightarrow OH + ClO$	4.1×10^{-11}	450±200	9.1×10^{-12}	2.0
$HO_2 + ClO \rightarrow HOCl + O_2$	4.8×10^{-13}	–(700±)	5.0×10^{-12}	1.4
$H_2O + ClONO_2 \rightarrow$ products	–	–	$<2.0\times10^{-21}$	–
$NO + OClO \rightarrow NO_2 + ClO$	2.5×10^{-12}	600±300	3.4×10^{-13}	2.0
$NO + Cl_2O_2 \rightarrow$ products	–	–	$<2.0\times10^{-14}$	–
$NO_3 + HCl \rightarrow HNO_3 + Cl$	–	–	$<5.0\times10^{-17}$	–
$HO_2NO_2 + HCl \rightarrow$ products	–	–	$<1.0\times10^{-21}$	–
$Cl + O_3 \rightarrow ClO + O_2$	2.9×10^{-11}	260±100	1.2×10^{-11}	1.15
$Cl + H_2 \rightarrow HCl + H$	3.7×10^{-11}	2300±200	1.6×10^{-14}	1.25
$Cl + H_2O_2 \rightarrow HCl + HO_2$	1.1×10^{-11}	980±500	4.1×10^{-13}	1.5
$Cl + NO_3 \rightarrow ClO + NO_2$	2.4×10^{-11}	0±400	2.4×10^{-11}	1.5
$Cl + N_2O \rightarrow ClO + N_2$	See reference			
$Cl + HNO_3 \rightarrow$ products	–	–	$<2.0\times10^{-16}$	–
$Cl + CH_4 \rightarrow HCl + CH_3$	1.1×10^{-11}	1400±150	1.0×10^{-13}	1.1
$Cl + CH_3D \rightarrow$ products	–	–	7.4×10^{-14}	2.0
$Cl + H_2CO \rightarrow HCl + HCO$	8.1×10^{-11}	30±100	7.3×10^{-11}	1.15
$Cl + CH_3O_2 \rightarrow$ products	–	–	1.6×10^{-10}	1.5
$Cl + CH_3OH \rightarrow CH_2OH + HCl$	5.4×10^{-11}	0±250	5.4×10^{-11}	1.5
$Cl + C_2H_6 \rightarrow HCl + C_2H_5$	7.7×10^{-11}	90±90	5.7×10^{-11}	1.1
$Cl + C_2H_5O_2 \rightarrow ClO + C_2H_5O$	–	–	7.4×10^{-11}	2.0
$\rightarrow HCl + C_2H_4O_2$	–	–	7.7×10^{-11}	2.0
$Cl + CH_3CN \rightarrow$ products	1.6×10^{-11}	2140±300	1.2×10^{-14}	2.0
$Cl + CH_3CO_3NO_2 \rightarrow$ products	–	–	$<1\times10^{-14}$	
$Cl + C_3H_8 \rightarrow HCl + C_3H_7$	1.2×10^{-10}	–(40±250)	1.4×10^{-10}	1.3
$Cl + OClO \rightarrow ClO + ClO$	3.4×10^{-11}	–(160±200)	5.8×10^{-11}	1.25
$Cl + ClOO \rightarrow Cl_2 + O_2$	2.3×10^{-10}	0±250	2.3×10^{-10}	3.0
$\rightarrow ClO + ClO$	1.2×10^{-11}	0±250	1.2×10^{-11}	3.0
$Cl + Cl_2O \rightarrow Cl_2 + ClO$	6.2×10^{-11}	–(130±130)	9.6×10^{-11}	1.2
$Cl + Cl_2O_2 \rightarrow$ products	–	–	1.0×10^{-10}	2.0
$Cl + HOCl \rightarrow$ products	2.5×10^{-12}	130±250	1.6×10^{-12}	1.5
$Cl + ClNO \rightarrow NO + Cl_2$	5.8×10^{-11}	–(100±200)	8.1×10^{-11}	1.5

Reaction	*A* cm³ molecule⁻¹ s⁻¹	*E*/*R* K	*k* (298 K) cm³ molecule⁻¹ s⁻¹	*f*(298)
$Cl + ClONO_2 \rightarrow$ products	6.5×10^{-12}	−(135±50)	1.0×10^{-11}	1.2
$Cl + CH_3Cl \rightarrow CH_2Cl + HCl$	3.2×10^{-11}	1250±200	4.8×10^{-13}	1.2
$Cl + CH_2Cl_2 \rightarrow HCl + CHCl_2$	3.1×10^{-11}	1350±500	3.3×10^{-13}	1.5
$Cl + CHCl_3 \rightarrow HCl + CCl_3$	8.2×10^{-12}	1325±300	9.6×10^{-14}	1.3
$Cl + CH_3F \rightarrow HCl + CH_2F$ (HFC–41)	2.0×10^{-11}	1200±500	3.5×10^{-13}	1.3
$Cl + CH_2F_2 \rightarrow HCl + CHF_2$ (HFC–32)	1.2×10^{-11}	1630±500	5.0×10^{-14}	1.5
$Cl + CF_3H \rightarrow HCl + CF_3$ (HFC–23)	–	–	3.0×10^{-18}	5.0
$Cl + CH_2FCl \rightarrow HCl + CHFCl$ (HCFC–31)	1.2×10^{-11}	1390±500	1.1×10^{-13}	2.0
$Cl + CHFCl_2 \rightarrow HCl + CFCl_2$ (HCFC–21)	5.5×10^{-12}	1675±200	2.0×10^{-14}	1.3
$Cl + CHF_2Cl \rightarrow HCl + CF_2Cl$ (HCFC–22)	5.9×10^{-12}	2430±200	1.7×10^{-15}	1.3
$Cl + CH_3CCl_3 \rightarrow CH_2CCl_3 + HCl$	2.8×10^{-12}	1790±400	7.0×10^{-15}	2.0
$Cl + CH_3CH_2F \rightarrow HCl + CH_3CHF$ (HFC–161)	1.8×10^{-11}	290±500	6.8×10^{-12}	3.0
$\rightarrow HCl + CH_2CH_2F$	1.4×10^{-11}	880±500	7.3×10^{-13}	3.0
$Cl + CH_3CHF_2 \rightarrow HCl + CH_3CF_2$ (HFC–152a)	6.4×10^{-12}	950±500	2.6×10^{-13}	1.3
$\rightarrow HCl + CH_2CHF_2$	7.2×10^{-12}	2390±500	2.4×10^{-15}	3.0
$Cl + CH_2FCH_2F \rightarrow HCl + CHFCH_2F$ (HFC–152)	2.6×10^{-11}	1060±500	7.5×10^{-13}	3.0
$Cl + CH_3CFCl_2 \rightarrow HCl + CH_2CFCl_2$ (HCFC–141b)	1.8×10^{-12}	2000±300	2.2×10^{-15}	1.2
$Cl + CH_3CF_2Cl \rightarrow HCl + CH_2CF_2Cl$ (HCFC–142b)	1.4×10^{-12}	2420±500	4.2×10^{-16}	1.2
$Cl + CH_3CF_3 \rightarrow HCl + CH_2CF_3$ (HFC–143a)	1.2×10^{-11}	3880±500	2.6×10^{-17}	5.0
$Cl + CH_2FCHF_2 \rightarrow HCl + CH_2FCF_2$ (HFC–143)	5.5×10^{-12}	1610±500	2.5×10^{-14}	3.0
$\rightarrow HCl + CHFCHF_2$	7.7×10^{-12}	1720±500	2.4×10^{-14}	3.0
$Cl + CH_2ClCF_3 \rightarrow HCl + CHClCF_3$ (HCFC–133a)	1.8×10^{-12}	1710±500	5.9×10^{-15}	3.0
$Cl + CH_2FCF_3 \rightarrow HCl + CHFCF_3$ (HFC–134a)	–	–	1.5×10^{-15}	1.2
$Cl + CHF_2CHF_2 \rightarrow HCl + CF_2CHF_2$ (HCF–134)	7.5×10^{-12}	2430±500	2.2×10^{-15}	1.5
$Cl + CHCl_2CF_3 \rightarrow HCl + CCl_2CF_3$ (HCFC–123)	4.4×10^{-12}	1750±500	1.2×10^{-14}	1.3
$Cl + CHFClCF_3 \rightarrow HCl + CFClCF_3$ (HCFC–124)	1.1×10^{-12}	1800±500	2.7×10^{-15}	1.3
$Cl + CHF_2CF_3 \rightarrow HCl + CF_2CF_3$ (HFC–125)	–	–	2.4×10^{-16}	1.3
$ClO + O_3 \rightarrow ClOO + O_2$	–	–	$<1.4\times10^{-17}$	–
$\rightarrow OClO + O_2$	1.0×10^{-12}	>4000	$<1.0\times10^{-18}$	–
$ClO + H_2 \rightarrow$ products	$\sim1.0\times10^{-12}$	>4800	$<1.0\times10^{-19}$	–
$ClO + NO \rightarrow NO_2 + Cl$	6.4×10^{-12}	−(290±100)	1.7×10^{-11}	1.15
$ClO + NO_3 \rightarrow ClOO + NO_2$	4.7×10^{-13}	0±400	4.7×10^{-13}	1.5
$ClO + N_2O \rightarrow$ products	$\sim1.0\times10^{-12}$	>4300	$<6.0\times10^{-19}$	–
$ClO + CO \rightarrow$ products	$\sim1.0\times10^{-12}$	>3700	$<4.0\times10^{-18}$	–
$ClO + CH_4 \rightarrow$ products	$\sim1.0\times10^{-12}$	>3700	$<4.0\times10^{-18}$	–
$ClO + H_2CO \rightarrow$ products	$\sim1.0\times10^{-12}$	>2100	$<1.0\times10^{-15}$	–
$ClO + CH_3O_2 \rightarrow$ products	3.3×10^{-12}	115±115	2.2×10^{-12}	1.5
$ClO + ClO \rightarrow Cl_2 + O_2$	1.0×10^{-12}	1590±300	4.8×10^{-15}	1.5
$\rightarrow ClOO + Cl$	3.0×10^{-11}	2450±500	8.0×10^{-15}	1.5
$\rightarrow OClO + Cl$	3.5×10^{-13}	1370±300	3.5×10^{-15}	1.5
$HCl + ClONO_2 \rightarrow$ products	–	–	$<1.0\times10^{-20}$	–
$CH_2ClO + O_2 \rightarrow CHClO + HO_2$	–	–	6×10^{-14}	5
$CH_2ClO_2 + HO_2 \rightarrow CH_2ClO_2H + O_2$	3.3×10^{-13}	−(820±200)	5.2×10^{-12}	1.5
$CH_2ClO_2 + NO \rightarrow CH_2ClO + NO_2$	7×10^{-12}	−(300±200)	1.9×10^{-11}	1.5
$CCl_3O_2 + NO \rightarrow CCl_2O + NO_2 + Cl$	7.3×10^{-12}	−(270±200)	1.8×10^{-11}	1.3
$CCl_2FO_2 + NO \rightarrow CClFO + NO_2 + Cl$	4.5×10^{-12}	−(350±200)	1.5×10^{-11}	1.3
$CClF_2O_2 + NO \rightarrow CF_2O + NO_2 + Cl$	3.8×10^{-12}	−(400±200)	1.5×10^{-11}	1.2
BrO_x Reactions				
$O + BrO \rightarrow Br + O_2$	1.9×10^{-11}	−(230±150)	4.1×10^{-11}	1.5
$O + HBr \rightarrow OH + Br$	5.8×10^{-12}	1500±200	3.8×10^{-14}	1.3
$O + HOBr \rightarrow OH + BrO$	1.2×10^{-10}	430±300	2.8×10^{-11}	3.0
$OH + Br_2 \rightarrow HOBr + Br$	4.2×10^{-11}	0±600	4.2×10^{-11}	1.3
$OH + BrO \rightarrow$ products	–	–	7.5×10^{-11}	3.0
$OH + HBr \rightarrow H_2O + Br$	1.1×10^{-11}	0±250	1.1×10^{-11}	1.2
$OH + CH_3Br \rightarrow CH_2Br + H_2O$	4.0×10^{-12}	1470±150	2.9×10^{-14}	1.1
$OH + CH_2Br_2 \rightarrow CHBr_2 + H_2O$	2.4×10^{-12}	900±300	1.2×10^{-13}	1.1
$OH + CHBr_3 \rightarrow CBr_3 + H_2O$	1.6×10^{-12}	710±200	1.5×10^{-13}	2.0

Reaction	*A* cm³ molecule⁻¹ s⁻¹	*E*/*R* K	*k* (298 K) cm³ molecule⁻¹ s⁻¹	*f*(298)
$OH + CHF_2Br \rightarrow CF_2Br + H_2O$	1.1×10^{-12}	1400±200	1.0×10^{-14}	1.1
$OH + CH_2ClBr \rightarrow CHClBr + H_2O$	2.3×10^{-12}	930±150	1.0×10^{-13}	1.2
$OH + CF_2ClBr \rightarrow$ products	–	–	$<1.5\times10^{-16}$	–
$OH + CF_2Br_2 \rightarrow$ products	–	–	$<5.0\times10^{-16}$	–
$OH + CF_3Br \rightarrow$ products	–	–	$<1.2\times10^{-16}$	–
$OH + CH_2BrCF_3 \rightarrow CHBrCF_3 + H_2O$	1.4×10^{-12}	1340±200	1.6×10^{-14}	1.3
$OH + CHFBrCF_3 \rightarrow CFBrCF_3$	7.2×10^{-13}	1110±150	1.8×10^{-14}	1.5
$OH + CHClBrCF_3 \rightarrow CClBrCF_3 + H_2O$	1.3×10^{-12}	995±150	4.5×10^{-14}	1.5
$OH + CF_2BrCHFCl \rightarrow CF_2BrCFCl + H_2O$	9.3×10^{-13}	1250±150	1.4×10^{-14}	1.5
$OH + CF_2BrCF_2Br \rightarrow$ products	–	–	$<1.5\times10^{-16}$	–
$HO_2 + Br \rightarrow HBr + O_2$	1.5×10^{-11}	600±600	2.0×10^{-12}	2.0
$HO_2 + BrO \rightarrow$ products	3.4×10^{-12}	–(540±200)	2.1×10^{-11}	1.5
$NO_3 + HBr \rightarrow HNO_3 + Br$	–	–	$<1.0\times10^{-16}$	–
$Cl + CH_2ClBr \rightarrow HCl + CHClBr$	4.3×10^{-11}	1370±500	4.3×10^{-13}	3.0
$Cl + CH_3Br \rightarrow HCl + CH_2Br$	1.5×10^{-11}	1060±100	4.3×10^{-13}	1.2
$Cl + CH_2Br_2 \rightarrow HCl + CHBr_2$	6.4×10^{-12}	810±100	4.2×10^{-13}	1.2
$Br + O_3 \rightarrow BrO + O_2$	1.7×10^{-11}	800±200	1.2×10^{-12}	1.2
$Br + H_2O_2 \rightarrow HBr + HO_2$	1.0×10^{-11}	>3000	$<5.0\times10^{-16}$	–
$Br + NO_3 \rightarrow BrO + NO_2$	–	–	1.6×10^{-11}	2.0
$Br + H_2CO \rightarrow HBr + HCO$	1.7×10^{-11}	800±200	1.1×10^{-12}	1.3
$Br + OClO \rightarrow BrO + ClO$	2.6×10^{-11}	1300±300	3.4×10^{-13}	2.0
$Br + Cl_2O \rightarrow BrCl + ClO$	2.1×10^{-11}	470±150	4.3×10^{-12}	1.3
$Br + Cl_2O_2 \rightarrow$ products	–	–	3.0×10^{-12}	2.0
$BrO + O_3 \rightarrow$ products	$\sim1.0\times10^{-12}$	>3200	$<2.0\times10^{-17}$	–
$BrO + NO \rightarrow NO_2 + Br$	8.8×10^{-12}	–(260±130)	2.1×10^{-11}	1.15
$BrO + NO_3 \rightarrow$ products	–	–	1.0×10^{-12}	3.0
$BrO + ClO \rightarrow Br + OClO$	1.6×10^{-12}	–(430±200)	6.8×10^{-12}	1.25
$\rightarrow Br + ClOO$	2.9×10^{-12}	–(220±200)	6.1×10^{-12}	1.25
$\rightarrow BrCl + O_2$	5.8×10^{-13}	–(170±200)	1.0×10^{-12}	1.25
$BrO + BrO \rightarrow$ products	1.5×10^{-12}	–(230±150)	3.2×10^{-12}	1.15
$CH_2BrO_2 + NO \rightarrow CH_2O + NO_2 + Br$	4×10^{-12}	–(300±200)	1.1×10^{-11}	1.5
IO_x Reactions				
$O + I_2 \rightarrow IO + I$	1.4×10^{-10}	0±250	1.4×10^{-10}	1.4
$O + IO \rightarrow O_2 + I$			1.2×10^{-10}	2.0
$OH + I_2 \rightarrow HOI + I$			1.8×10^{-10}	2.0
$OH + HI \rightarrow H_2O + I$			3.0×10^{-11}	2.0
$OH + CH_3I \rightarrow H_2O + CH_2I$	3.1×10^{-12}	1120±500	7.2×10^{-14}	3.0
$OH + CF_3I \rightarrow HOI + CF_3$			3.1×10^{-14}	5.0
$HO_2 + I \rightarrow HI + O_2$	1.5×10^{-11}	1090±500	3.8×10^{-13}	2.0
$HO_2 + IO \rightarrow HOI + O_2$			8.4×10^{-11}	1.5
$NO_3 + HI \rightarrow HNO_3 + I$	See reference			
$I + O_3 \rightarrow IO + O_2$	2.3×10^{-11}	870±200	1.2×10^{-12}	1.2
$I + BrO \rightarrow IO + Br$	–	–	1.2×10^{-11}	2.0
$IO + NO \rightarrow I + NO_2$	9.1×10^{-12}	–(240±150)	2.0×10^{-11}	1.2
$IO + ClO \rightarrow$ products	5.1×10^{-12}	–(280±200)	1.3×10^{-11}	2.0
$IO + BrO \rightarrow$ products	–	–	6.9×10^{-11}	1.5
$IO + IO \rightarrow$ products	1.5×10^{-11}	–(500±500)	8.0×10^{-11}	1.5
$INO + INO \rightarrow I_2 + 2NO$	8.4×10^{-11}	2620±600	1.3×10^{-14}	2.5
$INO_2 + INO_2 \rightarrow I_2 + 2NO_2$	2.9×10^{-11}	2600±1000	4.7×10^{-15}	3.0
SO_x Reactions				
$O + SH \rightarrow SO + H$	–	–	1.6×10^{-10}	5.0
$O + CS \rightarrow CO + S$	2.7×10^{-10}	760±250	2.1×10^{-11}	1.1
$O + H_2S \rightarrow OH + SH$	9.2×10^{-12}	1800±550	2.2×10^{-14}	1.7
$O + OCS \rightarrow CO + SO$	2.1×10^{-11}	2200±150	1.3×10^{-14}	1.2
$O + CS_2 \rightarrow CS + SO$	3.2×10^{-11}	650±150	3.6×10^{-12}	1.2
$O + CH_3SCH_3 \rightarrow CH_3SO + CH_3$	1.3×10^{-11}	–(410±100)	5.0×10^{-11}	1.1
$O + CH_3SSCH_3 \rightarrow CH_3SO + CH_3S$	5.5×10^{-11}	–(250±100)	1.3×10^{-10}	1.3

Reaction	*A* cm³ molecule⁻¹ s⁻¹	*E*/*R* K	*k* (298 K) cm³ molecule⁻¹ s⁻¹	*f*(298)
$O_3 + H_2S \rightarrow$ products	–	–	$<2.0\times10^{-20}$	–
$O_3 + CH_3SCH_3 \rightarrow$ products	–	–	$<1.0\times10^{-18}$	–
$O_3 + SO_2 \rightarrow SO_3 + O_2$	3.0×10^{-12}	>7000	$<2.0\times10^{-22}$	–
$OH + H_2S \rightarrow SH + H_2O$	6.0×10^{-12}	75±75	4.7×10^{-12}	1.2
$OH + OCS \rightarrow$ products	1.1×10^{-13}	1200±500	1.9×10^{-15}	2.0
$OH + CS_2 \rightarrow$ products	See reference	–	–	–
$OH + CH_3SH \rightarrow CH_3S + H_2O$	9.9×10^{-12}	–(360±100)	3.3×10^{-11}	1.2
$OH + CH_3SCH_3 \rightarrow H_2O + CH_2SCH_3$	1.2×10^{-11}	260±100	5.0×10^{-12}	1.15
$OH + CH_3SSCH_3 \rightarrow$ products	6.0×10^{-11}	–(400±200)	2.3×10^{-10}	1.2
$OH + S \rightarrow H + SO$	–	–	6.6×10^{-11}	3.0
$OH + SO \rightarrow H + SO_2$	–	–	8.6×10^{-11}	2.0
$HO_2 + H_2S \rightarrow$ products	–	–	$<3.0\times10^{-15}$	–
$HO_2 + CH_3SH \rightarrow$ products	–	–	$<4.0\times10^{-15}$	–
$HO_2 + CH_3SCH_3 \rightarrow$ products	–	–	$<5.0\times10^{-15}$	–
$HO_2 + SO_2 \rightarrow$ products	–	–	$<1.0\times10^{-18}$	–
$NO_2 + SO_2 \rightarrow$ products	–	–	$<2.0\times10^{-26}$	–
$NO_3 + H_2S \rightarrow$ products	–	–	$<8.0\times10^{-16}$	–
$NO_3 + OCS \rightarrow$ products	–	–	$<1.0\times10^{-16}$	–
$NO_3 + CS_2 \rightarrow$ products	–	–	$<4.0\times10^{-16}$	–
$NO_3 + CH_3SH \rightarrow$ products	4.4×10^{-13}	–(210±210)	8.9×10^{-13}	1.25
$NO_3 + CH_3SCH_3 \rightarrow CH_3SCH_2 + HNO_3$	1.9×10^{-13}	–(500±200)	1.0×10^{-12}	1.2
$NO_3 + CH_3SSCH_3 \rightarrow$ products	1.3×10^{-12}	270±270	5.3×10^{-13}	1.4
$NO_3 + SO_2 \rightarrow$ products	–	–	$<7.0\times10^{-21}$	–
$N_2O_5 + CH_3SCH_3 \rightarrow$ products	–	–	$<1.0\times10^{-17}$	–
$CH_3O_2 + SO_2 \rightarrow$ products	–	–	$<5.0\times10^{-17}$	–
$F + CH_3SCH_3 \rightarrow$ products	–	–	$2.4.\times10^{-10}$	2.0
$Cl + H_2S \rightarrow HCl + SH$	3.7×10^{-11}	–(210±100)	7.4×10^{-11}	1.25
$Cl + OCS \rightarrow$ products	–	–	$<1.0\times10^{-16}$	–
$Cl + CS_2 \rightarrow$ products	–	–	$<4.0\times10^{-15}$	–
$Cl + CH_3SH \rightarrow CH_3S + HCl$	1.2×10^{-10}	–(150±50)	2.0×10^{-10}	1.25
$Cl + CH_3SCH_3 \rightarrow$ products	See reference	–	–	–
$ClO + OCS \rightarrow$ products	–	–	$<2.0\times10^{-16}$	–
$ClO + CH_3SCH_3 \rightarrow$ products	–	–	9.5×10^{-15}	2.0
$ClO + SO \rightarrow Cl + SO_2$	2.8×10^{-11}	0±50	2.8×10^{-11}	1.3
$ClO + SO_2 \rightarrow Cl + SO_3$	–	–	$<4.0\times10^{-18}$	–
$Br + H_2S \rightarrow HBr + SH$	1.4×10^{-11}	2750±300	1.4×10^{-15}	2.0
$Br + CH_3SH \rightarrow CH_3S + HBr$	9.2×10^{-12}	390±100	2.5×10^{-12}	2.0
$Br + CH_3SCH_3 \rightarrow$ products	See reference			
$BrO + CH_3SCH_3 \rightarrow$ products	1.5×10^{-14}	–(850±200)	2.6×10^{-13}	1.3
$BrO + SO \rightarrow Br + SO_2$			5.7×10^{-11}	1.4
$IO + CH_3SH \rightarrow$ products			6.6×10^{-16}	2.0
$IO + CH_3SCH_3 \rightarrow$ products			1.2×10^{-14}	1.5
$S + O_2 \rightarrow SO + O$	2.3×10^{-12}	0±200	2.3×10^{-12}	1.2
$S + O_3 \rightarrow SO + O_2$			1.2×10^{-11}	2.0
$SO + O_2 \rightarrow SO_2 + O$	2.6×10^{-13}	2400±500	8.4×10^{-17}	2.0
$SO + O_3 \rightarrow SO_2 + O_2$	3.6×10^{-12}	1100±200	9.0×10^{-14}	1.2
$SO + NO_2 \rightarrow SO_2 + NO$	1.4×10^{-11}	0±50	1.4×10^{-11}	1.2
$SO + OClO \rightarrow SO_2 + ClO$			1.9×10^{-12}	3.0
$SO_3 + H_2O \rightarrow$ products	See reference		–	–
$SO_3 + NO_2 \rightarrow$ products			1.0×10^{-19}	10.0
$SH + O_2 \rightarrow OH + SO$			$<4.0\times10^{-19}$	–
$SH + O_3 \rightarrow HSO + O_2$	9.0×10^{-12}	280±200	3.5×10^{-12}	1.3
$SH + H_2O_2 \rightarrow$ products			$<5.0\times10^{-15}$	–
$SH + NO_2 \rightarrow HSO + NO$	2.9×10^{-11}	–(240±50)	6.5×10^{-11}	1.2
$SH + Cl_2 \rightarrow ClSH + Cl$	1.7×10^{-11}	690±200	1.7×10^{-12}	2.0
$SH + BrCl \rightarrow$ products	2.3×10^{-11}	–(350±200)	7.4×10^{-11}	2.0
$SH + Br_2 \rightarrow BrSH + Br$	6.0×10^{-11}	–(160±160)	1.0×10^{-10}	2.0
$SH + F_2 \rightarrow FSH + F$	4.3×10^{-11}	1390±200	4.0×10^{-13}	2.0

Reaction	A cm³ molecule⁻¹ s⁻¹	E/R K	k (298 K) cm³ molecule⁻¹ s⁻¹	$f(298)$
$HSO + O_2 \rightarrow$ products			$<2.0\times10^{-17}$	–
$HSO + O_3 \rightarrow$ products			1.0×10^{-13}	1.3
$HSO + NO \rightarrow$ products			$<1.0\times10^{-15}$	–
$HSO + NO_2 \rightarrow HSO_2 + NO$			9.6×10^{-12}	2.0
$HSO_2 + O_2 \rightarrow HO_2 + SO_2$			3.0×10^{-13}	3.0
$HOSO_2 + O_2 \rightarrow HO_2 + SO_3$	1.3×10^{-12}	330±200	4.4×10^{-13}	1.2
$CS + O_2 \rightarrow OCS + O$			2.9×10^{-19}	2.0
$CS + O_3 \rightarrow OCS + O_2$			3.0×10^{-16}	3.0
$CS + NO_2 \rightarrow OCS + NO$			7.6×10^{-17}	3.0
$CH_3S + O_2 \rightarrow$ products			$<3.0\times10^{-18}$	–
$CH_3S + O_3 \rightarrow$ products	2.0×10^{-12}	–(290±100)	5.3×10^{-12}	1.15
$CH_3S + NO \rightarrow$ products			$<1.0\times10^{-13}$	–
$CH_3S + NO_2 \rightarrow CH_3SO + NO$	2.1×10^{-11}	–(320±100)	6.1×10^{-11}	1.15
$CH_2SH + O_2 \rightarrow$ products			6.5×10^{-12}	2.0
$CH_2SH + O_3 \rightarrow$ products			3.5×10^{-11}	2.0
$CH_2SH + NO \rightarrow$ products			1.9×10^{-11}	2.0
$CH_2SH + NO_2 \rightarrow$ products			5.2×10^{-11}	2.0
$CH_3SO + O_3 \rightarrow$ products			6.0×10^{-13}	1.5
$CH_3SO + NO_2 \rightarrow CH_3SO_2 + NO$			1.2×10^{-11}	1.4
$CH_3SOO + O_3 \rightarrow$ products			$<8.0\times10^{-13}$	–
$CH_3SOO + NO \rightarrow$ products	1.1×10^{-11}	0±100	1.1×10^{-11}	2.0
$CH_3SO_2 + NO_2 \rightarrow$ products	2.2×10^{-11}	0±100	2.2×10^{-11}	2.0
$CH_3SCH_2 + NO_3 \rightarrow$ products			3.0×10^{-10}	2.0
$CH_3SCH_2O_2 + NO \rightarrow CH_3SCH_2O + NO_2$			1.9×10^{-11}	2.0
$CH_3SS + O_3 \rightarrow$ products			4.6×10^{-13}	2.0
$CH_3SS + NO_2 \rightarrow$ products			1.8×10^{-11}	2.0
$CH_3SSO + NO_2 \rightarrow$ products			4.5×10^{-12}	2.0
Metal Reactions				
$Na + O_3 \rightarrow NaO + O_2$	1.0×10^{-9}	95±50	7.3×10^{-10}	1.2
$\rightarrow NaO_2 + O$	–	–	$<4.0\times10^{-11}$	–
$Na + N_2O \rightarrow NaO + N_2$	2.8×10^{-10}	1600±400	1.3×10^{-12}	1.2
$Na + Cl_2 \rightarrow NaCl + Cl$	7.3×10^{-10}	0±200	7.3×10^{-10}	1.3
$NaO + O \rightarrow Na + O_2$	3.7×10^{-10}	0±400	3.7×10^{-10}	3.0
$NaO + O_3 \rightarrow NaO_2 + O_2$	1.1×10^{-9}	570±300	1.6×10^{-10}	1.5
$\rightarrow Na + 2O_2$	6.0×10^{-11}	0±800	6.0×10^{-11}	3.0
$NaO + H_2 \rightarrow NaOH + H$	2.6×10^{-11}	0±600	2.6×10^{-11}	2.0
$NaO + H_2O \rightarrow NaOH + OH$	2.2×10^{-10}	0±400	2.2×10^{-10}	2.0
$NaO + NO \rightarrow Na + NO_2$	1.5×10^{-10}	0±400	1.5×10^{-10}	4.0
$NaO + HCl \rightarrow$ products	2.8×10^{-10}	0±400	2.8×10^{-10}	3.0
$NaO_2 + O \rightarrow NaO + O_2$	2.2×10^{-11}	0±600	2.2×10^{-11}	5.0
$NaO_2 + NO \rightarrow NaO + NO_2$	–	–	$<10^{-14}$	–
$NaO_2 + HCl \rightarrow$ products	2.3×10^{-10}	0±400	2.3×10^{-10}	3.0
$NaOH + HCl \rightarrow NaCl + H_2O$	2.8×10^{-10}	0±400	2.8×10^{-10}	3.0

TABLE 2. Rate Constants for Association Reactions

The values quoted are suitable for air as the third body, M. The integer in parentheses is the power of ten.

Reaction	Low pressure limit $k_0(T) = k_0(300)\,(T/300)^{-n}$ cm⁶ molecule⁻² s⁻¹ $k_0(300)$	n	High pressure limit $k_\infty(T) = k_\infty(300)\,(T/300)^{-m}$ cm³ molecule⁻¹ s⁻¹ $k_\infty(300)$	m
O_x Reactions				
$O + O_2 \rightarrow O_3$	(6.0±0.5) (–34)	2.3±0.5	—	—
$O(^1D)$ Reactions				
$O(^1D) + N_2 \rightarrow N_2O$	(3.5±3.0) (–37)	0.6	—	—

Reaction	Low pressure limit $k_0(T) = k_0(300)\,(T/300)^{-n}$ cm^6 molecule^{-2} s^{-1} $k_0(300)$	n	High pressure limit $k_\infty(T) = k_\infty(300)\,(T/300)^{-m}$ cm^3 molecule^{-1} s^{-1} $k_\infty(300)$	m
HO_x Reactions				
$H + O_2 \rightarrow HO_2$	(5.7±0.5) (–32)	1.6±0.5	(7.5±4.0) (–11)	0±1.0
$OH + OH \rightarrow H_2O_2$	(6.2±1.2) (–31)	1.0	(2.6±1.0) (–11)	0±0.5
NO_x Reactions				
$O + NO \rightarrow NO_2$	(9.0±2.0) (–32)	1.5±0.3	(3.0±1.0) (–11)	0±1.0
$O + NO_2 \rightarrow NO_3$	(9.0±1.0) (–32)	2.0±1.0	(2.2±0.3) (–11)	0±1.0
$OH + NO \rightarrow HONO$	(7.0±1.0) (–31)	2.6±0.3	(3.6±1.0) (–11)	0.1±0.5
$OH + NO_2 \rightarrow HNO_3$	(2.5±0.1) (–30)	4.4±0.3	(1.6±0.2) (–11)	1.7±0.2
$HO_2 + NO_2 \rightarrow HO_2NO_2$	(1.8±0.3) (–31)	3.2±0.4	(4.7±1.0) (–12)	1.4±1.4
$NO_2 + NO_3 \rightarrow N_2O_5$	(2.2±0.5) (–30)	3.9±1.0	(1.5±0.8) (–12)	0.7±0.4
$NO_3 \rightarrow NO + O_2$	See reference			
Hydrocarbon Reactions				
$CH_3 + O_2 \rightarrow CH_3O_2$	(4.5±1.5) (–31)	3.0±1.0	(1.8±0.2) (–12)	1.7±1.7
$C_2H_5 + O_2 \rightarrow C_2H_5O_2$	(1.5±1.0) (–28)	3.0±1.0	(8.0±1.0) (–12)	0±1.0
$OH + C_2H_2 \rightarrow HOCHCH$	(5.5±2.0) (–30)	0.0±0.2	(8.3±1.0) (–13)	–2
$OH + C_2H_4 \rightarrow HOCH_2CH_2$	(1.0±0.6) (–28)	0.8±2.0	(8.8±0.9) (–12)	0
$CH_3O + NO \rightarrow CH_3ONO$	(1.4±0.5) (–29)	3.8±1.0	(3.6±1.6) (–11)	0.6±1.0
$CH_3O + NO_2 \rightarrow CH_3ONO_2$	(1.1±0.4) (–28)	4.0±2.0	(1.6±0.5) (–11)	1.0±1.0
$C_2H_5O + NO \rightarrow C_2H_5ONO$	(2.8±1.0) (–27)	4.0±2.0	(5.0±1.0) (–11)	1.0±1.0
$C_2H_5O + NO_2 \rightarrow C_2H_5ONO_2$	(2.0±1.0) (–27)	4.0±2.0	(2.8±0.4) (–11)	1.0±1.0
$CH_3O_2 + NO_2 \rightarrow CH_3O_2NO_2$	(1.5±0.8) (–30)	4.0±2.0	(6.5±3.2) (–12)	2.0±2.0
$CH_3C(O)O_2 + NO_2 \rightarrow CH_3C(O)O_2NO_2$	(9.7±3.8) (–29)	5.6±2.8	(9.3±0.4)(–12)	1.5±0.3
FO_x Reactions				
$F + O_2 \rightarrow FO_2$	(4.4±0.4) (–33)	1.2±0.5	–	–
$F + NO \rightarrow FNO$	(1.8±0.3) (–31)	1.0±10	(2.8±1.4) (–10)	0.0±1.0
$F + NO_2 \rightarrow FNO_2$	(6.3±3.0) (–32)	2.0±2.0	(2.6±1.3) (–10)	0.0±1.0
$FO + NO_2 \rightarrow FONO_2$	(2.6±2.0) (–31)	1.3±1.3	(2.0±1.0) (–11)	1.5±1.5
$CF_3 + O_2 \rightarrow CF_3O_2$	(3.0±0.3) (–29)	4.0±2.0	(4.0±1.0) (–12)	1.0±1.0
$CF_3O + NO_2 \rightarrow CF_3ONO_2$	See reference			
$CF_3O_2 + NO_2CF_3O_2NO_2$	(2.2±0.5) (–29)	5.0±1.0	(6.0±1.0) (–12)	2.5±1.0
$CF_3O + CO \rightarrow CF_3OCO$	(2.5±0.2) (–31)	–	(6.8±0.4) (–14)	–1.2
$CF_3O \rightarrow CF_2O + F$	See reference			
ClO_x Reactions				
$Cl + O_2 \rightarrow ClOO$	(2.7±1.0) (–33)	1.5±0.5	–	–
$Cl + NO \rightarrow ClNO$	(9.0±2.0) (–32)	1.6±0.5	–	–
$Cl + NO_2$ $ClONO \rightarrow$	(1.3±0.2) (–30)	2.0±1.0	(1.0±0.5) (–10)	1.0±1.0
$ClNO_2$	(1.8±0.3) (–31)	2.0±1.0	(1.0±0.5) (–10)	1.0±1.0
$Cl + CO \rightarrow ClCO$	(1.3±0.5) (–33)	3.8±0.5	–	–
$Cl + C_2H_2 \rightarrow ClC_2H_2$	((5.9±1.0) (–30)	2.1±1.0	(2.1±0.4) (–10)	1.0±0.5
$Cl + C_2H_4 \rightarrow ClC_2H_4$	(1.6±1) (–29)	3.3±1.0	(3.1±2) (–10)	1.0±0.5
$Cl + C_2Cl_4 \rightarrow C_2Cl_5$	(1.4±0.6) (–28)	8.5±1.0	(4.0±1.0) (–11)	1.2±0.5
$ClO + NO_2 \rightarrow ClONO_2$	(1.8±0.3) (–31)	3.4±1.0	(1.5±0.7) (–11)	1.9±1.9
$OClO + NO_3 \rightarrow O_2ClONO_2$	See reference			
$ClO + ClO \rightarrow Cl_2O_2$	(2.2±0.4) (–32)	3.1±0.5	(3.5±2) (–12)	1.0±1.0
$ClO + OClO \rightarrow Cl_2O_3$	(6.2±1.0) (–32)	4.7±0.6	(2.4±1.2) (–11)	0±1.0
$OClO + O \rightarrow ClO_3$	(1.9±0.5) (–31)	1.1±1.0	(3.1±0.8) (–11)	0±1.0
$CH_2Cl + O_2 \rightarrow CH_2ClO_2$	(1.9±0.1) (–30)	3.2±0.2	(2.9±0.2) (–12)	1.2±0.6
$CHCl_2 + O_2 \rightarrow CHCl_2O_2$	(1.3±0.1) (–30)	4.0±0.2	(2.8±0.2) (–12)	1.4±0.6
$CCl_3 + O_2 \rightarrow CCl_3O_2$	(6.9±0.2) (–31)	6.4±0.3	(2.4±0.2) (–12)	2.1±0.6
$CFCl_2 + O_2 \rightarrow CFCl_2O_2$	(5.0±0.8) (–30)	4.0±2.0	(6.0±1.0) (–12)	1.0±1.0
$CF_2Cl + O_2 \rightarrow CF_2ClO_2$	(3.0±1.5) (–30)	4.0±2.0	(3±2) (–12)	1.0±1.0
$CCl_3O_2 + NO_2 \rightarrow CCl_3O_2NO_2$	(5.0±1.0) (–29)	5.0±1.0	(6.0±1.0) (–12)	2.5±1.0
$CFCl_2O_2 + NO_2 \rightarrow CFCl_2O_2NO_2$	(3.5±0.5) (–29)	5.0±1.0	(6.0±1.0) (–12)	2.5±1.0
$CF_2ClO_2 + NO_2 \rightarrow CF_2ClO_2NO_2$	(3.3±0.7) (–29)	6.7±1.3	(4.1±1.9) (–12)	2.8±0.7

Reaction	Low pressure limit $k_0(T) = k_0(300)\,(T/300)^{-n}$ cm^6 molecule^{-2} s^{-1} $k_0(300)$	n	High pressure limit $k_\infty(T) = k_\infty(300)\,(T/300)^{-m}$ cm^3 molecule^{-1} s^{-1} $k_\infty(300)$	m
BrO_x Reactions				
$Br + NO_2 \rightarrow BrNO_2$	(4.2±0.8) (−31)	2.4±0.5	(2.7±0.5) (−11)	0±1.0
$BrO + NO_2 \rightarrow BrONO_2$	(5.2±0.6) (−31)	3.2±0.8	(6.9±1.0) (−12)	2.9±1.0
IO_x Reactions				
$I + NO \rightarrow INO$	(1.8±0.5) (−32)	1.0±0.5	(1.7±1.0) (−11)	0±1.0
$I + NO_2 \rightarrow INO_2$	(3.0±1.5) (−31)	1.0±1.0	(6.6±5.0) (−11)	0±1.0
$IO + NO_2 \rightarrow IONO_2$	(5.9±2.0) (−31)	3.5±1.0	(9.0±1.0) (−12)	1.5±1.0
SO_x Reactions				
$HS + NO \rightarrow HSNO$	(2.4±0.4) (−31)	3.0±1.0	(2.7±0.5) (−11)	0
$CH_3S + NO \rightarrow CH_3SNO$	(3.2±0.4) (−29)	4.0±1.0	(3.9±0.6) (−11)	2.7±1.0
$O + SO_2 \rightarrow SO_3$	(1.3±)(−33)	−3.6±0.7		
$OH + SO_2 \rightarrow HOSO_2$	(3.0±1.0) (−31)	3.3±1.5	(1.5±0.5) (−12)	0
$CH_3SCH_2 + O_2 \rightarrow CH_3SCH_2O_2$	See reference			
$SO_3 + NH_3 \rightarrow H_3NSO_3$	(3.9±0.8) (−30)	3.0±3.0	(4.7±1.3) (−11)	0±1.0
Metal Reactions				
$Na + O_2 \rightarrow NaO_2$	(3.2±0.3) (−30)	1.4±0.3	(6.0±2.0) (−10)	0±1.0
$NaO + O_2 \rightarrow NaO_3$	(3.5±0.7) (−30)	2.0±2.0	(5.7±3.0) (−10)	0±1.0
$NaO + CO_2 \rightarrow NaCO_3$	(8.7±2.6) (−28)	2.0±2.0	(6.5±3.0) (−10)	0±1.0
$NaOH + CO_2 \rightarrow NaHCO_3$	(1.3±0.3) (−28)	2.0±2.0	(6.8±4.0) (−10)	0±1.0

TABLE 3. Equilibrium Constants

$K(T)$/cm^3 molecule^{-1} = A exp (B/T) [200 < T/K < 300]

Reaction	A/cm^3 molecule^{-1}	B/K	K (298 K)	f (298 K)
$HO_2 + NO_2 \rightarrow HO_2NO_2$	2.1×10^{-27}	10900±1000	1.6×10^{-11}	5
$NO + NO_2 \rightarrow N_2O_3$	3.3×10^{-27}	4667±100	2.1×10^{-20}	2
$NO_2 + NO_2 \rightarrow N_2O_4$	5.2×10^{-29}	6643±250	2.5×10^{-19}	2
$NO_2 + NO_3 \rightarrow N_2O_5$	2.7×10^{-27}	11000±500	2.9×10^{-11}	1.3
$CH_3O_2 + NO_2 \rightarrow CH_3O_2NO_2$	1.3×10^{-28}	11200±1000	2.7×10^{-12}	2
$CH_3C(O)O_2 + NO_2 \rightarrow CH_3C(O)O_2NO_2$	9.0×10^{-29}	14000±200	2.3×10^{-8}	2
$F + O_2 \rightarrow FOO$	3.2×10^{-25}	6100±1200	2.5×10^{-16}	1.0
$Cl + O_2 \rightarrow ClOO$	5.7×10^{-25}	2500±750	2.5×10^{-21}	2
$Cl + CO \rightarrow ClCO$	1.6×10^{-25}	4000±500	1.1×10^{-19}	5
$ClO + O_2 \rightarrow ClO\cdot O_2$	2.9×10^{-26}	<3700	$<7.2\times10^{-21}$	–
$ClO + ClO \rightarrow Cl_2O_2$	1.3×10^{-27}	8744±850	7.2×10^{-15}	1.5
$ClO + OClO \rightarrow Cl_2O_3$	1.1×10^{-24}	5455±300	9.8×10^{-17}	3
$OClO + NO_3 \rightarrow O_2ClONO_2$	1×10^{-28}	9300±1000	3.6×10^{-15}	5
$OH + CS_2 \rightarrow CS_2OH$	4.5×10^{-25}	5140±500	1.4×10^{-17}	1.4
$CH_3S + O_2 \rightarrow CH_3SO_2$	1.8×10^{-27}	5545±300	2.2×10^{-19}	1.4

KINETIC DATA FOR COMBUSTION MODELLING

D. L. Baulch, C. J. Cobos, R. A. Cox, C. Esser, P. Frank, Th. Just, J. A. Kerr, M. J. Pilling, J. Troe, R. W. Walker, and J. Warnatz

The following tables present evaluated rate constants and other chemical kinetic data required for modelling the combustion of hydrocarbons. The compilation was prepared as part of the project "Kinetics and Mechanisms of Chemical Processes in Combustion", which is one of the projects in the third European Community Energy Research and Development Program. The tables are reprinted from the *Journal of Physical and Chemical Reference Data* by permission of the authors and the American Institute of Physics.

Table 1 lists all the reactions studied and gives the recommended rate constant k for every bimolecular reaction, as well as the applicable temperature range and the associated error limits. Where more than one set of products is possible, rate constants or branching ratios are given for all channels considered feasible. The data for decomposition reactions and combination reactions are given in Tables 2 and 3, respectively. The reference includes a detailed data sheet for each reaction listed here, covering the thermodynamic data, kinetic measurements, and reliability assessments.

REFERENCE

Baulch, D. L., et al., *J. Phys. Chem. Ref. Data*, 21, 411-734, 1992.

Table 1
BIMOLECULAR REACTIONS

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
O Atom Reactions			
$O + H_2 \rightarrow OH + H$	$8.5 \times 10^{-20} T^{2.67} \exp(-3160/T)$	300–2500	± 0.5 at 300 K falling to ± 0.2 for $T > 500$ K
$O + OH \rightarrow O_2 + H$	$2.0 \times 10^{-11} \exp(112/T)$ $2.4 \times 10^{-11} \exp(-353/T)$	220–500 1000–2000	± 0.2 ± 0.1
$O + HO_2 \rightarrow OH + O_2$	5.3×10^{-11}	300–1000	± 0.3 at 300 K rising to ± 0.5 at 1000 K.
$O + H_2O_2 \rightarrow OH + HO_2$	$1.1 \times 10^{-12} \exp(-2000/T)$	300–500	± 0.3
$O + NH_3 \rightarrow OH + NH_2$	$1.6 \times 10^{-11} \exp(-3670/T)$	500–2500	± 0.5
$O + CH \rightarrow CO + H$ $\rightarrow CHO^+ + e$	6.6×10^{-11} $4.2 \times 10^{-13} \exp(-850/T)$	300–2000 300–2500	± 0.5 ± 0.5
$O + {}^3CH_2 \rightarrow CO + 2H$ $\rightarrow CO + H_2$	2×10^{-10} $k_1/k = 0.6 \pm 0.3$ over whole range	300–2500	± 0.2 at 300 K rising to ± 0.7 at 2500 K.
$O + CH_3 \rightarrow HCHO + H$	1.4×10^{-10}	300–2500	± 0.2
$O + CH_4 \rightarrow OH + CH_3$	$1.5 \times 10^{-15} T^{1.56} \exp(-4270/T)$	300–2500	± 0.3 at 300 K falling to ± 0.15 at 2500 K.
$O + CHO \rightarrow OH + CO$ $\rightarrow CO_2 + H$	5.0×10^{-11} 5.0×10^{-11}	300–2500 300–2500	± 0.3 ± 0.3
$O + HCHO \rightarrow OH + CHO$	$6.9 \times 10^{-13} T^{0.57} \exp(-1390/T)$	250–2200	± 0.1 at 250 K rising to ± 0.3 at 2200 K.
$O + CH_3O \rightarrow O_2 + CH_3$ $\rightarrow OH + HCHO$	2.5×10^{-11} $k_2/k = (0.12 \pm 0.1)$ at 300 K	300–1000	± 0.3 at 300 K rising to ± 0.7 at 1000 K.
$O + CN \rightarrow CO + N(^4S)$ $\rightarrow CO + N(^2D)$	1.7×10^{-11}	300–5000	± 0.2 at 300 K rising to ± 0.6 × 5000 K.
$O + NCO \rightarrow NO + CO$ $\rightarrow O_2 + CN$	7.0×10^{-11}	1450–2600	± 0.8

Table 1

BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
$O + HCN \rightarrow NCO + H$ $\rightarrow CO + NH$ $\rightarrow OH + CN$	$2.3 \times 10^{-18} T^{2.1} \exp(-3075/T)$	450–2500	± 0.2 at 450 K rising to ±0.3 at 2500 K.
$O + CH_3OOH \rightarrow OH + CH_2COOH$ $\rightarrow OH + CH_3O_2$	$6.9 \times 10^{-13} T^{0.57} \exp(-1390/T)$ [estimate]	250–2200	± 0.1 at 250 K rising to ± 0.3 at 2200 K.
$O + C_2H \rightarrow CO + CH$	1.7×10^{-11}	300–2500	± 1.0
$O + C_2H_2 \rightarrow CO + {}^3CH_2$ $\rightarrow CHCO + H$	$3.6 \times 10^{-20} T^{2.8} \exp(-250/T)$ $k_1/k = 0.5 \pm 0.3$ over whole range.	300–2500	± 0.2
$O + C_2H_3 \rightarrow OH + C_2H_2$ $\rightarrow CO + CH_3$ $\rightarrow HCO + CH_2$	5×10^{-11}	300–2000	± 0.5
$O + C_2H_4 \rightarrow CH_2CHO + H$ $\rightarrow HCO + CH_3$ $\rightarrow HCHO + CH_2$ $\rightarrow CH_2CO + H_2$	$5.75 \times 10^{-18} T^{2.08}$ $k_1/k = 0.35 \pm 0.05$ at p> 3 Torr $k_2/k = 0.6 \pm 0.10$	300–2000 over whole temperature range	± 0.1 for $T < 1000$ K rising to ± 0.3 at 2000 K.
$O + C_2H_5 \rightarrow CH_3CHO + H$ $\rightarrow HCHO + CH_3$	1.1×10^{-10} $k_2/k = 0.17 \pm 0.2$ at 300 K	300–2500	± 0.3 from 300 to 1000 K ± 0.5 from 1000 to 2500 K
$O + C_2H_6 \rightarrow OH + C_2H_5$	$1.66 \times 10^{-15} T^{1.5} \exp(-2920/T)$	300–1200	± 0.3 at 300 K falling to ± 0.15 at 1200 K.
$O + CHCO \rightarrow 2CO + H$	1.6×10^{-10}	300–2500	± 0.3
$O + CH_2CO \rightarrow CH_2O + CO$ $\rightarrow HCO + H + CO$ $\rightarrow HCO + HCO$	$3.8 \times 10^{-12} \exp(-680/T)$	230–500	± 0.3
$O + CH_3CHO \rightarrow OH + CH_3CO$ $\rightarrow OH + CH_2CHO$	$9.7 \times 10^{-12} \exp(-910/T)$	300–1500	± 0.05 at 300 K rising to ± 0.5 at 1500 K.
$O + C_2H_5OOH \rightarrow OH + C_2H_4OOH$ $\rightarrow OH + C_2H_5OO$	$6.9 \times 10^{-13} T^{0.57} \exp(-1390/T)$ [estimate]	250–2200	± 0.1 at 150 K rising to ± 0.3 at 2200 K.
$O + C_6H_6 \rightarrow OH + C_6H_5$ $\rightarrow C_6H_5OH$	$1.2 \times 10^{-22} T^{3.7} \exp(-570/T)$	300–1000	± 0.5
$O + C_6H_5CH_2 \rightarrow HCO + C_6H_6$ $\rightarrow C_6H_5CH + H$	5.5×10^{-10}	300	±0.3
$\rightarrow CH_2O + C_6H_5$	No recommendation		
$O + C_6H_5CH_3 \rightarrow$ products	$5.3 \times 10^{-15} T^{1.21} \exp(-1260/T)$	300–2800	± 0.1 at 300 K rising to ± 0.4 at 2800 K
$O + p\text{-}C_6H_4(CH_3)_2 \rightarrow$ products	$2.6 \times 10^{-11} \exp(-1409/T)$	300–600	± 0.3
$O + C_6H_5C_2H_5 \rightarrow$ products	1.0×10^{-13}	298	± 0.3
O_2 Reactions			
$O_2 + CH_4 \rightarrow HO_2 + CH_3$	$6.6 \times 10^{-11} \exp(-28630/T)$	500–2000	± 0.5 at 500 K rising to ± 1.0 at 2000 K.

Table 1

BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
$O_2 + C_2H_6 \rightarrow HO_2 + C_2H_5$	$1.0 \times 10^{-10} \exp(-26100/T)$	500–2000	± 0.5 at 500 K rising to ± 1.0 at 2000 K
$O_2 + HCHO \rightarrow HO_2 + HCO$	$1.0 \times 10^{-10} \exp(-20460/T)$	700–1000	± 0.5
$O_2 + CH_3CHO \rightarrow HO_2 + CH_3CO$	$5.0 \times 10^{-11} \exp(-19700/T)$	600–1100	± 0.5 at 600 K rising to ± 1.0 at 1100 K.
H Atom Reactions			
$H + O_2 \rightarrow OH + O$	$3.3 \times 10^{-10} \exp(-8460/T)$	300–2500	± 0.1 at 300 K rising to ± 0.2 at 2500 K.
$H + O_2 + Ar \rightarrow HO_2 + Ar$	See Table 3		
$H + O_2 + H_2 \rightarrow HO_2 + H_2$	See Table 3		
$H + O_2 + N_2 \rightarrow HO_2 + N_2$	See Table 3		
$H + O_2 + H_2O \rightarrow HO_2 + H_2O$	See Table 3		
$H + H + Ar \rightarrow H_2 + Ar$	See Table 3		
$H + H + H_2 \rightarrow H_2 + H_2$	See Table 3		
$H + OH + H_2O \rightarrow H_2O + H_2O$	See Table 3		
$H + OH + Ar \rightarrow H_2O + Ar$	See Table 3		
$H + HO + N_2 \rightarrow H_2O + N_2$	See Table 3		
$H + HO_2 \rightarrow H_2 + O_2$	$7.1 \times 10^{-11} \exp(-710/T)$	300–1000	± 0.3
$\rightarrow 2\,OH$	$2.8 \times 10^{-10} \exp(-440/T)$	300–1000	± 0.3
$\rightarrow H_2O + O$	$5.0 \times 10^{-11} \exp(-866/T)$	300–1000	± 0.3
$H + H_2O \rightarrow OH + H_2$	$7.5 \times 10^{-16} T^{1.6} \exp(-9270/T)$	300–2500	±0.2
$H + H_2O_2 \rightarrow H_2 + HO_2$	$2.8 \times 10^{-12} \exp(-1890/T)$	300–1000	± 0.3
$\rightarrow OH + H_2O$	$1.7 \times 10^{-11} \exp(-1800/T)$	300–1000	± 0.3
$H + NH \rightarrow H_2 + N$	1.7×10^{-11}	1500–2500	± 1.0
$H + NH_2 \rightarrow H_2 + NH$	1.0×10^{-11}	2000–3000	± 1.0
$H + {}^3CH_2 \rightarrow H_2 + CH$	$1.0 \times 10^{-11} \exp(900/T)$	300–3000	± 0.7
$H + CH_3 \rightarrow H_2 + {}^1CH_2$	$1.0 \times 10^{-10} \exp(-7600/T)$	300–2500	± 1.0
$\rightarrow CH_4$	See Table 3		
$H + CH_4 \rightarrow H_2 + CH_3$	$2.2 \times 10^{-20} T^{3.0} \exp(-4045/T)$	300–2500	± 0.2
$H + CHO \rightarrow H_2 + CO$	1.5×10^{-10}	300–2500	± 0.3
$H + HCHO \rightarrow H_2 + HCO$	$3.8 \times 10^{-14} T^{1.05} \exp(-1650/T)$	300–2200	± 0.1 at 300 K rising to ± 0.5 at 2200 K
$H + CH_3O \rightarrow H_2 + HCHO$	3.0×10^{-11}	300–1000	± 0.5
$H + HNCO \rightarrow NH_2 + CO$	No recommendation		
$\rightarrow H_2 + NCO$	$3.4 \times 10^{-10} T^{-0.27} \exp(-10190/T)$	500–1000	± 1.0
$H + NCO \rightarrow NH + CO$]	8.7×10^{-11}	1400–1500	± 0.5
$\rightarrow HCN + O$]			

Table 1
BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits (Δ log k)
$H + C_2H_2 \rightarrow H_2 + C_2H$ $\rightarrow C_2H_3$	$1.0 \times 10^{-10} \exp(-14000/T)$ See Table 3	1000–3000	± 1.0
$H + C_2H_3 \rightarrow H_2 + C_2H_2$ $\rightarrow C_2H_4$	2.0×10^{-11} See Table 3	300–2500	± 0.5
$H + C_2H_4 \rightarrow C_2H_3 + H_2$ $\rightarrow C_2H_5$	$9.0 \times 10^{-10} \exp(-7500/T)$ See Table 3	700–2000	± 0.5
$H + C_2H_5 \rightarrow 2CH_3$ $\rightarrow C_2H_6$	6.0×10^{-11} See Table 3	300–2000	± 0.3
$H + C_2H_6 \rightarrow H_2 + C_2H_5$	$2.4 \times 10^{-15} T^{1.5} \exp(-3730/T)$	300–2000	± 0.15 at 300 K rising to ± 0.3 at 2000 K
$H + CHCO \rightarrow CH_2 + CO$ $\rightarrow H_2 + C_2O$ $\rightarrow HCCOH$	2.5×10^{-10}	300–2500	± 0.4
$H + CH_2CO \rightarrow CH_3 + CO$ $\rightarrow CH_2CHO$	$3.0 \times 10^{-11} \exp(-1700/T)$ k_2/k very small	200–2000	± 0.5 at 200 K rising to ± 1.0 at 2000 K.
$H + CH_3CHO \rightarrow H_2 + CH_3CO$ $\rightarrow H_2 + CH_2CHO$	$6.8 \times 10^{-15} T^{1.16} \exp(-1210/T)$	300–2000	± 0.1 at 300 rising to ± 0.4 at 2000 K.
$H + C_6H_5 + M \rightarrow C_6H_6 + M$	See Table 3		
$H + C_6H_6 \rightarrow H_2 + C_6H_5$ $\rightarrow C_6H_7$	No recommendation See Table 3		
$H + C_6H_5O + M \rightarrow C_6H_5OH + M$	See Table 3		
$H + C_6H_5OH \rightarrow C_6H_5O + H_2$ $\rightarrow C_6H_6 + OH$	$1.9 \times 10^{-10} \exp(-6240/T)$ $3.7 \times 10^{-11} \exp(-3990/T)$	1000–1150 1000–1150	± 0.3 ± 0.3
$H + C_6H_5CH_2 + M \rightarrow C_6H_5CH_3 + M$	See Table 3		
$H + C_6H_5CH_3 \rightarrow H_2 + C_6H_5CH_2$ $\rightarrow H_2 + C_6H_4CH_3$ $\rightarrow C_6H_6 + CH_3$ $\rightarrow C_6H_6CH_3$	$6.6 \times 10^{-22} T^{3.44} \exp(-1570/T)$ No recommendation No recommendation See Table 3	600–2800	± 0.3 at 600 K rising to ± 0.5 at 2800 K.
$H + p\text{-}C_6H_4(CH_3)_2 \rightarrow$ products	5.8×10^{-13}	298	± 0.1
$H + C_6H_5C_2H_5 \rightarrow H_2 + C_6H_5C_2H_4$ $\rightarrow C_6H_6C_2H_5$	2.4×10^{-12} See Table 3	773	± 0.1
H_2 Reactions			
$H_2 + Ar \rightarrow 2H + Ar$	See Table 2		
$H_2 + H_2 \rightarrow 2H + H_2$	See Table 2		
OH Radical Reactions			
$OH + H_2 \rightarrow H_2O + H$	$1.7 \times 10^{-16} T^{1.6} \exp(-1660/T)$	300–2500	± 0.1 at 300 K rising to ± 0.3 at 2500 K
$OH + OH \rightarrow H_2O + O$	$2.5 \times 10^{-15} T^{1.14} \exp(-50/T)$	250–2500	± 0.2
$OH + OH + M \rightarrow H_2O_2 + M$	See Table 3		

Table 1

BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
$OH + HO_2 \rightarrow H_2O + O_2$	$4.8 \times 10^{-11} \exp(250/T)$	300–2000	± 0.2 at 300 K rising to ± 0.5 at 2000 K.
$OH + H_2O_2 \rightarrow H_2O + HO_2$	$1.3 \times 10^{-11} \exp(-670/T)$	300–1000	± 0.2
$OH + NH \rightarrow NO + H_2$ $\rightarrow H_2O + N$	8.0×10^{-11}	300–1000	± 0.5
$OH + NH_2 \rightarrow O + NH_3$ $\rightarrow H_2O + NH$	$3.3 \times 10^{-14} T^{0.405} \exp(-250/T)$ No recommendation	500–2500	± 0.5
$OH + CO \rightarrow H + CO_2$	$1.05 \times 10^{-17} T^{1.5} \exp(250/T)$	300–2000	± 0.2 at 300 K rising to ± 0.5 at 2000 K.
$OH + CH_3 \rightarrow H + CH_2OH$ $\rightarrow H + CH_3O$ $\rightarrow H_2O + {}^1CH_2$	6.0×10^{-11}	300–2000	± 0.7
$\rightarrow CH_3OH$	See Table 3		
$OH + CH_4 \rightarrow H_2O + CH_3$	$2.6 \times 10^{-17} T^{1.83} \exp(-1400/T)$	250–2500	± 0.07 at 250 K rising to ± 0.15 at 1200 K.
$OH + CHO \rightarrow H_2O + CO$	1.7×10^{-10}	300–2500	± 0.3
$OH + HCHO \rightarrow H_2O + CHO$	$5.7 \times 10^{-15} T^{1.18} \exp(225/T)$	300–3000	± 0.1 at 300 K rising to ± 0.7 at 3000 K.
$OH + CN \rightarrow O + HCN$ $\rightarrow NCO + H$	1.0×10^{-10}	1500–3000	± 0.5
$OH + HCN \rightarrow H_2O + CN$	$1.5 \times 10^{-11} \exp(-5400/T)$	1500–2500	± 0.5
$\rightarrow HOCN + H$ $\rightarrow HNCO + H$	No recommendation		
$OH + CH_3OOH \rightarrow H_2O + CH_3OO$	$1.2 \times 10^{-12} \exp(130/T)$	300–1000	± 0.2 at 300 K rising to ± 0.4 at 1000 K
$\rightarrow H_2O + CH_2OOH$	$1.8 \times 10^{-12} \exp(220/T)$	300–1000	± 0.1 at 300 K rising to ±0.3 at 1000 K.
$OH + C_2H_2 \rightarrow H_2O + C_2H$ $\rightarrow H + CH_2CO$	$1.0 \times 10^{-10} \exp(-6500/T)$	1000–2000	± 1.0
$\rightarrow C_2H_2OH$	See Table 3		
$OH + C_2H_4 \rightarrow H_2O + C_2H_3$	$3.4 \times 10^{-11} \exp(-2990/T)$	650–1500	± 0.5
$OH + C_2H_6 \rightarrow H_2O + C_2H_5$	$1.2 \times 10^{-17} T^{2.0} \exp(-435/T)$	250–2000	± 0.07 at 250 K rising to ± 0.15 at 2000 K.
$OH + CH_2CO \rightarrow CH_2OH + CO$ $\rightarrow H_2CO + HCO$	1.7×10^{-11}	300–2000	± 1.0
$OH + CH_3CHO \rightarrow H_2O + CH_3CO$ $\rightarrow H_2O + CH_2CHO$	$3.9 \times 10^{-14} T^{0.73} \exp(560/T)$	250–1200	± 0.1 at 250 K rising to ± 0.3 at 1200 K.
$OH + C_2H_5OOH \rightarrow H_2O + C_2H_5OO$ $\rightarrow H_2O + C_2H_4OOH$	$3.0 \times 10^{-12} \exp(190/T)$ [estimate]	250–1000	± 0.3 at 250 K rising to ± 0.7 at 1000 K

Table 1

BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
$OH + C_6H_6 \rightarrow H_2O + C_6H_5$	$2.7 \times 10^{-16}\, T^{1.42} \exp(-730/T)$	400–1500	± 0.3
$\rightarrow H + C_6H_5OH$	$2.2 \times 10^{-11} \exp(-5330/T)$	1000–1150	± 0.3
$\rightarrow C_6H_6OH$	See Table 3		
$OH + C_6H_5OH \rightarrow C_6H_5(OH)_2$	See Table 3		
$\rightarrow H_2O + C_6H_5O$]			
$\rightarrow H_2O + C_6H_4OH$]	1.0×10^{-11}	1000–1150	± 0.5
$OH + C_6H_5CH_3 \rightarrow H_2O + C_6H_5CH_2$	$8.6 \cdot 10^{-15}\, T \exp(-1440/T)$	400–1200	± 0.5 at 400 K reducing to ±0.3 at 1200 K.
	See Table 3		
$OH + p\text{-}C_6H_4(CH_3)_2 \rightarrow C_6H_4CH_2CH_3 + H_2O$	$6.4 \times 10^{-11} \exp(-1440/T)$	500–960	±0.1
$\rightarrow p\text{-}C_6H_4(CH_3)_2OH$	See Table 3		
$OH + C_6H_5C_2H_5 \rightarrow HOC_6H_5C_2H_5$	See Table 3		
$\rightarrow H_2O + C_6H_5C_2H_4$]	8.7×10^{-12}	773	± 0.1
$\rightarrow H_2O + C_6H_4C_2H_5$]			
H_2O Reactions			
$H_2O + M \rightarrow H + OH + M$	See Table 2		
HO_2 Radical Reactions			
$HO_2 + HO_2 \rightarrow H_2O_2 + O_2$	$3.1 \times 10^{-12} \exp(-775/T)$	550–1250	± 0.15 at 550 K rising to ± 0.3 at 1250 K.
$HO_2 + NH_2 \rightarrow NH_3 + O_2$]			
$\rightarrow HNO + H_2O$]	2.6×10^{-11}	300–400	± 0.4
$HO_2 + CH_3 \rightarrow OH + CH_3O$	3×10^{-11}	300–2500	± 0.7
$\rightarrow O_2 + CH_4$	No recommendation		
$HO_2 + CH_4 \rightarrow H_2O_2 + CH_3$	$1.5 \times 10^{-11} \exp(-12400/T)$	600–1000	± 0.2 at 600 K rising to ± 0.3 at 1000 K.
$HO_2 + HCHO \rightarrow H_2O_2 + CHO$	$5.0 \times 10^{-12} \exp(-6580/T)$	600–1000	± 0.5
$HO_2 + C_2H_4 \rightarrow OH + C_2H_4O$	$3.7 \times 10^{-12} \exp(-8650/T)$	600–900	± 0.15 at 600 K rising to ± 0.25 at 900 K.
$HO_2 + C_2H_6 \rightarrow H_2O_2 + C_2H_5$	$2.2 \times 10^{-11} \exp(-10300/T)$	500–1000	± 0.2 at 500 K rising to ± 0.3 at 1000 K.
$HO_2 + CH_3CHO \rightarrow H_2O_2 + CH_3CO$	$5.0 \times 10^{-12} \exp(-6000/T)$	900–1200	± 0.7
H_2O_2 Reactions			
$H_2O_2 + M \rightarrow 2OH + M$	See Table 2		
N Atom Reactions			
$N + CN \rightarrow N_2 + C$	3×10^{-10}	300–2500	± 1.0
$N + NCO \rightarrow NO + CN$	No recommendation		
$\rightarrow N_2 + CO$	3.3×10^{-11}	1700	± 0.5

Table 1

BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
NH Radical Reactions			
$NH + O_2 \rightarrow NO + OH$ $\rightarrow NO_2 + H$ $\rightarrow HNO + O$	$1.26 \times 10^{-13} \exp(-770/T)$	270–550	± 0.2 at 270 K rising to ± 0.5 at 550 K.
$NH + NO \rightarrow N_2O + H$ $\rightarrow HN_2 + O$ $\rightarrow N_2 + OH$	5.0×10^{-11}	270–380	± 0.2
NH_2 Radical Reactions			
$NH_2 + O_2 \rightarrow$ products	$< 3 \times 10^{-18}$	298	
$NH_2 + NO \rightarrow N_2 + H_2O$ $\rightarrow N_2 + H + OH$ $\rightarrow N_2H + OH$ $\rightarrow N_2O + H_2$	$1.8 \times 10^{-12} \exp(650/T)$ $(k_2 + k_3)/k \approx 0.12$ at 298 K.	220–2000	± 0.5
$^1C_2$ and $^3C_2$ Radical Reactions	See data sheets.		
CH Radical Reactions			
$CH + O_2 \rightarrow CHO + O$ $\rightarrow CO + OH$	5.5×10^{-11}	300–2000	± 0.3 at 300 K rising to ± 0.5 at 2000 K.
$CH + H_2 \rightarrow CH_2 + H$ $\rightarrow CH_3$	$2.4 \times 10^{-10} \exp(-1760/T)$	300–1000	± 0.3
$CH + H_2O \rightarrow$ products	$9.5 \times 10^{-12} \exp(380/T)$	300–1000	± 1.0
$CH + CO \rightarrow$ products	$4.6 \times 10^{-13} \exp(860/T)$	300–1000	± 1.0
$CH + CO_2 \rightarrow$ products	$5.7 \times 10^{-12} \exp(-345/T)$	300–1000	± 1.0
$CH + CH_4 \rightarrow$ products	$5.0 \times 10^{-11} \exp(200/T)$	200–700	± 1.0
$CH + C_2H_2 \rightarrow$ products	$3.5 \times 10^{-10} \exp(61/T)$	200–700	± 1.0
$CH + C_2H_4 \rightarrow$ products	$2.2 \times 10^{-10} \exp(173/T)$	200–700	± 1.0
$CH + C_2H_6 \rightarrow$ products	$1.8 \times 10^{-10} \exp(132/T)$	200–700	± 1.0
$CH + C_3H_8 \rightarrow$ products	$1.9 \times 10^{-10} \exp(240/T)$	300–700	± 1.0
$CH + n\text{-}C_4H_{10} \rightarrow$ products	$4.4 \times 10^{-10} \exp(28/T)$	250–700	± 1.0
$CH + i\text{-}C_4H_{10} \rightarrow$ products	$2.0 \times 10^{-10} \exp(240/T)$	300–700	± 1.0
$CH +$ neo-$C_5H_{12} \rightarrow$ products	$1.6 \times 10^{-10} \exp(340/T)$	300–700	± 1.0
$CH + CH_3C_2H \rightarrow$ products	No recommendation		
$CH + CH_2O \rightarrow$ products	$1.6 \times 10^{-10} \exp(260/T)$	300–700	± 1.0

Table 1
BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
$^3CH_2$ Radical Reactions			
$^3CH_2 + O_2 \rightarrow CO + H + OH$ $\rightarrow CO_2 + H + H$ $\rightarrow CO + H_2O$ $\rightarrow CO_2 + H_2$ $\rightarrow HCHO + O$	$4.1 \times 10^{-11} \exp(-750/T)$	300–1000	± 0.3 at 300 K rising to ± 0.5 at 1000 K.
$^3CH_2 + {}^3CH_2 \rightarrow C_2H_2 + H_2$ $\rightarrow C_2H_2 + 2H$	$2.0 \times 10^{-10} \exp(-400/T)$ $k_2/k = 0.9 \pm 0.1$ over range 300–3000 K.	300–3000	± 0.5
$^3CH_2 + CH_3 \rightarrow C_2H_4 + H$	7.0×10^{-11}	300–3000	± 0.3 at 300 K rising to ± 0.5 at 3000 K.
$^3CH_2 + C_2H_2 \rightarrow C_3H_4$	See Table 3		
$^3CH_2 + C_2H_4 \rightarrow C_3H_6$ $\rightarrow c\text{-}C_3H_6$ $\rightarrow CH_2CHCH_2 + H$	See Table 3		
$^1CH_2$ Radical Reactions			
$^1CH_2 + Ar \rightarrow {}^3CH_2 + Ar$	6.0×10^{-12}	300–2000	± 0.3
$^1CH_2 + N_2 \rightarrow {}^3CH_2 + N_2$	1.0×10^{-11}	300–2000	± 0.3
$^1CH_2 + CH_4 \rightarrow {}^3CH_2 + CH_4$	1.2×10^{-11}	300–2000	± 0.4
$^1CH_2 + C_2H_2 \rightarrow {}^3CH_2 + C_2H_2$	8.0×10^{-11}	300–2000	± 0.4
$^1CH_2 + C_2H_4 \rightarrow {}^3CH_2 + C_2H_4$	2.3×10^{-11}	300–2000	± 0.4
$^1CH_2 + C_2H_6 \rightarrow {}^3CH_2 + C_2H_6$	3.6×10^{-11}	300–2000	± 0.4
$^1CH_2 + O_2 \rightarrow CO + H + OH$ $\rightarrow CO_2 + H_2$ $\rightarrow CO + H_2O$ $\rightarrow {}^3CH_2 + O_2$	5.2×10^{-11}	300–1000	± 0.3 at 300 K rising to ± 0.5 at 1000 K
$^1CH_2 + H_2 \rightarrow CH_3 + H$	1.2×10^{-10}	300–1000	± 0.1 at 300 K rising to ± 0.3 at 1000 K
$^1CH_2 + C_2H_2 \rightarrow CH_2CCH_2$ $\rightarrow CH_3CCH$ $\rightarrow CH_2CCH + H$	See Table 3		
$\rightarrow {}^3CH_2 + C_2H_2$	See earlier entry		
$^1CH_2 + C_2H_4 \rightarrow C_3H_6$	See Table 3		
$\rightarrow {}^3CH_2 + C_2H_4$	See earlier entry		
CH_3 Radical Reactions			
$CH_3 + M \rightarrow CH_2 + H + M$	See Table 2		
$CH_3 + O_2 \rightarrow CH_3O + O$	$2.2 \times 10^{-10} \exp(-15800/T)$	300–2500	± 0.5
$\rightarrow HCHO + OH$	$5.5 \times 10^{-13} \exp(-4500/T)$	1000–2500	± 0.5
$\rightarrow CH_3O_2$	See Table 3		

Table 1
BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
$CH_3 + H_2 \rightarrow CH_4 + H$	$1.14 \times 10^{-20} T^{2.74} \exp(-4740/T)$	300–2500	± 0.15 in the range 300–700 K. ± 0.3 in the range 700–2500 K.
$CH_3 + CH_3 \rightarrow C_2H_5 + H$	$5 \times 10^{-11} \exp(-6800/T)$	1300–2500	± 0.6
$\rightarrow C_2H_4 + H_2$	No recommendation (see data sheets)		
$\rightarrow C_2H_6$	See Table 3		
$CH_3 + HCHO \rightarrow CH_4 + HCO$	$6.8 \times 10^{-12} \exp(-4450/T)$	300–1000	± 0.3
$CH_3 + C_2H_2 + M \rightarrow C_3H_5 + M$	See Table 3		
$\rightarrow CH_4 + C_2H$	No recommendation		
$CH_3 + C_2H_4 \rightarrow CH_4 + C_2H_3$	$6.9 \times 10^{-12} \exp(-5600/T)$	400–3000	± 0.5
$\rightarrow n\text{-}C_3H_7$	See Table 3		
$CH_3 + C_2H_5 \rightarrow CH_4 + C_2H_4$	1.9×10^{-12}	300–800	± 0.4
$\rightarrow C_3H_8$	See Table 3		
$CH_3 + C_2H_6 \rightarrow CH_4 + C_2H_5$	$2.5 \times 10^{-31} T^{6.0} \exp(-3043/T)$	300–1500	± 0.1 at 300 K rising to ± 0.2 at 1500 K.
$CH_3 + CH_3CHO \rightarrow CH_4 + CH_3CO$	$3.3 \times 10^{-30} T^{5.64} \exp(-1240/T)$	300–1250	± 0.3
$\rightarrow CH_4 + CH_2CHO$	No recommendation (see data sheets)		
CH_4 Reactions			
$CH_4 + M \rightarrow CH_3 + H + M$	See Table 2		
CHO Radical Reactions			
$CHO + O_2 \rightarrow CO + HO_2$ $\rightarrow OH + CO_2$ $\rightarrow HCO_3$	5.0×10^{-12}	300–2500	± 0.3
$CHO + CHO \rightarrow HCHO + CO$	5.0×10^{-11}	300	± 0.3
HCHO Reactions			
$HCHO + M \rightarrow H + CHO + M$ $\rightarrow H_2 + CO + M$	See Table 2		
CH_2OH Reactions			
$CH_2OH + O_2 \rightarrow CH_2O + HO_2$	$2.6 \times 10^{-9} T^{-1.0} +$ $1.2 \times 10^{-10} \exp(-1800/T)$	300–1200	± 0.1 at 300 K rising to ± 0.3 at 1200 K.
CH_3O Radical Reactions			
$CH_3O + M \rightarrow HCHO + H + M$	See Table 2		
$CH_3O + O_2 \rightarrow HCHO + HO_2$	$6.7 \times 10^{-14} \exp(-1070/T)$	300–1000	± 0.2 at 500 K rising to ± 0.3 at 300 K and 1000 K.

Table 1

BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
CH_3OOH Reactions			
$CH_3OOH + M \rightarrow CH_3O + OH + M$	See Table 2		
CN Radical Reactions			
$CN + O_2 \rightarrow NCO + O$	$1.1 \times 10^{-11} \exp(205/T)$	300–2500	± 0.25 at 300 K rising to ± 0.5 at 2500 K.
$CN + H_2O \rightarrow HCN + OH$ $\rightarrow HOCN + H$	$1.3 \times 10^{-11} \exp(-3750/T)$	500–3000	± 0.3 at 500 K rising to ± 0.5 at 3000 K.
$CN + CH_4 \rightarrow HCN + CH_3$	$1.5 \times 10^{-11} \exp(-940/T)$	260–400	± 0.3
NCO Radical Reactions			
$NCO + M \rightarrow N + CO + M$	See Table 2		
$NCO + NO \rightarrow N_2O + CO$ $\rightarrow N_2 + CO_2$ $\rightarrow N_2 + CO + O$	$1.7 \times 10^{-11} \exp(200/T)$	300–600	± 0.5
C_2H Radical Reactions			
$C_2H + O_2 \rightarrow CO_2 + CH$ $\rightarrow 2CO + H$ $\rightarrow C_2HO + O$ $\rightarrow CO + HCO$	3.0×10^{-11}	300	± 0.5
$C_2H + H_2 \rightarrow C_2H_2 + H$	$2.5 \times 10^{-11} \exp(-1560/T)$	300–2500	± 0.3 at 300 K rising to ± 0.7 at 2500 K
$C_2H + C_2H_2 \rightarrow C_4H_2 + H$	5.0×10^{-11}	300–2700	± 0.3
$C_2H + CH_4 \rightarrow$ products	2.0×10^{-12}	298	± 1
$C_2H + C_2H_6 \rightarrow$ products	No recommendation		
C_2H_3 Radical Reactions			
$C_2H_3 + M \rightarrow C_2H_2 + H + M$	See Table 2		
$C_2H_3 + O_2 \rightarrow HCHO + CHO$	9.0×10^{-12}	300–2000	± 0.3 at 300 K rising to ± 0.5 at 2000 K
C_2H_5 Radical Reactions			
$C_2H_5 + O_2 \rightarrow C_2H_4 + HO_2$	$1.7 \times 10^{-14} \exp(1100/T)$	600–1200	± 0.3
$C_2H_5 + C_2H_5 \rightarrow C_2H_6 + C_2H_4$ $\rightarrow n\text{-}C_4H_{10}$	2.4×10^{-12} See Table 3	300–1200	± 0.4
C_2H_6 Reactions			
$C_2H_6 + M \rightarrow CH_3 + CH_3 + M$	See Table 2		

KINETIC DATA FOR COMBUSTION MODELLING (continued)

Table 1

BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
CHCO Reactions			
$CHCO + O_2 \rightarrow CO_2 + HCO$ $\rightarrow 2CO + OH$ $\rightarrow C_2O + HO_2$ $\rightarrow CHO_2CO$	$2.7 \times 10^{-12} \exp(430/T)$ M = He, 2 Torr	300–550	± 0.7
CH_2CHO Radical Reactions			
$CH_2CHO + O_2 \rightarrow HO_2 + CH_2CHO$ $\rightarrow HCHO + CO + OH$ $\rightarrow O_2CH_2CHO$	$k_\infty = 2.6 \times 10^{-13}$ $k_2 = 3.0 \times 10^{-14}$	250–1000 300	± 0.2 ± 0.3
CH_3CO Radical Reactions			
$CH_3CO + O_2 + M \rightarrow CH_3CO_3 + M$	See Table 3		
CH_3CHO Reactions			
$CH_3CHO + M \rightarrow CH_3 + HCO + M$	See Table 2		
C_2H_5O Reactions			
$C_2H_5O + M \rightarrow HCHO + CH_3 + M$ $\rightarrow CH_3CHO + H + M$	See Table 2		
$C_2H_5O + O_2 \rightarrow CH_3CHO + HO_2$	$1.0 \times 10^{-13} \exp(-830/T)$	300–1000	± 0.3 at 300 K rising to ± 0.5 at 1000 K
C_2H_5OOH Reactions			
$C_2H_5OOH + M \rightarrow C_2H_5O + OH + M$	See Table 2		
C_6H_5 Radical Reactions			
$C_6H_5 + M \rightarrow C_2H_2 + C_4H_3 + M$ $\rightarrow C_2H_3 + C_4H_2 + M$ $\rightarrow$ linear-$C_6H_5 + M$	See Table 2		
C_6H_6 Reactions			
$C_6H_6 + M \rightarrow C_6H_5 + H + M$ $\rightarrow C_4H_4 + C_2H_2 + M$	See Table 2		
C_6H_5O Radical Reactions			
$C_6H_5O + M \rightarrow C_5H_5 + CO + M$	See Table 2		
$C_6H_5CH_2$ Radical Reactions			
$C_6H_5CH_2 + M \rightarrow C_3H_3 + 2C_2H_2 + M$ $\rightarrow C_4H_4 + C_3H_3 + M$ $\rightarrow C_5H_5 + C_2H_2 + M$ $\rightarrow C_7H_7$(BCH) + M	See Table 2		

Table 1
BIMOLECULAR REACTIONS (continued)

Reaction	k/cm^3 molecule^{-1}s^{-1}	Temp/K	Error limits ($\Delta \log k$)
$C_6H_5CH_3$ Reactions			
$C_6H_5CH_3 + M \rightarrow C_6H_5CH_2 + H + M$ $\rightarrow C_6H_5 + CH_3 + M$	See Table 2		
p-$C_6H_4(CH_3)_2$ Reactions			
p-$C_6H_4(CH_3)_2 + M \rightarrow C_6H_4CH_2CH_3 + H + M$	See Table 2		
$C_6H_5C_2H_5$ Reactions			
$C_6H_5C_2H_5 + M \rightarrow C_6H_5CH_2 + CH + M$ $\rightarrow C_6H_6 + C_2H_4 + M$ $\rightarrow C_6H_5CHCH_2 + H_2 + M$ $\rightarrow C_6H_5 + C_2H_5 + M$ $\rightarrow C_6H_5CHCH_3 + H + M$	See Table 2		

Table 2
DECOMPOSITION REACTIONS

Reaction	k_∞/s^{-1} k_0/cm^3 molecule^{-1} s^{-1} F_c $k/s^{-1} = \frac{k_0 k_\infty [M]}{k_0[M] + k_\infty} F$	Temp/K	Error limits ($\Delta \log k$)
$H_2 + Ar \rightarrow 2H + Ar$	$k_0 = 3.7 \times 10^{-10} \exp(-48350/T)$	2500–8000	± 0.3
$H_2 + H_2 \rightarrow 2H + H_2$	$k_0 = 1.5 \times 10^{-9} \exp(-48350/T)$	2500–8000	± 0.5
$H_2O + N_2 \rightarrow H + OH + N_2$	$k_0 = 5.8 \times 10^{-9} \exp(-52920/T)$	2000–6000	± 0.5
$H_2O_2 + M \rightarrow 2\,OH + M$	$k_0(Ar) = 3 \times 10^{-8} \exp(-21600/T)$ $k_0(N_2) = 2 \times 10^{-7} \exp(-22900/T)$ $k_\infty = 3 \times 10^{14} \exp(-24400/T)$ $F_c(Ar) = 0.5$	1000–1500 700–1500 1000–1500 700–1500	± 0.2 ± 0.2 ± 0.5 $\Delta F_c = \pm 0.1$
$CH_3 + M \rightarrow CH_2 + H + M$	$k_0 = 1.7 \times 10^{-8} \exp(-45600/T)$	1500–3000	± 0.5
$CH_4 + M \rightarrow CH_3 + H + M$	$k_0(Ar) = 1.2 \times 10^{-6} \exp(-47000/T)$ $k_0(CH_4) = 1.4 \times 10^{-5} \exp(-48100/T)$ $k_\infty = 2.4 \times 10^{16} \exp(-52800/T)$ F_c (Ar) $= \exp(-0.45 - T/3231)$ F_c (CH_4) $= \exp(-0.37 - T/2210)$	1000–3000 1000–2000 1000–3000 1000–3000 1000–2000	± 0.3 ± 0.3 ± 0.5 $\Delta F_c = \pm 0.1$ $\Delta F_c = \pm 0.1$
$HCHO + M \rightarrow H + CHO + M$ $\rightarrow H_2 + CO + M$	$k_0(1) = 2.1 \times 10^{-8} \exp(-39200/T)$ $k_1/k_2 = 0.5$ at 2200 K	1500–2500	± 0.3
$CH_3O + M \rightarrow HCHO + H + M$	$k_0 = 3.16 \times 10^2\, T^{-2.7} \exp(-15400/T)$ [estimate]	300–1000	± 1.0
$CH_3OOH + M \rightarrow CH_3O + OH + M$	$k_\infty = 4 \times 10^{15} \exp(-21600/T)$	400–1000	± 0.5 at 600 K rising to ± 1.0 at 400 and 1000 K
$NCO + Ar \rightarrow N + CO + Ar$	$k_0 = 1.7 \times 10^{-9} \exp(-23500/T)$	1450–2600	± 0.4

Table 2
DECOMPOSITION REACTIONS (continued)

Reaction	k_∞/s^{-1} k_0/cm^3 molecule^{-1} s^{-1} F_c $k/s^{-1} = \frac{k_0 k_\infty [M]}{k_0[M] + k_\infty} F$	Temp/K	Error limits ($\Delta \log k$)
$C_2H_3 + M \rightarrow C_2H_2 + H + M$	$k_0 = 6.9 \times 10^{17} T^{-7.5} \exp(-22900/T)$	500–2500	± 0.5
	$k_\infty = 2 \times 10^{14} \exp(-20000/T)$	500–2500	± 0.5
	$F_c = 0.35$	500–2500	ΔF_c = ± 0.1
$C_2H_6 + M \rightarrow 2CH_3 + M$	$k_0(Ar) = 1.1 \times 10^{25} T^{-8.24} \exp(-47090/T)$	300–2000	± 0.5
	$k_0(C_2H_6) = 4.5 \times 10^{-2} \exp(-41930/T)$	800–1000	± 0.5
	$k_\infty = 1.8 \times 10^{21} T^{-1.24} \exp(-45700/T)$	300–2000	± 0.3
	$F_c(Ar) = 0.38 \exp(-T/73) + 0.62 \exp(-T/1180)$	300–2000	ΔF_c = ± 0.1
	$F_c(C_2H_6) = 0.54 \exp(-T/1250)$	800–1000	ΔF_c = ± 0.1
$CH_3CHO + M \rightarrow CH_3 + CHO + M$	k(1 atm.) $= 7 \times 10^{15} \exp(-41100/T)$ (pressure dependent region)	750–1200	± 0.4
$C_2H_5O + M \rightarrow HCHO + CH_3 + M$	$k_\infty = 8 \times 10^{13} \exp(-10830/T)$ [estimate]	300–600	± 1.0
$C_2H_5OOH + M \rightarrow C_2H_5O + OH + M$	k_∞ $4 \times 10^{15} \exp(-21600/T)$	400–1000	± 1.0
$C_6H_5 + M \rightarrow C_2H_2 + C_4H_3 + M$ $\rightarrow C_2H_3 + C_4H_2 + M$	No recommendation		
$\rightarrow$ linear-$CH_5 + M$	$4.0 \times 10^{13} \exp(-36700/T)$	1450–1900	± 0.4
$C_6H_6 + M \rightarrow C_6H_5 + H + M$ $\rightarrow C_4H_4 + H_2 + M$	$9.0 \times 10^{15} \exp(-54060/T)$	1200–2500	± 0.4 at 1200 K reducing to ± 0.3 at 2500 K
$C_6H_5O + M \rightarrow C_5H_5 + CO + M$	$2.5 \times 10^{11} \exp(-22100/T)$	1000–1580	± 0.2
$C_6H_5CH_2 + M \rightarrow C_3H_3 + 2C_2H_2 + M$ $\rightarrow C_4H_4 + C_3H_3 + M$ $\rightarrow C_5H_5 + C_2H_2 + M$ $\rightarrow C_7H_7$ (BCH) + M	$5.1 \times 10^{13} \exp(-36370/T)$	1350–1900	± 0.3 at 1350 K rising to ± 0.5 1900 K
$C_6H_5CH_3 + M \rightarrow C_6H_5CH_2 + H + M$	$3.1 \times 10^{15} \exp(-44890/T)$	920–2200	± 0.3 at 900 K rising to ± 0.5 at 2200 K
$\rightarrow C_6H_5 + CH_3 + M$	No recommendation		
p-$C_6H_4(CH_3)_2 + M \rightarrow p$-$C_6H_4CH_2CH_3 + H + M$	$4.0 \times 10^{15} \exp(-42600/T)$	1400–1800	± 0.5
$C_6H_5C_2H_5 + M \rightarrow C_6H_5CH_2 + CH + M$	$6.1 \times 10^{15} \exp(-37800/T)$	770–1800	± 0.1 at 770 K rising to ± 0.4 at
$\rightarrow C_6H_6 + C_2H_4 + M$ $\rightarrow C_6H_5CHCH_2 + H_2 + M$ $\rightarrow C_6H_5 + C_2H_5 + M$ $\rightarrow C_6H_5CHCH_3 + H + M$	No recommendations		

Table 3
COMBINATION REACTIONS

Reaction	k_∞/cm^3 molecule$^{-1}s^{-1}$ k_0/cm^6 molecule^{-2} s^{-1} F_c k/cm^3 molecule$^{-1}s^{-1} = \frac{k_0 k_\infty [M]}{k_0[M] + k_\infty} F$	Temp/K	Error limits ($\Delta \log k$)
$H + O_2 + Ar \rightarrow HO_2 + Ar$	$k_0 = 1.7 \times 10^{-30} T^{-0.8}$	300–2000	± 0.5

Table 3

COMBINATION REACTIONS (continued)

Reaction	k_∞/cm^3 molecule^{-1}s^{-1} k_0/cm^6 molecule^{-2} s^{-1} F_c $k = \frac{k_0 k_\infty [M]}{k_0[M] + k_\infty} F$	Temp/K	Error limits ($\Delta \log k$)
$H + O_2 + H_2 \rightarrow HO_2 + H_2$	$k_0 = 5.8 \times 10^{-30} T^{-0.8}$	300–2000	± 0.5
$H + O_2 + N_2 \rightarrow HO_2 + N_2$	$k_0 = 3.9 \times 10^{-30} T^{-0.8}$	300–2000	± 0.5
$H + O_2 + H_2O \rightarrow HO_2 + H_2O$	$k_0 = 4.3 \times 10^{-30} T^{-0.8}$	300–2000	± 0.5
$H + H + Ar \rightarrow H_2 + Ar$	$k_0 = 1.8 \times 10^{-30} T^{-1.0}$	300–2500	± 0.5
$H + H + H_2 \rightarrow H_2 + H_2$	$k_0 = 2.7 \times 10^{-31} T^{-0.6}$	100–5000	± 0.5
$H + OH + H_2O \rightarrow H_2O + H_2O$	$k_0 = 3.9 \times 10^{-25} T^{-2.0}$	300–3000	± 0.3
$H + OH + Ar \rightarrow H_2O + Ar$	$k_0 = 2.3 \times 10^{-26} T^{-2.0}$	300–3000	± 0.3
$H + OH + N_2 \rightarrow H_2O + N_2$	$k_0 = 6.1 \times 10^{-26} T^{-2.0}$	300–3000	± 0.3
$H + CH_3 + M \rightarrow CH_4 + M$	$k_0(He) = 6.2 \times 10^{-29} (T/3000)^{-1.8}$	300–1000	± 0.3
	$k_0(Ar) = 6 \times 10^{-29} (T/300)^{-1.8}$	300–1000	± 0.5
	$k_0(C_2H_6) = 3 \times 10^{-28} (T/300)^{-1.8}$	300–1000	± 0.5
	$k_\infty = 3.5 \times 10^{-10}$	300–1000	± 0.3
	$F_c(He,Ar) = \exp(-0.45 - T/3231)$	300–1000	ΔF_c = ± 0.1
	$F_c(C_2H_6) = \exp(-0.34 - T/3053)$	300–1000	ΔF_c = ± 0.1
$H + C_2H_2 + He \rightarrow C_2H_3 + He$	$k_\infty = 1.4 \times 10^{-11} \exp(-1300/T)$	200–400	± 0.3
	$k_0 = 3.3 \times 10^{-30} \exp(-740/T)$	200–400	± 0.5
	$F_c = 0.44$	200–400	ΔF_c = ± 0.1
$H + C_2H_3 + M \rightarrow C_2H_4 + M$	No recommendation		
$H + C_2H_4 + M \rightarrow C_2H_5 + M$	No recommendation		
$H + C_2H_5 + M \rightarrow C_2H_6 + M$	No recommendation		
$H + C_6H_5 + M \rightarrow C_6H_6 + M$	$k_\infty = 1.3 \times 10^{-10}$	1400–1700	± 0.5
$H + C_6H_6 + M \rightarrow C_6H_7 + M$	$k_\infty = 6.7 \times 10^{-11} \exp(-2170/T)$	300–1000	± 0.2
$H + C_6H_5O + M \rightarrow C_6H_5OH + M$	$k_\infty = 4.2 \times 10^{-10}$	1000	± 0.3
$H + C_6H_5CH_2 + M \rightarrow C_6H_5CH_3 + M$	$k_\infty = 5.5 \times 10^{-10}$	300–2000	± 0.2 at 300 K rising to ± 0.7 at 2000 K.
$H + C_6H_5CH_3 + M \rightarrow C_6H_6CH_3 + M$	$k_\infty = 1.2 \times 10^{-13}$	298	± 0.2
$H + C_6H_5C_2H_5 + M \rightarrow C_6H_6C_2H_5 + M$	$k_\infty = 3.3 \times 10^{-13}$	298	± 0.1
$OH + OH + M \rightarrow H_2O_2 + M$	$k_0(N_2) = 8 \times 10^{-31} (T/300)^{-0.76}$	250–1400	± 0.4
	$k_0(H_2O) = 4 \times 10^{-30}$	300–400	
	$k_\infty = 1.5 \times 10^{-11} (T/300)^{-0.37}$	200–1500	± 0.5
	$F_c(N_2) = 0.5$	200–1500	ΔF_c = ± 0.2
$OH + CH_3 + M \rightarrow CH_3OH + M$	No data available for this channel (See Table 1)		

Table 3

COMBINATION REACTIONS (continued)

Reaction	k_∞/cm^3 molecule^{-1}s^{-1} k_0/cm^6 molecule^{-2} s^{-1} F_c k/cm^3 molecule^{-1}s^{-1} = $\frac{k_0 k_\infty [M]}{k_0[M] + k_\infty} F$	Temp/K	Error limits ($\Delta \log k$)
$OH + C_2H_2 + M \rightarrow C_2H_2OH + M$	See data sheet		
$OH + C_6H_6 + M \rightarrow C_6H_6OH + M$	$k_\infty = 3.8 \times 10^{-12} \exp(-340/T)$	240–340	± 0.2
$OH + C_6H_5OH + M \rightarrow C_6H_5(OH)_2 + M$	$k_\infty = 2.8 \times 10^{-11}$	298	± 0.1
$OH + C_6H_5CH_3 + M \rightarrow HOC_6H_5CH_3 + M$	$k_\infty = 3.8 \times 10^{-12} \exp(180/T)$	200–300	± 0.4
$OH + C_6H_4(CH_3)_2 + M \rightarrow C_6H_4(CH_3)_2OH + M$	$k_\infty = 1.4 \times 10^{-11}$	300–320	± 0.1
$OH + C_6H_5C_2H_5 + M \rightarrow HOC_6H_5C_2H_5 + M$	7.5×10^{-12} at p ≤ 1 atm.	298	± 0.1
$^3CH_2 + C_2H_2 + M \rightarrow C_3H_4 + M$	$2.0 \times 10^{-11} \exp(-3330/T)$ at p = ≤ 10 Torr.	300–1000	± 0.3
$^3CH_2 + C_2H_4 + M \rightarrow C_3H_6 + M$ $\rightarrow c\text{-}C_3H_6 + M$ $\rightarrow C_3H_5 + H + M$	$5.3 \times 10^{-12} \exp(-2660/T)$	300–1000	± 0.2 at 300 K rising to ± 0.3 at 1000 K
$^1CH_2 + C_2H_2 + M \rightarrow CH_2CCH_2 + M$ $\rightarrow CH_3CCH + M$ $\rightarrow CH_2CCH + H + M$	3.7×10^{-10} independent of p	300–1000	± 0.3 at 300 K rising to ± 0.7 at 1000 K.
$^1CH_2 + C_2H_4 + M \rightarrow C_3H_6$	1.1×10^{-10} independent of p	300–1000	± 0.2 at 300 K rising to ± 0.5 at 1000 K.
$CH_3 + O_2 + M \rightarrow CH_3O_2 + M$	$k_0(Ar) = 1.5 \times 10^{-22} T^{-3.3}$	300–800	± 0.3
	$k_0(N_2) = 1.6 \times 10^{-22} T^{-3.3}$	300–800	± 0.3
	$k_\infty = 1.3 \times 10^{-15} T^{-1.2}$	300–800	± 0.3
	$F_c = 0.466 - 1.30 \times 10^{-4} T$	300–800	
$CH_3 + CH_3 + Ar \rightarrow C_2H_6 + Ar$	$k_\infty = 6 \times 10^{-11}$	300–2000	± 0.05 at 300 K rising to ± 0.3 at 2000 K
	$k_0 = 3.5 \times 10^{-7} T^{-7.0} \exp(-1390/T)$	300–2000	± 0.3
	$F_c = 0.38 \exp(-T/73)$ + $0.62\exp(-T/1180)$	300–2000	ΔF_c = ± 0.1
$CH_3 + C_2H_2 + M \rightarrow C_3H_5 + M$	$k_\infty = 1 \times 10^{-12} \exp(-3900/T)$	300–600	± 0.5
$CH_3 + C_2H_4 + M \rightarrow n\text{-}C_3H_7 + M$	$3.5 \times 10^{-13} \exp(-3700/T)$	300–600	± 0.3
$CH_3 + C_2H_5 + M \rightarrow C_3H_8 + M$	$k_\infty = 4.7 \times 10^{-11}$	300–800	± 0.3
$C_2H_5 + C_2H_5 + M \rightarrow n\text{-}C_4H_{10} + M$	$k_\infty = 1.9 \times 10^{-11}$	300–1200	± 0.3
$CH_3CO + O_2 + M \rightarrow CH_3CO_3 + M$	2×10^{-12} for p = 1–4 Torr.	300	± 0.3

ELECTRICAL CONDUCTIVITY OF WATER

This table gives the electrical conductivity of highly purified water over a range of temperature and pressure. The first column of conductivity data refers to water at its own vapor pressure. Equations for calculating the conductivity at any temperature and pressure may be found in the reference.

Reference

Marshall, W. L., *J. Chem. Eng. Data* 32, 221, 1987.

Conductivity in μS/cm at the Indicated Pressure

t/°C	Sat. vapor	50 MPa	100 MPa	200 MPa	400 MPa	600 MPa
0	0.0115	0.0150	0.0189	0.0275	0.0458	0.0667
25	0.0550	0.0686	0.0836	0.117	0.194	0.291
100	0.765	0.942	1.13	1.53	2.45	3.51
200	2.99	4.08	5.22	7.65	13.1	19.5
300	2.41	4.87	7.80	14.1	28.9	46.5
400		1.17	4.91	14.3	39.2	71.3
600			0.134	4.65	33.8	85.7

ELECTRICAL CONDUCTIVITY OF AQUEOUS SOLUTIONS

The following table gives the electrical conductivity of aqueous solutions of some acids, bases, and salts as a function of concentration. All values refer to 20°C. The conductivity κ (often called specific conductance in older literature) is the reciprocal of the resistivity. The molar conductivity Λ is related to this by $\Lambda = \kappa/c$, where c is the amount-of-substance concentration of the electrolyte. Thus if κ has units of millisiemens per centimeter (mS/cm), as in this table, and c is expressed in mol/L, then Λ has units of S cm^2 mol^{-1}. For these electrolytes the concentration c corresponding to the mass percent values given here can be found in the table "Concentrative Properties of Aqueous Solutions" in Section 7.

References

1. *CRC Handbook of Chemistry, and Physics, 70th Edition*, 1989, p. D-221.
2. Wolf, A. V., *Aqueous Solutions and Body Fluids*, Hoeber, 1996.

Electrical Conductivity κ in mS/cm for the Indicated Concentration in Mass Percent

Name	Formula	0.5%	1%	2%	5%	10%	15%	20%	25%	30%	40%	50%
Acetic acid	CH_3COOH	0.3	0.6	0.8	1.2	1.5	1.7	1.7	1.6	1.4	1.1	0.8
Ammonia	NH_3	0.5	0.7	1.0	1.1	1.0	0.7	0.5	0.4			
Ammonium chloride	NH_4Cl	10.5	20.4	40.3	95.3	180						
Ammonium sulfate	$(NH_4)_2SO_4$	7.4	14.2	25.7	57.4	105	147	185	215			
Barium chloride	$BaCl_2$	4.7	9.1	17.4	40.4	76.7	109.0	137.0				
Calcium chloride	$CaCl_2$	8.1	15.7	29.4	67.0	117	157	177	183	172	106	
Cesium chloride	CsCl	3.8	7.4	13.8	32.9	65.8	102	142				
Citric acid	$H_3C(OH)(COO)_3$	1.2	2.1	3.0	4.7	6.2	7.0	7.2	7.1			
Copper(II) sulfate	$CuSO_4$	2.9	5.4	9.3	19.0	32.2	42.3					
Formic acid	HCOOH	1.4	2.4	3.5	5.6	7.8	9.0	9.9	10.4	10.5	9.9	8.6
Hydrogen chloride	HCl	45.1	92.9	183								
Lithium chloride	LiCl	10.1	19.0	34.9	76.4	127	155	170	165	146		
Magnesium chloride	$MgCl_2$	8.6	16.6	31.2	66.9	108	129	134	122	98		
Magnesium sulfate	$MgSO_4$	4.1	7.6	13.3	27.4	42.7	54.2	51.1	44.1			
Manganese(II) sulfate	$MnSO_4$		6.2	10.6	21.6	34.5	43.7	47.6				
Nitric acid	HNO_3	28.4	56.1	108								
Oxalic acid	$H_2C_2O_4$	14.0	21.8	35.3	65.6							
Phosphoric acid	H_3PO_4	5.5	10.1	16.2	31.5	59.4	88.4	118	146	173	209	
Potassium bromide	KBr	5.2	10.2	19.5	47.7	95.6	144	194				
Potassium carbonate	K_2CO_3	7.0	13.6	25.4	58.0	109	152	188	223			
Potassium chloride	KCl	8.2	15.7	29.5	71.9	143	208					
Potassium dihydrogen phosphate	KH_2PO_4	3.0	5.9	11.0	25.0	44.6						
Potassium hydrogen carbonate	$KHCO_3$	4.6	8.9	17.0	38.8	72.4	101	128				
Potassium hydrogen phosphate	K_2HPO_4	5.2	9.9	18.3	40.3							
Potassium hydroxide	KOH	20.0	38.5	75.0	178							
Potassium iodide	KI	3.8	7.5	14.2	35.2	71.8	110	188	224			
Potassium nitrate	KNO_3	5.5	10.7	20.1	47.0	87.3	124	157	182			
Potassium permanganate	$KMnO_4$	3.5	6.9	13.0	30.5							
Potassium sulfate	K_2SO_4	5.8	11.2	21.0	48.0	88.6						
Silver(I) nitrate	$AgNO_3$	3.1	6.1	12.0	26.7	49.8	72.0	92.8	112	129	162	
Sodium acetate	$NaCH_3COO$	3.9	7.6	14.4	30.9	53.4	64.1	69.3	69.2	64.3		
Sodium bromide	NaBr	5.0	9.7	18.4	44.0	84.6	122	157	191	216		
Sodium carbonate	Na_2CO_3	7.0	13.1	23.3	47.0	74.4	88.6					
Sodium chloride	NaCl	8.2	16.0	30.2	70.1	126	171	204	222			
Sodium citrate	$Na_3C_6H_5O_7$		7.4	12.8	26.2	42.1	52.0	57.1	57.3	53.5		
Sodium dihydrogen phosphate	NaH_2PO_4	2.2	4.4	9.1	21.0	33.2	43.3	49.6	53.1	54.0	46.1	
Sodium hydrogen carbonate	$NaHCO_3$	4.2	8.2	15.0	31.4							
Sodium hydrogen phosphate	Na_2HPO_4	4.6	8.7	15.6	31.4							
Sodium hydroxide	NaOH	24.8	48.6	93.1	206							
Sodium nitrate	$NaNO_3$	5.4	10.6	20.4	46.2	82.6	111	134	152	165	178	
Sodium phosphate	Na_3PO_4	7.3	14.1	22.7	43.5							
Sodium sulfate	Na_2SO_4	5.9	11.2	19.8	42.7	71.3	91.1	109				
Sodium thiosulfate	$Na_2S_2O_3$	5.7	10.7	19.5	43.3	76.7	104	123	134	136	118	
Strontium chloride	$SrCl_2$	5.9	11.4	22.0	49.1	91.5	127	153	168	178		
Sulfuric acid	H_2SO_4	24.3	47.8	92	211							
Trichloroacetic acid	CCl_3COOH	10.3	19.6	37.2	84.7	148	193	221				
Zinc sulfate	$ZnSO_4$	2.8	5.4	10.0	20.5	33.7	43.3					

THERMODYNAMIC PROPERTIES OF AIR

These tables summarize the thermodynamic properties of air in the liquid and gaseous states, as well as along the saturation line. In the table for the saturation state, *P*(boil) is the bubble point temperature (i.e., the pressure at which boiling begins as the temperature of the liquid is raised), and *P*(con) is the dew point temperature (pressure at which condensation begins as the temperature of the gas is lowered). The other properties tabulated are density (ρ), enthalpy (*H*), entropy (*S*), and isobaric heat capacity (C_p). More detailed tables may be found in the references.

References

1. Vasserman, A. A., and Rabinovich, V. A., *Thermophysical Properties of Liquid Air and its Components*, Izdatel'stvo Komiteta, Standartov, Moscow, 1968.
2. Vasserman, A. A., et al., *Thermophysical Properties of Air and Air Components,* Izdatel'stvo Nauka, Moscow, 1966.

Properties in the saturation state:

T K	*P*(boil) bar	*P*(con) bar	ρ (liq) g/cm³	ρ (gas) g/L
65	0.1468	0.0861	0.939	0.464
70	0.3234	0.2052	0.917	1.033
75	0.6366	0.4321	0.894	2.048
80	1.146	0.8245	0.871	3.709
85	1.921	1.453	0.845	6.258
90	3.036	2.397	0.819	9.980
95	4.574	3.748	0.792	15.21
100	6.621	5.599	0.763	22.39
110	12.59	11.22	0.699	45.15
120	21.61	20.14	0.622	87.34
130	34.16	33.32	0.487	184.33
132.55	37.69	37.69	0.313	312.89

Properties of liquid air:

P bar	*T* K	ρ g/cm³	*H* J/g	*S* J/g K	C_p J/g K
1	75	0.8935	−131.7	2.918	1.843
5	75	0.8942	−131.4	2.916	1.840
5	80	0.8718	−122.3	3.031	1.868
5	85	0.8482	−112.9	3.143	1.901
5	90	0.8230	−103.3	3.250	1.941
5	95	0.7962	−93.5	3.356	1.991
10	75	0.8952	−131.1	2.913	1.836
10	80	0.8729	−122.0	3.028	1.863
10	90	0.8245	−103.1	3.246	1.932
10	100	0.7695	−83.2	3.452	2.041
50	75	0.9025	−128.2	2.892	1.806
50	100	0.7859	−81.8	3.415	1.939
50	125	0.6222	−28.3	3.889	2.614
50	150	0.1879	91.9	4.764	2.721
100	75	0.9111	−124.5	2.867	1.774
100	100	0.8033	−79.4	3.376	1.852
100	125	0.6746	−31.4	3.805	2.062
100	150	0.4871	32.8	4.271	2.832

Properties of air in the gaseous state:

P bar	*T* K	ρ g/L	*H* J/g	*S* J/g K	C_p J/g K
1	100	3.556	98.3	5.759	1.032
1	200	1.746	199.7	6.463	1.007
1	300	1.161	300.3	6.871	1.007
1	500	0.696	503.4	7.389	1.030
1	1000	0.348	1046.6	8.138	1.141
10	200	17.835	195.2	5.766	1.049
10	300	11.643	298.3	6.204	1.021
10	500	6.944	502.9	6.727	1.034
10	1000	3.471	1047.2	7.477	1.142
100	200	213.950	148.8	4.949	1.650
100	300	116.945	279.9	5.486	1.158
100	500	66.934	499.0	6.048	1.073
100	1000	33.613	1052.4	6.812	1.151

PROPERTIES OF WATER IN THE RANGE 0–100 °C

This table summarizes the best available values of the density, specific heat capacity at constant pressure (C_p), vapor pressure, viscosity, thermal conductivity, dielectric constant, and surface tension for liquid water in the range 0 – 100 °C. All values (except vapor pressure) refer to a pressure of 100 kPa (1 bar). The temperature scale is IPTS-68.

References

1. L. Harr, J. S. Gallagher, and G. S. Kell, *NBS/NRC Steam Tables*, Hemisphere Publishing Corp., New York, 1984.
2. K. N. Marsh, Ed., *Recommended Reference Materials for the Realization of Physicochemical Properties*, Blackwell Scientific Publications, Oxford, 1987.
3. J. V. Sengers and J. T. R. Watson, Improved international formulations for the viscosity and thermal conductivity of water substance, *J. Phys. Chem. Ref. Data*, 15, 1291, 1986.
4. D. G. Archer and P. Wang, The dielectric constant of water and Debye-Hückel limiting law slopes, *J. Phys. Chem. Ref. Data*, 19, 371, 1990.
5. N. B. Vargaftik, et al., International tables of the surface tension of water, *J. Phys. Chem. Ref. Data*, 12, 817, 1983.

t °C	Density g/cm³	C_p J/g K	Vap. pres. kPa	Visc. μPa s	Ther. cond. mW/K m	Diel. const.	Surf. ten. mN/m
0	0.99984	4.2176	0.6113	1793	561.0	87.90	75.64
10	0.99970	4.1921	1.2281	1307	580.0	83.96	74.23
20	0.99821	4.1818	2.3388	1002	598.4	80.20	72.75
30	0.99565	4.1784	4.2455	797.7	615.4	76.60	71.20
40	0.99222	4.1785	7.3814	653.2	630.5	73.17	69.60
50	0.98803	4.1806	12.344	547.0	643.5	69.88	67.94
60	0.98320	4.1843	19.932	466.5	654.3	66.73	66.24
70	0.97778	4.1895	31.176	404.0	663.1	63.73	64.47
80	0.97182	4.1963	47.373	354.4	670.0	60.86	62.67
90	0.96535	4.2050	70.117	314.5	675.3	58.12	60.82
100	0.95840	4.2159	101.325	281.8	679.1	55.51	58.91
Ref.	1–3	2	1, 3	3	3	4	5

ENTHALPY OF VAPORIZATION OF WATER

The enthalpy (heat) of vaporization of water is tabulated as a function of temperature on the IPTS-68 scale.

Reference

Marsh, K. N., Ed., *Recommended Reference Materials for the Realization of Physicochemical Properties*, Blackwell, Oxford, 1987.

t °C	$\Delta_{vap}H$ kJ/mol	*t* °C	$\Delta_{vap}H$ kJ/mol
0	45.054	200	34.962
25	43.990	220	33.468
40	43.350	240	31.809
60	42.482	260	29.930
80	41.585	280	27.795
100	40.657	300	25.300
120	39.684	320	22.297
140	38.643	340	18.502
160	37.518	360	12.966
180	36.304	374	2.066

ENTHALPY OF VAPORIZATION OF WATER

The enthalpy (heat) of vaporization of water is tabulated as a function of temperature on the IPTS-68 scale.

Reference

Marsh, K. N., Ed., *Recommended Reference Materials for the Realization of Physicochemical Properties*, Blackwell, Oxford, 1987.

t °C	$\Delta_{vap}H$ kJ/mol	t °C	$\Delta_{vap}H$ kJ/mol
0	45.054	200	34.962
25	43.990	220	33.468
40	43.350	240	31.809
60	42.482	260	29.930
80	41.585	280	27.795
100	40.657	300	25.300
120	39.684	320	22.297
140	38.643	340	18.502
160	37.518	360	12.966
180	36.304	374	2.066

FIXED POINT PROPERTIES OF H_2O AND D_2O

Temperatures are given on the IPTS-68 scale.

References

1. Haar, L., Gallagher, J. S., and Kell, G. S., *NBS/NRC Steam Tables*, Hemisphere Publishing Corp., New York, 1984.
2. Levelt Sengers, J. M. H., Straub, J., Watanabe, K., and Hill, P. G., Assessment of critical parameter values for H_2O and D_2O, *J. Phys. Chem. Ref. Data,* 14, 193, 1985.
3. Kestin, J. et. al., Thermophysical properties of fluid D_2O, *J. Phys. Chem. Ref. Data,* 13, 601, 1984.
4. Kestin, J. et. al., Thermophysical properties of fluid H_2O, *J. Phys. Chem. Ref. Data*, 13, 175, 1984.
5. Hill, P. G., MacMillan, R. D. C., and Lee, V., A fundamental equation of state for heavy water, *J. Phys. Chem. Ref. Data*, 11, 1, 1982.

	Unit	H_2O	D_2O
Molar mass	g/mol	18.01528	20.02748
Melting point(101.325 kPa)	°C	0.00	3.82
Boiling point(101.325 kPa)	°C	100.00	101.42
Triple point temperature	°C	0.01	3.82
Triple point pressure	Pa	611.73	661
Triple point density(l)	g/cm³	0.99978	1.1055
Triple point density(g)	mg/L	4.885	5.75
Critical temperature	°C	373.99	370.74
Critical pressure	MPa	22.064	21.671
Critical density	g/cm³	0.322	0.356
Critical specific volume	cm³/g	3.11	2.81
Maximum density(saturated liquid)	g/cm³	0.99995	1.1053
Temperature of maximum density	°C	4.0	11.2

THERMAL CONDUCTIVITY OF SATURATED H_2O AND D_2O

This table gives the thermal conductivity λ for water (H_2O or D_2O) in equilibrium with its vapor. Values for the liquid (λ_l) and vapor (λ_v) are listed, as well as the vapor pressure.

References

1. Sengers, J.V. and Watson, J.T.R., Improved international formulations for the viscosity and thermal conductivity of water substance, *J. Phys. Chem. Ref. Data*, 15, 1291, 1986.
2. Matsunaga, N. and Nagashima, A., Transport properties of liquid and gaseous D_2O over a wide range of temperature and pressure, *J. Phys. Chem. Ref. Data*, 12, 933, 1983.

	H_2O			D_2O		
***t*/°C**	***P*/kPa**	λ_l/ (mW/K m)	λ_v/ (mW/K m)	***P*/kPa**	λ_l/ (mW/K m)	λ_v/ (mW/K m)
0	0.6	561.0	16.49			
10	1.2	580.0	17.21	1.0	575	17.0
20	2.3	598.4	17.95	2.0	589	17.8
30	4.2	615.4	18.70	3.7	600	18.5
40	7.4	630.5	19.48	6.5	610	19.3
50	12.3	643.5	20.28	11.1	618	20.2
60	19.9	654.3	21.10	18.2	625	21.0
70	31.2	663.1	21.96	28.8	629	21.9
80	47.4	670.0	22.86	44.2	633	22.8
90	70.1	675.3	23.80	66.1	635	23.8
100	101.3	679.1	24.79	96.2	636	24.8
150	476	682.1	30.77	465	625	30.8
200	1555	663.4	39.10	1546	592	39.0
250	3978	621.4	51.18	3995	541	52.0
300	8593	547.7	71.78	8688	473	75.2
350	16530	447.6	134.59	16820	391	143.0

THERMAL CONDUCTIVITY OF SATURATED H_2O AND D_2O

This table gives the thermal conductivity λ for water (H_2O or D_2O) in equilibrium with its vapor. Values for the liquid (λ_l) and vapor (λ_v) are listed, as well as the vapor pressure.

References

1. Sengers, J.V. and Watson, J.T.R., Improved international formulations for the viscosity and thermal conductivity of water substance, *J. Phys. Chem. Ref. Data*, 15, 1291, 1986.
2. Matsunaga, N. and Nagashima, A., Transport properties of liquid and gaseous D_2O over a wide range of temperature and pressure, *J. Phys. Chem. Ref. Data*, 12, 933, 1983.

	H_2O			D_2O		
***t*/°C**	***P*/kPa**	λ_l/ (mW/K m)	λ_v/ (mW/K m)	***P*/kPa**	λ_l/ (mW/K m)	λ_v/ (mW/K m)
0	0.6	561.0	16.49			
10	1.2	580.0	17.21	1.0	575	17.0
20	2.3	598.4	17.95	2.0	589	17.8
30	4.2	615.4	18.70	3.7	600	18.5
40	7.4	630.5	19.48	6.5	610	19.3
50	12.3	643.5	20.28	11.1	618	20.2
60	19.9	654.3	21.10	18.2	625	21.0
70	31.2	663.1	21.96	28.8	629	21.9
80	47.4	670.0	22.86	44.2	633	22.8
90	70.1	675.3	23.80	66.1	635	23.8
100	101.3	679.1	24.79	96.2	636	24.8
150	476	682.1	30.77	465	625	30.8
200	1555	663.4	39.10	1546	592	39.0
250	3978	621.4	51.18	3995	541	52.0
300	8593	547.7	71.78	8688	473	75.2
350	16530	447.6	134.59	16820	391	143.0

STANDARD DENSITY OF WATER

This table gives the density ρ of standard mean ocean water (SMOW), free from dissolved salts and gases, at a pressure of 101325 Pa. SMOW is a standard water sample of high purity and known isotopic composition. Methods of correcting for different isotopic compositions are discussed in the reference. The table below is reprinted with the permission of IUPAC. Note that the temperature scale is IPTS-68.

Reference

Marsh, K. N., Ed., *Recommended Reference Materials for the Realization of Physicochemical Properties,* Blackwell Scientific Publications, Oxford, 1987.

	ρ/kg m^{-3}									
t_{68}/°C	**0.0**	**0.1**	**0.2**	**0.3**	**0.4**	**0.5**	**0.6**	**0.7**	**0.8**	**0.9**
0	999.8426	8493	8558	8622	8683	8743	8801	8857	8912	8964
1	999.9015	9065	9112	9158	9202	9244	9284	9323	9360	9395
2	999.9429	9461	9491	9519	9546	9571	9595	9616	9636	9655
3	999.9672	9687	9700	9712	9722	9731	9738	9743	9747	9749
4	999.9750	9748	9746	9742	9736	9728	9719	9709	9696	9683
5	999.9668	9651	9632	9612	9591	9568	9544	9518	9490	9461
6	999.9430	9398	9365	9330	9293	9255	9216	9175	9132	9088
7	999.9043	8996	8948	8898	8847	8794	8740	8684	8627	8569
8	999.8509	8448	8385	8321	8256	8189	8121	8051	7980	7908
9	999.7834	7759	7682	7604	7525	7444	7362	7279	7194	7108
10	999.7021	6932	6842	6751	6658	6564	6468	6372	6274	6174
11	999.6074	5972	5869	5764	5658	5551	5443	5333	5222	5110
12	999.4996	4882	4766	4648	4530	4410	4289	4167	4043	3918
13	999.3792	3665	3536	3407	3276	3143	3010	2875	2740	2602
14	999.2464	2325	2184	2042	1899	1755	1609	1463	1315	1166
15	999.1016	0864	0712	0558	0403	0247	0090	9932*	9772*	9612*
16	998.9450	9287	9123	8957	8791	8623	8455	8285	8114	7942
17	998.7769	7595	7419	7243	7065	6886	6706	6525	6343	6160
18	998.5976	5790	5604	5416	5228	5038	4847	4655	4462	4268
19	998.4073	3877	3680	3481	3282	3081	2880	2677	2474	2269
20	998.2063	1856	1649	1440	1230	1019	0807	0594	0380	0164
21	997.9948	9731	9513	9294	9073	8852	8630	8406	8182	7957
22	997.7730	7503	7275	7045	6815	6584	6351	6118	5883	5648
23	997.5412	5174	4936	4697	4456	4215	3973	3730	3485	3240
24	997.2994	2747	2499	2250	2000	1749	1497	1244	0990	0735
25	997.0480	0223	9965*	9707*	9447*	9186*	8925*	8663*	8399*	8135*
26	996.7870	7604	7337	7069	6800	6530	6259	5987	5714	5441
27	996.5166	4891	4615	4337	4059	3780	3500	3219	2938	2655
28	996.2371	2087	1801	1515	1228	0940	0651	0361	0070	9778*
29	995.9486	9192	8898	8603	8306	8009	7712	7413	7113	6813
30	995.6511	6209	5906	5602	5297	4991	4685	4377	4069	3760
31	995.3450	3139	2827	2514	2201	1887	1572	1255	0939	0621
32	995.0302	9983*	9663*	9342*	9020*	8697*	8373*	8049*	7724*	7397*
33	994.7071	6743	6414	6085	5755	5423	5092	4759	4425	4091
34	994.3756	3420	3083	2745	2407	2068	1728	1387	1045	0703
35	994.0359	0015	9671*	9325*	8978*	8631*	8283*	7934*	7585*	7234*
36	993.6883	6531	6178	5825	5470	5115	4759	4403	4045	3687
37	993.3328	2968	2607	2246	1884	1521	1157	0793	0428	0062
38	992.9695	9328	8960	8591	8221	7850	7479	7107	6735	6361
39	992.5987	5612	5236	4860	4483	4105	3726	3347	2966	2586
40	992.2204									

* The leading figure decreases by 1.

VOLUMETRIC PROPERTIES OF AQUEOUS SODIUM CHLORIDE SOLUTIONS

This table gives the following properties of aqueous solutions of NaCl as a function of temperature and concentration:

Specific volume v (reciprocal of density) in cm^3/g
Isothermal compressibility $\kappa_T = -(1/v)(\partial v/\partial P)_T$ in GPa^{-1}
Cubic expansion coefficient $\alpha_v = (1/v)(\partial v/\partial T)_p$ in kK^{-1}

All data refer to a pressure of 100 kPa (1 bar). The reference gives properties over a wider range of temperature and pressure.

Reference

Rogers, P. S. Z., and Pitzer, K. S., *J. Phys. Chem. Ref. Data,* 11, 15, 1982.

	Molality in mol/kg								
***t*/°C**	**0.100**	**0.250**	**0.500**	**0.750**	**1.000**	**2.000**	**3.000**	**4.000**	**5.000**
Specific volume v in cm³/g									
0	0.995732	0.989259	0.978889	0.968991	0.959525	0.925426	0.896292	0.870996	0.848646
10	0.995998	0.989781	0.979804	0.970256	0.961101	0.927905	0.899262	0.874201	0.851958
20	0.997620	0.991564	0.981833	0.972505	0.963544	0.930909	0.902565	0.877643	0.855469
25	0.998834	0.992832	0.983185	0.973932	0.965038	0.932590	0.904339	0.879457	0.857301
30	1.000279	0.994319	0.984735	0.975539	0.966694	0.934382	0.906194	0.881334	0.859185
40	1.003796	0.997883	0.988374	0.979243	0.970455	0.938287	0.910145	0.885276	0.863108
50	1.008064	1.002161	0.992668	0.983551	0.974772	0.942603	0.914411	0.889473	0.867241
60	1.0130	1.0071	0.9976	0.9885	0.9797	0.9474	0.9191	0.8940	0.8716
70	1.0186	1.0127	1.0031	0.9939	0.9851	0.9526	0.9240	0.8987	0.8762
80	1.0249	1.0188	1.0092	0.9999	0.9909	0.9581	0.9293	0.9037	0.8809
90	1.0317	1.0256	1.0157	1.0063	0.9972	0.9640	0.9348	0.9089	0.8858
100	1.0391	1.0329	1.0228	1.0133	1.0040	0.9703	0.9406	0.9144	0.8910
Compressibility κ_T in GPa⁻¹									
0	0.503	0.492	0.475	0.459	0.443	0.389	0.346	0.315	0.294
10	0.472	0.463	0.449	0.436	0.423	0.377	0.341	0.313	0.294
20	0.453	0.446	0.433	0.422	0.411	0.371	0.338	0.313	0.294
25	0.447	0.440	0.428	0.417	0.407	0.369	0.337	0.313	0.294
30	0.443	0.436	0.425	0.414	0.404	0.367	0.337	0.313	0.294
40	0.438	0.432	0.421	0.411	0.401	0.367	0.338	0.315	0.296
50	0.438	0.431	0.421	0.411	0.402	0.369	0.340	0.317	0.299
60	0.44	0.44	0.43	0.42	0.41	0.38	0.35	0.32	0.30
70	0.45	0.44	0.43	0.42	0.42	0.38	0.36	0.33	0.31
80	0.46	0.45	0.44	0.43	0.43	0.39	0.37	0.34	0.32
90	0.47	0.47	0.46	0.45	0.44	0.41	0.38	0.35	0.33
100	0.49	0.48	0.47	0.46	0.45	0.42	0.39	0.37	0.34
Cubic expansion coefficient α_V in kK⁻¹									
0	–0.058	–0.026	0.024	0.069	0.110	0.237	0.313	0.355	
10	0.102	0.123	0.156	0.186	0.213	0.297	0.349	0.380	
20	0.218	0.232	0.254	0.274	0.292	0.349	0.384	0.406	
25	0.267	0.278	0.296	0.312	0.327	0.373	0.401	0.420	
30	0.311	0.320	0.334	0.347	0.359	0.395	0.418	0.433	
40	0.389	0.394	0.402	0.410	0.417	0.438	0.451	0.460	
50	0.458	0.460	0.464	0.467	0.470	0.479	0.484	0.486	
60	0.52	0.52	0.52	0.52	0.52	0.52	0.52	0.52	
70	0.58	0.58	0.58	0.57	0.57	0.56	0.55	0.54	
80	0.64	0.63	0.63	0.62	0.61	0.60	0.58	0.56	
90	0.69	0.68	0.67	0.67	0.66	0.63	0.61	0.59	
100	0.74	0.73	0.72	0.71	0.70	0.66	0.64	0.61	

DENSITY OF D_2O

Density of liquid D_2O in g/cm^3 at a pressure of 100 kPa (1 bar).

Reference

Kirillin, V.A., Ed., *Heavy Water: Thermophysical Properties*, Gosudarstvennoe Energeticheskoe Izdatel'stvo, Moscow, 1963.

t/°C	3.8	5	10	15	20	25	30
Density	1.1053	1.1055	1.1057	1.1056	1.105	1.1044	1.1034

t/°C	35	40	45	50	55	60	65
Density	1.1019	1.1001	1.0979	1.0957	1.0931	1.0905	1.0875

t/°C	70	75	80	85	90	95	100
Density	1.0847	1.0815	1.0783	1.0748	1.0712	1.0673	1.0635

VAPOR PRESSURE OF ICE

The values of the vapor (sublimation) pressure of ice in this table were calculated from the equation recommended by the International Association for the Properties of Steam (IAPS) in 1993. Temperature values correspond to the ITS-90 temperature scale. The uncertainty in the pressure is estimated to be 0.1% for $t > -25$°C and 0.5% for $t < -25$°C. The first entry in the table is the triple point of water.

Reference

Wagner, W., Saul, A., and Pruss, A., *J. Phys. Chem. Ref. Data*, 23, 515, 1994.

t/°C	***p***/Pa	***t***/°C	***p***/Pa	***t***/°C	***p***/Pa
0.01	611.657	−16	150.68	−33	27.71
0	611.15	−17	137.25	−34	24.90
−1	562.67	−18	124.92	−35	22.35
−2	517.72	−19	113.62	−36	20.04
−3	476.06	−20	103.26	−37	17.96
−4	437.47	−21	93.77	−38	16.07
−5	401.76	−22	85.10	−39	14.37
−6	368.73	−23	77.16	−40	12.84
−7	338.19	−24	69.91	−45	7.202
−8	309.98	−25	63.29	−50	3.936
−9	283.94	−26	57.25	−55	2.093
−10	259.90	−27	51.74	−60	1.080
−11	237.74	−28	46.73	−65	0.540
−12	217.32	−29	42.16	−70	0.261
−13	198.52	−30	38.01	−75	0.122
−14	181.22	−31	34.24	−80	0.055
−15	165.30	−32	30.82		

VAPOR PRESSURE OF WATER FROM 0 TO 370°C

This table gives the vapor pressure of water at intervals of 1° C from the melting point to the critical point.

Reference

Haar, L., Gallagher, J. S., and Kell, G. S., *NBS/NRC Steam Tables*, Hemisphere Publishing Corp., New York, 1984.

t/°C	*P*/kPa	*t*/°C	*P*/kPa	*t*/°C	*P*/kPa	*t*/°C	*P*/kPa
0	0.61129	52	13.623	104	116.67	156	557.32
1	0.65716	53	14.303	105	120.79	157	571.94
2	0.70605	54	15.012	106	125.03	158	586.87
3	0.75813	55	15.752	107	129.39	159	602.11
4	0.81359	56	16.522	108	133.88	160	617.66
5	0.87260	57	17.324	109	138.50	161	633.53
6	0.93537	58	18.159	110	143.24	162	649.73
7	1.0021	59	19.028	111	148.12	163	666.25
8	1.0730	60	19.932	112	153.13	164	683.10
9	1.1482	61	20.873	113	158.29	165	700.29
10	1.2281	62	21.851	114	163.58	166	717.83
11	1.3129	63	22.868	115	169.02	167	735.70
12	1.4027	64	23.925	116	174.61	168	753.94
13	1.4979	65	25.022	117	180.34	169	772.52
14	1.5988	66	26.163	118	186.23	170	791.47
15	1.7056	67	27.347	119	192.28	171	810.78
16	1.8185	68	28.576	120	198.48	172	830.47
17	1.9380	69	29.852	121	204.85	173	850.53
18	2.0644	70	31.176	122	211.38	174	870.98
19	2.1978	71	32.549	123	218.09	175	891.80
20	2.3388	72	33.972	124	224.96	176	913.03
21	2.4877	73	35.448	125	232.01	177	934.64
22	2.6447	74	36.978	126	239.24	178	956.66
23	2.8104	75	38.563	127	246.66	179	979.09
24	2.9850	76	40.205	128	254.25	180	1001.9
25	3.1690	77	41.905	129	262.04	181	1025.2
26	3.3629	78	43.665	130	270.02	182	1048.9
27	3.5670	79	45.487	131	278.20	183	1073.0
28	3.7818	80	47.373	132	286.57	184	1097.5
29	4.0078	81	49.324	133	295.15	185	1122.5
30	4.2455	82	51.342	134	303.93	186	1147.9
31	4.4953	83	53.428	135	312.93	187	1173.8
32	4.7578	84	55.585	136	322.14	188	1200.1
33	5.0335	85	57.815	137	331.57	189	1226.9
34	5.3229	86	60.119	138	341.22	190	1254.2
35	5.6267	87	62.499	139	351.09	191	1281.9
36	5.9453	88	64.958	140	361.19	192	1310.1
37	6.2795	89	67.496	141	371.53	193	1338.8
38	6.6298	90	70.117	142	382.11	194	1368.0
39	6.9969	91	72.823	143	392.92	195	1397.6
40	7.3814	92	75.614	144	403.98	196	1427.8
41	7.7840	93	78.494	145	415.29	197	1458.5
42	8.2054	94	81.465	146	426.85	198	1489.7
43	8.6463	95	84.529	147	438.67	199	1521.4
44	9.1075	96	87.688	148	450.75	200	1553.6
45	9.5898	97	90.945	149	463.10	201	1586.4
46	10.094	98	94.301	150	475.72	202	1619.7
47	10.620	99	97.759	151	488.61	203	1653.6
48	11.171	100	101.32	152	501.78	204	1688.0
49	11.745	101	104.99	153	515.23	205	1722.9
50	12.344	102	108.77	154	528.96	206	1758.4
51	12.970	103	112.66	155	542.99	207	1794.5

t/°C	*P*/kPa	*t*/°C	*P*/kPa	*t*/°C	*P*/kPa	*t*/°C	*P*/kPa
208	1831.1	250	3973.6	292	7657.2	334	13528
209	1868.4	251	4041.2	293	7768.6	335	13701
210	1906.2	252	4109.6	294	7881.3	336	13876
211	1944.6	253	4178.9	295	7995.2	337	14053
212	1983.6	254	4249.1	296	8110.3	338	14232
213	2023.2	255	4320.2	297	8226.8	339	14412
214	2063.4	256	4392.2	298	8344.5	340	14594
215	2104.2	257	4465.1	299	8463.5	341	14778
216	2145.7	258	4539.0	300	8583.8	342	14964
217	2187.8	259	4613.7	301	8705.4	343	15152
218	2230.5	260	4689.4	302	8828.3	344	15342
219	2273.8	261	4766.1	303	8952.6	345	15533
220	2317.8	262	4843.7	304	9078.2	346	15727
221	2362.5	263	4922.3	305	9205.1	347	15922
222	2407.8	264	5001.8	306	9333.4	348	16120
223	2453.8	265	5082.3	307	9463.1	349	16320
224	2500.5	266	5163.8	308	9594.2	350	16521
225	2547.9	267	5246.3	309	9726.7	351	16725
226	2595.9	268	5329.8	310	9860.5	352	16931
227	2644.6	269	5414.3	311	9995.8	353	17138
228	2694.1	270	5499.9	312	10133	354	17348
229	2744.2	271	5586.4	313	10271	355	17561
230	2795.1	272	5674.0	314	10410	356	17775
231	2846.7	273	5762.7	315	10551	357	17992
232	2899.0	274	5852.4	316	10694	358	18211
233	2952.1	275	5943.1	317	10838	359	18432
234	3005.9	276	6035.0	318	10984	360	18655
235	3060.4	277	6127.9	319	11131	361	18881
236	3115.7	278	6221.9	320	11279	362	19110
237	3171.8	279	6317.0	321	11429	363	19340
238	3228.6	280	6413.2	322	11581	364	19574
239	3286.3	281	6510.5	323	11734	365	19809
240	3344.7	282	6608.9	324	11889	366	20048
241	3403.9	283	6708.5	325	12046	367	20289
242	3463.9	284	6809.2	326	12204	368	20533
243	3524.7	285	6911.1	327	12364	369	20780
244	3586.3	286	7014.1	328	12525	370	21030
245	3648.8	287	7118.3	329	12688	371	21283
246	3712.1	288	7223.7	330	12852	372	21539
247	3776.2	289	7330.2	331	13019	373	21799
248	3841.2	290	7438.0	332	13187	373.98	22055
249	3907.0	291	7547.0	333	13357		

BOILING POINT OF WATER AT VARIOUS PRESSURES

Data are based on the equation of state recommended by the International Association for the Properties of Steam in 1984, as presented in Haar, Gallagher, and Kell, *NBS-NRC Steam Tables* (Hemisphere Publishing Corp., New York, 1984). The temperature scale is IPTS-68.

Note that: 1 mbar = 100 Pa = 0.000986923 atmos = 0.750062 mmHg.

***P*/mbar**	***T*/°C**	***P*/mbar**	***T*/°C**	***P*/mbar**	***T*/°C**	***P*/mbar**	***T*/°C**
50	32.88	915	97.17	1013.25	100.00	1200	104.81
100	45.82	920	97.32	1015	100.05	1250	105.99
150	53.98	925	97.47	1020	100.19	1300	107.14
200	60.07	930	97.62	1025	100.32	1350	108.25
250	64.98	935	97.76	1030	100.46	1400	109.32
300	69.11	940	97.91	1035	100.60	1450	110.36
350	72.70	945	98.06	1040	100.73	1500	111.38
400	75.88	950	98.21	1045	100.87	1550	112.37
450	78.74	955	98.35	1050	101.00	1600	113.33
500	81.34	960	98.50	1055	101.14	1650	114.26
550	83.73	965	98.64	1060	101.27	1700	115.18
600	85.95	970	98.78	1065	101.40	1750	116.07
650	88.02	975	98.93	1070	101.54	1800	116.94
700	89.96	980	99.07	1075	101.67	1850	117.79
750	91.78	985	99.21	1080	101.80	1900	118.63
800	93.51	990	99.35	1085	101.93	1950	119.44
850	95.15	995	99.49	1090	102.06	2000	120.24
900	96.71	1000	99.63	1095	102.19	2050	121.02
905	96.87	1005	99.77	1100	102.32	2100	121.79
910	97.02	1010	99.91	1150	103.59	2150	122.54

MELTING POINT OF ICE AS A FUNCTION OF PRESSURE

This table gives values of the melting temperature of ice at various pressures, as calculated from the equation for the ice I - liquid water phase boundary recommended by the International Association for the Properties of Steam (IAPS). Temperatures are on the ITS-90 scale. See the Reference for information on forms of ice that exist at higher pressures. The transition points for transformations of the various forms of ice (in each case in equilibrium with liquid water) are:

ice I - ice III	209.9 MPa	−21.985°C
ice III - ice V	350.1	−16.986
ice V - ice VI	632.4	0.16
ice VI - ice VII	2216	82

Reference

Wagner, W., Saul, A., and Pruss, A., *J. Phys. Chem. Ref. Data,* 23, 515, 1994.

***p*/MPa**	***t*/°C**	***p*/MPa**	***t*/°C**	***p*/MPa**	***t*/°C**
0.1	0.00	40	−3.15	130	−12.07
1	−0.06	50	−4.02	140	−13.22
2	−0.14	60	−4.91	150	−14.40
3	−0.21	70	−5.83	160	−15.62
4	−0.29	80	−6.79	170	−16.85
5	−0.36	90	−7.78	180	−18.11
10	−0.74	100	−8.80	190	−19.39
20	−1.52	110	−9.86	200	−20.69
30	−2.32	120	−10.95	210	−22.00

PROPERTIES OF WATER AND STEAM AS A FUNCTION OF TEMPERATURE AND PRESSURE

This table gives properties of compressed water and superheated steam at selected pressures and temperatures. The properties included are density ρ, enthalpy H, entropy S, heat capacity at constant pressure C_p, and static dielectric constant (relative permittivity). The table was generated from the formulation approved by the International Association for the Properties of Water and Steam for general and scientific use. The reference state for this table is the liquid at the triple point, at which the internal energy and entropy are taken as zero. A duplicate entry in the temperature column indicates a phase transition (liquid–vapor) at that temperature; property values are then given for both phases. In the 100 MPa section of the table, an entry is given at the critical temperature, 647.10 K. Temperatures refer to the ITS-90 scale, on which the normal boiling point of water is 373.12 K (99.97°C).

References

1. Release on the IAPWS Formulation 1995 for the Thermodynamic Properties of Ordinary Water Substance for General and Scientific Use, September 1996; available from Executive Secretary of IAPWS, Electric Power Research Institute, 3412 Hillview Ave., Palo Alto, CA 94304-1395.
2. NIST Chemistry WebBook, NIST Standard Reference Database Number 69, Mallard, W. G., and Linstrom, P. J., Eds., March 1998, National Institute of Standards and Technology, Gaithersburg, MD, 20899 (http://webbook.nist.gov).
3. Pruss, A. and Wagner, W., to be published.
4. Fernandez, D. P., Goodwin, A. R. H., Lemmon, E. W., Levelt Sengers, J. M. H., and Williams, R. C., *J. Phys. Chem. Ref. Data*, 26, 1125, 1997. [Dielectric constant]

p/MPa	T/K	ρ/kg m^{-3}	H/J g^{-1}	S/J g^{-1}K^{-1}	C_p/J g^{-1}K^{-1}	Diel. const.
0.1	273.16	999.84	0.10	0.0000	4.2194	87.90
0.1	300	996.56	112.65	0.3931	4.1806	77.75
0.1	325	987.19	217.15	0.7276	4.1819	69.32
0.1	350	973.73	321.84	1.0380	4.1945	61.79
0.1	372.76	958.63	417.50	1.3028	4.2152	55.61
0.1	372.76	0.59034	2674.9	7.3588	2.0784	1.006
0.1	375	0.58653	2679.6	7.3713	2.0686	1.006
0.1	400	0.54761	2730.4	7.5025	2.0078	1.005
0.1	450	0.48458	2829.7	7.7365	1.9752	1.004
0.1	500	0.43514	2928.6	7.9447	1.9813	1.003
0.1	550	0.39507	3028.1	8.1344	2.0010	1.003
0.1	600	0.36185	3128.8	8.3096	2.0268	1.002
0.1	650	0.33384	3230.8	8.4730	2.0557	1.002
0.1	700	0.30988	3334.4	8.6264	2.0867	1.002
0.1	750	0.28915	3439.5	8.7715	2.1191	1.002
0.1	800	0.27102	3546.3	8.9093	2.1525	1.001
0.1	850	0.25504	3654.8	9.0408	2.1868	1.001
0.1	900	0.24085	3765.0	9.1668	2.2216	1.001
0.1	950	0.22815	3876.9	9.2879	2.2568	1.001
0.1	1000	0.21673	3990.7	9.4045	2.2921	1.001
0.1	1050	0.20640	4106.1	9.5172	2.3273	1.001
0.1	1100	0.19701	4223.4	9.6263	2.3621	1.001
0.1	1150	0.18844	4342.3	9.7321	2.3965	1.001
0.1	1200	0.18058	4463.0	9.8348	2.4302	1.001
1	273.16	1000.3	1.02	0.0000	4.2150	87.93
1	300	996.96	113.48	0.3928	4.1781	77.78
1	325	987.58	217.93	0.7272	4.1798	69.36
1	350	974.13	322.56	1.0374	4.1925	61.82
1	375	957.43	427.64	1.3274	4.2158	55.09
1	400	937.87	533.47	1.6005	4.2535	49.06
1	450	890.39	749.20	2.1086	4.3924	38.81
1	453.03	887.13	762.51	2.1381	4.4045	38.23
1	453.03	5.1450	2777.1	6.5850	2.7114	1.042
1	500	4.5323	2891.2	6.8250	2.2795	1.034
1	550	4.0581	3001.8	7.0359	2.1647	1.028
1	600	3.6871	3109.0	7.2224	2.1292	1.024
1	650	3.3843	3215.2	7.3925	2.1254	1.020
1	700	3.1305	3321.7	7.5504	2.1368	1.017
1	750	2.9140	3429.0	7.6984	2.1566	1.015
1	800	2.7265	3537.5	7.8384	2.1816	1.013
1	850	2.5624	3647.3	7.9715	2.2098	1.012
1	900	2.4174	3758.5	8.0986	2.2402	1.011

p/MPa	T/K	ρ/kg m^{-3}	H/J g^{-1}	S/J g^{-1}K^{-1}	C_p/J g^{-1}K^{-1}	Diel. const.
1	950	2.2882	3871.3	8.2206	2.2721	1.010
1	1000	2.1723	3985.7	8.3380	2.3048	1.009
1	1050	2.0678	4101.8	8.4512	2.3380	1.008
1	1100	1.9729	4219.5	8.5608	2.3713	1.007
1	1150	1.8865	4338.9	8.6669	2.4044	1.007
1	1200	1.8074	4460.0	8.7699	2.4371	1.006
10	273.16	1004.8	10.1	0.000	4.173	88.30
10	300	1001.0	121.7	0.390	4.153	78.11
10	325	991.46	225.6	0.723	4.160	69.67
10	350	978.09	329.7	1.031	4.173	62.13
10	375	961.62	434.4	1.320	4.195	55.40
10	400	942.42	539.6	1.592	4.230	49.39
10	450	896.16	753.9	2.096	4.355	39.17
10	500	838.02	977.1	2.566	4.602	30.79
10	550	761.82	1218	3.027	5.140	23.53
10	584.15	688.42	1408	3.360	6.123	18.70
10	584.15	55.463	2725	5.616	7.140	1.404
10	600	49.773	2820	5.775	5.136	1.365
10	650	40.479	3022	6.100	3.396	1.267
10	700	35.355	3177	6.330	2.874	1.214
10	750	31.810	3314	6.520	2.645	1.179
10	800	29.107	3443	6.686	2.531	1.154
10	850	26.933	3568	6.838	2.473	1.134
10	900	25.123	3691	6.978	2.445	1.118
10	950	23.580	3813	7.110	2.436	1.105
10	1000	22.241	3935	7.235	2.439	1.095
10	1050	21.063	4057	7.354	2.450	1.086
10	1100	20.017	4180	7.469	2.466	1.078
10	1150	19.078	4304	7.579	2.485	1.072
10	1200	18.230	4429	7.685	2.507	1.066
100	273.16	1045.3	95.4	–0.008	3.905	91.83
100	300	1037.2	201.4	0.362	3.979	81.22
100	325	1026.6	301.3	0.682	4.008	72.58
100	350	1013.6	401.7	0.979	4.025	64.95
100	375	998.59	502.6	1.258	4.040	58.19
100	400	981.82	603.7	1.518	4.056	52.20
100	450	943.51	807.8	1.999	4.110	42.15
100	500	899.21	1015	2.436	4.196	34.15
100	550	848.78	1228	2.842	4.323	27.67
100	600	791.49	1448	3.225	4.501	22.29
100	647.10	730.24	1665	3.573	4.733	17.97
100	650	726.21	1679	3.595	4.750	17.72
100	700	651.77	1925	3.958	5.083	13.75
100	750	568.52	2188	4.322	5.449	10.34
100	800	482.23	2466	4.681	5.610	7.562
100	850	404.66	2742	5.016	5.380	5.571
100	900	343.61	3000	5.310	4.887	4.284
100	950	298.61	3231	5.560	4.382	3.477
100	1000	265.45	3440	5.774	3.978	2.956
100	1050	240.32	3631	5.961	3.683	2.601
100	1100	220.62	3809	6.127	3.471	2.347
100	1150	204.71	3979	6.278	3.319	2.158
100	1200	191.53	4142	6.417	3.209	2.011

PERMITTIVITY (DIELECTRIC CONSTANT) OF WATER AT VARIOUS FREQUENCIES

The permittivity of liquid water in the radiofrequency and microwave regions can be represented by the Debye equation (References 1 and 2):

$$\varepsilon' = \varepsilon_\infty + \frac{\varepsilon_s - \varepsilon_\infty}{1 + \omega^2\tau^2}$$

$$\varepsilon'' = \frac{(\varepsilon_s - \varepsilon_\infty)\omega\tau}{1 + \omega^2\tau^2}$$

where $\varepsilon = \varepsilon' + i\,\varepsilon''$ is the (complex) relative permittivity (i.e., the absolute permittivity divided by the permittivity of free space $\varepsilon_0 = 8.854 \cdot 10^{-12}$ F m^{-1}). Here ε_s is the static permittivity (see Reference 3 and the table "Properties of Water in the Range 0–100°C" in this Section); ε_∞ is a parameter describing the permittivity in the high frequency limit; τ is the relaxation time for molecular orientation; and $\omega = 2\pi f$ is the angular frequency. The values in this table have been calculated from parameters given in Reference 2:

	0°C	25°C	50°C
ε_∞	5.7	5.2	4.0
τ/ps	17.67	8.27	4.75

Other useful quantities that can be calculated from the values in the table are the loss tangent:

$$\tan\delta = \varepsilon''/\varepsilon'$$

and the absorption coefficient α which describes the power attenuation per unit length ($P = P_0\, e^{-\alpha l}$):

$$\alpha = \frac{\pi f \varepsilon''}{c\sqrt{\varepsilon'}}$$

and c is the speed of light. The last equation is valid when $\varepsilon''/\varepsilon' << 1$.

References

1. Fernendez, D. P., Mulev, Y., Goodwin, A. R. H., and Levelt Sengers, J. M. H., *J. Phys. Chem. Ref. Data*, 24, 33, 1995.
2. Kaatze, U., *J. Chem. Eng. Data,* 34, 371, 1989.
3. Archer, D. G., and Wang, P., *J. Phys. Chem. Ref. Data*, 12, 817, 1983.

	0°C		25°C		50°C	
Frequency	ε'	ε''	ε'	ε''	ε'	ε''
0	87.90	0.00	78.36	0.00	69.88	0.00
1 kHz	87.90	0.00	78.36	0.00	69.88	0.00
1 MHz	87.90	0.01	78.36	0.00	69.88	0.00
10 MHz	87.90	0.09	78.36	0.04	69.88	0.02
100 MHz	87.89	0.91	78.36	0.38	69.88	0.20
200 MHz	87.86	1.82	78.35	0.76	69.88	0.39
500 MHz	87.65	4.55	78.31	1.90	69.87	0.98
1 GHz	86.90	9.01	78.16	3.79	69.82	1.96
2 GHz	84.04	17.39	77.58	7.52	69.65	3.92
3 GHz	79.69	24.64	76.62	11.13	69.36	5.85
4 GHz	74.36	30.49	75.33	14.58	68.95	7.75
5 GHz	68.54	34.88	73.73	17.81	68.45	9.62
10 GHz	42.52	40.88	62.81	29.93	64.49	18.05
20 GHz	19.56	30.78	40.37	36.55	52.57	28.99
30 GHz	12.50	22.64	26.53	33.25	40.57	32.74
40 GHz	9.67	17.62	18.95	28.58	31.17	32.43
50 GHz	8.28	14.34	14.64	24.53	24.42	30.47

THERMOPHYSICAL PROPERTIES OF FLUIDS

These tables give thermodynamic and transport properties of some important fluids, as generated from the equations of state presented in the references below. The properties tabulated are density (ρ), energy (*E*), enthalpy (*H*), entropy (*S*), isochoric heat capacity (C_v), isobaric heat capacity (C_p), speed of sound (v_s), viscosity (η), thermal conductivity (λ), and dielectric constant (*D*). All extensive properties are given on a molar basis. Not all properties are included for every substance. The references should be consulted for information on the uncertainties and the reference states for *E*, *H*, and *S*.

Values are given as a function of temperature for several isobars. The phase can be determined by noting the sharp decrease in density between two successive temperature entries; all lines above this point refer to the liquid phase, and all lines below refer to the gas phase. If there is no sharp discontinuity in density, all data in the table refer to the supercritical region (i.e., the isobar is above the critical pressure).

References

1. Younglove, B. A., Thermophysical Properties of Fluids. Part I, *J. Phys. Chem. Ref. Data*, 11, Suppl. 1, 1982.
2. Younglove, B. A., and Ely, J. F., Thermophysical Properties of Fluids. Part II, *J. Phys. Chem. Ref. Data*, 16, 577, 1987.
3. McCarty, R. D., Thermodynamic Properties of Helium, *J. Phys. Chem. Ref. Data*, 2, 923, 1973.

NITROGEN (N_2)

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	η μPa s	λ mW/m K	*D*
***P* = 0.1 MPa (1 bar)**									
70	30.017	−3828	−3824	73.8	28.5	57.2	203.9	143.5	1.45269
77.25	28.881	−3411	−3407	79.5	27.8	57.8	152.2	133.8	1.43386
77.25	0.163	1546	2161	151.6	21.6	31.4	5.3	7.6	1.00215
100	0.123	2041	2856	159.5	21.1	30.0	6.8	9.6	1.00162
200	0.060	4140	5800	179.9	20.8	29.2	12.9	18.4	1.00079
300	0.040	6223	8717	191.8	20.8	29.2	18.0	25.8	1.00053
400	0.030	8308	11635	200.2	20.9	29.2	22.2	32.3	1.00040
500	0.024	10414	14573	206.7	21.2	29.6	26.1	38.5	1.00032
600	0.020	12563	17554	212.2	21.8	30.1	29.5	44.5	1.00026
700	0.017	14770	20593	216.8	22.4	30.7	32.8	50.5	1.00023
800	0.015	17044	23698	221.0	23.1	31.4	35.8	56.3	1.00020
900	0.013	19383	26869	224.7	23.7	32.0	38.7	62.0	1.00017
1000	0.012	21786	30103	228.1	24.3	32.6	41.5	67.7	1.00016
1500	0.008	34530	47004	241.8	26.4	34.7	54.0	93.3	1.00010
***P* = 1 MPa**									
70	30.070	−3838	−3805	73.6	28.9	56.9	205.9	144.1	1.45355
80	28.504	−3267	−3232	81.3	27.8	57.7	139.5	130.7	1.42760
90	26.721	−2685	−2648	88.2	26.7	59.4	100.1	115.3	1.39824
100	24.634	−2073	−2032	94.6	26.2	64.4	73.1	98.5	1.36417
103.75	23.727	−1828	−1786	97.1	26.2	67.8	64.8	91.8	1.34947
103.75	1.472	1788	2467	138.1	24.1	45.0	7.6	12.5	1.01954
200	0.614	4048	5675	160.3	21.0	30.4	13.2	19.3	1.00812
300	0.402	6171	8661	172.5	20.9	29.6	18.1	26.3	1.00529
400	0.300	8273	11609	180.9	20.9	29.5	22.4	32.7	1.00395
500	0.240	10389	14563	187.5	21.3	29.7	26.1	38.8	1.00315
600	0.200	12544	17554	193.0	21.8	30.2	29.6	44.8	1.00262
700	0.171	14756	20600	197.7	22.4	30.8	32.8	50.7	1.00224
800	0.150	17032	23709	201.8	23.1	31.4	35.9	56.5	1.00196
900	0.133	19374	26884	205.6	23.7	32.1	38.8	62.2	1.00174
1000	0.120	21778	30121	209.0	24.3	32.7	41.5	67.8	1.00157
1500	0.080	34527	47029	222.7	26.4	34.8	54.0	93.4	1.00104
***P* = 10 MPa**									
65.32	31.120	−4176	−3855	68.6	31.8	53.8	275.7	153.8	1.47067
100	26.201	−2328	−1946	92.0	27.4	56.3	90.2	112.3	1.38942
200	7.117	3037	4442	136.4	22.7	45.5	17.6	30.4	1.09698
300	3.989	5667	8174	151.7	21.4	33.4	20.1	31.9	1.05347
400	2.898	7941	11392	161.0	21.3	31.3	23.7	36.7	1.03860

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	η μPa s	λ mW/m K	*D*
500	2.302	10148	14492	167.9	21.5	30.8	27.1	42.0	1.03055
600	1.918	12361	17575	173.5	21.9	30.9	30.4	47.4	1.02538
700	1.647	14613	20683	178.3	22.5	31.3	33.5	53.0	1.02175
800	1.445	16919	23837	182.5	23.2	31.8	36.4	58.6	1.01904
900	1.288	19283	27046	186.3	23.8	32.4	39.3	64.1	1.01694
1000	1.162	21705	30308	189.8	24.4	32.9	42.0	69.6	1.01526
1500	0.783	34504	47283	203.5	26.5	34.8	54.3	94.7	1.01020

OXYGEN (O_2)

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	η μPa s	λ mW/m K	*D*
***P* = 0.1 MPa (1 bar)**									
60	40.049	–5883	–5880	72.4	34.9	53.4	425.2	188.2	1.55619
80	37.204	–4814	–4812	87.7	31.0	53.6	251.7	166.1	1.51114
100	0.123	2029	2840	172.9	21.4	30.5	7.5	9.3	1.00146
120	0.102	2458	3442	178.4	21.0	29.8	9.0	11.2	1.00121
140	0.087	2881	4035	182.9	20.9	29.5	10.5	13.1	1.00103
160	0.076	3301	4624	186.9	20.9	29.4	11.9	15.0	1.00090
180	0.067	3720	5210	190.3	20.8	29.3	13.3	16.7	1.00080
200	0.060	4138	5796	193.4	20.8	29.3	14.6	18.4	1.00072
220	0.055	4556	6381	196.2	20.8	29.3	15.9	20.1	1.00065
240	0.050	4974	6966	198.8	20.9	29.3	17.2	21.7	1.00060
260	0.046	5393	7552	201.1	20.9	29.3	18.4	23.2	1.00055
280	0.043	5812	8138	203.3	21.0	29.4	19.5	24.8	1.00051
300	0.040	6234	8726	205.3	21.1	29.4	20.6	26.3	1.00048
320	0.038	6657	9316	207.2	21.2	29.5	21.7	27.8	1.00045
340	0.035	7082	9908	209.0	21.3	29.7	22.8	29.3	1.00042
360	0.033	7510	10503	210.7	21.5	29.8	23.8	30.8	1.00040
380	0.032	7941	11100	212.3	21.6	30.0	24.8	32.2	1.00038
***P* = 1 MPa**									
60	40.084	–5887	–5863	72.3	34.9	53.3	428.5	188.4	1.55674
80	37.254	–4822	–4795	87.6	31.0	53.5	253.8	166.4	1.51192
100	34.153	–3741	–3712	99.7	28.5	55.2	155.6	137.9	1.46381
120	1.198	2163	2997	156.7	24.0	40.6	9.4	13.9	1.01429
140	0.950	2683	3735	162.4	22.2	34.4	10.8	14.9	1.01133
160	0.802	3151	4398	166.8	21.5	32.2	12.2	16.3	1.00955
180	0.698	3598	5030	170.5	21.2	31.2	13.5	17.7	1.00831
200	0.620	4035	5647	173.8	21.1	30.6	14.8	19.3	1.00738
220	0.559	4466	6255	176.7	21.0	30.3	16.1	20.8	1.00665
240	0.509	4894	6858	179.3	21.0	30.1	17.3	22.3	1.00606
260	0.468	5321	7458	181.7	21.0	29.9	18.5	23.8	1.00556
280	0.433	5748	8056	183.9	21.1	29.9	19.6	25.2	1.00515
300	0.403	6174	8654	186.0	21.1	29.9	20.7	26.7	1.00479
320	0.377	6602	9252	187.9	21.2	29.9	21.8	28.2	1.00448
340	0.355	7032	9851	189.7	21.4	30.0	22.8	29.6	1.00421
360	0.335	7463	10452	191.4	21.5	30.1	23.9	31.1	1.00397
380	0.317	7898	11056	193.1	21.7	30.2	24.9	32.6	1.00376
***P* = 10 MPa**									
60	40.419	–5931	–5684	71.5	35.1	53.0	461.8	189.9	1.56210
80	37.727	–4893	–4628	86.7	31.6	52.7	274.4	168.6	1.51936
100	34.881	–3856	–3570	98.5	29.1	53.4	171.0	141.2	1.47500
120	31.721	–2796	–2481	108.4	27.3	55.9	113.0	115.1	1.42677
140	27.890	–1662	–1304	117.5	26.2	62.9	76.3	91.8	1.36972
160	22.379	–322	125	127.0	26.1	84.8	48.6	71.2	1.29037
180	13.232	1489	2245	139.5	26.6	105.9	26.2	46.8	1.16560
200	8.666	2681	3835	147.9	24.0	60.6	21.2	34.0	1.10650

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	η μPa s	λ mW/m K	*D*
220	6.868	3424	4880	152.9	22.6	46.4	20.5	30.8	1.08380
240	5.836	4029	5742	156.6	22.0	40.6	20.8	30.1	1.07090
260	5.134	4573	6521	159.7	21.8	37.6	21.4	30.2	1.06219
280	4.613	5086	7254	162.5	21.6	35.8	22.1	30.8	1.05575
300	4.205	5581	7959	164.9	21.6	34.7	22.9	31.6	1.05073
320	3.874	6063	8645	167.1	21.7	33.9	23.7	32.6	1.04667
340	3.598	6538	9318	169.1	21.8	33.4	24.6	33.7	1.04329
360	3.363	7009	9982	171.0	21.9	33.0	25.4	34.9	1.04043
380	3.161	7477	10641	172.8	22.0	32.8	26.3	36.1	1.03796

HYDROGEN (H_2)

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	v_s m/s	*D*
***P* = 0.1 MPa (1 bar)**								
15	37.738	−605	−603	11.2	9.7	14.4	1319	1.24827
20	35.278	−524	−521	15.8	11.3	19.1	1111	1.23093
40	0.305	491	818	75.6	12.5	21.3	521	1.00186
60	0.201	748	1244	84.3	13.1	21.6	636	1.00122
80	0.151	1030	1694	90.7	15.3	23.7	714	1.00091
100	0.120	1370	2202	96.4	18.7	27.1	773	1.00073
120	0.100	1777	2776	101.6	21.8	30.2	827	1.00061
140	0.086	2237	3401	106.4	23.8	32.2	883	1.00052
160	0.075	2723	4054	110.8	24.6	33.0	940	1.00046
180	0.067	3216	4714	114.7	24.6	32.9	998	1.00041
200	0.060	3703	5367	118.1	24.1	32.4	1054	1.00037
220	0.055	4179	6009	121.2	23.4	31.8	1110	1.00033
240	0.050	4641	6638	123.9	22.8	31.2	1163	1.00030
260	0.046	5093	7256	126.4	22.3	30.6	1214	1.00028
280	0.043	5535	7865	128.6	21.9	30.2	1263	1.00026
300	0.040	5970	8466	130.7	21.6	29.9	1310	1.00024
400	0.030	8093	11421	139.2	21.0	29.3	1518	1.00018
***P* = 1 MPa**								
15	38.109	−609	−583	10.9	10.1	14.1	1315	1.25089
20	35.852	−532	−504	15.5	11.4	18.4	1155	1.23496
40	3.608	399	676	54.1	12.9	28.4	498	1.02209
60	2.098	697	1173	64.3	13.2	23.5	635	1.01280
80	1.523	994	1651	71.1	15.4	24.7	719	1.00928
100	1.204	1343	2174	77.0	18.8	27.7	779	1.00733
120	0.999	1756	2758	82.3	21.9	30.6	835	1.00608
140	0.854	2219	3390	87.1	23.9	32.5	891	1.00520
160	0.747	2709	4048	91.5	24.7	33.2	949	1.00454
180	0.663	3204	4712	95.4	24.6	33.1	1006	1.00404
200	0.597	3693	5368	98.9	24.1	32.5	1063	1.00363
220	0.543	4170	6012	102.0	23.5	31.9	1118	1.00330
240	0.498	4634	6643	104.7	22.9	31.2	1171	1.00303
260	0.460	5087	7263	107.2	22.3	30.7	1222	1.00279
280	0.427	5530	7873	109.5	21.9	30.3	1271	1.00259
300	0.399	5966	8475	111.5	21.6	30.0	1317	1.00242
400	0.299	8091	11433	120.1	21.0	29.4	1525	1.00182
***P* = 10 MPa**								
20	39.669	−568	−316	13.0	10.9	15.0	1458	1.26198
40	31.344	−209	110	27.3	13.2	27.0	1171	1.20354
60	21.273	255	725	39.7	13.8	32.5	931	1.13527
80	14.830	686	1360	48.8	15.9	31.1	886	1.09303
100	11.417	1110	1986	55.8	19.3	31.9	904	1.07109
120	9.357	1571	2640	61.8	22.4	33.5	941	1.05801

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	v_s m/s	*D*
140	7.969	2068	3323	67.0	24.3	34.6	989	1.04925
160	6.963	2583	4020	71.7	25.0	34.9	1042	1.04294
180	6.195	3099	4713	75.7	24.9	34.4	1096	1.03814
200	5.588	3604	5393	79.3	24.4	33.6	1150	1.03436
220	5.094	4094	6057	82.5	23.7	32.8	1203	1.03129
240	4.683	4569	6704	85.3	23.1	32.0	1254	1.02874
260	4.336	5030	7336	87.8	22.6	31.3	1302	1.02659
280	4.038	5481	7958	90.1	22.1	30.8	1349	1.02475
300	3.780	5924	8570	92.3	21.8	30.4	1394	1.02315
400	2.869	8073	11559	100.9	21.2	29.6	1592	1.01753

HELIUM (He-4)

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	v_s m/s	η μPa s	*D*
***P* = 0.1 MPa (1 bar)**									
3	35.794	−39	−36	9.8	7.6	9.4	222	3.85	1.05646
4	32.477	−27	−24	13.3	9.1	16.3	185	3.33	1.05114
5	2.935	52	86	39.1	12.7	27.1	120	1.39	1.00456
10	1.238	120	201	55.2	12.5	21.7	185	2.26	1.00192
20	0.602	247	413	69.9	12.5	21.0	264	3.58	1.00093
50	0.240	623	1039	89.0	12.5	20.8	417	6.36	1.00037
100	0.120	1247	2079	103.4	12.5	20.8	589	9.78	1.00019
200	0.060	2494	4158	117.8	12.5	20.8	833	15.14	1.00009
300	0.040	3741	6237	126.3	12.5	20.8	1020	19.93	1.00006
400	0.030	4988	8315	132.3	12.5	20.8	1177	24.29	1.00005
500	0.024	6236	10394	136.9	12.5	20.8	1316	28.36	1.00004
600	0.020	7483	12472	140.7	12.5	20.8	1441	32.22	1.00003
700	0.017	8730	14551	143.9	12.5	20.8	1557	35.89	1.00003
800	0.015	9977	16630	146.7	12.5	20.8	1664	39.43	1.00002
900	0.013	11224	18708	149.1	12.5	20.8	1765	42.85	1.00002
1000	0.012	12471	20787	151.3	12.5	20.8	1861	46.16	1.00002
1500	0.008	18707	31179	159.7	12.5	20.8	2279	61.55	1.00001
***P* = 1 MPa**									
3	39.703	−42	−16	8.6	7.1	7.8	300	5.63	1.06274
4	38.210	−34	−7	11.2	8.3	10.9	290	5.01	1.06034
5	35.818	−22	6	14.0	9.7	15.1	269	4.38	1.05650
10	15.378	78	143	32.2	12.3	30.5	198	3.07	1.02402
20	6.067	228	393	49.8	12.6	22.9	274	3.94	1.00943
50	2.353	617	1042	69.8	12.5	21.1	428	6.53	1.00365
100	1.186	1245	2089	84.3	12.5	20.9	597	9.89	1.00184
200	0.597	2495	4170	98.7	12.5	20.8	838	15.21	1.00093
300	0.399	3742	6249	107.1	12.5	20.8	1024	19.96	1.00062
400	0.300	4990	8327	113.1	12.5	20.8	1180	24.32	1.00046
500	0.240	6237	10406	117.8	12.5	20.8	1319	28.38	1.00037
600	0.200	7485	12484	121.5	12.5	20.8	1444	32.23	1.00031
700	0.172	8732	14562	124.7	12.5	20.8	1559	35.91	1.00027
800	0.150	9979	16641	127.5	12.5	20.8	1666	39.44	1.00023
900	0.133	11227	18719	130.0	12.5	20.8	1767	42.86	1.00021
1000	0.120	12474	20798	132.2	12.5	20.8	1862	46.17	1.00019
1500	0.080	18710	31190	140.6	12.5	20.8	2280	61.55	1.00012
***P* = 10 MPa**									
4	51.978	−24	169	6.7	6.0	7.3	586	24.27	1.08262
5	51.118	−18	177	8.5	7.9	9.3	576	18.16	1.08122
10	46.872	23	236	16.6	11.0	14.5	546	9.31	1.07432
20	37.092	154	423	29.5	12.6	20.7	498	6.99	1.05854
50	19.192	572	1093	49.9	12.9	22.4	541	8.07	1.03003

T K	ρ mol/L	E J/mol	H J/mol	S J/mol K	C_v J/mol K	C_p J/mol K	v_s m/s	η μPa s	D
100	10.525	1231	2181	65.0	12.8	21.3	674	10.93	1.01640
200	5.605	2500	4284	79.6	12.6	20.9	889	15.82	1.00871
300	3.829	3755	6367	88.0	12.6	20.8	1063	20.25	1.00595
400	2.908	5006	8445	94.0	12.6	20.8	1212	24.54	1.00452
500	2.344	6256	10522	98.6	12.5	20.8	1346	28.56	1.00364
600	1.963	7505	12599	102.4	12.5	20.8	1467	32.38	1.00305
700	1.689	8754	14676	105.6	12.5	20.8	1580	36.04	1.00262
800	1.481	10003	16753	108.4	12.5	20.8	1685	39.56	1.00230
900	1.320	11252	18830	110.9	12.5	20.8	1784	42.96	1.00205
1000	1.189	12500	20907	113.0	12.5	20.8	1877	46.26	1.00185
1500	0.797	18742	31294	121.5	12.5	20.8	2289	61.62	1.00124

ARGON (Ar)

T K	ρ mol/L	E J/mol	H J/mol	S J/mol K	C_v J/mol K	C_p J/mol K	v_s m/s	η μPa s	λ mW/m K
P = 0.1 MPa (1 bar)									
85	35.243	–4811	–4808	53.6	23.1	44.7	820	278.8	132.4
90	0.138	1077	1802	129.4	13.1	22.5	174	7.5	6.0
100	0.123	1211	2024	131.8	12.9	21.9	184	8.2	6.6
120	0.102	1471	2456	135.7	12.6	21.4	203	9.8	7.8
140	0.087	1727	2881	139.0	12.6	21.1	220	11.4	9.0
160	0.076	1980	3302	141.8	12.5	21.0	235	13.0	10.2
180	0.067	2232	3722	144.3	12.5	21.0	250	14.5	11.4
200	0.060	2483	4141	146.5	12.5	20.9	263	16.0	12.5
220	0.055	2734	4559	148.5	12.5	20.9	276	17.5	13.7
240	0.050	2984	4976	150.3	12.5	20.9	289	18.9	14.8
260	0.046	3234	5394	152.0	12.5	20.9	300	20.3	15.8
280	0.043	3484	5811	153.5	12.5	20.8	312	21.6	16.9
300	0.040	3734	6227	155.0	12.5	20.8	323	22.9	17.9
320	0.038	3984	6644	156.3	12.5	20.8	333	24.2	18.9
340	0.035	4234	7060	157.6	12.5	20.8	344	25.4	19.9
360	0.033	4484	7477	158.7	12.5	20.8	354	26.6	20.8
380	0.032	4734	7893	159.9	12.5	20.8	363	27.8	21.7
P = 1 MPa									
85	35.307	–4820	–4792	53.5	23.1	44.6	823	281.3	133.0
90	34.542	–4598	–4569	56.1	21.6	44.7	808	242.7	124.2
100	32.909	–4145	–4115	60.9	19.9	46.2	753	185.0	109.2
120	1.181	1210	2057	114.3	14.7	30.1	189	10.3	9.3
140	0.945	1544	2603	118.5	13.5	25.4	212	11.8	10.1
160	0.799	1838	3089	121.8	13.0	23.6	231	13.3	11.1
180	0.697	2116	3551	124.5	12.8	22.7	247	14.8	12.1
200	0.619	2384	3999	126.9	12.7	22.2	262	16.3	13.2
220	0.559	2648	4438	128.9	12.6	21.8	275	17.7	14.2
240	0.509	2908	4873	130.8	12.6	21.6	288	19.1	15.3
260	0.468	3167	5304	132.6	12.6	21.5	301	20.4	16.3
280	0.433	3423	5732	134.2	12.6	21.4	312	21.8	17.3
300	0.403	3679	6159	135.6	12.5	21.3	324	23.1	18.3
320	0.377	3934	6583	137.0	12.5	21.2	334	24.3	19.2
340	0.355	4188	7007	138.3	12.5	21.2	345	25.5	20.2
360	0.335	4441	7429	139.5	12.5	21.1	355	26.7	21.1
380	0.317	4694	7851	140.6	12.5	21.1	365	27.9	22.0
P = 10 MPa									
90	35.208	–4694	–4410	55.0	21.9	43.2	846	265.2	129.5
100	33.744	–4271	–3974	59.6	20.4	44.0	800	205.0	115.1
120	30.525	–3396	–3069	67.8	18.8	46.9	672	131.2	92.1
140	26.609	–2447	–2072	75.5	17.6	54.1	526	85.9	71.7

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	v_s m/s	η μPa s	λ mW/m K
160	20.816	–1279	–799	83.9	17.4	78.6	357	51.3	52.8
180	12.296	228	1042	94.8	17.3	83.6	257	27.8	32.0
200	8.442	1118	2302	101.4	15.3	48.6	268	23.3	23.6
220	6.776	1661	3137	105.4	14.2	36.8	284	22.8	21.6
240	5.787	2087	3815	108.4	13.7	31.6	300	23.2	21.3
260	5.105	2458	4416	110.8	13.4	28.8	314	23.9	21.4
280	4.596	2798	4974	112.9	13.2	27.1	327	24.8	21.8
300	4.195	3119	5503	114.7	13.1	25.9	339	25.7	22.3
320	3.869	3427	6012	116.3	13.0	25.0	350	26.7	22.9
340	3.596	3726	6506	117.8	13.0	24.4	361	27.7	23.5
360	3.364	4017	6989	119.2	12.9	23.9	372	28.7	24.2
380	3.164	4303	7464	120.5	12.9	23.5	381	29.7	24.9

METHANE (CH_4)

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	η μPa s	λ mW/m K	*D*
***P* = 0.1 MPa (1 bar)**									
100	27.370	–5258	–5254	73.0	33.4	54.1	156.3	208.1	1.65504
125	0.099	3026	4039	156.5	25.4	34.6	5.0	13.4	1.00193
150	0.081	3667	4896	162.7	25.2	34.0	5.9	16.2	1.00159
175	0.069	4301	5743	168.0	25.2	33.8	6.9	19.1	1.00136
200	0.061	4935	6587	172.5	25.3	33.8	7.8	21.9	1.00119
225	0.054	5571	7434	176.5	25.5	34.0	8.7	24.8	1.00105
250	0.048	6216	8288	180.1	26.0	34.4	9.6	27.8	1.00095
275	0.044	6875	9156	183.4	26.6	35.0	10.4	30.9	1.00086
300	0.040	7552	10042	186.4	27.5	35.9	11.2	34.1	1.00079
325	0.037	8252	10951	189.4	28.5	36.9	12.0	37.6	1.00073
350	0.034	8979	11887	192.1	29.7	38.0	12.8	41.2	1.00068
375	0.032	9737	12853	194.8	30.9	39.3	13.5	45.1	1.00063
400	0.030	10528	13852	197.4	32.3	40.7	14.3	49.1	1.00059
425	0.028	11354	14886	199.9	33.7	42.1	15.0	53.3	1.00056
450	0.027	12215	15956	202.3	35.2	43.5	15.7	57.6	1.00053
500	0.024	14047	18204	207.1	38.0	46.4	17.0	66.5	1.00047
600	0.020	18111	23101	216.0	42.9	51.3	19.4	84.1	1.00039
***P* = 1 MPa**									
100	27.413	–5268	–5231	72.9	33.4	54.0	158.1	208.9	1.65617
125	25.137	–3882	–3842	85.3	32.4	57.4	89.2	168.2	1.59261
150	0.969	3282	4315	140.9	27.9	45.2	6.2	18.4	1.01911
175	0.765	4041	5348	147.3	26.4	38.9	7.1	20.6	1.01507
200	0.644	4736	6289	152.3	25.9	36.8	8.0	23.1	1.01268
225	0.560	5410	7197	156.6	25.9	36.0	8.9	25.8	1.01102
250	0.497	6081	8093	160.4	26.2	35.8	9.7	28.7	1.00979
275	0.448	6758	8991	163.8	26.8	36.1	10.6	31.7	1.00882
300	0.408	7449	9901	167.0	27.6	36.7	11.4	34.9	1.00803
325	0.375	8160	10829	169.9	28.6	37.6	12.1	38.3	1.00738
350	0.347	8897	11781	172.8	29.7	38.6	12.9	41.9	1.00683
375	0.323	9662	12760	175.5	31.0	39.8	13.6	45.7	1.00636
400	0.302	10460	13770	178.1	32.4	41.1	14.4	49.6	1.00595
425	0.284	11291	14814	180.6	33.8	42.4	15.1	53.8	1.00559
450	0.268	12157	15892	183.1	35.2	43.8	15.7	58.1	1.00527
500	0.241	13997	18153	187.8	38.1	46.6	17.0	66.9	1.00474
600	0.200	18073	23070	196.8	43.0	51.4	19.5	84.5	1.00394
***P* = 10 MPa**									
100	27.815	–5362	–5003	72.0	33.8	53.2	175.4	217	1.66668
125	25.754	–4036	–3648	84.1	32.7	55.3	100.4	178.8	1.60895
150	23.441	–2655	–2229	94.4	31.4	58.6	65.7	144.6	1.54553

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	η μPa s	λ mW/m K	*D*
175	20.613	−1175	−689	103.9	30.3	65.5	44.9	113.4	1.47021
200	16.602	542	1144	113.6	30.1	84.7	29.4	85.8	1.36789
225	10.547	2680	3628	125.3	30.8	102.2	17.6	61.0	1.22352
250	7.013	4289	5714	134.1	29.3	67.4	14.3	47.6	1.14481
275	5.530	5387	7195	139.8	28.7	53.4	13.8	44.1	1.11297
300	4.685	6320	8454	144.2	28.9	48.0	13.9	44.6	1.09513
325	4.115	7192	9622	147.9	29.6	45.8	14.3	46.6	1.08322
350	3.695	8047	10753	151.3	30.5	44.9	14.7	49.2	1.07450
375	3.366	8903	11874	154.4	31.7	44.8	15.2	52.3	1.06773
400	3.101	9774	12999	157.3	32.9	45.2	15.8	55.7	1.06227
425	2.880	10666	14138	160.0	34.3	46.0	16.3	59.4	1.05775
450	2.692	11584	15298	162.7	35.7	46.9	16.9	63.3	1.05392
500	2.389	13507	17692	167.7	38.5	48.9	18.0	71.6	1.04775
600	1.963	17700	22795	177.0	43.3	52.9	20.2	88.3	1.03911

ETHANE (C_2H_6)

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	v_s m/s	*D*
***P* = 0.1 MPa (1 bar)**								
95	21.50	−14555	−14550	80.2	47.2	68.7	1970	1.93480
100	21.32	−14210	−14205	83.8	47.1	69.3	1943	1.92500
125	20.41	−12468	−12463	99.3	45.0	69.8	1775	1.87634
150	19.47	−10717	−10712	112.1	43.4	70.4	1587	1.82726
175	18.49	−8938	-8933	123.1	42.7	72.1	1396	1.77671
200	0.062	5503	7123	210.1	34.5	43.8	258	1.00208
225	0.054	6401	8238	215.4	36.5	45.5	273	1.00183
250	0.049	7349	9401	220.3	38.9	47.7	287	1.00164
275	0.044	8360	10624	224.9	41.6	50.2	300	1.00148
300	0.040	9439	11914	229.4	44.5	53.1	312	1.00136
325	0.037	10592	13278	233.8	47.6	56.1	324	1.00125
350	0.035	11823	14719	238.1	50.7	59.2	335	1.00116
375	0.032	13133	16240	242.3	54.0	62.4	345	1.00108
400	0.030	14525	17841	246.4	57.2	65.6	355	1.00101
450	0.027	17548	21282	254.5	63.6	72.0	375	1.00090
500	0.024	20883	25035	262.4	69.7	78.1	393	1.00081
600	0.020	28429	33415	277.6	80.9	89.3	428	1.00067
***P* = 1 MPa**								
95	21.514	−14562	−14515	80.2	47.3	68.7	1972	1.93537
100	21.334	−14217	−14170	83.7	47.2	69.3	1946	1.92560
125	20.427	−12478	−12429	99.2	45.0	69.8	1778	1.87709
150	19.494	−10731	−10679	112.0	43.4	70.3	1592	1.82823
175	18.515	−8957	−8903	123.0	42.7	72.0	1402	1.77800
200	17.464	−7127	−7070	132.7	42.9	74.9	1209	1.72513
225	16.288	−5199	−5137	141.8	43.8	80.2	1008	1.66733
250	0.564	6762	8534	198.7	41.6	57.5	260	1.01909
275	0.489	7902	9949	204.1	43.2	56.2	280	1.01650
300	0.435	9063	11363	209.0	45.5	57.2	297	1.01467
325	0.393	10273	12815	213.7	48.3	59.1	311	1.01327
350	0.360	11546	14321	218.1	51.3	61.5	325	1.01214
375	0.333	12889	15893	222.5	54.4	64.2	337	1.01121
400	0.310	14306	17534	226.7	57.5	67.1	349	1.01043
450	0.272	17367	21038	234.9	63.8	73.0	370	1.00917
500	0.244	20730	24836	242.9	69.9	78.9	390	1.00819
600	0.201	28313	33278	258.3	81.0	89.8	427	1.00677
***P* = 10 MPa**								
95	21.624	−14626	−14163	79.5	47.4	68.5	2000	1.94104

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	v_s m/s	*D*
100	21.448	−14286	−13819	83.0	47.4	69.1	1974	1.93146
125	20.570	−12572	−12086	98.5	45.5	69.3	1814	1.88436
150	19.678	−10858	−10350	111.1	43.9	69.6	1637	1.83753
175	18.758	−9130	−8596	121.9	43.3	70.8	1459	1.79010
200	17.793	−7363	−6801	131.5	43.5	73.0	1284	1.74134
225	16.760	−5535	−4938	140.3	44.3	76.4	1110	1.69017
250	15.620	−3609	−2969	148.6	45.8	81.5	935	1.63488
275	14.301	−1539	−839	156.7	47.9	89.4	758	1.57249
300	12.666	757	1547	165.0	50.8	102.7	577	1.49740
325	10.398	3443	4404	174.1	54.7	129.1	399	1.39745
350	7.292	6643	8015	184.8	58.8	150.1	290	1.26832
375	5.182	9419	11349	194.1	60.0	115.7	289	1.18570
400	4.182	11577	13968	200.8	61.4	96.9	310	1.14797
450	3.204	15379	18500	211.5	65.8	87.5	347	1.11193
500	2.677	19135	22870	220.7	71.2	88.0	378	1.09288
600	2.076	27160	31978	237.3	81.8	94.7	427	1.07142

PROPANE (C_3H_8)

T K	ρ mol/L	*E* J/mol	*H* J/mol	*S* J/mol K	C_v J/mol K	C_p J/mol K	v_s m/s	*D*
***P* = 0.1 MPa (1 bar)**								
90	16.526	−21486	−21426	87.3	59.2	84.5	2126	2.07988
100	16.295	−20639	−20577	96.2	59.6	85.2	2041	2.05806
125	15.726	−18495	−18432	115.4	59.2	86.5	1856	2.00674
150	15.156	−16319	−16253	131.3	58.9	88.0	1685	1.95796
175	14.577	−14096	−14028	145.0	59.5	90.3	1521	1.91036
200	13.982	−11806	−11735	157.3	61.0	93.5	1359	1.86300
225	13.339	−9395	−9387	168.5	63.4	97.9	1197	1.81487
250	0.050	9194	11213	257.6	57.2	66.8	228	1.00238
275	0.045	10691	12930	264.1	61.6	70.7	239	1.00215
300	0.041	12297	14752	270.5	66.2	75.1	249	1.00195
325	0.037	14019	16689	276.7	71.1	79.8	259	1.00179
350	0.035	15862	18744	282.8	76.0	84.6	269	1.00166
375	0.032	17827	20921	288.8	80.9	89.5	278	1.00154
400	0.030	19912	23217	294.7	85.7	94.3	286	1.00144
450	0.027	24441	28166	306.4	95.2	103.6	303	1.00128
500	0.024	29428	33573	317.7	104.1	112.6	318	1.00115
600	0.020	40677	45658	339.7	120.4	128.8	347	1.00095
***P* = 1 MPa**								
90	16.526	−21486	−21426	87.2	59.3	84.5	2128	2.08034
100	16.295	−20639	−20577	96.2	59.7	85.2	2043	2.05856
125	15.726	−18495	−18432	115.3	59.2	86.4	1859	2.00736
150	15.156	−16319	−16253	131.2	59.0	88.0	1690	1.95873
175	14.577	−14096	−14028	144.9	59.6	90.2	1526	1.91132
200	13.982	−11806	−11735	157.2	61.1	93.4	1365	1.86421
225	13.361	−9424	−9349	168.4	63.4	97.7	1205	1.81642
250	12.696	−6919	−6840	179.0	66.4	103.3	1045	1.76672
275	11.962	−4252	−4169	189.1	70.0	110.8	881	1.71316
300	11.102	−1360	−1270	199.2	74.1	121.9	708	1.65216
325	0.428	13278	15614	255.2	74.1	89.6	233	1.02067
350	0.383	15259	17869	261.9	78.0	91.2	248	1.01846
375	0.349	17318	20183	268.3	82.2	94.2	261	1.01678
400	0.322	19472	22582	274.4	86.7	97.8	272	1.01544
450	0.279	24092	27672	286.4	95.7	105.9	293	1.01337
500	0.248	29137	33172	298.0	104.4	114.1	312	1.01184
600	0.203	40455	45374	320.2	120.5	129.7	344	1.00968

T K	ρ mol/L	E J/mol	H J/mol	S J/mol K	C_v J/mol K	C_p J/mol K	v_s m/s	D
P = 10 MPa								
90	16.590	−21553	−20951	86.5	59.9	84.4	2146	2.08489
100	16.364	−20714	−20103	95.4	60.1	85.1	2068	2.06350
125	15.810	−18595	−17962	114.5	59.6	86.1	1895	2.01342
150	15.259	−16448	−15793	130.3	59.3	87.5	1733	1.96617
175	14.705	−14261	−13581	144.0	59.9	89.5	1577	1.92048
200	14.141	−12016	−11309	156.1	61.4	92.4	1425	1.87557
225	13.562	−9692	−8955	167.2	63.7	96.1	1277	1.83076
250	12.960	−7268	−6496	177.5	66.7	100.7	1133	1.78529
275	12.322	−4721	−3909	187.4	70.2	106.4	991	1.73826
300	11.631	−2027	−1167	196.9	74.1	113.2	851	1.68849
325	10.860	843	1764	206.3	78.4	121.5	715	1.63437
350	9.973	3924	4927	215.7	82.9	132.0	582	1.57361
375	8.905	7270	8393	225.2	87.7	146.1	455	1.50271
400	7.561	10957	12279	235.3	93.0	165.7	339	1.41671
450	4.614	18845	21013	255.8	101.8	167.8	249	1.24060
500	3.241	25567	28652	272.0	107.8	142.7	276	1.16439
600	2.242	38131	42591	297.4	121.7	140.5	332	1.11122

VIRIAL COEFFICIENTS OF SELECTED GASES

Henry V. Kehiaian

This table gives second virial coefficients of about 110 inorganic and organic gases as a function of temperature. Selected data from the literature have been fitted by least squares to the equation

$$B / \mathrm{cm^3 mol^{-1}} = \sum_{i=1}^{n} a(i)[(T_o / T) - 1]^{i-1}$$

where T_o = 298.15 K. The table gives the coefficients $a(i)$ and values of B at fixed temperature increments, as calculated from this smoothing equation.

The equation may be used with the tabulated coefficients for interpolation within the indicated temperature range. It should not be used for extrapolation beyond this range.

Compounds are listed in the modified Hill order (see Introduction), with carbon-containing compounds following those compounds not containing carbon.

A useful compilation of virial coefficient data from the literature may be found in:

J. H. Dymond and E. B. Smith, *The Virial Coefficients of Pure Gases and Mixtures, A Critical Compilation*, Oxford University Press, Oxford, 1980.

Compounds Not Containing Carbon

Mol. form.	Name	T/K	B/cm³ mol⁻¹
Ar	Argon	100	−184
		120	−131
		140	−98
	a(1) = −16	160	−76
	a(2) = −60	80	−60
	a(3) = −10	200	−48
		300	−16
		400	−1
		500	7
		600	12
		700	15
		800	18
		900	20
		1000	22
BF_3	Boron trifluoride	200	−338
		240	−202
		280	−129
	a(1) = −106	320	−85
	a(2) = −330	360	−56
	a(3) = −251	400	−37
	a(4) = −80	440	−23
ClH	Hydrogen chloride	190	−451
		230	−269
		270	−181
	a(1) = −144	310	−132
	a(2) = −325	350	−102
	a(3) = −277	390	−81
	a(4) = −170	430	−66
		470	−54
Cl_2	Chlorine	210	−508
		220	−483
		230	−457
	a(1) = −303	240	−432
	a(2) = −555	250	−407
	a(3) = 9	260	−383
	a(4) = 329	270	−360
	a(5) = 68	280	−339
		290	−318
		300	−299
		350	−221
		400	−166
		450	−126
		500	−97
		600	−59
		700	−36
		800	−22
		900	−12
F_2	Fluorine	80	−386
		110	−171
		140	−113
	a(1) = −25	170	−73
	a(2) = 21	200	−47
	a(3) = −185	230	−32
	a(4) = 113	260	−25
F_4Si	Silicon tetrafluoride	210	−268
		240	−213
		270	−170
	a(1) = −138	300	−136
	a(2) = −312	330	−108
		360	−84
		390	−64
		420	−47
		450	−32
F_5I	Iodine pentafluoride	320	−2540
		330	−2344
		340	−2172
	a(1) = −3077	350	−2021
	a(2) = −8474	360	−1890
	a(3) = −9116	370	−1775
		380	−1674
		390	−1587
		400	−1510
		410	−1443
F_5P	Phosphorus pentafluoride	320	−162
		340	−143
		360	−127
	a(1) = −186	380	−112
	a(2) = −345	400	−98
		420	−86
		440	−75
		460	−64
F_6Mo	Molybdenum hexafluoride	300	−896
		310	−810
		320	−737

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
	a(1) = −914	330	−677
	a(2) = −2922	340	−627
	a(3) = −4778	350	−586
		360	−553
		370	−527
		380	−506
		390	−491
F_6S	Sulfur hexafluoride	200	−685
		250	−416
		300	−275
	a(1) = −279	350	−190
	a(2) = −647	400	−135
	a(3) = −335	450	−96
	a(4) = −72	500	−68
F_6U	Uranium hexafluoride	320	−1030
		340	−905
		360	−805
	a(1) = −1204	380	−724
	a(2) = −2690	400	−658
	a(3) = −2144	420	−604
		440	−560
F_6W	Tungsten hexafluoride	320	−641
		340	−578
		360	−523
	a(1) = −719	380	−473
	a(2) = −1143	400	−428
		420	−387
		440	−350
		460	−317
H_2	Hydrogen	15	−230
		20	−151
		25	−108
	a(1) = 15.4	30	−82
	a(2) = −9.0	35	−64
	a(3) = −0.2	40	−52
		45	−42
		50	−35
		60	−24
		70	−16
		80	−11
		90	−7
		100	−3
		200	11
		300	15
		400	18
H_2O	Water	300	−1126
		320	−850
		340	−660
	a(1) = −1158	360	−526
	a(2) = −5157	380	−428
	a(3) = −10301	400	−356
	a(4) =−10597	420	−301
	a(5) = −4415	440	−258
		460	−224
		480	−197
		500	−175
		600	−104
		700	−67
		800	−44
		900	−30
		1000	−20
		1100	−14
		1200	−11
H_3N	Ammonia	290	−302
		300	−265
		310	−236
	a(1) = −271	320	−213
	a(2) = −1022	330	−194
	a(3) = −2715	340	−179
	a(4) = −4189	350	−166
		360	−154
		370	−144
		380	−135
		400	−118
		420	−101
H_3P	Phosphine	190	−457
		200	−404
		210	−364
	a(1) = −146	220	−332
	a(2) = −733	230	−305
	a(3) = 1022	240	−281
	a(4) = −1220	250	−258
		260	−235
		270	−213
		280	−190
		290	−166
He	Helium	2	−172
		6	−48
		10	−24
	a(1) = 12	14	−13
	a(2) = −1	18	−7
		22	−3
		26	−1
		30	1
		50	6
		70	8
		90	10
		110	10
		150	11
		250	12
		650	13
		700	13
Kr	Krypton	110	−363
		120	−307
		130	−263
	a(1) = −51	140	−229
	a(2) = −118	150	−201
	a(3) = −29	160	−178
	a(4) = −5	170	−159
		180	−143
		190	−129
		200	−117
		250	−75
		300	−51
		400	−23
		500	−8
		600	2
		700	8
NO	Nitric oxide	120	−232
		130	−176
		140	−138
	a(1) = −12	150	−113

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
	a(2) = −119	160	−96
	a(3) = 89	170	−83
	a(4) = −73	180	−73
		190	−65
		200	−58
		210	−52
		230	−42
		250	−32
		270	−24
N_2	Nitrogen	75	−274
		100	−161
		125	−104
	a(1) = −4	150	−71
	a(2) = −56	175	−49
	a(3) = −12	200	−34
		225	−24
		250	−15
		300	−4
		400	9
		500	16
		600	21
		700	24
N_2O	Nitrous oxide	240	−219
		260	−181
		280	−151
	a(1) = −130	300	−128
	a(2) = −307	320	−110
	a(3) = −248	340	−96
		360	−85
		380	−76
		400	−68
Ne	Neon	60	−25
		80	−13
		100	−6
	a(1) = 10.8	120	−1
	a(2) = −7.5	140	2
	a(3) = 0.4	160	4
		180	6
		200	7
		300	11
		400	13
		500	14
		600	15
O_2	Oxygen	90	−241
		110	−161
		130	−117
	a(1) = −16	150	−88
	a(2) = −62	170	−69
	a(3) = −8	190	−55
	a(4) = −3	210	−44
		230	−36
		250	−29
		270	−23
		290	−18
		310	−14
		330	−10
		350	−7
		400	−1
O_2S	Sulfur dioxide	290	−465
		320	−354
		350	−276
	a(1) = −430	380	−221
	a(2) = −1193	410	−181
	a(3) = −1029	440	−153
		470	−132
Xe	Xenon	160	−421
		170	−377
		180	−340
	a(1) = −130	190	−307
	a(2) = −262	200	−280
	a(3) = −87	210	−255
		220	−234
		230	−215
		240	−199
		250	−184
		300	−129
		350	−93
		400	−69
		500	−39
		600	−21
		650	−14

Compounds Containing Carbon

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
$CClF_3$	Chlorotrifluoromethane	240	−369
		290	−237
		340	−165
	a(1) = −223	390	−119
	a(2) = −504	440	−86
	a(3) = −340	490	−60
	a(4) = −291	540	−39
CCl_2F_2	Dichlorodifluoromethane	250	−769
		280	−570
		310	−441
	a(1) = −486	340	−353
	a(2) = −1217	370	−289
	a(3) = −1188	400	−241
	a(4) = −698	430	−204
		460	−174
CCl_3F	Trichlorofluoromethane	240	−1140
		280	−879
		320	−689
	a(1) = −786	360	−545
	a(2) = −1428	400	−431
	a(3) = −142	440	−340
		480	−265
CCl_4	Tetrachloromethane	320	−1345
		340	−1171
		360	−1040
	a(1) = −1600	380	−942
	a(2) = −4059	400	−868
	a(3) = −4653	420	−814
CF_4	Tetrafluoromethane	250	−137
		300	−87
		350	−55
	a(1) = −88	400	−32
	a(2) = −238	450	−16
	a(3) = −70	500	−4
		600	14
		700	25

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
		800	33
$CHClF_2$	Chlorodifluoromethane	300	−343
		325	−298
		350	−257
	a(1) = −347	375	−221
	a(2) = −575	400	−188
	a(3) = 187	425	−158
$CHCl_2F$	Dichlorofluoromethane	250	−728
		275	−634
		300	−557
	a(1) = −562	325	−491
	a(2) = −862	350	−434
		375	−385
		400	−343
		425	−305
		450	−271
$CHCl_3$	Trichloromethane	320	−1001
		330	−926
		340	−858
	a(1) = −1193	350	−797
	a(2) = −2936	360	−740
	a(3) = −1751	370	−689
		380	−642
		390	−599
		400	−559
CHF_3	Trifluoromethane	200	−433
		220	−350
		240	−288
	a(1) = −177	260	−241
	a(2) = −399	280	−204
	a(3) = −250	300	−174
		320	−151
		340	−132
		360	−116
		380	−103
		400	−91
CH_2Cl_2	Dichloromethane	320	−706
		330	−634
		340	−574
	a(1) = −913	350	−524
	a(2) = −3371	360	−482
	a(3) = −5013	370	−447
		380	−420
		400	−380
		420	−357
CH_2F_2	Difluoromethane	280	−375
		290	−343
		300	−316
	a(1) = −321	310	−294
	a(2) = −754	320	−275
	a(3) = −1300	330	−260
		340	−248
		350	−238
CH_3Br	Bromomethane	280	−645
		290	−596
		300	−551
	a(1) = −559	310	−509
	a(2) = −1324	320	−469
		340	−396
		360	−332
		380	−274

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
CH_3Cl	Chloromethane	280	−466
		300	−402
		320	−348
	a(1) = −407	340	−304
	a(2) = −887	360	−266
	a(3) = −385	380	−234
		400	−206
		420	−182
		440	−161
		460	−142
		480	−126
		500	−112
		600	−58
CH_3F	Fluoromethane	280	−244
		300	−205
		320	−174
	a(1) = −209	340	−150
	a(2) = −525	360	−129
	a(3) = −365	380	−112
		400	−99
		420	−87
CH_3I	Iodomethane	310	−725
		320	−646
		330	−582
	a(1) = −844	340	−531
	a(2) = −3353	350	−492
	a(3) = −6590	360	−462
		370	−441
		380	−427
CH_4	Methane	110	−328
		120	−276
		130	−237
	a(1) = −43	140	−206
	a(2) = −114	150	−181
	a(3) = −19	160	−160
	a(4) = −7	170	−143
		180	−128
		190	−116
		200	−105
		250	−66
		300	−43
		350	−27
		400	−16
		500	0
		600	10
CH_4O	Methanol	320	−1431
		330	−1299
		340	−1174
	a(1) = −1752	350	−1056
	a(2) = −4694	360	−945
		370	−840
		380	−741
		390	−646
		400	−557
CH_5N	Methylamine	300	−451
		325	−367
		350	−304
	a(1) = −459	375	−257
	a(2) = −1191	400	−220
	a(3) = −995	425	−192
		450	−170

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
		500	−140
		550	−122
CO	Carbon monoxide	210	−36
		240	−24
		270	−15
	a(1) = −9	300	−8
	a(2) = −58	330	−3
	a(3) = −18	360	1
		420	7
		480	11
CO_2	Carbon dioxide	220	−244
		240	−204
		260	−172
	a(1) = −127	280	−146
	a(2) = −288	300	−126
	a(3) = −118	320	−108
		340	−94
		360	−81
		380	−71
		400	−62
		500	−30
		600	−13
		700	−1
		800	7
		900	12
		1000	16
		1100	19
CS_2	Carbon disulfide	280	−932
		310	−740
		340	−603
	a(1) = −807	370	−504
	a(2) = −1829	400	−431
	a(3) = −1371	430	−375
$C_2Cl_2F_4$	1,2-Dichloro-1,1,2,2-tetrafluoroethane	300	−801
		320	−695
		340	−608
	a(1) = −812	360	−536
	a(2) = −1773	380	−475
	a(3) = −963	400	−423
		420	−379
		440	−341
		460	−307
		480	−279
		500	−253
$C_2Cl_3F_3$	1,1,2-Trichloro-1,2,2-trifluoroethane	290	−1041
		310	−943
		330	−856
	a(1) = −999	350	−780
	a(2) = −1479	370	−712
		390	−651
		410	−596
		430	−546
		450	−500
C_2H_2	Ethyne	200	−573
		210	−500
		220	−440
	a(1) = −216	230	−390
	a(2) = −375	240	−349
	a(3) = −716	250	−315
		260	−287
		270	−263
C_2H_3N	Ethanenitrile	330	−3468
		340	−2971
		350	−2563
	a(1) = −5840	360	−2233
	a(2) = −29175	370	−1970
	a(3) = −47611	380	−1765
		390	−1610
		400	−1499
		410	−1425
C_2H_4	Ethene	240	−218
		270	−172
		300	−139
	a(1) = −140	330	−113
	a(2) = −296	360	−92
	a(3) = −101	390	−76
		420	−63
		450	−52
$C_2H_4Cl_2$	1,2-Dichloroethane	370	−812
		390	−716
		410	−635
	a(1) = −1362	430	−566
	a(2) = −3240	450	−508
	a(3) = −2100	470	−458
		490	−416
		510	−379
		530	−347
		550	−319
		570	−295
C_2H_4O	Ethanal	290	−1352
		320	−927
		350	−654
	a(1) = −1217	380	−482
	a(2) = −4647	410	−375
	a(3) = −5725	440	−314
		470	−283
$C_2H_4O_2$	Methyl methanoate	320	−821
		330	−744
		340	−677
	a(1) = −1035	350	−620
	a(2) = −3425	360	−571
	a(3) = −4203	370	−528
		380	−492
		390	−461
		400	−435
C_2H_5Cl	Chloroethane	320	−634
		360	−450
		400	−330
	a(1) = −777	440	−249
	a(2) = −2205	480	−195
	a(3) = −1764	520	−157
		560	−131
		600	−114
C_2H_6	Ethane	200	−409
		220	−337
		240	−284
	a(1) = −184	260	−242
	a(2) = −376	280	−209
	a(3) = −143	300	−181
	a(4) = −54	320	−159
		340	−140

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
		360	−123
		380	−109
		400	−96
		500	−52
		600	−24
C_2H_6O	Ethanol	320	−2710
		330	−2135
		340	−1676
	a(1) = −4475	350	−1317
	a(2) = −29719	360	−1043
	a(3) = −56716	370	−843
		380	−705
		390	−622
C_2H_6O	Dimethyl ether	275	−536
		280	−517
		285	−499
	a(1) = −455	290	−482
	a(2) = −965	295	−465
		300	−449
		305	−433
		310	−418
C_2H_7N	Dimethylamine	310	−606
		320	−563
		330	−523
	a(1) = −662	340	−487
	a(2) = −1504	350	−454
	a(3) = −667	360	−423
		370	−395
		380	−369
		390	−345
		400	−322
C_2H_7N	Ethylamine	300	−773
		310	−710
		320	−654
	a(1) = −785	330	−604
	a(2) = −2012	340	−558
	a(3) = −1397	350	−517
		360	−480
		370	−447
		380	−416
		390	−389
		400	−363
C_3H_6	Cyclopropane	300	−383
		310	−356
		320	−332
	a(1) = −388	330	−310
	a(2) = −861	340	−290
	a(3) = −538	350	−272
		360	−256
		370	−241
		380	−227
		390	−215
		400	−204
C_3H_6	Propene	280	−395
		300	−342
		320	−299
	a(1) = −347	340	−262
	a(2) = −727	360	−232
	a(3) = −325	380	−205
		400	−183
		420	−163

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
		440	−146
		460	−131
		480	−118
		500	−106
C_3H_6O	2-Propanone	300	−1996
		320	−1522
		340	−1198
	a(1) = −2051	360	−971
	a(2) = −8903	380	−806
	a(3) = −18056	400	−683
	a(4) = −16448	420	−586
		440	−506
		460	−437
		480	−375
C_3H_6O	Ethyl methanoate	330	−1003
		340	−916
		350	−839
	a(1) = −1371	360	−771
	a(2) = −4231	370	−712
	a(3) = −4312	380	−660
		390	−614
C_3H_6O	Methyl ethanoate	320	−1320
		330	−1186
		340	−1074
	a(1) = −1709	350	−980
	a(2) = −6348	360	−903
	a(3) = −9650	370	−840
		380	−789
		390	−749
C_3H_7Cl	1-Chloropropane	310	−1001
		340	−772
		370	−614
	a(1) = −1121	400	−501
	a(2) = −3271	430	−417
	a(3) = −3786	460	−352
	a(4) = −1974	490	−302
		520	−261
		550	−227
		580	−198
C_3H_8	Propane	240	−641
		260	−527
		280	−444
	a(1) = −386	300	−381
	a(2) = −844	320	−331
	a(3) = −720	340	−292
	a(4) = −574	360	−259
		380	−232
		400	−208
		440	−169
		480	−138
		520	−112
		560	−90
C_3H_8O	1-Propanol	380	−873
		385	−826
		390	−783
	a(1) = −2690	395	−744
	a(2) = −12040	400	−709
	a(3) = −16738	405	−679
		410	−651
		415	−627
		420	−606

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
C_3H_8O	2-Propanol	380	−821
		385	−766
		390	−717
	a(1) = −3165	395	−674
	a(2) = −16092	400	−636
	a(3) = −24197	405	−604
		410	−576
		415	−552
		420	−533
C_3H_9N	Trimethylamine	310	−675
		320	−628
		330	−585
	a(1) = −737	340	−547
	a(2) = −1669	350	−512
	a(3) = −986	360	−480
		370	−450
C_4H_8	1-Butene	300	−624
		320	−539
		340	−470
	a(1) = −633	360	−413
	a(2) = −1442	380	−366
	a(3) = −932	400	−327
		420	−294
C_4H_8O	2-Butanone	310	−2056
		320	−1878
		330	−1712
	a(1) = −2282	340	−1555
	a(2) = −5907	350	−1407
		360	−1267
		370	−1135
$C_4H_8O_2$	Propyl methanoate	330	−1496
		340	−1354
		350	−1231
	a(1) = −2118	360	−1126
	a(2) = −7299	370	−1035
	a(3) = −8851	380	−957
		390	−890
		400	−834
$C_4H_8O_2$	Ethyl ethanoate	330	−1543
		340	−1385
		350	−1254
	a(1) = −2272	360	−1144
	a(2) = −8818	370	−1055
	a(3) = −13130	380	−982
		390	−923
		400	−878
$C_4H_8O_2$	Methyl propanoate	330	−1588
		340	−1444
		350	−1319
	a(1) = −2216	360	−1211
	a(2) = −7339	370	−1117
	a(3) = −8658	380	−1037
		390	−968
		400	−908
C_4H_9Cl	1-Chlorobutane	330	−1224
		370	−898
		410	−691
	a(1) = −1643	450	−551
	a(2) = −4897	490	−449
	a(3) = −6178	530	−371
	a(4) = −3718	570	−309

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
C_4H_{10}	Butane	250	−1170
		280	−863
		310	−668
	a(1) = −735	340	−536
	a(2) = −1835	370	−442
	a(3) = −1922	400	−371
	a(4) = −1330	430	−315
		460	−270
		490	−232
		520	−199
		550	−171
C_4H_{10}	2-Methylpropane	270	−900
		300	−697
		330	−553
	a(1) = −707	360	−450
	a(2) = −1719	390	−374
	a(3) = −1282	420	−317
		450	−273
		480	−240
		510	−215
$C_4H_{10}O$	1-Butanol	350	−1693
		360	−1544
		370	−1402
	a(1) = −2629	380	−1268
	a(2) = −6315	390	−1141
		400	−1021
		420	−796
		440	−593
$C_4H_{10}O$	2-Methyl-1-propanol	390	−1076
		400	−979
		410	−887
	a(1) = −2269	420	−800
	a(2) = −5065	430	−716
		440	−636
$C_4H_{10}O$	2-Butanol	380	−1110
		390	−1005
		400	−906
	a(1) = −2232	410	−811
	a(2) = −5209	420	−721
$C_4H_{10}O$	2-Methyl-2-propanol	380	−924
		390	−827
		400	−736
	a(1) = −1952	410	−649
	a(2) = −4775	420	−567
$C_4H_{10}O$	Diethyl ether	280	−1550
		300	−1199
		320	−954
	a(1) = −1226	340	−776
	a(2) = −4458	360	−638
	a(3) = −7746	380	−525
	a(4) = −10005	400	−428
		420	−340
$C_4H_{11}N$	Diethylamine	320	−1228
		330	−1134
		340	−1056
	a(1) = −1522	350	−988
	a(2) = −5204	360	−926
	a(3) = −15047	370	−868
	a(4) = −28835	380	−812
		390	−755

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
		400	–697
C_5H_5N	Pyridine	350	–1257
		360	–1176
		370	–1099
	a(1) = –1765	380	–1026
	a(2) = –3431	390	–957
		400	–892
		420	–770
		440	–659
C_5H_{10}	Cyclopentane	300	–1049
		305	–1015
		310	–981
	a(1) = –1062	315	–949
	a(2) = –2116	320	–918
C_5H_{10}	1-Pentene	310	–966
		320	–898
		330	–836
	a(1) = –1055	340	–780
	a(2) = –2377	350	–729
	a(3) = –1189	360	–681
		370	–638
		380	–598
		390	–561
		400	–527
		410	–495
$C_5H_{10}O$	2-Pentanone	330	–2850
		340	–2420
		350	–2076
	a(1) = –4962	360	–1804
	a(2) = –26372	370	–1595
	a(3) = –46537	380	–1440
		390	–1332
C_5H_{12}	Pentane	300	–1234
		310	–1130
		320	–1038
	a(1) = –1254	330	–957
	a(2) = –3345	340	–884
	a(3) = –2726	350	–818
		400	–579
		450	–436
		500	–348
		550	–294
C_5H_{12}	2-Methylbutane	280	–1263
		290	–1166
		300	–1079
	a(1) = –1095	310	–1001
	a(2) = –2503	320	–931
	a(3) = –1534	330	–867
		340	–810
		350	–757
		400	–557
		450	–424
C_5H_{12}	2,2-Dimethylpropane	300	–916
		310	–843
		320	–780
	a(1) = –931	330	–724
	a(2) = –2387	340	–674
	a(3) = –2641	350	–629
	a(4) = –1810	360	–590
		370	–554
		380	–521
		390	–492
		400	–464
		450	–357
		500	–279
		550	–218
C_6H_6	Benzene	290	–1588
		300	–1454
		310	–1335
	a(1) = –1477	320	–1231
	a(2) = –3851	330	–1139
	a(3) = –3683	340	–1056
	a(4) = –1423	350	–983
		400	–712
		450	–542
		500	–429
		550	–349
		600	–291
C_6H_7N	2-Methylpyridine	360	–1656
		370	–1523
		380	–1404
	a(1) = –2940	390	–1297
	a(2) = –8813	400	–1202
	a(3) = –7809	410	–1117
		420	–1040
		430	–972
C_6H_7N	3-Methylpyridine	380	–1819
		390	–1612
		400	–1448
	a(1) = –6304	410	–1322
	a(2) = –30415	420	–1230
	a(3) = –44549	430	–1166
C_6H_7N	4-Methylpyridine	380	–1787
		390	–1578
		400	–1417
	a(1) = –6553	410	–1297
	a(2) = –32873	420	–1214
	a(3) = –49874	430	–1163
C_6H_{12}	Cyclohexane	300	–1698
		320	–1391
		340	–1170
	a(1) = –1733	360	–1007
	a(2) = –5618	380	–883
	a(3) = –9486	400	–786
	a(4) = –7936	420	–707
		440	–641
		460	–584
		480	–534
		500	–488
		520	–446
		540	–406
		560	–368
C_6H_{12}	Methylcyclopentane	305	–1447
		315	–1357
		325	–1272
	a(1) = –1512	335	–1192
	a(2) = –2910	345	–1117
C_6H_{14}	Hexane	300	–1920
		310	–1724
		320	–1561
	a(1) = –1961	330	–1424
	a(2) = –6691	340	–1309

Mol. form.	Name	T/K	B/cm^3 mol^{-1}
	a(3) = –13167	350	–1209
	a(4) = –15273	360	–1123
		370	–1046
		380	–978
		390	–916
		400	–859
		410	–806
		430	–707
		450	–616
$C_6H_{15}N$	Triethylamine	330	–1562
		340	–1444
		350	–1340
	a(1) = –2061	360	–1249
	a(2) = –5735	370	–1169
	a(3) = –5899	380	–1099
		390	–1037
		400	–983
C_7H_8	Toluene	350	–1641
		360	–1511
		370	–1394
	a(1) = –2620	380	–1289
	a(2) = –7548	390	–1195
	a(3) = –6349	400	–1110
		410	–1034
		420	–965
		430	–903
C_7H_{14}	1-Heptene	340	–1781
		350	–1651
		360	–1532
	a(1) = –2491	370	–1424
	a(2) = –6230	380	–1324
	a(3) = –3780	390	–1233
		400	–1150
		410	–1073
C_7H_{16}	Heptane	300	–2782
		320	–2297
		340	–1928
	a(1) = –2834	360	–1641
	a(2) = –8523	380	–1415
	a(3) = –10068	400	–1233
	a(4) = –5051	420	–1085
		440	–963
		460	–862
		480	–775
		500	–702
		540	–583
		580	–490
		620	–416
		660	–355
		700	–304
C_8H_{10}	1,2-Dimethylbenzene	380	–2046
		390	–1848
		400	–1681
	a(1) = –5632	410	–1543
	a(2) = –22873	420	–1428
	a(3) = –28900	430	–1335
		440	–1261
C_8H_{10}	1,3-Dimethylbenzene	380	–2082
		390	–1865
		400	–1679
	a(1) = –5808	410	–1521
	a(2) = –23244	420	–1388
	a(3) = –27607	430	–1276
		440	–1184
C_8H_{10}	1,4-Dimethylbenzene	380	–2043
		390	–1851
		400	–1680
	a(1) = –4921	410	–1529
	a(2) = –16843	420	–1395
	a(3) = –16159	430	–1276
		440	–1171
C_8H_{16}	1-Octene	360	–2147
		370	–2000
		380	–1861
	a(1) = –3273	390	–1729
	a(2) = –6557	400	–1604
		410	–1485
C_8H_{18}	Octane	300	–4042
		350	–2511
		400	–1704
	a(1) = –4123	450	–1234
	a(2) = –13120	500	–936
	a(3) = –16408	550	–732
	a(4) = –8580	600	–583
		650	–468
		700	–375

VAN DER WAALS CONSTANTS FOR GASES

The van der Waals equation of state for a real gas is

$$(P + n^2a/V^2)(V - nb) = nRT$$

where P is the pressure, V the volume, T the temperature, n the amount of substance (in moles), and R the gas constant. The van der Waals constants a and b are characteristic of the substance and are independent of temperature. They are related to the critical temperature and pressure, T_c and P_c, by

$$a = 27R^2T_c^2/64P_c \quad b = RT_c/8P_c$$

This table gives values of a and b for some common gases. Most of the values have been calculated from the critical temperature and pressure values given in the table "Critical Constants" in this section. Van der Waals constants for other gases may easily be calculated from the data in that table.

To convert the van der Waals constants to SI units, note that 1 bar L^2/mol^2 = 0.1 Pa m^6/mol^2 and 1 L/mol = 0.001 m^3/mol.

Reference

Reid, R. C, Prausnitz, J. M., and Poling, B. E., *The Properties of Gases and Liquids, Fourth Edition*, McGraw-Hill, New York, 1987.

Substance	*a* bar L^2/mol^2	*b* L/mol
Acetic acid	17.71	0.1065
Acetone	16.02	0.1124
Acetylene	4.516	0.0522
Ammonia	4.225	0.0371
Aniline	29.14	0.1486
Argon	1.355	0.0320
Benzene	18.82	0.1193
Bromine	9.75	0.0591
Butane	13.89	0.1164
1-Butanol	20.94	0.1326
2-Butanone	19.97	0.1326
Carbon dioxide	3.658	0.0429
Carbon disulfide	11.25	0.0726
Carbon monoxide	1.472	0.0395
Chlorine	6.343	0.0542
Chlorobenzene	25.80	0.1454
Chloroethane	11.66	0.0903
Chloromethane	7.566	0.0648
Cyclohexane	21.92	0.1411
Cyclopropane	8.34	0.0747
Decane	52.74	0.3043
1-Decanol	59.51	0.3086
Diethyl ether	17.46	0.1333
Dimethyl ether	8.690	0.0774
Dodecane	69.38	0.3758
1-Dodecanol	75.70	0.3750
Ethane	5.580	0.0651
Ethanol	12.56	0.0871
Ethylene	4.612	0.0582
Fluorine	1.171	0.0290
Furan	12.74	0.0926
Helium	0.0346	0.0238
Heptane	31.06	0.2049
1-Heptanol	38.17	0.2150
Hexane	24.84	0.1744
1-Hexanol	31.79	0.1856
Hydrazine	8.46	0.0462
Hydrogen	0.2452	0.0265
Hydrogen bromide	4.500	0.0442
Hydrogen chloride	3.700	0.0406
Hydrogen cyanide	11.29	0.0881
Hydrogen fluoride	9.565	0.0739
Hydrogen iodide	6.309	0.0530
Hydrogen sulfide	4.544	0.0434
Isobutane	13.32	0.1164
Krypton	5.193	0.0106
Methane	2.303	0.0431
Methanol	9.476	0.0659
Methylamine	7.106	0.0588
Neon	0.208	0.0167
Neopentane	17.17	0.1411
Nitric oxide	1.46	0.0289
Nitrogen	1.370	0.0387
Nitrogen dioxide	5.36	0.0443
Nitrogen trifluoride	3.58	0.0545
Nitrous oxide	3.852	0.0444
Octane	37.88	0.2374
1-Octanol	44.71	0.2442
Oxygen	1.382	0.0319
Ozone	3.570	0.0487
Pentane	19.09	0.1449
1-Pentanol	25.88	0.1568
Phenol	22.93	0.1177
Propane	9.39	0.0905
1-Propanol	16.26	0.1079
2-Propanol	15.82	0.1109
Propene	8.442	0.0824
Pyridine	19.77	0.1137
Pyrrole	18.82	0.1049
Silane	4.38	0.0579
Sulfur dioxide	6.865	0.0568
Sulfur hexafluoride	7.857	0.0879
Tetrachloromethane	20.01	0.1281
Tetrachlorosilane	20.96	0.1470
Tetrafluoroethylene	6.954	0.0809
Tetrafluoromethane	4.040	0.0633
Tetrafluorosilane	5.259	0.0724
Tetrahydrofuran	16.39	0.1082
Thiophene	17.21	0.1058
Toluene	24.86	0.1497
1,1,1-Trichloroethane	20.15	0.1317
Trichloromethane	15.34	0.1019
Trifluoromethane	5.378	0.0640
Trimethylamine	13.37	0.1101
Water	5.537	0.0305
Xenon	4.192	0.0516

MEAN FREE PATH AND RELATED PROPERTIES OF GASES

In the simplest version of the kinetic theory of gases, molecules are treated as hard spheres of diameter d which make binary collisions only. In this approximation the mean distance traveled by a molecule between successive collisions, the mean free path l, is related to the collision diameter by:

$$l = \frac{kT}{\pi\sqrt{2}Pd^2}$$

where P is the pressure, T the absolute temperature, and k the Boltzmann constant. At standard conditions (P = 100 000 Pa and T = 298.15 K) this relation becomes:

$$l = \frac{9.27 \cdot 10^{27}}{d^2}$$

where l and d are in meters.

Using the same model and the same standard pressure, the collision diameter can be calculated from the viscosity η by the kinetic theory relation:

$$\eta = \frac{2.67 \cdot 10^{-20}(MT)^{1/2}}{d^2}$$

where η is in units of μPa s and M is the molar mass in g/mol. Kinetic theory also gives a relation for the mean velocity $\bar{v}$ of molecules of mass m:

$$\bar{v} = \left(\frac{8kT}{\pi m}\right)^{1/2} = 145.5(T/M)^{1/2}\ \text{m/s}$$

Finally, the mean time τ between collisions can be calculated from the relation $\tau\bar{v} = l$.

The table below gives values of l, $\bar{v}$, and τ for some common gases at 25°C and atmospheric pressure, as well as the value of d, all calculated from measured gas viscosities (see References 2 and 3 and the table "Viscosity of Gases" in this section). It is seen from the above equations that the mean free path varies directly with T and inversely with P, while the mean velocity varies as the square root of T and, in this approximation, is independent of P.

A more accurate model, in which molecular interactions are described by a Lennard-Jones potential, gives mean free path values about 5% lower than this table (see Reference 4).

References

1. Reid, R. C., Prausnitz, J. M., and Poling, B. E., *The Properties of Gases and Liquids, Fourth Edition*, McGraw-Hill, New York, 1987.
2. Lide, D. R., and Kehiaian, H. V., *CRC Handbook of Thermophysical and Thermochemical Data*, CRC Press, Boca Raton, FL, 1994.
3. Vargaftik, N. B., *Tables of Thermophysical Properties of Liquids and Gases, Second Edition*, John Wiley, New York, 1975.
4. Kaye, G. W. C., and Laby, T. H., *Tables of Physical and Chemical Constants, 15th Edition*, Longman, London, 1986.

Gas	d	l	$\bar{v}$	τ
Air	$3.66 \cdot 10^{-10}$ m	$6.91 \cdot 10^{-8}$ m	467 m/s	148 ps
Ar	3.58	7.22	397	182
CO_2	4.53	4.51	379	119
H_2	2.71	12.6	1769	71
He	2.15	20.0	1256	159
Kr	4.08	5.58	274	203
N_2	3.70	6.76	475	142
NH_3	4.32	4.97	609	82
Ne	2.54	14.3	559	256
O_2	3.55	7.36	444	166
Xe	4.78	4.05	219	185

INFLUENCE OF PRESSURE ON FREEZING POINTS

This table illustrates the variation of the freezing point of representative types of liquids with pressure. Substances are listed in alphabetical order. Note that 1 MPa = 0.01 kbar = 9.87 atm.

References

1. Isaacs, N. S., *Liquid Phase High Pressure Chemistry*, John Wiley, New York, 1981.
2. Merrill, L., *J. Phys. Chem. Ref. Data*, 6, 1205, 1977; 11, 1005, 1982.

Substance	Molecular formula	Freezing point in °C at: 0.1 MPa	100 MPa	1000 MPa
Acetic acid	$C_2H_4O_2$	16.6	37	
Acetophenone	C_8H_8O	20.0	41.2	
Aniline	C_6H_7N	–6.0	13.5	140
Benzene	C_6H_6	5.5	33.4	
Benzonitrile	C_7H_5N	–12.8	7.6	
Benzyl alcohol	C_7H_8O	–15.2	0.2	
Bromobenzene	C_6H_5Br	–30.6	–12	108
Bromoethane	C_2H_5Br	–118.6	–108	
1-Bromonaphthalene	$C_{10}H_7Br$	–1.8	6.1	
1-Bromopropane	C_3H_7Br	–110	–98	
p-Bromotoluene	C_7H_7Br	28.0	56.7	
Butanoic acid	$C_4H_8O_2$	–5.7	13.8	
1-Butanol	$C_4H_{10}O$	–89.8	–77.2	
Carbon disulfide	CS_2	–111.5	–98	
Chlorobenzene	C_6H_5Cl	–45.2	–28	84
p-Chlorotoluene	C_7H_7Cl	6.9	33.1	
o-Cresol	C_7H_8O	29.8	47.7	
m-Cresol	C_7H_8O	11.8	25.6	
p-Cresol	C_7H_8O	35.8	56.2	
Cyclohexane	C_6H_{12}	6.6	32.5	
Cyclohexanol	$C_6H_{12}O$	25.5	62.3	
1,2-Dibromoethane	$C_2H_4Br_2$	9.9	34.0	
p-Dichlorobenzene	$C_6H_4Cl_2$	52.7	79.1	
Dichloromethane	CH_2Cl_2	–95.1	–83	
N,N-Dimethylaniline	$C_8H_{11}N$	2.5	26.3	
1,4-Dioxane	$C_4H_8O_2$	11	23	
Ethanol	C_2H_6O	–114.1	–108	
Formamide	CH_3NO	–15.5	10.8	
Formic acid	CH_2O_2	8.3	20.6	
Furan	C_4H_4O	–85.6	–73	
Hexamethyldisiloxane	$C_6H_{18}OSi_2$	–66	–37	
Menthol	$C_{10}H_{20}O$	42	60	
Methyl benzoate	$C_8H_8O_2$	–15	31.8	
2-Methyl-2-butanol	$C_5H_{12}O$	–8.8	13.4	
2-Methyl-2-propanol	$C_4H_{10}O$	25.4	58.1	
Naphthalene	$C_{10}H_8$	78.2	115.7	
Nitrobenzene	$C_6H_5NO_2$	5.7	13.5	
m-Nitrotoluene	$C_7H_7NO_2$	15.5	40.6	
Pentachloroethane	C_2HCl_5	–29.0	–6.3	
Potassium	K	63.7	78	170
Potassium chloride	ClK	771		945
Propanoic acid	$C_3H_6O_2$	–20.7	–1.2	
Silver chloride	AgCl	455		545
Sodium	Na	97.8	106	167
Sodium chloride	ClNa	800.7		997
Sodium fluoride	FNa	996		1115
Tetrachloromethane	CCl_4	–23.0	14.2	
Tribromomethane	$CHBr_3$	8.1	31.5	
Trichloromethane	$CHCl_3$	–63.6	–45.2	
Water	H_2O	0.0	–9.0	
o-Xylene	C_8H_{10}	–25.2	–3.5	
m-Xylene	C_8H_{10}	–47.8	–25.2	
p-Xylene	C_8H_{10}	13.2	46.0	

CRITICAL CONSTANTS

The parameters of the liquid–gas critical point are important constants in determining the behavior of fluids. This table lists the critical temperature, pressure, and molar volume, as well as the normal boiling point, for approximately 850 inorganic and organic substances. The properties and their units are:

T_b: Normal boiling point in kelvins at a pressure of 101.325 kPa (1 atmosphere); an "s" following the value indicates a sublimation point (temperature at which the solid is in equilibrium with the gas at a pressure of 101.325 kPa)
T_c: Critical temperature in kelvins
P_c: Critical pressure in megapascals
V_c: Critical molar volume in cm^3/mol

The number of digits given for T_b, T_c, and P_c indicates the estimated accuracy of these quantities; however, values of T_c greater than 750 K may be in error by 10 K or more. Although most V_c values are given to three figures, they cannot be assumed accurate to better than a few percent. All values are experimentally determined except for a few values, indicated by an asterisk*, which are based on extrapolations. Methods of measurement are described and critiqued in Reference 1.

Many of the critical constants in this table are taken from reviews produced by the IUPAC Commission on Thermodynamics (References 1– 8). Compounds are listed by molecular formula in modified Hill order, with compounds not containing carbon preceding those that do contain carbon.

The assistance of Douglas Ambrose is gratefully acknowledged.

References

1. Ambrose, D., and Young, C. L., *J. Chem. Eng. Data,* 40, 345, 1995. [IUPAC Part 1]
2. Ambrose, D., and Tsonopoulos, C., *J. Chem. Eng. Data,* 40, 531, 1995. [IUPAC Part 2]
3. Tsonopoulos, C., and Ambrose, D., *J. Chem. Eng. Data*, 40, 547, 1995. [IUPAC Part 3]
4. Gude, M., and Teja, A. S., *J. Chem. Eng. Data*, 40, 1025, 1995. [IUPAC Part 4]
5. Daubert, T. E., *J. Chem. Eng. Data*, 41, 365, 1996. [IUPAC Part 5]
6. Tsonopoulos, C., and Ambrose, D., *J. Chem. Eng. Data*, 41, 645, 1996. [IUPAC Part 6]
7. Kudcharker, A. P., Ambrose, D., and Tsonopoulos, C., *J. Chem. Eng. Data*, 46, 457, 2001. [IUPAC Part 7]
8. Tsonopoulos, C., and Ambrose, D., *J. Chem. Eng. Data,* 46, 480, 2001. [IUPAC Part 8]
9. Ambrose, D., "Vapor-Liquid Constants of Fluids", in Stevenson, R. M., and Malanowski, S., Eds., *Handbook of the Thermodynamics of Organic Compounds*, Elsevier, New York, 1987.
10. Das, A., Frenkel, M., Gadalla, N. A. M., Kudchadker, S., Marsh, K. N., Rodgers, A. S., and Wilhoit, R. C., *J. Phys. Chem. Ref. Data*, 22, 659, 1993.
11. Wilson, L. C., Wilson, H. L., Wilding, W. V., and Wilson, G. M., *J. Chem. Eng. Data,* 41, 1252, 1996.
12. Daubert, T. E., Danner, R. P., Sibul, H. M., and Stebbins, C. C., *Physical and Thermodynamic Properties of Pure Compounds: Data Compilation*, extant 2002 (core with supplements), Taylor & Francis, Bristol, PA.
13. Morton, D. W., Lui, M. P. W., Tran, C. A., and Young, C. L., *J. Chem. Eng. Data,* 45, 437, 2000.
14. VonNiederhausern, D. M., Wilson, L. C., Giles, N. F., and Wilson, G. M., *J. Chem. Eng. Data*, 45, 154, 2000.
15. VonNiederhausern, D. M., Wilson, G. M., and Giles, N. F., *J. Chem. Eng. Data*, 45, 157, 2000.
16. Nikitin, E. D., Popov, A. P., Bogatishcheva, N. S., and Yatluk, Y. G., *J. Chem. Eng. Data,* 47, 1012, 2002.
17. Wilson, G. M., VonNiederhausern, D. M., and Giles, N. F., *J. Chem. Eng. Data,* 47, 761, 2002.
18. Wang, B. H., Adcock, J. L., Mathur, S. B., and Van Hook, W. A., *J. Chem. Thermodynamics,* 23, 699, 1991.
19. Chae, H. B., Schmidt, J. W., and Moldover, M. R., *J. Phys. Chem*., 94, 8840, 1990.
20. Dillon, I. G., Nelson, P. A., and Swanson, B. S., *J. Chem. Phys*., 44, 4229, 1966.
21. *Physical Constants of Hydrocarbon and Non-Hydrocarbon Compounds*, ASTM Data Series DS 4B, ASTM, Philadelphia, 1988.
22. Nowak, P., Tielkes, T., Kleinraum, R., and Wagner, W., *J. Chem. Thermodynamics,* 29, 885, 1997.
23. Steele, W. V., Chirico, R. D., Nguyen, A., and Knipmeyer, S. E., *J. Chem. Thermodynamics,* 27, 311, 1995
24. Duan, Y. Y., Shi, L., Zhu, M. S., and Han, L. Z., *J. Chem. Eng. Data,* 44, 501, 1999.
25. Weber, L. A., and Defibaugh, D. R., *J. Chem. Eng. Data,* 41, 382, 1996.
26. Duarte-Garza, H. A., Hwang, C. A., Kellerman, S. A., Miller, R. C., Hall, K. R., and Holste, J. C., *J. Chem. Eng. Data,* 42, 497, 1997.
27. Weber, L. A., and Defibaugh, D. R., *J. Chem. Eng. Data,* 41, 1477, 1996.
28. Fujiwara, K., Nakamura, S., and Noguchi, M., *J. Chem. Eng. Data,* 43, 55, 1998.
29. Widiatmo, J. V., Morimoto, Y., and Watanabe, K., *J. Chem. Eng. Data,* 47, 1246, 2002.
30. Duarte-Garza, H. A., Stouffer, C. E., Hall, K. R., Holste, J. C., Marsh, K. N., and Gammon, B. E., *J. Chem. Eng. Data,* 42, 745, 1997.
31. Nikitin, E. D., Pavlov, P. A., Popov, A. P., and Nikitina, H. E., *J. Chem. Thermodynamics,* 27, 945, 1995.
32. Sako, T., Sato, M., Nakazawa, N., Oowa, M., Yasumoto, M., Ito, H., and Yamashita, S., *J. Chem. Eng. Data,* 41, 802, 1996.
33. Zhang, H-L, Sato, H., and Watanabe, K., *J. Chem. Eng. Data,* 40, 1281, 1995.
34. Sifner, O., and Klomfar, J., *J. Phys. Chem. Ref. Data,* 23, 63, 1994.
35. Younglove, B. A., and McLinden, M. O., *J. Phys. Chem. Ref. Data,* 23, 731, 1994.
36. Tillner-Roth, R., and Baehr, H. D., *J. Phys. Chem. Ref. Data,* 23, 657, 1994.
37. Xiang, H. W., *J. Phys. Chem. Ref. Data,* 30, 1161, 2001.
38. Goodwin, A. H. R., Defibaugh, D. R., and Weber, L. A., *J. Chem. Eng. Data,* 43, 846, 1998.
39. Lim, J. S., Park, K. H., Lee, B. G., and Kim, J-D., *J. Chem. Eng. Data,* 46, 1580, 2001.
40. Linstrom, P. J., and Mallard, W. G., Eds., *NIST Chemistry WebBook*, NIST Standard Reference Database No. 69, July 2001, National Institute of Standards and Technology, Gaithersburg, MD 20899, http://webbook.nist.gov.
41. *ASHRAE Fundamentals Handbook 2001*, Chapter 19. Refrigerants, American Society of Heating, Refrigerating, and Air-Conditioning Engineers, Atlanta, GA, 2001.
42. Fialho, P. S., and Nieto de Castro, C. A., *Int. J. Thermophys.,* 21, 385, 2000.
43. Vargaftik, N. B., *Int. J. Thermophys*., 11, 467, 1990
44. Vargaftik, N.B., Vinogradov, Y. K., and Yargin, V. S., *Handbook of Physical Properties of Liquids and Gases, Third Edition*, Begell House, New York, 1996.
45. Schmidt, J. W., Carrillo-Nava, E., and Moldover, M. R., *Fluid Phase Equilibria*, 122, 187, 1996.
46. Defibaugh, D. R., Gillis, K. A., Moldover, M. R., Morrison, G., and Schmidt, J. W., *Fluid Phase Equilibria,* 81, 285, 1992.
47. Salvi-Narkhede, M., Wang, B-H., Adcock, J. L., and Van Hook, W. A., *J. Chem. Thermodynamics,* 24, 1065, 1992.

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
$AlBr_3$	Aluminum bromide	528	763	2.89	310	9
$AlCl_3$	Aluminum chloride	453 s	620	2.63	257	9
AlI_3	Aluminum iodide	655	983		408	9
Ar	Argon	87.30	150.87	4.898	75	9
As	Arsenic	876	1673		35	9
$AsCl_3$	Arsenic(III) chloride	403	654		252	9
AsH_3	Arsine	210.7	373.1			9
BBr_3	Boron tribromide	364	581		272	9
BCl_3	Boron trichloride	285.80	455	3.87	239	9
BF_3	Boron trifluoride	172	260.8	4.98	115	9
BI_3	Boron triiodide	482.7	773		356	9
B_2H_6	Diborane	180.8	289.8	4.05		9
$BiBr_3$	Bismuth tribromide	726	1220		301	9
$BiCl_3$	Bismuth trichloride	720	1179	12.0	261	9
BrH	Hydrogen bromide	206.77	363.2	8.55		9
BrI	Iodine bromide	389	719		139	9
Br_2	Bromine	332.0	588	10.34	127	9
Br_2Hg	Mercury(II) bromide	595	1012			9
Br_3Ga	Gallium(III) bromide	552	806.7		303	9
Br_3HSi	Tribromosilane	382	610.0		305	9
Br_3P	Phosphorus(III) bromide	446.4	711		300	9
Br_3Sb	Antimony(III) bromide	553	904		300	9
Br_4Ge	Germanium(IV) bromide	459.50	718		392	9
Br_4Hf	Hafnium(IV) bromide	596 s	746		415	9
Br_4Si	Tetrabromosilane	427	663		382	9
Br_4Sn	Tin(IV) bromide	478	744		417	9
Br_4Ti	Titanium(IV) bromide	503	795.7		391	9
Br_4Zr	Zirconium(IV) bromide	633 s	805		424	9
Br_5Ta	Tantalum(V) bromide	622	974		461	9
$ClFO_3$	Perchloryl fluoride	226.40	368.4	5.37	161	9
ClF_2N	Nitrogen chloride difluoride	206	337.5	5.15		9
ClF_2P	Phosphorus(III) chloride difluoride	225.9	362.4	4.52		9
ClF_2PS	Phosphorothioc chloride difluoride	279.5	439.2	4.14		9
ClF_3Si	Chlorotrifluorosilane	203.2	307.7	3.46		9
ClF_5	Chlorine pentafluoride	260.1	416	5.27	233	9
ClF_5S	Sulfur chloride pentafluoride	254.10	390.9			9
ClH	Hydrogen chloride	188	324.7	8.31	81	9
ClH_4N	Ammonium chloride	611 s	1155	163.5		9
ClH_4P	Phosphonium chloride	246 s	322.3	7.37		9
ClNO	Nitrosyl chloride	267.7	440			9
ClOV	Vanadyl chloride	400	636		171	9
Cl_2	Chlorine	239.11	416.9	7.991	123	9
Cl_2FP	Phosphorus(III) dichloride fluoride	287.00	463.0	4.96		9
Cl_2F_2Si	Dichlorodifluorosilane	241	369.0	3.5		9
Cl_2Hg	Mercury(II) chloride	577	973		174	9
Cl_2OSe	Selenium oxychloride	450	730	7.09	235	9
Cl_3FSi	Trichlorofluorosilane	285.40	438.6	3.58		9
Cl_3Ga	Gallium(III) chloride	474	694		263	9
Cl_3HSi	Trichlorosilane	306	479		268	9
Cl_3P	Phosphorus(III) chloride	349.3	563		264	9
Cl_3Sb	Antimony(III) chloride	493.5	794		272	9
Cl_4Ge	Germanium(IV) chloride	359.70	553.2	3.861	330	9
Cl_4Hf	Hafnium(IV) chloride	590 s	725.7	5.42	314	9
Cl_4ORe	Rhenium(VI) oxytetrachloride	496	781		362	9
Cl_4OW	Tungsten(VI) oxytetrachloride	500.70	782		338	9
Cl_4Si	Tetrachlorosilane	330.80	508.1	3.593	326	9
Cl_4Sn	Tin(IV) chloride	387.30	591.9	3.75	351	9
Cl_4Te	Tellurium tetrachloride	660	1002	8.56	310	9
Cl_4Ti	Titanium(IV) chloride	409.60	638	4.66	339	9
Cl_4Zr	Zirconium(IV) chloride	604 s	778	5.77	319	9

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
Cl_5Mo	Molybdenum(V) chloride	541	850		369	9
Cl_5Nb	Niobium(V) chloride	527.2	803.5	4.88	397	9
Cl_5P	Phosphorus(V) chloride	433 s	646			9
Cl_5Ta	Tantalum(V) chloride	512.50	767		402	9
Cl_6W	Tungsten(VI) chloride	619.90	923		422	9
Cs	Cesium	944	1938	9.4	341	43
FH	Hydrogen fluoride	293	461	6.48	69	9
FNO_2	Nitryl fluoride	200.8	349.5			9
F_2	Fluorine	85.03	144.13	5.172	66	9
F_2HN	Difluoramine	250	403			9
F_2N_2	*cis*-Difluorodiazine	167.40	272	7.09		9
F_2N_2	*trans*-Difluorodiazine	161.70	260	5.57		9
F_2O	Fluorine monoxide	128.40	215			9
F_2Xe	Xenon difluoride	387.50	631	9.32	148	9
F_3N	Nitrogen trifluoride	144.40	234.0	4.46	126	9
F_3NO	Trifluoramine oxide	185.7	303	6.43	147	9
F_3P	Phosphorus(III) fluoride	171.4	271.2	4.33		9
F_3PS	Phosphorothioc trifluoride	220.90	346.0	3.82		9
F_4N_2	Tetrafluorohydrazine	199	309	3.75		9
F_4S	Sulfur tetrafluoride	232.70	364			9
F_4Si	Tetrafluorosilane	187	259.0	3.72		9
F_4Xe	Xenon tetrafluoride	388.90	612	7.04	188	9
F_5Nb	Niobium(V) fluoride	502	737	6.28	155	9
F_6Mo	Molybdenum(VI) fluoride	307.2	473	4.75	226	9
F_6S	Sulfur hexafluoride	209.35	318.69	3.77	199	9
F_6Se	Selenium hexafluoride	226.55	345.5			9
F_6Te	Tellurium hexafluoride	234.25	356			9
F_6U	Uranium(VI) fluoride	329.65	505.8	4.66	250	9
F_6W	Tungsten(VI) fluoride	290.3	444	4.34	233	9
GaI_3	Gallium(III) iodide	613	951		395	9
GeH_4	Germane	185.1	312.2	4.95	147	9
GeI_4	Germanium(IV) iodide	650	973		500	9
HI	Hydrogen iodide	237.60	424.0	8.31		9
H_2	Hydrogen	20.28	32.97	1.293	65	9
H_2O	Water	373.2	647.14	22.06	56	9
H_2O_2	Hydrogen peroxide	423.4	728*	22*		31
H_2S	Hydrogen sulfide	213.60	373.2	8.94	99	9
H_2Se	Hydrogen selenide	231.90	411	8.92		9
H_3N	Ammonia	239.82	405.5	11.35	72	9
H_3P	Phosphine	185.40	324.5	6.54		9
H_4N_2	Hydrazine	386.70	653	14.7		9
He	Helium	4.22	5.19	0.227	57	9
HfI_4	Hafnium iodide	667 s	916		528	9
Hg	Mercury	629.88	1750	172.00	43	9
HgI_2	Mercury(II) iodide	627	1072			9
I_2	Iodine	457.6	819		155	9
I_3Sb	Antimony(III) iodide	674	1102			9
I_4Si	Tetraiodosilane	560.50	944		558	9
I_4Sn	Tin(IV) iodide	637.50	968		531	9
I_4Ti	Titanium(IV) iodide	650	1040		505	9
I_4Zr	Zirconium(IV) iodide	704 s	960		530	9
K	Potassium	1032	2223*	16*	209*	20
Kr	Krypton	119.93	209.41	5.50	91	9
Li	Lithium	1615	3223*	67*	66*	20
NO	Nitric oxide	121.41	180	6.48	58	9
N_2	Nitrogen	77.36	126.21	3.39	90	9
N_2O	Nitrous oxide	184.67	309.57	7.255	97	9
N_2O_4	Nitrogen tetroxide	294.30	431	10.1	167	9
Na	Sodium	1156	2573*	35*	116*	20
Ne	Neon	27.07	44.4	2.76	42	9

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
O_2	Oxygen	90.20	154.59	5.043	73	9
O_2S	Sulfur dioxide	263.10	430.8	7.884	122	9
O_3	Ozone	161.80	261.1	5.57	89	9
O_3S	Sulfur trioxide	318	491.0	8.2	127	9
O_4Os	Osmium(VIII) oxide	408	678			9
O_7Re_2	Rhenium(VII) oxide	633	942		334	9
P	Phosphorus	553.7	994			9
Rb	Rubidium	961	2093*	16*	247*	20
Rn	Radon	211.5	377	6.28		9
S	Sulfur	717.75	1314	20.7		9
Se	Selenium	958	1766	27.2		9
Xe	Xenon	165.03	289.77	5.841	118	34
$CBrClF_2$	Bromochlorodifluoromethane	269.5	426.88	4.254	246	9
$CBrF_3$	Bromotrifluoromethane	215.4	340.2	3.97	196	9
CBr_2F_2	Dibromodifluoromethane	295.91	471.3	4.45		9
$CClF_3$	Chlorotrifluoromethane	191.8	302	3.870	180	9
CCl_2F_2	Dichlorodifluoromethane	243.4	384.95	4.136	217	9
CCl_2O	Carbonyl chloride [Phosgene]	281	455	5.67	190	9
CCl_3F	Trichlorofluoromethane	296.9	471.1	4.47	247	18
CCl_4	Tetrachloromethane	350.0	556.6	4.516	276	9
CF_3I	Trifluoroiodomethane	250.7	396.44	3.953	226	24
CF_4	Tetrafluoromethane	145.2	227.6	3.74	140	9
$CHBrF_2$	Bromodifluoromethane	258.6	411.98	5.132	275	47
$CHClF_2$	Chlorodifluoromethane	232.5	369.5	5.035	164	18
$CHCl_2F$	Dichlorofluoromethane	282.1	451.58	5.18	196	9
$CHCl_3$	Trichloromethane	334.32	536.4	5.47	239	9
CHF_3	Trifluoromethane	191.1	298.98	4.82	133	42
CHN	Hydrogen cyanide	299	456.7	5.39	139	9
CH_2ClF	Chlorofluoromethane	264.1	427	5.70		37
CH_2Cl_2	Dichloromethane	313	510	6.10		9
CH_2F_2	Difluoromethane	221.6	351.56	5.83	123	42
CH_2O_2	Formic acid	374	588			7
CH_3Cl	Chloromethane	249.06	416.25	6.679	139	9
CH_3Cl_3Si	Methyltrichlorosilane	338.8	517	3.28	348	9
CH_3F	Fluoromethane	194.8	317.8	5.88	113	9
CH_3I	Iodomethane	315.58	528			9
CH_3NO_2	Nitromethane	374.34	588	5.87	173	9
CH_4	Methane	111.67	190.56	4.599	98.60	2
CH_4O	Methanol	337.8	512.5	8.084	117	4
CH_4S	Methanethiol	279.1	470	7.23	147	8
CH_5ClSi	Chloromethylsilane	280	517.8			9
CH_5N	Methylamine	266.83	430.7	7.614		9
CH_6N_2	Methylhydrazine	360.7	567	8.24	271	9
CH_6Si	Methylsilane	215.7	352.4			8
CO	Carbon monoxide	81.7	132.91	3.499	93	9
COS	Carbon oxysulfide	223	375	5.88	137	9
CO_2	Carbon dioxide	194.6 s	304.13	7.375	94	22
CS_2	Carbon disulfide	319	552	7.90	173	9
$C_2Br_2ClF_3$	1,2-Dibromo-1-chloro-1,2,2-trifluoroethane	366	560.7	3.61	368	9
$C_2Br_2F_4$	1,2-Dibromotetrafluoroethane	320.50	487.8	3.393	341	9
C_2ClF_3	Chlorotrifluoroethene	245.4	379	4.05	212	9
C_2ClF_5	Chloropentafluoroethane	234.1	353.2	3.229	252	9
$C_2Cl_2F_4$	1,1-Dichloro-1,2,2,2-tetrafluoroethane	276.6	418.6	3.30	294	9
$C_2Cl_2F_4$	1,2-Dichloro-1,1,2,2-tetrafluoroethane	276.7	418.78	3.252	297	42
$C_2Cl_3F_3$	1,1,1-Trichloro-2,2,2-trifluoroethane	318.7	482.9			40
$C_2Cl_3F_3$	1,1,2-Trichloro-1,2,2-trifluoroethane	320.9	487.3	3.42	325	9
C_2Cl_4	Tetrachloroethene	394.5	620.2			9
$C_2Cl_4F_2$	1,1,2,2-Tetrachloro-1,2-difluoroethane	366.0	551			9
C_2Cl_6	Hexachloroethane	457.85	695	3.34*	412*	12
C_2F_3N	Trifluoroacetonitrile	204.4	311.11	3.618	202	9

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
C_2F_4	Tetrafluoroethene	197.3	306.5	3.94	172	9
C_2F_6	Hexafluoroethane	195.1	293		222	9
C_2HClF_2	1-Chloro-2,2-difluoroethene	254.7	400.6	4.46	197	9
C_2HClF_4	1-Chloro-1,1,2,2-tetrafluoroethane	261.5	399.9	3.72	244	9
C_2HClF_4	1-Chloro-1,2,2,2-tetrafluoroethane	261	395.65	3.643	244	42
$C_2HCl_2F_3$	1,2-Dichloro-1,1,2-trifluoroethane	302.7	461.6		278	19
$C_2HCl_2F_3$	2,2-Dichloro-1,1,1-trifluoroethane	300.97	456.83	3.661	278	35
C_2HCl_3	Trichloroethene	360.36	544.2	5.02		9
$C_2HF_3O_2$	Trifluoroacetic acid	346	491.3	3.258	204	9
C_2HF_5	Pentafluoroethane	225.1	339.17	3.620	208.0	29,30
C_2HF_5O	Trifluoromethyl difluoromethyl ether	235	354.0	3.33	192	25,45,46
C_2H_2	Acetylene	188.45	308.3	6.138	112.2	6
$C_2H_2ClF_3$	2-Chloro-1,1,1-trifluoroethane	279.3	425.01		228	40
$C_2H_2Cl_2$	*cis*-1,2-Dichloroethene	333.3	544.2			9
$C_2H_2Cl_2$	*trans*-1,2-Dichloroethene	321.9	516.5	5.51		9
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane	418.4	661.15			9
$C_2H_2F_2$	1,1-Difluoroethene	187.5	302.9	4.46	154	9
$C_2H_2F_4$	1,1,1,2-Tetrafluoroethane	247.07	374.18	4.065	198	36
$C_2H_2F_4$	1,1,2,2-Tetrafluoroethane	253.3	391.74	4.615	191	19,42
$C_2H_2F_4O$	Bis(difluoromethyl) ether	275	420.25	4.228	223	46
C_2H_3Cl	Chloroethene [Vinyl chloride]	259.4	432	5.67	179	12
$C_2H_3ClF_2$	1-Chloro-1,1-difluoroethane	264.1	410.34	4.048	225	19,32
$C_2H_3Cl_2F$	1,1-Dichloro-1-fluoroethane	305.2	477.5	4.194	255	26,42
$C_2H_3Cl_3$	1,1,1-Trichloroethane	347.24	545	4.30		9
$C_2H_3Cl_3$	1,1,2-Trichloroethane	387.0	602*	4.48*	281*	12
C_2H_3F	Fluoroethene	201	327.9	5.24	144	9
$C_2H_3F_3$	1,1,1-Trifluoroethane	225.90	345.86	3.764	194	27,28
$C_2H_3F_3$	1,1,2-Trifluoroethane	276.9	429.8	5.241	207	40
$C_2H_3F_3O$	Methyl trifluoromethyl ether	249.49	378.02	3.588	228	47
C_2H_3N	Acetonitrile	354.80	545.6	4.884	173	14
C_2H_4	Ethylene [Ethene]	169.38	282.34	5.041	131	6
$C_2H_4Br_2$	1,2-Dibromoethane	404.8	583.0	7.2		9
$C_2H_4Cl_2$	1,1-Dichloroethane	330.5	523	5.07	236	9
$C_2H_4Cl_2$	1,2-Dichloroethane	356.7	561	5.4	225	9
$C_2H_4F_2$	1,1-Difluoroethane	249.10	386.7	4.50	181	9,19
C_2H_4O	Acetaldehyde	293.3	466		154	7
C_2H_4O	Oxirane [Ethylene oxide]	283.8	469	7.2	142	7
$C_2H_4O_2$	Acetic acid	391.1	590.7	5.78	171	7
$C_2H_4O_2$	Methyl formate	304.9	487.2	6.00	172	7
C_2H_5Br	Bromoethane	311.7	503.9	6.23	215	9
C_2H_5Cl	Chloroethane	285.5	460.4	5.3		9
C_2H_5F	Fluoroethane	235.5	375.31	5.028		9
C_2H_6	Ethane	184.6	305.32	4.872	145.5	2
$C_2H_6Cl_2Si$	Dichlorodimethylsilane	343.5	520.4	3.49	350	9
C_2H_6O	Ethanol	351.44	514.0	6.137	168	4
C_2H_6O	Dimethyl ether	248.4	400.2	5.34	168	7
$C_2H_6O_2$	1,2-Ethanediol	470.5	720	8		7,14
C_2H_6S	Ethanethiol	308.2	499	5.49	207	8
C_2H_6S	Dimethyl sulfide	310.48	503	5.53	203.7	8
$C_2H_6S_2$	Dimethyl disulfide	382.89	615			8
C_2H_7N	Ethylamine	289.7	456	5.62	182	9
C_2H_7N	Dimethylamine	280.03	437.22	5.340		9
$C_2H_8N_2$	1,2-Ethanediamine	390	613.1	6.707		11,12
C_2N_2	Cyanogen	252.1	400	5.98		9
C_3ClF_5O	Chloropentafluoroacetone	281	410.6	2.878		9
$C_3Cl_2F_6$	1,3-Dichloro-1,1,2,2,3,3-hexafluoropropane	308.9	453	2.753		41
C_3F_6O	Perfluoroacetone	245.8	357.14	2.84	329	9
C_3F_6O	Perfluorooxetane	244.8	361.8	3.03	272	18,47
C_3F_8	Perfluoropropane	236.6	345.1	2.680	299	9
$C_3F_8O_2$	Perfluorodimethoxymethane	263	372.3	2.333	363	18

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
C_3HF_7	1,1,1,2,3,3,3-Heptafluoropropane	256.8	374.89	2.929	274	39,47
C_3HF_7O	Trifluoromethyl 1,1,2,2-tetrafluoroethyl ether	270	387.78	2.293	337	18,47
$C_3H_2F_6$	1,1,1,2,3,3-Hexafluoropropane	279.3	412.38	3.412	269	33
$C_3H_2F_6$	1,1,1,3,3,3-Hexafluoropropane	272.2	398.07			45
$C_3H_2F_6O$	1,2,2,2-Tetrafluoroethyl difluoromethyl ether	296.50	428.95	3.050	315	32
$C_3H_3F_3$	3,3,3-Trifluoropropene	256	376.2	3.80	211	9
$C_3H_3F_5$	1,1,1,3,3-Pentafluoropropane	288.5	427.20			45
$C_3H_3F_5$	1,1,1,2,2-Pentafluoropropane	255.8	380.11	3.137	273	9
$C_3H_3F_5$	1,1,2,2,3-Pentafluoropropane	298.2	447.57			45
$C_3H_3F_5O$	Methyl pentafluoroethyl ether	278.74	406.80	2.887	301	32
$C_3H_3F_5O$	Difluoromethyl 2,2,2-trifluoroethyl ether	302.39	443.99			38
C_3H_3N	Acrylonitrile	350.5	540	4.660		11,12
C_3H_3NO	Isoxazole	368	552.0			9
C_3H_4	Allene	238.8	394	5.25		6
C_3H_4	Propyne	250.0	402.4	5.63	163.5	6
C_3H_5Cl	3-Chloropropene	318.3	514			9
$C_3H_5F_3O$	2,2,2-Trifluoroethyl methyl ether	304.77	448.98	3.513	277	32
C_3H_5N	Propanenitrile	370.29	561.3	4.26	229	9
C_3H_6	Propene	225.46	364.9	4.60	185	6
C_3H_6	Cyclopropane	240.34	398.0	5.54	162	5
$C_3H_6Cl_2$	1,2-Dichloropropane	369.6	578.5			13
$C_3H_6Cl_2$	1,3-Dichloropropane	394.1	614.6			13
C_3H_6O	Allyl alcohol	370.2	545.1			4
C_3H_6O	Propanal	321	505	5.26	204	7
C_3H_6O	Acetone	329.20	508.1	4.700	213	7
C_3H_6O	Methyloxirane [1,2-Propylene oxide]	308	485	5.2	190	7
$C_3H_6O_2$	Propanoic acid	414.30	598.5	4.67	233	7
$C_3H_6O_2$	Ethyl formate	327.6	508.54	4.74	229	7
$C_3H_6O_2$	Methyl acetate	330.02	506.5	4.750	228	7
$C_3H_6O_3$	Dimethyl carbonate	363.7	557	4.80	252	7
C_3H_7Cl	1-Chloropropane	319.7	503	4.58		9
C_3H_7Cl	2-Chloropropane	308.9	484			13
C_3H_7NO	*N,N*-Dimethylformamide	426	649.6		262	9
C_3H_8	Propane	231.1	369.83	4.248	200	2
C_3H_8O	1-Propanol	370.4	536.8	5.169	218	4
C_3H_8O	2-Propanol	355.5	508.3	4.764	222	4
C_3H_8O	Ethyl methyl ether	280.6	437.9	4.38	222	7
$C_3H_8O_2$	1,2-Propylene glycol	460.8	676.4	5.941		7,14
$C_3H_8O_2$	1,3-Propylene glycol [Trimethylene glycol]	487.6	718.2	6.55		14,17
$C_3H_8O_2$	2-Methoxyethanol [Ethylene glycol monomethyl ether]	397.3	597.6	5.285	263	7,11,12
$C_3H_8O_2$	Dimethoxymethane [Methylal]	315	491	3.96	213	7
$C_3H_8O_3$	Glycerol	563	850	7.5		7
C_3H_8S	1-Propanethiol	341.0	537	4.6	286	8
C_3H_8S	Ethyl methyl sulfide	339.9	533	4.25		8
$C_3H_9BO_3$	Trimethyl borate	340.7	501.7	3.59		9
C_3H_9ClSi	Trimethylchlorosilane	333	497.8	3.20	366	9
C_3H_9N	Propylamine	320.37	497.0	4.72		9
C_3H_9N	Isopropylamine	304.91	471.8	4.54	221	9
C_3H_9N	Trimethylamine	276.02	432.79	4.087	254	9
$C_4Br_2F_8$	1,4-Dibromooctafluorobutane	370	532.5	2.39		9
$C_4Cl_2F_6$	1,2-Dichloro-1,2,3,3,4,4-hexafluorocyclobutane	332.7	497*	2.73*	386*	12
C_4F_8	Perfluorocyclobutane	267.3	388.46	2.784	324	9
C_4F_{10}	Perfluorobutane	271.3	386.4	2.323	378	9
C_4F_{10}	Perfluoroisobutane	273	395.4			9
$C_4H_2F_8O$	Perfluoroethyl 2,2,2-trifluoroethyl ether	301.04	421.68	2.330	409	32
$C_4H_3F_7O$	Perfluoropropyl methyl ether	307.38	437.70	2.481	377	32
$C_4H_3F_7O$	Perfluoroisopropyl methyl ether	302.49	433.30	2.553	369	32
C_4H_4O	Furan	304.7	490.2	5.3	218	7
$C_4H_4O_4$	Maleic acid		620			7
C_4H_4S	Thiophene	357.2	580	5.70	219	8

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
$C_4H_5F_5O$	Perfluoroethyl ethyl ether	301.26	431.23	2.533	366	32
C_4H_5N	Pyrrole	402.94	639.7	6.34	200	10
C_4H_6	1,3-Butadiene	268.74	425	4.32	221	6
C_4H_6	1-Butyne	281.23	440	4.60	208	6
C_4H_6	2-Butyne	300.1	488.7			9
$C_4H_6O_2$	Vinyl acetate	346.0	519.2	4.185		7
$C_4H_6O_2$	γ-Butyrolactone	477	731	5.13		7,11
$C_4H_6O_3$	Acetic anhydride	412.7	606	4.0		7
$C_4H_6O_3$	Propylene carbonate	515	762.7	4.14		17
C_4H_7N	Butanenitrile	390.8	585.4	3.88		9
C_4H_8	1-Butene	266.89	419.5	4.02	240.8	6
C_4H_8	*cis*-2-Butene	276.86	435.5	4.21	233.8	6
C_4H_8	*trans*-2-Butene	274.03	428.6	4.10	237.7	6
C_4H_8	Isobutene	266.3	417.9	4.000	238.8	6
C_4H_8	Cyclobutane	285.8	460.0	4.98	210	9
C_4H_8O	Ethyl vinyl ether	308.7	475	4.07		7
C_4H_8O	Butanal	348.0	537	4.32	258	7
C_4H_8O	Isobutanal	337.7	544	5.1		7
C_4H_8O	2-Butanone [Methyl ethyl ketone]	352.74	536.7	4.207	267	7
C_4H_8O	Tetrahydrofuran	338	540.5	5.19	224	7
C_4H_8OS	*S*-Ethyl thioacetate	389.6	590.55	4.075	319	11,12
$C_4H_8O_2$	Butanoic acid	436.90	615.2	4.06	292	7
$C_4H_8O_2$	2-Methylpropanoic acid	427.60	605.0	3.70	290	7
$C_4H_8O_2$	Propyl formate	354.1	538.0	4.06	285	7
$C_4H_8O_2$	Isopropyl formate	341.4	535	3.95		7
$C_4H_8O_2$	Ethyl acetate	350.26	523.3	3.87	286	7
$C_4H_8O_2$	Methyl propanoate	353.0	530.7	4.00	282	7
$C_4H_8O_2$	1,4-Dioxane	374.7	588	5.21	238	7
C_4H_8S	Tetrahydrothiophene	394.3	632	5.4		8
C_4H_9Cl	1-Chlorobutane	351.6	539.2			13
C_4H_9Cl	2-Chlorobutane	341.4	518.6			13
C_4H_9Cl	2-Chloro-2-methylpropane	324.1	500			13
C_4H_9N	Pyrrolidine	359.71	568	6.00	238	10
C_4H_{10}	Butane	272.7	425.12	3.796	255	2
C_4H_{10}	Isobutane	261.42	407.8	3.640	259	5
$C_4H_{10}O$	1-Butanol	390.88	563.0	4.414	274	4
$C_4H_{10}O$	2-Butanol [sec-Butyl alcohol]	372.66	536.2	4.202	269	4
$C_4H_{10}O$	2-Methyl-1-propanol [Isobutyl alcohol]	381.04	547.8	4.295	274	4
$C_4H_{10}O$	2-Methyl-2-propanol [tert-Butyl alcohol]	355.6	506.2	3.972	275	4
$C_4H_{10}O$	Diethyl ether	307.7	466.7	3.644	281	7
$C_4H_{10}O$	Methyl propyl ether	312.3	476.2	3.801		7
$C_4H_{10}O$	Isopropyl methyl ether	303.92	464.4	3.762		7
$C_4H_{10}O_2$	2-Methyl-1,3-propanediol	484.8	708.0	5.35		17
$C_4H_{10}O_2$	1,2-Butanediol	463.7	680	5.21	303	7,23
$C_4H_{10}O_2$	1,3-Butanediol	480.7	676	4.02	305	7,23
$C_4H_{10}O_2$	1,4-Butanediol [Tetramethylene glycol]	508	723.8	5.52		17
$C_4H_{10}O_2$	1,2-Dimethoxyethane [Ethylene glycol dimethyl ether]	357.7	540	3.90	308	7
$C_4H_{10}O_2$	1,2-Propylene glycol monomethyl ether	392	579.8	4.113		11,12
$C_4H_{10}O_3$	Diethylene glycol	519.0	750	4.7		7
$C_4H_{10}S$	1-Butanethiol	371.7	570	4.0	324	8
$C_4H_{10}S$	Diethyl sulfide	365.3	557.8	3.90	317.6	8,15
$C_4H_{10}S_2$	Diethyl disulfide	427.2	642			8
$C_4H_{11}N$	Butylamine	350.15	531.9	4.25	277	10
$C_4H_{11}N$	*sec*-Butylamine	335.88	514.3	4.20	278	10
$C_4H_{11}N$	*tert*-Butylamine	317.19	483.9	3.84	292	10
$C_4H_{11}N$	Isobutylamine	340.90	519	4.07	278	10
$C_4H_{11}N$	Diethylamine	328.7	499.99	3.758		9
$C_4H_{12}N_2O$	*N*-(2-Aminoethyl)ethanolamine	512	739.2	4.65		17
$C_4H_{12}Si$	Tetramethylsilane	299.8	448.6	2.821	361.6	8
$C_4H_{12}Sn$	Tetramethylstannane	351	521.8	2.981		8

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
$C_4H_{13}N_3$	Bis(2-aminoethyl)amine	480	709.8	4.38		14,17
C_5F_{12}	Perfluoropentane	302.4	420.59	2.045	473	9
$C_5H_2F_6O_2$	Hexafluoroacetylacetone	327.30	485.1	2.767		9
$C_5H_4O_2$	Furfural	434.9	670*	5.89*		7
C_5H_5N	Pyridine	388.38	620.0	5.67	243	10
$C_5H_6N_2$	2-Methylpyrazine	410	634.3	5.01	283	9
C_5H_6O	2-Methylfuran	337.9	528	4.7	247	7
C_5H_7N	1-Methylpyrrole	385.96	596.0	4.86	271	10
C_5H_7N	2-Methylpyrrole	420.8	654	5.08	266	10
C_5H_7N	3-Methylpyrrole	416.1	647	5.08	266	10
C_5H_8	1-Pentyne	313.3	493.5			9
C_5H_8	Cyclopentene	317.4	506.5	4.80	245	6
C_5H_8O	Cyclopentanone	403.72	624	4.60		7
C_5H_8O	3,4-Dihydro-2*H*-pyran	359	562	4.56	268	7
C_5H_9N	Pentanenitrile	414.5	610.3	3.58		9
C_5H_9NO	*N*-Methyl-2-pyrrolidone	475	721.8		311	9
C_5H_{10}	1-Pentene	303.11	464.8	3.56	298.4	6
C_5H_{10}	*cis*-2-Pentene	310.08	475	3.69		6
C_5H_{10}	*trans*-2-Pentene	309.49	471	3.52		9
C_5H_{10}	2-Methyl-1-butene	304.4	470	3.8		9
C_5H_{10}	3-Methyl-1-butene	293.3	452.7	3.53	304.9	6
C_5H_{10}	2-Methyl-2-butene	311.71	470	3.42		6
C_5H_{10}	Cyclopentane	322.5	511.7	4.51	259	5
$C_5H_{10}O$	Cyclopentanol	413.57	619.5	4.9		4
$C_5H_{10}O$	Allyl ethyl ether	340.8	518			7
$C_5H_{10}O$	Pentanal	376	567	3.97	313	7
$C_5H_{10}O$	2-Pentanone [Methyl propyl ketone]	375.41	561.1	3.683	321	7
$C_5H_{10}O$	3-Pentanone [Diethyl ketone]	374.9	561.4	3.729	331	7
$C_5H_{10}O$	3-Methyl-2-butanone	367.48	553.0	3.80	308	7
$C_5H_{10}O$	Tetrahydropyran	361	572	4.77	263	7
$C_5H_{10}O$	2-Methyltetrahydrofuran	351	537	3.76	267	7
$C_5H_{10}O_2$	Pentanoic acid	459.3	637.2	3.63	346	7
$C_5H_{10}O_2$	3-Methylbutanoic acid	449.7	629	3.40		7
$C_5H_{10}O_2$	Isobutyl formate	371.4	551	3.88	355	7
$C_5H_{10}O_2$	Propyl acetate	374.69	549.7	3.36	345	7
$C_5H_{10}O_2$	Isopropyl acetate	361.8	531.0	3.31	344	7
$C_5H_{10}O_2$	Ethyl propanoate	372.3	546.7	3.45	342	7
$C_5H_{10}O_2$	Methyl butanoate	376.0	554.5	3.47	340	7
$C_5H_{10}O_2$	Methyl isobutanoate	365.7	540.7	3.43	339	7
$C_5H_{10}O_3$	2-Methoxyethyl acetate	416	630.0			7
$C_5H_{11}Cl$	1-Chloropentane	381.6	571.2			13
$C_5H_{11}Cl$	2-Chloro-2-methylbutane	358.8	509.1			13
$C_5H_{11}N$	Piperidine	379.37	594	4.94	288	10
C_5H_{12}	Pentane	309.21	469.7	3.370	311	2
C_5H_{12}	Isopentane	301.03	460.4	3.38	306	5
C_5H_{12}	Neopentane	282.63	433.8	3.196	307	5
$C_5H_{12}O$	1-Pentanol	411.13	588.1	3.897	326	4
$C_5H_{12}O$	2-Pentanol	392.5	560.3	3.675	329	4
$C_5H_{12}O$	3-Pentanol	389.40	559.6		325	4
$C_5H_{12}O$	2-Methyl-1-butanol	400.7	575.4	3.94		4
$C_5H_{12}O$	3-Methyl-1-butanol	404.3	577.2	3.93		4
$C_5H_{12}O$	2-Methyl-2-butanol	375.6	543.7	3.71		4
$C_5H_{12}O$	3-Methyl-2-butanol	386.1	556.1	3.87		4
$C_5H_{12}O$	Butyl methyl ether	343.31	512.7	3.37	329	7
$C_5H_{12}O$	Methyl *tert*-butyl ether	328.2	497.1	3.430		7
$C_5H_{12}O$	Ethyl propyl ether	336.36	500.2	3.370	339	7
$C_5H_{12}O_2$	2-Propoxyethanol	423.0	615	3.65	364	7
$C_5H_{12}O_2$	Diethoxymethane	361	531.7			7
$C_5H_{12}O_2$	1,2-Dimethoxypropane	369	543.0			7
$C_5H_{12}O_2$	2,2-Dimethoxypropane	356	510			7

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
$C_5H_{12}O_3$	Diethylene glycol monomethyl ether	466	672	3.67		11,12
$C_5H_{12}S$	3-Methyl-1-butanethiol	389	594			8
C_6BrF_5	Bromopentafluorobenzene	410	601	3.0		9
C_6ClF_5	Chloropentafluorobenzene	391.11	570.81	3.238	376	9
$C_6Cl_2F_4$	1,2-Dichloro-3,4,5,6-tetrafluorobenzene	430.9	626	5.32		9
$C_6Cl_3F_3$	1,3,5-Trichloro-2,4,6-trifluorobenzene	471.6	684.8	3.27	448	9
C_6F_6	Hexafluorobenzene	353.41	516.73	3.273	335	9
C_6F_{10}	Perfluorocyclohexene	325.2	461.8			9
C_6F_{12}	Perfluoro-1-hexene	330.2	454.4			9
C_6F_{12}	Perfluorocyclohexane	325.95	457.2	2.43		9
C_6F_{14}	Perfluorohexane	329.8	448.77	1.868	606	9
C_6F_{14}	Perfluoro-2-methylpentane	330.8	455.3	1.923	532	9
C_6F_{14}	Perfluoro-3-methylpentane	331.6	450	1.69		9
C_6F_{14}	Perfluoro-2,3-dimethylbutane	333.0	463	1.87	525	9
C_6HF_5	Pentafluorobenzene	358.89	530.97	3.531	324	9
C_6HF_5O	Pentafluorophenol	418.8	609	4.0	348	9
C_6HF_{11}	Undecafluorocyclohexane	335.2	477.7			9
$C_6H_2F_4$	1,2,3,4-Tetrafluorobenzene	367.5	550.83	3.791	313	9
$C_6H_2F_4$	1,2,3,5-Tetrafluorobenzene	357.6	535.25	3.747		9
$C_6H_2F_4$	1,2,4,5-Tetrafluorobenzene	363.4	543.35	3.801		9
$C_6H_3ClF_2$	1-Chloro-2,4-difluorobenzene	400	609.6			13
$C_6H_3ClF_2$	1-Chloro-2,5-difluorobenzene	401	612.5			13
$C_6H_3ClF_2$	1-Chloro-3,4-difluorobenzene	400	609.2			13
$C_6H_3ClF_2$	1-Chloro-3,5-difluorobenzene	391.7	592.0			13
$C_6H_3F_3$	1,2,3-Trifluorobenzene	368	560.3			13
$C_6H_3F_3$	1,2,4-Trifluorobenzene	363	551.1			13
$C_6H_3F_3$	1,3,5-Trifluorobenzene	348.7	530.9			13
C_6H_4BrF	1-Bromo-2-fluorobenzene	427	669.6			13
C_6H_4BrF	1-Bromo-3-fluorobenzene	423	652.0			13
C_6H_4BrF	1-Bromo-4-fluorobenzene	424.7	654.8			13
C_6H_4ClF	1-Chloro-2-fluorobenzene	410.8	633.8			13
C_6H_4ClF	1-Chloro-3-fluorobenzene	400.8	615.9			13
C_6H_4ClF	1-Chloro-4-fluorobenzene	403	620.1			13
$C_6H_4Cl_2$	*m*-Dichlorobenzene	446	685.7			13
$C_6H_4F_2$	*o*-Difluorobenzene	367	566.0			13
$C_6H_4F_2$	*m*-Difluorobenzene	355.8	548.4			13
$C_6H_4F_2$	*p*-Difluorobenzene	362	556.9	4.40		9,13
C_6H_5Br	Bromobenzene	429.21	670	4.52	324	9
C_6H_5Cl	Chlorobenzene	404.87	633.4	4.52	308	9,13
C_6H_5F	Fluorobenzene	357.88	560.09	4.551	269	9
C_6H_5I	Iodobenzene	461.6	721	4.52	351	9
C_6H_6	Benzene	353.24	562.05	4.895	256	3
C_6H_6O	Phenol	455.02	694.2	5.93		7
C_6H_7N	Aniline	457.32	699	4.89	287	9
C_6H_7N	2-Methylpyridine [2-Picoline]	402.53	621.0	4.60	292	10
C_6H_7N	3-Methylpyridine [3-Picoline]	417.29	645.0	4.65	288	10
C_6H_7N	4-Methylpyridine [4-Picoline]	418.51	645.7	4.70	292	10
C_6H_{10}	1,5-Hexadiene	332.6	508			6
C_6H_{10}	Cyclohexene	356.13	560.4			6
$C_6H_{10}O$	Cyclohexanone	428.58	665	4.6		7
$C_6H_{10}O$	2-Methylcyclopentanone	412.7	631			7
$C_6H_{10}O$	Mesityl oxide	403	605	4.00	353	7
$C_6H_{10}O_2$	Ethyl *trans*-2-butenoate	411	599			7
$C_6H_{10}S$	Diallyl sulfide	411.8	653			8
$C_6H_{11}Cl$	Chlorocyclohexane	415	586			13
$C_6H_{11}N$	Hexanenitrile	436.80	633.8	3.30		9
C_6H_{12}	1-Hexene	336.63	504.0	3.21	355.1	6
C_6H_{12}	Cyclohexane	353.88	553.8	4.08	308	5
C_6H_{12}	Methylcyclopentane	345.0	532.7	3.79	318	5
$C_6H_{12}O$	Butyl vinyl ether	367	540	3.20	384	7

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
$C_6H_{12}O$	Hexanal	404	592	3.46	378	7
$C_6H_{12}O$	2-Hexanone [Butyl methyl ketone]	400.8	587.1	3.30	377	7
$C_6H_{12}O$	3-Hexanone [Ethyl propyl ketone]	396.7	583.0	3.320	378	7
$C_6H_{12}O$	4-Methyl-2-pentanone [Isobutyl methyl ketone]	389.7	574.6	3.270		7
$C_6H_{12}O$	3,3-Dimethyl-2-butanone	379.3	570.9	3.43	382	7
$C_6H_{12}O$	Cyclohexanol	433.99	647.1	4.401		11,12
$C_6H_{12}O_2$	Hexanoic acid	478.4	655	3.38	413	7
$C_6H_{12}O_2$	Pentyl formate	403.6	576	3.46	412	7
$C_6H_{12}O_2$	Isopentyl formate	396.7	578			7
$C_6H_{12}O_2$	Butyl acetate	399.3	575.6	3.14		7
$C_6H_{12}O_2$	*sec*-Butyl acetate	385	571	3.01		7
$C_6H_{12}O_2$	Isobutyl acetate	389.7	561	2.99	401	7
$C_6H_{12}O_2$	Propyl propanoate	395.7	570	3.06		7
$C_6H_{12}O_2$	Ethyl butanoate	394.5	568.8	3.1	415	7
$C_6H_{12}O_2$	Ethyl 2-methylpropanoate	383.3	554	3.1	415	7
$C_6H_{12}O_2$	Methyl pentanoate	400.6	590	3.20	422	7
$C_6H_{12}O_3$	1,2-Propylene glycol monomethyl ether acetate	420	597.8	3.01	432	7
$C_6H_{12}O_3$	2-Ethoxyethyl acetate	429.6	608.0	3.17	443	7,23
$C_6H_{12}O_3$	Paraldehyde	397.5	563			7
$C_6H_{12}S$	Cyclohexanethiol	432.0	684		401	8
$C_6H_{13}Cl$	1-Chlorohexane	408.3	599			13
$C_6H_{13}Cl$	3-Chloro-3-methylpentane	389	528			13
C_6H_{14}	Hexane	341.88	507.6	3.025	368	2
C_6H_{14}	2-Methylpentane	333.41	497.7	3.04	368	5
C_6H_{14}	3-Methylpentane	336.42	504.6	3.12	368	5
C_6H_{14}	2,2-Dimethylbutane	322.88	489.0	3.10	358	5
C_6H_{14}	2,3-Dimethylbutane	331.08	500.0	3.15	361	5
$C_6H_{14}O$	2-Methoxy-2-methylbutane	359.3	535	3.20	374	7
$C_6H_{14}O$	1-Hexanol	430.8	610.3	3.417	387	4
$C_6H_{14}O$	2-Hexanol	413	585.9	3.31	384	4
$C_6H_{14}O$	3-Hexanol	408	582.4	3.36	383	4
$C_6H_{14}O$	2-Methyl-1-pentanol	422	604.4	3.45		4
$C_6H_{14}O$	4-Methyl-1-pentanol	425.1	603.5			4
$C_6H_{14}O$	2-Methyl-2-pentanol	394.3	559.5			4
$C_6H_{14}O$	4-Methyl-2-pentanol	404.8	574.4			4
$C_6H_{14}O$	2-Methyl-3-pentanol	399.7	576.0	3.46		4
$C_6H_{14}O$	3-Methyl-3-pentanol	395.6	575.6	3.52		4
$C_6H_{14}O$	Dipropyl ether	363.23	530.6	3.028		7
$C_6H_{14}O$	Diisopropyl ether	341.6	500.3	2.832	386	7
$C_6H_{14}O$	*tert*-Butyl ethyl ether	345.8	509.4	2.934	395	7
$C_6H_{14}O$	Methyl pentyl ether	372	546.5	3.042	391	7
$C_6H_{14}O_2$	1-Propoxy-2-propanol	423	605.1	3.051		14
$C_6H_{14}O_2$	2-Butoxyethanol	441.6	634	3.27	424	7
$C_6H_{14}O_2$	1,1-Diethoxyethane [Acetal]	375.40	540	3.22		7
$C_6H_{14}O_2$	1,2-Diethoxyethane [Ethylene glycol diethyl ether]	394.4	542			7
$C_6H_{14}O_3$	Diethylene glycol monoethyl ether [Carbitol]	469	670	3.167		11,12
$C_6H_{14}O_3$	Diethylene glycol dimethyl ether	435	617			7
$C_6H_{14}O_4$	Triethylene glycol	558	780	3.3		7
$C_6H_{15}N$	Dipropylamine	382.5	555.8	3.63		9
$C_6H_{15}N$	Diisopropylamine	357.1	523.1	3.02		9
$C_6H_{15}N$	Triethylamine	362	535.6	3.032	389	9
C_7F_8	Perfluorotoluene	377.7	534.47	2.705	428	9
C_7F_{14}	Perfluoro-1-heptene	354.2	478.2			9
C_7F_{14}	Perfluoromethylcyclohexane	349.5	485.91	2.019	570	9
C_7F_{16}	Perfluoroheptane	355.7	474.8	1.62	664	9
C_7HF_{15}	1*H*-Pentadecafluoroheptane	369.2	495.8			9
$C_7H_3F_5$	2,3,4,5,6-Pentafluorotoluene	390.7	566.52	3.126	384	9
$C_7H_4BrF_3$	1-Bromo-2-(trifluoromethyl)benzene	440.7	656.5			13
$C_7H_4BrF_3$	1-Bromo-3-(trifluoromethyl)benzene	424.7	627.1			13
$C_7H_4BrF_3$	1-Bromo-4-(trifluoromethyl)benzene	433	629.8			13

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
C_7H_5N	Benzonitrile	464.3	699.4	4.21		9
$C_7H_6F_2$	2,4-Difluorotoluene	390	581.4			13
$C_7H_6F_2$	2,5-Difluorotoluene	391	587.8			13
$C_7H_6F_2$	2,6-Difluorotoluene	385	581.8			13
$C_7H_6F_2$	3,4-Difluorotoluene	385	598.5			13
C_7H_6O	Benzaldehyde	452.0	695	4.7		7
C_7H_7F	2-Fluorotoluene	388	591.2			13
C_7H_7F	3-Fluorotoluene	388	591.8			13
C_7H_7F	4-Fluorotoluene	389.8	592.1			13
C_7H_8	Toluene	383.78	591.80	4.110	316	3,15
C_7H_8O	*o*-Cresol	464.19	697.6	4.17		7
C_7H_8O	*m*-Cresol	475.42	705.8	4.36		7
C_7H_8O	*p*-Cresol	475.13	704.6	4.07		7
C_7H_8O	Benzyl alcohol	478.46	715	4.3		9
C_7H_8O	Anisole [Methoxybenzene]	426.9	646.5	4.24	341	7,11,12
C_7H_9N	2-Methylaniline	473.5	707	4.37		9
C_7H_9N	3-Methylaniline	476.5	707	4.28		9
C_7H_9N	4-Methylaniline	473.6	706	4.58		9
C_7H_9N	*N*-Methylaniline	469.4	701	5.20		9
C_7H_9N	2,3-Dimethylpyridine	434.27	655.4	4.10	356	23
C_7H_9N	2,4-Dimethylpyridine	431.53	647	3.95	361	23
C_7H_9N	2,5-Dimethylpyridine	430.13	645	3.85	361	23
C_7H_9N	2,6-Dimethylpyridine	417.16	624	3.85	361	23
C_7H_9N	3,4-Dimethylpyridine	452.25	684	4.20	355	23
C_7H_9N	3,5-Dimethylpyridine	444.99	668	4.05	361	23
C_7H_{14}	1-Heptene	366.79	537.3	2.92	409	6
C_7H_{14}	Cycloheptane	391.6	604.2	3.82	353	5
C_7H_{14}	Methylcyclohexane	374.08	572.1	3.48	369	5
C_7H_{14}	Ethylcyclopentane	376.7	569.5	3.40	375	5
C_7H_{14}	1,1-Dimethylcyclopentane	360.7	547	3.45		21
C_7H_{14}	*cis*-1,2-Dimethylcyclopentane	372.7	565	3.45		21
C_7H_{14}	*trans*-1,2-Dimethylcyclopentane	365.1	553	3.45		21
C_7H_{14}	*cis*-1,3-Dimethylcyclopentane	364.0	551	3.45		21
C_7H_{14}	*trans*-1,3-Dimethylcyclopentane	364.9	553	3.45		21
$C_7H_{14}O$	Heptanal	426.0	617	3.16	434	7
$C_7H_{14}O$	2-Heptanone [Methyl pentyl ketone]	424.20	611.4	2.97	436	7
$C_7H_{14}O$	3-Heptanone [Ethyl butyl ketone]	420	606.6		433	7
$C_7H_{14}O$	4-Heptanone	417	602.0		434	7
$C_7H_{14}O$	5-Methyl-2-hexanone [Methyl isopentyl ketone]	417	604.1			7
$C_7H_{14}O$	2-Methyl-3-hexanone	408	593.3			7
$C_7H_{14}O_2$	Heptanoic acid	495.4	678	3.16		7
$C_7H_{14}O_2$	Pentyl acetate	422.4	599	2.73	470	7,23
$C_7H_{14}O_2$	Isopentyl acetate	415.7	586.1	2.76		7
$C_7H_{14}O_2$	Butyl propanoate	420.0	594.5			7
$C_7H_{14}O_2$	Isobutyl propanoate	410	584			7
$C_7H_{14}O_2$	Propyl butanoate	416.2	593.1	2.72		7
$C_7H_{14}O_2$	Propyl isobutanoate	408.6	579.4			7
$C_7H_{14}O_2$	Ethyl pentanoate	419.3	593.3			7
$C_7H_{14}O_2$	Ethyl 3-methylbutanoate	408.2	582.4			7
$C_7H_{14}O_3$	Ethyl 3-ethoxypropanoate	439	621.0	2.66	458	7
$C_7H_{15}Cl$	1-Chloroheptane	433.6	614			13
C_7H_{16}	Heptane	371.6	540.2	2.74	428	2
C_7H_{16}	2-Methylhexane	363.19	530.4	2.74	421	5
C_7H_{16}	3-Methylhexane	365	535.2	2.81	404	5
C_7H_{16}	3-Ethylpentane	366.7	540.6	2.89	416	5
C_7H_{16}	2,2-Dimethylpentane	352.4	520.5	2.77	416	5
C_7H_{16}	2,3-Dimethylpentane	362.93	537.3	2.91	393	5
C_7H_{16}	2,4-Dimethylpentane	353.64	519.8	2.74	418	5
C_7H_{16}	3,3-Dimethylpentane	359.21	536.4	2.95	414	5
C_7H_{16}	2,2,3-Trimethylbutane	354.01	531.1	2.95	398	5

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
$C_7H_{16}O$	2-Ethoxy-2-methylbutane	375	546	2.935	463	7
$C_7H_{16}O$	1-Heptanol	449.60	632.6	3.058	435	4
$C_7H_{16}O$	2-Heptanol	432	608.3	3.021	442	4
$C_7H_{16}O$	3-Heptanol, (*S*)	430	605.4		434	4
$C_7H_{16}O$	4-Heptanol	429	602.6		432	4
$C_7H_{16}O_2$	1-Butoxy-2-propanol	444.7	624.9	2.739		14
$C_7H_{16}O_2$	1-*tert*-Butoxy-2-methoxyethane		574			7
$C_7H_{16}O_2$	2,2-Diethoxypropane	387	510.7			7
$C_7H_{16}O_3$	Diethylene glycol monopropyl ether	486	680	3.00	489	7
$C_7H_{20}Si_2$	Bis(trimethylsilyl)methane	406	573.9	1.99		8
$C_8F_{16}O$	Perfluoro-2-butyltetrahydrofuran	375.8	500.2	1.607	588	9
C_8F_{18}	Perfluorooctane	379.1	502	1.66		9
C_8H_6S	Benzo[b]thiophene	494	764	4.76	379	8
C_8H_7N	4-Methylbenzonitrile	490.2	723			9
C_8H_7N	1*H*-Indole	526.8	794	4.8	356	10
C_8H_8	Styrene	418	635.2	3.87		15
C_8H_8O	Acetophenone	475	709.6	4.01	388	7,23
$C_8H_8O_2$	Phenyl acetate	469	685.7	3.59		17
$C_8H_8O_3$	Methyl salicylate	496.1	709			7
C_8H_{10}	Ethylbenzene	409.34	617.15	3.609	374	3,15
C_8H_{10}	*o*-Xylene	417.7	630.3	3.732	370	3
C_8H_{10}	*m*-Xylene	412.27	617.0	3.541	375	3
C_8H_{10}	*p*-Xylene	411.52	616.2	3.511	378	3
$C_8H_{10}O$	2-Ethylphenol	477.7	703.0			7
$C_8H_{10}O$	3-Ethylphenol	491.6	716.4			7
$C_8H_{10}O$	4-Ethylphenol	491.1	716.4			7
$C_8H_{10}O$	2,3-Xylenol	490.1	722.8			7
$C_8H_{10}O$	2,4-Xylenol	484.13	707.6			7
$C_8H_{10}O$	2,5-Xylenol	484.3	706.9			7
$C_8H_{10}O$	2,6-Xylenol	474.22	701.0			7
$C_8H_{10}O$	3,4-Xylenol	500	729.8			7
$C_8H_{10}O$	3,5-Xylenol	494.89	715.6			7
$C_8H_{10}O$	α-Methylbenzenemethanol	478	699	3.77		14
$C_8H_{10}O$	Ethoxybenzene	442.96	647	3.4		7
$C_8H_{10}O$	2-Methylanisole	444	662.0			7
$C_8H_{10}O$	3-Methylanisole	448.7	665.3			7
$C_8H_{10}O$	4-Methylanisole	448.7	666			7
$C_8H_{11}N$	*N*-Ethylaniline	476.2	698			9
$C_8H_{11}N$	*N,N*-Dimethylaniline	467.30	687	3.63		9
$C_8H_{14}O_4$	Diethyl succinate	490.9	663			7
$C_8H_{15}N$	Octanenitrile	478.40	674.4	2.85		9
C_8H_{16}	1-Octene	394.44	567.0	2.68	468	6
C_8H_{16}	Cyclooctane	422	647.2	3.56	410	5
C_8H_{16}	Ethylcyclohexane	405.1	609	3.04		21
C_8H_{16}	*cis*-1,2-Dimethylcyclohexane	403.0	606	2.95		21
C_8H_{16}	*trans*-1,2-Dimethylcyclohexane	396.7	596	2.94		21
C_8H_{16}	*cis*-1,3-Dimethylcyclohexane	393.3	591	2.94		21
C_8H_{16}	*trans*-1,3-Dimethylcyclohexane	397.7	598	2.94		21
C_8H_{16}	*trans*-1,4-Dimethylcyclohexane	392.6	587.7			5
$C_8H_{16}O$	Octanal	444	639	2.96	488	7
$C_8H_{16}O$	2-Octanone [Hexyl methyl ketone]	445.7	632.7		497	7
$C_8H_{16}O$	3-Octanone [Ethyl amyl ketone]	440.7	627.7		497	7
$C_8H_{16}O$	4-Octanone [Butyl propyl ketone]	436	623.8		497	7
$C_8H_{16}O$	2-Methyl-3-heptanone [Butyl isopropyl ketone]	431	614.9			7
$C_8H_{16}O$	5-Methyl-3-heptanone	434	619.0			7
$C_8H_{16}O_2$	Octanoic acid	512	693	2.87	519	7
$C_8H_{16}O_2$	2-Ethylhexanoic acid	501	674	2.78	528	7
$C_8H_{16}O_2$	Hexyl acetate	444.7	618.4			7
$C_8H_{16}O_2$	Isopentyl propanoate	433.4	611			7
$C_8H_{16}O_2$	Butyl butanoate	439	612.1			7

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
$C_8H_{16}O_2$	Isobutyl butanoate	430.1	611			7
$C_8H_{16}O_2$	Isobutyl isobutanoate	421.8	602			7
$C_8H_{16}O_2$	Propyl 3-methylbutanoate	429.1	609			7
$C_8H_{16}O_2$	Ethyl hexanoate	440	615.2			7
$C_8H_{16}O_2$	Methyl heptanoate	447	628			7
$C_8H_{16}O_3$	2-Butoxyethyl acetate	465	640.7	2.694	549	7
$C_8H_{16}O_4$	Diethylene glycol monoethyl ether acetate	491.7	673.5	2.59		17
$C_8H_{17}Cl$	1-Chlorooctane	456.7	643			13
C_8H_{18}	Octane	398.82	568.7	2.49	492	2
C_8H_{18}	2-Methylheptane	390.81	559.7	2.50	488	5
C_8H_{18}	3-Methylheptane	392.1	563.6	2.55	464	5
C_8H_{18}	4-Methylheptane	390.87	561.7	2.54	476	5
C_8H_{18}	3-Ethylhexane	391.8	565.5	2.61	455	5
C_8H_{18}	2,2-Dimethylhexane	380.01	549.8	2.53	478	5
C_8H_{18}	2,3-Dimethylhexane	388.77	563.5	2.63	468	5
C_8H_{18}	2,4-Dimethylhexane	382.7	553.5	2.56	472	5
C_8H_{18}	2,5-Dimethylhexane	382.27	550.0	2.49	482	5
C_8H_{18}	3,3-Dimethylhexane	385.12	562.0	2.65	443	5
C_8H_{18}	3,4-Dimethylhexane	390.88	568.8	2.69	466	5
C_8H_{18}	3-Ethyl-2-methylpentane	388.81	567.1	2.70	442	5
C_8H_{18}	3-Ethyl-3-methylpentane	391.42	576.5	2.81	455	5
C_8H_{18}	2,2,3-Trimethylpentane	383	563.5	2.73	436	5
C_8H_{18}	2,2,4-Trimethylpentane [Isooctane]	372.37	543.8	2.57	468	5
C_8H_{18}	2,3,3-Trimethylpentane	388.0	573.5	2.82	455	5
C_8H_{18}	2,3,4-Trimethylpentane	386.7	566.4	2.73	460	5
C_8H_{18}	2,2,3,3-Tetramethylbutane	379.60	567.8	2.87	461	9
$C_8H_{18}O$	1-Octanol	468.31	652.5	2.777	497	4
$C_8H_{18}O$	2-Octanol	452.5	629.6	2.754	519	4
$C_8H_{18}O$	3-Octanol	444	628.5		515	4
$C_8H_{18}O$	4-Octanol	449.5	625.1		515	4
$C_8H_{18}O$	4-Methyl-3-heptanol	443	623.5			4
$C_8H_{18}O$	5-Methyl-3-heptanol	445	621.2			4
$C_8H_{18}O$	2-Ethyl-1-hexanol	457.8	640.6	2.8		4
$C_8H_{18}O$	Dibutyl ether	413.43	584	3.0		7
$C_8H_{18}O$	Di-*tert*-butyl ether	380.38	550			9
$C_8H_{18}O_2$	1-*tert*-Butoxy-2-ethoxyethane	421.2	585			7
$C_8H_{18}O_3$	Diethylene glycol monobutyl ether	504	692	2.79		7
$C_8H_{18}O_3$	Diethylene glycol diethyl ether	461	612			7
$C_8H_{18}O_5$	Tetraethylene glycol	601	800	3.2		7
$C_8H_{18}S$	1-Octanethiol	472.3	667		504	8
$C_8H_{18}S$	Dibutyl sulfide	458	650	2.48		8
$C_8H_{19}N$	Dibutylamine	432.8	607.5	3.11		9
$C_8H_{19}N$	Diisobutylamine	412.8	584.4	3.20		9
$C_8H_{20}Si$	Tetraethylsilane	427.9	605	2.50	587	8
C_9F_{20}	Perfluorononane	398.5	524	1.56		9
C_9H_7N	Quinoline	510.31	782	4.86	371	10
C_9H_7N	Isoquinoline	516.37	803	5.10	374	10
C_9H_{10}	Indan	451.12	684.9	3.95		3
C_9H_{12}	Propylbenzene	432.39	638.35	3.200	440	3
C_9H_{12}	Isopropylbenzene [Cumene]	425.56	631.0	3.209		3
C_9H_{12}	2-Ethyltoluene	438.4	651	3.38		21
C_9H_{12}	3-Ethyltoluene	434.5	637	3.25		21
C_9H_{12}	4-Ethyltoluene	435	640.2	3.23		3
C_9H_{12}	1,2,3-Trimethylbenzene	449.27	664.5	3.454		3
C_9H_{12}	1,2,4-Trimethylbenzene	442.53	649.1	3.232		3
C_9H_{12}	1,3,5-Trimethylbenzene [Mesitylene]	437.89	637.3	3.127		3
$C_9H_{12}O$	2-Methoxy-1,4-dimethylbenzene	467	677.3			7
$C_9H_{12}O$	1-Methoxy-2,4-dimethylbenzene	465	682			7
$C_9H_{13}N$	2-Methyl-*N*,*N*-dimethylaniline	467.3	668	3.12		9
C_9H_{18}	1-Nonene	420.1	594.0		526	6

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
C_9H_{18}	Cyclononane	451.6	682	3.34		21
C_9H_{18}	1α,3α,5β-1,3,5-Trimethylcyclohexane	413.7	602.2			5
$C_9H_{18}O$	Nonanal	464	659	2.68	543	7
$C_9H_{18}O$	2-Nonanone [Heptyl methyl ketone]	468.5	652.2	2.48	560	7,11,12
$C_9H_{18}O$	3-Nonanone [Ethyl hexyl ketone]	463	648.1		560	7
$C_9H_{18}O$	4-Nonanone [Pentyl propyl ketone]	460.7	643.7		560	7
$C_9H_{18}O$	5-Nonanone [Dibutyl ketone]	461.60	641.4	2.32	560	7
$C_9H_{18}O_2$	Nonanoic acid	527.7	712	2.35		7
$C_9H_{18}O_2$	Isopentyl butanoate	452	619			7
$C_9H_{18}O_2$	Isobutyl 3-methylbutanoate	441.7	621			7
$C_9H_{18}O_2$	Ethyl heptanoate	460	634			7
C_9H_{20}	Nonane	423.97	594.6	2.29	555	2
C_9H_{20}	2-Methyloctane	416.4	582.8	2.31		5
C_9H_{20}	2,2-Dimethylheptane	405.9	576.7	2.35		5
C_9H_{20}	2,2,5-Trimethylhexane	397.24	569.8			5
C_9H_{20}	2,2,3,3-Tetramethylpentane	413.4	607.5	2.74		5
C_9H_{20}	2,2,3,4-Tetramethylpentane	406.2	592.6	2.60		5
C_9H_{20}	2,2,4,4-Tetramethylpentane	395.44	574.6	2.49		5
C_9H_{20}	2,3,3,4-Tetramethylpentane	414.7	607.5	2.72		5
$C_9H_{20}O$	1-Nonanol	486.52	670.7	2.528	572	4
$C_9H_{20}O$	2-Nonanol	466.7	649.6	2.53	575	4
$C_9H_{20}O$	3-Nonanol	468	648.0		577	4
$C_9H_{20}O$	4-Nonanol	465.7	645.1		575	4
$C_{10}F_8$	Perfluoronaphthalene	482	673.1			9
$C_{10}F_{18}$	Perfluorodecalin	415	566	1.52		9
$C_{10}F_{22}$	Perfluorodecane	417.4	542	1.45		9
$C_{10}H_8$	Naphthalene	491.1	748.4	4.05	407	3
$C_{10}H_9N$	1-Naphthylamine	573.9	850	5.0	438	10
$C_{10}H_9N$	2-Naphthylamine	579.4	850	4.9	438	10
$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene [Tetralin]	480.8	720	3.65	408	4
$C_{10}H_{14}$	Butylbenzene	456.46	660.5	2.89	497	3
$C_{10}H_{14}$	Isobutylbenzene	445.94	650	3.05		4
$C_{10}H_{14}$	1-Isopropyl-4-methylbenzene [*p*-Cymene]	450.3	652	2.8		3
$C_{10}H_{14}$	*p*-Diethylbenzene	456.9	657.9	2.803		3
$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene [Durene]	470.0	676	2.9		3
$C_{10}H_{14}O$	Thymol	505.7	698			7
$C_{10}H_{16}$	*d*-Limonene	451	653		470	6
$C_{10}H_{16}$	α-Pinene	429.4	644		454	6
$C_{10}H_{16}$	3-Carene, (+)	444	658		487	6
$C_{10}H_{18}$	1,3-Decadiene	442	615			9
$C_{10}H_{18}$	*cis*-Decahydronaphthalene	469.0	702.3	3.20		9
$C_{10}H_{18}$	*trans*-Decahydronaphthalene	460.5	687.1			9
$C_{10}H_{20}$	1-Decene	443.7	617	2.22	584	6
$C_{10}H_{20}O$	Decanal	481.7	674	2.60	599	7
$C_{10}H_{20}O$	2-Decanone [Methyl octyl ketone]	483	671.8		625	7
$C_{10}H_{20}O$	3-Decanone [Ethyl heptyl ketone]	476	667.6		628	7
$C_{10}H_{20}O$	4-Decanone [Hexyl propyl ketone]	479.7	662.9		628	7
$C_{10}H_{20}O$	5-Decanone [Butyl pentyl ketone]	477	661.0		628	7
$C_{10}H_{20}O$	5-Methyl-2-isopropylcyclohexanol [Menthol]	489	694			9
$C_{10}H_{20}O_2$	Decanoic acid [Capric acid]	541.9	722	2.10	638	7
$C_{10}H_{20}O_2$	2-Ethylhexyl acetate	472	642	2.09	681	7
$C_{10}H_{20}O_2$	Ethyl octanoate	481.7	649			7
$C_{10}H_{20}O_4$	Diethylene glycol monobutyl ether acetate	518	693.9	2.15		17
$C_{10}H_{22}$	Decane	447.30	617.7	2.11	624	2
$C_{10}H_{22}$	3,3,5-Trimethylheptane	428.9	609.5	2.32		5
$C_{10}H_{22}$	2,2,3,3-Tetramethylhexane	433.5	623.0	2.51		5
$C_{10}H_{22}$	2,2,5,5-Tetramethylhexane	410.6	581.4	2.19		5
$C_{10}H_{22}O$	1-Decanol	504.3	687.3	2.315	649	4
$C_{10}H_{22}O$	2-Decanol	484	668.6		646	4
$C_{10}H_{22}O$	3-Decanol	486	666.1		643	4

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm³ mol⁻¹	Ref.
$C_{10}H_{22}O$	4-Decanol	483.7	663.7		643	4
$C_{10}H_{22}O$	5-Decanol	474	663.2		646	4
$C_{10}H_{22}S$	Diisopentyl sulfide	484	664			8
$C_{11}H_{10}$	1-Methylnaphthalene	517.9	772	3.60		3
$C_{11}H_{10}$	2-Methylnaphthalene	514.3	761			3
$C_{11}H_{16}$	Pentylbenzene	478.6	675	2.58		16
$C_{11}H_{22}O$	2-Undecanone	504.7	688		692	7
$C_{11}H_{22}O$	3-Undecanone	500	685		692	7
$C_{11}H_{22}O$	4-Undecanone		681		692	7
$C_{11}H_{22}O$	5-Undecanone	500	679		692	7
$C_{11}H_{22}O$	6-Undecanone	501	678		692	7
$C_{11}H_{22}O_2$	Ethyl nonanoate	500.2	664			7
$C_{11}H_{24}$	Undecane	469.1	639	1.98	689	2
$C_{11}H_{24}O$	1-Undecanol	518	703.6	2.147	718	4
$C_{12}H_8$	Acenaphthylene	553	792	3.20		21
$C_{12}H_8O$	Dibenzofuran	560	824	3.64	495	7
$C_{12}H_8S$	Dibenzothiophene	605.7	897	3.86	512	8
$C_{12}H_9N$	Carbazole	627.84	901.8	3.13	454	10
$C_{12}H_{10}$	Biphenyl	529.3	773	3.38	497	3
$C_{12}H_{10}O$	Diphenyl ether	531.2	767			7
$C_{12}H_{12}$	2,7-Dimethylnaphthalene	538	775	3.23	601	3
$C_{12}H_{18}$	Hexylbenzene	499.3	695	2.35		16
$C_{12}H_{18}$	Hexamethylbenzene	536.6	758			3
$C_{12}H_{20}O$	[1,1'-Bicyclohexyl]-2-one	537	787			7
$C_{12}H_{24}$	1-Dodecene	487.0	658	1.93		6
$C_{12}H_{24}O$	2-Dodecanone	519.7	702		752	7
$C_{12}H_{24}O$	3-Dodecanone		701		752	7
$C_{12}H_{24}O$	4-Dodecanone		697		759	7
$C_{12}H_{24}O$	5-Dodecanone		695		759	7
$C_{12}H_{24}O$	6-Dodecanone		694		762	7
$C_{12}H_{26}$	Dodecane	489.47	658	1.82	754	2
$C_{12}H_{26}O$	1-Dodecanol	533	719.4	1.994		4
$C_{13}H_9N$	Acridine	618.01	891.1	3.21	548	10
$C_{13}H_9N$	Phenanthridine	622.1	895	3.6	548	10
$C_{13}H_{10}O$	Benzophenone	578.6	830	3.35	568	7
$C_{13}H_{11}N$	9-Methyl-9*H*-carbazole	616.79	890	3.38	572	10
$C_{13}H_{12}$	Diphenylmethane	538.2	760	2.71	563	3
$C_{13}H_{20}$	Heptylbenzene	513	708	2.14		16
$C_{13}H_{26}O$	2-Tridecanone	536	717		820	7
$C_{13}H_{26}O$	3-Tridecanone		716		823	7
$C_{13}H_{26}O$	4-Tridecanone		712		823	7
$C_{13}H_{26}O$	5-Tridecanone		710		826	7
$C_{13}H_{26}O$	6-Tridecanone		709		826	7
$C_{13}H_{26}O$	7-Tridecanone	534	708		830	7
$C_{13}H_{26}O_2$	Methyl dodecanoate	540	712			7
$C_{13}H_{28}$	Tridecane	508.62	675	1.68	823	2
$C_{13}H_{28}O$	1-Tridecanol	547	734	1.935		9
$C_{14}H_{10}$	Anthracene	613.1	869.3		554	9
$C_{14}H_{10}$	Phenanthrene	613	869			4
$C_{14}H_{22}$	Octylbenzene	537	725	1.98		16
$C_{14}H_{28}O$	2-Tetradecanone		728		896	7
$C_{14}H_{28}O$	3-Tetradecanone		727		896	7
$C_{14}H_{28}O$	4-Tetradecanone		725		900	7
$C_{14}H_{28}O$	7-Tetradecanone		723		904	7
$C_{14}H_{30}$	Tetradecane	526.73	693	1.57	894	2
$C_{14}H_{30}O$	1-Tetradecanol	560	747	1.81		9
$C_{15}H_{32}$	Pentadecane	543.8	708	1.48	966	2
$C_{16}H_{26}$	Decylbenzene	566	752	1.72		16
$C_{16}H_{34}$	Hexadecane	560.01	723	1.40	1034	2
$C_{16}H_{34}$	2,2,4,4,6,8,8-Heptamethylnonane	519.5	692			5

Molecular formula	Name	T_b/K	T_c/K	P_c/MPa	V_c/cm^3 mol^{-1}	Ref.
$C_{16}H_{34}O$	1-Hexadecanol	585	770	1.61		9
$C_{17}H_{28}$	Undecylbenzene	589	763	1.64		16
$C_{17}H_{36}$	Heptadecane	575.2	736	1.34	1103	2
$C_{17}H_{36}O$	1-Heptadecanol	597	780	1.50		9
$C_{18}H_{14}$	*o*-Terphenyl	605	857	2.99	731	3
$C_{18}H_{14}$	*m*-Terphenyl	636	883	2.48	724	3
$C_{18}H_{14}$	*p*-Terphenyl	649	908	2.99	729	3
$C_{18}H_{38}$	Octadecane	589.5	747	1.29	1189	2
$C_{18}H_{38}O$	1-Octadecanol	608	790	1.44		9
$C_{19}H_{32}$	Tridecylbenzene	619	790	1.54		16
$C_{19}H_{40}$	Nonadecane	603.1	755	1.16		3
$C_{20}H_{42}$	Eicosane	616	768	1.07		3
$C_{20}H_{42}O$	1-Eicosanol [Arachic alcohol]	629	809	1.30		9
$C_{21}H_{44}$	Heneicosane	629.7	778	1.03		2
$C_{22}H_{46}$	Docosane	641.8	786	0.98		2
$C_{23}H_{48}$	Tricosane	653	790	0.92		2
$C_{24}H_{50}$	Tetracosane	664.5	800	0.87		2
$C_{30}H_{50}$	Squalene	694.5	795.9	0.59		15

SUBLIMATION PRESSURE OF SOLIDS

This table gives the sublimation (vapor) pressure of some representative solids as a function of temperature. Entries include simple inorganic and organic substances in their solid phase below room temperature, as well as polycyclic organic compounds which show measurable sublimation pressure only at elevated temperatures. Substances are listed by molecular formula in the Hill order. Values marked by * represent the solid–liquid–gas triple point. Note that some pressure values are in pascals (Pa) and others are in kilopascals (kPa). For conversion, 1 kPa = 7.506 mmHg = 0.0098692 atm.

References

1. Lide, D. R. and Kehiaian, H. V., CRC *Handbook of Thermophysical and Thermochemical Data*, CRC Press, Boca Raton, FL, 1994.
2. *TRC Thermodynamic Tables,* Thermodynamic Research Center, Texas A&M University, College Station, TX.
3. Oja, V. and Suuberg, E. M., *J. Chem. Eng. Data,* 43, 486, 1998.

Ar	*T*/K	55	60	65	70	75	80	83.81*	
Argon	*p*/kPa	0.2	0.8	2.8	7.7	18.7	40.7	68.8*	
BrH	*T*/K	135	140	150	160	170	180	185.1*	
Hydrogen bromide	*p*/kPa	0.1	0.3	1.1	3.3	8.7	20.1	27.4*	
Br_2	*T*/K	170	180	190	200	210	220	230	240*
Bromine	*p*/Pa	0.069	0.416	2.04	8.45	30.3	96.0	273	710*
ClH	*T*/K	120	130	140	150	155	159.0*		
Hydrogen chloride	*p*/kPa	0.1	0.5	1.9	5.8	9.5	13.5*		
Cl_2	*T*/K	120	130	140	150	160	170*		
Chlorine	*p*/Pa	0.144	1.52	11.2	63.1	283	1054*		
F_4Si	*T*/K	130	140	150	160	170	175	180	186.3*
Tetrafluorosilane	*p*/kPa	0.2	0.9	3.9	14.0	43.8	74.2	122.4	220.8*
F_6S	*T*/K	150	165	180	190	200	210	220	223.1*
Sulfur hexafluoride	*p*/kPa	0.4	2.6	11.3	25.9	54.5	106.1	195.1	232.7*
HI	*T*/K	160	170	180	190	200	210	220	222.4*
Hydrogen iodide	*p*/kPa	0.2	0.8	2.2	5.3	11.7	23.6	44.1	49.3*
H_2O	*T*/K	190	210	225	240	250	260	270	273.16*
Water	*p*/Pa	0.032	0.702	4.942	27.28	76.04	195.8	470.1	611.66*
H_2S	*T*/K	140	150	160	165	170	175	180	187.6*
Hydrogen sulfide	*p*/kPa	0.2	0.6	1.9	3.2	5.2	8.3	12.7	22.7*
H_3N	*T*/K	160	170	180	190	195	195.4*		
Ammonia	*p*/kPa	0.1	0.4	1.2	3.5	5.8	6.12*		
I_2	*T*/K	240	250	260	270	280	290	300	310*
Iodine	*p*/Pa	0.081	0.297	0.971	2.89	7.92	20.1	47.9	107*
Kr	*T*/K	80	90	95	100	105	110	115.8*	
Krypton	*p*/kPa	0.4	2.7	6.0	12.1	22.8	40.4	73.1*	
NO	*T*/K	85	90	95	100	105	109.5*		
Nitric oxide	*p*/kPa	0.1	0.4	1.3	3.8	10.0	21.9*		
Xe	*T*/K	110	120	130	140	150	155	160	161.4*
Xenon	*p*/kPa	0.3	1.5	4.9	14.0	34.2	51.1	74.2	81.7*
CHN	*T*/K	200	210	220	230	240	250	255	259.83*
Hydrogen cyanide	*p*/kPa	0.2	0.4	1.0	2.2	4.8	9.7	13.6	18.62*
CH_4	*T*/K	65	70	75	80	85	90.69*		
Methane	*p*/kPa	0.1	0.3	0.8	2.1	4.9	11.70*		
CO	*T*/K	50	55	60	65	68.13*			
Carbon monoxide	*p*/kPa	0.1	0.6	2.6	8.2	15.4*			
CO_2	*T*/K	130	140	155	170	185	194.7	205	216.58*
Carbon dioxide	*p*/kPa	0.032	0.187	1.674	9.987	44.02	101.3	227.1	518.0*
C_2Cl_6	*T*/K	275	300	325	350	375	400	425	459.9*
Hexachloroethane	*p*/Pa	0.004	0.056	0.383	1.62	5.30	14.8	36.4	107.4*
C_2H_2	*T*/K	130	140	150	160	170	180	190	192.4*
Acetylene	*p*/kPa	0.2	0.7	2.6	7.8	20.6	49.0	106.3	126.0*
$C_2H_4O_2$	*T*/K	250	260	270	280	289.7*			
Acetic acid	*p*/kPa	0.092	0.199	0.406	0.79	1.29*			
C_5H_{12}	*T*/K	200	210	220	230	240	250	255	256.58*
Neopentane	*p*/kPa	0.7	1.6	3.6	7.3	13.9	24.8	32.4	35.8*

$C_6H_6Cl_6$	T/K	300	320	330	340	350	360	370	380
1,2,3,4,5,6–Hexa–chlorocyclohexane (Lindane)	p/Pa	0.01	0.13	0.39	1.04	2.66	6.42	14.8	32.7
$C_6H_6O_2$	T/K	330	340	350	360	370	380		
Resorcinol	p/Pa	1.03	2.78	7.09	17.2	39.6	87.6		
$C_6H_6O_2$	T/K	350	360	370	380	390	400		
p–Hydroquinone	p/Pa	1.20	3.18	7.96	19.0	43.4	95.1		
$C_{10}H_8$	T/K	250	270	280	290	300	310	330	353.43*
Naphthalene	p/Pa	0.036	0.514	1.662	4.918	13.43	34.15	182.9	999.6*
$C_{12}H_8N_2$	T/K	290	300	310	320				
Phenazine	p/Pa	0.0013	0.0046	0.0150	0.0448				
$C_{12}H_8O$	T/K	300	310	320	330	340	350		
Dibenzofuran	p/Pa	0.408	1.21	3.35	8.71	21.4	50.0		
$C_{12}H_9N$	T/K	350	355	360					
Carbazole	p/Pa	0.086	0.140	0.245					
$C_{13}H_7NO_2$	T/K	330	340	350	360	370	380		
Benz[g]isoquinoline–5,10–dione	p/Pa	0.006	0.018	0.053	0.148	0.394	0.994		
$C_{13}H_8O$	T/K	330	340	350					
1H–Phenalen–1–one	p/Pa	0.040	0.113	0.302					
$C_{13}H_8O_2$	T/K	400	410	420	430				
3–Hydroxy–1H–phenalen–1–one	p/Pa	0.006	0.018	0.053	0.144				
$C_{13}H_9N$	T/K	290	300	310	320				
Acridine	p/Pa	0.0024	0.0085	0.0278	0.0845				
$C_{13}H_9N$	T/K	310	320	330	340				
Phenanthridine	p/Pa	0.020	0.066	0.206	0.603				
$C_{14}H_{10}$	T/K	320	330	340	350	360	370	380	390
Anthracene	p/Pa	0.014	0.043	0.125	0.342	1.01	2.38	5.35	11.5
$C_{14}H_{10}$	T/K	300	310	320	330	340	350	360	
Phenanthrene	p/Pa	0.025	0.085	0.270	0.796	2.02	4.89	11.2	
$C_{16}H_{10}$	T/K	320	330	340	350	360	370	380	390
Pyrene	p/Pa	0.008	0.024	0.073	0.208	0.556	1.32	2.86	6.30
$C_{16}H_{10}O$	T/K	360	370	380	390	400			
1–Pyrenol	p/Pa	0.005	0.016	0.047	0.135	0.364			
$C_{16}H_{12}S$	T/K	330	340	350	360	370	380	390	
Benzo[b]naphtho–(2,1–d)thiophene	p/Pa	0.001	0.004	0.012	0.036	0.098	0.255	0.631	
$C_{17}H_{12}$	T/K	340	350	360	370	380	390	400	
11*H*–Benzo[b]fluorene	p/Pa	0.003	0.009	0.029	0.085	0.235	0.619	1.55	
$C_{18}H_{10}O_4$	T/K	420	430	440	450				
6,11–Dihydroxy–5,12–naphthacenedione	p/Pa	0.008	0.022	0.055	0.131				
$C_{18}H_{12}$	T/K	390	400	410	420				
Chrysene	p/Pa	0.087	0.221	0.539	1.26				
$C_{18}H_{12}$	T/K	390	400	410	420	430	440	450	460
Naphthacene	p/Pa	0.005	0.014	0.035	0.084	0.194	0.432	0.928	1.929
$C_{20}H_{12}$	T/K	390	400	410	420	430			
Perylene	p/Pa	0.006	0.015	0.040	0.102	0.246			
$C_{22}H_{14}$	T/K	450	460	470	480	490			
Pentacene	p/Pa	0.002	0.006	0.013	0.031	0.069			
$C_{24}H_{12}$	T/K	430	440	450	460	470	480	490	500
Coronene	p/Pa	0.004	0.010	0.021	0.046	0.097	0.197	0.389	0.747

VAPOR PRESSURE

This table gives vapor pressure data for about 1800 inorganic and organic substances. In order to accommodate elements and compounds ranging from refractory to highly volatile in a single table, the temperature at which the vapor pressure reaches specified pressure values is listed. The pressure values run in decade steps from 1 Pa (about 7.5 μm Hg) to 100 kPa (about 750 mm Hg). All temperatures are given in °C.

The data used in preparing the table came from a large number of sources; the main references used for each substance are indicated in the last column. Since the data were refit in most cases, values appearing in this table may not be identical with values in the source cited. The temperature entry in the 100 kPa column is close to, but not identical with, the normal boiling point (which is defined as the temperature at which the vapor pressure reaches 101.325 kPa). Although some temperatures are quoted to 0.1°C, uncertainties of several degrees should generally be assumed. Values followed by an "e" were obtained by extrapolating (usually with an Antoine equation) beyond the region for which experimental measurements were available and are thus subject to even greater uncertainty.

Compounds are listed by molecular formula following the Hill convention. Substances not containing carbon are listed first, followed by those that contain carbon. To locate an organic compound by name or CAS Registry Number when the molecular formula is not known, use the table "Physical Constants of Organic Compounds" in Section 3 and its indexes to determine the molecular formula. The indexes to "Physical Constants of Inorganic Compounds" in Section 4 can be used in a similar way.

More extensive and detailed vapor pressure data on selected important substances appear in other tables in this section of the *Handbook*. These substances are flagged by a symbol following the name as follows:

* See "Vapor Pressure of Fluids below 300 K"
** See "IUPAC Recommended Data for Vapor Pressure Calibration"
*** See "Vapor Pressure of Ice" and "Vapor Pressure of Water from 0 to 370°C"

The following notations appear after individual temperature entries:

s — Indicates the substance is a solid at this temperature.
e — Indicates an extrapolation beyond the region where experimental measurements exist.
i — Indicates the value was calculated from ideal gas hermodynamic functions, such as those in the *JANAF Thermochemical Tables* (see Reference 8).

References

1. Lide, D.R., and Kehiaian, H.V., CRC Handbook of *Thermophysical and Thermochemical Data*, CRC Press, Boca Raton, FL, 1994.
2. Stull, D., in *American Institute of Physics Handbook, Third Edition*, Gray, D.E., Ed., McGraw Hill, New York, 1972.
3. Hultgren, R., Desai, P.D., Hawkins, D.T., Gleiser, M., Kelley, K.K., and Wagman, D.D., *Selected Values of Thermodynamic Properties of the Elements*, American Society for Metals, Metals Park, OH, 1973.
4. Stull, D., *Ind. Eng. Chem*., 39, 517, 1947.
5. *TRCVP, Vapor Pressure Database, Version 2.2P*, Thermodynamic Research Center, Texas A&M University, College Station, TX.
6. *TRC Thermodynamic Tables,* Thermodynamic Research Center, Texas A&M University, College Station, TX.
7. Ohe, S., *Computer Aided Data Book of Vapor Pressure*, Data Book Publishing Co., Tokyo, 1976.
8. Chase, M.W., Davies, C.A., Downey, J.R., Frurip, D.J., McDonald, R.A., and Syverud, A.N., *JANAF Thermochemical Tables, Third Edition, J. Phys. Chem. Ref. Data*, Vol. 14, Suppl. 1, 1985.
9. Barin, I., *Thermochemical Data of Pure Substances*, VCH Publishers, New York, 1993.
10. Jacobsen, R.T., et. al, *International Thermodynamic Tables of the Fluid State, No. 10. Ethylene*, Blackwell Scientific Publications, Oxford, 1988.
11. Wakeham, W.A., *International Thermodynamic Tables of the Fluid State, No.* 12. *Methanol*, Blackwell Scientific Publications, Oxford, 1993.
12. Janz, G.J., *Molten Salts Handbook*, Academic Press, New York, 1967.
13. Ohse, R.W. *Handbook of Thermodynamic and Transport Properties of Alkali Metals*, Blackwell Scientific Publications, Oxford, 1994.
14. Gschneidner, K.A., in *CRC Handbook of Chemistry and Physics, 77th Edition*, p. 4–112, CRC Press, Boca Raton, FL, 1996.
15. Leider, H.R., Krikorian, O.H., and Young, D.A., *Carbon*, 11, 555, 1973.
16. Ruzicka, K., and Majer, V., *J. Phys. Chem. Ref. Data*, 23, 1, 1994.
17. Tillner–Roth, R., and Baehr, H.D., *J. Phys. Chem. Ref. Data*, 23, 657, 1994.
18. Younglove, B.A., and McLinden, M.O., *J. Phys. Chem. Ref. Data*, 23, 731, 1994.
19. Outcalt, S.L., and McLinden, M.O., *J. Phys. Chem. Ref. Data*, 25, 605, 1996.
20. Weber, L.A., and Defibaugh, D.R., *J. Chem. Eng. Data*, 41, 382, 1996.
21. Rodrigues, M.F., and Bernardo-Gil, M.G., *J. Chem. Eng. Data*, 41, 581, 1996.
22. Piacente, V., Gigli, G., Scardala, P., and Giustini, A., *J. Phys. Chem*., 100, 9815, 1996.
23. Barton, J.L., and Bloom, H., *J. Phys. Chem*., 60, 1413, 1956.
24. Sense, K.A., Alexander, C.A., Bowman, R.E., and Filbert, R.B., *J. Phys. Chem*., 61, 337, 1957.
25. Ewing, C.T., and Stern, K.H., *J. Phys. Chem*. 78, 1998, 1974.
26. Cady, G.H., and Hargreaves, G.B., *J. Chem. Soc*., 1563, 1961; 1568, 1961.
27. Skudlarski, K., Dudek, J., and Kapala, J., *J. Chem. Thermodynamics*, 19, 857, 1987.
28. Wagner, W., and de Reuck, K.M., *International Thermodynamic Tables of the Fluid State, No. 9. Oxygen*, Blackwell Scientific Publications, Oxford, 1987.
29. Marsh, K.N., Editor, *Recommended Reference Materials for the Realization of Physicochemical Properties*, Blackwell Scientific Publications, Oxford, 1987.
30. Alcock, C.B., Itkin, V.P., and Horrigan, M.K., *Canadian Metallurgical Quarterly*, 23, 309, 1984.
31. Stewart, R.B., and Jacobsen, R.T., *J. Phys. Chem. Ref. Data*, 18, 639, 1989.
32. Sifner, O., and Klomfar, J., *J. Phys. Chem. Ref. Data*, 23, 63, 1994.
33. Bah, A., and Dupont–Pavlovsky, N., *J. Chem. Eng. Data,* 40, 869, 1995.
34. Behrens, R.G., and Rosenblatt, G., *J. Chem. Thermodynamics*, 4, 175, 1972.
35. Behrens, R.G., and Rosenblatt, G., *J. Chem. Thermodynamics*, 5, 173, 1973.
36. Haar, L., Gallagher, J.S., and Kell, G.S., *NBS/NRC Steam Tables*, Hemisphere Publishing Corp., New York, 1984.
37. Wagner, W., Saul, A., and Pruss, A., *J. Phys. Chem. Ref. Data*, 23, 515. 1994.
38. Behrens, R.G., Lemons, R.S., and Rosenblatt, G., *J. Chem. Thermodynamics*, 6, 457, 1974.
39. Boublik, T., Fried, V., and Hala, E., *The Vapor Pressure of Pure Substances, Second Edition,* Elsevier, Amsterdam, 1984.
40. Goodwin, R.D., *J. Phys. Chem. Ref. Data*, 14, 849, 1985.
41. Younglove, B.A., and Ely, J.F., *J. Phys. Chem. Ref. Data*, 16, 577, 1987.

Mol. form.	Name	Temperature in °C for the indicated pressure						Ref.
		1 Pa	10 Pa	100 Pa	1 kPa	10 kPa	100 kPa	
Substances not containing carbon:								
Ag	Silver	1010	1140	1302	1509	1782	2160	2
AgBr	Silver(I) bromide	569 i	656 i	765 i	905 i	1093 i	1359 i	9
AgCl	Silver(I) chloride	670	769	873	1052	1264	1561	4
AgI	Silver(I) iodide	594	686	803	959	1177	1503	4
Al	Aluminum	1209	1359	1544	1781	2091	2517	2
AlB_3H_{12}	Aluminum borohydride				−46.8	−9.4	45.5	4
$AlCl_3$	Aluminum trichloride	58.4 s	76.5 s	97.1 s	120.7 s	148.2 s	180.5 s	4
AlF_3	Aluminum trifluoride	744 s	819 s	906 s	1008 s	1130 s	1276 s	8
AlI_3	Aluminum triiodide				218	285	385	4
Al_2O_3	Aluminum oxide			2122	2351	2629	2975	4
Ar	Argon*		−226.4 s	−220.3 s	−212.4 s	−201.7 s	−186.0	1,5,31
As	Arsenic	280 s	323 s	373 s	433 s	508 s	601 s	3
$AsCl_3$	Arsenic(III) chloride			−8 e	21.3	63.1	129.4	1
AsF_3	Arsenic(III) fluoride					8.1	56.0	4
AsI_3	Arsenic(III) iodide				187	261	367 e	7
As_2O_3	Arsenic(III) oxide (arsenolite)	133.7 s	163.0 s	196.8 s	236.2 s	283.0		34
At	Astatine	88 s	119 s	156 s	202 s	258 s	334	2
Au	Gold	1373	1541	1748	2008	2347	2805	2
B	Boron	2075	2289	2549	2868	3272	3799	2
BBr_3	Boron tribromide			−45 e	−15 e	27.5	90.4	1
BCl_3	Boron trichloride*			−94.0	−70.5	−37.4	12.3	4
BF_3	Boron trifluoride*	−173.9 s	−166.0 s	−156.0 s	−143.0 s	−125.9	−101.1	4
B_2F_4	Tetrafluorodiborane						−34	1
B_2H_6	Diborane			−162 e	−147.0	−125.8	−92.6	1
B_5H_9	Pentaborane(9)				−34.8	3.8	57.6	4
Ba	Barium	638 s	765	912	1115	1413	1897	9
Be	Beryllium	1189 s	1335	1518	1750	2054	2469	2
$BeBr_2$	Beryllium bromide	203 s	240 s	283 s	335 s	397 s	473 s	4
$BeCl_2$	Beryllium chloride	196 s	237 s	284 s	339 s	402 s	487	4
BeF_2	Beryllium fluoride		686 e	767 e	869	999	1172 e	7
BeI_2	Beryllium iodide	188 s	229 s	276 s	333 s	402 s	487	4
Bi	Bismuth	668	768	892	1052	1265	1562	2
$BiBr_3$	Bismuth tribromide			217 s	273 i	348 i	455 i	4,9
$BiCl_3$	Bismuth trichloride				248.9	328.6	438.7	1,4
BrCs	Cesium bromide	531 s	601 s	701 i	834 i	1019 i	1293 e	9
BrH	Hydrogen bromide*		−153.3 s	−140.4 s	−123.8 s	−101.5 s	−67.0	5
BrH_3Si	Bromosilane				−81.0	−47.3	2.2	4
BrH_4N	Ammonium bromide	121 s	154 s	195 s	246 s	310.4 s	395.1 s	5
BrK	Potassium bromide	597 s	674 s	773				25
BrLi	Lithium bromide		630	733	868	1049	1308	4
BrNa	Sodium bromide			791	931	1120	1389	4
BrRb	Rubidium bromide			766	903	1087	1350	4
BrTl	Thallium(I) bromide				509	635	817	4
Br_2	Bromine*	−87.7 s	−71.8 s	−52.7 s	−29.3 s	2.5	58.4	1
Br_2Cd	Cadmium bromide	373 s	435 s	509 s				27
Br_2Hg	Mercury(II) bromide	71 s	98 s	132 s	174 s	227 s	318	4
Br_2OS	Thionyl bromide	−49 e	−29 e	−5 e	27.8	72.9	139.6	5
Br_2Pb	Lead(II) bromide	374	431	502	597	726	914	4
Br_2S_2	Sulfur bromide	−7 e	15 e	42 e	78.4	128.1	200.9	5
Br_3In	Indium(III) bromide			304.6 s	328.7 s	364.8 s		1
Br_3OP	Phosphorus(V) oxybromide				64 e	115.5	191.4	5
Br_3P	Phosphorus(III) bromide		−23 e	5 e	42.3	94.6	172.6	5
Br_3Sb	Antimony(III) bromide				136.5	196.9	286.5	1
Br_4Ge	Germanium(IV) bromide				51	105	188	4
Br_4Sn	Tin(IV) bromide				67	122	204	4
Br_4Zr	Zirconium(IV) bromide	136 s	167 s	203 s	245 s	295 s	356 s	4
Br_5P	Phosphorus(V) bromide		−19 s	4 s	31 s	65.5 s	110.1	5
Ca	Calcium	591 s	683 s	798 s	954	1170	1482	2
Cd	Cadmium	257 s	310 s	381	472	594	767	2

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$CdCl_2$	Cadmium chloride	412 s	471 s	541 s	634	768	959	23, 27
CdF_2	Cadmium fluoride				1257	1461	1742	4
CdI_2	Cadmium iodide	296 s	344 s	406	498	622	795	4,27
CdO	Cadmium oxide	770 s	866 s	983 s	1128 s	1314 s	1558 s	4
Ce	Cerium	1719	1921	2169	2481	2886	3432	14
ClCs	Cesium chloride			730	864	1043	1297	4
ClCu	Copper(I) chloride		459	543	675	914	1477	4
ClF	Chlorine fluoride*				−144.4	−122.6	−90.2	5
ClF_2P	Phosphorus(III) chloride difluoride				−119.5	−91.1	−47.6	5
ClF_3	Chlorine trifluoride				−63.7	−33.0	11.4	5
ClF_5	Chlorine pentafluoride				−88 e	−59	−14	7
ClH	Hydrogen chloride*				−138.2 s	−118.0	−85.2	1,5
$ClHO_3S$	Chlorosulfonic acid	−40 e	−20 e	5 e	38.7	85.0	153.6	5
ClH_4N	Ammonium chloride	91 s	121 s	159 s	204.7 s	263.1 s	339.5 s	5
ClK	Potassium chloride	625 s	704 s	804	945	1137	1411	23,25
ClLi	Lithium chloride		649 i	761 i	905 i	1101 i	1381 i	8
ClNO	Nitrosyl chloride		−116 s	−100 s	−78.7 s	−50.2	−5.7	5
$ClNO_2$	Nitryl chloride	−121 e	−113 e	−102 e	−86.1	−60.9	−15.7	5
ClNa	Sodium chloride	653 s	733 s	835	987	1182	1461	23,25
ClO_2	Chlorine dioxide*					−34.3	10.5	5
ClRb	Rubidium chloride			777	916	1105	1379	4
ClTl	Thallium(I) chloride				504	626	806	4
Cl_2	Chlorine*	−145 s	−133.7 s	−120.2 s	−103.6 s	−76.1	−34.2	1
Cl_2Co	Cobalt(II) chloride					818	1048	4
Cl_2FP	Phosphorus(III) dichloride fluoride				−71.1	−37.4	13.5	5
Cl_2F_3P	Phosphorus(V) dichloride trifluoride		−120 e	−101 e	−77.1	−44.3	3 e	7
Cl_2Fe	Iron(II) chloride				685	821	1025	4
Cl_2Hg	Mercury(II) chloride	64.4 s	94.7 s	130.8 s	174.5 s	228.5 s	304.0	4
Cl_2Mg	Magnesium chloride			762	908	1111	1414	4
Cl_2Mn	Manganese(II) chloride				760	933	1189	4
Cl_2Ni	Nickel(II) chloride	534 s	592 s	662 s	747 s	852 s	985 s	4
Cl_2OS	Thionyl chloride	−99 e	−81 e	−58 e	−27.1	14.6	75.2	5
Cl_2O_2S	Sulfuryl chloride				−27 e	11.8	69.0	5
Cl_2Pb	Lead(II) chloride			541 e	637	765	949	23
Cl_2S	Sulfur dichloride	−76 e	−61 e	−41 e	−16.7	15.3	58.7	5
Cl_2S_2	Sulfur chloride	−55 e	−36 e	−12 e	21.0	67.2	137.1	5
Cl_2Sn	Tin(II) chloride		253	308	381	479	622	4
Cl_2Zn	Zinc chloride	305 i	356 i	419 i	497 i	596 i	726 i	4,9,12
Cl_3Fe	Iron(III) chloride	118 s	153 s	190 s	229 s	268 s	319	4
Cl_3HSi	Trichlorosilane			−81 e	−56 e	−21 e	31.6	7
Cl_3N	Nitrogen trichloride				−25 e	13.2	70.6	5
Cl_3OP	Phosphorus(V) oxychloride					39.9	105.0	5
Cl_3P	Phosphorus(III) chloride	−93 e	−77 e	−55 e	−26.0	14.5	75.7	5
Cl_4Po	Polonium(IV) chloride					300.6	389.4	5
Cl_4Se	Selenium tetrachloride	23 s	45 s	71 s	102 s	141.4 s	191.1 s	5
Cl_4Si	Tetrachlorosilane*				−39 e	0 e	57.3	1
Cl_4Te	Tellurium tetrachloride				237 e	299.4	387.8	5
Cl_4Zr	Zirconium(IV) chloride	117 s	146 s	181 s	222 s	272 s	336 s	9
Cl_5P	Phosphorus(V) chloride	−2 s	19 s	44 s	74 s	111.4 s	158.9 s	5
Co	Cobalt	1517	1687	1892	2150	2482	2925	2
Cr	Chromium	1383 s	1534 s	1718 s	1950	2257	2669	2
Cs	Cesium	144.5	195.6	260.9	350.0	477.1	667.0	13,30
CsF	Cesium fluoride				825	999	1249	4
CsI	Cesium iodide	523 s	595 s	692	854	1029	1278	4,25
Cu	Copper	1236	1388	1577	1816	2131	2563	2
CuI	Copper(I) iodide				636	864	1331	4
Dy	Dysprosium	1105 s	1250 s	1431 i	1681 i	2031 i	2558 i	3
Er	Erbium	1231 s	1390 s	1612 i	1890 i	2279 i	2859 i	3

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
Eu	Europium	590 s	684 s	799 s	961	1179	1523	14
FH	Hydrogen fluoride*				−71.1	−33.7	19.2	1,5
FHO_3S	Fluorosulfonic acid	−14 e	4 e	28 e	59.1	101.3	162.2	5
FK	Potassium fluoride			869	1017	1216	1499	4
FLi	Lithium fluoride	801 s	896	1024	1188	1395	1672	4,12,25
FNO	Nitrosyl fluoride			−131 e	−116.1	−94.3	−60.1	5
FNO_2	Nitryl fluoride		−156 e	−144 e	−128.1	−106.0	−72.6	5
FNO_3	Fluorine nitrate	−160 e	−149 e	−135 e	−115.1	−87.4	−45.0	5
FNa	Sodium fluoride		920 s	1058	1218	1426	1702	4,12,24
FRb	Rubidium fluoride			910	1001	1145	1409	4,12
F_2	Fluorine*	−235 s	−229.5 s	−222.9 s	−214.8	−204.3	−188.3	1,5
F_2O	Fluorine monoxide*	−211.7	−204.7	−195.9	−184.2	−168.2	−144.9	5
F_2OS	Thionyl fluoride			−124 e	−106.5	−81.5	−44.1	5
F_2O_2Re	Rhenium(VI) dioxydifluoride				89.2	131.9	185 e	26
F_2Pb	Lead(II) fluoride				865	1054	1292	4
F_2Xe	Xenon difluoride			2.9 s	31.8 s	67.9 s	114 s	1,5
F_2Zn	Zinc fluoride	731 s	813 s	911 i	1048 i	1237 i	1503 i	9
F_3N	Nitrogen trifluoride*	−201 e	−194 e	−185 e	−172.8	−155.5	−129.2	5
F_3OP	Phosphorus(V) oxyfluoride	−124 s	−113 s	−100 s	−83.7 s	−64.1 s	−39.7 s	5
F_3P	Phosphorus(III) fluoride*				−152 e	−132.6	−101.4	5
F_4MoO	Molybdenum(VI) oxytetrafluoride	−21 s	3 s	33 s	69.3 s	117.3	184.1	26
F_4ORe	Rhenium(VI) oxytetrafluoride	5 s	26 s	50.7 s	80.1 s	117.1	171.2	26
F_4OW	Tungsten(VI) oxytetrafluoride	2 s	25 s	52.1 s	84.3 s	126.7	185.4	26
F_4S	Sulfur tetrafluoride				−110.0	−82.1	−40.3	5
F_4Se	Selenium tetrafluoride				13.6	51.6	104.7	5
F_4Si	Tetrafluorosilane*	−166 s	−157 s	−145.6 s	−132.3 s	−115.7 s	−94.9 s	4,7
F_5Mo	Molybdenum(V) fluoride				86.6	140.3	213 e	26
F_5Nb	Niobium(V) fluoride				80	140	224	4
F_5ORe	Rhenium(VII) oxypentafluoride	−103 s	−84 s	−59 s	−28 s	13.7 s	72.8	26
F_5Os	Osmium(V) fluoride			74.1	113.2	162.3	226 e	26
F_5P	Phosphorus(V) fluoride	−157 s	−148 s	−137 s	−124.5 s	−108.6 s	−84.8	5
F_5Re	Rhenium(V) fluoride			58.8	99.5	152 e	221 e	26
F_5Ta	Tantalum(V) fluoride					119	229	4
F_6Ir	Iridium(VI) fluoride	−88 s	−71 s	−51 s	−27 s	3.8 s	53.1	26
F_6Mo	Molybdenum(VI) fluoride	−98 s	−82 s	−64 s	−41.2 s	−13.4 s	33.5	26
F_6Os	Osmium(VI) fluoride	−89 s	−73 s	−54 s	−30.6 s	−1.7 s	47.4	26
F_6Re	Rhenium(VI) fluoride	−97 s	−82 s	−63 s	−40.2 s	−11.9 s	33.4	26
F_6S	Sulfur hexafluoride*	−158 s	−147 s	−133.6 s	−116.6 s	−94.4 s	−64.1 s	5
F_6Se	Selenium hexafluoride	−143 s	−132 s	−118 s	−100.7 s	−77.8 s	−46.5 s	5
F_6Te	Tellurium hexafluoride	−142 s	−130 s	−115 s	−96 s	−71.8 s	−39.1 s	5
F_6W	Tungsten(VI) fluoride	−107 s	−92 s	−74 s	−52.1 s	−24.8 s	16.9	26
$F_{10}S_2$	Sulfur decafluoride					−22.0	28.5	5
Fe	Iron	1455 s	1617	1818	2073	2406	2859	2
Fr	Francium	131 e	181 e	246 e	335 e	465 e	673 e	2
Ga	Gallium	1037	1175	1347	1565	1852	2245	2
Gd	Gadolinium	1563 i	1755 i	1994 i	2300 i	2703 i	3262 i	3
Ge	Germanium	1371	1541	1750	2014	2360	2831	2
HI	Hydrogen iodide*	−146 s	−135.2 s	−120.8 s	−101.9 s	−75.9 s	−35.9	5
HKO	Potassium hydroxide	520 e	601 e	704	842	1035	1325	4
HNO_3	Nitric acid			−37 e	−9 e	28.4	82.2	5
HN_3	Hydrazoic acid			−79 e	−54 e	−18.0	35.7	5
HNaO	Sodium hydroxide	513	605	722	874	1080	1377	4
H_2	Hydrogen*					−258.6	−252.8	1
H_2I_2Si	Diiodosilane				11.8	70.5	149.4	4
H_2O	Water***	−60.7 s	−42.2 s	−20.3 s	7.0	45.8	99.6	36,37
H_2O_2	Hydrogen peroxide			13 e	45 e	89.0	149.8	5
H_2O_4S	Sulfuric acid	72	103	140	187	248	330	4
H_2S	Hydrogen sulfide*		−149 s	−136 s	−118.9 s	−95.9 s	−60.5	1,5
H_2S_2	Hydrogen disulfide				−27 e	12.2	70.7	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
H_2Se	Hydrogen selenide	−145 s	−134 s	−120 s	−102.8 s	−78.9 s	−41.5	5
H_2Te	Hydrogen telluride					−46.6	−2.3	5
H_3ISi	Iodosilane				−47.7	−10.1	45.2	4
H_3N	Ammonia*	−139 s	−127 s	−112 s	−94.5 s	−71.3	−33.6	1,5,6
H_3NO	Hydroxylamine				43.7	73.3	109.8	4
H_3P	Phosphine*	−182 s	−173 s	−161 s	−145 s	−122.7	−88.0	5
H_4IN	Ammonium iodide	125 s	159 s	201 s	253 s	318.4 s	405.2 s	5
H_4N_2	Hydrazine				14.7	55.6	113 e	5
H_4Si	Silane*			−181	−165.4	−143.7	−111.8	4
He	Helium*					−270.6	−268.9	2
Hf	Hafnium	2416	2681	3004	3406	3921	4603	9
Hg	Mercury**	42.0	76.6	120.0	175.6	250.3	355.9	29,30
HgI_2	Mercury(II) iodide	85.1 s	115.6 s	152.4 s	197.8 s	255.1 s	353.6	4
Ho	Holmium	1159 s	1311 s	1502 i	1767 i	2137 i	2691 i	3
IK	Potassium iodide			731	866	1052	1322	4
ILi	Lithium iodide	545	619	710	824	972	1170	4
INa	Sodium iodide			753	883	1058	1301	4
IRb	Rubidium iodide			733	866	1045	1302	4
ITl	Thallium(I) iodide				520	644	821	4
I_2	Iodine (rhombic)	−12.8 s	9.3 s	35.9 s	68.7 s	108 s	184.0	1,2
I_2Pb	Lead(II) iodide			470	558	682	869	4
I_2Zn	Zinc iodide	301 s	351 s	409 s	488 i	598 i	750 i	9
I_3Sb	Antimony(III) iodide				214.9	292.0	401.2	4
I_4Sn	Tin(IV) iodide				167.1	242.7	347.7	4
I_4Zr	Zirconium(IV) iodide	187 s	220 s	259 s	305 s	361 s	430 s	4
In	Indium	923	1052	1212	1417	1689	2067	2
Ir	Iridium	2440 s	2684	2979	3341	3796	4386	2
K	Potassium	200.2	256.5	328	424	559	756.2	13,30
Kr	Krypton*	−214.0 s	−208.0 s	−199.4 s	−188.9 s	−174.6 s	−153.6	5
La	Lanthanum	1732 i	1935 i	2185 i	2499 i	2905 i	3453 i	3
Li	Lithium	524.3	612.3	722.1	871.2	1064.3	1337.1	13,30
Lu	Lutetium	1633 s	1829.8	2072.8	2380 i	2799 i	3390 i	3
Mg	Magnesium	428 s	500 s	588 s	698	859	1088	2
Mn	Manganese	955 s	1074 s	1220 s	1418	1682	2060	2
Mo	Molybdenum	2469 s	2721	3039	3434	3939	4606	2
MoO_3	Molybdenum(VI) oxide				801	935	1151	4
NO	Nitric oxide*	−201 s	−195 s	−188 s	−179.3 s	−168.1 s	−151.9	5
N_2	Nitrogen*	−236 s	−232 s	−226.8 s	−220.2 s	−211.1 s	−195.9	1,5
N_2O	Nitrous oxide*	−167 s	−157 s	−145.4 s	−131.1 s	−112.9 s	−88.7	5
N_2O_4	Nitrogen tetroxide	−92 s	−78 s	−61 s	−41.1 s	−16.6 s	28.7	5
N_2O_5	Nitrogen pentoxide	−71 s	−56 s	−40 s	−19.9 s	3.9 s	33.2	5
Na	Sodium	280.6	344.2	424.3	529	673	880.2	13,30
Nb	Niobium	2669	2934	3251	3637	4120	4740	2
Nd	Neodymium	1322.3	1501.2	1725.3	2023 i	2442 i	3063 i	3
Ne	Neon*	−261 s	−260 s	−258 s	−255 s	−252 s	−246.1	2
Ni	Nickel	1510	1677	1881	2137	2468	2911	2
OPb	Lead(II) oxide	724	816	928	1065	1241	1471	4
OSr	Strontium oxide	1789 s	1903 s	2047 s	2235 s	2488 s		4
O_2	Oxygen*				−211.9	−200.5	−183.1	1,28
O_2S	Sulfur dioxide*			−98 s	−80 s	−52.2	−10.3	1,5
O_2Se	Selenium dioxide	124.5 s	153.9 s	188 s	228 s	275 s	315 s	38
O_2Si	Silicon dioxide	1966 i	2149 i	2368 i				8
O_3	Ozone*	−189 e	−182 e	−172 e	−158 e	−139.7	−111.5	5
O_3P_2	Phosphorus(III) oxide				47.3	100.3	172.8	4
O_3S	Sulfur trioxide				−20 s	6.6 s	44.5	5
O_3Sb_2	Antimony(III) oxide (valentinite)	426.1 s	478 s	539 s	610 s	907	1420	4,35
O_5P_2	Phosphorus(V) oxide	285 s	328 s	377.5 s	434.4 s	500.5 s	591	4
O_7Re_2	Rhenium(VII) oxide	147 s	176 s	208 s	244 s	284 s	362	4
Os	Osmium	2887 s	3150	3478	3875	4365	4983	2

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
P	Phosphorus (white)	6 s	34 s	69	115	180	276	3,9
P	Phosphorus (red)	182 s	216 s	256 s	303 s	362 s	431 s	2,3
Pb	Lead	705	815	956	1139	1387	1754	2
PbS	Lead(II) sulfide	656 s	741 s	838 s	953 s	1088 s	1280	4
Pd	Palladium	1448 s	1624	1844	2122	2480	2961	2
Po	Polonium				573 e	730.2	963.3	5
Pr	Praseodymium	1497.7	1699.4	1954 i	2298 i	2781 i	3506 i	3
Pt	Platinum	2057	2277 e	2542	2870	3283	3821	2
Pu	Plutonium	1483	1680	1925	2238	2653	3226	2
Ra	Radium	546 s	633 s	764	936	1173	1526	2
Rb	Rubidium	160.4	212.5	278.9	368	496.1	685.3	13,30
Re	Rhenium	3030 s	3341	3736	4227	4854	5681	2
Rh	Rhodium	2015	2223	2476	2790	3132	3724	2
Rn	Radon*	−163 s	−152 s	−139 s	−121.4 s	−97.6 s	−62.3	5
Ru	Ruthenium	2315 s	2538	2814	3151	3572	4115	2
S	Sulfur	102 s	135	176	235	318	444	3
Sb	Antimony	534 s	603 s	738	946	1218	1585	2,3
Sc	Scandium	1372 s	1531 s	1733 i	1993 i	2340 i	2828 i	3
Se	Selenium	227	279	344	431	540	685	3
Si	Silicon	1635	1829	2066	2363	2748	3264	2
Sm	Samarium	728 s	833 s	967 s	1148 i	1402 i	1788 i	3
Sn	Tin	1224	1384	1582	1834	2165	2620	2
Sr	Strontium	523 s	609 s	717 s	866	1072	1373	2
Ta	Tantalum	3024	3324	3684	4122	4666	5361	2
Tb	Terbium	1516.1	1706.1	1928 i	2232 i	2640 i	3218 i	3
Tc	Technetium	2454 e	2725 e	3051 e	3453 e	3961 e	4621 e	2
Te	Tellurium			502 e	615 e	768.8	992.4	5
Th	Thorium	2360	2634	2975	3410	3986	4782	2
Ti	Titanium	1709	1898	2130 e	2419	2791	3285	2
Tl	Thallium	609	704	824	979	1188	1485	2
Tm	Thulium	844 s	962 s	1108 s	1297 s	1548 i	1944 i	3
U	Uranium	2052	2291	2586	2961	3454	4129	2
V	Vanadium	1828 s	2016	2250	2541	2914	3406	2
W	Tungsten	3204 s	3500	3864	4306	4854	5550	2
Xe	Xenon*	−190 s	−181 s	−170 s	−155.8 s	−136.6 s	−108.4	5,32
Y	Yttrium	1610.1	1802.3	2047 i	2354 i	2763 i	3334 i	3
Yb	Ytterbium	463 s	540 s	637 s	774 s	993 i	1192 i	3
Zn	Zinc	337 s	397 s	477	579	717	912 e	2
Zr	Zirconium	2366	2618	2924	3302	3780	4405	2
Substances containing carbon:								
C	Carbon (graphite)		2566 s	2775 s	3016 s	3299 s	3635 s	15
$CBrClF_2$	Bromochloro-difluoromethane	−136 e	−123 e	−106 e	−83.4	−51.8	−4.3	1
$CBrCl_3$	Bromotrichloromethane				−6 e	38.9	104.4	5
$CBrF_3$	Bromotrifluoromethane*	−168 e	−156 e	−142 e	−122.8	−96.6	−58.1	5
CBrN	Cyanogen bromide				−13 s	17.7 s	61.0	1
CBr_2F_2	Dibromodifluoromethane		−110 e	−91 e	−66 e	−30 e	22.5	1
CBr_4	Tetrabromomethane			25.6 s	65.8 s	111.6	188.9	5
$CClF_3$	Chlorotrifluoromethane	−176 e	−167 e	−155 e	−139 e	−116 e	−81.7	5
CClN	Cyanogen chloride		−94.6 s	−78.1 s	−57 s	−29 s	13.0	5
CCl_2F_2	Dichlorodifluoromethane*	−150 e	−138 e	−122 e	−101.8	−73.1	−30.0	5
CCl_2O	Carbonyl chloride	−127 e	−113 e	−96 e	−73 e	−40.6	7.2	5
CCl_3F	Trichlorofluoromethane*		−107 e	−89 e	−63 e	−28.5	23.3	1,5
CCl_3NO_2	Trichloronitromethane		−59 e	−30 e	4.4	47.8	112.0	5
CCl_4	Tetrachloromethane*	−79.4 s	−70.8 s	−53.5 s	−24.4 s	15.8	76.2	1,5
CFN	Cyanogen fluoride		−135 s	−121.2 s	−104.1 s	−82.8 s	−46.2	1,5
CF_4	Tetrafluoromethane*	−199.9 s	−193 s	−183.9 s	−171.6	−153.9	−128.3	1,5
$CHBrF_2$	Bromodifluoromethane		−128 s	−111.4 s	−89.7 s	−59.7 s	−16 s	5
$CHBr_3$	Tribromomethane				30.5	78.3	148.8	1
$CHClF_2$	Chlorodifluoromethane*	−152 e	−141 e	−126 e	−107.1	−80.5	−41.1	5
$CHCl_2F$	Dichlorofluoromethane	−76 e	−70 e	−61 e	−49 e	−28.7	8.6	1

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$CHCl_3$	Trichloromethane*			−61 e	−34 e	4.3	60.8	1
CHF_3	Trifluoromethane*			−152 e	−136 e	−114.4	−82.3	1
CHI_3	Triiodomethane	51.1 s	82.7 s	121 e			218.0	5
CHN	Hydrogen cyanide*			−77 s	−52.6 s	−22.7 s	25.4	1,5
CHNO	Cyanic acid			−81.1	−56.8	−23.9	23 e	5
CH_2BrCl	Bromochloromethane	−83 e	−69 e	−50 e	−25 e	11.4	67.7	1
CH_2Br_2	Dibromomethane			−37 e	−7 e	35.2	96.5	5
CH_2ClF	Chlorofluoromethane		−124 e	−108 e	−86.2	−55.7	−9.4	5
CH_2Cl_2	Dichloromethane*		−92 e	−73 e	−48 e	−12.5	39.3	1
CH_2F_2	Difluoromethane*	−156.7	−145.8	−131.9	−113.6	−88.6	−51.9	1
CH_2I_2	Diiodomethane			17 e	55 e	106.1	181.6	5
CH_2O	Formaldehyde*				−91 e	−61.7	−19.3	1
CH_2O_2	Formic acid	−56 s	−40.4 s	−22.3 s	−0.8 s	37.0	100.2	1,5
CH_3AsF_2	Methyldifluoroarsine				−15 e	22.1	76.1	5
CH_3BO	Borane carbonyl				−124	−99	−64	4
CH_3Br	Bromomethane				−77 e	−44.3	3.3	1
CH_3Cl	Chloromethane*	−140.2 s	−128.6 s	−114.7 s	−96 e	−67.1	−24.4	1,33
CH_3Cl_3Si	Methyltrichlorosilane		−83 e	−61 e	−33 e	7 e	65.7	1
CH_3F	Fluoromethane*				−130 e	−111 e	−78.6	1
CH_3I	Iodomethane				−49 e	−12.4	42.1	1
CH_3NO	Formamide		22 e	53 e	93 e	145.0	218 e	5
CH_3NO_2	Nitromethane				−2 e	40 e	100.8	1
CH_3NO_3	Methyl nitrate		−75 e	−55 e	−27 e	9.8	63 e	5
CH_4	Methane*	−220 s	−214.2 s	−206.8 s	−197 s	−183.6 s	−161.7	5,41
CH_4Cl_2Si	Dichloromethylsilane			−77 e	−51 e	−14 e	40.5	1
CH_4O	Methanol*	−87 e	−69 e	−47.5	−20.4	15.2	64.2	11
CH_4S	Methanethiol		−115 e	−97 e	−74 e	−41.7	5.7	1
CH_5ClSi	Chloromethylsilane	−129 e	−115 e	−97.9	−74.4	−41.5	8.3	5
CH_5N	Methylamine				−76.7	−48.1	−6.6	1
CH_6N_2	Methylhydrazine			−31 e	−4.7	32.9	91 e	1
CH_6OSi	Methyl silyl ether				−90.2	−61.8	−18 e	1
CH_6Si	Methylsilane			−144 e	−124.6	−97.5	−57.5	5
CIN	Cyanogen iodide						153.8	5
CNNa	Sodium cyanide		672 e	798	961	1182	1497	4
CN_4O_8	Tetranitromethane				18.0	61.8	124 e	5
CO	Carbon monoxide*			−223 s	−216.5 s	−207.2 s	−191.7	40
COS	Carbon oxysulfide*			−136 e	−117 e	−90.0	−50.4	1
COSe	Carbon oxyselenide			−120	−98	−67	−22	4
CO_2	Carbon dioxide*	−159.1 s	−148.9 s	−136.7 s	−121.6 s	−103.1 s	−78.6 s	5
CS_2	Carbon disulfide		−96 e	−76 e	−49 e	−10.9	45.9	1
CSe_2	Carbon diselenide			−24 e	9.4	56.2	127 e	1
$C_2Br_2ClF_3$	1,2-Dibromo-1-chloro-1,2,2-trifluoroethane						92.3	5
$C_2Br_2F_4$	1,2-Dibromotetrafluoroethane		−97 e	−75 e	−46 e	−7.2	47.1	5
C_2Br_4	Tetrabromoethylene		−54.5 s	−31.7 s	−3.5 s	32.2 s	226.0	5
C_2ClF_3	Chlorotrifluoroethylene	−146 e	−134 e	−119 e	−99 e	−71 e	−28.4	1
C_2ClF_5	Chloropentafluoroethane					−80.3	−39.4	1
$C_2Cl_2F_4$	1,1-Dichlorotetrafluoroethane					−45.4	2.7	5
$C_2Cl_2F_4$	1,2-Dichlorotetrafluoroethane				−76.8	−44.9	3.2	5
$C_2Cl_3F_3$	1,1,1-Trichlorotrifluoroethane						45.6	1,5
$C_2Cl_3F_3$	1,1,2-Trichlorotrifluoroethane					−8.2	47.3	1,5
C_2Cl_3N	Trichloroacetonitrile				−16 e	25.3	85.1	1
C_2Cl_4	Tetrachloroethylene			−22 e	10 e	54.4	120.7	1
$C_2Cl_4F_2$	1,1,1,2-Tetrachloro-2,2-difluoroethane				−7 e	31.0	91.1	5
$C_2Cl_4F_2$	1,1,2,2-Tetrachloro-1,2-difluoroethane					32.3	92.5	1
C_2Cl_4O	Trichloroacetyl chloride			−25 e	7 e	51.7	117.8	1,5
C_2Cl_6	Hexachloroethane	−7.6 s	9.9 s	33.6 s	67.7 s	116.9 s	184.2 s	5
C_2F_3N	Trifluoroacetonitrile				−126.1	−102.5	−67.8	1
C_2F_4	Tetrafluoroethylene				−132.3	−109.7	−75.8	1
$C_2F_4N_2O_4$	1,1,2,2-Tetrafluoro-1,2-dinitroethane				−30 e	6.4	59.5	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
C_2F_6	Hexafluoroethane**			−155.2 s	−137.5 s	−113.4 s	−78.4 s	1,5
$C_2HBrClF_3$	2-Bromo-2-chloro-1,1,1-trifluoroethane				−41.4	−4.8	49.8	1
C_2HBr_3O	Tribromoacetaldehyde			15.0	52.7	103.0	173.5	5
C_2HClF_4	1-Chloro-1,1,2,2-tetrafluoroethane			−110 e	−87.6	−57.0	−12.1	5
$C_2HCl_2F_3$	2,2-Dichloro-1,1,1-trifluoroethane		−101.0	−82.2	−57.4	−23.3	26.7	18
C_2HCl_3	Trichloroethylene	−74 e	−59 e	−39 e	−12 e	26.7	86.8	1
C_2HCl_3O	Trichloroacetaldehyde			−41.6	−9.8	33.8	97.4	5
$C_2HCl_3O_2$	Trichloroacetic acid				83.8	130.0	197.2	1,5
C_2HCl_5	Pentachloroethane		−23 e	3 e	37.4	86.0	159.4	1
$C_2HF_3O_2$	Trifluoroacetic acid					16.8	71.4	1,5
C_2HF_5O	Trifluoromethyl difluoromethyl ether	−147 e	−136 e	−121 e	−102 e	−75.0	−35.4	20
C_2H_2	Acetylene*			−146.6 s	−130.7 s	−110.6 s	−84.8 s	5
$C_2H_2Br_2$	*cis*-1,2-Dibromoethylene		−45 e	−21 e	10 e	52.2	114.8	1
$C_2H_2Br_2$	*trans*-1,2–Dibromoethylene				−4 e	42.2	107.4	5
$C_2H_2Br_2Cl_2$	1,2-Dibromo-1,1-dichloroethane					103.6	177.8	5
$C_2H_2Br_2Cl_2$	1,2-Dibromo-1,2-dichloroethane		−11 e	22 e	64.1	119 e	193 e	5
$C_2H_2Br_4$	1,1,2,2-Tetrabromoethane	14 e	38 e	69 e	109 e	163.7	242.9	5
$C_2H_2Cl_2$	1,1-Dichloroethylene	−116 e	−101 e	−82 e	−57 e	−21.4	31.2	1
$C_2H_2Cl_2$	*cis*-1,2-Dichloroethylene			−62 e	−34 e	3.8	60.3	1
$C_2H_2Cl_2$	*trans*-1,2-Dichloroethylene				−44 e	−7.5	47.3	1
$C_2H_2Cl_2F_2$	1,2-Dichloro-1,1-difluoroethane	−101 e	−87 e	−68 e	−42.2	−6.8	46.3	5
$C_2H_2Cl_2O$	Chloroacetyl chloride			−23.7	5.6	46.1	105.6	5
$C_2H_2Cl_4$	1,1,1,2-Tetrachloroethane	−58 e	−40 e	−15 e	17 e	62.2	129.7	1
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane		−22 e	1 e	32.4	76.9	144.7	1
$C_2H_2F_4$	1,1,1,2-Tetrafluoroethane				−94.3	−66.8	−26.4	17
$C_2H_2F_4$	1,1,2,2-Tetrafluoroethane				−96.0	−66.9	−23.3	5
C_2H_2O	Ketene		−151 e	−135 e	−115 e	−88.2	−50.0	1
C_2H_3Br	Bromoethylene	−124 e	−110 e	−92 e	−68 e	−34.5	15.4	5
C_2H_3BrO	Acetyl bromide	−78 e	−65 e	−49 e	−25 e	13.9	84 e	5
$C_2H_3Br_3$	1,1,2-Tribromoethane	−18 e	4 e	32 e	68 e	117.1	188.4	5
C_2H_3Cl	Chloroethylene	−139 e	−127 e	−110 e	−89 e	−59.0	−14.1	1
$C_2H_3ClF_2$	1-Chloro-1,1-difluoroethane		−123 e	−107 e	−85.3	−55.4	−10.5	5
C_2H_3ClO	Acetyl chloride	−100 e	−85 e	−66 e	−40 e	−3.6	50.4	1
$C_2H_3ClO_2$	Chloroacetic acid				78.4	123.9	188.9	1
$C_2H_3Cl_2F$	1,1-Dichloro-1-fluoroethane		−101 e	−83 e	−57.9	−22.7	31.4	5
$C_2H_3Cl_2F$	1,2-Dichloro-1-fluoroethane			−50 e	−23.8	14.1	73.4	5
$C_2H_3Cl_3$	1,1,1-Trichloroethane				-25.3	14.2	73.7	5
$C_2H_3Cl_3$	1,1,2-Trichloroethane			−23 e	7 e	49.9	113.4	1
C_2H_3F	Fluoroethylene			−153.3	−135.2	−109.9	−72.2	5
C_2H_3FO	Acetyl fluoride					−64.1	17.0	5
$C_2H_3F_3$	1,1,1-Trifluoroethane				−113 e	−86.6	−47.8	1
$C_2H_3F_3O$	2,2,2-Trifluoroethanol			−33 e	−8 e	26.0	74 e	5
C_2H_3I	Iodoethylene				−41 e	−3 e	55.6	5
C_2H_3IO	Acetyl iodide				−0.6	47 e	107.0	5
C_2H_3N	Acetonitrile				−20 e	21.4	81.2	1
C_2H_3NO	Methylisocyanate				−43.5	−10.2	38.8	1
C_2H_3NS	Methyl thiocyanate			−18.4	16.2	63.5	132.5	5
C_2H_4	Ethylene*				−155.6	−135.1	−104.0	1,10
C_2H_4BrCl	1-Bromo-2-chloroethane				−0.4	41.7	105.7	6
$C_2H_4Br_2$	1,1-Dibromoethane		−49 e	−26 e	5 e	46.4	107.6	5
$C_2H_4Br_2$	1,2-Dibromoethane				18 e	62.2	130.9	1
C_2H_4ClF	1-Chloro-1-fluoroethane				−69.9	−36.1	15.8	5
$C_2H_4Cl_2$	1,1-Dichloroethane		−84 e	−64 e	−36.7	1.0	56.9	1
$C_2H_4Cl_2$	1,2-Dichloroethane				−16.4	23.7	83.1	1
$C_2H_4F_2$	1,1-Difluoroethane			−115.2	−94.6	−66.1	−24.3	19
$C_2H_4N_2O_6$	Ethylene glycol dinitrate	4 e	25.6	51.0	81 e	117 e	162 e	5
C_2H_4O	Acetaldehyde		−105 e	−87 e	−62.8	−29.4	20.0	5
C_2H_4O	Ethylene oxide		−111 e	−93 e	−70 e	−37.0	10.2	1
$C_2H_4O_2$	Acetic acid	−42.8 s	−26.7 s	−8 s	14.2 s	55.9	117.5	1,5
$C_2H_4O_2$	Methyl formate		−95 e	−76 e	−51.8	−18.1	31.4	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_2H_4O_3$	Peroxyacetic acid				14.4	55.3	109.7	5
$C_2H_4O_3$	Glycolic acid						99.9	5
$C_2H_5AsF_2$	Ethyldifluoroarsine			−36 e	−6.0	35.0	93.1	5
C_2H_5Br	Bromoethane	−111 e	−96 e	−77 e	−51.3	−15.5	38.0	5
C_2H_5Cl	Chloroethane	−126 e	−112 e	−94 e	−70 e	−37.0	12.0	1
C_2H_5ClO	2-Chloroethanol	−61 e	−39 e	−12 e	23 e	67.1	127.3	5
C_2H_5ClO	Chloromethyl methyl ether	−96 e	−80 e	−59 e	−32 e	6 e	61 e	5
$C_2H_5Cl_3OSi$	Trichloroethoxysilane	−78 e	−60 e	−36.0	−4.6	38.7	102.0	5
$C_2H_5Cl_3Si$	Trichloroethylsilane	−79 e	−61 e	−38 e	−8 e	34.9	98.7	5
C_2H_5F	Fluoroethane		−142 e	−127 e	−106.3	−78.7	−37.9	1
C_2H_5FO	2-Fluoroethanol			−22 e	8.3	47.5	99 e	5
C_2H_5I	Iodoethane	−94 e	−78 e	−56 e	−27.9	11.9	71.9	5
C_2H_5N	Ethyleneimine		−74 e	−55 e	−30 e	4.1	55 e	5
C_2H_5NO	Acetamide	16.7 s	39.1 s	65.2 s	102.8	150.8	218.2	5
C_2H_5NO	*N*-Methylformamide		13 e	41 e	78 e	127.9	199.1	1
$C_2H_5NO_2$	Nitroethane	−61 e	−44 e	−21 e	8.3	50.1	113.5	5
$C_2H_5NO_3$	Ethyl nitrate	−81 e	−63 e	−41 e	−12 e	28.2	87 e	1
C_2H_6	Ethane*	−183.3 s	−173.2	−161.3	−145.3	−122.8	−88.8	41
$C_2H_6Cl_2Si$	Dichlorodimethylsilane					11.1	70.1	5
C_2H_6Hg	Dimethyl mercury				−13.5	29.0	92.1	5
$C_2H_6N_2O$	*N*-Nitrosodimethylamine				30.7	80.5	149.8	5
C_2H_6O	Ethanol	−73 e	−56 e	−34 e	−7 e	29.2	78.0	1,5
C_2H_6O	Dimethyl ether*		−135 e	−118 e	−96.8	−67.6	−25.1	1,5
C_2H_6OS	Dimethyl sulfoxide			27.4	65.0	115.9	188.6	1
$C_2H_6O_2$	Ethylene glycol	2 e	24 e	51.1	86.1	132.5	196.9	1
$C_2H_6O_2$	Ethyl hydroperoxide	−70 e	−49 e	−25 e	6.8	47.0	101 e	5
$C_2H_6O_2S$	Dimethyl sulfone				109 e	166.8	248.9	5
C_2H_6S	Ethanethiol	−112 e	−97 e	−78 e	−53 e	−18 e	34.7	1
C_2H_6S	Dimethyl sulfide		−96 e	−77 e	−51.2	−16.0	37.0	1,5
$C_2H_6S_2$	Dimethyl disulfide	−71 e	−53 e	−29 e	1.7	45.0	109.3	5
$C_2H_7BO_2$	Dimethoxyborane	−116 e	−101.9	−83.5	−59.2	−25.4	25 e	5
C_2H_7N	Ethylamine			−71 e	−53 e	−27 e	16.4	1
C_2H_7N	Dimethylamine			−88 e	−66.9	−37.2	6.6	1
C_2H_7NO	Ethanolamine		11 e	35 e	66.2	109.0	170.6	1
$C_2H_8N_2$	1,2-Ethanediamine				17.0	57.5	116.6	1,5
$C_2H_8N_2$	1,1-Dimethylhydrazine			−52 e	−25.6	10.5	63 e	5
$C_2H_8N_2$	1,2-Dimethylhydrazine		−49 e	−33 e	−9 e	26.4	88 e	1
C_2N_2	Cyanogen	−127 s	−114.1 s	−98.5 s	−79.2 s	−54.9 s	−21.4	5
C_3ClF_5O	Chloropentafluoroacetone	−122 e	−109 e	−93 e	−71 e	−39.4	7.4	5
C_3Cl_6	Hexachloropropene	−12 e	11 e	40 e	79 e	132.8	213.6	5
C_3F_6	Perfluoropropene	−150 e	−138 e	−122 e	−101 e	−72 e	−30.6	5
C_3F_6O	Perfluoroacetone			−113 e	−94 e	−67.8	−27.6	5
C_3F_8	Perfluoropropane		−139 e	−124 e	−105 e	−77.5	−37.0	1
C_3HN	Cyanoacetylene			−58.7 s	−35.6 s	−7 s	42.0	5
$C_3H_2F_6O$	1,1,1,3,3,3-Hexafluoro-2-propanol					12.7	57.1	5
$C_3H_3F_5$	1,1,1,2,2–Pentafluoropropane					−60 e	−17.9	5
C_3H_3N	2-Propenenitrile		−72 e	−50 e	−22 e	17.7	77.0	1
C_3H_3NS	Thiazole					54.4	117.8	5
C_3H_4	Allene*		−129 e	−118 e	−101.4	−76.7	−34.7	5
C_3H_4	Propyne				−94 e	−65.3	−23.2	1
$C_3H_4ClF_3$	3-Chloro-1,1,1-trifluoropropane	−102 e	−87 e	−68 e	−43 e	−8 e	45.3	5
$C_3H_4Cl_2O$	1,1-Dichloroacetone				1 e	47.8	118.0	5
$C_3H_4Cl_2O_2$	Methyl dichloroacetate	−44 e	−25 e	0 e	33 e	77.7	142.3	5
$C_3H_4Cl_4$	1,1,1,2-Tetrachloropropane	−48 e	−28 e	−2 e	32 e	79.1	149.5	5
$C_3H_4F_4O$	2,2,3,3-Tetrafluoro-1-propanol			−10 e	17 e	53.9	107.2	5
C_3H_4O	Acrolein		−87 e	−67 e	−40 e	−3.0	52.8	1
$C_3H_4O_2$	Propenoic acid				35 e	78.0	140.7	1
$C_3H_4O_2$	Vinyl formate			−58 e	−34 e	−1.6	46.2	1
$C_3H_4O_2$	2-Oxetanone		−21 e	8 e	45.5	93.8	159.3	5
$C_3H_4O_3$	Ethylene carbonate	12.7 s	37 e				247	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
C_3H_5Br	*cis*-1-Bromopropene	−100 e	−84 e	−64 e	−37 e	1.0	57.4	5
C_3H_5Br	2-Bromopropene	−112 e	−95 e	−75 e	−47 e	−9 e	48.0	5
C_3H_5Br	3-Bromopropene	−98 e	−80 e	−58 e	−28 e	12 e	69.6	5
C_3H_5Cl	*cis*-1-Chloropropene	−114 e	−100 e	−81 e	−55 e	−20.1	32.4	5
C_3H_5Cl	*trans*-1-Chloropropene		−97 e	−77 e	−52 e	−16.2	37.0	5
C_3H_5Cl	2-Chloropropene	−120 e	−106 e	−87 e	−63 e	−28.7	22.3	5
C_3H_5Cl	3-Chloropropene	−107 e	−92 e	−72.4	−46.3	−9.8	44.6	5
C_3H_5ClO	Epichlorohydrin			−21 e	11 e	53.8	115.5	5
$C_3H_5ClO_2$	Methyl chloroacetate		−28 e	−5 e	25 e	66.9	129.1	5
$C_3H_5Cl_3$	1,1,3-Trichloropropane	−51 e	−31 e	−5 e	28 e	75.3	145.1	5
$C_3H_5Cl_3$	1,2,3-Trichloropropane			2 e	37 e	84.9	156.3	5
$C_3H_5Cl_3Si$	Trichloro-2-propenylsilane					53.0	116.5	5
C_3H_5I	3-Iodopropene	−80 e	−62 e	−39 e	−8 e	36 e	101.5	5
C_3H_5N	Propanenitrile	−69.4	−55.3	−36.0	−7.9	35.2	97.4	1,5
C_3H_5NO	Acrylamide			109.6	161 e			5
C_3H_5NO	3-Hydroxypropanenitrile	−11 e	18 e	53 e	96.1	150.3	220.8	5
C_3H_5NS	Ethyl thiocyanate	−39 e	−20 e	4 e	35 e	79.1	143.4	5
C_3H_5NS	Ethyl isothiocyanate				17.4	66 e	136 e	5
$C_3H_5N_3O_9$	Trinitroglycerol	48.6	75.7	118 e	191 e	353 e	1007 e	5
C_3H_6	Propene*	−160.6	−149.0	−134.3	−114.9	−88.2	−47.9	1,5
C_3H_6	Cyclopropane			−124 e	−104 e	−75.7	−33.1	1
C_3H_6BrCl	1-Bromo-3-chloropropane	−51 e	−31 e	−6 e	28 e	74.1	142.9	5
$C_3H_6Br_2$	1,2-Dibromopropane	−46 e	−26 e	−2 e	31 e	75.3	139.5	5
$C_3H_6Br_2$	1,3-Dibromopropane	−30 e	−9 e	17 e	52 e	98.7	166.8	5
$C_3H_6Cl_2$	1,1-Dichloropropane				−14 e	27.0	87.7	5
$C_3H_6Cl_2$	1,2-Dichloropropane	−78 e	−61 e	−38.1	−8.1	33.7	95.9	5
$C_3H_6Cl_2$	1,3-Dichloropropane	−65 e	−46 e	−22 e	10 e	54.0	119.9	5
$C_3H_6Cl_2$	2,2-Dichloropropane				−28 e	10.8	68.9	5
$C_3H_6Cl_2O$	1,3-Dichloro-2-propanol			21.8	59.0	107.6	173.9	5
$C_3H_6N_2O_4$	1,1-Dinitropropane	−9 e	12 e	39 e	73.2	120 e	187 e	5
C_3H_6O	Allyl alcohol	−63 e	−48 e	−21.9	6.8	44.5	96.2	5
C_3H_6O	Methyl vinyl ether			−114 e	−89 e	−52.7	4.6	1
C_3H_6O	Propanal			−69 e	−42 e	−6 e	47.7	1
C_3H_6O	Acetone	−95	−81.8	−62.8	−35.6	1.3	55.7	1,5
C_3H_6O	Methyloxirane	−109 e	−95 e	−76 e	−51.5	−17.2	33.9	5
$C_3H_6O_2$	Propanoic acid			0 e	35.1	79.9	140.8	1,5
$C_3H_6O_2$	Ethyl formate		−80 e	−61 e	−35 e	1 e	54.0	1
$C_3H_6O_2$	Methyl acetate	−95 e	−79 e	−59 e	−33 e	3.3	56.6	1
$C_3H_6O_2$	1,3-Dioxolane		−72 e	−50 e	−22 e	17.0	75.3	1
$C_3H_6O_3$	1,3,5-Trioxane					53 e	113.7	1
C_3H_6S	Thietane		−62 e	−40 e	−9 e	32.5	94.5	5
C_3H_7Br	1-Bromopropane	−95 e	−78 e	−57 e	−28 e	11.6	70.6	1
C_3H_7Br	2-Bromopropane		−84 e	−65 e	−39.6	−1.7	59.1	1,5
C_3H_7Cl	1-Chloropropane	−106 e	−90 e	−71 e	−44.5	−8.1	46.2	1
C_3H_7Cl	2-Chloropropane		−91 e	−74 e	−51.1	−17.8	35.4	1,5
C_3H_7ClO	2-Chloro-1-propanol				23 e	63.8	125.7	5
C_3H_7F	1-Fluoropropane	−133 e	−120 e	−103 e	−80.7	−49.4	−2.8	5
C_3H_7I	1-Iodopropane	−78 e	−60 e	−37 e	−6 e	36.9	102.0	5
C_3H_7I	2-Iodopropane	−89 e	−71 e	−47 e	−16.3	26.5	89.2	5
C_3H_7N	Allylamine		−88 e	−65 e	−37 e	0.4	52 e	5
C_3H_7NO	*N,N*-Dimethylformamide	−39 e	−20 e	5 e	38.0	83.9	152.6	1
C_3H_7NO	*N*-Methylacetamide	−13.3 s	13 s	43 e	83.8	136.1	206.3	5
$C_3H_7NO_2$	1-Nitropropane	−56 e	−37 e	−13 e	20 e	64.8	130.8	1
$C_3H_7NO_2$	2-Nitropropane		−48 e	−22 e	10.7	55.6	119.8	1
$C_3H_7NO_3$	Propyl nitrate			−23.9	6.1	48.1	111 e	5
C_3H_8	Propane*	−156.9	−145.6	−130.9	−111.4	−83.8	−42.3	1,41
C_3H_8O	1-Propanol	−54 e	−38 e	−16 e	10 e	47 e	96.9	1,5
C_3H_8O	2-Propanol	−65 e	−49 e	−28 e	−1.3	33.6	82.0	1,5
C_3H_8O	Ethyl methyl ether	−98 e	−89 e	−77 e	−60 e	−34.8	7.0	5
$C_3H_8O_2$	1,2-Propylene glycol	−11 e	13 e	42 e	78 e	125.0	187.2	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_3H_8O_2$	1,3-Propylene glycol	4 e	30 e	62 e	101 e	149.9	214.0	5
$C_3H_8O_2$	Ethylene glycol monomethyl ether	−57 e	−37 e	−12 e	21 e	63.8	124.3	1
$C_3H_8O_2$	Dimethoxymethane	−93 e	−81 e	−64 e	−42 e	−9.3	41.7	5
$C_3H_8O_3$	Glycerol	96 e	113 e	136 e	168 e	213.4	287 e	1
C_3H_8S	1-Propanethiol	−94 e	−78 e	−57 e	−29.1	9.6	67.4	1,5
C_3H_8S	2-Propanethiol	−102 e	−87 e	−67 e	−41 e	−3 e	52.2	1
C_3H_8S	Ethyl methyl sulfide	−94 e	−78 e	−57 e	−29.7	8.8	66.3	1
$C_3H_8S_2$	1,3–Propanedithiol	−53 e	−28 e	3 e	43 e	97 e	172.4	5
C_3H_9As	Trimethylarsine			−74 e	−45 e	−5.4	52.0	5
$C_3H_9BO_3$	Trimethyl borate				−14 e	15.6	67.9	5
C_3H_9BS	Methyl dimethylthioborane			−62 e	−30.4	11.4	70.7	5
C_3H_9ClSi	Trimethylchlorosilane				−37.8	0.4	57.3	5
C_3H_9N	Propylamine		−81 e	−63 e	−38.3	−4.1	46.9	1,5
C_3H_9N	Isopropylamine		−91 e	−74 e	−50.4	−17.6	31.5	1,5
C_3H_9N	Trimethylamine		−114 e	−97 e	−75.0	−43.8	2.6	1,5
C_3H_9NO	1-Amino-2-propanol			18 e	53.2	98.2	157.9	5
$C_3H_9O_4P$	Trimethyl phosphate	−31 e	−7 e	23.6	62.8	116.0	192.0	5
C_3H_9P	Trimethylphosphine			−81 e	−53 e	−15.0	37.1	5
C_3H_9Sb	Trimethylstibine			−56 e	−23.8	19 e	80 e	5
$C_3H_{10}N_2$	1,2-Propanediamine		−35.4	−12.0	18.8	61 e	119 e	5
C_3N_2O	Carbonyl dicyanide				−21.7	15.3	65.2	5
C_4Cl_6	Hexachloro-1,3-butadiene	−1 e	22 e	50 e	86.7	137.0	209.7	5
$C_4F_6O_3$	Trifluoroacetic acid anhydride			−63 e	−39 e	−7.1	38.8	5
C_4F_8	Perfluorocyclobutane						−6.2	1
C_4F_{10}	Perfluorobutane		−122 e	−105 e	−82 e	−49.8	−2.5	1,5
$C_4H_2Cl_2O_2$	*trans*-2-Butenedioyl dichloride			8.0	45.6	94.3	159.8	5
$C_4H_2Cl_2S$	2,5-Dichlorothiophene			−20 e	22 e	81.4	171 e	5
$C_4H_2O_3$	Maleic anhydride				73.7	127.9	201.7	5
C_4H_3ClS	2-Chlorothiophene		−62 e	−35 e	2 e	51.8	123 e	5
C_4H_3IS	2-Iodothiophene			−25 e	23 e	94.9	181.0	5
C_4H_4	1-Buten-3-yne			−96.1	−73.4	−41.8	4.9	5
$C_4H_4N_2$	Succinonitrile	24.8 s					266.0	5
C_4H_4O	Furan			−78 e	−54 e	−20 e	31.0	1
$C_4H_4O_2$	Diketene				19.3	63.3	126 e	5
$C_4H_4O_3$	Succinic anhydride				121 e	180.8	260.8	5
$C_4H_4O_4$	Fumaric acid	123.9 s	150 s	180 s				5
C_4H_4S	Thiophene				−17 e	23.7	83.7	5
C_4H_5Cl	2-Chloro-1,3-butadiene	−113 e	−95 e	−71 e	−41 e	0.3	59.0	5
C_4H_5ClO	2-Methyl-2-propenoyl chloride		−57 e	−35 e	−5 e	36.4	98.2	5
$C_4H_5Cl_3O_2$	Ethyl trichloroacetate			15.3	51.9	100.1	166.6	5
C_4H_5N	3-Butenenitrile	−67 e	−48 e	−23.1	9.3	53.7	118.4	5
C_4H_5N	Methylacrylonitrile				−12 e	29.0	89.8	5
C_4H_5N	Pyrrole			−8 e	24 e	66.7	129.4	1
$C_4H_5NO_2$	Methyl cyanoacetate	−3 e	19 e	48 e	84 e	134.0	204.6	5
C_4H_5NS	Allyl isothiocyanate	−45 e	−27 e	−3 e	32.1	89 e	198 e	5
C_4H_5NS	4-Methylthiazole						67.0	5
C_4H_6	1,2-Butadiene	−132 e	−117 e	−98 e	−72.8	−38.9	10.5	5
C_4H_6	1,3-Butadiene*			−106 e	−83 e	−51.9	−4.7	1
C_4H_6	1-Butyne	−125 e	−111 e	−94 e	−71.2	−39.4	7.8	1
C_4H_6	2-Butyne		−89.2 s	−73.8 s	−53.5 s	−23.9	26.6	5
$C_4H_6Cl_2O_2$	Ethyl dichloroacetate			2.6	40.1	89.1	156.3	5
C_4H_6O	Divinyl ether		−99 e	−80 e	−56 e	−22.1	28.0	5
C_4H_6O	*trans*-2-Butenal	−74 e	−56 e	−33 e	−3 e	39.7	102.4	5
C_4H_6O	3-Buten-2-one					21 e	81.0	5
C_4H_6O	Cyclobutanone			−34 e	−4 e	37.1	97 e	5
$C_4H_6O_2$	*cis*-Crotonic acid			30 e	63 e	106.7	168.9	5
$C_4H_6O_2$	*trans*-Crotonic acid				74 e	120.8	184.9	5
$C_4H_6O_2$	3-Butenoic acid	−19 e	2 e	27 e	61 e	105.6	168.6	5
$C_4H_6O_2$	Methacrylic acid			22 e	56 e	99.9	161.5	5
$C_4H_6O_2$	Vinyl acetate	−88 e	−71 e	−50 e	−22 e	16.2	72.2	1

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_4H_6O_2$	Methyl acrylate		−71 e	−48 e	−18 e	22 e	79.9	5
$C_4H_6O_2$	2,3-Butanedione					30.7	84.8	5
$C_4H_6O_2$	gamma-Butyrolactone		−17 e	24 e	72 e	130.2	203 e	5
$C_4H_6O_3$	Acetic anhydride	−44 e	−25 e	−1 e	31 e	75.1	139.7	1
$C_4H_6O_3$	Propylene carbonate	−40 e	−5 e	43 e	112 e	220 e	410 e	5
$C_4H_6O_4$	Dimethyl oxalate				50.5	98.1	163.0	5
C_4H_7Br	*trans*-1-Bromo-1-butene	−87 e	−68 e	−43.3	−11.4	31.9	94.4	5
C_4H_7Br	2-Bromo-1-butene	−87 e	−70 e	−48 e	−20 e	20.7	80.6	5
C_4H_7Br	*cis*-2-Bromo-2-butene	−90 e	−72 e	−49.0	−18.5	23.5	85.2	5
C_4H_7Br	*trans*-2-Bromo-2-butene	−86 e	−67 e	−43.4	−12.0	31.0	93.5	5
$C_4H_7Br_3$	1,2,3-Tribromobutane	0 e	23 e	53 e	91 e	143.7	219.5	5
$C_4H_7Br_3$	1,2,4-Tribromobutane	−3 e	20 e	49 e	87 e	139.4	214.5	5
C_4H_7Cl	3-Chloro-1-butene			−64 e	−36 e	4 e	63.6	5
C_4H_7Cl	*cis*-2-Chloro-2-butene	−100 e	−83 e	−62 e	−34 e	6 e	66.4	5
C_4H_7Cl	*trans*-2-Chloro-2-butene	−102 e	−86 e	−65 e	−37 e	3 e	62.2	5
C_4H_7Cl	3-Chloro-2-methylpropene		−75 e	−54 e	−25 e	13.8	71.5	5
$C_4H_7ClO_2$	Ethyl chloroacetate			−2.6	32.6	79.1	143.8	5
C_4H_7N	Butanenitrile	−67 e	−48 e	−24 e	8 e	52.3	117.2	1
C_4H_8	1-Butene	−139.0	−125.2	−107.8	−85.3	−53.7	−6.6	1,5
C_4H_8	*cis*-2-Butene	−131.2	−117.4	−99.8	−76.7	−44.8	3.4	1,5
C_4H_8	*trans*-2-Butene			−102 e	−80 e	−47.6	0.6	1
C_4H_8	Isobutene	−139.1	−125.5	−108.2	−85.5	−54.5	−7.3	1,5
C_4H_8	Cyclobutane				−71.8	−38.1	12.1	5
C_4H_8	Methylcyclopropane	−130 e	−116 e	−99.3	−76.3	−44.2	4.2	5
$C_4H_8Br_2$	1,2-Dibromobutane	−54 e	−30 e	0.4	39.6	92.1	166.1	5
$C_4H_8Br_2$	1,4-Dibromobutane	−13 e	9 e	37 e	74 e	124.0	196.5	5
$C_4H_8Cl_2$	1,1-Dichlorobutane			−25 e	6 e	49.3	113.4	5
$C_4H_8Cl_2$	1,2-Dichlorobutane			−28.4	5.8	53.1	123.1	5
$C_4H_8Cl_2$	1,4-Dichlorobutane		−26 e	0 e	35 e	82.4	153.4	5
$C_4H_8Cl_2$	2,2-Dichlorobutane		−58 e	−35 e	−5 e	37.8	102.1	5
$C_4H_8Cl_2O$	Bis(2-chloroethyl) ether	−32 e	−9 e	19.8	56.9	106.9	177.9	5
C_4H_8O	Ethyl vinyl ether		−102 e	−81 e	−53.1	−16.5	34.7	5
C_4H_8O	1,2-Epoxybutane	−135 e	−114 e	−87 e	−53 e	−5.5	62.1	5
C_4H_8O	Butanal	−88 e	−72 e	−50 e	−22 e	16.6	74.5	1,5
C_4H_8O	Isobutanal			−56 e	−29 e	8 e	63.8	1
C_4H_8O	2-Butanone	−85 e	−68 e	−46 e	−18.1	21.2	79.2	1
C_4H_8O	Tetrahydrofuran	−94 e	−78 e	−57.3	−29.8	9 e	65.6	1
$C_4H_8O_2$	Butanoic acid			12.9	52.2	101.4	163.3	1,5
$C_4H_8O_2$	2-Methylpropanoic acid	−30.1	−8.2	18.1	50.5	92.9	154.0	5
$C_4H_8O_2$	Propyl formate	−78 e	−62 e	−42 e	−15.1	23.0	80.4	1,5
$C_4H_8O_2$	Isopropyl formate	−80 e	−65 e	−47 e	−22.2	13.2	67.7	5
$C_4H_8O_2$	Ethyl acetate	−83 e	−66 e	−45 e	−18 e	20.4	76.8	1
$C_4H_8O_2$	Methyl propanoate	−80 e	−64 e	−43 e	−15.8	22.2	79.0	1
$C_4H_8O_2$	*cis*-2-Butene-1,4-diol	17 e	44 e	77 e	117.4	168.5	234.9	5
$C_4H_8O_2$	1,3-Dioxane			−37 e	−3 e	43.4	106.0	5
$C_4H_8O_2$	1,4-Dioxane					39.6	101.0	1
$C_4H_8O_2S$	Sulfolane		49 e	87 e	135 e	198.0	283.5	5
C_4H_8S	Tetrahydrothiophene	−66 e	−47 e	−23 e	9.4	54.1	120.5	1
C_4H_9Br	1-Bromobutane	−68.4	−53.9	−34.1	−5.4	37.6	101.1	1,5
C_4H_9Br	2-Bromobutane	−86 e	−68 e	−46 e	−16 e	26.6	90.7	5
C_4H_9Br	1-Bromo-2-methylpropane	−85 e	−68 e	−46 e	−16 e	26.8	91.1	5
C_4H_9Br	2-Bromo-2-methylpropane					11.7	72.4	1,5
C_4H_9Cl	1-Chlorobutane	−87 e	−71 e	−49 e	−21 e	18.4	78.1	1
C_4H_9Cl	2-Chlorobutane	−96 e	−80 e	−59 e	−31.0	8.5	67.9	1
C_4H_9Cl	1-Chloro-2-methylpropane	−94 e	−78 e	−56.6	−28.7	10.2	68.5	5
C_4H_9Cl	2-Chloro-2-methylpropane					−4.2	50.3	5
$C_4H_9Cl_3Si$	Butyltrichlorosilane					77.2	148.4	5
C_4H_9F	1-Fluorobutane	−114 e	−99 e	−80 e	−55 e	−20.0	32.1	5
C_4H_9F	2-Fluorobutane	−117 e	−103 e	−85 e	−60.7	−26.7	24.7	5
C_4H_9I	1-Iodobutane	−62 e	−43 e	−19 e	14 e	60.5	130.0	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
C_4H_9I	2-Iodobutane	−70 e	−51 e	−27 e	5 e	50 e	119.5	5
C_4H_9I	1-Iodo-2-methylpropane		−47 e	−21.4	12.0	56.8	120.0	5
C_4H_9I	2-Iodo-2-methylpropane	−75.1 s	−58.8 s	−39.5 s	-5.2	41 e	100.0	5
C_4H_9N	Pyrrolidine		−59 e	−38 e	−10 e	28.5	86.2	1
C_4H_9NO	*N*-Methylpropanamide				81.1	105 e		5
C_4H_9NO	*N,N*-Dimethylacetamide	−8 e	8 e	28.0	56.4	98.2	165.7	1
C_4H_9NO	2-Butanone oxime		−18 e	7 e	38.9	81.9	142.9	5
C_4H_9NO	Morpholine				21 e	64.5	128.5	1
$C_4H_9NO_3$	Isobutyl nitrate			−18 e	15.1	59.2	123.0	5
C_4H_{10}	Butane*	−134.3	−121.0	−103.9	−81.1	−49.1	−0.8	1,41
C_4H_{10}	Isobutane*		−129.0	−113.0	−90.9	−59.4	−12.0	1,41
$C_4H_{10}O$	1-Butanol	−37 e	−20 e	0 e	28 e	64 e	117.4	1
$C_4H_{10}O$	2-Butanol	−50 e	−34 e	−14 e	12.6	48.2	99.2	1,5
$C_4H_{10}O$	2-Methyl-1-propanol	−39 e	−24 e	−5 e	20.9	56.0	107.6	1,5
$C_4H_{10}O$	2-Methyl-2-propanol					34.4	82.1	1,5
$C_4H_{10}O$	Diethyl ether	−111 e	−96 e	−77 e	−52.6	−17.8	34.1	1
$C_4H_{10}O$	Methyl propyl ether				−40 e	−11.3	38.7	5
$C_4H_{10}O$	Isopropyl methyl ether				−56 e	−21.2	30.4	5
$C_4H_{10}O_2$	1,3-Butanediol	−4 e	23 e	55 e	94 e	142.9	206.1	5
$C_4H_{10}O_2$	1,4-Butanediol		45 e	77 e	116 e	164.7	227.6	5
$C_4H_{10}O_2$	2,3-Butanediol		15 e	43 e	77 e	121.2	180.3	5
$C_4H_{10}O_2$	Ethylene glycol monoethyl ether	−49 e	−29 e	−3 e	30 e	73.6	135.3	1
$C_4H_{10}O_2$	Ethylene glycol dimethyl ether			−44 e	−15 e	25.2	85.2	1
$C_4H_{10}O_2$	Dimethylacetal	−89 e	−74 e	−55 e	−29 e	7.7	64.1	5
$C_4H_{10}O_2$	Diethylperoxide				−39 e	3.6	65.0	5
$C_4H_{10}O_2S$	Bis(2-hydroxyethyl) sulfide			31 e	114.2		282.0	5
$C_4H_{10}O_3$	Diethylene glycol	35 e	58 e	86 e	123 e	173.6	245.2	1
$C_4H_{10}O_4S$	Diethyl sulfate		3 e	36 e	79 e	134 e	208.3	5
$C_4H_{10}S$	1-Butanethiol	−77 e	−59 e	−37 e	−6 e	35.4	98.0	5
$C_4H_{10}S$	2-Butanethiol	−86 e	−69 e	−47 e	−17 e	23.4	84.5	5
$C_4H_{10}S$	2-Methyl-1-propanethiol		−66 e	−44 e	−15 e	26.5	88.1	5
$C_4H_{10}S$	2-Methyl-2-propanethiol					5.8	63.8	5
$C_4H_{10}S$	Diethyl sulfide	−80 e	−62 e	−40 e	−10.8	30.3	91.7	1
$C_4H_{10}S$	Methyl propyl sulfide	−78 e	−61 e	−38 e	−8 e	33.1	95.1	5
$C_4H_{10}S$	Isopropyl methyl sulfide	−85 e	−68 e	−46 e	−17 e	23.4	84.3	5
$C_4H_{10}S_2$	1,4-Butanedithiol	−17 e	5 e	32 e	69.1	119.9	195.1	5
$C_4H_{10}S_2$	Diethyl disulfide	−46 e	−26 e	0 e	35 e	82.4	153.5	5
$C_4H_{11}N$	Butylamine			−46 e	−18.1	20.0	75.9	5
$C_4H_{11}N$	*sec*-Butylamine			−55 e	−29.1	7.5	62.3	5
$C_4H_{11}N$	*tert*-Butylamine			−67 e	−42.4	−8.1	43.7	5
$C_4H_{11}N$	Isobutylamine	−85 e	−70 e	−50 e	−24.5	12.0	67.3	5
$C_4H_{11}N$	Diethylamine			−46 e	−26 e	5 e	55.2	1
$C_4H_{11}NO$	*N,N*-Dimethylethanolamine	−52 e	−31 e	−6 e	27 e	70.9	133 e	5
$C_4H_{11}NO_2$	Diethanolamine	53 e	77 e	107 e	146 e	197.3	268 e	5
$C_4H_{12}BN$	(Dimethylamino)dimethyl-borane		−81 e	−60.1	−31.9	7.0	64.2	5
$C_4H_{12}Cl_2OSi_2$	1,3-Dichloro-1,1,3,3-tetramethyldisiloxane		−33 e	−9 e	23.8	69.1	136.5	5
$C_4H_{12}O_4Si$	Tetramethyl silicate				14.4	59.3	119.7	5
$C_4H_{12}Si$	Tetramethylsilane			−83 e	−59 e	−25 e	26.7	5
$C_4H_{12}Sn$	Tetramethylstannane			−55.0	−25.6	16.6	77.7	5
$C_4H_{13}N_3$	Diethylenetriamine	−10 e	13 e	43 e	80 e	129.6	198 e	5
C_4NiO_4	Nickel carbonyl					−12	42	4
C_5F_{12}	Perfluoropentane				−54.7	−20.9	28.6	5
C_5FeO_5	Iron pentacarbonyl				0	44	105	4
C_5H_4ClN	2-Chloropyridine			7.4	45.8	97.3	169.9	5
$C_5H_4O_2$	Furfural	−26 e	−8 e	16 e	47 e	92.4	161.4	1
C_5H_5N	Pyridine			−23 e	8 e	51.0	114.9	1
C_5H_6	1,3-Cyclopentadiene			−77 e	−51 e	−14 e	39.8	5
$C_5H_6N_2$	Pentanedinitrile	24.1	52 e	85 e	126 e	178 e	245 e	5
C_5H_6O	2-Methylfuran			−66 e	−35 e	6 e	64.5	1

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_5H_6O_2$	Furfuryl alcohol	−30 e	−5 e	25 e	62.6	109.3	169.7	5
C_5H_6S	2-Methylthiophene		−58 e	−32 e	2 e	47.9	112.2	1
C_5H_6S	3-Methylthiophene		−53 e	−28 e	6 e	50.6	115.1	1
C_5H_7N	1-Methylpyrrole				8 e	49.9	112.3	5
$C_5H_7NO_2$	Ethyl cyanoacetate	16 e	39 e	67.0	102.1	146.7	205.6	5
C_5H_8	1,2-Pentadiene	−109 e	−93 e	−73 e	−46.1	−9.7	44.5	5
C_5H_8	*cis*-1,3-Pentadiene	−109 e	−93 e	−73 e	−47.0	−10.5	43.7	1,5
C_5H_8	*trans*-1,3-Pentadiene			−75 e	−49.0	−13 e	42 e	1
C_5H_8	1,4-Pentadiene	−120 e	−105 e	−86 e	−60.9	−26.2	25.6	5
C_5H_8	2,3-Pentadiene	−106 e	−90 e	−70 e	−42.9	−6.3	47.9	5
C_5H_8	3-Methyl-1,2-butadiene	−111 e	−95 e	−75 e	−49.2	−13.1	40.4	5
C_5H_8	2-Methyl-1,3-butadiene	−115 e	−100 e	−81 e	−55.4	−19.7	33.7	1,5
C_5H_8	1-Pentyne			−75 e	−49.1	−13.5	39.9	5
C_5H_8	2-Pentyne	−100 e	−85 e	−65 e	−37.9	−0.5	55.7	5
C_5H_8	3-Methyl-1-butyne			−82 e	−57.5	−23.1	28.6	5
C_5H_8	Cyclopentene	−109 e	−94 e	−74 e	−48 e	−11.1	43.8	5
C_5H_8	Spiropentane	−110 e	−95 e	−76 e	−51 e	−15 e	38.6	5
C_5H_8O	3-Methyl-3-buten-2-one			−35 e	−5 e	36.0	97.3	5
C_5H_8O	Cyclopropyl methyl ketone		−57 e	−31 e	3 e	49 e	112 e	5
C_5H_8O	Cyclopentanone		−39 e	−14 e	19 e	64 e	130.3	1
C_5H_8O	3,4-Dihydro-2H-pyran				−22 e	22.0	84.9	5
$C_5H_8O_2$	4-Pentenoic acid	0 e	19 e	44 e	77 e	122.0	187.5	5
$C_5H_8O_2$	Vinyl propanoate					31.2	94 e	5
$C_5H_8O_2$	Ethyl acrylate		−55 e	−32.7	−2.8	38.5	99.2	5
$C_5H_8O_2$	Methyl methacrylate			−31 e	−1 e	39.7	100.0	1
$C_5H_8O_2$	2,4-Pentanedione			−5 e	24.7	67.8	137.4	1
$C_5H_8O_2$	Tetrahydro-2*H*-pyran-2-one		5 e	35.1	74.4	128.3	207.0	5
$C_5H_8O_3$	Methyl acetoacetate				50.1	101.1	171.3	5
$C_5H_8O_4$	Glutaric acid		121 e	153.2	191.9	240.3	302.5	5
$C_5H_8O_4$	Dimethyl malonate	−22 e	1 e	30.0	66.7	114.7	180.2	5
$C_5H_9ClO_2$	Ethyl 2-chloropropanoate			1.4	36.4	82.5	146.0	5
$C_5H_9ClO_2$	Isopropyl chloroacetate			−2 e	35.0	83.3	148.1	5
C_5H_9N	Pentanenitrile	−54 e	−34 e	−8 e	26 e	72.2	140.9	1
C_5H_9N	2,2-Dimethylpropanenitrile					41.1	104.8	5
C_5H_9NO	*N*-Methyl-2-pyrrolidone	1 e	24 e	53.1	92.3	147.2	229 e	5
C_5H_{10}	1-Pentene	−118.9	−103.4	−84.0	−58.8	−23.3	29.6	1,5
C_5H_{10}	*cis*-2-Pentene	−113.8	−98.1	−78.4	−52.7	−16.8	36.6	1,5
C_5H_{10}	*trans*-2-Pentene	−114.5	−98.9	−79.1	−53.3	−17.5	36.0	1,5
C_5H_{10}	2-Methyl-1-butene	−117.7	−102.2	−82.7	−57.2	−21.9	30.8	1,5
C_5H_{10}	3-Methyl-1-butene	−125.0	−110.1	−91.2	−66.7	−32.1	19.7	1,5
C_5H_{10}	2-Methyl-2-butene	−113.4	−97.6	−77.7	−51.6	−15.8	38.2	1,5
C_5H_{10}	Cyclopentane			−77.0	−45.4	−7.1	48.8	5
C_5H_{10}	Ethylcyclopropane	−118 e	−102 e	−83 e	−57 e	−20 e	35.5	5
C_5H_{10}	*cis*-1,2-Dimethylcyclo-propane	−118 e	−103 e	−83 e	−57 e	−20 e	36.6	5
C_5H_{10}	*trans*-1,2-Dimethylcyclo-propane	−122 e	−108 e	−89 e	−63 e	−27 e	27.8	5
$C_5H_{10}Br_2$	1,5-Dibromopentane	1 e	25 e	54 e	93 e	145.6	221.8	5
$C_5H_{10}Cl_2$	1,2-Dichloropentane				30 e	77.4	147.8	5
$C_5H_{10}Cl_2$	1,5-Dichloropentane	−31 e	−10 e	17 e	54 e	104.1	178.9	5
$C_5H_{10}N_2$	3-(Dimethylamino)-propanenitrile				51.1	101.8	171.4	5
$C_5H_{10}O$	Cyclopentanol		−13 e	11.5	42.2	82.5	140.0	5
$C_5H_{10}O$	Allyl ethyl ether			−56 e	−28.7	9.8	67.2	5
$C_5H_{10}O$	Pentanal	−71 e	−53 e	−31 e	−1 e	40.8	102.6	5
$C_5H_{10}O$	2-Pentanone				−1 e	40.3	101.9	1,5
$C_5H_{10}O$	3-Pentanone			−31 e	−1 e	40 e	101.6	1
$C_5H_{10}O$	3-Methyl-2-butanone	−69 e	−54 e	−34 e	−6.9	32.2	94.0	1,5
$C_5H_{10}O$	Tetrahydropyran				−15 e	26.0	88 e	5
$C_5H_{10}O$	2-Methyltetrahydrofuran				−20 e	19.7	79.8	5
$C_5H_{10}O_2$	Pentanoic acid	−7.4	15.3	42.7	76.3	122.1	185.7	5
$C_5H_{10}O_2$	2-Methylbutanoic acid	−10 e	10 e	36 e	69 e	112.8	175.2	5
$C_5H_{10}O_2$	3-Methylbutanoic acid	−15.8	4 e	30.0	64.7	110.6	176.1	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_5H_{10}O_2$	Butyl formate			−29 e	2 e	44.4	105.7	5
$C_5H_{10}O_2$	Isobutyl formate	−69 e	−53 e	−31 e	−3 e	37.4	97.6	5
$C_5H_{10}O_2$	Propyl acetate	−69 e	−51 e	−29 e	0 e	40.9	101.2	1
$C_5H_{10}O_2$	Isopropyl acetate		−61 e	−40 e	−11 e	29.8	88.2	5
$C_5H_{10}O_2$	Ethyl propanoate	−69 e	−52 e	−30 e	−1 e	38.9	98.7	1
$C_5H_{10}O_2$	Methyl butanoate	−68 e	−50 e	−28 e	0.9	41.7	102.3	5
$C_5H_{10}O_2$	Methyl isobutanoate	−83 e	−65 e	−41 e	−11 e	31 e	92.1	5
$C_5H_{10}O_2$	Tetrahydrofurfuryl alcohol	−40 e	−16 e	15 e	55 e	106 e	176.8	5
$C_5H_{10}O_3$	Diethyl carbonate		−42 e	−17 e	17 e	61.6	125.9	5
$C_5H_{10}O_3$	Ethylene glycol monomethyl ether acetate	−47 e	−26 e	0 e	34 e	79.4	144.1	5
$C_5H_{10}S$	Thiacyclohexane				24 e	71.1	141.2	5
$C_5H_{10}S$	Cyclopentanethiol				18 e	64 e	131.7	5
$C_5H_{11}Br$	1-Bromopentane	−60 e	−41 e	−16 e	16 e	61.5	129.1	5
$C_5H_{11}Br$	2-Bromopentane	−69 e	−51 e	−27 e	5 e	49.7	116.9	5
$C_5H_{11}Br$	3-Bromopentane	−68 e	−50 e	−26 e	6 e	50.8	118.1	5
$C_5H_{11}Br$	1-Bromo-3-methylbutane	−67 e	−49 e	−25 e	8 e	52.4	119.9	5
$C_5H_{11}Cl$	1-Chloropentane	−73 e	−55 e	−32 e	−1 e	42.5	107.9	5
$C_5H_{11}Cl$	2-Chloropentane	−80 e	−62 e	−39 e	−9 e	33.2	96.1	5
$C_5H_{11}Cl$	3-Chloropentane	−77 e	−60 e	−37 e	−7 e	34.9	97.3	5
$C_5H_{11}Cl$	2-Chloro-2-methylbutane			−52 e	−21 e	21.8	85.2	5
$C_5H_{11}Cl$	1-Chloro-2,2-dimethyl-propane				−17 e	23.5	83.9	5
$C_5H_{11}F$	1-Fluoropentane	−97 e	−80 e	−60 e	−32 e	5.7	62.4	5
$C_5H_{11}I$	1-Iodopentane	−47 e	−27 e	−1 e	34 e	83.0	156.5	5
$C_5H_{11}I$	1-Iodo-3-methylbutane		−34 e	−6.6	28.8	77.3	147.8	5
$C_5H_{11}N$	Cyclopentylamine	−66 e	−48 e	−26 e	4 e	45.8	108 e	5
$C_5H_{11}N$	Piperidine				2 e	43.3	105.8	5
$C_5H_{11}N$	*N*-Methylpyrrolidine				−23 e	18.5	78 e	5
$C_5H_{11}NO_3$	3-Methylbutyl nitrate		−26 e	1.0	35.5	81.7	147.0	5
C_5H_{12}	Pentane**	−115.5	−99.8	−80.0	−54.0	−18.1	35.7	16
C_5H_{12}	Isopentane	−119 e	−105 e	−86 e	−61 e	−26 e	27.5	1
C_5H_{12}	Neopentane*		−107.5 s	−90.8 s	−68.8 s	−38.5 s	9.2	1,5
$C_5H_{12}N_2O$	Tetramethylurea			20.7	58.0	106.7	179.5	5
$C_5H_{12}O$	1-Pentanol	−27 e	−10 e	12 e	41 e	79.8	137.4	5
$C_5H_{12}O$	2-Pentanol	−35 e	−19 e	1 e	28.0	64.9	118.7	1
$C_5H_{12}O$	3-Pentanol	−41 e	−25 e	−4 e	24 e	61.1	114.9	5
$C_5H_{12}O$	2-Methyl-1-butanol	−27 e	−11 e	9 e	36.2	73.4	128.3	1
$C_5H_{12}O$	3-Methyl-1-butanol	−22 e	−7 e	13 e	39.1	75.7	130.1	5
$C_5H_{12}O$	2-Methyl-2-butanol			−5 e	17.7	50.6	101.7	1,5
$C_5H_{12}O$	3-Methyl-2-butanol			−3 e	22.7	58.2	111.1	5
$C_5H_{12}O$	2,2-Dimethyl-1-propanol					59.2	112.7	5
$C_5H_{12}O$	Butyl methyl ether			−54 e	−27 e	12 e	69.8	1
$C_5H_{12}O$	Methyl *tert*-butyl ether			−66 e	−39 e	−2 e	54.8	1
$C_5H_{12}O$	Ethyl propyl ether	−92 e	−77 e	−57 e	−30.5	6.7	63.4	1,5
$C_5H_{12}O_2$	1,5-Pentanediol	25 e	52 e	85 e	125 e	175.1	238.9	5
$C_5H_{12}O_2$	Ethylene glycol monopropyl ether				40 e	85.6	149.3	5
$C_5H_{12}O_2$	Diethoxymethane		−65 e	−43 e	−14 e	27.3	87.7	5
$C_5H_{12}O_3$	Diethylene glycol monomethyl ether		12 e	40 e	76 e	124.2	193.7	1
$C_5H_{12}S$	1-Pentanethiol	−60 e	−41 e	−17 e	15 e	60 e	126.2	1
$C_5H_{12}S$	2-Pentanethiol	−70 e	−52 e	−28 e	3 e	46.6	111.9	5
$C_5H_{12}S$	3-Pentanethiol	−70 e	−51 e	−28 e	4 e	47.7	113.4	5
$C_5H_{12}S$	2-Methyl-1-butanethiol				8.0	52.3	118.5	5
$C_5H_{12}S$	3-Methyl-1-butanethiol				7.8	51.9	117.9	5
$C_5H_{12}S$	2-Methyl-2-butanethiol				−8.0	34.6	98.7	5
$C_5H_{12}S$	Butyl methyl sulfide		−43 e	−19 e	13 e	57 e	123.0	1
$C_5H_{12}S$	*tert*-Butyl methyl sulfide				−7.8	34.7	98.4	5
$C_5H_{12}S$	Ethyl propyl sulfide	−64 e	−46 e	−23 e	9 e	52.7	118.0	5
$C_5H_{12}S$	Ethyl isopropyl sulfide	−72 e	−54 e	−31 e	0 e	42.7	106.9	5
$C_5H_{13}N$	Pentylamine		−52 e	−29 e	1 e	42.8	104.0	5
C_6BrF_5	Bromopentafluorobenzene			−10 e	23 e	68 e	136.0	5
C_6ClF_5	Chloropentafluorobenzene		−44 e	−21 e	11 e	53.8	117.6	1

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_6Cl_3F_3$	1,3,5-Trichloro-2,4,6-trifluorobenzene	−19 e	4 e	32 e	70 e	121.7	197.9	1
C_6F_6	Hexafluorobenzene		−56.9 s	−36 s	−11.5 s	22.6	79.9	1,5
C_6F_{12}	Perfluorocyclohexane				−46.2 s	−7.6 s	48.9 s	5
C_6F_{14}	Perfluorohexane		−75 e	−57 e	−32 e	2.8	56.8	5
C_6F_{14}	Perfluoro-2-methylpentane				−33 e	2.9	57.1	5
C_6F_{14}	Perfluoro-3-methylpentane	−95 e	−80 e	−60 e	−34 e	2.8	57.9	5
C_6F_{14}	Perfluoro-2,3-dimethylbutane					4.3	59.3	5
C_6HF_5	Pentafluorobenzene			−41 e	−13 e	27 e	85.3	5
C_6HF_5O	Pentafluorophenol				39 e	82 e	145.2	5
$C_6H_2F_4$	1,2,3,4-Tetrafluorobenzene			−36 e	−7 e	33.8	94.0	1
$C_6H_2F_4$	1,2,3,5-Tetrafluorobenzene			−43 e	−14 e	25.5	84.1	1
$C_6H_2F_4$	1,2,4,5-Tetrafluorobenzene					30.7	89.9	1
$C_6H_3Cl_3O$	2,4,6-Trichlorophenol			71.8	114.0	169.5	245.7	5
$C_6H_3F_3$	1,3,5-Trifluorobenzene					18.2	75.0	5
$C_6H_4Br_2$	*m*-Dibromobenzene	−7 e	16 e	44 e	83 e	137.0	218.2	5
$C_6H_4ClNO_2$	1-Chloro-4-nitrobenzene	15.4 s	35.8 s		97 e	156.0	238 e	5
$C_6H_4Cl_2$	*o*-Dichlorobenzene		−13 e	16.3	53.9	104.6	180.0	1,5
$C_6H_4Cl_2$	*m*-Dichlorobenzene		−22 e	8.0	46.7	97.8	172.5	1,5
$C_6H_4Cl_2$	*p*-Dichlorobenzene	−45.5 s	−21.8 s	8 s	46.7 s	99.0	173.6	1,5
$C_6H_4O_2$	*p*-Benzoquinone	−4.1 s	17.8 s	43.5 s	74.3 s	111.6 s		5
$C_6H_5AsCl_2$	Dichlorophenylarsine	6.9	35.2	70 e	113 e	170 e	245 e	5
C_6H_5Br	Bromobenzene		−25 e	1 e	34.9	83.1	155.4	1
C_6H_5Cl	Chlorobenzene		−43 e	−17 e	16.8	62.9	131.3	1,5
C_6H_5ClO	*o*-Chlorophenol				45.8	97.9	173.9	5
C_6H_5ClO	*m*-Chlorophenol			39.7	80.2	135.1	213.4	5
C_6H_5ClO	*p*-Chlorophenol			45.0	86.5	142.0	219.9	5
$C_6H_5Cl_3Si$	Trichlorophenylsilane			33 e	70.2	122.6	201 e	5
C_6H_5F	Fluorobenzene				−16.9	24.2	84.4	1
C_6H_5I	Iodobenzene	−30 e	−7 e	20.9	58.5	110.6	187.8	1
$C_6H_5NO_2$	Nitrobenzene		10 e	40 e	78 e	132 e	210.3	1
$C_6H_5NO_3$	*p*-Nitrophenol	72.6 s	97.4 s					5
C_6H_6	1,5-Hexadien-3-yne	−82 e	−66 e	−44.3	−16.0	23.7	83.6	5
C_6H_6	Benzene**			−40 s	−15.1 s	20.0	79.7	1,5
C_6H_6ClN	*o*-Chloroaniline		10 e	39.0	75.2	131.4	208.3	5
C_6H_6ClN	*m*-Chloroaniline	−5 e	19.7	49.4	94.2	162 e	1069 e	5
$C_6H_6N_2O_2$	*p*-Nitroaniline	87.8 s			192.0	252.6	331.2	5
C_6H_6O	Phenol	−9.7 s	9.6 s	34.1 s	68.9	113.7	181.4	1,5
$C_6H_6O_3$	1,2,3-Benzenetriol				162.0	222.8	308.3	5
C_6H_6S	Benzenethiol		−15 e	12 e	47 e	96.0	168.6	5
C_6H_7N	Aniline		−2.5	26.7	63.5	112.5	183.5	1,5
C_6H_7N	2-Methylpyridine	−56.5	−37.8	−13.9	18.3	62.9	129.0	1,5
C_6H_7N	3-Methylpyridine			−5 e	28.8	75.2	143.7	1
C_6H_7N	4-Methylpyridine	−58.2 s	−43.1 s	−3.9 s	29.6	76.1	144.9	1,5
C_6H_8	*cis*-1,3,5-Hexatriene					21 e	78 e	5
C_6H_8	1,3-Cyclohexadiene	−88 e	−71 e	−50 e	−21 e	19 e	79.9	5
C_6H_8	1,4-Cyclohexadiene				−15 e	27.3	85.0	5
$C_6H_8N_2$	Adiponitrile	30 e	61 e	100 e	148.6	211.8	297 e	5
$C_6H_8N_2$	*m*-Phenylenediamine			94.5	140.2	200.8	285.0	5
$C_6H_8N_2$	Phenylhydrazine		38 e	69 e	109 e	163.9	242.5	5
$C_6H_8O_4$	Dimethyl maleate		5 e	36 e	76 e	127.3	197 e	5
C_6H_8S	2,5-Dimethylthiophene		−43 e	−16 e	20 e	67.5	134.8	5
C_6H_{10}	*trans*-1,3-Hexadiene	−86 e	−70 e	−51 e	−24 e	14 e	72 e	5
C_6H_{10}	*trans*-1,4-Hexadiene	−98 e	−81 e	−60 e	−33 e	7 e	65 e	5
C_6H_{10}	1,5-Hexadiene	−99 e	−84 e	−64 e	−37 e	0.9	59.2	5
C_6H_{10}	*cis,cis*-2,4-Hexadiene					18 e	79.6	5
C_6H_{10}	*trans,cis*-2,4-Hexadiene	−89 e	−73 e	−52 e	−23 e	18 e	79.6	5
C_6H_{10}	*trans,trans*-2,4-Hexadiene				−23 e	18 e	79.6	5
C_6H_{10}	*trans*-2-Methyl-1,3-pentadiene	−92 e	−75 e	−54 e	−26 e	14 e	75.6	5
C_6H_{10}	2,3-Dimethyl-1,3-butadiene			−59 e	−30 e	9.7	68.1	5
C_6H_{10}	1-Hexyne	−91 e	−75 e	−54 e	−26 e	12.8	71.0	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
C_6H_{10}	2-Hexyne	−84 e	−67 e	−46 e	−17 e	23.6	84.1	5
C_6H_{10}	3-Hexyne	−86 e	−69 e	−48 e	−19.1	21.0	81.0	1,5
C_6H_{10}	4-Methyl-1-pentyne	−97 e	−81 e	−61 e	−34 e	4.1	60.7	5
C_6H_{10}	4-Methyl-2-pentyne	−91 e	−74 e	−54 e	−26 e	13.8	72.7	5
C_6H_{10}	Cyclohexene	−87 e	−70 e	−49 e	−19 e	21 e	82.6	1
$C_6H_{10}Cl_2$	1,1-Dichlorocyclohexane	−39 e	−19 e	8 e	43 e	93.5	170.5	5
$C_6H_{10}Cl_2$	*cis*-1,2-Dichlorocyclohexane			27 e	69 e	125.7	206.2	5
$C_6H_{10}O$	4-Methyl-4-penten-2-one	−59 e	−41 e	−17 e	14 e	57.0	121.0	5
$C_6H_{10}O$	Cyclohexanone		−25 e	1 e	36 e	84 e	155.2	1
$C_6H_{10}O$	Mesityl oxide	−56 e	−37 e	−13 e	19 e	63.5	129.3	5
$C_6H_{10}O_2$	Vinyl butanoate					53 e	114.5	5
$C_6H_{10}O_2$	Ethyl methacrylate				8 e	53.2	116.8	5
$C_6H_{10}O_2$	Allyl glycidyl ether				40.1	85.7	152.8	5
$C_6H_{10}O_3$	Ethyl acetoacetate	−25 e	−3 e	25.7	62.3	111.3	180.2	5
$C_6H_{10}O_3$	Propanoic anhydride	−32 e	−15 e	6 e	36 e	77.6	142.9	5
$C_6H_{10}O_4$	Diethyl oxalate	−5 e	18 e	44.9	79.4	124.3	185.2	5
$C_6H_{10}O_4$	Dimethyl succinate			30 e	70.4	123.3	195.4	5
$C_6H_{10}O_4$	Ethylene glycol diacetate	−17 e	6 e	35.0	71.9	121.1	190.0	5
$C_6H_{10}S$	Diallylsulfide	−58 e	−38 e	−12.4	21.7	68.8	138.1	5
$C_6H_{11}Cl$	Chlorocyclohexane		−35 e	−9 e	25 e	71.6	142.1	5
$C_6H_{11}N$	Hexanenitrile	−40 e	−19 e	8 e	43 e	91.5	163.2	1,5
$C_6H_{11}N$	4-Methylpentanenitrile		−50 e	−20 e	20 e	75.2	155.2	5
$C_6H_{11}NO$	Caprolactam	36.8 s	58.9 s	86.6 s			270	5
C_6H_{12}	1-Hexene	−99.8	−82.8	−61.4	−33.7	5.2	63.1	1,5
C_6H_{12}	*cis*-2-Hexene	−97 e	−80 e	−58 e	−30 e	9.9	68.5	5
C_6H_{12}	*trans*-2-Hexene	−94 e	−78 e	−57 e	−30 e	9.3	67.5	5
C_6H_{12}	*cis*-3-Hexene	−96 e	−79 e	−59 e	−30.8	7.9	66.0	5
C_6H_{12}	*trans*-3-Hexene	−95 e	−79 e	−58 e	−30.0	8.8	66.7	5
C_6H_{12}	2-Methyl-1-pentene	−98 e	−82 e	−62 e	−34.2	4.1	61.7	5
C_6H_{12}	3-Methyl-1-pentene	−104 e	−88 e	−68 e	−41.5	−3.6	53.8	5
C_6H_{12}	4-Methyl-1-pentene	−105 e	−89 e	−69 e	−41.6	−3.6	53.5	5
C_6H_{12}	2-Methyl-2-pentene	−95 e	−78 e	−58 e	−30 e	9.0	66.9	5
C_6H_{12}	3-Methyl-*cis*-2-pentene	−95 e	−79 e	−58 e	−30 e	8.9	67.3	5
C_6H_{12}	3-Methyl-*trans*-2-pentene	−93 e	−77 e	−55 e	−27.4	11.7	70.0	5
C_6H_{12}	4-Methyl-*cis*-2-pentene	−102 e	−86 e	−66 e	−38.7	−0.9	56.0	5
C_6H_{12}	4-Methyl-*trans*-2-pentene	−100 e	−84 e	−64 e	−36.8	1.2	58.2	5
C_6H_{12}	2-Ethyl-1-butene	−98 e	−81 e	−60 e	−32 e	6.6	64.3	5
C_6H_{12}	2,3-Dimethyl-1-butene	−103 e	−87 e	−67 e	−39.9	−1.9	55.2	5
C_6H_{12}	3,3-Dimethyl-1-butene	−110 e	−95 e	−76 e	−50.8	−14.5	40.8	5
C_6H_{12}	2,3-Dimethyl-2-butene		−75 e	−54 e	−25 e	14 e	72.9	1
C_6H_{12}	Cyclohexane	−85.6 s	−68.9 s	−47.6 s	−19.8 s	19.3	80.4	1,5
C_6H_{12}	Methylcyclopentane	−97 e	−80 e	−58 e	−28.8	11.6	71.4	1,5
C_6H_{12}	Ethylcyclobutane	−99 e	−82 e	−61 e	−32 e	9 e	70.2	5
C_6H_{12}	Isopropylcyclopropane	−104 e	−88 e	−68 e	−40 e	−1 e	57.9	5
C_6H_{12}	1-Ethyl-1-methylcyclopropane	−105 e	−89 e	−69 e	−41 e	−3 e	56.3	5
C_6H_{12}	1,1,2-Trimethylcyclopropane	−109 e	−94 e	−73 e	−46 e	−7 e	52.0	5
$C_6H_{12}Cl_2$	1,2-Dichlorohexane				49 e	98.1	171.7	5
$C_6H_{12}Cl_2O$	2,2´-Dichlorodiisopropyl ether		−1 e	27.3	63.4	112.3	182.1	5
$C_6H_{12}O$	Butyl vinyl ether	−87 e	−67 e	−42 e	−9.3	33.6	93.2	5
$C_6H_{12}O$	Isobutyl vinyl ether	−87 e	−68 e	−44 e	−13 e	26.5	80.7	5
$C_6H_{12}O$	Hexanal	−56 e	−37 e	−13 e	19 e	62.6	127.8	5
$C_6H_{12}O$	2-Hexanone	−43 e	−21 e	4.2	34.5	61.9	127.2	1,5
$C_6H_{12}O$	3-Hexanone		−40 e	−16 e	15 e	58.5	123.1	1
$C_6H_{12}O$	3-Methyl-2-pentanone				8.5	52.7	117.0	5
$C_6H_{12}O$	4-Methyl-2-pentanone	−61 e	−43 e	−21 e	9 e	51.5	116.1	5
$C_6H_{12}O$	2-Methyl-3-pentanone					50.2	113.0	5
$C_6H_{12}O$	3,3-Dimethyl-2-butanone			−30 e	0 e	42.5	105.7	1
$C_6H_{12}O$	Cyclohexanol			34 e	61 e	99.2	160.7	1
$C_6H_{12}O_2$	Hexanoic acid		33 e	59 e	93 e	139.3	204.5	1
$C_6H_{12}O_2$	4-Methylpentanoic acid	36 e	49 e	67.1	92.9	133.6	206.8	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_6H_{12}O_2$	Diethylacetic acid	−9 e	16 e	46 e	83 e	130.7	192.5	5
$C_6H_{12}O_2$	Isopentyl formate	−60 e	−41 e	−17 e	15 e	59.1	124 e	5
$C_6H_{12}O_2$	Butyl acetate	−63 e	−43 e	−19 e	14 e	61.0	125.6	1,5
$C_6H_{12}O_2$	Isobutyl acetate	−63 e	−45 e	−21 e	10 e	53.4	116 e	5
$C_6H_{12}O_2$	Propyl propanoate	−62 e	−42 e	−18 e	14 e	58.3	122.0	5
$C_6H_{12}O_2$	Ethyl butanoate	−49 e	−34 e	−14 e	14.3	55.2	121.1	5
$C_6H_{12}O_2$	Ethyl 2-methylpropanoate	−65 e	−47 e	−24.6	5.4	47.3	109.8	5
$C_6H_{12}O_2$	Methyl pentanoate				19.2	63.7	127.4	5
$C_6H_{12}O_2$	Methyl isopentanoate					53.3	116.3	5
$C_6H_{12}O_2$	Diacetone alcohol	−41 e	−17 e	13 e	50.1	98.5	164 e	5
$C_6H_{12}O_3$	Ethylene glycol monoethyl ether acetate	−25 e	−8 e	14 e	44.6	88.0	155.6	5
$C_6H_{12}O_3$	Paraldehyde				17 e	62.2	124 e	5
$C_6H_{12}S$	Cyclohexanethiol					84.8	158.3	5
$C_6H_{12}S$	*cis*-Tetrahydro-2,5-dimethylthiophene	−53 e	−34 e	−8 e	25 e	72.0	142.1	5
$C_6H_{12}S$	Tetrahydro-3-methyl-2H-thiopyran	−48 e	−27 e	0 e	35 e	84.1	157.5	5
$C_6H_{13}Br$	1-Bromohexane	−45 e	−25 e	2 e	36 e	83.7	154.8	5
$C_6H_{13}Cl$	1-Chlorohexane	−55 e	−36 e	−11 e	21 e	66.7	134.6	5
$C_6H_{13}F$	1-Fluorohexane	−80 e	−62 e	−40 e	−11 e	30.4	91.1	5
$C_6H_{13}I$	1-Iodohexane	−33 e	−11 e	16 e	53 e	104.0	180.8	5
$C_6H_{13}N$	Cyclohexylamine			−9 e	22 e	66.6	133.5	1
C_6H_{14}	Hexane	−96.4 s	−79.2	−57.6	−29.3	9.8	68.3	16
C_6H_{14}	2-Methylpentane	−100 e	−84 e	−64 e	−36 e	2 e	59.9	1
C_6H_{14}	3-Methylpentane	−99 e	−83 e	−62 e	−34.3	4.6	62.9	1
C_6H_{14}	2,2-Dimethylbutane		−90 e	−71.5	−45.5	−7.7	49.4	1
C_6H_{14}	2,3-Dimethylbutane	−103 e	−87 e	−66 e	−39.0	−0.4	57.6	1
$C_6H_{14}O$	1-Hexanol		5 e	28 e	56.8	97.3	157.1	1
$C_6H_{14}O$	2-Hexanol	−28 e	−10 e	12 e	41.4	81.5	139.6	1
$C_6H_{14}O$	3-Hexanol	−43 e	−23 e	1 e	33 e	75.4	135.1	1
$C_6H_{14}O$	2-Methyl-1-pentanol			14 e	45.9	88.3	147.6	5
$C_6H_{14}O$	4-Methyl-1-pentanol			24 e	53 e	92.4	151.4	5
$C_6H_{14}O$	2-Methyl-2-pentanol	−29 e	−15 e	3 e	27.1	63.0	120.9	5
$C_6H_{14}O$	3-Methyl-2-pentanol				36.5	76.1	133.8	5
$C_6H_{14}O$	4-Methyl-2-pentanol	−43 e	−24 e	0 e	30 e	71.9	131.3	5
$C_6H_{14}O$	2-Methyl-3-pentanol				29.8	68.8	126.0	5
$C_6H_{14}O$	3-Methyl-3-pentanol		−23 e	−4 e	22.9	61.1	121.1	5
$C_6H_{14}O$	2-Ethyl-1-butanol		−5 e	17 e	46 e	85.7	146.1	5
$C_6H_{14}O$	3,3-Dimethyl-1-butanol	−37 e	−16 e	9 e	42 e	84.3	142.5	5
$C_6H_{14}O$	2,3-Dimethyl-2-butanol			−5 e	23 e	61.3	118.2	5
$C_6H_{14}O$	Dipropyl ether	−80 e	−63 e	−41 e	−12 e	28.8	89.7	1
$C_6H_{14}O$	Diisopropyl ether		−76 e	−55 e	−28 e	11 e	68.1	1
$C_6H_{14}O$	Butyl ethyl ether	−78 e	−61 e	−39 e	−10 e	31.0	91.9	1
$C_6H_{14}O$	*tert*-Butyl ethyl ether	−90 e	−74 e	−53 e	−24.6	14.4	72.6	5
$C_6H_{14}O_2$	2-Methyl-2,4-pentanediol	−8 e	17 e	48 e	86 e	134.4	197.5	5
$C_6H_{14}O_2$	Ethylene glycol monobutyl ether	−31 e	−8 e	20 e	55 e	103.2	170.2	5
$C_6H_{14}O_2$	1,1-Diethoxyethane	−68 e	−49 e	−26 e	3.7	44.2	101.9	5
$C_6H_{14}O_2$	Ethylene glycol diethyl ether		−59 e	−35.3	−2.8	44.4	118.8	5
$C_6H_{14}O_3$	1,2,6-Hexanetriol	92 e	114.8	146.0	191 e			5
$C_6H_{14}O_3$	Dipropylene glycol				110 e	162.6	231.4	5
$C_6H_{14}O_3$	Diethylene glycol monoethyl ether			40 e	80.3	132.4	201.4	5
$C_6H_{14}O_3$	Diethylene glycol dimethyl ether	−42 e	−20 e	8.3	44.3	92.3	159.4	5
$C_6H_{14}O_3$	Trimethylolpropane	73 e	98 e	128 e	167.8	220.5	295 e	5
$C_6H_{14}O_4$	Triethylene glycol	44 e	74 e	109.0	152.6	207.2	277.9	5
$C_6H_{14}S$	1-Hexanethiol	−45 e	−25 e	1 e	35 e	81.7	152.2	5
$C_6H_{14}S$	2-Hexanethiol	−50 e	−32 e	−8 e	25 e	69.9	138.4	5
$C_6H_{14}S$	Dipropyl sulfide	−50 e	−30 e	−6 e	28 e	73.6	142.4	5
$C_6H_{14}S$	Diisopropyl sulfide	−65 e	−47 e	−23 e	9 e	53.1	119.6	5
$C_6H_{14}S$	Isopropyl propyl sulfide				18.5	63.8	131.6	5
$C_6H_{14}S$	Butyl ethyl sulfide	−49 e	−30 e	−5 e	29 e	74.8	143.8	5
$C_6H_{15}N$	Hexylamine			−10 e	22 e	66.0	130.6	5
$C_6H_{15}N$	Butylethylamine				6.1	47.7	107.0	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_6H_{15}N$	Dipropylamine		−48 e	−25 e	6 e	47.5	108.8	5
$C_6H_{15}N$	Diisopropylamine			−47 e	−17.5	23.5	84.0	5
$C_6H_{15}N$	Triethylamine	−58 e	−45 e	−29 e	−5 e	29.9	88.5	1
$C_6H_{15}NO$	2-Diethylaminoethanol					97 e	160.6	5
$C_6H_{15}NO_3$	Triethanolamine	75 e	108 e	148 e	196 e	256.7	334 e	5
$C_6H_{15}O_4P$	Triethyl phosphate			34	76	132	211	4
$C_6H_{16}N_2$	Hexamethylenediamine				76.0	128.2	199.0	5
$C_6H_{16}O_2Si$	Diethoxydimethylsilane	−62 e	−44 e	−21.2	9.1	51.0	113.0	5
$C_6H_{18}Cl_2O_2Si_3$	1,5-Dichloro-1,1,3,3,5,5-hexamethyltrisiloxane	−29 e	−7 e	22.2	59.7	110.5	183.4	5
$C_6H_{18}OSi_2$	Hexamethyldisiloxane		−56 e	−34 e	−5 e	37.1	100.1	5
C_6MoO_6	Molybdenum hexacarbonyl		17.4 s	42.8 s	73.1 s	109.9 s	155.4 s	5
C_7F_{14}	Perfluoromethylcyclohexane				−21 e	18 e	75.9	1
C_7F_{16}	Perfluoroheptane		−62 e	−41 e	−14 e	24.7	82.1	1
C_7HF_{15}	1H-Pentadecafluoroheptane				−7 e	35.9	96.0	5
$C_7H_3ClF_3NO_2$	1-Chloro-2-nitro-4-trifluoromethyl)benzene	3 e	26 e	55 e	92.8	145.2	222.0	5
$C_7H_3F_5$	2,3,4,5,6-Pentafluorotoluene			−20 e	11 e	53.6	117.0	5
$C_7H_4ClF_3$	1-Chloro-2-(trifluoromethyl) benzene			1 e	34.5	81.8	151.8	5
$C_7H_4ClF_3$	1-Chloro-3-(trifluoromethyl) benzene	−53 e	−34 e	−9 e	24.2	69.8	137.2	5
$C_7H_4ClF_3$	1-Chloro-4-(trifluoromethyl) benzene			−9 e	24.2	70.4	138.1	5
$C_7H_4Cl_2O$	*o*-Chlorobenzoyl chloride				93 e	149 e	237.0	5
$C_7H_4Cl_2O$	*m*-Chlorobenzoyl chloride				87.8	147 e	225.0	5
$C_7H_4F_3NO_2$	1-Nitro-3-(trifluoromethyl) benzene		11 e	39 e	76.2	127.3	202.2	5
$C_7H_4F_4$	1-Fluoro-4-(trifluoromethyl) benzene			−38 e	−6 e	38.6	102.3	5
C_7H_5BrO	Benzoyl bromide	−15 e	11 e	42.6	83.9	139.5	218.0	5
C_7H_5ClO	Benzoyl chloride			27.5	67.0	120.4	196.7	5
$C_7H_5Cl_3$	(Trichloromethyl)benzene		9 e	40.6	81.5	136.2	213.0	5
$C_7H_5F_3$	(Trifluoromethyl)benzene				−3 e	39 e	101.6	5
C_7H_5N	Benzonitrile		−6 e	23.9	63.1	115.7	190.0	5
C_7H_5NS	Phenyl isothiocyanate				79.4	105 e	117 e	5
$C_7H_6Cl_2$	2,4-Dichlorotoluene		6 e	33 e	68.3	119.5	199.1	5
$C_7H_6Cl_2$	3,4-Dichlorotoluene	−13 e	9 e	38 e	76 e	129.3	208.4	5
$C_7H_6Cl_2$	(Dichloromethyl)benzene			31	72	130	213	4
C_7H_6O	Benzaldehyde		−9 e	19 e	54.6	104.6	178.3	1
$C_7H_6O_2$	Salicylaldehyde		−1 e	29 e	68 e	120.7	196.2	5
C_7H_7Br	*o*-Bromotoluene		−10 e	17 e	54 e	104.8	181.1	5
C_7H_7Br	*m*-Bromotoluene	−34 e	−11 e	19.4	58.1	109.9	183.1	5
C_7H_7Br	*p*-Bromotoluene				57 e	107.8	183.8	5
C_7H_7Br	(Bromomethyl)benzene			25.4	66.8	121.7	198.3	5
C_7H_7Cl	*o*-Chlorotoluene		−24 e	3 e	38 e	86.3	158.7	1,5
C_7H_7Cl	*m*-Chlorotoluene	−41 e	−21 e	6 e	41 e	89 e	161.8	5
C_7H_7Cl	*p*-Chlorotoluene				40 e	88.9	161.5	1,5
C_7H_7Cl	(Chloromethyl)benzene	−34 e	−11 e	17.7	55.4	106.3	178.9	5
C_7H_7ClO	1-Chloro-2-methoxy-benzene	−22 e	2 e	33 e	72 e	125.2	201 e	5
C_7H_7F	*o*-Fluorotoluene		−50 e	−26 e	5 e	49.0	113.9	5
C_7H_7F	*m*-Fluorotoluene	−67 e	−48 e	−25 e	7 e	51.0	116.1	5
C_7H_7F	*p*-Fluorotoluene		−48 e	−24 e	7 e	51 e	116.2	5
$C_7H_7NO_2$	*o*-Nitrotoluene	23 e	40 e	62 e	94 e	141.9	221.9	5
$C_7H_7NO_2$	*m*-Nitrotoluene			45 e	89.7	148.7	231.3	5
$C_7H_7NO_3$	2-Nitroanisole	15 e	45 e	82 e	129 e	189.4	271.8	5
C_7H_8	Toluene	−78.1	−57.1	−31.3	1.5	45.2	110.1	5
C_7H_8	Bicyclo[2.2.1]hepta-2,5-diene				−15 e	27.4	91 e	5
$C_7H_8Cl_2Si$	Dichloromethylphenylsilane			32.4	71.8	126.0	205.0	5
C_7H_8O	*o*-Cresol	−6.4 s	12.8 s	40.2	72.3	120.3	190.5	1,5
C_7H_8O	*m*-Cresol	20.8	33.6	52.4	82.6	130.6	201.8	1,5
C_7H_8O	*p*-Cresol	−0.2 s	20.7 s	52.7	83.1	130.7	201.5	1,5
C_7H_8O	Benzyl alcohol	8 e	28 e	54 e	88 e	134.7	204.9	1
C_7H_8O	Anisole		−21 e	4 e	38 e	84 e	153.2	1,5
C_7H_8S	3-Methylbenzenethiol		0 e	29 e	66 e	117.9	194.6	5
C_7H_9N	Benzylamine			25.6	62.6	112.7	183.9	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
C_7H_9N	*o*-Methylaniline	1.0	18.8	42.6	76.1	125.6	199.9	1,5
C_7H_9N	*m*-Methylaniline	3.8	22.0	46.2	80.1	128.8	202.9	1,5
C_7H_9N	*p*-Methylaniline				77.1	126.2	199.9	5
C_7H_9N	*N*-Methylaniline	−16 e	6 e	34 e	70.3	121.1	195.8	1
C_7H_9N	2-Ethylpyridine	−46 e	−26 e	−1 e	33 e	79.3	149.0	5
C_7H_9N	3-Ethylpyridine	−38 e	−17 e	9 e	44 e	92.7	166.5	5
C_7H_9N	4-Ethylpyridine	−35 e	−15 e	11 e	46 e	94.4	168.6	5
C_7H_9N	2,3-Dimethylpyridine				42 e	89.9	160.6	5
C_7H_9N	2,4-Dimethylpyridine		−25 e	3.7	40.0	87.5	157.9	1,5
C_7H_9N	2,5-Dimethylpyridine			4 e	39 e	86.2	156.6	1
C_7H_9N	2,6-Dimethylpyridine			−3 e	29.9	75.8	143.6	1
C_7H_9N	3,4-Dimethylpyridine		−9 e	19 e	55 e	104.8	178.6	5
C_7H_9N	3,5-Dimethylpyridine			11 e	48 e	98 e	171.5	1
$C_7H_{10}N_2$	Toluene-2,4-diamine			100.4	145.3	202.9	279.5	5
C_7H_{12}	1-Heptyne	−75 e	−57 e	−35 e	−5 e	37.1	99.5	5
C_7H_{12}	2-Heptyne		−51 e	−27 e	4 e	46.9	111.5	5
C_7H_{12}	3-Heptyne	−71 e	−53 e	−31 e	0 e	42.7	106.4	5
C_7H_{12}	5-Methyl-1-hexyne	−80 e	−62 e	−40 e	−11 e	30.1	91.4	5
C_7H_{12}	5-Methyl-2-hexyne	−75 e	−57 e	−34 e	−4 e	38.6	102.0	5
C_7H_{12}	2-Methyl-3-hexyne	−78 e	−61 e	−39 e	−9 e	32.6	94.8	5
C_7H_{12}	4,4-Dimethyl-1-pentyne		−73 e	−52 e	−24 e	15.9	75.6	5
C_7H_{12}	4,4-Dimethyl-2-pentyne		−70 e	−48 e	−19 e	21.4	82.6	5
C_7H_{12}	Bicyclo[4.1.0]heptane					49.9	116.3	5
C_7H_{12}	Cycloheptene			−30.0	3.4	47.5	108 e	5
C_7H_{12}	1-Methylbicyclo(3,1,0)hexane					29.8	92.6	5
C_7H_{12}	Methylenecyclohexane	−76 e	−58 e	−35 e	−5 e	38 e	103.0	5
C_7H_{12}	1-Methylcyclohexene	−72 e	−53 e	−30 e	1 e	45 e	109.8	5
C_7H_{12}	4-Methylcyclohexene	−76 e	−59 e	−36 e	−5 e	37.9	102.3	5
C_7H_{12}	1-Ethylcyclopentene	−75 e	−57 e	−34 e	−3 e	40.7	105.8	5
C_7H_{12}	1,2-Dimethylcyclopentene	−75 e	−57 e	−34 e	−3 e	40.2	105.3	5
C_7H_{12}	1,5-Dimethylcyclopentene	−77 e	−59 e	−36 e	−5.5	37.3	101.5	5
$C_7H_{12}O$	Cycloheptanone			18 e	53.7	104.0	178.7	5
$C_7H_{12}O_2$	Butyl acrylate	−52 e	−31 e	−4.5	30.4	78.0	146.9	5
$C_7H_{12}O_2$	Propyl methacrylate				26 e	73.8	139.7	5
$C_7H_{12}O_3$	Ethyl levulinate		17 e	45.3	82.6	133.2	205.7	5
$C_7H_{12}O_4$	Diethyl malonate	−23 e	4 e	36.0	76.4	128.5	198.3	5
$C_7H_{12}O_4$	Dimethyl glutarate	−11 e	15 e	47 e	87.7	139.8	209.5	5
$C_7H_{13}ClO$	Heptanoyl chloride	−17 e	4 e	29.4	59.7	96.9	144.0	5
C_7H_{14}	1-Heptene	−82.1	−63.8	−40.6	−10.7	31.1	93.2	1,5
C_7H_{14}	*cis*-2-Heptene	−79 e	−61 e	−38 e	−8 e	34.3	98.0	5
C_7H_{14}	*trans*-2-Heptene	−79 e	−61 e	−39 e	−8 e	34.0	97.5	5
C_7H_{14}	*cis*-3-Heptene	−80 e	−62 e	−40 e	−10 e	32.3	95.3	5
C_7H_{14}	*trans*-3-Heptene	−80 e	−62 e	−40 e	−10 e	32.2	95.2	5
C_7H_{14}	2-Methyl-1-hexene	−81 e	−64 e	−42 e	−12 e	29.3	91.6	5
C_7H_{14}	4-Methyl-1-hexene	−84 e	-67 e	−45 e	−16 e	25.3	86.3	5
C_7H_{14}	2-Methyl-2-hexene	−80 e	−63 e	−40 e	−10 e	32.0	95.0	5
C_7H_{14}	*cis*-3-Methyl-2-hexene	−79 e	−62 e	−39 e	−9 e	33.4	96.8	5
C_7H_{14}	*trans*-4-Methyl-2-hexene	−83 e	−66 e	−44 e	−15 e	25.9	87.1	5
C_7H_{14}	*trans*-5-Methyl-2-hexene	−83 e	−66 e	−44 e	−15 e	26.3	87.7	5
C_7H_{14}	*trans*-2-Methyl-3-hexene	−84 e	−67 e	−45 e	−16 e	24.6	85.5	5
C_7H_{14}	3-Ethyl-1-pentene	−85 e	−68 e	−46 e	−17 e	23.2	83.7	5
C_7H_{14}	2,3-Dimethyl-1-pentene	−85 e	−68 e	−46 e	−17 e	23.4	83.8	5
C_7H_{14}	2,4-Dimethyl-1-pentene	−88 e	−71 e	−50 e	−21 e	20.0	81.2	5
C_7H_{14}	3,3-Dimethyl-1-pentene	−87 e	−71 e	−50 e	−21 e	18.1	77.1	5
C_7H_{14}	4,4-Dimethyl-1-pentene	−94 e	−78 e	−57 e	−28 e	11.5	72.1	5
C_7H_{14}	2,3-Dimethyl-2-pentene	−79 e	−62 e	−39 e	−9 e	33.5	96.9	5
C_7H_{14}	2,4-Dimethyl-2-pentene	−84 e	−68 e	−46 e	−18 e	22.6	82.9	5
C_7H_{14}	*cis*-3,4-Dimethyl-2-pentene	−83 e	−65 e	−43 e	−14 e	27.2	88.8	5
C_7H_{14}	*trans*-3,4-Dimethyl-2-pentene	−82 e	−64 e	−42 e	−13 e	29.0	91.1	5
C_7H_{14}	*cis*-4,4-Dimethyl-2-pentene	−90 e	−73 e	−51 e	−22 e	18.6	80.0	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
C_7H_{14}	*trans*-4,4-Dimethyl-2-pentene	−90 e	−73 e	−52 e	−23 e	16.6	76.3	5
C_7H_{14}	2,3,3-Trimethyl-1-butene	−91 e	−75 e	−53 e	−24.2	16.3	77.5	5
C_7H_{14}	Cycloheptane				6 e	51.1	118.4	1
C_7H_{14}	Methylcyclohexane	−79 e	−62 e	−39 e	−7.9	35.5	100.5	1
C_7H_{14}	Ethylcyclopentane	−76 e	−59 e	−35 e	−5 e	38.4	103.0	5
C_7H_{14}	1,1-Dimethylcyclopentane		−69 e	−47 e	−17 e	24.8	87.4	5
C_7H_{14}	*cis*-1,2-Dimethylcyclopentane			−38 e	−8 e	34.9	99.0	5
C_7H_{14}	*trans*-1,2-Dimethylcyclopentane	−83 e	−66 e	−43 e	−13 e	28.4	91.4	5
C_7H_{14}	*cis*-1,3-Dimethylcyclopentane	−84 e	−66 e	−44 e	−14 e	28.2	91.1	5
C_7H_{14}	*trans*-1,3-Dimethylcyclopentane	−84 e	−67 e	−44 e	−14 e	27.4	90.3	5
$C_7H_{14}O$	1-Heptanal	−41 e	−21 e	4 e	37 e	83.7	152.3	5
$C_7H_{14}O$	2-Heptanone		−22 e	3 e	36 e	82.2	150.6	1
$C_7H_{14}O$	3-Heptanone		−28 e	0 e	36 e	83.2	147.0	5
$C_7H_{14}O$	4-Heptanone	−27 e	−6 e	18.8	50.2	90.3	143.4	5
$C_7H_{14}O$	5-Methyl-2-hexanone		−27 e	−2 e	31.0	76.6	144.4	5
$C_7H_{14}O$	2,4-Dimethyl-3-pentanone	−61 e	−42 e	−18 e	14 e	58.5	124.8	1
$C_7H_{14}O_2$	Heptanoic acid	24 e	46 e	72 e	107 e	154.6	222.6	5
$C_7H_{14}O_2$	Pentyl acetate	−58 e	−39 e	−14 e	20 e	70.1	149 e	5
$C_7H_{14}O_2$	Isopentyl acetate	−51 e	−30 e	−4 e	30.3	76.2	141.4	5
$C_7H_{14}O_2$	Isobutyl propanoate	−35 e	−19 e	2 e	31 e	72.0	136.1	5
$C_7H_{14}O_2$	Propyl butanoate	−35 e	−19 e	3 e	32.0	74.9	142.8	5
$C_7H_{14}O_2$	Propyl isobutanoate		−28 e	−5.7	24.5	67.5	133.3	5
$C_7H_{14}O_2$	Isopropyl isobutanoate		−44 e	−19.7	12.2	56.0	120.1	5
$C_7H_{14}O_2$	Ethyl 3-methylbutanoate	−57 e	−36 e	−10 e	23.9	69.5	134.4	5
$C_7H_{14}O_2$	Methyl hexanoate	−47 e	−26 e	2 e	36.6	83.3	149 e	5
$C_7H_{14}O_2$	4-Methoxy-4-methyl-2-pentanone				43 e	89.8	160 e	5
$C_7H_{15}Br$	1-Bromoheptane	−30 e	−9 e	18 e	54 e	104.4	178.4	5
$C_7H_{15}Cl$	1-Chloroheptane	−39 e	−19 e	7 e	41 e	88.6	159.9	5
$C_7H_{15}F$	1-Fluoroheptane	−64 e	−45 e	−22 e	10 e	53.3	117.4	5
$C_7H_{15}I$	1-Iodoheptane	−19 e	3 e	32 e	71 e	123.8	203.4	5
C_7H_{16}	Heptane	−78.6	−60.2	−37.0	−6.6	35.4	98.0	16
C_7H_{16}	2-Methylhexane	−82 e	−65 e	−43 e	−13 e	27.8	89.7	1
C_7H_{16}	3-Methylhexane	−81 e	−64 e	−42 e	−12 e	29.2	91.5	1
C_7H_{16}	3-Ethylpentane	−81 e	−63 e	−41 e	−11 e	30.5	93.1	1
C_7H_{16}	2,2-Dimethylpentane	−90 e	−73 e	−52 e	−22.9	17.6	78.8	1
C_7H_{16}	2,3-Dimethylpentane	−87 e	−68.4	−45.3	−14.9	26.8	89.3	5
C_7H_{16}	2,4-Dimethylpentane	−89 e	−72 e	−50 e	−21.3	19.2	80.1	1
C_7H_{16}	3,3-Dimethylpentane	−88 e	−71 e	−49 e	−18.8	22.9	85.6	1
C_7H_{16}	2,2,3-Trimethylbutane				−23.2	18.1	80.4	5
$C_7H_{16}O$	1-Heptanol		17 e	40 e	70.1	112.5	176 e	1
$C_7H_{16}O$	2-Heptanol	−9 e	7 e	27 e	55.0	95.2	158.7	5
$C_7H_{16}O$	3-Heptanol	−8 e	7 e	27 e	54.5	93.9	156.3	5
$C_7H_{16}O$	4-Heptanol	−16 e	1 e	22 e	51 e	91.9	154.6	5
$C_7H_{16}O$	2,2-Dimethyl-3-pentanol			9 e	35 e	73.1	135.5	5
$C_7H_{16}S$	1-Heptanethiol	−30 e	−9 e	18 e	53 e	102.7	176.4	5
$C_7H_{17}N$	Heptylamine			5 e	39 e	86.7	156.4	5
$C_7H_{18}N_2$	*N,N*-Diethyl-1,3-propanediamine				50.1	99.9	167.7	5
C_8F_{18}	Perfluorooctane				5 e	45.0	105.6	5
$C_8H_4O_3$	Phthalic anhydride	48.2 s	72.4 s			192.7	284.2	5
C_8H_6O	Benzofuran		−16 e	12 e	47.9	97.7	170.7	5
C_8H_7Cl	*o*-Chlorostyrene	−33 e	−10 e	20 e	58 e	110.8	188 e	5
C_8H_7N	2-Methylbenzonitrile		1 e	32.1	72.2	126.6	204.7	5
C_8H_7N	4-Methylbenzonitrile			40.1	78.7	134.3	221.3	5
C_8H_7N	Benzeneacetonitrile	−3 e	23 e	55.3	97.4	153.7	233.1	5
C_8H_7N	Indole	20.6 s	44.5 s				254.0	5
$C_8H_7NO_4$	Methyl 2-nitrobenzoate	17 e	49 e	89 e	140 e	208 e	302 e	5
C_8H_8	Styrene		−31 e	−5 e	28.6	75.4	144.7	1
C_8H_8	1,3,5,7-Cyclooctatetraene				24.3	71.0	140.1	5
C_8H_8O	Acetophenone			36 e	73 e	125.3	201.5	5
$C_8H_8O_2$	Phenyl acetate		3 e	33.1	72.2	123.9	195.5	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_8H_8O_2$	Methyl benzoate		−1 e	29 e	68 e	121.2	198.9	5
$C_8H_8O_2$	4-Methoxybenzaldehyde	9 e	35 e	68.1	110.8	167.9	248.5	5
$C_8H_8O_3$	Methyl salicylate	−1 e	22 e	51 e	88.8	141.8	219.9	5
C_8H_9Cl	1-Chloro-2-ethylbenzene	−30 e	−9 e	18 e	54 e	103.7	177.9	5
C_8H_9Cl	1-Chloro-4-ethylbenzene	−27 e	−6 e	22 e	58 e	108.7	183.9	5
$C_8H_9NO_2$	1-Ethyl-4-nitrobenzene	10 e	36 e	69 e	111.6	168 e	245 e	5
C_8H_{10}	Ethylbenzene	−56.2	−36.8	−12.0	21.1	67.1	135.7	1
C_8H_{10}	*o*-Xylene			−7 e	27 e	74.2	143.9	1
C_8H_{10}	*m*-Xylene		−35 e	−10 e	23.4	69.8	138.7	1
C_8H_{10}	*p*-Xylene				22.4	68.9	137.9	1
$C_8H_{10}O$	*o*-Ethylphenol		16.9	44.5	81.1	130.9	204.0	5
$C_8H_{10}O$	*m*-Ethylphenol	5.6	29.2	57.5	91.9	144.8	217.9	5
$C_8H_{10}O$	*p*-Ethylphenol			60 e	95.5	144.6	217.5	5
$C_8H_{10}O$	2,3-Xylenol	14.3 s	34.3 s	57.2 s	91.4	141.7	216.4	1,5
$C_8H_{10}O$	2,4-Xylenol			50.2	85.5	137.2	210.5	1,5
$C_8H_{10}O$	2,5-Xylenol	13.4 s	33.2 s	55.9 s	87.4	137.0	210.6	5
$C_8H_{10}O$	2,6-Xylenol	−3.1 s	16.7 s	39.6 s	75.3	125.9	200.6	1,5
$C_8H_{10}O$	3,4-Xylenol	19.7 s	40.2 s	63.7 s	102.1	152.3	226.4	1,5
$C_8H_{10}O$	3,5-Xylenol	16.5 s	37.2 s	61.1 s	98.0	147.9	221.3	1,5
$C_8H_{10}O$	Benzeneethanol	2 e	25 e	54 e	92 e	143.6	217.7	5
$C_8H_{10}O$	Phenetole		−9 e	17 e	51 e	99 e	169.3	5
$C_8H_{10}O_2$	2-Phenoxyethanol	21 e	46 e	75.9	115.4	168.7	244.8	5
$C_8H_{10}O_2$	1,3-Dimethoxybenzene	18 e	34 e	56 e	86.7	135.5	223 e	5
$C_8H_{11}N$	*p*-Ethylaniline	−2 e	21 e	49 e	87 e	139.4	216.7	5
$C_8H_{11}N$	*N*-Ethylaniline	−15 e	8 e	38 e	76.4	128.8	204.2	5
$C_8H_{11}N$	*N,N*-Dimethylaniline			28 e	66 e	118.1	193.6	1
$C_8H_{11}N$	2,4-Xylidine	−2 e	21 e	51 e	88 e	139.1	210.9	5
$C_8H_{11}N$	2,6-Xylidine			37 e	80 e	137.7	217.7	5
$C_8H_{11}N$	5-Ethyl-2-picoline	−33 e	−9.3	20 e			178.0	5
$C_8H_{11}NO$	*o*-Phenetidine	0 e	27 e	60 e	102.2	156.0	228.1	5
C_8H_{12}	1,5-Cyclooctadiene		−37 e	−8 e	30 e	80.2	150 e	5
C_8H_{12}	4-Vinylcyclohexene	−62 e	−43 e	−19 e	14.1	59.9	129 e	5
$C_8H_{12}O_4$	Diethyl maleate	−6 e	20 e	52.2	93.5	148.4	224.8	5
C_8H_{14}	2,5-Dimethyl-1,5-hexadiene	−38 e	−26 e	−10 e	14 e	50.8	115.1	5
C_8H_{14}	1-Octyne	−59 e	−40 e	−16 e	16 e	60.3	125.8	1
C_8H_{14}	2-Octyne	−52 e	−33 e	−8 e	25 e	70.6	137.8	1
C_8H_{14}	3-Octyne	−55 e	−35 e	−11 e	22 e	66.8	132.8	1
C_8H_{14}	4-Octyne	−56 e	−36 e	−12 e	21 e	65.6	131.4	1
C_8H_{14}	1-Ethylcyclohexene	−55 e	−35 e	−11 e	22 e	68 e	136.5	5
$C_8H_{14}O_2$	Cyclohexyl acetate					103.1	172.9	5
$C_8H_{14}O_2$	Butyl methacrylate				47 e	93.3	159.0	5
$C_8H_{14}O_3$	Butanoic anhydride	−28 e	−2 e	30 e	71 e	123.8	196.5	5
$C_8H_{14}O_4$	Ethyl succinate	−6 e	20 e	51.0	91.1	143.7	216.1	5
$C_8H_{14}O_4$	Dipropyl oxalate	−4 e	20 e	49.9	88.6	140.4	213.0	5
$C_8H_{14}O_4$	Dimethyl adipate		28 e	61 e	103 e	156.1	227.3	5
$C_8H_{15}Br$	(2-Bromoethyl)cyclohexane	−14 e	8 e	36.9	75.3	129.7	212.5	5
$C_8H_{15}ClO$	Octanoyl chloride	1 e	22 e	46 e	74.7	109 e	150 e	5
$C_8H_{15}N$	Octanenitrile	−15 e	8 e	37 e	75 e	127.7	204.4	5
C_8H_{16}	1-Octene	−65.7	−46.1	−21.4	10.5	54.9	120.9	1,5
C_8H_{16}	*cis*-2-Octene	−59 e	−41 e	−17 e	15 e	59 e	125.2	5
C_8H_{16}	*trans*-2-Octene	−59 e	−41 e	−17 e	14 e	59 e	124.5	5
C_8H_{16}	*cis*-3-Octene	−65 e	−46 e	−22 e	10 e	55.1	122.4	5
C_8H_{16}	*trans*-3-Octene	−61 e	−43 e	−19 e	13 e	57 e	122.8	5
C_8H_{16}	*cis*-4-Octene	−63 e	−44 e	−20 e	11 e	56 e	122.1	5
C_8H_{16}	*trans*-4-Octene	−65 e	−46 e	−22 e	10 e	54.6	121.8	5
C_8H_{16}	2-Methyl-1-heptene	−66 e	−48 e	−24 e	8 e	52.3	118.7	5
C_8H_{16}	2,2-Dimethyl-*cis*-3-hexene	−74 e	−56 e	−33 e	−3 e	40.1	105.0	5
C_8H_{16}	2,3-Dimethyl-2-hexene	−65 e	−47 e	−23 e	10 e	54.3	121.3	5
C_8H_{16}	2,3,3-Trimethyl-1-pentene		−53 e	−30 e	1 e	43.8	107.9	5
C_8H_{16}	2,4,4-Trimethyl-1-pentene	−79 e	−61 e	−38 e	−7 e	36.2	101.0	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
C_8H_{16}	2,3,4-Trimethyl-2-pentene	−68 e	−49 e	−26 e	6 e	50.0	115.8	5
C_8H_{16}	2,4,4-Trimethyl-2-pentene	−73 e	−56 e	−33 e	−2 e	40.4	104.5	5
C_8H_{16}	Cyclooctane				30 e	78 e	150.7	1
C_8H_{16}	Ethylcyclohexane	−61 e	−42 e	−17 e	15.8	61.9	131.3	5
C_8H_{16}	1,1-Dimethylcyclohexane			−27 e	5 e	50.6	119.1	5
C_8H_{16}	*cis*-1,2-Dimethylcyclohexane		−44 e	−20 e	14 e	59.7	129.2	5
C_8H_{16}	*trans*-1,2-Dimethylcyclohexane	−68 e	−49 e	−25 e	8 e	53.9	122.9	5
C_8H_{16}	*cis*-1,3-Dimethylcyclohexane	−68 e	−48 e	−23 e	10 e	55.6	123.1	5
C_8H_{16}	*trans*-1,3-Dimethylcyclohexane	−62 e	−45 e	−23 e	8 e	51.5	120.9	5
C_8H_{16}	*cis*-1,4-Dimethylcyclohexane	−66 e	−47 e	−23 e	10 e	55.3	123.8	5
C_8H_{16}	*trans*-1,4-Dimethylcyclohexane			−27 e	5 e	50.6	118.9	5
C_8H_{16}	Propylcyclopentane	−60 e	−41 e	−16 e	16.5	62.1	130.5	5
C_8H_{16}	Isopropylcyclopentane	−65 e	−46 e	−21 e	12 e	57.3	125.9	5
C_8H_{16}	1-Ethyl-1-methylcyclopentane	−67 e	−49 e	−24 e	8 e	53.2	121.0	5
C_8H_{16}	*cis*-1-Ethyl-2-methylcyclopentane	−63 e	−44 e	−19 e	13.3	59.1	127.6	5
C_8H_{16}	1,1,2-Trimethylcyclopentane				2 e	46.2	113.2	5
C_8H_{16}	1,1,3-Trimethylcyclopentane	−77 e	−59 e	−36 e	−5 e	38.7	104.4	5
C_8H_{16}	1′,2′,4a-1,2,4-Trimethylcyclo-pentane	−70 e	−52 e	−28 e	4 e	48.9	116.2	5
C_8H_{16}	1′,2a,4′-1,2,4-Trimethylcyclo-pentane	−74 e	−56 e	−33 e	−1 e	42.8	108.8	5
$C_8H_{16}O$	1-Propylcyclopentanol	9 e	24 e	43 e	69.0	108.4	173.5	5
$C_8H_{16}O$	Octanal			6 e	45.7	97.8	170.2	5
$C_8H_{16}O$	2-Octanone		−3 e	23 e	57 e	103.8	172.1	5
$C_8H_{16}O$	3-Octanone			8 e	47.7	97 e	161 e	5
$C_8H_{16}O$	2,2,4-Trimethyl-3-pentanone			11.3	42.1	81.7	134.6	5
$C_8H_{16}O_2$	Octanoic acid	37 e	58 e	85 e	120 e	165.5	238.4	1,5
$C_8H_{16}O_2$	2-Ethylhexanoic acid				108 e	159.6	226.6	5
$C_8H_{16}O_2$	Hexyl acetate	−37 e	−13 e	16 e	52.8	100.4	164 e	5
$C_8H_{16}O_2$	Isopentyl propanoate			3.1	40.7	90.6	159.8	5
$C_8H_{16}O_2$	Isobutyl isobutanoate	−47 e	−26 e	0.4	34.8	81.1	147.0	5
$C_8H_{16}O_2$	Propyl 3-methylbutanoate			1.8	38.9	87.9	155.6	5
$C_8H_{16}O_2$	Ethyl hexanoate	−31 e	−9 e	18.7	53.9	100.7	166.2	5
$C_8H_{16}O_2$	Methyl heptanoate	−30 e	−9 e	19 e	54.2	102.4	172 e	5
$C_8H_{16}O_4$	Diethylene glycol monoethyl ether acetate	−16 e	10.6	43.9	86.2	141.3	216.6	5
$C_8H_{17}Br$	1-Bromooctane	−17 e	6 e	34 e	72 e	123.8	200.3	5
$C_8H_{17}Cl$	1-Chlorooctane	−25 e	−4 e	23 e	59 e	108.8	182.9	5
$C_8H_{17}Cl$	3-(Chloromethyl)heptane					100.3	172.4	5
$C_8H_{17}F$	1-Fluorooctane				29 e	74.6	141.8	5
$C_8H_{17}I$	1-Iodooctane	−6 e	18 e	48 e	87 e	142.5	224.5	5
C_8H_{18}	Octane		−42.6	−17.9	14.4	58.9	125.3	16
C_8H_{18}	2-Methylheptane	−69 e	−49.1	−24.5	7.6	51.6	117.2	1,5
C_8H_{18}	3-Methylheptane	−67 e	−48.1	−23.6	8.5	52.7	118.5	1,5
C_8H_{18}	4-Methylheptane	−65 e	−47 e	−24 e	7.8	51.6	117.2	5
C_8H_{18}	3-Ethylhexane				8 e	52.1	118.1	5
C_8H_{18}	2,2-Dimethylhexane	−73 e	−55 e	−32 e	−1.5	41.6	106.4	5
C_8H_{18}	2,3-Dimethylhexane				5 e	49.2	115.1	5
C_8H_{18}	2,4-Dimethylhexane				0.6	43.9	109.0	5
C_8H_{18}	2,5-Dimethylhexane	−71 e	−53 e	−30 e	0.7	43.8	108.6	5
C_8H_{18}	3,3-Dimethylhexane	−72 e	−54 e	−30 e	1.4	45.4	111.5	5
C_8H_{18}	3,4-Dimethylhexane				7 e	50.9	117.3	5
C_8H_{18}	3-Ethyl-2-methylpentane	−69 e	−50 e	−27 e	5 e	48.9	115.2	5
C_8H_{18}	3-Ethyl-3-methylpentane	−70 e	−51 e	−27 e	5 e	50.2	117.8	5
C_8H_{18}	2,2,3-Trimethylpentane	−74 e	−56 e	−32 e	−0.8	43.1	109.4	5
C_8H_{18}	2,2,4-Trimethylpentane	−81.9	−63.4	−39.8	−8.9	34.0	98.8	5
C_8H_{18}	2,3,3-Trimethylpentane	−72 e	−54 e	−30 e	2.1	46.9	114.3	5
C_8H_{18}	2,3,4-Trimethylpentane	−74 e	−54.5	−30.0	2.2	46.7	113.1	1,5
C_8H_{18}	2,2,3,3-Tetramethylbutane	−62.5 s	−44 s	−20.9 s	8.9 s	48.8 s	105.8	5
$C_8H_{18}O$	1-Octanol	12 e	30 e	53 e	84 e	128.2	194.8	1,39
$C_8H_{18}O$	2-Octanol			40 e	69.9	112.5	179.4	1,39
$C_8H_{18}O$	3-Octanol	12 e	24 e	40 e	64 e	102.8	174.1	1

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_8H_{18}O$	4-Octanol			40 e	66.9	107.3	176.0	1,39
$C_8H_{18}O$	4-Methyl-3-heptanol	−52 e	−28 e	1 e	39 e	87.6	155.0	5
$C_8H_{18}O$	5-Methyl-3-heptanol	−35 e	−16 e	8 e	40 e	84.8	153.0	5
$C_8H_{18}O$	4-Methyl-4-heptanol	−17 e	1 e	24 e	55 e	97.2	160.7	5
$C_8H_{18}O$	2-Ethyl-1-hexanol			45 e	75 e	118.3	184.2	1
$C_8H_{18}O$	2-Ethyl-2-hexanol	−13 e	4 e	26 e	55 e	96.3	160.3	5
$C_8H_{18}O$	2,4,4-Trimethyl-2-pentanol		−7 e	13 e	40 e	79.8	146.1	5
$C_8H_{18}O$	2,2,4-Trimethyl-3-pentanol	−2 e	9 e	24 e	47 e	82.6	150.4	5
$C_8H_{18}O$	Dibutyl ether	−55 e	−35 e	−8 e	26 e	73.0	141.2	5
$C_8H_{18}O$	Di-*sec*-butyl ether			−19 e	12.1	55.4	120.6	5
$C_8H_{18}O$	Di-*tert*-butyl ether			−33 e	−2 e	41.7	106.8	1
$C_8H_{18}O_2$	Ethylene glycol monohexyl ether	−13 e	14 e	46 e	86 e	137.7	206.9	5
$C_8H_{18}O_2$	1,2-Dipropoxyethane			−44.2	−2.0	63.6	179.2	5
$C_8H_{18}O_2$	Di-*tert*-butyl peroxide			−26 e	4.3	46.6	110.5	5
$C_8H_{18}O_3$	Diethylene glycol monobutyl ether	14 e	37 e	66.8	104.9	153 e	230.4	5
$C_8H_{18}O_3$	Diethylene glycol diethyl ether	−32 e	−7 e	25 e	64.9	117.1	189 e	5
$C_8H_{18}O_5$	Tetraethylene glycol	89 e	117 e	151.1	192.2	242.9	307.3	5
$C_8H_{18}S$	1-Octanethiol	−15 e	6 e	34 e	71 e	122.1	198.5	5
$C_8H_{18}S$	Dibutyl sulfide	−22 e	0 e	27 e	63 e	113.5	188.4	5
$C_8H_{19}N$	Dibutylamine	−37 e	−16 e	10 e	44 e	90.8	159.1	5
$C_8H_{19}N$	Diisobutylamine	−57 e	−36 e	−9.0	25.5	72.2	139.0	5
$C_8H_{20}O_4Si$	Ethyl silicate	−77 e	−52 e	−21 e	21.6	80.5	164.1	5
$C_8H_{20}Si$	Tetraethylsilane			−6.5	30.5	80.6	152.6	5
C_9F_{20}	Perfluorononane					40 e	114.7	5
$C_9H_6N_2O_2$	Toluene-2,4-diisocyanate		39 e	72 e	113.9	169.7	247 e	5
C_9H_7N	Quinoline	−1.3	23.7	55.4	96.8	153.4	236.5	1,5
C_9H_7N	Isoquinoline		30.2	60.7	101.3	157.9	242.7	1,5
C_9H_8	Indene			12 e	53.0	106.8	181.0	5
C_9H_{10}	*cis*-1-Propenylbenzene	−38 e	−15.4	13.3	51.4	103.7	178.4	5
C_9H_{10}	*trans*-1-Propenylbenzene		−16 e	13.3	51.6	103.7	178.4	5
C_9H_{10}	Isopropenylbenzene			3.2	41.5	92.8	164.9	5
C_9H_{10}	Indan	−33 e	−12 e	16 e	52 e	102.3	177.5	1
$C_9H_{10}O$	2,4-Dimethylbenzaldehyde	−3 e	23 e	54 e	93.2	144.6	214.5	5
$C_9H_{10}O_2$	Ethyl benzoate	−18 e	8 e	39 e	80.1	135.1	212.8	5
$C_9H_{10}O_2$	Benzyl acetate	−11 e	15 e	46.6	86.9	139.5	211 e	5
$C_9H_{11}Br$	1-Bromo-4-isopropylbenzene	−8 e	15 e	45 e	84 e	138.1	218.5	5
$C_9H_{11}Cl$	1-Chloro-2-isopropylbenzene	−23 e	−1 e	27 e	64 e	114.6	190.5	5
$C_9H_{11}Cl$	1-Chloro-4-isopropylbenzene		3 e	31 e	69 e	120.5	197.8	5
C_9H_{12}	Propylbenzene	−43 e	−23 e	4 e	38 e	86.7	158.8	1
C_9H_{12}	Isopropylbenzene	−46 e	−26 e	−1 e	33 e	80.9	152.0	1
C_9H_{12}	*o*-Ethyltoluene	−40 e	−19 e	8 e	43 e	92.1	164.7	5
C_9H_{12}	*m*-Ethyltoluene	−42 e	−21 e	5 e	40.4	88.9	160.8	5
C_9H_{12}	*p*-Ethyltoluene	−41 e	−21 e	6 e	41 e	89.2	161.5	5
C_9H_{12}	1,2,3-Trimethylbenzene		−12 e	15 e	52 e	101.5	175.6	1
C_9H_{12}	1,2,4-Trimethylbenzene	−37 e	−16 e	11 e	47 e	95.9	168.9	1
C_9H_{12}	1,3,5-Trimethylbenzene	−39 e	−18 e	9 e	43.7	92.4	164.3	1
$C_9H_{12}O$	Benzyl ethyl ether		−10 e	20.4	59.3	111.3	184.5	5
$C_9H_{12}O$	Phenyl propyl ether		−10 e	21 e	61 e	113.9	189.3	5
$C_9H_{12}O$	Phenyl isopropyl ether	−20 e	−1 e	23 e	56 e	103.7	176.9	5
$C_9H_{13}N$	2,4,6-Trimethylaniline	12 e	36 e	66 e	104.1	154.9	226 e	5
$C_9H_{13}N$	*N,N*-Dimethyl-*o*-toluidine	−25 e	−3 e	24.4	60.6	110.7	184.5	5
$C_9H_{13}N$	Amphetamine			33 e	70.1	118 e	202.0	5
$C_9H_{14}O$	Isophorone		1 e	33.1	75.1	132.4	215.1	5
$C_9H_{14}O_6$	Triacetin	37.6	62 e	90 e	124 e	165 e	214 e	5
$C_9H_{16}O_4$	Diethyl glutarate	−1 e	26 e	60.2	103.3	159.6	236.5	5
$C_9H_{17}N$	Nonanenitrile	−3 e	21 e	50.9	90.7	145.4	225.1	5
C_9H_{18}	1-Nonene	−50.1	−29.4	−3.3	30.4	77.1	146.4	1,5
C_9H_{18}	2-Methyl-1-octene	−53 e	−34 e	−9 e	25 e	72 e	144.1	5
C_9H_{18}	Butylcyclopentane	−45 e	−24 e	1 e	36 e	84 e	156.1	5
C_9H_{18}	Propylcyclohexane	−46 e	−26 e	0 e	35.1	83.6	156.2	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
C_9H_{18}	Isopropylcyclohexane	−48 e	−28 e	−2 e	33 e	81.3	154.0	5
C_9H_{18}	*trans*-1-Ethyl-4-methylcyclo-hexane	−53 e	−33 e	−8 e	25 e	71.8	141.5	5
C_9H_{18}	1,1,2-Trimethylcyclohexane			−12 e	23 e	71.5	145.5	5
C_9H_{18}	1,1,3-Trimethylcyclohexane	−60 e	−41 e	−16 e	18 e	65.2	136.1	5
C_9H_{18}	1′,2a,4a-1,2,4-Trimethylcyclo-hexane	−71 e	−50 e	−22 e	15 e	65.7	140.7	5
C_9H_{18}	1′,3′,5′-1,3,5-Trimethylcyclo-hexane	−72 e	−50 e	−22 e	14 e	65.1	140.0	5
C_9H_{18}	Isobutylcyclopentane	−105 e	−88 e	−64 e	−28 e	31 e	147.0	5
C_9H_{18}	*cis*-1-Methyl-2-propylcyclo-pentane	−52 e	−33 e	−7 e	28 e	77 e	152.0	5
C_9H_{18}	*trans*-1-Methyl-2-propylcyclo-pentane	−56 e	−36 e	−11 e	23 e	72 e	145.8	5
C_9H_{18}	1,1,3,3-Tetramethylcyclo-pentane	−72 e	−54 e	−30 e	2 e	47 e	117.4	5
$C_9H_{18}O$	Nonanal		−3 e	27.4	65.5	115.6	184.6	5
$C_9H_{18}O$	2-Nonanone		8 e	35 e	71 e	121.0	194.0	5
$C_9H_{18}O$	5-Nonanone			−1 e	39.1	94 e	188 e	5
$C_9H_{18}O$	2,6–Dimethyl-4-heptanone	−32 e	−12 e	14 e	48 e	96.2	167.7	5
$C_9H_{18}O_2$	Nonanoic acid	48 e	69 e	97 e	133 e	182.7	255.1	5
$C_9H_{18}O_2$	Heptyl acetate	−16 e	6 e	34 e	70 e	119.9	191.9	5
$C_9H_{18}O_2$	Isopentyl butanoate				55 e	105.6	178.4	5
$C_9H_{18}O_2$	Isobutyl 3-methylbutanoate			11.3	48.3	97.9	168.3	5
$C_9H_{18}O_2$	Propyl hexanoate	−26 e	−2 e	28 e	65.1	113.4	178 e	5
$C_9H_{18}O_2$	Methyl octanoate	−26 e	−9 e	13 e	40 e	76 e	127.9	5
$C_9H_{19}Cl$	1-Chlorononane	−11 e	11 e	39 e	76 e	127.8	204.7	5
C_9H_{20}	Nonane	−46.8	−26.0	0.0	34.0	80.8	150.3	16
C_9H_{20}	2-Methyloctane	−49 e	−30 e	−5 e	28 e	73.9	142.8	5
C_9H_{20}	3-Methyloctane	−49 e	−29 e	−5 e	29 e	74.7	143.7	5
C_9H_{20}	4-Methyloctane	−50 e	−30 e	−6 e	27 e	73.2	141.9	5
C_9H_{20}	2,2-Dimethylheptane	−58 e	−39 e	−15 e	18 e	63.6	132.3	5
C_9H_{20}	2,3-Dimethylheptane	−53 e	−33 e	−9 e	25 e	70.8	140.0	5
C_9H_{20}	2,6-Dimethylheptane	−55 e	−36 e	−12 e	21 e	66.4	134.7	5
C_9H_{20}	3-Ethyl-4-methylhexane			−9 e	24 e	70.6	139.9	5
C_9H_{20}	2,2,4-Trimethylhexane	−66.1	−46.4	−21.3	11.8	57.7	126.0	5
C_9H_{20}	2,2,5-Trimethylhexane	−65.1	−45.8	−21.2	11.2	56.2	123.7	1,5
C_9H_{20}	2,3,3-Trimethylhexane	−58 e	−38 e	−13 e	20 e	66.7	137.2	5
C_9H_{20}	2,3,5-Trimethylhexane	−60 e	−41 e	−16 e	17 e	62.3	130.9	5
C_9H_{20}	2,4,4-Trimethylhexane	−62 e	−43 e	−18 e	15 e	61.0	130.2	5
C_9H_{20}	3,3,4-Trimethylhexane	−53 e	−33 e	−7 e	28 e	76.3	148.9	5
C_9H_{20}	3,3-Diethylpentane			−9 e	26 e	73.7	145.7	1
C_9H_{20}	3-Ethyl-2,4-dimethylpentane	−58 e	−38 e	−13 e	20 e	66.7	136.2	5
C_9H_{20}	2,2,3,3-Tetramethylpentane				21 e	68.5	139.8	1
C_9H_{20}	2,2,3,4-Tetramethylpentane	−61 e	−42 e	−17 e	16 e	62.5	132.6	1
C_9H_{20}	2,2,4,4-Tetramethylpentane		−49 e	−25 e	8 e	53.2	121.8	1
C_9H_{20}	2,3,3,4-Tetramethylpentane	−57 e	−37 e	−12 e	22 e	69.7	141.1	1
$C_9H_{20}O$	1-Nonanol		40 e	64 e	96.9	141.0	213.0	5,39
$C_9H_{20}O$	3-Nonanol		24 e	47 e	78 e	123.0	194.2	5
$C_9H_{20}O$	4-Nonanol			45 e	76.4	121.3	192.0	5
$C_9H_{20}O$	5-Nonanol	13 e	31 e	54 e	84.5	128.1	194.7	5
$C_9H_{20}O$	2,2,4,4-Tetramethyl-3-pentanol				58	100	167	5
$C_9H_{20}S$	1-Nonanethiol	−2 e	21 e	49 e	87 e	140.4	219.2	5
$C_9H_{21}BO_3$	Triisopropyl borate					73.1	139.0	5
$C_9H_{21}N$	Nonylamine		9 e	37 e	75 e	126.2	202.1	5
$C_9H_{21}N$	Tripropylamine	−39 e	−18 e	8 e	42 e	88.2	156.0	5
$C_{10}F_8$	Perfluoronaphthalene	5.2 s	25.1 s	48.1 s				5
$C_{10}F_{22}$	Perfluorodecane					52 e	132.9	5
$C_{10}H_7Br$	1-Bromonaphthalene	17 e	45 e	80.3	126.7	189.8	280.5	5
$C_{10}H_7Cl$	1-Chloronaphthalene	14 e	39 e	70.5	112.8	171.6	258.6	5
$C_{10}H_8$	Naphthalene**	3.2 s	24.1 s	49.3 s	80.7	135.6	217.5	1,5
$C_{10}H_8$	Azulene	24.1 s	46 s	71.5 s	103.3	162.6	244.0	5
$C_{10}H_8O$	1-Naphthol				137.2	196.7	281.8	5
$C_{10}H_8O$	2-Naphthol				140.7	200.5	286.8	5
$C_{10}H_9N$	1-Naphthalenamine		62 e	99.0	146.9	210.7	300.1	5
$C_{10}H_9N$	2-Naphthalenamine	36.3 s	65.9 s	103 s	150.9	215.1	305.5	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_{10}H_9N$	2-Methylquinoline	5.3	31.9	63.8	102.9	165.8	247.2	5
$C_{10}H_9N$	4-Methylquinoline	29 e	54 e	85 e	127 e	183.0	265.1	5
$C_{10}H_9N$	6-Methylquinoline	27 e	51 e	81 e	122 e	179.2	264.5	5
$C_{10}H_9N$	8-Methylquinoline	15 e	40 e	70 e	111 e	166.1	247.3	5
$C_{10}H_{10}$	*m*-Divinylbenzene	−29 e	−4 e	27.1	67.6	122.1	199 e	5
$C_{10}H_{10}O_4$	Dimethyl phthalate	27 e	56 e	92.7	137.8	195.8	272.7	5
$C_{10}H_{10}O_4$	Dimethyl isophthalate			85 e	129.5	189.2	273 e	5
$C_{10}H_{10}O_4$	Dimethyl terephthalate	56.6 s	79.4 s	106.1 s	137.9 s	197.9	282 e	5
$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene	−21 e	3 e	33.2	74.1	127.4	207.8	5
$C_{10}H_{12}$	2-Ethylstyrene	−31 e	−8 e	21 e	60 e	111.7	187 e	5
$C_{10}H_{12}$	3-Ethylstyrene	−28 e	−5.3	24.1	62.6	116 e	193 e	5
$C_{10}H_{12}$	4-Ethylstyrene	−31 e	−8.2	21.3	60.5	115 e	196 e	5
$C_{10}H_{12}O$	Estragole			48.5	88.0	140.7	214.6	5
$C_{10}H_{12}O$	4-Isopropylbenzaldehyde			54.1	96.0	152.2	231.5	5
$C_{10}H_{12}O_2$	4-Allyl-2-methoxyphenol	9 e	37 e	72 e	115.9	173.8	252.9	5
$C_{10}H_{12}O_2$	2-Phenylethyl acetate	−4 e	22 e	54 e	96 e	152.3	232.0	5
$C_{10}H_{12}O_2$	Propyl benzoate	−8 e	18 e	50.2	92.3	149.2	230.5	5
$C_{10}H_{12}O_2$	Ethyl phenylacetate	−9 e	19 e	52 e	95 e	150.2	225 e	5
$C_{10}H_{12}O_2$	Isoeugenol				125 e	185.3	267.1	5
$C_{10}H_{14}$	Butylbenzene	−28 e	−7 e	21 e	56.9	107.6	182.8	1,5
$C_{10}H_{14}$	*sec*-Butylbenzene	−35 e	−14 e	13 e	48 e	98.3	172.8	5
$C_{10}H_{14}$	*tert*-Butylbenzene	−37 e	−16 e	10 e	46 e	94.9	168.6	5
$C_{10}H_{14}$	Isobutylbenzene	−36 e	−15 e	12 e	47.9	97.8	172.3	5
$C_{10}H_{14}$	*o*-Cymene	−39 e	−16 e	13 e	51 e	103.1	177.8	5
$C_{10}H_{14}$	*m*-Cymene	−34 e	−13 e	14 e	50 e	99.9	174.6	5
$C_{10}H_{14}$	*p*-Cymene	−33 e	−12 e	16 e	52 e	102.2	176.6	5
$C_{10}H_{14}$	*o*-Diethylbenzene	−28 e	−6 e	21 e	58 e	107.9	182.9	5
$C_{10}H_{14}$	*m*-Diethylbenzene	−28 e	−7 e	20 e	56 e	106.2	180.6	5
$C_{10}H_{14}$	*p*-Diethylbenzene	−28 e	−6 e	21 e	57 e	108.1	183.3	5
$C_{10}H_{14}$	3-Ethyl-1,2-dimethylbenzene	−22 e	0 e	28 e	66 e	117.2	193.4	5
$C_{10}H_{14}$	4-Ethyl-1,2-dimethylbenzene	−24 e	−2 e	26 e	63 e	113.6	189.2	5
$C_{10}H_{14}$	2-Ethyl-1,3-dimethylbenzene		−2 e	26 e	63 e	113.7	189.5	5
$C_{10}H_{14}$	2-Ethyl-1,4-dimethylbenzene	−27 e	−5 e	23 e	60 e	110.6	186.4	5
$C_{10}H_{14}$	1-Ethyl-2,4-dimethylbenzene	−25 e	−4 e	24 e	61 e	112.2	187.9	5
$C_{10}H_{14}$	1-Ethyl-3,5-dimethylbenzene	−28 e	−6 e	21 e	58 e	108.3	183.2	5
$C_{10}H_{14}$	1-Methyl-2-propylbenzene	−27 e	−6 e	22 e	58.2	108.9	184.3	5
$C_{10}H_{14}$	1-Methyl-3-propylbenzene	−29 e	−8 e	20 e	56.1	106.5	181.3	5
$C_{10}H_{14}$	1-Methyl-4-propylbenzene	−29 e	−7 e	20 e	56.6	107.4	182.8	5
$C_{10}H_{14}$	1,2,3,4-Tetramethylbenzene		7 e	36 e	74 e	126.6	204.5	5
$C_{10}H_{14}$	1,2,3,5-Tetramethylbenzene	−19 e	3 e	32 e	69 e	120.9	197.5	5
$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene					119.9	196.3	5
$C_{10}H_{14}O$	2-Butylphenol	7 e	31 e	61 e	101 e	155.2	234.4	5
$C_{10}H_{14}O$	Butyl phenyl ether	−16 e	8 e	38 e	77 e	131.3	209.7	5
$C_{10}H_{14}O$	Thymol	18.9 s	37.9 s	59.5	101.2	155.0	230.4	5
$C_{10}H_{15}N$	2-Methyl-5-isopropylaniline	19 e	43 e	72 e	107.4	150 e	204 e	5
$C_{10}H_{15}N$	*N*-Butylaniline	11 e	35 e	66 e	106 e	160.9	241.0	5
$C_{10}H_{15}N$	*N,N*-Diethylaniline	−11 e	14 e	44.3	84.2	138.4	216.3	5
$C_{10}H_{16}$	Dipentene	−42 e	−19 e	10.6	48.7	100.2	173.9	5
$C_{10}H_{16}$	*d*-Limonene	−45 e	−21 e	9.1	48.0	100.4	174.5	5
$C_{10}H_{16}$	*l*-Limonene	−33 e	−12 e	16 e	52.0	102.3	177.0	21
$C_{10}H_{16}$	β-Myrcene			9.4	47.3	98.3	171.0	5
$C_{10}H_{16}$	α-Pinene	−48 e	−27 e	−1 e	33.6	82.2	155.1	21
$C_{10}H_{16}$	β-Pinene	−43 e	−22 e	5.0	40.6	90.5	165.5	21
$C_{10}H_{16}$	Camphene					90.7	160.1	4
$C_{10}H_{16}$	Terpinolene			26.5	64.9	115.4	184.6	5
$C_{10}H_{16}$	β-Phellandrene			16 e	53.2	104 e	171.0	5
$C_{10}H_{16}O$	(+)-Camphor	−15.8 s	10 s	41.5 s	80.8 s	131.4 s	207.6	5
$C_{10}H_{16}O$	Pulegone	37 e	49.1	66.4	92.2	135.1	220.2	5
$C_{10}H_{18}$	1-Decyne	−34 e	−13 e	14 e	51 e	100.3	173.5	5
$C_{10}H_{18}$	*cis*-Decahydronaphthalene	−26 e	−4 e	24 e	62.4	115.5	195.3	1

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_{10}H_{18}$	*trans*-Decahydronaphthalene		−10 e	18 e	55.3	107.9	186.8	1
$C_{10}H_{18}O$	α-Terpineol			48	89	142	217	4
$C_{10}H_{18}O$	Eucalyptol			10.6	48.5	100.3	175.4	5
$C_{10}H_{18}O$	*trans*-Geraniol	4 e	31 e	63.2	104.3	157.7	229.6	5
$C_{10}H_{18}O_4$	Sebacic acid	125.9 s						5
$C_{10}H_{18}O_4$	Dipropyl succinate	11 e	38 e	72.1	115.4	172.3	250.4	5
$C_{10}H_{18}O_4$	Diethyl adipate	4 e	35 e	72 e	116.6	171.2	239.5	5
$C_{10}H_{19}N$	Decanenitrile	13 e	36 e	66 e	105.8	160.6	241.6	5
$C_{10}H_{20}$	1-Decene	−35.5	−13.7	13.7	49.0	97.9	170.1	1,5
$C_{10}H_{20}$	Cyclodecane			29 e	68 e	121.3	201.8	1
$C_{10}H_{20}$	Butylcyclohexane	−31 e	−9 e	18 e	54 e	104.7	180.4	5
$C_{10}H_{20}$	Isobutylcyclohexane	−37 e	−16 e	10 e	46 e	95.9	170.8	5
$C_{10}H_{20}$	*tert*-Butylcyclohexane	−39 e	−18 e	9 e	45 e	95.3	171.1	5
$C_{10}H_{20}O$	Decanal		16 e	47.2	86.3	137.7	208.0	5
$C_{10}H_{20}O_2$	Decanoic acid	58 e	80 e	108 e	145 e	195.2	269.5	5
$C_{10}H_{20}O_2$	Octyl acetate	−26 e	−3 e	27 e	66.3	120.0	198.2	5
$C_{10}H_{20}O_2$	2-Ethylhexyl acetate	−11 e	5 e	26 e	57.6	107.1	197.2	5
$C_{10}H_{20}O_2$	Isopentyl isopentanoate			22 e	62.8	116.9	193.6	5
$C_{10}H_{20}O_2$	Ethyl octanoate	−17 e	9 e	41 e	81.4	133.2	203 e	5
$C_{10}H_{20}O_4$	Diethylene glycol monobutyl ether acetate	6 e	34 e	69 e	112.6	169.2	245.4	5
$C_{10}H_{21}Br$	1-Bromodecane	9 e	33 e	63 e	104 e	159.2	240.0	5
$C_{10}H_{21}Cl$	1-Chlorodecane	2 e	25 e	54 e	92 e	145.7	225.3	5
$C_{10}H_{21}F$	1-Fluorodecane	−22 e	0 e	27 e	64 e	113.3	185.7	5
$C_{10}H_{22}$	Decane		−10.6	16.7	52.3	101.1	173.7	16
$C_{10}H_{22}$	2-Methylnonane	−34 e	−14 e	12 e	47 e	94.8	166.5	5
$C_{10}H_{22}$	3-Methylnonane	−34 e	−14 e	12 e	47 e	95.1	167.3	5
$C_{10}H_{22}$	4-Methylnonane	−36 e	−16 e	10 e	45 e	93.1	165.2	5
$C_{10}H_{22}$	5-Methylnonane	−36 e	−16 e	10 e	45 e	92.6	164.6	5
$C_{10}H_{22}$	2,4-Dimethyloctane				38 e	84.9	155.4	5
$C_{10}H_{22}$	2,7-Dimethyloctane	−39 e	−19 e	7 e	41 e	88.4	159.4	5
$C_{10}H_{22}$	2,2,6-Trimethylheptane	−46 e	−27 e	−2 e	32 e	78.5	148.4	5
$C_{10}H_{22}$	3,3,5-Trimethylheptane			0 e	35 e	82.7	155.2	5
$C_{10}H_{22}$	2,2,3,3-Tetramethylhexane	−46 e	−25 e	1 e	36 e	85.6	159.8	5
$C_{10}H_{22}$	2,2,5,5-Tetramethylhexane			−10 e	22 e	68.3	137.0	5
$C_{10}H_{22}$	2,4-Dimethyl-3-isopropylpentane	−46 e	−26 e	0 e	35 e	83.2	156.5	5
$C_{10}H_{22}$	2,2,3,3,4-Pentamethylpentane		−24 e	3 e	39 e	89.1	165.5	5
$C_{10}H_{22}$	2,2,3,4,4-Pentamethylpentane		−29 e	−3 e	33 e	82.8	158.7	5
$C_{10}H_{22}O$	1-Decanol	30 e	50 e	75 e	109 e	157.3	230.6	1,39
$C_{10}H_{22}O$	4-Decanol	18 e	37 e	61 e	93 e	139 e	210 e	5
$C_{10}H_{22}O$	Dipentyl ether	−31 e	−8 e	22 e	60 e	111.6	186.2	5
$C_{10}H_{22}O$	Diisopentyl ether			14.0	51.5	101.8	172.8	5
$C_{10}H_{22}O_2$	Ethylene glycol dibutyl ether	0 e	20 e	44 e	78.4	127.1	202.9	5
$C_{10}H_{22}O_5$	Tetraethylene glycol dimethyl ether				138 e	200.9	275.3	5
$C_{10}H_{22}S$	1-Decanethiol	11 e	34 e	64 e	103 e	157.5	238.6	5
$C_{10}H_{22}S$	Diisopentylsulfide			7 e	82 e	118 e	139 e	5
$C_{10}H_{23}N$	Dipentylamine				77 e	127.7	202.0	5
$C_{10}H_{30}O_3Si_4$	Decamethyltetrasiloxane	−31 e	−6 e	26 e	66.8	118.8	193.9	5
$C_{10}H_{30}O_5Si_5$	Decamethylcyclopentasiloxane	−2 e	19 e	46 e	82 e	132.9	210.4	5
$C_{11}H_8O_2$	1-Naphthalenecarboxylic acid				191.9	239.3	299.6	5
$C_{11}H_8O_2$	2-Naphthalenecarboxylic acid				197.9	246.0	308.1	5
$C_{11}H_{10}$	1-Methylnaphthalene	5 e	29 e	60 e	102 e	159.1	244.1	1
$C_{11}H_{10}$	2-Methylnaphthalene			57 e	99 e	156.0	240.5	1
$C_{11}H_{12}O_2$	Ethyl *trans*-cinnamate			79	125	187	271	4
$C_{11}H_{12}O_3$	Myristicin	23 e	53 e	88.9	135.2	196.0	279.4	5
$C_{11}H_{14}$	4-Isopropylstyrene	−25 e	−1 e	30.2	70.3	124.5	202.1	5
$C_{11}H_{14}$	1,2,3,4-Tetrahydro-5-methylnaphthalene	9 e	31 e	60 e	99 e	153.1	233.8	5
$C_{11}H_{14}$	1,2,3,4-Tetrahydro-6-methylnaphthalene	17 e	36 e	62 e	97 e	147.8	228.5	5
$C_{11}H_{14}O_2$	Butyl benzoate	6 e	34 e	67.9	110.3	165 e	237 e	5
$C_{11}H_{16}$	Pentylbenzene	−14 e	8 e	37 e	74 e	126.7	204.9	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_{11}H_{16}$	*p-tert*-Butyltoluene	−24 e	−2 e	27 e	64.1	115.5	190.8	5
$C_{11}H_{16}$	1,3-Diethyl-5-methylbenzene	−26 e	−1 e	29.5	69.5	123.5	200.2	5
$C_{11}H_{16}$	2-Ethyl-1,3,5-trimethylbenzene		6 e	36 e	75.7	129.6	207.6	5
$C_{11}H_{16}$	1-Ethyl-2,4,5-trimethylbenzene	−13 e	11 e	40 e	79.4	132.1	207.7	5
$C_{11}H_{20}$	1-Undecyne	−22 e	0 e	29 e	67 e	118.5	194.5	5
$C_{11}H_{20}$	2-Undecyne	−17 e	6 e	35 e	74 e	127.4	205.4	5
$C_{11}H_{20}O_2$	10-Undecenoic acid	35 e	67 e	105 e	150.0	205.4	274.5	5
$C_{11}H_{20}O_4$	Ethyl diethylmalonate			74 e	105 e	149.4	219 e	5
$C_{11}H_{21}N$	Undecanenitrile			78.6	120.3	177.3	259.9	5
$C_{11}H_{22}$	1-Undecene	−21.6	1.2	29.7	66.4	117.1	192.2	5
$C_{11}H_{22}$	*cis*-2-Undecene	−14 e	7 e	34 e	70.2	120.6	196 e	5
$C_{11}H_{22}$	*trans*-2-Undecene	−14 e	7 e	33 e	69.3	119.6	195 e	5
$C_{11}H_{22}$	*cis*-4-Undecene	−19 e	3 e	30 e	66.6	117.1	192 e	5
$C_{11}H_{22}$	*trans*-4-Undecene	−17 e	4 e	31 e	67.1	117.4	193 e	5
$C_{11}H_{22}$	*cis*-5-Undecene	−19 e	2 e	30 e	66.2	116.7	191 e	5
$C_{11}H_{22}$	*trans*-5-Undecene	−18 e	3 e	31 e	67.0	117.4	192 e	5
$C_{11}H_{22}$	Pentylcyclohexane	−17 e	6 e	34 e	72 e	124.2	202.7	5
$C_{11}H_{22}$	Hexylcyclopentane	−15 e	7 e	36 e	73 e	125.0	202.5	5
$C_{11}H_{22}O$	2-Undecanone	17 e	37 e	64.3	103.0	153.6	232.6	1,5
$C_{11}H_{22}O$	6-Undecanone		28 e	57 e	95 e	148.4	226.9	1
$C_{11}H_{22}O_2$	Undecanoic acid	68 e	90 e	118 e	156 e	207.2	283.6	5
$C_{11}H_{22}O_2$	Heptyl butanoate	2 e	29 e	62 e	102.6	155.1	224.7	5
$C_{11}H_{22}O_2$	Propyl octanoate	−2 e	23 e	55 e	94.0	145.2	215 e	5
$C_{11}H_{22}O_2$	Methyl decanoate	10 e	33 e	62 e	100.9	154.0	232 e	5
$C_{11}H_{24}$	Undecane	−18.4	4.3	32.6	69.5	120.2	195.4	16
$C_{11}H_{24}$	2-Methyldecane	−20 e	1 e	28 e	64 e	114.0	188.7	5
$C_{11}H_{24}$	3-Methyldecane	−35 e	−10 e	22 e	61.9	115.6	190.4	5
$C_{11}H_{24}$	4-Methyldecane	−38 e	−12 e	20 e	60.8	113.9	186.4	5
$C_{11}H_{24}$	2,4,7-Trimethyloctane				43 e	94 e	170.4	5
$C_{11}H_{24}O$	1-Undecanol	52.2	80.0	82 e	118 e	167.6	244.1	5
$C_{11}H_{24}S$	1-Undecanethiol	23 e	47 e	77 e	118 e	173.6	256.8	5
$C_{12}F_{27}N$	Trinonafluorobutylamine		3 e	29.0	63.3	109.9	176.8	5
$C_{12}H_8$	Acenaphthylene	24 s	49.8 s	80.6 s				5
$C_{12}H_9N$	Carbazole					254.7	354.0	5
$C_{12}H_{10}$	Acenaphthene				126.2	187 e	276 e	1
$C_{12}H_{10}$	Biphenyl			69.0	111.1	169.5	254.7	1
$C_{12}H_{10}N_2$	Azobenzene			98.1	144.8	206.7	292.7	4
$C_{12}H_{10}O$	Diphenyl ether		44 e	75 e	116 e	173 e	257.4	5
$C_{12}H_{10}O$	1-Acetonaphthone	37 e	69 e	107.0	154.6	215.2	294.9	5
$C_{12}H_{10}O$	2-Acetonaphthone	48.3 s		118.7	163.0	221.1	300.3	5
$C_{12}H_{10}S$	Diphenyl sulfide	20 e	51 e	88.7	137.5	202.2	291.8	5
$C_{12}H_{11}N$	Diphenylamine	48 s		102.8	150.5	213.7	301.4	5
$C_{12}H_{12}$	1-Ethylnaphthalene	16 e	41 e	72 e	114 e	171.8	257.7	5
$C_{12}H_{12}$	2-Ethylnaphthalene	14 e	39 e	71 e	113 e	171.2	257.3	5
$C_{12}H_{12}$	1,2-Dimethylnaphthalene	26 e	51 e	82 e	123 e	180.5	265.7	5
$C_{12}H_{12}$	2,7-Dimethylnaphthalene	31.5 s	53.1 s	78.8 s	115.9	175 e	260 e	5
$C_{12}H_{14}O_4$	Diethyl phthalate	12 e	51 e	96 e	150.5	215.9	296.2	5
$C_{12}H_{16}$	*p*-Isopropenylisopropylbenzene	−11 e	15 e	46 e	87 e	142.4	221 e	5
$C_{12}H_{16}$	Cyclohexylbenzene		28 e	58 e	98 e	154.7	239.5	5
$C_{12}H_{16}O_2$	3-Methylbutyl benzoate			66 e	115.0	177.7	261.4	5
$C_{12}H_{18}$	Hexylbenzene	−2 e	22 e	51 e	90 e	144.5	225.5	5
$C_{12}H_{18}$	1,2-Diisopropylbenzene	−14 e	9 e	37 e	74 e	125.9	203.2	5
$C_{12}H_{18}$	1,3-Diisopropylbenzene	−14 e	8 e	36 e	74 e	125.5	202.6	5
$C_{12}H_{18}$	1,4-Diisopropylbenzene	−6 e	18 e	49 e	90 e	148.8	238 e	5
$C_{12}H_{18}$	Hexamethylbenzene	46.3 s	72.5 s	81.7 s	121.8 s	178.3	263.7	5
$C_{12}H_{18}$	1,5,9-Cyclododecatriene	−14 e	11 e	44 e	87 e	145.0	229.8	5
$C_{12}H_{20}O_2$	Geranyl acetate			67.7	110.8	166.9	242.9	5
$C_{12}H_{20}O_4$	Dibutyl maleate	12.3	50.4	94.0	144.2	203 e	272 e	5
$C_{12}H_{22}$	1-Dodecyne	−11 e	13 e	43 e	82 e	135.8	214.4	5
$C_{12}H_{22}$	Cyclohexylcyclohexane		20 e	53.1	96.0	154.1	237.2	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_{12}H_{22}O_2$	Methyl 10-undecenoate	10 e	38 e	73 e	116 e	172.2	247.1	5
$C_{12}H_{22}O_4$	Dimethyl sebacate		53 e	97	150	214	293	4
$C_{12}H_{23}N$	Dodecanenitrile	36 e	60 e	92 e	133 e	190.5	275.5	5
$C_{12}H_{24}$	1-Dodecene	−8.3	15.2	44.8	82.9	135.4	212.8	5
$C_{12}H_{24}$	Hexylcyclohexane	−3 e	20 e	50 e	89 e	143.1	224.2	5
$C_{12}H_{24}$	Heptylcyclopentane	−1 e	22 e	51 e	90 e	143.5	223.5	5
$C_{12}H_{24}O$	Dodecanal			70 e	116.2	175.9	256.6	5
$C_{12}H_{24}O_2$	Dodecanoic acid	78 e	100 e	128 e	166 e	219.1	298.1	5
$C_{12}H_{24}O_2$	Decyl acetate	12 e	40 e	74 e	115.1	168.1	238 e	5
$C_{12}H_{24}O_2$	Ethyl decanoate	8 e	35 e	69 e	111.8	166.1	238 e	5
$C_{12}H_{25}Br$	1-Bromododecane	31 e	57 e	90 e	132 e	190.8	275.3	5
$C_{12}H_{25}Cl$	1-Chlorododecane	27 e	51 e	81 e	122 e	178.7	262.6	5
$C_{12}H_{26}$	Dodecane	−5.4	18.2	47.6	85.8	138.2	215.8	16
$C_{12}H_{26}O$	1-Dodecanol				133 e	185.0	264.1	1
$C_{12}H_{26}O_3$	Diethylene glycol dibutyl ether	5 e	34.4	70.2	115.3	174.1	253.8	5
$C_{12}H_{27}N$	Tributylamine	−26 e	1 e	35 e	77.7	134.5	213.4	5
$C_{12}H_{27}N$	Triisobutylamine		1 e	28.9	64.9	112.5	178.5	5
$C_{12}H_{27}O_4P$	Tributyl phosphate					205 e	288.3	5
$C_{12}H_{36}O_6Si_6$	Dodecamethylcyclohexasiloxane	18 e	41 e	69 e	108 e	162.2	244.7	5
$C_{13}H_9N$	Acridine			124.4	176.2	246.0	345.4	5
$C_{13}H_9N$	Phenanthridine	79 s						5
$C_{13}H_{10}$	Fluorene	48.4 s			137.4	205.4	295 e	5
$C_{13}H_{10}O_2$	Phenyl benzoate			102.3	151.4	217.9	313.3	5
$C_{13}H_{10}O_3$	Phenyl salicylate				166.0	224.8	312.4	5
$C_{13}H_{12}$	Diphenylmethane		45 e	77 e	119.3	177.7	263.6	1,5
$C_{13}H_{13}N$	Methyldiphenylamine	35 e	63 e	98.4	143.1	201.6	281.6	5
$C_{13}H_{14}$	1-Isopropylnaphthalene	27 e	51 e	82 e	123.2	180.8	267.3	5
$C_{13}H_{20}$	Heptylbenzene	12 e	36 e	66 e	107 e	162.7	246.2	5
$C_{13}H_{24}O_2$	Ethyl 10-undecenoate	32 e	55 e	86 e	125.2	179.5	258.4	5
$C_{13}H_{26}$	1-Tridecene	4.1	28.5	59.0	98.3	152.5	232.3	5
$C_{13}H_{26}$	Heptylcyclohexane	11 e	34 e	65 e	105 e	160.9	244.3	5
$C_{13}H_{26}$	Octylcyclopentane	13 e	36 e	66 e	106 e	160.9	243.1	5
$C_{13}H_{26}O_2$	Tridecanoic acid	87 e	109 e	138 e	176 e	230.3	311.5	5
$C_{13}H_{26}O_2$	Methyl dodecanoate	38 e	61 e	90 e	130 e	184.9	269 e	5
$C_{13}H_{28}$	Tridecane	7.2	31.5	61.8	101.1	155.1	234.9	16
$C_{13}H_{28}O$	1-Tridecanol	71.6	101.0	103 e	140 e	192.3	273.1	5
$C_{14}H_{10}$	Anthracene	89.2 s	125.9 s	151.5 s	165 s	238.8	340.2	1,5
$C_{14}H_{10}$	Phenanthrene	53 s	83 s	120.8	170.4	238.4	337.7	5
$C_{14}H_{10}O_2$	Benzil			123	175	246	346	4
$C_{14}H_{12}$	*cis*-Stilbene	26 e	54 e	88 e	130.4	183 e	253 e	5
$C_{14}H_{12}$	*trans*-Stilbene				155.6	218.1	305.8	5
$C_{14}H_{12}O_2$	Benzoin				181	248	342	4
$C_{14}H_{14}$	1,1-Diphenylethane	19 e	47 e	82.0	125.3	181 e	254 e	5
$C_{14}H_{15}N$	Dibenzylamine	48 e	77 e	113.1	158.9	218.5	299.4	5
$C_{14}H_{16}$	1-Butylnaphthalene	67 e	82 e	103 e	135 e	186.7	288.6	5
$C_{14}H_{16}$	2-Butylnaphthalene	44 e	67 e	98 e	139 e	197.5	287.4	5
$C_{14}H_{22}$	Octylbenzene	20.1	46.2	79.1	121.9	178.1	263.8	5
$C_{14}H_{26}O_4$	Diethyl sebacate		83 e	120	166	225	305	4
$C_{14}H_{27}N$	Tetradecanenitrile	52 e	79 e	114.0	159.0	219.7	306.3	5
$C_{14}H_{28}$	1-Tetradecene	16.1	41.3	72.7	113.2	168.7	250.6	5
$C_{14}H_{28}$	Octylcyclohexane	16.9	44.3	77.8	120.0	177.6	263.2	5
$C_{14}H_{28}$	Nonylcyclopentane	25 e	49 e	80 e	120 e	177.2	261.5	5
$C_{14}H_{28}O_2$	Tetradecanoic acid	96 e	118 e	147 e	186 e	241.3	325.6	5
$C_{14}H_{30}$	Tetradecane	19.1	44.1	75.3	115.7	171.1	253.0	16
$C_{14}H_{30}O$	1-Tetradecanol	80.0	110.5	149.6	152 e	205.3	286.7	5
$C_{14}H_{31}N$	Tetradecylamine			104 e	147 e	206.1	290.9	5
$C_{14}H_{42}O_5Si_6$	Tetradecamethylhexasiloxane	6 e	36 e	72 e	117 e	176.0	259.1	5
$C_{15}H_{18}$	1-Pentylnaphthalene	34 e	62 e	96 e	141.3	202.2	289 e	5
$C_{15}H_{24}$	Nonylbenzene	33.0	58.9	92.0	135.4	193.7	281.4	5
$C_{15}H_{30}$	Nonylcyclohexane	35 e	60 e	92 e	134 e	193.4	280.9	5

		Temperature in °C for the indicated pressure						
Mol. form.	**Name**	**1 Pa**	**10 Pa**	**100 Pa**	**1 kPa**	**10 kPa**	**100 kPa**	**Ref.**
$C_{15}H_{30}$	Decylcyclopentane	37 e	61 e	93 e	134 e	192.5	278.8	5
$C_{15}H_{30}O_2$	Methyl tetradecanoate		75 e	110	155	214	295	4
$C_{15}H_{32}$	Pentadecane	30.5	56.1	88.1	129.6	186.3	270.1	16
$C_{16}H_{22}O_4$	Dibutyl phthalate		104.0	142.7	191.5	254.5	339.4	4
$C_{16}H_{32}$	1-Hexadecene	38.4	65.0	98.1	140.5	198.8	284.3	5
$C_{16}H_{32}O_2$	Hexadecanoic acid		136 e	165 e	205 e	261.9	350.2	5
$C_{16}H_{34}$	Hexadecane	41.1	67.4	100.3	142.7	200.7	286.3	16
$C_{16}H_{34}O$	1-Hexadecanol	99.5	130.6	171.9	175 e	229.0	311.7	5
$C_{16}H_{35}N$	Hexadecylamine	63 e	91 e	126 e	171 e	232.6	320.5	5
$C_{17}H_{10}O$	Benzanthrone		184 e	229.3	290.3	377.2	511 e	5
$C_{17}H_{34}O_2$	Methyl hexadecanoate	65 e	93	129	177			4
$C_{17}H_{36}$	Heptadecane	51.5	78.5	112.0	155.3	214.5	302 e	16
$C_{17}H_{36}O$	1-Heptadecanol	94 e	117 e	146 e	185 e	240.1	323.3	5
$C_{18}H_{14}$	*o*-Terphenyl	66 e	94 e	129 e	176 e	241.3	336.3	5
$C_{18}H_{14}$	*m*-Terphenyl	87 e	118 e	156 e	206.6	275.3	374.6	5
$C_{18}H_{14}$	*p*-Terphenyl	127.1 s	154.7 s		217.2	284.0	383.0	5
$C_{18}H_{30}$	Hexaethylbenzene				144.1	206.8	297.5	5
$C_{18}H_{34}O_2$	Oleic acid	94 e	126 e	165.5	214.5	277.0	359.7	5
$C_{18}H_{34}O_2$	Elaidic acid		124 e	166	216	280	361	4
$C_{18}H_{36}O$	Stearaldehyde			142 e	186 e	246.9	336.7	5
$C_{18}H_{36}O_2$	Stearic acid		153 e	183 e	223 e	281.6	374.5	5
$C_{18}H_{38}$	Octadecane	61.5	89.0	123.1	167.3	227.6	316 e	16
$C_{18}H_{38}O$	1-Octadecanol	106 e	130 e	160 e	200.5	257.3	343.0	5
$C_{19}H_{16}$	Triphenylmethane	81 s		112 e	175 e	254.6	360.0	5
$C_{19}H_{36}O_2$	Methyl oleate	85 e	114 e	149.7	195.6	256 e	340 e	5
$C_{19}H_{40}$	Nonadecane	71.1	99.1	133.8	178.8	240.1	330 e	16
$C_{20}H_{42}$	Eicosane	80.4	108.9	144.2	189.8	252.1	344 e	16
$C_{20}H_{42}O$	1-Eicosanol	119 e	143 e	173 e	213 e	270.0	355.1	5
$C_{20}H_{60}O_8Si_9$	Eicosamethylnonasiloxane			141 e	183.1	236.7	307.1	5
$C_{21}H_{21}O_4P$	Tri-*o*-cresyl phosphate	119.0	156.1	201.0	256.3	326.3	418 e	5
$C_{21}H_{21}O_4P$	Tri-*m*-cresyl phosphate	147.8	177.3	211.4	251.3	298 e	355 e	5
$C_{21}H_{21}O_4P$	Tri-*p*-cresyl phosphate	140.6	174 e	214 e	262 e	320 e	392 e	5
$C_{21}H_{44}$	Heneicosane	82.3	113.5	152.2	201.6	263.8	355.9	5
$C_{22}H_{42}O_2$	Brassidic acid	134 e	166 e	203.6	249.8	307.6	382.0	5
$C_{22}H_{42}O_2$	Erucic acid	126 e	160 e	199.4	247.4	306.5	381.1	5
$C_{22}H_{42}O_2$	Butyl oleate	95.5	124.2	158 e	198 e	245 e	304 e	5
$C_{22}H_{44}O_2$	Behenic acid	145.4	176.5	213.7	259.3	316.2	390 e	5
$C_{22}H_{44}O_2$	Butyl stearate	99.6	128 e	162 e	201 e	249 e	307 e	5
$C_{22}H_{46}$	Docosane	83.5	115.0	154.0	203.6	274.8	368.0	5
$C_{23}H_{48}$	Tricosane	102.9	135.1	174.8	221 e	285.3	379.5	5
$C_{24}H_{38}O_4$	Dioctyl phthalate	130 e	163.7	203.8	252 e	311 e	385 e	5
$C_{24}H_{38}O_4$	Bis(2-ethylhexyl) phthalate	122.0	153.2	189.2	231.3	281.1	341.1	5
$C_{24}H_{50}$	Tetracosane	115.0	148.1	188.5	239.1	295.4	390.6	5
$C_{25}H_{52}$	Pentacosane	119.7	152.7	193.2	244.4	305.0	401.1	5
$C_{26}H_{54}$	Hexacosane	125.1	158.8	200.1	252.1	314.3	411.3	5
$C_{27}H_{56}$	Heptacosane	136.7	168.8	206.5	255.8	323.3	421.2	5
$C_{28}H_{58}$	Octacosane	136.5	169.8	210.9	263.1	332.0	430.6	5
$C_{29}H_{60}$	Nonacosane	148.2	182.8	221.2	271.5	340.2	439.7	5
$C_{30}H_{62}$	Squalane	66 e	84 e	105.8	131.9	163.7	203.2	5
C_{70}	Carbon (fullerene-C_{70})	598 s	662 s					22

VAPOR PRESSURE OF FLUIDS AT TEMPERATURES BELOW 300 K

This table gives vapor pressures of 67 important fluids in the temperature range 2 to 300 K. Helium (^{4}He), hydrogen (H_2), and neon (Ne) are covered on this page. The remaining fluids are listed on subsequent pages by molecular formula in the Hill order (see Introduction). The data have been taken from evaluated sources; references are listed at the end of the table.

Pressures are given in kilopascals (kPa). Note that:

1 kPa = 7.50062 Torr
100 kPa = 1 bar
101.325 kPa = 1 atmos

"s" following an entry indicates that the compound is solid at that temperature.

Helium		Hydrogen		Neon	
T/K	*P*/kPa	*T*/K	*P*/kPa	*T*/K	*P*/kPa
2.2	5.3	14.0	7.90	25.0	51.3
2.3	6.7	14.5	10.38	26.0	71.8
2.4	8.3	15.0	13.43	27.0	98.5
2.5	10.2	15.5	17.12	28.0	132.1
2.6	12.4	16.0	21.53	29.0	173.5
2.7	14.8	16.5	26.74	30.0	223.8
2.8	17.5	17.0	32.84	31.0	284.0
2.9	20.6	17.5	39.92	32.0	355.2
3.0	24.0	18.0	48.08	33.0	438.6
3.1	27.8	18.5	57.39	34.0	535.2
3.2	32.0	19.0	67.96	35.0	646.2
3.3	36.5	19.5	79.89	36.0	772.8
3.4	41.5	20.0	93.26	37.0	916.4
3.5	47.0	20.5	108.2	38.0	1078
3.6	52.9	21.0	124.7	39.0	1260
3.7	59.3	21.5	143.1	40.0	1462
3.8	66.1	22.0	163.2	41.0	1688
3.9	73.5	22.5	185.3	42.0	1939
4.0	81.5	23.0	209.4	43.0	2216
4.1	90.0	23.5	235.7	44.0	2522
4.2	99.0	24.0	264.2		
4.3	108.7	24.5	295.1		
4.4	119.0	25.0	328.5		
4.5	129.9	25.5	364.3		
4.6	141.6	26.0	402.9		
4.7	153.9	26.5	444.3		
4.8	167.0	27.0	488.5		
4.9	180.8	27.5	535.7		
5.0	195.4	28.0	586.1		
5.1	210.9	28.5	639.7		
		29.0	696.7		
		29.5	757.3		
		30.0	821.4		
		30.5	889.5		
		31.0	961.5		
		31.5	1038.0		
		32.0	1119.0		
		32.5	1204.0		
Ref.	17,18		1		13

T/K	Ar Argon	BCl_3 Boron trichloride	BF_3 Boron trifluoride	BrH Hydrogen bromide	Br_2 Bromine	ClF Chlorine fluoride	ClH Hydrogen chloride
50	0.1 s						
55	0.2 s						
60	0.8 s						
65	2.8 s						
70	7.7 s						
75	18.7 s						
80	40.7 s						
85	79.0						
90	134						
95	213						
100	324						
105	473						
110	666						
115	910					0.1	
120	1214					0.3	0.1 s
125	1584					0.6	0.3 s
130	2027					1.2	0.5 s
135	2553			0.1 s		2.1	1.0 s
140	3170			0.3 s		3.6	1.9 s
145	3892		7.7	0.6 s		6.0	3.4 s
150	4736		13.4	1.1 s		9.5	5.8 s
155			22.3	1.9 s		14.6	9.5 s
160			35.2	3.3 s		21.8	14.7
165			53.7	5.4 s		31.7	22.0
170			79.1	8.7 s		44.8	31.9
175			113	13.4 s		62.0	45.1

T/K	Ar Argon	BCl_3 Boron trichloride	BF_3 Boron trifluoride	BrH Hydrogen bromide	Br_2 Bromine	ClF Chlorine fluoride	ClH Hydrogen chloride
180		0.1	157	20.1 s		84.2	62.5
185		0.2	214	29.5 s		112	84.7
190		0.3	285	37.9		147	113
195		0.5	372	51.8		190	148
200		0.8	479	69.5		242	190
205		1.2	608	91.8		304	242
210		1.8	762	119		378	304
215		2.6	944	153		464	377
220		3.8	1160	194	0.1 s	564	463
225		5.2	1413	242	0.2 s	680	563
230		7.2	1709	299	0.3 s	812	678
235		9.7	2056	366	0.4 s	961	811
240		12.9	2460	443	0.7 s	1130	961
245		17.0	2913	532	1.1 s	1319	1132
250		22.0	3481	633	1.7 s	1529	1325
255		28.1	4123	748	2.6 s	1762	1542
260		35.6	4874	878	3.8 s	2019	1784
265		44.5		1023	5.5 s	2301	2054
270		55.1		1185	7.3	2608	2354
275		67.6		1364	9.5	2941	2686
280		82.2		1562	12.3	3303	3053
285		99.1		1780	15.6	3693	3457
290		119		2018	19.7	4111	3901
295		141		2278	24.6	4560	4388
300		166		2561	30.5	5039	4921
Ref.	8,15	12	12	12	12	12	12

T/K	ClO_2 Chlorine dioxide	Cl_2 Chlorine	Cl_4Si Silicon tetrachloride	FH Hydrogen fluoride	F_2 Fluorine	F_2O Difluorine oxide	F_3N Nitrogen trifluoride
50							
55					0.4		
60					1.5		
65					4.8		
70					12.3		
75					27.6	0.1	
80					55.3	0.2	
85					101	0.5	0.1
90					172	1.2	0.2
95					276	2.6	0.4
100					420	5.3	0.9
105					615	10.1	2.0
110					870	18.0	4.0
115					1196	30.5	7.3
120					1605	49.3	12.8
125					2108	76.7	21.1
130					2721	115	33.5
135					3458	168	51.1
140					4339	237	75.4
145						328	108
150						444	150
155						588	205
160						766	273
165						981	357
170						1238	459
175		1.8				1541	581
180		2.8				1895	726
185		4.2				2303	896
190		6.1		0.3		2771	1092
195	0.1	8.7		0.5		3302	1319
200	0.3	12.3		0.8		3899	1578
205	0.5	16.9		1.2		4567	1871
210	0.9	22.9	0.1	1.7		5308	2203

T/K	ClO_2 Chlorine dioxide	Cl_2 Chlorine	Cl_4Si Silicon tetrachloride	FH Hydrogen fluoride	F_2 Fluorine	F_2O Difluorine oxide	F_3N Nitrogen trifluoride
215	1.4	30.5	0.2	2.3			2577
220	2.3	40.1	0.3	3.2			2995
225	3.5	51.9	0.5	4.4			3464
230	5.3	66.4	0.7	5.9			3991
235	7.6	84.0	1.0	7.9			
240	10.8	105	1.5	10.3			
245	14.9	130	2.0	13.4			
250	20.1	160	2.8	17.2			
255	26.6	194	3.8	21.8			
260	34.6	234	5.0	27.4			
265	44.4	280	6.6	34.2			
270	56.1	332	8.6	42.2			
275	69.9	392	11.1	51.8			
280	86.2	459	14.2	63.1			
285	105	535	17.9	76.3			
290	127	619	22.3	91.7			
295	151	714	27.7	110			
300	179	818	34.0	130			
Ref.	12	5	12	12	12	12	1

T/K	F_3P Phosphorus trifluoride	F_4Si Silicon tetrafluoride	F_6S Sulfur hexafluoride	HI Hydrogen iodide	H_2S Hydrogen sulfide	H_3N Ammonia	H_3P Phosphine
105	0.1						
110	0.2						0.1
115	0.5						0.2
120	1.0						0.4
125	1.9	0.1 s					0.7
130	3.5	0.2 s					1.3
135	5.9	0.4 s			0.1 s		2.3
140	9.5	0.9 s	0.1 s		0.2 s		3.9
145	14.9	1.9 s	0.2 s		0.3 s		6.2
150	22.5	3.8 s	0.4 s		0.6 s		9.6
155	33.1	7.5 s	0.8 s	0.1 s	1.1 s		14.5
160	47.3	14.0 s	1.5 s	0.2 s	1.9 s	0.1 s	21.1
165	66.0	25.2 s	2.6 s	0.4 s	3.2 s	0.2 s	30.0
170	90.1	43.8 s	4.4 s	0.8 s	5.2 s	0.3 s	41.6
175	121	74.2 s	7.1 s	1.3 s	8.3 s	0.6 s	56.6
180	159	122 s	11.3 s	2.2 s	12.7 s	1.2 s	75.6
185	206	197 s	17.3 s	3.4 s	18.9 s	2.1 s	99.2
190	262	280	25.9 s	5.3 s	26.6	3.5 s	128
195	330	376	38.0 s	8.0 s	36.7	5.8 s	163
200	410	488	54.4 s	11.7 s	49.8	8.7	205
205	503	618	76.6 s	16.8 s	66.4	12.6	254
210	611	766	106 s	23.6 s	87.1	17.9	312
215	736	932	145 s	32.5 s	113	24.9	379
220	877	1117	195 s	44.0 s	144	34.1	456
225	1037	1324	249	56.2	182	45.9	544
230	1217	1555	305	71.4	227	60.8	644
235	1418	1816	371	89.7	281	79.6	756
240	1640	2111	448	112	344	103	881
245	1885	2449	536	137	416	131	1019
250	2154	2841	636	168	500	165	1172
255	2448	3301	750	203	597	207	1341
260	2767		878	244	706	256	1525
265	3112		1021	290	830	313	1725
270			1181	343	969	381	1942
275			1358	404	1124	460	2176
280			1554	472	1297	552	2428
285			1768	548	1488	655	2699
290			2003	633	1698	774	2987
295			2258	727	1929	909	3295
300			2534	831	2181	1062	3621
Ref.	12	12	12,15	12	12,15	11	12

T/K	H_4Si Silane	Kr Krypton	NO Nitric oxide	N_2 Nitrogen	N_2O Nitrous oxide	O_2 Oxygen	O_2S Sulfur dioxide
50				0.4 s			
55				1.8 s		0.2	
60				6.3 s		0.7	
65				17.4		2.3	
70				38.6		6.3	
75		0.1 s		76.1		14.5	
80		0.4 s		137		30.1	
85		1.1 s	0.1 s	229		56.8	
90		2.7 s	0.4 s	361		99.3	
95	0.1	6.0 s	1.3 s	541		163	
100	0.2	12.1 s	3.8 s	779		254	
105	0.4	22.8 s	10.0 s	1084		379	
110	1.0	40.4 s	23.5	1467		543	
115	1.9	68.0 s	46.8	1939	0.1	756	
120	3.5	103	86.5	2513	0.1	1022	
125	6.1	150	151	3209	0.3	1351	
130	10.0	211	248		0.7	1749	
135	15.8	290	391		1.3	2225	
140	24.1	388	592		2.5	2788	
145	35.3	509	867		4.3	3448	
150	50.3	655	1231		7.1	4219	
155	69.8	830	1703		11.4		
160	94.6	1037	2302		17.6		
165	126	1278	3050		26.4		
170	164	1557	3971		38.5		0.1
175	210	1877	5089		54.7		0.2
180	265	2241	6433		75.9		0.3
185	331	2655			103		0.5
190	408	3120			138		0.8
195	498	3641			181		1.3
200	602	4223			234		2.0
205	722	4870			298		3.0
210	859				374		4.4
215	1017				465		6.3
220	1196				571		9.0
225	1398				694		12.6
230	1628				835		17.3
235	1888				996		23.3
240	2180				1179		31.1
245	2509				1385		40.9
250	2880				1615		53.2
255	3296				1870		68.3
260	3763				2152		86.7
265	4288				2462		109
270					2802		136
275					3172		168
280					3573		205
285					4006		249
290					4473		300
295					4973		359
300					5508		426
Ref.	12	13, 15	12, 15	1	12	3	12

T/K	O_3 Ozone	Rn Radon	Xe Xenon	$CBrF_3$ Bromotri-fluoromethane	$CClF_3$ Chlorotri-fluoromethane	CCl_2F_2 Dichlorodi-fluoromethane	CCl_3F Trichloro-fluoromethane
100	0.1		0.1 s				
105	0.2		0.1 s				
110	0.4		0.3 s				
115	1.0		0.7 s		0.1		
120	2.0		1.5 s		0.2		
125	3.8		2.7 s		0.3		
130	6.8	0.1	4.9 s		0.6		

T/K	O_3 Ozone	Rn Radon	Xe Xenon		$CBrF_3$ Bromotri-fluoromethane	$CClF_3$ Chlorotri-fluoromethane	CCl_2F_2 Dichlorodi-fluoromethane	CCl_3F Trichloro-fluoromethane
135	11.5	0.3	8.5	s	0.1	1.1		
140	18.7	0.5	14.0	s	0.3	2.0		
145	29.1	0.9	22.2	s	0.5	3.3		
150	43.7	1.5	34.2	s	0.9	5.3		
155	63.6	2.4	51.1	s	1.5	8.3	0.1	
160	89.9	3.8	74.2	s	2.5	12.6	0.3	
165	124	5.8	101		3.9	18.6	0.5	
170	168	8.6	134		5.9	26.8	0.8	
175	222	12.5	173		8.8	37.6	1.3	
180	289	17.7	222		12.8	51.7	2.1	
185	367	24.5	280		18.1	69.7	3.2	
190	468	33.2	348		25.1	92.3	4.8	0.2
195	584	44.4	428		34.1	120	6.9	0.3
200	721	58.2	521		45.6	155	9.9	0.4
205	881	75.3	628		60.0	196	13.7	0.6
210	1068	96	750		77.8	246	18.8	1.0
215	1285	121	889		99.5	304	25.2	1.4
220	1536	151	1045		126	372	33.3	2.0
225	1824	185	1220		157	451	43.3	2.9
230	2155		1416		194	542	55.5	4.1
235	2534		1633		237	646	70.4	5.6
240	2968		1872		287	763	88.1	7.6
245	3464		2136		344	896	109	10.1
250	4031		2425		410	1044	134	13.3
255	4678		2742		485	1210	163	17.2
260	5417		3087		570	1394	196	22.1
265			3462		665	1598	234	28.0
270			3869		771	1823	278	35.1
275			4310		889	2071	327	43.7
280			4786		1021	2343	383	53.8
285			5299		1166	2641	445	65.7
290					1325	2968	515	79.6
295					1501	3325	593	95.6
300					1692	3716	679	114.1
Ref.	12	15	12,13		12	12	12	12

T/K	CCl_4 Tetrachloro-methane	CF_4 Tetrafluoro-methane	CO Carbon monoxide		COS Carbon oxysulfide	CO_2 Carbon dioxide		$CHClF_2$ Chlorodifluo-methane	$CHCl_3$ Trichloro-methane
50			0.1	s					
55			0.6	s					
60			2.6	s					
65			8.2	s					
70			21.0						
75			44.4						
80			83.7						
85			147						
90		0.1	239						
95		0.3	371						
100		0.8	545						
105		1.7	771						
110		3.4	1067						
115		6.5	1428						
120		11.5	1877						
125		19.3	2400						
130		30.8	3064						
135		47.4				0.1	s		
140		70.2			0.1	0.2	s		
145		101			0.2	0.4	s		
150		141			0.4	0.8	s	0.1	
155		191			0.8	1.7	s	0.3	

T/K	CCl_4 Tetrachloro-methane	CF_4 Tetrafluoro-methane	CO Carbon monoxide	COS Carbon oxysulfide	CO_2 Carbon dioxide	$CHClF_2$ Chlorodifluo-methane	$CHCl_3$ Trichloro-methane
160		254		1.3	3.1 s	0.5	
165		332		2.2	5.7 s	0.8	
170		425		3.4	9.9 s	1.4	
175		537		5.2	16.8 s	2.3	
180		669		7.8	27.6 s	3.6	
185		824		11.3	44.0 s	5.5	
190		1005		15.9	68.4 s	8.1	
195		1216		22.1	104 s	11.8	
200		1460		30.0	155 s	16.7	
205		1743		40.1	227 s	23.1	
210		2073		52.7	327 s	31.5	
215		2457		68.2	465 s	42.1	0.1
220		2907		87.2	599	55.3	0.2
225		3438		110	734	71.7	0.3
230				137	893	91.6	0.4
235				169	1075	116	0.7
240				207	1283	144	1.0
245				250	1519	178	1.4
250				301	1785	218	2.0
255	1.5			358	2085	264	2.7
260	2.1			423	2419	317	3.7
265	2.8			497	2790	377	5.0
270	3.7			580	3203	446	6.6
275	4.9			673	3658	525	8.7
280	6.4			777	4161	613	11.3
285	8.2			892	4714	711	14.4
290	10.5			1019	5318	821	18.3
295	13.2			1159	5984	944	22.9
300	16.5			1313	6713	1080	28.5
Ref.	12	12	9	12	6, 19	12	12

T/K	CHF_3 Trifluoro-methane	CHN Hydrogen cyanide	CH_2Cl_2 Dichloro-methane	CH_2F_2 Difluoro-methane	CH_2O Formaldehyde	CH_3Cl Chloromethane	CH_3F Fluoromethane
120	0.1						
125	0.2						
130	0.4						
135	0.7						0.6
140	1.4			0.1			1.2
145	2.5			0.2			2.1
150	4.3			0.3			3.6
155	7.1			0.6			5.9
160	11.1			1.0			9.3
165	17.0			1.7			14.1
170	25.3			2.8			20.9
175	36.5			4.4			29.9
180	51.4			6.8			42.0
185	70.9			10.2	1.3	2.1	57.6
190	95.8			14.8	2.0	3.1	77.4
195	127			21.2	3.0	4.6	102
200	166	0.1 s	0.1	29.5	4.4	6.7	133
205	214	0.2 s	0.2	40.5	6.4	9.5	171
210	271	0.4 s	0.3	54.5	9.1	13.1	216
215	340	0.6 s	0.4	72.1	12.7	17.9	270
220	421	1 s	0.6	94.1	17.4	24.0	333
225	516	1.5 s	0.9	121	23.4	31.8	408
230	626	2.2 s	1.4	154	31.0	41.4	495
235	754	3.3 s	2.0	193	40.6	53.3	595
240	900	4.7 s	2.8	240	52.5	67.7	711
245	1067	6.8 s	3.8	295	67.0	85.1	843
250	1257	9.7 s	5.3	360	84.6	106	993
255	1472	13.6 s	7.1	434	106	131	1163
260	1713	18.8	9.5	521	131	159	1355

T/K	CHF_3 Trifluoro-methane	CHN Hydrogen cyanide	CH_2Cl_2 Dichloro-methane	CH_2F_2 Difluoro-methane	CH_2O Formaldehyde	CH_3Cl Chloromethane	CH_3F Fluoromethane
265	1984	24.1	12.4	620	161	193	1571
270	2287	30.5	16.1	732	196	232	1813
275	2624	38.3	20.7	860	236	277	2084
280	3000	47.7	26.3	1004	283	327	2387
285	3418	58.8	33.0	1165	337	385	2724
290	3881	72.1	41.1	1346	399	450	3099
295	4393	87.6	50.8	1547	470	524	3516
300		105.9	62.1	1770	549	606	3978
Ref.	12	12,16	12	12	12	12	12

T/K	CH_4 Methane	CH_4O Methanol	C_2H_2 Acetylene	C_2H_4 Ethylene	C_2H_6 Ethane	C_2H_6O Dimethyl ether	C_3H_4 Propadiene
65	0.1						
70	0.3						
75	0.8						
80	2.1						
85	4.9						
90	10.6						
95	20.0						
100	34.5						
105	57.0						
110	88.4			0.3			
115	133			0.8	0.1		
120	192			1.4	0.4		
125	269			2.7	0.7		
130	368		0.1 s	4.5	1.3		
135	491		0.3 s	7.7	2.2		
140	642		0.7 s	11.9	3.8		
145	824		1.3 s	18.3	6.0		
150	1041		2.6 s	27.5	9.7		0.1
155	1297		4.6 s	39.9	15.0	0.1	0.2
160	1594		7.8 s	56.4	21.5	0.2	0.3
165	1937		12.8 s	77.9	31.0	0.3	0.6
170	2331		20.6 s	105	42.9	0.5	1.0
175	2779		32.2 s	140	59.0	0.9	1.7
180	3288		49.0 s	182	78.7	1.4	2.7
185	3865		72.9 s	234	104	2.1	4.1
190	4520		106 s	296	135	3.2	6.1
195			146	369	172	4.7	8.9
200			190	456	217	6.8	12.5
205			244	557	271	9.6	17.4
210			309	673	334	13.3	23.7
215			385	806	407	18.1	31.6
220			475	958	492	24.3	41.4
225			579	1128	590	32.1	53.5
230		0.1	699	1321	700	41.9	68.2
235		0.2	837	1535	826	53.9	85.8
240		0.4	993	1774	967	68.6	107
245		0.5	1170	2039	1125	86.3	131
250		0.8	1370	2331	1301	108	160
255		1.2	1593	2652	1496	133	193
260		1.7	1843	3005	1712	162	230
265		2.4	2121	3391	1949	197	273
270		3.3	2429	3813	2210	237	322
275		4.5	2771	4275	2495	283	376
280		6.2	3150		2806	335	438
285		8.3	3567		3146	395	506
290		11	4028		3515	463	582
295		14.4	4535		3917	538	666
300		18.7	5093		4355	623	759
Ref.	2,16	12	12,16	4	2	12	12

T/K	C_3H_6 Propylene	C_3H_8 Propane	C_4H_6 Buta-1,3-diene	C_4H_{10} Butane	C_4H_{10} Isobutane	C_5H_{12} Pentane	C_5H_{12} Neopentane	
140	0.1							
145	0.2							
150	0.4							
155	0.7							
160	1.2	0.8			0.1			
165	2.0	1.4			0.1			
170	3.1	2.2	0.1	0.1	0.3			
175	4.7	3.3	0.2	0.2	0.4			
180	7.0	5.0	0.4	0.3	0.7			
185	10.1	7.3	0.6	0.5	1.1		0.1	s
190	14.2	10.5	1.0	0.8	1.7		0.2	s
195	19.7	15.0	1.5	1.3	2.5		0.4	s
200	26.9	20.1	2.3	1.9	3.7		0.7	s
205	35.9	27.0	3.4	2.8	5.3		1.1	s
210	47.3	36.0	4.8	4.0	7.4		1.6	s
215	61.3	47.0	6.7	5.7	10.2		2.4	s
220	78.5	60.0	9.2	7.8	13.8	1.0	3.6	s
225	99.2	77.0	12.5	10.6	18.3	1.5	5.2	s
230	124	97.0	16.7	14.1	24.0	2.1	7.3	s
235	153	120	21.9	18.5	31.1	3.0	10.2	s
240	188	148	28.4	24.1	39.8	4.2	13.9	s
245	228	180	36.3	30.9	50.3	5.7	18.7	s
250	274	218	46.0	39.1	62.9	7.6	24.8	s
255	327	261	57.6	49.1	77.8	10.0	32.4	s
260	387	311	71.3	61.0	95.4	13.0	41.6	
265	456	367	87.6	75.0	116	16.6	51.4	
270	533	431	107	91.5	140	21.1	63.0	
275	619	502	129	111	167	26.6	76.6	
280	715	582	154	133	198	33.1	92.3	
285	822	671	184	159	234	40.8	111	
290	940	769	217	188	274	50.0	131	
295	1069	878	255	221	319	60.7	155	
300	1212	998	297	258	370	73.2	182	
Ref.	7	2	12	2	2	14	12,16	

References

1. B. A. Younglove, Thermophysical properties of fluids. I. Ethylene, parahydrogen, nitrogen trifluoride, and oxygen, *J. Phys. Chem. Ref. Data,* 11, Supp. 1, 1982.
2. B. A. Younglove and J. F. Ely, Thermophysical properties of fluids. II. Methane, ethane, propane, isobutane, and normal butane, *J. Phys. Chem. Ref. Data*, 16, 577, 1987.
3. W. Wagner, et al., *International Tables for the Fluid State: Oxygen*, Blackwell Scientific Publications, Oxford, 1987.
4. R. T. Jacobsen, et al., *International Tables for the Fluid State: Ethylene*, Blackwell Scientific Publications, Oxford, 1988.
5. S. Angus, et al., *International Tables for the Fluid State: Chlorine*, Pergamon Press, Oxford, 1985.
6. S. Angus, et al., *International Tables for the Fluid State: Carbon Dioxide*, Pergamon Press, Oxford, 1976.
7. S. Angus, et al., *International Tables for the Fluid State: Propylene*, Pergamon Press, Oxford, 1980.
8. R. B. Stewart and R. T. Jacobsen, Thermophysical properties of argon, *J. Phys. Chem. Ref. Data*, 18, 639, 1989.
9. R. D. Goodwin, Carbon monoxide thermophysical properties, *J. Phys. Chem. Ref. Data,* 14, 849, 1985.
10. R. D. Goodwin, Methanol thermophysical properties, *J. Phys. Chem. Ref. Data*, 16, 799, 1987.
11. L. Haar, Thermodynamic properties of ammonia, *J. Phys. Chem. Ref. Data*, 7, 635, 1978.
12. DIPPR Data Compilation of Pure Compound Properties, Design Institute for Physical Properties Data, American Institute of Chemical Engineers, 1987.
13. V. A. Rabinovich, et al., *Thermophysical Properties of Neon, Argon, Krypton, and Xenon*, Hemisphere Publishing Corp., New York, 1987.
14. K. N. Marsh, *Recommended Reference Methods for the Realization of Physicochemical Properties*, Blackwell Scientific Publications, Oxford, 1987.
15. TRC Thermodynamic Tables: Non-Hydrocarbons, Thermodynamic Research Center, Texas A & M University, College Station, Texas, 1985.
16. R. M. Stevenson and S. Malanowski, *Handbook of the Thermodynamics of Organic Compounds*, Elsevier, New York, 1987.
17. S. Angus and K. M. de Reuck, *International Tables of the Fluid State: Helium-4*, Pergamon Press, Oxford, 1977.
18. R. D. McCarty, *J. Phys. Chem. Ref. Data*, 2, 923, 1973.
19. R. Span and W. Wagner, *J. Phys. Chem. Ref. Data*, 25, 1509, 1996.

IUPAC RECOMMENDED DATA FOR VAPOR PRESSURE CALIBRATION

These precise vapor pressure values are recommended as secondary standards. Values are given in kPa (1 kPa = 0.0098692 atm = 7.5006 Torr). Reprinted by permission of IUPAC.

Reference

Marsh, K.N., Ed., *Recommended Reference Materials for the Realization of Physicochemical Properties*, Blackwell Scientific Publications, Oxford, 1987.

T/K	CO_2(s)	H_2O(s)	$C_{10}H_8$(s)	*n*–C_5H_{12}	C_6H_6	C_6F_6	H_2O	Hg
180	27.62							
190	68.44							
200	155.11	0.0002						
210	327.17	0.0007						
220		0.0026						
230		0.0089						
240		0.0273						
250		0.0760		7.60				
260		0.1958	0.0001	12.98				
270		0.4701	0.0005	21.15			0.485	
280			0.0017	33.11	5.148	4.322	0.991	
290			0.0049	50.01	8.606	7.463	1.919	
300			0.0134	73.17	13.816	12.328	3.535	
310			0.0341	104.07	21.389	19.576	6.228	
320			0.0814	144.3	32.054	30.009	10.540	
330			0.1829	195.7	46.656	44.578	17.202	
340			0.3899	260.1	66.152	64.380	27.167	
350			0.7920	339.4	91.609	90.664	41.647	
360				435.9	124.192	124.816	62.139	
370				551.5	165.2	168.4	90.453	
380				688.8	215.9	223.0	128.74	
390				850.2	277.7	290.4	179.48	
400				1038	353.2	372.6	245.54	0.138
410				1256	441.0	471.5	330.15	0.215
420				1507	545.5	589.3	436.89	0.329
430				1793	667.6	728.3	569.73	0.493
440				2120	808.8	890.9	732.99	0.724
450				2490	971.1	1080	931.36	1.045
460				2910	1156	1297	1169.9	1.485
470					1366	1547	1453.9	2.078
480					1602	1833	1789.0	2.866
490					1868	2159	2181.4	3.899
500					2164	2530	2637.3	5.239
510					2494	2954	3163.3	6.955
520					2861		3766.4	9.131
530					3267		4453.9	11.861
540					3717		5233.5	15.256
550					4216		6113.4	19.438
560					4770		7102.0	25.547
570							8208.6	30.74
580							9443.0	38.19
590							10816	47.09
600							12339	57.64

ENTHALPY OF VAPORIZATION

The molar enthalpy (heat) of vaporization $\Delta_{vap}H$, which is defined as the enthalpy change in the conversion of one mole of liquid to gas at constant temperature, is tabulated here for approximately 850 inorganic and organic compounds. Values are given, when available, both at the normal boiling point t_b, referred to a pressure of 101.325 kPa (760 mmHg), and at 25°C. Substances are listed by molecular formula in the modified Hill order (see Preface).

The values in this table were measured either by calorimetric techniques or by application of the Claperyon equation to the variation of vapor pressure with temperature. See Reference 1 for a discussion of the accuracy of different experimental techniques and for methods of estimating enthalpy of vaporization at other temperatures.

References

1. Majer, V. and Svoboda, V., *Enthalpies of Vaporization of Organic Compounds,* Blackwell Scientific Publications, Oxford, 1985.
2. Chase, M. W., Davies, C. A., Downey, J. R., Frurip, D. J., McDonald, R. A., and Syverud, A. N., *JANAF Thermochemical Tables, Third Edition, J. Phys. Chem. Ref. Data*, Vol. 14, Suppl. 1, 1985.
3. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, Sixth Edition,* II/4, *Caloric Quantities of State*, Springer-Verlag, Heidelberg, 1961.
4. Daubert, T. E., Danner, R. P., Sibul, H. M., and Stebbins, C. C., *Physical and Thermodynamic Properties of Pure Compounds: Data Compilation*, extant 1994 (core with 4 supplements), Taylor & Francis, Bristol, PA.
5. Ruzicka, K. and Majer, V., Simultaneous Treatment of Vapor Pressures and Related Thermal Data Between the Triple and Normal Boiling Temperatures for *n*–Alkanes C_5 – C_{20}, *J. Phys. Chem. Ref. Data*, 23, 1, 1994.
6. Verevkin, S. P., Thermochemistry of Amines: Experimental Standard Molar Enthalpies of Formation of Some Aliphatic and Aromatic Amines, *J. Chem. Thermodynamics*, 29, 891, 1997.
7. Cady, G. H. and Hargreaves, G. B., The Vapor Pressure of Some Heavy Transition Metal Hexafluorides, *J. Chem. Soc.*, 1563, 1961; 1578, 1961.
8. Steele, W. V., Chirico, R. D., Knipmeyer, S. E., and Nguyen, A., *J. Chem. Eng. Data*, 41, 1255, 1996.

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H$(25°C) kJ/mol
AgBr	Silver(I) bromide	1502	198	
AgCl	Silver(I) chloride	1547	199	
AgI	Silver(I) iodide	1506	143.9	
Al	Aluminum	2519	294	
AlB_3H_{12}	Aluminum borohydride	44.5	30	
$AlBr_3$	Aluminum tribromide	255	23.5	
AlI_3	Aluminum triiodide	382	32.2	
Ar	Argon	–185.85	6.43	
$AsBr_3$	Arsenic(III) bromide	221	41.8	
$AsCl_3$	Arsenic(III) chloride	130	35.01	
AsF_3	Arsenic(III) fluoride	57.8	29.7	
AsF_5	Arsenic(V) fluoride	–52.8	20.8	
AsH_3	Arsine	–62.5	16.69	
AsI_3	Arsenic(III) iodide	424	59.3	
Au	Gold	2856	324	
B	Boron	4000	480	
BBr_3	Boron tribromide	91	30.5	
BCl_3	Boron trichloride	12.65	23.77	23.1
BF_3	Boron trifluoride	–101	19.33	
BI_3	Boron triiodide	210	40.5	
B_2F_4	Tetrafluorodiborane	–34	28	
B_2H_6	Diborane	–92.4	14.28	
B_4H_{10}	Tetraborane	18	27.1	
B_5H_{11}	Pentaborane(11)	63	31.8	
Ba	Barium	1897	140	
$BeCl_2$	Beryllium chloride	482	105	
BeI_2	Beryllium iodide	487	70.5	
Bi	Bismuth	1564	151	
$BiBr_3$	Bismuth tribromide	453	75.4	
$BiCl_3$	Bismuth trichloride	447	72.61	
BrF	Bromine fluoride	20	25.1	
BrF_3	Bromine trifluoride	125.8	47.57	
BrF_5	Bromine pentafluoride	40.76	30.6	
BrH	Hydrogen bromide	–66.38		12.69
BrH_3Si	Bromosilane	1.9	24.4	
BrIn	Indium(I) bromide	656	92	
BrTl	Thallium(I) bromide	819	99.56	

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
Br_2	Bromine	58.8	29.96	30.91
Br_2Cd	Cadmium bromide	844	115	
Br_2H_2Si	Dibromosilane	66	31	
Br_2Hg	Mercury(II) bromide	322	58.89	
Br_2Pb	Lead(II) bromide	892	133	
Br_2Sn	Tin(II) bromide	639	102	
Br_2Zn	Zinc bromide	697	118	
Br_3Ga	Gallium(III) bromide	279	38.9	
Br_3HSi	Tribromosilane	109	34.8	
Br_3OP	Phosphorus(V) oxybromide	191.7	38	
Br_3P	Phosphorus(III) bromide	172.95	38.8	
Br_3Sb	Antimony(III) bromide	280	59	
Br_4Ge	Germanium(IV) bromide	186.35	41.4	
Br_4Si	Tetrabromosilane	154	37.9	
Br_4Sn	Tin(IV) bromide	205	43.5	
Br_4Ti	Titanium(IV) bromide	230	44.37	
Br_5Ta	Tantalum(V) bromide	349	62.3	
Cd	Cadmium	767	99.87	
$CdCl_2$	Cadmium chloride	960	124.3	
CdF_2	Cadmium fluoride	1748	214	
CdI_2	Cadmium iodide	742	115	
ClF	Chlorine fluoride	−101.1	24	
$ClFO_3$	Perchloryl fluoride	−46.75	19.33	
ClF_2P	Phosphorus(III) chloride difluoride	−47.25	17.6	
ClF_3	Chlorine trifluoride	11.75	27.53	
ClF_3Si	Chlorotrifluorosilane	−70.0	18.7	
ClH	Hydrogen chloride	−85	16.15	9.08
ClH_3Si	Chlorosilane	−30.4	21	
ClNO	Nitrosyl chloride	−5.5	25.78	
$ClNO_2$	Nitryl chloride	−15	25.7	
ClO_2	Chlorine dioxide	11	30	
ClTl	Thallium(I) chloride	720	102.2	
Cl_2	Chlorine	−34.04	20.41	17.65
Cl_2Cr	Chromium(II) chloride	1300	197	
Cl_2CrO_2	Chromyl chloride	117	35.1	
Cl_2FP	Phosphorus(III) dichloride fluoride	14	24.9	
Cl_2F_2Si	Dichlorodifluorosilane	−32	21.2	
Cl_2H_2Si	Dichlorosilane	8.3	25	24.2
Cl_2Hg	Mercury(II) chloride	304	58.9	
Cl_2O	Chlorine monoxide	2.2	25.9	
Cl_2OS	Thionyl chloride	75.6	31.7	31
Cl_2O_2S	Sulfuryl chloride	69.4	31.4	30.1
Cl_2Pb	Lead(II) chloride	951	127	
Cl_2Sn	Tin(II) chloride	623	86.8	
Cl_2Ti	Titanium(II) chloride	1500	232	
Cl_2Zn	Zinc chloride	732	126	
Cl_3Ga	Gallium(III) chloride	201	23.9	
Cl_3HSi	Trichlorosilane	33		25.7
Cl_3OP	Phosphorus(V) oxychloride	105.5	34.35	38.6
Cl_3OV	Vanadyl trichloride	127	36.78	
Cl_3P	Phosphorus(III) chloride	75.95	30.5	32.1
Cl_3Sb	Antimony(III) chloride	220.3	45.19	
Cl_3Ti	Titanium(III) chloride	960	124	
Cl_4Ge	Germanium(IV) chloride	86.55	27.9	
Cl_4OW	Tungsten(VI) oxytetrachloride	227.55	67.8	
Cl_4Si	Tetrachlorosilane	57.65	28.7	29.7
Cl_4Sn	Tin(IV) chloride	114.15	34.9	
Cl_4Te	Tellurium tetrachloride	387	77	
Cl_4Th	Thorium(IV) chloride	921	146.4	
Cl_4Ti	Titanium(IV) chloride	136.45	36.2	

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
Cl_4V	Vanadium(IV) chloride	148	41.4	42.5
Cl_5Mo	Molybdenum(V) chloride	268	62.8	
Cl_5Nb	Niobium(V) chloride	254.0	52.7	
Cl_5Ta	Tantalum(V) chloride	239.35	54.8	
Cl_6W	Tungsten(VI) chloride	346.75	52.7	
FH_3Si	Fluorosilane	−98.6	18.8	
FLi	Lithium fluoride	1673	147	
FNO	Nitrosyl fluoride	−59.9	19.28	
FNO_2	Nitryl fluoride	−72.4	18.05	
FNS	Thionitrosyl fluoride (NSF)	4.8	22.2	
F_2	Fluorine	−188.12	6.62	
F_2H_2Si	Difluorosilane	−77.8	16.3	
F_2O	Fluorine monoxide	−144.75	11.09	
F_2OS	Thionyl fluoride	−43.8	21.8	
F_2O_2	Fluorine dioxide	−57	19.1	
F_2Pb	Lead(II) fluoride	1293	160.4	
F_2Zn	Zinc fluoride	1500	190.1	
F_3HSi	Trifluorosilane	−95	16.2	
F_3N	Nitrogen trifluoride	−128.75	11.56	
F_3O_2Re	Rhenium(VII) dioxytrifluoride	185.4	65.7	
F_3P	Phosphorus(III) fluoride	−101.5	16.5	
F_3PS	Phosphorus(V) sulfide trifluoride	−52.25	19.6	
F_4MoO	Molybdenum(VI) oxytetrafluoride	186.0	50.6	
F_4N_2	Tetrafluorohydrazine	−74	13.27	
F_4ORe	Rhenium(VI) oxytetrafluoride	171.7	61.0	
F_4OW	Tungsten(VI) oxytetrafluoride	185.9	59.5	
F_4S	Sulfur tetrafluoride	−40.45	26.44	
F_4Se	Selenium tetrafluoride	106	47.2	
F_4Th	Thorium(IV) fluoride	1680	258	
F_5I	Iodine pentafluoride	100.5	41.3	
F_5Mo	Molybdenum(V) fluoride	213.6	51.8	
F_5Nb	Niobium(V) fluoride	229	52.3	
F_5Os	Osmium(V) fluoride	225.9	65.6	
F_5P	Phosphorus(V) fluoride	−84.6	17.2	
F_5Re	Rhenium(V) fluoride	221.3	58.1	
F_5Ta	Tantalum(V) fluoride	229.2	56.9	
F_5V	Vanadium(V) fluoride	48.3	44.52	
F_6Ir	Iridium(VI) fluoride	53.6	30.9	
F_6Mo	Molybdenum(VI) fluoride	34.0	29.0	
F_6Os	Osmium(VI) fluoride	47.5	28.1	
F_6Re	Rhenium(VI) fluoride	33.8	28.7	
F_6S	Sulfur hexafluoride			8.99
F_6W	Tungsten(VI) fluoride	17.1	26.5	
Ga	Gallium	2204	254	
GaI_3	Gallium(III) iodide	340	56.5	
Ge	Germanium	2833	334	
GeH_4	Germane	−88.1	14.06	
Ge_2H_6	Digermane	30.8	25.1	
Ge_3H_8	Trigermane	110.5	32.2	
HI	Hydrogen iodide	−35.55	19.76	17.36
HLiO	Lithium hydroxide	1626	188	
HNO_3	Nitric acid	83		39.1
HN_3	Hydrazoic acid	35.7	30.5	
HNaO	Sodium hydroxide	1388	175	
H_2	Hydrogen	−252.87	0.90	
H_2O	Water	100.0	40.657	43.990
H_2O_2	Hydrogen peroxide	150.2		51.6
H_2S	Hydrogen sulfide	−59.55	18.67	14.08
H_2S_2	Hydrogen disulfide	70.7		33.78
H_2Se	Hydrogen selenide	−41.25	19.7	

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
H_2Te	Hydrogen telluride	−2	19.2	
H_3N	Ammonia	−33.33	23.33	19.86
H_3P	Phosphine	−87.75	14.6	
H_3Sb	Stibine	−17	21.3	
H_4N_2	Hydrazine	113.55	41.8	44.7
H_4P_2	Diphosphine	63.5	28.8	
H_4Si	Silane	−111.9	12.1	
H_4Sn	Stannane	−51.8	19.05	
H_6Si_2	Disilane	−14.3	21.2	
H_8Si_3	Trisilane	52.9	28.5	
He	Helium	−268.93	0.08	
Hg	Mercury	356.73	59.11	
HgI_2	Mercury(II) iodide	354	59.2	
IIn	Indium(I) iodide	712	90.8	
ITl	Thallium(I) iodide	824	104.7	
I_2	Iodine	184.4	41.57	
I_2Pb	Lead(II) iodide	872	104	
I_2Sn	Tin(II) iodide	714	105	
I_3P	Phosphorus(III) iodide	227	43.9	
I_3Sb	Antimony(III) iodide	401	68.6	
I_4Si	Tetraiodosilane	287.35	50.2	
I_4Sn	Tin(IV) iodide	364.35	56.9	
I_4Ti	Titanium(IV) iodide	377	58.4	
Kr	Krypton	−153.22	9.08	
MoO_3	Molybdenum(VI) oxide	1155	138	
NO	Nitric oxide	−151.74	13.83	
N_2	Nitrogen	−195.79	5.57	
N_2O	Nitrous oxide	−88.48	16.53	
N_2O_4	Nitrogen tetroxide	21.15	38.12	
Ne	Neon	−246.08	1.71	
O_2	Oxygen	−182.95	6.82	
O_2S	Sulfur dioxide	−10.05	24.94	22.92
O_3S	Sulfur trioxide	45	40.69	43.14
P	Phosphorus	280.5	12.4	14.2
Pb	Lead	1749	179.5	
S	Sulfur	444.60	45	
STl_2	Thallium(I) sulfide	1367	154	
Se	Selenium	685	95.48	
Te	Tellurium	988	114.1	
Xe	Xenon	−108.11	12.57	
$CClF_3$	Chlorotrifluoromethane	−81.4	15.8	
CCl_2F_2	Dichlorodifluoromethane	−29.8	20.1	
CCl_3F	Trichlorofluoromethane	23.7	25.1	
CCl_4	Tetrachloromethane	76.8	29.82	32.43
$CHBr_3$	Tribromomethane	149.1	39.66	46.05
$CHClF_2$	Chlorodifluoromethane	−40.7	20.2	
$CHCl_2F$	Dichlorofluoromethane	8.9	25.2	
$CHCl_3$	Trichloromethane	61.17	29.24	31.28
CH_2BrCl	Bromochloromethane	68.0	30.0	
CH_2Br_2	Dibromomethane	97	32.92	36.97
CH_2Cl_2	Dichloromethane	40	28.06	28.82
CH_2I_2	Diiodomethane	182	42.5	
CH_2O_2	Formic acid	101	22.69	20.10
CH_3Br	Bromomethane	3.5	23.91	22.81
CH_3Cl	Chloromethane	−24.09	21.40	18.92
CH_3I	Iodomethane	42.55	27.34	27.97
CH_3NO	Formamide	220		60.15
CH_3NO_2	Nitromethane	101.19	33.99	38.27
CH_4	Methane	−161.48	8.19	
CH_4O	Methanol	64.6	35.21	37.43

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
CH_5N	Methylamine	−6.32	25.60	23.37
CH_6N_2	Methylhydrazine	87.5	36.12	40.37
CN_4O_8	Tetranitromethane	126.1	40.74	49.93
CO	Carbon monoxide	−191.5	6.04	
CS_2	Carbon disulfide	46	26.74	27.51
$C_2Br_2ClF_3$	1,2-Dibromo-1-chloro-1,2,2-trifluoroethane	93	31.17	35.04
$C_2Br_2F_4$	1,2-Dibromotetrafluoroethane	47.35	27.03	28.39
C_2ClF_5	Chloropentafluoroethane	−37.95	19.41	
$C_2Cl_2F_4$	1,2-Dichlorotetrafluoroethane	3.8	23.3	
$C_2Cl_3F_3$	1,1,1-Trichlorotrifluoroethane	46.1	26.85	28.08
$C_2Cl_3F_3$	1,1,2-Trichloro-1,2,2-trifluoroethane	47.7	27.04	28.40
C_2Cl_4	Tetrachloroethylene	121.3	34.68	39.68
C_2F_6	Hexafluoroethane	−78.1	16.15	
$C_2HBrClF_3$	2-Bromo-2-chloro-1,1,1-trifluoroethane	50.2	28.08	29.61
C_2HCl_3	Trichloroethylene	87.21	31.40	34.54
C_2HCl_5	Pentachloroethane	159.8	36.9	
$C_2HF_3O_2$	Trifluoroacetic acid	73	33.3	
$C_2H_2Br_4$	1,1,2,2-Tetrabromoethane	243.5	48.7	
$C_2H_2Cl_2$	1,1-Dichloroethylene	31.6	26.14	26.48
$C_2H_2Cl_2$	*cis*-1,2-Dichloroethylene	60.1	30.2	
$C_2H_2Cl_2$	*trans*-1,2-Dichloroethylene	48.7	28.9	
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane	146.5	37.64	45.71
C_2H_3Br	Bromoethylene	15.8	23.4	
C_2H_3Cl	Chloroethylene	−13.3	20.8	
$C_2H_3Cl_2F$	1,1-Dichloro-1-fluoroethane	32.0	26.06	26.48
$C_2H_3Cl_3$	1,1,1-Trichloroethane	74.09	29.86	32.50
$C_2H_3Cl_3$	1,1,2-Trichloroethane	113.8	34.82	40.24
$C_2H_3F_3$	1,1,1-Trifluoroethane	−47.25	18.99	
C_2H_3N	Acetonitrile	81.65	29.75	32.94
C_2H_4	Ethylene	−103.77	13.53	
$C_2H_4Br_2$	1,2-Dibromoethane	131.6	34.77	41.73
$C_2H_4Cl_2$	1,1-Dichloroethane	57.4	28.85	30.62
$C_2H_4Cl_2$	1,2-Dichloroethane	83.5	31.98	35.16
$C_2H_4F_2$	1,1-Difluoroethane	−24.95	21.56	19.08
C_2H_4O	Acetaldehyde	20.1	25.76	25.47
C_2H_4O	Ethylene oxide	10.6	25.54	24.75
$C_2H_4O_2$	Acetic acid	117.9	23.70	23.36
$C_2H_4O_2$	Methyl formate	31.7	27.92	28.35
C_2H_5Br	Bromoethane	38.5	27.04	28.03
C_2H_5Cl	Chloroethane	12.3	24.65	
C_2H_5ClO	2-Chloroethanol	128.6	41.4	
C_2H_5I	Iodoethane	72.5	29.44	31.93
C_2H_5NO	*N*-Methylformamide	199.51		56.19
$C_2H_5NO_2$	Nitroethane	114.0	38.0	
C_2H_6	Ethane	−88.6	14.69	5.16
C_2H_6O	Ethanol	78.29	38.56	42.32
C_2H_6O	Dimethyl ether	−24.8	21.51	18.51
C_2H_6OS	Dimethyl sulfoxide	189	43.1	
$C_2H_6O_2$	Ethylene glycol	197.3	50.5	
C_2H_6S	Ethanethiol	35.1	26.79	27.30
C_2H_6S	Dimethyl sulfide	37.33	27.0	27.65
$C_2H_6S_2$	1,2-Ethanedithiol	146.1	37.93	44.68
$C_2H_6S_2$	Dimethyl disulfide	109.8	33.78	37.86
C_2H_7N	Dimethylamine	6.88	26.40	25.05
C_2H_7NO	Ethanolamine	171	49.83	
$C_2H_8N_2$	1,2-Ethanediamine	117	37.98	44.98
$C_2H_8N_2$	1,1-Dimethylhydrazine	63.9	32.55	35.0
C_2N_2	Cyanogen	−21.1	23.33	19.75
$C_3Cl_2F_6$	1,2-Dichlorohexafluoropropane	34.1	26.28	26.93
$C_3H_3Cl_3O_2$	Methyl trichloroacetate	153.8		48.33

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
C_3H_3N	Acrylonitrile	77.3	32.6	
$C_3H_4Cl_2O_2$	Methyl dichloroacetate	142.9	39.28	47.72
C_3H_4O	Acrolein	52.6	28.3	
$C_3H_4O_2$	2-Oxetanone	162		47.03
C_3H_5Br	3-Bromopropene	70.1	30.24	32.73
C_3H_5Cl	3-Chloropropene	45.1	29.0	
$C_3H_5ClO_2$	Methyl chloroacetate	129.5	39.23	46.73
$C_3H_5Cl_3$	1,2,3-Trichloropropane	157	37.1	
C_3H_5N	Propanenitrile	97.14	31.81	36.03
C_3H_6	Propene	–47.69	18.42	14.24
C_3H_6	Cyclopropane	–32.81	20.05	16.93
$C_3H_6Br_2$	1,2-Dibromopropane	141.9	35.61	41.67
$C_3H_6Br_2$	1,3-Dibromopropane	167.3		47.45
$C_3H_6Cl_2$	1,3-Dichloropropane	120.9	35.18	40.75
C_3H_6O	Allyl alcohol	97.0	40.0	
C_3H_6O	Propanal	48	28.31	29.62
C_3H_6O	Acetone	56.05	29.10	30.99
C_3H_6O	Methyloxirane	35	27.35	27.89
C_3H_6O	Oxetane	47.6	28.67	29.85
$C_3H_6O_2$	Propanoic acid	141.15		32.14
$C_3H_6O_2$	Ethyl formate	54.4	29.91	31.96
$C_3H_6O_2$	Methyl acetate	56.87	30.32	32.29
C_3H_6S	Thietane	95	32.32	35.97
C_3H_7Br	1-Bromopropane	71.1	29.84	32.01
C_3H_7Br	2-Bromopropane	59.5	28.33	30.17
C_3H_7Cl	1-Chloropropane	46.5	27.18	28.35
C_3H_7Cl	2-Chloropropane	35.7	26.30	26.90
C_3H_7I	1-Iodopropane	102.6	32.08	36.25
C_3H_7I	2-Iodopropane	89.5	30.68	34.06
C_3H_7NO	*N*-Ethylformamide	198		58.44
C_3H_7NO	*N,N*-Dimethylformamide	153		46.89
$C_3H_7NO_2$	1-Nitropropane	131.1	38.5	
$C_3H_7NO_2$	2-Nitropropane	120.2	36.8	
C_3H_8	Propane	–42.1	19.04	14.79
C_3H_8O	1-Propanol	97.2	41.44	47.45
C_3H_8O	2-Propanol	82.3	39.85	45.39
$C_3H_8O_2$	1,2-Propylene glycol	187.6	52.4	
$C_3H_8O_2$	1,3-Propylene glycol	214.4	57.9	
$C_3H_8O_2$	Ethylene glycol monomethyl ether	124.1	37.54	45.17
$C_3H_8O_3$	Glycerol	290	61.0	
C_3H_8S	1-Propanethiol	67.8	29.54	31.89
C_3H_8S	2-Propanethiol	52.6	27.91	29.45
C_3H_8S	Ethyl methyl sulfide	66.7	29.53	31.85
$C_3H_8S_2$	1,3-Propanedithiol	172.9		49.66
C_3H_9N	Propylamine	47.22	29.55	31.27
C_3H_9N	Isopropylamine	31.76	27.83	28.36
C_3H_9N	Trimethylamine	2.87	22.94	21.66
$C_3H_{10}N_2$	1,3-Propanediamine	139.8	40.85	50.16
C_4F_8	Perfluorocyclobutane	–5.9	23.2	
C_4F_{10}	Perfluorobutane	–1.9	22.9	
$C_4H_4N_2$	Succinonitrile	266	48.5	
$C_4H_4N_2$	Pyrimidine	123.8	43.09	49.79
$C_4H_4N_2$	Pyridazine	208		53.47
C_4H_4O	Furan	31.5	27.10	27.45
$C_4H_4O_2$	Diketene	126.1	36.80	42.89
C_4H_4S	Thiophene	84.0	31.48	34.70
$C_4H_5Cl_3O_2$	Ethyl trichloroacetate	167.5		50.97
C_4H_5N	2-Methylacrylonitrile	90.3	31.8	
C_4H_5N	Pyrrole	129.79	38.75	45.09
C_4H_5N	Cyclopropanecarbonitrile	135.1	35.55	41.94

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
$C_4H_5NO_2$	Methyl cyanoacetate	200.5	48.2	
C_4H_5NS	4-Methylthiazole	133.3	37.58	43.85
C_4H_6	1,2-Butadiene	10.9	24.02	23.21
C_4H_6	1,3-Butadiene	–4.41	22.47	20.86
C_4H_6	1-Butyne	8.08	24.52	23.35
$C_4H_6Cl_2O_2$	Ethyl dichloroacetate	155		50.60
$C_4H_6O_2$	Vinyl acetate	72.5	34.6	
$C_4H_6O_2$	Methyl acrylate	80.7	33.1	
$C_4H_6O_2$	γ-Butyrolactone	204	52.2	
$C_4H_6O_3$	Acetic anhydride	139.5	38.2	
C_4H_6S	2,3-Dihydrothiophene	112.1	33.24	37.74
C_4H_6S	2,5-Dihydrothiophene	122.4	34.83	39.95
$C_4H_7ClO_2$	Ethyl chloroacetate	144.3	40.43	49.47
C_4H_7N	Butanenitrile	117.6	33.68	39.33
C_4H_7N	2-Methylpropanenitrile	103.9	32.39	37.13
C_4H_8	1-Butene	–6.26	22.07	20.22
C_4H_8	*cis*-2-Butene	3.71	23.34	22.16
C_4H_8	*trans*-2-Butene	0.88	22.72	21.40
C_4H_8	Cyclobutane	12.6	24.19	23.51
$C_4H_8Br_2$	1,4-Dibromobutane	197		53.09
$C_4H_8Cl_2$	1,2-Dichlorobutane	124.1	33.90	39.58
$C_4H_8Cl_2$	1,4-Dichlorobutane	161		46.36
$C_4H_8Cl_2O$	Bis(2-chloroethyl) ether	178.5	45.2	
C_4H_8O	Ethyl vinyl ether	35.5	26.2	
C_4H_8O	1,2-Epoxybutane	63.4	30.3	
C_4H_8O	Butanal	74.8	31.5	
C_4H_8O	2-Butanone	79.59	31.30	34.79
C_4H_8O	Tetrahydrofuran	65	29.81	31.99
$C_4H_8O_2$	Butanoic acid	163.75		40.45
$C_4H_8O_2$	2-Methylpropanoic acid	154.45		35.30
$C_4H_8O_2$	Propyl formate	80.9	33.61	37.53
$C_4H_8O_2$	Ethyl acetate	77.11	31.94	35.60
$C_4H_8O_2$	Methyl propanoate	79.8	32.24	35.85
$C_4H_8O_2$	1,3-Dioxane	106.1	34.37	39.09
$C_4H_8O_2$	1,4-Dioxane	101.5	34.16	38.60
C_4H_8S	Tetrahydrothiophene	121.0	34.66	39.43
C_4H_9Br	1-Bromobutane	101.6	32.51	36.64
C_4H_9Br	2-Bromobutane	91.3	30.77	34.41
C_4H_9Br	1-Bromo-2-methylpropane	91.1	31.33	34.82
C_4H_9Br	2-Bromo-2-methylpropane	73.3	29.23	31.81
C_4H_9Cl	1-Chlorobutane	78.6	30.39	33.51
C_4H_9Cl	2-Chlorobutane	68.2	29.17	31.53
C_4H_9Cl	1-Chloro-2-methylpropane	68.5	29.22	31.67
C_4H_9Cl	2-Chloro-2-methylpropane	50.9	27.55	28.98
C_4H_9I	1-Iodobutane	130.6	34.66	40.63
C_4H_9I	2-Iodobutane	120.1	33.27	38.46
C_4H_9I	1-Iodo-2-methylpropane	121.1	33.54	38.83
C_4H_9I	2-Iodo-2-methylpropane	100.1	31.43	35.41
C_4H_9N	Pyrrolidine	86.56	33.01	37.52
C_4H_9NO	*N*-Ethylacetamide	205		64.89
C_4H_9NO	*N,N*-Dimethylacetamide	165		50.24
C_4H_9NO	Morpholine	128	37.1	
C_4H_{10}	Butane	–0.5	22.44	21.02
C_4H_{10}	Isobutane	–11.73	21.30	19.23
$C_4H_{10}O$	1-Butanol	117.73	43.29	52.35
$C_4H_{10}O$	2-Butanol	99.51	40.75	49.72
$C_4H_{10}O$	2-Methyl-1-propanol	107.89	41.82	50.82
$C_4H_{10}O$	2-Methyl-2-propanol	82.4	39.07	46.69
$C_4H_{10}O$	Diethyl ether	34.5	26.52	27.10
$C_4H_{10}O$	Methyl propyl ether	39.1	26.75	27.60

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
$C_4H_{10}O$	Isopropyl methyl ether	30.77	26.05	26.41
$C_4H_{10}O_2$	1,2-Butanediol	190.5	52.84	71.55
$C_4H_{10}O_2$	1,3-Butanediol	207.5	54.31	74.46
$C_4H_{10}O_2$	Ethylene glycol monoethyl ether	135	39.22	48.21
$C_4H_{10}O_2$	Ethylene glycol dimethyl ether	85	32.42	36.39
$C_4H_{10}O_3$	Diethylene glycol	245.8	52.3	
$C_4H_{10}S$	1-Butanethiol	98.5	32.23	36.63
$C_4H_{10}S$	2-Butanethiol	85	30.59	33.99
$C_4H_{10}S$	2-Methyl-1-propanethiol	88.5	31.01	34.63
$C_4H_{10}S$	2-Methyl-2-propanethiol	64.3	28.45	30.78
$C_4H_{10}S$	Diethyl sulfide	92.1	31.77	35.80
$C_4H_{10}S$	Methyl propyl sulfide	95.6	32.08	36.24
$C_4H_{10}S$	Isopropyl methyl sulfide	84.8	30.71	34.15
$C_4H_{10}S_2$	1,4-Butanedithiol	195.5		55.10
$C_4H_{10}S_2$	Diethyl disulfide	154.1	37.58	45.18
$C_4H_{11}N$	Butylamine	77.00	31.81	35.72
$C_4H_{11}N$	*sec*-Butylamine	62.73	29.92	32.85
$C_4H_{11}N$	*tert*-Butylamine	44.04	28.27	29.64
$C_4H_{11}N$	Isobutylamine	67.75	30.61	33.85
$C_4H_{11}N$	Diethylamine	55.5	29.06	31.31
$C_4H_{11}N$	Isopropylmethylamine	50.4	28.71	30.69
$C_4H_{11}NO$	2-Amino-2-methyl-1-propanol	165.5	50.6	
$C_4H_{11}NO_2$	Diethanolamine	268.8	65.2	
$C_5H_2F_6O_2$	Hexafluoroacetylacetone	54.15	27.05	30.58
$C_5H_4O_2$	Furfural	161.7	43.2	
C_5H_5N	Pyridine	115.23	35.09	40.21
$C_5H_6O_2$	Furfuryl alcohol	171	53.6	
C_5H_6S	2-Methylthiophene	112.6	33.90	38.87
C_5H_6S	3-Methylthiophene	115.5	34.24	39.43
C_5H_7N	*trans*-3-Pentenenitrile	142.6	37.09	44.77
C_5H_7N	Cyclobutanecarbonitrile	149.6	36.88	44.34
C_5H_8	Spiropentane	39	26.76	27.49
C_5H_8O	Cyclopropyl methyl ketone	111.3	34.07	39.41
C_5H_8O	Cyclopentanone	130.57	36.35	42.72
$C_5H_8O_2$	Methyl cyclopropanecarboxylate	114.9	35.25	41.27
$C_5H_8O_2$	Allyl acetate	103.5	36.3	
$C_5H_8O_2$	Ethyl acrylate	99.4	34.7	
$C_5H_8O_2$	Methyl methacrylate	100.5	36.0	
$C_5H_8O_2$	2,4-Pentanedione	138	34.30	41.77
C_5H_9N	Pentanenitrile	141.3	36.09	43.60
C_5H_9N	3-Methylbutanenitrile	127.5	35.10	41.64
C_5H_9N	2,2-Dimethylpropanenitrile	106.1	32.40	37.35
C_5H_{10}	1-Pentene	29.96	25.20	25.47
C_5H_{10}	*cis*-2-Pentene	36.93		26.86
C_5H_{10}	*trans*-2-Pentene	36.34		26.76
C_5H_{10}	2-Methyl-1-butene	31.2	25.50	25.92
C_5H_{10}	3-Methyl-1-butene	20.1		23.77
C_5H_{10}	2-Methyl-2-butene	38.56	26.31	27.06
C_5H_{10}	Cyclopentane	49.3	27.30	28.52
$C_5H_{10}Cl_2$	1,2-Dichloropentane	148.3	36.45	43.89
$C_5H_{10}Cl_2$	1,5-Dichloropentane	179		50.71
$C_5H_{10}O$	Cyclopentanol	140.42		57.05
$C_5H_{10}O$	2-Pentanone	102.26	33.44	38.40
$C_5H_{10}O$	3-Pentanone	101.96	33.45	38.52
$C_5H_{10}O$	3-Methyl-2-butanone	94.33	32.35	36.78
$C_5H_{10}O$	3,3-Dimethyloxetane	80.6	30.85	33.94
$C_5H_{10}O$	Tetrahydropyran	88	31.17	34.58
$C_5H_{10}O_2$	Pentanoic acid	186.1	44.1	
$C_5H_{10}O_2$	2-Methylbutanoic acid	177		46.91
$C_5H_{10}O_2$	Butyl formate	106.1	36.58	41.11

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
$C_5H_{10}O_2$	Isobutyl formate	98.2	33.6	
$C_5H_{10}O_2$	Propyl acetate	101.54	33.92	39.72
$C_5H_{10}O_2$	Isopropyl acetate	88.6	32.93	37.20
$C_5H_{10}O_2$	Ethyl propanoate	99.1	33.88	39.21
$C_5H_{10}O_2$	Methyl butanoate	102.8	33.79	39.28
$C_5H_{10}O_2$	Methyl isobutanoate	92.5	32.61	37.32
$C_5H_{10}O_2$	Tetrahydrofurfuryl alcohol	178	45.2	
$C_5H_{10}O_3$	Diethyl carbonate	126		43.60
$C_5H_{10}O_3$	Ethylene glycol monomethyl ether acetate	143	43.9	
$C_5H_{10}S$	Thiacyclohexane	141.8	35.96	42.58
$C_5H_{10}S$	Cyclopentanethiol	132.1	35.32	41.42
$C_5H_{11}Br$	1-Bromopentane	129.8	35.01	41.28
$C_5H_{11}Cl$	1-Chloropentane	107.8	33.15	38.24
$C_5H_{11}Cl$	2-Chloropentane	97.0	31.79	36.03
$C_5H_{11}Cl$	1-Chloro-3-methylbutane	98.9	32.02	36.24
$C_5H_{11}I$	1-Iodopentane	155		45.27
$C_5H_{11}N$	Piperidine	106.22		39.29
C_5H_{12}	Pentane	36.06	25.79	26.43
C_5H_{12}	Isopentane	27.88	24.69	24.85
C_5H_{12}	Neopentane	9.48	22.74	21.84
$C_5H_{12}O$	1-Pentanol	137.98	44.36	57.02
$C_5H_{12}O$	2-Pentanol	119.3	41.40	54.21
$C_5H_{12}O$	3-Pentanol	116.25		54.0
$C_5H_{12}O$	2-Methyl-1-butanol	128		55.16
$C_5H_{12}O$	3-Methyl-1-butanol	131.1	44.07	55.61
$C_5H_{12}O$	2-Methyl-2-butanol	102.4	39.04	50.10
$C_5H_{12}O$	3-Methyl-2-butanol	112.9		53.0
$C_5H_{12}O$	Butyl methyl ether	70.16	29.55	32.37
$C_5H_{12}O$	*sec*-Butyl methyl ether	59.1	28.09	30.23
$C_5H_{12}O$	Methyl *tert*-butyl ether	55.2	27.94	29.82
$C_5H_{12}O$	Isobutyl methyl ether	58.6	28.02	30.13
$C_5H_{12}O$	Ethyl propyl ether	63.21	28.94	31.43
$C_5H_{12}O$	Ethyl isopropyl ether	54.1	28.21	30.08
$C_5H_{12}O_2$	1-Ethoxy-2-methoxyethane	102.1	34.33	39.83
$C_5H_{12}O_2$	1,5-Pentanediol	239	60.7	
$C_5H_{12}O_2$	Ethylene glycol monopropyl ether	149.8	41.40	52.12
$C_5H_{12}O_2$	Diethoxymethane	88	31.33	35.65
$C_5H_{12}O_3$	Diethylene glycol monomethyl ether	193	46.6	
$C_5H_{12}S$	1-Pentanethiol	126.6	34.88	41.24
$C_5H_{12}S$	2-Methyl-1-butanethiol	119.1	33.79	39.45
$C_5H_{12}S$	2-Methyl-2-butanethiol	99.1	31.37	35.67
$C_5H_{12}S$	Butyl methyl sulfide	123.5	34.47	40.46
$C_5H_{12}S$	*tert*-Butyl methyl sulfide	99	31.47	35.84
$C_5H_{12}S$	Ethyl propyl sulfide	118.6	34.24	39.97
$C_5H_{12}S$	Ethyl isopropyl sulfide	107.5	32.74	37.78
$C_5H_{13}N$	Pentylamine	104.3	34.01	40.08
$C_5H_{13}N$	Ethylisopropylamine	69.6	29.94	33.13
C_6ClF_5	Chloropentafluorobenzene	117.96	34.76	41.07
C_6F_6	Hexafluorobenzene	80.26	31.66	35.71
C_6HF_5	Pentafluorobenzene	85.74	32.15	36.27
$C_6H_4Cl_2$	*o*-Dichlorobenzene	180	39.66	50.21
$C_6H_4Cl_2$	*m*-Dichlorobenzene	173	38.62	48.58
$C_6H_4Cl_2$	*p*-Dichlorobenzene	174	38.79	49.0
$C_6H_4F_2$	*o*-Difluorobenzene	94	32.21	36.18
$C_6H_4F_2$	*m*-Difluorobenzene	82.6	31.10	34.59
$C_6H_4F_2$	*p*-Difluorobenzene	89	31.77	35.54
C_6H_5Br	Bromobenzene	156.06		44.54
C_6H_5Cl	Chlorobenzene	131.72	35.19	40.97
C_6H_5F	Fluorobenzene	84.73	31.19	34.58
C_6H_5I	Iodobenzene	188.4	39.5	

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H$(25°C) kJ/mol
$C_6H_5NO_2$	Nitrobenzene	210.8		55.01
C_6H_6	Benzene	80.09	30.72	33.83
C_6H_6ClN	*o*-Chloroaniline	208.8	44.4	
C_6H_6O	Phenol	181.87	45.69	57.82
C_6H_6S	Benzenethiol	169.1	39.93	47.56
C_6H_7N	Aniline	184.17	42.44	55.83
C_6H_7N	2-Methylpyridine	129.38	36.17	42.48
C_6H_7N	3-Methylpyridine	144.14	37.35	44.44
C_6H_7N	4-Methylpyridine	145.36	37.51	44.56
C_6H_7N	1-Cyclopentenecarbonitrile			44.98
C_6H_9N	Cyclopentanecarbonitrile			43.43
$C_6H_9NO_3$	Triacetamide			60.41
C_6H_{10}	Cyclohexene	82.98	30.46	33.47
$C_6H_{10}O$	Cyclohexanone	155.43		45.06
$C_6H_{10}O$	Mesityl oxide	130	36.1	
$C_6H_{10}O_2$	Methyl cyclobutanecarboxylate	135.5	37.13	44.72
$C_6H_{10}O_3$	Propanoic anhydride	170	41.7	
$C_6H_{10}O_4$	Diethyl oxalate	185.7	42.0	
$C_6H_{10}O_4$	Ethylene glycol diacetate	190		61.44
$C_6H_{11}N$	Hexanenitrile	163.65		47.91
C_6H_{12}	1-Hexene	63.48		30.61
C_6H_{12}	*cis*-2-Hexene	68.8		32.19
C_6H_{12}	*trans*-2-Hexene	67.9		31.60
C_6H_{12}	*cis*-3-Hexene	66.4		31.23
C_6H_{12}	*trans*-3-Hexene	67.1		31.55
C_6H_{12}	2-Methyl-1-pentene	62.1		30.48
C_6H_{12}	3-Methyl-1-pentene	54.2		28.62
C_6H_{12}	4-Methyl-1-pentene	53.9		28.71
C_6H_{12}	2-Methyl-2-pentene	67.3		31.60
C_6H_{12}	3-Methyl-*cis*-2-pentene	67.7		32.09
C_6H_{12}	3-Methyl-*trans*-2-pentene	70.4		31.35
C_6H_{12}	4-Methyl-*cis*-2-pentene	56.3		29.48
C_6H_{12}	4-Methyl-*trans*-2-pentene	58.6		29.97
C_6H_{12}	2-Ethyl-1-butene	64.7		31.13
C_6H_{12}	2,3-Dimethyl-1-butene	55.6		29.18
C_6H_{12}	3,3-Dimethyl-1-butene	41.2		26.61
C_6H_{12}	2,3-Dimethyl-2-butene	73.3	29.64	32.51
C_6H_{12}	Cyclohexane	80.73	29.97	33.01
C_6H_{12}	Methylcyclopentane	71.8	29.08	31.64
C_6H_{12}	Ethylcyclobutane	70.8	28.67	31.24
$C_6H_{12}Cl_2$	1,2-Dichlorohexane	173		48.16
$C_6H_{12}O$	Butyl vinyl ether	94	31.58	36.17
$C_6H_{12}O$	2-Hexanone	127.6	36.35	43.14
$C_6H_{12}O$	3-Hexanone	123.5	35.36	42.47
$C_6H_{12}O$	3-Methyl-2-pentanone	117.5	34.16	40.53
$C_6H_{12}O$	4-Methyl-2-pentanone	116.5	34.49	40.61
$C_6H_{12}O$	2-Methyl-3-pentanone	113.5	33.84	39.79
$C_6H_{12}O$	3,3-Dimethyl-2-butanone	106.1	33.39	37.91
$C_6H_{12}O$	Cyclohexanol	160.84		62.01
$C_6H_{12}O_2$	Butyl acetate	126.1	36.28	43.86
$C_6H_{12}O_2$	*tert*-Butyl acetate	95.1	33.07	38.03
$C_6H_{12}O_2$	Isobutyl acetate	116.5	35.9	
$C_6H_{12}O_2$	Propyl propanoate	122.5	35.54	43.45
$C_6H_{12}O_2$	Ethyl butanoate	121.5	35.47	42.68
$C_6H_{12}O_2$	Ethyl 2-methylpropanoate	110.1	33.67	39.83
$C_6H_{12}O_2$	Methyl pentanoate	127.4	35.36	43.10
$C_6H_{12}O_2$	Methyl 2,2-dimethylpropanoate	101.1	33.42	38.76
$C_6H_{12}O_3$	Ethylene glycol monoethyl ether acetate	156.4	40.76	52.61
$C_6H_{12}S$	Cyclohexanethiol	158.9	37.06	44.57
$C_6H_{13}Br$	1-Bromohexane	155.3		45.89

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
$C_6H_{13}Cl$	1-Chlorohexane	135	35.67	42.83
$C_6H_{13}I$	1-Iodohexane	181		49.75
$C_6H_{13}N$	Cyclohexylamine	134	36.14	43.67
C_6H_{14}	Hexane	68.73	28.85	31.56
C_6H_{14}	2-Methylpentane	60.26	27.79	29.89
C_6H_{14}	3-Methylpentane	63.27	28.06	30.28
C_6H_{14}	2,2-Dimethylbutane	49.73	26.31	27.68
C_6H_{14}	2,3-Dimethylbutane	57.93	27.38	29.12
$C_6H_{14}N_2$	Azopropane	114		39.88
$C_6H_{14}O$	1-Hexanol	157.6	44.50	61.61
$C_6H_{14}O$	2-Hexanol	140	41.01	58.46
$C_6H_{14}O$	2-Methyl-1-pentanol	149	50.2	
$C_6H_{14}O$	4-Methyl-1-pentanol	151.9	44.46	60.47
$C_6H_{14}O$	2-Methyl-2-pentanol	121.1	39.59	54.77
$C_6H_{14}O$	4-Methyl-2-pentanol	131.6	44.2	
$C_6H_{14}O$	2-Ethyl-1-butanol	147	43.2	
$C_6H_{14}O$	Dipropyl ether	90.08	31.31	35.69
$C_6H_{14}O$	Diisopropyl ether	68.51	29.10	32.12
$C_6H_{14}O$	Butyl ethyl ether	92.3	31.63	36.32
$C_6H_{14}O$	Methyl pentyl ether	99	32.02	36.85
$C_6H_{14}O_2$	2-Methyl-2,4-pentanediol	197.1	57.3	
$C_6H_{14}O_2$	Ethylene glycol monobutyl ether	168.4		56.59
$C_6H_{14}O_2$	1,1-Diethoxyethane	102.25	36.28	43.20
$C_6H_{14}O_2$	Ethylene glycol diethyl ether	119.4	36.28	43.20
$C_6H_{14}O_3$	Bis(ethoxymethyl) ether	140.6	36.17	44.69
$C_6H_{14}O_3$	Diethylene glycol monoethyl ether	196	47.5	
$C_6H_{14}O_3$	Diethylene glycol dimethyl ether	162	36.17	44.69
$C_6H_{14}O_4$	Triethylene glycol	285	71.4	
$C_6H_{14}S$	Dipropyl sulfide	142.9	36.60	44.21
$C_6H_{14}S$	Diisopropyl sulfide	120.1	33.80	39.60
$C_6H_{14}S$	Isopropyl propyl sulfide	132.1	35.11	41.78
$C_6H_{14}S$	Butyl ethyl sulfide	144.3	37.01	44.51
$C_6H_{14}S$	Methyl pentyl sulfide	145.1	37.41	45.24
$C_6H_{15}N$	Hexylamine	132.8	36.54	45.10
$C_6H_{15}N$	Butylethylamine	107.5	33.97	40.15
$C_6H_{15}N$	Dipropylamine	109.3	33.47	40.04
$C_6H_{15}N$	Diisopropylamine	83.9	30.40	34.61
$C_6H_{15}N$	Isopropylpropylamine	96.9	32.14	37.23
$C_6H_{15}N$	Triethylamine	89	31.01	34.84
C_6MoO_6	Molybdenum hexacarbonyl	701	72.51	
$C_7H_3F_5$	2,3,4,5,6-Pentafluorotoluene	117.5	34.75	41.12
$C_7H_5F_3$	(Trifluoromethyl)benzene	102.1	32.63	37.60
C_7H_5N	Benzonitrile	191.1	45.9	
C_7H_6O	Benzaldehyde	179.0	42.5	
$C_7H_6O_2$	Salicylaldehyde	197	38.2	
C_7H_7Cl	*o*-Chlorotoluene	159.0	37.5	
C_7H_7Cl	*p*-Chlorotoluene	162.4	38.7	
C_7H_7F	*o*-Fluorotoluene	115	35.4	
C_7H_7F	*p*-Fluorotoluene	116.6	34.08	39.42
C_7H_8	Toluene	110.63	33.18	38.01
C_7H_8O	*o*-Cresol	191.04	45.19	
C_7H_8O	*m*-Cresol	202.27	47.40	61.71
C_7H_8O	*p*-Cresol	201.98	47.45	
C_7H_8O	Benzyl alcohol	205.31	50.48	
C_7H_8O	Anisole	153.7	38.97	46.90
C_7H_9N	Benzylamine	185		60.16
C_7H_9N	*o*-Methylaniline	200.3	44.6	
C_7H_9N	*m*-Methylaniline	203.3	44.9	
C_7H_9N	*p*-Methylaniline	200.4	44.3	
C_7H_9N	1-Cyclohexenecarbonitrile			53.55

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H$(25°C) kJ/mol
C_7H_9N	2,3-Dimethylpyridine	161.12	39.08	47.82
C_7H_9N	2,4-Dimethylpyridine	158.38	38.53	47.49
C_7H_9N	2,5-Dimethylpyridine	156.98	38.68	47.04
C_7H_9N	2,6-Dimethylpyridine	144.01	37.46	45.34
C_7H_9N	3,4-Dimethylpyridine	179.10	39.99	50.50
C_7H_9N	3,5-Dimethylpyridine	171.84	39.46	49.33
$C_7H_{10}O$	Dicyclopropyl ketone	161		53.70
$C_7H_{11}N$	Cyclohexanecarbonitrile			51.92
C_7H_{12}	1-Methylbicyclo(3,1,0)hexane	93.1	31.07	34.77
$C_7H_{12}O_4$	Diethyl malonate	200	54.8	
C_7H_{14}	1-Heptene	93.64		35.49
C_7H_{14}	*cis*-2-Heptene	98.4		36.26
C_7H_{14}	*trans*-2-Heptene	98		36.27
C_7H_{14}	*cis*-3-Heptene	95.8		35.81
C_7H_{14}	*trans*-3-Heptene	95.7		35.84
C_7H_{14}	*cis*-3-Methyl-3-hexene	95.4		36.31
C_7H_{14}	*trans*-3-Methyl-3-hexene	93.5		35.70
C_7H_{14}	2,4-Dimethyl-1-pentene	81.6		33.03
C_7H_{14}	4,4-Dimethyl-1-pentene	72.5		31.13
C_7H_{14}	2,4-Dimethyl-2-pentene	83.4		34.19
C_7H_{14}	*cis*-4,4-Dimethyl-2-pentene	80.4		32.56
C_7H_{14}	*trans*-4,4-Dimethyl-2-pentene	76.7		32.81
C_7H_{14}	2-Ethyl-3-methyl-1-butene	89		34.35
C_7H_{14}	2,3,3-Trimethyl-1-butene	77.9		32.09
C_7H_{14}	Methylcyclohexane	100.93	31.27	35.36
C_7H_{14}	Ethylcyclopentane	103.5	31.96	36.40
C_7H_{14}	*cis*-1,3-Dimethylcyclopentane	90.8	30.40	34.20
$C_7H_{14}O$	2-Heptanone	151.05		47.24
$C_7H_{14}O$	2,2-Dimethyl-3-pentanone	125.6	36.09	42.34
$C_7H_{14}O$	2,4-Dimethyl-3-pentanone	125.4	34.64	41.51
$C_7H_{14}O$	1-Methylcyclohexanol	155	79.0	
$C_7H_{14}O$	*cis*-2-Methylcyclohexanol	165	48.5	
$C_7H_{14}O$	*trans*-2-Methylcyclohexanol	167.5	53.0	
$C_7H_{14}O_2$	Pentyl acetate	149.2	38.42	48.56
$C_7H_{14}O_2$	Isopentyl acetate	142.5	37.5	
$C_7H_{14}O_2$	Ethyl pentanoate	146.1	36.96	47.01
$C_7H_{14}O_2$	Ethyl 3-methylbutanoate	135.0	37.0	
$C_7H_{14}O_2$	Ethyl 2,2-dimethylpropanoate	118.4	34.51	41.25
$C_7H_{14}O_2$	Methyl hexanoate	149.5	38.55	48.04
$C_7H_{15}Br$	1-Bromoheptane	179		50.60
$C_7H_{15}Cl$	1-Chloroheptane	159		47.66
C_7H_{16}	Heptane	98.5	31.77	36.57
C_7H_{16}	2-Methylhexane	90.04	30.62	34.87
C_7H_{16}	3-Methylhexane	92	30.9	
C_7H_{16}	3-Ethylpentane	93.5	31.12	35.22
C_7H_{16}	2,2-Dimethylpentane	79.2	29.23	32.42
C_7H_{16}	2,3-Dimethylpentane	89.78	30.46	34.26
C_7H_{16}	2,4-Dimethylpentane	80.49	29.55	32.88
C_7H_{16}	3,3-Dimethylpentane	86.06	29.62	33.03
C_7H_{16}	2,2,3-Trimethylbutane	80.86	28.90	32.05
$C_7H_{16}O$	Hexyl methyl ether	126.1	34.93	42.07
$C_7H_{16}O$	1-Heptanol	176.45		66.81
$C_7H_{16}O$	3-Heptanol	157	42.5	
$C_7H_{16}O$	Butyl propyl ether	118.1	33.72	40.22
$C_7H_{16}O$	Ethyl pentyl ether	117.6	34.41	41.01
$C_7H_{17}N$	Heptylamine	156		49.96
C_8F_{18}	Perfluorooctane	105.9	33.38	41.13
C_8H_8	Styrene	145	38.7	
C_8H_8O	Acetophenone	202	43.98	55.40
$C_8H_8O_2$	Methyl benzoate	199		55.57

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
$C_8H_8O_3$	Methyl salicylate	222.9	46.7	
C_8H_{10}	Ethylbenzene	136.19	35.57	42.24
C_8H_{10}	*o*-Xylene	144.5	36.24	43.43
C_8H_{10}	*m*-Xylene	139.12	35.66	42.65
C_8H_{10}	*p*-Xylene	138.37	35.67	42.40
$C_8H_{10}O$	2,4-Xylenol	210.98		64.96
$C_8H_{10}O$	2,5-Xylenol	211.1	46.9	
$C_8H_{10}O$	2,6-Xylenol	201.07		75.31
$C_8H_{10}O$	3,4-Xylenol	227		85.03
$C_8H_{10}O$	3,5-Xylenol	221.74		82.01
$C_8H_{10}O$	Phenetole	169.81		51.04
$C_8H_{11}N$	*N*-Ethylaniline	203.0		58.3
$C_8H_{11}N$	*N,N*-Dimethylaniline	194.15		52.83
$C_8H_{11}N$	2,4-Dimethylaniline	214		61.3
$C_8H_{11}N$	2,5-Dimethylaniline	214		61.7
$C_8H_{11}N$	2,3,6-Trimethylpyridine	171.6	39.95	50.61
$C_8H_{11}N$	2,4,6-Trimethylpyridine	170.6	39.87	50.33
C_8H_{14}	1-Octyne	126.3	35.83	42.30
C_8H_{14}	2-Octyne	137.6	37.26	44.49
C_8H_{14}	3-Octyne	133.1	36.94	43.92
C_8H_{14}	4-Octyne	131.6	36.0	42.73
$C_8H_{14}O_3$	Butanoic anhydride	200	50.0	
$C_8H_{15}N$	Octanenitrile	205.25		56.80
C_8H_{16}	1-Octene	121.29	34.07	40.34
C_8H_{16}	*cis*-2,2-Dimethyl-3-hexene	105.5		36.86
C_8H_{16}	*trans*-2,2-Dimethyl-3-hexene	100.8		37.03
C_8H_{16}	3-Ethyl-2-methyl-1-pentene	109.5		37.27
C_8H_{16}	2,4,4-Trimethyl-1-pentene	101.4		35.59
C_8H_{16}	2,4,4-Trimethyl-2-pentene	104.9		37.23
C_8H_{16}	Ethylcyclohexane	131.9	34.04	40.56
C_8H_{16}	1,1-Dimethylcyclohexane	119.6	32.51	37.92
C_8H_{16}	*cis*-1,2-Dimethylcyclohexane	129.8	33.47	39.70
C_8H_{16}	*trans*-1,2-Dimethylcyclohexane	123.5	32.96	38.36
C_8H_{16}	*cis*-1,3-Dimethylcyclohexane	120.1	32.91	38.26
C_8H_{16}	*trans*-1,3-Dimethylcyclohexane	124.5	33.39	39.16
C_8H_{16}	*cis*-1,4-Dimethylcyclohexane	124.4	33.28	39.02
C_8H_{16}	*trans*-1,4-Dimethylcyclohexane	119.4	32.56	37.90
C_8H_{16}	Propylcyclopentane	131	34.70	41.08
C_8H_{16}	Isopropylcyclopentane	126.5	33.56	39.44
C_8H_{16}	1-Ethyl-1-methylcyclopentane	121.6	33.20	38.85
$C_8H_{16}O$	2,2,4-Trimethyl-3-pentanone	135.1	35.64	43.30
$C_8H_{16}O_2$	Octanoic acid	239	58.5	
$C_8H_{16}O_2$	2-Ethylhexanoic acid	228		75.60
$C_8H_{16}O_2$	Isobutyl isobutanoate	148.6	38.2	
$C_8H_{16}O_2$	Ethyl hexanoate	167		51.72
$C_8H_{16}O_2$	Methyl heptanoate	174		51.62
$C_8H_{17}Br$	1-Bromooctane	200		55.77
$C_8H_{17}Cl$	1-Chlorooctane	181.5		52.42
$C_8H_{17}F$	1-Fluorooctane	142.4	40.43	49.65
C_8H_{18}	Octane	125.67	34.41	41.49
C_8H_{18}	2-Methylheptane	117.66	33.26	39.67
C_8H_{18}	3-Methylheptane	118.9	33.66	39.83
C_8H_{18}	4-Methylheptane	117.72	33.35	39.69
C_8H_{18}	3-Ethylhexane	118.6	33.59	39.64
C_8H_{18}	2,2-Dimethylhexane	106.86	32.07	37.28
C_8H_{18}	2,3-Dimethylhexane	115.62	33.17	38.78
C_8H_{18}	2,4-Dimethylhexane	109.5	32.51	37.76
C_8H_{18}	2,5-Dimethylhexane	109.12	32.54	37.85
C_8H_{18}	3,3-Dimethylhexane	111.97	32.31	37.53
C_8H_{18}	3,4-Dimethylhexane	117.73	33.24	38.97

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
C_8H_{18}	3-Ethyl-2-methylpentane	115.66	32.93	38.52
C_8H_{18}	3-Ethyl-3-methylpentane	118.27	32.78	37.99
C_8H_{18}	2,2,3-Trimethylpentane	110	31.94	36.91
C_8H_{18}	2,2,4-Trimethylpentane	99.22	30.79	35.14
C_8H_{18}	2,3,3-Trimethylpentane	114.8	32.12	37.27
C_8H_{18}	2,3,4-Trimethylpentane	113.5	32.36	37.75
C_8H_{18}	2,2,3,3-Tetramethylbutane	106.45		42.90
$C_8H_{18}N_2$	Azobutane			49.31
$C_8H_{18}O$	1-Octanol	195.16		70.98
$C_8H_{18}O$	2-Octanol	180	44.4	
$C_8H_{18}O$	2-Ethyl-1-hexanol	184.6	54.2	
$C_8H_{18}O$	Dibutyl ether	140.28	36.49	44.97
$C_8H_{18}O$	Di-*sec*-butyl ether	121.1	34.06	40.84
$C_8H_{18}O$	Di-*tert*-butyl ether	107.23	32.15	37.61
$C_8H_{18}O_2$	1,2-Dipropoxyethane			50.62
$C_8H_{18}O_3$	Diethylene glycol diethyl ether	188		58.40
$C_8H_{18}S$	Dibutyl sulfide	185		52.96
$C_8H_{18}S$	Di-*tert*-butyl sulfide	149.1	33.26	43.76
$C_8H_{18}S$	Diisobutyl sulfide	171		48.71
$C_8H_{19}N$	Dibutylamine	159.6	38.44	49.45
$C_8H_{19}N$	2-Ethylhexylamine	169.2	40.0	
C_9H_7N	Quinoline	237.16	49.7	59.30
C_9H_7N	Isoquinoline	243.22	49.0	60.26
C_9H_{10}	Cyclopropylbenzene	173.6		50.22
C_9H_{10}	Indan	177.97	39.63	48.79
$C_9H_{10}O_2$	Benzyl acetate	213	49.4	
C_9H_{12}	Propylbenzene	159.24		46.22
C_9H_{12}	Isopropylbenzene	152.41		45.13
C_9H_{12}	1,2,3-Trimethylbenzene	176.12		49.05
C_9H_{12}	1,2,4-Trimethylbenzene	169.38		47.93
C_9H_{12}	1,3,5-Trimethylbenzene	164.74		47.50
$C_9H_{14}O_6$	Triacetin	259		85.74
C_9H_{18}	Butylcyclopentane	156.6	36.16	45.89
C_9H_{18}	Propylcyclohexane	156.7		45.08
C_9H_{18}	Isopropylcyclohexane	154.8		44.02
$C_9H_{18}O$	2-Nonanone	195.3		56.44
$C_9H_{18}O$	5-Nonanone	188.45		53.30
$C_9H_{18}O$	2,6-Dimethyl-4-heptanone	169.4		50.92
$C_9H_{18}O_2$	Methyl octanoate	192.9		56.41
C_9H_{20}	Nonane	150.82	37.18	46.55
C_9H_{20}	2,2,5-Trimethylhexane	124.09	33.65	40.16
C_9H_{20}	2,3,5-Trimethylhexane	131.4	34.43	41.41
C_9H_{20}	3,3-Diethylpentane	146.3	34.61	42.0
C_9H_{20}	2,2,4,4-Tetramethylpentane	122.29	32.51	38.49
$C_9H_{20}O$	1-Nonanol	213.37		76.86
$C_{10}H_7Br$	1-Bromonaphthalene	281	39.3	
$C_{10}H_7Cl$	1-Chloronaphthalene	259	52.1	
$C_{10}H_8$	Naphthalene	217.9	43.2	
$C_{10}H_9N$	2-Methylquinoline	246.5		66.1
$C_{10}H_9N$	4-Methylquinoline	262		67.6
$C_{10}H_9N$	6-Methylquinoline	258.6		67.7
$C_{10}H_9N$	8-Methylquinoline	247.5		65.7
$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene	207.6	43.9	
$C_{10}H_{14}$	Butylbenzene	183.31	38.87	51.36
$C_{10}H_{14}$	*sec*-Butylbenzene	173.3		47.98
$C_{10}H_{14}$	*tert*-Butylbenzene	169.1		47.71
$C_{10}H_{14}$	Isobutylbenzene	172.79		47.86
$C_{10}H_{14}$	1-Isopropyl-4-methylbenzene	177.1	38.2	
$C_{10}H_{16}O$	(+)-Camphor	207.4	59.5	
$C_{10}H_{18}$	*cis*-Decahydronaphthalene	195.8	41.0	

Mol. form.	Name	t_b/°C	$\Delta_{vap}H(t_b)$ kJ/mol	$\Delta_{vap}H(25°C)$ kJ/mol
$C_{10}H_{18}$	*trans*-Decahydronaphthalene	187.3	40.2	
$C_{10}H_{19}N$	Decanenitrile	243		66.84
$C_{10}H_{20}$	1-Decene	170.5		50.43
$C_{10}H_{20}$	Butylcyclohexane	180.9		49.36
$C_{10}H_{20}O_2$	2-Ethylhexyl acetate	199	43.5	
$C_{10}H_{20}O_2$	Isopentyl isopentanoate	190.4	45.9	
$C_{10}H_{22}$	Decane	174.15	39.58	51.42
$C_{10}H_{22}$	2-Methylnonane	167.1	38.23	49.63
$C_{10}H_{22}$	3-Methylnonane	167.9	38.26	49.71
$C_{10}H_{22}$	5-Methylnonane	165.1	38.14	49.34
$C_{10}H_{22}$	2,4-Dimethyloctane	156	36.47	47.13
$C_{10}H_{22}O$	1-Decanol	231.1		81.50
$C_{10}H_{22}O$	Diisopentyl ether	172.5	35.1	
$C_{10}H_{22}S$	1-Decanethiol	240.6		65.48
$C_{11}H_{10}$	1-Methylnaphthalene	244.7	45.5	
$C_{11}H_{21}N$	Undecanenitrile	253		71.14
$C_{11}H_{22}$	Pentylcyclohexane	203.7		53.88
$C_{11}H_{24}$	Undecane	195.9	41.91	56.58
$C_{11}H_{24}$	2-Methyldecane	189.3	40.25	54.28
$C_{11}H_{24}$	4-Methyldecane	187	40.70	53.76
$C_{11}H_{24}$	2,4,7-Trimethyloctane	168.1	38.22	49.91
$C_{12}F_{27}N$	Tris(perfluorobutyl)amine	178	46.4	
$C_{12}H_{10}O$	Diphenyl ether	258.0	48.2	
$C_{12}H_{16}$	Cyclohexylbenzene	240.1		59.94
$C_{12}H_{22}$	Cyclohexylcyclohexane	238		57.98
$C_{12}H_{23}N$	Dodecanenitrile	277		76.12
$C_{12}H_{24}$	1-Dodecene	213.8		60.78
$C_{12}H_{26}$	2,2,4,6,6-Pentamethylheptane	177.8		48.97
$C_{12}H_{26}$	Dodecane	216.32	44.09	61.52
$C_{12}H_{26}O$	1-Dodecanol	259		91.96
$C_{12}H_{27}BO_3$	Tributyl borate	234	56.1	
$C_{12}H_{27}N$	Tributylamine	216.5	46.9	
$C_{13}H_{13}N$	*N*-Benzylaniline	306.5		79.6
$C_{13}H_{26}O_2$	Methyl dodecanoate	267		77.17
$C_{13}H_{28}$	Tridecane	235.47	46.20	66.68
$C_{14}H_{10}$	Phenanthrene	340		75.50
$C_{14}H_{12}O_2$	Benzyl benzoate	323.5	53.6	
$C_{14}H_{27}N$	Tetradecanenitrile			85.29
$C_{14}H_{30}$	Tetradecane	253.58	48.16	71.73
$C_{14}H_{30}O$	1-Tetradecanol	289		102.20
$C_{15}H_{32}$	Pentadecane	270.6	50.08	76.77
$C_{16}H_{22}O_4$	Dibutyl phthalate	340	79.2	
$C_{16}H_{32}$	1-Hexadecene	284.9		80.25
$C_{16}H_{34}$	Hexadecane	286.86	51.84	81.35
$C_{17}H_{36}$	Heptadecane	302.0	53.58	86.47
$C_{18}H_{34}O_2$	Oleic acid	360	67.4	
$C_{18}H_{38}$	Octadecane	316.3	55.23	91.44
$C_{19}H_{40}$	Nonadecane	329.9	56.93	96.4
$C_{20}H_{42}$	Eicosane	343	58.49	101.81

ENTHALPY OF FUSION

This table lists the molar enthalpy (heat) of fusion, $\Delta_{fus}H$, of over 800 inorganic and organic compounds. All values refer to the enthalpy change at equilibrium between the liquid phase and the most stable solid phase at the transition temperature. Most values of $\Delta_{fus}H$ are given at the normal melting point t_m. However, a "t" following the entry in the melting point column indicate a triple–point temperature, where the solid, liquid, and gas phases are in equilibrium. Substances are listed by molecular formula in the Hill order, with substances containing carbon (except graphite) following those that do not contain carbon.

All temperatures are given on the ITS–90 scale.

An * following an entry indicates that the value includes the enthalpy of transition between crystalline phases whose transformation occurs within 1˚C of the melting point.

References

1. Chase, M. W., Davies, C. A., Downey, J. R., Frurip, D. J., McDonald, R. A., and Syverud, A. N., *JANAF Thermochemical Tables, Third Edition, J. Phys. Chem. Ref. Data,* 14, Suppl. 1, 1985.
2. Gurvich, L. V., Veyts, I. V., and Alcock, C. B., *Thermodynamic Properties of Individual Substances, Fourth Edition*; Vol. 2, Hemisphere Publishing Corp., New York, 1991; Vol. 3, CRC Press, Boca Raton, FL, 1994.
3. Dinsdale, A. T., *CALPHAD*, 15, 317, 1991
4. *Landolt–Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series*, IV/8A, *Enthalpies of Fusion and Transition of Organic Compounds*, Springer–Verlag, Heidelberg, 1995.
5. *Landolt–Börnstein, Numerical Values and Functions for Physics, Chemistry, Astronomy, Geophysics, and Technology, Sixth Edition,* Vol. 2, Part 4, Springer–Verlag, Heidelberg, 1961.
6. Janz, G. J., et al., *Physical Properties Data Compilations Relevant to Energy Storage. II. Molten Salts,* Nat. Stand. Ref. Data Sys.– Nat. Bur. Standards (U.S.), No. 61, Part 2, 1979.
7. *TRC Thermodynamic Tables,* Thermodynamic Research Center, Texas A&M University, College Station, TX.

Molecular formula	Name	t_m/˚C	$\Delta_{fus}H$/ kJ mol^{-1}
Ag	Silver	961.78	11.28
AgBr	Silver(I) bromide	432	9.12
AgCl	Silver(I) chloride	455	13.2
AgI	Silver(I) iodide	558	9.41
$AgNO_3$	Silver(I) nitrate	212	11.5
Ag_2S	Silver(I) sulfide	825	14.1
Al	Aluminum	660.32	10.789
$AlBr_3$	Aluminum bromide	97.5	11.25
$AlCl_3$	Aluminum chloride	192.6	35.4
AlF_3	Aluminum fluoride	2250 t	98
AlI_3	Aluminum iodide	188.28	15.9
Al_2O_3	Aluminum oxide	2053	111.4
Al_2S_3	Aluminum sulfide	1100	55
Am	Americium	1176	14.39
Ar	Argon	–189.36 t	1.18
As	Arsenic (gray)	817 t	24.44
$AsBr_3$	Arsenic(III) bromide	31.1	11.7
$AsCl_3$	Arsenic(III) chloride	–16	10.1
AsF_3	Arsenic(III) fluoride	–5.9	10.4
Au	Gold	1064.18	12.72
B	Boron	2075	50.2
BCl_3	Boron trichloride	–107	2.10
BF_3	Boron trifluoride	–126.8	4.20
BHO_2	Metaboric acid (γ form)	236	14.3
BH_3O_3	Boric acid (orthoboric acid)	170.9	22.3
BN	Boron nitride	2966	81
$BNaO_2$	Sodium metaborate	966	36.2
B_2O_3	Boron oxide	450	24.56
Ba	Barium	727	7.12
$BaBr_2$	Barium bromide	857	32.2
$BaCl_2$	Barium chloride	962	15.85
BaF_2	Barium fluoride	1368	17.8
BaH_2	Barium hydride	1200	25
BaH_2O_2	Barium hydroxide	408	16
BaI_2	Barium iodide	711	26.5
BaO	Barium oxide	1972	46
BaO_4S	Barium sulfate	1580	40
BaS	Barium sulfide	2229	63
Be	Beryllium	1287	7.895
$BeBr_2$	Beryllium bromide	508	18
$BeCl_2$	Beryllium chloride	415	8.66
BeF_2	Beryllium fluoride	552	4.77
BeI_2	Beryllium iodide	470	18
BeO	Beryllium oxide	2577	86
BeO_4S	Beryllium sulfate	1127	6
Bi	Bismuth	271.40	11.145
$BiCl_3$	Bismuth trichloride	230	10.9
BrF_5	Bromine pentafluoride	–60.5	5.67
BrH	Hydrogen bromide	–86.80	2.41
BrIn	Indium(I) bromide	290	15
BrK	Potassium bromide	734	25.5
BrLi	Lithium bromide	552	17.6
BrNa	Sodium bromide	747	26.11
$BrNaO_3$	Sodium bromate	381	28.11
BrRb	Rubidium bromide	682	15.5
BrTl	Thallium(I) bromide	460	16.4
Br_2	Bromine	–7.2	10.57
Br_2Ca	Calcium bromide	742	29.1
Br_2Cd	Cadmium bromide	568	20.9
Br_2Fe	Iron(II) bromide	691	50.2
Br_2Hg	Mercury(II) bromide	236	17.9
Br_2Mg	Magnesium bromide	711	39.3
Br_2Pb	Lead(II) bromide	371	16.44
Br_2Sr	Strontium bromide	657	10.1
Br_2Zn	Zinc bromide	394	16.7
Br_3Ga	Gallium(III) bromide	121.5	12.1
Br_3In	Indium(III) bromide	420	26
Br_3Pu	Plutonium(III) bromide	681	55.2
Br_3U	Uranium(III) bromide	727	43.9
Br_4Sn	Tin(IV) bromide	29.1	12.2
Br_4Th	Thorium(IV) bromide	679	66.9
Br_4Ti	Titanium(IV) bromide	39	12.9
Br_4U	Uranium(IV) bromide	519	55.2
Br_5Ta	Tantalum(V) bromide	265	45.6
C	Carbon (graphite)	4489 t	117
Ca	Calcium	842	8.54

Molecular formula	Name	t_m/°C	$\Delta_{fus}H$/ kJ mol^{-1}
$CaCl_2$	Calcium chloride	775	28.05
CaF_2	Calcium fluoride	1418	30
CaH_2	Calcium hydride	1000	6.7
CaI_2	Calcium iodide	783	41.8
CaO	Calcium oxide	2898	80
CaO_4S	Calcium sulfate	1460	28
CaS	Calcium sulfide	2524	70
Cd	Cadmium	321.07	6.21
$CdCl_2$	Cadmium chloride	564	48.58
CdF_2	Cadmium fluoride	1110	22.6
CdI_2	Cadmium iodide	387	15.3
Ce	Cerium	798	5.46
$CeCl_3$	Cerium(III) chloride	817	54.4
ClCs	Cesium chloride	645	15.9
ClCu	Copper(I) chloride	430	10.2
ClH	Hydrogen chloride	−114.17	2.00
ClI	Iodine chloride	27.39	11.6
ClIn	Indium(I) chloride	211	21.3
ClK	Potassium chloride	771	26.53
ClLi	Lithium chloride	610	19.9
$ClLiO_4$	Lithium perchlorate	236	29
ClNa	Sodium chloride	800.7	28.16
$ClNaO_3$	Sodium chlorate	248	22.1
ClRb	Rubidium chloride	715	18.4
ClTl	Thallium(I) chloride	430	15.56
Cl_2	Chlorine	−101.5	6.40
Cl_2Co	Cobalt(II) chloride	740	45
Cl_2Cr	Chromium(II) chloride	814	32.2
Cl_2Cu	Copper(II) chloride	630	20.4
Cl_2Fe	Iron(II) chloride	677	43.01
Cl_2Hg	Mercury(II) chloride	276	19.41
Cl_2Mg	Magnesium chloride	714	43.1
Cl_2Mn	Manganese(II) chloride	650	30.7
Cl_2Ni	Nickel(II) chloride	1009	71.2
Cl_2Pb	Lead(II) chloride	501	21.75
Cl_2Sn	Tin(II) chloride	247.1	14.52
Cl_2Sr	Strontium chloride	874	17.5
Cl_3Fe	Iron(III) chloride	304	43.1
Cl_3Ga	Gallium(III) chloride	77.9	11.13
Cl_3In	Indium(III) chloride	583	27
Cl_3La	Lanthanum chloride	859	43.1
Cl_3OP	Phosphorus(V) oxychloride	1.18	13.1
Cl_3P	Phosphorus(III) chloride	−112	7.10
Cl_3Sb	Antimony(III) chloride	73.4	12.7
Cl_4OW	Tungsten(VI) oxytetrachloride	211	45
Cl_4Si	Tetrachlorosilane	−68.74	7.60
Cl_4Sn	Tin(IV) chloride	−34.07	9.20
Cl_4Th	Thorium(IV) chloride	770	40.2
Cl_4Ti	Titanium(IV) chloride	−24.12	9.97
Cl_4U	Uranium(IV) chloride	590	45
Cl_4V	Vanadium(IV) chloride	−25.7	2.30
Cl_4Zr	Zirconium(IV) chloride	437 t	50
Cl_5Mo	Molybdenum(V) chloride	194	19
Cl_5Nb	Niobium(V) chloride	204.7	38.3
Cl_5Ta	Tantalum(V) chloride	216	41.6
Cl_6W	Tungsten(VI) chloride	275	6.60
Co	Cobalt	1495	16.06
CoF_2	Cobalt(II) fluoride	1127	59
Cr	Chromium	1907	21.0
Cr_2O_3	Chromium(III) oxide	2329	130

Molecular formula	Name	t_m/°C	$\Delta_{fus}H$/ kJ mol^{-1}
Cs	Cesium	28.5	2.09
CsF	Cesium fluoride	703	21.7
CsHO	Cesium hydroxide	342.3	7.78
Cs_2O_4S	Cesium sulfate	1005	35.7
Cu	Copper	1084.62	12.93
CuF_2	Copper(II) fluoride	836	55
CuO	Copper(II) oxide	1446	11.8
Dy	Dysprosium	1412	11.06
Er	Erbium	1529	19.9
Eu	Europium	822	9.21
FH	Hydrogen fluoride	−83.35	4.58
FK	Potassium fluoride	858	27.2
FLi	Lithium fluoride	848.2	27.09
FNa	Sodium fluoride	996	33.35
FRb	Rubidium fluoride	833	17.3
FTl	Thallium(I) fluoride	326	13.87
F_2	Fluorine	−219.66	0.51
F_2Fe	Iron(II) fluoride	1100	52
F_2HK	Potassium hydrogen fluoride	238.9	6.62
F_2Mg	Magnesium fluoride	1263	58.5
F_2Pb	Lead(II) fluoride	830	14.7
F_2Sr	Strontium fluoride	1477	28.5
F_3In	Indium(III) fluoride	1170	64
F_3Pu	Plutonium(III) fluoride	1396	59.8
F_4Pu	Plutonium(IV) fluoride	1027	65.3
F_4Th	Thorium(IV) fluoride	1110	44.0
F_4U	Uranium(IV) fluoride	1036	42.7
F_4Zr	Zirconium(IV) fluoride	932 t	64.2
F_5Nb	Niobium(V) fluoride	80	12.2
F_5V	Vanadium(V) fluoride	19.5	49.96
F_6Ir	Iridium(VI) fluoride	44	8.40
F_6Mo	Molybdenum(VI) fluoride	17.5	4.33
F_6Pu	Plutonium(VI) fluoride	52	17.6
F_6S	Sulfur hexafluoride	−50.7 t	5.02
F_6U	Uranium(VI) fluoride	64.0 t	19.1
F_6W	Tungsten(VI) fluoride	2.3	4.10
Fe	Iron	1538	13.81
FeI_2	Iron(II) iodide	587	45
FeO	Iron(II) oxide	1377	24
FeS	Iron(II) sulfide	1188	31.5
Fe_3O_4	Iron(II,III) oxide	1597	138
Ga	Gallium	29.76	5.576
GaI_3	Gallium(III) iodide	212	12.9
GaSb	Gallium antimonide	712	25.1
Ga_2O_3	Gallium(III) oxide	1806	100
Gd	Gadolinium	1313	10.0
Ge	Germanium	938.25	36.94
HI	Hydrogen iodide	−50.76	2.87
HKO	Potassium hydroxide	406	7.9
HLi	Lithium hydride	688.7	22.59
HLiO	Lithium hydroxide	471.1	20.88
HNO_3	Nitric acid	−41.6	10.5
HNaO	Sodium hydroxide	323	6.60
HORb	Rubidium hydroxide	382	8.0
H_2	Hydrogen	−259.34	0.12
H_2Mg	Magnesium hydride	327	14
H_2O	Water	0.00	6.01
H_2O_2	Hydrogen peroxide	−0.43	12.50
H_2O_2Sr	Strontium hydroxide	535	23
H_2O_4S	Sulfuric acid	10.31	10.71

Molecular formula	Name	t_m/°C	$\Delta_{fus}H$/ kJ mol^{-1}
H_2S	Hydrogen sulfide	−85.5	2.38
H_2Sr	Strontium hydride	1050	23
H_3N	Ammonia	−77.73	5.66
H_3O_2P	Hypophosphorous acid	26.5	9.7
H_3O_3P	Phosphorous acid	74.4	12.8
H_3O_4P	Phosphoric acid	42.4	13.4
H_4IN	Ammonium iodide	551	21
H_4N_2	Hydrazine	1.4	12.6
$H_4N_2O_3$	Ammonium nitrate	169.7	6.40
Hf	Hafnium	2233	27.2
Hg	Mercury	−38.83	2.29
HgI_2	Mercury(II) iodide	259	18.9
Hg_2I_2	Mercury(I) iodide	290	27
Ho	Holmium	1474	17.0
IIn	Indium(I) iodide	364.4	17.26
IK	Potassium iodide	681	24
ILi	Lithium iodide	469	14.6
INa	Sodium iodide	660	23.6
IRb	Rubidium iodide	642	12.5
ITl	Thallium(I) iodide	441.7	14.73
I_2	Iodine	113.7	15.52
I_2Mg	Magnesium iodide	634	26
I_2Pb	Lead(II) iodide	410	23.4
I_2Sr	Strontium iodide	538	19.7
I_3In	Indium(III) iodide	207	18.48
I_4Si	Tetraiodosilane	120.5	19.7
I_4Th	Thorium(IV) iodide	570	61.4
I_4Ti	Titanium(IV) iodide	150	19.8
I_4U	Uranium(IV) iodide	506	70.7
In	Indium	156.60	3.281
InSb	Indium antimonide	525	25.5
In_2O_3	Indium(III) oxide	1912	105
Ir	Iridium	2446	41.12
K	Potassium	63.5	2.33
KNO_3	Potassium nitrate	337	10.1
K_2O_4S	Potassium sulfate	1069	36.4
K_2S	Potassium sulfide	948	16.15
Kr	Krypton	−157.38 t	1.64
La	Lanthanum	918	6.20
Li	Lithium	180.50	3.00
$LiNO_3$	Lithium nitrate	253	24.9
Li_2O_3Si	Lithium metasilicate	1201	28
Li_2O_4S	Lithium sulfate	859	7.50
Lu	Lutetium	1663	22
Mg	Magnesium	650	8.48
MgO	Magnesium oxide	2825	77
MgO_4S	Magnesium sulfate	1127	14.6
MgS	Magnesium sulfide	2226	63
Mg_2O_4Si	Magnesium orthosilicate	1897	71
Mn	Manganese	1246	12.91
MnO	Manganese(II) oxide	1839	54.4
Mo	Molybdenum	2623	37.48
MoO_3	Molybdenum(VI) oxide	801	48
$NNaO_3$	Sodium nitrate	307	15
NO	Nitric oxide	−163.6	2.30
NO_3Rb	Rubidium nitrate	305	5.60
NO_3Tl	Thallium(I) nitrate	206	9.6
N_2	Nitrogen	−210.0	0.71
N_2O	Nitrous oxide	−90.8	6.54
N_2O_4	Nitrogen tetroxide	−9.3	14.65

Molecular formula	Name	t_m/°C	$\Delta_{fus}H$/ kJ mol^{-1}
Na	Sodium	97.80	2.60
Na_2O	Sodium oxide	1132	48
Na_2O_3Si	Sodium metasilicate	1089	52
Na_2O_4S	Sodium sulfate	884	23.6
Na_2S	Sodium sulfide	1172	19
Nb	Niobium	2477	30
NbO	Niobium(II) oxide	1936	85
NbO_2	Niobium(IV) oxide	1901	92
Nb_2O_5	Niobium(V) oxide	1512	104.3
Nd	Neodymium	1021	7.14
Ne	Neon	−248.61 t	0.328
Ni	Nickel	1455	17.04
NiS	Nickel(II) sulfide	976	30.1
Np	Neptunium	644	3.20
OSr	Strontium oxide	2531	81
OTl_2	Thallium(I) oxide	579	30.3
OV	Vanadium(II) oxide	1789	63
OZn	Zinc oxide	1974	52.3
O_2	Oxygen	−218.79	0.44
O_2Si	Silicon dioxide (cristobalite)	1722	9.6
O_2Zr	Zirconium(IV) oxide	2709	87
O_3S	Sulfur trioxide	16.8	8.60
O_3Tl_2	Thallium(III) oxide	834	53
O_3W	Tungsten(VI) oxide	1472	73
O_3Y_2	Yttrium oxide	2438	105
O_4Os	Osmium(VIII) oxide	41	9.8
O_4SSr	Strontium sulfate	1606	36
O_4STl_2	Thallium(I) sulfate	632	23
O_5P_2	Phosphorus(V) oxide	562	27.2
O_5Ta_2	Tantalum(V) oxide	1784	120
O_5V_2	Vanadium(V) oxide	670	64.5
O_7Re_2	Rhenium(VII) oxide	297	64.2
Os	Osmium	3033	57.85
P	Phosphorus (white)	44.15	0.66
Pa	Protactinium	1572	12.34
Pb	Lead	327.46	4.782
PbS	Lead(II) sulfide	1113	49.4
Pd	Palladium	1554.9	16.74
Pr	Praseodymium	931	6.89
Pt	Platinum	1768.4	22.17
Pu	Plutonium	640	2.82
Rb	Rubidium	39.3	2.19
Re	Rhenium	3186	60.43
Rh	Rhodium	1964	26.59
Ru	Ruthenium	2334	38.59
S	Sulfur (monoclinic)	115.21	1.72
SSr	Strontium sulfide	2226	63
STl_2	Thallium(I) sulfide	448	12
Sb	Antimony	630.63	19.79
Sc	Scandium	1541	14.1
Se	Selenium (gray)	220.5	6.69
Si	Silicon	1414	50.21
Sm	Samarium	1074	8.62
Sn	Tin (white)	231.93	7.173
Sr	Strontium	777	7.43
Ta	Tantalum	3017	36.57
Tb	Terbium	1356	10.15
Tc	Technetium	2157	33.29
Te	Tellurium	449.51	17.49
Th	Thorium	1750	13.81

Molecular formula	Name	t_m/°C	$\Delta_{fus}H$/ kJ mol^{-1}
Ti	Titanium	1668	14.15
Tl	Thallium	304	4.14
Tm	Thulium	1545	16.84
U	Uranium	1135	9.14
V	Vanadium	1910	21.5
W	Tungsten	3422	52.31
Xe	Xenon	–111.79 t	2.27
Y	Yttrium	1522	11.4
Yb	Ytterbium	819	7.66
Zn	Zinc	419.53	7.068
Zr	Zirconium	1855	21.00
$CBaO_3$	Barium carbonate	1555	40
$CBrCl_3$	Bromotrichloromethane	–5.65	2.53
CBr_4	Tetrabromomethane	92.3	3.76
$CCaO_3$	Calcium carbonate (calcite)	1330	36
CCl_2O	Carbonyl chloride	–127.78	5.74
CCl_3F	Trichlorofluoromethane	–110.44	6.89
CCl_4	Tetrachloromethane	–22.62	2.56
CF_4	Tetrafluoromethane	–183.60	0.704
$CHBr_3$	Tribromomethane	8.69	11.05
$CHClF_2$	Chlorodifluoromethane	–157.42	4.12
$CHCl_3$	Trichloromethane	–63.41	9.5
CHF_3	Trifluoromethane	–155.2	4.06
CHI_3	Triiodomethane	121.2	16.44
CHN	Hydrogen cyanide	–13.29	8.41
$CHNaO_2$	Sodium formate	257.3	17.7
CHO_2Tl	Thallium(I) formate	101	10.9
CH_2Cl_2	Dichloromethane	–97.2	4.60
CH_2N_2	Cyanamide	45.56	7.27
CH_2N_4	Tetrazole	157.3	18.2
CH_2O_2	Formic acid	8.3	12.68
CH_3Br	Bromomethane	–93.68	5.98
CH_3Cl	Chloromethane	–97.7	6.43
CH_3NO	Formamide	2.49	8.44
CH_3NO_2	Nitromethane	–28.38	9.70
CH_3NO_3	Methyl nitrate	–83.0	8.24
CH_4	Methane	–182.47	0.94
CH_4N_2O	Urea	133.3	13.9
CH_4N_2S	Thiourea	178	14.0
CH_4O	Methanol	–97.53	3.215
CH_4S	Methanethiol	–123	5.91
CH_5N	Methylamine	–93.5	6.13
CH_6N_2	Methylhydrazine	–52.36	10.42
CK_2O_3	Potassium carbonate	898	27.6
CLi_2O_3	Lithium carbonate	723	41
$CMgO_3$	Magnesium carbonate	990	59
CNa_2O_3	Sodium carbonate	858.1	29.7
CO	Carbon monoxide	–205.02	0.833
COS	Carbon oxysulfide	–138.8	4.73
CO_2	Carbon dioxide	–56.56 t	9.02
CO_3Sr	Strontium carbonate	1494	40
CO_3Tl_2	Thallium(I) carbonate	272	18.4
CS_2	Carbon disulfide	–112.1	4.39
CSe_2	Carbon diselenide	–43.7	6.36
$C_2Br_2F_4$	1,2–Dibromotetrafluoroethane	–110.32	7.04
C_2ClF_3	Chlorotrifluoroethene	–158.2	5.55
C_2ClF_5	Chloropentafluoroethane	–99.4	1.86
$C_2Cl_2F_4$	1,2–Dichloro–1,1,2,2–tetrafluoroethane	–92.53	1.51
$C_2Cl_3F_3$	1,1,2–Trichloro–1,2,2–trifluoroethane	–36.22	2.47
C_2Cl_4	Tetrachloroethene	–22.3	10.88
$C_2Cl_4F_2$	1,1,2,2–Tetrachloro–1,2–difluoroethane	24.8	3.67
C_2Cl_6	Hexachloroethane	186.8 t	9.75
C_2F_4	Tetrafluoroethene	–131.15	7.72
C_2F_6	Hexafluoroethane	–100.05	2.69
C_2HCl_3	Trichloroethylene	–84.7	8.45
$C_2HCl_3O_2$	Trichloroacetic acid	59.2	5.90
C_2HCl_5	Pentachloroethane	–28.78	11.3
$C_2H_2Cl_2$	1,1–Dichloroethene	–122.56	6.51
$C_2H_2Cl_2$	*cis*–1,2–Dichloroethene	–80.0	7.2
$C_2H_2Cl_4$	1,1,2,2–Tetrachloroethane	–42.4	9.17
C_2H_3Br	Bromoethene	–139.54	5.12
C_2H_3Cl	Chloroethene	–153.84	4.92
$C_2H_3ClO_2$	Chloroacetic acid	63	12.28
$C_2H_3Cl_3$	1,1,1–Trichloroethane	–30.01	2.35
$C_2H_3Cl_3$	1,1,2–Trichloroethane	–36.3	11.46
$C_2H_3F_3$	1,1,1–Trifluoroethane	–111.3	6.19
$C_2H_3KO_2$	Potassium acetate	309	7.65
C_2H_3N	Acetonitrile	–43.82	8.16
$C_2H_3NaO_2$	Sodium acetate	328.2	17.9
C_2H_4	Ethylene	–169.15	3.35
$C_2H_4Br_2$	1,2–Dibromoethane	9.84	10.89
$C_2H_4Cl_2$	1,1–Dichloroethane	–96.9	7.87
$C_2H_4Cl_2$	1,2–Dichloroethane	–35.7	8.84
C_2H_4O	Acetaldehyde	–123.37	2.31
C_2H_4O	Ethylene oxide	–112.5	5.17
$C_2H_4O_2$	Acetic acid	16.64	11.73
C_2H_5Br	Bromoethane	–118.6	7.47
C_2H_5Cl	Chloroethane	–138.4	4.45
C_2H_5NO	Acetamide	80.16	15.59
$C_2H_5NO_2$	Nitroethane	–89.5	9.85
C_2H_6	Ethane	–182.79	2.72*
$C_2H_6N_2O$	*N*–Methylurea	104.9	14.0
C_2H_6O	Ethanol	–114.14	4.931
C_2H_6O	Dimethyl ether	–141.5	4.94
C_2H_6OS	Dimethyl sulfoxide	17.89	14.37
$C_2H_6O_2$	Ethylene glycol	–12.69	9.96
$C_2H_6O_2S$	Dimethyl sulfone	108.9	18.30
C_2H_6S	Ethanethiol	–147.88	4.98
C_2H_6S	Dimethyl sulfide	–98.24	7.99
$C_2H_6S_2$	Dimethyl disulfide	–84.67	9.19
C_2H_6Zn	Dimethyl zinc	–43.0	6.83
C_2H_7N	Dimethylamine	–92.18	5.94
$C_2H_8N_2$	1,2–Ethanediamine	11.14	22.58
$C_2H_8N_2$	1,1–Dimethylhydrazine	–57.20	10.07
$C_2H_8N_2$	1,2–Dimethylhydrazine	–8.9	13.64
C_2N_2	Cyanogen	–27.83	8.11
C_3F_6O	Perfluoroacetone	–125.45	8.38
C_3F_8	Perfluoropropane	–147.70	0.477
C_3H_3N	Acrylonitrile	–83.48	6.23
C_3H_3NS	Thiazole	–33.62	9.57
$C_3H_3N_3$	1,3,5–Triazine	80.3	14.56
C_3H_4	Allene	–136.6	4.40
$C_3H_4N_2$	1*H*–Pyrazole	70.7	14.0
$C_3H_4N_2$	Imidazole	89.5	12.82
$C_3H_4O_2$	Acrylic acid	12.5	9.51
C_3H_5N	Propanenitrile	–92.78	5.03

Molecular formula	Name	t_m/°C	$\Delta_{fus}H$/ kJ mol^{-1}
$C_3H_5N_3O_9$	Trinitroglycerol	13.5	21.87
C_3H_6	Propene	−185.24	3.003
C_3H_6	Cyclopropane	−127.58	5.44
$C_3H_6Br_2$	1,2−Dibromopropane	−55.49	8.94
$C_3H_6Br_2$	1,3−Dibromopropane	−34.5	14.6
$C_3H_6Cl_2$	1,2−Dichloropropane, (±)	−100.53	6.40
$C_3H_6Cl_2$	2,2−Dichloropropane	−33.9	2.30
C_3H_6O	Acetone	−94.7	5.77
C_3H_6O	Methyloxirane	−111.9	6.53
C_3H_6O	Oxetane	−97	6.5
$C_3H_6O_2$	Propanoic acid	−20.5	10.66
$C_3H_6O_2$	Methyl acetate	−98.25	7.49
$C_3H_6O_2$	1,3−Dioxolane	−97.22	6.57
$C_3H_6O_3$	1,3,5−Trioxane	60.29	15.11
C_3H_6S	Thietane	−73.24	8.25
C_3H_7Br	1−Bromopropane	−110.3	6.44
C_3H_7Br	2−Bromopropane	−89.0	6.53
C_3H_7Cl	1−Chloropropane	−122.9	5.54
C_3H_7Cl	2−Chloropropane	−117.18	7.39
C_3H_7N	Cyclopropylamine	−35.39	13.18
C_3H_7NO	*N,N*−Dimethylformamide	−60.48	7.90
C_3H_8	Propane	−187.63	3.50
$C_3H_8N_2O$	*N,N*−Dimethylurea	182.1	23.0
$C_3H_8N_2O$	N,N′−Dimethylurea	106.6	13.0
C_3H_8O	1−Propanol	−124.39	5.37
C_3H_8O	2−Propanol	−87.9	5.41
$C_3H_8O_2$	1,3−Propylene glycol	−27.7	7.1
$C_3H_8O_2$	Dimethoxymethane	−105.1	8.33
$C_3H_8O_3$	Glycerol	18.1	18.3
C_3H_8S	1−Propanethiol	−113.13	5.48
C_3H_8S	2−Propanethiol	−130.5	5.74
C_3H_8S	Ethyl methyl sulfide	−105.93	9.76
C_3H_9N	Propylamine	−84.75	10.97
C_3H_9N	Isopropylamine	−95.13	7.33
C_3H_9N	Trimethylamine	−117.1	7
C_3H_9NO	3−Amino−1−propanol	12.4	19.7
C_4F_8	Perfluorocyclobutane	−40.19	2.77
C_4F_{10}	Perfluorobutane	−129.1	7.66
$C_4H_2O_3$	Maleic anhydride	52.56	13.60
$C_4H_4N_2$	Succinonitrile	57.98	3.70
$C_4H_4N_2$	Pyrazine	51.0	12.9
C_4H_4O	Furan	−85.61	3.80
$C_4H_4O_3$	Succinic anhydride	119	20.4
C_4H_4S	Thiophene	−38.21	5.07
C_4H_5N	Pyrrole	−23.39	7.91
C_4H_6	1,2−Butadiene	−136.2	6.96
C_4H_6	1,3−Butadiene	−108.91	7.98
C_4H_6	1−Butyne	−125.7	6.03
C_4H_6	2−Butyne	−32.2	9.23
C_4H_6O	Divinyl ether	−100.6	7.9
$C_4H_6O_2$	*cis*−Crotonic acid	15	12.6
$C_4H_6O_2$	*trans*−Crotonic acid	71.5	13.0
$C_4H_6O_2$	γ−Butyrolactone	−43.61	9.57
$C_4H_6O_3$	Acetic anhydride	−74.1	10.5
$C_4H_6O_4$	Succinic acid	187.9	32.4
$C_4H_6O_4$	Dimethyl oxalate	54.8	21.1
C_4H_8	1−Butene	−185.34	3.96
C_4H_8	*cis*−2−Butene	−138.88	7.31
C_4H_8	*trans*−2−Butene	−105.52	9.76
C_4H_8	Isobutene	−140.7	5.92
C_4H_8	Cyclobutane	−90.7	1.09
C_4H_8	Methylcyclopropane	−177.6	2.8
C_4H_8O	Butanal	−96.86	10.77
C_4H_8O	2−Butanone	−86.64	8.39
C_4H_8O	Tetrahydrofuran	−108.44	8.54
$C_4H_8O_2$	Butanoic acid	−5.1	11.59
$C_4H_8O_2$	Ethyl acetate	−83.8	10.48
$C_4H_8O_2$	1,4−Dioxane	11.85	12.84
C_4H_8S	Tetrahydrothiophene	−96.2	7.35
C_4H_9Br	1−Bromobutane	−112.6	9.23
C_4H_9Br	2−Bromobutane, (±)	−112.65	6.89
C_4H_9Cl	2−Chloro−2−methylpropane	−25.60	2.07
C_4H_9N	Pyrrolidine	−57.79	8.58
C_4H_9NO	Morpholine	−4.8	14.5
C_4H_{10}	Butane	−138.3	4.66
C_4H_{10}	Isobutane	−159.4	4.54
$C_4H_{10}O$	1−Butanol	−88.6	9.37
$C_4H_{10}O$	2−Butanol	−88.5	5.97
$C_4H_{10}O$	2−Methyl−1−propanol	−101.9	6.32
$C_4H_{10}O$	2−Methyl−2−propanol	25.69	6.70
$C_4H_{10}O$	Diethyl ether	−116.2	7.19
$C_4H_{10}O_2$	1,4−Butanediol	20.4	18.70
$C_4H_{10}O_2$	Ethylene glycol dimethyl ether	−69.20	12.6
$C_4H_{10}S$	1−Butanethiol	−115.7	10.46
$C_4H_{10}S$	Diethyl sulfide	−103.91	10.90
$C_4H_{11}N$	*tert*−Butylamine	−66.94	0.882
$C_4H_{12}Pb$	Tetramethyl lead	−30.2	10.80
$C_4H_{12}Si$	Tetramethylsilane	−99.06	6.87
$C_4H_{12}Sn$	Tetramethylstannane	−55.1	9.30
$C_5H_4O_2$	Furfural	−38.1	14.37
C_5H_5N	Pyridine	−41.70	8.28
C_5H_6O	2−Methylfuran	−91.3	8.55
$C_5H_6O_2$	Furfuryl alcohol	−14.6	13.13
C_5H_8	*cis*−1,3−Pentadiene	−140.8	5.64
C_5H_8	*trans*−1,3−Pentadiene	−87.4	7.14
C_5H_8	1,4−Pentadiene	−148.2	6.12
C_5H_8	2−Methyl−1,3−butadiene	−145.9	4.93
C_5H_8	Cyclopentene	−135.0	3.36
C_5H_8	Spiropentane	−107.0	6.43
$C_5H_8O_2$	Methyl methacrylate	−47.55	14.4
$C_5H_8O_3$	4−Oxopentanoic acid	33	9.22
$C_5H_8O_4$	Glutaric acid	97.8	20.3
C_5H_9N	Pentanenitrile	−96.2	9
C_5H_{10}	1−Pentene	−165.12	5.94
C_5H_{10}	*cis*−2−Pentene	−151.36	7.11
C_5H_{10}	*trans*−2−Pentene	−140.21	8.35
C_5H_{10}	2−Methyl−1−butene	−137.53	7.91
C_5H_{10}	3−Methyl−1−butene	−168.43	5.36
C_5H_{10}	2−Methyl−2−butene	−133.72	7.60
C_5H_{10}	Cyclopentane	−93.4	0.61
$C_5H_{10}O$	Cyclopentanol	−17.5	1.535
$C_5H_{10}O$	2−Pentanone	−76.8	10.63
$C_5H_{10}O$	3−Pentanone	−39	11.59
$C_5H_{10}O$	3−Methyl−2−butanone	−93.1	9.34
$C_5H_{10}O$	Tetrahydropyran	−49.1	1.8
$C_5H_{10}O_2$	Pentanoic acid	−33.6	14.16
$C_5H_{11}Br$	1−Bromopentane	−88.0	14.37
$C_5H_{11}N$	Cyclopentylamine	−82.7	8.31
$C_5H_{11}N$	Piperidine	−11.02	14.85
C_5H_{12}	Pentane	−129.67	8.40

Molecular formula	Name	t_m/°C	$\Delta_{fus}H$/ kJ mol^{-1}
C_5H_{12}	Isopentane	−159.77	5.15
C_5H_{12}	Neopentane	−16.4	3.10
$C_5H_{12}O$	1−Pentanol	−77.6	10.50
$C_5H_{12}O$	2−Methyl−2−butanol	−9.1	4.46
$C_5H_{12}O$	Butyl methyl ether	−115.7	10.85
$C_5H_{12}O$	Methyl *tert*−butyl ether	−108.6	7.60
$C_5H_{12}O_4$	Pentaerythritol	258	4.8
$C_5H_{12}S$	1−Pentanethiol	−75.65	17.53
C_6Cl_6	Hexachlorobenzene	228.83	25.2
C_6F_6	Hexafluorobenzene	5.03	11.59
C_6F_{14}	Perfluorohexane	−88.2	6.84
C_6HF_5	Pentafluorobenzene	−47.4	10.87
C_6HF_5O	Pentafluorophenol	37.5	16.41
$C_6H_2F_4$	1,2,3,5−Tetrafluorobenzene	−46.25	6.36
$C_6H_2F_4$	1,2,4,5−Tetrafluorobenzene	3.88	15.05
$C_6H_3Cl_3$	1,2,3−Trichlorobenzene	51.3	17.9
$C_6H_3Cl_3$	1,2,4−Trichlorobenzene	16.92	16.4
$C_6H_3Cl_3$	1,3,5−Trichlorobenzene	62.8	18.1
$C_6H_3N_3O_6$	1,3,5−Trinitrobenzene	122.9	15.4
$C_6H_4ClNO_2$	1−Chloro−2−nitrobenzene	32.1	17.9
$C_6H_4ClNO_2$	1−Chloro−3−nitrobenzene	44.4	19.4
$C_6H_4ClNO_2$	1−Chloro−4−nitrobenzene	82	14.1
$C_6H_4Cl_2$	*o*−Dichlorobenzene	−17.0	12.4
$C_6H_4Cl_2$	*m*−Dichlorobenzene	−24.8	12.6
$C_6H_4Cl_2$	*p*−Dichlorobenzene	53.09	18.19
$C_6H_4F_2$	*o*−Difluorobenzene	−47.1	11.05
$C_6H_4F_2$	*m*−Difluorobenzene	−69.12	8.58
$C_6H_4O_2$	*p*−Benzoquinone	115	18.5
C_6H_5Br	Bromobenzene	−30.72	10.70
C_6H_5Cl	Chlorobenzene	−45.31	9.6
C_6H_5ClO	*o*−Chlorophenol	9.4	13.0
C_6H_5ClO	*m*−Chlorophenol	32.6	14.9
C_6H_5ClO	*p*−Chlorophenol	42.8	14.1
C_6H_5F	Fluorobenzene	−42.18	11.31
C_6H_5I	Iodobenzene	−31.3	9.75
C_6H_5NO	Nitrosobenzene	67	31.0
$C_6H_5NO_2$	Nitrobenzene	5.7	12.12
$C_6H_5NO_3$	*o*−Nitrophenol	44.8	17.7
$C_6H_5NO_3$	*m*−Nitrophenol	96.8	20.6
$C_6H_5NO_3$	*p*−Nitrophenol	113.6	18.8
C_6H_6	Benzene	5.49	9.87
C_6H_6ClN	*o*−Chloroaniline	−1.9	11.9
C_6H_6ClN	*m*−Chloroaniline	−10.28	10.15
C_6H_6ClN	*p*−Chloroaniline	70.5	20.0
$C_6H_6N_2O_2$	*o*−Nitroaniline	71.0	16.1
$C_6H_6N_2O_2$	*m*−Nitroaniline	113.4	23.6
$C_6H_6N_2O_2$	*p*−Nitroaniline	147.5	21.2
C_6H_6O	Phenol	40.89	11.51
$C_6H_6O_2$	*p*−Hydroquinone	172.4	26.8
$C_6H_6O_2$	Pyrocatechol	104.6	22.8
$C_6H_6O_2$	Resorcinol	109.4	20.4
C_6H_6S	Benzenethiol	−14.93	11.48
C_6H_7N	Aniline	−6.02	10.54
C_6H_7N	2−Methylpyridine	−66.68	9.72
C_6H_7N	3−Methylpyridine	−18.14	14.18
C_6H_7N	4−Methylpyridine	3.67	12.58
$C_6H_8N_2$	*o*−Phenylenediamine	102.1	23.1
$C_6H_8N_2$	*m*−Phenylenediamine	66.0	15.57
$C_6H_8N_2$	*p*−Phenylenediamine	141.1	23.8
$C_6H_8N_2$	Phenylhydrazine	20.6	14.05
C_6H_{10}	Cyclohexene	−103.5	3.29
$C_6H_{10}O$	Cyclohexanone	−27.9	1.328
$C_6H_{10}O_2$	2−Oxepanone	−1.0	13.83
$C_6H_{10}O_4$	Adipic acid	152.5	36.3
$C_6H_{11}Cl$	Chlorocyclohexane	−43.81	2.043
C_6H_{12}	1−Hexene	−139.76	9.35
C_6H_{12}	*cis*−2−Hexene	−141.11	8.88
C_6H_{12}	2,3−Dimethyl−2−butene	−74.19	6.45
C_6H_{12}	Cyclohexane	6.59	2.68
C_6H_{12}	Methylcyclopentane	−142.42	6.93
$C_6H_{12}O$	Hexanal	−56	13.3
$C_6H_{12}O$	2−Hexanone	−55.5	14.9
$C_6H_{12}O$	3−Hexanone	−55.4	13.49
$C_6H_{12}O$	Cyclohexanol	25.93	1.78
$C_6H_{12}O_3$	Paraldehyde	12.6	13.5
$C_6H_{13}Br$	1−Bromohexane	−83.7	18.1
$C_6H_{13}N$	Cyclohexylamine	−17.8	17.5
C_6H_{14}	Hexane	−95.35	13.08
C_6H_{14}	2−Methylpentane	−153.6	6.27
C_6H_{14}	3−Methylpentane	−162.90	5.30
C_6H_{14}	2,2−Dimethylbutane	−98.8	0.58
C_6H_{14}	2,3−Dimethylbutane	−128.10	0.79
$C_6H_{14}O$	1−Hexanol	−47.4	15.38
$C_6H_{14}O$	Dipropyl ether	−114.8	10.8
$C_6H_{14}O$	Diisopropyl ether	−85.4	12.04
$C_6H_{14}O_2$	1,6−Hexanediol	41.5	22.2
C_7F_8	Perfluorotoluene	−65.49	11.54
C_7F_{16}	Perfluoroheptane	−51.2	6.95
$C_7H_3F_5$	2,3,4,5,6−Pentafluorotoluene	−29.78	13.1
C_7H_5ClO	Benzoyl chloride	−0.4	19.2
$C_7H_5ClO_2$	*o*−Chlorobenzoic acid	140.2	25.6
C_7H_5N	Benzonitrile	−13.99	9.1
$C_7H_5N_3O_6$	2,4,6−Trinitrotoluene	80.5	22.9
$C_7H_6O_2$	Benzoic acid	122.35	18.02
$C_7H_6O_3$	*o*−Hydroxybenzoic acid	159.0	14.2
C_7H_7Cl	*o*−Chlorotoluene	−35.8	9.6
C_7H_7NO	Benzamide	127.3	19.5
$C_7H_7NO_2$	*p*−Nitrotoluene	51.63	16.81
C_7H_8	Toluene	−94.95	6.64
C_7H_8O	*o*−Cresol	31.03	15.82
C_7H_8O	*m*−Cresol	12.24	10.71
C_7H_8O	*p*−Cresol	34.77	12.71
C_7H_8O	Benzyl alcohol	−15.4	8.97
C_7H_8O	Anisole	−37.13	12.9
C_7H_9N	*o*−Methylaniline	−14.41	11.66
C_7H_9N	*m*−Methylaniline	−31.3	7.9
C_7H_9N	*p*−Methylaniline	43.6	18.9
C_7H_{14}	1−Heptene	−118.9	12.41
C_7H_{14}	Cycloheptane	−8.46	1.88
C_7H_{14}	Methylcyclohexane	−126.6	6.75
$C_7H_{14}O$	1−Heptanal	−43.4	23.2
$C_7H_{14}O$	Cycloheptanol	7.2	1.60
$C_7H_{14}O_2$	Heptanoic acid	−7.17	15.13
$C_7H_{15}Br$	1−Bromoheptane	−56.1	21.8
C_7H_{16}	Heptane	−90.55	14.03
C_7H_{16}	2−Methylhexane	−118.2	9.19
C_7H_{16}	3−Ethylpentane	−118.55	9.55
C_7H_{16}	2,2−Dimethylpentane	−123.7	5.82
C_7H_{16}	2,4−Dimethylpentane	−119.2	6.85
C_7H_{16}	3,3−Dimethylpentane	−134.4	6.85

Molecular formula	Name	t_m/°C	$\Delta_{fus}H$/ kJ mol^{-1}
C_7H_{16}	2,2,3–Trimethylbutane	–24.6	2.26
$C_7H_{16}O$	1–Heptanol	–33.2	18.17
C_8H_8	Styrene	–30.65	10.9
$C_8H_8O_2$	*o*–Toluic acid	103.5	19.5
$C_8H_8O_2$	*m*–Toluic acid	109.9	15.7
$C_8H_8O_2$	*p*–Toluic acid	179.6	22.7
$C_8H_8O_2$	Benzeneacetic acid	76.5	16.3
$C_8H_8O_2$	Methyl benzoate	–12.4	9.74
C_8H_{10}	Ethylbenzene	–94.96	9.18
C_8H_{10}	*o*–Xylene	–25.2	13.6
C_8H_{10}	*m*–Xylene	–47.8	11.6
C_8H_{10}	*p*–Xylene	13.25	17.12
$C_8H_{10}O$	2,3–Xylenol	72.5	21.0
$C_8H_{10}O$	2,5–Xylenol	74.8	23.4
$C_8H_{10}O$	2,6–Xylenol	45.8	18.9
$C_8H_{10}O$	3,4–Xylenol	65.1	18.1
$C_8H_{10}O$	3,5–Xylenol	63.4	17.4
C_8H_{16}	1–Octene	–101.7	15.31
C_8H_{16}	Cyclooctane	14.59	2.41
C_8H_{16}	Ethylcyclohexane	–111.3	8.33
C_8H_{16}	1,1–Dimethylcyclohexane	–33.3	2.07
C_8H_{16}	*cis*–1,2–Dimethylcyclohexane	–49.8	1.64
C_8H_{16}	*trans*–1,2–Dimethylcyclohexane	–88.15	10.49
C_8H_{16}	*cis*–1,3–Dimethylcyclohexane	–75.53	10.82
C_8H_{16}	*trans*–1,3–Dimethylcyclohexane	–90.07	9.87
C_8H_{16}	*cis*–1,4–Dimethylcyclohexane	–87.39	9.31
C_8H_{16}	*trans*–1,4–Dimethylcyclohexane	–36.93	12.33
$C_8H_{16}O_2$	Octanoic acid	16.5	21.35
$C_8H_{17}Br$	1–Bromooctane	–55.0	24.7
C_8H_{18}	Octane	–56.82	20.73
C_8H_{18}	2–Methylheptane	–109.02	11.92
C_8H_{18}	3–Methylheptane	–120.48	11.69
C_8H_{18}	4–Methylheptane	–121.0	10.8
C_8H_{18}	2,2,4–Trimethylpentane	–107.3	9.20
$C_8H_{18}O$	1–Octanol	–14.8	23.7
C_9H_7N	Quinoline	–14.78	10.66
C_9H_7N	Isoquinoline	26.47	13.54
C_9H_8	Indene	–1.5	10.20
C_9H_{10}	Indan	–51.38	8.60
C_9H_{12}	Propylbenzene	–99.6	9.27
C_9H_{12}	Isopropylbenzene	–96.02	7.33
C_9H_{12}	*o*–Ethyltoluene	–79.83	9.96
C_9H_{12}	*m*–Ethyltoluene	–95.6	7.6
C_9H_{12}	*p*–Ethyltoluene	–62.35	12.7
C_9H_{12}	1,2,3–Trimethylbenzene	–25.4	8.18
C_9H_{12}	1,2,4–Trimethylbenzene	–43.77	13.19
C_9H_{12}	1,3,5–Trimethylbenzene	–44.72	9.51
C_9H_{18}	Propylcyclohexane	–94.9	10.37
$C_9H_{18}O$	Nonanal	–19.3	30.5
$C_9H_{18}O$	5–Nonanone	–3.8	24.93
$C_9H_{18}O_2$	Nonanoic acid	12.4	19.82
C_9H_{20}	Nonane	–53.46	15.47
C_9H_{20}	3,3–Diethylpentane	–33.1	10.09
C_9H_{20}	2,2,3,3–Tetramethylpentane	–9.75	2.33
C_9H_{20}	2,2,4,4–Tetramethylpentane	–66.54	9.74
$C_{10}H_7Br$	1–Bromonaphthalene	6.1	15.2
$C_{10}H_7Br$	2–Bromonaphthalene	55.9	14.4
$C_{10}H_7Cl$	1–Chloronaphthalene	–2.5	12.9
$C_{10}H_7Cl$	2–Chloronaphthalene	58.0	14.0
$C_{10}H_8$	Naphthalene	80.26	19.01
$C_{10}H_8O$	1–Naphthol	95.0	23.1
$C_{10}H_8O$	2–Naphthol	121.5	18.1
$C_{10}H_{14}$	Butylbenzene	–87.85	11.22
$C_{10}H_{14}$	1–Isopropyl–4–methylbenzene	–67.94	9.66
$C_{10}H_{14}$	1,2,4,5–Tetramethylbenzene	79.3	21
$C_{10}H_{14}O$	Thymol	49.5	21.3
$C_{10}H_{18}$	*cis*–Decahydronaphthalene	–42.9	9.49
$C_{10}H_{18}$	*trans*–Decahydronaphthalene	–30.4	14.41
$C_{10}H_{18}O_4$	Sebacic acid	130.9	40.8
$C_{10}H_{20}$	1–Decene	–66.3	13.81
$C_{10}H_{20}$	Butylcyclohexane	–74.73	14.16
$C_{10}H_{20}O$	Decanal	–4.0	34.5
$C_{10}H_{20}O_2$	Decanoic acid	31.4	27.8
$C_{10}H_{22}$	Decane	–29.6	28.72
$C_{10}H_{22}O$	1–Decanol	6.9	43
$C_{11}H_{10}$	1–Methylnaphthalene	–30.43	6.95
$C_{11}H_{10}$	2–Methylnaphthalene	34.6	12.13
$C_{11}H_{24}$	Undecane	–25.5	22.2
$C_{12}H_8$	Acenaphthylene	91.8	6.9
$C_{12}H_9N$	Carbazole	246.3	24.1
$C_{12}H_{10}$	Acenaphthene	93.4	21.49
$C_{12}H_{10}$	Biphenyl	68.93	18.57
$C_{12}H_{10}N_2$	Azobenzene	67.88	22.52
$C_{12}H_{10}N_2O$	*trans*–Azoxybenzene	34.6	17.9
$C_{12}H_{10}O$	Diphenyl ether	26.87	17.22
$C_{12}H_{11}N$	Diphenylamine	53.2	18.5
$C_{12}H_{16}$	Cyclohexylbenzene	7.07	15.6
$C_{12}H_{18}$	Hexamethylbenzene	165.5	20.6
$C_{12}H_{24}$	1–Dodecene	–35.2	19.9
$C_{12}H_{24}O_2$	Dodecanoic acid	43.8	36.3
$C_{12}H_{26}$	Dodecane	–9.57	36.8
$C_{12}H_{26}O$	1–Dodecanol	23.9	40.2
$C_{13}H_{10}$	9*H*–Fluorene	114.77	19.58
$C_{13}H_{10}O$	Benzophenone	47.9	18.19
$C_{13}H_{12}$	Diphenylmethane	25.4	18.6
$C_{13}H_{28}$	Tridecane	–5.4	28.50
$C_{13}H_{28}O$	1–Tridecanol	31.7	41.4
$C_{14}H_{10}$	Anthracene	215.76	29.4
$C_{14}H_{10}$	Phenanthrene	99.24	16.46
$C_{14}H_{10}O_2$	Benzil	94.87	23.5
$C_{14}H_{12}$	*trans*–Stilbene	124.2	27.7
$C_{14}H_{12}O_2$	α–Phenylbenzeneacetic acid	147.29	31.3
$C_{14}H_{28}O_2$	Tetradecanoic acid	54.2	45.1
$C_{14}H_{30}$	Tetradecane	5.82	45.07
$C_{14}H_{30}O$	1–Tetradecanol	38.2	25.1*
$C_{15}H_{32}$	Pentadecane	9.95	34.6
$C_{16}H_{10}$	Fluoranthene	110.19	18.69
$C_{16}H_{10}$	Pyrene	150.62	17.36
$C_{16}H_{32}O_2$	Hexadecanoic acid	62.5	53.7
$C_{16}H_{34}$	Hexadecane	18.12	53.36
$C_{16}H_{34}O$	1–Hexadecanol	49.2	33.6
$C_{17}H_{36}$	Heptadecane	22.0	40.16
$C_{18}H_{12}$	Benz[a]anthracene	160.5	21.4
$C_{18}H_{12}$	Benzo[c]phenanthrene	68	16.3
$C_{18}H_{12}$	Chrysene	255.5	26.2
$C_{18}H_{12}$	Triphenylene	197.8	24.74

Molecular formula	Name	t_m/°C	$\Delta_{fus}H$/ kJ mol^{-1}	Molecular formula	Name	t_m/°C	$\Delta_{fus}H$/ kJ mol^{-1}
$C_{18}H_{14}$	*o*–Terphenyl	56.20	17.19	$C_{20}H_{12}$	Perylene	277.76	31.9
$C_{18}H_{14}$	*p*–Terphenyl	213.9	35.3	$C_{20}H_{12}$	Benzo[a]pyrene	181.1	17.3
$C_{18}H_{15}N$	Triphenylamine	126.5	24.9	$C_{20}H_{12}$	Benzo[e]pyrene	181.4	16.6
$C_{18}H_{36}O_2$	Stearic acid	69.3	61.2	$C_{20}H_{14}$	2,2´–Binaphthalene	187.9	38.9
$C_{18}H_{38}$	Octadecane	28.2	61.7	$C_{20}H_{42}$	Eicosane	36.6	69.9
$C_{18}H_{38}O$	1–Octadecanol	57.9	45	$C_{20}H_{42}O$	1–Eicosanol	65.4	42
$C_{19}H_{40}$	Nonadecane	32.0	45.8	$C_{24}H_{12}$	Coronene	437.4	19.2

PRESSURE AND TEMPERATURE DEPENDENCE OF LIQUID DENSITY

This table gives data on the variation of the density of some common liquids with pressure and temperature. The pressure dependence is described to first order by the isothermal compressibility coefficient κ defined as

$$\kappa = -(1/V)\,(\partial V/\partial P)_T$$

where V is the volume, and the temperature dependence by the cubic expansion coefficient α,

$$\alpha = (1/V)\,(\partial V/\partial T)_p$$

Substances are listed by molecular formula in the Hill order. More precise data on the variation of density with temperature over a wide temperature range can be found in Reference 1.

References

1. Lide, D. R., and Kehiaian, H. V., *CRC Handbook of Thermophysical and Thermochemical Data*, CRC Press, Boca Raton, FL, 1994.
2. Le Neindre, B., *Effets des Hautes et Très Hautes Pressions*, in *Techniques de l'Ingénieur*, Paris, 1991.
3. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series*, IV/4, *High-Pressure Properties of Matter*, Springer–Verlag, Heidelberg, 1980.
4. Riddick, J.A., Bunger, W.B., and Sakano, T.K., *Organic Solvents, Fourth Edition*, John Wiley & Sons, New York, 1986.
5. Isaacs, N. S., *Liquid Phase High Pressure Chemistry*, John Wiley, New York, 1981.

Molecular formula	Name	Isothermal compressibility		Cubic thermal expansion	
		t/°C	$\kappa \times 10^4$/MPa^{-1}	t/°C	$\alpha \times 10^3$/°C^{-1}
Cl_3P	Phosphorus trichloride	20	9.45	20	1.9
H_2O	Water	20	4.591	20	0.206
		25	4.524	25	0.256
		30	4.475	30	0.302
Hg	Mercury	20	0.401	20	1.811
CCl_4	Tetrachloromethane	20	10.50	20	1.14
		40	12.20	40	1.21
		70	15.6	70	1.33
$CHBr_3$	Tribromomethane	50	8.76	25	0.91
$CHCl_3$	Trichloromethane	20	9.96	20	1.21
		50	12.9	50	1.33
CH_2Br_2	Dibromomethane	27	6.85		
CH_2Cl_2	Dichloromethane	25	10.3	25	1.39
CH_3I	Iodomethane	27	10.3	25	1.26
CH_4O	Methanol	20	12.14	20	1.49
		40	13.83	40	1.59
CS_2	Carbon disulfide	20	9.38	20	1.12
		40	10.6	35	1.16
C_2Cl_4	Tetrachloroethylene	25	7.56	25	1.02
C_2HCl_3	Trichloroethylene	25	8.57	25	1.17
$C_2H_2Cl_2$	*trans*-1,2-Dichloroethylene	25	11.2	25	1.36
$C_2H_4Cl_2$	1,1-Dichloroethane	20	7.97	25	0.93
$C_2H_4Cl_2$	1,2-Dichloroethane	30	8.46	20	1.14
$C_2H_4O_2$	Acetic acid	20	9.08	20	1.08
		80	13.7	80	1.38
C_2H_5Br	Bromoethane	20	11.53	20	1.31
C_2H_5I	Iodoethane	20	9.82	25	1.17
C_2H_6O	Ethanol	20	11.19	20	1.40
		70	15.93	70	1.67
$C_2H_6O_2$	Ethylene glycol	20	3.64	20	0.626
C_3H_6O	Acetone	20	12.62	20	1.46
		40	15.6	40	1.57
C_3H_7Br	1-Bromopropane	0	10.22	25	1.2
C_3H_7Cl	1-Chloropropane	0	12.09	20	1.4
C_3H_7I	1-Iodopropane	0	10.22	25	1.09
C_3H_8O	1-Propanol	0	8.43	0	1.22
C_3H_8O	2-Propanol	40	13.32	40	1.55
$C_3H_8O_2$	1,2-Propanediol	0	4.45	20	0.695
$C_3H_8O_2$	1,3-Propanediol	0	4.09	20	0.61
$C_3H_8O_3$	Glycerol	0	2.54	20	0.520
$C_4H_8O_2$	Ethyl acetate	20	11.32	20	1.35
		60	16.2	60	1.54

Molecular formula	Name	Isothermal compressibility		Cubic thermal expansion	
		t/°C	$\kappa \times 10^4$/MPa^{-1}	t/°C	$\alpha \times 10^3$/°C^{-1}
C_4H_9Br	1-Bromobutane	25	10.26	20	1.13
C_4H_9I	1-Iodobutane	0	7.73	25	1.02
$C_4H_{10}O$	1-Butanol	0	8.10	0	1.12
$C_4H_{10}O$	Diethyl ether	20	18.65	20	1.65
		30	20.85	30	1.72
$C_4H_{10}O_3$	Diethylene glycol	0	3.34	20	0.635
C_5H_{10}	Cyclopentane	20	13.31	20	1.35
$C_5H_{11}Br$	1-Bromopentane	0	8.42	25	1.04
$C_5H_{11}I$	1-Iodopentane	0	7.56		
C_5H_{12}	Pentane	25	21.80	25	1.64
$C_5H_{12}O$	1-Pentanol	0	7.71	0	1.02
C_6H_5Br	Bromobenzene	20	6.46	20	0.86
C_6H_5Cl	Chlorobenzene	20	7.45	20	0.94
$C_6H_5NO_2$	Nitrobenzene	20	4.93	25	0.833
C_6H_6	Benzene	25	9.66	25	1.14
		45	11.28	45	1.21
C_6H_6O	Phenol	60	6.05	60	0.82
C_6H_7N	Aniline	20	4.53	20	0.81
		80	6.32	80	0.91
C_6H_{12}	Cyclohexane	20	11.30	20	1.15
		60	15.2	60	1.29
C_6H_{14}	Hexane	25	16.69	25	1.41
		45	20.27	45	1.52
C_6H_{14}	2-Methylpentane	0	13.97	25	1.43
C_6H_{14}	3-Methylpentane	0	14.57	25	1.40
C_6H_{14}	2,3-Dimethylbutane	20	17.97	25	1.39
$C_6H_{14}O$	1-Hexanol	25	8.24	25	1.03
$C_6H_{15}NO_3$	Triethanolamine	0	3.61	55	0.53
C_7H_8	Toluene	20	8.96	20	1.05
		50	11.0	50	1.13
C_7H_8O	Anisole	20	6.60	20	0.951
C_7H_{14}	Cycloheptane	20	9.22		
C_7H_{16}	Heptane	25	14.38	25	1.26
C_8H_{10}	*o*-Xylene	25	8.10	25	0.96
C_8H_{10}	*m*-Xylene	20	8.46	20	0.99
C_8H_{10}	*p*-Xylene	25	8.59	25	1.00
C_8H_{16}	Cyclooctane	20	8.03		
C_8H_{18}	Octane	25	12.82	25	1.16
		45	15.06	45	1.23
$C_8H_{18}O$	1-Octanol	25	7.64	25	0.827
C_9H_{12}	Mesitylene	25	8.14	25	0.94
$C_9H_{14}O_6$	Triacetin	0	4.49	25	0.94
C_9H_{20}	Nonane	25	11.75	25	1.08
$C_{10}H_{22}$	Decane	25	10.94	25	1.02
$C_{11}H_{24}$	Undecane	25	10.31	25	0.97
$C_{12}H_{26}$	Dodecane	25	9.88	25	0.93
$C_{13}H_{28}$	Tridecane	25	9.48	25	0.90
$C_{14}H_{30}$	Tetradecane	25	9.10	25	0.87
$C_{15}H_{32}$	Pentadecane	25	8.82		
$C_{16}H_{22}O_4$	Butyl phthalate	0	5.0	25	0.86
$C_{16}H_{34}$	Hexadecane	25	8.57		
		45	9.78		
$C_{19}H_{36}O_2$	Methyl oleate	0	6.18	60	0.85

PROPERTIES OF CRYOGENIC FLUIDS

This table gives physical and thermodynamic properties of eight cryogenic fluids. The properties are:

M	Molar mass in grams per mole
T_t	Triple point temperature in kelvins
P_t	Triple point pressure in kilopascals
ρ_t (l)	Liquid density at the triple point in grams per milliliter
$\Delta_{fus}H$ @ T_t	Enthalpy of fusion at the triple point in joules per gram
T_b	Normal boiling point in kelvins at a pressure of 101325 pascals (760 mmHg)
$\Delta_{vap}H$ @ T_b	Enthalpy of vaporization at the normal boiling point in joules per gram
ρ (l) @ T_b	Liquid density at the normal boiling point in grams per milliliter
ρ (g) @ T_b	Vapor density at the normal boiling point in grams per liter
C_p (l) @ T_b	Liquid heat capacity at constant pressure at the normal boiling point in joules per gram kelvin
C_p (g) @ T_b	Vapor heat capacity at constant pressure at the normal boiling point in joules per gram kelvin
T_c	Critical temperature in kelvins
P_c	Critical pressure in megapascals
ρ_c	Critical density in grams per milliliter

In the case of air, the value given for the triple point temperature is the incipient solidification temperature, and the normal boiling point value is the incipient boiling (bubble) point. See Reference 3 for more details.

References

1. Younglove, B. A., *J. Phys. Chem. Ref. Data*, 11, Suppl. 1, 1982.
2. Daubert, T. E., Danner, R. P., Sibul, H. M., and Stebbins, C. C., *Physical and Thermodynamic Properties of Pure Compounds: Data Compilation*, extant 1994 (core with 4 supplements), Taylor & Francis, Bristol, PA (also available as database).
3. Sytchev, V. V., et al., *Thermodynamic Properties of Air*, Hemisphere Publishing, New York, 1987.
4. Jacobsen, R. T., Stewart, R. B., and Jahangiri, M., *J. Phys. Chem. Ref. Data*, 15, 735, 1986. [Nitrogen]
5. Stewart, R. B., Jacobsen, R. T., and Wagner, W., *J. Phys. Chem. Ref. Data*, 20, 917, 1991. [Oxygen]
6. McCarty, R. D., *J. Phys. Chem. Ref. Data*, 2, 923, 1973. [Helium] Also, Donnelly, R. J., private communication.
7. Stewart, R. B. and Jacobsen, R. T., *J. Phys. Chem. Ref. Data*, 18, 639, 1989. [Argon]
8. Setzmann, U. and Wagner, W., *J. Phys. Chem. Ref. Data*, 20, 1061, 1991. [Methane]
9. Vargaftik, N. B., *Thermophysical Properties of Liquids and Gases*, 2nd ed., John Wiley, New York, 1975.

Property	Units	Air	N_2	O_2	H_2	He	Ne	Ar	Kr	Xe	CH_4
M	g/mol	28.96	28.014	31.999	2.0159	4.0026	20.180	39.948	83.800	131.290	16.043
T_t	K	59.75	63.15	54.3584	13.8		24.5561	83.8058	115.8	161.4	90.694
P_t	kPa		12.463	0.14633	7.042		50	68.95	72.92	81.59	11.696
ρ_t(l)	g/mL	0.959	0.870	1.306	0.0770		1.251	1.417	2.449	2.978	0.4515
$\Delta_{fus}H$ @ T_t	J/g		25.3	13.7	59.5		16.8	28.0	16.3	13.8	58.41
T_b	K	78.67	77.35	90.188	20.28	4.2221	27.07	87.293	119.92	165.10	111.668
$\Delta_{vap}H$ @ T_b	J/g	198.7	198.8	213.1	445	20.7	84.8	161.0	108.4	96.1	510.83
ρ (l) @ T_b	g/mL	0.8754	0.807	1.141	0.0708	0.124901	1.204	1.396	2.418	2.953	0.4224
ρ (g) @ T_b	g/L	3.199	4.622	4.467	1.3390	16.89	9.51	5.79	8.94		1.816
C_p (l) @ T_b	J/g K	1.865	2.042	1.699	9.668	4.545	1.877	1.078	0.533	0.340	3.481
C_p (g) @ T_b	J/g K		1.341	0.980	12.24	9.78		0.570	0.248	0.158	2.218
T_c	K	132.5	126.20	154.581	32.98	5.1953	44.40	150.663	209.40	289.73	190.56
P_c	MPa	3.766	3.390	5.043	1.293	0.227460	2.760	4.860	5.500	5.840	4.592
ρ_c	g/mL	0.316	0.313	0.436	0.031	0.06964	0.484	0.531	0.919	1.110	0.1627

PROPERTIES OF REFRIGERANTS

This table gives physical properties of compounds that have been used as working fluids in traditional refrigeration systems or are under consideration as replacements in newer systems. Some are also used as solvents and blowing agents. Many of the compounds listed are believed to be less harmful to the environment than the traditional halocarbons refrigerants.

Compounds are listed by their ASHRAE standard refrigerant designations (Reference 1), which appear in the first column. These codes are often prefixed by symbols such as CFC– (for chlorofluorocarbon), HCFC– (for hydrochlorofluorocarbon), or simply R– (for refrigerant). The molecular formula and CAS Registry Number are also given. The properties tabulated are:

t_m normal melting point in °C
t_b normal boiling point in °C (at 101.325 kPa or 760 mmHg)
t_c critical temperature in °C
TLV Threshold Limit Value, which is the maximum safe concentration in air in the workplace, expressed as the time–weighted average (TWA) in parts per million by volume over an 8–hr workday and 40–hr workweek. A value followed by C is an absolute ceiling limit.

References

1. *ASHRAE Standard 34–1997*, Number Designation and Safety Classification of Refrigerants.
2. *ASHRAE Fundamentals Handbook 2001*, Chapter 19. Refrigerants, American Society of Heating, Refrigerating, and Air-Conditioning Engineers, Atlanta, GA, 2001.
3. Platzer, B., Polt, A., and Mauer, G., *Thermophysical Properties of Refrigerants*, Springer, Berlin, 1990.
4. Sako, T., Sato, M., Nakazawa, N., Oowa, M., Yasumoto, M., Ito, H., and Yamashita, S., *J. Chem. Eng. Data,* 41, 802, 1996.
5. Schmidt, J. W., Carrillo-Nava, E., and Moldover, M. R., *Fluid Phase Equilibria*, 122, 187, 1996.
6. Salvi–Narkhede, M., Wang, B.-H., Adcock, J. L., and Van Hook, W. A., *J. Chem. Thermodynamics,* 24, 1065, 1992.
7. Fialho, P. S., and Nieto de Castro, C. A., *Int. J. Thermophys.,* 21, 385, 2000.
8. Daubert, T. E., Danner, R. P., Sibul, H. M., and Stebbins, C. C., *Physical and Thermodynamic Properties of Pure Compounds: Data Compilation*, extant 2002 (core with supplements), Taylor & Francis, Bristol, PA.

Further references and additional data on the critical properties may be found in the table "Critical Constants" in this section.

Code	Name	Molecular formula	CAS Reg. No.	t_m/°C	t_b/°C	t_c/°C	TLV
10	Tetrachloromethane	CCl_4	56–23–5	–22.62	76.8	283.4	5
11	Trichlorofluoromethane	CCl_3F	75–69–4	–110.44	23.7	197.9	1000C
12	Dichlorodifluoromethane	CCl_2F_2	75–71–8	–158	–29.8	111.80	1000
12B1	Bromochlorodifluoromethane	$CBrClF_2$	353–59–3	–159.5	–3.7	153.73	
12B2	Dibromodifluoromethane	CBr_2F_2	75–61–6	–110.1	22.76	198.1	100
13	Chlorotrifluoromethane	$CClF_3$	75–72–9	–181	–81.4	29	
13B1	Bromotrifluoromethane	$CBrF_3$	75–63–8	–172	–57.8	67.0	1000
14	Tetrafluoromethane	CF_4	75–73–0	–183.60	–128.0	–45.5	
20	Trichloromethane	$CHCl_3$	67–66–3	–63.41	61.17	263.2	10
21	Dichlorofluoromethane	$CHCl_2F$	75–43–4	–135	8.9	178.43	10
22	Chlorodifluoromethane	$CHClF_2$	75–45–6	–157.42	–40.7	96.3	1000
22B1	Bromodifluoromethane	$CHBrF_2$	1511–62–2	–145	–14.6	138.83	
23	Trifluoromethane	CHF_3	75–46–7	–155.2	–82.1	25.83	
30	Dichloromethane	CH_2Cl_2	75–09–2	–97.2	40	237	50
31	Chlorofluoromethane	CH_2ClF	593–70–4	–135.1	–9.1	154	
32	Difluoromethane	CH_2F_2	75–10–5	–136.8	–51.6	78.41	
40	Chloromethane	CH_3Cl	74–87–3	–97.7	–24.09	143.10	50
41	Fluoromethane	CH_3F	593–53–3	–141.8	–78.4	44.6	
50	Methane	CH_4	74–82–8	–182.47	–161.48	–82.59	1000
110	Hexachloroethane	C_2Cl_6	67–72–1	186.8	184.7 sp	422	1
111	Pentachlorofluoroethane	C_2Cl_5F	354–56–3	101.3	138		
112	1,1,2,2-Tetrachloro-1,2-difluoroethane	$C_2Cl_4F_2$	76–12–0	24.8	92.8	278	500
112a	1,1,1,2-Tetrachloro-2,2-difluoroethane	$C_2Cl_4F_2$	76–11–9	41.0	92.8		500
113	1,1,2-Trichloro-1,2,2-trifluoroethane	$C_2Cl_3F_3$	76–13–1	–36.22	47.7	214.1	1000
113a	1,1,1-Trichloro-2,2,2-trifluoroethane	$C_2Cl_3F_3$	354–58–5	14.37	45.5	209.7	
114	1,2-Dichloro-1,1,2,2-tetrafluoroethane	$C_2Cl_2F_4$	76–14–2	–92.53	3.5	145.63	1000
114a	1,1-Dichloro-1,2,2,2-tetrafluoroethane	$C_2Cl_2F_4$	374–07–2	–56.6	3.4	145.4	
114B2	1,2-Dibromotetrafluoroethane	$C_2Br_2F_4$	124–73–2	–110.32	47.35	214.6	
115	Chloropentafluoroethane	C_2ClF_5	76–15–3	–99.4	–39.1	80.0	1000
116	Hexafluoroethane	C_2F_6	76–16–4	–100.05	–78.1	20	
120	Pentachloroethane	C_2HCl_5	76–01–7	–28.78	162.0		
121	1,1,2,2-Tetrachloro-1-fluoroethane	C_2HCl_4F	354–14–3	–82.6	116.7		
121a	1,1,1,2-Tetrachloro-2-fluoroethane	C_2HCl_4F	354–11–0	–95.3	117.1		
122	1,2,2-Trichloro-1,1-difluoroethane	$C_2HCl_3F_2$	354–21–2	–140	71.9		

Code	Name	Molecular formula	CAS Reg. No.	t_m/°C	t_b/°C	t_c/°C	TLV
122a	1,2,2-Trichloro-1,2-difluoroethane	$C_2HCl_3F_2$	354–15–4	–174	72.5		
122b	1,1,1-Trichloro-2,2-difluoroethane	$C_2HCl_3F_2$	354–12–1		73		
123	2,2-Dichloro-1,1,1-trifluoroethane	$C_2HCl_2F_3$	306–83–2	–107	27.82	183.68	
123a	1,2-Dichloro-1,1,2-trifluoroethane	$C_2HCl_2F_3$	354–23–4	–78	29.5	188.4	
124	1-Chloro-1,2,2,2-tetrafluoroethane	C_2HClF_4	2837–89–0		–12	122.50	
124a	1-Chloro-1,1,2,2-tetrafluoroethane	C_2HClF_4	354–25–6	–117	–11.7	126.7	
125	Pentafluoroethane	C_2HF_5	354–33–6	–103	–48.1	66.02	
E125	Trifluoromethyl difluoromethyl ether	C_2HF_5O	3822–68–2	–157	–38	80.8	
130	1,1,2,2-Tetrachloroethane	$C_2H_2Cl_4$	79–34–5	–42.4	145.2	388.00	1
131	1,1,2-Trichloro-2-fluoroethane	$C_2H_2Cl_3F$	359–28–4		102.4		
132	1,2-Dichloro-1,2-difluoroethane	$C_2H_2Cl_2F_2$	431–06–1	–101.2	59.6		
132b	1,2-Dichloro-1,1-difluoroethane	$C_2H_2Cl_2F_2$	1649–08–7	–101.2	46.2		
133	1-Chloro-1,2,2-trifluoroethane	$C_2H_2ClF_3$	431–07–2		17.3		
133a	2-Chloro-1,1,1-trifluoroethane	$C_2H_2ClF_3$	75–88–7	–105.5	6.1	151.86	
133b	1-Chloro-1,1,2-trifluoroethane	$C_2H_2ClF_3$	421–04–5		12		
134	1,1,2,2-Tetrafluoroethane	$C_2H_2F_4$	359–35–3	–89	–19.9	118.59	
134a	1,1,1,2-Tetrafluoroethane	$C_2H_2F_4$	811–97–2	–103.3	–26.08	101.03	
E134	Bis(difluoromethyl) ether	$C_2H_2F_4O$	1691–17–4		2	147.10	
140	1,1,2-Trichloroethane	$C_2H_3Cl_3$	79–00–5	–36.3	113.8	329	10
140a	1,1,1-Trichloroethane	$C_2H_3Cl_3$	71–55–6	–30.01	74.09	272	350
141	1,2-Dichloro-1-fluoroethane	$C_2H_3Cl_2F$	430–57–9	–60	73.8		
141b	1,1-Dichloro-1-fluoroethane	$C_2H_3Cl_2F$	1717–00–6	–103.5	32.0	204.1	
142	1-Chloro-2,2-difluoroethane	$C_2H_3ClF_2$	338–65–8		35.1		
142b	1-Chloro-1,1-difluoroethane	$C_2H_3ClF_2$	75–68–3	–130.8	–9.1	137.19	
143	1,1,2-Trifluoroethane	$C_2H_3F_3$	430–66–0	–84	3.7	156.6	
143a	1,1,1-Trifluoroethane	$C_2H_3F_3$	420–46–2	–111.3	–47.25	72.71	
143m	Methyl trifluoromethyl ether	$C_2H_3F_3O$	421–14–7	–149	–23.66	104.87	
E143a	2,2,2-Trifluoroethyl methyl ether	$C_3H_5F_3O$	460–43–5		31.62	175.83	
150	1,2-Dichloroethane	$C_2H_4Cl_2$	107–06–2	–35.7	83.5	288	10
150a	1,1-Dichloroethane	$C_2H_4Cl_2$	75–34–3	–96.9	57.3	250	100
151	1-Chloro-2-fluoroethane	C_2H_4ClF	762–50–5		52.8		
151a	1-Chloro-1-fluoroethane	C_2H_4ClF	1615–75–4		16.2		
152	1,2-Difluoroethane	$C_2H_4F_2$	624–72–6		26		
152a	1,1-Difluoroethane	$C_2H_4F_2$	75–37–6	–117	–24.05	113.5	
160	Chloroethane	C_2H_5Cl	75–00–3	–138.4	12.3	187.2	100
161	Fluoroethane	C_2H_5F	353–36–6	–143.2	–37.7	102.16	
170	Ethane	C_2H_6	74–84–0	–182.79	–88.6	32.17	1000
216ca	1,3-Dichloro-1,1,2,2,3,3-hexafluoropropane	$C_3Cl_2F_6$	662–01–1	–125.4	35.7	180	
218	Perfluoropropane	C_3F_8	76–19–7	–147.70	–36.6	71.9	
227ca2	Trifluoromethyl 1,1,2,2-tetrafluoroethyl ether	C_3HF_7O	2356–61–8	–141	–3	114.63	
227ea	1,1,1,2,3,3,3-Heptafluoropropane	C_3HF_7	431–89–0	–131	–16.4	101.74	
227me	Trifluoromethyl 1,2,2,2-tetrafluoroethyl ether	C_3HF_7O	2356–62–9		–9.6		
236ea	1,1,1,2,3,3-Hexafluoropropane	$C_3H_2F_6$	431–63–0		6.1	139.23	
236fa	1,1,1,3,3,3-Hexafluoropropane	$C_3H_2F_6$	690–39–1	–93.6	–1.0	124.92	
236me	1,2,2,2-Tetrafluoroethyl difluoromethyl ether	$C_3H_2F_6O$	57041–67–5		23.35	155.80	
245ca	1,1,2,2,3-Pentafluoropropane	$C_3H_3F_5$	679–86–7		25.0	174.42	
245cb	1,1,1,2,2-Pentafluoropropane	$C_3H_3F_5$	1814–88–6		–17.4	106.96	
245fa	1,1,1,3,3-Pentafluoropropane	$C_3H_3F_5$	460–73–1		15.3	154.05	
245mc	Methyl pentafluoroethyl ether	$C_3H_3F_5O$	22410–44–2		5.59	133.65	
245mf	Difluoromethyl 2,2,2-trifluoroethyl ether	$C_3H_3F_5O$	1885–48–9		29.24	170.84	
245qc	Difluoromethyl 1,1,2-trifluoroethyl ether	$C_3H_3F_5O$	69948–24–9		43.1		
254pc	Methyl 1,1,2,2-tetrafluoroethyl ether	$C_3H_4F_4O$	425–88–7	–107	37.1		
290	Propane	C_3H_8	74–98–6	–187.63	–42.1	96.68	1000
C316	1,2-Dichloro-1,2,3,3,4,4-hexafluorocyclobutane	$C_4Cl_2F_6$	356–18–3	–24.2	59.5	224	
C317	1-Chloro-1,2,2,3,3,4,4-heptafluorocyclobutane	C_4ClF_7	377–41–3	–39.1	25		
C318	Perfluorocyclobutane	C_4F_8	115–25–3	–40.19	–5.9	115.31	
347mcc	Perfluoropropyl methyl ether	$C_4H_3F_7O$	375–03–1		34.23	164.55	
347mmy	Perfluoroisopropyl methyl ether	$C_4H_3F_7O$	22052–84–2		29.34	160.15	
600	Butane	C_4H_{10}	106–97–8	–138.3	–0.5	151.97	1000
600a	Isobutane	C_4H_{10}	75–28–5	–159.4	–11.73	134.6	1000

Code	Name	Molecular formula	CAS Reg. No.	t_m/°C	t_b/°C	t_c/°C	TLV
610	Diethyl ether	$C_4H_{10}O$	60–29–7	–116.2	34.5	193.5	400
611	Methyl formate	$C_2H_4O_2$	107–31–3	–99	31.7	214.0	100
717	Ammonia	H_3N	7664–41–7	–77.73	–33.33	132.3	25
744	Carbon dioxide	CO_2	124–38–9	–56.56	–78.5 sp	30.98	5000
764	Sulfur dioxide	O_2S	7446–09–5	–75.5	–10.05	157.6	2
1112a	1,1-Dichloro-2,2-difluoroethene	$C_2Cl_2F_2$	79–35–6	–116	19		
1113	Chlorotrifluoroethene	C_2ClF_3	79–38–9	–158.2	–27.8	106	
1114	Tetrafluoroethene	C_2F_4	116–14–3	–131.15	–75.9	33.3	2
1120	Trichloroethene	C_2HCl_3	79–01–6	–84.7	87.21	271.0	50
1130	*trans*-1,2-Dichloroethene	$C_2H_2Cl_2$	156–60–5	–49.8	48.7	243.3	200
1132a	1,1-Difluoroethene	$C_2H_2F_2$	75–38–7	–144	–85.7	29.7	500
1140	Chloroethene	C_2H_3Cl	75–01–4	–153.84	–13.8	159	
1141	Fluoroethene	C_2H_3F	75–02–5	–160.5	–72	54.7	1
1150	Ethylene	C_2H_4	74–85–1	–169.15	–103.77	9.19	
1270	Propene	C_3H_6	115–07–1	–185.24	–47.69	91.7	

DENSITY AND SPECIFIC VOLUME OF MERCURY

The data in this table have been adjusted to the ITS–90 temperature scale. The uncertainty in density values is 0.0003 g/mL between –20 and –10°C; 0.0001 or less between –10 and 200°C; and 0.0002 between 200 and 300°C.

Reference

Ambrose, D., *Metrologia*, 27, 245, 1990.

t/°C	ρ/(g/mL)	*v*/(mL/kg)	*t*/°C	ρ/(g/mL)	*v*/(mL/kg)	*t*/°C	ρ/(g/mL)	*v*/(mL/kg)
–20	13.64461	73.2890	30	13.52134	73.9572	80	13.39971	74.6285
–19	13.64212	73.3024	31	13.51889	73.9705	81	13.39729	74.6420
–18	13.63964	73.3157	32	13.51645	73.9839	82	13.39487	74.6554
–17	13.63716	73.3291	33	13.51400	73.9973	83	13.39245	74.6689
–16	13.63468	73.3424	34	13.51156	74.0107	84	13.39003	74.6824
–15	13.63220	73.3558	35	13.50911	74.0241	85	13.38762	74.6959
–14	13.62972	73.3691	36	13.50667	74.0375	86	13.38520	74.7094
–13	13.62724	73.3824	37	13.50422	74.0509	87	13.38278	74.7229
–12	13.62476	73.3958	38	13.50178	74.0643	88	13.38037	74.7364
–11	13.62228	73.4091	39	13.49934	74.0777	89	13.37795	74.7498
–10	13.61981	73.4225	40	13.49690	74.0911	90	13.37554	74.7633
–9	13.61733	73.4358	41	13.49446	74.1045	91	13.37313	74.7768
–8	13.61485	73.4492	42	13.49202	74.1179	92	13.37071	74.7903
–7	13.61238	73.4625	43	13.48958	74.1313	93	13.36830	74.8038
–6	13.60991	73.4759	44	13.48714	74.1447	94	13.36589	74.8173
–5	13.60743	73.4892	45	13.48470	74.1581	95	13.36347	74.8308
–4	13.60496	73.5026	46	13.48226	74.1715	96	13.36106	74.8443
–3	13.60249	73.5160	47	13.47982	74.1850	97	13.35865	74.8579
–2	13.60002	73.5293	48	13.47739	74.1984	98	13.35624	74.8714
–1	13.59755	73.5427	49	13.47495	74.2118	99	13.35383	74.8849
0	13.59508	73.5560	50	13.47251	74.2252	100	13.35142	74.8984
1	13.59261	73.5694	51	13.47008	74.2386	110	13.3273	75.0337
2	13.59014	73.5827	52	13.46765	74.2520	120	13.3033	75.1693
3	13.58768	73.5961	53	13.46521	74.2655	130	13.2793	75.3052
4	13.58521	73.6095	54	13.46278	74.2789	140	13.2553	75.4413
5	13.58275	73.6228	55	13.46035	74.2923	150	13.2314	75.5778
6	13.58028	73.6362	56	13.45791	74.3057	160	13.2075	75.7147
7	13.57782	73.6495	57	13.45548	74.3192	170	13.1836	75.8519
8	13.57535	73.6629	58	13.45305	74.3326	180	13.1597	75.9895
9	13.57289	73.6763	59	13.45062	74.3460	190	13.1359	76.1274
10	13.57043	73.6896	60	13.44819	74.3594	200	13.1120	76.2659
11	13.56797	73.7030	61	13.44576	74.3729	210	13.0882	76.4047
12	13.56551	73.7164	62	13.44333	74.3863	220	13.0644	76.5440
13	13.56305	73.7297	63	13.44090	74.3998	230	13.0406	76.6838
14	13.56059	73.7431	64	13.43848	74.4132	240	13.0167	76.8241
15	13.55813	73.7565	65	13.43605	74.4266	250	12.9929	76.9650
16	13.55567	73.7698	66	13.43362	74.4401	260	12.9691	77.1064
17	13.55322	73.7832	67	13.43120	74.4535	270	12.9453	77.2484
18	13.55076	73.7966	68	13.42877	74.4670	280	12.9214	77.3909
19	13.54831	73.8100	69	13.42635	74.4804	290	12.8975	77.5341
20	13.54585	73.8233	70	13.42392	74.4939	300	12.8736	77.6779
21	13.54340	73.8367	71	13.42150	74.5073			
22	13.54094	73.8501	72	13.41908	74.5208			
23	13.53849	73.8635	73	13.41665	74.5342			
24	13.53604	73.8769	74	13.41423	74.5477			
25	13.53359	73.8902	75	13.41181	74.5612			
26	13.53114	73.9036	76	13.40939	74.5746			
27	13.52869	73.9170	77	13.40697	74.5881			
28	13.52624	73.9304	78	13.40455	74.6016			
29	13.52379	73.9438	79	13.40213	74.6150			

THERMAL PROPERTIES OF MERCURY

Lev R. Fokin

The first of these tables gives the molar heat capacity at constant pressure of liquid and gaseous mercury as a function of temperature. To convert to specific heat in units of J/g K, divide these values by 200.59, the atomic weight of mercury.

Reference

Douglas, T. B., Ball, A. T., and Ginnings, D. C., *J. Res. Natl. Bur. Stands.*, 46, 334, 1951.

	C_p/(J/mol K)			C_p/(J/mol K)			C_p/(J/mol K)	
t/°C	Liquid	Gas	*t*/°C	Liquid	Gas	*t*/°C	Liquid	Gas
−38.84	28.2746	20.786	140	27.3675	20.786	340	27.1500	20.836
−20	28.1466	20.786	160	27.3090	20.786	356.73	27.1677	20.849
0	28.0190	20.786	180	27.2588	20.790	360	27.1709	20.853
20	27.9002	20.786	200	27.2169	20.790	380	27.1981	20.870
25	27.8717	20.786	220	27.1834	20.794	400	27.2324	20.891
40	27.7897	20.786	240	27.1583	20.794	420	27.2738	20.916
60	27.6880	20.786	260	27.1412	20.799	440	27.3207	20.941
80	27.5952	20.786	280	27.1320	20.807	460	27.3742	20.974
100	27.5106	20.786	300	27.1303	20.815	480	27.4332	21.008
120	27.4349	20.786	320	27.1366	20.824	500	27.4985	21.046

The second table gives the molar heat capacity of solid mercury in its rhombohedral (α–mercury) form.

References

1. Busey and Giaque, *J. Am. Chem. Soc.*, 75, 806, 1953.
2. Amitin, Lebedeva, and Paukov, *Rus. J. Phys. Chem.*, 2666, 1979.

t/°C	C_p/(J/mol K)	*t*/°C	C_p/(J/mol K)	*t*/°C	C_p/(J/mol K)	*t*/°C	C_p/(J/mol K)
−268.99	0.99*	−248.15	12.74	−193.15	23.16	−93.15	26.69
−268.99	0.97**	−243.15	14.78	−183.15	23.76	−73.15	27.28
−268.15	1.6	−233.15	17.90	−173.15	24.24	−53.15	27.96
−263.15	4.6	−223.15	19.94	−153.15	25.00	−38.87	28.5
−258.15	7.6	−213.15	21.40	−133.15	25.61	* Superconducting state	
−253.15	10.33	−203.15	22.42	−113.15	26.15	**Normal state	

The final table gives the cubic thermal expansion coefficient α, the isothermal compressibility coefficient κ_T, and the speed of sound U for liquid mercury as a function of temperature. These properties are defined as follows:

$$\alpha = \frac{1}{v}\left(\frac{\partial v}{\partial T}\right)_p \qquad \kappa_T = -\frac{1}{v}\left(\frac{\partial v}{\partial P}\right)_T \qquad U^2 = \left(\frac{\partial P}{\partial \rho}\right)_s \qquad \rho = v^{-1}$$

where v is the specific volume (given in the table on the preceding page).

Reference

Vukalovich, M. P., et al., *Thermophysical Properties of Mercury*, Moscow Standard Press, 1971.

		$\kappa_T \times 10^6$/bar^{-1}				$\kappa_T \times 10^6$/bar^{-1}		
t/°C	$\alpha \times 10^4$/K^{-1}	At 1 bar	At 1000 bar	U/m s^{-1}	*t*/°C	$\alpha \times 10^4$/K^{-1}	At 1 bar	At 1000 bar	U/m s^{-1}
−20	1.818	3.83		1470	120	1.8058	4.513	4.33	1404.7
0	1.8144	3.918	3.78	1460.8	140	1.8074	4.622		1395.4
20	1.8110	4.013	3.87	1451.4	160	1.8100	4.731	4.53	1386.1
40	1.8083	4.109	3.96	1442.0	180	1.8136	4.844		1376.7
60	1.8064	4.207		1432.7	200	1.818	4.96		1367
80	1.8053	4.308	4.14	1423.4	250	1.834	5.26		1344
100	1.8051	4.410		1414.1	300	1.856	5.59		1321

SURFACE TENSION OF COMMON LIQUIDS

The surface tension γ of about 200 liquids is tabulated here as a function of temperature. Values of γ are given in units of millinewtons per meter (mN/m), which is equivalent to dyn/cm in cgs units. The values refer to a nominal pressure of one atmosphere (about 100 kPa) except in cases where the indicated temperature is above the normal boiling point of the substance; in those cases, the applicable pressure is the saturation vapor pressure at the temperature in question.

The uncertainty of the values is 0.1 to 0.2 mN/m or less in most cases. Values at temperatures between the points tabulated can be obtained by linear interpolation to a good approximation.

Substances are listed by molecular formula in the modified Hill order, with substances not containing carbon appearing before those that do contain carbon. A more extensive compilation of surface tension may be found in Reference 1.

References

1. Jasper, J. J., *J. Phys. Chem. Ref. Data*, 1, 841, 1972.
2. Kahl, H., Wadewitz, T., and Winkelmann, J., *J. Chem. Eng. Data*, 48, 580, 2003.

		γ in mN/m				
Mol. formula	**Name**	**10°C**	**25°C**	**50°C**	**75°C**	**100°C**
Br_2	Bromine	43.68	40.95	36.40		
Cl_2O_2S	Sulfuryl chloride		28.78			
Cl_3OP	Phosphoryl chloride		32.03	28.85	25.66	
Cl_3P	Phosphorus trichloride		27.98	24.81		
Cl_4Si	Silicon tetrachloride	19.78	18.29	15.80		
H_2O	Water	74.23	71.99	67.94	63.57	58.91
H_4N_2	Hydrazine		66.39			
Hg	Mercury	488.55	485.48	480.36	475.23	470.11
CCl_4	Tetrachloromethane		26.43	23.37	20.31	17.25
CS_2	Carbon disulfide	33.81	31.58	27.87		
$CHBr_3$	Tribromomethane		44.87	41.60	38.33	
$CHCl_3$	Trichloromethane		26.67	23.44	20.20	
CH_2Br_2	Dibromomethane		39.05	35.33	31.61	
CH_2Cl_2	Dichloromethane		27.20			
CH_2O_2	Formic acid		37.13	34.38	31.64	
CH_3I	Iodomethane	32.19	30.34			
CH_3NO	Formamide		57.03	54.92	52.82	50.71
CH_3NO_2	Nitromethane	39.04	36.53	32.33		
CH_4O	Methanol	23.23	22.07	20.14		
CH_5N	Methylamine		19.15			
C_2HCl_5	Pentachloroethane		34.15	31.20	28.26	
$C_2HF_3O_2$	Trifluoroacetic acid		13.53	11.42		
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane		35.58	32.41	29.24	26.07
$C_2H_3Cl_3$	1,1,1-Trichloroethane		25.18	22.07		
$C_2H_3Cl_3$	1,1,2-Trichloroethane		34.02	30.65	27.27	23.89
C_2H_3N	Acetonitrile		28.66	25.51		
$C_2H_4Br_2$	1,2-Dibromoethane		39.55	36.25	32.95	
$C_2H_4Cl_2$	1,1-Dichloroethane		24.07			
$C_2H_4Cl_2$	1,2-Dichloroethane		31.86	28.29	24.72	
C_2H_4O	Acetaldehyde	22.54	20.50	17.10		
$C_2H_4O_2$	Acetic acid		27.10	24.61	22.13	
$C_2H_4O_2$	Methyl formate	26.72	24.36	20.43	16.50	12.57
C_2H_5Br	Bromoethane	25.36	23.62			
C_2H_5I	Iodoethane	30.38	28.46	25.24		
$C_2H_5NO_2$	Nitroethane	34.02	32.13	29.00		
C_2H_6O	Ethanol	23.22	21.97	19.89		
C_2H_6OS	Dimethyl sulfoxide		42.92	40.06		
$C_2H_6O_2$	Ethylene glycol		47.99	45.76	43.54	41.31
C_2H_6S	Dimethyl sulfide	25.27	24.06			
C_2H_6S	Ethanethiol		23.08			
$C_2H_6S_2$	Dimethyl disulfide		33.39	30.04		
C_2H_7N	Dimethylamine		26.34			
C_2H_7N	Ethylamine		19.20			
C_2H_7NO	Ethanolamine		48.32	45.53	42.73	
C_3H_5Br	3-Bromopropene		26.31	23.17		

		γ in mN/m				
Mol. formula	**Name**	**10°C**	**25°C**	**50°C**	**75°C**	**100°C**
C_3H_5Cl	3-Chloropropene		23.14			
C_3H_5ClO	Epichlorohydrin	38.40	36.36	32.96	29.56	26.16
C_3H_5N	Propanenitrile		26.75	23.87		
$C_3H_6Cl_2$	1,2-Dichloropropane		28.32	25.22	22.12	
C_3H_6O	Acetone	24.57	22.72	19.65		
C_3H_6O	Allyl alcohol	26.63	25.28	23.02	20.77	
$C_3H_6O_2$	Ethyl formate	25.16	23.18			
$C_3H_6O_2$	Methyl acetate	26.66	24.73	21.51		
$C_3H_6O_2$	Propanoic acid		26.20	23.72	21.23	
C_3H_7Br	1-Bromopropane	27.08	25.26	22.21		
C_3H_7Br	2-Bromopropane	25.03	23.25	20.30		
C_3H_7Cl	1-Chloropropane	23.16	21.30			
C_3H_7Cl	2-Chloropropane	20.49	19.16			
C_3H_7NO	*N*,*N*-Dimethylformamide	37.56	35.74	32.70	29.66	26.62
$C_3H_7NO_2$	2-Nitropropane	31.02	29.29	26.39		
C_3H_8O	1-Propanol	24.48	23.32	21.38	19.43	
C_3H_8O	2-Propanol	22.11	20.93	18.96	16.98	
$C_3H_8O_2$	2-Methoxyethanol	32.32	30.84	28.38	25.92	23.46
C_3H_8S	1-Propanethiol		24.20	21.02		
C_3H_8S	2-Propanethiol		21.33	18.39		
C_3H_9N	Propylamine		21.75			
C_3H_9N	Trimethylamine		13.41			
$C_4H_4N_2$	Pyridazine	49.51	47.96	45.37	42.78	40.19
$C_4H_4N_2$	Pyrimidine		30.33	27.80	25.28	22.75
C_4H_4S	Thiophene		30.68	27.36		
C_4H_5N	Pyrrole	38.71	37.06	34.31		
$C_4H_6O_3$	Acetic anhydride	34.08	31.93	28.34	24.75	21.16
C_4H_7N	Butanenitrile		26.92	24.33	21.73	
C_4H_8O	2-Butanone		23.97	21.16		
$C_4H_8O_2$	1,4-Dioxane		32.75	29.28	25.80	22.32
$C_4H_8O_2$	Ethyl acetate	25.13	23.39	20.49	17.58	14.68
$C_4H_8O_2$	Methyl propanoate	26.32	24.44	21.29		
$C_4H_8O_2$	Butanoic acid		26.05	23.75	21.45	
C_4H_9Br	1-Bromobutane	27.58	25.90	23.08	20.27	17.45
C_4H_9Cl	1-Chlorobutane	24.85	23.18	20.39		
C_4H_9I	1-Iodobutane	29.79	28.24	25.67	23.09	20.51
C_4H_9N	Pyrrolidine	30.58	29.23	26.98		
$C_4H_{10}O$	1-Butanol	26.28	24.93	22.69	20.44	18.20
$C_4H_{10}O$	2-Butanol	23.74	22.54	20.56	18.57	16.58
$C_4H_{10}O$	2-Methyl-2-propanol		19.96	17.71		
$C_4H_{10}O$	Diethyl ether		16.65			
$C_4H_{10}O_2$	2-Ethoxyethanol		28.35	26.11	23.86	21.62
$C_4H_{10}O_3$	Diethylene glycol		44.77	42.57	40.37	38.17
$C_4H_{10}S$	Diethyl sulfide	26.22	24.57	21.80		
$C_4H_{11}N$	Butylamine		23.44	20.63		
$C_4H_{11}N$	Isobutylamine		21.75	19.02		
$C_4H_{11}N$	*tert*-Butylamine		16.87			
$C_4H_{11}N$	Diethylamine		19.85			
$C_5H_4O_2$	Furfural	45.08	43.09	39.78	36.46	33.14
C_5H_5N	Pyridine		36.56	33.29	30.03	
C_5H_8	Cyclopentene	24.45	22.20			
C_5H_8O	Cyclopentanone	34.45	32.80	30.05	27.30	24.55
C_5H_9NO	*N*-Methyl-2-pyrrolidinone	41.94	40.21	37.33	34.45	31.57
C_5H_{10}	1-Pentene	17.10	15.45			
C_5H_{10}	2-Methyl-2-butene	18.61	17.15			
C_5H_{10}	Cyclopentane	24.07	21.88	18.22		
$C_5H_{10}O$	2-Pentanone		23.25	21.62		
$C_5H_{10}O$	3-Pentanone		24.74	22.13		
$C_5H_{10}O$	Pentanal	26.95	25.44	22.91		
$C_5H_{10}O_2$	Butyl formate	26.05	24.52	21.95	19.39	16.82

Mol. formula	Name	γ in mN/m				
		10°C	25°C	50°C	75°C	100°C
$C_5H_{10}O_2$	Propyl acetate	25.48	23.80	21.00	18.20	15.40
$C_5H_{10}O_2$	Isopropyl acetate	23.37	21.76	19.08	16.40	
$C_5H_{10}O_2$	Ethyl propanoate	25.55	23.80	20.88	17.96	
$C_5H_{10}O_2$	Methyl butanoate	26.34	24.62	21.76	18.89	16.03
$C_5H_{11}Cl$	1-Chloropentane	26.01	24.40	21.71	19.02	16.33
$C_5H_{11}N$	Piperidine	30.64	28.91	26.03	23.14	20.26
C_5H_{12}	Pentane	17.15	15.49			
$C_5H_{12}O$	1-Pentanol	26.67	25.36	23.17	20.99	18.80
$C_5H_{12}O$	2-Pentanol	24.96	23.45	20.94	18.43	15.92
$C_5H_{12}O$	3-Methyl-1-butanol	24.94	23.71	21.66	19.61	17.56
$C_5H_{13}N$	Pentylamine		24.69	22.14	19.58	
$C_6H_4Cl_2$	*m*-Dichlorobenzene	37.15	35.43	32.57	29.70	26.83
C_6H_5Br	Bromobenzene	36.98	35.24	32.34	29.44	26.54
C_6H_5Cl	Chlorobenzene	34.78	32.99	30.02	27.04	24.06
C_6H_5ClO	*o*-Chlorophenol		39.70	36.89	34.09	31.28
C_6H_5ClO	*m*-Chlorophenol		41.18	38.66	36.13	33.61
C_6H_5F	Fluorobenzene	28.47	26.66	23.65	20.64	
C_6H_5I	Iodobenzene	40.40	38.71	35.91	33.10	30.29
$C_6H_5NO_2$	Nitrobenzene			40.56	37.66	34.77
C_6H_6	Benzene		28.22	25.00	21.77	
C_6H_6O	Phenol			38.20	35.53	32.86
C_6H_7N	Aniline		42.12	39.41	36.69	
C_6H_7N	2-Methylpyridine		33.00	29.90	26.79	
$C_6H_8N_2$	Adiponitrile		45.45	43.02	40.58	
C_6H_{10}	Cyclohexene	28.01	26.17	23.12		
$C_6H_{10}O$	Cyclohexanone	36.43	34.57	31.46	28.36	25.25
$C_6H_{11}N$	Hexanenitrile		27.37	25.11	22.84	
C_6H_{12}	Cyclohexane	25.91	24.16	21.26	15.44	
C_6H_{12}	Methylcyclopentane	23.47	21.72	18.82		
C_6H_{12}	1-Hexene	19.44	17.90	15.33		
$C_6H_{12}O$	Cyclohexanol		32.92	30.50	28.09	25.67
$C_6H_{12}O$	2-Hexanone		25.45	22.72		
$C_6H_{12}O_2$	Butyl acetate	26.48	24.88	22.21	19.54	16.87
$C_6H_{12}O_2$	Isobutyl acetate	24.58	23.06	20.53	17.99	15.46
$C_6H_{12}O_2$	Ethyl butanoate	25.51	23.94	21.33	18.71	16.10
$C_6H_{12}O_3$	Paraldehyde	27.22	25.63	22.97	20.32	17.66
$C_6H_{13}Cl$	1-Chlorohexane	27.28	25.73	23.13	20.54	17.94
$C_6H_{13}N$	Cyclohexylamine		31.22	28.25	25.28	
C_6H_{14}	Hexane	19.42	17.89	15.33		
C_6H_{14}	2-Methylpentane	18.37	16.88	14.39		
C_6H_{14}	3-Methylpentane	19.20	17.61	14.96		
$C_6H_{14}O$	Diisopropyl ether		17.27	14.65		
$C_6H_{14}O$	1-Hexanol		25.81	23.81	21.80	19.80
$C_6H_{14}O_2$	1,1-Diethoxyethane		20.89	18.31	15.74	
$C_6H_{14}O_2$	2-Butoxyethanol	27.36	26.14	24.10	22.06	20.02
$C_6H_{15}N$	Triethylamine		20.22	17.74		
$C_6H_{15}N$	Dipropylamine		22.31	19.75	17.20	
$C_6H_{15}N$	Diisopropylamine		19.14	16.45		
C_7H_5N	Benzonitrile		38.79	35.90	33.00	
C_7H_6O	Benzaldehyde	39.63	38.00	35.27	32.55	29.82
C_7H_8	Toluene	29.46	27.73	24.85	21.98	19.10
C_7H_8O	*o*-Cresol		36.90	34.38	31.85	29.32
C_7H_8O	*m*-Cresol		35.69	33.38	31.07	28.76
C_7H_8O	Benzyl alcohol				27.89	24.44
C_7H_8O	Anisole		35.10	32.09	29.08	
C_7H_9N	*N*-Methylaniline		36.90	34.47	32.05	
C_7H_9N	2,3-Dimethylpyridine		32.71	30.04	27.36	
C_7H_9N	Benzylamine		39.30	36.27	33.23	
C_7H_{14}	Methylcyclohexane	24.98	23.29	20.46		
C_7H_{14}	1-Heptene	21.29	19.80	17.33	14.85	

		γ in mN/m				
Mol. formula	**Name**	**10°C**	**25°C**	**50°C**	**75°C**	**100°C**
$C_7H_{14}O$	2-Heptanone		26.12	23.48		
$C_7H_{14}O_2$	Pentyl acetate	26.67	25.17	22.69	20.20	17.72
$C_7H_{14}O_2$	Heptanoic acid		27.76	25.64		
C_7H_{16}	Heptane	21.14	19.66	17.19	14.73	
C_7H_{16}	3-Methylhexane	20.76	19.31	16.88	14.46	
C_8H_8O	Acetophenone		39.04	36.15	33.27	
$C_8H_8O_2$	Methyl benzoate		37.17	34.25	31.32	
$C_8H_8O_3$	Methyl salicylate	40.98	39.22	36.28	33.35	30.41
C_8H_{10}	Ethylbenzene	30.39	28.75	26.01	23.28	20.54
C_8H_{10}	*o*-Xylene	31.41	29.76	27.01	24.25	21.50
C_8H_{10}	*m*-Xylene	30.13	28.47	25.71	22.95	20.19
C_8H_{10}	*p*-Xylene		28.01	25.32	22.64	19.95
$C_8H_{10}O$	Phenetole		32.41	29.65	26.89	
$C_8H_{11}N$	*N,N*-Dimethylaniline		35.52	32.90	30.27	
$C_8H_{11}N$	*N*-Ethylaniline		36.33	33.65	30.98	
C_8H_{16}	Ethylcyclohexane	26.73	25.15	22.51		
C_8H_{18}	Octane	22.57	21.14	18.77	16.39	14.01
C_8H_{18}	2,5-Dimethylhexane	20.77	19.40	17.12	14.84	12.56
$C_8H_{18}O$	1-Octanol	28.30	27.10	25.12		
$C_8H_{19}N$	Dibutylamine		24.12	21.74	19.36	
$C_8H_{19}N$	Diisobutylamine		21.72	19.44	17.16	
C_9H_7N	Quinoline	44.19	42.59	39.94	37.28	34.62
C_9H_{12}	Cumene	29.27	27.69	25.05	22.42	19.78
C_9H_{12}	1,2,4-Trimethylbenzene	30.74	29.20	26.64	24.07	21.51
C_9H_{12}	Mesitylene	28.89	27.55	25.31	23.07	20.82
$C_9H_{18}O$	5-Nonanone		26.28	23.85		
C_9H_{20}	Nonane	23.79	22.38	20.05	17.71	15.37
$C_9H_{20}O$	1-Nonanol	29.03	27.89	26.00	24.10	22.20
$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene		33.17	30.78	28.40	
$C_{10}H_{22}$	Decane	24.75	23.37	21.07	18.77	16.47
$C_{10}H_{22}O$	1-Decanol	29.61	28.51	26.68	24.85	23.02
$C_{11}H_{24}$	Undecane	25.56	24.21	21.96	19.70	17.45
$C_{12}H_{10}O$	Diphenyl ether		26.75	24.80		
$C_{12}H_{27}N$	Tributylamine		24.39	22.32	20.24	
$C_{13}H_{28}$	Tridecane	26.86	25.55	23.37	21.19	19.01
$C_{14}H_{12}O_2$	Benzyl benzoate	44.47	42.82	40.06	37.31	34.55
$C_{14}H_{30}$	Tetradecane	27.43	26.13	23.96	21.78	19.61
$C_{16}H_{34}$	Hexadecane		27.05	24.91	22.78	20.64
$C_{18}H_{38}$	Octadecane		27.87	25.77	23.66	21.55

PERMITTIVITY (DIELECTRIC CONSTANT) OF LIQUIDS

Christian Wohlfarth

The permittivity of a substance (often called the dielectric constant) is the ratio of the electric displacement D to the electric field strength E when an external field is applied to the substance. The quantity tabulated here is the relative permittivity, which is the ratio of the actual permittivity to the permittivity of a vacuum; it is a dimensionless number.

The table gives the static relative permittivity ε_r, i.e., the relative permittivity measured in static fields or at low frequencies where no relaxation effects occur. The fourth column of the table lists the value of ε_r at the temperature specified in the third column, usually 293.15 or 298.15 K. Otherwise, the temperature closest to 293.15 K was chosen, or (as it is the case for many of the substances included here) ε_r is given at the only temperature for which data are available.

The static permittivity refers to nominal atmospheric pressure as long as the corresponding temperature is below the normal boiling point. Otherwise, at temperatures above the normal boiling point, the pressure is understood to be the saturated vapor pressure of the substance considered.

For substances where information on the temperature dependence of the permittivity is available, the table gives the coefficients of a simple polynomial fitting of permittivity to temperature with an equation of the form

$$\varepsilon_r(T) = a + bT + cT^2 + dT^3$$

where T is the absolute temperature in K. Since the parameter d was used in only a few cases where the quadratic fit was not satisfactory, only a, b, and c are listed as columns in the table, while the d values are given at the end of this introduction. For all other substances, $d = 0$. The temperature range of the fit is given in the last column. The coefficients of the fitting equation can be used to calculate dielectric constants within the fitted temperature range but should not be used for extrapolation outside this range. The user who needs dielectric constant data with more accuracy than can be provided by this equation is referred to Reference 1, which gives the original data together with their literature source.

Substances are listed by molecular formula in modified Hill order, with substances not containing carbon preceding those that do contain carbon.

* Indicates that the isomer was not specified in the original reference.

** Indicates a compound for which the cubic term is needed:

Ethanol	d = –0.15512E-05
N-Methylacetamide	d = –0.12998E-04
1,2-Propylene glycol	d = –0.32544E-05
1-Butanol	d = –0.48841E-06
2-Butanol	d = –0.89512E-06
2-Methyl-1-propanol	d = –0.45229E-06
2-Methyl-2-propanol	d = –0.25968E-05
N-Butylacetamide	d = –0.48716E-05

References

1. Wohlfarth, Ch., Static Dielectric Constants of Pure Liquids and Binary Liquid Mixtures, *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series*, Editor in Chief, O. Madelung, Group IV, Macroscopic and Technical Properties of Matter, Volume 6, Springer-Verlag, Berlin, 1991.
2. Marsh, K. N., Ed., *Recommended Reference Materials for the Realization of Physicochemical Properties*, Blackwell Scientific Publications, Oxford, 1987.

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
$AlBr_3$	Aluminum tribromide	373.2	3.38				
Ar	Argon	140.00	1.3247	0.12408E+01	0.68755E-02	–0.45344E-04	87-149
AsH_3	Arsine	200.9	2.40	0.37674E+01	–0.97454E-02	0.14537E-04	157-201
BBr_3	Boron tribromide	273.2	2.58				
B_2H_6	Diborane	180.66	1.8725	0.23848E+01	–0.29501E–02	0.64189E-06	108-181
B_5H_9	Pentaborane(9)	298.2	21.1	0.40952E+03	–0.24414E+01	0.38225E-02	226-298
BrF_3	Bromine trifluoride	298.2	106.8				
BrF_5	Bromine pentafluoride	297.7	7.91	0.11428E+02	–0.11822E-01		262-298
BrH	Hydrogen bromide	186.8	8.23				
BrNO	Nitrosyl bromide	288.4	13.4				
Br_2	Bromine	297.9	3.1484	0.32701E+01	–0.12535E-03		273-327
Br_2OS	Thionyl bromide	293.2	9.06				
Br_3OV	Vanadyl tribromide	298.2	3.6	0.61112E+01	–0.84211E-02		203-298
Br_4Ge	Germanium(IV) bromide	299.9	2.955	0.34450E+01	–0.16083E-02		300-316
Br_4Sn	Tin(IV) bromide	303.45	3.169	0.50001E+01	–0.60383E-02		304-316
$ClFO_3$	Perchloryl fluoride	150.2	2.194	0.23808E+01	–0.38629E-03	–0.57143E-05	125-150
ClF_3	Chlorine trifluoride	293.2	4.394	0.96716E+01	–0.18000E-01		273-313
ClF_5	Chlorine pentafluoride	193.2	4.28	0.78192E+01	–0.20860E-01	0.13132E-04	193-256
ClH	Hydrogen chloride	158.9	14.3	0.47316E+02	–0.28455E+00	0.48650E-03	159-258
ClNO	Nitrosyl chloride	285.2	18.2				
Cl_2	Chlorine	208.0	2.147	0.29440E+01	–0.44649E-02	0.30388E-05	208-240
Cl_2F_3P	Phosphorus(V) dichloride trifluoride	228.63	2.8129	0.46501E+01	–0.80358E-02		172-229
Cl_2OS	Thionyl chloride	298.2	8.675				
Cl_2OSe	Selenium oxychloride	293.2	46.2				
Cl_2O_2S	Sulfuryl chloride	293.2	9.1				

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
Cl_2S	Sulfur dichloride	298.2	2.915				
Cl_2S_2	Sulfur chloride	288.2	4.79				
Cl_3F_2P	Phosphorus(V) trichloride difluoride	268.0	2.3752	0.28905E+01	−0.19228E-02		215-268
Cl_3OP	Phosphorus(V) oxychloride	293.2	14.1				
Cl_3OV	Vanadyl trichloride	298.2	3.4				
Cl_3P	Phosphorus(III) chloride	290.2	3.498	0.59098E+01	−0.83322E-02		290-333
Cl_3PS	Phosphorus(V) sulfide trichloride	298.2	4.94				
Cl_4FP	Phosphorus(V) tetrachloride fluoride	272.64	2.6499	0.33503E+01	−0.29651E-02		244-273
Cl_4Ge	Germanium(IV) chloride	273.2	2.463	−0.55078E+01	0.64881E-01	−0.13091E-03	246-273
Cl_4Pb	Lead(IV) chloride	293.2	2.78				
Cl_4Si	Tetrachlorosilane	273.2	2.248	0.58041E+01	−0.27129E-01	0.51678E-04	207-273
Cl_4Sn	Tin(IV) chloride	273.2	3.014	0.43951E+01	−0.48805E-02		234-273
Cl_4Ti	Titanium(IV) chloride	257.4	2.843	0.33668E+01	−0.19675E-02		237-257
Cl_4V	Vanadium(IV) chloride	298.2	3.05				
Cl_5P	Phosphorus(V) chloride	433.2	2.85				
Cl_5Sb	Antimony(V) chloride	293.0	3.222	0.45413E+01	−0.45078E-02		276-320
FH	Hydrogen fluoride	273.2	83.6	0.50352E+03	−0.19297E+01	0.14372E-02	200-273
F_2	Fluorine	53.48	1.4913	0.14144E+01	0.26387E-02	−0.28356E-04	54-144
F_5I	Iodine pentafluoride	293.2	37.13	0.95184E+02	−0.19800E+00		273-313
F_6S	Sulfur hexafluoride	223.2	1.81				
F_6Xe	Xenon hexafluoride	328.2	4.10				
F_7I	Iodine heptafluoride	298.2	1.75				
$F_{10}S_2$	Sulfur decafluoride	293.2	2.0202				
HI	Hydrogen iodide	220.2	3.87	0.51557E+03	−0.44552E+01	0.96795E-02	220-236
H_2	Hydrogen	13.52	1.2792	0.13327E+01	−0.51946E-02		14-19
H_2O	Water	293.2	80.100	0.24921E+03	−0.79069E+00	0.72997E-03	273-372
H_2O_2	Hydrogen peroxide	290.2	74.6	0.48511E+03	−0.23145E+01	0.31020E-02	233-303
H_2S	Hydrogen sulfide	283.2	5.93	0.14736E+02	−0.33675E-01	0.96740E-05	212-363
H_3N	Ammonia	293.2	16.61	0.66756E+02	−0.24696E+00	0.25913E-03	238-323
H_4N_2	Hydrazine	298.2	51.7	0.22061E+03	−0.89633E+00	0.11066E-02	278-323
He	Helium	2.055	1.0555	0.10640E+01	−0.35584E-02		2-4
I_2	Iodine	391.25	11.08	0.64730E+02	−0.29266E+00	0.39759E-03	391-441
Kr	Krypton	119.80	1.664				
Mn_2O_7	Manganese(VII) oxide	293.2	3.28	0.37655E+01	−0.16463E-02		283-312
NO	Nitric oxide	1.997					
N_2	Nitrogen	63.15	1.4680	0.12550E+01	0.67949E-02	−0.56704E-04	63-126
N_2O_3	Nitrogen trioxide	203.2	31.13	0.92287E+02	−0.43306E+00	0.65000E-03	203-243
N_2O_4	Nitrogen tetroxide	293.2	2.44	0.28212E+01	−0.13000E-02		253-293
Ne	Neon	26.11	1.1907	0.12667E+01	−0.29064E-02		26-29
O_2	Oxygen	54.478	1.5684	0.15434E+01	0.14615E-02	−0.21964E-04	55-154
O_2S	Sulfur dioxide	298.2	16.3	0.52045E+02	−0.16125E+00	0.11042E-03	213-449
O_3	Ozone	90.2	4.75	0.86344E+01	−0.54807E-01	0.12596E-03	90-185
O_3S	Sulfur trioxide	291.2	3.11				
P	Phosphorus	307.2	4.096	0.79018E+00	0.23911E-01	−0.42826E-04	307-358
S	Sulfur	407.2	3.4991	0.51651E+01	−0.77381E-02	0.89120E-05	407-479
Se	Selenium	510.65	5.44	0.67569E+01	−0.25829E-02		511-575
Xe	Xenon	161.35	1.880				
$CBrClF_2$	Bromochlorodifluoromethane	123.2	3.920	0.52442E+01	−0.11000E-01		123-223
$CBrCl_3$	Bromotrichloromethane	293.2	2.405	0.29249E+01	−0.17650E-02		273-333
$CBrF_3$	Bromotrifluoromethane	123.2	3.730	0.54154E+01	−0.13680E-01		123-173
CBr_2Cl_2	Dibromodichloromethane	298.2	2.542	0.32330E+01	−0.23162E-02		298-333
CBr_2F_2	Dibromodifluoromethane	273.2	2.939	0.67296E+01	−0.22133E-01	0.30213E-04	139-273
CBr_3Cl	Tribromochloromethane	333.2	2.601				
CBr_3F	Tribromofluoromethane	293.2	3.00	0.53203E+01	−0.11061E-01	0.10688E-04	206-323
CBr_3NO_2	Tribromonitromethane	298.2	9.034	0.16079E+02	−0.23630E-01		298-328
$CClF_3$	Chlorotrifluoromethane	123.2	3.010	0.43677E+01	−0.11020E-01		123-173
CCl_2F_2	Dichlorodifluoromethane	123.2	3.500	0.46984E+01	−0.97600E-02		123-223
CCl_2O	Carbonyl chloride	295.2	4.30				
CCl_3D	Trichloromethane-*d*	298.2	4.67				
CCl_3F	Trichlorofluoromethane	293.2	3.00	0.53203E+01	−0.11061E-01	0.10688E-04	206-323
CCl_3NO_2	Trichloronitromethane	293.2	7.319	0.14403E+02	−0.24178E-01		276-333
CCl_4	Tetrachloromethane	293.2	2.2379	0.28280E+01	−0.20339E-02	0.71795E-07	283-333
CF_4	Tetrafluoromethane	126.3	1.685	0.20350E+01	−0.27616E-02		126-142

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
$CHBr_3$	Tribromomethane	283.2	4.404	0.71707E+01	−0.98000E-02		283-343
$CHCl_3$	Trichloromethane	293.2	4.8069	0.15115E+02	−0.51830E-01	0.56803E-04	218-323
CHF_3	Trifluoromethane	294.0	5.2	0.11442E+03	−0.75600E+00	0.13562E-02	130-263
CHN	Hydrogen cyanide	293.2	114.9	0.37331E+04	−0.23180E+02	0.36963E-01	258-299
CH_2Br_2	Dibromomethane	283.2	7.77	0.18060E+02	−0.36333E-01		283-313
CH_2Cl_2	Dichloromethane	298.0	8.93	0.40452E+02	−0.17748E+00	0.23942E-03	184-306
CH_2F_2	Difluoromethane	152.2	53.74	0.19428E+03	−0.12939E+01	0.24280E-02	152-224
CH_2I_2	Diiodomethane	298.2	5.32				
CH_2O_2	Formic acid	298.2	51.1	0.14040E+03	−0.24673E+00	−0.17151E-03	287-358
CH_3Br	Bromomethane	275.7	9.71	0.40580E+02	−0.18418E+00	0.26219E-03	195-276
CH_3Cl	Chloromethane	295.2	10.0	0.42775E+02	−0.16175E+00	0.17108E-03	190-392
CH_3ClO_2S	Methanesulfonyl chloride	293.2	34.0	0.10384E+03	−0.33838E+00	0.34156E-03	293-373
CH_3DO	Methan-d_1-ol	297.5	31.68	0.20839E+03	−0.10318E+01	0.14740E-02	176-298
CH_3F	Fluoromethane	131.0	51.0	0.11338E+03	−0.63979E+00	0.96983E-03	150-299
CH_3I	Iodomethane	293.2	6.97	0.24264E+02	−0.93914E-01	0.11926E-03	223-303
CH_3NO	Formamide	293.2	111.0	0.26076E+03	−0.61145E+00	0.34296E-03	278-333
CH_3NO_2	Nitromethane	293.2	37.27	0.11227E+03	−0.35591E+00	0.34206E-03	288-343
CH_3NO_2	Methyl nitrite	200.0	20.77	0.11071E+03	−0.73428E+00	0.14054E-02	110-260
CH_3NO_3	Methyl nitrate	293.2	23.9				
CH_4	Methane	91.0	1.6761	0.15996E+01	0.27434E-02	−0.22086E-04	91-184
CH_4O	Methanol	293.2	33.0	0.19341E+03	−0.92211E+00	0.12839E-02	177-293
CH_5N	Methylamine	215.2	16.7	0.34398E+02	−0.73630E-01	−0.41279E-04	198-258
CN_4O_8	Tetranitromethane	293.2	2.317				
COS	Carbon oxysulfide	185.0	4.47	0.84702E+01	−0.21488E-01		143-185
COSe	Carbon oxyselenide	283.2	3.47	0.48740E+01	−0.49425E-02		219-283
CO_2	Carbon dioxide	295.0	1.4492	0.79062E+00	0.10639E-01	−0.28510E-04	220-300
CS_2	Carbon disulfide	293.2	2.6320	0.45024E+01	−0.12054E-01	0.19147E-04	154-319
$C_2Br_2F_4$	1,2-Dibromotetrafluoroethane	298.2	2.34				
$C_2Cl_2F_4$	1,2-Dichlorotetrafluoroethane	273.2	2.4842	0.36663E+01	−0.42271E-02	−0.36255E-06	193-273
$C_2Cl_2O_2$	Oxalyl chloride	294.35	3.470				
C_2Cl_3N	Trichloroacetonitrile	292.2	7.85				
C_2Cl_4	Tetrachloroethylene	303.2	2.268				
$C_2Cl_4F_2$	1,1,2,2-Tetrachloro-1,2-difluoroethane	308.2	2.52				
C_2HBr_3O	Tribromoacetaldehyde	293.2	7.6				
C_2HCl_3	Trichloroethylene	301.5	3.390	0.58319E+01	−0.80828E-02		302-338
$C_2HCl_3F_2$	1,2,2-Trichloro-1,1-difluoroethane	303.2	4.01	0.75423E+01	−0.11667E-01		303-333
C_2HCl_3O	Trichloroacetaldehyde	298.2	6.8				
$C_2HCl_3O_2$	Trichloroacetic acid	333.2	4.34	0.13412E+01	0.90000E-02	−0.24130E-14	333-393
C_2HCl_5	Pentachloroethane	298.2	3.716	0.65972E+01	−0.96800E-02		298-338
$C_2HF_3O_2$	Trifluoroacetic acid	293.2	8.42	0.21652E+02	−0.68146E-01	0.78571E-04	263-323
C_2H_2	Acetylene	195.0	2.4841				
$C_2H_2Br_2$	*cis*-1,2-Dibromoethylene	298.2	7.08				
$C_2H_2Br_2$	*trans*-1,2-Dibromoethylene	298.2	2.88				
$C_2H_2Br_4$	1,1,2,2-Tetrabromoethane	303.2	6.72	0.16246E+02	−0.31500E-01		303-333
$C_2H_2Cl_2$	1,1-Dichloroethylene	293.2	4.60				
$C_2H_2Cl_2$	*cis*-1,2-Dichloroethylene	298.2	9.20				
$C_2H_2Cl_2$	*trans*-1,2-Dichloroethylene	293.2	2.14				
$C_2H_2Cl_2O_2$	Dichloroacetic acid	293.2	8.33	0.11014E+02	−0.10859E-01	0.49242E-05	284-363
$C_2H_2Cl_4$	1,1,1,2-Tetrachloroethane	207.2	9.22	0.19606E+02	−0.49847E-01		207-233
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane	293.2	8.50				
$C_2H_2I_2$	*cis*-1,2-Diiodoethylene	345.65	4.46				
C_2H_3ClO	Acetyl chloride	295.2	15.8				
$C_2H_3ClO_2$	Chloroacetic acid	338.2	12.35	0.17310E+02	−0.14674E-01		338-393
$C_2H_3Cl_2NO_2$	1,1-Dichloro-1-nitroethane	303.2	16.3	0.37576E+02	−0.70400E-01		303-333
$C_2H_3Cl_3$	1,1,1-Trichloroethane	293.2	7.243	0.27705E+02	−0.10621E+00	0.12424E-03	258-318
$C_2H_3Cl_3$	1,1,2-Trichloroethane	298.2	7.1937	0.17147E+02	−0.33371E-01		288-318
$C_2H_3F_3O$	2,2,2-Trifluoroethanol	293.2	27.68	0.90593E+02	−0.21421E+00		293-318
C_2H_3N	Acetonitrile	293.2	36.64	0.29724E+03	−0.15508E+01	0.22591E-02	288-333
C_2H_3NO	Methyl isocyanate	288.7	21.75				
C_2H_4	Ethylene	270.0	1.4833	0.13546E+01	0.62614E-02	−0.21374E-04	200-270
C_2H_4BrCl	1-Bromo-2-chloroethane	283.2	7.41	0.19493E+02	−0.59054E-01	0.58036E-04	263-363
$C_2H_4Br_2$	1,2-Dibromoethane	293.2	4.9612	0.67142E+01	−0.59800E-02		293-313
$C_2H_4Cl_2$	1,1-Dichloroethane	298.2	10.10	0.24429E+02	−0.48000E-01		288-318

Mol. form.	Name	*T*/K	ε_r	*a*	*b*	*c*	Range/K
$C_2H_4Cl_2$	1,2-Dichloroethane	293.2	10.42	0.24404E+02	−0.47892E-01		293-343
$C_2H_4Cl_2O$	Bis(chloromethyl) ether	293.2	3.51				
$C_2H_4N_2O_6$	Ethylene glycol dinitrate	293.2	28.26				
C_2H_4O	Acetaldehyde	291.2	21.0				
C_2H_4O	Ethylene oxide	293.2	12.42	0.52661E+02	−0.21337E+00	0.25947E-03	293-243
C_2H_4OS	Thioacetic acid	298.2	14.30				
$C_2H_4O_2$	Acetic acid	293.2	6.20	−0.15731E+02	0.12662E+00	−0.17738E-03	293-363
$C_2H_4O_2$	Methyl formate	288.2	9.20	0.19699E+02	−0.36429E-01		288-302
$C_2H_4O_3S$	Ethylene glycol sulfite	298.2	39.6	0.85483E+02	−0.15400E+00		298-328
C_2H_5Br	Bromoethane	298.2	9.01	0.28473E+02	−0.85495E-01	0.67971E-04	243-308
C_2H_5Cl	Chloroethane	293.2	9.45	0.60693E+02	−0.31290E+00	0.47154E-03	237-293
C_2H_5ClO	2-Chloroethanol	293.2	25.80	0.11155E+03	−0.30149E+00		140-175
C_2H_5I	Iodoethane	293.2	7.82	0.25598E+02	−0.94367E-01	0.11424E-03	183-343
C_2H_5N	Ethyleneimine	298.2	18.3	0.61405E+02	−0.14474E+00		273-298
C_2H_5NO	Acetamide	363.7	67.6	−0.20055E+03	0.15515E+01	−0.22392E-02	364-448
C_2H_5NO	*N*-Methylformamide	293.2	189.0	0.10383E+04	−0.43165E+01	0.48398E-02	276-353
C_2H_5NO	Acetaldoxime	298.2	4.70				
$C_2H_5NO_2$	Nitroethane	288.2	29.11	0.57406E+02	−0.97657E-01		276-333
$C_2H_5NO_2$	Methyl carbamate	328.2	18.48	0.36773E+02	−0.55700E-01		328-368
$C_2H_5NO_3$	Ethyl nitrate	293.2	19.7				
C_2H_6	Ethane	95.0	1.9356	0.20185E+01	−0.51493E-03	−0.48148E-05	95-295
C_2H_6O	Ethanol	293.2	25.3	0.15145E+03	−0.87020E+00	0.19570E-02	163-523
C_2H_6O	Dimethyl ether	258.0	6.18	0.22389E+02	−0.86524E-01	0.91291E-04	155-258
C_2H_6OS	Dimethyl sulfoxide	293.2	47.24	0.38478E+02	0.16939E+00	−0.47423E-03	288-343
$C_2H_6O_2$	Ethylene glycol	293.2	41.4	0.14355E+03	−0.48573E+00	0.46703E-03	293-423
$C_2H_6O_2S$	Dimethyl sulfone	383.2	47.39	0.10830E+03	−0.15900E+00		383-398
$C_2H_6O_4S$	Dimethyl sulfate	298.2	55.0				
C_2H_6S	Ethanethiol	298.2	6.667				
C_2H_6S	Dimethyl sulfide	294.2	6.70				
$C_2H_6S_2$	1,2-Ethanedithiol	293.2	7.26	0.11228E+02	−0.13500E-01		293-333
$C_2H_6S_2$	Dimethyl disulfide	298.2	9.6	0.19109E+02	−0.32000E-01		298-323
C_2H_7N	Ethylamine	273.2	8.7	0.30163E+02	−0.79000E-01		233-273
C_2H_7NO	Ethanolamine	293.2	31.94	0.14890E+03	−0.62491E+00	0.77143E-03	253-293
$C_2H_8N_2$	1,2-Ethanediamine	293.2	13.82	0.48922E+02	−0.17021E+00	0.17262E-03	273-333
C_3Cl_6O	Hexachloroacetone	291.9	3.925	0.76423E+01	−0.15838E-01	0.10618E-04	269-303
C_3F_6O	Perfluoroacetone	202.2	2.104	0.34809E+01	−0.92883E-02	0.12282E-04	151-238
C_3HN	Cyanoacetylene	291.9	72.3	0.91803E+03	−0.49149E+01	0.69104E-02	281-314
$C_3H_2F_6O$	1,1,1,3,3,3-Hexafluoro-2-propanol	293.2	16.70				
$C_3H_3ClO_3$	4-Chloro-1,3-dioxolan-2-one	313.2	62.0				
C_3H_3N	Acrylonitrile	293.2	33.0	0.11109E+03	−0.36806E+00	0.34879E-03	233-413
$C_3H_3NO_2$	Cyanoacetic acid	277.2	33.4				
C_3H_4	Allene	269.0	2.025	0.26049E+01	−0.44147E-03	−0.63420E-05	156-269
C_3H_4	Propyne	246.0	3.218	0.60871E+01	−0.11730E-01		185-246
$C_3H_4ClF_3$	3-Chloro-1,1,1-trifluoropropane	295.2	7.32	0.22361E+02	−0.68840E-01	0.60594E-04	275-313
C_3H_4ClNO	2-Chloroethyl isocyanate	288.2	29.1	0.64311E+02	−0.12217E+00		288-403
$C_3H_4Cl_2O$	1,1-Dichloroacetone	293.2	14.6				
$C_3H_4F_4O$	2,2,3,3-Tetrafluoro-1-propanol	298.2	21.03				
C_3H_4O	Propargyl alcohol	293.2	20.8	0.99895E+02	−0.38911E+00	0.40776E-03	213-293
$C_3H_4O_3$	Ethylene carbonate	313.2	89.78	0.20746E+03	−0.37610E+00		313-343
C_3H_5Br	3-Bromopropene	293.2	7.0				
$C_3H_5BrO_2$	2-Bromopropanoic acid	294.2	11.0				
$C_3H_5Br_3$	1,2,3-Tribromopropane	303.2	6.00	0.11024E+02	−0.16596E-01		303-358
C_3H_5Cl	2-Chloropropene	299.25	8.92				
C_3H_5Cl	3-Chloropropene	293.2	8.2				
$C_3H_5ClN_2O_6$	3-Chloro-1,2-propanediol dinitrate	293.2	17.50				
C_3H_5ClO	Epichlorohydrin	293.2	22.6				
$C_3H_5ClO_2$	Ethyl chloroformate	308.7	9.736	0.15356E+02	−0.18250E-01		309-349
$C_3H_5ClO_2$	Methyl chloroacetate	293.2	12.0				
$C_3H_5Cl_3$	1,2,3-Trichloropropane	293.2	7.5				
C_3H_5I	3-Iodopropene	292.2	6.1				
C_3H_5N	Propanenitrile	293.2	29.7	0.82222E+02	−0.22937E+00	0.17424E-03	213-473
C_3H_5NO	Ethyl isocyanate	293.2	19.7				
C_3H_5NS	Ethyl isothiocyanate	293.2	19.6				

Mol. form.	Name	*T*/K	ε_r	*a*	*b*	*c*	Range/K
$C_3H_5N_3O_9$	Trinitroglycerol	293.2	19.25				
C_3H_6	Propene	220.0	2.1365	0.29623E+01	−0.37564E-02		220-250
$C_3H_6Br_2$	1,2-Dibromopropane	283.2	4.60	0.54973E+01	−0.31695E-02		283-333
$C_3H_6Br_2$	1,3-Dibromopropane	293.2	9.482	0.29193E+02	−0.94450E-01	0.92800E-04	293-368
$C_3H_6ClNO_2$	2-Chloro-2-nitropropane	250.4	31.90				
$C_3H_6Cl_2$	1,2-Dichloropropane	293.2	8.37	0.18915E+02	−0.35907E-01		281-323
$C_3H_6Cl_2$	1,3-Dichloropropane	303.2	10.27	0.21609E+02	−0.37333E-01		303-333
$C_3H_6Cl_2$	2,2-Dichloropropane	293.2	11.37	0.32421E+02	−0.72188E-01		245-293
$C_3H_6N_2O_4$	2,2-Dinitropropane	325.1	42.4				
C_3H_6O	Allyl alcohol	293.2	19.7	0.62714E+02	−0.14771E+00	0.37879E-05	213-303
C_3H_6O	Propanal	290.2	18.5				
C_3H_6O	Acetone	293.2	21.01	0.88157E+02	−0.34300E+00	0.38925E-03	273-323
$C_3H_6O_2$	Propanoic acid	298.2	3.44	0.18793E+01	0.46841E-02	0.19983E-05	289-408
$C_3H_6O_2$	Ethyl formate	288.2	8.57	0.15884E+02	−0.25333E-01		288-318
$C_3H_6O_2$	Methyl acetate	288.2	7.07	0.13190E+02	−0.21226E-01		276-318
$C_3H_6O_3$	3-Hydroxypropanoic acid	296.2	30.0				
$C_3H_6O_3$	Dimethyl carbonate	298.2	3.087				
$C_3H_6O_3$	1,3,5-Trioxane	338.2	15.55				
C_3H_7Br	1-Bromopropane	293.2	8.09	0.17769E+02	−0.32599E-01		274-328
C_3H_7Br	2-Bromopropane	293.2	9.46	0.26195E+02	−0.72995E-01	0.55454E-04	186-328
C_3H_7Cl	1-Chloropropane	293.2	8.588	0.21214E+02	−0.43130E-01		273-313
C_3H_7ClO	3-Chloro-1-propanol	215.2	36.0	0.12436E+03	−0.60841E+00	0.92060E-03	145-215
C_3H_7ClO	1-Chloro-2-propanol	153.2	59.0	−0.19169E+02	0.13605E+01	−0.55567E-02	153-177
$C_3H_7ClO_2$	3-Chloro-1,2-propanediol	293.2	31.0				
C_3H_7I	1-Iodopropane	293.2	7.07	0.13744E+02	−0.22745E-01		293-323
C_3H_7I	2-Iodopropane	298.2	8.19				
C_3H_7NO	*N*-Ethylformamide	298.2	102.7	0.64764E+03	−0.28499E+01	0.34286E-02	298-338
C_3H_7NO	*N*,*N*-Dimethylformamide	293.2	38.25	0.15364E+03	−0.60367E+00	0.71505E-03	213-353
C_3H_7NO	*N*-Methylacetamide	303.2	179.0	0.15975E+04	−0.90451E+01	0.18345E-01	303-473
$C_3H_7NO_2$	1-Nitropropane	288.2	24.70	0.94999E+02	−0.38358E+00	0.48480E-03	276-333
$C_3H_7NO_2$	2-Nitropropane	288.2	26.74	0.60138E+02	−0.11566E+00		276-303
$C_3H_7NO_2$	Propyl nitrite	250.0	12.35	0.70552E+02	−0.40362E+00	0.66687E-03	110-310
$C_3H_7NO_2$	Isopropyl nitrite	260.0	13.92	0.74578E+02	−0.38283E+00	0.57071E-03	150-300
$C_3H_7NO_2$	Ethyl carbamate	328.2	14.14	0.32431E+02	−0.65097E-01	0.28571E-04	328-368
C_3H_8	Propane	293.19	1.6678	0.22883E+01	−0.23276E-02	0.84710E-06	90-300
C_3H_8O	1-Propanol	293.2	20.8	0.98045E+02	−0.36860E+00	0.36422E-03	193-493
C_3H_8O	2-Propanol	293.2	20.18	0.10416E+03	−0.41011E+00	0.42049E-03	193-493
$C_3H_8O_2$	1,2-Propylene glycol	303.2	27.5	0.24546E+03	−0.15738E+01	0.38068E-02	193-403
$C_3H_8O_2$	1,3-Propylene glycol	293.2	35.1	0.11365E+03	−0.36680E+00	0.33766E-03	288-328
$C_3H_8O_2$	Ethylene glycol monomethyl ether	298.2	17.2	0.11803E+03	−0.58000E+00	0.81001E-03	254-318
$C_3H_8O_2$	Dimethoxymethane	293.2	2.644	0.25877E+01	−0.93019E-03	0.38472E-05	171-293
$C_3H_8O_3$	Glycerol	293.2	46.53	0.77503E+02	−0.37984E-01	−0.23107E-03	288-343
C_3H_8S	1-Propanethiol	288.2	5.937	0.11602E+02	−0.19580E-01		273-318
C_3H_8S	2-Propanethiol	298.2	5.952				
$C_3H_8S_2$	1,2-Propanedithiol	293.2	7.24	0.14667E+02	−0.32660E-01	0.25000E-04	293-333
$C_3H_8S_2$	1,3-Propanedithiol	303.2	8.11	0.66607E+01	0.31310E-01	−0.87500E-04	303-343
$C_3H_9BO_3$	Trimethyl borate	293.2	2.2762				
C_3H_9ClSi	Trimethylchlorosilane	273.2	10.21	−0.19492E+02	0.29806E+00	−0.69284E-03	223-273
C_3H_9N	Propylamine	296.2	5.08	0.17719E+02	−0.59022E-01	0.54780E-04	204-296
C_3H_9N	Isopropylamine	293.2	5.6268	0.40429E+02	−0.21441E+00	0.32634E-03	213-298
C_3H_9N	Trimethylamine	298.2	2.440	0.39745E+01	−0.51331E-02		273-298
$C_3H_9O_4P$	Trimethyl phosphate	293.2	20.6				
C_4Cl_6	Hexachloro-1,3-butadiene	293.2	2.55				
$C_4Cl_6O_3$	Trichloroacetic anhydride	298.2	5.0				
$C_4F_6O_3$	Trifluoroacetic acid anhydride	298.2	2.7				
$C_4H_2Cl_4O_3$	Dichloroacetic anhydride	298.2	15.8				
$C_4H_2O_3$	Maleic anhydride	326.2	52.75				
$C_4H_3F_7O$	2,2,3,3,4,4,4-Heptafluoro-1-butanol	298.2	14.4				
$C_4H_4N_2$	Succinonitrile	298.2	62.6	0.17724E+03	−0.54654E+00	0.54046E-03	236-351
$C_4H_4N_2$	Pyrazine	323.2	2.80				
C_4H_4O	Furan	277.1	2.88	0.13636E+01	0.12864E-01	−0.22701E-04	188-277
C_4H_4S	Thiophene	293.2	2.739	0.32941E+01	−0.19019E-02		253-293
C_4H_5Cl	2-Chloro-1,3-butadiene	293.2	4.914				

Mol. form.	Name	*T*/K	ε_r	*a*	*b*	*c*	Range/K
$C_4H_5Cl_3O_2$	Ethyl trichloroacetate	293.2	8.428				
C_4H_5N	Pyrrole	293.0	8.00	0.12672E+02	−0.14075E-01	−0.62671E-05	293-357
C_4H_5NO	Allyl isocynate	288.2	15.15	0.34299E+02	−0.66444E-01		288-333
C_4H_6	1,3-Butadiene	265.0	2.050	0.27674E+01	−0.26738E-02		185-265
C_4H_6O	Divinyl ether	288.2	3.94				
C_4H_6O	Ethoxyacetylene	298.2	8.05				
C_4H_6O	Cyclobutanone	298.2	14.27	0.43974E+02	−0.15712E+00	0.19264E-03	220-317
$C_4H_6O_2$	Methyl acrylate	303.2	7.03	0.11968E+02	−0.16500E-01		303-333
$C_4H_6O_2$	2,3-Butanedione	298.2	4.04	0.46907E+01	−0.22302E-02		278-348
$C_4H_6O_2$	γ-Butyrolactone	293.2	39.0				
$C_4H_6O_3$	Acetic anhydride	293.2	22.45				
$C_4H_6O_3$	Propylene carbonate	293.0	66.14	0.15940E+03	−0.39530E+00	0.26284E-03	273-333
C_4H_7Br	*cis*-2-Bromo-2-butene	293.2	5.38				
C_4H_7Br	*trans*-2-Bromo-2-butene	293.2	6.76				
$C_4H_7BrO_2$	2-Bromobutanoic acid	293.2	7.2				
$C_4H_7BrO_2$	Ethyl bromoacetate	303.2	9.75	0.15627E+02	−0.19600E-01		303-333
$C_4H_7BrO_2$	Methyl 3-bromopropanoate	303.2	5.81	0.36001E+01	0.72500E-02		303-343
$C_4H_7ClO_2$	Propyl chlorocarbonate	293.2	11.2				
$C_4H_7ClO_2$	Methyl 2-chloropropanoate	303.2	11.45	0.22449E+02	−0.36250E-01		303-343
C_4H_7N	Butanenitrile	293.2	24.83	0.53884E+02	−0.99257E-01		293-333
C_4H_7N	2-Methylpropanenitrile	293.2	24.42	0.52554E+02	−0.96000E-01		293-313
C_4H_7NO	2-Pyrrolidone	298.2	28.18	0.11054E+03	−0.47945E+00	0.68182E-03	298-338
C_4H_8	1-Butene	220.0	2.2195	0.29354E+01	−0.32580E-02		220-250
C_4H_8	*cis*-2-Butene	296.0	1.960	0.28802E+01	−0.31064E-02		197-296
C_4H_8	Isobutene	288.7	2.1225	0.33701E+01	−0.43295E-02		220-289
$C_4H_8Br_2$	1,2-Dibromobutane	293.2	4.74	0.11199E+03	−0.63334E+00	0.91250E-03	293-333
$C_4H_8Br_2$	1,3-Dibromobutane	293.2	9.14	0.34031E+02	−0.13254E+00	0.16250E-03	293-333
$C_4H_8Br_2$	1,4-Dibromobutane	303.2	8.68	0.20944E+02	−0.55620E-01	0.50000E-04	303-333
$C_4H_8Br_2$	2,3-Dibromobutane	298.2	6.245	0.23849E+02	−0.96300E-01	0.12500E-03	293-333
$C_4H_8Br_2$	1,2-Dibromo-2-methylpropane	293.2	4.1				
$C_4H_8Cl_2$	1,2-Dichlorobutane	293.2	7.74	0.31925E+02	−0.13232E+00	0.17007E-03	293-356
$C_4H_8Cl_2$	1,4-Dichlorobutane	308.2	9.30	0.59766E+01	0.49300E-01	−0.12500E-03	308-338
$C_4H_8Cl_2$	1,2-Dichloro-2-methylpropane	296.0	7.15	0.39429E+02	−0.20028E+00	0.30917E-03	165-296
$C_4H_8Cl_2O$	Bis(2-chloroethyl) ether	293.2	21.20				
C_4H_8O	Butanal	298.2	13.45				
C_4H_8O	2-Butanone	293.2	18.56	0.15457E+02	0.90152E-01	−0.27100E-03	293-333
C_4H_8O	Tetrahydrofuran	295.2	7.52	0.30739E+02	−0.12946E+00	0.17195E-03	224-295
$C_4H_8O_2$	Butanoic acid	287.2	2.98	0.15010E+01	0.50046E-02		287-403
$C_4H_8O_2$	2-Methylpropanoic acid	293.2	2.58				
$C_4H_8O_2$	Propyl formate	303.2	6.92				
$C_4H_8O_2$	Ethyl acetate	293.2	6.0814	0.15646E+02	−0.44066E-01	0.39137E-04	293-433
$C_4H_8O_2$	Methyl propanoate	293.2	6.200	0.12798E+02	−0.22540E-01		293-333
$C_4H_8O_2$	1,4-Dioxane	293.2	2.2189	0.27299E+01	−0.17440E-02		293-313
$C_4H_8O_3$	2-Hydroxybutanoic acid	296.2	37.7				
$C_4H_8O_3$	3-Hydroxybutanoic acid	296.2	31.5				
$C_4H_8O_3$	Ethyl methyl carbonate	293.2	2.985				
$C_4H_8O_3$	Ethylene glycol monoacetate	303.2	12.95				
C_4H_9Br	1-Bromobutane	283.2	7.315	0.22542E+02	−0.79306E-01	0.89867E-04	183-363
C_4H_9Br	2-Bromobutane	298.2	8.64	0.18461E+02	−0.32933E-01		274-328
C_4H_9Br	1-Bromo-2-methylpropane	273.2	7.70	0.37558E+02	−0.20571E+00	0.35496E-03	112-273
C_4H_9Br	2-Bromo-2-methylpropane	293.0	10.98	0.35085E+02	−0.14075E+00	0.19960E-03	258-293
C_4H_9Cl	1-Chlorobutane	293.2	7.276	0.13565E+02	−0.10161E-01	−0.38750E-04	273-323
C_4H_9Cl	2-Chlorobutane	293.2	8.564	0.30376E+02	−0.11377E+00	0.13429E-03	273-323
C_4H_9Cl	1-Chloro-2-methylpropane	293.2	7.027	0.14945E+02	−0.33747E-01	0.23036E-04	273-323
C_4H_9Cl	2-Chloro-2-methylpropane	293.2	9.663	0.35077E+02	−0.12867E+00	0.14304E-03	273-323
C_4H_9I	1-Iodobutane	293.2	6.27	0.16493E+02	−0.50262E-01	0.52485E-04	293-323
C_4H_9I	2-Iodobutane	293.2	7.873	0.10883E+02	−0.14680E-02	−0.30000E-04	293-323
C_4H_9I	2-Iodo-2-methylpropane	283.2	6.65	0.76780E+01	0.69900E-02	−0.37500E-04	283-323
C_4H_9N	Pyrrolidine	293.0	8.30	0.38191E+02	−0.15462E+00	0.17941E-03	274-333
C_4H_9NO	*N*-Methylpropanamide	293.2	170.0				
C_4H_9NO	*N*-Ethylacetamide	293.2	135.0	0.74494E+03	−0.31400E+01	0.36131E-02	213-353
C_4H_9NO	*N*,*N*-Dimethylacetamide	294.2	38.85	0.15420E+03	−0.57506E+00	0.61911E-03	294-433
C_4H_9NO	2-Butanone oxime	293.2	3.4				

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
C_4H_9NO	Morpholine	298.2	7.42				
$C_4H_9NO_2$	*tert*-Butyl nitrite	298.2	11.47				
$C_4H_9NO_2$	Propyl carbamate	338.2	12.06	0.24356E+02	−0.36400E-01		338-378
$C_4H_9NO_2$	Ethyl-*N*-methyl carbamate	298.2	21.10	0.11477E+03	−0.47568E+00	0.54127E-03	298-373
$C_4H_9NO_2$	*N*-Acetylethanolamine	298.2	96.6	0.37016E+03	−0.13113E+01	0.13214E-02	298-348
$C_4H_9NO_3$	Butyl nitrate	293.2	13.10				
C_4H_{10}	Butane	295.0	1.7697	0.22379E+01	−0.13884E-02	−0.66711E-06	135-303
C_4H_{10}	Isobutane	295.0	1.7518	0.23295E+01	−0.19953E-02	0.14197E-06	115-303
$C_4H_{10}O$	1-Butanol	293.2	17.84	0.10578E+03	−0.50587E+00	0.84733E-03	193-553
$C_4H_{10}O$	2-Butanol	293.2	17.26	0.13850E+03	−0.75146E+00	0.14086E-02	172-533
$C_4H_{10}O$	2-Methyl-1-propanol	293.2	17.93	0.10762E+03	−0.51398E+00	0.83702E-03	173-533
$C_4H_{10}O$	2-Methyl-2-propanol	298.2	12.47	0.22541E+03	−0.14990E+01	0.34050E-02	298-503
$C_4H_{10}O$	Diethyl ether	293.2	4.2666	0.79725E+01	−0.12519E-01		283-301
$C_4H_{10}O_2$	1,2-Butanediol	298.2	22.4	0.63702E+02	−0.13807E+00		278-323
$C_4H_{10}O_2$	1,3-Butanediol	298.2	28.8	0.72883E+02	−0.14770E+00		278-323
$C_4H_{10}O_2$	1,4-Butanediol	298.2	31.9	0.13079E+03	−0.46985E+00	0.46320E-03	288-328
$C_4H_{10}O_2$	Ethylene glycol monoethyl ether	298.2	13.38				
$C_4H_{10}O_2$	Ethylene glycol dimethyl ether	296.7	7.30	0.48832E+02	−0.24218E+00	0.34413E-03	256-318
$C_4H_{10}O_2S$	Bis(2-hydroxyethyl) sulfide	293.2	28.61	0.13128E+03	−0.52719E+00	0.60465E-03	253-333
$C_4H_{10}O_3$	Diethylene glycol	293.2	31.82	0.13973E+03	−0.54725E+00	0.61149E-03	288-343
$C_4H_{10}O_3S$	Diethyl sulfite	293.2	15.6				
$C_4H_{10}O_4$	1,2,3,4-Butanetetrol	393.2	28.2				
$C_4H_{10}O_4S$	Diethyl sulfate	293.2	29.2				
$C_4H_{10}S$	1-Butanethiol	288.2	5.204	0.11201E+02	−0.20767E-01		273-318
$C_4H_{10}S$	2-Butanethiol	288.2	5.645	0.10866E+02	−0.17993E-01		273-318
$C_4H_{10}S$	2-Methyl-1-propanethiol	298.2	4.961				
$C_4H_{10}S$	2-Methyl-2-propanethiol	293.2	5.475	0.10597E+02	−0.17500E-01		283-313
$C_4H_{10}S$	Diethyl sulfide	298.2	5.723				
$C_4H_{11}N$	Butylamine	293.2	4.71	0.13322E+02	−0.44176E-01	0.50250E-04	223-333
$C_4H_{11}N$	Diethylamine	293.2	3.680	0.26462E+02	−0.13750E+00	0.20373E-03	243-323
$C_4H_{11}NO_2$	Diethanolamine	293.2	25.75	0.73435E+02	−0.21377E+00	0.17500E-03	273-323
$C_4H_{12}O_2Si$	Dimethoxydimethylsilane	298.2	3.663				
$C_4H_{12}O_3Si$	Trimethoxymethylsilane	298.2	4.9				
$C_4H_{12}O_4Si$	Tetramethyl silicate	293.2	6.0				
$C_4H_{12}Si$	Diethylsilane	293.2	2.544				
$C_4H_{12}Si$	Tetramethylsilane	293.2	1.921				
$C_4H_{13}N_3$	Diethylenetriamine	293.2	12.62	0.57840E+02	−0.23873E+00	0.28841E-03	213-333
C_5FeO_5	Iron pentacarbonyl	293.2	2.602				
C_5H_4BrN	2-Bromopyridine	298.2	23.18	0.73391E+02	−0.23678E+00	0.22930E-03	298-398
C_5H_4ClN	2-Chloropyridine	298.2	27.32	0.98702E+02	−0.34237E+00	0.34502E-03	298-398
$C_5H_4F_8O$	2,2,3,3,4,4,5,5-Octafluoro-1-pentanol	298.2	15.30				
$C_5H_4O_2$	Furfural	293.2	42.1				
C_5H_5N	Pyridine	293.2	13.260	0.43991E+02	−0.15150E+00	0.15925E-03	293-323
C_5H_5NO	Pyridine-1-oxide	343.0	35.94	0.20878E+02	0.16450E+00	−0.35269E-03	343-398
C_5H_6O	2-Methylfuran	293.2	2.76				
$C_5H_6O_2$	Furfuryl alcohol	298.2	16.85				
$C_5H_7Cl_3O_2$	Propyl trichloroacetate	298.2	8.32				
$C_5H_7NO_2$	Ethyl cyanoacetate	263.2	31.62				
C_5H_8	1,3-Pentadiene*	298.2	2.319				
C_5H_8	1,4-Pentadiene	294.0	2.054	0.29994E+01	−0.34578E-02	0.85300E-06	178-294
C_5H_8	2-Methyl-1,3-butadiene	293.2	2.098	0.28170E+01	−0.23147E-02	−0.43975E-06	198-293
C_5H_8	Cyclopentene	295.0	2.083	0.28177E+01	−0.27597E-02	0.89346E-06	171-319
C_5H_8O	Cyclopentanone	298.2	13.58	0.24083E+02	−0.30286E-01	−0.16802E-04	219-298
$C_5H_8O_2$	Ethyl acrylate	303.2	6.05	0.47827E+02	−0.24394E+00	0.35000E-03	303-343
$C_5H_8O_2$	Methyl *trans*-2-butenoate	293.2	6.6645				
$C_5H_8O_2$	Methyl methacrylate	303.2	6.32	0.32098E+02	−0.14568E+00	0.20000E-03	303-343
$C_5H_8O_2$	2,4-Pentanedione	303.2	26.524				
$C_5H_8O_4$	Dimethyl malonate	293.2	9.82	0.26470E+02	−0.76656E-01	0.67888E-04	293-433
$C_5H_9BrO_2$	Ethyl 2-bromopropanoate	293.2	9.4				
$C_5H_9ClO_2$	Isobutyl chlorocarbonate	293.2	9.1				
$C_5H_9ClO_2$	Ethyl 2-chloropropanoate	303.2	11.95	0.25965E+02	−0.46250E-01		303-343
$C_5H_9ClO_2$	Ethyl 3-chloropropanoate	303.2	10.19	0.21951E+02	−0.38750E-01		303-343
$C_5H_9ClO_2$	Methyl 4-chlorobutanoate	303.2	9.51	0.17127E+02	−0.25000E-01		303-343

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
C_5H_9N	Pentanenitrile	293.2	20.04	0.55793E+02	−0.15750E+00	0.12432E-03	183-333
C_5H_9N	2,2-Dimethylpropanenitrile	293.2	21.1	0.58418E+02	−0.16884E+00	0.14131E-03	293-453
C_5H_9NO	Isobutyl isocyanate	293.2	11.638	0.38026E+02	−0.12714E+00	0.12679E-03	293-353
C_5H_9NO	N-Methyl-2-pyrrolidone	293.2	32.55				
C_5H_{10}	1-Pentene	293.2	2.011	−0.11438E+01	0.25420E-01	−0.50000E-04	273-293
C_5H_{10}	2-Methyl-1-butene	293.2	2.180				
C_5H_{10}	2-Methyl-2-butene	296.0	1.979	0.26064E+01	−0.19578E-02	−0.53908E-06	225-296
C_5H_{10}	Cyclopentane	293.2	1.9687	0.24287E+01	−0.15304E-02	−0.13095E-06	278-313
C_5H_{10}	Ethylcyclopropane	293.2	1.933				
$C_5H_{10}Br_2$	1,2-Dibromopentane	298.2	4.39				
$C_5H_{10}Br_2$	1,4-Dibromopentane	293.2	9.05	0.26443E+02	−0.88640E-01	0.10000E-03	293-333
$C_5H_{10}Br_2$	1,5-Dibromopentane	303.2	9.14	0.38192E+02	−0.15648E+00	0.20000E-03	303-333
$C_5H_{10}Cl_2$	1,2-Dichloropentane	293.2	6.89	0.19016E+02	−0.57954E-01	0.56801E-04	293-356
$C_5H_{10}Cl_2$	1,5-Dichloropentane	298.2	9.92				
$C_5H_{10}O$	Cyclopentanol	288.2	18.5	0.10565E+03	−0.44244E+00	0.48657E-03	258-323
$C_5H_{10}O$	Pentanal	293.2	10.00				
$C_5H_{10}O$	2,2-Dimethylpropanal	293.2	9.051	0.18645E+02	−0.32395E-01	−0.16157E-05	280-333
$C_5H_{10}O$	2-Pentanone	293.2	15.45	0.40893E+02	−0.10423E+00	0.60557E-04	204-353
$C_5H_{10}O$	3-Pentanone	293.2	17.00	0.12690E+02	0.95177E-01	−0.27321E-03	233-353
$C_5H_{10}O$	3-Methyl-2-butanone	293.2	10.37	0.30695E+02	−0.10962E+00	0.13810E-03	293-328
$C_5H_{10}O$	Tetrahydropyran	293.2	5.66	0.19793E+02	−0.76071E-01	0.94852E-04	234-333
$C_5H_{10}O$	2-Methyltetrahydrofuran	298.2	6.97				
$C_5H_{10}O_2$	Pentanoic acid	294.4	2.661	0.33491E+01	−0.75156E-02	0.17820E-04	250-344
$C_5H_{10}O_2$	Butyl formate	303.2	6.10	0.21532E+02	−0.84106E-01	0.10952E-03	288-323
$C_5H_{10}O_2$	Isobutyl formate	293.2	6.41				
$C_5H_{10}O_2$	Propyl acetate	293.2	5.62	0.17677E+02	−0.61404E-01	0.69196E-04	253-353
$C_5H_{10}O_2$	Ethyl propanoate	293.2	5.76				
$C_5H_{10}O_2$	Methyl butanoate	301.2	5.48	0.38604E+02	−0.19171E+00	0.27128E-03	301-343
$C_5H_{10}O_2$	Tetrahydrofurfuryl alcohol	303.2	13.48				
$C_5H_{10}O_2S$	3-Methyl sulfolane	298.2	29.4	0.53158E+02	−0.93730E-01	0.47275E-04	298-398
$C_5H_{10}O_3$	Diethyl carbonate	297.2	2.820				
$C_5H_{10}O_3$	Ethyl lactate	303.2	15.4	0.31225E+02	−0.43531E-01	−0.28571E-04	273-373
$C_5H_{10}O_4$	1,2,3-Propanetriol-1-acetate	242.2	38.57	0.10653E+03	−0.26439E+00	−0.62371E-04	215-242
$C_5H_{11}Br$	2-Bromo-2-methylbutane	298.2	9.21				
$C_5H_{11}Br$	1-Bromopentane	299.2	6.31	0.20954E+02	−0.78743E-01	0.98908E-04	183-328
$C_5H_{11}Br$	3-Bromopentane	298.2	8.37				
$C_5H_{11}Br$	1-Bromo-3-methylbutane	291.5	6.33	0.27743E+02	−0.13927E+00	0.22627E-03	123-292
$C_5H_{11}Cl$	1-Chloropentane	293.2	6.654	0.18626E+02	−0.54719E-01	0.47143E-04	273-323
$C_5H_{11}Cl$	1-Chloro-3-methylbutane	292.0	6.10	0.22228E+02	−0.93189E-01	0.12991E-03	171-297
$C_5H_{11}Cl$	2-Chloro-2-methylbutane	222.75	12.31	0.55104E+02	−0.29866E+00	0.47840E-03	201-223
$C_5H_{11}F$	1-Fluoropentane	293.2	3.931				
$C_5H_{11}I$	1-Iodopentane	293.2	5.78	0.15753E+02	−0.50543E-01	0.56401E-04	293-323
$C_5H_{11}I$	3-Iodopentane	293.2	7.432				
$C_5H_{11}I$	1-Iodo-3-methylbutane	292.2	5.6				
$C_5H_{11}I$	2-Iodo-2-methylbutane	293.2	8.192				
$C_5H_{11}N$	Piperidine	293.0	4.33	0.82317E+01	−0.11229E-01	−0.71429E-05	293-333
$C_5H_{11}N$	*N*-Methylpyrrolidine	298.2	32.2				
$C_5H_{11}NO$	2,2-Dimethylpropanamide	298.2	20.13	0.10400E+03	−0.46017E+00	0.60000E-03	298-328
$C_5H_{11}NO$	*N*,*N*-Diethylformamide	293.2	29.6				
$C_5H_{11}NO$	2-Pentanone oxime	293.2	3.3				
$C_5H_{11}NO_2$	Pentyl nitrite	298.2	7.21				
C_5H_{12}	Pentane	293.2	1.8371				
C_5H_{12}	Isopentane	293.2	1.845	0.22384E+01	−0.12985E-02	−0.16182E-06	143-293
C_5H_{12}	Neopentane	296.0	1.769	0.10949E+02	−0.63057E-01	0.10835E-03	251-296
$C_5H_{12}N_2O$	Tetramethylurea	293.2	23.10				
$C_5H_{12}O$	1-Pentanol	298.2	15.13	0.73397E+02	−0.28165E+00	0.28427E-03	213-513
$C_5H_{12}O$	2-Pentanol	298.2	13.71	0.16437E+03	−0.86506E+00	0.11955E-02	273-323
$C_5H_{12}O$	3-Pentanol	298.2	13.35	0.12838E+03	−0.60980E+00	0.75000E-03	288-318
$C_5H_{12}O$	2-Methyl-1-butanol	298.2	15.63	0.14020E+02	0.13948E+00	−0.45000E-03	288-318
$C_5H_{12}O$	3-Methyl-1-butanol	293.2	15.63	0.79733E+02	−0.31272E+00	0.32014E-03	173-513
$C_5H_{12}O$	2-Methyl-2-butanol	298.2	5.78	0.11662E+03	−0.69756E+00	0.10920E-02	268-318
$C_5H_{12}O$	3-Methyl-2-butanol	298.2	12.1				
$C_5H_{12}O$	2,2-Dimethyl-1-propanol	333.2	8.35	0.92350E+02	−0.41870E+00	0.50000E-03	333-373

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
$C_5H_{12}O_2$	1,2-Pentanediol	296.8	17.31	0.18436E+03	−0.10682E+01	0.17037E-02	197-297
$C_5H_{12}O_2$	1,4-Pentanediol	295.7	26.74	0.13568E+03	−0.59198E+00	0.75398E-03	193-318
$C_5H_{12}O_2$	1,5-Pentanediol	293.2	26.2	0.11858E+03	−0.45920E+00	0.49341E-03	243-343
$C_5H_{12}O_2$	2,3-Pentanediol	296.9	17.37	0.95876E+02	−0.46463E+00	0.67434E-03	238-297
$C_5H_{12}O_2$	2,4-Pentanediol	294.2	24.69	0.11914E+03	−0.52569E+00	0.69607E-03	224-294
$C_5H_{12}O_2$	Diethoxymethane	293.2	2.527	0.25294E+01	0.73988E-04	−0.28331E-06	227-293
$C_5H_{12}O_4$	Tetramethoxymethane	293.2	2.40				
$C_5H_{12}O_5$	Xylitol	293.2	40.0				
$C_5H_{12}S$	1-Pentanethiol	293.2	4.847	0.71131E+01	−0.30228E-02	−0.16414E-04	273-333
$C_5H_{12}S$	2-Methyl-2-butanethiol	293.2	5.087	0.15116E+02	−0.50700E-01	0.56250E-04	273-333
$C_5H_{12}S_4$	Tetrakis(methylthio)methane	343.2	2.818				
$C_5H_{13}N$	Pentylamine	293.2	4.27	0.11274E+02	−0.34965E-01	0.37706E-04	223-353
$C_5H_{13}N_3$	1,1,3,3-Tetramethylguanidine	298.2	11.5				
$C_5H_{14}OSi$	Ethoxytrimethylsilane	298.2	3.013				
C_6F_6	Hexafluorobenzene	298.2	2.029	0.24041E+01	−0.83086E-03	−0.14286E-05	298-338
C_6F_{14}	Perfluorohexane	298.2	1.76				
$C_6H_3N_3O_7$	2,4,6-Trinitrophenol	294.2	4.0				
C_6H_4BrF	1-Bromo-2-fluorobenzene	298.2	4.72				
C_6H_4BrF	1-Bromo-3-fluorobenzene	298.2	4.85				
C_6H_4BrF	1-Bromo-4-fluorobenzene	298.2	2.60				
$C_6H_4BrNO_2$	1-Bromo-3-nitrobenzene	328.2	20.2	0.81413E+02	−0.27645E+00	0.27367E-03	328-413
$C_6H_4Br_2$	*o*-Dibromobenzene	293.2	7.86	−0.81849E-02	0.62671E-01	−0.12222E-03	293-353
$C_6H_4Br_2$	*m*-Dibromobenzene	293.2	4.81	0.93214E+01	−0.20273E-01	0.16667E-04	293-353
$C_6H_4Br_2$	p-Dibromobenzene	368.2	2.57				
C_6H_4ClF	1-Chloro-2-fluorobenzene	298.2	6.10				
C_6H_4ClF	1-Chloro-3-fluorobenzene	298.2	4.96				
C_6H_4ClF	1-Chloro-4-fluorobenzene	298.2	3.34				
$C_6H_4ClNO_2$	1-Chloro-2-nitrobenzene	323.2	37.7	0.16800E+03	−0.59708E+00	0.59957E-03	323-436
$C_6H_4ClNO_2$	1-Chloro-3-nitrobenzene	323.2	20.9	0.77193E+02	−0.25118E+00	0.23798E-03	323-433
$C_6H_4ClNO_2$	1-Chloro-4-nitrobenzene	393.2	8.09				
$C_6H_4Cl_2$	*o*-Dichlorobenzene	293.2	10.12	0.13629E+02	0.10622E-02	−0.44444E-04	293-353
$C_6H_4Cl_2$	*m*-Dichlorobenzene	293.2	5.02	0.77565E+01	−0.93333E-02	−0.26880E-14	293-353
$C_6H_4Cl_2$	*p*-Dichlorobenzene	328.2	2.3943	0.26999E+01	−0.35325E-03	−0.17619E-05	328-363
C_6H_4FI	1-Fluoro-2-iodobenzene	298.2	8.22				
C_6H_4FI	1-Fluoro-4-iodobenzene	298.2	3.12				
$C_6H_4F_2$	*o*-Difluorobenzene	301.2	13.38	0.59107E+02	−0.23611E+00	0.27987E-03	273-323
$C_6H_4F_2$	*m*-Difluorobenzene	301.2	5.01	0.14448E+02	−0.46982E-01	0.51948E-04	273-323
$C_6H_4I_2$	*o*-Diiodobenzene	323.2	5.41	0.31150E+02	−0.14428E+00	0.20000E-03	323-353
$C_6H_4I_2$	*m*-Diiodobenzene	323.2	4.11				
$C_6H_4I_2$	*p*-Diiodobenzene	393.2	2.88				
$C_6H_4N_2$	2-Pyridinecarbonitrile	303.2	93.77	0.45596E+03	−0.17746E+01	0.19105E-02	303-398
$C_6H_4N_2$	3-Pyridinecarbonitrile	323.2	20.54	0.60484E+02	−0.17280E+00	0.15218E-03	323-398
$C_6H_4N_2$	4-Pyridinecarbonitrile	353.2	5.23	0.12533E+02	−0.30115E-01	0.26674E-04	353-398
$C_6H_4N_2O_4$	1,3-Dinitrobenzene	365.2	22.9	0.10406E+03	−0.34133E+00	0.32609E-03	365-413
C_6H_5Br	Bromobenzene	293.2	5.45	0.94100E+01	−0.12537E-01	−0.31127E-05	234-333
C_6H_5Cl	Chlorobenzene	293.2	5.6895	0.19471E+02	−0.70786E-01	0.82466E-04	293-430
C_6H_5ClO	*o*-Chlorophenol	296.2	7.40	0.29755E+02	−0.11256E+00	0.12390E-03	296-448
C_6H_5ClO	*m*-Chlorophenol	293.2	6.255				
C_6H_5ClO	*p*-Chlorophenol	314.2	11.18	0.31997E+02	−0.94241E-01	0.88392E-04	314-453
$C_6H_5ClO_2S$	Benzenesulfonyl chloride	323.2	28.90	0.83886E+02	−0.23405E+00	0.19713E-03	323-473
C_6H_5ClS	4-Chlorobenzenethiol	338.2	3.59				
C_6H_5F	Fluorobenzene	293.2	5.465				
C_6H_5I	Iodobenzene	293.2	4.59	0.89442E+01	−0.20008E-01	0.17641E-04	243-323
C_6H_5NOS	*N*-Sulfinylaniline	298.2	6.97				
$C_6H_5NO_2$	Nitrobenzene	293.0	35.6	0.11212E+03	−0.35211E+00	0.31128E-03	279-533
$C_6H_5NO_3$	*o*-Nitrophenol	323.2	16.50	0.33827E+02	−0.62123E-01	0.26774E-04	323-453
$C_6H_5NO_3$	*m*-Nitrophenol	373.2	35.45	0.18967E+03	−0.66144E+00	0.66532E-03	373-458
$C_6H_5NO_3$	*p*-Nitrophenol	393.2	42.20	0.22901E+03	−0.74264E+00	0.68006E-03	393-463
C_6H_6	Benzene	293.2	2.2825	0.26706E+01	−0.91648E-03	−0.14257E-05	293-513
C_6H_6BrN	*m*-Bromoaniline	293.2	13.0				
C_6H_6ClN	*o*-Chloroaniline	293.2	13.40				
C_6H_6ClN	*m*-Chloroaniline	293.2	13.3				
$C_6H_6N_2O_2$	*o*-Nitroaniline	353.0	47.3	0.18900E+03	−0.56977E+00	0.47484E-03	353-468

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
$C_6H_6N_2O_2$	*m*-Nitroaniline	398.0	35.6	0.20352E+03	−0.66582E+00	0.61310E-03	398-468
$C_6H_6N_2O_2$	*p*-Nitroaniline	428.0	78.5	0.48673E+03	−0.15040E+01	0.12857E-02	428-468
C_6H_6O	Phenol	303.2	12.40	0.63391E+02	−0.24988E+00	0.26930E-03	303-433
$C_6H_6O_2$	Pyrocatechol	388.2	17.57	0.74930E+02	−0.22142E+00	0.18919E-03	388-463
$C_6H_6O_2$	Resorcinol	393.2	13.55	0.30252E+02	−0.56443E-01	0.35578E-04	393-463
C_6H_6S	Benzenethiol	303.2	4.26	0.57155E+01	−0.70336E-02	0.73617E-05	303-358
C_6H_7N	Aniline	293.2	7.06	0.89534E+01	0.38990E-02	−0.36310E-04	293-413
C_6H_7N	2-Methylpyridine	293.2	10.18	0.34560E+02	−0.11980E+00	0.12500E-03	293-333
C_6H_7N	3-Methylpyridine	303.0	11.10	0.19643E+03	−0.11167E+01	0.16667E-02	303-333
C_6H_7N	4-Methylpyridine	293.0	12.2	0.33765E+02	−0.10113E+00	0.93860E-04	274-333
C_6H_7NO	2-Methylpyridine-1-oxide	323.2	36.4	0.11705E+03	−0.35301E+00	0.32000E-03	323-398
C_6H_7NO	3-Methylpyridine-1-oxide	318.2	28.26	0.59851E+02	−0.12682E+00	0.86622E-04	318-398
C_6H_8	1,3-Cyclohexadiene	184.2	2.68				
C_6H_8	1,4-Cyclohexadiene	296.0	2.211	0.27459E+01	−0.16975E-02	−0.36461E-06	232-356
$C_6H_8N_2$	Phenylhydrazine	293.2	7.15				
$C_6H_8N_2$	2,5-Dimethylpyrazine	293.2	2.436				
$C_6H_8N_2$	2,6-Dimethylpyrazine	308.2	2.653				
$C_6H_8O_2$	1,4-Cyclohexanedione	351.2	4.40				
$C_6H_9Cl_3O_2$	Butyl trichloroacetate	293.2	7.480				
$C_6H_9Cl_3O_2$	Isobutyl trichloroacetate	293.2	7.667				
C_6H_9N	Cyclopentanecarbonitrile	293.2	22.68	0.69830E+02	−0.25303E+00	0.31491E-03	201-293
C_6H_{10}	1,5-Hexadiene	294.0	2.125	0.30014E+01	−0.28668E-02	−0.31026E-06	151-294
C_6H_{10}	*cis,cis*-2,4-Hexadiene	297.0	2.163	0.27284E+01	−0.17178E-02	−0.62926E-06	234-351
C_6H_{10}	*trans,trans*-2,4-Hexadiene	297.0	2.123	0.26774E+01	−0.16977E-02	−0.55637E-06	232-353
C_6H_{10}	2-Methyl-1,3-pentadiene*	298.2	2.422				
C_6H_{10}	3-Methyl-1,3-pentadiene	298.2	2.426				
C_6H_{10}	4-Methyl-1,3-pentadiene	293.2	2.599	0.51328E+01	−0.12774E-01	0.14215E-04	198-323
C_6H_{10}	2,3-Dimethyl-1,3-butadiene	293.2	2.102	0.26258E+01	−0.17990E-02	0.12035E-06	223-323
C_6H_{10}	1-Hexyne	296.0	2.621	0.58591E+01	−0.17099E-01	0.20856E-04	184-296
C_6H_{10}	Cyclohexene	293.2	2.2176	0.30598E+01	−0.39841E-02	0.37554E-05	141-313
$C_6H_{10}O$	Butoxyacetylene	298.2	6.62				
$C_6H_{10}O$	Cyclohexanone	293.0	16.1	0.41577E+02	−0.11463E+00	0.92454E-04	253-423
$C_6H_{10}O$	Mesityl oxide	273.2	15.6				
$C_6H_{10}O_2$	Ethyl 2-butenoate	293.2	5.4				
$C_6H_{10}O_2$	Ethyl methacrylate	303.2	5.68	0.40962E+02	−0.20520E+00	0.29286E-03	303-343
$C_6H_{10}O_3$	Ethyl acetoacetate	293.2	14.0				
$C_6H_{10}O_3$	Propanoic anhydride	293.2	18.30				
$C_6H_{10}O_4$	Monomethyl glutarate	293.2	8.37	0.16779E+02	−0.39839E-01	0.38095E-04	293-363
$C_6H_{10}O_4$	Diethyl oxalate	293.2	8.266	0.21938E+02	−0.66226E-01	0.66800E-04	293-368
$C_6H_{10}O_4$	Dimethyl succinate	293.2	7.19	0.13551E+02	−0.23109E-01	0.55440E-05	293-433
$C_6H_{10}O_4$	Ethylene glycol diacetate	290.2	7.7	0.25093E+02	−0.95171E-01	0.12224E-03	223-290
$C_6H_{11}Br$	Bromocyclohexane	303.2	8.0026				
$C_6H_{11}BrO_2$	Ethyl 2-bromobutanoate	303.2	8.57	0.49005E+02	−0.23193E+00	0.32500E-03	303-333
$C_6H_{11}BrO_2$	Ethyl 2-bromo-2-methylpropanoate	303.2	8.55	0.77044E+02	−0.40784E+00	0.60000E-03	303-333
$C_6H_{11}Cl$	Chlorocyclohexane	303.2	7.9505				
$C_6H_{11}N$	Hexanenitrile	298.2	17.26				
$C_6H_{11}N$	4-Methylpentanenitrile	295.2	17.5				
$C_6H_{11}NO$	Cyclohexanone oxime	362.2	3.04				
C_6H_{12}	1-Hexene	294.0	2.077	0.31476E+01	−0.50003E-02	0.46673E-05	149-294
C_6H_{12}	*trans*-2-Hexene	295.0	1.978	0.24338E+01	−0.11323E-02	−0.13720E-05	157-295
C_6H_{12}	*cis*-3-Hexene	296.0	2.069	0.30691E+01	−0.45458E-02	0.39898E-05	155-296
C_6H_{12}	*trans*-3-Hexene	293.2	1.954				
C_6H_{12}	Cyclohexane	293.2	2.0243	0.24293E+01	−0.12095E-02	−0.58741E-06	283-333
C_6H_{12}	Methylcyclopentane	293.2	1.9853	0.21587E+01	−0.22450E-03	−0.12500E-05	293-323
C_6H_{12}	Ethylcyclobutane	293.2	1.965				
$C_6H_{12}Br_2$	1,6-Dibromohexane	298.2	8.52	−0.55185E+01	0.11746E+00	−0.23658E-03	274-328
$C_6H_{12}Br_2$	3,4-Dibromohexane	298.2	6.732				
$C_6H_{12}Cl_2$	1,6-Dichlorohexane	308.2	8.60	0.11277E+02	0.67200E-02	−0.50000E-04	308-338
$C_6H_{12}O$	1-Methylcyclopentanol	310.1	7.11	0.75444E+02	−0.36617E+00	0.47021E-03	310-333
$C_6H_{12}O$	Isobutyl vinyl ether	293.2	3.34	0.48060E+01	−0.50000E-02	−0.41495E-14	293-323
$C_6H_{12}O$	2-Hexanone	293.2	14.56	0.70378E+02	−0.29385E+00	0.35289E-03	243-293
$C_6H_{12}O$	4-Methyl-2-pentanone	293.2	13.11	0.36341E+02	−0.97119E-01	0.61896E-04	204-373
$C_6H_{12}O$	3,3-Dimethyl-2-butanone	293.2	12.73	0.66857E+02	−0.28552E+00	0.34422E-03	243-293

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
$C_6H_{12}O$	Cyclohexanol	293.2	16.40	0.10173E+03	−0.43072E+00	0.47926E-03	293-423
$C_6H_{12}O_2$	Hexanoic acid	298.2	2.600	0.21730E+01	0.14840E-02	−0.16526E-06	298-433
$C_6H_{12}O_2$	2-Ethylbutanoic acid	296.2	2.72				
$C_6H_{12}O_2$	*tert*-Butylacetic acid	296.2	2.85				
$C_6H_{12}O_2$	Pentyl formate	292.2	5.7				
$C_6H_{12}O_2$	Isopentyl formate	288.2	5.44	0.29257E+02	−0.14028E+00	0.20000E-03	288-323
$C_6H_{12}O_2$	Butyl acetate	293.2	5.07	0.13825E+02	−0.43994E-01	0.48214E-04	253-353
$C_6H_{12}O_2$	*sec*-Butyl acetate	293.2	5.135	0.12427E+02	−0.32035E-01	0.24286E-04	273-323
$C_6H_{12}O_2$	*tert*-Butyl acetate	293.2	5.672	0.55435E+02	−0.30494E+00	0.46107E-03	273-323
$C_6H_{12}O_2$	Isobutyl acetate	293.2	5.068	0.14323E+02	−0.46048E-01	0.49286E-04	273-323
$C_6H_{12}O_2$	Propyl propanoate	293.2	5.249				
$C_6H_{12}O_2$	Ethyl butanoate	301.2	5.18	0.48698E+02	−0.25660E+00	0.37237E-03	301-343
$C_6H_{12}O_2$	Methyl pentanoate	293.2	4.992				
$C_6H_{12}O_2$	Diacetone alcohol	298.2	18.2				
$C_6H_{12}O_3$	Ethylene glycol monoethyl ether acetate	303.2	7.567	0.23290E+02	−0.71566E-01	0.65000E-04	303-323
$C_6H_{12}S$	Cyclohexanethiol	298.2	5.420				
$C_6H_{13}Br$	1-Bromohexane	298.2	5.82	0.15233E+02	−0.44385E-01	0.43039E-04	274-328
$C_6H_{13}Cl$	1-Chlorohexane	293.2	6.104	0.15994E+02	−0.43647E-01	0.33393E-04	273-323
$C_6H_{13}ClO$	6-Chloro-1-hexanol	242.2	21.6	−0.73364E+01	0.46377E+00	−0.14202E-02	195-242
$C_6H_{13}I$	1-Iodohexane	293.3	5.35	0.16685E+02	−0.61309E-01	0.77262E-04	293-323
$C_6H_{13}N$	Cyclohexylamine	293.2	4.547				
$C_6H_{13}NO$	*N*-Propylpropanamide	298.2	118.1	0.58846E+03	−0.22012E+01	0.20870E-02	298-328
$C_6H_{13}NO$	*N*-Butylacetamide	293.2	104.0	0.70739E+03	−0.37369E+01	0.71585E-02	253-493
$C_6H_{13}NO$	*N,N*-Diethylacetamide	293.2	32.1				
C_6H_{14}	Hexane	293.2	1.8865	0.19768E+01	0.70933E-03	−0.34470E-05	293-473
C_6H_{14}	2-Methylpentane	293.2	1.886	0.20745E+01	0.50871E-03	−0.39286E-05	273-323
C_6H_{14}	3-Methylpentane	293.2	1.886	0.24739E+01	−0.23190E-02	0.10714E-05	273-323
C_6H_{14}	2,2-Dimethylbutane	293.2	1.869	0.22740E+01	−0.96229E-03	−0.14286E-05	273-313
C_6H_{14}	2,3-Dimethylbutane	293.2	1.889	0.24305E+01	−0.20081E-02	0.53571E-06	273-323
$C_6H_{14}O$	1-Hexanol	293.2	13.03	0.62744E+02	−0.24214E+00	0.24704E-03	233-513
$C_6H_{14}O$	2-Hexanol	298.2	11.06				
$C_6H_{14}O$	3-Hexanol	298.2	9.66				
$C_6H_{14}O$	3-Methyl-1-pentanol	298.2	15.2				
$C_6H_{14}O$	3-Methyl-3-pentanol	293.2	4.322				
$C_6H_{14}O$	2-Ethyl-1-butanol	362.2	6.19				
$C_6H_{14}O$	2,2-Dimethyl-1-butanol	293.2	10.5	0.14054E+03	−0.72925E+00	0.97821E-03	243-393
$C_6H_{14}O$	Dipropyl ether	297.0	3.38	0.14600E+02	−0.72670E-01	0.11742E-03	161-297
$C_6H_{14}O$	Diisopropyl ether	303.2	3.805				
$C_6H_{14}OS$	Dipropyl sulfoxide	303.2	30.37	0.84868E+02	−0.23486E+00	0.18198E-03	303-373
$C_6H_{14}O_2$	2-Methyl-2,4-pentanediol	293.2	25.86	0.14531E+03	−0.65285E+00	0.83503E-03	203-333
$C_6H_{14}O_2$	Ethylene glycol diethyl ether	293.2	3.90	0.99099E+01	−0.33403E-01	0.44048E-04	223-303
$C_6H_{14}O_2S$	Dipropyl sulfone	303.2	32.62	0.70195E+02	−0.15008E+00	0.86506E-04	303-398
$C_6H_{14}O_3$	1,2,6-Hexanetriol	285.3	31.5	0.26127E+03	−0.14552E+01	0.22765E-02	261-285
$C_6H_{14}O_3$	Diethylene glycol dimethyl ether	298.2	7.23	0.28291E+02	−0.11236E+00	0.14000E-03	298-333
$C_6H_{14}O_4$	Triethylene glycol	293.2	23.69	0.91845E+02	−0.33827E+00	0.36062E-03	253-333
$C_6H_{14}O_6$	*D*-Glucitol	353.2	35.5				
$C_6H_{14}O_6$	*D*-Mannitol	443.2	24.6				
$C_6H_{14}S$	1-Hexanethiol	293.2	4.436	0.11774E+02	−0.37298E-01	0.41875E-04	273-333
$C_6H_{15}B$	Triethylborane	293.2	1.974				
$C_6H_{15}N$	Hexylamine	293.2	4.08	0.80244E+01	−0.16627E-01	0.10874E-04	253-373
$C_6H_{15}N$	Dipropylamine	293.2	2.923	0.11376E+02	−0.49796E-01	0.71792E-04	243-323
$C_6H_{15}N$	Triethylamine	293.2	2.418	0.29205E+01	−0.14007E-02	−0.13469E-05	233-323
$C_6H_{15}OP$	Triethylphosphine oxide	323.2	35.5				
$C_6H_{15}O_4P$	Triethyl phosphate	298.2	13.20	0.61230E+02	−0.26047E+00	0.33333E-03	298-333
$C_6H_{15}PS$	Triethylphosphine sulfide	371.2	39.0				
$C_6H_{16}O_2Si$	Diethoxydimethylsilane	298.2	3.216				
$C_6H_{16}Si$	Triethylsilane	293.2	2.323				
$C_6H_{18}N_3OP$	Hexamethylphosphoric triamide	293.2	31.3	0.95666E+02	−0.29769E+00	0.26407E-03	283-363
$C_6H_{18}N_4$	*N,N′*-Bis(2-aminoethyl)-1,2-ethanediamine	293.2	10.76	0.50699E+02	−0.21730E+00	0.27582E-03	213-333
$C_6H_{18}OSi_2$	Hexamethyldisiloxane	293.2	2.179	0.34537E+01	−0.61530E-02	0.61544E-05	213-313
$C_6H_{18}O_3Si_3$	Hexamethylcyclotrisiloxane	343.2	2.139				

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
$C_6H_{19}NSi_2$	Hexamethyldisilazane	294.2	2.273	0.23358E+01	0.16127E-02	−0.62078E-05	294-333
C_7F_{14}	Perfluoromethylcyclohexane	298.2	1.82				
C_7F_{16}	Perfluoroheptane	289.2	1.847				
$C_7H_3Cl_5$	2,3,4,5,6-Pentachlorotoluene	293.2	4.8				
C_7H_4ClNO	4-Chlorophenyl isocyanate	288.2	3.177	0.40896E+01	−0.31667E-02		288-348
C_7H_5BrO	Benzoyl bromide	293.2	21.33	0.84231E+02	−0.31089E+00	0.32857E-03	283-313
C_7H_5ClO	Benzoyl chloride	293.2	23.0				
C_7H_5FO	Benzoyl fluoride	293.2	22.7				
$C_7H_5F_3$	(Trifluoromethyl)benzene	298.2	9.22				
C_7H_5N	Benzonitrile	293.2	25.9	0.57605E+02	−0.13354E+00	0.87767E-04	273-453
C_7H_5NO	Phenyl isocyanate	293.2	8.940	0.17541E+02	−0.29790E-01	0.15476E-05	293-353
$C_7H_6ClNO_2$	4-Chloro-3-nitrotoluene	301.2	28.07				
$C_7H_6Cl_2$	2,4-Dichlorotoluene	301.2	5.68				
$C_7H_6Cl_2$	2,6-Dichlorotoluene	301.2	3.36				
$C_7H_6Cl_2$	3,4-Dichlorotoluene	301.2	9.39				
$C_7H_6Cl_2$	(Dichloromethyl)benzene	293.2	6.9				
C_7H_6O	Benzaldehyde	293.2	17.85	0.35046E+02	−0.61271E-01	0.16222E-04	301-346
$C_7H_6O_2$	Salicylaldehyde	293.2	18.35	0.51315E+02	−0.15379E+00	0.14111E-03	289-453
C_7H_7Br	*o*-Bromotoluene	293.2	4.641	0.10229E+02	−0.25050E-01	0.20357E-04	273-323
C_7H_7Br	*m*-Bromotoluene	293.2	5.566	0.11522E+02	−0.24946E-01	0.15714E-04	273-323
C_7H_7Br	*p*-Bromotoluene	293.2	5.503	0.10014E+02	−0.13918E-01	−0.50000E-05	273-293
C_7H_7Br	(Bromomethyl)benzene	293.2	6.658	0.18482E+02	−0.57207E-01	0.57321E-04	273-323
C_7H_7BrO	*o*-Bromoanisole	303.2	8.96	0.12023E+02	−0.59116E-02	−0.13787E-04	303-358
C_7H_7BrO	*p*-Bromoanisole	303.2	7.40	0.74367E+01	0.12648E-01	−0.42128E-04	303-358
C_7H_7Cl	*o*-Chlorotoluene	293.2	4.721	0.11507E+02	−0.31148E-01	0.27143E-04	273-323
C_7H_7Cl	*m*-Chlorotoluene	293.2	5.763	0.13921E+02	−0.37186E-01	0.31786E-04	273-323
C_7H_7Cl	*p*-Chlorotoluene	293.2	6.25	0.20265E+01	0.40060E-01	−0.87500E-04	293-333
C_7H_7Cl	(Chloromethyl)benzene	293.2	6.854	0.17108E+02	−0.45285E-01	0.35000E-04	273-323
C_7H_7ClO	*p*-Chloroanisole	293.2	7.84	0.64019E+01	0.30560E-01	−0.87500E-04	293-333
$C_7H_7ClO_2S$	*p*-Toluenesulfonyl chloride	343.2	22.6				
$C_7H_7ClO_3S$	4-Methoxybenzenesulfonyl chloride	314.2	27.2				
C_7H_7F	*o*-Fluorotoluene	298.2	4.23				
C_7H_7F	*m*-Fluorotoluene	298.2	5.41				
C_7H_7F	*p*-Fluorotoluene	298.2	5.88				
C_7H_7I	*p*-Iodotoluene	308.2	4.4				
C_7H_7N	2-Vinylpyridine	293.2	9.126				
C_7H_7N	4-Vinylpyridine	293.2	10.50				
$C_7H_7NO_2$	Benzyl nitrite	298.2	7.78				
$C_7H_7NO_2$	*o*-Nitrotoluene	293.0	26.26	0.10420E+03	−0.41726E+00	0.51607E-03	273-323
$C_7H_7NO_2$	*m*-Nitrotoluene	303.2	24.95	0.62492E+02	−0.16235E+00	0.12844E-03	303-403
$C_7H_7NO_2$	*p*-Nitrotoluene	331.2	22.2				
$C_7H_7NO_2S$	4-Nitrothioanisole	346.0	21.7				
$C_7H_7NO_3$	2-Nitroanisole	293.2	45.75	0.16684E+03	−0.58196E+00	0.57382E-03	293-423
$C_7H_7NO_3$	3-Nitroanisole	318.2	25.7	0.65402E+02	−0.16460E+00	0.12560E-03	318-443
$C_7H_7NO_3$	4-Nitroanisole	338.2	26.95	0.59811E+02	−0.10955E+00	0.36042E-04	338-443
C_7H_8	Toluene	296.35	2.379	0.32584E+01	−0.34410E-02	0.15937E-05	207-316
C_7H_8O	*o*-Cresol	298.2	6.76	0.21633E+02	−0.71069E-01	0.70590E-04	298-453
C_7H_8O	*m*-Cresol	298.2	12.44	0.81716E+02	−0.35039E+00	0.39878E-03	274-463
C_7H_8O	*p*-Cresol	298.2	13.05	0.70253E+02	−0.28870E+00	0.31979E-03	298-453
C_7H_8O	Benzyl alcohol	303.2	11.916	0.13661E+03	−0.72127E+00	0.10225E-02	303-333
C_7H_8O	Anisole	294.2	4.30	0.10887E+02	−0.32372E-01	0.33629E-04	294-413
$C_7H_8O_2$	2-Methoxyphenol	298.2	11.95	0.31751E+02	−0.88173E-01	0.72953E-04	291-448
$C_7H_8O_2$	3-Methoxyphenol	298.2	11.59	0.37279E+02	−0.12113E+00	0.11698E-03	298-433
$C_7H_8O_2$	4-Methoxyphenol	333.7	11.05	0.39483E+02	−0.12142E+00	0.10841E-03	334-453
$C_7H_8O_2S$	Ethyl thiophene-2-carboxylate	293.2	6.18				
$C_7H_8O_2S$	Methyl phenyl sulfone	373.2	37.9				
C_7H_8S	Benzenemethanethiol	298.2	4.705	0.16628E+02	−0.68276E-01	0.94636E-04	298-358
C_7H_8S	4-Methylbenzenethiol	323.2	4.74	0.87052E+01	−0.15347E-01	0.95238E-05	323-358
C_7H_8S	(Methylthio)benzene	303.2	4.88	0.21841E+02	−0.97630E-01	0.13750E-03	303-343
C_7H_9N	Benzylamine	293.2	5.18				
C_7H_9N	*o*-Methylaniline	298.2	6.138	0.10988E+02	−0.18976E-01	0.91958E-05	298-398
C_7H_9N	*m*-Methylaniline	298.2	5.816	0.13477E+02	−0.35551E-01	0.33135E-04	298-398
C_7H_9N	*p*-Methylaniline	333.2	5.058	0.78897E+01	−0.10196E-01	0.51190E-05	333-403

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
C_7H_9N	*N*-Methylaniline	293.2	5.96				
C_7H_9N	2-Ethylpyridine	293.2	8.33	0.36397E+02	−0.15070E+00	0.18750E-03	293-333
C_7H_9N	4-Ethylpyridine	293.2	10.98	−0.73831E+01	0.14326E+00	−0.27500E-03	293-333
C_7H_9N	2,4-Dimethylpyridine	293.2	9.60	0.25895E+02	−0.73900E-01	0.62500E-04	293-333
C_7H_9N	2,6-Dimethylpyridine	293.2	7.33	0.17714E+02	−0.39080E-01	0.12500E-04	293-333
C_7H_9NO	2,6-Dimethylpyridine-1-oxide	298.2	46.11	0.22765E+03	−0.90760E+00	0.10011E-02	298-398
C_7H_9NO	*o*-Methoxyaniline	303.2	5.230	0.79911E+01	−0.92183E-02	0.37879E-06	303-393
C_7H_9NO	*m*-Methoxyaniline	298.2	8.76	0.28179E+02	−0.97840E-01	0.11027E-03	289-393
C_7H_9NO	*p*-Methoxyaniline	333.2	7.85	0.30149E+02	−0.10523E+00	0.11467E-03	333-453
$C_7H_{10}N_2$	1-Methyl-1-phenylhydrazine	292.2	7.3				
$C_7H_{11}Cl_3O_2$	Isopentyl trichloroacetate	293.2	7.287				
C_7H_{12}	1,6-Heptadiene	293.0	2.161	0.30815E+01	−0.36095E-02	0.16354E-05	184-293
C_7H_{12}	Cycloheptene	295.0	2.265	0.32309E+01	−0.42373E-02	0.32572E-05	227-363
$C_7H_{12}O$	Cycloheptanone	298.2	13.16	0.17511E+03	−0.11221E+01	0.19417E-02	258-298
$C_7H_{12}O$	2-Methylcyclohexanone	293.2	14.0				
$C_7H_{12}O$	3-Methylcyclohexanone	293.2	12.4				
$C_7H_{12}O$	4-Methylcyclohexanone	293.2	12.35				
$C_7H_{12}O_2$	Cyclohexanecarboxylic acid	304.2	2.67				
$C_7H_{12}O_2$	Cyclohexyl formate	293.2	6.47				
$C_7H_{12}O_2$	Butyl acrylate	301.2	5.25	0.38296E+02	−0.19109E+00	0.27006E-03	301-343
$C_7H_{12}O_4$	Monomethyl adipate	293.2	6.69	0.11962E+02	−0.23973E-01	0.20608E-04	293-433
$C_7H_{12}O_4$	Diethyl malonate	304.2	7.550	0.14809E+02	−0.31207E-01	0.24066E-04	304-393
$C_7H_{12}O_4$	Dimethyl glutarate	293.2	7.87	0.20697E+02	−0.57794E-01	0.48405E-04	293-433
$C_7H_{12}O_5$	1,2,3-Propanetriol-1,3-diacetate	288.2	9.80	0.28321E+02	−0.89073E-01	0.86891E-04	258-374
C_7H_{14}	1-Heptene	293.2	2.092	0.21755E+01	0.13896E-02	−0.57049E-05	273-323
C_7H_{14}	2-Methyl-2-hexene	293.2	2.962				
C_7H_{14}	3-Ethyl-2-pentene	293.2	2.051				
C_7H_{14}	Cycloheptane	293.2	2.0784	0.25136E+01	−0.15089E-02	0.84915E-07	278-333
C_7H_{14}	Methylcyclohexane	293.2	2.024				
$C_7H_{14}Br_2$	1,2-Dibromoheptane	298.2	3.77				
$C_7H_{14}Br_2$	2,3-Dibromoheptane	298.2	5.08				
$C_7H_{14}Br_2$	3,4-Dibromoheptane	298.2	4.70				
$C_7H_{14}Cl_2$	1,7-Dichloroheptane	298.2	8.34				
$C_7H_{14}O$	1-Heptanal	295.2	9.07				
$C_7H_{14}O$	2-Heptanone	293.2	11.95	0.38348E+02	−0.12531E+00	0.12005E-03	253-413
$C_7H_{14}O$	3-Heptanone	293.2	12.7				
$C_7H_{14}O$	4-Heptanone	293.2	12.60	0.41520E+02	−0.13839E+00	0.13497E-03	253-393
$C_7H_{14}O$	5-Methyl-2-hexanone	293.2	13.53	0.52353E+02	−0.17695E+00	0.15195E-03	293-333
$C_7H_{14}O$	Cyclohexanemethanol	333.2	9.70	0.10164E+03	−0.45839E+00	0.54762E-03	333-368
$C_7H_{14}O$	2-Methylcyclohexanol*	293.2	9.375	0.17315E+03	−0.98794E+00	0.14634E-02	273-323
$C_7H_{14}O$	3-Methylcyclohexanol*	293.2	13.79	0.65896E+02	−0.21954E+00	0.14107E-03	273-323
$C_7H_{14}O$	4-Methylcyclohexanol*	293.2	13.45	0.65021E+02	−0.22896E+00	0.17946E-03	273-323
$C_7H_{14}O_2$	Heptanoic acid	288.2	3.04	0.36423E+01	−0.31996E-02	0.39362E-05	288-423
$C_7H_{14}O_2$	Pentyl acetate	293.2	4.79	0.12091E+02	−0.36536E-01	0.39732E-04	253-353
$C_7H_{14}O_2$	Isopentyl acetate	293.2	4.72				
$C_7H_{14}O_2$	Butyl propanoate	293.2	4.838				
$C_7H_{14}O_2$	Propyl butanoate	293.2	4.3				
$C_7H_{14}O_2$	Ethyl pentanoate	291.2	4.71				
$C_7H_{14}O_2$	Ethyl 3-methylbutanoate	293.2	4.71				
$C_7H_{14}O_2$	Methyl hexanoate	293.2	4.615				
$C_7H_{15}Br$	1-Bromoheptane	303.2	5.255	0.15289E+02	−0.50621E-01	0.57753E-04	203-343
$C_7H_{15}Br$	2-Bromoheptane	295.2	6.46				
$C_7H_{15}Br$	4-Bromoheptane	295.2	6.81				
$C_7H_{15}Cl$	1-Chloroheptane	293.2	5.521	0.14279E+02	−0.39431E-01	0.32321E-04	273-323
$C_7H_{15}Cl$	2-Chloroheptane	295.2	6.52				
$C_7H_{15}Cl$	3-Chloroheptane	295.2	6.70				
$C_7H_{15}Cl$	4-Chloroheptane	295.2	6.54				
$C_7H_{15}I$	1-Iodoheptane	298.2	4.92	0.11856E+02	−0.33493E-01	0.34368E-04	294-323
$C_7H_{15}I$	3-Iodoheptane	295.2	6.39				
C_7H_{16}	Heptane	293.2	1.9209	0.24740E+01	−0.22577E-02	0.12428E-05	273-373
C_7H_{16}	2-Methylhexane	293.2	1.9221	0.24759E+01	−0.22535E-02	0.12500E-05	293-323
C_7H_{16}	3-Methylhexane	293.2	1.920	0.27089E+01	−0.37908E-02	0.37500E-05	273-323
C_7H_{16}	3-Ethylpentane	293.2	1.942	0.23771E+01	−0.15140E-02	0.10093E-06	163-363

Mol. form.	Name	*T*/K	ε_r	*a*	*b*	*c*	Range/K
C_7H_{16}	2,2-Dimethylpentane	293.2	1.915	0.23414E+01	−0.14362E-02	−0.51322E-07	153-353
C_7H_{16}	2,3-Dimethylpentane	293.2	1.929	0.25637E+01	−0.26328E-02	0.16071E-05	273-323
C_7H_{16}	2,4-Dimethylpentane	293.2	1.902	0.23979E+01	−0.17436E-02	0.17857E-06	273-323
C_7H_{16}	3,3-Dimethylpentane	291.3	1.9419	0.24007E+01	−0.16802E-02	0.36069E-06	291-322
C_7H_{16}	2,2,3-Trimethylbutane	293.2	1.930				
$C_7H_{16}O$	1-Heptanol	293.2	11.75	0.60662E+02	−0.24049E+00	0.25155E-03	239-513
$C_7H_{16}O$	2-Heptanol	293.7	9.72	0.10050E+03	−0.49793E+00	0.64504E-03	207-365
$C_7H_{16}O$	3-Heptanol	296.1	7.07	0.19586E+03	−0.11465E+01	0.17175E-02	248-349
$C_7H_{16}O$	4-Heptanol	296.2	6.18	0.28995E+03	−0.18499E+01	0.30109E-02	270-301
$C_7H_{16}O$	2-Methyl-2-hexanol	297.0	3.257				
$C_7H_{16}O$	3-Methyl-2-hexanol	297.2	4.990	0.59724E+02	−0.32417E+00	0.47058E-03	244-372
$C_7H_{16}O$	3-Methyl-3-hexanol	298.2	3.248				
$C_7H_{16}O$	3-Ethyl-3-pentanol	293.2	3.158				
$C_7H_{16}O$	2,2-Dimethyl-1-pentanol	293.2	6.020	0.37318E+02	−0.17095E+00	0.22022E-03	283-393
$C_7H_{16}O$	Ethyl pentyl ether	296.2	3.6				
$C_7H_{16}O$	Ethyl isopentyl ether	293.2	3.955	0.66541E+01	−0.55450E-02	−0.12500E-04	293-323
$C_7H_{16}O_3$	Triethoxymethane	293.2	4.779				
$C_7H_{16}S$	1-Heptanethiol	293.2	4.194	0.71333E+01	−0.97320E-02	−0.12500E-05	273-333
$C_7H_{17}N$	Heptylamine	293.2	3.81	0.87794E+01	−0.24363E-01	0.25325E-04	253-373
$C_7H_{18}O_3Si$	Triethoxymethylsilane	298.2	3.845				
$C_8H_4F_6$	1,3-Bis(trifluoromethyl)benzene	303.2	5.98				
C_8H_6	Phenylacetylene	298.2	2.98				
$C_8H_6Cl_2$	2,5-Dichlorostyrene	298.2	2.58				
$C_8H_6Cl_4$	1,2,3,4-Tetrachloro-5,6-dimethylbenzene	293.2	8.0				
$C_8H_6Cl_4$	1,2,3,5-Tetrachloro-4,6-dimethylbenzene	293.2	5.4				
C_8H_6O	Phenoxyacetylene	298.2	4.76				
C_8H_7N	Benzeneacetonitrile	299.2	17.87	0.82175E+02	−0.37416E+00	0.53220E-03	299-343
$C_8H_7NO_2$	4-Methoxyphenyl isocyanate	333.2	10.26	0.20780E+02	−0.31571E-01		333-403
$C_8H_7NO_4$	Methyl 2-nitrobenzoate	300.1	27.76				
C_8H_8	Styrene	293.2	2.4737	0.44473E+01	−0.11422E-01	0.16000E-04	293-313
C_8H_8O	Acetophenone	298.2	17.44	0.26099E+02	0.64048E-02	−0.11905E-03	298-333
$C_8H_8O_2$	Benzeneacetic acid	353.2	3.47	0.24104E+01	0.30000E-02		353-393
$C_8H_8O_2$	Benzyl formate	303.2	6.34	0.26162E+02	−0.11026E+00	0.14787E-03	303-358
$C_8H_8O_2$	Phenyl acetate	298.2	5.403	0.11327E+02	−0.26707E-01	0.22938E-04	298-404
$C_8H_8O_2$	Methyl benzoate	302.7	6.642	0.17486E+02	−0.51027E-01	0.50222E-04	303-393
$C_8H_8O_2$	(Hydroxyacetyl)benzene	298.2	21.33	0.42286E+02	−0.69215E-01	−0.35714E-05	298-368
$C_8H_8O_2$	4-Methoxybenzaldehyde	303.2	22.0				
$C_8H_8O_3$	Methyl salicylate	314.4	8.80	0.20501E+02	−0.39045E-01	0.68298E-05	223-398
C_8H_9Br	1-Bromo-2-ethylbenzene	298.2	5.55				
C_8H_9Br	1-Bromo-3-ethylbenzene	298.2	5.56				
C_8H_9Br	1-Bromo-4-ethylbenzene	298.2	5.42				
C_8H_9BrO	1-Bromo-2-ethoxybenzene	313.2	7.04	0.23146E+02	−0.75753E-01	0.77778E-04	313-358
C_8H_9Cl	1-Chloro-2-ethylbenzene	298.2	4.36				
C_8H_9Cl	1-Chloro-3-ethylbenzene	298.2	5.18				
C_8H_9Cl	1-Chloro-4-ethylbenzene	298.2	5.16				
$C_8H_9NO_2$	1-Ethyl-2-nitrobenzene	273.4	21.9				
$C_8H_9NO_2$	Methyl 2-aminobenzoate	298.2	21.9				
$C_8H_9NO_2$	Ethyl 4-pyridinecarboxylate	293.2	8.95				
C_8H_{10}	Ethylbenzene	293.2	2.4463	0.35969E+01	−0.53169E-02	0.47500E-05	293-323
C_8H_{10}	*o*-Xylene	293.2	2.562	0.36163E+01	−0.40177E-02	0.14286E-05	273-323
C_8H_{10}	*m*-Xylene	293.2	2.359	0.28421E+01	−0.10191E-02	−0.21429E-05	273-323
C_8H_{10}	*p*-Xylene	293.2	2.2735	0.23140E+01	0.97221E-03	−0.37500E-05	293-363
$C_8H_{10}O$	2,3-Xylenol	343.2	4.81	0.14399E+02	−0.41438E-01	0.39244E-04	343-433
$C_8H_{10}O$	2,4-Xylenol	303.2	5.060	0.22125E+02	−0.85543E-01	0.96548E-04	303-363
$C_8H_{10}O$	2,5-Xylenol	338.2	5.36	0.18049E+02	−0.54991E-01	0.51656E-04	338-455
$C_8H_{10}O$	2,6-Xylenol	313.2	4.90	0.12284E+02	−0.32996E-01	0.29867E-04	313-453
$C_8H_{10}O$	3,4-Xylenol	333.2	9.02	0.54423E+02	−0.21153E+00	0.22508E-03	333-453
$C_8H_{10}O$	3,5-Xylenol	323.2	9.06	0.54251E+02	−0.21647E+00	0.23542E-03	323-453
$C_8H_{10}O$	Benzeneethanol	293.2	12.31	0.12170E+03	−0.63124E+00	0.87776E-03	278-333
$C_8H_{10}O$	1-Phenylethanol	293.2	8.77	0.32971E+02	−0.12042E+00	0.12809E-03	293-423
$C_8H_{10}O$	Phenetole	293.2	4.216	−0.15043E+02	0.13752E+00	−0.24500E-03	293-313

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
$C_8H_{10}O$	2-Methylanisole	293.2	3.502	0.50825E+01	−0.62297E-02	0.28571E-05	293-333
$C_8H_{10}O$	3-Methylanisole	293.2	3.967	0.12830E+02	−0.49701E-01	0.66429E-04	293-333
$C_8H_{10}O$	4-Methylanisole	293.2	3.914	0.86608E+01	−0.23510E-01	0.25000E-04	293-333
$C_8H_{10}O_2$	1,2-Dimethoxybenzene	293.2	4.45	0.74604E+01	−0.13445E-01	0.10737E-04	293-443
$C_8H_{10}O_2$	1,3-Dimethoxybenzene	298.2	5.363	0.11911E+02	−0.30804E-01	0.29643E-04	298-358
$C_8H_{10}O_2$	1,4-Dimethoxybenzene	333.7	5.60	0.11289E+02	−0.20765E-01	0.11987E-04	334-463
$C_8H_{10}O_2S$	Ethyl phenyl sulfone	348.2	39.0				
$C_8H_{10}S$	(Ethylthio)benzene	298.2	4.95				
$C_8H_{11}N$	*p*-Ethylaniline	298.2	4.84				
$C_8H_{11}N$	*N*-Ethylaniline	293.2	5.87				
$C_8H_{11}N$	*N,N*-Dimethylaniline	298.2	4.90	0.84052E+01	−0.13549E-01	0.62835E-05	289-453
$C_8H_{11}N$	2,4,6-Trimethylpyridine	298.2	7.807	0.20990E+02	−0.57419E-01	0.44286E-04	298-358
$C_8H_{11}NO$	4-Ethoxyaniline	298.2	7.43				
$C_8H_{12}N_2O_2$	Hexamethylene diisocyanate	288.2	14.41	0.26715E+02	−0.42696E-01		288-403
$C_8H_{12}O_4$	Diethyl maleate	298.2	7.560	0.13953E+02	−0.21969E-01	0.17817E-05	298-343
$C_8H_{12}O_4$	Diethyl fumarate	296.2	6.56				
C_8H_{14}	1,7-Octadiene	293.0	2.186	0.28376E+01	−0.17442E-02	−0.16141E-05	214-293
C_8H_{14}	*cis*-Cyclooctene	296.0	2.306	0.31115E+01	−0.32058E-02	0.16713E-05	269-406
C_8H_{14}	1,2-Dimethylcyclohexene	296.0	2.144	0.26443E+01	−0.17973E-02	0.35815E-06	211-374
C_8H_{14}	1,3-Dimethylcyclohexene	296.0	2.182	0.29951E+01	−0.34615E-02	0.24026E-05	213-373
$C_8H_{14}O_2$	Methyl cyclohexanecarboxylate	293.2	4.87				
$C_8H_{14}O_2$	Cyclohexyl acetate	293.2	5.08				
$C_8H_{14}O_3$	Butanoic anhydride	293.2	12.8				
$C_8H_{14}O_3$	2-Methylpropanoic anhydride	292.2	13.6				
$C_8H_{14}O_4$	Diisopropyl oxalate	293.2	6.403	0.10709E+02	−0.16328E-01	0.56000E-05	293-368
$C_8H_{14}O_4$	Diethyl succinate	293.2	6.098	0.80213E+01	0.11810E-02	−0.26400E-04	293-343
$C_8H_{14}O_4$	Dimethyl adipate	293.2	6.84	0.11739E+02	−0.17281E-01	0.11447E-05	293-433
$C_8H_{15}N$	Octanenitrile	293.2	13.90				
C_8H_{16}	1-Octene	293.2	2.113	0.24348E+01	0.34200E-03	−0.50000E-05	273-323
C_8H_{16}	*cis*-3-Octene	298.2	2.062				
C_8H_{16}	*trans*-3-Octene	298.2	2.002				
C_8H_{16}	*cis*-4-Octene	298.2	2.053				
C_8H_{16}	*trans*-4-Octene	298.2	2.004				
C_8H_{16}	3-Methyl-2-heptene*	293.2	2.436				
C_8H_{16}	2,5-Dimethyl-2-hexene	293.2	2.431				
C_8H_{16}	2,4,4-Trimethyl-1-pentene	298.2	2.0908				
C_8H_{16}	Cyclooctane	295.0	2.116	0.25036E+01	−0.12460E-02	−0.23175E-06	295-411
$C_8H_{16}Br_2$	1,8-Dibromooctane	298.2	7.43	0.94117E+00	0.61520E-01	−0.13333E-03	298-328
$C_8H_{16}Cl_2$	1,8-Dichlorooctane	298.2	7.64				
$C_8H_{16}O$	2-Octanone	293.2	9.51	−0.16219E+02	0.18799E+00	−0.34156E-03	293-333
$C_8H_{16}O$	3-Octanone	303.2	10.50				
$C_8H_{16}O_2$	Octanoic acid	288.2	2.85	0.29391E+01	−0.38721E-03		288-423
$C_8H_{16}O_2$	2-Ethylhexanoic acid	296.2	2.64				
$C_8H_{16}O_2$	Hexyl acetate	293.2	4.42				
$C_8H_{16}O_2$	Pentyl propanoate	293.2	4.552				
$C_8H_{16}O_2$	Isopentyl propanoate	273.2	5.21	0.17665E+02	−0.71718E-01	0.95635E-04	273-373
$C_8H_{16}O_2$	Butyl butanoate	298.2	4.39	0.79684E+01	−0.12000E-01	0.15266E-13	298-318
$C_8H_{16}O_2$	Propyl pentanoate	292.2	4.0				
$C_8H_{16}O_2$	Ethyl hexanoate	293.2	4.45	0.11007E+02	−0.32800E-01	0.35714E-04	253-353
$C_8H_{16}O_2$	Methyl heptanoate	293.2	4.355				
$C_8H_{16}O_3$	Isopentyl lactate	273.2	11.2	0.48649E+02	−0.21253E+00	0.27619E-03	273-373
$C_8H_{17}Br$	1-Bromooctane	293.2	5.0957	0.12404E+02	−0.35050E-01	0.34542E-04	283-353
$C_8H_{17}Br$	2-Bromooctane	293.2	5.44				
$C_8H_{17}Cl$	1-Chlorooctane	298.2	5.05	0.11346E+02	−0.25120E-01	0.13450E-04	274-328
$C_8H_{17}Cl$	2-Chlorooctane	293.2	5.42				
$C_8H_{17}F$	1-Fluorooctane	293.2	3.89				
$C_8H_{17}I$	1-Iodooctane	293.2	4.67	0.12452E+02	−0.41229E-01	0.50108E-04	233-313
$C_8H_{17}NO_2$	1-Nitrooctane	293.2	11.46				
C_8H_{18}	Octane	293.2	1.948	0.22590E+01	−0.84212E-03	−0.75758E-06	233-393
C_8H_{18}	2-Methylheptane	293.2	1.9519				
C_8H_{18}	3-Ethylhexane	293.2	1.9617				
C_8H_{18}	2,2-Dimethylhexane	293.2	1.9498				
C_8H_{18}	2,5-Dimethylhexane	293.95	1.9619	0.25821E+01	−0.26804E-02	0.19404E-05	294-324

Mol. form.	Name	*T*/K	ε_r	*a*	*b*	*c*	Range/K
C_8H_{18}	3,3-Dimethylhexane	293.2	1.9645				
C_8H_{18}	3,4-Dimethylhexane	292.1	1.9814	0.26849E+01	−0.33712E-02	0.32949E-05	292-324
C_8H_{18}	3-Ethyl-3-methylpentane	291.49	1.9869	0.25983E+01	−0.28027E-02	0.24195E-05	292-324
C_8H_{18}	2,2,3-Trimethylpentane	293.2	1.960				
C_8H_{18}	2,2,4-Trimethylpentane	293.2	1.943	0.23677E+01	−0.14768E-02	0.94261E-07	173-373
C_8H_{18}	2,3,3-Trimethylpentane	293.2	1.9780				
C_8H_{18}	2,3,4-Trimethylpentane	293.2	1.9738				
$C_8H_{18}O$	1-Octanol	293.2	10.30	0.51647E+02	−0.20371E+00	0.21320E-03	258-513
$C_8H_{18}O$	2-Octanol	293.2	8.13	0.63760E+02	−0.27643E+00	0.31075E-03	213-513
$C_8H_{18}O$	3-Octanol	293.2	5.55	0.12505E+03	−0.70646E+00	0.10245E-02	223-383
$C_8H_{18}O$	4-Octanol	293.2	4.48	0.51049E+02	−0.26664E+00	0.37280E-03	243-403
$C_8H_{18}O$	2-Methyl-1-heptanol	293.1	5.16	0.61698E+02	−0.33647E+00	0.49066E-03	236-328
$C_8H_{18}O$	3-Methyl-1-heptanol	290.3	2.884	0.84687E+01	−0.33712E-01	0.49793E-04	241-316
$C_8H_{18}O$	4-Methyl-1-heptanol	290.6	4.63	0.48612E+02	−0.26773E+00	0.39972E-03	237-332
$C_8H_{18}O$	5-Methyl-1-heptanol	290.4	7.68	0.54581E+02	−0.24772E+00	0.29734E-03	235-328
$C_8H_{18}O$	6-Methyl-1-heptanol	290.3	10.54	0.57997E+02	−0.23517E+00	0.24663E-03	265-328
$C_8H_{18}O$	2-Methyl-2-heptanol	292.2	3.43				
$C_8H_{18}O$	3-Methyl-2-heptanol	289.6	7.47	0.39178E+02	−0.17976E+00	0.24218E-03	229-329
$C_8H_{18}O$	4-Methyl-2-heptanol	290.0	3.59	0.39715E+02	−0.23115E+00	0.36771E-03	240-333
$C_8H_{18}O$	5-Methyl-2-heptanol	278.5	7.5	0.68568E+02	−0.40706E+00	0.67433E-03	230-279
$C_8H_{18}O$	6-Methyl-2-heptanol	290.1	6.41	0.77520E+02	−0.41724E+00	0.59448E-03	239-329
$C_8H_{18}O$	2-Methyl-3-heptanol	293.2	3.260	−0.59739E+01	0.56700E-01	−0.83125E-04	343-403
$C_8H_{18}O$	3-Methyl-3-heptanol	293.2	3.013	−0.38440E+01	0.42327E-01	−0.61250E-04	343-403
$C_8H_{18}O$	4-Methyl-3-heptanol	293.2	3.312	−0.48003E+01	0.50740E-01	−0.75000E-04	343-403
$C_8H_{18}O$	5-Methyl-3-heptanol	293.2	3.832	0.61967E+01	−0.63750E-02		343-383
$C_8H_{18}O$	6-Methyl-3-heptanol	293.2	4.992	0.23037E+02	−0.98029E-01	0.12479E-03	283-383
$C_8H_{18}O$	2-Methyl-4-heptanol	296.3	3.338	0.42102E+00	0.10427E-01	−0.20438E-05	230-333
$C_8H_{18}O$	3-Methyl-4-heptanol	290.0	7.46	0.33354E+02	−0.14077E+00	0.17750E-03	230-330
$C_8H_{18}O$	4-Methyl-4-heptanol	296.2	2.902				
$C_8H_{18}O$	2-Ethyl-1-hexanol	298.2	7.58	0.86074E+02	−0.42636E+00	0.55078E-03	208-318
$C_8H_{18}O$	2,2-Dimethyl-1-hexanol	293.2	4.50	0.91244E+01	−0.21785E-01	0.21018E-04	283-393
$C_8H_{18}O$	Dibutyl ether	293.2	3.0830	0.65383E+01	−0.16172E-01	0.14969E-04	293-314
$C_8H_{18}OS$	Dibutyl sulfoxide	313.2	24.73	0.67156E+02	−0.16448E+00	0.92275E-04	313-393
$C_8H_{18}O_2$	2-Ethyl-1,3-hexanediol	293.2	18.73	0.57919E+02	−0.17128E+00	0.12949E-03	233-333
$C_8H_{18}O_2S$	Dibutyl sulfone	323.2	25.72	0.66248E+02	−0.16417E+00	0.12001E-03	323-398
$C_8H_{18}O_4$	Triethylene glycol dimethyl ether	298.2	7.62				
$C_8H_{18}O_5$	Tetraethylene glycol	293.2	20.44	0.83547E+02	−0.31691E+00	0.34689E-03	253-333
$C_8H_{18}S$	1-Octanethiol	293.2	3.949	0.63667E+01	−0.87920E-02	0.18750E-05	273-333
$C_8H_{18}S$	Dibutyl sulfide	298.2	4.29				
$C_8H_{19}N$	Octylamine	293.2	3.58	0.77931E+01	−0.20015E-01	0.19347E-04	273-373
$C_8H_{19}N$	Dibutylamine	293.2	2.765	0.52504E+01	−0.10538E-01	0.71485E-05	243-323
$C_8H_{20}O_4Si$	Ethyl silicate	293.2	2.50				
$C_8H_{20}Si$	Tetraethylsilane	293.2	2.090				
$C_8H_{20}Sn$	Tetraethylstannane	293.2	2.241				
$C_8H_{23}N_5$	Tetraethylenepentamine	293.2	9.40	0.40553E+02	−0.16681E+00	0.20659E-03	213-333
$C_8H_{24}O_4Si_4$	Octamethylcyclotetrasiloxane	296.2	2.390	0.36286E+01	−0.56885E-02	0.50874E-05	296-333
$C_9H_6N_2O_2$	Toluene-2,4-diisocyanate	293.2	8.433	0.22174E+02	−0.66982E-01	0.68571E-04	293-353
$C_9H_6O_2$	2*H*-1-Benzopyran-2-one	343.2	34.04	0.11311E+03	−0.33804E+00	0.31324E-03	343-423
C_9H_7N	Quinoline	293.2	9.16	0.33432E+02	−0.13497E+00	0.17788E-03	258-323
C_9H_7N	Isoquinoline	298.2	11.0	0.14412E+03	−0.79935E+00	0.11839E-02	298-323
C_9H_8O	Cinnamaldehyde	305.8	17.72	0.41837E+02	−0.11060E+00	0.10401E-03	306-354
$C_9H_8O_4$	2-(Acetyloxy)benzoic acid	333.2	6.55	0.69994E+01	−0.14553E-02		333-416
C_9H_{10}	1-Propenylbenzene	293.2	2.73				
C_9H_{10}	Allylbenzene	293.2	2.63				
C_9H_{10}	Isopropenylbenzene	293.2	2.28				
$C_9H_{10}OS$	4-Acetylthioanisole	355.2	11.34				
$C_9H_{10}O_2$	Ethyl benzoate	293.2	6.20	0.18216E+02	−0.62361E-01	0.72884E-04	288-343
$C_9H_{10}O_2$	Methyl 4-methylbenzoate	306.2	4.3				
$C_9H_{10}O_2$	Benzyl acetate	303.2	5.34	0.11727E+02	−0.30869E-01	0.32340E-04	303-358
$C_9H_{10}O_2$	Phenyl propanoate	293.2	4.77				
$C_9H_{10}O_2$	4-Acetylanisole	313.2	17.3				
$C_9H_{10}O_3$	Ethyl salicylate	308.2	8.48	0.18910E+02	−0.35623E-01	0.46529E-05	225-321
$C_9H_{10}O_3$	Methyl 2-methoxybenzoate	294.2	7.7				

Mol. form.	Name	*T*/K	ε_r	*a*	*b*	*c*	Range/K
$C_9H_{11}Br$	(3-Bromopropyl)benzene	302.2	5.41	0.11360E+02	−0.27471E-01	0.25775E-04	302-358
$C_9H_{11}NO$	*N*-Ethylbenzamide	352.7	42.6	−0.20109E+03	0.17866E+01	−0.31065E-02	353-389
$C_9H_{11}NO$	*N*,*N*-Dimethylbenzamide	318.2	20.77	0.76725E+02	−0.26908E+00	0.29409E-03	318-443
$C_9H_{11}NO_2$	Ethyl 2-aminobenzoate	298.2	4.14				
C_9H_{12}	Propylbenzene	293.2	2.370	0.26933E+01	0.21679E-03	−0.44643E-05	273-323
C_9H_{12}	Isopropylbenzene	293.2	2.381	0.31149E+01	−0.30801E-02	0.19643E-05	273-323
C_9H_{12}	*o*-Ethyltoluene	293.2	2.595				
C_9H_{12}	*m*-Ethyltoluene	293.2	2.365				
C_9H_{12}	*p*-Ethyltoluene	293.2	2.265				
C_9H_{12}	1,2,3-Trimethylbenzene	293.2	2.656	0.76006E+01	−0.29118E-01	0.41786E-04	273-323
C_9H_{12}	1,2,4-Trimethylbenzene	293.2	2.377	0.31517E+01	−0.30634E-02	0.14286E-05	273-323
C_9H_{12}	1,3,5-Trimethylbenzene	293.2	2.279	0.38998E+01	−0.88072E-02	0.11149E-04	288-358
$C_9H_{12}O$	Benzenepropanol	293.2	11.97	0.94482E+02	−0.45540E+00	0.59307E-03	213-303
$C_9H_{12}O$	α-Ethylbenzenemethanol	293.2	6.68	0.44520E+02	−0.21505E+00	0.29443E-03	233-373
$C_9H_{12}O$	α,α-Dimethylbenzenemethanol	303.2	5.61	0.57072E+01	0.86568E-02	−0.29580E-04	303-373
$C_9H_{12}O$	1-Phenyl-2-propanol	293.2	9.35	0.10762E+03	−0.56026E+00	0.76915E-03	233-373
$C_9H_{12}O$	Benzyl ethyl ether	298.2	3.90				
$C_9H_{12}O$	2,6-Dimethylanisole	293.2	3.780	0.76700E+01	−0.18298E-01	0.17143E-04	293-333
$C_9H_{12}O$	3,5-Dimethylanisole	293.2	3.711	0.54981E+01	−0.56651E-02	−0.14286E-05	293-333
$C_9H_{12}O_2S$	Butyl thiophene-2-carboxylate	293.2	6.40				
$C_9H_{12}S$	Benzenepropanethiol	303.2	4.36	0.82411E+01	−0.15034E-01	0.73617E-05	303-358
$C_9H_{13}N$	Benzylethylamine	293.2	4.3				
$C_9H_{13}N$	*N*-Propylaniline	293.2	5.48				
$C_9H_{13}N$	2-Methyl-*N*,*N*-dimethylaniline	293.2	3.4				
$C_9H_{13}N$	4-Methyl-*N*,*N*-dimethylaniline	293.2	3.9				
$C_9H_{14}OSi$	Trimethylphenoxysilane	298.2	3.3953				
$C_9H_{14}O_6$	Triacetin	293.6	7.11	0.17819E+02	−0.53656E-01	0.57759E-04	219-304
$C_9H_{14}Si$	Trimethylphenylsilane	298.2	2.3533	0.21463E+01	0.32711E-02	−0.86264E-05	288-323
$C_9H_{16}O_2$	2-Nonenoic acid	296.2	2.5				
$C_9H_{16}O_2$	Cyclohexyl propanoate	293.2	4.82				
$C_9H_{16}O_2$	Ethyl cyclohexanecarboxylate	293.2	4.64				
$C_9H_{16}O_4$	Diethyl glutarate	303.2	6.659				
$C_9H_{17}N$	Nonanenitrile	293.2	12.08				
C_9H_{18}	1-Nonene	293.2	2.180	0.22710E+01	0.15797E-02	−0.64286E-05	273-323
$C_9H_{18}Br_2$	1,9-Dibromononane	293.2	7.153	0.18931E+02	−0.57764E-01	0.60000E-04	293-343
$C_9H_{18}O$	2-Nonanone	295.2	9.14				
$C_9H_{18}O$	5-Nonanone	293.2	10.6				
$C_9H_{18}O$	Di-*tert*-butyl ketone	287.65	10.0				
$C_9H_{18}O$	2,6-Dimethyl-4-heptanone	293.2	9.91	0.33178E+02	−0.11290E+00	0.11454E-03	273-393
$C_9H_{18}O_2$	Nonanoic acid	294.9	2.475	0.25039E+01	0.67274E-03	−0.24180E-05	295-365
$C_9H_{18}O_2$	2-Methyloctanoic acid	293.2	2.39				
$C_9H_{18}O_2$	2-Ethylheptanoic acid	293.2	1.98				
$C_9H_{18}O_2$	Heptyl acetate	293.2	4.2				
$C_9H_{18}O_2$	Pentyl butanoate	301.2	4.08	0.59029E+01	−0.49905E-02	−0.34292E-05	301-343
$C_9H_{18}O_2$	Isopentyl butanoate	293.2	4.0				
$C_9H_{18}O_2$	Isobutyl pentanoate	292.2	3.8				
$C_9H_{18}O_2$	Methyl octanoate	293.2	4.101				
$C_9H_{19}Br$	1-Bromononane	298.2	4.74	0.79870E+01	−0.10488E-01	−0.13450E-05	274-328
$C_9H_{19}Cl$	1-Chlorononane	293.2	4.803	0.95528E+01	−0.16200E-01	−0.16365E-13	293-323
$C_9H_{19}NO$	*N*,*N*-Dibutylformamide	293.2	18.4				
C_9H_{20}	Nonane	293.2	1.9722	0.23894E+01	−0.14830E-02	0.14881E-06	253-393
C_9H_{20}	2-Methyloctane	293.2	1.967				
C_9H_{20}	4-Methyloctane	293.2	1.967				
C_9H_{20}	2,4-Dimethylheptane	293.2	1.89				
C_9H_{20}	2,5-Dimethylheptane	293.2	1.89				
C_9H_{20}	2,6-Dimethylheptane	293.2	1.987				
$C_9H_{20}N_2O$	Tetraethylurea	296.8	14.29	0.52820E+02	−0.18790E+00	0.19580E-03	205-411
$C_9H_{20}O$	1-Nonanol	293.2	8.83	0.97467E+02	−0.51103E+00	0.71429E-03	288-343
$C_9H_{20}O$	2-Nonanol	298.2	6.66	0.10136E+03	−0.55612E+00	0.80000E-03	288-308
$C_9H_{20}O$	3-Nonanol	298.2	4.49	0.55214E+02	−0.31920E+00	0.50000E-03	288-308
$C_9H_{20}O$	4-Nonanol	298.2	3.69	0.27954E+01	0.30000E-02	−0.52375E-13	288-308
$C_9H_{20}O$	5-Nonanol	298.2	3.54	−0.25463E+01	0.35320E-01	−0.50000E-04	288-308
$C_9H_{21}B$	Tripropylborane	293.2	2.026				

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
$C_9H_{21}N$	Nonylamine	293.2	3.42	0.53575E+01	−0.71982E-02	0.19481E-05	293-373
$C_9H_{21}N$	Tripropylamine	293.2	2.380	0.33380E+01	−0.86332E-02	0.18322E-04	243-293
$C_9H_{21}O_4P$	Tripropyl phosphate	293.2	10.93	0.33166E+02	−0.10514E+00	0.10000E-03	293-373
$C_{10}H_7Br$	1-Bromonaphthalene	298.2	4.768	0.10561E+02	−0.27671E-01	0.27655E-04	293-323
$C_{10}H_7Cl$	1-Chloronaphthalene	298.2	5.04	0.84861E+01	−0.12357E-01	0.26899E-05	274-328
$C_{10}H_7NO_2$	1-Nitronaphthalene	333.2	19.68	0.36267E+02	−0.41283E-01	−0.25595E-04	333-403
$C_{10}H_8$	Naphthalene	363.2	2.54				
$C_{10}H_8O$	1-Naphthol	373.0	5.03	0.16489E+02	−0.46700E-01	0.42857E-04	373-453
$C_{10}H_8O$	2-Naphthol	413.0	4.95	0.92865E+01	−0.10500E-01	0.42501E-15	413-453
$C_{10}H_9N$	1-Naphthylamine	333.2	5.20	0.10577E+02	−0.22114E-01	0.17857E-04	333-453
$C_{10}H_9N$	2-Naphthylamine	393.0	5.26	0.19722E+02	−0.60679E-01	0.60714E-04	393-473
$C_{10}H_9N$	2-Methylquinoline	293.2	7.24	0.11688E+02	−0.78400E-02	−0.25000E-04	293-333
$C_{10}H_9N$	4-Methylquinoline	293.2	9.31	0.17788E+02	−0.32580E-01	0.12500E-04	293-333
$C_{10}H_9N$	6-Methylquinoline	293.2	8.48	0.21696E+02	−0.63400E-01	0.62500E-04	293-333
$C_{10}H_9N$	8-Methylquinoline	293.2	6.58	0.19356E+02	−0.61900E-01	0.62500E-04	293-333
$C_{10}H_{10}O_4$	Methyl 2-(acetyloxy)benzoate	328.9	5.31	0.19579E+02	−0.69970E-01	0.80889E-04	329-371
$C_{10}H_{10}O_4$	Dimethyl phthalate	293.2	8.66				
$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene	298.2	2.771	0.29172E+01	0.12832E-02	−0.59453E-05	298-343
$C_{10}H_{12}$	4-Ethylstyrene	298.2	3.350				
$C_{10}H_{12}$	Dicyclopentadiene	313.2	2.43	0.30564E+01	−0.20000E-02	0.82443E-15	313-373
$C_{10}H_{12}O$	Tetrahydro-2-naphthol*	293.2	11.70	0.98978E+02	−0.48267E+00	0.63008E-03	293-363
$C_{10}H_{12}O$	4-Isopropylbenzaldehyde	288.2	10.68				
$C_{10}H_{12}O_2$	4-Allyl-2-methoxyphenol	293.2	9.55	0.52377E+02	−0.24380E+00	0.33333E-03	273-323
$C_{10}H_{12}O_2$	2-Phenylethyl acetate	297.2	4.93				
$C_{10}H_{12}O_2$	Benzyl propanoate	303.0	5.11	0.42301E+01	0.13962E-01	−0.36426E-04	303-358
$C_{10}H_{12}O_2$	Phenyl butanoate	293.2	4.48				
$C_{10}H_{12}O_2$	Propyl benzoate	303.2	5.78	0.10927E+02	−0.20535E-01	0.11745E-04	303-358
$C_{10}H_{12}O_2$	Ethyl phenylacetate	293.2	5.320				
$C_{10}H_{14}$	Butylbenzene	293.2	2.359				
$C_{10}H_{14}$	*sec*-Butylbenzene	293.2	2.357	0.28348E+01	−0.68586E-03	−0.32143E-05	273-323
$C_{10}H_{14}$	*tert*-Butylbenzene	293.2	2.359	0.27924E+01	−0.38350E-03	−0.37500E-05	273-323
$C_{10}H_{14}$	Isobutylbenzene	293.2	2.318	0.28055E+01	−0.92614E-03	−0.25000E-05	273-323
$C_{10}H_{14}$	1-Isopropyl-4-methylbenzene	298.2	2.2322	0.25266E+01	−0.25121E-03	−0.24867E-05	277-333
$C_{10}H_{14}$	*o*-Diethylbenzene	293.2	2.594				
$C_{10}H_{14}$	*m*-Diethylbenzene	293.2	2.369				
$C_{10}H_{14}$	*p*-Diethylbenzene	293.2	2.259				
$C_{10}H_{14}$	1-Ethyl-3,5-dimethylbenzene	293.2	2.275				
$C_{10}H_{14}$	1,2,3,4-Tetramethylbenzene	296.0	2.538	0.33822E+01	−0.33630E-02	0.17475E-05	273-412
$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	356.0	2.223	0.26834E+01	−0.10327E-02	−0.73533E-06	356-430
$C_{10}H_{14}N_2$	*L*-Nicotine	293.2	8.937	0.21347E+02	−0.57177E-01	0.50655E-04	293-363
$C_{10}H_{14}O$	1-Phenyl-2-methyl-2-propanol	298.2	5.71	0.21922E+02	−0.84231E-01	0.99475E-04	298-423
$C_{10}H_{14}O$	Butyl phenyl ether	293.2	3.734				
$C_{10}H_{14}O$	Thymol	333.2	4.259				
$C_{10}H_{15}N$	*N*,*N*-Diethylaniline	303.2	5.15	0.50773E+01	0.15399E-01	−0.50000E-04	303-328
$C_{10}H_{16}$	γ-Terpinene	298.2	2.2738				
$C_{10}H_{16}$	*d*-Limonene	298.2	2.3746				
$C_{10}H_{16}$	*l*-Limonene	298.2	2.3738				
$C_{10}H_{16}$	Terpinolene	298.2	2.2918				
$C_{10}H_{16}$	α-Pinene	298.2	2.1787				
$C_{10}H_{16}$	β-Pinene	298.2	2.4970				
$C_{10}H_{16}$	α-Terpinene	298.2	2.4526				
$C_{10}H_{16}$	β-Myrcene	298.2	2.3				
$C_{10}H_{16}O$	Carvenone	293.2	18.8				
$C_{10}H_{16}O$	*d*-Fenchone	294.2	12.8				
$C_{10}H_{17}Cl$	2-Chlorobornane	368.2	5.21				
$C_{10}H_{18}$	Pinane	298.2	2.1456				
$C_{10}H_{18}$	*cis*-Decahydronaphthalene	293.2	2.219	0.25410E+01	−0.11420E-02	0.15092E-06	293-373
$C_{10}H_{18}$	*trans*-Decahydronaphthalene	293.2	2.184	0.26615E+01	−0.21241E-02	0.16864E-05	293-373
$C_{10}H_{18}O$	Eucalyptol	298.2	4.57				
$C_{10}H_{18}O_2$	Cyclohexyl butanoate	293.2	4.58				
$C_{10}H_{18}O_4$	Diethyl adipate	293.2	6.109	0.14824E+02	−0.40749E-01	0.37600E-04	293-343
$C_{10}H_{20}$	1-Decene	293.2	2.136	0.19091E+01	0.33442E-02	−0.87500E-05	273-323
$C_{10}H_{20}$	*cis*-5-Decene	298.2	2.071				

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
$C_{10}H_{20}$	*trans*-5-Decene	298.2	2.030				
$C_{10}H_{20}$	5-Methyl-4-nonene	293.2	2.175				
$C_{10}H_{20}$	2,4,6-Trimethyl-3-heptene	293.2	2.293				
$C_{10}H_{20}Br_2$	1,10-Dibromodecane	303.2	6.56	0.17350E+02	−0.50328E-01	0.48633E-04	303-368
$C_{10}H_{20}Cl_2$	1,10-Dichlorodecane	308.2	6.68	−0.57423E+01	0.94220E-01	−0.17500E-03	308-338
$C_{10}H_{20}O$	2-Decanone	287.2	8.3				
$C_{10}H_{20}O$	Menthol	309.3	3.90	0.68202E+01	−0.15894E-01	0.20837E-04	309-358
$C_{10}H_{20}O_2$	2,2-Dimethyloctanoic acid	296.2	2.8				
$C_{10}H_{20}O_2$	Octyl acetate	288.2	4.18	−0.34691E+01	0.58106E-01	−0.10952E-03	288-323
$C_{10}H_{20}O_2$	2-Methylheptyl acetate	288.2	4.27	0.23285E+02	−0.11538E+00	0.17143E-03	288-323
$C_{10}H_{20}O_2$	Pentyl pentanoate	305.6	4.076	0.77641E+01	−0.14335E-01	0.73740E-05	306-393
$C_{10}H_{20}O_2$	Isopentyl pentanoate	292.2	3.6				
$C_{10}H_{20}O_2$	Isopentyl isopentanoate	288.2	4.39	0.14698E+02	−0.57726E-01	0.76190E-04	288-323
$C_{10}H_{20}O_2$	Methyl nonanoate	293.2	3.943				
$C_{10}H_{21}Br$	1-Bromodecane	298.2	4.44	0.11202E+02	−0.33491E-01	0.36314E-04	274-328
$C_{10}H_{21}Cl$	1-Chlorodecane	293.2	4.581	0.68741E+01	−0.12210E-02	−0.22500E-04	293-323
$C_{10}H_{21}NO$	*N*,*N*-Dibutylacetamide	293.2	19.1				
$C_{10}H_{22}$	Decane	293.2	1.9853	0.24054E+01	−0.15445E-02	0.44643E-06	253-393
$C_{10}H_{22}$	2,7-Dimethyloctane	293.2	1.98				
$C_{10}H_{22}$	4-Propylheptane	293.2	1.9955				
$C_{10}H_{22}O$	1-Decanol	293.2	7.93	0.47195E+02	−0.20740E+00	0.24942E-03	293-343
$C_{10}H_{22}O$	2-Decanol	298.2	5.82	0.13621E+03	−0.81000E+00	0.12500E-02	288-308
$C_{10}H_{22}O$	3-Decanol	298.2	4.05	0.52090E+02	−0.31020E+00	0.50000E-03	288-308
$C_{10}H_{22}O$	4-Decanol	298.2	3.42	−0.11260E+02	0.93960E-01	−0.15000E-03	288-308
$C_{10}H_{22}O$	5-Decanol	298.2	3.24	−0.25832E+01	0.31456E-01	−0.40000E-04	288-308
$C_{10}H_{22}O$	2,2-Dimethyl-1-octanol	293.2	7.86	0.69536E+02	−0.34596E+00	0.46250E-03	293-333
$C_{10}H_{22}O$	Dipentyl ether	298.2	2.798				
$C_{10}H_{22}O$	Diisopentyl ether	293.2	2.817	0.44690E+01	−0.63710E-02	0.25000E-05	293-323
$C_{10}H_{22}OS$	Dipentyl sulfoxide	348.2	18.8				
$C_{10}H_{22}O_5$	Tetraethylene glycol dimethyl ether	298.2	7.68				
$C_{10}H_{22}S$	Dipentyl sulfide	298.2	3.826				
$C_{10}H_{23}N$	Decylamine	293.2	3.31	0.61497E+01	−0.12801E-01	0.10606E-04	293-373
$C_{10}H_{30}O_3Si_4$	Decamethyltetrasiloxane	293.2	2.370				
$C_{10}H_{30}O_5Si_5$	Decamethylcyclopentasiloxane	293.2	2.50				
$C_{11}H_{10}$	1-Methylnaphthalene	293.2	2.915	0.45126E+01	−0.76480E-02	0.75000E-05	293-333
$C_{11}H_{10}$	2-Methylnaphthalene	313.2	2.747				
$C_{11}H_{10}O$	1-Methoxynaphthalene	293.2	4.020	0.71885E+01	−0.14838E-01	0.13750E-04	293-333
$C_{11}H_{10}O$	2-Methoxynaphthalene	353.2	3.563	0.56702E+01	−0.69754E-02	0.28571E-05	353-373
$C_{11}H_{12}O_2$	Ethyl *trans*-cinnamate	293.2	5.63				
$C_{11}H_{12}O_3$	Ethyl benzoylacetate	303.2	13.50	0.93644E+01	0.74280E-01	−0.20000E-03	303-323
$C_{11}H_{14}O_2$	Benzyl butanoate	301.2	4.55				
$C_{11}H_{14}O_2$	Phenyl pentanoate	293.2	4.30				
$C_{11}H_{14}O_2$	Butyl benzoate	303.2	5.52	0.77854E+01	−0.34972E-02	−0.13149E-04	303-358
$C_{11}H_{14}O_2$	Isobutyl benzoate	291.2	5.39				
$C_{11}H_{16}$	1,3-Diethyl-5-methylbenzene	293.2	2.264				
$C_{11}H_{16}$	Pentamethylbenzene	334.0	2.358	0.30196E+01	−0.22619E-02	0.83831E-06	334-413
$C_{11}H_{22}$	1-Undecene	293.2	2.137	0.22132E+01	0.13121E-02	−0.53571E-05	273-323
$C_{11}H_{22}O$	2-Undecanone	285.3	8.3				
$C_{11}H_{22}O_2$	Nonyl acetate	293.2	3.87				
$C_{11}H_{22}O_2$	Pentyl hexanoate	288.2	4.22	0.83503E+01	−0.18449E-01	0.14286E-04	288-323
$C_{11}H_{23}Br$	1-Bromoundecane	272.6	4.61				
$C_{11}H_{24}$	Undecane	293.2	1.9972	0.23637E+01	−0.12500E-02	−0.85869E-16	283-363
$C_{11}H_{24}O$	1-Undecanol	313.2	5.98				
$C_{11}H_{25}N$	Undecylamine	293.2	3.25	0.54945E+01	−0.96161E-02	0.66017E-05	293-373
$C_{12}F_{27}N$	Tris(perfluorobutyl)amine	293.2	2.15				
$C_{12}H_8O$	Dibenzofuran	373.2	3.00				
$C_{12}H_{10}$	Biphenyl	348.2	2.53	0.26869E+01	0.63072E-03	−0.30995E-05	348-428
$C_{12}H_{10}N_2O$	*trans*-Azoxybenzene	311.2	5.2				
$C_{12}H_{10}O$	Diphenyl ether	283.2	3.726				
$C_{12}H_{10}O$	2-Acetonaphthone	333.2	13.03	0.14538E+03	−0.73040E+00	0.10000E-02	333-363
$C_{12}H_{10}OS$	Diphenyl sulfoxide	344.7	16.6				
$C_{12}H_{10}O_2S$	Diphenyl sulfone	406.2	21.1				
$C_{12}H_{10}S$	Diphenyl sulfide	298.2	5.43				

Mol. form.	Name	*T*/K	ε_r	*a*	*b*	*c*	Range/K
$C_{12}H_{11}N$	Diphenylamine	323.2	3.73				
$C_{12}H_{11}NO$	*N*-1-Naphthylenylacetamide	433.2	24.3	0.84739E+02	−0.12391E+00	−0.35714E-04	433-533
$C_{12}H_{12}$	1,6-Dimethylnaphthalene	293.2	2.7250				
$C_{12}H_{12}O$	1-Ethoxynaphthalene	292.2	3.3				
$C_{12}H_{14}O_2$	Propyl cinnamate	293.2	5.45				
$C_{12}H_{14}O_4$	Diethyl phthalate	293.2	7.86				
$C_{12}H_{16}O$	2-Cyclohexylphenol	328.2	3.97				
$C_{12}H_{16}O$	4-Cyclohexylphenol	404.2	4.42				
$C_{12}H_{16}O_2$	Pentyl benzoate	293.2	5.07				
$C_{12}H_{16}O_3$	Pentyl salicylate	301.2	6.25				
$C_{12}H_{16}O_3$	Isopentyl salicylate	293.12	7.26	0.13129E+02	−0.19190E-01	−0.36060E-05	225-397
$C_{12}H_{17}NO$	*N*-Butyl-*N*-phenylacetamide	298.2	11.66				
$C_{12}H_{18}$	Hexylbenzene	293.2	2.3				
$C_{12}H_{18}$	1,3,5-Triethylbenzene	293.2	2.256				
$C_{12}H_{18}$	Hexamethylbenzene	449.0	2.172	0.35710E+01	−0.46912E-02	0.35088E-05	449-489
$C_{12}H_{20}O_2$	*l*-Bornyl acetate	303.2	4.46	0.60791E+01	0.98200E-02	−0.50000E-04	303-323
$C_{12}H_{22}O$	Dicyclohexyl ether	293.2	3.45	0.95324E+01	−0.31740E-01	0.37500E-04	293-333
$C_{12}H_{22}O$	Cyclododecanone	303.2	11.4	0.39327E+02	−0.13248E+00	0.13298E-03	303-423
$C_{12}H_{22}O_6$	Dibutyl tartrate	314.2	9.4				
$C_{12}H_{24}$	1-Dodecene	293.2	2.152	0.22581E+01	0.11106E-02	−0.50000E-05	273-323
$C_{12}H_{24}O_2$	Decyl acetate	293.2	3.75				
$C_{12}H_{24}O_2$	Ethyl decanoate	293.2	3.75	0.70969E+01	−0.15080E-01	0.12500E-04	293-353
$C_{12}H_{24}O_2$	Methyl undecanoate	293.2	3.671				
$C_{12}H_{25}Br$	1-Bromododecane	298.2	4.07	0.86103E+01	−0.20891E-01	0.18994E-04	274-328
$C_{12}H_{25}Cl$	1-Chlorododecane	298.2	4.17	0.10002E+02	−0.27798E-01	0.27559E-04	274-328
$C_{12}H_{25}I$	1-Iododododecane	298.2	3.91	0.34641E+01	0.97404E-02	−0.27602E-04	293-323
$C_{12}H_{26}$	Dodecane	293.2	2.0120	0.23697E+01	−0.12200E-02	−0.36375E-16	283-363
$C_{12}H_{26}O$	1-Dodecanol	303.2	5.82	0.18518E+02	−0.44859E-01	0.99900E-05	303-358
$C_{12}H_{26}O$	2-Butyl-1-octanol	363.2	3.28				
$C_{12}H_{27}BO_3$	Tributyl borate	293.2	2.23				
$C_{12}H_{27}N$	Dodecylamine	303.2	3.07	0.27999E+01	0.44810E-02	−0.11905E-04	303-373
$C_{12}H_{27}N$	Tributylamine	293.2	2.340	0.19846E+01	0.28108E-02	−0.54545E-05	233-293
$C_{12}H_{27}O_4P$	Tributyl phosphate	293.2	8.34	0.26304E+02	−0.88480E-01	0.92857E-04	293-373
$C_{12}H_{28}O_4Si$	Tetrapropoxysilane	298.2	3.21				
$C_{12}H_{28}Sn$	Tetrapropylstannane	293.2	2.267				
$C_{12}H_{30}OSi_2$	Hexaethyldisiloxane	298.2	2.259	0.36559E+01	−0.72406E-02	0.85714E-05	298-333
$C_{13}H_{10}O$	Benzophenone	300.2	12.62	0.34130E+02	−0.10249E+00	0.10268E-03	300-420
$C_{13}H_{10}O_3$	Phenyl salicylate	290.2	6.92	0.26545E+02	−0.11180E+00	0.15220E-03	290-358
$C_{13}H_{12}$	Diphenylmethane	303.2	2.540	0.30638E+01	−0.17286E-02		303-333
$C_{13}H_{12}O$	Benzyl phenyl ether	313.2	3.748				
$C_{13}H_{18}O_2$	Hexyl benzoate	293.2	4.80				
$C_{13}H_{20}$	Heptylbenzene	293.2	2.26				
$C_{13}H_{20}O$	α-Ionone*	292.4	10.78				
$C_{13}H_{20}O$	β-Ionone*	297.65	11.66				
$C_{13}H_{24}O_4$	Diethyl nonanedioate	303.2	5.133				
$C_{13}H_{26}$	1-Tridecene	293.2	2.139	0.14154E+01	0.66514E-02	−0.14286E-04	273-323
$C_{13}H_{26}O$	7-Tridecanone	303.2	7.6				
$C_{13}H_{26}O_2$	Ethyl undecanoate	293.2	3.55				
$C_{13}H_{26}O_2$	Methyl dodecanoate	293.2	3.539				
$C_{13}H_{27}Br$	1-Bromotridecane	281.15	4.19				
$C_{13}H_{28}$	Tridecane	293.2	2.0213	0.23731E+01	−0.12000E-02	−0.21841E-15	283-363
$C_{13}H_{28}$	5-Butylnonane	293.2	2.0319				
$C_{13}H_{28}O$	1-Tridecanol	333.2	4.02				
$C_{14}H_{10}$	Anthracene	502.0	2.649	0.20571E+02	−0.69169E-01	0.66667E-04	502-516
$C_{14}H_{10}$	Phenanthrene	383.2	2.72				
$C_{14}H_{10}O_2$	Benzil	368.2	13.04	−0.23599E+02	0.22715E+00	−0.34667E-03	368-393
$C_{14}H_{12}O_2$	Benzyl benzoate	303.2	5.26	0.76856E+01	−0.80000E-02	−0.80361E-15	303-358
$C_{14}H_{12}O_3$	Benzyl salicylate	301.2	4.12				
$C_{14}H_{14}$	1,2-Diphenylethane	331.2	2.47	0.31178E+01	−0.21572E-02	0.59800E-06	331-451
$C_{14}H_{14}O$	Dibenzyl ether	293.2	3.821	0.80154E+01	−0.20536E-01	0.21250E-04	293-333
$C_{14}H_{15}N$	Dibenzylamine	293.2	3.446				
$C_{14}H_{16}O_2Si$	Dimethyldiphenoxysilane	298.2	3.500	0.51669E+01	−0.77001E-02	0.70156E-05	283-353
$C_{14}H_{18}O_2$	Pentyl cinnamate	293.2	4.89				

Mol. form.	Name	T/K	ε_r	a	b	c	Range/K
$C_{14}H_{22}$	Octylbenzene	293.2	2.26				
$C_{14}H_{26}O_4$	Diisobutyl adipate	293.2	5.19				
$C_{14}H_{26}O_4$	Diethyl sebacate	303.2	4.995	0.39143E+02	−0.20965E+00	0.32000E-03	303-313
$C_{14}H_{28}O_2$	Dodecyl acetate	293.2	3.6				
$C_{14}H_{28}O_2$	Ethyl laurate	273.2	3.94				
$C_{14}H_{28}O_2$	Methyl tridecanoate	293.2	3.442				
$C_{14}H_{29}Br$	1-Bromotetradecane	293.2	3.84	0.10058E+02	−0.33905E-01	0.43528E-04	274-328
$C_{14}H_{30}$	Tetradecane	293.2	2.0343	0.23832E+01	−0.11900E-02	−0.51229E-16	283-363
$C_{14}H_{30}O$	1-Tetradecanol	318.2	4.42	0.12272E+02	−0.24667E-01	−0.13168E-13	318-358
$C_{14}H_{31}N$	Tetradecylamine	312.55	2.90				
$C_{15}H_{12}O_4$	Phenyl 2-(acetyloxy)benzoate	384.2	4.33				
$C_{15}H_{26}O_6$	Tributyrin	282.8	5.72	0.13152E+02	−0.36684E-01	0.36795E-04	199-283
$C_{15}H_{30}O_2$	Methyl tetradecanoate	293.2	3.352				
$C_{15}H_{31}Br$	1-Bromopentadecane	293.35	3.88				
$C_{15}H_{32}$	Pentadecane	293.2	2.0391	0.23792E+01	−0.11600E-02	−0.71069E-16	283-363
$C_{15}H_{32}O$	1-Pentadecanol	333.2	3.70				
$C_{15}H_{33}N$	Pentadecylamine	313.25	2.85				
$C_{15}H_{33}N$	Triisopentylamine	294.2	2.29				
$C_{16}H_{22}O_4$	Dibutyl phthalate	293.2	6.58	0.12444E+02	−0.20000E-01		293-333
$C_{16}H_{32}O_2$	Hexadecanoic acid	338.2	2.417				
$C_{16}H_{32}O_2$	Ethyl myristate	293.2	3.50	0.52642E+01	−0.60000E-02	−0.47358E-15	293-353
$C_{16}H_{32}O_2$	Methyl pentadecanoate	293.2	3.296				
$C_{16}H_{33}Br$	1-Bromohexadecane	298.2	3.68	0.58668E+01	−0.73333E-02	−0.52666E-14	298-328
$C_{16}H_{33}I$	1-Iodohexadecane	293.2	3.57	0.79531E+01	−0.22859E-01	0.26955E-04	293-323
$C_{16}H_{34}$	Hexadecane	293.2	2.0460	0.23861E+01	−0.11600E-02	0.25555E-15	293-363
$C_{16}H_{34}O$	1-Hexadecanol	333.2	3.69	0.85935E+01	−0.14714E-01	−0.45533E-13	333-363
$C_{16}H_{35}N$	Hexadecylamine	328.35	2.71				
$C_{16}H_{36}Sn$	Tetrabutylstannane	293.2	9.74	0.56115E+02	−0.24812E+00	0.30682E-03	293-313
$C_{17}H_{12}O_3$	2-Naphthyl salicylate	293.0	6.30	0.11229E+02	−0.18857E-01	0.70332E-05	293-353
$C_{17}H_{34}O$	9-Heptadecanone	328.2	5.43	0.44176E+02	−0.21183E+00	0.28571E-03	328-363
$C_{17}H_{34}O_2$	Methyl palmitate	313.2	3.124				
$C_{17}H_{36}$	Heptadecane	293.2	2.0578	0.23627E+01	−0.10400E-02	−0.10397E-12	293-308
$C_{17}H_{36}O$	1-Heptadecanol	333.2	3.41				
$C_{18}H_{26}O_4$	Dipentyl phthalate	293.2	6.00				
$C_{18}H_{28}O_2$	Phenyl laurate	293.2	3.28				
$C_{18}H_{30}O_2$	Linolenic acid	293.2	2.825	0.33867E+01	−0.19181E-02		274-368
$C_{18}H_{30}O_4$	Dicyclohexyl adipate	308.2	4.84				
$C_{18}H_{32}O_2$	Linoleic acid	293.2	2.754	0.32073E+01	−0.15477E-02		275-368
$C_{18}H_{34}O_2$	Oleic acid	293.2	2.336	0.25385E+01	−0.69448E-03		275-368
$C_{18}H_{34}O_4$	Dibutyl sebacate	293.2	4.54				
$C_{18}H_{36}O_2$	Stearic acid	293.2	2.314	0.27159E+01	−0.13300E-02		293-373
$C_{18}H_{36}O_2$	Hexadecyl acetate	308.2	3.19	0.47310E+01	−0.50000E-02	0.41338E-14	308-348
$C_{18}H_{36}O_2$	Ethyl palmitate	303.2	3.07	0.57938E+01	−0.12294E-01	0.10919E-04	303-455
$C_{18}H_{36}O_2$	Methyl heptadecanoate	313.2	3.07				
$C_{18}H_{37}Br$	1-Bromooctadecane	303.35	3.53	0.46790E+01	−0.30355E-02	−0.24798E-05	303-332
$C_{18}H_{38}O$	1-Octadecanol	333.2	3.38	0.73784E+01	−0.12000E-01	−0.22871E-13	333-363
$C_{18}H_{39}BO_3$	Trihexyl borate	293.2	2.22				
$C_{18}H_{39}N$	Octadecylamine	326.35	2.67				
$C_{19}H_{16}$	Triphenylmethane	367.2	2.46	0.40201E+01	−0.66507E-02	0.65329E-05	367-448
$C_{19}H_{18}O_3Si$	Methyltriphenoxysilane	298.2	3.628				
$C_{19}H_{32}O_2$	Methyl linolenate	293.2	3.355				
$C_{19}H_{34}O_2$	Methyl linoleate	293.2	3.466				
$C_{19}H_{36}O_2$	Methyl oleate	293.2	3.211				
$C_{19}H_{38}O$	10-Nonadecanone	353.2	5.37				
$C_{19}H_{38}O_2$	Methyl stearate	313.2	3.021				
$C_{19}H_{40}$	Nonadecane	293.2	2.0706				
$C_{20}H_{30}O_4$	Dihexyl phthalate	293.2	5.62				
$C_{20}H_{38}O_2$	Ethyl oleate	301.2	3.17	0.57033E+01	−0.11223E-01	0.93447E-05	301-423
$C_{20}H_{40}O_2$	Octadecyl acetate	308.2	3.07	0.44569E+01	−0.45000E-02	0.33923E-14	308-348
$C_{20}H_{40}O_2$	Ethyl stearate	313.2	2.958	0.70930E+01	−0.19081E-01	0.19555E-04	331-440
$C_{20}H_{40}O_2$	Methyl nonadecanoate	313.2	2.982				
$C_{20}H_{42}O$	1-Eicosanol	338.2	3.13	0.21700E+01	0.12497E-01	−0.28571E-04	338-363
$C_{20}H_{42}O$	Didecyl ether	293.2	2.644	0.41465E+01	−0.62240E-02	0.37500E-05	293-333

Mol. form.	Name	*T*/K	ε_r	*a*	*b*	*c*	Range/K
$C_{20}H_{60}O_8Si_9$	Eicosamethylnonasiloxane	293.2	2.645	0.57840E+01	−0.16568E-01	0.20000E-04	293-323
$C_{21}H_{21}O_4P$	Tricresyl phosphate*	298.2	6.7				
$C_{21}H_{38}O_6$	1,2,3-Propanetriyl hexanoate	293.2	4.476				
$C_{22}H_{42}O_2$	Butyl oleate	298.2	4.00				
$C_{22}H_{44}O_2$	Butyl stearate	298.2	3.120	0.73894E+02	−0.46261E+00	0.75500E-03	298-343
$C_{22}H_{46}$	Docosane	293.2	2.0840				
$C_{22}H_{46}O$	1-Docosanol	348.2	2.94	0.82062E+01	−0.25069E-01	0.28571E-04	348-373
$C_{24}H_{20}O_4Si$	Tetraphenoxysilane	333.2	3.4915				
$C_{24}H_{38}O_4$	Dioctyl phthalate	293.2	5.22				
$C_{26}H_{50}O_4$	Dioctyl sebacate	299.2	4.01				
$C_{27}H_{50}O_6$	1,2,3-Propanetriyl octanoate	293.2	3.931				
$C_{30}H_{58}O_4$	Ethylene glycol ditetradecanoate	343.2	2.98				
$C_{30}H_{62}$	Triacontane	373.2	1.9112				
$C_{30}H_{62}$	2,6,10,15,19,23-Hexamethyltetracosane	373.2	1.9106				
$C_{34}H_{66}O_4$	Ethylene glycol dipalmitate	348.2	2.89				
$C_{34}H_{68}O_2$	Hexadecyl stearate	333.2	2.61				
$C_{38}H_{74}O_4$	Ethylene glycol distearate	353.2	2.79				
$C_{39}H_{74}O_6$	Glycerol trilaurate	313.2	3.287				
$C_{51}H_{98}O_6$	Glycerol tripalmitate	328.2	2.901	−0.29131E+01	0.32206E-01	−0.44154E-04	328-393
$C_{57}H_{104}O_6$	Glycerol trioleate	293.2	3.109				
$C_{57}H_{104}O_6$	Glycerol trielaidate	313.2	2.980				
$C_{57}H_{110}O_6$	Glycerol tristearate	353.2	2.740				

PERMITTIVITY (DIELECTRIC CONSTANT) OF GASES

This table gives the relative permittivity ε (often called the dielectric constant) of some common gases at a temperature of 20°C and pressure of one atmosphere (101.325 kPa). Values of the permanent dipole moment μ in Debye Units (1 D = 3.33564×10^{-30} C m) are also included.

The density dependence of the permittivity is given by the equation

$$\frac{\varepsilon - 1}{\varepsilon - 2} = \rho_m \left(\frac{4\pi N\alpha}{3} + \frac{4\pi N\mu^2}{9kT} \right)$$

where ρ_m is the molar density, N is Avogadro's number, k is the Boltzmann constant, T is the temperature, and α is the molecular polarizability. Therefore, in regions where the gas can be considered ideal, ε − 1 is approximately proportional to the pressure at constant temperature. For nonpolar gases (μ = 0), ε −1 is inversely proportional to temperature at constant pressure.

The number of significant figures indicates the accuracy of the values given. The values of ε for air, Ar, H_2, He, N_2, O_2, and CO_2 are recommended as reference values; these are accurate to 1 ppm or better.

The second part of the table gives the permittivity of water vapor in equilibrium with liquid water as a function of temperature (derived from Reference 4).

References

1. A. A. Maryott and F. Buckley, *Table of Dielectric Constants and Electric Dipole Moments of Substances in the Gaseous State*, National Bureau of Standards Circular 537, 1953.
2. B. A. Younglove, *J. Phys. Chem. Ref. Data*, 11, Suppl. 1, 1982; 16, 577, 1987 (for data on N_2, H_2, O_2, and hydrocarbons over a range of pressure and temperature).
3. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology*, New Series, Group IV, Vol. 4, Springer-Verlag, Heidelberg, 1980 (for data at high pressures).
4. G. Birnbaum and S. K. Chatterjee, *J. Appl. Phys.*, 23, 220, 1952 (for data on water vapor).

Mol. form.	Name	ε	μ/D
Compounds not containing carbon			
	Air (dry, CO_2 free)	1.0005364	
Ar	Argon	1.0005172	0
BF_3	Boron trifluoride	1.0011	0
BrH	Hydrogen bromide	1.00279	0.827
ClH	Hydrogen chloride	1.00390	1.109
F_3N	Nitrogen trifluoride	1.0013	0.235
F_6S	Sulfur hexafluoride	1.00200	0
HI	Hydrogen iodide	1.00214	0.448
H_2	Hydrogen	1.0002538	0
H_2S	Hydrogen sulfide	1.00344	0.97
H_3N	Ammonia	1.00622	1.471
He	Helium	1.0000650	0
Kr	Krypton	1.00078	0
NO	Nitric oxide	1.00060	0.159
N_2	Nitrogen	1.0005480	0
N_2O	Nitrous oxide	1.00104	0.161
Ne	Neon	1.00013	0
O_2	Oxygen	1.0004947	0
O_2S	Sulfur dioxide	1.00825	1.633
O_3	Ozone	1.0017	0.534
Xe	Xenon	1.00126	0

Mol. form.	Name	ε	μ/D
Compounds containing carbon			
CF_4	Tetrafluoromethane	1.00121	0
CO	Carbon monoxide	1.00065	0.110
CO_2	Carbon dioxide	1.000922	0
CH_3Br	Bromomethane	1.01028	1.822
CH_3Cl	Chloromethane	1.01080	1.892
CH_3F	Fluoromethane	1.00973	1.858
CH_3I	Iodomethane	1.00914	1.62
CH_4	Methane	1.00081	0
C_2H_2	Acetylene	1.00124	0
C_2H_3Cl	Chloroethylene	1.0075	1.45
C_2H_4	Ethylene	1.00134	0
C_2H_5Cl	Chloroethane	1.01325	2.05
C_2H_6	Ethane	1.00140	0
C_2H_6O	Dimethyl ether	1.0062	1.30
C_3H_6	Propene	1.00228	0.366
C_3H_6	Cyclopropane	1.00178	0
C_3H_8	Propane	1.00200	0.084
C_4H_{10}	Butane	1.00258	0
C_4H_{10}	Isobutane	1.00260	0.132

Permittivity of Saturated Water Vapor

t/°C	ε	*t*/°C	ε
0	1.00007	60	1.00144
10	1.00012	70	1.00213
20	1.00022	80	1.00305
30	1.00037	90	1.00428
40	1.00060	100	1.00587
50	1.00095		

AZEOTROPIC DATA FOR BINARY MIXTURES

J. Gmehling, J. Menke, J. Krafczyk, K. Fischer, J.-C. Fontaine, and H. V. Kehiaian

Binary homogeneous (single-phase) liquid mixtures having an extremum (maximum or minimum) vapor pressure P at constant temperature T, as a function of composition, are called azeotropic mixtures, or simply azeotropes. The composition is usually expressed as mole fractions, where x_1 for component 1 in the liquid phase and y_1 for component 1 in the vapor phase are identical. Mixtures that do not show a maximum or minimum are called zeotropic. A maximum (minimum) of the $P(x_1)$ or $P(y_1)$ curves corresponds to a minimum (maximum) of the boiling temperature T at constant P, plotted as a function of x_1 or y_1 [see $T(x_1)$ and $T(y_1)$ curves, Types I and III, in Fig.1]. Azeotropes in which the pressure is a maximum (temperature is a minimum) are often called positive azeotropes, while pressure-minimum (temperature-maximum) azeotropes are called negative azeotropes. The coordinates of an azeotropic point are the azeotropic temperature T_{Az}, pressure P_{Az}, and the vapor-phase composition $y_{1,Az}$, which is the same as the liquid-phase composition $x_{1,Az}$.

In the two-phase liquid-liquid region of partially miscible (heterogeneous) mixtures, the vapor pressure at constant T (or the boiling temperature at constant P) is independent of the global composition x_1 of the two coexisting liquid phases between the equilibrium compositions x_1' and x_1'' ($x_1' < x_1''$).

The constant vapor pressure (boiling temperature) above the two-phase region of certain partially miscible mixtures is usually larger (smaller) than the vapor pressure (boiling temperature) at any other liquid-phase composition in the homogeneous region. In this case, the vapor-phase composition is inside the miscibility gap. Mixtures of this type are called heteroazeotropic mixtures, or simply heteroazeotropes. (Fig. 1, Type II), as opposed to the other types of azeotropes, called homoazeotropes.

Only in a few cases partially miscible mixtures present a positive or negative azeotropic point in the single-phase region, outside the miscibility gap, similar to the azeotropic points of homogeneous mixtures (Fig. 1, Types IV and VI).

A few binary mixtures, for example the system perfluorobenzene + benzene, may present two azeotropic points at constant temperature (pressure), a positive and a negative one. They are called double azeotropic mixtures, or simply double azeotropes. (Fig. 1, Type V).

The knowledge of the occurrence of azeotropic points in binary and higher systems is of special importance for the design of distillation processes. The number of theoretical stages of a distillation column required for the separation depends on the separation factor α_{12}, i.e. the ratio of the K_i-factors ($K_i = y_i/x_i$) of the components i (i = 1, 2). The required separation factor can be calculated with the following simplified relation (Reference 1):

$$\alpha_{12} = K_1/K_2 = (y_1/x_1)/(y_2/x_2) = (\gamma_1 P_1^s)/(\gamma_2 P_2^s) \qquad (1)$$

where γ_i is the activity coefficient of component i in the liquid phase and P_i^s is the vapor pressure of the pure component i.

In distillation processes, only the difference between the separation factor and unity ($\alpha_{12} - 1$) can be exploited for the separation. If the separation factor is close to unity, a large number of theoretical stages is required for the separation. If the binary system to be separated shows an azeotropic point ($\alpha_{12} = 1$), the separation is impossible by ordinary distillation, even with an infinitely large number of stages.

Following eq. (1) azeotropic behavior will always occur in homogeneous binary systems when the vapor pressure ratio P_1^s/P_2^s is equal to the ratio of the activity coefficients γ_2/γ_1.

Various thermodynamic methods based on g^E-models (Wilson, NRTL, UNIQUAC) or group contribution methods (UNIFAC, modified UNIFAC, ASOG, PSRK) can be used for either calculating or predicting the required activity coefficients for the components under given conditions of temperature and composition (Reference 2).

Because of the importance of azeotropic data for the design of distillation processes, compilations have been available in book form for quite some time (References 3-7). The most recent printed data collection was published in 1994 (Reference 8). A revised and extended version appeared in 2004 (Reference 9).

A collection of approximately 47,400 zeotropic and azeotropic data sets, compiled from 6600 references, are stored in a comprehensive computerized data bank (Reference 10). The references from the above-mentioned compilations and from the vapor-liquid equilibrium part of the Dortmund Data Bank (Reference 11) were supplemented by references found from CAS online searches, private communications, data from industry, etc.. Over 24,000 zeotropic data and over 20,000 azeotropic data are available for binary systems. Nearly 90% of the binary azeotropic data show a pressure maximum. In most cases (ca. 90%) these are homogeneous azeotropes, and in approximately 7–8% of the cases heterogeneous azeotropes are reported. Less than 10% of the data stored show a pressure minimum. Approximately 21,000 of the data sets stored were published after 1970.

The table below provides information about azeotropes for 808 selected binary systems. Compounds are listed in the modified Hill order, with carbon-containing compounds following those compounds not containing carbon. In columns 1 and 2 are the molecular formulas of components 1 and 2 written in the Hill convention. In column 3 the names of the components are given, either a systematic IUPAC name or a name in ubiquitous use. Columns 4, 5, and 6 contain the azeotropic coordinates of the mixtures: temperature T_{Az}, pressure P_{Az}, and vapor-phase composition $y_{1,Az}$. The explanation of the type of azeotrope (column 7) is given by the following codes:

O: homogeneous azeotrope in a completely miscible system
L: homogeneous azeotrope in a partially miscible system
E: heterogeneous azeotrope
X: pressure maximum
N: pressure minimum
D: double azeotrope
C: system contains a supercritical compound

References

1. Gmehling, J. and Brehm, A., *Grundoperationen*, Thieme-Verlag, Stuttgart, 1996.
2. Gmehling, J. and Kolbe, B., *Thermodynamik*, VCH-Verlag, Weinheim, 1992.
3. Lecat, M., *Doctoral Dissertation*, 1908.




Figure 1 Different types of binary azeotropic systems: I - homogeneous pressure-maximum azeotrope in a completely miscible system (OX); II - heterogeneous pressure-maximum azeotrope (EX); III - homogeneous pressure-minimum azeotrope in a completely miscible system (ON); IV - homogeneous pressure-maximum azeotrope in a partially miscible system (LX); V - D: double azeotrope (OND, OXD); VI - homogeneous pressure-minimum azeotrope in a partially miscible system (LN). A - $y_1(x_1)$; B - $P(x_1)$ and $P(y_1)$; C - $T(x_1)$ and $T(y_1)$. Continuous line - (x_1); Dashed line - (y_1).

4. Lecat, M., *L'Azeotropisme*, Monograph, L'Auteur, Brussel, 1918.
5. Lecat, M., *Tables Azeotropiques*, Monograph, Lamertin, Brussel 1949.
6. Ogorodnikov, S. K., Lesteva, T. M., and Kogan V. B., *Azeotropic Mixtures*, Khimia, Leningrad, 1971.
7. Horsley, L. H., *Azeotropic Data III*, American Chemical Society, Washington, 1973.
8. Gmehling, J., Menke, J., Krafczyk, J., and Fischer, K., *Azeotropic Data*, 2 Volumes, VCH Verlag, Weinheim, 1994.
9. Gmehling, J., Menke, J., Krafczyk, J., and Fischer, K., *Azeotropic Data*, 2nd Ed., 3 Volumes, VCH Verlag, Weinheim, 2004.
10. Gmehling, J., Menke, J., Krafczyk, J., and Fischer, K., *A Data Bank for Azeotropic Data, Status and Applications*, *Fluid Phase Equilib.* 103, 51, 1995.
11. Dortmund Data Bank, www.ddbst.de

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
$AlCl_3$		**Aluminum chloride**				
	Cl_3OP	Phosphoryl trichloride	660.15	0.5150	101.33	ONC
ClH		**Hydrogen chloride**				
	H_2O	Water	389.34	0.1083	133.32	ONC
Cl_2OS		**Thionyl chloride**				
	Cl_3P	Phosphorus(III) chloride	345.85	0.4200	101.33	OX
Cl_2O_2S		**Sulfuryl chloride**				
	Cl_3P	Phosphorus(III) chloride	364.15	0.5000	101.33	ON
Cl_3OP		**Phosphoryl trichloride**				
	Cl_5Nb	Niobium(V) chloride	536.15	0.4020	101.33	ON
	Cl_5Ta	Tantalum(V) chloride	558.85	0.4650	101.33	ON
Cl_4Ge		**Germanium(IV) chloride**				
	$C_2H_4Cl_2$	1,2-Dichloroethane	350.75	0.4630	101.33	OX
Cl_4Si		**Tetrachlorosilane**				
	C_2H_3N	Acetonitrile	321.05	0.6900	101.33	EX
Cl_5Mo		**Molybdenum(V) chloride**				
	Cl_6W	Tungsten(VI) chloride	274.70	0.9750	101.33	OX
FH		**Hydrogen fluoride**				
	H_2O	Water	382.15	0.3508	101.33	ON
	CCl_3F	Trichlorofluoromethane	283.15	0.7840	129.45	EX
HNO_3		**Nitric acid**				
	H_2O	Water	393.20	0.3820	101.33	ON
H_2O		**Water**				
	$CHCl_3$	Trichloromethane	329.27	0.1603	101.33	EX
	CH_2O	Formaldehyde	355.75	0.9300	53.33	OX
	CH_2O_2	Formic acid	380.35	0.4272	101.33	ON
	CH_3NO_2	Nitromethane	356.90	0.5160	101.33	EX
	C_2HCl_3	Trichloroethene	346.55	0.3560	101.33	EX
	C_2H_3N	Acetonitrile	349.95	0.3100	101.33	OX
	$C_2H_4Cl_2$	1,2-Dichloroethane	345.43	0.3570	101.33	EX
	C_2H_6O	Ethanol	351.25	0.1030	101.33	OX
	$C_2H_8N_2$	1,2-Ethanediamine	391.85	0.4450	101.33	ON
	C_3H_3N	Acrylonitrile	344.05	0.2850	101.33	EX
	C_3H_4O	Acrolein	325.45	0.0730	101.33	LX
	C_3H_6O	Propanal	320.65	0.0600	101.33	LX
	C_3H_6O	Allyl alcohol	361.15	0.5562	101.33	OX
	$C_3H_6O_2$	Methyl acetate	330.05	0.1060	103.62	LX
	$C_3H_6O_2$	1,3-Dioxolane	344.95	0.2520	101.30	OX
	$C_3H_6O_2$	Ethyl formate	325.75	0.0700	101.33	EX
	$C_3H_6O_2$	Propanoic acid	373.05	0.9500	101.33	OX
	C_3H_7Br	1-Bromopropane	336.35	0.2210	101.33	EX
	C_3H_8O	1-Propanol	360.80	0.5680	101.33	OX
	C_3H_8O	2-Propanol	353.70	0.3260	101.33	OX
	$C_3H_8O_2$	2-Methoxyethanol	372.65	0.9441	99.99	OX
	$C_3H_8O_2$	Dimethoxymethane	315.05	0.0269	101.38	LX
	C_4H_5N	*cis*-2-Butenenitrile	358.45	0.3832	101.33	EX
	C_4H_5N	*trans*-2-Butenenitrile	363.05	0.6843	101.33	EX
	C_4H_5N	Pyrrole	348.15	0.7514	50.13	EX
	$C_4H_6O_2$	Methacrylic acid	372.25	0.9464	98.93	OX
	C_4H_8O	2-Butanone	346.54	0.3480	101.33	LX
	C_4H_8O	Tetrahydrofuran	336.67	0.1828	101.33	OX
	C_4H_8O	Isobutanal	332.80	0.1698	100.99	EX
	$C_4H_8O_2$	Ethyl acetate	343.55	0.2990	101.33	EX
	$C_4H_8O_2$	Butanoic acid	372.95	0.9559	101.33	OX
	$C_4H_8O_2$	1,4-Dioxane	360.65	0.5280	101.33	OX
	$C_4H_8O_2$	Propyl formate	344.85	0.3090	101.33	EX
	$C_4H_8O_2$	Methyl propanoate	344.75	0.3050	101.33	EX
	C_4H_9Br	1-Bromobutane	353.95	0.4950	101.33	EX

Comp. 1	Comp. 2 (Molecular formula)	Name	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	Type
	C_4H_9Br	1-Bromo-2-methylpropane	348.45	0.3730	101.33	EX
	C_4H_9Cl	1-Chloro-2-methylpropane	333.95	0.1970	101.33	LX
	$C_4H_{10}O$	1-Butanol	365.45	0.7540	101.33	EX
	$C_4H_{10}O$	2-Butanol	360.50	0.6200	101.33	LX
	$C_4H_{10}O$	2-Methyl-2-propanol	353.00	0.4011	101.33	OX
	$C_4H_{11}N$	Butylamine	349.85	0.0700	101.33	OX
	C_5H_5N	Pyridine	367.30	0.7500	101.33	OX
	C_5H_8	2-Methyl-1,3-butadiene	305.85	0.0520	101.33	EX
	C_5H_8	Methylenecyclobutane	313.15	0.0212	101.30	EX
	C_5H_8O	Cyclopropyl methyl ketone	361.65	0.7060	101.19	EX
	$C_5H_8O_2$	Methyl methacrylate	354.45	0.4996	101.33	EX
	C_5H_{10}	2-Methyl-2-butene	309.75	0.0650	101.33	EX
	$C_5H_{10}O$	3-Methyl-2-buten-1-ol	369.55	0.9141	101.33	EX
	$C_5H_{10}O$	3-Methyl-3-buten-1-ol	333.15	0.8680	101.33	EX
	$C_5H_{10}O$	2-Methyl-3-buten-2-ol	359.25	0.5770	101.33	LX
	$C_5H_{10}O$	3-Pentanone	356.05	0.4750	101.33	EX
	$C_5H_{10}O_2$	Isopropyl acetate	349.75	0.3960	101.33	EX
	$C_5H_{10}O_2$	Propyl acetate	355.91	0.5228	101.33	EX
	$C_5H_{10}O_2$	Butyl formate	356.95	0.5360	101.33	EX
	$C_5H_{10}O_2$	Isobutyl formate	352.75	0.4460	101.33	EX
	$C_5H_{12}O$	3-Methyl-1-butanol	367.97	0.8265	101.33	EX
	$C_5H_{12}O$	2-Methyl-2-butanol	360.85	0.6355	101.75	EX
	$C_5H_{12}O$	1-Pentanol	369.08	0.8633	101.33	EX
	$C_5H_{12}O$	2-Pentanol	363.15	0.7550	92.49	EX
	C_6H_6	Benzene	342.35	0.2980	101.33	EX
	C_6H_7N	Aniline	372.55	0.9580	101.33	EX
	C_6H_7N	4-Methylpyridine	370.50	0.8972	101.33	OX
	C_6H_{10}	Cyclohexene	343.95	0.3090	101.33	EX
	$C_6H_{10}O$	Cyclohexanone	369.45	0.8694	101.33	EX
	$C_6H_{10}O$	Methyldihydropyran (unspecified isomer)	360.75	0.5841	100.93	EX
	$C_6H_{10}O_2$	4-Vinyl-1,3-dioxane	367.65	0.8955	101.33	EX
	C_6H_{12}	1-Hexene	318.15	0.1510	63.35	EX
	$C_6H_{12}O_2$	Butyl acetate	363.35	0.7013	101.33	EX
	$C_6H_{12}O_2$	Isobutyl acetate	361.05	0.6440	101.33	EX
	$C_6H_{12}O_2$	4,4-Dimethyl-1,3-dioxane	366.00	0.7779	101.33	EX
	$C_6H_{12}O_2$	4,5-Dimethyl-1,3-dioxane (unspecified isomer)	365.05	0.7966	101.50	EX
	$C_6H_{12}O_2$	4-Ethyl-1,3-dioxane	365.75	0.7257	101.30	EX
	$C_6H_{12}O_2$	Diacetone alcohol	370.00	0.9900	90.79	OX
	$C_6H_{12}O_2$	Propyl propanoate	362.05	0.6600	101.33	EX
	$C_6H_{13}N$	Cyclohexylamine	369.55	0.8692	101.33	OX
	C_6H_{14}	Hexane	334.75	0.2110	101.33	EX
	$C_6H_{14}O$	Butyl ethyl ether	349.85	0.4070	101.33	EX
	$C_6H_{14}O$	1-Hexanol	367.89	0.9432	101.33	EX
	$C_6H_{14}O_3$	Di(ethylene glycol) dimethyl ether	372.70	0.9679	101.33	OX
	$C_6H_{15}N$	Diisopropylamine	347.25	0.3654	101.33	EX
	$C_6H_{15}N$	Dipropylamine	359.00	0.6046	101.33	EX
	C_7H_8	Toluene	357.25	0.5230	101.33	EX
	C_7H_8O	Benzyl alcohol	373.05	0.9840	101.33	EX
	C_7H_9N	2,6-Dimethylpyridine	369.17	0.8647	101.33	EX
	$C_7H_{12}O_4$	1,2-Propanediol diacetate	358.15	0.9740	59.41	EX
	C_7H_{14}	1-Heptene	350.20	0.4100	101.33	EX
	$C_7H_{14}O_2$	Isopentyl acetate	367.05	0.7990	101.46	EX
	$C_7H_{14}O_2$	Butyl propanoate	367.95	0.8340	101.33	EX
	C_7H_{16}	Heptane	352.35	0.4510	101.33	EX
	$C_7H_{16}O$	1-Heptanol	371.99	0.9703	101.33	EX
	C_8H_8	Styrene	367.15	0.8000	101.33	EX
	C_8H_8O	Acetophenone	371.15	0.9675	101.19	EX
	C_8H_{10}	*m*-Xylene	365.15	0.7667	101.33	EX

Molecular formula

Comp. 1	Comp. 2	Name	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	Type
	C_8H_{10}	*p*-Xylene	365.15	0.7450	101.33	EX
	C_8H_{10}	Ethylbenzene	364.15	0.7221	101.33	EX
	$C_8H_{16}O_2$	Butyl butanoate	369.85	0.9110	101.33	EX
	C_8H_{18}	Octane	362.75	0.6850	101.33	EX
	C_8H_{18}	2,2,4-Trimethylpentane	351.95	0.4420	101.33	EX
	$C_8H_{18}O$	Dibutyl ether	368.65	0.7628	101.33	EX
	$C_8H_{18}O$	1-Octanol	372.75	0.9820	101.33	EX
	$C_8H_{19}N$	Dibutylamine	370.05	0.8850	101.33	EX
	C_9H_{10}	Isopropenylbenzene	369.95	0.8880	101.33	EX
	C_9H_{12}	Isopropylbenzene	368.15	0.8340	101.33	EX
	$C_9H_{12}O$	2-Phenyl-2-propanol	371.25	0.9718	101.33	EX
	C_9H_{20}	Nonane	367.95	0.8280	101.33	EX
	$C_9H_{20}O$	1-Nonanol	373.00	0.9846	101.33	EX
	$C_{10}H_{22}$	Decane	370.75	0.9180	101.33	EX
	$C_{10}H_{22}O$	1-Decanol	373.13	0.9865	101.33	EX
	$C_{12}H_{27}N$	Tributylamine	372.80	0.9762	101.46	EX
CCl_4		**Tetrachloromethane**				
	C_2H_6O	Ethanol	338.19	0.6140	101.33	OX
	C_3H_6O	Acetone	341.25	0.0337	149.93	OX
	C_3H_8O	1-Propanol	346.28	0.8032	101.33	OX
	C_3H_8O	2-Propanol	341.83	0.6686	101.33	OX
	C_4H_6O	2-Butenal	348.15	0.6500	97.86	OX
	C_4H_6O	2-Methylpropenal	339.15	0.6000	97.86	OX
	C_4H_8O	2-Butanone	346.99	0.6630	101.33	OX
	$C_4H_8O_2$	Ethyl acetate	347.95	0.5700	101.33	OX
	$C_4H_{10}O$	1-Butanol	349.71	0.9500	101.33	OX
	$C_4H_{10}O$	2-Methyl-1-propanol	348.95	0.9080	101.33	OX
	$C_5H_{10}O$	2-Methyl-3-buten-2-ol	348.45	0.9009	101.06	OX
CS_2		**Carbon disulfide**				
	CH_4O	Methanol	310.65	0.7000	101.33	LX
$CHCl_3$		**Trichloromethane**				
	CH_4O	Methanol	328.15	0.6480	107.99	OX
	C_2H_6O	Ethanol	332.45	0.8410	101.33	OX
	C_3H_6O	Acetone	337.58	0.6398	101.33	ON
	$C_3H_6O_2$	Methyl acetate	337.51	0.6760	101.33	ON
	C_3H_8O	2-Propanol	334.15	0.9500	101.33	OX
	C_4H_6O	2-Butenal	329.15	0.9950	97.86	OX
	C_6H_{12}	2-Methyl-1-pentene	333.95	0.6235	101.19	OX
	C_6H_{14}	Hexane	333.45	0.7840	101.33	OX
CHN		**Hydrogen cyanide**				
	C_3H_5Cl	3-Chloropropene	296.45	0.8016	101.33	OX
CH_2Cl_2		**Dichloromethane**				
	C_2H_6O	Ethanol	312.05	0.9600	101.33	OX
CH_2O_2		**Formic acid**				
	$C_2H_4Cl_2$	1,2-Dichloroethane	350.17	0.4275	101.33	OX
	$C_5H_{10}O_2$	Butyl formate	372.15	0.8700	101.33	OX
	C_8H_{10}	*m*-Xylene	365.95	0.8545	101.33	EX
CH_3NO_2		**Nitromethane**				
	C_2H_6O	Ethanol	333.15	0.2850	53.61	OX
	C_3H_7Br	1-Bromopropane	343.25	0.1020	99.82	OX
	$C_4H_8O_2$	1,4-Dioxane	373.25	0.4101	101.48	OX
	C_5H_{10}	2-Methyl-2-butene	311.15	0.0570	101.33	LX
	C_7H_{14}	Methylcyclohexane	354.85	0.5123	101.33	EX
	C_7H_{16}	Heptane	353.25	0.4790	101.33	EX
	C_8H_{18}	Octane	363.38	0.6964	99.73	EX
	C_9H_{20}	Nonane	369.29	0.8403	99.73	EX
	$C_{10}H_{22}$	Decane	371.96	0.9239	99.73	EX
	$C_{11}H_{24}$	Undecane	373.16	0.9619	99.73	EX

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
	$C_{12}H_{26}$	Dodecane	373.75	0.9846	99.73	EX
CH_4O		**Methanol**				
	$C_2HBrClF_3$	2-Bromo-2-chloro-1,1,1-trifluoroethane	317.25	0.1890	93.33	OX
	C_2H_5Br	Bromoethane	308.05	0.1610	101.33	OX
	C_3H_5Cl	3-Chloropropene	312.15	0.2570	100.39	OX
	C_3H_6O	Acetone	328.29	0.2400	101.33	OX
	$C_3H_6O_2$	Methyl acetate	328.15	0.3480	107.19	OX
	$C_3H_6O_2$	1,3-Dioxolane	334.66	0.6910	101.30	OX
	$C_3H_6O_2$	Ethyl formate	318.15	0.3000	81.34	OX
	$C_3H_6O_3$	Dimethyl carbonate	337.25	0.8504	102.52	OX
	C_3H_7Cl	1-Chloropropane	313.35	0.2500	101.59	OX
	$C_4H_4F_6O$	Bis(2,2,2-trifluoroethyl) ether	326.28	0.4450	101.30	OX
	$C_4H_6O_2$	Vinyl acetate	332.05	0.6182	101.33	OX
	C_4H_8O	2-Butanone	323.15	0.8020	58.80	OX
	C_4H_8O	Tetrahydrofuran	332.75	0.5040	101.33	OX
	$C_4H_8O_2$	Ethyl acetate	335.66	0.7120	101.33	OX
	$C_4H_{10}O$	Diethyl ether	305.15	0.0500	93.33	OX
	$C_4H_{10}O_2$	Dimethylacetal	330.35	0.4700	101.33	OX
	$C_5H_3F_9O$	1,1,1,2,3,3-Hexafluoro-3-(2,2,2-trifluoroethoxy)propane	330.67	0.5600	101.30	OX
	C_5H_6	1,3-Cyclopentadiene	309.05	0.2120	101.33	OX
	C_5H_8	2-Methyl-1,3-butadiene	303.55	0.1670	101.33	OX
	C_5H_8	Methylenecyclobutane	309.05	0.2190	101.33	OX
	C_5H_8	1-Methylcyclobutene	304.85	0.1900	101.33	OX
	C_5H_8	*cis*-1,3-Pentadiene	311.10	0.2300	101.33	OX
	C_5H_8	*trans*-1,3-Pentadiene	309.65	0.2110	101.33	OX
	C_5H_{10}	2-Methyl-1-butene	300.55	0.1720	101.33	OX
	C_5H_{10}	3-Methyl-1-butene	291.05	0.0890	101.33	OX
	C_5H_{10}	2-Methyl-2-butene	306.25	0.2160	101.33	OX
	C_5H_{10}	1-Pentene	300.05	0.1469	102.47	OX
	$C_5H_{10}O$	2,3-Epoxy-2-methylbutane	334.95	0.6590	101.33	OX
	C_5H_{12}	Isopentane	297.05	0.0930	101.33	OX
	C_5H_{12}	Pentane	303.20	0.1930	101.30	OX
	$C_5H_{12}O$	Butyl methyl ether	330.00	0.5515	100.08	OX
	$C_5H_{12}O$	Methyl *tert*-butyl ether	325.00	0.3140	103.15	OX
	$C_5H_{12}O$	Ethyl propyl ether	330.00	0.4050	112.25	OX
	$C_5H_{12}O_2$	Diethoxymethane	336.03	0.8127	101.52	OX
	$C_5H_{12}O_2$	2,2-Dimethoxypropane	334.15	0.7250	100.00	OX
	$C_5H_{14}N_2$	*N,N,N',N'*-Tetramethylmethanediamine	335.15	0.7670	101.33	OX
	C_6F_6	Hexafluorobenzene	318.15	0.6100	61.73	OX
	C_6H_5F	Fluorobenzene	333.35	0.6625	101.62	OX
	C_6H_6	Benzene	331.56	0.6090	101.33	OX
	C_6H_{12}	Cyclohexane	328.75	0.6090	106.66	OX
	C_6H_{12}	2-Methyl-1-pentene	330.00	0.4517	141.80	OX
	C_6H_{14}	2,3-Dimethylbutane	313.15	0.3620	85.50	OX
	C_6H_{14}	Hexane	333.15	0.5160	149.64	OX
	$C_6H_{14}O$	*tert*-Butyl ethyl ether	330.95	0.6002	101.54	OX
	$C_6H_{14}O$	Diisopropyl ether	330.00	0.5390	101.61	OX
	$C_6H_{14}O$	Butyl ethyl ether	335.00	0.8010	98.84	OX
	$C_6H_{14}O$	2-Methoxy-2-methylbutane	335.55	0.7735	101.69	OX
	C_7H_8	Toluene	336.65	0.8820	101.33	OX
	C_7H_{14}	Methylcyclohexane	333.15	0.7520	102.87	EX
	C_7H_{16}	Heptane	331.95	0.7279	101.33	OX
	$C_7H_{16}O$	2-Ethoxy-2-methylbutane	335.15	0.8736	97.28	OX
	C_8H_{18}	Octane	335.55	0.8830	101.33	LX
	C_9H_{20}	Nonane	337.25	0.9526	101.33	OX
$C_2Cl_3F_3$		**1,1,2-Trichloro-1,2,2-trifluoroethane**				
	$C_2H_3F_3O$	2,2,2-Trifluoroethanol	316.58	0.7770	101.33	EX

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
	C_2H_6O	Ethanol	317.75	0.8456	101.42	OX
	C_3H_8O	2-Propanol	319.35	0.9159	100.95	OX
	$C_4H_{10}O$	2-Methyl-2-propanol	319.95	0.9426	101.09	OX
C_2Cl_4		**Tetrachloroethene**				
	$C_2H_3Cl_3$	1,1,2-Trichloroethane	385.95	0.2115	101.33	OX
	C_8H_{16}	1-Octene	393.15	0.5900	101.33	OX
	C_8H_{16}	*cis*-4-Octene	393.65	0.7100	101.33	OX
	C_8H_{16}	*trans*-4-Octene	393.45	0.6700	101.33	OX
	C_8H_{18}	Octane	371.90	0.8781	53.44	OX
$C_2Cl_4F_2$		**1,1,2,2-Tetrachloro-1,2-difluoroethane**				
	$C_2H_4Cl_2$	1,2-Dichloroethane	353.80	0.2700	101.33	OX
$C_2HBrClF_3$		**2-Bromo-2-chloro-1,1,1-trifluoroethane**				
	$C_4H_{10}O$	Diethyl ether	323.65	0.7200	93.33	ON
C_2HCl_3		**Trichloroethene**				
	$C_2H_4Cl_2$	1,2-Dichloroethane	355.35	0.3324	101.36	OX
	C_2H_6O	Ethanol	343.85	0.4741	101.33	OX
	C_4H_6O	2-Butenal	360.15	0.9000	97.86	OX
	C_6H_{12}	Cyclohexane	353.40	0.0975	101.32	OX
$C_2H_2Cl_2$		***trans*-1,2-Dichloroethene**				
	$C_5H_3F_9O$	1,1,1,2,3,3-Hexafluoro-3-(2,2,2-trifluoroethoxy)propane	318.50	0.8390	101.30	OX
C_2H_3N		**Acetonitrile**				
	C_3H_8O	2-Propanol	348.15	0.5287	100.81	OX
	$C_4H_6O_2$	Vinyl acetate	344.65	0.1948	98.33	OX
	C_4H_8O	2-Butanone	352.15	0.3195	101.15	OX
	C_4H_8O	Tetrahydrofuran	338.95	0.0784	101.13	OX
	$C_4H_{10}O$	2-Methyl-2-propanol	333.15	0.6200	56.93	OX
	C_5H_8	2-Methyl-1,3-butadiene	306.75	0.0410	101.33	OX
	C_5H_8	Methylenecyclobutane	312.45	0.1450	101.33	OX
	$C_5H_8O_2$	Methyl methacrylate	355.25	0.9866	102.07	OX
	C_5H_{10}	2-Methyl-2-butene	308.95	0.1320	101.33	OX
	C_5H_{10}	1-Pentene	301.85	0.0830	101.33	OX
	C_5H_{12}	Isopentane	298.45	0.1040	101.33	EX
	C_6H_6	Benzene	328.15	0.4560	54.65	OX
	$C_6H_{14}O$	2-Methoxy-2-methylbutane	346.13	0.5835	100.56	OX
	$C_7H_{16}O$	2-Ethoxy-2-methylbutane	348.85	0.7219	98.99	OX
	$C_{10}H_{20}$	1-Decene	354.55	0.9924	100.51	OX
$C_2H_4Cl_2$		**1,1-Dichloroethane**				
	C_3H_8O	2-Propanol	329.55	0.8928	101.60	OX
	C_6H_{14}	Hexane	329.30	0.8025	101.21	OX
$C_2H_4Cl_2$		**1,2-Dichloroethane**				
	C_3H_8O	2-Propanol	347.25	0.5258	100.32	OX
	$C_4H_{10}O$	2-Methyl-1-propanol	356.05	0.9173	101.26	OX
	$C_4H_{10}O$	2-Methyl-2-propanol	349.45	0.5336	101.43	OX
	C_7H_{14}	Methylcyclohexane	354.65	0.8036	101.21	OX
	C_8H_{18}	2,2,4-Trimethylpentane	343.15	0.7600	73.13	OX
C_2H_4O		**Acetaldehyde**				
	C_4H_6	1,3-Butadiene	268.15	0.0520	101.33	OX
	C_5H_8	2-Methyl-1,3-butadiene	292.23	0.8140	101.33	OX
$C_2H_4O_2$		**Acetic acid**				
	C_5H_5N	Pyridine	411.25	0.5780	101.33	ON
	$C_5H_{12}O$	3-Methyl-2-butanol	392.65	0.7210	101.33	ON
	C_6H_7N	2-Methylpyridine	417.27	0.5120	101.33	ON
	$C_6H_{10}O_2$	Vinyl butanoate	386.45	0.5750	101.33	OX
	C_6H_{14}	Hexane	341.40	0.0839	101.33	OX
	C_7H_9N	2,4-Dimethylpyridine	435.45	0.3022	101.33	ON
	C_7H_{16}	Heptane	364.95	0.4490	101.33	OX
	C_8H_{10}	*o*-Xylene	389.75	0.8640	101.33	OX

Molecular formula

Comp. 1	Comp. 2	Name	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	Type
	C_8H_{10}	*p*-Xylene	388.40	0.8200	101.33	OX
	C_8H_{18}	Octane	378.85	0.6870	101.33	OX
	C_9H_{20}	Nonane	386.05	0.8250	101.33	OX
	$C_{10}H_{22}$	Decane	390.05	0.9250	101.33	OX
	$C_{11}H_{24}$	Undecane	391.15	0.9720	101.33	OX
$C_2H_4O_2$		**Methyl formate**				
	C_2H_5Br	Bromoethane	303.05	0.7360	101.33	OX
	$C_4H_{10}O$	Diethyl ether	301.55	0.6030	101.33	OX
	C_5H_8	2-Methyl-1,3-butadiene	298.90	0.5150	101.33	OX
	C_5H_{10}	2-Methyl-2-butene	297.75	0.5760	101.33	OX
	C_5H_{12}	Isopentane	291.55	0.4920	101.33	OX
	C_5H_{12}	Pentane	294.85	0.5740	101.33	OX
	C_6H_{14}	Hexane	302.65	0.8490	101.33	OX
C_2H_5Br		**Bromoethane**				
	C_5H_{10}	2-Methyl-2-butene	308.55	0.5110	101.33	OX
	C_5H_{12}	Isopentane	300.55	0.2180	101.33	OX
$C_2H_5NO_2$		**Nitroethane**				
	$C_4H_{10}O$	2-Methyl-1-propanol	375.81	0.4080	101.33	OX
	C_7H_{16}	Heptane	362.95	0.3520	101.33	OX
C_2H_6O		**Ethanol**				
	C_3H_3N	Acrylonitrile	343.95	0.4440	101.33	OX
	$C_3H_6O_2$	Methyl acetate	329.79	0.0362	101.33	OX
	$C_4H_3F_7O$	1,1,2,2-Tetrafluoroethyl 1,1,1-trifluoroethyl ether	326.67	0.2000	101.30	OX
	$C_4H_4F_6O$	Bis(2,2,2-trifluoroethyl) ether	331.90	0.2840	101.30	OX
	C_4H_8O	Butanal	345.45	0.3690	101.33	OX
	C_4H_8O	2-Butanone	347.15	0.5080	101.33	OX
	C_4H_8O	Tetrahydrofuran	344.95	0.1290	125.00	OX
	$C_4H_8O_2$	Ethyl acetate	344.85	0.4590	101.33	OX
	$C_4H_8O_2$	1,4-Dioxane	351.33	0.9480	101.33	OX
	$C_4H_8O_2$	Methyl propanoate	346.30	0.5140	103.91	OX
	$C_4H_{11}N$	Butylamine	354.99	0.5900	101.33	ON
	$C_5H_3F_9O$	1,1,1,2,3,3-Hexafluoro-3-(2,2,2-trifluoroethoxy)propane	337.88	0.3980	101.30	OX
	C_5H_8	2-Methyl-1,3-butadiene	305.95	0.1500	101.33	OX
	C_5H_8	Cyclopentene	323.40	0.1440	134.00	OX
	C_5H_{10}	2-Methyl-2-butene	309.79	0.0795	101.33	OX
	C_5H_{10}	Cyclopentane	323.44	0.1800	121.00	OX
	$C_5H_{10}O$	2,3-Epoxy-2-methylbutane	343.45	0.2930	101.33	OX
	$C_5H_{10}O$	3-Methyl-2-butanone	350.85	0.8250	101.33	OX
	$C_5H_{10}O$	2-Pentanone	351.15	0.9779	100.50	OX
	$C_5H_{10}O$	3-Pentanone	351.33	0.9590	101.33	OX
	$C_5H_{10}O_2$	Isopropyl acetate	349.85	0.7010	101.33	OX
	$C_5H_{10}O_2$	Methyl butanoate	346.30	0.8800	83.88	OX
	C_5H_{12}	Isopentane	299.95	0.0540	101.33	OX
	C_5H_{12}	Pentane	307.15	0.0537	101.33	OX
	$C_5H_{12}O$	Methyl *tert*-butyl ether	327.75	0.0380	101.33	OX
	$C_5H_{12}O_2$	Diethoxymethane	348.30	0.6497	102.35	OX
	C_6H_5F	Fluorobenzene	343.85	0.4752	101.54	OX
	C_6H_6	Benzene	341.25	0.4600	101.33	OX
	C_6H_{12}	Cyclohexane	337.95	0.4540	102.26	OX
	C_6H_{14}	Hexane	331.65	0.3410	101.33	OX
	$C_6H_{14}O$	*tert*-Butyl ethyl ether	339.95	0.3728	101.72	OX
	$C_6H_{14}O$	2-Methoxy-2-methylbutane	346.81	0.5820	101.32	OX
	C_7H_8	Toluene	349.75	0.8152	101.33	OX
	$C_7H_{16}O$	2-Ethoxy-2-methylbutane	349.35	0.7644	101.54	OX
	C_8H_{18}	Octane	349.85	0.8250	101.33	OX
	C_8H_{18}	2,2,4-Trimethylpentane	344.42	0.6450	101.33	OX

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
	C_9H_{20}	Nonane	351.35	0.9400	101.33	OX
$C_2H_6O_2$		**1,2-Ethanediol**				
	$C_5H_{12}O_3$	Di(ethylene glycol) monomethyl ether	463.95	0.4388	101.33	OX
	$C_6H_{14}O_3$	Di(ethylene glycol) monoethyl ether	467.15	0.6480	101.33	OX
	C_7H_8O	*o*-Cresol	462.67	0.3797	101.33	OX
	$C_7H_{16}O_3$	Di(ethylene glycol) monoisopropyl ether	466.35	0.6964	101.33	OX
	$C_7H_{16}O_3$	Di(ethylene glycol) monopropyl ether	468.55	0.8448	101.33	OX
	$C_7H_{16}O_3$	Di(propylene glycol) monomethyl ether (unspecified isomer)	457.65	0.3500	101.33	OX
	$C_8H_{11}N$	2,4,6-Trimethylpyridine	443.65	0.1734	101.33	OX
	$C_8H_{18}O_3$	Di(ethylene glycol) monobutyl ether	469.15	0.9102	101.33	OX
	$C_8H_{18}O_3$	Di(ethylene glycol) monoisobutyl ether	467.55	0.8355	101.33	OX
	$C_8H_{18}O_3$	Di(propylene glycol) monoethyl ether (unspecified isomer)	458.65	0.4800	101.33	OX
	$C_9H_{20}O_3$	Di(propylene glycol) monopropyl ether (unspecified isomer)	463.15	0.6590	101.33	OX
	$C_{10}H_{22}O_3$	Di(propylene glycol) monobutyl ether (unspecified isomer)	465.75	0.8130	101.33	OX
C_3H_3N		**Acrylonitrile**				
	C_5H_8	Methylenecyclobutane	313.80	0.1275	101.33	OX
	C_6H_6	Benzene	347.45	0.5575	101.46	OX
	C_6H_{12}	Cyclohexane	337.75	0.4836	101.94	OX
	C_6H_{14}	Hexane	330.90	0.4048	101.05	OX
C_3H_4O		**Acrolein**				
	C_5H_8	2-Methyl-1,3-butadiene	306.45	0.1980	101.33	OX
C_3H_6O		**Propanal**				
	C_5H_8	2-Methyl-1,3-butadiene	306.35	0.1700	101.33	OX
	C_5H_8	Methylenecyclobutane	311.30	0.3600	101.33	OX
C_3H_6O		**Acetone**				
	$C_3H_6O_2$	Methyl acetate	328.85	0.6470	101.33	OX
	C_3H_7Br	1-Bromopropane	328.75	0.9915	99.75	OX
	C_4H_8O	Tetrahydrofuran	328.85	0.9603	100.35	OX
	C_4H_9Cl	2-Chloro-2-methylpropane	322.05	0.1944	102.11	OX
	C_5H_8	2-Methyl-1,3-butadiene	306.95	0.0610	101.33	OX
	C_5H_8	Methylenecyclobutane	311.25	0.2800	101.33	OX
	C_5H_8	1-Methylcyclobutene	307.75	0.2220	101.33	OX
	C_5H_{10}	2-Methyl-1-butene	303.25	0.1400	101.33	OX
	C_5H_{10}	2-Methyl-2-butene	308.75	0.2440	101.33	OX
	C_5H_{12}	Isopentane	298.75	0.1730	101.33	OX
	$C_5H_{12}O$	Methyl *tert*-butyl ether	324.35	0.4824	102.19	OX
	C_6H_{12}	Cyclohexane	330.05	0.7590	109.32	OX
	C_6H_{12}	1-Hexene	323.35	0.5973	101.40	OX
	C_6H_{12}	2-Methyl-1-pentene	333.40	0.5793	140.60	OX
	C_6H_{14}	Hexane	322.95	0.6480	101.33	OX
	$C_6H_{14}O$	Diisopropyl ether	327.10	0.7424	100.17	OX
	$C_6H_{15}N$	Triethylamine	318.15	0.9800	68.13	OX
	C_7H_{14}	Methylcyclohexane	318.15	0.9500	68.66	OX
C_3H_6O		**Allyl alcohol**				
	$C_5H_{10}O_2$	Ethyl propanoate	367.65	0.5597	99.79	OX
	C_6H_6	Benzene	349.90	0.2203	101.33	OX
	C_6H_{12}	Cyclohexane	333.15	0.2790	63.98	OX
$C_3H_6O_2$		**Methyl acetate**				
	C_3H_7Br	1-Bromopropane	329.60	0.9727	99.56	OX
	C_6H_{10}	Cyclohexene	330.35	0.9121	102.87	OX
	C_6H_{12}	Cyclohexane	328.65	0.8000	101.33	OX
	C_6H_{12}	Methylcyclopentane	325.85	0.6917	99.50	OX
	C_6H_{12}	1-Hexene	323.15	0.6340	92.08	OX
	C_6H_{12}	2-Methyl-1-pentene	325.15	0.5931	100.38	OX

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
	C_6H_{14}	Hexane	326.65	0.6590	106.66	OX
	C_7H_{16}	Heptane	323.15	0.9570	79.48	OX
$C_3H_6O_2$		**Ethyl formate**				
	C_3H_7Br	2-Bromopropane	326.15	0.7090	101.33	OX
	C_6H_{12}	Cyclohexane	323.15	0.8210	91.46	OX
$C_3H_6O_2$		**Propanoic acid**				
	C_5H_5N	Pyridine	421.75	0.6860	101.33	ON
$C_3H_6O_3$		**Dimethyl carbonate**				
	$C_5H_{12}O_2$	Diethoxymethane	358.71	0.4437	100.42	OX
	C_6H_6	Benzene	353.50	0.1366	100.48	OX
	C_6H_{12}	Cyclohexane	346.95	0.3780	101.49	OX
	C_6H_{12}	Methylcyclopentane	342.35	0.2680	103.46	OX
	C_6H_{14}	Hexane	338.15	0.2540	98.46	OX
	$C_6H_{14}O$	Dipropyl ether	356.45	0.5044	100.73	OX
	C_7H_{16}	Heptane	355.15	0.5930	99.67	OX
C_3H_7Br		**1-Bromopropane**				
	C_3H_8O	2-Propanol	339.15	0.7349	99.97	OX
	C_6H_{12}	Cyclohexane	343.35	0.9219	98.84	OX
C_3H_7NO		***N,N*-Dimethylformamide**				
	C_7H_{16}	Heptane	370.15	0.0800	101.33	OX
	$C_{10}H_{16}$	1,4-Dimethyl-4-vinylcyclohexene	415.65	0.5880	101.33	OX
	$C_{10}H_{16}$	1-Methyl-3-(1-methylethylidene)cyclohexene	419.05	0.7250	101.33	OX
$C_3H_7NO_2$		**1-Nitropropane**				
	C_7H_{16}	Heptane	369.25	0.1630	101.33	OX
$C_3H_7NO_2$		**2-Nitropropane**				
	C_7H_{16}	Heptane	367.55	0.2920	101.33	OX
C_3H_8O		**1-Propanol**				
	$C_4H_3F_7O$	1,1,2,2-Tetrafluoroethyl 1,1,1-trifluoroethyl ether	329.23	0.0350	101.30	OX
	$C_4H_4F_6O$	Bis(2,2,2-trifluoroethyl) ether	336.22	0.1100	101.30	OX
	$C_4H_6O_2$	2,3-Butanedione	359.30	0.3600	100.67	OX
	$C_4H_8O_2$	1,4-Dioxane	365.30	0.6418	101.30	OX
	$C_5H_{10}O_2$	Propyl acetate	367.88	0.6190	101.33	OX
	$C_5H_{12}O_2$	Diethoxymethane	359.01	0.2320	99.43	OX
	C_6H_6	Benzene	350.20	0.2060	101.33	OX
	C_6H_{12}	Cyclohexane	347.68	0.2490	101.33	OX
	C_6H_{12}	Methylcyclopentane	340.85	0.1729	101.19	OX
	$C_6H_{12}O_2$	4,4-Dimethyl-1,3-dioxane	368.20	0.9597	101.30	OX
	C_6H_{14}	Hexane	348.15	0.1900	137.23	OX
	C_7H_8	Toluene	365.35	0.6770	101.33	OX
	C_7H_{16}	Heptane	357.65	0.4830	101.33	OX
	C_8H_8	Styrene	369.08	0.9884	98.13	OX
	C_8H_{10}	*o*-Xylene	369.85	0.9886	98.66	OX
	C_8H_{10}	*m*-Xylene	369.90	0.9531	99.06	OX
	C_8H_{10}	*p*-Xylene	369.60	0.9531	99.99	OX
	C_8H_{14}	1-Octyne	369.00	0.8600	101.33	OX
	C_8H_{18}	Octane	366.85	0.7483	101.33	OX
	C_8H_{18}	2,2,4-Trimethylpentane	357.89	0.4580	101.30	OX
	C_9H_{20}	Nonane	369.95	0.9225	101.33	OX
C_3H_8O		**2-Propanol**				
	$C_4H_4F_6O$	Bis(2,2,2-trifluoroethyl) ether	334.16	0.2230	101.30	OX
	$C_4H_6O_2$	2,3-Butanedione	350.85	0.6454	100.95	OX
	C_4H_8O	2-Butanone	350.55	0.3830	101.33	OX
	$C_4H_{10}O$	2-Methyl-2-propanol	343.05	0.5551	60.27	ON
	$C_5H_3F_9O$	1,1,1,2,3,3-Hexafluoro-3-(2,2,2-trifluoroethoxy)propane	341.23	0.3420	101.30	OX
	C_5H_8	2-Methyl-1,3-butadiene	307.05	0.0150	101.33	OX

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
	C_5H_{10}	2-Methyl-2-butene	310.95	0.0460	101.33	OX
	$C_5H_{10}O$	2,3-Epoxy-2-methylbutane	346.10	0.1400	101.33	OX
	$C_5H_{10}O$	3-Methyl-2-butanone	354.75	0.8500	101.33	OX
	C_5H_{12}	Isopentane	298.15	0.1370	101.33	OX
	$C_5H_{12}O_2$	Diethoxymethane	351.45	0.6107	98.61	OX
	C_6H_5F	Fluorobenzene	347.75	0.4666	101.25	OX
	C_6H_6	Benzene	345.03	0.3960	101.33	OX
	C_6H_{10}	Cyclohexene	344.65	0.4271	101.40	OX
	C_6H_{12}	Cyclohexane	342.75	0.4050	101.33	OX
	C_6H_{12}	Methylcyclopentane	336.45	0.2900	98.14	OX
	C_6H_{14}	Hexane	338.15	0.2900	112.66	OX
	$C_6H_{14}O$	Diisopropyl ether	340.00	0.2050	103.36	OX
	$C_6H_{15}N$	Diisopropylamine	352.94	0.4890	101.33	OX
	C_7H_8	Toluene	354.65	0.8370	101.33	OX
	C_7H_{14}	Methylcyclohexane	350.85	0.6530	101.33	OX
	C_7H_{16}	Heptane	349.55	0.6023	101.33	OX
	$C_7H_{16}O$	*tert*-Butyl isopropyl ether	349.95	0.5306	102.70	OX
	C_8H_{18}	Octane	354.63	0.8990	101.33	OX
	C_8H_{18}	2,2,4-Trimethylpentane	349.58	0.6350	101.30	OX
$C_3H_8O_2$		**2-Methoxyethanol**				
	C_8H_8	Styrene	393.95	0.7787	98.93	OX
	C_8H_{10}	*o*-Xylene	392.65	0.7127	98.79	OX
	C_8H_{10}	*m*-Xylene	392.15	0.6397	99.73	OX
	C_8H_{10}	*p*-Xylene	392.65	0.6303	99.99	OX
	C_8H_{16}	1-Octene	380.75	0.4700	101.33	OX
	C_8H_{16}	*cis*-4-Octene	381.25	0.4900	101.33	OX
	C_8H_{16}	*trans*-4-Octene	381.05	0.4900	101.33	OX
$C_3H_8O_2$		**Dimethoxymethane**				
	C_5H_6	1,3-Cyclopentadiene	313.65	0.3350	101.33	OX
	C_5H_8	2-Methyl-1,3-butadiene	306.80	0.0160	101.33	OX
	C_5H_8	Methylenecyclobutane	310.35	0.4630	101.33	OX
	C_5H_8	1-Methylcyclobutene	309.05	0.2900	101.33	OX
$C_3H_8O_2$		**1,2-Propanediol**				
	$C_7H_{16}O_3$	Di(propylene glycol) monomethyl ether (unspecified isomer)	456.85	0.5691	101.33	OX
	$C_8H_{18}O_3$	Di(propylene glycol) monoethyl ether (unspecified isomer)	458.75	0.7778	101.33	OX
	$C_9H_{20}O_3$	Di(propylene glycol) monoisopropyl ether (unspecified isomer)	458.95	0.8130	101.33	OX
	$C_9H_{20}O_3$	Di(propylene glycol) monopropyl ether (unspecified isomer)	458.95	0.9010	101.33	OX
	$C_{10}H_{22}O_3$	Di(propylene glycol) monobutyl ether (unspecified isomer)	459.65	0.9721	101.33	OX
	$C_{10}H_{22}O_3$	Di(propylene glycol) monoisobutyl ether (unspecified isomer)	459.05	0.9255	101.33	OX
$C_3H_8O_2$		**1,3-Propanediol**				
	$C_5H_{12}O_3$	Di(ethylene glycol) monomethyl ether	455.25	0.6300	101.33	OX
	$C_6H_{14}O_3$	Di(ethylene glycol) monoethyl ether	459.25	0.9350	101.33	OX
C_4H_6		**1,3-Butadiene**				
	C_4H_8	2-Butene (unspecified isomer)	267.59	0.7650	101.33	OX
C_4H_6O		**2-Butenal**				
	C_7H_8	Toluene	374.15	0.5950	97.86	OX
	C_8H_{18}	Octane	353.15	0.4950	97.86	OX
$C_4H_6O_2$		**Vinyl acetate**				
	C_6H_{12}	Cyclohexane	340.45	0.6200	101.33	OX
	C_6H_{14}	Hexane	335.25	0.4450	101.33	OX
$C_4H_6O_2$		**2,3-Butanedione**				
	C_7H_8	Toluene	362.70	0.9513	101.34	OX

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
$C_4H_6O_3$		**Acetic anhydride**				
	C_8H_{16}	1-Octene	367.53	0.2840	53.88	OX
	C_8H_{18}	Octane	397.65	0.3500	129.80	OX
C_4H_8O		**Butanal**				
	C_6H_{12}	2-Methyl-1-pentene	334.15	0.2293	101.48	OX
C_4H_8O		**2-Butanone**				
	$C_4H_8O_2$	Ethyl acetate	349.55	0.1700	101.33	OX
	C_6H_6	Benzene	351.53	0.4790	101.33	OX
	C_6H_{10}	Cyclohexene	343.29	0.5110	89.35	OX
	C_6H_{12}	1-Hexene	334.75	0.1760	100.58	OX
	C_6H_{14}	Hexane	337.15	0.3280	101.33	OX
	$C_6H_{14}O$	Diisopropyl ether	340.55	0.1938	101.56	OX
	$C_6H_{14}O$	Dipropyl ether	351.40	0.7785	100.88	OX
	C_7H_{14}	Methylcyclohexane	350.50	0.7984	98.93	OX
	C_7H_{16}	Heptane	350.15	0.7670	101.33	OX
C_4H_8O		**Tetrahydrofuran**				
	C_6H_{12}	2-Methyl-1-pentene	334.65	0.2867	101.29	OX
	C_6H_{14}	Hexane	323.15	0.5900	65.83	OX
$C_4H_8O_2$		**Ethyl acetate**				
	$C_4H_{10}O$	2-Methyl-2-propanol	349.75	0.7778	101.28	OX
	C_6H_6	Benzene	350.55	0.9453	102.45	OX
	C_6H_{10}	Cyclohexene	347.45	0.6183	100.87	OX
	C_6H_{12}	Cyclohexane	345.00	0.5390	102.45	OX
	C_6H_{12}	1-Hexene	333.15	0.1230	91.47	OX
	C_6H_{14}	Hexane	338.00	0.3430	101.32	OX
	C_7H_{14}	Methylcyclohexane	349.90	0.9001	101.83	OX
$C_4H_8O_2$		**Butanoic acid**				
	C_5H_5N	Pyridine	436.35	0.9117	101.33	ON
	$C_8H_{16}O_2$	Butyl butanoate	434.60	0.6532	93.33	OXD
	$C_8H_{16}O_2$	Butyl butanoate	434.78	0.8639	93.33	OND
	$C_{11}H_{24}$	Undecane	435.55	0.9060	101.33	OX
$C_4H_8O_2$		**1,4-Dioxane**				
	$C_4H_{10}O$	2-Butanol	371.75	0.4732	100.77	OX
	$C_5H_{10}O_2$	Propyl acetate	373.35	0.6334	101.13	OX
	$C_5H_{12}O$	2-Methyl-2-butanol	373.75	0.8119	99.62	OX
	C_6H_{10}	Cyclohexene	355.75	0.1065	101.44	OX
	C_6H_{12}	Methylcyclopentane	343.85	0.0538	99.79	OX
	$C_6H_{15}N$	Triethylamine	343.15	0.2500	56.80	OX
	C_7H_{16}	Heptane	364.30	0.4868	101.06	OX
	$C_7H_{16}O$	2-Ethoxy-2-methylbutane	369.15	0.5452	100.27	OX
$C_4H_8O_2$		**Propyl formate**				
	C_6H_6	Benzene	343.15	0.3770	76.08	OX
$C_4H_8O_2$		**Methyl propanoate**				
	C_7H_{14}	Methylcyclohexane	352.45	0.8956	101.33	OX
C_4H_9Cl		**1-Chlorobutane**				
	C_6H_{12}	Cyclohexane	348.31	0.5800	95.85	OX
C_4H_9NO		***N,N*-Dimethylacetamide**				
	C_8H_{10}	*o*-Xylene	416.95	0.0591	103.40	OX
	C_8H_{10}	Ethylbenzene	408.95	0.0037	101.70	OX
$C_4H_{10}O$		**1-Butanol**				
	C_5H_5N	Pyridine	392.00	0.7050	101.33	ON
	$C_5H_{10}O_3$	Diethyl carbonate	370.85	0.6346	53.20	OX
	C_6H_5Cl	Chlorobenzene	388.25	0.6950	101.33	OX
	C_6H_{12}	Cyclohexane	352.68	0.0787	101.33	OX
	$C_6H_{12}O_2$	Butyl acetate	389.97	0.7700	101.33	OX
	$C_6H_{12}O_2$	Isobutyl acetate	387.15	0.5980	101.33	OX
	C_6H_{14}	Hexane	341.35	0.0370	101.33	OX
	C_7H_8	Toluene	378.85	0.3320	101.33	OX

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
	C_7H_{12}	3-Ethylcyclopentene	367.65	0.1900	101.33	OX
	C_7H_{16}	Heptane	366.55	0.2272	101.38	OX
	C_8H_8	Styrene	388.71	0.8923	98.39	OX
	C_8H_{10}	*o*-Xylene	388.05	0.8671	100.13	OX
	C_8H_{10}	*m*-Xylene	387.75	0.7865	101.46	OX
	C_8H_{10}	*p*-Xylene	387.85	0.7823	99.73	OX
	C_8H_{14}	1-Octyne	386.50	0.6200	101.33	OX
	C_8H_{14}	2-Octyne	398.30	0.7910	101.33	OX
	C_8H_{16}	1-Octene	363.45	0.4530	53.33	OX
	C_8H_{16}	*cis*-4-Octene	382.35	0.5300	101.33	OX
	C_8H_{16}	*trans*-4-Octene	382.15	0.5310	101.33	OX
	C_8H_{18}	Octane	383.15	0.5500	102.79	OX
	$C_8H_{18}O$	Dibutyl ether	390.59	0.8754	101.33	OX
	C_9H_{16}	1-Butylcyclopentene	356.70	0.8450	79.99	OX
	C_9H_{16}	1-Nonyne	390.60	0.9400	101.33	OX
	C_9H_{20}	Nonane	389.05	0.8128	101.33	OX
$C_4H_{10}O$		**2-Butanol**				
	$C_5H_{10}O$	3-Pentanone	370.50	0.6075	99.98	OX
	C_6H_{10}	Cyclohexene	352.75	0.2046	101.25	OX
	C_6H_{12}	Cyclohexane	349.90	0.1892	101.02	OX
	C_6H_{14}	Hexane	348.15	0.1010	128.66	OX
	$C_6H_{14}O$	2-Methoxy-2-methylbutane	359.15	0.0991	102.12	OX
	C_7H_8	Toluene	353.44	0.5550	56.67	OX
	C_7H_{16}	Heptane	361.95	0.4116	102.70	OX
	$C_7H_{16}O$	2-Ethoxy-2-methylbutane	367.75	0.4931	102.89	OX
	C_8H_{10}	*m*-Xylene	369.85	0.9717	101.06	OX
	C_8H_{10}	*p*-Xylene	369.55	0.9646	101.46	OX
	C_8H_{18}	Octane	371.05	0.8001	101.30	OX
$C_4H_{10}O$		**Diethyl ether**				
	C_5H_{12}	Pentane	306.85	0.5500	101.33	OX
$C_4H_{10}O$		**2-Methyl-1-propanol**				
	$C_5H_{10}O_2$	Isobutyl formate	370.90	0.1930	101.33	OX
	C_6H_6	Benzene	352.45	0.0780	101.33	OX
	C_6H_{10}	Cyclohexene	353.75	0.1363	100.31	OX
	C_6H_{12}	Cyclohexane	351.35	0.1325	101.45	OX
	C_6H_{12}	Methylcyclopentane	343.15	0.0567	100.35	OX
	C_7H_8	Toluene	374.35	0.4941	101.33	OX
	C_8H_{10}	*m*-Xylene	380.35	0.9300	101.33	OX
	C_8H_{10}	*p*-Xylene	380.30	0.9200	101.33	OX
	C_8H_{18}	Octane	376.58	0.6700	101.30	OX
$C_4H_{10}O$		**2-Methyl-2-propanol**				
	C_5H_8	Methylenecyclobutane	314.65	0.0150	101.33	OX
	C_6H_{10}	Cyclohexene	346.00	0.4172	99.61	OX
	C_6H_{12}	Methylcyclopentane	339.35	0.2559	99.93	OX
	C_6H_{12}	1-Hexene	333.25	0.2650	101.30	OX
	C_6H_{14}	Hexane	337.70	0.2502	101.30	OX
	$C_6H_{14}O$	*tert*-Butyl ethyl ether	342.85	0.2512	101.44	OX
	$C_6H_{14}O$	Diisopropyl ether	340.45	0.1058	101.72	OX
	$C_6H_{14}O$	2-Methoxy-2-methylbutane	353.20	0.5617	101.80	OX
	C_7H_8	Toluene	353.44	0.9200	93.61	OX
	$C_7H_{16}O$	*tert*-Butyl isopropyl ether	350.90	0.5390	102.94	OX
	C_8H_{18}	Octane	343.15	0.9680	61.18	OX
	C_8H_{18}	2,2,4-Trimethylpentane	339.28	0.6040	59.49	OX
$C_4H_{10}O_2$		**1,4-Butanediol**				
	$C_{15}H_{32}O$	1-Pentadecanol	502.75	0.9980	101.33	OX
$C_4H_{10}O_2$		**1,2-Dimethoxyethane**				
	C_7H_{14}	Methylcyclohexane	350.00	0.8190	79.42	OX
$C_4H_{10}O_2$		**2-Ethoxyethanol**				

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
	C_8H_8	Styrene	405.75	0.6438	101.33	OX
	C_8H_{10}	*o*-Xylene	404.95	0.5965	101.36	OX
	C_8H_{10}	*m*-Xylene	401.75	0.5159	101.33	OX
	C_8H_{10}	*p*-Xylene	402.55	0.5042	102.19	OX
	C_8H_{10}	Ethylbenzene	401.05	0.4632	100.94	OX
$C_4H_{10}O_3$		**Di(ethylene glycol)**				
	$C_9H_{20}O$	1-Nonanol	486.65	0.0095	101.33	OX
$C_4H_{11}N$		**Butylamine**				
	C_6H_6	Benzene	343.15	0.7000	80.89	OX
C_5H_5N		**Pyridine**				
	C_7H_8	Toluene	383.19	0.2250	101.33	OX
	C_7H_{16}	Heptane	368.61	0.3002	101.33	OX
	C_9H_{20}	Nonane	388.15	0.9350	101.33	OX
C_5H_6		**2-Methyl-1-buten-3-yne**				
	C_5H_8	2-Methyl-1,3-butadiene	305.88	0.7210	101.33	OX
	C_5H_{10}	2-Methyl-1-butene	303.15	0.3450	101.33	OX
	C_5H_{12}	Isopentane	299.35	0.3620	101.33	OX
C_5H_6		**1,3-Cyclopentadiene**				
	C_5H_{10}	2-Methyl-2-butene	310.85	0.3000	101.33	OX
	C_5H_{12}	Pentane	307.75	0.1959	101.30	OX
C_5H_8		**2-Methyl-1,3-butadiene**				
	C_5H_{12}	Pentane	310.55	0.7421	114.66	OX
	$C_6F_{15}N$	Tris(perfluoroethyl)amine	303.35	0.8200	101.33	EX
C_5H_8		**3-Methyl-1-butyne**				
	C_5H_{12}	Isopentane	297.15	0.5650	101.33	OX
C_5H_8		**1-Pentyne**				
	C_5H_{10}	2-Methyl-2-butene	310.95	0.3300	101.33	OX
	C_5H_{12}	Pentane	307.55	0.3050	101.33	OX
C_5H_8O		**Cyclopentanone**				
	$C_5H_{12}O$	3-Methyl-1-butanol	402.02	0.5944	101.33	OX
	$C_5H_{12}O$	1-Pentanol	403.84	0.9196	101.33	OX
$C_5H_8O_2$		**Methyl methacrylate**				
	C_7H_{16}	Heptane	366.35	0.4597	99.94	OX
	C_8H_{18}	Octane	373.70	0.9651	100.16	OX
C_5H_{10}		**2-Methyl-1-butene**				
	$C_6F_{15}N$	Tris(perfluoroethyl)amine	301.95	0.8450	101.33	OX
C_5H_{10}		**2-Methyl-2-butene**				
	$C_6F_{15}N$	Tris(perfluoroethyl)amine	307.65	0.8170	101.33	OX
$C_5H_{10}O$		**3-Methyl-3-buten-1-ol**				
	C_6H_{12}	Cyclohexane	352.65	0.0215	101.10	OX
	$C_6H_{12}O_2$	4,4-Dimethyl-1,3-dioxane	403.05	0.7590	102.26	OX
	C_7H_8	Toluene	381.55	0.2391	101.60	OX
	C_7H_{16}	Heptane	370.00	0.2100	101.30	OX
$C_5H_{10}O$		**2-Methyl-3-buten-2-ol**				
	C_6H_{12}	Cyclohexane	350.15	0.1904	101.20	OX
	C_6H_{12}	1-Hexene	336.55	0.0479	101.30	OX
	C_7H_8	Toluene	366.55	0.7788	101.20	OX
$C_5H_{10}O$		**3-Pentanone**				
	C_7H_{14}	Methylcyclohexane	366.95	0.4441	99.82	OX
	$C_7H_{16}O$	2-Ethoxy-2-methylbutane	371.15	0.4764	100.21	OX
$C_5H_{10}O_2$		**Propyl acetate**				
	C_6H_{12}	Cyclohexane	353.15	0.0598	100.43	OX
	C_7H_{14}	Methylcyclohexane	368.40	0.4746	100.90	OX
	C_7H_{16}	Heptane	366.75	0.4215	101.38	OX
	$C_7H_{16}O$	2-Ethoxy-2-methylbutane	370.95	0.6529	100.03	OX
C_5H_{12}		**Isopentane**				
	$C_6F_{15}N$	Tris(perfluoroethyl)amine	299.65	0.9020	101.33	OX
$C_5H_{12}O$		**2-Methyl-1-butanol**				

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
	C_8H_{10}	*o*-Xylene	402.05	0.7417	101.87	OX
	C_8H_{10}	*m*-Xylene	400.65	0.6316	101.85	OX
	C_8H_{10}	*p*-Xylene	400.15	0.6273	101.07	OX
	C_8H_{10}	Ethylbenzene	398.75	0.5657	99.46	OX
$C_5H_{12}O$		**3-Methyl-1-butanol**				
	$C_6H_{10}O$	Cyclohexanone	404.87	0.9094	101.33	OX
	C_7H_8	Toluene	383.15	0.1250	101.33	OX
	$C_7H_{14}O_2$	Isopentyl acetate	403.95	0.9900	101.33	OX
	C_7H_{16}	Heptane	368.15	0.1016	95.06	OX
$C_5H_{12}O$		**2-Methyl-2-butanol**				
	C_6H_6	Benzene	352.35	0.1500	101.33	OX
	C_6H_{12}	Cyclohexane	351.95	0.1100	101.33	OX
	C_6H_{12}	Methylcyclopentane	344.75	0.0551	101.80	OX
	C_6H_{14}	Hexane	339.06	0.0436	93.55	OX
	C_7H_{14}	Methylcyclohexane	366.60	0.3965	99.87	OX
	C_7H_{16}	Heptane	348.15	0.3140	56.83	OX
	$C_7H_{16}O$	2-Ethoxy-2-methylbutane	369.85	0.3904	100.52	OX
$C_5H_{12}O$		**1-Pentanol**				
	$C_6H_{10}O$	Cyclohexanone	392.37	0.9748	53.32	OX
	$C_7H_{14}O_2$	Isopentyl acetate	407.45	0.6000	101.33	OX
	C_7H_{16}	Heptane	371.45	0.0576	101.33	OX
	C_8H_{18}	Octane	393.15	0.2847	101.33	OX
	C_9H_{20}	Nonane	404.45	0.6242	101.33	OX
	$C_{10}H_{22}$	Decane	410.65	0.9221	101.33	OX
$C_5H_{12}O$		**3-Pentanol**				
	C_7H_{16}	Heptane	368.15	0.2001	98.62	OX
$C_5H_{12}O_2$		**Diethoxymethane**				
	C_6H_{12}	Cyclohexane	353.21	0.1774	101.39	OX
	C_6H_{14}	Hexane	361.27	0.9101	102.30	OX
C_6F_6		**Hexafluorobenzene**				
	C_6H_6	Benzene	353.60	0.7600	101.33	OND
	C_6H_6	Benzene	352.50	0.1832	101.33	OXD
$C_6F_{15}N$		**Tris(perfluoroethyl)amine**				
	C_6H_6	Benzene	329.95	0.5900	101.33	EX
	C_6H_{12}	Cyclohexane	329.35	0.5690	101.33	EX
	C_6H_{14}	Hexane	327.65	0.4840	101.33	OX
C_6H_5Br		**Bromobenzene**				
	$C_6H_{12}O$	Cyclohexanol	403.15	0.7390	52.45	OX
C_6H_6		**Benzene**				
	C_6H_{12}	Cyclohexane	353.15	0.5460	109.18	OX
	C_6H_{12}	Methylcyclopentane	333.15	0.1390	69.93	OX
	C_6H_{14}	Hexane	341.45	0.0500	101.33	OX
	C_7H_{16}	Heptane	353.25	0.9922	101.32	OX
	C_8H_{18}	2,2,4-Trimethylpentane	353.25	0.9751	101.32	OX
C_6H_6O		**Phenol**				
	C_6H_7N	Aniline	459.09	0.3884	101.33	ON
	C_6H_7N	2-Methylpyridine	458.33	0.7852	101.32	ON
	C_6H_7N	3-Methylpyridine	462.93	0.6918	101.32	ON
	C_7H_5N	Benzonitrile	465.11	0.2345	101.33	ON
	C_7H_6O	Benzaldehyde	447.00	0.6001	73.00	ON
	C_7H_9N	2,6-Dimethylpyridine	459.32	0.7539	101.32	ON
	C_8H_{18}	Octane	398.17	0.0690	101.32	OX
	C_9H_{12}	Propylbenzene	428.15	0.1150	91.85	OX
	C_9H_{12}	1,2,3-Trimethylbenzene	443.45	0.3936	101.33	OX
	C_9H_{12}	1,2,4-Trimethylbenzene	440.65	0.2409	101.33	OX
	C_9H_{12}	1,3,5-Trimethylbenzene	436.95	0.1828	101.33	OX
	C_9H_{18}	1-Nonene	413.15	0.1297	86.57	OX
	C_9H_{20}	Nonane	419.18	0.2180	101.32	OX

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
	$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene	448.15	0.9031	84.25	OX
	$C_{10}H_{14}$	Butylbenzene	447.05	0.5535	101.33	OX
	$C_{10}H_{14}$	*sec*-Butylbenzene	441.15	0.3129	101.33	OX
	$C_{10}H_{14}$	*tert*-Butylbenzene	439.95	0.2773	101.33	OX
	$C_{10}H_{14}$	Diethylbenzene (unspecified isomer)	446.45	0.4705	101.33	OX
	$C_{10}H_{14}$	*o*-Diethylbenzene	447.15	0.5565	101.33	OX
	$C_{10}H_{14}$	*m*-Diethylbenzene	445.95	0.5152	101.33	OX
	$C_{10}H_{14}$	1-Ethyl-3,5-dimethylbenzene	447.95	0.5840	101.33	OX
	$C_{10}H_{14}$	2-Ethyl-1,4-dimethylbenzene	447.95	0.5840	101.33	OX
	$C_{10}H_{14}$	Isobutylbenzene	441.75	0.3522	101.33	OX
	$C_{10}H_{14}$	1-Isopropyl-2-methylbenzene	443.75	0.4643	101.33	OX
	$C_{10}H_{14}$	1-Isopropyl-3-methylbenzene	443.05	0.4027	101.33	OX
	$C_{10}H_{14}$	1-Isopropyl-4-methylbenzene	443.65	0.4430	101.33	OX
	$C_{10}H_{14}$	1-Methyl-2-propylbenzene	447.75	0.5801	101.33	OX
	$C_{10}H_{14}$	1-Methyl-3-propylbenzene	446.35	0.5264	101.33	OX
	$C_{10}H_{14}$	1-Methyl-4-propylbenzene	447.15	0.5575	101.33	OX
	$C_{10}H_{14}$	1,2,3,5-Tetramethylbenzene	454.25	0.7957	101.33	OX
	$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	453.36	0.7857	101.33	OX
	$C_{10}H_{18}$	*trans*-Decahydronaphthalene	443.15	0.5419	99.85	OX
	$C_{10}H_{22}$	Decane	434.15	0.4450	101.32	OX
	$C_{11}H_{16}$	1-Butyl-2-methylbenzene	455.55	0.8504	101.33	OX
	$C_{11}H_{16}$	1-Butyl-3-methylbenzene	454.15	0.8099	101.33	OX
	$C_{11}H_{16}$	1-Butyl-4-methylbenzene	454.55	0.8230	101.33	OX
	$C_{11}H_{22}$	1-Undecene	443.15	0.6426	92.31	OX
	$C_{12}H_{26}$	Dodecane	450.73	0.7900	101.32	OX
	$C_{14}H_{30}$	Tetradecane	452.48	0.9650	101.32	OX
C_6H_7N		**Aniline**				
	C_7H_8O	*o*-Cresol	464.29	0.0953	101.33	ON
	C_9H_{12}	1,2,3-Trimethylbenzene	444.65	0.3331	101.33	OX
	C_9H_{12}	1,2,4-Trimethylbenzene	441.80	0.1850	101.33	OX
	C_9H_{12}	1,3,5-Trimethylbenzene	437.68	0.1071	101.33	OX
	C_9H_{20}	Nonane	422.35	0.1770	101.33	OX
	$C_{10}H_{14}$	Butylbenzene	448.65	0.4993	101.33	OX
	$C_{10}H_{14}$	*sec*-Butylbenzene	443.15	0.3021	101.33	OX
	$C_{10}H_{14}$	*tert*-Butylbenzene	438.25	0.2104	101.33	OX
	$C_{10}H_{14}$	*o*-Diethylbenzene	448.75	0.5024	101.33	OX
	$C_{10}H_{14}$	*m*-Diethylbenzene	447.45	0.4584	101.33	OX
	$C_{10}H_{14}$	*p*-Diethylbenzene	448.85	0.5086	101.33	OX
	$C_{10}H_{14}$	1-Ethyl-3,5-dimethylbenzene	449.65	0.5310	101.33	OX
	$C_{10}H_{14}$	2-Ethyl-1,4-dimethylbenzene	449.65	0.5310	101.33	OX
	$C_{10}H_{14}$	Isobutylbenzene	442.75	0.2890	101.33	OX
	$C_{10}H_{14}$	1-Isopropyl-2-methylbenzene	445.95	0.4052	101.33	OX
	$C_{10}H_{14}$	1-Isopropyl-3-methylbenzene	444.15	0.3419	101.33	OX
	$C_{10}H_{14}$	1-Isopropyl-4-methylbenzene	445.35	0.3829	101.33	OX
	$C_{10}H_{14}$	1-Methyl-2-propylbenzene	449.45	0.5270	101.33	OX
	$C_{10}H_{14}$	1-Methyl-3-propylbenzene	447.85	0.4711	101.33	OX
	$C_{10}H_{14}$	1-Methyl-4-propylbenzene	448.75	0.5035	101.33	OX
	$C_{10}H_{14}$	1,2,3,5-Tetramethylbenzene	456.55	0.7504	101.33	OX
	$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	455.36	0.7349	101.33	OX
	$C_{10}H_{22}$	Decane	440.43	0.4660	101.33	OX
	$C_{11}H_{16}$	1-Butyl-2-methylbenzene	458.15	0.8091	101.33	OX
	$C_{11}H_{16}$	1-Butyl-3-methylbenzene	456.55	0.7661	101.33	OX
	$C_{11}H_{16}$	1-Butyl-4-methylbenzene	457.05	0.7807	101.33	OX
	$C_{11}H_{24}$	Undecane	449.05	0.6970	101.33	OX
	$C_{12}H_{26}$	Dodecane	453.52	0.8220	101.33	OX
	$C_{13}H_{28}$	Tridecane	456.22	0.9300	101.33	OX
	$C_{14}H_{30}$	Tetradecane	457.05	0.9770	101.33	OX
C_6H_7N		**2-Methylpyridine**				

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
	C_8H_{18}	Octane	394.27	0.4610	101.33	OX
	C_9H_{20}	Nonane	402.35	0.8790	101.33	OX
C_6H_7N		**3-Methylpyridine**				
	C_7H_8O	*m*-Cresol	477.01	0.1556	101.32	ON
	C_7H_9N	2,6-Dimethylpyridine	416.64	0.2940	101.33	OX
C_6H_7N		**4-Methylpyridine**				
	C_7H_8O	*m*-Cresol	477.74	0.1822	101.32	ON
	C_7H_9N	2,6-Dimethylpyridine	417.08	0.2000	101.32	OX
$C_6H_{10}O$		**Methyldihydropyran (unspecified isomer)**				
	C_7H_8	Toluene	381.85	0.0207	101.30	OX
$C_6H_{10}O$		**4-Methylenetetrahydropyran**				
	C_7H_8	Toluene	381.15	0.5253	101.20	OX
$C_6H_{12}O$		**Cyclohexanol**				
	C_8H_{10}	*o*-Xylene	415.95	0.1426	101.33	OX
	C_8H_{10}	*m*-Xylene	411.85	0.0503	101.33	OX
	C_8H_{10}	*p*-Xylene	410.95	0.0505	101.33	OX
	C_9H_{20}	Nonane	410.20	0.3350	79.99	OX
$C_6H_{12}O_2$		**Butyl acetate**				
	C_8H_{16}	1-Octene	393.00	0.3030	101.33	OX
$C_6H_{12}O_2$		**4,4-Dimethyl-1,3-dioxane**				
	C_8H_{10}	*o*-Xylene	404.65	0.9662	101.30	OX
	C_8H_{18}	Octane	393.95	0.3343	101.20	OX
	C_9H_{20}	Nonane	402.15	0.8864	101.30	OX
	$C_{10}H_{22}$	Decane	405.35	0.9999	100.60	OX
$C_6H_{14}O$		**1-Hexanol**				
	C_8H_{18}	Octane	398.55	0.0886	101.33	OX
	C_9H_{20}	Nonane	416.95	0.3649	101.33	OX
	$C_{10}H_{22}$	Decane	427.05	0.7123	101.33	OX
$C_6H_{14}O_2$		**2,2-Dimethoxybutane**				
	C_7H_8	Toluene	380.15	0.9180	101.44	OX
C_7F_{16}		**Perfluoroheptane**				
	C_7H_{16}	Heptane	328.16	0.6100	53.60	OX
C_7H_5N		**Benzonitrile**				
	C_7H_8O	*o*-Cresol	468.91	0.5100	101.33	ON
	C_7H_8O	*m*-Cresol	476.10	0.1441	101.33	ON
	C_7H_8O	*p*-Cresol	476.95	0.0898	101.33	ON
	$C_8H_{10}O$	2,6-Xylenol	477.15	0.0807	101.33	ON
C_7H_8O		***o*-Cresol**				
	$C_8H_{11}N$	2,4,6-Trimethylpyridine	470.35	0.6561	101.33	ON
	$C_{10}H_{14}$	*sec*-Butylbenzene	444.65	0.0938	101.33	OX
	$C_{10}H_{14}$	Diethylbenzene (unspecified isomer)	453.10	0.2694	101.33	OX
	$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	462.37	0.6273	101.33	OX
	$C_{10}H_{22}$	Decane	433.15	0.3100	78.71	OX
	$C_{11}H_{22}$	1-Undecene	448.15	0.5516	83.07	OX
	$C_{11}H_{24}$	Undecane	433.15	0.5800	56.40	OX
	$C_{12}H_{26}$	Dodecane	458.15	0.8466	93.55	OX
C_7H_8O		***m*-Cresol**				
	C_7H_9N	2,6-Dimethylpyridine	475.66	0.9869	101.32	ON
	C_9H_7N	Quinoline	511.20	0.0356	101.33	ON
	C_9H_{20}	Nonane	413.15	0.0400	76.54	OX
	$C_{10}H_8$	Naphthalene	474.65	0.9680	101.33	OX
	$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene	468.45	0.5900	93.10	OX
	$C_{10}H_{14}$	*sec*-Butylbenzene	445.85	0.0136	101.33	OX
	$C_{10}H_{14}$	Diethylbenzene (unspecified isomer)	454.10	0.1010	101.33	OX
	$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	466.87	0.3591	101.33	OX
	$C_{10}H_{22}$	Decane	433.15	0.2170	75.85	OX
C_7H_8O		***p*-Cresol**				
	$C_{10}H_8$	Naphthalene	474.55	0.9414	101.33	OX

Molecular formula

Comp. 1	Comp. 2	Name	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	Type
	$C_{10}H_{14}$	*sec*-Butylbenzene	446.05	0.0186	101.33	OX
	$C_{10}H_{14}$	Diethylbenzene (unspecified isomer)	454.50	0.1105	101.33	OX
C_7H_8O		**Benzyl alcohol**				
	$C_{10}H_{22}$	Decane	445.75	0.2490	101.33	OX
C_7H_9N		**2-Methylaniline**				
	$C_{10}H_{22}$	Decane	446.91	0.1770	101.33	OX
	$C_{11}H_{24}$	Undecane	461.40	0.4930	101.33	OX
	$C_{12}H_{26}$	Dodecane	468.90	0.7650	101.33	OX
	$C_{13}H_{28}$	Tridecane	472.55	0.9070	101.33	OX
$C_7H_{14}O_2$		**Pentyl acetate**				
	C_9H_{20}	Nonane	419.20	0.5380	101.32	OX
$C_7H_{16}O$		**1-Heptanol**				
	C_9H_{20}	Nonane	423.45	0.1071	101.33	OX
	$C_{10}H_{22}$	Decane	438.75	0.4308	101.33	OX
	$C_{11}H_{24}$	Undecane	447.85	0.8014	101.33	OX
C_8H_{10}		***o*-Xylene**				
	C_9H_{20}	Nonane	417.40	0.8498	101.33	OX
$C_8H_{10}O$		**2,6-Xylenol**				
	C_9H_7N	Quinoline	511.00	0.0890	101.33	ON
	$C_{10}H_8$	Naphthalene	475.70	0.9381	101.33	OX
	$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	468.85	0.3480	101.33	OX
$C_8H_{10}O$		**2,3-Xylenol**				
	C_9H_7N	Quinoline	513.30	0.2684	101.33	ON
	$C_{10}H_8$	Naphthalene	485.45	0.4123	101.33	OX
$C_8H_{10}O$		**2,4-Xylenol**				
	C_9H_7N	Quinoline	512.30	0.1717	101.33	ON
	$C_{10}H_8$	Naphthalene	481.25	0.6435	101.33	OX
	$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	474.05	0.1869	101.33	OX
$C_8H_{10}O$		**2,5-Xylenol**				
	C_9H_7N	Quinoline	512.30	0.1717	101.33	ON
	$C_{10}H_8$	Naphthalene	481.25	0.6435	101.33	OX
	$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	474.35	0.1763	101.33	OX
$C_8H_{10}O$		**3,4-Xylenol**				
	C_9H_7N	Isoquinoline	519.75	0.2955	101.33	ON
	C_9H_7N	Quinoline	514.77	0.3907	101.33	ON
	$C_{10}H_8$	Naphthalene	490.95	0.1158	101.33	OX
	$C_{10}H_9N$	3-Methylisoquinoline	524.35	0.0811	101.33	ON
	$C_{10}H_9N$	2-Methylquinoline	521.17	0.1647	101.33	ON
	$C_{10}H_9N$	3-Methylquinoline	523.60	0.1152	101.33	ON
	$C_{10}H_9N$	7-Methylquinoline	525.85	0.0466	101.33	ON
	$C_{11}H_{11}N$	2,3-Dimethylquinoline	521.60	0.2113	101.33	ON
$C_8H_{10}O$		**3,5-Xylenol**				
	C_9H_7N	Isoquinoline	518.05	0.1915	101.33	ON
	C_9H_7N	Quinoline	513.58	0.3287	101.33	ON
	$C_{10}H_8$	Naphthalene	489.33	0.2601	101.33	OX
	$C_{10}H_9N$	2-Methylquinoline	520.65	0.0094	101.33	ON
	$C_{11}H_{11}N$	2,3-Dimethylquinoline	520.70	0.0530	101.33	ON
$C_8H_{10}O$		**2-Ethylphenol**				
	C_9H_7N	Quinoline	511.75	0.1041	101.33	ON
	$C_{10}H_8$	Naphthalene	478.35	0.8005	101.33	OX
	$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	471.45	0.3707	101.33	OX
$C_8H_{10}O$		**3-Ethylphenol**				
	C_9H_7N	Quinoline	512.70	0.2089	101.33	ON
	$C_{10}H_8$	Naphthalene	483.45	0.5551	101.33	OX
	$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	475.95	0.1249	101.33	OX
$C_8H_{10}O$		**4-Ethylphenol**				
	C_9H_7N	Quinoline	513.45	0.2832	101.33	ON
	$C_{10}H_8$	Naphthalene	486.10	0.3762	101.33	OX

Molecular formula						
Comp. 1	**Comp. 2**	**Name**	T_{Az}/K	$y_{1,Az}$	P_{Az}/kPa	**Type**
$C_8H_{11}N$		**2,4-Dimethylaniline**				
	$C_{11}H_{24}$	Undecane	468.13	0.1490	101.33	OX
	$C_{12}H_{26}$	Dodecane	482.95	0.4520	101.33	OX
	$C_{13}H_{28}$	Tridecane	488.43	0.7880	101.33	OX
	$C_{14}H_{30}$	Tetradecane	490.53	0.9840	101.33	OX
$C_8H_{18}O$		**1-Octanol**				
	$C_{10}H_{22}$	Decane	446.45	0.1029	101.33	OX
	$C_{11}H_{24}$	Undecane	460.05	0.4772	101.33	OX
	$C_{12}H_{26}$	Dodecane	466.95	0.8836	101.33	OX
C_9H_7N		**Isoquinoline**				
	$C_{11}H_{10}$	2-Methylnaphthalene	513.90	0.2074	101.33	OX
C_9H_7N		**Quinoline**				
	$C_9H_{12}O$	3-Isopropylphenol	514.70	0.6109	101.33	ON
	$C_9H_{12}O$	2-Isopropylphenol	512.75	0.8015	101.33	ON
	$C_9H_{12}O$	2-Propylphenol	513.60	0.7243	101.33	ON
	$C_9H_{12}O$	3-Propylphenol	514.70	0.6109	101.33	ON
	$C_9H_{12}O$	4-Propylphenol	515.35	0.5451	101.33	ON
	$C_{10}H_{14}O$	2-Butylphenol	515.70	0.5350	101.33	ON
	$C_{10}H_{14}O$	2-*tert*-Butylphenol	513.70	0.7299	101.33	ON
	$C_{10}H_{14}O$	3-*tert*-Butylphenol	517.05	0.4315	101.33	ON
	$C_{10}H_{14}O$	4-Isobutylphenol	515.95	0.5061	101.33	ON
	$C_{10}H_{14}O$	2-*sec*-Butylphenol	514.70	0.6339	101.33	ON
	$C_{10}H_{14}O$	4-*sec*-Butylphenol	516.45	0.4551	101.33	ON
	$C_{11}H_{10}$	2-Methylnaphthalene	511.05	0.9213	101.33	OX
	$C_{11}H_{16}O$	2-*tert*-Butyl-5-methylphenol	515.45	0.5854	101.33	ON
	$C_{11}H_{16}O$	2-*sec*-Butyl-4-methylphenol	516.10	0.5139	101.33	ON
C_9H_{12}		**1,2,3-Trimethylbenzene**				
	$C_{10}H_{22}$	Decane	433.35	0.4010	72.54	OX
C_9H_{12}		**1,2,4-Trimethylbenzene**				
	$C_{10}H_{22}$	Decane	433.35	0.8600	80.25	OX
$C_9H_{12}O$		**2-Ethyl-4-methylphenol**				
	$C_{10}H_8$	Naphthalene	488.20	0.2218	101.33	OX
$C_9H_{12}O$		**2-Ethyl-5-methylphenol**				
	$C_{10}H_8$	Naphthalene	489.45	0.1710	101.33	OX
$C_9H_{12}O$		**2-Isopropylphenol**				
	$C_{10}H_8$	Naphthalene	483.15	0.5102	101.33	OX
	$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	476.25	0.1036	101.33	OX
$C_9H_{12}O$		**2,4,6-Trimethylphenol**				
	$C_{10}H_8$	Naphthalene	486.70	0.3161	101.33	OX
$C_9H_{20}O$		**1-Nonanol**				
	$C_{11}H_{24}$	Undecane	468.45	0.0925	101.33	OX
	$C_{12}H_{26}$	Dodecane	480.65	0.5235	101.33	OX
$C_{10}H_{22}O$		**1-Decanol**				
	$C_{12}H_{26}$	Dodecane	489.25	0.1068	101.33	OX

VISCOSITY OF GASES

The following table gives the viscosity of some common gases as a function of temperature. Unless otherwise noted, the viscosity values refer to a pressure of 100 kPa (1 bar). The notation P=0 indicates the low pressure limiting value is given. The difference between the viscosity at 100 kPa and the limiting value is generally less than 1%. Viscosity is given in units of μPa s; note that 1 μPa s = 10^{-5} poise. Substances are listed in the modified Hill order (see Introduction).

		Viscosity in micropascal seconds (μPa s)						
		100 K	**200 K**	**300 K**	**400 K**	**500 K**	**600 K**	**Ref.**
	Air	7.1	13.3	18.6	23.1	27.1	30.8	1
Ar	Argon	8.0	15.9	22.9	28.8	34.2	39.0	2,8
BF_3	Boron trifluoride		12.3	17.1	21.7	26.1	30.2	13
ClH	Hydrogen chloride			14.6	19.7	24.3		13
F_6S	Sulfur hexafluoride (P=0)			15.3	19.8	23.9	27.7	10
H_2	Hydrogen (P=0)	4.2	6.8	9.0	10.9	12.7	14.4	4
D_2	Deuterium (P=0)	5.9	9.6	12.6	15.4	17.9	20.3	11
H_2O	Water			10.0	13.3	17.3	21.4	6
D_2O	Deuterium oxide			11.1	13.7	17.7	22.0	7
He	Helium (P=0)	9.7	15.3	20.0	24.4	28.4	32.3	8
Kr	Krypton (P=0)	8.8	17.1	25.6	33.1	39.8	45.9	8
NO	Nitric oxide		13.8	19.2	23.8	28.0	31.9	13
N_2	Nitrogen (P=0)		12.9	17.9	22.2	26.1	29.6	12
N_2O	Nitrous oxide		10.0	15.0	19.4	23.6	27.4	13
Ne	Neon (P=0)	14.4	24.3	32.1	38.9	45.0	50.8	8
O_2	Oxygen (P=0)	7.5	14.6	20.8	26.1	30.8	35.1	12
O_2S	Sulfur dioxide		8.6	12.9	17.5	21.7		13
Xe	Xenon (P=0)	8.3	15.4	23.2	30.7	37.6	44.0	8
CO	Carbon monoxide	6.7	12.9	17.8	22.1	25.8	29.1	13
CO_2	Carbon dioxide		10.0	15.0	19.7	24.0	28.0	9,10
$CHCl_3$	Chloroform			10.2	13.7	16.9	20.1	13
CH_4	Methane		7.7	11.2	14.3	17.0	19.4	10
CH_4O	Methanol				13.2	16.5	19.6	13
C_2H_2	Acetylene			10.4	13.5	16.5		13
C_2H_4	Ethylene		7.0	10.4	13.6	16.5	19.1	3
C_2H_6	Ethane		6.4	9.5	12.3	14.9	17.3	5
C_2H_6O	Ethanol				11.6	14.5	17.0	13
C_3H_8	Propane			8.3	10.9	13.4	15.8	5
C_4H_{10}	Butane			7.5	10.0	12.3	14.6	5
C_4H_{10}	Isobutane			7.6	10.0	12.3	14.6	5
$C_4H_{10}O$	Diethyl ether			7.6	10.1	12.4		13
C_5H_{12}	Pentane			6.7	9.2	11.4	13.4	13
C_6H_{14}	Hexane				8.6	10.8	12.8	13

References

1. K. Kadoya, N. Matsunaga, and A. Nagashima, Viscosity and thermal conductivity of dry air in the gaseous phase, *J. Phys. Chem. Ref. Data*, 14, 947, 1985.
2. B. A. Younglove and H. J. M. Hanley, The viscosity and thermal conductivity coefficients of gaseous and liquid argon, *J. Phys. Chem. Ref. Data*, 15, 1323, 1986.
3. P. M. Holland, B. E. Eaton, and H. J. M. Hanley, A correlation of the viscosity and thermal conductivity data of gaseous and liquid ethylene, *J. Phys. Chem. Ref. Data*, 12, 917, 1983.
4. M. J. Assael, S. Mixafendi, and W. A. Wakeham, The viscosity and thermal conductivity of normal hydrogen in the limit zero density, *J. Phys. Chem. Ref. Data*, 15, 1315, 1986.
5. B. A. Younglove and J. F. Ely, Thermophysical properties of fluids. II. Methane, ethane, propane, isobutane, and normal butane, *J. Phys. Chem. Ref. Data*, 16, 577, 1987.
6. J. V. Sengers and J. T. R. Watson, Improved international formulations for the viscosity and thermal conductivity of water substance, *J. Phys. Chem. Ref. Data*, 15, 1291, 1986.
7. N. Matsunaga and A. Nagashima, Transport properties of liquid and gaseous D_2O over a wide range of temperature and pressure, *J. Phys. Chem. Ref. Data*, 12, 933, 1983.
8. J. Kestin, et al., Equilibrium and transport properties of the noble gases and their mixtures at low density, *J. Phys. Chem. Ref. Data*, 13, 299, 1984.
9. V. Vescovic, et al., The transport properties of carbon dioxide, *J. Phys. Chem. Ref. Data*, 19, 1990.
10. R. D. Trengove and W. A. Wakeham, The viscosity of carbon dioxide, methane, and sulfur hexafluoride in the limit of zero density, *J. Phys. Chem. Ref. Data*, 16, 175, 1987.
11. M. J. Assael, S. Mixafendi, and W. A. Wakeham, The viscosity of normal deuterium in the limit of zero density, *J. Phys. Chem. Ref. Data*, 16, 189, 1987.
12. W. A. Cole and W. A. Wakeham, The viscosity of nitrogen, oxygen, and their binary mixtures in the limit of zero density, *J. Phys. Chem. Ref. Data*, 14, 209, 1985.
13. C. Y. Ho, Ed., *Properties of Inorganic and Organic Fluids*, *CINDAS Data Series on Materials Properties*, Vol. V-1, Hemisphere Publishing Corp., New York, 1988.

VISCOSITY OF LIQUIDS

The absolute viscosity of some common liquids at temperatures between −25 and 100°C is given in this table. Values were derived by fitting experimental data to suitable expressions for the temperature dependence. The substances are arranged by molecular formula in the modified Hill order (see Preface). All values are given in units of millipascal seconds (mPa s); this unit is identical to centipoise (cp).

Viscosity values correspond to a nominal pressure of 1 atmosphere. If a value is given at a temperature above the normal boiling point, the applicable pressure is understood to be the vapor pressure of the liquid at that temperature. A few values are given at a temperature slightly below the normal freezing point; these refer to the supercooled liquid.

The accuracy ranges from 1% in the best cases to 5 to 10% in the worst cases. Additional significant figures are included in the table to facilitate interpolation.

References

1. Viswanath, D. S. and Natarajan, G., *Data Book on the Viscosity of Liquids*, Hemisphere Publishing Corp., New York, 1989.
2. Daubert, T. E., Danner, R. P., Sibul, H. M., and Stebbins, C. C., *Physical and Thermodynamic Properties of Pure Compounds: Data Compilation*, extant 1994 (core with 4 supplements), Taylor & Francis, Bristol, PA (also available as database).
3. Ho, C. Y., Ed., *CINDAS Data Series on Material Properties*, Vol. V-1, *Properties of Inorganic and Organic Fluids*, Hemisphere Publishing Corp., New York, 1988.
4. Stephan, K. and Lucas, K., *Viscosity of Dense Fluids*, Plenum Press, New York, 1979.
5. Vargaftik, N. B., *Tables of Thermophysical Properties of Liquids and Gases*, 2nd ed., John Wiley, New York, 1975.

Molecular formula	Name	Viscosity in mPa s					
		−25°C	0°C	25°C	50°C	75°C	100°C
Compounds not containing carbon							
Br_2	Bromine		1.252	0.944	0.746		
Cl_3HSi	Trichlorosilane		0.415	0.326			
Cl_3P	Phosphorous trichloride	0.870	0.662	0.529	0.439		
Cl_4Si	Tetrachlorosilane			99.4	96.2		
H_2O	Water		1.793	0.890	0.547	0.378	0.282
H_4N_2	Hydrazine			0.876	0.628	0.480	0.384
Hg	Mercury			1.526	1.402	1.312	1.245
NO_2	Nitrogen dioxide		0.532	0.402			
Compounds containing carbon							
CCl_3F	Trichlorofluoromethane	0.740	0.539	0.421			
CCl_4	Tetrachloromethane		1.321	0.908	0.656	0.494	
CS_2	Carbon disulfide		0.429	0.352			
$CHBr_3$	Tribromomethane			1.857	1.367	1.029	
$CHCl_3$	Trichloromethane	0.988	0.706	0.537	0.427		
CHN	Hydrogen cyanide		0.235	0.183			
CH_2Br_2	Dibromomethane	1.948	1.320	0.980	0.779	0.652	
CH_2Cl_2	Dichloromethane	0.727	0.533	0.413			
CH_2O_2	Formic acid			1.607	1.030	0.724	0.545
CH_3I	Iodomethane		0.594	0.469			
CH_3NO	Formamide		7.114	3.343	1.833		
CH_3NO_2	Nitromethane	1.311	0.875	0.630	0.481	0.383	0.317
CH_4O	Methanol	1.258	0.793	0.544			
CH_5N	Methylamine	0.319	0.231				
$C_2Cl_3F_3$	1,1,2-Trichlorotrifluoro-ethane	1.465	0.945	0.656	0.481		
C_2Cl_4	Tetrachloroethylene		1.114	0.844	0.663	0.535	0.442
C_2HCl_3	Trichloroethylene		0.703	0.545	0.444	0.376	
C_2HCl_5	Pentachloroethane		3.761	2.254	1.491	1.061	
$C_2HF_3O_2$	Trifluoroacetic acid			0.808	0.571		
$C_2H_2Cl_2$	*cis*-1,2-Dichloroethylene	0.786	0.575	0.445			
$C_2H_2Cl_2$	*trans*-1,2-Dichloroethylene	0.522	0.398	0.317	0.261		
$C_2H_2Cl_4$	1,1,1,2-Tetrachloroethane	3.660	2.200	1.437	1.006	0.741	0.570
$C_2H_3ClF_2$	1-Chloro-1,1-difluoro-ethane	0.477	0.376				
C_2H_3ClO	Acetyl chloride			0.368	0.294		
$C_2H_3Cl_3$	1,1,1-Trichloroethane	1.847	1.161	0.793	0.578	0.428	
C_2H_3N	Acetonitrile		0.400	0.369	0.284	0.234	
$C_2H_4Br_2$	1,2-Dibromoethane			1.595	1.116	0.837	0.661

Molecular formula	Name	Viscosity in mPa s					
		−25°C	0°C	25°C	50°C	75°C	100°C
$C_2H_4Cl_2$	1,1-Dichloroethane			0.464	0.362		
$C_2H_4Cl_2$	1,2-Dichloroethane		1.125	0.779	0.576	0.447	
$C_2H_4O_2$	Acetic acid			1.056	0.786	0.599	0.464
$C_2H_4O_2$	Methyl formate		0.424	0.325			
C_2H_5Br	Bromoethane	0.635	0.477	0.374			
C_2H_5Cl	Chloroethane	0.416	0.319				
C_2H_5I	Iodoethane		0.723	0.556	0.444	0.365	
C_2H_5NO	*N*-Methylformamide		2.549	1.678	1.155	0.824	0.606
$C_2H_5NO_2$	Nitroethane	1.354	0.940	0.688	0.526	0.415	0.337
C_2H_6O	Ethanol	3.262	1.786	1.074	0.694	0.476	
C_2H_6OS	Dimethyl sulfoxide			1.987	1.290		
$C_2H_6O_2$	Ethylene glycol			16.1	6.554	3.340	1.975
C_2H_6S	Dimethyl sulfide		0.356	0.284			
C_2H_6S	Ethanethiol		0.364	0.287			
C_2H_7N	Dimethylamine	0.300	0.232				
C_2H_7NO	Ethanolamine			21.1	8.560	3.935	1.998
C_3H_5Br	3-Bromopropene		0.620	0.471	0.373		
C_3H_5Cl	3-Chloropropene		0.408	0.314			
C_3H_5ClO	Epichlorohydrin	2.492	1.570	1.073	0.781	0.597	0.474
C_3H_5N	Propanenitrile			0.294	0.240	0.202	
C_3H_6O	Acetone	0.540	0.395	0.306	0.247		
C_3H_6O	Allyl alcohol			1.218	0.759	0.505	
C_3H_6O	Propanal			0.321	0.249		
$C_3H_6O_2$	Ethyl formate		0.506	0.380	0.300		
$C_3H_6O_2$	Methyl acetate		0.477	0.364	0.284		
$C_3H_6O_2$	Propanoic acid		1.499	1.030	0.749	0.569	0.449
C_3H_7Br	1-Bromopropane		0.645	0.489	0.387		
C_3H_7Br	2-Bromopropane		0.612	0.458	0.359		
C_3H_7Cl	1-Chloropropane		0.436	0.334			
C_3H_7Cl	2-Chloropropane		0.401	0.303			
C_3H_7I	1-Iodopropane		0.970	0.703	0.541	0.436	0.363
C_3H_7I	2-Iodopropane		0.883	0.653	0.506	0.407	
C_3H_7NO	*N,N*-Dimethylformamide		1.176	0.794	0.624		
$C_3H_7NO_2$	1-Nitropropane	1.851	1.160	0.798	0.589	0.460	0.374
C_3H_8O	1-Propanol	8.645	3.815	1.945	1.107	0.685	
C_3H_8O	2-Propanol		4.619	2.038	1.028	0.576	
$C_3H_8O_2$	1,2-Propylene glycol		248	40.4	11.3	4.770	2.750
$C_3H_8O_3$	Glycerol			934	152	39.8	14.8
C_3H_8S	1-Propanethiol		0.503	0.385			
C_3H_8S	2-Propanethiol		0.477	0.357	0.280		
C_3H_9N	Propylamine			0.376			
C_3H_9N	Isopropylamine		0.454	0.325			
C_4H_4O	Furan	0.661	0.475	0.361			
C_4H_5N	Pyrrole		2.085	1.225	0.828	0.612	
$C_4H_6O_3$	Acetic anhydride		1.241	0.843	0.614	0.472	0.377
C_4H_7N	Butanenitrile			0.553	0.418	0.330	0.268
C_4H_8O	2-Butanone	0.720	0.533	0.405	0.315	0.249	
C_4H_8O	Tetrahydrofuran	0.849	0.605	0.456	0.359		
$C_4H_8O_2$	1,4-Dioxane			1.177	0.787	0.569	
$C_4H_8O_2$	Ethyl acetate		0.578	0.423	0.325	0.259	
$C_4H_8O_2$	Methyl propionate		0.581	0.431	0.333	0.266	
$C_4H_8O_2$	Propyl formate		0.669	0.485	0.370	0.293	
$C_4H_8O_2$	Butanoic acid		2.215	1.426	0.982	0.714	0.542
$C_4H_8O_2$	2-Methylpropanoic acid		1.857	1.226	0.863	0.639	0.492
$C_4H_8O_2S$	Sulfolane				6.280	3.818	2.559
C_4H_8S	Tetrahydrothiophene			0.973	0.912		
C_4H_9Br	1-Bromobutane		0.815	0.606	0.471	0.379	
C_4H_9Cl	1-Chlorobutane		0.556	0.422	0.329	0.261	
C_4H_9N	Pyrrolidine	1.914	1.071	0.704	0.512		
C_4H_9NO	*N,N*-Dimethylacetamide			1.927			

Molecular formula	Name	Viscosity in mPa s					
		−25°C	0°C	25°C	50°C	75°C	100°C
C_4H_9NO	Morpholine			2.021	1.247	0.850	0.627
$C_4H_{10}O$	1-Butanol	12.19	5.185	2.544	1.394	0.833	0.533
$C_4H_{10}O$	2-Butanol			3.096	1.332	0.698	0.419
$C_4H_{10}O$	2-Methyl-2-propanol			4.312	1.421	0.678	
$C_4H_{10}O$	Diethyl ether		0.283	0.224			
$C_4H_{10}O_3$	Diethylene glycol			30.200	11.130	4.917	2.505
$C_4H_{10}S$	Diethyl sulfide		0.558	0.422	0.331	0.267	
$C_4H_{11}N$	Butylamine		0.830	0.574	0.409	0.298	
$C_4H_{11}N$	Isobutylamine		0.770	0.571	0.367		
$C_4H_{11}N$	Diethylamine			0.319	0.239		
$C_4H_{11}NO_2$	Diethanolamine				109.5	28.7	9.100
$C_5H_4O_2$	Furfural		2.501	1.587	1.143	0.906	0.772
C_5H_5N	Pyridine		1.361	0.879	0.637	0.497	0.409
C_5H_{10}	1-Pentene	0.313	0.241	0.195			
C_5H_{10}	2-Methyl-2-butene		0.255	0.203			
C_5H_{10}	Cyclopentane		0.555	0.413	0.321		
$C_5H_{10}O$	Mesityl oxide	1.291	0.838	0.602	0.465	0.381	0.326
$C_5H_{10}O$	2-Pentanone		0.641	0.470	0.362	0.289	0.238
$C_5H_{10}O$	3-Pentanone		0.592	0.444	0.345	0.276	0.227
$C_5H_{10}O_2$	Butyl formate		0.937	0.644	0.472	0.362	0.289
$C_5H_{10}O_2$	Propyl acetate		0.768	0.544	0.406	0.316	0.255
$C_5H_{10}O_2$	Ethyl propanoate		0.691	0.501	0.380	0.299	0.242
$C_5H_{10}O_2$	Methyl butanoate		0.759	0.541	0.406	0.318	0.257
$C_5H_{10}O_2$	Methyl isobutanoate		0.672	0.488	0.373	0.296	
$C_5H_{11}N$	Piperidine			1.573	0.958	0.649	0.474
C_5H_{12}	Pentane	0.351	0.274	0.224			
C_5H_{12}	Isopentane	0.376	0.277	0.214			
$C_5H_{12}O$	1-Pentanol	25.4	8.512	3.619	1.820	1.035	0.646
$C_5H_{12}O$	2-Pentanol			3.470	1.447	0.761	0.465
$C_5H_{12}O$	3-Pentanol			4.149	1.473	0.727	0.436
$C_5H_{12}O$	2-Methyl-1-butanol			4.453	1.963	1.031	0.612
$C_5H_{12}O$	3-Methyl-1-butanol		8.627	3.692	1.842	1.031	0.631
$C_5H_{13}N$	Pentylamine		1.030	0.702	0.493	0.356	
C_6F_6	Hexafluorobenzene			2.789	1.730	1.151	
$C_6H_4Cl_2$	*o*-Dichlorobenzene		1.958	1.324	0.962	0.739	0.593
$C_6H_4Cl_2$	*m*-Dichlorobenzene		1.492	1.044	0.787	0.628	0.525
C_6H_5Br	Bromobenzene		1.560	1.074	0.798	0.627	0.512
C_6H_5Cl	Chlorobenzene	1.703	1.058	0.753	0.575	0.456	0.369
C_6H_5ClO	*o*-Chlorophenol			3.589	1.835	1.131	0.786
C_6H_5ClO	*m*-Chlorophenol				4.041		
C_6H_5F	Fluorobenzene		0.749	0.550	0.423	0.338	
C_6H_5I	Iodobenzene		2.354	1.554	1.117	0.854	0.683
$C_6H_5NO_2$	Nitrobenzene		3.036	1.863	1.262	0.918	0.704
C_6H_6	Benzene			0.604	0.436	0.335	
C_6H_6ClN	*o*-Chloroaniline			3.316	1.913	1.248	0.887
C_6H_6O	Phenol				3.437	1.784	1.099
C_6H_7N	Aniline			3.847	2.029	1.247	0.850
$C_6H_8N_2$	Phenylhydrazine			13.0	4.553	1.850	0.848
C_6H_{10}	Cyclohexene		0.882	0.625	0.467	0.364	
$C_6H_{10}O$	Cyclohexanone			2.017	1.321	0.919	0.671
$C_6H_{11}N$	Hexanenitrile			0.912	0.650	0.488	0.382
C_6H_{12}	Cyclohexane			0.894	0.615	0.447	
C_6H_{12}	Methylcyclopentane	0.927	0.653	0.479	0.364		
C_6H_{12}	1-Hexene	0.441	0.326	0.252	0.202		
$C_6H_{12}O$	Cyclohexanol			57.5	12.3	4.274	1.982
$C_6H_{12}O$	2-Hexanone	1.300	0.840	0.583	0.429	0.329	0.262
$C_6H_{12}O$	4-Methyl-2-pentanone			0.545	0.406		
$C_6H_{12}O_2$	Butyl acetate		1.002	0.685	0.500	0.383	0.305
$C_6H_{12}O_2$	Isobutyl acetate			0.676	0.493	0.370	0.286
$C_6H_{12}O_2$	Ethyl butanoate			0.639	0.453		

Molecular formula	Name	Viscosity in mPa s					
		−25°C	0°C	25°C	50°C	75°C	100°C
$C_6H_{12}O_2$	Diacetone alcohol	28.7	6.621	2.798	1.829	1.648	
$C_6H_{12}O_3$	Paraldehyde			1.079	0.692	0.485	0.362
$C_6H_{13}N$	Cyclohexylamine			1.944	1.169	0.782	0.565
C_6H_{14}	Hexane		0.405	0.300	0.240		
C_6H_{14}	2-Methylpentane		0.372	0.286	0.226		
C_6H_{14}	3-Methylpentane		0.395	0.306			
$C_6H_{14}O$	Dipropyl ether		0.542	0.396	0.304	0.242	
$C_6H_{14}O$	1-Hexanol			4.578	2.271	1.270	0.781
$C_6H_{15}N$	Triethylamine		0.455	0.347	0.273	0.221	
$C_6H_{15}N$	Dipropylamine		0.751	0.517	0.377	0.288	0.228
$C_6H_{15}N$	Diisopropylamine			0.393	0.300	0.237	
$C_6H_{15}NO_3$	Triethanolamine			609	114	31.5	11.7
C_7H_5N	Benzonitrile			1.267	0.883	0.662	0.524
C_7H_7Cl	*o*-Chlorotoluene		1.390	0.964	0.710	0.547	0.437
C_7H_7Cl	*m*-Chlorotoluene		1.165	0.823	0.616	0.482	0.391
C_7H_7Cl	*p*-Chlorotoluene			0.837	0.621	0.483	0.390
C_7H_8	Toluene	1.165	0.778	0.560	0.424	0.333	0.270
C_7H_8O	*o*-Cresol				3.035	1.562	0.961
C_7H_8O	*m*-Cresol			12.9	4.417	2.093	1.207
C_7H_8O	Benzyl alcohol			5.474	2.760	1.618	1.055
C_7H_8O	Anisole			1.056	0.747	0.554	0.427
C_7H_9N	*N*-Methylaniline		4.120	2.042	1.222	0.825	0.606
C_7H_9N	*o*-Methyl aniline		10.3	3.823	1.936	1.198	0.839
C_7H_9N	*m*-Methyl aniline		8.180	3.306	1.679	1.014	0.699
C_7H_9N	Benzylamine			1.624	1.080	0.769	0.577
C_7H_{14}	Methylcyclohexane		0.991	0.679	0.501	0.390	0.316
C_7H_{14}	1-Heptene		0.441	0.340	0.273	0.226	
$C_7H_{14}O$	2-Heptanone			0.714	0.407	0.297	
$C_7H_{14}O_2$	Heptanoic acid			3.840	2.282	1.488	1.041
C_7H_{16}	Heptane	0.757	0.523	0.387	0.301	0.243	
C_7H_{16}	3-Methylhexane			0.350			
$C_7H_{16}O$	1-Heptanol			5.810	2.603	1.389	0.849
$C_7H_{16}O$	2-Heptanol			3.955	1.799	0.987	0.615
$C_7H_{16}O$	3-Heptanol				1.957	0.976	0.584
$C_7H_{16}O$	4-Heptanol			4.207	1.695	0.882	0.539
$C_7H_{17}N$	Heptylamine			1.314	0.865	0.600	0.434
C_8H_8	Styrene		1.050	0.695	0.507	0.390	0.310
C_8H_8O	Acetophenone			1.681			0.634
$C_8H_8O_2$	Methyl benzoate			1.857			
$C_8H_8O_3$	Methyl salicylate					1.102	0.815
C_8H_{10}	Ethylbenzene		0.872	0.631	0.482	0.380	0.304
C_8H_{10}	*o*-Xylene		1.084	0.760	0.561	0.432	0.345
C_8H_{10}	*m*-Xylene		0.795	0.581	0.445	0.353	0.289
C_8H_{10}	*p*-Xylene			0.603	0.457	0.359	0.290
$C_8H_{10}O$	Phenetole			1.197	0.817	0.594	0.453
$C_8H_{11}N$	*N,N*-Dimethylaniline		1.996	1.300	0.911	0.675	0.523
$C_8H_{11}N$	*N*-Ethylaniline		3.981	2.047	1.231	0.825	0.596
C_8H_{16}	Ethylcyclohexane		1.139	0.784	0.579		
$C_8H_{16}O_2$	Octanoic acid			5.020	2.656	1.654	1.147
C_8H_{18}	Octane		0.700	0.508	0.385	0.302	0.243
$C_8H_{18}O$	1-Octanol			7.288	3.232	1.681	0.991
$C_8H_{18}O$	4-Methyl-3-heptanol		1.904	1.085	0.702	0.497	0.375
$C_8H_{18}O$	5-Methyl-3-heptanol		2.052	1.178	0.762	0.536	0.401
$C_8H_{18}O$	2-Ethyl-1-hexanol		20.7	6.271	2.631	1.360	0.810
$C_8H_{18}O$	Dibutyl ether	1.417	0.918	0.637	0.466	0.356	0.281
$C_8H_{19}N$	Dibutylamine		1.509	0.918	0.619	0.449	0.345
$C_8H_{19}N$	Diisobutylamine		1.115	0.723	0.511	0.384	0.303
C_9H_7N	Quinoline			3.337	1.892	1.201	0.833
C_9H_{10}	Indane		2.230	1.357	0.931	0.692	0.545
C_9H_{12}	Cumene		1.075	0.737	0.547		

Molecular formula	Name	Viscosity in mPa s					
		−25°C	0°C	25°C	50°C	75°C	100°C
$C_9H_{14}O$	Isophorone		4.201	2.329	1.415	0.923	0.638
$C_9H_{18}O$	5-Nonanone			1.199	0.834	0.619	0.484
$C_9H_{18}O_2$	Nonanoic acid			7.011	3.712	2.234	1.475
C_9H_{20}	Nonane		0.964	0.665	0.488	0.375	0.300
$C_9H_{20}O$	1-Nonanol			9.123	4.032		
$C_{10}H_{10}O_4$	Dimethyl phthalate		63.2	14.4	5.309	2.824	1.980
$C_{10}H_{14}$	Butylbenzene			0.950	0.683	0.515	
$C_{10}H_{18}$	*cis*-Decahydronaphthalene	12.8	5.645	3.042	1.875	1.271	0.924
$C_{10}H_{18}$	*trans*-Decahydronaphthalene	6.192	3.243	1.948	1.289	0.917	0.689
$C_{10}H_{20}O_2$	Decanoic acid				4.327	2.651	
$C_{10}H_{22}$	Decane	2.188	1.277	0.838	0.598	0.453	0.359
$C_{10}H_{22}O$	1-Decanol			10.9	4.590		
$C_{11}H_{24}$	Undecane		1.707	1.098	0.763	0.562	0.433
$C_{12}H_{10}O$	Diphenyl ether				2.130	1.407	1.023
$C_{12}H_{26}$	Dodecane		2.277	1.383	0.930	0.673	0.514
$C_{13}H_{12}$	Diphenylmethane					1.265	0.929
$C_{13}H_{28}$	Tridecane		2.909	1.724	1.129	0.796	0.594
$C_{14}H_{30}$	Tetradecane			2.128	1.376	0.953	0.697
$C_{16}H_{22}O_4$	Dibutyl phthalate	483	66.4	16.6	6.470	3.495	2.425
$C_{16}H_{34}$	Hexadecane			3.032	1.879	1.260	0.899
$C_{18}H_{38}$	Octadecane				2.487	1.609	1.132

THERMAL CONDUCTIVITY OF GASES

This table gives the thermal conductivity of several gases as a function of temperature. Unless otherwise noted, the values refer to a pressure of 100 kPa (1 bar) or to the saturation vapor pressure if that is less than 100 kPa. The notation $P = 0$ indicates the low pressure limiting value is given. In general, the $P = 0$ and $P = 100$ kPa values differ by less than 1%. Units are milliwatts per meter kelvin. Substances are listed in the modified Hill order.

		Thermal conductivity in mW/m K						
MF	**Name**	**100 K**	**200 K**	**300 K**	**400 K**	**500 K**	**600 K**	**Ref.**
	Air	9.4	18.4	26.2	33.3	39.7	45.7	1
Ar	Argon	6.2	12.4	17.9	22.6	26.8	30.6	2,8
BF_3	Boron trifluoride			19.0	24.6			11
ClH	Hydrogen chloride		9.2	14.5	19.5	24.0	28.1	11
F_6S	Sulfur hexafluoride ($P = 0$)			13.0	20.6	27.5	33.8	16
H_2	Hydrogen ($P = 0$)	68.6	131.7	186.9	230.4			4
H_2O	Water			18.7	27.1	35.7	47.1	6
	Deuterium oxide				27.0	36.5	47.6	7
H_2S	Hydrogen sulfide			14.6	20.5	26.4	32.4	11
H_3N	Ammonia			24.4	37.4	51.6	66.8	11
He	Helium ($P = 0$)	75.5	119.3	156.7	190.6	222.3	252.4	8
Kr	Krypton ($P = 0$)	3.3	6.4	9.5	12.3	14.8	17.1	8
NO	Nitric oxide		17.8	25.9	33.1	39.6	46.2	11
N_2	Nitrogen	9.8	18.7	26.0	32.3	38.3	44.0	12
N_2O	Nitrous oxide		9.8	17.4	26.0	34.1	41.8	11
Ne	Neon ($P = 0$)	22.3	37.6	49.8	60.3	69.9	78.7	8
O_2	Oxygen	9.3	18.4	26.3	33.7	41.0	48.1	10
O_2S	Sulfur dioxide			9.6	14.3	20.0	25.6	11
Xe	Xenon ($P = 0$)	2.0	3.6	5.5	7.3	8.9	10.4	8
CCl_2F_2	Dichlorodifluoromethane			9.9	15.0	20.1	25.2	13
CF_4	Tetrafluoromethane ($P = 0$)			16.0	24.1	32.2	39.9	16
CO	Carbon monoxide ($P = 0$)			25.0	32.3	39.2	45.7	14
CO_2	Carbon dioxide		9.6	16.8	25.1	33.5	41.6	9
$CHCl_3$	Trichloromethane			7.5	11.1	15.1		11
CH_4	Methane		22.5	34.1	49.1	66.5	84.1	5,15
CH_4O	Methanol				26.2	38.6	53.0	11
$C_2Cl_2F_4$	1,2-Dichlorotetrafluoroethane			10.25	15.7	21.1		13
$C_2Cl_3F_3$	1,1,2-Trichlorotrifluoroethane			9.0	13.6	18.3		13
C_2H_2	Acetylene			21.4	33.3	45.4	56.8	11
C_2H_4	Ethylene		11.1	20.5	34.6	49.9	68.6	3
C_2H_6	Ethane		11.0	21.3	35.4	52.2	70.5	5
C_2H_6O	Ethanol			14.4	25.8	38.4	53.2	11
C_3H_6O	Acetone			11.5	20.2	30.6	42.7	11
C_3H_8	Propane			18.0	30.6	45.5	61.9	5
C_4F_8	Perfluorocyclobutane			12.5	19.5			13
C_4H_{10}	Butane			16.4	28.4	43.0	59.1	5
C_4H_{10}	Isobutane			16.1	27.9	42.1	57.6	5
$C_4H_{10}O$	Diethyl ether			15.1	25.0	37.1		11
C_5H_{12}	Pentane			14.4	24.9	37.8	52.7	11
C_6H_{14}	Hexane				23.4	35.4	48.7	11

References

1. Kadoya, K. Matsunaga, N., and Nagashima, A., Viscosity and thermal conductivity of dry air in the gaseous phase, *J. Phys. Chem. Ref. Data*, 14, 947, 1985.
2. Younglove, B. A. and Hanley, H. J. M., The viscosity and thermal conductivity coefficients of gaseous and liquid argon, *J. Phys. Chem. Ref. Data*, 15, 1323, 1986.
3. Holland, P. M., Eaton, B. E., and Hanley, H. J. M., A correlation of the viscosity and thermal conductivity data of gaseous and liquid ethylene, *J. Phys. Chem. Ref. Data*, 12, 917, 1983.
4. Assael, M. J., Mixafendi, S., and Wakeham, W. A., The viscosity and thermal conductivity of normal hydrogen in the limit of zero density, *J. Phys. Chem. Ref. Data*, 15, 1315, 1986.
5. Younglove, B. A. and Ely, J. F., Thermophysical properties of fluids. II. Methane, ethane, propane, isobutane, and normal butane, *J. Phys. Chem. Ref. Data*, 16, 577, 1987.

6. Sengers, J. V. and Watson, J. T. R., Improved international formulations for the viscosity and thermal conductivity of water substance, *J. Phys. Chem. Ref. Data*, 15, 1291, 1986.
7. Matsunaga, N. and Nagashima, A., Transport properties of liquid and gaseous D_2O over a wide range of temperature and pressure, *J. Phys. Chem. Ref. Data*, 12, 933, 1983.
8. Kestin, J. et al., Equilibrium and transport properties of the noble gases and their mixtures at low density, *J. Phys. Chem. Ref. Data*, 13, 229, 1984.
9. Vescovic, V. et al., The transport properties of carbon dioxide, *J. Phys. Chem. Ref. Data*, 19, 1990.
10. Younglove, B. A., Thermophysical properties of fluids. I. Argon, ethylene, parahydrogen, nitrogen, nitrogen trifluoride, and oxygen, *J. Phys. Chem. Ref. Data*, 11, Suppl. 1, 1982.
11. Ho, C. Y., Ed., *Properties of Inorganic and Organic Fluids, CINDAS Data Series on Materials Properties*, Volume V-1, Hemisphere Publishing Corp., New York, 1988.
12. Stephen, K., Krauss, R., and Laesecke, A., Viscosity and thermal conductivity of nitrogen for a wide range of fluid states, *J. Phys. Chem. Ref. Data*, 16, 993, 1987.
13. Krauss, R. and Stephan, K., Thermal conductivity of refrigerants in a wide range of temperature and pressure, *J. Phys. Chem. Ref. Data*, 18, 43, 1989.
14. Millat, J. and Wakeham, W. A., The thermal conductivity of nitrogen and carbon monoxide in the limit of zero density, *J. Phys. Chem. Ref. Data*, 18, 565, 1989.
15. Friend, D. G., Ely, J. F., and Ingham, H., Thermophysical properties of methane, *J. Phys. Chem. Ref. Data*, 18, 583, 1989.
16. Uribe, F. J., Mason, E. A., and Kestin, J., Thermal conductivity of nine polyatomic gases at low density, *J. Phys. Chem. Ref. Data*, 19, 1123, 1990.

THERMAL CONDUCTIVITY OF LIQUIDS

This table gives the thermal conductivity of about 275 liquids at temperatures between –25 and 100°C. Values refer to nominal atmospheric pressure; when an entry is given for a temperature above the normal boiling point of the liquid, the pressure is understood to be the saturation vapor pressure at that temperature. Reference 1 contains data on many of these liquids at high pressures. Data on halocarbon refrigerants over a wide range of temperature and pressure may be found in Reference 6.

Values given to three decimal places (i.e., to 0.001 W/m K) have an uncertainty of 2% to 5%. Values given to 0.0001 W/m K should be accurate to 1% or better.

Substances are arranged by molecular formula in Hill order, except that compounds not containing carbon precede those that do contain carbon.

References

1. Vargaftik, N. B., Filippov, L. P., Tarzimanov, A. A., and Totskii, E. E., *Handbook of Thermal Conductivity of Liquids and Gases*, CRC Press, Boca Raton FL, 1994.
2. Daubert, T. E., Danner, R. P., Sibul, H. M., and Stebbins, C. C., *Physical and Thermodynamic Properties of Pure Compounds: Data Compilation*, extant 1994 (core with four supplements), Taylor and Francis, Bristol, PA (also available as a database).
3. Watanabe, H., *J. Chem. Eng. Data* 48, 124, 2003.
4. Watanabe, H., and Seong, D. J., *Int. J. Thermophys*. 23, 337, 2002.
5. Nieto de Castro, C. A., Li, S. F. Y., Nagashima, A., Trengove, R. D., and Wakeham, W. A., *J. Phys. Chem. Ref. Data* 15, 1073, 1986.
6. Krauss, R., and Stephan, K., *J. Phys. Chem. Ref. Data* 18, 43, 1989.
7. Assael, M. J., Ramires, M. L. V., Nieto de Castro, C. A., and Wakeham, W. A., *J. Phys. Chem. Ref. Data* 19, 113, 1990.
8. Ramires, M. L. V., Nieto de Castro, C. A., Nagasaka, Y., Nagashima, A., Assael, M. J., and Wakeham, W. A., *J. Phys. Chem. Ref. Data* 24, 1377, 1995.
9. Ramires, M. L. V., Nieto de Castro, C. A., Perkins, R. A., Nagasaka, Y., Nagashima, A., Assael, M. J., and Wakeham, W. A., *J. Phys. Chem. Ref. Data* 29, 133, 2000.
10. Marsh, K. N., Ed., *Recommended Reference Materials for the Realization of Physicochemical Properties*, Blackwell Scientific Publications, Oxford, 1987.
11. Beaton, C. F., and Hewitt, G. F., *Physical Property Data for the Design Engineer*, Hemisphere Publishing Corp., New York, 1989.

Molecular formula	Name	Thermal conductivity in W/m K						
		–25°C	0°C	25°C	50°C	75°C	100°C	Ref.
Cl_4Ge	Germanium(IV) chloride	0.111	0.105	0.100	0.095	0.090	0.084	1
Cl_4Si	Tetrachlorosilane			0.099	0.096			2
Cl_4Sn	Tin(IV) chloride	0.123	0.117	0.112	0.106	0.101	0.095	1
Cl_4Ti	Titanium(IV) chloride		0.143	0.138	0.134	0.129	0.124	1
H_2O	Water		0.5562	0.6062	0.6423	0.6643	0.6729	8
Hg	Mercury	7.85	8.175	8.514	8.842	9.161	9.475	11
CCl_3F	Trichlorofluoromethane	0.102	0.096	0.089	0.083	0.076	0.070	1
CCl_4	Tetrachloromethane		0.109	0.103	0.098	0.092	0.087	1
$CHCl_3$	Trichloromethane	0.127	0.122	0.117	0.112	0.107	0.102	2
CH_2Br_2	Dibromomethane	0.120	0.114	0.108	0.103	0.097		2
CH_2Cl_2	Dichloromethane	0.158	0.149	0.140	0.133	0.128	0.127	1
CH_2I_2	Diiodomethane			0.098	0.093	0.088	0.083	1
CH_2O_2	Formic acid			0.267	0.265	0.263	0.261	1
CH_3NO_2	Nitromethane	0.226	0.215	0.204	0.193	0.182	0.171	1
CH_4O	Methanol	0.218	0.210	0.202	0.195	0.189	0.182	1
CS_2	Carbon disulfide		0.154	0.149				2
$C_2Br_2F_4$	1,2-Dibromotetrafluoroethane	0.071	0.066	0.061	0.057	0.053	0.049	1
$C_2Cl_3F_3$	1,1,2-Trichloro-1,2,2-trifluoroethane	0.0847	0.0790	0.0736	0.0683			6
C_2Cl_4	Tetrachloroethene		0.117	0.110	0.104	0.098	0.093	1
$C_2Cl_4F_2$	1,1,2,2-Tetrachloro-1,2-difluoroethane			0.082	0.078	0.074	0.069	1
C_2HCl_3	Trichloroethene	0.128	0.121	0.114	0.106	0.098	0.090	1
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane	0.124	0.118	0.111	0.104	0.098	0.091	1
$C_2H_3Cl_3$	1,1,1-Trichloroethane		0.106	0.101	0.096			2
C_2H_3N	Acetonitrile	0.208	0.198	0.188	0.178	0.168		2
$C_2H_4Br_2$	1,2-Dibromoethane			0.100	0.096	0.092	0.088	1
$C_2H_4Cl_2$	1,2-Dichloroethane	0.144	0.139	0.133	0.128	0.122	0.117	1
$C_2H_4O_2$	Acetic acid			0.158	0.153	0.149	0.144	2
$C_2H_4O_2$	Methyl formate		0.194	0.187				1
C_2H_5Br	Bromoethane	0.107	0.104	0.101				1
C_2H_5Cl	Chloroethane	0.145	0.132	0.119	0.106	0.093		2
C_2H_5I	Iodoethane		0.091	0.087	0.083	0.079		1
C_2H_5NO	*N*-Methylformamide			0.203	0.201	0.199	0.196	2
$C_2H_5NO_2$	Nitroethane			0.173	0.161	0.149		1
C_2H_6O	Ethanol	0.181	0.174	0.167	0.160	0.153	0.148	1
$C_2H_6O_2$	1,2-Ethanediol		0.248	0.254	0.258	0.261	0.261	1
C_2H_7NO	Ethanolamine			0.240	0.238	0.236		1

Molecular formula	Name	Thermal conductivity in W/m K						
		–25°C	0°C	25°C	50°C	75°C	100°C	Ref.
C_3F_8	Perfluoropropane	0.062	0.056	0.051	0.046	0.041	0.035	1
C_3H_3N	Acrylonitrile	0.186	0.176	0.166	0.156	0.146	0.136	1
C_3H_5ClO	Epichlorohydrin	0.142	0.137	0.131	0.125	0.119	0.114	2
C_3H_6O	Allyl alcohol			0.162				1
C_3H_6O	Acetone		0.169	0.161				2
C_3H_6O	Methyloxirane		0.181	0.171				1
$C_3H_6O_2$	Propanoic acid		0.147	0.144	0.141	0.139	0.136	1
$C_3H_6O_2$	Ethyl formate	0.181	0.171	0.160	0.149	0.138		1
$C_3H_6O_2$	Methyl acetate	0.174	0.164	0.153	0.143	0.133	0.122	2
C_3H_7Br	1-Bromopropane	0.108	0.104	0.099	0.094			1
C_3H_7Cl	1-Chloropropane	0.129	0.123	0.116	0.110	0.104	0.098	1
C_3H_7I	1-Iodopropane	0.096	0.092	0.087	0.083	0.078	0.074	1
C_3H_7I	2-Iodopropane	0.089	0.085	0.082	0.078	0.074	0.071	1
C_3H_7NO	*N,N*-Dimethylformamide			0.183	0.175	0.167	0.159	1
$C_3H_7NO_2$	1-Nitropropane			0.152	0.144	0.137		1
C_3H_8O	1-Propanol	0.162	0.158	0.154	0.149	0.145	0.141	2
C_3H_8O	2-Propanol	0.146	0.141	0.135	0.129	0.124	0.118	2
$C_3H_8O_2$	1,2-Propanediol	0.199	0.200	0.200	0.200	0.199	0.197	1
$C_3H_8O_2$	2-Methoxyethanol			0.190	0.180	0.170		1
$C_3H_8O_3$	Glycerol			0.285	0.288	0.292	0.296	1
C_3H_9N	Trimethylamine	0.143	0.133					2
C_4F_8	Perfluorocyclobutane	0.082	0.072	0.063	0.053	0.044	0.034	1
C_4H_4O	Furan	0.142	0.134	0.126				2
C_4H_4S	Thiophene			0.199	0.195	0.191	0.186	2
C_4H_6	1,2-Butadiene	0.147	0.134					1
C_4H_6	2-Butyne	0.137	0.129	0.121				2
$C_4H_6O_2$	Vinyl acetate			0.151	0.141	0.131	0.120	1
$C_4H_6O_3$	Acetic anhydride		0.170	0.164	0.158	0.152	0.146	1
C_4H_8O	Butanal		0.155	0.147	0.140	0.132		1
C_4H_8O	2-Butanone	0.158	0.151	0.145	0.139	0.133		2
C_4H_8O	Tetrahydrofuran	0.132	0.126	0.120	0.114			2
$C_4H_8O_2$	Propyl formate		0.151	0.144	0.137	0.130		1
$C_4H_8O_2$	Ethyl acetate		0.151	0.144	0.136			1
$C_4H_8O_2$	Methyl propanoate			0.141	0.137			1
$C_4H_8O_2$	1,4-Dioxane			0.159	0.147	0.135	0.123	2
C_4H_9Br	1-Bromobutane	0.112	0.107	0.103	0.098	0.093	0.088	1
C_4H_9I	1-Iodobutane		0.094	0.090	0.085	0.081	0.077	1
C_4H_9NO	*N,N*-Dimethylacetamide			0.175	0.172	0.168		1
$C_4H_{10}O$	1-Butanol		0.158	0.153	0.147	0.142	0.137	1
$C_4H_{10}O$	2-Methyl-2-propanol			0.112	0.110	0.109	0.108	1
$C_4H_{10}O$	Diethyl ether	0.150	0.140	0.130	0.120	0.110	0.100	2
$C_4H_{10}O_2$	2-Ethoxyethanol			0.190	0.182	0.174	0.165	1
C_5H_5N	Pyridine		0.171	0.166	0.162	0.157	0.153	1
$C_5H_6O_2$	Furfuryl alcohol			0.179				1
C_5H_8	2-Methyl-1,3-butadiene	0.141	0.130	0.119				1
C_5H_8	1-Pentyne	0.144	0.136	0.127	0.119			1
C_5H_8	Cyclopentene	0.143	0.136	0.129				2
$C_5H_8O_2$	Methyl methacrylate		0.156	0.147	0.137	0.127	0.117	1
$C_5H_8O_2$	2,4-Pentanedione			0.154	0.150	0.146	0.143	1
C_5H_9NO	*N*-Methyl-2-pyrrolidone			0.167	0.162	0.157		1
C_5H_{10}	1-Pentene	0.131	0.124	0.116				2
C_5H_{10}	Cyclopentane	0.140	0.133	0.126				2
$C_5H_{10}O$	Pentanal		0.146	0.139	0.133	0.127	0.121	1
$C_5H_{10}O$	2-Pentanone		0.149	0.142	0.135	0.128	0.121	1
$C_5H_{10}O$	3-Pentanone		0.151	0.144	0.137	0.129	0.122	1
$C_5H_{10}O_2$	Pentanoic acid			0.140	0.137	0.133	0.130	1
$C_5H_{10}O_2$	Butyl formate			0.136	0.130	0.123	0.117	1
$C_5H_{10}O_2$	Propyl acetate		0.146	0.140	0.135	0.130	0.124	1
$C_5H_{10}O_2$	Ethyl propanoate				0.133	0.121		1
$C_5H_{10}O_2$	Methyl butanoate			0.140				1
$C_5H_{11}Br$	1-Bromopentane	0.113	0.109	0.105	0.101	0.097	0.093	1
$C_5H_{11}Cl$	1-Chloropentane		0.125	0.120	0.115	0.109		1

Molecular formula	Name	Thermal conductivity in W/m K						
		–25°C	0°C	25°C	50°C	75°C	100°C	Ref.
$C_5H_{11}I$	1-Iodopentane		0.096	0.092	0.088	0.084	0.081	1
C_5H_{12}	Pentane	0.130	0.1207	0.1113	0.1018	0.0923	0.083	4
C_5H_{12}	Isopentane			0.111				1
$C_5H_{12}O$	1-Pentanol	0.159	0.155	0.150	0.145	0.141	0.136	1
$C_5H_{12}O$	2-Methyl-2-butanol		0.119	0.116	0.113	0.109	0.106	1
$C_5H_{12}O_2$	1,5-Pentanediol		0.221	0.222				1
$C_5H_{12}O_3$	Diethylene glycol monomethyl ether			0.190	0.185	0.180	0.175	1
C_6F_6	Hexafluorobenzene				0.083			1
C_6F_{14}	Perfluorohexane		0.067	0.065	0.064			1
$C_6H_3Cl_3$	1,2,3-Trichlorobenzene				0.110	0.108	0.106	1
$C_6H_3Cl_3$	1,2,4-Trichlorobenzene			0.112	0.109	0.106		1
$C_6H_4Cl_2$	*o*-Dichlorobenzene		0.125	0.121	0.117	0.113	0.109	1
$C_6H_4Cl_2$	*m*-Dichlorobenzene		0.120	0.116	0.113	0.109		1
$C_6H_4Cl_2$	*p*-Dichlorobenzene				0.112	0.108	0.105	1
C_6H_5Br	Bromobenzene	0.119	0.115	0.111	0.107	0.103	0.099	1
C_6H_5Cl	Chlorobenzene	0.137	0.132	0.127	0.123	0.118	0.113	1
C_6H_5F	Fluorobenzene			0.136	0.131	0.126		1
C_6H_5I	Iodobenzene	0.106	0.103	0.101	0.098	0.095	0.092	1
$C_6H_5NO_2$	Nitrobenzene			0.149	0.145	0.142	0.139	1
C_6H_6	Benzene			0.1411	0.1329	0.1247		7
C_6H_6ClN	2-Chloroaniline			0.148				1
C_6H_6O	Phenol				0.153	0.149	0.147	1
C_6H_7N	Aniline		0.175					1
$C_6H_8N_2$	Hexanedinitrile			0.174	0.168			1
C_6H_{10}	Cyclohexene	0.142	0.136	0.130	0.124	0.118		2
$C_6H_{10}O$	Cyclohexanone			0.138	0.134	0.130	0.126	1
$C_6H_{10}O$	Mesityl oxide	0.170	0.163	0.156	0.149	0.142	0.134	2
$C_6H_{10}O_3$	Ethyl acetoacetate			0.155	0.152	0.148	0.144	1
$C_6H_{10}O_4$	Diethyl oxalate			0.157				1
C_6H_{12}	1-Hexene	0.138	0.129	0.121	0.113			1
C_6H_{12}	Cyclohexane			0.123	0.117	0.111		2
$C_6H_{12}O$	2-Hexanone		0.156	0.145	0.134	0.124	0.115	1
$C_6H_{12}O$	Cyclohexanol			0.138	0.134	0.130	0.126	1
$C_6H_{12}O_2$	Hexanoic acid		0.148	0.142	0.137	0.131		1
$C_6H_{12}O_2$	Butyl acetate		0.143	0.136	0.130	0.123	0.116	1
$C_6H_{12}O_2$	Propyl propanoate				0.133			1
$C_6H_{12}O_2$	Ethyl butanoate		0.143	0.137	0.131	0.126		1
$C_6H_{12}O_2$	Methyl pentanoate		0.143	0.138	0.132	0.127		1
$C_6H_{12}O_3$	Paraldehyde			0.130				1
$C_6H_{13}Br$	1-Bromohexane	0.115	0.111	0.108	0.104	0.101	0.097	1
$C_6H_{13}I$	1-Iodohexane		0.098	0.095	0.091	0.088	0.084	1
C_6H_{14}	Hexane	0.133	0.1250	0.1167	0.1083	0.0999	0.092	4
C_6H_{14}	2-Methylpentane	0.120	0.1127	0.1050	0.0972	0.0894	0.082	3
C_6H_{14}	3-Methylpentane	0.122	0.1142	0.1064	0.0986	0.0909	0.083	3
C_6H_{14}	2,2-Dimethylbutane	0.108	0.1006	0.0934	0.0861	0.0788	0.072	3
C_6H_{14}	2,3-Dimethylbutane	0.115	0.1076	0.1003	0.0930	0.0857	0.078	3
$C_6H_{14}O$	1-Hexanol	0.161	0.157	0.152	0.147	0.142	0.137	1
$C_6H_{14}O$	Dipropyl ether		0.137	0.130	0.123	0.117		1
$C_6H_{14}O_2$	1,2-Diethoxyethane				0.140	0.133	0.125	1
$C_6H_{14}O_3$	Diethylene glycol monoethyl ether				0.188	0.184	0.180	1
$C_6H_{14}O_4$	Triethylene glycol		0.193	0.195	0.196	0.196	0.196	1
$C_6H_{15}N$	Triethylamine	0.146	0.139	0.132	0.125	0.118	0.111	1
C_7F_{16}	Perfluoroheptane	0.068	0.064	0.060	0.056	0.053		1
C_7H_5N	Benzonitrile			0.148	0.142	0.136	0.130	1
C_7H_6O	Benzaldehyde			0.153	0.148	0.143	0.139	1
C_7H_8	Toluene	0.1455	0.1385	0.1310	0.1235	0.1162	0.1095	9
C_7H_8O	*o*-Cresol							1
C_7H_8O	*m*-Cresol			0.149	0.147	0.145		1
C_7H_8O	Benzyl alcohol			0.159	0.158	0.156	0.154	1
C_7H_8O	Anisole			0.145	0.142	0.139	0.136	1
C_7H_9N	2-Methylaniline			0.162				1
C_7H_9N	3-Methylaniline			0.161				1

Molecular formula	Name	Thermal conductivity in W/m K						
		–25°C	0°C	25°C	50°C	75°C	100°C	Ref.
C_7H_{14}	1-Heptene	0.139	0.132	0.125	0.118	0.111		1
C_7H_{14}	Cycloheptane			0.123	0.118	0.112	0.108	1
$C_7H_{14}O$	Heptanal			0.140				1
$C_7H_{14}O$	3-Heptanone		0.143	0.137	0.131	0.125	0.119	1
$C_7H_{14}O$	4-Heptanone			0.136	0.131	0.125	0.120	1
$C_7H_{14}O_2$	Hexyl formate			0.141	0.133	0.126	0.119	1
$C_7H_{14}O_2$	Heptanoic acid			0.140	0.137	0.133		1
$C_7H_{14}O_2$	Pentyl acetate		0.141	0.134	0.126	0.120	0.113	1
$C_7H_{14}O_2$	Butyl propanoate			0.139	0.133	0.126	0.121	1
$C_7H_{14}O_2$	Ethyl pentanoate			0.132				1
$C_7H_{14}O_2$	Methyl hexanoate			0.136	0.131	0.126	0.121	1
C_7H_{16}	Heptane	0.1378	0.1303	0.1228	0.1152	0.1077		5
C_7H_{16}	2-Methylhexane	0.125	0.1177	0.1105	0.1033	0.0961	0.089	3
C_7H_{16}	3-Methylhexane	0.126	0.1184	0.1112	0.1040	0.0968	0.090	3
C_7H_{16}	3-Ethylpentane	0.128	0.1203	0.1128	0.1053	0.0978	0.090	3
C_7H_{16}	2,2-Dimethylpentane	0.111	0.1046	0.0980	0.0913	0.0847	0.078	3
C_7H_{16}	2,3-Dimethylpentane	0.120	0.1127	0.1059	0.0990	0.0922	0.085	3
C_7H_{16}	2,4-Dimethylpentane	0.116	0.1089	0.1020	0.0951	0.0882	0.081	3
C_7H_{16}	3,3-Dimethylpentane	0.113	0.1068	0.1001	0.0934	0.0867	0.080	3
C_7H_{16}	2,2,3-Trimethylbutane	0.107	0.1011	0.0950	0.0889	0.0828	0.077	3
$C_7H_{16}O$	1-Heptanol	0.160	0.158	0.153	0.149	0.144	0.139	1
C_8F_{18}	Perfluorooctane		0.066	0.062	0.059	0.055	0.052	1
C_8H_8	Styrene	0.148	0.142	0.137	0.131	0.126	0.120	2
C_8H_8O	Acetophenone			0.147	0.146	0.144	0.142	1
$C_8H_8O_2$	Methyl benzoate			0.147				1
C_8H_{10}	Ethylbenzene	0.143	0.137	0.130	0.123	0.116	0.110	1
C_8H_{10}	*o*-Xylene			0.131	0.126	0.120	0.114	2
C_8H_{10}	*m*-Xylene			0.130	0.124	0.118	0.113	2
C_8H_{10}	*p*-Xylene			0.130	0.124	0.118	0.112	2
$C_8H_{10}O$	Ethoxybenzene	0.151	0.145	0.140	0.135	0.130		1
$C_8H_{10}O_2$	2-Phenoxyethanol			0.169	0.168	0.166	0.165	1
$C_8H_{11}N$	*N*-Ethylaniline			0.150				1
$C_8H_{11}N$	*N,N*-Dimethylaniline			0.122	0.119	0.115		1
C_8H_{16}	1-Octene	0.139	0.133	0.126	0.120	0.114	0.107	1
$C_8H_{16}O$	2-Octanone		0.141	0.135	0.129	0.124	0.118	1
$C_8H_{16}O_2$	Heptyl formate		0.141	0.137	0.132	0.128	0.123	1
$C_8H_{16}O_2$	Octanoic acid			0.146	0.143	0.139	0.135	1
$C_8H_{16}O_2$	Hexyl acetate			0.135	0.129	0.123	0.118	1
$C_8H_{16}O_2$	Pentyl propanoate			0.138	0.132			1
$C_8H_{16}O_2$	Ethyl hexanoate		0.142	0.137	0.133	0.128	0.123	1
$C_8H_{17}Cl$	1-Chlorooctane		0.130	0.127	0.124	0.121	0.119	1
C_8H_{18}	Octane	0.139	0.1317	0.1244	0.1171	0.1097	0.102	4
C_8H_{18}	2-Methylheptane	0.127	0.1206	0.1139	0.1072	0.1005	0.094	3
C_8H_{18}	3-Methylheptane	0.128	0.1216	0.1149	0.1081	0.1014	0.095	3
C_8H_{18}	2,2,4-Trimethylpentane	0.107	0.1007	0.0948	0.0888	0.0829	0.077	3
C_8H_{18}	2,3,4-Trimethylpentane	0.115	0.1093	0.1035	0.0976	0.0918	0.086	3
$C_8H_{18}O$	Ethyl hexyl ether		0.131	0.126	0.120	0.114	0.109	1
$C_8H_{18}O$	1-Octanol		0.162	0.158	0.153	0.148	0.143	1
$C_8H_{18}O$	Dibutyl ether		0.139	0.132	0.125	0.118	0.112	1
$C_8H_{18}O_3$	Diethylene glycol monobutyl ether			0.163	0.158	0.153	0.148	1
$C_8H_{18}O_4$	Triethylene glycol dimethyl ether			0.169	0.158	0.147		1
$C_8H_{18}O_5$	Tetraethylene glycol			0.191	0.192			1
C_9H_7N	Quinoline			0.147	0.144	0.141	0.138	1
C_9H_{10}	Indan			0.135				1
$C_9H_{10}O_2$	Ethyl benzoate			0.141				1
C_9H_{12}	Propylbenzene	0.134	0.130	0.125	0.120	0.115	0.109	1
C_9H_{12}	Isopropylbenzene	0.132	0.128	0.123	0.118	0.112	0.107	1
C_9H_{12}	1,2,4-Trimethylbenzene			0.129	0.124	0.118	0.114	1
C_9H_{12}	1,3,5-Trimethylbenzene	0.143	0.139	0.134	0.129	0.123	0.117	1
C_9H_{18}	1-Nonene	0.136	0.130	0.123	0.116	0.110	0.104	1
$C_9H_{18}O_2$	Nonanoic acid			0.150	0.146	0.142	0.138	1
$C_9H_{18}O_2$	Heptyl acetate			0.135	0.128	0.122	0.116	1

Molecular formula	Name	Thermal conductivity in W/m K						
		–25°C	0°C	25°C	50°C	75°C	100°C	Ref.
$C_9H_{19}Br$	1-Bromononane		0.116	0.112	0.109	0.106	0.103	1
$C_9H_{19}Cl$	1-Chlorononane		0.132	0.128	0.124	0.120	0.115	1
$C_9H_{19}I$	1-Iodononane		0.105	0.102	0.099	0.095	0.092	1
C_9H_{20}	Nonane	0.141	0.1337	0.1269	0.1201	0.1133	0.106	4
$C_9H_{20}O$	1-Nonanol		0.164	0.159	0.155	0.150	0.145	1
$C_{10}H_7Br$	1-Bromonaphthalene			0.110	0.109	0.108	0.106	1
$C_{10}H_7Cl$	1-Chloronaphthalene			0.126				1
$C_{10}H_{10}O_4$	Dimethyl phthalate			0.1473	0.1443	0.1409	0.1373	10
$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene			0.131	0.129	0.128	0.126	1
$C_{10}H_{14}$	Butylbenzene			0.126	0.121	0.116	0.111	1
$C_{10}H_{14}$	*sec*-Butylbenzene, (±)-		0.129	0.124	0.119	0.114	0.108	1
$C_{10}H_{14}$	*tert*-Butylbenzene			0.117	0.114	0.110	0.106	1
$C_{10}H_{14}$	1-Isopropyl-4-methylbenzene	0.132	0.127	0.122	0.117	0.112	0.107	2
$C_{10}H_{14}$	*o*-Diethylbenzene		0.133	0.127	0.122	0.116	0.111	1
$C_{10}H_{18}$	*trans*-Decahydronaphthalene			0.113				1
$C_{10}H_{20}$	1-Decene	0.138	0.132	0.126	0.120	0.114	0.109	1
$C_{10}H_{20}O$	Decanal		0.149	0.144	0.139	0.134	0.129	1
$C_{10}H_{20}O_2$	Heptyl propanoate			0.137	0.132	0.127	0.122	1
$C_{10}H_{20}O_2$	Hexyl butanoate			0.137	0.132	0.127	0.121	1
$C_{10}H_{20}O_2$	Decanoic acid				0.148	0.144	0.140	1
$C_{10}H_{22}$	Decane	0.142	0.1360	0.1296	0.1232	0.1167	0.110	4
$C_{10}H_{22}O$	1-Decanol			0.162	0.159	0.155	0.151	1
$C_{10}H_{22}O$	Dipentyl ether			0.131	0.125	0.121	0.116	1
$C_{10}H_{22}O_2$	1,2-Dibutoxyethane			0.140	0.134	0.127	0.120	1
$C_{11}H_{16}$	Pentylbenzene		0.135	0.130	0.125	0.120	0.115	1
$C_{11}H_{22}$	1-Undecene			0.126	0.118	0.114	0.108	1
$C_{11}H_{22}O$	6-Undecanone			0.137	0.132	0.127		1
$C_{11}H_{22}O_2$	Undecanoic acid				0.153	0.149		1
$C_{11}H_{22}O_2$	Octyl propanoate			0.135	0.130	0.125	0.120	1
$C_{11}H_{22}O_2$	Heptyl butanoate			0.139	0.134	0.129	0.123	1
$C_{11}H_{24}$	Undecane			0.136	0.128	0.122	0.116	1
$C_{11}H_{24}O$	1-Undecanol			0.169	0.165	0.161	0.158	1
$C_{12}H_{10}O$	Diphenyl ether				0.139	0.135	0.131	2
$C_{12}H_{14}O_4$	Diethyl phthalate			0.172	0.169	0.166		1
$C_{12}H_{16}$	Cyclohexylbenzene			0.121	0.119	0.117		1
$C_{12}H_{18}$	Hexylbenzene		0.141	0.137	0.132	0.128	0.124	1
$C_{12}H_{24}O_2$	Decyl acetate			0.146	0.136	0.126		1
$C_{12}H_{24}O_2$	Octyl butanoate			0.139	0.134	0.129	0.125	1
$C_{12}H_{26}$	Dodecane			0.135	0.130	0.124	0.119	1
$C_{12}H_{26}O$	1-Dodecanol				0.167	0.163	0.159	1
$C_{12}H_{26}O_3$	Diethylene glycol dibutyl ether		0.150	0.146	0.143	0.139	0.135	1
$C_{12}H_{27}N$	Tributylamine			0.129				1
$C_{13}H_{26}$	1-Tridecene			0.130	0.125	0.120	0.115	1
$C_{13}H_{28}$	Tridecane			0.130	0.125	0.120	0.115	1
$C_{14}H_{28}$	1-Tetradecene			0.136	0.131	0.126	0.121	1
$C_{14}H_{30}$	Tetradecane			0.139	0.134	0.129	0.124	1
$C_{14}H_{30}O$	1-Tetradecanol				0.167	0.162	0.157	2
$C_{16}H_{22}O_4$	Dibutyl phthalate		0.139	0.136	0.134	0.131	0.129	1
$C_{16}H_{34}$	Hexadecane			0.140	0.135	0.130	0.125	2
$C_{18}H_{38}$	Octadecane				0.146	0.142	0.137	2
$C_{20}H_{40}O_2$	Butyl palmitate			0.151	0.148	0.144	0.140	1
$C_{22}H_{42}O_2$	Butyl oleate			0.157	0.153	0.149	0.145	1
$C_{22}H_{42}O_4$	Dioctyl hexanedioate			0.157	0.153	0.149	0.145	1

DIFFUSION IN GASES

This table gives binary diffusion coefficients D_{12} for a number of common gases as a function of temperature. Values refer to atmospheric pressure. The diffusion coefficient is inversely proportional to pressure as long as the gas is in a regime where binary collisions dominate. See Reference 1 for a discussion of the dependence of D_{12} on temperature and composition.

The first part of the table gives data for several gases in the presence of a large excess of air. The remainder applies to equimolar mixtures of gases. Each gas pair is ordered alphabetically according to the most common way of writing the formula. The listing of pairs then follows alphabetical order by the first constituent.

References

1. Marrero, T. R., and Mason, E. A., *J. Phys. Chem. Ref. Data*, 1, 1, 1972.
2. Kestin, J., et al., *J. Phys. Chem. Ref. Data*, 13, 229, 1984.

D_{12}/cm^2 s^{-1} for p = 101.325 kPa and the Specified T/K

System	200	273.15	293.15	373.15	473.15	573.15	673.15
Large Excess of Air							
Ar-air		0.167	0.189	0.289	0.437	0.612	0.810
CH_4-air			0.210	0.321	0.485	0.678	0.899
CO-air			0.208	0.315	0.475	0.662	0.875
CO_2-air			0.160	0.252	0.390	0.549	0.728
H_2-air		0.668	0.756	1.153	1.747	2.444	3.238
H_2O-air			0.242	0.399	0.638	0.873	1.135
He-air		0.617	0.697	1.057	1.594	2.221	2.933
SF_6-air				0.150	0.233	0.329	0.438
Equimolar Mixture							
Ar-CH_4				0.306	0.467	0.657	0.876
Ar-CO		0.168	0.190	0.290	0.439	0.615	0.815
Ar-CO_2		0.129	0.148	0.235	0.365	0.517	0.689
Ar-H_2		0.698	0.794	1.228	1.876	2.634	3.496
Ar-He	0.381	0.645	0.726	1.088	1.617	2.226	2.911
Ar-Kr	0.064	0.117	0.134	0.210	0.323	0.456	0.605
Ar-N_2		0.168	0.190	0.290	0.439	0.615	0.815
Ar-Ne	0.160	0.277	0.313	0.475	0.710	0.979	1.283
Ar-O_2		0.166	0.187	0.285	0.430	0.600	0.793
Ar-SF_6				0.128	0.202	0.290	0.389
Ar-Xe	0.052	0.095	0.108	0.171	0.264	0.374	0.498
CH_4-H_2			0.708	1.084	1.648	2.311	3.070
CH_4-He			0.650	0.992	1.502	2.101	2.784
CH_4-N_2			0.208	0.317	0.480	0.671	0.890
CH_4-O_2			0.220	0.341	0.523	0.736	0.978
CH_4-SF_6				0.167	0.257	0.363	0.482
CO-CO_2			0.162	0.250	0.384		
CO-H_2	0.408	0.686	0.772	1.162	1.743	2.423	3.196
CO-He	0.365	0.619	0.698	1.052	1.577	2.188	2.882
CO-Kr		0.131	0.149	0.227	0.346	0.485	0.645
CO-N_2	0.133	0.208	0.231	0.336	0.491	0.673	0.878
CO-O_2			0.202	0.307	0.462	0.643	0.849
CO-SF_6				0.144	0.226	0.323	0.432
CO_2-C_3H_8			0.084	0.133	0.209		
CO_2-H_2	0.315	0.552	0.627	0.964	1.470	2.066	2.745
CO_2-H_2O			0.162	0.292	0.496	0.741	1.021
CO_2-He	0.300	0.513	0.580	0.878	1.321		
CO_2-N_2			0.160	0.253	0.392	0.553	0.733
CO_2-N_2O	0.055	0.099	0.113	0.177	0.276		
CO_2-Ne	0.131	0.227	0.258	0.395	0.603	0.847	
CO_2-O_2			0.159	0.248	0.380	0.535	0.710
CO_2-SF_6				0.099	0.155		
D_2-H_2	0.631	1.079	1.219	1.846	2.778	3.866	5.103
H_2-He	0.775	1.320	1.490	2.255	3.394	4.726	6.242
H_2-Kr	0.340	0.601	0.682	1.053	1.607	2.258	2.999

System	200	273.15	293.15	373.15	473.15	573.15	673.15
H_2-N_2	0.408	0.686	0.772	1.162	1.743	2.423	3.196
H_2-Ne	0.572	0.982	1.109	1.684	2.541	3.541	4.677
H_2-O_2		0.692	0.782	1.188	1.792	2.497	3.299
H_2-SF_6			0.412	0.649	0.998	1.400	1.851
H_2-Xe		0.513	0.581	0.890	1.349	1.885	2.493
H_2O-N_2			0.242	0.399			
H_2O-O_2			0.244	0.403	0.645	0.882	1.147
He-Kr	0.330	0.559	0.629	0.942	1.404	1.942	2.550
He-N_2	0.365	0.619	0.698	1.052	1.577	2.188	2.882
He-Ne	0.563	0.948	1.066	1.592	2.362	3.254	4.262
He-O_2		0.641	0.723	1.092	1.640	2.276	2.996
He-SF_6			0.400	0.592	0.871	1.190	1.545
He-Xe	0.282	0.478	0.538	0.807	1.201	1.655	2.168
Kr-N_2		0.131	0.149	0.227	0.346	0.485	0.645
Kr-Ne	0.131	0.228	0.258	0.392	0.587	0.812	1.063
Kr-Xe	0.035	0.064	0.073	0.116	0.181	0.257	0.344
N_2-Ne			0.317	0.483	0.731	1.021	1.351
N_2-O_2			0.202	0.307	0.462	0.643	0.849
N_2-SF_6				0.148	0.231	0.328	0.436
N_2-Xe		0.107	0.122	0.188	0.287	0.404	0.539
Ne-Xe	0.111	0.193	0.219	0.332	0.498	0.688	0.901
O_2-SF_6			0.097	0.154	0.238	0.334	0.441

DIFFUSION COEFFICIENTS IN LIQUIDS AT INFINITE DILUTION

This table lists diffusion coefficients D_{AB} at infinite dilution for some binary liquid mixtures. Although values are given to two decimal places, measurements in the literature are often in poor agreement. Therefore most values in the table cannot be relied upon to better than 10%.

Solvents are listed in alphabetical order, as are the solutes within each solvent group.

Reference

Landolt-Börnstein, *Numerical Data and Functional Relationships in Science and Technology*, Sixth Edition, Vol. II/5a, Springer–Verlag, Heidelberg, 1969.

Solute	Solvent	t/°C	D_{AB} 10^{-5} cm^2 s^{-1}
Acetic acid	Acetone	25	3.31
Benzoic acid	Acetone	25	2.62
Formic acid	Acetone	25	3.77
Nitrobenzene	Acetone	20	2.94
Tetrachloromethane	Acetone	25	3.29
Trichloromethane	Acetone	25	3.64
Water	Acetone	25	4.56
Acetic acid	Benzene	25	2.09
Aniline	Benzene	25	1.96
Benzoic acid	Benzene	25	1.38
Bromobenzene	Benzene	8	1.45
2-Butanone	Benzene	30	2.09
Chloroethylene	Benzene	8	1.77
Cyclohexane	Benzene	25	2.25
Ethanol	Benzene	25	3.02
Formic acid	Benzene	25	2.28
Heptane	Benzene	25	1.78
Methanol	Benzene	25	3.80
Toluene	Benzene	25	1.85
1,2,4-Trichlorobenzene	Benzene	8	1.34
Trichloromethane	Benzene	25	2.26
Adipic acid	1-Butanol	30	0.40
Benzene	1-Butanol	25	1.00
Biphenyl	1-Butanol	25	0.63
Butyric acid	1-Butanol	30	0.51
p-Dichlorobenzene	1-Butanol	25	0.82
Methanol	1-Butanol	30	0.59
Oleic acid	1-Butanol	30	0.25
Propane	1-Butanol	25	1.57
Water	1-Butanol	25	0.56
Benzene	Cyclohexane	25	1.41
Tetrachloromethane	Cyclohexane	25	1.49
Toluene	Cyclohexane	25	1.57
Allyl alcohol	Ethanol	20	0.98
Benzene	Ethanol	25	1.81
Iodine	Ethanol	25	1.32
Iodobenzene	Ethanol	20	1.00
3-Methyl-1-butanol	Ethanol	20	0.81
Pyridine	Ethanol	20	1.10
Tetrachloromethane	Ethanol	25	1.50
Water	Ethanol	25	1.24
Acetic acid	Ethyl acetate	20	2.18
Acetone	Ethyl acetate	20	3.18
2-Butanone	Ethyl acetate	30	2.93
Ethyl benzoate	Ethyl acetate	20	1.85
Nitrobenzene	Ethyl acetate	20	2.25
Water	Ethyl acetate	25	3.20
Benzene	Heptane	25	3.91
Toluene	Heptane	25	3.72
Bromobenzene	Hexane	8	2.60
2-Butanone	Hexane	30	3.74
Dodecane	Hexane	25	2.73
Iodine	Hexane	25	4.45
Methane	Hexane	25	0.09
Propane	Hexane	25	4.87
Tetrachloromethane	Hexane	25	3.70
Toluene	Hexane	25	4.21
Acetone	Tetrachloromethane	25	1.75
Benzene	Tetrachloromethane	25	1.42
Cyclohexane	Tetrachloromethane	25	1.30
Ethanol	Tetrachloromethane	25	1.90
Iodine	Tetrachloromethane	30	1.63
Trichloromethane	Tetrachloromethane	25	1.66
Acetic acid	Toluene	25	2.26
Benzene	Toluene	25	2.54
Benzoic acid	Toluene	25	1.49
Cyclohexane	Toluene	25	2.42
Formic acid	Toluene	25	2.65
Water	Toluene	25	6.19
Acetone	Trichloromethane	25	2.55
Benzene	Trichloromethane	25	2.89
2-Butanone	Trichloromethane	25	2.13
Butyl acetate	Trichloromethane	25	1.71
Diethyl ether	Trichloromethane	25	2.15
Ethanol	Trichloromethane	15	2.20
Ethyl acetate	Trichloromethane	25	2.02
Acetic acid	Water	25	1.29
Acetone	Water	25	1.28
Acetonitrile	Water	15	1.26
Alanine	Water	25	0.91
Allyl alcohol	Water	15	0.90
Aniline	Water	20	0.92
Arabinose	Water	20	0.69
Benzene	Water	20	1.02
1-Butanol	Water	25	0.56
Caprolactam	Water	25	0.87
Chloroethylene	Water	25	1.34
Cyclohexane	Water	20	0.84
Diethylamine	Water	20	0.97
Ethanol	Water	25	1.24
Ethanolamine	Water	25	1.08
Ethyl acetate	Water	20	1.00
Ethylbenzene	Water	20	0.81
Ethylene glycol	Water	25	1.16
Glucose	Water	25	0.67
Glycerol	Water	25	1.06
Glycine	Water	25	1.05
Lactose	Water	15	0.38
Maltose	Water	15	0.38
Mannitol	Water	15	0.50
Methane	Water	25	1.49
Methanol	Water	15	1.28
3-Methyl-1-butanol	Water	10	0.69
Methylcyclopentane	Water	20	0.85
Phenol	Water	20	0.89
1-Propanol	Water	15	0.87
Propene	Water	25	1.44
Pyridine	Water	25	0.58
Raffinose	Water	15	0.33
Sucrose	Water	25	0.52
Toluene	Water	20	0.85
Urea	Water	25	1.38
Urethane	Water	15	0.80

VAPOR PRESSURE OF SATURATED SALT SOLUTIONS

This table gives the vapor pressure of water above saturated solutions of some common salts at ambient temperatures. Data on pure water are given on the last line for comparison.

The references provide additional information on water activity, osmotic coefficient, and enthalpy of vaporization.

References

1. Apelblat, A., *J. Chem. Thermodynamics*, 24, 619, 1992.
2. Apelblat, A., *J. Chem. Thermodynamics,* 25, 63, 1993.
3. Apelblat, A., *J. Chem. Thermodynamics,* 25, 1513, 1993.
4. Apelblat, A. and Korin, E., *J. Chem. Thermodynamics,* 30, 59, 1998.

	Vapor Pressure in kPa							
Salt	**10°C**	**15°C**	**20°C**	**25°C**	**30°C**	**35°C**	**40°C**	**Ref.**
$BaCl_2$	0.971	1.443	2.073	2.887	3.903	5.133	6.576	1
$Ca(NO_3)_2$	0.701	1.015	1.381	1.772	2.154	2.487		1
$CuSO_4$	1.113	1.574	2.189	2.996	4.037	5.363		3
$FeSO_4$	0.978	1.516	2.208	3.035	3.950	4.884		3
KBr	0.953	1.338	1.853	2.533	3.419	4.563		3
KIO_3	1.100	1.564	2.177	2.970	3.979	5.236	6.778	4
K_2CO_3	0.541	0.802	1.134	1.536	1.997	2.499	3.016	1
LiCl	0.128	0.193	0.279	0.384				2
$Mg(NO_3)_2$	0.726	0.999	1.339	1.749	2.231	2.782	3.397	1
$MnCl_2$	0.697	1.064	1.515	2.020	2.535	3.002		3
NH_4Cl	0.971	1.328	1.836	2.481				2
NH_4NO_3	0.853	1.152	1.524	1.972				2
$(NH_4)_2SO_4$	0.901	1.319	1.871	2.573	3.439	4.474		3
NaBr	0.722	1.004	1.376	1.858	2.475	3.255	4.229	4
NaCl	0.921	1.285	1.768	2.401	3.218	4.262	5.581	4
$NaNO_2$	0.703	0.994	1.381	1.888	2.540	3.368	4.403	4
$NaNO_3$	0.884	1.244	1.719	2.335	3.121	4.109	5.333	4
RbCl	0.862	1.215	1.684	2.298	3.088	4.089	5.343	4
$ZnSO_4$	0.945	1.401	1.986	2.698	3.523	4.431	5.382	1
Water	1.228	1.706	2.339	3.169	4.246	5.627	7.381	

DIFFUSION OF GASES IN WATER

This table gives values of the diffusion coefficient, D, for diffusion of several common gases in water at various temperatures. For simple one-dimensional transport, the diffusion coefficient describes the time-rate of change of concentration, dc/dt, through the equation

$$dc/dt = D\, d^2c/dx^2$$

where x is, for example, the perpendicular distance from a gas–liquid interface. The values below have been selected from the references indicated; in some cases data have been refitted to permit interpolation in temperature.

Gas–liquid diffusion coefficients are difficult to measure, and large differences are found between values obtained by different authors and through different experimental methods. See References 1 and 2 for a discussion of measurement techniques.

References

1. Jähne, B., Heinz, G., and Dietrich, W., *J. Geophys. Res.,* 92, 10767, 1987.
2. Himmelblau, D. M., *Chem. Rev*., 64, 527, 1964.
3. Boerboom, A. J. H., and Kleyn, G., *J. Chem. Phys*., 50, 1086, 1969.
4. O'Brien, R. N., and Hyslop, W. F., *Can. J. Chem.*, 55, 1415, 1977.
5. Maharajh, D. M., and Walkley, J., *Can. J. Chem.*, 51, 944, 1973.
6. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, Sixth Edition,* II/5a, *Transport Phenomena I (Viscosity and Diffusion),* Springer–Verlag, Heidelberg, 1969.

$D/10^{-5}$ cm^2 s^{-1}

	10°C	15°C	20°C	25°C	30°C	35°C	Ref.
Ar				2.5			3,4
$CHCl_2F$				1.80			5
CH_3Br				1.35			5
CH_3Cl				1.40			5
CH_4	1.24	1.43	1.62	1.84	2.08	2.35	1
CO_2	1.26	1.45	1.67	1.91	2.17	2.47	1
C_2H_2	1.43	1.59	1.78	1.99	2.23		2
Cl_2		1.13	1.5	1.89			2,6
HBr				3.15			6
HCl				3.07			6
H_2	3.62	4.08	4.58	5.11	5.69	6.31	1
H_2S				1.36			2,6
He	5.67	6.18	6.71	7.28	7.87	8.48	1,3
Kr	1.20	1.39	1.60	1.84	2.11	2.40	1,3
NH_3		1.3	1.5				2
NO_2			1.23	1.4	1.59		2,6
N_2				2.0			2
N_2O		1.62	2.11	2.57			2,6
Ne	2.93	3.27	3.64	4.03	4.45	4.89	1,3
O_2		1.67	2.01	2.42			2,6
Rn	0.81	0.96	1.13	1.33	1.55	1.80	1
SO_2			1.62	1.83	2.07	2.32	2
Xe	0.93	1.08	1.27	1.47	1.70	1.95	1,3

PROPERTIES OF ICE AND SUPERCOOLED WATER

The common form of ice at ambient temperature and pressure is hexagonal ice, designated as ice I_h (see phase diagram in Section 12). The data given here refer to that form. Data have been taken from the references indicated; values have been interpolated and smoothed in some cases. All properties are sensitive to the method of preparation of the sample, since air or other gases are sometimes occluded. For this reason there is often disagreement among values found in the literature.

Density values (except at 0°C) and the thermal expansion coefficient were calculated from the temperature variation in the crystal lattice constants of ice (see Ref. 1). The thermal expansion coefficient appears to become negative around –200°C, but there is considerable scatter in the data.

Density of ice I_h and supercooled water in g cm^{-3}

t/°C	ρ (ice)	ρ (supercooled water)
0	0.9167	0.9998
–10	0.9187	0.9982
–20	0.9203	0.9935
–30	0.9216	0.9839
–40	0.9228	
–50	0.9240	
–60	0.9252	
–80	0.9274	
–100	0.9292	
–120	0.9305	
–140	0.9314	
–160	0.9331	
–180	0.9340	
Ref.	1	8

Phase transition properties:

$\Delta_{fus}H$(0°C) = 333.6 J/g (Ref. 2)
$\Delta_{sub}H$(0°C) = 2838 J/g (Ref. 2)

Other properties of ice I_h:

α_V: cubic thermal expansion coefficient, $\alpha_V = -(1/V)(\partial V/\partial t)_p$
κ : adiabatic compressibility, $\kappa = -(1/V)(\partial V/\partial p)_S$
ε : relative permittivity (dielectric constant)
k : thermal conductivity
c_p: specific heat capacity at constant pressure

t/°C	$\alpha_V/10^{-6}$ °C^{-1}	κ/10^{-5} MPa^{-1}	ε	k/W cm^{-1} °C^{-1}	c_p/J g^{-1} °C^{-1}
0	159	13.0	91.6	0.0214	2.11
–10	155	12.8	94.4	0.023	2.03
–20	149	12.7	97.5	0.024	1.96
–30	143	12.5	99.7	0.025	1.88
–40	137	12.4	101.9	0.026	1.80
–50	130	12.2	106.9	0.028	1.72
–60	122	12.1	119.5	0.030	1.65
–80	105	11.9		0.033	1.50
–100	85	11.6		0.037	1.36
–120	77	11.4		0.042	1.23
–140	60	11.3		0.049	1.10
–160	45	11.2		0.057	0.97
–180	30	11.1		0.070	0.83
–200		11.0		0.087	0.67
–220		10.9		0.118	0.50
–240		10.9		0.20	0.29
–250		10.9		0.32	0.17
Ref.	1,2,3,5	1,5	6	7	1

References

1. Eisenberg, D., and Kauzmann, W., *The Structure and Properties of Water,* Oxford University Press, Oxford, 1969.
2. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series*, V/1b, Springer-Verlag, Heidelberg, 1982.
3. LaPlaca, S., and Post, B., *Acta Cryst*., 13, 503, 1960. [Thermal expansion of lattice]
4. Brill, R., and Tippe, A., *Acta Cryst*., 23, 343, 1967. [Thermal expansion of lattice]
5. Leadbetter, A. J., *Proc. Roy. Soc. A* 287, 403, 1965. [Compressibility and thermal expansion]
6. Auty, R. P., and Cole, R. H., *J. Chem. Phys*., 20, 1309, 1952. [Dielectric constant]
7. Slack, G. A., *Phys. Rev. B*, 22, 3065, 1980. [Thermal conductivity]
8. Hare, D. E., and Sorensen, C. M., *J. Chem. Phys*., 87, 4840, 1987. [Supercooled water]
9. Hobbs, P. V., *Ice Physics,* Clarendon Press, Oxford, 1974.

PROPERTIES OF LIQUID HELIUM

The following data were obtained by a critical evaluation of all existing experimental measurements on liquid helium, using a fitting procedure described in the reference. All values refer to liquid helium at saturated vapor pressure; temperatures are on the ITS–90 scale. Several properties show a singularity at the lambda point (2.1768 K).

p : vapor pressure
ρ : density
C_s : molar heat capacity
$\Delta_{vap}H$: molar enthalpy of vaporization
ε : relative permittivity (dielectric constant)
σ : surface tension
α : coefficient of linear expansion
η : viscosity
λ : thermal conductivity

Reference

Donnelly, R. J., and Barenghi, C. F., *J. Phys. Chem. Reference Data,* 27, 1217, 1998.

T/K	p/kPa	ρ/g cm^{-3}	C_s/J mol^{-1}K^{-1}	$\Delta_{vap}H$/J mol^{-1}	ε	σ /mN m^{-1}	$10^3\alpha$/K^{-1}	η/μPa s	λ /W cm^{-1}K^{-1}
0.0		0.1451397	0	59.83	1.057255		0.000		
0.5		0.1451377	0.010	70.24	1.057254	0.3530	0.107		
1.0	0.01558	0.1451183	0.415	80.33	1.057246	0.3471	0.309	3.873	
1.5	0.4715	0.1451646	4.468	89.35	1.057265	0.3322	–2.36	1.346	
2.0	3.130	0.1456217	21.28	93.07	1.057449	0.3021	–12.2	1.468	
2.5	10.23	0.1448402	9.083	92.50	1.057135	0.2623	39.4	3.259	0.1497
3.0	24.05	0.1412269	9.944	94.11	1.055683	0.2161	61.5	3.517	0.1717
3.5	47.05	0.1360736	12.37	92.84	1.053615	0.1626	88.7	3.509	0.1868
4.0	81.62	0.1289745	15.96	87.00	1.050770	0.1095	129	3.319	0.1965
4.5	130.3	0.1188552	21.8	75.86	1.046725	0.0609	211		
5.0	196.0		44.7	47.67		0.0157			

SURFACE TENSION OF AQUEOUS MIXTURES

The composition dependence of the surface tension of binary mixtures of several compounds with water is given in this table. The data are tabulated as a function of the mass percent of the non-aqueous component. Data for methanol, ethanol, 1-propanol, and 2-propanol are taken from Reference 1, which also gives values at other temperatures.

References

1. Vazquez, G., Alvarez, E., and Navaza, J. M., *J. Chem. Eng. Data*, 40, 611, 1995.
2. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series*, IV/16, *Surface Tension*, Springer-Verlag, Heidelberg, 1997.

		Surface Tension in mN/m for the Specified Mass %										
Compound	***t*/°C**	**0%**	**10%**	**20%**	**30%**	**40%**	**50%**	**60%**	**70%**	**80%**	**90%**	**100%**
Acetic acid	30	71.2	51.4	43.3	41.2	38.2	37.4	36.1	33.5	31.5	30.2	26.3
Acetone	25	72.0	44.9	40.5	36.7	33.0	30.1	29.4	29.4	27.6	24.5	23.1
Acetonitrile	20	72.8	48.5	40.2	34.1	31.6	30.6	30.0	29.6	29.1	28.7	28.4
1,2-Butanediol	25	72.0	66.1	60.4	55.1	50.1	45.6	43.3	41.9	40.8	39.2	35.8
1,3-Butanediol	30	71.2	58.1	51.6	48.7	45.8	43.9	42.4	41.2	40.0	39.0	37.0
1,4-Butanediol	30	71.2	61.2	56.9	54.2	52.0	50.7	49.5	47.9	46.6	45.2	43.8
Butanoic acid	30	71.2	42.4	37.5	35.5	34.8	32.2	30.8	29.2	27.4	26.3	25.5
2-Butanone	20	72.8	41.6	32.2				25.2				24.6
γ-Butyrolactone	30	71.2	64	58	53	50	48	46	45	44	42.8	42.7
Chloroacetic acid	25	72.0	59.8	53.6	51.3	49.7	48.3	47.5	46.1			
Diethanolamine	25	72.0	66.8	63.2	60.7	58.8	57.2	55.7	54.3	52.7	50.6	47.2
N,N-Dimethylacetamide	25	72.0	72.0	72.0	72.4	73.5	74.9	75.4	73.0	65.7	54.7	36.4
N,N-Dimethylformamide	25	72.0	65.4	59.2	53.8	49.6	47.3	46.9	44.9	42.3	38.4	35.2
1,4-Dioxane	25	72.0					41.2	39.6	37.9	36.2	34.5	33.7
Ethanol	25	72.01	47.53	37.97	32.98	30.16	27.96	26.23	25.01	23.82	22.72	21.82
Ethylene glycol	20	72.8	68.5	64.9	61.9		57.0					48.2
Formic acid	20	72.8	66	60	55.7	52.2	50.3	48.8	47.1	44.7	40.9	38.0
Glycerol	25	72.0	70.5	69.5	68.5	67.9	67.4	66.9	66.5	65.7	64.5	62.5
Methanol	25	72.01	56.18	47.21	41.09	36.51	32.86	29.83	27.48	25.54	23.93	22.51
Morpholine	20	72.8	65.1	60.7	58.9	56.7	53.0	49.6	47.0	43.7	41.8	38.7
Nitric acid	20	72.8	71.9	70.7	68.9	66.6	63.8	60.6	56.8	52.6	47.9	42.6
Propanoic acid	30	71.2	46.6	42.2	37.7	35.6	33.1	31.7	30.2	28.2	27.4	25.8
1-Propanol	25	72.01	34.32	27.84	25.98	25.26	24.80	24.49	24.08	23.86	23.59	23.28
2-Propanol	25	72.01	40.42	30.57	26.82	25.27	24.26	23.51	22.68	22.14	21.69	21.22
1,2-Propylene glycol	30	71.2	60.5	54.9	50.7	47.2	44.5	41.5	38.6	37.6	36.3	35.5
1,3-Propylene glycol	30	71.2	62.6	58.8	55.7	53.8	52.8	51.7	50.8	49.6	48.2	47.0
Pyridine	25	72.0	52.8	51.2	48.0	46.8	46.6	45.8	45.0	43.6	40.9	37.0
Sulfolane	20	72.8					62.5	61.6	59.6	57.1	54.9	50.9
Sulfuric acid	50	67.9	73.5	75.1	73.6	71.2	68.0	64.1	60.0	56.4	53.6	51.7
Trichloroacetaldehyde	25	72.0	56.7	51.0	46.7	44.1	43.0	42.5	41.5	38.9	34.7	29.4
Trichloroacetic acid	25	72.0	55.8	46.5	42.8	41.6	40.6	39.4	38.3	37.4	36.5	

VISCOSITY OF CARBON DIOXIDE ALONG THE SATURATION LINE

The table below gives the viscosity of gas and liquid CO_2 along the liquid–vapor saturation line.

		Gas	Liquid
***T*/K**	***P*/kPa**	**η/μPa s**	**η/μPa s**
205	227	10.33	
210	327	10.60	
215	465	10.87	
220	600	11.13	241.68
225	735	11.41	221.72
230	894	11.69	203.75
235	1075	11.98	187.48
240	1283	12.27	172.67
245	1519	12.58	159.13
250	1786	12.90	146.69
255	2085	13.24	135.20
260	2419	13.61	124.30
265	2790	14.02	114.63
270	3203	14.47	105.21
275	3658	14.99	96.44
280	4160	15.61	87.89
285	4712	16.37	79.64
290	5315	17.36	71.47
295	5984	18.79	63.01
300	6710	21.29	53.33
302	6997	23.52	48.30

References

1. Fenghour, A., Wakeham, W. A., and Vesovic, V., *J. Phys. Chem. Ref. Data*, 27, 31, 1998.
2. Angus, S., et al., *International Tables for the Fluid State: Carbon Dioxide*, Pergamon Press, Oxford, 1976.

PERMITTIVITY (DIELECTRIC CONSTANT) OF WATER AS A FUNCTION OF TEMPERATURE AND PRESSURE

The following table summarizes the relative permittivity (static dielectric constant) of liquid water and steam over a wide range of temperature and pressure. Values are given from slightly above the freezing point to 1000 K and at pressures from normal atmospheric to 1000 MPa (about 10000 atm). The values are generated from an equation that correlates the best experimental measurements from a large number of sources. The correlating equation and full details of the formulation may be found in Reference 1.

Temperatures are given on the ITS-90 scale. Liquid–vapor boundaries are indicated by horizontal lines.

Reference

Fernandez, D. P., Goodwin, A. R. H., Lemmon, E. W., Levelt Sengers, J. M. H., and Williams, R. C., *J. Phys. Chem. Ref. Data*, 26, 1125, 1997.

	Pressure in MPa										
***T*/K**	**0.1**	**1**	**2**	**5**	**10**	**20**	**50**	**100**	**200**	**500**	**1000**
275	87.16	87.20	87.24	87.36	87.57	87.97	89.16	91 05	94.55	103.7	
280	85.19	85.23	85.27	85.39	85.59	85.98	87.14	88.98	92.38	101.3	
285	83.27	83.30	83.34	83.46	83.65	84.04	85.17	86.96	90.27	98.91	
290	81.39	81.42	81.46	81.57	81.76	82.14	83.24	84.99	88.22	96.64	
295	79.55	79.58	79.62	79 73	79.92	80.29	81.37	83.08	86.24	94.44	
300	77.75	77.78	77.82	77.93	78.11	78.48	79.54	81.22	84.31	92.31	
305	75.99	76.02	76.06	76.17	76.35	76.71	77.75	79.40	82.43	90.25	101.3
310	74.27	74.30	74.33	74.44	74.62	74.98	76.01	77.63	80.61	88.26	99.06
315	72.58	72.61	72.65	72.76	72.93	73.28	74.30	75.90	78.84	86.34	96.87
320	70.93	70.97	71.00	71.11	71.28	71.63	72.64	74.22	77.11	84.48	94.76
340	64.70	64.73	64.77	64.87	65.04	65.38	66.36	67.89	70.65	77.58	87.07
360	59.00	59.03	59 07	59.17	59.34	59.68	60.65	62.15	64.83	71.45	80.36
380	1.006	53.83	53.86	53.97	54.14	54.48	55.45	56.94	59.57	65.95	74.43
400	1.005	49.06	49.10	49.21	49.39	49.73	50.71	52.20	54.80	61.00	69.12
420	1.005	44.70	44.74	44.85	45.04	45.39	46.39	47.90	50.48	56.53	64.35
440	1.004	40.70	40.74	40 85	41.05	41.42	42.45	43.98	46.55	52.48	60.03
460	1.004	1.041	37.04	37.17	37.37	37.76	38.84	40.40	42.99	48.81	56.11
480	1.004	1.038	33.61	33.75	33.97	34.39	35.53	37.14	39.75	45.47	52.55
500	1.003	1.034	1.074	30.55	30.79	31.25	32.47	34.15	36.79	42.44	49.30
550	1.003	1.028	1.059	1.177	23.53	24.18	25.73	27.67	30.46	35.99	42.38
600	1.002	1.024	1.049	1.137	1.365	17.50	19.90	22.29	25.34	30.82	36.82
650	1.002	1.020	1.041	1.112	1.267	2.066	14.50	17.72	21.12	26.62	32.31
700	1.002	1.017	1.036	1.095	1.214	1.603	8.963	13.75	17.60	23.17	28.60
750	1.002	1.015	1.031	1.082	1.179	1.452	4.424	10.34	14.65	20.30	25.51
800	1.001	1.013	1.027	1.071	1.154	1.365	2.844	7.562	12.17	17.88	22.91
850	1.001	1.012	1.024	1.063	1.134	1.307	2.269	5.571	10.10	15.83	20.70
900	1.001	1.011	1.022	1.056	1.118	1.265	1.975	4.284	8.416	14.08	18.80
950	1.001	1.010	1.020	1.050	1.105	1.232	1.793	3.477	7.066	12.57	17.15
1000	1.001	1.009	1.018	1.046	1.095	1.206	1.668	2.956	6.003	11.27	15.72
1050	1.001	1.008	1.016	1.041	1.086	1.184	1.576	2.601	5.172	10.14	14.45
1100	1.001	1.007	1.015	1.038	1.078	1.167	1.505	2.347	4.523	9.160	13.34
1150	1.001	1.007	1.014	1.035	1.072	1.151	1.449	2.158	4.012	8.309	12.35
1200	1.001	1.006	1.013	1.032	1.066	1.139	1.403	2.011	3.606	7.569	11.47

VISCOSITY AND DENSITY OF AQUEOUS HYDROXIDE SOLUTIONS

The viscosity and density of aqueous hydroxide solutions at 25°C is tabulated here as a function of concentration. Viscosity is given in millipascal second, which is equal to the c.g.s. unit centipoise (cP). The last entry in each column refers to the saturated solution.

Reference

Sipos, P. M., Hefter, G., and May, P. M., *J. Chem. Eng. Data,* 45, 613, 2000.

Viscosity in mPa s

c/mol L^{-1}	LiOH	NaOH	KOH	CsOH	$(CH_3)_4NOH$
0.5	1.017	0.997	0.937	0.91	1.017
1.0	1.169	1.116	0.990	0.94	1.186
1.5	1.340	1.248	1.050	0.97	1.430
2.0	1.537	1.396	1.116	1.03	1.762
3.0	2.050	1.754	1.269	1.19	3.031
4.0	2.734	2.228	1.448	1.41	7.238
5.0		2.867	1.657	1.67	
6.0		3.727	1.902	1.98	
7.0		4.869	2.196	2.40	
8.0		6.351	2.554	3.09	
9.0		8.230	3.005	4.31	
10.0		10.554	3.581	6.46	
11.0		13.362	4.328		
12.0		16.677	5.303		
13.0		20.503	6.577		
14.0		24.826	8.235		
15.0		29.604			
16.0		34.767			
17.0		40.212			
18.0		45.800			
19.0		51.354			
Sat.	3.311	51.911	8.526		8.850

Density in g/cm^3

c/mol L^{-1}	LiOH	NaOH	KOH	CsOH	$(CH_3)_4NOH$
0.5	1.012	1.019	1.022	1.063	0.999
1.0	1.025	1.040	1.045	1.128	1.002
1.5	1.038	1.059	1.068	1.193	1.005
2.0	1.050	1.078	1.090	1.257	1.009
3.0	1.072	1.115	1.133	1.383	1.019
4.0	1.093	1.149	1.174	1.508	1.030
5.0		1.182	1.214	1.632	
6.0		1.213	1.253	1.755	
7.0		1.243	1.290	1.876	
8.0		1.271	1.326	1.997	
9.0		1.299	1.362	2.117	
10.0		1.325	1.396	2.236	
11.0		1.350	1.429	2.354	
12.0		1.374	1.462	2.471	
13.0		1.397	1.494	2.587	
14.0		1.419	1.524	2.703	
15.0		1.441			
16.0		1.461			
17.0		1.481			
18.0		1.499			
19.0		1.517			
Sat.	1.109	1.519	1.529	2.800	1.032

VAPOR PRESSURE OF MERCURY

The following table gives the vapor pressure of mercury in kilopascals (100 kPa = 1 bar) from 0°C to 800°C.

References

1. Vukalovich, M. P., and Fokin, L. R., *Thermophysical Properties of Mercury,* Standards Press (USSR), 1972.
2. Vargaftik, N. B., Vinogradov, Y. K., and Yargin, V. S., *Handbook of Physical Properties of Liquids and Gases, Third Edition*, Begell House, New York, 1996.

***t*/°C**	***p*/kPa**	***t*/°C**	***p*/kPa**	***t*/°C**	***p*/kPa**	***t*/°C**	***p*/kPa**
0	2.728×10^{-5}	210	3.177	420	285.2	630	3072
10	7.101×10^{-5}	220	4.304	430	329.9	640	3347
20	1.729×10^{-4}	230	5.758	440	380.1	650	3641
30	3.680×10^{-4}	240	7.614	450	436.2	660	3953
40	8.626×10^{-4}	250	9.959	460	498.6	670	4285
50	1.786×10^{-3}	260	12.892	470	567.9	680	4636
60	3.536×10^{-3}	270	16.527	480	644.6	690	5009
70	6.724×10^{-3}	280	20.993	490	729.2	700	5403
80	0.01232	290	26.435	500	822.2	710	5820
90	0.02128	300	33.015	510	924.2	720	6259
100	0.03745	310	40.910	520	1035.8	730	6722
110	0.06247	320	50.320	530	1157.6	740	7210
120	0.1015	330	61.460	540	1290.1	750	7722
130	0.1608	340	74.567	550	1434.0	760	8260
140	0.2491	350	89.896	560	1589.9	770	8825
150	0.3778	360	107.72	570	1758.4	780	9417
160	0.5618	370	128.34	580	1940.3	790	10037
170	0.8204	380	152.07	590	2136	800	10685
180	1.178	390	179.25	600	2346		
190	1.664	400	210.24	610	2572		
200	2.315	410	245.4	620	2814		

VISCOSITY OF LIQUID METALS

This table gives the viscosity of several liquid metals as a function of temperature. Experimental data from some of the references were smoothed to produce the table. Viscosity is given in millipascal second (mPa s), which equals the c.g.s. unit centipoise (cP).

References

1. Shpil'rain, E. E., Yakimovich, K. A., Fomin, V. A., Skovorodjko, S. N., and Mozgovoi, A. G., in *Handbook of Thermodynamic and Transport Properties of the Alkali Metals*, Ohse, R. H., Ed., Blackwell Scientific Publishers, Oxford, 1985. [Li, Na, K, Rb, Cs]
2. Rothwell, E., *J. Inst. Metals*, 90, 389, 1961. [Al]
3. Culpin, M. F., *Proc. Phys. Soc.*, 70, 1079, 1957. [Ca]
4. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, Sixth Edition,* II/5a, *Transport Phenomena I (Viscosity and Diffusion)*, Springer–Verlag, Heidelberg, 1961 [Co, Au, Mg, Ni, Ag]
5. Spells, K. E., *Proc. Phys. Soc.*, 48, 299, 1936. [Ga]
6. Walsdorfer, H., Arpshofen, I., and Predel, B., *Z. Met.*, 79, 503, 1988. [In]

	Viscosity in mPa s					
***t*/°C**	**Lithium**	**Sodium**	**Potassium**	**Rubidium**	**Cesium**	**Gallium**
50				0.542	0.598	1.921
100		0.687	0.441	0.435	0.469	1.608
150		0.542	0.358	0.365	0.389	1.397
200	0.566	0.451	0.303	0.316	0.334	1.245
250	0.503	0.387	0.263	0.280	0.294	1.130
300	0.453	0.341	0.234	0.252	0.264	1.040
350	0.412	0.306	0.211	0.230	0.240	0.968
400	0.379	0.278	0.193	0.212	0.221	0.909
450	0.352	0.255	0.178	0.197	0.206	0.859
500	0.328	0.237	0.166	0.185	0.192	0.817
550	0.308	0.221	0.155	0.174	0.181	0.781
600	0.290	0.208	0.146	0.165	0.171	0.750
650	0.275	0.196	0.138	0.157	0.163	0.722
700	0.261	0.186	0.132	0.150	0.156	0.698
750	0.249	0.177	0.126	0.143	0.149	0.677
800	0.238	0.170	0.120	0.138	0.143	0.657
850	0.228	0.163	0.115	0.133	0.138	0.640
900	0.219	0.156	0.111	0.128	0.134	0.624
950	0.211	0.151	0.107	0.124	0.129	0.610
1000	0.204	0.146	0.104	0.120	0.125	0.597
1050	0.197	0.141	0.101	0.117	0.122	0.585
1100	0.191	0.137	0.098	0.114	0.119	0.574
1150	0.185	0.133	0.095	0.111	0.116	
1200	0.180	0.129	0.092	0.108	0.113	
1250	0.175	0.126	0.090	0.105	0.110	
1300	0.170	0.123	0.088	0.103	0.108	
1350	0.166	0.120	0.086	0.101	0.106	
1400	0.162	0.117	0.084	0.099	0.104	
1450	0.158	0.115	0.082	0.097	0.102	
1500	0.155	0.113	0.081	0.095	0.100	
1550	0.151	0.110	0.079	0.093	0.098	
1600	0.148	0.108	0.078	0.092	0.097	
1650	0.145	0.106	0.076	0.090	0.095	
1700	0.142	0.105	0.075		0.094	
1750	0.139	0.103	0.074		0.092	
1800	0.137	0.101			0.091	
1850	0.135	0.100			0.090	
1900	0.132	0.098			0.089	
1950	0.130	0.097			0.088	
2000	0.128	0.096			0.086	

	Viscosity in mPa s							
***t*/°C**	**Aluminum**	**Calcium**	**Cobalt**	**Gold**	**Indium**	**Magnesium**	**Nickel**	**Silver**
250					1.35			
300					1.22			
350					1.12			
400					1.04			
450					0.98			
700	1.289					1.10		
750	1.200					0.96		
800	1.115					0.84		
850	1.028	1.107				0.74		
900		0.959				0.67		
1000								3.80
1050								3.56
1100				5.130				3.31
1150				4.874				3.06
1200				4.640				2.82
1250				4.429				2.61
1300				4.240				2.42
1350								2.28
1400								2.20
1450								2.19
1500			4.15				4.35	
1550			3.89				4.09	
1600			3.64				3.87	
1650			3.41				3.67	
1700			3.20				3.49	
1750			2.99				3.32	

PROPERTIES OF AMINO ACIDS

This table gives selected properties of some important amino acids and closely related compounds. The first part of the table lists the 20 "standard" amino acids that are the basic constituents of proteins. The second part includes other amino acids and related compounds of biochemical importance. Within each part of the table the compounds are listed by name in alphabetical order. Structures are given in the following table.

Symbol : Three-letter symbol for the standard amino acids
M_r: Molecular weight
t_m: Melting point
pK_a , pK_b , pK_c , pK_d : Negative of the logarithm of the acid dissociation constants for the COOH and NH_2 groups (and, in some cases, other groups) in the molecule (at 25°C)
pI: pH at the isoelectric point
S: Solubility in water in units of grams of compound per kilogram of water; a temperature of 25°C is understood unless otherwise stated in a superscript. When quantitative data are not available, the notations sl.s. (for slightly soluble), s. (for soluble), and v.s. (for very soluble) are used.
V_2^0: Partial molar volume in aqueous solution at infinite dilution (at 25°C)

Data on the enthalpy of formation of many of these compounds are included in the table "Standard Thermodynamic Properties of Chemical Substances" in Section 5 of this Handbook. Absorption spectra and optical rotation data can be found in Reference 3. Partial molar volume is taken from Reference 5; other thermodynamic properties, including solubility as a function of temperature, are given in References 3 and 5. Most of the p*K* values come from References 1, 6, and 7.

References


1. Dawson, R. M. C., Elliott, D. C., Elliott, W. H., and Jones, K. M., *Data for Biochemical Research*, Third Edition, Clarendon Press, Oxford, 1986.
2. O'Neil, Maryadele J., Ed., *The Merck Index, Thirteenth Edition*, Merck & Co., Rahway, NJ, 2001.
3. Sober, H. A., Ed., *CRC Handbook of Biochemistry. Selected Data for Molecular Biology,* CRC Press, Boca Raton, FL, 1968.
4. Voet, D., and Voet, J. G., *Biochemistry, Second Edition,* John Wiley & Sons, New York, 1995.
5. Hinz, H. J., Ed., *Thermodynamic Data for Biochemistry and Biotechnology*, Springer–Verlag, Heidelberg, 1986.
6. Fasman, G. D., Ed. *Practical Handbook of Biochemistry and Molecular Biology*, CRC Press, Boca Raton, FL, 1989.
7. Smith, R. M., and Martell, A. E., *NIST Standard Reference Database 46: Critically Selected Stability Constants of Metal Complexes Database*, Version 3.0, National Institute of Standards and Technology, Gaithersburg, MD, 1997.
8. Ramasami, P., *J. Chem. Eng. Data*, 47, 1164, 2002.

Symbol	Name	Mol. form	M_r	t_m/°C	pK_a	pK_b	pK_c	pK_d	pI	S/g kg^{-1}	V_2^0/cm^3 mol^{-1}
Ala	*L*-Alanine	$C_3H_7NO_2$	89.09	297	2.33	9.71			6.00	166.9	60.54
Arg	*L*-Arginine	$C_6H_{14}N_4O_2$	174.20	244	2.03	9.00	12.10		10.76	182.6	127.42
Asn	*L*-Asparagine	$C_4H_8N_2O_3$	132.12	235	2.16	8.73			5.41	25.1	78.0
Asp	*L*-Aspartic acid	$C_4H_7NO_4$	133.10	270	1.95	9.66	3.71		2.77	5.04	74.8
Cys	*L*-Cysteine	$C_3H_7NO_2S$	121.16	240	1.91	10.28	8.14		5.07	v.s.	73.45
Gln	*L*-Glutamine	$C_5H_{10}N_2O_3$	146.14	185	2.18	9.00			5.65	42.5	
Glu	*L*-Glutamic acid	$C_5H_9NO_4$	147.13	160	2.16	9.58	4.15		3.22	8.6	89.85
Gly	Glycine	$C_2H_5NO_2$	75.07	290	2.34	9.58			5.97	250.2	43.26
His	*L*-Histidine	$C_6H_9N_3O_2$	155.15	287	1.70	9.09	6.04		7.59	43.5	98.3
Ile	*L*-Isoleucine	$C_6H_{13}NO_2$	131.17	284	2.26	9.60			6.02	34.2	105.80
Leu	*L*-Leucine	$C_6H_{13}NO_2$	131.17	293	2.32	9.58			5.98	22.0	107.77
Lys	*L*-Lysine	$C_6H_{14}N_2O_2$	146.19	224	2.15	9.16	10.67		9.74	5.8	108.5
Met	*L*-Methionine	$C_5H_{11}NO_2S$	149.21	281	2.16	9.08			5.74	56	105.57
Phe	*L*-Phenylalanine	$C_9H_{11}NO_2$	165.19	283	2.18	9.09			5.48	27.9	121.5
Pro	*L*-Proline	$C_5H_9NO_2$	115.13	221	1.95	10.47			6.30	1622	82.76
Ser	*L*-Serine	$C_3H_7NO_3$	105.09	228	2.13	9.05			5.68	250	60.62
Thr	*L*-Threonine	$C_4H_9NO_3$	119.12	256	2.20	8.96			5.60	98.1	76.90
Trp	*L*-Tryptophan	$C_{11}H_{12}N_2O_2$	204.23	289	2.38	9.34			5.89	13.2	143.8
Tyr	*L*-Tyrosine	$C_9H_{11}NO_3$	181.19	343	2.24	9.04	10.10		5.66	0.46	
Val	*L*-Valine	$C_5H_{11}NO_2$	117.15	315	2.27	9.52			5.96	88	90.75


Name	Mol. form	M_r	t_m/°C	pK_a	pK_b	pK_c	pK_d	pI	S/g kg^{-1}	V_2^0/cm^3 mol^{-1}
N-Acetylglutamic acid	$C_7H_{11}NO_5$	189.17	199						s.	
*N*6-Acetyl-*L*-lysine	$C_8H_{16}N_2O_3$	188.22	265	2.12	9.51					
β-Alanine	$C_3H_7NO_2$	89.09	200	3.51	10.08				723.6	58.28
2-Aminoadipic acid	$C_6H_{11}NO_4$	161.16	207	2.14	4.21	9.77		3.18	2.2[40]	
DL-2-Aminobutanoic acid	$C_4H_9NO_2$	103.12	304	2.30	9.63			6.06	210	75.6
DL-3-Aminobutanoic acid	$C_4H_9NO_2$	103.12	194.3	3.43	10.05			7.30	1250	76.3
4-Aminobutanoic acid	$C_4H_9NO_2$	103.12	203	4.02	10.35				971	73.2
10-Aminodecanoic acid	$C_{10}H_{21}NO_2$	187.28	188.5							167.3

Name	Mol. form	M_r	t_m/°C	pK_a	pK_b	pK_c	pK_d	pI	S/g kg^{-1}	V_2^0/cm^3 mol^{-1}
7-Aminoheptanoic acid	$C_7H_{15}NO_2$	145.20	195						v.s.	120.0
6-Aminohexanoic acid	$C_6H_{13}NO_2$	131.17	205					7.29	863	104.2
L-3-Amino-2-methylpropanoic acid	$C_4H_9NO_2$	103.12	185						s.	
2-Amino-2-methylpropanoic acid	$C_4H_9NO_2$	103.12	335	2.36	10.21			5.72	137	77.55
9-Aminononanoic acid	$C_9H_{19}NO_2$	173.26	191							151.3
8-Aminooctanoic acid	$C_8H_{17}NO_2$	159.23	192							136.1
5-Amino-4-oxopentanoic acid	$C_5H_9NO_3$	131.13	118	4.05	8.90					
5-Aminopentanoic acid	$C_5H_{11}NO_2$	117.15	157 dec						s.	87.6
o-Anthranilic acid	$C_7H_7NO_2$	137.14	146	2.05	4.95				3.5[14]	
Azaserine	$C_5H_7N_3O_4$	173.13	150		8.55				v.s.	
Canavanine	$C_5H_{12}N_4O_3$	176.17	172	2.50	6.60	9.25		7.93	v.s.	
L-γ-Carboxyglutamic acid	$C_6H_9NO_6$	191.14	167	1.70	9.90	4.75	3.20			
Carnosine	$C_9H_{14}N_4O_3$	226.23	260	2.51	9.35	6.76			322	
Citrulline	$C_6H_{13}N_3O_3$	175.19	222	2.32	9.30			5.92	s.	
Creatine	$C_4H_9N_3O_2$	131.13	303	2.63	14.30				16	
L-Cysteic acid	$C_3H_7NO_5S$	169.16	260	1.89	8.70	1.30			v.s.	
L-Cystine	$C_6H_{12}N_2O_4S_2$	240.30	260	1.50	8.80	2.05	8.03		0.11	
2,4-Diaminobutanoic acid	$C_4H_{10}N_2O_2$	118.13	118.1	1.85	8.24	10.44		9.27	s.	
3,5-Dibromo-*L*-tyrosine	$C_9H_9Br_2NO_3$	338.98	245						2.72	
3,5-Dichloro-*L*-tyrosine	$C_9H_9Cl_2NO_3$	250.08	247						1.97	
3,5-Diiodo-*L*-tyrosine	$C_9H_9I_2NO_3$	432.98	213	2.12	9.10	6.16			0.62	
Dopamine	$C_8H_{11}NO_2$	153.18			10.36	8.88			s.	
L-Ethionine	$C_6H_{13}NO_2S$	163.24	273	2.18	9.05	13.10				
N-Glycylglycine	$C_4H_8N_2O_3$	132.12	263	3.13	8.10				225	
Guanidinoacetic acid	$C_3H_7N_3O_2$	117.11	282	2.82					5	
Histamine	$C_5H_9N_3$	111.15	83		9.83	6.11			v.s.	
L-Homocysteine	$C_4H_9NO_2S$	135.19	232	2.15	8.57	10.38		5.55	s.	
Homocystine	$C_8H_{16}N_2O_4S_2$	268.35	264	1.59	9.44	2.54	8.52		0.2	
L-Homoserine	$C_4H_9NO_3$	119.12	203	2.27	9.28			6.17	1100	
3-Hydroxy-*DL*-glutamic acid	$C_5H_9NO_5$	163.13	209					3.28		
5-Hydroxylysine	$C_6H_{14}N_2O_3$	162.19		2.13	8.85	9.83		9.15		
trans-4-Hydroxy-*L*-proline	$C_5H_9NO_3$	131.13	274	1.82	9.47			5.74	361	84.49
L-3-Iodotyrosine	$C_9H_{10}INO_3$	307.08	205	2.20	9.10	8.70			sl.s.	
L-Kynurenine	$C_{10}H_{12}N_2O_3$	208.21	194						sl.s.	
L-Lanthionine	$C_6H_{12}N_2O_4S$	208.24	294						1.5	
Levodopa	$C_9H_{11}NO_4$	197.19	277	2.32	8.72	9.96	11.79		5[20]	
L-1-Methylhistidine	$C_7H_{11}N_3O_2$	169.18	249	1.69	8.85	6.48			200	
L-Norleucine	$C_6H_{13}NO_2$	131.17	301	2.31	9.68			6.09	15	107.7
L-Norvaline	$C_5H_{11}NO_2$	117.15	307	2.31	9.65				107	91.8
L-Ornithine	$C_5H_{12}N_2O_2$	132.16	140	1.94	8.78	10.52		9.73	v.s.	
O-Phosphoserine	$C_3H_8NO_6P$	185.07	166	2.14	9.80	5.70				
L-Pyroglutamic acid	$C_5H_7NO_3$	129.12	162	3.32						
Sarcosine	$C_3H_7NO_2$	89.09	212	2.18	9.97				428	
Taurine	$C_2H_7NO_3S$	125.15	328	-0.3	9.06				105	
L-Thyroxine	$C_{15}H_{11}I_4NO_4$	776.87	235	2.20	10.01	6.45			sl.s.	


STRUCTURES OF COMMON AMINO ACIDS




L-Alanine (Ala)




L-Arginine (Arg)




L-Asparagine (Asn)




L-Aspartic acid (Asp)




L-Cysteine (Cys)




L-Glutamine (Gln)




L-Glutamic acid (Glu)




Glycine (Gly)




L-Histidine (His)




L-Isoleucine (Ile)




L-Leucine (Leu)




L-Lysine (Lys)




L-Methionine (Met)




L-Phenylalanine (Phe)




L-Proline (Pro)




L-Serine (Ser)




L-Threonine (Thr)




L-Tryptophan (Trp)




L-Tyrosine (Tyr)




L-Valine (Val)




N-Acetylglutamic acid




*N*6-Acetyl-*L*-lysine




β-Alanine




2-Aminoadipic acid




DL-2-Aminobutanoic acid




DL-3-Aminobutanoic acid




4-Aminobutanoic acid




6-Aminohexanoic acid




L-3-Amino-2-methylpropanoic acid




2-Amino-2-methylpropanoic acid




5-Amino-4-oxopentanoic acid




5-Aminopentanoic acid




Azaserine




Canavanine





L-γ-Carboxyglutamic acid





Carnosine



Citrulline



Creatine



L-Cysteic acid



L-Cystine



2,4-Diaminobutanoic acid



3,5-Dibromo-*L*-tyrosine



3,5-Diiodo-*L*-tyrosine



Dopamine



L-Ethionine



N-Glycylglycine



Guanidinoacetic acid



Histamine



L-Homocysteine



Homocystine



L-Homoserine



trans-4-Hydroxy-*L*-proline



L-3-Iodotyrosine



L-Kynurenine



L-Lanthionine



Levodopa



L-1-Methylhistidine



L-Norleucine



L-Norvaline



L-Ornithine


O-Phosphoserine


L-Pyroglutamic acid


Sarcosine



Taurine


L-Thyroxine


PROPERTIES OF PURINE AND PYRIMIDINE BASES

This table lists some of the important purine and pyrimidine bases that occur in nucleic acids. The pK_a values (negative logarithm of the acid dissociation constant) are given for each ionization stage. The last column gives the aqueous solubility S at the indicated temperature in units of grams per 100 grams of solution.

The numbering system in the rings is:



Purine



Pyrimidine

References

1. Dawson, R. M. C., et al., *Data for Biochemical Research*, 3rd ed., Clarendon Press, Oxford, 1986.
2. O'Neil, M. J., Ed., *The Merck Index*, 13th ed., Merck and Co., Rahway, NJ, 2001.

Common name	Systematic name	Mol. form.	Mol. wt.	pK_a values			S/mass % (temp.)
Pyrimidines							
Cytosine	4-Amino-2-hydroxypyrimidine	$C_4H_5N_3O$	111.10	4.60	12.16		0.73 (25°C)
5-Methylcytosine	4-Amino-2-hydroxy-5-methylpyrimidine	$C_5H_7N_3O$	125.13	4.6	12.4		0.45 (25°C)
5-Hydroxymethylcytosine	4-Amino-2-hydroxy-5-hydroxymethylpyrimidine	$C_5H_7N_3O_2$	141.13	4.3	13		
Uracil	2,4-Dihydroxypyrimidine	$C_4H_4N_2O_2$	112.09	0.5	9.5	>13	0.27 (25°C)
Thymine	5-Methyluracil	$C_5H_6N_2O_2$	126.11	9.94	>13		0.35 (25°C)
Orotic acid	Uracil-6-carboxylic acid	$C_5H_4N_2O_4$	156.10	2.4	9.5	>13	0.18 (18°C)
Purines							
Adenine	6-Aminopurine	$C_5H_5N_5$	135.14	<1	4.3	9.83	0.104 (25°C)
Guanine	2-Amino-6-hydroxypurine	$C_5H_5N_5O$	151.13	3.3	9.2	12.3	0.0068 (40°C)
7-Methylguanine	7-Methyl-2-amino-6-hydroxypurine	$C_6H_7N_5O$	165.16	3.5	9.9		
Isoguanine	6-Amino-2-hydroxypurine	$C_5H_5N_5O$	151.13	4.5	9.0		0.006 (25°C)
Xanthine	2,6-Dioxopurine	$C_5H_4N_4O_2$	152.11	0.8	7.4	11.1	0.05 (20°C)
Hypoxanthine	6-Hydroxypurine	$C_5H_4N_4O$	136.11	2.0	8.9	12.1	0.07 (19°C)
Uric acid	2,6,8-Trihydroxypurine	$C_5H_4N_4O_3$	168.11	5.4	11.3		0.002 (20°C)

THE GENETIC CODE

This table gives the correspondence between a messenger RNA codon and the amino acid which it specifies. The symbols for bases in the codon are:

U: uracil
C: cytosine
A: adenine
G: guanine

The amino acid symbols are given in the table entitled "Structures of Common Amino Acids". A chain-initiating codon is indicated by **init** and a chain-terminating codon by **term**.

Example: UCA codes for **Ser**, UAC codes for **Tyr**, etc.

	Second position				
First position	**U**	**C**	**A**	**G**	**Third position**
U	Phe	Ser	Tyr	Cys	U
	Phe	Ser	Tyr	Cys	C
	Leu	Ser	**term**	**term**	A
	Leu	Ser	**term**	Trp	G
C	Leu	Pro	His	Arg	U
	Leu	Pro	His	Arg	C
	Leu	Pro	Gln	Arg	A
	Leu	Pro	Gln	Arg	G
A	Ile	Thr	Asn	Ser	U
	Ile	Thr	Asn	Ser	C
	Ile	Thr	Lys	Arg	A
	Met (**init**)	Thr	Lys	Arg	G
G	Val	Ala	Asp	Gly	U
	Val	Ala	Asp	Gly	C
	Val	Ala	Glu	Gly	A
	Val (**init**)	Ala	Glu	Gly	G

PROPERTIES OF FATTY ACIDS

This table gives the systematic names and selected properties of some of the more important fatty acids of five or more carbon atoms. Compounds are listed first by degree of saturation and, secondly, by number of carbon atoms. The following data are included:

M_r: Molecular weight
S: Aqueous solubility at 20°C in units of grams of solute per 100 grams of water
t_m: Melting point in °C

References

1. Dawson, R. M. C., Elliott, D. C., Elliott, W. H., and Jones, K. M., *Data for Biochemical Research*, 3rd ed., Clarendon Press, Oxford, 1986.
2. Fasman, G. D., Ed., *Practical Handbook of Biochemistry and Molecular Biology*, CRC Press, Boca Raton, FL, 1989.

Common name	Systematic name	Mol. form.	M_r	t_m/°C	*S*
Saturated					
Valeric acid	Pentanoic acid	$C_5H_{10}O_2$	102.13	–33.6	2.5
Isovaleric acid	3-Methylbutanoic acid	$C_5H_{10}O_2$	102.13	–29.3	4.3
Caproic acid	Hexanoic acid	$C_6H_{12}O_2$	116.16	–3	0.967
Enanthic acid	Heptanoic acid	$C_7H_{14}O_2$	130.19	–7.17	0.24
Caprylic acid	Octanoic acid	$C_8H_{16}O_2$	144.21	16.5	0.080
Pelargonic acid	Nonanoic acid	$C_9H_{18}O_2$	158.24	12.4	0.0284
Capric acid	Decanoic acid	$C_{10}H_{20}O_2$	172.27	31.4	0.015
Lauric acid	Dodecanoic acid	$C_{12}H_{24}O_2$	200.32	43.8	0.0055
Tridecylic acid	Tridecanoic acid	$C_{13}H_{26}O_2$	214.35	41.5	0.0033
Myristic acid	Tetradecanoic acid	$C_{14}H_{28}O_2$	228.38	54.2	0.0020
Pentadecylic acid	Pentadecanoic acid	$C_{15}H_{30}O_2$	242.40	52.3	0.0012
Palmitic acid	Hexadecanoic acid	$C_{16}H_{32}O_2$	256.43	62.5	0.00072
Margaric acid	Heptadecanoic acid	$C_{17}H_{34}O_2$	270.46	61.3	0.00042
Stearic acid	Octadecanoic acid	$C_{18}H_{36}O_2$	284.48	69.3	0.00029
Arachidic acid	Eicosanoic acid	$C_{20}H_{40}O_2$	312.54	76.5	
Phytanic acid	3,7,11,15-Tetramethylhexadecanoic acid	$C_{20}H_{40}O_2$	312.54	-65	
Behenic acid	Docosanoic acid	$C_{22}H_{44}O_2$	340.59	81.5	
Lignoceric acid	Tetracosanoic acid	$C_{24}H_{48}O_2$	368.64	87.5	
Cerotic acid	Hexacosanoic acid	$C_{26}H_{52}O_2$	396.70	88.5	
Montanic acid	Octacosanoic acid	$C_{28}H_{56}O_2$	424.75	90.9	
Monounsaturated					
Caproleic acid	9-Decenoic acid	$C_{10}H_{18}O_2$	170.25	26.5	
Palmitoleic acid	*cis*-9-Hexadecenoic acid	$C_{16}H_{30}O_2$	254.41	0.5	
Oleic acid	*cis*-9-Octadecenoic acid	$C_{18}H_{34}O_2$	282.47	13.4	
Elaidic acid	*trans*-9-Octadecenoic acid	$C_{18}H_{34}O_2$	282.47	45	
Vaccenic acid	*trans*-11-Octadecenoic acid	$C_{18}H_{34}O_2$	282.47	44	
Erucic acid	*cis*-13-Docosenoic acid	$C_{22}H_{42}O_2$	338.57	34.7	
Brassidic acid	*trans*-13-Docosenoic acid	$C_{22}H_{42}O_2$	338.57	61.9	
Nervonic acid	*cis*-15-Tetracosenoic acid	$C_{24}H_{46}O_2$	366.63	43	
Diunsaturated					
Linoleic acid	*cis,cis*-9,12-Octadecadienoic acid	$C_{18}H_{32}O_2$	280.45	–7	
Triunsaturated					
cis-Eleostearic acid	*trans,cis,trans*-9,11,13-Octadecatrienoic acid	$C_{18}H_{30}O_2$	278.44	49	
trans-Eleostearic acid	*trans,trans,trans*-9,11,13-Octadecatrienoic acid	$C_{18}H_{30}O_2$	278.44	71.5	
Linolenic acid	*cis,cis,cis*-9,12,15-Octadecatrienoic acid	$C_{18}H_{30}O_2$	278.44	–11	
Tetraunsaturated					
Arachidonic acid	5,8,11,14-Eicosatetraenoic acid, (all-*trans*)	$C_{20}H_{32}O_2$	304.47	–49.5	

CARBOHYDRATE NAMES AND SYMBOLS

The following table lists the systematic names and symbols for selected carbohydrates and some of their derivatives. The symbols for monosaccharide residues and derivatives are recommended by IUPAC for use in describing the structures of oligosaccharide chains. A more complete list can be found in the reference.

Reference

McNaught, A. D., *Pure Appl. Chem.*, 68, 1919-2008, 1996.

Common name	Symbol	Systematic name
Abequose	Abe	3,6-Dideoxy-D-*xylo*-hexose
N-Acetyl-2-deoxyneur-2-enaminic acid	Neu2en5Ac	
N-Acetylgalactosamine	GalNAc	
N-Acetylglucosamine	GlcNAc	
N-Acetylneuraminic acid	Neu5Ac	
Allose	All	*allo*-Hexose
Altrose	Alt	*altro*-Hexose
Apiose	Api	3-*C*-(Hydroxymethyl)-*glycero*-tetrose
Arabinitol	Ara-ol	Arabinitol
Arabinose	Ara	*arabino*-Pentose
Arcanose		2,6-Dideoxy-3-*C*-methyl-3-*O*-methyl-*xylo*-hexose
Ascarylose		3,6-Dideoxy-L-*arabino*-hexose
Boivinose		2,6-Dideoxy-D-gulose
Chalcose		4,6-Dideoxy-3-*O*-methyl-D-*xylo*-hexose
Cladinose		2,6-Dideoxy-3-*C*-methyl-3-*O*-methyl-L-*ribo*-hexose
Colitose		3,6-Dideoxy-L-*xylo*-hexose
Cymarose		6-Deoxy-3-*O*-methyl-*ribo*-hexose
3-Deoxy-D-*manno*-oct-2-ulosonic acid	Kdo	
2-Deoxyribose	dRib	2-Deoxy-*erythro*-pentose
2,3-Diamino-2,3-dideoxy-D-glucose	GlcN3N	
Diginose		2,6-Dideoxy-3-*O*-methyl-*lyxo*-hexose
Digitalose		6-Deoxy-3-*O*-methyl-D-galactose
Digitoxose		2,6-Dideoxy-D-*ribo*-hexose
3,4-Di-*O*-methylrhamnose	$Rha3,4Me_2$	
Ethyl glucopyranuronate	Glc*p*A6Et	
Evalose		6-Deoxy-3-*C*-methyl-D-mannose
Fructose	Fru	*arabino*-Hex-2-ulose
Fucitol	Fuc-ol	6-Deoxy-D-galactitol
Fucose	Fuc	6-Deoxygalactose
β-D-Galactopyranose 4-sulfate	β-D-Gal*p*4*S*	
Galactosamine	GalN	2-Amino-2-deoxygalactose
Galactose	Gal	*galacto*-Hexose
Glucitol	Glc-ol	
Glucosamine	GlcN	2-Amino-2-deoxyglucose
Glucose	Glc	*gluco*-Hexose
Glucuronic acid	GlcA	
N-Glycoloylneuraminic acid	Neu5Gc	
Gulose	Gul	*gulo*-Hexose
Hamamelose		2-*C*-(Hydroxymethyl)-D-ribose
Idose	Ido	*ido*-Hexose
Iduronic acid	IdoA	
Lactose	Lac	β-D-Galactopyranosyl-(1→4)-D-glucose
Lyxose	Lyx	*lyxo*-Pentose
Maltose		α-D-Glucopyranosyl-(1→4)-D-glucose
Mannose	Man	*manno*-Hexose
2-*C*-Methylxylose	Xyl2*C*Me	
Muramic acid	Mur	2-Amino-3-*O*-[(R)-1-carboxyethyl]-2-deoxy-D-glucose
Mycarose		2,6-Dideoxy-3-*C*-methyl-L-*ribo*-hexose
Mycinose		6-Deoxy-2,3-di-*O*-methyl-D-allose

Common name	Symbol	Systematic name
Neuraminic acid	Neu	5-Amino-3,5-dideoxy-D-*glycero*-D-*galacto*-non-2-ulosonic acid
Panose		α-D-Glucopyranosyl-(1→6)-α-D-glucopyranosyl-(1→ 4)-D-glucose
Paratose		3,6-Dideoxy-D-*ribo*-hexose
Primeverose		β-D-Xylopyranosyl-(1→6)-D-glucose
Psicose	Psi	*ribo*-Hex-2-ulose
Quinovose	Qui	6-Deoxyglucose
Raffinose		β-D-Fructofuranosyl-α-D-galactopyranosyl-(1→6)-α-D-glucopyranoside
Rhamnose	Rha	6-Deoxymannose
Rhodinose		2,3,6-Trideoxy-L-*threo*-hexose
Ribose	Rib	*ribo*-Pentose
Ribose 5-phosphate	Rib5*P*	
Ribulose	Ribulo (Rul)	*erythro*-Pent-2-ulose
Rutinose		α-L-Rhamnopyranosyl-(1→6)-D-glucose
Sarmentose		2,6-Dideoxy-3-*O*-methyl-D-*xylo*-hexose
Sedoheptulose		D-*altro*-Hept-2-ulose
Sorbose	Sor	*xylo*-Hex-2-ulose
Streptose		5-Deoxy-3-*C*-formyl-L-lyxose
Sucrose		β-D-Fructofuranosyl-α-D-glucopyranoside
Tagatose	Tag	*lyxo*-Hex-2-ulose
Talose	Tal	*talo*-Hexose
Turanose		α-D-Glucopyranosyl-(1→3)-D-fructose
Tyvelose	Tyv	3,6-Dideoxy-D-*arabino*-hexose
Xylose	Xyl	*xylo*-Pentose
Xylulose	Xylulo (Xul)	*threo*-Pent-2-ulose

BIOLOGICAL BUFFERS

This table of frequently used buffers gives the pK_a value at 25°C and the useful pH range of each buffer. The buffers are listed in order of increasing pH.

The table is reprinted with permission of Sigma Chemical Company, St. Louis, Mo.

Acronym	Name	Mol. wt.	pK_a	Useful pH range
MES	2-(*N*-Morpholino)ethanesulfonic acid	195.2	6.1	5.5–6.7
BIS TRIS	*Bis*(2-hydroxyethyl)iminotris(hydroxymethyl)methane	209.2	6.5	5.8–7.2
ADA	*N*-(2-Acetamido)-2-iminodiacetic acid	190.2	6.6	6.0–7.2
ACES	2-[(2-Amino-2-oxoethyl)amino]ethanesulfonic acid	182.2	6.8	6.1–7.5
PIPES	Piperazine-*N,N´-bis*(2-ethanesulfonic acid)	302.4	6.8	6.1–7.5
MOPSO	3-(*N*-Morpholino)-2-hydroxypropanesulfonic acid	225.3	6.9	6.2–7.6
BIS TRISPROPANE	1,3-*Bis*[*tris*(hydroxymethyl)methylamino]propane	282.3	6.8[a]	6.3–9.5
BES	*N,N-Bis*(2-hydroxyethyl)-2-aminoethanesulfonic acid	213.2	7.1	6.4–7.8
MOPS	3-(*N*-Morpholino)propanesulfonic acid	209.3	7.2	6.5–7.9
HEPES	*N*-(2-Hydroxyethyl)piperazine-*N´*-(2-ethanesulfonic acid)	238.3	7.5	6.8–8.2
TES	*N-Tris*(hydroxymethyl)methyl-2-aminoethanesulfonic acid	229.2	7.5	6.8–8.2
DIPSO	3-[*N,N-Bis*(2-hydroxyethyl)amino]-2-hydroxypropanesulfonic acid	243.3	7.6	7.0–8.2
TAPSO	3-[*N-Tris*(hydroxymethyl)methylamino)-2-hydroxypropanesulfonic acid	259.3	7.6	7.0–8.2
TRIZMA	Tris(hydroxymethyl)aminomethane	121.1	8.1	7.0–9.1
HEPPSO	*N*-(2-hydroxyethyl)piperazine-*N´*-(2-hydroxypropanesulfonic acid)	268.3	7.8	7.1–8.5
POPSO	Piperazine-*N,N´-bis*(2-hydroxypropanesulfonic acid)	362.4	7.8	7.2–8.5
EPPS	*N*-(2-Hydroxyethyl)piperazine-*N´*-(3-propanesulfonic acid)	252.3	8.0	7.3–8.7
TEA	Triethanolamine	149.2	7.8	7.3–8.3
TRICINE	*N-Tris*(hydroxymethyl)methylglycine	179.2	8.1	7.4–8.8
BICINE	*N,N-Bis*(2-hydroxyethyl)glycine	163.2	8.3	7.6–9.0
TAPS	*N-Tris*(hydroxymethyl)methyl-3-aminopropanesulfonic acid	243.3	8.4	7.7–9.1
AMPSO	3-[(1,1-Dimethyl-2-hydroxyethyl)amino]-2-hydroxypropanesulfonic acid	227.3	9.0	8.3–9.7
CHES	2-(*N*-Cyclohexylamino)ethanesulfonic acid	207.3	9.3	8.6–10.0
CAPSO	3-(Cyclohexylamino)-2-hydroxy-1-propanesulfonic acid	237.3	9.6	8.9–10.3
AMP	2-Amino-2-methyl-1-propanol	89.1	9.7	9.0–10.5
CAPS	3-(Cyclohexylamino)-1-propanesulfonic acid	221.3	10.4	9.7–11.1

[a] pK_a = 9.0 for the second dissociation stage.

TYPICAL pH VALUES OF BIOLOGICAL MATERIALS AND FOODS

This table gives typical pH ranges for various biological fluids and common foods. All values refer to 25°C.

Biological Materials	
Blood, human	7.35–7.45
Blood, dog	6.9–7.2
Spinal fluid, human	7.3–7.5
Saliva, human	6.5–7.5
Gastric contents, human	1.0–3.0
Duodenal contents, human	4.8–8.2
Feces, human	4.6–8.4
Urine, human	4.8–8.4
Milk, human	6.6–7.6
Bile, human	6.8–7.0

Foods	
Apples	2.9–3.3
Apricots	3.6–4.0
Asparagus	5.4–5.8
Bananas	4.5–4.7
Beans	5.0–6.0
Beers	4.0–5.0
Beets	4.9–5.5
Blackberries	3.2–3.6
Bread, white	5.0–6.0
Butter	6.1–6.4
Cabbage	5.2–5.4
Carrots	4.9–5.3
Cheese	4.8–6.4
Cherries	3.2–4.0
Cider	2.9–3.3
Corn	6.0–6.5
Crackers	6.5–8.5
Dates	6.2–6.4
Eggs, fresh white	7.6–8.0
Flour, wheat	5.5–6.5
Gooseberries	2.8–3.0
Grapefruit	3.0–3.3
Grapes	3.5–4.5
Hominy (lye)	6.8–8.0
Jams, fruit	3.5–4.0
Jellies, fruit	2.8–3.4
Lemons	2.2–2.4
Limes	1.8–2.0
Maple syrup	6.5–7.0
Milk, cows	6.3–6.6
Olives	3.6–3.8
Oranges	3.0–4.0
Oysters	6.1–6.6
Peaches	3.4–3.6
Pears	3.6–4.0
Peas	5.8–6.4
Pickles, dill	3.2–3.6
Pickles, sour	3.0–3.4
Pimento	4.6–5.2
Plums	2.8–3.0
Potatoes	5.6–6.0
Pumpkin	4.8–5.2
Raspberries	3.2–3.6
Rhubarb	3.1–3.2
Salmon	6.1–6.3
Sauerkraut	3.4–3.6
Shrimp	6.8–7.0
Soft drinks	2.0–4.0
Spinach	5.1–5.7
Squash	5.0–5.4
Strawberries	3.0–3.5
Sweet potatoes	5.3–5.6
Tomatoes	4.0–4.4
Tuna	5.9–6.1
Turnips	5.2–5.6
Vinegar	2.4–3.4
Water, drinking	6.5–8.0
Wines	2.8–3.8

CHEMICAL COMPOSITION OF THE HUMAN BODY

The elemental composition of the "standard man" of mass 70 kg is given below.

References

1. Padikal, T. N., and Fivozinsky, S. P., *Medical Physics Data Book*, *National Bureau of Standards Handbook 138*, U. S. Government Printing Office, Washington, DC, 1981.
2. Snyde, W. S., et al., *Reference Man: Anatomical, Physiological, and Metabolic Characteristics*, Pergamon, New York, 1975.

Element	Amount (g)	Percent of total body mass
Oxygen	43,000	61
Carbon	16,000	23
Hydrogen	7000	10
Nitrogen	1800	2.6
Calcium	1000	1.4
Phosphorus	780	1.1
Sulfur	140	0.20
Potassium	140	0.20
Sodium	100	0.14
Chlorine	95	0.12
Magnesium	19	0.027
Silicon	18	0.026
Iron	4.2	0.006
Fluorine	2.6	0.0037
Zinc	2.3	0.0033
Rubidium	0.32	0.00046
Strontium	0.32	0.00046
Bromine	0.20	0.00029
Lead	0.12	0.00017
Copper	0.072	0.00010
Aluminum	0.061	0.00009
Cadmium	0.050	0.00007
Boron	<0.048	0.00007
Barium	0.022	0.00003
Tin	<0.017	0.00002
Manganese	0.012	0.00002
Iodine	0.013	0.00002
Nickel	0.010	0.00001
Gold	<0.010	0.00001
Molybdenum	<0.0093	0.00001
Chromium	<0.0018	0.000003
Cesium	0.0015	0.000002
Cobalt	0.0015	0.000002
Uranium	0.00009	0.0000001
Beryllium	0.000036	
Radium	$3.1 \cdot 10^{-11}$	

STANDARD TRANSFORMED GIBBS ENERGIES OF FORMATION FOR BIOCHEMICAL REACTANTS

Robert N. Goldberg and Robert A. Alberty

This table contains values of the standard transformed Gibbs energies of formation $\Delta_f G'^\circ$ for 130 biochemical reactants. Values of $\Delta_f G'^\circ$ are given at pH 7.0, the temperature 298.15 K, and the pressure 100 kPa for three ionic strengths: I = 0, I = 0.1 mol/L and I = 0.25 mol/L. The table can be used for calculating apparent equilibrium constants K' and standard apparent reduction potentials E'° for biochemical reactions. Such a listing is more compact than tabulating the actual apparent equilibrium constants or standard apparent reduction potentials, which would require a very large number of reactant-product combinations. In the table, all reactants are in aqueous solution unless indicated otherwise.

A biochemical reactant is a sum of species. For example, ATP consists of an equilibrium mixture of the aqueous species ATP^{4-}, $HATP^{3-}$, H_2ATP^{2-}, $MgATP^{2-}$, etc. Similarly, phosphate refers to the equilibrium mixture of the aqueous species PO_4^{3-}, HPO_4^{2-}, $H_2PO_4^-$, H_3PO_4, $MgHPO_4$, etc. Biochemical reactions are written using biochemical reactants in terms of an apparent equilibrium constant K', which is distinct from the standard equilibrium constant K. This subject is discussed in an IUPAC report (see Reference 1 below).

The apparent equilibrium constant K' and the standard transformed Gibbs energy change $\Delta_r G'^\circ$ for a biochemical reaction can be calculated from the $\Delta_f G'^\circ$ values by using the relationship

$$-RT \ln K' = \Delta_r G'^\circ = \Sigma \nu'_i \Delta_f G'^\circ,$$

where the summation is over all of the biochemical reactants. The quantity ν'_i is the stoichiometric number of reactant i (ν'_i is positive for reactants on the right side of the equation and negative for reactants on the left side); R is the gas constant. As an example, the hydrolysis reaction of ATP is

$$ATP + H_2O(l) = ADP + phosphate.$$

At pH 7.00 and I = 0.25 M, $\Delta_r G'^\circ$ and K' are calculated as follows:

$$\Delta_r G'^\circ = \{-1424.70 - 1059.49 - (-2292.50 - 155.66)\} \cdot (\text{kJ mol}^{-1}) = -36.03 \text{ kJ mol}^{-1}$$

$$K' = \exp[-(-36030 \text{ J mol}^{-1})/\{(8.3145 \text{ J mol}^{-1} \text{ K}^{-1}) \cdot (298.15 \text{ K})\} = 2.05 \cdot 10^6$$

An example involving a biochemical half-cell reaction is

$$\text{acetaldehyde(aq)} + 2\ e^- = \text{ethanol(aq)}.$$

At 298.15 K, pH 7.00, and I = 0, the standard apparent reduction potential E'° can be calculated as follows

$$E'^\circ = -(1/nF) \cdot \{\Delta_f G'^\circ(\text{ethanol}) - \Delta_f G'^\circ(\text{acetaldehyde})\},$$

where n is the number of electrons in the half-cell reaction and F is the Faraday constant. Then,

$$E'^\circ = [-1/(2 \cdot 9.6485 \cdot 10^4 \text{ C mol}^{-1})] \cdot (58.10 \cdot 10^3 \text{ J mol}^{-1} - 20.83 \cdot 10^3 \text{ J mol}^{-1}) = -0.193 \text{ V}$$

References

1. Alberty, R.A., Cornish-Bowden, A., Gibson, Q.H., Goldberg, R.N., Hammes, G., Jencks, W., Tipton, K.F, Veech, R., Westerhoff, H.V., and Webb, E.C. *Pure Appl. Chem.* 66, 1641-1666, 1994.
2. Alberty, R.A., *Arch. Biochem. Biophys.*, 353, 116-130, 1998; 358, 25-39, 1998.
3. Alberty, R.A., *Thermodynamics of Biochemical Reactions,* Wiley-Interscience, New York, 2003.
4. Alberty, R.A., *BasicBiochemData2: Data and Programs for Biochemical Thermodynamics,* <http://library.wolfram.com/infocenter/MathSource/797>.

Reactant	$\Delta_f G'^\circ(I = 0)$ kJ mol^{-1}	$\Delta_f G'^\circ(I = 0.1$ M) kJ mol^{-1}	$\Delta_f G'^\circ(I = 0.25$ M) kJ mol^{-1}
Acetaldehyde	20.83	23.27	24.06
Acetate	-249.46	-248.23	-247.83
Acetone	80.04	83.71	84.90
Acetyl Coenzyme A	-60.49	-58.65	-58.06
Acetylphosphate	-1109.34	-1107.57	-1107.02
cis-Aconitate	-797.26	-800.93	-802.12
Adenine	510.45	513.51	514.50
Adenosine	324.93	332.89	335.46
Adenosine 5'-diphosphate (ADP)	-1428.93	-1425.55	-1424.70
Adenosine 5'-monophosphate (AMP)	-562.04	-556.53	-554.83
Adenosine 5'-triphosphate (ATP)	-2292.61	-2292.16	-2292.50
D-Alanine	-91.31	-87.02	-85.64
Ammonia	80.50	82.34	82.93
D-Arabinose	-342.67	-336.55	-334.57
L-Asparagine	-206.28	-201.38	-199.80
L-Aspartate	-456.14	-453.08	-452.09
1,3-Biphosphoglycerate	-2202.06	-2205.69	-2207.30
Butanoate	-72.94	-69.26	-68.08
1-Butanol	227.72	233.84	235.82

Reactant	$\Delta_f G'^\circ(I = 0)$ kJ mol^{-1}	$\Delta_f G'^\circ(I = 0.1\ M)$ kJ mol^{-1}	$\Delta_f G'^\circ(I = 0.25\ M)$ kJ mol^{-1}
Citrate	-963.46	-965.49	-966.23
Isocitrate	-956.82	-958.84	-959.58
Coenzyme A (CoA)	-7.98	-7.43	-7.26
CO(aq)	-119.90	-119.90	-119.90
CO(g)	-137.17	-137.17	-137.17
CO_2(aq)[total]	-547.33	-547.15	-547.10
CO_2(g)	-394.36	-394.36	-394.36
Creatine	100.41	105.92	107.69
Creatinine	256.55	260.84	262.22
L-Cysteine	-59.23	-55.01	-53.65
L-Cystine	-187.03	-179.69	-177.32
Cytochrome c [oxidized]	0.00	-5.51	-7.29
Cytochrome c [reduced]	-24.51	-26.96	-27.75
Dihydroxyacetone phosphate	-1096.60	-1095.91	-1095.70
Ethanol	58.10	61.77	62.96
Ethyl acetate	-18.00	-13.10	-11.52
Ferredoxin [oxidized]	0.00	-0.61	-0.81
Ferredoxin [reduced]	38.07	38.07	38.07
Flavine adenine dinucleotide (FAD) [oxidized]	1238.65	1255.17	1260.51
Flavine adenine dinucleotide (FAD) [reduced]	1279.68	1297.43	1303.16
Flavin adenine dinucleotide-enzyme (FADenz) [oxidized]	1238.65	1255.17	1260.51
Flavin adenine dinucleotide-enzyme (FADenz) [reduced]	1229.96	1247.71	1253.44
Flavin mononucleotide (FMN) [oxidized]	759.17	768.35	771.32
Flavin mononucleotide (FMN) [reduced]	800.20	810.61	813.97
Formate	-311.04	-311.04	-311.04
D-Fructose	-436.03	-428.69	-426.32
D-Fructose 1,6-diphosphate	-2202.84	-2205.66	-2206.78
D-Fructose 6-phosphate	-1321.71	-1317.16	-1315.74
Fumarate	-521.97	-523.19	-523.58
D-Galactose	-429.45	-422.11	-419.74
α-*D*-Galactose 1-phosphate	-1317.50	-1313.01	-1311.60
D-Glucose	-436.42	-429.08	-426.71
α-*D*-Glucose 1-phosphate	-1318.03	-1313.34	-1311.89
D-Glucose 6-phosphate	-1325.00	-1320.37	-1318.92
Glutamate	-377.82	-373.54	-372.16
D-Glutamine	-128.46	-122.34	-120.36
Glutathione [oxidized]	1198.69	1214.60	1219.74
Glutathione [reduced]	625.75	634.76	637.62
Glutathione-coenzyme A	563.49	572.06	574.83
D-Glyceraldehyde 3-phosphate	-1088.94	-1088.25	-1088.04
Glycerol	-177.83	-172.93	-171.35
sn-Glycerol 3-phosphate	-1080.22	-1077.83	-1077.13
Glycine	-180.13	-177.07	-176.08
Glycolate	-411.08	-409.86	-409.46
Glycylglycine	-200.55	-195.65	-194.07
Glyoxylate	-428.64	-428.64	-428.64
H_2(aq)	97.51	98.74	99.13
H_2(g)	79.91	81.14	81.53
H_2O(l)	-157.28	-156.05	-155.66
H_2O_2(aq)	-54.12	-52.89	-52.50
3-Hydroxypropanoate	-318.62	-316.17	-315.38
Hypoxanthine	249.33	251.77	252.56
Indole	503.49	507.78	509.16
Lactate	-316.94	-314.49	-313.70
Lactose	-688.29	-674.83	-670.48
L-Leucine	167.18	175.14	177.71
L-Isoleucine	175.53	183.49	186.06
D-Lyxose	-349.58	-343.46	-341.48
Malate	-682.88	-682.85	-682.85
Maltose	-695.65	-682.19	-677.84

Reactant	$\Delta_f G'^\circ(I = 0)$ kJ mol^{-1}	$\Delta_f G'^\circ(I = 0.1\ M)$ kJ mol^{-1}	$\Delta_f G'^\circ(I = 0.25\ M)$ kJ mol^{-1}
D-Mannitol	-383.22	-374.65	-371.89
Mannose	-430.52	-423.18	-420.81
Methane(aq)	125.50	127.94	128.73
Methane(g)	109.11	111.55	112.34
Methanol	-15.48	-13.04	-12.25
L-Methionine	-63.40	-56.67	-54.49
N_2(aq)	18.70	18.70	18.70
N_2(g)	0.00	0.00	0.00
Nicotinamide Adenine Dinucleotide (NAD) [oxidized]	1038.86	1054.17	1059.11
Nicotinamide Adenine Dinucleotide (NAD) [reduced]	1101.47	1115.55	1120.09
Nicotinamide Adenine Dinucleotide Phosphate (NADP) [oxidized]	163.73	173.52	176.68
Nicotinamide Adenine Dinucleotide Phosphate (NADP) [reduced]	229.67	235.79	237.77
O_2(aq)	16.40	16.40	16.40
O_2(g)	0.00	0.00	0.00
Oxalate	-673.90	-676.35	-677.14
Oxaloacetate	-713.38	-714.60	-715.00
Oxalosuccinate	-979.05	-979.05	-979.05
2-Oxoglutarate	-633.58	-633.58	-633.58
Palmitate	979.25	997.61	1003.54
L-Phenylalanine	232.42	239.15	241.33
Phosphate	-1058.56	-1059.17	-1059.49
2-Phospho-*D*-glycerate	-1340.72	-1341.32	-1341.79
3-Phospho-*D*-glycerate	-1346.38	-1347.19	-1347.73
Phospho*enol*pyruvate	-1185.46	-1188.53	-1189.73
1-Propanol	143.84	148.74	150.32
2-Propanol	134.42	139.32	140.90
Pyrophosphate	-1934.95	-1939.13	-1940.66
Pyruvate	-352.40	-351.18	-350.78
Retinal	1118.78	1135.91	1141.45
Retinol	1170.78	1189.14	1195.07
Ribose	-339.23	-333.11	-331.13
Ribose 1-phosphate	-1215.87	-1212.24	-1211.14
Ribose 5-phosphate	-1223.95	-1220.32	-1219.22
Ribulose	-336.38	-330.26	-328.28
L-Serine	-231.18	-226.89	-225.51
Sorbose	-432.47	-425.13	-422.76
Succinate	-530.72	-530.65	-530.64
Succinyl Coenzyme A	-349.90	-348.06	-347.47
Sucrose	-685.66	-672.20	-667.85
Thioredoxin [oxidized]	0.00	0.00	0.00
Thioredoxin [reduced]	54.32	55.41	55.74
L-Tryptophan	364.78	372.12	374.49
L-Tyrosine	68.82	75.55	77.73
Ubiquinone [oxidized]	3596.07	3651.15	3668.94
Ubiquinone [reduced]	3586.06	3642.37	3660.55
Urate	-206.03	-204.81	-204.41
Urea	-42.97	-40.53	-39.74
Uric acid	-197.07	-194.63	-193.84
L-Valine	80.87	87.60	89.78
D-Xylose	-350.93	-344.81	-342.83
D-Xylulose	-346.59	-340.47	-338.49

THERMODYNAMIC QUANTITIES FOR THE IONIZATION REACTIONS OF BUFFERS IN WATER

Robert N. Goldberg, Nand Kishore, and Rebecca M. Lennen

This table contains selected values for the pK, standard molar enthalpy of reaction $\Delta_r H°$, and standard molar heat-capacity change $\Delta_r C°_p$ for the ionization reactions of 64 buffers many of which are relevant to biochemistry and to biology.[1] The values pertain to the temperature T = 298.15 K and the pressure p = 0.1 MPa. The standard state is the hypothetical ideal solution of unit molality. These data permit one to calculate values of the pK and of $\Delta_r H°$ at temperatures in the vicinity $\{T \approx (274\ \text{K to}\ 350\ \text{K})\}$ of the reference temperature θ = 298.15 K by using the following equations[2]

$$\Delta_r G°_T = -RT \ln K_T = \ln(10)\cdot RT\cdot \mathrm{p}K_T\ , \qquad (1)$$

$$R\ln K_T = -(\Delta_r G°_\theta/\theta) + \Delta_r H°_\theta\{(1/\theta) - (1/T)\} + \Delta_r C°_{p\theta}\{(\theta/T) - 1 + \ln(T/\theta)\}, \qquad (2)$$

$$\Delta_r H°_T = \Delta_r H°_\theta + \Delta_r C°_{p\theta}(T - \theta). \qquad (3)$$

Here, $\Delta_r G°$ is the standard molar Gibbs energy change and K is the equilibrium constant for a reaction; R is the gas constant (8.314 472 J K^{-1} mol^{-1}). The subscripts T and θ denote the temperature to which a quantity pertains, the subscript p denotes constant pressure, and the subscript r denotes that the quantity refers to a reaction. Combination of equations (1) and (2) yields the following equation that gives pK as a function of temperature:

$$\mathrm{p}K_T = -\{R\cdot\ln(10)\}^{-1}[-\{\ln(10)\cdot RT\cdot \mathrm{p}K_\theta/\theta\} + \Delta_r H°_\theta\{(1/\theta) - (1/T)\} + \Delta_r C°_{p\theta}\{(\theta/T) - 1 + \ln(T/\theta)\}]. \qquad (4)$$

The above equations neglect higher order terms that involve temperature derivatives of $\Delta_r C°_p$. Also, it is important to recognize that the values of pK and $\Delta_r H°$ effectively pertain to ionic strength I = 0. However, the values of pK and $\Delta_r H°$ are almost always dependent on the ionic strength and the actual composition of the solution. These issues are discussed in Reference 1 which also gives an approximate method for making appropriate corrections.

References

1. Goldberg, R. N., Kishore, N., and Lennen, R. M., "Thermodynamic Quantities for the Ionization Reactions of Buffers," *J. Phys. Chem. Ref. Data*, in press.
2. Clarke, E. C. W., and Glew, D. N., *Trans. Faraday Soc.*, 62, 539-547, 1966.

Selected Values of Thermodynamic Quantities for the Ionization Reactions of Buffers in Water at T = 298.15 K and p = 0.1 MPa

			$\Delta_r H°$	$\Delta_r C°_p$
Buffer	**Reaction**	**pK**	**kJ mol^{-1}**	**J K^{-1} mol^{-1}**
ACES	$HL^{\pm} = H^+ + L^-$, ($HL = C_4H_{10}N_2O_4S$)	6.847	30.43	−49
Acetate	$HL = H^+ + L^-$, ($HL = C_2H_4O_2$)	4.756	−0.41	−142
ADA	$H_3L^+ = H^+ + H_2L^{\pm}$, ($H_2L = C_6H_{10}N_2O_5$)	1.59		
	$H_2L^{\pm} = H^+ + HL^-$	2.48	16.7	
	$HL^- = H^+ + L^{2-}$	6.844	12.23	−144
2-Amino-2-methyl-1,3-propanediol	$HL^+ = H^+ + L$, ($L = C_4H_{11}NO_2$)	8.801	49.85	−44
2-Amino-2-methyl-1-propanol	$HL^+ = H^+ + L$, ($L = C_4H_{11}NO$)	9.694	54.05	≈−21
3-Amino-1-propanesulfonic acid	$HL = H^+ + L^-$, ($HL = C_3H_9NO_3S$)	10.2		
Ammonia	$NH_4^+ = H^+ + NH_3$	9.245	51.95	8
AMPSO	$HL^{\pm} = H^+ + L^-$, ($HL = C_7H_{17}NO_5S$)	9.138	43.19	−61
Arsenate	$H_3AsO_4 = H^+ + H_2AsO_4^-$	2.31	−7.8	
	$H_2AsO_4^- = H^+ + HAsO_4^{2-}$	7.05	1.7	
	$HAsO_4^{2-} = H^+ + AsO_4^{3-}$	11.9	15.9	
Barbital	$H_2L = H^+ + HL^-$, ($H_2L = C_8H_{12}N_2O_3$)	7.980	24.27	−135
	$HL^- = H^+ + L^{2-}$	12.8		
BES	$HL^{\pm} = H^+ + L^-$, ($HL = C_6H_{15}NO_5S$)	7.187	24.25	−2
Bicine	$H_2L^+ = H^+ + HL^{\pm}$, ($HL = C_6H_{13}NO_4$)	2.0		
	$HL^{\pm} = H^+ + L^-$	8.334	26.34	0
Bis-tris	$H_3L^+ = H^+ + H_2L^{\pm}$, ($H_2L = C_8H_{19}NO_5$)	6.484	28.4	27
Bis-tris propane	$H_2L^{2+} = H^+ + HL^+$, ($L = C_{11}H_{26}N_2O_6$)	6.65		
	$HL^+ = H^+ + L$	9.10		
Borate	$H_3BO_3 = H^+ + H_2BO_3^-$	9.237	13.8	≈−240
Cacodylate	$H_2L^+ = H^+ + HL$, ($HL = C_2H_6AsO_2$)	1.78	−3.5	
	$HL = H^+ + L^-$	6.28	−3.0	−86
CAPS	$HL^{\pm} = H^+ + L^-$, ($HL = C_9H_{19}NO_3S$)	10.499	48.1	57
CAPSO	$HL^{\pm} = H^+ + L^-$, ($HL = C_9H_{19}NO_4S$)	9.825	46.67	21
Carbonate	$H_2CO_3 = H^+ + HCO_3^-$	6.351	9.15	−371
	$HCO_3^- = H^+ + CO_3^{2-}$	10.329	14.70	−249
CHES	$HL^{\pm} = H^+ + L^-$, ($HL = C_8H_{17}NO_3S$)	9.394	39.55	9

Buffer	Reaction	pK	$\Delta_r H^\circ$ kJ mol^{-1}	$\Delta_r C_p^\circ$ J K^{-1} mol^{-1}
Citrate	$H_3L = H^+ + H_2L^-$, ($H_3L = C_6H_8O_7$)	3.128	4.07	−131
	$H_2L^- = H^+ + HL^{2-}$	4.761	2.23	−178
	$HL^{2-} = H^+ + L^{3-}$	6.396	−3.38	−254
L-Cysteine	$H_3L^+ = H^+ + H_2L$, ($H_2L = C_3H_7NO_2S$)	1.71	≈−0.6	
	$H_2L = H^+ + HL^-$	8.36	36.1	≈−66
	$HL^- = H^+ + L^{2-}$	10.75	34.1	≈−204
Diethanolamine	$HL^+ = H^+ + L$, ($L = C_4H_{11}NO_2$)	8.883	42.08	36
Diglycolate	$H_2L = H^+ + HL^-$, ($H_2L = C_4H_6O_5$)	3.05	−0.1	≈−142
	$HL^- = H^+ + L^{2-}$	4.37	−7.2	≈−138
3,3-Dimethylglutarate	$H_2L = H^+ + HL^-$, ($H_2L = C_7H_{12}O_4$)	3.70		
	$HL^- = H^+ + L^{2-}$	6.34		
DIPSO	$HL^\pm = H^+ + L^-$, ($HL = C_7H_{17}NO_6S$)	7.576	30.18	42
Ethanolamine	$HL^+ = H^+ + L$, ($L = C_2H_7NO$)	9.498	50.52	26
N-Ethylmorpholine	$HL^+ = H^+ + L$, ($L = C_6H_{13}NO$)	7.77	27.4	
Glycerol 2-phosphate	$H_2L = H^+ + HL^-$, ($H_2L = C_3H_9NO_6P$)	1.329	−12.2	−330
	$HL^- = H^+ + L^{2-}$	6.650	−1.85	−212
Glycine	$H_2L^+ = H^+ + HL^\pm$, ($HL = C_2H_5NO_2$)	2.351	4.00	−139
	$HL^\pm = H^+ + L^-$	9.780	44.2	−57
Glycine amide	$HL^+ = H^+ + L$, ($L = C_2H_6N_2O$)	8.04	42.9	
Glycylglycine	$H_2L^+ = H^+ + HL^\pm$, ($HL = C_4H_8N_2O_3$)	3.140	0.11	−128
	$HL^\pm = H^+ + L^-$	8.265	43.4	−16
Glycylglycylglycine	$H_2L^+ = H^+ + HL^\pm$, ($HL = C_6H_{11}N_3O_4$)	3.224	0.84	
	$HL^\pm = H^+ + L^-$	8.090	41.7	
HEPES	$H_2L^+ = H^+ + HL^\pm$, ($HL = C_8H_{18}N_2O_4S$)	≈3.0		
	$HL^\pm = H^+ + L^-$	7.564	20.4	47
HEPPS	$HL^\pm = H^+ + L^-$, ($HL = C_6H_{20}N_2O_4S$)	7.957	21.3	48
HEPPSO	$HL^\pm = H^+ + L^-$, ($HL = C_9H_{20}N_2O_5S$)	8.042	23.70	47
L-Histidine	$H_3L^{2+} = H^+ + H_2L^+$, ($HL = C_6H_9N_3O_2$)	1.5_4	3.6	
	$H_2L^+ = H^+ + HL$	6.07	29.5	176
	$HL = H^+ + L^-$	9.34	43.8	−233
Hydrazine	$H_2L^{2+} = H^+ + HL^+$, ($L = H_4N_2$)	−0.99	38.1	
	$HL^+ = H^+ + L$	8.02	41.7	
Imidazole	$HL^+ = H^+ + L$, ($L = C_3H_4N_2$)	6.993	36.64	−9
Maleate	$H_2L = H^+ + HL^-$, ($H_2L = C_4H_4O_4$)	1.92	1.1	≈−21
	$HL^- = H^+ + L^{2-}$	6.27	−3.6	≈−31
2-Mercaptoethanol	$HL = H^+ + L^-$, ($HL = C_2H_6OS$)	9.7_5	26.2	
MES	$HL^\pm = H^+ + L^-$, ($HL = C_6H_{13}NO_4S$)	6.270	14.8	5
Methylamine	$HL^+ = H^+ + L$, ($L = CH_5N$)	10.645	55.34	33
2-Methylimidazole	$HL^+ = H^+ + L$, ($L = C_4H_6N_2$)	8.0_1	36.8	
MOPS	$HL^\pm = H^+ + L^-$, ($HL = C_7H_{15}NO_4S$)	7.184	21.1	25
MOPSO	$H_2L^+ = H^+ + HL^\pm$, ($HL = C_7H_{15}NO_5S$)	0.060		
	$HL^\pm = H^+ + L^-$	6.90	25.0	≈38
Oxalate	$H_2L = H^+ + HL^-$, ($H_2L = C_2H_2O_4$)	1.27	−3.9	≈−231
	$HL^- = H^+ + L^{2-}$	4.266	7.00	−231
Phosphate	$H_3PO_4 = H^+ + H_2PO_4^-$	2.148	−8.0	−141
	$H_2PO_4^- = H^+ + HPO_4^{2-}$	7.198	3.6	−230
	$HPO_4^{2-} = H^+ + PO_4^{3-}$	12.35	16.0	−242
Phthalate	$H_2L = H^+ + HL^-$, ($H_2L = C_8H_6O_4$)	2.950	−2.70	−91
	$HL^- = H^+ + L^{2-}$	5.408	−2.17	−295
Piperazine	$H_2L^{2+} = H^+ + HL^+$, ($L = C_4H_{10}N_2$)	5.333	31.11	86
	$HL^+ = H^+ + L$	9.731	42.89	75
PIPES	$HL^\pm = H^+ + L^-$, ($HL = C_8H_{18}N_2O_6S_2$)	7.141	11.2	22
POPSO	$HL^\pm = H^+ + L^-$, ($HL = C_{10}H_{22}N_2O_8S_2$)	≈8.0		
Pyrophosphate	$H_4P_2O_7 = H^+ + H_3P_2O_7^-$	0.83	−9.2	≈−90
	$H_3P_2O_7^- = H^+ + H_2P_2O_7^{2-}$	2.26	−5.0	≈−130
	$H_2P_2O_7^{2-} = H^+ + HP_2O_7^{3-}$	6.72	0.5	−136
	$HP_2O_7^{3-} = H^+ + P_2O_7^{4-}$	9.46	1.4	−141
Succinate	$H_2L = H^+ + HL^-$, ($H_2L = C_4H_6O_4$)	4.207	3.0	−121
	$HL^- = H^+ + L^{2-}$	5.636	−0.5	−217
Sulfate	$HSO_4^- = H^+ + SO_4^{2-}$	1.987	−22.4	−258

Buffer	Reaction	p*K*	$\Delta_r H^\circ$ kJ mol^{-1}	$\Delta_r C_p^\circ$ J K^{-1} mol^{-1}
Sulfite	$H_2SO_3 = H^+ + HSO_3^-$	1.857	−17.80	−272
	$HSO_3^- = H^+ + SO_3^{2-}$	7.172	−3.65	−262
TAPS	$HL^\pm = H^+ + L^-$, (HL = $C_7H_{17}NO_6S$)	8.44	40.4	15
TAPSO	$HL^\pm = H^+ + L^-$, (HL = $C_7H_{17}NO_7S$)	7.635	39.09	−16
L(+)-Tartaric acid	$H_2L = H^+ + HL^-$, (H_2L = $C_4H_6O_6$)	3.036	3.19	−147
	$HL^- = H^+ + L^{2-}$	4.366	0.93	−218
TES	$HL^\pm = H^+ + L^-$, (HL = $C_6H_{15}NO_6S$)	7.550	32.13	0
Tricine	$H_2L^+ = H^+ + HL^\pm$, (HL = $C_6H_{13}NO_5$)	2.023	5.85	−196
	$HL^\pm = H^+ + L^-$	8.135	31.37	−53
Triethanolamine	$HL^+ = H^+ + L$, (L = $C_6H_{15}NO_3$)	7.762	33.6	50
Triethylamine	$HL^+ = H^+ + L$, (L = $C_6H_{15}N$)	10.72	43.13	151
Tris	$HL^+ = H^+ + L$, (L = $C_4H_{11}NO_3$)	8.072	47.45	−59

PREPARATION OF SPECIAL ANALYTICAL REAGENTS

Aluminon (qualitative test for aluminum). Aluminon is a trade name for the ammonium salt of aurintricarboxylic acid. Dissolve 1 g of the salt in 1 L of distilled water. Shake the solution well to insure thorough mixing.

Bang's reagent (for glucose estimation). Dissolve 100 g of K_2CO_3, 66 g of KCl and 160 g of $KHCO_3$ in the order given in about 700 mL of water at 30°C. Add 4.4 g of $CuSO_4$ and dilute to 1 L after the CO_2 is evolved. This solution should be shaken only in such a manner as not to allow entry of air. After 24 hours 300 mL are diluted to 1 L with saturated KCl solution, shaken gently and used after 24 hours; 50 mL is equivalent to 10 mg glucose.

Barfoed's reagent (test for glucose). See Cupric acetate.

Baudisch's reagent. See Cupferron.

Benedict's solution (qualitative reagent for glucose). With the aid of heat, dissolve 173 g of sodium citrate and 100 g of Na_2CO_3 in 800 mL of water. Filter, if necessary, and dilute to 850 mL. Dissolve 17.3 g of $CuSO_4 \cdot 5H_2O$ in 100 mL of water. Pour the latter solution, with constant stirring, into the carbonate-citrate solution, and dilute to 1 L.

Benzidine hydrochloride solution (for sulfite determination). Make a paste of 8 g of benzidine hydrochloride ($C_{12}H_8(NH_3)_2 \cdot 2HCl$) and 20 mL of water, add 20 mL of HCl (sp. gr. 1.12) and dilute to 1 L with water. Each mL of this solution is equivalent to 0.00357 g of H_2SO_4.

Bertrand's reagent (glucose estimation). Consists of the following solutions:

1. Dissolve 200 g of Rochelle salt and 150 g of NaOH in sufficient water to make 1 L of solution.
2. Dissolve 40 g of $CuSO_4$ in enough water to make 1 L of solution.
3. Dissolve 50 g of $Fe_2(SO_4)_3$ and 200 g of H_2SO_4 (sp. gr. 1.84) in sufficient water to make 1 L of solution.
4. Dissolve 5 g of $KMnO_4$ in sufficient water to make 1 L of solution.

Bial's reagent (for pentose). Dissolve 1 g of orcinol (5-methyl-1,3-benzenediol) in 500 mL of 30% HCl to which 30 drops of a 10% solution of $FeCl_3$ has been added.

Boutron — Boudet soap solution:

1. Dissolve 100 g of pure castile soap in about 2.5 L of 56% ethanol.
2. Dissolve 0.59 g of $Ba(NO_3)_2$ in 1 L of water.

Adjust the castile soap solution so that 2.4 mL of it will give a permanent lather with 40 mL of solution (b). When adjusted, 2.4 mL of soap solution is equivalent to 220 parts per million of hardness (as $CaCO_3$) for a 40 mL sample. See also Soap solution.

Brucke's reagent (protein precipitation). See Potassium iodide-mercuric iodide.

Clarke's soap solution (estimation of hardness in water).

1. Dissolve 100 g of pure powdered castile soap in 1 L of 80% ethanol and allow to stand over night.
2. Prepare a solution of $CaCl_2$ by dissolving 0.5 g of $CaCO_3$ in HCl (sp. gr. 1.19), neutralize with NH_4OH and make slightly alkaline to litmus, and dilute to 500 mL. One mL is equivalent to 1 mg of $CaCO_3$.

Titrate (1) against (2) and dilute (1) with 80% ethanol until 1 mL of the resulting solution is equivalent to 1 mL of (2) after making allowance for the lather factor (the amount of standard soap solution required to produce a permanent lather in 50 mL of distilled water). One mL of the adjusted solution after subtracting the lather factor is equivalent to 1 mg of $CaCO_3$. See also Soap solution.

Cobalticyanide paper (Rinnmann's test for Zn). Dissolve 4 g of $K_3Co(CN)_6$ and 1 g of $KClO_3$ in 100 mL of water. Soak filter paper in solution and dry at 100°C. Apply drop of zinc solution and burn in an evaporating dish. A green disk is obtained if zinc is present.

Cochineal. Extract 1 g of cochineal for 4 days with 20 mL of alcohol and 60 mL of distilled water. Filter.

Congo red. Dissolve 0.5 g of congo red in 90 mL of distilled water and 10 mL of alcohol.

Cupferron (Baudisch's reagent for iron analysis). Dissolve 6 g of the ammonium salt of *N*-hydroxy-*N*-nitrosoaniline (cupferron) in 100 mL of H_2O. Reagent good for 1 week only and must be kept in the dark.

Cupric acetate (Barfoed's reagent for reducing monosaccharides). Dissolve 66 g of cupric acetate and 10 mL of glacial acetic acid in water and dilute to 1 L.

Cupric oxide, ammoniacal; Schweitzer's reagent (dissolves cotton, linen, and silk, but not wool).

1. Dissolve 5 g of cupric sulfate in 100 mL of boiling water, and add sodium hydroxide until precipitation is complete. Wash the precipitate well, and dissolve it in a minimum quantity of ammonium hydroxide.
2. Bubble a slow stream of air through 300 mL of strong ammonium hydroxide containing 50 g of fine copper turnings. Continue for 1 hour.

Cupric sulfate in glycerin-potassium hydroxide (reagent for silk). Dissolve 10 g of cupric sulfate, $CuSO_4 \cdot 5H_2O$, in 100 mL of water and add 5 g of glycerol. Add KOH solution slowly until a deep blue solution is obtained.

Cupron (precipitates copper). Dissolve 5 g of benzoinoxime in 100 mL of 95% ethanol.

Cuprous chloride, acidic (reagent for CO in gas analysis).

1. Cover the bottom of a 2-L flask with a layer of cupric oxide about 0.5 inch deep, suspend a coil of copper wire so as to reach from the bottom to the top of the solution, and fill the flask with hydrochloric acid (sp. gr. 1.10). Shake occasionally. When the solution becomes nearly colorless, transfer to reagent bottles, which should also contain copper wire. The stock bottle may be refilled with dilute hydrochloric acid until either the cupric oxide or the copper wire is used up. Copper sulfate may be substituted for copper oxide in the above procedure.
2. Dissolve 340 g of $CuCl_2 \cdot 2H_2O$ in 600 mL of conc. HCl and reduce the cupric chloride by adding 190 mL of a saturated solution of stannous chloride or until the solution is colorless. The stannous chloride is prepared by treating 300 g of metallic tin in a 500 mL flask with conc. HCl until no more tin goes into solution.
3. (Winkler method). Add a mixture of 86 g of CuO and 17 g of finely divided metallic Cu, made by the reduction of CuO with hydrogen, to a solution of HCl, made by dilut-

ing 650 mL of conc. HCl with 325 mL of water. After the mixture has been added slowly and with frequent stirring, a spiral of copper wire is suspended in the bottle, reaching all the way to the bottom. Shake occasionally, and when the solution becomes colorless, it is ready for use.

Cuprous chloride, ammoniacal (reagent for CO in gas analysis).

1. The acid solution of cuprous chloride as prepared above is neutralized with ammonium hydroxide until an ammonia odor persists. An excess of metallic copper must be kept in the solution.
2. Pour 800 mL of acidic cuprous chloride, prepared by the Winkler method, into about 4 L of water. Transfer the precipitate to a 250 mL graduate. After several hours, siphon off the liquid above the 50 mL mark and refill with 7.5% NH_4OH solution which may be prepared by diluting 50 mL of conc. NH_4OH with 150 mL of water. The solution is well shaken and allowed to stand for several hours. It should have a faint odor of ammonia.

Dichlorofluorescein indicator. Dissolve 1 g in 1 L of 70% alcohol or 1 g of the sodium salt in 1 L of water.

Dimethylglyoxime, 0.01 N. Dissolve 0.6 g of dimethylglyoxime (2,3-butanedione oxime) in 500 mL of 95% ethanol. This is an especially sensitive test for nickel, a very definite crimson color being produced.

Diphenylamine (reagent for rayon). Dissolve 0.2 g in 100 mL of concentrated sulfuric acid.

Diphenylamine sulfonate (for titration of iron with $K_2Cr_2O_7$). Dissolve 0.32 g of the barium salt of diphenylamine sulfonic acid in 100 mL of water, add 0.5 g of sodium sulfate and filter off the precipitate of $BaSO_4$.

Diphenylcarbazide. Dissolve 0.2 g of diphenylcarbazide in 10 mL of glacial acetic acid and dilute to 100 mL with 95% ethanol.

Esbach's reagent (estimation of protein). To a water solution of 10 g of picric acid and 20 g of citric acid, add sufficient water to make 1 L of solution.

Eschka's compound. Two parts of calcined ("light") magnesia are thoroughly mixed with 1 part of anhydrous sodium carbonate.

Fehling's solution (reagent for reducing sugars.)

1. Copper sulfate solution. Dissolve 34.66 g of $CuSO_4 \cdot 5H_2O$ in water and dilute to 500 mL.
2. Alkaline tartrate solution. Dissolve 173 g of potassium sodium tartrate (Rochelle salt, $KNaC_4H_4O_6 \cdot 4H_2O$) and 50 g of NaOH in water and dilute when cold to 500 mL.

Mix equal volumes of the two solutions at the time of using.

Ferric-alum indicator. Dissolve 140 g of ferric ammonium sulfate crystals in 400 mL of hot water. When cool, filter, and make up to a volume of 500 mL with dilute nitric acid.

Folin's mixture (for uric acid). To 650 mL of water add 500 g of $(NH_4)_2SO_4$, 5 g of uranium acetate, and 6 g of glacial acetic acid. Dilute to 1 L.

Formaldehyde — sulfuric acid (Marquis' reagent for alkaloids). Add 10 mL of formaldehyde solution to 50 mL of sulfuric acid.

Froehde's reagent. See Sulfomolybdic acid.

Fuchsin (reagent for linen). Dissolve 1 g of fuchsin in 100 mL of alcohol.

Fuchsin — sulfurous acid (Schiff's reagent for aldehydes). Dissolve 0.5 g of fuchsin and 9 g of sodium bisulfite in 500 mL of water, and add 10 mL of HCl. Keep in well-stoppered bottles and protect from light.

Gunzberg's reagent (detection of HCl in gastric juice). Prepare as needed a solution containing 4 g of phloroglucinol (1,3,5-benzenetriol) and 2 g of vanillin in 100 mL of absolute ethanol.

Hager's reagent. See Picric acid.

Hanus solution (for iodine number). Dissolve 13.2 g of resublimed iodine in 1 L of glacial acetic acid which will pass the dichromate test for reducible matter. Add sufficient bromine to double the halogen content, determined by titration (3 mL is about the proper amount). The iodine may be dissolved by the aid of heat, but the solution should be cold when the bromine is added.

Iodine, tincture of. To 50 mL of water add 70 g of I_2 and 50 g of KI. Dilute to 1 L with alcohol.

Iodo-potassium iodide (Wagner's reagent for alkaloids). Dissolve 2 g of iodine and 6 g of KI in 100 mL of water.

Litmus (indicator). Extract litmus powder three times with boiling alcohol, each treatment consuming an hour. Reject the alcoholic extract. Treat residue with an equal weight of cold water and filter; then exhaust with five times its weight of boiling water, cool and filter. Combine the aqueous extracts.

Magnesia mixture (reagent for phosphates and arsenates). Dissolve 55 g of magnesium chloride and 105 g of ammonium chloride in water, barely acidify with hydrochloric acid, and dilute to 1 L. The ammonium hydroxide may be omitted until just previous to use. The reagent, if completely mixed and stored for any period of time, becomes turbid.

Magnesium uranyl acetate. Dissolve 100 g of $UO_2(C_2H_3O_2)_2 \cdot 2H_2O$ in 60 mL of glacial acetic acid and dilute to 500 mL. Dissolve 330 g of $Mg(C_2H_3O_2)_2 \cdot 4H_2O$ in 60 mL of glacial acetic acid and dilute to 200 mL. Heat solutions to the boiling point until clear, pour the magnesium solution into the uranyl solution, cool and dilute to 1 L. Let stand over night and filter if necessary.

Marme's reagent. See Potassium-cadmium iodide.

Marquis' reagent. See Formaldehyde-sulfuric acid.

Mayer's reagent (white precipitate with most alkaloids in slightly acid solutions). Dissolve 1.358 g of $HgCl_2$ in 60 mL of water and pour into a solution of 5 g of KI in 10 mL of H_2O. Add sufficient water to make 100 mL.

Methyl orange indicator. Dissolve 1 g of methyl orange in 1 L of water. Filter, if necessary.

Methyl orange, modified. Dissolve 2 g of methyl orange and 2.8 g of xylene cyanole FF in 1 L of 50% alcohol.

Methyl red indicator. Dissolve 1 g of methyl red in 600 mL of alcohol and dilute with 400 mL of water.

Methyl red, modified. Dissolve 0.50 g of methyl red and 1.25 g of xylene cyanole FF in 1 L of 90% alcohol. Or, dissolve 1.25 g of methyl red and 0.825 g of methylene blue in 1 L of 90% alcohol.

Millon's reagent (for albumins and phenols). Dissolve 1 part of mercury in 1 part of cold fuming nitric acid. Dilute with twice the volume of water and decant the clear solution after several hours.

Molisch's reagent. See 1-Naphthol.

1-Naphthol (Molisch's reagent for wool). Dissolve 15 g of 1-naphthol in 100 mL of alcohol or chloroform.

Nessler's reagent (for ammonia). Dissolve 50 g of KI in the smallest possible quantity of cold water (50 mL). Add a saturated solution of mercuric chloride (about 22 g in 350 mL of water will be needed) until an excess is indicated by the formation of a precipitate. Then add 200 mL of 5 N NaOH and dilute to 1 L. Let settle, and draw off the clear liquid.

Nickel oxide, ammoniacal (reagent for silk). Dissolve 5 g of nickel sulfate in 100 mL of water, and add sodium hydroxide solution until nickel hydroxide is completely precipitated. Wash the precipitate well and dissolve in 25 mL of concentrated ammonium hydroxide and 25 mL of water.

Nitron (detection of nitrate radical). Dissolve 10 g of nitron (1,4-diphenyl-3-(phenylamino)-1,2,4-triazolium hydroxide) in 5 mL of glacial acetic acid and 95 mL of water. The solution may be filtered with slight suction through an alumdum crucible and kept in a dark bottle.

1-Nitroso-2-naphthol. Make a saturated solution in 50% acetic acid (1 part of glacial acetic acid with 1 part of water). Does not keep well.

Nylander's solution (carbohydrates). Dissolve 20 g of bismuth subnitrate and 40 g of Rochelle salt in 1 L of 8% NaOH solution. Cool and filter.

Obermayer's reagent (for indoxyl in urine). Dissolve 4 g of $FeCl_3$ in 1 L of HCl (sp. gr. 1.19).

Oxine. Dissolve 14 g of 8-hydroxyquinoline in 30 mL of glacial acetic acid. Warm slightly, if necessary. Dilute to 1 L.

Oxygen absorbent. Dissolve 300 g of ammonium chloride in 1 L of water and add 1 L of concentrated ammonium hydroxide solution. Shake the solution thoroughly. For use as an oxygen absorbent, a bottle half full of copper turnings is filled nearly full with the NH_4Cl-NH_4OH solution and the gas passed through.

Pasteur's salt solution. To 1 L of distilled water add 2.5 g of potassium phosphate, 0.25 g of calcium phosphate, 0.25 g of magnesium sulfate, and 12.00 g of ammonium tartrate.

Pavy's solution (glucose reagent). To 120 mL of Fehling's solution, add 300 mL of NH_4OH (sp. gr. 0.88) and dilute to 1 L with water.

Phenanthroline ferrous ion indicator. Dissolve 1.485 g of 1,10-phenanthroline monohydrate in 100 mL of 0.025 M ferrous sulfate solution.

Phenolphthalein. Dissolve 1 g of phenolphthalein in 50 mL of alcohol and add 50 mL of water.

Phenolsulfonic acid (determination of nitrogen as nitrate). Dissolve 25 g of phenol in 150 mL of conc. H_2SO_4, add 75 mL of fuming H_2SO_4 (15% SO_3), stir well and heat for 2 hours at 100°C.

Phloroglucinol solution (pentosans). Make a 3% phloroglucinol (1,3,5-benzenetriol) solution in alcohol. Keep in a dark bottle.

Phosphomolybdic acid (Sonnenschein's reagent for alkaloids).

1. Prepare ammonium phosphomolybdate and after washing with water, boil with nitric acid and expel NH_3; evaporate to dryness and dissolve in 2 M nitric acid.
2. Dissolve ammonium molybdate in HNO_3 and treat with phosphoric acid. Filter, wash the precipitate, and boil with aqua regia until the ammonium salt is decomposed. Evaporate to dryness. The residue dissolved in 10% HNO_3 constitutes Sonnenschein's reagent.

Phosphoric acid — sulfuric acid mixture. Dilute 150 mL of conc. H_2SO_4 and 100 mL of conc. H_3PO_4 (85%) with water to a volume of 1 L.

Phosphotungstic acid (Schcibicr's reagent for alkaloids).

1. Dissolve 20 g of sodium tungstate and 15 g of sodium phosphate in 100 mL of water containing a little nitric acid.
2. The reagent is a 10% solution of phosphotungstic acid in water. Thc.phosphotungstic acid is prepared by evaporating a mixture of 10 g of sodium tungstate dissolved in 5 g of phosphoric acid (sp. gr. 1.13) and enough boiling water to effect solution. Crystals of phosphotungstic acid separate.

Picric acid (Hager's reagent for alkaloids, wool and silk). Dissolve 1 g of picric acid in 100 mL of water.

Potassium antimonate (reagent for sodium). Boil 22 g of potassium antimonate with 1 L of water until nearly all of the salt has dissolved, cool quickly, and add 35 mL of 10% potassium hydroxide. Filter after standing overnight.

Potassium-cadmium iodide (Marme's reagent for alkaloids). Add 2 g of CdI_2 to a boiling solution of 4 g of KI in 12 mL of water, and then mix with 12 mL of saturated KI solution.

Potassium hydroxide (for CO_2 absorption). Dissolve 360 g of KOH in water and dilute to 1 L.

Potassium iodide — mercuric iodide (Brucke's reagent for proteins). Dissolve 50 g of KI in 500 mL of water, and saturate with mercuric iodide (about 120 g). Dilute to 1 L.

Potassium pyrogallate (for oxygen absorption). For mixtures of gases containing less than 28% oxygen, add 100 mL of KOH solution (50 g of KOH to 100 mL of water) to 5 g of pyrogallol. For mixtures containing more than 28% oxygen the KOH solution should contain 120 g of KOH to 100 mL of water.

Pyrogallol, alkaline.

1. Dissolve 75 g of pyrogallic acid in 75 mL of water.
2. Dissolve 500 g of KOH in 250 mL of water. When cool, adjust until sp. gr. is 1.55.

For use, add 270 mL of solution (2) to 30 mL of solution (1).

Rosolic acid (indicator). Dissolve 1 g of rosolic acid in 10 mL of alcohol and add 100 mL of water.

Scheibler's reagent. See Phosphotungstic acid.

Schiff's reagent. See Fuchsin-sulfurous acid.

Schweitzer's reagent. See Cupric oxide, ammoniacal.

Soap solution (reagent for hardness in water). Dissolve 100 g of dry castile soap in 1 L of 80% alcohol (5 parts alcohol to 1 part water). Allow to stand several days and dilute with 70% to 80% alcohol until 6.4 mL produces a permanent lather with 20 mL of standard calcium solution. The latter solution is made by dissolving 0.2 g of $CaCO_3$ in a small amount of dilute HCl, evaporating to dryness and making up to 1 L.

Sodium bismuthate (oxidation of manganese). Heat 20 parts of NaOH nearly to redness in an iron or nickel crucible and add slowly 10 parts of basic bismuth nitrate which has been previously dried. Add 2 parts of sodium peroxide, and pour the brownish-yellow fused mass onto an iron plate to cool. When cold, break up in a mortar, extract with water, and collect on an asbestos filter.

Sodium hydroxide (for CO_2 absorption). Dissolve 330 g of NaOH in water and dilute to 1 L.

Sodium nitroprusside (reagent for hydrogen sulfide and wool). Use a freshly prepared solution of 1 g of sodium nitroferricyanide in 10 mL of water.

Sodium oxalate (primary standard). Dissolve 30 g of the commercial salt in 1 L of water, make slightly alkaline with sodium hydroxide, and let stand until perfectly clear. Filter and evaporate the filtrate to 100 mL. Cool and filter. Pulverize the residue and wash it several times with small volumes of water. The procedure is repeated until the mother liquor is free from sulfate and is neutral to phenolphthalein.

Sodium plumbite (reagent for wool). Dissolve 5 g of sodium hydroxide in 100 mL of water. Add 5 g of litharge (PbO) and boil until dissolved.

Sodium polysulfide. Dissolve 480 g of $Na_2S{\cdot}9H_2O$ in 500 mL of water, add 40 g of NaOH and 18 g of sulfur. Stir thoroughly and dilute to 1 L with water.

Sonnenschein's reagent. See Phosphomolybdic acid.

Starch solution.

1. Make a paste with 2 g of soluble starch and 0.01 g of HgI_2 with a small amount of water. Add the mixture slowly to 1 L of boiling water and boil for a few minutes. Keep in a glass stoppered bottle. If other than soluble starch is used, the solution will not clear on boiling; it should be allowed to stand and the clear liquid decanted.
2. A solution of starch which keeps indefinitely is made as follows: Mix 500 mL of saturated NaCl solution (filtered), 80 mL of glacial acetic acid, 20 mL of water and 3 g of starch. Bring slowly to a boil and boil for 2 minutes.
3. Make a paste with 1 g of soluble starch and 5 mg of HgI_2, using as little cold water as possible. Then pour about 200 mL of boiling water on the paste and stir immediately. This will give a clear solution if the paste is prepared correctly and the water actually boiling. Cool and add 4 g of KI. Starch solution decomposes on standing due to bacterial action, but this solution will keep well if stored under a layer of toluene.

Stoke's reagent. Dissolve 30 g of $FeSO_4$ and 20 g of tartaric acid in water and dilute to 1 L. Just before using, add concentrated NH_4OH until the precipitate first formed is redissolved.

Sulfanilic acid (reagent for nitrites). Dissolve 0.5 g of sulfanilic acid in a mixture of 15 mL of glacial acetic acid and 135 mL of recently boiled water.

Sulfomolybdic acid (Froehde's reagent for alkaloids and glucosides). Dissolve 10 g of molybdic acid or sodium molybdate in 100 mL of conc. H_2SO_4.

Tannic acid (reagent for albumin, alkaloids, and gelatin). Dissolve 10 g of tannic acid in 10 mL of alcohol and dilute with water to 100 mL.

Titration mixture (residual chlorine in water analyasis). Prepare 1 L of dilute HCl (100 mL of HCl (sp. gr. 1.19) in sufficient water to make 1 L). Dissolve 1 g of *o*-tolidine in 100 mL of the dilute HCl and dilute to 1 L with dilute HCl solution.

Trinitrophenol solution. See Picric acid.

Turmeric tincture (reagent for borates). Digest ground turmeric root with several quantities of water which are discarded. Dry the residue and digest it several days with six times its weight of alcohol. Filter.

Uffelmann's reagent (turns yellow in presence of lactic acid). To a 2% solution of pure phenol in water, add a water solution of $FeCl_3$ until the phenol solution becomes violet in color.

Wagner's reagent. See Iodo-potassium iodide.

Wagner's solution (used in phosphate rock analysis to prevent precipitation of iron and aluminum). Dissolve 25 g of citric acid and 1 g of salicylic acid in water and dilute to 1 L. Use 50 mL of the reagent.

Wij's iodine monochloride solution (for iodine number). Dissolve 13 g of resublimed iodine in 1 L of glacial acetic acid which will pass the dichromate test for reducible matter. Set aside 25 mL of this solution. Pass into the remainder of the solution dry chlorine gas (dried and washed by passing through H_2SO_4 (sp. gr. 1.84)) until the characteristic color of free iodine has been discharged. Now add the iodine solution which was reserved, until all free chlorine has been destroyed. A slight excess of iodine does little or no harm, but an excess of chlorine must be avoided. Preserve in well stoppered, amber colored bottles. Avoid use of solutions which have been prepared for more than 30 days.

Wij's special solution (for iodine number). To 200 mL of glacial acetic acid that will pass the dichromate test for reducible matter, add 12 g of dichloramine T (*N,N*-dichloro-4-methylbenzenesulfonamide), and 16.6 g of dry KI (in small quantities with continual shaking until all the KI has dissolved). Make up to 1 L with the same quality of acetic acid used above and preserve in a dark colored bottle.

Zimmermann-Reinhardt reagent (determination of iron). Dissolve 70 g of $MnSO_4{\cdot}4H_2O$ in 500 mL of water, add 125 mL of conc. H_2SO_4 and 125 mL of 85% H_3P0_4, and dilute to 1 L.

Zinc chloride solution, basic (reagent for silk). Dissolve 1000 g of zinc chloride in 850 mL of water, and add 40 g of zinc oxide. Heat until solution is complete.

Zinc uranyl acetate (reagent for sodium). Dissolve 10 g of $UO_2(C_2H_3O_2)_2{\cdot}2H_2O$ in 6 g of 30% acetic acid with heat, if necessary, and dilute to 50 mL. Dissolve 30 g of $Zn(C_2H_3O_2)_2{\cdot}H_2O$ in 3 g of 30% acetic acid and dilute to 50 mL. Mix the two solutions, add 50 mg of NaCl, allow to stand overnight and filter.

STANDARD SOLUTIONS OF ACIDS, BASES, AND SALTS

For each compound listed, the last column of this table gives the mass in grams which is contained in 1 liter of a solution whose amount-of-substance concentration divided by the equivalence factor of the compound equals 0.1 mol/L. In the older literature such a solution is often referred to as a "decinormal solution" (0.1 N).

Reference

Compendium of Analytical Nomenclature (IUPAC), Pergamon Press, Oxford, 1978.

Name	Formula	Atomic or molecular weight	Equivalence factor	Mass in grams
Acetic acid	$HC_2H_3O_2$	60.0530	1	6.0053
Ammonia	NH_3	17.0306	1	1.7031
Ammonium ion	NH_4^+	18.0386	1	1.8039
Ammonium chloride	NH_4Cl	53.4916	1	5.3492
Ammonium sulfate	$(NH_4)_2SO_4$	132.1388	1/2	6.6069
Ammonium thiocyanate	NH_4CNS	76.1204	1	7.6120
Barium	Ba	137.34	1/2	6.867
Barium carbonate	$BaCO_3$	197.3494	1/2	9.8675
Barium chloride hydrate	$BaCl_2 \cdot 2H_2O$	244.2767	1/2	12.2138
Barium hydroxide	$Ba(OH)_2$	171.3547	1/2	8.5677
Barium oxide	BaO	153.3394	1/2	7.6670
Bromine	Br	79.909	1	7.9909
Calcium	Ca	40.08	1/2	2.004
Calcium carbonate	$CaCO_3$	100.0894	1/2	5.0045
Calcium chloride	$CaCl_2$	110.9860	1/2	5.5493
Calcium chloride hydrate	$CaCl_2 \cdot 6H_2O$	219.0150	1/2	10.9508
Calcium hydroxide	$Ca(OH)_2$	74.0947	1/2	3.7047
Calcium oxide	CaO	56.0794	1/2	2.8040
Chlorine	Cl	35.453	1	3.5453
Citric acid	$C_6H_8O_7 \cdot H_2O$	210.1418	1/3	7.0047
Cobalt	Co	58.9332	1/2	2.9466
Copper	Cu	63.54	1/2	3.177
Copper oxide (cupric)	CuO	79.5394	1/2	3.9770
Copper sulfate hydrate	$CuSO_4 \cdot 5H_2O$	249.6783	1/2	12.4839
Hydrochloric acid	HCl	36.4610	1	3.6461
Hydrocyanic acid	HCN	27.0258	1	2.7026
Iodine	I	126.9044	1	12.6904
Lactic acid	$C_3H_6O_3$	90.0795	1	9.0080
Malic acid	$C_4H_6O_5$	134.0894	1/2	6.7045
Magnesium	Mg	24.312	1/2	1.2156
Magnesium carbonate	$MgCO_3$	84.3214	1/2	4.2161
Magnesium chloride	$MgCl_2$	95.2180	1/2	4.7609
Magnesium chloride hydrate	$MgCl_2 \cdot 6H_2O$	203.2370	1/2	10.1623
Magnesium oxide	MgO	40.3114	1/2	2.0156
Manganese	Mn	54.938	1/2	2.7469
Manganese sulfate	$MnSO_4$	150.9996	1/2	7.5500
Mercuric chloride	$HgCl_2$	271.4960	1/2	13.5748
Nickel	Ni	58.71	1/2	2.9356
Nitric acid	HNO_3	63.0129	1	6.3013
Oxalic acid	$H_2C_2O_4$	90.0358	1/2	4.5018
Oxalic acid hydrate	$H_2C_2O_4 \cdot 2H_2O$	126.0665	1/2	6.3033
Oxalic acid anhydride	C_2O_3	72.0205	1/2	3.6010
Phosphoric acid	H_3PO_4	97.9953	1/3	3.2665
Potassium	K	39.102	1	3.9102
Potassium bicarbonate	$KHCO_3$	100.1193	1	10.0119
Potassium carbonate	K_2CO_3	138.2134	1/2	6.9106
Potassium chloride	KCl	74.5550	1	7.4555
Potassium cyanide	KCN	65.1199	1	6.5120
Potassium hydroxide	KOH	56.1094	1	5.6109

Name	Formula	Atomic or molecular weight	Equivalence factor	Mass in grams
Potassium oxide	K_2O	94.2034	1/2	4.7102
Potassium tartrate	$K_2H_4C_4O_6$	226.2769	1/2	11.3139
Silver	Ag	107.87	1	10.787
Silver nitrate	$AgNO_3$	169.8749	1	16.9875
Sodium	Na	22.9898	1	2.2990
Sodium bicarbonate	$NaHCO_3$	84.0071	1	8.4007
Sodium carbonate	Na_2CO_3	105.9890	1/2	5.2995
Sodium chloride	NaCl	58.4428	1	5.8443
Sodium hydroxide	NaOH	39.9972	1	3.9997
Sodium oxide	Na_2O	61.9790	1/2	3.0990
Sodium sulfide	Na_2S	78.0436	1/2	3.9022
Succinic acid	$H_2C_4H_4O_4$	118.0900	1/2	5.9045
Sulfuric acid	H_2SO_4	98.0775	1/2	4.9039
Tartaric acid	$C_4H_6O_6$	150.0888	1/2	7.5044
Zinc	Zn	65.37	1/2	3.269
Zinc sulfate hydrate	$ZnSO_4 \cdot 7H_2O$	287.5390	1/2	14.3769

STANDARD SOLUTIONS OF OXIDATION AND REDUCTION REAGENTS

For each reagent listed, the last column of this table gives the mass in grams which is contained in a solution whose amount-of-substance concentration divided by the equivalence factor of the compound equals 0.1 mol/L. The equivalence factor given refers to the most common reactions of the reagent. In the older literature such a solution is often called a "decinormal solution" (0.1 N).

Reference

Compendium of Analytical Nomenclature (IUPAC), Pergamon Press, Oxford, 1978.

Name	Formula	Atomic or molecular weight	Equivalence factor	Mass in grams
Antimony	Sb	121.75	1/2	6.0875
Arsenic	As	74.9216	1/2	3.7461
Arsenic trisulfide	As_2S_3	246.0352	1/4	6.1509
Arsenous oxide	As_2O_3	197.8414	1/4	4.9460
Barium peroxide	BaO_2	169.3388	1/2	8.4669
Barium peroxide hydrate	$BaO_2 \cdot 8H_2O$	313.4615	1/2	15.6730
Calcium	Ca	40.08	1/2	2.004
Calcium carbonate	$CaCO_3$	100.0894	1/2	5.0045
Calcium hypochlorite	$Ca(OCl)_2$	142.9848	1/4	3.5746
Calcium oxide	CaO	56.0794	1/2	2.8040
Chlorine	Cl	35.453	1	3.5453
Chromium trioxide	CrO_3	99.9942	1/3	3.3331
Ferrous ammonium sulfate	$FeSO_4(NH_4)SO_4 \cdot 6H_2O$	392.0764	1	39.2076
Hydroferrocyanic acid	$H_4Fe(CN)_6$	215.9860	1	21.5986
Hydrogen peroxide	H_2O_2	34.0147	1/2	1.7007
Hydrogen sulfide	H_2S	34.0799	1/2	1.7040
Iodine	I	126.9044	1	12.6904
Iron	Fe	55.847	1	5.5847
Iron oxide (ferrous)	FeO	71.8464	1	7.1846
Iron oxide (ferric)	Fe_2O_3	159.6922	1/2	7.9846
Lead peroxide	PbO_2	239.1888	1/2	11.9594
Manganese dioxide	MnO_2	86.9368	1/2	4.3468
Nitric acid	HNO_3	63.0129	1/3	2.1004
Nitrogen trioxide	N_2O_3	76.0116	1/4	1.9002
Nitrogen pentoxide	N_2O_5	108.0104	1/6	1.8001
Oxalic acid	$C_2H_2O_4$	90.0358	1/2	4.5018
Oxalic acid hydrate	$C_2H_2O_4 \cdot 2H_2O$	126.0665	1/2	6.3033
Oxygen	O	15.9994	1/2	0.8000
Potassium dichromate	$K_2Cr_2O_7$	294.1918	1/6	4.9032
Potassium chlorate	$KClO_3$	122.5532	1/6	2.0425
Potassium chromate	K_2CrO_4	194.1076	1/3	6.4733
Potassium ferrocyanide	$K_4Fe(CN)_6$	368.3621	1	36.8362
Potassium ferrocyanide hydrate	$K_4Fe(CN)_6 \cdot 3H_2O$	422.4081	1	42.2408
Potassium iodide	KI	166.0064	1	16.6006
Potassium nitrate	KNO_3	101.1069	1/3	3.3702
Potassium perchlorate	$KClO_4$	138.5526	1/8	1.7319
Potassium permanganate	$KMnO_4$	158.0376	1/5	3.1608
Sodium chlorate	$NaClO_3$	106.4410	1/6	1.7740
Sodium nitrate	$NaNO_3$	84.9947	1/3	2.8332
Sodium thiosulfate hydrate	$Na_2S_2O_3 \cdot 5H_2O$	248.1825	1	24.8183
Stannous chloride	$SnCl_2$	189.5960	1/2	9.4798
Stannous oxide	SnO	134.6894	1/2	6.7345
Sulfur dioxide	SO_2	64.0628	1/2	3.2031
Tin	Sn	118.69	1/2	5.935

ORGANIC ANALYTICAL REAGENTS FOR THE DETERMINATION OF INORGANIC SUBSTANCES

G. Ackermann, L. Sommer, and D. Thorburn Burns

Determination	Reagents	Ref.
Aluminium	Alizarin Red S	Onishi, Part II a, p 28. (5), Snell, *Metals I,* p 587. (7)
	Aluminon	Fries/Getrost, p 16. (2), Onishi, IIa, p 21. (5), Snell, *Metals I,* p 590. (7)
	Aluminon + Cetyltrimethylammonium bromide	Huaxue Shiji, *8*, 85, (1986)
	Chrome Azurol S	Onishi, Part IIa, p 26. (5), Snell, *Metals I,* p 605. (7)
	Chrome Azurol S + Cetyltrimethylammonium bromide	Marczenko, p 133. (3), Snell, *Metals I,* p 606. (7)
	Chromazol KS + Cetylpyridinium bromide	*Analyst, 107,* 428, (1982).
	Eriochrome Cyanine R	Fries/Getrost, p 19. (2), Onishi, Part IIa, p 25. (5), Snell, *Metals I,* p 611. (7)
	Eriochrome Cyanine R + Cetyltrimethylammonium bromide	Snell, *Metals I,* p 613. (7), A*nalyst, 107*, 1431, (1982).
	8-Hydroxyquinoline	Fries/Getrost, p 22. (2), Marczenko, p 131. (3), Onishi, Part IIa, p 31. (5), Snell, *Metals I* , p 622. (7)
Ammonia	Phenol + Sodium hypochlorite	Boltz, p 210 (1), Marczenko, p 413. (3), Snell, *Nonmetals*, p 604. (9)
Antimony	Brilliant Green	Onishi, Part IIa, p 102. (5), Snell, *Metals I,* p 384. (7)
	Bromopyrogallol Red	*Talanta, 13*, 507, (1966).
	Rhodamine B	Fries/Getrost, p 32. (2), Marczenko, p 141. (3), Onishi, Part IIa, p 93. (5), Snell, *Metals I,* p 404. (7)
	Silver diethyldithiocarbamate	Fries/Getrost, p 36. (2)
Arsenic	Silver diethyldithiocarbamate	Fries/Getrost, p 41. (2), Marczenko, p 153. (3), Onishi, Part IIa, p 153. (5), Snell, *Metals I,* p 370. (7)
Barium	Sulfonazo III	Fries/Getrost, p 46. (2), Snell, *Metals II,* p 1782. (8), Onishi, Part IIa, p 202. (5)
Beryllium	Beryllon II	Snell, *Metals I,* p 667. (7)
	Chrome Azurol S	Marczenko, p 163. (3), Snell, *Metals I,* p 672. (7)
	Chrome Azurol S + Cetyltrimethylammonium bromide	Marczenko, p 164. (3), Snell, *Metals I,* p 673. (7)
	Eriochrome Cyanine R	Snell, *Metals I,* p 675. (7), *Talanta, 31,* 249, (1984).
	Eriochrome Cyanine R + Cetyltrimethylammonium bromide	Zh. *Anal. Khim.*, *33*, 1298, (1978).
Bismuth	Dithizone	Onishi, Part IIa, p 262. (5), Snell, *Metals I,* p 303. (7)
	Pyrocatechol Violet	Fres. Z. *Anal. Chem., 186,* 418, (1962).
	Pyrocatechol Violet + Cetyltrimethylammonium bromide	Zh. *Anal. Khim., 38,* 216, (1983).
	Thiourea	Onishi, Part IIa, p 260. (5), Snell, *Metals I,* p 317. (7)
	Xylenol Orange	Friez/Getrost, p 57. (2), Marczenko, p 172. (3), Snell, *Metals I,* p 320. (7)
Boron	Azomethine H	Snell, Nonmetals, p 165. (9)
	Carminic acid	Boltz, p 14. (1), Fries/Getrost, p 65. (2), Snell, *Nonmetals*, p 170. (9), Williams, p 35. (11)
	Curcumin	Boltz, p 8. (1), Fries/Getrost, p 68. (2), Marczenko, p 180. (3), Snell, *Nonmetals*, p 180. (9), Fres. Z. A*nal. Chem., 323*, 266, (1986).
	Methylene Blue	Boltz, p 21. (1), Marczenko, p 183. (3), Snell, *Nonmetals*, p 205. (9), *Talanta,* 31, 547, (1984).
Bromide	Fluorescein	Boltz, p 48. (1), Snell, *Nonmetals*, p 276., Fres. Z. *Anal. Chem., 301*, 28 (1980).
	Phenol Red	Boltz, p 44. (1), Marczenko, p 190. (3), Snell, Nonmetals, p 28. (9)
Cadmium	2-(5-Bromo-2-pyridylazo)-5-diethylaminophenol	Marczenko, p 197. (3)
	Cadion	Onishi, Part IIa, p 323. (5)
	Dithizone	Fries/Getrost, p 78. (2), Onishi, Part IIa, p 315. (5), Snell, *Metals I,* p 279. (7), West, p 25. (10).
	4–(2-Pyridylazo)resorcinol	Fres. Z. *Anal. Chem.*, *310*, 51, (1982).
Calcium	Chlorophosphonazo III	Marczenko, p 207. (3), Snell, *Metals II,* p 1744. (8)
	Glyoxal-bis(2-hydroxyanil)	Fries/Getrost, p 86. (2), Onishi, Part IIa, p 352. (5), Snell, *Metals I,* p 1762. (8)
	Murexide	Onishi, Part IIa, p 357. (5), Snell, *Metals II,* p 1769. (8)
	Phthalein Purple	*Anal. Chim. Acta*, *34,* 71 (1966).
Cerium	*N*-benzoyl-*N*-phenylhydroxylamine	*Anal. Chim. Acta, 48,* 155, (1969).

Determination	Reagents	Ref.
	8-Hydroxyquinoline	Fries/Getrost, p 93. (2), Marczenko, p 220. (3), Onishi, Part IIa, p 383. (7)
Chlorine	*N,N*-Diethyl-1,4-phenylenediamine	Boltz, p 92. (1), Fries/Getrost, p 101. (2), Snell, Nonmetals, p 225. (9), *Analyst, 90,* 187, (1965).
Chromium	1,5-Diphenylcarbazide	Fries/Getrost, p 105. (2), Onishi, Part IIa, p 412. (5), Snell, *Metals I,* p 714. (7), West, p 12. (10)
	4-(2-Pyridylazo)resorcinol	Snell, *Metals I,* p 736. (7), West, p 17. (10)
	4-(2-Pyridylazo)resorcinol + Tetradecyldimethyl-benzylammonium chloride	West, p 17. (10), A*nal. Chim. Acta, 67*, 297, (1973).
	4-(2-Pyridylazo)resorcinol + Hydrogen peroxide	Fres. Z. *Anal. Chem.*, *304*, 382, (1980).
Cobalt	Nitroso-R salt	Fries/Getrost, p 118. (2), Onishi, Part IIa, p 454. (5), Snell, *Metals I,* p 953. (7)
	1-Nitroso-2-naphthol	Fries/Getrost, p 111. (2), Marczenko, p 246. (3), Snell, *Metals I,* p 947. (5)
	2-Nitroso-1-naphthol	Fries/Getrost, p 113. (2), Onishi, Part IIa, p 459. (5), Snell, *Metals I,* p 949. (7), West, p 45. (10)
	4-(2-Pyridylazo)resorcinol	Snell, *Metals I,* p 969. (7), West, p 44. (10)
	4-(2-Pyridylazo)resorcinol + Diphenylguanidine	Zh. *Anal. Khim., 35*, 1306, (1980).
Copper	Bathocuproine	Fries/Getrost, p 135. (2), Snell, *Metals I,* p 148. (7)
	Bathocuproine disulfonic acid	Fries/Getrost, p 137. (2), West, p 52. (10)
	Dithizone	Marczenko, p 258. (3), Onishi, Part IIa, p 529. (5), Snell, *Metals I,* p 199. (7)
	Neocuproine	Snell, *Metals I,* p 217. (5), West, p 51. (10)
	Cuprizone	Onishi, Part IIa, p 534. (5), Snell, *Metals I,* p 157. (7), West, p 53. (10)
	4-(2-pyridylazo)resorcinol + Tetradecyldimethyl-benzylammonium chloride	*Anal. Chim. Acta*, *138,* 321, (1982).
Cyanide	Barbituric Acid + Pyridine	Fries/Getrost, p 153. (2), Snell, *Nonmetals*, p 653. (9)
	Barbituric Acid + Pyridine-4-carboxylic acid	*Anal. Chim. Acta*, *99*, 197, (1978).
Fluoride	Alizarin Fluorine blue + Lanthanum(III) ion	Boltz, p 129. (1), Fries/Getrost, p 158. (2), Snell, *Nonmetals,* p 333. (9), Williams, p 354. (11)
	Eriochrome Cyanine R + Zirconium(IV) ion	Boltz, p 119. (1), Snell, *Nonmetals*, p 359. (2), Williams, p 357. (11)
Gallium	Pyrocatechol violet + Diphenylguanidine	Snell, *Metals I,* p 500. (7)
	8-Hydroxyquinoline	Onishi Pt IIa, p 582. (5), Snell, *Metals I,* p 505. (7)
	1-(2-Pyridylazo)-2-naphthol	Snell, *Metals I,* p 512. (7)
	4-(2-Pyridylazo)resorcinol	Snell, *Metals I,* p 513. (7)
	Rhodamine B	Marczenko, p 284. (3), Onishi, Part IIa, p 578. (5), Snell, *Metals I,* p 515. (7)
	Xylenol Orange	Fries/Getrost, p 166. (2), Snell, *Metals I,* p 523. (7)
	Xylenol Orange + 8-Hydroxyquinoline	*Zh. Anal. Khim.*, *26*, 75, (1971).
Germanium	Brilliant Green + Molybdate	Snell, *Metals I,* p 562. (7)
	Phenylfluorone	Fries/Getrost, p 168. (2), Marczenko, p 292. (3), Onishi, Part IIa, p 607. (5), Snell, *Metals I,* p 570. (7)
Gold	5-(4-Diethylaminobenzylidene) rhodanine	Fries/Getrost, p 173. (2), Onishi, Part IIa, p 631. (5), Snell, *Metals II,* p 1516. (8)
	Rhodamine B	Fries/Getrost, p 175. (2), Marczenko, p 301. (3), Onishi, Part IIa, p 637. (5), Snell, *Metals II,* p 513. (8)
Hafnium	Arsenazo III	Snell, *Metals II,* p 1184. (8), *Talanta, 19,* 807, (1972).
Indium	Bromopyrogallol Red	Snell, *Metals I,* p 469. (7)
	Chrome Azurol S	Snell, *Metals I,* p 474. (7)
	Chrome Azurol S + Cetyltrimethylammonium bromide	*Anal. Chim. Acta, 67*, 107, (1973).
	Dithizone	Fries/Getrost, p 179. (2), Onishi, Part IIa, p 672. (5), Snell, *Metals I,* p 474. (7)
	8-Hydroxyquinoline	Onishi, Part IIa, p 670. (5), Snell, *Metals I,* p 475. (7)
	1-(2-Pyridylazo)-2-naphthol	Snell, *Metals I,* p 480. (7)
	4-(2-Pyridylazo)resorcinol	Marczenko, p 309. (3), Snell, *Metals* I, p 480. (7)
Iodide	Neocuproine + Copper(II)	*Anal. Chim. Acta, 69*, 321, (1974).
Iodine	Starch	Boltz, p 162. (1), Marczenko, p 316. (3), Snell, *Nonmetals,* p 307. (9)
Iridium	Rhodamine 6G + Tin(II)	Marczenko, p 323. (3)
	N,N-Dimethyl-4-nitrosoaniline	*Anal. Chem., 27,* 1776, (1955).
Iron	Bathophenanthroline	Fries/Getrost, p 189. (2), Onishi, Part IIa, p 729. (5), Snell, *Metals I,* p 763. (7)
	Bathophenanthroline disulfonic acid	Fries/Getrost, p 191. (2), Snell, *Metals I,* p 772. (7)

Determination	Reagents	Ref.
	2,2′-Bipyridyl	Snell, *Metals I,* p 750. (7)
	Chrome Azurol S + Cetyltrimethylammonium bromide	Snell, *Metals I,* p 757. (7), *Coll. Czech. Chem. Comm., 45*, 2656, (1980).
	1,10-Phenanthroline	Fries/Getrost, p 199. (2), Marczenko, p 331. (3), Onishi, Part IIa, p 725. (5), Snell, *Metals I,* p 795. (7)
	1,10-Phenanthroline + Bromothymol Blue	*Zh. Anal. Khim., 25,* 1348, (1970).
	Ferrozine	Onishi, Part IIa, p 730. (5), Snell, *Metals I,* p 783. (7)
Lanthanum	Arsenazo III	Marczenko, p 468. (3), Snell, *Metals II,* p 1910. (8)
Lead	Dithizone	Fries/Getrost, p 207. (2), Onishi, Part IIa, p 824. (5), Snell, *Metals I,* p 2. (7), West, p 34. (10)
	Sodium diethyldithiocarbamate	Fries/Getrost, p 214. (2), Snell, *Metals I,* p 27. (7)
	4-(2-Pyridylazo)resorcinol	Fries/Getrost, p 220. (2), Marczenko, p 347. (3), Snell, *Metals I,* p 34. (7)
Lithium	Thoron	Onishi, Part IIa, p 863. (5), Snell, *Metals II,* p 1726. (8), *Talanta,* 30, 587, (1983).
Magnesium	Eriochrome Black T	Fries/Getrost, p 226. (2), Marczenko, p 355. (3), Onishi, Part IIb, p 13. (6), Snell, *Metals II,* p 1932. (8)
	8-Hydroxyquinoline	Onishi, Part IIb, p 11. (6), Snell, *Metals II,* p 1938. (8)
	8-Hydroxyquinoline + Butylamine	Fries/Getrost, p 228. (2), Snell, *Metals II,* p 1938. (8)
	Titan Yellow	Fries/Getrost, p 234. (2), Marczenko, p 352. (3), Snell, *Metals II,* p 1945. (8)
	Xylidyl Blue	Fries/Getrost, p 231. (2), Onishi, Part IIb, p 14. (6), Snell, *Metals II,* p 1950. (8)
Manganese	Formaldoxime	Fries/Getrost, p 236. (2), Marczenko, p 364. (3), Onishi Part IIb, p 38. (6), Snell, *Metals II,* 1010. (8)
Mercury	Dithizone	Fries/Getrost, p 243. (2), Marczenko, p 373. (3), Onishi, Part IIb, p 66. (6), Snell, *Metals I,* p 107. (7), West, p 29. (10)
	Michler's thioketone	Marczenko, p 375. (3), Snell, *Metals I,* p 126. (7)
	Xylenol Orange	*Talanta, 16,* 1023, (1969)
Molybdenum	Bromopyrogallol Red + Cetylpyridium chloride	West, p 58. (10)
	Phenylfluorone	Snell, *Metals II,* p 1311. (8), *Microchem. J., 31,* 56, (1985).
	Toluene-3,4-dithiol	Fries/Getrost, p 251. (2), Marczenko, p 384. (3), Onishi, Part IIb, p 96. (6), Snell, *Metals II,* p 1301. (8)
Nickel	2-(5-Bromo-2-pyridylazo)-5-diethylaminophenol	Marczenko, p 397. (3), *Talanta 28,* 189, (1981).
	Dimethylglyoxime	Fries/Getrost, p 263. (2), Marczenko, p 393. (3), Onishi, Part IIb, p 125. (6), Snell, *Metals I,* p 887. (7)
	Dimethylglyoxime + Oxidant	Fries/Getrost, p 263. (2), Onishi, Part IIb, p 125. (6), Snell, *Metals I,* p 887. (7)
	2,2′-Furildioxime	Marczenko, p 396. (3), Snell, *Metals I,* p 904. (7)
	2-(2-Pyridylazo)-2-naphthol	Snell, *Metals I,* p 910. (7)
	4-(2-Pyridylazo)resorcinol	Snell, *Metals I,* p 911. (7), West, p 39. (10), *Anal. Chim. Acta, 82,* 431, (1976).
Niobium	*N*-Benzoyl-*N*-phenylhydroxylamine	Snell, *Metals II,* p 1425. (8)
	Pyrocatechol + EDTA or 2,2′Bipyridyl or 1-(2-thenoyl)-3,3,3,-trifluoroacetone	Snell, *Metals II,* p 1427. (8)
	Bromopyrogallol red	Marczenko, p 407. (3), Snell, *Metals II,* p 1426. (8)
	Bromopyrogallol red + Cetylpyridinium chloride	*Talanta, 32,* 189, (1985).
	4-(2-Pyridylazo)resorcinol	Fries/Getrost, p 274. (2), Marczenko, p 406. (3), Onishi, Part IIb, p 160. (7), Snell, *Metals II,* p 1447. (8)
	Sulfochlorophenol S	Onishi, Part IIb, p 161. (7), Snell, *Metals II,* p 1430. (8)
	Xylenol Orange	Onishi, Part IIb, p 164. (7)
Nitrate	Brucine	Boltz, p 227. (1), Fries/Getrost, p 280. (2), Snell, *Nonmetals,* p 546. (9)
	Chromotropic acid	Boltz, p 229. (1), Fries/Getrost, p 281. (2), Snell, *Nonmetals,* p 548. (9), Williams, p 132. (11), *Fres. Z. Anal. Chem., 320,* 490, (1985).
	Sulfanilamide + *N*-(1-Naphthyl)ethylenediamine dihydrochloride	Fries/Getrost, p 279. (2), Snell, *Nonmetals,* p 559. (9)
Nitrite	Sulfanilamide + *N*-(1-Naphthyl)ethylenediamine dihydrochlorine	Boltz, p 241. (1), Snell, *Nonmetals, p* 585. (8), A*nalyst, 109,* 1281, (1984).
	Sulfanilic acid + 1-Naphthylamine	Boltz, p 237. (1), Fries/Getrost, p 285. (2), Marczenko, p 419. (3), Snell, *Nonmetals,* p 586. (9)
Osmium	1,5-Diphenylcarbazide	Marczenko, p 428. (3)
Palladium	2-(5 Bromo-2-pyridylazo)-5-diethylaminophenol	*Talanta, 33,* 939, (1986).

Determination	Reagents	Ref.
	Dithizone	Marczenko, p 440. (3), Onishi, Part IIb, p 227. (6), Snell, *Metals II,* p 1577. (8)
	2-Nitroso-1-naphthol	Fries/Getrost, p 294. (2), Onishi, Part IIb, p 226. (6), Snell, *Metals II,* p 1581. (8)
	4-(2-Pyridylazo)resorcinol	Snell, *Metals II,* p 1583. (8) *Analyst, 107*, 708, (1982).
Phosphate	Rhodamine B + Molybdate	Snell, *Nonmetals,* p 103. (9)
	Malachite Green + Molybdate	Snell, *Nonmetals*, p 12. (9), Analyst, *108*, 361, (1983).
Platinum	Sulfochlorophenolazorhodamine	Onishi, Part IIb, p 253. (6), *Talanta, 34,* 87, (1987).
	Dithizone	Fries/Getrost, p 300. (2), Onishi, Part IIb, p 253. (6), Snell, *Metals II,* p 1534. (8)
	2-Mercaptobenzothiazole	Fries/Getrost, p 302. (2), *Zh. Anal. Khim., 24,* 1172, (1969).
Rare Earths	Arsenazo I	Marczenko, p 470. (3), Onishi, Part IIa, p 785. (5), Snell, *Metals II,* p 1857. (8)
	Arsenazo III	Fries/Getrost, p 309. (2), Marczenko, p 468. (3), Onishi, Part IIa, p 786. (5), Snell, *Metals II,* p 1862. (8)
	Xylenol Orange	Onishi, Part IIa, p 787. (5), Snell, *Metals II,* p 1874. (8)
Rhenium	2,2′-Furildioxime	Fries/Getrost, p 310. (2), Marczenko, p 481. (3), Onishi, Part IIb, p 288. (6), Snell, *Metals II,* p 1659. (8)
Rhodium	1-(2-Pyridylazo)-2-naphthol	Fries/Getrost, p 311. (2), Snell, *Metals II,* p 1553. (8)
Ruthenium	1,10-Phenanthroline	Onishi, Part IIb, p 331. (6), Snell, *Metals II,* p 1623. (8)
	Thiourea	Fries/Getrost, p 318. (2), Onishi, Part IIb, 329. (6), Snell, *Metals II,* p 1626. (8)
	1,4-Diphenylthiosemicarbazide	Marczenko, p 493. (3), Onishi, Part IIb, p 330. (8)
Scandium	Alizarin red S	Fries/Getrost, p 319. (2), Onishi, Part IIb, p 360. (6), Snell, *Metals I,* p 536. (7)
	Arsenazo III	Onishi, Part IIb, p 359. (6), Snell, *Metals I,* p 539. (7)
	Chrome Azurol S	Snell, *Metals* I, p 551. (7), *Anal. Chim. Acta, 159,* 309, (1984).
	Xylenol Orange	Marczenko, p 501. (3), Onishi, Part IIb, p 357. (6), Snell, *Metals I,* p 547. (7)
Selenium	3,3′-Diaminobenzidine	Boltz, p 391. (1), Fries/Getrost, p 323. (2), Marczenko, p 508. (3), Snell, *Nonmetals,* p 490. (9), West, p 4. (10).
	2,3-Diaminonaphthaline	Snell, *Nonmetals,* p 501. (9)
Silver	Dithizone	Fries/Getrost, p 328. (2), Marczenko, p 524. (3), Onishi, Part IIb, p 379. (6), Snell, *Metals I,* p 82. (7)
	Eosin + 1,10-Phenanthroline	Snell, *Metals I,* p 93. (7)
Sulfate	Methylthymol blue + Barium (II)	Snell, *Nonmetals,* p 457. (9)
Sulfide	*N,N,*-Dimethyl-1,4-phenylenediamine	Boltz, p 483. (1), Fries/Getrost, p 344. (2), Snell, *Nonmetals,* p 400. (9), Williams, p 578. (11)
Sulfite	Pararosaniline + Formaldehyde	Boltz, p 478. (1), Marczenko, p 540. (3), Snell, *Nonmetals,* p 430. (9), Williams, p 591. (11)
Tantalum	Methyl Violet	Marczenko, p 551. (3), Snell, *Metals II,* p 1485. (8)
	4-(2-Pyridylazo)resorcinol	Snell, *Metals II,* p 1488. (8)
	Phenylfluorone	Onishi, Part IIb, p 166. (6), Snell, *Metals II,* p 1486. (8)
Tellurium	Diethyldithiocarbamate	Boltz, p 402. (1), Fries/Getrost, p 348. (2), Snell, *Nonmetals,* p 533. (9), Williams, p 220. (10)
	Bismuthiol II	Boltz, p 401. (1), Marczenko, p 557. (3), Snell, *Nonmetals,* p 524. (9)
Thallium	Brilliant green	Fries/Getrost, p 352. (2), Marczenko, p 567. (3), Onishi, Part IIb, p 426. (6), Snell, *Metals I,* p 45. (7)
	Dithizone	Fries/Getrost, p 355. (2), Onishi, Part IIb, p 426. (6), Snell, *Metals I,* p 54. (7)
	Rhodamine B	Fries/Getrost, p 354. (2), Marczenko, p 566. (3), Onishi, Part IIb, p 424. (6), Snell, *Metals I,* p 63. (7)
Thorium	Arsenazo III	Fries/Getrost, p 360. (2), Marczenko, p 575. (3), Onishi, Part IIb, p 460. (6), Snell, *Metals II,* p 1820. (8)
	Thoron	Marczenko, p 574. (3), Onishi, Part IIb, p 463. (6), Snell, *Metals I,* p 1835. (7)
	Xylenol Orange	Snell, *Metals I,* p 1852. (7)
	Xylenol Orange + Cetyltrimethylammonium bromide	*Talanta, 26,* 499, (1979).
Tin	Pyrocatechol violet (and + Cetyltrimethylammonium bromide)	Marczenko, p 585. (3), Onishi, Part IIb, p 501. (6), Snell, M*etals I,* p 422. (7)
	Gallein	Onishi, Part IIb, p 507, 510. (6), Snell, *Metals I,* p 432. (7)
	Phenylfluorone	Fries/Getrost, p 368. (2), Marczenko, p 582. (3), Onishi, Part IIb, p 497. (6), Snell, *Metals I,* p 444. (7)

Determination	Reagents	Ref.
	Toluene-3,4-dithiol + Dispersant	Fries/Getrost, p 366. (2), Onishi, Part IIb, p 502. (6), Snell, *Metals I,* p 427. (7)
Titanium	Chromotropic acid	Marczenko, p 593. (3), Onishi, Part IIb, p 551. (6), Snell, *Metals II,* p 1080. (8)
	Diantipyrinylmethane	Onishi, Part IIb, p 545. (6), Snell, *Metals II,* 1085. (8)
	Tiron	Fries/Getrost, p 376. (2), Onishi, Part IIb, p 549. (6), Snell, *Metals II,* p 1114. (8)
Tungsten	Pyrocatechol Violet	Snell, *Metals II*, p 1265. (8)
	Tetraphenylarsonium chloride + Thiocyanate	Onishi, Part IIb, p 596. (6), Snell, *Metals II,* p 1278. (8)
	Toluene-3,5-dithiol	Marczenko, p 605. (3), Onishi, Part IIb, p 590. (6), Snell, *Metals II,* p 1267. (8)
Uranium	Arsenazo III	Marczenko, p 611. (3), Onishi, Part IIb, p 627. (6), Snell, *Metals II,* p 1356. (8)
	2-(5-Bromo-2-pyridylazo)diethylaminophenol	Fries/Getrost, p 388. (2), Onishi, Part IIb, p 625. (6)
	Chlorophosphonazo III	Snell, *Metals II*, p 1367. (8), *Fres. Z. Anal. Chem., 306*, 110, (1981).
	1-(2-Pyridylazo)-2-naphthol	Fries/Getrost, p 386. (2), Onishi, Part IIb, p 625. (6), Snell, *Metals II,* p 1387. (8)
Vanadium	*N*-Benzoyl-*N*-phenylhydroxylamine	Fries/Getrost, p 395. (2), Marczenko, p 625. (3), Snell, *Metals II,* p 1196. (8)
	8-Hydroxyquinoline	Marczenko, p 623. (3), Snell, *Metals II,* p 1209. (8)
	4-(2-pyridylazo)resorcinol	Fries/Getrost, p 404. (2), Marczenko, p 628. (3), Onishi, Part IIb, p 625. (6), Snell, *Metals II,* p 1226. (8)
Yttrium	Alizarin Red S	Fries/Getrost, p 406. (2), Onishi, Part IIa, p 784. (5), Snell, *Metals II,* p 1919. (8)
	Arsenazo III	Marczenko, p 468. (3), Onishi, Part IIa, p 786. (5), Snell, *Metals II,* p 1921. (8)
	Xylenol Orange	Fries/Getrost, p 406. (2), Onishi, Part IIa, p 787. (5), Snell, *Metals II,* p 1923. (8)
Zinc	Dithizone	Fries/Getrost, p 408. (2), Marczenko, p 637. (3), Onishi, Part IIb, p 708. (6), Snell, *Metals II,* p 1042. (8)
	1-(2-Pyridylazo)-2-naphthol	Marczenko, p 639. (3), Onishi, Part IIb, p 719. (6), Snell, *Metals II,* p 1056. (8)
	Xylenol Orange	Fries/Getrost, p 417. (2), Snell, *Metals II,* p 1062. (8), Talanta, *26*, 693, (1979).
	Zircon	Fries/Getrost, p 412. (2), Onishi, Part IIb, p 719. (6), Snell, *Metals II,* p 1063. (8), West, p 23. (10)
Zirconium	Alizarin Red S	Fries/Getrost, p 421. (2), Marczenko, p 647. (3), Onishi, Part IIb, p 763. (6), Snell, *Metals II,* p 1136. (8)
	Arsenazo III	Fries/Getrost, p 421. (2), Onishi, Part IIb, p 770. (6), Snell, *Metals II,* p 1143. (8)
	Pyrocatechol Violet	Onishi, Part IIb, p 771. (6), Snell, *Metals II,* p 1149. (8)
	Morin	Fries/Getrost, p 424. (2), Onishi, Part IIb, p 765. (6), Snell, *Metals II,* p 1158. (8)
	Xylenol Orange	Fries/Getrost, p 419. (2), Marczenko, p 648. (3), Onishi, Part IIb, p 767. (6), Snell, *Metals II,* p 1167. (8)

Reviews

Sommer, L, Ackermann, G., Thorburn Burns, D., and Savvin, S. B., *Pure and Applied Chem.,* 62, 2147, 1990.

Sommer, L., Ackermann, G., and Thorburn Burns, D., *Pure and Applied Chem.,* 62, 2323, 1990)

Sommer, L., Komarek, J., and Thorburn Burns, D., *Pure and Applied Chem., 64,* 213, 1992.

Savvin, S. B., *Crit. Rev. Anal. Chem.,* 8, 55, 1979.

Monographs

1. Boltz, D. F., and Howell, J. A., *Colorimetric Determination of Nonmetals,* 2nd ed, Wiley, New York, 1978.
2. Fries, J. and Getrost, H., *Organic Reagents for Trace Analysis,* E Merck, Darmstadt, 1977.
3. Marczenko, Z., *Separation and Spectrophotometric Determination of Elements,* Ellis Horwood, Chichester, 1986.
4. Sandell, E. B. and Onishi, H., *Photometric Determination of Traces of Metals. General Aspects, Part I,* 4th ed, J. Wiley, New York, 1978.
5. Onishi, H., *Photometric Determination of Traces of Metals. Part IIa: Individual Metals, Aluminium to Lithium,* 4th ed, J. Wiley, New York, 1986.
6. Onishi, H., *Photometric Determination of Traces of Metals. Part IIb: Individual Metals, Magnesium to Zinc,* 4th ed, J. Wiley, New York, 1989.
7. Snell, F. D., *Photometric and Fluorimetric Methods of Analysis, Metals Part 1,* J. Wiley, New York, 1978.
8. Snell, F. D., *Photometric and Fluorimetric Methods of Analysis, Metals Part 2,* J. Wiley, New York, 1978.
9. Snell, F. D., *Photometric and Fluorimetric Methods of Analysis, Nonmetals,* J. Wiley, New York, 1981.
10. West, T. S. and Nürnberg, H. W., Eds., *The Determination of Trace Metals in Natural Waters,* Blackwell, Oxford, 1988.
11. Williams, W. J., *Handbook of Anion Determination,* Butterworth, London, 1979.
12. Townshend, A., Burns, D. T., Guilbault, G. G., Lobinski, R., Marczenko, Z., Newman, E., and Onishi, H., *Dictionary of Analytical Reagents*, Chapman & Hall, London, 1993.

ACID-BASE INDICATORS

A. K. Covington

The first part of this table lists some common acid-base indicators in alphabetical order along with the approximate pH range(s) at which a color change occurs. Following this is a table of the same indicators ordered by pH range, which includes the nature of the color change, instructions on preparation of the indicator solution, and the acid dissociation constant p*K*, when available.

The color code is:

C = colorless	A = amber	B/G = blue-green
Pk = pink	Y = yellow	V = violet
R = red	B = blue	P = purple
O = orange		

Reference

Bishop, E., Ed., *Indicators*, Pergamon, Oxford, 1972.

Indicator	pH Range
Alizarin	5.6-7.2; 11.0-12.4
Alizarin Red S	4.6-6.0
Alizarin Yellow R	10.1-12.0
Benzopurpurine 4B	2.2-4.2
4,4'-Bis(2-amino-1-naphthylazo)-2,2'-stilbenedisulfonic acid	3.0-4.0
4,4'-Bis(4-amino-1-naphthylazo)-2,2'-stilbenedisulfonic acid	8.0-9.0
Brilliant Yellow	6.6-7.8
Bromocresol Green	3.8-5.4
Bromocresol Purple	5.2-6.8
Bromophenol Blue	3.0-4.6
Bromothymol Blue	6.0-7.6
Chlorophenol Red	5.2-6.8
Clayton Yellow	12.2-13.2
Congo Red	3.0-5.0
o-Cresolphthalein	8.2-9.8
Cresol Red	0.0-1.0; 7.0-8.8
Crystal Violet	0.0-1.8
Curcumin (Turmaric)	7.4-8.6
p-(2,4-Dihydroxyphenylazo) benzenesulfonic acid, sodium salt	11.4-12.6
p-Dimethylaminoazobenzene	2.8-4.4
4-(4-Dimethylamino-1-naphylazo)-3-methoxybenzenesulfonic acid	3.5-4.8
2-(*p*-Dimethylamino-phenylazo)pyridine	0.2-1.8; 4.4-5.6
N,N-Dimethyl-*p*-(*m*-tolylazo)aniline	2.6-4.8
2,4-Dinitrophenol	2.0-4.7
2-(2,4 Dinitrophenylazo)-1-naphthol-3,6-disulfonic acid, disodium salt	6.0-7.0
6,8-Dinitro-2,4-(1*H*)quinazolinedione	6.4-8.0
Erythrosin, disodium salt	2.2-3.6
4-(*p*-Ethoxyphenylazo)-*m*-phenylene-diamine monohydrochloride	4.4-5.8

Indicator	pH Range
Ethyl bis(2,4-dimethylphenyl)ethanoate	8.4-9.6
Ethyl Orange	3.4-4.8
Ethyl Red	4.0-5.8
Ethyl Violet	0.0-2.4
5,5'-Indigodisulfonic acid, disodium salt	11.4-13.0
Malachite Green	0.2-1.8
Metacresol Purple	1.2-2.8; 7.4-9.0
Metanil Yellow	1.2-2.4
Methyl Green	0.2-1.8
Methyl Orange	3.2-4.4
Methyl Red	4.8-6.0
Methyl Violet	0.0-1.6
p-Naphtholbenzein	8.2-10.0
Neutral Red	6.8-8.0
p-Nitrophenol	5.4-6.6
m-Nitrophenol	6.8-8.6
Orange IV	1.4-2.8
Paramethyl Red	1.0-3.0
Phenolphthalein	8.2-10.0
Phenol Red	6.6-8.0
4-Phenylazodiphenylamine	1.2-2.6
4-Phenylazo-1-naphthylamine	4.0-5.6
Propyl Red	4.8-6.6
Quinaldine Red	1.4-3.2
Resazurin	3.8-6.4
Resorcin Blue	4.4-6.2
Tetrabromophenolphthalein ethyl ester, potassium salt	3.0-4.2
Thymol Blue	1.2-2.8; 8.0-9.6
Thymolphthalein	9.4-10.6
4-*o*-Tolylazo-*o*-toluidine	1.4-2.8
1,3,5-Trinitrobenzene	12.0-14.0
2,4,6-Trinitrotoluene	11.5-13.0
Turmaric	7.4-8.6

pH range	Color change	Indicator	p*K*	Preparation
0.0-1.0	R-Y	Cresol Red		0.1 g in 26.2 mL 0.01 M NaOH + 223.8 mL water
0.0-1.6	Y-B	Methyl Violet		0.01-0.05% in water
0.0-1.8	Y-B	Crystal Violet		0.02% in water
0.0-2.4	Y-B	Ethyl Violet		0.1 g in 50 mL 50% v/v methanol-water
0.2-1.8	Y-B/G	Malachite Green	1.3	water
0.2-1.8	Y-B	Methyl Green		0.1% in water
0.2-1.8	Y-R	2-(*p*-Dimethylaminophenylazo)pyridine		0.1% in ethanol
1.0-3.0	R-Y	Paramethyl Red		ethanol
1.2-2.4	R-Y	Metanil Yellow		0.01% in water
1.2-2.6	R-Y	4-Phenylazodiphenylamine		0.01 g in 1 mL 1 M HCl + 50 mL ethanol + 49 mL water
1.2-2.8	R-Y	Thymol Blue	1.65	0.1 g in 21.5 mL 0.01 M NaOH + 228.5 mL water
1.2-2.8	R-Y	Metacresol Purple	1.51	0.1 g in 26.2 mL 0.01 M NaOH + 223.8 mL water
1.4-2.8	R-Y	Orange IV		0.01% in water
1.4-2.8	O-Y	4-*o*-Tolylazo-*o*-toluidine		water
1.4-3.2	C-R	Quinaldine Red	2.63	1% in ethanol
2.0-4.7	C-Y	2,4-Dinitrophenol	3.96	sat. solution in water
2.2-3.6	O-R	Erythrosin, disodium salt		0.1% in water
2.2-4.2	V-R	Benzopurpurine 4B		0.1% in water
2.6-4.8	R-Y	*N,N*-Dimethyl-*p*-(*m*-tolylazo)aniline		0.1% in water
2.8-4.4	R-Y	*p*-Dimethylaminoazobenzene		0.1 g in 100 mL 90% v/v ethanol-water
3.0-4.0	P-R	4,4'-Bis(2-amino-1-naphthylazo)-2,2'-stilbenedisulfonic acid		0.1 g in 5.9 mL 0.05 M NaOH + 94.1 mL water
3.0-4.2	Y-B	Tetrabromophenolphthalein ethyl ester, potassium salt		0.1% in ethanol
3.0-4.6	Y-B	Bromophenol Blue	4.10	0.1 g in 14.9 mL 0.01 M NaOH + 235.1 mL water
3.0-5.0	B-R	Congo Red		0.1% in water
3.2-4.4	R-Y	Methyl Orange	3.46	0.1% in water
3.4-4.8	R-Y	Ethyl Orange	4.34	0.05-0.2% in water or aqueous ethanol
3.5-4.8	V-Y	4-(4-Dimethylamino-1-naphylazo)-3-methoxybenzenesulfonic acid		0.1% in 60% ethanol-water
3.8-5.4	Y-B	Bromocresol Green	4.90	0.1 g in 14.3 mL 0.01 M NaOH + 235.7 mL water
3.8-6.4	O-V	Resazurin		water
4.0-5.6	R-Y	4-Phenylazo-1-naphthylamine		0.1% in ethanol
4.0-5.8	C-R	Ethyl Red	5.42	0.1 g in 100 mL 50% v/v methanol-water 0.1% in ethanol
4.4-5.6	R-Y	2-(*p*-Dimethylaminophenylazo)pyridine		0.1% in ethanol
4.4-5.8	O-Y	4-(*p*-Ethoxyphenylazo)-*m*-phenylene-diamine monohydrochloride		0.1% in water
4.4-6.2	R-B	Resorcin Blue		0.2% in ethanol
4.6-6.0	Y-R	Alizarin Red S		water
4.8-6.0	R-Y	Methyl Red	5.00	0.02 g in 100 mL 60% v/v ethanol-water
4.8-6.6	R-Y	Propyl Red	5.48	ethanol
5.2-6.8	Y-P	Bromocresol Purple	6.40	0.1 g in 18.5 mL 0.01 M NaOH + 231.5 mL water
5.2-6.8	Y-R	Chlorophenol Red	6.25	0.1 g in 23.6 mL 0.01 M NaOH + 226.4 mL water
5.4-6.6	C-Y	*p*-Nitrophenol	7.15	0.1% in water
5.6-7.2	Y-R	Alizarin		0.1% in methanol
6.0-7.0	Y-B	2-(2,4-Dinitrophenylazo)-1-naphthol-3,6-disulfonic acid, disodium salt		0.1% in water
6.0-7.6	Y-B	Bromothymol Blue	7.30	0.1 g in 16 mL 0.01 M NaOH + 234 mL water
6.4-8.0	C-Y	6,8-Dinitro-2,4-(1*H*)quinazolinedione		25 g in 115 mL 1 M NaOH + 50 mL water at 100°C
6.6-7.8	Y-R	Brilliant Yellow		1% in water
6.6-8.0	Y-R	Phenol Red	8.00	0.1 g in 28.2 mL 0.01 M NaOH + 221.8 mL water
6.8-8.0	R-A	Neutral Red		0.01 g in 100 mL 50% v/v ethanol-water
6.8-8.6	C-Y	*m*-Nitrophenol	8.28	0.3% in water
7.0-8.8	Y-R	Cresol Red	8.46	0.1 g in 26.2 mL 0.01 M NaOH + 223.8 mL water
7.4-8.6	Y-R	Turmaric (Curcumin)		ethanol
7.4-9.0	Y-P	Metacresol Purple	8.3	0.1 g in 26.2 mL 0.01 M NaOH + 223.8 mL water
8.0-9.0	B-R	4,4'-Bis(4-amino-1-naphthylazo)-2,2'-stilbenedisulfonic acid		0.1 g in 5.9 mL 0.05 M NaOH + 94.1 mL water
8.0-9.6	Y-B	Thymol Blue	9.20	0.1 g in 21.5 mL 0.01 M NaOH + 228.5 mL water
8.2-10.0	O-B	*p*-Naphtholbenzein		1% in dil. alkali

pH range	Color change	Indicator	p*K*	Preparation
8.2-10.0	C-Pk	Phenolphthalein	9.5	0.5 g in 100 mL 50% v/v ethanol-water
8.2-9.8	C-R	*o*-Cresolphthalein		0.04% in ethanol
8.4-9.6	C-B	Ethyl bis(2,4-dimethylphenyl)ethanoate		sat. solution in 50% acetone-ethanol
9.4-10.6	C-B	Thymolphthalein		0.04 g in 100 mL 50% v/v ethanol-water
10.1-12.0	Y-R	Alizarin Yellow R		0.01% in water
11.0-12.4	R-P	Alizarin		0.1% in methanol
11.4-12.6	Y-O	*p*-(2,4-Dihydroxyphenylazo) benzenesulfonic acid, sodium salt		0.1% in water
11.4-13.0	B-Y	5,5'-Indigodisulfonic acid, disodium salt		water
11.5-13.0	C-O	2,4,6-Trinitrotoluene		0.1-0.5% in ethanol
12.0-14.0	C-O	1,3,5-Trinitrobenzene		0.1-0.5% in ethanol
12.2-13.2	Y-A	Clayton Yellow		0.1% in water

FLUORESCENT INDICATORS

Jack DeMent

Fluorescent indicators are substances which show definite changes in fluorescence with change in pH. Some fluorescent materials are not suitable for indicators since their change in fluorescence is too gradual. Fluorescent indicators find greatest utility in the titration of opaque, highly turbid or deeply colored solutions. A long wavelength ultraviolet ("black light") lamp in a dimly lighted room provides the best environment for titrations involving fluorescent indictors, although bright daylight is sometimes sufficient to evoke a response in the bright green, yellow and orange fluorescent indicators. Titrations are carried out in non-fluorescent glassware. One should check the glassware prior to use to make certain that it does not fluoresce due to the wavelengths of light involved in the titration. The meniscus of the liquid in the burette can be followed when a few particles of an insoluble fluorescent solid are dropped onto its surface.

In this table the indicators are arranged by approximate pH range covered. In the case of some of the dyestuffs the end point may vary slightly with the source or manufacturer.

Indicator	C.I.	From pH	To pH
		pH 0 to 2	
Benzoflavine	—	0.3, yellow fl.	1.7, green fl.
3,6-Dioxyphthalimide	—	0, blue fl.	2.4, green fl.
Eosine YS	768	0,yellow colored	3.0, yellow fl.
Erythrosine	772	0, yellow colored	3.6, yellow fl.
Esculin	—	1.5, colorless	2, blue fl.
4-Ethoxyacridone	—	1.2, green fl.	3.2, blue fl.
3,6-Tetramethyldiaminooxanthone	—	1.2, green fl.	3.4, blue fl.
		pH 2 to 4	
Chromotropic acid	—	3.5, colorless	4.5, blue fl
Fluorescein	766	4, colorless	4.5, green fl.
Magdala Red	—	3.0, purple colored	4.0, fl
α-Naphthylamine	—	3.4, colorless	4.8, blue fl.
β-Naphthylamine	—	2.8, colorless	4.4, violet fl.
Phloxine	774	3.4, colorless	5.0, bright yellow fl.
Salicylic acid	—	2.5, colorless	3.5, blue fl.
		pH 4 to 6	
Acridine	788	4.9, green fl.	5.1, violet colored
Dichlorofluorescein	—	4.0, colorless	5.0, green fl.
3,6-Dioxyxanthone	—	5.4, colorless	7.6, blue-violet fl.
Erythrosine	772	4.0, colorless	4.5, yellow-green fl.
β-Methylesculetin	—	4.0, colorless	6.2, blue fl
Neville-Winther acid	—	6.0, colorless	6.5, blue fl.
Resorufin	—	4.4, yellow fl	6.4, weak orange fl.
Quininic acid	—	4.4, yellow colored	5.0, blue fl.
Quinine [first end point]	—	5.0, blue fl.	6.1, violet fl.
		pH 6 to 8	
Acid R Phosphine	—	(claimed for range pH 6.0–7.0)	
Brilliant Diazol Yellow	—	6.5, colorless	7.5, violet, fl.
Cleves acid	—	6.5, colorless	7.5, green fl.
Coumaric acid	—	7.2, colorless	9.0, green fl.
3,6-Dioxyphthalic dinitrile	—	5.8, blue fl.	8.2, green fl.
Magnesium 8-hydrozyquinolinate	—	6.5, colorless	7.5, golden fl.
β-Methylumbelliferone	—	7.0, colorless	7.5, blue fl.
1-Naphthol-4-sulfonic acid	—	6.0, colorless	6.5, blue fl.
Orcinaurine	—	6.5, colorless	8.0, green fl.
Patent Phosphine	789	(for the range pH 6.0–7.0, green-yellow fl.)	
Thioflavine	816	(for the region pH 6.5–7.0, yellow fl.)	
Umbelliferone	—	6.5, colorless	7.6, blue fl.
		pH 8 to 10	
Acridine Orange	788	8.4, orange colored	10.4, green fl.
Ethoxyphenylnaphthostilbazonium chloride	—	9, green fl.	11, non-fl.

G Salt	—	9.0, dull blue fl.	9.5, bright blue fl.
Naphthazol derivatives	—	8.2, colorless	10.0, yellow or green fl.
α-Naphthionic acid	—	9, blue fl.	11, green fl.
2-Naphthol-3,6-disulfonic acid	—	9.5, dark blue fl	Light blue fl. at higher pH
β-Naphthol	—	8.6, colorless	Blue fl. at higher pH
α-Naphtholsulfonic acid	—	8.0, dark blue fl.	9.0, bright violet fl.
1,4-Naphtholsulfonic acid	—	8.2, dark blue fl.	Light blue fl. at higher pH
Orcinsulfonphthalein	—	8.6, yellow colored	10.0 fl.
Quinine [second end point]	—	9.5, violet fl.	10.0, colorless
R-Salt	—	9.0, dull blue fl.	9.5, bright blue fl.
Sodium 1-naphthol-2-sulfonate	—	9.0, dark blue fl.	10.0, bright violet fl.
		pH 10 to 12	
Courmarin	—	9.8, deep green fl.	12, light green fl.
Eosine BN	771	10.5, colorless	14.0, yellow fl.
Papaverine (permanganate oxidized)	—	9.5, yellow fl.	11.0, blue fl.
Schaffers Salt	—	5.0, violet fl.	11.0, green-blue fl.
SS-Acid (sodium salt)	—	10.0, violet fl.	12.0, yellow-colored
		pH 12 to 14	
Cotarnine	—	12.0, yellow fl.	13.0, white fl.
α-Naphthionic acid	—	12, blue fl.	13, green fl.
β-Naphthionic acid	—	12, blue fl.	13, violet fl.

CONVERSION FORMULAS FOR CONCENTRATION OF SOLUTIONS

A = Weight percent of solute
B = Molecular weight of solvent
E = Molecular weight of solute
F = Grams of solute per liter of solution
G = Molality
M = Molarity
N = Mole fraction
R = Density of solution in grams per milliliter

Concentration of solute—SOUGHT	Concentration of solute—GIVEN				
	A	***N***	***G***	***M***	***F***
A	—	$\frac{100N \times E}{N \times E + (1-N)B}$	$\frac{100G \times E}{1000 + G \times E}$	$\frac{M \times E}{10R}$	$\frac{F}{10R}$
N	$\frac{\frac{A}{E}}{\frac{A}{E} + \frac{100-A}{B}}$	—	$\frac{B \times G}{B \times G + 1000}$	$\frac{B \times M}{M(B-E) + 1000R}$	$\frac{B \times F}{F(B-E) + 1000R \times E}$
G	$\frac{1000A}{E(100-A)}$	$\frac{1000N}{B - N \times B}$	—	$\frac{1000M}{1000R - (M \times E)}$	$\frac{1000F}{E(1000R - F)}$
M	$\frac{10R \times A}{E}$	$\frac{1000R \times N}{N \times E + (1-N)B}$	$\frac{1000R \times G}{1000 + E \times G}$	—	$\frac{F}{E}$
F	$10AR$	$\frac{1000R \times N \times E}{N \times E + (1-N)B}$	$\frac{1000R \times G \times E}{1000 + G \times E}$	$M \times E$	—

ELECTROCHEMICAL SERIES

Petr Vanýsek

There are three tables for this electrochemical series. Each table lists standard reduction potentials, $E°$ values, at 298.15 K (25°C), and at a pressure of 101.325 kPa (1 atm). Table 1 is an alphabetical listing of the elements, according to the symbol of the elements. Thus, data for silver (Ag) precedes those for aluminum (Al). Table 2 lists only those reduction reactions which have $E°$ values positive in respect to the standard hydrogen electrode. In Table 2, the reactions are listed in the order of increasing positive potential, and they range from 0.0000 V to + 3.4 V. Table 3 lists only those reduction potentials which have $E°$ negative with respect to the standard hydrogen electrode. In Table 3, the reactions are listed in the order of decreasing potential and range from 0.0000 V to –4.10 V. The reliability of the potentials is not the same for all the data. Typically, the values with fewer significant figures have lower reliability. The values of reduction potentials, in particular those of less common reactions, are not definite; they are subject to occasional revisions.

Abbreviations: ac = acetate; bipy = 2,2´-dipyridine, or bipyridine; en = ethylenediamine; phen = 1,10-phenanthroline.

References

1. Milazzo, G., Caroli, S., and Sharma, V. K. *Tables of Standard Electrode Potentials*, Wiley, Chichester, 1978.
2. Bard, A. J., Parsons, R., and Jordan, J. *Standard Potentials in Aqueous Solutions*, Marcel Dekker, New York, 1985.
3. Bratsch, S. G. *J. Phys. Chem. Ref. Data*, 18, 1–21, 1989.

TABLE 1. Alphabetical Listing

Reaction	$E°$/V
$Ac^{3+} + 3\ e \rightleftharpoons Ac$	–2.20
$Ag^{+} + e \rightleftharpoons Ag$	0.7996
$Ag^{2+} + e \rightleftharpoons Ag^{+}$	1.980
$Ag(ac) + e \rightleftharpoons Ag + (ac)^{-}$	0.643
$AgBr + e \rightleftharpoons Ag + Br^{-}$	0.07133
$AgBrO_3 + e \rightleftharpoons Ag + BrO_3^{-}$	0.546
$Ag_2C_2O_4 + 2\ e \rightleftharpoons 2\ Ag + C_2O_4^{2-}$	0.4647
$AgCl + e \rightleftharpoons Ag + Cl^{-}$	0.22233
$AgCN + e \rightleftharpoons Ag + CN^{-}$	–0.017
$Ag_2CO_3 + 2\ e \rightleftharpoons 2\ Ag + CO_3^{2-}$	0.47
$Ag_2CrO_4 + 2\ e \rightleftharpoons 2\ Ag + CrO_4^{2-}$	0.4470
$AgF + e \rightleftharpoons Ag + F^{-}$	0.779
$Ag_4[Fe(CN)_6] + 4\ e \rightleftharpoons 4\ Ag + [Fe(CN)_6]^{4-}$	0.1478
$AgI + e \rightleftharpoons Ag + I^{-}$	–0.15224
$AgIO_3 + e \rightleftharpoons Ag + IO_3^{-}$	0.354
$Ag_2MoO_4 + 2\ e \rightleftharpoons 2\ Ag + MoO_4^{2-}$	0.4573
$AgNO_2 + e \rightleftharpoons Ag + 2\ NO_2^{-}$	0.564
$Ag_2O + H_2O + 2\ e \rightleftharpoons 2\ Ag + 2\ OH^{-}$	0.342
$Ag_2O_3 + H_2O + 2\ e \rightleftharpoons 2\ AgO + 2\ OH^{-}$	0.739
$Ag^{3+} + 2\ e \rightleftharpoons Ag^{+}$	1.9
$Ag^{3+} + e \rightleftharpoons Ag^{2+}$	1.8
$Ag_2O_2 + 4\ H^{+} + e \rightleftharpoons 2\ Ag + 2\ H_2O$	1.802
$2\ AgO + H_2O + 2\ e \rightleftharpoons Ag_2O + 2\ OH^{-}$	0.607
$AgOCN + e \rightleftharpoons Ag + OCN^{-}$	0.41
$Ag_2S + 2\ e \rightleftharpoons 2\ Ag + S^{2-}$	–0.691
$Ag_2S + 2\ H^{+} + 2\ e \rightleftharpoons 2\ Ag + H_2S$	–0.0366
$AgSCN + e \rightleftharpoons Ag + SCN^{-}$	0.08951
$Ag_2SeO_3 + 2\ e \rightleftharpoons 2\ Ag + SeO_4^{2-}$	0.3629
$Ag_2SO_4 + 2\ e \rightleftharpoons 2\ Ag + SO_4^{2-}$	0.654
$Ag_2WO_4 + 2\ e \rightleftharpoons 2\ Ag + WO_4^{2-}$	0.4660
$Al^{3+} + 3\ e \rightleftharpoons Al$	–1.662
$Al(OH)_3 + 3\ e \rightleftharpoons Al + 3\ OH^{-}$	–2.31
$Al(OH)_4^{-} + 3\ e \rightleftharpoons Al + 4\ OH^{-}$	–2.328
$H_2AlO_3^{-} + H_2O + 3\ e \rightleftharpoons Al + 4\ OH^{-}$	–2.33
$AlF_6^{3-} + 3\ e \rightleftharpoons Al + 6\ F^{-}$	–2.069
$Am^{4+} + e \rightleftharpoons Am^{3+}$	2.60
$Am^{2+} + 2\ e \rightleftharpoons Am$	–1.9
$Am^{3+} + 3\ e \rightleftharpoons Am$	–2.048
$Am^{3+} + e \rightleftharpoons Am^{2+}$	–2.3
$As + 3\ H^{+} + 3\ e \rightleftharpoons AsH_3$	–0.608
$As_2O_3 + 6\ H^{+} + 6\ e \rightleftharpoons 2\ As + 3\ H_2O$	0.234
$HAsO_2 + 3\ H^{+} + 3\ e \rightleftharpoons As + 2\ H_2O$	0.248
$AsO_2^{-} + 2\ H_2O + 3\ e \rightleftharpoons As + 4\ OH^{-}$	–0.68
$H_3AsO_4 + 2\ H^{+} + 2\ e^{-} \rightleftharpoons HAsO_2 + 2\ H_2O$	0.560
$AsO_4^{3-} + 2\ H_2O + 2\ e \rightleftharpoons AsO_2^{-} + 4\ OH^{-}$	–0.71
$At_2 + 2\ e \rightleftharpoons 2\ At^{-}$	0.3
$Au^{+} + e \rightleftharpoons Au$	1.692
$Au^{3+} + 2\ e \rightleftharpoons Au^{+}$	1.401
$Au^{3+} + 3\ e \rightleftharpoons Au$	1.498
$Au^{2+} + e^{-} \rightleftharpoons Au^{+}$	1.8
$AuOH^{2+} + H^{+} + 2\ e \rightleftharpoons Au^{+} + H_2O$	1.32
$AuBr_2^{-} + e \rightleftharpoons Au + 2\ Br^{-}$	0.959
$AuBr_4^{-} + 3\ e \rightleftharpoons Au + 4\ Br^{-}$	0.854
$AuCl_4^{-} + 3\ e \rightleftharpoons Au + 4\ Cl^{-}$	1.002
$Au(OH)_3 + 3\ H^{+} + 3\ e \rightleftharpoons Au + 3\ H_2O$	1.45
$H_2BO_3^{-} + 5\ H_2O + 8\ e \rightleftharpoons BH_4^{-} + 8\ OH^{-}$	–1.24
$H_2BO_3^{-} + H_2O + 3\ e \rightleftharpoons B + 4\ OH^{-}$	–1.79
$H_3BO_3 + 3\ H^{+} + 3\ e \rightleftharpoons B + 3\ H_2O$	–0.8698
$B(OH)_3 + 7\ H^{+} + 8\ e \rightleftharpoons BH_4^{-} + 3\ H_2O$	–0.481
$Ba^{2+} + 2\ e \rightleftharpoons Ba$	–2.912
$Ba^{2+} + 2\ e \rightleftharpoons Ba(Hg)$	–1.570
$Ba(OH)_2 + 2\ e \rightleftharpoons Ba + 2\ OH^{-}$	–2.99
$Be^{2+} + 2\ e \rightleftharpoons Be$	–1.847
$Be_2O_3^{2-} + 3\ H_2O + 4\ e \rightleftharpoons 2\ Be + 6\ OH^{-}$	–2.63
p–benzoquinone + $2\ H^{+} + 2\ e \rightleftharpoons$ hydroquinone	0.6992
$Bi^{+} + e \rightleftharpoons Bi$	0.5
$Bi^{3+} + 3\ e \rightleftharpoons Bi$	0.308
$Bi^{3+} + 2\ e \rightleftharpoons Bi^{+}$	0.2
$Bi + 3\ H^{+} + 3\ e \rightleftharpoons BiH_3$	–0.8
$BiCl_4^{-} + 3\ e \rightleftharpoons Bi + 4\ Cl^{-}$	0.16
$Bi_2O_3 + 3\ H_2O + 6\ e \rightleftharpoons 2\ Bi + 6\ OH^{-}$	–0.46
$Bi_2O_4 + 4\ H^{+} + 2\ e \rightleftharpoons 2\ BiO^{+} + 2\ H_2O$	1.593
$BiO^{+} + 2\ H^{+} + 3\ e \rightleftharpoons Bi + H_2O$	0.320
$BiOCl + 2\ H^{+} + 3\ e \rightleftharpoons Bi + Cl^{-} + H_2O$	0.1583
$Bk^{4+} + e \rightleftharpoons Bk^{3+}$	1.67
$Bk^{2+} + 2\ e \rightleftharpoons Bk$	–1.6
$Bk^{3+} + e \rightleftharpoons Bk^{2+}$	–2.8

Reaction	E°/V
$Br_2(aq) + 2\,e \rightleftharpoons 2\,Br^-$	1.0873
$Br_2(l) + 2\,e \rightleftharpoons 2\,Br^-$	1.066
$HBrO + H^+ + 2\,e \rightleftharpoons Br^- + H_2O$	1.331
$HBrO + H^+ + e \rightleftharpoons 1/2\,Br_2(aq) + H_2O$	1.574
$HBrO + H^+ + e \rightleftharpoons 1/2\,Br_2(l) + H_2O$	1.596
$BrO^- + H_2O + 2\,e \rightleftharpoons Br^- + 2\,OH^-$	0.761
$BrO_3^- + 6\,H^+ + 5\,e \rightleftharpoons 1/2\,Br_2 + 3\,H_2O$	1.482
$BrO_3^- + 6\,H^+ + 6\,e \rightleftharpoons Br^- + 3\,H_2O$	1.423
$BrO_3^- + 3\,H_2O + 6\,e \rightleftharpoons Br^- + 6\,OH^-$	0.61
$(CN)_2 + 2\,H^+ + 2\,e \rightleftharpoons 2\,HCN$	0.373
$2\,HCNO + 2\,H^+ + 2\,e \rightleftharpoons (CN)_2 + 2\,H_2O$	0.330
$(CNS)_2 + 2\,e \rightleftharpoons 2\,CNS^-$	0.77
$CO_2 + 2\,H^+ + 2\,e \rightleftharpoons HCOOH$	−0.199
$Ca^+ + e \rightleftharpoons Ca$	−3.80
$Ca^{2+} + 2\,e \rightleftharpoons Ca$	−2.868
$Ca(OH)_2 + 2\,e \rightleftharpoons Ca + 2\,OH^-$	−3.02
Calomel electrode, 1 molal KCl	0.2800
Calomel electrode, 1 molar KCl (NCE)	0.2801
Calomel electrode, 0.1 molar KCl	0.3337
Calomel electrode, saturated KCl (SCE)	0.2412
Calomel electrode, saturated NaCl (SSCE)	0.2360
$Cd^{2+} + 2\,e \rightleftharpoons Cd$	−0.4030
$Cd^{2+} + 2\,e \rightleftharpoons Cd(Hg)$	−0.3521
$Cd(OH)_2 + 2\,e \rightleftharpoons Cd(Hg) + 2\,OH^-$	−0.809
$CdSO_4 + 2\,e \rightleftharpoons Cd + SO_4^{2-}$	−0.246
$Cd(OH)_4^{2-} + 2\,e \rightleftharpoons Cd + 4\,OH^-$	−0.658
$CdO + H_2O + 2\,e \rightleftharpoons Cd + 2\,OH^-$	−0.783
$Ce^{3+} + 3\,e \rightleftharpoons Ce$	−2.336
$Ce^{3+} + 3\,e \rightleftharpoons Ce(Hg)$	−1.4373
$Ce^{4+} + e \rightleftharpoons Ce^{3+}$	1.72
$CeOH^{3+} + H^+ + e \rightleftharpoons Ce^{3+} + H_2O$	1.715
$Cf^{4+} + e \rightleftharpoons Cf^{3+}$	3.3
$Cf^{3+} + e \rightleftharpoons Cf^{2+}$	−1.6
$Cf^{3+} + 3\,e \rightleftharpoons Cf$	−1.94
$Cf^{2+} + 2\,e \rightleftharpoons Cf$	−2.12
$Cl_2(g) + 2\,e \rightleftharpoons 2\,Cl^-$	1.35827
$HClO + H^+ + e \rightleftharpoons 1/2\,Cl_2 + H_2O$	1.611
$HClO + H^+ + 2\,e \rightleftharpoons Cl^- + H_2O$	1.482
$ClO^- + H_2O + 2\,e \rightleftharpoons Cl^- + 2\,OH^-$	0.81
$ClO_2 + H^+ + e \rightleftharpoons HClO_2$	1.277
$HClO_2 + 2\,H^+ + 2\,e \rightleftharpoons HClO + H_2O$	1.645
$HClO_2 + 3\,H^+ + 3\,e \rightleftharpoons 1/2\,Cl_2 + 2\,H_2O$	1.628
$HClO_2 + 3\,H^+ + 4\,e \rightleftharpoons Cl^- + 2\,H_2O$	1.570
$ClO_2^- + H_2O + 2\,e \rightleftharpoons ClO^- + 2\,OH^-$	0.66
$ClO_2^- + 2\,H_2O + 4\,e \rightleftharpoons Cl^- + 4\,OH^-$	0.76
$ClO_2(aq) + e \rightleftharpoons ClO_2^-$	0.954
$ClO_3^- + 2\,H^+ + e \rightleftharpoons ClO_2 + H_2O$	1.152
$ClO_3^- + 3\,H^+ + 2\,e \rightleftharpoons HClO_2 + H_2O$	1.214
$ClO_3^- + 6\,H^+ + 5\,e \rightleftharpoons 1/2\,Cl_2 + 3\,H_2O$	1.47
$ClO_3^- + 6\,H^+ + 6\,e \rightleftharpoons Cl^- + 3\,H_2O$	1.451
$ClO_3^- + H_2O + 2\,e \rightleftharpoons ClO_2^- + 2\,OH^-$	0.33
$ClO_3^- + 3\,H_2O + 6\,e \rightleftharpoons Cl^- + 6\,OH^-$	0.62
$ClO_4^- + 2\,H^+ + 2\,e \rightleftharpoons ClO_3^-\,H_2O$	1.189
$ClO_4^- + 8\,H^+ + 7\,e \rightleftharpoons 1/2\,Cl_2 + 4\,H_2O$	1.39
$ClO_4^- + 8\,H^+ + 8\,e \rightleftharpoons Cl^- + 4\,H_2O$	1.389
$ClO_4^- + H_2O + 2\,e \rightleftharpoons ClO_3^- + 2\,OH^-$	0.36
$Cm^{4+} + e \rightleftharpoons Cm^{3+}$	3.0
$Cm^{3+} + 3\,e \rightleftharpoons Cm$	−2.04
$Co^{2+} + 2\,e \rightleftharpoons Co$	−0.28
$Co^{3+} + e \rightleftharpoons Co^{2+}$	1.92
$[Co(NH_3)_6]^{3+} + e \rightleftharpoons [Co(NH_3)_6]^{2+}$	0.108
$Co(OH)_2 + 2\,e \rightleftharpoons Co + 2\,OH^-$	−0.73
$Co(OH)_3 + e \rightleftharpoons Co(OH)_2 + OH^-$	0.17
$Cr^{2+} + 2\,e \rightleftharpoons Cr$	−0.913
$Cr^{3+} + e \rightleftharpoons Cr^{2+}$	−0.407
$Cr^{3+} + 3\,e \rightleftharpoons Cr$	−0.744
$Cr_2O_7^{2-} + 14\,H^+ + 6\,e \rightleftharpoons 2\,Cr^{3+} + 7\,H_2O$	1.232
$CrO_2^- + 2\,H_2O + 3\,e \rightleftharpoons Cr + 4\,OH^-$	−1.2
$HCrO_4^- + 7\,H^+ + 3\,e \rightleftharpoons Cr^{3+} + 4\,H_2O$	1.350
$CrO_2 + 4\,H^+ + e \rightleftharpoons Cr^{3+} + 2H_2O$	1.48
$Cr(V) + e \rightleftharpoons Cr(IV)$	1.34
$CrO_4^{2-} + 4\,H_2O + 3\,e \rightleftharpoons Cr(OH)_3 + 5\,OH^-$	−0.13
$Cr(OH)_3 + 3\,e \rightleftharpoons Cr + 3\,OH^-$	−1.48
$Cs^+ + e \rightleftharpoons Cs$	−3.026
$Cu^+ + e \rightleftharpoons Cu$	0.521
$Cu^{2+} + e \rightleftharpoons Cu^+$	0.153
$Cu^{2+} + 2\,e \rightleftharpoons Cu$	0.3419
$Cu^{2+} + 2\,e \rightleftharpoons Cu(Hg)$	0.345
$Cu^{3+} + e \rightleftharpoons Cu^{2+}$	2.4
$Cu_2O_3 + 6\,H^+ + 2e \rightleftharpoons 2Cu^{2+} + 3\,H_2O$	2.0
$Cu^{2+} + 2\,CN^- + e \rightleftharpoons [Cu(CN)_2]^-$	1.103
$CuI_2^- + e \rightleftharpoons Cu + 2\,I^-$	0.00
$Cu_2O + H_2O + 2\,e \rightleftharpoons 2\,Cu + 2\,OH^-$	−0.360
$Cu(OH)_2 + 2\,e \rightleftharpoons Cu + 2\,OH^-$	−0.222
$2\,Cu(OH)_2 + 2\,e \rightleftharpoons Cu_2O + 2\,OH^- + H_2O$	−0.080
$2\,D^+ + 2\,e \rightleftharpoons D_2$	−0.013
$Dy^{2+} + 2\,e \rightleftharpoons Dy$	−2.2
$Dy^{3+} + 3\,e \rightleftharpoons Dy$	−2.295
$Dy^{3+} + e \rightleftharpoons Dy^{2+}$	−2.6
$Er^{2+} + 2\,e \rightleftharpoons Er$	−2.0
$Er^{3+} + 3\,e \rightleftharpoons Er$	−2.331
$Er^{3+} + e \rightleftharpoons Er^{2+}$	−3.0
$Es^{3+} + e \rightleftharpoons Es^{2+}$	−1.3
$Es^{3+} + 3\,e \rightleftharpoons Es$	−1.91
$Es^{2+} + 2\,e \rightleftharpoons Es$	−2.23
$Eu^{2+} + 2\,e \rightleftharpoons Eu$	−2.812
$Eu^{3+} + 3\,e \rightleftharpoons Eu$	−1.991
$Eu^{3+} + e \rightleftharpoons Eu^{2+}$	−0.36
$F_2 + 2\,H^+ + 2\,e \rightleftharpoons 2\,HF$	3.053
$F_2 + 2\,e \rightleftharpoons 2\,F^-$	2.866
$F_2O + 2\,H^+ + 4\,e \rightleftharpoons H_2O + 2\,F^-$	2.153
$Fe^{2+} + 2\,e \rightleftharpoons Fe$	−0.447
$Fe^{3+} + 3\,e \rightleftharpoons Fe$	−0.037
$Fe^{3+} + e \rightleftharpoons Fe^{2+}$	0.771
$2\,HFeO_4^- + 8\,H^+ + 6\,e \rightleftharpoons Fe_2O_3 + 5\,H_2O$	2.09
$HFeO_4^- + 4\,H^+ + 3\,e \rightleftharpoons FeOOH + 2\,H_2O$	2.08
$HFeO_4^- + 7\,H^+ + 3\,e \rightleftharpoons Fe^{3+} + 4\,H_2O$	2.07
$Fe_2O_3 + 4\,H^+ + 2\,e \rightleftharpoons 2\,FeOH^+ + H_2O$	0.16
$[Fe(CN)_6]^{3-} + e \rightleftharpoons [Fe(CN)_6]^{4-}$	0.358
$FeO_4^{2-} + 8\,H^+ + 3\,e \quad Fe^{3+} + 4\,H_2O$	2.20
$[Fe(bipy)_2]^{3+} + e \rightleftharpoons Fe(bipy)_2]^{2+}$	0.78
$[Fe(bipy)_3]^{3+} + e \rightleftharpoons Fe(bipy)_3]^{2+}$	1.03
$Fe(OH)_3 + e \rightleftharpoons Fe(OH)_2 + OH^-$	−0.56
$[Fe(phen)_3]^{3+} + e \rightleftharpoons [Fe(phen)_3]^{2+}$	1.147
$[Fe(phen)_3]^{3+} + e \rightleftharpoons [Fe(phen)_3]^{2+}$ (1 molar H_2SO_4)	1.06
[Ferricinium]$^+ + e \rightleftharpoons$ ferrocene	0.400
$Fm^{3+} + e \rightleftharpoons Fm^{2+}$	−1.1
$Fm^{3+} + 3\,e \rightleftharpoons Fm$	−1.89
$Fm^{2+} + 2\,e \rightleftharpoons Fm$	−2.30

Reaction	E°/V
$Fr^+ + e \rightleftharpoons Fr$	−2.9
$Ga^{3+} + 3\,e \rightleftharpoons Ga$	−0.549
$Ga^+ + e \rightleftharpoons Ga$	−0.2
$GaOH^{2+} + H^+ + 3\,e \rightleftharpoons Ga + H_2O$	−0.498
$H_2GaO_3^- + H_2O + 3\,e \rightleftharpoons Ga + 4\,OH^-$	−1.219
$Gd^{3+} + 3\,e \rightleftharpoons Gd$	−2.279
$Ge^{2+} + 2\,e \rightleftharpoons Ge$	0.24
$Ge^{4+} + 4\,e \rightleftharpoons Ge$	0.124
$Ge^{4+} + 2\,e \rightleftharpoons Ge^{2+}$	0.00
$GeO_2 + 2\,H^+ + 2\,e \rightleftharpoons GeO + H_2O$	−0.118
$H_2GeO_3 + 4\,H^+ + 4\,e \rightleftharpoons Ge + 3\,H_2O$	−0.182
$2\,H^+ + 2\,e \rightleftharpoons H_2$	0.00000
$H_2 + 2\,e \rightleftharpoons 2\,H^-$	−2.23
$HO_2 + H^+ + e \rightleftharpoons H_2O_2$	1.495
$2\,H_2O + 2\,e \rightleftharpoons H_2 + 2\,OH^-$	−0.8277
$H_2O_2 + 2\,H^+ + 2\,e \rightleftharpoons 2\,H_2O$	1.776
$Hf^{4+} + 4\,e \rightleftharpoons Hf$	−1.55
$HfO^{2+} + 2\,H^+ + 4\,e \rightleftharpoons Hf + H_2O$	−1.724
$HfO_2 + 4\,H^+ + 4\,e \rightleftharpoons Hf + 2\,H_2O$	−1.505
$HfO(OH)_2 + H_2O + 4\,e \rightleftharpoons Hf + 4\,OH^-$	−2.50
$Hg^{2+} + 2\,e \rightleftharpoons Hg$	0.851
$2\,Hg^{2+} + 2\,e \rightleftharpoons Hg_2^{2+}$	0.920
$Hg_2^{2+} + 2\,e \rightleftharpoons 2\,Hg$	0.7973
$Hg_2(ac)_2 + 2\,e \rightleftharpoons 2\,Hg + 2(ac)^-$	0.51163
$Hg_2Br_2 + 2\,e \rightleftharpoons 2\,Hg + 2\,Br^-$	0.13923
$Hg_2Cl_2 + 2\,e \rightleftharpoons 2\,Hg + 2\,Cl^-$	0.26808
$Hg_2HPO_4 + 2\,e \rightleftharpoons 2\,Hg + HPO_4^{2-}$	0.6359
$Hg_2I_2 + 2\,e \rightleftharpoons 2\,Hg + 2\,I^-$	−0.0405
$Hg_2O + H_2O + 2\,e \rightleftharpoons 2\,Hg + 2\,OH^-$	0.123
$HgO + H_2O + 2\,e \rightleftharpoons Hg + 2\,OH^-$	0.0977
$Hg(OH)_2 + 2\,H^+ + 2\,e \rightleftharpoons Hg + 2\,H_2O$	1.034
$Hg_2SO_4 + 2\,e \rightleftharpoons 2\,Hg + SO_4^{2-}$	0.6125
$Ho^{2+} + 2\,e \rightleftharpoons Ho$	−2.1
$Ho^{3+} + 3\,e \rightleftharpoons Ho$	−2.33
$Ho^{3+} + e \rightleftharpoons Ho^{2+}$	−2.8
$I_2 + 2\,e \rightleftharpoons 2\,I^-$	0.5355
$I_3^- + 2\,e \rightleftharpoons 3\,I^-$	0.536
$H_3IO_6^{2-} + 2\,e \rightleftharpoons IO_3^- + 3\,OH^-$	0.7
$H_5IO_6 + H^+ + 2\,e \rightleftharpoons IO_3^- + 3\,H_2O$	1.601
$2\,HIO + 2\,H^+ + 2\,e \rightleftharpoons I_2 + 2\,H_2O$	1.439
$HIO + H^+ + 2\,e \rightleftharpoons I^- + H_2O$	0.987
$IO^- + H_2O + 2\,e \rightleftharpoons I^- + 2\,OH^-$	0.485
$2\,IO_3^- + 12\,H^+ + 10\,e \rightleftharpoons I_2 + 6\,H_2O$	1.195
$IO_3^- + 6\,H^+ + 6\,e \rightleftharpoons I^- + 3\,H_2O$	1.085
$IO_3^- + 2\,H_2O + 4\,e \rightleftharpoons IO^- + 4\,OH^-$	0.15
$IO_3^- + 3\,H_2O + 6\,e \rightleftharpoons IO^- + 6\,OH^-$	0.26
$In^+ + e \rightleftharpoons In$	−0.14
$In^{2+} + e \rightleftharpoons In^+$	−0.40
$In^{3+} + e \rightleftharpoons In^{2+}$	−0.49
$In^{3+} + 2\,e \rightleftharpoons In^+$	−0.443
$In^{3+} + 3\,e \rightleftharpoons In$	−0.3382
$In(OH)_3 + 3\,e \rightleftharpoons In + 3\,OH^-$	−0.99
$In(OH)_4^- + 3\,e \rightleftharpoons In + 4\,OH^-$	−1.007
$In_2O_3 + 3\,H_2O + 6\,e \rightleftharpoons 2\,In + 6\,OH^-$	−1.034
$Ir^{3+} + 3\,e \rightleftharpoons Ir$	1.156
$[IrCl_6]^{2-} + e \rightleftharpoons [IrCl_6]^{3-}$	0.8665
$[IrCl_6]^{3-} + 3\,e \rightleftharpoons Ir + 6\,Cl^-$	0.77
$Ir_2O_3 + 3\,H_2O + 6\,e \rightleftharpoons 2\,Ir + 6\,OH^-$	0.098
$K^+ + e \rightleftharpoons K$	−2.931

Reaction	E°/V
$La^{3+} + 3\,e \rightleftharpoons La$	−2.379
$La(OH)_3 + 3\,e \rightleftharpoons La + 3\,OH^-$	−2.90
$Li^+ + e \rightleftharpoons Li$	−3.0401
$Lr^{3+} + 3\,e \rightleftharpoons Lr$	−1.96
$Lu^{3+} + 3\,e \rightleftharpoons Lu$	−2.28
$Md^{3+} + e \rightleftharpoons Md^{2+}$	−0.1
$Md^{3+} + 3\,e \rightleftharpoons Md$	−1.65
$Md^{2+} + 2\,e \rightleftharpoons Md$	−2.40
$Mg^+ + e \rightleftharpoons Mg$	−2.70
$Mg^{2+} + 2\,e \rightleftharpoons Mg$	−2.372
$Mg(OH)_2 + 2\,e \rightleftharpoons Mg + 2\,OH^-$	−2.690
$Mn^{2+} + 2\,e \rightleftharpoons Mn$	−1.185
$Mn^{3+} + e \rightleftharpoons Mn^{2+}$	1.5415
$MnO_2 + 4\,H^+ + 2\,e \rightleftharpoons Mn^{2+} + 2\,H_2O$	1.224
$MnO_4^- + e \rightleftharpoons MnO_4^{2-}$	0.558
$MnO_4^- + 4\,H^+ + 3\,e \rightleftharpoons MnO_2 + 2\,H_2O$	1.679
$MnO_4^- + 8\,H^+ + 5\,e \rightleftharpoons Mn^{2+} + 4\,H_2O$	1.507
$MnO_4^- + 2\,H_2O + 3\,e \rightleftharpoons MnO_2 + 4\,OH^-$	0.595
$MnO_4^{2-} + 2\,H_2O + 2\,e \rightleftharpoons MnO_2 + 4\,OH^-$	0.60
$Mn(OH)_2 + 2\,e \rightleftharpoons Mn + 2\,OH^-$	−1.56
$Mn(OH)_3 + e \rightleftharpoons Mn(OH)_2 + OH^-$	0.15
$Mn_2O_3 + 6\,H^+ + e \rightleftharpoons 2\,Mn^{2+} + 3\,H_2O$	1.485
$Mo^{3+} + 3\,e \rightleftharpoons Mo$	−0.200
$MoO_2 + 4\,H^+ + 4\,e \rightleftharpoons Mo + 4\,H_2O$	−0.152
$H_3Mo_7O_{24}^{3-} + 45\,H^+ + 42\,e \rightleftharpoons 7\,Mo + 24\,H_2O$	0.082
$MoO_3 + 6\,H^+ + 6\,e \rightleftharpoons Mo + 3\,H_2O$	0.075
$N_2 + 2\,H_2O + 6\,H^+ + 6\,e \rightleftharpoons 2\,NH_4OH$	0.092
$3\,N_2 + 2\,H^+ + 2\,e \rightleftharpoons 2\,HN_3$	−3.09
$N_5^+ + 3\,H^+ + 2\,e \rightleftharpoons 2\,NH_4^+$	1.275
$N_2O + 2\,H^+ + 2\,e \rightleftharpoons N_2 + H_2O$	1.766
$H_2N_2O_2 + 2\,H^+ + 2\,e \rightleftharpoons N_2 + 2\,H_2O$	2.65
$N_2O_4 + 2\,e \rightleftharpoons 2\,NO_2^-$	0.867
$N_2O_4 + 2\,H^+ + 2\,e \rightleftharpoons 2\,NHO_2$	1.065
$N_2O_4 + 4\,H^+ + 4\,e \rightleftharpoons 2\,NO + 2\,H_2O$	1.035
$2\,NH_3OH^+ + H^+ + 2\,e \rightleftharpoons N_2H_5^+ + 2\,H_2O$	1.42
$2\,NO + 2\,H^+ + 2\,e \rightleftharpoons N_2O + H_2O$	1.591
$2\,NO + H_2O + 2\,e \rightleftharpoons N_2O + 2\,OH^-$	0.76
$HNO_2 + H^+ + e \rightleftharpoons NO + H_2O$	0.983
$2\,HNO_2 + 4\,H^+ + 4\,e \rightleftharpoons H_2N_2O_2 + 2\,H_2O$	0.86
$2\,HNO_2 + 4\,H^+ + 4\,e \rightleftharpoons N_2O + 3\,H_2O$	1.297
$NO_2^- + H_2O + e \rightleftharpoons NO + 2\,OH^-$	−0.46
$2\,NO_2^- + 2\,H_2O + 4\,e \rightleftharpoons N_2O_2^{2-} + 4\,OH^-$	−0.18
$2\,NO_2^- + 3\,H_2O + 4\,e \rightleftharpoons N_2O + 6\,OH^-$	0.15
$NO_3^- + 3\,H^+ + 2\,e \rightleftharpoons HNO_2 + H_2O$	0.934
$NO_3^- + 4\,H^+ + 3\,e \rightleftharpoons NO + 2\,H_2O$	0.957
$2\,NO_3^- + 4\,H^+ + 2\,e \rightleftharpoons N_2O_4 + 2\,H_2O$	0.803
$NO_3^- + H_2O + 2\,e \rightleftharpoons NO_2^- + 2\,OH^-$	0.01
$2\,NO_3^- + 2\,H_2O + 2\,e \rightleftharpoons N_2O_4 + 4\,OH^-$	−0.85
$Na^+ + e \rightleftharpoons Na$	−2.71
$Nb^{3+} + 3\,e \rightleftharpoons Nb$	−1.099
$NbO_2 + 2\,H^+ + 2\,e \rightleftharpoons NbO + H_2O$	−0.646
$NbO_2 + 4\,H^+ + 4\,e \rightleftharpoons Nb + 2\,H_2O$	−0.690
$NbO + 2\,H^+ + 2\,e \rightleftharpoons Nb + H_2O$	−0.733
$Nb_2O_5 + 10\,H^+ + 10\,e \rightleftharpoons 2\,Nb + 5\,H_2O$	−0.644
$Nd^{3+} + 3\,e \rightleftharpoons Nd$	−2.323
$Nd^{2+} + 2\,e \rightleftharpoons Nd$	−2.1
$Nd^{3+} + e \rightleftharpoons Nd^{2+}$	−2.7
$Ni^{2+} + 2\,e \rightleftharpoons Ni$	−0.257
$Ni(OH)_2 + 2\,e \rightleftharpoons Ni + 2\,OH^-$	−0.72

Reaction	E°/V
$NiO_2 + 4\,H^+ + 2\,e \rightleftharpoons Ni^{2+} + 2\,H_2O$	1.678
$NiO_2 + 2\,H_2O + 2\,e \rightleftharpoons Ni(OH)_2 + 2\,OH^-$	−0.490
$No^{3+} + e \rightleftharpoons No^{2+}$	1.4
$No^{3+} + 3\,e \rightleftharpoons No$	−1.20
$No^{2+} + 2\,e \rightleftharpoons No$	−2.50
$Np^{3+} + 3\,e \rightleftharpoons Np$	−1.856
$Np^{4+} + e \rightleftharpoons Np^{3+}$	0.147
$NpO_2 + H_2O + H^+ + e \rightleftharpoons Np(OH)_3$	−0.962
$O_2 + 2\,H^+ + 2\,e \rightleftharpoons H_2O_2$	0.695
$O_2 + 4\,H^+ + 4\,e \rightleftharpoons 2\,H_2O$	1.229
$O_2 + H_2O + 2\,e \rightleftharpoons HO_2^- + OH^-$	−0.076
$O_2 + 2\,H_2O + 2\,e \rightleftharpoons H_2O_2 + 2\,OH^-$	−0.146
$O_2 + 2\,H_2O + 4\,e \rightleftharpoons 4\,OH^-$	0.401
$O_3 + 2\,H^+ + 2\,e \rightleftharpoons O_2 + H_2O$	2.076
$O_3 + H_2O + 2\,e \rightleftharpoons O_2 + 2\,OH^-$	1.24
$O(g) + 2\,H^+ + 2\,e \rightleftharpoons H_2O$	2.421
$OH + e \rightleftharpoons OH^-$	2.02
$HO_2^- + H_2O + 2\,e \rightleftharpoons 3\,OH^-$	0.878
$OsO_4 + 8\,H^+ + 8\,e \rightleftharpoons Os + 4\,H_2O$	0.838
$OsO_4 + 4\,H^+ + 4\,e \rightleftharpoons OsO_2 + 2\,H_2O$	1.02
$[Os(bipy)_2]^{3+} + e \rightleftharpoons [Os(bipy)_2]^{2+}$	0.81
$[Os(bipy)_3]^{3+} + e \rightleftharpoons [Os(bipy)_3]^{2+}$	0.80
$P(red) + 3\,H^+ + 3\,e \rightleftharpoons PH_3(g)$	−0.111
$P(white) + 3\,H^+ + 3\,e \rightleftharpoons PH_3(g)$	−0.063
$P + 3\,H_2O + 3\,e \rightleftharpoons PH_3(g) + 3\,OH^-$	−0.87
$H_2P_2^- + e \rightleftharpoons P + 2\,OH^-$	−1.82
$H_3PO_2 + H^+ + e \rightleftharpoons P + 2\,H_2O$	−0.508
$H_3PO_3 + 2\,H^+ + 2\,e \rightleftharpoons H_3PO_2 + H_2O$	−0.499
$H_3PO_3 + 3\,H^+ + 3\,e \rightleftharpoons P + 3\,H_2O$	−0.454
$HPO_3^{2-} + 2\,H_2O + 2\,e \rightleftharpoons H_2PO_2^- + 3\,OH^-$	−1.65
$HPO_3^{2-} + 2\,H_2O + 3\,e \rightleftharpoons P + 5\,OH^-$	−1.71
$H_3PO_4 + 2\,H^+ + 2\,e \rightleftharpoons H_3PO_3 + H_2O$	−0.276
$PO_4^{3-} + 2\,H_2O + 2\,e \rightleftharpoons HPO_3^{2-} + 3\,OH^-$	−1.05
$Pa^{3+} + 3\,e \rightleftharpoons Pa$	−1.34
$Pa^{4+} + 4\,e \rightleftharpoons Pa$	−1.49
$Pa^{4+} + e \rightleftharpoons Pa^{3+}$	−1.9
$Pb^{2+} + 2\,e \rightleftharpoons Pb$	−0.1262
$Pb^{2+} + 2\,e \rightleftharpoons Pb(Hg)$	−0.1205
$PbBr_2 + 2\,e \rightleftharpoons Pb + 2\,Br^-$	−0.284
$PbCl_2 + 2\,e \rightleftharpoons Pb + 2\,Cl^-$	−0.2675
$PbF_2 + 2\,e \rightleftharpoons Pb + 2\,F^-$	−0.3444
$PbHPO_4 + 2\,e \rightleftharpoons Pb + HPO_4^{2-}$	−0.465
$PbI_2 + 2\,e \rightleftharpoons Pb + 2\,I^-$	−0.365
$PbO + H_2O + 2\,e \rightleftharpoons Pb + 2\,OH^-$	−0.580
$PbO_2 + 4\,H^+ + 2\,e \rightleftharpoons Pb^{2+} + 2\,H_2O$	1.455
$HPbO_2^- + H_2O + 2\,e \rightleftharpoons Pb + 3\,OH^-$	−0.537
$PbO_2 + H_2O + 2\,e \rightleftharpoons PbO + 2\,OH^-$	0.247
$PbO_2 + SO_4^{2-} + 4\,H^+ + 2\,e \rightleftharpoons PbSO_4 + 2\,H_2O$	1.6913
$PbSO_4 + 2\,e \rightleftharpoons Pb + SO_4^{2-}$	−0.3588
$PbSO_4 + 2\,e \rightleftharpoons Pb(Hg) + SO_4^{2-}$	−0.3505
$Pd^{2+} + 2\,e \rightleftharpoons Pd$	0.951
$[PdCl_4]^{2-} + 2\,e \rightleftharpoons Pd + 4\,Cl^-$	0.591
$[PdCl_6]^{2-} + 2\,e \rightleftharpoons [PdCl_4]^{2-} + 2\,Cl^-$	1.288
$Pd(OH)_2 + 2\,e \rightleftharpoons Pd + 2\,OH^-$	0.07
$Pm^{2+} + 2\,e \rightleftharpoons Pm$	−2.2
$Pm^{3+} + 3\,e \rightleftharpoons Pm$	−2.30
$Pm^{3+} + e \rightleftharpoons Pm^{2+}$	−2.6
$Po^{4+} + 2\,e \rightleftharpoons Po^{2+}$	0.9
$Po^{4+} + 4\,e \rightleftharpoons Po$	0.76

Reaction	E°/V
$Pr^{4+} + e \rightleftharpoons Pr^{3+}$	3.2
$Pr^{2+} + 2\,e \rightleftharpoons Pr$	−2.0
$Pr^{3+} + 3\,e \rightleftharpoons Pr$	−2.353
$Pr^{3+} + e \rightleftharpoons Pr^{2+}$	−3.1
$Pt^{2+} + 2\,e \rightleftharpoons Pt$	1.18
$[PtCl_4]^{2-} + 2\,e \rightleftharpoons Pt + 4\,Cl^-$	0.755
$[PtCl_6]^{2-} + 2\,e \rightleftharpoons [PtCl_4]^{2-} + 2\,Cl^-$	0.68
$Pt(OH)_2 + 2\,e \rightleftharpoons Pt + 2\,OH^-$	0.14
$PtO_3 + 2\,H^+ + 2\,e \rightleftharpoons PtO_2 + H_2O$	1.7
$PtO_3 + 4\,H^+ + 2\,e \rightleftharpoons Pt(OH)_2^{2+} + H_2O$	1.5
$PtOH^+ + H^+ + 2\,e \rightleftharpoons Pt + H_2O$	1.2
$PtO_2 + 2\,H^+ + 2\,e \rightleftharpoons PtO + H_2O$	1.01
$PtO_2 + 4\,H^+ + 4\,e \rightleftharpoons Pt + 2\,H_2O$	1.00
$Pu^{3+} + 3\,e \rightleftharpoons Pu$	−2.031
$Pu^{4+} + e \rightleftharpoons Pu^{3+}$	1.006
$Pu^{5+} + e \rightleftharpoons Pu^{4+}$	1.099
$PuO_2(OH)_2 + 2\,H^+ + 2\,e \rightleftharpoons Pu(OH)_4$	1.325
$PuO_2(OH)_2 + H^+ + e \rightleftharpoons PuO_2OH + H_2O$	1.062
$Ra^{2+} + 2\,e \rightleftharpoons Ra$	−2.8
$Rb^+ + e \rightleftharpoons Rb$	−2.98
$Re^{3+} + 3\,e \rightleftharpoons Re$	0.300
$ReO_4^- + 4\,H^+ + 3\,e \rightleftharpoons ReO_2 + 2\,H_2O$	0.510
$ReO_2 + 4\,H^+ + 4\,e \rightleftharpoons Re + 2\,H_2O$	0.2513
$ReO_4^- + 2\,H^+ + e \rightleftharpoons ReO_3 + H_2O$	0.768
$ReO_4^- + 4\,H_2O + 7\,e \rightleftharpoons Re + 8\,OH^-$	−0.584
$ReO_4^- + 8\,H^+ + 7\,e \rightleftharpoons Re + 4\,H_2O$	0.368
$Rh^+ + e \rightleftharpoons Rh$	0.600
$Rh^+ + 2e \rightleftharpoons Rh$	0.600
$Rh^{3+} + 3\,e \rightleftharpoons Rh$	0.758
$[RhCl_6]^{3-} + 3\,e \rightleftharpoons Rh + 6\,Cl^-$	0.431
$RhOH^{2+} + H^+ + 3\,e \rightleftharpoons Rh + H_2O$	0.83
$Ru^{2+} + 2\,e \rightleftharpoons Ru$	0.455
$Ru^{3+} + e \rightleftharpoons Ru^{2+}$	0.2487
$RuO_2 + 4\,H^+ + 2\,e \rightleftharpoons Ru^{2+} + 2\,H_2O$	1.120
$RuO_4^- + e \rightleftharpoons RuO_4^{2-}$	0.59
$RuO_4 + e \rightleftharpoons RuO_4^-$	1.00
$RuO_4 + 6\,H^+ + 4\,e \rightleftharpoons Ru(OH)_2^{2+} + 2\,H_2O$	1.40
$RuO_4 + 8\,H^+ + 8\,e \rightleftharpoons Ru + 4\,H_2O$	1.038
$[Ru(bipy)_3)^{3+} + e^- \rightleftharpoons [Ru(bipy)_3]^{2+}$	1.24
$[Ru(H_2O)_6]^{3+} + e^- \rightleftharpoons [Ru(H_2O)_6]^{2+}$	0.23
$[Ru(NH_3)_6]^{3+} + e^- \rightleftharpoons [Ru(NH_3)_6]^{2+}$	0.10
$[Ru(en)_3]^{3+} + e^- \rightleftharpoons [Ru(en)_3]^{2+}$	0.210
$[Ru(CN)_6]^{3-} + e^- \rightleftharpoons [Ru(CN)_6]^{4-}$	0.86
$S + 2\,e \rightleftharpoons S^{2-}$	−0.47627
$S + 2H^+ + 2\,e \rightleftharpoons H_2S(aq)$	0.142
$S + H_2O + 2\,e \rightleftharpoons SH^- + OH^-$	−0.478
$2\,S + 2\,e \rightleftharpoons S_2^{2-}$	−0.42836
$S_2O_6^{2-} + 4\,H^+ + 2\,e \rightleftharpoons 2\,H_2SO_3$	0.564
$S_2O_8^{2-} + 2\,e \rightleftharpoons 2\,SO_4^{2-}$	2.010
$S_2O_8^{2-} + 2\,H^+ + 2\,e \rightleftharpoons 2\,HSO_4^-$	2.123
$S_4O_6^{2-} + 2\,e \rightleftharpoons 2\,S_2O_3^{2-}$	0.08
$2\,H_2SO_3 + H^+ + 2\,e \rightleftharpoons HS_2O_4^- + 2\,H_2O$	−0.056
$H_2SO_3 + 4\,H^+ + 4\,e \rightleftharpoons S + 3\,H_2O$	0.449
$2\,SO_3^{2-} + 2\,H_2O + 2\,e \rightleftharpoons S_2O_4^{2-} + 4\,OH^-$	−1.12
$2\,SO_3^{2-} + 3\,H_2O + 4\,e \rightleftharpoons S_2O_3^{2-} + 6\,OH^-$	−0.571
$SO_4^{2-} + 4\,H^+ + 2\,e \rightleftharpoons H_2SO_3 + H_2O$	0.172
$2\,SO_4^{2-} + 4\,H^+ + 2\,e \rightleftharpoons S_2O_6^{2-} + H_2O$	−0.22
$SO_4^{2-} + H_2O + 2\,e \rightleftharpoons SO_3^{2-} + 2\,OH^-$	−0.93
$Sb + 3\,H^+ + 3\,e \rightleftharpoons SbH_3$	−0.510

Reaction	E°/V
$Sb_2O_3 + 6\ H^+ + 6\ e \rightleftharpoons 2\ Sb + 3\ H_2O$	0.152
Sb_2O_5 (senarmontite) $+ 4\ H^+ + 4\ e \rightleftharpoons Sb_2O_3 + 2\ H_2O$	0.671
Sb_2O_5 (valentinite) $+ 4\ H^+ + 4\ e \rightleftharpoons Sb_2O_3 + 2\ H_2O$	0.649
$Sb_2O_5 + 6\ H^+ + 4\ e \rightleftharpoons 2\ SbO^+ + 3\ H_2O$	0.581
$SbO^+ + 2\ H^+ + 3\ e \rightleftharpoons Sb + 2\ H_2O$	0.212
$SbO_2^- + 2\ H_2O + 3\ e \rightleftharpoons Sb + 4\ OH^-$	−0.66
$SbO_3^- + H_2O + 2\ e \rightleftharpoons SbO_2^- + 2\ OH^-$	−0.59
$Sc^{3+} + 3\ e \rightleftharpoons Sc$	−2.077
$Se + 2\ e \rightleftharpoons Se^{2-}$	−0.924
$Se + 2\ H^+ + 2\ e \rightleftharpoons H_2Se(aq)$	−0.399
$H_2SeO_3 + 4\ H^+ + 4\ e \rightleftharpoons Se + 3\ H_2O$	0.74
$Se + 2\ H^+ + 2\ e \rightleftharpoons H_2Se$	−0.082
$SeO_3^{2-} + 3\ H_2O + 4\ e \rightleftharpoons Se + 6\ OH^-$	−0.366
$SeO_4^{2-} + 4\ H^+ + 2\ e \rightleftharpoons H_2SeO_3 + H_2O$	1.151
$SeO_4^{2-} + H_2O + 2\ e \rightleftharpoons SeO_3^{2-} + 2\ OH^-$	0.05
$SiF_6^{2-} + 4\ e \rightleftharpoons Si + 6\ F^-$	−1.24
$SiO + 2\ H^+ + 2\ e \rightleftharpoons Si + H_2O$	−0.8
SiO_2 (quartz) $+ 4\ H^+ + 4\ e \rightleftharpoons Si + 2\ H_2O$	0.857
$SiO_3^{2-} + 3\ H_2O + 4\ e \rightleftharpoons Si + 6\ OH^-$	−1.697
$Sm^{3+} + e \rightleftharpoons Sm^{2+}$	−1.55
$Sm^{3+} + 3\ e \rightleftharpoons Sm$	−2.304
$Sm^{2+} + 2\ e \rightleftharpoons Sm$	−2.68
$Sn^{2+} + 2\ e \rightleftharpoons Sn$	−0.1375
$Sn^{4+} + 2\ e _ Sn^{2+}$	0.151
$Sn(OH)_3^+ + 3\ H^+ + 2\ e \rightleftharpoons Sn^{2+} + 3\ H_2O$	0.142
$SnO_2 + 4\ H^+ + 2\ e^- \rightleftharpoons Sn^{2+} + 2\ H_2O$	−0.094
$SnO_2 + 4\ H^+ + 4\ e \rightleftharpoons Sn + 2\ H_2O$	−0.117
$SnO_2 + 3\ H^+ + 2\ e \rightleftharpoons SnOH^+ + H_2O$	−0.194
$SnO_2 + 2\ H_2O + 4\ e \rightleftharpoons Sn + 4\ OH^-$	−0.945
$HSnO_2^- + H_2O + 2\ e \rightleftharpoons Sn + 3\ OH^-$	−0.909
$Sn(OH)_6^{2-} + 2\ e \rightleftharpoons HSnO_2^- + 3\ OH^- + H_2O$	−0.93
$Sr^+ + e \rightleftharpoons Sr$	−4.10
$Sr^{2+} + 2\ e \rightleftharpoons Sr$	−2.899
$Sr^{2+} + 2\ e \rightleftharpoons Sr(Hg)$	−1.793
$Sr(OH)_2 + 2\ e \rightleftharpoons Sr + 2\ OH^-$	−2.88
$Ta_2O_5 + 10\ H^+ + 10\ e \rightleftharpoons 2\ Ta + 5\ H_2O$	−0.750
$Ta^{3+} + 3\ e \rightleftharpoons Ta$	−0.6
$Tc^{2+} + 2\ e \rightleftharpoons Tc$	0.400
$TcO_4^- + 4\ H^+ + 3\ e \rightleftharpoons TcO_2 + 2\ H_2O$	0.782
$Tc^{3+} + e \rightleftharpoons Tc^{2+}$	0.3
$TcO_4^- + 8\ H^+ + 7\ e \rightleftharpoons Tc + 4\ H_2O$	0.472
$Tb^{4+} + e \rightleftharpoons Tb^{3+}$	3.1
$Tb^{3+} + 3\ e \rightleftharpoons Tb$	−2.28
$Te + 2\ e \rightleftharpoons Te^{2-}$	−1.143
$Te + 2\ H^+ + 2\ e \rightleftharpoons H_2Te$	−0.793
$Te^{4+} + 4\ e \rightleftharpoons Te$	0.568
$TeO_2 + 4\ H^+ + 4\ e \rightleftharpoons Te + 2\ H_2O$	0.593
$TeO_3^{2-} + 3\ H_2O + 4\ e \rightleftharpoons Te + 6\ OH^-$	−0.57
$TeO_4^- + 8\ H^+ + 7\ e \rightleftharpoons Te + 4\ H_2O$	0.472
$H_6TeO_6 + 2\ H^+ + 2\ e \rightleftharpoons TeO_2 + 4\ H_2O$	1.02
$Th^{4+} + 4\ e \rightleftharpoons Th$	−1.899
$ThO_2 + 4\ H^+ + 4\ e \rightleftharpoons Th + 2\ H_2O$	−1.789
$Th(OH)_4 + 4\ e \rightleftharpoons Th + 4\ OH^-$	−2.48
$Ti^{2+} + 2\ e \rightleftharpoons Ti$	−1.630
$Ti^{3+} + e \rightleftharpoons Ti^{2+}$	−0.9
$TiO_2 + 4\ H^+ + 2\ e \rightleftharpoons Ti^{2+} + 2\ H_2O$	−0.502

Reaction	E°/V
$Ti^{3+} + 3\ e \rightleftharpoons Ti$	−1.37
$TiOH^{3+} + H^+ + e \rightleftharpoons Ti^{3+} + H_2O$	−0.055
$Tl^+ + e \rightleftharpoons Tl$	−0.336
$Tl^+ + e \rightleftharpoons Tl(Hg)$	−0.3338
$Tl^{3+} + 2\ e \rightleftharpoons Tl^+$	1.252
$Tl^{3+} + 3\ e \rightleftharpoons Tl$	0.741
$TlBr + e \rightleftharpoons Tl + Br^-$	−0.658
$TlCl + e \rightleftharpoons Tl + Cl^-$	−0.5568
$TlI + e \rightleftharpoons Tl + I^-$	−0.752
$Tl_2O_3 + 3\ H_2O + 4\ e \rightleftharpoons 2\ Tl^+ + 6\ OH^-$	0.02
$TlOH + e \rightleftharpoons Tl + OH^-$	−0.34
$Tl(OH)_3 + 2\ e \rightleftharpoons TlOH + 2\ OH^-$	−0.05
$Tl_2SO_4 + 2\ e \rightleftharpoons Tl + SO_4^{2-}$	−0.4360
$Tm^{3+} + e \rightleftharpoons Tm^{2+}$	−2.2
$Tm^{3+} + 3\ e \rightleftharpoons Tm$	−2.319
$Tm^{2+} + 2\ e \rightleftharpoons Tm$	−2.4
$U^{3+} + 3\ e \rightleftharpoons U$	−1.798
$U^{4+} + e \rightleftharpoons U^{3+}$	−0.607
$UO_2^+ + 4\ H^+ + e \rightleftharpoons U^{4+} + 2\ H_2O$	0.612
$UO_2^{2+} + e \rightleftharpoons UO^+_2$	0.062
$UO_2^{2+} + 4\ H^+ + 2\ e \rightleftharpoons U^{4+} + 2\ H_2O$	0.327
$UO_2^{2+} + 4\ H^+ + 6\ e \rightleftharpoons U + 2\ H_2O$	−1.444
$V^{2+} + 2\ e \rightleftharpoons V$	−1.175
$V^{3+} + e \rightleftharpoons V^{2+}$	−0.255
$VO^{2+} + 2\ H^+ + e \rightleftharpoons V^{3+} + H_2O$	0.337
$VO_2^+ + 2\ H^+ + e \rightleftharpoons VO^{2+} + H_2O$	0.991
$V_2O_5 + 6\ H^+ + 2\ e \rightleftharpoons 2\ VO^{2+} + 3\ H_2O$	0.957
$V_2O_5 + 10\ H^+ + 10\ e \rightleftharpoons 2\ V + 5\ H_2O$	−0.242
$V(OH)_4^+ + 2\ H^+ + e \rightleftharpoons VO^{2+} + 3\ H_2O$	1.00
$V(OH)_4^+ + 4\ H^+ + 5\ e \rightleftharpoons V + 4\ H_2O$	−0.254
$[V(phen)_3]^{3+} + e \rightleftharpoons [V(phen)_3]^{2+}$	0.14
$W^{3+} + 3\ e \rightleftharpoons W$	0.1
$W_2O_5 + 2\ H^+ + 2\ e \rightleftharpoons 2\ WO_2 + H_2O$	−0.031
$WO_2 + 4\ H^+ + 4\ e \rightleftharpoons W + 2\ H_2O$	−0.119
$WO_3 + 6\ H^+ + 6\ e \rightleftharpoons W + 3\ H_2O$	−0.090
$WO_3 + 2\ H^+ + 2\ e \rightleftharpoons WO_2 + H_2O$	0.036
$2\ WO_3 + 2\ H^+ + 2\ e \rightleftharpoons W_2O_5 + H_2O$	−0.029
$H_4XeO_6 + 2\ H^+ + 2\ e \rightleftharpoons XeO_3 + 3\ H_2O$	2.42
$XeO_3 + 6\ H^+ + 6\ e \rightleftharpoons Xe + 3\ H_2O$	2.10
$XeF + e \rightleftharpoons Xe + F^-$	3.4
$Y^{3+} + 3\ e \rightleftharpoons Y$	−2.372
$Yb^{3+} + e \rightleftharpoons Yb^{2+}$	−1.05
$Yb^{3+} + 3\ e \rightleftharpoons Yb$	−2.19
$Yb^{2+} + 2\ e \rightleftharpoons Yb$	−2.76
$Zn^{2+} + 2\ e \rightleftharpoons Zn$	−0.7618
$Zn^{2+} + 2\ e \rightleftharpoons Zn(Hg)$	−0.7628
$ZnO_2^{2-} + 2\ H_2O + 2\ e \rightleftharpoons Zn + 4\ OH^-$	−1.215
$ZnSO_4 \cdot 7\ H_2O + 2\ e = Zn(Hg) + SO_4^{2-} + 7\ H_2O$ (Saturated $ZnSO_4$)	−0.7993
$ZnOH^+ + H^+ + 2\ e \rightleftharpoons Zn + H_2O$	−0.497
$Zn(OH)_4^{2-} + 2\ e \rightleftharpoons Zn + 4\ OH^-$	−1.199
$Zn(OH)_2 + 2\ e \rightleftharpoons Zn + 2\ OH^-$	−1.249
$ZnO + H_2O + 2\ e \rightleftharpoons Zn + 2\ OH^-$	−1.260
$ZrO_2 + 4\ H^+ + 4\ e \rightleftharpoons Zr + 2\ H_2O$	−1.553
$ZrO(OH)_2 + H_2O + 4\ e \rightleftharpoons Zr + 4\ OH^-$	−2.36
$Zr^{4+} + 4\ e \rightleftharpoons Zr$	−1.45

TABLE 2. Reduction Reactions Having E° Values More Positive than That of the Standard Hydrogen Electrode

Reaction	E°/V
$2\ H^+ + 2\ e \rightleftharpoons H_2$	0.00000
$CuI_2^- + e \rightleftharpoons Cu + 2\ I^-$	0.00
$Ge^{4+} + 2\ e \rightleftharpoons Ge^{2+}$	0.00
$NO_3^- + H_2O + 2\ e \rightleftharpoons NO_2^- + 2\ OH^-$	0.01
$Tl_2O_3 + 3\ H_2O + 4\ e \rightleftharpoons 2\ Tl^+ + 6\ OH^-$	0.02
$SeO_4^{2-} + H_2O + 2\ e \rightleftharpoons SeO_3^{2-} + 2\ OH^-$	0.05
$WO_3 + 2\ H^+ + 2\ e \rightleftharpoons WO_2 + H_2O$	0.036
$UO_2^{2+} + e = UO_2^+$	0.062
$Pd(OH)_2 + 2\ e \rightleftharpoons Pd + 2\ OH^-$	0.07
$AgBr + e \rightleftharpoons Ag + Br^-$	0.07133
$MoO_3 + 6\ H^+ + 6\ e \rightleftharpoons Mo + 3\ H_2O$	0.075
$S_4O_6^{2-} + 2\ e \rightleftharpoons 2\ S_2O_3^{2-}$	0.08
$H_3Mo_7O_{24}^{3-} + 45\ H^+ + 42\ e \rightleftharpoons 7\ Mo + 24\ H_2O$	0.082
$AgSCN + e \rightleftharpoons Ag + SCN^-$	0.8951
$N_2 + 2\ H_2O + 6\ H^+ + 6\ e \rightleftharpoons 2\ NH_4OH$	0.092
$HgO + H_2O + 2\ e \rightleftharpoons Hg + 2\ OH^-$	0.0977
$Ir_2O_3 + 3\ H_2O + 6\ e \rightleftharpoons 2\ Ir + 6\ OH^-$	0.098
$2\ NO + 2\ e \rightleftharpoons N_2O_2^{2-}$	0.10
$[Ru(NH_3)_6]^{3+} + e \rightleftharpoons [Ru(NH_3)_6]^{2+}$	0.10
$W^{3+} + 3\ e \rightleftharpoons W$	0.1
$[Co(NH_3)_6]^{3+} + e \rightleftharpoons [Co(NH_3)_6]^{2+}$	0.108
$Hg_2O + H_2O + 2\ e \rightleftharpoons 2\ Hg + 2\ OH^-$	0.123
$Ge^{4+} + 4\ e \rightleftharpoons Ge$	0.124
$Hg_2Br_2 + 2\ e \rightleftharpoons 2\ Hg + 2\ Br^-$	0.13923
$Pt(OH)_2 + 2\ e \rightleftharpoons Pt + 2\ OH^-$	0.14
$[V(phen)_3]^{3+} + e \rightleftharpoons [V(phen)_3]^{2+}$	0.14
$S + 2H^+ + 2\ e \rightleftharpoons H_2S(aq)$	0.142
$Sn(OH)_3^+ + 3\ H^+ + 2\ e \rightleftharpoons Sn^{2+} + 3\ H_2O$	0.142
$Np^{4+} + e \rightleftharpoons Np^{3+}$	0.147
$Ag_4[Fe(CN)_6] + 4\ e \rightleftharpoons 4\ Ag + [Fe(CN)_6]^{4-}$	0.1478
$IO_3^- + 2\ H_2O + 4\ e \rightleftharpoons IO^- + 4\ OH^-$	0.15
$Mn(OH)_3 + e \rightleftharpoons Mn(OH)_2 + OH^-$	0.15
$2\ NO_2^- + 3\ H_2O + 4\ e \rightleftharpoons N_2O + 6\ OH^-$	0.15
$Sn^{4+} + 2\ e \rightleftharpoons Sn^{2+}$	0.151
$Sb_2O_3 + 6\ H^+ + 6\ e \rightleftharpoons 2\ Sb + 3\ H_2O$	0.152
$Cu^{2+} + e \rightleftharpoons Cu^+$	0.153
$BiOCl + 2\ H^+ + 3\ e \rightleftharpoons Bi + Cl^- + H_2O$	0.1583
$BiCl_4^- + 3\ e \rightleftharpoons Bi + 4\ Cl^-$	0.16
$Fe_2O_3 + 4\ H^+ + 2\ e \rightleftharpoons 2\ FeOH^+ + H_2O$	0.16
$Co(OH)_3 + e \rightleftharpoons Co(OH)_2 + OH^-$	0.17
$SO_4^{2-} + 4\ H^+ + 2\ e \rightleftharpoons H_2SO_3 + H_2O$	0.172
$Bi^{3+} + 2\ e \rightleftharpoons Bi^+$	0.2
$[Ru(en)_3]^{3+} + e \rightleftharpoons [Ru(en)_3]^{2+}$	0.210
$SbO^+ + 2\ H^+ + 3\ e \rightleftharpoons Sb + 2\ H_2O$	0.212
$AgCl + e \rightleftharpoons Ag + Cl^-$	0.22233
$[Ru(H_2O)_6]^{3+} + e \rightleftharpoons [Ru(H_2O)_6]^{2+}$	0.23
$As_2O_3 + 6\ H^+ + 6\ e \rightleftharpoons 2\ As + 3\ H_2O$	0.234
Calomel electrode, saturated NaCl (SSCE)	0.2360
$Ge^{2+} + 2\ e \rightleftharpoons Ge$	0.24
$Ru^{3+} + e \rightleftharpoons Ru^{2+}$	0.24
Calomel electrode, saturated KCl	0.2412
$PbO_2 + H_2O + 2\ e \rightleftharpoons PbO + 2\ OH^-$	0.247
$HAsO_2 + 3\ H^+ + 3\ e \rightleftharpoons As + 2\ H_2O$	0.248
$Ru^{3+} + e \rightharpoonup Ru^{2+}$	0.2487
$ReO_2 + 4\ H^+ + 4\ e \rightleftharpoons Re + 2\ H_2O$	0.2513
$IO_3^- + 3\ H_2O + 6\ e \rightleftharpoons I^- + OH^-$	0.26

Reaction	E°/V
$Hg_2Cl_2 + 2\ e \rightleftharpoons 2\ Hg + 2\ Cl^-$	0.26808
Calomel electrode, 1 molal KCl	0.2800
Calomel electrode, 1 molar KCl (NCE)	0.2801
$At_2 + 2\ e \rightleftharpoons 2\ At^-$	0.3
$Re^{3+} + 3\ e \rightleftharpoons Re$	0.300
$Tc^{3+} + e \rightleftharpoons Tc^{2+}$	0.3
$Bi^{3+} + 3\ e \rightleftharpoons Bi$	0.308
$BiO^+ + 2\ H^+ + 3\ e \rightleftharpoons Bi + H_2O$	0.320
$UO_2^{2+} + 4\ H^+ + 2\ e \rightleftharpoons U^{4+} + 2\ H_2O$	0.327
$ClO_3^- + H_2O + 2\ e \rightleftharpoons ClO_2^- + 2\ OH^-$	0.33
$2\ HCNO + 2\ H^+ + 2\ e \rightleftharpoons (CN)_2 + 2\ H_2O$	0.330
Calomel electrode, 0.1 molar KCl	0.3337
$VO^{2+} + 2\ H^+ + e \rightleftharpoons V^{3+} + H_2O$	0.337
$Cu^{2+} + 2\ e \rightleftharpoons Cu$	0.3419
$Ag_2O + H_2O + 2\ e \rightleftharpoons 2\ Ag + 2\ OH^-$	0.342
$Cu^{2+} + 2\ e \rightleftharpoons Cu(Hg)$	0.345
$AgIO_3 + e \rightleftharpoons Ag + IO_3^-$	0.354
$[Fe(CN)_6]^{3-} + e \rightleftharpoons [Fe(CN)_6]^{4-}$	0.358
$ClO_4^- + H_2O + 2\ e \rightleftharpoons ClO_3^- + 2\ OH^-$	0.36
$Ag_2SeO_3 + 2\ e \rightleftharpoons 2\ Ag + SeO_3^{2-}$	0.3629
$ReO_4^- + 8\ H^+ + 7\ e \rightleftharpoons Re + 4\ H_2O$	0.368
$(CN)_2 + 2\ H^+ + 2\ e \rightleftharpoons 2\ HCN$	0.373
$[Ferricinium]^+ + e \rightleftharpoons ferrocene$	0.400
$Tc^{2+} + 2\ e \rightleftharpoons Tc$	0.400
$O_2 + 2\ H_2O + 4\ e \rightleftharpoons 4\ OH^-$	0.401
$AgOCN + e \rightleftharpoons Ag + OCN^-$	0.41
$[RhCl_6]^{3-} + 3\ e \rightleftharpoons Rh + 6\ Cl^-$	0.431
$Ag_2CrO_4 + 2\ e \rightleftharpoons 2\ Ag + CrO_4^{2-}$	0.4470
$H_2SO_3 + 4\ H^+ + 4\ e \rightleftharpoons S + 3\ H_2O$	0.449
$Ru^{2+} + 2\ e \rightleftharpoons Ru$	0.455
$Ag_2MoO_4 + 2\ e \rightleftharpoons 2\ Ag + MoO_4^{2-}$	0.4573
$Ag_2C_2O_4 + 2\ e \rightleftharpoons 2\ Ag + C_2O_4^{2-}$	0.4647
$Ag_2WO_4 + 2\ e \rightleftharpoons 2\ Ag + WO_4^{2-}$	0.4660
$Ag_2CO_3 + 2\ e \rightleftharpoons 2\ Ag + CO_3^{2-}$	0.47
$TcO_4^- + 8\ H^+ + 7\ e \rightleftharpoons Tc + 4\ H_2O$	0.472
$TeO_4^- + 8\ H^+ + 7\ e \rightleftharpoons Te + 4\ H_2O$	0.472
$IO^- + H_2O + 2\ e \rightleftharpoons I^- + 2\ OH^-$	0.485
$NiO_2 + 2\ H_2O + 2\ e \rightleftharpoons Ni(OH)_2 + 2\ OH^-$	0.490
$Bi^+ + e \rightleftharpoons Bi$	0.5
$ReO_4^- + 4\ H^+ + 3\ e \rightleftharpoons ReO_2 + 2\ H_2O$	0.510
$Hg_2(ac)_2 + 2\ e \rightleftharpoons 2\ Hg + 2(ac)^-$	0.51163
$Cu^+ + e \rightleftharpoons Cu$	0.521
$I_2 + 2\ e \rightleftharpoons 2\ I^-$	0.5355
$I_3^- + 2\ e \rightleftharpoons 3\ I^-$	0.536
$AgBrO_3 + e \rightleftharpoons Ag + BrO_3^-$	0.546
$MnO_4^- + e \rightleftharpoons MnO_4^-$	0.558
$H_3AsO_4 + 2\ H^+ + 2\ e \rightleftharpoons HAsO_2 + 2\ H_2O$	0.560
$S_2O_6^{2-} + 4\ H^+ + 2\ e \rightleftharpoons 2\ H_2SO_3$	0.564
$AgNO_2 + e \rightleftharpoons Ag + NO_2^-$	0.564
$Te^{4+} + 4\ e \rightleftharpoons Te$	0.568
$Sb_2O_5 + 6\ H^+ + 4\ e \rightleftharpoons 2\ SbO^+ + 3\ H_2O$	0.581
$RuO_4^- + e \rightleftharpoons RuO_4^{2-}$	0.59
$[PdCl_4]^{2-} + 2\ e \rightleftharpoons Pd + 4\ Cl^-$	0.591
$TeO_2 + 4\ H^+ + 4\ e \rightleftharpoons Te + 2\ H_2O$	0.593
$MnO_4^- + 2\ H_2O + 3\ e \rightleftharpoons MnO_2 + 4\ OH^-$	0.595
$Rh^{2+} + 2\ e \rightleftharpoons Rh$	0.600

Reaction	E°/V
$Rh^+ + e \rightleftharpoons Rh$	0.600
$MnO_4^{2-} + 2\,H_2O + 2\,e \rightleftharpoons MnO_2 + 4\,OH^-$	0.60
$2\,AgO + H_2O + 2\,e \rightleftharpoons Ag_2O + 2\,OH^-$	0.607
$BrO_3^- + 3\,H_2O + 6\,e \rightleftharpoons Br^- + 6\,OH^-$	0.61
$UO_2^+ + 4\,H^+ + e \rightleftharpoons U^{4+} + 2\,H_2O$	0.612
$Hg_2SO_4 + 2\,e \rightleftharpoons 2\,Hg + SO_4^{2-}$	0.6125
$ClO_3^- + 3\,H_2O + 6\,e \rightleftharpoons Cl^- + 6\,OH^-$	0.62
$Hg_2HPO_4 + 2\,e \rightleftharpoons 2\,Hg + HPO_4^{2-}$	0.6359
$Ag(ac) + e \rightleftharpoons Ag + (ac)^-$	0.643
Sb_2O_5(valentinite) $+ 4\,H^+ + 4\,e \rightleftharpoons Sb_2O_3 + 2\,H_2O$	0.649
$Ag_2SO_4 + 2\,e \rightleftharpoons 2\,Ag + SO_4^{2-}$	0.654
$ClO_2^- + H_2O + 2\,e \rightleftharpoons ClO^- + 2\,OH^-$	0.66
Sb_2O_5(senarmontite) $+ 4\,H^+ + 4\,e \rightleftharpoons Sb_2O_5 + 2\,H_2O$	0.671
$[PtCl_6]^{2-} + 2\,e \rightleftharpoons [PtCl_4]^{2-} + 2\,Cl^-$	0.68
$O_2 + 2\,H^+ + 2\,e \rightleftharpoons H_2O_2$	0.695
p–benzoquinone $+ 2\,H^+ + 2\,e \rightleftharpoons\rightleftharpoons$ hydroquinone	0.6992
$H_3IO_6^{2-} + 2\,e \rightleftharpoons IO_3^- + 3\,OH^-$	0.7
$Ag_2O_3 + H_2O + 2\,e \rightleftharpoons 2\,AgO + 2\,OH^-$	0.739
$Tl^{3+} + 3\,e \rightleftharpoons Tl$	0.741
$[PtCl_4]^{2-} + 2\,e \rightleftharpoons Pt + 4\,Cl^-$	0.755
$Rh^{3+} + 3\,e \rightleftharpoons Rh$	0.758
$ClO_2^- + 2\,H_2O + 4\,e \rightleftharpoons Cl^- + 4\,OH^-$	0.76
$2\,NO + H_2O + 2\,e \rightleftharpoons N_2O + 2\,OH^-$	0.76
$Po^{4+} + 4\,e \rightleftharpoons Po$	0.76
$BrO^- + H_2O + 2\,e \rightleftharpoons Br^- + 2\,OH^-$	0.761
$ReO_4^- + 2\,H^+ + e \rightleftharpoons ReO_3 + H_2O$	0.768
$(CNS)_2 + 2\,e \rightleftharpoons 2\,CNS^-$	0.77
$[IrCl_6]^{3-} + 3\,e \rightleftharpoons Ir + 6\,Cl^-$	0.77
$Fe^{3+} + e \rightleftharpoons Fe^{2+}$	0.771
$AgF + e \rightleftharpoons Ag + F^-$	0.779
$[Fe(bipy)_2]^{3+} + e \rightleftharpoons [Fe(bipy)_2]^{2+}$	0.78
$TcO_4^- + 4\,H^+ + 3\,e \rightleftharpoons TcO_2 + 2\,H_2O$	0.782
$Hg_2^{2+} + 2\,e \rightleftharpoons 2\,Hg$	0.7973
$Ag^+ + e \rightleftharpoons Ag$	0.7996
$[Os(bipy)_3]^{3+} + e \rightleftharpoons [Os(bipy)_3]^{2+}$	0.80
$2\,NO_3^- + 4\,H^+ + 2\,e \rightleftharpoons N_2O_4 + 2\,H_2O$	0.803
$[Os(bipy)_2]^{3+} + e \rightleftharpoons [Os(bipy)_2]^{2+}$	0.81
$RhOH^{2+} + H + 3\,e \rightleftharpoons Rh + H_2O$	0.83
$OsO_4 + 8\,H^+ + 8\,e \rightleftharpoons Os + 4\,H_2O$	0.838
$ClO^- + H_2O + 2\,e \rightleftharpoons Cl^- + 2\,OH^-$	0.841
$Hg^{2+} + 2\,e \rightleftharpoons Hg$	0.851
$AuBr_4^- + 3\,e \rightleftharpoons Au + 4\,Br^-$	0.854
SiO_2(quartz) $+ 4\,H^+ + 4\,e \rightleftharpoons Si + 2\,H_2O$	0.857
$2\,HNO_2 + 4\,H^+ + 4\,e \rightleftharpoons H_2N_2O_2 + H_2O$	0.86
$[Ru(CN)_6]^{3-} + e^- \rightleftharpoons [Ru(CN)_6]^{4-}$	0.86
$[IrCl_6]^{2-} + e \rightleftharpoons [IrCl_6]^{3-}$	0.8665
$N_2O_4 + 2\,e \rightleftharpoons 2\,NO_2^-$	0.867
$HO_2^- + H_2O + 2\,e \rightleftharpoons 3\,OH^-$	0.878
$Po^{4+} + 2\,e \rightleftharpoons Po^{2+}$	0.9
$2\,Hg^{2+} + 2\,e \rightleftharpoons Hg_2^{2+}$	0.920
$NO_3^- + 3\,H^+ + 2\,e \rightleftharpoons HNO_2 + H_2O$	0.934
$Pd^{2+} + 2\,e \rightleftharpoons Pd$	0.951
ClO_2(aq) $+ e \rightleftharpoons ClO_2^-$	0.954
$NO_3^- + 4\,H^+ + 3\,e \rightleftharpoons NO + 2\,H_2O$	0.957
$V_2O_5 + 6\,H^+ + 2\,e \rightleftharpoons 2\,VO^{2+} + 3\,H_2O$	0.957
$AuBr_2^- + e \rightleftharpoons Au + 2\,Br^-$	0.959
$HNO_2 + H^+ + e \rightleftharpoons NO + H_2O$	0.983

Reaction	E°/V
$HIO + H^+ + 2\,e \rightleftharpoons I^- + H_2O$	0.987
$VO_2^+ + 2\,H^+ + e \rightleftharpoons VO^{2+} + H_2O$	0.991
$PtO_2 + 4\,H^+ + 4\,e \rightleftharpoons Pt + 2\,H_2O$	1.00
$RuO_4 + e \rightleftharpoons RuO_4^-$	1.00
$V(OH)_4^+ + 2\,H^+ + e \rightleftharpoons VO^{2+} + 3\,H_2O$	1.00
$AuCl_4^- + 3\,e \rightleftharpoons Au + 4\,Cl^-$	1.002
$Pu^{4+} + e \rightleftharpoons Pu^{3+}$	1.006
$PtO_2 + 2\,H^+ + 2\,e \rightleftharpoons PtO + H_2O$	1.01
$OsO_4 + 4\,H + 4\,e \rightleftharpoons OsO_2 + 2\,H_2O$	1.02
$H_6TeO_6 + 2\,H^+ + 2\,e \rightleftharpoons TeO_2 + 4\,H_2O$	1.02
$[Fe(bipy)_3]^{3+} + e \rightleftharpoons [Fe(bipy)_3]^{2+}$	1.03
$Hg(OH)_2 + 2\,H^+ + 2\,e \rightleftharpoons Hg + 2\,H_2O$	1.034
$N_2O_4 + 4\,H^+ + 4\,e \rightleftharpoons 2\,NO + 2\,H_2O$	1.035
$RuO_4 + 8\,H^+ + 8\,e \rightleftharpoons Ru + 4H_2O$	1.038
$[Fe(phen)_3]^{3+} + e \rightleftharpoons [Fe(phen)_3]^{2+}$ (1 molar H_2SO_4)	1.06
$PuO_2(OH)_2 + H^+ + e \rightleftharpoons PuO_2OH + H_2O$	1.062
$N_2O_4 + 2\,H^+ + 2\,e \rightleftharpoons 2\,HNO_2$	1.065
$Br_2(l) + 2\,e \rightleftharpoons 2Br^-$	1.066
$IO_3^- + 6\,H^+ + 6\,e \rightleftharpoons I^- + 3\,H_2O$	1.085
$Br_2(aq) + 2\,e \rightleftharpoons 2Br^-$	1.0873
$Pu^{5+} + e \rightleftharpoons Pu^{4+}$	1.099
$Cu^{2+} + 2\,CN^- + e \rightleftharpoons [Cu(CN)_2]^-$	1.103
$RuO_2 + 4\,H^+ + 2\,e \rightleftharpoons Ru^{2+} + 2\,H_2O$	1.120
$[Fe(phen)_3]^{3+} + e \rightleftharpoons [Fe(phen)_3]^{2+}$	1.147
$SeO_4^{2-} + 4\,H^+ + 2\,e \rightleftharpoons H_2SeO_3 + H_2O$	1.151
$ClO_3^- + 2\,H^+ + e \rightleftharpoons ClO_2 + H_2O$	1.152
$Ir^{3+} + 3\,e \rightarrow Ir$	1.156
$Pt^{2+} + 2\,e \rightleftharpoons Pt$	1.18
$ClO_4^- + 2\,H^+ + 2\,e \rightleftharpoons ClO_3^- + H_2O$	1.189
$2\,IO_3^- + 12\,H^+ + 10\,e \rightleftharpoons I_2 + 6\,H_2O$	1.195
$PtOH^+ + H^+ + 2\,e \rightleftharpoons Pt + H_2O$	1.2
$ClO_3^- + 3\,H^+ + 2\,e \rightleftharpoons HClO_2 + H_2O$	1.214
$MnO_2 + 4\,H^+ + 2\,e \rightleftharpoons Mn^{2+} + 2\,H_2O$	1.224
$O_2 + 4\,H^+ + 4\,e \rightleftharpoons 2\,H_2O$	1.229
$Cr_2O_7^{2-} + 14\,H^+ + 6\,e \rightleftharpoons 2\,Cr^{3+} + 7\,H_2O$	1.232
$O_3 + H_2O + 2\,e \rightleftharpoons O_2 + 2\,OH^-$	1.24
$[Ru(bipy)_3]^{3+} + e \rightleftharpoons [Ru(bipy)_3]^{2+}$	1.24
$Tl^{3+} + 2\,e \rightleftharpoons Tl^+$	1.252
$N_2H_5^+ + 3\,H^+ + 2\,e \rightleftharpoons 2\,NH_4^+$	1.275
$ClO_2 + H^+ + e \rightleftharpoons HClO_2$	1.277
$[PdCl_6]^{2-} + 2\,e \rightleftharpoons [PdCl_4]^{2-} + 2\,Cl^-$	1.288
$2\,HNO_2 + 4\,H^+ + 4\,e \rightleftharpoons N_2O + 3\,H_2O$	1.297
$AuOH^{2+} + H^+ + 2\,e \rightleftharpoons Au^+ + H_2O$	1.32
$PuO_2(OH)_2 + 2\,H^- + 2\,e \rightleftharpoons Pu(OH)_4$	1.325
$HBrO + H^+ + 2\,e \rightleftharpoons Br^- + H_2O$	1.331
$Cr(V) + e \rightleftharpoons Cr(IV)$	1.34
$HCrO_4^- + 7\,H^+ + 3\,e \rightleftharpoons Cr^{3+} + 4\,H_2O$	1.350
$Cl_2(g) + 2\,e \rightleftharpoons 2Cl^-$	1.35827
$ClO_4^- + 8\,H^+ + 8\,e \rightleftharpoons Cl^- + 4\,H_2O$	1.389
$ClO_4^- + 8\,H^+ + 7\,e \rightleftharpoons 1/2\,Cl_2 + 4\,H_2O$	1.39
$No^{3+} + e \rightleftharpoons No^{2+}$	1.4
$RuO_4 + 6\,H^+ + 4\,e \rightleftharpoons Ru(OH)_2^{2+} + 2\,H_2O$	1.40
$Au^{3+} + 2\,e \rightleftharpoons Au^+$	1.401
$2\,NH_3OH^+ + H^+ + 2\,e \rightleftharpoons N_2H_5^+ + 2\,H_2O$	1.42
$BrO_3^- + 6\,H^+ + 6\,e \rightleftharpoons Br^- + 3\,H_2O$	1.423
$2\,HIO + 2\,H^+ + 2\,e \rightleftharpoons I_2 + 2\,H_2O$	1.439
$Au(OH)_3 + 3\,H^+ + 3\,e \rightleftharpoons Au^- + 3\,H_2O$	1.45

Reaction	$E°$/V
$3IO_3^- + 6\,H^+ + 6\,e \rightleftharpoons Cl^- + 3\,H_2O$	1.451
$PbO_2 + 4\,H^+ + 2\,e \rightleftharpoons Pb^{2+} + 2\,H_2O$	1.455
$ClO_3^- + 6\,H^+ + 5\,e \rightleftharpoons 1/2\,Cl_2 + 3\,H_2O$	1.47
$CrO_2 + 4\,H^+ + e \rightleftharpoons Cr^{3+} + 2\,H_2O$	1.48
$BrO_3^- + 6\,H^+ + 5\,e \rightleftharpoons 1/2\,Br_2 + 3\,H_2O$	1.482
$HClO + H^+ + 2\,e \rightleftharpoons Cl^- + H_2O$	1.482
$Mn_2O_3 + 6\,H^+ + e \rightleftharpoons 2\,Mn^{2+} + 3\,H_2O$	1.485
$HO_2 + H^+ + e \rightleftharpoons H_2O_2$	1.495
$Au^{3+} + 3\,e \rightleftharpoons Au$	1.498
$PtO_3 + 4\,H^+ + 2\,e \rightleftharpoons Pt(OH)_2^{2+} + H_2O$	1.5
$MnO_4^- + 8\,H^+ + 5\,e \rightleftharpoons Mn^{2+} + 4\,H_2O$	1.507
$Mn^{3+} + e \rightleftharpoons Mn^{2-}$	1.5415
$HClO_2 + 3\,H^+ + 4\,e \rightleftharpoons Cl^- + 2\,H_2O$	1.570
$HBrO + H^+ + e \rightleftharpoons 1/2\,Br_2(aq) + H_2O$	1.574
$2\,NO + 2\,H^+ + 2\,e \rightleftharpoons N_2O + H_2O$	1.591
$Bi_2O_4 + 4\,H^+ + 2\,e \rightleftharpoons 2\,BiO^+ + 2\,H_2O$	1.593
$HBrO + H^+ + e \rightleftharpoons 1/2\,Br_2(l) + H_2O$	1.596
$H_5IO_6 + H^+ + 2\,e \rightleftharpoons IO_3^- + 3\,H_2O$	1.601
$HClO + H^+ + e \rightleftharpoons 1/2\,Cl_2 + H_2O$	1.611
$HClO_2 + 3\,H^+ + 3\,e \rightleftharpoons 1/2\,Cl_2 + 2\,H_2O$	1.628
$HClO_2 + 2\,H^+ + 2\,e \rightleftharpoons HClO + H_2O$	1.645
$Bk^{4+} + e \rightleftharpoons Bk^{3+}$	1.67
$NiO_2 + 4\,H^+ + 2\,e \rightleftharpoons Ni^{2+} + 2\,H_2O$	1.678
$MnO_4^- + 4\,H^+ + 3\,e _ MnO_2 + 2\,H_2O$	1.679
$PbO_2 + SO_4^{2-} + 4\,H^+ + 2\,e \rightleftharpoons PbSO_4 + 2\,H_2O$	1.6913
$Au^+ + e \rightleftharpoons Au$	1.692
$PtO_3 + 2\,H^+ + 2\,e \rightleftharpoons PtO_2 + H_2O$	1.7
$CeOH^{3+} + H^+ + e \rightleftharpoons Ce^{3+} + H_2O$	1.715
$Ce^{4+} + e \rightleftharpoons Ce^{3+}$	1.72
$N_2O + 2\,H^+ + 2\,e \rightleftharpoons N_2 + H_2O$	1.766
$H_2O_2 + 2\,H^+ + 2\,e \rightleftharpoons 2\,H_2O$	1.776
$Ag^{3+} + e \rightleftharpoons Ag^{2+}$	1.8
$Au^{2+} + e^- \rightleftharpoons Au^+$	1.8
$Ag_2O_2 + 4\,H^+ + e \rightleftharpoons 2\,Ag + 2\,H_2O$	1.802
$Co^{3+} + e \rightleftharpoons Co^{2-}$(2 molar H_2SO_4)	1.83
$Ag^{3+} + 2\,e \rightleftharpoons Ag^+$	1.9
$Co^{3+} + e \rightleftharpoons Co^{2+}$	1.92
$Ag^{2+} + e \rightleftharpoons Ag^+$	1.980
$Cu_2O_3 + 6\,H^+ + 2\,e \rightleftharpoons 2\,Cu^{2+} + 3\,H_2O$	2.0
$S_2O_8^{2-} + 2\,e \rightleftharpoons 2\,SO_4^{2-}$	2.010
$OH + e \rightleftharpoons OH^-$	2.02
$HFeO_4^- + 7\,H^+ + 3\,e \rightleftharpoons Fe^{3+} + 4\,H_2O$	2.07
$O_3 + 2\,H^+ + 2\,e \rightleftharpoons O_2 + H_2O$	2.076
$HFeO_4^- + 4\,H^+ + 3\,e \rightleftharpoons FeOOH + 2\,H_2O$	2.08
$2\,HFeO_4^- + 8\,H^+ + 6\,e \rightleftharpoons Fe_2O_3 + 5\,H_2O$	2.09
$XeO_3 + 6\,H^+ + 6\,e \rightleftharpoons Xe + 3\,H_2O$	2.10
$S_2O_8^{2-} + 2\,H^+ + 2\,e \rightleftharpoons 2\,HSO_4^-$	2.123
$F_2O + 2\,H^+ + 4\,e \rightleftharpoons H_2O + 2\,F^-$	2.153
$FeO_4^{2-} + 8\,H^+ + 3\,e \rightleftharpoons Fe^{3+} + 4\,H_2O$	2.20
$Cu^{3+} + e \rightleftharpoons Cu^{2+}$	2.4
$H_4XeO_6 + 2\,H^+ + 2\,e \rightleftharpoons XeO_3 + 3\,H_2O$	2.42
$O(g) + 2\,H^+ + 2\,e \rightleftharpoons H_2O$	2.421
$Am^{4+} + e \rightleftharpoons Am^{3+}$	2.60
$H_2N_2O_2 + 2\,H^+ + 2\,e \rightleftharpoons N_2 + 2\,H_2O$	2.65
$F_2 + 2\,e \rightleftharpoons 2\,F^-$	2.866
$Cm^{4+} + e \rightleftharpoons Cm^{3+}$	3.0
$F_2 + 2\,H^+ + 2\,e \rightleftharpoons 2\,HF$	3.053
$Tb^{4+} + e \rightleftharpoons Tb^{3+}$	3.1
$Pr^{4+} + e \rightleftharpoons Pr^{3+}$	3.2
$Cf^{4+} + e \rightleftharpoons Cf^{3+}$	3.3
$XeF + e \rightleftharpoons Xe + F^-$	3.4

TABLE 3. Reduction Reactions Having $E°$ Values More Negative than That of the Standard Hydrogen Electrode

Reaction	$E°$/V
$2\,H^+ + 2\,e \rightleftharpoons H_2$	0.00000
$2\,D^+ + 2\,e \rightleftharpoons D_2$	−0.013
$AgCN + e \rightleftharpoons Ag + CN^-$	−0.017
$2\,WO_3 + 2\,H^+ + 2\,e \rightleftharpoons W_2O_5 + H_2O$	−0.029
$W_2O_5 + 2\,H^+ + 2\,e \rightleftharpoons 2\,WO_2 + H_2O$	−0.031
$Ag_2S + 2\,H^+ + 2\,e \rightleftharpoons 2\,Ag + H_2S$	−0.0366
$Fe^{3+} + 3\,e \rightleftharpoons Fe$	−0.037
$Hg_2I_2 + 2\,e \rightleftharpoons 2\,Hg + 2\,I^-$	−0.0405
$Tl(OH)_3 + 2\,e \rightleftharpoons TlOH + 2\,OH^-$	−0.05
$TiOH^{3+} + H^+ + e \rightleftharpoons Ti^{3+} + H_2O$	−0.055
$2\,H_2SO_3 + H^+ + 2\,e \rightleftharpoons HS_2O_4^- + 2\,H_2O$	−0.056
$P(white) + 3\,H^+ + 3\,e \rightleftharpoons PH_3(g)$	−0.063
$O_2 + H_2O + 2\,e \rightleftharpoons HO_2^- + OH^-$	−0.076
$2\,Cu(OH)_2 + 2\,e \rightleftharpoons Cu_2O + 2\,OH^- + H_2O$	−0.080
$Se + 2\,H^+ + 2\,e \rightleftharpoons H_2Se$	−0.082
$WO_3 + 6\,H^+ + 6\,e \rightleftharpoons W + 3\,H_2O$	−0.090
$SnO_2 + 4\,H^+ + 2\,e \rightleftharpoons Sn^{2+} + 2\,H_2O$	−0.094
$Md^{3+} + e \rightleftharpoons Md^{2+}$	−0.1
$P(red) + 3\,H^+ + 3\,e \rightleftharpoons PH_3(g)$	−0.111
$SnO_2 + 4\,H^+ + 4\,e \rightleftharpoons Sn + 2\,H_2O$	−0.117
$GeO_2 + 2\,H^+ + 2\,e \rightleftharpoons GeO + H_2O$	−0.118
$WO_2 + 4\,H^+ + 4\,e \rightleftharpoons W + 2\,H_2O$	−0.119
$Pb^{2+} + 2\,e \rightleftharpoons Pb(Hg)$	−0.1205
$Pb^{2+} + 2\,e \rightleftharpoons Pb$	−0.1262
$CrO_4^{2-} + 4\,H_2O + 3\,e \rightleftharpoons Cr(OH)_3 + 5\,OH^-$	−0.13
$Sn^{2-} + 2\,e \rightleftharpoons Sn$	−0.1375
$In^+ + e \rightleftharpoons In$	−0.14
$O_2 + 2\,H_2O + 2\,e \rightleftharpoons H_2O_2 + 2\,OH^-$	−0.146
$MoO_2 + 4\,H^+ + 4\,e \rightleftharpoons Mo + 4\,H_2O$	−0.152
$AgI + e \rightleftharpoons Ag + I^-$	−0.15224
$2\,NO_2^- + 2\,H_2O + 4\,e \rightleftharpoons N_2O_2^{2-} + 4\,OH^-$	−0.18
$H_2GeO_3 + 4\,H^+ + 4\,e \rightleftharpoons Ge + 3\,H_2O$	−0.182
$SnO_2 + 3\,H^+ + 2\,e \rightleftharpoons SnOH^+ + H_2O$	−0.194
$CO_2 + 2\,H^+ + 2\,e \rightleftharpoons HCOOH$	−0.199
$Mo^{3+} + 3\,e \rightleftharpoons Mo$	−0.200
$Ga^+ + e \rightleftharpoons Ga$	−0.2
$2\,SO_2^{2-} + 4\,H^+ + 2\,e \rightleftharpoons S_2O_6^{2-} + H_2O$	−0.22
$Cu(OH)_2 + 2\,e \rightleftharpoons Cu + 2\,OH^-$	−0.222
$V_2O_5 + 10\,H^+ + 10\,e \rightleftharpoons 2\,V + 5\,H_2O$	−0.242
$CdSO_4 + 2\,e \rightleftharpoons Cd + SO_4^{2-}$	−0.246
$V(OH)_4^+ + 4\,H^+ + 5\,e \rightleftharpoons V + 4\,H_2O$	−0.254
$V^{3+} + e \rightleftharpoons V^{2+}$	−0.255
$Ni^{2+} + 2\,e \rightleftharpoons Ni$	−0.257
$PbCl_2 + 2\,e \rightleftharpoons Pb + 2\,Cl^-$	−0.2675
$H_3PO_4 + 2\,H^+ + 2\,e \rightleftharpoons H_3PO_3 + H_2O$	−0.276
$Co^{2+} + 2\,e \rightleftharpoons Co$	−0.28

Reaction	$E°$/V
$PbBr_2 + 2\,e \rightleftharpoons Pb + 2\,Br^-$	−0.284
$Tl^+ + e \rightleftharpoons Tl(Hg)$	−0.3338
$Tl^+ + e \rightleftharpoons Tl$	−0.336
$In^{3+} + 3\,e \rightleftharpoons In$	−0.3382
$TlOH + e \rightleftharpoons Tl + OH^-$	−0.34
$PbF_2 + 2\,e \rightleftharpoons Pb + 2\,F^-$	−0.3444
$PbSO_4 + 2\,e \rightleftharpoons Pb(Hg) + SO_4^{2-}$	−0.3505
$Cd^{2+} + 2\,e \rightleftharpoons Cd(Hg)$	−0.3521
$PbSO_4 + 2\,e \rightleftharpoons Pb + SO_4^{2-}$	−0.3588
$Cu_2O + H_2O + 2\,e \rightleftharpoons 2\,Cu + 2\,OH^-$	−0.360
$Eu^{3+} + e \rightleftharpoons Eu^{2+}$	−0.36
$PbI_2 + 2\,e \rightleftharpoons Pb + 2\,I^-$	−0.365
$SeO_3^{2-} + 3\,H_2O + 4\,e \rightleftharpoons Se + 6\,OH^-$	−0.366
$Se + 2\,H^+ + 2\,e \rightleftharpoons H_2Se(aq)$	−0.399
$In^{2+} + e \rightleftharpoons In^+$	−0.40
$Cd^{2+} + 2\,e \rightleftharpoons Cd$	−0.4030
$Cr^{3+} + e \rightleftharpoons Cr^{2+}$	−0.407
$2\,S + 2\,e \rightleftharpoons S_2^{2-}$	−0.42836
$Tl_2SO_4 + 2\,e \rightleftharpoons Tl + SO_4^{2-}$	−0.4360
$In^{3+} + 2\,e \rightleftharpoons In^+$	−0.443
$Fe^{2+} + 2\,e \rightleftharpoons Fe$	−0.447
$H_3PO_3 + 3\,H^+ + 3\,e \rightleftharpoons P + 3\,H_2O$	−0.454
$Bi_2O_3 + 3\,H_2O + 6\,e \rightleftharpoons 2\,Bi + 6\,OH^-$	−0.46
$NO_2^- + H_2O + e \rightleftharpoons NO + 2\,OH$	−0.46
$PbHPO_4 + 2\,e \rightleftharpoons Pb + HPO_4^{2-}$	−0.465
$S + 2\,e \rightleftharpoons S^{2-}$	−0.47627
$S + H_2O + 2\,e \rightleftharpoons HS^- + OH^-$	−0.478
$B(OH)_3 + 7\,H^+ + 8\,e \rightleftharpoons BH_4^- + 3\,H_2O$	−0.481
$In^{3+} + e \rightleftharpoons In^{2+}$	−0.49
$ZnOH^+ + H^+ + 2\,e \rightleftharpoons Zn + H_2O$	−0.497
$GaOH^{2+} + H^+ + 3\,e \rightleftharpoons Ga + H_2O$	−0.498
$H_3PO_3 + 2\,H^+ + 2\,e \rightleftharpoons H_3PO_2 + H_2O$	−0.499
$TiO_2 + 4\,H^+ + 2\,e \rightleftharpoons Ti^{2+} + 2\,H_2O$	−0.502
$H_3PO_2 + H^+ + e \rightleftharpoons P + 2\,H_2O$	−0.508
$Sb + 3\,H^+ + 3\,e \rightleftharpoons SbH_3$	−0.510
$HPbO_2^- + H_2O + 2\,e \rightleftharpoons Pb + 3\,OH^-$	−0.537
$Ga^{3+} + 3\,e \rightleftharpoons Ga$	−0.549
$TlCl + e \rightleftharpoons Tl + Cl^-$	−0.5568
$Fe(OH)_3 + e \rightleftharpoons Fe(OH)_2 + OH^-$	−0.56
$TeO_3^{2-} + 3\,H_2O + 4\,e \rightleftharpoons Te + 6\,OH^-$	−0.57
$2\,SO_3^{2-} + 3\,H_2O + 4\,e \rightleftharpoons S_2O_3^{2-} + 6\,OH^-$	−0.571
$PbO + H_2O + 2\,e \rightleftharpoons Pb + 2\,OH^-$	−0.580
$ReO_2^- + 4\,H_2O + 7\,e \rightleftharpoons Re + 8\,OH^-$	−0.584
$SbO_3^- + H_2O + 2\,e \rightleftharpoons SbO_2^- + 2\,OH^-$	−0.59
$Ta^{3+} + 3\,e \rightleftharpoons Ta$	−0.6
$U^{4+} + e \rightleftharpoons U^{3+}$	−0.607
$As + 3\,H^+ + 3\,e \rightleftharpoons AsH_3$	−0.608
$Nb_2O_5 + 10\,H^+ + 10\,e \rightleftharpoons 2\,Nb + 5\,H_2O$	−0.644
$NbO_2 + 2\,H^+ + 2\,e \rightleftharpoons NbO + H_2O$	−0.646
$Cd(OH)_4^{2-} + 2\,e \rightleftharpoons Cd + 4\,OH^-$	−0.658
$TlBr + e \rightleftharpoons Tl + Br^-$	−0.658
$SbO_2^- + 2\,H_2O + 3\,e \rightleftharpoons Sb + 4\,OH^-$	−0.66
$AsO_2^- + 2\,H_2O + 3\,e \rightleftharpoons As + 4\,OH^-$	−0.68
$NbO_2 + 4\,H^+ + 4\,e \rightleftharpoons Nb + 2\,H_2O$	−0.690
$Ag_2S + 2\,e \rightleftharpoons 2\,Ag + S^{2-}$	−0.691
$AsO_4^{3-} + 2\,H_2O + 2\,e \rightleftharpoons AsO_2^- + 4\,OH^-$	−0.71
$Ni(OH)_2 + 2\,e \rightleftharpoons Ni + 2\,OH^-$	−0.72

Reaction	$E°$/V
$Co(OH)_2 + 2\,e \rightleftharpoons Co + 2\,OH^-$	−0.73
$NbO + 2\,H^+ + 2\,e \rightleftharpoons Nb + H_2O$	−0.733
$H_2SeO_3 + 4\,H^+ + 4\,e \rightleftharpoons Se + 3\,H_2O$	−0.74
$Cr^{3+} + 3\,e \rightleftharpoons Cr$	−0.744
$Ta_2O_5 + 10\,H^+ + 10\,e \rightleftharpoons 2\,Ta + 5\,H_2O$	−0.750
$TlI + e \rightleftharpoons Tl + I^-$	−0.752
$Zn^{2+} + 2\,e \rightleftharpoons Zn$	−0.7618
$Zn^{2+} + 2\,e \rightleftharpoons Zn(Hg)$	−0.7628
$CdO + H_2O + 2\,e \rightleftharpoons Cd + 2\,OH^-$	−0.783
$Te + 2\,H^+ + 2\,e \rightleftharpoons H_2Te$	−0.793
$ZnSO_4{\cdot}7H_2O + 2\,e \rightleftharpoons Zn(Hg) + SO_4^{2-} + 7\,H_2O$ (Saturated $ZnSO_4$)	−0.7993
$Bi + 3\,H^+ + 3\,e \rightleftharpoons BiH_3$	−0.8
$SiO + 2\,H^+ + 2\,e \rightleftharpoons Si + H_2O$	−0.8
$Cd(OH)_2 + 2\,e \rightleftharpoons Cd(Hg) + 2\,OH^-$	−0.809
$2\,H_2O + 2\,e \rightleftharpoons H_2 + 2\,OH^-$	−0.8277
$2\,NO_3^- + 2\,H_2O + 2\,e \rightleftharpoons N_2O_4 + 4\,OH^-$	−0.85
$H_3BO_3 + 3\,H^+ + 3\,e \rightleftharpoons B + 3\,H_2O$	−0.8698
$P + 3\,H_2O + 3\,e \rightleftharpoons PH_3(g) + 3\,OH^-$	−0.87
$Ti^{3+} + e \rightleftharpoons Ti^{2+}$	−0.9
$HSnO_2^- + H_2O + 2\,e \rightleftharpoons Sn + 3\,OH^-$	−0.909
$Cr^{2+} + 2\,e \rightleftharpoons Cr$	−0.913
$Se + 2\,e \rightleftharpoons Se^{2-}$	−0.924
$SO_4^{2-} + H_2O + 2\,e \rightleftharpoons SO_3^{2-} + 2\,OH^-$	−0.93
$Sn(OH)_6^{2-} + 2\,e \rightleftharpoons HSnO_2^- + 3\,OH^- + H_2O$	−0.93
$SnO_2 + 2\,H_2O + 4\,e \rightleftharpoons Sn + 4\,OH^-$	−0.945
$In(OH)_3 + 3\,e \rightleftharpoons In + 3\,OH^-$	−0.99
$NpO_2 + H_2O + H^+ + e \rightleftharpoons Np(OH)_3$	−0.962
$In(OH)_4^- + 3\,e \rightleftharpoons In + 4\,OH^-$	−1.007
$In_2O_3 + 3\,H_2O + 6\,e \rightleftharpoons 2\,In + 6\,OH^-$	−1.034
$PO_4^{3-} + 2\,H_2O + 2\,e \rightleftharpoons HPO_3^{2-} + 3\,OH^-$	−1.05
$Yb^{3+} + e \rightleftharpoons Yb^{2+}$	−1.05
$Nb^{3+} + 3\,e \rightleftharpoons Nb$	−1.099
$Fm^{3+} + e \rightleftharpoons Fm^{2+}$	−1.1
$2\,SO_3^{2-} + 2\,H_2O + 2\,e \rightleftharpoons S_2O_4^{2-} + 4\,OH^-$	−1.12
$Te + 2\,e \rightleftharpoons Te^{2-}$	−1.143
$V^{2+} + 2\,e \rightleftharpoons V$	−1.175
$Mn^{2+} + 2\,e \rightleftharpoons Mn$	−1.185
$Zn(OH)_4^{2-} + 2\,e \rightleftharpoons Zn + 4\,OH^-$	−1.199
$CrO_2 + 2\,H_2O + 3\,e \rightleftharpoons Cr + 4\,OH^-$	−1.2
$No^{3+} + 3\,e \rightleftharpoons No$	−1.20
$ZnO_2^- + 2\,H_2O + 2\,e \rightleftharpoons Zn + 4\,OH^-$	−1.215
$H_2GaO_3^- + H_2O + 3\,e \rightleftharpoons Ga + 4\,OH^-$	−1.219
$H_2BO_3^- + 5\,H_2O + 8\,e \rightleftharpoons BH_4^- + 8\,OH^-$	−1.24
$SiF_6^{2-} + 4\,e \rightleftharpoons Si + 6\,F^-$	−1.24
$Zn(OH)_2 + 2\,e \rightleftharpoons Zn + 2\,OH^-$	−1.249
$ZnO + H_2O + 2\,e \rightleftharpoons Zn + 2\,OH^-$	−1.260
$Es^{3+} + e \rightleftharpoons Es^{2+}$	−1.3
$Pa^{3+} + 3\,e \rightleftharpoons Pa$	−1.34
$Ti^{3+} + 3\,e \rightleftharpoons Ti$	−1.37
$Ce^{3+} + 3\,e \rightleftharpoons Ce(Hg)$	−1.4373
$UO_2^{2+} + 4\,H^+ + 6\,e \rightleftharpoons U + 2\,H_2O$	−1.444
$Zr^{4+} + 4\,e \rightleftharpoons Zr$	−1.45
$Cr(OH)_3 + 3\,e \rightleftharpoons Cr + 3\,OH^-$	−1.48
$Pa^{4+} + 4\,e \rightleftharpoons Pa$	−1.49
$HfO_2 + 4\,H^+ + 4\,e \rightleftharpoons Hf + 2\,H_2O$	−1.505
$Hf^{4+} + 4\,e \rightleftharpoons Hf$	−1.55

Reaction	$E°$/V
$Sm^{3+} + e \rightleftharpoons Sm^{2+}$	−1.55
$ZrO_2 + 4\,H^+ + 4\,e \rightleftharpoons Zr + 2\,H_2O$	−1.553
$Mn(OH)_2 + 2\,e \rightleftharpoons Mn + 2\,OH^-$	−1.56
$Ba^{2+} + 2\,e \rightleftharpoons Ba(Hg)$	−1.570
$Bk^{2+} + 2\,e \rightleftharpoons Bk$	−1.6
$Cf^{3+} + e \rightleftharpoons Cf^{2+}$	−1.6
$Ti^{2+} + 2\,e \rightleftharpoons Ti$	−1.630
$Md^{3+} + 3\,e \rightleftharpoons Md$	−1.65
$HPO_3^{2-} + 2\,H_2O + 2\,e \rightleftharpoons H_2PO_2^- + 3\,OH^-$	−1.65
$Al^{3+} + 3\,e \rightleftharpoons Al$	−1.662
$SiO_3^{2-} + H_2O + 4\,e \rightleftharpoons Si + 6\,OH^-$	−1.697
$HPO_3^{2-} + 2\,H_2O + 3\,e \rightleftharpoons P + 5\,OH^-$	−1.71
$HfO^{2+} + 2\,H^+ + 4\,e \rightleftharpoons Hf + H_2O$	−1.724
$ThO_2 + 4\,H^+ + 4\,e \rightleftharpoons Th + 2\,H_2O$	−1.789
$H_2BO_3^- + H_2O + 3\,e \rightleftharpoons B + 4\,OH^-$	−1.79
$Sr^{2+} + 2\,e \rightleftharpoons Sr(Hg)$	−1.793
$U^{3+} + 3\,e \rightleftharpoons U$	−1.798
$H_2PO^-_2 + e \rightleftharpoons P + 2\,OH^-$	−1.82
$Be^{2+} + 2\,e \rightleftharpoons Be$	−1.847
$Np^{3+} + 3\,e \rightleftharpoons Np$	−1.856
$Fm^{3+} + 3\,e \rightleftharpoons Fm$	−1.89
$Th^{4+} + 4\,e \rightleftharpoons Th$	−1.899
$Am^{2+} + 2\,e \rightleftharpoons Am$	−1.9
$Pa^{4+} + e \rightleftharpoons Pa^{3+}$	−1.9
$Es^{3+} + 3\,e \rightleftharpoons Es$	−1.91
$Cf^{3+} + 3\,e \rightleftharpoons Cf$	−1.94
$Lr^{3+} + 3\,e \rightleftharpoons Lr$	−1.96
$Eu^{3+} + 3\,e \rightleftharpoons Eu$	−1.991
$Er^{2+} + 2\,e \rightleftharpoons Er$	−2.0
$Pr^{2+} + 2\,e \rightleftharpoons Pr$	−2.0
$Pu^{3+} + 3\,e \rightleftharpoons Pu$	−2.031
$Cm^{3+} + 3\,e \rightleftharpoons Cm$	−2.04
$Am^{3+} + 3\,e \rightleftharpoons Am$	−2.048
$AlF_6^{3-} + 3\,e \rightleftharpoons Al + 6\,F^-$	−2.069
$Sc^{3+} + 3\,e \rightleftharpoons Sc$	−2.077
$Ho^{2+} + 2\,e \rightleftharpoons Ho$	−2.1
$Nd^{2+} + 2\,e \rightleftharpoons Nd$	−2.1
$Cf^{2+} + 2\,e \rightleftharpoons Cf$	−2.12
$Yb^{3+} + 3\,e \rightleftharpoons Yb$	−2.19
$Ac^{3+} + 3\,e \rightleftharpoons Ac$	−2.20
$Dy^{2+} + 2\,e \rightleftharpoons Dy$	−2.2
$Tm^{3+} + e \rightleftharpoons Tm^{2+}$	−2.2
$Pm^{2+} + 2\,e \rightleftharpoons Pm$	−2.2
$Es^{2+} + 2\,e \rightleftharpoons Es$	−2.23
$H_2 + 2\,e \rightleftharpoons 2\,H^-$	−2.23
$Gd^{3+} + 3\,e \rightleftharpoons Gd$	−2.279
$Tb^{3+} + 3\,e \rightleftharpoons Tb$	−2.28
$Lu^{3+} + 3\,e \rightleftharpoons Lu$	−2.28
$Dy^{3+} + 3\,e \rightleftharpoons Dy$	−2.295
$Am^{3+} + e \rightleftharpoons Am^{2+}$	−2.3
$Fm^{2+} + 2\,e \rightleftharpoons Fm$	−2.30

Reaction	$E°$/V
$Pm^{3+} + 3\,e \rightleftharpoons Pm$	−2.30
$Sm^{3+} + 3\,e \rightleftharpoons Sm$	−2.304
$Al(OH)_3 + 3\,e \rightleftharpoons Al + 3\,OH^-$	−2.31
$Tm^{3+} + 3\,e \rightleftharpoons Tm$	−2.319
$Nd^{3+} + 3\,e \rightleftharpoons Nd$	−2.323
$Al(OH)^- + 3\,e \rightleftharpoons Al + 4\,OH^-$	−2.328
$H_2AlO_3^- + H_2O + 3\,e \rightleftharpoons Al + 4\,OH^-$	−2.33
$Ho^{3+} + 3\,e \rightleftharpoons Ho$	−2.33
$Er^{3+} + 3\,e \rightleftharpoons Er$	−2.331
$Ce^{3+} + 3\,e \rightleftharpoons Ce$	−2.336
$Pr^{3+} + 3\,e \rightleftharpoons Pr$	−2.353
$ZrO(OH)_2 + H_2O + 4\,e \rightleftharpoons Zr + 4\,OH^-$	−2.36
$Mg^{2+} + 2\,e \rightleftharpoons Mg$	−2.372
$Y^{3+} + 3\,e \rightleftharpoons Y$	−2.372
$La^{3+} + 3\,e \rightleftharpoons La$	−2.379
$Tm^{2+} + 2\,e \rightleftharpoons Tm$	−2.4
$Md^{2+} + 2\,e \rightleftharpoons Md$	−2.40
$Th(OH)_4 + 4\,e \rightleftharpoons Th + 4\,OH^-$	−2.48
$HfO(OH)_2 + H_2O + 4\,e \rightleftharpoons Hf + 4\,OH^-$	−2.50
$No^{2+} + 2\,e \rightleftharpoons No$	−2.50
$Dy^{3+} + e \rightleftharpoons Dy^{2+}$	−2.6
$Pm^{3+} + e \rightleftharpoons Pm^{2+}$	−2.6
$Be_2O_3^{2-} + 3\,H_2O + 4\,e \rightleftharpoons 2\,Be + 6\,OH^-$	−2.63
$Sm^{2+} + 2\,e \rightleftharpoons Sm$	−2.68
$Mg(OH)_2 + 2\,e \rightleftharpoons Mg + 2\,OH^-$	−2.690
$Nd^{3+} + e \rightleftharpoons Nd^{2+}$	−2.7
$Mg^+ + e \rightleftharpoons Mg$	−2.70
$Na^+ + e \rightleftharpoons Na$	−2.71
$Yb^{2+} + 2\,e \rightleftharpoons Yb$	−2.76
$Bk^{3+} + e \rightleftharpoons Bk^{2+}$	−2.8
$Ho^{3+} + e \rightleftharpoons Ho^{2+}$	−2.8
$Ra^{2+} + 2\,e \rightleftharpoons Ra$	−2.8
$Eu^{2+} + 2\,e \rightleftharpoons Eu$	−2.812
$Ca^{2+} + 2\,e \rightleftharpoons Ca$	−2.868
$Sr(OH)_2 + 2\,e \rightleftharpoons Sr + 2\,OH^-$	−2.88
$Sr^{2+} + 2\,e \rightleftharpoons Sr$	−2.899
$Fr^+ + e \rightleftharpoons Fr$	−2.9
$La(OH)_3 + 3\,e \rightleftharpoons La + 3\,OH^-$	−2.90
$Ba^{2+} + 2\,e \rightleftharpoons Ba$	−2.912
$K^+ + e \rightleftharpoons K$	−2.931
$Rb^+ + e \rightleftharpoons Rb$	−2.98
$Ba(OH)_2 + 2\,e \rightleftharpoons Ba + 2\,OH^-$	−2.99
$Er^{3+} + e \rightleftharpoons Er^{2+}$	−3.0
$Ca(OH)_2 + 2\,e \rightleftharpoons Ca + 2\,OH^-$	−3.02
$Cs^+ + e \rightleftharpoons Cs$	−3.026
$Li^+ + e \rightleftharpoons Li$	−3.0401
$3\,N_2 + 2\,H^+ + 2\,e \rightleftharpoons 2\,HN_3$	−3.09
$Pr^{3+} + e \rightleftharpoons Pr^{2+}$	−3.1
$Ca^+ + e \rightleftharpoons Ca$	−3.80
$Sr^+ + e \rightleftharpoons Sr$	−4.10

REDUCTION AND OXIDATION POTENTIALS FOR CERTAIN ION RADICALS

Petr Vanýsek

There are two tables for ion radicals. The first table lists reduction potentials for organic compounds which produce anion radicals during reduction, a process described as $A + e^- \rightleftharpoons A^{-\cdot}$. The second table lists oxidation potentials for organic compounds which produce cation radicals during oxidation, a process described as $A \rightleftharpoons A^{+\cdot} + e^-$. To obtain reduction potential for a reverse reaction, the sign for the potential is changed.

Unlike the table of the Electrochemical Series, which lists *standard* potentials, values for radicals are experimental values with experimental conditions given in the second column. Since the measurements leading to potentials for ion radicals are very dependent on conditions, an attempt to report standard potentials for radicals would serve no useful purpose. For the same reason, the potentials are also reported as experimental values, usually a half-wave potential ($E_{1/2}$ in polarography) or a peak potential (E_p in cyclic voltammetry). Unless otherwise stated, the values are reported vs. SCE (saturated calomel electrode). To obtain a value vs. normal hydrogen electrode, 0.241 V has to be added to the SCE values. All the ion radicals chosen for inclusion in the tables result from electrochemically reversible reactions. More detailed data on ion radicals can be found in the *Encyclopedia of Electrochemistry of Elements,* (A. J. Bard, Ed.), Vol. XI and XII in particular, Marcel Dekker, New York, 1978.

Abbreviations are: CV — cyclic voltammetry; DMF — *N,N*-Dimethylformamide; *E* swp — potential sweep; E° — standard potential; E_p — peak potential; $E_{p/2}$ — half-peak potential; $E_{1/2}$ — half wave potential; *M* — mol/L; MeCN — acetonitrile; pol — polarography; rot Pt dsk — rotated Pt disk; SCE — saturated calomel electrode; $TBABF_4$ — tetrabutylammonium tetrafluoroborate; TBAI — tetrabutylammonium iodide; TBAP — tetrabutylammonium perchlorate; TEABr — tetraethylammonium bromide; TEAP — tetraethylammonium perchlorate; THF — tetrahydrofuran; $TPACF_3SO_3$ — tetrapropylammonium trifluoromethanesulfite; TPAP — tetrapropylammonium perchlorate; and wr — wire.

Reduction Potentials (Products are Anion Radicals)

Substance	Conditions/electrode/technique	Potential V (vs. SCE)
Acetone	DMF, 0.1 *M* TEABr/Hg/pol	$E_{1/2} = -2.84$
1-Naphthyphenylacetylene	DMF, 0.03 *M* TBAI/Hg/pol	$E_{1/2} = -1.91$
1-Naphthalenecarboxyaldehyde	-/Hg/pol	$E_{1/2} = -0.91$
2-Naphthalenecarboxyaldehyde	-/Hg/pol	$E_{1/2} = -0.96$
2-Phenanthrenecarboxaldehyde	-/Hg/pol	$E_{1/2} = -1.00$
3-Phenanthrenecarboxaldehyde	-/Hg/pol	$E_{1/2} = -0.94$
9-Phenanthrenecarboxaldehyde	-/Hg/pol	$E_{1/2} = -0.83$
1-Anthracenecarboxaldehyde	-/Hg/pol	$E_{1/2} = -0.75$
1-Pyrenecarboxaldehyde	-/Hg/pol	$E_{1/2} = -0.76$
2-Pyrenecarboxaldehyde	-/Hg/pol	$E_{1/2} = -1.00$
Anthracene	DMF, 0.1 *M* TBAP/Pt dsk/CV	$E_p = -2.00$
	DMF, 0.5 *M* $TBABF_4$/Hg/CV	$E_{1/2} = -1.93$
	MeCN, 0.1 *M* TEAP/Hg/CV	$E_{1/2} = -2.07$
	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -1.92$
9,10-Dimethylanthracene	DMF, 0.1 *M* TBAP/Pt/CV	$E_p = -2.08$
	MeCN, 0.1 *M* TBAP/Pt/CV	$E_p = -2.10$
1-Phenylanthracene	DMF, 0.5 *M* $TBABF_2$/Hg/CV	$E_{1/2} = -1.91$
	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -1.878$
2-Phenylanthracene	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -1.875$
8-Phenylanthracene	DMF, 0.5 *M* $TBABF_4$/Hg/CV	$E_{1/2} = -1.91$
9-Phenylanthracene	DMF, 0.5 *M* $TBABF_4$/Hg/CV	$E_{1/2} = -1.93$
	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -1.863$
1,8-Diphenylanthracene	DMF, 0.5 *M* $TBABF_4$/Hg/CV	$E_{1/2} = -1.88$
1,9-Diphenylanthracene	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -1.846$
1,10-Diphenylanthracene	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -1.786$
8,9-Diphenylanthracene	DMF, 0.5 *M* $TBABF_4$/Hg/CV	$E_{1/2} = -1.90$
9,10-Diphenylanthracene	MeCN, 0.1 *M* TBAP/rot Pt/E swp	$E_{1/2} = -1.83$
	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -1.835$
1,8,9-Triphenylanthracene	DMF, 0.5 *M* $TBABF_4$/Hg/CV	$E_{1/2} = -1.85$
1,8,10-Triphenylanthracene	DMF, 0.5 *M* $TBABF_4$/Hg/CV	$E_{1/2} = -1.81$
9,10-Dibiphenylanthracene	MeCN, 0.1 *M* TBAP/rot Pt/E swp	$E_{1/2} = -1.94$
Benz(a)anthracene	MeCN, 0.1 *M* TEAP/Hg/CV	$E_{1/2} = -2.11$
	MeCN, 0.1 *M* TEAP/Hg/pol	$E_{1/2} = -2.40^a$
Azulene	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -1.10^c$
Annulene	DMF, 0.5 *M* TBAP 0°C/Hg/pol	$E_{1/2} = -1.23$
Benzaldehyde	DMF, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = -1.67$
Benzil	DMSO, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = -1.04$
Benzophenone	-/Hg/pol	$E_{1/2} = -1.80$
	DMF/Pt dsk/CV	$E^\circ = -1.72$
Chrysene	MeCN, 0.1 *M* TEAP/Hg/pol	$E_{1/2} = -2.73^a$
Fluoranthrene	DMF, 0.1 *M* TBAP/Pt dsk/CV	$E_p = -1.76$
Cyclohexanone	DMF, 0.1 *M* TEABr/Hg/pol	$E_{1/2} = -2.79$

Substance	Conditions/electrode/technique	Potential V (vs. SCE)
5,5-Dimethyl-3-phenyl-2-cyclohexen-1-one	DMF, 0.5 *M*/Hg/pol	$E_{1/2} = -1.71$
1,2,3-Indanetrione hydrate (ninhydrin)	DMF, 0.2 *M* $NaNO_3$/Hg/pol	$E_{1/2} = -0.039$
Naphthacene	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -1.53$
Naphthalene	DMF, 0.1 *M* TBAP/Pt dsk/CV	$E_p = -2.55$
	DMF, 0.5 *M* $TBABF_4$/Hg/CV	$E_{1/2} = -2.56$
	DMF, MeCN, 0.1 *M* TEAP/Hg/CV	$E_{1/2} = -2.63$
	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -2.50$
1-Phenylnaphthalene	DMF, 0.5 *M* $TBABF_4$/Hg/CV	$E_{1/2} = -2.36$
1,2-Diphenylnaphthalene	DMF, 0.5 *M* $TBABF_4$/Hg/CV	$E_{1/2} = -2.25$
Cyclopentanone	DMF, 0.1 *M* TEABr/Hg/pol	$E_{1/2} = -2.82$
Phenanthrene	MeCN, 0.1 *M* TBAP/Pt wr/CV	$E_{1/2} = -2.47$
	MeCN, 0.1 *M* TEAP/Hg/pol	$E_{1/2} = -2.88$[a]
Pentacene	THF, 0.1 *M* TBAP/rot Pt dsk/E swp	$E_{1/2} = -1.40$
Perylene	MeCN, 0.1 *M* TEAP/Hg/CV	$E_{1/2} = -1.73$
1,3-Diphenyl-1,3-propanedione	DMSO, 0.2 *M* TBAP/Hg/CV	$E_{1/2} = -1.42$
2,2-Dimethyl-1,3-diphenyl-1,3 propanedione	DMSO, TBAP/Hg/CV	$E_{1/2} = -1.80$
Pyrene	DMF, 0.1 *M* TBAP/Pt/CV	$E_p = -2.14$
	MeCN, 0.1 *M* TEAP/Hg/pol	$E_{1/2} = -2.49$[a]
Diphenylsulfone	DMF, TEABr	$E_{1/2} = -2.16$
Triphenylene	MeCN, 0.1 *M* TEAP/Hg/pol	$E_{1/2} = -2.87$[a]
9,10-Anthraquinone	DMF, 0.5 *M* TBAP, 20°/Pt dsk/CV	$E_{1/2} = -1.01$
1,4-Benzoquinone	MeCN, 0.1 *M* TEAP/Pt/CV	$E_p = -0.54$
1,4-Naphthohydroquinone, dipotassium salt	DMF, 0.5 *M* TBAP, 20°/Pt dsk/CV	$E_{1/2} = -1.55$
Rubrene	DMF, 0.1 *M* TBAP/Pt dsk/CV	$E_p = -1.48$
	DMF, 0.1 *M* TBAI/Hg/pol	$E_{1/2} = -1.410$
Benzocyclooctatetraene	THF, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = -2.13$
sym-Dibenzocyclooctatetraene	THF, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = -2.29$
Ubiquinone-6	MeCN, 0.1 *M* TEAP/Pt/CV	$E_p = -1.05$[e]
$(9\text{-Phenyl-fluorenyl})^+$	10.2 *M* H_2SO_4/Hg/CV	$E_p = -0.01$[b]
$(\text{Triphenylcyclopropenyl})^+$	MeCN, 0.1 *M* TEAP/Hg/CV	$E_p = -1.87$
$(\text{Triphenylmethyl})^+$	MeCN, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = 0.27$
	H_2SO_4, 10.2 *M*/Hg/CV	$E_p = -0.58$[b]
$(\text{Tribiphenylmethyl})^+$	MeCN, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = 0.19$
$(\text{Tri-4-}t\text{-butyl-5-phenylmethyl})^+$	MeCN, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = 0.13$
$(\text{Tri-4-isopropylphenylmethyl})^+$	MeCN, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = 0.07$
$(\text{Tri-4-methylphenylmethyl})^+$	MeCN, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = 0.05$
$(\text{Tri-4-cyclopropylphenylmethyl})^+$	MeCN, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = 0.01$
$(\text{Tropylium})^+$	MeCN, 0.1 *M* TBAP/Hg/pol	$E_{1/2} = -0.17$
	DMF, 0.15 *M* TBAI/Hg/pol	$E_{1/2} = -1.55$
	DMF, 0.15 *M* TBAI/Hg/pol	$E_{1/2} = -1.55$
	DMF, 0.15 *M* TBAI/Hg/pol	$E_{1/2} = -1.57$
	DMF, 0.15 *M* TBAI/Hg/pol	$E_{1/2} = -1.60$
	DMF, 0.15 *M* TBAI/Hg/pol	$E_{1/2} = -1.87$
	DMF, 0.15 *M* TBAI/Hg/pol	$E_{1/2} = -1.96$
	DMF, 0.15 *M* TBAI/Hg/pol	$E_{1/2} = -2.05$

Oxidation Potentials (Products are Cation Radicals)

Anthracene	CH_2Cl_2, 0.2 *M* $TBABF_4$, –70°C/Pt dsk/CV	$E_p = +0.73$[d]
9,10-Dimethylanthracene	MeCN, 0.1 *M* $LiClO_4$/Pt wr/CV	$E_p = +1.0$
9,10-Dipropylanthracene	MeCN, 0.1 *M* TEAP/Pt/CV	$E_p = +1.08$
1,8-Diphenylanthracene	CH_2Cl_2, 0.2 *M* $TPrACF_3SO_3$/rot Pt wr/E swp	$E_{1/2} = +1.34$
8,9-Diphenylanthracene	CH_2Cl_2, 0.2 *M* $TPrACF_3SO_3$/rot Pt wr/E swp	$E_{1/2} = +1.30$
9,10-Diphenylanthracene	MeCN/Pt/CV	$E_p = +1.22$
Perylene	MeCN, 0.1 *M* TBAP/Pt/CV	$E_p = +1.34$
Pyrene	DMF, 0.1 *M* TBAP/Pt dsk/CV	$E_p = +1.25$
Rubrene	DMF, 0.1 *M* TBAP/Pt dsk/CV	$E_p = +1.10$
Tetracene	CH_2Cl_2, 0.2 *M* $TBABF_4$, –70°C/Pt wr/CV	$E_p = +0.35$[d]
1,4-Dithiabenzene	MeCN, 0.1 *M* TEAP/Pt dsk/rot	$E_{1/2} = +0.69$
1,4-Dithianaphthalene	MeCN, 0.1 *M* TEAP/Pt dsk/rot	$E_{1/2} = +0.80$
Thianthrene	0.1 *M* TPAP/Pt/CV	$E_{1/2} = +1.28$

[a] vs 0.01 M $Ag/AgClO_4$
[b] vs. Hg/Hg_2SO_4, 17 M H_2SO_4
[c] vs Hg pool
[d] vs Ag/saturated $AgNO_3$
[e] vs Ag/0.01 M Ag+

pH SCALE FOR AQUEOUS SOLUTIONS

A.K. Covington

A Working Party of IUPAC, after extensive considerations over five years, has recently produced a report (1) which sets pH firmly within the International System of Units (SI). A summary of these important developments is given below.

The concept of pH is unique amongst the commonly encountered physicochemical quantities in that, in terms of its definition,

$$\mathrm{pH} = -\lg a_{\mathrm{H}} \qquad (1)$$

it involves a single ion quantity, the activity of the hydrogen ion, which is immeasurable by any thermodynamically valid method and requires a convention for its evaluation.

pH was originally defined by Sørensen (2) in terms of the concentration of hydrogen ions (in modern nomenclature) as $\mathrm{pH} = -\lg (c_{\mathrm{H}}/c^{\mathrm{o}})$ where c_{H} is the hydrogen ion concentration in mol dm^{-3}, and $c^{\mathrm{o}} = 1$ mol dm^{-3} is the standard amount concentration. Subsequently (3), it was accepted as more satisfactory to define pH in terms of the relative activity of hydrogen ions in solution

$$\mathrm{pH} = -\lg a_{\mathrm{H}} = -\lg (m_{\mathrm{H}}\gamma_{\mathrm{H}}/m^{\mathrm{o}}) \qquad (2)$$

where a_{H} is the relative (molality basis) activity and γ_{H} is the molal activity coefficient of the hydrogen ion H^+ at the molality m_{H} , and m^{o} the standard molality. The quantity pH is intended to be a measure of the activity of hydrogen ions in solution. However, since it is defined in terms of a quantity that cannot be measured by a thermodynamically valid method, eqn.(2) can only be considered a *notional definition* of pH.

pH being a single ion quantity, it is not determinable in terms of a fundamental (or base) unit of any measurement system, and there is difficulty providing a proper basis for the traceability of pH measurements. A satisfactory approach is now available in that pH determinations can be incorporated into the International System (SI) if they can be traced to measurements made using a method that fulfils the definition of a 'primary method of measurement' (4).

The essential feature of a primary method is that it must operate according to a well-defined measurement equation in which all of the variables can be determined experimentally in terms of SI units. Any limitation in the determination of the experimental variables, or in the theory, must be included within the estimated uncertainty of the method if traceability to the SI is to be established. If a convention were used without an estimate of its uncertainty, true traceability to SI would not be established. The electrochemical cell without liquid junction, known as the Harned cell (5), fulfils the definition of a primary method for the measurement of the acidity function, $\mathrm{p}(a_{\mathrm{H}}\gamma_{\mathrm{Cl}})$, and subsequently of the pH of buffer solutions.

The Harned cell is written as

$$\mathrm{Pt} \mid \mathrm{H_2} \mid \text{buffer S}, \mathrm{Cl^-} \mid \mathrm{AgCl} \mid \mathrm{Ag} \qquad \text{Cell I}$$

and contains a standard buffer, S, with chloride ions, as potassium or sodium chloride, added in order to use the silver-silver chloride electrode as reference electrode. The application of the Nernst equation to the spontaneous cell reaction of Cell I:

$$^1/_2\ \mathrm{H_2} + \mathrm{AgCl} \rightarrow \mathrm{Ag(s)} + \mathrm{H^+} + \mathrm{Cl^-}$$

yields the potential difference E_{I} of the cell (corrected to 1 atm (101.325 kPa), the partial pressure of hydrogen gas used in electrochemistry in preference to 100 kPa) as

$$E_{\mathrm{I}} = E^{\mathrm{o}} - (RT/F)\ln 10 \lg [(m_{\mathrm{H}}\gamma_{\mathrm{H}}/m^{\mathrm{o}})(m_{\mathrm{Cl}}\gamma_{\mathrm{Cl}}/m^{\mathrm{o}})] \qquad (3)$$

which can be rearranged, since $a_{\mathrm{H}} = m_{\mathrm{H}}\gamma_{\mathrm{H}}/m^{\mathrm{o}}$, to give the acidity function

$$\mathrm{p}(a_{\mathrm{H}}\,\gamma_{\mathrm{Cl}}) = -\lg(a_{\mathrm{H}}\gamma_{\mathrm{Cl}}) = (E_{\mathrm{I}} - E^{\mathrm{o}})/[(RT/F)\ln 10] + \lg(m_{\mathrm{Cl}}/m^{\mathrm{o}}) \qquad (4)$$

where E^{o} is the standard potential difference of the cell, and hence of the silver-silver chloride electrode, and γ_{Cl} is the activity coefficient of the chloride ion.

The standard potential difference of the silver/silver chloride electrode, E^{o}, is determined from a Harned cell in which only HCl is present at a fixed molality (e.g. $m = 0.01$ mol kg^{-1})

$$\mathrm{Pt} \mid \mathrm{H_2} \mid \mathrm{HCl}\ (m) \mid \mathrm{AgCl} \mid \mathrm{Ag} \qquad \text{Cell Ia}$$

The application of the Nernst equation to the HCl cell (Ia) gives

$$E_{\mathrm{Ia}} = E^{\mathrm{o}} - (2RT/F)\ln 10 \lg[(m_{\mathrm{HCl}}/m^{\mathrm{o}})(\gamma_{\pm\mathrm{HCl}})] \qquad (5)$$

where E_{Ia} has been corrected to 1 atmosphere partial pressure of hydrogen gas (101.325 kPa) and $\gamma_{\pm\mathrm{HCl}}$ is the mean ionic activity coefficient of HCl.

Values of the activity coefficient ($\gamma_{\pm\mathrm{HCl}}$) at molality 0.01 mol kg^{-1} and various temperatures were given by Bates and Robinson (6). The standard potential difference depends on the method of preparation of the electrodes, but individual determinations of the activity coefficient of HCl at 0.01 mol kg^{-1} are more uniform than values of E^{o}. Hence the practical determination of the potential difference of the cell with HCl at 0.01 mol kg^{-1} is recommended at 298.15 K at which the mean ionic activity coefficient is 0.904. (It is unnecessary to repeat the measurement of E^{o} at other temperatures but simply to correct published smoothed values by the observed difference in E^0 at 298.15 K)

In national metrology institutes (NMIs), measurements of Cells I and Ia are often done simultaneously in a thermostat bath. Subtracting eqn.(5) from (3) gives

$$\Delta E = E_{\mathrm{I}} - E_{\mathrm{Ia}} = -(RT/F)\ln 10\{\lg[(m_{\mathrm{H}}\gamma_{\mathrm{H}}/m^{\mathrm{o}})(m_{\mathrm{Cl}}\gamma_{\mathrm{Cl}}/m^{\mathrm{o}})] - \lg[(m_{\mathrm{HCl}}/m^{\mathrm{o}})^2\gamma^2_{\pm\mathrm{HCl}}]\} \qquad (6)$$

which is independent of the standard potential difference. Therefore, the subsequently calculated pH does not depend on the standard potential difference and hence does not depend on the assumption that the standard potential of the hydrogen electrode is zero at all temperatures. Therefore, the Harned cell gives an exact comparison between hydrogen ion activities at different temperatures.

The quantity $\mathrm{p}(a_{\mathrm{H}}\gamma_{\mathrm{Cl}}) = -\lg (a_{\mathrm{H}}\gamma_{\mathrm{Cl}})$, on the left hand side of (4), is called the acidity function (5). To obtain the quantity pH according to eqn. (2) from the acidity function, it is necessary to evaluate $\lg \gamma_{\mathrm{Cl}}$ independently. This is done in two steps: (i) the

value of lg ($a_H\gamma_{Cl}$) at zero chloride molality, lg ($a_H\gamma_{Cl}$)°, is evaluated and (ii) a value for the activity of the chloride ion γ^o_{Cl}, at zero chloride molality (sometimes referred to as the limiting or 'trace' activity coefficient) is calculated using the Bates-Guggenheim convention (7). The value of lg ($a_H\gamma_{Cl}$)° corresponding to zero chloride molality is determined by linear extrapolation of measurements using Harned cells with at least three added molalities of sodium or potassium chloride (I < 0.1 mol kg^{-1}).

The value of lg ($a_H\gamma_{Cl}$)° corresponding to zero chloride molality is determined by linear extrapolation of measurements using Harned cells with at least three added molalities of sodium or potassium chloride (I < 0.1 mol kg^{-1}) in accord with eqn. (7):

$$-\lg (a_H\gamma_{Cl}) = -\lg (a_H\gamma_{Cl})^o + Sm_{Cl} \quad (7)$$

where S is an empirical, temperature dependent, constant.

The Bates-Guggenheim convention (7) assumes that the trace activity coefficient of the chloride ion γ^o_{Cl} is given by

$$\lg \gamma^o_{Cl} = -A\, I^{1/2} / (1 + Ba\, I^{1/2}) \quad (8)$$

where A is the Debye-Hückel temperature dependent constant (limiting slope), a is the *mean* distance of closest approach of the ions (ion size parameter), Ba is set equal to 1.5 (mol kg^{-1})$^{-1/2}$ at all temperatures in the range 5-50 °C, and I is the ionic strength of the buffer (which for its evaluation requires knowledge of appropriate acid dissociation constants).

The various stages in the assignment of primary standard pH values are combined in eqn. (9), which is derived from eqns. (4), (5) and (8)

$$\mathrm{pH(PS)} = \lim m_{Cl\to 0} \{(E_I - E^o)/[(RT/F)\ln 10] + \lg (m_{Cl}/m^o)\} - AI^{1/2}/[1 + 1.5\,(I/m^o)^{1/2}] \quad (9)$$

In order for a particular buffer solution to be considered a primary buffer solution, it must be of the "highest metrological" quality (4) in accordance with the definition of a primary standard. It is recommended that it have the following attributes (9):

1. High buffer value in the range 0.016-0.07 (mol OH^-)/pH.
2. Small dilution value at half concentration (change in pH with change in buffer concentration) in the range 0.01-0.20.
3. Small dependence of pH on temperature less than ± 0.01 K^{-1}.
4. Low residual liquid junction potential < 0.01 in pH.
5. Ionic strength ≤0.1 mol kg^{-1} to permit applicability of Bates-Guggenheim convention.
6. NMI certificate for specific batch.
7. Reproducible purity of preparation (lot to lot differences of |ΔpH(PS)| < 0.003).
8. Long term stability of stored solid material.

Values for the above and other important parameters for the primary and secondary buffer materials are given in Table 1.

Primary Standard Buffers

As there can be significant variations in the purity of samples of a buffer of the same nominal chemical composition, it is essential that the primary buffer material used has been certified with values that have been measured with Cell I. The Harned cell is used by many national metrological institutes for accurate measurements of pH of buffer solutions.

Typical values of the pH(PS) of the seven solutions from the six accepted primary standard reference buffers, which meet the conditions stated above, are listed in Table 2. Batch-to-batch variations in purity can result in changes in the pH value of samples of at most 0.003. The typical values in Table 2 should not be used in place of the certified value (from a Harned cell measurement) for a specific batch of buffer material.

The required attributes listed above effectively limit the range of primary buffers available to between pH 3 and 10 (at 25 °C). Calcium hydroxide and potassium tetraoxalate are excluded because the contribution of hydroxide or hydrogen ions to the ionic strength is significant. Also excluded are the nitrogen bases of the type BH^+ (such as tris(hydroxymethyl)aminomethane and piperazine phosphate) and the zwitterionic buffers (e.g. HEPES and MOPS (10)). These do not comply because either the Bates-Guggenheim convention is not applicable, or the liquid junction potentials are high. This means the choice of primary standards is restricted to buffers derived from oxy-carbon, -phosphorus, -boron and mono, di- and tri-protic carboxylic acids. The uncertainties (11) associated with Harned cell measurements are calculated (1) to be 0.004 in pH at NMIs, with typical variation between batches of primary standard buffers of 0.003.

Secondary Standards

Substances that do not fulfil all the criteria for primary standards, but to which pH values can be assigned using Cell I are considered to be secondary standards (Table 3). Reasons for their exclusion as primary standards include difficulties in achieving consistent and suitable chemical quality (e.g. acetic acid is a liquid), suspected high liquid junction potential, or inappropriateness of the Bates-Guggenheim convention (e.g. other charge-type buffers). The uncertainty is higher (e.g. 0.01) for biological buffers. Certain other substances, which cannot be used in cells containing hydrogen gas electrodes, are also classed as secondary standards.

Calibration Procedures

(a) One-point calibration

A single point calibration is insufficient to determine both slope and one-point parameters. The theoretical value for the slope can be assumed but the practical slope may be up to 5% lower. Alternatively, a value for the practical slope can be assumed from the manufacturer's prior calibration. The one-point calibration therefore yields only an estimate of pH(X). Since both parameters may change with age of the electrodes, this is not a reliable procedure.

(b) Two-point calibration [target uncertainty: 0.02-0.03 at 25 °C]

In the majority of practical applications, glass electrodes cells are calibrated by a two-point calibration, or bracketing, procedure using two standard buffer solutions, with pH values, pH(S_1) and pH(S_2), bracketing the unknown pH(X). Bracketing is often taken to mean that the pH(S_1) and pH(S_2) buffers selected from Table 2 should be those that are immediately above and below pH(X). This may not be appropriate in all situations and choice of a wider range may be better.

(c) Multi-point calibration [target uncertainty: 0.01-0.03 at 25 °C].
Multi-point calibration is carried out using up to five standard buffers . The use of more than five points yields no significant improvement in the statistical information obtainable.
Details of uncertainty computations (11) have been given (1).

Measurement of pH and choice of pH Standard Solutions

1a) If pH is not required to better than ±0.05 any pH standard solution may be selected.
1b) If pH is required to ±0.002 and interpretation in terms of hydrogen ion concentration or activity is desired, choose a standard solution, pH(PS), to match X as closely as possible in terms of pH, composition and ionic strength.
2) Alternatively, a bracketing procedure may be adopted whereby two standard solutions are chosen whose pH values, pH(S1), pH(S2) are on either side of pH(X). Then if the corresponding potential difference measurements are E(S1), E(S2), E(X), then pH(X) is obtained from

$$\mathrm{pH(X)} = \mathrm{pH(S1)} + [E(\mathrm{X}) - E(\mathrm{S1})]/\ \%k$$

where $\%k = 100[E(\mathrm{S2}) - E(\mathrm{S1})]/[\mathrm{pH(S2)} - \mathrm{pH(S1)}]$ is the apparent percentage slope. This procedure is very easily done on some pH meters simply by adjusting downwards the slope factor control with the electrodes in S2. The purpose of the bracketing procedure is to compensate for deficiencies in the electrodes and measuring system.

Information to be given about the measurement of pH(X)

The standard solutions selected for calibration of the pH meter system should be reported with the measurement as follows:

System calibrated with pH(S) = ... at ...K.

System calibrated with two primary standards, pH(PS1) =.... and pH(PS2) =....at ....K.

System calibrated with *n* standards, pH(S1) =.... , pH(S2) =.... etc. at....K.

Interpretation of pH(X) in terms of hydrogen ion concentration

The defined pH has no simple interpretation in terms of hydrogen ion concentration but the mean ionic activity coefficient of a typical 1:1 electrolyte can be used to obtain hydrogen ion concentration subject to an uncertainty of 3.9% in concentration, corresponding to 0.02 in pH.

References

1. Buck, R.P., Rondinini, S., Covington, A.K., Baucke, F.G.K., Brett, C.M.A., Camoes, M.F.C., Milton, M.J.T., Mussini, T., Naumann, R., Pratt, K.W., Spitzer, P., and Wilson, G.S. *Pure Appl. Chem.,* 74, 2105, 2002.
2. Sørensen, S.P.L. *Comp. Rend.Trav. Lab. Carlsberg,* 8**,** 1, 1909.
3. Sørensen, S.P.L., and Linderstrøm-Lang, K.L., *Comp. Rend. Trav. Lab. Carlsberg*, 15**,** 1924.
4. BIPM, *Com. Cons. Quantité de Matière* 4, 1998. See also M.J.T. Milton and T.J. Quinn, *Metrologia* 38, 289, 2001.
5. Harned H.S., and Owen, B.B., *The Physical Chemistry of Electrolytic Solutions*, Ch 14, Reinhold, New York, 1958.
6. Bates R.G., and Robinson, R.A., *J. Soln. Chem*. 9, 455, 1980.
7. Bates R.G., and Guggenheim, E.A., *Pure Appl. Chem.* 1, 163, 1960.
8. *International Vocabulary of Basic and General Terms in Metrology* (VIM), Beuth, Berlin, 2nd. Edn. 1994.
9. Bates, R.G. *Determination of pH*, Wiley, New York, 1973.
10. Good, N.E. et al., *Biochem. J.* 5, 467, 1966.
11. *Guide to the Expression of Uncertainty* (GUM), BIPM, IEC, IFCC, ISO, IUPAC, IUPAP, OIML, 1993.

TABLE 1. Summary of Useful Properties of Some Primary and Secondary Standard Buffer Substances and Solutions

Salt or solid substance	Formula	Molality/ mol kg^{-1}	Molar mass/ g mol^{-1}	Density/ g/mL	Amount conc. at 20°C/ mol dm^{-3}	Mass/g to make 1 dm^3	Dilution value $\Delta pH_{1/2}$	Buffer value (β)/ mol OH$^-$ dm^{-3}	pH Temperature coefficient/ K^{-1}
Potassium tetroxalate dihydrate	$KH_3C_4O_8{\cdot}2H_2O$	0.1	254.191	1.0091	0.09875	25.101			
Potassium tetraoxalate dihydrate	$KH_3C_4O_8{\cdot}2H_2O$	0.05	254.191	1.0032	0.04965	12.620	0.186	0.070	0.001
Potassium hydrogen tartrate (sat at 25°C)	$KHC_4H_4O_6$	0.0341	188.18	1.0036	0.034	6.4	0.049	0.027	- 0.0014
Potassium dihydrogen citrate	$KH_2C_6H_5O_7$	0.05	230.22	1.0029	0.04958	11.41	0.024	0.034	- 0.022
Potassium hydrogen phthalate	$KHC_8H_4O_4$	0.05	204.44	1.0017	0.04958	10.12	0.052	0.016	0.00012
Disodium hydrogen orthophosphate +	Na_2HPO_4	0.025	141.958	1.0038	0.02492	3.5379	0.080	0.029	- 0.0028

Salt or solid substance	Formula	Molality/ mol kg^{-1}	Molar mass/ g mol^{-1}	Density/ g/mL	Amount conc. at 20°C/ mol dm^{-3}	Mass/g to make 1 dm^3	Dilution value $\Delta pH_{1/2}$	Buffer value (β)/ mol OH^- dm^{-3}	pH Temperature coefficient/ K^{-1}
potassium dihydrogen orthophosphate	KH_2PO_4	0.025	136.085			3.3912			
Disodium hydrogen orthophosphate +	Na_2HPO_4	0.03043	141.959	1.0020	0.08665	4.302	0.07	0.016	- 0.0028
potassium dihydrogen orthophosphate	KH_2PO_4	0.00869	136.085		0.03032	1.179			
Disodium tetraborate decahydrate	$Na_2B_4O_7{\cdot}10H_2O$	0.05	381.367	1.0075	0.04985	19.012			
Disodium tetraborate decahydrate	$Na_2B_4O_7{\cdot}10H_2O$	0.01	381.367	1.0001	0.00998	3.806	0.01	0.020	- 0.0082
Sodium hydrogen carbonate +	$NaHCO_3$	0.025	84.01	1.0013	0.02492	2.092	0.079	0.029	-0.0096
sodium carbonate	Na_2CO_3	0.025	105.99			2.640			
Calcium hydroxide (sat. at 25°C)	$Ca(OH)_2$	0.0203	74.09	0.9991	0.02025	1.5	-0.28	0.09	-0.033

TABLE 2. Typical Values of pH(PS) for Primary Standards at 0–50°C

	Temperature in °C										
Primary standards (PS)	0	5	10	15	20	25	30	35	37	40	50
Sat. potassium hydrogen tartrate (at 25°C)						3.557	3.552	3.549	3.548	3.547	3.549
0.05 mol kg^{-1} potassium dihydrogen citrate	3.863	3.840	3.820	3.802	3.788	3.776	3.766	3.759	3.756	3.754	3.749
0.05 mol kg^{-1} potassium hydrogen phthalate	4.000	3.998	3.997	3.998	4.000	4.005	4.011	4.018	4.022	4.027	4.050
0.025 mol kg^{-1} disodium hydrogen phosphate + 0.025 mol kg^{-1} potassium dihydrogen phosphate	6.984	6.951	6.923	6.900	6.881	6.865	6.853	6.844	6.841	6.838	6.833
0.03043 mol kg^{-1} disodium hydrogen phosphate + 0.008695 mol kg^{-1} potassium dihydrogen phosphate	7.534	7.500	7.472	7.448	7.429	7.413	7.400	7.389	7.386	7.380	7.367
0.01 mol kg^{-1} disodium tetraborate	9.464	9.395	9.332	9.276	9.225	9.180	9.139	9.102	9.088	9.068	9.011
0.025 mol kg^{-1} sodium hydrogen carbonate + 0.025 mol kg^{-1} sodium carbonate	10.317	10.245	10.179	10.118	10.062	10.012	9.966	9.926	9.910	9.889	9.828

TABLE 3. Values of pH(SS) of Some Secondary Standards from Harned Cell I Measurements

	Temperature in °C									
Secondary standards	**0**	**5**	**10**	**15**	**20**	**25**	**30**	**37**	**40**	**50**
0.05 mol kg^{-1} potassium tetroxalate[a]	1.67	1.67	1.67	1.67	1.68	1.68	1.68	1.69	1.69	1.71
0.05 mol kg^{-1} sodium hydrogen diglycolate[b]		3.47	3.47	3.48	3.48	3.49	3.50	3.52	3.53	3.56
0.1 mol dm^{-3} acetic acid + 0.1 mol dm^{-3} sodium acetate	4.68	4.67	4.67	4.66	4.66	4.65	4.65	4.66	4.66	4.68
mol dm^{-3} acetic acid + 0.1 mol dm^{-3} sodium acetate	4.74	4.73	4.73	4.72	4.72	4.72	4.72	4.73	4.73	4.75
0.02 mol kg^{-1} piperazine phosphate [c]	6.58	6.51	6.45	6.39	6.34	6.29	6.24	6.16	6.14	6.06
0.05 mol kg^{-1} tris hydrochloride + 0.01667 mol kg^{-1} tris [c]	8.47	8.30	8.14	7.99	7.84	7.70	7.56	7.38	7.31	7.07
0.05 mol kg^{-1} disodium tetraborate	9.51	9.43	9.36	9.30	9.25	9.19	9.15	9.09	9.07	9.01
Saturated (at 25 °C) calcium hydroxide	13.42	13.21	13.00	12.81	12.63	12.45	12.29	12.07	11.98	11.71

[a] Potassium trihydrogen dioxalate ($KH_3C_4O_8$)
[b] Sodium hydrogen 2,2'-oxydiacetate
[c] 2-Amino-2-(hydroxymethyl)-1,3 propanediol or tris(hydroxymethyl)aminomethane

PRACTICAL pH MEASUREMENTS ON NATURAL WATERS

A. K. Covington and W. Davison

(1) Dilute solutions and freshwater including 'acid-rain' samples (I < 0.02 mol kg^{-1})

Major problems could be encountered due to errors associated with the liquid junction. It is recommended that either a free diffusion junction is used or it is verified that the junction is working correctly using dilute solutions as follows. For commercial electrodes calibrated with IUPAC aqueous RVS or PS standards, the pH(X) of dilute solutions should be within ±0.02 of those given in Table 1. The difference in determined pH(X) between a stirred and unstirred dilute solution should be < 0.02. The characteristics of glass electrodes are such that below pH 5 the readings should be stable within 2 min, but for pH 5 to 8.8 or so minutes may be necessary to attain stability. Interpretation of pH(X) measured in this way in terms of activity of hydrogen ion, a_{H+} is subject[1] to an uncertainty of ±0.02 in pH.

(2) Seawater

Measurements made by calibration of electrodes with IUPAC aqueous RVS or PS standards to obtain pH(X) are perfectly valid. However, the interpretation of pH(X) in terms of the activity of hydrogen ion is complicated by the non zero residual liquid junction potential as well as by systematic differences between electrode pairs, principally attributable to the reference electrode. For 35‰ salinity seawater (S = 0.035) a_{H+} calculated from pH(X) is typically 12% too low. Special seawater pH scales have been devised to overcome this problem:

(i) The total hydrogen ion scale, pH_T, is defined in terms of the sum of free and complexed (total) hydrogen ion concentrations, where

$$^{T}C_{H} = [H^+] + [HSO_4^-] + [HF].$$

$$\text{So, } pH_T = -\log {}^{T}C_{H}$$

Calibration of the electrodes with a buffer having a composition similar to that of seawater, to which pH_T has been assigned, results in values of pHT(X) (Tables 2, 3) which are accurately interpretable in terms of $^{T}C_{H}$.

(ii) The free hydrogen ion scale, pH_F, is defined, and fully interpretable, in terms of the concentration of free hydrogen ions.

$$pH_F = -\log [H^+]$$

Values of pH_F as a function of temperature have been assigned to the same set of pH_T seawater buffers,and so alternatively can be used for calibration (Tables 2, 3) [2,3]

(3) Estuarine water

Prescriptions for seawater scale buffers are available for a range of salinities. Reliable estuarine pH measurements can be made by calibrating with a buffer of the same salinity as the sample. However, these buffers are difficult to prepare and their use presumes prior knowledge of salinity of the sample. Interpretable measurements of estuarine pH can be made by calibration with IUPAC aqueous RVS or PS standards if the electrode pair is additionally calibrated using a 20‰ salinity seawater buffer.[4] The difference between the assigned pH_{SWS} of the seawater buffer and its measured pH(X) value using RVS or PS standards is

$$\Delta pH = pH_{SWS} - pH(X)$$

Values of ΔpH should be in the range of 0.08 to 0.18. It empirically corrects for differences between the two pH scales and for measurement errors associated with the electrode pair. The pH(X) of samples measured using IUPAC aqueous buffers, can be converted to pH_T or pH_F using the appropriate measured ΔpH:

$$pH_T = pH(X) - \Delta pH$$

$$\text{or } pH_F = pH(X) - \Delta pH$$

This simple procedure is appropriate to pH measurement at salinities from 2‰ to 35‰. For salinities lower than 2‰ the procedures for freshwaters should be adopted.

References

1. Davison, W. and Harbinson, T. R., *Analyst*, 113, 709, 1988.
2. Culberson, C. H., in *Marine Electrochemistry*, Whitfield, M. and Jagner, D., Eds., Wiley, 1981.
3. Millero, F. J., *Limnol. Oceanogr.*, 31, 839, 1986.
4. Covington, A. K., Whalley, P. D., Davison, W., and Whitfield, M., in *The Determination of Trace Metals in Natural Waters*, West, T. S. and Nurnberg, H. W., Eds., Blackwell, Oxford, 1988.
5. Koch, W. F., Marinenko, G., and Paule, R. C., *J. Res. NBS*, 91, 33, 1986.

TABLE 1. pH of Dilute Solutions at 25°C, Degassed and Equilibrated with Air, Suitable as Quality Control Standards

	Ionic strength mmol kg^{-1}	Concentration(x) mmol kg^{-1}	pH p_{CO_2} = 0	pH p_{CO_2} = air
Potassium hydrogen phthalate	10.7	10	4.12	4.12
	1.1	1	4.33	4.33
xKH$_2$PO$_4$ + xNa$_2$HPO$_4$	9.9	2.5	7.07	7.05
xKH$_2$PO$_4$ + 3.5xNa$_2$HPO$_4$	10	0.87	7.61	7.58
Na$_2$B$_4$O$_7$ · 10H$_2$O	10	5	9.20	—
HCl	0.1	0.1	4.03	4.03
SRM2694-I[a]	—	—	4.30	—
SRM2694-II[a]	—	—	3.59	—

Note: The pH of solutions near to pH 4 is virtually independent of temperature over the range of 5 to 30°C.
[a] Simulated rainwater samples are available (Reference 5) from NIST containing sulfate, nitrate, chloride, fluoride, sodium, potassium, calcium and magnesium.

TABLE 2. Composition of Seawater Buffer of Salinity S = 35‰ at 25°C (Reference 3)

Solute	mol dm^{-3}	mol kg^{-1}	g kg^{-1}	g dm^{-3}
NaCl	0.3666	0.3493	20.416	20.946
Na$_2$SO$_4$	0.02926	0.02788	3.96	4.063
KCl	0.01058	0.01008	0.752	0.772
CaCl$_2$	0.01077	0.01026	1.139	1.169
MgCl$_2$	0.05518	0.05258	5.006	5.139
Tris	0.06	0.05717	6.926	7.106
Tris · HCl	0.06	0.05717	9.010	9.244

Tris = tris(hydroxymethyl)aminomethane (HOCH$_2$)$_3$CNH$_2$.
A 20‰ buffer is made by diluting the 35‰ in the ratio 20:35.

TABLE 3. Assigned Values of 20‰ and 35‰ Buffers on Free and Total Hydrogen Ion Scales. Calculated from Equations Provided by Millero (Reference 3)

Temp (°C)	pH$_T$ S = 20‰	pH$_T$ S = 35‰	pH$_F$ S = 20‰	pH$_F$ S = 35‰
5	8.683	8.718	8.759	8.81
10	8.513	8.542	8.597	8.647
15	8.351	8.374	8.442	8.491
20	8.195	8.212	8.292	8.341
25	8.045	8.057	8.149	8.197
30	7.901	7.908	8.011	8.059
35	7.762	7.764	7.879	7.926

BUFFER SOLUTIONS GIVING ROUND VALUES OF pH AT 25°C

A		B		C		D		E	
pH	*x*	pH	*x*	pH	*x*	pH	*x*	pH	*x*
1.00	67.0	2.20	49.5	4.10	1.3	5.80	3.6	7.00	46.6
1.10	52.8	2.30	45.8	4.20	3.0	5.90	4.6	7.10	45.7
1.20	42.5	2.40	42.2	4.30	4.7	6.00	5.6	7.20	44.7
1.30	33.6	2.50	38.8	4.40	6.6	6.10	6.8	7.30	43.4
1.40	26.6	2.60	35.4	4.50	8.7	6.20	8.1	7.40	42.0
1.50	20.7	2.70	32.1	4.60	11.1	6.30	9.7	7.50	40.3
1.60	16.2	2.80	28.9	4.70	13.6	6.40	11.6	7.60	38.5
1.70	13.0	2.90	25.7	4.80	16.5	6.50	13.9	7.70	36.6
1.80	10.2	3.00	22.3	4.90	19.4	6.60	16.4	7.80	34.5
1.90	8.1	3.10	18.8	5.00	22.6	6.70	19.3	7.90	32.0
2.00	6.5	3.20	15.7	5.10	25.5	6.80	22.4	8.00	29.2
2.10	5.10	3.30	12.9	5.20	28.8	6.90	25.9	8.10	26.2
2.20	3.9	3.40	10.4	5.30	31.6	7.00	29.1	8.20	22.9
		3.50	8.2	5.40	34.1	7.10	32.1	8.30	19.9
		3.60	6.3	5.50	36.6	7.20	34.7	8.40	17.2
		3.70	4.5	5.60	38.8	7.30	37.0	8.50	14.7
		3.80	2.9	5.70	40.6	7.40	39.1	8.60	12.2
		3.90	1.4	5.80	42.3	7.50	40.9	8.70	10.3
		4.00	0.1	5.90	43.7	7.60	42.4	8.80	8.5
						7.70	43.5	8.90	7.0
						7.80	44.5	9.00	5.7
						7.90	45.3		
						8.00	46.1		

F		G		H		I		J	
pH	*x*	pH	*x*	pH	*x*	pH	*x*	pH	*x*
8.00	20.5	9.20	0.9	9.60	5.0	10.90	3.3	12.00	6.0
8.10	19.7	9.30	3.6	9.70	6.2	11.00	4.1	12.10	8.0
8.20	18.8	9.40	6.2	9.80	7.6	11.10	5.1	12.20	10.2
8.30	17.7	9.50	8.8	9.90	9.1	11.20	6.3	12.30	12.8
8.40	16.6	9.60	11.1	10.00	10.7	11.30	7.6	12.40	16.2
8.50	15.2	9.70	13.1	10.10	12.2	11.40	9.1	12.50	20.4
8.60	13.5	9.80	15.0	10.20	13.8	11.50	11.1	12.60	25.6
8.70	11.6	9.90	16.7	10.30	15.2	11.60	13.5	12.70	32.2
8.80	9.6	10.00	18.3	10.40	16.5	11.70	16.2	12.80	41.2
8.90	7.1	10.10	19.5	10.50	17.8	11.80	19.4	12.90	53.0
9.00	4.6	10.20	20.5	10.60	19.1	11.90	23.0	13.00	66.0
9.10	2.0	10.30	21.3	10.70	20.2	12.00	26.9		
		10.40	22.1	10.80	21.2				
		10.50	22.7	10.90	22.0				
		10.60	23.3	11.00	22.7				
		10.70	23.8						
		10.80	24.25						

A. 25 ml of 0.2 molar KCl + *x* ml of 0.2 molar HCl.
B. 50 ml of 0.1 molar potassium hydrogen phthalate + *x* ml of 0.1 molar HCl.
C. 50 ml of 0.1 molar potassium hydrogen phthalate + *x* ml of 0.1 molar NaOH.
D. 50 ml of 0.1 molar potassium dihydrogen phosphate + *x* ml of 0.1 molar NaOH.
E. 50 ml of 0.1 molar tris(hydroxymethyl)aminomethane + *x* ml of 0.1 M HCl.
F. 50 ml of 0.025 molar borax + *x* ml of 0.1 molar HCl.
G. 50 ml of 0.025 molar borax + *x* ml of 0.1 molar NaOH.
H. 50 ml of 0.05 molar sodium bicarbonate + *x* ml of 0.1 molar NaOH.
I. 50 ml of 0.05 molar disodium hydrogen phosphate + *x* ml of 0.1 molar NaOH.
J. 25 ml of 0.2 molar KCl + *x* ml of 0.2 molar NaOH.

Final volume of mixtures = 100 ml.

References

1. Bower, V. E., and Bates, R. G., *J. Res. Natl. Bur. Stand.*, 55, 197, 1955 (A–D).
2. Bates, R. G., and Bower, V. E., *Anal. Chem.*, 28, 1322, 1956 (E–J).

DISSOCIATION CONSTANTS OF INORGANIC ACIDS AND BASES

The data in this table are presented as values of pK_a, defined as the negative logarithm of the acid dissociation constant K_a for the reaction

$$BH \rightleftharpoons B^- + H^+$$

Thus $pK_a = -\log K_a$, and the hydrogen ion concentration $[H^+]$ can be calculated from

$$K_a = \frac{[H^+][B^-]}{[BH]}$$

In the case of bases, the entry in the table is for the conjugate acid; e.g., ammonium ion for ammonia. The OH^- concentration in the system

$$NH_3 + H_2O \rightleftharpoons NH_4^+ + OH^-$$

can be calculated from the equation

$$K_b = K_{water}/K_a = \frac{[OH^-][NH_4^+]}{[NH_3]}$$

where $K_{water} = 1.01 \times 10^{-14}$ at 25 °C. Note that $pK_a + pK_b = pK_{water}$.

All values refer to dilute aqueous solutions at zero ionic strength at the temperature indicated. The table is arranged alphabetically by compound name.

Reference

1. Perrin, D. D., *Ionization Constants of Inorganic Acids and Bases in Aqueous Solution, Second Edition,* Pergamon, Oxford, 1982.

Name	Formula	Step	*t*/°C	pK_a
Aluminum(III) ion	Al^{+3}		25	5.0
Ammonia	NH_3		25	9.25
Arsenic acid	H_3AsO_4	1	25	2.26
		2	25	6.76
		3	25	11.29
Arsenious acid	H_2AsO_3		25	9.29
Barium(II) ion	Ba^{+2}		25	13.4
Boric acid	H_3BO_3	1	20	9.27
		2	20	>14
Calcium(II) ion	Ca^{+2}		25	12.6
Carbonic acid	H_2CO_3	1	25	6.35
		2	25	10.33
Chlorous acid	$HClO_2$		25	1.94
Chromic acid	H_2CrO_4	1	25	0.74
		2	25	6.49
Cyanic acid	HCNO		25	3.46
Germanic acid	H_2GeO_3	1	25	9.01
		2	25	12.3
Hydrazine	N_2H_4		25	8.1
Hydrazoic acid	HN_3		25	4.6
Hydrocyanic acid	HCN		25	9.21
Hydrofluoric acid	HF		25	3.20
Hydrogen peroxide	H_2O_2		25	11.62
Hydrogen selenide	H_2Se	1	25	3.89
		2	25	11.0
Hydrogen sulfide	H_2S	1	25	7.05
		2	25	19
Hydrogen telluride	H_2Te	1	18	2.6
		2	25	11
Hydroxylamine	NH_2OH		25	5.94
Hypobromous acid	HBrO		25	8.55
Hypochlorous acid	HClO		25	7.40
Hypoiodous acid	HIO		25	10.5
Iodic acid	HIO_3		25	0.78
Lithium ion	Li^+		25	13.8
Magnesium(II) ion	Mg^{+2}		25	11.4
Nitrous acid	HNO_2		25	3.25
Perchloric acid	$HClO_4$		20	-1.6
Periodic acid	HIO_4		25	1.64
Phosphoric acid	H_3PO_4	1	25	2.16

Name	Formula	Step	t/°C	pK_a
		2	25	7.21
		3	25	12.32
Phosphorous acid	H_3PO_3	1	20	1.3
		2	20	6.70
Pyrophosphoric acid	$H_4P_2O_7$	1	25	0.91
		2	25	2.10
		3	25	6.70
		4	25	9.32
Selenic acid	H_2SeO_4	2	25	1.7
Selenious acid	H_2SeO_3	1	25	2.62
		2	25	8.32
Silicic acid	H_4SiO_4	1	30	9.9
		2	30	11.8
		3	30	12
		4	30	12
Sodium ion	Na^+		25	14.8
Strontium(II) ion	Sr^{+2}		25	13.2
Sulfamic acid	NH_2SO_3H		25	1.05
Sulfuric acid	H_2SO_4	2	25	1.99
Sulfurous acid	H_2SO_3	1	25	1.85
		2	25	7.2
Telluric acid	H_2TeO_4	1	18	7.68
		2	18	11.0
Tellurous acid	H_2TeO_3	1	25	6.27
		2	25	8.43
Tetrafluoroboric acid	HBF_4		25	0.5
Thiocyanic acid	HSCN		25	–1.8
Water	H_2O		25	13.995

DISSOCIATION CONSTANTS OF ORGANIC ACIDS AND BASES

This table lists the dissociation (ionization) constants of over 1070 organic acids, bases, and amphoteric compounds. All data apply to dilute aqueous solutions and are presented as values of pK_a, which is defined as the negative of the logarithm of the equilibrium constant K_a for the reaction

$$HA \rightleftharpoons H^+ + A^-$$

i.e.,

$$K_a = [H^+][A^-]/[HA]$$

where $[H^+]$, etc. represent the concentrations of the respective species in mol/L. It follows that $pK_a = pH + \log[HA] - \log[A^-]$, so that a solution with 50% dissociation has pH equal to the pK_a of the acid.

Data for bases are presented as pK_a values for the conjugate acid, i.e., for the reaction

$$BH^+ \rightleftharpoons H^+ + B$$

In older literature, an ionization constant K_b was used for the reaction $B + H_2O \rightleftharpoons BH^+ + OH^-$. This is related to K_a by

$$pK_a + pK_b = pK_{water} = 14.00 \quad (\text{at } 25°C)$$

Compounds are listed by molecular formula in Hill order.

References

1. Perrin, D. D., *Dissociation Constants of Organic Bases in Aqueous Solution*, Butterworths, London, 1965; Supplement, 1972.
2. Serjeant, E. P., and Dempsey, B., *Ionization Constants of Organic Acids in Aqueous Solution*, Pergamon, Oxford, 1979.
3. Albert, A., "Ionization Constants of Heterocyclic Substances", in Katritzky, A. R., Ed., *Physical Methods in Heterocyclic Chemistry*, Academic Press, New York, 1963.
4. Sober, H.A., Ed., *CRC Handbook of Biochemistry*, CRC Press, Boca Raton, FL, 1968.
5. Perrin, D. D., Dempsey, B., and Serjeant, E. P., pK_a *Prediction for Organic Acids and Bases*, Chapman and Hall, London, 1981.
6. Albert, A., and Serjeant, E. P., *The Determination of Ionization Constants, Third Edition*, Chapman and Hall, London, 1984.
7. Budavari, S., Ed., *The Merck Index, Twelth Edition*, Merck & Co., Whitehouse Station, NJ, 1996.

Mol. form.	Name	Step	*t*/°C	pK_a
CHNO	Cyanic acid		25	3.7
CH_2N_2	Cyanamide		29	1.1
CH_2O	Formaldehyde		25	13.27
CH_2O_2	Formic acid		25	3.75
CH_3NO_2	Nitromethane		25	10.21
CH_3NS_2	Carbamodithioic acid		25	2.95
CH_4N_2O	Urea		25	0.10
CH_4N_2S	Thiourea		25	-1
CH_4O	Methanol		25	15.5
CH_4S	Methanethiol		25	10.33
CH_5N	Methylamine		25	10.66
CH_5NO	*O*-Methylhydroxylamine			12.5
CH_5N_3	Guanidine		25	13.6
C_2HCl_3O	Trichloroacetaldehyde		25	10.04
$C_2HCl_3O_2$	Trichloroacetic acid		20	0.66
$C_2HF_3O_2$	Trifluoroacetic acid		25	0.52
$C_2H_2Cl_2O_2$	Dichloroacetic acid		25	1.35
$C_2H_2O_3$	Glyoxylic acid		25	3.18
$C_2H_2O_4$	Oxalic acid	1	25	1.25
		2	25	3.81
$C_2H_3BrO_2$	Bromoacetic acid		25	2.90
$C_2H_3ClO_2$	Chloroacetic acid		25	2.87
$C_2H_3Cl_3O$	2,2,2-Trichloroethanol		25	12.24
$C_2H_3FO_2$	Fluoroacetic acid		25	2.59
$C_2H_3F_3O$	2,2,2-Trifluoroethanol		25	12.37
$C_2H_3IO_2$	Iodoacetic acid		25	3.18
$C_2H_3NO_4$	Nitroacetic acid		24	1.48
$C_2H_3N_3$	1H-1,2,3-Triazole		20	1.17
$C_2H_3N_3$	1H-1,2,4-Triazole		20	2.27
$C_2H_4N_2$	Aminoacetonitrile		25	5.34
C_2H_4O	Acetaldehyde		25	13.57
C_2H_4OS	Thioacetic acid		25	3.33
$C_2H_4O_2$	Acetic acid		25	4.756
$C_2H_4O_2S$	Thioglycolic acid		25	3.68
$C_2H_4O_3$	Glycolic acid		25	3.83
C_2H_5N	Ethyleneimine		25	8.04
C_2H_5NO	Acetamide		25	15.1
$C_2H_5NO_2$	Acetohydroxamic acid			8.70
$C_2H_5NO_2$	Nitroethane		25	8.46
$C_2H_5NO_2$	Glycine	1	25	2.35
		2	25	9.78
$C_2H_6N_2$	Ethanimidamide		25	12.1
C_2H_6O	Ethanol		25	15.5
C_2H_6OS	2-Mercaptoethanol		25	9.72
$C_2H_6O_2$	Ethyleneglycol		25	15.1
$C_2H_7AsO_2$	Dimethylarsinic acid	1	25	1.57
		2	25	6.27
C_2H_7N	Ethylamine		25	10.65
C_2H_7N	Dimethylamine		25	10.73
C_2H_7NO	Ethanolamine		25	9.50
$C_2H_7NO_3S$	2-Aminoethanesulfonic acid	1	25	1.5
		2	25	9.06
C_2H_7NS	Cysteamine	1	25	8.27
		2	25	10.53
$C_2H_7N_5$	Biguanide	1		11.52
		2		2.93
$C_2H_8N_2$	1,2-Ethanediamine	1	25	9.92
		2	25	6.86
$C_2H_8O_7P_2$	1-Hydroxy-1,1-diphosphonoethane	1		1.35
		2		2.87
		3		7.03
		4		11.3
$C_3H_2O_2$	2-Propynoic acid		25	1.84
C_3H_3NO	Oxazole		33	0.8
C_3H_3NO	Isoxazole		25	-2.0
$C_3H_3NO_2$	Cyanoacetic acid		25	2.47
C_3H_3NS	Thiazole		25	2.52
$C_3H_3N_3O_3$	Cyanuric acid	1		6.88
		2		11.40
		3		13.5
$C_3H_4N_2$	1*H*-Pyrazole		25	2.49
$C_3H_4N_2$	Imidazole		25	6.99

Mol. form.	Name	Step	t/°C	pK_a
$C_3H_4N_2S$	2-Thiazolamine		20	5.36
C_3H_4O	Propargyl alcohol		25	13.6
$C_3H_4O_2$	Acrylic acid		25	4.25
$C_3H_4O_3$	Pyruvic acid		25	2.39
$C_3H_4O_4$	Malonic acid	1	25	2.85
		2	25	5.70
$C_3H_4O_5$	Hydroxypropanedioic acid	1		2.42
		2		4.54
$C_3H_5BrO_2$	3-Bromopropanoic acid		25	4.00
$C_3H_5ClO_2$	2-Chloropropanoic acid		25	2.83
$C_3H_5ClO_2$	3-Chloropropanoic acid		25	3.98
$C_3H_6N_2$	3-Aminopropanenitrile		20	7.80
$C_3H_6N_6$	1,3,5-Triazine-2,4,6-triamine		25	5.00
C_3H_6O	Allyl alcohol		25	15.5
$C_3H_6O_2$	Propanoic acid		25	4.87
$C_3H_6O_2S$	(Methylthio)acetic acid		25	3.66
$C_3H_6O_3$	Lactic acid		25	3.86
$C_3H_6O_3$	3-Hydroxypropanoic acid		25	4.51
$C_3H_6O_4$	Glyceric acid		25	3.52
C_3H_7N	Allylamine		25	9.49
C_3H_7N	Azetidine		25	11.29
C_3H_7NO	2-Propanone oxime		25	12.42
$C_3H_7NO_2$	*L*-Alanine	1	25	2.34
		2	25	9.87
$C_3H_7NO_2$	β-Alanine	1	25	3.55
		2	25	10.24
$C_3H_7NO_2$	Sarcosine	1	25	2.21
		2	25	10.1
$C_3H_7NO_2S$	*L*-Cysteine	1	25	1.5
		2	25	8.7
		3	25	10.2
$C_3H_7NO_3$	*L*-Serine	1	25	2.19
		2	25	9.21
$C_3H_7NO_5S$	*DL*-Cysteic acid	1	25	1.3
		2	25	1.9
		3	25	8.70
$C_3H_7N_3O_2$	Glycocyamine		25	2.82
$C_3H_8O_2$	Ethylene glycol monomethyl ether		25	14.8
$C_3H_8O_3$	Glycerol		25	14.15
C_3H_9N	Propylamine		25	10.54
C_3H_9N	Isopropylamine		25	10.63
C_3H_9N	Trimethylamine		25	9.80
C_3H_9NO	2-Methoxyethylamine		25	9.40
C_3H_9NO	Trimethylamine oxide		20	4.65
$C_3H_{10}N_2$	1,2-Propanediamine, (±)	1	25	9.82
		2	25	6.61
$C_3H_{10}N_2$	1,3-Propanediamine	1	25	10.55
		2	25	8.88
$C_3H_{10}N_2O$	1,3-Diamino-2-propanol	1	20	9.69
		2	20	7.93
$C_3H_{11}N_3$	1,2,3-Triaminopropane	1	20	9.59
		2	20	7.95
$C_4H_4FN_3O$	Flucytosine			3.26
$C_4H_4N_2$	Pyrazine		20	0.65
$C_4H_4N_2$	Pyrimidine		20	1.23
$C_4H_4N_2$	Pyridazine		20	2.24
$C_4H_4N_2O_2$	Uracil		25	9.45
$C_4H_4N_2O_3$	Barbituric acid		25	4.01
$C_4H_4N_2O_5$	Alloxanic acid		25	6.64
$C_4H_4N_4O_2$	5-Nitropyrimidinamine		20	0.35
$C_4H_4O_2$	2-Butynoic acid		25	2.62
$C_4H_4O_4$	Maleic acid	1	25	1.92
		2	25	6.23
$C_4H_4O_4$	Fumaric acid	1	25	3.02
		2	25	4.38
$C_4H_4O_5$	Oxaloacetic acid	1	25	2.55
		2	25	4.37
		3	25	13.03
C_4H_5N	Pyrrole		25	-3.8
$C_4H_5NO_2$	Succinimide		25	9.62
$C_4H_5N_3$	2-Pyrimidinamine		20	3.45
$C_4H_5N_3$	4-Pyrimidinamine		20	5.71
$C_4H_5N_3O$	Cytosine	1		4.60
		2		12.16
$C_4H_5N_3O_2$	6-Methyl-1,2,4-triazine-3,5(2H,4H)-dione			7.6
$C_4H_6N_2$	1-Methylimidazol		25	6.95
$C_4H_6N_4O_3$	Allantoin		25	8.96
$C_4H_6N_4O_3S_2$	Acetazolamide			7.2
$C_4H_6O_2$	*trans*-Crotonic acid		25	4.69
$C_4H_6O_2$	3-Butenoic acid		25	4.34
$C_4H_6O_2$	Cyclopropanecarboxylic acid		25	4.83
$C_4H_6O_3$	2-Oxobutanoic acid		25	2.50
$C_4H_6O_3$	Acetoacetic acid		25	3.6
$C_4H_6O_4$	Succinic acid	1	25	4.21
		2	25	5.64
$C_4H_6O_4$	Methylmalonic acid	1	25	3.07
		2	25	5.76
$C_4H_6O_5$	Malic acid	1	25	3.40
		2	25	5.11
$C_4H_6O_6$	*DL*-Tartaric acid	1	25	3.03
		2	25	4.37
$C_4H_6O_6$	*meso*-Tartaric acid	1	25	3.17
		2	25	4.91
$C_4H_6O_6$	*L*-Tartaric acid	1	25	2.98
		2	25	4.34
$C_4H_6O_8$	Dihydroxytartaric acid		25	1.92
$C_4H_7ClO_2$	2-Chlorobutanoic acid			2.86
$C_4H_7ClO_2$	3-Chlorobutanoic acid			4.05
$C_4H_7ClO_2$	4-Chlorobutanoic acid			4.52
$C_4H_7NO_2$	4-Cyanobutanoic acid		25	2.42
$C_4H_7NO_3$	*N*-Acetylglycine		25	3.67
$C_4H_7NO_4$	Iminodiacetic acid	1		2.98
		2		9.89
$C_4H_7NO_4$	*L*-Aspartic acid	1	25	1.99
		2	25	3.90
		3	25	9.90
$C_4H_7N_3O$	Creatinine	1	25	4.8
		2		9.2
$C_4H_7N_5$	2,4,6-Pyrimidinetriamine		20	6.84
$C_4H_8N_2O_3$	*L*-Asparagine	1	20	2.1
		2	20	8.80
$C_4H_8N_2O_3$	*N*-Glycylglycine	1	25	3.14
		2		8.17
$C_4H_8O_2$	Butanoic acid		25	4.83
$C_4H_8O_2$	2-Methylpropanoic acid		20	4.84
$C_4H_8O_3$	3-Hydroxybutanoic acid, (±)		25	4.70
$C_4H_8O_3$	4-Hydroxybutanoic acid		25	4.72
$C_4H_8O_3$	Ethoxyacetic acid		18	3.65
C_4H_9N	Pyrrolidine		25	11.31

Mol. form.	Name	Step	t/°C	pK_a
C_4H_9NO	Morpholine		25	8.50
$C_4H_9NO_2$	2-Methylalanine	1	25	2.36
		2	25	10.21
$C_4H_9NO_2$	*N,N*-Dimethylglycine		25	9.89
$C_4H_9NO_2$	*DL*-2-Aminobutanoic acid	1	25	2.29
		2	25	9.83
$C_4H_9NO_2$	4-Aminobutanoic acid	1	25	4.031
		2	25	10.556
$C_4H_9NO_2S$	*DL*-Homocysteine	1	25	2.22
		2	25	8.87
		3	25	10.86
$C_4H_9NO_3$	*L*-Threonine	1	25	2.09
		2	25	9.10
$C_4H_9NO_3$	*L*-Homoserine	1	25	2.71
		2	25	9.62
$C_4H_9N_3O_2$	Creatine	1	25	2.63
		2	25	14.3
$C_4H_{10}N_2$	Piperazine	1	25	9.73
		2	25	5.33
$C_4H_{10}N_2O_2$	2,4-Diaminobutanoic acid	1	25	1.85
		2	25	8.24
		3	25	10.44
$C_4H_{10}O_4$	1,2,3,4-Butanetetrol			13.9
$C_4H_{11}N$	Butylamine		25	10.60
$C_4H_{11}N$	*sec*-Butylamine		25	10.56
$C_4H_{11}N$	*tert*-Butylamine		25	10.68
$C_4H_{11}N$	Diethylamine		25	10.84
$C_4H_{11}NO_3$	Tris(hydroxymethyl) methylamine		20	8.3
$C_4H_{12}N_2$	1,4-Butanediamine	1	25	10.80
		2	25	9.63
C_5H_4BrN	3-Bromopyridine		25	2.84
C_5H_4ClN	2-Chloropyridine		25	0.49
C_5H_4ClN	3-Chloropyridine		25	2.81
C_5H_4ClN	4-Chloropyridine		25	3.83
C_5H_4FN	2-Fluoropyridine		25	-0.44
$C_5H_4N_2O_2$	4-Nitropyridine		25	1.61
$C_5H_4N_4$	1*H*-Purine	1	20	2.30
		2	20	8.96
$C_5H_4N_4O$	Hypoxanthine		25	8.7
$C_5H_4N_4O$	Allopurinol			10.2
$C_5H_4N_4O_3$	Uric acid		12	3.89
$C_5H_4N_4S$	1,7-Dihydro-6H-purine-6-thione	1		7.77
		2		11.17
$C_5H_4O_2S$	2-Thiophenecarboxylic acid		25	3.49
$C_5H_4O_2S$	3-Thiophenecarboxylic acid		25	4.1
$C_5H_4O_3$	2-Furancarboxylic acid		25	3.16
$C_5H_4O_3$	3-Furancarboxylic acid		25	3.9
C_5H_5N	Pyridine		25	5.23
C_5H_5NO	2-Pyridinol	1	20	0.75
		2	20	11.65
C_5H_5NO	3-Pyridinol	1	20	4.79
		2	20	8.75
C_5H_5NO	4-Pyridinol	1	20	3.20
		2	20	11.12
C_5H_5NO	2(1H)-Pyridinone	1	20	0.75
		2	20	11.65
C_5H_5NO	Pyridine-1-oxide		24	0.79
$C_5H_5NO_2$	1*H*-Pyrrole-2-carboxylic acid		20	4.45
$C_5H_5NO_2$	1*H*-Pyrrole-3-carboxylic acid		20	5.00
$C_5H_5N_3O$	Pyrazinecarboxamide			0.5
$C_5H_5N_5$	Adenine	1		4.3
		2		9.83
$C_5H_5N_5O$	Guanine		40	9.92
$C_5H_6N_2$	2-Pyridinamine		20	6.82
$C_5H_6N_2$	3-Pyridinamine		25	6.04
$C_5H_6N_2$	4-Pyridinamine		25	9.11
$C_5H_6N_2$	2-Methylpyrazine		27	1.45
$C_5H_6N_2O_2$	Thymine		25	9.94
$C_5H_6O_4$	1,1-Cyclopropanedi-carboxylic acid	1	25	1.82
		2	25	7.43
$C_5H_6O_4$	*trans*-1-Propene-1,2-dicarboxylic acid	1	25	3.09
		2	25	4.75
$C_5H_6O_4$	1-Propene-2,3-dicarboxylic acid	1	25	3.85
		2	25	5.45
$C_5H_6O_5$	2-Oxoglutaric acid	1	25	2.47
		2	25	4.68
$C_5H_7NO_3$	5,5-Dimethyl-2,4-oxazolidinedione		37	6.13
$C_5H_7NO_3$	*L*-Pyroglutamic acid		25	3.32
$C_5H_7N_3$	2,5-Pyridinediamine		20	6.48
$C_5H_7N_3$	Methylaminopyrazine		25	3.39
$C_5H_7N_3O_4$	Azaserine			8.55
$C_5H_8N_2$	2,4-Dimethylimidazole		25	8.36
$C_5H_8N_4O_3S_2$	Methazolamide			7.30
$C_5H_8O_2$	*trans*-3-Pentenoic acid		25	4.51
$C_5H_8O_4$	Dimethylmalonic acid		25	3.15
$C_5H_8O_4$	Glutaric acid	1	18	4.32
		2	25	5.42
$C_5H_8O_4$	Methylsuccinic acid	1	25	4.13
		2	25	5.64
$C_5H_9NO_2$	*L*-Proline	1	25	1.95
		2	25	10.64
$C_5H_9NO_3$	5-Amino-4-oxopentanoic acid	1	25	4.05
		2	25	8.90
$C_5H_9NO_3$	*trans*-4-Hydroxyproline	1	25	1.82
		2	25	9.66
$C_5H_9NO_4$	*L*-Glutamic acid	1	25	2.13
		2	25	4.31
		3		9.67
$C_5H_9N_3$	Histamine	1	25	6.04
		2	25	9.75
$C_5H_{10}N_2O_3$	Glycylalanine		25	3.15
$C_5H_{10}N_2O_3$	*L*-Glutamine	1	25	2.17
		2	25	9.13
$C_5H_{10}N_2O_4$	Glycylserine	1	25	2.98
		2	25	8.38
$C_5H_{10}O_2$	Pentanoic acid		20	4.83
$C_5H_{10}O_2$	2-Methylbutanoic acid		25	4.80
$C_5H_{10}O_2$	3-Methylbutanoic acid		25	4.77
$C_5H_{10}O_2$	2,2-Dimethylpropanoic acid		20	5.03
$C_5H_{10}O_4$	*D*-2-Deoxyribose		25	12.61
$C_5H_{10}O_5$	*L*-Ribose		25	12.22
$C_5H_{10}O_5$	*D*-Xylose		18	12.14
$C_5H_{11}N$	Piperidine		25	11.123
$C_5H_{11}N$	*N*-Methylpyrrolidine		25	10.46
$C_5H_{11}NO$	4-Methylmorpholine		25	7.38
$C_5H_{11}NO_2$	*L*-Valine	1	25	2.29
		2	25	9.74

Mol. form.	Name	Step	t/°C	pK_a
$C_5H_{11}NO_2$	*DL*-Norvaline	1		2.36
		2		9.72
$C_5H_{11}NO_2$	*L*-Norvaline	1	25	2.32
		2	25	9.81
$C_5H_{11}NO_2$	*N*-Propylglycine	1	25	2.35
		2	25	10.19
$C_5H_{11}NO_2$	5-Aminopentanoic acid	1	25	4.27
		2	25	10.77
$C_5H_{11}NO_2$	Betaine		0	1.83
$C_5H_{11}NO_2S$	*L*-Methionine	1	25	2.13
		2	25	9.27
$C_5H_{12}N_2O$	Tetramethylurea			2
$C_5H_{12}N_2O_2$	*L*-Ornithine	1	25	1.71
		2	25	8.69
		3	25	10.76
$C_5H_{13}N$	Pentylamine		25	10.63
$C_5H_{13}N$	3-Pentanamine		17	10.59
$C_5H_{13}N$	3-Methyl-1-butanamine		25	10.60
$C_5H_{13}N$	2-Methyl-2-butanamine		19	10.85
$C_5H_{13}N$	2,2-Dimethylpropylamine		25	10.15
$C_5H_{13}N$	Diethylmethylamine		25	10.35
$C_5H_{14}NO$	Choline		25	13.9
$C_5H_{14}N_2$	1,5-Pentanediamine	1	25	10.05
		2	25	10.93
$C_6H_3Cl_3N_2O_2$	4-Amino-3,5,6-trichloro-2-pyridinecarboxlic acid			3.6
$C_6H_3N_3O_7$	2,4,6-Trinitrophenol		24	0.42
$C_6H_4Cl_2O$	2,3-Dichlorophenol		25	7.44
$C_6H_4N_2O_5$	2,4-Dinitrophenol		25	4.07
$C_6H_4N_2O_5$	2,5-Dinitrophenol		15	5.15
$C_6H_4N_4$	Pteridine		20	4.05
C_6H_5BrO	2-Bromophenol		25	8.45
C_6H_5BrO	3-Bromophenol		25	9.03
C_6H_5BrO	4-Bromophenol		25	9.37
$C_6H_5Br_2N$	3,5-Dibromoaniline		25	2.34
C_6H_5ClO	2-Chlorophenol		25	8.56
C_6H_5ClO	3-Chlorophenol		25	9.12
C_6H_5ClO	4-Chlorophenol		25	9.41
$C_6H_5Cl_2N$	2,4-Dichloroaniline		22	2.05
C_6H_5FO	2-Fluorophenol		25	8.73
C_6H_5FO	3-Fluorophenol		25	9.29
C_6H_5FO	4-Fluorophenol		25	9.89
C_6H_5IO	2-Iodophenol		25	8.51
C_6H_5IO	3-Iodophenol		25	9.03
C_6H_5IO	4-Iodophenol		25	9.33
C_6H_5NO	2-Pyridinecarboxaldehyde		25	12.68
C_6H_5NO	4-Pyridinecarboxaldehyde		30	12.05
$C_6H_5NO_2$	Nitrobenzene		0	3.98
$C_6H_5NO_2$	2-Pyridinecarboxylic acid	1	20	0.99
		2	20	5.39
$C_6H_5NO_2$	3-Pyridinecarboxylic acid	1	25	2.00
		2	25	4.82
$C_6H_5NO_2$	4-Pyridinecarboxylic acid	1	25	1.77
		2	25	4.84
$C_6H_5NO_3$	2-Nitrophenol		25	7.23
$C_6H_5NO_3$	3-Nitrophenol		25	8.36
$C_6H_5NO_3$	4-Nitrophenol		25	7.15
$C_6H_5N_3$	1*H*-Benzotriazole		20	1.6
$C_6H_5N_5O$	2-Amino-4-hydroxypteridine	1	20	2.27
		2	20	7.96
$C_6H_5N_5O_2$	Xanthopterin	2	20	6.59
		3	20	9.31
C_6H_6BrN	2-Bromoaniline		25	2.53
C_6H_6BrN	3-Bromoaniline		25	3.53
C_6H_6BrN	4-Bromoaniline		25	3.89
C_6H_6ClN	2-Chloroaniline		25	2.66
C_6H_6ClN	3-Chloroaniline		25	3.52
C_6H_6ClN	4-Chloroaniline		25	3.98
C_6H_6FN	2-Fluoroaniline		25	3.20
C_6H_6FN	3-Fluoroaniline		25	3.59
C_6H_6FN	4-Fluoroaniline		25	4.65
C_6H_6IN	2-Iodoaniline		25	2.54
C_6H_6IN	3-Iodoaniline		25	3.58
C_6H_6IN	4-Iodoaniline		25	3.81
$C_6H_6N_2O$	3-Pyridinecarboxamide		20	3.3
$C_6H_6N_2O$	2-Pyridinecarboxaldehyde oxime	1	20	3.59
		2	20	10.18
$C_6H_6N_2O_2$	2-Nitroaniline		25	-0.25
$C_6H_6N_2O_2$	3-Nitroaniline		25	2.46
$C_6H_6N_2O_2$	4-Nitroaniline		25	1.02
C_6H_6O	Phenol		25	9.99
$C_6H_6O_2$	*p*-Hydroquinone	1	25	9.85
		2	25	11.4
$C_6H_6O_2$	Pyrocatechol	1	25	9.34
		2	25	12.6
$C_6H_6O_2$	Resorcinol	1	25	9.32
		2	25	11.1
$C_6H_6O_2S$	Benzenesulfinic acid		20	1.3
$C_6H_6O_3S$	Benzenesulfonic acid		25	0.70
$C_6H_6O_4$	5-Hydroxy-2-(hydroxymethyl)-4H-pyran-4-one			7.9
$C_6H_6O_4S$	3-Hydroxybenzenesulfonic acid		25	9.07
$C_6H_6O_4S$	4-Hydroxybenzenesulfonic acid		25	9.11
$C_6H_6O_6$	*cis*-1-Propene-1,2,3-tricarboxylic acid		25	1.95
$C_6H_6O_6$	*trans*-1-Propene-1,2,3-tricarboxylic acid	1	25	2.80
		2	25	4.46
C_6H_6S	Benzenethiol		25	6.62
$C_6H_7BO_2$	Benzeneboronic acid			8.83
C_6H_7N	Aniline		25	4.87
C_6H_7N	2-Methylpyridine		25	6.00
C_6H_7N	3-Methylpyridine		25	5.70
C_6H_7N	4-Methylpyridine		25	5.99
C_6H_7NO	2-Aminophenol	1	20	4.78
		2	20	9.97
C_6H_7NO	3-Aminophenol	1	20	4.37
		2	20	9.82
C_6H_7NO	4-Aminophenol	1	25	5.48
		2	25	10.30
C_6H_7NO	2-Methoxypyridine		20	3.28
C_6H_7NO	3-Methoxypyridine		25	4.78
C_6H_7NO	4-Methoxypyridine		25	6.58
$C_6H_7NO_3S$	2-Aminobenzenesulfonic acid		25	2.46
$C_6H_7NO_3S$	3-Aminobenzenesulfonic acid		25	3.74
$C_6H_7NO_3S$	4-Aminobenzenesulfonic acid		25	3.23
$C_6H_8N_2$	*N*-Methylpyridinamine		20	9.65
$C_6H_8N_2$	*o*-Phenylenediamine	1	20	4.57

Mol. form.	Name	Step	t/°C	pK_a
		2	20	0.80
$C_6H_8N_2$	*m*-Phenylenediamine	1	20	5.11
		2	20	2.50
$C_6H_8N_2$	*p*-Phenylenediamine	1	20	6.31
		2	20	2.97
$C_6H_8N_2$	Phenylhydrazine		15	8.79
$C_6H_8O_2$	2,4-Hexadienoic acid		25	4.76
$C_6H_8O_2$	1,3-Cyclohexanedione		25	5.26
$C_6H_8O_4$	2,2-Dimethyl-1,3-dioxane-4,6-dione			5.1
$C_6H_8O_6$	*L*-Ascorbic acid	1	25	4.04
		2	16	11.7
$C_6H_8O_7$	Citric acid	1	25	3.13
		2	25	4.76
		3	25	6.40
$C_6H_8O_7$	Isocitric acid	1	25	3.29
		2	25	4.71
		3	25	6.40
$C_6H_9NO_6$	Nitrilotriacetic acid	1	20	3.03
		2	20	3.07
		3	20	10.70
$C_6H_9NO_6$	*L*-γ-Carboxyglutamic acid	1	25	1.7
		2	25	3.2
		3	25	4.75
		4	25	9.9
$C_6H_9N_3$	4,6-Dimethylpyrimidinamine		20	4.82
$C_6H_9N_3O_2$	*L*-Histidine	1	25	1.80
		2	25	6.04
		3	25	9.33
$C_6H_{10}O_2$	Cyclopentanecarboxylic acid		25	4.99
$C_6H_{10}O_3$	Ethyl acetoacetate		25	10.68
$C_6H_{10}O_4$	3-Methylglutaric acid		25	4.24
$C_6H_{10}O_4$	Adipic acid	1	18	4.41
		2	18	5.41
$C_6H_{11}NO_2$	2-Piperidinecarboxylic acid	1	25	2.28
		2	25	10.72
$C_6H_{11}NO_3$	Adipamic acid		25	4.63
$C_6H_{11}NO_4$	2-Aminoadipic acid	1	25	2.14
		2	25	4.21
		3	25	9.77
$C_6H_{11}N_3O_4$	*N*-(*N*-Glycylglycyl)glycine	1	25	3.225
		2	25	8.09
$C_6H_{11}N_3O_4$	Glycylasparagine	1	25	2.942
		2	18	8.44
$C_6H_{12}N_2$	Triethylenediamine	1		3.0
		2		8.7
$C_6H_{12}N_2O_4S_2$	*L*-Cystine	1		1
		2		2.1
		3		8.02
		4		8.71
$C_6H_{12}O_2$	Hexanoic acid		25	4.85
$C_6H_{12}O_2$	4-Methylpentanoic acid		18	4.84
$C_6H_{12}O_6$	β-*D*-Fructose		25	12.27
$C_6H_{12}O_6$	α-*D*-Glucose		25	12.46
$C_6H_{12}O_6$	*D*-Mannose		25	12.08
$C_6H_{13}N$	Cyclohexylamine		25	10.64
$C_6H_{13}N$	1-Methylpiperidine		25	10.38
$C_6H_{13}N$	1,2-Dimethylpyrrolidine		26	10.20
$C_6H_{13}NO$	*N*-Ethylmorpholine		25	7.67
$C_6H_{13}NO_2$	*L*-Leucine	1	25	2.33
		2	25	9.74
$C_6H_{13}NO_2$	*L*-Isoleucine	1	25	2.32
		2	25	9.76
$C_6H_{13}NO_2$	*L*-Norleucine	1	25	2.34
		2	25	9.83
$C_6H_{13}NO_2$	6-Aminohexanoic acid	1	25	4.37
		2	25	10.80
$C_6H_{13}NO_4$	*N,N*-Bis(2-hydroxyethyl)glycine	2	20	8.35
$C_6H_{13}N_3O_3$	Citrulline	1	25	2.43
		2	25	9.69
$C_6H_{14}N_2$	*cis*-1,2-Cyclohexanediamine	1	20	9.93
		2	20	6.13
$C_6H_{14}N_2$	*trans*-1,2-Cyclohexanediamine	1	20	9.94
		2	20	6.47
$C_6H_{14}N_2$	*cis*-2,5-Dimethylpiperazine	1	25	9.66
		2	25	5.20
$C_6H_{14}N_2O_2$	*L*-Lysine	1	25	2.16
		2	25	9.06
		3	25	10.54
$C_6H_{14}N_4O_2$	*L*-Arginine	1	25	1.82
		2	25	8.99
		3	25	12.5
$C_6H_{14}O_6$	*D*-Mannitol		18	13.5
$C_6H_{15}N$	Hexylamine		25	10.56
$C_6H_{15}N$	Diisopropylamine		25	11.05
$C_6H_{15}N$	Triethylamine		25	10.75
$C_6H_{15}NO_3$	Triethanolamine		25	7.76
$C_6H_{16}N_2$	1,6-Hexanediamine	1	0	11.86
		2	0	10.76
$C_6H_{16}N_2$	*N,N,N',N'*-Tetramethyl-1,2-ethanediamine	1	25	10.40
		2	25	8.26
$C_6H_{19}NSi_2$	Hexamethyldisilazane			7.55
$C_7HF_5O_2$	Pentafluorobenzoic acid		25	1.75
$C_7H_3Br_2NO$	3,5-Dibromo-4-hydroxybenzonitrile			4.06
$C_7H_3N_3O_8$	2,4,6-Trinitrobenzoic acid		25	0.65
$C_7H_4Cl_3NO_3$	Triclopyr			2.68
$C_7H_4N_2O_6$	2,4-Dinitrobenzoic acid		25	1.43
$C_7H_5BrO_2$	2-Bromobenzoic acid		25	2.85
$C_7H_5BrO_2$	3-Bromobenzoic acid		25	3.81
$C_7H_5BrO_2$	4-Bromobenzoic acid		25	3.96
$C_7H_5ClO_2$	2-Chlorobenzoic acid		25	2.90
$C_7H_5ClO_2$	3-Chlorobenzoic acid		25	3.84
$C_7H_5ClO_2$	4-Chlorobenzoic acid		25	4.00
$C_7H_5FO_2$	2-Fluorobenzoic acid		25	3.27
$C_7H_5FO_2$	3-Fluorobenzoic acid		25	3.86
$C_7H_5FO_2$	4-Fluorobenzoic acid		25	4.15
$C_7H_5F_3O$	2-(Trifluoromethyl)phenol		25	8.95
$C_7H_5F_3O$	3-(Trifluoromethyl)phenol		25	8.68
$C_7H_5IO_2$	2-Iodobenzoic acid		25	2.86
$C_7H_5IO_2$	3-Iodobenzoic acid		25	3.87
$C_7H_5IO_2$	4-Iodobenzoic acid		25	4.00
C_7H_5NO	2-Hydroxybenzonitrile		25	6.86
C_7H_5NO	3-Hydroxybenzonitrile		25	8.61
C_7H_5NO	4-Hydroxybenzonitrile		25	7.97
$C_7H_5NO_3S$	Saccharin		18	11.68
$C_7H_5NO_4$	2-Nitrobenzoic acid		25	2.17
$C_7H_5NO_4$	3-Nitrobenzoic acid		25	3.46
$C_7H_5NO_4$	4-Nitrobenzoic acid		25	3.43

Mol. form.	Name	Step	t/°C	pK_a
$C_7H_5NO_4$	2,3-Pyridinedicarboxylic acid	1	25	2.43
		2	25	4.78
$C_7H_5NO_4$	2,4-Pyridinedicarboxylic acid	1	25	2.15
$C_7H_5NO_4$	2,6-Pyridinedicarboxylic acid	1	25	2.16
		2	25	4.76
$C_7H_5NO_4$	3,5-Pyridinedicarboxylic acid	1	25	2.80
	Chlorothiazide	1		6.85
$C_7H_6ClN_3O_4S_2$		2		9.45
$C_7H_6F_3N$	3-(Trifluoromethyl)aniline		25	3.49
$C_7H_6F_3N$	4-(Trifluoromethyl)aniline		25	2.45
$C_7H_6N_2$	1*H*-Benzimidazole		25	5.53
$C_7H_6N_2$	2-Aminobenzonitrile		25	0.77
$C_7H_6N_2$	3-Aminobenzonitrile		25	2.75
$C_7H_6N_2$	4-Aminobenzonitrile		25	1.74
C_7H_6O	Benzaldehyde		25	14.90
$C_7H_6O_2$	Benzoic acid		25	4.204
$C_7H_6O_2$	Salicylaldehyde		25	8.37
$C_7H_6O_2$	3-Hydroxybenzaldehyde		25	8.98
$C_7H_6O_2$	4-Hydroxybenzaldehyde		25	7.61
$C_7H_6O_3$	2-Hydroxybenzoic acid	1	20	2.98
		2	20	13.6
$C_7H_6O_3$	3-Hydroxybenzoic acid	1	25	4.08
		2	19	9.92
$C_7H_6O_3$	4-Hydroxybenzoic acid	1	25	4.57
		2	25	9.46
$C_7H_6O_4$	2,4-Dihydroxybenzoic acid	1	25	3.11
		2	25	8.55
		3	25	14.0
$C_7H_6O_4$	2,5-Dihydroxybenzoic acid	1	25	2.97
$C_7H_6O_4$	3,4-Dihydroxybenzoic acid	1	25	4.48
		2	25	8.83
		3	25	12.6
$C_7H_6O_4$	3,5-Dihydroxybenzoic acid	1	25	4.04
$C_7H_6O_5$	2,4,6-Trihydroxybenzoic acid		25	1.68
$C_7H_6O_5$	3,4,5-Trihydroxybenzoic acid		25	4.41
C_7H_7NO	Benzamide		25	~13
$C_7H_7NO_2$	Aniline-2-carboxylic acid	1	25	2.17
		2	25	4.85
$C_7H_7NO_2$	Aniline-3-carboxylic acid	1	25	3.07
		2	25	4.79
$C_7H_7NO_2$	Aniline-4-carboxylic acid	1	25	2.50
		2	25	4.87
$C_7H_7NO_3$	4-Amino-2-hydroxy-benzoic acid			3.25
$C_7H_8ClN_3O_4S_2$	Hydrochlorothiazide	1		7.9
		2		9.2
$C_7H_8N_4O_2$	Theobromine		18	7.89
$C_7H_8N_4O_2$	Theophylline	1	25	8.77
C_7H_8O	*o*-Cresol		25	10.29
C_7H_8O	*m*-Cresol		25	10.09
C_7H_8O	*p*-Cresol		25	10.26
C_7H_8OS	4-(Methylthio)phenol		25	9.53
$C_7H_8O_2$	2-Methoxyphenol		25	9.98
$C_7H_8O_2$	3-Methoxyphenol		25	9.65
$C_7H_8O_2$	4-Methoxyphenol		25	10.21
C_7H_8S	Benzenemethanethiol		25	9.43
C_7H_9N	Benzylamine		25	9.34
C_7H_9N	2-Methylaniline		25	4.45
C_7H_9N	3-Methylaniline		25	4.71
C_7H_9N	4-Methylaniline		25	5.08
C_7H_9N	*N*-Methylaniline		25	4.85
C_7H_9N	2-Ethylpyridine		25	5.89
C_7H_9N	2,3-Dimethylpyridine		25	6.57
C_7H_9N	2,4-Dimethylpyridine		25	6.99
C_7H_9N	2,5-Dimethylpyridine		25	6.40
C_7H_9N	2,6-Dimethylpyridine		25	6.65
C_7H_9N	3,4-Dimethylpyridine		25	6.46
C_7H_9N	3,5-Dimethylpyridine		25	6.15
C_7H_9NO	2-Methoxyaniline		25	4.53
C_7H_9NO	3-Methoxyaniline		25	4.20
C_7H_9NO	4-Methoxyaniline		25	5.36
C_7H_9NS	2-(Methylthio)aniline		25	3.45
C_7H_9NS	4-(Methylthio)aniline		25	4.35
$C_7H_9N_5$	2-Dimethylaminopurine	1	20	4.00
		2	20	10.24
$C_7H_{11}N_3O_2$	*L*-1-Methylhistidine	1	25	1.69
		2	25	6.48
		3	25	8.85
$C_7H_{11}N_3O_2$	*L*-3-Methylhistidine	1	25	1.92
		2	25	6.56
		3	25	8.73
$C_7H_{12}O_2$	Cyclohexanecarboxylic acid		25	4.91
$C_7H_{12}O_4$	Heptanedioic acid	1	25	4.71
		2	25	5.58
$C_7H_{12}O_4$	Butylpropanedioic acid	1	5	2.96
$C_7H_{13}NO_4$	α-Ethylglutamic acid	1	25	3.846
		2	25	7.838
$C_7H_{14}O_2$	Heptanoic acid		25	4.89
$C_7H_{14}O_6$	α-Methylglucoside		25	13.71
$C_7H_{15}N$	1-Ethylpiperidine		23	10.45
$C_7H_{15}N$	1,2-Dimethylpiperidine,(±)		25	10.22
$C_7H_{15}NO_3$	Carnitine		25	3.80
$C_7H_{17}N$	Heptylamine		25	10.67
$C_7H_{17}N$	2-Heptanamine		19	10.7
$C_8H_5NO_2$	3-Cyanobenzoic acid		25	3.60
$C_8H_5NO_2$	4-Cyanobenzoic acid		25	3.55
$C_8H_6N_2$	Cinnoline		20	2.37
$C_8H_6N_2$	Quinazoline		29	3.43
$C_8H_6N_2$	Quinoxaline		20	0.56
$C_8H_6N_2$	Phthalazine		20	3.47
$C_8H_6N_4O_5$	Nitrofurantoin			7.2
$C_8H_6O_3$	3-Formylbenzoic acid		25	3.84
$C_8H_6O_3$	4-Formylbenzoic acid		25	3.77
$C_8H_6O_4$	Phthalic acid	1	25	2.943
		2	25	5.432
$C_8H_6O_4$	Isophthalic acid	1	25	3.70
		2	25	4.60
$C_8H_6O_4$	Terephthalic acid	1	25	3.54
		2	25	4.34
$C_8H_7ClO_2$	2-Chlorobenzeneacetic acid		25	4.07
$C_8H_7ClO_2$	3-Chlorobenzeneacetic acid		25	4.14
$C_8H_7ClO_2$	4-Chlorobenzeneacetic acid		25	4.19
$C_8H_7ClO_3$	2-Chlorophenoxyacetic acid		25	3.05
$C_8H_7ClO_3$	3-Chlorophenoxyacetic acid		25	3.10
$C_8H_7NO_4$	2-Nitrobenzeneacetic acid		25	4.00
$C_8H_7NO_4$	3-Nitrobenzeneacetic acid		25	3.97
$C_8H_7NO_4$	4-Nitrobenzeneacetic acid		25	3.85
$C_8H_8F_3N_3O_4S_2$	Hydroflumethiazide	1		8.9

Mol. form.	Name	Step	*t*/°C	pK_a
		2		9.7
$C_8H_8N_2$	2-Methyl-1*H*-benzimidazole	1	25	6.19
$C_8H_8O_2$	*o*-Toluic acid		25	3.91
$C_8H_8O_2$	*m*-Toluic acid		25	4.25
$C_8H_8O_2$	*p*-Toluic acid		25	4.37
$C_8H_8O_2$	Benzeneacetic acid		25	4.31
$C_8H_8O_2$	1-(2-Hydroxyphenyl)ethanone		25	10.06
$C_8H_8O_2$	1-(3-Hydroxyphenyl)ethanone		25	9.19
$C_8H_8O_2$	1-(4-Hydroxyphenyl)ethanone		25	8.05
$C_8H_8O_3$	2-Methoxybenzoic acid		25	4.08
$C_8H_8O_3$	3-Methoxybenzoic acid		25	4.10
$C_8H_8O_3$	4-Methoxybenzoic acid		25	4.50
$C_8H_8O_3$	Phenoxyacetic acid		25	3.17
$C_8H_8O_3$	Mandelic acid		25	3.37
$C_8H_8O_4$	2,5-Hydroxybenzeneacetic acid		25	4.40
C_8H_9NO	Acetanilide		25	0.5
$C_8H_9NO_2$	2-(Methylamino)benzoic acid		25	5.34
$C_8H_9NO_2$	3-(Methylamino)benzoic acid		25	5.10
$C_8H_9NO_2$	4-(Methylamino)benzoic acid		25	5.04
$C_8H_9NO_2$	*N*-Phenylglycine	1	25	1.83
		2		4.39
$C_8H_{10}BrN$	4-Bromo-*N,N*-dimethylaniline		25	4.23
$C_8H_{10}ClN$	3-Chloro-*N,N*-dimethylaniline		20	3.83
$C_8H_{10}ClN$	4-Chloro-*N,N*-dimethylaniline		20	4.39
$C_8H_{10}N_2O_2$	*N,N*-Dimethyl-3-nitroaniline		25	2.62
$C_8H_{11}N$	*N*-Ethylaniline		25	5.12
$C_8H_{11}N$	*N,N*-Dimethylaniline		25	5.07
$C_8H_{11}N$	2,6-Dimethylaniline		25	3.89
$C_8H_{11}N$	Benzeneethanamine		25	9.83
$C_8H_{11}N$	2,4,6-Trimethylpyridine		25	7.43
$C_8H_{11}NO$	2-Ethoxyaniline		28	4.43
$C_8H_{11}NO$	3-Ethoxyaniline		25	4.18
$C_8H_{11}NO$	4-Ethoxyaniline		28	5.20
$C_8H_{11}NO$	4-(2-Aminoethyl)phenol	1	25	9.74
		2	25	10.52
$C_8H_{11}NO$	2-(2-Methoxyethyl)pyridine			5.5
$C_8H_{11}NO_2$	Dopamine	1	25	8.9
		2	25	10.6
$C_8H_{11}NO_3$	Norepinephrine	1	25	8.64
		2	25	9.70
$C_8H_{11}N_3O_6$	6-Azauridine			6.70
$C_8H_{11}N_5$	Phenylbiguanide	1		10.76
		2		2.13
$C_8H_{12}N_2O_3$	Barbital		25	7.43
$C_8H_{12}O_2$	5,5-Dimethyl-1,3-cyclohexanedione		25	5.15
$C_8H_{13}NO_2$	Arecoline			6.84
$C_8H_{14}O_2S_2$	Thioctic acid			5.4
$C_8H_{14}O_4$	Octanedioic acid	1	25	4.52
$C_8H_{15}NO$	Tropine		15	3.80
$C_8H_{15}NO$	Pseudotropine		15	3.80
$C_8H_{16}N_2O_3$	*N*-Glycylleucine		25	3.18
$C_8H_{16}N_2O_3$	*N*-Leucylglycine	1	25	3.25
		2	25	8.2
$C_8H_{16}N_2O_4S_2$	Homocystine	1	25	1.59
		2	25	2.54
		3	25	8.52
		4	25	9.44
$C_8H_{16}O_2$	Octanoic acid		25	4.89
$C_8H_{16}O_2$	2-Propylpentanoic acid			4.6
$C_8H_{17}N$	2-Propylpiperidine,(*S*)			10.9
$C_8H_{17}N$	2,2,4-Trimethylpiperidine		30	11.04
$C_8H_{17}NO$	*trans*-6-Propyl-3-piperidinol,(3*S*)			10.3
$C_8H_{19}N$	Octylamine		25	10.65
$C_8H_{19}N$	*N*-Methyl-2-heptanamine		17	10.99
$C_8H_{19}N$	Dibutylamine		21	11.25
$C_8H_{20}N_2$	1,8-Octanediamine	1	20	11.00
		2	20	10.1
C_9H_6BrN	3-Bromoquinoline		25	2.69
$C_9H_7ClO_2$	*trans-o*-Chlorocinnamic acid		25	4.23
$C_9H_7ClO_2$	*trans-m*-Chlorocinnamic acid		25	4.29
$C_9H_7ClO_2$	*trans-p*-Chlorocinnamic acid		25	4.41
C_9H_7N	Quinoline		20	4.90
C_9H_7N	Isoquinoline		20	5.40
C_9H_7NO	2-Quinolinol	1	20	-0.31
		2	20	11.76
C_9H_7NO	3-Quinolinol	1	20	4.28
		2	20	8.08
C_9H_7NO	4-Quinolinol	1	20	2.23
		2	20	11.28
C_9H_7NO	6-Quinolinol	1	20	5.15
		2	20	8.90
C_9H_7NO	8-Quinolinol	1	25	4.91
		2	25	9.81
C_9H_7NO	7-Isoquinolinol	1	20	5.68
		2	20	8.90
$C_9H_7NO_3$	2-Cyanophenoxyacetic acid		25	2.98
$C_9H_7NO_3$	3-Cyanophenoxyacetic acid		25	3.03
$C_9H_7NO_3$	4-Cyanophenoxyacetic acid		25	2.93
$C_9H_7N_7O_2S$	Azathioprine			8.2
$C_9H_8N_2$	2-Quinolinamine		20	7.34
$C_9H_8N_2$	3-Quinolinamine		20	4.91
$C_9H_8N_2$	4-Quinolinamine		20	9.17
$C_9H_8N_2$	1-Isoquinolinamine		20	7.62
$C_9H_8N_2$	3-Isoquinolinamine		20	5.05
$C_9H_8O_2$	*cis*-Cinnamic acid		25	3.88
$C_9H_8O_2$	*trans*-Cinnamic acid		25	4.44
$C_9H_8O_2$	α-Methylenebenezene-acetic acid			4.35
$C_9H_8O_4$	2-(Acetyloxy)benzoic acid		25	3.48
$C_9H_9Br_2NO_3$	3,5-Dibromo-*L*-tyrosine	1		2.17
		2		6.45
		3		7.60
$C_9H_9ClO_2$	3-(2-Chlorophenyl)-propanoic acid		25	4.58
$C_9H_9ClO_2$	3-(3-Chlorophenyl)-propanoic acid		25	4.59
$C_9H_9ClO_2$	3-(4-Chlorophenyl)-propanoic acid		25	4.61
$C_9H_9I_2NO_3$	*L*-3,5-Diiodotyrosine	1	25	2.12

Mol. form.	Name	Step	t/°C	pK_a
		2	25	5.32
		3	25	9.48
$C_9H_9NO_3$	*N*-Benzoylglycine		25	3.62
$C_9H_9NO_4$	3-(2-Nitrophenyl)-propanoic acid		25	4.50
$C_9H_9NO_4$	3-(4-Nitrophenyl)-propanoic acid		25	4.47
$C_9H_9N_3O_2$	Carbendazim			4.48
$C_9H_9N_3O_2S_2$	Sulfathiazole			7.2
$C_9H_{10}INO_3$	*L*-3-Iodotyrosine	1	25	2.2
		2	25	8.7
		3	25	9.1
$C_9H_{10}N_2$	2-Ethylbenzimidazole		25	6.18
$C_9H_{10}O_2$	3,5-Dimethylbenzoic acid		25	4.32
$C_9H_{10}O_2$	Benzenepropanoic acid		25	4.66
$C_9H_{10}O_2$	α-Methylbenzeneacetic acid		25	4.64
$C_9H_{10}O_3$	α-Hydroxy-α-methyl-benezeneacetic acid		25	3.47
$C_9H_{11}Cl_2N_3O_4S_2$	Methylclothiazide			9.4
$C_9H_{11}N$	*N*-Allylaniline		25	4.17
$C_9H_{11}N$	1-Indanamine		22	9.21
$C_9H_{11}NO_2$	4-(Dimethylamino)-benzoic acid	1		6.03
		2		11.49
$C_9H_{11}NO_2$	Ethyl 4-aminobenzoate			2.5
$C_9H_{11}NO_2$	*L*-Phenylalanine	1	25	2.20
		2	25	9.31
$C_9H_{11}NO_3$	*L*-Tyrosine	1	25	2.20
		2	25	9.11
		3	25	10.1
$C_9H_{11}NO_4$	Levodopa	1	25	2.32
		2	25	8.72
		3	25	9.96
		4	25	11.79
$C_9H_{12}N_2O_2$	Tyrosineamide		25	7.33
$C_9H_{13}N$	*N*-Isopropylaniline		25	5.77
$C_9H_{13}NO_3$	Epinephrine	1	25	8.66
		2	25	9.95
$C_9H_{13}N_2O_9P$	5'-Uridylic acid	1		6.4
		2		9.5
$C_9H_{13}N_3O_5$	Cytidine	1		4.22
		2		12.5
$C_9H_{14}ClNO$	Phenylpropanolamine hydrochloride			9.44
$C_9H_{14}N_2O_3$	Metharbital			8.45
$C_9H_{14}N_3O_8P$	3'-Cytidylic acid	1		0.8
		2		4.28
		3		6.0
$C_9H_{14}N_4O_3$	Carnosine	1	20	2.73
		2	20	6.87
		3	20	9.73
$C_9H_{15}NO_3S$	Captopril	1		3.7
		2		9.8
$C_9H_{15}N_5O$	Minoxidil			4.61
$C_9H_{16}O_4$	Nonanedioic acid	1	25	4.53
		2	25	5.33
$C_9H_{18}O_2$	Nonanoic acid		25	4.96
$C_9H_{19}N$	*N*-Butylpiperidine		23	10.47
$C_9H_{19}N$	2,2,6,6-Tetramethyl-piperidine		25	11.07
$C_9H_{21}N$	Nonylamine		25	10.64
$C_{10}H_7NO_2$	8-Quinolinecarboxylic acid		25	1.82
$C_{10}H_8O$	1-Naphthol		25	9.39
$C_{10}H_8O$	2-Naphthol		25	9.63
$C_{10}H_9N$	1-Naphthylamine		25	3.92
$C_{10}H_9N$	2-Naphthylamine		25	4.16
$C_{10}H_9N$	2-Methylquinoline		20	5.83
$C_{10}H_9N$	4-Methylquinoline		20	5.67
$C_{10}H_9N$	5-Methylquinoline		20	5.20
$C_{10}H_9NO$	5-Amino-1-naphthol		25	3.97
$C_{10}H_9NO$	6-Methoxyquinoline		20	5.03
$C_{10}H_9NO_2$	1H-Indole-3-acetic acid			4.75
$C_{10}H_{10}O_2$	*o*-Methylcinnamic acid		25	4.50
$C_{10}H_{10}O_2$	*m*-Methylcinnamic acid		25	4.44
$C_{10}H_{10}O_2$	*p*-Methylcinnamic acid		25	4.56
$C_{10}H_{12}N_2$	Tryptamine		25	10.2
$C_{10}H_{12}N_2O$	5-Hydroxytryptamine	1	25	9.8
		2	25	11.1
$C_{10}H_{12}N_2O_5$	Dinoseb			4.62
$C_{10}H_{12}N_4O_3$	Dideoxyinosine			9.12
$C_{10}H_{12}O$	5,6,7,8-Tetrahydro-2-naphthalenol		25	10.48
$C_{10}H_{12}O_2$	Benzenebutanoic acid		25	4.76
$C_{10}H_{12}O_5$	Propyl 3,4,5-trihydroxy-benzoate			8.11
$C_{10}H_{13}N_5O_4$	Adenosine	1	25	3.6
		2	25	12.4
$C_{10}H_{14}N_2$	*L*-Nicotine	1		8.02
		2		3.12
$C_{10}H_{14}N_5O_7P$	5'-Adenylic acid	1		3.8
		2		6.2
$C_{10}H_{14}O$	2-*tert*-Butylphenol		25	10.62
$C_{10}H_{14}O$	3-*tert*-Butylphenol		25	10.12
$C_{10}H_{14}O$	4-*tert*-Butylphenol		25	10.23
$C_{10}H_{15}N$	*N*-*tert*-Butylaniline		25	7.00
$C_{10}H_{15}N$	*N*,*N*-Diethylaniline		25	6.57
$C_{10}H_{15}NO$	*d*-Ephedrine		10	10.139
$C_{10}H_{15}NO$	*l*-Ephedrine		10	9.958
$C_{10}H_{17}N_3O_6S$	*l*-Glutathione	1	25	2.12
		2	25	3.59
		3	25	8.75
		4	25	9.65
$C_{10}H_{18}N_4O_5$	*L*-Argininosuccinic acid	1	25	1.62
		2	25	2.70
		3	25	4.26
		4	25	9.58
$C_{10}H_{18}O_4$	Sebacic acid	1		4.59
		2		5.59
$C_{10}H_{19}N$	Bornylamine		25	10.17
$C_{10}H_{19}N$	Neobornylamine		25	10.01
$C_{10}H_{21}N$	Butylcyclohexylamine		25	11.23
$C_{10}H_{21}N$	1,2,2,6,6-Pentamethyl-piperidine		30	11.25
$C_{10}H_{23}N$	Decylamine		25	10.64
$C_{11}H_8N_2$	1*H*-Perimidine		20	6.35
$C_{11}H_8O_2$	1-Naphthalenecarboxylic acid		25	3.69
$C_{11}H_8O_2$	2-Naphthalenecarboxylic acid		25	4.16
$C_{11}H_{11}N$	Methyl-1-naphthylamine		27	3.67
$C_{11}H_{12}I_3NO_2$	Iopanoic acid			4.8
$C_{11}H_{12}N_2O_2$	*L*-Tryptophan	1	25	2.46
		2	25	9.41

Mol. form.	Name	Step	*t*/°C	pK_a
$C_{11}H_{12}N_4O_3S$	Sulfamethoxypyridazine			6.7
$C_{11}H_{13}F_3N_2O_3S$	Mefluidide			4.6
$C_{11}H_{13}NO_3$	Hydrastinine			11.38
$C_{11}H_{13}N_3O_3S$	Sulfisoxazole			5
$C_{11}H_{14}N_2O$	Cytisine	1		6.11
		2		13.08
$C_{11}H_{14}O_2$	2-*tert*-Butylbenzoic acid		25	3.54
$C_{11}H_{14}O_2$	3-*tert*-Butylbenzoic acid		25	4.20
$C_{11}H_{14}O_2$	4-*tert*-Butylbenzoic acid		25	4.38
$C_{11}H_{16}N_2O_2$	Pilocarpine	1	25	1.6
		2	25	6.9
$C_{11}H_{16}N_4O_4$	Pentostatin			5.2
$C_{11}H_{17}N$	*N,N*-Diethyl-2-methyl-aniline		25	7.24
$C_{11}H_{17}NO_3$	Isoproterenol			8.64
$C_{11}H_{17}N_3O_8$	Tetrodotoxin			8.76
$C_{11}H_{18}ClNO_3$	Methoxamine hydrochloride		25	9.2
$C_{11}H_{18}N_2O_3$	Amobarbital		25	8.0
$C_{11}H_{25}N$	Undecylamine		25	10.63
$C_{11}H_{26}NO_2PS$	Methylphosphonothioic acid *S*[2-[bis(1-isopropyl)amino]-ethyl], *O*-ethylester			7.9
$C_{12}H_6Cl_4O_2S$	Bithionol	1		4.82
		2		10.50
$C_{12}H_8N_2$	1,10-Phenanthroline		25	4.84
$C_{12}H_8N_2$	Phenazine		20	1.20
$C_{12}H_{10}O$	2-Hydroxybiphenyl		25	10.01
$C_{12}H_{10}O$	3-Hydroxybiphenyl		25	9.64
$C_{12}H_{10}O$	4-Hydroxybiphenyl		25	9.55
$C_{12}H_{11}N$	Diphenylamine		25	0.79
$C_{12}H_{11}N$	2-Aminobiphenyl		25	3.83
$C_{12}H_{11}N$	3-Aminobiphenyl		18	4.25
$C_{12}H_{11}N$	4-Aminobiphenyl		18	4.35
$C_{12}H_{11}N$	2-Benzylpyridine		25	5.13
$C_{12}H_{11}N_3$	4-Aminoazobenzene		25	2.82
$C_{12}H_{12}N_2$	*p*-Benzidine	1	20	4.65
		2	20	3.43
$C_{12}H_{12}N_2O_3$	Phenobarbital	1		7.3
		2		11.8
$C_{12}H_{13}I_3N_2O_3$	Iocetamic acid			4
$C_{12}H_{13}N$	*N,N*-Dimethyl-1-naphthylamine		25	4.83
$C_{12}H_{13}N$	*N,N*-Dimethyl-2-naphthylamine		25	4.566
$C_{12}H_{14}N_4O_2S$	Sulfamethazine	1		7.4
		2		2.65
$C_{12}H_{14}N_4O_3S$	Sulfacytine			6.9
$C_{12}H_{17}N_3O_4$	Agaritine	1		3.4
		2		8.86
$C_{12}H_{20}N_2O_2$	Aspergillic acid			5.5
$C_{12}H_{21}N_5O_2S_2$	Nizatidine	1		2.1
		2		6.8
$C_{12}H_{22}O_{11}$	Sucrose		25	12.7
$C_{12}H_{22}O_{11}$	α-Maltose		21	12.05
$C_{12}H_{23}N$	Dicyclohexylamine			10.4
$C_{12}H_{27}N$	Dodecylamine		25	10.63
$C_{13}H_9N$	Acridine		20	5.58
$C_{13}H_9N$	Phenanthridine		20	5.58
$C_{13}H_{10}N_2$	9-Acridinamine		20	9.99
$C_{13}H_{10}N_2$	2-Phenylbenzimidazole	1	25	5.23
		2	25	11.91
$C_{13}H_{10}O_2$	2-Phenylbenzoic acid		25	3.46
$C_{13}H_{10}O_3$	2-Phenoxybenzoic acid		25	3.53
$C_{13}H_{10}O_3$	3-Phenoxybenzoic acid		25	3.95
$C_{13}H_{10}O_3$	4-Phenoxybenzoic acid		25	4.57
$C_{13}H_{11}N_3$	3,6-Acridinediamine		20	9.65
$C_{13}H_{12}Cl_2O_4$	Ethacrynic acid			3.50
$C_{13}H_{12}N_2O$	Harmine			7.70
$C_{13}H_{12}N_2O_3S$	Sulfabenzamide		25	4.57
$C_{13}H_{13}N$	4-Benzylaniline		25	2.17
$C_{13}H_{14}N_2O_{13}$	Harmaline			4.2
$C_{13}H_{15}N_3O_3$	Imazapyr	1		1.9
		2		3.6
$C_{13}H_{16}ClNO$	Ketamine			7.5
$C_{13}H_{19}NO_4S$	4-[(Dipropylamino)-sulfonyl]benzoic acid			5.8
$C_{13}H_{21}N$	2,6-Di-*tert*-butylpyridine			3.58
$C_{13}H_{29}N$	(Tridecyl)amine		25	10.63
$C_{14}H_{12}F_3NO_4S_2$	Perfluidone			2.5
$C_{14}H_{12}O_2$	α-Phenylbenzeneacetic acid		25	3.94
$C_{14}H_{12}O_3$	α-Hydroxy-**α**-phenyl-benezeneacetic acid		25	3.04
$C_{14}H_{18}N_4O_3$	Trimethoprim			6.6
$C_{14}H_{19}NO_2$	Methylphenidate			8.9
$C_{14}H_{21}N_3O_3S$	Tolazamide		25	3.6
$C_{14}H_{22}N_2O_3$	Atenolol			9.6
$C_{14}H_{31}N$	Tetradecylamine		25	10.62
$C_{15}H_{10}ClN_3O_3$	Clonazepam	1		1.5
		2		10.5
$C_{15}H_{11}I_4NO_4$	*L*-Thyroxine	1	25	2.2
		2	25	6.45
		3	25	10.1
$C_{15}H_{14}O_3$	Fenoprofen			7.3
$C_{15}H_{15}NO_2$	Mefenamic acid			4.2
$C_{15}H_{15}N_3O_2$	Methyl Red	1		2.5
		2		9.5
$C_{15}H_{17}ClN_4$	NeutralRed			6.7
$C_{15}H_{19}NO_2$	Tropacocaine		15	4.32
$C_{15}H_{19}N_3O_3$	Imazethapyr	1		2.1
		2		3.9
$C_{15}H_{21}N_3O_2$	Physostigmine	1		6.12
		2		12.24
$C_{15}H_{26}N_2$	Sparteine	1	20	2.24
		2	20	9.46
$C_{15}H_{33}N$	Pentadecylamine		25	10.61
$C_{16}H_{13}ClN_2O$	Valium			3.4
$C_{16}H_{14}ClN_3O$	Chlorodiazepoxide			4.8
$C_{16}H_{16}N_2O_2$	Lysergic acid	1		3.44
		2		7.68
$C_{16}H_{17}N_3O_4S$	Cephalexin	1		5.2
		2		7.3
$C_{16}H_{19}N_3O_4S$	Cephradine	1		2.63
		2		7.27
$C_{16}H_{22}N_2$	Lycodine	1		3.97
		2		8.08
$C_{16}H_{35}N$	Hexadecylamine		25	10.61
$C_{17}H_{17}NO_2$	Apomorphine	1		7.0
		2		8.92
$C_{17}H_{19}NO_3$	Piperine		18	12.22
$C_{17}H_{19}NO_3$	Morphine	1	25	8.21
		2	20	9.85
$C_{17}H_{20}N_4O_6$	Riboflavin	1		1.7

Mol. form.	Name	Step	*t*/°C	pK_a
		2	25	9.69
$C_{17}H_{20}O_6$	Mycophenolic acid			4.5
$C_{17}H_{23}NO_3$	Hyoscyamine		21	9.7
$C_{17}H_{27}NO_4$	Nadolol			9.67
$C_{18}H_{19}ClN_4$	Clozapine	1		3.70
		2		7.60
$C_{18}H_{21}NO_3$	Codeine			8.21
$C_{18}H_{21}N_3O$	Dibenzepin			8.25
$C_{18}H_{32}O_2$	Linoleic acid			7.6
$C_{18}H_{33}ClN_2O_5S$	Clindamycin			7.6
$C_{18}H_{39}N$	Octadecylamine		25	10.60
$C_{19}H_{10}Br_4O_5S$	Bromophenol Blue			4.0
$C_{19}H_{14}O_5S$	Phenol Red			7.9
$C_{19}H_{16}ClNO_4$	Indomethacin			4.5
$C_{19}H_{17}N_3O_4S_2$	Cephaloridine			3.2
$C_{19}H_{20}N_2O_2$	Phenylbutazone			4.5
$C_{19}H_{21}N$	Protriptyline			8.2
$C_{19}H_{21}NO_3$	Thebaine		15	6.05
$C_{19}H_{22}N_2O$	Cinchonine	1		5.85
		2		9.92
$C_{19}H_{22}N_2O$	Cinchonidine	1		5.80
		2		10.03
$C_{19}H_{22}N_2O_2$	Cupreine			6.57
$C_{19}H_{22}O_6$	Gibberellic acid			4.0
$C_{19}H_{23}N_3O_2$	Ergometrinine			7.3
$C_{19}H_{23}N_3O_2$	Ergonovine			6.8
$C_{20}H_{14}O_4$	Phenolphthalein		25	9.7
$C_{20}H_{21}NO_4$	Papaverine			6.4
$C_{20}H_{23}N$	Amitriptyline			9.4
$C_{20}H_{23}N_7O_7$	Folinic acid	1		3.1
		2		4.8
		3		10.4
$C_{20}H_{24}N_2O_2$	Quinine	1	25	8.52
		2	25	4.13
$C_{20}H_{24}N_2O_2$	Quinidine	1	20	5.4
		2	20	10.0
$C_{20}H_{26}N_2O_2$	Hydroquinine			5.33
$C_{21}H_{14}Br_4O_5S$	Bromocresol Green			4.7
$C_{21}H_{16}Br_2O_5S$	Bromocresol Purple			6.3
$C_{21}H_{18}O_5S$	CresolRed			8.3
$C_{21}H_{21}NO_6$	Hydrastine			7.8
$C_{21}H_{22}N_2O_2$	Strychnine		25	8.26
$C_{21}H_{23}ClFNO_2$	Haloperidol			8.3
$C_{21}H_{31}NO_4$	Furethidine			7.48
$C_{21}H_{35}N_3O_7$	Lisinopril	1		2.5
		2		4.0
		3		6.7
		4		10.1
$C_{22}H_{18}O_4$	*o*-Cresolphthalein			9.4
$C_{22}H_{22}FN_3O_2$	Droperidol			7.64
$C_{22}H_{23}NO_7$	Noscapine			7.8
$C_{22}H_{25}NO_6$	Colchicine		20	12.36
$C_{22}H_{25}N_3O$	Benzpiperylon	1		6.73
		2		9.13
$C_{22}H_{33}NO_2$	Atisine			12.2
$C_{23}H_{26}N_2O_4$	Brucine	1		6.04
		2		11.07
$C_{24}H_{40}O_4$	Deoxycholic acid			6.58
$C_{24}H_{40}O_5$	Cholic acid			6.4
$C_{25}H_{29}I_2NO_3$	Amiodarone		25	6.56
$C_{25}H_{41}NO_9$	Aconine			9.52
$C_{26}H_{43}NO_6$	Glycocholic acid			4.4
$C_{26}H_{45}NO_7S$	Taurocholic acid			1.4
$C_{27}H_{28}Br_2O_5S$	Bromothymol Blue			7.0
$C_{27}H_{38}N_2O_4$	Verapamil			8.6
$C_{29}H_{32}O_{13}$	Etoposide			9.8
$C_{29}H_{40}N_2O_4$	Emetine	1		5.77
		2		6.64
$C_{30}H_{23}BrO_4$	Bromadiolone		21	4.04
$C_{30}H_{48}O_3$	Oleanolic acid			2.52
$C_{31}H_{36}N_2O_{11}$	Novobiocin	1		4.3
		2		9.1
$C_{32}H_{32}O_{13}S$	Teniposide			10.13
$C_{33}H_{40}N_2O_9$	Reserpine			6.6
$C_{34}H_{47}NO_{11}$	Aconitine			5.88
$C_{36}H_{51}NO_{11}$	Veratridine			9.54
$C_{37}H_{67}NO_{13}$	Erythromycin			8.8
$C_{43}H_{58}N_4O_{12}$	Rifampin	1		1.7
		2		7.9
$C_{45}H_{73}NO_{15}$	Solanine		15	6.66
$C_{46}H_{56}N_4O_{10}$	Vincristine			5.4
$C_{46}H_{58}N_4O_9$	Vinblastine	1		5.4
		2		7.4

CONCENTRATIVE PROPERTIES OF AQUEOUS SOLUTIONS: DENSITY, REFRACTIVE INDEX, FREEZING POINT DEPRESSION, AND VISCOSITY

This table gives properties of aqueous solutions of 66 substances as a function of concentration. All data refer to a temperature of 20°C. The properties are:

Mass %: Mass of solute divided by total mass of solution, expressed as percent.

m Molality (moles of solute per kg of water).

c Molarity (moles of solute per liter of solution).

ρ Density of solution in g/cm^3.

n Index of refraction, relative to air, at a wavelength of 589 nm (sodium D line); the index of pure water at 20°C is 1.3330.

Δ Freezing point depression in °C relative to pure water.

η Absolute (dynamic) viscosity in mPa s (equal to centipoise, cP); the viscosity of pure water at 20°C is 1.002 mPa s.

Density data for aqueous solutions over a wider range of temperatures and pressures (and for other compounds) may be found in Reference 2. Solutes are listed in the following order:

Acetic acid
Acetone
Ammonia
Ammonium chloride
Ammonium sulfate
Barium chloride
Calcium chloride
Cesium chloride
Citric acid
Copper sulfate
Disodium ethylenediamine tetraacetate (EDTA sodium)
Ethanol
Ethylene glycol
Ferric chloride
Formic acid
D-Fructose
D-Glucose
Glycerol
Hydrochloric acid
Lactic acid
Lactose
Lithium chloride
Magnesium chloride
Magnesium sulfate
Maltose
Manganese(II) sulfate
D-Mannitol
Methanol
Nitric acid
Oxalic acid
Phosphoric acid
Potassium bicarbonate
Potassium bromide
Potassium carbonate
Potassium chloride
Potassium hydroxide
Potassium iodide
Potassium nitrate
Potassium permanganate
Potassium hydrogen phosphate
Potassium dihydrogen phosphate
Potassium sulfate
1-Propanol
2-Propanol
Silver nitrate
Sodium acetate
Sodium bicarbonate
Sodium bromide
Sodium carbonate
Sodium chloride
Sodium citrate
Sodium hydroxide
Sodium nitrate
Sodium phosphate
Sodium hydrogen phosphate
Sodium dihydrogen phosphate
Sodium sulfate
Sodium thiosulfate
Strontium chloride
Sucrose
Sulfuric acid
Trichloroacetic acid
Tris(hydroxymethyl)methylamine
Urea
Zinc sulfate

References

1. Wolf, A. V., *Aqueous Solutions and Body Fluids*, Hoeber, 1966.
2. Söhnel, O., and Novotny, P., *Densities of Aqueous Solutions of Inorganic Substances*, Elsevier, Amsterdam, 1985.

Solute	Mass %	*m*/mol kg^{-1}	*c*/mol L^{-1}	ρ/g cm^{-3}	*n*	Δ/°C	η/mPa s
Acetic acid	0.5	0.084	0.083	0.9989	1.3334	0.16	1.012
CH_3COOH	1.0	0.168	0.166	0.9996	1.3337	0.32	1.022
	2.0	0.340	0.333	1.0011	1.3345	0.63	1.042
	3.0	0.515	0.501	1.0025	1.3352	0.94	1.063
	4.0	0.694	0.669	1.0038	1.3359	1.26	1.084
	5.0	0.876	0.837	1.0052	1.3366	1.58	1.105
	6.0	1.063	1.006	1.0066	1.3373	1.90	1.125
	7.0	1.253	1.175	1.0080	1.3381	2.23	1.143
	8.0	1.448	1.345	1.0093	1.3388	2.56	1.162
	9.0	1.647	1.515	1.0107	1.3395	2.89	1.186
	10.0	1.850	1.685	1.0121	1.3402	3.23	1.210
	12.0	2.271	2.028	1.0147	1.3416	3.91	1.253
	14.0	2.711	2.372	1.0174	1.3430	4.61	1.298
	16.0	3.172	2.718	1.0200	1.3444	5.33	1.341
	18.0	3.655	3.065	1.0225	1.3458	6.06	1.380
	20.0	4.163	3.414	1.0250	1.3472	6.81	1.431
	22.0	4.697	3.764	1.0275	1.3485	7.57	1.478
	24.0	5.259	4.116	1.0299	1.3498	8.36	1.525

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	26.0	5.851	4.470	1.0323	1.3512	9.17	1.572
	28.0	6.476	4.824	1.0346	1.3525	10.00	1.613
	30.0	7.137	5.180	1.0369	1.3537	10.84	1.669
	32.0	7.837	5.537	1.0391	1.3550	11.70	1.715
	34.0	8.579	5.896	1.0413	1.3562	12.55	1.762
	36.0	9.367	6.255	1.0434	1.3574	13.38	1.812
	38.0	10.207	6.615	1.0454	1.3586		1.852
	40.0	11.102	6.977	1.0474	1.3598		1.912
	50.0	16.653	8.794	1.0562	1.3653		2.158
	60.0	24.979	10.620	1.0629	1.3700		2.409
	70.0	38.857	12.441	1.0673	1.3738		2.629
	80.0	66.611	14.228	1.0680	1.3767		2.720
	90.0	149.875	15.953	1.0644	1.3771		2.386
	92.0	191.507	16.284	1.0629	1.3766		2.240
	94.0	260.894	16.602	1.0606	1.3759		2.036
	96.0	399.667	16.911	1.0578	1.3748		1.813
	98.0	815.987	17.198	1.0538	1.3734		1.535
	100.0		17.447	1.0477	1.3716		1.223
Acetone	0.5	0.087	0.086	0.9975	1.3334	0.16	1.013
$(CH_3)_2CO$	1.0	0.174	0.172	0.9968	1.3337	0.32	1.024
	2.0	0.351	0.343	0.9954	1.3344	0.65	1.047
	3.0	0.533	0.513	0.9940	1.3352	0.97	1.072
	4.0	0.717	0.684	0.9926	1.3359	1.30	1.099
	5.0	0.906	0.853	0.9912	1.3366	1.63	1.125
	6.0	1.099	1.023	0.9899	1.3373	1.96	1.150
	7.0	1.296	1.191	0.9886	1.3381	2.29	1.174
	8.0	1.497	1.360	0.9874	1.3388	2.62	1.198
	9.0	1.703	1.528	0.9861	1.3395	2.95	1.221
	10.0	1.913	1.696	0.9849	1.3402	3.29	1.244
Ammonia	0.5	0.295	0.292	0.9960	1.3332	0.55	1.009
NH_3	1.0	0.593	0.584	0.9938	1.3335	1.14	1.015
	2.0	1.198	1.162	0.9895	1.3339	2.32	1.029
	3.0	1.816	1.736	0.9853	1.3344	3.53	1.043
	4.0	2.447	2.304	0.9811	1.3349	4.78	1.057
	5.0	3.090	2.868	0.9770	1.3354	6.08	1.071
	6.0	3.748	3.428	0.9730	1.3359	7.43	1.085
	7.0	4.420	3.983	0.9690	1.3365	8.95	1.099
	8.0	5.106	4.533	0.9651	1.3370	10.34	1.113
	9.0	5.807	5.080	0.9613	1.3376	11.90	1.127
	10.0	6.524	5.622	0.9575	1.3381	13.55	1.141
	12.0	8.007	6.695	0.9502	1.3393	17.13	1.169
	14.0	9.558	7.753	0.9431	1.3404	21.13	1.195
	16.0	11.184	8.794	0.9361	1.3416	25.63	1.218
	18.0	12.889	9.823	0.9294	1.3428	30.70	1.237
	20.0	14.679	10.837	0.9228	1.3440	36.42	1.254
	22.0	16.561	11.838	0.9164	1.3453	43.36	1.268
	24.0	18.542	12.826	0.9102	1.3465	51.38	1.280
	26.0	20.630	13.801	0.9040	1.3477	60.77	1.288
	28.0	22.834	14.764	0.8980	1.3490	71.66	
	30.0	25.164	15.713	0.8920	1.3502	84.06	
Ammonium	0.5	0.094	0.093	0.9998	1.3340	0.32	0.999
chloride	1.0	0.189	0.187	1.0014	1.3349	0.64	0.996
NH_4Cl	2.0	0.382	0.376	1.0045	1.3369	1.27	0.992
	3.0	0.578	0.565	1.0076	1.3388	1.91	0.988
	4.0	0.779	0.756	1.0107	1.3407	2.57	0.985
	5.0	0.984	0.948	1.0138	1.3426	3.25	0.982
	6.0	1.193	1.141	1.0168	1.3445	3.94	0.979
	7.0	1.407	1.335	1.0198	1.3464	4.66	0.976

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	8.0	1.626	1.529	1.0227	1.3483	5.40	0.974
	9.0	1.849	1.726	1.0257	1.3502	6.16	0.972
	10.0	2.077	1.923	1.0286	1.3521	6.95	0.970
	12.0	2.549	2.320	1.0344	1.3559	8.60	0.969
	14.0	3.043	2.722	1.0401	1.3596		0.969
	16.0	3.561	3.128	1.0457	1.3634		0.971
	18.0	4.104	3.537	1.0512	1.3671		0.973
	20.0	4.674	3.951	1.0567	1.3708		0.978
	22.0	5.273	4.368	1.0621	1.3745		0.986
	24.0	5.903	4.789	1.0674	1.3782		0.996
Ammonium	0.5	0.038	0.038	1.0012	1.3338	0.17	1.008
sulfate	1.0	0.076	0.076	1.0042	1.3346	0.33	1.014
$(NH_4)_2SO_4$	2.0	0.154	0.153	1.0101	1.3363	0.63	1.027
	3.0	0.234	0.231	1.0160	1.3379	0.92	1.041
	4.0	0.315	0.309	1.0220	1.3395	1.21	1.057
	5.0	0.398	0.389	1.0279	1.3411	1.49	1.073
	6.0	0.483	0.469	1.0338	1.3428	1.77	1.090
	7.0	0.570	0.551	1.0397	1.3444	2.05	1.108
	8.0	0.658	0.633	1.0456	1.3460	2.33	1.127
	9.0	0.748	0.716	1.0515	1.3476	2.61	1.147
	10.0	0.841	0.800	1.0574	1.3492	2.89	1.168
	12.0	1.032	0.971	1.0691	1.3523	3.47	1.210
	14.0	1.232	1.145	1.0808	1.3555	4.07	1.256
	16.0	1.441	1.323	1.0924	1.3586	4.69	1.305
	18.0	1.661	1.504	1.1039	1.3616		1.359
	20.0	1.892	1.688	1.1154	1.3647		1.421
	22.0	2.134	1.876	1.1269	1.3677		1.490
	24.0	2.390	2.067	1.1383	1.3707		1.566
	26.0	2.659	2.262	1.1496	1.3737		1.650
	28.0	2.943	2.460	1.1609	1.3766		1.743
	30.0	3.243	2.661	1.1721	1.3795		1.847
	32.0	3.561	2.866	1.1833	1.3824		1.961
	34.0	3.898	3.073	1.1945	1.3853		2.086
	36.0	4.257	3.284	1.2056	1.3881		2.222
	38.0	4.638	3.499	1.2166	1.3909		2.371
	40.0	5.045	3.716	1.2277	1.3938		2.530
Barium	0.5	0.024	0.024	1.0026	1.3337	0.12	1.009
chloride	1.0	0.049	0.048	1.0070	1.3345	0.23	1.016
$BaCl_2$	2.0	0.098	0.098	1.0159	1.3360	0.46	1.026
	3.0	0.149	0.148	1.0249	1.3375	0.69	1.037
	4.0	0.200	0.199	1.0341	1.3391	0.93	1.049
	5.0	0.253	0.251	1.0434	1.3406	1.18	1.062
	6.0	0.307	0.303	1.0528	1.3422	1.44	1.075
	7.0	0.361	0.357	1.0624	1.3438	1.70	1.087
	8.0	0.418	0.412	1.0721	1.3454	1.98	1.101
	9.0	0.475	0.468	1.0820	1.3470	2.27	1.114
	10.0	0.534	0.524	1.0921	1.3487	2.58	1.129
	12.0	0.655	0.641	1.1128	1.3520	3.22	1.161
	14.0	0.782	0.763	1.1342	1.3555	3.92	1.195
	16.0	0.915	0.889	1.1564	1.3591	4.69	1.234
	18.0	1.054	1.019	1.1793	1.3627		1.277
	20.0	1.201	1.156	1.2031	1.3664		1.325
	22.0	1.355	1.297	1.2277	1.3703		1.378
	24.0	1.517	1.444	1.2531	1.3741		1.437
	26.0	1.687	1.597	1.2793	1.3781		1.503
Calcium	0.5	0.045	0.045	1.0024	1.3342	0.22	1.015
chloride	1.0	0.091	0.091	1.0065	1.3354	0.44	1.028
$CaCl_2$	2.0	0.184	0.183	1.0148	1.3378	0.88	1.050

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	3.0	0.279	0.277	1.0232	1.3402	1.33	1.078
	4.0	0.375	0.372	1.0316	1.3426	1.82	1.110
	5.0	0.474	0.469	1.0401	1.3451	2.35	1.143
	6.0	0.575	0.567	1.0486	1.3475	2.93	1.175
	7.0	0.678	0.667	1.0572	1.3500	3.57	1.208
	8.0	0.784	0.768	1.0659	1.3525	4.28	1.242
	9.0	0.891	0.872	1.0747	1.3549	5.04	1.279
	10.0	1.001	0.976	1.0835	1.3575	5.86	1.319
	12.0	1.229	1.191	1.1014	1.3625	7.70	1.408
	14.0	1.467	1.413	1.1198	1.3677	9.83	1.508
	16.0	1.716	1.641	1.1386	1.3730	12.28	1.625
	18.0	1.978	1.878	1.1579	1.3784	15.11	1.764
	20.0	2.253	2.122	1.1775	1.3839	18.30	1.930
	22.0	2.541	2.374	1.1976	1.3895	21.70	2.127
	24.0	2.845	2.634	1.2180	1.3951	25.30	2.356
	26.0	3.166	2.902	1.2388	1.4008	29.70	2.645
	28.0	3.504	3.179	1.2600	1.4066	34.70	3.000
	30.0	3.862	3.464	1.2816	1.4124	41.00	3.467
	32.0	4.240	3.759	1.3036	1.4183	49.70	4.035
	34.0	4.642	4.062	1.3260	1.4242		4.820
	36.0	5.068	4.375	1.3488	1.4301		5.807
	38.0	5.522	4.698	1.3720	1.4361		7.321
	40.0	6.007	5.030	1.3957	1.4420		8.997
Cesium	0.5	0.030	0.030	1.0020	1.3334	0.10	1.000
chloride	1.0	0.060	0.060	1.0058	1.3337	0.20	0.997
CsCl	2.0	0.121	0.120	1.0135	1.3345	0.40	0.992
	3.0	0.184	0.182	1.0214	1.3353	0.61	0.988
	4.0	0.247	0.245	1.0293	1.3361	0.81	0.984
	5.0	0.313	0.308	1.0374	1.3369	1.02	0.980
	6.0	0.379	0.373	1.0456	1.3377	1.22	0.977
	7.0	0.447	0.438	1.0540	1.3386	1.43	0.974
	8.0	0.516	0.505	1.0625	1.3394	1.64	0.971
	9.0	0.587	0.573	1.0711	1.3403	1.85	0.969
	10.0	0.660	0.641	1.0798	1.3412	2.06	0.966
	12.0	0.810	0.782	1.0978	1.3430	2.51	0.961
	14.0	0.967	0.928	1.1163	1.3448	2.97	0.955
	16.0	1.131	1.079	1.1355	1.3468	3.46	0.950
	18.0	1.304	1.235	1.1552	1.3487	3.96	0.945
	20.0	1.485	1.397	1.1756	1.3507	4.49	0.939
	22.0	1.675	1.564	1.1967	1.3528		0.934
	24.0	1.876	1.737	1.2185	1.3550		0.930
	26.0	2.087	1.917	1.2411	1.3572		0.926
	28.0	2.310	2.103	1.2644	1.3594		0.924
	30.0	2.546	2.296	1.2885	1.3617		0.922
	32.0	2.795	2.497	1.3135	1.3641		0.922
	34.0	3.060	2.705	1.3393	1.3666		0.924
	36.0	3.341	2.921	1.3661	1.3691		0.926
	38.0	3.640	3.146	1.3938	1.3717		0.930
	40.0	3.960	3.380	1.4226	1.3744		0.934
	42.0	4.301	3.624	1.4525	1.3771		0.940
	44.0	4.667	3.877	1.4835	1.3800		0.947
	46.0	5.060	4.142	1.5158	1.3829		0.956
	48.0	5.483	4.418	1.5495	1.3860		0.967
	50.0	5.940	4.706	1.5846	1.3892		0.981
	60.0	8.910	6.368	1.7868	1.4076		1.120
	64.0	10.560	7.163	1.8842	1.4167		1.238
Citric acid	0.5	0.026	0.026	1.0002	1.3336	0.05	1.013
$(HO)C(COOH)_3$	1.0	0.053	0.052	1.0022	1.3343	0.11	1.024
	2.0	0.106	0.105	1.0063	1.3356	0.21	1.048

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	3.0	0.161	0.158	1.0105	1.3368	0.32	1.073
	4.0	0.217	0.211	1.0147	1.3381	0.43	1.098
	5.0	0.274	0.265	1.0189	1.3394	0.54	1.125
	6.0	0.332	0.320	1.0232	1.3407	0.65	1.153
	7.0	0.392	0.374	1.0274	1.3420	0.76	1.183
	8.0	0.453	0.430	1.0316	1.3433	0.88	1.214
	9.0	0.515	0.485	1.0359	1.3446	1.00	1.247
	10.0	0.578	0.541	1.0402	1.3459	1.12	1.283
	12.0	0.710	0.655	1.0490	1.3486	1.38	1.357
	14.0	0.847	0.771	1.0580	1.3514	1.66	1.436
	16.0	0.991	0.889	1.0672	1.3541	1.95	1.525
	18.0	1.143	1.008	1.0764	1.3569	2.26	1.625
	20.0	1.301	1.130	1.0858	1.3598	2.57	1.740
	22.0	1.468	1.254	1.0953	1.3626	2.88	1.872
	24.0	1.644	1.380	1.1049	1.3655	3.21	2.017
	26.0	1.829	1.508	1.1147	1.3684	3.55	2.178
	28.0	2.024	1.639	1.1246	1.3714	3.89	2.356
	30.0	2.231	1.772	1.1346	1.3744	4.25	2.549
Copper	0.5	0.031	0.031	1.0033	1.3339	0.08	1.017
sulfate	1.0	0.063	0.063	1.0085	1.3348	0.14	1.036
$CuSO_4$	2.0	0.128	0.128	1.0190	1.3367	0.26	1.084
	3.0	0.194	0.194	1.0296	1.3386	0.37	1.129
	4.0	0.261	0.261	1.0403	1.3405	0.48	1.173
	5.0	0.330	0.329	1.0511	1.3424	0.59	1.221
	6.0	0.400	0.399	1.0620	1.3443	0.70	1.276
	7.0	0.472	0.471	1.0730	1.3462	0.82	1.336
	8.0	0.545	0.543	1.0842	1.3481	0.93	1.400
	9.0	0.620	0.618	1.0955	1.3501	1.05	1.469
	10.0	0.696	0.694	1.1070	1.3520	1.18	1.543
	12.0	0.854	0.850	1.1304	1.3560	1.45	1.701
	14.0	1.020	1.013	1.1545	1.3601	1.75	1.889
	16.0	1.193	1.182	1.1796	1.3644		2.136
	18.0	1.375	1.360	1.2059	1.3689		2.449
Disodium	0.5	0.015	0.015	1.0009	1.3339	0.07	1.017
ethylenediamine	1.0	0.030	0.030	1.0036	1.3348	0.14	1.032
tetraacetate	1.5	0.045	0.045	1.0062	1.3356	0.21	1.046
(EDTA sodium)	2.0	0.061	0.060	1.0089	1.3365	0.27	1.062
$Na_2C_{10}H_{14}N_2O_8$	2.5	0.076	0.075	1.0115	1.3374	0.33	1.077
	3.0	0.092	0.090	1.0142	1.3383	0.40	1.093
	3.5	0.108	0.106	1.0169	1.3392	0.46	1.109
	4.0	0.124	0.121	1.0196	1.3400	0.52	1.125
	4.5	0.140	0.137	1.0223	1.3409	0.58	1.142
	5.0	0.157	0.152	1.0250	1.3418	0.65	1.160
	5.5	0.173	0.168	1.0277	1.3427	0.71	1.178
	6.0	0.190	0.184	1.0305	1.3436	0.77	1.197
Ethanol	0.5	0.109	0.108	0.9973	1.3333	0.20	1.023
CH_3CH_2OH	1.0	0.219	0.216	0.9963	1.3336	0.40	1.046
	2.0	0.443	0.432	0.9945	1.3342	0.81	1.095
	3.0	0.671	0.646	0.9927	1.3348	1.23	1.140
	4.0	0.904	0.860	0.9910	1.3354	1.65	1.183
	5.0	1.142	1.074	0.9893	1.3360	2.09	1.228
	6.0	1.385	1.286	0.9878	1.3367	2.54	1.279
	7.0	1.634	1.498	0.9862	1.3374	2.99	1.331
	8.0	1.887	1.710	0.9847	1.3381	3.47	1.385
	9.0	2.147	1.921	0.9833	1.3388	3.96	1.442
	10.0	2.412	2.131	0.9819	1.3395	4.47	1.501
	12.0	2.960	2.551	0.9792	1.3410	5.56	1.627
	14.0	3.534	2.967	0.9765	1.3425	6.73	1.761

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	16.0	4.134	3.382	0.9739	1.3440	8.01	1.890
	18.0	4.765	3.795	0.9713	1.3455	9.40	2.019
	20.0	5.427	4.205	0.9687	1.3469	10.92	2.142
	22.0	6.122	4.613	0.9660	1.3484	12.60	2.259
	24.0	6.855	5.018	0.9632	1.3498	14.47	2.370
	26.0	7.626	5.419	0.9602	1.3511	16.41	2.476
	28.0	8.441	5.817	0.9571	1.3524	18.43	2.581
	30.0	9.303	6.212	0.9539	1.3535	20.47	2.667
	32.0	10.215	6.601	0.9504	1.3546	22.44	2.726
	34.0	11.182	6.987	0.9468	1.3557	24.27	2.768
	36.0	12.210	7.370	0.9431	1.3566	25.98	2.803
	38.0	13.304	7.747	0.9392	1.3575	27.62	2.829
	40.0	14.471	8.120	0.9352	1.3583	29.26	2.846
	42.0	15.718	8.488	0.9311	1.3590	30.98	2.852
	44.0	17.055	8.853	0.9269	1.3598	32.68	2.850
	46.0	18.490	9.213	0.9227	1.3604	34.36	2.843
	48.0	20.036	9.568	0.9183	1.3610	36.04	2.832
	50.0	21.706	9.919	0.9139	1.3616	37.67	2.813
	60.0	32.559	11.605	0.8911	1.3638	44.93	2.547
	70.0	50.648	13.183	0.8676	1.3652		2.214
	80.0	86.824	14.649	0.8436	1.3658		1.881
	90.0	195.355	15.980	0.8180	1.3650		1.542
	92.0	249.620	16.225	0.8125	1.3646		1.475
	94.0	340.062	16.466	0.8070	1.3642		1.407
	96.0	520.946	16.697	0.8013	1.3636		1.342
	98.0		16.920	0.7954	1.3630		1.273
	100.0		17.133	0.7893	1.3614		1.203
Ethylene	0.5	0.081	0.080	0.9988	1.3335	0.15	1.010
glycol	1.0	0.163	0.161	0.9995	1.3339	0.30	1.020
$(CH_2OH)_2$	2.0	0.329	0.322	1.0007	1.3348	0.61	1.048
	3.0	0.498	0.484	1.0019	1.3358	0.92	1.074
	4.0	0.671	0.646	1.0032	1.3367	1.24	1.099
	5.0	0.848	0.809	1.0044	1.3377	1.58	1.125
	6.0	1.028	0.972	1.0057	1.3386	1.91	1.153
	7.0	1.213	1.136	1.0070	1.3396	2.26	1.182
	8.0	1.401	1.299	1.0082	1.3405	2.62	1.212
	9.0	1.593	1.464	1.0095	1.3415	2.99	1.243
	10.0	1.790	1.628	1.0108	1.3425	3.37	1.277
	12.0	2.197	1.959	1.0134	1.3444	4.16	1.348
	14.0	2.623	2.292	1.0161	1.3464	5.01	1.424
	16.0	3.069	2.626	1.0188	1.3484	5.91	1.500
	18.0	3.537	2.962	1.0214	1.3503	6.89	1.578
	20.0	4.028	3.300	1.0241	1.3523	7.93	1.661
	24.0	5.088	3.981	1.0296	1.3564	10.28	1.843
	28.0	6.265	4.669	1.0350	1.3605	13.03	2.047
	32.0	7.582	5.364	1.0405	1.3646	16.23	2.280
	36.0	9.062	6.067	1.0460	1.3687	19.82	2.537
	40.0	10.741	6.776	1.0514	1.3728	23.84	2.832
	44.0	12.659	7.491	1.0567	1.3769	28.32	3.166
	48.0	14.872	8.212	1.0619	1.3811	33.30	3.544
	52.0	17.453	8.939	1.0670	1.3851	38.81	3.981
	56.0	20.505	9.671	1.0719	1.3892	44.83	4.475
	60.0	24.166	10.406	1.0765	1.3931	51.23	5.026
Ferric	0.5	0.031	0.031	1.0025	1.3344	0.21	1.024
chloride	1.0	0.062	0.062	1.0068	1.3358	0.39	1.047
$FeCl_3$	2.0	0.126	0.125	1.0153	1.3386	0.75	1.093
	3.0	0.191	0.189	1.0238	1.3413	1.15	1.139
	4.0	0.257	0.255	1.0323	1.3441	1.56	1.187
	5.0	0.324	0.321	1.0408	1.3468	2.00	1.238

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	6.0	0.394	0.388	1.0493	1.3496	2.48	1.292
	7.0	0.464	0.457	1.0580	1.3524	2.99	1.350
	8.0	0.536	0.526	1.0668	1.3552	3.57	1.412
	9.0	0.610	0.597	1.0760	1.3581	4.19	1.480
	10.0	0.685	0.669	1.0853	1.3611	4.85	1.553
	12.0	0.841	0.817	1.1040	1.3670	6.38	1.707
	14.0	1.004	0.969	1.1228	1.3730	8.22	1.879
	16.0	1.174	1.126	1.1420		10.45	2.080
	18.0	1.353	1.289	1.1615		13.08	2.311
	20.0	1.541	1.457	1.1816		16.14	2.570
	24.0	1.947	1.810	1.2234		23.79	3.178
	28.0	2.398	2.189	1.2679		33.61	4.038
	32.0	2.901	2.595	1.3153		49.16	5.274
	36.0	3.468	3.030	1.3654			7.130
	40.0	4.110	3.496	1.4176			9.674
Formic acid	0.5	0.109	0.109	0.9994	1.3333	0.21	1.006
HCOOH	1.0	0.219	0.217	1.0006	1.3336	0.42	1.011
	2.0	0.443	0.436	1.0029	1.3342	0.82	1.017
	3.0	0.672	0.655	1.0053	1.3348	1.24	1.195
	4.0	0.905	0.876	1.0077	1.3354	1.67	1.032
	5.0	1.143	1.097	1.0102	1.3359	2.10	1.039
	6.0	1.387	1.320	1.0126	1.3365	2.53	1.046
	7.0	1.635	1.544	1.0150	1.3371	2.97	1.052
	8.0	1.889	1.768	1.0175	1.3376	3.40	1.058
	9.0	2.149	1.994	1.0199	1.3382	3.84	1.064
	10.0	2.414	2.221	1.0224	1.3387	4.27	1.070
	12.0	2.962	2.678	1.0273	1.3397	5.19	1.082
	14.0	3.537	3.139	1.0322	1.3408	6.11	1.094
	16.0	4.138	3.605	1.0371	1.3418	7.06	1.106
	18.0	4.769	4.074	1.0419	1.3428	8.08	1.119
	20.0	5.431	4.548	1.0467	1.3437	9.11	1.132
	28.0	8.449	6.481	1.0654	1.3475	13.10	1.179
	36.0	12.220	8.477	1.0839	1.3511	17.65	1.227
	44.0	17.070	10.529	1.1015	1.3547	22.93	1.281
	52.0	23.535	12.633	1.1183	1.3581	29.69	1.340
	60.0	32.587	14.813	1.1364	1.3612	38.26	1.410
	68.0	46.166	17.054	1.1544	1.3641		1.490
D-Fructose	0.5	0.028	0.028	1.0002	1.3337	0.05	1.015
$C_6H_{12}O_6$	1.0	0.056	0.056	1.0021	1.3344	0.10	1.028
	2.0	0.113	0.112	1.0061	1.3358	0.21	1.054
	3.0	0.172	0.168	1.0101	1.3373	0.32	1.080
	4.0	0.231	0.225	1.0140	1.3387	0.43	1.106
	5.0	0.292	0.283	1.0181	1.3402	0.54	1.134
	6.0	0.354	0.340	1.0221	1.3417	0.66	1.165
	7.0	0.418	0.399	1.0262	1.3431	0.78	1.198
	8.0	0.483	0.458	1.0303	1.3446	0.90	1.232
	9.0	0.549	0.517	1.0344	1.3461	1.03	1.270
	10.0	0.617	0.576	1.0385	1.3476	1.16	1.309
	12.0	0.757	0.697	1.0469	1.3507	1.43	1.391
	14.0	0.904	0.820	1.0554	1.3538	1.71	1.483
	16.0	1.057	0.945	1.0640	1.3569	2.01	1.587
	18.0	1.218	1.072	1.0728	1.3601	2.32	1.703
	20.0	1.388	1.201	1.0816	1.3634	2.64	1.837
	22.0	1.566	1.332	1.0906	1.3667	3.05	1.986
	24.0	1.753	1.465	1.0996	1.3700	3.43	2.154
	26.0	1.950	1.600	1.1089	1.3734	3.82	2.348
	28.0	2.159	1.738	1.1182	1.3768	4.20	2.562
	30.0	2.379	1.878	1.1276	1.3803		2.817
	32.0	2.612	2.020	1.1372	1.3839		3.112

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	34.0	2.859	2.164	1.1469	1.3874		3.462
	36.0	3.122	2.312	1.1568	1.3911		3.899
	38.0	3.402	2.461	1.1668	1.3948		4.418
	40.0	3.700	2.613	1.1769	1.3985		5.046
	42.0	4.019	2.767	1.1871	1.4023		5.773
	44.0	4.361	2.925	1.1975	1.4062		6.644
	46.0	4.728	3.084	1.2080	1.4101		7.753
	48.0	5.124	3.247	1.2187	1.4141		9.060
D-Glucose	0.5	0.028	0.028	1.0001	1.3337	0.05	1.010
$C_6H_{12}O_6$	1.0	0.056	0.056	1.0020	1.3344	0.11	1.021
	2.0	0.113	0.112	1.0058	1.3358	0.21	1.052
	3.0	0.172	0.168	1.0097	1.3373	0.32	1.083
	4.0	0.231	0.225	1.0136	1.3387	0.43	1.113
	5.0	0.292	0.282	1.0175	1.3402	0.55	1.145
	6.0	0.354	0.340	1.0214	1.3417	0.67	1.179
	7.0	0.418	0.398	1.0254	1.3432	0.79	1.214
	8.0	0.483	0.457	1.0294	1.3447	0.91	1.250
	9.0	0.549	0.516	1.0334	1.3462	1.04	1.289
	10.0	0.617	0.576	1.0375	1.3477	1.17	1.330
	12.0	0.757	0.697	1.0457	1.3508	1.44	1.416
	14.0	0.904	0.819	1.0540	1.3539	1.73	1.512
	16.0	1.057	0.944	1.0624	1.3571	2.03	1.625
	18.0	1.218	1.070	1.0710	1.3603	2.35	1.757
	20.0	1.388	1.199	1.0797	1.3635	2.70	1.904
	22.0	1.566	1.329	1.0884	1.3668	3.07	2.063
	24.0	1.753	1.462	1.0973	1.3702	3.48	2.242
	26.0	1.950	1.597	1.1063	1.3736	3.90	2.458
	28.0	2.159	1.734	1.1154	1.3770	4.34	2.707
	30.0	2.379	1.873	1.1246	1.3805	4.79	2.998
	32.0	2.612	2.014	1.1340	1.3840		3.324
	34.0	2.859	2.158	1.1434	1.3876		3.704
	36.0	3.122	2.304	1.1529	1.3912		4.193
	38.0	3.402	2.452	1.1626	1.3949		4.786
	40.0	3.700	2.603	1.1724	1.3986		5.493
	42.0	4.019	2.756	1.1823	1.4024		6.288
	44.0	4.361	2.912	1.1924	1.4062		7.235
	46.0	4.728	3.071	1.2026	1.4101		8.454
	48.0	5.124	3.232	1.2130	1.4141		9.883
	50.0	5.551	3.396	1.2235	1.4181		11.884
	52.0	6.013	3.562	1.2342	1.4222		14.489
	54.0	6.516	3.732	1.2451	1.4263		17.916
	56.0	7.064	3.905	1.2562	1.4306		22.886
	58.0	7.665	4.081	1.2676	1.4349		29.389
	60.0	8.326	4.261	1.2793	1.4394		37.445
Glycerol	0.5	0.055	0.054	0.9994	1.3336	0.07	1.011
$CH_2OHCHOHCH_2OH$	1.0	0.110	0.109	1.0005	1.3342	0.18	1.022
	2.0	0.222	0.218	1.0028	1.3353	0.41	1.048
	3.0	0.336	0.327	1.0051	1.3365	0.63	1.074
	4.0	0.452	0.438	1.0074	1.3376	0.85	1.100
	5.0	0.572	0.548	1.0097	1.3388	1.08	1.127
	6.0	0.693	0.659	1.0120	1.3400	1.32	1.157
	7.0	0.817	0.771	1.0144	1.3412	1.56	1.188
	8.0	0.944	0.883	1.0167	1.3424	1.81	1.220
	9.0	1.074	0.996	1.0191	1.3436	2.06	1.256
	10.0	1.207	1.109	1.0215	1.3448	2.32	1.291
	12.0	1.481	1.337	1.0262	1.3472	2.88	1.365
	14.0	1.768	1.568	1.0311	1.3496	3.47	1.445
	16.0	2.068	1.800	1.0360	1.3521	4.09	1.533
	18.0	2.384	2.035	1.0409	1.3547	4.76	1.630

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	20.0	2.715	2.271	1.0459	1.3572	5.46	1.737
	24.0	3.429	2.752	1.0561	1.3624	7.01	1.988
	28.0	4.223	3.242	1.0664	1.3676	8.77	2.279
	32.0	5.110	3.742	1.0770	1.3730	10.74	2.637
	36.0	6.108	4.252	1.0876	1.3785	12.96	3.088
	40.0	7.239	4.771	1.0984	1.3841	15.50	3.653
	44.0	8.532	5.300	1.1092	1.3897		4.443
	48.0	10.024	5.838	1.1200	1.3954		5.413
	52.0	11.764	6.385	1.1308	1.4011		6.666
	56.0	13.820	6.944	1.1419	1.4069		8.349
	60.0	16.288	7.512	1.1530	1.4129		10.681
	64.0	19.305	8.092	1.1643	1.4189		13.657
	68.0	23.075	8.680	1.1755	1.4249		18.457
	72.0	27.923	9.277	1.1866	1.4310		27.625
	76.0	34.387	9.884	1.1976	1.4370		40.571
	80.0	43.436	10.498	1.2085	1.4431		59.900
	84.0	57.009	11.121	1.2192	1.4492		84.338
	88.0	79.632	11.753	1.2299	1.4553		147.494
	92.0	124.878	12.392	1.2404	1.4613		384.467
	96.0	260.615	13.039	1.2508	1.4674		780.458
	100.0		13.694	1.2611	1.4735		
Hydrochloric	0.5	0.138	0.137	1.0007	1.3341	0.49	1.008
acid	1.0	0.277	0.275	1.0031	1.3353	0.99	1.015
HCl	2.0	0.560	0.553	1.0081	1.3376	2.08	1.029
	3.0	0.848	0.833	1.0130	1.3399	3.28	1.044
	4.0	1.143	1.117	1.0179	1.3422	4.58	1.059
	5.0	1.444	1.403	1.0228	1.3445	5.98	1.075
	6.0	1.751	1.691	1.0278	1.3468	7.52	1.091
	7.0	2.064	1.983	1.0327	1.3491	9.22	1.108
	8.0	2.385	2.277	1.0377	1.3515	11.10	1.125
	9.0	2.713	2.574	1.0426	1.3538	13.15	1.143
	10.0	3.047	2.873	1.0476	1.3561	15.40	1.161
	12.0	3.740	3.481	1.0576	1.3607	20.51	1.199
	14.0	4.465	4.099	1.0676	1.3653		1.239
	16.0	5.224	4.729	1.0777	1.3700		1.282
	18.0	6.020	5.370	1.0878	1.3746		1.326
	20.0	6.857	6.023	1.0980	1.3792		1.374
	22.0	7.736	6.687	1.1083	1.3838		1.426
	24.0	8.661	7.362	1.1185	1.3884		1.483
	26.0	9.636	8.049	1.1288	1.3930		1.547
	28.0	10.666	8.748	1.1391	1.3976		1.620
	30.0	11.754	9.456	1.1492	1.4020		1.705
	32.0	12.907	10.175	1.1594	1.4066		1.799
	34.0	14.129	10.904	1.1693	1.4112		1.900
	36.0	15.427	11.642	1.1791	1.4158		2.002
	38.0	16.810	12.388	1.1886	1.4204		2.105
	40.0	18.284	13.140	1.1977	1.4250		
Lactic acid	0.5	0.056	0.055	0.9992	1.3335	0.10	1.014
$CH_3CHOHCOOH$	1.0	0.112	0.111	1.0002	1.3340	0.19	1.027
	2.0	0.227	0.223	1.0023	1.3350	0.38	1.056
	3.0	0.343	0.334	1.0043	1.3360	0.57	1.084
	4.0	0.463	0.447	1.0065	1.3370	0.76	1.110
	5.0	0.584	0.560	1.0086	1.3380	0.95	1.138
	6.0	0.709	0.673	1.0108	1.3390	1.16	1.167
	7.0	0.836	0.787	1.0131	1.3400	1.36	1.198
	8.0	0.965	0.902	1.0153	1.3410	1.57	1.229
	9.0	1.098	1.017	1.0176	1.3420	1.79	1.262
	10.0	1.233	1.132	1.0199	1.3430	2.02	1.296
	12.0	1.514	1.365	1.0246	1.3450	2.49	1.366

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	14.0	1.807	1.600	1.0294	1.3470	2.99	1.441
	16.0	2.115	1.837	1.0342	1.3491	3.48	1.522
	18.0	2.437	2.076	1.0390	1.3511	3.96	1.607
	20.0	2.775	2.318	1.0439	1.3532	4.44	1.699
	24.0	3.506	2.807	1.0536	1.3573		1.902
	28.0	4.317	3.305	1.0632	1.3615		2.136
	32.0	5.224	3.811	1.0728	1.3657		2.414
	36.0	6.244	4.325	1.0822	1.3700		2.730
	40.0	7.401	4.847	1.0915	1.3743		3.114
	44.0	8.722	5.377	1.1008	1.3786		3.566
	48.0	10.247	5.917	1.1105	1.3828		4.106
	52.0	12.026	6.466	1.1201	1.3871		4.789
	56.0	14.129	7.023	1.1297	1.3914		5.579
	60.0	16.652	7.588	1.1392	1.3958		6.679
	64.0	19.736	8.161	1.1486	1.4001		8.024
	68.0	23.590	8.741	1.1579	1.4045		9.863
	72.0	28.546	9.328	1.1670	1.4088		12.866
	76.0	35.154	9.922	1.1760	1.4131		16.974
	80.0	44.405	10.522	1.1848	1.4173		22.164
Lactose	0.5	0.015	0.015	1.0002	1.3337	0.03	1.013
$C_{12}H_{22}O_{11}$	1.0	0.030	0.029	1.0021	1.3345	0.06	1.026
	2.0	0.060	0.059	1.0061	1.3359	0.11	1.058
	3.0	0.090	0.089	1.0102	1.3375	0.17	1.089
	4.0	0.122	0.119	1.0143	1.3390	0.23	1.120
	5.0	0.154	0.149	1.0184	1.3406	0.29	1.154
	6.0	0.186	0.179	1.0225	1.3421	0.35	1.191
	7.0	0.220	0.210	1.0267	1.3437	0.42	1.232
	8.0	0.254	0.241	1.0308	1.3453	0.50	1.276
	9.0	0.289	0.272	1.0349	1.3468		1.321
	10.0	0.325	0.304	1.0390	1.3484		1.370
	12.0	0.398	0.367	1.0473	1.3515		1.476
	14.0	0.476	0.432	1.0558	1.3548		1.593
	16.0	0.556	0.498	1.0648	1.3582		1.724
	18.0	0.641	0.565	1.0746	1.3619		1.869
Lithium	0.5	0.119	0.118	1.0012	1.3341	0.42	1.019
chloride	1.0	0.238	0.237	1.0041	1.3351	0.84	1.037
LiCl	2.0	0.481	0.476	1.0099	1.3373	1.72	1.072
	3.0	0.730	0.719	1.0157	1.3394	2.68	1.108
	4.0	0.983	0.964	1.0215	1.3415	3.73	1.146
	5.0	1.241	1.211	1.0272	1.3436	4.86	1.185
	6.0	1.506	1.462	1.0330	1.3457	6.14	1.226
	7.0	1.775	1.715	1.0387	1.3478	7.56	1.269
	8.0	2.051	1.971	1.0444	1.3499	9.11	1.313
	9.0	2.333	2.230	1.0502	1.3520	10.79	1.360
	10.0	2.621	2.491	1.0560	1.3541	12.61	1.411
	12.0	3.217	3.022	1.0675	1.3583	16.59	1.522
	14.0	3.840	3.564	1.0792	1.3625	21.04	1.647
	16.0	4.493	4.118	1.0910	1.3668		1.787
	18.0	5.178	4.683	1.1029	1.3711		1.942
	20.0	5.897	5.260	1.1150	1.3755		2.128
	22.0	6.653	5.851	1.1274	1.3799		2.341
	24.0	7.449	6.453	1.1399	1.3844		2.600
	26.0	8.288	7.069	1.1527	1.3890		2.925
	28.0	9.173	7.700	1.1658	1.3936		3.318
	30.0	10.109	8.344	1.1791	1.3983		3.785
Magnesium	0.5	0.053	0.053	1.0022	1.3343	0.26	1.024
chloride	1.0	0.106	0.106	1.0062	1.3356	0.52	1.046
$MgCl_2$	2.0	0.214	0.213	1.0144	1.3381	1.06	1.091

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	3.0	0.325	0.322	1.0226	1.3406	1.65	1.139
	4.0	0.438	0.433	1.0309	1.3432	2.30	1.188
	5.0	0.553	0.546	1.0394	1.3457	3.01	1.241
	6.0	0.670	0.660	1.0479	1.3483		1.298
	7.0	0.791	0.777	1.0564	1.3508		1.358
	8.0	0.913	0.895	1.0651	1.3534		1.423
	9.0	1.039	1.015	1.0738	1.3560		1.493
	10.0	1.167	1.137	1.0826	1.3587		1.570
	12.0	1.432	1.387	1.1005	1.3641		1.745
	14.0	1.710	1.645	1.1189	1.3695		1.956
	16.0	2.001	1.911	1.1372	1.3749		2.207
	18.0	2.306	2.184	1.1553	1.3804		2.507
	20.0	2.626	2.467	1.1742	1.3859		2.867
	22.0	2.962	2.758	1.1938	1.3915		3.323
	24.0	3.317	3.060	1.2140	1.3972		3.917
	26.0	3.690	3.371	1.2346	1.4030		4.694
	28.0	4.085	3.692	1.2555	1.4089		5.709
	30.0	4.501	4.022	1.2763	1.4148		7.017
Magnesium	0.5	0.042	0.042	1.0033	1.3340	0.10	1.027
sulfate	1.0	0.084	0.084	1.0084	1.3350	0.19	1.054
$MgSO_4$	2.0	0.170	0.169	1.0186	1.3371	0.36	1.112
	3.0	0.257	0.256	1.0289	1.3391	0.52	1.177
	4.0	0.346	0.345	1.0392	1.3411	0.69	1.249
	5.0	0.437	0.436	1.0497	1.3431	0.87	1.328
	6.0	0.530	0.528	1.0602	1.3451	1.05	1.411
	7.0	0.625	0.623	1.0708	1.3471	1.24	1.498
	8.0	0.722	0.719	1.0816	1.3492	1.43	1.593
	9.0	0.822	0.817	1.0924	1.3512	1.64	1.702
	10.0	0.923	0.917	1.1034	1.3532	1.85	1.829
	12.0	1.133	1.122	1.1257	1.3572	2.31	2.104
	14.0	1.352	1.336	1.1484	1.3613	2.86	2.412
	16.0	1.582	1.557	1.1717	1.3654	3.67	2.809
	18.0	1.824	1.788	1.1955	1.3694		3.360
	20.0	2.077	2.027	1.2198	1.3735		4.147
	22.0	2.343	2.275	1.2447	1.3776		5.199
	24.0	2.624	2.532	1.2701	1.3817		6.498
	26.0	2.919	2.800	1.2961	1.3858		8.066
Maltose	0.5	0.015	0.015	1.0003	1.3337	0.03	1.016
$C_{12}H_{22}O_{11}$	1.0	0.030	0.029	1.0023	1.3345	0.06	1.030
	2.0	0.060	0.059	1.0063	1.3359	0.11	1.060
	3.0	0.090	0.089	1.0104	1.3374	0.17	1.092
	4.0	0.122	0.119	1.0144	1.3389	0.23	1.126
	5.0	0.154	0.149	1.0184	1.3404	0.29	1.162
	6.0	0.186	0.179	1.0224	1.3420	0.35	1.200
	7.0	0.220	0.210	1.0265	1.3435	0.42	1.239
	8.0	0.254	0.241	1.0305	1.3450	0.48	1.281
	9.0	0.289	0.272	1.0345	1.3466	0.55	1.325
	10.0	0.325	0.303	1.0385	1.3482	0.62	1.372
	12.0	0.398	0.367	1.0465	1.3513	0.77	1.474
	14.0	0.476	0.431	1.0545	1.3546	0.92	1.588
	16.0	0.556	0.497	1.0629	1.3578	1.08	1.715
	18.0	0.641	0.564	1.0716	1.3612	1.25	1.859
	20.0	0.730	0.631	1.0801	1.3644	1.43	2.021
	22.0	0.824	0.700	1.0894	1.3678	1.64	2.216
	24.0	0.923	0.770	1.0984	1.3714	1.85	2.463
	26.0	1.026	0.842	1.1080	1.3749	2.08	2.753
	28.0	1.136	0.914	1.1171	1.3785	2.34	3.066
	30.0	1.252	0.988	1.1269	1.3821	2.62	3.427
	40.0	1.948	1.375	1.1769	1.4013	4.41	6.926

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	50.0	2.921	1.797	1.2304	1.4217		17.786
	52.0	3.165	1.886	1.2416	1.4260		22.034
	54.0	3.429	1.976	1.2528	1.4308		28.757
	56.0	3.718	2.068	1.2638	1.4350		38.226
	58.0	4.034	2.159	1.2740	1.4394		49.298
	60.0	4.382	2.253	1.2855	1.4440		
Manganese(II)	1.0	0.067	0.067	1.0080	1.3348	0.16	1.046
sulfate	2.0	0.135	0.135	1.0178	1.3366	0.31	1.090
$MnSO_4$	3.0	0.205	0.204	1.0277	1.3384	0.44	1.137
	4.0	0.276	0.275	1.0378	1.3402	0.57	1.187
	5.0	0.349	0.347	1.0480	1.3420	0.70	1.242
	6.0	0.423	0.421	1.0583	1.3438	0.84	1.301
	7.0	0.498	0.495	1.0688	1.3457	0.98	1.363
	8.0	0.576	0.572	1.0794	1.3475	1.12	1.431
	9.0	0.655	0.650	1.0902	1.3494	1.28	1.505
	10.0	0.736	0.729	1.1012	1.3513	1.44	1.587
	12.0	0.903	0.893	1.1236	1.3551	1.80	1.779
	14.0	1.078	1.063	1.1467	1.3589	2.21	2.005
	16.0	1.261	1.240	1.1705	1.3629	2.67	2.272
	18.0	1.454	1.424	1.1950	1.3668	3.19	2.580
	20.0	1.656	1.616	1.2203	1.3708	3.80	2.938
D-Mannitol	0.5	0.028	0.027	1.0000	1.3337	0.05	1.019
$CH_2(CHOH)_4CH_2OH$	1.0	0.055	0.055	1.0017	1.3345	0.10	1.032
	2.0	0.112	0.110	1.0053	1.3359	0.21	1.057
	3.0	0.170	0.166	1.0088	1.3374	0.32	1.081
	4.0	0.229	0.222	1.0124	1.3389	0.43	1.107
	5.0	0.289	0.279	1.0159	1.3403	0.54	1.135
	6.0	0.350	0.336	1.0195	1.3418	0.66	1.166
	7.0	0.413	0.393	1.0230	1.3433	0.77	1.200
	8.0	0.477	0.451	1.0266	1.3447	0.90	1.236
	9.0	0.543	0.509	1.0302	1.3462	1.02	1.275
	10.0	0.610	0.567	1.0338	1.3477	1.15	1.314
	11.0	0.678	0.626	1.0375	1.3491	1.28	1.355
	12.0	0.749	0.686	1.0412	1.3506	1.41	1.398
	13.0	0.820	0.746	1.0450	1.3521	1.55	1.443
	14.0	0.894	0.806	1.0489	1.3536	1.69	1.489
	15.0	0.969	0.867	1.0529	1.3552	1.84	1.537
Methanol	0.5	0.157	0.156	0.9973	1.3331	0.28	1.022
CH_3OH	1.0	0.315	0.311	0.9964	1.3332	0.56	1.040
	2.0	0.637	0.621	0.9947	1.3334	1.14	1.070
	3.0	0.965	0.930	0.9930	1.3336	1.75	1.100
	4.0	1.300	1.238	0.9913	1.3339	2.37	1.131
	5.0	1.643	1.544	0.9896	1.3341	3.02	1.163
	6.0	1.992	1.850	0.9880	1.3343	3.71	1.196
	7.0	2.349	2.155	0.9864	1.3346	4.41	1.229
	8.0	2.714	2.459	0.9848	1.3348	5.13	1.264
	9.0	3.087	2.762	0.9832	1.3351	5.85	1.297
	10.0	3.468	3.064	0.9816	1.3354	6.60	1.329
	12.0	4.256	3.665	0.9785	1.3359	8.14	1.389
	14.0	5.081	4.262	0.9755	1.3365	9.72	1.446
	16.0	5.945	4.856	0.9725	1.3370	11.36	1.501
	18.0	6.851	5.447	0.9695	1.3376	13.13	1.554
	20.0	7.803	6.034	0.9666	1.3381	15.02	1.604
	22.0	8.803	6.616	0.9636	1.3387	16.98	1.652
	24.0	9.856	7.196	0.9606	1.3392	19.04	1.697
	26.0	10.966	7.771	0.9576	1.3397	21.23	1.735
	28.0	12.138	8.341	0.9545	1.3402	23.59	1.769
	30.0	13.376	8.908	0.9514	1.3407	25.91	1.795

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	32.0	14.688	9.470	0.9482	1.3411	28.15	1.814
	34.0	16.078	10.028	0.9450	1.3415	30.48	1.827
	36.0	17.556	10.580	0.9416	1.3419	32.97	1.835
	38.0	19.129	11.127	0.9382	1.3422	35.60	1.839
	40.0	20.807	11.669	0.9347	1.3425	38.60	1.837
	50.0	31.211	14.288	0.9156	1.3431	54.50	1.761
	60.0	46.816	16.749	0.8944	1.3426	74.50	1.600
	70.0	72.826	19.040	0.8715	1.3411		1.368
	80.0	124.844	21.144	0.8468	1.3385		1.128
	90.0	280.899	23.045	0.8204	1.3348		0.861
	100.0		24.710	0.7917	1.3290		0.586
Nitric acid HNO_3	0.5	0.080	0.079	1.0009	1.3336	0.28	1.004
	1.0	0.160	0.159	1.0037	1.3343	0.56	1.005
	2.0	0.324	0.320	1.0091	1.3356	1.12	1.007
	3.0	0.491	0.483	1.0146	1.3368	1.70	1.010
	4.0	0.661	0.648	1.0202	1.3381	2.32	1.014
	5.0	0.835	0.814	1.0257	1.3394	2.96	1.018
	6.0	1.013	0.982	1.0314	1.3407	3.63	1.022
	7.0	1.194	1.152	1.0370	1.3421	4.33	1.027
	8.0	1.380	1.324	1.0427	1.3434	5.05	1.032
	9.0	1.570	1.498	1.0485	1.3447	5.81	1.038
	10.0	1.763	1.673	1.0543	1.3460	6.60	1.044
	12.0	2.164	2.030	1.0660	1.3487	8.27	1.058
	14.0	2.583	2.395	1.0780	1.3514	10.08	1.075
	16.0	3.023	2.768	1.0901	1.3541	12.04	1.094
	18.0	3.484	3.149	1.1025	1.3569	14.16	1.116
	20.0	3.967	3.539	1.1150	1.3596		1.141
	22.0	4.476	3.937	1.1277	1.3624		1.169
	24.0	5.011	4.344	1.1406	1.3652		1.199
	26.0	5.576	4.760	1.1536	1.3680		1.233
	28.0	6.172	5.185	1.1668	1.3708		1.271
	30.0	6.801	5.618	1.1801	1.3736		1.311
	32.0	7.468	6.060	1.1934	1.3763		1.354
	34.0	8.175	6.512	1.2068	1.3790		1.400
	36.0	8.927	6.971	1.2202	1.3817		1.450
	38.0	9.727	7.439	1.2335	1.3842		1.504
	40.0	10.580	7.913	1.2466	1.3867		1.561
Oxalic acid $(COOH)_2$	0.5	0.056	0.056	1.0006	1.3336	0.16	1.013
	1.0	0.112	0.111	1.0030	1.3342	0.30	1.023
	1.5	0.169	0.167	1.0054	1.3347	0.44	1.033
	2.0	0.227	0.224	1.0079	1.3353	0.57	1.044
	2.5	0.285	0.281	1.0103	1.3359	0.71	1.055
	3.0	0.343	0.337	1.0126	1.3364	0.84	1.065
	3.5	0.403	0.395	1.0150	1.3370	0.97	1.076
	4.0	0.463	0.452	1.0174	1.3375	1.09	1.086
	4.5	0.523	0.510	1.0197	1.3381		1.097
	5.0	0.585	0.568	1.0220	1.3386		1.108
	6.0	0.709	0.684	1.0265	1.3397		1.129
	7.0	0.836	0.802	1.0310	1.3407		1.150
	8.0	0.966	0.920	1.0355	1.3418		1.172
Phosphoric acid H_3PO_4	0.5	0.051	0.051	1.0010	1.3335	0.12	1.010
	1.0	0.103	0.102	1.0038	1.3340	0.24	1.020
	2.0	0.208	0.206	1.0092	1.3349	0.46	1.050
	3.0	0.316	0.311	1.0146	1.3358	0.69	1.079
	4.0	0.425	0.416	1.0200	1.3367	0.93	1.108
	5.0	0.537	0.523	1.0254	1.3376	1.16	1.138
	6.0	0.651	0.631	1.0309	1.3385	1.38	1.169
	7.0	0.768	0.740	1.0363	1.3394	1.62	1.200

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	8.0	0.887	0.850	1.0418	1.3403	1.88	1.232
	9.0	1.009	0.962	1.0474	1.3413	2.16	1.267
	10.0	1.134	1.075	1.0531	1.3422	2.45	1.303
	12.0	1.392	1.304	1.0647	1.3441	3.01	1.382
	14.0	1.661	1.538	1.0765	1.3460	3.76	1.469
	16.0	1.944	1.777	1.0885	1.3480	4.45	1.565
	18.0	2.240	2.022	1.1009	1.3500	5.25	1.671
	20.0	2.551	2.273	1.1135	1.3520	6.23	1.788
	22.0	2.878	2.529	1.1263	1.3540	7.38	1.914
	24.0	3.223	2.791	1.1395	1.3561	8.69	2.049
	26.0	3.585	3.059	1.1528	1.3582	10.12	2.198
	28.0	3.968	3.333	1.1665	1.3604	11.64	2.365
	30.0	4.373	3.614	1.1804	1.3625	13.23	2.553
	32.0	4.802	3.901	1.1945	1.3647	14.94	2.766
	34.0	5.257	4.194	1.2089	1.3669	16.81	3.001
	36.0	5.740	4.495	1.2236	1.3691	18.85	3.260
	38.0	6.254	4.803	1.2385	1.3713	21.09	3.544
	40.0	6.803	5.117	1.2536	1.3735	23.58	3.856
Potassium	0.5	0.050	0.050	1.0014	1.3335	0.18	1.009
bicarbonate	1.0	0.101	0.100	1.0046	1.3341	0.34	1.015
$KHCO_3$	2.0	0.204	0.202	1.0114	1.3353	0.67	1.027
	3.0	0.309	0.305	1.0181	1.3365	0.98	1.040
	4.0	0.416	0.409	1.0247	1.3376	1.29	1.053
	5.0	0.526	0.515	1.0310	1.3386	1.60	1.067
	6.0	0.638	0.622	1.0379	1.3397	1.91	1.081
	7.0	0.752	0.730	1.0446	1.3409	2.22	1.096
	8.0	0.869	0.840	1.0514	1.3419	2.53	1.112
	9.0	0.988	0.951	1.0581	1.3430	2.84	1.128
	10.0	1.110	1.064	1.0650	1.3441	3.16	1.145
	12.0	1.362	1.293	1.0788	1.3462	3.79	1.183
	14.0	1.626	1.528	1.0929	1.3484	4.41	1.224
	16.0	1.903	1.770	1.1073	1.3506		1.270
	18.0	2.193	2.017	1.1221	1.3528		1.319
	20.0	2.497	2.272	1.1372	1.3550		1.373
	22.0	2.817	2.533	1.1527	1.3572		1.432
	24.0	3.154	2.801	1.1685	1.3595		1.497
Potassium	0.5	0.042	0.042	1.0018	1.3336	0.15	1.000
bromide	1.0	0.085	0.084	1.0054	1.3342	0.29	0.998
KBr	2.0	0.171	0.170	1.0127	1.3354	0.59	0.994
	3.0	0.260	0.257	1.0200	1.3366	0.88	0.990
	4.0	0.350	0.345	1.0275	1.3379	1.18	0.985
	5.0	0.442	0.435	1.0350	1.3391	1.48	0.981
	6.0	0.536	0.526	1.0426	1.3403	1.78	0.977
	7.0	0.633	0.618	1.0503	1.3416	2.10	0.974
	8.0	0.731	0.711	1.0581	1.3429	2.42	0.970
	9.0	0.831	0.806	1.0660	1.3441	2.74	0.967
	10.0	0.934	0.903	1.0740	1.3454	3.07	0.964
	12.0	1.146	1.099	1.0903	1.3481	3.76	0.958
	14.0	1.368	1.302	1.1070	1.3507	4.49	0.953
	16.0	1.601	1.512	1.1242	1.3535	5.25	0.949
	18.0	1.845	1.727	1.1419	1.3562	6.04	0.946
	20.0	2.101	1.950	1.1601	1.3591	6.88	0.944
	22.0	2.370	2.179	1.1788	1.3620	7.76	0.943
	24.0	2.654	2.416	1.1980	1.3650	8.70	0.943
	26.0	2.952	2.661	1.2179	1.3680	9.68	0.944
	28.0	3.268	2.914	1.2383	1.3711	10.72	0.947
	30.0	3.601	3.175	1.2593	1.3743	11.82	0.952
	32.0	3.954	3.445	1.2810	1.3776	12.98	0.959
	34.0	4.329	3.724	1.3033	1.3809		0.968

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	36.0	4.727	4.012	1.3263	1.3843		0.979
	38.0	5.150	4.311	1.3501	1.3878		0.993
	40.0	5.602	4.620	1.3746	1.3914		1.010
Potassium	0.5	0.036	0.036	1.0027	1.3339	0.18	1.013
carbonate	1.0	0.073	0.073	1.0072	1.3347	0.34	1.025
K_2CO_3	2.0	0.148	0.147	1.0163	1.3365	0.66	1.048
	3.0	0.224	0.223	1.0254	1.3382	0.99	1.071
	4.0	0.301	0.299	1.0345	1.3399	1.32	1.094
	5.0	0.381	0.378	1.0437	1.3416	1.67	1.119
	6.0	0.462	0.457	1.0529	1.3433	2.03	1.146
	7.0	0.545	0.538	1.0622	1.3450	2.40	1.174
	8.0	0.629	0.620	1.0715	1.3467	2.77	1.204
	9.0	0.716	0.704	1.0809	1.3484	3.17	1.235
	10.0	0.804	0.789	1.0904	1.3501	3.57	1.269
	12.0	0.987	0.963	1.1095	1.3535	4.45	1.339
	14.0	1.178	1.144	1.1291	1.3569	5.39	1.414
	16.0	1.378	1.330	1.1490	1.3603	6.42	1.497
	18.0	1.588	1.523	1.1692	1.3637	7.55	1.594
	20.0	1.809	1.722	1.1898	1.3671	8.82	1.707
	24.0	2.285	2.139	1.2320	1.3739	11.96	1.978
	28.0	2.814	2.584	1.2755	1.3807	16.01	2.331
	32.0	3.405	3.057	1.3204	1.3874	21.46	2.834
	36.0	4.070	3.559	1.3665	1.3940	28.58	3.503
	40.0	4.824	4.093	1.4142	1.4006	37.55	4.360
	50.0	7.236	5.573	1.5404	1.4168		9.369
Potassium	0.5	0.067	0.067	1.0014	1.3337	0.23	1.000
chloride	1.0	0.135	0.135	1.0046	1.3343	0.46	0.999
KCl	2.0	0.274	0.271	1.0110	1.3357	0.92	0.999
	3.0	0.415	0.409	1.0174	1.3371	1.38	0.998
	4.0	0.559	0.549	1.0239	1.3384	1.85	0.997
	5.0	0.706	0.691	1.0304	1.3398	2.32	0.996
	6.0	0.856	0.835	1.0369	1.3411	2.80	0.994
	7.0	1.010	0.980	1.0434	1.3425	3.29	0.992
	8.0	1.166	1.127	1.0500	1.3438	3.80	0.990
	9.0	1.327	1.276	1.0566	1.3452	4.30	0.989
	10.0	1.490	1.426	1.0633	1.3466	4.81	0.988
	12.0	1.829	1.733	1.0768	1.3493	5.88	0.990
	14.0	2.184	2.048	1.0905	1.3521		0.994
	16.0	2.555	2.370	1.1043	1.3549		0.999
	18.0	2.944	2.701	1.1185	1.3577		1.004
	20.0	3.353	3.039	1.1328	1.3606		1.012
	22.0	3.783	3.386	1.1474	1.3635		1.024
	24.0	4.236	3.742	1.1623	1.3665		1.040
Potassium	0.5	0.090	0.089	1.0025	1.3340	0.30	1.010
hydroxide	1.0	0.180	0.179	1.0068	1.3350	0.61	1.019
KOH	2.0	0.364	0.362	1.0155	1.3369	1.24	1.038
	3.0	0.551	0.548	1.0242	1.3388	1.89	1.058
	4.0	0.743	0.736	1.0330	1.3408	2.57	1.079
	5.0	0.938	0.929	1.0419	1.3427	3.36	1.102
	6.0	1.138	1.124	1.0509	1.3445	4.14	1.126
	7.0	1.342	1.322	1.0599	1.3464	4.92	1.151
	8.0	1.550	1.524	1.0690	1.3483		1.177
	9.0	1.763	1.729	1.0781	1.3502		1.205
	10.0	1.980	1.938	1.0873	1.3520		1.233
	12.0	2.431	2.365	1.1059	1.3558		1.294
	14.0	2.902	2.806	1.1246	1.3595		1.361
	16.0	3.395	3.261	1.1435	1.3632		1.436
	18.0	3.913	3.730	1.1626	1.3670		1.521

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	20.0	4.456	4.213	1.1818	1.3707		1.619
	22.0	5.027	4.711	1.2014	1.3744		1.732
	24.0	5.629	5.223	1.2210	1.3781		1.861
	26.0	6.262	5.750	1.2408	1.3818		2.006
	28.0	6.931	6.293	1.2609	1.3854		2.170
	30.0	7.639	6.851	1.2813	1.3889		2.357
	40.0	11.882	9.896	1.3881	1.4068		3.879
	50.0	17.824	13.389	1.5024	1.4247		7.892
Potassium	0.5	0.030	0.030	1.0019	1.3337	0.11	0.999
iodide	1.0	0.061	0.061	1.0056	1.3343	0.22	0.997
KI	2.0	0.123	0.122	1.0131	1.3357	0.43	0.991
	3.0	0.186	0.184	1.0206	1.3370	0.64	0.986
	4.0	0.251	0.248	1.0282	1.3384	0.86	0.981
	5.0	0.317	0.312	1.0360	1.3397	1.08	0.976
	6.0	0.385	0.377	1.0438	1.3411	1.30	0.969
	7.0	0.453	0.443	1.0517	1.3425	1.53	0.963
	8.0	0.524	0.511	1.0598	1.3440	1.77	0.957
	9.0	0.596	0.579	1.0679	1.3454	2.01	0.951
	10.0	0.669	0.648	1.0762	1.3469	2.26	0.946
	12.0	0.821	0.790	1.0931	1.3498	2.77	0.937
	14.0	0.981	0.937	1.1105	1.3529	3.30	0.929
	16.0	1.147	1.088	1.1284	1.3560	3.87	0.921
	18.0	1.322	1.244	1.1469	1.3593	4.46	0.915
	20.0	1.506	1.405	1.1659	1.3626	5.09	0.910
	22.0	1.699	1.571	1.1856	1.3661	5.76	0.905
	24.0	1.902	1.744	1.2060	1.3696	6.46	0.901
	26.0	2.117	1.922	1.2270	1.3733	7.21	0.898
	28.0	2.343	2.106	1.2487	1.3771	8.01	0.895
	30.0	2.582	2.297	1.2712	1.3810	8.86	0.892
	32.0	2.835	2.495	1.2944	1.3851	9.76	0.891
	34.0	3.103	2.700	1.3185	1.3893	10.72	0.890
	36.0	3.388	2.913	1.3434	1.3936	11.73	0.890
	38.0	3.692	3.134	1.3692	1.3981	12.81	0.893
	40.0	4.016	3.364	1.3959	1.4027	13.97	0.897
Potassium	0.5	0.050	0.050	1.0014	1.3335	0.17	0.999
nitrate	1.0	0.100	0.099	1.0045	1.3339	0.33	0.996
KNO_3	2.0	0.202	0.200	1.0108	1.3349	0.64	0.990
	3.0	0.306	0.302	1.0171	1.3358	0.94	0.986
	4.0	0.412	0.405	1.0234	1.3368	1.22	0.983
	5.0	0.521	0.509	1.0298	1.3377	1.50	0.980
	6.0	0.631	0.615	1.0363	1.3386	1.76	0.977
	7.0	0.744	0.722	1.0428	1.3396	2.02	0.975
	8.0	0.860	0.830	1.0494	1.3405	2.27	0.973
	9.0	0.978	0.940	1.0560	1.3415	2.52	0.971
	10.0	1.099	1.051	1.0627	1.3425	2.75	0.970
	12.0	1.349	1.277	1.0762	1.3444		0.970
	14.0	1.610	1.509	1.0899	1.3463		0.972
	16.0	1.884	1.747	1.1039	1.3482		0.976
	18.0	2.171	1.991	1.1181	1.3502		0.982
	20.0	2.473	2.240	1.1326	1.3521		0.990
	22.0	2.790	2.497	1.1473	1.3541		0.999
	24.0	3.123	2.759	1.1623	1.3561		1.010
Potassium	0.5	0.032	0.032	1.0017		0.11	1.001
permanganate	1.0	0.064	0.064	1.0051		0.22	1.000
$KMnO_4$	1.5	0.096	0.096	1.0085		0.32	0.999
	2.0	0.129	0.128	1.0118		0.43	0.998
	3.0	0.196	0.193	1.0186			0.995
	4.0	0.264	0.260	1.0254			0.992

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	5.0	0.333	0.327	1.0322			0.989
	6.0	0.404	0.394	1.0390			0.985
Potassium	0.5	0.029	0.029	1.0025	1.3338	0.13	1.013
hydrogen	1.0	0.058	0.058	1.0068	1.3345	0.25	1.023
phosphate	1.5	0.087	0.087	1.0110	1.3353	0.37	1.034
K_2HPO_4	2.0	0.117	0.117	1.0153	1.3361	0.49	1.046
	2.5	0.147	0.146	1.0195	1.3368	0.61	1.057
	3.0	0.178	0.176	1.0238	1.3376	0.73	1.069
	3.5	0.208	0.207	1.0281	1.3384	0.86	1.081
	4.0	0.239	0.237	1.0324	1.3392	0.97	1.094
	4.5	0.271	0.268	1.0368	1.3399	1.10	1.107
	5.0	0.302	0.299	1.0412	1.3407	1.22	1.120
	6.0	0.366	0.362	1.0500	1.3422	1.46	1.147
	7.0	0.432	0.426	1.0590	1.3438	1.70	1.177
	8.0	0.499	0.491	1.0680	1.3453	1.95	1.209
Potassium	0.5	0.037	0.037	1.0018	1.3336	0.13	1.010
dihydrogen	1.0	0.074	0.074	1.0053	1.3342	0.25	1.019
phosphate	1.5	0.112	0.111	1.0089	1.3348	0.37	1.028
KH_2PO_4	2.0	0.150	0.149	1.0125	1.3354	0.49	1.038
	3.0	0.227	0.225	1.0197	1.3365	0.72	1.060
	4.0	0.306	0.302	1.0269	1.3377	0.96	1.083
	5.0	0.387	0.380	1.0342	1.3388	1.19	1.108
	6.0	0.469	0.459	1.0414	1.3400	1.41	1.133
	7.0	0.553	0.539	1.0486	1.3411	1.63	1.160
	8.0	0.639	0.621	1.0558	1.3422	1.84	1.187
	9.0	0.727	0.703	1.0630	1.3434	2.04	1.215
	10.0	0.816	0.786	1.0703	1.3445	2.23	1.245
Potassium	0.5	0.029	0.029	1.0022	1.3336	0.14	1.006
sulfate	1.0	0.058	0.058	1.0062	1.3343	0.26	1.011
K_2SO_4	2.0	0.117	0.116	1.0143	1.3355	0.50	1.021
	3.0	0.177	0.176	1.0224	1.3368	0.73	1.033
	4.0	0.239	0.237	1.0306	1.3380	0.95	1.045
	5.0	0.302	0.298	1.0388	1.3393	1.17	1.058
	6.0	0.366	0.360	1.0470	1.3405		1.072
	7.0	0.432	0.424	1.0553	1.3417		1.087
	8.0	0.499	0.488	1.0637	1.3428		1.102
	9.0	0.568	0.554	1.0721	1.3440		1.117
	10.0	0.638	0.620	1.0806	1.3452		1.132
1-Propanol	1.0	0.168	0.166	0.9963	1.3339	0.31	1.051
$CH_3CH_2CH_2OH$	2.0	0.340	0.331	0.9946	1.3348	0.61	1.100
	3.0	0.515	0.496	0.9928	1.3357	0.93	1.152
	4.0	0.693	0.660	0.9911	1.3366	1.24	1.208
	5.0	0.876	0.823	0.9896	1.3376	1.57	1.267
	6.0	1.062	0.987	0.9882	1.3385	1.91	1.325
	7.0	1.252	1.149	0.9868	1.3394	2.26	1.387
	8.0	1.447	1.312	0.9855	1.3404	2.61	1.449
	9.0	1.646	1.474	0.9842	1.3414	2.99	1.514
	10.0	1.849	1.635	0.9829	1.3423	3.36	1.577
	12.0	2.269	1.958	0.9804	1.3442	4.09	1.710
	14.0	2.709	2.278	0.9779	1.3460	4.91	1.849
	16.0	3.169	2.595	0.9749	1.3477	5.78	1.986
	18.0	3.652	2.911	0.9719	1.3494	6.67	2.106
	20.0	4.160	3.223	0.9686	1.3510	7.76	2.218
	24.0	5.254	3.838	0.9612	1.3539	9.12	2.432
	28.0	6.471	4.441	0.9533	1.3566	10.17	2.612
	32.0	7.830	5.033	0.9452	1.3592	10.66	2.765
	36.0	9.359	5.613	0.9370	1.3614		2.900

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	40.0	11.093	6.182	0.9288	1.3635		3.010
	60.0	24.958	8.860	0.8875	1.3734		3.186
	80.0	66.556	11.275	0.8470	1.3812		2.822
	100.0		13.368	0.8034	1.3852		2.227
2-Propanol	1.0	0.168	0.166	0.9960	1.3338	0.30	1.056
$CH_3CHOHCH_3$	2.0	0.340	0.331	0.9939	1.3346	0.60	1.112
	3.0	0.515	0.495	0.9920	1.3355	0.93	1.166
	4.0	0.693	0.659	0.9902	1.3364	1.26	1.225
	5.0	0.876	0.822	0.9884	1.3373	1.61	1.287
	6.0	1.062	0.985	0.9871	1.3382	1.96	1.352
	7.0	1.252	1.148	0.9855	1.3392	2.32	1.417
	8.0	1.447	1.310	0.9843	1.3400	2.68	1.485
	9.0	1.646	1.472	0.9831	1.3410	3.06	1.553
	10.0	1.849	1.633	0.9816	1.3420	3.48	1.629
	12.0	2.269	1.955	0.9793	1.3439	4.43	1.794
	14.0	2.709	2.276	0.9772	1.3459	5.29	1.970
	16.0	3.169	2.596	0.9751	1.3478	6.36	2.160
	18.0	3.652	2.913	0.9725	1.3496	7.40	2.352
	20.0	4.160	3.227	0.9696	1.3514	8.52	2.550
	40.0	11.093	6.191	0.9302	1.3642		
	60.0	24.958	8.809	0.8824	1.3717		
	80.0	66.556	11.103	0.8341	1.3742		
	100.0		13.058	0.7848	1.3776		
Silver	0.5	0.030	0.030	1.0027	1.3336	0.10	1.003
nitrate	1.0	0.059	0.059	1.0070	1.3342	0.20	1.005
$AgNO_3$	2.0	0.120	0.120	1.0154	1.3352	0.40	1.009
	3.0	0.182	0.181	1.0239	1.3363	0.59	1.013
	4.0	0.245	0.243	1.0327	1.3374	0.78	1.016
	5.0	0.310	0.307	1.0417	1.3385	0.96	1.020
	6.0	0.376	0.371	1.0506	1.3396	1.15	1.024
	7.0	0.443	0.437	1.0597	1.3407	1.33	1.027
	8.0	0.512	0.503	1.0690	1.3419	1.51	1.031
	9.0	0.582	0.571	1.0785	1.3431	1.69	1.035
	10.0	0.654	0.641	1.0882	1.3443	1.87	1.039
	12.0	0.803	0.783	1.1079	1.3467	2.21	1.049
	14.0	0.958	0.930	1.1284	1.3493	2.55	1.060
	16.0	1.121	1.083	1.1496	1.3519	2.86	1.072
	18.0	1.292	1.241	1.1715	1.3546		1.086
	20.0	1.472	1.406	1.1942	1.3574		1.101
	22.0	1.660	1.577	1.2177	1.3602		1.117
	24.0	1.859	1.755	1.2420	1.3632		1.135
	26.0	2.068	1.940	1.2672	1.3662		1.154
	28.0	2.289	2.132	1.2933	1.3694		1.176
	30.0	2.523	2.332	1.3204	1.3726		1.200
	32.0	2.770	2.541	1.3487	1.3760		1.227
	34.0	3.033	2.758	1.3780	1.3795		1.257
	36.0	3.311	2.985	1.4087	1.3832		1.290
	38.0	3.608	3.223	1.4407	1.3871		1.326
	40.0	3.925	3.472	1.4743	1.3911		1.366
Sodium	0.5	0.061	0.061	1.0008	1.3337	0.22	1.021
acetate	1.0	0.123	0.122	1.0034	1.3344	0.43	1.040
CH_3COONa	2.0	0.249	0.246	1.0085	1.3358	0.88	1.080
	3.0	0.377	0.371	1.0135	1.3372	1.34	1.124
	4.0	0.508	0.497	1.0184	1.3386	1.82	1.171
	5.0	0.642	0.624	1.0234	1.3400	2.32	1.222
	6.0	0.778	0.752	1.0283	1.3414	2.85	1.278
	7.0	0.918	0.882	1.0334	1.3428	3.40	1.337
	8.0	1.060	1.013	1.0386	1.3442	3.98	1.401

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	9.0	1.206	1.145	1.0440	1.3456	4.57	1.468
	10.0	1.354	1.279	1.0495	1.3470		1.539
	12.0	1.662	1.552	1.0607	1.3498		1.688
	14.0	1.984	1.829	1.0718	1.3526		1.855
	16.0	2.322	2.112	1.0830	1.3554		2.054
	18.0	2.676	2.400	1.0940	1.3583		2.284
	20.0	3.047	2.694	1.1050	1.3611		2.567
	22.0	3.438	2.993	1.1159	1.3639		2.948
	24.0	3.849	3.297	1.1268	1.3666		3.400
	26.0	4.283	3.606	1.1377	1.3693		3.877
	28.0	4.741	3.921	1.1488	1.3720		4.388
	30.0	5.224	4.243	1.1602	1.3748		4.940
Sodium	0.5	0.060	0.060	1.0018	1.3337	0.20	1.015
bicarbonate	1.0	0.120	0.120	1.0054	1.3344	0.40	1.028
$NaHCO_3$	1.5	0.181	0.180	1.0089	1.3351	0.59	1.042
	2.0	0.243	0.241	1.0125	1.3357	0.78	1.057
	2.5	0.305	0.302	1.0160	1.3364	0.98	1.071
	3.0	0.368	0.364	1.0196	1.3370	1.16	1.086
	3.5	0.432	0.426	1.0231	1.3377	1.35	1.102
	4.0	0.496	0.489	1.0266	1.3383	1.54	1.118
	4.5	0.561	0.552	1.0301	1.3390	1.72	1.134
	5.0	0.627	0.615	1.0337	1.3396	1.90	1.151
	5.5	0.693	0.679	1.0372	1.3403	2.08	1.168
	6.0	0.760	0.743	1.0408	1.3409	2.26	1.185
Sodium	0.5	0.049	0.049	1.0021	1.3337	0.17	1.004
bromide	1.0	0.098	0.098	1.0060	1.3344	0.34	1.007
NaBr	2.0	0.198	0.197	1.0139	1.3358	0.69	1.012
	3.0	0.301	0.298	1.0218	1.3372	1.04	1.017
	4.0	0.405	0.400	1.0298	1.3386	1.39	1.022
	5.0	0.512	0.504	1.0380	1.3401	1.76	1.028
	6.0	0.620	0.610	1.0462	1.3415	2.14	1.034
	7.0	0.732	0.717	1.0546	1.3430	2.53	1.040
	8.0	0.845	0.826	1.0630	1.3445	2.93	1.046
	9.0	0.961	0.937	1.0716	1.3460	3.34	1.053
	10.0	1.080	1.050	1.0803	1.3475	3.77	1.060
	12.0	1.325	1.281	1.0981	1.3506	4.67	1.077
	14.0	1.582	1.519	1.1164	1.3538	5.65	1.096
	16.0	1.851	1.765	1.1352	1.3570	6.74	1.119
	18.0	2.133	2.020	1.1546	1.3604		1.144
	20.0	2.430	2.283	1.1745	1.3638		1.174
	22.0	2.741	2.555	1.1951	1.3673		1.207
	24.0	3.069	2.837	1.2163	1.3708		1.244
	26.0	3.415	3.129	1.2382	1.3745		1.287
	28.0	3.780	3.431	1.2608	1.3783		1.336
	30.0	4.165	3.744	1.2842	1.3822		1.395
	32.0	4.574	4.069	1.3083	1.3862		1.465
	34.0	5.007	4.406	1.3333	1.3903		1.546
	36.0	5.467	4.755	1.3592	1.3946		1.639
	38.0	5.957	5.119	1.3860	1.3990		1.745
	40.0	6.479	5.496	1.4138	1.4035		1.866
Sodium	0.5	0.047	0.047	1.0034	1.3341	0.22	1.025
carbonate	1.0	0.095	0.095	1.0086	1.3352	0.43	1.049
Na_2CO_3	2.0	0.193	0.192	1.0190	1.3375	0.75	1.102
	3.0	0.292	0.291	1.0294	1.3397	1.08	1.159
	4.0	0.393	0.392	1.0398	1.3419	1.42	1.222
	5.0	0.497	0.495	1.0502	1.3440	1.77	1.292
	6.0	0.602	0.600	1.0606	1.3462	2.13	1.367
	7.0	0.710	0.707	1.0711	1.3483		1.448

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	8.0	0.820	0.816	1.0816	1.3504		1.538
	9.0	0.933	0.927	1.0922	1.3525		1.638
	10.0	1.048	1.041	1.1029	1.3547		1.754
	11.0	1.166	1.156	1.1136	1.3568		1.884
	12.0	1.287	1.273	1.1244	1.3589		2.028
	13.0	1.410	1.392	1.1353	1.3610		2.186
	14.0	1.536	1.514	1.1463	1.3631		2.361
	15.0	1.665	1.638	1.1574	1.3652		2.551
Sodium	0.5	0.086	0.086	1.0018	1.3339	0.30	1.011
chloride	1.0	0.173	0.172	1.0053	1.3347	0.59	1.020
NaCl	2.0	0.349	0.346	1.0125	1.3365	1.19	1.036
	3.0	0.529	0.523	1.0196	1.3383	1.79	1.052
	4.0	0.713	0.703	1.0268	1.3400	2.41	1.068
	5.0	0.901	0.885	1.0340	1.3418	3.05	1.085
	6.0	1.092	1.069	1.0413	1.3435	3.70	1.104
	7.0	1.288	1.256	1.0486	1.3453	4.38	1.124
	8.0	1.488	1.445	1.0559	1.3470	5.08	1.145
	9.0	1.692	1.637	1.0633	1.3488	5.81	1.168
	10.0	1.901	1.832	1.0707	1.3505	6.56	1.193
	12.0	2.333	2.229	1.0857	1.3541	8.18	1.250
	14.0	2.785	2.637	1.1008	1.3576	9.94	1.317
	16.0	3.259	3.056	1.1162	1.3612	11.89	1.388
	18.0	3.756	3.486	1.1319	1.3648	14.04	1.463
	20.0	4.278	3.928	1.1478	1.3684	16.46	1.557
	22.0	4.826	4.382	1.1640	1.3721	19.18	1.676
	24.0	5.403	4.847	1.1804	1.3757		1.821
	26.0	6.012	5.326	1.1972	1.3795		1.990
Sodium	1.0	0.039	0.039	1.0049	1.3348	0.20	1.043
citrate	2.0	0.079	0.078	1.0120	1.3366	0.39	1.081
$(HO)C(COONa)_3$	3.0	0.120	0.118	1.0186	1.3383	0.59	1.122
	4.0	0.161	0.159	1.0260	1.3401	0.79	1.166
	5.0	0.204	0.200	1.0331	1.3419	0.97	1.210
	6.0	0.247	0.242	1.0405	1.3437	1.17	1.263
	7.0	0.292	0.284	1.0482	1.3455	1.36	1.314
	8.0	0.337	0.327	1.0557	1.3473	1.57	1.371
	9.0	0.383	0.371	1.0632	1.3491	1.77	1.427
	10.0	0.431	0.415	1.0708	1.3509	1.96	1.499
	12.0	0.528	0.505	1.0861	1.3546	2.38	1.649
	14.0	0.631	0.598	1.1019	1.3583	2.82	1.832
	16.0	0.738	0.693	1.1173	1.3618	3.27	2.045
	18.0	0.851	0.790	1.1327	1.3656	3.82	2.290
	20.0	0.969	0.891	1.1492	1.3693	4.39	2.596
	24.0	1.224	1.099	1.1813	1.3767		3.409
	28.0	1.507	1.318	1.2151	1.3845		4.586
	32.0	1.823	1.548	1.2487	1.3923		6.541
	36.0	2.180	1.792	1.2843	1.4001		9.788
Sodium	0.5	0.126	0.125	1.0039	1.3344	0.43	1.027
hydroxide	1.0	0.253	0.252	1.0095	1.3358	0.86	1.054
NaOH	2.0	0.510	0.510	1.0207	1.3386	1.74	1.112
	3.0	0.773	0.774	1.0318	1.3414	2.64	1.176
	4.0	1.042	1.043	1.0428	1.3441	3.59	1.248
	5.0	1.316	1.317	1.0538	1.3467	4.57	1.329
	6.0	1.596	1.597	1.0648	1.3494	5.60	1.416
	7.0	1.882	1.883	1.0758	1.3520	6.69	1.510
	8.0	2.174	2.174	1.0869	1.3546	7.87	1.616
	9.0	2.473	2.470	1.0979	1.3572	9.12	1.737
	10.0	2.778	2.772	1.1089	1.3597	10.47	1.882
	12.0	3.409	3.393	1.1309	1.3648	13.42	2.201

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	14.0	4.070	4.036	1.1530	1.3697	16.76	2.568
	15.0	4.412	4.365	1.1640	1.3722		2.789
	16.0	4.762	4.701	1.1751	1.3746		3.043
	18.0	5.488	5.387	1.1971	1.3793		3.698
	20.0	6.250	6.096	1.2192	1.3840		4.619
	22.0	7.052	6.827	1.2412	1.3885		5.765
	24.0	7.895	7.579	1.2631	1.3929		7.100
	26.0	8.784	8.352	1.2848	1.3971		8.744
	28.0	9.723	9.145	1.3064	1.4012		10.832
	30.0	10.715	9.958	1.3277	1.4051		13.517
	32.0	11.766	10.791	1.3488	1.4088		16.844
	34.0	12.880	11.643	1.3697	1.4123		20.751
	36.0	14.064	12.512	1.3901	1.4156		25.290
	38.0	15.324	13.398	1.4102	1.4186		30.461
	40.0	16.668	14.300	1.4299	1.4215		36.312
Sodium	0.5	0.059	0.059	1.0016	1.3336	0.20	1.004
nitrate	1.0	0.119	0.118	1.0050	1.3341	0.40	1.007
$NaNO_3$	2.0	0.240	0.238	1.0117	1.3353	0.79	1.012
	3.0	0.364	0.359	1.0185	1.3364	1.18	1.018
	4.0	0.490	0.483	1.0254	1.3375	1.56	1.025
	5.0	0.619	0.607	1.0322	1.3387	1.94	1.032
	6.0	0.751	0.734	1.0392	1.3398	2.32	1.040
	7.0	0.886	0.862	1.0462	1.3409	2.70	1.049
	8.0	1.023	0.991	1.0532	1.3421	3.08	1.059
	9.0	1.164	1.123	1.0603	1.3432	3.46	1.069
	10.0	1.307	1.256	1.0674	1.3443	3.84	1.081
	12.0	1.604	1.527	1.0819	1.3466	4.60	1.107
	14.0	1.915	1.806	1.0967	1.3489	5.37	1.138
	18.0	2.583	2.387	1.1272	1.3536	6.98	1.215
	20.0	2.941	2.689	1.1429	1.3559	7.81	1.263
	30.0	5.042	4.326	1.2256	1.3678		1.609
	40.0	7.844	6.200	1.3175	1.3802		2.226
Sodium	0.5	0.031	0.031	1.0042	1.3343	0.19	1.033
phosphate	1.0	0.062	0.062	1.0100	1.3356	0.37	1.064
Na_3PO_4	1.5	0.093	0.093	1.0158	1.3369	0.53	1.094
	2.0	0.124	0.125	1.0216	1.3381	0.67	1.126
	2.5	0.156	0.157	1.0275	1.3394	0.79	1.161
	3.0	0.189	0.189	1.0335	1.3406		1.198
	3.5	0.221	0.222	1.0395	1.3419		1.238
	4.0	0.254	0.255	1.0456	1.3432		1.281
	4.5	0.287	0.289	1.0517	1.3444		1.327
	5.0	0.321	0.323	1.0579	1.3457		1.375
	5.5	0.355	0.357	1.0642	1.3470		1.426
	6.0	0.389	0.392	1.0705	1.3482		1.480
	6.5	0.424	0.427	1.0768	1.3495		1.538
	7.0	0.459	0.462	1.0832	1.3507		1.598
	7.5	0.495	0.498	1.0896	1.3519		1.662
	8.0	0.530	0.535	1.0961	1.3532		1.729
Sodium hydrogen	0.5	0.035	0.035	1.0032	1.3340	0.17	1.021
phosphate	1.0	0.071	0.071	1.0082	1.3349	0.32	1.042
Na_2HPO_4	1.5	0.107	0.107	1.0131	1.3358	0.46	1.064
	2.0	0.144	0.143	1.0180	1.3368		1.088
	2.5	0.181	0.180	1.0229	1.3377		1.113
	3.0	0.218	0.217	1.0279	1.3386		1.138
	3.5	0.255	0.255	1.0328	1.3396		1.165
	4.0	0.293	0.292	1.0378	1.3405		1.193
	4.5	0.332	0.331	1.0428	1.3414		1.223
	5.0	0.371	0.369	1.0478	1.3424		1.254

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	5.5	0.410	0.408	1.0528	1.3433		1.286
Sodium	0.5	0.042	0.042	1.0019	1.3336	0.14	1.018
dihydrogen	1.0	0.084	0.084	1.0056	1.3343	0.28	1.035
phosphate	1.5	0.127	0.126	1.0094	1.3349	0.42	1.051
NaH_2PO_4	2.0	0.170	0.169	1.0131	1.3356	0.56	1.068
	2.5	0.214	0.212	1.0168	1.3362	0.70	1.085
	3.0	0.258	0.255	1.0206	1.3369	0.84	1.103
	3.5	0.302	0.299	1.0244	1.3375	0.98	1.121
	4.0	0.347	0.343	1.0281	1.3382	1.12	1.140
	4.5	0.393	0.387	1.0319	1.3388	1.25	1.160
	5.0	0.439	0.432	1.0358	1.3395	1.39	1.180
	6.0	0.532	0.522	1.0434	1.3408	1.65	1.223
	7.0	0.627	0.613	1.0511	1.3421	1.89	1.270
	8.0	0.725	0.706	1.0589	1.3434	2.12	1.319
	9.0	0.824	0.800	1.0668	1.3447	2.35	1.371
	10.0	0.926	0.896	1.0747	1.3460	2.58	1.428
	12.0	1.137	1.091	1.0907	1.3486	3.06	1.552
	14.0	1.357	1.292	1.1070	1.3512	3.53	1.694
	16.0	1.588	1.499	1.1236	1.3538	4.03	1.861
	18.0	1.830	1.711	1.1404	1.3565	4.55	2.050
	20.0	2.084	1.930	1.1576	1.3592	5.10	2.283
	22.0	2.351	2.155	1.1752	1.3618		2.550
	24.0	2.632	2.387	1.1931	1.3646		2.850
	26.0	2.929	2.625	1.2113	1.3673		3.214
	28.0	3.242	2.870	1.2299	1.3700		3.682
	30.0	3.572	3.123	1.2488	1.3728		4.300
	32.0	3.923	3.383	1.2682	1.3756		5.079
	34.0	4.294	3.650	1.2879	1.3784		6.008
	36.0	4.689	3.925	1.3080	1.3812		7.098
	38.0	5.109	4.208	1.3285	1.3840		8.363
	40.0	5.557	4.499	1.3493	1.3869		9.814
Sodium	0.5	0.035	0.035	1.0027	1.3338	0.17	1.013
sulfate	1.0	0.071	0.071	1.0071	1.3345	0.32	1.026
Na_2SO_4	2.0	0.144	0.143	1.0161	1.3360	0.61	1.058
	3.0	0.218	0.217	1.0252	1.3376	0.87	1.091
	4.0	0.293	0.291	1.0343	1.3391	1.13	1.126
	5.0	0.371	0.367	1.0436	1.3406	1.36	1.163
	6.0	0.449	0.445	1.0526	1.3420	1.56	1.202
	7.0	0.530	0.523	1.0619	1.3435		1.244
	8.0	0.612	0.603	1.0713	1.3449		1.289
	9.0	0.696	0.685	1.0808	1.3464		1.337
	10.0	0.782	0.768	1.0905	1.3479		1.390
	12.0	0.960	0.938	1.1101	1.3509		1.508
	14.0	1.146	1.114	1.1301	1.3539		1.646
	16.0	1.341	1.296	1.1503	1.3567		1.812
	18.0	1.545	1.483	1.1705	1.3595		2.005
	20.0	1.760	1.677	1.1907	1.3620		2.227
	22.0	1.986	1.875	1.2106	1.3643		2.481
Sodium	0.5	0.032	0.032	1.0024	1.3340	0.14	1.012
thiosulfate	1.0	0.064	0.064	1.0065	1.3351	0.28	1.023
$Na_2S_2O_3$	2.0	0.129	0.128	1.0148	1.3371	0.57	1.044
	3.0	0.196	0.194	1.0231	1.3392	0.84	1.066
	4.0	0.264	0.261	1.0315	1.3413	1.09	1.090
	5.0	0.333	0.329	1.0399	1.3434	1.34	1.115
	6.0	0.404	0.398	1.0483	1.3454	1.59	1.141
	7.0	0.476	0.468	1.0568	1.3475	1.83	1.169
	8.0	0.550	0.539	1.0654	1.3496	2.06	1.199
	9.0	0.626	0.611	1.0740	1.3517	2.30	1.231

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	10.0	0.703	0.685	1.0827	1.3538	2.55	1.267
	12.0	0.862	0.835	1.1003	1.3581	3.06	1.345
	14.0	1.030	0.990	1.1182	1.3624	3.60	1.435
	16.0	1.205	1.150	1.1365	1.3667	4.17	1.537
	18.0	1.388	1.315	1.1551	1.3711	4.76	1.657
	20.0	1.581	1.485	1.1740	1.3756	5.37	1.798
	30.0	2.711	2.417	1.2739	1.3987		2.903
	40.0	4.216	3.498	1.3827	1.4229		5.758
Strontium	0.5	0.032	0.032	1.0027	1.3339	0.16	1.012
chloride	1.0	0.064	0.064	1.0071	1.3348	0.31	1.021
$SrCl_2$	2.0	0.129	0.128	1.0161	1.3366	0.62	1.039
	3.0	0.195	0.194	1.0252	1.3384	0.93	1.057
	4.0	0.263	0.261	1.0344	1.3402	1.26	1.076
	5.0	0.332	0.329	1.0437	1.3421	1.61	1.096
	6.0	0.403	0.399	1.0532	1.3440	1.98	1.116
	7.0	0.475	0.469	1.0628	1.3459	2.38	1.136
	8.0	0.549	0.541	1.0726	1.3478	2.80	1.157
	9.0	0.624	0.615	1.0825	1.3498	3.25	1.180
	10.0	0.701	0.689	1.0925	1.3518	3.74	1.204
	12.0	0.860	0.843	1.1131	1.3558	4.81	1.258
	14.0	1.027	1.002	1.1342	1.3599	6.03	1.317
	16.0	1.202	1.167	1.1558	1.3641	7.41	1.383
	18.0	1.385	1.338	1.1780	1.3684	8.98	1.460
	20.0	1.577	1.515	1.2008	1.3728	10.74	1.549
	22.0	1.779	1.699	1.2241	1.3772	12.74	1.650
	24.0	1.992	1.890	1.2481	1.3817	14.99	1.765
	26.0	2.216	2.087	1.2728	1.3864		1.897
	28.0	2.453	2.293	1.2983	1.3911		2.056
	30.0	2.703	2.507	1.3248	1.3961		2.245
	32.0	2.968	2.730	1.3523	1.4013		2.527
	34.0	3.250	2.962	1.3811	1.4067		2.846
	36.0	3.548	3.205	1.4114	1.4124		3.206
Sucrose	0.5	0.015	0.015	1.0002	1.3337	0.03	1.015
$C_{12}H_{22}O_{11}$	1.0	0.030	0.029	1.0021	1.3344	0.06	1.028
	2.0	0.060	0.059	1.0060	1.3359	0.11	1.055
	3.0	0.090	0.089	1.0099	1.3373	0.17	1.084
	4.0	0.122	0.118	1.0139	1.3388	0.23	1.114
	5.0	0.154	0.149	1.0178	1.3403	0.29	1.146
	6.0	0.186	0.179	1.0218	1.3418	0.35	1.179
	7.0	0.220	0.210	1.0259	1.3433	0.42	1.215
	8.0	0.254	0.241	1.0299	1.3448	0.49	1.254
	9.0	0.289	0.272	1.0340	1.3463	0.55	1.294
	10.0	0.325	0.303	1.0381	1.3478	0.63	1.336
	12.0	0.398	0.367	1.0465	1.3509	0.77	1.429
	14.0	0.476	0.431	1.0549	1.3541	0.93	1.534
	16.0	0.556	0.497	1.0635	1.3573	1.10	1.653
	18.0	0.641	0.564	1.0722	1.3606	1.27	1.790
	20.0	0.730	0.632	1.0810	1.3639	1.47	1.945
	22.0	0.824	0.700	1.0899	1.3672	1.67	2.124
	24.0	0.923	0.771	1.0990	1.3706	1.89	2.331
	26.0	1.026	0.842	1.1082	1.3741	2.12	2.573
	28.0	1.136	0.914	1.1175	1.3776	2.37	2.855
	30.0	1.252	0.988	1.1270	1.3812	2.64	3.187
	32.0	1.375	1.063	1.1366	1.3848	2.94	3.762
	34.0	1.505	1.139	1.1464	1.3885	3.27	4.052
	36.0	1.643	1.216	1.1562	1.3922	3.63	4.621
	38.0	1.791	1.295	1.1663	1.3960	4.02	5.315
	40.0	1.948	1.375	1.1765	1.3999	4.45	6.162
	42.0	2.116	1.456	1.1868	1.4038	4.93	7.234

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	44.0	2.295	1.539	1.1972	1.4078		8.596
	46.0	2.489	1.623	1.2079	1.4118		10.301
	48.0	2.697	1.709	1.2186	1.4159		12.515
	50.0	2.921	1.796	1.2295	1.4201		15.431
	60.0	4.382	2.255	1.2864	1.4419		58.487
	70.0	6.817	2.755	1.3472	1.4654		481.561
	80.0	11.686	3.299	1.4117	1.4906		
Sulfuric acid	0.5	0.051	0.051	1.0016	1.3336	0.21	1.010
H_2SO_4	1.0	0.103	0.102	1.0049	1.3342	0.42	1.019
	2.0	0.208	0.206	1.0116	1.3355	0.80	1.036
	3.0	0.315	0.311	1.0183	1.3367	1.17	1.059
	4.0	0.425	0.418	1.0250	1.3379	1.60	1.085
	5.0	0.537	0.526	1.0318	1.3391	2.05	1.112
	6.0	0.651	0.635	1.0385	1.3403	2.50	1.136
	7.0	0.767	0.746	1.0453	1.3415	2.95	1.159
	8.0	0.887	0.858	1.0522	1.3427	3.49	1.182
	9.0	1.008	0.972	1.0591	1.3439	4.08	1.206
	10.0	1.133	1.087	1.0661	1.3451	4.64	1.230
	12.0	1.390	1.322	1.0802	1.3475	5.93	1.282
	14.0	1.660	1.563	1.0947	1.3500	7.49	1.337
	16.0	1.942	1.810	1.1094	1.3525	9.26	1.399
	18.0	2.238	2.064	1.1245	1.3551	11.29	1.470
	20.0	2.549	2.324	1.1398	1.3576	13.64	1.546
	22.0	2.876	2.592	1.1554	1.3602	16.48	1.624
	24.0	3.220	2.866	1.1714	1.3628	19.85	1.706
	26.0	3.582	3.147	1.1872	1.3653	24.29	1.797
	28.0	3.965	3.435	1.2031	1.3677	29.65	1.894
	30.0	4.370	3.729	1.2191	1.3701	36.21	2.001
	32.0	4.798	4.030	1.2353	1.3725	44.76	2.122
	34.0	5.252	4.339	1.2518	1.3749	55.28	2.255
	36.0	5.735	4.656	1.2685	1.3773		2.392
	38.0	6.249	4.981	1.2855	1.3797		2.533
	40.0	6.797	5.313	1.3028	1.3821		2.690
	42.0	7.383	5.655	1.3205	1.3846		2.872
	44.0	8.011	6.005	1.3386	1.3870		3.073
	46.0	8.685	6.364	1.3570	1.3895		3.299
	48.0	9.411	6.734	1.3759	1.3920		3.546
	50.0	10.196	7.113	1.3952	1.3945		3.826
	52.0	11.045	7.502	1.4149	1.3971		4.142
	54.0	11.969	7.901	1.4351	1.3997		4.499
	56.0	12.976	8.312	1.4558	1.4024		4.906
	58.0	14.080	8.734	1.4770	1.4050		5.354
	60.0	15.294	9.168	1.4987	1.4077		5.917
	70.0	23.790	11.494	1.6105			
	80.0	40.783	14.088	1.7272			
	90.0	91.762	16.649	1.8144			
	92.0	117.251	17.109	1.8240			
	94.0	159.734	17.550	1.8312			
	96.0	244.698	17.966	1.8355			
	98.0	499.592	18.346	1.8361			
	100.0		18.663	1.8305			
Trichloroacetic	0.5	0.031	0.031	1.0008	1.3337	0.11	1.011
acid	1.0	0.062	0.061	1.0034	1.3343	0.21	1.021
CCl_3COOH	2.0	0.125	0.123	1.0083	1.3356	0.42	1.044
	3.0	0.189	0.186	1.0133	1.3369	0.64	1.069
	4.0	0.255	0.249	1.0182	1.3381	0.86	1.096
	5.0	0.322	0.313	1.0230	1.3394	1.08	1.123
	6.0	0.391	0.377	1.0279	1.3406	1.30	1.150
	7.0	0.461	0.442	1.0328	1.3418	1.53	1.177

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	8.0	0.532	0.508	1.0378	1.3431	1.76	1.204
	9.0	0.605	0.574	1.0428	1.3444	1.99	1.233
	10.0	0.680	0.641	1.0479	1.3456	2.23	1.263
	12.0	0.835	0.777	1.0583	1.3483	2.73	1.326
	14.0	0.996	0.916	1.0692	1.3510	3.26	1.393
	16.0	1.166	1.058	1.0806	1.3539	3.82	1.462
	18.0	1.343	1.203	1.0921	1.3568		1.533
	20.0	1.530	1.351	1.1035	1.3597		1.608
	24.0	1.933	1.654	1.1260	1.3652		1.768
	28.0	2.380	1.968	1.1485	1.3705		1.935
	32.0	2.880	2.294	1.1713	1.3759		2.118
	36.0	3.443	2.632	1.1947	1.3813		2.320
	40.0	4.080	2.984	1.2188	1.3868		1.543
	44.0	4.809	3.349	1.2435	1.3923		2.797
	48.0	5.650	3.726	1.2682	1.3977		3.076
Tris	0.5	0.041	0.041	0.9994	1.3337	0.08	1.014
(hydroxymethyl)-	1.0	0.083	0.083	1.0006	1.3344	0.16	1.027
methylamine	2.0	0.168	0.166	1.0030	1.3359	0.31	1.054
$H_2NC(CH_2OH)_3$	3.0	0.255	0.249	1.0054	1.3374	0.47	1.083
	4.0	0.344	0.333	1.0078	1.3388	0.64	1.115
	5.0	0.434	0.417	1.0103	1.3403	0.80	1.148
	6.0	0.527	0.502	1.0128	1.3418	0.97	1.182
	7.0	0.621	0.587	1.0153	1.3433	1.15	1.218
	8.0	0.718	0.672	1.0179	1.3448	1.33	1.256
	9.0	0.816	0.758	1.0204	1.3463	1.51	1.295
	10.0	0.917	0.844	1.0230	1.3478	1.70	1.337
	12.0	1.126	1.019	1.0282	1.3508	2.08	1.427
	14.0	1.344	1.194	1.0335	1.3539	2.47	1.527
	16.0	1.572	1.372	1.0389	1.3570	2.90	1.642
	18.0	1.812	1.552	1.0443	1.3601	3.36	1.772
	20.0	2.064	1.733	1.0498	1.3633	3.85	1.920
	30.0	3.538	2.670	1.0781	1.3797		2.998
	40.0	5.503	3.657	1.1076	1.3970		5.208
Urea	0.5	0.084	0.083	0.9995	1.3337	0.16	1.007
$(NH_2)_2CO$	1.0	0.168	0.167	1.0007	1.3344	0.31	1.010
	2.0	0.340	0.334	1.0033	1.3358	0.62	1.012
	3.0	0.515	0.502	1.0058	1.3372	0.93	1.017
	4.0	0.694	0.672	1.0085	1.3387	1.24	1.025
	5.0	0.876	0.842	1.0111	1.3401	1.55	1.033
	6.0	1.063	1.013	1.0138	1.3416	1.88	1.041
	7.0	1.253	1.185	1.0165	1.3431	2.22	1.049
	8.0	1.448	1.358	1.0192	1.3446	2.56	1.057
	9.0	1.647	1.531	1.0220	1.3461	2.91	1.065
	10.0	1.850	1.706	1.0248	1.3476	3.26	1.074
	12.0	2.270	2.059	1.0304	1.3506	3.95	1.091
	14.0	2.710	2.415	1.0360	1.3537	4.66	1.109
	16.0	3.171	2.775	1.0417	1.3568	5.40	1.130
	18.0	3.655	3.139	1.0473	1.3599	6.19	1.153
	20.0	4.163	3.506	1.0530	1.3629	7.00	1.178
	22.0	4.696	3.878	1.0586	1.3661	7.81	1.205
	24.0	5.258	4.253	1.0643	1.3692	8.64	1.235
	26.0	5.850	4.632	1.0699	1.3723	9.52	1.266
	28.0	6.475	5.014	1.0756	1.3754	10.45	1.298
	30.0	7.136	5.401	1.0812	1.3785	11.40	1.332
	32.0	7.835	5.791	1.0869	1.3817	12.34	1.371
	34.0	8.577	6.185	1.0926	1.3848	13.27	1.413
	36.0	9.366	6.584	1.0984	1.3881	14.20	1.459
	38.0	10.205	6.988	1.1044	1.3913	15.11	1.509
	40.0	11.100	7.397	1.1106	1.3947	15.99	1.565

Solute	Mass %	m/mol kg^{-1}	c/mol L^{-1}	ρ/g cm^{-3}	n	Δ/°C	η/mPa s
	42.0	12.057	7.812	1.1171	1.3982	16.83	1.629
	44.0	13.082	8.234	1.1239	1.4018	17.62	1.700
	46.0	14.183	8.665	1.1313	1.4056		1.780
Zinc sulfate	0.5	0.031	0.031	1.0034	1.3339	0.08	1.021
$ZnSO_4$	1.0	0.063	0.062	1.0085	1.3348	0.15	1.040
	2.0	0.126	0.126	1.0190	1.3366	0.28	1.081
	3.0	0.192	0.191	1.0296	1.3384	0.41	1.126
	4.0	0.258	0.258	1.0403	1.3403	0.53	1.175
	5.0	0.326	0.326	1.0511	1.3421	0.65	1.227
	6.0	0.395	0.395	1.0620	1.3439	0.77	1.283
	7.0	0.466	0.465	1.0730	1.3457	0.89	1.341
	8.0	0.539	0.537	1.0842	1.3475	1.01	1.403
	9.0	0.613	0.611	1.0956	1.3494	1.14	1.470
	10.0	0.688	0.686	1.1071	1.3513	1.27	1.545
	12.0	0.845	0.840	1.1308	1.3551	1.55	1.716
	14.0	1.008	1.002	1.1553	1.3590	1.89	1.918
	16.0	1.180	1.170	1.1806	1.3630	2.31	2.152

ION PRODUCT OF WATER SUBSTANCE

William L. Marshall and E. U. Franck

Pressure (bars)	Temperature (°C)								
	0	**25**	**50**	**75**	**100**	**150**	**200**	**250**	**300**
Saturated vapor	14.938	13.995	13.275	12.712	12.265	11.638	11.289	11.191	11.406
250	14.83	13.90	13.19	12.63	12.18	11.54	11.16	11.01	11.14
500	14.72	13.82	13.11	12.55	12.10	11.45	11.05	10.85	10.86
750	14.62	13.73	13.04	12.48	12.03	11.36	10.95	10.72	10.66
1,000	14.53	13.66	12.96	12.41	11.96	11.29	10.86	10.60	10.50
1,500	14.34	13.53	12.85	12.29	11.84	11.16	10.71	10.43	10.26
2,000	14.21	13.40	12.73	12.18	11.72	11.04	10.57	10.27	10.08
2,500	14.08	13.28	12.62	12.07	11.61	10.92	10.45	10.12	9.91
3,000	13.97	13.18	12.53	11.98	11.53	10.83	10.34	9.99	9.76
3,500	13.87	13.09	12.44	11.90	11.44	10.74	10.24	9.88	9.63
4,000	13.77	13.00	12.35	11.82	11.37	10.66	10.16	9.79	9.52
5,000	13.60	12.83	12.19	11.66	11.22	10.52	10.00	9.62	9.34
6,000	13.44	12.68	12.05	11.53	11.09	10.39	9.87	9.48	9.18
7,000	13.31	12.55	11.93	11.41	10.97	10.27	9.75	9.35	9.04
8,000	13.18	12.43	11.82	11.30	10.86	10.17	9.64	9.24	8.93
9,000	13.04	12.31	11.71	11.20	10.77	10.07	9.54	9.13	8.82
10,000	12.91	12.21	11.62	11.11	10.68	9.98	9.45	9.04	8.71

Pressure (bars)	Temperature (°C)								
	350	**400**	**450**	**500**	**600**	**700**	**800**	**900**	**1000**
Saturated vapor	12.30	—	—	—	—	—	—	—	—
250	11.77	19.43	21.59	22.40	23.27	23.81	24.23	24.59	24.93
500	11.14	11.88	13.74	16.13	18.30	19.29	19.92	20.39	20.80
750	10.79	11.17	11.89	13.01	15.25	16.55	17.35	17.93	18.39
1,000	10.54	10.77	11.19	11.81	13.40	14.70	15.58	16.22	16.72
1,500	10.22	10.29	10.48	10.77	11.59	12.50	13.30	13.97	14.50
2,000	9.98	9.98	10.07	10.23	10.73	11.36	11.98	12.54	12.97
2,500	9.79	9.74	9.77	9.86	10.18	10.63	11.11	11.59	12.02
3,000	9.61	9.54	9.53	9.57	9.78	10.11	10.49	10.89	11.24
3,500	9.47	9.37	9.33	9.34	9.48	9.71	10.02	10.35	10.62
4,000	9.34	9.22	9.16	9.15	9.23	9.41	9.65	9.93	10.13
5,000	9.13	8.99	8.90	8.85	8.85	8.95	9.11	9.30	9.42
6,000	8.96	8.80	8.69	8.62	8.57	8.61	8.72	8.86	8.97
7,000	8.81	8.64	8.51	8.42	8.34	8.34	8.40	8.51	8.64
8,000	8.68	8.50	8.36	8.25	8.13	8.10	8.13	8.21	8.38
9,000	8.57	8.37	8.22	8.10	7.95	7.89	7.89	7.95	8.12
10,000	8.46	8.25	8.09	7.96	7.78	7.70	7.68	7.70	7.85

Data in this table were calculated from the equation, $\log_{10} K_w^* = A + B/T + C/T^2 + D/T^3 + (E + F/T + G/T^2) \log_{10} \rho_w^*$, where $K_w^* = K_w/(\text{mol kg}^{-1})$, and $\rho_w^* = \rho_w/(\text{g cm}^{-3})$. The parameters are:

A = −4.098
B = −3245.2 K
C = $+2.2362 \times 10^5$ K^2
D = -3.984×10^7 K^3
E = +13.957
F = 1262.3 K
G = $+8.5641 \times 10^5$ K^2

Reprinted with permission from W. L. Marshall and E. U. Franck, *J. Phys. Chem. Ref. Data*, 10, 295, 1981.

IONIZATION CONSTANT OF NORMAL AND HEAVY WATER

This table gives the ionization constant in molality terms for H_2O and D_2O at temperatures from 0 to 100°C at the saturated vapor pressure. The quantity tabulated is $-\log K_W$, where K_W is defined by

$$K_W = m_+ \times m_-$$

and m_+ and m_- are the molalities, in mol/kg of water, for H^+ and OH^-, respectively.

References

1. Marshall W. L., and Franck, E. U., *J. Phys. Chem. Ref. Data*, 10, 295, 1981.
2. Mesmer R. E., and Herting, D. L., *J. Solution Chem.*, 7, 901, 1978.

	$-\log K_W$	
t/°C	H_2O	D_2O
0	14.938	15.972
5	14.727	15.743
10	14.528	15.527
15	14.340	15.324
20	14.163	15.132
25	13.995	14.951
30	13.836	14.779
35	13.685	14.616
40	13.542	14.462
45	13.405	14.316
50	13.275	14.176
55	13.152	14.044
60	13.034	13.918
65	12.921	13.798
70	12.814	13.683
75	12.712	13.574
80	12.613	13.470
85	12.520	13.371
90	12.428	13.276
95	12.345	13.186
100	12.265	13.099

SOLUBILITY OF SELECTED GASES IN WATER

L. H. Gevantman

The values in this table are taken almost exclusively from the International Union of Pure and Applied Chemistry "Solubility Data Series". Unless noted, they comprise evaluated data fitted to a smoothing equation. The data at each temperature are then derived from the smoothing equation which expresses the mole fraction solubility X_1 of the gas in solution as:

$$\ln X_1 = A + B/T^* + C \ln T^*$$

where

$$T^* = T/100\ \text{K}$$

All values refer to a partial pressure of the gas of 101.325 kPa (one atmosphere).

The equation constants, the standard deviation for $\ln X_1$ (except where noted), and the temperature range over which the equation applies are given in the column headed Equation constants. There are two exceptions. The equation for methane has an added term, DT^*. The equation for H_2Se and H_2S takes the form,

$$\ln X_1 = A + B/T + C \ln T + DT$$

where T is the temperature in kelvin.

Solubilities given for those gases which react with water, namely ozone, nitrogen oxides, chlorine and its oxides, carbon dioxide, hydrogen sulfide, hydrogen selenide and sulfur dioxide, are recorded as bulk solubilities; i.e., all chemical species of the gas and its reaction products with water are included.

Gas	T/K	Solubility (X_1)	Equation constants	Ref.
Hydrogen (H_2)	288.15	1.510×10^{-5}	$A = -48.1611$	1
$M_r = 2.01588$	293.15	1.455×10^{-5}	$B = 55.2845$	
	298.15	1.411×10^{-5}	$C = 16.8893$	
	303.15	1.377×10^{-5}	Std. dev. = ± 0.54%	
	308.15	1.350×10^{-5}	Temp. range = 273.15—353.15	
Deuterium (D_2)	283.15	1.675×10^{-5} ± 0.57%	Averaged experimental values	1
$M_r = 4.0282$	288.15	1.595×10^{-5} ± 0.57%		
	293.15	1.512×10^{-5} ± 0.78%	Temp. range = 278.15—303.15	
	298.15	1.460×10^{-5} ± 0.52%		
	303.15	1.395×10^{-5} ± 0.37%		
Helium (He)	288.15	7.123×10^{-6}	$A = -41.4611$	2
$A_r = 4.0026$	293.15	7.044×10^{-6}	$B = 42.5962$	
	298.15	6.997×10^{-6}	$C = 14.0094$	
	303.15	6.978×10^{-6}	Std. dev. = ±0.54%	
	308.15	6.987×10^{-6}	Temp. range = 273.15—348.15	
Neon (Ne)	288.15	8.702×10^{-6}	$A = -52.8573$	2
$A_r = 20.1797$	293.15	8.395×10^{-6}	$B = 61.0494$	
	298.15	8.152×10^{-6}	$C = 18.9157$	
	303.15	7.966×10^{-6}	Std. dev. = ±0.47%	
	308.15	7.829×10^{-6}	Temp. range = 273.15—348.15	
Argon (Ar)	288.15	3.025×10^{-5}	$A = -57.6661$	3
$A_r = 39.948$	293.15	2.748×10^{-5}	$B = 74.7627$	
	298.15	2.519×10^{-5}	$C = 20.1398$	
	303.15	2.328×10^{-5}	Std. dev. = ±0.26%	
	308.15	2.169×10^{-5}	Temp. range = 273.15—348.15	
Krypton (Kr)	288.15	5.696×10^{-5}	$A = -66.9928$	4
$A_r = 83.80$	293.15	5.041×10^{-5}	$B = 91.0166$	
	298.15	4.512×10^{-5}	$C = 24.2207$	
	303.15	4.079×10^{-5}	Std. dev. = ±0.32%	
	308.15	3.725×10^{-5}	Temp. range = 273.15—353.15	
Xenon (Xe)	288.15	10.519×10^{-5}	$A = -74.7398$	4
$A_r = 131.29$	293.15	9.051×10^{-5}	$B = 105.210$	
	298.15	7.890×10^{-5}	$C = 27.4664$	
	303.15	6.961×10^{-5}	Std. dev. = ±0.35%	
	308.15	6.212×10^{-5}	Temp. range = 273.15—348.15	

Gas	T/K	Solubility (X_1)	Equation constants	Ref.
Radon-222(^{222}Rn)	288.15	2.299×10^{-4}	$A = -90.5481$	
$A_r = 222$	293.15	1.945×10^{-4}	$B = 130.026$	
	298.15	1.671×10^{-4}	$C = 35.0047$	
	303.15	1.457×10^{-4}	Std. dev. = ±1.02%	
	308.15	1.288×10^{-4}	Temp. range = 273.15—373.15	
Oxygen (O_2)	288.15	2.756×10^{-5}	$A = -66.7354$	5
$M_r = 31.9988$	293.15	2.501×10^{-5}	$B = 87.4755$	
	298.15	2.293×10^{-5}	$C = 24.4526$	
	303.15	2.122×10^{-5}	Std. dev. = ±0.36%	
	308.15	1.982×10^{-5}	Temp. range = 273.15—348.15	
Ozone (O_3)	293.15	1.885×10^{-6} ± 10%	Experimental value derived	5
$M_r = 47.9982$		pH = 7.0	from Henry's Law Constant Equation	
Nitrogen (N_2)	288.15	1.386×10^{-5}	$A = -67.3877$	6
$M_r = 28.0134$	293.15	1.274×10^{-5}	$B = 86.3213$	
	298.15	1.183×10^{-5}	$C = 24.7981$	
	303.15	1.108×10^{-5}	Std. dev. = ±0.72%	
	308.15	1.047×10^{-5}	Temp. range = 273.15—348.15	
Nitrous oxide (N_2O)	288.15	5.948×10^{-4}	$A = -60.7467$	7
$M_r = 44.0129$	293.15	5.068×10^{-4}	$B = 88.8280$	
	298.15	4.367×10^{-4}	$C = 21.2531$	
	303.15	3.805×10^{-4}	Std. dev. = ±1.2%	
	308.15	3.348×10^{-4}	Temp. range = 273.15—313.15	
Nitric oxide (NO)	288.15	4.163×10^{-5}	$A = -62.8086$	7
$M_r = 30.0061$	293.15	3.786×10^{-5}	$B = 82.3420$	
	298.15	3.477×10^{-5}	$C = 22.8155$	
	303.15	3.222×10^{-5}	Std. dev. = ±0.76%	
	308.15	3.012×10^{-5}	Temp. range = 273.15—358.15	
Carbon monoxide (CO)	288.15	2.095×10^{-5}	Derived from Henry's	8
$M_r = 28.0104$	293.15	1.918×10^{-5}	Law Constant Equation	
	298.15	1.774×10^{-5}	Std. dev. = ±0.043%	
	303.15	1.657×10^{-5}	Temp. range = 273.15—328.15	
	308.15	1.562×10^{-5}		
Carbon dioxide (CO_2)	288.15	8.21×10^{-4}	Derived from Henry's	9
$M_r = 44.0098$	293.15	7.07×10^{-4}	Law Constant Equation	
	298.15	6.15×10^{-4}	Std. dev. = ±1.1%	
	303.15	5.41×10^{-4}	Temp. range = 273.15—353.15	
	308.15	4.80×10^{-4}		
Hydrogen selenide (H_2Se)	288.15	1.80×10^{-3}	$A = 9.15$	10
$M_r = 80.976$	298.15	1.49×10^{-3}	$B = 974$	
	308.15	1.24×10^{-3}	$C = -3.542$	
			$D = 0.0042$	
			Std. dev. = $\pm 2.3 \times 10^{-5}$	
			Temp. range = 288.15—343.15	
Hydrogen sulfide (H_2S)	288.15	2.335×10^{-3}	$A = -24.912$	10
$M_r = 34.082$	293.15	2.075×10^{-3}	$B = 3477$	
	298.15	1.85×10^{-3}	$C = 0.3993$	
	303.15	1.66×10^{-3}	$D = 0.0157$	
	308.15	1.51×10^{-3}	Std. dev. = $\pm 6.5 \times 10^{-5}$	
			Temp. range = 283.15—603.15	
Sulfur dioxide (SO_2)	288.15	3.45×10^{-2}	$A = -25.2629$	11
$M_r = 64.0648$	293.15	2.90×10^{-2}	$B = 45.7552$	

Gas	T/K	Solubility (X_1)	Equation constants	Ref.
	298.15	2.46×10^{-2}	C = 5.6855	
	303.15	2.10×10^{-2}	Std. dev. = ±1.8%	
	308.15	1.80×10^{-2}	Temp. range = 278.15—328.15	
Chlorine (Cl_2)	283.15	2.48×10^{-3} ± 2%	Experimental data	11
M_r = 70.9054	293.15	1.88×10^{-3} ± 2%	Temp. range = 283.15—333.15	
	303.15	1.50×10^{-3} ± 2%		
	313.15	1.23×10^{-3} ± 2%		
Chlorine monoxide (Cl_2O)	273.15	5.25×10^{-1} ± 1%	Experimental data	11
M_r = 86.9048	276.61	4.54×10^{-1} ± 1%	Temp. range = 273.15—293.15	
	283.15	4.273×10^{-1} ± 1%		
	293.15	3.353×10^{-1} ± 1%		
Chlorine dioxide (ClO_2)	288.15	2.67×10^{-2}	A = 7.9163	11
M_r = 67.4515	293.15	2.20×10^{-2}	B = 0.4791	
	298.15	1.823×10^{-2}	C = 11.0593	
	303.15	1.513×10^{-2}	Std. dev. = ±4.6%	
	308.15	1.259×10^{-2}	Temp. range = 283.15—333.15	
Methane (CH_4)	288.15	3.122×10^{-5}	A = −115.6477	12
M_r = 16.0428	293.15	2.806×10^{-5}	B = 155.5756	
	298.15	2.552×10^{-5}	C = 65.2553	
	303.15	2.346×10^{-5}	D = −6.1698	
	308.15	2.180×10^{-5}	Std. dev. = ±0.056%	
			Temp. range = 273.15—328.15	
Ethane (C_2H_6)	288.15	4.556×10^{-5}	A = −90.8225	13
M_r = 30.0696	293.15	3.907×10^{-5}	B = 126.9559	
	298.15	3.401×10^{-5}	C = 34.7413	
	303.15	3.002×10^{-5}	Std. dev. = ±0.13%	
	308.15	2.686×10^{-5}	Temp. range = 273.15—323.15	
Propane (C_3H_8)	288.15	3.813×10^{-5}	A = −102.044	14
M_r = 44.097	293.15	3.200×10^{-5}	B = 144.345	
	298.15	2.732×10^{-5}	C = 39.4740	
	303.15	2.370×10^{-5}	Std. dev. = ±0.012%	
	308.15	2.088×10^{-5}	Temp. range = 273.15—347.15	
Butane (C_4H_{10})	288.15	3.274×10^{-5}	A = −102.029	14
M_r = 58.123	293.15	2.687×10^{-5}	B = 146.040	
	298.15	2.244×10^{-5}	C = 38.7599	
	303.15	1.906×10^{-5}	Std. dev. = ±0.026%	
	308.15	1.645×10^{-5}	Temp. range = 273.15—349.15	
2-Methyl propane (Isobutane) (C_4H_{10})	288.15	2.333×10^{-5}	A = −129.714	14
M_r = 58.123	293.15	1.947×10^{-5}	B = 183.044	
	298.15	1.659×10^{-5}	C = 53.4651	
	303.15	1.443×10^{-5}	Std. dev. = ±0.034%	
	308.15	1.278×10^{-5}	Temp. range = 278.15—318.15	

References

1. C. L. Young, Ed., *IUPAC Solubility Data Series*, Vol. 5/6, Hydrogen and Deuterium, Pergamon Press, Oxford, England, 1981.
2. H. L. Clever, Ed., *IUPAC Solubility Data Series*, Vol. 1, Helium and Neon, Pergamon Press, Oxford, England, 1979.
3. H. L. Clever, Ed., *IUPAC Solubility Data Series*, Vol. 4, Argon, Pergamon Press, Oxford, England, 1980.
4. H. L. Clever, Ed., *IUPAC Solubility Data Series*, Vol. 2, Krypton, Xenon and Radon, Pergamon Press, Oxford, England, 1979.
5. R. Battino, Ed., *IUPAC Solubility Data Series*, Vol. 7, Oxygen and Ozone, Pergamon Press, Oxford, England, 1981.
6. R. Battino, Ed., *IUPAC Solubility Data Series*, Vol. 10, Nitrogen and Air, Pergamon Press, Oxford, England, 1982.
7. C. L. Young, Ed., *IUPAC Solubility Data Series*, Vol. 8, Oxides of Nitrogen, Pergamon Press, Oxford, England, 1981.
8. R. W. Cargill, Ed., *IUPAC Solubility Data Series*, Vol. 43, Carbon Monoxide, Pergamon Press, Oxford, England, 1990.
9. R. Crovetto, Evaluation of Solubility Data for the System CO2-H2O, *J. Phys. Chem. Ref. Data*, 20, 575, 1991.

10. P. G. T. Fogg and C. L. Young, Eds., *IUPAC Solubility Data Series*, Vol. 32, Hydrogen Sulfide, Deuterium Sulfide, and Hydrogen Selenide, Pergamon Press, Oxford, England, 1988.
11. C. L. Young, Ed., *IUPAC Solubility Data Series*, Vol. 12, Sulfur Dioxide, Chlorine, Fluorine and Chlorine Oxides, Pergamon Press, Oxford, England, 1983.
12. H. L. Clever and C. L. Young, Eds., *IUPAC Solubility Data Series*, Vol. 27/28, Methane, Pergamon Press, Oxford, England, 1987.
13. W. Hayduk, Ed., *IUPAC Solubility Data Series*, Vol. 9, Ethane, Pergamon Press, Oxford, England, 1982.
14. W. Hayduk, Ed., *IUPAC Solubility Data Series*, Vol. 24, Propane, Butane and 2-Methylpropane, Pergamon Press, Oxford, England, 1986.

SOLUBILITY OF CARBON DIOXIDE IN WATER AT VARIOUS TEMPERATURES AND PRESSURES

The solubility of CO_2 in water, expressed as mole fraction of CO_2 in the liquid phase, is given for pressures up to atmospheric and temperatures of 0 to 100°C. Note that 1 standard atmosphere equals 101.325 kPa. The references give data over a wider range of temperature and pressure. The estimated accuracy is about 2%.

References

1. Carroll, J. J., Slupsky, J. D., and Mather, A. E., *J. Phys. Chem. Ref. Data*, 20, 1201, 1991.
2. Fernandez-Prini, R. and Crovetto, R., *J. Phys. Chem. Ref. Data*, 18, 1231, 1989.
3. Crovetto, R., *J. Phys. Chem. Ref. Data*, 20, 575,1991.

	1000 × mole fraction of CO_2 in liquid phase						
	Partial pressure of CO_2 in kPa						
***t*/°C**	**5**	**10**	**20**	**30**	**40**	**50**	**100**
0	0.067	0.135	0.269	0.404	0.538	0.671	1.337
5	0.056	0.113	0.226	0.338	0.451	0.564	1.123
10	0.048	0.096	0.191	0.287	0.382	0.477	0.950
15	0.041	0.082	0.164	0.245	0.327	0.409	0.814
20	0.035	0.071	0.141	0.212	0.283	0.353	0.704
25	0.031	0.062	0.123	0.185	0.247	0.308	0.614
30	0.027	0.054	0.109	0.163	0.218	0.271	0.541
35	0.024	0.048	0.097	0.145	0.193	0.242	0.481
40	0.022	0.043	0.087	0.130	0.173	0.216	0.431
45	0.020	0.039	0.078	0.117	0.156	0.196	0.389
50	0.018	0.036	0.071	0.107	0.142	0.178	0.354
55	0.016	0.033	0.065	0.098	0.131	0.163	0.325
60	0.015	0.030	0.060	0.090	0.121	0.150	0.300
65	0.014	0.028	0.056	0.084	0.112	0.140	0.279
70	0.013	0.026	0.052	0.079	0.105	0.131	0.261
75	0.012	0.025	0.049	0.074	0.099	0.123	0.245
80	0.012	0.023	0.047	0.070	0.093	0.116	0.232
85	0.011	0.022	0.044	0.067	0.089	0.111	0.221
90	0.011	0.021	0.042	0.064	0.085	0.106	0.211
95	0.010	0.020	0.041	0.061	0.082	0.102	0.203
100	0.010	0.020	0.039	0.059	0.079	0.098	0.196

AQUEOUS SOLUBILITY AND HENRY'S LAW CONSTANTS OF ORGANIC COMPOUNDS

The solubility in water of over 1200 organic compounds, including many compounds of environmental interest, is tabulated here. Values are given at ambient temperature (usually 20°C or 25°C) and at higher temperatures when data are available. Solids, liquids, and gases are included; additional data on gases can be found in the table "Solubility of Selected Gases in Water" in Section 8.

Solubility of solids is defined as the concentration of the compound in a solution that is in equilibrium with the solid phase at the specified temperature and one atmosphere pressure. For liquids whose water mixtures separate into two phases, the solubility given here is the concentration of the specified compound in the water-rich phase at equilibrium. In the case of gases (i.e., compounds whose vapor pressure at the specified temperature exceeds one atmosphere) the solubility is defined here as the concentration in the water phase when the partial pressure of the compound above the solution is 101.325 kPa (1 atm). Values for gases are marked with [a].

The primary solubility values in this tables are expressed as mass percent of solute, $S = 100w_2$, where the mass fraction w_2 is defined as

$$w_2 = m_2/(m_1 + m_2) ,$$

where m_2 is the mass of solute and m_1 the mass of water. For convenience, the solubility expressed in grams of solute per liter of solution is tabulated in the adjacent column to mass percent. The conversion between these two measures involves the density of the solution, which usually is not readily available. For compounds with low solubility (say, S<1%), the error from approximating the density is generally less than the uncertainty in the experimental solubility measurement, so that little accuracy is lost in the conversion. However, this may not be true for more soluble compounds; for that reason, some values in the table are indicated as approximate (~).

The mass fraction w_2 is related to other common measures of solubility as follows:

Molality: $m_2 = 1000\ w_2/M_2(1\text{-}w_2)$

Molarity: $c_2 = 1000\rho w_2/M_2$

Mole fraction: $x_2 = (w_2/M_2)/\{(w_2/M_2) + (1\text{-}w_2)/M_1\}$

Mass of solute per 100 g of H_2O: $r_2 = 100w_2/(1\text{-}w_2)$

Mass of solute per liter of solution $1000\rho w_2$

Here M_2 is the molar mass of the solute, M_1 = 18.015 g/mol is the molar mass of water, and ρ is the density of the solution in g/mL.

Data have been selected from evaluated sources wherever possible, in particular the *IUPAC Solubility Data Series* (References 1,2,3,4,35,36,38,39). Many values come from experimental measurements reported in the *Journal of Chemical and Engineering Data* and the *Journal of Chemical Thermodynamics*, as well as critical review papers in the *Journal of Physical and Chemical Reference Data*. The primary source for each value is listed in the column following the solubility values. The user is cautioned that wide variations of data are found in the literature for the lower solubility compounds.

The table also contains values of the Henry's Law constant k_H, which provides a measure of the partition of a substance between the atmosphere and the aqueous phase. Here k_H is defined as the limit of p_2/c_2 as the concentration approaches zero, where p_2 is the partial pressure of the solute above the solution and c_2 is the concentration in the solution at equilibrium (other formulations of Henry's Law are often used; see Reference 5). The values of k_H listed here are based on direct experimental measurement whenever available, but many of them are simply calculated as the ratio of the pure compound vapor pressure to the solubility. This approximation is reliable only for compounds of very low solubility. In fact, values of k_H found in the literature frequently differ by a factor of two or three, and variations over an order of magnitude are not unusual (Reference 5). Therefore the data given here should be taken only as a rough indication of the true Henry's Law constant, which is difficult to measure precisely.

All values of k_H refer to 25°C. If the vapor pressure of the compound at 25°C is greater than one atmosphere, it can be assumed that the k_H value has been calculated as $101.325/c_2$ kPa m³/mol. The source of the Henry's Law data is given in the last column. The air-water partition coefficient (i.e., ratio of air concentration to water concentration when both are expressed in the same units) is equal to k_H/RT or $k_H/2.48$ in the units used here.

Compounds are listed by molecular formula following the Hill convention. To locate a compound by name or CAS Registry Number when the molecular formula is not known, use the table "Physical Constants of Organic Compounds" in Section 3 and its indexes to determine the molecular formula.

References

1. *Solubility Data Series, International Union of Pure and Applied Chemistry, Vol. 15*, Pergamon Press, Oxford, 1982.
2. *Solubility Data Series, International Union of Pure and Applied Chemistry, Vol. 20*, Pergamon Press, Oxford, 1985.
3. *Solubility Data Series, International Union of Pure and Applied Chemistry, Vol. 37*, Pergamon Press, Oxford, 1988.
4. *Solubility Data Series, International Union of Pure and Applied Chemistry, Vol. 38*, Pergamon Press, Oxford, 1988.
5. Mackay, D., and Shiu, W. Y., *J. Phys. Chem. Ref. Data*, 10, 1175, 1981.
6. Pearlman, R. S., and Yalkowsky, S. H., *J. Phys. Chem. Ref. Data*, 13, 975, 1984.
7. Shiu, W. Y., and Mackay, D., *J. Phys. Chem. Ref. Data*, 15, 911, 1986.
8. Varhanickova, D., Lee, S. C., Shiu, W. Y., and Mackay, D., *J. Chem. Eng. Data*, 40, 620, 1995.
9. Miller, M. M., Ghodbane, S., Wasik, S. P., Tewari, Y. B., and Martire, D. E., *J. Chem. Eng. Data*, 29, 184, 1984.
10. Riddick, J. A., Bunger, W. B., and Sakano, T. K., *Organic Solvents, Fourth Edition*, John Wiley & Sons, New York, 1986.
11. Mackay, D., Shiu, W. Y., and Ma, K. C., *Illustrated Handbook of Physical-Chemical Properties and Environmental Fate for Organic Chemicals, Vol. I*, Lewis Publishers/CRC Press, Boca Raton, FL, 1992.
12. Mackay, D., Shiu, W. Y., and Ma, K. C., *Illustrated Handbook of Physical-Chemical Properties and Environmental Fate for Organic Chemicals, Vol. II*, Lewis Publishers/CRC Press, Boca Raton, FL, 1992.
13. Mackay, D., Shiu, W. Y., and Ma, K. C., *Illustrated Handbook of Physical-Chemical Properties and Environmental Fate for Organic Chemicals, Vol. III*, Lewis Publishers/CRC Press, Boca Raton, FL, 1993.

14. Horvath, A. L., *Halogenated Hydrocarbons*, Marcel Dekker, New York, 1982.
15. Howard, P. H., *Handbook of Environmental Fate and Exposure Data for Organic Chemicals, Vol. I*, Lewis Publishers/CRC Press, Boca Raton, FL, 1989.
16. Howard, P. H., *Handbook of Environmental Fate and Exposure Data for Organic Chemicals, Vol. II*, Lewis Publishers/CRC Press, Boca Raton, FL, 1990.
17. Banergee, S., Yalkowsky, S. H., and Valvani, S. C., *Environ. Sci. Technol.*, 14, 1227, 1980.
18. Gevantman, L., in *CRC Handbook of Chemistry and Physics*, *84th Edition*, p. 8-88, CRC Press, Boca Raton, FL, 2003.
19. Wilhelm, E., Battino, R., and Wilcock, R. J., *Chem. Rev.* 77, 219, 1977.
20. Stephenson, R. M., *J. Chem. Eng. Data*, 37, 80, 1992.
21. Stephenson, R. M., Stuart, J., and Tabak, M., *J. Chem. Eng. Data*, 29, 287, 1984.
22. Shiu, W.-Y., and Ma, K.-C, *J. Phys. Chem. Ref. Data*, 29, 41, 2000.
23. Lun, R., Varhanickova, D., Shiu, W.-Y., and Mackay, D., *J. Chem. Eng. Data,* 42, 951 (1997).
24. Huang, G.-L., Xiao, H., Chi, J., Shiu, W.-Y., and Mackay, D., *J. Chem. Eng. Data*, 45, 411, 2000.
25. Horvath, A. L., Getzen, F. W., and Maczynska, Z., *J. Phys. Chem. Ref. Data*, 28, 395, 2000 [IUPAC No. 67].
26. Dawson, R. M. C., Elliott, D. C., Elliott, W. H., and Jones, K. M., *Data for Biochemical Research*, Third Edition, Clarendon Press, Oxford, 1986.
27. Stephen, H., and Stephen, T., *Solubilities of Organic and Inorganic Compounds*, MacMillan, New York, 1963.
28. Shiu, W.-Y., and Mackay, D., *J. Chem. Eng. Data,* 42, 27, 1997.
29. Hinz, H.-J., ed., *Thermodynamic Data for Biochemistry and Biotechnology*, Springer-Verlag, Berlin, 1986.
30. Budavari, S., ed., *The Merck Index, Twelfth Edition*, Merck & Co., Rahway, NJ, 1996.
31. Bamford, H. A., Poster, D. L., and Baker, J. E., *J. Chem. Eng. Data,* 45, 1069, 2000.
32. Lide, D. R., and Milne, G. W. A., *Handbook of Data on Organic Compounds, Third Edition*, CRC Press, Boca Raton, FL, 1994.
33. Apelblat, A., and Manzurola, E., *J. Chem. Thermodynamics* 21, 1005, 1989.
34. Apelblat, A., and Manzurola, E., *J. Chem. Thermodynamics* 22, 289, 1990.
35. Horvath, A. L., and Getzen, F. W., *J. Phys. Chem. Ref. Data* 28, 649, 1999 [IUPAC No. 68].
36. Sazonov, V. P., Marsh, K. N., and Hefter, G. T., *J. Phys. Chem. Ref. Data* 29, 1165, 2000 [IUPAC No. 71].
37. Verbruggen, E. M. J., Hermens, J. L. M., and Tolls, J., *J. Phys. Chem. Ref. Data* 29, 1435, 2000.
38. Sazonov, V. P., Shaw, D. G., and Marsh, K. N., *J. Phys. Chem. Ref. Data* 31, 1, 2002 [IUPAC No. 77].
39. Sazonov, V. P., and Shaw, D. G., *J. Phys. Chem. Ref. Data* 31, 989, 2002 [IUPAC No. 78].
40. Yalkowsky, S. H., and He, Y., *Handbook of Aqueous Solubility Data*, CRC Press, Boca Raton, FL, 2003.
41. Shiu, W.-Y., and Ma, K.-C., *J. Phys. Chem. Ref. Data* 29, 387, 2000.

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	**t/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
$CBrF_3$	Bromotrifluoromethane	148.910	25	0.032[a]	0.32[a]	14		
CBr_3F	Tribromofluoromethane	270.721	25	0.040	0.40	14		
CBr_4	Tetrabromomethane	331.627	30	0.024	0.24	14		
$CClF_3$	Chlorotrifluoromethane	104.459	25	0.009[a]	0.09[a]	10	6.9	13
CClN	Cyanogen chloride	61.471	0	5.7	60	40		
CCl_2F_2	Dichlorodifluoromethane	120.914	20	0.028[a]	0.28[a]	5	41	13
CCl_3F	Trichlorofluoromethane	137.368	20	0.11	1.1	5	10.2	13
CCl_3NO_2	Trichloronitromethane	164.376	0	0.227	2.27	40		
			25	0.162	1.62	40		
CCl_4	Tetrachloromethane	153.823	25	0.065	0.65	20	2.99	13
			75	0.115	11.5	20	2.99	13
CF_4	Tetrafluoromethane	88.005	25	0.00187[a]	0.0187[a]	19		
$CHBrCl_2$	Bromodichloromethane	163.829	30	0.300	3.00	40		
$CHBr_2Cl$	Chlorodibromomethane	208.280	30	0.251	2.51	40		
$CHBr_3$	Tribromomethane	252.731	25	0.30	3.0	5	0.047	13
$CHClF_2$	Chlorodifluoromethane	86.469	25	0.30[a]	3.0[a]	10	3.0	13
$CHCl_2F$	Dichlorofluoromethane	102.923	25	0.95[a]	9.5[a]	10		
$CHCl_3$	Trichloromethane	119.378	25	0.80	8.0	20	0.43	13
			59	0.79	7.9	20	0.43	13
CHF_3	Trifluoromethane	70.014	25	0.09[a]	0.9[a]	14		
CHI_3	Triiodomethane	393.732	25	0.012	0.12	14		
CH_2BrCl	Bromochloromethane	129.384	25	1.7	17	10	0.18	13
CH_2Br_2	Dibromomethane	173.835	20	1.28	11.5	20	0.086	13
			90	1.51	15.3	20		
CH_2ClF	Chlorofluoromethane	68.478	25	1.05[a]	10.6[a]	14		
CH_2Cl_2	Dichloromethane	84.933	25	1.73	17.6	20	0.30	13
CH_2I_2	Diiodomethane	267.836	30	0.124	1.24	10	0.032	13
CH_3Br	Bromomethane	94.939	20	1.80[a]	18.3[a]	5	0.63	13
CH_3Cl	Chloromethane	50.488	25	0.535[a]	5.35[a]	5	0.98	13
CH_3F	Fluoromethane	34.033	30	0.177[a]	1.77[a]	5		
CH_3I	Iodomethane	141.939	20	1.4	14	10	0.54	13
CH_3NO_2	Nitromethane	61.041	0	9.2	101	36		

Mol. formula	Name	Mol. wt.	t/°C	Solubility S Mass%	Solubility S g/L	Ref.	Henry Const. k_H kPa m³mol⁻¹	Ref.
			25	11.0	~125	36		
			50	14.8	~175	36		
CH_4	Methane	16.043	25	0.00227[a]	0.0227[a]	18	67.4	5
CH_4N_2O	Urea	60.055	5	44		26		
			25	54.4		26		
CH_4N_2S	Thiourea	76.121	20	10.6	~120	40		
			80	~37	580	40		
$CH_4N_4O_2$	Nitroguanidine	104.069	25	1.2	12	40		
CO	Carbon monoxide	28.010	25	0.00276[a]	0.0276[a]	18		
CO_2	Carbon dioxide	44.010	25	0.1501	1.501	18		
CS_2	Carbon disulfide	76.141	20	0.210	2.10	10		
$C_2Br_2F_4$	1,2-Dibromotetrafluoroethane	259.823	25	0.00030	0.0030	25		
C_2ClF_5	Chloropentafluoroethane	154.466	25	0.006[a]	0.06[a]	10	260	13
$C_2Cl_2F_4$	1,2-Dichloro-1,1,2,2-tetrafluoroethane	170.921	25	0.013[a]	0.13[a]	10	127	13
$C_2Cl_3F_3$	1,1,2-Trichloro-1,2,2-trifluoroethane	187.375	25	0.017	0.17	25	32	13
C_2Cl_4	Tetrachloroethene	165.833	0	0.0273	0.24	20		
			20	0.0286	0.21	20	1.73	13
			80	0.0380	0.20	20		
$C_2Cl_4F_2$	1,1,2,2-Tetrachloro-1,2-difluoroethane	203.830	27	0.016	0.16	25		
C_2Cl_6	Hexachloroethane	236.739	25	0.005	0.05	25	0.85	13
C_2F_4	Tetrafluoroethene	100.015	25	0.0158[a]	0.158[a]	19		
$C_2HBrClF_3$	2-Bromo-2-chloro-1,1,1-trifluoroethane	197.381	10	0.52	5.2	25		
			25	0.41	4.1	25		
			40	0.40	4.0	25		
$C_2HCl_2F_3$	2,2-Dichloro-1,1,1-trifluoroethane	152.930	25	0.46	4.6	25		
C_2HCl_3	Trichloroethene	131.388	0	0.145	1.45	25		
			25	0.128	1.28	25	1.03	13
			60	0.133	1.33	25		
C_2HCl_3O	Trichloroacetaldehyde	147.387	25	~39	650	40		
$C_2HCl_3O_2$	Trichloroacetic acid	163.387	25	92.3		27		
C_2HCl_5	Pentachloroethane	202.294	25	0.049	0.49	25	0.25	13
C_2H_2	Acetylene	26.037	25	0.1081[a]	1.081[a]	19		
$C_2H_2Br_2Cl_2$	1,2-Dibromo-1,2-dichloroethane	256.751	20	0.070	0.70	25		
$C_2H_2Br_4$	1,1,2,2-Tetrabromoethane	345.653	0	0.052	0.52	25		
			25	0.068	0.68	25		
			50	0.106	1.06	25		
			100	0.307	3.07	25		
$C_2H_2Cl_2$	1,1-Dichloroethene	96.943	5	0.310	3.10	25		
			25	0.242	2.42	25	2.62	13
			50	0.225	2.25	25		
			90	0.355	3.55	25		
$C_2H_2Cl_2$	*cis*-1,2-Dichloroethene	96.943	10	0.76	7.6	25		
			25	0.64	6.4	25	0.46	13
			40	0.66	6.6	25		
$C_2H_2Cl_2$	*trans*-1,2-Dichloroethene	96.943	10	0.53	5.3	25		
			25	0.45	4.5	25	0.96	13
			40	0.41	4.1	25		
$C_2H_2Cl_2F_2$	1,2-Dichloro-1,1-difluoroethane	134.940	24	0.49	4.9	25		
$C_2H_2Cl_4$	1,1,1,2-Tetrachloroethane	167.849	0	0.120	1.20	25		
			25	0.107	1.07	25	0.24	13
			50	0.123	1.23	25		
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane	167.849	5	0.302	3.02	25		
			25	0.283	2.83	25	0.026	13
			50	0.318	3.18	25		
$C_2H_2I_2$	*cis*-1,2-Diiodoethene	279.846	25	0.046	0.46	25		
$C_2H_2I_2$	*trans*-1,2-Diiodoethene	279.846	25	0.015	0.15	25		
$C_2H_2O_4$	Oxalic acid	90.035	20	8.69	95.1	27		
			80	45.8		27		

Mol. formula	Name	Mol. wt.	t/°C	Solubility S Mass%	Solubility S g/L	Solubility S Ref.	Henry Const. k_H kPa m³mol⁻¹	Henry Const. k_H Ref.
$C_2H_3Br_2Cl$	1,2-Dibromo-1-chloroethane	222.306	20	0.060	0.60	25		
$C_2H_3Br_3$	1,1,2-Tribromoethane	266.757	20	0.050	0.50	25		
C_2H_3Cl	Chloroethene	62.498	25	0.27[a]	2.7[a]	5	2.68	13
$C_2H_3Cl_2F$	1,1-Dichloro-1-fluoroethane	116.949	25	0.042	0.42	25		
$C_2H_3Cl_3$	1,1,1-Trichloroethane	133.404	0	0.134	1.34	25		
			25	0.129	1.29	25	1.76	13
			50	0.138	1.38	25		
$C_2H_3Cl_3$	1,1,2-Trichloroethane	133.404	0	0.425	4.25	25		
			25	0.459	4.59	25	0.092	13
			50	0.536	5.36	25		
C_2H_3N	Acetonitrile	41.052	-3	40.5		39		
			-10	31.7		39		
C_2H_3NS	Methyl isothiocyanate	73.117	20	0.75	7.6	40		
C_2H_4	Ethylene	28.053	25	0.01336[a]	0.1336[a]	19	21.7	5
C_2H_4BrCl	1-Bromo-2-chloroethane	143.410	30	0.683	6.83	25		
$C_2H_4Br_2$	1,2-Dibromoethane	187.861	20	0.412	3.1	20		
			50	0.493	3.9	20	0.066	13
			80	0.572	5.4	20		
$C_2H_4Cl_2$	1,1-Dichloroethane	98.959	0	0.62	6.2	25		
			25	0.50	5.0	25	0.63	13
			50	0.50	5.0	25		
$C_2H_4Cl_2$	1,2-Dichloroethane	98.959	0	0.92	9.2	25		
			25	0.86	8.6	25	0.14	13
			50	1.05	10.6	25		
			100	2.17	22.1	25		
$C_2H_4N_4$	Cyanoguanidine	84.080	25	3.8	40	40		
$C_2H_4N_4$	1*H*-1,2,4-Triazol-3-amine	84.080	23	22		26		
$C_2H_4O_2$	Methyl formate	60.052	25	23		10		
$C_2H_4O_3$	Glycolic acid	76.051	25	71.21		34		
			55	77.95		34		
C_2H_5Br	Bromoethane	108.965	0	1.05	10.6	25		
			25	0.90	9.0	25	1.23	13
C_2H_5Cl	Chloroethane	64.514	0	0.45	4.5	25		
			25	0.67	6.7	25	1.02	13
C_2H_5F	Fluoroethane	48.059	25	0.216[a]	2.16[a]	14		
C_2H_5I	Iodoethane	155.965	0	0.44	4.4	25		
			25	0.40	4.0	25	0.52	13
C_2H_5N	Ethyleneimine	43.068	20	0.90	9.12	40		
C_2H_5NO	Acetamide	59.067	20	40.8		10		
$C_2H_5NO_2$	Nitroethane	75.067	25	4.4	46	38		
			50	5.3	56	38		
$C_2H_5NO_2$	Methyl carbamate	75.067	15	69		27		
$C_2H_5NO_2$	Glycine	75.067	25	20.06		26		
C_2H_5NS	Thioacetamide	75.133	25	12.3	140	40		
$C_2H_5N_3O_2$	*N*-Methyl-*N*-nitrosourea	103.080	14	2.3	24	40		
$C_2H_5N_3O_2$	Imidodicarbonic diamide	103.080	15	1.5	15	40		
C_2H_6	Ethane	30.069	25	0.00568[a]	0.0568[a]	18	50.6	5
C_2H_6O	Dimethyl ether	46.068	24	35.3[a]		10	0.077	13
C_2H_6OS	Dimethyl sulfoxide	78.133	25	25.3		10		
$C_2H_6O_4S$	Dimethyl sulfate	126.132	18	2.7	28	27		
C_2H_6S	Dimethyl sulfide	62.134	25	2	20	10		
$C_2H_7AsO_2$	Dimethylarsinic acid	137.998	25	~41	684	40		
C_2N_2	Cyanogen	52.034	25	0.8	8	30		
$C_3Br_2F_6$	1,2-Dibromo-1,1,2,3,3,3-hexafluoropropane	309.830	21	0.0068	0.068	35		
$C_3Cl_2F_6$	1,2-Dichloro-1,1,2,3,3,3-hexafluoropropane	220.928	21	0.0096	0.096	35		
$C_3Cl_3F_5$	1,1,1-Trichloro-2,2,3,3,3-pentafluoropropane	237.383	21	0.0058	0.058	35		

				Solubility S			Henry Const. k_H	
Mol. formula	Name	Mol. wt.	t/°C	Mass%	g/L	Ref.	kPa m^3mol^{-1}	Ref.
$C_3Cl_4F_4$	1,1,1,3-Tetrachloro-2,2,3,3-tetrafluoropropane	253.838	21	0.0052	0.052	35		
C_3Cl_6	Hexachloropropene	248.750	20	0.00118	0.0118	35		
C_3F_6	Perfluoropropene	150.022	25	0.0194[a]	0.194[a]	14		
C_3F_8	Perfluoropropane	188.019	15	0.0015[a]	0.015[a]	14		
$C_3H_2N_2$	Malononitrile	66.061	20	10.6	118	40		
C_3H_3N	Acrylonitrile	53.063	20	7.35	79.3	10		
$C_3H_3NOS_2$	2-Thioxo-4-thiazolidinone	133.192	25	0.225	2.25	40		
$C_3H_3N_3O_3$	Cyanuric acid	129.074	25	0.259	2.59	40		
C_3H_4	Propyne	40.064	25	0.364[a]	3.64[a]	5	1.11	5
$C_3H_4ClF_3$	3-Chloro-1,1,1-trifluoropropane	132.512	20	0.133	1.33	35		
$C_3H_4Cl_2$	*cis*-1,3-Dichloropropene	110.970	20	0.27	2.7	5	0.24	5
$C_3H_4Cl_2$	*trans*-1,3-Dichloropropene	110.970	20	0.28	2.8	5	0.18	5
$C_3H_4Cl_2$	2,3-Dichloropropene	110.970	25	0.215	2.15	5	0.36	5
$C_3H_4N_2O$	2-Cyanoacetamide	84.076	20	11.5	130	40		
$C_3H_4N_2O_2$	2,4-Imidazolidinedione	100.076	25	3.93	40.9	29		
C_3H_4O	Acrolein	56.063	20	20.8		10		
$C_3H_4O_4$	Malonic acid	104.062	0	37.9		26		
			20	42.4		26		
			50	48.1		26		
C_3H_5Br	3-Bromopropene	120.976	25	0.38	3.8	35		
$C_3H_5Br_2Cl$	1,2-Dibromo-3-chloropropane	236.333	20	0.123	1.23	35		
C_3H_5Cl	3-Chloropropene	76.525	25	0.40	4.0	35	1.10	5
			50	0.13	1.3	35		
C_3H_5ClO	Epichlorohydrin	92.524	20	6.58	70.4	10	0.003	13
			65	7.2	77.9	40		
$C_3H_5Cl_3$	1,2,3-Trichloropropane	147.431	10	0.14	1.4	35		
			25	0.20	2.0	35	0.038	13
C_3H_5N	Propanenitrile	55.079	25	10.3	~115	10		
C_3H_5NO	Acrylamide	71.078	20	~27	371	40		
$C_3H_5N_3O_9$	Trinitroglycerol	227.087	25	0.13	1.3	40		
			80	0.34	3.4	40		
C_3H_6	Propene	42.080	25	0.0200[a]	0.200[a]	5	21.3	5
C_3H_6	Cyclopropane	42.080	25	0.0484[a]	0.484[a]	19		
C_3H_6BrCl	1-Bromo-3-chloropropane	157.437	25	0.223	2.23	35		
$C_3H_6Br_2$	1,2-Dibromopropane	201.888	25	0.143	1.43	10		
$C_3H_6Br_2$	1,3-Dibromopropane	201.888	25	0.169	1.69	35		
$C_3H_6Cl_2$	1,2-Dichloropropane, (±)-	112.986	5	0.270	2.70	35		
			25	0.274	2.74	35	0.29	13
			40	0.297	2.97	35		
$C_3H_6Cl_2$	1,3-Dichloropropane	112.986	5	0.218	2.18	35		
			25	0.280	2.80	35		
$C_3H_6N_6$	1,3,5-Triazine-2,4,6-triamine	126.120	20	0.323	3.23	40		
			95	4.2	44	40		
$C_3H_6N_6O_6$	Hexahydro-1,3,5-trinitro-1,3,5-triazine	222.116	25	0.0060	0.060	17		
C_3H_6O	Propanal	58.079	25	30.6		10		
C_3H_6O	Methyloxirane	58.079	20	40.5		10	0.0087	13
$C_3H_6O_2$	Ethyl formate	74.079	25	11.8	~135	10		
$C_3H_6O_2$	Methyl acetate	74.079	20	24.5		10		
$C_3H_6O_3$	1,3,5-Trioxane	90.078	25	17.4	~210	30		
C_3H_7Br	1-Bromopropane	122.992	0	0.298	2.98	35		
			25	0.234	2.34	35	3.8	13
C_3H_7Br	2-Bromopropane	122.992	20	0.32	3.2	35	1.27	13
C_3H_7Cl	1-Chloropropane	78.541	25	0.250	2.50	35	1.41	13
C_3H_7Cl	2-Chloropropane	78.541	0	0.44	4.4	35		
			20	0.30	3.0	35		
C_3H_7ClO	1-Chloro-2-methoxyethane	94.540	20	7.79	84	20		
			70	6.31	67	20		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
C_3H_7F	1-Fluoropropane	62.086	14	0.386[a]	3.86[a]	14		
C_3H_7F	2-Fluoropropane	62.086	15	0.366	3.66	14		
C_3H_7I	1-Iodopropane	169.992	0	0.114	1.14	35		
			20	0.100	1.00	35	0.93	13
C_3H_7I	2-Iodopropane	169.992	0	0.167	1.67	35		
			20	0.140	1.40	35		
$C_3H_7NO_2$	1-Nitropropane	89.094	25	1.54	15.6	38		
			90	2.29	23	20		
$C_3H_7NO_2$	2-Nitropropane	89.094	25	1.75	17.8	38		
			90	2.36	24	20		
$C_3H_7NO_2$	Ethyl carbamate	89.094	15	48		27		
$C_3H_7NO_2$	*L*-Alanine	89.094	25	14.30	~170	26		
$C_3H_7NO_2$	β-Alanine	89.094	25	47.1		26		
$C_3H_7NO_2$	Sarcosine	89.094	25	30.0		26		
$C_3H_7NO_3$	*L*-Serine	105.093	25	20	~200	26		
$C_3H_7N_3O_2$	*N*-Ethyl-*N*-nitrosourea	117.107	20	1.3	13	40		
$C_3H_7N_3O_2$	Guanidinoacetic acid	117.107	25	0.5	5	26		
C_3H_8	Propane	44.096	25	0.00669[a]	0.0669[a]	18	71.6	5
$C_3H_8NO_5P$	Glyphosate	169.074	25	1.2	12	32		
$C_3H_8O_2$	Dimethoxymethane	76.095	16	24.4		10		
$C_3H_9O_4P$	Trimethyl phosphate	140.074	25	~33	500	40		
C_4Cl_6	Hexachloro-1,3-butadiene	260.761	25	0.41	4.1	35		
C_4F_8	Perfluorocyclobutane	200.030	21	0.014[a]	0.14[a]	14		
$C_4H_3FN_2O_2$	5-Fluorouracil	130.077	22	1.10	11.1	40		
$C_4H_4N_2$	Succinonitrile	80.088	25	11.5	~130	10		
$C_4H_4N_2O_2$	Uracil	112.087	25	0.27	2.7	29		
C_4H_4O	Furan	68.074	25	1	10	10	0.54	13
$C_4H_4O_4$	Maleic acid	116.073	25	44.1		26		
C_4H_5N	2-Methylacrylonitrile	67.090	20	2.57	26.3	10		
C_4H_5N	Pyrrole	67.090	25	4.5	47	10		
$C_4H_5N_3O$	Cytosine	111.102	25	0.73	7.3	29		
C_4H_6	1,3-Butadiene	54.091	25	0.0735[a]	0.735[a]	5	20.7	13
C_4H_6	1-Butyne	54.091	25	0.287[a]	2.87[a]	5	1.91	5
$C_4H_6N_2O_2$	2,5-Piperazinedione	114.103	25	1.64	16.6	29		
$C_4H_6N_4O_3S_2$	Acetazolamide	222.246	30	0.10	1.0	40		
C_4H_6O	*trans*-2-Butenal	70.090	20	15.6	~185	10		
$C_4H_6O_2$	*trans*-2-Butenoic acid	86.090	20	7.1	76	26		
$C_4H_6O_2$	Methacrylic acid	86.090	20	8.9	98	10		
$C_4H_6O_2$	Vinyl acetate	86.090	20	2.0	20	10		
$C_4H_6O_2$	Methyl acrylate	86.090	25	4.94	52.0	10		
$C_4H_6O_2$	2,3-Butanedione	86.090	20	31.7		20		
			80	21.8		20		
$C_4H_6O_4$	Succinic acid	118.089	25	7.71	83.5	27		
			100	55		27		
$C_4H_6O_4$	Methylmalonic acid	118.089	0	30.1		26		
			20	40		26		
$C_4H_6O_4$	Dimethyl oxalate	118.089	20	5.82	61.8	27		
$C_4H_6O_5$	Diglycolic acid	134.088	24	40.03		34		
$C_4H_6O_5$	Malic acid	134.088	26	59		26		
			50	59.9		34		
$C_4H_6O_6$	*DL*-Tartaric acid	150.087	0	8.95	98	26		
			20	17.1	~200	26		
			100	65		26		
$C_4H_6O_6$	*L*-Tartaric acid	150.087	20	58		26		
			100	77		26		
C_4H_7Br	4-Bromo-1-butene	135.003	25	0.076	0.76	35		
C_4H_7Cl	1-Chloro-2-methylpropene	90.552	25	0.916	9.16	5	0.12	5
C_4H_7ClO	3-Chloro-2-butanone	106.551	19	2.80	29	20		

Mol. formula	Name	Mol. wt.	*t*/°C	Solubility *S* Mass%	Solubility *S* g/L	Ref.	Henry Const. k_H kPa m^3mol^{-1}	Ref.
			92	3.38	35	20		
C_4H_7N	Butanenitrile	69.106	20	3.3	34	10		
$C_4H_7NO_4$	Iminodiacetic acid	133.104	5	2.32	23.7	40		
$C_4H_7NO_4$	*L*-Aspartic acid	133.104	25	0.501	5.01	26		
C_4H_8	1-Butene	56.107	25	0.0222[a]	0.222[a]	5	25.6	13
C_4H_8	Isobutene	56.107	25	0.0263[a]	0.263[a]	5	21.6	13
$C_4H_8Br_2$	1,4-Dibromobutane	215.915	25	0.035	0.35	35		
$C_4H_8Cl_2$	1,1-Dichlorobutane	127.013	25	0.050	0.50	35		
$C_4H_8Cl_2$	1,4-Dichlorobutane	127.013	25	0.16	1.6	35		
$C_4H_8Cl_2$	2,3-Dichlorobutane, (±)-	127.013	20	0.056	0.56	35		
$C_4H_8Cl_2O$	Bis(2-chloroethyl) ether	143.012	20	1.04	10.4	20	0.003	13
			81	1.26	12.8	20		
$C_4H_8N_2O_2$	Succinamide	116.119	50	18.4	~225	27		
$C_4H_8N_2O_2$	Dimethylglyoxime	116.119	20	0.06	0.6	40		
$C_4H_8N_2O_3$	*L*-Asparagine	132.118	25	2.45	25.1	26		
$C_4H_8N_2O_3$	*N*-Glycylglycine	132.118	25	18.4	~225	29		
C_4H_8O	*cis*-2-Buten-1-ol	72.106	20	16.6	~200	10		
C_4H_8O	Ethyl vinyl ether	72.106	20	0.9	9	10		
C_4H_8O	Butanal	72.106	25	7.1	76	10		
C_4H_8O	Isobutanal	72.106	20	9.1	100	10		
C_4H_8O	2-Butanone	72.106	25	25.9		20		
			70	18.1	~220	20		
$C_4H_8O_2$	2-Methylpropanoic acid	88.106	20	22.8		10		
$C_4H_8O_2$	Propyl formate	88.106	22	2.05	20.9	10		
$C_4H_8O_2$	Ethyl acetate	88.106	25	8.08	87.9	10		
$C_4H_8O_2$	Methyl propanoate	88.106		6	6	30		
C_4H_9Br	1-Bromobutane	137.018	25	0.087	0.87	35	1.2	13
C_4H_9Br	1-Bromo-2-methylpropane	137.018	18	0.051	0.51	35		
C_4H_9Cl	1-Chlorobutane	92.567	1	0.062	0.62	35		
			25	0.087	0.87	35	1.54	13
C_4H_9Cl	2-Chlorobutane	92.567	0	0.107	1.07	35		
			25	0.092	0.92	35		
C_4H_9Cl	1-Chloro-2-methylpropane	92.567	25	0.92	9.2	35		
C_4H_9Cl	2-Chloro-2-methylpropane	92.567	15	0.29	2.9	35		
C_4H_9I	1-Iodobutane	184.018	17	0.021	0.21	10	1.87	13
C_4H_9NO	Butanamide	87.120	25	~19	230	40		
$C_4H_9NO_2$	Ethyl *N*-methylcarbamate	103.120	15	69		27		
$C_4H_9NO_2$	2-Methylalanine	103.120	25	12.0	~135	26		
$C_4H_9NO_2$	*DL*-2-Aminobutanoic acid	103.120	25	17.4	~210	26		
$C_4H_9NO_2$	*DL*-3-Aminobutanoic acid	103.120	25	55.6		26		
$C_4H_9NO_3$	*L*-Threonine	119.119	25	8.93	98.0	26		
$C_4H_9NO_3$	*L*-Homoserine	119.119	25	52.4		26		
$C_4H_9N_3O_2$	Creatine	131.133	25	1.6	16	26		
C_4H_{10}	Butane	58.122	25	0.00724[a]	0.0724[a]	18	95.9	5
C_4H_{10}	Isobutane	58.122	25	0.00535[a]	0.0535[a]	18	120	5
$C_4H_{10}NO_3PS$	Acephate	183.166	20	~28	394	40		
$C_4H_{10}N_2O$	*N*-Nitrosodiethylamine	102.134	24	9.6	106	40		
$C_4H_{10}O$	1-Butanol	74.121	0	10.4	~115	1		
			25	7.4	80	1		
			50	6.4	68	1		
$C_4H_{10}O$	2-Butanol	74.121	10	23.9		1		
			25	18.1	~220	1		
			50	14.0	~165	1		
$C_4H_{10}O$	2-Methyl-1-propanol	74.121	0	11.5	~130	1		
			25	8.1	88	1	0.00273	28
			50	6.5	70	1		
$C_4H_{10}O$	Diethyl ether	74.121	25	6.04	64.2	10	0.088	13
$C_4H_{10}O$	Methyl propyl ether	74.121	25	3.5	36	30		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m³mol⁻¹**	**Ref.**
$C_4H_{10}O_4$	1,2,3,4-Butanetetrol	122.120	20	38.0		27		
$C_4H_{10}S$	1-Butanethiol	90.187	20	0.0597	0.597	10		
$C_4H_{10}S$	Diethyl sulfide	90.187	25	0.307	3.07	40		
$C_4H_{11}NO_2$	Diethanolamine	105.136	20	95.4		10		
$C_4H_{11}NO_3$	Tris(hydroxymethyl)methylamine	121.135	25	~41	699	40		
$C_4H_{12}Si$	Tetramethylsilane	88.224	25	0.00196	0.0196	10		
C_5Cl_8	Octachloro-1,3-pentadiene	343.678	20	0.000020	0.00020	35		
C_5F_{12}	Perfluoropentane	288.035	25	0.00012	0.0012	35		
$C_5H_4N_2O_4$	Orotic acid	156.097	18	0.18	1.8	26		
$C_5H_4N_4O$	Allopurinol	136.112	25	0.057	0.57	40		
$C_5H_4N_4O$	Hypoxanthine	136.112	25	0.070	0.70	29		
$C_5H_4N_4O_2$	Xanthine	152.112	20	0.05	0.5	26		
$C_5H_4N_4O_3$	Uric acid	168.111	20	0.002	0.02	26		
$C_5H_4N_4S$	1,7-Dihydro-6*H*-purine-6-thione	152.178	25	0.0124	0.124	40		
$C_5H_4O_2$	Furfural	96.085	20	8.2	89	10		
$C_5H_4O_3$	2-Furancarboxylic acid	112.084	25	4.758	50.0	33		
			50	25.16		33		
$C_5H_5N_5$	Adenine	135.128	25	0.104	1.04	29		
$C_5H_5N_5O$	Guanine	151.127	25	0.0068	0.068	29		
$C_5H_5N_5O$	6-Amino-1,3-dihydro-2*H*-purin-2-one	151.127	25	0.006	0.06	26		
C_5H_6	1,3-Cyclopentadiene	66.102	25	0.068	0.68	3		
$C_5H_6Cl_2N_2O_2$	1,3-Dichloro-5,5-dimethyl hydantoin	197.019	20	0.050	0.50	40		
$C_5H_6N_2OS$	Methylthiouracil	142.179	25	0.0533	0.533	40		
$C_5H_6N_2O_2$	Thymine	126.114	25	0.35	3.5	29		
$C_5H_6O_4$	1-Propene-2,3-dicarboxylic acid	130.100	20	7.7	83	26		
$C_5H_7NO_2$	Ethyl cyanoacetate	113.116	20	25.9		10		
$C_5H_7N_3O$	4-Amino-5-methyl-2(1*H*)-pyrimidinone	125.129	25	0.45	4.5	26		
C_5H_8	1,4-Pentadiene	68.118	25	0.056	0.56	3	12	5
C_5H_8	2-Methyl-1,3-butadiene	68.118	25	0.061	0.61	3	7.78	5
			50	0.076[a]	0.76[a]	3		
C_5H_8	1-Pentyne	68.118	25	0.157	1.57	3	2.5	5
C_5H_8	Cyclopentene	68.118	25	0.054	0.54	3	6.56	13
$C_5H_8N_4O_3S_2$	Methazolamide	236.273	15	0.0472	0.472	40		
$C_5H_8N_4O_{12}$	Pentaerythritol tetranitrate	316.138	20	0.0002	0.002	40		
C_5H_8O	Cyclopentanone	84.117	20	31.0		20		
			80	24.8		20		
C_5H_8O	3,4-Dihydro-2*H*-pyran	84.117	20	1.04	10.5	20		
			82	2.26	23	20		
$C_5H_8O_2$	Ethyl acrylate	100.117	25	1.50	15.2	10		
$C_5H_8O_2$	Methyl methacrylate	100.117	20	1.56	15.9	10		
$C_5H_8O_2$	2,4-Pentanedione	100.117	20	16.1	~200	20		
			80	32.2		20		
$C_5H_8O_3$	4-Oxopentanoic acid	116.116	10	63.6		34		
			25	83.97		34		
$C_5H_8O_4$	Pentanedioic acid	132.116	25	58.3		33		
			50	78.06		33		
$C_5H_8O_4$	Dimethyl malonate	132.116	19	14.9	~175	20		
			90	29.8		20		
C_5H_9ClO	5-Chloro-2-pentanone	120.577	22	4.7	49	20		
			71	13.5	~155	20		
$C_5H_9NO_2$	*L*-Proline	115.131	25	61.9		26		
$C_5H_9NO_3$	*trans*-4-Hydroxy-*L*-proline	131.130	25	26.5		26		
$C_5H_9NO_4$	*DL*-Glutamic acid	147.130	25	2.30	23.5	29		
$C_5H_9NO_4$	*L*-Glutamic acid	147.130	25	0.85	8.5	26		
C_5H_{10}	1-Pentene	70.133	25	0.0148	0.148	3	40.3	5
C_5H_{10}	*cis*-2-Pentene	70.133	25	0.0203	0.203	3	22.8	5
C_5H_{10}	3-Methyl-1-butene	70.133	25	0.013[a]	0.13[a]	3	54.7	5
C_5H_{10}	2-Methyl-2-butene	70.133	25	0.041	0.41	3		

				Solubility S			Henry Const. k_H	
Mol. formula	Name	Mol. wt.	t/°C	Mass%	g/L	Ref.	kPa m^3mol^{-1}	Ref.
C_5H_{10}	Cyclopentane	70.133	25	0.0157	0.157	3	19.1	13
$C_5H_{10}Cl_2$	1,2-Dichloropentane	141.038	25	0.029	0.29	35		
$C_5H_{10}Cl_2$	1,5-Dichloropentane	141.038	19	0.02	0.2	35		
$C_5H_{10}Cl_2$	2,3-Dichloropentane	141.038	25	0.029	0.29	35		
$C_5H_{10}Cl_2$	2,3-Dichloro-2-methylbutane	141.038	25	0.029	0.29	35		
$C_5H_{10}N_2O_2S$	Methomyl	162.210	25	5.5	58	40		
$C_5H_{10}N_2O_3$	*L*-Glutamine	146.144	25	4.0	42	26		
$C_5H_{10}N_2S_2$	Dazomet	162.276	25	0.12	1.2	40		
$C_5H_{10}O$	Pentanal	86.132	25	1.2	12	40		
$C_5H_{10}O$	2-Pentanone	86.132	25	5.5	58	20	0.00847	28
			80	3.8	40	20	0.00847	28
$C_5H_{10}O$	3-Pentanone	86.132	25	4.72	49.5	20		
			80	3.16	33	20		
$C_5H_{10}O$	3-Methyl-2-butanone	86.132	18	6.7	72	20		
			80	3.9	41	20		
$C_5H_{10}O$	Tetrahydropyran	86.132	20	8.57	87.1	20		
			81	4.29	45	20		
$C_5H_{10}O$	2-Methyltetrahydrofuran	86.132	19	14.4	~160	20	0.67	13
			71	6.0	64	20		
$C_5H_{10}O_2$	Pentanoic acid	102.132	16	3.6	37	26		
$C_5H_{10}O_2$	3-Methylbutanoic acid	102.132	20	4.0	42	26		
$C_5H_{10}O_2$	Isobutyl formate	102.132	22	1.0	10	10		
$C_5H_{10}O_2$	Propyl acetate	102.132	20	2.3	34	10		
$C_5H_{10}O_2$	Isopropyl acetate	102.132	20	2.9	30	10		
$C_5H_{10}O_2$	Ethyl propanoate	102.132	20	1.92	19.6	10		
$C_5H_{10}O_2$	Methyl butanoate	102.132		1.6	16	30		
$C_5H_{10}O_3$	Diethyl carbonate	118.131	20	1.8	18	40		
$C_5H_{10}O_5$	*D*-Xylose	150.130	25	~30	432	40		
$C_5H_{11}Br$	1-Bromopentane	151.045	25	0.0127	0.127	35		
$C_5H_{11}Br$	1-Bromo-3-methylbutane	151.045	16	0.020	0.20	35		
$C_5H_{11}Cl$	1-Chloropentane	106.594	5	0.020	0.20	35		
			25	0.0201	0.201	35	2.37	13
$C_5H_{11}Cl$	3-Chloropentane	106.594	25	0.025	0.25	35		
$C_5H_{11}NO_2$	*L*-Valine	117.147	25	8.13	88.4	26		
$C_5H_{11}NO_2$	*L*-Norvaline	117.147	25	9.7	107	26		
$C_5H_{11}NO_2S$	*L*-Methionine	149.212	25	5.3	56	26		
C_5H_{12}	Pentane	72.149	25	0.0041	0.041	3	128	13
C_5H_{12}	Isopentane	72.149	25	0.00485	0.0485	3	479	13
C_5H_{12}	Neopentane	72.149	25	0.00332[a]	0.0332[a]	3	220	13
$C_5H_{12}NO_3PS_2$	Cygon	229.258	20	2.6	27	40		
$C_5H_{12}O$	1-Pentanol	88.148	0	3.1	32	1		
			25	2.20	22.4	1		
			50	1.8	18	1		
$C_5H_{12}O$	2-Pentanol	88.148	25	4.3	45	21		
$C_5H_{12}O$	3-Pentanol	88.148	25	5.6	59	21		
$C_5H_{12}O$	2-Methyl-1-butanol, (±)-	88.148	25	3.0	31	3		
$C_5H_{12}O$	3-Methyl-1-butanol	88.148	25	2.7	28	1		
$C_5H_{12}O$	2-Methyl-2-butanol	88.148	25	11.0	~125	1		
$C_5H_{12}O$	3-Methyl-2-butanol, (±)-	88.148	25	5.6	59	1		
$C_5H_{12}O$	2,2-Dimethyl-1-propanol	88.148	25	3.5	36	1		
$C_5H_{12}O$	Methyl *tert*-butyl ether	88.148	0	8.3	37.6	20	0.070	13
			20	4.2	44	20		
			49	1.9	19	20		
$C_5H_{12}O_4$	Pentaerythritol	136.147	15	5.3	56	30		
$C_6Cl_4O_2$	2,3,5,6-Tetrachloro-2,5-cyclohexadiene-1,4-dione	245.875	20	0.025	0.25	40		
$C_6Cl_5NO_2$	Pentachloronitrobenzene	295.335	20	0.000044	0.00044	40		
C_6Cl_6	Hexachlorobenzene	284.782	25	0.0000005	0.000005	41	0.131	11

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
C_6F_{14}	Perfluorohexane	338.042	25	0.0000098	0.000098	35		
C_6F_{14}	Perfluoro-2-methylpentane	338.042	25	0.000017	0.00017	35		
C_6HCl_5	Pentachlorobenzene	250.337	25	0.000050	0.00050	41	0.085	11
C_6HCl_5O	Pentachlorophenol	266.336	25	0.0013	0.013	24		
$C_6H_2Br_4$	1,2,4,5-Tetrabromobenzene	393.696	25	0.00000434	0.0000434	2		
$C_6H_2ClN_3O_6$	2-Chloro-1,3,5-trinitrobenzene	247.549	15	0.018	0.18	40		
$C_6H_2Cl_4$	1,2,3,4-Tetrachlorobenzene	215.892	25	0.0007	0.007	41	0.144	11
$C_6H_2Cl_4$	1,2,3,5-Tetrachlorobenzene	215.892	25	0.00035	0.0035	41	0.59	11
$C_6H_2Cl_4$	1,2,4,5-Tetrachlorobenzene	215.892	25	0.000060	0.00060	41	0.122	11
$C_6H_2Cl_4O$	2,3,4,6-Tetrachlorophenol	231.891	25	0.017	0.17	24		
$C_6H_2Cl_4O_2$	3,4,5,6-Tetrachloro-1,2-benzenediol	247.891	25	0.071	0.71	8		
$C_6H_3Br_3$	1,2,4-Tribromobenzene	314.800	25	0.0010	0.010	2		
$C_6H_3Br_3$	1,3,5-Tribromobenzene	314.800	25	0.0000789	0.000789	2		
$C_6H_3Br_3O$	2,4,6-Tribromophenol	330.799	15	0.0007	0.007	2		
$C_6H_3ClN_2O_4$	1-Chloro-2,4-dinitrobenzene	202.552	25	0.00092	0.0092	40		
$C_6H_3Cl_2NO_2$	1,2-Dichloro-4-nitrobenzene	192.000	20	0.0121	0.121	40		
$C_6H_3Cl_2NO_2$	Clopyralid	192.000	20	0.1	1	40		
$C_6H_3Cl_3$	1,2,3-Trichlorobenzene	181.447	25	0.0021	0.021	41	0.242	11
$C_6H_3Cl_3$	1,2,4-Trichlorobenzene	181.447	25	0.0040	0.040	41	0.277	11
$C_6H_3Cl_3$	1,3,5-Trichlorobenzene	181.447	25	0.0008	0.008	41	1.1	11
$C_6H_3Cl_3O$	2,4,5-Trichlorophenol	197.446	25	0.1	1	2		
$C_6H_3Cl_3O$	2,4,6-Trichlorophenol	197.446	25	0.050	0.50	24		
$C_6H_3Cl_3O_2$	3,4,5-Trichloro-1,2-benzenediol	213.446	25	0.051	0.51	8		
$C_6H_3Cl_4N$	Nitrapyrin	230.907	20	0.0040	0.040	40		
$C_6H_3N_3O_6$	1,3,5-Trinitrobenzene	213.104	15	0.028	0.28	40		
$C_6H_3N_3O_7$	2,4,6-Trinitrophenol	229.104	25	1.25	12.7	40		
			90	4.9	51	40		
C_6H_4BrCl	1-Bromo-2-chlorobenzene	191.453	25	0.0124	0.124	2		
C_6H_4BrCl	1-Bromo-3-chlorobenzene	191.453	25	0.0118	0.118	2		
C_6H_4BrCl	1-Bromo-4-chlorobenzene	191.453	25	0.00442	0.0442	2		
C_6H_4BrI	1-Bromo-4-iodobenzene	282.904	25	0.000794	0.00794	2		
$C_6H_4Br_2$	*o*-Dibromobenzene	235.904	25	0.00748	0.0748	2		
$C_6H_4Br_2$	*m*-Dibromobenzene	235.904	25	0.0064	0.064	2		
$C_6H_4Br_2$	*p*-Dibromobenzene	235.904	25	0.0020	0.020	2		
$C_6H_4Br_2O$	2,4-Dibromophenol	251.903	25	0.2	2	2		
C_6H_4ClF	1-Chloro-2-fluorobenzene	130.547	25	0.0502	0.502	40		
C_6H_4ClI	1-Chloro-2-iodobenzene	238.453	25	0.00689	0.0689	2		
C_6H_4ClI	1-Chloro-3-iodobenzene	238.453	25	0.00674	0.0674	2		
C_6H_4ClI	1-Chloro-4-iodobenzene	238.453	25	0.00311	0.0311	2		
$C_6H_4ClNO_2$	1-Chloro-2-nitrobenzene	157.555	20	0.0441	0.441	40		
$C_6H_4ClNO_2$	1-Chloro-3-nitrobenzene	157.555	20	0.0273	0.273	40		
$C_6H_4ClNO_2$	1-Chloro-4-nitrobenzene	157.555	20	0.0453	0.453	40		
$C_6H_4Cl_2$	*o*-Dichlorobenzene	147.002	0	0.0142	0.142	2		
			25	0.0147	0.147	2	0.195	28
			50	0.0212	0.212	2		
$C_6H_4Cl_2$	*m*-Dichlorobenzene	147.002	10	0.0103	0.103	2		
			25	0.0120	0.120	41	0.376	11
			50	0.0165	0.165	2		
$C_6H_4Cl_2$	*p*-Dichlorobenzene	147.002	10	0.00512	0.0512	2		
			25	0.0080	0.080	41	0.244	28
			50	0.0167	0.167	2		
$C_6H_4Cl_2O$	2,3-Dichlorophenol	163.001	25	0.82	8.22	40		
$C_6H_4Cl_2O$	2,4-Dichlorophenol	163.001	20	0.49	4.9	24		
$C_6H_4Cl_2O$	2,6-Dichlorophenol	163.001	25	0.262	2.62	40		
$C_6H_4Cl_2O_2$	3,5-Dichloro-1,2-benzenediol	179.001	25	0.78	7.8	8		
$C_6H_4Cl_2O_2$	4,5-Dichloro-1,2-benzenediol	179.001	25	1.19	12.0	8		
$C_6H_4F_2$	*o*-Difluorobenzene	114.093	25	0.114	1.14	2		
$C_6H_4F_2$	*m*-Difluorobenzene	114.093	25	0.114	1.14	2		

				Solubility S			Henry Const. k_H	
Mol. formula	Name	Mol. wt.	t/°C	Mass%	g/L	Ref.	kPa m^3mol^{-1}	Ref.
$C_6H_4F_2$	*p*-Difluorobenzene	114.093	25	0.122	1.22	2		
$C_6H_4I_2$	*o*-Diiodobenzene	329.905	25	0.00192	0.0192	2		
$C_6H_4I_2$	*m*-Diiodobenzene	329.905	25	0.000185	0.00185	2		
$C_6H_4I_2$	*p*-Diiodobenzene	329.905	25	0.000893	0.00893	2		
$C_6H_4N_2O_4$	1,2-Dinitrobenzene	168.107	20	0.21	2.1	27		
$C_6H_4N_2O_4$	1,3-Dinitrobenzene	168.107	20	2.09	21.3	27		
$C_6H_4N_2O_4$	1,4-Dinitrobenzene	168.107	20	1.30	13.1	27		
$C_6H_4N_2O_5$	2,4-Dinitrophenol	184.106	25	0.046	0.46	40		
			100	1.4	14	40		
$C_6H_4O_2$	*p*-Benzoquinone	108.095	25	1.36	13.8	27		
C_6H_5Br	Bromobenzene	157.008	10	0.0387	0.387	2		
			25	0.0445	0.445	2	0.250	28
			40	0.0516	0.516	2		
C_6H_5BrO	4-Bromophenol	173.007	25	1.86	19.0	2		
C_6H_5Cl	Chlorobenzene	112.557	10	0.0387	0.387	2		
			25	0.0484	0.484	41	0.32	28
			50	0.0882	0.882	2		
C_6H_5ClO	2-Chlorophenol	128.556	25	2.0	20	2		
C_6H_5ClO	3-Chlorophenol	128.556	25	2.2	22	2		
C_6H_5ClO	4-Chlorophenol	128.556	25	2.7	28	2		
C_6H_5F	Fluorobenzene	96.102	19	0.170	1.70	20	0.70	11
			80	0.188	1.88	20	0.70	11
C_6H_5I	Iodobenzene	204.008	10	0.0193	0.193	2		
			25	0.0226	0.226	2	0.078	11
			45	0.0279	0.279	2		
$C_6H_5NO_2$	Nitrobenzene	123.110	25	0.21	2.1	17		
$C_6H_5NO_2$	3-Pyridinecarboxylic acid	123.110	20	1.8	18	40		
$C_6H_5NO_3$	2-Nitrophenol	139.109	20	0.21	2.1	27		
$C_6H_5NO_3$	3-Nitrophenol	139.109	20	2.14	21.9	27		
$C_6H_5NO_3$	4-Nitrophenol	139.109	20	1.32	13.3	27		
$C_6H_5N_3O_4$	2,4-Dinitroaniline	183.122	25	0.0078	0.078	40		
C_6H_6	Benzene	78.112	10	0.178	1.78	3		
			25	0.178	1.78	22	0.557	22
			50	0.208	2.08	3		
C_6H_6ClN	2-Chloroaniline	127.572	25	0.876	8.76	10		
C_6H_6ClN	3-Chloroaniline	127.572	20	0.54	5.44	40		
C_6H_6ClN	4-Chloroaniline	127.572	20	0.275	2.75	40		
$C_6H_6Cl_6$	1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2α,3β,4α,5α,6β)	290.830	25	0.00073	0.0073	40		
$C_6H_6Cl_6$	1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2α,3β,4α,5β,6β)	290.830	25	0.00020	0.0020	40		
$C_6H_6Cl_6$	1,2,3,4,5,6-Hexachlorocyclohexane, (1α,2β,3α,4β,5α,6β)	290.830	25	0.000024	0.00024	40		
$C_6H_6N_2O$	3-Pyridinecarboxamide	122.124	20	~33	500	40		
$C_6H_6N_2O_2$	2-Nitroaniline	138.124	30	1.47	14.9	27		
$C_6H_6N_2O_2$	3-Nitroaniline	138.124	30	0.121	1.21	27		
$C_6H_6N_2O_2$	4-Nitroaniline	138.124	30	0.073	0.73	27		
$C_6H_6N_4O_4$	Nitrofurazone	198.137	20	0.0238	0.238	40		
C_6H_6O	Phenol	94.111	16	6.3	67	26		
			25	8.66	94.8	10		
$C_6H_6O_2$	*p*-Hydroquinone	110.111	25	7.42	80.1	27		
$C_6H_6O_2$	Pyrocatechol	110.111	20	31.1		27		
$C_6H_6O_2$	Resorcinol	110.111	20	63.7		27		
$C_6H_6O_3$	1,2,3-Benzenetriol	126.110	25	38.5		27		
$C_6H_6O_3$	1,3,5-Benzenetriol	126.110	20	1.12	11.3	27		
$C_6H_6O_6$	*trans*-1-Propene-1,2,3-tricarboxylic acid	174.108	25	20.9		26		
			90	52.5		26		
C_6H_7N	Aniline	93.127	25	3.38	35.0	10	14	15

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m³mol⁻¹**	**Ref.**
C_6H_7NO	2-Aminophenol	109.126	20	1.92	19.6	40		
C_6H_7NO	3-Aminophenol	109.126	20	2.56	26.3	40		
			70	~24	319	40		
C_6H_7NO	4-Aminophenol	109.126	20	1.55	15.7	40		
$C_6H_7NO_3S$	4-Aminobenzenesulfonic acid	173.190	7	0.59	5.9	27		
$C_6H_7N_3O$	Isoniazid	137.139	25	11.0	123	40		
C_6H_8	1,4-Cyclohexadiene	80.128	25	0.08	0.8	3	1.03	13
C_6H_8ClN	Aniline hydrochloride	129.588	15	15.1	~180	27		
$C_6H_8N_2$	Hexanedinitrile	108.141	20	0.80	8.0	16		
$C_6H_8N_2$	1,2-Benzenediamine	108.141	20	3.02	31.1	40		
$C_6H_8N_2$	1,3-Benzenediamine	108.141	20	3.48	36.1	40		
$C_6H_8N_2$	1,4-Benzenediamine	108.141	24	3.45	35.7	40		
$C_6H_8N_2O_2S$	4-Aminobenzenesulfonamide	172.205	20	0.71	7.14	40		
$C_6H_8N_2O_8$	Isosorbide dinitrate	236.136	25	0.055	0.55	40		
$C_6H_8O_4$	Dimethyl maleate	144.126	25	8.0	87	10		
$C_6H_8O_6$	*L*-Ascorbic acid	176.124	25	25.22		33		
			50	41.00		33		
$C_6H_8O_7$	Citric acid	192.124	20	59		26		
$C_6H_9N_3O_2$	*L*-Histidine	155.154	25	4.17	43.5	26		
$C_6H_9N_3O_3$	Metronidazole	171.153	20	0.93	9.4	40		
C_6H_{10}	1,5-Hexadiene	82.143	25	0.017	0.17	3		
C_6H_{10}	1-Hexyne	82.143	25	0.036	0.36	3	4.14	13
C_6H_{10}	Cyclohexene	82.143	25	0.016	0.16	3	4.57	13
$C_6H_{10}O$	Cyclohexanone	98.142	25	8.8	96	20		
			80	6.8	73	20		
$C_6H_{10}O$	Mesityl oxide	98.142	20	2.89	29.8	10		
$C_6H_{10}O_3$	Ethyl acetoacetate	130.141	25	12	~135	10		
$C_6H_{10}O_4$	1,6-Hexanedioic acid	146.141	15	1.48	15.0	26		
			100	61.5		26		
$C_6H_{10}O_4$	Dimethyl succinate	146.141	21	12.4	~140	20		
			92	17.1	~205	20		
$C_6H_{10}O_4$	1,2-Ethanediol, diacetate	146.141	25	13.3	153	40		
$C_6H_{10}O_8$	Galactaric acid	210.138	14	0.33	3.3	40		
$C_6H_{11}NO$	Cyclohexanone oxime	113.157	25	1.57	15.9	40		
$C_6H_{11}NO$	Caprolactam	113.157	25	84.0		10		
$C_6H_{11}N_2O_4PS_3$	Methidathion	302.330	20	0.0187	0.187	40		
C_6H_{12}	1-Hexene	84.159	25	0.0053	0.053	3	41.8	5
C_6H_{12}	*trans*-2-Hexene	84.159	25	0.0067	0.067	3		
C_6H_{12}	2-Methyl-1-pentene	84.159	25	0.0078	0.078	3	28.1	5
C_6H_{12}	4-Methyl-1-pentene	84.159	25	0.0048	0.048	3	63.2	5
C_6H_{12}	2,3-Dimethyl-1-butene	84.159	30	0.046	0.46	3		
C_6H_{12}	Cyclohexane	84.159	25	0.0058	0.058	3	19.4	13
C_6H_{12}	Methylcyclopentane	84.159	25	0.0043	0.043	3	36.7	5
$C_6H_{12}N_2O_3$	Daminozide	160.170	25	9.1	100	40		
$C_6H_{12}N_2O_4S$	*L*-Lanthionine	208.235	25	0.15	1.5	26		
$C_6H_{12}N_2O_4S_2$	*L*-Cystine	240.300	25	0.011	0.11	26		
$C_6H_{12}N_2S_4$	Thiram	240.432	20	0.003	0.03	40		
$C_6H_{12}N_2S_4Zn$	Ziram	305.841	20	0.0065	0.065	40		
$C_6H_{12}N_4$	Hexamethylenetetramine	140.186	12	44.8		27		
$C_6H_{12}O$	1-Hexen-3-ol	100.158	25	2.52	25.9	1		
$C_6H_{12}O$	4-Hexen-2-ol	100.158	25	3.81	39.6	1		
$C_6H_{12}O$	Butyl vinyl ether	100.158	20	0.3	3	10		
$C_6H_{12}O$	2-Hexanone	100.158	20	1.51	17.8	20		
			81	1.15	11.6	20		
$C_6H_{12}O$	4-Methyl-2-pentanone	100.158	19	1.92	17	20		
			90	1.22	12.4	20		
$C_6H_{12}O$	3,3-Dimethyl-2-butanone	100.158	19	1.97	18.4	20		
			90	1.14	11.5	20		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
$C_6H_{12}O$	Cyclohexanol	100.158	10	4.62	48.4	1		
			25	3.8	40	1		
			40	3.30	34.1	1		
$C_6H_{12}O_2$	Hexanoic acid	116.158	20	0.96	9.6	26		
			60	1.16	11.7	26		
$C_6H_{12}O_2$	Isopentyl formate	116.158	22	0.3	3	27		
$C_6H_{12}O_2$	Butyl acetate	116.158	20	0.68	6.8	10		
$C_6H_{12}O_2$	*sec*-Butyl acetate	116.158	20	0.62	6.2	10		
$C_6H_{12}O_2$	Isobutyl acetate	116.158	20	0.63	6.3	10		
$C_6H_{12}O_2$	Propyl propanoate	116.158	25	0.6	6	27		
$C_6H_{12}O_2$	Ethyl butanoate	116.158	20	0.49	4.9	10		
$C_6H_{12}O_3$	2-Ethoxyethyl acetate	132.157		14	~165	30		
$C_6H_{12}O_3$	Tetrahydro-2,5-dimethoxyfuran	132.157	21	32		20		
			90	19	~235	20		
$C_6H_{12}O_3$	Paraldehyde	132.157	25	11	~125	30		
$C_6H_{12}O_6$	β-*D*-Fructose	180.155	20	~31	444	40		
$C_6H_{12}O_6$	*D*-Galactose	180.155	20	40.6		27		
$C_6H_{12}O_6$	α-*D*-Glucose	180.155	15	45.0		27		
			30	54.6		27		
			80	81.5		27		
$C_6H_{12}O_6$	*L*-Sorbose	180.155	17	~26	355	40		
$C_6H_{13}Br$	1-Bromohexane	165.071	25	0.00258	0.0258	35		
$C_6H_{13}Cl$	1-Chlorohexane	120.620	5	0.0047	0.047	35		
			25	0.0064	0.064	35		
$C_6H_{13}NO_2$	*L*-Leucine	131.173	25	2.15	22.0	26		
$C_6H_{13}NO_2$	*L*-Isoleucine	131.173	25	3.31	34.2	26		
$C_6H_{13}NO_2$	*L*-Norleucine	131.173	25	1.5	15	26		
$C_6H_{13}NO_2$	6-Aminohexanoic acid	131.173	25	46		29		
$C_6H_{13}NO_2$	Ethyl *N*-propylcarbamate	131.173	15	7.70	83.4	27		
C_6H_{14}	Hexane	86.175	25	0.0011	0.011	3	183	13
			60	0.00136	0.0136	3		
C_6H_{14}	2-Methylpentane	86.175	25	0.00137	0.0137	3	176	13
C_6H_{14}	3-Methylpentane	86.175	25	0.00129	0.0129	3	170	13
C_6H_{14}	2,2-Dimethylbutane	86.175	25	0.0021	0.021	3	199	13
C_6H_{14}	2,3-Dimethylbutane	86.175	25	0.0021	0.021	3	144	13
$C_6H_{14}N_2O_2$	*L*-Lysine	146.187	25	0.58	5.8	26		
$C_6H_{14}N_4O_2$	*L*-Arginine	174.201	25	15.44	~185	26		
$C_6H_{14}O$	2-Methoxy-2-methylbutane	102.174	20	1.10	12.7	20		
			79	0.36	3.6	20		
$C_6H_{14}O$	1-Hexanol	102.174	0	0.79	7.9	1		
			25	0.60	6.0	1		
			50	0.51	5.1	1		
$C_6H_{14}O$	2-Hexanol	102.174	25	1.4	14	1		
$C_6H_{14}O$	3-Hexanol	102.174	25	1.6	16	1		
$C_6H_{14}O$	2-Methyl-1-pentanol	102.174	25	0.81	8.1	1		
$C_6H_{14}O$	4-Methyl-1-pentanol	102.174	25	0.76	7.6	1		
$C_6H_{14}O$	2-Methyl-2-pentanol	102.174	25	3.2	33	1		
$C_6H_{14}O$	3-Methyl-2-pentanol	102.174	25	1.9	19	1		
$C_6H_{14}O$	4-Methyl-2-pentanol	102.174	27	1.5	15	1		
$C_6H_{14}O$	2-Methyl-3-pentanol	102.174	25	2.0	20	1		
$C_6H_{14}O$	3-Methyl-3-pentanol	102.174	25	4.3	45	1		
$C_6H_{14}O$	2-Ethyl-1-butanol	102.174	25	1.0	10	1		
$C_6H_{14}O$	2,2-Dimethyl-1-butanol	102.174	25	0.8	8	1		
$C_6H_{14}O$	2,3-Dimethyl-2-butanol	102.174	25	4.2	44	1		
$C_6H_{14}O$	3,3-Dimethyl-2-butanol, (±)-	102.174	25	2.4	25	1		
$C_6H_{14}O$	Dipropyl ether	102.174	25	0.49	4.9	10	0.26	13
$C_6H_{14}O$	Diisopropyl ether	102.174	20	0.79	12	20	0.26	13
			61	0.22	2.2	20		

Mol. formula	Name	Mol. wt.	t/°C	Solubility S Mass%	Solubility S g/L	Solubility S Ref.	Henry Const. k_H kPa m³mol⁻¹	Henry Const. k_H Ref.
$C_6H_{14}O$	Butyl ethyl ether	102.174	20	0.65	6.5	20		
			70	0.39	3.9	20		
$C_6H_{14}O_2$	1,1-Diethoxyethane	118.174	25	5	5	10		
$C_6H_{14}O_2$	1,2-Diethoxyethane	118.174	20	21.0		10		
$C_6H_{14}O_6$	*D*-Glucitol	182.171	20	~41	~689	40		
$C_6H_{14}O_6$	*D*-Mannitol	182.171	25	17.7	~215	27		
$C_6H_{15}N$	Dipropylamine	101.190	20	2.5	26	10		
$C_6H_{15}N$	Triethylamine	101.190	20	5.5	58	10		
$C_6H_{16}ClN$	Triethylamine hydrochloride	137.651	25	57.8		27		
$C_6H_{16}N_2$	1,6-Hexanediamine	116.204	5	~42	~711	40		
C_7F_{16}	Perfluoroheptane	388.049	25	0.0000013	0.000013	35		
$C_7H_3Br_2NO$	3,5-Dibromo-4-hydroxybenzonitrile	276.913	25	0.013	0.13	40		
$C_7H_3N_3O_8$	2,4,6-Trinitrobenzoic acid	257.114	23	1.97	20.1	40		
$C_7H_4ClNO_4$	3-Chloro-2-nitrobenzoic acid	201.565	25	0.047	0.47	27		
$C_7H_4ClNO_4$	5-Chloro-2-nitrobenzoic acid	201.565	25	0.96	9.6	27		
$C_7H_4Cl_4O$	2,3,4,6-Tetrachloro-5-methylphenol	245.918	25	0.00061	0.0061	2		
$C_7H_4N_2O_6$	3,5-Dinitrobenzoic acid	212.116	25	0.134	1.34	27		
$C_7H_4O_6$	4-Oxo-4*H*-pyran-2,6-dicarboxylic acid	184.103	25	1.45	14.7	27		
$C_7H_4O_7$	3-Hydroxy-4-oxo-4*H*-pyran-2,6-dicarboxylic acid	200.103	25	0.84	8.4	27		
$C_7H_5BrO_2$	2-Bromobenzoic acid	201.018	25	0.185	1.85	27		
$C_7H_5BrO_2$	3-Bromobenzoic acid	201.018	25	0.040	0.40	27		
$C_7H_5BrO_2$	4-Bromobenzoic acid	201.018	25	0.0056	0.056	27		
$C_7H_5ClO_2$	2-Chlorobenzoic acid	156.567	25	0.209	2.09	27		
$C_7H_5ClO_2$	3-Chlorobenzoic acid	156.567	25	0.040	0.40	27		
$C_7H_5ClO_2$	4-Chlorobenzoic acid	156.567	25	0.072	0.72	27		
$C_7H_5Cl_2NO_2$	3-Amino-2,5-dichlorobenzoic acid	206.027	25	0.070	0.70	40		
$C_7H_5Cl_3$	(Trichloromethyl)benzene	195.474	5	0.0053	0.053	10		
$C_7H_5Cl_3O$	2,4,6-Trichloro-3-methylphenol	211.473	25	0.0112	0.112	2		
$C_7H_5FO_2$	2-Fluorobenzoic acid	140.112	25	0.72	7.2	27		
$C_7H_5FO_2$	3-Fluorobenzoic acid	140.112	25	0.15	1.5	27		
$C_7H_5FO_2$	4-Fluorobenzoic acid	140.112	25	0.12	1.2	27		
$C_7H_5IO_2$	2-Iodobenzoic acid	248.018	25	0.095	0.95	27		
$C_7H_5IO_2$	3-Iodobenzoic acid	248.018	25	0.016	0.16	27		
$C_7H_5IO_2$	4-Iodobenzoic acid	248.018	25	0.0027	0.027	27		
C_7H_5N	Benzonitrile	103.122	25	0.2	2	10		
C_7H_5NO	Benzoxazole	119.121	20	0.834	8.34	6		
$C_7H_5NO_3$	3-Nitrobenzaldehyde	151.120	25	0.16	1.6	27		
$C_7H_5NO_3$	4-Nitrobenzaldehyde	151.120	25	0.23	2.3	27		
$C_7H_5NO_3S$	Saccharin	183.185	25	0.40	4.0	27		
			100	4.0	42	27		
$C_7H_5NO_4$	2-Nitrobenzoic acid	167.120	25	0.55	5.58	40		
$C_7H_5NO_4$	3-Nitrobenzoic acid	167.120	25	0.256	2.56	40		
$C_7H_5NO_4$	4-Nitrobenzoic acid	167.120	25	0.0422	0.422	40		
$C_7H_5N_3O_6$	2,4,6-Trinitrotoluene	227.131	20	0.012	0.12	40		
			100	0.15	1.5	40		
$C_7H_5N_5O_8$	*N*-Methyl-*N*,2,4,6-tetranitroaniline	287.144	20	0.0074	0.074	40		
$C_7H_6ClN_3O_4S_2$	Chlorothiazide	295.724	25	0.0283	0.283	40		
$C_7H_6Cl_2$	(Dichloromethyl)benzene	161.029	30	0.025	0.25	10		
$C_7H_6Cl_2O$	2,4-Dichloro-6-methylphenol	177.028	25	0.0283	0.283	2		
$C_7H_6Cl_2O$	2,6-Dichloro-4-methylphenol	177.028	25	0.0673	0.673	2		
$C_7H_6N_2$	1*H*-Benzimidazole	118.136	20	0.201	2.01	6		
$C_7H_6N_2$	1*H*-Indazole	118.136	20	0.0827	0.827	6		
$C_7H_6N_2O_4$	1-Methyl-2,4-dinitrobenzene	182.134	20	0.0271	0.271	40		
$C_7H_6N_2O_5$	2-Methyl-4,6-dinitrophenol	198.133	15	0.0130	0.130	40		
C_7H_6O	Benzaldehyde	106.122	20	0.3	3	10		
$C_7H_6O_2$	Benzoic acid	122.122	25	0.34	3.4	27		
			95	6.4	68	26		

				Solubility S			Henry Const. k_H	
Mol. formula	Name	Mol. wt.	t/°C	Mass%	g/L	Ref.	kPa m^3mol^{-1}	Ref.
$C_7H_6O_2$	Salicylaldehyde	122.122	86	1.68	17.0	10		
$C_7H_6O_2$	4-Hydroxybenzaldehyde	122.122	30	1.27	12.9	40		
$C_7H_6O_3$	2-Hydroxybenzoic acid	138.121	25	0.2550	2.550	33		
			50	0.5665	5.665	33		
$C_7H_6O_3$	4-Hydroxybenzoic acid	138.121	15	0.8	8	26		
			75	2.5	26	27		
$C_7H_6O_4$	3,4-Dihydroxybenzoic acid	154.121	14	1.8	18	26		
			80	21.3		26		
$C_7H_6O_5$	3,4,5-Trihydroxybenzoic acid	170.120	15	0.94	9.4	27		
			100	25.0		27		
C_7H_7Br	4-Bromotoluene	171.035	25	0.011	0.11	2		
C_7H_7Cl	4-Chlorotoluene	126.584	20	0.0137	0.137	40		
C_7H_7Cl	(Chloromethyl)benzene	126.584	20	0.0493	0.493	10		
C_7H_7ClO	2-Chloro-6-methylphenol	142.583	25	0.36	3.6	2		
C_7H_7ClO	4-Chloro-2-methylphenol	142.583	25	0.68	6.8	2		
C_7H_7ClO	4-Chloro-3-methylphenol	142.583	25	0.40	4.0	2		
C_7H_7NO	Benzamide	121.137	12	0.577	5.77	27		
$C_7H_7NO_2$	2-Hydroxybenzamide	137.137	15	0.145	1.45	40		
$C_7H_7NO_2$	Aniline-2-carboxylic acid	137.137	20	0.349	3.49	40		
$C_7H_7NO_2$	Aniline-4-carboxylic acid	137.137	25	0.54	5.39	40		
$C_7H_7NO_2$	2-Nitrotoluene	137.137	30	0.065	0.65	27		
$C_7H_7NO_2$	3-Nitrotoluene	137.137	30	0.050	0.50	27		
$C_7H_7NO_2$	4-Nitrotoluene	137.137	30	0.044	0.44	27		
$C_7H_7NO_3$	4-Amino-2-hydroxybenzoic acid	153.136	20	0.20	2.0	40		
$C_7H_7NO_3$	2-Nitroanisole	153.136	30	0.169	1.69	10		
$C_7H_7NO_3$	4-Nitroanisole	153.136	30	0.059	0.59	27		
C_7H_8	Toluene	92.139	25	0.053	0.531	22	0.660	22
			90	0.12	1.2	22		
C_7H_8	1,3,5-Cycloheptatriene	92.139	25	0.064	0.64	3	0.47	13
C_7H_8	1,6-Heptadiyne	92.139	25	0.125	1.25	3		
$C_7H_8ClN_3O_4S_2$	Hydrochlorothiazide	297.740	25	0.007	0.07	40		
$C_7H_8N_2S$	Phenylthiourea	152.217	25	2.55	26.1	27		
$C_7H_8N_4O_2$	Theophylline	180.165	20	0.52	5.2	29		
C_7H_8O	*o*-Cresol	108.138	40	3.08	31.8	10		
C_7H_8O	*m*-Cresol	108.138	40	2.51	25.8	10		
C_7H_8O	*p*-Cresol	108.138	40	2.26	23.1	10		
C_7H_8O	Benzyl alcohol	108.138	20	0.08	0.8	10		
C_7H_8O	Anisole	108.138	20	0.203	2.0	20	0.025	13
			81	0.294	2.9	20	0.025	13
$C_7H_8O_2$	4-Methoxyphenol	124.138	20	2.51	25.7	40		
$C_7H_8O_3S$	*p*-Toluenesulfonic acid	172.202	40	~33	500	40		
C_7H_9N	2-Methylaniline	107.153	20	1.66	16.9	10		
C_7H_9N	4-Methylaniline	107.153	21	7.35	79.3	10		
C_7H_9N	*N*-Methylaniline	107.153	25	0.56	5.62	40		
C_7H_9NO	2-Methoxyaniline	123.152	25	1.24	12.6	40		
C_7H_9NO	4-Methoxyaniline	123.152	20	1.14	11.5	40		
$C_7H_9NO_2S$	2-Methylbenzenesulfonamide	171.217	25	0.162	1.62	27		
$C_7H_9NO_2S$	3-Methylbenzenesulfonamide	171.217	25	0.78	7.8	27		
$C_7H_9NO_2S$	4-Methylbenzenesulfonamide	171.217	25	0.316	3.16	27		
$C_7H_{10}N_2OS$	2,3-Dihydro-6-propyl-2-thioxo-4(1*H*)-pyrimidinone	170.231	25	0.120	1.20	40		
$C_7H_{10}O_5$	Shikimic acid	174.151		15	~175	26		
C_7H_{12}	1-Heptyne	96.170	25	0.0094	0.094	3	4.47	13
C_7H_{12}	Cycloheptene	96.170	25	0.0066	0.066	3	4.9	13
C_7H_{12}	1-Methylcyclohexene	96.170	25	0.0052	0.052	3		
$C_7H_{12}O$	Cycloheptanone	112.169	20	3.61	37	20		
			92	2.82	29	20		
$C_7H_{12}O$	2-Methylcyclohexanone, (±)-	112.169	20	1.98	20.2	20		

Mol. formula	Name	Mol. wt.	*t*/°C	Solubility *S* Mass%	Solubility *S* g/L	Solubility *S* Ref.	Henry Const. k_H kPa m³mol⁻¹	Henry Const. k_H Ref.
			90	1.54	15.6	20		
$C_7H_{12}O$	4-Methylcyclohexanone	112.169	20	2.43	25	20		
			80	1.95	19.9	20		
$C_7H_{12}O_2$	Cyclohexanecarboxylic acid	128.169	15	0.201	2.01	27		
$C_7H_{12}O_4$	Heptanedioic acid	160.168	25	6.347	67.77	33		
			50	42.80		33		
$C_7H_{12}O_4$	Diethyl malonate	160.168	20	2.26	23.2	20		
			91	2.47	25	20		
$C_7H_{12}O_6$	Quinic acid	192.166	9	29		26		
$C_7H_{13}N_3O_3S$	Oxamyl	219.261	25	~21	280	40		
C_7H_{14}	1-Heptene	98.186	25	0.032	0.32	3	40.3	13
C_7H_{14}	*trans*-2-Heptene	98.186	25	0.015	0.15	3	42.2	13
C_7H_{14}	Cycloheptane	98.186	25	0.0030	0.030	3	9.59	13
C_7H_{14}	Methylcyclohexane	98.186	25	0.00151	0.0151	3	43.3	13
			50	0.0019	0.019	3		
C_7H_{14}	Ethylcyclopentane	98.186	20	0.012	0.12	3		
$C_7H_{14}N_2O_2S$	Aldicarb	190.263	20	0.60	6.02	40		
$C_7H_{14}O$	Heptanal	114.185	11	0.124	1.24	27		
$C_7H_{14}O$	2-Heptanone	114.185	25	0.435	4.3	20	0.0171	28
			90	0.353	3.53	20	0.0171	28
$C_7H_{14}O$	3-Heptanone	114.185	20	0.479	4.8	20		
			90	0.309	3.1	20		
$C_7H_{14}O$	4-Heptanone	114.185	20	0.457	4.57	20		
			90	0.316	3.16	20		
$C_7H_{14}O$	5-Methyl-2-hexanone	114.185	19	0.537	5.40	20		
			90	0.417	4.19	20		
$C_7H_{14}O$	5-Methyl-3-hexanone	114.185	20	0.47	4.7	20		
			81	0.32	3.2	20		
$C_7H_{14}O$	2,4-Dimethyl-3-pentanone	114.185	20	0.52	5.9	20		
			90	0.30	3.0	20		
$C_7H_{14}O_2$	Ethyl 2-methylbutanoate, (+)	130.185	19	0.257	2.58	20		
			91	0.151	1.51	20		
$C_7H_{14}O_2$	Heptanoic acid	130.185	15	0.24	2.4	27		
$C_7H_{14}O_2$	Pentyl acetate	130.185	20	0.17	1.7	10		
$C_7H_{14}O_2$	Isopentyl acetate	130.185	20	0.2	2	10		
$C_7H_{14}O_2$	*sec*-Pentyl acetate (*S*)-	130.185	25	0.2	2	27		
$C_7H_{14}O_2$	Butyl propanoate	130.185	22	0.572	5.72	27		
$C_7H_{14}O_2$	Isobutyl propanoate	130.185	19	0.225	2.26	20		
			91	0.142	1.42	20		
$C_7H_{14}O_2$	Propyl butanoate	130.185	17	0.162	1.62	27		
$C_7H_{14}O_2$	Ethyl pentanoate	130.185	25	0.3	3	27		
$C_7H_{14}O_2$	Ethyl 3-methylbutanoate	130.185	20	0.2	2	10		
$C_7H_{15}Br$	1-Bromoheptane	179.098	25	0.00067	0.0067	35		
$C_7H_{15}Cl$	1-Chloroheptane	134.647	25	0.00136	0.0136	35		
$C_7H_{15}I$	1-Iodoheptane	226.098	25	0.00035	0.0035	35		
C_7H_{16}	Heptane	100.202	0	0.0003	0.003	3		
			25	0.00024	0.0024	3	209	13
			40	0.00025	0.0025	3		
C_7H_{16}	2-Methylhexane	100.202	25	0.00025	0.0025	3	346	5
C_7H_{16}	3-Methylhexane	100.202	25	0.00026	0.0026	3	249	13
C_7H_{16}	2,2-Dimethylpentane	100.202	25	0.00044	0.0044	3	318	5
C_7H_{16}	2,3-Dimethylpentane	100.202	25	0.00052	0.0052	3	175	5
C_7H_{16}	2,4-Dimethylpentane	100.202	25	0.00042	0.0042	3	323	13
C_7H_{16}	3,3-Dimethylpentane	100.202	25	0.00059	0.0059	3	186	5
$C_7H_{16}O$	1-Heptanol	116.201	10	0.25	2.5	1		
			25	0.174	1.74	1	0.00562	28
			50	0.12	1.2	1		
$C_7H_{16}O$	2-Heptanol, (±)-	116.201	30	0.33	3.3	1		

				Solubility S			Henry Const. k_H	
Mol. formula	Name	Mol. wt.	t/°C	Mass%	g/L	Ref.	kPa m^3mol^{-1}	Ref.
$C_7H_{16}O$	3-Heptanol, (*S*)-	116.201	25	0.43	4.3	1		
$C_7H_{16}O$	4-Heptanol	116.201	25	0.47	4.7	1		
$C_7H_{16}O$	2-Methyl-2-hexanol	116.201	25	1.0	10	1		
$C_7H_{16}O$	5-Methyl-2-hexanol	116.201	25	0.49	4.9	1		
$C_7H_{16}O$	3-Methyl-3-hexanol	116.201	25	1.2	12	1		
$C_7H_{16}O$	3-Ethyl-3-pentanol	116.201	25	1.7	17	1		
$C_7H_{16}O$	2,3-Dimethyl-2-pentanol	116.201	25	1.5	15	1		
$C_7H_{16}O$	2,4-Dimethyl-2-pentanol	116.201	25	1.3	13	1		
$C_7H_{16}O$	2,2-Dimethyl-3-pentanol	116.201	25	0.82	8.2	1		
$C_7H_{16}O$	2,3-Dimethyl-3-pentanol	116.201	25	1.6	16	1		
$C_7H_{16}O$	2,4-Dimethyl-3-pentanol	116.201	25	0.70	7.0	1		
$C_7H_{16}O$	2,3,3-Trimethyl-2-butanol	116.201	40	2.2	22	1		
$C_8Cl_4N_2$	Chlorothalonil	265.911	25	0.00006	0.0006	40		
C_8F_{18}	Perfluorooctane	438.057	25	0.00000017	0.0000017	35		
$C_8H_4F_6$	1,3-Bis(trifluoromethyl)benzene	214.108	25	0.0041	0.041	2		
$C_8H_4O_3$	Phthalic anhydride	148.116	27	0.62	6.20	40		
$C_8H_5Cl_3O_3$	2,4,5-Trichlorophenoxyacetic acid	255.483	25	0.028	0.28	40		
$C_8H_5NO_2$	1*H*-Isoindole-1,3(2*H*)-dione	147.132	25	0.036	0.36	40		
$C_8H_6Cl_2O_3$	(2,4-Dichlorophenoxy)acetic acid	221.038	25	0.07	0.7	40		
$C_8H_6Cl_2O_3$	3,6-Dichloro-2-methoxybenzoic acid	221.038	25	0.45	4.5	40		
$C_8H_6N_2$	Quinoxaline	130.147	50	54		6		
$C_8H_6N_4O_5$	Nitrofurantoin	238.158	30	0.011	0.11	40		
$C_8H_6O_3$	1,3-Benzodioxole-5-carboxaldehyde	150.132	20	0.35	3.5	40		
$C_8H_6O_4$	Phthalic acid	166.132	25	0.6977	6.977	33		
			65	3.575	37.08	33		
$C_8H_6O_4$	Isophthalic acid	166.132	25	0.013	0.13	27		
C_8H_6S	Benzo[b]thiophene	134.199	20	0.0130	0.130	6		
$C_8H_7ClO_3$	2-Chloro-4-hydroxy-5-methoxybenzaldehyde	186.593	25	0.013	0.13	8		
$C_8H_7ClO_3$	3-Chloro-4-hydroxy-5-methoxybenzaldehyde	186.593	25	0.093	0.93	8		
$C_8H_7Cl_3O$	2,4,6-Trichloro-3,5-dimethylphenol	225.500	25	0.00050	0.0050	2		
C_8H_7N	1*H*-Indole	117.149	20	0.187	1.87	6		
C_8H_8	Styrene	104.150	25	0.0321	0.321	22	0.286	22
			50	0.046	0.46	4	0.30	13
$C_8H_8Cl_3O_3PS$	Ronnel	321.546	20	0.00011	0.0011	40		
$C_8H_8F_3N_3O_4S_2$	Hydroflumethiazide	331.293	37	0.068	0.68	40		
$C_8H_8HgO_2$	Mercury(II) phenyl acetate	336.74	20	0.2	2	30		
$C_8H_8N_2$	2-Methyl-1*H*-benzimidazole	132.163	20	0.145	1.45	6		
$C_8H_8N_2O_2$	1,2-Benzenedicarboxamide	164.162	30	0.59	5.9	40		
C_8H_8O	Acetophenone	120.149	25	0.55	5.5	28	0.00108	28
			80	1.204	12.2	20		
$C_8H_8O_2$	*o*-Toluic acid	136.149	25	0.118	1.18	27		
$C_8H_8O_2$	*m*-Toluic acid	136.149	25	0.098	0.98	27		
$C_8H_8O_2$	*p*-Toluic acid	136.149	25	0.345	3.45	27		
$C_8H_8O_2$	Benzeneacetic acid	136.149	25	1.71	17.4	27		
$C_8H_8O_2$	Benzyl formate	136.149	20	1.07	10.8	20		
			80	1.43	14.5	20		
$C_8H_8O_2$	Phenyl acetate	136.149	20	0.59	5.9	20		
			91	0.91	9.2	20		
$C_8H_8O_2$	Methyl benzoate	136.149	20	0.21	2.1	10		
$C_8H_8O_2$	4-Methoxybenzaldehyde	136.149	25	0.429	4.29	40		
$C_8H_8O_3$	Methyl 4-hydroxybenzoate	152.148	25	0.24	2.4	40		
$C_8H_8O_3$	4-Methoxybenzoic acid	152.148	25	0.023	0.23	27		
$C_8H_8O_3$	α-Hydroxybenzeneacetic acid, (±)-	152.148	25	11.3	~125	27		
$C_8H_8O_3$	Methyl salicylate	152.148	30	0.74	7.4	10		
$C_8H_8O_3$	4-Hydroxy-3-methoxybenzaldehyde	152.148	25	0.247	2.47	8		
C_8H_9ClO	4-Chloro-2,5-dimethylphenol	156.609	25	0.89	8.9	2		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
C_8H_9ClO	4-Chloro-2,6-dimethylphenol	156.609	25	0.52	5.2	2		
C_8H_9ClO	4-Chloro-3,5-dimethylphenol	156.609	25	0.34	3.4	2		
C_8H_9NO	Acetanilide	135.163	20	0.52	5.2	27		
			70	2.7	28	27		
$C_8H_9NO_2$	*N*-(4-Hydroxyphenyl)acetamide	151.163	25	1.3	13	40		
C_8H_{10}	Ethylbenzene	106.165	0	0.020	0.20	4		
			25	0.0161	0.161	22	0.843	22
			40	0.0200	0.200	4		
C_8H_{10}	*o*-Xylene	106.165	25	0.0171	0.171	22	0.551	22
			45	0.021	0.21	4		
C_8H_{10}	*m*-Xylene	106.165	0	0.0203	0.203	4		
			25	0.0161	0.161	22	0.730	22
			40	0.022	0.22	4		
C_8H_{10}	*p*-Xylene	106.165	0	0.0160	0.160	4		
			25	0.0181	0.181	22	0.690	22
			40	0.022	0.22	4		
$C_8H_{10}NO_5PS$	Methyl parathion	263.208	10	0.00218	0.0218	40		
			20	0.00380	0.0380	40		
			30	0.0059	0.059	40		
$C_8H_{10}N_4O_2$	Caffeine	194.191	25	2.12	21.7	29		
$C_8H_{10}O$	4-Ethylphenol	122.164	20	0.59	5.9	40		
$C_8H_{10}O$	2,3-Xylenol	122.164	25	0.457	4.57	40		
$C_8H_{10}O$	2,4-Xylenol	122.164	25	0.787	7.87	10		
$C_8H_{10}O$	2,5-Xylenol	122.164	25	0.354	3.54	40		
$C_8H_{10}O$	2,6-Xylenol	122.164	25	0.60	6.05	40		
$C_8H_{10}O$	3,4-Xylenol	122.164	25	0.477	4.77	40		
$C_8H_{10}O$	3,5-Xylenol	122.164	29	0.62	6.2	10		
$C_8H_{10}O$	Benzeneethanol	122.164	25	1.72	17.5	40		
$C_8H_{10}O$	Ethoxybenzene	122.164	25	0.12	1.2	10		
$C_8H_{10}O_2$	2-Phenoxyethanol	138.164	20	2.53	26.0	40		
$C_8H_{10}O_2$	1,2-Dimethoxybenzene	138.164	20	0.716	7.21	20		
			92	1.073	10.9	20		
$C_8H_{11}N$	*N,N*-Dimethylaniline	121.180	25	0.111	1.11	40		
$C_8H_{11}N$	2,5-Dimethylaniline	121.180	20	0.66	6.6	27		
$C_8H_{11}NO$	4-(2-Aminoethyl)phenol	137.179	15	1.03	10.4	40		
C_8H_{12}	4-Vinylcyclohexene	108.181	25	0.005	0.05	4		
$C_8H_{12}O_2$	1,2-Epoxy-4-(epoxyethyl)cyclohexane	140.180	20	13.4	155	40		
$C_8H_{12}O_4$	Diethyl maleate	172.179	20	1.56	15.9	20		
			91	1.75	17.8	20		
C_8H_{14}	1-Octyne	110.197	25	0.0024	0.024	4	7.87	13
$C_8H_{14}ClN_5$	Atrazine	215.684	25	0.007	0.07	26		
$C_8H_{14}O_4$	Octanedioic acid	174.195	25	0.2416	2.416	34		
			50	0.5570	5.570	34		
$C_8H_{14}O_4$	Diethyl succinate	174.195	20	0.19	1.9	40		
$C_8H_{15}N_3O_7$	Streptozotocin	265.221	25	0.50	5.07	40		
C_8H_{16}	1-Octene	112.213	25	0.00027	0.0027	4	96.3	13
C_8H_{16}	Cyclooctane	112.213	25	0.00079	0.0079	4	10.7	13
C_8H_{16}	Ethylcyclohexane	112.213	40	0.00066	0.0066	4		
C_8H_{16}	*cis*-1,2-Dimethylcyclohexane	112.213	25	0.00060	0.0060	4	36	5
C_8H_{16}	*trans*-1,4-Dimethylcyclohexane	112.213	25	0.000384	0.00384	4	88.2	5
C_8H_{16}	Propylcyclopentane	112.213	25	0.00020	0.0020	4	90.2	5
C_8H_{16}	1,1,3-Trimethylcyclopentane	112.213	25	0.00037	0.0037	4	159	5
$C_8H_{16}N_2O_4S_2$	Homocystine	268.354	25	0.02	0.2	26		
$C_8H_{16}O$	2-Octanone	128.212	25	0.113	1.13	10		
			91	0.094	0.94	20		
$C_8H_{16}O$	3-Octanone	128.212	20	0.137	1.37	20		
			91	0.106	1.06	20		
$C_8H_{16}O$	5-Methyl-3-heptanone	128.212	20	0.192	1.92	20		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
			90	0.131	1.31	20		
$C_8H_{16}O_2$	Octanoic acid	144.212	25	0.080	0.80	26		
$C_8H_{16}O_2$	Hexyl acetate	144.212	20	0.02	0.2	10		
$C_8H_{16}O_2$	*sec*-Hexyl acetate	144.212	20	0.13	1.3	10		
$C_8H_{16}O_2$	Pentyl propanoate	144.212	20	0.1	1	27		
$C_8H_{16}O_2$	Isobutyl isobutanoate	144.212	20	0.5	5	10		
$C_8H_{16}O_2$	Ethyl hexanoate	144.212	20	0.063	0.63	27		
$C_8H_{17}Br$	1-Bromooctane	193.125	25	0.000167	0.00167	35		
$C_8H_{17}Cl$	1-Chlorooctane	148.674	25	0.0345	0.345	35		
$C_8H_{17}Cl$	3-(Chloromethyl)heptane	148.674	20	0.01	0.1	10		
C_8H_{18}	Octane	114.229	25	0.000071	0.00071	4	311	13
			50	0.00010	0.0010	4		
C_8H_{18}	3-Methylheptane, (*S*)-	114.229	25	0.000079	0.00079	4	376	5
C_8H_{18}	2,2,4-Trimethylpentane	114.229	25	0.00022	0.0022	4	307	13
C_8H_{18}	2,3,4-Trimethylpentane	114.229	25	0.00018	0.0018	4	206	13
$C_8H_{18}O$	1-Octanol	130.228	25	0.054	0.54	1		
$C_8H_{18}O$	2-Octanol	130.228	25	0.4	4	1		
$C_8H_{18}O$	2-Methyl-2-heptanol	130.228	30	0.25	2.5	1		
$C_8H_{18}O$	2-Ethyl-1-hexanol	130.228	25	0.01	0.1	1		
$C_8H_{18}O$	Dibutyl ether	130.228	20	0.023	0.3	20	0.48	13
			90	0.010	0.10	20		
$C_8H_{19}N$	Dibutylamine	129.244	20	0.47	4.7	10		
$C_8H_{19}N$	2-Ethylhexylamine	129.244	20	0.25	2.5	10		
$C_8H_{20}Si$	Tetraethylsilane	144.331	25	0.0000325	0.000325	10		
$C_9H_4Cl_3NO_2S$	Folpet	296.558	20	0.00010	0.0010	40		
$C_9H_5Cl_3N_4$	Anilazine	275.522	20	0.001	0.01	40		
$C_9H_6Cl_2N_2O_3$	Methazole	261.061	24	0.00015	0.0015	40		
$C_9H_6O_2$	2*H*-1-Benzopyran-2-one	146.143	20	0.190	1.90	40		
			60	0.69	6.95	40		
$C_9H_7BrO_4$	2-(Acetyloxy)-5-bromobenzoic acid	259.054		0.07	0.7	30		
$C_9H_7Cl_3O_3$	Silvex	269.509	25	0.014	0.14	40		
C_9H_7N	Quinoline	129.159	20	0.633	6.33	6		
C_9H_7N	Isoquinoline	129.159	20	0.452	4.52	6		
C_9H_7NO	8-Quinolinol	145.158	25	0.065	0.65	40		
$C_9H_8Cl_2O_3$	2-(2,4-Dichlorophenoxy)propanoic acid	235.064	25	0.083	0.83	40		
$C_9H_8Cl_3NO_2S$	Captan	300.590	20	0.00005	0.0005	40		
C_9H_8O	*trans*-Cinnamaldehyde	132.159	25	0.135	1.35	40		
$C_9H_8O_2$	*trans*-Cinnamic acid	148.159	20	0.1	1	26		
			98	0.59	5.9	26		
$C_9H_8O_4$	2-(Acetyloxy)benzoic acid	180.158		0.25	2.5	27		
$C_9H_9ClO_3$	(4-Chloro-2-methylphenoxy)acetic acid	200.618	25	0.117	1.17	40		
$C_9H_9Cl_2NO$	Propanil	218.079	20	0.013	0.13	40		
$C_9H_9I_2NO_3$	3,5-Diiodo-*L*-tyrosine	432.981	25	0.062	0.62	26		
C_9H_9N	3-Methyl-1*H*-indole	131.174	20	0.050	0.50	6		
$C_9H_9NO_3$	*N*-Benzoylglycine	179.172	25	0.37	3.7	29		
$C_9H_9N_3O_2S_2$	Sulfathiazole	255.316	20	0.048	0.48	40		
C_9H_{10}	Isopropenylbenzene	118.175	20	0.0116	0.116	40		
C_9H_{10}	Indan	118.175	25	0.010	0.10	4		
$C_9H_{10}Cl_2N_2O$	Diuron	233.093	25	0.0042	0.042	40		
$C_9H_{10}Cl_2N_2O_2$	Linuron	249.093	25	0.0075	0.075	40		
$C_9H_{10}O$	1-Phenyl-1-propanone	134.174	19	0.32	3.2	20		
			80	0.24	2.4	20		
$C_9H_{10}O_2$	Ethyl benzoate	150.174	25	0.083	0.83	20		
$C_9H_{10}O_2$	Benzyl acetate	150.174	25	0.150	1.50	40		
$C_9H_{10}O_3$	Ethyl 4-hydroxybenzoate	166.173	25	0.0080	0.080	40		
$C_9H_{11}ClN_2O$	*N'*-(4-Chlorophenyl)-*N,N*-dimethylurea	198.648	25	0.023	0.23	26		
$C_9H_{11}Cl_2N_3O_4S_2$	Methyclothiazide	360.237	20	0.005	0.05	40		
$C_9H_{11}Cl_3NO_3PS$	Chlorpyrifos	350.586	20	0.000073	0.00073	40		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
$C_9H_{11}NO_2$	*DL*-Phenylalanine	165.189	25	1.40	14.2	29		
$C_9H_{11}NO_2$	*L*-Phenylalanine	165.189	25	2.71	27.9	26		
$C_9H_{11}NO_3$	*DL*-Tyrosine	181.188	25	0.35	3.5	30		
$C_9H_{11}NO_3$	*L*-Tyrosine	181.188	25	0.046	0.46	26		
$C_9H_{11}NO_4$	Levodopa	197.188	25	62.3		26		
C_9H_{12}	1,8-Nonadiyne	120.191	25	0.0125	0.125	4		
C_9H_{12}	Propylbenzene	120.191	25	0.0052	0.052	22	1.041	22
C_9H_{12}	Isopropylbenzene	120.191	25	0.0050	0.050	22	1.466	22
C_9H_{12}	2-Ethyltoluene	120.191	25	0.0093	0.093	5	0.529	13
C_9H_{12}	4-Ethyltoluene	120.191	25	0.0094	0.094	5	0.500	13
C_9H_{12}	1,2,3-Trimethylbenzene	120.191	25	0.0070	0.070	22	0.343	22
C_9H_{12}	1,2,4-Trimethylbenzene	120.191	25	0.0057	0.057	22	0.569	22
C_9H_{12}	1,3,5-Trimethylbenzene	120.191	25	0.0050	0.050	22	0.781	22
$C_9H_{12}N_2O$	*N,N*-Dimethyl-*N'*-phenylurea	164.203	25	0.32	3.2	40		
$C_9H_{13}BrN_2O_2$	Bromacil	261.115	25	0.082	0.82	40		
$C_9H_{13}ClN_2O_2$	Terbacil	216.664	25	0.071	0.71	40		
$C_9H_{13}ClN_6$	Cyanazine	240.692	25	0.0171	0.171	40		
$C_9H_{13}NO_3$	Epinephrine	183.204	20	0.018	0.18	40		
$C_9H_{14}N_4O_3$	Carnosine	226.232	25	24.4		26		
$C_9H_{14}O$	Isophorone	138.206	20	1.57	16.0	20		
			80	1.27	12.9	20		
$C_9H_{14}O_6$	Glycerol triacetate	218.203	25	5.8	62	10		
C_9H_{16}	1-Nonyne	124.223	25	0.00072	0.0072	4		
$C_9H_{16}ClN_5$	Propazine	229.710	20	0.00086	0.0086	40		
$C_9H_{16}N_4OS$	Tebuthiuron	228.314	20	0.23	2.3	40		
$C_9H_{16}O_4$	Nonanedioic acid	188.221	25	0.1780	1.780	34		
			65	1.322	13.40	34		
$C_9H_{16}O_4$	Diethyl glutarate	188.221	30	1.20	12.2	20		
			91	0.91	9.2	20		
$C_9H_{17}N_5S$	Ametryn	227.330	20	0.0190	0.190	40		
C_9H_{18}	1-Nonene	126.239	25	0.000112	0.00112	40		
C_9H_{18}	1,1,3-Trimethylcyclohexane	126.239	25	0.000177	0.00177	4	105	13
$C_9H_{18}FeN_3S_6$	Ferbam	416.494	20	0.013	0.13	40		
$C_9H_{18}N_2O_4$	2-Methyl-2-propyl-1,3-propanediol dicarbamate	218.250	25	0.33	3.3	40		
$C_9H_{18}O$	2-Nonanone	142.238	20	0.038	0.38	20		
			70	0.034	0.34	20		
$C_9H_{18}O$	3-Nonanone	142.238	30	0.056	0.56	20		
			80	0.046	0.46	20		
$C_9H_{18}O$	5-Nonanone	142.238	20	0.054	0.54	20		
			80	0.029	0.29	20		
$C_9H_{18}O$	2,6-Dimethyl-4-heptanone	142.238	21	0.045	0.43	20		
			91	0.037	0.37	20		
$C_9H_{18}O_2$	Nonanoic acid	158.238	20	0.0284	0.284	26		
$C_9H_{18}O_2$	Ethyl heptanoate	158.238	20	0.029	0.29	27		
C_9H_{20}	Nonane	128.255	25	0.000017	0.00017	4	333	13
			50	0.000022	0.00022	4		
C_9H_{20}	4-Methyloctane	128.255	25	0.0000115	0.000115	4	1000	5
C_9H_{20}	2,2,5-Trimethylhexane	128.255	25	0.00008	0.0008	4	246	13
$C_9H_{20}O$	3,5-Dimethyl-4-heptanol	144.254	15	0.072	0.72	1		
$C_9H_{20}O$	1-Nonanol	144.254	25	0.014	0.14	1		
$C_9H_{20}O$	2-Nonanol, (±)-	144.254	15	0.026	0.26	1		
$C_9H_{20}O$	3-Nonanol, (±)-	144.254	15	0.032	0.32	1		
$C_9H_{20}O$	4-Nonanol	144.254	15	0.0026	0.026	1		
$C_9H_{20}O$	5-Nonanol	144.254	15	0.0032	0.032	1		
$C_{10}Cl_{10}O$	Kepone	490.636	100	0.4	4	40		
$C_{10}Cl_{12}$	Mirex	545.543	25	0.0000085	0.000085	40		
$C_{10}F_{22}$	Perfluorodecane	538.072	20	0.000031	0.00031	35		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
$C_{10}H_4Cl_2O_2$	2,3-Dichloro-1,4-naphthalenedione	227.044	25	0.00001	0.0001	40		
$C_{10}H_5Cl_7$	Heptachlor	373.318	25	0.0000056	0.000056	40		
$C_{10}H_6Cl_4O_4$	Dimethyl tetrachloroterephthalate	331.965	25	0.00005	0.0005	40		
$C_{10}H_6Cl_8$	Chlordane	409.779	25	0.000185	0.00185	40		
$C_{10}H_7Cl$	1-Chloronaphthalene	162.616	25	0.00224	0.0224	5	0.0363	28
$C_{10}H_7Cl$	2-Chloronaphthalene	162.616	25	0.00117	0.0117	5	0.0335	28
$C_{10}H_7NO_2$	1-Nitronaphthalene	173.169	18	0.005	0.05	40		
$C_{10}H_8$	Naphthalene	128.171	10	0.0019	0.019	4		
			25	0.00316	0.0316	22	0.043	22
			50	0.0082	0.082	4		
$C_{10}H_8N_2$	2,2'-Bipyridine	156.184	25	0.61	6.1	40		
$C_{10}H_8O$	1-Naphthol	144.170	20	0.111	1.11	40		
$C_{10}H_8O$	2-Naphthol	144.170	20	0.064	0.64	40		
			80	0.67	6.7	40		
$C_{10}H_9Cl_4NO_2S$	Captafol	349.061	20	0.000142	0.00142	40		
$C_{10}H_9N$	1-Naphthylamine	143.185	20	0.17	1.7	40		
$C_{10}H_9N$	2-Naphthylamine	143.185	20	0.0189	0.189	40		
$C_{10}H_9N$	3-Methylisoquinoline	143.185	20	0.092	0.92	6		
$C_{10}H_{10}Cl_2O_3$	4-(2,4-Dichlorophenoxy)butanoic acid	249.090	25	0.0046	0.046	40		
$C_{10}H_{10}O_4$	Dimethyl phthalate	194.184	25	0.40	4.0	15		
$C_{10}H_{10}O_4$	Dimethyl terephthalate	194.184	25	0.00328	0.0328	40		
$C_{10}H_{11}F_3N_2O$	*N,N*-Dimethyl-*N'*-[3-(trifluoromethyl) phenyl]urea	232.201	20	0.0105	0.105	40		
$C_{10}H_{11}N_3O_3S$	Sulfamethoxazole	253.277	25	0.0281	0.281	40		
$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene	132.202	20	0.0045	0.045	40		
$C_{10}H_{12}ClNO_2$	Chloropropham	213.661	25	0.0080	0.080	40		
$C_{10}H_{12}N_2O_3S$	Bentazon	240.278	20	0.050	0.50	40		
$C_{10}H_{12}N_3O_3PS_2$	Azinphos-methyl	317.324	20	0.00209	0.0209	40		
$C_{10}H_{12}N_4O_5$	Inosine	268.226	20	1.6	16	29		
$C_{10}H_{12}O_3$	Propyl 4-hydroxybenzoate	180.200	25	0.04	0.4	40		
$C_{10}H_{12}O_4$	Cantharidin	196.200	20	0.003	0.03	40		
$C_{10}H_{13}NO_2$	Isopropyl phenylcarbamate	179.216	20	0.01	0.1	40		
$C_{10}H_{13}NO_2$	*N*-(4-Ethoxyphenyl)acetamide	179.216	25	0.0502	0.502	40		
$C_{10}H_{13}N_5O_3$	2'-Deoxyadenosine	251.242	25	0.67	6.7	29		
$C_{10}H_{13}N_5O_4$	Adenosine	267.242	25	0.51	5.1	29		
$C_{10}H_{13}N_5O_5$	Guanosine	283.241	25	0.0500	0.500	29		
$C_{10}H_{14}$	Butylbenzene	134.218	25	0.00138	0.0138	22	1.33	22
$C_{10}H_{14}$	*sec*-Butylbenzene, (±)-	134.218	25	0.0014	0.014	4	1.89	11
$C_{10}H_{14}$	*tert*-Butylbenzene	134.218	25	0.0032	0.032	4	1.28	11
$C_{10}H_{14}$	Isobutylbenzene	134.218	25	0.0010	0.010	4	3.32	11
$C_{10}H_{14}$	1-Isopropyl-4-methylbenzene	134.218	25	0.0051	0.051	23	0.80	5
$C_{10}H_{14}$	*o*-Diethylbenzene	134.218	20	0.0071	0.071	40		
$C_{10}H_{14}$	*p*-Diethylbenzene	134.218	20	0.0025	0.025	40		
$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	134.218	25	0.000348	0.00348	4	2.55	11
$C_{10}H_{14}NO_5PS$	Parathion	291.261	20	0.00129	0.0129	40		
$C_{10}H_{14}N_2O_5$	Thymidine	242.228	25	5.1	54	29		
$C_{10}H_{14}O$	4-*tert*-Butylphenol	150.217	25	0.058	0.58	40		
$C_{10}H_{14}O$	Carvone, (±)-	150.217	15	0.13	1.3	27		
$C_{10}H_{14}O$	Thymol	150.217		0.1	1	30		
$C_{10}H_{15}NO$	*l*-Ephedrine	165.232	25	0.57	5.69	40		
$C_{10}H_{15}N_5O_5$	Vidarabine	285.257	20	0.051	0.51	40		
$C_{10}H_{16}$	*d*-Limonene	136.234	0	0.00097	0.0097	4		
			25	0.00138	0.0138	4		
$C_{10}H_{16}N_2O_3S$	Biotin	244.310	25	0.035	0.35	40		
$C_{10}H_{16}O$	Camphor, (+)	152.233	20	0.01	0.1	10		
$C_{10}H_{16}O$	Carvenone, (*S*)-	152.233	15	0.22	2.2	27		
$C_{10}H_{16}O_4$	*trans*-Camphoric acid, (±)-	200.232	25	0.8	8	27		
$C_{10}H_{18}$	*cis*-Decahydronaphthalene	138.250	25	0.000089	0.00089	37		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
$C_{10}H_{18}$	*trans*-Decahydronaphthalene	138.250	25	0.000089	0.00089	4	3	13
$C_{10}H_{18}O$	Borneol, (±)-	154.249	25	0.074	0.74	27		
$C_{10}H_{18}O$	α-Terpineol	154.249	15	0.20	2.0	27		
$C_{10}H_{18}O$	Eucalyptol	154.249	21	0.379	3.79	40		
			50	0.170	1.70	40		
$C_{10}H_{18}O_2$	Cyclohexyl butanoate	170.249	20	0.11	1.1	20		
			90	0.09	0.90	20		
$C_{10}H_{18}O_4$	Sebacic acid	202.248	20	0.10	1.0	40		
$C_{10}H_{19}N_5O$	Prometone	225.291	20	0.075	0.75	40		
$C_{10}H_{19}N_5S$	Prometryn	241.357	20	0.0048	0.048	32		
$C_{10}H_{20}$	1-Decene	140.266	25	0.00057	0.0057	4		
$C_{10}H_{20}$	Pentylcyclopentane	140.266	25	0.0000115	0.000115	4	185	5
$C_{10}H_{20}O$	4-Decanone	156.265	20	0.0238	0.238	20		
			80	0.0064	0.064	20		
$C_{10}H_{20}O_2$	Nonyl formate	172.265	10	0.012	0.12	20		
$C_{10}H_{20}O_2$	Hexyl butanoate	172.265	29	0.021	0.21	20		
			90	0.039	0.39	20		
$C_{10}H_{20}O_2$	Decanoic acid	172.265	20	0.015	0.15	26		
$C_{10}H_{20}O_2$	Octyl acetate	172.265	19	0.020	0.20	20		
			92	0.012	0.12	20		
$C_{10}H_{20}O_2$	Ethyl octanoate	172.265	20	0.007	0.07	27		
$C_{10}H_{22}$	Decane	142.282	0	0.0000015	0.000015	4	479	13
$C_{10}H_{22}O$	1-Decanol	158.281	25	0.0037	0.037	1		
$C_{10}H_{22}O$	Diisopentyl ether	158.281	20	0.02	0.2	10		
$C_{11}H_8O_2$	2-Methyl-1,4-naphthalenedione	172.181	25	0.016	0.16	40		
$C_{11}H_8O_2$	1-Naphthalenecarboxylic acid	172.181	25	0.0058	0.058	27		
$C_{11}H_{10}$	1-Methylnaphthalene	142.197	25	0.00281	0.0281	22	0.045	22
$C_{11}H_{10}$	2-Methylnaphthalene	142.197	25	0.0025	0.025	4	0.051	12
$C_{11}H_{10}N_2S$	1-Naphthalenylthiourea	202.275	20	0.06	0.6	40		
$C_{11}H_{12}Cl_2N_2O_5$	Chloramphenicol	323.129	25	0.38	3.8	40		
$C_{11}H_{12}I_3NO_2$	Iopanoic acid	570.932	37	0.034	0.34	40		
$C_{11}H_{12}NO_4PS_2$	Phosmet	317.321	25	0.0025	0.025	40		
$C_{11}H_{12}N_2O_2$	*L*-Tryptophan	204.225	25	1.30	13.1	26		
$C_{11}H_{13}NO_4$	Bendiocarb	223.226	25	0.004	0.04	40		
$C_{11}H_{13}N_3O_3S$	Sulfisoxazole	267.304	37	0.03	0.3	40		
$C_{11}H_{14}ClNO$	Propachlor	211.688	20	0.07	0.7	40		
$C_{11}H_{14}N_2O$	Cytisine	190.241	16	~30	439	40		
$C_{11}H_{14}O_3$	Butyl 4-hydroxybenzoate	194.227	25	0.020	0.20	40		
$C_{11}H_{15}NO_2$	Butyl 4-aminobenzoate	193.243	25	0.018	0.18	40		
$C_{11}H_{15}NO_3$	Propoxur	209.242	20	0.193	1.93	40		
$C_{11}H_{16}$	Pentylbenzene	148.245	25	0.00105	0.0105	5	1.69	11
$C_{11}H_{16}O$	4-(1,1-Dimethylpropyl)phenol	164.244	25	0.017	0.17	40		
$C_{11}H_{17}N_3O_3S$	4-Amino-*N*-[(butylamino)carbonyl] benzenesulfonamide	271.336	37	0.053	0.53	40		
$C_{11}H_{18}N_2O_3$	Amobarbital	226.272	25	0.06	0.6	40		
$C_{11}H_{22}O_2$	Heptyl butanoate	186.292	20	0.028	0.28	20		
			80	0.020	0.20	20		
$C_{11}H_{22}O_2$	Ethyl nonanoate	186.292	20	0.003	0.03	27		
$C_{11}H_{24}$	Undecane	156.309	25	0.0000004	0.000004	37		
$C_{12}Br_{10}O$	Decabromobiphenyl ether	959.167	25	0.0000025	0.000025	40		
$C_{12}Cl_{10}$	Decachlorobiphenyl	498.658	25	0.00000000012	0.0000000012	7	0.0208	7
$C_{12}F_{26}$	Hexacosafluorododecane	638.086	20	0.00000096	0.0000096	35		
$C_{12}HCl_9$	2,2′,3,3′,4,5,5′,6,6′-Nonachlorobiphenyl	464.213	25	0.0000000018	0.000000018	7		
$C_{12}H_2Cl_8$	2,2′,3,3′,5,5′,6,6′-Octachlorobiphenyl	429.768	25	0.00000015	0.0000015	41	0.0381	7
$C_{12}H_3Cl_7$	2,2′,3,3′,4,4′,6-Heptachlorobiphenyl	395.323	25	0.0000002	0.000002	7	0.0054	7
$C_{12}H_4Cl_4O_2$	2,3,7,8-Tetrachlorodibenzo-*p*-dioxin	321.971	22	0.0000000019	0.000000019	40		
$C_{12}H_4Cl_6$	2,2′,3,3′,4,4′-Hexachlorobiphenyl	360.878	25	0.00000006	0.0000006	7	0.0354	31
$C_{12}H_4Cl_6$	2,2′,4,4′,6,6′-Hexachlorobiphenyl	360.878	25	0.0000003	0.000003	41	0.818	7

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
$C_{12}H_4Cl_6$	2,2′,3,3′,6,6′-Hexachlorobiphenyl	360.878	25	0.0000004	0.000004	41		
$C_{12}H_5Cl_5$	2,3,4,5,6-Pentachlorobiphenyl	326.433	25	0.0000008	0.000008	7		
$C_{12}H_5Cl_5$	2,2′,4,5,5′-Pentachlorobiphenyl	326.433	25	0.000001	0.00001	7	0.0421	31
$C_{12}H_5N_7O_{12}$	2,4,6-Trinitro-*N*-(2,4,6-trinitrophenyl) aniline	439.208	17	0.0060	0.060	40		
$C_{12}H_6Cl_4$	2,3,4,5-Tetrachlorobiphenyl	291.988	25	0.000002	0.00002	7		
$C_{12}H_6Cl_4$	2,2′,4′,5-Tetrachlorobiphenyl	291.988	25	0.0000016	0.000016	9		
$C_{12}H_7Cl_2NO_3$	Nitrofen	284.095	22	0.00095	0.0095	40		
$C_{12}H_7Cl_3$	2,4,5-Trichlorobiphenyl	257.543	25	0.000014	0.00014	7	0.0379	31
$C_{12}H_7Cl_3$	2,4,6-Trichlorobiphenyl	257.543	25	0.00002	0.0002	7	0.0495	7
$C_{12}H_8$	Acenaphthylene	152.192	20	0.0016	0.016	28	0.012	28
$C_{12}H_8Cl_2$	2,5-Dichlorobiphenyl	223.098	25	0.0002	0.002	7	0.0201	7
$C_{12}H_8Cl_2$	2,6-Dichlorobiphenyl	223.098	25	0.00014	0.0014	7		
$C_{12}H_8Cl_6$	Aldrin	364.910	25	0.00002	0.0002	40		
$C_{12}H_8Cl_6O$	Dieldrin	380.909	25	0.000020	0.00020	40		
$C_{12}H_8Cl_6O$	Endrin	380.909	25	0.000026	0.00026	40		
$C_{12}H_8O$	Dibenzofuran	168.191	25	0.000475	0.00475	41	0.011	12
$C_{12}H_8O_4$	Methoxsalen	216.190	30	0.0048	0.048	40		
$C_{12}H_8S$	Dibenzothiophene	184.257	25	0.000103	0.00103	6		
$C_{12}H_9Cl$	2-Chlorobiphenyl	188.652	25	0.00055	0.0055	7	0.0701	7
$C_{12}H_9ClF_3N_3O$	Norflurazon	303.666	25	0.0028	0.028	40		
$C_{12}H_9Cl_2NO_3$	Vinclozolin	286.110	20	0.1	1	32		
$C_{12}H_9N$	Carbazole	167.206	22	0.000120	0.00120	6		
$C_{12}H_9NS$	10*H*-Phenothiazine	199.271	25	0.00016	0.0016	40		
$C_{12}H_{10}$	Acenaphthene	154.207	0	0.00015	0.0015	4		
			25	0.000380	0.00380	22	0.01217	22
			50	0.00092	0.0092	4		
$C_{12}H_{10}$	Biphenyl	154.207	0	0.000272	0.00272	4		
			25	0.00072	0.0072	22	0.0280	22
			50	0.0022	0.022	4		
$C_{12}H_{10}Cl_2N_2$	3,3′-Dichloro-*p*-benzidine	253.126	25	0.00031	0.0031	40		
$C_{12}H_{10}N_2$	*trans*-Azobenzene	182.220	20	0.03	0.3	27		
$C_{12}H_{10}N_2O$	*N*-Nitrosodiphenylamine	198.219	25	0.0035	0.035	17		
$C_{12}H_{10}O$	2-Hydroxybiphenyl	170.206	25	0.07	0.7	40		
$C_{12}H_{10}O$	4-Hydroxybiphenyl	170.206	25	0.0056	0.056	40		
$C_{12}H_{10}O$	Diphenyl ether	170.206	25	0.00180	0.0180	6	0.027	13
$C_{12}H_{10}O_2$	1-Naphthaleneacetic acid	186.206	25	0.0415	0.415	40		
$C_{12}H_{11}Cl_2NO$	Propyzamide	256.127	25	0.0015	0.015	32		
$C_{12}H_{11}N$	Diphenylamine	169.222	20	0.0055	0.055	40		
			50	0.0058	0.058	40		
$C_{12}H_{11}NO_2$	Carbaryl	201.221	20	0.0102	0.102	40		
$C_{12}H_{11}N_3$	4-Aminoazobenzene	197.235	25	0.0030	0.030	40		
			97	0.068	0.68	40		
$C_{12}H_{11}N_3$	1,3-Diphenyl-1-triazene	197.235	20	0.050	0.50	40		
$C_{12}H_{12}$	1-Ethylnaphthalene	156.223	25	0.00101	0.0101	4	0.039	12
$C_{12}H_{12}$	2-Ethylnaphthalene	156.223	25	0.00080	0.0080	4	0.078	12
$C_{12}H_{12}$	1,3-Dimethylnaphthalene	156.223	25	0.0008	0.008	4		
$C_{12}H_{12}$	1,4-Dimethylnaphthalene	156.223	25	0.00114	0.0114	4		
$C_{12}H_{12}$	1,5-Dimethylnaphthalene	156.223	25	0.00031	0.0031	4	0.036	28
$C_{12}H_{12}$	2,3-Dimethylnaphthalene	156.223	25	0.00025	0.0025	4		
$C_{12}H_{12}$	2,6-Dimethylnaphthalene	156.223	25	0.00017	0.0017	4		
$C_{12}H_{12}ClN_5O_4S$	Chlorsulfuron	357.773	25	2.71	27.9	32		
$C_{12}H_{12}N_2$	*p*-Benzidine	184.236	24	0.0360	0.360	40		
$C_{12}H_{12}N_2O_2S$	Bis(4-aminophenyl) sulfone	248.300	25	0.016	0.16	40		
$C_{12}H_{12}N_2O_3$	Phenobarbital	232.234	25	0.12	1.2	40		
			45	0.26	2.6	40		
$C_{12}H_{13}NO_2S$	Carboxin	235.302	25	0.017	0.17	40		
$C_{12}H_{14}N_4O_2S$	Sulfamethazine	278.330	20	0.053	0.53	40		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
$C_{12}H_{14}O_4$	Diethyl phthalate	222.237	25	0.12	1.2	40		
$C_{12}H_{15}ClNO_4PS_2$	Phosalone	367.808	20	0.00026	0.0026	40		
$C_{12}H_{15}NO_3$	Carbofuran	221.252	20	0.032	0.32	40		
$C_{12}H_{18}$	Hexylbenzene	162.271	25	0.00021	0.0021	4		
$C_{12}H_{18}N_2O_3S$	Tolbutamide	270.347	25	0.011	0.11	40		
$C_{12}H_{18}N_4O_6S$	Oryzalin	346.359	25	0.00024	0.0024	40		
$C_{12}H_{18}O_2$	4-Hexyl-1,3-benzenediol	194.270	18	0.05	0.5	40		
$C_{12}H_{19}ClNO_3P$	Crufomate	291.711	20	0.50	5.0	40		
$C_{12}H_{20}N_4O_2$	Hexazinone	252.313	25	3.2	33	40		
$C_{12}H_{22}O_4$	Dodecanedioic acid	230.301	20	0.004	0.04	40		
$C_{12}H_{22}O_{11}$	Sucrose	342.296	20	67.1		27		
			50	72.3		27		
			100	83.0		27		
$C_{12}H_{22}O_{11}$	α-Maltose	342.296	20	51.9		27		
$C_{12}H_{24}O$	2,6,8-Trimethyl-4-nonanone	184.318	10	0.012	0.12	20		
			80	0.014	0.14	20		
$C_{12}H_{24}O_2$	Dodecanoic acid	200.318	20	0.0055	0.055	26		
$C_{12}H_{24}O_2$	Ethyl decanoate	200.318	20	0.0015	0.015	27		
$C_{12}H_{26}$	Dodecane	170.334	25	0.00000037	0.0000037	4	750	5
$C_{12}H_{26}O$	1-Dodecanol	186.333	25	0.0004	0.004	1		
$C_{12}H_{26}O$	Dihexyl ether	186.333	20	0.019	0.19	20		
			90	0.019	0.19	20		
$C_{12}H_{27}N$	Tributylamine	185.349	25	0.0142	0.142	40		
$C_{12}H_{27}O_4P$	Tributyl phosphate	266.313	25	0.039	0.39	10		
$C_{13}H_9N$	Acridine	179.217	25	0.00466	0.0466	6		
$C_{13}H_9N$	Benzo[f]quinoline	179.217	25	0.0079	0.079	6		
$C_{13}H_{10}$	9*H*-Fluorene	166.218	0	0.00007	0.0007	4		
			25	0.00019	0.0019	22	0.00787	22
			50	0.00063	0.0063	4		
$C_{13}H_{10}Cl_2O_2$	Dichlorophene	269.123	25	0.003	0.03	40		
$C_{13}H_{10}O$	Benzophenone	182.217	20	0.0075	0.075	40		
$C_{13}H_{11}ClO$	Clorophene	218.678	20	0.42	4.2	40		
$C_{13}H_{12}$	Diphenylmethane	168.234	25	0.000141	0.00141	4	0.001	12
$C_{13}H_{12}N_2O$	*N,N'*-Diphenylurea	212.246	20	0.015	0.15	40		
$C_{13}H_{13}Cl_2N_3O_3$	Iprodione	330.166	20	0.0013	0.013	40		
$C_{13}H_{14}$	1,4,5-Trimethylnaphthalene	170.250	25	0.00021	0.0021	4		
$C_{13}H_{17}N_3O$	Aminopyrine	231.293	25	4.8	50	40		
$C_{13}H_{18}Cl_2N_2O_2$	Melphalan	305.200	30	0.44	4.4	40		
$C_{13}H_{18}O_2$	Ibuprofen	206.281	25	0.0011	0.011	40		
			60	0.0048	0.048	40		
$C_{13}H_{19}N_3O_4$	Pendimethalin	281.308	20	0.00003	0.0003	40		
$C_{13}H_{22}NO_3PS$	Fenamiphos	303.358	20	0.0329	0.329	40		
$C_{13}H_{26}O_2$	Tridecanoic acid	214.344	20	0.0033	0.033	26		
$C_{13}H_{28}$	Tridecane	184.361	25	0.00000003	0.0000003	37		
$C_{14}H_8O_2$	9,10-Anthracenedione	208.213	25	0.00014	0.0014	40		
$C_{14}H_8O_4$	1,4-Dihydroxy-9,10-anthracenedione	240.212	25	0.0000096	0.000096	40		
$C_{14}H_9ClF_2N_2O_2$	Diflubenzuron	310.683	20	0.00002	0.0002	40		
$C_{14}H_9Cl_5$	1,1,1-Trichloro-2,2-bis(4-chlorophenyl) ethane	354.486	25	0.0000001	0.000001	40		
$C_{14}H_9Cl_5O$	1,1-Bis(4-chlorophenyl)-2,2,2-trichloroethanol	370.485	25	0.00013	0.0013	40		
$C_{14}H_9NO_2$	2-Amino-9,10-anthracenedione	223.227	25	0.000016	0.00016	40		
$C_{14}H_{10}$	Anthracene	178.229	0	0.0000022	0.000022	4		
			25	0.0000045	0.000045	22	0.00396	22
$C_{14}H_{10}$	Phenanthrene	178.229	10	0.000050	0.00050	4		
			25	0.00011	0.0011	22	0.00324	22
			50	0.00041	0.0041	4		
$C_{14}H_{10}Cl_4$	1,1-Dichloro-2,2-bis(*p*-chlorophenyl) ethane	320.041	25	0.000009	0.00009	40		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
			45	0.000024	0.00024	40		
$C_{14}H_{10}O_4$	Benzoyl peroxide	242.227	20	0.000016	0.00016	40		
$C_{14}H_{12}$	*trans*-Stilbene	180.245	25	0.000029	0.00029	4	0.040	12
$C_{14}H_{12}O_2$	Benzoin	212.244	25	0.03	0.3	40		
$C_{14}H_{14}$	1,2-Diphenylethane	182.261	25	0.00044	0.0044	6	0.017	12
$C_{14}H_{14}NO_4PS$	Ethyl *p*-nitrophenyl benzenethiophosphate	323.304	22	0.00031	0.0031	40		
$C_{14}H_{14}O$	Dibenzyl ether	198.260	35	0.0040	0.040	10		
$C_{14}H_{14}O_3$	2-Pivaloyl-1,3-indandione	230.259	25	0.0018	0.018	40		
$C_{14}H_{15}N_3$	4-(Dimethylamino)azobenzene	225.289	20	0.00014	0.0014	40		
$C_{14}H_{15}N_3$	2',3-Dimethyl-4-aminoazobenzene	225.289	37	0.0007	0.007	40		
$C_{14}H_{16}ClN_3O_2$	Bayleton	293.749	20	0.026	0.26	40		
$C_{14}H_{16}N_2$	*o*-Tolidine	212.290	25	0.13	1.3	40		
$C_{14}H_{16}N_2O_2$	3,3'-Dimethoxybenzidine	244.289	25	0.006	0.06	40		
$C_{14}H_{18}N_4O_3$	Trimethoprim	290.318	25	0.04	0.4	40		
$C_{14}H_{20}ClNO_2$	Alachlor	269.768	23	0.024	0.24	40		
$C_{14}H_{21}N_3O_3S$	Tolazamide	311.400	30	0.0065	0.065	40		
$C_{14}H_{22}N_2O$	2-(Diethylamino)-*N*-(2,6-dimethylphenyl)acetamide	234.337	25	0.38	3.8	40		
$C_{14}H_{28}O_2$	Tetradecanoic acid	228.371	20	0.0020	0.020	26		
$C_{14}H_{29}Cl$	1-Chlorotetradecane	232.833	25	0.0232	0.232	35		
$C_{14}H_{30}$	Tetradecane	198.388	25	0.000012	0.00012	5		
$C_{14}H_{30}O$	1-Tetradecanol	214.387	25	0.000031	0.00031	1		
$C_{15}H_{12}$	2-Methylanthracene	192.256	25	0.00003	0.0003	22		
$C_{15}H_{12}$	9-Methylanthracene	192.256	25	0.000026	0.00026	4		
$C_{15}H_{12}$	1-Methylphenanthrene	192.256	25	0.0000269	0.000269	4		
$C_{15}H_{12}N_2O_2$	Phenytoin	252.268	37	0.0038	0.038	40		
$C_{15}H_{15}NO_2$	Mefenamic acid	241.286	20	0.0026	0.026	40		
$C_{15}H_{16}O_2$	2,2-Bis(4-hydroxyphenyl)propane	228.287	20	0.035	0.35	40		
$C_{15}H_{20}N_2O_4S$	Acetohexamide	324.396	37	0.0013	0.013	40		
$C_{15}H_{24}O$	4-Nonylphenol	220.351	25	0.000636	0.00636	40		
$C_{15}H_{26}O_6$	Tributyrin	302.363	20	0.010	0.10	40		
$C_{15}H_{30}O_2$	Pentadecanoic acid	242.398	20	0.0012	0.012	26		
$C_{15}H_{32}O$	1-Pentadecanol	228.414	25	0.000010	0.00010	1		
$C_{16}H_{10}$	Fluoranthene	202.250	25	0.000026	0.00026	22	0.00096	22
$C_{16}H_{10}$	Pyrene	202.250	25	0.000013	0.00013	22	0.00092	22
			50	0.00009	0.0009	4		
$C_{16}H_{13}ClN_2O$	Valium	284.739	25	0.005	0.05	40		
$C_{16}H_{14}$	9,10-Dimethylanthracene	206.282	25	0.0000056	0.000056	4		
$C_{16}H_{14}ClN_3O$	Chlorodiazepoxide	299.754	20	0.2	2	40		
$C_{16}H_{14}Cl_2O_3$	Chlorobenzilate	325.186	20	0.001	0.01	32		
$C_{16}H_{14}Cl_2O_4$	Diclofop-methyl	341.186	20	0.0003	0.003	32		
$C_{16}H_{14}N_2O$	2-Methyl-3-(2-methylphenyl)-4(3*H*)-quinazolinone	250.294	23	0.03	0.3	40		
$C_{16}H_{15}Cl_3O_2$	Methoxychlor	345.648	25	0.000005	0.00005	40		
$C_{16}H_{15}NO_3$	*N*-Benzoyl-*L*-phenylalanine	269.295	25	0.085	0.85	29		
$C_{16}H_{16}N_2O_4$	Phenmedipham	300.309	25	0.00047	0.0047	32		
$C_{16}H_{17}NO$	Diphenamid	239.312	27	0.026	0.26	32		
$C_{16}H_{17}N_3O_4S$	Cephalexin	347.389	25	1.2	12	40		
$C_{16}H_{22}O_4$	Dibutyl phthalate	278.344	25	0.00112	0.0112	15		
$C_{16}H_{32}O_2$	Hexadecanoic acid	256.424	20	0.00072	0.0072	26		
$C_{16}H_{34}$	Hexadecane	226.441	25	0.0000006	0.000006	37		
$C_{16}H_{34}O$	1-Hexadecanol	242.440	25	0.000003	0.00003	1		
$C_{17}H_{12}$	11*H*-Benzo[a]fluorene	216.277	25	0.0000045	0.000045	4		
$C_{17}H_{12}$	11*H*-Benzo[b]fluorene	216.277	25	0.0000002	0.000002	4		
$C_{17}H_{17}NO_2$	Apomorphine	267.323	25	2.0	20	40		
$C_{17}H_{17}N_3O_3$	Imazaquin	311.335	20	0.009	0.09	32		
$C_{17}H_{19}NO_3$	Morphine	285.338	20	0.015	0.15	27		
$C_{17}H_{19}NO_4$	Fenoxycarb	301.338	20	0.0006	0.006	32		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
$C_{17}H_{20}N_2O$	*N,N,N',N'*-Tetramethyl-4,4'-diaminobenzophenone	268.353	20	0.04	0.4	40		
$C_{17}H_{20}N_4O_6$	Riboflavin	376.364	25	0.0075	0.075	40		
$C_{17}H_{21}NO_4$	Cocaine	303.354	25	0.17	1.7	27		
$C_{17}H_{23}NO_3$	Atropine	289.370	20	0.3	3	40		
$C_{17}H_{23}NO_3$	Hyoscyamine	289.370	20	0.36	3.6	40		
$C_{17}H_{34}O_2$	Heptadecanoic acid	270.451	20	0.00042	0.0042	26		
$C_{18}H_{12}$	Benz[a]anthracene	228.288	25	0.0000011	0.000011	22	0.00058	22
$C_{18}H_{12}$	Chrysene	228.288	25	0.0000002	0.000002	22	0.000065	22
$C_{18}H_{12}$	Naphthacene	228.288	25	0.00000006	0.0000006	4	0.000004	12
$C_{18}H_{12}$	Triphenylene	228.288	25	0.0000041	0.000041	4	0.00001	12
$C_{18}H_{12}N_2$	2,2'-Biquinoline	256.301	24	0.000102	0.00102	6		
$C_{18}H_{14}$	*o*-Terphenyl	230.304	25	0.00012	0.0012	40		
$C_{18}H_{14}$	*m*-Terphenyl	230.304	25	0.00015	0.0015	40		
$C_{18}H_{14}$	*p*-Terphenyl	230.304		0.0000018	0.000018	40		
$C_{18}H_{15}O_4P$	Triphenyl phosphate	326.283	24	0.000073	0.00073	40		
$C_{18}H_{16}OSn$	Triphenyltin hydroxide	367.029	20	0.0001	0.001	32		
$C_{18}H_{20}O_2$	*trans*-Diethylstilbestrol	268.351	20	0.01	0.1	40		
$C_{18}H_{21}NO_3$	Codeine	299.365	25	0.79	7.9	27		
$C_{18}H_{32}O_{16}$	Raffinose	504.437	20	12.5	~145	27		
$C_{18}H_{34}O_4$	Dibutyl sebacate	314.461	20	0.004	0.04	10		
$C_{18}H_{36}O_2$	Stearic acid	284.478	20	0.00029	0.0029	26		
$C_{18}H_{38}$	Octadecane	254.495	25	0.0000006	0.000006	37		
$C_{18}H_{38}O$	1-Octadecanol	270.494	34	0.000011	0.00011	1		
$C_{19}H_{14}$	9-Methylbenz[a]anthracene	242.314	27	0.0000066	0.000066	4		
$C_{19}H_{14}$	10-Methylbenz[a]anthracene	242.314	25	0.0000055	0.000055	4		
$C_{19}H_{14}$	5-Methylchrysene	242.314	27	0.0000062	0.000062	4		
$C_{19}H_{16}ClNO_4$	Indomethacin	357.788	25	0.001	0.01	40		
$C_{19}H_{16}O_4$	Warfarin	308.328	20	0.004	0.04	40		
$C_{19}H_{19}N_7O_6$	Folic acid	441.397	0	0.001	0.01	26		
			100	0.05	0.5	26		
$C_{19}H_{20}N_2O_2$	Phenylbutazone	308.374	25	0.0034	0.034	40		
$C_{19}H_{28}O_2$	17-Hydroxyandrost-4-en-3-one, (17β)	288.424	25	0.0024	0.024	40		
$C_{20}H_{12}$	Perylene	252.309	25	0.00000004	0.0000004	4	0.000003	12
$C_{20}H_{12}$	Benzo[a]pyrene	252.309	25	0.0000003	0.000003	22	0.0000465	22
$C_{20}H_{12}$	Benzo[e]pyrene	252.309	20	0.0000005	0.000005	22	0.0000467	22
$C_{20}H_{12}$	Benzo[k]fluoranthene	252.309		0.00000008	0.0000008	40		
$C_{20}H_{12}$	Benzo[b]fluoranthene	252.309	20	0.0000002	0.000002	40		
$C_{20}H_{12}O_5$	Fluorescein	332.306	20	0.005	0.05	27		
$C_{20}H_{13}N$	13*H*-Dibenzo[a,i]carbazole	267.324	24	0.00000104	0.0000104	6		
$C_{20}H_{14}$	1,2-Dihydrobenz[j]aceanthrylene	254.325	25	0.00000036	0.0000036	6		
$C_{20}H_{14}O_4$	Phenolphthalein	318.323	20	0.018	0.18	27		
$C_{20}H_{14}O_4$	Diphenyl phthalate	318.323	24	0.000008	0.00008	40		
$C_{20}H_{21}NO_4$	Papaverine	339.386	37	0.0037	0.037	40		
$C_{20}H_{23}N$	Amitriptyline	277.404	24	0.00097	0.0097	40		
$C_{20}H_{24}N_2O_2$	Quinine	324.417	25	0.057	0.57	27		
$C_{20}H_{24}N_2O_2$	Quinidine	324.417	20	0.020	0.20	27		
$C_{20}H_{26}O_2$	Norethisterone	298.419	25	0.00063	0.0063	40		
$C_{20}H_{30}O_2$	17-Methyltestosterone	302.451	25	0.0033	0.033	40		
$C_{20}H_{42}$	Eicosane	282.547	25	0.00000019	0.0000019	4		
$C_{21}H_{13}N$	Dibenz[a,j]acridine	279.335	25	0.000016	0.00016	6		
$C_{21}H_{16}$	1,2-Dihydro-3-methylbenz[j] aceanthrylene	268.352	25	0.00000022	0.0000022	6		
$C_{21}H_{20}Cl_2O_3$	Permethrin	391.288	20	0.00002	0.0002	32		
$C_{21}H_{21}O_4P$	Tri-*p*-cresyl phosphate	368.363	25	0.00004	0.0004	40		
$C_{21}H_{22}N_2O_2$	Strychnine	334.412	20	0.013	0.13	27		
$C_{21}H_{23}ClFNO_2$	Haloperidol	375.865	30	0.0003	0.003	40		
$C_{21}H_{26}O_5$	17,21-Dihydroxypregna-1,4-diene-3,11,20-trione	358.428	25	0.012	0.12	40		

				Solubility S			Henry Const. k_H	
Mol. formula	**Name**	**Mol. wt.**	***t*/°C**	**Mass%**	**g/L**	**Ref.**	**kPa m^3mol^{-1}**	**Ref.**
$C_{21}H_{28}O_5$	Prednisolone	360.444	25	0.03	0.3	40		
$C_{21}H_{28}O_5$	17,21-Dihydroxypregn-4-ene-3,11,20-trione	360.444	25	0.028	0.28	30		
$C_{21}H_{30}O_2$	Progesterone	314.462	25	0.00088	0.0088	40		
			41	0.00206	0.0206	40		
$C_{21}H_{30}O_5$	Hydrocortisone	362.460	25	0.029	0.29	40		
$C_{21}H_{33}NO_7$	Lasiocarpine	411.490	20	0.67	6.75	40		
$C_{22}H_{12}$	Indeno[1,2,3-cd]pyrene	276.330	20	0.00000002	0.0000002	40		
$C_{22}H_{12}$	Benzo[ghi]perylene	276.330	25	0.000000026	0.00000026	4	0.000075	12
$C_{22}H_{14}$	Benzo[b]triphenylene	278.346	25	0.0000027	0.000027	4		
$C_{22}H_{14}$	Dibenz[a,h]anthracene	278.346	25	0.00000006	0.0000006	4		
$C_{22}H_{14}$	Dibenz[a,j]anthracene	278.346	25	0.0000012	0.000012	4		
$C_{22}H_{14}$	Picene	278.346	25	0.00000025	0.0000025	4		
$C_{22}H_{18}Cl_2FNO_3$	Cyfluthrin	434.287	20	0.0000002	0.000002	32		
$C_{22}H_{19}Cl_2NO_3$	Cypermethrin	416.297	20	0.000001	0.00001	32		
$C_{22}H_{20}O_{13}$	Carminic acid	492.386	20	0.13	1.3	40		
$C_{22}H_{22}FN_3O_2$	Droperidol	379.427	30	0.00041	0.0041	40		
$C_{22}H_{23}NO_7$	Noscapine	413.421	25	0.03	0.3	40		
$C_{22}H_{25}NO_6$	Colchicine	399.437	20	4	4	26		
$C_{22}H_{29}FO_5$	Dexamethasone	392.460	25	0.009	0.09	40		
$C_{22}H_{30}O_5$	Methylprednisolone	374.470	25	0.012	0.12	40		
$C_{22}H_{44}O_2$	Butyl stearate	340.583	25	0.2	2	10		
$C_{22}H_{46}$	Docosane	310.600	22	0.0000006	0.000006	37		
$C_{23}H_{19}ClF_3NO_3$	Cyhalothrin	449.850	20	0.0000005	0.000005	32		
$C_{23}H_{22}ClF_3O_2$	Bifenthrin	422.868	25	0.00001	0.0001	32		
$C_{23}H_{22}O_6$	Rotenone	394.417	25	0.000017	0.00017	40		
$C_{23}H_{26}N_2O_4$	Brucine	394.463	20	0.012	0.12	27		
$C_{23}H_{27}NO_8$	Narceine	445.462	13	0.078	0.78	27		
$C_{24}H_{12}$	Coronene	300.352	25	0.000000014	0.00000014	4		
$C_{24}H_{38}O_4$	Bis(2-ethylhexyl) phthalate	390.557	25	0.000027	0.00027	40		
$C_{24}H_{40}O_4$	3,12-Dihydroxycholan-24-oic acid, (3α,5β,12α)	392.573	20	0.001	0.01	40		
$C_{24}H_{40}O_5$	Cholic acid	408.572	20	0.028	0.28	26		
$C_{24}H_{50}$	Tetracosane	338.654	22	0.0000004	0.000004	37		
$C_{25}H_{24}F_6N_4$	Hydramethylnon	494.476	20	0.0000006	0.000006	32		
$C_{26}H_{54}$	Hexacosane	366.707	25	0.0000002	0.000002	37		
$C_{28}H_{58}$	Octacosane	394.761	22	0.0000006	0.000006	37		
$C_{29}H_{32}O_{13}$	Etoposide	588.556	20	0.02	0.2	40		
$C_{29}H_{40}N_2O_4$	Emetine	480.639	15	0.096	0.96	40		
$C_{29}H_{44}O_{12}$	Ouabain	584.652	25	1.3	13	40		
$C_{33}H_{40}N_2O_9$	Reserpine	608.679	30	0.0073	0.073	40		
$C_{36}H_{74}$	Hexatriacontane	506.973	25	0.0000002	0.000002	37		
$C_{37}H_{67}NO_{13}$	Erythromycin	733.927	30	0.12	1.2	40		
			80	0.04	0.4	40		
$C_{41}H_{64}O_{13}$	Digitoxin	764.939	25	0.0004	0.004	40		
$C_{41}H_{64}O_{14}$	Digoxin	780.939	25	0.0059	0.059	40		
$C_{45}H_{73}NO_{15}$	Solanine	868.060	15	0.0026	0.026	40		
$C_{60}H_{78}OSn_2$	Fenbutatin oxide	1052.68	23	0.0000005	0.000005	32		

[a] Indicates a value of S for a gas at a partial pressure of 101.325 kPa (1 atm) in equilibrium with the solution.

AQUEOUS SOLUBILITY OF INORGANIC COMPOUNDS AT VARIOUS TEMPERATURES

The solubility of over 300 common inorganic compounds in water is tabulated here as a function of temperature. Solubility is defined as the concentration of the compound in a solution that is in equilibrium with a solid phase at the specified temperature. In this table the solid phase is generally the most stable crystalline phase at the temperature in question. An asterisk * on solubility values in adjacent columns indicates that the solid phase changes between those two temperatures (usually from one hydrated phase to another or from a hydrate to the anhydrous solid). In such cases the slope of the solubility vs. temperature curve may show a discontinuity.

All solubility values are expressed as mass percent of solute, $100 \cdot w_2$, where

$$w_2 = m_2/(m_1 + m_2)$$

and m_2 is the mass of solute and m_1 the mass of water. This quantity is related to other common measures of solubility as follows:

Molarity: $c_2 = 1000\ \rho w_2/M_2$
Molality: $m_2 = 1000 w_2/M_2(1\text{-}w_2)$
Mole fraction: $x_2 = (w_2/M_2)/\{(w_2/M_2) + (1\text{-}w_2)/M_1\}$
Mass of solute per 100 g of H_2O: $r_2 = 100 w_2/(1\text{-}w_2)$

Here M_2 is the molar mass of the solute and M_1 = 18.015 g/mol is the molar mass of water. ρ is the density of the solution in g cm^{-3}.

The data in the table have been derived from the references indicated; in many cases the data have been refitted or interpolated in order to present solubility at rounded values of temperature. Where available, values were taken from the IUPAC *Solubility Data Series* (Reference 1) or the related papers in the *Journal of Physical and Chemical Reference Data* (References 2 to 5), which present carefully evaluated data.

The solubility of sparingly soluble compounds that do not appear in this table may be calculated from the data in the table "Solubility Product Constants". Solubility of inorganic gases may be found in the table "Solubility of Selected Gases in Water".

Compounds are listed alphabetically by chemical formula in the most commonly used form (e.g., NaCl, NH_4NO_3, etc.).

References

1. *Solubility Data Series*, International Union of Pure and Applied Chemistry. Volumes 1 to 53 were published by Pergamon Press, Oxford, from 1979 to 1994; subsequent volumes were published by Oxford University Press, Oxford. The number following the colon is the volume number in the series.
2. Clever, H. L., and Johnston, F. J., *J. Phys. Chem. Ref. Data*, 9, 751, 1980.
3. Marcus, Y., *J. Phys. Chem. Ref. Data*, 9, 1307, 1980.
4. Clever, H. L., Johnson, S. A., and Derrick, M. E., *J. Phys. Chem. Ref. Data*, 14, 631, 1985.
5. Clever, H. L., Johnson, S. A., and Derrick, M. E., *J. Phys. Chem. Ref. Data*, 21, 941, 1992.
6. Söhnel, O., and Novotny, P., *Densities of Aqueous Solutions of Inorganic Substances*, Elsevier, Amsterdam, 1985.
7. Krumgalz, B.S., *Mineral Solubility in Water at Various Temperatures*, Israel Oceanographic and Limnological Research Ltd., Haifa, 1994.
8. Potter, R. W., and Clynne, M. A., *J. Research U.S. Geological Survey*, 6, 701, 1978; Clynne, M. A., and Potter, R. W., *J. Chem. Eng. Data,* 24, 338, 1979.
9. Marshal, W. L., and Slusher, R., *J. Phys. Chem.*, 70, 4015, 1966; Knacke, O., and Gans, W., *Zeit. Phys. Chem.*, NF, 104, 41, 1977.
10. Stephen, H., and Stephen, T., *Solubilities of Inorganic and Organic Compounds, Vol. 1*, Macmillan, New York, 1963.

Compound	0°C	10°C	20°C	25°C	30°C	40°C	50°C	60°C	70°C	80°C	90°C	100°C	Ref.
$AgBrO_3$				0.193							1.32		7
$AgClO_2$	0.17	0.31	0.47	0.55	0.64	0.82	1.02	1.22	1.44	1.66	1.88	2.11	7
$AgClO_3$				15									7
$AgClO_4$	81.6	83.0	84.2	84.8	85.3	86.3	86.9	87.5	87.9	88.3	88.6	88.8	6
$AgNO_2$	0.155			0.413									7
$AgNO_3$	55.9	62.3	67.8	70.1	72.3	76.1	79.2	81.7	83.8	85.4	86.7	87.8	6
Ag_2SO_4	0.56	0.67	0.78	0.83	0.88	0.97	1.05	1.13	1.20	1.26	1.32	1.39	7
$AlCl_3$	30.84	30.91	31.03	31.10	31.18	31.37	31.60	31.87	32.17	32.51	32.90	33.32	7
$Al(ClO_4)_3$	54.9										64.4		7
AlF_3	0.25	0.34	0.44	0.50	0.56	0.68	0.81	0.96	1.11	1.28	1.45	1.64	7
$Al(NO_3)_3$	37.0	38.2	39.9	40.8	42.0	44.5	47.3	50.4	53.8*			61.5*	6
$Al_2(SO_4)_3$	27.5			27.8	28.2	29.2	30.7	32.6	34.9	37.6	40.7	44.2	7
As_2O_3	1.19	1.48	1.80	2.01	2.27	2.86	3.43	4.11	4.89	5.77	6.72	7.71	10
$BaBr_2$	47.6	48.5	49.5	50.0	50.4	51.4	52.5	53.5	54.5	55.5	56.6	57.6	6
$Ba(BrO_3)_2$	0.285	0.442	0.656	0.788	0.935	1.30	1.74	2.27	2.90	3.61	4.40	5.25	1:14
$Ba(C_2H_3O_2)_2$	37.0			44.2									7
$BaCl_2$	23.30	24.88	26.33	27.03	27.70	29.00	30.27	31.53	32.81	34.14	35.54	37.05	8
$Ba(ClO_2)_2$	30.5			31.3								44.7	7
$Ba(ClO_3)_2$	16.90	21.23	23.66	27.50	29.43	33.16	36.69	40.05	43.04	45.90	48.70	51.17	1:14
$Ba(ClO_4)_2$	67.30	70.96	74.30	75.75	77.05	79.23	80.92	82.21	83.16	83.88	84.43	84.90	7
BaF_2		0.158		0.161									7
BaI_2	62.5	64.7	67.3	68.8	69.1	69.5	70.1	70.7	71.3	72.0	72.7	73.4	6

Compound	0°C	10°C	20°C	25°C	30°C	40°C	50°C	60°C	70°C	80°C	90°C	100°C	Ref.
$Ba(IO_3)_2$	0.0182	0.0262	0.0342	0.0396	0.045*	0.058*	0.073	0.090	0.109	0.131	0.156	0.182	1:14
$Ba(NO_2)_2$	31.1	36.6	41.8	44.3	46.8	51.6	56.2	60.5	64.6	68.5	72.1	75.6	10
$Ba(NO_3)_2$	4.7	6.3	8.2	9.3	10.2	12.4	14.7	17.0	19.3	21.5	23.5	25.5	6
$Ba(OH)_2$	1.67			4.68	8.4	19	33	52	74	100			7
BaS	2.79	4.78	6.97	8.21	9.58	12.67	16.18	20.05	24.19	28.55	33.04	37.61	7
$Ba(SCN)_2$				62.6									7
$BaSO_3$				0.0011									1:26
$BeCl_2$	40.5			41.7									7
$Be(ClO_4)_2$				59.5									7
$BeSO_4$	26.69	27.58	28.61	29.22	29.90	31.51	33.39	35.50	37.78	40.21	42.72	45.28	7
$CaBr_2$	55	56	59	61	63	68	71	73					10
$CaCl_2$	36.70	39.19	42.13	44.83*	49.12*	52.85*	56.05*	56.73	57.44	58.21	59.04	59.94	8
$Ca(ClO_3)_2$	63.2	64.2	65.5	66.3	67.2	69.0	71.0	73.2	75.5*	77.4*	77.7	78.0	1:14
$Ca(ClO_4)_2$				65.3									7
CaF_2	0.0013			0.0016									10
CaI_2	64.6	66.0	67.6	68.3	69.0	70.8	72.4	74.0	76.0	78.0	79.6	81.0	7
$Ca(IO_3)_2$	0.082	0.155	0.243	0.305	0.384*	0.517*	0.590	0.652	0.811*	0.665*	0.668		1:14
$Ca(NO_2)_2$	38.6	39.5	44.5	48.6									7
$Ca(NO_3)_2$	50.1	53.1	56.7	59.0	60.9	65.4	77.8	78.1	78.2	78.3	78.4	78.5	6
$CaSO_3$			0.0059	0.0054	0.0049	0.0041	0.0035	0.0030	0.0026	0.0023	0.0020	0.0019	1:26
$CaSO_4$	0.174	0.191	0.202	0.205	0.208	0.210	0.207	0.201	0.193	0.184	0.173	0.163	9
$CdBr_2$	36.0	43.0	49.9	53.4	56.4	60.3*	60.3*	60.5	60.7	60.9	61.3	61.6	6
CdC_2O_4				0.0060									5
$CdCl_2$	47.2	50.1	53.2	54.6	56.3*	57.3*	57.5	57.8	58.1	58.51	58.98	59.5	6
$Cd(ClO_4)_2$				58.7								66.9	7
CdF_2		5.82	4.65	4.18	3.76								5
CdI_2	44.1	44.9	45.8	46.3	46.8	47.9	49.0	50.2	51.5	52.7	54.1	55.4	6
$Cd(IO_3)_2$				0.091									5
$Cd(NO_3)_2$	55.4	57.1	59.6	61.0	62.8	66.5	70.6	86.1	86.5	86.8	87.1	87.4	6
$CdSO_4$	43.1	43.1	43.2	43.4	43.6	44.1	43.5	42.5	41.4	40.2	38.5	36.7	6
$CdSeO_4$	42.04	40.59	39.02	38.18	37.29	35.35	33.15	30.65	27.84	24.69	21.24	17.49	5
$Ce(NO_3)_3$	57.99	59.80	61.89	63.05	64.31*	67.0*	68.6	71.1*	74.9*	79.2	80.9	83.1	1:13
$CoCl_2$	30.30	32.60	34.87	35.99	37.10	39.27	41.38	43.46	45.50	47.51	49.51	51.50	7
$Co(ClO_4)_2$	50.0			53.0									7
CoF_2				1.4									7
CoI_2	58.00	61.78	65.35	66.99	68.51	71.17	73.41	75.29	76.89	78.28	79.52	80.70	7
$Co(NO_2)_2$	0.076			0.49									7
$Co(NO_3)_2$	45.5	47.0	49.4	50.8	52.4	56.0	60.1	62.6	64.9	67.7			6
$CoSO_4$	19.9	23.0	26.1	27.7	29.2	32.3	34.4	35.9	35.5	33.2	30.6	27.8	6
$Co(SCN)_2$				50.7									7
CrO_3	62.2	62.3	62.6	62.8	63.0	63.5	64.1	64.7	65.5	66.2	67.1	67.9	6
CsBr				55.2									7
$CsBrO_3$	1.16	1.93	3.01	3.69	4.46	6.32	8.60	11.32	14.45	17.96	21.83	25.98	1:30
CsCl	61.83	63.48	64.96	65.64	66.29	67.50	68.60	69.61	70.54	71.40	72.21	72.96	1:47
$CsClO_3$	2.40	3.87	5.94	7.22	8.69	12.15	16.33	21.14	26.45	32.10	37.89	43.42	1:30
$CsClO_4$	0.79	1.01	1.51	1.96	2.57	4.28	6.55	9.29	12.41	15.80	19.39	23.07	7
CsI	30.9	37.2	43.2	45.9	48.6	53.3	57.3	60.7	63.6	65.9	67.7	69.2	6
$CsIO_3$	1.08	1.58	2.21	2.59	3.02	3.96	5.06	6.29	7.70	9.20	10.79	12.45	1:30
$CsNO_3$	8.46	13.0	18.6	21.8	25.1	32.0	39.0	45.7	51.9	57.3	62.1	66.2	6
CsOH					75								7
Cs_2SO_4	62.6	63.4	64.1	64.5	64.8	65.5	66.1	66.7	67.3	67.8	68.3	68.8	6
$CuBr_2$				55.8									7
$CuCl_2$	40.8	41.7	42.6	43.1	43.7	44.8	46.0	47.2	48.5	49.9	51.3	52.7	6
$Cu(ClO_4)_2$	54.3				59.3								7
CuF_2				0.075									7
$Cu(NO_3)_2$	45.2	49.8	56.3	59.2	61.1	62.0	63.1	64.5	65.9	67.5	69.2	71.0	6
$CuSO_4$	12.4	14.4	16.7	18.0	19.3	22.2	25.4	28.8	32.4	36.3	40.3	43.5	6
$CuSeO_4$	10.6			16.0									7
$Dy(NO_3)_3$	58.79	59.99	61.49	62.35	63.29	65.43	68.04	71.58					1:13
$Er(NO_3)_3$	61.58	63.15	64.84	65.75	66.69	68.70	70.96	73.64	77.75				1:13
$Eu(NO_3)_3$	55.2	56.7	58.5	59.4	60.4	62.5	64.6						1:13

Compound	0°C	10°C	20°C	25°C	30°C	40°C	50°C	60°C	70°C	80°C	90°C	100°C	Ref.
$FeBr_2$				54.6								64.8*	7
$FeCl_2$	33.2*			39.4*								48.7*	7
$FeCl_3$	42.7	44.9	47.9	47.7	51.6	74.8	76.7	84.6	84.3	84.3	84.4	84.7	6
$Fe(ClO_4)_2$	63.39			67.76									7
FeF_3				5.59									7
$Fe(NO_3)_3$	40.15			46.57									7
$Fe(NO_3)_2$	41.44			46.67									7
$FeSO_4$	13.5	17.0	20.8	22.8	24.8	28.8	32.8	35.5	33.6	30.4	27.1	24.0	6
$Gd(NO_3)_3$	56.3	57.7	59.2	60.1	61.0	62.9	65.2	67.9	71.5				1:13
HIO_3	73.45	74.10	74.98	75.48	76.03	77.20	78.46	79.78	81.13	82.48	83.82	85.14	1:30
H_3BO_3	2.61	3.57	4.77	5.48	6.27	8.10	10.3	12.9	15.9	19.3	23.1	27.3	6
$HgBr_2$	0.26	0.37	0.52	0.61	0.72	0.96	1.26	1.63	2.08	2.61	3.23	3.95	4
$Hg(CN)_2$	6.57	7.83	9.33	10.2	11.1	13.1	15.5	18.2	21.2	24.6	28.3	32.3	6
$HgCl_2$	4.24	5.05	6.17	6.81	7.62	9.53	12.02	15.18	19.16	24.06	29.90	36.62	4
HgI_2			0.0041	0.0055	0.0072	0.0122	0.0199						4
$Hg(SCN)_2$				0.070									4
Hg_2Cl_2				0.0004									3
$Hg_2(ClO_4)_2$	73.8			79.8*								85.3*	7
Hg_2SO_4	0.038	0.043	0.048	0.051	0.054	0.059	0.065	0.070	0.076	0.082	0.088	0.093	4
$Ho(NO_3)_3$				63.8									1:13
KBF_4	0.28	0.34	0.45	0.55	0.75	1.38	2.09	2.82	3.58	4.34	5.12	5.90	10
KBr	35.0	37.3	39.4	40.4	41.4	43.2	44.8	46.2	47.6	48.8	49.8	50.8	6
$KBrO_3$	2.97	4.48	6.42	7.55	8.79	11.57	14.71	18.14	21.79	25.57	29.42	33.28	1:30
$KC_2H_3O_2$	68.40	70.29	72.09	72.92	73.70	75.08	76.27	77.31	78.22	79.04	79.80	80.55	7
KCl	21.74	23.61	25.39	26.22	27.04	28.59	30.04	31.40	32.66	33.86	34.99	36.05	1:47
$KClO_3$	3.03	4.67	6.74	7.93	9.21	12.06	15.26	18.78	22.65	26.88	31.53	36.65	1:30
$KClO_4$	0.70	1.10	1.67	2.04	2.47	3.54	4.94	6.74	8.99	11.71	14.94	18.67	6
KF	30.90	39.8	47.3	50.41	53.2					60.0			7
$KHCO_3$	18.62	21.73	24.92	26.6	28.13	31.32	34.46	37.51	40.45				6
$KHSO_4$	27.1	29.7	32.3	33.6	35.0	37.8	40.5	43.4	46.2	49.02	51.82	54.6	6
KH_2PO_4	11.74	14.91	18.25	19.97	21.77	25.28	28.95	32.76	36.75	40.96	45.41	50.12	1:31
KI	56.0	57.6	59.0	59.7	60.4	61.6	62.8	63.8	64.8	65.7	66.6	67.4	6
KIO_3	4.53	5.96	7.57	8.44	9.34	11.09	13.22	15.29	17.41	19.58	21.78	24.03	1:30
KIO_4	0.16	0.22	0.37	0.51	0.70	1.24	1.96	2.83	3.82	4.89	6.02	7.17	7
$KMnO_4$	2.74	4.12	5.96	7.06	8.28	11.11	14.42	18.16					6
KNO_2	73.7	74.6	75.3	75.7	76.0	76.7	77.4	78.0	78.5	79.1	79.6	80.1	6
KNO_3	12.0	17.6	24.2	27.7	31.3	38.6	45.7	52.2	58.0	63.0	67.3	70.8	6
KOH	48.7	50.8	53.2	54.7	56.1	57.9	58.6	59.5	60.6	61.8	63.1	64.6	6
KSCN	63.8	66.4	69.1	70.4	71.6	74.1	76.5	78.9	81.1	83.3	85.3	87.3	6
K_2CO_3	51.3	51.7	52.3	52.7	53.1	54.0	54.9	56.0	57.2	58.4	59.6	61.0	6
K_2CrO_4	37.1	38.1	38.9	39.4	39.8	40.5	41.3	41.9	42.6	43.2	43.8	44.3	6
$K_2Cr_2O_7$	4.30	7.12	10.9	13.1	15.5	20.8	26.3	31.7	36.9	41.5	45.5	48.9	6
K_2HAsO_4	48.5*			63.6*								79.8*	7
K_2HPO_4	57.0	59.1	61.5	62.7	64.1	67.7*		72.7*					1:31
K_2MoO_4				64.7							66.5		7
K_2SO_3	51.30	51.39	51.49	51.55	51.62	51.76	51.93	52.11	52.32	52.54	52.79	53.06	1:26
K_2SO_4	7.11	8.46	9.95	10.7	11.4	12.9	14.2	15.5	16.7	17.7	18.6	19.3	6
$K_2S_2O_3$	49.0*			62.3*							75.7*		7
$K_2S_2O_5$	22.1	26.7	31.1	33.1	35.2	39.0	42.6	46.0	49.1	52.0	54.6		1:26
K_2SeO_3	68.4*			68.5*								68.5*	7
K_2SeO_4	52.70	52.93	53.17	53.30	53.43	53.70	53.99	54.30	54.61	54.94	55.26	55.60	7
K_3AsO_4	51.5*			55.6*								73*	7
$K_3Fe(CN)_6$	23.9	27.6	31.1	32.8	34.3	37.2	39.6	41.7	43.5	45.0	46.1	47.0	6
K_3PO_4	44.3			51.4									7
$K_4Fe(CN)_6$	12.5	17.3	22.0	23.9	25.6	29.2	32.5	35.5	38.2	40.6	41.4	43.1	6
$LaCl_3$	49.0	48.5	48.6	48.9	49.3	50.5	52.1	54.0	56.3	58.9	61.7		6
$La(NO_3)_3$	55.0	56.9	58.9	60.0	61.1	63.6	66.3	69.9*	74.1*				1:13
LiBr	58.4	60.1	62.7	64.4	65.9	67.8	68.3	69.0	69.8	70.7	71.7	72.8	6
$LiBrO_3$	61.03	62.62	64.44	65.44	66.51	68.90	71.68*	73.24*	74.43	75.66	76.93	78.32	1:30
$LiC_2H_3O_2$	23.76	26.49	29.42	31.02	32.72	36.48	40.65	45.15	49.93	54.91	60.04	65.26	7
LiCl	40.45	42.46*	45.29*	45.81	46.25	47.30	48.47	49.78	51.27	52.98	54.98*	56.34*	1:47

Compound	0°C	10°C	20°C	25°C	30°C	40°C	50°C	60°C	70°C	80°C	90°C	100°C	Ref.
$LiClO_3$	73.2	75.6*	80.8*	82.1	83.4	85.9*	87.1*	88.2	89.6	91.3	93.4	95.7	1:30
$LiClO_4$	30.1	32.6	35.5	37.0	38.6	41.9	45.5	49.2	53.2	57.2	61.3	71.4	6
LiF	0.120	0.126	0.131	0.134									7
LiH_2PO_4	55.8												7
LiI	59.4	60.5	61.7	62.3	63.0	64.3	65.8	67.3	68.8	81.3	81.7	82.6	6
$LiIO_3$				43.8									1:30
$LiNO_2$	41	45	49	51	53	56	60	63	66	68			10
$LiNO_3$	34.8	37.6	42.7	50.5	57.9	60.1	62.2	64.0	65.7	67.2	68.5	69.7	6
LiOH	10.8	10.8	11.0	11.1	11.3	11.7	12.2	12.7	13.4	14.2	15.1	16.1	6
LiSCN				54.5									7
Li_2CO_3	1.54	1.43	1.33	1.28	1.24	1.15	1.07	0.99	0.92	0.85	0.78	0.72	7
$Li_2C_2O_4$				5.87									7
Li_2HPO_3	9.07	8.40	7.77	7.47	7.18	6.64	6.16	5.71	5.30	4.91	4.53	4.16	7
Li_2SO_4	26.3	25.9	25.6	25.5	25.3	25.0	24.8	24.5	24.3	24.0	23.8	23.6	6
Li_3PO_4				0.027									1:31
$Lu(NO_3)_3$				71.1									1:13
$MgBr_2$	49.3	49.8	50.3	50.6	50.9	51.5	52.1	52.8	53.5	54.2	55.0	55.7	6
$Mg(BrO_3)_2$	43.0	45.2	48.0	49.4	51.0	54.3	57.9	61.6	65.3	69.0*	70.9*	71.7	1:14
$Mg(C_2H_3O_2)_2$	36.18	37.55	38.92	39.61									7
MgC_2O_4				0.038									7
$MgCl_2$	33.96	34.85	35.58	35.90	36.20	36.77	37.34	37.97	38.71	39.62	40.75	42.15	8
$Mg(ClO_3)_2$	53.35	54.40	56.81	58.66	60.91*	65.46*	67.33	69.27	71.01	72.44	73.48		1:14
$Mg(ClO_4)_2$	47.8	48.7	49.6	50.1	50.5	51.3	52.1						6
$MgCrO_4$	32.06*			35.39*									7
$MgCr_2O_7$				58.9						67.0			7
MgF_2				0.013									7
MgI_2	54.7	56.1	58.2	59.4	60.8	63.9	65.0	65.0	65.0	65.0	65.1	65.2	6
$Mg(IO_3)_2$	3.19*	6.70*	7.92	8.52	9.11	10.45	11.99	13.7	15.6	17.6	19.6		1:14
$Mg(NO_2)_2$				47									7
$Mg(NO_3)_2$	38.4	39.5	40.8	41.6	42.4	44.1	45.9	47.9	50.0	52.2	70.6	72.0	6
$MgSO_3$	0.32	0.37	0.46	0.52	0.61	0.87*	0.85*	0.76	0.69	0.64	0.62	0.60	1:26
$MgSO_4$	18.2	21.7	25.1	26.3	28.2	30.9	33.4	35.6	36.9	35.9	34.7	33.3	6
MgS_2O_3	30.7			34.1									7
$MgSeO_4$	31.4*			35.7*								47*	7
$MnBr_2$	56.00	57.72	59.39	60.19	60.96	62.41	63.75	65.01	66.19	67.32	68.42	69.50	7
$MnCl_2$	38.7	40.6	42.5	43.6	44.7	47.0	49.4	54.1	54.7	55.2	55.7	56.1	6
MnF_2	0.80*			1.01*								0.48	7
$Mn(IO_3)_2$				0.27							0.34		7
$Mn(NO_3)_2$	50.5			61.7									7
$MnSO_4$	34.6	37.3	38.6	38.9	38.9	37.7	36.3	34.6	32.8	30.8	28.8	26.7	6
NH_4Br	37.5	40.2	42.7	43.9	45.1	47.3	49.4	51.3	53.0	54.6	56.1	57.4	7
NH_4Cl	22.92	25.12	27.27	28.34	29.39	31.46	33.50	35.49	37.46	39.40	41.33	43.24	1:47
NH_4ClO_4	10.8	14.1	17.8	19.7	21.7	25.8	29.8	33.6	37.3	40.7	43.8	46.6	6
NH_4F	41.7	43.2	44.7	45.5	46.3	47.8	49.3	50.9	52.5	54.1			7
NH_4HCO_3	10.6	13.7	17.6	19.9	22.4	27.9	34.2	41.4	49.3	58.1	67.6	78.0	7
$NH_4H_2AsO_4$	25.2	29.0	32.7	34.5	36.3	39.7	43.1	46.2	49.3	52.2	55.0		7
$NH_4H_2PO_4$	17.8	22.0	26.4	28.8	31.2	36.2	41.6	47.2	53.0	59.2	65.7	72.4	7
NH_4I	60.7	62.1	63.4	64.0	64.6	65.8	66.8	67.8	68.7	69.6	70.4	71.1	6
NH_4IO_3				3.70	4.20	5.64	7.63						1:30
NH_4NO_2	55.7	59.0	64.9	68.8									7
NH_4NO_3	54.0	60.1	65.5	68.0	70.3	74.3	77.7	80.8	83.4	85.8	88.2	90.3	6
NH_4SCN				64.4					81.1				7
$(NH_4)_2C_2O_4$	2.31	3.11	4.25	4.94	5.73	7.56	9.73	12.2	15.1	18.3	21.8	25.7	7
$(NH_4)_2HPO_4$	36.4	38.2	40.0	41.0	42.0	44.1	46.2	48.5	50.9	53.3	55.9	58.6	7
$(NH_4)_2S_2O_5$	65.5	67.9	69.8	70.5	71.3	72.3	72.9	73.1					1:26
$(NH_4)_2S_2O_8$	37.00	40.45	43.84	45.49	47.11	50.25	53.28	56.23	59.13	62.00			7
$(NH_4)_2SO_3$	32.2	34.9	37.7	39.1	40.6	43.7	47.0	50.6	54.5	58.9			1:26
$(NH_4)_2SO_4$	41.3	42.1	42.9	43.3	43.8	44.7	45.6	46.6	47.5	48.5	49.5	50.5	6
$(NH_4)_2SeO_3$	49.0	51.1	53.4	54.7	56.0	58.9	62.0	65.4	69.1				7
$(NH_4)_2SeO_4$				54.02									7
$(NH_4)_3PO_4$				15.5									7

Compound	0°C	10°C	20°C	25°C	30°C	40°C	50°C	60°C	70°C	80°C	90°C	100°C	Ref.
NaBr	44.4	45.9	47.7	48.6	49.6	51.6	53.7	54.1	54.3	54.5	54.7	54.9	6
$NaBrO_3$	20.0	23.22	26.65	28.28	29.86	32.83	35.55	38.05	40.37	42.52			1:30
$NaCHO_2$	30.8	37.9	45.7	48.7	50.6	52.0	53.5	55.0					6
$NaC_2H_3O_2$	26.5	28.8	31.8	33.5	35.5	39.9	45.1	58.3	59.3	60.5	61.7	62.9	6
NaCl	26.28	26.32	26.41	26.45	26.52	26.67	26.84	27.03	27.25	27.50	27.78	28.05	1:47
NaClO	22.7			44.4									7
$NaClO_2$				97.0*				95.3*					7
$NaClO_3$	44.27	46.67	49.3	50.1	51.2	53.6	55.5	57.0	58.5	60.5	63.3	67.1	1:30
$NaClO_4$	61.9	64.1	66.2	67.2	68.3	70.4	72.5	74.1	74.7	75.4	76.1	76.7	6
NaF	3.52	3.72	3.89	3.97	4.05	4.20	4.34	4.46	4.57	4.66	4.75	4.82	6
$NaHCO_3$	6.48	7.59	8.73	9.32	9.91	11.13	12.40	13.70	15.02	16.37	17.73	19.10	7
$NaHSO_4$				22.2								33.3	10
NaH_2PO_4	36.54	41.07	46.00	48.68	51.54	57.89*	61.7*	62.3*	65.9	68.7			1:31
NaI	61.2	62.4	63.9	64.8	65.7	67.7	69.8	72.0	74.7	74.8	74.9	75.1	6
$NaIO_3$	2.43	4.40	7.78*	8.65*	9.60	11.67	13.99	16.52	19.25*	21.1*	22.9	24.7	1:30
$NaIO_4$				12.62									7
$NaNO_2$	41.9	43.4	45.1	45.9	46.8	48.7	50.7	52.8	55.0	57.2	59.5	61.8	6
$NaNO_3$	42.2	44.4	46.6	47.7	48.8	51.0	53.2	55.3	57.5	59.6	61.7	63.8	6
NaOH	30	39	46	50	53	58	63	67	71	74	76	79	10
NaSCN		52.9	57.1	60.2	62.7	63.5	64.2	65.0	65.9	66.9	67.9	69.0	6
$Na_2B_4O_7$	1.23	1.71	2.50	3.07	3.82	6.02	9.7	14.9	17.1	19.9	23.5	28.0	6
Na_2CO_3	6.44	10.8	17.9	23.5	28.7	32.8	32.2	31.7	31.3	31.1	30.9	30.9	6
$Na_2C_2O_4$	2.62	2.95	3.30	3.48	3.65	4.00	4.36	4.71	5.06	5.41	5.75	6.08	6
Na_2CrO_4	22.6	32.3	44.6	46.7	46.9	48.9	51.0	53.4	55.3	55.5	55.8	56.1	6
$Na_2Cr_2O_7$	62.1	63.1	64.4	65.2	66.1	68.0	70.1	72.3	74.6	77.0	79.6	80.7	6
Na_2HAsO_4	5.6*			29.3*								67*	7
Na_2HPO_4	1.66	4.19	7.51	10.55	16.34*	35.17*	44.64*	45.20	46.81	48.78	50.52	51.53	1:31
Na_2MoO_4	30.6	38.8	39.4	39.4	39.8	40.3	41.0	41.7	42.6	43.5	44.5	45.5	6
Na_2S	11.1	13.2	15.7	17.1	18.6	22.1	26.7	28.1	30.2	33.0	36.4	41.0	6
Na_2SO_3	12.0	16.1	20.9	23.5	26.3*	27.3*	25.9	24.8	23.7	22.8	22.1	21.5	1:26
Na_2SO_4			16.13	21.94	29.22*	32.35*	31.55	30.90	30.39	30.02	29.79	29.67	8
$Na_2S_2O_3$	33.1	36.3	40.6	43.3	45.9	52.0	62.3	65.7	68.8	69.4	70.1	71.0	6
$Na_2S_2O_5$		38.4	39.5	40.0	40.6	41.8	43.0	44.2	45.5	46.8	48.1	49.5	1:26
Na_2SeO_3				47.3*								45*	7
Na_2SeO_4	11.7			36.9*								42.1*	7
Na_2WO_4	41.6	41.9	42.3	42.6	42.9	43.6	44.4	45.3	46.2	47.3	48.4	49.5	6
Na_3PO_4	4.28	7.30	10.8	12.6	14.1	16.6	22.9	28.4	32.4	37.6	40.4	43.5	6
$Na_4P_2O_7$	2.23	3.28	4.81	6.62	7.00	10.10	14.38	20.07	27.31	36.03	32.37	30.67	6
$NdCl_3$	49.0	49.3	49.7	50.0	50.4	51.2	52.2	53.3	54.5	55.8	57.1	58.5	6
$Nd(NO_3)_3$	55.76	57.49	59.37	60.38	61.43	63.69	66.27	69.47					1:13
$NiCl_2$	34.7	36.1	38.5	40.3	41.7	42.1	43.2	45.0	46.1	46.2	46.4	46.6	6
$Ni(ClO_4)_2$	51.1			52.8									7
NiF_2				2.50							2.52		7
NiI_2	55.40	57.68	59.78	60.69	61.50	62.80	63.73	64.38	64.80	65.09	65.30		7
$Ni(NO_3)_2$	44.1	46.0	48.4	49.8	51.3	54.6	58.3	61.0	63.1	65.6	67.9	69.0	6
$NiSO_4$	21.4	24.4	27.4	28.8	30.3*	32.0*	34.1	35.8	37.7	39.9	42.3	44.8	6
$Ni(SCN)_2$				35.48									7
$NiSeO_4$	21.6		26.2*									45.6*	7
$PbBr_2$	0.449	0.620	0.841	0.966	1.118	1.46	1.89						2
$PbCl_2$	0.66	0.81	0.98	1.07	1.17	1.39	1.64	1.93	2.24	2.60	2.99	3.42	2
$Pb(ClO_4)_2$				81.5									7
PbF_2		0.0603	0.0649	0.0670	0.0693								2
PbI_2	0.041	0.052	0.067	0.076	0.086	0.112	0.144	0.187	0.243	0.315			2
$Pb(IO_3)_2$				0.0025									7
$Pb(NO_3)_2$	28.46	32.13	35.67	37.38	39.05	42.22	45.17	47.90	50.42	52.72	54.82	56.75	2
$PbSO_4$	0.0033	0.0038	0.0042	0.0044	0.0047	0.0052	0.0058						2
$PrCl_3$	48.0	48.1	48.6	49.0	49.5	50.8	52.3	54.1	56.1	58.3			6
$Pr(NO_3)_3$	57.50	59.20	61.16	62.24	63.40*	65.7*	67.8	70.2	73.4				1:13
RbBr	47.4	50.1	52.6	53.8	54.9	57.0	58.8	60.6	62.1	63.5	64.8	65.9	6
$RbBrO_3$	0.97	1.55	2.36	2.87	3.45	4.87	6.64	8.78	11.29	14.15	17.32	20.76	1:30
RbCl	43.58	45.65	47.53	48.42	49.27	50.86	52.34	53.67	54.92	56.08	57.16	58.15	1:47

Compound	0°C	10°C	20°C	25°C	30°C	40°C	50°C	60°C	70°C	80°C	90°C	100°C	Ref.
$RbClO_3$	2.10	3.38	5.14	6.22	7.45	10.35	13.85	17.93	22.53	27.57	32.96	38.60	1:30
$RbClO_4$	1			1.5								17	7
RbF			75										7
$RbHCO_3$			53.7										7
RbI	55.8	58.6	61.1	62.3	63.4	65.4	67.2	68.8	70.3	71.6	72.7	73.8	6
$RbIO_3$	1.09	1.53	2.07	2.38	2.74	3.52	4.41	5.42	6.52	7.74	9.00	10.36	1:30
$RbNO_3$	16.4	25.0	34.6	39.4	44.2	53.1	60.8	67.2	72.2	76.1	79.0	81.2	6
RbOH					63.4								7
Rb_2CrO_4	38.27			43.26									7
Rb_2SO_4	27.3	30.0	32.5	33.7	34.8	36.9	38.7	40.3	41.8	43.0	44.1	44.9	6
$SbCl_3$	85.7			90.8									7
SbF_3	79.4			83.1									7
$Sc(NO_3)_3$	57.0	59.3	61.6	62.8	63.9	66.2	68.5						1:13
$Sm(NO_3)_3$	54.83	56.33	58.08	59.05	60.08	62.38	65.05*	68.1*	70.8	74.2			1:13
$SmCl_3$		48.0	48.2	48.4	48.6	49.2	50.0						6
$SnCl_2$	46	64											7
SnI_2			0.97									3.87	7
$SrBr_2$	46.0	48.3	50.6	51.7	52.9	55.2	57.6	59.9	62.3	64.6	66.8	69.0	6
$Sr(BrO_3)_2$	18.53	22.00	25.39	27.02	28.59	31.55	34.21	36.57	38.64*	40.2*	40.8	41.0	1:14
$SrCl_2$	31.94	32.93	34.43	35.37	36.43	38.93	41.94	45.44*	46.81*	47.69	48.70	49.87	8
$Sr(ClO_2)_2$	13.0	13.6	14.1	14.3	14.5	14.9	15.3	15.6	15.9				7
$Sr(ClO_3)_2$	63.29	63.42	63.64	63.77	63.93	64.29	64.70	65.16	65.65	66.18	66.74	67.31	1:14
$Sr(ClO_4)_2$	70.04*			75.35*		78.44*							7
SrF_2	0.011			0.021									7
SrI_2	62.5	62.8	63.5	63.9	64.5	65.8	67.3	69.0	70.8	72.7	74.7	79.2	6
$Sr(IO_3)_2$	0.102	0.126	0.152	0.165	0.179	0.206	0.233	0.259	0.284	0.307	0.328	0.346	1:14
$Sr(MnO_4)_2$	2.5												7
$Sr(NO_2)_2$					41.9	44.3						58.6	7
$Sr(NO_3)_2$	28.2	34.6	41.0	44.5	47.0	47.4	47.9	48.4	48.9	49.5	50.1	50.7	6
$Sr(OH)_2$	0.9			2.2									7
$SrSO_3$				0.0015									1:26
$SrSO_4$				0.0135									7
SrS_2O_3	8.8	13.2	17.7	20.0	22.2	26.8							7
$Tb(NO_3)_3$			60.6	61.02									1:13
Tl_2SO_4	2.65	3.56	4.61	5.19	5.80	7.09	8.46	9.89	11.33	12.77	14.18	15.53	6
$Tm(NO_3)_3$				67.9									1:13
$UO_2(NO_3)_2$	49.52	51.82	54.42	55.85	57.55	61.59	67.07						1:55
$Y(NO_3)_3$	55.57	56.93	58.75	59.86	61.11*	63.3*	64.9	67.9	72.5				1:13
$Yb(NO_3)_3$				70.5									1:13
$ZnBr_2$	79.3	80.1	81.8	83.0	84.1	85.6	85.8	86.1	86.3	86.6	86.8	87.1	6
ZnC_2O_4		0.0010	0.0019	0.0026									5
$ZnCl_2$		76.6	79.0	80.3	81.4	81.8	82.4	83.0	83.7	84.4	85.2	86.0	6
$Zn(ClO_4)_2$	44.29*			46.27*			48.70						7
ZnF_2				1.53									5
ZnI_2	81.1	81.2	81.3	81.4	81.5	81.7	82.0	82.3	82.6	83.0	83.3	83.7	6
$Zn(IO_3)_2$			0.58	0.64	0.69	0.77	0.82						5
$Zn(NO_3)_2$	47.8	50.8	54.4	54.6	58.5	79.1	80.1	87.5	89.9				6
$ZnSO_3$			0.1786	0.1790	0.1794	0.1803	0.1812						5
$ZnSO_4$	29.1	32.0	35.0	36.6	38.2	41.3	43.0	42.1	41.0	39.9	38.8	37.6	6
$ZnSeO_4$	33.06	34.98	37.38	38.79	40.34								5

SOLUBILITY PRODUCT CONSTANTS

The solubility product constant K_{sp} is a useful parameter for calculating the aqueous solubility of sparingly soluble compounds under various conditions. It may be determined by direct measurement or calculated from the standard Gibbs energies of formation $\Delta_f G°$ of the species involved at their standard states. Thus if $K_{sp} = [M^+]^m$, $[A^-]^n$ is the equilibrium constant for the reaction

$$M_mA_n(s) \rightleftharpoons mM^+(aq) + nA^-(aq),$$

where M_mA_n is the slightly soluble substance and M^+ and A^- are the ions produced in solution by the dissociation of M_mA_n, then the Gibbs energy change is

$$\Delta G° = m\,\Delta_f G°\,(M^+,aq) + n\;\Delta_f G°\,(A^-,aq) - \Delta_f G°\,(M_mA_n, s)$$

The solubility product constant is calculated from the equation

$$\ln K_{sp} = -\Delta\, G°/RT$$

The first table below gives selected values of K_{sp} at 25°C. Many of these have been calculated from standard state thermodynamic data in References 1 and 2; other values are taken from publications of the IUPAC Solubility Data Project (References 3 to 7).

The above formulation is not convenient for treating sulfides because the S^{-2} ion is usually not present in significant concentrations (see Reference 8). This is due to the hydrolysis reaction

$$S^{-2} + H_2O \rightleftharpoons HS^- + OH^-$$

which is strongly shifted to the right except in very basic solutions. Furthermore, the equilibrium constant for this reaction, which depends on the second ionization constant of H_2S, is poorly known. Therefore it is more useful in the case of sulfides to define a different solubility product K_{spa} based on the reaction

$$M_mS_n(s) + 2H^+ \rightleftharpoons mM^+ + nH_2S\,(aq)$$

Values of K_{spa}, taken from Reference 8, are given for several sulfides in the auxiliary table following the main table. Additional discussion of sulfide equilibria may be found in References 7 and 9.

References

1. Wagman, D. D., Evans, W. H., Parker, V. B., Schumm, R. H., Halow, I., Bailey, S. M., Churney, K. L., and Nuttall, R. L., *The NBS Tables of Chemical Thermodynamic Properties, J. Phys. Chem. Ref. Data*, Vol. 11, Suppl. 2, 1982.
2. Garvin, D., Parker, V. B., and White, H. J., *CODATA Thermodynamic Tables*, Hemisphere, New York, 1987.
3. *Solubility Data Series* (53 Volumes), International Union of Pure and Applied Chemistry, Pergamon Press, Oxford, 1979–1992.
4. Clever, H. L., and Johnston, F. J., *J. Phys. Chem. Ref. Data*, 9, 751, 1980.
5. Marcus, Y., *J. Phys. Chem. Ref. Data*, 9, 1307, 1980.
6. Clever, H. L., Johnson, S. A., and Derrick, M. E., *J. Phys. Chem. Ref. Data*, 14, 631, 1985.
7. Clever, H. L., Johnson, S. A., and Derrick, M. E., *J. Phys. Chem. Ref. Data*, 21, 941, 1992.
8. Myers, R. J., *J. Chem. Educ.*, 63, 687, 1986.
9. Licht, S., *J. Electrochem. Soc.*, 135, 2971, 1988.

Compound	Formula	K_{sp}
Aluminum phosphate	$AlPO_4$	$9.84 \cdot 10^{-21}$
Barium bromate	$Ba(BrO_3)_2$	$2.43 \cdot 10^{-4}$
Barium carbonate	$BaCO_3$	$2.58 \cdot 10^{-9}$
Barium chromate	$BaCrO_4$	$1.17 \cdot 10^{-10}$
Barium fluoride	BaF_2	$1.84 \cdot 10^{-7}$
Barium hydroxide octahydrate	$Ba(OH)_2 \cdot 8H_2O$	$2.55 \cdot 10^{-4}$
Barium iodate	$Ba(IO_3)_2$	$4.01 \cdot 10^{-9}$
Barium iodate monohydrate	$Ba(IO_3)_2 \cdot H_2O$	$1.67 \cdot 10^{-9}$
Barium molybdate	$BaMoO_4$	$3.54 \cdot 10^{-8}$
Barium nitrate	$Ba(NO_3)_2$	$4.64 \cdot 10^{-3}$
Barium selenate	$BaSeO_4$	$3.40 \cdot 10^{-8}$
Barium sulfate	$BaSO_4$	$1.08 \cdot 10^{-10}$
Barium sulfite	$BaSO_3$	$5.0 \cdot 10^{-10}$
Beryllium hydroxide	$Be(OH)_2$	$6.92 \cdot 10^{-22}$
Bismuth arsenate	$BiAsO_4$	$4.43 \cdot 10^{-10}$
Bismuth iodide	BiI_3	$7.71 \cdot 10^{-19}$
Cadmium arsenate	$Cd_3(AsO_4)_2$	$2.2 \cdot 10^{-33}$
Cadmium carbonate	$CdCO_3$	$1.0 \cdot 10^{-12}$
Cadmium fluoride	CdF_2	$6.44 \cdot 10^{-3}$
Cadmium hydroxide	$Cd(OH)_2$	$7.2 \cdot 10^{-15}$
Cadmium iodate	$Cd(IO_3)_2$	$2.5 \cdot 10^{-8}$
Cadmium oxalate trihydrate	$CdC_2O_4 \cdot 3H_2O$	$1.42 \cdot 10^{-8}$
Cadmium phosphate	$Cd_3(PO_4)_2$	$2.53 \cdot 10^{-33}$
Calcium carbonate (calcite)	$CaCO_3$	$3.36 \cdot 10^{-9}$
Calcium fluoride	CaF_2	$3.45 \cdot 10^{-11}$
Calcium hydroxide	$Ca(OH)_2$	$5.02 \cdot 10^{-6}$

Compound	Formula	K_{sp}
Calcium iodate	$Ca(IO_3)_2$	$6.47 \cdot 10^{-6}$
Calcium iodate hexahydrate	$Ca(IO_3)_2 \cdot 6H_2O$	$7.10 \cdot 10^{-7}$
Calcium molybdate	$CaMoO_4$	$1.46 \cdot 10^{-8}$
Calcium oxalate monohydrate	$CaC_2O_4 \cdot H_2O$	$2.32 \cdot 10^{-9}$
Calcium phosphate	$Ca_3(PO_4)_2$	$2.07 \cdot 10^{-33}$
Calcium sulfate	$CaSO_4$	$4.93 \cdot 10^{-5}$
Calcium sulfate dihydrate	$CaSO_4 \cdot 2H_2O$	$3.14 \cdot 10^{-5}$
Calcium sulfite hemihydrate	$CaSO_3 \cdot 0.5H_2O$	$3.1 \cdot 10^{-7}$
Cesium perchlorate	$CsClO_4$	$3.95 \cdot 10^{-3}$
Cesium periodate	$CsIO_4$	$5.16 \cdot 10^{-6}$
Cobalt(II) arsenate	$Co_3(AsO_4)_2$	$6.80 \cdot 10^{-29}$
Cobalt(II) hydroxide (blue)	$Co(OH)_2$	$5.92 \cdot 10^{-15}$
Cobalt(II) iodate dihydrate	$Co(IO_3)_2 \cdot 2H_2O$	$1.21 \cdot 10^{-2}$
Cobalt(II) phosphate	$Co_3(PO_4)_2$	$2.05 \cdot 10^{-35}$
Copper(I) bromide	CuBr	$6.27 \cdot 10^{-9}$
Copper(I) chloride	CuCl	$1.72 \cdot 10^{-7}$
Copper(I) cyanide	CuCN	$3.47 \cdot 10^{-20}$
Copper(I) iodide	CuI	$1.27 \cdot 10^{-12}$
Copper(I) thiocyanate	CuSCN	$1.77 \cdot 10^{-13}$
Copper(II) arsenate	$Cu_3(AsO_4)_2$	$7.95 \cdot 10^{-36}$
Copper(II) iodate monohydrate	$Cu(IO_3)_2 \cdot H_2O$	$6.94 \cdot 10^{-8}$
Copper(II) oxalate	CuC_2O_4	$4.43 \cdot 10^{-10}$
Copper(II) phosphate	$Cu_3(PO_4)_2$	$1.40 \cdot 10^{-37}$
Europium(III) hydroxide	$Eu(OH)_3$	$9.38 \cdot 10^{-27}$
Gallium(III) hydroxide	$Ga(OH)_3$	$7.28 \cdot 10^{-36}$
Iron(II) carbonate	$FeCO_3$	$3.13 \cdot 10^{-11}$

Compound	Formula	K_{sp}
Iron(II) fluoride	FeF_2	$2.36 \cdot 10^{-6}$
Iron(II) hydroxide	$Fe(OH)_2$	$4.87 \cdot 10^{-17}$
Iron(III) hydroxide	$Fe(OH)_3$	$2.79 \cdot 10^{-39}$
Iron(III) phosphate dihydrate	$FePO_4 \cdot 2H_2O$	$9.91 \cdot 10^{-16}$
Lanthanum iodate	$La(IO_3)_3$	$7.50 \cdot 10^{-12}$
Lead(II) bromide	$PbBr_2$	$6.60 \cdot 10^{-6}$
Lead(II) carbonate	$PbCO_3$	$7.40 \cdot 10^{-14}$
Lead(II) chloride	$PbCl_2$	$1.70 \cdot 10^{-5}$
Lead(II) fluoride	PbF_2	$3.3 \cdot 10^{-8}$
Lead(II) hydroxide	$Pb(OH)_2$	$1.43 \cdot 10^{-20}$
Lead(II) iodate	$Pb(IO_3)_2$	$3.69 \cdot 10^{-13}$
Lead(II) iodide	PbI_2	$9.8 \cdot 10^{-9}$
Lead(II) selenate	$PbSeO_4$	$1.37 \cdot 10^{-7}$
Lead(II) sulfate	$PbSO_4$	$2.53 \cdot 10^{-8}$
Lithium carbonate	Li_2CO_3	$8.15 \cdot 10^{-4}$
Lithium fluoride	LiF	$1.84 \cdot 10^{-3}$
Lithium phosphate	Li_3PO_4	$2.37 \cdot 10^{-11}$
Magnesium carbonate	$MgCO_3$	$6.82 \cdot 10^{-6}$
Magnesium carbonate trihydrate	$MgCO_3 \cdot 3H_2O$	$2.38 \cdot 10^{-6}$
Magnesium carbonate pentahydrate	$MgCO_3 \cdot 5H_2O$	$3.79 \cdot 10^{-6}$
Magnesium fluoride	MgF_2	$5.16 \cdot 10^{-11}$
Magnesium hydroxide	$Mg(OH)_2$	$5.61 \cdot 10^{-12}$
Magnesium oxalate dihydrate	$MgC_2O_4 \cdot 2H_2O$	$4.83 \cdot 10^{-6}$
Magnesium phosphate	$Mg_3(PO_4)_2$	$1.04 \cdot 10^{-24}$
Manganese(II) carbonate	$MnCO_3$	$2.24 \cdot 10^{-11}$
Manganese(II) iodate	$Mn(IO_3)_2$	$4.37 \cdot 10^{-7}$
Manganese(II) oxalate dihydrate	$MnC_2O_4 \cdot 2H_2O$	$1.70 \cdot 10^{-7}$
Mercury(I) bromide	Hg_2Br_2	$6.40 \cdot 10^{-23}$
Mercury(I) carbonate	Hg_2CO_3	$3.6 \cdot 10^{-17}$
Mercury(I) chloride	Hg_2Cl_2	$1.43 \cdot 10^{-18}$
Mercury(I) fluoride	Hg_2F_2	$3.10 \cdot 10^{-6}$
Mercury(I) iodide	Hg_2I_2	$5.2 \cdot 10^{-29}$
Mercury(I) oxalate	$Hg_2C_2O_4$	$1.75 \cdot 10^{-13}$
Mercury(I) sulfate	Hg_2SO_4	$6.5 \cdot 10^{-7}$
Mercury(I) thiocyanate	$Hg_2(SCN)_2$	$3.2 \cdot 10^{-20}$
Mercury(II) bromide	$HgBr_2$	$6.2 \cdot 10^{-20}$
Mercury(II) iodide	HgI_2	$2.9 \cdot 10^{-29}$
Neodymium carbonate	$Nd_2(CO_3)_3$	$1.08 \cdot 10^{-33}$
Nickel(II) carbonate	$NiCO_3$	$1.42 \cdot 10^{-7}$
Nickel(II) hydroxide	$Ni(OH)_2$	$5.48 \cdot 10^{-16}$
Nickel(II) iodate	$Ni(IO_3)_2$	$4.71 \cdot 10^{-5}$
Nickel(II) phosphate	$Ni_3(PO_4)_2$	$4.74 \cdot 10^{-32}$
Palladium(II) thiocyanate	$Pd(SCN)_2$	$4.39 \cdot 10^{-23}$
Potassium hexachloroplatinate	K_2PtCl_6	$7.48 \cdot 10^{-6}$
Potassium perchlorate	$KClO_4$	$1.05 \cdot 10^{-2}$
Potassium periodate	KIO_4	$3.71 \cdot 10^{-4}$
Praseodymium hydroxide	$Pr(OH)_3$	$3.39 \cdot 10^{-24}$

Compound	Formula	K_{sp}
Radium iodate	$Ra(IO_3)_2$	$1.16 \cdot 10^{-9}$
Radium sulfate	$RaSO_4$	$3.66 \cdot 10^{-11}$
Rubidium perchlorate	$RbClO_4$	$3.00 \cdot 10^{-3}$
Scandium fluoride	ScF_3	$5.81 \cdot 10^{-24}$
Scandium hydroxide	$Sc(OH)_3$	$2.22 \cdot 10^{-31}$
Silver(I) acetate	$AgCH_3COO$	$1.94 \cdot 10^{-3}$
Silver(I) arsenate	Ag_3AsO_4	$1.03 \cdot 10^{-22}$
Silver(I) bromate	$AgBrO_3$	$5.38 \cdot 10^{-5}$
Silver(I) bromide	$AgBr$	$5.35 \cdot 10^{-13}$
Silver(I) carbonate	Ag_2CO_3	$8.46 \cdot 10^{-12}$
Silver(I) chloride	$AgCl$	$1.77 \cdot 10^{-10}$
Silver(I) chromate	Ag_2CrO_4	$1.12 \cdot 10^{-12}$
Silver(I) cyanide	$AgCN$	$5.97 \cdot 10^{-17}$
Silver(I) iodate	$AgIO_3$	$3.17 \cdot 10^{-8}$
Silver(I) iodide	AgI	$8.52 \cdot 10^{-17}$
Silver(I) oxalate	$Ag_2C_2O_4$	$5.40 \cdot 10^{-12}$
Silver(I) phosphate	Ag_3PO_4	$8.89 \cdot 10^{-17}$
Silver(I) sulfate	Ag_2SO_4	$1.20 \cdot 10^{-5}$
Silver(I) sulfite	Ag_2SO_3	$1.50 \cdot 10^{-14}$
Silver(I) thiocyanate	$AgSCN$	$1.03 \cdot 10^{-12}$
Strontium arsenate	$Sr_3(AsO_4)_2$	$4.29 \cdot 10^{-19}$
Strontium carbonate	$SrCO_3$	$5.60 \cdot 10^{-10}$
Strontium fluoride	SrF_2	$4.33 \cdot 10^{-9}$
Strontium iodate	$Sr(IO_3)_2$	$1.14 \cdot 10^{-7}$
Strontium iodate monohydrate	$Sr(IO_3)_2 \cdot H_2O$	$3.77 \cdot 10^{-7}$
Strontium iodate hexahydrate	$Sr(IO_3)_2 \cdot 6H_2O$	$4.55 \cdot 10^{-7}$
Strontium sulfate	$SrSO_4$	$3.44 \cdot 10^{-7}$
Thallium(I) bromate	$TlBrO_3$	$1.10 \cdot 10^{-4}$
Thallium(I) bromide	$TlBr$	$3.71 \cdot 10^{-6}$
Thallium(I) chloride	$TlCl$	$1.86 \cdot 10^{-4}$
Thallium(I) chromate	Tl_2CrO_4	$8.67 \cdot 10^{-13}$
Thallium(I) iodate	$TlIO_3$	$3.12 \cdot 10^{-6}$
Thallium(I) iodide	TlI	$5.54 \cdot 10^{-8}$
Thallium(I) thiocyanate	$TlSCN$	$1.57 \cdot 10^{-4}$
Thallium(III) hydroxide	$Tl(OH)_3$	$1.68 \cdot 10^{-44}$
Tin(II) hydroxide	$Sn(OH)_2$	$5.45 \cdot 10^{-27}$
Yttrium carbonate	$Y_2(CO_3)_3$	$1.03 \cdot 10^{-31}$
Yttrium fluoride	YF_3	$8.62 \cdot 10^{-21}$
Yttrium hydroxide	$Y(OH)_3$	$1.00 \cdot 10^{-22}$
Yttrium iodate	$Y(IO_3)_3$	$1.12 \cdot 10^{-10}$
Zinc arsenate	$Zn_3(AsO_4)_2$	$2.8 \cdot 10^{-28}$
Zinc carbonate	$ZnCO_3$	$1.46 \cdot 10^{-10}$
Zinc carbonate monohydrate	$ZnCO_3 \cdot H_2O$	$5.42 \cdot 10^{-11}$
Zinc fluoride	ZnF_2	$3.04 \cdot 10^{-2}$
Zinc hydroxide	$Zn(OH)_2$	$3 \cdot 10^{-17}$
Zinc iodate dihydrate	$Zn(IO_3)_2 \cdot 2H_2O$	$4.1 \cdot 10^{-6}$
Zinc oxalate dihydrate	$ZnC_2O_4 \cdot 2H_2O$	$1.38 \cdot 10^{-9}$
Zinc selenide	$ZnSe$	$3.6 \cdot 10^{-26}$
Zinc selenite monohydrate	$ZnSeO_3 \cdot H_2O$	$1.59 \cdot 10^{-7}$

Sulfides

Compound	**Formula**	K_{spa}
Cadmium sulfide	CdS	$8 \cdot 10^{-7}$
Copper(II) sulfide	CuS	$6 \cdot 10^{-16}$
Iron(II) sulfide	FeS	$6 \cdot 10^{2}$
Lead(II) sulfide	PbS	$3 \cdot 10^{-7}$
Manganese(II) sulfide (green)	MnS	$3 \cdot 10^{7}$
Mercury(II) sulfide (red)	HgS	$4 \cdot 10^{-33}$
Mercury(II) sulfide (black)	HgS	$2 \cdot 10^{-32}$
Silver(I) sulfide	Ag_2S	$6 \cdot 10^{-30}$
Tin(II) sulfide	SnS	$1 \cdot 10^{-5}$
Zinc sulfide (sphalerite)	ZnS	$2 \cdot 10^{-4}$
Zinc sulfide (wurtzite)	ZnS	$3 \cdot 10^{-2}$

SOLUBILITY CHART

Abbreviations: **W**, soluble in water; **A**, insoluble in water but soluble in acids; **w**, sparingly soluble in water but soluble in acids; **a**, insoluble in water and only sparingly soluble in acids; **I,** insoluble in water and acids; **d**, decomposes in water. * Indicates two modifications of the salt.

No.		Al	NH_4	Sb	Ba	Bi	Cd	Ca	Cr	Co	Cu	Au (I)	Au (II)	H	Fe (II)	Fe (III)
1	Acetate	W	W		W	W	W	W	W	W	W	W	W	W		
	—$(C_2H_3O_2)$	$Al(—)_3$	$NH_4(—)$		$Ba(—)_2$	$Bi(—)_3$	$Cd(—)_2$	$Ca(—)_2$	$Cr(—)_3$	$Co(—)_2$	$Cu(—)_2$			$C_2H_4O_2$	$Fe(—)_2$	$Fe_2(—)_6$
2	Arsenate	a	W	A	w	A	A	w		A	A			W	A	A
	—(AsO_4)	$Al(—)$	$(NH_4)_3(—)$	$Sb(—)$	$Ba_3(—)_2$	$Bi(—)$	$Cd_3(—)_2$	$Ca_3(—)_2$		$Co_3(—)_2$	$Cu_3(—)_2$			H_3AsO_4	$Fe_3(—)_2$	$Fe(—)$
3	Arsenite		W	A				w		A	A					
	—(AsO_3)		NH_4AsO_2	$Sb(—)$				$Ca_3(—)_2$		$Co_3H_6(—)_4$	$CuH(—)$					
4	Benzoate		W		W	A	W	W		W	w			W	W	A
	—$(C_7H_5O_2)$		$NH_4(—)$		$Ba(—)_2$	$Bi(—)_3$	$Cd(—)_2$	$Ca(—)_2$		$Co(—)_2$	$Cu(—)_2$			$C_7H_6O_2$	$Fe(—)_2$	$Fe_2(—)_6$
5	Bromide	W	W	d	W	d	W	W	W(I)*	W	W	w	W	W	W	W
		$AlBr_2$	NH_4Br	$SbBr_3$	$BaBr_2$	$BiBr_3$	$CdBr_2$	$CaBr_2$	$CrBr_3$	$CoBr_2$	$CuBr_2$	AuBr	$AuBr_3$	HBr	$FeBr_2$	$FeBr_3$
6	Carbonate		W		w		A	w	W	A					w	
			$(NH_4)_2CO_3$		$BaCO_3$		$CdCO_3$	$CaCO_3$	$CrCO_3$	$CoCO_3$					$FeCO_3$	
7	Chlorate	W	W		W	W	W	W		W	W			W	W	W
	—(ClO_3)	$Al(—)_3$	$NH_4(—)$		$Ba(—)_2$	$Bi(—)_3$	$Cd(—)_2$	$Ca(—)_2$		$Co(—)_2$	$Cu(—)_2$			$HClO_3$	$Fe(—)_2$	$Fe(—)_3$
8	Chloride	W	W	W	W	d	W	W	I	W	W	w	W	W	W	W
		$AlCl_3$	NH_4Cl	$SbCl_3$	$BaCl_2$	$BiCl_3$	$CdCl_2$	$CaCl_2$	$CrCl_3$	$CoCl_2$	$CuCl_2$	AuCl	$AuCl_3$	HCl	$FeCl_2$	$FeCl_3$
9	Chromate		W		A		A	W		A						A
	—(CrO_4)		$(NH_4)_2(—)$		$Ba(—)$		$Cd(—)$	$Ca(—)$		$Co(—)$						$Fe_2(—)_3$
10	Citrate	W	W		w	A	A	w		w				W		W
	—$(C_6H_5O_7)$	$Al(—)$	$(NH_4)_3(—)$		$Ba_3(—)_2$	$Bi(—)$	$Cd_3(—)_2$	$Ca_3(—)_2$		$Co_3(—)_2$				$C_6H_8O_7$		$Fe(—)$
11	Cyanide		W		W	w	W	W	A	A	A	w	W	W	a	
			NH_4CN		$Ba(CN)_2$	$Bi(CN)_3$	$Cd(CN)_2$	$Ca(CN)_2$	$Cr(CN)_3$	$Co(CN)_2$	$Cu(CN)_2$	AuCN	$Au(CN)_3$	HCN	$Fe(CN)_2$	
12	Ferricy'de		W		w		A	W		I	I			W	I	
	—$(Fe(CN)_6)$		$(NH_4)_3(—)$		$Ba_3(—)_2$		$Cd_3(—)_2$	$Ca_3(—)_2$		$Co_3(—)_2$	$Cu_3(—)_2$			$H_3(—)$	$Fe_3(—)_2$	
13	Ferrocy'de	w	W		W		A	W		I	I			W	I	a
	—$(Fe(CN)_6)$	$Al_4(—)_3$	$(NH_4)_4(—)$		$Ba_2(—)$		$Cd_2(—)$	$Ca_2(—)$		$Co_2(—)$	$Cu_2(—)$			$H_4(—)$	$Fe_2(—)$	$Fe_4(—)_3$
14	Fluoride	W	W	W	w	W	W	w	W(a)*	W	w			W	w	w
		AlF_3	NH_4F	SbF_3	BaF_2	BiF_3	CdF_2	CaF_2	CrF_3	CoF_2	CuF_2			HF	FeF_2	FeF_3
15	Formate	W	W		W	W	W	W		W	W			W	W	W
	—(CHO_2)	$Al(—)_3$	$NH_4(—)$		$Ba(—)_2$	$Bi(—)_3$	$Cd(—)_2$	$Ca(—)_2$		$Co(—)_2$	$Cu(—)_2$			CH_2O_2	$Fe(—)_2$	$Fe(—)_3$
16	Hydroxide	A	W		W	A	A	W	A	A	A	W	A		A	A
		$Al(OH)_3$	NH_4OH		$Ba(OH)_2$	$Bi(OH)_3$	$Cd(OH)_2$	$Ca(OH)_2$	$Cr(OH)_3$	$Co(OH)_2$	$Cu(OH)_2$	AuOH	$Au(OH)_3$		$Fe(OH)_2$	$Fe(OH)_3$
17	Iodide	W	W	d	W	A	W	W	W	W	a	a	a	W	W	W
		AlI_3	NH_4I	SbI_3	BaI_2	BiI_3	CdI_2	CaI_2	CrI_3	CoI_2	CuI	AuI	AuI_3	HI	FeI_2	FeI_3
18	Nitrate	W	W		W	d	W	W	W	W	W			W	W	W
		$Al(NO_3)_3$	NH_4NO_3		$Ba(NO_3)_2$	$Bi(NO_3)_3$	$Cd(NO_3)_2$	$Ca(NO_3)_2$	$Cr(NO_3)_3$	$Co(NO_3)_2$	$Cu(NO_3)_2$			HNO_3	$Fe(NO_3)_2$	$Fe(NO)_3$
19	Oxalate	A	W		w	A	w	A	W	A	A			W	A	W
	—(C_2O_4)	$Al_2(—)_3$	$(NH_4)_2(—)$		$Ba(—)$	$Bi_2(—)_3$	$Cd(—)$	$Ca(—)$	$Cr(—)$	$Co(—)$	$Cu(—)$			$C_2H_2O_4$	$Fe(—)$	$Fe_2(—)_3$
20	Oxide	a		w	W	A	A	w	a	A	A		A	W	A	A
		Al_2O_3		Sb_2O_3	BaO	Bi_2O_3	CdO	CaO	Cr_2O_3	CoO	CuO	Au_2O	Au_2O_3	H_2O_2	FeO	Fe_2O_3
21	Phosphate	A	W		A	A	A	w	w	A	A			W	A	w
		$AlPO_4$	$NH_4H_2PO_4$		$Ba_3(PO_4)_2$	$BiPO_4$	$Cd_3(PO_4)_2$	$Ca_3(PO_4)_2$	$Cr_2(PO_4)_2$	$Co_3(PO_4)_2$	$Cu_3(PO_4)_2$		H_3PO_4	$Fe_3(PO_4)_2$	$FePO_4$	
22	Silicate,	I			W		A	w		A	A			I		
	—(SiO_3)	$Al_2(—)_3$			$Ba(—)$		$Cd(—)$	$Ca(—)$		Co_2SiO_4	$Cu(—)$			H_2SiO_3		
23	Sulfate	W	W	A	a	d	W	w	W(I)*	W	W			W	W	w
		$Al_2(SO_4)_3$	$(NH_4)_2SO_4$	$Sb_2(SO_4)_3$	$BaSO_4$	$Bi_2(SO_4)_3$	$CdSO_4$	$CaSO_4$	$Cr_2(SO_4)_3$	$CoSO_4$	$CuSO_4$			H_2SO_4	$FeSO_4$	$Fe(SO_4)_3$
24	Sulfide	d	W	A	d	A	A	w	d	A	A	I	I	W	A	d
		Al_2S_3	$(NH_4)_2S$	Sb_2S_3	BaS	Bi_2S_3	CdS	CaS	Cr_2S_3	CoS	CuS	Au_2S	Au_2S_3	H_2S	FeS	Fe_2S_3
25	Tartrate	w	W	W	w	A	A	w	d	A	A	I	I	W	A	d
	—$(C_4H_4O_6)$	$Al_2(—)_3$	$(NH_4)_2(—)$	$Sb_2(—)_3$	$Ba(—)$	$Bi_2(—)_3$	$Cd(—)$	$Ca(—)$		$Co(—)$	$Cu(—)$			$C_4H_6O_6$	$Fe(—)$	$Fe_2(—)_3$
26	Thiocy'te		W		W			W		W	d			W	W	W
			NH_4CNS		$Ba(CNS)_2$			$Ca(CNS)$		$Co(CNS)_2$	CuCNS			CNSH	$Fe(CNS)_2$	$Fe(CNS)_3$

No.		Pb	Mg	Mn	Hg (I)	Hg (II)	Ni	K	Pt	Ag	Na	Sn (IV)	Sn (II)	Sr	Zn
1	Acetate	W	W	W	w	W	W	W		w	W	W	d	W	W
	—($C_2H_3O_2$)	Pb(—)$_2$	Mg(—)$_2$	Mn(—)$_2$	Hg(—)	Hg(—)$_2$	Ni(—)$_2$	K(—)		Ag(—)	Na(—)	Sn(—)$_4$	Sn(—)$_2$	Sr(—)$_2$	Zn(—)$_2$
2	Arsenate	A	A	w	A	w	A	W		A	W			w	A
	—(AsO_4)	PbH(—)	Mg$_3$(—)	MnH(—)	Hg$_3$(—)	Hg$_3$(—)$_2$	Ni$_3$(—)$_2$	K$_3$(—)		Ag$_3$(—)	Na$_3$(—)			SrH(—)	Zn$_3$(—)$_2$
3	Arsenite		W	A	A	A	A	W		A	W		A	w	
	—(AsO_3)		Mg$_3$(—)$_2$	Mn$_3$H$_6$(—)$_4$	Hg$_3$(—)	Hg$_3$(—)	Ni$_3$H$_6$(—)$_4$	K$_3$AsO$_3$		Ag$_3$(—)	Na$_2$H(—)		Sn$_3$(—)$_2$	Sr$_3$(—)$_2$	
4	Benzoate	w	W	W	A	w	w	W		w	W				W
	—($C_7H_5O_2$)	Pb(—)$_2$	Mg(—)$_2$	Mn(—)$_2$	Hg$_2$(—)$_2$	Hg(—)$_2$	Ni(—)$_2$	K(—)		Ag(—)	Na(—)				Zn(—)$_2$
5	Bromide	W	W	W	A	W	W	W	w	a	W	W	W	W	W
		PbBr$_2$	MgBr$_2$	MnBr$_2$	HgBr	HgBr$_2$	NiBr$_2$	KBr	PtBr$_4$	AgBr	NaBr	SnBr$_4$	SnBr$_2$	SrBr$_2$	ZnBr$_2$
6	Carbonate	A	w	w	A		w	W		A	W			w	w
		PbCO$_3$	MgCO$_3$	MnCO$_3$	Hg$_2$CO$_3$		NiCO$_3$	K$_2$CO$_3$		Ag$_2$CO$_3$	Na$_2$CO$_3$			SrCO$_3$	ZnCO$_3$
7	Chlorate	W	W	W	W	W	W	W		W	W		W	W	W
	—(ClO_3)	Pb(—)$_2$	Mg(—)$_2$	Mn(—)$_2$	Hg(—)	Hg(—)$_2$	Ni(—)$_2$	K(—)		Ag(—)	Na(—)		Sn(—)$_2$	Sr(—)$_2$	Zn(—)$_2$
8	Chloride	W	W	W	a	W	W	W	W	a	W	W	W	W	W
		PbCl$_2$	MgCl$_2$	MnCl$_2$	HgCl	HgCl$_2$	NiCl$_2$	KCl	PtCl$_4$	AgCl	NaCl	SnCl$_4$	SnCl$_2$	SrCl$_2$	ZnCl$_2$
9	Chromate	A	W		w	w	A	W		w	W	W	A	w	w
	—(CrO_4)	Pb(—)	Mg(—)		Hg$_2$(—)	Hg(—)	Ni(—)	K$_2$(—)		Ag$_2$(—)	Ma$_2$(—)	Sn(—)$_2$	Sn(—)	Sr(—)	Zn(—)
10	Citrate	W	W	w	w		W	W		w	W			A	w
	—($C_6H_5O_7$)	Pb$_3$(—)$_2$	Mg$_3$(—)$_2$	MnH(—)	Hg$_3$(—)		Ni$_3$(—)$_2$	K$_3$(—)		Ag$_3$(—)	Na$_3$(—)			SrH(—)	Zn$_3$(—)$_2$
11	Cyanide	w	W		A	W	a	W	I	a	W			W	A
		Pb(CN)$_2$	Mg(CN)$_2$		HgCN	Hg(CN)$_2$	Ni(CN)$_2$	KCN	Pt(CN)$_2$	AgCN	NaCN			Sr(CN)$_2$	Zn(CN)$_2$
12	Ferricy'de	w	W			A	I	W		I	W		A	W	A
	—Fe(CN)$_6$	Pb$_3$(—)$_2$	Mg$_3$(—)$_2$			Hg$_3$(—)$_2$	Ni$_3$(—)$_2$	K$_3$(—)		Ag$_3$(—)	Na$_3$(—)		Sn$_3$(—)$_2$	Sr$_3$(—)$_2$	Zn$_3$(—)$_2$
13	Ferrocy'de	a	W	A		I	I	W		I	W		a	W	I
	—Fe(CN)$_6$	Pb$_2$(—)	Mg$_2$(—)	Mn$_2$(—)		Hg$_2$(—)	Ni$_2$(—)	K$_4$(—)		Ag$_4$(—)	Na$_4$(—)		Sn$_2$(—)	Sr$_2$(—)	Zn$_2$(—)
14	Fluoride	w	w	A	d	d	w	W	W	W	W	W	W	w	w
		PbF$_2$	MgF$_2$	MnF$_2$	HgF	HgF$_2$	NiF$_2$	KF	PtF$_4$	AgF	NaF	SnF$_4$	SnF$_2$	SrF$_2$	ZnF$_2$
15	Formate	W	W	W	w	W	W	W		W	W			W	W
	—(CHO_2)	Pb(—)$_2$	Mg(—)$_2$	Mn(—)$_2$	Hg(—)	Hg(—)$_2$	Ni(—)$_2$	K(—)		Ag(—)	Na(—)			Sr(—)$_2$	Zn(—)$_2$
16	Hydroxide	w	A	A		A	w	W	A		W	w	A	W	A
		Pb(OH)$_2$	Mg(OH)$_2$	Mn(OH)$_2$		Hg(OH)$_2$	Ni(OH)$_2$	KOH	Pt(OH)$_4$		NaOH	Sn(OH)$_4$	Sn(OH)$_2$	Sr(OH)$_2$	Zn(OH)$_2$
17	Iodide	w	W	W	A	w	W	W	I	I	W	d	W	W	W
		PbI$_2$	MgI$_2$	MnI$_2$	HgI	HgI$_2$	NiI$_2$	KI	PtI$_2$	AgI	NaI	SnI$_4$	SnI$_2$	SrI$_2$	ZnI$_2$
18	Nitrate	W	W	W	W	W	W	W	W	W	W		d	W	W
		Pb(NO$_3$)$_2$	Mg(NO$_3$)$_2$	Mn(NO$_3$)$_2$	HgNO$_3$	Hg(NO$_3$)$_2$	Ni(NO$_3$)$_2$	KNO$_3$	Pt(NO$_3$)$_4$	AgNO$_3$	NaNO$_3$		Sn(NO$_3$)$_2$	Sr(NO$_3$)$_2$	Zn(NO$_3$)$_2$
19	Oxalate	A	w	w	a	A	A	W		a	W		A	w	A
	—(C_2O_4)	Pb(—)	Mg(—)	Mn(—)	Hg$_2$(—)	Hg(—)	Ni(—)	K$_2$(—)		Ag$_2$(—)	Na$_2$(—)		Sn(—)	Sr(—)	Zn(—)
20	Oxide	w	A	A	A	w	A	W	A	w	d	A	A	W	w
		PbO	MgO	MnO	Hg$_2$O	HgO	NiO	K$_2$O	PtO	Ag$_2$O	Na$_2$O	SnO$_2$	SnO	SrO	ZnO
21	Phosphate	A	w	w	A	A	A	W		A	W		A	A	A
		Pb$_3$(PO$_4$)$_2$	Mg$_3$(PO$_4$)$_2$	Mn$_3$(PO$_4$)$_2$	Hg$_3$PO$_4$	Hg$_3$(PO$_4$)$_2$	Ni$_3$(PO$_4$)$_2$	K$_3$PO$_4$		Ag$_3$PO$_4$	Na$_3$PO$_4$		Sn$_3$(PO$_4$)	Sr$_3$(PO$_4$)$_2$	Zn$_3$(PO$_4$)$_2$
22	Silicate	A	A	I				W			W			A	A
	—(SiO_3)	Pb(—)	Mg(—)	Mn(—)				K$_2$(—)			Na$_2$(—)			Sr(—)	Zn(—)
23	Sulfate	w	W	W	w	d	W	W	W	w	W	W	W	w	W
		PbSO$_4$	MgSO$_4$	MnSO$_4$	Hg$_2$SO$_4$	HgSO$_4$	NiSO$_4$	K$_2$SO$_4$	Pt(SO$_4$)$_2$	Ag$_2$SO$_4$	Na$_2$SO$_4$	Sn(SO$_4$)$_2$	SnSO$_4$	SrSO$_4$	ZnSO$_4$
24	Sulfide	A	d	A	I	I	A	W	I	A	W	A	A	W	A
		PbS	MgS	MnS	Hg$_2$S	HgS	NiS	K$_2$S	PtS	Ag$_2$S	Na$_2$S	SnS$_2$	SnS	SrS	ZnS
25	Tartrate	A	w	w	I	I	A	W	I	A	W	A	A	W	A
	—($C_4H_4O_6$)	Pb(—)	Mg(—)	Mn(—)	Hg$_2$(—)		Ni(—)	K$_2$(—)		Ag$_2$(—)	Na$_2$(—)		Sn(—)	Sr(—)	Zn(—)
26	Thiocy'te	w	W	W	A	w		W		I	W			W	W
		Pb(CNS)$_2$	Mg(CNS)$_2$	Mn(CNS)$_2$	HgCNS	Hg(CNS)$_2$		KCNS		AgCNS	NaCNS			Sr(CNS)$_2$	Zn(CNS)$_2$

REDUCTION OF WEIGHINGS IN AIR TO VACUO

When the mass M of a body is determined in air, a correction is necessary for the buoyancy of the air. The corrected mass is given by $M + kM/1000$, where k is a function of the material used for the weights, given by

$$k = 1000\rho_{air}(1/\rho_{body} - 1/\rho_{weight})$$

and ρ is density. The table below is computed for an air density of 0.0012 g/cm^3 and for densities of three common weights: platinum-iridium (21.6 g/cm^3), brass (8.5 g/cm^3), and aluminum or quartz (2.65 g/cm^3).

References

1. Kaye, G. W. C., and Laby, T. H., *Tables of Physical and Chemical Constants, 16th Edition,* pp. 25-28, Longman, London, 1995.
2. Giacomo, P., *Metrologia,* 18, 33, 1982.
3. Davis, R. S., *Metrologia,* 29, 67, 1992.

Density of body (g/cm^3)	Value of k for weights of:		
	Pt-Ir	Brass	Quartz or Al
0.5	2.34	2.26	1.95
0.6	1.94	1.86	1.55
0.7	1.66	1.57	1.26
0.8	1.44	1.36	1.05
0.9	1.28	1.19	0.88
1.0	1.14	1.06	0.75
1.1	1.04	0.95	0.64
1.2	0.94	0.86	0.55
1.3	0.87	0.78	0.47
1.4	0.80	0.72	0.40
1.5	0.74	0.66	0.35
1.6	0.69	0.61	0.30
1.7	0.65	0.56	0.25

Density of body (g/cm^3)	Value of k for weights of:		
	Pt-Ir	Brass	Quartz or Al
1.8	0.61	0.53	0.21
1.9	0.58	0.49	0.18
2.0	0.54	0.46	0.15
2.5	0.42	0.34	0.03
3.0	0.34	0.26	-0.05
4.0	0.24	0.16	-0.15
6.0	0.14	0.06	-0.25
8.0	0.09	0.01	-0.30
10.0	0.06	-0.02	-0.33
15.0	0.02	-0.06	-0.37
20.0	0.00	-0.08	-0.39
22.0	0.00	-0.09	-0.40

For a more accurate calculation, use the following values of the density of air (assuming 50% relative humidity and 0.04% CO_2):

	Air temperature		
P/kPa	10°C	20°C	30°C
85	0.001043	0.001005	0.000968
90	0.001105	0.001065	0.001025
95	0.001166	0.001124	0.001083
100	0.001228	0.001184	0.001140
105	0.001290	0.001243	0.001198

Formulas for calculating the density of air over more extended ranges of temperature, pressure, and humidity may be found in the references.

VOLUME OF ONE GRAM OF WATER

The following table, which is designed for gravimetric calibration of volumetric apparatus, gives the specific volume of water at standard atmospheric pressure as a function of temperature.

Reference

Marsh, K. N., Ed., *Recommended Reference Materials for the Realization of Physicochemical Properties*, pp. 25-27, Blackwell Scientific Publications, Oxford, 1987.

t/°C	Volume of 1 g H_2O in cm^3
10	1.0002980
11	1.0003928
12	1.0005007
13	1.0006212
14	1.0007542
15	1.0008992
16	1.0010561
17	1.0012246
18	1.0014044
19	1.0015952
20	1.0017969
21	1.0020092
22	1.0022320
23	1.0024649
24	1.0027079
25	1.0029607
26	1.0032234
27	1.0034956
28	1.0037771
29	1.0040679
30	1.0043679

PROPERTIES OF CARRIER GASES FOR GAS CHROMATOGRAPHY

The following is a list of carrier gases sometimes used in gas chromatography, with properties relevant to the design of chromatographic systems. All data refer to normal atmospheric pressure (101.325 kPa).

M_r: Molecular weight (relative molar mass)
ρ_{25}: Density at 25°C in g/L
λ: Thermal conductivity in mW/m °C
η: Viscosity in μPa s (equal to 10^{-3} cp)
c_p: Specific heat at 25°C in J/g °C

References

1. Lide, D. R., and Kehiaian, H. V., *CRC Handbook of Thermophysical and Thermochemical Data*, CRC Press, Boca Raton, FL, 1994.
2. Bruno, T. J., and Svoronos, P. D. N., *CRC Handbook of Basic Tables for Chemical Analysis*, CRC Press, Boca Raton, FL, 1989.

			At 25°C		At 250°C		
Gas	M_r	ρ_{25} **g L^{-1}**	λ **mW/m °C**	η **μPa s**	λ **mW/m °C**	η **μPa s**	c_p**(25 °C) J/g °C**
Hydrogen	2.016	0.0824	185.9	8.9	280	13.1	14.3
Helium	4.003	0.1636	154.6	19.9	230	29.5	5.20
Argon	39.95	1.6329	17.8	22.7	27.7	35.3	0.521
Nitrogen	28.01	1.1449	25.9	17.9	39.6	26.8	1.039
Oxygen	32.00	1.3080	26.2	20.7	42.6	31.8	0.919
Carbon monoxide	28.01	1.1449	24.8	17.8	40.7	26.5	1.039
Carbon dioxide	44.01	1.7989	16.7	14.9	35.5	24.9	0.843
Sulfur hexafluoride	146.05	5.9696	13.1	28.1	15.3	24.8	0.664
Methane	16.04	0.6556	34.5	11.1	75.0	17.6	2.23
Ethane	30.07	1.2291	20.9	9.4	57.7	15.5	1.75
Ethylene	28.05	1.1465	20.5	10.3	53.8	17.2	1.53
Propane	44.10	1.8025	17.9	8.3	49.2	14.0	1.67

SOLVENTS FOR ULTRAVIOLET SPECTROPHOTOMETRY

This table lists some solvents commonly used for sample preparation for ultraviolet spectrophotometry. The properties given are:

- λ_c: cutoff wavelength, below which the solvent absorption becomes excessive.
- ε: dielectric constant (relative permittivity); the temperature in °C is given as a superscript.
- t_b: normal boiling point.

References

1. Bruno, T. J., and Svoronos, P. D. N., *CRC Handbook of Basic Tables for Chemical Analysis*, CRC Press, Boca Raton, FL, 1989.
2. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series,* IV/6*, Static Dielectric Constants of Pure Liquids and Binary Liquid Mixtures,* Springer–Verlag, Heidelberg, 1991.

Name	λ_c/nm	ε	t_b/°C
Acetic acid	260	6.20^{20}	117.9
Acetone	330	21.01^{20}	56.0
Acetonitrile	190	36.64^{20}	81.6
Benzene	280	2.28^{20}	80.0
2-Butanol	260	17.26^{20}	99.5
Butyl acetate	254	5.07^{20}	126.1
Carbon disulfide	380	2.63^{20}	46
Carbon tetrachloride	265	2.24^{20}	76.8
1-Chlorobutane	220	7.28^{20}	78.6
Chloroform	245	4.81^{20}	61.1
Cyclohexane	210	2.02^{20}	80.7
1,2-Dichloroethane	226	10.42^{20}	83.5
Dichloromethane	235	8.93^{25}	40
Diethyl ether	218	4.27^{20}	34.5
N,N-Dimethylacetamide	268	38.85^{21}	165
N,N-Dimethylformamide	270	38.25^{20}	153
Dimethyl sulfoxide	265	47.24^{20}	189
1,4-Dioxane	215	2.22^{20}	101.5
Ethanol	210	25.3^{20}	78.2
Ethyl acetate	255	6.08^{20}	77.1
Ethylene glycol dimethyl ether	240	7.30^{24}	85
Ethylene glycol monoethyl ether	210	13.38^{25}	135
Ethylene glycol monomethyl ether	210	17.2^{25}	124.1
Glycerol	207	46.53^{20}	290
Heptane	197	1.92^{20}	98.5
Hexadecane	200	2.05^{20}	286.8
Hexane	210	1.89^{20}	68.7
Methanol	210	33.0^{20}	64.6
Methylcyclohexane	210	2.02^{20}	100.9
Methyl ethyl ketone	330	18.56^{20}	79.5
Methyl isobutyl ketone	335	13.11^{20}	116.5
2-Methyl-1-propanol	230	17.93^{20}	107.8
N-Methyl-2-pyrrolidone	285	32.55^{20}	202
Nitromethane	380	37.27^{20}	101.1
Pentane	210	1.84^{20}	36.0
Pentyl acetate	212	4.79^{20}	149.2
1-Propanol	210	20.8^{20}	97.2
2-Propanol	210	20.18^{20}	82.3
Pyridine	330	13.26^{20}	115.2
Tetrachloroethylene	290	2.27^{30}	121.3
Tetrahydrofuran	220	7.52^{22}	65
Toluene	286	2.38^{23}	110.6
1,1,2-Trichloro-1,2,2-trifluoroethane	231	2.41^{25}	47.7
2,2,4-Trimethylpentane	215	1.94^{20}	99.2
Water	191	80.10^{20}	100.0
o-Xylene	290	2.56^{20}	144.5
m-Xylene	290	2.36^{20}	139.1
p-Xylene	290	2.27^{20}	138.3

^{13}C CHEMICAL SHIFTS OF USEFUL NMR SOLVENTS

The following table gives the expected carbon-13 chemical shifts, relative to tetramethylsilane, for various useful NMR solvents. In some solvents, slight changes can occur with change of concentration.[2,3]

References

1. Bruno, T. J., and Svoronos, P. D. N., *CRC Handbook of Basic Tables for Chemical Analysis*, CRC Press, Boca Raton, FL, 1989.
2. Silverstein, R. M., Bassler, G. C., and Morrill, T. C., *Spectrometric Identification of Organic Compounds,* John Wiley & Sons, Now York, 1981.
3. Rahman, A. U., *Nuclear Magnetic Resonance. Basic Principles,* Springer-Verlag, New York, 1986.
4. Pretsch, E., Clerc, T., Seibl, J., and Simon, W., *Spectral Data for Structure Determination of Organic Compounds, Second Edition*, Springer-Verlag, Heidelberg, 1989.

Solvent	Formula	Chemical shift (ppm)
Acetic acid-d_4	CD_3COOD	20.0 (CD_3) 205.8 (C=O)
Acetone	$(CH_3)_2C=O$	30.7 (CH_3) 206.7 (C=O)
Acetone-d_6	$(CD_3)_2C=O$	29.2 (CD_3) 204.1 (C=O)
Acetonitrile-d_3	$CD_3C\equiv N$	1.3 (CD_3) 117.1 (C≡N)
Benzene	C_6H_6	128.5
Benzene-d_6	C_6D_6	128.4
Carbon disulfide	CS_2	192.3
Carbon tetrachloride	CCl_4	96.0
Chloroform	$CHCl_3$	77.2
Chloroform-d_3	$CDC1_3$	77.05
Cyclohexane-d_{12}	C_6D_{12}	27.5
Dichloromethane-d_2	CD_2C1_2	53.6
Dimethylformamide-d_7	$(CD_3)_2NCDO$	31 (CD_3) 36 (CD_3) 162.4 (C=O)
Dimethylsulfoxide-d_6	$(CD_3)_2S=O$	39.6
Dioxane-d_8	$C_4D_3O_2$	67.4
Formic acid-d_2	DCOOD	165.5
Methanol-d_4	CD_3OD	49.3
Nitromethane-d_3	CD_3NO_2	57.3
Pyridine	C_5H_5N	123.6 (C_3) 135.7 (C_4) 149.8 (C_2)
Pyridine-d_5	C_5D_5N	123.9 (C_3) 135.9 (C_4) 150.2 (C_2)
1,1,2,2-Tetrachloroethane-d_2	$CDC1_2CDC1_2$	75.5
Tetrahydrofuran-d_8	C_4D_8O	25.8 (C_2) 67.9 (C_1)
Trichlorofluoromethane	$CFC1_3$	117.6

MASS SPECTRAL PEAKS OF COMMON ORGANIC SOLVENTS

The strongest peaks in the mass spectra of 200 important solvents are listed in this table. The *e/m* value for each peak is followed by the relative intensity in parentheses, with the strongest peak assigned an intensity of 100. The peaks for each compound are listed in order of decreasing intensity. Solvents are listed in alphabetical order by common name.

Data on the physical properties of the same compounds may be found in Section 15 in the table "Properties of Common Laboratory Solvents".

References

1. NIST/EPA/NIH Mass Spectral Database, National Institute of Standards and Technology, Gaithersburg, MD, 20899.
2. Lide, D. R., and Milne, G. W. A., Eds., *Handbook of Data on Organic Compounds, Third Edition*, CRC Press, Boca Raton, FL, 1994. (Also available as a CD ROM database.)

Compound	*e/m* (intensity)									
Acetal (1,1-Diethoxyethane)	44(100)	43(92)	29(77)	31(76)	45(74)	27(52)	72(48)	73(23)	28(17)	46(15)
Acetic acid	43(100)	45(87)	60(57)	15(42)	42(14)	29(13)	14(13)	28(7)	18(6)	16(6)
Acetone	43(100)	15(34)	58(23)	27(9)	14(9)	42(8)	26(7)	29(5)	28(5)	39(4)
Acetonitrile	41(100)	40(46)	39(13)	14(9)	38(6)	28(4)	26(4)	25(3)	42(2)	27(2)
Acetylacetone	43(100)	85(31)	100(20)	27(12)	42(10)	29(10)	41(7)	39(7)	31(5)	26(5)
Acrylonitrile	53(100)	26(85)	52(79)	51(34)	27(13)	50(8)	25(7)	38(5)	54(3)	37(3)
Adiponitrile	41(100)	68(50)	54(42)	40(21)	55(20)	27(17)	39(16)	28(13)	52(7)	42(6)
Allyl alcohol	57(100)	31(34)	29(32)	28(31)	58(25)	39(22)	27(20)	30(16)	32(14)	26(11)
Allylamine	30(100)	56(80)	28(76)	57(33)	39(21)	29(20)	27(18)	26(13)	41(8)	18(8)
2-Aminoisobutanol	58(100)	41(18)	18(17)	42(13)	28(11)	56(10)	30(10)	29(8)	43(6)	59(5)
Benzal chloride	125(100)	127(32)	160(14)	89(13)	162(9)	63(9)	126(8)	62(7)	105(5)	39(5)
Benzaldehyde	51(100)	77(81)	50(55)	106(44)	105(43)	52(26)	78(16)	39(13)	27(10)	74(8)
Benzene	78(100)	77(20)	52(19)	51(17)	50(15)	39(12)	79(6)	76(5)	74(4)	38(4)
Benzonitrile	103(100)	76(34)	50(13)	104(9)	75(7)	51(7)	77(5)	52(4)	39(4)	74(3)
Benzyl chloride	91(100)	126(20)	65(14)	92(9)	39(9)	63(8)	128(6)	45(6)	89(5)	125(3)
Bromochloromethane	49(100)	130(67)	128(52)	51(31)	93(23)	81(20)	79(20)	95(17)	132(16)	47(8)
Bromoform (Tribromomethane)	173(100)	171(50)	175(49)	93(22)	91(22)	79(18)	81(17)	94(13)	92(13)	254(11)
Butyl acetate	43(100)	56(34)	41(17)	27(16)	29(15)	73(11)	61(10)	28(7)	55(6)	39(6)
Butyl alcohol	31(100)	56(81)	41(62)	43(60)	27(50)	42(31)	29(31)	28(17)	39(16)	55(12)
sec-Butyl alcohol	45(100)	31(22)	27(22)	59(20)	29(18)	43(13)	41(12)	44(8)	18(8)	28(5)
tert-Butyl alcohol	59(100)	31(33)	41(22)	43(18)	29(13)	27(11)	57(10)	42(4)	60(3)	28(3)
Butylamine	30(100)	73(10)	28(5)	41(3)	27(3)	18(3)	44(2)	42(2)	31(2)	29(2)
tert-Butylamine	58(100)	41(21)	42(15)	18(9)	30(8)	15(8)	39(7)	57(6)	28(6)	59(4)
Butyl methyl ketone	43(100)	58(60)	57(17)	100(16)	29(15)	41(13)	85(8)	27(8)	71(7)	59(5)
p-*tert*-Butyltoluene	133(100)	105(38)	41(23)	148(18)	93(16)	91(14)	115(13)	134(11)	39(11)	116(10)
γ-Butyrolactone	28(100)	42(74)	29(48)	27(33)	41(27)	56(25)	86(24)	26(18)	85(10)	39(10)
Caprolactam	55(100)	113(87)	30(81)	56(66)	84(60)	85(57)	42(51)	41(33)	28(26)	43(17)
Carbon disulfide	76(100)	32(22)	44(17)	78(9)	38(6)	28(5)	77(3)	64(1)	46(1)	39(1)
Carbon tetrachloride	117(100)	119(98)	121(31)	82(24)	47(23)	84(16)	35(14)	49(8)	28(8)	36(6)
1-Chloro-1,1-difluoroethane	65(100)	45(31)	85(14)	31(10)	64(8)	44(7)	35(6)	26(6)	87(5)	81(4)
Chlorobenzene	112(100)	77(63)	114(33)	51(29)	50(14)	75(8)	113(7)	78(5)	76(5)	28(4)
Chloroform	83(100)	85(64)	47(35)	35(19)	48(16)	49(12)	87(10)	37(6)	50(5)	84(4)
Chloropentafluoroethane	85(100)	69(61)	31(38)	87(32)	50(17)	35(8)	119(6)	66(4)	100(3)	47(3)
Cumene (Isopropylbenzene)	105(100)	120(25)	77(13)	51(12)	79(10)	106(9)	39(9)	27(8)	103(6)	91(5)
Cyclohexane	56(100)	84(71)	41(70)	27(37)	55(36)	39(35)	42(30)	69(23)	28(18)	43(14)
Cyclohexanol	57(100)	44(68)	41(68)	39(51)	32(40)	43(38)	31(32)	42(22)	67(18)	82(16)
Cyclohexanone	55(100)	42(85)	41(34)	27(33)	98(31)	39(27)	69(26)	70(20)	43(14)	28(14)
Cyclohexylamine	56(100)	43(23)	28(17)	99(10)	70(8)	57(6)	30(6)	93(5)	54(4)	41(4)
Cyclopentane	42(100)	70(30)	55(29)	41(29)	39(22)	27(15)	40(7)	29(5)	28(4)	43(3)
Cyclopentanone	55(100)	28(50)	84(42)	41(38)	56(29)	27(24)	39(19)	42(15)	26(9)	29(7)
p-Cymene (1-Methyl-4-isopropyl-benzene)	119(100)	91(42)	134(33)	39(27)	41(20)	117(18)	65(18)	77(17)	27(16)	120(15)
cis-Decalin	67(100)	81(87)	41(81)	138(67)	96(62)	82(62)	39(50)	55(45)	27(44)	95(42)
trans-Decalin	41(100)	68(91)	67(88)	82(67)	27(65)	96(61)	95(55)	138(51)	81(51)	29(51)
Diacetone alcohol	43(100)	59(41)	58(17)	101(10)	41(9)	31(9)	83(6)	56(6)	55(6)	29(6)
1,2-Dibromoethane	27(100)	107(77)	109(72)	26(24)	28(10)	81(5)	79(5)	25(5)	95(4)	93(4)
Dibromofluoromethane	111(100)	113(98)	192(29)	43(16)	41(16)	190(15)	194(14)	81(9)	79(9)	122(7)
Dibromomethane	174(100)	93(96)	95(84)	172(53)	176(50)	91(11)	81(9)	79(9)	94(5)	65(5)
1,2-Dibromotetrafluoroethane	179(100)	181(97)	129(34)	131(33)	100(17)	31(13)	260(12)	50(8)	69(7)	262(6)
Dibutylamine	86(100)	72(52)	30(48)	44(40)	29(31)	57(24)	41(21)	73(15)	28(15)	43(13)

Compound	*e/m* (intensity)									
o-Dichlorobenzene	146(100)	148(64)	111(38)	75(23)	113(12)	74(12)	50(11)	150(10)	73(9)	147(7)
1,1-Dichloroethane (Ethylidene dichloride)	63(100)	27(71)	65(31)	26(19)	83(11)	85(7)	61(7)	35(6)	98(5)	62(5)
1,2-Dichloroethane (Ethylene dichloride)	62(100)	27(91)	49(40)	64(32)	26(31)	63(19)	98(14)	51(13)	61(12)	100(9)
1,1-Dichloroethylene	61(100)	96(61)	98(38)	63(32)	26(16)	60(15)	62(7)	25(7)	100(6)	35(6)
cis-1,2-Dichloroethylene	61(100)	96(73)	98(47)	63(32)	26(30)	60(21)	25(13)	35(12)	62(9)	100(8)
trans-1,2-Dichloroethylene	61(100)	96(67)	98(43)	26(34)	63(32)	60(24)	25(15)	62(10)	100(7)	47(7)
Dichloroethyl ether	93(100)	63(74)	27(38)	95(32)	65(24)	31(9)	49(4)	28(4)	94(3)	62(3)
Dichloromethane (Methylene chloride)	49(100)	84(64)	86(39)	51(31)	47(14)	48(8)	88(6)	50(3)	85(2)	83(2)
1,2-Dichloropropane	63(100)	62(71)	27(57)	41(49)	39(32)	65(31)	76(27)	64(25)	49(13)	77(12)
1,2-Dichlorotetrafluoroethane	85(100)	135(52)	87(33)	137(17)	101(9)	31(9)	103(6)	100(6)	50(5)	69(4)
Diethanolamine	30(100)	74(82)	28(77)	56(69)	18(50)	42(46)	29(36)	27(34)	45(30)	43(19)
Diethylamine	30(100)	58(81)	44(28)	73(18)	29(18)	28(17)	72(12)	42(11)	27(11)	59(4)
Diethyl carbonate	29(100)	45(70)	31(53)	27(39)	91(24)	28(15)	63(11)	26(10)	30(6)	43(5)
Diethylene glycol	45(100)	75(23)	31(20)	44(16)	27(14)	76(12)	29(12)	43(11)	42(9)	41(4)
Diethylene glycol dimethyl ether (Diglyme)	59(100)	58(43)	31(34)	29(32)	45(28)	28(19)	89(15)	43(9)	27(5)	60(4)
Diethylene glycol monoethyl ether (Carbitol)	45(100)	59(56)	72(37)	73(22)	60(14)	31(13)	75(11)	44(9)	104(8)	103(7)
Diethylene glycol monoethyl ether acetate	43(100)	29(51)	31(42)	45(40)	59(24)	72(18)	44(10)	73(9)	42(9)	30(6)
Diethylene glycol monomethyl ether	45(100)	31(42)	59(41)	29(38)	28(32)	58(21)	43(14)	27(13)	44(11)	32(10)
Diethylenetriamine	44(100)	73(59)	30(35)	19(18)	56(16)	28(16)	27(16)	42(11)	99(8)	43(8)
Diethyl ether	31(100)	29(63)	59(40)	27(35)	45(33)	74(23)	15(17)	43(9)	28(9)	26(9)
Diisobutyl ketone (Isovalerone)	57(100)	85(82)	41(46)	43(39)	58(33)	28(30)	26(30)	39(22)	42(12)	142(11)
Diisopropyl ether	45(100)	43(39)	87(15)	41(12)	59(10)	27(8)	39(4)	69(3)	42(3)	31(3)
N,N-Dimethylacetamide	44(100)	87(69)	43(46)	45(23)	42(19)	72(15)	15(11)	30(8)	28(5)	88(4)
Dimethylamine	44(100)	45(81)	18(32)	28(30)	43(19)	42(15)	15(9)	46(5)	41(5)	27(5)
Dimethyl disulfide	94(100)	45(63)	79(59)	46(38)	47(26)	15(18)	48(14)	61(12)	64(11)	96(9)
N,N-Dimethylformamide	73(100)	44(86)	42(36)	30(22)	28(20)	29(8)	43(7)	72(6)	58(5)	74(4)
Dimethyl sulfoxide	63(100)	78(70)	15(40)	45(35)	29(16)	61(13)	46(12)	31(11)	48(10)	47(10)
1,4-Dioxane	28(100)	29(37)	88(31)	58(24)	31(17)	15(17)	27(15)	30(13)	43(11)	26(9)
1,3-Dioxolane	73(100)	29(56)	44(53)	45(28)	28(21)	43(20)	27(13)	31(7)	74(5)	42(3)
Dipentene	68(100)	93(50)	67(44)	94(22)	39(22)	107(18)	92(18)	53(18)	136(16)	79(16)
Epichlorohydrin	57(100)	27(39)	29(32)	49(25)	31(22)	62(18)	28(16)	92(1)		
Ethanolamine (Glycinol)	30(100)	18(30)	28(15)	42(7)	31(6)	17(6)	61(5)	15(5)	43(3)	29(3)
Ethyl acetate	43(100)	29(46)	27(33)	45(32)	61(28)	28(25)	42(18)	73(11)	88(10)	70(10)
Ethyl acetoacetate	43(100)	29(24)	88(18)	28(16)	85(14)	27(12)	42(11)	60(9)	130(6)	45(6)
Ethyl alcohol	31(100)	45(44)	46(18)	27(18)	29(15)	43(14)	30(6)	42(3)	19(3)	14(3)
Ethylamine	30(100)	28(32)	44(20)	45(19)	27(13)	15(10)	42(9)	29(8)	41(5)	40(5)
Ethylbenzene	91(100)	106(31)	51(14)	39(10)	77(8)	65(8)	105(7)	92(7)	78(7)	27(6)
Ethyl bromide (Bromoethane)	108(100)	110(97)	29(62)	27(51)	28(35)	26(14)	93(6)	32(6)	95(5)	81(5)
Ethyl chloride (Cloroethane)	64(100)	28(91)	29(84)	27(75)	66(32)	26(28)	49(25)	51(8)	63(6)	65(4)
Ethylene carbonate	29(100)	44(62)	43(54)	88(40)	30(16)	28(11)	45(7)	58(6)	42(6)	73(4)
Ethylenediamine (1,2-Ethane-diamine)	30(100)	18(13)	42(6)	43(5)	27(5)	44(4)	29(4)	17(4)	15(4)	41(3)
Ethylene glycol	31(100)	33(35)	29(13)	32(11)	43(6)	27(5)	28(4)	62(3)	30(3)	44(2)
Ethylene glycol diethyl ether	31(100)	59(71)	29(58)	45(43)	27(33)	74(27)	43(15)	15(14)	28(12)	44(10)
Ethylene glycol dimethyl ether	45(100)	60(13)	29(13)	90(7)	58(6)	31(5)	28(5)	43(4)	59(3)	46(2)
Ethylene glycol monobutyl ether	57(100)	45(38)	29(35)	41(31)	87(16)	27(12)	56(11)	31(9)	75(7)	28(7)
Ethylene glycol monoethyl ether (Cellosolve)	31(100)	29(52)	59(50)	27(27)	45(26)	72(14)	43(14)	15(14)	28(8)	26(6)
Ethylene glycol monoethyl ether acetate	43(100)	31(34)	59(31)	72(28)	44(25)	29(24)	45(12)	27(11)	15(11)	87(7)
Ethylene glycol monomethyl ether	45(100)	31(15)	29(14)	28(11)	47(9)	76(6)	43(6)	58(4)	46(4)	27(4)
Ethylene glycol monomethyl ether acetate	43(100)	45(48)	58(42)	29(10)	42(4)	31(4)	73(3)	27(3)	59(2)	26(2)
Ethyl formate	31(100)	28(73)	27(51)	29(38)	45(34)	26(17)	74(11)	43(9)	47(8)	56(4)
Furan	68(100)	39(64)	40(9)	38(9)	42(6)	29(6)	37(5)	69(4)	34(2)	67(1)
Furfural	39(100)	96(55)	95(52)	38(38)	29(35)	37(29)	40(11)	97(9)	50(7)	42(7)
Furfuryl alcohol	98(100)	41(65)	39(59)	81(55)	53(53)	97(51)	42(49)	69(39)	70(36)	29(28)
Glycerol	61(100)	43(90)	31(57)	44(54)	29(38)	18(32)	27(12)	42(11)	60(10)	45(10)
Heptane	43(100)	41(56)	29(49)	57(47)	27(46)	71(45)	56(27)	42(26)	39(23)	70(18)
1-Heptanol	41(100)	70(87)	56(86)	31(78)	43(72)	29(70)	55(67)	27(65)	42(54)	69(41)
Hexane	57(100)	43(78)	41(77)	29(61)	27(57)	56(45)	42(39)	39(27)	28(16)	86(14)
1-Hexanol (Caproyl alcohol)	56(100)	43(78)	31(74)	41(71)	27(64)	29(59)	55(58)	42(53)	39(37)	69(27)
Hexylene glycol	59(100)	43(61)	56(25)	45(17)	41(16)	57(13)	42(13)	85(11)	61(10)	31(10)

Compound	*e/m* (intensity)									
Hexyl methyl ketone	43(100)	58(79)	41(56)	59(52)	71(49)	27(46)	29(36)	39(27)	57(18)	55(17)
Isobutyl acetate	43(100)	56(26)	73(15)	41(10)	29(5)	71(3)	57(3)	39(3)	27(3)	86(2)
Isobutyl alcohol	43(100)	33(73)	31(72)	41(66)	42(60)	27(43)	29(18)	39(17)	28(8)	74(6)
Isobutylamine	30(100)	28(9)	41(6)	73(5)	27(5)	39(4)	29(3)	15(3)	58(2)	56(2)
Isopentyl acetate	43(100)	70(49)	55(38)	61(15)	42(15)	41(14)	27(12)	87(11)	29(10)	73(9)
Isophorone	82(100)	39(20)	138(17)	54(13)	27(12)	41(10)	53(8)	83(7)	29(7)	55(6)
Isopropyl acetate	43(100)	61(17)	41(14)	87(9)	59(8)	27(8)	42(7)	39(4)	45(3)	44(2)
Isopropyl alcohol	45(100)	43(19)	27(17)	29(12)	41(7)	31(6)	19(6)	42(5)	44(4)	59(3)
Isoquinoline	129(100)	102(26)	51(20)	128(18)	50(11)	130(10)	75(10)	76(9)	103(8)	74(7)
d-Limonene (Citrene)	68(100)	93(50)	67(49)	41(22)	94(21)	79(21)	39(21)	136(20)	53(19)	121(16)
2,6-Lutidine (2,6-Dimethyl-pyridine)	107(100)	39(39)	106(29)	66(22)	92(18)	65(18)	38(12)	27(11)	79(9)	63(9)
Mesitylene (1,3,5-Trimethyl-benzene)	105(100)	120(64)	119(15)	77(13)	39(11)	106(9)	91(9)	51(8)	27(7)	121(6)
Mesityl oxide	55(100)	83(89)	43(73)	29(42)	98(36)	39(32)	27(28)	53(11)	41(10)	56(5)
Methyl acetate	43(100)	74(52)	28(38)	42(19)	59(17)	44(8)	32(8)	29(6)	31(4)	75(2)
Methylal (Dimethoxymethane)	45(100)	75(61)	29(59)	31(13)	30(6)	15(6)	47(5)	76(2)	46(2)	44(2)
Methyl alcohol	31(100)	29(72)	32(67)	15(42)	28(12)	14(10)	30(9)	13(6)	12(3)	16(2)
Methylamine	30(100)	31(87)	28(56)	29(19)	32(15)	15(12)	27(9)			
Methyl benzoate	105(100)	77(81)	51(45)	136(24)	50(18)	106(8)	78(6)	28(6)	39(5)	27(5)
Methylcyclohexane	83(100)	55(82)	41(60)	98(44)	42(35)	56(30)	27(29)	39(27)	69(23)	70(22)
Methyl ethyl ketone	43(100)	72(24)	29(19)	27(12)	57(7)	42(5)	26(4)	28(3)	44(2)	39(2)
N-Methylformamide	59(100)	30(54)	28(34)	29(13)	58(8)	15(7)	60(3)	41(3)	27(3)	31(2)
Methyl formate	31(100)	29(63)	32(34)	60(28)	30(7)	28(7)	44(2)	18(2)	61(1)	59(1)
Methyl iodide (Iodomethane)	142(100)	127(38)	141(14)	15(13)	139(5)	140(4)	128(3)	14(1)	13(1)	71(0)
Methyl isobutyl ketone	43(100)	58(84)	29(65)	41(56)	57(44)	27(42)	39(31)	85(19)	100(14)	42(14)
Methyl isopentyl ketone	43(100)	58(34)	27(14)	41(13)	15(13)	57(11)	39(9)	71(8)	59(8)	29(8)
2-Methylpentane	43(100)	42(53)	41(35)	27(31)	71(29)	39(20)	29(18)	57(11)	15(10)	70(7)
4-Methyl-2-pentanol	45(100)	43(47)	69(30)	41(27)	27(19)	39(13)	29(12)	87(11)	84(10)	57(10)
Methyl pentyl ketone	43(100)	58(60)	71(14)	41(11)	27(11)	59(9)	39(8)	29(8)	42(5)	114(4)
Methyl propyl ketone	43(100)	41(17)	86(12)	42(12)	27(11)	39(8)	71(7)	58(7)	45(7)	44(3)
N-Methyl-2-pyrrolidone	99(100)	44(89)	98(80)	42(60)	41(38)	43(17)	28(17)	71(13)	39(11)	70(10)
Morpholine	57(100)	29(100)	87(69)	28(69)	30(38)	56(33)	86(28)	31(28)	27(12)	15(7)
Nitrobenzene	77(100)	51(59)	123(42)	50(25)	30(15)	65(14)	39(10)	93(9)	74(7)	78(6)
Nitroethane	29(100)	30(12)	28(11)	26(9)	27(8)	43(5)	41(5)	14(5)	15(3)	46(2)
Nitromethane	30(100)	61(64)	46(39)	28(30)	45(8)	27(8)	44(7)	29(7)	60(5)	43(4)
1-Nitropropane	43(100)	27(93)	41(90)	39(34)	30(25)	44(20)	42(20)	26(20)	28(13)	54(12)
2-Nitropropane	43(100)	41(73)	27(71)	39(30)	30(18)	15(11)	42(9)	28(8)	26(8)	38(6)
Octane	43(100)	57(30)	85(25)	41(25)	71(19)	29(17)	56(14)	70(10)	42(10)	27(10)
1-Octanol	41(100)	56(85)	43(82)	55(81)	31(69)	27(69)	29(68)	42(62)	70(53)	69(48)
Pentachloroethane	167(100)	165(91)	117(90)	119(89)	83(58)	169(54)	130(43)	132(42)	60(40)	85(37)
Pentamethylene glycol (1,5-Pentanediol)	31(100)	56(85)	41(67)	57(59)	55(51)	44(45)	29(37)	43(31)	68(29)	27(26)
Pentane	43(100)	42(55)	41(45)	27(42)	29(26)	39(19)	57(13)	28(9)	15(9)	72(8)
1-Pentanol (Amyl alcohol)	42(100)	70(72)	55(65)	41(56)	31(47)	29(41)	27(26)	57(22)	28(22)	43(21)
Pentyl acetate (Amyl acetate)	43(100)	70(90)	42(52)	28(51)	61(50)	55(41)	73(21)	41(20)	29(14)	69(11)
2-Picoline (2-Methylpyridine)	93(100)	66(41)	39(31)	92(20)	78(19)	51(19)	65(16)	38(13)	50(12)	52(11)
α-Pinene	93(100)	92(30)	39(24)	41(23)	77(22)	91(21)	27(21)	79(18)	121(13)	53(10)
β-Pinene	93(100)	41(64)	69(47)	39(33)	27(31)	79(20)	77(18)	53(14)	94(13)	91(13)
Piperidine (Hexahydropyridine)	84(100)	85(53)	56(46)	57(43)	28(41)	29(37)	44(34)	42(30)	30(30)	43(25)
Propanenitrile	28(100)	54(63)	26(20)	27(17)	52(11)	55(10)	51(9)	15(9)	53(7)	25(7)
Propyl acetate	43(100)	61(19)	31(18)	27(15)	42(11)	73(9)	41(9)	29(9)	59(5)	39(5)
Propyl alcohol	31(100)	27(19)	29(18)	59(11)	42(9)	60(7)	41(7)	28(7)	43(3)	32(3)
Propylamine	30(100)	28(13)	59(8)	27(7)	41(5)	42(3)	39(3)	29(3)	26(3)	18(3)
Propylbenzene	91(100)	120(21)	92(10)	38(10)	65(9)	78(6)	51(6)	27(5)	63(4)	105(3)
1,2-Propylene glycol	45(100)	18(46)	29(21)	43(19)	31(18)	27(17)	28(11)	19(8)	44(6)	61(5)
Pseudocumene (1,2,4-Trimethyl-benzene)	105(100)	120(56)	119(17)	77(15)	39(15)	51(11)	91(10)	27(10)	106(9)	79(7)
Pyridine	79(100)	52(62)	51(31)	50(19)	78(11)	53(7)	39(7)	80(6)	27(3)	77(2)
Pyrrole	67(100)	41(58)	39(58)	40(51)	28(42)	38(20)	37(12)	66(7)	68(5)	27(3)
Pyrrolidine	43(100)	28(52)	70(33)	71(26)	42(22)	41(20)	27(16)	39(15)	29(10)	30(9)
2-Pyrrolidone	85(100)	42(43)	41(36)	28(33)	30(29)	56(16)	84(14)	40(12)	27(12)	29(9)
Quinoline	129(100)	51(28)	76(25)	128(24)	44(24)	50(20)	32(19)	75(18)	74(12)	103(11)
Styrene	104(100)	103(41)	78(32)	51(28)	77(23)	105(12)	50(12)	52(11)	39(11)	102(10)
Sulfolane	41(100)	28(94)	56(82)	55(72)	120(37)	27(32)	39(19)	29(17)	26(11)	48(5)
α-Terpinene	121(100)	93(85)	136(43)	91(40)	77(34)	39(33)	27(33)	79(27)	41(26)	43(18)
1,1,1,2-Tetrachloro-2,2-difluoroethane	167(100)	169(96)	117(85)	119(82)	171(31)	85(29)	121(26)	82(14)	47(14)	101(13)
Tetrachloro-1,2-difluoroethane	101(100)	103(64)	167(54)	169(52)	117(19)	119(18)	171(17)	105(11)	31(11)	132(9)

Compound	*e/m* (intensity)									
1,1,1,2-Tetrachloroethane	131(100)	133(96)	117(76)	119(73)	95(34)	135(31)	121(23)	97(23)	61(19)	60(18)
1,1,2,2-Tetrachloroethane	83(100)	85(63)	95(11)	87(10)	168(8)	133(8)	131(8)	96(8)	61(8)	60(8)
Tetrachloroethylene	166(100)	164(82)	131(71)	129(71)	168(45)	94(38)	47(31)	96(24)	133(20)	59(17)
Tetraethylene glycol	45(100)	89(10)	44(8)	43(6)	31(6)	29(6)	27(6)	101(5)	75(5)	28(5)
Tetrahydrofuran	42(100)	41(52)	27(33)	72(29)	71(27)	39(24)	43(22)	29(22)	40(13)	15(10)
1,2,3,4-Tetrahydronaphthalene	104(100)	132(53)	91(43)	51(17)	39(17)	131(15)	117(15)	115(14)	78(13)	77(13)
Tetrahydropyran	41(100)	28(64)	56(57)	45(57)	29(51)	27(49)	85(47)	86(42)	39(28)	55(23)
Tetramethylsilane	73(100)	43(14)	45(12)	74(8)	29(7)	15(5)	75(4)	44(4)	42(4)	31(4)
Toluene	91(100)	92(73)	39(20)	65(14)	63(11)	51(11)	50(7)	27(6)	93(5)	90(5)
o-Toluidine	106(100)	107(83)	77(17)	79(13)	39(12)	53(10)	52(10)	54(9)	51(9)	28(9)
Triacetin	43(100)	103(44)	145(34)	116(17)	115(13)	44(10)	86(9)	28(8)	73(7)	42(7)
Tributylamine	142(100)	100(19)	143(11)	29(8)	185(7)	57(6)	44(6)	41(6)	30(5)	86(4)
1,1,1-Trichloroethane	97(100)	99(64)	61(58)	26(31)	27(24)	117(19)	63(19)	119(18)	35(17)	62(11)
1,1,2-Trichloroethane	97(100)	83(95)	99(62)	85(60)	61(58)	26(23)	96(21)	63(19)	27(17)	98(15)
Trichloroethylene	95(100)	130(90)	132(85)	60(65)	97(64)	35(40)	134(27)	47(26)	62(21)	59(13)
Trichlorofluoromethane	101(100)	103(66)	66(13)	105(11)	35(11)	47(9)	31(8)	82(4)	68(4)	37(4)
1,1,2-Trichlorotrifluoroethane	101(100)	151(68)	103(64)	85(45)	31(45)	153(44)	35(20)	66(19)	47(18)	87(14)
Triethanolamine	118(100)	56(69)	45(60)	42(56)	44(27)	43(25)	41(14)	116(8)	57(8)	86(7)
Triethylamine	86(100)	30(68)	58(37)	28(24)	29(23)	27(19)	44(18)	101(17)	42(16)	56(8)
Triethylene glycol	45(100)	58(11)	89(9)	31(8)	29(8)	75(7)	44(7)	43(7)	27(7)	28(5)
Triethyl phosphate	99(100)	81(71)	155(56)	82(45)	45(45)	109(44)	127(41)	43(24)	125(16)	111(14)
Trimethylamine	58(100)	59(47)	30(29)	42(26)	44(17)	15(14)	28(10)	18(10)	43(8)	57(7)
Trimethylene glycol (1,3-Propanediol)	28(100)	58(93)	31(76)	57(70)	29(40)	27(26)	45(24)	43(23)	19(18)	30(17)
Trimethyl phosphate	110(100)	109(35)	79(34)	95(25)	80(23)	15(20)	140(18)	47(10)	31(7)	139(5)
Veratrole	138(100)	95(65)	77(48)	123(44)	52(42)	41(33)	65(30)	51(29)	39(19)	63(17)
o-Xylene	91(100)	106(40)	39(21)	105(17)	51(17)	77(15)	27(12)	65(10)	92(8)	79(8)
m-Xylene	91(100)	106(65)	105(29)	39(18)	51(15)	77(14)	27(10)	92(8)	79(8)	78(8)
p-Xylene	91(100)	106(62)	105(30)	51(16)	39(16)	77(13)	27(11)	92(7)	78(7)	65(7)

SOLUBILITY OF COMMON SALTS AT AMBIENT TEMPERATURES

This table gives the aqueous solubility of selected salts at temperatures from 10°C to 40°C. Values are given in molality terms.

References

1. Apelblat, A., *J. Chem. Thermodynamics*, 24, 619, 1992.
2. Apelblat, A., *J. Chem. Thermodynamics*, 25, 63, 1993.
3. Apelblat, A., *J. Chem. Thermodynamics*, 25, 1513, 1993.
4. Apelblat, A. and Korin, E., *J. Chem. Thermodynamics,* 30, 59, 1998.

Salt	10°C	15°C	20°C	25°C	30°C	35°C	40°C	Ref.
$BaCl_2$	1.603	1.659	1.716	1.774	1.834	1.895	1.958	1
$Ca(NO_3)_2$	6.896	7.398	7.986	8.675	9.480	10.421		1
$CuSO_4$	1.055	1.153	1.260	1.376	1.502	1.639		3
$FeSO_4$	1.352	1.533	1.729	1.940	2.165	2.405		3
KBr	5.002	5.237	5.471	5.703	5.932	6.157		3
KIO_3	0.291	0.333	0.378	0.426	0.478	0.534	0.593	4
K_2CO_3	7.756	7.846	7.948	8.063	8.191	8.331	8.483	1
LiCl	19.296	19.456	19.670	19.935				2
$Mg(NO_3)_2$	4.403	4.523	4.656	4.800	4.958	5.130	5.314	1
$MnCl_2$	5.421	5.644	5.884	6.143	6.422	6.721		3
NH_4Cl	6.199	6.566	6.943	7.331				2
NH_4NO_3	18.809	21.163	23.721	26.496				2
$(NH_4)_2SO_4$	5.494	5.589	5.688	5.790	5.896	6.005		3
NaBr	8.258	8.546	8.856	9.191	9.550	9.937	10.351	4
NaCl	6.110	6.121	6.136	6.153	6.174	6.197	6.222	4
$NaNO_2$	11.111	11.484	11.883	12.310	12.766	13.253	13.772	4
$NaNO_3$	9.395	9.819	10.261	10.723	11.204	11.706	12.230	4
RbCl	6.911	7.180	7.449	7.717	7.986	8.253	8.520	4
$ZnSO_4$	2.911	3.116	3.336	3.573	3.827	4.099	4.194	1

FLAME AND BEAD TESTS

Flame Colorations

Violet

Potassium compounds. Purple red through blue glass. Easily obscured by sodium flame. Bluish-green through green glass. Rubidium and cesium compounds impart same flame as potassium compounds.

Blues

Azure — Copper chloride. Copper bromide gives azure blue followed by green. Other copper compounds give same coloration when moistened with hydrochloric acid.

Light blue — Lead, arsenic, selenium.

Greens

Emerald — Copper compounds except the halides, and when not moistened with hydrochloric acid.

Pure green — Compounds of thallium and tellurium.

Yellowish — Barium compounds. Some molybdenum compounds. Borates, especially when treated with sulfuric acid or when burned with alcohol.

Bluish — Phosphates with sulfuric acid.

Feeble — Antimony compounds. Ammonium compounds.

Whitish — Zinc.

Reds

Carmine — Lithium compounds. Violet through blue glass. Invisible through green glass. Masked by barium flame.

Scarlet — Strontium compounds. Violet through blue glass. Yellowish through green glass. Masked by barium flame.

Yellowish — Calcium compounds. Greenish through blue glass. Green through green glass. Masked by barium flame.

Yellow

Yellow — All sodium compounds. Invisible with blue glass.

Bead Tests

Abbreviations employed: s = saturated; ss = supersaturated; ns = not saturated; h = hot; c = cold

Borax Beads

Substance	Oxidizing flame	Reducing flame
Aluminum	Colorless (h, c, ns); opaque (ss)	Colorless; opaque (s)
Antimony	Colorless; yellow or brownish (h, ss)	Gray and opaque
Barium	Colorless (ns)	
Bismuth	Colorless; yellow or brownish (h, ss)	Gray and opaque
Cadmium	Colorless	Gray and opaque
Calcium	Colorless (ns)	
Cerium	Red (h)	Colorless (h, c)
Chromium	Green (c)	Green
Cobalt	Blue (h, c)	Blue (h, c)
Copper	Green (h); blue (c)	Red (c); opaque (ss); colorless (h)
Iron	Yellow or brownish red (h, ns)	Green (ss)
Lead	Colorless; yellow or brownish (h, ss)	Gray and opaque
Magnesium	Colorless (ns)	
Manganese	Violet (h, c)	Colorless (h, c)
Molybdenum	Colorless	Yellow or brown (h)
Nickel	Brown; red (c)	Gray and opaque
Silicon	Colorless (h, c); opaque (ss)	Colorless; opaque (s)
Silver	Colorless (ns)	Gray and opaque
Strontium	Colorless (ns)	
Tin	Colorless (h, c); opaque (ss)	Colorless; opaque (s)
Titanium	Colorless	Yellow (h); violet (c)
Tungsten	Colorless	Brown
Uranium	Yellow or brownish (h, ns)	Green
Vanadium	Colorless	Green

Beads of Microcosmic Salt
$NaNH_4HPO_4$

Substance	Oxidizing flame	Reducing flame
Aluminum	Colorless; opaque (s)	Colorless; not clear (ss)
Antimony	Colorless (ns)	Gray and opaque
Barium	Colorless; opaque (s)	Colorless; not clear (ss)
Bismuth	Colorless (ns)	Gray and opaque
Cadmium	Colorless (ns)	Gray and opaque
Calcium	Colorless; opaque (s)	Colorless; not clear (ss)

Beads of Microcosmic Salt $NaNH_4HPO_4$

Substance	Oxidizing flame	Reducing flame
Cerium	Yellow or brownish red (h, s)	Colorless
Chromium	Red (h, s); green (c)	Green (c)
Cobalt	Blue (h, c)	Blue (h, c)
Copper	Blue (c); green (h)	Red and opaque (c)
Iron	Yellow or brown (h, s)	Colorless; yellow or brownish (h)
Lead	Colorless (ns)	Gray and opaque
Magnesium	Colorless; opaque (s)	Colorless; not clear (ss)
Manganese	Violet (h, c)	Colorless
Molybdenum	Colorless; green (h)	Green (h)
Nickel	Yellow (c); red (h, s)	Yellow (c); red (h); gray and opaque
Silver		Gray and opaque
Strontium	Colorless; opaque (s)	Colorless; not clear (ss)
Tin	Colorless; opaque (s)	Colorless
Titanium	Colorless (ns)	Violet (c); yellow or brownish (h)
Uranium	Green; yellow or brownish	Green (h) (h, s)
Vanadium	Yellow	Green
Zinc	Colorless (ns)	Gray and opaque

Sodium Carbonate Bead

Substance	Oxidizing flame	Reducing flame
Manganese	Green	Colorless

BOND LENGTHS IN CRYSTALLINE ORGANIC COMPOUNDS

The following table gives average interatomic distances for bonds between the elements H, B, C, N, O, F, Si, P, S, Cl, As, Se, Br, Te, and I as determined from X-ray and neutron diffraction measurements on organic crystals. The table has been derived from an analysis of high-precision structure data on about 10,000 crystals contained in the 1985 version of the Cambridge Structural Database, which is maintained by the Cambridge Crystallographic Data Center. The explanation of the columns is:

Column 1: Specification of elements in the bond, with coordination number given in parentheses, and bond type (single, double, etc.). For carbon, the hybridization state is given.

Column 2: Substructure in which the bond is found. The target bond is set in boldface. Where X is not specified, it denotes any element type. C# indicates any sp^3 carbon atom, and C* denotes an sp^3 carbon whose bonds, in addition to those specified in the linear formulation, are to C and H atoms only.

Column 3: *d* is the unweighted mean in Å units of all the values for that bond length found in the sample.

Column 4: *m* is the median in Å units of all values.

Column 5: σ is the standard deviation in the sample.

Column 6: q_1 is the lower quartile for the sample (i.e., 25% of values are less than q_1 and 75% exceed it).

Column 7: q_u is the upper quartile for the sample.

Column 8: *n* is number of observations in the sample.

Column 9: Notes refer to the footnotes in Appendix 1.

References to special cases are given in a shorthand form and listed in Appendix 2. Further information on the method of analysis of the data may be found in the reference cited below.

The table is reprinted with permission of the authors, the Royal Society of Chemistry, and the International Union of Crystallography.

Reference

Frank H. Allen, Olga Kennard, David G. Watson, Lee Brammer, A. Guy Orpen, and Robin Taylor, *J. Chem. Soc. Perkin Trans.* II, S1–S19, 1987.

Bond	Substructure	*d*	*m*	σ	q_1	q_u	*n*	Note
As(3)–As(3)	X_2–**As–As**–X_2	2.459	2.457	0.011	2.456	2.466	8	
As–B	see CUDLOC (2.065), CUDLUI (2.041)							
As–BR	see CODDEE, CODDII (2.346–3.203)							
As(4)–C	$\mathbf{X_3}$**–As–C**$\mathbf{H_3}$	1.903	1.907	0.016	1.893	1.916	12	
	$(X)_2$(C,O,S=)**As–C***sp*^{3}	1.927	1.929	0.017	1.921	1.937	16	
	As–C*ar* in Ph_4As^+	1.905	1.909	0.012	1.897	1.912	108	
	$(X)_2$(C,O,S=)**As–C***ar*	1.922	1.927	0.016	1.908	1.934	36	
As(3)–C	X_2–**As–C***sp*^{3}	1.963	1.965	0.017	1.948	1.978	6	
	X_2–**As–C***ar*	1.956	1.956	0.015	1.944	1.964	41	
As(3)–Cl	X_2–**As–C**l	2.268	2.256	0.039	2.247	2.281	10	
As(6)–F	in $\mathbf{AsF_6^-}$	1.678	1.676	0.020	1.659	1.695	36	
As(3)–I	see OPIMAS (2.579, 2.590)							
As(3)–N(3)	X_2–**As–N**–X_2	1.858	1.858	0.029	1.839	1.873	19	
As(4)=N(2)	see TPASSN (1.837)							
As(4)–O	$(X)_2$(O=)**As–OH**	1.710	1.712	0.017	1.695	1.726	6	
As(3)–O	see ASAZOC, PHASOC01 (1.787–1.845)							
As(4)=O	X_3–**As=O**	1.661	1.661	0.016	1.652	1.667	9	
As(3)=P(3)	see BELNIP (2.350, 2.362)							†
As(3)–P(3)	see BUTHAZ10 (2.124)							†
As(3)–S	X_2–**As–S**	2.275	2.266	0.032	2.247	2.298	14	
As(4)=S	X_3–**As=S**	2.083	2.082	0.004	2.080	2.086	9	
As(3)–Se(2)	see COSDIX, ESEARS (2.355–2.401)							†
As(3)–Si(4)	see BICGEZ, MESIAD (2.351–2.365)							†
As(3)–Te(2)	see ETEARS (2.571, 2.576)							†
B(n)–B(n)	*n* = 5–7 in boron cages	1.775	1.773	0.031	1.763	1.786	688	
B(4)–B(4)	see CETTAW (2.041)							
B(4)–B(3)	see COFVOI (1.698)							
B(3)–B(3)	X_2–**B–B**–X_2	1.701	1.700	0.014	1.691	1.712	8	
B(6)–BR		1.967	1.971	0.014	1.954	1.979	7	†
B(4)–BR		2.017	2.008	0.031	1.990	2.044	15	†
B(*n*)–C	*n* = 5–7: **B–C** in cages	1.716	1.717	0.020	1.707	1.728	96	
	n = 3–4: **B–C***sp*^{3} not cages	1.597	1.599	0.022	1.585	1.611	29	1
	n = 4: **B–C***ar*	1.606	1.607	0.012	1.596	1.615	41	
	n = 4: **B–C***ar* in Ph_4B^-	1.643	1.643	0.006	1.641	1.645	16	
B(*n*)–C	*n* = 3: **B–C***ar*	1.556	1.552	0.015	1.546	1.566	24	
B(*n*)–Cl	**B**(5)**–Cl** and **B**(3)**–Cl**	1.751	1.751	0.011	1.743	1.761	14	

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
	B(4)–**Cl**	1.833	1.833	0.013	1.821	1.843	22	
B(4)–F	**B–F** (B neutral)	1.366	1.368	0.017	1.356	1.375	25	
	B$^-$**–F** in BF_4^-	1.365	1.372	0.029	1.352	1.390	84	
B(4)–I	see TMPBTI (2.220, 2.253)							
B(4)–N(3)	X_3–**B**–**N**(=C)(X)	1.611	1.617	0.013	1.601	1.625	8	
	in pyrazaboles	1.549	1.552	0.015	1.536	1.560	10	
B(3)–N(3)	X_2–**B–N**–C_2: all coplanar	1.404	1.404	0.014	1.389	1.408	40	2
	for τ(BN) > 30° see BOGSUL, BUSHAY, CILRUK (1.434–1.530)							
	S_2–**B–N**–X_2	1.447	1.443	0.013	1.435	1.470	14	
B(4)–O	**B**$^-$**–O** in BO^-_4	1.468	1.468	0.022	1.453	1.479	24	
	for neutral B–O see Note 3							3
B(3)–O(2)	X_2–**B–O**–X	1.367	1.367	0.024	1.349	1.382	35	
B(*n*)–P	*n* = 4: **B–P**	1.922	1.927	0.027	1.900	1.954	10	
	n = 3: see BUPSIB10 (1.892, 1.893)							
B(4)–S	**B**(4)–**S**(3)	1.930	1.927	0.009	1.925	1.934	10	
	B(4)–**S**(2)	1.896	1.896	0.004	1.893	1.899	6	
B(3)–S	N–**B**–S_2	1.806	1.806	0.010	1.799	1.816	28	
	(=X–)(N–)**B–S**	1.851	1.854	0.013	1.842	1.859	10	
Br–Br	see BEPZEB, TPASTB	2.542	2.548	0.015	2.526	2.551	4	
Br–C	**Br–C***	1.966	1.967	0.029	1.951	1.983	100	4
	Br–C*sp*^{3} (cyclopropane)	1.910	1.910	0.010	1.900	1.914	8	
	Br–C*sp*^{2}	1.883	1.881	0.015	1.874	1.894	31	4
	Br–C*ar* (mono-Br + *m.p*-Br_2)	1.899	1.899	0.012	1.892	1.906	119	4
	Br–C*ar* (o-Br_2)	1.875	1.872	0.011	1.864	1.884	8	4
$^-$Br(2)–Cl	see TEACBR (2.362–2.402)							†
Br–I	see DTHIBR10 (2.646), TPHOSI (2.695)							
Br–N	see NBBZAM (1.843)							
Br–O	see CIYFOF	1.581	1.581	0.007	1.574	1.587	4	
Br–P	see CISTED (2.366)							
Br–S(2)	see BEMLIO (2.206)							†
Br–S(3)	see CIWYIQ (2.435, 2.453)							†
Br–S(3)$^+$	see THINBR (2.321)							†
Br–SE	see CIFZUM (2.508, 2.619)							
Br–Si	see BIZJAV (2.284)							
Br–Te	In $\mathbf{Br_6Te}^{2-}$ see CUGBAH (2.692–2.716)							
	Br–Te(4) see BETUTE10 (3.079, 3.015)							
	Br–Te(3) see BTUPTE (2.835)							
C*sp*^{3}**–C***sp*^{3}	C#–$\mathbf{CH_2}$–$\mathbf{CH_3}$	1.513	1.514	0.014	1.507	1.523	192	
	$(C\#)_2$–**CH**–$\mathbf{CH_3}$	1.524	1.526	0.015	1.518	1.534	226	
	$(C\#)_3$–**C**–$\mathbf{CH_3}$	1.534	1.534	0.011	1.527	1.541	825	
	C#–$\mathbf{CH_2}$–$\mathbf{CH_2}$–C#	1.524	1.524	0.014	1.516	1.532	2459	
	$(C\#)_2$–**CH**–$\mathbf{CH_2}$–C#	1.531	1.531	0.012	1.524	1.538	1217	
	$(C\#)_3$–**C**–$\mathbf{CH_2}$–C#	1.538	1.539	0.010	1.533	1.544	330	
	$(C\#)_2$–**CH–CH**–$(C\#)_2$	1.542	1.542	0.011	1.536	1.549	321	
	$(C\#)_3$–**C–CH**–$(C\#)_2$	1.556	1.556	0.011	1.549	1.562	215	
	$(C\#)_3$–**C–C**–$(C\#)_3$	1.588	1.580	0.025	1.566	1.610	21	
	C*–C* (overall)	1.530	1.530	0.015	1.521	1.539	5777	5,6
	in cyclopropane (any subst.)	1.510	1.509	0.026	1.497	1.523	888	7
	in cyclobutane (any subst.)	1.554	1.553	0.021	1.540	1.567	679	8
	in cyclopentane (C,H-subst.)	1.543	1.543	0.018	1.532	1.554	1641	
	in cyclohexane (C,H-subst.)	1.535	1.535	0.016	1.525	1.545	2814	
	cyclopropyl-C* (exocyclic)	1.518	1.518	0.019	1.505	1.531	366	7
	cyclobutyl-C* (exocyclic)	1.529	1.529	0.016	1.519	1.539	376	8
	cyclopentyl-C* (exocyclic)	1.540	1.541	0.017	1.527	1.549	956	
	cyclohexyl-C* (exocyclic)	1.539	1.538	0.016	1.529	1.549	2682	
	in cyclobutene (any subst.)	1.573	1.574	0.017	1.566	1.586	25	8
	in cyclopentene (C,H-subst.)	1.541	1.539	0.015	1.532	1.549	208	
	in cyclohexene (C,H-subst.)	1.541	1.541	0.020	1.528	1.554	586	
	in oxirane (epoxide)	1.466	1.466	0.015	1.458	1.474	249	9
	in aziridine	1.480	1.481	0.021	1.465	1.496	67	9

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
	in oxetane	1.541	1.541	0.019	1.527	1.557	16	
	in azetidine	1.548	1.543	0.018	1.536	1.558	22	
	oxiranyl-C* (exocyclic)	1.509	1.507	0.018	1.497	1.519	333	9
	aziridinyl-C* (exocyclic)	1.512	1.512	0.018	1.496	1.526	13	9
C*sp*³–C*sp*²	**C**H$_3$–**C**=C	1.503	1.504	0.011	1.497	1.509	215	
	C#–**C**H$_2$–**C**=C	1.502	1.502	0.013	1.494	1.510	483	
	(C#)$_2$–**C**H–**C**=C	1.510	1.510	0.014	1.501	1.518	564	
	(C#)$_3$–**C**–**C**=C	1.522	1.522	0.016	1.511	1.533	193	
C*sp*³–C*sp*²	**C***–**C**=C (overall)	1.507	1.507	0.015	1.499	1.517	1456	5
	C*–**C**=C (endocyclic)							
	in cyclopropene	1.509	1.508	0.016	1.500	1.516	20	10
	in cyclobutene	1.513	1.512	0.018	1.500	1.525	50	8
	in cyclopentene	1.512	1.512	0.014	1.502	1.521	208	
	in cyclohexene	1.506	1.505	0.016	1.495	1.516	391	
	in cyclopentadiene	1.502	1.503	0.019	1.490	1.515	18	
	in cyclohexa-1,3-diene	1.504	1.504	0.017	1.491	1.517	56	
	C*–**C**=C (exocyclic):							
	cyclopropenyl-C*	1.478	1.475	0.012	1.470	1.485	7	10
	cyclobutenyl-C*	1.489	1.483	0.015	1.479	1.496	11	8
	cyclopentenyl-C*	1.504	1.506	0.012	1.495	1.512	115	
	cyclohexenyl-C*	1.511	1.511	0.013	1.502	1.519	292	
	C*–**C**H=O in aldehydes	1.510	1.510	0.008	1.501	1.518	7	
	(**C***)$_2$–**C**=O							
	in ketones	1.511	1.511	0.015	1.501	1.521	952	11
	in cyclobutanone	1.529	1.530	0.016	1.514	1.545	18	
	in cyclopentanone	1.514	1.514	0.016	1.505	1.523	312	
	acyclic and 6 + rings	1.509	1.509	0.016	1.499	1.519	626	
	C*–**COOH** in carboxylic acids	1.502	1.502	0.014	1.495	1.510	176	
	C*–**COO**$^-$ in carboxylate anions	1.520	1.521	0.011	1.516	1.528	57	
	C*–**C**(=O)(–OC*)							
	in acyclic esters	1.497	1.496	0.018	1.484	1.509	553	12
	in β-lactones	1.519	1.519	0.020	1.500	1.538	4	13
	in γ-lactones	1.512	1.512	0.015	1.501	1.521	110	12
	in δ-lactones	1.504	1.502	0.013	1.495	1.517	27	12
	cyclopropyl (**C**)–**C**=O in ketones, acids and esters	1.486	1.485	0.018	1.474	1.497	105	7
	C*–**C**(=O)(–NH$_2$) in acyclic amides	1.514	1.512	0.016	1.506	1.526	32	14
	C*–**C**(=O)(–NHC*) in acyclic amides	1.506	1.505	0.012	1.498	1.515	78	14
	C*–**C**(=O)[–N(C*)$_2$] in acyclic amides	1.505	1.505	0.011	1.496	1.517	15	14
C*sp*³–C*ar*	**C**H$_3$–**C***ar*	1.506	1.507	0.011	1.501	1.513	454	
	C#–**C**H$_2$–**C***ar*	1.510	1.510	0.009	1.505	1.516	674	
	(C#)$_2$–**C**H–**C***ar*	1.515	1.515	0.011	1.508	1.522	363	
	(C#)$_3$–**C**–**C***ar*	1.527	1.530	0.016	1.517	1.539	308	
	C*–**C***ar* (overall)	1.513	1.513	0.014	1.505	1.521	1813	
	cyclopropyl (**C**)–**C***ar*	1.490	1.490	0.015	1.479	1.503	90	7
C*sp*³–C*sp*¹	**C***–**C**≡C	1.466	1.465	0.010	1.460	1.469	21	15
	C#–**C**≡C	1.472	1.472	0.012	1.464	1.481	88	15
	C*–**C**≡N	1.470	1.469	0.013	1.463	1.479	106	7b
	cyclopropyl (**C**)–**C**≡N	1.444	1.447	0.010	1.436	1.451	38	7
C*sp*²–C*sp*²	C=**C**–**C**=C							
	(conjugated)	1.455	1.455	0.011	1.447	1.463	30	16,18
	(unconjugated)	1.478	1.476	0.012	1.470	1.479	8	17,18
	(overall)	1.460	1.460	0.015	1.450	1.470	38	
	C=**C**–**C**=**C**–**C**=C	1.443	1.445	0.013	1.431	1.454	29	18
	C=**C**–**C**=C (endocyclic in TCNQ)	1.432	1.433	0.012	1.424	1.441	280	19
	C=**C**–**C**(=O)(–C*)							
	(conjugated)	1.464	1.462	0.018	1.453	1.476	211	16,18
	(unconjugated)	1.484	1.486	0.017	1.475	1.497	14	17,18
	(overall)	1.465	1.462	0.018	1.453	1.478	226	
	C=**C**–**C**(=O)–**C**=C							
	in benzoquinone (C,H-subst. only)	1.478	1.476	0.011	1.469	1.488	28	
	in benzoquinone (any subst.)	1.478	1.478	0.031	1.464	1.498	172	

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
	non-quinonoid	1.456	1.455	0.012	1.447	1.464	28	
	C=**C**–**C**OOH	1.475	1.476	0.015	1.461	1.488	22	
	C=**C**–**C**OOC*	1.488	1.489	0.014	1.478	1.497	113	
	C=**C**–**C**OO⁻	1.502	1.499	0.017	1.488	1.510	11	
	HOO**C**–**C**OOH	1.538	1.537	0.007	1.535	1.541	9	
	HOO**C**–**C**OO⁻	1.549	1.552	0.009	1.546	1.553	13	
	⁻OO**C**–**C**OO⁻	1.564	1.559	0.022	1.554	1.568	9	
	formal Csp^2–Csp^2 single bond in selected non-fused heterocycles:							
	in 1*H*-pyrrole (C3–C4)	1.412	1.410	0.016	1.401	1.427	29	
	in furan (C3–C4)	1.423	1.423	0.016	1.412	1.433	62	
	in thiophene (C3–C4)	1.424	1.425	0.015	1.415	1.433	40	
	in pyrazole (C3–C4)	1.410	1.412	0.016	1.400	1.418	20	
	in isoxazole (C3–C4)	1.425	1.425	0.016	1.413	1.438	9	
	in furazan (C3–C4)	1.428	1.427	0.007	1.422	1.435	6	
	in furoxan (C3–C4)	1.417	1.417	0.006	1.412	1.422	14	
Csp^2–Car	C=**C**–**C***ar*							
	(conjugated)	1.470	1.470	0.015	1.463	1.480	37	16,18
Csp^2–Car		1.488	1.490	0.012	1.480	1.496	87	17,18
	(overall)	1.483	1.483	0.015	1.472	1.494	124	
	cyclopropenyl (C=**C)**–**C***ar*	1.447	1.448	0.006	1.441	1.452	8	10
	C*ar*–**C**(=O)–C*	1.488	1.489	0.016	1.478	1.500	84	
	C*ar*–**C**(=O)–**C***ar*	1.480	1.481	0.017	1.468	1.494	58	
	C*ar*–**C**OOH	1.484	1.485	0.014	1.474	1.491	75	
	C*ar*–**C**(=O)(–OC*)	1.487	1.487	0.012	1.480	1.494	218	
	C*ar*–**C**OO⁻	1.504	1.509	0.014	1.495	1.512	26	
	C*ar*–**C**(–O)–NH_2	1.500	1.503	0.020	1.498	1.510	19	
	C*ar*–**C**=N–C#							
	(conjugated)	1.476	1.478	0.014	1.466	1.486	27	16
	(unconjugated)	1.491	1.490	0.008	1.485	1.496	48	17
	(overall)	1.485	1.487	0.013	1.481	1.493	75	
	in indole (C3–C3a)	1.434	1.434	0.011	1.428	1.439	40	
Csp^2–Csp^1	C=**C**–**C**≡C	1.431	1.427	0.014	1.425	1.441	11	7b
	C=**C**–**C**≡N in TCNQ	1.427	1.427	0.010	1.420	1.433	280	19
Car–Car	in biphenyls (*ortho* subst. all **H**)	1.487	1.488	0.007	1.484	1.493	30	
	(≥1 non-**H** *ortho*-subst.)	1.490	1.491	0.010	1.486	1.495	212	
Car–Csp^1	**C***ar*–**C**≡C	1.434	1.436	0.006	1.430	1.437	37	
	C*ar*–**C**≡N	1.443	1.444	0.008	1.436	1.448	31	
Csp^1–Csp^1	C≡**C**–**C**=C	1.377	1.378	0.012	1.374	1.384	21	
Csp^2=Csp^2	C*–CH=CH_2	1.299	1.300	0.027	1.280	1.311	42	
	(**C***)$_2$–**C**=CH_2	1.321	1.321	0.013	1.313	1.328	77	
	C*–**CH=CH**–C*							
	(*cis*)	1.317	1.318	0.013	1.310	1.323	106	
	(*trans*)	1.312	1.311	0.011	1.304	1.320	19	
	(overall)	1.316	1.317	0.015	1.309	1.323	127	
	(C*)$_2$–**C**=**CH**–C*	1.326	1.328	0.011	1.319	1.334	168	
	(C*$_2$–**C=C**–(C*)$_2$	1.331	1.330	0.009	1.326	1.334	89	
	(C*,H)$_2$–**C=C**–(C*,H)$_2$ (overall)	1.322	1.323	0.014	1.315	1.331	493	5
	in cyclopropene (any subst.)	1.294	1.288	0.017	1.284	1.302	10	10
	in cyclobutene (any subst.)	1.335	1.335	0.019	1.324	1.347	25	8
	in cyclopentene (C,H-subst.)	1.323	1.324	0.013	1.314	1.331	104	
	in cyclohexene (C,H-subst.)	1.326	1.325	0.012	1.318	1.334	196	
	C=C=C (allenes, any subst.)	1.307	1.307	0.005	1.303	1.310	18	
	C=C–C=C (C,**H** subst., conjugated)	1.330	1.330	0.014	1.322	1.338	76	16
	C=C–C=C–C=C (C,**H** subst., conjugated)	1.345	1.345	0.012	1.337	1.350	58	16
	C=**C**–**C***ar* (C,H subst., conjugated)	1.339	1.340	0.011	1.334	1.346	124	16
	C=C in cyclopenta-1,3-diene (any subst.)	1.341	1.341	0.017	1.328	1.356	18	
	C=C in cyclohexa-1,3-diene (any subst.)	1.332	1.332	0.013	1.323	1.341	56	
	in **C=C**–C=O							
	(C,**H** subst., conjugated)	1.340	1.340	0.013	1.332	1.348	211	16,18
	(C,**H** subst., unconjugated)	1.331	1.330	0.008	1.326	1.339	14	17,18

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
	(C,**H** subst., overall)	1.340	1.339	0.013	1.332	1.348	226	
	in cyclohexa-2,5-dien-1-ones	1.329	1.327	0.011	1.321	1.335	28	
	in *p*-benzoquinones							
	(C*,**H** subst.)	1.333	1.337	0.011	1.325	1.338	14	
	(any subst.)	1.349	1.339	0.030	1.330	1.364	86	
	in TCNQ							
	(endocyclic)	1.352	1.353	0.010	1.345	1.358	142	19
	(exocyclic)	1.392	1.391	0.017	1.379	1.405	139	19
	C=C–OH in enol tautomers	1.362	1.360	0.020	1.349	1.370	54	
	in heterocycles (any subst.):							
	1*H*-pyrrole (C2–C3, C4–C5)	1.375	1.377	0.018	1.361	1.388	58	
	furan (C2–C3, C4–C5)	1.341	1.342	0.021	1.329	1.351	125	
	thiophene (C2–C3, C4–C5)	1.362	1.359	0.025	1.346	1.377	60	
	pyrazole (C4–C5)	1.369	1.372	0.019	1.362	1.383	20	
	imidazole (C4–C5)	1.360	1.361	0.014	1.352	1.367	44	
	isoxazole (C4–C5)	1.341	1.336	0.012	1.331	1.355	9	
	indole (C2–C3)	1.364	1.363	0.012	1.355	1.371	40	
Car ≃ *Car*	in phenyl rings with C*, **H** subst. only							
	H–**C** ≃ **C**–H	1.380	1.381	0.013	1.372	1.388	2191	
	C*–**C** ≃ **C**–H	1.387	1.388	0.010	1.382	1.393	891	
	C*–**C** ≃ **C**–C*	1.397	1.397	0.009	1.392	1.403	182	
	C ≃ **C** (overall)	1.384	1.384	0.013	1.375	1.391	3264	
	F–**C** ≃ **C**–F	1.372	1.374	0.011	1.366	1.380	84	4
	Cl–**C** ≃ **C**–Cl	1.388	1.389	0.014	1.380	1.398	152	4
	in naphthalene (D_{2h}, any subst.)							
	C1–C2	1.364	1.364	0.014	1.356	1.373	440	
	C2–C3	1.406	1.406	0.014	1.397	1.415	218	
	C1–C8a	1.420	1.419	0.012	1.412	1.426	440	
	C4a–C8a	1.422	1.424	0.011	1.417	1.429	109	
Car ≃ *Car*	in anthracene ($D_{2h,}$ any subst.)							
	C1–C2	1.356	1.356	0.009	1.350	1.360	56	
	C2–C3	1.410	1.410	0.010	1.401	1.416	34	
	C1–C9a	1.430	1.430	0.006	1.426	1.434	56	
	C4a–C9a	1.435	1.436	0.007	1.429	1.440	34	
	C9–C9a	1.400	1.402	0.009	1.395	1.406	68	
	in pyridine (C,H subst.)	1.379	1.381	0.012	1.371	1.387	276	20
	(any subst.)	1.380	1.380	0.015	1.371	1.389	537	20
	in pyridinium cation							
	(N^+ –H; C,H subst. on C)							
	C2–C3	1.373	1.375	0.012	1.368	1.380	30	
	C3–C4	1.379	1.380	0.011	1.371	1.388	30	
	(N^+ –X; C,H subst. on C)							
	C2–C3	1.373	1.372	0.019	1.362	1.382	151	
	C3–C4	1.383	1.385	0.019	1.372	1.394	151	
	in pyrazine (H subst. on C)	1.379	1.377	0.010	1.370	1.388	10	
	(any subst. on C)	1.405	1.405	0.024	1.388	1.420	60	
	in pyrimidine (C,H subst. on C)	1.387	1.389	0.018	1.379	1.400	28	
Csp^1≡Csp^1	X–**C**≡**C**–X	1.183	1.183	0.014	1.174	1.193	119	15
	C,H–**C**≡**C**–C,H	1.181	1.181	0.014	1.173	1.192	104	15
	in **C**≡**C**–C(sp^2,*ar*)	1.189	1.193	0.010	1.181	1.195	38	15
	in **C**≡**C**–**C**≡**C**	1.192	1.192	0.010	1.187	1.197	42	15
	in **CH**≡**C**–C#	1.174	1.174	0.011	1.167	1.180	42	15
Csp^3–Cl	Omitting 1,2-dichlorides:							
	C–**CH_2–Cl**	1.790	1.790	0.007	1.783	1.795	13	4
	C_2–**CH–Cl**	1.803	1.802	0.003	1.800	1.807	8	4
	C_3–**C–Cl**	1.849	1.856	0.011	1.837	1.858	5	4
	X–CH_2–Cl (X = C,H,N,O)	1.790	1.791	0.011	1.783	1.797	37	4
	X_2–CH–Cl (X = C,H,N,O)	1.805	1.803	0.014	1.800	1.812	26	4
	X_3–**C–Cl** (X = C,H,N,O)	1.843	1.838	0.014	1.835	1.858	7	4
	X_2–**C–Cl_2** (X = C,H,N,O)	1.779	1.776	0.015	1.769	1.790	18	4
	X–**C–Cl_3** (X = C,H,N,O)	1.768	1.765	0.011	1.761	1.776	33	4

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
	Cl–CH(–C)–**CH**(–C)–**Cl**	1.793	1.793	0.013	1.786	1.800	66	4
	Cl–C($–C_2$)–**C**($–C_2$)–**Cl**	1.762	1.760	0.010	1.757	1.765	54	4
	cyclopropyl–Cl	1.755	1.756	0.011	1.749	1.763	64	
C*sp*²–Cl	C=**C–Cl** (C,H,N,O subst. on C)	1.734	1.729	0.019	1.719	1.748	63	4
	C=**C–**$\mathbf{Cl_2}$ (C,H,N,O subst. on C)	1.720	1.716	0.013	1.708	1.729	20	4
	Cl–C=C–Cl	1.713	1.711	0.011	1.705	1.720	80	4
C*ar*–Cl	**C***ar***–Cl** (mono–Cl + m,p-Cl_2)	1.739	1.741	0.010	1.734	1.745	340	4
	C*ar***–Cl** (*o*–Cl_2)	1.720	1.720	0.010	1.713	1.717	364	4
C*sp*¹Cl	see HCLENE10 (1.634, 1.646)							
C*sp*³–F	Omitting 1,2-difluorides							
	C–CH_2–**F** and C_2–CH–**F**	1.399	1.399	0.017	1.389	1.408	25	4
	C_3–C–F	1.428	1.431	0.009	1.421	1.435	11	4
	$(C^*,H)_2$–**C–**$\mathbf{F_2}$	1.349	1.347	0.012	1.342	1.356	58	4
	C*–**C–**$\mathbf{F_3}$	1.336	1.334	0.007	1.330	1.344	12	4
	F–C*–C*–F	1.371	1.374	0.007	1.362	1.375	26	4
	X_3–**C–F** (X = C,H,N,O)	1.386	1.389	0.033	1.373	1.408	70	4
	X_2–**C–**$\mathbf{F_2}$ (X = C,H,N,O)	1.351	1.349	0.013	1.342	1.356	58	4
	X–**C–**$\mathbf{F_3}$ (X = C,H,N,O)	1.322	1.323	0.015	1.314	1.332	309	4
	F–C($–X)_2$–**C**($–X)_2$–**F** (X = C,H,N,O)	1.373	1.374	0.009	1.362	1.377	30	4
	F–C($–X)_2$–NO_2 (X = any subst.)	1.320	1.319	0.009	1.312	1.327	18	
C*sp*²–F	C=**C–F** (C,H,N,O subst. on C)	1.340	1.340	0.013	1.334	1.346	34	4
C*ar*–F	**C***ar***–F** (mono-F + *m,p*-F_2)	1.363	1.362	0.008	1.357	1.368	38	4
	C*ar***–F** (*o*-F_2)	1.340	1.340	0.009	1.336	1.344	167	4
C*sp*³–H	C–**C–**$\mathbf{H_3}$ (methyl)	1.059	1.061	0.030	1.039	1.083	83	21
	C_2–**C–**$\mathbf{H_2}$ (primary)	1.092	1.095	0.013	1.088	1.099	100	21
	C_3–**C–H** (secondary)	1.099	1.097	0.004	1.095	1.103	14	21
	$C_{2,3}$–**C–H** (primary and secondary)	1.093	1.095	0.012	1.089	1.100	118	21
	X–**C–**$\mathbf{H_3}$ (methyl)	1.066	1.074	0.028	1.049	1.087	160	21
	X_2–**C–**$\mathbf{H_2}$ (primary)	1.092	1.095	0.012	1.088	1.099	230	21
	X_3–**C–H** (secondary)	1.099	1.099	0.007	1.095	1.103	117	21
	$X_{2,3}$–**C–H** (primary and secondary)	1.094	1.096	0.011	1.091	1.100	348	21
C*sp*²–H	C–C=**C–H**	1.077	1.079	0.012	1.074	1.085	14	21
C*ar*–H	**C***ar***–H**	1.083	1.083	0.011	1.080	1.087	218	21
C*sp*³–I	**C*–I**	2.162	2.159	0.015	2.149	2.179	15	4
C*ar*–I	**C***ar***–I**	2.095	2.095	0.015	2.089	2.104	51	4
C*sp*³–N(4)	**C*–**$\mathbf{NH_3^+}$	1.488	1.488	0.013	1.482	1.495	298	
	$(\mathbf{C^*})_2$–**N**$\mathbf{H_2^+}$	1.494	1.493	0.016	1.484	1.503	249	
	$(\mathbf{C^*})_3$–**NH**$^+$	1.502	1.502	0.015	1.491	1.512	509	
	$(\mathbf{C^*})_4$–**N**$^+$	1.510	1.509	0.020	1.496	1.523	319	
	C*–N$^+$ (overall)	1.499	1.498	0.018	1.488	1.510	1370	
C*sp*³–N(3)	**C*–N**$^+$ in N-subst. pyridinium	1.485	1.484	0.009	1.477	1.490	32	
	C*–$\mathbf{NH_2}$ (N*sp*³: pyramidal)	1.469	1.470	0.010	1.462	1.474	19	22
	$(\mathbf{C^*})_2$–**NH** (N*sp*³: pyramidal)	1.469	1.467	0.012	1.461	1.477	152	5,22
	$(C^*)_3$–**N** (N*sp*³: pyramidal)	1.469	1.468	0.014	1.460	1.476	1042	5,22
	C*–N*sp*³ (overall)	1.469	1.468	0.014	1.460	1.476	1201	
	C*sp*³–**N***sp*³							
	in aziridine	1.472	1.471	0.016	1.464	1.482	134	
	in azetidine	1.484	1.481	0.018	1.472	1.495	21	
	in tetrahydropyrrole	1.475	1.473	0.016	1.464	1.483	66	
	in piperidine	1.473	1.473	0.013	1.460	1.479	240	
	C*sp*³–**N***sp*² (N planar) in:							23
	acyclic amides **C*–NH**–C=O	1.454	1.451	0.011	1.446	1.461	78	14
	β-lactams **C*–N**(–X)–C=O (endo)	1.464	1.465	0.012	1.458	1.475	23	13
	γ-lactams							
	C*–NH–C=O (endo)	1.457	1.458	0.011	1.449	1.465	20	13
	C*–N(–C*)–C=O (endo)	1.462	1.461	0.010	1.453	1.466	15	13
	C*–N(–C*)–C=O (exo)	1.458	1.456	0.014	1.448	1.465	15	13
	δ-lactams							
	C*–NH–C=O (endo)	1.478	1.472	0.016	1.467	1.491	6	14
	C*–N(–C*)–C=O (endo)	1.479	1.476	0.007	1.475	1.482	15	14
	C*–N(–C*)–C=O (exo)	1.468	1.471	0.009	1.462	1.477	15	14

Bond	Substructure	*d*	*m*	*σ*	q_1	q_u	*n*	Note
	nitro compounds (1,2-dinitro omitted):							
	C–**C**H_2–**N**O_2	1.485	1.483	0.020	1.478	1.502	8	
	C_2–**C**H–**N**O_2	1.509	1.509	0.011	1.502	1.511	12	
	C_3–**C**–**N**O_2	1.533	1.533	0.013	1.530	1.539	17	
	C_2–**C**–(**N**O_2)$_2$	1.537	1.536	0.016	1.525	1.550	19	
	1,2-dinitro: **N**O_2–**C***–**C***–**N**O_2	1.552	1.550	0.023	1.536	1.572	32	
C*sp*³–N(2)	C#–**N**=N	1.493	1.493	0.020	1.477	1.506	54	
	C*–**N**=C–C*ar*	1.465	1.468	0.011	1.461	1.472	75	
C*sp*²–N(3)	C=**C**–**N**H_2 N*sp*² planar	1.336	1.344	0.017	1.317	1.348	10	23
	C=**C**–**N**H–**C**# N*sp*² planar	1.339	1.340	0.016	1.327	1.351	17	23
	C=**C**–**N**–(C#)$_2$							
	N*sp*² planar	1.355	1.358	0.014	1.341	1.363	22	23
	N*sp*³ pyramidal	1.416	1.418	0.018	1.397	1.432	18	22
	C*sp*²–N*sp*² (N planar) in:							23
	acyclic amides							
	NH_2–**C**=O	1.325	1.323	0.009	1.318	1.331	32	14
	C*–**N**H–**C**=O	1.334	1.333	0.011	1.326	1.343	78	14
	(C*)$_2$–**N**–**C**=O	1.346	1.342	0.011	1.339	1.356	5	14
	β-lactams C*–**NH**–**C**=O	1.385	1.388	0.019	1.374	1.396	23	13
	γ-lactams							
	C*–**NH**–**C**=O	1.331	1.331	0.011	1.326	1.337	20	13
	C*–N(–C*)–**C**=O	1.347	1.344	0.014	1.335	1.359	15	13
	δ-lactams							
	C*–**NH**–**C**=O	1.334	1.334	0.006	1.330	1.339	6	14
	(C*)–**N**(–C*)–**C**=O	1.352	1.353	0.010	1.344	1.356	15	14
	peptides C#–**N**(–X)–**C**(–C#)(=O)	1.333	1.334	0.013	1.326	1.340	380	24
	ureas							
	(**N**H_2)$_2$–**C**=O	1.334	1.334	0.008	1.329	1.339	48	25,26
	(C#–**N**H)$_2$–**C**=O	1.347	1.345	0.010	1.341	1.354	26	25
	[(C#)$_n$–**N**]$_2$–**C**=O	1.363	1.359	0.014	1.354	1.370	40	25,27
	thioureas	1.346	1.343	0.023	1.328	1.361	192	
	(X_2**N**)$_2$–**C**=S							
	imides							
	[C#–**C**(=O)]$_2$–**NH**	1.376	1.377	0.012	1.369	1.383	64	
	[C#–**C**(=O)]$_2$–**N**–C#	1.389	1.383	0.017	1.376	1.404	38	
	[C*sp*²–**C**(=O)]$_2$–**N**–C#	1.396	1.396	0.010	1.389	1.403	46	
	[C*sp*²–**C**(=O)]$_2$–**N**–C*sp*²	1.409	1.406	0.020	1.391	1.419	28	
	guanidinium [**C**–(**NH**$_2$)$_3$]$^+$ (unsubst.)	1.321	1.320	0.008	1.314	1.327	39	
	(any subst.)	1.328	1.325	0.015	1.317	1.333	140	
	in heterocyclic systems (any subst.)							
	1*H*-pyrrole (N1–C2, N1–C5)	1.372	1.374	0.016	1.363	1.384	58	
	indole (N1–C2)	1.370	1.370	0.012	1.364	1.377	40	
	pyrazole (N1–C5)	1.357	1.359	0.012	1.347	1.365	20	
	imidazole (N1–C2)	1.349	1.349	0.018	1.338	1.358	44	
	imidazole (N1–C5)	1.370	1.370	0.010	1.365	1.377	44	
C*sp*²–N(2)	in imidazole (N3–C4)	1.376	1.377	0.011	1.369	1.384	44	
C*ar*–N(4)	**C***ar*–**N**$^+$–(C,H)$_3$	1.465	1.466	0.007	1.461	1.470	23	
C*ar*–N(3)	**C***ar*–**NH**$_2$							
	(N*sp*²: planar)	1.355	1.360	0.020	1.340	1.372	33	23
	(N*sp*³: pyramidal)	1.394	1.396	0.011	1.385	1.403	25	22
	(overall)	1.375	1.377	0.025	1.363	1.394	98	28
C*ar*–N(3)	**C***ar*–**NH**–C#							
	(N*sp*²: planar)	1.353	1.353	0.007	1.347	1.359	16	23
	(N*sp*³: pyramidal)	1.419	1.423	0.017	1.412	1.432	8	22
	(overall)	1.380	1.364	0.032	1.353	1.412	31	28
	C*ar*–**N**–(C#)$_2$							
	(N*sp*²: planar)	1.371	1.370	0.016	1.363	1.382	41	23
	(N*sp*³: pyramidal)	1.426	1.425	0.011	1.421	1.431	22	22
	(overall)	1.390	1.385	0.030	1.366	1.420	69	28
	in indole (N1–C7a)	1.372	1.372	0.007	1.367	1.376	40	
	C*ar*–**N**O_2	1.468	1.469	0.014	1.460	1.476	556	

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
C*ar*–N(2)	**C***ar*–**N**=N	1.431	1.435	0.020	1.422	1.442	26	
C*sp*²=N(3)	in furoxan ($^+$N2=C3)	1.316	1.316	0.009	1.311	1.324	14	
C*sp*²=N(2)	C*ar*–**C=N**–C#	1.279	1.279	0.008	1.275	1.285	75	
	$(C,H)_2$–**C=N**–OH in oximes	1.281	1.280	0.013	1.273	1.288	67	
	S–**C=N**–X	1.302	1.302	0.021	1.285	1.319	36	
	in pyrazole (N2=C3)	1.329	1.331	0.014	1.315	1.339	20	
	in imidazole (C2=N3)	1.313	1.314	0.011	1.307	1.319	44	
	in isoxazole (N2=C3)	1.314	1.315	0.009	1.305	1.320	9	
	in furazan (N2=C3, C4=N5)	1.298	1.299	0.006	1.294	1.303	12	
	in furoxan (C4=N5)	1.304	1.306	0.008	1.300	1.308	14	
C*ar* ≃ N(3)	**C** ≃ **N**$^+$–H (pyrimidinium)	1.335	1.334	0.015	1.325	1.342	30	
	C ≃ **N**$^+$–C* (pyrimidinium)	1.346	1.346	0.010	1.340	1.352	64	
	C ≃ **N**$^+$–O$^-$ (pyrimidinium)	1.362	1.359	0.013	1.353	1.369	56	
C*ar* ≃ N(2)	**C** ≃ **N** (pyridine)	1.337	1.338	0.012	1.330	1.344	269	
	C ≃ **N** (pyrazine)	1.336	1.335	0.022	1.319	1.347	120	
	C ≃ **N** ≃ **C** (pyrimidine)	1.339	1.338	0.015	1.333	1.342	28	
	N ≃ **C** ≃ **N** (pyrimidine)	1.333	1.335	0.013	1.326	1.337	28	
	C ≃ **N** (pyrimidine) (overall)	1.336	1.337	0.014	1.331	1.339	56	
	in any 6-membered N-containing aromatic ring:							
	H–C ≃ **N** ≃ **C–H**	1.334	1.334	0.014	1.327	1.341	146	
	H–C ≃ **N** ≃ **C–C***	1.339	1.341	0.013	1.336	1.345	38	
	C*–C ≃ **N** ≃ **C–C***	1.345	1.345	0.008	1.342	1.348	24	
	C ≃ **N** ≃ **C** (overall)	1.336	1.337	0.014	1.329	1.344	204	
C*sp*¹≡N(2)	X–S–N≡C$^-$ (isothiocyanide)	1.144	1.147	0.006	1.140	1.148	6	
C*sp*¹≡N(1)	C*–**C≡N**	1.136	1.137	0.010	1.131	1.142	140	
	C=C–**C≡N** in TCNQ	1.144	1.144	0.008	1.139	1.149	284	19
	C*ar*–**C≡N**	1.138	1.138	0.007	1.133	1.143	31	
	X–**C≡N**	1.144	1.141	0.012	1.138	1.151	10	
	(*S*–**C≡N**)$^-$	1.155	1.156	0.012	1.147	1.165	14	
C*sp*³–O(2)	in alcohols							
	CH_3–OH	1.413	1.414	0.018	1.395	1.425	17	
	C–**CH_2–OH**	1.426	1.426	0.011	1.420	1.431	75	
	C_2–**CH–OH**	1.432	1.431	0.011	1.425	1.439	266	
	C_3–**C–OH**	1.440	1.440	0.012	1.432	1.449	106	
	C*–OH (overall)	1.432	1.431	0.013	1.424	1.441	464	
	in dialkyl ethers							29
	CH_3–O–C*	1.416	1.418	0.016	1.405	1.426	110	
	C–**CH_2–O**–C*	1.426	1.424	0.011	1.418	1.435	34	
	C_2–**CH–O**–C*	1.429	1.430	0.010	1.420	1.437	53	
	C_3–**C–O**–C*	1.452	1.450	0.011	1.445	1.458	39	
	C*–O–C* (overall)	1.426	1.425	0.019	1.414	1.437	236	5
	in aryl alkyl ethers							29
	CH_3–O–C*ar*	1.424	1.424	0.012	1.417	1.431	616	
	C–**CH_2–O**–C*ar*	1.431	1.430	0.013	1.422	1.438	188	
	C_2–**CH–O**–C*ar*	1.447	1.446	0.020	1.435	1.466	58	
	C_3–**C–O**–C*ar*	1.470	1.469	0.018	1.456	1.483	55	
	C*–O–C*ar* (overall)	1.429	1.427	0.018	1.419	1.436	917	
	in alkyl esters of carboxylic acids							12,29
	CH_3–O–C(=O)–C*	1.448	1.449	0.010	1.442	1.455	200	
	C–CH_2–O–C(=O)–C*	1.452	1.453	0.009	1.445	1.458	32	
	C_2–**CH–O**–C(=O)–C*	1.460	1.460	0.010	1.454	1.465	78	
	C_3–**C–O**–C(=O)–C*	1.477	1.475	0.008	1.472	1.484	6	
	C*–O–C(=O)–C* (overall)	1.450	1.451	0.014	1.442	1.459	314	
	in alkyl esters of α,β-unsaturated acids:							
	C*–O–C(=O)–C=C (overall)	1.453	1.452	0.013	1.444	1.459	112	
	in alkyl esters of benzoic acid							
	C*–O–C(=O)–C(phenyl) (overall)	1.454	1.454	0.012	1.446	1.463	219	
	in ring systems							
	oxirane (epoxides) (any subst.)	1.446	1.446	0.014	1.438	1.456	498	9
	oxetane (any subst.)	1.463	1.460	0.015	1.451	1.474	16	
	tetrahydrofuran (C,H subst.)	1.442	1.441	0.017	1.430	1.451	154	

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
C*sp*³–O(2)	tetrahydropyran (C,H subst.)	1.441	1.442	0.015	1.431	1.451	22	
	β-lactones: **C*–O**–C(=O)	1.492	1.494	0.010	1.481	1.501	4	16
	γ-lactones: **C*–O**–C(=O)	1.464	1.464	0.012	1.455	1.473	110	12
	δ-lactones: **C*–O**–C(=O)	1.461	1.464	0.017	1.452	1.473	27	12
	O–C–O system in *gem*-diols, and pyranose and furanose sugars:							30,31
	HO–C*–OH	1.397	1.401	0.012	1.388	1.405	18	
	C_5–O_5–C_1–O_1H in pyranoses							
	O_1 axial (α):							
	C_5–O_5	1.439	1.440	0.008	1.432	1.445	29	
	O_5–C_1	1.427	1.426	0.012	1.421	1.432	29	
	C_1–O_1	1.403	1.400	0.012	1.391	1.412	29	
	O_1 equatorial (β):							
	C_5–O_5	1.435	1.436	0.008	1.429	1.440	17	
	O_5–C_1	1.430	1.431	0.010	1.424	1.436	17	
	C_1–O_1	1.393	1.393	0.007	1.386	1.399	17	
	α + β (overall):							
	C_5–O_5	1.439	1.440	0.008	1.432	1.446	60	
	O_5–C_1	1.430	1.429	0.012	1.421	1.436	60	
	C_1–O_1	1.401	1.399	0.011	1.392	1.407	60	
	C_4–O_4–C_1–O_1H in furanoses (overall values)							
	C_4–O_4	1.442	1.446	0.012	1.436	1.449	18	
	O_4–C_1	1.432	1.432	0.012	1.421	1.443	18	
	C_1–O_1	1.404	1.405	0.013	1.397	1.409	18	
	C_5–O_5–C_1–O_1–C* in pyranoses							
	O_1 axial (α):							
	C_5–O_5	1.439	1.438	0.010	1.433	1.446	67	
	O_5–C_1	1.417	1.417	0.009	1.410	1.424	67	
	C_1–O_1	1.409	1.409	0.014	1.401	1.417	67	
	O_1–C*	1.435	1.435	0.013	1.427	1.443	67	
	O_1 equatorial (β):							
	C_5–O_5	1.434	1.435	0.006	1.429	1.439	39	
	O_5–C_1	1.424	1.424	0.008	1.418	1.431	39	
	C_1–O_1	1.390	1.390	0.011	1.381	1.400	39	
	O_1–C*	1.437	1.438	0.013	1.428	1.445	39	
	α + β (overall):							
	C_5–O_5	1.436	1.436	0.009	1.431	1.442	126	
	O_5–C_1	1.419	1.419	0.011	1.412	1.426	126	
	C_1–O_1	1.402	1.403	0.016	1.391	1.413	126	
	O_1–C*	1.436	1.436	0.013	1.428	1.445	126	
	C_4–O_4–C_1–O_1–C* in furanoses (overall values)							
	C_4–O_4	1.443	1.445	0.013	1.429	1.453	23	
	O_4–C_1	1.421	1.418	0.012	1.413	1.431	23	
	C_1–O_1	1.410	1.409	0.014	1.401	1.420	23	
	O_1–C*	1.439	1.437	0.014	1.429	1.449	23	
	Miscellaneous:							
	C#–O–SiX_3	1.416	1.416	0.017	1.405	1.428	29	
	C*–O–SO_2–C	1.465	1.461	0.014	1.454	1.475	33	
C*sp*²–O(2)	in enols: C=**C–OH**	1.333	1.331	0.017	1.324	1.342	53	
	in enol esters: C=**C–O–C***	1.354	1.353	0.016	1.341	1.363	40	
	in acids:							
	C*–**C**(=O)–**OH**	1.308	1.311	0.019	1.298	1.320	174	
	C=C–**C**(=O)–**OH**	1.293	1.295	0.019	1.279	1.307	22	
	C*ar*–**C**(=O)–**OH**	1.305	1.311	0.020	1.291	1.317	75	
	in esters:							
	C*–**C**(=O)–**O**–C*	1.336	1.337	0.014	1.328	1.346	551	12,29
	C=C–**C**(=O)–**O**–C*	1.332	1.331	0.011	1.324	1.339	112	
	C*ar*–**C**(=O)–**O**–C*	1.337	1.335	0.013	1.329	1.344	219	12
	C*–**C**(=O)–**O**–C=C	1.362	1.359	0.018	1.351	1.374	26	
	C*–**C**(=O)–**O**–C=C	1.407	1.405	0.017	1.394	1.420	26	

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
	C*–**C**(=O)–**O**–C*ar*	1.360	1.359	0.011	1.355	1.367	40	12
	in anhydrides: O=**C**–**O**–**C**=O	1.386	1.386	0.011	1.379	1.393	70	
	in ring systems:							
	furan (O1–C2, O1–C5)	1.368	1.369	0.015	1.359	1.377	125	
	isoxazole (O1–C5)	1.354	1.354	0.010	1.345	1.360	9	
	β-lactones: C*–**C**(=O)–**O**–C*	1.359	1.359	0.013	1.348	1.371	4	13
	γ-lactones: C*–**C**(=O)–**O**–C*	1.350	1.349	0.012	1.342	1.359	110	12
	δ-lactones: C*–**C**(=O)–**O**–C*	1.339	1.339	0.016	1.332	1.347	27	12
C*ar*–O(2)	in phenols: **C***ar*–**OH**	1.362	1.364	0.015	1.353	1.373	551	
	in aryl alkyl ethers: **C***ar*–**O**–C*	1.370	1.370	0.011	1.363	1.377	920	29,32
C*ar*–O(2)	in diaryl ethers: **C***ar*–**O**–**C***ar*	1.384	1.381	0.014	1.375	1.391	132	
	in esters: **C***ar*–**O**–C(=O)–C*	1.401	1.401	0.010	1.394	1.408	40	12
Csp^2=O(1)	in aldehydes and ketones:							
	C*–**CH**=**O**	1.192	1.192	0.005	1.188	1.197	7	
	$(C^*)_2$–**C**=**O**	1.210	1.210	0.008	1.206	1.215	474	5
	$(C\#)_2$–**C**=**O**							
	in cyclobutanones	1.198	1.198	0.007	1.194	1.204	12	
	in cyclopentanones	1.208	1.208	0.007	1.203	1.212	155	
	in cyclohexanones	1.211	1.211	0.009	1.207	1.216	312	
	C=C–**C**=**O**	1.222	1.222	0.010	1.216	1.229	225	
	$(C{=}C)_2$–**C**=**O**	1.233	1.229	0.010	1.226	1.242	28	
	C*ar*–**C**=**O**	1.221	1.218	0.014	1.212	1.229	85	
	$(C_{ar})_2$–**C**=**O**	1.230	1.226	0.015	1.220	1.238	66	
	C=**O** in benzoquinones	1.222	1.220	0.013	1.211	1.231	86	
	delocalized double bonds in carboxylate anions:							
	H–**C** ≃ $\mathbf{O_2^-}$ (formate)	1.242	1.243	0.012	1.234	1.252	24	
	C*–**C** ≃ $\mathbf{O_2^-}$	1.254	1.253	0.010	1.247	1.261	114	
	C=C–**C** ≃ $\mathbf{O_2^-}$	1.250	1.248	0.017	1.238	1.261	52	
	C*ar*–**C** ≃ $\mathbf{O_2^-}$	1.255	1.253	0.010	1.249	1.262	22	
	HOO**C**–**C** ≃ $\mathbf{O_2^-}$ (hydrogen oxalate)	1.243	1.247	0.015	1.232	1.256	26	
	$\mathbf{^-O_2}$ ≃ **C**–**C** ≃ $\mathbf{O_2^-}$ (oxalate)	1.251	1.251	0.007	1.248	1.254	18	
	in carboxylic acids (X–COOH)							
	C*–**C**(=**O**)–OH	1.214	1.214	0.019	1.203	1.224	175	
	C=C–**C**(=**O**)–OH	1.229	1.226	0.017	1.218	1.237	22	
	C*ar*–**C**(=**O**)–OH	1.226	1.223	0.020	1.211	1.241	75	
	in esters:							
	C*–**C**(=**O**)–O–C*	1.196	1.196	0.010	1.190	1.202	551	12
	C=C–**C**(=**O**)–O–C*	1.199	1.198	0.009	1.193	1.203	113	
	C*ar*–**C**(=**O**)–O–C*	1.202	1.201	0.009	1.196	1.207	218	12
	C*–**C**(=**O**)–O–C=C	1.190	1.190	0.014	1.184	1.198	26	
	C*–**C**(=**O**)–O–C*ar*	1.187	1.188	0.011	1.181	1.195	40	12
	in anhydrides: **O**=**C**–O–**C**=**O**	1.187	1.187	0.010	1.184	1.193	70	
	in β-lactones: C*–**C**(=**O**)–O–C*	1.193	1.193	0.006	1.187	1.198	4	13
	γ-lactones: C*–**C**(=**O**)–O–C*	1.201	1.202	0.009	1.196	1.206	109	12
	δ-lactones: C*–**C**(=**O**)–O–C*	1.205	1.207	0.008	1.201	1.209	27	12
	in amides:							
	NH_2–**C**(–C*)=**O**	1.234	1.233	0.012	1.225	1.243	32	14
	(C*–)(C*,H–)N–**C**(–C*)=**O**	1.231	1.231	0.012	1.224	1.238	378	14
	β-lactams: C*–NH–**C**=**O**	1.198	1.200	0.012	1.193	1.204	23	13
	γ-lactams:							
	C*–NH–**C**=**O**	1.235	1.235	0.008	1.232	1.240	20	13
	C*–N(–C*)–C=O	1.225	1.226	0.011	1.217	1.233	15	13
	δ-lactams:							
	C*–NH–**C**=**O**	1.240	1.241	0.003	1.237	1.243	6	14
	C*–N(–C*)–**C**=**O**	1.233	1.233	0.007	1.229	1.239	15	14
	in ureas:							
	$(NH)_2)_2$–**C**=**O**	1.256	1.256	0.007	1.249	1.261	24	25,26
	$(C\#{-}NH)_2$–**C**=**O**	1.241	1.237	0.011	1.235	1.245	13	25
	$[(C\#)_n{-}N]_2$–**C**=**O**	1.230	1.230	0.007	1.224	1.234	20	25,27
Csp^3–P(4)	C_3–$\mathbf{P^+}$–**C***	1.800	1.802	0.015	1.790	1.812	35	33
	C_2–**P**(=O)–$\mathbf{CH_3}$	1.791	1.790	0.006	1.786	1.795	10	

Bond	Substructure	*d*	*m*	*σ*	q_1	q_u	*n*	Note
	C_2–**P**(=O)–**C**H_2–C	1.806	1.806	0.009	1.801	1.813	45	
	C_2–**P**(=O)–**C**H–C_2	1.821	1.821	0.009	1.815	1.828	15	
	C_2–**P**(=O)–**C**–C_3	1.841	1.842	0.008	1.835	1.847	14	
	C_2–**P**(=O)–**C*** (overall)	1.813	1.811	0.017	1.800	1.822	84	
C*sp*³–P(3)	C_2–**P**–**C***	1.855	1.857	0.019	1.840	1.870	23	
C*ar*–P(4)	C_3–**P**$^+$–**C***ar*	1.793	1.792	0.011	1.786	1.800	276	
	C_2–**P**(=O)–**C***ar*	1.801	1.802	0.011	1.796	1.807	98	
	Ph$_3$–**P**=N$^+$=**P**–**Ph**$_3$	1.795	1.795	0.008	1.789	1.800	197	
C*ar*–P(3)	C_2–**P**–**C***ar*	1.836	1.837	0.010	1.830	1.844	102	
	$(N\simeq)_2$P–**C***ar*(P ≃ N aromatic)	1.795	1.793	0.011	1.788	1.803	43	
C*sp*³–S(4)	**C***–**S**O_2–C (C* = CH_3 excluded)	1.786	1.782	0.018	1.774	1.797	75	
	C*–**S**O_2–C (overall)	1.779	1.778	0.020	1.764	1.790	94	
	C*–**S**O_2–O–X	1.745	1.744	0.009	1.738	1.754	7	34
	C*–**S**O_2–N–X_2	1.758	1.756	0.018	1.746	1.773	17	34
C*sp*³–S(3)	**C***–**S**(=O)–C (C* = CH_3 excluded)	1.818	1.814	0.024	1.802	1.829	69	
	C*–**S**(=O)–C (overall)	1.809	1.806	0.025	1.793	1.820	88	
	CH$_3$–**S**$^+$–X_2	1.786	1.787	0.007	1.779	1.792	21	
	C*–**S**$^+$–X_2 (C* = CH_3 excluded)	1.823	1.820	0.016	1.812	1.834	18	
	C*–**S**$^+$–X_2 (overall)	1.804	1.794	0.025	1.788	1.820	41	
C*sp*³–S(2)	**C***–**SH**	1.808	1.805	0.010	1.800	1.819	6	
	CH$_3$–**S**–C*	1.789	1.787	0.008	1.784	1.794	9	
C*sp*³–S(2)	C–**CH**$_2$–**S**–C*	1.817	1.816	0.013	1.808	1.824	92	
	C_2–**CH**–**S**–C*	1.819	1.819	0.011	1.811	1.825	32	
	C_3–**C**–**S**–C*	1.856	1.860	0.011	1.854	1.863	26	
	C*–**S**–**C*** (overall)	1.819	1.817	0.019	1.809	1.827	242	
	in thiirane	1.834	1.835	0.025	1.810	1.858	4	9
	in thiirane: see ZCMXSP (1.817, 1.844)							
	in tetrahydrothiophene	1.827	1.826	0.018	1.811	1.837	20	
	in tetrahydrothiopyran	1.823	1.821	0.014	1.812	1.832	24	
	C–**CH**$_2$–**S**–S–X	1.823	1.820	0.014	1.813	1.832	41	
	C_3–**C**–**S**–S–X	1.863	1.865	0.015	1.848	1.878	11	
	C*–**S**–**S**–X (overall)	1.833	1.828	0.022	1.818	1.848	59	
C*sp*²–S(2)	C=**C**–**S**–C*	1.751	1.755	0.017	1.740	1.764	61	
	C=**C**–**S**–C=C (in tetrathiafulvalene)	1.741	1.741	0.011	1.733	1.750	88	
	C=**C**–**S**–C=C (in thiophene)	1.712	1.712	0.013	1.703	1.722	60	
	O=**C**–**S**–C#	1.762	1.759	0.018	1.747	1.778	20	
C*ar*–S(4)	**C***ar*–**S**O_2–C	1.763	1.764	0.009	1.756	1.769	96	
	C*ar*–**S**O_2–O–X	1.752	1.750	0.008	1.749	1.756	27	
	C*ar*–**S**O_2–N–X_2	1.758	1.759	0.013	1.749	1.765	106	35
C*ar*–S(3)	**C***ar*–**S**(=O)–C	1.790	1.790	0.010	1.783	1.798	41	
	C*ar*–**S**$^+$–X_2	1.778	1.779	0.010	1.771	1.787	10	
C*ar*–S(2)	**C***ar*–**S**–C*	1.773	1.774	0.009	1.765	1.779	44	
	C*ar*–**S**–C*ar*	1.768	1.767	0.010	1.762	1.774	158	
	C*ar*–**S**–C*ar* (in phenothiazine)	1.764	1.764	0.008	1.760	1.769	48	
	C*ar*–**S**–S–X	1.777	1.777	0.012	1.767	1.785	47	
C*sp*¹–S(2)	N≡**C**–**S**–X	1.679	1.683	0.026	1.645	1.698	10	
C*sp*¹–S(1)	(N≡**C**–**S**)$^-$	1.630	1.630	0.014	1.619	1.641	14	
C*sp*²=S(1)	$(C^*)_2$–**C**=**S**: see IPMUDS (1.599)							
	$(Car)_2$–**C**=**S**: see CELDOM (1.611)							
	$(X)_2$–**C**=**S** (X = C,N,O,S)	1.671	1.675	0.024	1.656	1.689	245	
	X_2N–**C**(=**S**)–S–X	1.660	1.660	0.016	1.648	1.674	38	
	$(X_2N)_2$–**C**=**S** (thioureas)	1.681	1.684	0.020	1.669	1.693	96	
	N–**C**$(\simeq$**S**$)_2$	1.720	1.721	0.012	1.709	1.731	20	
C*sp*³–Se	**C#**–**Se**	1.970	1.967	0.032	1.948	1.998	21	
C*sp*²–Se(2)	C=**C**–**Se**–**C**=C (in tetraselenafulvalene)	1.893	1.895	0.013	1.882	1.902	32	
C*ar*–Se(3)	**Ph**$_3$–**Se**$^+$	1.930	1.929	0.006	1.924	1.936	13	
C*sp*³–Si(5)	**C#**–**Si**$^-$–X_4	1.874	1.876	0.015	1.859	1.884	9	
C*sp*³–Si(4)	**CH**$_3$–**Si**–X_3	1.857	1.857	0.018	1.848	1.869	552	
	C*–**Si**–X_3 (**C*** = CH_3 excluded)	1.888	1.887	0.023	1.872	1.905	124	
	C*–**Si**–X_3 (overall)	1.863	1.861	0.024	1.850	1.875	681	
C*ar*–Si(4)	**C***ar*–**Si**–X_3	1.868	1.868	0.014	1.857	1.878	178	

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
C*sp*¹–Si(4)	C≡**C**–**Si**–X_3	1.837	1.840	0.012	1.824	1.849	8	
C*sp*³–Te	**C#–Te**	2.158	2.159	0.030	2.128	2.177	13	
C*ar*–Te	C*ar*–**Te**	2.116	2.115	0.020	2.104	2.130	72	
C*sp*²=Te	see CEDCUJ (2.044)							
Cl–Cl	see PHASCL (2.306, 2.227)							
Cl–I	see CMBIDZ (2.563), HXPASC (2.541, 2.513), METAMM (2.552), BQUINI (2.416, 2.718)							
Cl–N	see BECTAE (1.743–1.757), BOGPOC (1.705)							
Cl–O(1)	in ClO^-_4	1.414	1.419	0.026	1.403	1.431	252	
Cl–P	$(N\simeq)_2$**P–Cl** (N ≃ P aromatic)	1.997	1.994	0.015	1.989	2.004	46	
	Cl–P (overall)	2.008	2.001	0.035	1.986	2.028	111	
Cl–S	**Cl–S** (overall)	2.072	2.079	0.023	2.047	2.091	6	
	see also longer bonds in CILSAR (2.283), BIHXIZ (2.357), CANLUY (2.749)							
Cl–Se	see BIRGUE10, BIRHAL10, CTCNSE (2.234–2.851)							
Cl–Si(4)	**Cl–Si**–X_3 (monochloro)	2.072	2.075	0.009	2.066	2.078	5	
	Cl$_2$–**Si**–X_2 and **Cl**$_3$–**Si**–X	2.020	2.012	0.015	2.007	2.036	5	
Cl–Te	Cl–Te in range 2.34–2.60	2.520	2.515	0.034	2.493	2.537	22	36
	see also longer bonds in BARRIV, BOJPUL, CETUTE, EPHTEA, OPNTEC10 (2.73–2.94)							
F–N(3)	**F–N**–C_2 and **F**$_2$–**N**–C	1.406	1.404	0.016	1.395	1.416	9	
F–P(6)	in hexafluorophosphate, PF^-_6	1.579	1.587	0.025	1.563	1.598	72	
F–P(3)	$(N\simeq)_2$**P–F**(N ≃ P aromatic)	1.495	1.497	0.016	1.481	1.510	10	
F–S	43 observations in range 1.409–1.770 in a wide variety of environments; F–S(6) in F_2–SO_2–C_2 (see FPSULF10, BETJOZ)	1.640	1.646	0.011	1.626	1.649	6	
	F–S(4) in **F**$_2$–**S**(=O)–N (see BUDTEZ)	1.527	1.528	0.004	1.524	1.530	24	37
F–Si(6)	in SiF^{2-}_6	1.694	1.701	0.013	1.677	1.703	6	
F–Si(5)	**F–Si**$^-$–X_4	1.636	1.639	0.035	1.602	1.657	10	
F–Si(4)	**F–Si**–X_3	1.588	1.587	0.014	1.581	1.599	24	
F–Te	see CUCPlZ (F–Te(6) = 1.942, 1.937), FPHTEL(F–Te(4) = 2.006)							
H–N(4)	X_3–**N**$^+$–**H**	1.033	1.036	0.022	1.026	1.045	87	21
H–N(3)	X_3–**N–H**	1.009	1.010	0.019	0.997	1.023	95	21
H–O(2)	in alcohols C*–**O–H**	0.967	0.969	0.010	0.959	0.974	63	21
	C#–**O–H**	0.967	0.970	0.010	0.959	0.974	73	21
	in acids O=C–**O–H**	1.015	1.017	0.017	1.001	1.031	16	21,38
I–I	in I^-_3	2.917	2.918	0.011	2.907	2.927	6	
I–N	see BZPRIB, CMBIDZ, HMTITI, HMTNTI, IFORAM, IODMAM (2.042–2.475)							
I–O	X–**I–O**(see BZPRIB, CAJMAB, IBZDAC11)	2.144	2.144	0.028	2.127	2.164	6	
	for IO^-_6 see BOVMEE (1.829–1.912)							
I–P(3)	see CEHKAB (2.490–2.493)							†
I–S	sec DTHIBR10 (2.687), ISUREA10 (2.629), BZTPPI (3.251)							
I–Te(4)	**I–Te**–X_3	2.926	2.928	0.026	2.902	2.944	8	
N(4)–N(3)	X_3–**N**$^+$–**N**^{0}–X_2 (N^0 planar)	1.414	1.414	0.005	1.412	1.418	13	
N(3)–N(3)	(C)(C,H)–**N**$_a$–**N**$_b$(C)(C,H)							5,39
	N$_a$, **N**$_b$ pyramidal	1.454	1.452	0.021	1.444	1.457	44	40
	N$_a$ pyramidal, N_b planar	1.420	1.420	0.015	1.407	1.433	68	40
	N$_a$, N_b planar	1.401	1.401	0.018	1.384	1.418	40	40
	overall	1.425	1.425	0.027	1.407	1.443	139	
N(3)–N(2)	in pyrazole (N1–N2)	1.366	1.366	0.019	1.350	1.375	20	
	in pyridaznium ($Nl^+\simeq$N2)	1.350	1.349	0.010	1.345	1.361	7	
N(2) ≃ N(2)	**N** ≃ **N** (aromatic) in pyridazine							
	with C,H as *ortho* substituents	1.304	1.300	0.019	1.287	1.326	6	
	with N,Cl as *ortho* substituents	1.368	1.373	0.011	1.362	1.375	9	

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
N(2)=N(2)	C#–**N**=**N**–C#							
	cis	1.245	1.244	0.009	1.239	1.252	21	
	trans	1.222	1.222	0.006	1.218	1.227	6	
	(overall)	1.240	1.241	0.012	1.230	1.251	27	
	C*ar*–**N**=**N**–C*ar*	1.255	1.253	0.016	1.247	1.262	13	
	X–**N**=**N**=**N** (azides)	1.216	1.226	0.028	1.202	1.237	19	
N(2)=N(1)	X–**N**=**N**=**N** (azides)	1.124	1.128	0.015	1.114	1.137	19	
N(3)–O(2)	$(C,H)_2$–**N**–**OH** (Nsp^2: planar)	1.396	1.394	0.012	1.390	1.401	28	
	C_2–**N**–**O**–C							
	(Nsp^3: pyramidal)	1.463	1.465	0.012	1.457	1.468	22	
	(Nsp^2: planar)	1.397	1.394	0.011	1.388	1.409	12	
	in furoxan (N2–O1)	1.438	1.436	0.009	1.430	1.447	14	
N(3)–O(1)	$(C{\simeq})_2$**N**$^+$–**O**$^-$ in pyridine *N*-oxides	1.304	1.299	0.015	1.291	1.316	11	
	in furoxan ($^+$N2–O6$^-$)	1.234	1.234	0.008	1.228	1.240	14	
N(2)–O(2)	in oximes							
	$(C\#)_2$–C=**N**–**OH**	1.416	1.418	0.006	1.416	1.420	7	
	(H)(Csp^2)–C=**N**–**OH**	1.390	1.390	0.011	1.380	1.401	20	
	(C#)(Csp^2)–C=**N**–**OH**	1.402	1.403	0.010	1.393	1.410	18	
	$(Csp^2)_2$–C=**N**–**OH**	1.378	1.377	0.017	1.365	1.393	16	
	$(C,H)_2$–C=**N**–**OH** (overall)	1.394	1.395	0.018	1.379	1.408	67	
	in furazan (O1–N2, O1–N5)	1.385	1.383	0.013	1.378	1.392	12	
	in furoxan (O1–N5)	1.380	1.380	0.011	1.370	1.388	14	
	in isoxazole (O1–N2)	1.425	1.425	0.010	1.417	1.434	9	
N(3)=O(1)	in nitrate ions $\mathbf{NO_3^-}$	1.239	1.240	0.020	1.227	1.251	105	
	in nitro groups							
	C*–$\mathbf{NO_2}$	1.212	1.214	0.012	1.206	1.221	84	
	C#–$\mathbf{NO_2}$	1.210	1.210	0.011	1.203	1.218	251	
	C*ar*–$\mathbf{NO_2}$	1.217	1.218	0.011	1.211	1.215	1116	
	C–$\mathbf{NO_2}$ (overall)	1.218	1.219	0.013	1.210	1.226	1733	
N(3)–P(4)	X_2–**P**(=X)–NX_2							
	Nsp^2: planar	1.652	1.651	0.024	1.634	1.670	205	
	Nsp^3: pyramidal	1.683	1.683	0.005	1.680	1.686	6	
	(overall)	1.662	1.662	0.029	1.639	1.682	358	
	subsets of this group are:							
	O_2–**P**(=S)–$\mathbf{NX_2}$	1.628	1.624	0.015	1.615	1.634	9	
	C–**P**(=S)–$(\mathbf{NX_2})_2$	1.691	1.694	0.018	1.678	1.703	28	
	O–**P**(=S)–$(\mathbf{NX_2})_2$	1.652	1.654	0.014	1.642	1.664	28	
	P(=O)–$(\mathbf{NX_2})_3$	1.663	1.668	0.026	1.640	1.679	78	
N(3)–P(3)	–**N**X–**P**(–X)–**N**X–**P**(–X)–(P_2N_2 ring)	1.730	1.721	0.017	1.716	1.748	20	
	–**N**X–**P**(=S)–**N**X–**P**(=S)–(P_2N_2 ring)	1.697	1.697	0.015	1.690	1.703	44	
	in P-substituted phosphazenes:							
	$(N{\simeq})_2$**P**–**N** (amino)	1.637	1.638	0.014	1.625	1.651	16	
	(aziridinyl)	1.672	1.674	0.010	1.665	1.676	15	
N(2)=P(4)	Ph_3–**P**=**N**$^+$=P–Ph_3	1.571	1.573	0.013	1.563	1.580	66	
N(2)=P(3)	Ph_3–**P**=**N**–C,S	1.599	1.597	0.018	1.580	1.615	7	
N(2) ≃ P(3)	**N** ≃ **P** aromatic							
	in phosphazenes	1.582	1.582	0.019	1.571	1.594	126	
	in P ≃ N ≃ S	1.604	1.606	0.009	1.594	1.612	36	
N(3)–S(4)	C–SO_2–$\mathbf{NH_2}$	1.600	1.601	0.012	1.591	1.610	14	35
	C–SO_2–**NH**–C#	1.633	1.633	0.019	1.615	1.652	47	35
	C–SO_2–**N**–$C(\#)_2$	1.642	1.641	0.024	1.623	1.659	38	35
N(3)–S(2)	C–S–$\mathbf{NX_2}$ Nsp^2: planar	1.710	1.707	0.019	1.698	1.722	22	23
	(for Nsp^3 pyramidal see MODIAZ: 1.765)							
	X–**S**–$\mathbf{N}X_2$ Nsp^2: planar	1.707	1.705	0.012	1.699	1.715	30	23
N(2)–S(2)	C=**N**–**S**–X	1.656	1.663	0.027	1.632	1.677	36	
N(2) ≃ S(2)	**N** ≃ **S** aromatic in **P** ≃ **N** ≃ **S**	1.560	1.558	0.011	1.554	1.563	37	
N(2)=S(2)	**N**=**S** in **N**=**S**=**N** and **N**=**S**=**S**	1.541	1.546	0.022	1.521	1.558	37	
N(3)–SE	see COJCUZ (1.830), DSEMOR10 (1.846, 1.852), MORTRS10 (1.841)							
N(2)–Se	see SEBZQI (1.805), NAPSEZ10 (1.809, 1.820)							
N(2)=Se	see CISMUM (1.790, 1.791)							

Bond	Substructure	*d*	*m*	*σ*	q_l	q_u	*n*	Note
N(3)–Si(5)	see DMESIP01, BOJLER, CASSAQ, CASYOK, CECXEN, CINTEY, CIPBUY, FMESIB, MNPSIL, PNPOSI (1.973–2.344)							
N(3)–Si(4)	X_3–**Si–N**X_2 (overall)	1.748	1.746	0.022	1.735	1.757	170	
	subsets of this group are:							
	X_3–**Si–N**HX	1.714	1.719	0.014	1.702	1.727	16	
	X_3–**Si–N**X–Si–X_3 acyclic	1.743	1.744	0.016	1.731	1.755	45	
	N–Si–N in 4-membered rings	1.742	1.742	0.009	1.735	1.748	53	
	N–Si–N in 5-membered rings	1.741	1.742	0.019	1.726	1.749	33	
N(2)–Si(4)	X_3–**Si–N**$^-$–Si–X_3	1.711	1.712	0.019	1.693	1.729	15	
N–Te	see ACLTEP (2.402), BIBLAZ (1.980), CESSAU (2.023)							
O(2)–O(2)	C*–**O–O**–C*,H							
	τ(OO) = 70–85°	1.464	1.464	0.009	1.458	1.472	12	
	τ(OO) *ca.* 180°	1.482	1.480	0.005	1.478	1.486	5	
	overall	1.469	1.471	0.012	1.461	1.478	17	
	O=C–**O–O**–C=O see ACBZPO01 (1.446), CEYLUN (1.452), CIMHIP (1.454)							
	Si–**O–O**–Si	1.496	1.499	0.005	1.490	1.499	10	
O(2)–P(5)	X–**P**–(**O**X)$_4$							41
	trigonal bipyramidal:							
	axial	1.689	1.685	0.024	1.675	1.712	20	
	equatorial	1.619	1.622	0.024	1.604	1.628	20	
	square pyramidal	1.662	1.661	0.020	1.649	1.673	28	
O(2)–P(4)	C–**O–P**(≃ O)$_3^{2-}$	1.621	1.622	0.007	1.615	1.628	12	
	(H–**O**)$_2$–**P**(≃ O)$_2^-$	1.560	1.561	0.009	1.555	1.566	16	
	(C–**O**)$_2$–**P**(≃ O)$_2^-$	1.608	1.607	0.013	1.599	1.615	16	
	(C#–**O**)$_3$–**P**=O	1.558	1.554	0.011	1.550	1.564	30	
	(C*ar*–**O**)$_3$–**P**=O	1.587	1.588	0.014	1.572	1.599	19	
	X–**O–P**(=O)–(C,N)$_2$	1.590	1.585	0.016	1.577	1.601	33	
	(X–**O**)$_2$–**P**(=O)–(C,N)	1.571	1.572	0.013	1.563	1.579	70	
O(2)–P(3)	(N≃)$_2$**P–O**–C (N ≃ P aromatic)	1.573	1.573	0.011	1.563	1.584	16	
O(1)=P(4)	C–O–**P**(≃ **O**)$_3^{2-}$ (delocalized)	1.513	1.512	0.008	1.508	1.518	42	
	(H–O)$_2$–**P**(≃ **O**)$_2^-$ (delocalized)	1.503	1.503	0.005	1.499	1.508	16	
	(C–O)$_2$–**P**(≃ **O**)$_2^-$ (delocalized)	1.483	1.485	0.008	1.474	1.490	16	
	(C–O)$_3$–**P=O**	1.449	1.448	0.007	1.446	1.452	18	
	C_3–**P=O**	1.489	1.486	0.010	1.481	1.496	72	
	N_3–**P=O**	1.461	1.462	0.014	1.449	1.470	26	
	(C)$_2$(N)–**P=O**	1.487	1.489	0.007	1.479	1.493	5	
	(C,N)$_2$(O)–**P=O**	1.467	1.462	0.007	1.462	1.472	33	
	(C,N)(O)$_2$–**P=O**	1.457	1.458	0.009	1.454	1.462	35	
O(2)–S(4)	C–**O–SO**$_2$–C	1.577	1.576	0.015	1.566	1.584	41	
	C–**O–SO**$_2$–CH_3	1.569	1.569	0.013	1.556	1.582	7	
	C–**O–SO**$_2$–C*ar*	1.580	1.578	0.015	1.571	1.588	27	
O(1)=S(4)	C–**SO**$_2$–C	1.436	1.437	0.010	1.431	1.442	316	42
	X–**SO**$_2$–NX_2	1.428	1.428	0.010	1.422	1.434	326	
	C–**SO**$_2$–N–(C,H)$_2$	1.430	1.430	0.009	1.425	1.435	206	
	C–**SO**$_2$–O–C	1.423	1.423	0.008	1.418	1.428	82	
	in **SO**$_4^{2-}$	1.472	1.473	0.013	1.463	1.481	104	
O(1)=S(3)	C–**S**(=**O**)–C	1.497	1.498	0.013	1.489	1.505	90	5
O–Se	see BAPPAJ, BIRGUE10, BIRHAL10, CXMSEO, DGLYSE, SPSEBU (1.597 for **O**=**Se** to 1.974 for **O–Se**)							
O(2)–Si(5)	(X–**O**)$_3$–**Si**–(N)(C)	1.663	1.658	0.023	1.650	1.665	21	
O(2)–Si(4)	X_3–**Si–O–X** (overall)	1.631	1.630	0.022	1.617	1.646	191	
O(2)–Si(4)	subsets of this group are:							
	X_3–**Si–O**–C#	1.645	1.647	0.012	1.634	1.652	29	
	X_3–**Si–O**–Si–X_3	1.622	1.625	0.014	1.614	1.631	70	
	X_3–**Si–O–O–Si**–X_3	1.680	1.676	0.008	1.673	1.688	10	
O(2)–Te(6)	(X–**O**)$_6$–**Te**	1.927	1.927	0.020	1.908	1.942	16	
O(2)–Te(4)	(X–**O**)$_2$–**Te**–X_2	2.133	2.136	0.054	2.078	2.177	12	
P(4)–P(4)	X_3–**P–P**–X_3	2.256	2.259	0.025	2.243	2.277	6	

Bond	Substructure	*d*	*m*	*σ*	q_1	q_u	*n*	Note
P(4)–P(3)	see CECHEX (2.197), COZPIQ (2.249)							
P(3)–P(3)	X_2–**P–P**–X_2	2.214	2.210	0.022	2.200	2.224	41	
P(4)=P(4)	see BUTSUE (2.054)							
P(3)=P(3)	see BALXOB (2.034)							
P(4)=S(1)	C_3–**P=S**	1.954	1.952	0.005	1.950	1.957	13	
	$(N,O)_2(C)$–**P=S**	1.922	1.924	0.014	1.913	1.927	26	
	$(N,O)_3$–**P=S**	1.913	1.914	0.014	1.906	1.921	50	
P(4)=Se(1)	X_3–**P=S**e	2.093	2.099	0.019	2.075	2.108	12	
P(3)–Si(4)	X_2–**P–Si**–X_3: 3- and 4-rings	2.264	2.260	0.019	2.249	2.283	22	
	excluded (see BOPFER, BOPFIV, CASTOF10, COZVIW: 2.201–2.317)							
P(4)=Te(1)	see MOPHTE (2.356), TTEBPZ (2.327)							
S(2)–S(2)	C–**S–S**–C							
	τ(SS) = 75–105°	2.031	2.029	0.015	2.021	2.038	46	
	τ(SS) = 0–20°	2.070	2.068	0.022	2.057	2.077	28	
	(overall)	2.048	2.045	0.026	2.028	2.068	99	
	in polysulphide chain–**S–S–S**–	2.051	2.050	0.022	2.037	2.065	126	
S(2)–S(1)	X–N=S–S	1.897	1.896	0.012	1.887	1.908	5	
S–Se(4)	see BUWZUO (2.264, 2.269)							
S–Se(2)	X–**Se–S** (any)	2.193	2.195	0.015	2.174	2.207	9	
S(2)–Si(4)	X_3–**Si**–S–X	2.145	2.138	0.020	2.130	2.158	19	
S(2)–Te	X–**S–Te** (any)	2.405	2.406	0.022	2.383	2.424	10	
	X=**S–Te** (any)	2.682	2.686	0.035	2.673	2.694	28	
Se(2)–Se(2)	X–**Se–Se**–X	2.340	2.340	0.024	2.315	2.361	15	
Se(2)–Te(2)	see BAWFUA, BAWGAH (2.524–2.561)							†
Si(4)–Si(4)	X_3–**Si–Si**–X_3 3–membered rings excluded: see CIHRAM (2.511)	2.359	2.359	0.012	2.349	2.366	42	
Te–Te	see CAHJOK (2.751, 2.704)							

Appendix 1. (Footnotes to Table)

1. Sample dominated by B–CH_3. For longer bonds in B^-–CH_3 see LITMEB10 [B(4)–CH_3 = 1.621–1.644Å].
2. p(π)–p(π) Bonding with B*sp*² and N*sp*² coplanar (τBN = 0 ± 15°) predominates. See G. Schmidt, R. Boese, and D. Bläser, *Z. Naturforsch.*, 1982, **37b**, 1230.
3. 84 observations range from 1.38 to 1.61 Å and individual values depend on substituents on B and O. For a discussion of borinic acid adducts see S. J. Rettig and J. Trotter, *Can. J. Chem.*, 1982, **60**, 2957.
4. See M. Kaftory in 'The Chemistry of Functional Groups. Supplement D: The Chemistry of Halides, Pseudohalides, and Azides', S. Patai and Z. Rappoport, Eds., Wiley: New York, 1983, Part 2, ch. 24.
5. Bonds which are endocyclic or exocyclic to any 3- or 4-membered rings have been omitted from all averages in this section.
6. The overall average given here is for C*sp*³–C*sp*³ bonds which carry only C or H substituents. The value cited reflects the relative abundance of each 'substitution' group. The 'mean of means' for the 9 subgroups is 1.538 (σ = 0.022) Å.
7. See F. H. Allen, (a) *Acta Crystallogr.*, 1980, **B36**, 81; (b) 1981, **B37**, 890.
8. See F. H. Allen, *Acta Crystallogr.*, 1984, **B40**, 64.
9. See F. H. Allen, *Tetrahedron*, 1982, **38**, 2843.
10. See F. H. Allen, *Tetrahedron*, 1982, **38**, 645.
11. Cyclopropanones and cyclobutanones excluded.
12. See W. B. Schweizer and J. D. Dunitz, *Helv. Chim. Acta*, 1982, **65**, 1547.
13. See L. Norskov-Lauritsen, H.-B. Bürgi, P. Hoffmann, and H. R. Schmidt, *Helv. Chim. Acta*, 1985, **68**, 76.
14. See P. Chakrabarti and J. D. Dunitz, *Helv. Chim. Acta,* 1982, **65**, 1555.
15. See J. L. Hencher in 'The Chemistry of the C≡C Triple Bond,' S. Patai, Ed., Wiley, New York, 1978, ch. 2.
16. Conjugated: torsion angle about central C–C single bond is 0 ± 20° (*cis*) or 180 ± 20° (*trans*).
17. Unconjugated: torsion angle about central C–C single bond is 20–160°.
18. Other conjugative substituents excluded.
19. TCNQ is tetracyanoquinodimethane.
20. No difference detected between C2 ≃ C3 and C3 ≃ C4 bonds.
21. Derived from neutron diffraction results only.
22. N*sp*³: pyramidal; mean valence angle at N is in range 108–114°.
23. N*sp*²: planar; mean valence angle at N is ≥ 117.5°.
24. Cyclic and acyclic peptides.
25. See R. H. Blessing, *J. Am. Chem. Soc.*, 1983, **105**, 2776.
26. See L. Lebioda, *Acta Crystallogr.*, 1980, **B36**, 271.
27. *n* = 3 or 4, *i.e.* tri- or tetra-substituted ureas.
28. Overall value also includes structures with mean valence angle at N in the range 115–118°.
29. See F. H. Allen and A. J. Kirby, *J. Am. Chem. Soc.*, 1984, **106**, 6197.
30. See A. J. Kirby, 'The Anomeric Effect and Related Stereoelectronic Effects at Oxygen,' Springer, Berlin, 1983.
31. See B. Fuchs, L. Schleifer, and E. Tartakovsky, *Nouv. J. Chim.*, 1984, **8**, 275.
32. See S. C. Nyburg and C. H. Faerman, *J. Mol. Struct.,* 1986, **140,** 347.
33. Sample dominated by P–CH_3 and P–CH_2–C.
34. Sample dominated by C* = methyl.
35. See A. Kalman, M. Czugler, and G. Argay, *Acta Crystallogr.*, 1981, **B37**, 868.
36. Bimodal distribution resolved into 22 'short' bonds and 5 longer outliers.
37. All 24 observations come from BUDTEZ.
38. 'Long' O–H bonds in centrosymmetric O---H---O H–bonded dimers are excluded.
39. N–N bond length also dependent on torsion angle about N–N bond and on nature of substituent C atoms; these effects are ignored here.
40. N pyramidal has average angle at N in range 100–113.5°; N planar has average angle of ≥ 117.5°.
41. See R. R. Holmes and J. A. Deiters, *J. Amer. Chem. Soc.*, 1977, **99**, 3318**.**
42. No detectable variation in S=O bond length with type of C-substituent**.**

Appendix 2

Short-form references to individual CSD entries cited by reference code in the Table. A full list of CSD bibliographic entries is given in SUP 56701.

ACBZPO01 *J. Am. Chem. Soc.,* 1975, **97,** 6729.
ACLTEP *J. Organomet. Chem.,* 1980, **184,** 417.
ASAZOC *Dokl. Akad. Nauk SSSR,* 1979, **249,** 120.
BALXOB *J. Am. Chem. Soc.,* 1981, **103,** 4587.
BAPPAJ *Inorg. Chem.,* 1981, **20,** 3071.
BARRIV *Acta Chem. Scand., Ser. A,* 1981, **35,** 443.
BAWFUA *Cryst. Struct. Commun.,* 1981, **10,** 1345.
BAWGAH *Cryst. Struct. Commun.,* 1981, **10,** 1353.
BECTAE *J. Org. Chem.,* 1981, **46,** 5048, 1981.
BELNIP *Z. Naturforsch., Teil B,* 1982, **37,** 299.
BEMLIO *Chem. Ber.,* 1982, **115,** 1126.
BEPZEB *Cryst. Struct. Commun.,* 1982, **11,** 175.
BETJOZ *J. Am. Chem. Soc.,* 1982, **104,** 1683.
BETUTE10 *Acta Chem. Scand., Ser. A,* 1976, **30,** 719.
BIBLAZ *Zh. Strukt. Khim.,* 1981, **22,** 118.
BICGEZ *Z. Anorg. Allg. Chem.,* 1982, **486,** 90.
BIHXIZ *J. Chem. Soc., Chem. Commun.,* 1982, 982.
BIRGUE10 *Z. Naturforsch., Teil B,* 1983, **38,** 20.
BIRHAL10 *Z. Naturforsch., Teil B,* 1982, **37,** 1410.
BIZJAV *J. Organomet. Chem.,* 1982, **238,** C1.
BOGPOC *Z. Naturforsch., Teil B,* 1982, **37,** 1402.
BOGSUL *Z. Naturforsch., Teil* B, 1982, **37,** 1230.
BOJLER *Z. Anorg. Allg. Chem.,* 1982, **493,** 53.
BOJPUL *Acta Chem. Scand., Ser. A,* 1982, **36,** 829.
BOPFER *Chem. Ber.,* 1983, **116,** 146.
BOPFIV *Chem. Ber.,* 1983, **116,** 146.
BOVMEE *Acta Crystallogr., Sect. B,* 1982, **38,** 1048.
BQUINI *Acta Crystallogr., Sect. B,* 1979, **35,** 1930.
BTUPTE *Acta Chem. Scand., Ser. A,* 1975, **29,** 738.
BUDTEZ *Z. Naturforsch., Teil B,* 1983, **38,** 454.
BUPSIB10 *Z. Anorg. Allg. Chem.,* 1981, **474,** 31.
BUSHAY *Z. Naturforsch., Teil. B,* 1983, **38,** 692.
BUTHAZ10 *Inorg. Chem.,* 1984, **23,** 2582.
BUTSUE *J. Chem. Soc., Chem. Commun.,* 1983, 862.
BUWZUO *Acta Chem. Scand., Ser A,* 1983, **37,** 219.
BZPRIB *Z. Naturforsch., Teil B,* 1981, **36,** 922.
BZTPPI *Inorg. Chem.,* 1978, **17,** 894.
CAHJOK *Inorg. Chem.,* 1983, **22,** 1809.
CAJMAB *Chem. Z,* 1983, **107,** 169.
CANLUY *Tetrahedron Lett.,* 1983, **24,** 4337.
CASSAQ *J. Struct. Chem.,* 1983, **2,** 101.
CASTOF10 *Acta Crystallogr., Sect. C,* 1984, **40,** 1879.
CASYOK *J. Struct. Chem.,* 1983, **2,** 107.
CECHEX *Z. Anorg. Allg. Chem.,* 1984, **508,** 61.
CECXEN *J. Struct. Chem.,* 1983, **2,** 207.
CEDCUJ *J. Org. Chem.,* 1983, **48,** 5149.
CEHKAB *Z. Naturforsch., Teil B,* 1984, **39,** 139.
CELDOM *Acta Crystallogr., Sect. C,* 1984, **40,** 556.
CESSAU *Acta Crystallogr., Sect. C,* 1984, **40,** 653.
CETTAW *Chem. Ber.,* 1984, **117,** 1089.
CETUTE *Acta Chem. Scand., Ser A,* 1975, **29,** 763.
CEYLUN *Izv. Akad. Nauk SSSR, Ser. Khim.,* 1983, 2744.
CIFZUM *Acta Chem. Scand., Ser A,* 1984, **38,** 289.
CIHRAM *Angew. Chem., Int. Ed. Engl.,* 1984, **23,** 302.
CILRUK *J. Chem. Soc., Chem. Commun.,* 1984, 1023.
CILSAR *J. Chem. Soc., Chem. Commun.,* 1984, 1021.
CIMHIP *Acta Crystallogr., C,* 1984, **40,** 1458.
CINTEY *Dokl. Akad. Nauk SSSR,* 1984, **274,** 615.
CIPBUY *J. Struct. Chem.,* 1983, **2,** 281.
CISMUM *Z. Naturforsch., Teil B,* 1984, **39,** 485.
CISTED *Z. Anorg. Allg. Chem.,* 1984, **511,** 95.
CIWYIQ *Inorg. Chem.,* 1984, **23,** 1946.
CIYFOF *Inorg. Chem.,* 1984, **23,** 1790.
CMBIDZ *J. Org. Chem.,* 1979, **44,** 1447.
CODDEE *Z. Naturforsch., Teil B,* 1984, **39,** 1257.
CODDII *Z. Naturforsch., Teil B,* 1984, **39,** 1257.
COFVOI *Z. Naturforsch., Teil B,* 1984, **39,** 1027.
COJCUZ *Chem. Ber.,* 1984, **117,** 2686.
COSDIX *Z. Naturforsch., Teil B,* 1984, **39,** 1344.
COZPIQ *Chem. Ber.,* 1984, **117,** 2063.
COZVIW *Z. Anorg. Allg. Chem.,* 1984, **515,** 7.
CTCNSE *J. Am. Chem. Soc.,* 1980, **102,** 5430.
CUCPIZ *J. Am. Chem. Soc.,* 1984, **106,** 7529.
CUDLOC *J. Cryst. Spectrosc.,* 1985, **15,** 53.
CUDLUI *J. Cryst. Spectrosc.,* 1985, **15,** 53.
CUGBAH *Acta Crystallogr., Sect. C,* 1985, **41,** 476.
CXMSEO *Acta Crystallogr., Sect. B,* 1973, **29,** 595.
DGLYSE *Acta Crystallogr., Sect. B,* 1975, **31,** 1785.
DMESIP01 *Acta Crystallogr., Sect. C,* 1984, **40,** 895.
DSEMOR10 *J. Chem. Soc., Dalton Trans.,* 1980, 628.
DTHIBR10 *Inorg. Chem.,* 1971, **10,** 697.
EPHTEA *Inorg. Chem.,* 1980, **19,** 2487.
ESEARS *J. Chem. Soc. C,* 1971, 1511.
ETEARS *J. Chem. Soc. C,* 1971, 1511.
FMESIB *J. Organomet. Chem.,* 1980, **197,** 275.
FPHTEL *J. Chem. Soc., Dalton Trans.,* 1980, 2306.
FPSULF10 *J. Am. Chem. Soc.,* 1982, **104,** 1683.
HCLENE10 *Acta Crystallogr., Sect. B,* 1982, **38,** 3139.
HMTITI *Acta Crystallogr., Sect. B,* 1975, **31,** 1505.
HMTNTI *Z. Anorg. Allg. Chem.,* 1974, **409,** 237.
HXPASC *J. Chem. Soc., Dalton Trans.,* 1975, 1381.
IBZDAC11 *J. Chem. Soc., Dalton Trans.,* 1979, 854.
IFORAM *Monatsh. Chem.,* 1974, **105,** 621.
IODMAM *Acta Crystallogr., Sect. B,* 1977, **33,** 3209.
IPMUDS *Acta Crystallogr., Sect. B,* 1973, **29,** 2128.
ISUREA10 *Acta Crystallogr., Sect. B,* 1972, **28,** 643.
LITMEB10 *J. Am. Chem. Soc.,* 1975, **97,** 6401.
MESIAD *Z. Naturforsch., Teil B,* 1980, **35,** 789.
METAMM *Acta Crystallogr.,* 1964, **17,** 1336.
MNPSIL *J. Am. Chem. Soc.,* 1969, **91,** 4134.
MODIAZ *J. Heterocycl. Chem.,* 1980, **17,** 1217.
MOPHTE *Acta Chem. Scand., Ser. A,* 1980, **34,** 333.
MORTRS10 *J. Chem. Soc., Dalton Trans.,* 1980, 628.
NAPSEZ10 *J. Am. Chem. Soc.,* 1980, **102,** 5070.
NBBZAM *Z. Naturforsch., Teil B,* 1977, **32,** 1416.
OPIMAS *Aust. J. Chem.,* 1977, **30,** 2417.
OPNTEC10 *J. Chem. Soc., Dalton Trans.,* 1982, 251.
PHASCL *Acta Crystallogr., Sect. B,* 1981, **37,** 1357.
PHASOC01 *Aust. J. Chem.,* 1975, **28,** 15.
PNPOSI *J. Am. Chem. Soc.,* 1968, **90,** 5102.
SEBZQI *J. Chem. Soc., Chem. Commun.,* 1977, 325.
SPSEBU *Acta Chem. Scand., Ser. A,* 1979, **33,** 403.
TEACBR *Cryst. Struct. Commun.,* 1974, **3,** 753.
THINBR *J. Am. Chem. Soc.,* 1970, **92,** 4002.
TMPBTI *Acta Crystallogr., Sect. B,* 1975, **31,** 1116.
TPASSN *J. Chem. Soc., Dalton Trans.,* 1977, 514.
TPASTB *Cryst. Struct. Commun.,* 1976, **5,** 39.
TPHOSI *Z. Naturforsch., Teil B,* 1979, **34,** 1064.
TTEBPZ *Z. Naturforsch., Teil B,* 1979, **34,** 256.
ZCMXSP *Cryst. Struct. Commun.,* 1977, **6,** 93.

BOND LENGTHS AND ANGLES IN GAS-PHASE MOLECULES

This table is reprinted from *Kagaku Benran, 3rd Edition*, Vol. II, pp. 649–661 (1984), with permission of the publisher, Maruzen Company, LTD. (Copyright 1984 by the Chemical Society of Japan). Translation was carried out by Kozo Kuchitsu.

Internuclear distances and bond angles are represented in units of Å (1 Å = 10^{-10} m) and degrees, respectively. The same but inequivalent atoms are discriminated by subscripts a, b, etc. In some molecules ax for axial and eq for equatorial are also used. All measurements were made in the gas phase. The methods used are abbreviated as follows. UV: ultraviolet (including visible) spectroscopy; IR: infrared spectroscopy; R: Raman spectroscopy; MW: microwave spectroscopy; ED: electron diffraction; NMR: nuclear magnetic resonance; LMR: laser magnetic resonance; EPR: electron paramagnetic resonance; MBE: molecular beam electric resonance. If two methods were used jointly for structure determination, they are listed together, as (ED, MW). If the numerical values listed refer to the equilibrium values, they are specified by r_e and θ_e. In other cases the listed values represent various average values in vibrational states; it is frequently the case that they represent the r_s structure derived from several isotopic species for MW or the r_g structure (i.e., the average internuclear distances at thermal equilibrium) for ED. These internuclear distances for the same atom pair with different definitions may sometimes differ as much as 0.01 Å. Appropriate comments are made on the symmetry and conformation in the equilibrium structure.

In general, the numerical values listed in the following tables contain uncertainties in the last digits. However, for certain molecules such as diatomic molecules, with experimental uncertainties of the order of 10^{-5} Å or smaller, numerical values are listed to four decimal places.




References


1. L. E. Sutton, Ed., *Tables of Interatomic Distances and Configuration in Molecules and Ions,* The Chemical Society Special Publication, No. 11, 18, The Chemical Society (London) (1958, 1965).
2. K.-H. Hellwege, Ed., *Landolt-Börnstein Numerical Data and Functional Relations in Science and Technology,* New Series, II/7, J. H. Callomon, E. Hirota, K. Kuchitsu, W. J. Lafferty, A. G. Maki, C. S. Pote, with assistance of I. Buck and B. Starck, *Structure Data of Free Polyatomic Molecules*, Springer-Verlag (1976).
3. K. P. Huber and G. Herzberg, *Molecular Spectra and Molecular Structure IV. Constants of Diatomic Molecules,* Van Nostrand Reinhold Co., London (1979).
4. B. Starck, *Microwave Catalogue and Supplements.*
5. B. Starck, *Electron Diffraction Catalogue and Supplements.*


STRUCTURES OF ELEMENTS AND INORGANIC COMPOUNDS



Compounds are arranged in alphabetical order by their chemical formulas



(Lengths in Å and Angles in Degrees)




Compound	Structure					Method
AgBr	Ag—Br (r_e)	2.3931				MW
AgCl	Ag—Cl (r_e)	2.2808				MW
AgF	Ag—F (r_e)	1.9832				MW
AgH	Ag—H (r_e)	1.617				UV
AgI	Ag—I (r_e)	2.5446				MW
AgO	Ag—O (r_e)	2.0030				UV
AlBr	Al—Br (r_e)	2.295				UV
AlCl	Al—Cl (r_e)	2.1301				MW
AlF	Al—F (r_e)	1.6544				MW
AlH	Al—H (r_e)	1.6482				UV
AlI	Al—I (r_e)	2.5371				MW
AlO	Al—O (r_e)	1.6176				UV
Al_2Br_6				$Al—Br_a$	2.22	ED
				$Al—Br_b$	2.38	
				$\angle Br_bAlBr_b$	82	
				$\angle Br_aAlBr_a$	118	
				(D_{2h})		
Al_2Cl_6				$Al—Cl_a$	2.04	ED
				$Al—Cl_b$	2.24	
				$\angle Cl_bAlCl_b$	87	
				$\angle Cl_aAlCl_a$	122	
				(D_{2h})		
$AsBr_3$	As—Br	2.324		$\angle BrAsBr$	99.6	ED
$AsCl_3$	As—Cl	2.165		$\angle ClAsCl$	98.6	ED, MW
AsF_3	As—F	1.710		$\angle FAsF$	95.9	ED, MW
AsF_5		$As—F_a$	1.711	$As—F_b$	1.656	
				(D_{3h})		



Compound	Structure							Method
AsH_3	As—H (r_e)		1.511			∠HAsH (θ_e)	92.1	MW, IR
AsI_3	As—I		2.557			∠IAsI	100.2	ED
AuH	Au—H (r_e)		1.5237					UV
BBr_3	B—Br		1.893			(D_{3h})		ED
BCl_3	B—Cl		1.742			(D_{3h})		ED
BF	B—F (r_e)		1.2626					UV
BF_2H	B—H	1.189		B—F	1.311	∠FBF	118.3	MW
BF_2OH	B—F	1.32		B—O	1.34	O—H	0.941	MW
	∠FBF	118		∠FBO	123	∠BOH	114.1	
BF_3	B—F		1.313			(D_{3h})		ED, IR
BH	B—H (r_e)		1.2325					UV
BH_3PH_3	B—P	1.937		B—H	1.212	P—H	1.399	MW
	∠PBH	103.6		∠BPH	116.9	∠HBH	114.6	
	∠HPH	101.3		staggered form				
BI_3	B—I		2.118			(D_{3h})		ED
BN	B—N (r_e)		1.281					UV
BO	B—O (r_e)		1.2045					EPR
BO_2	B—O		1.265			linear		UV
BS	B—S		1.6091					UV
B_2H_6						B—H_a	1.19	IR, ED
						B—H_b	1.33	
						B···B	1.77	
						∠H_aBH_a	122	
						∠H_bBH_b	97	
$B_3H_3O_3$	B—O		1.376			∠BOB≅∠OBO	120	ED
$B_3H_6N_3$	B—N	1.435		B—H	1.26	N—H	1.05	ED
	∠NBN	118		∠BNB	121	(C_2)		
BaH	Ba—H (r_e)		2.2318					UV
BaO	Ba—O (r_e)		1.9397					MW
BaS	Ba—S (r_e)		2.5074					MBE
BeF	Be—F (r_e)		1.3609					UV
BeH	Be—H (r_e)		1.3431					UV
BeO	Be—O (r_e)		1.3308					UV
BiBr	Bi—Br (r_e)		2.6095					MW
$BiBr_3$	Bi—Br		2.63			∠BrBiBr	90	(C_{3v}) ED
BiCl	Bi—Cl (r_e)		2.4716					MW
$BiCl_3$	Bi—Cl		2.423			∠ClBiCl	100	(C_{3v}) ED
BiF	Bi—F (r_e)		2.0516					MW
BiH	Bi—H (r_e)		1.805					UV
BiI	Bi—I (r_e)		2.8005					MW
BiO	Bi—O (r_e)		1.934					UV
BrCN	C—N (r_e)		1.157			C—Br (r_e)	1.790	IR
BrCl	Br—Cl (r_e)		2.1361					MW
BrF	Br—F (r_e)		1.7590					MW
BrF_3	F_a—Br—F_a (with F_b below Br)			Br—F_a	1.810		Br—F_b 1.721	MW
				∠F_aBrF_b	86.2		(C_{2v})	
BrF_5	Br—F (average)		1.753					ED, MW
	(Br—F_{eq}) – (Br—F_{ax}) = 0.069							
	∠$F_{ax}BrF_{eq}$		85.1			(C_{4v})		
BrO	Br—O (r_e)		1.7172					MW
Br_2	Br—Br (r_e)		2.2811					R
CBr_4	C—Br		1.935			(T_d)		ED
CCl	C—Cl		1.6512					UV
$CClF_3$	C—Cl	1.752		C—F	1.325	∠FCF	108.6	ED, MW
CCl_3F	C—Cl	1.754		C—F	1.362	∠ClCCl	111	MW
						(C_{3v})		
CCl_4	C—Cl		1.767			(T_d)		ED
CF	C—F (r_e)		1.2718					EPR
CF_3I	C—I	2.138		C—F	1.330	∠FCF	108.1	ED, MW
CF_4	C—F		1.323			(T_d)		ED


Compound	Structure							Method
CH	C—H (r_e)	1.1199						UV
CI_4	C—I	2.15			(T_d)			ED
CN	C—N (r_e)	1.1718						MW
CO	C—O (r_e)	1.1283						MW
$COBr_2$	C—O	1.178			C—Br	1.923		ED, MW
	∠BrCBr	112.3						
COClF	C—F	1.334	C—O	1.173		C—Cl	1.725	ED, MW
	∠FCCl	108.8	∠ClCO	127.5				
$COCl_2$	C—O	1.179			C—Cl	1.742		ED, MW
	∠ClCCl	111.8						
COF_2	C—F	1.3157			C—O	1.172		ED, MW
	∠FCF	107.71						
CO_2	C—O (r_e)	1.1600						IR
CP	C—P (r_e)	1.562						UV
CS	C—S (r_e)	1.5349						MW
CS_2	C—S (r_e)	1.5526						IR
C_2	C—C (r_e)	1.2425						UV
C_3O_2	C—O	1.163			C—C	1.289		ED
	linear (large-amplitude bending vibration)							
CaH	Ca—H (r_e)	2.002						UV
CaO	Ca—O (r_e)	1.8221						UV
CaS	Ca—S (r_e)	2.3178						UV
CdH	Cd—H (r_e)	1.781						EPR
$CdBr_2$	Cd—Br	2.35			linear			ED
$CdCl_2$	Cd—Cl	2.24			linear			ED
CdI_2	Cd—I	2.56			linear			ED
ClCN	C—Cl (r_e)	1.629			C—N (r_e)	1.160		MW
ClF	Cl—F (r_e)	1.6283						MW
ClF_3	F_a—Cl(—F_a)—F_b		Cl—F_a	1.698		Cl—F_b	1.598	MW
			∠F_aClF_b	87.5		(C_{2v})		
ClO	Cl—O (r_e)	1.5696						MW, UV
ClOH	O—Cl	1.690	O—H	0.975		∠HOCl	102.5	MW, IR
ClO_2	Cl—O	1.470			∠OClO	117.38		MW
$ClO_3(OH)$	O_a—Cl	1.407			O_b—Cl	1.639		ED
			∠O_aClO_a		114.3	∠O_aClO_b	104.1	
Cl_2	Cl—Cl (r_e)	1.9878						UV
Cl_2O	Cl—O	1.6959			∠ClOCl	110.89		MW
CoH	Co—H (r_e)	1.542						UV
Cr $(CO)_6$	C—O	1.16			Cr—C	1.92		ED
	∠CrCO	180						
CrO	Cr—O (r_e)	1.615						UV
CsBr	Cs—Br (r_e)	3.0723						MW
CsCl	Cs—Cl (r_e)	2.9063						MW
CsF	Cs—F (r_e)	2.3454						MW
CsH	Cs—H (r_e)	2.4938						UV
CsI	Cs—I (r_e)	3.3152						MW
CsOH	Cs—O (r_e)	2.395			O—H (r_e)		0.97	MW
CuBr	Cu—Br (r_e)	2.1734						MW
CuCl	Cu—Cl (r_e)	2.0512						MW
CuF	Cu—F (r_e)	1.7449						MW
CuH	Cu—H (r_e)	1.4626						UV
CuI	Cu—I (r_e)	2.3383						MW
FCN	C—F	1.262			C—N	1.159		MW
FOH	O—H	0.96	O—F	1.442		∠HOF	97.2	MW
F_2	F—F (r_e)	1.4119						R


Compound	Structure							Method
$Fe(CO)_5$	Fe—C (average)		1.821					ED
	$(Fe—C)_{eq} - (Fe—C)_{ax}$		0.020					
	C—O (average)		1.153			(D_{3h})		
GaBr	Ga—Br (r_e)		2.3525					MW
GaCl	Ga—Cl (r_e)		2.2017					MW
GaF	Ga—F (r_e)		1.7744					MW
GaF_3	Ga—F		1.88			(D_{3h})		ED
GaI	Ga—I (r_e)		2.5747					MW
GaI_3	Ga—I		2.458			(D_{3h})		ED
GdI_3	Gd—I		2.841			∠IGdI	108 (C_{3v})	ED
$GeBrH_3$	Ge—H		1.526			Ge—Br	2.299	MW, IR
	∠HGeH		106.2					
$GeBr_4$	Ge—Br		2.272			(T_d)		ED
$GeClH_3$	Ge—H		1.537			Ge—Cl	2.150	IR, MW
	∠HGeH		111.0					
$GeCl_2$	Ge—Cl		2.183			∠ClGeCl	100.3	ED
$GeCl_4$	Ge—Cl		2.113			(T_d)		ED
$GeFH_3$	Ge—H		1.522			Ge—F	1.732	MW, IR
	∠HGeH		113.0					
GeF_2	Ge—F (r_e)		1.7321			∠FGeF (θ_e)	97.17	MW
GeH	Ge—H (r_e)		1.5880					UV
GeH_4	Ge—H		1.5251			(T_d)		IR, R
GeO	Ge—O (r_e)		1.6246					MW
GeS	Ge—S (r_e)		2.0121					MW
GeSe	Ge—Se (r_e)		2.1346					MW
GeTe	Ge—Te (r_e)		2.3402					MW
Ge_2H_6	Ge—H		1.541			Ge—Ge	2.403	ED
	∠HGeH		106.4			∠GeGeH	112.5	
HBr	H—Br (r_e)		1.4145					MW
HCN	C—H (r_e)		1.0655			C—N (r_e) linear	1.1532	MW, IR
HCNO	H—C	1.027		C—N	1.161	N—O linear	1.207	MW
HCl	H—Cl (r_e)		1.2746					MW
HF	H—F (r_e)		0.9169					MW
HI	H—I (r_e)		1.6090					MW
HNCO	N—H	0.986		N—C	1.209	C—O	1.166	MW
	∠HNC	128.0						
HNCS	N—H	0.989		N—C	1.216	C—S	1.561	MW
	∠HNC	135.0		∠NCS	180			
HNO	N—H	1.063		N—O	1.212	∠HNO	108.6	UV
HNO_2				*s-trans* conformer		*s-cis* conformer		MW
				O_b—H	0.958	0.98		
				N—O_b	1.432	1.39		
				N—O_a	1.170	1.19		
				∠O_aNO_b	110.7	114		
				∠NO_bH	102.1	104		
HNO_3				O_c—H	0.96	N—O_c	1.41	MW
				N—O_a	1.20	N—O_b	1.21	
				∠HO_cN	102.2	∠O_cNO_a	113.9	
				∠O_cNO_b	115.9	planar		
HNSO	N—H	1.029		N—S	1.512	S—O	1.451	MW
	∠HNS	115.8		∠NSO planar	120.4			
H_2	H—H (r_e)		0.7414					UV
H_2O	O—H (r_e)		0.9575			∠HOH (θ_e)	104.51	MW, IR
H_2O_2	O—O		1.475			∠OOH	94.8	IR
	dihedral angle of internal rotation					119.8	(C_2)	
H_2S	H—S (r_e)		1.3356			∠HSH (θ_e)	92.12	MW, IR

Compound	Structure							Method
H_2SO_4			O—H	0.97	S—O_a	1.574		MW
			S—O_c	1.422	∠H_aO_aS	108.5		
			∠O_aSO_b	101.3	∠O_cSO_d	123.3		
			∠O_aSO_c	108.6	∠O_aSO_d	106.4		
		dihedral angle between the H_aO_aS and O_aSO_c planes				20.8		
		dihedral angle between the H_aO_aS and O_aSO_b planes				90.9		
		dihedral angle between the H_aSO_b and O_cSO_d planes				88.4	(C_2)	
H_2S_2	S—S	2.055	S—H	1.327	∠SSH	91.3		ED, MW
	dihedral angle of internal rotation		90.6	(C_2)				
$HfCl_4$	Hf—Cl	2.33		(T_d)				ED
$HgCl_2$	Hg—Cl	2.252		linear				ED
HgH	Hg—H (r_e)	1.7404						UV
HgI_2	Hg—I	2.553		linear				ED
IBr	I—Br (r_e)	2.4691						MW
ICN	C—I	1.995		C—N	1.159			MW
ICl	I—Cl (r_e)	2.3210						MW
IF_5	I—F (average)	1.860		$(I—F)_{eq} - (I—F)_{ax}$	0.03			ED, MW
	∠$F_{ax}IF_{eq}$	82.1	(C_{4v})					
IO	I—O (r_e)	1.8676						MW
I_2	I—I (r_e)	2.6663						R
InBr	In—Br (r_e)	2.5432						MW
InCl	In—Cl (r_e)	2.4012						MW
InF	In—F (r_e)	1.9854						MW
InH	In—H (r_e)	1.8376						UV
InI	In—I (r_e)	2.7537						MW
IrF_6	Ir—F	1.830		(O_h)				ED
KBr	K—Br (r_e)	2.8208						MW
KCl	K—Cl (r_e)	2.6667						MW
KF	K—F (r_e)	2.1716						MW
KH	K—H (r_e)	2.244						UV
KI	K—I (r_e)	3.0478						MW
KOH	O—H	0.91		K—O	2.212 linear			MW
K_2	K—K (r_e)	3.9051						UV
KrF_2	Kr—F	1.89		linear				ED
LiBr	Li—Br (r_e)	2.1704						MW
LiCl	Li—Cl (r_e)	2.0207						MW
LiF	Li—F (r_e)	1.5639						MW
LiH	Li—H (r_e)	1.5949						MW
LiI	Li—I (r_e)	2.3919						MW
Li_2	Li—Li (r_e)	2.6729						UV
Li_2Cl_2				Li—Cl	2.23			ED
				Cl—Cl	3.61			
				∠ClLiCl	108			
$LuCl_3$	Lu—Cl	2.417		∠ClLuCl	112		(C_{3v})	ED
MgF	Mg—F (r_e)	1.7500						UV
MgH	Mg—H (r_e)	1.7297						UV
MgO	Mg—O (r_e)	1.749						UV
MnH	Mn—H (r_e)	1.7308						UV
$Mo(CO)_6$	Mo—C	2.063	C—O	1.145	(O_h)			ED
$MoCl_4O$	Mo—Cl	2.279		Mo—O	1.658			ED
	∠ClMoCl	87.2		(C_{4v})				
MoF_6	Mo—F	1.820		(O_h)				ED
$NClH_2$	N—H	1.017		N—Cl	1.748			MW, IR
	∠HNCl	103.7		∠HNH	107			
NCl_3	N—Cl	1.759		∠ClNCl	107.1			ED
NF_2	N—F	1.3528		∠FNF	103.18			MW
NH_2	N—H	1.024		∠HNH	103.3			UV
NH_2CN	N—H	1.00		N_a—C	1.35			MW

Compound	Structure						Method
		C—N_b	1.160	∠HNH	114		
		angle between the NH_2 plane and the N—C bond			142		
NH_2NO_2	N—N	1.427		N—H	1.005		MW
	∠HNH	115.2		∠ONO	130.1		
	dihedral angle between the NH_2 and NNO_2 planes				128.2		
NH_3	N—H (r_e)	1.012		∠HNH (θ_e)	106.7		IR
NH_4Cl	N—H	1.22	N—Cl	2.54	(C_{3v})		ED
NF_2CN	F_2N_b—C≡N_a		C—N_a	1.158	C—N_b	1.386	MW
	N_b—F	1.399	∠N_aCN_b	174			
	∠CN_bF	105.4	∠FN_bF	102.8			
NH	N—H (r_e)	1.0362					LMR
NH_2OH	N—H	1.02	N—O	1.453	O—H	0.962	MW
	∠HNH	107	∠HNO	103.3	∠NOH	101.4	
	The bisector of H—N—H angle is *trans* to the O—H bond						
NO	N—O (r_e)	1.1506					IR
NOCl	N—Cl	1.975	N—O	1.14	∠ONCl	113	MW
NOF	O—N	1.136	N—F	1.512	∠FNO	110.1	MW
NO_2	N—O	1.193		∠ONO	134.1		MW
NO_2Cl	N—Cl	1.840		N—O	1.202		MW
	∠ONO	130.6		(C_{2v})			
NO_2F	N—O	1.1798		N—F	1.467		MW
	∠ONO	136		(C_{2v})			
NS	N—S (r_e)	1.4940					IR
N_2	N—N (r_e)	1.0977					UV
N_2H_4	N—H	1.021		N—N	1.449		ED, MW
	∠HNH	106.6 (assumed)		∠NNH_a	112		
	∠NNH_b	106	dihedral angle of internal rotation		91		
	H_a: the H atom closer to the C_2 axis, H_b: the H atom farther from the C_2 axis						
N_2O	N—N (r_e)	1.1284		N—O (r_e)	1.1841		MW, IR
N_2O_3		N_a—N_b	1.864	N_a—O_a	1.142		MW
		N_b—O_b	1.202	N_b—O_c	1.217		
		∠$O_aN_aN_b$	105.05				
		∠$N_aN_bO_b$	112.72				
		∠$N_aN_bO_c$	117.47				
N_2O_4		N—N	1.782	N—O	1.190		ED
		∠ONO	135.4	(D_{2h})			
NaBr	Na—Br (r_e)	2.5020					MW
NaCl	Na—Cl (r_e)	2.3609					MW
NaF	Na—F (r_e)	1.9260					MW
NaH	Na—H (r_e)	1.8873					UV
NaI	Na—I (r_e)	2.7115					MW
Na_2	Na—Na (r_e)	3.0789					UV
$NbCl_5$	Nb—Cl_{eq}	2.241	Nb—Cl_{ax}	2.338 (D_{3h})	ED		
NbO	Nb—O (r_e)	1.691					UV
$Ni(CO)_4$	Ni—C	1.838	C—O	1.141	(T_d)		ED
NiH	Ni—H (r_e)	1.476					UV
NpF_6	Np—F	1.981		(O_h)			ED
OCS	C—O (r_e)	1.1578		C—S (r_e)	1.5601		MW
OCSe	C—O	1.159		C—Se	1.709		MW
OF	O—F (r_e)	1.3579					LMR
OF_2	O—F (r_e)	1.4053		∠FOF (θ_e)	103.07	(C_{2v})	MW
$O(SiH_3)_2$	Si—H	1.486		Si—O	1.634		ED
	∠SiOSi	144.1					
O_2	O—O (r_e)	1.2074					MW
O_2F_2	O—O	1.217		F—O	1.575		MW
	∠OOF	109.5	dihedral angle of internal rotation		87.5	(C_2)	






Compound	Structure							Method
O_3	O—O (r_e)		1.2716			∠OOO (θ_e)	117.47 (C_{2v})	MW
OsF_6	Os—F		1.831			(O_h)		ED
OsO_4	Os—O		1.712			(T_d)		ED
PBr_3	P—Br		2.220			∠BrPBr	101.0	ED
PCl_3	P—Cl		2.039			∠ClPCl	100.27	ED
PCl_5				$P—Cl_a$	2.124		$P—Cl_b$ 2.020 (D_{3h})	ED
PF	P—F (r_e)		1.5896					UV
PF_3	P—F		1.570			∠FPF	97.8	ED, MW
PF_5	$P—F_{ax}$	1.577		$P—F_{eq}$	1.534		(D_{3h})	ED
PH	P—H (r_e)		1.4223					LMR
PH_2	P—H		1.418			∠HPH	91.70	UV
PH_3	P—H		1.4200			∠HPH	93.345	MW
PN	N—P (r_e)		1.4909					MW
PO	O—P (r_e)		1.4759					UV
$POCl_3$	P—O		1.449			P—Cl	1.993	ED
	∠ClPCl		103.3					
POF_3	P—O	1.436		P—F	1.524		∠FPF 101.3	ED, MW
P_2	P—P (r_e)		1.8931					UV
P_2F_4	P—F		1.587			P—P	2.281	ED
	∠PPF		95.4			∠FPF	99.1	
	The two PF_2 planes are *trans* to each other (the *gauche* conformer is less than 10%)							
P_4	P—P		2.21			(T_d)		ED
P_4O_6	P—O	1.638		∠POP	126.4		(T_d)	ED
PbH	Pb—H (r_e)		1.839					UV
PbO	Pb—O (r_e)		1.9218					MW
PbS	Pb—S (r_e)		2.2869					MW
PbSe	Pb—Se (r_e)		2.4022					MW
PbTe	Pb—Te (r_e)		2.5950					MW
PrI_3	Pr—I	2.904		∠IPrI	113		(C_{3v})	ED
PtO	Pt—O (r_e)		1.7273					UV
PuF_6	Pu—F		1.971			(O_h)		ED
RbBr	Rb—Br (r_e)		2.9447					MW
RbCl	Rb—Cl (r_e)		2.7869					MW
RbF	Rb—F (r_e)		2.2703					MW
RbH	Rb—H (r_e)		2.367					UV
RbI	Rb—I (r_e)		3.1768					MW
RbOH	Rb—O	2.301		O—H	0.957		linear	MW
$ReClO_3$	Re—O		1.702			Re—Cl	2.229	MW
	∠ClReO		109.4			(C_{3v})		
ReF_6	Re—F		1.832			(O_h)		ED
RuO_4	Ru—O		1.706			(T_d)		ED
SCSe	C—Se		1.693			C—S	1.553	MW
SCTe	C—S		1.557			C—Te	1.904	MW
SCl_2	S—Cl	2.006		∠ClSCl	103.0		(C_{2v})	ED
SF	S—F (r_e)		1.6006					MW
SF_2	S—F		1.5921			∠FSF	98.20	MW
SF_6	S—F		1.561			(O_h)		ED
SO	S—O (r_e)		1.4811					MW
$SOCl_2$	S—O		1.44			S—Cl	2.072	MW
	∠ClSCl		97.2			∠OSCl	108.0	
SOF_2	S—O		1.420			S—F	1.583	ED
	∠OSF		106.2			∠FSF	92.2	
SOF_4				S—O	1.403		$S—F_a$ 1.575	ED
				$S—F_b$	1.552		$∠OSF_a$ 90.7	
				$∠OSF_b$	124.9		$∠F_aSF_b$ 89.6	
				$∠F_bSF_b$	110.2		(C_{2v})	
SO_2	S—O (r_e)		1.4308			∠OSO (θ_e)	119.329	MW







Compound	Structure								Method
SO_2Cl_2	S—O	1.404		S—Cl	2.011		∠OSO	123.5	ED
	∠ClSCl	100.0		(C_{2v})					
SO_2F_2	S—O	1.397		S—F	1.530		∠OSO	123	ED
	∠FSF	97		(C_{2v})					
SO_3	S—O		1.4198			(D_{3h})			IR
$S(SiH_3)_2$	Si—H	1.494		Si—S	2.136		∠SiSSi	97.4	ED
S_2	S—S (r_e)		1.8892						R
S_2Br_2	S—Br		2.24			S—S	1.98		ED
	∠SSBr		105	dihedral angle of internal rotation			83.5		
S_2Cl_2	S—Cl		2.057			S—S	1.931		ED
	∠SSCl		108.2	dihedral angle of internal rotation			84.1	(C_2)	
S_2O_2	S—O	1.458		S—S	2.025		∠OSS	112.8	MW
							planar *cis* form		
S_8				S—S	2.07				ED
				∠SSS	105				
				(D_{4d})					
$SbCl_3$	Sb—Cl		2.333			∠ClSbCl	97.2		ED
SbH_3	Sb—H		1.704			∠HSbH	91.6		MW
SeF	Se—F		1.742						MW
SeF_6	Se—F		1.69			(O_h)			ED
SeO	Se—O (r_e)		1.6393						MW
$SeOF_2$	Se—O		1.576			Se—F	1.730		MW
	∠OSeF		104.82			∠FSeF	92.22		
SeO_2	Se—O (r_e)		1.6076			∠OSeO (θ_e)	113.83		MW
SeO_3	Se—O		1.69			(D_{3h})			ED
Se_2	Se—Se (r_e)		2.1660						UV
Se_6	Se—Se		2.34			∠SeSeSe	102		ED
	six-membered ring with chair conformation								
$SiBrF_3$	Si—F		1.560			Si—Br	2.153		MW
	∠FSiBr		108.5			(C_{3v})			
$SiBrH_3$	Si—H		1.485			Si—Br	2.210		MW
	∠HSiBr		107.8			(C_{3v})			
$SiClH_3$	Si—H		1.482			Si—Cl	2.048		MW
	∠HSiCl		107.9			(C_{3v})			
$SiCl_4$	Si—Cl		2.019			(T_4)			ED
SiF	Si—F		1.6008						UV
$SiFH_3$	Si—H		1.484			Si—F	1.593		MW, IR
	∠HSiH		110.63			(C_{3v})			
SiF_2	Si—F (r_e)		1.590			∠FSiF (θ_e)	100.8		MW
SiF_3H	Si—H (r_e)		1.4468			Si—F (r_e)	1.5624		MW
	∠HSiF (θ_e)		110.64						
SiF_4	Si—F		1.553			(T_d)			ED
SiH	Si—H (r_e)		1.5201						UV
SiH_3I	Si—H		1.485			Si—I	2.437		MW
	∠HSH		107.8						
SiH_4	Si—H		1.4798			(T_d)			IR
SiN	N—Si (r_e)		1.572						UV
SiO	Si—O (r_e)		1.5097						MW
SiS	Si—S (r_e)		1.9293						MW
SiSe	Se—Si (r_e)		2.0583						MW
Si_2	Si—Si (r_e)		2.246						UV
Si_2Cl_6	Si—Si		2.32			Si—Cl	2.009		ED
	∠ClSiCl		109.7						
Si_2F_6	Si—Si		2.317			Si—F	1.564		ED
	∠FSiF		108.6						
Si_2H_6	Si—H		1.492			Si—Si	2.331		ED
	∠SiSiH		110.3			∠HSiH	108.6		
						staggered form (assumed)			






Compound			Structure				Method
$SnCl_4$	Sn—Cl	2.280		(T_d)			ED
SnH	Sn—H (r_e)	1.7815					UV
SnH_4	Sn—H	1.711		(T_d)			R, IR
SnO	Sn—O	1.8325					MW
SnS	S—Sn (r_e)	2.2090					MW
SnSe	Se—Sn (r_e)	2.3256					MW
SnTe	Sn—Te (r_e)	2.5228					MW
SrH	Sr—H (r_e)	2.1455					UV
SrO	Sr—O (r_e)	1.9198					MW
SrS	S—Sr (r_e)	2.4405					UV
$TaCl_5$	Ta—Cl_{eq}	2.227		Ta—Cl_{ax}	2.369	(D_{3h})	ED
TaO	Ta—O (r_e)	1.6875					UV
TeF_6	Te—F	1.815		(O_h)			ED
Te_2	Te—Te (r_e)	2.5574					UV
$ThCl_4$	Th—Cl	2.58		(T_d)			ED
ThF_4	Th—F	2.14		(T_d)			ED
TlBr	Tl—Br (r_e)	2.6182					MW
TlCl	Tl—Cl (r_e)	2.4848					MW
TlF	Tl—F (r_e)	2.0844					MW
TlH	Tl—H (r_e)	1.870					UV
TlI	Tl—I (r_e)	2.8137					MW
$TiBr_4$	Ti—Br	2.339		(T_d)			ED
$TiCl_4$	Ti—Cl	2.170		(T_d)			ED
TiO	Ti—O (r_e)	1.620					UV
TiS	Ti—S (r_e)	2.0825					UV
UF_6	U—F	1.996		(O_h)			ED
$V(CO)_6$	V—C	2.015		C—O	1.138		ED
		(O_h, involving dynamic Jahn-Teller effect)					
VCl_3O	V—O	1.570		V—Cl	2.142		ED, MW
	∠ClVCl	111.3					
VCl_4	V—Cl	2.138		(T_d, involving dynamic Jahn-Teller effect)			ED
VF_5	V—F (average)	1.71					ED
VO	V—O (r_e)	1.5893					UV
$W(CO)_6$	W—C	2.059	C—O	1.149	(O_h)		ED
$WClF_5$				W—Cl	2.251		MW
				W—F (average)	1.836		
				∠F_aWF_b	88.7		
WF_4O	W—O	1.666		W—F	1.847		ED
	∠FWF	86.2		(C_{4v})			
WF_6	W—F	1.832		(O_h)			ED
XeF_2	Xe—F	1.977		linear			IR
XeF_4	Xe—F	1.94		(D_{4h})			ED
XeF_6	Xe—F	1.890	(large-amplitude bending vibration around the O_h structure)				ED
XeO_4	Xe—O	1.736		(T_d)			ED
ZnH	Zn—H (r_e)	1.5949					UV
$ZrCl_4$	Zr—Cl	2.32		(T_d)			ED
ZrF_4	Zr—F	1.902		(T_d)			ED
ZrO	Zr—O (r_e)	1.7116					UV

STRUCTURES OF ORGANIC MOLECULES








Compounds are arranged in alphabetical order by chemical name; cross references are given for common synonyms (lengths in Å and angles in degrees)





Compound	Structure				Method
Acetaldehyde			C_a—O	1.210	ED, MW
			C_b—H	1.107	
			C_a—H	1.128	
	C_a—C_b	1.515	∠C_bC_aO	124.1	
	∠HC_bH	109.8	∠C_bC_aH	115.3	
Acetamide	C—O	1.220	C—N	1.380	ED
CH_3CONH_2	C—C	1.519	N—H	1.022	
	C—H	1.124	∠NCO	122.0	
	∠CCN	115.1			
Acetic acid			C—C	1.520	ED
			C—O_a	1.214	
			C—O_b	1.364	
	C—H	1.10	∠CCO_a	126.6	
	∠CCO_b	110.6			
Acetone	C—C	1.520	C—O	1.213	ED, MW
$(CH_3)_2CO$	C—H	1.103	∠CCC	116.0	
	∠HCH	108.5	symmetry axis of each methyl group is tilted 2° from the C—C bond		
Acetonitrile	C—H	1.107	C—C	1.468	ED, MW
CH_3CN	C—N	1.159	∠CCH	109.7	
Acetonitrile oxide	C—C	1.442	C—N	1.169	MW
CH_3CNO	N—O	1.217	(C_{3v})		
Acetyl chloride	C—H	1.105	C—O	1.187	ED, MW
CH_3COCl	C—C	1.506	C—Cl	1.798	
	∠HCH	108.6	∠OCCl	121.2	
	∠CCCl	111.6			
Acetyl cyanide → Pyruvonitrile					
Acetylene	C—H (r_e)	1.060	C—C (r_e)	1.203	IR
HC≡CH					
Acrolein → Acrylaldehyde					
Acrylaldehyde			C_b—C_c	1.484	ED, MW
			C_a—C_b	1.345	
			C_c—O	1.217	
			C_a—H	1.10	
			C_c—H	1.13	
	∠$C_aC_bC_c$	120.3	∠C_bC_cO	123.3	
	∠HC_cC_b	114	other CCH angles (average)	122	
	planar *s-trans* form				
Acrylonitrile			C_a—C_b	1.343	ED, MW
			C_b—C_c	1.438	
			C_c—N	1.167	
			C_a—H	1.114	
			∠$C_aC_bC_c$	121.7	
	∠C_bC_cN	178	∠HCC	120	
Acryloyl chloride	C—H	1.086 (assumed)	C_b—C_c	1.48	MW
	C_c—Cl	1.82	C_a—C_b	1.35	
			C_c—O	1.19	
			∠C_aC_bH	120 (assumed)	
			∠C_bC_aH	121.5 (assumed)	
			∠$C_aC_bC_c$	123	
			∠C_bC_cCl	116	
			∠C_bC_cO	127	





Compound	Structure					Method
Allene	C—C	1.3084	C—H		1.087	IR
$CH_2=C=CH_2$	∠HCH	118.2				
Allyl chloride			*cis* conformer	C—Cl	1.811	MW
				∠CCCl	115.2	
			skew conformer	C—Cl	1.809	
	∠CCCl	109.6	CCCCl	dihedral angle of internal rotation	122.4	
Aniline	C—C	1.392	C—N		1.431	MW
$C_6H_5NH_2$	N—H	0.998	∠HNH		113.9	
	dihedral angle between the NH_2 plane and the N—C bond				140.6	
Azetidine			C—N		1.482	ED
			C—C		1.553	
			C—H		1.107	
	N—H	1.03	∠CNC		92.2	
	∠CCC	86.9	∠CCN		85.8	
	dihedral angle between the CCC and CNC planes				147	
Aziridine			N—H		1.016	MW
			N—C		1.475	
			C—C		1.481	
			C—H		1.084	
			∠CNC		60.3	
			$\angle H_aNC$		109.3	
	$\angle H_bCH_c$	115.7	$\angle H_bCC$		117.8	
	$\angle H_bCN$	118.3	$\angle H_cCC$		119.3	
	$\angle H_cCN$	114.3				
Azomethane	C—N	1.482	N—N		1.247	ED
$CH_3N=NCH_3$	∠CNN	112.3	*trans* conformer			
Benzene	C—C	1.399	C—H		1.101	ED, IR
C_6H_6						
p-Benzoquinone			C_a—O		1.225	ED
			C_b—C_b		1.344	
			C_a—C_b		1.481	
			$\angle C_bC_aC_b$		118.1	
Biacetyl	C—O	1.215	C—C (average)		1.524	ED
$CH_3COCOCH_3$	C—H	1.108	∠CCO		119.5	
	∠CCC	116.2	*trans* conformer			
Bicyclo[1.1.0]butane			C_a—C_a		1.497	MW
			C_a—C_b		1.498	
			C_a—H_a		1.071	
			C_b—H_b, C_b—H_c		1.093	
			$\angle H_bC_bH_c$		115.6	
	$\angle C_bC_aH_a$	130.4	$\angle C_aC_bC_a$		60.0	
	$\angle C_aC_aH_a$	128.4	dihedral angle between the two $C_aC_aC_b$ planes		121.7	
Bicyclo[2.2.1]hepta-2,5-diene			C_a—C_b		1.535	ED
			C_b—C_b		1.343	
			C_a—C_c		1.573	
			C—H		1.12	
			$\angle C_aC_cC_a$		94	
	dihedral angle between the two $C_aC_bC_bC_a$ planes				115.6 (C_{2v})	
Bicyclo[2.2.1]heptane	See the preceding molecule for the labels of the C atoms					ED
C_7H_{12}	C_a—C_b	1.54	C_b—C_b		1.56	
	C_a—C_c	1.56	C—C (average)		1.549	
	$-C_aC_cC_a$	93.1	dihedral angle between the two $C_aC_bC_bC_a$ planes		113.1	



Compound	Structure				Method
Bicyclo[2.2.0]hexa-2,5-diene			$C_b—C_b$	1.345	ED
			$C_a—C_a$	1.574	
			$C_a—C_b$	1.524	
		dihedral angle between the two $C_aC_bC_bC_a$ planes		117.3	
Bicyclo[2.2.2]octane	$HC_a(C_bH_2C_bH_2)_3C_aH$		$C_a—C_b$	1.54	ED
	$C_b—C_b$	1.55	$\angle C_aC_bC_b$	109.7	
	C—C (average)	1.542			
	large-amplitude torsional motion about the D_{3h} symmetry axis				
Bicyclo[1.1.1]pentane	C—C	1.557	∠CCC	74.2	ED
C_5H_8					
Bicyclo[2.1.0]pentane			$C_a—C_a$	1.536	MW
			$C_b—C_b$	1.565	
			$C_a—C_b$	1.528	
			$C_a—C_c$	1.507	
	Dihedral angle between the $C_aC_aC_bC_b$ and $C_aC_aC_c$ planes			112.7	
Biphenyl			C—C (intra-ring)	1.396	ED
			(inter-ring)	1.49	
			torsional dihedral angle between the two rings	~40	
4,4′-Bipyridyl	C—C, C—N (intra-ring)		1.375		ED
			C—C (inter-ring)	1.465	
			torsional dihedral angle between the two rings	~37	
Bis (cyclopentadienyl) beryllium	Be—(cyclopentadienyl plane)		1.470, 1.92		ED
$(C_5H_5)_2Be$	C—C 1.423 (C_{5v}) (The Be atom has two equilibrium positions)				
Bis (cyclopentadienyl) iron → Ferrocene					
Bis (cyclopentadienyl) lead	C—C	1.430	Pb—C	2.79	ED
$(C_5H_5)_2Pb$	dihedral angle between the two C_5H_5 planes 40~50 (The two rings are not parallel.)				
Bis (cyclopentadienyl) manganese	Mn—C 2.383	C—C 1.429	(D_{5h})		ED
$(C_5H_5)_2Mn$					
Bis (cyclopentadienyl) nickel	Ni—C	2.196	C—C	1.430 (D_{5h})	ED
$(C_5H_5)_2Ni$					
Bis (cyclopentadienyl) ruthenium	C—C	1.439	Ru—C	2.196	ED
$(C_5H_5)_2Ru$					
Bis (cyclopentadienyl) tin	C—C	1.431	Sn—C	2.71	ED
$(C_5H_5)_2Sn$	C—H	1.14	(D_{5h})		
Bis (trifluoromethyl) peroxide	O—O	1.42	C—O	1.399	ED
CF_3OOCF_3	C—F	1.320	∠COO	107	
	∠FCF	109.0	COOC dihedral angle of internal rotation	123	
Borine carbonyl	B—H	1.194	B—C	1.540	MW
BH_3CO	C—O	1.131	∠HBH	113.9	
	∠BCO	180	(C_{3v})		
Bromobenzene			C—H	1.072	MW
			$C_c—C_d$	1.401	
			$C_b—C_c$	1.375	
			C—Br	1.85	
			$C_a—C_b$	1.42	
			$\angle C_bC_aC_b$	117.4	
Bromoform	C—Br	1.924	C—H	1.11	ED, MW
$CHBr_3$	∠BrCBr	111.7	(C_{3v})		
Bromoiodoacetylene	C—I	1.972	C—C	1.206	ED
IC≡CBr	C—Br	1.795			







Compound	Structure				Method
1,3-Butadiene	C_aH_2		$C_b—C_b$	1.467	ED
	$C_bH—C_bH$		$C_a—C_b$	1.349	
	C_aH_2		C—H (average)	1.108	
			∠CCC	124.4	
	$\angle C_bC_aH$	120.9	*anti* conformer	(C_{2h})	
1,3-Butadiyne	$HC_a≡C_b—C_b≡C_aH$		C—H	1.09	ED
	$C_a—C_b$	1.218	$C_b—C_b$	1.384	
			linear		
Butane	C—C	1.531	C—H	1.117	ED
$CH_3CH_2CH_2CH_3$	∠CCC	113.8	∠CCH	111.0	
	trans conformer	54%	dihedral angle for the *gauche* conformer		65
2-Butanone → Ethyl methyl ketone					
Butatriene	$H_2C_a=C_b=C_b=C_aH_2$		C—H	1.08	ED
	$C_a—C_b$	1.32	$C_b—C_b$	1.28 (D_{2h})	
2-Butene	$C_aH_3—C_bH=C_bH—C_aH_3$				ED
	$C_a—C_b$	*cis* conformer	1.506	*trans* conformer 1.508	
	$C_b—C_b$	1.346	1.347		
	$\angle C_aC_bC_b$	125.4	123.8		
3-Buten-1-yne → Vinylacetylene					
tert-Butyl chloride	C—H	1.102	C—C	1.528	ED, MW
$(CH_3)_3CCl$	C—Cl	1.828	∠CCCl	107.3	
	∠CCH	110.8	∠CCC	111.6	
tert-Butyl cyanide → Pivalonitrile					
2-Butyne	$C_aH_3—C_b≡C_b—C_aH_3$	C—H	1.116	ED	
	$C_b—C_b$	1.214	$C_a—C_b$	1.468	
	$\angle C_bC_aH$	110.7			
Carbon C_2	C—C (r_e)	1.3119			UV
Carbon C_3	C—C	1.277	linear		UV
Carbon suboxide → Tricarbon dioxide					
Carbon tetrabromide	C—Br	1.935	(T_d)		ED
CBr_4					
Carbon tetrachloride	C—Cl	1.767	(T_d)		ED
CCl_4					
Carbon tetrafluoride	C—F	1.323	(T_d)		ED
CF_4					
Carbon tetraiodide	C—I	2.15	(T_d)		ED
CI_4					
Carbonyl cyanide	C—O	1.209	C—C	1.466	ED, MW
$CO(CN)_2$	C—N	1.153	∠CCC	115	
	∠CCN	180			
Chloroacetylene	C—H	1.0550	C—C	1.2033	MW
HC≡CCl	C—Cl	1.6368			
Chlorobenzene	C—C	1.400	C—Cl	1.737	ED
C_6H_5Cl	C—H	1.083	∠CC(Cl)C	121.7	
	∠CC(H)C	120			
Chlorobromoacetylene	Cl—C	1.636	C—C	1.206	ED
ClC≡CBr	C—Br	1.784			
Chlorocyanoacetylene	C—Cl	1.624	C—C	1.205	ED
ClC≡CCN	C—CN	1.362	C—N	1.160	
Chloroethane → Ethyl chloride					
2-Chloroethanol	C—O	1.413	C—C	1.519	ED
$ClCH_2CH_2OH$	C—Cl	1.801	C—H	1.093	
	O—H	1.033	∠CCCl	110.7	∠CCO 113.8
	fraction of the *gauche* conformer at 37°C is 92 ∼ 94%,				
	dihedral angle of internal rotation		62.4		
Chloroethylene → Vinyl chloride					
Chloroform	C—H	1.100	C—Cl	1.758	MW
$CHCl_3$	∠ClCCl	111.3	(C_{3v})		
Chloroiodoacetylene	C—Cl	1.63	C—I	1.99	MW
ClC≡CI	C—C	1.209 (assumed)			





Compound	Structure				Method
Chloromethane → Methyl chloride					
3-Chloropropene → Allyl chloride					
Cyanamide	N_a—C	1.346	C—N_b	1.160	MW
$H_2N_aCN_b$	N—H	1.00	∠HNH	114	
	dihedral angle between the NH_2 plane and the N—C bond			142	
Cyanoacetylene	C_b—H	1.058	C_a—C_b	1.205	MW
H—C_b≡C_a—C_c≡N	C_a—C_c	1.378	C_c—N	1.159	
Cyanocyclopropane	C—C (ring)	1.513	C—C_a	1.472	MW
$C_3H_5C_aN$	C—H	1.107	C_a—N	1.157	
	∠HCH	114.6	∠C_aCH	119.6	
Cyanogen	C—N	1.163	C—C	1.393	ED
$(CN)_2$				linear	
Cyclobutane	C—H	1.113	C—C	1.555	ED
$(CH_2)_4$	dihedral angle between the two CCC planes 145				
Cyclobutanone			C_a—C_b	1.527	MW
			C_b—C_c	1.556	
			∠$C_bC_aC_b$	93.1	
			∠$C_aC_bC_c$	88.0	
Cyclobutene		C_b—C_b	1.342	C_a—C_a 1.566	MW
		C_a—C_b	1.517	C_a—H 1.094	
		C_b—H	1.083		
	∠$C_aC_bC_b$	94.2	∠C_bC_bH	133.5	
	∠C_aC_aH	114.5	∠$C_aC_aC_b$	85.8	
	∠HC_aH	109.2	dihedral angle between the CH_2 plane and the C_a—C_a bond	135.8	
Cyclohexane	C—C	1.536	C—H	1.119	ED
C_6H_{12}	∠CCC	111.3	chair form		
Cyclohexene			C_a—C_a	1.334	ED
			C_a—C_b	1.50	
			C_b—C_c	1.52	
			C_c—C_c	1.54	
	∠$C_aC_aC_b$	123.4	∠$C_aC_bC_c$	112.0	
	∠$C_bC_cC_c$	110.9	(C_2)	half-chair form	
Cyclooctatetraene			C_a—C_b	1.476	ED
			C—H	1.100	
			C_a—C_a,C_b—C_b	1.340	
			∠$C_bC_aC_a$, ∠$C_aC_bC_b$	126.1	
	dihedral angle between the $C_aC_aC_aC_a$ and $C_aC_bC_bC_a$ planes			136.9	
	tub form (D_{2d})				
1,3-Cyclopentadiene			C_a—C_b	1.509	MW
			C_b—C_c	1.342	
			C_c—C_c	1.469	
			∠$C_aC_bC_c$	109.3	
	∠$C_bC_cC_c$	109.4	∠$C_bC_aC_b$	102.8	
Cyclopentadienylindium			In—C	2.621	ED
			C—C	1.426	
			(C_{5v})		
Cyclopentane	C—H	1.114	C—C	1.546	ED
$(CH_2)_5$	∠CCH	111.7			
	(The out-of-plane vibration of the C atoms is essentially free pseudorotation; average value of the displacements of the C atoms from the molecular plane 0.43)				
Cyclopentene			C_a—C_b	1.546	ED
			C_b—C_c	1.519	
			C_c—C_c	1.342	
			∠$C_bC_aC_b$	104.0	
	∠$C_bC_cC_c$	110.0	∠$C_aC_bC_c$	103.0	
	dihedral angle between the $C_bC_aC_b$ and $C_bC_cC_cC_b$ planes			151.2	





Compound	Structure						Method
Cyclopropane	C—C	1.512	C—H	1.083			R
$(CH_2)_3$	∠HCH	114.0					
Cyclopropanone		C—H	1.086	C_a—C_b	1.475		MW
		C_b—C_b	1.575	C_a—O	1.191		
		$\angle C_aC_bC_b$	57.7				
	∠HC_bH	114	dihedral angle between the CH_2 plane and the C_b—C_b bond		151		
Cyclopropene			C_b—C_b	1.304			ED
			C_a—C_b	1.519			
			C_b—H	1.077			
	C_a—H	1.112	∠C_bC_bH	133			
	∠HC_aH	118					
Decalin	C—C (average)	1.530	C—H (average)	1.113			ED
$C_{10}H_{18}$	∠CCC (average)	111.4					
Dewer benzene → Bicyclo[2.2.0] hexa-2,5-diene							
Diacetylene → 1,3-Butadiyne							
1,4-Diazabicyclo[2.2.2]octane			C—N	1.472			ED
			C—C	1.562			
			∠NCC	110.2			
			∠CNC	108.7			
	large-amplitude torsional motion about the D_{3h} symmetry axis						
2,3-Diaza-1,3-butadiene → Formaldehyde azine							
Diazirine			C—H	1.09			MW
			C—N	1.482			
			N—N	1.228			
			∠HCH	117			
Diazoacetonitrile			C_b—N_b	1.280			MW
			N_b—N_c	1.132			
			C_a—N_a	1.165			
			C—H	1.082			
			C_a—C_b	1.424			
	∠C_aC_bH	117	∠$C_aC_bN_b$	119.5			
Diazomethane	C—H	1.075	C—N	1.32			MW, IR
CH_2N_2	N—N	1.12	∠HCH	126.0 linear			
1,2-Dibromoethane	C—C	1.506	C—Br	1.950			ED
CH_2BrCH_2Br	C—H	1.108	∠CCBr	109.5			
	∠CCH 110		fraction of the *trans* conformer at 25°C	95%			
Dibromomethane	C—H	1.08	C—Br	1.924			ED
CH_2Br_2	∠HCBr	109	∠BrCBr	113.2			
2,2′-Dichlorobiphenyl	C—C	1.398	C—C inter-ring	1.495			ED
C_6H_4Cl—C_6H_4Cl	C—Cl	1.732	C—H	1.10			
	∠CCCl	121.4	∠CCH	126			
	dihedral angle between the two aromatic rings 74 (defined to be 0 for that of the *cis* conformer)						
trans-1,4-Dichlorocyclohexane	C—H	1.102	C—Cl	1.810			ED
$C_6H_{10}Cl_2$	C—C	1.530	∠CCC	111.5			
	∠CCCl (*ee*)	108.6	∠CCCl (*aa*)	110.6			
	∠HCCl (*ee*)	111.5	∠HCCl (*aa*)	107.6			
	ee 49%		aa 51%	e: equatorial, a: axial			
1,1-Dichloroethane	C—Cl	1.766	C—C	1.540			MW
$CHCl_2CH_3$	∠ClCCl	112.0	∠CCCl	111.0			
1,2-Dichloroethane	C—C	1.531	C—Cl	1.790			ED
CH_2ClCH_2Cl	C—H	1.11	∠CCCl	109.0			
	∠CCH	113					
	fraction of the *trans* conformer at room temperature 73%, that of the *gauche* conformer 27%						






Compound	Structure				Method
1,1-Dichloroethylene	C—C	1.32 (assumed)	C—Cl	1.73	MW
$CH_2{=}CCl_2$	∠ClCC	123	(C_{2v})		
cis-1,2-Dichloroethylene	C—Cl	1.718	C—C	1.354	ED
CHCl=CHCl	∠ClCC	123.8			
Dichloromethane	C—H (r_e)	1.087	C—Cl (r_e)	1.765	MW, IR
CH_2Cl_2	∠HCH (θ_e)	111.5	∠ClCCl (θ_e)	112.0	
1,1-Difluoroethane	C—C	1.498	C—H (average)	1.081	ED
CH_3CHF_2	C—F	1.364	∠CCH (average)	111.0	
	∠CCF 110.7	dihedral angle between the two CCF planes		118.9	
1,2-Difluoroethane	C—F	1.389	C—C	1.503	ED
CH_2FCH_2F	C—H	1.103	∠CCF	110.3	
	∠CCH 111	dihedral angle of internal rotation		109	
	fraction of the *gauche* conformer at 22°C 94%				
1,1-Difluoroethane	C—C	1.340	C—F	1.315	ED, MW
$CH_2{=}CF_2$	C—H	1.091	∠CCF	124.7	
	∠CCH	119.0			
cis-1,2-Difluoroethylene	C—C	1.33	C—F	1.342	ED, MW
CHF=CHF	C—H	1.099	∠CCF	122.0	
	∠CCH	124.1			
Difluoromethane	C—H	1.093	C—F	1.357	MW
CH_2F_2	∠HCH	113.7	∠FCF	108.3	
Dimethoxymethane			C_a—O	1.432	ED
			C_b—O	1.382	
			C—H (average)	1.108	
	∠COC	114.6	∠OCO	114.3	
	∠OCH	110.3			
Dimethylacetylene → 2-Butyne					
Dimethylamine	C—H	1.106	N—H	1.00	ED
$(CH)_2NH$	C—N	1.455	∠CNC	111.8	
	∠CNH	107	∠NCH	112	
	∠HCH	107			
Dimethylberyllium	Be—C	1.698	C—H	1.127	ED
$(CH_3)_2Be$	∠BeCH	113.9	CBeC linear		
Dimethylcadmium	C—Cd	2.112	∠HCH	108.4	R
$(CH_3)_2Cd$					
Dimethyl carbonate			C_b—O_b	1.209	ED
			C_b—O_a	1.34	
			C_a—O_a	1.42	
	$\angle O_aC_bO_a$	107	$\angle C_bO_aC_a$	114.5	
Dimethylcyanamide	C_b—N_b	1.161	C_b—N_a	1.338	ED
$(C_aH_3)_2N_a$—$C_b{\equiv}N_b$	C_a—N_a	1.463	$\angle C_aNC_a$	115.5	
	$\angle C_aNC_b$	116.0			
1,2-Dimethyldiborane			B—B	1.799	ED
			B—C	1.580	
			B—H_b	1.358 (*cis*), 1.365 (*trans*)	
	B—H_t	1.24			
	∠BBC	122.6 (*cis*), 121.8 (*trans*)			
Dimethyl diselenide	C—H	1.13	C—Se	1.95	ED
$(CH_3)_2Se_2$	Se—Se	2.326	∠CSeSe	98.9	
	∠HCSe 108	dihedral angle between the CSeSe and SeSeC planes		88	
Dimethyl disulfide	C—S	1.816	S—S	2.029	ED
$(CH_3)_2S_2$	C—H	1.105	∠SSC	103.2	
	∠SCH 111.3	CSSC dihedral angle of internal rotation		85	
S,S′-Dimethyl dithiocarbonate			C_b—O	1.206	ED
			C_b—S	1.777	
			C_a—S	1.802	
	∠OCS	124.9	∠CSC	99.3	
			syn-syn conformer		







Compound	Structure				Method
Dimethyl ether	C—O	1.416	C—H	1.121	ED
$(CH_3)_2O$	∠COC	112	∠HCH	108	
Dimethylglyoxal → Biacetyl					
N,N′-Dimethylhydrazine	N—N	1.42	C—N	1.46	ED
$CH_3NH—NHCH_3$	N—H	1.03	C—H	1.12	
	∠NNC 112	CNNC dihedral angle of internal rotation		90	
Dimethylmercury	C—Hg	2.083	C—H	1.160 (assumed)	ED
$(CH_3)_2Hg$	Hg···H	2.71			
Dimethylphosphine	C—P	1.848	P—H	1.419	MW
$(CH_3)_2PH$	∠CPC	99.7	∠CPH	97.0	
Dimethyl selenide	C—H	1.093	Se—C	1.943	MW
$(CH_3)_2Se$	∠CSeC	96.2	∠SeCH	108.7	
	∠HCH	110.3			
Dimethyl sulfide	C—S	1.807	C—H	1.116	ED, MW
$(CH_3)_2S$	∠CSC	99.05	∠HCH	109.3	
Dimethyl sulfone	C—H	1.114	S—O	1.435	ED
$(CH_3)_2SO_2$	S—C	1.771	∠CSC	102	
	∠OSO	121			
Dimethyl sulfoxide	C—H	1.081	C—S	1.799	MW
$(CH_3)_2SO$	S—O	1.485	∠CSC	96.6	
	∠CSO	106.7	∠HCH	110.3	
	dihedral angle between the SCC plane and the S—O bond			115.5	
Dimethylzinc	Zn—C	1.929	∠HCH	107.7	R
$(CH_3)_2Zn$					
1,4-Dioxane	C—C	1.523	C—O	1.423	ED
	C—H	1.112	∠COC	112.45	
	∠CCO	109.2	chair form		
Ethanal → Acetaldehyde					
Ethane	C—C	1.5351	C—H	1.0940	MW
C_2H_6	∠CCH	111.17	staggered conformation		
Ethanethiol	$C_bH_3—C_aH_2—SH$		$C_a—H$	1.090	MW
	$C_b—H$	1.093	$C_a—C_b$	1.530	
	$C_a—S$	1.829	S—H	1.350	
	$∠C_bC_aH$	109.6	$∠C_aC_bH$	109.7	
	$∠C_bC_aS$	108.3	$∠C_aSH$	96.4	
Ethanol	$C_bH_3C_aH_2OH$		C—C	1.512	MW
	C—O	1.431	O—H	0.971	
	$C_a—H$	1.10	$C_b—H$	1.09	
	∠CCO	107.8	∠COH	105	
	$∠C_bC_aH$	111	$∠C_aC_bH$	110	
	staggered conformation				
Ethyl chloride			C—C	1.528	ED, MW
			C—Cl	1.802	
			C—H	1.103	
			$C_a—H_a=C_b—H_b$ (assumed)		
			∠CCCl	110.7	
	$∠H_bC_bH_b$	109.8	$∠H_aC_aH_a$	109.2	
	$∠C_bC_aH_a$	110.6			
Ethylene	C—H	1.087	C—C	1.339	MW
$CH_2=CH_2$	∠CCH	121.3			
Ethylenediamine	C—N	1.469	C—C	1.545	ED
$H_2NCH_2CH_2NH_2$	C—H	1.11	∠CCN	110.2	
	gauche conformer	dihedral angle between the NCC and CCN planes		64	
Ethylene dibromide → 1,2-Dibromoethane					
Ethylene dichloride → 1,2-Dichloroethane					
Ethyleneimine → Aziridine					








Compound	Structure						Method
Ethylene oxide	C—C	1.466	C—H		1.085		MW
	C—O	1.431	∠HCH		116.6		
	dihedral angle between the NH_2 plane and the N—C bond				158.0		
Ethylene sulfide → Thiirane							
Ethyl methyl ether	C—O (average)	1.418	C—C		1.520		ED
$C_2H_5OCH_3$	C—H (average)	1.118	∠COC		111.9		
	∠OCC	109.4	∠HCH		109.0		
	fraction of the *trans* conformer at 20°C		80%				
Ethyl methyl ketone			C—C (average)		1.518		ED
			C_c—O		1.219		
			C—H (average)		1.102		
			$\angle C_aC_bC_c$		113.5		
	$\angle C_bC_cO$, $\angle C_dC_cO$	121.9	trans conformer		95%		
Ethyl methyl sulfide	C—S (average)	1.813	C—C		1.536		ED
$C_2H_5SCH_3$	C—H	1.111	∠CSC		97		
	∠SCC	114.0	∠HCH		110		
	fraction of the *gauche* conformer at 20°C		75%				
Ferrocene	C—C	1.440	C—H		1.104		ED
$(C_5H_5)_2Fe$	Fe—C	2.064	(D_{5h})				
Fluoroform	C—H	1.098	C—F		1.332		MW
CHF_3	∠FCF	108.8	(C_{3v})				
Formaldehyde	C—H	1.116	C—O		1.208		MW
H_2CO	∠HCH	116.5					
Formaldehyde azine	$H_2C{=}N{-}N{=}CH_2$	N—N	1.418				ED
	C—N	1.277	C—H		1.094		
	∠CNN	111.4	∠HCN		120.7		
	fraction of the *trans* conformer at –30°C		91%				
Formaldehyde dimethylacetal → Dimethoxymethane							
Formaldoxime			$C{-}H_a$		1.085		MW
			$C{-}H_b$		1.086		
			C—N		1.276		
	N—O	1.408	$O{-}H_c$		0.956		
	$\angle H_bCN$	115.6	∠CNO		110.2		
	$\angle H_aCN$	121.8	$\angle NOH_c$		102.7		
Formamide			$C{-}H_a$		1.125		ED, MW
			N—H		1.027		
			C—N		1.368		
	C—O	1.212	∠NCO		125.0		
	∠CNH (average)	119.2					
Formic acid			$C{-}O_a$		1.202		MW
			$C{-}O_b$		1.343		
	O_b—H	0.972	C—H		1.097		
	$\angle HCO_a$	124.1	$\angle O_aCO_b$		124.9		
	$\angle CO_bH$	106.3	planar				
Formic acid dimer			$O_a{\cdots}O_b$		2.703		ED
			$C{-}O_a$		1.220		
			$C{-}O_b$		1.323		
			$\angle O_aCO_b$		126.2		
			$\angle CO_aO_b$		108.5		
Formyl radical		C—H	1.110	C—O		1.1712	MW
		∠HCO	127.43				








Compound	Structure				Method
Fulvene			$C_a—C_d$	1.349	MW
			$C_a—C_b$	1.470	
			$C_b—C_c$	1.355	
			$C_c—C_c$	1.476	
			$C_b—H$	1.078	
			$C_c—H$	1.080	
	$C_d—H$	1.13	$\angle C_bC_aC_b$	106.6	
	$\angle C_aC_bC_c$	107.7	$\angle C_bC_cC_c$	109	
	$\angle C_aC_bH$	124.7	$\angle C_bC_cH$	126.4	
	$\angle HC_dH$	117			
2-Furaldehyde			$C_a—C_e$	1.458	MW
			$C_e—O_b$	1.250	
			$C_e—H$	1.088	
			$\angle C_eC_aC_b$	133.9	
	$\angle C_aC_eH$	116.9	$\angle C_aC_eO$	121.6	
	trans conformer (with respect to the O_a and O_b atoms)				
Furan			$C_b—C_b$	1.431	MW
			$C_a—C_b$	1.361	
			$C_a—O$	1.362	
			$C_a—H_a$	1.075	
			$C_b—H_b$	1.077	
	$\angle C_aC_bC_b$	106.1	$\angle C_aOC_a$	106.6	
	$\angle C_bC_aO$	110.7	$\angle OC_aH_a$	115.9	
	$\angle C_bC_bH_b$	128.0			
Furfural → 2-Furaldehyde					
Glycolaldehyde			$C_b—O_b$	1.209	MW
			$C_a—O_a$	1.437	
			$C_a—C_b$	1.499	
			$O_a—H_a$	1.051	
			$C_b—H_c$	1.102	
			$C_a—H_b$	1.093	
	$\angle C_aC_bO_b$	122.7	$\angle C_aC_bH_c$	115.3	
	$\angle C_bC_aO_a$	111.5	$\angle C_aO_aH_a$	101.6	
	$\angle C_bC_aH_b$	109.2	$\angle H_bC_aH_b$	107.6	
	$\angle H_bC_aO_a$	109.7			
Glyoxal	C—C	1.526	C—O	1.212	ED, UV
CHOCHO	C—H	1.132	∠CCO	121.2	
	∠HCO	112	*trans* conformer	(C_{2h} (assumed))	
Hexachloroethane	C—C	1.56	C—Cl	1.769	ED
Cl_3CCCl_3	∠CCCl	110.0			
2,4-Hexadiyne	$C_aH_3—C_b≡C_c—C_c≡C_b—C_aH_3$				ED
	$C_a—C_b$	1.450	$C_b—C_c$	1.208	
	$C_c—C_c$	1.377	$C_a—H$	1.09	
Hexafluoroethane	C—C	1.545	C—F	1.326	ED
F_3CCF_3	∠CCF	109.8	staggered conformation		
Hexafluoropropene	average value of the C=C and C—F distances			1.329	ED
$CF_2=CFCF_3$	C—C	1.513	∠CCC	127.8	
	∠FCC (CF_2)	124	∠FCC (CF)	120	
	∠FCC (CF_3)	110			
1,3,5-Hexatriene	$H_2C_a=C_bH—C_cH=C_cH—C_bH=C_aH_2$				ED
	$C_a—C_b$	1.337	$C_b—C_c$	1.458	
	$C_c—C_c$	1.368	$\angle C_aC_bC_c$	121.7	
	$\angle C_bC_cC_c$	124.4			
Iminocyanide radical	N—H	1.034	N···N	2.470	UV
HNCN	∠HNC	116.5	∠NCN	∼180	
Iodocyanoacetylene	$I—C_a$	1.985	$C_a—C_b$	1.207	MW
$I—C_a≡C_b—C_c≡N$	$C_b—C_c$	1.370	$C_c—N$	1.160	









Compound	Structure					Method
Isobutane	C_a—H	1.122	C_b—H		1.113	ED, MW
$(C_bH_3)_3C_aH$	C_a—C_b	1.535	∠$C_bC_aC_b$		110.8	
	∠C_aC_bH	111.4				
Isobutylene → 2-Methylpropene						
Ketene	C—C	1.317	C—O		1.161	MW
CH_2=C=O	C—H	1.080	∠HCH		123.0	
Malononitrile	C—H	1.091	C—C		1.480	MW
$C_aH_2(C_bN)_2$	C—N	1.147	∠CCC		110.4	
	∠HCH	108.4	∠CCN		176.6	
	(The two N atoms are bent away from each other in the plane of C_b—C_a—C_b)					
Methane	C—H (r_e)	1.0870	(T_d)			MW
CH_4						
Methanethiol	C—H	1.09	C—S		1.819	MW
CH_3SH	S—H	1.34	∠HSC		96.5	
	∠HCH	109.8				
	angle between the CH_3 symmetry axis and the C—S bond 2.2. (The axis of the CH_3 group is tilted away from the H atom with respect to the C—S bond.)					
Methanol	C—H	1.0936	C—O		1.4246	MW
CH_3OH	O—H	0.9451	∠HCH		108.63	
	∠COH	108.53				
	angle between the CH_3 symmetry axis and the C—O bond (The axis of the CH_3 group is tilted away from the H atom with respect to the C—O bond.)				3.27	
Methyl radical	C—H	1.08	planar			UV
$\cdot CH_3$						
N-Methylacetamide			C_a—C_b		1.520	ED
			N—C_c		1.469	
			C—H		1.107	
	C_b—N	1.386	C_b—O		1.225	
	∠C_bNC_c	119.7				
	∠NC_bO	121.8				
	∠C_aC_bN	114.1				
Methylacetylene → Propyne						
Methylal → Dimethoxymethane						
Methylamine	N—H	1.010	C—N		1.471	MW
CH_3NH_2	C—H	1.099	∠HNH		107.1	
	∠HNC	110.3	∠HCH		108.0	
	dihedral angle between the CH_3 symmetry axis and the C—N bond (The axis of the CH_3 group is tilted away from the NH_2 group with respect to the C—N bond.)				2.9	
Methyl azide			C—H		1.09	ED
			C—N_a		1.468	
			N_a—N_b		1.216	
	N_b—N_c	1.113	∠CN_aN_b		116.8	
	NNN linear					
Methyl bromide	C—H (r_e)	1.086	C—Br (r_e)		1.933	MW, IR
CH_3Br	∠HCH (θ_e)	111.2	(C_{3v})			
Methyl chloride	C—H	1.090	C—Cl		1.785	MW, IR
CH_3Cl	∠HCH	110.8				
Methyldiazirine		C—N	1.481	C—C	1.501	MW
		N—N	1.235	∠NCN	49.3	
		dihedral angle between the CNN plane and the C—C bond		122.3		
Methylene	C—H	1.078	∠HCH	130		LMR
$:CH_2$						
Methylenecyclopropane			C_a—C_b	1.332		MW
			C_b—C_c	1.457		
			C_c—C_c	1.542		
	C_c—H	1.09	∠$C_cC_bC_c$	63.9		

Compound	Structure					Method
	∠HC_aH	114.3	∠HC_cH	113.5		
	dihedral angle between the C_cH_2 plane and the C_c—C_c bond			150.8		
3-Methyleneoxetane			C_b—C_c	1.52		MW
			C_c—O	1.45		
			C_a—C_b	1.33		
	C—H	1.09 (assumed)	∠$C_cC_bC_c$	87		
	∠HC_cH	114 (assumed)	∠HC_aH	120 (assumed		
Methyl fluoride	C—H (r_e)	1.095				MW, IR
CH_3F	C—F (r_e)	1.382	∠HCH (θ_e)	110.45	(C_{3v})	
Methyl formate			C_a—H	1.08		ED
			C_b—O_b	1.206		
			C—O (average)	1.393		
			C_b—H	1.101 (assumed)		
	∠$O_aC_bO_b$	127	∠COC	114		
	∠O_aC_aH	110				
Methylgermane	C—H	1.083	Ge—H	1.529		MW
CH_3GeH_3	C—Ge	1.945	∠HCH	108.4		
	∠HGeH	109.3				
Methyl hypochlorite	C—H	1.103	O—Cl	1.674		MW
CH_3OCl	O—C	1.389	∠HCH	109.6		
	∠COCl	112.8				
Methylidyne radical	C—H (r_e)	1.1198				UV
:CH						
Methylidyne phosphide	H—C (r_e)	1.0692	C—P (r_e)	1.5398		MW
HCP						
Methyl iodide	C—H (r_e)	1.084	C—I (r_e)	2.132		MW, IR
CH_3I	∠HCH (θ_e)	111.2	(C_{3v})			
Methyl isocyanide	C_aH_3—N≡C_b	C_a—H	1.102	C_a—N	1.424	MW
	N—C_b	1.166	∠NC_aH	109.12		
Methylketene			O—C_a	1.171		MW
			C_b—C_c	1.518		
			C_c—H	1.10		
	C_a—C_b	1.306	C_b—H	1.083		
	∠OC_aC_b	180.5	∠$C_aC_bC_c$	122.6		
	∠C_aC_bH	113.7	∠C_cC_bH	123.7		
	∠HCH	109.2				
Methylmercury chloride	Hg—Cl	2.282	C—H	1.15		MW,
CH_3HgCl	Hg—C	1.99	(C_{3v})			NMR
Methyl nitrate			C—H_a	1.10		MW
			C—H_b	1.09		
			C—O	1.437		
			O—N	1.402		
	N—O_a	1.205	N—O_b			
	∠OCH_a	110	∠OCH_b	103		
	∠CON	112.7	∠ONO_a	118.1		
	∠ONO_b	112.4				
Methylphosphine	C—P	1.858	C—H	1.094		ED
CH_3PH_2						
2-Methylpropane → Isobutane						
2-Methylpropene			C_a—H		1.119	ED, MW
			C_c—H_c		1.10	
			C_a—C_b		1.508	
			C_b—C_c		1.342	
	∠HC_aC_b (average)	111.4	∠$H_cC_cH_c$		118.5	
	∠$C_aC_bC_a$	115.6	∠$C_aC_bC_c$		122.2	
	∠HC_aH	107.9	∠C_bC_cH		121	




Compound	Structure						Method
Methylsilane	C—H	1.093	C—Si		1.867		MW
CH_3SiH_3	Si—H	1.485	∠HCH		107.7		
	∠HSiH	108.3	(C_{3v})				
Methylstannane	C—Sn	2.143	Sn—H		1.700		MW
CH_3SnH_3			(C_{3v})				
Methyl thiocyanate	C_aH_3	S—C_b	1.684	S—C_a		1.824	MW
	S—C_b—N	C_b—N	1.170	C—H		1.081	
	∠C_aSC_b	99.0	∠HCH	110.6	∠HCS	108.3	
Naphthalene			C_a—C_b		1.37		ED
			C_b—C_b		1.41		
			C_a—C_c		1.42		
			C_c—C_c		1.42		
			C—C (average)		1.40		
			∠$C_aC_cC_c$		119.4		
Neopentane	C—C	1.537	C—H		1.114		ED
$C(CH_3)_4$	∠CCH	112					
Nickelocene → Bis (cyclopentadienyl) nickel							
Nitromethane	C—H	1.088 (assumed)	C—N		1.489		MW
CH_3NO_2	N—O	1.224	∠NCH		107		
	∠ONO	125.3					
N-Nitrosodimethylamine	N—O	1.235	N—N		1.344		ED
$(CH_3)_2NNO$	C—N	1.461	∠ONN		113.6		
	∠CNC	123.2	∠CNN		116.4		
Nitrosomethane	C—N	1.49	N—O		1.22		MW
CH_3NO	C—H	1.084	∠CNO		112.6		
	∠NCH	109.0					
Norbornane → Bicyclo[2.2.1]heptane							
Norbornadiene → Bicyclo[2.2.1]hepta-2,5-diene							
1,2,5-Oxadiazole		O—N	1.380	∠NON	110.4		MW
		C—N	1.300	∠ONC	105.8		
		C—C	1.421	∠CCN	109.0		
		C—H	1.076	∠CCH	130.2		
		∠NCH	120.9	planar			
1,3,4-Oxadiazole		O—C	1.348	∠COC	102.0		MW
		C—N	1.297	∠OCN	113.4		
		N—N	1.399	∠CNN	105.6		
		C—H	1.075	∠OCH	118.1		
		∠NCH	128.5	planar			
Oxalic acid			C—C		1.544		ED
			C—O_a		1.205		
			C—O_b		1.336		
			O_b—H		1.05		
			∠CCO_a		123.1		
			∠O_aCO_b		125.0		
			∠CO_bH		104		
Oxalyl dichloride			C—O		1.182		ED
			C—C		1.534		
			C—Cl		1.744		
	∠CCO	124.2	∠CCCl		111.7		
	fraction of the *trans* conformer at 0°C 68%, that of the *gauche* conformer 32%						
Oxetane			C—O		1.448		MW
			C—C		1.546		
			C—H (average)		1.090		
			∠COC		92		





Compound	Structure						Method
	∠CCC	85	∠OCC	92			
	∠HCH (average)	109.9					
Oxirane → Ethylene oxide							
Phenol			C—C (average)	1.397			MW
			C_b—H	1.084			
			C_c—H	1.076			
			C_d—H	1.082			
			C_a—O	1.364			
			O—H	0.956			
			∠COH	109.0			
Phosphirane			C—P	1.867	P—H	1.43	MW
			C—C	1.502	C—H	1.09	
			∠CPC	47.4	∠HCH	114.4	
	∠HPC	95.2	∠CCH	118			
	dihedral angle between the PCC plane and the PH bond			95.7			
Piperazine			C—C	1.540			ED
			C—N	1.467			
			C—H	1.110			
	∠CNC	109.0	∠CCN	110.4			
			(C_{2h})				
Pivalonitrile	C_a—C_b	1.495	C_a—N	1.159			MW
$(C_cH_3)_3C_b$—C_a≡N	C_b—C_c	1.536	∠$C_cC_bC_c$	110.5			
Propadiene → Allene							
Propane	C—C	1.532	C—H	1.107			ED
C_3H_8	∠CCC	112	∠HCH	107			
Propenal → Acrylaldehyde							
Propene			C_a—H_a	1.104			ED, MW
			C_a—C_b	1.341			
			C_c—H_d	1.117			
			C_b—C_c	1.506			
			∠$C_bC_aH_{a,b,c}$	121.3			
	∠$C_bC_cH_d$	110.7	∠$C_aC_bC_c$	124.3			
l-Propenyl chloride	CH_3—C_bH=C_aH—Cl	C_a—Cl	1.728				MW
	∠C_bC_aCl	121.9	*trans* conformer				
Propiolaldehyde	H_aC_a≡C_b—C_cH_cO		C_a—H_a	1.085			ED, MW
	C_a—C_b	1.211	C_b—C_c	1.453			
	C_c—H_c	1.130	C_c—O	1.214			
	∠C_bC_cO	124.2	∠$C_bC_cH_c$	113.7			
	∠$C_aC_bC_c$	178.6	planar				
Propylene → Propene							
Propylene oxide			C_a—C_b	1.51			MW
			∠$C_aC_bC_c$	121.0			
			dihedral angle between the C_bC_cO plane and the C_aC_b bond	123.8			
Propynal → Propiolaldehyde							
Propyne	H_3C_c—C_b≡C_aH		C_c—H	1.105			MW
	C_c—C_b	1.459	C_b—C_a	1.206			
	C_a—H	1.056	∠HC_cC_b	110.2			
Pyrazine			C—C	1.339	C—N	1.403	ED
			C—H	1.115	∠CCN	115.6	
			∠CCH	123.9			
Pyridazine			N—C_a	1.341			ED, MW
			C_a—C_b	1.393			
			N—N	1.330			
			C_b—C_b	1.375			
	∠NCC	123.7	∠NNC	119.3			

Compound	Structure						Method
Pyridine			$N—C_a$			1.340	MW
			$C_b—C_c$			1.394	
			$C_b—H_b$			1.081	
			$C_a—C_b$			1.395	
			$C_a—H_a$			1.084	
			$C_c—H_c$			1.077	
	$\angle C_aNC_a$	116.8	$\angle NC_aC_b$			123.9	
	$\angle C_aC_bC_c$	118.5	$\angle C_bC_cC_b$			118.3	
	$\angle NC_aH_a$	115.9	$\angle C_cC_bH_b$			121.3	
Pyrimidine			N—C	1.340	C—C	1.393	ED
			∠NCN	127.6	∠CNC	115.5	
	(C_{2v} assumed)						
Pyrrole			N—Ca			1.370	MW
			$C_b—C_b$			1.417	
			$C_a—C_b$			1.382	
			N—H			0.996	
			$C_a—H_a$			1.076	
	$C_b—H_b$	1.077	$\angle C_aNC_a$			109.8	
	$\angle NC_aC_b$	107.7	$\angle C_aC_bC_b$			107.4	
	$\angle NC_aH_a$	121.5	$\angle C_bC_bH$			127.1	
Pyruvonitrile			C—H			1.12	ED, MW
			C—N			1.17	
			C—O			1.208	
			$C_b—C_c$			1.477	
	$C_a—C_b$	1.518	∠HCH			109.2	
	$\angle C_aC_bO$	124.5	$\angle C_aC_bC_c$			114.2	
	∠CCN	179					
Ruthenocene → Bis (cyclopentadienyl) ruthenium							
Silacyclobutane			Si—C			1.892	ED
			C—C			1.600	
			Si—H			1.47	
	C—H	1.14	∠CSiC			80.7	
	∠SiCC	84.8	∠CCC			99.8	
	dihedral angle between the CCC and CSiC planes					146	
Spiropentane			$C_b—C_b$			1.52	ED
			$C_a—C_b$			1.47	
			C—H			1.09	
			$\angle C_bC_aC_b$			62	
	∠HCH	118	(D_{2d})				
Succinonitrile	CH_2CN	C—C	1.561	C—C(N)		1.465	ED
	CH_2CN	C—N	1.161	C—H		1.09	
		∠CCC	110.4				
	fraction of the *anti* conformer at 170°C 74%,						
	dihedral angle of CCCC for the *gauche* conformer					75	
Tetrachloroethylene	C—Cl	1.718	C—C			1.354	ED
$CCl_2=CCl_2$	∠ClCCl	115.7					
Tetracyanoethylene	C—N	1.162	C—C			1.435	ED
$(CN)_2C=C(CN)_2$	C=C	1.357	∠CC=C			121.1	
Tetrafluoro-1,3-dithietane			C—S			1.785	ED
			C—F			1.314	
			∠CSC			83.2	
	∠FCS	113.7	(D_{2h} assumed)				
Tetrafluoroethylene	C—C	1.31	C—F			1.319	ED
$CF_2=CF_2$	∠CCF	123.8	(D_{2h} assumed)				

Compound	Structure						Method
Tetrahydrofuran	C—H	1.115	C—O		1.428		ED
	C—C	1.536					
	The skeletal bending vibration of the molecular plane is essentially free pseudorotation						
Tetrahydropyran			C—O		1.420		ED
			C—C		1.531		
			C—H		1.116		
			∠COC		111.5		
			∠OCC		111.8		
	∠CCC (C)	108	∠CCC (O)		111		
	chair form						
Tetrahydrothiophene	C—S	1.839	C—H		1.120		
	C—C	1.536	∠CSC		93.4		
	∠SCC	106.1	∠CCC		105.0		
Tetramethylgermane	Ge—C	1.945	C—H		1.12		ED
$(CH_3)_4Ge$	∠GeCH	108	(T_d excluding the H atoms)				
Tetramethyllead	Pb—C	2.238	(T_d excluding the H atoms)				ED
$(CH_3)_4Pb$							
Tetramethylsilane	C—H	1.115	C—Si		1.875		ED
$(CH_3)_4Si$	∠HCH	109.8	(T_d excluding the H atoms)				
Tetramethylstannane	C—Sn	2.144					ED
$(CH_3)_4Sn$	C—H	1.12	(T_d excluding the H atoms)				
1,2,5-Thiadiazole		S—N	1.631	∠NSN		99.6	MW
		C—N	1.328	∠CCN		113.8	
		C—C	1.420	∠CCH		126.2	
		C—H	1.079	planar			
1,3,4-Thiadiazole		S—C	1.721	∠CSC		86.4	MW
		N—N	1.371	∠SCN		114.6	
		C—N	1.302	∠CCN		112.2	
		C—H	1.08	∠SCH		121.9	
		∠NCH	123.5			planar	
Thietane			C—S		1.847		ED, MW
			C—C		1.549		
			C—H (average)		1.100		
	∠CSC	76.8	∠HCH (average)		112		
	dihedral angle between the CCC and CSC planes				154		
Thiirane		C—C	1.484	∠HCH		116	MW
		C—H	1.083	∠CSC		48.3	
		C—S	1.815	∠CCS		65.9	
		dihedral angle between the CH_2 plane and the C—C bond		152			
Thioformaldehyde	C—S	1.611	C—H		1.093		MW
CH_2S	∠HCH	116.9					
Thioformamide			$N—H_a$		1.002		MW
			$N—H_b$		1.007		
			C—N		1.358		
	C—S	1.626	$C—H_c$		1.10		
	$∠H_aNH_b$	121.7	$∠H_aNC$		117.9		
	$∠H_bNC$	120.4	∠NCS		125.3		
	$∠NCH_c$	108	$∠SCH_c$		127		

Thiolane → Tetrahydrothiophene

Compound	Structure					Method
Thiophene			C_a—H_a	1.078		MW
			C_b—H_b	1.081		
			C_a—S	1.714		
			C_a—C_b	1.370		
			C_b—C_b	1.423		
			$\angle C_aSC_a$	92.2		
	$\angle SC_aC_b$	115.5	$\angle C_aC_bC_b$	112.5		
	$\angle SC_aH_a$	119.9	$\angle C_bC_bH_b$	124.3		
Toluene		C—C (ring)	1.399	$C—CH_3$	1.524	ED
		C—H (average)	1.11			
		the difference between the C—H(CH_3) and C—H(ring): about 0.01				
1,1,1-Tribromoethane	C—Br	1.93	C—H	1.095 (assumed)		MW
CH_3CBr_3	C—C	1.51 (assumed)	$\angle$CCBr	108		
	$\angle$BrCBr	111	$\angle$CCH	109.0 (assumed)		
Tribromomethane → Bromoform						
Tri-*tert*-butyl methane	C_a—C_b	1.611	C—H	1.111		ED
$HC_a[C_b(C_cH_3)_3]_3$	C_b—C_c	1.548	$\angle C_aC_bC_c$	113.0		
Tricarbon dioxide	C—O	1.163	C—C	1.289		ED
OCCCO	linear (with a large-amplitude bending vibration)					
Trichloroacetonitrile	C—N	1.165	C—C	1.460		ED
CCl_3CN	C—Cl	1.763	$\angle$ClCCl	110.0		
1,1,1-Trichloroethane	C—H	1.090	C—C	1.541		MW
CH_3CCl_3	C—Cl	1.771	$\angle$HCH	110.0		
	$\angle$CCH	108.9	$\angle$ClCCl	109.4		
	$\angle$CCCl	109.6				
Trichloro(methyl)germane	Ge—Cl	2.132	Ge—C	1.89		ED, MW
CH_3GeCl_3	C—H	1.103 (assumed)	$\angle$ClGeCl	106.4		
	$\angle$GeCH	110.5 (assumed)				
Trichloro(methyl)silane	C—Si	1.876	Si—Cl	2.021		MW
CH_3SiCl_3			(C_{3v})			
Trichloro(methyl)stannane	Sn—Cl	2.304	Sn—C	2.10		ED
CH_3SnCl_3	C—H	1.100	$\angle$CSnCl	113.9		
	$\angle$ClSnCl	104.7	$\angle$SnCH	108		
Triethylenediamine → 1,4-Diazabicyclo [2.2.2]octane						
Trifluoroacetic acid			C—F	1.325		ED
			C—C	1.546		
			$C—O_a$	1.192		
	$C—O_b$	1.35	O—H	0.96 (assumed)		
	$\angle CCO_a$	126.8	$\angle CCO_b$	111.1		
	$\angle$CCF	109.5				
1,1,1-Trifluoroethane	C—C	1.494	C—F	1.340		ED
CH_3CF_3	C—H	1.081	$\angle$CCF	119.2		
	$\angle$CCH	112				
Trifluoromethane → Fluoroform						
1,1,1-Trifluoro-2,2,2-trichloroethane	C—C	1.54	C—F	1.33		MW
CF_3CCl_3	C—Cl	1.77	$\angle$CCF	110		
	$\angle$CCCl	109.6	staggered conformation			
Trimethylaluminium	C—H	1.113	Al—C	1.957		ED
$(CH_3)_3Al$	$\angle$AlCH	111.7	$\angle$CAlC	120		
Trimethylamine	C—N	1.458	C—H	1.100		ED
$(CH_3)_3N$	$\angle$CNC	110.9	$\angle$HCH	110		
Trimethylarsine	C—As	1.979	$\angle$CAsC	98.8		ED
$(CH_3)_3As$	$\angle$AsCH	111.4				
Trimethylbismuth	Bi—C	2.263	C—H	1.07		ED
$(CH_3)_3Bi$	$\angle$CBiC	97.1				
Trimethylborane	C—B	1.578	C—H	1.114		ED
$(CH_3)_3B$	$\angle$CBC	120.0	$\angle$BCH	112.5		

Compound	Structure				Method
Trimethyleneimine → Azetidine					
Trimethylphosphine	C—P	1.847	C—H	1.091	ED
$(CH_3)_3P$	∠CPC	98.6	∠PCH	110.7	
1,3,5-Trioxane			C—O	1.422	MW
			∠OCO	112.2	
			∠COC	110.3	
Triphenylamine	C—C	1.392	C—N	1.42	ED
$(C_6H_5)_3N$	∠CNC	116	(C_3)		
	torsional dihedral angle of the two phenyl rings 47° (defined to be 0 when the symmetry axis is contained in the phenyl planes)				
Tropone			C_a—O	1.23	ED
			C_a—C_b	1.45	
			C_b—C_c	1.36	
			C_c—C_d	1.46	
			C_d—C_d	1.34	
			∠$C_bC_aC_b$	122	
			∠$C_aC_bC_c$	133	
	∠$C_bC_cC_d$	126	∠$C_cC_dC_d$	130	
				(C_{2v})	
Vinylacetylene			C_b—C_c	1.434	ED, MW
			C_a—C_b	1.344	
			C_c—C_d	1.215	
			C_a—H_a	1.11	
			C_d—H_d	1.09	
			∠$C_aC_bC_c$	123.1	
	∠$C_bC_cC_d$	178	∠$H_aC_aC_b$	119	
	∠$H_bC_aC_b$	122	∠$H_cC_bC_a$	122	
	∠$C_cC_dH_d$	182			
Vinyl chloride			C—C	1.342	ED, MW
			C—Cl	1.730	
			C—H	1.09	
	∠CCCl	122.5	∠CCH_a	124	
	∠CCH_b	120	∠CCH_c	121.1	

DIPOLE MOMENTS

This table gives values of the electric dipole moment for about 800 molecules. When available, values determined by microwave spectroscopy, molecular beam electric resonance, and other high-resolution spectroscopic techniques were selected. Otherwise, the values come from measurements of the dielectric constant in the gas phase or, if these do not exist, in the liquid phase. Compounds are listed by molecular formula in Hill order; compounds not containing carbon are listed first, followed by compounds containing carbon.

The dipole moment μ is given in debye units (D). The conversion factor to SI units is 1 D = 3.33564×10^{-30} C m.

Dipole moments of individual conformers (rotational isomers) are given when they have been measured. The conformers are designated as *gauche*, *trans*, *axial*, etc. The meaning of these terms can be found in the references. In some cases an average value, obtained from measurements on the bulk gas, is also given. Other information on molecules that have been studied by spectroscopy, such as the components of the dipole moment in the molecular framework and the variation with vibrational state and isotopic species, is given in References 1 and 2.

When the accuracy of a value is explicitly stated (i.e., 1.234 ± 0.005), the stated uncertainty generally indicates two or three standard deviations. When no uncertainty is given, the value may be assumed to be precise to a few units in the last decimal place. However, if more than three decimal places are given, the exact interpretation of the final digits may require analysis of the vibrational averaging.

Values measured in the gas phase that are questionable because of undetermined error sources are indicated as approximate (≈). Values obtained by liquid phase measurements, which sometimes have large errors because of association effects, are enclosed in brackets, e.g., [1.8].

References

1. Nelson, R. D., Lide, D. R., and Maryott, A. A., *Selected Values of Electric Dipole Moments for Molecules in the Gas Phase*, Natl. Stand. Ref. Data Ser. - Nat. Bur. Stnds. 10, 1967.
2. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series*, II/6 (1974), II/14a (1982), II/14b (1983), II/19c (1992), Springer-Verlag, Heidelberg.
3. Riddick, J. A., Bunger, W. B., and Sakano, T. K., *Organic Solvents, Fourth Edition*, John Wiley & Sons, New York, 1986.

Mol. form.	Name	μ/D
Compounds not containing carbon		
AgBr	Silver(I) bromide	5.62 ± 0.03
AgCl	Silver(I) chloride	6.08 ± 0.06
AgF	Silver(I) fluoride	6.22 ± 0.30
AgI	Silver(I) iodide	4.55 ± 0.05
AlF	Aluminum monofluoride	1.53 ± 0.15
$AsCl_3$	Arsenic(III) chloride	1.59 ± 0.08
AsF_3	Arsenic(III) fluoride	2.59 ± 0.05
AsH_3	Arsine	0.217 ± 0.003
$BClH_2$	Chloroborane	0.75 ± 0.05
BF	Fluoroborane(1)	≈0.5
BF_2H	Difluoroborane	0.971 ± 0.010
B_4H_{10}	Tetraborane	0.486 ± 0.002
B_5H_9	Pentaborane(9)	2.13 ± 0.04
B_6H_{10}	Hexaborane	2.50 ± 0.05
BaO	Barium oxide	7.954 ± 0.003
BaS	Barium sulfide	10.86 ± 0.02
BrCl	Bromine chloride	0.519 ± 0.004
BrF	Bromine fluoride	1.422 ± 0.016
BrF_3Si	Bromotrifluorosilane	0.83 ± 0.01
BrF_5	Bromine pentafluoride	1.51 ± 0.15
BrH	Hydrogen bromide	0.8272 ± 0.0003
BrH_3Si	Bromosilane	1.319
BrI	Iodine bromide	0.726 ± 0.003
BrK	Potassium bromide	10.628 ± 0.001
BrLi	Lithium bromide	7.268 ± 0.001
BrNO	Nitrosyl bromide	≈1.8
BrNa	Sodium bromide	9.1183 ± 0.0006
BrO	Bromine monoxide	1.76 ± 0.04
BrO_2	Bromine dioxide	2.8 ± 0.3
BrRb	Rubidium bromide	≈10.9
BrTl	Thallium(I) bromide	4.49 ± 0.05
CaCl	Calcium monochloride	≈3.6
ClCs	Cesium chloride	10.387 ± 0.004
ClF	Chlorine fluoride	0.888061
$ClFO_3$	Perchloryl fluoride	0.023 ± 0.001
ClF_3	Chlorine trifluoride	0.6 ± 0.10
ClF_3Si	Chlorotrifluorosilane	0.636 ± 0.004
$ClGeH_3$	Chlorogermane	2.13 ± 0.02
ClH	Hydrogen chloride	1.1086 ± 0.0003
ClHO	Hypochlorous acid	≈1.3
ClH_3Si	Chlorosilane	1.31 ± 0.01
ClI	Iodine chloride	1.24 ± 0.02
ClIn	Indium(I) chloride	3.79 ± 0.19
ClK	Potassium chloride	10.269 ± 0.001
ClLi	Lithium chloride	7.12887
$ClNO_2$	Nitryl chloride	0.53
ClNS	Thionitrosyl chloride	1.87 ± 0.02
ClNa	Sodium chloride	9.00117
ClO	Chlorine oxide	1.297 ± 0.001
ClRb	Rubidium chloride	10.510 ± 0.005
ClTl	Thallium(I) chloride	4.54299
Cl_2H_2Si	Dichlorosilane	1.17 ± 0.02
Cl_2OS	Thionyl chloride	1.45 ± 0.03
Cl_2O_2S	Sulfuryl chloride	1.81 ± 0.04
Cl_2S	Sulfur dichloride	0.36 ± 0.01
Cl_3FSi	Trichlorofluorosilane	0.49 ± 0.01
Cl_3HSi	Trichlorosilane	0.86 ± 0.01
Cl_3N	Nitrogen trichloride	0.39 ± 0.01
Cl_3OP	Phosphorus(V) oxychloride	2.54 ± 0.05
Cl_3P	Phosphorus(III) chloride	0.56 ± 0.02
CrO	Chromium monoxide	3.88 ± 0.13
CsF	Cesium fluoride	7.884 ± 0.001
CsNa	Cesium sodium	4.75 ± 0.20
CuF	Copper(I) fluoride	5.77 ± 0.29
CuO	Copper(II) oxide	4.5 ± 0.5
FGa	Gallium monofluoride	2.45 ± 0.05
$FGeH_3$	Fluorogermane	2.33 ± 0.12
FH	Hydrogen fluoride	1.826178
FHO	Hypofluorous acid	2.23 ± 0.11

Mol. form.	Name	μ/D
FH_2N	Fluoramide	2.27 ± 0.18
FH_3Si	Fluorosilane	1.2969 ± 0.0006
FI	Iodine fluoride	1.948 ± 0.020
FIn	Indium(I) fluoride	3.40 ± 0.07
FK	Potassium fluoride	8.585 ± 0.003
FLi	Lithium fluoride	6.3274 ± 0.0002
FNO	Nitrosyl fluoride	1.730 ± 0.003
FNO_2	Nitryl fluoride	0.466 ± 0.005
FNS	Thionitrosyl fluoride (NSF)	1.902 ± 0.012
FN_3	Fluorine azide	≈1.3
FNa	Sodium fluoride	8.156 ± 0.001
FO	Fluorine oxide	0.0043 ± 0.0004
FRb	Rubidium fluoride	8.5465 ± 0.0005
FS	Sulfur monofluoride	0.794 ± 0.02
FTl	Thallium(I) fluoride	4.2282 ± 0.0008
F_2Ge	Germanium(II) fluoride	2.61 ± 0.02
F_2HN	Difluoramine	1.92 ± 0.02
F_2H_2Si	Difluorosilane	1.55 ± 0.02
F_2N_2	*cis*-Difluorodiazine	0.16 ± 0.01
F_2O	Fluorine monoxide	0.308180
F_2OS	Thionyl fluoride	1.63 ± 0.01
F_2O_2	Fluorine dioxide	1.44 ± 0.07
F_2O_2S	Sulfuryl fluoride	1.12 ± 0.02
F_2S	Sulfur difluoride	1.05 ± 0.05
F_2Si	Difluorosilylene	1.23 ± 0.02
F_3HSi	Trifluorosilane	1.27 ± 0.03
$F_3H_3Si_2$	1,1,1-Trifluorodisilane	2.03 ± 0.10
F_3ISi	Trifluoroiodosilane	1.11 ± 0.03
F_3N	Nitrogen trifluoride	0.235 ± 0.004
F_3NO	Trifluoramine oxide	0.0390 ± 0.0004
F_3OP	Phosphorus(V) oxyfluoride	1.8685 ± 0.0001
F_3P	Phosphorus(III) fluoride	1.03 ± 0.01
F_3PS	Phosphorus(V) sulfide trifluoride	0.64 ± 0.02
F_4N_2	Tetrafluorohydrazine (*gauche*)	0.257 ± 0.002
F_4S	Sulfur tetrafluoride	0.632 ± 0.003
F_4Se	Selenium tetrafluoride	1.78 ± 0.09
F_5I	Iodine pentafluoride	2.18 ± 0.11
GeH_3N_3	Germylazide	2.579 ± 0.003
GeO	Germanium(II) oxide	3.2823 ± 0.0001
GeS	Germanium(II) sulfide	2.00 ± 0.06
GeSe	Germanium(II) selenide	1.65 ± 0.05
GeTe	Germanium(II) telluride	1.06 ± 0.07
HI	Hydrogen iodide	0.448 ± 0.001
HKO	Potassium hydroxide	7.415 ± 0.002
HLi	Lithium hydride	5.884 ± 0.001
HLiO	Lithium hydroxide	4.754 ± 0.002
HN	Imidogen	1.39 ± 0.07
HNO	Nitrosyl hydride	1.62 ± 0.03
HNO_2	Nitrous acid (*cis*)	1.423 ± 0.005
HNO_2	Nitrous acid (*trans*)	1.855 ± 0.016
HNO_3	Nitric acid	2.17 ± 0.02
HN_3	Hydrazoic acid	1.70 ± 0.09
HO	Hydroxyl	1.655 ± 0.001
HS	Mercapto	0.7580 ± 0.0001
H_2O	Water	1.8546 ± 0.0040
H_2O_2	Hydrogen peroxide	1.573 ± 0.001
H_2S	Hydrogen sulfide	0.97833
H_3N	Ammonia	1.4718 ± 0.0002
H_3NO	Hydroxylamine	0.59 ± 0.05
H_3P	Phosphine	0.5740 ± 0.0003
H_3Sb	Stibine	0.12 ± 0.05
H_4N_2	Hydrazine	1.75 ± 0.09
H_6OSi_2	Disiloxane	0.24 ± 0.02
IK	Potassium iodide	≈10.8
ILi	Lithium iodide	7.428 ± 0.001
INa	Sodium iodide	9.236 ± 0.003
IO	Iodine monoxide	2.45 ± 0.05
IRb	Rubidium iodide	≈11.5
ITl	Thallium(I) iodide	4.61 ± 0.07
KLi	Lithium potassium	3.45 ± 0.20
KNa	Potassium sodium	2.693 ± 0.014
LaO	Lanthanum monoxide	3.207 ± 0.011
LiNa	Lithium sodium	0.463 ± 0.002
LiO	Lithium monoxide	6.84 ± 0.03
LiRb	Lithium rubidium	4.0 ± 0.1
MgO	Magnesium oxide	6.2 ± 0.6
NO	Nitric oxide	0.15872
NO_2	Nitrogen dioxide	0.316 ± 0.010
NP	Phosphorus nitride	2.7470 ± 0.0001
NS	Nitrogen sulfide	1.81 ± 0.02
N_2O	Nitrous oxide	0.16083
N_2O_3	Nitrogen trioxide	2.122 ± 0.010
NaRb	Rubidium sodium	3.1 ± 0.3
OP	Phosphorus monoxide	1.88 ± 0.07
OPb	Lead(II) oxide	4.64 ± 0.50
OS	Sulfur monoxide	1.55 ± 0.02
OS_2	Sulfur oxide (SSO)	1.47 ± 0.03
OSi	Silicon monoxide	3.0982
OSn	Tin(II) oxide	4.32 ± 0.22
OSr	Strontium oxide	8.900 ± 0.003
OTi	Titanium(II) oxide	2.96 ± 0.05
OY	Yttrium monoxide	4.524 ± 0.007
OZr	Zirconium(II) oxide	2.55 ± 0.01
O_2S	Sulfur dioxide	1.63305
O_2Se	Selenium dioxide	2.62 ± 0.05
O_2Zr	Zirconium(IV) oxide	7.80 ± 0.02
O_3	Ozone	0.53373
PbS	Lead(II) sulfide	3.59 ± 0.18
SSi	Silicon monosulfide	1.73 ± 0.09
SSn	Tin(II) sulfide	3.18 ± 0.16
Compounds containing carbon		
$CBrF_3$	Bromotrifluoromethane	0.65 ± 0.05
CBr_2F_2	Dibromodifluoromethane	0.66 ± 0.05
$CClF_3$	Chlorotrifluoromethane	0.50 ± 0.01
CClN	Cyanogen chloride	2.8331 ± 0.0002
CCl_2F_2	Dichlorodifluoromethane	0.51 ± 0.05
CCl_2O	Carbonyl chloride	1.17 ± 0.01
CCl_3F	Trichlorofluoromethane	0.46 ± 0.02
CF	Fluoromethylidyne	0.645 ± 0.005
CFN	Cyanogen fluoride	2.120 ± 0.001
CF_2	Difluoromethylene	0.47 ± 0.02
CF_2O	Carbonyl fluoride	0.95 ± 0.01
CF_3I	Trifluoroiodomethane	1.048 ± 0.003
CH	Methylidyne	≈1.46
CHBrClF	Bromochlorofluoromethane	1.5 ± 0.3
$CHBr_3$	Tribromomethane	0.99 ± 0.02
$CHClF_2$	Chlorodifluoromethane	1.42 ± 0.03
$CHCl_2F$	Dichlorofluoromethane	1.29 ± 0.03
$CHCl_3$	Trichloromethane	1.04 ± 0.02
CHFO	Formyl fluoride	2.081 ± 0.001
CHF_2N	Carboimidic difluoride	1.393 ± 0.001
CHF_3	Trifluoromethane	1.65150

Mol. form.	Name	μ/D
CHN	Hydrogen cyanide	2.985188
CHN	Hydrogen isocyanide	3.05 ± 0.15
CHNO	Isocyanic acid (HNCO)	≈1.6
CHNO	Fulminic acid	3.09934
CH_2BrCl	Bromochloromethane	[1.66]
CH_2Br_2	Dibromomethane	1.43 ± 0.03
CH_2ClF	Chlorofluoromethane	1.82 ± 0.04
CH_2Cl_2	Dichloromethane	1.60 ± 0.03
CH_2F_2	Difluoromethane	1.9785 ± 0.02
CH_2I_2	Diiodomethane	[1.08]
CH_2N_2	Diazomethane	1.50 ± 0.01
CH_2N_2	Cyanamide	4.28 ± 0.10
CH_2N_4	1H-Tetrazole	2.19 ± 0.05
CH_2O	Formaldehyde	2.332 ± 0.002
CH_2O_2	Formic acid	1.425 ± 0.002
CH_2S	Thioformaldehyde	1.6491 ± 0.0004
CH_2Se	Selenoformaldehyde	1.41 ± 0.01
CH_3BCl_2	Dichloromethylborane	1.419 ± 0.013
CH_3BF_2	Difluoromethylborane	1.668 ± 0.003
CH_3BO	Borane carbonyl	1.698 ± 0.020
CH_3Br	Bromomethane	1.8203 ± 0.0004
CH_3Cl	Chloromethane	1.8963 ± 0.0002
CH_3Cl_3Si	Methyltrichlorosilane	1.91 ± 0.01
CH_3F	Fluoromethane	1.858 ± 0.002
CH_3F_2OP	Methylphosphonic difluoride	3.69 ± 0.26
CH_3F_2P	Methyldifluorophosphine	2.056 ± 0.006
CH_3F_3Si	Trifluoromethylsilane	2.3394 ± 0.0002
CH_3F_3Si	(Trifluoromethyl)silane	2.32 ± 0.02
CH_3I	Iodomethane	1.6406 ± 0.0004
CH_3NO	Formamide	3.73 ± 0.07
CH_3NO_2	Nitromethane	3.46 ± 0.02
CH_3N_3	Methyl azide	2.17 ± 0.04
CH_4O	Methanol	1.70 ± 0.02
CH_4O_2	Methylhydroperoxide	≈0.65
CH_4S	Methanethiol	1.52 ± 0.08
CH_5FSi	Fluoromethylsilane	1.700 ± 0.008
CH_5ISi	Iodomethylsilane	1.862 ± 0.005
CH_5N	Methylamine	1.31 ± 0.03
CH_6OSi	Methyl silyl ether	1.15 ± 0.02
CH_6Si	Methylsilane	0.73456
CH_8B_2	Methyldiborane(6)	0.566 ± 0.006
CIN	Cyanogen iodide	3.67 ± 0.02
CO	Carbon monoxide	0.10980
COS	Carbon oxysulfide	0.715189
COSe	Carbon oxyselenide	0.73 ± 0.02
CS	Carbon monosulfide	1.958 ± 0.005
CSe	Carbon monoselenide	1.99 ± 0.04
C_2BrF	Bromofluoroacetylene	0.448 ± 0.002
C_2ClF_3	Chlorotrifluoroethene	0.40 ± 0.10
C_2ClF_5	Chloropentafluoroethane	0.52 ± 0.05
$C_2Cl_2F_2$	1,1-Dichloro-2,2-difluoroethene	0.50
$C_2Cl_2F_4$	1,2-Dichloro-1,1,2,2-tetrafluoroethane	≈0.5
C_2F_3N	Trifluoroacetonitrile	1.262 ± 0.010
C_2F_3N	Trifluoroisocyanomethane	1.153 ± 0.010
C_2HBr	Bromoacetylene	0.22962
C_2HCl	Chloroacetylene	0.44408
C_2HCl_3	Trichloroethene	[0.8]
C_2HCl_5	Pentachloroethane	0.92 ± 0.05
C_2HF	Fluoroacetylene	0.7207 ± 0.0003
C_2HF_3	Trifluoroethene	1.32 ± 0.03

Mol. form.	Name	μ/D
$C_2HF_3O_2$	Trifluoroacetic acid	2.28 ± 0.25
C_2HI	Iodoacetylene	0.02525
$C_2H_2Br_4$	1,1,2,2-Tetrabromoethane	[1.38]
$C_2H_2Cl_2$	1,1-Dichloroethene	1.34 ± 0.01
$C_2H_2Cl_2$	*cis*-1,2-Dichloroethene	1.90 ± 0.04
$C_2H_2Cl_2O$	Chloroacetyl chloride	2.23 ± 0.11
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane	1.32 ± 0.07
$C_2H_2F_2$	1,1-Difluoroethene	1.3893 ± 0.0002
$C_2H_2F_2$	*cis*-1,2-Difluoroethene	2.42 ± 0.02
$C_2H_2F_4$	1,1,1,2-Tetrafluoroethane	1.80 ± 0.22
$C_2H_2N_2S$	1,2,5-Thiadiazole	1.579 ± 0.007
C_2H_2O	Ketene	1.42215
$C_2H_2O_2$	Glyoxal (*cis*)	4.8 ± 0.2
C_2H_3Br	Bromoethene	1.42 ± 0.03
C_2H_3Cl	Chloroethene	1.45 ± 0.03
$C_2H_3ClF_2$	1-Chloro-1,1-difluoroethane	2.14 ± 0.04
C_2H_3ClO	Acetyl chloride	2.72 ± 0.14
$C_2H_3Cl_3$	1,1,1-Trichloroethane	1.755 ± 0.015
$C_2H_3Cl_3$	1,1,2-Trichloroethane	[1.4]
C_2H_3F	Fluoroethene	1.468 ± 0.003
C_2H_3FO	Acetyl fluoride	2.96 ± 0.03
$C_2H_3F_3$	1,1,1-Trifluoroethane	2.3470 ± 0.005
C_2H_3HgN	Cyanomethylmercury	4.7 ± 0.1
C_2H_3I	Iodoethene	1.311 ± 0.005
C_2H_3N	Acetonitrile	3.92519
C_2H_3NO	Methyl cyanate	4.26 ± 0.18
C_2H_3NO	Methyl isocyanate	≈2.8
C_2H_3NS	Methyl isothiocyanate	3.453 ± 0.003
$C_2H_3N_3$	1H-1,2,4-Triazole	2.7 ± 0.1
C_2H_4BrCl	1-Bromo-2-chloroethane	[1.2]
$C_2H_4Br_2$	1,2-Dibromoethane	[1.19]
C_2H_4ClF	1-Chloro-1-fluoroethane	2.068 ± 0.014
$C_2H_4Cl_2$	1,1-Dichloroethane	2.06 ± 0.04
$C_2H_4Cl_2$	1,2-Dichloroethane	[1.83]
$C_2H_4F_2$	1,1-Difluoroethane	2.27 ± 0.05
$C_2H_4F_2$	1,2-Difluoroethane (*gauche*)	2.67 ± 0.13
C_2H_4O	Acetaldehyde	2.750 ± 0.006
C_2H_4O	Ethylene oxide	1.89 ± 0.01
$C_2H_4O_2$	Acetic acid	1.70 ± 0.03
$C_2H_4O_2$	Methyl formate	1.77 ± 0.04
$C_2H_4O_2$	Glycolaldehyde	2.73 ± 0.05
C_2H_5Br	Bromoethane	2.04 ± 0.02
C_2H_5Cl	Chloroethane	2.05 ± 0.02
C_2H_5ClO	2-Chloroethanol	1.78 ± 0.09
$C_2H_5Cl_3Si$	Trichloroethylsilane	[2.04]
C_2H_5F	Fluoroethane	1.937 ± 0.007
C_2H_5I	Iodoethane	1.976 ± 0.002
C_2H_5N	Ethyleneimine	1.90 ± 0.01
C_2H_5NO	Acetamide	3.68 ± 0.03
C_2H_5NO	*N*-Methylformamide	3.83 ± 0.08
$C_2H_5NO_2$	Nitroethane	3.23 ± 0.03
C_2H_6O	Ethanol (*gauche*)	1.68 ± 0.03
C_2H_6O	Ethanol (*trans*)	1.44 ± 0.03
C_2H_6O	Ethanol (*average*)	1.69 ± 0.03
C_2H_6O	Dimethyl ether	1.30 ± 0.01
C_2H_6OS	Dimethyl sulfoxide	3.96 ± 0.04
$C_2H_6O_2$	Ethylene glycol (*average*)	2.36 ± 0.10
C_2H_6S	Ethanethiol (*gauche*)	1.61 ± 0.08
C_2H_6S	Ethanethiol (*trans*)	1.58 ± 0.08
C_2H_6S	Dimethyl sulfide	1.554 ± 0.004
$C_2H_6S_2$	1,2-Ethanedithiol	2.03 ± 0.08

Mol. form.	Name	μ/D
$C_2H_6S_2$	Dimethyl disulfide	[1.85]
C_2H_6Si	Vinylsilane	0.657 ± 0.002
C_2H_7N	Ethylamine (*gauche*)	1.210 ± 0.015
C_2H_7N	Ethylamine (*trans*)	1.304 ± 0.011
C_2H_7N	Ethylamine (*average*)	1.22 ± 0.10
C_2H_7N	Dimethylamine	1.01 ± 0.02
C_2H_7NO	Ethanolamine	[2.27]
$C_2H_8N_2$	1,2-Ethanediamine	1.99 ± 0.10
C_3HF_3	3,3,3-Trifluoro-1-propyne	2.317 ± 0.013
C_3HN	Cyanoacetylene	3.73172
$C_3H_2F_2$	3,3-Difluorocyclopropene	2.98 ± 0.02
C_3H_2O	2-Propynal	2.78 ± 0.02
$C_3H_3Cl_2F$	1,1-Dichloro-2-fluoropropene	2.43 ± 0.02
C_3H_3F	3-Fluoropropyne	1.73 ± 0.02
$C_3H_3F_3$	3,3,3-Trifluoropropene	2.45 ± 0.05
C_3H_3N	Acrylonitrile	3.92 ± 0.07
C_3H_3NO	Oxazole	1.503 ± 0.030
C_3H_3NO	Isoxazole	2.95 ± 0.04
C_3H_4	Propyne	0.784 ± 0.001
C_3H_4	Cyclopropene	0.454 ± 0.010
$C_3H_4F_2$	1,1-Difluoro-1-propene	0.889 ± 0.007
$C_3H_4N_2$	1*H*-Pyrazole	2.20 ± 0.01
$C_3H_4N_2$	Imidazole	3.8 ± 0.4
C_3H_4O	Propargyl alcohol	1.13 ± 0.06
C_3H_4O	Acrolein (*trans*)	3.117 ± 0.004
C_3H_4O	Acrolein (*cis*)	2.552 ± 0.003
C_3H_4O	Cyclopropanone	2.67 ± 0.13
$C_3H_4O_2$	Vinyl formate	1.49 ± 0.01
$C_3H_4O_2$	2-Oxetanone	4.18 ± 0.03
$C_3H_4O_2$	3-Oxetanone	0.887 ± 0.005
$C_3H_4O_3$	Ethylene carbonate	[4.9]
C_3H_5Br	2-Bromopropene	[1.51]
C_3H_5Br	3-Bromopropene	≈1.9
C_3H_5Cl	*cis*-1-Chloropropene	1.67 ± 0.08
C_3H_5Cl	*trans*-1-Chloropropene	1.97 ± 0.10
C_3H_5Cl	2-Chloropropene	1.647 ± 0.010
C_3H_5Cl	3-Chloropropene	1.94 ± 0.10
C_3H_5ClO	Epichlorohydrin	[1.8]
C_3H_5F	*cis*-1-Fluoropropene	1.46 ± 0.03
C_3H_5F	*trans*-1-Fluoropropene	≈1.9
C_3H_5F	2-Fluoropropene	1.61 ± 0.03
C_3H_5F	3-Fluoropropene (*gauche*)	1.939 ± 0.015
C_3H_5F	3-Fluoropropene (*cis*)	1.765 ± 0.014
C_3H_5N	Propanenitrile	4.05 ± 0.03
C_3H_5NO	Ethyl cyanate	4.72 ± 0.09
C_3H_5NO	3-Hydroxypropanenitrile (*gauche*)	3.17 ± 0.02
C_3H_6	Propene	0.366 ± 0.001
$C_3H_6Br_2$	1,2-Dibromopropane	[1.2]
$C_3H_6Cl_2$	1,2-Dichloropropane	[1.85]
$C_3H_6Cl_2$	1,3-Dichloropropane	2.08 ± 0.04
C_3H_6O	Acetone	2.88 ± 0.03
C_3H_6O	Propanal (*gauche*)	2.86 ± 0.01
C_3H_6O	Propanal (*cis*)	2.52 ± 0.05
C_3H_6O	Propanal (*average*)	2.72
C_3H_6O	Allyl alcohol (*gauche*)	1.55 ± 0.08
C_3H_6O	Allyl alcohol (*average*)	1.60 ± 0.08
C_3H_6O	Methyl vinyl ether	0.965 ± 0.002
C_3H_6O	Methyloxirane	2.01 ± 0.02
C_3H_6O	Oxetane	1.94 ± 0.01
$C_3H_6O_2$	Propanoic acid (*cis*)	1.46 ± 0.07
$C_3H_6O_2$	Propanoic acid (*average*)	1.75 ± 0.09
$C_3H_6O_2$	Ethyl formate (*gauche*)	1.81 ± 0.02
$C_3H_6O_2$	Ethyl formate (*trans*)	1.98 ± 0.02
$C_3H_6O_2$	Ethyl formate (*average*)	1.93
$C_3H_6O_2$	Methyl acetate	1.72 ± 0.09
$C_3H_6O_2$	1,3-Dioxolane	1.19 ± 0.06
$C_3H_6O_2S$	Thietane 1,1-dioxide	4.8 ± 0.1
$C_3H_6O_3$	1,3,5-Trioxane	2.08 ± 0.02
C_3H_6S	Thietane	1.85 ± 0.09
C_3H_7Br	1-Bromopropane	2.18 ± 0.11
C_3H_7Br	2-Bromopropane	2.21 ± 0.11
C_3H_7Cl	1-Chloropropane (*gauche*)	2.02 ± 0.03
C_3H_7Cl	1-Chloropropane (*trans*)	1.95 ± 0.02
C_3H_7Cl	1-Chloropropane (*average*)	2.05 ± 0.04
C_3H_7Cl	2-Chloropropane	2.17 ± 0.11
C_3H_7F	1-Fluoropropane (*gauche*)	1.90 ± 0.10
C_3H_7F	1-Fluoropropane (*trans*)	2.05 ± 0.04
C_3H_7F	2-Fluoropropane	1.958 ± 0.001
C_3H_7I	1-Iodopropane	2.04 ± 0.10
C_3H_7I	2-Iodopropane	[1.95]
C_3H_7N	Allylamine	≈1.2
C_3H_7N	Cyclopropylamine	1.19 ± 0.01
C_3H_7N	Propyleneimine (*cis*)	1.77 ± 0.09
C_3H_7N	Propyleneimine (*trans*)	1.57 ± 0.03
C_3H_7NO	*N,N*-Dimethylformamide	3.82 ± 0.08
C_3H_7NO	*N*-Methylacetamide	[4.3]
$C_3H_7NO_2$	1-Nitropropane	3.66 ± 0.07
$C_3H_7NO_2$	2-Nitropropane	3.73 ± 0.07
C_3H_8	Propane	0.084 ± 0.001
C_3H_8O	1-Propanol (*gauche*)	1.58 ± 0.03
C_3H_8O	1-Propanol (*trans*)	1.55 ± 0.03
C_3H_8O	2-Propanol (*trans*)	1.58 ± 0.03
C_3H_8O	Ethyl methyl ether (*trans*)	1.17 ± 0.02
$C_3H_8O_2$	1,2-Propylene glycol	[2.25]
$C_3H_8O_2$	1,3-Propylene glycol	[2.55]
$C_3H_8O_2$	Ethylene glycol monomethyl ether (*gauche*)	2.36 ± 0.05
$C_3H_8O_2$	Dimethoxymethane	[0.74]
$C_3H_8O_3$	Glycerol	[2.56]
C_3H_8S	1-Propanethiol (*gauche*)	1.683 ± 0.010
C_3H_8S	1-Propanethiol (*trans*)	1.60 ± 0.08
C_3H_8S	2-Propanethiol (*gauche*)	1.53 ± 0.03
C_3H_8S	2-Propanethiol (*trans*)	1.61 ± 0.03
C_3H_8S	Ethyl methyl sulfide (*gauche*)	1.593 ± 0.004
C_3H_8S	Ethyl methyl sulfide (*trans*)	1.56 ± 0.03
C_3H_9N	Propylamine	1.17 ± 0.06
C_3H_9N	Isopropylamine	1.19 ± 0.06
C_3H_9N	Trimethylamine	0.612 ± 0.003
$C_3H_9O_4P$	Trimethyl phosphate	[3.18]
C_4H_4	1-Buten-3-yne	0.22 ± 0.02
C_4H_4	Methylenecyclopropene	1.90 ± 0.01
$C_4H_4N_2$	Succinonitrile	[3.7]
$C_4H_4N_2$	Pyrimidine	2.334 ± 0.010
$C_4H_4N_2$	Pyridazine	4.22 ± 0.02
C_4H_4O	Furan	0.66 ± 0.01
$C_4H_4O_2$	Diketene	3.53 ± 0.07
C_4H_4S	Thiophene	0.55 ± 0.01
C_4H_5N	2-Methylacrylonitrile	3.69 ± 0.18
C_4H_5N	Pyrrole	1.767 ± 0.001
C_4H_5N	Isocyanocyclopropane	4.03 ± 0.10
C_4H_5NO	2-Methyloxazole	1.37 ± 0.07
C_4H_5NO	4-Methyloxazole	1.08 ± 0.05

Mol. form.	Name	μ/D
C_4H_5NO	5-Methyloxazole	2.16 ± 0.04
C_4H_5NO	4-Methylisoxazole	3.583 ± 0.005
C_4H_6	1,2-Butadiene	0.403 ± 0.002
C_4H_6	1-Butyne	0.782 ± 0.004
C_4H_6	Cyclobutene	0.132 ± 0.001
C_4H_6O	Divinyl ether	0.78 ± 0.05
C_4H_6O	3-Methoxy-1,2-propadiene	0.963 ± 0.020
C_4H_6O	*trans*-2-Butenal	3.67 ± 0.07
C_4H_6O	2-Methylpropenal	2.68 ± 0.13
C_4H_6O	Cyclobutanone	2.89 ± 0.03
C_4H_6O	2,3-Dihydrofuran	1.32 ± 0.03
C_4H_6O	2,5-Dihydrofuran	1.63 ± 0.01
$C_4H_6O_2$	*trans*-Crotonic acid	[2.13]
$C_4H_6O_2$	Methacrylic acid	[1.65]
$C_4H_6O_2$	Vinyl acetate	[1.79]
$C_4H_6O_2$	Methyl acrylate	[1.77]
$C_4H_6O_2$	γ-Butyrolactone	4.27 ± 0.03
$C_4H_6O_2$	2,3-Dihydro-1,4-dioxin	0.939 ± 0.008
$C_4H_6O_2$	3,6-Dihydro-1,2-dioxin	2.329 ± 0.001
$C_4H_6O_3$	Acetic anhydride	≈2.8
$C_4H_6O_3$	Propylene carbonate	[4.9]
C_4H_6S	2,3-Dihydrothiophene	1.61 ± 0.20
C_4H_6S	2,5-Dihydrothiophene	1.75 ± 0.01
C_4H_7N	Butanenitrile (*gauche*)	3.91 ± 0.04
C_4H_7N	Butanenitrile (*anti*)	3.73 ± 0.06
C_4H_7N	2-Methylpropanenitrile	4.29 ± 0.09
C_4H_7N	2-Isocyanopropane	4.055 ± 0.001
C_4H_7NO	2-Pyrrolidone	[3.5]
C_4H_8	1-Butene (*cis*)	0.438 ± 0.007
C_4H_8	1-Butene (*skew*)	0.359 ± 0.011
C_4H_8	*cis*-2-Butene	0.253 ± 0.005
C_4H_8	Isobutene	0.503 ± 0.010
C_4H_8	Methylcyclopropane	0.139 ± 0.004
$C_4H_8Cl_2$	1,4-Dichlorobutane	2.22 ± 0.11
$C_4H_8Cl_2O$	Bis(2-chloroethyl) ether	[2.58]
C_4H_8O	*cis*-2-Buten-1-ol	1.96 ± 0.03
C_4H_8O	*trans*-2-Buten-1-ol	1.90 ± 0.02
C_4H_8O	2-Methyl-2-propenol (*skew*)	1.295 ± 0.022
C_4H_8O	Ethyl vinyl ether	[1.26]
C_4H_8O	1,2-Epoxybutane	1.891 ± 0.011
C_4H_8O	Butanal	2.72 ± 0.05
C_4H_8O	Isobutanal (*gauche*)	2.69 ± 0.01
C_4H_8O	Isobutanal (*trans*)	2.86 ± 0.01
C_4H_8O	2-Butanone	2.779 ± 0.015
C_4H_8O	Tetrahydrofuran	1.75 ± 0.04
C_4H_8OS	1,4-Oxathiane	0.295 ± 0.003
$C_4H_8O_2$	Butanoic acid	[1.65]
$C_4H_8O_2$	2-Methylpropanoic acid	[1.08]
$C_4H_8O_2$	Propyl formate	[1.89]
$C_4H_8O_2$	Ethyl acetate	1.78 ± 0.09
$C_4H_8O_2$	*cis*-2-Butene-1,4-diol	[2.48]
$C_4H_8O_2$	*trans*-2-Butene-1,4-diol	[2.45]
$C_4H_8O_2$	1,3-Dioxane	2.06 ± 0.04
$C_4H_8O_2S$	Sulfolane	[4.8]
C_4H_8S	3-Methylthietane	2.046 ± 0.009
C_4H_8S	Tetrahydrothiophene	[1.90]
$C_4H_8S_2$	1,3-Dithiane	2.14 ± 0.04
C_4H_9Br	1-Bromobutane	2.08 ± 0.10
C_4H_9Br	2-Bromobutane	2.23 ± 0.11
C_4H_9Br	2-Bromo-2-methylpropane	[2.17]
C_4H_9Cl	1-Chlorobutane	2.05 ± 0.04
C_4H_9Cl	2-Chlorobutane	2.04 ± 0.10
C_4H_9Cl	1-Chloro-2-methylpropane	2.00 ± 0.10
C_4H_9Cl	2-Chloro-2-methylpropane	2.13 ± 0.04
C_4H_9I	1-Iodobutane	[1.93]
C_4H_9I	2-Iodobutane	2.12 ± 0.11
C_4H_9I	1-Iodo-2-methylpropane	[1.87]
C_4H_9N	Pyrrolidine	[1.57]
C_4H_9NO	*N*-Methylpropanamide	3.61
C_4H_9NO	*N,N*-Dimethylacetamide	[3.7]
C_4H_9NO	Morpholine	1.55 ± 0.03
C_4H_{10}	Isobutane	0.132 ± 0.002
$C_4H_{10}O$	1-Butanol	1.66 ± 0.03
$C_4H_{10}O$	2-Butanol	[1.8]
$C_4H_{10}O$	2-Methyl-1-propanol	1.64 ± 0.08
$C_4H_{10}O$	2-Methyl-2-propanol	[1.66]
$C_4H_{10}O$	Diethyl ether	1.15 ± 0.02
$C_4H_{10}O$	Methyl propyl ether (*trans-trans*)	1.107 ± 0.013
$C_4H_{10}O$	Isopropyl methyl ether	1.247 ± 0.003
$C_4H_{10}O_2$	1,4-Butanediol	[2.58]
$C_4H_{10}O_2$	Ethylene glycol monoethyl ether	[2.08]
$C_4H_{10}O_3$	Diethylene glycol	[2.31]
$C_4H_{10}S$	1-Butanethiol	[1.53]
$C_4H_{10}S$	2-Methyl-2-propanethiol	1.66 ± 0.03
$C_4H_{10}S$	Diethyl sulfide	1.54 ± 0.08
$C_4H_{11}N$	Butylamine	≈1.0
$C_4H_{11}N$	*sec*-Butylamine	[1.28]
$C_4H_{11}N$	*tert*-Butylamine	[1.29]
$C_4H_{11}N$	Isobutylamine	[1.27]
$C_4H_{11}N$	Diethylamine	0.92 ± 0.05
$C_4H_{11}NO_2$	Diethanolamine	[2.8]
$C_4H_{13}N_3$	Diethylenetriamine	[1.89]
C_5F_5N	Perfluoropyridine	0.98 ± 0.08
C_5H_3NS	2-Thiophenecarbonitrile	4.59 ± 0.02
C_5H_3NS	3-Thiophenecarbonitrile	4.13 ± 0.02
C_5H_4	1,3-Pentadiyne	1.207 ± 0.001
C_5H_4ClN	4-Chloropyridine	0.756 ± 0.005
C_5H_4FN	3-Fluoropyridine	2.09 ± 0.26
C_5H_4O	2,4-Cyclopentadien-1-one	3.132 ± 0.007
C_5H_4OS	4H-Pyran-4-thione	3.95 ± 0.05
$C_5H_4O_2$	Furfural	[3.54]
$C_5H_4O_2$	4H-Pyran-4-one	3.79 ± 0.02
$C_5H_4S_2$	4H-Thiopyran-4-thione	3.9 ± 0.2
C_5H_5N	Pyridine	2.215 ± 0.010
C_5H_6	1,2,3-Pentatriene	0.51 ± 0.05
C_5H_6	1-Penten-3-yne	0.66 ± 0.02
C_5H_6	*cis*-3-Penten-1-yne	0.78 ± 0.02
C_5H_6	*trans*-3-Penten-1-yne	1.06 ± 0.05
C_5H_6	2-Methyl-1-buten-3-yne	0.513 ± 0.02
C_5H_6	1,3-Cyclopentadiene	0.419 ± 0.004
$C_5H_6N_2$	2-Methylpyrimidine	1.676 ± 0.010
$C_5H_6N_2$	5-Methylpyrimidine	2.881 ± 0.006
C_5H_6O	2-Methylfuran	0.65 ± 0.05
C_5H_6O	3-Methylfuran	1.03 ± 0.02
C_5H_6O	3-Cyclopenten-1-one	2.79 ± 0.03
$C_5H_6O_2$	5-Methyl-2(3H)-furanone	4.08 ± 0.02
$C_5H_6O_2$	Furfuryl alcohol	[1.92]
C_5H_6S	2-Methylthiophene	0.674 ± 0.005
C_5H_6S	3-Methylthiophene	0.914 ± 0.015
C_5H_7N	3-Methyl-2-butenenitrile	4.61 ± 0.13
C_5H_7N	Cyclobutanecarbonitrile	4.04 ± 0.04
$C_5H_7NO_2$	Ethyl cyanoacetate	[2.17]

Mol. form.	Name	μ/D
C_5H_8	*cis*-1,3-Pentadiene	0.500 ± 0.015
C_5H_8	*trans*-1,3-Pentadiene	0.585 ± 0.010
C_5H_8	2-Methyl-1,3-butadiene	0.25 ± 0.01
C_5H_8	1-Pentyne (*gauche*)	0.769 ± 0.028
C_5H_8	1-Pentyne (*trans*)	0.842 ± 0.010
C_5H_8	Cyclopentene	0.20 ± 0.02
C_5H_8	3,3-Dimethylcyclopropene	0.287 ± 0.003
C_5H_8O	Cyclopropyl methyl ketone	2.62 ± 0.25
C_5H_8O	Cyclopentanone	≈3.3
C_5H_8O	3,4-Dihydro-2H-pyran	1.400 ± 0.008
C_5H_8O	3,6-Dihydro-2H-pyran	1.283 ± 0.005
$C_5H_8O_2$	Ethyl acrylate	[1.96]
$C_5H_8O_2$	Methyl methacrylate	[1.67]
$C_5H_8O_2$	2,4-Pentanedione	[2.78]
$C_5H_8O_2$	Dihydro-3-methyl-2(3H)-furanone	4.56 ± 0.02
$C_5H_8O_2$	Dihydro-5-methyl-2(3H)-furanone	4.71 ± 0.05
$C_5H_8O_2$	Tetrahydro-4H-pyran-4-one	1.720 ± 0.003
C_5H_9N	Pentanenitrile	4.12 ± 0.08
C_5H_9N	2,2-Dimethylpropanenitrile	3.95 ± 0.04
C_5H_9N	1,2,5,6-Tetrahydropyridine	1.007 ± 0.003
C_5H_9NO	*N*-Methyl-2-pyrrolidone	[4.1]
C_5H_{10}	1-Pentene	≈0.5
C_5H_{10}	3-Methyl-1-butene (*gauche*)	0.398 ± 0.004
C_5H_{10}	3-Methyl-1-butene (*trans*)	0.320 ± 0.010
C_5H_{10}	1,1-Dimethylcyclopropane	0.142 ± 0.001
$C_5H_{10}O$	2,2-Dimethylpropanal	2.66 ± 0.05
$C_5H_{10}O$	2-Pentanone	[2.70]
$C_5H_{10}O$	3-Pentanone	[2.82]
$C_5H_{10}O$	Tetrahydropyran (*chair*)	1.58 ± 0.03
$C_5H_{10}O_2$	Pentanoic acid	[1.61]
$C_5H_{10}O_2$	3-Methylbutanoic acid	[0.63]
$C_5H_{10}O_2$	Butyl formate	[2.03]
$C_5H_{10}O_2$	Isobutyl formate	[1.88]
$C_5H_{10}O_2$	Propyl acetate	[1.78]
$C_5H_{10}O_2$	Ethyl propanoate	[1.74]
$C_5H_{10}O_2$	Tetrahydrofurfuryl alcohol	[2.1]
$C_5H_{10}O_3$	Diethyl carbonate	1.10 ± 0.06
$C_5H_{10}O_3$	Ethylene glycol monomethyl ether acetate	[2.13]
$C_5H_{10}O_3$	Ethyl lactate	[2.4]
$C_5H_{10}S$	Thiacyclohexane	1.781 ± 0.010
$C_5H_{11}Br$	1-Bromopentane	2.20 ± 0.11
$C_5H_{11}Cl$	1-Chloropentane	2.16 ± 0.11
$C_5H_{11}Cl$	1-Chloro-3-methylbutane	[1.92]
$C_5H_{11}N$	Piperidine (*equitorial*)	0.82 ± 0.02
$C_5H_{11}N$	Piperidine (*axial*)	1.19 ± 0.02
$C_5H_{11}N$	Piperidine (*average*)	[1.19]
$C_5H_{11}N$	*N*-Methylpyrrolidine	0.572 ± 0.003
C_5H_{12}	Isopentane	0.13 ± 0.05
$C_5H_{12}N_2O$	Tetramethylurea	[3.5]
$C_5H_{12}O$	1-Pentanol	[1.7]
$C_5H_{12}O$	2-Pentanol	[1.66]
$C_5H_{12}O$	3-Pentanol	[1.64]
$C_5H_{12}O$	2-Methyl-1-butanol	[1.88]
$C_5H_{12}O$	2-Methyl-2-butanol	[1.82]
$C_5H_{12}O_2$	1,5-Pentanediol	[2.5]
$C_5H_{12}O_3$	Diethylene glycol monomethyl ether	[1.6]
$C_6H_2F_4$	1,2,3,4-Tetrafluorobenzene	2.42 ± 0.05
$C_6H_2F_4$	1,2,3,5-Tetrafluorobenzene	1.46 ± 0.06
$C_6H_3F_3$	1,2,4-Trifluorobenzene	1.402 ± 0.009
$C_6H_4ClNO_2$	1-Chloro-2-nitrobenzene	4.64 ± 0.09
$C_6H_4ClNO_2$	1-Chloro-3-nitrobenzene	3.73 ± 0.07
$C_6H_4ClNO_2$	1-Chloro-4-nitrobenzene	2.83 ± 0.06
$C_6H_4Cl_2$	*o*-Dichlorobenzene	2.50 ± 0.05
$C_6H_4Cl_2$	*m*-Dichlorobenzene	1.72 ± 0.09
$C_6H_4FNO_2$	1-Fluoro-4-nitrobenzene	2.87 ± 0.06
$C_6H_4F_2$	*o*-Difluorobenzene	2.46 ± 0.05
$C_6H_4F_2$	*m*-Difluorobenzene	1.51 ± 0.02
$C_6H_4N_2$	2-Pyridinecarbonitrile	5.78 ± 0.11
$C_6H_4N_2$	3-Pyridinecarbonitrile	3.66 ± 0.11
$C_6H_4N_2$	4-Pyridinecarbonitrile	1.96 ± 0.03
$C_6H_4O_2$	3,5-Cyclohexadiene-1,2-dione	4.23 ± 0.02
C_6H_5Br	Bromobenzene	1.70 ± 0.03
C_6H_5Cl	Chlorobenzene	1.69 ± 0.03
C_6H_5ClO	*p*-Chlorophenol	2.11 ± 0.11
C_6H_5F	Fluorobenzene	1.60 ± 0.08
C_6H_5I	Iodobenzene	1.70 ± 0.09
C_6H_5NO	2-Pyridinecarboxaldehyde	3.56 ± 0.07
C_6H_5NO	3-Pyridinecarboxaldehyde	1.44
C_6H_5NO	4-Pyridinecarboxaldehyde	1.66
$C_6H_5NO_2$	Nitrobenzene	4.22 ± 0.08
C_6H_6	Fulvene	0.4236 ± 0.013
C_6H_6ClN	*o*-Chloroaniline	[1.77]
C_6H_6O	Phenol	1.224 ± 0.008
C_6H_6O	2-Vinylfuran	0.69 ± 0.07
$C_6H_6O_2$	*p*-Hydroquinone	2.38 ± 0.05
C_6H_6S	Benzenethiol	[1.23]
C_6H_7N	Aniline	1.13 ± 0.02
C_6H_7N	2-Methylpyridine	1.85 ± 0.04
C_6H_7N	3-Methylpyridine	[2.40]
C_6H_7N	4-Methylpyridine	2.70 ± 0.02
C_6H_8O	3-Methyl-2-cyclopenten-1-one	4.33 ± 0.002
$C_6H_8O_4$	Dimethyl maleate	[2.48]
C_6H_8Si	Phenylsilane	0.845 ± 0.012
C_6H_9F	1-Fluorocyclohexene	1.942 ± 0.010
C_6H_{10}	1-Hexyne	0.83 ± 0.05
C_6H_{10}	3,3-Dimethyl-1-butyne	0.661 ± 0.004
C_6H_{10}	Cyclohexene (*half-chair*)	0.332 ± 0.012
$C_6H_{10}F_2$	1,1-Difluorocyclohexane	2.556 ± 0.010
$C_6H_{10}O$	3-Methylcyclopentanone	3.14 ± 0.03
$C_6H_{10}O$	Cyclohexanone	3.246 ± 0.006
$C_6H_{10}O$	Mesityl oxide	[2.79]
$C_6H_{10}O_4$	Diethyl oxalate	[2.49]
$C_6H_{10}O_4$	Ethylene glycol diacetate	[2.34]
$C_6H_{11}Cl$	Chlorocyclohexane (*equitorial*)	2.44 ± 0.07
$C_6H_{11}Cl$	Chlorocyclohexane (*axial*)	1.91 ± 0.02
$C_6H_{11}F$	Fluorocyclohexane (*equitorial*)	2.11 ± 0.04
$C_6H_{11}F$	Fluorocyclohexane (*axial*)	1.81 ± 0.04
$C_6H_{11}N$	4-Methylpentanenitrile	[3.5]
$C_6H_{11}NO$	Caprolactam	[3.9]
$C_6H_{12}O$	Butyl vinyl ether	[1.25]
$C_6H_{12}O$	2-Hexanone	[2.66]
$C_6H_{12}O_2$	Hexanoic acid	[1.13]
$C_6H_{12}O_2$	Pentyl formate	1.90 ± 0.10
$C_6H_{12}O_2$	Butyl acetate	[1.87]
$C_6H_{12}O_2$	*sec*-Butyl acetate	[1.87]
$C_6H_{12}O_2$	Isobutyl acetate	[1.86]
$C_6H_{12}O_2$	Ethyl butanoate	[1.74]
$C_6H_{12}O_2$	Diacetone alcohol	[3.24]
$C_6H_{12}O_3$	Ethylene glycol monoethyl ether acetate	[2.25]

Mol. form.	Name	μ/D
$C_6H_{12}O_3$	Paraldehyde	1.43 ± 0.07
$C_6H_{13}N$	Cyclohexylamine	[1.26]
$C_6H_{14}O$	Dipropyl ether	1.21 ± 0.06
$C_6H_{14}O$	Diisopropyl ether	1.13 ± 0.10
$C_6H_{14}O$	Butyl ethyl ether	[1.24]
$C_6H_{14}O_2$	2-Methyl-2,4-pentanediol	[2.9]
$C_6H_{14}O_2$	Ethylene glycol monobutyl ether	[2.08]
$C_6H_{14}O_2$	1,1-Diethoxyethane	[1.38]
$C_6H_{14}O_3$	Diethylene glycol monoethyl ether	[1.6]
$C_6H_{14}O_3$	Diethylene glycol dimethyl ether	[1.97]
$C_6H_{15}N$	Dipropylamine	[1.03]
$C_6H_{15}N$	Diisopropylamine	[1.15]
$C_6H_{15}N$	Triethylamine	0.66 ± 0.05
$C_6H_{15}NO_3$	Triethanolamine	[3.57]
$C_6H_{15}O_4P$	Triethyl phosphate	[3.12]
$C_6H_{18}N_3OP$	Hexamethylphosphoric triamide	[5.5]
$C_7H_5Cl_3$	(Trichloromethyl)benzene	[2.03]
$C_7H_5F_3$	(Trifluoromethyl)benzene	2.86 ± 0.06
C_7H_5N	Benzonitrile	4.18 ± 0.08
C_7H_5N	Isocyanobenzene	4.018 ± 0.003
$C_7H_6Cl_2$	2,4-Dichlorotoluene	[1.70]
$C_7H_6Cl_2$	3,4-Dichlorotoluene	[2.95]
$C_7H_6Cl_2$	(Dichloromethyl)benzene	[2.07]
C_7H_6O	2,4,6-Cycloheptatrien-1-one	4.1 ± 0.3
C_7H_6O	Benzaldehyde	[3.0]
$C_7H_6O_2$	Salicylaldehyde	[2.86]
C_7H_7Cl	*o*-Chlorotoluene	1.56 ± 0.08
C_7H_7Cl	*m*-Chlorotoluene	[1.82]
C_7H_7Cl	*p*-Chlorotoluene	2.21 ± 0.04
C_7H_7Cl	(Chloromethyl)benzene	[1.82]
C_7H_7F	*o*-Fluorotoluene	1.37 ± 0.07
C_7H_7F	*m*-Fluorotoluene	1.82 ± 0.04
C_7H_7F	*p*-Fluorotoluene	2.00 ± 0.10
$C_7H_7NO_3$	2-Nitroanisole	[5.0]
C_7H_8	Toluene	0.375 ± 0.010
C_7H_8	2,5-Norbornadiene	0.0587 ± 0.0001
C_7H_8O	*o*-Cresol	[1.45]
C_7H_8O	*m*-Cresol	[1.48]
C_7H_8O	*p*-Cresol	[1.48]
C_7H_8O	Benzyl alcohol	1.71 ± 0.09
C_7H_8O	Anisole	1.38 ± 0.07
C_7H_9N	*o*-Methylaniline	[1.60]
C_7H_9N	*m*-Methylaniline	[1.45]
C_7H_9N	*p*-Methylaniline	[1.52]
C_7H_9N	2,4-Dimethylpyridine	[2.30]
C_7H_9N	2,6-Dimethylpyridine	[1.66]
C_7H_{10}	1,3-Cycloheptadiene	0.740
C_7H_{12}	Methylenecyclohexane	0.62 ± 0.01
$C_7H_{12}O_4$	Diethyl malonate	[2.54]
$C_7H_{14}O$	2-Heptanone	[2.59]
$C_7H_{14}O$	3-Heptanone	[2.78]
$C_7H_{14}O$	2,4-Dimethyl-3-pentanone	[2.74]
$C_7H_{14}O$	*cis*-3-Methylcyclohexanol	[1.91]
$C_7H_{14}O$	*trans*-3-Methylcyclohexanol	[1.75]
$C_7H_{14}O_2$	Pentyl acetate	1.75 ± 0.10
$C_7H_{14}O_2$	Isopentyl acetate	[1.86]
$C_7H_{15}Br$	1-Bromoheptane	2.16 ± 0.11
$C_7H_{16}O$	2-Heptanol	[1.71]
$C_7H_{16}O$	3-Heptanol	[1.71]
C_8H_6	Phenylacetylene	0.656 ± 0.005
C_8H_7N	Benzeneacetonitrile	[3.5]
C_8H_8	Styrene	0.123 ± 0.003
C_8H_8O	Acetophenone	3.02 ± 0.06
$C_8H_8O_2$	Methyl benzoate	[1.94]
$C_8H_8O_3$	Methyl salicylate	[2.47]
C_8H_{10}	Ethylbenzene	0.59 ± 0.05
C_8H_{10}	*o*-Xylene	0.640 ± 0.005
$C_8H_{10}O$	2,4-Xylenol	[1.4]
$C_8H_{10}O$	2,5-Xylenol	[1.45]
$C_8H_{10}O$	2,6-Xylenol	[1.40]
$C_8H_{10}O$	3,4-Xylenol	[1.56]
$C_8H_{10}O$	3,5-Xylenol	[1.55]
$C_8H_{10}O$	Phenetole	1.45 ± 0.15
$C_8H_{10}O_2$	1,2-Dimethoxybenzene	[1.29]
$C_8H_{11}N$	*N,N*-Dimethylaniline	1.68 ± 0.17
$C_8H_{11}N$	2,4-Dimethylaniline	[1.40]
$C_8H_{11}N$	2,6-Dimethylaniline	[1.63]
$C_8H_{11}N$	2,4,6-Trimethylpyridine	[2.05]
$C_8H_{16}O$	2-Octanone	[2.70]
$C_8H_{16}O_2$	Octanoic acid	[1.15]
$C_8H_{16}O_2$	*sec*-Hexyl acetate	[1.9]
$C_8H_{16}O_2$	Isobutyl isobutanoate	[1.9]
$C_8H_{16}O_4$	Diethylene glycol monoethyl ether acetate	[1.8]
$C_8H_{17}Cl$	1-Chlorooctane	[2.00]
$C_8H_{18}O$	1-Octanol	[1.76]
$C_8H_{18}O$	2-Octanol	[1.71]
$C_8H_{18}O$	2-Ethyl-1-hexanol	[1.74]
$C_8H_{18}O$	Dibutyl ether	1.17 ± 0.06
$C_8H_{18}S$	Dibutyl sulfide	[1.61]
$C_8H_{19}N$	Dibutylamine	[0.98]
C_9H_7N	Quinoline	2.29 ± 0.11
C_9H_7N	Isoquinoline	2.73 ± 0.14
$C_9H_{10}O_2$	Ethyl benzoate	2.00 ± 0.10
$C_9H_{10}O_2$	Benzyl acetate	[1.22]
C_9H_{12}	Isopropylbenzene	≈0.79
$C_9H_{18}O$	2,6-Dimethyl-4-heptanone	[2.66]
$C_9H_{18}O_2$	Nonanoic acid	[0.79]
$C_{10}H_7Br$	1-Bromonaphthalene	[1.55]
$C_{10}H_7Cl$	1-Chloronaphthalene	[1.57]
$C_{10}H_8$	Azulene	0.80 ± 0.02
$C_{10}H_{14}$	*tert*-Butylbenzene	≈0.83
$C_{10}H_{16}O$	Camphor, (+)	[3.1]
$C_{10}H_{20}O_2$	2-Ethylhexyl acetate	[1.8]
$C_{10}H_{21}Br$	1-Bromodecane	[1.93]
$C_{10}H_{22}O$	Dipentyl ether	[1.20]
$C_{10}H_{22}O$	Diisopentyl ether	[1.23]
$C_{11}H_{12}O_2$	Ethyl *trans*-cinnamate	[1.84]
$C_{12}H_{10}$	Acenaphthene	≈0.85
$C_{12}H_{10}O$	Diphenyl ether	≈1.3
$C_{12}H_{27}BO_3$	Tributyl borate	[0.77]
$C_{12}H_{27}N$	Tributylamine	[0.78]
$C_{12}H_{27}O_4P$	Tributyl phosphate	[3.07]
$C_{14}H_{12}O_2$	Benzyl benzoate	[2.06]
$C_{16}H_{22}O_4$	Dibutyl phthalate	[2.82]
$C_{18}H_{34}O_2$	Oleic acid	[1.18]
$C_{18}H_{34}O_4$	Dibutyl sebacate	[2.48]
$C_{21}H_{21}O_4P$	Tri-*o*-cresyl phosphate	[2.87]
$C_{21}H_{21}O_4P$	Tri-*m*-cresyl phosphate	[3.05]
$C_{21}H_{21}O_4P$	Tri-*p*-cresyl phosphate	[3.18]
$C_{22}H_{44}O_2$	Butyl stearate	[1.88]
$C_{24}H_{38}O_4$	Bis(2-ethylhexyl) phthalate	[2.84]

BOND DISSOCIATION ENERGIES

Yu-Ran Luo and J. Alistair Kerr

The bond dissociation energy (enthalpy) is also referred to as bond disruption energy, bond energy, bond strength, or binding energy (abbreviation: BDE, BE, or D). It is defined as the standard enthalpy change of the following fission: R–X → R + X. The BDE, denoted by D^o(R–X), is usually derived by the thermochemical equation, $D^o(R–X) = \Delta_f H^o(R) + \Delta_f H^o(X) - \Delta_f H^o(RX)$. The enthalpy of formation $\Delta_f H^o$ of a large number of atoms, free radicals, ions, clusters and compounds is available from the websites of NIST, NASA, CODATA, and IUPAC. Most authors prefer to use BDE values at 298.15 K.

The following tables provide essential information on experimental BDE values for diatomic (Table 1) and polyatomic (Table 3) species. The enthalpy of formation of atoms and free radicals in the gas phase at 298.15 K is listed in Tables 2 and 4, respectively. Table 5 provides a summary of BDEs for simple organic molecules.

The data in these tables have been revised through September 2004.

TABLE 1. Bond Dissociation Energies in Diatomic Molecules

The BDEs in diatomic species have usually been measured by spectroscopy or mass spectrometry. In the absence of data on the enthalpy function, the values at 0 K, D^o(A–B), are converted to D^o_{298} by the approximate equation:

$$D^o_{298}(A–B) \approx D^o(A–B) + (3/2)RT = D^o(A–B) + 3.7181 \text{ kJ mol}^{-1}$$

This table has been arranged in an alphabetical order of the atoms A in the diatomics A–B.

A-B	D^o_{298}/kJ mol^{-1}	Ref.	A-B	D^o_{298}/kJ mol^{-1}	Ref.	A-B	D^o_{298}/kJ mol^{-1}	Ref.
Ac-O	794	338	Al-H	288±13	298	As-N	489±2.1	224
Ag-Ag	159.2±2.9	297	Al-I	369.9±2.1	115	As-O	484±8	160
Ag-Al	183.7±9.2	68	Al-Kr	6.28	301	As-P	433.5±12.6	80
Ag-Au	202.5±9.6	173	Al-Li	76.1	152	As-S	379.5±6.3	152
Ag-Bi	192±42	81	Al-N	356±42	81	As-Sb	330.5±5.4	110
Ag-Br	293±29	29	Al-Ni	224.7±4.8	235	As-Se	96	15
Ag-Cl	279.1±8.4	345	Al-O	501.9±10.6	308	As-Tl	198.3±14.6	65
Ag-Cu	171.5±9.6	243	Al-P	216.7±12.6	14	Au-Au	226.2±0.5	256
Ag-D	226.8	123	Al-Pd	254.4±12.1	97	Au-B	367.8±10.5	50
Ag-Dy	130±19	140	Al-S	332±10	272	Au-Ba	254.8±10.0	132
Ag-Eu	126.7±13	192	Al-Sb	216.3±6	116	Au-Be	305	73
Ag-F	354.4±16.3	29	Al-Se	337.6±10.0	55	Au-Bi	293±8.4	81
Ag-Ga	154.8±16.7	81	Al-Si	246.9±12.6	87	Au-Br	209±21	327
Ag-Ge	174.5±20.9	63	Al-Te	267.8±10.0	56	Au-Ca	242	132
Ag-H	202.4±9.6	262	Al-Ti	263.4	123	Au-Ce	322±18	192
Ag-Ho	123.8±19	140	Al-U	326±29	23	Au-Cl	276±13	327
Ag-I	234±29	29	Al-V	147.4±1.0	322	Au-Co	218.0±16.4	173
Ag-In	166.5±4.9	190	Al-Xe	7.43±0.69	191	Au-Cr	223.7±28.9	173
Ag-Li	198.8	274	Am-O	553±36	334	Au-Cs	255±3.3	139
Ag-Mn	99.2±21	173	Ar-Ar	4.73±0.04	181	Au-Cu	227.1±1.2	236
Ag-Na	133.1±12.6	125	Ar-B	4.99	270	Au-D	318.4	123
Ag-Nd	<209	81	Ar-C	5.158	312	Au-Dy	259±24	192
Ag-O	221±21	208	Ar-Ga	5.15	302	Au-Eu	245±12	192
Ag-S	217.1	67	Ar-Ge	<5.4	343	Au-F	318±33	259
Ag-Se	202.5	67	Ar-He	4.15	123	Au-Fe	187.0±19.3	173
Ag-Si	177.8±10.0	146	Ar-Hg	6.19	81	Au-Ga	290±15	57
Ag-Sn	136.0±20.9	4	Ar-I	10	41	Au-Ge	273.2±14.6	63
Ag-Te	195.8	67	Ar-In	6.03	238	Au-H	303±13	214
Al-Al	133±5.8	203	Ar-K	4.6	123	Au-Ho	267±35	192
Al-Ar	5.69	247	Ar-Ne	4.15	123	Au-I	276	325
Al-As	202.7±7.1	127	Ar-Si	5.857	336	Au-In	286.0±5.7	190
Al-Au	325.9±6.3	72	Ar-Sn	<5.1	350	Au-La	335.7±9.6	173
Al-Br	429±6	195	Ar-Tl	6.11	276	Au-Li	284.5±6.7	84
Al-C	267.7	326	As-As	382.0±10.5	234	Au-Lu	332±19	192
Al-Ca	52.7	251	As-Cl	448	43	Au-Mg	179.1±2.7	337
Al-Cl	502	298	As-D	270.3	123	Au-Mn	197.7±21	173
Al-Co	181.6±0.2	322	As-F	410	123	Au-Na	215.1±12.6	105
Al-Cr	222.9±0.9	322	As-Ga	202.5±4.8	207	Au-Nd	294±29	192
Al-Cu	227.1±1.2	236	As-H	274.0±2.9	177	Au-Ni	247±16.4	231
Al-D	290.4	320	As-I	296.6±24	128	Au-O	223±21	208
Al-F	675	298	As-In	201±10	154	Au-Pb	130±42	81

A-B	D^o_{298}/kJ mol^{-1}	Ref.
Au-Pd	142.7±21	173
Au-Pr	311±25	192
Au-Rb	243±3.5	139
Au-Rh	232.6±29	173
Au-S	418±25	45
Au-Sc	280±40	192
Au-Se	243.1	67
Au-Si	304.6±6.0	122
Au-Sn	256.5±7.2	172
Au-Sr	264±42	81
Au-Tb	285±33	192
Au-Te	314	67
Au-U	318±29	23
Au-V	243.1±8.7	173
Au-Y	310.6±12	192
B-B	290	298
B-Br	396	216
B-C	448±29	10
B-Cd	301	123
B-Ce	305±21	44
B-Cl	511.3±4.6	283
B-D	341.0±6.3	81
B-F	732	323
B-H	340	185
B-I	361	298
B-Ir	512.2±17	46
B-La	339±63	81
B-N	389±21	43
B-O	809	296
B-P	346.9±16.7	60
B-Pd	351.5±16.7	81
B-Pt	477.8±16.7	34
B-Rh	475.8±21	46
B-Ru	446.9±21	46
B-S	580.7±9.2	49
B-Sc	276±63	81
B-Se	461.9±14.6	49
B-Si	317±12	290
B-Te	354.4±20.1	49
B-Th	297±33	36
B-Ti	276±63	81
B-U	322±33	44
B-Y	293±63	81
Ba-Br	402	298
Ba-Cl	443	298
Ba-D	≤193.7	123
Ba-F	571.5	120
Ba-H	192	123
Ba-I	322.6±6.3	226
Ba-O	561.9±13.4	160
Ba-Pd	221.8±5.0	112
Ba-Rh	259.4±25.1	112
Ba-S	400.0±18.8	7
Be-Be	59	163
Be-Br	316	298
Be-Cl	434	155
Be-D	203.1	123
Be-F	573	298
Be-H	199.9±1.3	123
Be-I	261	298
Be-O	437	298
Be-S	372±59	29
Be-T	204.4	123
Bi-Bi	196.6±7.5	234
Bi-Br	240.2	314
Bi-Cl	300.4±4.2	19
Bi-D	283.7	91
Bi-F	367±13	233
Bi-Ga	158.6±16.7	64
Bi-H	≤283.3	91
Bi-I	188	156
Bi-In	153.6±1.7	145
Bi-Li	149.4	143
Bi-O	337.2±12.6	160
Bi-P	281.7±13	80
Bi-Pb	141.8±14.6	24
Bi-S	315.5±4.6	40
Bi-Sb	252.7±3.9	33
Bi-Se	280.3±5.9	40
Bi-Sn	193±13	331
Bi-Te	232.2±11.3	40
Bi-Tl	120.9±12.6	62
Bk-O	598	338
Br-Br	193.857	123
Br-C	318.0±8.4	296
Br-Ca	339	298
Br-Cd	159±96	29
Br-Cl	219.32±0.05	277
Br-Co	326±42	81
Br-Cr	328.0±24.3	29
Br-Cs	389.1±4.2	135
Br-Cu	331±25	29
Br-D	370.74	123
Br-Dy	339.3±10.5	345
Br-F	280±12	205
Br-Fe	243±84	81
Br-Ga	402±13	281
Br-Ge	347±8	221
Br-H	366.35	123
Br-Hg	74.9	240
Br-I	179.1±0.4	223
Br-In	409±10	281
Br-K	379.1±4.2	135
Br-Li	418.8±4.2	135
Br-Mg	294	298
Br-Mn	314.2±9.6	29
Br-Mo	313.4	298
Br-N	280.8±21	42
Br-Na	363.1±4.2	135
Br-Ni	360±13	29
Br-O	235.1±2.4	296
Br-P	≤329	279
Br-Pb	248.5±14.6	266
Br-Rb	380.7±4.2	135
Br-S	218±17	109
Br-Sb	314±59	29
Br-Sc	444±63	81
Br-Se	297±84	81
Br-Si	358.2±8.4	296
Br-Sn	337±13	221
Br-Sr	365	298
Br-T	372.77	123
Br-Th	364	204
Br-Ti	373	298
Br-Tl	331±21	43
Br-U	377±15	168
Br-V	439±42	81
Br-W	329.3	104
Br-Xe	5.94±0.02	264
Br-Y	481±84	81
Br-Zn	138±29	81
Br-Zr	420	298
C-C	595.63	296
C-Ce	443±30	192
C-Cl	394.9±13.4	307
C-D	341.4	123
C-F	513.8±10.0	296
C-Fe	376.3±28.9	291
C-Ge	455.7±11	300
C-H	338.4±1.2	123
C-Hf	540±25	208
C-I	253.1±35.6	221
C-Ir	631±5	208
C-La	463±20	208
C-Mo	482±16	208
C-N	750.0±2.9	310
C-Nb	568±13	208
C-Ni	≥326.4	328
C-O	1076.38±0.67	296
C-Os	608±25	324
C-P	513.4±8	55
C-Pd	436±20	208
C-Pt	610±5	208
C-Rh	580±4	208
C-Ru	648±13	208
C-S	713.3±1.2	265
C-Sc	444±21	208
C-Se	590.4±5.9	106
C-Si	447	296
C-Tc	564±29	208
C-Th	453±17	208
C-Ti	423±30	208
C-U	455±15	208
C-V	423±24	208
C-Y	418±14	230
C-Zr	561±25	208
Ca-Ca	~17	267
Ca-Cl	409±8.7	242
Ca-D	≤169.9	123
Ca-F	529	298
Ca-H	223.8	320
Ca-I	284.7±8.4	226
Ca-Li	84.9±8.4	162
Ca-O	383.3±5.0	275
Ca-Pd	347 - 360	348
Ca-S	335±21	81
Cd-Cd	7.36	169
Cd-Cl	208.4	123
Cd-F	305±21	11
Cd-H	69.0±0.4	208
Cd-I	97.2±2.1	229
Cd-In	134	81
Cd-Na	10.2	78

A-B	D^o_{298}/kJ mol^{-1}	Ref.
Cd-O	236±84	208
Cd-S	208.5±20.9	149
Cd-Se	127.6±25.1	149
Cd-Te	100.0±15.1	149
Ce-Ce	242±21	192
Ce-F	582±42	81
Ce-Ir	575±9	192
Ce-N	519±21	51
Ce-O	790	254
Ce-Os	524±20	192
Ce-Pd	319±21	192
Ce-Pt	550±5	192
Ce-Rh	545±7	192
Ce-Ru	494±12	192
Ce-S	569	39
Ce-Se	494.5±14.6	83
Ce-Te	189.4±12.6	183
Cf-O	498	338
Cl-Cl	242.580±0.004	123
Cl-Co	337.6±6.7	268
Cl-Cr	377.8±6.7	268
Cl-Cs	445.7±7.7	167
Cl-Cu	377.8±7.5	286
Cl-D	436.47	123
Cl-Eu	~326	59
Cl-F	260.83	303
Cl-Fe	329.7±6.7	268
Cl-Ga	463±13	281
Cl-Ge	390.8±9.6	285
Cl-H	431.328±0.014	332
Cl-Hg	100±8	29
Cl-I	211.3±0.4	29
Cl-In	436±8	281
Cl-K	433.0±8.4	136
Cl-Li	469±13	43
Cl-Mg	312	298
Cl-Mn	338.5±6.7	268
Cl-N	333.9±9.6	42
Cl-Na	412.1±8.4	136
Cl-Ni	377.0±6.7	268
Cl-O	267.47±0.08	241
Cl-P	≤376	279
Cl-Pb	301±50	298
Cl-Ra	343±75	29
Cl-Rb	427.6±8.4	136
Cl-S	241.8	296
Cl-Sb	360±50	29
Cl-Sc	331	123
Cl-Se	322	81
Cl-Si	416.7±6.3	296
Cl-Sm	422±13	101
Cl-Sn	346±8	245
Cl-Sr	409	298
Cl-T	438.64	123
Cl-Ta	544	131
Cl-Th	489	206
Cl-Ti	405.4±10.5	284
Cl-Tl	372.8±2.1	27
Cl-U	439	228
Cl-V	477±63	81
Cl-W	419	298
Cl-Xe	6.7	123
Cl-Y	523±84	81
Cl-Yb	~322	59
Cl-Zn	229±8	306
Cl-Zr	530	298
Cm-O	732	47
Co-Co	<127	321
Co-Cu	161.1±16.4	173
Co-D	270.2±5.8	313
Co-F	431±63	81
Co-Ge	230±21	81
Co-H	244.9±4.8	313
Co-I	280±21	81
Co-Mn	50±8	222
Co-Nb	267.02±0.10	250
Co-O	384.5±13.4	199
Co-S	331	67
Co-Si	274.4±17	38
Co-Ti	235.39±0.10	232
Co-Y	253.71±0.10	250
Co-Zr	306.39±0.10	250
Cr-Cr	152.0±6	301
Cr-Cu	154.4±14.5	173
Cr-F	523±19	217
Cr-Ge	154±7	196
Cr-H	189.9±6.7	237
Cr-I	287.0±24.3	29
Cr-N	377.8±18.8	75
Cr-Nb	295.72±0.06	317
Cr-O	461±8.7	282
Cr-Pb	105±2	196
Cr-S	331	21
Cr-Sn	141±3	196
Cs-Cs	43.919±0.010	170
Cs-F	517.1±7.7	167
Cs-H	175.364	188
Cs-Hg	4.6	73
Cs-I	338.6±2.1	129
Cs-Na	63.2±1.3	165
Cs-O	297±63	160
Cs-Rb	49.57±0.01	180
Cu-Cu	201	321
Cu-D	270.3	123
Cu-Dy	144±18	192
Cu-F	414	342
Cu-Ga	215.9±15	57
Cu-Ge	208.8±21	63
Cu-H	254.8±6	280
Cu-Ho	144±19	192
Cu-I	197±21	29
Cu-In	187.4±7.9	190
Cu-Li	192.9±8.8	84
Cu-Na	176.1±16.7	74
Cu-Ni	201.7±9.6	193
Cu-O	280.5	298
Cu-S	276	67
Cu-Se	251	67
Cu-Si	221.3±6.3	146
Cu-Sn	170±10	114
Cu-Tb	191±18	192
Cu-Te	278.7	94
D-D	443.3038±0.0003	351
D-F	576.174±0.096	249
D-Ga	<276.5	53
D-Ge	≤322	123
D-H	439.2066±0.0002	351
D-Hg	42.05	123
D-I	302.33	123
D-In	246	123
D-K	182.4	123
D-Li	240.24	90
D-Lu	302	257
D-Mg	161.33±0.32	314
D-Mn	312±6	293
D-N	341.6	123
D-Ni	≤302.9	123
D-O	429.64	123
D-P	299	123
D-Pt	≤350.2	123
D-S	350.62±1.20	244
D-Si	302.5	123
D-Sr	167.7	123
D-T	444.91	123
D-Tl	193	123
D-Zn	88.7	123
Dy-Dy	71±29	192
Dy-F	531	17
Dy-I	269.0±8.4	345
Dy-O	611	254
Dy-S	414±42	81
Dy-Se	322±20	41
Dy-Te	234±20	41
Er-Er	75±29	192
Er-F	565±17	17
Er-O	606	254
Er-S	418±21	39
Er-Se	326±20	41
Er-Te	238±20	41
Es-O	460	338
Eu-Eu	33±17	192
Eu-F	544	142
Eu-Li	268.1±12.6	159
Eu-O	472.8±9.6	219
Eu-Rh	238±34	192
Eu-S	365.7±13.4	117
Eu-Se	302.9±14.6	83
Eu-Te	251.0±14.6	83
F-F	158.78	123
F-Fe	447	298
F-Ga	584±13	281
F-Gd	590±17	25
F-Ge	523±13	221
F-H	569.87±0.06	249
F-Hf	650±15	215
F-Hg	~180	123
F-Ho	540	17
F-I	≤271.5	96
F-In	516±13	281
F-K	489.2	123
F-La	659.0±17.2	269
F-Li	577±21	43
F-Lu	333.5	151

A-B	D^o_{298}/kJ mol^{-1}	Ref.
F-Mg	463	298
F-Mn	423.4±14.6	9
F-Mo	464	98
F-N	≤349	179
F-Na	519	123
F-Nd	545.2±12.6	16
F-Ni	428.4±19.3	202
F-Np	430±50	168
F-O	220	341
F-P	≤405	279
F-Pb	355±13	298
F-Pr	582±46	81
F-Pu	480±27	168
F-Rb	494±21	43
F-Ru	402	182
F-S	343.5±6.7	133
F-Sb	439±96	29
F-Sc	599.1±13.4	269
F-Se	339±42	81
F-Si	549.4±8.4	296
F-Sm	565	142
F-Sn	476±8	221
F-Sr	538	298
F-T	579.009±0.108	249
F-Ta	573±13	124
F-Tb	561±42	81
F-Th	652	198
F-Ti	569±33	26
F-Tl	439±21	43
F-Tm	510	142
F-U	648	228
F-V	590±63	81
F-W	≤544	89
F-Xe	15.77	144
F-Y	685.3±13.4	269
F-Yb	≥517.6±9.6	101
F-Zn	364±63	81
F-Zr	627.2±10.5	292
Fe-Fe	118	321
Fe-Ge	210.9±29	32
Fe-H	148±3	280
Fe-O	414	298
Fe-S	325.1±14.6	330
Fe-Si	297±25	38
Fm-O	443	338
Ga-Ga	<106.4	343
Ga-H	276	281
Ga-I	334±13	281
Ga-In	94.0±3	295
Ga-Kr	5.75	302
Ga-Li	133.1±14.6	88
Ga-O	374±21	281
Ga-P	229.7±12.6	52
Ga-Sb	192.0±12.6	85
Ga-Te	251±25	35
Ga-Xe	8.16	302
Gd-Gd	176±33	192
Gd-O	715	254
Gd-S	526.8±10.5	111
Gd-Se	430±15	41
Gd-Te	341±15	41
Ge-Ge	264.4±6.8	335
Ge-H	263.2±4.8	315
Ge-I	268±25	221
Ge-Ni	290.3±10.9	186
Ge-O	652.7	288
Ge-Pd	254.7±10.5	174
Ge-S	534±3	294
Ge-Sc	270±11	197
Ge-Se	484.7±1.7	289
Ge-Si	297	2
Ge-Sn	230.1±13	299
Ge-Te	396.7±3.3	273
Ge-Y	279±11	192
H-H	435.7644±0.0001	351
H-Hg	39.844	123
H-I	298.407	123
H-In	243.1	278
H-K	174.576	188
H-Li	238.039±0.006	77
H-Mg	126.4±2.9	108
H-Mn	251±5	293
H-Mo	211±19	214
H-N	≤338.9	123
H-Na	185.69±0.29	158
H-Nb	>221.9±9.6	318
H-Ni	240±8	280
H-O	429.91±0.29	333
H-P	297.0±2.1	171
H-Pb	≤157	123
H-Pd	234±25	175
H-Pt	327	305
H-Rb	167±21	29
H-Rh	241.0±5.9	263
H-Ru	223±15	304
H-S	354.2±1.2	244
H-Sb	239.7±4.2	246
H-Sc	205±17	214
H-Se	312.5	347
H-Si	293.3±1.9	347
H-Sn	264±17	29
H-Sr	164±8	123
H-T	440.49	123
H-Te	259.8±6.7	194
H-Ti	204.6±8.8	218
H-Tl	195.4±4	281
H-V	209.3±6.8	237
H-Yb	159±38	208
H-Zn	85.8±2	123
He-He	3.8	123
He-Hg	6.61	81
He-Xe	3.8	123
Hf-Hf	328±58	173
Hf-N	535±30	82
Hf-O	801±13	208
Hg-Hg	8±2	150
Hg-I	34.69±0.96	239
Hg-K	8.4	81
Hg-Li	13.8	123
Hg-Na	10.5	78
Hg-O	269	298
Hg-Rb	8.4	123
Hg-S	217.3±22.2	149
Hg-Se	144.3±30.1	149
Hg-T	43.14	123
Hg-Te	<142	81
Hg-Tl	2.9	73
Ho-Ho	86±30	192
Ho-O	606	254
Ho-S	428.4±14.6	39
Ho-Se	333±15	41
Ho-Te	≤259±15	41
I-I	152.534	161
I-In	323±8	281
I-K	322.5±2.1	129
I-Li	345.2±4.2	129
I-Mg	229	298
I-Mn	282.8±9.6	29
I-Mo	266.9	298
I-N	159±17	81
I-Na	304.2±2.1	129
I-Ni	293±21	29
I-O	240±5	341
I-Pb	194±38	298
I-Rb	318.8±2.1	129
I-Si	243.1±8.4	296
I-Sn	235±3	221
I-Sr	301	298
I-Te	192±42	81
I-Th	361±25	168
I-Ti	306	298
I-Tl	285±21	43
I-U	299±27	168
I-Y	422.6±12.5	157
I-Zn	153.1±6.3	340
I-Zr	127	298
In-In	82.0±5.7	295
In-Kr	6.83	302
In-Li	92.5±14.6	88
In-O	346±30	281
In-P	197.9±8.4	99
In-S	287.9±14.6	28
In-Sb	151.9±10.5	3
In-Se	245.2±14.6	28
In-Te	215.5±14.6	28
In-Xe	9.36	302
In-Zn	32.2	20
Ir-Ir	361±68	173
Ir-La	577±12	192
Ir-Nb	465±25	173
Ir-O	414±42	208
Ir-Si	462.8±21	46
Ir-Th	574±42	79
Ir-Ti	422±13	200
Ir-Y	457±15	192
K-K	56.97±0.02	213
K-Kr	4.6	123
K-Li	82.0±4.2	107
K-Na	65.994±0.008	119
K-O	277.8±21	160
K-Xe	5	123
Kr-Kr	5.23	123
Kr-Ne	4.18	123

A-B	D^o_{298}/kJ mol^{-1}	Ref.
Kr-O	<8	81
Kr-Tl	6.78	302
Kr-Xe	5.505±0.002	189
La-La	247±21	192
La-N	519±42	81
La-O	798	254
La-Pt	505±12	192
La-Rh	550±12	192
La-S	573.36±1.7	103
La-Se	485.7±14.6	83
La-Te	385.6±15	41
La-Y	197±21	81
Li-Li	110.4±6.3	100
Li-Mg	67.4±6.3	137
Li-Na	87.181±0.001	220
Li-O	333.0±8.4	160
Li-Pb	78.7±8	134
Li-S	312.5±7.5	141
Li-Sb	169.0±10.0	153
Li-Sm	193.3±18.8	159
Li-Tm	276.1±14.6	159
Li-Yb	143.5±12.6	159
Lr-O	665	338
Lu-Lu	142±33	192
Lu-O	669	254
Lu-Pt	402±34	192
Lu-S	508.4±14.4	121
Lu-Se	418±15	41
Lu-Te	325±15	41
Md-O	418	338
Mg-Mg	11.3	162
Mg-O	358.2±7.2	316
Mg-S	234	7
Mn-Mn	≤80.8	173
Mn-O	362±25	210
Mn-S	301±17	12
Mn-Se	239.3±9.2	118
Mo-Mo	435.5±1.0	301
Mo-Nb	452±25	173
Mo-O	502	329
N-N	945.33±0.59	123
N-O	630.57±0.13	123
N-P	617.1±20.9	37
N-Pu	469±63	81
N-S	467±24	349
N-Sb	460±84	81
N-Sc	464±84	81
N-Si	437.1±9.9	316
N-Ta	607±84	81
N-Th	577±33	30
N-Ti	476±33	48
N-U	531±21	22
N-V	523±38	178
N-Xe	26.9	5
N-Y	477±63	81
N-Zr	565±25	31
Na-Na	74.8048	287
Na-O	256.1±16.7	160
Na-Rb	63.887±0.024	225
Nb-Nb	513	280
Nb-Ni	271.9±0.1	250
Nb-O	784	298
Nb-Ti	302.0±0.1	271
Nb-V	369.3±0.1	255
Nd-Nd	84±29	192
Nd-O	703	254
Nd-S	471.5±14.6	39
Nd-Se	393.9	166
Nd-Te	305±15	41
Ne-Ne	3.93	76
Ne-Xe	4.18	123
Ni-Ni	204	321
Ni-O	366±30	248
Ni-Pd	140.9	211
Ni-Pt	273.7±0.3	212
Ni-S	356±21	81
Ni-Si	318±17	38
Ni-V	206.3±0.2	209
Ni-Y	283.9±0.1	250
Ni-Zr	279.8±0.1	250
No-O	268	338
Np-O	731	338
O-O	498.36±0.17	123
O-Os	575	227
O-P	589	298
O-Pa	792	254
O-Pb	374	298
O-Pd	238.1±12.6	311
O-Pr	740	254
O-Pt	391±42	208
O-Pu	661	338
O-Rb	297±42	160
O-Re	627±84	208
O-Rh	405±42	208
O-Ru	528±42	208
O-S	517.90±0.05	253
O-Sb	434±42	160
O-Sc	670.8±8.9	309
O-Se	469±21	160
O-Si	799.6±13.4	298
O-Sm	573	254
O-Sn	528	221
O-Sr	426.3±6.3	258
O-Ta	839	298
O-Tb	694	254
O-Tc	548	208
O-Te	377±21	160
O-Th	877	339
O-Ti	668	298
O-Tl	213±84	160
O-Tm	514	254
O-U	755	338
O-V	637	298
O-W	832±71	344
O-Xe	36.4	81
O-Y	698.1±14.5	308
O-Yb	401	254
O-Zn	≤226	248
O-Zr	766.1±10.6	319
Os-Os	415±77	173
P-P	485.3	234
P-Pt	≤416.7±16.7	54
P-Rh	353.1±16.7	54
P-S	442±10	349
P-Sb	356.9±4.2	61
P-Se	363.7±10.0	69
P-Si	363.6	66
P-Te	297.9±10.0	69
P-Th	376±29	36
P-Tl	209±13	116
P-U	293±21	81
P-W	305±4	8
Pb-Pb	86.6±0.8	143
Pb-S	398	221
Pb-Sb	161.5±10.5	147
Pb-Se	302.9±4.2	40
Pb-Te	249.8±10.5	40
Pd-Pd	>136	211
Pd-Pt	191	212
Pd-Si	261±12	176
Pd-Y	241±15	192
Po-Po	187	123
Pr-Pr	130±29	192
Pr-S	492.5±4.6	70
Pr-Se	446.4±23.0	83
Pr-Te	326±20	41
Pt-Pt	306.7±1.9	187
Pt-Si	501.2±18.0	46
Pt-Th	551±42	71
Pt-Ti	397.5±10.6	173
Pt-Y	474±12	192
Rb-Rb	48.898±0.005	201
Re-Re	386±96	173
Rh-Rh	235.84±0.05	297
Rh-Sc	444±11	192
Rh-Si	395.0±18.0	46
Rh-Th	513±21	113
Rh-Ti	390.8±14.6	173
Rh-U	519±17	113
Rh-V	364±29	173
Rh-Y	446±11	192
Ru-Ru	331	173
Ru-Si	397.1±20.9	46
Ru-Th	591.6±42	79
Ru-V	414±29	173
S-S	425.3	123
S-Sb	378.7	58
S-Sc	478.2±12.6	92
S-Se	371.1±6.7	102
S-Si	617±5	294
S-Sm	389	70
S-Sn	467	221
S-Sr	338.5±16.7	18
S-Tb	515±42	81
S-Te	335±42	81
S-Ti	418±3	126
S-Tm	368±21	39
S-U	528.4±10.5	92
S-V	477.9±1.9	164
S-Y	528.4±10.5	93
S-Yb	167	81
S-Zn	224.8±12.6	149
S-Zr	575.3±16.7	92

A-B	D^o_{298}/kJ mol^{-1}	Ref.
Sb-Sb	301.7±6.3	234
Sb-Te	277.4±3.8	86
Sb-Tl	126.7±10.5	138
Sc-Sc	163±21	192
Sc-Se	385±17	81
Sc-Si	227.2±14	197
Sc-Te	289±17	81
Se-Se	330.5	102
Se-Si	538±13	260
Se-Sm	331.0±14.6	83
Se-Sn	401.2±5.9	6
Se-Sr	251.0±12.6	13
Se-Tb	423±20	41
Se-Te	293.3	102
Se-Ti	381±42	81
Se-Tm	274±40	41
Se-V	347±21	81
Se-Y	435±13	81
Se-Zn	170.7±25.9	149
Si-Si	310	296
Si-Te	448±8	260
Si-Y	258±17	192
Sm-Sm	54±21	192
Sm-Te	272.4±14.6	83
Sn-Sn	187.1±0.3	184
Sn-Te	338.1±6.3	6
Sr-Sr	15.5±0.4	148
T-T	446.67	123
Ta-Ta	390±96	173
Tb-Tb	132±25	192
Tb-Te	339±42	81
Tc-Tc	330	173
Te-Te	257.6±4.1	261
Te-Ti	289±17	81
Te-Tm	182±40	41
Te-Y	339±13	81
Te-Zn	117.6±18.0	149
Th-Th	≤289±33	36
Ti-Ti	117.6	346
Ti-V	203.2±0.1	232
Ti-Zr	214.3±0.1	271
Tl-Tl	64.4±17	130
Tl-Xe	8.29	302
Tm-Tm	54±17	192
U-U	222±21	81
V-V	269.3±0.1	232
V-Zr	260.6±0.3	271
W-W	486±96	173
Xe-Xe	6.52	95
Y-Y	160±21	192
Yb-Yb	21±17	192
Zn-Zn	22.2±6.3	81
Zr-Zr	298.2±0.1	250

References

1. Drowart, J. and Honig, R.E., *J. Phys. Chem*., 61, 980-985, 1957.
2. Drowart, J., de Maria, G., et al., *J. Chem. Phys*., 30, 308-313, 1959.
3. De Maria, G. and Drowart, J., *J. Chem. Phys*., 31, 1076-1081, 1959
4. Ackerman, M., Drowart, J., et al., *J. Chem. Phys*., 36, 1557-1560, 1962.
5. Herman, L. and Herman, R., *J. Phys. Radium*, 24, 73-75, 1963
6. Colin, R. and Drowart, J., *Trans. Faraday Soc*., 60, 673-683, 1964.
7. Colin, R., Goldfinger, P., et al., *Trans. Faraday Soc*., 60, 306-316, 1964.
8. Gingerich, K.A., *J. Phys. Chem*., 68, 768-772, 1964.
9. Kent, R.A., Ehlert, T.C., et al., *J. Am. Chem. Soc*., 86, 5090-5093, 1964.
10. Verhaegen, G., Stafford, F.E., et al., J., *J. Chem. Phys*., 40, 1622-1628 , 1964.
11. Besenbruch, G., Kana'an, A.S., et al., *J. Phys. Chem*., 69, 3174-3176, 1965.
12. Wiedemeier, H. and Gilles, P.W., *J. Chem. Phys*., 42, 2765-2769, 1965.
13. Berkowitz, J. and Chupka, W.A., *J. Chem. Phys*., 45, 4289-4302, 1966.
14. De Maria, G., Gingerich, K.A., et al., *J. Chem. Phys*., 44, 2531-2532, 1966.
15. Pelevin, O.V., Mil'vidskii, M.G., et la., *Izv. Akad. Nauk, SSR Neorg. Mater*., 2, 942-943, 1966.
16. Zmbov, K.F. and Margrave, J.L., *J. Chem. Phys*. 45, 3167-3170, 1966.
17. Zmbov, K.F. and Margrave, J.L., *J. Phys. Chem*., 70, 3379-3382, 1966.
18 Cater, E.D. and Johnson, E.W., *J. Chem. Phys*., 47, 5353-5357, 1967.
19. Cubicciotti, D., *J. Phys. Chem*., 71, 3067-3068, 1967.
20. Drowart, J. and Goldfinger, P., *Angew. Chem. Int. Ed. English*, 6, 581-596, 1967.
21. Drowart, J., Pattoret. A., and Smoes, S., *Pro. Brit. Cerem. Soc. Ogneupory*, 8, 67-89, 1967.
22. Gigerich, K.A., *J. Chem. Phys*., 47, 2192-2193, 1967.
23. Gingerich, K.A. and Blue, G.D., *J. Chem. Phys*., 47, 5447-5449, 1967.
24. Rovner, L.H., Drowart, A., et al., *Trans. Faraday Soc*., 63, 2906-2912, 1967.
25. Zmbov, K. F. and Margrave, J.L., *J. Inorg. Nucl. Chem*., 29, 59-63. 1967.
26. Zmbov, K. F. and Margrave, J.L., *J. Phys. Chem*., 71, 2893-2895, 1967.
27. Berkowitz, J. and Walter, T.A., *J. Chem. Phys*., 49, 1184-1189, 1968.
28. Colin, R. and Drowart, J., *Trans. Faraday Soc*., 64, 2611-2621, 1968.
29. Gay, A.G., *Dissociation Energies and Spectra of Diatomic molecules*. 3rd ed. Chapman and Hall, London, 1968.
30. Gingerich, K.A., *J. Chem. Phys*., 49, 19-24, 1968.
31. Gingerich, K.A., *J. Chem. Phys*., 49, 14-18, 1968.
32. Kant, A. and Strauss, B.H., *J. Chem. Phys*., 49, 3579-3582, 1968.
33. Kohl, F.J. and Carlson, K.D., *J. Am. Chem. Soc*., 90, 4814-4817, 1968.
34. Mclntyre, N.S., Mahieu, V.A.A., et al., *Trans. Faraday Soc*., 64, 3006-3010, 1968.
35. Uy, O.M., Muenow, D.W., et al., *Trans. Faraday Soc*., 64, 2998-3005, 1968.
36. Gingerich, K.A., *High Temp. Sci*., 1, 258-267, 1969.
37. Gingerich, K.A., *J. Phys. Chem*., 73, 2734-2741, 1969
38. Mahieu, A.V.A., Mclntyre, N.S., et al., *Chem. Phys. Lett*., 4, 198-200, 1969.
39. Smoes, S., Coppens, P., et al., *Trans. Faraday Soc*., 65, 682-687, 1969.
40. Uy, O.M. and Drowart, J., *Trans. Faraday Soc.,* 65, 3221-3230, 1969.
41. Bergman, C., Coppens, P., et al., *Trans. Faraday Soc*., 66, 800-808, 1970.
42. Clark, T.C. and Clyne, M.A.A., *Trans. Faraday Soc.,* 66, 877-885, 1970.
43. Darwent, D. de B., *Bond Dissociation Energies in Simple Molecules*. NBSDS-NBS, 31, GPO, Washington, DC, 1970.
44. Gingerich, K.A., *J. Chem. Phys*., 53, 746-748, 1970.
45. Gingerich, K.A., *Chem. Commun*., 580-581, 1970.
46. Mahieu, A.V.A., Peeters, R., et al., *Trans. Faraday Sco*., 66, 809-816, 1970.
47. Smith, P.K. and Peterson, D.E., *J. Chem. Phys*., 52, 4963-4972, 1970.
48. Stearns, C.A. and Kohl, F.J., *High Temp. Sci*., 2, 146-153, 1970.
49. Uy, O.M. and Drowart, J., *High Temp. Sci*., 2, 293-298, 1970.
50. Gingerich, K.A., *J. Chem. Phys*. 54, 2646-2650, 1971.
51. Gingerich, K.A., *J. Chem. Phys*., 54, 3720-3702, 1971.
52. Gingerich, K.A. and Piacente, V., *J. Chem. Phys*., 54, 2498-2503, 1971.
53. Kronekvist, M., Lagerqvist, A., et al., *J. Mol. Spectros*., 39, 516-518, 1971.
54. Smoes, S., Hugues, R., et al., Z. Naturforschchung Teil A, 26, 1934-1935, 1971.
55. Smoes, S., Myers, C.E., et al., *Chem. Phys. Lett*., 8, 10-21, 1971.
56. Uy, O.M. and Drowart, J., *Trans. Faraday Soc*., 67, 1293-1301, 1971.
57. Carbonel, M., Bergman, C., et la., *Colloq. Int. Cent. Nat. Rech. Sci*., 201, 311-323, 1972.
58. Faure, F.M., Mitchell, M.J., et al., *High Temp. Sci*., 4, 181-191, 1972.
59. Filippenko, N.V., Morozov, E.V., et al., *Izv. Vyssh. Ucheb. Zaved. Khim. Khim. Teknol*. 15, 1416-1418, 1972.
60. Gingerich, K.A., *J. Chem. Phys*. 56, 4239-4240, 1972.
61. Kordis, J. and Gingerich, K.A., *J. Phys. Chem*., 76, 2336-2341, 1972.
62. de Maria, G., Malaspina, L., et al., V., *J. Chem. Phys*., 56, 1978-1980, 1972.
63. Neckel, A. and Sodeck, G., *Monatsh. Chem*. 103, 367-382, 1972.
64. Piacente, V. and Desideri, A., *J. Chem. Phys*., 57, 2213-2215, 1972.
65. Piacente, V. and Malaspina, L., *J. Chem. Phys*. 56, 1780-1782, 1972.
66. Smoes, S., Depiere, D., et al., J., *Rev. Int. Hautes Temp. Refractaires*, 9, 171-176, 1972.
67. Smoes, S., Mandy, F., et al., *J. Bull. Scoc. Chim. Belg*. 81, 45-56, 1972.
68. Cuthill, A.M., Fabian, D.J. et la., *J. Phys. Chem*. 77, 2008-2011, 1973.
69. Drowart, J., Myers, C.E., et al., *High Temp. Sci*., 5, 482-488, 1973.
70. Fenochka, B.V. and Gorkienko, S.P., *Zh. Fizicheskoi Khim*., 47, 2445. 1973.
71. Gingerich, K.A., *Chem. Phys. Lett*., 23, 270-274, 1973.

72. Gingerich, K.A. and Blue, G.D., *J. Chem. Phys*. 59, 185-189, 1973.
73. Litzow, M.R. and Spalding, T.R., Physical inorganic chemistry, Monograph No. 2. Elsevier, New York, 1973.
74. Piacente, V. and Gingerich, K.A., *Z. Naturforsch Teil* A, 28, 316-317, 1973.
75. Srivastara, R.D. and Farber, M., *High Temp. Sci*., 5, 489-493, 1973.
76. Tanaka, Y., Yoshino, K., et al., *J. Chem. Phys*., 59, 564-565, 1973.
77. Way, K.R. and Stwalley, W.C., *J. Chem. Phys*., 59, 5298-5303, 1973.
78. Zollweg, R.J., *Int. Conf. Phenom. Ioniz. Gases*, 11th, 402, 1973.
79. Gingerich, K.A., *Chem. Phys. Lett*., 25, 523-526, 1974.
80. Gingerich, K.A., Cocke, D.L., et al., *J. Phys. Chem*., 78, 603-606, 1974.
81. Gurvich, L.V., Karachevtsev, G.V., et al., *Bond Energies of Chemical Bonds, Ionization Potentials and Electron Affinities*, Nauka, Moscow, 1974.
82. Kohl, F.J. and Stearns, C.A., *J. Phys. Chem*., 78, 273-274, 1974.
83. Nagai, S., Shinmei, M., et al., *J. Ionorg. Nucl. Chem*., 36, 1940-1945, 1974.
84. Neubert, A. and Zmbov, K.F., *High Tem. Sci*., 6, 303-308, 1974.
85. Piacente, V. and Balducci, G., *High Temp. Sci*., 6, 254-258, 1974.
86. Sullivan, C.L., Zehe, M.J., et al., *High Temp. Sci*., 6, 80-97, 1974.
87. Chatillon, C., Allibert, M., et al., *Com. Ren. Sean. Acad. Sci. Ser. C: Sci. Chim*. 280, 1505-1508, 1975.
88. Guggi, D.J., Neubert, A., et al., *Conf. Int. Thermodyn. Chim*., , [C.R.], 4th, 3, 124-131, 1975. Marseille, Fr.
89. Hildenbrand, D.L., *J. Chem. Phys*., 62, 3074-3079, 1975.
90. Ihle, H.R. and Wu, C.H., *J. Chem. Phys*., 63, 1605-1608, 1975.
91. Lindgren, B. and Nilsson, Ch., *J. Mol. Spectros*., 55, 407-419, 1975.
92. Steiger, R.P. and Cater, E.D., *High Temp. Sci*., 7, 288-300, 1975.
93. Steiger, R.A., and Cater, E.D. *High Temp. Sci*., 7, 204-214, 1975.
94. Abbasov, A.S., Azizov, T.Kh., et al., *Zh. Fiz. Khim*., 50, 2172, 1976.
95. Chashchina, G.I. and Shreider, E.Ya., *Zh. Priklad. Spektros*., 25, 163-165, 1976.
96. Clyne, M.A.A. and McDermid, I.S., *J. Chem. Soc. Faraday Trans*., 2, 72, 2252-2268, 1976.
97 Cocke, D.L., Gingerich, K.A., et al., *J. Chem. Soc. Faraday Trans*. 1, 72, 268-272, 1976.
98. Hildenbrand, D.L., *J. Chem. Phys*., 65, 614-618, 1976.
99. Piacente, V. and Balducci, G., *Dynamic Mass Spectrometry*. 4, 295-304, 1976.
100. Wu, C.H., *J. Chem. Phys*., 65, 3181-3186, 1976.
101. Yokozeki, A. and Menzinger, M., Chem. Phys., 14, 427-439, 1976.
102. Drowart, J. and Smoes, S.J., *J. Chem. Soc. Faraday Trans*. 2, 73, 1755-1767, 1977.
103. Jones, R.W. and Gole, J., *Chem. Phys*., 20, 311-318, 1977.
104. Kaposi, O., *Magy. Kem. Foly*., 83, 356-363, 1977.
105. Piacente, V. and Gingerich, K.A., *High Temp. Sci*., 9, 189-196, 1977.
106. Smoes, S. and Drowart, J., *J. Chem. Soc. Faraday Trans.* 2, 73, 1746-1754, 1977.
107. Zmbov, K.F., Wu, C.H., et al., *J. Chem. Phys*., 67, 4603-4607, 1977.
108. Balfour, W.J. and Lindgren, B., *Can. J. Phys.,* 56, 767-779, 1978.
109. Benson, S.W., *Chem. Rev*., 78, 23-43, 1978.
110. Drowart, J., Smoes, S., et al., *J. Chem. Thermodyn*., 10, 453-464, 1978.
111 Fries, J.A. and Cater, E.D., *J. Chem. Phys*., 68, 3978-3989, 1978.
112. Gingerich, K.A. and Choudary, U.V., *J. Chem. Phys.* 68, 3265-3271, 1978.
113. Gingerich, K.A. and Gupta, S.K., *J. Chem. Phys*., 69, 505-511, 1978.
114. Kingcade, J.E.Jr., Dufner, D.C., et al.,*High Temp. Sci.,* 10, 213-222, 1978.
115. Martin, E. and Barrow, R.F., *Physica Scrpta*, 17, 501-505, 1978.
116. Piacente, V. and Bladucci, G., *Adv. Mass Spectrom*., 7A, 626-630, 1978.
117. Smoes, S., Drowart, J., et al., *Adv. Mass Spectrom*., 7A, 622-625, 1978.
118. Smoes, S., Pattje, W.R., et al., *High Temp. Sci*., 10, 109-129, 1978.
119. Breford, E.J. and Engelke, F., *J. Chem. Phys*., 71, 1994-2002, 1979.
120. Engelke, F., *Chem. Phys*., 39, 279-284, 1979
121. Franzen, H.F. and Hariharan, A.H., *J. Chem. Phys*., 70, 4907-4915, 1979.
122. Gingerich, K.A., Haque, R., et al., *Thermochim. Acta*, 30, 61-71, 1979.
123. Huber, K.P. and Herzberg, G., *Molecular Spectra and Molecular Structure. 4, Constants of Diatomic Molecules*, Van Nostrand Reinhold, New York. 1979
124. Lau, K.H. and Hildenbrand, D.L. *J. Chem. Phys*., 71, 1572-1577, 1979.
125. Pelino, M., Piacente, V., et al., *Thermocheim. Acta*, 31, 383-386, 1979.
126. Pelino, M., Viswanadham, P., et al., *J. Phys. Chem*., 83, 2964-2969, 1979.
127. Piacente, V., *J. Chem. Phys*., 70, 5911-5912, 1979.
128. Rusin, A.D., Zhukov, E., et al., *Zh. Neorg. Khim*., 24, 1457-1461, 1979.
129. Su, T.M.R. and Riley, S.J., *J. Chem. Phys*., 71, 3194-3202, 1979.
130. Balducci, G. and Piacente, V., *J. Chem. Soc. Chem. Commun*., 1287-1288, 1980.
131. Behrens, R.G. and Feber, R.C., *Less-Common Met*., 75, 281-292, 1980.
132. Gingerich, K.A., *Chem. Soc. Faraday, Symp*., No. 14, 109-125, 1980.
133. Kiang, T. and Zare, R.N., *J. Am. Chem. Soc*., 102, 4024-4029, 1980.
134. Neubert, A., Ihle, H.R., et al., *J. Chem. Phys.,* 73, 1406-1409, 1980.
135. Su, T.M.R. and Riley, S.J., *J. Chem. Phys*., 72, 1614-1622, 1980
136. Su, T.M.R. and Riley, S.J., J. Chem. Phys., 72, 6632-6636, 1980.
137. Wu, C.H. and Ihle, H.R., *Adv. Mass Spectrom.,* 8A, 374-377, 1980.
138. Balducci, G., Ferro, D., et al., *High Temp. Sci*., 14, 207-212, 1981.
139. Busse, V.B. and Weil, K.G., *Ber. Bunsenges. Phys. Chem*. 85, 3098-313, 1981.
140. Hilpert, K., *Ber. Kernfo-rschungsankage Juelich*, JUEL-1744, 272, 1981.
141. Kimura, H., Asano, M., et al., *J. Nuecl. Matet*. 97, 259-264, 1981.
142. Kleinschmidt, P.D., Lau, K.H., et al., *J. Chem. Phys*., 74, 653-660, 1981.
143. Pitzer, K.S., *J. Chem. Phys*., 74, 3078-3079, 1981.
144. Rao, T.V.R., Reddy, R.R., et al., *J. Pure Appl. Phys*., 19, 1219-1220, 1981.
145. Riekert, G., Harbach, G.R., et al., *Z. Metallkd*., 72, 406-411, 1981.
146. Riekert, G., Lamparter, P., et al., *Z. Metallkd*., 72, 765-768, 1981.
147. Zmbov, K.F., Neubert, A., et al., *Z. Naturforsch. Teil A*, 36A, 914-915, 1981.
148. Gerber, G. and Moeller, R., *Symp. At Surf. Phys*., 168-171, 1982.
149. Grade, M. and Hirschwald, W., *Ber. Bunsenges. Phys. Chem*., 86, 899-907, 1982.
150. Hilpert, K., *J. Chem. Phys*., 77, 1425-1427, 1982.
151. Ishwar, N.B., Varma, M.P., et al., *Acta Phys. Polo. A*, A61, 503-508, 1982.
152. Lau, K.H., Brittain, R.D., et al., *J. Phys. Chem.,* 86, 4429-4432, 1982.
153. Neubert, A., Zmbov, K.F., *J. Chem. Phys*., 77, 5218-5223, 1982.
154. Piacente, V. and Gigli, R., *J. Chem. Phys*., 77, 4791-4792, 1982.
155. Rajamanicham, N., Prahllad, U.D., et al., *Pramana*, 18, 225-231, 1982.
156. Rao, P.S. and Rao, T.V.R., *J. Quant. Spectrosc. Radiat Transfer*, 27, 207-208, 1982.
157. Reddy, R.R. and Rao, T.V.R., *THEOCHEM*, 7, 49-52, 1982.
158. Nedelec, O. and Giroud, M., *J. Chem. Phys*., 79, 2121-2125, 1983.
159. Neubert, A. and Zmbov, K.F., *Chem. Phys*., 76, 469-478, 1983
160. Pedley, J.B. and Marshall, E.M., *J. Phys. Chem. Ref. Data*, 12, 967-1031, 1983.
161. Tromp, J.W., Le Roy, R.J., et al., *J. Mol. Spectros*., 100, 82-94, 1983
162. Wu, C.H., Ihle, H.R., et al., *Int. J. Mass Spectrom*., 47, 235-238, 1983.
163. Bondybey, V.E., *Chem. Phys. Lett*., 109, 436-441, 1984.
164. Botor, J.P. and Edwards, J.G., *J. Chem. Phys*., 81, 2185-2186, 1984.
165. Diemer, U., Weickenmeier, H., et al., *Chem. Phys. Lett*., 104, 489-495, 1984.
166. Gordienko, S.P., I*zv. Akad. Nauk SSSR, Neorg. Mater*., 20, 1472-1475, 1984.
167. Parks, E.K. and Wexler, S., *J. Phys. Chem*., 88, 4492-4494, 1984.
168. Hildenbrand, D.L., Gurvich, L.V., et al.,*The Chemical Thermodynamics of Actinide Elements and Compounds*, Part 13, Int. Atom. Ener. Age. Vienna, 1985.
169. Kowalski, A., Czajkowski, M., et al., *Chem. Phys. Lett*., 119, 368-370, 1985.
170. Weickenmeier, W., Diemer, U., et al., *J. Chem. Phys*., 82, 5354-5363, 1985.
171. Berkowitz, J., Curtiss, L.A., et al., *J. Chem. Phys*., 84, 375-384, 1986
172. Kingcade, J.E. and Gingerich, K.A., *J. Chem. Phys*., 84, 3432-3438, 1986.
173. Morse, M.D., *Chem. Rev*., 86, 1049-1109, 1986.
174. Shim, I., Kingcade, J.E., et al., *J. Chem. Phys*., 85, 6629-6636, 1986.
175. Tolbert, M.A. and Beauchamp, J.L., *J. Phys. Chem*., 90, 5015-5022, 1986.
176. Shim, I., Kingcade, J.E., et al., *Z. Phus. D*. 7, 261-269, 1987.

177. Berkowitz, J., *J. Chem.Phys*., 89, 7065-7076, 1988.
178. Buckner, S.W., Gord, J.R., et al., *J. Am. Chem. Soc*., 110, 6606-6612, 1988.
179. Du, K.Y. and Setser, D.W., *Chem. Phys. Lett*., 153, 393-400, 1988.
180. Gustavsson, T., Amiot, C., et al., *Mol. Phys*., 64, 279-292, 1988.
181. Herman, P.R., LaRocque, P.E., et al., *J. Chem. Phys*., 89, 4535-4549, 1988.
182. Hildenbrand, D.L. and Lau, K.H., *J. Chem. Phys*., 89, 5825-5828, 1988.
183. Koyama, T. and Yamawaki, M., *J. Nucl. Mater*. 152, 30-34, 1988.
184. Pak, K., Cai, M.F., et al., *Faraday Diss. Chem. Soc*., 86, 153-162, 1988.
185. Pianalto, F.S., O'Brien, L.C., et al., *J. Mol. Spectros*., 129, 348-353, 1988.
186. Shim, I., Kingcade, J.E., et al., *J. Chem. Phys*., 89, 3104-3112, 1988.
187. Taylor, S., Lemire, G., et al., *J. Chem. Phys*., 89, 5517-5523, 1988.
188. Zemke, W.T. and Stwalley, W.C., *Chem. Phys. Lett*., 143, 84-90, 1988.
189. Balakrishnan, A., Jones, W.J., et al., *Chem. Phys. Lett*., 155, 43-46, 1989.
190. Balducci, G., Di Nunzio. P.E., et al., *J. Chem. Phys*., 90, 406-412, 1989.
191. Callender, C.L., Mitchell., et al., *J. Chem. Phys*., 90, 5252-5261, 1989.
192. Chandrasekharaiah, M.S. and Gingerich, K.A., *in: Handbook on the Chemistry and Physics of Rare Earths*; Elserier, 1989, Vol. 12, Chapter 86, p. 409-431.
193. Fu, Z. and Morse, M.D., *J. Chem. Phys*. 90, 3417-3426, 1989.
194. Gal, J.F., Maria, P.C., et al., *Int. J. Mass Spectrom. Ion Proc*., 93, 87-94, 1989.
195. Hildenbrand, D.L. and Lau, K.H., *J. Chem. Phys*., 91, 4909-4911, 1989.
196. Hilpert. K. and Ruthardt, K. *Ber. Bunsenges. Phys. Chem*., 93, 1070-1078, 1989.
197. Kingcade, J.E.Jr. and Gingerich, K.A., *J. Chem. Soc. Faraday Trans*., 2, 85, 195-200, 1989.
198. Lau, K.H., Brittain, R.D., et al., *J. Chem. Phys*., 90, 1158-1164, 1989.
199. Merer, A. J., *Annu. Rev. Phys. Chem*., 40, 407-438, 1989.
200. Pelino, M., Gingerich, K.A., et al., *J. Chem. Phys*., 90, 1286-1288, 1989.
201. Amiot, C., *J. Chem. Phys*., 93, 8591-8604, 1990.
202. Devore, T.C., McQuaid, M., et al., *High Temp. Sci*., 30, 83-94, 1990.
203. Fu, Z., Lemire, G.W., et al., *J. Chem. Phys*., 93, 8420-8441, 1990.
204. Hildenbrand, D.L. and Lau, K.H., *J. Chem. Phys*., 93, 5983-5989, 1990.
205. Jeyagopal, T., Rajavel, S.R.K., et al., *Acta Phys. Hung*., 68, 145-147, 1990.
206. Lau, K.H. and Hildenbrand, D.L., *J. Chem. Phys*., 92, 6124-6130, 1990.
207. Lemire, G.W., Bishea, G.A., et al., *J. Chem. Phys*., 92, 121-132, 1990.
208. Simoes, J.A.M. and Beauchamp, J.L., *Chem. Rev*. 90, 629-688, 1990.
209. Spain, E.M. and Morse, M.D., *Int. J. Mass Spectrom. Ion Proc*., 102, 183-197, 1990.
210. Sunderlin, L.S., and Armentrouy, P.B., *J. Phys. Chem*., 94, 3589-3597, 1990.
211. Taylor, S., Spain, E.M., et al., *J. Chem. Phys*., 92, 2698-2709, 1990.
212. Taylor, S., Spain, E.M., et al., *J. Chem. Phys*., 92, 2710-2720, 1990.
213. Amiot, C., *J. Mol. Spectrosc*., 147, 370-382, 1991.
214. Armentrout, P.B. and Sunderlin, L.S., in Transition Metal Hydrides, Dedieu, A. ed. VCH Pub. New York, Ch. 1, p. 1-64, 1991.
215. Barkoskii, N.V., Tsirel'nikov, V.I., et al., *Teplofiz. Vys. Temp*., 29, 474-479, 1991.
216. Bharate, N.S., Bhartiya, J.B., et al., *Proc. Indian Natl. Sci. Acad. Part A*, 419-422, 1991.
217. Boltalina, O.V., Borshchevskii, A.Y., et al., *Zh. Fiz. Khim. SSSR*, 65, 884-899, 1991.
218. Chen, Y.M., Clemmer, D.E., et al., *J. Chem. Phys*., 95, 1228-1233, 1991.
219. Cockett, M.C.R., Nyulaszi, L., et al., *J. Electron Spectro. Related Phenom*., 57, 373-397, 1991.
220. Fellows, C.E., *J. Chem. Phys*., 94, 5855-5864, 1991.
221. Gurvich, L.V., Veyts, I.V., et al., Thermodynamic Properties of Individual Substances, 4th ed, Hemisphere Pub Corp, New York, 1991.
222. Hop, C.E.C.A. and McMahon, T.B., *J. Am. Chem. Soc*., 113, 355-357, 1991.
223. Rajamanickam, N., Palaniselvam, K., et al., *Acta Phys. Hung*., 70, 141-144, 1991.
224. Rajamanickam, N., Senthikumar, R.M., et al., *Acta Phys. Hung*., 70, 71-76, 1991.
225. Wan, Y.C., Kajitani, M., et al., *J. Chem. Phys*., 95, 6229-6237, 1991.
226. Hildenbrand, D.L. and Lau, K.H., *J. Chem. Phys*., 96, 3830-3833, 1992.
227. Hildenbrand, D.L. and Lau, K.H., *J. Chem. Phys*., 96, 2325-2328, 1992.
228. Hildenbrand, D.L. and Lau, K.H., *Pure Appl. Chem*., 64, 87-92, 1992.
229. Jordan, K.J., Lipson, R.H., et al., J. Phys. Chem. 96, 4778-4787, 1992.
230. Shim, I., Pelino, M., et al., *J. Chem. Phys*., 97, 9240-9248, 1992.
231. Spain, E.M. and Morse, M.D., *J. Chem. Phys*., 97, 4605-4615, 1992.
232. Spain, E.M. and Morse, M.D., *J. Phys. Chem*., 96, 2479-2486, 1992.
233. Yoo, R.K., Ruscic, B., et al., *Chem. Phys*., 166, 215-227, 1992.
234. Yoo, R.K., Ruscic, B., et al., *J. Chem. Phys*., 96, 6696-6709, 1992.
235. Behm, J.M., Arrington, C.A., et al., *J. Chem. Phys*., 99, 6409-6415, 1993.
236. Behm, J.M., Arrington, C.A., et al., *J. Chem. Phys*., 99, 6394-6408, 1993.
237. Chen, Y.M., Clemmer, D.E., et al., *J. Chem. Phys*., 98, 4929-4936, 1993.
238. Fawzy, W.M., Le Roy, R.J., et al., *J. Chem. Phys*., 98, 140-149, 1993.
239. Jordan, K.J., Bascal, H.A., et al., *J. Mol. Spectrosc*., 159, 144-155, 1993.
240. Lipson, R.H., Jordan, K.J., et al., *J. Chem. Phys*., 98, 959-967, 1993.
241. McLoughlin, P.W., Park, C.R., et al., *J. Mol. Spectros*., 162, 307-326, 1993.
242. Menendez, M., Garay, M., et al., *J. Chem. Phys*., 99, 2760-2764, 1993.
243. Morse, M.D., in *Advances in metal and semiconductor clusters*, 1: Spectroscopy and dynamics, 83-121, 1993.
244. Morley, G.P., Lambert, I.R., et al., *J. Chem. Soc. Faraday Trans*., 89, 3865-3875, 1993.
245. Rajamanickam, N., Ponraj, N., et al., *Collection of Czech. Chem. Commun*., 58, 1485-1490, 1993.
246. Ruscic, B. and Berkowitz, J., *J. Chem. Phys*., 99, 5840-5848, 1993.
247. Stangassinger, A., Scheuchenpflug, J., et al., *Chem. Phys*., 178, 533-546, 1993.
248. Watson, L.R., Thiem, T.L., et al., *J. Phys. Chem*., 97, 5577-5580, 1993.
249. Zemke, W.T., Stwalley, C., et al., *Chem. Phys. Lett*., 177, 412-418, 1993.
250. Arrington, C.A., Blume, T., et al., *J. Phys. Chem*., 98, 1398-1406, 1994.
251. Behm, J.M., Morse, M.D., et al., *J. Chem. Phys*., 101, 5441-5453, 1994.
252. Brock, L.R., Pilgrim, J.S., et al., *Chem. Phys. Lett*., 230, 93-98, 1994.
253. Clerbaux, C. and Colin, R., *J. Mol. Spectrosc*., 165, 334-348, 1994.
254. Haire, R.G., *J. Alloys Compd*., 213/214, 185-190, 1994.
255. James, A.M., Kowalczyk, P., et al., *J. Chem. Phys*., 101, 4485-4495, 1994.
256. James, A.M., Kowalczyk, P., et al., *J. Mol. Spectros*. 168, 248-257, 1994.
257. Rajamanickam, N., Dhuvaragaikannan, N., et al., *Acta Phys. Hungarica*, 74, 385-389, 1994.
258. Samoilova, I.O. and Kazenas, E.K. *Ivz. Rossiskoi Akad. Nauk, Metally*, No. 3, 36-39, 1994.
259. Schroder, D., Hrusak, J., et al., *Angewandt Chem. Int. Ed. Engl*.,33, 212-214, 1994.
260. Tomaszkiewicz, I., Susman, S., et al., *J. Chem. Thermodyn*., 26, 1081-1093, 1994.
261. Viswanathan, R., Baba, M.S., et al., *Spectrochim. Acta, Part B*, 49B, 243-250, 1994.
262. Chen, Y.M. and Armentrout, P.B., *J. Phys. Chem*., 99, 11424-11431, 1995.
263. Chen, Y.M. and Armentrout, P.B.,*J. Am. Chem. Soc*., 117, 9291-9304, 1995.
264. Clevenger, J.O. and Tellinghuisen, J., *J. Chem. Phys*., 103, 9611-9620, 1995.
265. Coppens, P. and Drowart, J., *Chem. Phys. Lett*., 243, 108-113, 1995.
266. Drake, L.R., Simons, J.W., et al., *J. Phys. Chem*., 99, 11350-11356, 1995.

267. Gondal, M.A., Khan, M.A., et al., *Chem. Phys. Lett*., 243, 94-101, 1995.
268. Hildenbrand, D.L., *J. Chem. Phys*., 103, 2634-2641, 1995.
269. Hildenbrand, D.L. and Lau, K.H., *J. Chem. Phys*., 102, 3769-3775, 1995.
270. Hwang, E. and Dagdigian, P.J., *Chem. Phys. Lett*., 233, 483-488, 1995.
271. Langenberg, J.D. and Morse, M.D., *Chem. Phys. Lett*., 239, 25-30, 1995.
272. Nakajima, A., Taguwa, T., et al., *J. Chem. Phys*., 102, 660-665, 1995.
273. O'Hare, P.A.G., *J. Chem. Thermodyn*., 27, 921-926, 1995.
274. Pilgrim, J.S. and Duncan, M.A., *Chem. Phys. Lett*., 232, 335-340, 1995
275. Samoilova, I.O. and Kazenas, E.K., *Ivz. Rossiskoi Akad. Nauk Metally*, No. 1, 33-35, 1995.
276. Stangassinger, A., Mane, I., et al., *Chem. Phys*., 201, 227-235, 1995.
277. Tellinghuisen, J., *J. Mol. Spectrosc*., 173, 223-236, 1995.
278. White, J.B., Dulick, M., et al., *J. Mol. Spectros*. 169, 410-420, 1995.
279. Zhao, Y. and Setser, D.W., *J. Phys. Chem*., 99, 12179-12187, 1995.
280. Armentrout, P.B. and Kickel, B.L., in: *Organometallic Ion Chemistry*, Freiser. ed. Kluwer, Dordrecht, The Netherland, 1996. p. 1-45
281. Gurvich, L.V., Veyts, I.V., et al., *Thermodynamic Properties of Individual Substances*, vol. 3, Begell House, New York, 1996.
282. Hedgecock, I.M., Naulin, C., et al., *Chem. Phys*., 207, 379-387, 1996.
283. Hildenbrand, D.L., *J. Chem. Phys*., 105, 10507-10510, 1996.
284. Hildenbrand, D.L., *High Tem. Materials Sci*. 35, 151-158, 1996.
285. Hildenbrand, D.L. and Lau, K.H., *Chem. Phys. Lett*., 263, 145-147, 1996.
286. Hildenbrand, D.L. and Lau, K.H., *High Tem. Materials Sci*. 35, 11-20, 1996
287. Jones, K.M., Maleki, S., et al., *Physical Rev. A*, 54, R1006-R1009, 1996.
288. Kazenas, E.K., Bol'shikh, M.A., et al., *Izv. Rossiiskoi Akad. Nauk Metally*, No. 3, 29-35, 1996.
289. O'hare, P.A.G., Zywocinski, A., et al., *J. Chem. Thermodyn*., 28, 459-480, 1996.
290. Viswanathan, R., Schmude, R.W., et al., *J. Phys. Chem*. 100, 10784-10786, 1996.
291. Brugh, D.J. and Morse, M.D., *J. Chem. Phys*., 107, 9772-9782, 1997.
292. Hildenbrand, D.L., and Lau, K.H., *J. Chem. Phys*., 107, 6349-6352, 1997.
293. Nagarajan, K. and Rajamanickam, N., *Acta Phys. Slovaca*, 47, 485-490, 1997.
294. Tomaszkiewicz, I., Hope, G.A., et al., *J. Chem. Thermodyn*., 29, 1031-1045, 1997.
295. Balducci, G., Gigli, G., et al., *J. Chem. Phys*. 109, 4384-4388, 1998
296. Chase, M.W.Jr., NIST-JANAF Thermochemical Table, 4th ed. *J. Phys. Chem. Ref. Data*, Monograph 9, 1998.
297. Langenberg, J.D. and Morse, M.D., *J. Chem. Phys*., 108, 2331-2335, 1998.
298. NIST Chemistry Webbook, Mallard, W.G., ed., accessed August 1996, http://webbook.nist.gov, updated frequently.
299. Schmude, R.W. and Gingerich, K.A., *J. Chem. Phys*., 109, 3069-3071, 1998.
300. Shim, I., Baba, M.S., et al., *J. Phys. Chem*. A, 102, 10763-10767, 1998.
301. Simard, B., Lebeault-Dorget, M.A., et al., *J. Chem. Phys*., 108, 9668-9674, 1998.
302. Stangassinger, A., Knight, A.M., et al., *J. Chem. Phys*., 108, 5733-5741, 1998.
303. Alekeev, V., Setser, D.W., et al., *J. Mol. Spectros*., 194, 61-72, 1999.
304. Armentrout, P.B. and Chen, Y.M., *J. Am. Soc. Mass Spectrom*., 10, 821-839, 1999.
305. Diefenbach, M., Bronstrup, M., et al., *J. Am. Chem. Soc*., 121, 10614-10625, 1999.
306. Hildenbrand, D.L., Lau, K.H., et al., *J. Chem. Phys*., 111, 1337-1338, 1999.
307. Jesinger, R.A. and Squires, R.R., *Int. J. Mass Spectrom*., 185/186/187, 745-757, 1999.
308. Reddy, R.R., Ahammed, Y.N., et al., *Astrophys. Space Sci*., 262, 223-240, 1999.
309. Rostai, M. and Wahlbeck, P.G., *J. Chem. Thermodyn*., 31, 255-261, 1999.
310. Cook, P.A., Langford, S.R., et al., *J. Chem. Phys*. 113, 994-1004, 2000.
311. Hildenbrand, D.L. and Lau, K.H., *Chem. Phys. Lett*., 319, 95-98, 2000.
312. Lei, J. and Dagdigian, P.J., *J. Chem. Phys*., 113, 602-610, 2000.
313. Prithivikumaran, N., Gomez, M.F., et al., *Asian J. Spectros*., 4, 187-189, 2000.
314. Raja, V. and Rajamanickam, N., *Ukrains'kii Fizichnii Z*., 45, 914-917, 2000.
315. Raja, V. and Rajamanickam, N., *Astrophys. Space Sci*., 271, 59-63, 2000.
316. Reddy, R.R., Ahammed, Y.N., et al., *J. Quantit. Spectros. Radiat. Trans*., 66, 501-508, 2000.
317. Sickafoose, S.M., Langenberg, J.D., et al., *J. Phys. Chem*. A, 104, 3521-3527, 2000.
318. Sievers, M.R., Chen, Y.M., et al., *Int. J. Mass Spectrom*., 195/196, 149-170, 2000.
319. Simard, B., Mitchell, S.A., et al., in *Metal-Ligand Interactions in Chemistry, Physics and Biology*, Kluwer, Dordrecht, 2000, p. 329.
320. Urena, F.P., Gomez, M.F., et al., *Astrophys. Space Sci*., 272, 345-352, 2000.
321. Armentrout, P.B., *Annu. Rev. Phys. Chem*., 52, 423-461, 2001.
322. Fu, Z., Russon, L.M., et al., *Int. J. Mass Spectrom*., 204, 143-157, 2001.
323. Hildenbrand, D.L., Lau, K.H., et al., *J. Phys. Chem*. A, 105, 4114-4117, 2001.
324. Meloni, G., Thomson, L.M., et al., *J. Chem. Phys*., 115, 4496-4501, 2001.
325. Reynard, L., Evans, C.J., et al., *J. Mol. Spectrosc*., 205, 344-346, 2001.
326. Tzeli, D. and Mavridis, A., *J. Phys. Chem*. A, 105, 1175, 2001
327. Brown, J.R. and Schwerdtfeger, P., *J. Am. Soc. Mass Spectrom*., 13, 485-492, 2002.
328. Brugh, D.J. and Morse, M.D., *J. Chem. Phys*., 117, 10703-10714, 2002.
329. Goncharov, V.B. and Fialko, E.F., *J. Struc. Chem*. 43, 777-782, 2002.
330. Koszinowski, K., Schroder, D., et al., *Inorg. Chem*., 41, 5882-5890, 2002.
331. Meloni, G. and Gingerich, K.A., *J. Chem. Phys*., 116, 6957-6960, 2002.
332. Michel, M., Korolkov, M.V., et al., *Phys. Chem. Chem. Phys*., 4, 4083-4086, 2002.
333. Ruscic, B., Wagner, A.F., et al., *J. Phys. Chem*. A, 106, 2727-2747, 2002.
334. Santos, M., Marcalo, J., et al., *J. Phys. Chem*. A, 106, 7190-7194, 2002.
335. Shim, I., Baba, S.M., et al., *Chem. Phys*., 277, 9-20, 2002.
336. Tao, C., Teslja, A., et al., *J. Chem. Phys*. 116, 9239-9248, 2002.
337. Balducci, G., Ciccioli, A., et al., *Chem. Phys. Lett*., 369, 449-453, 2003.
338. Gibson, J.K., *J. Phys. Chem*. A, 107, 7891-7899, 2003.
339. Gibson, J.K. and Haire, R.G., *Radiochim. Acta*, 91, 441-448, 2003.
340. Hildenbrand, D.L. and Lau, K.H., *Chem. Phys. Lett*., 379, 37-39, 2003.
341. US NASA, http://jpldataeval.jpl.nasa.gov, Feb 24, 2003.
342. Sadeghi, N., Kowalczyk, P., et al., *Phys. Chem. Chem. Phys*., 5, 3443-3452, 2003.
343. Tao, C. and Dagdigian, P.J., *J. Chem. Phys*., 118, 1242-1252, 2003.
344. Blagojevic, V., Koyanagi, G.K., et al., *Chem. Phys. Lett*., 389, 303-308, 2004.
345. Hildenbrand, D.L., Lau, K.H., et al., *J. Phys. Chem.* A, 108, 3688-3691, 2004
346. Himmel, H.J. and Bihlmeier, A., *Chem. Euro. J*. 10, 627-633, 2004.
347. Hirata, S., Yanai, T., et al., *J. Chem. Phys*. 120, 3297-3310, 2004.
348. Jerdev, D.I., Prins, R., et al., *J. Phys. Chem*. B, 108, 14417–14427, 2004.
349. Lodders, K., *J. Phys. Chem. Ref. Data*. 33, 357-367, 2004.
350. Tao, C. and Dagdigian, P.J., *J. Chem. Phys*. 120, 7512-7519, 2004.
351. Zhang, Y.P., Cheng, C.H., et al., Phys. Rev. Lett., 92, 203003/1–203003/4, 2004.

TABLE 2. Enthalpy of Formation of Gaseous Atoms

Atom	$\Delta_f H^o_{298}$/kJ mol^{-1}	Ref.
Ac	406	5
Ag	284.9±0.8	2
Al	330.9±4.0	2
Am	284	6
As	302.5±13	1
Au	368.2±2.1	1
B	565±5	2
Ba	179.1±5.0	3
Be	324±5	2
Bi	209.6±2.1	1
Bk	310	6
Br	111.87±0.12	3
C	716.68±0.45	2
Ca	177.8±0.8	2
Cd	111.80±0.20	2
Ce	420.1±2.1	4
Cf	196	6
Cl	121.301±0.008	2
Cm	386	6
Co	426.7	3
Cr	397.48±4.2	3
Cs	76.5±1.0	2
Cu	337.4±1.2	2
Dy	290.4±2.1	4
Er	316.4±2.1	4
Es	133	6
Eu	177.4±2.1	4
F	79.38±0.30	2
Fe	415.5±1.3	3
Ga	271.96±2.1	3
Gd	397.5±2.1	4
Ge	372±3	2
H	217.998±0.006	2
Hf	618.4±6.3	3
Hg	61.38±0.04	2
Ho	300.6±2.1	4
I	106.76±0.04	2
In	243±4	1
Ir	669±4	1
K	89.0±0.8	2
La	431.0±2.1	4
Li	159.3±1.0	2
Lu	427.6±2.1	4
Mg	147.1±0.8	2
Mn	283.3±4.2	3
Mo	658.98±3.8	3
N	472.68±0.40	2
Na	107.5±0.7	3
Nb	733.0±8	3
Nd	326.9±2.1	4
Ni	430.1±8.4	3
Np	464.8	6
O	249.18±0.10	2
Os	787±6.3	1
P	316.5±1.0	2
Pa	563	5
Pb	195.2±0.8	2
Pd	376.6±2.1	1
Pr	356.9±2.1	4
Pt	565.7±1.3	1
Pu	345	6
Ra	159	5
Rb	80.9±0.8	2
Re	774±6.3	1
Rh	556±4	1
Ru	650.6±6.3	1
S	277.17±0.15	2
Sb	264.4 ±2.5	1
Sc	377.8±4	1
Se	227.2±4	1
Si	450.0±8	2
Sm	206.7±2.1	4
Sn	301.2±1.5	2
Sr	164.0±1.7	3
Ta	782.0±2.5	1
Tb	388.7±2.1	4
Tc	678	5
Te	196.6±2.1	1
Th	602±6	2
Ti	473±3	2
Tl	182.2±0.4	1
Tm	232.2±2.1	4
U	533±8	2
V	515.5±8	3
W	851.0±6.3	3
Y	424.7±2.1	4
Yb	155.6±2.1	4
Zn	130.40±0.40	2
Zr	610.0±8.4	3

References

1. Brewer, L. and Rosenblatt, G.M., *Adv. High Tem. Chem.,* 2, 1-83, 1969.
2. Cox, J.D., Wagman, D.D., and Medvedev, V.A., Eds., CODATA Key Values for Thermodynamics, Hemisphere Publishing Corporation, New York, 1989; updated e-version: http:www.codata.org/codata.
3. NIST Chemistry WebBook, http://webbook.nist.gov. NIST-JANAF Thermochemical Table 4th Edition, Ed. Chase, M.W.Jr., ACS, AIP, New York, 1998.
4. Chandrasekharaiah, M.S. and Gingerich, K.A., Thermodynamic properties of gaseous species, in Handbook on the Chemistry and Physics of Rare Earths; Gschneidner, K.A., Jr, Ering, L., Eds. Elsevier, Amsterdam, 1989, Vol. 12, Chapter 86, p. 409-431.
5. Lias, S.G. et al., Gas-phase ion and neutral thermochemistry, *J. Phys. Chem. Ref. Data,* 17, Supl. 1, 1988.
6. Klenschmidt, P.D., et al., *High Tem. Sci.,* 19, 267-274, 1985.

TABLE 3. Bond Dissociation Energies in Polyatomic Molecules

The D^o_{298} values in polyatomic molecules are notoriously difficult to measure accurately since the mechanism of the kinetic systems involved in many of the measurements are seldom straightforward. Thus, much lively controversy has taken place in the literature and is likely to continue for some time to come. We will continue to update and present our assessment of the most reliable BDE data every year.

Many D^o_{298} values in this table are derived by the equation

$$D^o_{298}(\text{R-X}) = \Delta_f H^o(\text{R}) + \Delta_f H^o(\text{X}) - \Delta_f H^o(\text{RX})$$

Here, the enthalpies of formation of the atoms and radicals are taken from Tables 2 and 4, respectively, and the enthalpies of formation of the molecules are from sources listed in the references. Table 3 is devided into sections for H-C, C-C, C-halogen, O-, N-, S-, and Si-X BDEs. The boldface in the species indicates the dissociated fragment.

Bond	D^o_{298}/kJ mol^{-1}	Ref.
(1) C-H BDEs		
CH_3-**H**	439.3 ±0.4	1
CH_3CH_2-**H**	420.5±1.3	1
$CH_3CH_2CH_2$-**H**	422.2±2.1	1
$CH_3C\mathbf{H}_2CH_3$	410.5±2.9	1
$CH_3CH_2CH_2CH_2$-**H**	421.3	1
$CH_3C\mathbf{H}_2CH_2CH_3$	411.1±2.2	1
$(CH_3)_2CHCH_2$-**H**	419.2±4.2	1
$(CH_3)_3C$-**H**	400.4±2.9	1
$(CH_3)_3CCH_2$-**H**	419.7±4.2	1
$(CH_3CH_2)C\mathbf{H}(CH_3)_2$	400.8	1
$CH_3C\mathbf{H}_2(CH_2)_2CH_3$	415.1	1
$(C_3H_7)C\mathbf{H}(CH_3)_2$	396.2±8.4	1
$CH_3CH(CH_3)C\mathbf{H}(CH_3)_2$	399.2±13.0	1
$CH_3C\mathbf{H}_2(CH_2)_3CH_3$	410	1
$CH_3C\mathbf{H}_2(CH_2)_4CH_3$	410	1
HCC-**H**	557.81±0.30	1
HCCCC-**H**	539±12	1
$CHCCH_2$-**H**	372.0±4.2	1
CH_3CCCH_2-**H**	365.7±8.4	1
$HCCC\mathbf{H}_2CH_3$	355.6	1
CH_2=$CHCCCH_2$-**H**	363.3	1
$CH_3CCC\mathbf{H}_2CH_3$	365.3±9.6	1
$HCCC\mathbf{H}_2CH_2CH_3$	349.8±8.4	1
$HCCC\mathbf{H}(CH_3)_2$	345.2±8.4	1
$CH_3CCC\mathbf{H}(CH_3)_2$	344.3±11.3	1
HCCCCCC-**H**	~543±13	1
H_2C=CH-**H**	465.3±3.3	1
CH_2=C=CH-**H**	371.1±12.6	1
CH_3CH=CH-**H**	464.8	1
CH_2=$CHCH_2$-**H**	369±3	1
CH_2=CH-CH_2CH_2-**H**	410.5	1
CH_2=$CHC\mathbf{H}_2CH_3$	350.6	1
CH_2=$C(CH_3)CH_2$-**H**	362.8±2.5	1
CH_2=$CHCH$=$CHCH_2$-**H**	347.3±12.6	1
$(CH_2$=$CH)_2CH$-**H**	320.5±4.2	1
CH_2=$CHC\mathbf{H}_2CH_2CH_3$	348.8	1
CH_2=$CHC\mathbf{H}(CH_3)_2$	332.6±7.1	1
CH_2=$C(CH_3CH_2)CH_2$-**H**	356.1±8.4	1
$(CH_2$=$CH)_2C(CH_3)$-**H**	322.2	1
H-*cyclo*-C_3H_5	444.8±1.0	1
H-CH_2-*cyclo*-C_3H_5	407.5±6.7	1
H-*cyclo*-C_4H_7	405.0±4.2	1
H-*cyclo*-C_5H_9	400.0±4.2	1
H-*cyclo*-C_6H_{11}	416.3	1
H-C_6H_5	472.2±2.2	1
H-$CH_2C_6H_5$	375.5±5.0	22
H-$CH(CH_3)C_6H_5$	357.3±6.3	1
H-$CH(C_6H_5)_2$	353.5±2.1	1
H-$C(CH_3)_2C_6H_5$	348.1±4.2	1
H-$C(C_6H_5)_3$	338.9±8.4	1
1-**H**-C_8H_7	469.4±5.4	1
2-**H**-C_8H_7	468.2±5.9	1
H–CF_3	445.2±2.9	1
H–CHF_2	431.8±4.2	1
H–CH_2F	423.8±4.2	1
H–$CClF_2$	421.3±8.4	1
H–CCl_2F	410.9±8.4	1
H–$CBrF_2$	415.5±12.6	1
H–CHClF	421.7±10.0	1
H–CCl_3	392.5±2.5	1
H–$CHCl_2$	407.1±4.2	1
H–CH_2Cl	419.0±2.3	1
H–CFClBr	413±21	1
H–CHClBr	406.0±2.4	14
H–CCl_2Br	387±21	1
H–$CClBr_2$	371±21	1
H–CBr_3	399.2±8.4	1
H–$CHBr_2$	417.1±7.5	1
H–CH_2Br	427.2±2.4	14
H–CHI_2	431.0±8.4	1
H–CH_2I	431.6±2.8	1
CF_3CF_2–**H**	429.7±2.1	1
CHF_2CF_2–**H**	431.0±18.8	1
CH_2FCF_2–**H**	433.0±14.6	1
CHF_2CFH–**H**	426.8±14.6	1
CF_3CH_2–**H**	446.4±4.5	1
CH_3CF_2–**H**	416.3±4.2	1
CH_2FCHF–**H**	413.4±12.6	1
CHF_2CH_2–**H**	433.0±14.6	1
CH_2FCH_2–**H**	433.5±8.4	1
CH_3CHF–**H**	410.9±8.4	1
CF_3CHCl–**H**	425.9±6.3	1
CF_3CClBr–**H**	404.2±6.3	1
$CClF_2CHF$–**H**	412.1±2.1	1
CCl_3CCl_2–**H**	397.5±8.4	1
$CHCl_2CCl_2$–**H**	393.3±8.4	1
CH_3CCl_2–**H**	397.9±5.0	1
CH_3CHCl–**H**	406.6±1.5	1
CH_2ClCH_2–**H**	423.1±2.4	1
CH_3CBr_2–**H**	397.1±5.0	1
CH_2BrCH_2–**H**	415.1±8.4	1
CH_3CHBr–**H**	406.7±4.2	1
CF_2=CF–**H**	464.4±8.4	1
$CF_3CF_2CF_2$–**H**	432.2	1
CH_3CH_2CHCl–**H**	407.0±3.5	1
CH_2=CH-CHF–**H**	370.7±4.6	1
CH_2=CHCHCl–**H**	370.7±4.6	1
CH_2=CHCHBr–**H**	374.0±4.6	1
H–C_6F_5	487.4	1
H–CH_2OH	401.92±0.63	1
$C\mathbf{H}_2CHOH$	467±11	1
$CH_3C\mathbf{H}_2OH$	396.6	1
$C\mathbf{H}_3CH_2OH$	421.7±8	1
$CH_3CH_2C\mathbf{H}_2OH$	392	1
$CH_3C\mathbf{H}_2CH_2OH$	394.6±8.4	1
$C\mathbf{H}_3CH_2CH_2OH$	406.3±8.4	1
$(CH_3)_2C\mathbf{H}OH$	380.7±4.2	1
$(C\mathbf{H}_3)_2CHOH$	394.6±8.4	1
CH_2=$CHC\mathbf{H}_2OH$	341.4±7.5	1
$(C\mathbf{H}_3)_3COH$	418.4±8.4	1
$(CH_2$=$CH)_2C\mathbf{H}OH$	372.4	1
$Ph_2C\mathbf{H}OH$	315.5±6.3	1
$CH_3C\mathbf{H}(OH)_2$	~ 385	1
$(C\mathbf{H}_2OH)_2$	385.3	1
$HOCH_2(CH_2)_2(OH)CH$–**H**	399.2	1
$C\mathbf{H}_3OCH_3$	402.1	1
$C\mathbf{H}F_2OCF_3$	443.5±4.2	1
$C\mathbf{H}F_2OCHF_2$	435.1±4.2	1
$C\mathbf{H}_3OCF_3$	426.8±4.2	1
$C\mathbf{H}_3OCH_2CH_3$	389.1	1
$(CH_3)_3COC(C\mathbf{H}_3)_3$	402.1	5
$CH_3C\mathbf{H}_2OCH_2CH_3$	389.1	1
$CH_3C\mathbf{H}_2$Ot-$C(CH_3)_3$	405.4	1
$C\mathbf{H}_3OPh$	385	5
H-2-oxiran-2-yl	420.5±6.5	1
H-tetrahydrofuran-2-yl	385.3±6.7	1
HC(O)–**H**	368.40±0.67	1

Bond	D^o_{298}/kJ mol^{-1}	Ref.
FC(O)–**H**	423	1
$CH_3C(O)$–**H**	374.0±1.3	1
$CF_3C(O)$–**H**	380.7±8.4	1
$C_2H_5C(O)$–**H**	371.1	1
CH_2=CHC(O)–**H**	372.8	1
$C_3H_7C(O)$–**H**	371.2	5
iso-$C_3H_7C(O)$–**H**	364.5	5
$C_4H_9C(O)$–**H**	372	5
$(CH_3)_2CHCH_2C(O)$–**H**	362.5	5
$C_2H_5CH(CH_3)C(O)$–**H**	360.8	5
tert-BuC(O)–**H**	375.1	5
$Et_2CHC(O)$–**H**	367.2	5
$CH_3(CH_2)_8C(O)$–**H**	373.3	5
$C_6H_5C(O)$–**H**	371.1±10.9	1
$PhCH_2C(O)$–**H**	362	5
$PhC(CH_3)_2C(O)$–**H**	362.9	5
H–CH=C=O	448.1	1
$CH_3C(O)H$	394.5±9.2	1
$CH_3C(O)Cl$	≤423.4	1
$CH_3CH_2C(O)H$	383.7	1
CH_3COCH_3	401.2±2.9	1
$CF_3C(O)CH_3$	465.6	1
$CH_3COCH_2CH_3$	403.8	1
$MeCOCH_2Me$	389.9	1
$EtCOCH_2Me$	396.5±2.8	5
$CH_3CH_2COC_6H_5$	402.8±3.6	5
$MeCH_2COPh$	388.7	1
H–C(O)OH	404.2	1
$CH_3C(O)OH$	398.7±12.1	1
$ClCH_2C(O)OH$	398.9	5
H–$C(O)OCH_3$	399.2±8.4	1
$CH_3C(O)OCH_3$	406.3±10.5	1
$CH_3C(O)OCH_3$	404.6	1
$CH_3C(O)OCH_2CH_3$	401.7	1
$CH_3C(O)OPh$	419.2±5.4	1
$CH_3CH_2C(O)OEt$	400	1
$PhCH_2C(O)OEt$	370.7	1
$Me_2CHC(O)OEt$	387.4	1
PhCHMe(C(O)OEt)	358.2	1
H-furaylmethyl	361.9±8.4	1
CH_3NH_2	392.9±8.4	1
CH_3N=CH_2	407.9±14.6	1
$CH_3CH_2NH_2$	377.0±8.4	1
$C_2H_5CH_2NH_2$	380.7±8.4	1
$C_3H_7CH_2NH_2$	393.3±8.4	1
$C_4H_9CH_2NH_2$	387.7±8.4	1
$HOCH_2CH_2NH_2$	379.5±8.4	1
$(CH_3CH_2)_2NH$	370.7±8.4	1
$(C_3H_7CH_2)_2NH$	379.9±8.4	1
$(C_4H_9CH_2)_2NH$	384.5±8.4	1
$(C_2H_5)_2NCH_2CH_3$	379.5±1.7	1
$(C_2H_5CH_2)_3N$	376.6±8.4	1
$((CH_3)_2CCH_2)_3N$	388.3±8.4	1
$(Bu)_2NCH_2(nPr)$	381±10.0	1
$((CH_3)_2CH)_3N$	387.0±8.4	1
$(CH_3)_2CHNH_2$	372.0±8.4	1
CH_3NHCH_3	364.0±8.4	1
$(CH_3)_3N$	380.7±8.4	1
tert-$BuN(CH_3)_2$	376.6±8.4	1
$((HOCH_2CH_2)_2(CH_3))N$	364.4±8.4	1
$(HOCH_2CH_2)_3N$	379.9±8.4	1
$((HOCH_2)CH(CH_3))_3N$	379.9±8.4	1
$PhCH_2NH_2$	368.2	1
$PhN(CH_2CH_3)_2$	383.3±4.2	1
Ph_2NCH_3	379.5±1.7	1
$PhN(CH_2Ph)_2$	357.3±8.8	1
$N(CH_2Ph)_3$	372.8±2.5	1
$PhN(CH_2CH$=$CH_2)_2$	339.3±2.9	1
$N(CH_2CH$=$CH_2)_3$	345.6±3.3	1
$H_2NNH(CH_3)$	410	1
$HNN(CH_3)_2$	410	1
$(CH_3)_2NC_6H_5$	383.7±5.4	1
H–CN	528.5±0.8	1
CH_3CN	401.7	1
CH_3CH_2CN	393.3±12.6	1
$PhCH_2CN$	344.3	1
$C_6F_5CH_2CN$	350.6	1
$CH_2(CN)_2$	366.5	1
$CH_2(CN)(NH_2)$	355.2	1
$(CH_3)_2CHCN$	384.5	1
CH_3NC	389.1±12.6	4
H–HCNN	405.8±8.4	1
H–CNN	331±17	1
CH_3NO_2	439.7	10
$CH_3CH_2NO_2$	410.5	1
$C_2H_5CH_2NO_2$	410.5	1
Me_2CHNO_2	396.2	1
$C_6H_5C(NO_2)CHCH_3$	357.3	1
H–C(S)H	399.6±5.0	1
CH_3SH	392.9±8.4	1
CH_3SCH_3	392.0±5.9	1
$PhSCH_3$	389.1	1
$PhCH_2SPh$	352.3	1
$(PhS)_2CHPh$	341	1
$PhSCHPh_2$	344.8	1
CH_3SOCH_3	393.3	1
$CH_3SO_2CH_3$	414.2	1
$CH_3SO_2CF_3$	431	1
CH_3SO_2Ph	414.2	1
$PhCH_2SO_2Me$	380.7	1
$PhCH_2SO_2CF_3$	372.4	1
$PhCH_2SO_2tBu$	376.6	1
Ph_2CHSO_2Ph	365.3	1
$CH_2(SPh)_2$	372.4	1
H–CH_2SiMe_3	418±6.3	1
H–$CH_2C(CH_3)_2SiMe_3$	409±5	1
H–CH_2SiMe_2Ph	410.1	5
H–$CH((CH_3)_3Si)_2$	397±13	1
H–$CH_2B(RO)_2$	412.5	1
H–$CH((CH_3)_2P)_2$	385±13	1
(2) C–C BDEs		
CH_3–CH_3	377.4±0.8	1
CH_3–C_2H_5	370.3±2.1	1
CH_3–C_3H_7	372.0±2.9	1
CH_3–*iso*-C_3H_7	369.0±3.8	1
CH_3–C_4H_9	371.5±2.9	1
CH_3–*iso*-C_4H_9	370.3±4.6	1
CH_3–*sec*-C_4H_9	368.2±2.9	1
CH_3–*tert*-C_4H_9	363.6±2.9	1
CH_3–C_5H_{11}	368.4±6.3	1
CH_3–$CH(C_2H_5)_2$	365.7±4.2	1
CH_3–$C(CH_3)_2(CH_2CH_3)$	360.9±6.3	1
CH_3–C_6H_{13}	368.2±6.3	1
C_2H_5–C_2H_5	363.2±2.5	1
C_3H_7–C_3H_7	366.1±3.3	1
iso-C_3H_7–*iso*-C_3H_7	353.5±4.6	1
C_4H_9–C_4H_9	364.0±3.8	1
iso-C_4H_9–*iso*-C_4H_9	362.3±6.3	1

Bond	D^o_{298}/kJ mol^{-1}	Ref.
***sec*-C_4H_9–*sec*-C_4H_9**	348.5±3.3	1
***tert*-C_4H_9–*tert*-C_4H_9**	322.6±4.2	1
CH_3–*cyclo*-C_5H_9	358.2±5.0	1
CH_3–*cyclo*-C_6H_{11}	377.0±7.5	1
***cyclo*-C_6H_{11}–*cyclo*-C_6H_{11}**	369.0±8.4	1
CH_3–$CH_2C{\equiv}CH$	320.5±5.0	1
CH_3–$CH_2C{\equiv}CCH_3$	308.4±6.3	1
CH_3–$CH(CH_3)C{\equiv}CH$	305.4±8.4	1
CH_3–$CH(CH_3)C{\equiv}CCH_3$	320.9±6.3	1
CH_3–$C(CH_3)_2C{\equiv}CH$	295.8±6.3	1
CH_3–$C(CH_3)_2C{\equiv}CCH_3$	303.3±6.3	1
CH_3–$CHCH_2$	426.3±6.3	1
CH_3–$CH{=}CCH_2$	359.8±5.9	1
CH_3–cyclopro-en-1-yl	340.6±20.9	1
CH_3–$CH_2CH{=}CH_2$	317.6±3.8	1
CH_3–$CH_2C(CH_3){=}CH_2$	310.0±4.2	1
CH_3–$CH(CH_3)CH{=}CH_2$	302.5±6.3	1
CH_3–$C(CH_3)_2CH{=}CH_2$	282.4±6.3	1
CH_3–*cyclo*-C_5H_7	299.2±8.4	1
CH_3–C_6H_5	426.8±4.2	1
HCC–C_6H_5	590.8±5.9	1
C_2H_3–C_6H_5	482.0±5.4	1
CH_3-$CH_2C_6H_5$	325.1±4.2	1
CH_3–$CH(CH_3)C_6H_5$	312.1±6.3	1
CH_3–$C(CH_3)_2C_6H_5$	303.3±8.4	1
CH_3–$CH_2CHCHPh$	295.4	1
CH_3–$CH(C_6H_5)_2$	315.9±6.3	1
CH_3–$C(CH_3)(C_6H_5)_2$	290.8±8.4	1
C_6H_5–C_6H_5	478.6±6.3	1
C_6H_5–$CH_2C_6H_5$	383.7±8.4	1
$C_6H_5CH_2$–$CH_2C_6H_5$	272.8±9.2	1
C_6H_5–$CH(C_6H_5)_2$	361.1±8.4	1
C_6H_5–$C(C_6H_5)_3$	324.3±12.6	1
Ph_2CH–$CHPh_2$	247.3±8.4	1
$PhCH_2$–CPh_3	234.7±14.6	1
R-R, R = phenalenyl	47.4±0.5	16
R-R, R = 9-phenylfluorenyl	63.6	20
CF_3–CF_3	413.0±5.0	1
CF_3–CHF_2	399.6±8.4	1
CF_3–$CClF_2$	373.6±12.5	1
CF_3–CH_2F	397.5±8.4	1
CF_3–CCl_3	332.2±5.4	1
CF_3–CHBrCl	377.0±10.5	1
CF_3–CH_2Br	399.6±8.4	1
CF_3–CH_2I	408.4±10.5	1
CF_3–CH_3	429.3±5.0	1
CHF_2–CHF_2	382.4±15.5	1
$CClF_2$–$CClF_2$	378.7±12.6	1
CF_2Cl–$CFCl_2$	358.6±12.6	1
CHF_2–CH_2F	394.1±16.7	1
CH_2F–CH_2F	368.2±8.4	1
CHF_2–CH_3	405.0±8.4	1
CH_2F–CH_3	389.9±8.4	1
$CHClF$–CH_3	399.6±12.6	1
CF_2Br–CHClF	369.4	1
CF_2Br–CH_3	396.6±15.1	1
CCl_3–CCl_3	285.8±6.3	1
CCl_3–$CClF_2$	282.0±12.6	1
CCl_3–$CHCl_2$	306.3±8.4	1
CCl_3–CH_2Cl	323.8±8.4	1
CCl_3–CH_3	362.3±6.3	1
$CHCl_2$–$CHCl_2$	342.3±8.4	1
$CHCl_2$–CH_2Cl	358.6±8.4	1
$CHCl_2$–CH_3	365.1±3.3	1
$CHBrCl$–CH_3	384.5	1
$CHClBr$–CHClBr	323.0±12.6	1
CH_2Cl–CH_2Cl	360.7±8.4	1
CH_2Cl–CH_3	375.7±9.2	1
Br_3C–CH_3	356.9±12.6	1
Br_3C–CBr_3	278.7±16.7	1
$CHBr_2$–CH_3	372.8	1
CH_2Br–CH_2Cl	378.2	1
CH_2Br–CH_2Br	379.9±8.4	1
CH_2I–CH_2I	387.0±10.5	1
CH_3–CH_2Br	381.6±8.4	1
CH_3–CH_2I	384.5±8.4	1
CF_3–CF_2CF_3	424.3±13.6	1
CF_3–$CF{=}CF_2$	420.5	1
CH_3–CH_2CH_2Cl	371.4±2.8	1
CH_3–$CHClCH_3$	367.5±2.0	1
CH_2Cl–$CHClCH_3$	356.5±8.4	1
CH_2Cl–CH_2CClH_2	369.0±8.4	1
CH_3–CCl_2CH_3	362.8±8.4	1
CH_2Br–$CHBrCH_3$	369.4±8.4	1
CH_2ClCH_2–$CHClCH_3$	364.4±8.4	1
CH_2ClCH_2–CH_2CClH_2	369.0±8.4	1
CH_3CHBr–$CHBrCH_3$	355.6±8.4	1
CF_3–C_6H_5	463.2±12.6	1
CCl_3–C_6H_5	388.7±8.4	1
CH_3–C_6F_5	439.3	1
CF_3–C_6F_5	435.1	1
CF_3–$CH_2C_6H_5$	365.7±12.6	1
C_6F_5–C_6F_5	488.3	1
CF_3–$CHPh_2$	352.3±16.7	1
CF_3–CPh_3	290.8±16.7	1
CF_2CF–$CFCF_2$	558.1±12.6	1
CH_2FCH_2–CPh_3	274.9±16.7	1
CHF_2CH_2–CPh_3	264.0±16.7	1
CH_3–CH_2OH	364.8±4.2	1
CF_3–CH_2OH	405.4±6.3	1
C_2H_5–CH_2OH	356.9±5.0	1
C_3H_7–CH_2OH	357.3±3.3	1
***iso*-C_3H_7–CH_2OH**	354.8±4.2	1
C_4H_9–CH_2OH	355.6±4.2	1
***sec*-C_4H_9–CH_2OH**	352.7±4.2	1
***iso*-C_4H_9–CH_2OH**	354.0±5.4	1
C_6H_5–CH_2OH	413.4±5.4	1
HOH_2C–CH_2OH	358.2±6.3	1
NH_2CH_2–CH_2OH	335.6±10.5	1
CH_3–CH_2OCH_3	363.2±5.0	1
CH_3OCH_2–CH_2OCH_3	338.9±10.5	1
CH_3–C(O)H	354.8±1.7	1
CCl_3–C(O)H	309.2±5.0	1
CH_3–C(O)F	417.6±6.3	1
CH_3–C(O)Cl	367.8±6.3	1
CCl_3–C(O)Cl	289.1±6.3	1
$CHCl_2$–C(O)Cl	312.5±8.4	1
$CClH_2$–C(O)Cl	340.2±8.4	1
C_6H_5–C(O)H	408.4±4.2	1
C_6H_5–C(O)Cl	417.6±6.3	1
CH_3–$C(O)CH_3$	351.9±2.1	1
C_2H_5–$C(O)CH_3$	347.3±2.9	1
C_3H_7–$C(O)CH_3$	348.5±2.9	1
***iso*-C_3H_7–$C(O)CH_3$**	340.2±3.8	1
C_4H_7–$C(O)CH_3$	346.9±5.4	1
***tert*-C_4H_9–$C(O)CH_3$**	329.3±4.2	1
C_6H_5–$C(O)CH_3$	406.7±4.6	1
$C_6H_5CH_2$–$C(O)CH_3$	299.7±8.4	1

Bond	D^o_{298}/kJ mol^{-1}	Ref.
HC(O)–C(O)H	295.8±6.3	1
ClC(O)–C(O)Cl	292.5±8.4	1
CH_3C(O)–C(O)H	302.5±8.4	1
CH_3C(O)–C(O)CH_3	307.1±4.2	1
C_6H_5C(O)–C(O)C_6H_5	288.3±16.7	1
CH_3–C(O)OH	384.9±8.4	1
CF_3–C(O)OH	370.7±8.4	1
CCl_3–C(O)OH	310.5±12.6	1
$CClH_2$–C(O)OH	357.7±8.4	1
CH_2Br–C(O)OH	358.2±8.4	1
NH_2CH_2–C(O)OH	349.4±8.4	1
CH_3NHCH_2–C(O)OH	300.4±8.4	1
C_6H_5–C(O)OH	429.7±8.4	1
C_6F_5–C(O)OH	470.0±10.5	1
$HOCH_2$–C(O)OH	371.5±5.4	1
HOC(O)–C(O)OH	334.7±6.3	1
CH_3NHCH_2–C(O)OH	301.2±16.7	1
$CH_3CH(NH_2)$–C(O)OH	331.4±16.7	1
NH_2CH_2–CH_2C(O)OH	325.5±16.7	1
CN–**CN**	571.9±6.7	1
HC(O)–**CN**	455.2±8.4	1
HC(S)–**CN**	530.1±8.4	1
CF_3–**CN**	469.0±4.2	1
CH_3–**CN**	521.7±9.2	1
NCC–**CN**	462.3	1
C_2H_5–**CN**	506.7±7.5	1
CH_3–CH_2CN	348.1±12.6	1
C_6H_5–CH_2CN	386.6±8.4	1
CH_3–CH(CH_3)CN	332.6±8.4	1
CH_3–C(CH_3)$_2$CN	340.6±16.7	1
CH_3–C(CH_3)(CN)C_6H_5	250.6	1
$(Ph)_2$(CN)C–C(CN)$(Ph)_2$	109.6	20
$(NO_2)_3$C–C$(NO_2)_3$	308.8	1
C_{58}–C_2	1082.5±22.2	24
(3) C–halogen BDEs		
F–CN	482.8	1
F–CF_3	546.8±2.1	1
F–CHF_2	533.9±5.9	1
F–CH_2F	496.2±8.8	1
F–CF_2Cl	511.7	1
F–$CFCl_2$	482.0±10.5	1
F–CHFCl	462.3±10.0	1
F–CCl_3	439.3±4	1
F–CH_2Cl	465.3±9.6	1
F–CH_3	460.2±8.4	1
F–C≡CH	521.3	1
F–C≡CF	519±21	1
F–CF=CF_2	546.4±12.6	1
F–CF_2CF_3	532.2±6.3	1
F–CH_2CF_3	457.7	1
F–CF_2CH_3	522.2±8.4	1
F–C_2H_3	517.6±12.6	1
F–C_2H_5	473.2±8.4	1
F–C_3H_7	474.9±8.4	1
F–*iso*-C_3H_7	482.8±8.4	1
F–*tert*-C_4H_9	489.5±8.4	1
F–C_6H_5	525.5±8.4	1
F–C_6F_5	485±25	18
F–$CH_2C_6H_5$	412.8±4.2	15
F–COH	497.9±10.5	1
F–COF	542.2±12.6	1
F–COCl	484.5	1
F–C(O)CH_3	511.7±12.6	1

Bond	D^o_{298}/kJ mol^{-1}	Ref.
Cl–CN	422.6±8.4	1
Cl–CF_3	365.3±3.8	1
Cl–CHF_2	364±8	1
Cl–CH_2F	354.4±11.7	1
Cl–CF_2Cl	333.9±10.5	1
Cl–$CFCl_2$	320.9±8.4	1
Cl–CHFCl	346.0±13.4	1
Cl–CCl_3	296.6	1
Cl–$CHCl_2$	320.5±6.3	1
Cl–CH_2Cl	338.1	1
Cl–$CBrCl_2$	287±10.5	1
Cl–CH_2Br	313.4	1
Cl–CH_3	350.2±1.7	1
Cl–C≡CCl	443±50	1
Cl–C≡CH	435.6±8.4	1
Cl–CH_2CN	267.4	1
Cl–CCl=CCl_2	383.7	1
Cl–CH=CH_2	396.5±4.8	1
Cl–CF=CF_2	434.7±8.4	1
Cl–CF_2CF_3	346.0±7.1	1
Cl–CF_2CF_2Cl	331.4±20.9	1
Cl–CCl_2CF_3	307.9	1
Cl–CCl_2CCl_3	303.8	1
Cl–$CHClCCl_3$	330.5±4.2	1
Cl–CCl_2CHCl_2	311.7	1
Cl–$CHClCH_3$	327.9±1.8	1
Cl–CH_2CH_2Cl	345.1±5.0	1
Cl–$CHBrCH_3$	331.8±8.4	1
Cl–CH_2CH_3	352.3±3.3	1
Cl–CH_2CH=CH_2	298.3±5.0	1
Cl–C_3H_7	352.7±4.2	1
Cl–$CH_2CH_2CH_2Cl$	348.9	1
Cl–*iso*-C_3H_7	354.0±6.3	1
Cl–CH_2CHCH=CH_2	342.7	1
Cl–C_4H_9	350.6±6.3	1
Cl–*sec*-C_4H_9	83.7±1.5	1
Cl–*tert*-C_4H_9	351.9±6.3	1
CH_2CHCH**Cl**(CH_3)	300.0±6.3	1
Cl–C_5H_{11}	350.6±6.3	1
Cl–C(CH_3)$_2$(C_2H_5)	352.7±6.3	1
Cl–*cyclo*-C_6H_{11}	360.2±6.5	1
Cl–C_6H_5	399.6±6.3	1
Cl–C_6F_5	383.3±8.4	1
Cl–$CH_2C_6H_5$	299.9±4.3	15
Cl–C(O)Cl	318.8±8.4	1
Cl–COF	376.6	1
Cl–C(O)CH_3	354.0±8.4	1
Cl–C(O)CH_2CH_3	352.7±6.3	1
Cl–C(O)C_6H_5	341.0±8.4	1
Cl–CH_2C(O)C_6H_5	309	1
Cl–CH_2C(O)OH	310.9±2.2	1
Cl–C(O)OC_6H_5	364	1
Cl–C$(NO_2)_3$	302.1	1
Br–CN	364.8±4.2	1
Br–CF_3	296.2±1.3	1
Br–CHF_2	288.7±8.4	1
Br–CF_2Cl	269.9±6.3	1
Br–CCl_3	231.4±4.2	1
Br–CH_2Cl	285	1
Br–CBr_3	228.9±9.6	1
Br–$CHBr_2$	274.9±13.0	1
Br–CH_2Br	290.0±10.0	1
Br–C≡CH	410.5	1

Bond	D^o_{298}/kJ mol^{-1}	Ref.
Br–$CH{=}CH_2$	332.2±6.3	1
Br–CF_2CF_3	283.3±6.3	1
Br–$CClBrCF_3$	251.0±6.3	1
Br–CF_2CF_2Br	282.8±6.7	1
Br–$CHClCF_3$	274.9±6.3	1
Br–CF_2CH_3	287.0±5.4	1
Br–CH_2CH_2Cl	292.5±8.4	1
Br–$CHClCH_3$	272.0±8.4	1
Br–C_2H_5	292.9±4.2	1
Br–$CH_2CH{=}CH_2$	237.2±5.0	1
Br–C_3H_7	298.3±4.2	1
Br–*iso*-C_3H_7	299.2±6.3	1
Br–$CH_2CH_2CH_2Br$	324.7	1
Br–$CF_2CF_2CF_3$	278.2±10.5	1
CF_3CF**Br**CF_3	274.2±4.6	1
Br–C_4H_9	296.6±4.2	1
Br–*sec*-C_4H_9	300.0±4.2	1
Br–*tert*-C_4H_9	292.9±6.3	1
Br–C_6H_5	336.4±6.3	1
Br–C_6F_5	~328	1
Br-$CH_2C_6H_5$	239.3±6.3	15
Br–$CH_2C_6F_5$	225.1±6.3	1
Br-1-$C_{10}H_7$	339.7	1
Br–2–$C_{10}H_7$	341.8	1
Br–anthracenyl	322.6	1
Br–$C(O)CH_3$	292.0±8.4	1
Br–$C(O)C_6H_5$	276.6±8.4	1
Br–$CH_2C(O)CH_3$	257.9±10.5	1
Br–$CH_2C(O)C_6H_5$	271	1
Br–$CH_2C(O)OH$	257.4±3.7	1
Br–$C(NO_2)_3$	218.4	1
I–CN	320.1	1
I–CF_3	227.2±1.3	1
I–CH_2Cl	204.2±0.8	1
I–CH_2I	217.1±8.4	1
I–CH_3	238.9±2.1	1
I–CH_2CN	187.0±6.3	1
I–CF_2CF_3	219.2±2.1	1
I–CF_2CF_2I	217.6±6.7	1
I–CH_2CF_3	235.6±4.2	1
I–$CHFCClF_2$	202±2	1
I–CF_2CH_3	217.6±4.2	1
I-CFICH3	218.0±4.2	1
CF_3CF**I**CF_3	215.1	1
I–$CH{=}CH_2$	259.0±4.2	1
I–C_2H_5	233.5±6.3	1
I–$CH_2CH{=}CH_2$	185.8±6.3	1
I–C_3H_7	236.8±4.2	1
I–*iso*-C_3H_7	234.7±6.3	1
I–C_4F_9	205.8	1
I–*tert*-C_4H_9	227.2±6.3	1
I–C_6H_5	272.0±4.2	1
I–C_6F_5	<301.7	1
I–$CH_2C_6H_5$	187.8±4.8	15
I–1-naphthyl	274.5±10.5	1
I–2-naphthyl	272.0±10.5	1
I–CH_2CN	187.0±8.4	1
I–CH_2OCH_3	229.4±8.4	1
I–CH_2SCH_3	216.8±6.3	1
I–$C(O)CH_3$	223.0±8.4	1
I–$C(O)C_6H_5$	212.1±8.4	1
I–$CH_2C(O)OH$	197.5±2.7	1
I–$C(NO_2)_3$	144.8	1

Bond	D^o_{298}/kJ mol^{-1}	Ref.
(4) O–X BDEs		
HO–**H**	497.1±0.4	25
FO–**H**	425.1	1
ClO–**H**	393.7	1
BrO–**H**	405	1
IO–**H**	403.3	1
CH_3O–**H**	440.0±2.2	25
CF_3O–**H**	497.1	1
HC≡CO–**H**	443.1	1
C_2H_5O–**H**	439.2±4.1	25
$CH_2{=}CHO$–**H**	355.6	1
CF_3CH_2O–**H**	447.7±10.5	13
C_3H_7O–**H**	≤433±2	17
iso-C_3H_7O–**H**	442.3±2.8	1
C_4H_9O–**H**	426.3±4.2	1
sec-C_4H_9O–**H**	441.4±4.2	1
tert-C_4H_9O–**H**	444.9±2.8	1
tert-BuCH_2O–**H**	428.0±4.2	1
$C_6H_5CH_2O$–**H**	425.5	1
$CH_3C(OH)O$–**H**	446.9±6.3	3
$(CH_3)_2C(OH)O$–**H**	450.6±6.3	3
$HC(O)O$–**H**	468.6±12.6	6
$CH_3C(O)O$–**H**	468.6±12.6	6
$C_2H_5C(O)O$–**H**	472.8	1
iso-$C_3H_7C(O)O$–**H**	472.8	1
HOO–**H**	367.4±2.1	1
CH_3OO–**H**	370.3±2.1	1
CF_3OO–**H**	383	1
CH_2FOO–**H**	379	1
CCl_3OO–**H**	386	1
$CHCl_2OO$–**H**	383	1
CH_2ClOO–**H**	379	1
CBr_3OO–**H**	383	1
CH_2BrOO–**H**	379	1
C_2H_5OO–**H**	354.8±9.2	1
$CH_3CHClOO$–**H**	377	1
CH_3CCl_2OO–**H**	383	1
$CF_3CHClOO$–**H**	384	1
C_2Cl_5OO–**H**	383	1
iso-C_3H_7OO–**H**	356	1
$CH_2{=}CHCH_2OO$–**H**	372.4	1
tert-C_4H_9OO–**H**	369	1
$C_6H_5CH_2OO$–**H**	363	1
$(C_6H_5)_2CHOO$–**H**	370	1
$CH_3C(O)OO$–**H**	386	1
$CCl_2(CN)OO$–**H**	384	1
$OHCH_2OO$–**H**	368	1
H–ONO	327.6±2.1	1
H–OONO	299.2	2
H–ONO_2	423.4	1
H–ONNOH	189	23
H–OSiMe3	495	1
$(CH_3)CHNO$-**H**	410.9	1
$(CH_3)_2CNO$-**H**	400.8	1
$(C_6H_5)CHNO$-**H**	368.6	1
PhO–**H**	371.1±2.1	8
α-Tocopherol RO-**H**	323.4	1
β-Tocopherol RO-**H**	335.6	1
γ-Tocopherol RO-**H**	335.1	1
δ-Tocopherol RO-**H**	342.8	1
O–O_2	106.6	1
HO–OH	210.66±0.42	1
HO–OF	199.7±8.4	1

Bond	D^o_{298}/kJ mol^{-1}	Ref.
HO–OBr	138.5±8.4	1
FO–OF	199.6	1
ClO–OCl	75.7±3	1
IO–OI	74.9±17	10
HO–ONO	≤70.3	11
HO–ONO_2	163.2±8.4	1
HO–OCH_3	189.1±4.2	1
HO–OCF_3	201.3±20.9	1
HO–OC_2H_5	178.7±6.3	1
HO–Oi-C_3H_7	185.8±6.3	1
HO–OtC_4H_9	186.2±4.2	1
HO–$OC(O)CH_3$	169.9±2.1	1
HO–$OC(O)C_2H_5$	169.9±2.1	1
CH_3O–OCH_3	167.4±6.3	1
CF_3O–OCF_3	198.7±2.1	1
C_2H_5O–OC_2H_5	166.1	1
C_3H_7O–OC_3H_7	155.2±4.2	1
***iso*-C_3H_7O**–O-*iso*-C_3H_7	157.7	1
***sec*-C_4H_9O**–O-*sec*-C_4H_9	152.3±4.2	1
***tert*-BuO**–O-*tert*-Bu	162.8±2.1	1
***tert*-$BuCH_2O$**–OCH_2-*tert*-Bu	152.3	1
$EtC(Me)_2O$–$OC(Me)_2Et$	164.4±4.2	1
$(CF_3)_3CO$–$OC(CF_3)_3$	148.5±4.6	1
Ph_3CO–$OCPh_3$	131.4	19
SF_5O–OSF_5	155.6	1
SF_5O–$OOSF_5$	126.8	1
$(CH_3)_3CO$–$OSi(CH_3)_3$	196.6	1
***tert*-BuO**–$OGeEt_3$	192.5	1
***tert*-BuO**–$OSnEt_3$	192.5	1
CF_3OO–OCF_3	126.8±8.4	1
HC(O)O–**OH**	199.2±8.4	7
FC(O)O–OC(O)F	96.2	9
$CH_3C(O)O$–ONO_2	131.4±8.4	10
$CH_3C(O)O$–$OC(O)CH_3$	140.2±21	1
$CF_3C(O)O$–$OC(O)CF_3$	125.5	1
$CF_3OC(O)O$–$OC(O)OCF_3$	119.2	9
$C_2H_5C(O)O$–$OC(O)C_2H_5$	150.6	1
$C_3H_7C(O)O$–$OC(O)C_3H_7$	150.6	1
HO–CF_3	≤482.0±1.3	1
FO–CF_3	408±17	1
HO–CH_3	384.93±0.71	1
HO–C_2H_5	391.2±2.9	1
HO–CH_2CF_3	408.4±8.4	1
HO–$CH_2CH{=}CH_2$	332.6±4.2	1
HO–C_3H_7	392.0±2.9	1
HO–*iso*-C_3H_7	397.9±4.2	1
HO–C_4H_9	389.9±4.2	1
HO–*sec*-C_4H_9	396.1±4.2	1
HO–*iso*-C_4H_9	394.1±4.2	1
HO–*tert*-C_4H_9	398.3±4.2	1
HO–$CH(CH_3)(nC_3H_7)$	398.3±4.2	1
HO–$CH(C_2H_5)_2$	399.2±4.2	1
HO–$C(CH_3)_2(C_2H_5)$	395.8±6.3	1
HO–C_6H_5	463.6±4.2	1
HO–C_6F_5	446.9±9.2	1
HO–$CH_2C_6H_5$	345.6±6.3	1
HO–$C(CH_3)_2C_6H_5$	339.3±6.3	1
cyclo-C_5H_9–**OH**	385.8±6.3	1
1-$C_{10}H_7$–**OH**	468.6±6.3	1
2-$C_{10}H_7$–**OH**	467.8±6.3	1
$(CH_3)_2(NH_2)C$–**OH**	310.4±6.3	1
CH_3–OCH_3	351.9±4.2	1
ICH_2–OCH_3	373.2±12.6	1
CH_3O–**C_2H_5**	355.2±5.4	1
CH_3O–**$CHClCH_3$**	370.3±8.4	1
CH_3O–**C_3H_7**	358.6±6.3	1
CH_3O–***iso*-C_3H_7**	360.7±4.2	1
CH_3O-**C_4H_9**	346.0±6.3	1
CH_3O-***tert*-C_4H_9**	353.1±6.3	1
C_6H_5–OCH_3	418.8±5.9	1
$C_6H_5CH(CH_3)$–OCH_3	306.7±8.4	1
C_6H_5–OC_6H_5	332.2±8.4	1
CH_3–OC(O)H	383.7±12.6	1
HC(O)–OH	457.7±2.1	1
$CH_3C(O)$–OH	459.4±4.2	1
$C_6H_5C(O)$–OH	447.7±10.5	1
HO–$CH_2C(O)OH$	368.2±10.5	1
CH_3-$OC(O)CH_3$	380.3±12.6	1
HC(O)–OCH_3	423.8±4.2	1
$CH_3C(O)$–OCH_3	424.3±6.3	1
$C_6H_5C(O)$–OCH_3	421.3±12.6	1
$C_6H_5C(O)$–OC_6H_5	313.0±12.6	1
CH_3OCH_2–OCH_3	367.5±8.4	1
$CH_3C(O)$–$OC(O)CH_3$	382.4±12.6	1
$C_6H_5C(O)$–$OC(O)C_6H_5$	384.9±16.7	1
CH_3–OOH	300.4±12.6	1
C_2H_5–OOH	332.2±20.9	1
C_3H_7–OOH	364.4	1
***iso*-C_3H_7**–OOH	298.3	1
***tert*-C_4H_9**–OOH	309.2±4.2	1
CH_3–$OOCH_3$	292.5±8.4	1
CF_3–$OOCF_3$	361.5±8.4	1
CH_3–**OO**	137.0±3.8	1
CF_3–**OO**	147.7	1
$CClF_2$–**OO**	127.6	1
CCl_2F-**OO**	124.7	1
CH_2Cl–**OO**	122.4±10.5	1
$CHCl_2$–**OO**	108.2±8.2	1
CCl_3–**OO**	92.0±6.4	1
HC(O)–**OOH**	290	7
$CH_3C(O)$–$OOC(O)CH_3$	315.1	1
ClO–CF_3	≤369.9±1.3	1
CH_3–**ONO**	245.2	1
C_2H_5–**ONO**	260.2	1
C_3H_7–**ONO**	249.4±6.3	1
iso-C_3H_7–**ONO**	254.4±6.3	1
C_4H_9–**ONO**	256.5±6.3	1
iso-C_4H_9–**ONO**	254.0±6.3	1
sec-C_4H_9–**ONO**	253.6±6.3	1
tert-C_4H_9–**ONO**	252.7±6.3	1
$(C_2H_5)(CH_3)_2C$–**ONO**	254.0±8.4	1
CH_3–**ONO_2**	340.2	1
C_2H_5–**ONO_2**	344.8	1
CH_3O–CH_2CN	393.3	1
O–**N_2**	167.4±0.4	1
O–**NO**	305	1
O–**NO_2**	211.3	1
NO–**NO**	40.6±2.1	1
O_2N–**ONO_2**	102.9	1
HO–**NO**	206.7	1
FO–**NO**	132.5±17	10
cis-ClO–**NO**	127.6±8.4	10
trans-ClO–**NO**	116.6±8.4	10
cis-BrO–**NO**	138.1±8.4	10
trans-BrO–**NO**	121.6±8.4	10
HOO–**NO**	114.2±4	2
CH_3O–**NO**	176.6±3.3	1
C_2H_5O–**NO**	185.4±4.2	1

Bond	D^o_{298}/kJ mol^{-1}	Ref.
C_3H_7O–**NO**	179.1±6.3	1
iso-C_3H_7O–**NO**	175.3±4.2	1
C_4H_9O–**NO**	177.8±6.5	1
iso-C_4H_9O–**NO**	175.7±6.5	1
sec-C_4H_9O–**NO**	173.6±3.3	1
tert-C_4H_9O–**NO**	176.1±5.9	1
tert-AmO–**NO**	171.1±0.4	1
C_6H_5O–**NO**	87	1
HO–**NO$_2$**	204.2	1
FO–**NO$_2$**	131.8±12.6	10
ClO–**NO$_2$**	111.8±2.1	1
BrO–**NO$_2$**	110.5±8.4	1
CH_3O–**NO$_2$**	176.1±4.2	1
C_2H_5O–**NO$_2$**	174.5±4.2	1
C_3H_7O–**NO$_2$**	177.0±4.2	1
iso-C_3H_7O–**NO$_2$**	175.7±4.2	1
HOO–**NO$_2$**	100.0±2.9	1
CH_3OO–**NO$_2$**	86.6±8.4	1
CF_3OO–**NO$_2$**	105	1
CF_2ClOO–**NO$_2$**	106.7	1
$CFCl_2OO$–**NO$_2$**	106.7	1
CCl_3OO–**NO$_2$**	95.8	1
O–SOF_2	456±113	1
O–SOCl	435±29	1
HO–SH	293.3±16.7	1
HO–SOH	313.4±12.6	1
HO–$S(OH)O_2$	384.9±8.4	1
HO–SCH_3	303.8±12.6	1
HO–SO_2CH_3	360.2±12.6	1
F–OH	215.1	1
F–OF	164.1	10
F–OCF_3	200.8±4.2	1
F–OCH_3	>196.6	1
F–ONO_2	140.6	1
Cl–OH	233.5	10
Cl–OCl	142	10
Cl–OCF_3	≤220.9±8.4	1
Cl–OCH_3	200.8	1
Cl–O-*tert*-C_4H_9	198.3	1
Cl–OOCl	91.2	1
Cl–ONO_2	169.5	1
Br–OH	209.6±4.2	10
Br–OBr	125	10
Br–O-*tert*-C_4H_9	212	1
Br–ONO_2	140.6	1
I–OH	213.4	1
I–OI	130.1	10
(5) N–X BDEs		
H–NH_2	450.1±1.1	25
H–NF_2	316.7±10.5	1
H–NNH	254.4	1
H–N_3	≤389	1
H–$N=CH_2$	364±25	1
H–NCO	450.6	1
H–NCS	≤396.6±4.6	1
CH_3N**H$_2$**	425.1±8.4	1
tert-BuN**H$_2$**	397.5±8.4	1
$C_6H_5CH_2N$**H$_2$**	418.4	1
$(CH_3)_2N$**H**	395.8±8.4	1
H–$NHNH(CH_3)$	276±21	1
H–$NHN(CH_3)_2$	356±21	1
N**H$_2$**CN	414.2	1
$(N$**H$_2$**$)_2$C=O	464.4	1
$(N$**H$_2$**$)_2$C=S	389.1	1
CH_3CSN**H$_2$**	380.7	1
PhCSN**H$_2$**	380.7	1
$(PhN$**H**$)_2$C=S	364	1
$(N$**H$_2$**$)_2$C=NH	435.1	1
$Ph_2C=N$**H**	489.5	1
H–$N(SiMe_3)_2$	464	1
H–NCO	462.3±15.9	1
H–NHPh	375.3	1
C_6H_5N**H**OH	292	1
C_6H_5N**H**(CONMe2)	387.9	1
H–NPh_2	364.8	1
HN–N_2	63	1
ON–N	480.7±0.4	1
ON–NO	8.49±0.12	12
ON–NO_2	36.8	1
O$_2$N–NO_2	55.2	1
H$_2$N–NH_2	277	1
F$_2$N–NF_2	92.9±12.6	1
H$_2$N–$NHCH_3$	275.8±8.4	1
H$_2$N–$N(CH_3)_2$	259.8±8.4	1
H$_2$N–NHC_6H_5	227.6±8.4	1
H$_2$N–NO_2	230	1
$H_2NN(CH_3)$–**NO**	179.6	1
N$_3$–CH_3	335.1±20.5	1
N$_3$–C_6H_5	375.7±20.9	1
N$_3$–$CH_2C_6H_5$	211.3±14.2	1
CH_3–**NC**	413.0±3.3	21
C_2H_5–**NC**	413.4±8.4	21
iso-C_3H_7–**NC**	423.0±8.4	21
tert-C_4H_9–**NC**	399.6±5.4	21
NC–**NO**	120.5±10.5	1
CH_3–**NO**	172	1
CF_3–**NO**	167	1
CCl_3–**NO**	125	1
C_2H_5–**NO**	171.5	1
CH_2CHCH_2–**NO**	110	1
iso-C_3H_7–**NO**	152.7±12.6	1
tert-C_4H_9–**NO**	167	1
C_6H_5–**NO**	226.8±2.1	1
C_6F_5–**NO**	211.3±4.2	1
$C_6H_5CH_2$–**NO**	123	1
CH_3–**NO$_2$**	260.7±2.1	1
C_2H_5–**NO$_2$**	254.4	1
C_3H_7–**NO$_2$**	256.5	1
iso-C_3H_7–**NO$_2$**	259.8	1
C_4H_9–**NO$_2$**	254.8	1
sec-C_4H_9–**NO$_2$**	263.2	1
tert-C_4H_9–**NO$_2$**	258.6	1
C_6H_5–**NO$_2$**	295.8±4.2	1
$C_6H_5CH_2$–**NO$_2$**	210.3±6.3	1
$(NO_2)CH_2$–**NO$_2$**	207.1	1
CF_3–**NF$_2$**	280.7	1
$C_6H_5CH_2$–**NF$_2$**	237.2±14.6	1
CH_3–**NH$_2$**	356.1±2.1	1
C_2H_5–**NH$_2$**	352.3±6.3	1
C_3H_7–**NH$_2$**	356.1±2.9	1
iso-C_3H_7–**NH$_2$**	357.7±3.8	1
C_4H_9–**NH$_2$**	356.1±2.9	1
sec-C_4H_9–**NH$_2$**	359.0±2.9	1
iso-C_4H_9–**NH$_2$**	254.8±5.0	1
tert-C_4H_9–**NH$_2$**	355.6±6.3	1
pyridin-2-yl–**NH$_2$**	431	1
C_6H_5–**NH$_2$**	429.3±4.2	1

Bond	D^o_{298}/kJ mol^{-1}	Ref.
$C_6H_5CH_2$–**NH_2**	306.7±6.3	1
$C_6H_5CH(CH)_3$–**NH_2**	300.8±8.4	1
HC(O)–**NH_2**	421.7±8.4	1
$CH_3C(O)$–**NH_2**	414.6±8.4	1
HS–**NO**	138.9	1
CH_3S–**NO**	104.6±4.2	1
tert-BuS–**NO**	115.1	1
$PhCH_2S$–**NO**	120.5	1
C_6H_5S-**NO**	81.2±5.4	1
SCN–SCN	255.6	1
FSO_2–NF_2	163	1
F–NO	235.26	10
F–NO_2	221.3	10
F–NF_2	254	1
F–NH_2	286.6	1
Cl–NO	158.8±0.8	10
Cl–NO_2	141.8±1.3	10
Cl–NF_2	~133.9	1
Cl–NH_2	253.1	1
Br–NO	120.1±0.8	10
Br–NO_2	82.0±7.1	1
Br–NF_2	<227.2	1
I–NO	75.6±4	10
I–NO_2	79.6±4	10
(6) S–X BDEs		
H–SOH	330.5±14.6	1
H–SH	381.18±0.05	1
H–SCH_3	365.7±2.1	1
H–$SCHCH_2$	351.5±8.4	1
H–SC_2H_5	365.3	1
H–SC_3H_7	365.7	1
H–S-*iso*-C_3H_7	369.9±8.4	1
H–S-*tert*-C_4H_9	362.3±9.2	13
H–$SCOCH_3$	370.7	1
H–SCOPh	364	1
H–SO_2CH_3	≤397	1
H–$SSCH_3$	330.5±14.6	1
H–SPh	349.4±4.5	1
H–SSH	318.0±14.6	1
H–SSSH	292.9±6.5	1
HS–SH	270.7±8.4	1
FS–SF	362.3	1
ClS–SCl	329.7	1
HS–SCH_3	272	1
HS–SPh	255.2±6.3	1
CH_3S–SCH_3	272.8±3.8	1
C_2H_5S–SC_2H_5	276.6	1
MeS–SPh	272.0±6.3	1
C_6H_5S–SC_6H_5	214.2±12.6	1
F_5S–SF_5	305±21	1
HS–CH_3	312.5±4.2	1
HS–C_2H_5	307.9±2.1	1
HS–C_3H_7	310.5±2.9	1
HS–*iso*-C_3H_7	307.1±3.8	1
HS–C_4H_9	309.2±2.9	1
HS–*sec*-C_4H_9	307.5±2.9	1
HS–*iso*-C_4H_9	310.0±4.6	1
HS–*tert*-C_4H_9	301.2±3.8	1
HS–C_6H_5	360.7±6.3	1
HS–$CH_2C_6H_5$	258.2±6.3	1
HS–C(O)H	309.6±8.4	1
HS–$C(O)CH_3$	307.9±6.3	1
CH_3S–CH_3	307.9±3.3	1
HOS–**CH_3**	284.9±12.6	1
CH_3SO–**CH_3**	221.8±8.4	1
$HOSO_2$–**CH_3**	324.3±12.6	1
CH_3SO_2–**CH_3**	279.5	1
F_5S–CF_3	392±43	1
F–SF_5	391.6	1
F–SO_2(F)	379	1
Cl–SF_5	<272	1
Cl–SO_2CH_3	293	1
Cl-SO_2Ph	297	1
Br–SF_5	<230	1
(7) Si–X BDEs and Others		
SiH_3–**H**	383.7±2.1	1
Me_3Si–**H**	396±7	1
H_5Si_2–**H**	373±8	1
$(C_2H_5)_3Si$–**H**	396±4	1
$C_6H_5SiH_2$–**H**	382±5	1
$(CH_3S)_3Si$–**H**	364	1
$(iPrS)_3Si$–**H**	376.6	1
$PhMe_2Si$–**H**	377±7	1
Ph_2SiH–**H**	379±7	1
Ph_2MeSi–**H**	361±10	1
SiF_3–**H**	432±5	1
$SiCl_3$–**H**	395±5	1
$SiBr_3$–**H**	334±8	1
SiH_3–**SiH_3**	321±4	1
SiH_3–Si_2H_5	313±8	1
Ph_3Si–$SiPh_3$	368.2	1
F_3Si–SiF_3	453.1±25	1
SiH_3–**CH_3**	375±5	1
SiF_3–**CH_3**	355.6	1
H_3Si–**NO**	158.2±5.7	1
H_3Si–**PH_2**	331.4	1
SiH_3–**F**	638±5	1
SiH_3–**Cl**	458±7	1
SiH_3–**Br**	376±9	1
SiH_3–**I**	299±8	1
GeH_3–**H**	348.9±8.4	1
Me_3Ge–**H**	364	1
Ph_3Ge–**H**	359.8	1
Me_3Sn–**H**	326.4	1
Ph_3Sn–**H**	294.6	1
Ph_3Sn–**H**	294.6	1
H_2P-**H**	351.0±2.1	1
CH_3PH-**H**	322.2±12.6	1
H_2P-PH_2	256.1	1
H-SeH	334.93±0.75	1
H-SeC_6H_5	326.4±16.7	1
H-TeH	277.0±5.0	1

References

1. Luo, Y.R., Handbook of Bond Dissociation Energies in Organic Compounds, CRC Press, 2002.
2. Hippler, H., Nasterlack, S., et al., *Phys. Chem. Chem. Phys.*, 4, 2959-2964, 2002.
3. Merenyi, G., Lind, J., et al., *J. Phys. Chem. A*, 106, 11127-11129, 2002.
4. Nimlos, M.R., Davico, G., et al., *J. Chem. Phys.,* 117, 4323-4339, 2002.
5. Tumanov, V.E., Kromkin, E.A., et al., *Russ. Chem. Bull.* 51, 1641-1650, 2002.
6. Blanksby, S.J. and Ellison, G.B., *Acc. Chem. Res.*, 36, 255-263, 2003.
7. Feller, D. and Dixon, A.A., *J. Phys. Chem. A,* 107, 9641-9651, 2003.
8. Guedes, R.C., Coutinho, K., et al., *J. Phys. Chem. A*, 107:9197-9207, 2003.
9. Maximiliano, A., Burgos, P., et al., *Int. J. Chem. Kinet.*, 35, 15-19, 2003.
10. US NASA, http://jpldataeval.jpl.nasa.gov, Feb 24, 2003.

11. Pollack, I.B., Konen, I.M., et al., *J. Chem. Phys.,* 119, 9981-9984, 2003.
12. Potter, A.B., Dribinski, V. *J. Chem. Phys.,* 119, 7197-7205, 2003.
13. Reed, D.R., Hare, M.C., et al., *J. Am. Chem. Soc.*, 125, 4643-4651, 2003.
14. Seetula, J.A., *Phys. Chem. Chem. Phys.*, 5, 849-855, 2003.
15. Verevkin, S.P., Krasnykh, E.L., et al., *Phys. Chem. Chem. Phys.*, 5, 2605-2611, 2003.
16. Zheng, S., Saeed, J.L., et al., *J. Am. Chem. Soc.,* 125, 5786-5791, 2003.
17. Zhou, W., Yuan, Y., et al., *J. Chem. Phys.*, 119, 7179-7187, 2003.
18. Caraiman, D., Koyanagi, G.K., *J. Phys. Chem.* A, 108, 978-986, 2004.
19. Donkeers, R.L. and Workentin, M.S., et al., *J. Am. Chem. Soc.*, 126, 1688-1698. 2004
20. Frenette, M., Aliaga, C., et al., *Org. Lett.*, 6, 2579-2582, 2004.
21. Koizumi, H. and Baer, T., J. *Phys. Chem A,* 108, 5956-5961, 2004.
22. Muralha, V.S.F., dos Santos, R.M.B., et al., *J. Phys. Chem. A*, 108, 936-942, 2004
23. Poskrebyshev, G.A, Shafirovich, V., et al., *J. Am. Chem. Soc.,* 126, 891-899, 2004
24. Gluch, K., Leubner, S.M. et al., *J. Chem. Phys.,* 121, 2137-2143, 2004.
25. Derived value based on the IUPAC database; see ref. 14 in the following Table 4.

TABLE 4. Enthalpies of Formation of Free Radicals and Other Transient Species

Radical	$\Delta_f H^o_{298}$/kJ mol-1	Ref.
(1) Carbon-Centered Species		
CH	595.8±0.6	14
CH_2 (triplet)	391.2±1.6	14
CH_2 (singlet)	428.8±1.6	14
$^{\bullet}CH_3$, methyl	146.7±0.3	14
$^{\bullet}C_2H$, acetenyl, $CH{\equiv}C^{\bullet}$	567.4±2.1	1
$^{\bullet}C_2H_2$, $CH_2{=}C^{\bullet\bullet}$	419.7±16.7	1
$^{\bullet}C_2H_3$, vinyl, $CH_2{=}C^{\bullet}H$	299.6±3.3	1
$^{\bullet}C_2H_5$, ethyl, $CH_3C^{\bullet}H_2$	118.8±1.3	1
$^{\bullet}C_3H_3$, propargyl, $CH{\equiv}CC^{\bullet}H_2$	339.0±4.2	1
$^{\bullet}C_3H_3$, $CH_3C{\equiv}C^{\bullet}$	515±13	1
$^{\bullet}C_3H_3$, $CH_2{=}C{=}CH^{\bullet} \leftrightarrow CH{\equiv}CC^{\bullet}H_2$	339.0±4.2	1
$^{\bullet}C_3H_3$, cyclopro-2-en-1-yl	439.7±17.2	1
$^{\bullet}C_3H_5$, allyl, $CH_2{=}CHC^{\bullet}H_2$	171.0±3.0	1
$^{\bullet}C_3H_5$, $CH_3CH{=}C^{\bullet}H$	267±6	1
$^{\bullet}C_3H_5$, $CH_3C^{\bullet}{=}CH_2$	231.4	1
$^{\bullet}C_3H_5$, cyclopropyl	279.9±10.5	1
$^{\bullet}C_3H_7$, *n*-propyl, $CH_3CH_2C^{\bullet}H_2$	100±2	1
iso-$C_3H_7^{\bullet}$, *iso*-propyl, $CH_3C^{\bullet}HCH_3$	88±3	1
$^{\bullet}C_4H_5$, $CH_3C{\equiv}CC^{\bullet}H_2$	293.7±8.4	1
$^{\bullet}C_4H_5$, $CH{\equiv}CC^{\bullet}HCH_3$	295.0±9.2	1
$^{\bullet}C_4H_7$, $CH_3CH{=}CHC^{\bullet}H_2$	146±8	1
$^{\bullet}C_4H_7$, $CH_2{=}CHCH_2C^{\bullet}H_2$	192.5	1
$^{\bullet}C_4H_7$, $CH_2{=}C(CH_3)C^{\bullet}H_2$	128.0±2.5	1
$^{\bullet}C_4H_7$, $CH_2{=}CHC^{\bullet}HCH_3$	133.1±6.5	1
$^{\bullet}C_4H_7$, cyclopropylmethyl	213.8±6.7	1
$^{\bullet}C_4H_7$, cyclobutyl	215.1±4.2	1
$^{\bullet}C_4H_9$, butyl, $CH_3CH_2CH_2C^{\bullet}H_2$	77.8±2.1	1
iso-$C_4H_9^{\bullet}$, *iso*-butyl, $(CH_3)_2CHC^{\bullet}H_2$	70±4	1
sec-$C_4H_9^{\bullet}$, *sec*-butyl, $CH_3C^{\bullet}HCH_2CH_3$	67.8±2.1	1
tert-$C_4H_9^{\bullet}$, *tert*-butyl, $(CH_3)_3C^{\bullet}$	48±3	1
$^{\bullet}C_5H_5$, $CH_2{=}CHC{\equiv}CC^{\bullet}H_2$	351.5	1
$^{\bullet}C_5H_5$, $CH_2{=}CH{-}C^{\bullet}H{-}C{\equiv}CH$	372.4	1
$^{\bullet}C_5H_5$, cyclopenta-1,3-dien-5-yl	261.5±4.2	1
$^{\bullet}C_5H_7$, $CH_3C{\equiv}CC^{\bullet}HCH_3$	272.8±9.2	1
$^{\bullet}C_5H_7$, $CH{\equiv}CC^{\bullet}HC_2H_5$	277.0±8.4	1
$^{\bullet}C_5H_7$, $CH{\equiv}CC^{\bullet}(CH_3)_2$	257.3±9.2	1
$^{\bullet}C_5H_7$, $CH_2{=}CHCH{=}CHC^{\bullet}H_2$	205.0±12.6	1
$^{\bullet}C_5H_7$, $(CH_2{=}CH)_2C^{\bullet}H$	208.0±4.2	1
$^{\bullet}C_5H_7$, $CH_3CH{=}C{=}CHC^{\bullet}H_2$	278	1
$^{\bullet}C_5H_7$, spiropentyl	380.7±4.2	1
$^{\bullet}C_5H_7$, cyclopent-1-en-3-yl	160.7±4.2	1
$^{\bullet}C_5H_9$, cyclopentyl	105.9±4.2	1
$^{\bullet}C_5H_9$, $CH_2{=}CHC^{\bullet}HCH_2CH_3$	109.6±8.4	1
$^{\bullet}C_5H_9$, $CH_3CH{=}CHC^{\bullet}H(CH_3)$	92	1
$^{\bullet}C_5H_9$, $CH_3CH{=}C(CH_3)C^{\bullet}H_2$	92	1
$^{\bullet}C_5H_9$, $CH_2{=}CHC^{\bullet}(CH_3)_2$	87.0±8.4	1
$^{\bullet}C_5H_9$, $CH_2{=}C(CH_3)C^{\bullet}H(CH_3)$	93.7	1
$^{\bullet}C_5H_9$, $CH_2{=}C(C^{\bullet}H_2)CH_2CH_3$	114.2	1
$^{\bullet}C_5H_9$, $CH_2{=}CH(CH_2)_2C^{\bullet}H_2$	179.5	1
$C_5H_{11}^{\bullet}$, $CH_3CH_2CH_2CH_2C^{\bullet}H_2$	54.4	1
$^{\bullet}C_5H_{11}$, $(C_2H_5)_2C^{\bullet}H$	47	1
$^{\bullet}C_5H_{11}$, $(nC_3H_7)(CH_3)C^{\bullet}H$	50.2	1
$^{\bullet}C_5H_{11}$, $(CH_3)_3C^{\bullet}CH_2$	36.4±8.4	1
$^{\bullet}C_5H_{11}$, $(C_2H_5)(CH_3)_2C^{\bullet}$	29	1
$^{\bullet}C_6H_5$, phenyl	330.1±3.3	1
$^{\bullet}C_6H_7$, cyclohexa-1,3-dien-5-yl	199.2	1
$^{\bullet}C_6H_7$, cyclohexa-1,4-dien-3-yl	201.7±5.0	1
$^{\bullet}C_6H_9$, $CH_3C{\equiv}CC^{\bullet}(CH_3)_2$	221.8±9.2	1
$^{\bullet}C_6H_9$, $(CH_2{=}CH)_2C^{\bullet}(CH_3)$	193.7	1
$^{\bullet}C_6H_9$, cyclohexa-1-en-3-yl	119.7	1
$^{\bullet}C_6H_{11}$, $CH_2{=}CH(CH_2)_3C^{\bullet}H_2$	158.6	1
$^{\bullet}C_6H_{11}$, $CH_2{=}C(CH_3)C^{\bullet}(CH_3)_2$	37.7±6.3	1
$^{\bullet}C_6H_{11}$, $(CH_3)_2C{=}C(CH_3)C^{\bullet}H_2$	39.7±6.3	1
$^{\bullet}C_6H_{11}$, cyclohexyl	75.3±6.3	1
$^{\bullet}C_6H_{13}$, $CH_3CH_2CH_2CH_2CH_2C^{\bullet}H_2$	33.5	1
$^{\bullet}C_6H_{13}$, $(nC_4H_9)(CH_3)C^{\bullet}H$	29.3	1
$^{\bullet}C_6H_{13}$, 2-methyl-2-pentyl	3.3±8.4	1
$^{\bullet}C_6H_{13}$, 3-methyl-3-pentyl	14.2	1
$^{\bullet}C_6H_{13}$, 2,3-dimethyl-2-butyl	3.1±10	1
$^{\bullet}C_7H_3$, $(CH{\equiv}C)_3C^{\bullet}$	784.5	1
$^{\bullet}C_7H_7$, benzyl, $C_6H_5C^{\bullet}H_2$	208.0±1.7	14
$^{\bullet}C_7H_7$, quadricyclolan-5-yl	578.6±5.4	1
$^{\bullet}C_7H_7$, quadricyclolan-4-yl	587.4±5.4	1
$^{\bullet}C_7H_7$, norborna-2,5-dien-7-yl	511.7±7.9	1
$^{\bullet}C_7H_7$, cyclohepta-1,3,5-trien-7-yl	285.3±12.6	1
$^{\bullet}C_7H_9$, $CH_2{=}CH(CH{=}CH)_2CC^{\bullet}H_2$	251	1
$^{\bullet}C_7H_9$, $(CH_2{=}CH)_3C^{\bullet}$	274	1
$^{\bullet}C_7H_{11}$, norborn-1-yl	136.4±10.5	1
$^{\bullet}C_7H_{11}$, cycloheptenyl	119.2	1
$^{\bullet}C_7H_{13}$, cycloheptyl	50.6±4.2	1
$^{\bullet}C_7H_{13}$, cyclo-[$C^{\bullet}(CH_3)(CH_2)_5$]	22.6	1
$^{\bullet}C_7H_{13}$, cyclo-[$C^{\bullet}(CH_2CH_3)(CH_2)_4$]	47	1
$^{\bullet}C_7H_{15}$, $(nC_5H_{11})(CH_3)CH^{\bullet}$	8.4	1
$^{\bullet}C_8H_7$, cubyl	831.0±16.7	1
$^{\bullet}C_8H_9$, $C_6H_5C^{\bullet}H(CH_3)$	175.7±7.5	15
$^{\bullet}C_9H_{11}$, $C_6H_5C^{\bullet}(CH_3)_2$	133.9±4.2	1
$^{\bullet}C_{10}H_7$, naphth-1-yl	401.7±5.4	1
$^{\bullet}C_{10}H_7$, naphth-2-yl	400.4±5.9	1
$^{\bullet}C_{10}H_{15}$, 1-adamantyl	51.5	1
$^{\bullet}C_{10}H_{15}$, 2-adamantyl	61.9	1
$^{\bullet}C_{13}H_9$, 9-fluorenyl	297.5	1
$^{\bullet}C_{13}H_{11}$, $(C_6H_5)_2C^{\bullet}H$	302.1±4.2	1
$^{\bullet}C_{19}H_{15}$, trityl, $(C_6H_5)_3C^{\bullet}$	392.0±8.4	1
CF	255.2±8	1
CF_2	-182.0±6.3	1
$FC^{\bullet}(O)$	-161.2±8.4	1
CHF	143.0±12.6	1

Radical	$\Delta_f H^o_{298}$/kJ mol-1	Ref.
CClF	31.0±13.4	1
CCl	443.1±13.0	1
CCl_2	226	1
ClC•(O)	-21.8±2.5	1
CHCl	326.4±8.4	1
CClBr	267	1
CBr	510±63	1
CBr_2	324	1
$•CF_3$	-465.7±2.1	1
$•CHF_2$	-238.9±4.2	1
$•CH_2F$	-31.8±4.2	1
$•CClF_2$	-279.0±8.4	1
$•CCl_2F$	-89.0±8.4	1
•CBrClF	-35.5±6.3	10
•CHClF	-60.7±10.0	1
$•CBrF_2$	-224.7±12.6	1
$•CCl_3$	71.1±2.5	1
$•CHCl_2$	93.3±4.2	1
$•CH_2Cl$	117.2±2.9	1
•CHBrCl	143±6	11
$•CHBr_2$	188.3±9.2	1
$•CBr_2Cl$	163±8	1
$•CBrCl_2$	124±8	1
$•CBr_3$	205.0±8.4	1
$•CH_2Br$	171.1±2.7	11
$•CHI_2$	314.4±3.3	1
$•CH_2I$	229.7±8.4	1
$•C_2F$, FC≡C•	460.0±21.0	1
$•C_2F_3$, CF_2=C•F	-192.0±8.4	1
$•C_2F_2H$, CF_2=C•H	-92.9±8.4	1
$•C_2F_2H$, CHF=C•F	-50.6±8.4	1
$•CCl_2H$, CHCl=C•Cl	234.7±8.4	1
$•CClH_2$, CH_2=C•Cl	>251	1
$•C_2F_5$, $CF_3C•F_2$	-892.9±4.2	1
$•C_2HF_4$, $CF_3C•HF$	-680.8±9.6	1
$•C_2HF_4$, $CHF_2C•F_2$	-664.8	1
$•C_2H_2F_3$, $CF_3C•H_2$	-517.1±8.4	1
$•C_2H_2F_3$, $CHF_2C•HF$	-456	1
$•C_2H_2F_3$, $CH_2FC•F_2$	-449.8	1
$•C_2H_2F_2Cl$, $CF_2ClC•H_2$	-310.9±7.0	1
$•C_2H_3F_2$, $CH_3C•F_2$	-302.5±8.4	1
$•C_2H_3F_2$, $CHF_2C•H_2$	-285.8	1
$•C_2H_3F_2$, $CH_2FC•HF$	-238.5	1
$•C_2H_4F$, $CH_3C•HF$	-70.3±8.4	1
$•C_2H_4F$, $CH_2FC•H_2$	-59.4±8.4	1
$•C_2F_4Cl$, $CF_2ClC•F_2$	-686	1
$•C_2F_3ClBr$, $CF_3C•ClBr$	-504.2±8.4	1
$•C_2HF_3Cl$, $CClF_2C•HF$	-450.6±12.6	1
$•C_2Cl$, ClC≡C•	534±50	1
$•C_2Cl_3$, CCl_2=C•Cl	190±50	1
$•C_2Cl_5$, $CCl_3C•Cl_2$	35.1±5.4	1
$•C_2HCl_4$, $CHCl_2C•Cl_2$	23.4±8.4	1
$•C_2HCl_4$, $CCl_3C•HCl$	51	1
$•C_2H_2Cl_3$, $CH_2ClC•Cl_2$	26.4	1
$•C_2H_2Cl_3$, $CHCl_2C•HCl$	46.4	1
$•C_2H_2Cl_3$, $CCl_3C•H_2$	71.5±8	1
$•C_2H_3Cl_2$, $CH_3C•Cl_2$	42.5±1.7	1
$•C_2H_3Cl_2$, $CH_2ClC•ClH$	65.3	1
$•C_2H_3Cl_2$, $CHCl_2C•H_2$	90.1±0.8	1
$•C_2H_4Cl$, $CH_3C•HCl$	76.5±1.6	1
$•C_2H_4Cl$, $CH_2ClC•H_2$	93.0±2.4	1

Radical	$\Delta_f H^o_{298}$/kJ mol-1	Ref.
$•C_2H_3Br_2$, $CH_3C•Br_2$	140.2±5.4	1
$•C_2H_4Br$, $BrCH_2C•H_2$	135.1	1
$•C_2H_4Br$, $CH_3C•HBr$	126.8	1
$•C_3F_7$, $CF_3CF_2C•F_2$	435.1±8.4	1
iso-C_3F_7•, $CF_3C•FCF_3$	433.5±2.5	1
$•C_3H_6Cl$, $CH_3CH_2C•HCl$	56.6	1
$•C_3H_6Cl$, $CH_3C•ClCH_3$	29.9±0.6	1
$•C_3H_6Br$, $C•H_2CH_2CH_2Br$	120.1±1.3	8
$•C_3H_6Br$, $CH_3C•HCH_2Br$	96.7±5.9	8
$•C_3H_6Br$, $CH_3CH_2C•HBr$	107.5±2.5	8
$•C_6F_5$	-547.7±8.4	1
$•CH_3O$, $HOC•H_2$	-17.0±0.7	14
$•CH_2BrO$, $BrOC•H_2$	151±16	1
$•C_2H_3O$, C•H=CHOH	121±11	1
$•C_2H_5O$, $C•H_2CH_2OH$	-31±7	1
$•C_2H_3O$, oxiran-2-yl	149.8±6.3	1
$•C_3H_5O$,CH_2=CHC•HOH	0±8.4	1
$•C_3H_7O$, $CH_3CH_2C•HOH$	-81±4	1
$•C_3H_7O$, $(CH_3)C•HCH_2OH$	-78.7±8.4	1
$•C_3H_7O$, $HOCH_2CH_2C•H_2$	-66.9±8.4	1
$•C_3H_7O$, $(CH_3)_2C•OH$	-110.0±4.2	1
$•C_4H_9O$, $•CH_2C(OH)(CH_3)_2$	-147.3±8.4	1
$•C_5H_7O$, $(CH_2$=$CH)_2C•OH$	92.5±8.4	1
$•C_2H_5O_3$, $C•H_2OCH_2OOH$	109.6±4.2	1
$Ph_2C•OH$	152.3±6.3	1
$•C_2H_5O$, $CH_3OC•H_2$	0±4.2	1
$•C_3H_7O$, $CH_3OC•HCH_3$	-57.7±8.4	1
$•C_3H_7O$, $CH_3CH_2OC•H_2$	-45.2±8.4	1
$•C_3H_7O$, $C•H_2CH_2OCH_3$	-7.1±4.2	7
$•C_4H_9O$, $(CH_3)_2CHOC•H_2$	-70.3±7.1	7
$•C_4H_9O$, $CH_3CH_2OC•HCH_3$	-81.2±4.2	1
$•C_4H_9O$, $C•H_2CH(CH_3)OCH_3$	-42.3±3.8	7
$•C_4H_9O$, $(CH_3)_2C•OCH_3$	-72.4±10	7
$•C_5H_{11}O$, $(CH_3)_3COC•H_2$	-102.5±8.4	7
$•C_2H_5O_2$, $HOCH_2C•HOH$	-220.1±8.4	1
C•H=C=O	176.6±2.9	1
HC•(O)	42.5±0.5	1
$CH_3C•(O)$	-10.3±1.8	14
$CH_2ClC•(O)$	-21±12.6	1
$CHCl_2C•(O)$	-17.6±23	1
$CCl_3C•(O)$	-21.8±23.4	1
$CF_3C•(O)$	-537.2	1
$CH_3CH_2C•(O)$	-32.3±4.2	1
$CH_2CHC•(O)$	80.8±8.4	1
$C_6H_5C•(O)$	116.3±10.9	1
$HC(O)CH_2•$	10.5±9.2	1
$CH_3C(O)CH_2•$	-34±3	1
$CH_3C(O)C•HCH_3$	-70.3±7.1	1
$CH_3C(O)C•=CH_2$	113.4	1
$C_2H_5C(O)C•HCH_3$	-107.5±20.9	1
iso-$PrC(O)C•(CH_3)_2$	-173.6±20.9	1
tert-$C_4H_9C(O)C•H_2$	-115.5±12.6	1
$PhC(O)C•H_2$	84.5±12.6	1
$PhC(O)C•HCH_3$	41.4±20.9	1
PhC•HC(O)CH_2Ph	134.3±20.9	1
$PhC(O)OC•H_2$	-69.9	1
•C(O)OH-*trans*	-194.6±2.9	1
•C(O)OH-*cis*	-219.7	1
$•C(O)OCH_3$	-169.5±8.4	1
$C•H_2C(O)OH$	-248.9±12.0	1
$C•H(CH_3)C(O)OH$	-293±3	1

Radical	$\Delta_f H^o_{298}$/kJ mol-1	Ref.
$C^{\bullet}H_2C(O)OCH_3$	-236.8±8.4	1
$C^{\bullet}H_2C(O)OCH_2CH_3$	-260.2±12.6	1
$C^{\bullet}H_2C(O)OPh$	-28	1
$^{\bullet}C_4H_7O$, tetrahydrofuran-2-yl	-18.0±6.3	1
$^{\bullet}C_4H_8O$, cyclopentanon-2-yl	-41.8±12.6	1
$^{\bullet}CH_3O_2$, $C^{\bullet}H_2OOH$	17	1
$^{\bullet}C_2H_5O_2$, $CH_3CH^{\bullet}OOH$	2	1
$^{\bullet}C_2H_3O_3$, $C^{\bullet}H_2C(O)OOH$	-137.9	3
$^{\bullet}CHN_2$	494.5	1
$^{\bullet}CH_2N{=}CH_2$	263.6±12.6	1
$^{\bullet}CH_2NH_2$	151.9±8.4	1
$CH_3C^{\bullet}HNH_2$	111.7±8.4	1
$(CH_3)_2C^{\bullet}NH_2$	69.9±8.4	1
$^{\bullet}CH_2NHCH_3$	127.6±8.4	1
$^{\bullet}CH_2N(CH_3)_2$	139.0±8.4	1
$(C_2H_5)_2NC^{\bullet}HCH_3$	68.6±2.1	1
$^{\bullet}CH_2N(CH_3)Ph$	266.0±12.6	1
$^{\bullet}CN$	439.3±2.9	1
$^{\bullet}CH_2CN$	252.6±4	1
$CH_3C^{\bullet}HCN$	226.7±12.6	1
$^{\bullet}CH_2CH_2CN$	245.4±12.6	1
$(CH_3)_2C^{\bullet}CN$	190.4±12.6	1
$Ph(CH_3)C^{\bullet}CN$	248.5±8.4	1
$NCC^{\bullet}HCH_2CN$	381.8±12.6	1
$^{\bullet}CH_2NC$	334.7±16.7	4
$^{\bullet}CCN$	556±126	1
$^{\bullet}C(O)NC$	210.0±10	1
$^{\bullet}C(O)NH_2$	-15.1±4	9
$C^{\bullet}NN$	569±21	1
$HC^{\bullet}NN$	460±8	1
$H_2C^{\bullet}NN$	292.5±2.1	1
$^{\bullet}CH_2NO$	157±4	9
$^{\bullet}CH_2NO_2$	115.1±12.6	1
$CH_3C^{\bullet}HNO_2$	61.9±12.6	1
$(CH_3)_2C^{\bullet}NO_2$	6.3±12.6	1
$PhC^{\bullet}HNO_2$	169.0±12.6	1
$^{\bullet}C(S)H$	300.4±8.4	1
$^{\bullet}CH_2SH$	151.9±8.4	1
$^{\bullet}CH_2SCH_3$	136.8±5.9	1
$^{\bullet}CH_2SPh$	268.6±12.6	1
$^{\bullet}CH_2SOCH_3$	23.8±12.6	1
$HOC^{\bullet}(S)S$	110.5	1
$^{\bullet}CH_2SO_2CH_3$	-177.0±12.6	1
$^{\bullet}CH_2SO_2Ph$	-57.3±12.6	1
$PhC^{\bullet}HSO_2CH_3$	-109.2±12.6	1
$PhC^{\bullet}HSO_2Ph$	7±12.6	1
$Ph_2C^{\bullet}SO_2Ph$	102±12.6	1
$Ph_2C^{\bullet}SPh$	435.6±12.6	1
$NC^{\bullet}(O)$	127.2	1
$^{\bullet}CNH$	207.9±12.1	1
$^{\bullet}CNO$	323±30	5
$^{\bullet}CH_2SiMe_3$	-32±6	1
$^{\bullet}CH_2C(CH_3)_2SiMe_3$	-125	1
$^{\bullet}CP$	450±9	1
(2) Oxygen-Centered Species		
$HO^{\bullet}$	37.3±0.3	14
$FO^{\bullet}$	109±10	9
$ClO^{\bullet}$	101.63±0.1	9
$BrO^{\bullet}$	126.2±1.7	9
$IO^{\bullet}$	115.9±5.0	9

Radical	$\Delta_f H^o_{298}$/kJ mol-1	Ref.
$HOO^{\bullet}$	13.4±2.1	1
$FOO^{\bullet}$	25.4±2	1
$ClOO^{\bullet}$	98.0±4	1
$BrOO^{\bullet}$	108±40	1
$IOO^{\bullet}$	96.6±15	1
$OFO^{\bullet}$	378.6±20	1
$OClO^{\bullet}$	95.4	1
$ClOOClO^{\bullet}$	142±12	1
$ClClO^{\bullet}$	90±30	1
$NCO^{\bullet}$	184.1	1
$HONNO^{\bullet}$	172	13
sym-ClO_3	217.2±21	1
$HSOO^{\bullet}$	112	1
$CH_3SOO^{\bullet}$	76	1
$CF_3SO_2O^{\bullet}$	-912	1
O_3	142.7±1.7	1
$NCO^{\bullet}$	184	1
$O_2NO^{\bullet}$	71.1	1
$ONOO^{\bullet}$	82.8	1
$CH_3O^{\bullet}$	21.0±2.1	14
$CH_2{=}CH\text{-}O^{\bullet}$	18.4±1.3	1
$CF_3CHFO^{\bullet}$	-851	12
$C_2H_5O^{\bullet}$	-13.6±3.3	14
$C_3H_7O^{\bullet}$	-30.1±8.4	1
iso-$C_3H_7O^{\bullet}$	-48.5±3.3	1
$C_4H_9O^{\bullet}$	-62.8	1
sec-$C_4H_9O^{\bullet}$	-69.5	1
tert-$C_4H_9O^{\bullet}$	-85.8±3.8	1
$CH_2{=}CHCH_2O^{\bullet}$	87	3
$C_6H_5O^{\bullet}$	54±6	1
o-OH-$C_6H_4O^{\bullet}$	-186.3	1
p-OH-$C_6H_4O^{\bullet}$	-143.6	1
o-CH_3O-$C_6H_4O^{\bullet}$	-125.5	1
p-CH_3O-$C_6H_4O^{\bullet}$	-81.1	1
$C_6H_5CH_2O^{\bullet}$	107.1±12.6	1
$C_{10}H_7O^{\bullet}$, naphthoxy-1	165.3	1
$C_{10}H_7O^{\bullet}$, naphthoxy-2	174.1	1
$CF_3O^{\bullet}$	-635.1±7.1	1
$HC(O)O^{\bullet}$	-125.5±12.6	6
$FC(O)O^{\bullet}$	368	1
$CH_3C(O)O^{\bullet}$	-179.9±12.6	6
$CF_3C(O)O^{\bullet}$	-797	1
$C_6H_5C(O)O^{\bullet}$	-50.2±16.7	6
$CH_3OO^{\bullet}$	20.1±5.1	1
$C_2H_3OO^{\bullet}$, $CH_2{=}CHOO^{\bullet}$	101.7±1.7	1
$C_2H_5OO^{\bullet}$	-28.5±9.6	1
$C_3H_5OO^{\bullet}$, $CH_2{=}CHCH_2OO^{\bullet}$	88.7	3
iso-$C_3H_7OO^{\bullet}$	-65.4±11.3	1
$C_4H_7OO^{\bullet}$, $CH_3CH{=}CHCH_2OO^{\bullet}$	82.6±5.3	1
tert-$C_4H_9OO^{\bullet}$	-101.5±9.2	1
$HOCH_2OO^{\bullet}$	-162.1	1
$C_6H_5CH_2OO^{\bullet}$	114.6±4.2	1
cyclo-$C_6H_7OO^{\bullet}$, R = cyclohexadienyl	151.6±12.6	1
cyclo-$C_6H_{11}OO^{\bullet}$	-25.0±10.5	1
cyclo-$C_4H_8NOO^{\bullet}$, R = pyrrolidin-2-yl	101.3±12.6	1
$(C_2H_5)N(CH3)CHOO^{\bullet}$	-36.0±12.6	1
$CF_3OO^{\bullet}$	-614.0±15.4	1
$CF_2ClOO^{\bullet}$	-406.7±14.6	1
$CFCl_2OO^{\bullet}$	-213.7	1
$CH_2ClOO^{\bullet}$	-5.1±13.6	1
$CHCl_2OO^{\bullet}$	-19.2±11.2	1

Radical	$\Delta_f H^\circ_{298}$/kJ mol-1	Ref.
$CCl_3OO^\bullet$	-20.9±8.9	1
$CH_3CHClOO^\bullet$	-54.7±3.4	1
$CH_3CCl_2OO^\bullet$	-63.8±9.8	1
$CH_3C(O)CH_2OO^\bullet$	-162	1
$CH_3C(O)OO^\bullet$	-154.4±5.8	9
$HOOO^\bullet$	29.7±8.4	2
$CH_3OOO^\bullet$	33.4±12.6	1
$C_2H_5OOO^\bullet$	5.4±12.6	1
(3) Nitrogen-Centered Species		
NH	357±1	1
$^\bullet NH_2$	186.2±1.0	14
$^\bullet NNH$	249.5	1
$^\bullet NCO$	131.8	1
$^\bullet N_3$	486.6±20.9	1
$^\bullet N_2H_3$	243.5	1
(*Z*)-N_2H_2	213.0±10.9	1
NF	209.2	1
$^\bullet NF_2$	42.3±8	1
NBr	301±21	1
HNO	107.1±2.5	1
FNO	-65.7±1.7	1
ClNO	51.71±0.42	1
BrNO	82.13±0.8	1
INO	112.1±20.9	1
NCO	131	1
NCN	464.8±2.9	1
NSi	372.4±62.8	1
$NH_2C(O)N^\bullet H$	0.8±12.6	1
$CH_3C(O)N^\bullet H$	-6.7±12.6	1
$NH_2C(S)N^\bullet H$	194±12.6	1
$CH_3C(S)N^\bullet H$	173±12.6	1
$PhC(S)N^\bullet H$	307±12.6	1
$HCON^\bullet H$	49.8±12.6	1
$NH_2C(NH)N^\bullet H$	250.6±12.6	1
$^\bullet NHCN$	319.2±2.9	1
$CH_2N^\bullet H$	104.6±12.6	1
$CH_3N^\bullet H$	184.1±8.4	1
tert-$BuN^\bullet H$	95.4±12.6	1
$C_6H_5CH_2N^\bullet H$	288.3±12.6	1
$C_6H_5N^\bullet H$	244.3±4.2	1
$(CH_3)_2N^\bullet$	158.2±4.2	1
$(C_6H_5)(CH_3)N^\bullet$	241.0±6.3	1
$(C_6H_5)_2N^\bullet$	366.0±6.3	1
carbazol-9-yl	383.3±4.2	1
$CH_3N_2^\bullet$	215.5±7.5	1
$C_2H_5N_2^\bullet$	187.4±10.5	1
(4) Sulfur-Centered Species		
$HOS^\bullet$	-3.8±2.9	1
$HC(O)S^\bullet$	56.5	1
$HS^\bullet O_2$	-221.8	1
$HOS^\bullet O_2$	-384.9	1
$NCS^\bullet$	300±8	1
$HS^\bullet$	143.0±0.8	1
$CH_3S^\bullet$	124.7±1.7	1
$C_2H_5S^\bullet$	101	1
$C_3H_7S^\bullet$	80	1
iso-$C_3H_7S^\bullet$	74.9±8.4	1
tert-$C_4H_9S^\bullet$	43.9±8.4	1
$C_6H_5S^\bullet$	242.7±4.6	1
$C_6H_5CH_2S^\bullet$	246	1
$CH_3S^\bullet O$	-67±10	1
$CH_3S^\bullet O_2$	-239.3	1
$HSS^\bullet$	115.5±14.6	1
$CH_3SS^\bullet$	68.6±8.4	1
$C_2H_5SS^\bullet$	43.5±8.4	1
iso-$C_3H_7SS^\bullet$	13.8±8.4	1
tert-$C_4H_9SS^\bullet$	-19.2±8.4	1
$HOC(S)S^\bullet$	110.5±4.6	1
$HC(O)S^\bullet$	56.5	1
SF	13.0±6.3	1
SF_2	-296.7±16.7	1
SF_3	-503.0±33.5	1
SF_4	-763.2±20.9	1
SF_5	-879.9±15.1	1
$ClS^\bullet$	156.5±16.7	1
SN	263.6±105	1
SCl	156.5±16.7	1
(5) Silicon-Centered Species		
SiF	-20.1±12.6	1
SiF_2	-638±6	1
$^\bullet SiF_3$	-987±20	1
SiCl	198.3±6.7	1
$SiCl_2$	-169±3	1
$^\bullet SiCl_3$	322±8	1
SiBr	235±46	1
$SiBr_2$	46±8	1
SiI	313.6±41.8	1
SiH	376.6±8.4	1
$SiH_2(^1A_1)$	273±2	1
$SiH_2(^3B_1)$	360.7	1
$^\bullet SiH_3$	200.4±2.5	1
$MeSi^\bullet H_2$	141±6	1
$Me_2Si^\bullet H$	78±6	1
$Me_3Si^\bullet$	15±7	1
$^\bullet Si_2H_3$	~402	1
$H_3SiSi^\bullet H_2$	234±6	1
$C_6H_5Si^\bullet H_2$	274	1
$H_3SiSi^\bullet H$	312±8	1
$MeSi^\bullet H$	202±6	1
$Me_2Si^{\bullet\bullet}$	135±8	1
SiN	313.6±41.8	1
(6) Ge, Sn-Centered Species		
$^\bullet GeH_3$	221.8±8.4	1
$^\bullet Sn(C_6H_5)_3$	518.8±21	1

References

1. Luo, Y. R., Handbook of Bond dissociation Energies in Organic Compounds, CRC Press, 2002.
2. Denis, P. A., Kieninger, M., et al., *Chem. Phys. Lett.,* 365, 440-449, 2002.
3. Lee, J. W., Chen, C. J., *J. Phys. Chem. A,* 106:7155-7170, 2002.
4. Nimlos, M. R., Davico, G., et al., *J. Chem. Phys.*, 117, 4323-4339, 2002.
5. Sailer, W., Pelc, A., et al., *J. Chem. Phys. A,* 117, 7989-7994, 2002.
6. Blanksby, S. J. and Ellison, G. B., *Acc. Chem. Res.,* 36, 255-263, 2003.
7. Chen, C. C. and Bozzelli, J. W., *J. Phys. Chem. A,* 107, 4531-4546, 2003.
8. Garcia, J. E., *Chem. Phys. Lett.,* 377, 607-612, 2003.
9. US NASA, http://jpldataeval.jpl.nasa.gov, Feb 24, 2003.
10. Owens, N. L., Nauta, K., *Chem. Phys. Lett.,* 370, 469-477, 2003.
11. Seetula, J. A., *Phys. Chem. Chem. Phys.*, 5, 849-855, 2003.
12. Wu, F. and Carr, R.W., *J. Phys. Chem. A,* 107, 10733-10742, 2003.
13. Poskrebyshev, G. A, Shafirovich, V., et al., *J. Am. Chem. Soc.,* 126, 891-899, 2004.
14. Ruscic, B., Boggs, J. E., et al., *J. Phys. Chem.* Ref. Data, 34, in press, 2005.
15. Tokmakov, I. V. and Lin, M. C., *J. Phys. Chem. A,* 108, 9697–9714, 2004.

TABLE 5. Bond Dissociation Energies of Some Organic Molecules

$D°_{298}$(R-X)/ kJ mol^{-1} of some organic compounds are listed below. All data are from Tables 1 and 3.

	X = H	**F**	**Cl**	**Br**	**I**	**OH**	**OCH_2**	**NH_2**	**NO**	**CH_3**	**$COCH_3$**	**CF_3**	**CCl_3**
R = H	435.7644	569.87	431.328	366.35	298.407	497.10	440.0	450.1	199.5	439.3	374.0	445.2	392.5
CH_3	439.3	460.2	350.2	294.1	238.9	384.93	351.9	356.1	172.0	377.4	351.9	429.3	362.3
C_2H_5	420.5	473.2	352.3	292.9	233.5	391.2	355.2	352.3	171.5	370.3	347.3	–	–
iso-C_3H_7	410.5	482.8	354.0	299.2	234.7	397.9	360.7	357.7	152.7	369.0	340.2	–	–
tert-C_4H_9	400.4	489.5	351.9	292.9	227.2	398.3	353.1	355.6	167	363.6	329.3	–	–
C_6H_5	472.2	525.5	399.6	336.4	272.0	463.6	418.8	429.3	226.8	426.8	406.7	463.2	388.7
$C_6H_5CH_2$	375.5	412.8	299.9	239.3	187.8	345.6	–	306.7	123	325.1	299.7	365.7	–
CCl_3	392.5	439.3	296.6	231.4	168	–	–	–	125	362.3	–	332.2	285.8
CF_3	445.2	546.8	365.3	296.2	227.2	≤482.0	–	280.7	167	429.3	–	413.0	332.2
C_2F_5	429.7	532.2	346.0	283.3	219.2	–	–	–	–	–	–	426.3	–
CH_3CO	374.0	511.7	354.0	292.0	223.0	459.4	424.3	414.6	–	351.9	307.1	–	–
CN	528.5	482.8	422.6	364.8	320.1	–	–	–	120.5	521.7	–	469.0	–
C_6F_5	487.4	485	383.3	~328	<301.7	446.9	–	–	211.3	439.3	–	435.1	–

ELECTRONEGATIVITY

Electronegativity is a parameter originally introduced by Pauling which describes, on a relative basis, the tendency of an atom in a molecule to attract bonding electrons. While electronegativity is not a precisely defined molecular property, the electronegativity difference between two atoms provides a useful measure of the polarity and ionic character of the bond between them. This table gives the electronegativity X, on the Pauling scale, for the most common oxidation state. Other scales are described in the references.

References

1. Pauling, L., *The Nature of the Chemical Bond, Third Edition*, Cornell University Press, Ithaca, NY, 1960.
2. Allen, L. C., *J. Am. Chem. Soc.*, 111, 9003, 1989.
3. Allred, A. L., *J. Inorg. Nucl. Chem.*, 17, 215, 1961.

Z	Symbol	*X*	*Z*	Symbol	*X*	*Z*	Symbol	*X*
1	H	2.20	33	As	2.18	65	Tb	—
2	He	—	34	Se	2.55	66	Dy	1.22
3	Li	0.98	35	Br	2.96	67	Ho	1.23
4	Be	1.57	36	Kr	—	68	Er	1.24
5	B	2.04	37	Rb	0.82	69	Tm	1.25
6	C	2.55	38	Sr	0.95	70	Yb	—
7	N	3.04	39	Y	1.22	71	Lu	1.0
8	O	3.44	40	Zr	1.33	72	Hf	1.3
9	F	3.98	41	Nb	1.6	73	Ta	1.5
10	Ne	—	42	Mo	2.16	74	W	1.7
11	Na	0.93	43	Tc	2.10	75	Re	1.9
12	Mg	1.31	44	Ru	2.2	76	Os	2.2
13	Al	1.61	45	Rh	2.28	77	Ir	2.2
14	Si	1.90	46	Pd	2.20	78	Pt	2.2
15	P	2.19	47	Ag	1.93	79	Au	2.4
16	S	2.58	48	Cd	1.69	80	Hg	1.9
17	Cl	3.16	49	In	1.78	81	Tl	1.8
18	Ar	—	50	Sn	1.96	82	Pb	1.8
19	K	0.82	51	Sb	2.05	83	Bi	1.9
20	Ca	1.00	52	Te	2.1	84	Po	2.0
21	Sc	1.36	53	I	2.66	85	At	2.2
22	Ti	1.54	54	Xe	2.60	86	Rn	—
23	V	1.63	55	Cs	0.79	87	Fr	0.7
24	Cr	1.66	56	Ba	0.89	88	Ra	0.9
25	Mn	1.55	57	La	1.10	89	Ac	1.1
26	Fe	1.83	58	Ce	1.12	90	Th	1.3
27	Co	1.88	59	Pr	1.13	91	Pa	1.5
28	Ni	1.91	60	Nd	1.14	92	U	1.7
29	Cu	1.90	61	Pm	—	93	Np	1.3
30	Zn	1.65	62	Sm	1.17	94	Pu	1.3
31	Ga	1.81	63	Eu	—			
32	Ge	2.01	64	Gd	1.20			

FORCE CONSTANTS FOR BOND STRETCHING

Representative force constants (f) for stretching of chemical bonds are listed in this table. Except where noted, all force constants are derived from values of the harmonic vibrational frequencies ω_e. Values derived from the observed vibrational fundamentals ν, which are noted by a, are lower than the harmonic force constants, typically by 2 to 3% in the case of heavy atoms (often by 5 to 10% if one of the atoms is hydrogen). Values are given in the SI unit newton per centimeter (N/cm), which is identical to the commonly used cgs unit mdyn/Å.

References

1. Huber, K. P., and Herzberg, G., *Molecular Spectra and Molecular Structure. IV. Constants of Diatomic Molecules*, Van Nostrand Reinhold, New York, 1979.
2. Shimanouchi, T., The Molecular Force Field, in Eyring, H., Henderson, D., and Yost, W., Eds., *Physical Chemistry: An Advanced Treatise*, Vol. IV, Academic Press, New York, 1970.
3. Tasumi, M., and Nakata, M., *Pure and Appl. Chem.*, 57, 121—147, 1985.

Bond	Molecule	f/(N/cm)	Note
H-H	H_2	5.75	
Be-H	BeH	2.27	
B-H	BH	3.05	
C-H	CH	4.48	
	CH_4	5.44	b
	C_2H_6	4.83	a,b,c
	CH_3CN	5.33	b
	CH_3Cl	5.02	a,b,c
	$CCl_2{=}CH_2$	5.57	b
	HCN	6.22	
N-H	NH	5.97	
O-H	OH	7.80	
	H_2O	8.45	
P-H	PH	3.22	
S-H	SH	4.23	
	H_2S	4.28	
F-H	HF	9.66	
Cl-H	HCl	5.16	
Br-H	HBr	4.12	
I-H	HI	3.14	
Li-H	LiH	1.03	
Na-H	NaH	0.78	
K-H	KH	0.56	
Rb-H	RbH	0.52	
Cs-H	CsH	0.47	
C-C	C_2	12.16	
	$CCl_2{=}CH_2$	8.43	
	C_2H_6	4.50	a,c
	CH_3CN	5.16	
C-F	CF	7.42	
	CH_3F	5.71	a,c
C-Cl	CCl	3.95	
	CH_3Cl	3.44	a,c
	$CCl_2{=}CH_2$	4.02	b
C-Br	CH_3Br	2.89	a,c
C-I	CH_3I	2.34	a,c
C-O	CO	19.02	
	CO_2	16.00	
	OCS	16.14	
	CH_3OH	5.42	a,c
C-S	CS	8.49	
	CS_2	7.88	
	OCS	7.44	
C-N	CN	16.29	
	HCN	18.78	
	CH_3CN	18.33	
	CH_3NH_2	5.12	a,c
C-P	CP	7.83	
Si-Si	Si_2	2.15	
Si-O	SiO	9.24	
Si-F	SiF	4.90	
Si-Cl	SiCl	2.63	
N-N	N_2	22.95	
	N_2O	18.72	
N-O	NO	15.95	
	N_2O	11.70	
P-P	P_2	5.56	
P-O	PO	9.45	
O-O	O_2	11.77	
	O_3	5.74	a
S-O	SO	8.30	
	SO_2	10.33	a
S-S	S_2	4.96	
F-F	F_2	4.70	
Cl-F	ClF	4.48	
Br-F	BrF	4.06	
Cl-Cl	Cl_2	3.23	
Br-Cl	BrCl	2.82	
Br-Br	Br_2	2.46	
I-I	I_2	1.72	
Li-Li	Li_2	0.26	
Li-Na	LiNa	0.21	
Na-Na	Na_2	0.17	
Li-F	LiF	2.50	
Li-Cl	LiCl	1.43	
Li-Br	LiBr	1.20	
Li-I	LiI	0.97	
Na-F	NaF	1.76	
Na-Cl	NaCl	1.09	
Na-Br	NaBr	0.94	
Na-I	NaI	0.76	
Be-O	BeO	7.51	
Mg-O	MgO	3.48	
Ca-O	CaO	3.61	

[a] Derived from fundamental frequency, without anharmonicity correction.
[b] Average of symmetric and antisymmetric (or degenerate) modes.
[c] Calculated from Local Symmetry Force Field (see Reference 2).

FUNDAMENTAL VIBRATIONAL FREQUENCIES OF SMALL MOLECULES

This table lists the fundamental vibrational frequencies of selected three-, four-, and five-atom molecules. Both stable molecules and transient free radicals are included. The data have been taken from evaluated sources. In general, the selected values are based on gas-phase infrared, Raman, or ultraviolet spectra; when these were not available, liquid-phase or matrix-isolation spectra were used.

Molecules are grouped by structural type. Within each group, related molecules appear together for convenient comparison.

The vibrational modes are described by their approximate character in terms of stretching, bending, deformation, etc. However, it should be emphasized that most such descriptions are only approximate, and that the true normal mode usually involves a mixture of motions. Abbreviations are:

sym.	symmetric
antisym.	antisymmetric
str.	stretch
deform.	deformation
scis.	scissors
rock.	rocking
deg.	degenerate

In the case of free radicals, strong interactions may exist between the electronic and bending vibrational motions. Details can be found in References 3 and 4. The references should be consulted for information on the accuracy of the data and for data on other molecules not listed here.

All fundamental frequencies (more precisely, wavenumbers) are given in units of cm^{-1}.

XY_2 Molecules

Point groups $D_{\infty h}$(linear) and C_{2v}(bent)

Molecule	Structure	Sym. str.	Bend	Antisym. str.
CO_2	Linear	1333	667	2349
CS_2	Linear	658	397	1535
C_3	Linear	1224	63	2040
CNC	Linear		321	1453
NCN	Linear	1197	423	1476
BO_2	Linear	1056	447	1278
BS_2	Linear	510	120	1015
KrF_2	Linear	449	233	590
XeF_2	Linear	515	213	555
$XeCl_2$	Linear	316		481
H_2O	Bent	3657	1595	3756
D_2O	Bent	2671	1178	2788
F_2O	Bent	928	461	831
Cl_2O	Bent	639	296	686
O_3	Bent	1103	701	1042
H_2S	Bent	2615	1183	2626
D_2S	Bent	1896	855	1999
SF_2	Bent	838	357	813
SCl_2	Bent	525	208	535
SO_2	Bent	1151	518	1362
H_2Se	Bent	2345	1034	2358
D_2Se	Bent	1630	745	1696

XY_2 Molecules

Point groups $D_{\infty h}$(linear) and C_{2v}(bent)

Molecule	Structure	Sym. str.	Bend	Antisym. str.
NH_2	Bent	3219	1497	3301
NO_2	Bent	1318	750	1618
NF_2	Bent	1075	573	942
ClO_2	Bent	945	445	1111
CH_2	Bent		963	
CD_2	Bent		752	
CF_2	Bent	1225	667	1114
CCl_2	Bent	721	333	748
CBr_2	Bent	595	196	641
SiH_2	Bent	2032	990	2022
SiD_2	Bent	1472	729	1468
SiF_2	Bent	855	345	870
$SiCl_2$	Bent	515		505
$SiBr_2$	Bent	403		400
GeH_2	Bent	1887	920	1864
$GeCl_2$	Bent	399	159	374
SnF_2	Bent	593	197	571
$SnCl_2$	Bent	352	120	334
$SnBr_2$	Bent	244	80	231
PbF_2	Bent	531	165	507
$PbCl_2$	Bent	314	99	299
ClF_2	Bent	500		576

XYZ Molecules

Point Groups $C_{\infty v}$ (linear) and C_s(bent)

Molecule	Structure	XY str.	Bend	YZ str.
HCN	Linear	3311	712	2097
DCN	Linear	2630	569	1925
FCN	Linear	1077	451	2323
ClCN	Linear	744	378	2216
BrCN	Linear	575	342	2198
ICN	Linear	486	305	2188
CCN	Linear	1060	230	1917
CCO	Linear	1063	379	1967
HCO	Bent	2485	1081	1868
HCC	Linear	3612		1848
OCS	Linear	2062	520	859
NCO	Linear	1270	535	1921

XYZ Molecules

Point Groups $C_{\infty v}$ (linear) and C_s(bent)

Molecule	Structure	XY str.	Bend	YZ str.
NNO	Linear	2224	589	1285
HNB	Linear	3675		2035
HNC	Linear	3653		2032
HNSi	Linear	3583	523	1198
HBO	Linear		754	1817
FBO	Linear		500	2075
ClBO	Linear	676	404	1958
BrBO	Linear	535	374	1937
FNO	Bent	766	520	1844
ClNO	Bent	596	332	1800
BrNO	Bent	542	266	1799
HNF	Bent		1419	1000

XYZ Molecules

Point Groups $C_{\infty v}$ (linear) and C_s (bent)

Molecule	Structure	XY str.	Bend	YZ str.
HNO	Bent	2684	1501	1565
HPO	Bent	2095	983	1179
HOF	Bent	3537	886	1393
HOCl	Bent	3609	1242	725
HOO	Bent	3436	1392	1098
FOO	Bent	579	376	1490
ClOO	Bent	407	373	1443
BrOO	Bent			1487
HSO	Bent		1063	1009

XYZ Molecules

Point Groups $C_{\infty v}$ (linear) and C_s (bent)

Molecule	Structure	XY str.	Bend	YZ str.
NSF	Bent	1372	366	640
NSCl	Bent	1325	273	414
HCF	Bent		1407	1181
HCCl	Bent		1201	815
HSiF	Bent	1913	860	834
HSiCl	Bent		808	522
HSiBr	Bent	1548	774	408

Symmetric XY_3 Molecules

Point Groups D_{3h} (planar) and C_{3v} (pyramidal)

Molecule	Structure	Sym. str.	Sym. deform.	Deg. str.	Deg. deform.
NH_3	Pyram.	3337	950	3444	1627
ND_3	Pyram.	2420	748	2564	1191
PH_3	Pyram.	2323	992	2328	1118
AsH_3	Pyram.	2116	906	2123	1003
SbH_3	Pyram.	1891	782	1894	831
NF_3	Pyram.	1032	647	907	492
PF_3	Pyram.	892	487	860	344
AsF_3	Pyram.	741	337	702	262
PCl_3	Pyram.	504	252	482	198
PI_3	Pyram.	303	111	325	79
AsI_3	Pyram.	219	94	224	71
$AlCl_3$	Pyram.	375	183	595	150
SO_3	Planar	1065	498	1391	530
BF_3	Planar	888	691	1449	480
BH_3	Planar		1125	2808	1640
CH_3	Planar		606	3161	1396
CD_3	Planar		453	2369	1029
CF_3	Pyram.	1090	701	1260	510
SiF_3	Pyram.	830	427	937	290

Linear XYYX Molecules

Point Group $D_{\infty h}$

Molecule	Sym. XY str.	Antisym. XY str.	YY str.	Bend	Bend
C_2H_2	3374	3289	1974	612	730
C_2D_2	2701	2439	1762	505	537
C_2N_2	2330	2158	851	507	233

Planar X_2YZ Molecules

Point Group C_{2v}

Molecule	Sym.XY str.	YZ str.	YX_2 scis.	Antisym. XY str.	YX_2 rock	YX_2 wag
H_2CO	2783	1746	1500	2843	1249	1167
D_2CO	2056	1700	1106	2160	990	938
F_2CO	965	1928	584	1249	626	774
Cl_2CO	567	1827	285	849	440	580
O_2NF	1310	822	568	1792	560	742
O_2NCl	1286	793	370	1685	408	652

Tetrahedral XY_4 Molecules

Point Group T_d

Molecule	Sym. str.	Deg. deform.(e)	Deg. str.(f)	Deg. deform.(f)
CH_4	2917	1534	3019	1306
CD_4	2109	1092	2259	996
CF_4	909	435	1281	632
CCl_4	459	217	776	314
CBr_4	267	122	672	182
CI_4	178	90	555	125
SiH_4	2187	975	2191	914
SiD_4	1558	700	1597	681
SiF_4	800	268	1032	389
$SiCl_4$	424	150	621	221
GeH_4	2106	931	2114	819
GeD_4	1504	665	1522	596
$GeCl_4$	396	134	453	172
$SnCl_4$	366	104	403	134
$TiCl_4$	389	114	498	136
$ZrCl_4$	377	98	418	113
$HfCl_4$	382	102	390	112
RuO_4	885	322	921	336
OsO_4	965	333	960	329

References

1. T. Shimanouchi, Tables of Molecular Vibrational Frequencies, Consolidated Volume I, Natl. Stand. Ref. Data Ser. Natl. Bur. Stand. (U.S.), 39, 1972.
2. T. Shimanouchi, Tables of Molecular Vibrational Frequencies, Consolidated Volume II, *J. Phys. Chem. Ref. Data*, 6, 993, 1977.
3. G. Herzberg, *Electronic Spectra and Electronic Structure of Polyatomic Molecules*, D. Van Nostrand Co., Princeton, NJ, 1966.
4. M. E. Jacox, Ground state vibrational energy levels of polyatomic transient molecules, *J. Phys. Chem. Ref. Data*, 13, 945, 1984.

SPECTROSCOPIC CONSTANTS OF DIATOMIC MOLECULES

This table lists the leading spectroscopic constants and equilibrium internuclear distance r_e in the ground electronic state for selected diatomic molecules. The constants are those describing the vibrational and rotational energy through the expressions:

$$E_{vib}/hc = \omega_e(v + 1/2) - \omega_e x_e(v + 1/2)^2 + \ldots$$

$$E_{rot}/hc = B_v J(J + 1) - D_v[J(J + 1)]^2 + \ldots$$

where

$$B_v = B_e - \alpha_e(v+1/2) + \ldots$$

$$D_v = D_e + \ldots$$

Here v and J are the vibrational and rotational quantum numbers, respectively, h is Planck's constant, and c is the speed of light. In this customary formulation the constants ω_e, B_e, etc. have dimensions of inverse length; in this table they are given in units of cm^{-1}.

Users should note that higher order terms in the above energy expressions are required for very precise calculations; constants for many of these terms can be found in the references. Also, if the ground electronic state is not $^1\Sigma$, additional terms are needed to account for the interaction between electronic and pure rotational angular momentum. For some molecules in the table the data have been analyzed in terms of the Dunham series expansion:

$$E/hc = \Sigma_{lm}\, Y_{lm}(v+1/2)^l J^m(J+1)^m$$

In such cases it has been assumed that $Y_{10} = \omega_e$, $Y_{01} = B_e$, etc., although in the highest approximations these identities are not precisely correct. Some of the values of r_e in the table have been corrected for breakdown of the Born-Oppenheimer approximation, which can affect the last decimal place. Because of differences in the method of data analysis and limitations in the model, care should be taken in comparing r_e values for different molecules to a precision beyond 0.001 Å.

Molecules are listed in alphabetical order by formula as written in the most common form. In most cases this form places the more electropositive element first, but there are exceptions such as OH, NH, CH, etc.

* Indicates a value for the interval between $v = 0$ and $v = 1$ states instead of a value of ω_e.

References

1. Huber, K. P., and Herzberg, G., *Molecular Spectra and Molecular Structure IV. Constants of Diatomic Molecules*, Van Nostrand Reinhold, New York, 1979.
2. Lovas, F. J., and Tiemann, E., *J. Phys. Chem. Ref. Data*, 3, 609, 1974.
3. *Landolt-Börnstein, Numerical Data and Functional Relationships in Science and Technology, New Series*, II/6 (1974), II/14a (1982), II/14b (1983), II/19a (1992), II/19d-1 (1995), *Molecular Constants*, Springer-Verlag, Heidelberg.

Molecule	State	ω_e cm^{-1}	$\omega_e x_e$ cm^{-1}	B_e cm^{-1}	α_e cm^{-1}	D_e $10^{-6}cm^{-1}$	r_e Å
$^{107}Ag^{79}Br$	$^1\Sigma^+$	249.57	0.63	0.064833	0.0002361	0.0175	2.39311
$^{107}Ag^{35}Cl$	$^1\Sigma^+$	343.49	1.17	0.12298388	0.00059541	0.06305	2.28079
$^{107}Ag^{19}F$	$^1\Sigma^+$	513.45	2.59	0.2657020	0.0019206	0.284	1.98318
$^{107}Ag^{1}H$	$^1\Sigma^+$	1759.9	34.06	6.449	0.201	344	1.618
$^{107}Ag^{2}H$	$^1\Sigma^+$	1250.70	17.17	3.2572	0.0722	85.9	1.6180
$^{107}Ag^{127}I$	$^1\Sigma^+$	206.50	0.46	0.04486821	0.0001414	0.00847	2.54463
$^{107}Ag^{16}O$	$^2\Pi_{1/2}$	490.2	3.1	0.3020	0.0025	0.45	2.003
$^{27}Al_2$	$^3\Sigma_g^-$	350.01	2.02	0.2054	0.0012	0.31	2.466
$^{27}Al^{79}Br$	$^1\Sigma^+$	378.0	1.28	0.15919713	0.00086045	0.11285	2.29481
$^{27}Al^{35}Cl$	$^1\Sigma^+$	481.30	1.95	0.24393012	0.00161113	0.2503	2.13011
$^{27}Al^{19}F$	$^1\Sigma^+$	802.3	4.77	0.5524798	0.0049841	1.0464	1.65437
$^{27}Al^{1}H$	$^1\Sigma^+$	1682.56	29.09	6.3907	0.1858	356.5	1.6478
$^{27}Al^{2}H$	$^1\Sigma^+$	1211.95	15.14	3.3186	0.0697	97	1.6463
$^{27}Al^{127}I$	$^1\Sigma^+$	316.1	1.0	0.11769985	0.00055859		2.53710
$^{27}Al^{16}O$	$^2\Sigma^+$	979.23	6.97	0.6414	0.0058	1.08	1.6179
$^{27}Al^{32}S$	$^2\Sigma^+$	617.1	3.33	0.2799	0.0018	0.22	2.029
$^{75}As_2$	$^1\Sigma_g^+$	429.55	1.12	0.10179	0.000333		2.1026
$^{75}As^{1}H$	$^3\Sigma^-$	2130*		7.3067	0.2117	327	1.52315
$^{75}As^{2}H$	$^3\Sigma^-$	1484*		3.6688		90	1.5306
$^{75}As^{14}N$	$^1\Sigma^+$	1068.54	5.41	0.54551	0.003366	0.53	1.6184
$^{75}As^{16}O$	$^2\Pi_{1/2}$	967.08	4.85	0.48482	0.003299	0.49	1.6236
$^{197}Au_2$	$^1\Sigma_g^+$	190.9	0.42	0.028013	0.0000723	0.00250	2.4719
$^{197}Au^{1}H$	$^1\Sigma^+$	2305.01	43.12	7.2401	0.2136	279	1.5239
$^{197}Au^{2}H$	$^1\Sigma^+$	1634.98	21.65	3.6415	0.07614	70.9	1.5238
$^{11}B_2$	$^3\Sigma_g^-$	1051.3	9.35	1.212	0.014		1.590
$^{11}B^{79}Br$	$^1\Sigma^+$	684.31	3.52	0.4894	0.0035	1.00	1.888
$^{11}B^{35}Cl$	$^1\Sigma^+$	840.29	5.49	0.684282	0.006812	1.84	1.71528
$^{11}B^{19}F$	$^1\Sigma^+$	1402.1	11.8	1.516950	0.019056	7.105	1.26267
$^{11}B^{1}H$	$^1\Sigma^+$	2366.9	49.40	12.021	0.412	1242	1.2324
$^{11}B^{2}H$	$^1\Sigma^+$	1703.3	28	6.54	0.17	400	1.2324
$^{11}B^{14}N$	$^3\Pi$	1514.6	12.3	1.666	0.025	8.1	1.281
$^{11}B^{16}O$	$^2\Sigma^+$	1885.69	11.81	1.7820	0.0166	6.32	1.2045


Molecule	State	ω_e cm^{-1}	$\omega_e x_e$ cm^{-1}	B_e cm^{-1}	α_e cm^{-1}	D_e 10^{-6}cm^{-1}	r_e Å
$^{11}B^{32}S$	$^2\Sigma^+$	1180.17	6.31	0.7949	0.0061	1.40	1.6092
$^{138}Ba^{79}Br$	$^2\Sigma^+$	193.77	0.41	0.0415082	0.0001219	0.00762	2.84449
$^{138}Ba^{35}Cl$	$^2\Sigma^+$	279.92	0.82	0.08396717	0.00033429	0.03022	2.68276
$^{138}Ba^{19}F$	$^2\Sigma^+$	468.9	1.79	0.2159	0.0012	0.175	2.163
$^{138}Ba^{1}H$	$^2\Sigma^+$	1168.31	14.50	3.38285	0.06599	112.67	2.23175
$^{138}Ba^{2}H$	$^2\Sigma^+$	829.77	7.32	1.7071	0.02363	28.77	2.2304
$^{138}Ba^{127}I$	$^2\Sigma^+$	152.14	0.27	0.02680587	0.00006634	0.00333	3.08476
$^{138}Ba^{16}O$	$^1\Sigma^+$	669.76	2.03	0.3126140	0.0013921	0.2724	1.93969
$^{138}Ba^{32}S$	$^1\Sigma^+$	379.42	0.88	0.10331	0.0003188	0.0306	2.5074
$^{9}Be^{19}F$	$^2\Sigma^+$	1247.36	9.12	1.4889	0.0176	8.28	1.3610
$^{9}Be^{1}H$	$^2\Sigma^+$	2060.78	36.31	10.3164	0.3030	1022.1	1.3426
$^{9}Be^{2}H$	$^2\Sigma^+$	1530.32	20.71	5.6872	0.1225	313.8	1.3419
$^{9}Be^{16}O$	$^1\Sigma^+$	1487.32	11.83	1.6510	0.0190	8.20	1.3309
$^{9}Be^{32}S$	$^1\Sigma^+$	997.94	6.14	0.79059	0.00664	2.00	1.7415
$^{209}Bi_2$	$^1\Sigma_g^+$	172.71	0.34	0.022781	0.000055	0.00150	2.6596
$^{209}Bi^{1}H$	$^3\Sigma^-$	1635.73	31.6	5.137	0.148	183	1.805
$^{209}Bi^{2}H$	$^3\Sigma^-$	1173.32	16.1	2.592	0.054	50.6	1.804
$^{79}Br_2$	$^1\Sigma_g^+$	325.32	1.08	0.082107	0.0003187	0.02092	2.2811
$^{79}Br^{35}Cl$	$^1\Sigma^+$	444.28	1.84	0.152470	0.000770	0.07183	2.13607
$^{79}Br^{19}F$	$^1\Sigma^+$	670.75	4.05	0.35584	0.00261	0.401	1.75894
$^{79}Br^{16}O$	$^2\Pi_{3/2}$	779	6.8	0.429598	0.003639	0.523	1.717
$^{12}C_2$	$^1\Sigma_g^+$	1854.71	13.34	1.8198	0.0177	6.92	1.2425
$^{12}C^{35}Cl$	$^2\Pi_{1/2}$	866.72*	6.2	0.6936	0.00672	1.9	1.6450
$^{12}C^{19}F$	$^2\Pi_{1/2}$	1308.1	11.10	1.4172	0.0184	6.5	1.2718
$^{12}C^{1}H$	$^2\Pi_{1/2}$	2858.5	63.0	14.457	0.534	1450	1.1199
$^{12}C^{2}H$	$^2\Pi_{1/2}$	2099.8	34.02	7.806	0.208	420	1.1190
$^{12}C^{14}N$	$^2\Sigma^+$	2068.59	13.09	1.8997830	0.0173717	6.4034	1.17181
$^{12}C^{16}O$	$^1\Sigma^+$	2169.81	13.29	1.93128075	0.01750390	6.1216	1.12823
$^{12}C^{31}P$	$^2\Sigma^+$	1239.67	6.86	0.7986	0.00597	1.33	1.562
$^{12}C^{32}S$	$^1\Sigma^+$	1285.15	6.50	0.8200434	0.0059182	1.336	1.53482
$^{12}C^{80}Se$	$^1\Sigma^+$	1035.36	4.86	0.5750	0.00379	0.71	1.67609
$^{40}Ca^{35}Cl$	$^2\Sigma^+$	367.53	1.31	0.1522302	0.0007990	0.1029	2.43676
$^{40}Ca^{19}F$	$^2\Sigma^+$	581.1	2.74	0.339	0.0026	0.45	1.967
$^{40}Ca^{1}H$	$^2\Sigma^+$	1298.34	19.10	4.2766	0.0970	183.7	2.0025
$^{40}Ca^{2}H$	$^2\Sigma^+$	910*		2.1769	0.035	47.9	2.002
$^{40}Ca^{127}I$	$^2\Sigma^+$	238.70	0.63	0.0693263	0.0002634	0.0234	2.82859
$^{40}Ca^{16}O$	$^1\Sigma^+$	732.03	4.83	0.444441	0.003282	0.6541	1.8221
$^{40}Ca^{32}S$	$^1\Sigma^+$	462.23	1.78	0.1766757	0.0008270	0.1032	2.31775
$^{114}Cd^{1}H$	$^2\Sigma^+$	1337.1*		5.323		314	1.781
$^{114}Cd^{2}H$	$^2\Sigma^+$			2.704		76	1.775
$^{35}Cl_2$	$^1\Sigma_g^+$	559.7	2.68	0.2440	0.0015	0.186	1.988
$^{35}Cl^{19}F$	$^1\Sigma^+$	786.15	6.16	0.516479	0.004358	0.88	1.62831
$^{35}Cl^{16}O$	$^2\Pi_{3/2}$	853.8	5.5	0.62345	0.0058	1.33	1.56963
$^{52}Cr^{1}H$	$^6\Sigma^+$	1581*	32	6.220	0.179	347	1.656
$^{52}Cr^{2}H$	$^6\Sigma^+$	1182*		3.14		88.8	1.664
$^{52}Cr^{16}O$	$^5\Pi$	898.4	6.8	0.5231	0.0070		1.615
$^{133}Cs_2$	$^1\Sigma_g^+$	42.02	0.08	0.0127	0.0000264	0.00464	4.47
$^{133}Cs^{79}Br$	$^1\Sigma^+$	149.66	0.37	0.03606925	0.00012401	0.00838	3.07225
$^{133}Cs^{35}Cl$	$^1\Sigma^+$	214.17	0.73	0.07209149	0.00033756	0.03268	2.90627
$^{133}Cs^{19}F$	$^1\Sigma^+$	352.56	1.62	0.18436969	0.0011756	0.20168	1.34535
$^{133}Cs^{1}H$	$^1\Sigma^+$	891.0	12.9	2.7099	0.0579	113	2.4938
$^{133}Cs^{2}H$	$^1\Sigma^+$	619.1*		1.354		20	2.505
$^{133}Cs^{127}I$	$^1\Sigma^+$	119.18	0.25	0.02362736	0.00006826	0.00371	3.31519
$^{133}Cs^{16}O$	$^2\Sigma^+$	357.5*		0.223073	0.001303	0.348	2.3007
$^{63}Cu_2$	$^1\Sigma_g^+$	264.55	1.02	0.10874	0.000614	0.0716	2.2197
$^{63}Cu^{79}Br$	$^1\Sigma^+$	314.8	0.96	0.10192625	0.00045214	0.04274	2.17344
$^{65}Cu^{35}Cl$	$^1\Sigma^+$	415.29	1.58	0.17628802	0.00099647	0.12706	2.05118
$^{63}Cu^{19}F$	$^1\Sigma^+$	622.7	3.95	0.3794029	0.0032298	0.563	1.74493
$^{63}Cu^{1}H$	$^1\Sigma^+$	1941.26	37.51	7.9441	0.2563	520	1.46263
$^{63}Cu^{2}H$	$^1\Sigma^+$	1384.14	18.97	4.0381	0.0917	136.2	1.4626

Molecule	State	ω_e cm^{-1}	$\omega_e x_e$ cm^{-1}	B_e cm^{-1}	α_e cm^{-1}	D_e 10^{-6}cm^{-1}	r_e Å
$^{63}Cu^{127}I$	$^1\Sigma^+$	264.5	0.60	0.07328742	0.00028390	0.02244	2.33832
$^{63}Cu^{16}O$	$^2\Pi_{3/2}$	640.17	4.43	0.44454	0.00456	0.85	1.7244
$^{63}Cu^{32}S$	$^2\Pi_{3/2}$	415.0	1.75	0.1891		0.18	2.051
$^{19}F_2$	$^1\Sigma_g^+$	916.64	11.24	0.89019	0.013847	3.3	1.41193
$^{56}Fe^{16}O$	$^5\Delta$	965*		0.650		0.72	1.444
$^{69}Ga^{81}Br$	$^1\Sigma^+$	263.0	0.81	0.081839	0.0003207	0.032	2.35248
$^{69}Ga^{35}Cl$	$^1\Sigma^+$	365.67	1.25	0.1499046	0.0007936	0.1008	2.20169
$^{69}Ga^{19}F$	$^1\Sigma^+$	622.2	3.2	0.3595161	0.0028642	0.50	1.77437
$^{69}Ga^{1}H$	$^1\Sigma^+$	1604.52	28.77	6.137	0.181	342	1.663
$^{69}Ga^{2}H$	$^1\Sigma^+$			3.083	0.06	84	1.663
$^{69}Ga^{127}I$	$^1\Sigma^+$	216.38	0.47	0.0569359	0.0001897	0.015770	2.57464
$^{69}Ga^{16}O$	$^2\Sigma$	767.5	6.24	0.4271		0.37	1.744
$^{74}Ge^{79}Br$	$^2\Pi_{1/2}$	295	0.7				
$^{74}Ge^{35}Cl$	$^2\Pi_{1/2}$	407.6	1.36				
$^{72}Ge^{1}H$	$^2\Pi_{1/2}$	1833.77	37	6.726	0.192	326	1.5880
$^{72}Ge^{2}H$	$^2\Pi_{1/2}$	1320.09	19	3.415	0.070	83.2	1.5874
$^{74}Ge^{16}O$	$^1\Sigma^+$	986.49	4.47	0.4856981	0.0030787	0.4709	1.62464
$^{74}Ge^{32}S$	$^1\Sigma^+$	575.8	1.80	0.18656576	0.00074910	0.07883	2.01209
$^{74}Ge^{80}Se$	$^1\Sigma^+$	408.7	1.36	0.09634051	0.00028904	0.02207	2.13463
$^{74}Ge^{130}Te$	$^1\Sigma^+$	323.9	0.75	0.06533821	0.00017246	0.012	2.34017
$^{1}H_2$	$^1\Sigma_g^+$	4401.21	121.34	60.853	3.062	47100	0.74144
$^{2}H_2$	$^1\Sigma_g^+$	3115.50	61.82	30.444	1.0786	11410	0.74152
$^{3}H_2$	$^1\Sigma_g^+$	2546.5	41.23	20.335	0.5887		0.74142
$^{1}H^{81}Br$	$^1\Sigma^+$	2648.97	45.22	8.46488	0.23328	345.8	1.41444
$^{2}H^{81}Br$	$^1\Sigma^+$	1884.75	22.72	4.245596	0.084	88.32	1.4145
$^{1}H^{35}Cl$	$^1\Sigma^+$	2990.95	52.82	10.59342	0.30718	531.94	1.27455
$^{2}H^{35}Cl$	$^1\Sigma^+$	2145.16	27.18	5.448796	0.113292	140	1.27458
$^{1}H^{19}F$	$^1\Sigma^+$	4138.32	89.88	20.9557	0.798	2151	0.91681
$^{2}H^{19}F$	$^1\Sigma^+$	2998.19	45.76	11.0102	0.3017	594	0.91694
$^{1}H^{127}I$	$^1\Sigma^+$	2309.01	39.64	6.4263650	0.1689	206.9	1.60916
$^{202}Hg^{1}H$	$^2\Sigma^+$	1203.24*		5.3888		395.3	1.7662
$^{202}Hg^{2}H$	$^2\Sigma^+$	896.12*		2.739		91	1.757
$^{127}I_2$	$^1\Sigma_g^+$	214.50	0.61	0.03737	0.000114	0.0043	2.666
$^{127}I^{79}Br$	$^1\Sigma^+$	268.64	0.81	0.0568325	0.0001969	0.0102	2.46899
$^{127}I^{35}Cl$	$^1\Sigma^+$	384.29	1.50	0.1141587	0.0005354	0.0403	2.32088
$^{127}I^{19}F$	$^1\Sigma^+$	610.24	3.12	0.2797111	0.0018738	0.2356	1.90976
$^{127}I^{16}O$	$^2\Pi_{3/2}$	681.5	4.3	0.34026	0.00270	0.36	1.8676
$^{115}In^{81}Br$	$^1\Sigma^+$	221.0	0.65	0.05489468	0.00018672	0.01350	2.54315
$^{115}In^{35}Cl$	$^1\Sigma^+$	317.39	1.03	0.1090583	0.0005177	0.0515	2.40117
$^{115}In^{19}F$	$^1\Sigma^+$	535.4	2.6	0.2623241	0.0018798	0.252	1.98540
$^{115}In^{1}H$	$^1\Sigma^+$	1476.0	25.61	4.995	0.143	223	1.8380
$^{115}In^{2}H$	$^1\Sigma^+$	1048.2	12.4	2.523	0.051	58	1.837
$^{115}In^{127}I$	$^1\Sigma^+$	177.08	0.34	0.03686702	0.00010411	0.00639	2.75364
$^{39}K_2$	$^1\Sigma_g^+$	92.02	0.28	0.056743	0.000165	0.0863	3.9051
$^{39}K^{79}Br$	$^1\Sigma^+$	213	0.80	0.08122109	0.00040481	0.04462	2.82078
$^{39}K^{35}Cl$	$^1\Sigma^+$	281	1.30	0.1286348	0.0007899	0.1087	2.66665
$^{39}K^{19}F$	$^1\Sigma^+$	426.26	2.45	0.27993741	0.00233492	0.4829	2.17146
$^{39}K^{1}H$	$^1\Sigma^+$	983.6	14.3	3.416400	0.085313	163.55	2.243
$^{39}K^{2}H$	$^1\Sigma^+$	707	7.7	1.754	0.0318	50	2.240
$^{39}K^{127}I$	$^1\Sigma^+$	186.53	0.57	0.06087473	0.00026776	0.02593	3.04784
$^{139}La^{16}O$	$^2\Sigma^+$	812.8	2.22	0.35252001	0.00142365	0.2626	1.82591
$^{7}Li_2$	$^1\Sigma_g^+$	351.43	2.61	0.67264	0.00704	9.87	2.6729
$^{7}Li^{79}Br$	$^1\Sigma^+$	563.2	3.5	0.555399	0.005644	2.159	2.17043
$^{7}Li^{35}Cl$	$^1\Sigma^+$	642.95	4.47	0.7065225	0.0080102	3.409	2.02067
$^{7}Li^{19}F$	$^1\Sigma^+$	910.57	8.21	1.3452583	0.0202887	11.745	1.56386
$^{7}Li^{1}H$	$^1\Sigma^+$	1405.65	23.20	7.51373	0.21665	862	1.59490
$^{7}Li^{2}H$	$^1\Sigma^+$	1054.80	12.94	4.23310	0.09155	276	1.5941
$^{7}Li^{127}I$	$^1\Sigma^+$	496.85	2.85	0.4431766	0.0040862	1.4104	2.39192
$^{7}Li^{16}O$	$^2\Pi$	814.62	7.78	1.212830	0.017899	0.1079	1.68822
$^{24}Mg_2$	$^1\Sigma_g^+$	51.12	1.64	0.09287	0.00378	1.22	3.891


Molecule	State	ω_e cm^{-1}	$\omega_e x_e$ cm^{-1}	B_e cm^{-1}	α_e cm^{-1}	D_e 10^{-6}cm^{-1}	r_e Å
$^{24}Mg^{35}Cl$	$^2\Sigma^+$	462.12*	2.1	0.2456154	0.0016204	0.2723	2.19639
$^{24}Mg^{19}F$	$^2\Sigma^+$	711.69*	4.9	0.51922	0.00470	1.080	1.7500
$^{24}Mg^{1}H$	$^2\Sigma^+$	1495.20	31.89	5.8257	0.1859	344	1.7297
$^{24}Mg^{2}H$	$^2\Sigma^+$	1077.9	16.1	3.0306	0.06289	92	1.7302
$^{24}Mg^{16}O$	$^1\Sigma^+$	784.78	5.26	0.57470436	0.00532377	1.2328	1.74838
$^{55}Mn^{1}H$	$^7\Sigma$	1548.0	28.8	5.6841	0.1570	303.9	1.7311
$^{55}Mn^{2}H$	$^7\Sigma$	1103	13.9	2.8957	0.051	79.5	1.7310
$^{14}N_2$	$^1\Sigma_g^+$	2358.57	14.32	1.99824	0.017318	5.76	1.09769
$^{14}N^{79}Br$	$^3\Sigma^-$	691.75	4.72	0.444	0.0040		1.79
$^{14}N^{35}Cl$	$^3\Sigma^-$	827.96	5.30	0.649770	0.006414	1.598	1.61071
$^{14}N^{19}F$	$^3\Sigma^-$	1141.37	8.99	1.2057	0.01492	5.39	1.3170
$^{14}N^{1}H$	$^3\Sigma^-$	3282.3	78.4	16.6993	0.6490	1709.7	1.0362
$^{14}N^{2}H$	$^3\Sigma^-$	2398	42	8.7913	0.2531	490.4	1.0361
$^{14}N^{16}O$	$^2\Pi_{1/2}$	1904.20	14.07	1.67195	0.0171	0.5	1.15077
$^{14}N^{32}S$	$^2\Pi_{1/2}$	1218.7	7.28	0.769602	0.0064	1.2	1.4940
$^{23}Na_2$	$^1\Sigma_g^+$	159.13	0.72	0.154707	0.008736	0.581	3.0789
$^{23}Na^{79}Br$	$^1\Sigma^+$	302	1.5	0.1512533	0.0009410	0.1554	2.50204
$^{23}Na^{35}Cl$	$^1\Sigma^+$	366	2.05	0.2180631	0.0016248	0.3120	2.36080
$^{23}Na^{19}F$	$^1\Sigma^+$	535.66	3.57	0.4369011	0.0045580	1.163	1.92595
$^{23}Na^{1}H$	$^1\Sigma^+$	1172.2	19.72	4.9033634	0.1370919	343.40	1.88654
$^{23}Na^{2}H$	$^1\Sigma^+$	826.1*		2.557089	0.051600	93.46	1.88654
$^{23}Na^{127}I$	$^1\Sigma^+$	258	1.1	0.1178056	0.0006478	0.0973	2.71145
$^{23}Na^{16}O$	$^2\Pi$	492.3		0.424630	0.004506	1.2638	2.05155
$^{93}Nb^{16}O$	$^4\Sigma^-$	989.0	3.8	0.4321	0.0021	0.22	1.691
$^{58}Ni^{1}H$	$^2\Delta_{5/2}$	1926.6	38	7.700	0.23	481	1.476
$^{58}Ni^{2}H$	$^2\Delta_{5/2}$	1390.1	19	3.992	0.092	130	1.465
$^{16}O_2$	$^3\Sigma_g^-$	1580.19	11.98	1.44563	0.0159	4.839	1.20752
$^{16}O^{1}H$	$^2\Pi_{3/2}$	3737.76	84.88	18.911	0.7242	1938	0.96966
$^{16}O^{2}H$	$^2\Pi_{3/2}$	2720.24	44.05	10.021	0.276	537.4	0.9698
$^{31}P_2$	$^1\Sigma_g^+$	780.77	2.84	0.30362	0.00149	0.188	1.8934
$^{31}P^{35}Cl$	$^3\Sigma^-$	551.38	2.23	0.2528748	0.0015119	0.2124	2.01461
$^{31}P^{19}F$	$^3\Sigma^-$	846.75	4.49	0.5665	0.00456		1.58938
$^{31}P^{1}H$	$^3\Sigma^-$	2365.2	44.5	8.5371	0.2514	436	1.42140
$^{31}P^{2}H$	$^3\Sigma^-$	1699.2	23.0	4.4081	0.0928	116	1.4220
$^{31}P^{14}N$	$^1\Sigma^+$	1337.24	6.98	0.7864854	0.0055364	1.091	1.49087
$^{31}P^{16}O$	$^2\Pi_{1/2}$	1233.34	6.56	0.7337	0.0055	1.3	1.4759
$^{208}Pb_2$		110.5	0.35				
$^{208}Pb^{79}Br$	$^2\Pi_{1/2}$	207.5	0.50				
$^{208}Pb^{35}Cl$	$^2\Pi_{1/2}$	303.9	0.88				
$^{208}Pb^{19}F$	$^2\Pi_{1/2}$	502.73	2.28	0.22875	0.001473	0.183	2.0575
$^{208}Pb^{1}H$	$^2\Pi_{1/2}$	1564.1	29.75	4.971	0.144	201	1.839
$^{208}Pb^{16}O$	$^1\Sigma^+$	720.96	3.52	0.30730373	0.00190977	0.2138	1.92181
$^{208}Pb^{32}S$	$^1\Sigma^+$	429.17	1.26	0.11632307	0.00043510	0.03418	2.28678
$^{208}Pb^{80}Se$	$^1\Sigma^+$	277.6	0.51	0.05059953	0.00012993	0.0070	2.40218
$^{208}Pb^{130}Te$	$^1\Sigma^+$	212.0	0.43	0.03130774	0.00006743	0.0027	2.59492
$^{195}Pt^{12}C$	$^1\Sigma^+$	1051.13	4.86	0.53044	0.003273	0.546	1.6767
$^{195}Pt^{1}H$	$^2\Delta_{5/2}$	2294.68*	46	7.1963	0.1996	261	1.52852
$^{195}Pt^{2}H$	$^2\Delta_{5/2}$	1644.3*	23	3.640	0.071	66	1.524
$^{85}Rb^{79}Br$	$^1\Sigma^+$	169.46	0.46	0.04752798	0.00018596	0.01496	2.94474
$^{85}Rb^{35}Cl$	$^1\Sigma^+$	228	0.92	0.0876404	0.0004537	0.04947	2.78673
$^{85}Rb^{19}F$	$^1\Sigma^+$	376	1.9	0.2106640	0.0015228	0.2684	2.27033
$^{85}Rb^{1}H$	$^1\Sigma^+$	936.9	14.21	3.020	0.072	123	2.367
$^{85}Rb^{127}I$	$^1\Sigma^+$	138.51	0.33	0.03283293	0.00010946	0.00738	3.17688
$^{85}Rb^{16}O$	$^2\Sigma^+$	388.4*		0.246481	0.002174	0.397	2.25420
$^{32}S_2$	$^3\Sigma_g^-$	725.65	2.84	0.2955	0.001570	0.19	1.8892
$^{32}S^{19}F$	$^2\Pi_{3/2}$			0.552174			1.60058
$^{32}S^{1}H$	$^2\Pi_{3/2}$	2711.6	59.9	9.5995	0.2785	480.6	1.34066
$^{32}S^{2}H$	$^2\Pi_{3/2}$	1885	31	4.95130	0.10308	130	1.34049
$^{32}S^{16}O$	$^3\Sigma^-$	1149.2	5.6	0.7208171	0.005737	1.134	1.48109
$^{121}Sb^{35}Cl$	$^3\Sigma^-$	374.7	0.6				

Molecule	State	ω_e cm^{-1}	$\omega_e x_e$ cm^{-1}	B_e cm^{-1}	α_e cm^{-1}	D_e 10^{-6}cm^{-1}	r_e Å
$^{121}Sb^{19}F$	$^3\Sigma^-$	605.0	2.6	0.2792	0.0020	0.23	1.918
$^{121}Sb^{1}H$	$^3\Sigma^-$			5.684		240	1.723
$^{121}Sb^{2}H$	$^3\Sigma^-$			2.8782		45	1.7194
$^{121}Sb^{14}N$	$^1\Sigma^+$	942.0	5.6				
$^{121}Sb^{16}O$	$^2\Pi_{1/2}$	816	4.2	0.3580	0.0022	0.270	1.826
$^{45}Sc^{19}F$	$^1\Sigma^+$	735.6	3.8	0.3950	0.00266		1.788
$^{80}Se_2$	$^3\Sigma_g^-$	385.30	0.96	0.08992	0.000288	0.024	2.166
$^{80}Se^{1}H$	$^2\Pi_{3/2}$	2400*		8.02	0.23	330	1.48
$^{80}Se^{2}H$	$^2\Pi_{3/2}$	1708*		3.94			1.48
$^{80}Se^{16}O$	$^3\Sigma^-$	914.69	4.52	0.4655	0.00323	0.5	1.648
$^{28}Si_2$	$^3\Sigma_g^-$	510.98	2.02	0.2390	0.0014	0.21	2.246
$^{28}Si^{35}Cl$	$^2\Pi_{1/2}$	535.60	2.17	0.2561	0.0016	0.25	2.058
$^{28}Si^{19}F$	$^2\Pi_{1/2}$	857.19	4.73	0.5812	0.00494	1.07	1.6011
$^{28}Si^{1}H$	$^2\Pi_{1/2}$	2041.80	35.51	7.4996	0.2190	397	1.5201
$^{28}Si^{2}H$	$^2\Pi_{1/2}$	1469.32	18.23	3.8840	0.0781	105.4	1.5199
$^{28}Si^{14}N$	$^2\Sigma^+$	1151.4	6.47	0.7311	0.00565	1.2	1.572
$^{28}Si^{16}O$	$^1\Sigma^+$	1241.54	5.97	0.7267521	0.0050379	0.9923	1.50975
$^{28}Si^{32}S$	$^1\Sigma^+$	749.64	2.58	0.30352788	0.00147308	0.201	1.92926
$^{28}Si^{80}Se$	$^1\Sigma^+$	580.0	1.78	0.1920117	0.0007767	0.0842	2.05832
$^{120}Sn^{79}Br$	$^2\Pi_{1/2}$	247.2	0.6				
$^{120}Sn^{35}Cl$	$^2\Pi_{1/2}$	351.1	1.06	0.1117	0.0004		2.361
$^{118}Sn^{19}F$	$^2\Pi_{1/2}$	577.6	2.69	0.2727	0.0014	0.26	1.944
$^{120}Sn^{1}H$	$^2\Pi_{1/2}$			5.31488		207.5	1.78146
$^{120}Sn^{2}H$	$^2\Pi_{1/2}$	1188.0*		2.6950	0.049	53.4	1.7770
$^{120}Sn^{127}I$	$^2\Pi_{1/2}$	199.0	0.6				
$^{120}Sn^{16}O$	$^1\Sigma^+$	822.13	3.72	0.35571998	0.00214432	0.26638	1.83251
$^{120}Sn^{32}S$	$^1\Sigma^+$	487.26	1.36	0.13686139	0.00050563	0.0424	2.20898
$^{120}Sn^{80}Se$	$^1\Sigma^+$	331.2	0.74	0.0649978	0.0001705	0.011	2.32557
$^{120}Sn^{130}Te$	$^1\Sigma^+$	259.5	0.50	0.04247917	0.00009543	0.0055	2.52280
$^{88}Sr^{79}Br$	$^2\Sigma^+$	216.60	0.52	0.0541847	0.0001827	0.01356	2.73522
$^{88}Sr^{35}Cl$	$^2\Sigma^+$	302.3	0.95				
$^{88}Sr^{19}F$	$^2\Sigma^+$	502.4	2.3	0.2505346	0.0015513	0.2498	2.07537
$^{88}Sr^{1}H$	$^2\Sigma^+$	1206.2	17.0	3.6751	0.0814	135	2.1456
$^{88}Sr^{2}H$	$^2\Sigma^+$	841	8.6	1.8609	0.0292	34.7	2.1449
$^{88}Sr^{127}I$	$^2\Sigma^+$	173.77	0.35	0.0367097	0.0001060	0.00655	2.94364
$^{88}Sr^{16}O$	$^1\Sigma^+$	653.5	3.96	0.33798	0.00219	0.36	1.91983
$^{181}Ta^{16}O$	$^2\Delta_{3/2}$	1028.69	3.51	0.40284	0.00182	0.2450	1.68746
$^{130}Te_2$	$^3\Sigma_g^-$	247.07	0.51	0.039681	0.000106	0.0044	2.5574
$^{130}Te^{1}H$	$^2\Pi_{3/2}$			5.56			1.74
$^{130}Te^{16}O$	0^+	797.11	4.00	0.3554	0.00237	0.27	1.825
$^{232}Th^{16}O$	$^1\Sigma^+$	895.77	2.39	0.332644	0.001302	0.1833	1.84032
$^{48}Ti^{16}O$	$^3\Delta_1$	1009.02	4.50	0.53541	0.00301	0.603	1.6202
$^{205}Tl^{81}Br$	$^1\Sigma^+$	192.10	0.39	0.0423899	0.0001276	0.0083	1.61817
$^{205}Tl^{35}Cl$	$^1\Sigma^+$	284.71	0.86	0.09139702	0.00039784	0.0377	2.48483
$^{205}Tl^{19}F$	$^1\Sigma^+$	476.86	2.24	0.22315014	0.00150380	0.1955	2.08439
$^{205}Tl^{1}H$	$^1\Sigma^+$	1390.7	22.7	4.806	0.154	254	1.870
$^{205}Tl^{2}H$	$^1\Sigma^+$	987.7	12.04	2.419	0.057	60	1.869
$^{205}Tl^{127}I$	$^1\Sigma^+$	150*		0.0271676	0.0000664	0.0036	2.81361
$^{51}V^{16}O$	$^4\Sigma^-$	1011.3	4.86	0.54825	0.00352	0.6	1.5893
$^{89}Y^{35}Cl$	$^1\Sigma$	380.7	1.3	0.1160	0.0003	0.09	2.41
$^{89}Y^{19}F$	$^1\Sigma^+$	631.29	2.50	0.29042	0.00163	0.237	1.9257
$^{89}Y^{16}O$	$^2\Sigma^+$	861.0	2.9	0.3881	0.0018	0.32	1.790
$^{174}Yb^{1}H$	$^2\Sigma^+$	1249.54	21.06	3.9931	0.0957	161.8	2.0526
$^{174}Yb^{2}H$	$^2\Sigma^+$	886.6	10.57	2.01162	0.03425	41.60	2.0516
$^{64}Zn^{35}Cl$	$^2\Sigma$	390.5	1.6				
$^{64}Zn^{19}F$	$^2\Sigma$	628	3.5				
$^{64}Zn^{1}H$	$^2\Sigma^+$	1607.6	55.14	6.6794	0.2500	466	1.5949
$^{64}Zn^{2}H$	$^2\Sigma^+$	1072	28	3.350		124	1.6054
$^{64}Zn^{127}I$	$^2\Sigma$	223.4	0.6				
$^{90}Zr^{16}O$	$^1\Sigma^+$	969.8	4.9	0.42263	0.0023	0.319	1.7116


INFRARED CORRELATION CHARTS




INFRARED CORRELATION CHARTS




INFRARED CORRELATION CHARTS



Far Infrared Region




MICROMETERS
12.5
16.7
25
50
100
300
Phosphorus-organo (RO)3P
(RO)2POH
(RO)2POR
(RO)3PO
(RO)2(PS)SM
(RO)2PSR
(RO)3PS
alkyl
ϕ
Sulfur-organo R-S-S-R
CH3-S-
R-CH2S-
RRCH-S-
RRRC-S-
R-S-(C=O)-S-R
R-S-(C=O)-S-ϕ
ϕ-S-(C=O)-S-ϕ
Cl-(C=O)-S-ϕ
Cl-(C=O)-S-R
Silicon-organo, SiH2
SiH3
SiCl
SiO
SiS
SiP
SiSi
alkyl-Si
phenyl-Si
Metal-organo, phenyl-Ge
phenyl-Sn
phenyl-Pb
alkyl-Ge
alkyl-Sn
alkyl-Pb
Ferrocene, etc.
Phthalocyanines
Acetylacetonates
Oxalato-
Inorganics cyanides
carbonyls
azides
PCl2
PBr2
PI2
metal Cl2
metal Br2
metal I2
metal F6
-SF5
SO4
ClO4
PO4
SeO4
CrO4
MnO4
RuO4
OsO4
MoO4
WO4
BO3
ClO3
BrO3
IO3
SO3
TiO3
NbO3
Fe2O4
Mn2O4
S2O3
Cr2O7
SCN
WAVENUMBER (CM-1)
800
600
400
200
100
33.

NUCLEAR SPINS, MOMENTS, AND OTHER DATA RELATED TO NMR SPECTROSCOPY

This table presents the following data relevant to nuclear magnetic resonance spectroscopy:

Z: Atomic number

Isotope: Element symbol and mass number

Abundance: Natural abundance of the isotope in percent. An * indicates a radioactive nuclide; if no value is given, the nuclide is not present in nature or its abundance is highly variable.

I: Nuclear spin

ν: Resonant frequency in megahertz for an applied field H_0 of 1 tesla (in cgs units, 10 kilogauss)

Relative sensitivity: Sensitivity relative to ^{1}H (=1) assuming an equal number of nuclei and constant temperature. Values were calculated from the expressions:

For constant H_0: $0.0076508(\mu/\mu_N)^3(I + 1)/I^2$
For constant ν: $0.23871(\mu/\mu_N)(I + 1)$

μ/μ_N: Nuclear magnetic moment in units of the nuclear magneton μ_N

Q: Nuclear quadrupole moment in units of femtometers squared (1 fm^2 = 10^{-2} barn)

The table includes all stable nuclides of non-zero spin for which spin and magnetic moment values have been measured, as well as selected radioactive nuclides of current or potential interest. At least one isotope is included for each element through Z = 95 for which data are available. See Reference 1 for a complete listing of spins and moments.

The assistance of P. Pyykko in providing data on nuclear quadrupole moments is gratefully acknowledged.

References

1. Holden, N. E., "Table of the Isotopes", in Lide, D. R., Ed., *CRC Handbook of Chemistry and Physics*, 86th Ed., CRC Press, Boca Raton, FL, 2005.
2. Raghavan, P., *At. Data Nuc. Data Tables*, 42, 189, 1989.
3. Pyykko, P., *Mol. Phys.*, 19, 1617–1629, 2001.
4. Stone, N. J., <www.nndc.bnl.gov/nndc/stone_moments/>

		Abundance		ν/MHz	Relative sensitivity			
Z	**Isotope**	**%**	***I***	**for H_0 = 1 T**	**Const. H_0**	**Const. ν**	**μ/μ_N**	***Q*/fm²**
1	^{1}n	*	1/2	29.1647	0.32139	0.6850	−1.91304272	
1	^{1}H	99.9850	1/2	42.5775	1.00000	1.0000	+2.792847337	
1	^{2}H	0.0115	1	6.5359	0.00965	0.4093	+0.857438228	+0.2860
1	^{3}H	*	1/2	45.4148	1.21354	1.0666	+2.9789625	
2	^{3}He	0.000137	1/2	32.4360	0.44212	0.7618	−2.1276248	
3	^{6}Li	7.59	1	6.2661	0.00850	0.3925	+0.8220467	−0.0808
3	^{7}Li	92.41	3/2	16.5483	0.29356	1.9433	+3.25644	−4.01
4	^{9}Be	100	3/2	5.9842	0.01388	0.7027	−1.1776	+5.288
5	^{10}B	19.9	3	4.5752	0.01985	1.7193	+1.800645	+8.459
5	^{11}B	80.1	3/2	13.6630	0.16522	1.6045	+2.688649	+4.059
6	^{13}C	1.07	1/2	10.7084	0.01591	0.2515	+0.7024118	
7	^{14}N	99.632	1	3.0777	0.00101	0.1928	+0.4037610	+2.044
7	^{15}N	0.368	1/2	4.3173	0.00104	0.1014	−0.2831888	
8	^{17}O	0.038	5/2	5.7742	0.02910	1.5822	−1.89379	−2.558
9	^{19}F	100	1/2	40.0776	0.83400	0.9413	+2.628868	
10	^{21}Ne	0.27	3/2	3.3631	0.00246	0.3949	−0.661797	+10.155
11	^{23}Na	100	3/2	11.2688	0.09270	1.3233	+2.217522	+10.4
12	^{25}Mg	10.00	5/2	2.6083	0.00268	0.7147	−0.85545	+19.94
13	^{27}Al	100	5/2	11.1031	0.20689	3.0424	+3.641507	+14.66
14	^{29}Si	4.6832	1/2	8.4655	0.00786	0.1988	−0.55529	
15	^{31}P	100	1/2	17.2515	0.06652	0.4052	+1.13160	
16	^{33}S	0.76	3/2	3.2717	0.00227	0.3842	+0.6438212	−6.78
17	^{35}Cl	75.78	3/2	4.1765	0.00472	0.4905	+0.8218743	−8.165
17	^{37}Cl	24.22	3/2	3.4765	0.00272	0.4083	+0.6841236	−6.435
18	^{37}Ar	*	3/2	5.819	0.01276	0.6833	+1.145	
18	^{39}Ar	*	7/2	3.46	0.01130	1.7079	−1.59	
19	^{39}K	93.2581	3/2	1.9893	0.00051	0.2336	+0.3914662	+5.85
19	^{40}K	0.0117	4	2.4737	0.00523	1.5493	−1.298100	−7.3
19	^{41}K	6.7302	3/2	1.0919	0.00008	0.1282	+0.2148701	+7.11
20	^{43}Ca	0.135	7/2	2.8688	0.00642	1.4150	−1.31726	−4.08
21	^{45}Sc	100	7/2	10.3591	0.30244	5.1093	+4.756487	−22.0
22	^{47}Ti	7.44	5/2	2.4041	0.00210	0.6587	−0.78848	+30.2
22	^{49}Ti	5.41	7/2	2.4048	0.00378	1.1861	−1.10417	+24.7
23	^{50}V	0.250	6	4.2505	0.05571	5.5904	+3.345689	+21
23	^{51}V	99.750	7/2	11.2133	0.38360	5.5306	+5.1487057	−5.2
24	^{53}Cr	9.501	3/2	2.4115	0.00091	0.2832	−0.47454	−15

		Abundance		ν/MHz	Relative sensitivity			
Z	Isotope	%	*I*	for H_0 = 1 T	Const. H_0	Const. ν	μ/μ$_N$	*Q*/fm²
25	^{55}Mn	100	5/2	10.5763	0.17881	2.8980	+3.46872	+33
26	^{57}Fe	2.119	1/2	1.3816	0.00003	0.0324	+0.0906230	
27	^{59}Co	100	7/2	10.077	0.27841	4.9702	+4.627	+42
28	^{61}Ni	1.1399	3/2	3.8114	0.00359	0.4476	−0.75002	+16.2
29	^{63}Cu	69.17	3/2	11.2982	0.09342	1.3268	+2.22329	−22.0
29	^{65}Cu	30.83	3/2	12.1030	0.11484	1.4213	+2.38167	−20.4
30	^{67}Zn	4.10	5/2	2.6694	0.00287	0.7314	+0.875479	+15.0
31	^{69}Ga	60.108	3/2	10.2478	0.06971	1.2034	+2.01659	+17.1
31	^{71}Ga	39.892	3/2	13.0208	0.14300	1.5291	+2.56227	+10.7
32	^{73}Ge	7.73	9/2	1.4897	0.00141	1.1546	−0.8794677	−19.6
33	^{75}As	100	3/2	7.3150	0.02536	0.8590	+1.439475	+31.4
34	^{77}Se	7.63	1/2	8.1571	0.00703	0.1916	+0.53506	
35	^{79}Br	50.69	3/2	10.7042	0.07945	1.2570	+2.106400	+31.3
35	^{81}Br	49.31	3/2	11.5384	0.09951	1.3550	+2.270562	+26.2
36	^{83}Kr	11.49	9/2	1.6442	0.00190	1.2744	−0.970669	+25.9
37	^{85}Rb	72.17	5/2	4.1254	0.01061	1.1304	+1.35303	+27.6
37	^{87}Rb	27.83	3/2	13.9811	0.17703	1.6418	+2.75124	+13.35
38	^{87}Sr	7.00	9/2	1.8525	0.00272	1.4358	−1.093603	+33.5
39	^{89}Y	100	1/2	2.0949	0.00012	0.0492	−0.1374154	
40	^{91}Zr	11.22	5/2	3.9748	0.00949	1.0891	−1.30362	−17.6
41	^{93}Nb	100	9/2	10.4523	0.48821	8.1011	+6.1705	−32
42	^{95}Mo	15.92	5/2	2.7874	0.00327	0.7638	−0.9142	−2.2
42	^{97}Mo	9.55	5/2	2.8463	0.00349	0.7799	−0.9335	+25.5
43	^{99}Tc	*	9/2	9.6294	0.38174	7.4633	+5.6847	−12.9
44	^{99}Ru	12.76	5/2	1.9553	0.00113	0.5358	−0.6413	+7.9
44	^{101}Ru	17.06	5/2	2.1916	0.00159	0.6005	−0.7188	+45.7
45	^{103}Rh	100	1/2	1.3477	0.00003	0.0317	−0.08840	
46	^{105}Pd	22.33	5/2	1.957	0.00113	0.5364	−0.642	+66.0
47	^{107}Ag	51.839	1/2	1.7331	0.00007	0.0407	−0.1136796	
47	^{109}Ag	48.161	1/2	1.9924	0.00010	0.0468	−0.1306906	
48	^{111}Cd	12.80	1/2	9.0692	0.00966	0.2130	−0.5948861	
48	^{113}Cd	12.22	1/2	9.4871	0.01106	0.2228	−0.6223009	
49	^{113}In	4.29	9/2	9.3655	0.35121	7.2588	+5.5289	+79.9
49	^{115}In	95.71	9/2	9.3856	0.35348	7.2744	+5.5408	+81
50	^{115}Sn	0.34	1/2	14.0077	0.03561	0.3290	−0.91883	
50	^{117}Sn	7.68	1/2	15.2610	0.04605	0.3584	−1.00104	
50	^{119}Sn	8.59	1/2	15.9660	0.05273	0.3750	−1.04728	
51	^{121}Sb	57.21	5/2	10.2551	0.16302	2.8100	+3.3634	−36
51	^{123}Sb	42.79	7/2	5.5532	0.04659	2.7389	+2.5498	−49
52	^{123}Te	0.89	1/2	11.2349	0.01837	0.2639	−0.7369478	
52	^{125}Te	7.07	1/2	13.5454	0.03220	0.3181	−0.8885051	
53	^{127}I	100	5/2	8.5778	0.09540	2.3504	+2.813273	−71.0
54	^{129}Xe	26.44	1/2	11.8604	0.02162	0.2786	−0.7779763	
54	^{131}Xe	21.18	3/2	3.5159	0.00282	0.4129	+0.6918619	−11.4
55	^{133}Cs	100	7/2	5.6234	0.04838	2.7735	+2.582025	−0.343
56	^{135}Ba	6.592	3/2	4.2582	0.00500	0.5001	+0.837943	+16.0
56	^{137}Ba	11.232	3/2	4.7634	0.00700	0.5594	+0.937365	+24.5
57	^{138}La	0.090	5	5.6615	0.09404	5.3188	+3.713646	+45
57	^{139}La	99.910	7/2	6.0612	0.06058	2.9895	+2.7830455	+20
58	^{137}Ce	*	3/2	4.88	0.00752	0.5729	0.96	
58	^{139}Ce	*	3/2	5.39	0.01012	0.6326	1.06	
58	^{141}Ce	*	7/2	2.37	0.00364	1.1708	1.09	
59	^{141}Pr	100	5/2	13.0359	0.33483	3.5720	+4.2754	−5.9
60	^{143}Nd	12.2	7/2	2.319	0.00339	1.1440	−1.065	−63
60	^{145}Nd	8.3	7/2	1.429	0.00079	0.7047	−0.656	−33
61	^{143}Pm	*	5/2	11.59	0.23510	3.1748	+3.80	
61	^{147}Pm	*	7/2	5.62	0.04827	2.7714	+2.58	+74
62	^{147}Sm	14.99	7/2	1.7748	0.00152	0.8753	−0.8149	−26
62	^{149}Sm	13.82	7/2	1.4631	0.00085	0.7216	−0.6718	+7.4
63	^{151}Eu	47.81	5/2	10.5856	0.17929	2.9006	+3.4718	+90.3


		Abundance		ν/MHz	Relative sensitivity			
Z	Isotope	%	*I*	for H_0 = 1 T	Const. H_0	Const. ν	μ/μ$_N$	*Q*/fm²
63	^{153}Eu	52.19	5/2	4.6745	0.01544	1.2809	+1.5331	+241
64	^{155}Gd	14.80	3/2	1.312	0.00015	0.1541	−0.2582	+127
64	^{157}Gd	15.65	3/2	1.720	0.00033	0.2020	−0.3385	+135
65	^{159}Tb	100	3/2	10.23	0.06945	1.2019	+2.014	+143.2
66	^{161}Dy	18.91	5/2	1.4654	0.00048	0.4015	−0.4806	+250.7
66	^{163}Dy	24.90	5/2	2.0508	0.00130	0.5619	+0.6726	+265
67	^{165}Ho	100	7/2	9.0883	0.20423	4.4825	+4.173	+358
68	^{167}Er	22.93	7/2	1.2281	0.00050	0.6057	−0.5639	+356.5
69	^{169}Tm	100	1/2	3.531	0.00057	0.0829	−0.2316	
70	^{171}Yb	14.28	1/2	7.5261	0.00552	0.1768	+0.49367	
70	^{173}Yb	16.13	5/2	2.0730	0.00135	0.5680	−0.67989	+280
71	^{175}Lu	97.41	7/2	4.8626	0.03128	2.3983	+2.2327	+349
71	^{176}Lu	2.59	7	3.451	0.03975	6.0516	+3.169	+497
72	^{177}Hf	18.60	7/2	1.7282	0.00140	0.8524	+0.7935	+336.5
72	^{179}Hf	13.62	9/2	1.0856	0.00055	0.8414	−0.6409	+379.3
73	^{180}Ta	0.012	9	4.087	0.10610	11.5175	+4.825	
73	^{181}Ta	99.988	7/2	5.1627	0.03744	2.5463	+2.3705	+317
74	^{183}W	14.31	1/2	1.7957	0.00008	0.0422	+0.1177848	
75	^{185}Re	37.40	5/2	9.7176	0.13870	2.6627	+3.1871	+218
75	^{187}Re	62.60	5/2	9.8170	0.14300	2.6900	+3.2197	+207
76	^{187}Os	1.96	1/2	0.9856	0.00001	0.0231	+0.06465189	
76	^{189}Os	16.15	3/2	3.3536	0.00244	0.3938	+0.659933	+85.6
77	^{191}Ir	37.3	3/2	0.7658	0.00003	0.0899	+0.1507	+81.6
77	^{193}Ir	62.7	3/2	0.8319	0.00004	0.0977	+0.1637	+75.1
78	^{195}Pt	33.832	1/2	9.2922	0.01039	0.2182	+0.60952	
79	^{197}Au	100	3/2	0.7406	0.00003	0.0870	+0.145746	+54.7
80	^{199}Hg	16.87	1/2	7.7123	0.00594	0.1811	+0.5058855	
80	^{201}Hg	13.18	3/2	2.8469	0.00149	0.3343	−0.5602257	+38.6
81	^{203}Tl	29.524	1/2	24.7316	0.19598	0.5809	+1.6222579	
81	^{205}Tl	70.476	1/2	24.9749	0.20182	0.5866	+1.6382146	
82	^{207}Pb	22.1	1/2	9.0340	0.00955	0.2122	+0.59258	
83	^{209}Bi	100	9/2	6.9630	0.14433	5.3967	+4.1106	−51.6
84	^{209}Po	*	1/2	11.7	0.02096	0.2757	+0.77	
86	^{211}Rn	*	1/2	9.16	0.00997	0.2152	+0.601	
87	^{223}Fr	*	3/2	5.95	0.01362	0.6982	+1.17	+117
88	^{223}Ra	*	3/2	1.3746	0.00017	0.1614	+0.2705	+125
88	^{225}Ra	*	1/2	11.187	0.01814	0.2627	−0.7338	
89	^{227}Ac	*	3/2	5.6	0.01131	0.6564	+1.1	+170
90	^{229}Th	*	5/2	1.40	0.00042	0.3843	+0.46	+430
91	^{231}Pa	*100	3/2	10.2	0.06903	1.1995	2.01	−172
92	^{235}U	*0.7200	7/2	0.83	0.00015	0.4082	−0.38	+493.6
93	^{237}Np	*	5/2	9.57	0.13264	2.6234	+3.14	+388.6
94	^{239}Pu	*	1/2	3.09	0.00038	0.0727	+0.203	
95	^{243}Am	*	5/2	4.6	0.01446	1.2532	+1.5	+421

PROTON NMR CHEMICAL SHIFTS FOR CHARACTERISTIC ORGANIC STRUCTURES

The chart below summarizies the range of chemical shifts for protons in several classes or organic compounds and substituent groups. The chemical shifts δ are given in parts per million relative to tetramethylsilane.

Reference

Mohacsi, E., *J. Chem. Edu.*, 41, 38, 1964 (with permission)



^{13}C-NMR ABSORPTIONS OF MAJOR FUNCTIONAL GROUPS

The table below lists the range of ^{13}C chemical shifts δ in parts per million relative to tetramethylsilane, in descending order, for various functional groups. Examples of simple compounds for each family are given to illustrate the correlations. The shifts for the carbons of interest, which are italicized, are given in parentheses; when two or more values appear, they refer to the sequence of italicized carbon atoms from left to right in the formula.

References

1. Yoder, C. H. and Schaeffer, C. D., Jr., *Introduction to Multinuclear NMR: Theory and Application*, Benjamin/Cummings, Menlo Park, CA, 1987.
2. Silverstein, R. M., Bassler, G. C., and Morrill, T. C., *Spectrometric Identification of Organic Compounds*, John Wiley & Sons, New York, 1981.
3. Brown, D. W., A Short Set of ^{13}C NMR Correlation Tables, *J. Chem. Educ.*, 62, 209, 1985.

δ (ppm)	Group	Family	Example (δ of italicized carbon)	
220-165	>C=O	Ketones	$(CH_3)_2\mathit{C}O$	(206.0)
			$(CH_3)_2CH\mathit{C}OCH_3$	(212.1)
		Aldehydes	$CH_3\mathit{C}HO$	(199.7)
		α,β-Unsaturated carbonyls	$CH_3CH{=}CH\mathit{C}HO$	(192.4)
			$CH_2{=}CH\mathit{C}OCH_3$	(169.9)
		Carboxylic acids	$H\mathit{C}O_2H$	(166.0)
			$CH_3\mathit{C}O_2H$	(178.1)
		Amides	$H\mathit{C}ONH_2$	(165.0)
			$CH_3\mathit{C}ONH_2$	(172.7)
		Esters	$CH_3\mathit{C}O_2CH_2CH_3$	(170.3)
			$CH_2{=}CH\mathit{C}O_2CH_3$	(165.5)
140-120	>C=C<	Aromatic	C_6H_6	(128.5)
		Alkenes	$\mathit{C}H_2{=}CH_2$	(123.2)
			$\mathit{C}H_2{=}\mathit{C}HCH_3$	(115.9, 136.2)
			$\mathit{C}H_2{=}\mathit{C}HCH_2Cl$	(117.5, 133.7)
			$CH_3CH{=}\mathit{C}HCH_2CH_3$	(132.7)
125-115	-CN	Nitriles	$CH_3\text{-}\mathit{C}N$	(117.7)
80-70	-CC-	Alkynes	$H\mathit{C}\mathit{C}H$	(71.9)
			$CH_3\mathit{C}\mathit{C}CH_3$	(73.9)
70-45	-C-O	Esters	$\mathit{C}H_3OO\mathit{C}H_2CH_3$	(57.6, 67.9)
		Alcohols	$HO\mathit{C}H_3$	(49.0)
			$HO\mathit{C}H_2CH_3$	(57.0)
40-20	-C-NH_2	Amines	$\mathit{C}H_3NH_2$	(26.9)
			$CH_3\mathit{C}H_2NH_2$	(35.9)
30-15	-S-CH_3	Sulfides (thioethers)	$C_6H_5\text{-}S\text{-}\mathit{C}H_3$	15.6
30-(-2.3)	-C-H	Alkanes, cycloalkanes	$\mathit{C}H_4$	(-2.3)
			$\mathit{C}H_3CH_3$	(5.7)
			$\mathit{C}H_3\mathit{C}H_2CH_3$	(15.8, 16.3)
			$\mathit{C}H_3\mathit{C}H_2\mathit{C}H_2CH_3$	(13.4, 25.2)
			$\mathit{C}H_3\mathit{C}H_2\mathit{C}H_2\mathit{C}H_2CH_3$	(13.9, 22.8, 34.7)
		Cyclohexane		(26.9)

BOND LENGTHS IN ORGANOMETALLIC COMPOUNDS

This table summarizes the average values of interatomic distances of representative metal–ligand bonds. Sigma bonds between *d*- and *f*-block metals and the elements C, N, O, P, S, and As are included. The values are extracted from a much larger list in Reference 1. The tabulated values are the unweighted means of reported measurements on compounds in each category. If four or more measurements are available, the standard deviation is given in parentheses. All values are in Ångstrom units (10^{-10} m).

The first part of the table covers metal-carbon bonds in different ligand categories, while the second part covers metal bonds to other elements. R stands for any alkyl group; Me for a CH_3 group; C_6R_5 indicates an aryl group; and C(=O)R an acyl group. Metals are listed in atomic number order.

Reference

1. Orpen, A. G., Brammer, L., Allen, F.H., Kennard, O., Watson, D. G., and Taylor, R., *J. Chem. Soc. Dalton Trans.*, 1989, S1-S83.

M	M-CH_3	M-CH_2R	M-CR=CR_2	M-C_6R_5	M-C(=O)R
Ti		2.167	2.215(0.042)	2.148	
V				2.114(0.012)	
Cr	2.168		2.035(0.009)	2.075(0.019)	
Mn	2.095(0.030)	2.176(0.024)	2.007	2.064(0.021)	2.044
Fe	2.074	2.091(0.030)	1.991(0.039)	2.031(0.062)	1.997(0.033)
Co	2.014(0.023)	2.039(0.032)	1.934(0.019)	1.974	1.990
Ni	2.029	1.964	1.892(0.017)	1.917(0.038)	1.850(0.059)
Cu				2.020	
Zn		1.964			
Zr	2.292(0.049)		2.257		
Nb	2.336	1.319			
Mo	2.254(0.065)	2.250(0.061)	2.204(0.049)	2.193(0.054)	2.109
Ru	2.179(0.045)	2.036(0.010)	2.063	2.092(0.057)	2.091
Rh	2.092(0.027)	2.100	2.040(0.054)	2.011(0.026)	1.995(0.031)
Pd		2.028	2.000(0.024)	1.981(0.032)	1.982(0.029)
Hf	2.275(0.049)		2.205		
Ta	2.217(0.035)	2.225(0.056)		2.199(0.073)	
W	2.189(0.039)	2.175	2.224		
Re	2.173(0.051)	2.290		2.027	2.190(0.027)
Os		2.221	2.052	2.090(0.032)	2.161
Ir	2.175		2.071(0.044)	2.070(0.038)	2.019
Pt	2.083(0.045)	2.062(0.031)	2.024(0.037)	2.049(0.046)	1.991(0.025)
Au	2.066(0.045)		2.042	2.059(0.024)	
Hg	2.072(0.026)	2.125		2.086(0.040)	
Th	2.567				

M	M-NH_3	M-OH_2	M-PMe_3	M-SR	M-AsR_3
Ti		2.066(0.052)		2.369	2.686
V		2.129(0.131)	2.510(0.010)	2.378(0.007)	
Cr	2.069(0.008)	1.997(0.070)	2.389(0.069)	2.362	2.460(0.040)
Mn		2.189(0.040)	2.455(0.164)	2.366(0.054)	2.400(0.013)
Fe		2.085(0.066)	2.246(0.042)	2.271(0.028)	2.352(0.043)
Co	1.965(0.021)	2.085(0.064)	2.217(0.043)	2.254(0.025)	2.323(0.021)
Ni	2.074(0.093)	2.079(0.038)	2.204(0.031)	2.187(0.007)	2.333(0.035)
Cu	1.987(0.017)	2.186(0.215)			2.367(0.016)
Zn	2.044	2.090(0.061)		2.295	
Y		2.398(0.068)			
Zr			2.692		
Nb		2.248(0.137)			2.741(0.008)
Mo	2.217	2.201(0.094)	2.462(0.046)	2.401(0.050)	2.582(0.036)
Ru	2.126(0.024)	2.074(0.051)	2.307(0.050)		2.446(0.031)
Rh	2.114(0.018)	2.190(0.096)	2.266(0.036)		2.416(0.039)
Pd	2.032	2.200	2.287(0.018)		2.386(0.052)
Ag		2.350			
Cd		2.318(0.065)		2.444	
La		2.556(0.062)			
Ce		2.565(0.063)			
Pr		2.518(0.038)			
Nd		2.533(0.058)			
Sm		2.459(0.050)			
Eu		2.441(0.055)			
Gd		2.443(0.074)			
Tb		2.455			
Dy		2.409(0.074)			
Ho		2.407(0.069)			
Er		2.404(0.083)			
Yb		2.353(0.066)			
Lu		2.404(0.116)			
Ta			2.589(0.044)		
W		2.115(0.065)	2.485(0.039)		
Re	2.253	2.199(0.091)	2.369(0.065)		2.575(0.006)
Os	2.136	2.166	2.328(0.029)		
Ir	2.050(0.021)		2.323(0.028)	2.461	
Pt			2.295(0.036)	2.320(0.015)	2.366(0.058)
Au		2.157		2.293	
Hg		2.690(0.083)		2.402(0.065)	
Th		2.483(0.032)			
U		2.455(0.047)			

CHARACTERISTIC BOND LENGTHS IN FREE MOLECULES

This is a summary of typical bond lengths in gas-phase molecules. The value given for each bond is near the mid-range of values found in simple molecules. Bond lengths usually vary by 1 or 2%, and often by more, depending on the nature of the other bonds attached to the two atoms in question. References 1 and 2 give bond lengths in individual gas-phase molecules, as determined by spectroscopic and electron diffraction methods.

All bond distances are given in Å (1 Å = 10^{-10} m).

References

1. "Bond Lengths and Angles in Gas-Phase Molecules", *CRC Handbook of Chemistry and Physics*, 86th Edition, 2005, p. **9**-19.
2. Harmony, M. D., Laurie, V. W., Kuczkowski, R. L., Schwendeman, R. H., Ramsay, D. A., Lovas, F. J., Lafferty, W. J., and Maki, A. G., Molecular structure of gas-phase polyatomic molecules determined by spectroscopic methods, *J. Phys. Chem. Ref. Data* 8, 619, 1979.
3. Lide, D. R., "A survey of carbon-carbon bond lengths", *Tetrahedron* 17, 125, 1962.

A. Characteristic lengths of single bonds.

	As	**Br**	**C**	**Cl**	**F**	**Ge**	**H**	**I**	**N**	**O**	**P**	**S**	**Sb**	**Se**	**Si**
As	2.10														
Br	2.32	2.28													
C	1.96	1.94	1.53												
Cl	2.17	2.14	1.79	1.99											
F	1.71	1.76	1.39	1.63	1.41										
Ge		2.30	1.95	2.15	1.73	2.40									
H	1.51	1.41	1.09	1.28	0.92	1.53	0.74								
I		2.47	2.13	2.32	1.91	2.51	1.61	2.67							
N			1.46	1.90	1.37		1.02		1.45						
O			1.42	1.70	1.42		0.96		1.43	1.48					
P		2.22	1.85	2.04	1.57		1.42		1.65		2.25				
S		2.24	1.82	2.05	1.56		1.34					2.00			
Sb				2.33			1.70								
Se			1.95		1.71		1.47							2.33	
Si		2.21	1.87	2.05	1.58		1.48	2.44		1.63		2.14			2.33
Sn			2.14	2.28			1.71	2.67							
Te					1.82		1.66								

B. Lengths of multiple bonds (non-ring molecules).

C=C	1.34
C≡C	1.20
C=N	1.21
C≡N	1.16
C=O	1.21
C=S	1.61
N=N	1.24
N≡N	1.13
N=O	1.18
O=O	1.21

C. Effect of environment on carbon-carbon single bonds (other single bonds not shown). From Reference 3.

Configuration	**C–C length**	**Examples of molecules**
C–C	1.526	$H_3C–CH_3$
C–C=	1.501	$H_3C–CH=CH_2$
C–C≡	1.459	$H_3C–C≡CH$
=C–C=	1.467	$H_2C=CH–CH=CH_2$
≡C–C=	1.445	$HC≡C–CH=CH_2$
≡C–C≡	1.378	$HC≡C–C≡CH$

D. Some metal-carbon bond lengths in gas-phase molecules.

Al–C	1.96	Bi–C	2.26	Pb–C	2.24
B–C	1.58	Cd–C	2.11	Sn–C	2.14
Be–C	1.70	Hg–C	2.08	Zn–C	1.93

LINE SPECTRA OF THE ELEMENTS

Joseph Reader and Charles H. Corliss

The original tables from which this table was derived were prepared under the auspices of the Committee on Line Spectra of the Elements of the National Academy of Sciences-National Research Council. The table contains the outstanding spectral lines of neutral (I) and singly ionized (II) atoms of the elements from hydrogen through plutonium (Z = 1–94); selected strong lines from doubly ionized (III), triply ionized (IV), and quadruply ionized (V) atoms are also included. Listed are lines that appear in emission from the vacuum ultraviolet to the far infrared. These lines were selected from much larger lists in such a way as to include the stronger observed lines in each spectral region. A more extensive list may be found in Reference 1.

The data were compiled by the following contributors.

J. G. Conway — Lawrence Berkeley Laboratory
C. H. Corliss — National Bureau of Standards
R. D. Cowan — Los Alamos Scientific Laboratory
C. R. Cowley — University of Michigan
Henry M. and Hannah Crosswhite — Argonne National Laboratory
S. P. Davis — University of California, Berkeley
V. Kaufman — National Bureau of Standards
R. L. Kelly — Naval Postgraduate School
J. F. Kielkopf — University of Louisville
W. C. Martin — National Bureau of Standards
T. K. McCubbin — Pennsylvania State University
L. J. Radziemski — Los Alamos Scientific Laboratory
J. Reader — National Bureau of Standards
C. J. Sansonetti — National Bureau of Standards
G. V. Shalimoff — Lawrence Berkeley Laboratory
R. W. Stanley — Purdue University
J. O. Stoner, Jr. — University of Arizona
H. H. Stroke — New York University
D. R. Wood — Wright State University
E. F. Worden — Lawrence Livermore Laboratory
J. J. Wynne — International Business Machines Corporation
R. Zalubas — National Bureau of Standards

All wavelengths are given in Ångstrom units (10^{-10} m). Below 2000 Å the wavelengths are in vacuum (except for the Cu II line at 1999.698 Å, which is in air); above 2000 Å the wavelengths are in air. Wavelengths given to three decimal places have an uncertainty of less than 0.001 Å and are therefore suitable for calibration purposes. In the air region, the elements used most commonly for calibration are Ne, Ar, Kr, Fe, Th, and Hg; in the vacuum region, the most common are C, N, O, Si, Cu.

All data refer to natural isotopic abundance of the elements except that Kr I and Kr II lines below 11,000 Å given to three decimal places are for ^{86}Kr. A separate table for ^{198}Hg contains accurately known wavelengths that are frequently used for calibration.

A large number of the lines for neutral and singly ionized atoms were extracted from the National Bureau of Standards (NBS) *Tables of Spectral-Line Intensities* (Reference 2). The intensities of these lines represent quantitative estimates of relative line strengths that take account of varying detection sensitivity at different wavelengths. They are on a linear scale. For nearly all of the other lines the intensities represent qualitative estimates of the relative strengths of lines not greatly separated in wavelength. Because different observers frequently use different scales for their intensity estimates, these intensities are useful only as a rough indication of the appearance of a spectrum. In some cases the intensity scale is not intended to be linear. In the first and second spectra the intensities of the lines of the singly ionized atom (II) relative to those of the neutral atom (I) should be used with caution, inasmuch as the concentration of ions in a light source depends greatly on the excitation conditions.

Descriptive symbols that follow the wavelength have the following meanings:

c — complex
d — line consists of two unresolved lines
h — hazy
l — shaded to longer wavelengths
s — shaded to shorter wavelengths
p — perturbed by a close line
r — easily reversed
w — wide

The table is arranged alphabetically by element name (not symbol); for each element the lines are listed by wavelength. References to the sources of data for each element are given at the end of the table, starting on page **10**-89.

General References

1. Reader, J., Corliss, C. H., Wiese, W. L., and Martin, G. A., *Tables of Line Spectra of the Elements, Part 1. Wavelengths and Intensities*, Nat. Stand. Ref. Data Sys.- Nat. Bur. Standards (U.S.), No. 68, 1980.
2. Meggers, W. F., Corliss, C. H., and Scribner, B. F., *Tables of Spectral Line Intensities, Part 1. Arranged by Elements*, Nat. Bur. Stand. (U.S.), Monograph 145, 1975.
3. Fuhr, J. R., Martin, W. C., Musgrove, A., Sugar, J., and Wiese, W. L., "NIST Atomic Spectroscopic Database" ver. 1.1, January 1996. *NIST Physical Reference Data*, National Institute of Standards and Technology, Gaithersburg, MD. Available at the WWW address: http://physics.nist.gov/PhysRefData/contents.html

Intensity	Wavelength/Å	
Actinium Ac Z = 89		
2000 h	2952.55	III
2000 h	3392.78	III
3000	3487.59	III
2000 s	3863.12	II
3000 s	4088.44	II
3000 s	4168.40	II
100	4179.98	I
20	4183.12	I
20	4194.40	I
20 l	4384.53	I
20	4396.71	I
2000 h	4413.09	III
20	4462.73	I
3000 h	4569.87	III
1000	5910.85	II
20	6359.86	I
20 l	6691.27	I
Aluminum Al Z = 13		
900	125.53	V
800	126.07	V
800	130.41	V
1000	130.85	V
900	131.00	V
900	131.44	V
800	160.07	IV
1000	278.69	V
900	281.39	V
70	486.884	III
30	486.912	III
250	511.138	III
150	511.191	III
500	560.317	III
200	560.433	III
100	670.068	III
200	671.118	III
500	695.829	III
400	696.217	III
200	725.683	III
300	726.915	III
400	855.034	III
500	856.746	III
400	892.024	III
50	893.887	III
450	893.897	III
800	1042.17	IV
50	1191.812	II
900	1237.19	IV
900	1257.62	IV
800	1264.18	IV
1000	1272.76	IV
150	1350.18	II
800	1384.13	III
800	1447.51	IV
800	1494.79	IV
1000	1526.14	V
800	1537.54	IV
800	1539.830	II
1000	1557.25	IV
100	1569.385	II
900	1582.04	IV
800	1584.46	IV
125	1596.059	II
700	1605.766	III
100	1611.814	III
800	1611.874	III
150	1625.627	II
800	1639.06	IV
100	1644.235	II
100	1644.809	II
1000	1670.787	II
100	1686.250	II
800	1719.440	II
500	1721.244	II
900	1721.271	II
500	1724.952	II
900	1724.984	II
350	1760.104	II
300	1761.975	II
290	1763.00	I
500	1763.869	II
700	1763.952	II
450	1765.64	I
300	1765.815	II
450	1766.38	I
400	1767.731	II
450	1769.14	I
1000	1818.56	IV
600	1828.588	II
400	1832.837	II
250	1834.808	II
1000	1854.716	III
300	1855.929	II
700	1858.026	II
120	1859.980	II
1000	1862.311	II
600	1862.790	III
200	1929.978	II
150	1931.048	II
200	1932.377	II
400	1934.503	II
150	1934.713	II
300	1935.840	III
200	1935.949	III
150	1936.907	II
220	1939.261	II
700	1990.531	II
150	2016.052	II
150	2016.234	II
100	2016.368	II
200	2074.008	II
700	2094.264	II
150	2094.744	II
300	2094.791	II
100	2095.104	II
200	2095.141	II
400	2269.10	I
120	2269.22	I
140	2321.56	I
460	2367.05	I
110	2367.61	I
110	2368.11	I
180	2369.30	I
140	2370.22	I
160	2372.07	I
850	2373.12	I
170	2373.35	I
110	2373.57	I
240	2567.98	I
480	2575.10	I
110	2637.70	II
150	2652.48	I
200	2660.39	I
160	2669.17	II
650	2816.19	II
150	3041.28	II
360	3050.07	I
450	3057.14	I
150	3074.64	II
4500 r	3082.153	I
7200 r	3092.710	I
1800 r	3092.839	I
150	3428.92	II
150	3443.64	I
900	3492.23	IV
800	3508.46	IV
450	3586.56	II
360	3587.07	II
290	3587.45	II
870	3601.63	III
220	3651.06	II
110	3651.10	II
150	3654.98	II
290	3655.00	II
450	3900.68	II
4500 r	3944.006	I
9000 r	3961.520	I
110	3995.86	II
290	4226.81	II
870	4529.19	III
150	4585.82	II
110	4588.19	II
550	4666.80	II
110	4898.76	II
110	4902.77	II
150	5280.21	II
290	5283.77	II
150	5285.85	II
110	5312.32	II
220	5316.07	II
150	5371.84	II
180	5557.06	I
110	5557.95	I
450	5593.23	II
1200	5696.60	III
1000	5722.73	III
110	5853.62	II
220	5971.94	II
290	6001.76	II
220	6001.88	II
450	6006.42	II
150	6061.11	II
290	6068.43	II
110	6068.53	II
450	6073.23	II
110	6181.57	II
150	6181.68	II
290	6182.28	II
220	6182.45	II
450 h	6183.42	II
450	6201.52	II
360	6201.70	II
290	6226.18	II
360	6231.78	II
450	6243.36	II
450	6335.74	II
360	6696.02	I
230	6698.67	I
110	7361.57	I
140	7362.30	I
230	7835.31	I
290	7836.13	I
110	8075.35	I
290	8640.70	II
360	8772.87	I
450	8773.90	I
110	8828.91	I
180	8841.28	I
140	8923.56	I
150	9290.65	II
110	9290.75	II
150	10076.29	II
110	10768.36	I
140	10782.04	I
110	10872.98	I
230	10891.73	I
450	11253.19	I
570	11254.88	I
570	13123.41	I
450	13150.76	I
230	16718.96	I
300	16750.56	I
140	16763.36	I
300	21093.04	I
360	21163.75	I
Antimony Sb Z = 51		
15	722.86	III
15	732.33	III
	861.5	IV
4	876.84	II
4	921.07	II
6	983.57	II
15	999.62	III
6	1001.13	II
6	1009.43	II
40	1011.94	III
6	1052.21	II
8	1056.27	II
8	1057.32	II
40	1065.90	III
6	1073.81	II
30	1075.82	III
	1087.6	IV

Intensity	Wavelength/Å	
8	1104.32	V
30	1151.49	III
40	1157.74	III
	1199.1	IV
50	1205.20	III
50	1210.64	III
12	1226.00	V
6	1230.30	II
8	1274.98	II
20	1306.69	III
8	1327.40	II
6	1358.04	II
8	1384.70	II
20	1404.18	III
6	1407.83	II
8	1436.49	II
20 r	1486.57	I
40 h	1491.36	I
	1499.2	IV
12	1505.70	V
50 r	1512.57	I
12	1524.47	V
120 r	1532.74	I
80 r	1535.06	I
6	1565.51	II
8	1576.11	II
7	1581.36	II
80 r	1599.96	I
10	1606.98	II
200 w	1612.8	I
100 w	1623.3	I
20	1657.04	II
100 w	1662.6	I
15	1673.89	III
15	1711.84	III
80 r	1716.93	I
150 r	1717.45	I
150 r	1723.43	I
15	1725.33	III
100 r	1736.19	I
100 h	1765.76	I
100 r	1780.87	I
100 r	1788.24	I
150	1800.18	I
50 r	1810.50	I
80 r	1814.20	I
100	1829.50	I
50 r	1868.17	I
300 r	1871.15	I
150 r	1882.56	I
100	1927.08	I
200 r	1950.39	I
60 r	2029.49	I
70 r	2039.77	I
150 r	2049.57	I
1000 r	2068.33	I
100	2079.56	I
50 r	2098.41	I
80 r	2118.48	I
100 r	2127.39	I
50 r	2137.05	I
100 r	2139.69	I
10	2141.80	II
50 r	2141.83	I
100 r	2144.86	I
1500 r	2175.81	I
250 r	2179.19	I
200 r	2201.32	I
300 r	2208.45	I
150 r	2220.73	I
100	2221.98	I
120 r	2224.93	I
300 r	2262.51	I
120	2288.98	I
150 r	2293.44	I
300 r	2306.46	I
2500 r	2311.47	I
150	2315.89	I
400 h	2373.67	I
300 h	2383.64	I
100	2395.22	I
150	2422.13	I
250	2426.35	I
400 r	2445.51	I
400	2478.32	I
150	2480.44	I
100	2510.54	I
2000 r	2528.52	I
15	2528.54	II
10	2567.75	II
150	2574.06	I
15	2590.13	III
1500 r	2598.05	I
500 r	2598.09	I
300 r	2612.31	I
12	2617.17	III
200 r	2652.60	I
20	2669.39	III
300 r	2670.64	I
200 r	2682.76	I
120	2692.25	I
150 r	2718.90	I
400 r	2769.95	I
1000 r	2877.92	I
15	2980.96	II
500 r	3029.83	I
600 r	3232.52	I
20	3241.28	II
700 r	3267.51	I
15	3498.46	II
25	3637.80	II
250	3637.83	I
20	3722.78	II
200 r	3722.79	I
20	3850.22	II
200	4033.55	I
20	4033.56	II
20	4133.63	II
15	4140.54	II
15	4195.17	II
20	4219.07	II
20	4314.32	II
15	4514.50	II
30	4596.90	II
20	4599.09	II
15	4604.77	II
30	4647.32	II
20	4675.74	II
40	4711.26	II
20	4757.81	II
20	4765.36	II
30	4784.03	II
20	4802.01	II
20	4832.82	II
20	4877.24	II
15	4947.40	II
15	5044.56	II
20	5238.94	II
20	5354.24	II
40 h	5556.10	I
100 l	5632.02	I
30	5639.75	II
60 h	5830.34	I
100	6005.21	II
20	6053.41	II
30	6079.80	II
50	6130.04	II
20	6154.94	II
20	6611.49	I
30	6647.44	II
30 h	7648.28	I
80	7844.44	I
200	7924.65	I
60	8411.69	I
150	8572.64	I
100	8619.55	I
400	9518.68	I
400	9949.14	I
200	10078.49	I
300	10261.01	I
200	10585.60	I
1000	10677.41	I
800	10741.94	I
80	10794.11	I
600	10839.73	I
200	10868.58	I
400	10879.55	I
300	11012.79	I
150	11266.23	I
5	12116.06	I

Argon Ar Z = 18

3	336.56	V
3	337.56	V
6	338.00	V
2	338.43	V
2	339.01	V
3	339.89	V
3	350.88	V
4	396.87	IV
4	398.55	IV
2	436.67	V
5	446.00	V
8	446.95	V
4	447.53	V
18	449.06	V
4	449.49	V
3	458.12	V
2	458.98	V
6 p	461.23	V
3	462.42	V
7	463.94	V
30	487.227	II
50	490.650	II
30	490.701	II
30	519.327	II
3	522.09	V
5	524.19	V
6	527.69	V
30	542.912	II
200	543.203	II
70	547.461	II
2	554.50	V
70	556.817	II
5	558.48	V
70	573.362	II
30	576.736	II
70	580.263	II
30	583.437	II
70	597.700	II
30	602.858	II
30	612.372	II
6	623.77	IV
3	635.12	V
500	661.867	II
30	664.562	II
200	666.011	II
1000	670.946	II
3000	671.851	II
70	676.242	II
30	677.952	II
30	679.218	II
200	679.401	II
10	683.28	IV
7	688.39	IV
12 p	689.01	IV
6	699.41	IV
8	700.28	IV
3	705.35	V
5	709.20	V
4	715.60	V
3	715.65	V
200	718.090	II
3000	723.361	II
2	725.11	V
500	725.548	II
70	730.930	II
200	740.269	II
200	744.925	II
70	745.322	II
4	754.20	IV
5	761.47	IV
12	769.15	III
5	800.57	IV
10	801.09	IV

Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å	
10	801.41	IV	12	2293.03	III	12	2913.00	IV	35	3718.206	II
5	801.91	IV	4	2299.72	IV	11	2926.33	IV	70	3729.309	II
20	802.859	I	10	2300.85	III	200	2942.893	II	50	3737.889	II
100	806.471	I	15	2302.17	III	100	2979.050	II	150	3765.270	II
60	806.869	I	9	2317.00	III	10	3010.02	III	50	3766.119	II
30	807.218	I	15	2317.47	III	12	3024.05	III	20	3770.369	I
40	807.653	I	12	2318.04	III	50	3033.508	II	20	3770.520	II
50	809.927	I	10	2319.13	III	6	3037.98	IV	25	3780.840	II
120	816.232	I	10	2319.37	III	12	3054.82	III	20	3795.37	III
70	816.464	I	9	2345.17	III	10	3064.77	III	25	3803.172	II
80	820.124	I	7	2351.67	III	8	3077.40	IV	50	3809.456	II
4	822.16	V	9	2360.26	III	10	3078.15	III	7	3834.679	I
120	825.346	I	10	2395.63	III	50	3093.402	II	70	3850.581	II
120	826.365	I	12	2399.15	III	7	3110.41	III	10	3858.32	III
5	827.05	V	10	2413.20	III	7	3127.90	III	35	3868.528	II
3	827.35	V	7	2415.61	III	8	3200.37	I	7	3907.84	III
150	834.392	I	10	2418.82	III	20	3243.689	II	35	3925.719	II
4 p	834.88	V	5	2420.456	II	25	3285.85	III	50	3928.623	II
100	835.002	I	12	2423.52	III	25	3293.640	II	25	3932.547	II
2	836.13	V	12	2423.93	III	20	3301.88	III	70	3946.097	II
15	840.03	IV	7	2443.69	III	20	3307.228	II	7	3947.505	I
100	842.805	I	8	2447.71	IV	15	3311.25	III	35	3948.979	I
20	843.77	IV	8	2472.95	III	7	3319.34	I	8	3960.53	III
25	850.60	IV	7	2476.10	III	7	3323.59	III	20	3979.356	II
180	866.800	I	12	2488.86	III	25	3336.13	III	35	3994.792	II
150	869.754	I	12	2513.28	IV	20	3344.72	III	50	4013.857	II
10	871.10	III	10	2516.789	II	25	3350.924	II	6	4023.60	III
9	875.53	III	6	2518.40	IV	15	3358.49	III	50	4033.809	II
180 r	876.058	I	9	2525.69	IV	7	3361.28	III	20	4035.460	II
12	878.73	III	10	2534.709	II	7	3373.47	I	150	4042.894	II
8	879.62	III	15	2562.087	II	25	3376.436	II	50	4044.418	I
180 r	879.947	I	12	2562.17	IV	25	3388.531	II	100	4052.921	II
9	883.18	III	10	2568.07	IV	15	3391.85	III	200	4072.005	II
10	887.40	III	7	2569.53	IV	7	3393.73	I	70	4072.385	II
150	894.310	I	12	2599.47	IV	7	3417.49	III	25	4076.628	II
5	900.36	IV	10	2608.06	IV	9	3424.25	III	35	4079.574	II
9	901.17	IV	7	2608.44	IV	8	3438.04	III	25	4082.387	II
1000	919.781	II	12	2615.68	IV	7	3461.07	I	150	4103.912	II
1000	932.054	II	6	2619.98	IV	9	3471.32	III	300	4131.724	II
1000 r	1048.220	I	12	2621.36	IV	70	3476.747	II	5	4146.70	III
500 r	1066.660	I	12	2624.92	IV	20	3478.232	II	35	4156.086	II
7	1669.67	III	7	2631.90	III	20	3480.55	III	400	4158.590	I
7	1673.42	III	15	2640.34	IV	50	3491.244	II	50	4164.180	I
7	1675.48	III	10	2654.63	III	100	3491.536	II	35	4179.297	II
9	1914.40	III	8	2674.02	III	12	3499.67	III	50	4181.884	I
7	1915.56	III	9	2678.38	III	15	3503.58	III	100	4190.713	I
10	2125.16	III	9	2682.63	IV	70	3509.778	II	50	4191.029	I
15	2133.87	III	10	2724.84	III	8	3511.12	III	200	4198.317	I
10	2138.59	III	14	2757.92	IV	70	3514.388	II	400	4200.674	I
10	2148.73	III	7	2762.23	III	70	3545.596	II	25	4218.665	II
15	2166.19	III	10	2776.26	IV	70	3545.845	II	25	4222.637	II
10	2168.26	III	12	2784.47	IV	7	3554.306	I	25	4226.988	II
20	2170.23	III	14	2788.96	IV	100	3559.508	II	100	4228.158	II
25	2177.22	III	7	2797.11	IV	100	3561.030	II	100	4237.220	II
8	2184.06	III	16	2809.44	IV	70	3576.616	II	25	4251.185	I
10	2188.22	III	10	2830.25	IV	25	3581.608	II	200	4259.362	I
15	2192.06	III	7	2842.88	III	50	3582.355	II	100	4266.286	I
7	2248.73	III	8	2855.29	III	70	3588.441	II	70	4266.527	II
10	2279.10	III	6	2874.40	IV	7	3606.522	I	150	4272.169	I
7	2281.22	III	9	2884.12	III	25	3622.138	II	550	4277.528	II
7	2282.21	III	25	2891.612	II	20	3639.833	II	20	4282.898	II

Intensity	Wavelength/Å	
100	4300.101	I
25	4300.650	II
70	4309.239	II
200	4331.200	II
50	4332.030	II
100	4333.561	I
50	4335.338	I
25	4345.168	I
800	4348.064	II
50	4352.205	II
25	4362.066	II
50	4367.832	II
200	4370.753	II
70	4371.329	II
50	4375.954	II
150	4379.667	II
50	4385.057	II
70	4400.097	II
200	4400.986	II
400	4426.001	II
150	4430.189	II
50	4430.996	II
50	4433.838	II
20	4439.461	II
35	4448.879	II
100	4474.759	II
200	4481.811	II
100	4510.733	I
20	4522.323	I
20	4530.552	II
400	4545.052	II
20	4564.405	II
400	4579.350	II
400	4589.898	II
15	4596.097	I
550	4609.567	II
7	4628.441	I
35	4637.233	II
400	4657.901	II
15	4702.316	I
20	4721.591	II
550	4726.868	II
50	4732.053	II
300	4735.906	II
800	4764.865	II
550	4806.020	II
150	4847.810	II
50	4865.910	II
800	4879.864	II
70	4889.042	II
20	4904.752	II
35	4933.209	II
200	4965.080	II
50	5009.334	II
70	5017.163	II
70	5062.037	II
20	5090.495	II
100	5141.783	II
70	5145.308	II
5	5151.391	I
15	5162.285	I
25	5165.773	II
20	5187.746	I
20	5216.814	II
7	5221.271	I
5	5421.352	I
10	5451.652	I
25	5495.874	I
5	5506.113	I
25	5558.702	I
10	5572.541	I
35	5606.733	I
20	5650.704	I
10	5739.520	I
5	5834.263	I
10	5860.310	I
15	5882.624	I
25	5888.584	I
50	5912.085	I
15	5928.813	I
5	5942.669	I
7	5987.302	I
5	5998.999	I
5	6025.150	I
70	6032.127	I
35	6043.223	I
10	6052.723	I
20	6059.372	I
7	6098.803	I
10	6105.635	I
100	6114.923	II
10	6145.441	I
7	6170.174	I
150	6172.278	II
10	6173.096	I
10	6212.503	I
5	6215.938	I
25	6243.120	II
7	6296.872	I
15	6307.657	I
7	6369.575	I
20	6384.717	I
70	6416.307	I
25	6483.082	II
15	6538.112	I
15	6604.853	I
25	6638.221	II
20	6639.740	II
50	6643.698	II
5	6660.676	I
5	6664.051	I
25	6666.359	II
100	6677.282	I
35	6684.293	II
150	6752.834	I
5	6756.163	I
15	6766.612	I
20	6861.269	II
150	6871.289	I
5	6879.582	I
10	6888.174	I
50	6937.664	I
7	6951.478	I
7	6960.250	I
10000	6965.431	I
150	7030.251	I
10000	7067.218	I
100	7068.736	I
25	7107.478	I
25	7125.820	I
1000	7147.042	I
15	7158.839	I
70	7206.980	I
15	7265.172	I
7	7270.664	I
2000	7272.936	I
35	7311.716	I
25	7316.005	I
5	7350.814	I
70	7353.293	I
200	7372.118	I
20	7380.426	II
10000	7383.980	I
20	7392.980	I
15	7412.337	I
10	7425.294	I
25	7435.368	I
10	7436.297	I
20000	7503.869	I
15000	7514.652	I
25000	7635.106	I
15000	7723.761	I
10000	7724.207	I
10	7891.075	I
20000	7948.176	I
20000	8006.157	I
25000	8014.786	I
7	8053.308	I
20000	8103.693	I
35000	8115.311	I
10000	8264.522	I
20	8392.27	I
15000	8408.210	I
20000	8424.648	I
15000	8521.442	I
7	8605.776	I
4500	8667.944	I
20	8771.860	II
180	8849.91	I
20	9075.394	I
35000	9122.967	I
550	9194.638	I
15000	9224.499	I
400	9291.531	I
1600	9354.220	I
25000	9657.786	I
4500	9784.503	I
180	10052.06	I
30	10332.72	I
100	10467.177	II
1600	10470.054	I
13	10478.034	I
180	10506.50	I
200	10673.565	I
11	10681.773	I
7	10683.034	II
30	10733.87	I
30	10759.16	I
7	10812.896	II
11	11078.869	I
30	11106.46	I
12	11441.832	I
400	11488.109	I
200	11668.710	I
12	11719.488	I
200	12112.326	I
50	12139.738	I
50	12343.393	I
200	12402.827	I
200	12439.321	I
100	12456.12	I
200	12487.663	I
150	12702.281	I
30	12733.418	I
12	12746.232	I
200	12802.739	I
50	12933.195	I
500	12956.659	I
200	13008.264	I
200	13213.99	I
200	13228.107	I
100	13230.90	I
500	13272.64	I
1000	13313.210	I
1000	13367.111	I
30	13499.41	I
1000	13504.191	I
11	13573.617	I
30	13599.333	I
400	13622.659	I
200	13678.550	I
1000	13718.577	I
10	13825.715	I
10	13907.478	I
200	14093.640	I
100	15046.50	I
25	15172.69	I
10	15329.34	I
30	15989.49	I
30	16519.86	I
500	16940.58	I
12	18427.76	I
50	20616.23	I
30	20986.11	I
20	23133.20	I
20	23966.52	I

Arsenic As Z = 33

510	871.7	III
325	889.0	III
325	927.5	III
325	937.2	III
325	953.6	III
325	963.8	III
250	987.7	V

Intensity	Wavelength/Å	
340	1021.96	II
250	1029.5	V
340	1082.35	II
500	1139.40	II
615	1149.31	II
555	1181.51	II
555	1189.87	II
615	1196.38	II
615	1196.56	II
340	1207.44	II
800	1211.17	II
800	1218.10	II
340	1223.15	II
760	1241.31	II
965	1243.08	II
870	1245.67	II
800	1258.58	II
965	1263.77	II
800	1266.34	II
800	1267.59	II
715	1280.99	II
715	1287.54	II
715	1305.70	II
340	1307.74	II
760	1333.15	II
965	1341.55	II
760	1355.93	II
965	1369.77	II
800	1373.65	II
1000	1375.07	II
760	1375.78	II
800	1394.64	II
800	1400.31	II
500	1448.59	II
500	1558.88	II
500	1570.99	II
100 r	1593.60	I
500	1660.55	II
340	1860.34	II
1000 r	1890.42	I
500	1912.94	II
800 r	1937.59	I
585 r	1972.62	I
170 r	1990.35	I
100 r	1991.13	I
100 r	1995.43	I
230 r	2003.34	I
100 r	2009.19	I
200	2263.2	IV
350 r	2288.12	I
200	2301.0	IV
350 r	2349.84	I
100 r	2370.77	I
135 r	2381.18	I
250	2417.5	IV
250	2454.0	IV
170 r	2456.53	I
200	2461.4	IV
340	2602.00	II
170 r	2780.22	I
300	2830.359	II
300	2831.164	II
100 r	2860.44	I
300	2884.406	II
80	2926.3	III
615	2959.572	II
300	3003.819	II
300	3116.516	II
340	3842.60	II
325	3922.6	III
715	4190.082	II
615	4197.40	II
615	4242.982	II
500	4315.657	II
500	4323.867	II
500	4336.64	II
500	4352.145	II
425	4352.864	II
375	4371.17	II
615	4427.106	II
615	4431.562	II
715	4458.469	II
340	4461.075	II
715	4466.348	II
500	4474.46	II
800	4494.230	II
850	4507.659	II
615	4539.74	II
715	4543.483	II
615	4602.427	II
340	4629.787	II
340	4707.586	II
340	4730.67	II
340	4888.557	II
340	5105.58	II
500	5107.55	II
425	5231.38	II
500	5331.23	II
340	5497.727	II
425	5558.09	II
425	5651.32	II
425	6110.07	II
500	6170.27	II
300	6511.74	II
300	7092.27	II
300	7102.72	II
340	7990.53	II
300	8174.51	II
200	9300.61	I
230	9597.95	I
290	9626.70	I
230	9833.76	I
170	9915.71	I
290	9923.05	I
290	10024.04	I
170	10614.07	I
Astatine At	***Z = 85***	
8	2162.25	I
10	2244.01	I
Barium Ba	***Z = 56***	
14	555.48	III
14	587.57	III
18	647.27	III
300	719.86	V
150	721.85	V
1000	766.87	V
40000	794.89	IV
300	877.41	V
50000	923.74	IV
200	946.26	V
200	1486.72	II
400	1504.01	II
300	1554.38	II
200	1572.73	II
	1573.92	II
	1630.40	II
100	1674.51	II
400	1694.37	II
	1697.16	II
	1761.75	II
	1771.03	II
	1786.93	II
100	1904.15	II
500	1924.70	II
	1985.60	II
300	1999.54	II
10	2001.30	III
	2009.20	II
400	2023.95	II
	2052.68	II
	2054.57	II
500	2214.7	II
800	2245.61	II
1000	2254.73	II
1400	2304.24	II
60	2331.10	III
2000	2335.27	II
190	2347.58	II
40	2512.28	III
40	2523.83	III
60	2528.51	II
50	2559.54	III
8 h	2596.64	I
100	2634.78	II
40	2681.89	III
8	2702.63	I
18	2771.36	II
15	2785.28	I
100 r	3071.58	I
40	3079.14	III
10 h	3108.21	I
8	3132.60	I
8 h	3135.72	I
10	3137.70	I
10	3155.34	I
10	3155.67	I
12	3158.05	I
12 h	3158.54	I
25	3165.60	I
15 h	3173.69	I
30	3183.16	I
15	3183.96	I
10	3193.91	I
25 h	3203.70	I
30	3221.63	I
40	3222.19	I
50	3261.96	I
60 r	3262.34	I
40	3281.50	I
15	3281.77	I
50	3322.80	I
80 h	3356.80	I
50	3368.18	III
60 r	3377.08	I
20	3377.39	I
70 r	3420.32	I
25	3421.01	I
30 h	3421.48	I
40	3463.74	I
200 r	3501.11	I
80 h	3524.97	I
30 h	3531.35	I
80 h	3544.66	I
20 h	3547.68	I
100	3552.45	II
200	3567.73	II
100	3576.28	II
30	3577.62	I
80 h	3579.67	I
200	3596.57	II
40	3630.64	I
40 h	3636.83	I
20 h	3688.47	I
400	3735.75	II
200	3816.69	II
200	3842.80	II
100	3854.76	II
20	3889.33	I
1400 l	3891.78	II
20	3892.65	I
40	3909.91	I
500	3914.73	II
25	3926.85	III
50	3935.72	I
20	3937.87	I
200	3939.67	II
500	3949.51	II
25	3993.06	III
80	3993.40	I
30	3995.66	I
300	4036.26	II
200	4083.77	II
30 h	4084.86	I
1500 h	4130.66	II
20	4132.43	I
200	4166.00	II
500	4216.04	II
800	4267.95	II
100	4283.10	I
300	4287.80	II
200	4297.60	II
800	4309.32	II
20 h	4323.00	I

Intensity	Wavelength/Å	
600	4325.73	II
200	4326.74	II
300	4329.62	II
80	4350.33	I
60	4402.54	I
400	4405.23	II
40	4431.89	I
60 h	4488.98	I
50 h	4493.64	I
40	4505.92	I
200	4509.63	II
60 h	4523.17	I
130	4524.93	II
65000	4554.03	II
40	4573.85	I
80	4579.64	I
30	4599.75	I
20 h	4619.92	I
25 h	4628.33	I
300	4644.10	II
30	4673.62	I
35	4691.62	I
20	4700.43	I
800	4708.94	II
40	4726.44	I
800	4843.46	II
300	4847.14	II
200	4850.84	II
30 h	4877.65	I
400	4899.97	II
15	4902.90	I
20000	4934.09	II
8	4947.35	I
1000	4957.15	II
300	4997.81	II
1000	5013.00	II
20 h	5159.94	I
20	5267.03	I
800	5361.35	II
1000	5391.60	II
200	5421.05	II
100	5424.55	I
200	5428.79	II
300	5480.30	II
200	5519.05	I
1000 r	5535.48	I
20 h	5620.40	I
10	5680.18	I
400	5777.62	I
800	5784.18	II
100	5800.23	I
20	5805.69	I
150	5826.28	I
2800	5853.68	II
15	5907.64	I
100	5971.70	I
800	5981.25	II
100	5997.09	I
300	5999.85	II
100	6019.47	I
200	6063.12	I
300	6110.78	I
400	6135.83	II
20000	6141.72	II
150	6341.68	I
500	6378.91	II
10	6383.76	III
90	6450.85	I
150	6482.91	I
12000	6496.90	II
300	6498.76	I
150	6527.31	I
3000	6595.33	I
150	6654.10	I
1500	6675.27	I
1800	6693.84	I
1000	6769.62	II
600	6865.69	I
300 h	6867.85	I
1000	6874.09	II
6000	7059.94	I
2400 hs	7120.33	I
600	7195.24	I
600 hl	7228.84	I
3000	7280.30	I
1200	7392.41	I
300	7417.53	I
900 hl	7459.78	I
600	7488.08	I
450 hl	7636.90	I
600 hl	7642.91	I
1800	7672.09	I
1200	7780.48	I
180 h	7839.57	I
1500	7905.75	I
600	7911.34	I
900 h	8210.24	I
8	8308.69	III
1800 h	8559.97	I
100	8710.74	II
100	8737.71	II
300 h	8799.76	I
300	8860.98	I
450	8914.99	I
300	9219.69	I
300	9308.08	I
300 h	9324.58	I
1500	9370.06	I
300	9455.92	I
8	9521.76	III
450	9589.37	I
900	9608.88	I
300 h	9645.72	I
1500 hl	9830.37	I
900	10001.08	I
600	10032.10	I
1200 h	10233.23	I
300	10471.26	I
120 hl	10791.25	I
180 hl	11012.69	I
150 h	11114.42	I
240	11303.04	I
120 h	11697.45	I
120	13207.30	I
120	13810.50	I
120	14077.90	I
120	15000.40	I
120	20712.00	I
150	25515.70	I
150	29223.90	I

Beryllium Be Z = 4

Intensity	Wavelength/Å	
	58.13	IV
	58.57	IV
	59.32	IV
	60.74	IV
	64.06	IV
	75.93	IV
1 h	76.10	III
2	76.48	III
3	78.53	III
4	78.66	III
1 h	78.92	III
5	81.89	III
10	82.38	III
	82.58	II
20	83.20	III
	83.66	II
30	84.76	III
50	88.31	III
	89.16	I
	89.80	II
	90.04	II
	90.21	I
	90.67	I
	91.06	II
	91.36	II
	91.74	II
	92.19	I
	92.61	II
	93.14	II
	93.42	II
	93.93	II
	94.78	II
	95.76	II
	96.29	I
	97.24	I
	97.44	I
	97.86	I
	97.97	I
	98.12	I
	98.37	I
	98.66	I
	98.94	I
	99.19	I
100	100.25	III
	100.86	I
	101.20	I
	102.13	I
	102.49	II
	104.40	II
	104.67	I
	105.80	I
	107.26	I
	107.38	I
3	509.99	III
2	549.31	III
6	582.08	III
4	661.32	III
8	675.59	III
	714.0	II
4	725.59	III
5	725.71	II
5	743.58	II
7	746.23	III
2	767.75	III
8	775.37	II
20	842.06	II
	865.3	II
2	925.25	II
10	943.56	II
10	973.27	II
	981.4	II
	1020.1	II
8	1026.93	II
5	1036.32	II
15	1048.23	II
1	1114.69	III
20	1143.03	II
	1155.9	II
60	1197.19	II
2	1213.12	III
1	1214.32	III
2	1362.25	III
1	1401.52	III
10	1421.26	III
5	1422.86	III
	1426.12	I
1	1435.17	III
2	1440.77	III
	1491.76	I
20	1512.30	II
60	1512.43	II
100	1661.49	I
2 h	1754.69	III
15	1776.12	II
20	1776.34	II
	1907.	I
	1909.0	II
	1912.	I
3	1917.03	III
	1919.	I
5	1929.67	I
10	1943.68	I
60 h	1954.97	III
	1956.	I
50	1964.59	I
5	1985.13	I
	1997.95	I
	1997.98	I
60	1998.01	I
	2033.25	I
	2033.28	I
	2033.38	I
50	2055.90	I

Intensity	Wavelength/Å	
100	2056.01	I
75 h	2076.94	III
60 h	2080.38	III
25	2118.56	III
15 h	2122.27	III
10	2125.57	I
20	2125.68	I
15 h	2127.20	III
5	2137.25	III
25	2145.	I
55	2174.99	I
55	2175.10	I
5	2191.57	III
	2273.5	II
	2324.6	II
	2337.0	I
950	2348.61	I
20	2350.66	I
60	2350.71	I
200	2350.83	I
2	2413.34	II
16	2413.46	II
20	2453.84	II
	2480.6	I
35	2494.54	I
35	2494.58	I
100	2494.73	I
16	2507.43	II
5	2617.99	II
20	2618.13	II
100	2650.45	I
60	2650.55	I
200	2650.62	I
60	2650.69	I
100	2650.76	I
5	2697.46	II
20	2697.58	II
20	2728.88	II
30	2738.05	I
	2764.2	II
20	2898.13	I
10	2898.19	I
20	2898.25	I
30	2986.06	I
10	2986.42	I
60	3019.33	I
30	3019.49	I
30	3019.53	I
20	3019.60	I
10	3046.52	II
30	3046.69	II
	3090.3	I
10	3110.81	I
10	3110.92	I
20	3110.99	I
	3120.	I
480	3130.42	II
320	3131.07	II
	3136.	I
	3150.	I
	3160.6	I
	3163.	I
	3168.	I
	3180.7	II
	3187.	I
20	3193.81	I
20	3197.10	II
30	3197.15	II
20	3208.60	I
	3220.	I
60	3229.63	I
2	3233.52	II
10	3241.62	II
30	3241.83	II
15	3269.02	I
100	3274.58	II
30	3274.67	II
30	3282.91	I
30	3321.01	I
30	3321.09	I
220	3321.34	I
20	3345.43	I
60	3367.63	I
	3405.6	II
5	3451.37	I
300	3455.18	I
20	3476.56	I
300	3515.54	I
10	3555.	I
100	3720.36	III
	3720.92	III
	3722.98	III
100	3736.30	I
700	3813.45	I
40	3865.13	I
80	3865.42	I
1	3865.51	I
6	3865.72	I
100	3866.03	I
90 h	4249.14	III
100	4253.05	I
60	4253.76	I
300	4360.66	II
500	4360.99	II
400	4407.94	I
2	4485.52	III
100 h	4487.30	III
1	4495.09	III
140 h	4497.8	III
	4526.6	I
	4548.	I
12	4572.66	I
700	4673.33	II
1000	4673.42	II
6	4709.37	I
200	4828.16	II
40	4849.16	I
2 h	4858.22	II
80	5087.75	I
8	5218.12	II
20	5218.33	II
3	5255.86	II
64	5270.28	II
500	5270.81	II
20	5403.04	II
20	5410.21	II
	5558.	I
140 h	6142.01	III
10	6229.11	I
16	6279.43	II
30	6279.73	II
30	6473.54	I
60	6547.89	II
60	6558.36	II
30	6564.52	I
2 h	6636.44	II
1	6756.72	II
2	6757.13	II
30	6786.56	I
1 h	6884.22	I
6 h	6884.44	I
100	6982.75	I
6 h	7154.40	I
40 h	7154.65	I
100	7209.13	I
3	7401.20	II
2	7401.43	II
10	7551.90	I
10 h	7618.68	I
20 h	7618.88	I
60	8090.06	I
5 h	8158.99	I
10 h	8159.24	I
4	8254.07	I
10 h	8287.07	I
30	8547.36	I
60	8547.67	I
300	8801.37	I
6	8882.18	I
40	9190.45	I
20 h	9243.92	I
1 h	9343.89	II
40	9392.74	I
2	9476.43	II
16	9477.03	II
20	9847.32	I
10 h	9895.63	I
20 h	9895.96	I
80	9939.78	I
16	10095.52	II
20	10095.73	II
60	10119.92	II
80	10331.03	I
30	11066.46	I
	11173.	II
1	11173.73	II
120	11496.39	I
2 h	11625.16	II
	11659.	II
2	11660.25	II
100	12095.36	II
30	12098.18	II
100	14643.92	I
60	14644.75	I
200	16157.72	I
80	17855.38	I
120	17856.63	I
100	18143.54	I
160	31775.05	I
200	31778.70	I

Bismuth Bi Z = 83

6	420.7	IV
6	431.2	IV
2	488.39	V
3	563.62	V
5	670.76	III
6	686.88	V
5	730.71	V
10	738.17	V
4	775.16	III
6	790.5	IV
6	790.6	IV
8	792.5	IV
10	820.3	IV
9	822.9	IV
12	824.9	IV
15 d	864.45	V
15	872.6	IV
12	923.9	IV
15	943.3	IV
25	1039.99	III
50 h	1045.76	III
30	1051.81	III
15	1058.88	II
20	1085.47	II
10	1099.20	II
24	1103.4	IV
20	1139.01	III
50	1224.64	III
10	1225.43	II
15	1232.78	II
10	1241.05	II
10	1265.35	II
15	1283.73	II
10	1306.18	II
60	1317.0	IV
20	1325.46	II
40	1326.84	III
20	1329.47	II
60	1346.12	III
20	1350.07	II
25	1372.61	II
15	1376.02	II
20	1393.92	II
35	1423.33	III
35	1423.52	III
45	1436.83	II
25	1447.94	II
50	1455.11	II
60 h	1461.00	III
25	1462.14	II
35	1486.93	II
20	1502.50	II
40	1520.57	II

Intensity	Wavelength/Å	
40	1533.17	II
30	1536.77	II
35	1538.06	II
20	1563.67	II
40	1573.70	II
60	1591.79	II
25	1601.58	II
60 h	1606.40	III
40	1609.70	II
40	1611.38	II
20	1652.81	II
20	1749.29	II
80	1777.11	II
60	1787.47	II
70	1791.93	II
70	1823.80	II
100	1902.41	II
9000	1954.53	I
7000	1960.13	I
25	1989.35	II
7000	2021.21	I
9000	2061.70	I
45 h	2068.9	II
4600	2110.26	I
2500	2133.63	I
15	2143.40	II
15	2143.46	II
60	2186.9	II
40 h	2214.0	II
360	2228.25	I
1700	2230.61	I
340	2276.58	I
100	2311.	IV
100	2326.	IV
16	2368.12	II
12	2368.25	II
100	2376.	IV
190	2400.88	I
75 h	2414.6	III
10	2501.0	II
25	2515.69	I
70	2524.49	I
20 h	2544.5	II
700	2627.91	I
100	2629.	IV
100	2677.	IV
12	2693.0	II
280 c	2696.76	I
20	2713.3	II
140 d	2730.50	I
100	2767.	IV
100	2772.	IV
360	2780.52	I
100	2786.	IV
15	2803.42	II
11	2803.70	II
12	2805.3	II
140 c	2809.62	I
100	2842.	IV
80 h	2855.6	III
4000	2897.98	I
100	2924.	IV
100	2933.	IV
100	2936.	IV
15	2936.7	II
3200	2938.30	I
20	2950.4	II
12	2963.4	II
2800	2989.03	I
700	2993.34	I
100	3012.	IV
2400	3024.64	I
60	3034.87	I
100	3042.	IV
9000 c	3067.72	I
140	3076.66	I
35	3115.0	III
100	3239.	IV
550 c	3397.21	I
10	3430.83	II
12	3431.23	II
40 h	3451.0	III
40	3473.8	III
35	3485.5	III
500 c	3510.85	I
380 c	3596.11	I
45	3613.4	III
100	3643.	IV
12	3654.2	II
100	3682.	IV
50	3695.32	III
50	3695.68	III
100	3734.	IV
70 h	3792.5	II
12	3811.1	II
20	3815.8	II
10	3845.8	II
30	3863.9	II
100	3868.	IV
40 h	4079.1	II
10	4097.2	II
140	4121.53	I
140	4121.86	I
75 h	4259.4	II
25	4272.0	II
70 h	4301.7	II
12 h	4339.8	II
25 h	4340.5	II
12 h	4379.4	II
25 h	4476.8	II
60 h	4705.3	II
600 c	4722.52	I
30	4730.3	II
20	4749.7	II
40 h	4797.4	III
12	4908.2	II
10	4916.6	II
12	4969.7	II
20	4993.6	II
45 h	5079.3	III
10	5091.6	II
50 h	5124.3	II
60 h	5144.3	II
20	5201.5	II
75 h	5209.2	II
40 h	5270.3	II
10	5397.8	II
10 c	5552.35	I
3	5599.41	I
20	5655.2	II
40 h	5719.2	II
6	5742.55	I
12	5818.3	II
20	5860.2	II
20	5973.0	II
15	6059.1	II
15	6128.0	II
6	6134.82	I
3	6475.73	I
3	6476.24	I
15	6497.7	II
10	6577.2	II
40 h	6600.2	II
50 h	6808.6	II
4 h	6991.12	I
12	7033.	II
2	7036.15	I
10 h	7381.	II
2	7502.33	I
10 h	7637.	II
10	7750.	II
3	7838.70	I
2	7840.33	I
20	7965.	II
40	8008.	III
12 h	8050.	II
50	8070.	III
15	8328.	II
15	8388.	II
30	8532.	II
2	8544.54	I
1	8579.74	I
25	8653.	II
2	8754.88	I
3	8761.54	I
25	8863.	II
2	8907.81	I
2000 d	9657.04	I
40	9827.78	I
20	10104.5	I
15	10138.8	I
20	10300.6	I
20	10536.19	I
50	11072.44	I
1500 d	11710.37	I
40	11999.49	I
200	12165.08	I
200	12690.04	I
100	12817.8	I
200	14330.5	I
50	16001.5	I
60	22551.6	I

Intensity	Wavelength/Å	
Boron B Z = 5		
	41.00	V
30	48.59	V
10	52.68	IV
30	60.31	IV
	194.37	V
	262.37	V
160	344.0	IV
450	385.0	IV
40	411.80	III
285	418.7	IV
20	510.77	III
40	510.85	III
	512.53	V
150	518.24	III
75	518.27	III
110	677.00	III
160	677.14	III
40	693.95	II
40	731.36	II
40	731.44	II
	749.74	V
40	758.48	III
70	758.67	III
110	882.54	II
110	882.68	II
40	984.67	II
110	1081.88	II
110	1082.07	II
70	1112.2	IV
450	1168.9	IV
70	1170.9	IV
110	1230.16	II
220	1362.46	II
70	1600.46	I
120	1600.73	I
160	1623.58	II
110	1623.77	II
220	1624.02	II
70	1624.16	II
160	1624.34	II
100	1663.04	I
150	1666.87	I
200	1667.29	I
150	1817.86	I
200	1818.37	I
300	1825.91	I
300	1826.41	I
110	1842.81	II
20	1953.83	III
550	2065.78	III
250	2066.38	I
250	2066.65	I
100	2066.93	I
300	2067.19	I
450	2067.23	III
160	2077.09	III
500	2088.91	I
500	2089.57	I
70	2220.30	II
40	2234.09	III

Intensity	Wavelength/Å	
70	2234.59	III
40	2323.03	II
40	2328.67	II
40	2393.20	II
220	2395.05	II
40	2459.69	II
40	2459.90	II
1000	2496.77	I
1000	2497.73	I
70	2524.7	IV
160	2530.3	IV
450	2821.68	IV
70	2824.57	IV
285	2825.85	IV
160	2918.08	II
110	3032.26	II
70	3179.33	II
110	3323.18	II
110	3323.60	II
450	3451.29	II
285	4121.93	II
110	4194.79	II
40	4242.98	III
70	4243.61	III
110	4472.10	II
110	4472.85	II
220	4487.05	III
360	4497.73	III
70	4784.21	II
110	4940.38	II
110	6080.44	II
70	6285.47	II
70	7030.20	II
40	7031.90	II
110	7835.25	III
70	7841.41	III
20	8667.22	I
70	8668.57	I
800	11660.04	I
570	11662.47	I
125	15629.08	I
200	16240.38	I
250	16244.67	I
235	18994.33	I

Bromine Br Z = 35

700	379.73	IV
700	400.37	IV
800	482.11	V
900	531.97	V
1000	545.43	IV
1000	547.90	V
1000	559.76	IV
1000	569.19	IV
1000	576.59	IV
1000	585.10	IV
1000	586.71	IV
1000	597.51	IV
1000	600.09	IV
1000	601.27	IV
1000	607.03	IV
1000	617.85	IV

Intensity	Wavelength/Å	
1000	619.87	IV
1000	630.14	IV
1000	642.23	IV
1000	661.53	IV
1000	683.51	IV
1000	697.72	IV
1000	715.39	IV
1000	731.00	IV
1000	800.12	IV
700	812.95	V
1000	813.66	IV
1000	850.81	V
1000	889.23	II
1000	948.97	II
1000	1015.54	II
1000	1049.00	II
1000	1069.15	V
900	1112.13	V
1000	1143.56	V
1000	1189.28	I
1000	1189.50	I
1000	1210.73	I
1000	1221.13	I
1000	1223.24	I
1200	1224.41	I
1200	1226.90	I
7500	1232.43	I
1200	1243.90	I
1500	1251.66	I
1000	1255.80	I
1500	1259.20	I
1200	1261.66	I
1200	1266.20	I
1000	1279.48	I
1000	1286.26	I
3000	1309.91	I
3000	1316.74	I
1000	1317.37	I
2000	1317.70	I
12000	1384.60	I
3000	1449.90	I
50000	1488.45	I
30000	1531.74	I
25000	1540.65	I
30000	1574.84	I
20000	1576.39	I
25000	1582.31	I
75000	1633.40	I
1000	2133.79	IV
1000	2145.02	IV
1000	2257.21	IV
1000	2272.73	IV
1000	2307.40	IV
1000	2408.16	IV
1000	2411.58	IV
700	2491.14	IV
1000	2581.19	IV
600	2661.40	IV
1000	2842.88	IV
1100 h	2907.71	IV
500 h	2972.26	II

Intensity	Wavelength/Å	
500	3041.18	IV
500	3074.42	III
500	3349.64	III
500	3380.56	IV
500	3540.16	III
500	3562.43	III
1200	3815.65	I
1500	3992.36	I
1000	4223.89	II
2000	4365.14	I
1000	4365.60	II
1500	4425.14	I
10000	4441.74	I
10000	4472.61	I
20000	4477.72	I
1000	4490.42	I
3000	4513.44	I
15000	4525.59	I
3000	4575.74	I
2500	4614.58	I
2500	4752.28	I
4000	4780.31	I
1600	4785.19	I
4000	4979.76	I
1200	5395.48	I
1200	5466.22	I
1800	5852.08	I
1600	5940.48	I
2400	6122.14	I
40000	6148.60	I
2000	6177.39	I
1500	6335.48	I
60000	6350.73	I
2500	6410.32	I
1800	6483.56	I
1000	6514.62	I
20000	6544.57	I
1500	6548.09	I
50000 c	6559.80	I
1000	6571.31	I
1800	6579.14	I
20000	6582.17	I
1500	6620.47	I
50000 c	6631.62	I
20000	6682.28	I
10000	6692.13	I
8000	6728.28	I
2000	6760.06	I
2000	6779.48	I
2200	6786.74	I
6500	6790.04	I
1600 c	6791.48	I
1800	6861.15	I
10000	7005.19	I
2000	7260.45	I
10000	7348.51	I
40000	7512.96	I
1600	7591.61	I
1800	7595.07	I
2000	7616.41	I
30000	7803.02	I

Intensity	Wavelength/Å	
1200	7827.23	I
2500 s	7881.45	I
2500	7881.57	I
2500	7925.81	I
30000 c	7938.68	I
3000	7947.94	I
3000	7950.18	I
8000	7978.44	I
10000	7978.57	I
30000	7989.94	I
2000	8026.35	I
2500	8026.54	I
30000	8131.52	I
1000 c	8152.65	I
10000	8153.75	I
25000	8154.00	I
5000	8246.86	I
15000	8264.96	I
75000 c	8272.44	I
20000	8334.70	I
10000	8343.70	I
1200	8384.04	I
40000	8446.55	I
4000	8477.45	I
1500	8513.38	I
1000	8557.73	I
1000	8566.28	I
20000	8638.66	I
4000	8698.53	I
10000 c	8793.47	I
15000	8819.96	I
25000	8825.22	I
4000	8888.98	I
30000	8897.62	I
6000	8932.40	I
1800	8949.39	I
9000	8964.00	I
30000	9166.06	I
15000	9173.63	I
20000	9178.16	I
40000	9265.42	I
15000	9320.86	I
6000	9793.48	I
10000	9896.40	I
3000	10140.08	I
6000	10237.74	I
1000	10299.62	I
1500	10377.65	I
30000	10457.96	I
1000	10742.14	I
3000	10755.92	I
1700	13217.17	I
1800	14354.57	I
1250	14888.70	I
1800	16731.19	I
1200	18568.31	I
3500	19733.62	I
1000	20281.73	I
1000	20624.67	I
1200	21787.24	I
4000	22865.65	I

Intensity	Wavelength/Å	
1000	23513.15	I
500	28346.50	I
500	30380.85	I
600	31630.13	I
150	38345.75	I
120	39964.36	I
Cadmium Cd Z = 48		
50	427.01	IV
50	447.85	IV
60	480.90	IV
70	493.00	IV
70	495.13	IV
70	498.14	IV
70	498.53	IV
80	504.09	IV
70	504.20	IV
70	504.50	IV
80	506.31	IV
60	508.01	IV
50	508.95	IV
70	509.55	IV
70	511.40	IV
80	513.00	IV
70	514.50	IV
60	519.42	IV
80	524.41	IV
70	524.47	IV
70	525.10	IV
60	525.19	IV
70	527.07	IV
80	531.09	IV
80	531.51	IV
70	534.29	IV
70	536.77	IV
60	540.90	IV
70	541.74	IV
80	542.60	IV
80	546.55	IV
60	553.06	IV
80	554.05	IV
60	567.01	IV
150	1118.16	IV
100	1164.65	IV
100	1183.40	IV
100	1256.00	II
150	1296.43	II
100	1326.50	II
60	1370.48	IV
150	1370.91	II
60	1418.89	IV
200	1514.26	II
50	1545.17	III
200	1571.58	II
100	1668.60	II
50	1702.47	II
40	1707.16	III
40	1722.95	III
50	1724.41	II
40	1747.67	III
40	1773.06	III
100	1785.84	II
75	1793.40	III
40	1823.41	III
100	1827.70	II
50	1844.66	III
40	1851.13	III
40	1855.85	III
200	1856.67	III
150	1874.08	III
300	1922.23	II
100	1943.54	II
40	1965.54	II
30	1986.89	II
200	1995.43	II
100	2007.49	II
50	2032.45	II
75	2036.23	II
40	2039.83	III
50	2045.61	III
75	2087.91	III
150	2096.00	II
50	2111.60	III
1000 r	2144.41	II
50	2155.06	II
100	2187.79	II
1000	2194.56	II
1000	2265.02	II
1500 r	2288.022	I
1000	2312.77	II
200	2321.07	II
40	2376.82	II
50	2418.69	II
50	2469.73	II
40	2487.93	II
40	2495.58	II
50	2509.11	II
30	2516.22	II
25 h	2525.196	I
50	2544.613	I
50	2551.98	II
25	2553.465	I
3	2565.789	I
500	2572.93	II
50	2580.106	I
30	2592.026	I
25 h	2602.048	I
50	2628.979	I
40	2632.190	I
75	2639.420	I
40	2659.23	II
50 h	2660.325	I
25	2668.20	II
50	2672.62	II
100	2677.540	I
25	2677.748	I
50	2707.00	II
75	2712.505	I
50	2733.820	I
1000	2748.54	II
100 h	2763.894	I
50 h	2764.230	I
50	2774.958	I
30	2823.19	II
200	2836.900	I
25	2856.46	II
100	2868.180	I
200 r	2880.767	I
50 r	2881.224	I
200	2914.67	II
50	2927.87	II
200	2929.27	II
1000 r	2980.620	I
200 r	2981.362	I
50	2981.845	I
50	3030.60	II
150	3080.822	I
25	3081.48	II
30	3082.593	I
100	3092.34	II
200	3133.167	I
50	3146.79	II
150	3250.33	II
300	3252.524	I
300	3261.055	I
50	3343.21	II
50	3385.49	II
30	3388.88	II
800	3403.652	I
50	3417.49	II
50	3442.42	II
100	3464.43	II
1000	3466.200	I
800	3467.655	I
25	3483.08	II
150	3495.44	II
25	3499.952	I
100	3524.11	II
100	3535.69	II
1000	3610.508	I
800	3612.873	I
60	3614.453	I
20	3649.558	I
10	3981.926	I
100	4029.12	II
200	4134.77	II
50	4141.49	II
100	4285.08	II
8	4306.672	I
100	4412.41	II
3	4412.989	I
1000	4415.63	II
30	4440.45	II
8	4662.352	I
200	4678.149	I
30	4744.69	II
300	4799.912	I
50	4881.72	II
50	5025.50	II
1000 h	5085.822	I
6	5154.660	I
100	5268.01	II
100	5271.60	II
1000	5337.48	II
1000	5378.13	II
200	5381.89	II
40	5843.30	II
50	5880.22	II
300	6099.142	I
100	6111.49	I
100	6325.166	I
30	6330.013	I
400	6354.72	II
500	6359.98	II
2000	6438.470	I
400	6464.94	II
25	6567.65	II
500	6725.78	II
100	6759.19	II
30	6778.116	I
50	7237.01	II
100	7284.38	II
1000	7345.670	I
50	8066.99	II
5	8200.309	I
20	9289.	I
15	11652.	I
35	14487.	I
80	15708.	I
55 d	19120.	I
25	24371.	I
35	25448.	I
Calcium Ca Z = 20		
250	190.46	V
250	196.97	V
300	199.55	V
250	200.51	V
265	257.98	V
400	267.77	V
300	270.31	V
400	280.99	V
300	284.98	V
450 c	286.96	V
500	322.17	V
300	323.22	V
300	330.94	V
300	334.55	V
250 c	342.45	IV
250	343.93	IV
450	352.92	V
250	377.18	V
200	387.08	V
750	425.00	V
600	434.57	IV
250	437.77	IV
750	443.82	IV
500	450.57	IV
500	558.60	V
400	637.93	V
300	643.12	V
400	646.57	V
750	656.00	IV
300	656.76	V
500	669.70	IV
24	1341.89	II

Intensity	Wavelength/Å	
12	1342.54	II
20	1433.75	II
20	1545.29	III
60	1649.86	II
20	1807.34	II
40	1814.50	II
40	1838.01	II
60	1840.06	II
20	1843.09	II
40	1850.69	II
17	2123.03	III
16	2152.43	III
16	2687.76	III
19	2881.78	III
21	2899.79	III
19	2924.33	III
20	2988.63	III
10	3006.86	I
15	3028.59	III
3	3055.32	I
19	3119.67	III
170	3158.87	II
180	3179.33	II
150	3181.28	II
20	3316.51	II
12	3361.92	I
19	3372.67	III
20	3461.87	II
13	3487.60	I
18	3537.77	III
20	3644.41	I
30	3683.70	II
40	3694.11	II
170	3706.03	II
180	3736.90	II
20	3755.67	II
30	3758.39	II
230	3933.66	II
220	3968.47	II
50	4097.10	II
60	4109.82	II
30	4110.28	II
40	4206.18	II
50	4220.07	II
50	4226.73	I
24	4283.01	I
22	4289.36	I
22	4298.99	I
25	4302.53	I
20	4302.81	III
23	4307.74	I
22	4318.65	I
20	4355.08	I
19	4399.59	III
25	4425.44	I
26	4434.96	I
25	4435.69	I
30	4454.78	I
28	4455.89	I
20	4456.61	I
20	4472.04	II
20	4489.18	II
19	4499.88	III
23	4526.94	I
22	4578.55	I
23	4581.40	I
23	4581.47	I
24	4585.87	I
24	4585.96	I
20	4685.27	I
30	4716.74	II
40	4721.03	II
40	4799.97	II
25	4878.13	I
70	5001.48	II
80	5019.97	II
40	5021.14	II
23	5041.62	I
25	5188.85	I
22	5261.71	I
23	5262.24	I
22	5264.24	I
24	5265.56	I
25	5270.27	I
60	5285.27	II
70	5307.22	II
50	5339.19	II
27	5349.47	I
23	5512.98	I
25	5581.97	I
27	5588.76	I
24	5590.12	I
26	5594.47	I
25	5598.49	I
24	5601.29	I
24	5602.85	I
30	5857.45	I
27	6102.72	I
29	6122.22	I
22	6161.29	I
30	6162.17	I
22	6163.76	I
24	6166.44	I
26	6169.06	I
28	6169.56	I
35	6439.07	I
30	6449.81	I
22	6455.60	I
80	6456.87	II
34	6462.57	I
29	6471.66	I
32	6493.78	I
28	6499.65	I
23	6572.78	I
30	6717.69	I
33	7148.15	I
31	7202.19	I
33	7326.15	I
30	7575.81	II
60	7581.11	II
80	7601.30	II
20	7602.32	II
40	7820.78	II
60	7843.38	II
20	8017.50	II
20	8020.50	II
70	8133.05	II
100	8201.72	II
110	8248.80	II
70	8254.73	II
130	8498.02	II
170	8542.09	II
160	8662.14	II
100	8912.07	II
110	8927.36	II
110	9213.90	II
90	9312.00	II
100	9319.56	II
110	9320.65	II
25	9416.97	I
100	9567.97	II
110	9599.24	II
80	9601.82	II
80	9854.74	II
110	9890.63	II
90	9931.39	II
100	10223.04	II
20	10343.81	I
20	11838.99	II
25	12816.04	I
24	12823.86	I
25	12909.10	I
30	13033.57	I
21	13086.44	I
24	13134.95	I
20	16150.77	I
22	16157.36	I
21	16197.04	I
20	18925.47	I
24	18970.14	I
30	19046.14	I
48	19309.20	I
49	19452.99	I
47	19505.72	I
50	19776.79	I
35	19853.10	I
34	19862.22	I
23	19917.19	I
24	19933.70	I
25	22624.93	I
30	22651.23	I

Carbon C Z = 6

110	34.973	V
450	40.268	V
110	227.19	V
250	244.91	IV
160	248.66	V
160	248.74	V
200	289.14	IV
250	289.23	IV
570	312.42	IV
500	312.46	IV
250	371.69	III
250	371.75	III
150	371.78	III
650	384.03	IV
700	384.18	IV
500	386.203	III
400	419.52	IV
500	419.71	IV
200	450.734	III
400	459.46	III
500	459.52	III
570	459.63	III
250	511.522	III
250	535.288	III
300	538.080	III
350	538.149	III
400	538.312	III
350	574.281	III
9	595.022	II
30	687.053	II
50	687.345	II
10	858.092	II
20	858.559	II
30	903.624	II
60	903.962	II
150	904.142	II
30	904.480	II
800	977.03	III
9	1009.86	II
10	1010.08	II
10	1010.37	II
80	1036.337	II
150	1037.018	II
150	1157.910	I
150	1158.019	I
150	1158.035	I
370	1174.93	III
350	1175.26	III
330	1175.59	III
500	1175.71	III
350	1175.99	III
370	1176.37	III
150	1188.992	I
150	1189.447	I
200	1189.631	I
300	1193.009	I
300	1193.031	I
300	1193.240	I
300	1193.264	I
100	1193.393	I
150	1193.649	I
150	1193.679	I
100	1194.064	I
100	1194.488	I
100	1261.552	I
250	1277.245	I
250	1277.282	I
300	1277.513	I
300	1277.550	I
200	1280.333	I
100	1311.363	I
9	1323.951	II

Intensity	Wavelength/Å	
120	1329.578	I
120	1329.600	I
150	1334.532	II
300	1335.708	II
100	1354.288	I
150	1355.84	I
120	1364.164	I
100	1459.032	I
200	1463.336	I
120	1467.402	I
150	1481.764	I
1000	1548.202	IV
900	1550.774	IV
150	1560.310	I
400	1560.683	I
400	1560.708	I
100	1561.341	I
400	1561.438	I
150	1656.266	I
120	1656.928	I
300	1657.008	I
120	1657.380	I
120	1657.907	I
150	1658.122	I
500	1751.823	I
1000	1930.905	I
250	2162.94	III
40	2270.91	V
5	2277.25	V
20	2277.92	V
800	2296.87	III
800	2478.56	I
250	2509.12	II
350	2512.06	II
200 l	2524.41	IV
300 s	2529.98	IV
250 h	2574.83	II
150	2697.75	III
110 l	2724.85	III
150 l	2725.30	III
150 l	2725.90	III
350 l	2741.28	II
250	2746.49	II
1000	2836.71	II
800	2837.60	II
200	2982.11	III
800 h	2992.62	II
350	3876.19	II
350	3876.41	II
350	3876.66	II
570	3918.98	II
800	3920.69	II
150	4056.06	III
200	4067.94	III
250	4068.91	III
250	4070.26	III
250	4074.52	II
350 l	4075.85	II
150	4162.86	III
250 h	4186.90	III
800	4267.00	II
1000	4267.26	II
200	4325.56	III
600	4647.42	III
520	4650.25	III
375	4651.47	III
200 w	4658.30	IV
200	4665.86	III
200	4771.75	I
200	4932.05	I
5	4943.88	V
5	4944.56	V
200	5052.17	I
350	5132.94	II
350	5133.28	II
350	5143.49	II
570	5145.16	II
400	5151.09	II
300	5380.34	I
250	5648.07	II
350	5662.47	II
450	5695.92	III
250	5801.33	IV
200	5811.98	IV
150	5826.42	III
570	5889.77	II
350	5891.59	II
200	6001.13	I
250	6006.03	I
110	6007.18	I
150	6010.68	I
300	6013.22	I
250	6014.84	I
800	6578.05	II
570	6582.88	II
200	6587.61	I
150	6744.38	III
250	6783.90	II
150 h	7037.25	III
250	7113.18	I
250	7115.19	I
250	7115.63	II
200	7116.99	I
350	7119.90	II
800	7231.32	II
1000	7236.42	II
150	7612.65	III
90 w	7726.2	IV
200	7860.89	I
200	8058.62	I
300 h	8196.48	III
150	8332.99	III
520	8335.15	I
300	8500.32	III
250	9061.43	I
200	9062.47	I
200	9078.28	I
250	9088.51	I
450	9094.83	I
300	9111.80	I
800	9405.73	I
150	9603.03	I
250	9620.80	I
300	9658.44	I
200	10683.08	I
300	10691.25	I
12	11619.29	I
23	11628.83	I
13	11658.85	I
47	11659.68	I
24	11669.63	I
85	11748.22	I
142	11753.32	I
114	11754.76	I
11	11777.54	I
17	11892.91	I
30	11895.75	I
26	12614.10	I
20	13502.27	I
38	14399.65	I
16	14403.25	I
61	14420.12	I
12	14429.03	I
13	14442.24	I
12	16559.66	I
50	16890.38	I
10	17338.56	I
11	17448.60	I
13	18139.80	I
23	19721.99	I

Cerium Ce Z = 58

300	399.36	V
200	482.96	V
40	741.79	IV
30	754.60	IV
75	1332.16	IV
75	1372.72	IV
100	2000.42	IV
100	2009.94	IV
10000	2318.64	III
10000	2372.34	III
10000	2380.12	III
10000	2431.45	III
15000	2439.80	III
10000	2454.32	III
10000	2469.95	III
10000	2483.82	III
10000	2497.50	III
20000	2531.99	III
10000	2603.59	III
340	2651.01	II
270	2830.90	II
250	2874.14	II
10000	2923.81	III
10000	2931.54	III
400	2976.91	II
10000	3022.75	III
50000	3031.58	III
95000	3055.59	III
20000	3056.56	III
40000	3057.23	III
20000	3057.58	III
680	3063.01	II
40000	3085.10	III
20000	3106.98	III
30000	3110.53	III
30000	3121.56	III
20000	3141.29	III
20000	3143.96	III
20000	3147.06	III
710	3194.83	II
990	3201.71	II
710	3218.94	II
880	3221.17	II
710	3227.11	II
20000	3228.57	III
710	3234.16	II
990	3272.25	II
20000	3353.29	III
10000	3395.77	III
30000	3427.36	III
40000	3443.63	III
30000	3454.39	III
40000	3459.39	III
60000	3470.92	III
710	3485.05	II
50000	3497.81	III
60000	3504.64	III
770	3539.08	II
50000	3544.07	III
1200	3560.80	II
1000	3577.45	II
1800	3655.85	II
880	3660.64	II
880	3667.98	II
1000	3709.29	II
1000	3709.93	II
1400	3716.37	II
800	3728.42	II
860	3786.63	II
2500	3801.52	II
800	3803.09	II
1000	3808.11	II
1100	3838.54	II
860	3848.59	II
860	3853.15	II
1200	3854.18	II
1200	3854.31	II
1100	3878.36	II
1500	3882.45	II
1000	3889.98	II
770	3907.29	II
980	3912.44	II
770	3918.28	II
770	3931.09	II
770	3940.34	II
2000	3942.15	II
2700	3942.75	II
770	3943.89	II
3100	3952.54	II
980	3956.28	II
770	3960.91	II
770	3967.05	II
770	3978.65	II

Intensity	Wavelength/Å	
770	3984.68	II
700	3992.39	II
910	3993.82	II
2800	3999.24	II
910	4003.77	II
2700	4012.39	II
910	4014.90	II
840	4024.49	II
840	4028.41	II
840	4031.34	II
2100	4040.76	II
910	4042.58	II
700	4053.51	II
1100	4071.81	II
1800	4073.48	II
1500	4075.71	II
1500	4075.85	II
910	4083.23	II
770	4118.14	II
980	4123.87	II
980	4127.37	II
2700	4133.80	II
2000	4137.65	II
770	4142.40	II
980	4149.94	II
1400	4151.97	II
1300	4165.61	II
3500	4186.60	II
840	4198.72	II
910	4202.94	II
1500	4222.60	II
770	4227.75	II
980	4239.92	II
1100	4248.68	II
2000	4289.94	II
1500	4296.67	II
770	4300.33	II
770	4306.72	II
980	4337.77	II
700	4349.79	II
910	4364.66	II
910	4382.17	II
700	4386.84	II
1700	4391.66	II
980	4418.78	II
770	4449.34	II
2400	4460.21	II
1400	4471.24	II
700	4479.36	II
700	4483.90	II
840	4486.91	II
770	4523.08	II
840	4527.35	II
840	4528.47	II
840	4539.75	II
2100	4562.36	II
1100	4572.28	II
840	4593.93	II
1700	4628.16	II
310	4737.28	II
470	5079.68	II
280	5159.69	I
280	5161.48	I
370	5187.46	II
260	5223.46	I
260	5245.92	I
340	5274.23	II
450	5353.53	II
300	5393.40	II
280	5409.23	II
260	5512.08	II
300	5696.99	I
370	5699.23	I
240	5719.03	I
230	5940.86	I
55	6001.90	I
55	6005.86	I
55	6006.82	I
75	6013.42	I
110	6024.20	I
10000	6032.54	III
110	6043.39	II
55	6047.40	I
10000	6060.91	III
45	6098.34	II
45	6123.67	I
35	6143.36	II
35	6186.17	I
35	6208.98	I
35	6228.94	I
23	6232.45	II
28	6237.45	I
45	6272.05	II
35	6295.58	I
28	6299.51	II
23	6300.21	I
35	6310.01	I
35	6343.95	II
35	6371.11	II
28	6386.84	I
23	6393.02	II
35	6430.07	I
23	6436.40	I
35	6458.03	I
28	6467.39	I
35	6473.72	I
23	6513.59	II
45	6555.65	I
23	6579.10	I
22	6612.06	I
30	6628.93	I
22	6652.72	II
26	6700.66	I
35	6704.27	I
30	6774.28	II
35	6775.59	I
30	6924.81	I
30	6986.02	I
35	7061.75	II
35	7086.35	II
22	7238.36	II
25	7252.75	I
25	7329.91	I
25	7397.77	I
25	7616.11	II
25	7689.17	II
22	7844.94	II
22	7857.54	II
30	8025.56	II
25	8772.14	II
30	8891.20	II

Cesium Ce Z = 55

10000	614.01	III
2000	638.17	III
2500	666.25	III
5000	691.60	III
3500	703.89	III
15000	718.14	II
20000	721.79	III
20000	722.20	III
5000	731.56	III
12000	740.29	III
15000	808.76	II
15000	813.84	II
7500	830.39	III
35000	901.27	II
15000	920.35	III
40000	926.66	II
25000 c	1054.79	III
17 c	1673.99	III
12	1705.25	III
10	1801.83	III
20 c	1822.40	III
11	1823.93	III
12	1824.70	III
12	1841.80	III
25	1915.50	III
25 c	1923.29	III
12	1961.33	III
17	1996.56	III
710	2035.11	III
120	2056.43	III
330	2076.43	III
540	2077.30	III
410	2088.68	III
210	2101.63	III
200	2141.47	III
1000	2316.88	III
230	2325.95	III
390	2340.49	III
1600	2455.81	III
1600	2477.57	III
890	2485.45	III
410	2495.07	III
1400	2525.67	III
430	2573.05	III
16000	2596.86	III
390	2610.12	III
6200	2630.51	III
370	2700.32	III
710	2701.20	III
390	2776.44	III
270	2810.87	III
630	2845.70	III
3100	2859.32	III
200	2893.85	III
180	2921.13	III
3200	2976.86	III
210	3001.28	III
1700	3066.59	III
1100 c	3149.36	III
1400	3152.36	III
8400	3268.32	III
1300	3315.51	III
550	3340.60	III
430	3344.02	III
1200	3349.46	III
400	3463.45	III
580	3476.83	III
480	3559.82	III
7200	3597.45	III
1300	3608.31	III
2300	3618.19	III
300 c	3641.34	III
520	3651.08	III
4800	3661.40	III
640	3699.50	III
430	3837.46	III
2100 c	3876.15	I
2900	3888.37	III
600 c	3888.61	I
2700	3925.60	III
680 c	4001.70	III
3100	4006.55	III
420	4006.78	III
520	4043.42	III
14000	4264.70	II
18000 w	4277.13	II
370	4403.86	III
1200	4410.22	III
940	4425.68	III
530	4471.48	III
12000	4501.55	II
1200	4506.72	III
590	4522.86	III
20000	4526.74	II
1000 c	4555.28	I
460 c	4593.17	I
99900	4603.79	II
420 h	4620.61	III
210	4665.52	III
25000	4830.19	II
140	4851.59	III
19000	4870.04	II
37000	4952.85	II
370	5035.72	III
27000	5043.80	II
75000	5227.04	II
29000	5249.38	II
11000	5274.05	II
10000 c	5349.13	II
22000	5370.99	II
230	5380.79	III
60 c	5465.94	I

Intensity	Wavelength/Å	
37	5502.88	I
39000	5563.02	II
100	5635.21	I
210 c	5664.02	I
27	5745.72	I
24000	5831.14	II
59 c	5838.83	I
300	5845.14	I
51000	5925.63	II
140	5950.14	III
110	5979.97	III
640 c	6010.49	I
86	6034.09	I
150	6043.99	III
870	6079.86	III
9800	6128.61	II
330	6150.42	III
1000	6213.10	I
170	6217.60	I
450	6242.96	III
320 c	6354.55	I
510	6456.33	III
8300	6495.53	II
10000 w	6536.44	II
490	6586.51	I
97	6628.66	I
8800	6646.57	II
3300 c	6723.28	I
9600	6724.47	II
400	6753.12	III
200	6824.65	I
300	6870.45	I
37000	6955.50	II
4800	6973.30	I
16000	6979.67	II
980	6983.49	I
13000 w	7149.54	II
1900 c	7219.60	III
790	7228.53	I
130	7279.90	I
1100	7279.96	I
2600 c	7608.90	I
3300	7943.88	I
22000	7997.44	II
3500	8015.73	I
510	8078.94	I
4500	8079.04	I
59000 c	8521.13	I
15000 c	8761.41	I
61000 c	8943.47	I
18000	9172.32	I
5200	9208.53	I
19000	10024.36	I
4800	10123.41	I
26000	10123.60	I
2900	13424.31	I
38000 c	13588.29	I
8400	13602.56	I
5700	13758.81	I
55000 c	14694.91	I
820	16535.63	I
1500	17012.32	I
760	20138.47	I
880	22811.86	I
1100	23037.98	I
3900	23344.47	I
4400	24251.21	I
850	24374.96	I
890 d	25763.51	I
500	25764.73	I
680 c	29310.06	I
2800	30103.27	I
610 c	30953.06	I
1100	34900.13	I
190	36131.00	I
2 c	39177.28	I
2 d	39421.25	I
1	39424.11	I
Chlorine Cl Z = 17		
500	392.43	V
800	486.17	IV
800	534.73	IV
700	535.67	IV
600	536.15	IV
900	537.61	IV
500	538.03	V
600	538.12	IV
800	542.23	V
600	542.30	V
1000	545.11	V
600	546.33	V
1000	547.63	V
500	549.22	IV
700	552.02	IV
600	553.30	IV
700	554.62	IV
600	556.23	III
700	556.61	III
700	557.12	III
350	559.305	II
700	561.53	III
700	561.68	III
700	561.74	III
400	571.904	II
800	574.406	II
500	601.50	IV
500	604.59	IV
500	606.35	III
700	618.057	II
600	619.982	II
800	620.298	II
700	626.735	II
800	635.881	II
1000	636.626	II
1000	650.894	II
1000	659.811	II
1300	661.841	II
2000	663.074	II
1500	682.053	II
1500	687.656	II
1500	693.594	II
2000	725.271	II
2500	728.951	II
2000	777.562	II
5000	787.580	II
5000	788.740	II
5000	793.342	II
500	834.84	IV
500	834.97	IV
6000	839.297	II
8000	839.599	II
600	840.93	IV
5000	851.691	II
2000	888.026	II
2000	893.549	II
2000	961.499	II
500	973.21	IV
600	977.56	IV
40	978.284	I
700	984.95	IV
25	998.372	I
25	998.432	I
75	1002.346	I
500	1005.28	III
600	1008.78	III
150	1013.664	I
700	1015.02	III
90	1025.553	I
6000	1063.831	II
3000	1067.945	II
9000	1071.036	II
6000	1071.767	II
5000	1075.230	II
5000	1079.080	II
200	1084.667	I
200	1085.171	I
250	1085.304	I
400	1088.06	I
350	1090.271	I
250	1090.982	I
250	1092.437	I
400	1094.769	I
350	1095.148	I
350	1095.662	I
400	1095.797	I
250	1096.810	I
300	1097.369	I
200	1098.068	I
200	1099.523	I
500	1107.528	I
800	1139.214	II
800	1167.148	I
3000	1179.293	I
1200	1188.774	I
900	1201.353	I
3000	1335.726	I
10000	1347.240	I
5000	1351.657	I
12000	1363.447	I
2500	1373.116	I
20000	1379.528	I
25000	1389.693	I
20000	1389.957	I
12000	1396.527	I
500	1441.470	II
500	1528.569	II
500	1542.942	II
500	1558.144	II
500	1565.050	II
600	1822.50	III
500	1828.40	III
500	1857.488	II
500	1901.61	III
500	1983.61	III
450 h	1997.370	II
450	2032.116	II
350 h	2088.583	II
350 h	2091.458	II
700	2253.07	III
500	2268.95	III
500	2278.34	III
700	2283.93	III
600	2323.50	III
500	2336.45	III
600	2340.64	III
600	2359.67	III
600	2370.37	III
700	2416.42	III
600	2447.14	III
600	2448.58	III
500	2486.91	III
500	2532.48	III
600	2580.67	III
500	2603.59	III
500	2632.67	III
500	2633.18	III
600	2665.54	III
700	2710.37	III
500	2724.03	IV
500	2751.23	IV
700	2782.47	IV
600	2965.56	III
500	3063.13	IV
600	3076.68	IV
600	3104.46	III
800	3139.34	III
900	3191.45	III
700	3289.80	III
700	3320.57	III
800	3329.06	III
900	3340.42	III
800	3392.89	III
800	3393.45	III
900	3530.03	III
800	3560.68	III
900	3602.10	III
800	3612.85	III
700	3622.69	III
700	3656.95	III
700	3670.28	III
700	3682.05	III
600	3705.45	III
600	3707.34	III
800	3720.45	III

Intensity	Wavelength/Å	
800	3748.81	III
500	3779.35	III
10000	3850.99	II
25000	3860.83	II
500	3925.87	III
700	3991.50	III
600	4018.50	III
600	4059.07	III
500	4104.23	III
500	4106.83	III
10000 h	4132.50	II
500	4608.21	III
40	4623.938	I
50	4654.040	I
80	4661.208	I
45	4691.523	I
40	4721.255	I
45	4740.729	I
13000	4781.32	II
99000	4794.55	II
29000	4810.06	II
16000	4819.47	II
81000	4896.77	II
47000	4904.78	II
26000	4917.73	II
10000	4995.48	II
26000	5078.26	II
30	5099.789	I
56000	5217.94	II
23000	5221.36	II
15000	5392.12	II
99000	5423.23	II
10000	5423.51	II
19000	5443.37	II
10000	5444.21	II
40	5532.162	I
50 d	5796.305	I
45	5799.914	I
30	5856.742	I
50	6019.812	I
200	6140.245	I
160	6194.757	I
150	6434.833	I
300	6932.903	I
300	6981.886	I
600	7086.814	I
7500	7256.62	I
5000	7414.11	I
550	7462.370	I
550	7489.47	I
700	7492.118	I
11000	7547.072	I
2300	7672.42	I
450	7702.828	I
7000	7717.581	I
10000	7744.97	I
2200	7769.16	I
650	7771.09	I
2200	7821.36	I
1700	7830.75	I
3000	7878.22	I
2300	7899.31	I
1800	7915.08	I
3000	7924.645	I
2100	7933.89	I
1700	7935.012	I
650	7952.52	I
1500	7974.72	I
1300	7976.97	I
600	7980.60	I
2900	7997.85	I
2200	8015.61	I
1100	8023.33	I
400	8051.07	I
1700	8084.51	I
2200	8085.56	I
3000	8086.67	I
1300	8087.73	I
2500	8194.42	I
2200	8199.13	I
2200	8200.21	I
800	8203.78	I
18000	8212.04	I
3000	8220.45	I
20000	8221.74	I
18000	8333.31	I
99900	8375.94	I
400	8406.199	I
15000	8428.25	I
2200	8467.34	I
2200	8550.44	I
20000	8575.24	I
750	8578.02	I
75000	8585.97	I
450	8628.54	I
300	8641.71	I
3500	8686.26	I
2200	8912.92	I
3000	8948.06	I
2000	9038.982	I
2500	9045.43	I
1000	9069.656	I
2000	9073.17	I
7500	9121.15	I
3000	9191.731	I
500	9197.596	I
4000	9288.86	I
1500	9393.862	I
3500	9452.10	I
500	9486.964	I
1000	9584.801	I
3500	9592.22	I
250	9632.509	I
1000	9702.439	I
250	9744.426	I
200	9807.057	I
400	9875.970	I
331	10392.549	I
300	11123.05	I
269	11409.69	I
1000	11436.33	I
350	13243.8	I
310	13296.0	I
550	13346.8	I
525	13821.7	I
294	14931.7	I
269	15108.0	I
381	15465.1	I
1094	15520.3	I
1487	15730.1	I
2780	15869.7	I
277	15883.3	I
342	15928.9	I
735	15960.0	I
283	15970.5	I
259	16198.5	I
717	19755.3	I
100	24470.0	I
	39716.0	I
	40085.5	I
	40089.5	I
	40532.2	I

Chromium Cr Z = 24

100	438.62	V
100	464.02	V
100	620.66	IV
100	629.26	IV
80	630.30	IV
100	666.55	IV
100	693.92	IV
60	1030.47	III
100	1033.69	III
100	1036.03	III
80	1055.89	IV
80	1068.41	III
100	1116.48	V
150	1121.07	V
150	1127.63	V
100	1263.50	V
100	1417.42	IV
150	1465.86	V
150	1497.97	V
170	1519.03	V
220	1579.70	V
170	1591.72	V
150	1603.19	V
120	1672.66	IV
120	1758.51	IV
140	1802.72	IV
130	1812.41	IV
200	1837.44	V
140	1873.89	IV
140	1967.18	IV
120	1972.07	IV
19000	2055.52	II
14000	2061.49	II
8900	2065.42	II
200	2226.72	III
200	2235.91	III
150	2237.59	III
150	2244.10	III
150	2284.44	III
150	2324.88	III
130	2383.33	I
140	2408.62	I
170	2496.31	I
110	2502.53	I
190	2504.31	I
110	2516.92	I
390	2519.52	I
190	2527.12	I
160	2549.54	I
130	2560.69	I
150	2571.74	I
100	2577.65	I
380	2591.85	I
250	2653.59	II
250	2658.59	II
320	2663.42	II
440	2666.02	II
280	2668.71	II
350	2671.81	II
280	2672.83	II
1800	2677.16	II
320	2678.79	II
230	2687.09	II
280	2691.04	II
180	2698.41	II
180	2698.69	II
110	2701.99	I
140	2712.31	II
170	2722.75	II
420 h	2726.51	I
280 h	2731.91	I
170 h	2736.47	I
250	2743.64	II
110 h	2748.29	I
330	2748.98	II
390	2750.73	II
280	2751.87	II
110 h	2752.88	I
150	2757.10	I
350	2757.72	II
750	2762.59	II
750	2766.54	II
250 h	2769.92	I
610	2780.70	I
180	2822.37	II
180	2830.47	II
2500	2835.63	II
110	2840.02	II
1700	2843.25	II
1200	2849.84	II
120	2851.36	II
880	2855.68	II
610	2858.91	II
440	2860.93	II
790	2862.57	II
750	2865.11	II
610	2866.74	II
480	2867.65	II
210	2870.44	II
110	2871.63	I
160	2873.48	II

Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å	
320	2875.99	II	220	3197.08	II	110	3807.93	I	110	4374.16	I
230	2876.24	II	170	3209.18	II	180	3815.43	I	530	4384.98	I
180	2877.98	II	140	3217.40	II	180	3819.56	I	110	4458.54	I
120	2879.27	I	120	3245.54	I	130	3826.42	I	660	4496.86	I
170	2887.00	I	130	3251.84	I	130	3830.03	I	380	4526.47	I
700	2889.29	I	130	3257.82	I	380	3841.28	I	380	4530.74	I
370	2893.25	I	130	3339.80	II	190	3848.98	I	240	4535.72	I
190	2894.17	I	110	3342.59	II	140	3849.36	I	240	4540.50	I
210	2896.75	I	170	3358.50	II	290	3850.04	I	240	4540.72	I
180	2905.49	I	160	3360.30	II	140	3852.22	I	140	4544.62	I
260	2909.05	I	430	3368.05	II	190	3854.22	I	600	4545.96	I
260	2910.90	I	140	3382.68	II	110	3855.29	I	120	4565.51	I
250	2911.14	I	170	3403.32	II	140	3855.57	I	120	4571.68	I
480	2967.64	I	360	3408.76	II	260	3857.63	I	360	4580.06	I
480	2971.11	I	210	3421.21	II	660	3883.29	I	360	4591.39	I
210	2971.91	II	270	3422.74	II	570	3885.22	I	480	4600.75	I
480	2975.48	I	140	3433.31	II	380	3886.79	I	240	4613.37	I
190	2979.74	II	270	3433.60	I	260	3894.04	I	600	4616.14	I
350	2980.79	I	160	3436.19	I	360	3902.92	I	550	4626.19	I
110	2985.32	II	140	3441.44	I	960	3908.76	I	1600	4646.17	I
480	2985.85	I	170	3445.62	I	120 hd	3911.82	I	570	4651.28	I
1500	2986.00	I	170	3447.43	I	120	3915.84	I	840	4652.16	I
2100	2986.47	I	190	3453.33	I	190	3916.24	I	240 d	4698.46	I
660	2988.65	I	130	3455.60	I	1900	3919.16	I	190	4708.04	I
160	2989.19	II	100	3460.43	I	600	3921.02	I	240	4718.43	I
480	2991.89	I	120	3550.64	I	600	3928.64	I	120	4730.71	I
230	2994.07	I	130	3566.16	I	410	3941.49	I	140	4737.35	I
300	2995.10	I	130	3573.64	I	1900	3963.69	I	340	4756.11	I
700	2996.58	I	330 h	3574.80	I	120	3969.06	I	190	4789.32	I
210	2998.79	I	19000	3578.69	I	1600	3969.75	I	120	4801.03	I
1100	3000.89	I	160 h	3584.33	I	1600	3976.66	I	110	4829.38	I
750	3005.06	I	130	3585.30	II	960	3983.91	I	140	4870.80	I
140	3013.03	I	17000	3593.49	I	190	3984.34	I	130	4887.01	I
710	3013.71	I	350	3601.67	I	160	3989.99	I	260	4922.27	I
710	3014.76	I	13000	3605.33	I	960	3991.12	I	110	4936.33	I
1400	3014.92	I	130	3632.84	I	160	3991.67	I	70	4942.50	I
710	3015.19	I	350	3636.59	I	190	3992.84	I	110	4954.81	I
2800	3017.57	I	630	3639.80	I	160	4001.44	I	60	5013.32	I
430	3018.50	I	220	3641.83	I	120	4012.47	II	70	5166.23	I
240	3018.82	I	220	3649.00	I	120	4026.17	I	70	5184.59	I
430	3020.67	I	170	3653.91	I	190	4039.10	I	70	5192.00	I
2800	3021.56	I	220	3656.26	I	160	4048.78	I	85	5196.44	I
1100	3024.35	I	130	3663.21	I	120	4058.77	I	5300	5204.52	I
170	3029.16	I	120	3685.55	I	140	4126.52	I	8400	5206.04	I
710	3030.24	I	130	3686.80	I	120	4153.82	I	11000	5208.44	I
140	3031.35	I	130	3687.25	I	140	4163.62	I	85	5224.94	I
390	3034.19	I	130	3730.81	I	170	4174.80	I	290	5247.56	I
550	3037.04	I	150	3732.03	I	170	4179.26	I	530	5264.15	I
550	3040.85	I	480	3743.58	I	110	4209.37	I	180	5265.72	I
110	3050.14	II	570	3743.88	I	20000	4254.35	I	95 h	5275.17	I
710	3053.88	I	340	3749.00	I	110	4263.14	I	70 h	5276.03	I
240	3118.65	II	230	3757.66	I	16000	4274.80	I	340	5296.69	I
430	3120.37	II	260	3768.24	I	10000	4289.72	I	70 h	5297.36	I
470	3124.94	II	130	3791.38	I	780	4337.57	I	660	5298.27	I
120	3128.70	II	130	3792.14	I	1100	4339.45	I	85	5300.75	I
590	3132.06	II	120	3793.29	I	380	4339.72	I	340 h	5328.34	I
140	3136.68	II	130	3793.88	I	1900	4344.51	I	70 h	5329.17	I
140	3147.23	II	140	3797.13	I	380	4351.05	I	780	5345.81	I
100	3155.15	I	200	3797.72	I	2300	4351.77	I	380	5348.32	I
100	3163.76	I	530	3804.80	I	570	4359.63	I	40	5400.61	I
240	3180.70	II	110	3806.83	I	530	4371.28	I	1400	5409.79	I

Intensity	Wavelength/Å	
24	5628.64	I
7	5642.36	I
24	5664.04	I
24	5694.73	I
40	5698.33	I
24	5702.31	I
24	5712.78	I
24 h	5783.11	I
30 h	5783.93	I
24 h	5785.00	I
19 h	5785.82	I
60 h	5787.99	I
180 h	5791.00	I
35	6330.10	I
22	6362.87	I
19	6661.08	I
21 h	6883.03	I
27 h	6924.13	I
30 h	6978.48	I
85	7355.90	I
130	7400.21	I
150	7462.31	I
40	8947.15	I
19	8976.83	I
Cobalt Co Z = 27		
20	355.52	V
18	355.88	V
12	356.06	V
66	609.16	IV
70	609.21	IV
64	609.28	IV
10	1018.36	V
10	1021.14	V
15	1231.73	V
50	1277.01	V
80	1299.58	II
80	1306.95	II
50	1345.67	V
1000	1696.01	III
800	1697.99	III
1000	1707.35	III
5000	1760.35	III
5000	1773.57	III
2000	1780.05	III
3000	1782.97	III
1000	1787.08	III
1000	1789.07	III
1000	1823.08	III
2000	1830.09	III
2000	1831.44	III
5000	1835.00	III
1500	1842.34	I
1800	1847.89	I
1800	1852.71	I
2400	1855.05	I
2000	1863.83	III
1500	1878.28	I
1800	1936.58	I
1500	1946.79	I
1500	1951.90	I
1800	1954.22	I

Intensity	Wavelength/Å	
1800	1955.17	I
1500	1958.55	I
1500	1961.59	I
1500 h	1968.69	I
1500 h	1968.93	I
3000	1970.71	I
1800 h	1971.16	I
1800 h	1972.52	I
1500	1973.85	I
1800	1976.97	I
2400 h	1980.89	I
1500	1989.80	I
1800	1990.34	I
1500 l	1998.49	I
1500	2002.32	I
900	2008.04	I
50	2011.51	II
1200 h	2014.58	I
900	2016.17	I
50	2022.35	II
50	2027.04	II
900	2031.96	I
1500	2039.95	I
1200	2041.11	I
50	2065.54	II
1500 h	2077.76	I
900	2085.67	I
900	2087.55	I
900	2089.35	I
900	2093.40	I
900	2094.86	I
900	2095.77	I
1200	2097.51	I
1500	2104.73	I
1500	2106.80	I
900	2108.98	I
900 s	2117.68	I
900	2137.78	I
900	2138.97	I
900	2163.03	I
1100	2174.60	I
200	2193.60	II
200	2256.73	II
150	2260.00	II
200	2283.52	II
1000	2286.15	II
200	2291.98	II
300 d	2293.38	II
300	2301.40	II
800 d	2307.85	II
2600	2309.02	I
500	2311.60	II
500	2314.05	II
300	2314.96	II
200 p	2317.06	II
2400	2323.14	I
300 p	2324.31	II
200 d	2326.11	II
500	2326.47	II
1400	2335.99	I
1600	2338.67	I

Intensity	Wavelength/Å	
200	2347.39	II
1600	2352.85	I
200 d	2353.41	II
2000	2353.42	I
500	2363.80	II
400	2378.62	II
1400	2380.48	I
200	2381.76	II
300 p	2383.45	II
1400	2384.86	I
200	2386.36	II
500	2388.92	II
200	2397.38	II
1100 d	2402.06	I
200 p	2404.16	II
5300	2407.25	I
5300	2411.62	I
1600	2412.76	I
4800	2414.46	I
4800	2415.30	I
300	2417.65	II
4100	2424.93	I
3300	2432.21	I
2900	2436.66	I
2400	2439.05	I
200	2442.63	II
200 d	2446.03	II
200 p	2447.69	II
200	2450.00	II
200	2464.20	II
200	2486.44	II
200	2498.82	II
570	2504.52	I
500	2506.46	II
360	2506.88	I
200	2511.16	II
860	2517.87	I
500	2519.82	II
4300	2521.36	I
200 h	2524.65	II
300	2524.97	II
500	2528.62	II
2900	2528.97	I
200 p	2530.09	II
720	2530.13	I
860	2532.18	I
200 d	2533.82	II
2900	2535.96	I
860	2536.49	I
300	2541.94	II
1700	2544.25	I
200	2546.74	II
340	2548.34	I
310	2553.37	I
310	2555.07	I
300	2559.41	II
200	2560.03	II
960	2562.15	I
500	2564.04	II
1100	2567.35	I
960	2574.35	I

Intensity	Wavelength/Å	
800	2580.32	II
300 d	2582.22	II
500	2587.22	II
500	2587.52	II
200	2588.91	II
100 p	2605.71	II
100	2612.50	II
100	2614.36	II
100 p	2628.77	II
100	2632.26	II
100	2636.07	II
310	2646.42	I
770	2648.64	I
100	2653.72	II
100	2663.53	II
200	2666.73	II
100	2675.85	II
100	2684.42	II
100	2702.02	II
200	2706.62	II
200	2707.35	II
190	2715.99	I
100	2727.78	II
80	2734.54	II
190	2745.10	I
100	2753.22	II
190	2764.19	I
100	2766.70	II
100	2774.97	II
100	2791.00	II
100	2793.73	II
150	2815.56	I
80	2835.63	II
80	2847.35	II
80	2871.22	II
190	2886.44	I
100	2918.38	II
100	2930.24	II
100	2954.73	II
690	2987.16	I
690	2989.59	I
60	3022.59	II
3100	3044.00	I
1700	3061.82	I
80	3387.70	II
1100	3388.17	I
2200	3395.38	I
11000	3405.12	I
4500	3409.18	I
6700	3412.34	I
2200	3412.63	I
2700	3417.16	I
50	3423.84	II
2500	3431.58	I
4500	3433.04	I
1600	3442.93	I
8800	3443.64	I
50	3446.39	II
4100	3449.17	I
2100	3449.44	I
21000	3453.50	I

Intensity	Wavelength/Å	
1000	3455.23	I
5100	3462.80	I
5100	3465.80	I
8000	3474.02	I
1900	3483.41	I
4800	3489.40	I
2400	3495.69	I
50	3501.72	II
9600	3502.28	I
7000	3506.32	I
50	3507.77	II
2900	3509.84	I
1400	3510.43	I
4800	3512.64	I
3800	3513.48	I
4800	3518.35	I
1300	3520.08	I
2700	3521.57	I
3800	3523.43	I
60	3523.51	II
6400	3526.85	I
2700	3529.03	I
7300	3529.81	I
1900	3533.36	I
50	3545.03	II
1100	3560.89	I
80	3561.07	II
8800	3569.38	I
50	3574.95	II
1600	3574.96	I
60	3575.32	II
2500	3575.36	I
60	3577.96	II
1000	3585.16	I
6700	3587.19	I
1900	3594.87	I
1600	3602.08	I
100	3621.21	II
1000	3627.81	I
80	3643.61	II
60	3681.35	II
1100	3745.50	I
1400	3842.05	I
6900	3845.47	I
5500	3873.12	I
2800	3873.96	I
7900	3894.08	I
1500	3935.97	I
80 h	3963.10	II
6000	3995.31	I
970	3997.91	I
350	4020.90	I
370	4045.39	I
350	4066.37	I
830	4092.39	I
550	4110.54	I
2800	4118.77	I
4400	4121.32	I
90	4190.71	I
90	4469.56	I
690	4530.96	I
90	4549.66	I
140	4565.59	I
190	4581.60	I
120	4629.38	I
85	4663.41	I
110	4792.86	I
100	4840.27	I
150	4867.88	I
80 h	4964.18	II
50	5212.71	I
50	5230.22	I
50	5247.93	I
50	5342.71	I
50	5352.05	I

Copper Cu Z = 29

80	685.141	II
100	709.313	II
100	718.179	II
150	724.489	II
200	735.520	II
250	736.032	II
80	779.295	II
100	797.455	II
150	810.998	II
200	813.883	II
300	826.996	II
150	848.808	II
250	851.303	II
250	858.487	II
400	861.994	II
400	865.390	II
250	869.336	II
150	873.263	II
200	876.723	II
250	877.012	II
200	877.555	II
500	878.699	II
100	884.133	II
250	885.847	II
600	886.943	II
600	890.567	II
500	892.414	II
800	893.678	II
400	894.227	II
600	896.759	II
400	896.976	II
600	901.073	II
400	906.113	II
800	914.213	II
600	922.019	II
500	924.239	II
400	935.232	II
600	935.898	II
600	943.335	II
600	945.525	II
500	945.965	II
200	954.383	II
250	956.290	II
400	958.154	II
200	960.414	II
250	968.042	II
200	974.759	II
250	977.567	II
100	987.657	II
250	992.953	II
300	1004.055	II
300	1008.569	II
300	1008.728	II
300	1010.269	II
250	1012.597	II
500	1018.707	II
500	1027.831	II
250	1028.328	II
200	1030.263	II
600	1036.470	II
600	1039.348	II
600	1039.582	II
800	1044.519	II
800	1044.744	II
500	1049.755	II
600	1054.690	II
400	1055.797	II
600	1056.955	II
400	1058.799	II
600	1059.096	II
600	1060.634	II
600	1063.005	II
200	1065.782	II
200	1066.134	II
500	1069.195	II
300	1073.745	II
200	1088.395	II
300	1094.402	II
250	1097.053	II
150	1119.947	II
200	1142.640	II
300	1144.856	II
100	1250.048	II
150	1265.506	II
300	1275.572	II
150	1282.455	II
150	1287.468	II
150	1298.395	II
300	1308.297	II
300	1314.337	II
100	1320.686	II
100	1326.395	II
150	1350.594	II
250	1351.837	II
150	1355.305	II
300	1358.773	II
200	1359.009	II
200	1362.600	II
250	1367.951	II
200	1371.840	II
300 r	1376.79	III
200 r	1377.49	III
100	1393.128	II
100	1398.642	II
150	1402.777	II
150	1407.169	II
100	1414.898	II
250	1418.426	II
250	1421.759	II
200	1427.829	II
400	1430.243	II
250	1434.904	II
150	1436.236	II
150	1442.139	II
200	1445.984	II
200	1449.058	II
250	1450.304	II
200	1452.294	II
300	1458.002	II
250	1459.412	II
200	1463.752	II
400	1463.838	II
200	1466.070	II
400	1470.697	II
200	1472.395	II
250	1473.978	II
200	1474.935	II
150	1476.059	II
300 r	1481.23	III
200	1481.544	II
200	1485.328	II
750	1488.831	II
300	1492.834	II
250	1493.366	II
250	1495.430	II
350	1496.687	II
150	1503.368	II
250	1504.757	II
200	1505.388	II
300	1508.632	II
350	1510.506	II
200	1512.465	II
200	1513.366	II
500	1514.492	II
200	1517.631	II
500	1519.492	II
600	1519.837	II
200	1520.540	II
200	1524.860	II
150	1525.764	II
500	1531.856	II
300	1532.131	II
250	1533.986	II
250	1535.002	II
500	1537.559	II
200	1540.239	II
300	1540.389	II
300	1540.588	II
750	1541.703	II
400	1544.677	II
100	1547.958	II
300	1550.653	II
300	1551.389	II
500	1552.646	II
250	1553.896	II
400	1555.134	II
500	1555.703	II
300	1558.345	II

Intensity	Wavelength/Å	
400	1565.924	II
400	1566.415	II
100	1569.416	II
300	1579.492	II
300	1580.626	II
400	1581.995	II
500	1583.682	II
400	1590.165	II
600	1593.556	II
500 r	1593.75	III
400	1598.402	II
400	1602.388	II
200	1604.848	II
300	1605.281	II
400	1606.834	II
250	1608.639	II
150	1610.296	II
200	1617.915	II
600	1621.426	II
400	1622.428	II
250	1630.268	II
100	1636.605	II
1000 r	1642.21	III
250	1649.458	II
30 r	1655.32	I
200	1656.322	II
200	1660.001	II
300	1663.002	II
100	1672.776	II
30	1688.09	I
30	1691.08	I
30 r	1703.84	I
50 r	1713.36	I
150	1717.721	II
50 r	1725.66	I
100	1736.551	II
50 r	1741.57	I
150	1753.281	II
200 r	1774.82	I
100 r	1825.35	I
250	1929.751	II
250	1944.597	II
100	1946.493	II
200	1957.518	II
150	1970.495	II
150	1977.027	II
500	1979.956	II
300	1989.855	II
250	1999.698	II
270	2035.854	II
250	2037.127	II
350	2043.802	II
300	2054.980	II
100	2078.663	II
110	2098.398	II
320	2104.797	II
300	2112.100	II
320	2117.310	II
350	2122.980	II
350	2126.044	II
420	2134.341	II
900	2135.981	II
400	2148.984	II
150	2161.320	II
1300 r	2165.09	I
250	2174.982	II
1600 r	2178.94	I
700	2179.410	II
1700 r	2181.72	I
700	2189.630	II
900	2192.268	II
400	2195.683	II
1700 r	2199.58	I
1300 r	2199.75	I
100	2200.509	II
200	2209.806	II
750	2210.268	II
1600 r	2214.58	I
250	2215.106	II
1000 r	2215.65	I
750	2218.108	II
2100 r	2225.70	I
150	2226.780	II
1600 r	2227.78	I
350	2228.868	II
2500 r	2230.08	I
1100 r	2238.45	I
900	2242.618	II
2300 r	2244.26	I
1000	2247.002	II
1300 r	2260.53	I
2200 r	2263.08	I
150	2263.786	II
200	2276.258	II
100	2286.645	II
2500 r	2293.84	I
170	2294.368	II
1000	2303.12	I
150	2369.890	II
2500 r	2392.63	I
120	2403.337	II
1500	2406.66	I
1000 r	2441.64	I
100	2485.792	II
2000 r	2492.15	I
150	2506.273	II
120	2526.593	II
300	2544.805	II
100	2571.756	II
150	2590.529	II
200	2600.270	II
2500 r	2618.37	I
200	2666.291	II
750	2689.300	II
700	2700.962	II
650	2703.184	II
700	2713.508	II
650	2718.778	II
300	2721.677	II
120	2737.342	II
270	2745.271	II
2500 r	2766.37	I
800	2769.669	II
200	2791.795	II
170	2799.528	II
100	2810.804	II
1250 r	2824.37	I
350	2837.368	II
100	2857.748	II
600	2877.100	II
270	2884.196	II
2500 r	2961.16	I
100	2986.335	II
2000	2997.36	I
2000	3010.84	I
2500	3036.10	I
2500	3063.41	I
1400	3073.80	I
1500	3093.99	I
1250	3099.93	I
2000	3108.60	I
1400 h	3126.11	I
1500	3194.10	I
1400	3208.23	I
1500 h	3243.16	I
10000 r	3247.54	I
10000 r	3273.96	I
1400 h	3282.72	I
400	3290.418	II
1500 h	3290.54	I
110	3300.881	II
250	3301.229	II
2500 h	3307.95	I
200	3316.276	II
1500	3337.84	I
150	3338.648	II
200	3365.648	II
450	3370.454	II
300	3374.952	II
200	3380.712	II
100	3384.945	II
1250 h	3483.76	I
1250	3524.23	I
2000	3530.38	I
1400	3599.13	I
1400	3602.03	I
1000	3686.555	II
150	3786.270	II
170	3797.849	II
100	3818.879	II
140	3826.921	II
160	3864.137	II
280	3884.131	II
150	3892.924	II
170	3903.177	II
140	3920.654	II
120	3933.268	II
120	3987.024	II
150	3993.302	II
140	4003.476	II
1250	4022.63	I
100	4032.647	II
600	4043.484	II
500	4043.751	II
2000	4062.64	I
120	4068.106	II
500	4131.363	II
200	4143.017	II
300	4153.623	II
500	4161.140	II
370	4164.284	II
400	4171.851	II
500	4179.512	II
500	4211.866	II
320	4230.449	II
200	4255.635	II
950	4275.11	I
300	4279.962	II
500	4292.470	II
400	4365.370	II
100	4444.831	II
400	4506.002	II
150	4516.049	II
150	4541.032	II
500	4555.920	II
100	4596.906	II
120	4649.271	II
2000	4651.12	I
120	4661.363	II
320	4671.702	II
300	4673.577	II
450	4681.994	II
100	4758.433	II
400	4812.948	II
120	4851.262	II
300	4854.988	II
100	4873.304	II
150	4901.427	II
1000	4909.734	II
500	4918.376	II
200	4926.424	II
900	4931.698	II
120	4943.026	II
700	4953.724	II
500	4985.506	II
400	5006.801	II
350	5009.851	II
400	5012.620	II
350	5021.279	II
200	5039.016	II
300	5047.348	II
900	5051.793	II
400	5058.910	II
500	5065.459	II
450	5067.094	II
350	5072.302	II
450	5088.277	II
420	5093.816	II
350	5100.067	II
1500	5105.54	I
250	5124.476	II
2000	5153.24	I
100	5158.093	II
100	5183.367	II

Intensity	Wavelength/Å	
2500	5218.20	I
100	5269.991	II
100	5276.525	II
1650	5292.52	I
100	5368.383	II
1500	5700.24	I
1500	5782.13	I
150	5805.989	II
100	5833.515	II
200	5897.971	II
120	5937.577	II
400	5941.196	II
100	5993.260	II
650	6000.120	II
100	6023.264	II
250	6072.218	II
150	6080.343	II
150	6099.990	II
160	6107.412	II
300	6114.493	II
600	6150.384	II
750	6154.222	II
500	6172.037	II
550	6186.884	II
400	6188.676	II
300	6198.092	II
470	6204.261	II
450	6208.457	II
750	6216.939	II
700	6219.844	II
500	6261.848	II
1000	6273.349	II
350	6288.696	II
900	6301.009	II
550	6305.972	II
400	6312.492	II
120	6326.466	II
400	6373.268	II
750	6377.840	II
400	6403.384	II
850	6423.884	II
200	6442.965	II
750	6448.559	II
170	6466.246	II
950	6470.168	II
750	6481.437	II
400	6484.421	II
220	6517.317	II
400	6530.083	II
120	6551.286	II
200	6577.080	II
750	6624.292	II
800	6641.396	II
450	6660.962	II
100	6770.362	II
300	6806.216	II
400	6809.647	II
320	6823.202	II
250	6844.157	II
320	6868.791	II
270	6872.231	II
270	6879.404	II
220	6937.553	II
150	6952.871	II
150	6977.572	II
200	7022.860	II
300	7194.896	II
400	7326.008	II
300	7331.694	II
250	7382.277	II
1000	7404.354	II
270	7434.156	II
500	7562.015	II
700	7652.333	II
1000	7664.648	II
150	7681.788	II
450	7744.097	II
800	7778.738	II
750	7805.184	II
1500	7807.659	II
1000	7825.654	II
350	7860.577	II
300	7890.567	II
700	7902.553	II
1500	7933.13	I
400	7944.438	II
400	7972.033	II
1200	7988.163	II
2000	8092.63	I
500	8277.560	II
800	8283.160	II
250	8503.396	II
750	8511.061	II
200	8609.134	II
500	9813.213	II
250	9827.978	II
200	9830.798	II
600	9861.280	II
600	9864.137	II
200	9883.969	II
550	9916.419	II
500	9917.954	II
550	9925.594	II
450	9938.998	II
500	9960.354	II
450	10006.588	II
550	10022.969	II
550	10038.093	II
650	10054.938	II
450	10080.354	II

Dysprosium Dy Z = 66

260	2356.91	II
240	2410.01	II
260	2439.84	II
220	2585.30	I
440	2634.80	II
220	2755.75	II
300	2816.39	II
390	2913.95	II
610	3038.28	II
830	3135.38	II
500	3141.14	II
1200	3156.52	II
670	3162.83	II
1000	3169.99	II
470	3215.19	II
830	3216.63	II
490	3235.89	II
490	3245.12	II
1200	3251.27	II
890	3280.09	II
490	3282.77	II
1100	3308.88	II
780	3316.32	II
1000	3319.88	II
780	3341.00	II
510	3353.58	II
510	3368.11	II
5300	3385.02	II
610	3388.85	II
3800	3393.57	II
1300	3396.16	II
5300	3407.80	II
1300	3413.78	II
530	3414.82	II
780	3419.63	II
530	3425.06	II
1900	3434.37	II
560	3440.93	II
1300	3441.45	II
3800	3445.57	II
830	3446.99	II
2700	3454.32	II
1300	3456.56	II
4400	3460.97	II
720	3468.43	II
560	3471.14	II
560 d	3471.53	II
1300	3477.07	II
4400	3494.49	II
560	3496.34	II
830	3498.71	II
830	3504.53	II
830	3505.45	II
1300	3506.81	II
560	3517.26	II
4400	3523.98	II
22000	3531.70	II
4400	3534.96	II
5500	3536.02	II
4400	3538.52	II
1700	3542.33	II
1400	3546.83	II
4400	3550.22	II
2200	3551.62	II
440 h	3558.23	II
440	3559.30	II
2200	3563.15	II
560	3563.69	II
780	3573.83	II
1400	3574.15	II
4400	3576.24	II
1700	3576.87	II
830	3577.98	II
440	3580.04	II
3300	3585.06	II
1400	3585.78	II
560	3586.11	II
1100	3591.41	II
560	3591.81	II
560	3592.11	II
1800	3595.04	II
560	3600.38	II
1800	3606.12	II
440	3618.51	II
560	3620.16	II
470	3624.27	II
1100	3629.42	II
4000	3630.24	II
440	3632.78	II
1100	3640.25	II
11000	3645.40	II
1000	3648.78	II
700	3664.62	II
990	3672.30	II
420	3672.70	II
1400	3674.08	II
2200	3676.59	II
640	3678.51	I
820	3684.85	I
1300	3685.78	I
4700	3694.81	II
990	3698.21	II
540	3701.63	II
440	3707.57	II
440	3708.22	II
420	3710.07	II
1600	3724.45	II
930	3739.34	I
1200	3747.82	II
1400	3753.51	II
1400	3753.75	II
1200	3757.05	I
4700	3757.37	II
640	3767.63	I
640	3773.05	I
420	3781.47	I
3300	3786.18	II
1600	3788.44	II
700	3791.87	II
510	3804.14	II
580	3806.27	II
470	3812.27	I
470	3813.67	II
1400	3816.76	II
700	3825.68	II
2300	3836.50	II
1400	3841.31	II
420	3846.34	II
420	3847.02	I
1200	3853.03	II
420	3858.40	I
560	3868.45	II
1600	3868.81	I

Intensity	Wavelength/Å	
820	3869.86	II
7000	3872.11	II
1200	3873.99	II
470	3879.11	II
5800	3898.53	II
540	3914.87	II
540	3915.59	II
540 d	3917.29	I
420	3927.86	I
540	3930.14	I
2100	3931.52	II
10000	3944.68	II
800	3957.79	II
14000	3968.39	II
2700	3978.57	II
1400	3981.92	II
1600	3983.65	II
800	3984.21	II
540	3991.32	II
1600	3996.69	II
8000	4000.45	II
420	4005.84	I
540	4011.29	II
540	4013.82	I
540	4014.70	II
420	4027.78	II
520 d	4028.32	II
520	4032.47	II
420	4033.65	II
420	4036.32	II
12000	4045.97	I
1600	4050.56	II
520	4055.14	II
2500	4073.12	II
7400	4077.96	II
3900	4103.30	II
860	4103.87	I
1500	4111.34	II
490	4124.63	II
990	4129.42	II
1200	4143.10	II
990	4146.06	I
5700	4167.97	I
930	4183.72	I
12000	4186.82	I
2200	4191.64	I
6800	4194.84	I
800	4198.02	I
680	4201.30	I
680	4202.24	I
16000	4211.72	I
1800	4213.18	I
3700	4215.16	I
4400	4218.09	I
4400	4221.11	I
2700	4225.16	I
1000	4308.63	II
540	4409.38	II
740	4449.70	II
420	4577.78	I
2100	4589.36	I
990	4612.26	I
170	4731.84	II
120 h	4775.79	I
480	4957.34	II
70	5022.12	I
160	5042.63	I
95	5070.68	I
120	5077.67	I
80	5090.38	II
80	5110.32	I
130 h	5120.04	I
190	5139.60	II
110	5169.69	II
80	5185.30	I
290	5192.86	II
95	5197.66	II
70	5259.88	I
130	5260.56	I
65	5267.11	I
55	5282.07	I
160	5301.58	I
65	5340.30	I
85	5389.58	II
80	5419.13	I
70	5423.32	I
95	5451.11	I
65	5547.27	I
100	5639.50	I
55 h	5645.99	I
80	5652.01	I
70 h	5718.46	I
55	5745.53	I
55 h	5868.11	II
70	5945.80	I
120	5974.49	I
140	5988.56	I
140	6088.26	I
100	6168.43	I
270	6259.09	I
160	6579.37	I
75	6667.86	I
180	6835.42	I
80	6852.96	I
65	6899.32	II
55	7426.86	II
55	7543.73	I
80	7662.36	I
100	8201.57	II
45	8791.39	II

Erbium Er Z = 68

600	2277.65	III
290	2586.73	II
490	2670.26	II
500	2739.27	III
610	2755.63	II
1000	2904.47	II
1500	2910.36	II
1500	2964.52	II
1200	3002.41	II
1000	3055.10	III
1000	3070.40	III
610	3073.34	II
720	3082.08	II
610	3084.02	II
770	3122.72	II
1500	3166.25	III
870	3181.92	II
870	3220.73	II
610	3223.31	II
2300	3230.58	II
2700	3264.78	II
720	3279.33	II
720	3280.22	II
2000	3301.23	III
2300	3312.42	II
770	3323.19	II
770	3332.70	II
1300	3346.04	II
1400	3364.08	II
1400 d	3368.02	II
7700	3372.71	II
970	3374.17	II
1700	3385.08	II
2300	3392.00	II
770	3441.13	II
970	3471.71	II
610	3479.41	II
970	3485.85	II
6700	3499.10	II
610	3502.78	I
610	3524.91	II
820	3549.84	II
1500	3558.02	I
1000	3559.90	II
920	3570.75	II
1000	3580.52	II
610	3590.76	I
610	3599.50	II
1000	3599.83	II
3100	3616.56	II
720	3628.04	I
1000	3633.54	II
1600	3638.68	I
900	3645.94	II
7900	3692.65	II
1300	3729.52	II
900	3742.64	II
900	3747.43	I
1800	3786.84	II
1600	3810.33	I
4000	3816.78	III
3600	3830.48	II
680	3855.90	I
7500	3862.85	I
1500	3880.61	II
1200	3882.89	II
4200	3892.68	I
5200	3896.23	II
11000	3906.31	II
3200	3937.01	I
2100	3938.63	II
3200	3944.42	I
2700	3973.04	I
3200	3973.58	I
1400	3974.72	II
810	3977.02	I
1100	3982.33	I
810	3987.66	I
14000	4007.96	I
1100	4012.58	I
3000	4020.51	I
1000	4046.96	I
940	4055.47	II
690	4059.78	II
3500	4087.63	I
1100	4098.10	I
6900	4151.11	I
1000	4190.70	I
1400	4218.43	I
690	4286.56	I
40000	4290.06	III
20000	4386.86	III
810	4409.34	I
1000	4606.61	I
570	4675.62	II
15000	4735.56	III
2000	4783.12	III
250	5007.25	I
200	5035.94	I
210	5042.05	II
120	5124.56	I
130	5127.41	II
120	5131.53	I
130	5133.83	II
170	5164.77	II
130	5172.78	I
160	5188.90	II
150	5206.52	I
140	5255.93	II
80	5272.91	I
90	5348.06	I
60	5414.63	II
180	5456.62	I
90	5468.32	I
80	5485.97	II
80	5593.46	I
60	5611.82	I
70	5622.01	I
80	5626.53	II
90	5640.36	I
70	5664.95	I
70	5719.55	I
100	5739.19	I
290	5762.80	I
70	5784.66	I
70	5800.79	I
430	5826.79	I
100	5850.07	I
120	5855.31	I
140	5872.35	I
120	5881.14	I
8000	5903.30	III

Intensity	Wavelength/Å	
70	6022.56	I
70	6061.25	I
60	6076.45	II
360	6221.02	I
55	6262.56	I
60	6268.87	I
130	6308.77	I
55	6326.13	I
55	6492.35	I
60	6583.48	I
70	6601.11	I
70	6759.87	I
35	6790.92	I
70	6848.10	I
55	6865.13	I
55	7459.55	I
120	7469.51	I
35	7680.01	I
35	7797.47	I
35	7921.85	I
30	7937.84	I
35	8312.82	I
55	8409.90	I
9	8866.84	II
Europium Eu Z = 63		
30	2124.69	III
200	2350.51	III
4000	2375.46	III
100 d	2435.14	III
1000	2444.38	III
4000	2445.99	III
2000	2513.76	III
200	2522.14	III
160	2564.17	II
110	2568.17	II
230	2577.14	II
1000	2638.77	II
380	2641.27	II
640	2668.34	II
110	2673.42	II
250	2678.29	II
250	2685.66	II
550	2692.03	II
700	2701.14	II
800	2701.90	II
240	2705.28	II
180	2709.99	I
700	2716.98	II
4200	2727.78	II
160	2740.62	II
120	2744.26	II
480	2781.89	II
1900	2802.84	II
220	2811.75	II
3400	2813.94	II
550	2816.18	II
2000	2820.78	II
400 cw	2828.72	II
260	2859.67	II
280	2862.57	II
200	2892.54	I
140	2893.03	I
360	2893.83	I
3200	2906.68	II
160	2908.99	I
850	2925.04	II
200 cw	2952.68	II
260	2960.21	II
300	2991.33	II
100 c	3023.93	III
200 c	3026.79	III
320 cw	3054.94	II
120	3058.98	I
220	3077.36	II
120	3097.45	II
320	3106.18	I
950	3111.43	I
120	3130.73	II
50 c	3171.00	III
50 c	3183.78	III
420	3210.57	I
1000	3212.81	I
420	3213.75	I
150	3272.77	II
210	3277.78	II
150	3301.95	II
140	3308.02	II
140	3313.33	II
950	3334.33	I
110	3350.40	I
140	3369.06	II
190	3391.99	II
280	3396.58	II
150	3425.02	II
150	3441.00	II
130	3461.38	II
470 cw	3521.09	II
150	3542.15	II
180	3552.52	II
150	3603.20	II
6400	3688.42	II
20000 cw	3724.94	II
350	3741.31	II
260	3761.12	II
39000 cw	3819.67	II
140	3844.23	II
190	3865.57	I
150	3884.75	I
28000 cw	3907.10	II
32000 cw	3930.48	II
30000 cw	3971.96	II
180	4011.69	II
150	4017.58	II
120	4039.19	I
120	4085.38	II
33000 cw	4129.70	II
60000 cw	4205.05	II
150	4298.73	I
240	4355.09	II
14000 cw	4435.56	II
3000	4522.57	II
11000	4594.03	I
9800	4627.22	I
8300	4661.88	I
110	4867.62	I
150	4907.18	I
180	4911.40	I
180	5013.17	I
170	5022.91	I
110	5029.54	I
170	5114.37	I
170	5129.10	I
210	5133.52	I
270	5160.07	I
210	5166.70	I
200	5199.85	I
110	5200.96	I
120	5206.44	I
750	5215.10	I
300	5223.49	I
120	5239.24	I
200	5266.40	I
390	5271.96	I
110	5272.48	I
150	5282.82	I
120	5291.26	I
120	5294.64	I
540	5357.61	I
120	5361.61	I
110	5376.94	I
120	5392.94	I
450	5402.77	I
380	5451.51	I
260	5452.94	I
120	5488.65	I
120	5510.52	I
200	5547.44	I
150	5570.33	I
200	5577.14	I
120	5580.03	I
210	5645.80	I
330	5765.20	I
180	5783.69	I
170	5818.74	II
600 cw	5830.98	I
330	5966.07	II
480 cw	5967.10	I
170	5972.75	I
240	5992.83	I
110	6012.56	I
420	6018.15	I
170	6029.00	I
420	6049.51	II
140	6057.36	I
240	6083.84	I
240	6099.35	I
120	6118.78	I
330	6173.05	II
110	6178.76	I
260 cw	6188.13	I
140	6195.07	I
240	6262.25	I
170	6299.77	I
230	6303.41	II
120 cw	6350.04	I
120 cw	6400.93	I
180	6410.04	I
140	6411.32	I
830	6437.64	II
120	6457.96	I
1400	6645.11	II
50	6666.35	III
140	6802.72	I
360	6864.54	I
120	7040.20	I
330	7077.10	II
570	7194.81	II
570	7217.55	II
540	7301.17	II
720	7370.22	II
300	7426.57	II
160	7583.91	I
60 cw	7742.57	I
70	7746.19	I
35	7887.99	I
24 cw	8209.80	I
21 cw	8642.67	I
18	8870.30	I
Fluorine F Z = 9		
50	148.00	V
50	163.56	V
90	165.98	V
100	166.18	V
50	186.84	V
60	190.57	V
70	190.84	V
50	196.39	IV
60	196.45	IV
70	200.09	IV
80	201.16	IV
90	208.25	IV
90	240.08	IV
100	251.03	IV
140	419.65	IV
150	420.05	IV
160	420.73	IV
100	429.51	III
110	430.15	III
150	430.76	IV
90	464.29	III
120	465.98	V
130	490.57	IV
160	491.00	IV
50	497.38	IV
60	497.83	IV
70	498.80	IV
90	506.16	V
100	508.08	V
120	508.39	III
60	514.08	V
90	525.29	V
100	526.30	V
120	567.69	III
110	567.75	III

Intensity	Wavelength/Å	
140	570.64	IV
140	571.30	IV
150	571.39	IV
160	572.66	IV
90	605.67	II
100	606.80	II
90	630.20	III
100	647.77	V
110	647.87	V
130	654.03	V
120	656.12	III
130	656.87	III
110	657.23	V
140	657.33	V
140	658.33	III
140	676.12	IV
130	677.15	IV
150	677.22	IV
130	678.99	IV
160	679.21	IV
60	757.04	V
150	806.96	I
125	809.60	I
500	951.87	I
1000	954.83	I
750	955.55	I
500	958.52	I
20	972.40	I
350	973.90	I
100	976.22	I
40	976.51	I
100	977.75	I
60	1082.31	V
70	1088.39	V
80	1219.03	III
80	1266.87	III
90	1267.71	III
70	1297.54	III
70	1359.92	III
110	1498.93	III
120	1502.01	III
110	1504.18	III
140	1504.79	III
130	1506.30	III
110	1506.77	III
100	1553.02	III
110	1557.59	III
100	1563.73	III
100	1565.54	III
100	1623.40	III
100	1650.76	III
130	1670.39	III
140	1677.40	III
100	1716.99	III
120	1770.09	III
150	1770.67	III
110	1772.93	III
140	1773.36	III
160	1791.65	III
110	1803.03	III
170	1805.90	III
110	1839.30	III
120	1839.97	III
110	1840.14	III
100	2027.44	III
120	2030.32	III
120	2217.17	III
50	2298.29	IV
40	2451.58	IV
120	2452.07	III
50	2456.92	IV
130	2464.85	III
130	2470.29	III
120	2478.73	III
150	2484.37	III
120	2542.77	III
120	2580.04	III
130	2583.81	III
120	2593.23	III
130	2595.53	III
140	2599.28	III
130	2625.01	III
140	2629.70	III
120	2656.44	III
130	2755.55	III
160	2759.63	III
120	2788.15	III
160	2811.45	III
40	2820.74	IV
50	2826.13	IV
140	2833.99	III
150	2835.63	III
150	2860.33	III
120	2862.86	III
140	2887.58	III
150	2889.45	III
120	2905.30	III
140	2913.29	III
160	2916.34	III
140	2932.49	III
140	2994.28	III
120 h	2997.21	III
130	2997.53	III
120	2999.47	III
130	3039.25	III
120	3039.75	III
160	3042.80	III
150	3049.14	III
140	3113.62	III
160	3115.70	III
180	3121.54	III
140	3124.79	III
140	3134.23	III
140	3146.99	III
180	3174.17	III
170	3174.76	III
120	3214.00	III
200	3501.45	II
200	3501.57	II
200	3502.96	II
6	3594.10	I
12	3668.17	I
270	3847.09	II
260	3849.99	II
250	3851.67	II
5	3898.48	I
8	3930.69	I
5	3934.26	I
5	3948.56	I
240	4024.73	II
220	4025.01	II
230	4025.49	II
200	4103.51	II
200	4246.23	II
200	4299.17	II
140 h	4420.30	III
120 h	4427.35	III
120 h	4432.32	III
140 h	4479.99	III
6	4960.65	I
150	5012.54	III
160	5110.99	III
15	5230.41	I
12	5279.01	I
18	5540.52	I
12	5552.43	I
10	5577.33	I
20	5624.06	I
12	5626.93	I
15	5659.15	I
40	5667.53	I
90	5671.67	I
18	5689.14	I
25	5700.82	I
25	5707.31	I
140	5753.17	III
120	5761.20	III
12	5950.15	I
25	5959.19	I
70	5965.28	I
50	5994.43	I
150	6015.83	I
80	6038.04	I
900	6047.54	I
100	6080.11	I
150	6091.82	III
140	6125.50	III
800	6149.76	I
400	6210.87	I
130	6233.57	III
13000	6239.65	I
10000	6348.51	I
140	6363.05	III
8000	6413.65	I
450	6569.69	I
300	6580.39	I
400	6650.41	I
1800	6690.48	I
400	6708.28	I
7000	6773.98	I
1500	6795.53	I
9000	6834.26	I
50000	6856.03	I
8000	6870.22	I
15000	6902.48	I
6000	6909.82	I
4000	6966.35	I
45000	7037.47	I
30000	7127.89	I
15000	7202.36	I
1000	7309.03	I
15000	7311.02	I
700	7314.30	I
5000	7331.96	I
120	7336.77	III
130	7354.94	III
10000	7398.69	I
4000	7425.65	I
2200	7482.72	I
2500	7489.16	I
900	7514.92	I
5000	7552.24	I
5000	7573.38	I
7000	7607.17	I
18000	7754.70	I
15000	7800.21	I
300	7879.18	I
500	7898.59	I
350	7936.31	I
300	7956.32	I
80	8016.01	II
1000	8040.93	I
900	8075.52	I
350	8077.52	I
350	8126.56	I
600	8129.26	I
300	8159.51	I
600	8179.34	I
300	8191.24	I
350	8208.63	I
2500	8214.73	I
3000	8230.77	I
500	8232.19	I
1500	8274.62	I
2000	8298.58	I
600	8302.40	I
900	8807.58	I
1000	8900.92	I
300	8912.78	I
350	9025.49	I
400	9042.10	I
350	9178.68	I
200	9433.67	I
25	9505.30	I
12	9662.04	I
25	9734.34	I
15	9822.11	I
12	9902.65	I
80 h	10047.98	II
15	10285.45	I
20	10862.31	I

Francium Fr Z = 87

	7177.	I

Intensity	Wavelength/Å	
Gadolinium Gd Z = 64		
1200	1007.24	IV
1200	1063.84	IV
1600	1476.98	IV
1500	1705.03	IV
1600	1706.01	IV
2000	1736.24	IV
1500	1815.32	IV
2200	1975.24	III
3400	2018.07	III
2800	2359.31	III
1400	2397.87	IV
2800	2697.39	III
2800	2703.28	III
2700	2727.89	III
9000	2904.73	III
9500	2955.53	III
1200	2999.04	II
2100	3010.13	II
1900	3027.60	II
2100	3032.84	II
1600	3034.05	II
2100	3081.99	II
3500	3100.50	II
930	3145.00	II
980	3156.53	II
980	3161.37	II
4000	3176.66	III
1400	3331.38	II
1100	3336.18	II
5400	3350.47	II
4300	3358.62	II
5400	3362.23	II
1100	3392.53	II
1100 d	3407.56	II
6900	3422.47	II
1700	3439.21	II
2700	3439.99	II
1400	3450.38	II
1100	3451.23	II
2700	3463.98	II
1700	3467.27	II
1700	3468.99	II
1400	3473.22	II
2200	3481.28	II
1700	3481.80	II
1700	3494.40	II
1400	3505.51	II
1100	3512.50	II
4300	3545.80	II
3900	3549.36	II
1400	3557.05	II
5400	3584.96	II
1100	3592.71	II
1100	3604.87	I
6100	3646.19	II
3900	3654.62	II
3100	3656.15	II
1400	3662.26	II
2700	3664.60	II
2000	3671.20	II
2000	3684.13	I
3100	3687.74	II
2000	3697.73	II
1300	3699.73	II
2700	3712.70	II
2000	3713.57	I
1400	3716.36	II
2000	3717.48	I
1800 d	3719.45	II
1500	3730.84	II
4500	3743.47	II
1400	3758.31	II
8700	3768.39	II
1400	3770.69	II
2900	3783.05	I
5100	3796.37	II
3700	3813.97	II
3300	3850.69	II
5100	3850.97	II
4300	3852.45	II
1600	3866.99	I
1500	3894.70	II
2200	3916.51	II
1200	3934.79	I
1400	3945.54	I
1200	3957.67	II
1100	4023.14	I
1100	4028.15	I
1400	4037.33	II
1600	4045.01	I
1300	4049.43	II
2200	4049.86	II
2600	4053.64	I
2600	4058.22	I
1900	4063.39	II
1300	4078.44	II
2800	4078.70	I
1500	4085.56	II
1100	4092.71	I
2600	4098.61	II
2200	4130.37	II
1100	4132.28	II
2400	4175.54	I
2400	4184.25	II
2200	4190.78	I
1300	4212.00	II
4800	4225.85	I
1700	4251.73	II
1600	4262.09	I
1100	4306.34	I
1800	4313.84	I
2600 d	4325.57	II
1900	4327.12	I
1000	4344.30	II
2200	4346.46	I
1400	4401.86	I
1400	4422.41	I
1100	4430.63	I
1100	4519.66	I
910	4537.81	I
520	4614.50	I
700	4694.33	I
410	4743.65	I
470	4767.24	I
300	4784.62	I
320	4821.69	I
280	4934.12	I
750	5015.04	I
75	5039.09	I
5000	5091.70	III
130	5098.38	II
910	5103.45	I
180	5108.91	II
120	5125.56	II
860	5155.84	I
190	5176.28	II
410	5197.77	I
280	5219.40	I
130	5233.93	I
320	5251.18	I
120	5252.14	II
140	5255.80	I
280	5283.08	I
280	5301.67	I
220	5302.76	I
280	5307.30	I
130	5321.50	I
280	5321.78	I
110	5327.32	I
170	5333.30	I
300	5343.00	I
200	5348.67	I
300	5350.38	I
240	5353.26	I
3000	5365.96	III
150	5370.63	I
4000	5553.30	III
3000	5587.88	III
190	5617.91	I
110	5632.25	I
260	5643.24	I
3000	5658.98	III
390	5696.22	I
120	5733.86	II
240	5791.38	I
220	5851.63	I
280	5856.22	I
110	5904.56	I
170	5911.45	II
85	5930.29	I
85	5936.84	I
65	5937.71	I
110 h	5988.02	I
430	6114.07	I
75	6305.15	II
40	6331.35	I
40	6380.95	II
40 h	6538.15	I
55	6564.78	I
50	6634.36	II
35	6681.23	II
85	6730.73	I
50	6752.67	II
26	6786.33	II
100	6828.25	I
100	6916.57	I
50	6985.89	II
75	6991.92	I
60	6996.76	II
45	7006.16	II
35	7122.57	I
170	7168.37	I
28	7189.57	II
28	7262.66	I
35	7441.85	I
40	7464.36	I
55	7562.97	I
80	7733.50	I
35	7846.35	II
35	7856.93	I
25	7930.25	II
18	8146.15	I
21	8668.63	I
21 h	8832.06	II
14 h	8849.14	I
18 h	8867.31	I
5000	14332.88	III
Gallium Ga Z = 31		
14	294.53	IV
61	295.67	IV
30	298.44	V
30	300.01	V
30	302.86	V
41	304.99	IV
30	307.03	V
30	308.26	V
30	311.79	V
30	313.68	V
40	319.41	V
40	322.31	V
50	322.99	V
30	323.10	V
40	324.25	V
40	324.95	V
40	326.14	V
30	326.77	V
30	328.65	V
25	423.18	IV
16	439.92	IV
50	620.00	III
40	622.01	III
90	806.51	III
90	817.30	III
50	828.70	III
20	878.17	V
40	973.21	V
40	989.75	V
90	1014.47	V
90	1019.71	V
120	1050.48	V
80	1054.56	V
90	1058.12	V
80	1066.69	V

Intensity	Wavelength/Å	
60	1069.60	V
80	1073.77	V
90	1078.83	V
110	1079.60	V
60	1080.99	V
80	1085.00	III
250	1085.01	V
80	1087.37	V
90	1091.71	V
100	1094.36	V
80	1095.10	V
160	1102.83	V
140	1103.03	V
60	1105.61	III
75	1105.62	V
70	1106.17	V
80	1118.34	V
120	1126.40	V
130	1128.10	V
120	1128.53	V
100	1129.94	V
130	1136.07	V
67	1137.06	IV
130	1150.23	V
90	1150.27	III
70	1156.10	IV
120	1156.51	V
35	1157.74	V
70	1163.60	IV
25	1169.40	V
75	1170.58	IV
48	1171.71	IV
40	1178.95	V
68	1185.23	IV
40	1186.06	IV
73	1190.89	IV
73	1193.02	IV
75	1195.02	IV
69	1201.54	IV
72	1206.89	IV
80	1213.17	V
63	1216.15	IV
50	1228.03	IV
60	1236.38	IV
60	1238.59	IV
75	1245.53	IV
83	1258.77	IV
81	1264.66	IV
82	1267.15	IV
90	1267.16	III
81	1279.24	IV
15	1283.64	V
80	1285.33	IV
80	1293.46	III
60	1295.36	III
82	1295.86	IV
83	1299.46	IV
82	1303.53	IV
80	1309.68	IV
80	1314.82	IV
60	1323.15	III
85	1338.09	IV
77	1347.03	IV
76	1351.06	IV
70	1353.92	III
74	1364.63	IV
60	1395.54	IV
77	1402.55	IV
70	1405.32	IV
73	1465.87	IV
90	1495.07	III
50	1534.46	III
10	1813.98	II
15	1845.30	II
20	2091.34	II
90	2417.70	III
90	2423.98	III
15	2424.36	III
10	2632.66	I
10	2665.05	I
20	2700.47	II
15	2780.15	II
50	3521.77	III
80	3581.19	III
100	3589.34	III
10	3731.10	III
10	3806.60	III
10	4032.99	I
10	4172.04	I
15	4251.16	II
10 h	4254.04	II
10	4255.77	II
40	4262.00	II
100	4380.69	III
150	4381.76	III
100	4863.00	III
150	4993.78	III
10	5808.28	III
20	5848.25	III
15	5993.51	III
10	6334.2	II
2000	6396.56	I
1000	6413.44	I
10 h	7251.4	I
20 h	7403.0	I
30 h	7464.0	I
10 h	7620.5	I
50 h	7734.77	I
100 h	7800.01	I
15 h	8002.55	I
20 h	8074.25	I
100 h	8311.86	I
200 h	8386.49	I
200 h	9492.92	I
200 h	9493.12	I
300 h	9589.36	I
100 h	10905.95	I
400	11949.12	I
200	12109.78	I
60	14996.64	I
60	22016.81	I
70	22568.71	I

Intensity	Wavelength/Å	
Germanium Ge Z = 32		
700	294.51	V
1000	295.64	V
200	304.98	V
20	621.52	V
50	724.21	V
60	746.88	V
60	760.05	V
10	862.234	II
15	875.493	II
15	905.977	II
20	920.554	II
300	971.35	V
300	990.66	V
50	999.101	II
300	1004.38	V
100	1016.638	II
900	1045.71	V
700	1072.66	V
100	1075.072	II
300	1085.51	II
40	1088.45	III
800	1089.49	V
200	1098.71	II
500	1106.74	II
1000	1116.94	V
500	1120.46	II
700	1163.39	V
200	1164.27	II
500	1181.19	II
500	1181.65	II
200	1188.73	II
20	1188.99	IV
300	1191.26	II
700	1222.30	V
20	1229.81	IV
500	1237.059	II
500	1261.905	II
100	1264.710	II
200	1401.24	II
200	1538.091	II
500	1576.855	II
75	1581.070	II
100	1602.486	II
3 r	1615.57	I
2 r	1624.130	I
2 r	1630.173	I
3 r	1636.31	I
4 r	1639.730	I
2	1647.531	I
200	1649.194	II
2	1651.528	I
4 r	1651.955	I
3	1661.345	I
4 r	1663.539	I
10 h	1665.275	I
4	1667.802	I
3 r	1670.608	I
100 r	1691.090	I
200 r	1716.784	I
100 h	1739.102	I
100	1742.195	I
50	1746.065	I
200	1750.043	I
100	1758.279	I
100 h	1764.185	I
100 h	1765.284	I
50 h	1766.433	I
200	1774.176	I
200	1785.046	I
100 h	1793.071	I
75 h	1801.432	I
200 h	1841.328	I
200 h	1842.410	I
100 h	1844.410	I
100 h	1845.872	I
100 h	1846.958	I
200	1853.134	I
500 r	1860.086	I
100	1865.052	I
300 r	1874.256	I
100	1895.197	I
500 r	1904.702	I
50 h	1908.434	I
30	1912.409	I
300 r	1917.592	I
100 h	1923.467	I
500 r	1929.826	I
10 h	1934.048	I
100 r	1937.483	I
500	1938.008	II
100 r	1938.300	I
500	1938.891	II
30 s	1944.116	I
200	1944.731	I
200	1955.115	I
500	1962.013	I
30 h	1963.373	I
30	1965.383	I
200	1970.880	I
200	1979.274	II
300 h	1987.849	I
300	1988.267	I
500 r	1998.887	I
200	2011.29	I
1700	2019.068	I
2400 r	2041.712	I
1600 r	2043.770	I
420	2054.461	I
220 h	2057.238	I
750 r	2065.215	I
2600 r	2068.656	I
420	2086.021	I
2000 r	2094.258	I
25	2104.45	III
240	2105.824	I
95 h	2124.744	I
50 h	2186.451	I
340 r	2198.714	I
15	2220.375	I
18	2256.001	I
18	2314.201	I

Intensity	Wavelength/Å	
24	2327.918	I
15	2359.233	I
20	2379.144	I
10	2389.472	I
15	2397.885	I
130	2417.367	I
30	2436.412	I
30	2488.25	IV
90	2497.962	I
500	2500.54	II
70	2533.230	I
20	2542.44	IV
3	2556.298	I
28	2589.188	I
500	2592.534	I
8	2644.184	I
1200	2651.172	I
500	2651.568	I
500	2691.341	I
850	2709.624	I
400	2729.78	II
40	2740.426	I
650	2754.588	I
70	2793.925	I
80	2829.008	I
1000	2831.843	II
1000	2845.527	II
750	3039.067	I
600	3067.021	I
20	3124.816	I
35	3211.86	III
40	3255.05	III
110	3269.489	I
40	3434.03	III
300	3499.21	II
60	3554.19	IV
50	3676.65	IV
200	4178.96	III
70	4226.562	I
200	4260.85	III
150	4291.71	III
10	4685.829	I
1000	4741.806	II
1000	4814.608	II
50	4824.097	II
100	5131.752	II
200	5178.648	II
3	5194.583	I
6	5265.892	I
6	5513.263	I
8	5564.741	I
8	5607.010	I
6	5616.135	I
7	5621.426	I
6	5664.226	I
5	5664.842	I
9	5691.954	I
6	5701.776	I
5	5717.877	I
6	5801.029	I
9	5802.093	I
1000	5893.389	II
500	6021.041	II
75	6283.452	II
100	6336.377	II
100	6484.181	II
6	6557.488	I
50	7049.369	II
30	7145.390	II
5	7353.334	I
7	7384.208	I
10	7833.575	I
10	8031.039	I
6	8044.165	I
10	8256.013	I
10	8482.21	I
9	8700.60	I
5	9068.785	I
5	9095.957	I
6	9398.868	I
20	9474.993	II
20	9475.645	II
4	9492.559	I
7	9625.664	I
5	10039.436	I
4	10200.952	I
10	10382.427	I
10	10404.913	I
8	10734.068	I
8	10947.416	I
10	11125.130	I
230	11252.83	I
600	11714.76	I
1300	12069.20	I
1050	12391.58	I
235	13107.61	I
470	14822.38	I
150	16759.79	I
135	17214.34	I
70	18811.86	I
62	19279.24	I
28	20673.64	I

Gold Au Z = 79

100	843.44	III
100	845.14	III
200	945.10	III
100	1040.63	III
80	1044.49	III
80	1046.81	III
100 h	1239.96	III
100	1278.51	III
100	1314.84	III
100 h	1328.37	I
200	1336.72	III
180	1341.68	III
100	1348.89	III
150	1350.32	III
150	1355.61	III
150	1356.13	III
50	1363.98	I
500	1365.40	III
200	1367.17	III
60	1368.62	I
70	1374.82	I
50	1375.76	I
180	1377.73	III
150	1378.69	III
150	1379.98	III
125	1380.53	III
200	1381.36	III
80	1382.75	I
50	1385.33	I
300	1385.79	III
100	1389.41	III
180	1391.46	III
60	1392.27	I
180	1396.00	III
50	1402.12	I
100	1402.91	III
70	1407.38	I
100	1408.45	I
225	1409.50	III
250	1413.80	III
100	1414.27	III
100	1417.09	III
125	1417.39	III
150	1427.42	III
300	1428.93	III
80	1429.19	I
250	1430.06	III
275	1433.37	III
50	1435.79	I
250	1435.81	III
300	1439.12	III
200	1441.21	III
150	1446.37	III
250	1448.42	III
250	1454.95	III
100	1464.72	III
150	1471.28	III
100	1474.73	III
150	1481.10	III
100	1481.76	I
300	1487.15	III
250	1487.91	III
200	1489.47	III
250	1500.37	III
200	1502.47	III
200	1503.74	III
100	1542.00	III
100	1548.50	III
200	1567.54	III
200	1574.85	III
200	1579.44	III
150	1584.10	III
200	1587.16	I
200	1589.56	III
150	1593.41	III
70	1598.24	I
200	1600.51	III
250	1617.16	III
100	1617.78	III
500	1621.93	III
100	1624.34	I
300 d	1629.13	III
250	1638.88	III
50	1639.90	I
100	1644.17	III
150	1646.67	I
250	1652.74	III
250	1664.77	III
100	1665.76	I
100	1668.11	III
125	1673.93	III
1000	1693.94	III
150	1697.09	III
200	1698.98	III
200	1699.34	I
200	1700.00	III
200	1702.25	III
100	1707.53	III
250	1710.16	III
200	1715.69	III
100	1716.71	III
300	1717.83	III
500	1727.31	III
100 d	1733.17	III
300	1738.48	III
150	1744.39	III
500	1746.10	III
500	1756.92	III
500	1761.95	III
300	1767.42	III
100	1774.42	III
800	1775.17	III
200	1776.40	III
100	1780.57	III
60	1783.22	II
300	1786.11	III
150	1792.65	III
500	1793.76	III
200	1801.98	III
400	1805.24	III
100	1809.81	III
400	1821.17	III
400	1844.89	III
150	1848.83	III
500	1861.80	III
150	1871.92	III
100	1879.83	I
150	1918.28	III
100	1932.04	III
100	1935.42	III
200	1948.79	III
100	1958.47	III
400	1989.63	III
150	1996.85	III
11000	2012.00	I
2600	2021.38	I
150	2082.09	II
300	2083.09	III
60	2110.68	II
100	2159.08	III
80	2167.33	III

Intensity	Wavelength/Å	
200	2172.20	III
100	2184.11	III
500	2188.97	III
70	2248.56	II
80	2263.62	II
300	2322.27	III
180	2352.65	I
100	2382.40	III
120	2387.75	I
150	2402.71	III
150	2405.12	III
2600	2427.95	I
60	2533.52	II
250	2641.48	I
3400	2675.95	I
1100	2748.25	I
100	2780.82	I
1000	2802.04	II
300	2819.79	II
100	2822.55	II
100 h	2825.44	II
300	2837.85	II
100	2846.92	II
100	2856.74	II
300	2883.45	I
300	2891.96	I
100	2893.25	II
100	2907.04	II
300	2913.52	II
300	2918.24	II
100	2954.22	II
100 h	2990.27	II
300	2994.80	II
320	3029.20	I
300	3065.42	I
100	3122.50	II
1600	3122.78	I
100	3194.72	I
100	3227.99	III
300	3230.63	I
300	3308.30	I
300	3309.64	I
100	3309.86	III
100	3320.12	I
100	3355.15	I
100 h	3391.31	I
100	3395.40	I
100	3467.21	I
300	3557.36	I
300	3586.73	I
100	3611.57	I
100 h	3631.31	I
300	3637.90	I
100 h	3645.02	I
100	3650.74	I
100	3709.62	I
100	3796.01	I
100	3874.73	I
100 h	3892.26	I
400	3897.86	I
300	3909.38	I
100	3927.69	I
400	4040.93	I
700	4065.07	I
100	4084.10	I
100	4241.80	I
200	4315.11	I
120 h	4437.27	I
250	4488.25	I
900 h	4607.51	I
100 h	4620.56	I
500	4792.58	I
100	4811.60	I
100	5147.44	I
300	5230.26	I
100 h	5261.76	I
100	5655.77	I
100 h	5721.36	I
300	5837.37	I
100 h	5862.93	I
300 h	5956.96	I
600	6278.17	I
100	6562.68	I
600	7510.73	I
10	8145.06	I
10	9254.28	I

Hafnium Hf Z = 72

220	545.41	V
180	600.00	V
200	618.27	IV
200	644.54	IV
400	647.39	IV
600	665.65	IV
200	673.49	IV
270	867.25	V
180	875.88	V
180	885.58	V
180	896.14	V
180	901.54	V
180	919.10	V
270	921.67	V
245	951.62	V
180	960.12	V
180	964.74	V
160	971.51	V
160	1092.76	V
160	1201.76	V
270	1232.03	V
200	1233.59	V
160	1237.42	V
160	1239.53	V
160	1244.46	V
440	1396.66	V
270	1400.09	V
160	1401.70	V
370	1407.17	V
370	1408.38	V
270	1412.28	V
270	1413.51	V
160	1421.96	V
220	1422.53	V
370	1433.43	V
370	1437.27	V
500	1437.73	V
370	1445.40	V
270	1457.91	V
100	1717.21	IV
270	1719.32	V
550	1729.08	V
750	1731.83	V
750	1733.96	V
440	1741.74	V
1000	1749.11	V
1000	1750.19	V
500	1760.89	V
370	1765.62	V
270	1774.02	V
6200	2012.78	II
8500	2028.18	II
300	2070.94	III
1200	2096.18	II
200 h	2099.30	III
200 h	2110.31	III
200	2155.66	III
200	2183.50	III
200	2195.44	III
540	2210.82	II
200	2234.59	III
320	2254.01	II
160	2255.15	II
250	2266.83	II
620	2277.16	II
200 h	2313.44	III
230	2321.14	II
580	2322.47	II
300	2323.25	II
300	2324.89	II
200	2332.97	II
300	2336.47	III
200	2337.33	II
230	2343.32	II
320	2347.44	II
540	2351.22	II
250	2380.30	II
250	2383.540	III
170	2393.18	II
450	2393.36	II
670	2393.83	II
540	2405.42	II
370	2410.14	II
320	2417.69	II
390	2447.25	II
450	2460.49	II
400	2461.74	III
430	2464.19	II
210	2469.18	II
2000	2495.16	III
290	2496.99	II
580	2512.69	II
580	2513.03	II
1000	2515.16	III
890	2516.88	II
340	2531.19	II
200	2537.33	II
320	2551.40	II
400 h	2560.74	III
250	2563.61	II
300 h	2567.46	III
890	2571.67	II
320	2573.90	II
320	2576.82	II
300	2578.14	II
320	2582.54	II
390	2606.37	II
450	2607.03	II
230	2613.60	II
450	2622.74	II
160	2637.00	I
1100	2638.71	II
1100	2641.41	II
160	2642.75	I
670	2647.29	II
160	2657.84	II
210	2661.88	II
290	2683.35	II
200	2687.22	III
670	2705.61	I
210	2712.42	II
250	2718.59	I
710	2738.76	II
200	2743.64	I
360	2751.81	II
500	2753.60	III
450	2761.63	I
160	2766.96	I
170	2773.02	I
980	2773.36	II
180	2774.02	II
390	2779.37	I
230	2808.00	II
230	2813.86	II
170	2814.48	II
230	2817.68	I
200	2819.74	I
1200	2820.22	II
490	2822.68	II
180	2833.28	I
410	2845.83	I
270	2849.21	II
270	2850.96	I
180	2851.21	II
180	2860.56	I
760	2861.01	II
760	2861.70	II
2100	2866.37	I
210	2887.14	I
800	2889.62	I
1800	2898.26	I
1200	2904.41	I
890	2904.75	I
2000	2916.48	I
580	2918.58	I
320	2919.59	II
180	2924.62	I

Intensity	Wavelength/Å	
490	2929.63	II
450	2929.90	I
710	2937.80	II
2000	2940.77	I
160	2944.71	I
1200	2950.68	I
1100	2954.20	I
540	2958.02	I
1400	2964.88	I
620	2966.93	I
710	2968.81	II
890	2975.88	II
1100	2980.81	I
210	2982.72	I
170	3000.10	II
800	3005.56	I
1100	3012.90	II
540	3016.78	I
1100	3016.94	II
980	3018.31	I
1200	3020.53	I
410	3031.16	II
710	3050.76	I
1100	3057.02	I
850	3067.41	I
2100	3072.88	I
170	3074.10	I
250	3074.79	I
430	3080.84	I
200	3096.76	I
340	3101.40	II
710	3109.12	II
710	3131.81	I
850	3134.72	II
170	3139.65	II
220	3145.32	II
220	3148.41	I
450	3156.63	I
270	3159.82	I
710	3162.61	II
450	3168.39	I
890	3172.94	I
450	3176.86	II
220	3181.01	I
360	3193.53	II
670	3194.19	II
200	3196.93	I
310	3206.11	I
180	3210.98	I
180	3217.30	II
180	3220.61	II
360	3247.66	I
220	3249.53	I
890	3253.70	II
270	3255.28	II
180	3273.66	II
200 h	3279.67	III
270	3279.98	II
160	3291.05	I
210	3306.12	I
340	3310.27	I
670	3312.86	I
180	3317.99	II
890	3332.73	I
370	3352.06	II
230	3358.91	I
180	3360.06	I
180	3378.93	I
230	3384.70	II
170	3386.21	I
800	3389.83	II
230	3392.81	I
230	3394.59	II
230	3397.26	I
230	3397.60	I
2300	3399.80	II
170	3400.21	I
180	3402.51	I
230	3410.17	II
230	3417.34	I
410	3419.18	I
200	3428.37	II
250	3438.24	II
710	3472.40	I
200	3478.99	II
480	3479.28	II
250	3495.75	II
250	3497.16	I
980	3497.49	I
1200	3505.23	II
980	3523.02	I
980	3535.54	II
760	3536.62	I
180	3548.81	I
540	3552.70	II
1300	3561.66	II
270	3567.36	I
1100	3569.04	II
210	3597.42	II
540	3599.87	I
800	3616.89	I
320	3630.87	II
800	3644.36	II
320	3649.10	I
200	3651.84	I
220	3665.35	II
200	3672.27	I
480	3675.74	I
2200	3682.24	I
280	3696.51	I
240	3699.72	II
340	3701.15	II
1000	3717.80	I
650	3719.28	II
160	3729.10	I
460	3733.79	I
160	3737.88	II
400	3746.80	I
170	3766.92	II
200	3768.25	I
1400	3777.64	I
1400	3785.46	I
650	3793.37	II
850 d	3800.38	I
320	3811.78	I
1300	3820.73	I
280	3830.02	I
800	3849.18	I
600	3858.31	I
230	3860.91	I
200	3872.55	II
160	3877.10	II
380	3880.82	II
200	3882.52	I
200	3889.23	I
200	3889.33	I
620	3899.94	I
620	3918.09	II
200	3923.90	II
320	3931.38	I
410	3951.83	I
160	3968.01	I
200	3973.48	I
180	4032.27	I
230	4062.84	I
180	4083.35	I
540	4093.16	II
1100	4174.34	I
160	4206.58	II
190	4209.70	I
170	4228.08	I
170	4232.44	II
170	4260.98	I
200	4263.39	I
170	4272.85	II
320	4294.79	I
160	4330.27	I
180	4336.66	II
250	4356.33	I
180	4370.97	II
160	4417.91	I
200	4438.04	I
250	4565.94	I
500 d	4598.80	I
230	4620.86	I
210	4655.19	I
120	4699.01	I
160	4782.74	I
310	4800.50	I
130	4859.24	I
120	4975.25	I
95	5018.20	I
95	5047.45	I
75	5170.18	I
230	5181.86	I
110	5243.99	I
120	5294.87	I
110	5354.73	I
110	5373.86	I
75	5452.92	I
230	5550.60	I
230	5552.12	I
95	5613.27	I
160	5719.18	I
95	6098.67	I
95	6185.13	I
85	6789.27	I
160	6818.94	I
160	7063.83	I
570	7131.81	I
650	7237.10	I
410	7240.87	I
360	7624.40	I
110	7740.17	I
310	7845.35	I
130	7920.71	I
250	7994.73	I
130	8204.58	I
150	8546.48	I
160	8640.06	I
40	8711.24	I
65	9004.73	I

Helium He Z = 2

15	231.454	II
20	232.584	II
30	234.347	II
50	237.331	II
100	243.027	II
300	256.317	II
1000	303.780	II
500	303.786	II
10	320.293	I
2	505.500	I
3	505.684	I
4	505.912	I
5	506.200	I
7	506.570	I
10	507.058	I
15	507.718	I
20	508.643	I
25	509.998	I
35	512.098	I
50	515.616	I
100	522.213	I
400	537.030	I
1000	584.334	I
50	591.412	I
5	958.70	II
6	972.11	II
8	992.36	II
15	1025.27	II
30	1084.94	II
35	1215.09	II
50	1215.17	II
120	1640.34	II
180	1640.47	II
7	2385.40	II
9	2511.20	II
50	2577.6	I
1	2723.19	I
12	2733.30	II
2	2763.80	I
10	2818.2	I
4	2829.08	I

Intensity	Wavelength/Å	
10	2945.11	I
40	3013.7	I
20	3187.74	I
3	3202.96	II
15	3203.10	II
1	3354.55	I
2	3447.59	I
1	3587.27	I
3	3613.64	I
2	3634.23	I
3	3705.00	I
1	3732.86	I
10	3819.607	I
1	3819.76	I
500	3888.65	I
20	3964.729	I
1	4009.27	I
50	4026.191	I
5	4026.36	I
12	4120.82	I
2	4120.99	I
3	4143.76	I
10	4387.929	I
3	4437.55	I
200	4471.479	I
25	4471.68	I
6	4685.4	II
30	4685.7	II
30	4713.146	I
4	4713.38	I
20	4921.931	I
100	5015.678	I
10	5047.74	I
5	5411.52	II
500	5875.62	I
100	5875.97	I
8	6560.10	II
100	6678.15	I
3	6867.48	I
200	7065.19	I
30	7065.71	I
50	7281.35	I
1	7816.15	I
2	8361.69	I
2	9063.27	I
2	9210.34	I
10	9463.61	I
4	9516.60	I
3	9526.17	I
1	9529.27	I
1	9603.42	I
3	9702.60	I
6	10027.73	I
2	10031.16	I
15	10123.6	II
1	10138.50	I
10	10311.23	I
2	10311.54	I
3	10667.65	I
300	10829.09	I
1000	10830.25	I
2000	10830.34	I
9	10913.05	I
3	10917.10	I
4	11626.4	II
30	11969.12	I
20	12527.52	I
50	12784.99	I
20	12790.57	I
7	12845.96	I
10	12968.45	I
2	12984.89	I
12	15083.64	I
200	17002.47	I
1	18555.55	I
6	18636.8	II
500	18685.34	I
200	18697.23	I
100	19089.38	I
20	19543.08	I
1000	20581.30	I
80	21120.07	I
10	21121.43	I
20	21132.03	I
3	30908.5	II
4	40478.90	I

Holmium Ho Z = 67

170	2502.91	II
170	2533.80	I
190	2605.86	II
270	2750.35	II
270	2769.89	II
300	2824.20	II
270 c	2831.69	II
270	2849.10	II
360	2880.26	II
460	2880.98	II
570 c	2909.41	II
410 c	2979.63	II
410	2987.64	II
480 c	3049.38	II
410 c	3054.00	II
500 c	3057.45	II
500 c	3082.34	II
910	3084.36	II
430 c	3086.54	II
760	3118.50	II
580 c	3166.62	II
810	3173.78	II
810 c	3181.50	II
980 c	3281.97	II
630 c	3337.23	II
980 c	3343.58	II
8100 c	3398.98	II
810 c	3410.26	II
1400 c	3414.90	II
5400	3416.46	II
1200	3421.63	II
2000 c	3425.34	II
2000 c	3428.13	II
3200	3453.14	II
16000 c	3456.00	II
1600	3461.97	II
810 c	3473.91	II
5400 c	3474.26	II
6300	3484.84	II
2500 c	3494.76	II
810 c	3498.88	II
810	3510.73	I
4100 c	3515.59	II
410 c	3519.94	II
630	3540.76	II
1600	3546.05	II
1100 c	3556.78	II
410	3560.15	II
410 c	3573.24	II
630 c	3574.80	II
810	3579.12	I
410	3580.75	II
410	3581.83	II
630 c	3592.23	II
1100 cw	3598.77	II
540 c	3600.95	II
410	3618.43	I
430 c	3626.69	II
490	3627.25	II
430 c	3631.76	II
430 c	3638.30	II
1600 c	3662.29	I
1400	3667.97	I
720	3679.19	I
670	3679.70	I
720	3682.65	I
580	3690.65	I
410	3700.04	I
490 c	3702.35	II
430	3712.88	I
450	3720.72	I
1100	3731.40	I
810	3736.35	I
3200 cw	3748.17	II
8900 c	3796.75	II
8900 c	3810.73	II
410 c	3835.35	II
1300 cw	3837.51	II
410 c	3842.05	II
1100	3843.86	II
490 c	3846.73	II
1800 c	3854.07	II
2700 c	3861.68	II
3000 c	3888.96	II
13000 c	3891.02	II
1300 cw	3905.68	II
580	3955.73	I
490	3959.68	I
2700	4040.81	I
5400 c	4045.44	II
8100	4053.93	I
1700	4065.09	II
720	4068.05	I
8900	4103.84	I
2900	4108.62	I
1500	4120.20	I
1300	4125.65	I
4300	4127.16	I
1500	4136.22	I
980 cw	4152.61	II
8100	4163.03	I
2500	4173.23	I
540	4194.35	I
2000	4227.04	I
1300 cw	4254.43	I
490	4264.05	I
1300	4350.73	I
300	4477.64	II
290	4629.10	II
80	4701.69	II
130	4709.84	II
130 c	4717.52	I
290	4742.04	II
100 c	4757.01	I
65	4782.92	I
290	4939.01	I
250 c	4967.21	II
220	4979.97	I
90	4995.05	I
130	5042.37	I
80	5093.07	I
140	5127.81	I
130	5142.59	II
110	5143.22	II
160	5149.59	II
90 c	5167.88	I
130 c	5182.11	I
90	5190.11	II
65	5251.82	I
90	5301.25	I
80	5330.11	I
90	5359.99	I
100	5407.08	I
70	5566.52	I
65	5627.60	I
140	5659.58	I
140 c	5691.47	I
140 c	5696.57	I
140 c	5860.28	I
70 c	5882.99	I
70	5921.76	I
70 cw	5948.03	I
70	5972.76	I
90	5973.52	I
230 c	5982.90	I
120	6081.79	I
70	6208.65	I
70 c	6305.36	I
70	6550.97	I
260	6604.94	I
120	6628.99	I
55 cw	6694.32	I
55 c	6785.43	I
40 cw	6939.49	I
45 cw	6950.39	I
140	7555.09	I
40 c	7628.42	I

Intensity	Wavelength/Å	
50 c	7693.15	I
60 cw	7815.48	I
60	7894.64	I
50	8512.94	I
40	8670.19	I
90	8915.98	II
Hydrogen H Z = 1		
15	926.226	I
20	930.748	I
30	937.803	I
50	949.743	I
100	972.537	I
300	1025.722	I
1000	1215.668	I
500	1215.674	I
5	3835.384	I
6	3889.049	I
8	3970.072	I
15	4101.74	I
30	4340.47	I
80	4861.33	I
120	6562.72	I
180	6562.852	I
5	9545.97	I
7	10049.4	I
12	10938.1	I
20	12818.1	I
40	18751.0	I
5	21655.3	I
8	26251.5	I
15	40511.6	I
4	46525.1	I
6	74578.	I
Indium In Z = 49		
17	378.61	V
17	386.21	V
14	388.91	V
25	393.89	V
25	400.57	V
25	402.39	V
622	472.71	IV
689	479.39	IV
709	498.62	IV
10	882.24	III
10	890.84	III
10	915.87	III
85	954.67	IV
87	973.50	IV
86	991.60	IV
89	1024.68	IV
85	1024.79	IV
88	1031.45	IV
82	1031.98	IV
80	1054.43	IV
84	1063.03	IV
83	1068.25	IV
82	1069.82	IV
86	1077.64	IV
90	1082.10	IV
83	1086.33	IV
82	1096.81	IV
84	1097.18	IV
85	1116.10	IV
80	1124.06	IV
90	1131.46	IV
85	1144.43	IV
80	1145.41	IV
89	1146.62	IV
83	1154.11	IV
84	1154.60	IV
90	1157.71	IV
90	1157.82	IV
85	1159.78	IV
88	1176.50	IV
85	1191.58	IV
83	1204.87	IV
90	1206.55	IV
88	1221.50	IV
85	1221.90	IV
85	1233.58	IV
87	1235.84	IV
90	1373.20	IV
88	1398.77	IV
81	1412.09	IV
100	1625.42	III
100	1748.83	III
30	1842.41	III
40	1850.30	III
30	2154.08	III
50	2205.28	II
40	2281.64	II
100 c	2306.05	II
90 d	2313.21	II
70 d	2327.95	II
80 h	2334.57	II
110 d	2382.63	II
70 h	2427.20	II
100	2447.90	II
110 d	2488.62	II
90	2488.95	II
80	2498.59	II
100	2499.60	II
90 d	2500.99	II
110 d	2512.31	II
100	2521.37	I
100	2527.41	III
160 d	2554.44	II
1100	2560.15	I
200	2601.76	I
90 d	2654.70	II
100 d	2662.63	II
140 d	2668.65	II
140 d	2674.56	II
80	2683.12	II
1600	2710.26	I
300	2713.94	I
80	2726.15	III
130 d	2749.75	II
700	2753.88	I
90 d	2818.97	II
180 c	2836.92	I
80	2865.68	II
120 d	2890.18	II
1100	2932.63	I
100	2941.05	II
100	2982.80	III
110 c	2999.40	II
100	3008.08	III
8000	3039.36	I
110 d	3099.80	II
180 c	3101.8	II
130 c	3138.60	II
80 c	3142.75	II
130 d	3146.70	II
150	3155.77	II
100 c	3158.40	II
90 c	3176.30	II
90 d	3198.11	II
13000	3256.09	I
3000	3258.56	I
90 c	3338.50	II
100 c	3404.28	II
110 d	3438.40	II
180 c	3693.91	II
95 c	3708.13	II
380 w	3716.14	II
120 c	3718.30	II
160 c	3718.72	II
160 c	3723.40	II
170 w	3795.21	II
230 c	3799.21	II
250 c	3834.65	II
200 c	3842.18	II
100	3852.82	III
100	3889.78	II
100 c	3902.07	II
250 w	3962.35	II
120 c	4004.66	II
140 d	4013.92	II
100	4023.77	III
150	4032.32	III
410 w	4056.94	II
100	4071.57	III
100	4072.93	III
17000	4101.76	I
140 c	4205.14	II
100 d	4213.04	II
110 d	4219.66	II
100	4252.68	III
150 d	4372.87	II
150 c	4500.78	II
18000	4511.31	I
110 c	4549.01	II
140 c	4570.85	II
180 w	4578.02	II
180 w	4578.40	II
140 c	4616.08	II
170 c	4617.17	II
250 c	4620.14	II
150 w	4620.70	II
170 c	4627.30	II
140 c	4637.04	II
380 c	4638.16	II
220 c	4644.58	II
360 c	4655.62	II
320 w	4656.74	II
190 c	4681.11	II
450 w	4684.8	II
90 d	4907.06	II
150 c	4973.77	II
80 h	5109.36	II
100 w	5115.14	II
140 c	5117.40	II
270 c	5120.80	II
200 w	5121.75	II
80 d	5129.85	II
240 c	5175.42	II
140 c	5184.44	II
200	5248.77	III
150 c	5309.45	II
80	5411.41	II
140 c	5418.45	II
220 w	5436.70	II
130 c	5497.50	II
140 c	5507.08	II
320 c	5513.00	II
250 w	5523.28	II
130 c	5536.50	II
190 w	5555.45	II
240 c	5576.90	II
200 w	5636.70	II
100	5645.15	III
160 c	5708.50	II
100 c	5721.80	II
100	5819.50	III
210 c	5853.15	II
490 w	5903.4	II
260 w	5915.4	II
120 c	5918.78	II
130 c	6062.9	II
250 c	6095.95	II
210 c	6108.66	II
180 w	6115.9	II
230 w	6128.7	II
240 w	6129.4	II
320 w	6132.1	II
150 c	6140.0	II
90	6143.23	II
140 c	6148.10	II
190 w	6149.5	II
80	6161.15	II
180 w	6162.45	II
200	6197.72	III
100 c	6224.28	II
280 w	6228.3	II
140 w	6231.1	II
270 w	6304.8	II
290 w	6362.3	II
300 w	6469.0	II
210 c	6541.20	II
190 c	6751.88	II
180 c	6765.9	II
100 c	6783.72	II

Intensity	Wavelength/Å	
320 w	6891.5	II
380 w	7182.9	II
180 c	7255.0	II
210 c	7276.5	II
180 c	7303.4	II
320 c	7350.6	II
100 c	7632.7	II
100 c	7682.9	II
210 c	7740.7	II
100 c	7776.96	II
180 c	7789.0	II
90 c	7840.9	II
240 c	8227.0	II
100 w	8813.5	II
80 c	8832.6	II
120 c	9197.7	II
120 c	9202.0	II
220 w	9213.0	II
160 d	9241.1	II
100	9977.86	I
200	10257.03	I
100 h	10744.31	I
20	11334.72	I
20	11731.48	I
10	12912.59	I
9	13429.96	I
7	14719.08	I
6	22291.06	I
7	23879.13	I
Iodine I Z = 53		
30	363.78	V
36	380.74	V
45	565.53	V
50	607.57	V
6	612.46	IV
6	666.81	III
8	705.11	III
7	784.64	III
7	784.80	III
8	795.52	III
7	919.28	IV
10000	1034.66	II
8	1094.20	III
10000	1139.80	II
10000	1160.56	II
20000	1166.48	II
10000	1178.65	II
15000	1187.34	II
10000	1190.85	II
200	1218.41	I
20000	1220.89	II
600	1224.05	I
600	1224.08	I
500	1228.89	I
20000	1234.06	II
600	1251.34	I
8	1252.35	III
2500	1259.15	I
3000	1259.51	I
800	1261.27	I
600	1267.57	I
600	1267.60	I
1500	1275.26	I
3000	1289.40	I
10000	1300.34	I
3000	1302.98	I
3000	1313.95	I
3000	1317.54	I
2000	1330.19	I
20000	1336.52	II
5000	1355.10	I
3000	1357.97	I
5000	1360.97	I
3000	1361.11	I
2500	1367.71	I
2500	1368.22	I
4000	1383.23	I
3000	1390.75	I
2000	1392.90	I
2000	1400.01	I
8000	1425.49	I
5000	1446.26	I
5000	1453.18	I
5000	1457.39	I
5000	1457.47	I
10000	1457.98	I
2500	1458.79	I
4000	1459.15	I
2500	1465.83	I
1000	1485.92	I
5000	1492.89	I
5000	1507.04	I
5000	1514.68	I
15000	1518.05	I
2500	1526.45	I
5000	1593.58	I
5000	1617.60	I
2500	1640.78	I
15000	1702.07	I
12000	1782.76	I
5000	1799.09	I
75000	1830.38	I
15000	1844.45	I
2000	2061.63	I
7	2361.13	IV
6	2372.45	IV
7	2376.46	IV
8	2387.11	IV
9	2426.10	IV
8	2475.35	IV
8	2519.74	IV
8	2545.67	IV
7	2545.71	III
8	2652.23	IV
5000	3078.75	II
200	4102.23	I
200	4129.21	I
100 d	4134.15	I
500 d	4321.84	I
250	4763.31	I
1000	4862.32	I
200	4916.94	I
10000	5119.29	I
3000 c	5161.20	II
1000	5234.57	I
3000 c	5245.71	II
10000	5338.22	II
5000 c	5345.15	II
600 c	5427.06	I
3000	5435.83	II
2000 c	5464.62	II
10000	5625.69	II
2000 c	5690.91	II
4000 c	5710.53	II
1000 d	5764.33	I
2000	5894.03	I
5000	5950.25	II
300	5984.86	I
2000 d	6024.08	I
2000 c	6074.98	II
1000	6082.43	I
2000 c	6127.49	II
800	6191.88	I
500	6213.10	I
800	6244.48	I
1000	6293.98	I
500	6313.13	I
800	6330.37	I
400	6333.50	I
2000	6337.85	I
1000	6339.44	I
500	6359.16	I
1000	6566.49	I
2000	6583.75	I
1000	6585.27	I
5000	6619.66	I
500	6661.11	I
500 c	6697.29	I
400	6732.03	I
4000	6812.57	II
500	6989.78	I
500	7120.05	I
1200	7122.05	I
2000	7142.06	I
1000	7164.79	I
400 d	7191.66	I
700	7227.30	I
1000	7236.78	I
500	7237.84	I
5000	7402.06	I
1000	7410.50	I
500	7416.48	I
5000	7468.99	I
500 c	7490.52	I
2000	7554.18	I
500 d	7556.65	I
2000 c	7700.20	I
600	7897.98	I
500	7969.48	I
1000	8003.63	I
99000	8043.74	I
300 d	8065.70	I
1000	8090.76	I
800 c	8169.38	I
500 d	8222.57	I
4000	8240.05	I
10000 c	8393.30	I
1000	8486.11	I
1500 c	8664.95	I
500 c	8700.80	I
250 d	8748.22	I
1000	8853.24	I
2000	8853.80	I
3000	8857.50	I
1000 d	8898.50	I
400	8964.69	I
400	8993.13	I
5000	9022.40	I
15000	9058.33	I
1000	9098.86	I
12000	9113.91	I
600	9128.03	I
600	9227.74	I
1000	9335.05	I
4000	9426.71	I
3000	9427.15	I
2000	9598.22	I
2000	9649.61	I
3000 d	9653.06	I
5000	9731.73	I
500	10003.05	I
750	10131.16	I
1000	10238.82	I
400	10375.20	I
400	10391.74	I
5000	10466.54	I
400	11236.56	I
350	11558.46	I
320	11778.34	I
450	11996.86	I
300	12033.69	I
150	12304.58	I
60	13149.16	I
140	13958.27	I
200	14287.02	I
100	14460.00	I
225	15032.57	I
105	15528.65	I
150	16037.33	I
15	18275.71	I
20	18348.52	I
15	18982.41	I
35	19070.17	I
110	19105.12	I
50	19370.02	I
10	20648.69	I
220	22183.03	I
150	22226.53	I
30	22309.21	I
32	24420.82	I
12	27365.42	I
9	27573.05	I
10	30361.93	I
8	30383.88	I

Intensity	Wavelength/Å	
10	34295.73	I
9	34513.11	I
3	40228.54	I
2	41633.80	I
Iridium Ir Z = 77		
9900	2010.65	I
8700	2022.35	I
15000	2033.57	I
6200	2052.22	I
5000	2060.64	I
3700	2083.22	I
3100	2085.74	I
17000	2088.82	I
14000	2092.63	I
2700	2112.68	I
1800	2119.54	I
2000	2125.44	I
4500	2126.81	II
2000	2127.52	I
4500	2127.94	I
3700	2148.22	I
2500	2150.54	I
3500	2152.68	II
2900	2155.81	I
7900	2158.05	I
2100	2162.88	I
5800	2169.42	II
4500	2175.24	I
2700	2178.17	I
1600	2187.43	II
1100	2190.38	II
740	2191.64	I
910	2208.09	II
1300	2220.37	I
790	2221.07	II
2500	2242.68	II
620	2245.76	II
2100	2253.38	I
2100	2255.10	I
1400	2255.81	I
350	2258.51	I
1400	2258.86	I
830	2264.61	I
1100	2266.33	I
1000	2268.90	I
660	2280.00	I
950	2281.02	II
660	2281.91	I
330	2284.60	I
330	2295.08	I
790	2298.05	I
460	2299.53	I
910	2300.50	I
2700	2304.22	I
410	2305.47	I
210	2307.27	I
910	2308.93	I
460	2315.38	I
410	2321.45	I
410	2321.58	I
210	2327.98	I
540	2333.30	I
740	2333.84	I
580	2334.50	I
1600	2343.18	I
740	2343.61	I
580	2355.00	I
230	2357.53	II
410	2358.16	I
500	2360.73	I
2500	2363.04	I
370	2368.04	II
3500	2372.77	I
290	2375.09	II
250	2377.28	I
250	2377.98	I
500	2379.38	I
540	2381.62	I
210	2383.17	I
1300	2386.89	I
2500	2390.62	I
2700	2391.18	I
230	2407.59	I
290	2409.37	I
290	2410.17	I
290	2410.73	I
540	2413.31	I
370	2415.86	I
620	2418.11	I
210	2424.89	I
370	2424.99	I
290	2425.66	I
540	2427.61	I
540	2431.24	I
1300	2431.94	I
270	2435.14	I
250	2445.34	I
250	2447.76	I
910	2452.81	I
1300	2455.61	I
230	2455.87	I
210	2457.03	I
210	2457.23	I
870	2467.30	I
3300	2475.12	I
210	2478.11	I
2100	2481.18	I
620	2493.08	I
210	2496.27	I
250	2502.63	I
4100	2502.98	I
210	2513.71	I
990	2533.13	I
1100	2534.46	I
580	2537.22	I
580	2542.02	I
7900	2543.97	I
790	2546.03	I
210	2551.40	I
210	2555.35	I
910	2564.18	I
210	2569.88	I
230	2572.70	I
740	2577.26	I
740	2592.06	I
740	2599.04	I
700	2608.25	I
1800	2611.30	I
210	2614.98	I
330	2617.78	I
210	2619.88	I
250	2625.32	I
700	2634.17	I
250	2639.42	I
3500	2639.71	I
210	2644.19	I
1800	2661.98	I
350	2662.63	I
2700	2664.79	I
520	2669.91	I
520	2671.84	I
330	2673.61	I
270	2692.34	I
3000	2694.23	I
330	2772.46	I
250	2775.55	I
520	2781.29	I
330	2785.22	I
540	2797.35	I
1600	2797.70	I
380	2798.18	I
410	2800.82	I
680	2823.18	I
1200	2824.45	I
820	2836.40	I
1100	2839.16	I
820	2840.22	I
3800	2849.72	I
380	2875.60	I
380	2875.98	I
270	2877.68	I
820	2882.64	I
650	2897.15	I
260	2901.95	I
260	2904.80	I
200	2907.24	I
440	2916.36	I
230	2918.57	I
4400	2924.79	I
1200	2934.64	I
880	2936.68	I
250	2938.47	I
2700	2943.15	I
230	2946.97	I
200	2949.76	I
1200	2951.22	I
200	2974.95	I
440	2980.65	I
300	2996.08	I
220	3002.25	I
600	3003.63	I
270	3017.31	I
380	3029.36	I
330	3039.26	I
300	3047.16	I
300	3049.44	I
300	3057.28	I
1600	3068.89	I
320	3083.22	I
240	3086.44	I
390	3088.04	I
510	3100.29	I
510	3100.45	I
340	3120.76	I
200	3121.78	I
3400	3133.32	I
490	3168.88	I
370	3177.58	I
370	3198.92	I
610	3212.12	I
370	3219.51	I
5100	3220.78	I
300	3229.28	I
470	3241.52	I
200	3262.01	I
390	3266.44	I
200	3322.60	I
560	3368.48	I
660	3437.02	I
410	3448.97	I
3200	3513.64	I
220	3515.95	I
410	3522.03	I
320	3558.99	I
1200	3573.72	I
320	3594.39	I
220	3609.77	I
660	3628.67	I
220	3636.20	I
300	3661.71	I
300	3664.62	I
320	3674.98	I
200	3687.08	I
200	3731.36	II
530	3747.20	I
3100	3800.12	I
230	3817.24	I
480	3902.51	I
480	3915.38	I
400	3934.84	I
590	3976.31	I
460	3992.12	I
350	4033.76	I
370	4069.92	I
150	4070.68	I
100	4092.61	I
140	4115.78	I
90	4172.56	I
260	4268.10	I
220	4311.50	I
160	4399.47	I
65	4403.78	I
110	4426.27	I
55	4478.48	I

Intensity	Wavelength/Å	
55	4545.68	I
30	4548.48	I
35	4568.09	I
75	4616.39	I
26	4656.18	I
50	4728.86	I
26	4756.46	I
65	4778.16	I
30	4795.67	I
50	4938.09	I
26	4970.48	I
25	4999.74	I
25	5002.74	I
30	5014.98	I
30	5123.66	I
35	5364.32	I
75	5449.50	I
45	5625.55	I
35	5894.06	I
20	6110.67	I
12	6288.28	I
10	6686.08	I
6	7834.32	I
Iron Fe Z = 26		
350	386.16	V
350	386.88	V
400	387.20	V
400	387.50	V
400	387.76	V
400	387.78	V
400	395.90	V
400	404.62	V
400	405.50	V
800	407.42	V
600	407.44	V
400	407.49	V
500	407.75	V
400	409.71	V
400	410.20	V
600	411.55	V
700	417.39	V
700	418.04	V
500	418.47	V
700	421.06	V
500	421.78	V
500	422.31	V
500	426.06	V
500	426.11	V
350	426.97	V
17	525.69	IV
15	526.29	IV
13	526.63	IV
14	536.61	IV
15	537.10	IV
13	537.26	IV
14	537.79	IV
13	537.94	IV
13	552.14	IV
14	607.53	IV
13	608.80	IV
10	813.38	III
10	844.28	III
10 p	861.83	III
10	891.17	III
10	950.33	III
10	981.37	III
10 w	983.88	III
12	1055.27	II
15	1068.36	II
15	1071.60	II
15	1096.89	II
12	1099.12	II
18	1112.09	II
12	1121.99	II
12	1122.86	II
12	1128.07	II
12	1130.43	II
15	1133.41	II
12	1133.68	II
12	1138.64	II
12	1142.33	II
12	1143.23	II
18	1144.95	II
12	1147.41	II
15	1148.29	II
12	1151.16	II
12	1267.44	II
12	1272.00	II
400	1317.86	V
400	1323.27	V
400	1330.40	V
400	1359.01	V
600	1361.82	V
700	1373.59	V
600	1373.67	V
500	1376.34	V
500	1378.56	V
800	1387.94	V
400	1397.97	V
600	1400.24	V
800	1402.39	V
400	1406.67	V
500	1406.82	V
400	1407.25	V
600	1409.45	V
400	1415.20	V
600	1420.46	V
800	1430.57	V
13	1431.43	IV
800	1440.53	V
400	1442.22	V
800	1446.62	V
700	1448.85	V
400	1449.93	V
700	1456.16	V
500	1459.83	V
400	1460.73	V
500	1462.63	V
700	1464.68	V
500	1465.38	V
400	1466.65	V
500	1469.00	V
500	1479.47	V
10 h	1505.17	III
13	1526.60	IV
13	1530.26	IV
14	1532.63	IV
13	1532.91	IV
15	1533.86	IV
13	1533.95	IV
14	1536.58	IV
10 h	1538.63	III
13	1542.16	IV
14	1542.70	IV
12 h	1550.20	III
13	1566.26	IV
14	1568.27	IV
13	1591.51	IV
13	1592.05	IV
13	1598.01	IV
13	1600.58	IV
10 h	1601.21	III
13	1601.67	IV
13	1603.18	IV
13	1603.73	IV
13	1604.88	IV
13	1605.68	IV
15	1605.97	IV
13	1606.98	IV
17	1609.10	IV
14	1609.83	IV
13	1610.47	IV
13	1611.20	IV
13	1613.64	IV
15	1614.02	IV
13	1614.64	IV
13	1615.00	IV
16	1616.68	IV
14	1617.68	IV
12	1618.47	II
14	1619.02	IV
13	1621.16	IV
14	1621.57	IV
13	1623.38	IV
13	1623.53	IV
15	1626.47	IV
14	1626.90	IV
13	1628.54	IV
13	1630.18	IV
17	1631.08	IV
15	1631.12	II
14	1632.40	IV
13	1634.01	IV
18	1635.40	II
15	1636.32	II
15	1639.40	II
14	1639.40	IV
16	1640.04	IV
14	1640.16	IV
12	1641.76	II
15	1641.87	IV
15	1647.09	IV
12	1647.16	II
15	1651.58	IV
15	1652.90	IV
13	1653.41	IV
13	1656.11	IV
15	1656.65	IV
14	1660.10	IV
13	1662.32	IV
13	1662.52	IV
13	1663.54	IV
13	1668.09	IV
12	1670.74	II
14	1671.04	IV
13	1673.68	IV
14	1675.66	IV
13	1681.36	IV
15	1687.69	IV
15	1698.88	IV
12	1702.04	II
13	1709.81	IV
15	1711.41	IV
14	1712.76	IV
14	1717.90	IV
14	1718.16	IV
14	1719.46	IV
14	1722.71	IV
14	1724.06	IV
16	1725.63	IV
13	1761.08	IV
12	1761.38	II
20	1785.26	II
20	1786.74	II
18	1788.07	II
13	1792.10	IV
13	1796.93	IV
13	1827.98	IV
10	1869.83	III
12	1877.99	III
10	1882.05	III
12	1886.76	III
13	1890.67	III
11	1893.98	III
20	1895.46	III
10 s	1907.58	III
19	1914.06	III
15	1915.08	III
15	1922.79	III
10 p	1926.01	III
18	1926.30	III
15	1930.39	III
14	1931.51	III
30	1934.538	I
25	1937.269	I
14	1937.34	III
10 l	1938.90	III
14 s	1943.48	III
12	1945.34	III
50	1946.988	I
10	1950.33	III
12	1951.01	III
25	1951.571	I
30	1952.59	I

Intensity	Wavelength/Å	
11	1952.65	III
30	1953.005	I
13	1953.32	III
10	1953.49	III
10 w	1954.22	III
60	1957.823	I
11	1958.58	III
60	1960.144	I
13	1960.32	III
30	1961.25	I
50	1962.111	I
12	1963.11	II
15	1987.50	III
14	1991.61	III
13	1994.07	III
12	1995.56	III
12	1996.42	III
10	2061.55	III
12	2068.24	III
14	2078.99	III
100	2084.122	I
10	2084.35	III
12	2090.14	III
15	2097.48	III
12	2097.69	III
12	2103.80	III
10	2107.32	III
15	2151.78	III
12	2157.71	III
50	2157.794	I
12	2158.47	III
10	2161.27	III
40	2166.773	I
12	2166.95	III
12	2171.04	III
15	2174.66	III
300	2178.118	I
12	2180.41	III
250	2186.486	I
60	2186.892	I
120	2187.195	I
250	2191.839	I
150	2196.043	I
80	2200.390	I
80	2200.724	I
15	2208.41	II
10 p	2208.85	III
20	2213.65	II
12	2218.26	II
20	2220.38	II
10	2221.83	III
10	2229.27	III
10	2232.43	III
10	2232.69	III
10	2235.91	III
10	2238.16	III
12 p	2241.54	III
50	2250.790	I
60	2251.874	I
300	2259.511	I
12	2261.59	III
60	2264.389	I
80	2267.085	I
10	2267.42	III
80	2267.469	I
50	2270.862	I
150	2272.070	I
150	2276.026	I
80	2279.937	I
150	2284.086	I
150	2287.250	I
300	2292.524	I
10	2293.06	III
15	2295.86	III
200	2297.787	I
600	2298.169	I
80	2299.220	I
300	2300.142	I
50	2301.684	I
100	2303.424	I
150	2303.581	I
120	2308.999	I
150	2313.104	I
10 p	2317.70	III
10	2319.22	III
200	2320.358	I
10 p	2321.71	III
10	2326.95	III
100	2327.40	II
100	2331.31	II
300	2332.80	II
10 p	2336.77	III
200	2338.01	II
10	2338.96	III
600	2343.49	II
80	2343.96	II
150	2344.28	II
200	2348.11	II
250	2348.30	II
200	2359.12	II
150	2360.00	II
120	2360.29	II
200	2364.83	II
80	2365.76	II
80	2368.59	II
80	2369.456	I
80	2369.95	II
120	2371.430	I
300	2373.624	I
150	2373.74	II
120	2374.518	I
120	2376.43	II
80	2379.27	II
120	2380.76	II
150	2381.835	I
1000	2382.04	II
300	2388.63	II
200	2389.973	I
1000	2395.62	II
300	2399.24	II
800	2404.88	II
250	2406.66	II
80	2406.97	II
300	2410.52	II
200	2411.07	II
150	2413.31	II
80	2417.87	II
60	2420.396	I
60	2423.089	I
150	2424.14	II
120	2428.36	II
120	2430.08	II
80	2432.26	II
60	2438.182	I
150	2439.30	II
150	2439.74	I
100	2442.57	I
250	2443.872	I
100	2444.51	II
50	2445.212	I
100	2445.57	II
60	2447.709	I
100	2453.476	I
1500	2457.598	I
150	2458.78	II
80	2461.28	II
100	2461.86	II
100	2462.181	I
1500	2462.647	I
50	2463.730	I
800	2465.149	I
60	2467.732	I
600	2468.879	I
80	2470.67	II
80	2470.965	I
800	2472.336	I
1000	2472.895	I
200	2473.16	I
600	2474.814	I
60	2476.657	I
120	2479.480	I
1200	2479.776	I
100	2480.16	II
80	2482.12	II
100	2482.66	II
10000	2483.271	I
300	2483.533	I
1000	2484.185	I
50	2485.990	I
800	2486.373	I
100	2486.691	I
100	2487.066	I
120	2487.370	I
4000	2488.143	I
100	2488.945	I
80	2489.48	II
1000	2489.750	I
50	2489.913	I
3000	2490.644	I
100	2490.71	II
2000	2491.155	I
100	2491.40	II
100	2493.18	II
500	2493.26	II
60	2494.000	I
50	2494.251	I
100	2495.87	I
600	2496.533	I
150	2498.90	I
1000	2501.132	I
50	2501.693	I
80	2506.09	II
500	2507.900	I
50	2508.753	I
1000	2510.835	I
120	2511.76	II
80	2512.275	I
400	2512.365	I
80	2516.570	I
300	2517.661	I
800	2518.102	I
150	2519.629	I
50	2522.480	I
4000	2522.849	I
200	2523.66	I
500	2524.293	I
100	2525.02	I
200	2525.39	II
300	2526.29	II
2000	2527.435	I
800	2529.135	I
250	2529.55	II
150	2529.836	I
200	2530.687	I
120	2533.63	II
100	2534.42	II
120	2535.49	II
400	2535.607	I
200	2536.792	I
200	2536.80	II
100	2538.80	II
100	2538.91	II
150	2538.99	II
50	2539.357	I
200	2540.66	II
600	2540.972	I
80	2541.10	II
300	2542.10	I
250	2543.92	I
150	2544.70	I
800	2545.978	I
80	2546.67	II
100	2548.74	II
80	2549.08	II
80	2549.39	II
600	2549.613	I
400	2562.53	II
200	2563.48	II
150	2574.36	II
300	2576.691	I
100	2582.58	II
1500	2584.54	I
650	2585.88	II
90	2591.54	II

Intensity	Wavelength/Å	
90	2593.73	II
650	2598.37	II
2000	2599.40	II
300	2599.57	I
60	2605.657	I
300	2606.51	II
800	2606.827	I
650	2607.09	II
600	2611.87	II
320	2613.82	II
320	2617.62	II
250	2618.018	I
90	2620.41	II
400	2623.53	I
200	2625.67	II
150	2628.29	II
250	2631.05	II
250	2631.32	II
100	2632.237	I
300	2635.809	I
50	2641.646	I
200	2643.998	I
300	2666.812	I
60	2666.965	I
600	2679.062	I
500	2684.75	II
400	2689.212	I
10 h	2695.13	III
200	2699.106	I
80	2706.012	I
400	2706.582	I
60	2708.571	I
200	2711.655	I
80	2714.41	II
50	2716.257	I
50	2717.786	I
250	2718.436	I
4000	2719.027	I
100	2719.420	I
50	2720.197	I
1500	2720.903	I
400	2723.578	I
150	2724.953	I
50	2726.235	I
80	2727.54	II
200	2728.020	I
50	2728.820	I
80	2728.90	II
1000	2733.581	I
60	2734.005	I
50	2734.268	I
500	2735.475	I
50	2735.612	I
500	2737.310	I
120	2737.83	I
400	2739.55	II
250	2742.254	I
800	2742.405	I
200	2743.20	II
150	2743.565	I
200	2744.068	I
80	2744.527	I
300	2746.48	II
100	2749.32	II
500	2749.48	II
1200	2750.140	I
80	2753.29	II
150	2754.032	I
100	2754.426	I
800	2755.73	II
250	2756.328	I
100	2757.316	I
120	2761.780	I
150	2761.81	II
150	2762.026	I
120	2762.772	I
120	2763.109	I
80	2766.910	I
250	2767.522	I
300	2772.07	I
600	2778.220	I
3000	2788.10	I
200	2797.78	I
400	2804.521	I
1500	2806.98	I
10 p	2813.24	III
2500	2813.287	I
300	2823.276	I
600	2825.56	I
50	2825.687	I
120	2828.808	I
1500	2832.436	I
120	2835.950	I
200	2838.119	I
200	2843.631	I
1000	2843.977	I
100	2845.594	I
800	2851.797	I
50	2869.307	I
50	2872.334	I
80	2874.172	I
50	2894.504	I
12	2904.43	III
10	2907.50	III
12	2907.70	III
120	2912.157	I
120	2929.007	I
1200	2936.903	I
60	2941.343	I
1000	2947.876	I
600	2953.940	I
250	2957.364	I
150	2965.254	I
1500	2966.898	I
120	2969.36	I
800	2970.099	I
1200	2973.132	I
500	2973.235	I
600	2981.445	I
1000	2983.570	I
1000	2994.427	I
250	2994.502	I
500	2999.512	I
120	3000.451	I
800	3000.948	I
12	3001.62	III
60	3001.655	I
12 h	3007.28	III
200	3007.282	I
500	3008.14	I
120	3009.569	I
15	3013.17	III
60	3017.627	I
60	3018.983	I
500	3020.491	I
1500	3020.639	I
600	3021.073	I
500	3024.032	I
150	3025.638	I
500	3025.842	I
80	3030.148	I
60	3031.214	I
60	3034.484	I
800	3037.389	I
80	3041.637	I
800	3047.604	I
600	3057.446	I
1000	3059.086	I
250	3067.244	I
120	3075.719	I
120	3091.577	I
80	3098.189	I
100	3099.895	I
100	3099.968	I
60	3100.303	I
100	3100.665	I
10 p	3136.43	III
10	3174.09	III
80	3175.445	I
10	3175.99	III
10	3178.01	III
150	3184.895	I
250	3191.659	I
500	3193.226	I
800	3193.299	I
200	3196.928	I
80	3199.500	I
50	3205.398	I
100	3211.88	I
200	3214.011	I
200	3214.396	I
60	3215.938	I
50	3217.377	I
80	3219.583	I
60	3219.766	I
300	3222.045	I
600	3225.78	I
80	3227.796	I
50	3233.967	I
120	3234.613	I
300	3236.222	I
100	3239.433	I
80	3244.187	I
80	3246.005	I
80	3265.046	I
50	3265.617	I
13	3266.88	III
50	3271.000	I
11	3276.08	III
150	3286.75	I
10	3288.81	III
120	3305.97	I
200	3306.343	I
400	3355.227	I
80	3355.517	I
60	3369.546	I
120	3370.783	I
50	3378.678	I
50	3380.110	I
60	3383.978	I
50	3392.304	I
150	3392.651	I
150	3399.333	I
80	3404.353	I
500	3407.458	I
250	3413.131	I
60	3424.284	I
500	3427.119	I
60	3428.748	I
6000	3440.606	I
2500	3440.989	I
1000	3443.876	I
200	3445.149	I
1200	3465.860	I
2000	3475.450	I
500	3476.702	I
2500	3490.574	I
500	3497.840	I
10	3501.76	III
250	3513.817	I
300	3521.261	I
400	3526.040	I
100	3526.166	I
60	3526.237	I
60	3526.381	I
60	3526.467	I
100	3533.199	I
200	3536.556	I
300	3541.083	I
250	3542.075	I
80	3553.739	I
400	3554.925	I
200	3556.878	I
400	3558.515	I
1000	3565.379	I
1200	3570.097	I
800	3570.25	I
120	3571.996	I
100	3573.393	I
60	3573.829	I
60	3573.888	I
4000	3581.19	I
150	3582.199	I
150	3584.660	I

Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å	
120	3584.929	I	6000	3737.131	I	1200	3927.920	I	40	4195.329	I
300	3585.319	I	100	3738.306	I	2000	3930.296	I	150	4198.304	I
150	3585.705	I	400	3743.362	I	60	3948.774	I	40	4199.095	I
10	3586.04	III	6000	3745.561	I	60	3949.953	I	300	4202.029	I
200	3586.103	I	1200	3745.899	I	50	3951.164	I	40	4203.984	I
400	3586.984	I	3000	3748.262	I	50	3952.601	I	80	4206.696	I
100	3594.633	I	80	3748.964	I	16	3954.33	III	80	4210.343	I
11	3600.94	III	3000	3749.485	I	60	3956.454	I	400	4216.183	I
150	3603.204	I	1500	3758.232	I	250	3956.68	I	100	4219.360	I
11	3603.88	III	400	3760.05	I	60	3966.614	I	50	4222.212	I
200	3605.454	I	1500	3763.788	I	11	3968.72	III	11	4222.27	III
500	3606.680	I	400	3765.54	I	100	3969.257	I	50	4225.956	I
1500	3608.859	I	600	3767.191	I	80	3977.741	I	200	4227.423	I
250	3610.16	I	60	3776.452	I	10 w	3979.42	III	100	4233.602	I
60	3612.068	I	250	3785.95	I	40	3981.771	I	13	4235.56	III
150	3617.788	I	100	3786.68	I	50	3983.956	I	250	4235.936	I
1500	3618.768	I	250	3787.880	I	60	3994.114	I	50	4238.809	I
200	3621.462	I	250	3790.092	I	200	3997.392	I	12	4243.75	III
150	3622.004	I	150	3794.34	I	40	3998.053	I	50	4247.425	I
150	3623.19	I	400	3795.002	I	400	4005.241	I	200	4250.118	I
100	3631.096	I	120	3797.518	I	60	4009.713	I	300	4250.787	I
1200	3631.463	I	250	3798.511	I	100	4021.867	I	40	4258.315	I
60	3632.041	I	400	3799.547	I	10	4035.42	III	800	4260.473	I
100	3638.298	I	200	3805.345	I	50	4040.638	I	250	4271.153	I
200	3640.389	I	80	3806.696	I	4000	4045.813	I	1200	4271.759	I
80	3643.717	I	600	3812.964	I	11	4053.11	III	12 h	4273.40	III
1500	3647.842	I	60	3813.059	I	1500	4063.594	I	12	4279.72	III
250	3649.506	I	1500	3815.840	I	50	4066.975	I	1200	4282.402	I
80	3650.279	I	2500	3820.425	I	50	4067.977	I	14 h	4286.16	III
200	3651.467	I	150	3821.179	I	1200	4071.737	I	80	4291.462	I
120	3670.024	I	80	3824.306	I	40	4076.629	I	16 h	4296.85	III
150	3670.089	I	2500	3824.444	I	12	4081.00	III	250	4299.234	I
100	3676.311	I	1500	3825.880	I	40	4100.737	I	18 h	4304.78	III
150	3677.629	I	1200	3827.823	I	40	4107.489	I	1200	4307.901	I
1500	3679.913	I	1000	3834.222	I	150	4118.544	I	20 h	4310.36	III
200	3682.242	I	120	3839.257	I	10	4120.90	III	150	4315.084	I
120	3683.054	I	500	3840.437	I	11	4122.02	III	1500	4325.761	I
150	3684.107	I	800	3841.047	I	11	4122.78	III	80	4352.734	I
120	3685.998	I	120	3843.256	I	40	4127.608	I	80	4369.771	I
500	3687.456	I	80	3846.800	I	400	4132.058	I	11 h	4372.31	III
120	3689.477	I	200	3849.96	I	80	4134.676	I	14 h	4372.53	III
150	3694.008	I	120	3850.817	I	40	4136.997	I	18 h	4372.81	III
120	3695.051	I	2500	3856.372	I	15	4137.76	III	800	4375.929	I
150	3701.086	I	150	3859.212	I	13	4139.35	III	3000	4383.544	I
80	3704.462	I	10000	3859.911	I	200	4143.415	I	1200	4404.750	I
1200	3705.566	I	150	3865.523	I	800	4143.869	I	300	4415.122	I
60	3707.041	I	60	3867.215	I	40	4153.898	I	12	4419.60	III
150	3707.821	I	250	3872.501	I	50	4154.500	I	600	4427.299	I
300	3707.919	I	150	3873.761	I	60	4156.799	I	400	4461.652	I
600	3709.246	I	250	3878.018	I	18	4164.73	III	120	4466.551	I
120	3716.442	I	2000	3878.573	I	13	4166.84	III	80	4476.017	I
8000	3719.935	I	4000	3886.282	I	50	4172.744	I	80	4482.169	I
1500	3722.563	I	200	3887.048	I	13	4174.26	III	200	4482.252	I
120	3724.377	I	300	3888.513	I	60	4174.912	I	50	4489.739	I
60	3725.491	I	800	3895.656	I	50	4175.635	I	50	4528.613	I
60	3727.093	I	1200	3899.707	I	50	4177.593	I	30	4647.433	I
500	3727.619	I	400	3902.945	I	120	4181.754	I	30	4736.771	I
150	3732.396	I	250	3906.479	I	50	4184.891	I	50	4859.741	I
1200	3733.317	I	80	3916.731	I	120	4187.038	I	120	4871.317	I
5000	3734.864	I	600	3920.258	I	120	4187.795	I	60	4872.136	I
120	3735.324	I	1200	3922.911	I	80	4191.430	I	30	4878.208	I

Intensity	Wavelength/Å	
100	4890.754	I
250	4891.492	I
30	4903.309	I
150	4918.992	I
500	4920.502	I
1500	4957.597	I
80	5001.862	I
30	5005.711	I
100	5006.117	I
60	5012.067	I
30	5014.941	I
150	5041.755	I
30	5049.819	I
30	5051.634	I
25	5074.748	I
150	5110.357	I
40	5139.251	I
100	5139.462	I
25	5151.910	I
12	5156.12	III
80	5166.281	I
2500	5167.487	I
80	5168.897	I
500	5171.595	I
50	5191.454	I
80	5192.343	I
200	5194.941	I
10	5199.08	III
30	5204.582	I
25	5215.179	I
150	5216.274	I
60	5226.862	I
1000	5227.150	I
250	5232.939	I
10	5235.66	III
18	5243.31	III
13 l	5260.34	III
100	5266.555	I
1200	5269.537	I
800	5270.357	I
14	5272.98	III
15	5276.48	III
30	5281.789	I
16	5282.30	III
60	5283.621	I
12	5284.83	III
11	5298.12	III
12	5299.93	III
25	5302.299	I
14 w	5302.60	III
10	5306.76	III
10	5322.74	III
150	5324.178	I
800	5328.038	I
300	5328.531	I
100	5332.899	I
80	5339.928	I
500	5341.023	I
11	5346.88	III
12	5353.77	III
12	5363.76	III
10	5368.06	III
400	5371.489	I
11 l	5375.47	III
40	5393.167	I
300	5397.127	I
250	5405.774	I
250	5429.695	I
100	5434.523	I
200	5446.871	I
120	5455.609	I
25	5497.516	I
20	5501.464	I
30	5506.778	I
30	5569.618	I
60	5572.841	I
120	5586.755	I
200	5615.644	I
20	5624.541	I
50	5662.515	I
11	5719.88	III
10	5756.38	III
20	5762.990	I
18	5833.93	III
10	5854.62	III
30	5862.353	I
15	5891.91	III
30	5914.114	I
10 p	5920.13	III
18 p	5929.69	III
10	5952.31	III
14	5953.62	III
12	5979.32	III
30	5986.956	I
12 h	5989.08	III
18	5999.54	III
16	6032.59	III
13	6036.56	III
11	6048.72	III
11	6054.18	III
40	6065.482	I
30	6102.159	I
40	6136.614	I
40	6137.694	I
40	6191.558	I
30	6213.429	I
30	6219.279	I
40	6230.726	I
20	6246.317	I
80	6247.56	II
30	6252.554	I
20	6393.602	I
30	6399.999	I
20	6411.647	I
20	6421.349	I
30	6430.844	I
200	6456.38	II
60	6494.981	I
20	6546.239	I
20	6592.913	I
40	6677.989	I
25	7164.443	I
80	7187.313	I
30	7207.381	I
30	7445.746	I
40	7495.059	I
60	7511.045	I
80	7937.131	I
60	7945.984	I
80	7998.939	I
60	8046.047	I
50	8085.176	I
150	8220.41	I
120	8327.053	I
20	8331.908	I
120	8387.770	I
30	8468.404	I
15	8514.069	I
60	8661.898	I
150	8688.621	I
52	11422.32	I
87	11439.12	I
91	11593.59	I
255	11607.57	I
160	11638.26	I
230	11689.98	I
160	11783.26	I
580	11882.84	I
225	11884.08	I
1030	11973.05	I
96	14400.56	I
72	14512.23	I
50	14555.06	I
40	14826.43	I
94	15294.58	I
41	15769.42	I
105	18856.65	I

Krypton Kr Z = 36

30	467.35	III
150	472.16	V
100	484.39	V
250	496.25	V
120	500.77	V
200	507.20	V
30	540.86	III
60	548.04	V
30	565.64	III
30	569.16	III
30	571.98	III
30	579.83	III
30	585.14	III
30	585.96	III
30	593.70	III
30	594.10	III
30	596.41	III
40	600.17	III
30	603.67	III
50	605.86	III
35	606.47	III
50	611.12	III
35	616.72	III
40	621.45	III
45	622.80	III
50	625.02	III
30	625.76	III
45	628.59	III
50	630.04	III
35	633.09	III
120	637.87	V
50	639.98	III
60	646.41	III
50	651.20	III
50	659.72	III
30	664.86	III
40	672.34	III
35	672.85	III
35	676.57	III
35	680.13	III
35	683.68	III
45	686.25	III
45	687.98	III
	690.86	V
	691.75	V
45	691.93	III
50	695.61	III
30	698.05	III
50	708.36	III
600	708.85	V
50	714.00	III
100 p	722.04	III
60	729.40	II
30	746.70	III
200	761.18	II
100	763.98	II
60	766.20	II
200	771.03	II
60 p	773.69	II
200	782.10	II
100	783.72	II
60	785.97	III
	793.44	IV
	794.11	IV
7	805.76	IV
	810.70	V
18	816.82	IV
60	818.15	II
60	830.38	II
50	837.66	III
22	842.04	IV
100	844.06	II
50	854.73	III
60	862.58	III
60	864.82	II
60	868.87	II
40	870.84	III
50	876.08	III
200	884.14	II
1000	886.30	II
400	891.01	II
75	897.81	III
200	911.39	II
2000	917.43	II
50	945.44	I
50	946.54	I

Intensity	Wavelength/Å	
20	951.06	I
50	953.40	I
50	963.37	I
2000	964.97	II
50	987.29	III
100	1001.06	I
100	1003.55	I
100	1030.02	I
30	1158.74	III
200	1164.87	I
650	1235.84	I
6	1638.82	III
6	1914.09	III
3	2237.34	IV
6	2291.26	IV
3	2329.3	IV
4	2336.75	IV
4	2348.27	IV
3	2358.5	IV
3	2388.05	IV
40	2393.94	III
4	2416.9	IV
3	2428.04	IV
5	2442.68	IV
4	2451.7	IV
6	2459.74	IV
100 h	2464.77	II
5	2474.06	IV
60	2492.48	II
40	2494.01	III
4	2517.0	IV
5	2518.02	IV
6	2519.38	IV
5	2524.5	IV
5	2546.0	IV
6	2547.0	IV
4	2558.08	IV
30	2563.25	III
3	2586.9	IV
5	2606.17	IV
10	2609.5	IV
8	2615.3	IV
7	2621.11	IV
60	2639.76	III
30	2680.32	III
40	2681.19	III
80 h	2712.40	II
3	2730.55	IV
8	2748.18	IV
6	2774.70	IV
3	2829.60	IV
100	2833.00	II
3	2836.08	IV
30	2841.00	III
30	2851.16	III
5	2853.0	IV
3	2859.3	IV
50	2870.61	III
100	2892.18	III
30	2909.17	III
50	2952.56	III
60	2992.22	III
50	3022.30	III
80	3024.45	III
50	3046.93	III
30	3056.72	III
60	3063.13	III
40	3097.16	III
60	3112.25	III
30	3120.61	III
100	3124.39	III
60	3141.35	III
3	3142.01	IV
100	3189.11	III
80	3191.21	III
6	3224.99	IV
40	3239.52	III
40	3240.44	III
300	3245.69	III
3	3261.70	IV
150	3264.81	III
100	3268.48	III
30	3271.65	III
30	3285.89	III
30	3304.75	III
50	3311.47	III
200	3325.75	III
60	3330.76	III
50	3342.48	III
100	3351.93	III
40	3374.96	III
100	3439.46	III
70	3474.65	III
100	3488.59	III
200	3507.42	III
100	3564.23	III
100 h	3607.88	II
200	3631.889	II
30	3641.34	III
250	3653.928	II
80	3665.324	I
150	3669.01	II
100	3679.559	I
80	3686.182	II
30	3690.65	III
300 h	3718.02	II
200	3718.595	II
150	3721.350	II
200	3741.638	II
150	3744.80	II
80	3754.245	II
500	3778.089	II
500	3783.095	II
3	3809.30	IV
5	3860.58	IV
40 h	3868.70	III
150 h	3875.44	II
150	3906.177	II
200	3920.081	II
5	3934.29	IV
100	3994.840	II
100 h	3997.793	II
300	4057.037	II
300	4065.128	II
50	4067.37	III
500	4088.337	II
250	4098.729	II
100	4109.248	II
40	4131.33	III
250	4145.122	II
40	4154.46	III
150	4250.580	II
1000	4273.969	I
100	4282.967	I
600	4292.923	II
200	4300.49	II
500 h	4317.81	II
400	4318.551	I
1000	4319.579	I
150 h	4322.98	II
100	4351.359	I
3000	4355.477	II
500	4362.641	I
200	4369.69	II
800	4376.121	I
300 h	4386.54	II
200	4399.965	I
100	4425.189	I
500	4431.685	II
600	4436.812	II
600	4453.917	I
800	4463.689	I
800	4475.014	II
400 h	4489.88	II
600	4502.353	I
400 h	4523.14	II
200 h	4556.61	II
800	4577.209	II
300	4582.978	II
150 h	4592.80	II
500	4615.292	II
1000	4619.166	II
800	4633.885	II
2000	4658.876	II
500	4680.406	II
100	4691.301	II
200	4694.360	II
3000	4739.002	II
300	4762.435	II
1000	4765.744	II
300	4811.76	II
300	4825.18	II
800	4832.077	II
700	4846.612	II
150	4857.20	II
300	4945.59	II
20 h	5016.45	III
200	5022.40	II
250	5086.52	II
400 h	5125.73	II
500	5208.32	II
200	5308.66	II
500	5333.41	II
200	5468.17	II
10	5501.43	III
500	5562.224	I
2000	5570.288	I
80	5580.386	I
100	5649.561	I
400	5681.89	II
200 h	5690.35	II
100	5832.855	I
3000	5870.914	I
200	5992.22	II
60	5993.849	I
10 h	6037.17	III
60	6056.125	I
10 h	6078.38	III
10	6310.22	III
300	6420.18	II
100	6421.026	I
200	6456.288	I
150	6570.07	II
60	6699.228	I
100	6904.678	I
250	7213.13	II
100	7224.104	I
80	7287.258	I
400	7289.78	II
400	7407.02	II
60	7425.541	I
200	7435.78	II
100	7486.862	I
300	7524.46	II
1000	7587.411	I
2000	7601.544	I
150	7641.16	II
1000	7685.244	I
1200	7694.538	I
250	7735.69	II
150	7746.827	I
800	7854.821	I
200	7913.423	I
180	7928.597	I
200	7933.22	II
120	7973.62	II
100	7982.401	I
1500	8059.503	I
4000	8104.364	I
6000	8112.899	I
60	8132.967	I
3000	8190.054	I
200	8202.72	II
80	8218.365	I
3000	8263.240	I
100	8272.353	I
1500	8281.050	I
5000	8298.107	I
100	8412.430	I
3000	8508.870	I
150	8764.110	I
6000	8776.748	I
2000	8928.692	I
500	9238.48	II

Intensity	Wavelength/Å	
500 hl	9293.82	II
200 h	9320.99	II
300	9361.95	II
100	9362.082	I
200 h	9402.82	II
200 h	9470.93	II
500	9577.52	II
500 h	9605.80	II
400 h	9619.61	II
200	9663.34	II
200 h	9711.60	II
2000	9751.758	I
500	9803.14	II
500	9856.314	I
1000	10221.46	II
100	11187.108	I
200	11257.711	I
150	11259.126	I
500	11457.481	I
150	11792.425	I
1500	11819.377	I
600	11997.105	I
160	12077.224	I
100	12861.892	I
1100	13177.412	I
1000	13622.415	I
2400	13634.220	I
800	13658.394	I
200	13711.036	I
600	13738.851	I
150	13974.027	I
550	14045.657	I
140	14104.298	I
180	14402.22	I
2000	14426.793	I
100	14517.84	I
1600	14734.436	I
550	14762.672	I
450	14765.472	I
400	14961.894	I
120	15005.307	I
140	15209.526	I
1700	15239.615	I
130	15326.480	I
1500	15334.958	I
700	15372.037	I
200	15474.026	I
180	15681.02	I
120	15820.09	I
200	16726.513	I
2000	16785.128	I
1000	16853.488	I
2400	16890.441	I
1600	16896.753	I
1800	16935.806	I
600	17098.771	I
700	17367.606	I
120	17404.443	I
150	17616.854	I
650	17842.737	I
700	18002.229	I
2600	18167.315	I
100	18399.786	I
150	18580.896	I
300	18696.294	I
170	18785.460	I
200	18797.703	I
140	20209.878	I
300	20423.964	I
140	20446.971	I
600	21165.471	I
1800	21902.513	I
120	22485.775	I
180	23340.416	I
120	24260.506	I
180	24292.221	I
600	25233.820	I
180	28610.55	I
1000	28655.72	I
150	28769.71	I
140	28822.49	I
300	29236.69	I
300	30663.54	I
300	30979.16	I
500	39300.6	I
1100	39486.52	I
220	39557.25	I
100	39572.60	I
1400	39588.4	I
1100	39589.6	I
500	39954.8	I
300	39966.6	I
1300	40306.1	I
250	40685.16	I

Lanthanum La Z = 57

100	344.12	IV
400	390.72	V
1000	432.11	V
2500	435.28	V
10000	463.14	IV
5000	482.16	V
7000	498.08	V
15000	499.54	IV
10000	503.58	V
12000	526.76	V
10000	531.07	V
15000	533.23	V
8000	547.44	V
40000	552.02	IV
5000	600.24	V
30000	631.26	IV
400	796.99	III
2000	870.40	III
1000	882.34	III
400	942.86	III
50000	1081.61	III
95000	1099.73	III
2000	1255.63	III
10000	1349.18	III
25000	1368.04	IV
20000	1463.47	IV
15000	1507.87	IV
10000	1523.79	III
4000	1808.66	IV
5000	1902.97	IV
4000 c	2197.45	IV
770	2256.76	II
25000 w	2417.58	IV
50000	2532.75	IV
45000	2582.05	IV
95000 w	2597.50	IV
70000 w	2662.75	IV
420	2808.39	II
50000 w	2848.30	IV
30000 c	2962.58	IV
70000 w	3009.51	IV
90000 c	3056.68	IV
1000	3171.63	III
1500	3171.74	III
510	3245.13	II
550	3265.67	II
800	3303.11	II
1500	3337.49	II
870	3344.56	II
1500	3380.91	II
320	3628.83	II
1000	3645.42	II
550	3713.54	II
2400	3759.08	II
3700	3790.83	II
3900	3794.78	II
600	3840.72	II
1600	3849.02	II
3400	3871.64	II
1700	3886.37	II
1300	3916.05	II
1100	3921.54	II
2200	3929.22	II
9000	3949.10	II
4400	3988.52	II
3600	3995.75	II
2800	4031.69	II
3000	4042.91	II
850	4067.39	II
2800	4077.35	II
5500	4086.72	II
4400	4123.23	II
550	4141.74	II
1100	4151.97	II
1500	4196.55	II
1600	4238.38	II
480	4269.50	II
600	4286.97	II
600	4296.05	II
440	4322.51	II
4600	4333.74	II
550	4354.40	II
2000	4429.90	II
850	4522.37	II
420	4526.12	II
400	4558.46	II
400	4574.88	II
410	4613.39	II
410	4619.88	II
540	4655.50	II
360	4662.51	II
230	4692.50	II
230	4728.42	II
500	4740.28	II
390	4743.09	II
320	4748.73	II
320	4860.91	II
850	4899.92	II
1000	4920.98	II
1000	4921.79	II
370	4949.77	I
340	4970.39	II
370	4986.83	II
720	4999.47	II
210	5050.57	I
470	5114.56	II
470	5122.99	II
450	5145.42	I
290	5158.69	I
580	5177.31	I
850	5183.42	II
260	5188.22	II
720	5211.86	I
520	5234.27	I
340	5253.46	I
370	5271.19	I
370	5301.98	II
180	5303.55	II
500	5455.15	I
470	5501.34	I
240	5648.25	I
180	5740.66	I
370	5769.34	I
320	5789.24	I
450	5791.34	I
140	5821.99	I
320	5930.62	I
720	6249.93	I
260 d	6262.30	II
450	6394.23	I
250	6455.99	I
180	6709.50	I
110	7045.96	I
160	7066.23	II
50	7161.25	I
110 w	7282.34	II
110 w	7334.18	I
75 cw	7483.50	II
50	7498.83	I
85	7539.23	I
40	7964.83	I
75	8086.05	I
85	8324.69	I
95	8346.53	I
65	8545.44	I
300	8583.45	III
40	8674.43	I
35	8825.82	I
120	9184.38	III

Intensity	Wavelength/Å	
100	9212.63	III
140	10284.79	III
Lead Pb Z = 82		
10	496.38	IV
12	499.94	IV
14	529.78	IV
20	570.16	IV
10	648.50	IV
20	703.73	V
12	749.46	V
10	752.52	V
10	761.09	IV
18	767.45	V
18	769.49	V
14	771.42	V
14	782.79	V
15	797.02	V
18	802.07	IV
12	802.82	IV
18	809.63	V
10	812.59	IV
10	827.41	IV
12	832.60	IV
12	845.94	IV
18	857.64	IV
16	862.33	IV
20	863.97	V
14	870.44	IV
6	873.71	II
12	879.96	IV
18	883.90	V
14	884.96	IV
14	884.99	IV
14	888.37	V
8	889.68	II
16	890.72	IV
14	894.40	V
12	896.08	V
12	908.51	IV
14	915.71	V
12	917.90	IV
12	918.09	V
12	920.28	V
12	920.66	V
10	922.12	IV
12	922.49	IV
10	927.64	IV
14	932.20	IV
12	954.35	V
10	967.23	II
10	986.71	II
10	995.89	II
10	1016.61	II
14	1028.61	IV
20	1032.05	IV
16	1041.24	IV
18	1044.14	IV
12	1048.9	III
10	1049.82	II
10	1050.77	II
10	1051.26	V

Intensity	Wavelength/Å	
15	1056.53	IV
10	1060.66	II
12	1072.09	IV
18	1080.81	IV
20	1084.17	IV
10	1088.86	V
10	1103.94	II
10	1108.43	II
10	1109.84	II
20	1116.08	IV
10	1119.57	II
10	1121.36	II
10	1133.14	II
18	1137.84	IV
14	1144.93	IV
12	1157.88	V
14	1185.43	V
20	1189.95	IV
10	1203.63	II
10	1231.20	II
11	1233.50	V
10	1291.10	IV
20	1313.05	IV
10	1331.65	II
10	1335.20	II
12	1343.06	IV
10	1348.37	II
16	1388.94	IV
18	1400.26	IV
10	1404.34	IV
10	1433.96	II
10	1512.42	II
14	1535.71	IV
20	1553.1	III
10	1671.53	II
10	1682.15	II
20	1726.75	II
10	1796.670	II
10	1822.050	II
10	1904.77	I
7	1921.471	II
12	1959.34	IV
16	1973.16	IV
10	1998.83	V
5 r	2022.02	I
10	2042.58	IV
12	2049.34	IV
8 r	2053.28	I
12	2079.22	IV
6	2111.758	I
10	2115.066	I
15	2154.01	IV
500 r	2170.00	I
7	2175.580	I
12	2177.46	IV
7	2187.888	I
8	2189.603	I
10	2203.534	II
20	2237.425	I
20	2246.86	I
25	2246.89	I

Intensity	Wavelength/Å	
20	2259.01	V
150	2332.418	I
16	2359.53	IV
180	2388.797	I
550 r	2393.792	I
140	2399.597	I
320 r	2401.940	I
320 r	2411.734	I
16	2417.61	IV
15	2424.81	V
150 r	2443.829	I
160 r	2446.181	I
130 r	2476.378	I
80 r	2577.260	I
500 r	2613.655	I
900 r	2614.175	I
160	2628.262	I
4	2634.256	II
10	2657.094	I
700	2663.154	I
10	2697.541	I
25000 r	2801.995	I
100	2822.58	I
14000 r	2823.189	I
35000 r	2833.053	I
6	2840.557	II
14000 r	2873.311	I
3	2914.442	II
15	2966.460	I
15	2972.991	I
15	2980.157	I
4	2986.876	II
10	3043.85	III
150	3118.894	I
10	3137.81	III
10	3176.50	III
600	3220.528	I
100	3229.613	I
400	3240.186	I
200	3262.355	I
35000	3572.729	I
50000 r	3639.568	I
20000	3671.491	I
70000 r	3683.462	I
10	3713.982	II
25000	3739.935	I
12	3854.08	III
15000	4019.632	I
95000	4057.807	I
14000	4062.136	I
10	4157.814	I
10000	4168.033	I
8	4272.66	III
200	4340.413	I
10	4496.15	IV
6	4499.34	III
16	4534.60	IV
7	4571.21	III
10	4579.051	II
6	4761.12	III
1000	5005.416	I

Intensity	Wavelength/Å	
100	5006.572	I
50	5089.484	I
10	5107.242	I
2000	5201.437	I
10	5372.099	II
40	5692.346	I
200	5895.624	I
2000	6001.862	I
500	6011.667	I
500	6059.356	I
40	6081.409	II
50	6110.520	I
100	6235.266	I
50 c	6660.20	II
20000	7228.965	I
10	7346.676	I
20	7809.259	I
5	7896.737	I
10	8168.001	I
6	8191.886	I
5	8217.711	I
40	8272.690	I
20	8409.384	I
10	8478.492	I
5	8722.810	I
10	8857.457	I
8	9293.476	I
15	9438.05	I
15	9604.297	I
15	9674.351	I
200	10290.458	I
100	10498.965	I
50	10649.249	I
15	10886.688	I
40	10969.53	I
	13512.6	I
	14743.0	I
	15349.6	I
	39039.4	I
Lithium Li Z = 3		
	102.9	III
	103.4	III
	104.1	III
	105.5	III
	108.0	III
	113.9	III
	125.5	II
	135.0	III
	136.5	II
	140.5	II
	167.21	II
	168.74	II
	171.58	II
	178.02	II
	199.28	II
	207.5	II
	456.	II
	483.	II
	540.	II
	540.0	III
	729.	II

Intensity	Wavelength/Å	
	729.1	III
	800.	II
	820.	II
	861.	II
	905.5	II
	917.5	II
	936.	II
	945.	II
	965.	II
	972.	II
	988.	II
	1018.	II
	1032.	II
	1036.	II
	1093.	II
	1103.	II
	1109.	II
	1116.	II
	1132.1	II
	1141.	II
	1166.4	II
	1198.09	II
	1215.	II
	1238.	II
	1253.8	II
	1420.89	II
	1424.	II
3	1492.93	II
5	1492.97	II
1	1493.04	II
	1555.	II
3	1653.08	II
5	1653.13	II
1	1653.21	II
	1681.66	II
	1755.33	II
	2009.	II
	2039.	I
	2068.	II
	2131.	II
	2164.	II
	2173.4	I
	2183.	II
	2214.	II
	2222.	II
	2237.	II
h	2249.21	II
	2286.82	II
	2302.57	II
	2303.33	II
	2304.59	I
	2304.92	I
	2305.36	I
	2305.83	I
	2306.29	I
	2306.82	I
	2307.44	I
	2308.97	I
	2309.88	I
	2310.94	I
	2312.11	I
	2313.49	I
	2315.08	I
	2316.95	I
	2319.18	I
	2321.88	I
	2325.11	I
	2329.02	I
	2329.84	II
	2333.94	I
3	2336.88	II
5	2336.91	II
2	2337.00	II
	2340.15	I
	2348.22	I
	2358.93	I
	2373.54	I
	2381.54	II
	2383.20	II
1	2394.39	I
	2402.33	II
	2410.84	II
3	2425.43	I
	2429.81	II
	2460.2	I
10	2475.06	I
	2506.94	II
	2508.78	II
	2518.	I
	2539.49	II
24	2551.7	II
	2559.	II
15	2562.31	I
	2605.08	II
2	2657.29	II
3	2657.30	II
	2674.46	II
	2728.24	II
5	2728.29	II
2	2728.32	II
3	2730.47	II
1	2730.55	II
5	2741.20	I
	2766.99	II
	2790.31	II
	2801.	I
	2846.	I
	2868.	I
	2895.	I
2	2934.02	II
2	2934.07	II
5	2934.12	II
1	2934.25	II
	2968.	I
3	3029.12	II
3	3029.14	II
	3144.	I
3	3155.31	II
4	3155.33	II
1	3196.26	II
9	3196.33	II
4	3196.36	II
5	3199.33	II
2	3199.43	II
17	3232.66	I
	3249.87	II
	3306.28	II
	3488.	I
	3579.8	I
	3618.	I
	3662.	I
	3684.32	II
1	3714.00	II
5	3714.16	II
6 d	3714.27	II
8	3714.29	II
7 d	3714.40	II
10	3714.41	II
1	3714.51	II
	3714.58	II
3	3718.7	I
6	3794.72	I
20	3915.30	I
20	3915.35	I
10	3985.48	I
10	3985.54	I
40	4132.56	I
40	4132.62	I
	4196.	I
20	4273.07	I
20	4273.13	I
5	4325.42	II
5	4325.47	II
1	4325.54	II
	4516.45	II
13	4602.83	I
13	4602.89	I
	4607.34	II
	4671.51	II
6	4671.65	II
2	4671.70	II
3	4678.06	II
1	4678.29	II
	4760.	I
	4763.	II
	4788.36	II
	4843.0	II
4	4881.32	II
4	4881.39	II
1	4881.49	II
8	4971.66	I
8	4971.75	I
	5037.92	II
	5271.	I
	5315.	I
	5395.	I
	5440.	I
600 c	5483.55	II
600 c	5485.65	II
320	6103.54	I
320	6103.65	I
3600	6707.76	I
3600	6707.91	I
48	8126.23	I
48	8126.45	I
	8517.37	II
	9581.42	II
	10120.	II
	12232.	I
	12782.	I
	13566.	I
	17552.	I
	18697.	I
	19290.	I
	24467.	I
	40475.	I

Lutetium Lu Z = 71

100	563.72	V
500	810.73	III
2000	832.28	III
100	861.92	V
400	876.80	IV
100	880.32	V
100	891.81	V
100	914.72	V
400	1001.18	III
100	1272.42	IV
800	1333.79	IV
400	1429.38	IV
200	1441.76	V
200	1453.35	V
200	1468.99	V
400	1472.12	V
200	1473.71	V
200	1485.58	V
400	1511.26	IV
600	1772.57	IV
100 c	1786.25	V
1000	1854.57	III
1500	2065.35	III
1500 c	2070.56	III
600 c	2086.47	IV
1000 c	2104.41	IV
1000 c	2108.31	IV
1700 h	2195.54	II
1000	2236.14	III
2000	2236.22	III
95	2276.94	II
190	2297.41	II
1300	2392.19	II
120	2399.14	II
80	2419.21	II
130	2459.64	II
370	2536.95	II
930	2571.23	II
1700	2578.79	II
4500 c	2603.35	III
1800	2613.40	II
18000	2615.42	II
1800	2619.26	II
2700	2657.80	II
570 h	2685.08	I
4200	2701.71	II
180 d	2719.09	I

Intensity	Wavelength/Å	
480 h	2728.95	I
3600	2754.17	II
750 h	2765.74	I
2000	2772.55	III
2700	2796.63	II
270 c	2834.35	II
330 h	2845.13	I
3000	2847.51	II
570 h	2885.14	I
6300	2894.84	II
4500	2900.30	II
300	2903.05	I
9000	2911.39	II
270 h	2949.73	I
1200	2951.69	II
4200	2963.32	II
2400	2969.82	II
1800	2989.27	I
3000	3020.54	II
2100	3056.72	II
1000	3057.86	III
7500	3077.60	II
390	3080.11	I
5100 h	3081.47	I
3000	3118.43	I
2400	3171.36	I
260	3191.80	II
1400	3198.12	II
4800	3254.31	II
3800	3278.97	I
7600	3281.74	I
6200	3312.11	I
7600	3359.56	I
6200	3376.50	I
950	3385.50	I
160 h	3391.55	I
1400	3396.82	I
4100	3397.07	II
4800	3472.48	II
8300 c	3507.39	II
1600	3508.42	I
4800	3554.43	II
4800	3567.84	I
340	3596.34	I
800	3623.99	II
680	3636.25	I
2600	3647.77	I
110	3756.70	I
110	3756.79	I
150	3800.67	I
2700	3841.18	I
530	3876.65	II
50	3918.86	I
480	3968.46	I
670	4054.45	I
310	4122.49	I
3100	4124.73	I
150 c	4131.79	I
460	4154.08	I
1600	4184.25	II
150	4277.50	I
250	4281.03	I
330 d	4295.97	I
150	4309.57	I
190 c	4430.48	I
190	4450.81	I
3300	4518.57	I
100 h	4648.21	I
1000	4658.02	I
85 h	4659.03	I
150	4785.42	II
85	4815.05	I
460	4904.88	I
180	4942.34	I
800	4994.13	II
800	5001.14	I
140	5134.05	I
2700	5135.09	I
170	5196.61	I
500	5402.57	I
140 c	5421.90	I
100	5437.88	I
2100	5476.69	II
550	5736.55	I
80	5800.59	I
690 cw	5983.9	II
140	5997.13	I
1400	6004.52	I
440	6055.03	I
150	6159.94	II
600	6198.13	III
160	6199.66	II
2100	6221.87	II
80	6235.36	II
160	6242.34	II
70 h	6345.35	I
1100	6463.12	II
29	6477.67	I
55 c	6523.18	I
35 cw	6611.28	II
23 c	6677.14	I
30 c	6793.77	I
45	6917.31	I
23	7031.24	I
45	7125.84	II
14 ch	7237.98	I
11 c	7441.52	I
9 c	8178.16	I
17	8382.08	I
35	8459.19	II
10 d	8478.50	I
29 c	8508.08	I
35 c	8610.98	I

Magnesium Mg Z = 12

400	146.95	IV
20	186.51	III
20	187.20	III
10	188.53	III
100	231.73	III
80	234.26	III
35	276.58	V
4000	320.99	IV
3000	323.31	IV
30	353.09	V
150	857.29	IV
50	919.03	IV
250	1037.41	IV
300	1210.99	IV
300	1342.19	IV
800	1346.57	IV
300	1346.68	IV
600	1352.05	IV
900	1384.46	IV
500	1385.77	IV
800	1387.53	IV
300	1404.68	IV
1000	1409.36	IV
500	1437.53	IV
1000	1437.64	IV
300	1447.42	IV
300	1459.54	IV
400	1459.62	IV
400	1481.51	IV
350	1490.45	IV
300	1495.50	IV
300	1607.11	IV
5	1668.43	I
500	1683.02	IV
10	1683.41	I
400	1698.81	IV
15	1707.06	I
40	1734.84	II
50	1737.62	II
20	1747.80	I
40	1750.65	II
50	1753.46	II
30	1827.93	I
300	1844.17	IV
9	2025.82	I
25	2064.90	III
20	2091.96	III
20	2177.70	III
3	2329.58	II
20	2395.15	III
6	2449.57	II
1	2557.23	I
1	2560.94	I
1	2562.26	I
1	2564.94	I
1	2570.91	I
1	2572.25	I
2	2574.94	I
1	2577.89	I
1	2580.59	I
1	2584.22	I
2	2585.56	I
3	2588.28	I
1	2591.89	I
1	2593.23	I
2	2595.97	I
2	2602.50	I
4	2603.85	I
5	2606.62	I
1	2613.36	I
2	2614.73	I
3	2617.51	I
3	2628.66	I
6	2630.05	I
8	2632.87	I
2	2644.80	I
3	2646.21	I
4	2649.06	I
8	2660.76	II
8	2660.82	II
6	2668.12	I
8	2669.55	I
10	2672.46	I
3	2693.72	I
5	2695.18	I
6	2698.14	I
8	2731.99	I
10	2733.49	I
12	2736.53	I
5	2765.22	I
7	2768.34	I
38	2776.69	I
32	2778.27	I
90	2779.83	I
8	2781.29	I
32	2781.42	I
36	2782.97	I
1000	2795.53	II
600	2802.70	II
3	2809.76	I
2	2811.11	I
1	2811.78	I
12	2846.72	I
12	2846.75	I
14	2848.34	I
14	2848.42	I
16	2851.65	I
16	2851.66	I
6000	2852.13	I
2	2902.92	I
4	2906.36	I
3	2915.45	I
10	2936.74	I
12	2938.47	I
2	2942.00	I
13	2942.00	I
20	3091.08	I
22	3092.99	I
14	3096.90	I
9	3104.71	II
8	3104.81	II
6	3168.98	II
6	3172.71	II
7	3175.78	II
2	3197.62	I
17	3329.93	I
6	3332.15	I
9	3336.68	I
7	3535.04	II
8	3538.86	II

Intensity	Wavelength/Å	
7	3549.52	II
8	3553.37	II
140	3829.30	I
300	3832.30	I
500	3838.29	I
8	3848.24	II
7	3850.40	II
3	3878.31	I
3	3895.57	I
4	3903.86	I
6	3938.40	I
8	3986.75	I
10	4057.50	I
15	4167.27	I
20	4351.91	I
9	4384.64	II
10	4390.59	II
8	4428.00	II
9	4433.99	II
14	4481.16	II
13	4481.33	II
28	4571.10	I
10	4730.03	I
7	4851.10	II
75	5167.33	I
220	5172.68	I
400	5183.61	I
8	5264.21	II
7	5264.37	II
9	5401.54	II
6	5528.41	I
30	5711.09	I
10	6318.72	I
9	6319.24	I
7	6319.49	I
10	6346.74	II
9	6346.96	II
11	6545.97	II
7	6781.45	II
8	6787.85	II
7	6812.86	II
8	6819.27	II
10	7193.17	I
10	7291.06	I
12	7387.69	I
20	7657.60	I
19	7659.15	I
17	7659.90	I
15	7691.55	I
12	7877.05	II
13	7896.37	II
10	8098.72	I
9	8115.22	II
8	8120.43	II
10	8209.84	I
20	8213.03	I
10	8213.99	II
11	8234.64	II
10	8310.26	I
15	8346.12	I
10	8710.18	I
12	8712.69	I
13	8717.83	I
10	8734.99	II
17	8736.02	I
11	8745.66	II
14	8806.76	I
10	8824.32	II
11	8835.08	II
20	8923.57	I
10	8997.16	I
14	9218.25	II
13	9244.27	II
12	9246.50	I
30	9255.78	I
10	9327.54	II
10	9340.54	II
25	9414.96	I
17	9429.81	I
19	9432.76	I
20	9438.78	I
12	9631.89	II
11	9632.43	II
15	9953.20	I
15	9983.20	I
17	9986.47	I
18	9993.21	I
14	10092.16	II
35	10811.08	I
11	10914.23	II
10	10951.78	II
25	10953.32	I
27	10957.30	I
28	10965.45	I
15	11032.10	I
14	11033.66	I
45	11828.18	I
30	12083.66	I
28	14877.62	I
35	15024.99	I
30	15040.24	I
25	15047.70	I
10	15765.84	I
30	17108.66	I
5	26392.90	I

Manganese Mn Z = 25

600	410.30	V
600	410.60	V
600	415.62	V
650	415.98	V
600	428.59	V
600	435.67	V
1000	441.72	V
850	442.49	V
60	579.79	IV
60	581.44	IV
60	581.65	IV
60	585.21	IV
90	1242.25	IV
90	1244.50	IV
95	1251.93	IV
95	1257.28	IV
90	1264.41	IV
500	1283.58	III
400	1287.59	III
300	1291.62	III
1000	1360.72	III
800	1365.20	III
500 h	1609.17	III
1000	1614.14	III
2000	1620.60	III
500	1633.80	III
80	1667.00	IV
80	1698.30	IV
20	1726.47	II
30	1732.70	II
50	1733.55	II
40	1734.49	II
30	1737.93	II
20	1740.16	II
20	1742.00	II
85	1742.10	IV
85	1766.27	IV
80	1795.65	IV
80	1795.79	IV
30	1853.27	II
20	1857.92	II
50	1902.95	II
20	1907.84	II
75	1910.25	IV
30	1911.41	II
20 d	1914.68	II
100	1915.10	II
20	1918.64	II
30	1919.64	II
80	1921.25	II
20	1923.07	II
20	1923.34	II
30	1925.52	II
50	1926.59	II
30	1931.40	II
500	1941.28	III
800	1943.21	III
20	1945.15	II
20	1947.93	II
20	1950.14	II
500	1952.36	III
1000	1952.52	III
30	1953.23	II
20 d	1954.81	II
30	1959.25	II
20	1969.24	II
500	1978.95	III
30	1994.23	II
9700	1996.06	I
14000	1999.51	I
18000	2003.85	I
1000 w	2027.83	III
500 w	2028.14	III
50	2037.31	II
40	2037.64	II
40	2039.97	II
500	2049.68	III
500	2066.38	III
1000	2069.02	III
30	2076.21	II
900	2077.38	III
800	2084.23	III
600	2090.05	III
1500	2092.16	I
500	2094.78	III
20	2097.46	II
500	2097.93	III
500	2099.97	III
20	2102.50	II
1700	2109.58	I
30	2113.96	II
1000	2169.78	III
700	2174.15	III
900	2176.87	III
800	2181.86	III
800	2184.87	III
290	2208.81	I
540	2213.85	I
900	2220.55	III
770	2221.84	I
1000	2227.42	III
20	2373.36	II
20	2427.38	II
50	2427.72	II
30	2427.94	II
30	2437.37	II
20	2437.84	II
30	2452.49	II
50	2499.00	II
30	2507.60	II
20	2516.60	II
30	2516.74	II
20	2521.66	II
20	2530.72	II
20	2531.80	II
50	2532.78	II
50	2533.33	II
30	2534.10	II
80	2534.22	II
100	2535.66	II
30	2535.98	II
100	2537.92	II
50	2541.11	II
80	2542.92	II
50	2543.45	II
100	2548.75	II
50	2551.85	II
30	2553.27	II
75	2556.57	II
30	2556.89	II
95	2558.59	II
30	2559.41	II
150	2563.65	II
30	2565.22	II
580	2572.76	I
480	2575.51	I
12000	2576.10	II
550	2584.31	I

Intensity	Wavelength/Å	
30	2588.97	II
45	2589.71	II
250	2592.94	I
6200	2593.73	II
250	2595.76	I
95	2598.90	II
30	2602.72	II
45	2603.72	II
4300	2605.69	II
190	2610.20	II
500	2618.14	II
140	2622.90	I
150	2624.04	I
40	2624.80	II
200	2625.58	II
190	2632.35	II
130	2638.17	II
80	2639.84	II
27	2650.99	II
60	2655.91	II
30	2666.77	II
30	2667.03	II
110	2672.59	II
55	2673.37	II
55	2674.43	II
45	2680.34	II
30	2680.68	II
30	2681.25	II
55	2684.55	II
55	2685.94	II
110	2688.25	II
27	2693.19	II
55	2695.36	II
27	2698.97	II
85	2701.00	II
50	2701.17	II
160	2701.70	II
100	2703.98	II
130	2705.74	II
80	2707.53	II
110	2708.45	II
45	2709.96	II
80	2710.33	II
110	2711.58	II
30	2716.80	II
30	2717.53	II
30	2719.01	II
50	2719.74	II
30	2722.10	II
30	2724.46	II
55	2728.61	II
6200	2794.82	I
5100	2798.27	I
220	2799.84	I
3700	2801.06	I
110	2809.11	I
60	2815.02	II
30	2816.33	II
60	2870.08	II
30	2872.94	II
80	2879.49	II

Intensity	Wavelength/Å	
70	2886.68	II
160	2889.58	II
55	2892.39	II
50	2898.70	II
80	2900.16	II
140 h	2914.60	I
190 h	2925.57	I
1100	2933.06	II
1500	2939.30	II
250 h	2940.39	I
1900	2949.20	II
30	3019.92	II
55	3031.06	II
30	3035.35	II
330	3044.57	I
120	3045.59	I
200	3047.04	I
30	3050.65	II
250	3054.36	I
140	3062.12	I
170	3066.02	I
170	3070.27	I
160	3073.13	I
140 h	3178.50	I
220	3212.88	I
1000	3228.09	I
300	3230.72	I
850	3236.78	I
330	3243.78	I
650	3248.52	I
100	3251.14	I
310	3252.95	I
310	3256.14	I
220	3258.41	I
180	3260.23	I
180	3264.71	I
200	3330.78	II
720	3441.99	II
50	3460.03	II
360	3460.33	II
360 h	3474.04	II
	3474.13	II
290	3482.91	II
180	3488.68	II
140	3495.84	II
50	3496.81	II
100	3497.54	II
360	3531.85	I
1100	3532.12	I
1300	3547.80	I
1100	3548.03	I
390	3548.20	I
2200	3569.49	I
720	3569.80	I
1400	3577.88	I
720	3586.54	I
290	3595.12	I
150	3601.72	III
420	3607.54	I
420	3608.49	I
360	3610.30	I

Intensity	Wavelength/Å	
290	3619.28	I
220	3623.79	I
140	3629.74	I
100	3660.40	I
280	3693.67	I
180	3696.57	I
210	3706.08	I
130	3718.93	I
130	3731.93	I
260	3790.22	I
110	3800.55	I
3200	3806.72	I
700	3809.59	I
2100	3823.51	I
390	3823.89	I
200	3829.68	I
480	3833.86	I
1300	3834.36	I
350	3839.78	I
670	3841.08	I
350	3843.98	I
120	3926.47	I
130	3982.58	I
150	3985.24	I
190	3986.83	I
150	3987.10	I
1500	4018.10	I
150	4026.44	I
27000	4030.76	I
19000	4033.07	I
11000	4034.49	I
1500	4035.73	I
5600	4041.36	I
210 d	4045.13	I
1100	4048.76	I
150	4055.21	I
1900	4055.54	I
210	4057.95	I
1100	4058.93	I
150	4059.39	I
730	4061.74	I
730	4063.53	I
290	4070.28	I
730	4079.24	I
730	4079.42	I
1100	4082.94	I
1100	4083.63	I
200	4110.90	I
150	4131.12	I
120	4135.04	I
150	4176.60	I
120	4189.99	I
370	4235.14	I
510	4235.29	I
190	4239.72	I
290	4257.66	I
290	4265.92	I
270	4281.10	I
50	4323.63	II
350	4414.88	I
210	4436.35	I

Intensity	Wavelength/Å	
800	4451.59	I
160	4453.00	I
130	4455.01	I
160	4455.32	I
110	4455.82	I
210	4457.55	I
270	4458.26	I
150	4461.08	I
510	4462.02	I
290	4464.68	I
200	4470.14	I
130	4472.79	I
170	4490.08	I
240	4498.90	I
240	4502.22	I
160	4709.72	I
180	4727.48	I
130	4739.11	I
1000	4754.04	I
180	4761.53	I
750	4762.38	I
300	4765.86	I
500	4766.43	I
940	4783.42	I
1000	4823.52	I
19	5004.91	I
30	5074.79	I
200	5079.20	III
150	5100.03	III
60	5117.94	I
50	5150.89	I
50	5196.59	I
85	5255.32	I
160	5341.06	I
19	5349.88	I
95	5377.63	I
95	5394.67	I
50	5399.49	I
95	5407.42	I
35	5413.69	I
85	5420.36	I
35	5432.55	I
150	5454.07	III
12	5457.47	I
60	5470.64	I
200	5474.68	III
40	5481.40	I
30	5505.87	I
50	5516.77	I
40	5537.76	I
21	5551.98	I
200	5946.65	III
140	6013.50	I
200	6016.64	I
290	6021.80	I
200	6231.21	III
17	6440.97	I
24	6491.71	I
14 h	6942.52	I
12	6989.96	I
14	7069.84	I

Intensity	Wavelength/Å	
12	7184.25	I
24 h	7283.82	I
35 h	7302.89	I
50	7326.51	I
12	7680.20	I
12 h	8672.06	I
12 h	8701.05	I
17 h	8703.76	I
30 h	8740.93	I
Mercury 198 Hg Z = 80		
80	1250.564	I
8	1259.242	I
100	1268.825	I
5	1307.751	I
20	1402.619	I
10	1435.503	I
1000	1849.492	I
60	2262.210	II
20	2302.065	I
20	2345.440	I
100	2378.325	I
20	2380.004	I
40	2399.349	I
20	2399.729	I
20	2446.900	I
15	2464.064	I
40	2481.999	I
30	2482.713	I
40	2483.821	I
90	2534.769	I
15000	2536.506	I
25	2563.861	I
25	2576.290	I
250	2652.043	I
400	2653.683	I
100	2655.130	I
50	2698.831	I
80	2752.783	I
20	2759.710	I
40	2803.471	I
30	2804.438	I
750	2847.675	II
50	2856.939	I
150	2893.598	I
150	2916.227	II
60	2925.413	I
1200	2967.283	I
300	3021.500	I
120	3023.476	I
30	3025.608	I
50	3027.490	I
400	3125.670	I
320	3131.551	I
320	3131.842	I
80	3341.481	I
2800	3650.157	I
300	3654.839	I
80	3662.883	I
240	3663.281	I
30	3701.432	I
35	3704.170	I

Intensity	Wavelength/Å	
30	3801.660	I
20	3901.867	I
60	3906.372	I
200	3983.839	II
1800	4046.572	I
150	4077.838	I
40	4108.057	I
250	4339.224	I
400	4347.496	I
4000	4358.337	I
80	4916.068	I
1100	5460.753	I
160	5675.922	I
240	5769.598	I
280	5790.663	I
20	6072.713	I
30	6234.402	I
160	6716.429	I
250	6907.461	I
240	11287.407	I
Mercury Hg Z = 80		
3	621.44	III
2	679.68	III
2	878.59	III
1	886.48	III
400	893.08	II
300	915.83	II
150	923.39	II
200	940.80	II
100	962.74	II
50	969.13	II
1	988.89	III
2	1009.29	III
5	1068.03	III
800	1099.26	II
2	1161.95	III
80	1250.58	I
8	1259.24	I
100	1268.82	I
5	1307.75	I
300	1307.93	II
400	1321.71	II
400	1331.74	II
80	1350.07	II
200	1361.27	II
20	1402.62	I
200	1414.43	II
10	1435.51	I
15	1619.46	II
120	1623.95	II
20	1628.25	II
150	1649.94	II
50	1653.64	II
200	1672.41	II
9	1681.40	III
100	1702.73	II
100	1707.40	II
120	1727.18	II
250	1732.14	II
15	1759.75	III
20	1775.68	I

Intensity	Wavelength/Å	
40	1783.70	II
30	1796.22	II
200	1796.90	II
60	1798.74	II
30	1803.89	II
40	1808.29	II
400	1820.34	II
5	1832.74	I
1000	1849.50	I
160	1869.23	II
300	1870.55	II
200	1875.54	II
1	1894.77	III
20	1900.28	II
30	1927.60	II
300	1942.27	II
100	1972.94	II
200	1973.89	II
150	1987.98	II
90	2026.97	II
90	2052.93	II
70	2148.00	II
5	2247.55	I
60	2262.23	II
20	2302.06	I
7	2314.15	III
15	2323.20	I
5	2340.57	I
20	2345.43	I
20	2352.48	I
100	2378.32	I
20	2380.00	I
4	2380.55	III
40	2399.38	I
20	2399.73	I
10	2400.49	I
60	2407.35	II
50	2414.13	II
8	2431.65	III
5	2441.06	I
20	2446.90	I
15	2464.06	I
5	2480.56	III
40	2482.00	I
30	2482.72	I
40	2483.82	I
7	2484.50	III
90	2534.77	I
15000	2536.52	I
25	2563.86	I
25	2576.29	I
5	2578.91	I
2	2612.92	III
4	2617.97	III
15	2625.19	I
5	2639.78	I
250	2652.04	I
400	2653.69	I
100	2655.13	I
3	2670.49	III
5	2674.91	I

Intensity	Wavelength/Å	
50	2698.83	I
50	2699.38	I
80	2705.36	II
70	2724.43	III
80	2752.78	I
20	2759.71	I
6	2769.22	III
40	2803.46	I
30	2804.43	I
2	2805.34	I
2	2806.77	I
150	2814.93	II
3	2844.76	III
750	2847.68	II
50	2856.94	I
150	2893.60	I
150	2916.27	II
60	2925.41	I
150	2935.94	II
400	2947.08	II
1200	2967.28	I
300	3021.50	I
120	3023.47	I
30	3025.61	I
50	3027.49	I
15	3090.05	III
400	3125.67	I
320	3131.55	I
320	3131.84	I
400	3208.20	II
400	3264.06	II
5	3283.02	III
12	3312.28	III
80	3341.48	I
100	3385.25	II
8	3389.01	III
5	3450.77	III
400	3451.69	II
3	3500.35	III
4	3538.88	III
200	3549.42	II
5	3557.24	III
2800	3650.15	I
300	3654.84	I
80	3662.88	I
240	3663.28	I
30	3701.44	I
35	3704.17	I
30	3801.66	I
15	3803.51	III
100	3806.38	II
20	3901.87	I
60	3906.37	I
100	3918.92	II
200	3983.96	II
1800	4046.56	I
150	4077.83	I
40	4108.05	I
70	4122.07	III
10	4140.34	III
100	4216.74	III

Intensity	Wavelength/Å	
250	4339.22	I
400	4347.49	I
4000	4358.33	I
100	4398.62	II
15	4470.58	III
12	4552.84	III
90	4660.28	II
50	4797.01	III
80	4855.72	II
10	4869.85	III
5	4883.00	I
5	4889.91	I
80	4916.07	I
5	4970.37	I
80	4973.57	III
5	4980.64	I
20	5102.70	I
40	5120.64	I
100	5128.45	II
20	5137.94	I
30	5210.82	III
20	5290.74	I
5	5316.78	I
60	5354.05	I
30	5384.63	I
1100	5460.74	I
30	5549.63	I
160	5675.86	I
6	5695.71	III
240	5769.60	I
100	5789.66	I
280	5790.66	I
140	5803.78	I
60	5859.25	I
60	5871.73	II
20	5871.98	I
20	6072.72	I
1000	6149.50	II
25	6220.35	III
30	6234.40	I
35	6418.98	III
40	6501.38	III
80	6521.13	II
10	6584.26	III
6	6610.12	III
30	6709.29	III
160	6716.43	I
250	6907.52	I
250	7081.90	I
200	7091.86	I
40	7346.37	II
100	7485.87	II
12	7517.46	III
20	7728.82	I
7	7808.10	III
100	7944.66	II
25	7946.75	III
50	7984.51	III
5	8151.64	III
2000	10139.75	I
240	11287.40	I
120	13209.95	I
140	13426.57	I
60	13468.38	I
80	13505.58	I
500	13570.21	I
450	13673.51	I
200	13950.55	I
500	15295.82	I
100	16881.48	I
400	16920.16	I
300	16942.00	I
500	17072.79	I
400	17109.93	I
20	17116.75	I
20	17198.67	I
20	17213.20	I
70	17329.41	I
30	17436.18	I
50	18130.38	I
40	19700.17	I
	22493.28	I
250	23253.07	I
	32148.06	I
	36303.03	I

Molybdenum Mo Z = 42

50	867.92	IV
100	884.19	IV
60	886.05	IV
50	891.74	IV
100	1169.33	III
100	1254.93	III
100	1258.52	III
100	1262.21	III
100	1263.74	III
100	1274.37	III
100	1276.40	III
200	1277.40	III
200	1277.58	III
200	1278.40	III
150	1281.90	III
150	1283.60	III
100	1854.73	III
80	1926.26	IV
100	1929.24	IV
80	1971.06	IV
70	2010.92	IV
19000	2015.11	II
40000	2020.30	II
21000	2038.44	II
17000	2045.98	II
50	2060.38	IV
4800	2081.68	II
2400	2089.52	II
2200	2092.50	II
4000	2093.11	II
2700	2100.84	II
1500	2104.29	II
1400	2108.02	II
100	2184.37	III
100	2211.02	III
400	2269.69	II
150	2269.71	III
200	2294.97	III
160	2304.25	II
160	2306.97	II
150	2330.93	III
110	2332.12	II
190	2341.59	II
100	2359.76	III
110	2389.20	II
140	2403.61	II
120	2413.01	II
85	2498.28	II
200	2506.19	III
440	2538.46	II
330	2542.67	II
80	2558.88	II
85	2564.34	II
250	2593.70	II
250	2602.80	II
400	2616.78	I
440	2629.85	I
330	2636.67	II
720	2638.76	II
410	2640.99	I
600	2644.35	II
370	2646.49	II
640	2649.46	I
480	2653.35	II
560 h	2655.03	I
640	2660.58	II
720	2672.84	II
250	2673.27	II
1000	2679.85	I
95	2681.36	II
640	2683.23	II
880	2684.14	II
560	2687.99	II
480	2701.42	II
190	2713.51	II
290	2717.35	II
85	2726.97	II
140	2729.68	II
80	2730.20	II
330	2732.88	II
160	2736.96	II
80 h	2737.88	II
290	2746.30	II
110	2756.07	II
220	2763.62	II
240	2769.76	II
160	2773.78	II
190	2774.39	II
1700	2775.40	II
65	2777.86	II
880	2780.04	II
400	2784.99	II
100	2807.74	III
400	2807.76	II
1700	2816.15	II
220	2817.44	II
80	2827.74	II
80	2834.39	II
80	2835.33	II
160	2842.15	II
1700	2848.23	II
370	2853.23	II
370	2863.81	II
220	2866.69	II
1700	2871.51	II
85	2872.88	II
220	2879.05	II
65	2888.15	II
1300	2890.99	II
95	2891.28	II
190	2892.81	II
950	2894.45	II
140	2897.63	II
70	2900.80	II
290	2903.07	II
80	2907.12	II
600	2909.12	II
1100	2911.92	II
120	2918.83	II
1300	2923.39	II
140	2924.32	II
1100	2930.50	II
800	2934.30	II
95	2940.10	II
110	2941.22	II
150	2944.82	II
140	2946.69	II
95	2947.28	II
125	2947.32	III
95	2955.84	II
240	2956.06	II
70	2956.90	II
95	2960.24	II
250	2963.79	II
210	2965.27	II
70	2971.91	II
250	2972.61	II
80	2975.40	II
95	2992.84	II
95	3027.77	II
100	3060.78	II
800	3064.28	I
250	3065.04	II
800	3074.37	I
85	3077.66	II
800	3085.62	I
270	3087.62	II
190	3092.07	II
560	3094.66	I
560	3101.34	I
1400	3112.12	I
290	3122.00	II
14000	3132.59	I
110	3138.72	II
220	3152.82	II
55	3155.64	II
6000	3158.16	I
8700	3170.35	I

Intensity	Wavelength/Å	
95	3172.03	II
160	3172.74	II
120 d	3187.59	II
7600	3193.97	I
880	3205.88	I
3000	3208.83	I
560	3215.07	I
880	3228.22	I
600	3229.79	I
1100	3233.14	I
950	3237.08	I
65	3240.71	II
950	3256.21	I
480	3264.40	I
800	3270.90	I
200	3271.69	III
1100	3289.02	I
950	3290.82	I
190	3292.31	II
100	3313.62	II
190	3320.90	II
640	3323.95	I
1300	3344.75	I
95	3346.40	II
1600	3358.12	I
950	3363.78	I
950	3379.97	I
1900	3384.62	I
130	3395.36	II
640	3404.34	I
1300	3405.94	I
640	3437.22	I
130	3446.08	II
3200	3447.12	I
640	3449.07	I
950	3456.39	I
640	3460.78	I
800	3504.41	I
560	3508.12	I
480	3521.41	I
640	3537.28	I
520	3558.10	I
400	3563.14	I
1400	3581.89	I
1400	3624.46	I
1000	3635.43	I
400	3657.35	I
540	3664.81	I
590	3672.82	I
1300	3680.60	I
65	3688.31	II
180	3692.64	II
1400	3694.94	I
500	3727.69	I
80	3744.37	II
29000	3798.25	I
520	3826.70	I
940	3828.87	I
1700	3833.75	I
29000	3864.11	I
580	3869.08	I
580	3886.82	I
19000	3902.96	I
65	3941.48	II
1400	4062.08	I
2300	4069.88	I
1300	4081.44	I
940	4084.38	I
730	4107.47	I
630	4120.10	I
2900	4143.55	I
480	4185.82	I
2500	4188.32	I
1500	4232.59	I
890	4276.91	I
1200	4277.24	I
1400	4288.64	I
680	4292.13	I
890	4293.21	I
840	4326.14	I
1900	4381.64	I
2500	4411.57	I
990	4434.95	I
480	4457.36	I
630	4474.56	I
400	4536.80	I
460	4626.47	I
640	4707.26	I
700	4731.44	I
770	4760.19	I
410	4819.25	I
410	4830.51	I
180	5014.60	I
80	5029.00	I
65	5030.78	I
100	5047.71	I
50	5055.00	I
200	5059.88	I
100	5080.02	I
100	5096.65	I
130	5097.52	I
130	5109.71	I
80	5114.97	I
150	5145.38	I
110	5147.39	I
80	5163.19	I
100	5167.76	I
160 d	5171.08	I
230 h	5172.94	I
160 h	5174.18	I
110	5200.17	I
50	5200.74	I
50	5211.86	I
80	5219.40	I
65	5231.06	I
100	5234.26	I
460 h	5238.20	I
230 h	5240.88	I
110 h	5242.81	I
100	5245.51	I
150	5259.04	I
65	5261.14	I
65	5279.65	I
210	5280.86	I
55	5292.08	I
55	5295.47	I
55	5313.89	I
80	5354.88	I
65	5356.48	I
560 hl	5360.56	I
110 hl	5364.28	I
65	5394.52	I
50	5400.47	I
55	5435.68	I
65	5437.75	I
50	5501.54	I
7800	5506.49	I
5200	5533.05	I
50	5543.12	I
55	5556.28	I
2500	5570.45	I
100	5610.93	I
330	5632.47	I
50	5634.86	I
230	5650.13	I
55	5674.47	I
460	5689.14	I
80	5705.72	I
210	5722.74	I
620	5751.40	I
520	5791.85	I
55 h	5849.73	I
50 h	5851.52	I
520	5858.27	I
50	5869.33	I
820	5888.33	I
50 h	5893.38	I
160 h	5928.88	I
35	6025.49	I
1300	6030.66	I
40	6101.87	I
40	6357.22	I
35	6401.07	I
100	6424.37	I
230	6619.13	I
50	6650.38	I
110	6733.98	I
50	6746.27	I
35	6753.97	I
40	6838.88	I
35	6914.01	I
110	7109.87	I
150	7242.50	I
40	7245.85	I
40	7391.36	I
140	7485.74	I
27	7720.77	I
40 h	8328.44	I
45 h	8389.32	I
45 h	8483.39	I

Neodymium Nd Z = 60

75	2764.98	I
80	2993.20	II
95	3007.97	II
95	3014.19	II
95	3018.35	II
140	3056.71	II
130	3069.73	II
160	3075.38	II
240	3092.92	II
260	3115.18	II
290	3133.60	II
220	3134.90	II
170	3141.46	II
170	3142.44	II
150	3203.47	II
220	3259.24	II
220	3265.12	II
320	3275.22	II
290	3285.10	II
410	3328.28	II
320	3353.59	II
410	3560.75	II
470	3587.51	II
370	3615.82	II
410	3653.15	II
470	3662.26	II
540	3665.18	II
540	3672.36	II
580	3673.54	II
1200	3685.80	II
440	3687.30	II
410	3689.69	II
410	3697.56	II
470	3713.70	II
640 d	3714.73	II
470	3715.68	II
410	3718.54	II
410	3721.35	II
780	3723.50	II
410	3724.87	II
710	3728.13	II
470	3730.58	II
1000 d	3735.54	II
440	3737.10	II
1000	3738.06	II
580	3752.49	II
510	3757.82	II
930	3758.95	II
930	3763.47	II
510	3769.65	II
1400	3775.50	II
710	3779.47	II
580	3780.40	II
510	3781.32	II
2400	3784.25	II
370	3801.12	II
1200	3803.47	II
2500	3805.36	II
470	3807.23	II
540	3808.77	II
440	3809.06	II
580	3810.49	II
710	3814.73	II

Intensity	Wavelength/Å	
410	3822.47	II
1200	3826.42	II
540	3828.85	II
440	3829.16	II
510	3830.47	II
740	3836.54	II
1700	3838.98	II
410 d	3841.82	II
1700 d	3848.24	II
1500	3848.52	II
470	3850.22	II
2400 d	3851.66	II
3700 d	3863.33	II
850	3869.07	II
470	3875.87	II
1100	3878.58	II
1000	3879.55	II
780	3880.38	II
1200	3880.78	II
540	3887.87	II
1300	3889.93	II
1300	3890.58	II
1300	3890.94	II
580	3891.51	II
470	3892.06	II
810	3894.63	II
440	3897.63	II
2000	3900.21	II
1300	3901.84	II
1700	3905.89	II
510	3907.84	II
2000	3911.16	II
850	3912.23	II
440	3915.13	II
610	3915.95	II
1100	3920.96	II
510	3927.10	II
610	3934.82	II
410	3936.11	II
510	3938.86	II
2000	3941.51	II
2000	3951.16	II
810	3952.20	II
590	3958.00	II
510	3962.21	II
1400	3963.12	II
1100	3973.30	II
740	3973.69	II
740	3976.85	II
740	3979.49	II
470	3986.25	II
1400	3990.10	II
1000	3991.74	II
1100	3994.68	II
410	4000.50	II
540	4004.02	II
410	4007.43	II
3700	4012.25	II
540	4012.70	II
1000	4020.87	II
1000	4021.34	II
1000	4021.78	II
1200	4023.00	II
410	4030.47	II
1200	4031.82	II
3000	4040.80	II
410	4043.59	II
410	4048.81	II
850	4051.15	II
850	4059.96	II
4700	4061.09	II
1100	4069.28	II
710	4075.12	II
470	4075.28	II
470	4080.23	II
1400	4109.08	II
2500	4109.46	II
510	4110.48	II
410	4123.88	II
470	4133.36	II
510	4135.33	II
3000	4156.08	II
510	4156.26	II
410	4168.00	II
810	4175.61	II
2400	4177.32	II
640	4179.59	II
470	4205.60	II
470	4211.29	II
440	4227.73	II
1300	4232.38	II
2000	4247.38	II
850	4252.44	II
410	4261.84	II
470	4282.44	II
710	4284.52	II
5400	4303.58	II
470	4314.52	II
1100	4325.76	II
510	4327.93	II
540	4338.70	II
680	4351.29	II
850	4358.17	II
470 d	4374.93	II
710	4385.66	II
540	4400.83	II
510	4411.06	II
580	4446.39	II
1400	4451.57	II
740	4462.99	II
410	4501.82	II
250	4516.36	II
340	4541.27	II
340	4542.61	II
340	4563.22	II
300	4621.94	I
510	4634.24	I
340	4641.10	I
250	4645.77	II
300	4649.67	I
310	4683.45	I
470	4706.54	II
240	4719.02	I
240	4811.34	II
350	4825.48	II
280	4859.02	II
350	4883.81	I
220	4890.70	II
240	4891.07	I
280	4896.93	I
210	4901.84	I
330	4920.68	II
470	4924.53	I
260	4944.83	I
290	4954.78	I
290	4959.13	II
250	4989.94	II
360	5076.59	II
360	5092.80	II
360	5107.59	II
340	5123.79	II
680	5130.60	II
500	5191.45	II
630	5192.62	II
330	5200.12	II
310	5212.37	II
450	5234.20	II
250	5239.79	II
720	5249.59	II
360	5255.51	II
590	5273.43	II
680	5293.17	II
220	5311.46	II
500	5319.82	II
290	5361.47	II
160	5431.53	II
240	5594.43	II
220	5620.54	I
140 d	5675.97	I
220	5688.53	II
130	5702.24	II
160	5708.28	II
100	5729.29	I
160	5804.02	II
80	5811.57	II
70	5825.87	II
80	5842.39	II
55	5858.91	I
45	6007.67	I
45	6034.24	II
55	6066.03	I
45	6178.59	I
45	6223.39	I
55	6310.49	I
65	6385.20	II
45	6630.14	I
45	6650.57	II
40	6740.11	II
40	6900.43	II
35	7037.30	II
40	7066.89	II
29	7129.35	II
24	7189.42	II
20	7192.01	II
15	7236.54	II
12	7316.81	II
10	7406.62	II
10	7418.18	II
12	7511.16	II
17	7513.73	II
12	7528.99	II
10	7538.26	II
12	7696.56	II
10	7750.95	II
10	7808.47	II
12	7863.04	II
12	7917.01	II
12	7958.95	I
12	7965.73	II
15	7982.09	II
12	7982.68	II
12	8000.76	II
10	8120.93	II
12	8122.07	II
12	8141.75	II
12	8143.27	II
10	8231.52	II
10	8307.72	II
12	8346.36	II
17	8839.10	II

Neon Ne Z = 10

66	119.01	V
200	122.52	V
66	125.12	V
45	131.99	V
50	132.04	V
150	140.76	V
150	140.79	V
100	142.44	V
100	142.50	V
150	142.72	V
100	143.27	V
150	143.34	V
150	147.13	V
66	151.23	V
120	151.42	V
15	151.82	IV
15	152.23	IV
45	154.50	V
15	158.65	IV
15	158.82	IV
100	164.02	V
100	164.14	V
80	172.62	IV
500	173.93	V
80	177.16	IV
150	186.58	IV
100	194.28	IV
100	208.48	IV
100	208.73	IV
80	208.90	IV
150	212.56	IV
140	223.24	IV
120	223.60	IV

Intensity	Wavelength/Å	
140	234.32	IV
120	234.70	IV
20	251.14	III
20	251.56	III
20	251.73	III
40	267.06	III
40	267.52	III
20	267.71	III
40	283.18	III
160	283.21	III
110	283.69	III
40	283.89	III
220	301.12	III
220	313.05	III
220	313.68	III
40	313.95	III
90	352.956	I
60	354.962	I
50	357.83	IV
400	357.96	V
500	358.47	V
200	358.72	IV
500	359.38	V
90	361.433	II
60	362.455	II
1000	365.59	V
220	379.31	III
125	387.14	IV
100	388.22	IV
150	405.854	II
120	407.138	II
800	416.20	V
150	421.61	IV
200	445.040	II
300	446.256	II
250	446.590	II
180	447.815	II
150	454.654	II
200	455.274	II
10	456.275	II
120	456.348	II
90	456.896	II
1000	460.728	II
500	462.391	II
140	469.77	IV
200	469.82	IV
180	469.87	IV
140	469.92	IV
250	480.41	V
150	481.28	V
250	481.36	V
500	482.99	V
285	488.10	III
220	488.87	III
450	489.50	III
70	489.64	III
220	490.31	III
360	491.05	III
120	521.74	IV
140	521.82	IV
80	541.13	IV
100	542.07	IV
150	543.89	IV
400	568.42	V
250	569.76	V
500	569.83	V
250	572.11	V
800	572.34	V
35	587.213	I
35	589.179	I
35	589.911	I
70	591.830	I
100	595.920	I
75	598.706	I
35	598.891	I
70	600.036	I
170	602.726	I
170	615.628	I
170	618.672	I
120	619.102	I
200	626.823	I
200	629.739	I
1000	735.896	I
400	743.720	I
60	993.88	I
70	1068.65	I
90	1131.72	I
100	1131.85	II
90	1229.83	I
20	1255.03	III
110	1255.68	III
160	1257.19	III
90	1418.38	I
90	1428.58	I
90	1436.09	I
120	1681.68	II
180	1688.36	II
100	1888.11	II
100	1889.71	II
200	1907.49	II
500	1916.08	II
300	1930.03	II
200	1938.83	II
100 c	1945.46	II
80	2007.01	II
65	2018.44	IV
110	2022.19	IV
80	2025.56	II
150	2085.47	II
200	2086.96	III
300	2089.43	III
240	2092.44	III
400	2095.54	III
180	2096.11	II
120	2096.25	II
200	2161.22	III
300	2163.77	III
200	2180.89	III
30	2203.88	IV
200	2209.35	III
200	2211.85	III
240	2213.76	III
300	2216.07	III
10	2220.81	IV
75	2227.42	V
110	2232.41	V
65	2245.48	V
250	2258.02	IV
65	2259.57	V
175	2262.08	IV
240	2263.21	III
65	2263.39	V
110	2264.54	IV
200	2264.91	III
250	2265.71	V
550	2285.79	IV
30	2293.14	IV
250	2293.49	IV
250	2350.84	IV
450	2352.52	IV
700	2357.96	IV
250	2362.68	IV
250	2363.28	IV
110	2365.49	IV
350	2372.16	IV
65	2384.20	IV
350	2384.95	IV
300	2412.73	III
240	2412.94	III
200	2413.78	III
200	2473.40	III
80 p	2562.12	II
90 w	2567.12	II
800	2590.04	III
600	2593.60	III
400	2595.68	III
300	2610.03	III
240	2613.41	III
200	2615.87	III
80	2623.11	II
80	2629.89	II
90 w	2636.07	II
80	2638.29	II
200	2638.70	III
200	2641.07	III
80	2644.10	II
600	2677.90	III
500	2678.64	III
80	2762.92	II
90	2792.02	II
80	2794.22	II
100	2809.48	II
80	2906.59	II
80	2906.82	II
90	2910.06	II
90	2910.41	II
80	2911.14	II
80	2915.12	II
80	2925.62	II
80 w	2932.10	II
80	2940.65	II
90	2946.04	II
150	2955.72	II
150	2963.24	II
150	2967.18	II
100	2973.10	II
15	2974.72	I
100	2979.46	II
12	2982.67	I
150	3001.67	II
120 p	3017.31	II
300	3027.02	II
300	3028.86	II
100	3030.79	II
120	3034.46	II
100	3035.92	II
100	3037.72	II
100	3039.59	II
100	3044.09	II
100	3045.56	II
120	3047.56	II
100	3054.34	II
100	3054.68	II
100	3059.11	II
100	3062.49	II
100	3063.30	II
100	3070.89	II
100	3071.53	II
100	3075.73	II
120	3088.17	II
100	3092.09	II
120	3092.90	II
100	3094.01	II
100	3095.10	II
100	3097.13	II
100	3117.98	II
120	3118.16	II
10	3126.199	I
300	3141.33	II
100	3143.72	II
100 p	3148.68	II
100	3164.43	II
100	3165.65	II
100	3188.74	II
120	3194.58	II
500	3198.59	II
60	3208.96	II
120	3209.36	II
120	3213.74	II
150	3214.33	II
150	3218.19	II
120	3224.82	II
120	3229.57	II
200	3230.07	II
120	3230.42	II
120	3232.02	II
150	3232.37	II
100	3243.40	II
100	3244.10	II
100	3248.34	II
100	3250.36	II
150	3297.73	II
150	3309.74	II
300	3319.72	II

Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å	
1000	3323.74	II	250	3727.11	II	100	6074.338	I	1000	8571.352	I
150	3327.15	II	800	3766.26	II	80	6096.163	I	4000	8591.259	I
100	3329.16	II	1000	3777.13	II	60	6128.450	I	6000	8634.647	I
200	3334.84	II	100	3818.43	II	100	6143.063	I	3000	8647.041	I
150	3344.40	II	120	3829.75	II	120	6163.594	I	15000	8654.383	I
300	3345.45	II	150	4219.74	II	250	6182.146	I	4000	8655.522	I
150	3345.83	II	100	4233.85	II	150	6217.281	I	100	8668.26	II
200	3355.02	II	120	4250.65	II	150	6266.495	I	5000	8679.492	I
120	3357.82	II	120	4369.86	II	60	6304.789	I	5000	8681.921	I
200	3360.60	II	70	4379.40	II	100	6334.428	I	2000	8704.112	I
120	3362.16	II	150	4379.55	II	120	6382.992	I	4000	8771.656	I
100	3362.71	II	100	4385.06	II	200	6402.246	I	12000	8780.621	I
120	3367.22	II	200	4391.99	II	150	6506.528	I	10000	8783.753	I
12	3369.808	I	150	4397.99	II	60	6532.882	I	500	8830.907	I
40	3369.908	I	150	4409.30	II	150	6598.953	I	7000	8853.867	I
100	3371.80	II	100	4413.22	II	70	6652.093	I	1000	8865.306	I
500	3378.22	II	100	4421.39	II	90	6678.276	I	1000	8865.755	I
150	3388.42	II	100 p	4428.52	II	20	6717.043	I	3000	8919.501	I
120	3388.94	II	100 p	4428.63	II	100	6929.467	I	2000	8988.57	I
300	3392.80	II	150 p	4430.90	II	90	7024.050	I	100	9079.46	II
100	3404.82	II	150 p	4430.94	II	100	7032.413	I	6000	9148.67	I
120	3406.95	II	120	4457.05	II	50	7051.292	I	6000	9201.76	I
100	3413.15	II	100	4522.72	II	80	7059.107	I	4000	9220.06	I
120	3416.91	II	10	4537.754	I	100	7173.938	I	2000	9221.58	I
120	3417.69	II	10	4540.380	I	150	7213.20	II	2000	9226.69	I
50	3417.904	I	100	4569.06	II	150	7235.19	II	1000	9275.52	I
15	3418.006	I	15	4704.395	I	100	7245.167	I	200	9287.56	II
120	3428.69	II	12	4708.862	I	150	7343.94	II	6000	9300.85	I
60	3447.703	I	10	4710.067	I	40	7472.439	I	1500	9310.58	I
50	3454.195	I	10	4712.066	I	90	7488.871	I	3000	9313.97	I
100	3456.61	II	15	4715.347	I	100	7492.10	II	6000	9326.51	I
100	3459.32	II	10	4752.732	I	150	7522.82	II	2000	9373.31	I
25	3460.524	I	12	4788.927	I	80	7535.774	I	5000	9425.38	I
30	3464.339	I	10	4790.22	I	60	7544.044	I	3000	9459.21	I
30	3466.579	I	10	4827.344	I	100	7724.628	I	5000	9486.68	I
60	3472.571	I	10	4884.917	I	120	7740.74	II	5000	9534.16	I
150	3479.52	II	4	5005.159	I	300	7839.055	I	3000	9547.40	I
200	3480.72	II	10	5037.751	I	120	7926.20	II	120	9577.01	II
200	3481.93	II	10	5144.938	I	400	7927.118	I	1000	9665.42	I
25	3498.064	I	25	5330.778	I	700	7936.996	I	100	9808.86	II
30	3501.216	I	20	5341.094	I	2000	7943.181	I	800	10295.42	I
25	3515.191	I	8	5343.283	I	2000	8082.458	I	2000	10562.41	I
150	3520.472	I	60	5400.562	I	100	8084.34	II	1500	10798.07	I
120	3542.85	II	5	5562.766	I	1000	8118.549	I	2000	10844.48	I
120	3557.80	II	10	5656.659	I	600	8128.911	I	3000	11143.020	I
100	3561.20	II	5	5719.225	I	3000	8136.406	I	3500	11177.528	I
250	3568.50	II	12	5748.298	I	2500	8259.379	I	1600	11390.434	I
100	3574.18	II	80	5764.419	I	100	8264.81	II	1100	11409.134	I
200	3574.61	II	12	5804.450	I	2500	8266.077	I	3000	11522.746	I
50	3593.526	I	40	5820.156	I	800	8267.117	I	1500	11525.020	I
30	3593.640	I	500	5852.488	I	6000	8300.326	I	950	11536.344	I
15	3600.169	I	100	5872.828	I	100	8315.00	II	500	11601.537	I
20	3633.665	I	100	5881.895	I	1500	8365.749	I	1200	11614.081	I
150	3643.93	II	60	5902.462	I	100	8372.11	II	300	11688.002	I
200	3664.07	II	60	5906.429	I	8000	8377.606	I	2000	11766.792	I
20	3682.243	I	100	5944.834	I	1000	8417.159	I	1500	11789.044	I
12	3685.736	I	100	5965.471	I	4000	8418.427	I	500	11789.889	I
200	3694.21	II	100	5974.627	I	1500	8463.358	I	1000	11984.912	I
10	3701.225	I	120	5975.534	I	800	8484.444	I	3000	12066.334	I
150	3709.62	II	80	5987.907	I	5000	8495.360	I	800	12459.389	I
250	3713.08	II	100	6029.997	I	600	8544.696	I	1000	12689.201	I

Intensity	Wavelength/Å	
1100	12912.014	I
700	13219.241	I
800	15230.714	I
400	17161.930	I
400	18035.80	I
1000	18083.21	I
350	18221.11	I
250	18227.02	I
2500	18276.68	I
2000	18282.62	I
1200	18303.97	I
250	18359.12	I
1200	18384.85	I
2000	18389.95	I
1000	18402.84	I
1200	18422.39	I
300	18458.65	I
400	18475.79	I
900	18591.55	I
1600	18597.70	I
350	18618.96	I
550	18625.16	I
1200	21041.295	I
750	21708.145	I
300	22247.35	I
350	22428.13	I
2250	22530.40	I
400	22661.81	I
600	23100.51	I
1000	23260.30	I
1050	23373.00	I
850	23565.36	I
3500	23636.52	I
300	23701.64	I
1100	23709.2	I
1800	23951.42	I
600	23956.46	I
1000	23978.12	I
200	24098.54	I
500	24161.42	I
600	24249.64	I
1500	24365.05	I
800	24371.60	I
400	24447.85	I
700	24459.4	I
300	24776.46	I
550	24928.88	I
250	25161.69	I
650	25524.37	I
125	28386.21	I
150	30200.	I
250	33173.09	I
450	33352.35	I
1300	33901.	I
2200	33912.10	I
600	34131.31	I
100	34471.44	I
120	35834.78	I

Neptunium Np Z = 93

300	3481.93	I
300 h	3501.50	I
300 l	3986.89	I
300 s	5044.66	I
300 l	5601.70	I
300 l	5652.75	I
300 l	5784.39	I
300 l	5878.04	I
300 s	6011.22	I
300	6056.09	I
300 s	6073.90	I
300 s	6080.05	I
300 l	6120.49	I
300	6188.59	I
300 l	6200.00	I
300 s	6215.90	I
300 s	6317.84	I
300 l	6341.38	I
300 l	6566.11	I
300 l	6720.68	I
300 s	6751.32	I
300 s	6795.21	I
300 l	6802.62	I
300 l	6805.81	I
300 s	6816.44	I
300 l	6865.45	I
300 s	6907.13	I
300 h	6912.91	I
1000 s	6930.31	I
300 l	6963.63	I
3000 s	6972.09	I
300	7014.02	I
300 l	7018.91	I
300 s	7039.14	I
300 s	7080.01	I
300 l	7174.83	I
300 l	7184.93	I
300 l	7284.28	I
300 l	7292.29	I
300 l	7332.52	I
300 s	7370.60	I
300 l	7381.03	I
300 l	7381.65	I
300 l	7402.70	I
300 s	7512.22	I
300 l	7515.15	I
300 l	7546.05	I
300 l	7624.83	I
300	7626.85	I
300 s	7681.01	I
300 s	7685.25	I
1000 l	7735.14	I
300 l	7761.61	I
1000 l	7765.75	I
300 s	7776.07	I
300	7787.46	I
1000 l	7791.38	I
300 l	7851.44	I
300 l	7887.88	I
300 l	7901.71	I
300 l	7975.98	I
300 h	8080.32	I
300 s	8124.59	I
300	8155.11	I
300 l	8167.42	I
300 l	8183.06	I
300 l	8188.61	I
300 l	8247.82	I
300 l	8287.11	I
300 s	8287.75	I
300 l	8306.22	I
300 s	8313.66	I
1000 l	8339.12	I
300	8356.79	I
300 l	8367.11	I
3000	8372.88	I
3000	8529.96	I
1000 s	8696.23	I
1000 s	8906.02	I
1000	8942.70	I
1000 s	9004.75	I
1000 l	9006.31	I
10000 l	9016.18	I
3000 l	9141.30	I
3000 s	9379.33	I
3000 l	9468.66	I
3000 s	9679.13	I
3000 l	9930.55	I
10000 l	10091.99	I
10000 s	10817.45	I
10000 l	11695.15	I
10000 l	11776.64	I
10000 s	12148.18	I
10000 s	12377.42	I
10000 l	12407.99	I
10000 l	13834.33	I

Nickel Ni Z = 28

55	315.24	V
56	315.71	V
72	354.18	V
76	354.42	V
68	354.49	V
500	630.71	III
500	676.94	III
300	713.33	III
300	713.38	III
500	718.48	III
300	722.09	III
500	729.82	III
400	731.70	III
300	732.16	III
300	747.99	III
300	750.05	III
300	757.80	III
400	770.22	III
500	778.81	III
300	788.04	III
500	811.57	III
500	826.14	III
500	842.14	III
400	845.24	III
300	847.43	III
300	860.64	III
300	862.88	III
300	863.22	III
300	867.51	III
300	973.79	III
400	979.59	III
500	1317.22	II
76	1398.19	IV
74	1411.45	IV
70	1438.82	IV
73	1449.01	IV
76	1452.22	IV
73	1482.25	IV
72	1489.83	IV
75	1525.31	IV
74	1527.68	IV
74	1527.80	IV
76	1534.71	IV
73	1537.25	IV
75	1543.41	IV
74	1546.23	IV
300	1604.54	III
300	1652.87	III
400	1687.90	III
1000	1692.51	III
800	1709.90	III
650	1715.30	III
500	1719.46	III
400	1722.28	III
500	1738.25	III
300	1739.78	III
1000	1741.55	II
300	1741.96	III
550	1747.01	III
300	1752.43	III
400	1753.01	III
800	1764.69	III
500	1767.94	III
2000	1769.64	III
400	1776.07	III
300	1807.24	III
300	1819.28	III
800	1823.06	III
400	1830.01	III
650	1847.28	III
800	1854.15	III
300	1858.75	III
1000	2165.55	II
2000	2169.10	II
2000	2174.67	II
1500	2175.15	II
2500	2185.50	II
3000	2192.09	II
5000	2205.55	II
4000	2206.72	II
6000	2216.48	II
1000	2264.46	II
2000	2270.21	II
1600	2289.98	I
630	2300.78	I
1000	2303.00	II
2000	2310.96	I
1700	2312.34	I

Intensity	Wavelength/Å	
1400	2313.66	I
1400	2313.98	I
1000	2316.04	II
1400	2317.16	I
2600	2320.03	I
1900	2321.38	I
1400	2325.79	I
940	2329.96	I
1200	2345.54	I
400	2347.52	I
1000	2375.42	II
240	2386.58	I
1000	2394.52	II
2000	2416.13	II
240	2419.31	I
160	2472.06	I
150	2798.65	I
250	2821.29	I
500	2943.91	I
570	2981.65	I
500	2992.60	I
1000	2994.46	I
4000	3002.49	I
2200	3003.63	I
3700	3012.00	I
1700	3037.94	I
3500	3050.82	I
1500	3054.32	I
1900	3057.64	I
500	3064.62	I
2600	3101.55	I
1300	3101.88	I
2900	3134.11	I
1100	3232.96	I
600	3243.06	I
660	3315.66	I
2000	3331.88	II
2900	3369.57	I
3300	3380.57	I
1300	3391.05	I
3300	3392.99	I
8200	3414.76	I
1600	3423.71	I
2600	3433.56	I
990	3437.28	I
4800	3446.26	I
1300	3452.89	I
5000	3458.47	I
5000	3461.65	I
1600	3472.54	I
550	3483.77	I
5500	3492.96	I
660	3500.85	I
2600	3510.34	I
6600	3515.05	I
660	3519.77	I
8200	3524.54	I
5000	3566.37	I
990	3571.87	I
1300	3597.70	I
1300	3610.46	I
530	3612.74	I
6600	3619.39	I
200	3664.10	I
130	3669.24	I
180	3670.43	I
260	3674.15	I
160	3688.42	I
80	3693.93	I
120	3722.48	I
150	3736.81	I
60	3739.23	I
600	3775.57	I
700	3783.53	I
700	3807.14	I
110	3831.69	I
1200	3858.30	I
110	3973.56	I
110	4401.55	I
85	4459.04	I
55	4470.48	I
65	4605.00	I
75	4648.66	I
110	4714.42	I
45	4786.54	I
45	4855.41	I
40	4904.41	I
45	4980.16	I
45	4984.13	I
50	5017.59	I
100	5035.37	I
100	5080.52	I
65	5081.11	I
40 h	5146.48	I
40 h	5155.76	I
180	5476.91	I
23	5709.56	I
16	5754.68	I
10	5857.76	I
10	5892.88	I
10	6108.12	I
10	6176.81	I
10	6191.18	I
13	6256.36	I
16	6643.64	I
22	6767.77	I
10	6914.56	I
26	7122.20	I
16	7393.60	I
16	7409.35	I
23	7422.28	I
13	7522.76	I
19	7555.60	I
23	7617.00	I
16	7714.32	I
19	7727.61	I
19	7748.89	I
10	7788.94	I
13	7797.59	I
1000	8096.75	II
700	8121.48	II
9	8862.55	I
500 w	9900.92	II

Niobium Nb Z = 41

Intensity	Wavelength/Å	
80	464.55	V
80	468.32	V
80	763.77	V
80	774.02	V
60	993.54	IV
400	1005.72	IV
500	1007.05	IV
500	1010.19	IV
100	1116.08	IV
150	1120.02	IV
100	1258.87	V
60	1314.56	III
80	1445.43	III
80	1445.98	III
80	1447.09	III
100	1456.68	III
80	1484.73	III
100	1495.94	III
80	1498.02	III
80	1499.45	III
100	1501.99	III
60	1502.30	IV
80	1513.81	III
60	1524.36	IV
100	1524.91	III
100	1590.21	III
80	1598.86	III
80	1604.72	III
80	1639.51	III
100	1682.77	III
100	1705.44	III
100	1707.14	III
100	1758.33	V
100	1877.34	V
100	1892.92	III
60	1922.41	IV
100	1938.84	III
60	1978.22	IV
3300	2029.32	II
65	2032.53	IV
3000	2032.99	II
2000	2109.42	II
1700	2125.21	II
1100	2126.54	II
80 h	2130.24	III
1500	2131.18	II
80	2273.92	III
100	2275.23	III
80	2279.36	III
100	2281.51	III
80	2284.40	III
100	2290.36	III
370	2295.68	II
280	2302.08	II
100	2313.30	III
100	2338.09	III
80	2344.12	III
90	2349.21	III
80	2355.54	III
100	2362.06	III
80	2362.50	III
80	2365.70	III
100	2372.73	III
170	2376.40	II
110	2387.09	II
100	2387.41	III
140	2387.52	II
80	2388.23	III
45	2388.27	II
160	2398.48	II
80	2404.89	III
55	2405.34	II
55	2405.85	II
140	2412.46	II
100	2413.94	III
160	2416.99	II
140	2418.69	II
100	2421.91	III
75	2433.80	II
40	2435.95	II
45	2437.42	II
40	2442.14	II
28	2442.68	II
65	2451.87	II
65	2453.95	II
100	2456.99	III
55	2458.09	II
65	2462.89	I
80	2468.72	III
80	2475.87	III
110	2477.38	II
65	2478.29	II
65	2479.94	II
35	2483.88	II
100	2499.73	III
110	2511.00	II
110	2521.40	II
390	2544.80	II
100	2545.64	III
110	2551.38	II
130	2556.94	II
80	2557.94	III
130	2562.41	II
110	2571.33	II
390	2583.99	II
390	2590.94	II
80	2598.86	III
80	2633.17	III
200	2642.24	II
320	2646.26	II
330	2647.50	I
330	2654.45	I
310	2656.08	II
80	2657.99	III
110	2665.25	II
110	2666.59	II
110	2667.30	II
400	2671.93	II
200	2673.57	II
200	2675.94	II

Intensity	Wavelength/Å	
160	2691.77	II
1000	2697.06	II
320	2698.86	II
320	2702.20	II
150	2702.52	II
470	2716.62	II
470	2721.98	II
310	2733.26	II
110	2737.09	II
240	2768.13	II
310	2773.20	I
270	2780.24	II
110	2793.05	II
190	2827.08	II
250	2841.15	II
280	2842.65	II
160	2846.28	II
240	2861.09	II
100	2865.61	II
500	2868.52	II
800	2875.39	II
270	2876.95	II
530	2877.03	II
100	2880.72	II
570	2883.18	II
280	2888.83	II
470	2897.81	II
400	2899.24	II
470	2908.24	II
670	2910.59	II
470	2911.74	II
1100	2927.81	II
110	2931.47	II
870	2941.54	II
110 h	2945.88	II
110	2946.12	II
110	2946.90	II
1100	2950.88	II
400	2972.57	II
320	2974.10	II
210	2977.68	II
200	2982.11	II
330	2990.26	II
470	2994.73	II
80	3001.84	III
140	3024.74	II
350	3028.44	II
300	3032.77	II
100	3044.76	II
100	3055.52	II
220	3064.53	II
110	3069.68	II
100	3070.90	II
110	3071.56	II
100	3073.24	II
400	3076.87	II
110	3080.35	II
1800	3094.18	II
140	3099.19	II
270	3127.53	II
1500	3130.79	II
80	3142.26	III
390	3145.40	II
1200	3163.40	II
150	3175.78	II
390	3180.29	II
300	3191.10	II
150	3191.43	II
1000	3194.98	II
120	3203.35	II
300	3206.34	II
390	3215.60	II
800	3225.48	II
140	3229.56	II
400	3236.40	II
200	3247.47	II
120	3248.94	II
320	3254.07	II
230	3260.56	II
160	3263.37	II
200	3283.46	II
160	3292.02	II
320	3296.01	I
400	3312.60	I
120	3319.58	II
130	3341.60	II
1300	3341.97	I
1300	3343.71	I
1700	3349.06	I
420	3349.52	I
340	3354.74	I
1700	3358.42	I
130	3365.58	II
340	3366.96	I
130	3369.16	II
350	3374.92	I
170	3386.24	II
350	3392.34	I
230	3408.68	II
180	3409.19	II
230	3412.94	II
230	3425.42	II
230	3426.57	II
180	3432.70	II
180	3440.59	II
200	3479.56	II
100	3484.05	II
500	3498.63	I
460	3507.96	I
200	3510.26	II
200	3515.42	II
200	3517.67	II
2000	3535.30	I
1300	3537.48	I
250	3540.96	II
500	3544.02	I
300	3550.45	I
1000	3554.66	I
630	3563.50	I
630	3563.62	I
1500	3575.85	I
5000	3580.27	I
500	3584.97	I
750	3589.11	I
500	3589.36	I
500	3593.97	I
500	3602.56	I
300	3619.51	II
420	3649.85	I
400	3651.19	II
200	3659.61	II
630	3660.37	I
900	3664.70	I
1500	3697.85	I
330	3711.34	I
3300	3713.01	I
480	3716.99	I
2700	3726.24	I
2700	3739.80	I
670	3740.73	II
1700	3742.39	I
530	3763.49	I
350	3765.08	I
530	3771.85	I
870	3781.01	I
1700	3787.06	I
1300	3790.15	I
3500	3791.21	I
2700	3798.12	I
2700	3802.92	I
670	3803.88	I
530	3804.74	I
670	3810.49	I
530	3811.03	I
530	3815.51	I
210	3818.86	II
670	3824.88	I
350	3835.18	I
350	3863.38	I
530	3877.56	I
870	3878.82	I
670	3883.14	I
1100	3885.44	I
670	3885.68	I
580	3891.30	I
670	3914.70	I
530	3920.20	I
670	3937.44	I
520	3943.67	I
910 d	3966.09	I
1100	4032.52	I
16000 c	4058.94	I
350	4060.79	I
12000	4079.73	I
440	4100.40	I
6700	4100.92	I
310	4116.90	I
5300	4123.81	I
670	4129.43	I
770	4129.93	I
2300	4137.10	I
440	4139.44	I
2700	4139.71	I
350	4143.21	I
870	4150.12	I
4400	4152.58	I
870	4163.47	I
4400	4163.66	I
4000	4164.66	I
3500	4168.13	I
310	4184.44	I
1200	4190.88	I
870	4192.07	I
870	4195.09	I
1300	4195.66	I
310	4198.51	I
350	4201.52	I
870	4205.31	I
350	4214.73	I
420	4217.94	I
420	4229.15	I
770	4262.05	I
420	4266.02	I
400	4286.99	I
580	4299.60	I
580	4300.99	I
390	4311.27	I
350	4326.33	I
390	4331.37	I
330	4410.21	I
150	4503.04	I
530	4523.41	I
480	4546.82	I
370	4564.53	I
720	4573.08	I
480	4581.62	I
1200	4606.77	I
170	4616.17	I
450	4630.11	I
450	4648.95	I
450	4663.83	I
340	4666.24	I
240	4667.22	I
580	4672.09	I
530	4675.37	I
320	4685.14	I
130 c	4706.14	I
260	4708.29	I
150	4713.50	I
220 c	4749.70	I
130 c	4967.78	I
190	4988.97	I
230	5017.75	I
150	5026.36	I
210	5039.04	I
170	5058.01	I
130	5065.25	I
750	5078.96	I
420	5095.30	I
170	5100.16	I
170	5120.30	I
210	5134.75	I
250	5160.33	I
250	5164.38	I

Intensity	Wavelength/Å	
230	5180.31	I
190	5189.20	I
170	5193.08	I
150	5195.84	I
150	5232.81	I
150 d	5251.62	I
270	5271.53	I
130 c	5276.20	I
250	5318.60	I
460	5344.17	I
340	5350.74	I
110	5437.27	I
85	5551.35	I
170	5642.11	I
130	5664.71	I
170	5665.63	I
130	5729.19	I
110	5760.34	I
110	5819.43	I
130 d	5838.64	I
190 cw	5900.62	I
150	5983.22	I
75	6221.96	I
85 c	6430.46	I
65	6544.61	I
210 cw	6660.84	I
150 cw	6677.33	I
130 c	6723.62	I
85	6828.11	I
85	6990.32	I
190 c	7046.81	I
130	7159.43	I
190 cw	7372.50	I
65	7515.93	I
170 c	7574.58	I
75 c	7726.68	I
35	7885.31	I
40	8135.20	I
29 cw	8320.93	I
29	8346.08	I
35	8905.78	I

Nitrogen N Z = 7

400	181.75	IV
52	186.069	V
62	186.153	V
400	191.7	IV
400	192.9	IV
500	196.87	IV
500	197.23	IV
500	202.60	IV
500	205.94	IV
500	205.97	IV
500	206.03	IV
90	209.303	V
500	217.20	IV
500 d	217.90	IV
500 d	223.4	IV
800 w	225.12	IV
800	225.21	IV
600 w	234.12	IV
600 w	234.20	IV
600 w	234.25	IV
550	236.07	IV
500	237.99	IV
500 w	238.7	IV
600	238.80	IV
500 w	239.62	IV
900	247.20	IV
90	247.561	V
120	247.706	V
500 w	248.43	IV
500 w	248.46	IV
500 w	248.48	IV
500	257.95	III
650	258.50	III
700	259.19	III
800	260.09	III
600	260.45	IV
800	261.28	III
500	262.91	III
500	265.23	III
500	265.27	III
150	266.196	V
200	266.379	V
500	268.70	III
650	270.99	IV
250	283.42	IV
300	283.48	IV
350	283.58	IV
600	285.56	IV
600 w	297.7	IV
700	297.82	IV
650	300.32	IV
90	303.123	IV
500	303.28	IV
150	314.715	III
200	314.850	III
90	314.877	III
150	315.053	IV
120	322.503	IV
150	322.570	IV
200	322.724	IV
120	323.175	IV
600	323.26	III
300	335.050	IV
500	338.35	III
500	340.20	III
500 w	351.93	IV
500	351.98	III
700	353.06	IV
120	362.833	III
150	362.881	III
150	362.946	III
90	362.985	III
300	374.204	III
350	374.441	III
500	387.48	III
500	420.77	IV
250	451.869	III
300	452.226	III
650	463.74	IV
285	644.634	II
360	644.837	II
450	645.178	II
140	647.50	I
360	660.286	II
170	671.016	II
285	671.386	II
150	671.630	II
160	671.773	II
170	672.001	II
500	684.996	III
570	685.513	III
650	685.816	III
500	686.335	III
350	692.70	I
90	713.518	V
150	713.860	V
285	746.984	II
150	748.195	V
200	748.291	V
500	763.336	III
570	764.359	III
570	765.148	IV
250	771.544	III
300	771.901	III
350	772.385	III
200	772.891	III
150	772.975	III
650	775.965	II
90	885.67	I
90	909.697	I
80	910.278	I
40	910.645	I
450	915.612	II
450	915.962	II
550	916.012	II
650	916.701	II
520	921.992	IV
500	922.519	IV
480	923.057	IV
520	924.283	IV
90	953.415	I
100	953.655	I
130	953.970	I
1000	955.335	IV
130	963.990	I
115	964.626	I
70	965.041	I
650	979.842	III
700	979.919	III
900	989.790	III
700	991.514	III
1000	991.579	III
150 w	1036.16	IV
90	1067.614	I
60	1068.612	I
90	1078.71	IV
450	1083.990	II
600	1084.580	II
430	1085.546	II
650	1085.701	II
175	1097.237	I
115	1098.095	I
115	1098.260	I
105	1100.360	I
40	1100.465	I
90	1101.291	I
360	1134.165	I
385	1134.415	I
410	1134.980	I
105	1143.65	I
130	1163.884	I
60	1164.206	I
105	1164.325	I
270	1167.448	I
105	1168.334	I
60	1168.417	I
195	1168.536	I
230	1176.510	I
105	1176.630	I
195	1177.695	I
500	1183.031	III
570	1184.550	III
90	1188.01	IV
410	1199.550	I
385	1200.223	I
360	1200.710	I
175	1225.026	I
160	1225.37	I
130	1228.41	I
160	1228.79	I
1000	1238.821	V
900	1242.804	V
360	1243.179	I
315	1243.306	I
290	1310.540	I
250	1310.95	I
230	1319.00	I
315	1319.68	I
115	1326.57	I
115	1327.92	I
150	1387.371	III
360	1411.94	I
700	1492.625	I
490	1492.820	I
640	1494.675	I
90	1549.336	V
200 l	1616.33	V
350 l	1619.69	V
1000	1718.55	IV
250	1729.945	III
775	1742.729	I
700	1745.252	I
570	1747.848	III
350	1751.218	III
650	1751.657	III
150	1804.486	III
200	1805.669	III
150	1846.42	III
90 w	1860.37	V
350	1885.06	III
400	1885.22	III
200	1907.99	III

Intensity	Wavelength/Å	
150	1919.55	III
150	1919.77	III
300	1920.65	III
150	1920.84	III
200	1921.30	III
200	2064.01	III
250	2064.42	III
120	2068.68	III
90	2071.09	III
90	2080.34	IV
160	2095.53	II
70	2096.20	II
110	2096.86	II
90	2117.59	III
90	2121.50	III
110	2130.18	II
160	2142.78	II
90	2147.31	III
200	2188.20	III
150	2188.38	III
160	2206.09	II
160	2286.69	II
110	2288.44	II
220	2316.49	II
160	2316.69	II
285	2317.05	II
90 w	2318.09	IV
160	2461.27	II
150	2477.69	IV
110	2496.83	II
70	2496.97	II
110	2520.22	II
160	2520.79	II
220	2522.23	II
110	2590.94	II
250	2645.65	IV
300	2646.18	IV
350	2646.96	IV
250 w	2682.18	III
90	2689.20	III
160	2709.84	II
110	2799.22	II
110	2823.64	II
60 l	2859.16	V
160	2885.27	II
90 l	2974.52	V
150 w	2980.78	V
250 w	2981.31	V
60 w	2998.43	V
220	3006.83	II
90	3078.25	IV
120	3367.34	III
360	3437.15	II
90	3463.37	IV
570	3478.71	IV
500	3482.99	IV
400	3484.96	IV
90	3747.54	IV
90	3754.67	III
120	3771.05	III
285	3838.37	II
360	3919.00	II
90	3938.52	III
450	3955.85	II
1000	3995.00	II
150	3998.63	III
200	4003.58	III
360	4035.08	II
550	4041.31	II
360	4043.53	II
150	4057.76	IV
250	4097.33	III
140	4099.94	I
200	4103.43	III
185	4109.95	I
285	4176.16	II
120	4195.76	III
150	4200.10	III
285	4227.74	II
285	4236.91	II
220	4237.05	II
450	4241.78	II
90	4332.91	III
120	4345.68	III
300	4379.11	III
285	4432.74	II
650	4447.03	II
90	4510.91	III
120	4514.86	III
360	4530.41	II
550	4601.48	II
350	4603.73	V
90	4606.33	IV
450	4607.16	II
360	4613.87	II
250	4619.98	V
450	4621.39	II
870	4630.54	II
90	4634.14	III
120	4640.64	III
550	4643.08	II
285	4788.13	II
450	4803.29	II
180	4847.38	I
90	4858.82	III
150	4867.15	III
285	4895.11	II
160	4914.94	I
210	4935.12	I
200 w	4944.56	V
160	4950.23	I
350	4963.98	I
285	4987.37	II
450	4994.36	II
650	5001.48	II
360	5002.70	II
870	5005.15	II
550	5007.32	II
450	5010.62	II
360	5016.39	II
360	5025.66	II
550	5045.10	II
185	5281.20	I
140	5292.68	I
90	5314.35	III
200	5320.82	III
150	5327.18	III
450	5495.67	II
285	5535.36	II
650	5666.63	II
550	5676.02	II
870	5679.56	II
450	5686.21	II
450	5710.77	II
285	5747.30	II
700	5752.50	I
240	5764.75	I
265	5829.54	I
235	5854.04	I
360	5927.81	II
550	5931.78	II
285	5940.24	II
650	5941.65	II
285	5952.39	II
160	5999.43	I
210	6008.47	I
285	6167.76	II
360	6379.62	II
150	6380.77	IV
185	6411.65	I
210	6420.64	I
210	6423.02	I
210	6428.32	I
185	6437.68	I
235	6440.94	I
90	6454.11	III
185	6457.90	I
120	6467.02	III
300	6468.44	I
265	6481.71	I
750	6482.05	II
360	6482.70	I
300	6483.75	I
325	6484.80	I
160	6491.22	I
210	6499.54	I
185	6506.31	I
750	6610.56	II
185	6622.54	I
185	6636.94	I
235	6644.96	I
185	6646.50	I
235	6653.46	I
210	6656.51	I
185	6722.62	I
210	7398.64	I
160	7406.12	I
265	7406.24	I
685	7423.64	I
785	7442.29	I
900	7468.31	I
185	7608.80	I
60 w	7618.46	V
450	7762.24	II
400	8184.87	I
400	8188.02	I
250	8200.36	I
300	8210.72	I
570	8216.34	I
400	8223.14	I
400	8242.39	I
550	8438.74	II
500	8567.74	I
570	8594.00	I
650	8629.24	I
500	8655.89	I
220	8676.08	II
700	8680.28	I
650	8683.40	I
500	8686.15	I
110	8687.43	II
110 h	8699.00	II
500	8703.25	I
160 h	8710.54	II
570	8711.70	I
500	8718.83	I
250	8728.89	I
200	8747.36	I
500	9386.80	I
570	9392.79	I
250	9460.68	I
200	9863.33	I
160 h	9865.41	II
110 h	9868.21	II
160 h	9887.39	II
220 h	9891.09	II
160 h	9961.86	II
220 h	9969.34	II
285 h	10023.27	II
220 h	10035.45	II
220 h	10065.15	II
160 h	10070.12	II
250	10105.13	I
300	10108.89	I
350	10112.48	I
400	10114.64	I
110 h	10126.27	II
250	10539.57	I
200	12074.51	I
380	12186.82	I
225	12288.97	I
290	12328.76	I
310	12381.65	I
180	12438.40	I
510	12461.25	I
920	12469.62	I
500	13429.61	I
840	13581.33	I
180	13587.73	I
180	13602.27	I
290	13624.18	I
250	14757.07	I
100	14868.87	I
160	14966.60	I

Intensity	Wavelength/Å	
180	15582.27	I
120 s	17516.58	I
100 l	17584.86	I
100	17878.26	I
Osmium Os Z = 76		
9600	2001.45	I
13000	2003.73	I
17000	2010.15	I
29000	2018.14	I
14000	2022.76	I
14000	2028.23	I
18000	2034.44	I
26000	2045.36	I
8600	2058.69	I
13000	2061.69	I
7800	2067.21	II
4200	2070.67	II
7200	2076.95	I
14000	2079.97	I
2900	2082.54	I
2900	2089.03	I
2900	2089.21	I
6000	2097.60	I
5300	2100.63	I
2100	2117.66	I
4800	2117.96	I
5300	2137.11	I
2600	2154.59	I
1300	2157.84	I
1200	2158.53	I
3100	2166.90	I
1100	2167.75	I
2100	2171.65	I
1100	2234.61	I
1300	2252.15	I
2000	2255.85	II
1400	2264.60	I
1400	2282.26	II
500	2367.35	II
2600	2377.03	I
1700	2387.29	I
1100	2395.88	I
200	2423.07	II
1400	2424.97	I
110	2454.91	II
1800	2461.42	I
110	2468.90	II
530	2486.24	II
4500	2488.55	I
2600	2498.41	I
2400	2513.25	I
780	2538.00	II
1000	2542.51	I
1000	2590.76	I
1800	2613.06	I
3800	2637.13	I
1900	2644.11	I
1900	2658.60	I
2100	2689.82	I
3000	2714.64	I
1300	2720.04	I
960	2770.71	I
2800	2806.91	I
5100	2838.63	I
2300	2844.40	I
1500	2850.76	I
1500	2860.96	I
9600	2909.06	I
2100	2912.33	I
2100	2919.79	I
1100 h	2948.23	I
1400	2949.53	I
4400	3018.04	I
1100	3030.70	I
2900	3040.90	I
120	3042.74	II
8600	3058.66	I
1100	3077.72	I
3100	3156.25	I
180	3173.93	II
150	3213.31	II
1900	3232.06	I
3100	3262.29	I
3100	3267.94	I
1200	3290.26	I
7600	3301.56	I
960	3336.15	I
960	3370.59	I
620	3387.84	I
620	3401.86	I
620	3504.66	I
1200	3528.60	I
1200	3560.86	I
620	3598.11	I
95	3604.48	II
480	3670.89	I
3700	3752.52	I
2100	3782.20	I
730	3876.77	I
1000	3963.63	I
730	3977.23	I
960	4066.69	I
1200	4112.02	I
2500	4135.78	I
1200	4173.23	I
1200	4211.86	I
4900	4260.85	I
560	4293.95	I
560	4311.40	I
4900	4420.47	I
540	4550.41	I
670	4793.99	I
55	5031.83	I
45	5039.12	I
35	5072.88	I
35	5074.77	I
35	5079.09	I
90	5103.50	I
55	5110.81	I
140	5149.74	I
40	5193.52	I
270	5202.63	I
35	5203.23	I
45	5255.82	I
55	5265.15	I
40	5298.78	I
110	5376.79	I
120	5416.34	I
45	5416.69	I
28	5417.51	I
55	5443.31	I
22	5446.93	I
22	5457.30	I
28	5470.00	I
22	5509.33	I
270	5523.53	I
22	5546.82	I
80	5584.44	I
35	5620.08	I
22	5642.56	I
28	5645.25	I
28	5680.88	I
170	5721.93	I
22	5765.05	I
170	5780.82	I
40	5800.60	I
110	5857.76	I
28	5860.64	I
65	5996.00	I
35	6227.70	I
22	6269.41	I
22	6403.15	I
27	6729.56	I
22	7145.54	I
26	7602.95	I
7	8041.29	I
Oxygen O Z = 8		
80	124.616	V
110	135.523	V
80	138.109	V
110	139.029	V
80	151.447	V
110	151.477	V
150	151.546	V
80	164.574	V
110	164.657	V
80	164.709	V
80	166.235	V
150	167.99	V
110	170.219	V
450	172.169	V
250	185.745	V
375	192.751	V
450	192.799	V
520	192.906	V
80	193.003	V
200	194.593	V
150	195.86	IV
200	196.01	IV
80	202.161	V
80	202.224	V
80	202.283	V
80	202.334	V
150	202.393	V
110	203.78	V
150	203.82	V
100	203.85	V
200	203.89	V
100	203.94	V
110	207.18	IV
150	207.24	IV
300	207.794	V
150	215.040	V
200	215.103	V
250	215.245	V
250	216.018	V
520	220.352	V
80	227.372	V
80	227.469	V
150	227.511	V
80	227.549	V
80	227.634	V
80	227.689	V
150	231.823	V
140	233.46	IV
150	233.50	IV
110	233.52	IV
200	233.56	IV
110	233.60	IV
90	238.36	IV
180	238.57	IV
110	248.459	V
110	252.56	IV
110	252.95	IV
150	253.08	IV
300	260.39	IV
250	260.56	IV
80 d	264.34	III
110	264.48	III
110	266.97	III
150	266.98	III
150	267.03	III
150	277.38	III
300	279.63	IV
375	279.94	IV
110	285.71	IV
150	285.84	IV
110	286.448	V
80	295.62	III
110	295.66	III
120	295.72	III
150	303.41	III
150	303.46	III
140	303.52	III
160	303.62	III
160	303.69	III
250	303.80	III
200	305.60	III
250	305.66	III
190	305.70	III
300	305.77	III
190	305.84	III
200	306.62	IV
150	306.88	IV

Intensity	Wavelength/Å	
450	320.979	III
300	328.45	III
250	328.74	III
300	345.31	III
110	355.14	III
90	355.33	III
80	355.47	III
200	359.02	III
190	359.22	III
150	359.38	III
210	373.80	III
200	374.00	III
300	374.08	III
190	374.16	III
200	374.33	III
210	374.44	III
450	395.558	III
300	434.98	III
800	507.391	III
900	507.683	III
1000	508.182	III
1000	525.795	III
250	537.83	II
300	538.26	II
220	539.09	II
200	539.55	II
150	539.85	II
700	553.330	IV
775	554.075	IV
850	554.514	IV
700	555.261	IV
700	597.818	III
1000	599.598	III
580	608.398	IV
110	609.70	III
640	609.829	IV
160	610.04	III
200	610.75	III
100	610.85	III
270	616.952	IV
150	617.005	IV
200	617.036	IV
520	624.617	IV
580	625.130	IV
640	625.852	IV
1000	629.730	V
150	644.148	II
200	672.95	II
150	673.77	II
230	681.272	V
70	685.544	I
800	702.332	III
800	702.822	III
900	702.899	III
1000	703.850	III
900	718.484	II
600	718.562	II
70	744.794	I
700	758.678	V
640	759.441	V
580	760.228	V

Intensity	Wavelength/Å	
775	760.445	V
640	761.128	V
700	762.003	V
70	770.793	I
90	771.056	I
520	774.518	V
70	775.321	I
200	779.734	IV
315	779.821	IV
360	779.912	IV
200	779.997	IV
640	787.711	IV
520	790.109	IV
700	790.199	IV
70	791.973	I
300	796.66	II
200	802.200	IV
160	802.255	IV
90	804.267	I
70	804.848	I
70	805.295	I
80	805.810	I
240	832.762	II
600	832.927	III
450	833.332	II
780	833.742	III
600	834.467	II
600	835.096	III
800	835.292	III
40	877.879	I
130	921.296	IV
160	921.366	IV
80	922.008	I
200	923.367	IV
130	923.433	IV
90	935.193	I
40	948.686	I
90	971.738	I
40	976.448	I
160	988.773	I
40	990.204	I
250	1025.762	I
90	1027.431	I
160	1039.230	I
60	1040.942	I
40	1152.152	I
900	1302.168	I
600	1304.858	I
300	1306.029	I
200	1338.612	IV
130	1342.992	IV
230	1343.512	IV
640	1371.292	V
160	1476.89	III
160 w	1506.72	V
285	1590.01	III
160	1591.33	III
315 w	1643.68	V
160	1707.996	V
220	1760.12	III
110	1760.42	III

Intensity	Wavelength/Å	
220	1763.22	III
220	1764.48	III
750	1767.78	III
550	1768.24	III
360	1771.67	III
110	1773.00	III
110	1773.85	III
220	1779.16	III
160	1781.03	III
160	1784.85	III
220	1789.66	III
110	1848.26	III
110	1856.62	III
285	1872.78	III
285	1872.87	III
285	1874.94	III
160	1920.04	III
110	1920.75	III
110	1921.52	III
220	1923.49	III
110	1923.82	III
110	1926.94	III
360	2013.27	III
160	2026.96	III
220	2045.67	III
160	2052.74	III
30 d	2283.42	II
30 d	2284.89	II
110	2293.32	II
200	2300.35	II
30 d	2313.05	II
30 d	2316.12	II
30 d	2316.79	II
50 d	2319.68	II
30 d	2322.15	II
30 d	2339.31	II
200 d	2390.44	III
80	2394.33	III
110	2411.60	II
80	2422.84	III
80	2425.55	II
250	2433.56	II
80 d	2436.06	II
80 d	2438.83	III
80	2444.26	II
300	2445.55	II
200	2449.372	IV
200	2450.040	IV
200	2454.99	III
200	2493.44	IV
200	2493.77	IV
200	2507.73	IV
230	2509.19	IV
200	2517.2	IV
200	2558.06	III
80	2687.53	III
110	2695.49	III
300	2733.34	II
110	2747.46	II
1000	2781.01	V
920	2786.99	V

Intensity	Wavelength/Å	
775	2789.85	V
160	2836.26	IV
160	2921.45	IV
200	2941.33	V
210	2941.65	V
80	2959.68	III
265	2972.29	I
250	2983.78	III
80	3017.63	III
80	3023.45	III
80	3043.02	III
200	3047.13	III
110	3059.30	III
460	3063.42	IV
410	3071.61	IV
80	3121.71	III
160	3122.62	II
220	3129.44	II
110	3132.86	III
450	3134.82	II
285	3138.44	II
160	3144.66	V
160	3209.66	IV
80	3238.57	III
200	3260.98	III
300	3265.46	III
80	3267.31	III
220	3270.98	II
220	3273.52	II
220	3277.69	II
360	3287.59	II
160	3305.15	II
160	3306.60	II
80	3312.30	III
110	3340.74	III
230	3348.08	IV
270	3349.11	IV
160	3354.27	IV
200	3375.40	IV
220	3377.20	II
130	3378.06	IV
360	3381.20	IV
360	3385.52	IV
285	3390.25	II
270	3396.79	IV
360	3403.52	IV
220	3407.38	II
230	3409.66	IV
160	3409.84	II
410	3411.69	IV
230	3413.64	IV
80	3444.10	III
80	3455.12	III
285	3470.81	II
200	3489.83	IV
160	3492.24	IV
230	3560.39	IV
270	3563.33	IV
80	3698.70	III
80	3702.75	III
80	3703.37	III

Intensity	Wavelength/Å	
110	3707.24	III
220	3712.75	II
110	3715.08	III
315 w	3725.93	IV
285	3727.33	II
360	3729.03	IV
410	3736.85	IV
160	3739.92	II
110	3744.00	III
230	3744.89	IV
360	3749.49	II
150	3754.67	III
80	3757.21	III
250	3759.87	III
110	3791.26	III
160	3803.14	II
120	3823.41	I
450	3911.96	II
160	3919.29	II
185	3947.29	I
160	3947.48	I
140	3947.59	I
220	3954.37	II
100	3954.61	I
200	3961.59	III
450	3973.26	II
220	3982.20	II
160	4069.90	II
285	4072.16	II
450	4075.87	II
80 d	4083.91	II
50 d	4087.14	II
150 d	4089.27	II
110	4097.24	II
220	4105.00	II
285	4119.22	II
100	4123.99	V
160	4132.81	II
50	4146.06	II
220	4153.30	II
285	4185.46	II
450	4189.79	II
80	4233.27	I
50 d	4253.74	II
50 d	4253.98	II
50 d	4275.47	II
50 d	4303.78	II
285	4317.14	II
160	4336.86	II
220	4345.56	II
285	4349.43	II
220	4366.90	II
100	4368.25	I
220	4395.95	II
450	4414.91	II
285	4416.98	II
160	4448.21	II
160	4452.38	II
50	4465.45	II
50 d	4466.28	II
50	4467.83	II
50	4469.41	II
360	4590.97	II
285	4596.17	II
80 d	4609.39	II
160	4638.85	II
360	4641.81	II
450	4649.14	II
160	4650.84	II
360	4661.64	II
285	4676.23	II
220	4699.21	II
285	4705.36	II
160	4924.60	II
230 w	4930.27	V
220	4943.06	II
135	5329.10	I
160	5329.68	I
190	5330.74	I
90	5435.18	I
110	5435.78	I
135	5436.86	I
120	5577.34	I
110	5592.37	III
130	5597.91	V
160	5958.39	I
190	5958.58	I
80	5995.28	I
160	6046.23	I
190	6046.44	I
110	6046.49	I
100	6106.27	I
400	6155.98	I
450	6156.77	I
490	6158.18	I
80	6256.83	I
100	6261.55	I
100	6366.34	I
100	6374.32	I
320	6453.60	I
360	6454.44	I
400	6455.98	I
130	6500.24	V
80	6604.91	I
100	6653.83	I
360	7001.92	I
450	7002.23	I
210	7156.70	I
400	7254.15	I
450	7254.45	I
320	7254.53	I
210	7476.44	I
100	7477.24	I
120	7479.08	I
120	7480.67	I
100	7706.75	I
870	7771.94	I
810	7774.17	I
750	7775.39	I
80	7886.27	I
100	7943.15	I
100	7947.17	I
235	7947.55	I
210	7950.80	I
185	7952.16	I
110	7981.94	I
135	7982.40	I
190	7986.98	I
135	7987.33	I
250	7995.07	I
400	8221.82	I
265	8227.65	I
265	8230.02	I
325	8233.00	I
120	8235.35	I
120	8426.16	I
810	8446.25	I
1000	8446.36	I
935	8446.76	I
325	8820.43	I
160 d	9057.01	I
120	9118.29	I
80	9134.71	I
80	9150.14	I
80	9151.48	I
235	9156.01	I
450	9260.81	I
490	9260.84	I
450	9260.94	I
400	9262.58	I
540	9262.67	I
590	9262.77	I
490	9265.94	I
640	9266.01	I
185	9399.19	I
120	9481.16	I
120 d	9482.88	I
235	9487.43	I
140	9492.71	I
265	9497.97	I
160	9499.30	I
235	9505.59	I
210	9521.96	I
120	9523.36	I
120	9523.96	I
100	9528.28	I
100	9622.13	I
120	9625.29	I
160	9677.38	I
80	9694.66	I
65	9694.91	I
235	9741.50	I
235	9760.65	I
120	9909.05	I
140	9936.98	I
120	9940.41	I
160	9995.31	I
120 d	10421.18	I
590	11286.34	I
640	11286.91	I
490	11287.02	I
490	11287.32	I
490	11295.10	I
540	11297.68	I
590	11302.38	I
265	11358.69	I
490	12464.02	I
450	12570.04	I
120	12990.77	I
160	13076.91	I
700	13163.89	I
750	13164.85	I
640	13165.11	I
160	16212.06	I
120	17966.70	I
590	18021.21	I
120	18041.48	I
120	18042.19	I
120	18046.23	I
140	18229.23	I
540	18243.63	I
140	26173.56	I

Palladium Pd Z = 46

200	705.49	III
200	727.72	III
500	763.06	III
500	766.42	III
2000	781.02	III
500	794.08	III
500	797.52	III
500	800.03	III
500	800.10	III
500	803.67	III
500	825.35	III
500	840.58	III
500	856.47	III
500	864.04	III
500	880.59	III
500	888.84	III
1000	889.29	III
300	1596.89	III
500	1741.62	III
4000	1782.55	III
400	1843.49	III
1500	1851.59	III
2000	1852.27	III
1000	1859.21	III
1500	1874.63	III
2000	1885.83	III
1000	1887.40	III
1500	1891.34	III
4000	1914.62	III
1000	1930.33	III
2000	1941.64	III
800	2002.16	III
1000	2004.47	III
500	2055.11	III
500	2149.82	III
500	2177.55	III
500	2177.63	III
100 r	2231.59	II
200 r	2296.53	II
100	2426.87	II
100	2430.94	II

Intensity	Wavelength/Å	
100	2433.11	II
100	2435.32	II
150	2446.17	II
1100	2447.91	I
100	2457.29	II
150	2469.29	II
100	2471.18	II
1700	2476.42	I
250	2486.52	II
300	2488.92	II
200	2498.81	II
150	2505.73	II
150	2551.84	II
150	2565.51	II
100	2569.56	II
150	2658.75	II
1900	2763.09	I
150 h	2776.85	II
100 h	2787.92	II
200	2854.59	II
100 h	2871.37	II
100 h	2878.01	II
520	2922.49	I
650	3002.65	I
1500	3027.91	I
1100	3065.31	I
2600	3114.04	I
11000	3242.70	I
2700	3251.64	I
3500	3258.78	I
3600	3302.13	I
5000	3373.00	I
24000	3404.58	I
13000	3421.24	I
5000	3433.45	I
6400	3441.40	I
7700	3460.77	I
10000	3481.15	I
2000	3489.77	I
12000	3516.94	I
12000	3553.08	I
4500	3571.16	I
20000	3609.55	I
20000	3634.70	I
5500	3690.34	I
1400	3718.91	I
1500	3799.19	I
1500	3832.29	I
2200	3894.20	I
1500	3958.64	I
290	4087.34	I
2500	4212.95	I
180	4473.59	I
160	5163.84	I
120	5295.63	I
55	5542.80	I
75	5670.07	I
55 h	5695.09	I
65	6784.52	I
75	7368.12	I
120	7764.03	I
45	7915.80	I
55	8132.82	I
45	8300.83	I
65	8761.35	I

Phosphorus P Z = 15

250	328.78	V
150	359.899	IV
500	388.318	IV
250	389.50	V
300	390.70	V
300	445.158	IV
375	475.60	V
120	498.180	III
520	542.57	V
600	544.92	V
200	569.853	III
200	581.831	III
350	629.008	IV
400	629.914	IV
500	631.779	IV
450	673.90	V
10	810.24	II
650	823.179	IV
700	824.730	IV
800	827.932	IV
300	847.669	III
350	855.624	III
500	859.652	III
10	865.44	II
450	865.45	V
600	871.39	V
700	877.476	IV
300	913.971	III
300	917.120	III
350	918.665	III
1000	950.655	IV
250	1003.598	III
570	1025.563	IV
500	1028.096	IV
570	1030.517	IV
500	1033.111	IV
500	1035.517	IV
900	1117.98	V
570	1118.551	IV
700	1128.01	V
20	1249.82	II
20	1301.87	II
20	1304.47	II
15	1304.68	II
35	1305.48	II
60	1310.70	II
500	1334.808	III
650	1344.327	III
300	1344.845	III
500	1366.695	IV
15	1372.033	I
400	1372.674	IV
15	1373.500	I
10	1374.732	I
15	1377.080	I
15	1377.937	I
25	1379.429	I
25	1381.469	I
15	1381.637	I
500	1484.507	IV
400	1487.788	IV
350	1502.228	III
80	1532.51	II
120	1535.90	II
450	1610.50	V
150	1618.632	III
200	1618.907	III
140	1671.070	I
100	1671.510	I
180	1671.680	I
140	1672.035	I
140	1672.474	I
600	1674.591	I
600	1679.695	I
140	1685.976	I
100	1694.028	I
100	1694.486	I
100	1706.376	I
100	1707.553	I
600	1774.951	I
500	1782.838	I
400	1787.656	I
140	1834.801	I
140	1847.165	I
100	1849.820	I
140	1851.194	I
100	1852.069	I
500	1858.886	I
400	1859.393	I
140	1864.348	I
650	1888.523	IV
180	1905.481	I
140	1906.403	I
280	1907.665	I
280	2023.489	I
180	2024.516	I
400	2032.432	I
400	2033.477	I
400	2135.465	I
400	2136.182	I
400	2149.145	I
280	2152.940	I
500	2154.080	I
180	2235.732	I
450	2440.93	V
250	2478.256	IV
750	2533.976	I
950	2535.603	I
750	2553.262	I
500	2554.915	I
250	2605.506	IV
300	2632.713	III
400	2644.295	IV
400	2728.770	IV
500	2739.309	IV
250	2739.872	IV
450	2978.55	V
700	3175.09	V
520	3204.04	V
300	3219.307	III
400	3233.602	III
650	3347.736	IV
570	3364.467	IV
400	3371.122	IV
300	3957.641	III
350	3978.307	III
400	4059.312	III
300	4080.084	III
500	4222.195	III
350	4246.720	III
400	4420.71	II
250	4479.776	III
250	4540.288	IV
250	4541.112	IV
500	4588.04	II
500	4589.86	II
600	4602.08	II
300	4626.70	II
300	4658.31	II
500	4943.53	II
300	4954.39	II
300	4969.71	II
100	5079.381	I
100	5098.221	I
100	5100.974	I
140	5109.628	I
140	5154.844	I
180	5162.290	I
300	5253.52	II
140	5293.539	I
400	5296.13	II
250	5316.07	II
300	5344.75	II
180	5345.851	I
100	5364.631	I
250	5378.20	II
300	5386.88	II
400	5425.91	II
100	5428.094	I
400	5450.74	II
140	5458.305	I
180	5477.672	I
140	5477.860	I
140	5478.267	I
100	5514.774	I
100	5516.997	I
250	5588.34	II
500	6024.18	II
400	6034.04	II
500	6043.12	II
250	6055.50	II
150	6083.409	III
350	6087.82	II
180	6097.690	I
350	6165.59	II
500	6199.024	I
180	6210.499	I
140	6375.681	I

Intensity	Wavelength/Å	
100	6388.579	I
250	6435.32	II
600	6459.99	II
600	6503.46	II
600	6507.97	II
100	6717.411	I
150	6992.690	III
100	7102.200	I
100	7158.367	I
180	7165.465	I
180	7175.102	I
180	7176.660	I
200	7443.657	IV
250	7845.63	II
100	8046.801	I
150	8113.528	III
140	8278.058	I
100	8367.856	I
140	8531.475	I
140	8613.835	I
180	8637.578	I
400	8741.529	I
100	8872.174	I
180	9175.819	I
950	9193.85	I
600	9278.88	I
1250	9304.94	I
500	9323.50	I
950	9435.069	I
950	9441.86	I
600	9452.83	I
1250	9493.56	I
1700	9525.73	I
1500	9545.18	I
280	9556.81	I
1700	9563.439	I
280	9593.50	I
750	9609.04	I
400	9638.939	I
500	9676.24	I
180	9706.533	I
1500	9734.750	I
280	9736.680	I
1500	9750.77	I
600	9790.21	I
1700	9796.85	I
280	9834.80	I
400	9903.68	I
280	9976.67	I
229	10084.27	I
458	10511.58	I
962	10529.52	I
1235	10581.57	I
415	10596.90	I
435	10681.40	I
265	10813.13	I
764	11183.23	I
402	11186.75	I
479	14241.64	I
256	14307.83	I
714	15711.52	I
228	15962.53	I
296	16254.77	I
203	16292.97	I
1627	16482.92	I
588	16590.07	I
225	16613.05	I
221	16738.68	I
419	16803.39	I
471	17112.48	I
289	17286.91	I
299	17423.67	I
287	23844.97	I
311	29097.16	I

Platinum Pt Z = 78

30	1621.66	II
30	1723.13	II
30	1751.70	II
50 r	1777.09	II
30	1781.86	II
30	1879.09	II
40	1883.05	II
50	1889.52	II
50	1911.70	II
30	1929.25	II
30	1929.68	II
30	1939.80	II
30	1949.90	II
30	1983.74	II
40	2014.93	II
3200	2030.63	I
4400	2032.41	I
100	2036.46	II
40	2041.57	II
5500	2049.37	I
1500	2067.50	I
3000	2084.59	I
1000	2103.33	I
30	2115.57	II
950	2128.61	I
30	2130.69	II
1900	2144.23	I
100	2144.24	II
600	2165.17	I
1500	2174.67	I
30	2190.32	II
400	2202.22	I
50 h	2202.58	II
320	2222.61	I
50 h	2233.11	II
30 h	2240.99	II
100	2245.52	II
150	2249.30	I
30	2251.52	II
30 h	2251.92	II
190	2268.84	I
30 h	2271.72	II
280	2274.38	I
50 h	2287.50	II
30	2288.20	II
150	2289.27	I
150	2292.40	I
240	2308.04	I
50	2310.96	II
90	2315.50	I
220	2318.29	I
100	2326.10	I
170	2340.18	I
280	2357.10	I
180	2368.28	I
50	2377.28	II
130	2383.64	I
40	2386.81	I
120	2389.53	I
35	2396.17	I
70	2401.87	I
200	2403.09	I
100	2418.06	I
50	2424.87	II
80	2428.04	I
50	2428.20	I
25	2429.10	I
180	2436.69	I
650	2440.06	I
60	2450.97	I
440	2467.44	I
35	2471.01	I
1000	2487.17	I
25	2488.74	II
200	2490.12	I
160	2495.82	I
240	2498.50	I
50	2505.93	I
120	2508.50	I
50	2514.07	I
60	2515.03	I
240	2515.58	I
140	2524.30	I
40	2529.41	I
50	2536.49	I
160	2539.20	I
18	2549.46	I
50	2552.25	I
50	2596.00	I
70	2603.14	I
30	2616.76	II
50	2619.57	I
30	2625.34	II
1100	2628.03	I
130	2639.35	I
1000	2646.89	I
500	2650.86	I
20	2658.17	I
2800	2659.45	I
40	2674.57	I
440	2677.15	I
200	2698.43	I
2000	2702.40	I
1600	2705.89	I
60	2713.13	I
1300	2719.04	I
130	2729.92	I
1800	2733.96	I
70	2738.48	I
70	2747.61	I
80	2753.86	I
200	2754.92	I
30	2769.84	I
500	2771.67	I
40	2773.24	I
20	2774.00	I
50	2774.77	II
50	2793.27	I
100	2794.21	II
40 h	2799.98	II
140	2803.24	I
10	2808.51	I
50	2818.25	I
30 h	2822.27	II
1400	2830.30	I
70	2834.71	I
16	2853.11	I
80 h	2860.68	II
40 h	2865.05	II
40 h	2875.85	II
100 h	2877.52	II
25	2888.20	I
25	2893.22	I
600	2893.86	I
300	2897.87	I
60	2905.90	I
120	2912.26	I
120	2913.54	I
70	2919.34	I
30	2921.38	I
1700	2929.79	I
30	2942.76	I
30	2944.75	I
25	2959.10	I
60	2960.75	I
1800	2997.97	I
35	3001.17	II
220	3002.27	I
30	3017.88	I
30 h	3031.22	II
130	3036.45	I
800	3042.64	I
3200	3064.71	I
30	3071.94	I
130	3100.04	I
320	3139.39	I
140	3156.56	I
120	3200.71	I
320	3204.04	I
30	3230.29	I
20	3233.42	I
20	3250.36	I
40	3251.98	I
160	3255.92	I
25	3268.42	I
25	3281.97	I
120	3290.22	I
500	3301.86	I
60	3315.05	I

Intensity	Wavelength/Å	
35	3323.80	I
340	3408.13	I
35	3427.93	I
60	3483.43	I
160	3485.27	I
120	3628.11	I
70	3638.79	I
70	3643.17	I
50	3663.10	I
80	3671.99	I
80	3674.04	I
35	3699.91	I
18	3706.53	I
80	3818.69	I
40	3900.73	I
110	3922.96	I
35	3948.40	I
100	3966.36	I
20	3996.57	I
110	4118.69	I
80	4164.56	I
40	4192.43	I
18	4327.06	I
18	4391.83	I
80	4442.55	I
14	4445.55	I
25	4498.76	I
12	4520.90	I
35	4552.42	I
12	4879.53	I
14	5044.04	I
30	5059.48	I
35	5227.66	I
40	5301.02	I
12	5368.99	I
12	5390.79	I
14	5475.77	I
14	5478.50	I
6	5763.57	I
20	5840.12	I
8	5844.84	I
6	6026.04	I
7	6318.37	I
8	6326.58	I
9	6523.45	I
10	6710.42	I
20	6760.02	I
60	6842.60	I
20	7113.73	I
10	8224.74	I

Plutonium Pu Z = 94

10000	2806.11	II
10000	2950.06	II
10000	3000.31	II
10000	3200.23	II
10000	3418.88	II
10000	3805.93	I
10000	4097.12	I
10000	4170.95	I
10000	4367.41	I
10000	5590.54	I

Intensity	Wavelength/Å	
10000	7068.90	I
10000	8691.94	I
3000	9533.07	I
3000	12144.46	I
3000	16897.38	I

Polonium Po Z = 84

1500 w	2450.08	I
1500 w	2558.01	I
2500 w	3003.21	I
1200	4170.52	I
800	4493.21	I
500	8618.26	I

Potassium K Z = 19

100	214.35	V
150	271.82	IV
100	273.06	IV
150	282.35	V
150	293.33	V
300	294.84	V
200	296.17	V
200	297.06	V
200	300.25	V
200	300.50	V
200	311.24	V
250	312.77	V
200	315.18	V
250	327.38	V
25	330.68	III
300	340.46	IV
150	340.74	IV
30	341.92	III
15	348.00	III
200	349.50	V
300	354.93	IV
150	356.26	IV
300	359.73	IV
200	359.91	IV
250	362.08	IV
150	362.15	IV
150	363.02	IV
500	372.15	V
200	372.46	V
200	372.77	V
300	375.96	IV
300	375.96	V
250	377.76	V
30	379.12	III
300	379.12	V
300	379.88	IV
25	380.48	III
250	380.48	IV
200	381.70	IV
30	382.23	III
300	382.23	IV
150	382.49	IV
200	382.65	IV
300	382.91	IV
250	384.10	IV
200	386.61	IV
300	387.80	V

Intensity	Wavelength/Å	
250	388.92	IV
250	389.07	IV
250	389.07	V
250	390.11	V
250	390.42	IV
300	390.57	IV
200	391.46	IV
200	392.47	IV
500	393.14	IV
250	395.40	V
200	398.36	V
15	398.63	III
200	398.88	V
200	399.75	V
400	400.21	IV
20	402.10	III
300	402.91	IV
250	403.97	IV
150	404.41	IV
30	406.48	III
250	408.08	IV
40	408.96	III
50	413.79	III
30	414.87	III
250	415.05	V
200	415.79	V
30	416.00	III
150	417.28	IV
30	417.54	III
30	418.62	III
400	422.18	V
300	425.16	V
500	425.59	V
75	434.72	III
50	435.68	III
250	438.02	V
25	441.81	II
200	442.30	IV
300	443.57	IV
75	444.34	III
200	445.61	IV
250	446.83	IV
75	448.60	III
750	448.60	IV
200	449.71	V
200	452.90	V
250	455.67	V
400	456.33	IV
400	456.33	V
75	466.79	III
100	470.09	III
75	471.57	III
45	474.92	III
10	476.03	II
40	479.18	III
10	482.11	III
10	482.41	III
200	482.71	V
200	483.75	V
30	495.14	II
75	497.10	III

Intensity	Wavelength/Å	
10	514.94	III
50	520.61	III
250	523.00	IV
25	523.79	III
200	526.45	IV
150	527.62	IV
40	529.80	III
15	539.71	III
15	546.12	III
750	580.32	V
250	585.51	V
500	586.32	V
30	600.77	II
250	602.27	V
400	603.43	V
25	607.93	II
30	612.62	II
250	638.67	V
750	646.19	IV
300	687.50	V
20	708.84	III
300	720.43	V
400	724.42	V
600	731.86	V
500	737.14	IV
500	741.95	IV
500	745.26	IV
400	746.35	IV
300	749.99	IV
150	754.19	IV
400	754.67	IV
20	765.31	III
30	765.64	III
150	770.29	V
150	771.46	V
35	778.53	III
20	872.31	III
10	873.86	III
15	874.04	III
6	2550.02	III
5	2635.11	III
5	2689.90	III
5	2938.45	III
5	2986.20	III
6	2992.42	III
6	3052.07	III
5	3056.84	III
5	3062.18	II
4	3101.79	I
3	3102.04	I
7	3217.16	I
6	3217.62	I
11	3446.37	I
10	3447.38	I
3	3648.84	I
4	3648.98	I
18	4044.14	I
17	4047.21	I
10	4641.88	I
11	4642.37	I

Intensity	Wavelength/Å	
4	4740.91	I
6	4744.35	I
5	4753.93	I
7	4757.39	I
5	4786.49	I
7	4791.05	I
6	4799.75	I
8	4804.35	I
7	4849.86	I
8	4856.09	I
8	4863.48	I
9	4869.76	I
8	4942.02	I
9	4950.82	I
9	4956.15	I
10	4965.03	I
10	5084.23	I
11	5097.17	I
11	5099.20	I
12	5112.25	I
12	5323.28	I
13	5339.69	I
12	5342.97	I
14	5359.57	I
16	5782.38	I
17	5801.75	I
15	5812.15	I
17	5831.89	I
8	6120.27	II
7	6307.29	II
19	6911.08	I
12	6936.28	I
20	6938.77	I
7	6964.18	I
12	6964.67	I
25	7664.90	I
24	7698.96	I
5	7955.37	I
4	7956.83	I
7	8078.11	I
6	8079.62	I
9	8250.18	I
8	8251.74	I
3	8390.22	I
11	8503.45	I
10	8505.11	I
4	8763.96	I
3	8767.05	I
13	8902.19	I
12	8904.02	I
5	8923.31	I
4	8925.44	I
7	9347.24	I
3	9349.25	I
6	9351.59	I
15	9595.70	I
14	9597.83	I
6	9949.67	I
5	9954.14	I
9	10479.63	I
5	10482.15	I
8	10487.11	I
17	11019.87	I
16	11022.67	I
17	11690.21	I
16	11769.62	I
17	11772.83	I
	12522.11	I
	13377.86	I
	13397.09	I
	15163.08	I
	15168.40	I
	40158.37	I

Praseodymium Pr Z = 59

7000	865.90	V
5000	869.17	V
2000	1228.59	IV
5000	1293.22	IV
5000	1295.28	IV
5000	1321.36	IV
5000	1333.57	IV
5000	1354.66	IV
2000	1360.64	IV
2000	1365.77	IV
5000	1374.41	IV
5000	1435.56	IV
2000	1520.98	IV
5000	1574.55	IV
5000	1575.10	IV
3000	1578.38	IV
2000	1622.30	IV
10000	1884.87	IV
2000	2083.23	IV
3300	2246.20	V
2000 c	2378.98	IV
40 h	2598.04	II
100 h	2707.37	II
60	2760.35	II
270	3168.24	II
200 d	3195.99	II
190	3219.48	II
200	3584.21	II
250	3645.66	II
250	3646.30	II
370	3668.83	II
290	3714.05	II
410	3739.18	II
680	3761.87	II
680	3800.30	II
390	3811.84	II
1300 h	3816.02	II
680	3818.28	II
310	3821.80	II
960	3830.72	II
480	3840.99	II
580	3846.59	II
1200	3850.79	II
720 c	3851.55	II
960	3852.80	II
480 c	3865.45	II
480	3876.19	II
1700 c	3877.18	II
680	3880.47	II
440 c	3885.19	II
440 c	3889.34	II
770 c	3908.05	II
630	3912.90	II
310	3913.55	II
1300 c	3918.85	II
420	3919.63	II
960	3925.47	II
480	3927.46	II
370	3929.29	II
370	3935.82	II
730 c	3947.63	II
900 c	3949.43	II
900 c	3953.51	II
380	3956.75	II
470	3962.45	II
560	3964.26	II
1600 c	3964.81	II
560 c	3966.57	II
500	3971.16	II
320	3971.67	II
620 c	3972.14	II
320	3974.85	II
1300 c	3989.68	II
340	3992.16	II
1600	3994.79	II
560 c	3997.04	II
320	3999.12	II
620 c	4000.17	II
730	4004.70	II
1900	4008.69	II
620	4010.60	II
730	4015.39	II
620	4020.96	II
470	4022.71	II
360	4025.54	II
360 c	4029.72	II
730 c	4031.75	II
960	4033.83	II
730	4038.45	II
470	4039.34	II
1300	4044.81	II
340	4047.08	II
450	4051.13	II
2200	4054.88	II
2200	4056.54	II
450	4058.80	II
3400	4062.81	II
500 c	4079.77	II
500 c	4080.98	II
790	4081.85	II
500	4083.34	II
560	4096.82	II
380	4098.40	II
2900 c	4100.72	II
1700 c	4118.46	II
340	4130.77	II
1500 c	4141.22	II
2700	4143.11	II
1700 c	4164.16	II
620	4171.82	II
730	4172.25	II
5200	4179.39	II
2500	4189.48	II
560 c	4191.60	II
2500 c	4206.72	II
500	4208.32	II
320	4211.86	II
320	4217.81	II
3800	4222.93	II
3800	4225.35	II
320	4233.11	II
320 c	4236.15	II
960	4241.01	II
340	4243.51	II
840 c	4247.63	II
500	4254.40	II
320	4269.09	II
790 c	4272.27	II
470 c	4280.07	II
790 c	4282.42	II
450 c	4298.98	II
1500	4305.76	II
1300	4333.97	II
360	4338.70	II
620 cw	4344.30	II
470 c	4347.49	II
340	4350.40	II
450	4354.91	II
410 c	4359.79	II
1200	4368.33	II
320	4371.62	II
430	4405.83	II
1700	4408.82	II
410	4413.77	II
1200 c	4429.13	II
730	4449.83	II
960	4468.66	II
1100	4496.46	II
790	4510.15	II
340 c	4534.15	II
340	4535.92	II
270 c	4628.74	II
270 c	4672.09	II
290	4695.77	I
250	4736.69	I
200	4924.60	I
320	4939.74	I
380	4951.37	I
270	5034.41	II
320	5045.52	I
360	5110.38	II
560	5110.76	II
410	5129.52	II
620	5173.90	II
360	5206.55	II
360	5219.05	II
560	5220.11	II
680	5259.73	II
340 c	5292.02	II
340	5292.62	II

Intensity	Wavelength/Å	
430	5322.76	II
65	5509.15	II
150	5535.17	II
110	5623.05	II
90	5624.45	II
90	5756.17	II
90	5779.28	I
160 d	5815.17	II
90	5823.72	II
90	5859.68	II
160	5939.90	II
7000 w	5956.05	III
90	5956.60	II
110	5967.82	II
90	6006.33	II
150	6017.80	II
150	6025.72	II
140	6055.13	I
65	6087.52	II
9000 w	6090.02	III
65	6114.38	II
65	6148.23	I
5000	6160.24	III
190	6161.18	II
270	6165.94	II
45	6244.35	II
110	6281.28	II
55 c	6359.03	I
55	6411.23	I
45	6429.63	II
45	6431.84	II
45	6486.55	I
45	6566.77	II
55	6616.67	I
75	6656.83	II
55	6673.41	II
75	6673.78	II
35 c	6747.09	I
55 cw	6798.60	I
35 cw	6827.60	II
7000	6910.14	III
40	7021.51	II
5000	7030.39	III
4500	7076.62	III
20	7114.55	I
24	7227.70	II
16	7407.56	II
20 c	7451.74	II
14	7541.02	II
20	7645.66	II
16	7721.84	I
14	7871.67	I
14	8067.44	I
10 cw	8122.78	II
11	8141.10	I
5000 w	8602.74	III
10	8714.59	II

Promethium Pm Z = 61

1000	3892.15	II
1000	3910.26	II
1000	3919.10	II
1000	3957.74	II
1000 r	3998.96	II
1000	4417.96	II
900 r	4728.36	I
900	6100.21	I
1000 d	6520.45	I

Protactinium Pa Z = 91

3000	2599.16	II
3000	2699.22	II
3000	2822.79	II
3000 h	2871.42	II
3000 h	2891.14	II
3000 l	3011.10	II
3000 s	3033.59	II
3000 l	3071.24	II
3000 l	3093.23	II
3000 l	3126.23	II
3000 l	3146.28	II
3000 l	3170.89	II
3000 l	3171.54	II
3000 l	3240.58	II
3000	3274.46	II
3000 l	3332.69	II
3000 s	3346.66	II
3000 l	3452.82	II
3000	3504.97	I
3000 s	3530.65	II
3000	3570.56	I
3000	3571.82	I
3000	3618.07	I
10000	3636.52	I
3000	3702.74	I
3000	3752.67	I
3000	3873.35	I
3000	3931.83	I
3000 s	3952.62	II
10000 l	3957.85	II
3000 s	3970.07	II
3000	3981.82	I
10000	3982.23	I
3000 l	4012.96	II
3000 s	4018.21	II
3000	4030.16	II
3000 s	4046.93	II
10000 s	4056.20	II
10000 s	4070.40	II
3000 l	4176.18	II
10000 l	4217.23	II
10000 s	4248.08	II
3000 s	4291.34	II
3000 s	4601.43	II
3000 l	6035.78	I
3000	6162.56	I
3000 l	6358.61	I
3000	6379.25	I
3000 l	6438.97	I
3000 h	6792.75	I
10000	6945.72	I
3000	6960.09	I
3000 h	6961.78	I
3000 s	6992.73	I
3000	7076.27	I
3000 h	7100.94	I
10000 s	7114.89	I
3000 h	7171.55	I
3000	7227.13	I
3000	7318.79	I
10000 l	7368.25	I
3000 h	7471.89	I
10000 h	7493.15	I
3000 h	7558.26	I
10000 h	7608.20	I
10000	7626.79	I
10000 s	7635.18	I
10000	7669.34	I
3000	7679.20	I
10000 h	7749.19	I
3000	7872.95	I
3000 l	7945.56	I
10000	8039.34	I
10000 h	8099.84	I
10000	8199.04	I
10000	8271.87	I
3000 s	8358.98	I
3000 s	8369.60	I
3000 h	8441.04	I
10000 h	8532.66	I
10000 s	8572.96	I
3000 h	8639.91	I
3000 h	8653.51	I
10000	8735.27	I
3000	10923.32	I
10000	11791.73	I
10000	14344.76	I
3000	18478.61	I

Radium Ra Z = 88

100	3649.55	II
200	3814.42	II
100	4340.64	II
100	4682.28	II
100	4825.91	I
50	5660.81	I
50	7141.21	I
50	8019.70	II

Radon Rn Z = 86

100	4349.60	I
200	7055.42	I
100	7268.11	I
300	7450.00	I
100	7809.82	I
100	8099.51	I
100	8270.96	I
100	8600.07	I

Rhenium Re Z = 75

25000	2003.53	I
16000	2017.87	I
27000	2049.08	I
10000	2085.59	I
9800	2097.12	I
3400	2139.04	II
3700	2156.67	I
4900	2167.94	I
3400	2176.21	I
4200 c	2214.26	II
5200 c	2275.25	II
2900	2287.51	I
2700	2294.49	I
390	2298.09	II
610	2302.99	I
680	2306.54	I
800	2322.49	I
300	2328.66	I
860	2344.78	I
230	2349.39	I
680	2352.07	I
250	2356.50	I
1200	2365.90	I
570	2367.68	I
520	2369.27	I
220	2370.76	II
320	2375.07	I
370	2379.77	I
340	2388.57	I
230	2393.65	I
320	2394.37	I
320	2396.79	I
210 d	2400.72	I
210	2401.68	I
1500	2405.06	I
740	2405.60	I
320	2406.70	I
270	2410.37	I
1200	2419.81	I
300	2421.73	I
300	2421.88	I
2500	2428.58	I
490	2431.54	I
420	2432.18	I
340 c	2441.47	I
230	2442.51	I
250	2444.94	I
610	2446.98	I
610	2449.71	I
390	2461.20	I
800 c	2461.84	II
1200	2483.92	I
390	2485.81	I
980	2487.33	I
370	2496.04	I
370	2501.72	I
570	2502.35	II
230	2504.60	II
270	2505.94	I
1800 c	2508.99	I
570	2520.01	I
540	2521.50	I
370	2534.80	I
570	2540.51	I
740 d	2544.74	I
370	2545.48	I
300	2552.02	I
370	2554.63	II

Intensity	Wavelength/Å	
1000	2556.51	I
250	2559.08	I
340	2564.19	I
540	2568.64	II
370	2571.81	II
380	2586.79	I
290	2599.86	I
290	2603.89	I
660	2608.50	II
610 d	2611.54	I
310	2635.83	II
550	2636.64	I
270	2642.75	I
270	2649.05	I
660	2651.90	I
400	2654.12	I
220	2663.63	I
940	2674.34	I
220	2688.53	I
1300	2715.47	I
220	2732.21	I
610	2733.04	II
220	2758.00	I
210	2763.79	I
310	2767.74	I
220	2768.85	I
220	2769.32	I
350	2770.42	I
550	2783.57	I
220	2791.29	I
220	2814.68	I
880	2819.95	I
310	2834.08	I
220	2843.00	I
270	2850.98	I
240	2867.19	I
2900	2887.68	I
490	2896.01	I
830 c	2902.48	I
210	2905.58	I
550	2909.82	I
830 c	2927.42	I
270	2930.61	I
440	2943.14	I
270	2962.27	I
720	2965.11	I
1500	2965.76	I
310	2976.29	I
210	2978.15	I
220	2980.82	I
220	2982.19	I
220	2988.47	I
1800	2992.36	I
5500	2999.60	I
350	3001.14	I
220	3004.14	I
500	3016.02	I
300	3016.49	I
380	3030.45	I
240	3047.25	I
1600	3067.40	I

Intensity	Wavelength/Å	
320	3069.94	I
260	3071.16	I
550	3082.43	I
340	3088.76	I
700	3100.67	I
700	3108.81	I
340	3110.86	I
340 c	3118.19	I
340	3121.36	I
420	3128.94	I
260	3134.02	I
250	3141.38	I
440	3151.64	I
330	3153.79	I
360 c	3158.31	I
220	3164.52	I
700	3168.37	I
220	3174.61	I
440	3177.71	I
260	3178.61	I
600	3182.87	I
1100	3184.76	I
1100	3185.57	I
260	3190.78	I
260	3192.36	I
220	3198.58	I
1100 c	3204.25	I
380	3235.94	I
600	3258.85	I
600	3259.55	I
300	3268.89	I
280	3296.70	I
280	3296.99	I
280	3301.60	I
240	3302.23	I
320	3303.21	II
280	3303.75	I
240	3313.95	I
600	3322.48	I
2000	3338.18	I
1600	3342.24	I
810	3344.32	I
320	3346.20	I
240 d	3356.33	I
240	3377.74	I
320	3379.06	II
320	3379.70	I
240	3389.43	I
4000	3399.30	I
650	3404.72	I
650	3405.89	I
240	3408.67	I
320	3409.83	I
320	3417.77	I
810	3419.41	I
8000	3424.62	I
400	3426.19	I
300	3427.61	I
320	3437.71	I
400	3449.37	I
16000 c	3451.88	I

Intensity	Wavelength/Å	
240	3453.50	I
55000 c	3460.46	I
40000 c	3464.73	I
400	3467.96	I
240	3476.44	I
400	3480.38	I
320	3480.85	I
240	3482.23	I
560	3503.06	I
320	3516.65	I
320	3517.33	I
320	3537.46	I
240	3549.89	I
240	3570.26	I
360	3579.12	I
810 c	3580.15	II
650	3580.97	I
810	3583.02	I
320	3617.08	I
810	3637.84	I
440	3651.97	I
320	3670.53	I
860 c	3689.50	I
1500 c	3691.48	I
520	3703.24	I
240	3709.93	I
360 c	3717.28	I
4000	3725.76	I
240 c	3735.01	I
810	3735.31	I
910	3740.10	I
300 cw	3745.44	I
700	3787.52	I
240	3869.94	I
240	3875.26	I
240	3876.86	I
380 c	3917.27	I
550	3929.85	I
280	3961.04	I
350 c	3962.48	I
220	4033.31	I
240	4081.43	I
240 c	4110.89	I
240 cw	4133.42	I
1800	4136.45	I
700	4144.36	I
220	4182.90	I
220	4183.06	I
650	4221.08	I
3600 c	4227.46	I
260 c	4257.60	I
380	4358.69	I
360 cw	4394.38	I
2600	4513.31	I
260	4516.64	I
500	4522.73	I
2200 cw	4889.14	I
220	4923.90	I
1300	5270.95	I
1600 cw	5275.56	I
100	5667.88	I

Intensity	Wavelength/Å	
110 c	5752.93	I
110 cw	5776.83	I
550	5834.31	I
200	6307.70	I
200	6321.90	I
100 cw	6605.19	I
180 c	6813.41	I
260	6829.90	I
50 cw	7640.94	I
65 cw	7912.94	I
Rhodium Rh Z = 45		
50	813.44	III
80	882.51	III
100	925.75	III
150	937.28	III
500	991.62	III
400	992.48	III
500 d	1009.60	III
200	1012.22	III
200	1015.17	III
200	1073.87	III
150	1784.24	III
200	1784.94	III
150	1796.50	III
200	1816.03	III
1000	1832.05	III
500	1859.85	III
800	1880.66	III
500	1884.91	III
500	1887.36	III
700	1888.62	III
800	1901.32	III
500	1910.16	III
600	1919.37	III
500	1927.07	III
700	1931.79	III
500	1954.25	III
500	1994.26	III
800	2013.71	III
500	2017.47	III
500	2028.53	III
800	2036.72	III
600	2037.61	III
1000	2040.18	III
3000	2048.67	III
2000	2064.11	III
800	2076.84	III
1000	2118.53	III
1000	2118.63	III
1000	2139.44	III
1000	2152.23	III
3000	2158.17	III
3000	2163.19	III
3000	2167.33	III
150	2276.21	II
140	2288.57	I
110	2309.82	I
350	2322.58	I
140	2326.47	I
190	2334.77	II
300	2361.92	I

Intensity	Wavelength/Å	
110	2368.34	I
270	2382.89	I
230	2383.40	I
270	2386.14	II
80	2415.84	II
130	2427.68	I
230	2429.52	I
110	2437.90	I
330	2440.34	I
90	2461.04	II
130	2473.09	I
150	2487.47	I
100	2490.77	II
130	2502.46	I
300	2504.29	II
150	2505.67	I
350	2509.70	I
300	2511.03	II
200	2515.75	I
130	2520.53	II
110	2537.04	II
350	2545.70	I
550	2555.36	I
150	2622.58	I
230	2625.88	I
100	2630.42	I
110	2647.28	I
400	2652.66	I
100	2680.63	I
400	2703.73	I
100	2715.31	II
180	2718.54	I
160	2728.94	I
100	2771.51	I
130	2783.03	I
150	2826.43	I
180	2826.68	I
280	2862.94	I
110	2878.66	I
140	2882.37	I
160	2907.21	I
65	2910.17	II
180	2924.02	I
130	2929.11	I
130	2931.94	I
230	2968.66	I
160	2977.68	I
450	2986.20	I
110	3004.46	I
50	3006.43	III
130	3023.91	I
50	3052.44	III
180	3083.96	I
140	3121.76	I
240	3123.70	I
130	3155.78	I
140	3189.05	I
470	3191.19	I
190	3197.13	I
520	3263.14	I
520	3271.61	I
2300	3280.55	I
2300	3283.57	I
280	3289.14	I
210	3294.28	I
260	3300.46	I
50	3310.69	III
4200	3323.09	I
330	3338.54	I
280	3360.80	I
420	3368.38	I
1100	3372.25	I
110	3377.14	I
110	3385.78	I
5600	3396.82	I
820	3399.70	I
160	3406.55	I
820	3412.27	I
330	3421.22	I
120 d	3424.38	I
8200	3434.89	I
1400	3440.53	I
120	3447.74	I
120	3450.29	I
400	3455.22	I
180	3457.07	I
220	3457.93	I
5900	3462.04	I
180	3469.62	I
4700	3470.66	I
120	3472.25	I
4700	3474.78	I
2100	3478.91	I
110	3494.44	I
1200	3498.73	I
5900	3502.52	I
2800	3507.32	I
8800	3528.02	I
880 d	3538.14	I
280	3541.91	I
1200	3543.95	I
1800	3549.54	I
1200	3570.18	I
4700	3583.10	I
4700	3596.19	I
5900	3597.15	I
3100	3612.47	I
1800	3626.59	I
8200	3657.99	I
1300	3666.22	I
560	3681.04	I
1900	3690.70	I
9400	3692.36	I
940	3695.52	I
280	3698.26	I
380	3698.60	I
7600	3700.91	I
940	3713.02	I
650	3735.28	I
420	3737.27	I
420	3744.17	I
1200	3748.22	I
240	3754.12	I
380	3754.27	I
490	3755.58	I
1000	3760.40	I
2300	3765.08	I
490	3769.97	I
380	3778.13	I
1000	3788.47	I
1300	3792.18	I
3800	3793.22	I
4900	3799.31	I
760	3805.92	I
1300	3806.76	I
470	3815.01	I
760	3816.47	I
1300	3818.19	I
3800	3822.26	I
2300	3828.48	I
2000	3833.89	I
5900	3856.52	I
490	3870.01	I
380	3877.34	I
120	3913.51	I
240	3922.19	I
2000	3934.23	I
590	3942.72	I
3800	3958.86	I
45	3964.54	II
380	3975.31	I
240	3984.40	I
240	3995.61	I
380	3996.15	I
120	4023.14	I
560	4082.78	I
140	4097.52	I
120	4119.68	I
1100	4121.68	I
1500	4128.87	I
2100	4135.27	I
240	4154.37	I
330	4196.50	I
3300	4211.14	I
820	4288.71	I
4200	4374.80	I
130	4569.00	I
150	4675.03	I
70	4745.11	I
70	5090.63	I
60	5155.54	I
60	5175.97	I
95	5193.14	I
130	5354.40	I
95	5390.44	I
160	5599.42	I
40	5686.38	I
29	5792.66	I
40	5806.91	I
35	5831.58	I
130	5983.60	I
35	6102.72	I
14	6199.99	I
16	6253.72	I
29	6319.53	I
40	6752.35	I
13	6827.33	I
11	6857.68	I
20	6879.94	I
65	6965.67	I
16	6979.15	I
16	7001.58	I
18	7101.64	I
15	7104.45	I
18	7268.18	I
35	7270.82	I
18 h	7442.39	I
12	7475.74	I
12	7495.24	I
11	7557.67	I
29	7791.61	I
55	7824.91	I
21	8029.91	I
29	8045.36	I
15	8136.20	I
8	8425.59	I

Rubidium Rb Z = 37

30	465.85	III
40	481.118	II
500	482.83	III
500	489.66	III
600	493.48	III
90	497.430	II
20	508.434	II
150	513.266	II
300	530.173	II
75	533.801	II
1200	535.86	III
40	542.887	II
200	555.036	II
1200	556.19	III
1500	566.71	III
1000	572.82	III
1500	576.65	III
2500	579.63	III
1500	581.26	III
2500	589.419	II
1000	594.94	III
1300	595.88	III
1200	598.49	III
1500	643.878	II
25	663.76	IV
3000	697.049	II
6000	711.187	II
25	716.24	IV
50	740.85	IV
10000	741.456	II
5000	769.04	III
25	776.89	IV
2500	815.28	III
15	850.18	IV
1000	1604.12	II
5000	1760.50	II
2000	2068.92	II

Intensity	Wavelength/Å	
10000	2075.95	II
30000	2143.83	II
10000	2217.08	II
5000	2291.71	II
50000	2472.20	II
1000	2631.75	III
2000	2956.07	III
500	3086.84	III
500	3111.36	III
5000 c	3148.90	II
25	3157.54	I
50	3227.98	I
500	3286.41	III
60	3348.72	I
75	3350.82	I
100	3587.05	I
40	3591.57	I
5000	3600.60	II
10000	3600.64	II
25000	3940.51	II
1000	4201.80	I
500	4215.53	I
90000	4244.40	II
15000	4273.14	II
20000	4571.77	II
10000	4648.57	II
30000	4775.95	II
2	5087.987	I
2	5132.471	I
10	5150.134	I
10000	5152.08	II
1	5165.023	I
2	5165.142	I
15	5195.278	I
2	5233.968	I
20	5260.034	I
1	5260.228	I
3	5322.380	I
40	5362.601	I
4	5390.568	I
75	5431.532	I
3	5431.830	I
6	5578.788	I
40	5647.774	I
20	5653.750	I
60	5724.121	I
3	5724.614	I
75	6070.755	I
30 c	6159.626	I
75 c	6206.309	I
120 c	6298.325	I
5	6299.224	I
10000	6458.33	II
5000	6560.81	II
100 l	7279.997	I
150	7408.173	I
200 l	7618.933	I
300	7757.651	I
60	7759.436	I
90000 c	7800.27	I
45000 c	7947.60	I
40 l	8271.41	I
30	8271.71	I
40 l	8868.512	I
30	8868.852	I
30 l	9522.65	I
20 l	9540.18	I
2000 c	9689.05	II
35 l	10075.282	I
30 l	10075.708	I
100	13235.17	I
20	13442.81	I
30	13443.57	I
75	13665.01	I
1000	14752.41	I
800	15288.43	I
150	15289.48	I
20	22529.65	I
4	27314.31	I

Ruthenium Ru Z = 44

250	850.09	III
200	850.30	III
250	919.74	III
500	940.09	III
500	966.54	III
750	974.14	III
900	979.43	III
500	981.35	III
900	986.84	III
900	994.56	III
300	1001.65	III
500	1009.13	III
900	1009.87	III
500	1014.68	III
800	1190.51	III
500	1200.07	III
500	1207.17	III
500	1209.77	III
300	1211.31	III
500	1941.35	III
500	2009.28	III
2400	2076.43	I
2600	2083.77	I
2400	2090.89	I
690	2255.52	I
780	2272.09	I
780	2279.57	I
480	2317.80	I
120	2334.96	II
190 h	2342.85	II
310	2351.33	I
170	2357.91	II
780	2402.72	II
150	2407.92	II
180	2455.53	II
150	2456.44	II
370	2456.57	II
280	2478.93	II
140	2498.42	II
140	2498.57	II
260	2507.01	II
110	2513.32	II
110	2517.32	II
150	2535.59	II
550	2549.58	I
370	2609.06	I
830	2612.07	I
460	2642.96	I
330	2651.84	I
400	2659.62	I
330	2661.61	II
690	2678.76	II
330	2692.06	II
200	2712.41	II
690	2719.52	I
140	2725.47	II
310	2734.35	II
1800	2735.72	I
100	2778.38	II
110	2787.83	II
350	2810.03	I
1700	2810.55	I
350	2818.36	I
400	2829.16	I
640	2854.07	I
420	2861.41	I
550	2866.64	I
1800	2874.98	I
740	2886.54	I
370	2908.88	I
1100	2916.26	I
180	2945.67	II
370	2949.50	I
550	2965.16	I
170	2965.55	II
140	2976.59	II
550	2976.92	I
1400	2988.95	I
460	2994.96	I
440	3006.59	I
330	3017.24	I
310	3020.88	I
390	3064.84	I
330	3096.57	I
830	3099.28	I
740	3100.84	I
490	3294.11	I
370	3301.59	I
930	3339.55	I
3100	3417.35	I
4900	3428.31	I
6400	3436.74	I
8300	3498.94	I
640	3514.49	I
790	3539.37	I
690	3570.59	I
6400	3589.22	I
6900	3593.02	I
6400	3596.18	I
1300	3599.76	I
3100	3634.93	I
6200	3661.35	I
830	3663.37	I
650	3669.49	I
550	3726.10	I
8700	3726.93	I
11000	3728.03	I
7100	3730.43	I
3500	3742.28	I
870	3742.78	I
2800	3745.59	I
760	3753.54	I
870	3755.93	I
1200	3759.84	I
600	3761.51	I
600	3767.35	I
1500	3777.59	I
600	3782.74	I
3900	3786.06	I
6000	3790.51	I
760	3798.05	I
7600	3798.90	I
7600	3799.35	I
600	3812.72	I
760	3817.27	I
760	3819.03	I
650	3822.09	I
550	3824.93	I
760	3831.80	I
930	3839.70	I
760	3850.43	I
1300	3857.55	I
650	3862.69	I
1300	3867.84	I
650	3892.21	I
760	3909.08	I
1500	3923.47	I
3300	3925.92	I
600	3931.76	I
760	3945.57	I
600	3978.44	I
600	3979.42	I
870	3984.86	I
1500	4022.16	I
600	4023.83	I
1400	4051.40	I
710	4054.05	I
760	4068.37	I
980	4076.73	I
6000	4080.60	I
930	4097.79	I
1900	4112.74	I
2000	4144.16	I
650	4145.74	I
870	4167.51	I
550	4197.58	I
550	4198.88	I
7600	4199.90	I
1500	4206.02	I
5400	4212.06	I
760	4214.44	I
930	4217.27	I
550	4230.31	I
760	4241.05	I

Intensity	Wavelength/Å	
760	4243.06	I
760	4284.33	I
550	4295.93	I
3700	4297.71	I
930	4307.60	I
550	4319.87	I
550	4342.07	I
710	4354.13	I
870	4361.21	I
2400	4372.21	I
870	4385.39	I
1300	4385.65	I
1700	4390.44	I
1600	4410.03	I
1100	4460.04	I
5400	4554.51	I
1700	4584.44	I
720	4647.61	I
1400	4709.48	I
500	4757.84	I
550	4869.15	I
160	5011.23	I
450	5057.33	I
120	5076.32	I
200	5093.83	I
530	5136.55	I
170	5142.76	I
250	5147.24	I
110	5151.07	I
500	5155.14	I
920	5171.03	I
180	5195.02	I
130	5284.08	I
260	5309.27	I
110	5335.93	I
130	5361.77	I
110 h	5401.04	I
80	5484.32	I
130	5510.71	I
90	5559.75	I
290	5636.24	I
180	5699.05	I
65	5814.98	I
55	5919.34	I
80	5921.45	I
21 h	5973.38	I
16	5988.67	I
35	5993.65	I
18	6116.77	I
26	6199.42	I
26	6225.20	I
18	6295.22	I
16	6390.23	I
26 h	6444.84	I
21	6663.14	I
55	6690.00	I
21	6766.95	I
30	6775.02	I
21	6824.17	I
26	6911.48	I
110	6923.23	I
26	6982.01	I
26	7027.98	I
35	7238.92	I
16	7393.93	I
18	7468.91	I
26	7485.79	I
70	7499.75	I
26	7559.61	I
18	7621.50	I
18	7722.87	I
22	7791.86	I
30	7847.80	I
80	7881.49	I
18	8264.96	I
22	8710.84	I

Samarium Sm Z = 62

150	2789.38	II
410	3152.52	II
720	3183.92	II
600	3211.73	II
530	3216.85	II
600	3218.61	II
720	3230.56	II
720	3236.64	II
720	3239.66	II
720	3250.37	II
850	3254.38	II
1700	3306.39	II
1200	3321.18	II
1200	3365.86	II
1200	3382.40	II
4200	3568.27	II
4200	3592.60	II
1700	3604.28	II
3400	3609.49	II
1700	3621.23	II
3400	3634.29	II
2200	3661.36	II
2200	3670.84	II
1100	3693.99	II
1600	3728.47	II
2100	3731.26	II
1600	3735.98	II
2900	3739.12	II
1200	3743.87	II
930	3745.46	I
800	3756.41	I
1200	3757.53	II
1900	3760.69	II
1100	3764.37	II
370 d	3773.33	I
1100	3778.14	II
1500	3788.12	II
1600	3793.97	II
1600	3797.73	II
1600	3826.20	II
1100	3831.50	II
560	3834.48	I
1600	3843.50	II
530	3853.30	I
2700	3854.21	II
480	3854.56	I
400	3858.74	I
3700	3885.29	II
1600	3896.98	II
1300	3903.42	II
2500	3922.40	II
1900	3928.28	II
1300	3941.87	II
470	3951.89	I
1500	3963.00	II
1500	3971.40	II
620	3974.66	I
1000	3976.43	II
1500	3990.00	II
1400	4064.58	II
1000	4092.27	II
1900	4118.55	II
1200	4152.21	II
1000	4188.13	II
1100	4203.05	II
1000	4225.33	II
1200	4236.74	II
2100	4256.39	II
1300	4262.68	II
1200	4279.68	II
2200	4280.79	II
710	4282.21	I
470	4282.83	I
1600	4296.74	I
1900	4318.94	II
470	4319.53	I
1800	4329.02	II
440	4330.02	I
1300	4334.15	II
880	4336.14	I
1100	4347.80	II
440	4362.91	I
530	4380.42	I
1600	4390.86	II
410	4401.17	I
470	4419.33	I
1500	4420.53	II
2900	4424.34	II
470	4429.66	I
1600	4433.88	II
1800	4434.32	II
530	4441.81	I
440	4442.28	I
710	4445.15	I
1300	4452.73	II
1200	4454.63	II
1000	4458.52	II
2200	4467.34	II
810	4470.89	I
370	4499.11	I
440	4581.73	I
380	4649.49	I
470 d	4670.75	I
1100	4674.60	II
370	4688.73	I
530	4704.40	II
730	4716.10	I
770	4728.42	I
470	4745.68	II
730	4760.27	I
580	4783.10	I
350	4785.86	I
970	4841.70	I
730	4883.97	I
630	4910.40	I
350	4913.25	II
430	4918.99	I
400	5044.28	I
540	5071.20	I
510	5117.16	I
350	5122.14	I
360	5155.03	II
470	5175.42	I
250	5200.59	I
260	5251.92	I
400	5271.40	I
250	5282.91	I
220	5453.00	I
230	5493.72	I
230	5516.09	I
140	5550.40	I
140	5659.86	I
120	5696.73	I
85	5706.20	I
70	5773.77	I
60	5778.33	I
70 d	5786.98	II
60	5788.38	I
60	5800.52	I
65	5802.84	I
65	5867.79	I
50	5874.21	I
50	5898.96	I
65	5965.71	II
50	6045.00	I
50	6070.06	I
45	6084.12	I
45 h	6159.56	I
45	6256.54	I
100	6267.28	II
140	6569.31	II
110	6589.72	II
50	6671.51	I
120 d	6731.84	II
95	6794.20	II
120	6860.93	I
120	6955.29	II
90	7020.44	II
90	7039.22	II
90	7042.24	II
90	7051.52	II
90	7082.37	II
26	7088.30	I
30	7095.50	I
30	7104.54	I
26	7115.96	I
85 d	7149.60	II

Intensity	Wavelength/Å	
23	7213.82	I
60	7240.90	II
26	7347.30	I
30	7444.56	I
26	7445.41	I
13	7470.76	I
45	7645.09	II
12	7645.82	I
40 w	7835.08	II
16	7895.96	I
90	7928.14	II
40	8048.70	II
16	8065.16	I
45	8068.46	II
40 w	8305.79	II
19	8383.71	I
45 w	8485.99	II
45 w	8708.43	II
95	8913.66	II
Scandium Sc Z = 21		
350	180.14	V
500	243.87	V
500	252.85	V
500	253.73	V
900	283.91	V
800	284.45	V
600	288.29	V
900	289.59	V
15	289.85	IV
1000 d	291.93	V
800	293.25	V
15	296.31	IV
15	299.04	IV
700	300.00	V
1000	573.36	V
600	587.94	V
10	785.12	IV
25	1168.61	III
15	1550.80	IV
180	1603.06	III
150	1610.19	III
160	2010.42	III
12	2118.97	IV
11	2185.43	IV
11	2205.46	IV
14	2222.22	IV
11	2271.33	IV
110	2438.62	I
560	2545.22	II
2900	2552.37	II
560	2555.82	II
2300	2560.25	II
1100	2563.21	II
11	2586.93	IV
120	2692.78	I
350	2699.07	III
360	2706.77	I
210	2707.95	I
580	2711.35	I
230	2734.05	III
340	2965.86	I
1200	2974.01	I
1400	2980.75	I
340	2988.95	I
2200	3015.36	I
2700	3019.34	I
360	3030.76	I
120 h	3056.31	I
130	3065.11	II
990	3251.32	II
1500	3255.69	I
4400	3269.91	I
5500	3273.63	I
110 d	3343.28	II
270	3352.05	II
9900	3353.73	II
2000	3359.68	II
1700	3361.27	II
1700	3361.94	II
4000	3368.95	II
6600	3372.15	II
130	3418.51	I
200	3429.21	I
200	3429.48	I
270	3431.36	I
530	3435.56	I
270	3457.45	I
180	3462.19	I
130 d	3469.65	I
110	3471.13	I
200	3498.91	I
2700	3535.73	II
6600	3558.55	II
6100	3567.70	II
13000	3572.53	II
9900	3576.35	II
7700	3580.94	II
4000	3589.64	II
4000	3590.48	II
28000	3613.84	II
110	3617.43	I
20000	3630.75	II
13000	3642.79	II
6600	3645.31	II
110	3646.90	I
5300	3651.80	II
110	3664.25	II
290	3666.54	II
75 h	3717.10	I
270	3833.07	II
610	3843.03	II
20000	3907.49	I
23000	3911.81	I
4400	3933.38	I
5500	3996.61	I
530	4014.49	II
20000	4020.40	I
20000	4023.69	I
220	4030.67	I
140	4031.39	I
220	4043.80	I
200	4046.48	I
2700	4047.79	I
120	4049.95	I
5500	4054.55	I
220	4056.59	I
100	4068.66	III
160 h	4074.97	I
160	4078.57	I
6100	4082.40	I
200	4086.67	I
400	4087.16	I
440 h	4133.00	I
530 h	4140.30	I
720	4152.36	I
1100 h	4165.19	I
110 h	4218.26	I
110 h	4219.73	I
180	4231.93	I
200	4233.61	I
400	4238.05	I
15000	4246.83	II
290	4294.77	II
350	4305.71	II
4200	4314.09	II
3300	4320.74	II
2400	4325.01	II
180	4354.61	II
110	4358.64	I
2000	4374.46	II
130	4384.81	II
1100	4400.37	II
880	4415.56	II
120 h	4557.24	I
160 h	4573.99	I
350	4670.40	II
120	4706.97	I
120	4709.34	I
200	4728.77	I
490	4729.23	I
590	4734.10	I
690	4737.65	I
790	4741.02	I
1200	4743.81	I
200	4753.16	I
220	4779.35	I
170	4839.44	I
90	4909.76	I
90	4922.84	I
90	4934.25	I
170	4954.06	I
120	4973.66	I
150	4980.37	I
140	4991.92	I
530	5031.02	II
250	5064.32	I
530	5070.23	I
250	5075.81	I
2100	5081.56	I
1200	5083.72	I
1100	5085.55	I
750	5086.95	I
390	5087.14	I
270	5089.89	I
390	5096.73	I
620	5099.23	I
370	5101.12	I
180	5109.06	I
150	5112.86	I
320	5116.69	I
390	5210.52	I
280	5219.67	I
350	5239.82	II
280	5258.33	I
210	5285.76	I
120	5341.05	I
350	5349.30	I
120	5349.71	I
210	5355.75	I
530	5356.10	I
270	5375.35	I
370	5392.08	I
270	5446.20	I
120	5451.34	I
750	5481.99	I
530	5484.62	I
570	5514.22	I
660	5520.50	I
660	5526.82	II
70	5564.86	I
110	5591.33	I
80	5640.98	II
250	5657.88	II
1500	5671.81	I
1200	5686.84	I
1100	5700.21	I
10	5706.82	IV
190	5708.61	I
880	5711.75	I
230	5717.28	I
180	5724.08	I
14	5771.63	IV
620	6210.68	I
320	6239.78	I
120	6245.63	II
110	6249.96	I
80	6256.01	III
250	6258.96	I
750	6305.67	I
60	6378.82	I
90	6413.35	I
60	6604.60	II
65	6737.87	I
50	6819.52	I
50	6835.03	I
90	7449.16	III
55 h	7741.17	I
30	7800.44	I
19 h	8761.40	I
50	8829.78	III
30 h	8834.35	I
400	22051.86	I
150	22065.05	I

Intensity	Wavelength/Å	
Selenium Se Z = 34		
360	613.0	V
360	652.7	IV
450	670.1	IV
360	724.3	III
450	746.4	IV
450	759.1	V
360	808.7	V
360	830.3	V
360	832.7	II
450	839.5	V
360	843.0	III
360	845.8	V
360	912.9	II
360	959.6	IV
360	974.8	III
450	996.7	IV
360	1013.4	II
360	1014.0	II
450	1033.6	II
450	1049.6	II
360	1057.4	II
360	1094.7	V
360	1099.1	III
450	1119.2	III
360	1141.9	II
450	1192.3	II
450	1227.6	V
285	1291.0	II
285	1308.9	II
285	1314.4	IV
120	1435.3	I
120	1435.8	I
150	1449.2	I
150	1500.9	I
250	1530.4	I
150	1531.3	I
200	1531.8	I
150	1575.3	I
150	1577.6	I
150	1577.9	I
150	1579.5	I
200	1580.0	I
150	1587.5	I
150	1593.2	I
250	1606.5	I
200	1617.4	I
150	1621.2	I
150	1643.4	I
250	1671.2	I
250	1675.3	I
250	1690.7	I
250	1793.3	I
300	1795.3	I
300	1855.2	I
250	1858.8	I
400	1898.6	I
350	1913.8	I
300	1919.2	I
500	1960.9	I
500	2039.8	I
285	2057.5	III
500	2074.8	I
285	2136.6	IV
500	2164.2	I
600	2413.5	I
300	2548.0	I
360	2665.5	IV
285	2724.3	IV
285	2767.2	III
220	2773.8	III
160	2951.6	IV
450	3387.2	III
450	3413.9	III
450	3457.8	III
450	3637.6	III
450	3738.7	III
450	3800.9	III
450	4169.1	III
360	4175.3	II
450	4180.9	II
285	4382.9	II
285	4446.0	II
220	4449.2	II
285	4467.6	II
500	4730.8	I
400	4739.0	I
300	4742.2	I
285	4840.6	II
360	4845.0	II
450	5227.5	II
360	5305.4	II
100	5365.5	I
120	5369.9	I
110	5374.1	I
285	5522.4	II
285	5566.9	II
285	5866.3	II
450	6056.0	II
285	6303.8	III
200	6325.6	I
360	6444.2	II
285	6490.5	II
285	6535.0	II
150	6831.3	I
120	6990.690	I
100	6991.792	I
200	7010.809	I
150	7013.875	I
300	7062.065	I
200	7575.1	I
250	7583.4	I
150	7592.2	I
300	8001.0	I
200	8036.4	I
150	8093.2	I
150	8094.7	I
180	8149.3	I
150	8152.0	I
200	8157.7	I
180	8163.1	I
150	8182.9	I
150	8440.47	I
150	8450.38	I
150	8742.33	I
300	8918.86	I
200	9001.97	I
200	9038.61	I
100	9432.50	I
200	10217.25	I
377	10307.45	I
900	10327.26	I
640	10386.36	I
275	11946.87	I
170	11952.64	I
205	11972.93	I
315	14817.93	I
410	14917.47	I
500	15151.44	I
320	15471.00	I
265	15520.97	I
395	15618.40	I
360	16659.44	I
505	16813.78	I
205	16866.54	I
235	21374.24	I
680	21442.56	I
415	21473.48	I
270	21716.36	I
240	21730.60	I
150	23388.85	I
265	24148.18	I
375	24385.99	I
255	25017.51	I
510	25127.43	I
Silicon Si Z = 14		
10	85.18	V
15	96.44	V
10	97.14	V
20	117.86	V
20	118.97	V
4	457.82	IV
8	566.61	III
8	653.33	III
7	815.05	IV
8	818.13	IV
9	823.41	III
40 h	845.77	II
100	889.72	II
200	892.00	II
9	967.95	III
100	989.87	II
200	992.68	II
10	993.52	III
13	994.79	III
16	997.39	III
50	1023.69	II
8	1066.63	IV
14	1108.37	III
16	1109.97	III
18	1113.23	III
8	1122.49	IV
10	1128.34	IV
100	1190.42	II
200	1193.28	II
250	1194.50	II
100	1197.39	II
30	1206.51	III
30	1206.53	III
9	1207.52	III
10	1210.46	III
50	1226.81	II
100	1227.60	II
150	1228.75	II
200	1229.39	II
100	1246.74	II
150	1248.43	II
100	1250.09	II
150	1250.43	II
200	1251.16	II
40	1256.49	I
50	1258.80	I
1000	1260.42	II
2000	1264.73	II
200	1265.02	II
17	1294.54	III
14	1296.73	III
15	1298.89	III
18	1298.96	III
14	1301.15	III
16	1303.32	III
100	1304.37	II
50 h	1305.59	II
200	1309.27	II
13	1312.59	III
100	1346.87	II
100	1348.54	II
150	1350.06	II
100	1352.64	II
100	1353.72	II
15	1393.76	IV
12	1402.77	IV
13	1417.24	III
90 h	1485.02	II
100 h	1485.51	II
12	1500.24	III
10	1501.19	III
9	1501.87	III
100 h	1509.10	II
50 h	1512.07	II
60 p	1516.91	II
500	1526.72	II
1000	1533.45	II
150	1594.55	I
100	1622.87	I
300	1629.43	I
200	1629.92	I
100	1667.62	I
100	1668.52	I
100	1672.59	I
200	1675.20	I
200	1696.20	I
200	1697.94	I
100 h	1770.92	I

Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å	
100 h	1776.83	I	300	2904.28	II	16	4716.65	III	90	6131.850	I
100 h	1799.12	I	500	2905.69	II	50	4782.991	I	100	6142.487	I
150	1808.00	II	55	2970.355	I	35	4792.212	I	100	6145.015	I
500 h	1814.07	I	150	2987.645	I	80	4792.324	I	160	6155.134	I
200	1816.92	II	50	3006.739	I	15	4813.33	III	160	6237.320	I
200	1836.51	I	75	3020.004	I	16	4819.72	III	40	6238.287	I
200	1841.44	I	100 h	3030.00	II	18	4828.97	III	125	6243.813	I
9	1842.55	III	9	3040.93	III	30	4947.607	I	125	6244.468	I
200	1843.77	I	100 h	3043.69	II	40	5006.061	I	180	6254.188	I
300	1845.51	I	50 h	3048.30	II	1000	5041.03	II	45	6331.954	I
400	1847.47	I	150 h	3053.18	II	1000	5055.98	II	1000	6347.10	II
200	1848.14	I	25	3086.24	III	10 h	5091.42	III	1000	6371.36	II
500	1850.67	I	20	3093.42	III	100	5181.90	II	45	6526.609	I
200	1852.46	I	16	3096.83	III	100 h	5185.25	II	45	6527.199	I
500 h	1874.84	I	9	3165.71	IV	200 h	5192.86	II	45	6555.462	I
200	1881.85	I	16	3185.13	III	500 h	5202.41	II	50 h	6660.52	II
200	1887.70	I	13	3186.02	III	100 h	5405.34	II	100	6671.88	II
200 h	1893.25	I	150	3188.97	II	100 h	5438.62	II	7	6701.21	IV
1000 h	1901.33	I	150	3193.09	II	100 h	5456.45	II	50 h	6717.04	II
100 h	1902.46	II	100	3195.41	II	500 h	5466.43	II	100	6721.853	I
50 h	1910.62	II	14	3196.50	III	500 h	5466.87	II	50	6829.82	II
50	1941.67	II	200	3199.51	II	100 h	5469.21	II	30	6848.568	I
100	1949.56	II	100 h	3203.87	II	200 h	5496.45	II	80	6976.523	I
100	1954.97	I	200 h	3210.03	II	35	5517.535	I	180	7003.567	I
50	2058.65	II	15	3210.55	III	100 h	5540.74	II	180	7005.883	I
50	2059.01	II	75	3214.66	II	150 h	5576.66	II	90	7017.646	I
200	2072.02	II	12	3230.50	III	30	5622.221	I	250	7034.903	I
200	2072.70	II	14	3233.95	III	100 h	5632.97	II	6 h	7047.94	IV
100	2124.12	I	15	3241.62	III	200 h	5639.48	II	200	7165.545	I
50 h	2136.56	II	12	3258.66	III	90	5645.611	I	100	7226.206	I
110	2207.98	I	10	3276.26	III	150 h	5660.66	II	100	7235.326	I
115	2210.89	I	300	3333.14	II	80	5665.554	I	180	7250.625	I
110	2211.74	I	500	3339.82	II	1000 h	5669.56	II	160	7275.294	I
120	2216.67	I	15	3486.91	III	120	5684.484	I	400	7289.173	I
120	2218.06	I	9	3525.94	III	300 h	5688.81	II	375	7405.774	I
10	2296.87	III	20	3590.47	III	100	5690.425	I	200	7409.082	I
10	2308.19	III	8	3762.44	IV	90	5701.105	I	275	7415.946	I
100 h	2356.30	II	20 c	3791.41	III	200 h	5701.37	II	425	7423.497	I
30 h	2357.18	II	25	3796.11	III	100 h	5706.37	II	9 h	7466.32	III
50 h	2357.97	II	30	3806.54	III	160	5708.397	I	12 h	7612.36	III
300	2435.15	I	100 h	3853.66	II	20	5739.73	III	100	7680.267	I
11	2449.48	III	500 h	3856.02	II	45	5747.667	I	6 h	7723.82	IV
425	2506.90	I	200 h	3862.60	II	45	5753.625	I	30	7800.008	I
375	2514.32	I	300	3905.523	I	45	5754.220	I	400	7848.80	II
500	2516.113	I	20	3924.47	III	45	5762.977	I	500	7849.72	II
7	2517.51	IV	10	4088.85	IV	70	5772.145	I	30	7849.967	I
350	2519.202	I	70	4102.936	I	70	5780.384	I	90	7918.386	I
425	2524.108	I	9	4116.10	IV	90	5793.071	I	120	7932.349	I
450	2528.509	I	300 h	4128.07	II	100	5797.859	I	140	7944.001	I
110	2532.381	I	500 h	4130.89	II	150 h	5800.47	II	35	7970.306	I
25	2541.82	III	100 h	4190.72	II	200	5806.74	II	35	8035.619	I
10	2546.09	III	50	4198.13	II	50	5846.13	II	70	8093.241	I
14	2559.21	III	9	4338.50	III	300 h	5868.40	II	9 h	8102.86	III
30	2563.679	I	30	4552.62	III	40	5873.764	I	11 h	8103.45	III
85	2568.641	I	25	4567.82	III	10 h	5898.79	III	35	8230.642	I
45	2577.151	I	20	4574.76	III	150	5915.22	II	9 h	8262.57	III
190	2631.282	I	100	4621.42	II	200	5948.545	I	40	8443.982	I
11	2640.79	III	150	4621.72	II	500	5957.56	II	40	8501.547	I
14	2655.51	III	9 h	4631.24	IV	500	5978.93	II	60	8502.221	I
9	2817.11	III	10 h	4654.32	IV	90	6125.021	I	40	8536.165	I
1000	2881.579	I	9	4683.02	III	85	6131.574	I	120	8556.780	I

Intensity	Wavelength/Å	
50	8648.462	I
40	8728.011	I
75	8742.451	I
100	8752.009	I
35	8790.389	I
100	9412.72	II
100	9413.506	I
30	10371.269	I
120	10585.141	I
120	10603.431	I
120	10660.975	I
30	10694.251	I
30	10727.408	I
60	10749.384	I
30	10784.550	I
80	10786.856	I
140	10827.091	I
60	10843.854	I
130	10869.541	I
30	10882.802	I
30	10885.336	I
80	10979.308	I
30	10982.061	I
80	11017.965	I
370	11984.19	I
220	11991.57	I
440	12031.51	I
190	15888.39	I
95	16060.03	I
110	19722.50	I
Silver Ag Z = 47		
25	730.83	II
30	752.80	II
400	799.41	III
15	1005.32	II
10	1065.49	II
12	1072.23	II
250	1074.22	II
150	1107.03	II
150	1112.46	II
60	1195.83	II
50	1223.33	II
50	1240.80	II
50	1246.87	II
55	1256.81	II
55	1257.55	II
50	1266.63	II
70	1273.67	II
65	1297.51	II
85	1311.20	II
55	1313.81	II
50	1314.61	II
60	1323.84	II
60	1342.09	II
50	1342.57	II
70	1346.62	II
50	1353.54	II
150	1364.50	II
100	1396.00	II
100	1410.93	II
90	1419.72	II

Intensity	Wavelength/Å	
95	1432.60	II
100	1464.72	II
50	1466.23	II
50 r	1507.37	I
100 r	1515.63	I
50 r	1548.58	I
100	1555.16	II
100	1644.50	II
60	1651.52	I
50	1652.10	I
700	1656.18	III
120	1682.82	II
500	1693.51	III
10	1708.11	I
50	1709.27	I
125	1736.44	II
750	1751.03	III
10 h	1766.14	I
75	1790.37	II
600	1917.08	III
700	1957.62	III
100	1967.38	II
600	1975.92	III
500	1977.03	III
600	2000.24	III
150	2015.96	II
150	2033.98	II
200	2061.17	I
100	2069.85	I
80 r	2113.82	II
60	2145.60	II
600	2161.89	III
50	2186.76	II
60	2229.53	II
100 r	2246.43	II
500	2246.51	III
75 r	2248.74	II
75	2280.03	II
30 h	2309.56	I
700	2310.04	III
70 r	2317.05	II
80 r	2320.29	II
70 r	2324.68	II
80 r	2331.40	II
70	2357.92	II
50 h	2375.02	I
75	2411.41	II
90 r	2413.23	II
100 r	2437.81	II
80	2447.93	II
80	2473.84	II
60	2506.63	II
50 h	2575.63	I
60	2660.49	II
60	2721.77	I
75	2767.54	II
100 h	2824.39	I
30 h	3130.02	I
90	3180.70	II
100	3267.35	II
55000 r	3280.68	I

Intensity	Wavelength/Å	
28000 r	3382.89	I
30	3469.16	I
70	3475.82	II
80	3495.28	II
50	3542.61	I
50 h	3624.68	I
75	3682.46	II
30	3682.50	I
80	3683.34	II
50 h	3709.20	I
200	3810.94	I
50	3811.78	I
100 h	3840.74	I
50 h	3907.41	I
50	3909.31	II
50 h	3914.40	I
70	3920.10	II
60	3949.43	II
100 h	3981.58	I
70	3985.19	II
100 h	4055.48	I
80	4085.91	II
100	4185.48	II
90 h	4210.96	I
100	4212.82	I
50	4311.07	I
50 h	4476.04	I
30 h	4615.69	I
80	4620.04	II
50	4620.46	II
60 h	4668.48	I
30 h	4677.60	I
100	4788.40	II
30 h	4847.82	I
100	4874.10	I
80	5027.35	II
1000	5209.08	I
1000	5465.50	I
100	5471.55	I
100	5667.34	I
10 h	6268.50	I
320	7687.78	I
25	8005.4	II
500	8273.52	I
25	8403.8	II
30 h	8645.70	I
10 h	8704.85	I
12	8747.6	II
15	9000.9	II
10	12551.0	I
60	16819.5	I
20	17416.7	I
15	18307.9	I
15	18382.3	I
Sodium Na Z = 11		
7	142.232	IV
8	146.064	IV
9	150.298	IV
8	150.687	IV
8	155.510	IV
8	156.537	IV

Intensity	Wavelength/Å	
12	162.448	IV
10	163.190	IV
12	168.411	IV
10	168.546	IV
5	183.95	III
10	190.445	IV
10	199.772	IV
8	202.49	III
8	202.76	III
8 p	203.06	III
8	203.28	III
8	203.33	III
15	229.87	III
50 c	250.52	III
30	251.37	III
25	266.90	III
70	267.65	III
50	267.87	III
50	268.63	III
20 p	272.08	III
20	272.45	III
10	319.644	IV
300	372.08	II
350	376.38	II
100	378.14	III
70	380.10	III
12	408.684	IV
10	409.614	IV
15	410.372	IV
10	411.334	IV
13	412.242	IV
11	1582.18	IV
11 d	1583.98	IV
12	1584.14	IV
12 d	1587.05	IV
11	1615.92	IV
12	1618.57	IV
11	1655.47	IV
15 c	1701.97	IV
20 d	1887.47	III
12	1960.76	IV
11	1965.08	IV
12 d	2106.33	IV
30	2230.33	III
16	2232.19	III
20 h	2246.70	III
300	2315.65	II
18	2386.99	III
17	2394.03	III
300	2420.99	II
300	2424.73	II
25	2459.31	III
18	2468.85	III
20	2474.73	III
1000	2493.15	II
25	2497.03	III
17	2510.26	III
20	2543.84	I
10	2543.87	I
70	2593.87	I
35	2593.92	I

Intensity	Wavelength/Å	
850	2611.81	II
850	2661.00	II
1000	2671.83	II
200	2680.34	I
100	2680.43	I
1000	2841.72	II
400	2852.81	I
200	2853.01	I
2	2893.62	I
1100	2904.92	II
1100	2917.52	II
1100	2919.05	II
1200	2919.85	II
1300	2920.95	II
1000	2923.49	II
1200	2951.24	II
1100	2952.40	II
1000	2977.13	II
1100	2979.66	II
1100	2980.63	II
1300	2984.19	II
1700	3124.42	II
2500	3135.48	II
1700	3137.86	II
2000	3149.28	II
2000	3163.74	II
1000	3179.06	II
1700	3189.79	II
1600	3212.19	II
1500	3257.96	II
1700	3285.60	II
1700	3301.35	II
1200	3302.37	I
600	3302.98	I
1500	3304.96	II
1000	3318.04	II
50	3426.86	I
1500	3533.05	II
1200	3631.27	II
6	4238.99	I
10	4242.08	I
1	4249.41	I
2	4252.52	I
15	4273.64	I
20	4276.79	I
2	4287.84	I
3	4291.01	I
30	4321.40	I
40	4324.62	I
3	4341.49	I
5	4344.74	I
40	4390.03	I
60	4393.34	I
5	4419.88	I
8	4423.25	I
60	4494.18	I
100	4497.66	I
10	4541.63	I
15	4545.19	I
120	4664.811	I
200	4668.560	I

Intensity	Wavelength/Å	
20	4747.941	I
30	4751.822	I
200	4978.541	I
400	4982.813	I
40	5148.838	I
80	5153.402	I
280	5682.633	I
70	5688.193	I
560	5688.205	I
80000	5889.950	I
40000	5895.924	I
120	6154.225	I
240	6160.747	I
130	6530.70	II
130	6544.04	II
130	6545.75	II
20	7373.23	I
10	7373.49	I
50	7809.78	I
25	7810.24	I
4400	8183.256	I
800	8194.790	I
8800	8194.824	I
100	8649.92	I
60	8650.89	I
25	8942.96	I
40	9153.88	I
60	9465.94	I
80	9961.28	I
20	10566.00	I
60	10572.28	I
200	10746.44	I
80	10749.29	I
120	10834.87	I
35	11190.19	I
50	11197.21	I
400	11381.45	I
1000	11403.78	I
400	12679.17	I
60	14767.48	I
100	14779.73	I
60	16373.85	I
100	16388.85	I
400	18465.25	I
50	22056.44	I
25	22083.67	I
60	23348.41	I
100	23379.13	I

Strontium Sr Z = 38

15	298.12	IV
15	300.12	IV
125	330.67	III
500	351.62	III
75	358.80	III
250	363.49	III
150	371.21	III
20	378.53	IV
75	392.44	IV
50	393.00	IV
50	396.22	IV
1000	437.24	III

Intensity	Wavelength/Å	
1875	491.79	III
1250	507.04	III
3750	514.38	III
10	517.28	V
2500	562.75	III
25	578.01	V
30	624.93	V
25	642.23	V
50	649.21	V
25	660.94	V
200	664.43	IV
35	686.23	V
100	710.35	IV
12	747.82	V
50	1025.23	III
35	1125.49	III
50	1236.23	III
1400	2152.84	II
1400	2165.96	II
100	2273.71	III
100	2340.13	III
50	2346.97	IV
160	2428.10	I
100	2486.52	III
40	2555.60	IV
40	2571.04	IV
100	3002.61	III
200	3012.32	III
10	3019.29	IV
100	3021.73	III
50	3061.43	III
50	3182.61	III
100	3235.39	III
400	3351.25	I
650	3380.71	II
50	3430.76	III
950	3464.46	II
600	3969.26	I
1300	4030.38	I
46000	4077.71	II
32000	4215.52	II
9	4298.57	IV
340	4305.45	II
65000	4607.33	I
9	4685.08	IV
3200	4722.28	I
2200	4741.92	I
1400	4784.32	I
4800	4811.88	I
3600	4832.08	I
3000	4872.49	I
2000	4876.32	I
1000	4891.98	I
8000	4962.26	I
1300	4967.94	I
800 h	5156.07	I
1400	5222.20	I
2000	5225.11	I
2000	5229.27	I
2800	5238.55	I
4800	5256.90	I

Intensity	Wavelength/Å	
40	5257.71	III
40	5443.48	III
1500	5450.84	I
7000	5480.84	I
3500	5504.17	I
2600	5521.83	I
2000	5534.81	I
2000	5540.05	I
1000	6380.75	I
900 h	6386.50	I
600 h	6388.24	I
9000	6408.47	I
5500	6504.00	I
1000	6546.79	I
1700	6550.26	I
3000	6617.26	I
1800	6791.05	I
4800	6878.38	I
1200	6892.59	I
5500	7070.10	I
2500	7309.41	I
500	7621.50	I
400 h	7673.06	I
200 h	8422.80	I
120	8505.69	II
200	8688.91	II
100	9294.10	I
400 h	9448.95	I
600	9596.00	I
300	9624.70	I
100	9638.10	I
100 h	9647.70	II
300	10036.66	II
1000	10327.31	II
200	10914.88	II
700	11241.25	I
100	12014.76	II
60	12445.90	II
40	12495.00	I
75	12974.70	II
100	13123.80	II
50	17447.40	I
230	20261.40	I
120	20700.70	I
30	26023.60	I

Sulfur S Z = 16

5	437.4	V
5	438.2	V
5	439.6	V
20	519.3	IV
20	520.1	IV
40	520.8	IV
20	522.0	IV
20	522.5	IV
20	551.2	IV
40	652.5	IV
40	653.0	IV
70	653.6	IV
40	654.0	IV
70	655.6	IV
20	655.9	IV

Intensity	Wavelength/Å	
110	657.3	IV
40	658.3	V
70	659.8	V
40	660.9	IV
160	661.4	IV
110	663.2	V
40	663.7	IV
40	664.8	IV
70	666.1	IV
20	678.1	V
40	680.3	V
110	680.9	V
40	681.6	V
20	693.5	V
70	729.5	III
110	732.42	III
70	735.2	III
70	738.5	III
110	744.9	IV
110	748.4	IV
110	750.2	IV
110	753.8	IV
285	786.5	V
70	789.0	III
70	796.7	III
70	800.5	IV
70	804.0	IV
70	809.7	IV
110	816.0	IV
70	824.9	III
70	836.3	III
160	849.2	V
110	852.2	V
220	854.8	V
110	857.9	V
110	860.5	V
40	906.9	II
40	910.5	II
40	912.7	II
40	937.4	II
40	937.7	II
160	1062.7	IV
160	1073.0	IV
70	1073.5	IV
285	1077.1	III
40	1102.3	II
70	1194.0	III
70	1201.0	III
40	1234.1	II
40	1250.5	II
110	1253.8	II
110	1259.5	II
275	1270.782	I
250	1277.216	I
280	1295.653	I
275	1302.337	I
235	1302.863	I
235	1303.110	I
245	1303.430	I
260	1305.883	I
265	1310.194	I
355	1316.542	I
290	1316.618	I
375	1323.515	I
355	1326.643	I
775	1381.552	I
710	1385.510	I
960	1388.435	I
640	1389.154	I
775	1392.588	I
1000	1396.112	I
300	1409.337	I
510	1425.030	I
425	1433.280	I
300	1436.968	I
300	1448.229	I
425	1472.972	I
550	1473.995	I
300	1474.380	I
355	1481.665	I
485	1483.039	I
300	1483.233	I
330	1485.622	I
390	1487.150	I
20	1624.0	IV
20	1629.2	IV
680	1666.688	I
640	1687.530	I
710	1807.311	I
680	1820.343	I
640	1826.245	I
710	1900.286	I
550	1914.698	I
20	2387.0	IV
40	2398.9	IV
110	2460.5	III
110	2489.6	III
160	2496.2	III
160	2499.1	III
220	2508.2	III
70	2636.9	III
220	2665.4	III
110	2691.8	III
110	2702.8	III
220	2718.9	III
110	2721.4	III
220	2726.8	III
220	2731.1	III
110	2741.0	III
285	2756.9	III
110	2775.2	III
160	2785.5	III
110	2863.5	III
160	2904.3	III
160	2986.0	III
110	3097.5	IV
110	3497.3	III
160	3632.0	III
110	3709.4	III
160	3717.8	III
160	3838.3	III
285	3867.6	I
285	3902.0	I
160	3928.6	III
360	3933.3	II
450	4120.8	I
280	4142.3	II
360	4145.1	II
450	4153.1	II
450	4162.7	II
360	4253.6	III
450	4694.1	I
285	4695.4	I
160	4696.2	I
280	4716.2	II
450	4815.5	II
360	4924.1	II
450	4925.3	II
285	4993.5	I
360	5428.6	II
650	5432.8	II
1000	5453.8	II
1000	5473.6	II
1000	5509.7	II
280	5564.9	II
1000	5606.1	II
450	5640.0	II
450	5640.3	II
280	5647.0	II
650	5659.9	II
450	5664.7	II
160	5706.1	I
450	5819.2	II
450	6052.7	I
280	6286.4	II
450	6287.1	II
450	6305.5	II
450	6312.7	II
280	6384.9	II
280	6397.3	II
280	6398.0	II
360	6413.7	II
160	6743.6	I
285	6748.8	I
450	6757.2	I
450	7579.0	I
450	7629.8	I
285	7686.1	I
450	7696.7	I
1000	7924.0	I
160	7928.8	I
285	7930.3	I
450	7931.7	I
450	7967.4	I
450	7967.4	II
450	8314.7	I
450	8314.7	II
450	8585.6	I
285	8680.5	I
450	8694.7	I
360	8874.5	I
110	8882.5	I
220	8884.2	I
160	9035.9	I
450	9212.9	I
450	9228.1	I
450	9237.5	I
285	9413.5	I
285	9421.9	I
285	9437.1	I
650	9649.9	I
450	9672.3	I
450	9680.8	I
450	9693.7	I
285	9697.3	I
285	9739.7	I
285	9932.3	I
285	9949.8	I
285	9958.9	I
285	10455.5	I
285	10459.5	I

Tantalum Ta Z = 73

60	493.07	V
1000	890.87	V
500	947.30	V
67	999.34	IV
79	1116.10	IV
78	1136.17	IV
85	1175.51	IV
80	1189.28	IV
80	1192.67	IV
85	1213.09	IV
500	1213.42	V
85	1215.53	IV
90	1223.73	IV
88	1238.12	IV
95	1240.06	IV
87	1258.34	IV
94	1264.91	IV
98	1272.42	IV
94	1275.48	IV
86	1275.94	IV
92	1308.51	IV
87	1315.58	IV
92	1332.38	IV
86	1343.30	IV
92	1365.88	IV
5000	1392.56	V
91	1398.78	IV
93	1413.40	IV
91	1454.32	IV
92	1464.41	IV
93	1469.82	IV
90	1495.25	IV
95	1514.19	IV
85	1607.70	IV
7000	1709.10	V
85	1712.16	IV
85	1716.13	IV
85	2055.75	IV
1100	2140.13	II
1500	2146.87	II
1200	2182.71	II
1100	2193.88	II

Intensity	Wavelength/Å	
1500	2196.03	II
90	2199.58	IV
1500	2199.67	II
90	2207.64	IV
1400 d	2210.03	II
1400	2239.48	II
1200	2250.76	II
840	2261.42	II
990	2262.30	II
990	2272.59	II
790	2285.25	II
600	2286.59	II
990	2289.16	II
440	2302.24	II
440	2302.93	II
440	2312.60	II
420	2315.46	II
690	2331.98	II
550	2332.19	II
250	2357.30	I
260	2361.09	I
600	2364.24	II
320	2371.58	I
1400	2387.06	II
2400	2400.63	II
320	2416.89	II
360	2427.64	I
360	2429.71	II
480	2432.70	II
380	2470.90	II
600	2474.62	I
500	2484.95	I
600	2488.70	II
500	2490.46	I
600	2504.45	I
600	2507.45	I
1200 d	2526.35	I
600	2532.12	II
1200	2559.43	I
460	2562.10	I
600	2577.37	II
600	2603.49	II
1400	2608.63	I
1200	2635.58	II
860	2636.90	I
2400	2647.47	I
2600	2653.27	I
1900	2656.61	I
1500	2661.34	I
770	2675.90	II
1500	2685.17	II
470	2694.52	II
1000	2698.30	I
1200	2710.13	I
2600	2714.67	I
470	2727.44	II
1200	2748.78	I
860	2749.83	I
410	2752.49	II
1000	2758.31	I
430	2761.68	II
770	2775.88	I
680	2796.34	I
680	2797.76	II
510	2806.58	I
640	2844.25	I
560	2848.52	I
1500	2850.49	I
1900	2850.98	I
360	2861.98	I
470	2871.42	I
380	2880.02	I
770	2891.84	I
560	2902.05	I
310	2915.49	I
410	2925.19	I
310	2932.70	I
1700	2933.55	I
470	2940.06	I
1200	2940.22	I
510	2951.92	I
340	2953.56	I
1500	2963.32	I
770	2965.13	II
770	2965.54	I
340	2969.47	I
430	2975.56	I
1800	3012.54	II
290 d	3027.48	I
530	3049.56	I
530	3069.24	I
360	3077.24	I
560	3103.25	I
380	3124.97	I
380	3130.58	I
270	3132.64	I
320	3170.29	I
270	3173.59	I
600	3180.95	I
300	3223.83	I
1100	3311.16	I
680	3318.84	I
330 d	3330.99	II
640	3371.54	I
360	3385.05	I
450	3406.94	I
490	3480.52	I
380	3497.85	I
490	3511.04	I
750	3607.41	I
980	3626.62	I
500	3642.06	I
210	3918.51	I
210	3970.10	I
210	3996.17	I
410	4061.40	I
310	4067.91	I
300	4205.88	I
360 c	4510.98	I
340	4574.31	I
260	4619.51	I
450	4681.88	I
200	5037.37	I
100	5067.87	I
110	5115.84	I
100	5141.62	I
100	5143.69	I
330	5156.56	I
110	5212.74	I
110 d	5218.45	I
140	5341.05	I
200	5402.51	I
130	5419.19	I
90	5518.91	I
150	5645.91	I
130	5664.90	I
130	5776.77	I
90	5780.71	I
130	5811.10	I
240	5877.36	I
130	5882.30	I
90	5901.91	I
90	5918.95	I
130	5939.76	I
240	5944.02	I
190 c	5997.23	I
100	6020.72	I
250	6045.39	I
100	6047.25	I
100	6101.58	I
65	6144.56	I
130	6154.50	I
150	6256.68	I
150	6268.70	I
150	6309.58	I
75	6325.08	I
65	6341.17	I
75	6356.16	I
65	6360.84	I
90	6389.45	I
65	6428.60	I
250	6430.79	I
200	6450.36	I
380	6485.37	I
65	6505.52	I
100	6514.39	I
100	6516.10	I
100	6574.84	I
110	6611.95	I
75	6621.30	I
100	6673.73	I
180	6675.53	I
75 c	6740.73	I
75	6771.74	I
160 c	6813.25	I
210	6866.23	I
180	6875.27	I
150	6902.10	I
140	6927.38	I
140	6928.54	I
65	6951.26	I
180	6966.13	I
110 d	6995.22	I
75	7006.96	I
150	7148.63	I
110	7172.90	I
140	7301.74	I
160	7346.41	I
140 c	7352.86	I
100	7356.96	I
90 cw	7369.09	I
160	7407.89	I
100	7882.37	I
75	8026.50	I
75	8281.62	I
Technetium Tc Z = 43		
10000 c	3636.07	I
20000 c	4031.63	I
15000	4095.67	I
20000	4262.27	I
30000	4297.06	I
20000	4853.59	I
Tellurium Te Z = 52		
8	802.28	II
8	1059.51	II
8	1077.66	II
10	1161.42	II
10	1174.34	II
12	1175.79	II
9	1208.54	II
9	1220.98	II
9	1253.62	II
9	1270.52	II
10	1324.92	II
9	1363.24	II
8	1366.73	II
10	1374.80	II
10	1608.41	II
10	1613.15	II
5	1655.4	I
5	1688.5	I
6	1700.0	I
5	1708.0	I
10	1822.4	I
26000	2002.02	I
6500	2081.16	I
18000	2142.81	I
3200	2147.25	I
500	2259.02	I
1200	2383.26	I
1500	2385.78	I
50	2438.69	II
120	2530.72	I
100	2649.66	II
80	2661.10	II
110	2677.13	I
100	2858.29	II
150	2895.41	II
70	2967.29	II
70	3047.00	II
100	3175.14	I
60	3256.80	II
60	3329.22	II

Intensity	Wavelength/Å	
150	3406.79	II
50	3442.25	II
50	3521.11	II
50	3552.19	II
100	3611.78	II
50	3617.57	II
50	4006.52	II
70	4127.32	II
100	4169.77	II
80	4225.73	II
100	4261.11	II
60	4273.43	II
80	4285.85	II
150	4364.00	II
75	4385.10	II
170	4478.63	II
80	4537.07	II
100	4557.78	II
70	4630.62	II
100	4641.12	II
180	4654.37	II
200	4686.91	II
100	4696.38	II
100	4706.53	II
100	4766.05	II
100	4784.87	II
100	4827.14	II
150	4831.28	II
150	4842.90	II
130	4865.12	II
200	4866.24	II
8	5083.0	I
50	5449.84	II
50	5487.95	II
150	5576.35	II
150	5649.26	II
100	5666.20	II
200	5708.12	II
150	5755.85	II
100	5974.68	II
50	6367.13	II
10 h	6790.0	I
20 h	6837.6	I
20 h	6854.7	I
15 h	7191.1	I
20 h	7263.5	I
12	7460.98	II
15	7468.75	II
15	7921.69	II
15	7943.14	II
10	7950.34	II
30 h	8061.4	I
10	8122.44	II
20	8186.44	II
15	8273.53	II
15	8672.95	II
10	8733.81	II
205	8758.18	I
81	9004.37	I
5660	9722.74	I
532	9868.92	I
689	9956.30	I
325	9977.13	I
5950	10051.41	I
4097	10091.01	I
381	10118.08	I
397	10300.56	I
745	10493.57	I
1880	10918.34	I
10200	11089.56	I
508	11163.74	I
6620	11487.23	I
1580	13247.75	I
1050	14513.51	I
1480	15452.45	I
2430	15546.23	I
3760	16403.90	I
1960	17303.54	I
2780	18291.59	I
1020	21043.73	I
464	21602.50	I
74	22555.29	I
38	26539.17	I

Terbium Tb Z = 65

1000	1259.40	IV
1000	1327.67	IV
1000	1373.86	IV
5000	1595.39	IV
2000	1633.19	IV
2000	2027.79	IV
1000	2089.98	IV
1000	2332.54	IV
110	2584.61	II
110	2608.57	II
130	2628.69	II
140	2669.29	II
190	2704.07	II
270	2769.53	II
320	2897.44	II
250	2956.21	II
230	3010.59	II
230	3016.18	II
460	3053.55	II
460	3070.05	II
670	3078.86	II
480	3082.36	II
480	3089.58	II
480	3102.96	II
440	3139.64	II
480	3187.26	II
480	3199.56	II
1100	3218.93	II
1200	3219.98	II
480	3252.32	II
760	3280.31	II
760	3281.40	II
1000	3285.04	II
1500	3293.07	II
3800	3324.40	II
760	3349.42	II
760	3364.93	II
810	3454.06	II
810 d	3472.79	II
810	3500.84	II
5700	3509.17	II
1300	3523.66	II
1100	3540.24	II
810	3543.89	II
3200	3561.74	II
810	3567.35	II
4200	3568.52	II
1600	3568.98	II
1100	3579.20	II
710	3585.03	II
810	3596.38	II
1600	3600.44	II
810	3625.54	II
2300	3650.40	II
810	3654.88	II
2000	3658.88	II
3800	3676.35	II
810	3682.26	II
450	3693.58	I
450	3700.12	I
4700	3702.86	II
2400	3703.92	II
1000 d	3711.76	II
650	3745.04	I
870	3747.17	II
870	3747.34	II
1100	3755.24	II
650	3759.35	I
1700	3765.14	I
2100	3776.49	II
600	3783.53	I
410	3789.92	I
760 d	3806.85	II
1500	3830.26	I
540	3833.42	I
920 d	3842.50	II
3700	3848.73	II
3500 w	3874.17	II
480	3888.22	I
490	3894.64	I
2400	3899.20	II
1600	3901.33	I
480	3908.06	I
650	3915.43	I
760	3925.45	II
810 d	3939.52	II
2200 d	3976.84	II
1800	3981.87	II
970	4002.59	II
1900	4005.47	II
760	4012.75	II
870	4032.28	I
2100	4033.03	II
430	4054.12	I
410	4060.37	I
1300	4061.58	I
650	4105.37	I
1100	4144.41	II
350	4158.53	I
390	4196.74	I
650	4203.74	I
600	4206.49	I
480	4215.09	I
480	4232.82	I
650	4266.34	I
760 cw	4278.52	II
450	4310.42	I
2200	4318.83	I
600	4322.23	I
600	4325.83	II
3000	4326.43	I
600	4332.12	I
870	4336.43	I
600	4337.64	I
1700	4338.41	I
700	4340.62	I
870	4356.81	I
330	4382.45	I
300	4388.23	I
260	4390.91	I
350	4423.10	I
240	4436.12	I
240	4448.04	I
430	4493.07	I
75	4514.31	II
110	4549.07	I
110	4550.45	I
110	4556.46	I
110	4563.69	II
210	4578.69	II
65	4584.84	II
65	4591.56	II
75 d	4626.32	II
95	4626.94	II
65	4632.07	I
65 h	4636.59	I
85	4641.00	II
210	4641.98	II
260 cw	4645.31	II
80	4647.23	I
80	4662.79	I
80	4676.90	I
70 c	4681.87	I
80	4688.63	II
80	4693.11	II
200	4702.41	II
110	4707.94	II
80	4739.93	I
70	4747.80	I
410 cw	4752.53	II
180	4786.78	I
100	4813.77	I
80	4875.57	II
80	4881.15	II
95	4915.90	I
65	4931.79	I
85	4993.82	II
110	5078.25	I
75	5089.12	II
85	5186.13	I

Intensity	Wavelength/Å	
120	5228.12	I
75	5248.71	I
75 w	5262.11	II
75	5281.05	I
65	5304.72	I
110	5319.23	I
65 w	5337.90	I
160	5354.88	I
75	5369.72	I
75	5375.98	I
50	5424.10	II
55	5459.81	I
55	5509.61	I
50	5514.54	I
65	5524.12	I
85 c	5747.58	I
75	5795.64	I
75	5803.13	II
65	5815.36	I
65	5851.07	I
65	5870.62	I
65 c	5920.78	I
75	5967.34	II
35	6331.68	II
35 cw	6518.68	I
35	6581.82	I
90	6677.94	II
40 cw	6702.61	I
130	6794.58	II
55	6896.37	II
45 h	6899.95	I
40	6901.98	I
65	7204.28	I
40	7257.73	I
45	7348.88	II
45	7496.12	I
27 h	7582.03	II
45	7590.24	I
65	7596.44	I
30	7627.81	I
30	7737.63	I
30	7855.79	II
27	7927.90	II
30	8025.42	II
30	8085.06	II
65	8194.82	II
95	8212.57	I
40	8450.06	II
30 h	8511.80	I
45	8583.45	II
30	8603.40	I
65	8765.74	II

Thallium Tl Z = 81

10	570.49	IV
5 r	670.87	II
15 r	696.30	II
5 r	709.23	II
10 r	817.18	II
5 r	836.34	II
8 r	1018.85	II
30	1028.69	IV
20	1034.73	IV
20	1036.61	IV
10 r	1049.73	II
8 r	1050.30	II
5 r	1074.97	II
30	1079.68	IV
10 r	1130.17	II
15 r	1162.55	II
10 r	1167.43	II
10 r	1183.41	II
12 r	1194.84	II
5 r	1246.00	II
10	1266.33	III
15 r	1307.50	II
8 r	1310.20	II
25 r	1321.71	II
8 r	1330.40	II
10 r	1373.52	II
10	1477.14	III
8 r	1489.65	I
10 r	1499.30	II
10 r	1507.82	II
15 r	1561.58	II
10 r	1568.57	II
7 r	1593.26	II
5 h	1616.	I
5	1685.40	I
10 r	1792.76	II
12 r	1814.85	II
25 r	1908.64	II
100 r	2007.56	I
100 r	2210.71	I
30	2298.04	II
140	2315.98	I
900 h	2379.69	I
20	2530.86	II
700	2580.14	I
420	2709.23	I
4400 d	2767.87	I
10	2849.80	II
2800	2918.32	I
20	3091.56	II
15	3185.51	II
15	3186.56	II
15	3187.74	II
1200	3229.75	I
15	3291.01	II
15	3369.15	II
9	3456.34	III
20000	3519.24	I
5000	3529.43	I
8	3540.08	II
9	3560.68	II
12000 w	3775.72	I
10	3832.30	II
10	3887.15	II
7	4109.85	III
6	4269.81	III
20	4274.98	II
40	4306.80	II
20	4737.05	II
15	4981.35	II
25	5078.54	II
25	5152.14	II
18000	5350.46	I
15 d	5384.85	II
10	5410.97	II
25	5949.48	II
10	6179.98	II
10	6378.32	II
16 h	6549.84	I
10	6966.5	II
10	7815.80	I
20	8373.6	I
10	8474.27	I
10	8664.1	II
20	9130.	II
20	9130.5	I
40	9509.4	I
20	9930.4	I
30	10011.9	I
40	10488.80	I
1000	11512.82	I
150	12736.4	I
700	13013.2	I

Thorium Th Z = 90

150	1707.37	IV
200	1959.02	IV
200	2002.34	IV
200	2413.50	III
200	2427.94	III
200	2431.68	III
200	2441.24	III
500	2565.593	II
480	2692.415	II
520	2747.156	II
410	2752.166	II
800	2832.315	II
1200	2837.295	II
100	2848.084	I
550	2870.406	II
100	2936.086	I
100	2943.729	I
420	3049.092	II
450	3067.729	II
670	3078.828	II
480	3080.217	II
510	3108.296	II
100	3116.263	I
510	3119.526	II
510	3122.963	II
480	3125.507	II
100	3136.216	I
420	3139.306	II
420	3142.835	II
420	3175.726	II
1100	3180.193	II
770	3188.233	II
560	3221.292	II
560	3229.009	II
480	3235.84	II
590	3238.116	II
910	3256.274	II
180	3257.366	I
910	3262.668	II
620	3287.789	II
910	3291.739	II
620	3292.520	II
240	3301.650	I
480	3304.238	I
510	3321.450	II
840	3325.120	II
250	3330.476	I
620	3334.604	II
620	3337.870	II
310	3348.768	I
980	3351.228	II
620	3358.602	II
250	3374.974	I
1300	3392.035	II
200	3396.727	I
250	3398.544	I
200	3405.558	I
250	3413.012	I
390	3421.210	I
270	3423.989	I
980	3433.998	II
770	3435.976	II
1300	3469.920	II
170	3471.218	I
200	3486.552	I
670	3539.587	II
180	3544.018	I
170	3549.595	I
200	3555.013	I
530	3559.451	II
200	3576.557	I
270	3592.780	I
270	3598.120	I
980	3609.445	II
200	3612.427	I
480	3615.133	II
270	3635.943	I
210	3642.248	I
170	3649.735	I
220	3663.202	I
280	3669.968	I
700	3675.567	II
150	3682.486	I
170	3692.566	I
180	3698.105	I
340	3706.767	I
590	3719.435	I
770	3721.825	II
1300	3741.183	II
310	3747.539	I
650	3752.569	II
180	3770.056	I
590	3803.075	I
450	3828.384	I
840	3839.746	II
450	3863.405	II
210	3875.374	I

Intensity	Wavelength/Å	
340	3895.419	I
590	3929.669	II
200	3932.911	I
390	3967.392	I
200	3972.155	I
150	3980.089	I
530	3994.549	II
220	4008.210	I
220	4009.056	I
280	4012.495	I
4200	4019.129	II
250	4030.842	I
250	4036.047	I
250	4063.407	I
700	4086.520	II
700	4094.747	II
150	4100.341	I
840	4108.421	II
240	4112.754	I
280	4115.758	I
1100	4116.713	II
200	4127.411	I
200	4134.067	I
450	4149.986	II
620	4178.060	II
620	4208.890	II
110	4253.538	I
110	4260.333	I
480	4277.313	II
700	4282.042	II
130	4337.277	I
1300	4381.860	II
1100	4391.110	II
110	4498.940	I
280	4510.527	II
90	4723.438	I
50	4840.843	I
280	4863.163	II
260	5017.255	II
110	5067.974	I
120	5148.211	II
95	5216.596	II
110	5231.160	I
95	5247.654	II
60	5343.581	I
60	5587.026	I
95	5707.103	II
70	5760.551	I
85	5989.044	II
60	6169.822	I
50	6182.622	I
50	6274.116	II
50	6274.117	II
50	6355.911	II
60	6457.283	I
50	6462.614	I
50 h	6531.342	I
55	6989.656	I
30	7045.795	II
30	7084.171	I
30	7168.896	I
40	7191.132	II
35	7208.006	I
50	7525.508	II
30	7647.380	I
30	8330.451	I
40	8967.641	I
20	9833.42	I
20	10726.93	I
20	10942.24	II
30	11230.259	I
20	11984.67	II
20	17208.22	II
15	18811.88	I
10	22264.35	II

Thulium Tm Z = 69

5000	2185.94	III
360	2284.79	II
20000	2296.21	III
5000	2305.03	III
20000	2311.16	III
5000	2312.72	III
5000	2326.19	III
6000	2328.50	III
6000	2329.29	III
3000	2331.80	III
3000	2357.05	III
4000	2406.63	III
450	2409.02	II
450	2426.17	II
770	2480.13	II
30000	2489.44	III
2000	2504.71	III
1300	2509.08	II
3000	2519.78	III
130	2527.02	I
10000	2552.46	III
360	2552.76	I
540	2561.65	II
430	2588.27	II
170 h	2596.49	I
810	2607.06	II
730	2624.33	II
5000	2682.32	III
2000	2707.03	III
3000	2719.47	III
540	2721.19	II
3000	2724.44	III
4000	2727.56	III
680	2794.60	II
730	2797.27	II
2000	2806.77	III
580	2827.92	II
200	2854.17	I
1600	2869.23	II
1000	2947.72	III
490	2973.22	I
1000	2998.28	III
1500	3015.30	II
360	3081.12	I
7400	3131.26	II
2300	3133.89	II
1900	3151.04	II
1500	3157.34	II
450	3172.65	I
2300	3172.83	II
1200	3236.81	II
1600	3240.23	II
2300	3241.54	II
320	3246.96	I
1900	3258.05	II
1600	3266.64	II
1200	3267.40	II
1100	3276.81	II
1200	3283.40	II
1200	3285.61	II
2300	3291.00	II
2000	3302.46	II
1200	3309.80	II
230	3349.99	I
4000	3362.61	II
1700	3397.50	II
850	3410.05	I
340	3412.59	I
340	3416.59	I
6400	3425.08	II
340	3429.33	I
4900	3441.50	II
4900	3453.66	II
8500	3462.20	II
210	3467.51	I
340	3476.69	I
340	3480.98	I
420	3487.38	I
340	3499.95	I
250	3517.60	I
1700	3535.52	II
420	3537.91	I
210	3555.82	I
340	3560.92	I
420	3563.88	I
1300	3566.47	II
420	3567.36	I
280	3586.07	I
2100	3608.77	II
1000	3629.09	III
380	3638.41	I
1100	3668.09	II
4800	3700.26	II
3800	3701.36	II
7700	3717.91	I
2400	3734.12	II
5000	3744.06	I
1700	3751.81	I
6000	3761.33	II
4800	3761.91	II
7100	3795.75	II
770	3798.54	I
600	3807.72	I
290	3826.39	I
1300	3838.20	II
290	3840.87	I
8900	3848.02	II
6800	3883.13	I
1800	3883.44	II
5400	3887.35	I
440	3896.62	I
3500	3916.48	I
1500	3949.27	I
1500	3958.10	II
1800	3996.52	II
220	4024.23	I
380	4044.47	I
10000	4094.19	I
9500	4105.84	I
1100	4138.33	I
8800	4187.62	I
6000	4203.73	I
380	4222.67	I
3000	4242.15	II
270	4271.71	I
150	4298.36	I
2700	4359.93	I
1400	4386.43	I
200	4394.42	I
140	4396.50	I
120	4454.03	I
540	4481.26	II
150	4519.60	I
260	4522.57	II
110	4548.60	I
270	4599.02	I
300	4615.94	II
80	4626.33	II
95	4626.56	II
110	4634.26	II
120	4655.09	I
160	4681.92	I
120	4691.11	I
110	4724.26	I
680	4733.34	I
70	4759.90	I
80	4831.20	II
140	4957.18	I
160	5009.77	II
160	5034.22	II
150	5060.90	I
95	5113.97	I
80	5213.38	I
650	5307.12	I
80	5346.49	II
270	5631.41	I
520	5675.84	I
40	5684.76	II
35	5709.97	II
190	5764.29	I
35	5838.76	II
240	5895.63	I
140	5971.26	I
200	6460.26	I
95	6604.96	I
110	6779.77	I
120	6844.26	I
80	6845.76	I

Intensity	Wavelength/Å	
10	6937.37	I
10	7017.90	I
12	7034.34	I
10	7106.14	I
17	7272.62	I
14	7310.51	I
14	7432.18	I
75	7481.08	I
75	7490.20	I
140	7558.33	I
80	7731.53	I
40	7856.08	I
55	7927.51	I
110	7930.84	I
95	8017.90	I
27	8472.01	II
Tin Sn Z = 50		
7	169.47	II
150	361.01	V
100	753.01	III
200	910.92	III
500	956.25	IV
7	985.13	II
500	1019.72	IV
1000	1044.49	IV
1000	1073.41	IV
200	1089.35	V
8	1108.19	II
1000	1119.34	IV
1000	1139.29	III
1000	1158.33	III
200	1160.74	V
10	1161.43	II
1000	1184.25	III
2000	1210.52	III
9	1219.07	II
13	1223.70	II
11	1243.00	II
2000	1251.38	V
1000	1259.92	III
20	1290.86	II
200	1294.36	V
1000	1305.97	III
1000	1314.55	IV
20	1316.59	II
1000	1327.34	III
1000	1347.65	III
1000	1386.74	III
25	1400.52	II
1000	1437.52	IV
20	1475.15	II
9	1489.22	II
1000	1570.36	III
10 r	1737.21	I
15 r	1751.46	I
20 r	1764.98	I
30 r	1790.75	I
80 r	1804.60	I
15	1811.34	II
500	1811.71	III
40 r	1815.74	I
120 r	1823.00	I
9	1831.89	II
50 r	1848.75	I
200 r	1860.32	I
80	1886.05	I
100	1891.40	I
12	1899.91	II
50	1909.30	I
80	1925.31	I
500	1941.86	III
150	1952.15	I
50 h	1977.6	I
80	1984.20	I
50	2040.66	I
50	2054.03	I
70	2058.31	I
80	2068.58	I
100	2072.89	I
100	2073.08	I
200	2096.39	I
100	2100.93	I
100 r	2113.93	I
50	2121.26	I
40 r	2148.73	I
20 r	2151.43	I
30	2151.54	II
80	2171.32	I
150 r	2194.49	I
300 r	2199.34	I
400 r	2209.65	I
80 r	2231.72	I
400 r	2246.05	I
60	2251.17	I
400 r	2268.91	I
200 r	2286.68	I
600 r	2317.23	I
300 r	2334.80	I
1000 r	2354.84	I
22	2368.33	II
100	2408.15	I
800 r	2421.70	I
1000 r	2429.49	I
15	2448.98	II
300	2483.39	I
13	2483.48	II
10	2486.99	II
200	2495.70	I
400	2546.55	I
500 r	2571.58	I
200	2594.42	I
200 r	2661.24	I
700 r	2706.51	I
150	2779.81	I
1400 r	2839.99	I
1000 r	2863.32	I
700 r	3009.14	I
850 r	3034.12	I
12	3047.50	II
550 r	3175.05	I
550 r	3262.34	I
50	3283.21	II
110	3330.62	I
60	3351.97	II
10	3472.46	II
11	3575.45	II
280 r	3801.02	I
10	5332.36	II
20	5561.95	II
25	5588.92	II
500	5631.71	I
15	5799.18	II
50	5925.44	I
100	5970.30	I
150	6037.70	I
250	6069.00	I
100	6073.46	I
400	6149.71	I
200	6154.60	I
150	6171.50	I
100	6310.78	I
70	6453.50	II
25	6844.05	II
20	7191.40	II
10	7387.79	II
13	7741.80	II
100	7754.97	I
100 h	8030.5	I
200	8114.09	I
80	8357.04	I
300	8422.72	I
400	8552.60	I
50 h	8681.7	I
50 h	9410.86	I
80 h	9415.37	I
150	9616.40	I
50	9741.1	I
100 h	9742.8	I
300 h	9805.38	I
500	9850.52	I
54	10894.00	I
70	11191.85	I
56	11277.66	I
200	11454.59	I
200	11616.26	I
258	11739.78	I
96	11825.18	I
106	11835.82	I
254	11932.99	I
48	12009.50	I
111	12313.24	I
42	12530.87	I
42	12536.5	I
89	12888.5	I
187	12981.7	I
187	13018.5	I
68	13081.5	I
378	13460.2	I
144	13608.2	I
40	20861.7	I
4	24738.2	I
Titanium Ti Z = 22		
17	252.96	V
15	498.26	V
14	502.08	V
13	526.57	V
18	779.07	IV
20	1298.66	III
20	1298.97	III
23	1455.19	III
20	1467.34	IV
11	1717.40	V
10	1841.49	V
20	2067.56	IV
18	2103.16	IV
180	2273.28	I
190	2279.96	I
190	2305.67	I
22	2413.99	III
25	2516.05	III
360	2525.60	II
24	2527.84	III
210	2529.85	I
190	2531.25	II
190	2534.62	II
130	2535.87	II
23	2540.06	III
24	2563.44	III
23	2565.42	III
22	2567.56	III
270	2599.92	I
340	2605.15	I
510	2611.28	I
300	2619.94	I
640	2641.10	I
800	2644.26	I
950	2646.64	I
250	2742.32	I
250	2802.50	I
190	2841.94	II
180	2877.44	II
280	2884.11	II
450	2912.08	I
340	2928.34	I
1100	2942.00	I
1300	2948.26	I
1600	2956.13	I
22	2984.75	III
1300 d	3066.22	II
1100	3072.97	II
1600	3075.22	II
2300	3078.64	II
3600	3088.02	II
720	3119.72	I
500	3161.20	II
780	3161.77	II
1000	3162.57	II
1600	3168.52	II
2400	3186.45	I
1000	3190.87	II
3100	3191.99	I
3800	3199.92	I
780	3202.54	II
1100	3217.06	II

Intensity	Wavelength/Å	
1300	3222.84	II
6600	3234.52	II
5200	3236.57	II
4100	3239.04	II
2600	3241.99	II
1200	3248.60	II
1200	3252.91	II
1200	3254.25	II
1200	3261.60	II
840	3314.42	I
2900	3322.94	II
2100	3329.46	II
1800	3335.20	II
1100	3340.34	II
5700	3341.88	I
4300	3349.04	II
12000	3349.41	II
4100	3354.64	I
7200	3361.21	II
1100	3370.44	I
4300	3371.45	I
5700	3372.80	II
2900 d	3377.48	I
1400	3380.28	II
5700	3383.76	II
1400	3385.95	I
1400	3387.84	II
1100	3394.58	II
890	3444.31	II
600	3461.50	II
600	3477.18	II
480	3491.05	II
890	3504.89	II
600	3510.84	II
17	3576.44	IV
600	3610.16	I
4800	3635.46	I
6600	3642.68	I
7200	3653.50	I
600	3671.67	I
3100	3685.20	II
600	3689.91	I
2900	3729.82	I
3300	3741.06	I
330	3741.64	II
5200	3752.86	I
3300	3759.30	II
2900	3761.32	II
840	3786.04	I
500	3882.89	I
530	3900.54	II
2600	3904.78	I
500	3913.46	II
500	3914.34	I
15	3915.47	III
1100	3924.53	I
890	3929.88	I
1100	3947.78	I
4500	3948.67	I
4500	3956.34	I
5200	3958.21	I
950	3962.85	I
950	3964.27	I
4800	3981.76	I
570	3982.48	I
5700	3989.76	I
7800	3998.64	I
950	4008.93	I
1200	4024.57	I
840	4078.47	I
890	4286.01	I
840	4287.40	I
950	4289.07	I
840	4290.94	I
840	4295.76	I
2000	4298.66	I
200	4300.05	II
2900	4300.56	I
4100	4301.09	I
6000	4305.92	I
1200	4314.80	I
330	4395.04	II
890	4427.10	I
230	4443.80	II
840	4449.15	I
550	4450.90	I
840	4453.32	I
950	4455.33	I
1100	4457.43	I
240	4468.50	II
530	4481.26	I
780	4512.74	I
1000	4518.03	I
1000	4522.80	I
780	4527.31	I
6000	4533.24	I
240	4533.97	II
3600	4534.78	I
2400	4535.58	I
1200	4535.92	I
1200	4536.05	I
720	4544.69	I
950	4548.77	I
240	4549.63	II
15	4549.84	III
950	4552.46	I
720	4555.49	I
240	4571.98	II
15 d	4572.20	III
950	4617.27	I
480	4623.09	I
720	4656.47	I
840	4667.59	I
950	4681.92	I
470	4840.87	I
400	4885.08	I
380	4899.91	I
5800	4981.73	I
4600	4991.07	I
4000	4999.51	I
3600	5007.21	I
3200 d	5014.19	I
840	5020.03	I
840	5022.87	I
1200	5035.91	I
840	5036.47	I
740	5038.40	I
1200	5039.95	I
1400	5064.66	I
1100	5173.75	I
1300	5192.98	I
1400	5210.39	I
17	5278.12	III
20	5398.93	IV
340	5512.53	I
270	5514.35	I
320	5514.54	I
250	5644.14	I
130	5675.44	I
95	5689.47	I
95	5715.13	I
85	5739.51	I
400	5866.46	I
230	5899.32	I
120	5918.55	I
150	5922.12	I
120	5941.76	I
300	5953.17	I
200	5965.84	I
270	5978.56	I
340	5999.04	I
110	6064.63	I
120	6085.23	I
120	6091.17	I
120	6126.22	I
17	6246.65	IV
380	6258.10	I
380	6258.70	I
300	6261.10	I
55	6546.28	I
65	6554.23	I
75	6556.07	I
18	6621.58	III
18	6667.99	III
80	6743.12	I
20	7072.64	III
18	7084.57	III
260	7209.44	I
130	7244.86	I
130	7251.72	I
120	7344.72	I
90	7357.74	I
60	7364.11	I
60	7978.88	I
55	8024.84	I
75	8364.24	I
100	8377.85	I
100	8382.54	I
75	8396.87	I
120	8412.36	I
170	8426.52	I
490	8434.94	I
240	8435.70	I
20	8466.87	III
90	8675.39	I

Tungsten W Z = 74

5800	2001.71	II
13000	2008.07	II
5100	2009.98	II
4100	2010.23	II
4100	2014.23	II
7300	2026.08	II
15000	2029.98	II
5300	2049.63	II
9700	2079.11	II
6100	2094.75	II
2100	2118.87	II
2400	2121.59	II
1500	2166.32	II
1300	2204.48	II
460	2249.80	I
510	2277.58	I
530 d	2294.49	I
340	2309.02	I
440	2313.17	I
460	2321.63	I
390 d	2326.56	I
320	2354.61	I
580	2360.44	I
850	2363.07	I
510	2374.47	I
670	2384.82	I
730	2397.09	II
560	2397.73	I
560	2397.98	I
1700 d	2405.58	I
610	2415.68	I
870	2424.21	I
1800	2435.96	I
580	2444.06	I
780	2451.48	II
870	2452.00	I
630	2454.98	I
780	2455.51	I
780	2456.53	I
1100	2459.30	I
1400	2466.85	I
480	2472.51	I
1200	2474.15	I
870	2480.13	I
1500	2481.44	I
480 d	2482.10	I
580	2484.74	I
390	2487.50	I
390	2489.23	II
630	2495.26	I
680	2504.70	I
75	2510.47	II
310	2520.46	I
780	2521.32	I
270	2522.04	II
780	2523.41	I
430	2527.76	I
780	2533.64	I

Intensity	Wavelength/Å	
1200	2547.14	I
780	2550.38	I
2700	2551.35	I
730	2561.97	I
870	2580.49	I
390	2584.39	I
390	2589.17	II
370	2601.96	I
680	2606.39	I
370	2608.32	I
970	2613.08	I
480	2613.82	I
400	2620.25	I
400	2622.21	I
400	2625.22	I
400	2632.48	I
400	2632.70	I
810	2633.13	I
400 d	2638.62	I
650	2646.18	I
400	2646.73	I
1600	2656.54	I
810	2662.84	I
810	2671.47	I
650	2677.28	I
2100	2681.42	I
650	2695.67	I
650	2699.59	I
400	2700.01	I
400	2706.58	I
400	2708.59	I
400 d	2708.80	I
400	2715.50	I
2100	2718.91	I
2600	2724.35	I
400	2725.03	I
650	2748.84	I
400	2762.34	I
400	2764.27	II
400	2769.74	I
810	2770.88	I
810	2774.00	I
810	2774.48	I
810	2792.70	I
400	2799.93	I
810	2818.06	I
1600	2831.38	I
810	2833.63	I
810	2848.02	I
1500	2896.44	I
690	2935.00	I
2400	2944.40	I
2400	2946.99	I
730 d	2979.71	I
360	3013.79	I
520	3016.47	I
770	3017.44	I
210	3024.93	I
310 d	3026.67	I
440 d	3041.73	I
270	3043.80	I
440	3046.44	I
810	3049.69	I
180	3073.28	I
180 d	3084.83	I
370	3093.50	I
240	3107.23	I
240	3108.02	I
230	3117.57	I
260	3120.18	I
290	3163.42	I
320	3176.60	I
190	3181.82	I
390	3191.57	I
390	3198.84	I
520	3207.25	I
1000	3215.56	I
190	3232.49	I
210	3254.36	I
210	3259.66	I
210 d	3266.62	I
730	3300.82	I
440	3311.38	I
440	3326.20	I
440	3331.69	I
390	3373.75	I
230	3429.59	I
240	3443.00	I
400	3495.24	I
650	3545.22	I
240	3570.65	I
1900	3617.52	I
650	3682.08	I
400	3683.30	I
570	3688.06	I
810	3707.92	I
510	3757.92	I
680	3760.13	I
1000	3768.45	I
340	3773.71	I
1000	3780.77	I
290	3809.22	I
190	3810.38	I
260	3810.79	I
1400	3817.48	I
1100	3835.06	I
730	3846.22	I
1800	3867.99	I
730	3881.41	I
8600	4008.75	I
540	4015.22	I
910	4045.59	I
730	4069.95	I
5000	4074.36	I
1000	4102.70	I
540	4137.46	I
450	4171.17	I
220	4207.05	I
250	4219.37	I
540	4244.36	I
1400	4269.38	I
4100	4294.61	I
2200	4302.11	I
200	4378.48	I
180	4384.85	I
200	4408.28	I
640	4484.19	I
170	4588.73	I
640	4659.87	I
640	4680.51	I
790	4843.81	I
380	4886.90	I
220	4982.59	I
820	5053.28	I
770	5224.66	I
220	5514.68	I
65	5648.37	I
55	5735.09	I
45	5804.85	I
40	5902.64	I
55	5947.57	I
55	5965.86	I
55	6012.78	I
40	6021.52	I
45	6292.02	I
35	6404.21	I
40	6445.12	I
17	6611.62	I
13	6678.42	I
15	6693.08	I
13	6984.27	I
15	7140.52	I
9	7162.64	I
11	7200.16	I
10	7278.24	I
15	7285.81	I
15	7296.55	I
10	7509.00	I
17	7569.92	I
17	7614.15	I
13	7688.97	I
11	7784.15	I
22	8017.19	I
22	8055.64	I
13	8123.82	I
10	8338.08	I
27	8585.11	I
10	8594.42	I
13	8865.53	I

Uranium U Z = 92

440	2565.41	II
610	2635.53	II
830	2793.94	II
870	2802.56	II
630	2807.05	II
630	2817.96	II
870	2821.12	II
680	2828.90	II
920	2832.06	II
970	2865.68	II
1200	2889.62	II
780	2906.80	II
780	2908.28	II
580	2931.41	II
530 p	2940.37	II
1300	2941.92	II
830	2943.90	II
580	2956.06	II
580	2967.94	II
580	2971.06	II
530	2984.61	II
630	3022.21	II
630	3031.99	II
580	3050.20	II
630	3057.91	II
630	3062.54	II
580	3072.78	II
580	3093.01	II
580	3102.39	II
970	3111.62	II
530	3119.35	II
680	3124.95	II
530	3139.61	II
680	3149.24	II
530	3153.11	II
730	3229.50	II
680	3232.16	II
730	3291.33	II
1100	3305.89	II
730	3390.38	I
580	3424.56	II
580	3435.49	I
630	3466.30	I
680	3482.49	II
1600	3489.37	I
530	3496.41	II
630	3500.08	I
780	3507.34	I
1600	3514.61	I
630	3533.57	II
530	3540.47	II
1200	3550.82	II
680	3555.32	I
1200	3561.80	I
2300	3566.59	I
530	3569.08	I
630	3578.72	II
3200	3584.88	I
840	3638.20	I
2800	3670.07	II
1100	3701.52	II
600	3738.04	II
680	3746.42	II
950	3748.68	II
600	3751.17	I
1900	3782.84	II
570	3793.10	II
1900	3811.99	I
750	3826.51	II
2000	3831.46	II
1200	3839.63	I
2400	3854.64	II
4900	3859.57	II
1900	3865.92	II

Intensity	Wavelength/Å	
1500	3871.03	I
1000	3881.45	II
2200	3890.36	II
2000	3932.02	II
1200	3943.82	I
1200	3985.79	II
1000	4042.75	I
1600	4050.04	II
880	4062.54	II
2200	4090.13	II
810	4116.10	II
880	4153.97	I
1400	4171.59	II
1000	4241.67	II
600	4472.33	II
620	4543.63	II
170	4689.07	II
150	4756.81	I
110	5008.21	II
170	5027.38	I
80	5160.32	II
70	5280.38	I
80	5475.70	II
70	5480.26	II
70	5481.20	II
160	5492.95	II
70	5780.59	I
70	5798.53	II
230	5915.39	I
100	5976.32	I
90	6077.29	I
55	6372.46	I
90	6395.42	I
110	6449.16	I
90	6826.92	I
45	7533.93	I
50	7881.94	I
35	8445.39	I
75	8607.95	I
30	8757.76	I
100	10554.93	I
75	11167.84	I
100	11384.13	I
100	11859.42	I
100	11908.83	I
100	12250.46	I
100	13185.16	I
75	13306.23	I
100	13961.58	I
75	18634.43	I
75	21910.22	I
Vanadium V Z = 23		
20	225.46	V
20	251.66	V
20	286.84	V
35	483.01	V
50	633.94	III
200	677.34	IV
500	684.37	IV
400	737.85	IV
100	864.27	III
500	1006.46	III
500	1149.94	III
100	1426.65	IV
1000	1643.03	III
1000	1650.14	III
100	1680.20	V
1000	1694.78	III
1000	1760.07	III
1000	1788.26	III
1000	1794.60	III
1000	1812.19	III
300	1861.56	IV
500	1939.06	IV
400	1951.43	IV
500	1997.72	IV
2100	2092.44	I
500	2268.30	IV
1000	2292.86	III
2500	2330.42	III
2500	2371.06	III
1000	2382.46	III
240	2507.78	I
410	2526.22	I
210	2527.90	II
80 h	2570.72	IV
230	2574.02	I
250	2593.05	III
250	2595.10	III
80 h	2645.54	IV
180	2661.42	I
1100	2687.96	II
680	2700.94	II
530	2706.17	II
640	2715.69	II
180	2731.35	I
240	2864.36	I
900	2891.64	II
900	2892.66	II
1400	2893.32	II
900	2906.46	II
2400	2908.82	II
710	2923.62	I
2400	2924.02	II
1700	2924.64	II
900	2941.37	II
1100	2944.57	II
410	2962.77	I
600	2968.38	II
1200	3056.33	I
1400	3060.46	I
2400	3066.38	I
3800	3093.11	II
3000	3102.30	II
2600	3110.71	II
2000	3118.38	II
1500	3125.28	II
3200	3183.41	I
5300	3183.98	I
3800	3185.40	I
410	3187.71	II
530	3188.51	II
750	3190.68	II
1100	3267.70	II
900	3271.12	II
750	3276.12	II
80 h	3514.25	IV
560	3517.30	II
560	3533.68	I
560	3545.20	II
560	3556.80	II
560	3589.76	II
490	3592.02	II
560	3592.53	I
100	3679.86	III
1300	3688.07	I
1000	3690.28	I
1500	3692.22	I
1000	3695.86	I
3800	3703.58	I
1800	3704.70	I
320	3715.47	II
250	3727.34	II
280	3732.76	II
520	3790.32	I
1100	3794.96	I
570	3799.91	I
570	3803.47	I
1000	3813.49	I
1300	3818.24	I
1700	3828.56	I
2600	3840.75	I
1200	3855.37	I
3000	3855.84	I
1300	3864.86	I
1500	3875.08	I
700	3890.18	I
2400	3902.25	I
700	3909.89	I
540	3990.57	I
430	3998.73	I
170	4005.71	II
1100	4090.58	I
1800	4092.69	I
890	4095.49	I
2800	4099.80	I
590	4102.16	I
2800	4105.17	I
2300	4109.79	I
8900	4111.78	I
4300	4115.18	I
1800	4116.47	I
2000	4123.57	I
3100	4128.07	I
3100	4132.02	I
2300	4134.49	I
20	4200.32	V
360	4232.46	I
560	4268.64	I
460	4271.55	I
460	4276.96	I
430	4284.06	I
460	4330.02	I
510	4332.82	I
760	4341.01	I
1000	4352.87	I
12000	4379.24	I
7000	4384.72	I
4800	4389.97	I
3600	4395.23	I
1400	4400.58	I
2300	4406.64	I
2800	4407.64	I
3600	4408.20	I
4600	4408.51	I
640	4416.47	I
640	4421.57	I
640	4437.84	I
830	4441.68	I
640	4444.21	I
610	4452.01	I
1000	4459.76	I
2000	4460.29	I
610	4462.36	I
510	4577.17	I
640	4580.40	I
830	4586.36	I
1300	4594.11	I
230	4619.77	I
100	4635.18	I
130	4646.40	I
160	4670.49	I
130	4776.36	I
110	4786.51	I
130	4796.92	I
130	4807.53	I
130	4827.45	I
150	4831.64	I
120	4832.43	I
320	4851.48	I
480	4864.74	I
620	4875.48	I
740	4881.56	I
110	5128.53	I
110	5138.42	I
110	5192.99	I
110	5194.83	I
110	5234.07	I
110	5240.87	I
100	5401.93	I
140	5415.26	I
140	5584.50	I
100	5592.42	I
200	5624.60	I
400	5627.64	I
110	5657.44	I
110	5668.36	I
310	5670.85	I
1200	5698.52	I
920	5703.56	I
570	5706.98	I
850	5727.03	I
230	5731.25	I
230	5737.06	I

Intensity	Wavelength/Å	
450	6039.73	I
480	6081.44	I
1300	6090.22	I
600	6119.52	I
450	6199.19	I
450	6216.37	I
430	6230.74	I
710	6243.10	I
280	6251.82	I
130	6268.82	I
170	6274.65	I
200	6285.16	I
200	6292.83	I
170	6296.49	I
110	6531.43	I
65 c	6753.00	I
50 c	6766.49	I
40	6784.98	I
40	7338.92	I
35	7356.54	I
29 c	8027.39	I
120 w	8116.80	I
70 c	8161.07	I
60 c	8919.85	I
Xenon Xe Z = 54		
8	657.8	III
8	660.1	III
9	673.8	III
9	674.0	III
9	676.6	III
10	694.0	III
20	698.5	III
12	705.1	III
10	721.2	III
15	731.0	III
10	733.3	III
350	740.41	II
15	742.6	III
10	756.0	III
10	761.5	III
10	769.1	III
25	779.1	III
15	792.9	III
12	796.1	III
15	802.0	III
350	803.07	II
25	823.2	III
30	824.9	III
25	853.0	III
600	880.80	II
350	885.54	II
15	889.3	III
20	894.0	III
20	896.0	III
600	925.87	II
250	935.40	II
10	965.5	III
800	972.77	II
700	976.68	II
35	1003.4	III
35	1017.7	III
500	1032.44	II
700	1037.68	II
1100	1041.31	II
10	1047.8	III
1000	1048.27	II
1200	1051.92	II
12	1066.4	III
2000	1074.48	II
600	1083.86	II
1200	1100.43	II
30	1130.3	III
600	1158.47	II
250	1169.63	II
800 p	1183.05	II
250	1192.04	I
25	1232.1	III
600	1244.76	II
250	1250.20	I
1000	1295.59	I
600	1469.61	I
80	2668.98	III
100	2717.33	III
30	2814.45	III
40	2815.91	III
30	2827.45	III
40	2847.65	III
30	2862.40	III
200	2864.73	II
80 w	2871.10	III
60 w	2871.24	III
30	2871.7	III
150 h	2895.22	II
30	2896.62	III
50	2906.6	III
40	2911.89	III
80 w	2912.36	III
40	2940.2	III
60	2945.2	III
40	2947.5	III
40	2948.1	III
80 w	2970.47	III
400	2979.32	II
40	2992.87	III
30	3004.25	III
100 h	3017.43	II
100	3023.81	III
40	3083.5	III
50	3091.1	III
30	3106.46	III
300	3128.87	II
100 w	3138.3	III
80 c	3150.82	III
40	3185.2	III
100	3242.86	III
80	3268.98	III
30	3287.82	III
80 w	3301.55	III
40	3331.6	III
30	3358.0	III
200 h	3366.72	II
80	3384.12	III
2	3400.07	I
2	3418.37	I
2	3420.00	I
3	3442.66	I
60	3444.2	III
70	3454.2	III
100 w	3458.7	III
100 h	3461.26	II
40	3468.22	III
4	3469.81	I
4	3472.36	I
5	3506.74	I
80	3522.83	III
50	3542.3	III
10	3549.86	I
50	3552.1	III
10	3554.04	I
40	3561.4	III
100	3579.7	III
80	3583.6	III
100 w	3595.4	III
100	3606.06	III
40	3607.0	III
15	3610.32	I
8	3613.06	I
100 w	3615.9	III
40	3623.1	III
600	3624.08	III
6	3633.06	I
10	3669.91	I
50	3676.67	III
40	3685.90	I
40	3693.49	I
40	3776.3	III
300	3781.02	III
100	3841.5	III
200	3877.8	III
60	3880.5	III
100 l	3907.91	II
500	3922.55	III
300	3950.59	III
100	4037.59	II
200	4050.07	III
200 l	4057.46	II
60	4060.4	III
100 h	4098.89	II
100	4109.1	III
100	4145.7	III
200 l	4158.04	II
1000 h	4180.10	II
500 h	4193.15	II
300 h	4208.48	II
100 h	4209.47	II
300 h	4213.72	II
100	4215.60	II
300 h	4223.00	II
400 h	4238.25	II
500 h	4245.38	II
100 l	4251.57	II
30	4285.9	III
500 h	4296.40	II
500 h	4310.51	II
1000 l	4330.52	II
200 h	4369.20	II
100 l	4373.78	II
500 h	4393.20	II
500 l	4395.77	II
200 l	4406.88	II
150 l	4416.07	II
50	4434.2	III
500 h	4448.13	II
100 w	4462.1	III
1000 h	4462.19	II
500 l	4480.86	II
100 l	4521.86	II
100 w	4569.1	III
100 w	4570.1	III
100 w	4641.4	III
30	4673.7	III
60	4683.57	III
30	4723.60	III
600	4734.152	I
100 w	4757.3	III
150	4792.619	I
500	4807.02	I
400	4829.71	I
300	4843.29	I
40	4869.5	III
500	4916.51	I
500	4923.152	I
200 l	4971.71	II
400	4972.71	II
300	4988.77	II
100 l	4991.17	II
200	5028.280	I
200	5044.92	II
1000	5080.62	II
300	5122.42	II
100	5125.70	II
100	5178.82	II
300	5188.04	II
400	5191.37	II
100	5192.10	II
60	5239.0	III
500	5260.44	II
500	5261.95	II
2000	5292.22	II
300	5309.27	II
1000	5313.87	II
2000	5339.33	II
200	5363.20	II
30	5367.1	III
200	5368.07	II
500	5372.39	II
100	5392.80	I
50	5401.0	III
3000	5419.15	II
800	5438.96	II
300	5445.45	II
200	5450.45	II
400	5460.39	II
1000	5472.61	II

Intensity	Wavelength/Å	
100 l	5494.86	II
40	5524.4	III
200	5525.53	II
600	5531.07	II
100	5566.62	I
300	5616.67	II
300	5659.38	II
600	5667.56	II
150	5670.91	II
100	5695.75	I
200	5699.61	II
200	5716.10	II
500	5726.91	II
500	5751.03	II
300	5758.65	II
300	5776.39	II
100	5815.96	II
300	5823.89	I
150	5824.80	I
100	5875.02	I
300	5893.29	II
100	5894.99	I
200	5905.13	II
100	5934.17	I
500	5945.53	II
300	5971.13	II
2000	5976.46	II
200	6008.92	II
1000	6036.20	II
2000	6051.15	II
600	6093.50	II
1500	6097.59	II
400	6101.43	II
100	6115.08	II
100	6146.45	II
150	6178.30	I
120	6179.66	I
300	6182.42	I
500	6194.07	II
100	6198.26	I
60	6205.97	III
100	6220.02	II
25	6221.7	III
60	6238.2	III
60	6259.05	III
500	6270.82	II
400	6277.54	II
100	6284.41	II
100	6286.01	I
250	6300.86	II
500	6318.06	I
400	6343.96	II
600	6356.35	II
200	6375.28	II
100	6397.99	II
300	6469.70	I
150	6472.84	I
120	6487.76	I
100	6498.72	I
200 h	6504.18	I
300	6512.83	II
200	6528.65	II
100	6533.16	I
1000	6595.01	II
100	6595.56	I
400	6597.25	II
100	6598.84	II
150	6668.92	I
300	6694.32	II
200	6728.01	I
150	6788.71	II
100	6790.37	II
1000	6805.74	II
200	6827.32	I
100	6872.11	I
300	6882.16	I
80	6910.22	II
100	6925.53	I
800 h	6942.11	II
100	6976.18	I
2000	6990.88	II
150	7082.15	II
500	7119.60	I
50 s	7147.50	II
200	7149.03	II
500	7164.83	II
100	7284.34	II
200	7301.80	II
200	7339.30	II
100	7386.00	I
150	7393.79	I
300	7548.45	II
200	7584.68	I
80	7618.57	II
500	7642.02	I
100	7643.91	I
200	7670.66	II
60	7787.04	II
100	7802.65	I
100	7881.32	I
300	7887.40	I
500	7967.34	I
100	8029.67	I
200	8057.26	I
150	8061.34	I
100	8101.98	I
150 h	8151.80	II
100	8171.02	I
700	8206.34	I
10000	8231.635	I
500	8266.52	I
7000	8280.116	I
2000	8346.82	I
100	8347.24	II
2000	8409.19	I
50 h	8515.19	II
200	8576.01	I
50 h	8604.23	II
250	8648.54	I
100	8692.20	I
200	8696.86	I
50 h	8716.19	II
300	8739.39	I
100	8758.20	I
5000	8819.41	I
300	8862.32	I
200	8908.73	I
200	8930.83	I
1000	8952.25	I
100	8981.05	I
200	8987.57	I
400	9045.45	I
500	9162.65	I
100	9167.52	I
100	9374.76	I
200	9513.38	I
50 h	9591.35	II
150	9685.32	I
50 l	9698.68	II
100	9718.16	I
2000	9799.70	I
3000	9923.19	I
100	10838.37	I
90	11742.01	I
375	12235.24	I
100	12257.76	I
300	12590.20	I
2500	12623.391	I
250	13544.15	I
2000	13657.055	I
1250	14142.444	I
800	14240.96	I
375	14364.99	I
140	14660.81	I
3000	14732.806	I
100	15099.72	I
2500	15418.394	I
150	15557.13	I
250	15979.54	I
100	16039.90	I
1000	16053.28	I
125	16554.49	I
1500	16728.15	I
1500	17325.77	I
350	18788.13	I
150	20187.19	I
3000	20262.242	I
250	21470.09	I
1250	23193.33	I
110	23279.54	I
1800	24824.71	I
175	25145.84	I
2000	26269.08	I
2500	26510.86	I
250	28381.54	I
750	28582.25	I
300	29384.41	I
150	29448.06	I
100	29649.58	I
100	29813.62	I
600	30253.14	I
1500	30475.46	I
100	30504.12	I
500	30794.18	I
6000	31069.23	I
125	31336.01	I
550	31607.91	I
100	32293.08	I
1800	32739.26	I
3500	33666.69	I
150	34014.67	I
450	34335.27	I
170	34744.00	I
5000	35070.25	I
110	35246.92	I
250	36209.21	I
150	36231.74	I
450	36508.36	I
850	36788.83	I
140	38685.98	I
175	38737.82	I
270	38939.60	I
120	39955.14	I

Ytterbium Yb Z = 70

1000	1050.24	IV
1000	1054.46	IV
5000	1134.43	IV
900	1316.04	IV
800	1326.36	IV
900	1350.26	IV
80	1561.42	III
80 h	1765.21	III
800	1791.06	IV
100	1863.32	III
800	1873.91	III
500	1898.25	III
500	1998.82	III
900	2116.65	IV
2500	2116.67	II
800	2123.32	IV
3000	2126.74	II
800	2139.99	IV
20000	2144.77	IV
15000	2154.18	IV
370	2161.60	II
850	2185.71	II
640	2224.46	II
300	2240.11	III
300	2305.32	III
140	2320.81	II
170	2390.74	II
460	2464.50	I
140	2512.06	II
270	2538.67	II
2000	2567.61	III
1000	2579.57	III
800	2599.14	III
600	2621.11	III
1000	2642.56	III
1000	2651.74	III
700	2652.25	III
990	2653.75	II
200	2665.04	II
2000	2666.13	III

Intensity	Wavelength/Å	
2000	2666.99	III
390	2671.96	I
390	2672.66	II
170	2718.35	II
230	2748.66	II
1300	2750.48	II
170	2776.28	II
600	2795.60	III
1000	2803.43	III
600	2816.92	III
1000	2818.72	III
140	2821.15	II
190	2830.99	II
230 h	2847.18	II
360	2851.13	II
430	2859.80	II
140	2861.21	II
200	2867.06	II
45	2873.49	I
200	2888.04	II
3600	2891.38	II
600	2898.30	III
1000	2906.31	III
170	2914.21	II
140	2915.28	II
280	2919.35	II
35	2934.36	I
140	2945.91	II
2000	2970.56	II
200	2983.99	II
170	2994.80	II
800	2998.00	III
310	3005.77	II
160	3017.56	II
160	3026.67	II
2000	3029.49	III
920	3031.11	II
3000	3092.50	III
28	3100.74	I
170	3107.90	II
190	3117.81	II
4000	3126.01	III
1000	3138.58	III
230	3140.94	II
28	3162.29	I
800	3191.35	III
390	3192.88	II
240	3201.16	II
2000	3228.58	III
35	3239.58	I
18000	3289.37	II
130	3305.25	I
140	3305.73	II
80	3319.41	I
2000	3325.51	III
240	3337.17	II
280 d	3342.93	II
240	3375.48	II
2000	3384.01	III
140	3387.50	I
50	3412.45	I
140	3418.39	I
360	3426.04	I
240	3431.11	I
85	3452.40	I
500	3454.08	II
190 d	3458.29	II
360	3460.27	I
2400	3464.37	I
500	3476.30	II
500	3478.84	II
50	3517.00	I
230	3520.29	II
35	3559.03	I
200	3560.33	II
170	3560.70	II
360	3585.47	II
200	3619.80	II
240	3637.76	II
70	3648.15	I
90	3655.73	I
240	3669.69	II
140	3675.08	II
32000	3694.19	II
70	3700.58	I
400	3711.91	III
180	3734.69	I
550	3770.10	I
80	3774.32	I
60 h	3791.74	I
170	3839.91	I
340	3872.85	I
340	3900.85	I
140	3911.27	I
500	3931.23	III
32000	3987.99	I
930	3990.88	I
50	4007.36	I
2000	4028.14	III
70	4052.28	I
440	4089.68	I
470	4149.07	I
120	4174.56	I
340	4180.81	II
300	4213.64	III
150 d	4218.56	II
120	4231.97	I
70	4277.74	I
120	4305.97	I
60 h	4393.69	I
60 h	4430.21	I
440	4439.19	I
85 h	4482.42	I
100	4517.58	III
85 h	4563.95	I
640	4576.21	I
200	4582.36	I
70	4589.21	I
140	4590.83	I
40	4684.27	I
190	4726.08	II
170 h	4781.87	I
170	4786.61	II
35	4816.43	I
40	4837.46	I
40 h	4894.60	I
27	4912.36	I
710	4935.50	I
140	4966.90	I
30	5067.80	I
70	5069.14	I
220	5074.34	I
50	5076.74	I
60	5196.08	I
85	5211.60	I
100	5244.11	I
150 h	5277.04	I
170	5335.15	II
30 h	5351.29	I
150	5352.95	II
30	5363.66	I
40	5449.27	II
60	5481.92	I
40	5505.49	I
17	5524.54	I
85 h	5539.05	I
2400	5556.47	I
60	5651.98	II
220	5719.99	I
27	5771.66	II
35	5833.99	II
35	5837.14	II
27	5854.51	I
17	5989.33	I
40	5991.51	II
60	6152.57	II
60	6274.78	II
200	6328.52	III
35 h	6400.35	I
35 h	6417.91	I
340	6489.06	I
180	6667.82	I
25	6727.61	II
690	6799.60	I
9 h	7244.41	I
8 h	7305.22	I
10 h	7313.05	I
16 h	7350.04	I
25	7448.28	I
30 h	7527.46	I
750	7699.48	I
100	7971.46	III
70 h	8922.56	II
200	10110.60	III
100	10830.36	III

Yttrium Y Z = 39

150	264.64	IV
150	273.03	IV
900	333.09	V
500	333.80	V
400	335.14	V
500	336.62	V
500	339.02	V
500	344.59	V
900	355.86	IV
300	370.42	IV
300	372.05	V
400	379.96	V
500	386.82	IV
300	403.45	V
300	420.74	V
600	425.03	IV
300	473.10	IV
4000	584.98	V
2000	630.97	V
5000	805.20	III
7000	809.92	III
15000	989.21	III
25000	996.37	III
5000	1314.51	III
4000	1334.04	III
4000	2068.98	III
10000	2127.98	III
16000	2191.16	III
350	2243.06	II
10000	2284.34	III
10000	2327.31	III
50	2354.20	I
50000	2367.23	III
40000	2414.64	III
560	2422.20	II
60	2694.21	I
95	2723.00	I
70	2742.53	I
140	2760.10	I
90000	2817.04	III
45	2822.56	I
70	2854.43	II
95	2886.48	I
160	2919.05	I
99000	2946.01	III
390	2948.40	I
350	2964.96	I
480	2974.59	I
750	2984.26	I
140	2996.94	I
130	3021.73	I
190	3045.37	I
95	3095.88	II
110	3173.06	II
220	3179.41	II
70	3191.31	I
2300	3195.62	II
2200	3200.27	II
2200	3203.32	II
3900	3216.69	II
6200	3242.28	II
4700	3327.89	II
85	3388.59	I
85	3412.47	I
170	3485.73	I
1700	3496.09	II
3900	3549.01	II
130	3551.80	I

Intensity	Wavelength/Å	
540	3552.69	I
170	3558.76	I
190	3571.43	I
260	3576.05	I
3300	3584.52	II
300	3587.75	I
100	3589.69	I
2800	3592.92	I
10000	3600.73	II
6200	3601.92	II
7800	3611.05	II
4300	3620.94	I
1900	3628.71	II
7800	3633.12	II
3000	3664.61	II
170	3692.53	I
13000	3710.30	II
1200	3747.55	II
10000	3774.33	II
1400	3776.56	II
7400	3788.70	II
1300	3818.35	II
4000	3832.88	II
80	3876.82	I
480	3878.28	II
4400	3950.36	II
3600	3982.60	II
940	4039.83	I
2400	4047.64	I
9400	4077.38	I
2000	4083.71	I
9900	4102.38	I
8900	4128.31	I
7500	4142.85	I
100 h	4157.63	I
2400	4167.52	I
2000	4174.14	I
8000	4177.54	II
160	4217.80	I
280 h	4220.63	I
600	4235.73	II
2200	4235.94	I
300	4251.20	I
360 h	4302.30	I
2800	4309.63	II
110	4330.78	I
440 h	4348.79	I
120	4357.73	I
800	4358.73	II
120	4366.03	I
12000	4374.94	II
150 h	4375.61	I
100	4387.74	I
1800	4398.02	II
890	4422.59	II
100	4443.66	I
130	4446.63	I
170	4475.72	I
180	4476.96	I
160	4477.45	I
110	4487.28	I
300	4487.47	I
500	4505.95	I
890	4527.25	I
440	4527.80	I
100	4544.32	I
100	4559.37	I
130	4596.55	I
95	4604.80	I
2000	4643.70	I
200 h	4658.32	I
2000	4674.84	I
180	4696.81	I
170	4728.53	I
160	4752.79	I
410	4760.98	I
120	4781.04	I
170	4786.89	I
180	4799.30	I
140	4819.64	I
120	4822.13	I
770	4839.87	I
550	4845.68	I
410	4852.69	I
120	4854.25	I
890	4854.87	II
330	4859.84	I
1900	4883.69	II
95	4893.44	I
1100	4900.12	II
100	4906.11	I
150	4921.87	I
120	4974.30	I
100	5006.97	I
75	5070.21	I
75	5072.19	I
1100	5087.42	II
180	5135.20	I
960	5200.41	II
1500	5205.72	II
10000	5238.10	III
180	5240.81	I
75	5380.62	I
220	5402.78	II
90	5424.37	I
190	5438.24	I
710	5466.46	I
100	5468.47	I
240	5497.41	II
300	5503.45	I
250	5509.90	II
120	5521.63	I
740	5527.54	I
120	5544.50	I
180	5577.42	I
620	5581.87	I
120	5606.33	I
560	5630.13	I
120	5644.69	I
120	5648.47	I
740	5662.94	II
90	5675.27	I
160	5706.73	I
90	5743.85	I
75	5765.64	I
100	5781.69	II
120	6009.19	I
120	6023.41	I
120	6135.04	I
150	6138.43	I
1200	6191.73	I
300	6222.59	I
1000	6435.00	I
90	6538.60	I
70	6557.39	I
95	6613.75	II
40	6650.61	I
150	6687.58	I
70	6700.71	I
190	6793.71	I
21	6815.16	I
45	6845.24	I
29	6887.22	I
24 h	6950.31	I
24	6979.88	I
29	7052.94	I
35	7191.66	I
35	7264.17	II
50	7346.46	I
29	7450.30	II
9000	7558.71	III
35	7563.13	I
29	7855.52	I
110	7881.90	II
10000	7991.43	III
24	8344.43	I
10000	8796.21	III
95	8800.62	I
19 h	8835.85	II

Zinc Zn Z = 30

200	425.90	IV
200	428.54	IV
200	430.59	IV
1000	677.63	III
750	677.96	III
200	713.90	III
60	1193.23	II
50	1239.12	IV
50	1249.69	IV
500	1265.74	IV
500	1306.66	IV
200	1456.72	III
200	1459.98	IV
300	1499.42	III
300	1500.42	III
300	1505.92	III
300	1515.85	III
300	1552.30	III
90	1572.99	II
200	1629.19	III
200	1639.33	III
200	1673.05	III
80 d	1735.61	II
100	1767.69	III
100	1797.64	II
100 d	1811.05	II
100 d	1833.57	II
100	1864.12	II
100	1866.08	II
100	1872.13	II
100 d	1918.96	II
100 d	1929.67	II
100	1969.40	II
100	1982.11	II
100	1986.99	II
500	2025.48	II
500	2062.00	II
200	2064.23	II
120	2079.08	I
300	2099.94	II
200	2102.18	II
800 r	2138.56	I
1000	2501.99	II
150	2515.81	I
1000	2557.95	II
300	2582.49	I
200	2608.56	I
300	2608.64	I
200	2670.53	I
300	2684.16	I
300	2712.49	I
200	2756.45	I
300	2770.86	I
300	2770.98	I
400	2800.87	I
100	2801.06	I
200	3035.78	I
200	3072.06	I
300	3196.31	II
500 r	3282.33	I
800	3302.58	I
700 r	3302.94	I
800	3345.02	I
500	3345.57	I
50	3883.34	I
300	4680.14	I
400	4722.15	I
400	4810.53	I
800	4911.62	II
500	4924.03	II
200	5181.98	I
500	5894.33	II
500	6021.18	II
500	6102.49	II
500	6214.61	II
1000 h	6362.34	I
300	7588.5	II
300	7732.5	II
100	11054.25	I
100	13053.63	I
100	13150.59	I
100	14038.70	I
20	16483.45	I
20	16491.98	I

Intensity	Wavelength/Å	
20	16505.23	I
10	24375.02	I
Zirconium Zr Z = 40		
500	304.01	V
60	480.66	IV
60	497.23	IV
60	500.22	IV
600	628.66	IV
500	633.56	IV
50	690.39	III
2000	740.61	V
10000	800.00	V
10000	806.89	V
10000	812.05	V
3000	841.40	V
300	863.65	IV
500	864.59	IV
9000	1183.97	IV
9000	1201.77	IV
10000	1219.86	IV
500	1303.93	V
500 p	1323.81	V
1000	1469.47	IV
10000	1546.17	IV
10000	1598.95	IV
5000	1607.95	IV
100	1612.38	III
700	1725.02	V
200	1790.19	III
150	1793.56	III
125	1798.13	III
600	1860.86	V
200	1940.25	III
600	2028.54	V
125	2070.43	III
200	2086.78	III
10000	2091.49	IV
10000	2092.36	IV
600	2132.42	V
10000	2163.68	IV
100	2175.80	III
100	2191.15	III
10000	2286.67	IV
100	2301.60	III
90	2539.65	I
570	2567.64	II
1600	2568.87	II
2100	2571.39	II
250	2620.56	III
200	2643.79	III
150	2664.26	III
1800	2678.63	II
90	2687.75	I
750	2700.13	II
1300	2722.61	II
800	2726.49	II
1400	2734.86	II
1100	2742.56	II
660	2745.86	II
660	2752.21	II
530	2758.81	II
620	2814.90	I
390	2818.74	II
530	2825.56	II
710	2837.23	I
660	2844.58	II
350	2848.52	I
350	2851.97	II
340	2869.81	II
490	2875.98	I
300	2915.99	II
270	2918.24	II
320	2926.99	II
320	2948.94	II
320	2955.78	II
320	2960.87	I
320	2962.68	II
320	2968.96	II
320	2978.05	II
820	2985.39	I
320	3003.74	II
820	3011.75	I
350	3020.47	II
500	3028.04	II
880	3029.52	I
350 d	3036.39	II
690	3054.84	II
690	3106.58	II
350	3120.74	I
500	3129.18	II
500	3129.76	II
350	3132.07	I
690	3138.68	II
540	3164.31	II
880	3165.97	II
880	3182.86	II
540	3191.21	I
540	3212.01	I
760	3214.19	II
630	3231.69	II
630	3234.12	I
760	3241.05	II
1000	3273.05	II
1300	3279.26	II
880	3284.71	II
540	3305.15	II
880	3306.28	II
380	3322.99	II
380	3326.80	II
380	3334.25	II
760	3340.56	II
380	3344.79	II
760	3356.09	II
540	3357.26	II
380	3374.73	II
570	3387.87	II
760	3388.30	II
5700	3391.98	II
570	3393.12	II
570	3404.83	II
760	3410.25	II
380	3414.66	I
1000	3430.53	II
4700	3438.23	II
600	3447.36	I
410	3457.56	II
820	3463.02	II
600	3471.19	I
1200	3479.39	II
1300	3481.15	II
4100	3496.21	II
820	3505.67	II
1000	3509.32	I
2000	3519.60	I
440	3525.81	II
440	3533.22	I
630	3542.62	II
1800	3547.68	I
630	3550.46	I
1800	3551.95	II
2100	3556.60	II
1100	3566.10	I
2100	3572.47	II
1100	3575.79	I
1300	3576.85	II
880	3586.29	I
3500	3601.19	I
690	3611.89	II
1100	3613.10	II
1100	3614.77	II
1100	3623.86	I
1100	3663.65	I
390	3671.27	II
800	3674.72	II
390	3697.46	II
960	3698.17	II
720	3709.26	II
560	3745.98	II
880	3751.60	II
480	3764.39	I
480	3766.72	I
340	3766.82	II
720	3780.54	I
560	3791.40	I
560	3822.41	I
2200	3835.96	I
1300	3836.76	II
550	3843.02	II
550	3847.01	I
550	3849.25	I
2900	3863.87	I
770	3864.34	I
990	3877.60	I
1500	3885.42	I
2900	3890.32	I
2000	3891.38	I
610	3921.79	I
1200	3929.53	I
940	3958.22	II
490	3966.66	I
990	3968.26	I
660	3973.50	I
770	3991.13	II
770	3998.97	II
400	4023.98	I
770	4024.92	I
990	4027.20	I
400	4029.68	II
490	4030.04	I
400	4035.89	I
610	4043.58	I
490	4044.56	I
400	4045.61	II
610	4048.67	II
770	4055.03	I
600	4055.71	I
1500	4064.16	I
2000	4072.70	I
240	4078.31	I
2000	4081.22	I
400	4121.46	I
1200	4149.20	II
400	4161.21	II
400	4166.36	I
660	4187.56	I
400	4194.76	I
610	4199.09	I
610	4201.46	I
610	4208.98	II
400	4213.86	I
2000	4227.76	I
2000	4239.31	I
770	4240.34	I
770	4241.20	I
1200	4241.69	I
550	4282.20	I
550	4294.79	I
550	4341.13	I
1000	4347.89	I
290	4359.74	II
310	4360.81	I
350	4366.45	I
550	4507.12	I
610	4535.75	I
490	4542.22	I
490	4575.52	I
350	4602.57	I
700	4633.98	I
2300	4687.80	I
510	4688.45	I
1900	4710.08	I
1400	4739.48	I
870	4772.31	I
700	4815.63	I
250	5046.58	I
360	5064.91	I
470	5078.25	I
300	5155.45	I
200	5158.00	I
100	5191.60	II
270	5385.14	I
160	5664.51	I
160	5797.74	I
340	5879.80	I

Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å		Intensity	Wavelength/Å	
170	6045.85	I	300	6313.02	I	170	7103.72	I	790	8070.08	I
170	6121.91	I	150	6953.84	I	590	7169.09	I	390	8132.99	I
680	6127.44	I	150	6990.84	I	160	7944.61	I	280	8212.53	I
340	6134.55	I	540	7097.70	I	160	8005.27	I			
440	6143.20	I	280	7102.91	I	150	8063.09	I			

Sources of Data for Each Element

Numbers following the element name refer to the references on the following pages.

Actinium: 193
Aluminum: 6,8,81,89,127,144,146,227,228,282
Americium: 92
Antimony: 164,167,194,386,406
Argon: 190,203,204,219,367,368,372,373,374,375,414,421
Arsenic: 163,168,197,244,280
Astatine: 188
Barium: 1,78,111,252,259,277,279
Berkelium: 53,339
Beryllium: 15,44,73,102,115,134,135,171,175,198,335
Bismuth: 1,357,358,359,360,361
Boron: 66,69,74,94,104,171,221,222
Bromine: 42,122,124,139,142,240,243,246,248,249,250,316
Cadmium: 44,285,296,353,399
Calcium: 16,25,70,150,270
Californium: 52,331
Carbon: 22,66,211
Cerium: 1,136,166,261,305
Cesium: 78,82,154,155,200,201,259,263,325
Chlorine: 11,28,30,31,85,233,238,239
Chromium: 1,379,380,412
Cobalt: 1,100,125,159,236,276,291
Copper: 199,273,290,295,324
Curium: 51,332
Dysprosium: 1
Einsteinium: 333
Erbium: 1,301
Europium: 1,312
Fluorine: 68,169,224,225,226
Francium: 408
Gadolinium: 1,46,137,151,152
Gallium: 2,19,62,132,140,141,143,195,281
Germanium: 5,119,293,340,341,342
Gold: 38,72,234,393,395
Hafnium: 1,369,404,410,425
Helium: 16,94,173,183,317
Holmium: 1
Hydrogen: 214
Indium: 1,132,348,349,350,351,352,353,435,436
Iodine: 20,21,58,84,124,153,161,176,184
Iridium: 1
Iron: 56,63,71,101,105,138,174,278,381,382
Krypton: 61,121,123,147,208,232,366,390,409,417,421
Lanthanum: 1,78,79,220,309
Lead: 54,64,106,256,274,297,283,329,330
Lithium: 3,15,17,18,37,44,112,284,321,335
Lutetium: 1,148,310,401
Magnesium: 4,7,49,83,103,128,129,177,217,269,315,335
Manganese: 1,126,385,405,433
Mercury (198): 43,50,69,145,229,242
Mercury (Natural): 34,45,90,117,133,189,235,304,327,328,343
Molybdenum: 1,383,420
Neodymium: 1
Neon: 56,58,69,118,150,230,364,365,371,388,389,400,402,413, 430
Neptunium: 93
Nickel: 1,294,415,416,422
Niobium: 1,392,407,431
Nitrogen: 66,107,108,212,213,318
Osmium: 1
Oxygen: 23,24,36,66,69,209,210,215
Palladium: 1,287,424
Phosphorus: 179,180,182,336
Platinum: 1,288
Plutonium: 91
Polonium: 47,48
Potassium: 32,59,60,75,76,86,150,160,172,268,314,322
Praseodymium: 1,149,306,308,337,338
Promethium: 196,260
Protactinium: 96
Radium: 253,254
Radon: 251
Rhenium: 1
Rhodium: 1,396
Rubidium: 12,109,130,241,257,258,262,264
Ruthenium: 1,423
Samarium: 1
Scandium: 1,88,150,298,323
Selenium: 9,80,181,216,245,247,275
Silicon: 87,170,237,292,319,320
Silver: 13,99,255,286,289,363,387,398
Sodium: 178,205,206,207,268,299,334
Strontium: 1,109,110,218,231,265,279,313
Sulfur: 29,144,202,209,210,266
Tantalum: 1,411,426
Technetium: 35
Tellurium: 1,344,345,346,347
Terbium: 1,302
Thallium: 1,195,348,354,355,356
Thorium: 1,97,98,156,157,165,434
Thulium: 1,307
Tin: 187,191,399,423
Titanium: 1,378,427,428
Tungsten: 1
Uranium: 1,303
Vanadium: 1,394,397,432
Xenon: 33,116,118,120,232,384,391,429
Ytterbium: 1,40,192,311
Yttrium: 1,77,265,419
Zinc: 39,55,113,131,185,186,370,376,377
Zirconium: 1,362,403,418

References

1. Meggers, W. F., Corliss, C. H., and Scribner, B. F., *Natl. Bur. Stand. (U.S.) Monogr.*, 145, Washington, D.C., 1975.
2. Aksenov, V. P. and Ryabtsev, A. N., *Opt. Spectrosc.*, 37, 860, 1970.
3. Andersen, N., Bickel, W. S., Carriveau, G. W., Jensen, K., and Veje, E., *Phys. Scr.*, 4, 113, 1971.
4. Andersson, E. and Johannesson, G. A., *Phys. Scr.*, 3, 203, 1971.
5. Andrew, K. L. and Meissner, K. W., *J. Opt. Soc. Am.*, 49, 146, 1959.
6. Artru, M. C. and Brillet, W. U. L., *J. Opt. Soc. Am.*, 64, 1063, 1974.
7. Artru, M. C. and Kaufman, V., *J. Opt. Soc. Am.*, 62, 949, 1972.
8. Artru, M. C. and Kaufman, V., *J. Opt. Soc. Am.*, 65, 594, 1975.
9. Badami, J. S. and Rao, K. R., *Proc. R. Soc. London*, 140(A), 387, 1933.
10. Baird, K. M. and Smith, D. S., *J. Opt. Soc. Am.*, 48, 300, 1958.
11. Bashkin, S. and Martinson, I., *J. Opt. Soc. Am.*, 61, 1686, 1971.
12. Beacham, J. R., Ph.D. thesis, Purdue University, 1970.
13. Benschop, H., Joshi, Y. N., and van Kleef, T. A. M., *Can. J. Phys.*, 53, 700, 1975.
14. Berry, H. G., Bromander, J., and Buchta, R., *Phys. Scr.*, 1, 181, 1970.
15. Berry, H. G., Bromander, J., Martinson, I., and Buchta, R., *Phys. Scr.*, 3, 63, 1971.
16. Berry, H. G., Desesquelles, J., and Dufay, M., *Phys. Rev. Sect A.*, 6, 600, 1972.
17. Berry, H. G., Desesquelles, J., and Dufay, M., *Nucl. Instrum. Methods*, 110, 43, 1973.
18. Berry, H. G., Pinnington, E. H., and Subtil, J. L., *J. Opt. Soc. Am.*, 62, 767, 1972.
19. Bidelman, W. P. and Corliss, C. H., *Astrophys. J.*, 135, 968, 1962.
20. Bloch, L. and Bloch, E., *Ann. Phys.* (Paris), 10(11), 141, 1929.
21. Bloch, L., Bloch, E., and Felici, N., *J. Phys. Radium*, 8, 355, 1937.
22. Bockasten, K., *Ark. Fys.*, 9, 457, 1955.
23. Bockasten, K., Hallin, R., Johansson, K. B., and Tsui, P., *Phys. Lett.* (Netherlands), 8, 181, 1964.
24. Bockasten, K. and Johansson, K. B., *Ark. Fys.*, 38, 563, 1969.
25. Borgstrom, A., *Ark. Fys.*, 38, 243, 1968.
26. Borgstrom, A., *Phys. Scr.*, 3, 157, 1971.
27. Bowen, I. S., *Phys. Rev.*, 29, 231, 1927.
28. Bowen, I. S., *Phys. Rev.*, 31, 34, 1928.
29. Bowen, I. S., *Phys. Rev.*, 39, 8, 1932.
30. Bowen, I. S., *Phys. Rev.*, 45, 401, 1934.
31. Bowen, I. S., *Phys. Rev.*, 46, 377, 1934.
32. Bowen, I. S., *Phys. Rev.*, 46, 791, 1934.
33. Boyce, J. C., *Phys. Rev.*, 49, 730, 1936.
34. Boyce, J. C. and Robinson, H. A., *J. Opt. Soc. Am.*, 26, 133, 1936.
35. Bozman, W. R., Meggers, W. F., and Corliss, C. H., *J. Res. Natl. Bur. Stand. Sect. A*, 71, 547, 1967.
36. Bromander, J., *Ark. Fys.*, 40, 257, 1969.
37. Bromander, J. and Buchta, R., *Phys. Scr.*, 1, 184, 1970.
38. Brown, C. M. and Ginter, M. L., *J. Opt. Soc. Am.*, 68, 243, 1978.
39. Brown, C. M., Tilford, S. G., and Ginter, M. L., *J. Opt. Soc. Am.*, 65, 1404, 1975.
40. Bryant, B. W., *Johns Hopkins Spectroscopic Report* No. 21, 1961.
41. Buchet, J. P., Buchet-Poulizac, M. C., Berry, H. G., and Drake, G. W. F., *Phys. Rev. Sect. A*, 7, 922, 1973.
42. Budhiraja, C. J. and Joshi, Y. N., *Can. J. Phys.*, 49, 391, 1971.
43. Burns, K. and Adams, K. B., *J. Opt. Soc. Am.*, 42, 56, 1952.
44. Burns, K. and Adams, K. B., *J. Opt. Soc. Am.*, 46, 94, 1956.
45. Burns, K., Adams, K. B., and Longwell, J., *J. Opt. Soc. Am.*, 40, 339, 1950.
46. Callahan, W. R., Ph.D. thesis, Johns Hopkins University, 1962.
47. Charles, G. W., *J. Opt. Soc. Am.*, 56, 1292, 1966.
48. Charles, G. W., Hunt, D. J., Pish, G., and Timma, D. L., *J. Opt. Soc. Am.*, 45, 869, 1955.
49. Codling, K., *Proc. Phys. Soc.*, 77, 797, 1961.
50. Comite Consulatif Pour La Definition du Metre, *J. Phys. Chem. Ref. Data*, 3, 852, 1974.
51. Conway, J. G., Blaise, J., and Verges, J., *Spectrochim. Acta Part B*, 31, 31, 1976.
52. Conway, J. G., Worden, E. F., Blaise, J., and Verges, J., *Spectrochim. Acta Part B*, 32, 97, 1977.
53. Conway, J. G., Worden, E. F., Blaise, J., Camus, P., and Verges, J., *Spectrochim. Acta Part B*, 32, 101, 1977.
54. Crooker, A. M., *Can. J. Res. Sect.* A, 14, 115, 1936.
55. Crooker, A. M. and Dick, K. A., *Can. J. Phys.*, 46, 1241, 1968.
56. Crosswhite, H. M., *J. Res. Natl. Bur. Stand. Sect. A*, 79, 17, 1975.
58. Crosswhite, H. M. and Dieke, G. H., *American Institute of Physics Handbook*, Section 7, 1972.
59. de Bruin, T. L., *Z. Phys.*, 38, 94, 1926.
60. de Bruin, T. L., *Z. Phys.*, 53, 658, 1929.
61. de Bruin, T. L., Humphreys, C. J., and Meggers, W. F., *J. Res. Natl. Bur. Stand.*, 11, 409, 1933.
62. Dick, K. A., *J. Opt. Soc. Am.*, 64, 702, 1973.
63. Dobbie, J. C., *Ann. Solar Phys. Observ.* (Cambridge), 5, 1, 1938.
64. Earls, L. T. and Sawyer, R. A., *Phys. Rev.*, 47, 115, 1935.
65. Edlen, B., *Z. Phys.*, 85, 85, 1933.
66. Edlen, B., *Nova Acta Reglae Soc. Sci. Ups.*, (IV) 9, No. 6, 1934.
67. Edlen, B., *Z. Phys.*, 93, 726, 1935.
68. Edlen, B., *Z. Phys.*, 94, 47, 1935.
69. Edlen, B., *Rep. Prog. Phys.*, 26, 181, 1963.
70. Edlen, B. and Risberg, P., *Ark. Fys.*, 10, 553, 1956.
71. Edlen, B. and Swings, P., *Astrophys. J.*, 95, 532, 1942.
72. Ehrhardt, J. C. and Davis, S. P., *J. Opt. Soc. Am.*, 61, 1342, 1971.
73. Eidelsberg, M., *J. Phys. B*, 5, 1031, 1972.
74. Eidelsberg, M., *J. Phys. B*, 7, 1476, 1974.
75. Ekberg, J. O. and Svensson, L. A., *Phys. Scr.*, 2, 283, 1970.
76. Ekefors, E., *Z. Phys.*, 71, 53, 1931.
77. Epstein, G. L. and Reader, J., *J. Opt. Soc. Am.*, 65, 310, 1975.
78. Epstein, G. L. and Reader, J., *J. Opt. Soc. Am.*, 66, 590, 1976.
79. Epstein, G. L. and Reader, J., unpublished.
80. Eriksson, K. B. S., *Phys. Lett. A.*, 41, 97, 1972.
81. Eriksson, K. B. S. and Isberg, H. B. S., *Ark. Fys.*, 23, 527, 1963.
82. Eriksson, K. B. S. and Wenaker, I., *Phys. Scr.*, 1, 21, 1970.
83. Esteva, J. M. and Mehlman, G., *Astrophys. J.*, 193, 747, 1974.
84. Even-Zohar, M. and Fraenkel, B. S., *J. Phys. B*, 5, 1596, 1972.
85. Fawcett, B. C., *J. Phys. B*, 3, 1732, 1970.
86. Fawcett, B. C., Culham Laboratory Report ARU-R4, 1971.
87. Ferner, E., *Ark. Mat. Astron. Fys.*, 28(A), 4, 1941.
88. Fischer, R. A., Knopf, W. C., and Kinney, F. E., *Astrophys. J.*, 130, 683, 1959.
89. Fowler, A., *Report on Series in Line Spectra*, Fleetway Press, London, 1922.
90. Fowles, G. R., *J. Opt. Soc. Am.*, 44, 760, 1954.
91. Fred, M., *Argonne Natl. Lab.*, unpublished, 1977.
92. Fred, M. and Tomkins, F. S., *J. Opt. Soc. Am.*, 47, 1076, 1957.
93. Fred, M., Tomkins, F. S., Blaise, J. E., Camus, P., and Verges, J., Argonne National Laboratory Report No. 76–68, 1976.
94. Garcia, J. D. and Mack, J. E., *J. Opt. Soc. Am.*, 55, 654, 1965.
96. Giacchetti, A., *Argonne Natl. Lab.*, unpublished, 1975.
97. Giacchetti, A., Blaise, J., Corliss, C. H., and Zalubas, R., *J. Res. Natl. Bur. Stand. Sect. A*, 78, 247, 1974.
98. Giacchetti, A., Stanley, R. W., and Zalubas, R., *J. Opt. Soc. Am.*, 69, 474, 1970.
99. Gilbert, W. P., *Phys. Rev.*, 47, 847, 1935.
100. Gilroy, H. T., *Phys. Rev.*, 38, 2217, 1931.
101. Glad, S., *Ark. Fys.*, 10, 291, 1956.
102. Goldsmith, S., *J. Phys. B*, 2, 1075, 1969.
103. Goorvitch, D., Mehlmam-Balloffet, G., and Valero, F. P. J., *J. Opt. Soc. Am.*, 60, 1458, 1970.
104. Goorvitch, D. and Valero, F. P. J., *Astrophys.* J., 171, 643, 1972.
105. Green, L. C., *Phys. Rev.*, 55, 1209, 1939.
106. Gutman, F., *Diss. Abstr. Int.* B, 31, 363, 1970.
107. Hallin, R., *Ark. Fys.*, 31, 511, 1966.
108. Hallin, R., *Ark. Fys.*, 32, 201, 1966.
109. Hansen, J. E. and Persson, W., *J. Opt. Soc. Am.*, 64, 696, 1974.
110. Hansen, J. E. and Persson, W., *Phys. Scr.*, 13, 166, 1976.
111. Hellintin, P., *Phys. Scr.*, 13, 155, 1976.
112. Herzberg, G. and Moore, H. R., *Can. J. Phys.*, 37, 1293, 1959.
113. Hetzler, C. W., Boreman, R. W., and Burns, K., *Phys. Rev.*, 48, 656, 1935.
114. Holmstrom, J. E. and Johansson, L., *Ark. Fys.*, 40, 133, 1969.

115. Hontzeas, S., Martinson, I., Erman, P., and Buchta, R., *Nucl. Instrum. Methods*, 110, 51, 1973.
116. Humphreys, C. J., *J. Res. Natl. Bur. Stand.*, 22, 19, 1939.
117. Humphreys, C. J., *J. Opt. Soc. Am.*, 43, 1027, 1953.
118. Humphreys, C. J., *J. Phys. Chem. Ref. Data*, 2, 519, 1973.
119. Humphreys, C. J. and Andrew, K. L., *J. Opt. Soc. Am.*, 54, 1134, 1964.
120. Humphreys, C. J. and Meggers, W. F., *J. Res. Natl. Bur. Stand.*, 10, 139, 1933.
121. Humphreys, C. J. and Paul, E., Jr., *J. Opt. Soc. Am.*, 60, 200, 1970.
122. Humphreys, C. J. and Paul, E., Jr., *J. Opt. Soc. Am.*, 62, 432, 1972.
123. Humphreys, C. J., Paul, E., Jr., Cowan, R. D., and Andrew, K. L., *J. Opt. Soc. Am.*, 57, 855, 1967.
124. Humphreys, C. J., Paul, E., Jr., and Minnhagen, L., *J. Opt. Soc. Am.*, 61, 110, 1971.
125. Iglesias, L., Inst. of Optics, Madrid, unpublished, 1977.
126. Iglesias, L. and Velasco, R., *Publ. Inst. Opt. Madrid*, No. 23, 1964.
127. Isberg, B., *Ark. Fys.*, 35, 551, 1967.
128. Johannesson, G. A., Lundstrom, T., and Minnhagen, L., *Phys. Scr.*, 6, 129, 1972.
129. Johannesson, G. A. and Lundstrom, T., *Phys. Scr.*, 8, 53, 1973.
130. Johansson, I. *Ark. Fys.*, 20, 135, 1961.
131. Johansson, I. and Contreras, R., *Ark. Fys.*, 37, 513, 1968.
132. Johansson, I. and Litzen, U., *Ark. Fys.*, 34, 573, 1967.
133. Johansson, I. and Svensson, K. F., *Ark. Fys.*, 16, 353, 1960.
134. Johansson, L., *Ark. Fys.*, 20, 489, 1961.
135. Johansson, L., *Ark. Fys.*, 23, 119, 1963.
136. Johansson, S. and Litzen, U., *Phys. Scr.*, 6, 139, 1972.
137. Johansson, S. and Litzen, U., *Phys. Scr.*, 8, 43, 1973.
138. Johansson, S. and Litzen, U., *Phys. Scr.*, 10, 121, 1974.
139. Joshi, Y. N., St. Francis Xavier Univ., Nova Scotia, unpublished.
140. Joshi, Y. N., Bhatia, K. S., and Jones, W. E., *Sci. Light Tokyo*, 21, 113, 1972.
141. Joshi, Y. N., Bhatia, K. S., and Jones, W. E., *Spectrochim. Acta Part B*, 28, 149, 1973.
142. Joshi, Y. N. and Budhiraja, C. J., *Can. J. Phys.*, 49, 670, 1971.
143. Joshi, Y. N. and van Kleef, T. A. M., *Can. J. Phys.*, 52, 1891, 1974.
144. Kaufman, V., *Natl. Bur. Stand.*, unpublished.
145. Kaufman, V., *J. Opt. Soc. Am.*, 52, 866, 1962.
146. Kaufman, V., Artru, M. C., and Brillet, W. U. L., *J. Opt. Soc. Am.*, 64, 197, 1974.
147. Kaufman, V. and Humphreys, C. J., *J. Opt. Soc. Am.*, 59, 1614, 1969.
148. Kaufman, V. and Sugar, J., *J. Opt. Soc. Am.*, 61, 1693, 1971.
149. Kaufman, V. and Sugar, J., *J. Res. Natl. Bur. Stand. Sect. A*, 71, 583, 1967.
150. Kelly, R. L. and Palumbo, L. J., *Naval Research Laboratory Report 7599*, Washington, DC., 1973.
151. Kielkopf, J. F., *Univ. of Louisville*, unpublished. 1975.
152. Kielkopf, J. F., *Univ. of Louisville*, unpublished, 1976.
153. Kiess, C. C. and Corliss, C. H., *J. Res. Natl. Bur. Stand. Sect. A*, 63, 1, 1959.
154. Kleiman, H., *J. Opt. Soc. Am.*, 52, 441, 1962.
155. Eriksson, K. B., Johansson, I., and Norlen, G., *Ark. Fys.*, 28, 233, 1964.
156. Klinkenberg, P. F. A., *Physica*, 15, 774, 1949.
157. Klinkenberg, P. F. A., *Physica*, 16, 618, 1950.
158. Krishnamurty, S. G., *Proc. Phys. Soc. London*, 48, 277, 1936.
159. Kruger, P. G. and Gilroy, H. T., *Phys. Rev.*, 48, 720, 1935.
160. Kruger, P. G. and Pattin, H. S., *Phys. Rev.*, 52, 621, 1937.
161. Lacroute, P., *Ann. Phys.* (Paris), 3, 5, 1935.
162. Lang, R. J., *Phys. Rev.*, 30, 762, 1927.
163. Lang, R. J., *Phys. Rev.*, 32, 737, 1928.
164. Lang, R. J., *Phys. Rev.*, 35, 445, 1930.
165. Lang, R. J., *Can. J. Res. Sect. A*, 14, 43, 1936.
166. Lang, R. J., *Can. J. Res. Sect. A*, 14, 127, 1936.
167. Lang, R. J. and Vestine, E. H., *Phys. Rev.*, 42, 233, 1932.
168. Li, H. and Andrew, K. L., *J. Opt. Soc. Am.*, 61, 96, 1971.
169. Liden, K., *Ark. Fys.*, 1, 229, 1949.
170. Litzen, U., *Ark. Fys.*, 28, 239, 1965.
171. Litzen, U., *Phys. Scr.*, 1, 251, 1970.
172. Litzen, U., *Phys. Scr.*, 1, 253, 1970.
173. Litzen, U., *Phys. Scr.*, 2, 103, 1970.
174. Litzen, U. and Verges, I., *Phys. Scr.*, 13, 240, 1976.
175. Lofstrand, B., *Phys. Scr.*, 8, 57, 1973.
176. Luc-Koenig, E., Morillon, C., and Verges, J., *Phys. Scr.*, 12, 199, 1975.
177. Lundstrom, T., *Phys. Scr.*, 7, 62, 1973.
178. Lundstrom, T. and Minnhagen, L., *Phys. Scr.*, 5, 243, 1972.
179. Magnusson, C. E. and Zetterberg, P. O., *Phys. Scr.*, 10, 177, 1974.
180. Magnusson, C. E., and Zetterberg, P. O., *Phys. Scr.*, 15, 237, 1977.
181. Martin, D. C., *Phys. Rev.*, 48. 938, 1935.
182. Svendenius, N., *Phys. Scr.*, 22, 240, 1980.
183. Martin, W. C., *J. Res. Natl. Bur. Stand. Sect. A*, 64, 19, 1960.
184. Martin, W. C. and Corliss, C. H., *J. Res. Natl. Bur. Stand. Sect. A*, 64, 443, 1960.
185. Martin, W. C. and Kaufman, V., *J. Res. Natl. Bur. Stand. Sect. A*, 74, 11, 1970.
186. Martin, W. C. and Kaufman, V., *J. Opt. Soc. Am.*, 60, 1096, 1970.
187. McCormick, W. W. and Sawyer, R. A., *Phys. Rev.*, 54, 71, 1938.
188. McLaughlin, R., *J. Opt. Soc. Am.*, 54, 965, 1964.
189. McLennan, J. C., McLay, A. B., and Crawford, M. F., *Proc. R. Soc. London Ser. A*, 134, 41, 1931.
190. Meissner, K. W., *Z. Phys.*, 39, 172, 1926.
191. Meggers, W. F., *J. Res. Natl. Bur. Stand.*, 24, 153, 1940.
192. Meggers, W. F. and Corliss, C. H., *J. Res. Natl. Bur. Stand. Sect. A*, 70, 63, 1966.
193. Meggers, W. F., Fred, M., and Tomkins, F. S., *J. Res. Natl. Bur. Stand.*, 58, 297, 1957.
194. Meggers, W. F. and Humphreys, C. J., *J. Res. Natl. Bur. Stand.*, 28, 463, 1942.
195. Meggers, W. F. and Murphy, R. J., *J. Res. Natl. Bur. Stand.*, 48, 334, 1952.
196. Meggers, W. F., Scribner, B. F., and Bozman, W. R., *J. Res. Natl. Bur. Stand.*, 46, 85, 1951.
197. Meggers, W. F., Shenstone, A. G., and Moore, C. E., *J. Res. Natl. Bur. Stand.*, 45, 346, 1950.
198. Mehlman, G. and Esteva, J. M., *Astrophys.* J., 188, 191, 1974.
199. Meinders, E., *Physica*, 84(C), 117, 1976.
200. Sansonetti, C. J., Dissertation, Purdue University, 1981.
201. Sansonetti, C. J., *Natl. Bur. Stand. (U.S.)*, unpublished.
202. Millikan, R. A. and Bowen, I. S., *Phys. Rev.*, 25, 600, 1925.
203. Minnhagen, L., *J. Opt. Soc. Am.*, 61, 1257, 1925.
204. Minnhagen, L., *J. Opt. Soc. Am.*, 63, 1185, 1973.
205. Minnhagen, L., *Phys. Scr.*, 11, 38, 1975.
206. Minnhagen, L., *J. Opt. Soc. Am.*, 66, 659, 1976.
207. Minnhagen, L. and Nietsche, H., *Phys. Scr.*, 5, 237, 1972.
208. Minnhagen. L., Strihed, H., and Petersson, B., *Ark. Fys.*, 39, 471, 1969.
209. Moore, C. E., *Natl. Bur. Stand. (U.S.) Circ.*, 488, 1950.
210. Moore, C. E., *Revised Multiplet Table*, Princeton University Observatory No. 20, 1945.
211. Moore, C. E., National Standard Reference Data Series - National Bureau of Standards 3, Sect. 3, 1970.
212. Moore, C. E., National Standard Reference Data Series - National Bureau of Standards 3, Sect. 4, 1971.
213. Moore, C. E., National Standard Reference Data Series - National Bureau of Standards 3, Sect. 5, 1975.
214. Moore, C. E., National Standard Reference Data Series - National Bureau of Standards 3, Sect. 6, 1972.
215. Moore, C. E., National Standard Reference Data Series - National Bureau of Standards 3, Sect. 7, 1975.
216. Morillon, C. and Verges, J., *Phys. Scr.*, 10, 227, 1974.
217. Newsom, G. H., *Astrophys.* J., 166, 243, 1971.
218. Newsom, G. H., O'Connor, S., and Learner, R. C. M., *J. Phys. B*, 6, 2162, 1973.
219. Norlen, G., *Phys. Scr.*, 8, 249, 1973.
220. Odabasi, H., *J. Opt. Soc. Am.*, 57, 1459, 1967.
221. Olme, A., *Ark. Fys.*, 40, 35, 1969.
222. Olme, A., *Phys. Scr.*, 1, 256, 1970.
223. Johansson, S., and Litzen, U., *J. Opt. Soc. Am.*, 61, 1427, 1971.
224. Palenius, H. P., *Ark. Fys.*, 39, 15, 1969.
225. Palenius, H. P., *Phys. Scr.*, 1, 113, 1970.
226. Palenius, H. P., *Univ. of Lund, Sweden*, unpublished.
227. Paschen, F., *Ann. Phys.*, Series 5, 12, 509, 1932.
228. Paschen, F. and Ritschl, R., *Ann. Phys.*, Series 5, 18, 867, 1933.

229. Peck, E. R., Khanna, B. N., and Anderholm, N. C., *J. Opt. Soc. Am.*, 52, 53, 1962.
230. Persson, W., *Phys. Scr.*, 3, 133, 1971.
231. Persson, W. and Valind, S., *Phys. Scr.*, 5, 187, 1972.
232. Petersson, B., *Ark. Fys.*, 27, 317, 1964.
233. Phillips, L. W. and Parker, W. L., *Phys. Rev.*, 60, 301, 1941.
234. Platt, J. R. and Sawyer, R. A., *Phys. Rev.*, 60, 866, 1941.
235. Plyer, E. K., Blaine, L. R., and Tidwell, E., *J. Res. Natl. Bur. Stand.*, 55, 279, 1955.
236. Poppe, R., van Kleef, T. A. M., and Raassen, A. J. J., *Physica*, 77, 165, 1974.
237. Radziemski, L. J., Jr. and Andrew, K. L., *J. Opt. Soc. Am.*, 55, 474, 1965.
238. Radziemski, L. J., Jr. and Kaufman, V., *J. Opt. Soc. Am.*, 59, 424, 1969.
239. Radziemski, L. J., Jr. and Kaufman, V., *J. Opt. Soc. Am.*, 64, 366, 1974.
240. Ramanadham, R. and Rao, K. R., *Indian J. Phys.*, 18, 317, 1944.
241. Ramb, R., *Ann. Phys.*, 10, 311, 1931.
242. Rank, D. H., Bennett, J. M., and Bennett, H. E., *J. Opt. Soc. Am.*, 40, 477, 1950.
243. Rao, A. S. and Krishnamurty, S. G., *Proc. Phys. Soc. London*, 46, 531, 1943.
244. Rao, K. R., *Proc. R. Soc. London, Ser. A*, 134, 604, 1932.
245. Rao, K. R. and Badami, *J. S., Proc. R. Soc. London Ser. A*, 131, 154, 1931.
246. Rao, K. R. and Krishnamurty, S. G., *Proc. R. Soc. London Ser. A*, 161, 38, 1937.
247. Rao, K. R. and Murti, S. G. K., *Proc. R. Soc. London* Ser. A, 145, 681, 1934.
248. Rao, Y. B., *Indian J. Phys.*, 32, 497, 1958.
249. Rao, Y. B., *Indian J. Phys.*, 33, 546, 1959.
250. Rao, Y. B., *Indian J. Phys.*, 35, 386, 1961.
251. Rasmussen, E., *Z. Phys.*, 80, 726, 1933.
252. Rasmussen, E., *Z. Phys.*, 83, 404, 1933.
253. Rasmussen, E., *Z. Phys.*, 86, 24, 1934.
254. Rasmussen, E., *Z. Phys.*, 87, 607, 1934.
255. Rasmussen, E., *Phys. Rev.*, 57, 840, 1940.
256. Rau, A. S. and Narayan, A. L., *Z. Phys.*, 59, 687, 1930.
257. Reader, J., *J. Opt. Soc. Am.*, 65, 286, 1975.
258. Reader, J., *J. Opt. Soc. Am.*, 65, 988, 1975.
259. Reader, J., *J. Opt Soc. Am.*, 73, 349, 1983.
260. Reader, J. and Davis, S., *J. Res. Natl. Bur. Stand. Sect. A*, 71, 587, 1967, and unpublished.
261. Reader, J. and Ekberg, J. O., *J. Opt. Soc. Am.*, 62, 464, 1972.
262. Reader, J. and Epstein, G. L., *J. Opt. Soc. Am.*, 62, 1467, 1972.
263. Reader, J. and Epstein, G. L., *J. Opt. Soc. Am.*, 65, 638, 1975.
264. Reader, J. and Epstein, G. L., *Natl. Bur. Stand.*, unpublished.
265. Reader, J., Epstein, G. L., and Ekberg, J. O., *J. Opt. Soc. Am.*, 62, 273, 1972.
266. Kaufman, V., *Phys. Scr.*, 26, 439, 1982.
267. Ricard, R., Givord, M., and George, F., *C. R. Acad. Sci. Paris*, 205, 1229, 1937.
268. Risberg, P., *Ark. Fys.*, 10, 583, 1956.
269. Risberg, G., *Ark. Fys.*, 28, 381, 1965.
270. Risberg, G., *Ark. Fys.*, 37, 231, 1968.
271. Robinson, H. A., *Phys. Rev.*, 49, 297, 1936.
272. Robinson, H. A., *Phys. Rev.*, 50, 99, 1936.
273. Ross, C. B., Jr., Doctoral dissertation, Purdue University, 1969.
274. Ross, C. B., Wood, D. R., and Scholl, P. S., *J. Opt. Soc. Am.*, 66, 36, 1976.
275. Ruedy, J. E. and Gibbs, R. C., *Phys. Rev.*, 46, 880, 1934.
276. Russell, H. N., King, R. B., and Moore, C. E., *Phys. Rev.*, 58, 407, 1940.
277. Russell, H. N. and Moore, C. E., *J. Res. Natl. Bur. Stand.*, 55, 299, 1955.
278. Russell, H. N., Moore, C. E., and Weeks, D. W., *Trans. Am. Philos. Soc.*, 34(2), 111, 1944.
279. Saunders, F., Schneider, E., and Buckingham, E., *Proc. Natl. Acad. Sci.*, 20, 291, 1934.
280. Sawyer, R. A. and Humphreys, C. J., *Phys. Rev.*, 32, 583, 1928.
281. Sawyer, R. A. and Lang, R. J., *Phys. Rev.*, 34, 712, 1929.
282. Sawyer, R. A. and Paschen, F., *Ann. Phys.*, 84(4),1, 1927.
283. Scholl, P. S., M.S. thesis, Wright State Univ., 1975.
284. Schurmann, D., *Z. Phys.*, 17, 4, 1975.
285. Seguier, J., *C. R. Acad. Sci. Paris*, 256, 1703, 1963.
286. Shenstone, A. G., *Phys. Rev.*, 31, 317, 1928.
287. Shenstone, A. G., *Phys. Rev.*, 32, 30, 1928.
288. Shenstone, A. G., *Trans. R. Soc. London*, 237(A), 57, 1938.
289. Shenstone, A. G., *Phys. Rev.*, 57, 894, 1940.
290. Shenstone, A. G. *Philos. Trans. R. Soc. London Ser. A*, 241, 297, 1948.
291. Shenstone, A. G., *Can. J. Phys.*, 38, 677, 1960.
292. Shenstone, A. G., *Proc. R. Soc. London*, 261(A), 153, 1961.
293. Shenstone, A. G., *Proc. R. Soc. London*, 276(A), 293, 1963.
294. Shenstone, A. G., *J. Res. Natl. Bur. Stand. Sect. A*, 74, 801, 1970.
295. Shenstone, A. G., *J. Res. Natl. Bur. Stand. Sect. A*, 79, 497, 1975.
296. Shenstone, A. G. and Pittenger, J. T., *J. Opt. Soc. Am.*, 39, 219, 1949.
297. Smith, S., *Phys. Rev.*, 36, 1, 1930.
298. Smitt, R., *Phys. Scr.*, 8, 292, 1973.
299. Soderqvist, J., *Ark. Mat. Astronom. Fys.*, 32(A), 1, 1946.
300. Sommer, L. A., *Ann. Phys.*, 75, 163, 1924.
301. Spector, N., *J. Opt. Soc. Am.*, 63, 358, 1973.
302. Spector, N. and Sugar, J., *J. Opt. Soc. Am.*, 66, 436, 1976.
303. Steinhaus, D. W., Radziemski, L. J., Jr., and Blaise, J., *Los Alamos Sci. Lab.*, unpublished, 1975.
304. Subbaraya, T. S., *Z. Phys.*, 78, 541, 1932.
305. Sugar, J., *J. Opt. Soc. Am.*, 55, 33, 1965.
306. Sugar, J., *J. Res. Natl. Bur. Stand. Sect. A*, 73, 333, 1969.
307. Sugar, J., *J. Opt. Soc. Am.*, 60, 454, 1970.
308. Sugar, J., *J. Res. Natl. Bur. Stand. Sect. A*, 78, 555, 1974.
309. Sugar, J. and Kaufman, V., *J. Opt. Soc. Am.*, 55, 1283, 1965.
310. Sugar, J. and Kaufman, V., *J. Opt. Soc. Am.*, 62, 562, 1972.
311. Sugar, J., Kaufman, V., and Spector, N., *J. Res. Natl. Bur. Stand., Sect. A*, 83, 233, 1978.
312. Sugar, J. and Spector, N., *J. Opt. Soc. Am.*, 64, 1484, 1974.
313. Sullivan, F. J. *Univ. Pittsburgh Bull.*, 35, 1, 1938.
314. Svensson, L. A. and Ekberg, J. O., *Ark. Fys.*, 37, 65, 1968.
315. Swensson, J. W. and Risberg, G., *Ark. Fys.*, 31, 237, 1966.
316. Tech, J. L., *J. Res. Natl. Bur. Stand. Sect. A*, 67, 505, 1963.
317. Tech, J. L. and Ward, J. F., *Phys. Rev. Lett.*, 27, 367, 1971.
318. Tilford, S. G., *J. Opt. Soc. Am.*, 53, 1051, 1963.
319. Toresson, Y. G., *Ark. Fys.*, 17, 179, 1960.
320. Toresson, Y. G., *Ark. Fys.*, 18, 389, 1960.
321. Toresson, Y. G. and Edlen, B., *Ark. Fys.*, 23, 117, 1963.
322. Tsien, W. Z., *Chin. J. Phys.*, Peiping, 3, 117, 1939.
323. van Deurzen, C. H. H., Conway, J., and Davis, S. P., *J. Opt. Soc. Am.*, 63, 158, 1973.
324. van Kleef, T. A. M., Raassen, A. J. J., and Joshi, Y. N., *Physica*, 84(C), 401, 1976.
325. Sansonetti, C. J., Andrew, K. L., and Verges, J., *J. Opt. Soc. Am.*, 71, 423, 1981.
326. Wheatley, M. A. and Sawyer, R. A., *Phys. Rev.*, 61, 591, 1942.
327. Wilkinson, P. G., *J. Opt. Soc. Am.*, 45, 862, 1955.
328. Wilkinson, P. G. and Andrew, K. L., *J. Opt. Soc. Am.*, 53, 710, 1963.
329. Wood, D. and Andrew, K. L., *J. Opt. Soc. Am.*, 58, 818, 1968.
330. Wood, D. R., Ron, C. B., Scholl, P. S., and Hoke, M., *J. Opt. Soc. Am.*, 64, 1159, 1974.
331. Worden, E. F. and Conway, J. G., *Lawrence Livermore Lab.*, unpublished, 1977.
332. Worden, E. F., Hulet, E. K., Gutmacher, R. G., Conway, J. G., *At. Data Nucl. Data Tables*, 18, 459, 1976.
333. Worden, E. F., Lougheed, R. W., Gutmacher, R. G., and Conway, J. G., *J. Opt. Soc. Am.*, 64, 77, 1974.
334. Wu, C. M., Ph.D. thesis, University of British Columbia, 1971.
335. Zaidel, A. N., Prokofev, V. K., Raiskii, S. M., Slavnyi, V. A., and Schreider, E. Y., *Tables of Spectral Lines*, 3rd ed., Plenum, New York, 1970.
336. Zetterberg, P. O. and Magnusson, C. E., *Phys. Scr.*, 15, 189, 1977.
337. Sugar, J., *J. Opt. Soc. Am.*, 55, 1058, 1965.
338. Sugar, J., *J. Opt. Soc. Am.*, 61, 727, 1971.
339. Worden, E. F., and Conway, J. G., *At. Data Nucl. Data Tables*, 22, 329, 1978.
340. Kaufman, V. and Edlen, B., *J. Phys. Chem. Ref. Data*, 3, 825, 1974.
341. Lang, R. J., *Phys. Rev.*, 34, 697, 1929.
342. Ryabtsev, A. N., *Opt. Spectros.*, 39, 455, 1975.

343. Foster, E. W., *Proc. R. Soc. London*, 200(A), 429, 1950.
344. Morillon, C. and Verges, J., *Phys. Scr.*, 12, 129, 1975.
345. Ruedy, J. E., *Phys. Rev.*, 41, 588, 1932.
346. McLennan, J. C., McLay, A. B., and McLeod, J. H., *Philos. Mag.*, 4 ,486, 1927.
347. Handrup, M. B. and Mack, J. E., *Physica*, 30, 1245, 1964.
348. Clearman, H. E., *J. Opt. Soc. Am.*, 42, 373, 1952.
349. Paschen, F., *Ann. Physik*, 424, 148, 1938.
350. Paschen, F. and Campbell, J. S., *Ann. Phys.*, 31(5), 29, 1938.
351. Nodwell, R., *Univ. of British Columbia, Vancouver*, unpublished, 1955.
352. Gibbs, R. C. and White, H. E., *Phys. Rev.*, 31, 776, 1928.
353. Green, M., *Phys. Rev.*, 60, 117, 1941.
354. Ellis, C. B. and Sawyer, R. A., *Phys. Rev.*, 49, 145, 1936.
355. McLennan, J. C., McLay, A. B., and Crawford, M. F., *Proc. R. Soc. London Ser. A*, 125, 50, 1929.
356. Mack, J. E. and Fromer, M., *Phys. Rev.*, 48, 346, 1935.
357. Humphreys, C. J. and Paul, E., U.S. Nav. Ord. Lab., Navord Rep. 4589, 25, 1956.
358. Walters, F. M., *Sci. Pap. Bur. Stand.*, 17, 161, 1921.
359. Crawford, M. F. and McLay, A. B., *Proc. R. Soc. London Ser. A*, 143, 540, 1934.
360. McLay, A. D. and Crawford, M. F., *Phys. Rev.*, 44, 986, 1933.
361. Schoepfle, G. K., *Phys. Rev.*, 47, 232, 1935.
362. Acquista, N., and Reader, J., *J. Opt. Soc. Am.*, 70, 789, 1980.
363. Benschop, H., Joshi, Y. N., and van Kleef, T. A. M., *Can. J. Phys.*, 53, 498, 1975.
364. Bockasten, K., Hallin, R., and Hughes, T. P., *Proc. Phys. Soc.*, 81, 522, 1963.
365. Boyce, J. C., *Phys. Rev.*, 46, 378, 1934.
366. Boyce, J. C., *Phys. Rev.*, 47, 718, 1935.
367. Boyce, J. C., *Phys. Rev.*, 48, 396, 1935.
368. Boyce, J. C., *Phys. Rev.*, 49, 351, 1936.
369. Corliss, C. H. and Meggers, W. F., *J. Res. Natl. Bur. Stand.*, 61, 269, 1958.
370. Crooker, A. M. and Dick, K. A., *Can. J. Phys.*, 42, 766, 1964.
371. De Bruin, T. L., *Z. Physik*, 77, 505, 1932.
372. De Bruin, T. L., *Proc. Roy. Acad. Amsterdam*, 36, 727, 1933.
373. De Bruin, T. L., *Zeeman Verhandelingen*, (The Hague), 1935, p. 415.
374. De Bruin, T. L., *Physica*, 3, 809, 1936.
375. De Bruin, T. L., Proc. Roy. Acad. Amsterdam, 40, 339, 1937.
376. Dick, K. A., *Can. J. Phys.*, 46, 1291, 1968.
377. Dick, K. A., unpublished, 1978.
378. Edlen, B. and Swensson, J. W., *Phys. Scr.*, 12, 21, 1975.
379. Ekberg, J. O., *Phys. Scr.*, 7, 55, 1973.
380. Ekberg, J. O., *Phys. Scr.*, 7, 59, 1973.
381. Ekberg, J. O., *Phys. Scr.*, 12, 42, 1975.
382. Ekberg, J. O. and Edlen, B., *Phys. Scr.*, 18, 107, 1978.
383. Eliason, A. Y., *Phys. Rev.*, 43, 745, 1933.
384. Gallardo, M., Massone, C. A., Tagliaferri, A. A., Garavaglia, M., and Persson, W., *Phys. Scr.*, 19, 538, 1979.
385. Garcia-Riquelme, O., *Optica Pura Y Aplicada*, 1, 53, 1968.
386. Gibbs, R. C., Vieweg, A. M., and Gartlein, C. W., *Phys. Rev.*, 34, 406, 1929.
387. Gilbert, W. P., *Phys. Rev.*, 48, 338, 1935.
388. Goldsmith, S. and Kaufman, A. S., *Proc. Phys. Soc.*, 81, 544, 1963.
389. Hermansdorfer, H., *J. Opt. Soc. Am.*, 62, 1149, 1972.
390. Humphreys, C. J., *Phys. Rev.*, 47, 712, 1935.
391. Humphreys, C. J., *J. Res. Natl. Bur. Stand.*, 16, 639, 1936.
392. Iglesias, L., *J. Opt. Soc. Am.*, 45, 856, 1955.
393. Iglesias, L., *J. Res. Natl. Bur. Stand.*, 64A, 481, 1960.
394. Iglesias, L., Anales Fisica Y Quimica, 58A, 191, 1962.
395. Iglesias, L., *J. Res. Natl. Bur. Stand.*, 70A, 465, 1966.
396. Iglesias, L., *Can. J. Phys.*, 44, 895, 1966.
397. Iglesias, L., *J. Res. Natl. Bur. Stand.*, 72A, 295, 1968.
398. Joshi, Y. N., *Can. Spectrosc.*, 15, 96, 1970.
399. Joshi, Y. N. and van Kleef, T. A. M., *Can. J. Phys.*, 55, 714, 1977.
400. Kaufman, A. S., Hughes, T. P., and Williams, R. V., *Proc. Phys. Soc.*, 76, 17, 1960.
401. Kaufman, V. and Sugar, J., *J. Opt. Soc. Am.*, 68, 1529, 1978.
402. Keussler, V., *Z. Physik, 85*, 1, 1933.
403. Kiess, C. C., *J. Res. Natl. Bur. Stand.*, 56, 167, 1956.
404. Klinkenberg, P. F. A., van Kleef, T. A. M., and Noorman, P. E., *Physica*, 27, 1177, 1961.
405. Kovalev, V. I., Romanos, A. A., and Ryabtsev, A. N., *Opt. Spectrosc.*, 43, 10, 1977.
406. Lang, R. J., *Proc. Natl. Acad. Sci.*, 13, 341, 1927.
407. Lang, R. J., *Zeeman Verhandelingen*, (The Hague), 44, 1935.
408. Liberman, S., et al., *C. R. Acad. Sci.* (Paris), 286, 253, 1978.
409. Livingston, A. E., *J. Phys.*, B9, L215, 1976.
410. Meijer, F. G., *Physica*, 72, 431, 1974.
411. Meijer, F. G. and Metsch, B. C., *Physica*, 94C, 259, 1978.
412. Moore, F. L., thesis, Princeton, 1949.
413. Paul, F. W. and Polster, H. D., *Phys. Rev.*, 59, 424, 1941.
414. Phillips, L. W. and Parker, W. L., *Phys. Rev.*, 60, 301, 1941.
415. Poppe, R., *Physica*, 81C, 351, 1976.
416. Raassen, A. J. J., van Kleef, T. A. M., and Metsch, B. C., *Physica*, 84C, 133, 1976.
417. Rao, A. B. and Krishnamurty, S. G., *Proc. Phys. Soc. (London)*, 51, 772, 1939.
418. Reader, J. and Acquista, N., *J. Opt. Soc. Am.*, 69, 239, 1979.
419. Reader, J. and Epstein, G. L., *J. Opt. Soc. Am.*, 62, 619, 1972.
420. Rico, F. R., *Anales, Real Soc. Esp. Fis. Quim.*, 61, 103, 1965.
421. Schonheit, E., *Optik*, 23, 409, 1966.
422. Shenstone, A. G., *J. Opt. Soc. Am.*, 44, 749, 1954.
423. Shenstone, A. G., unpublished, 1958.
424. Shenstone, A. G., *J. Res. Natl. Bur. Stand.*, 67A, 87, 1963.
425. Sugar, J. and Kaufman, V., *J. Opt. Soc. Am.*, 64, 1656, 1974.
426. Sugar, J. and Kaufman, V., *Phys. Rev.*, C12, 1336, 1975.
427. Svensson, L. A., *Phys. Scr.*, 13, 235, 1976.
428. Swensson, J. W. and Edlen, B., *Phys. Scr.*, 9, 335, 1974.
429. Tagliaferri, A. A., Gallego Lluesma, E., Garavaglia, M., Gallardo, M., and Massone, C. A., *Optica Pura Y Aplica*, 7, 89.
430. Tilford, S. G. and Giddings, L. E., *Astrophys.* J., 141, 1222, 1965.
431. Trawick, M. W., *Phys. Rev.*, 46, 63, 1934.
432. Van Deurzen, C. H. H., *J. Opt. Soc. Am.*, 67, 476, 1977.
433. Yarosewick, S. L. and Moore, F. L., *J. Opt. Soc. Am.*, 57, 1381, 1967.
434. Zalubas, R., unpublished, 1979.
435. Bhatia, K. S., Jones, W. E., and Crooker, A. M., *Can. J. Phys.*, 50, 2421, 1972.
436. van Kleef, T. A. M. and Joshi, Y. N., *Phys. Scr.*, 24, 557, 1981.

NIST ATOMIC TRANSITION PROBABILITIES

J. R. Fuhr and W. L. Wiese

For the 2005 edition of this *Handbook*, we include new, more accurate data for Fe I and Fe II,[1] and Ba I and Ba II.[2] The new tables contain critically evaluated atomic transition probabilities for over 10500 selected lines of all elements for which reliable data are available on an absolute scale. The material is largely for neutral and singly ionized spectra, but also includes a number of prominent lines of more highly charged ions of important elements.

Many of the data are obtained from comprehensive compilations of the Data Center on Atomic Transition Probabilities at the National Institute of Standards and Technology. Specifically, data have been taken from three recent comprehensive critical compilations on C, N and O,[3] on Sc through Mn[4] and Fe through Ni,[5] and special compilations on neutral and singly ionized iron and barium. Material from earlier compilations for the elements H through Ne[6] and Na through Ca[7] was supplemented by more recent material taken directly from the original literature. For the highly charged ions, some of the data were derived from studies of the systematic behavior of transition probabilities.[8-10] Most of the original literature is cited in the above tables and in recent bibliographies;[11,12] for lack of space, individual literature references are not cited here.

The wavelength range for the neutral species is normally the visible spectrum or shorter wavelengths; only the very prominent near infrared lines are included. For the higher ions, most of the strong lines are located in the far UV. The tabulation is limited to electric dipole — including intercombination — lines and comprises essentially the fairly strong transitions with estimated uncertainties in the 10% to 50% range. With the exception of hydrogen, helium, and the alkali metals, most transitions are between states with low principal quantum numbers.

The transition probability, A, is given in units of 10^8 s^{-1} and is listed to as many digits as is consistent with the indicated accuracy. The power of 10 is indicated by the E notation (i.e., E-02 means 10^{-2}). Generally, the estimated uncertainties of the A-values are ±25 to 50% for two-digit numbers, ±10 to 25% for three-digit numbers and ±1% or better for four- and five-digit numbers.

Each transition is identified by the wavelength λ in ångströms (1 Å = 10^{-10} m); and the statistical weights, g_i and g_k, of the lower (i) and upper (k) states [the product g_kA (or g_if) is needed for many applications]. Whenever the wavelengths of individual lines within a multiplet are extremely close, only an average wavelength for the multiplet as well as the multiplet A-value are given, and this is indicated by an asterisk (*) to the left of the wavelength. This also has been done when the transition probability for an entire multiplet has been taken from the literature and values for individual lines cannot be determined because of insufficient knowledge of the coupling of electrons. The wavelength data have been taken either from recent compilations or from the original literature cited in bibliographies published by the Atomic Energy Levels Data Center[13,14] at the National Institute of Standards and Technology. Wavelength values are consistent with those given in the table "Line Spectra of the Elements," which appears elsewhere in this *Handbook*.

In addition to the transition probability A, the atomic oscillator strength f and the line strength S are often used in the literature. The conversion factors between these quantities are (for electric-dipole transitions):

$$g_i f = 1.499 \cdot 10^{-8}\, \lambda^2 g_k A = 303.8\, \lambda^{-1}\, S$$

where λ is in ångströms, A is in 10^8 s^{-1}, and S is in atomic units, which are

$$a_0^2 e^2 = 7.188 \cdot 10^{-59}\ \mathrm{m^2\, C^2}.$$

The table for hydrogen is presented first, followed by the tables for other elements in alphabetical sequence by element name (not symbol). Within each element, the tables are ordered by increasing ionization stage (e.g., Al I, Al II, etc.).

The transition probabilities for hydrogen and hydrogen-like ions are known precisely. Because of the hydrogen degeneracy, a "transition" is actually the sum of all fine-structure transitions between the principal quantum numbers; therefore, the hydrogen table gives weighted average A-values. For hydrogen-like ions of nuclear charge Z, the following scaling laws hold:

$$A_Z = Z^4 A_{\mathrm{Hydrogen}}$$

$$f_Z = f_{\mathrm{Hydrogen}}$$

$$S_Z = Z^{-2} S_{\mathrm{Hydrogen}}$$

$$\lambda_Z = Z^{-2} \lambda_{\mathrm{Hydrogen}}$$

For very highly charged hydrogen-like ions, starting at about Z>25, relativistic corrections[15] must be applied.

References

1. J. R. Fuhr and W. L. Wiese, A Critical Compilation of Atomic Transition Probabilities for Neutral and Singly-Ionized Iron, *J. Phys. Chem. Ref. Data*, to be published, 2005.
2. J. Z. Klose, J. R. Fuhr, and W. L. Wiese, Critically Evaluated Atomic Transition Probabilities for Ba I and Ba II, *J. Phys. Chem. Ref. Data*, 31, 217 (2002).
3. W. L. Wiese, J. R. Fuhr and T. M. Deters, Atomic Transition Probabilities for Carbon, Nitrogen and Oxygen, *J. Phys. Chem. Ref. Data*, Monograph 7, 1996.
4. G. A. Martin, J. R. Fuhr, and W. L. Wiese, Atomic Transition Probabilities — Scandium through Manganese, *J. Phys. Chem. Ref. Data, 17, Suppl.* 3, 1988.
5. J. R. Fuhr, G. A. Martin, and W. L. Wiese, Atomic Transition Probabilities — Iron through Nickel, *J. Phys. Chem. Ref. Data, 17, Suppl.* 4, 1988.
6. W. L. Wiese, M. W. Smith, and B. M. Glennon, Atomic Transition Probabilities (H through Ne — A Critical Data Compilation), National Standard Reference Data Series, National Bureau of Standards 4, Vol. I, U.S. Government Printing Office, Washington, D.C., 1966.
7. W. L. Wiese, M. W. Smith, and B. M. Miles, Atomic Transition Probabilities (Na through Ca — A Critical Data Compilation), National Standard Reference Data Series, National Bureau of Standards 22, Vol. II, U. S. Government Printing Office, Washington, D.C., 1969.
8. W. L. Wiese and A. W. Weiss, *Phys. Rev.*, 175, 50, 1968.
9. M. W. Smith and W. L Wiese, *Astrophys. J., Suppl. Ser.,* 23, No. 196, 103, 1971.
10. G. A. Martin and W. L. Wiese, *J. Phys. Chem. Ref. Data,* 5, 537, 1976.
11. J. R. Fuhr, H. R. Felrice, K. Olsen, J. Hwang, and S. Kotochigova, Atomic Transition Probability Bibliographic Database, <http://physics.nist.gov/fvalbib>.
12. W. L. Wiese, Reports on Astronomy, *Trans. Int. Astron. Union*, 18A, 116-123, 1982; 19A, 122-138, 1985; 20A, 117-123, 1988; 21A, 111-

116, 1991; 22A, 109-114, 1994; 23A, 13-17, 1997; 24A, 2-9, 1999; 25A, 383-391, 2003, D. Reidel, Kluwer, Dordrecht, Holland.

13. C. E. Moore, Bibliography on the Analyses of Optical Atomic Spectra, National Bureau of Standards Special Publication 306 — Section 1, 1968; Sections 2-4, 1969.
14. L. Hagan and W. C. Martin, Bibliography on Atomic Energy Levels and Spectra (July 1968 through June 1971), National Bureau of Standards Special Publication 363, 1972; L. Hagan, Bibliography on Atomic Energy Levels and Spectra (July 1971 through June 1975), National Bureau of Standards Special Publication 363, Supplement 1, 1977; R. Zalubas and A. Albright, Bibliography on Atomic Energy Levels and Spectra (July 1975 through June 1979), National Bureau of Standards Special Publication 363, Supplement 2, 1980; A. Musgrove and R. Zalubas, Bibliography on Atomic Energy Levels and Spectra (July 1979 through December 1983), National Bureau of Standards Special Publication 363, Supplement 3, 1985.
15. S. M. Younger and A. Weiss, *J. Res. Natl. Bur. Stand.*, 79A, 629, 1975.

λ	Weights		*A*
Å	g_i	g_k	10^8 s^{-1}
Hydrogen			
H I			
912.768	2	1800	5.167E-06
912.839	2	1682	6.122E-06
912.918	2	1568	7.297E-06
913.006	2	1458	8.753E-06
913.104	2	1352	1.057E-05
913.215	2	1250	1.286E-05
913.339	2	1152	1.578E-05
913.480	2	1058	1.952E-05
913.641	2	968	2.438E-05
913.826	2	882	3.077E-05
914.039	2	800	3.928E-05
914.286	2	722	5.077E-05
914.576	2	648	6.654E-05
914.919	2	578	8.858E-05
915.329	2	512	1.200E-04
915.824	2	450	1.657E-04
916.429	2	392	2.341E-04
917.181	2	338	3.393E-04
918.129	2	288	5.066E-04
919.351	2	242	7.834E-04
920.963	2	200	1.263E-03
923.150	2	162	2.143E-03
926.226	2	128	3.869E-03
930.748	2	98	7.568E-03
937.803	2	72	1.644E-02
949.743	2	50	4.125E-02
972.537	2	32	1.278E-01
1025.72	2	18	5.575E-01
1215.67	2	8	4.699E+00
3662.26	8	1800	2.847E-06
3663.40	8	1682	3.374E-06
3664.68	8	1568	4.022E-06
3666.10	8	1458	4.826E-06
3667.68	8	1352	5.830E-06
3669.46	8	1250	7.096E-06
3671.48	8	1152	8.707E-06
3673.76	8	1058	1.078E-05
3676.36	8	968	1.347E-05
3679.35	8	882	1.700E-05
3682.81	8	800	2.172E-05
3686.83	8	722	2.809E-05
3691.55	8	648	3.685E-05
3697.15	8	578	4.910E-05
3703.85	8	512	6.658E-05
3711.97	8	450	9.210E-05
3721.94	8	392	1.303E-04
3734.37	8	338	1.893E-04
3750.15	8	288	2.834E-04
3770.63	8	242	4.397E-04
3797.90	8	200	7.122E-04
3835.38	8	162	1.216E-03
3889.05	8	128	2.215E-03
3970.07	8	98	4.389E-03
4101.73	8	72	9.732E-03
4340.46	8	50	2.530E-02
4861.32	8	32	8.419E-02
6562.80	8	18	4.410E-01
8392.40	18	800	1.517E-05
8413.32	18	722	1.964E-05
8437.96	18	648	2.580E-05
8467.26	18	578	3.444E-05
8502.49	18	512	4.680E-05
8545.39	18	450	6.490E-05
8598.40	18	392	9.211E-05
8665.02	18	338	1.343E-04
8750.48	18	288	2.021E-04
8862.79	18	242	3.156E-04
9014.91	18	200	5.156E-04
9229.02	18	162	8.905E-04
9545.97	18	128	1.651E-03
10049.4	18	98	3.358E-03
10938.1	18	72	7.783E-03
12818.1	18	50	2.201E-02
16407.2	32	288	1.620E-04
16806.5	32	242	2.556E-04
17362.1	32	200	4.235E-04
18174.1	32	162	7.459E-04
18751.0	18	32	8.986E-02
19445.6	32	128	1.424E-03
21655.3	32	98	3.041E-03
26251.5	32	72	7.711E-03
27575	50	288	1.402E-04
28722	50	242	2.246E-04
30384	50	200	3.800E-04
32961	50	162	6.908E-04
37395	50	128	1.388E-03
40511.5	32	50	2.699E-02
43753	72	288	1.288E-04
46525	50	98	3.253E-03
46712	72	242	2.110E-04
51273	72	200	3.688E-04
59066	72	162	7.065E-04
74578	50	72	1.025E-02
75004	72	128	1.561E-03
123680	72	98	4.561E-03
Aluminum			
Al I			
2263.5	2	4	6.6E-01
2269.1	4	6	7.9E-01
2269.2	4	4	1.3E-01
2367.1	2	4	7.2E-01
2373.1	4	6	8.6E-01
2373.4	4	4	1.4E-01
2568.0	2	4	2.3E-01
2575.1	4	6	2.8E-01
2575.4	4	4	4.4E-02
2652.5	2	2	1.33E-01
2660.4	4	2	2.64E-01
3082.2	2	4	6.3E-01
3092.7	4	6	7.4E-01
3092.8	4	4	1.2E-01
3944.0	2	2	4.93E-01
3961.5	4	2	9.8E-01
6696.0	2	4	1.69E-02
6698.7	2	2	1.69E-02
7835.3	4	6	5.7E-02
7836.1	6	8	6.2E-02
Al II			
1047.9	1	3	3.6E-01
1048.6	3	5	4.8E-01
1539.8	3	5	8.8E+00
1670.8	1	3	1.46E+01
1719.4	1	3	6.79E+00
1764.0	5	5	9.8E+00
1772.8	1	3	9.5E+00
1777.0	5	7	1.7E+01
*1819.0	15	15	5.6E+00
1855.9	1	3	8.32E-01
1858.0	3	3	2.48E+00
1862.3	5	3	4.12E+00
1931.0	3	1	1.08E+01
1990.5	3	5	1.47E+01
2816.2	3	1	3.83E+00
4663.1	5	3	5.3E-01
6226.2	1	3	6.2E-01
6231.8	3	5	8.4E-01
6243.4	5	7	1.1E+00
6335.7	5	3	1.4E-01
6823.4	3	3	3.4E-01
6837.1	5	3	5.7E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
6920.3	3	1	9.6E-01
7042.1	3	5	5.9E-01
7056.7	3	3	5.8E-01
7471.4	5	7	9.4E-01
Al III			
*560.36	2	6	4.0E-01
695.83	2	4	7.4E-01
696.22	2	2	7.2E-01
*1352.8	10	14	4.40E+00
1379.7	2	2	4.59E+00
1384.1	4	2	9.1E+00
1605.8	2	4	1.22E+01
1611.8	4	4	2.42E+00
1611.9	4	6	1.45E+01
1854.7	2	4	5.40E+00
1862.8	2	2	5.33E+00
*1935.9	10	14	1.22E+01
3601.6	6	4	1.34E+00
3601.9	4	4	1.49E-01
3612.4	4	2	1.5E+00
Al X			
39.925	1	3	2.22E+03
51.979	1	3	4.8E+03
55.227	1	3	5.2E+03
55.272	3	5	7.2E+03
55.376	5	7	9.5E+03
59.107	3	5	4.6E+03
332.78	1	3	5.6E+01
394.83	3	1	8.3E+01
395.36	3	5	1.2E+01
397.76	1	3	1.7E+01
400.43	3	3	1.3E+01
401.12	5	5	3.6E+01
403.55	3	1	4.9E+01
406.31	5	3	1.9E+01
670.06	3	5	9.8E+00
2535	1	3	3.8E-01
Al XI			
*36.675	2	6	1.5E+03
39.091	2	4	2.6E+03
39.180	4	6	3.1E+03
39.530	2	2	1.8E+02
39.623	4	2	3.7E+02
48.298	2	4	3.09E+03
48.338	2	2	3.08E+03
52.299	2	4	8.1E+03
52.446	4	6	9.6E+03
52.458	4	4	1.6E+03
54.217	2	2	4.8E+02
54.388	4	2	9.6E+02
*99.083	2	6	2.2E+02
103.6	2	4	4.2E+02
103.8	4	6	5.0E+02
*141.6	2	6	4.07E+02
150.31	2	4	8.5E+02
150.61	4	6	9.9E+02
157.0	2	2	1.3E+02
157.4	4	2	2.6E+02
*205.0	2	6	6.3E+01
*308.6	2	6	9.9E+01
*341.3	6	2	1.3E+02
550.05	2	4	8.55E+00
568.12	2	2	7.73E+00
1997	2	4	1.07E+00
2069	2	2	9.7E-01
*4761	2	6	2.55E-01
5172	2	4	3.95E-02
5551	4	6	3.85E-02
5687	4	4	6.0E-03
Argon			
Ar I			
1048.22	1	3	5.36E+00
1066.66	1	3	1.29E+00
3406.18	3	1	3.9E-03
3461.08	3	5	6.7E-04
3554.30	5	5	2.7E-03
3563.29	1	3	1.2E-03
3567.66	5	7	1.1E-03
3572.30	3	1	5.1E-03
3606.52	3	1	7.6E-03
3632.68	3	5	6.6E-04
3634.46	3	3	1.3E-03
3643.12	3	5	2.4E-04
3649.83	3	1	8.0E-03
3659.53	3	3	4.4E-04
3670.67	3	5	3.1E-04
3675.23	3	3	4.9E-04
3770.37	1	3	7.0E-04
3834.68	3	1	7.5E-03
3894.66	3	3	5.7E-04
3947.50	5	5	5.6E-04
3948.98	5	3	4.55E-03
4044.42	3	5	3.33E-03
4045.96	3	3	4.1E-04
4054.53	3	3	2.7E-04
4158.59	5	5	1.40E-02
4164.18	5	3	2.88E-03
4181.88	1	3	5.61E-03
4190.71	5	5	2.80E-03
4191.03	1	3	5.39E-03
4198.32	3	1	2.57E-02
4200.67	5	7	9.67E-03
4251.18	5	3	1.11E-03
4259.36	3	1	3.98E-02
4266.29	3	5	3.12E-03
4272.17	3	3	7.97E-03
4300.10	3	5	3.77E-03
4333.56	3	5	5.68E-03
4335.34	3	3	3.87E-03
4345.17	3	3	2.97E-03
4363.79	3	3	1.2E-04
4424.00	1	3	7.3E-05
4510.73	3	1	1.18E-02
4522.32	1	3	8.98E-04
4544.75	3	3	8.3E-04
4554.32	3	5	3.8E-04
4584.96	3	5	1.6E-03
4586.61	3	3	2.3E-03
4587.21	3	1	4.9E-03
4589.29	3	5	6.2E-05
4596.10	3	3	9.47E-04
4628.44	3	5	3.83E-04
4642.15	3	5	9.6E-04
4647.49	3	3	1.2E-03
4702.32	3	3	1.09E-03
4746.82	3	1	3.6E-03
4752.94	3	3	4.5E-03
4768.68	3	5	8.6E-03
4798.74	7	9	8.8E-04
4835.97	7	9	9.3E-04
4836.70	3	5	1.02E-03
4876.26	3	5	7.8E-03
4886.29	7	9	1.2E-03
4887.95	3	3	1.3E-02
4894.69	3	1	1.8E-02
4921.04	5	7	5.9E-04
4937.72	7	5	3.6E-04
4956.75	7	9	1.8E-03
4989.95	5	7	1.1E-03
5032.03	7	5	8.2E-04
5048.81	3	5	4.6E-03
5054.18	3	3	4.5E-03
5056.53	3	1	5.7E-03
5060.08	7	9	3.7E-03
5070.99	5	3	2.6E-03
5073.08	3	5	5.9E-04
5078.03	7	7	4.7E-04
5087.09	5	7	1.6E-03
5104.74	3	5	8.7E-04
5118.21	5	7	2.7E-03
5127.80	5	5	3.3E-04
5151.39	3	1	2.39E-02
5152.30	3	5	1.1E-03
5162.29	3	3	1.90E-02
5177.54	7	5	2.4E-03
5192.72	7	7	1.2E-04
5194.02	3	1	7.8E-03
5210.49	7	7	1.1E-03
5214.77	5	3	2.1E-03
5216.28	5	3	1.3E-03
5221.27	7	9	8.8E-03
5241.09	5	5	1.3E-03
5246.24	5	7	1.2E-03
5249.20	5	5	7.9E-04
5252.79	5	7	5.4E-03
5254.47	3	5	3.6E-03
5286.07	5	7	9.6E-04
5290.00	5	3	9.0E-04
5309.52	5	5	1.2E-03
5317.73	5	7	2.6E-03
5373.50	3	5	2.7E-03
5393.27	5	5	9.6E-04
5410.48	5	7	2.0E-03
5421.35	7	5	6.0E-03
5439.99	3	3	1.9E-03
5442.24	7	7	9.3E-04
5451.65	3	5	4.7E-03
5457.42	5	3	3.6E-03

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
5459.65	7	7	3.8E-04
5467.16	5	5	7.6E-04
5473.46	5	3	2.0E-03
5490.12	5	5	8.5E-04
5492.09	3	1	5.6E-03
5495.87	7	9	1.69E-02
5506.11	5	7	3.6E-03
5524.96	7	7	1.7E-03
5528.97	1	3	1.2E-03
5534.49	5	3	2.7E-03
5540.87	7	5	4.1E-04
5552.77	3	3	7.9E-04
5558.70	3	5	1.42E-02
5559.66	3	5	2.2E-03
5572.54	5	7	6.6E-03
5574.22	3	5	4.6E-04
5581.87	7	5	5.6E-04
5588.72	5	5	1.5E-03
5597.48	5	7	4.2E-03
5606.73	3	3	2.20E-02
5618.01	3	3	2.1E-03
5620.92	3	1	3.6E-03
5623.78	5	5	1.4E-03
5635.58	3	5	9.6E-04
5637.33	1	3	9.1E-04
5639.12	1	3	2.1E-03
5641.39	3	5	8.7E-04
5648.69	5	3	1.2E-03
5650.70	3	1	3.20E-02
5659.13	5	5	2.6E-03
5681.90	5	7	2.0E-03
5683.73	5	5	2.0E-03
5700.87	5	7	5.9E-03
5712.51	1	3	8.7E-04
5739.52	3	5	8.7E-03
5772.11	5	7	2.0E-03
5773.99	5	5	1.1E-03
5783.54	3	5	8.1E-04
5789.48	5	5	4.6E-04
5790.40	5	3	3.4E-04
5802.08	5	3	4.2E-03
5843.77	3	5	3.3E-04
5882.62	3	1	1.23E-02
5888.58	7	5	1.29E-02
5916.58	5	3	5.9E-04
5927.11	7	7	3.7E-04
5928.81	5	3	1.1E-02
5940.86	1	3	1.2E-03
5942.67	5	5	1.8E-03
5943.89	7	5	3.6E-04
5949.26	3	3	1.5E-03
5964.48	1	3	7.7E-04
5968.32	3	3	1.8E-03
5971.60	3	1	1.1E-02
5981.90	5	7	1.2E-04
5987.30	7	7	1.2E-03
5988.13	3	5	6.1E-04
5994.66	3	5	2.6E-04
5999.00	5	5	1.4E-03
6005.73	5	3	1.4E-03
6013.68	7	5	1.4E-03
6025.15	5	3	9.0E-03
6043.22	5	7	1.47E-02
6052.73	3	5	1.9E-03
6064.76	5	7	5.8E-04
6081.25	3	3	7.5E-04
6085.86	3	3	9.0E-05
6090.79	1	3	3.0E-03
6098.81	3	3	5.2E-03
6101.16	3	3	3.3E-03
6104.58	3	1	3.4E-03
6105.64	3	5	1.21E-02
6113.46	3	5	4.7E-04
6119.66	3	3	5.1E-04
6121.86	3	5	1.3E-04
6127.42	5	3	1.1E-03
6128.73	3	5	8.6E-04
6145.44	5	7	7.6E-03
6155.24	5	3	5.1E-03
6165.12	5	5	9.89E-04
6170.17	5	5	5.0E-03
6173.10	3	5	6.7E-03
6179.41	5	3	6.6E-04
6212.50	5	7	3.9E-03
6215.94	5	5	5.7E-03
6230.93	5	5	1.2E-04
6243.40	3	1	1.3E-03
6244.73	3	5	2.0E-04
6248.41	3	5	6.8E-04
6278.65	5	7	2.0E-04
6296.87	3	5	9.0E-03
6307.66	5	5	6.0E-03
6309.14	3	3	7.6E-04
6364.89	3	1	5.6E-03
6369.58	5	3	4.2E-03
6384.72	3	3	4.21E-03
6416.31	3	5	1.16E-02
6431.56	5	3	5.1E-04
6466.55	1	3	1.5E-03
6481.14	1	3	9.4E-04
6513.85	3	3	5.4E-04
6538.11	7	7	1.1E-03
6596.12	7	5	2.3E-04
6598.68	5	5	3.6E-04
6604.02	7	5	2.8E-03
6604.85	5	7	1.3E-04
6632.09	3	3	5.3E-04
6656.88	3	3	3.1E-04
6660.68	3	1	7.8E-03
6664.05	5	5	1.5E-03
6677.28	3	1	2.36E-03
6684.73	3	5	3.9E-04
6698.47	3	3	2.5E-04
6698.88	5	3	1.6E-03
6719.22	1	3	2.4E-03
6722.88	5	7	3.2E-04
6752.84	3	5	1.93E-02
6754.37	3	3	2.1E-03
6756.10	5	5	3.6E-03
6766.61	5	3	4.0E-03
6779.93	1	3	1.21E-03
6818.29	3	1	2.0E-03
6827.25	5	3	2.4E-03
6851.88	3	5	6.7E-04
6871.29	3	3	2.78E-02
6879.59	3	5	1.8E-03
6887.10	5	7	1.3E-03
6888.17	3	5	2.5E-03
6925.01	3	3	1.2E-03
6937.67	3	1	3.08E-02
6951.46	5	5	2.2E-03
6960.23	5	5	2.4E-03
6965.43	5	3	6.39E-02
6992.17	3	1	7.5E-03
7030.25	7	5	2.67E-02
7067.22	5	5	3.80E-02
7068.73	5	3	2.0E-02
7086.70	1	3	1.5E-03
7107.48	5	5	4.5E-03
7125.83	3	3	6.0E-03
7147.04	5	3	6.25E-03
7158.83	3	1	2.1E-02
7162.57	1	3	5.8E-04
7206.98	5	3	2.48E-02
7229.93	5	5	6.6E-04
7265.17	3	3	1.7E-03
7270.66	7	7	1.1E-03
7272.93	3	3	1.83E-02
7285.44	5	3	1.2E-03
7311.72	3	3	1.7E-02
7316.01	3	3	9.6E-03
7350.78	3	1	1.2E-02
7353.32	5	7	9.6E-03
7372.12	7	9	1.9E-02
7383.98	3	5	8.47E-02
7392.97	5	3	7.2E-03
7412.33	3	5	3.9E-03
7422.26	3	5	6.6E-04
7425.29	5	7	3.1E-03
7435.33	5	5	9.0E-03
7436.25	7	5	2.7E-03
7471.17	3	3	2.2E-04
7484.24	3	5	3.4E-03
7503.84	3	1	4.45E-01
7510.42	5	5	4.5E-03
7514.65	3	1	4.02E-01
7618.33	3	5	2.9E-03
7628.86	3	5	2.9E-03
7635.11	5	5	2.45E-01
7670.04	5	3	2.8E-03
7704.81	5	7	6.3E-04
7723.76	5	3	5.18E-02
7724.21	1	3	1.17E-01
7798.55	3	5	8.7E-04
7868.20	1	3	3.50E-03
7891.08	5	5	9.5E-03
7916.45	3	3	1.2E-03
7948.18	1	3	1.86E-01
8006.16	3	5	4.90E-02
8014.79	5	5	9.28E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
8037.23	1	3	3.59E-03
8046.13	3	1	1.12E-02
8053.31	5	3	8.6E-03
8066.60	5	5	1.4E-03
8103.69	3	3	2.5E-01
8115.31	5	7	3.31E-01
8264.52	3	3	1.53E-01
8384.73	5	7	2.4E-03
8408.21	3	5	2.23E-01
8424.65	3	5	2.15E-01
8490.30	3	5	9.6E-04
8521.44	3	3	1.39E-01
8605.78	5	5	1.04E-02
8620.46	1	3	9.2E-03
8667.94	1	3	2.43E-02
8761.69	3	5	9.5E-03
8784.61	3	1	2.4E-03
8799.08	5	3	4.6E-03
8962.19	3	3	1.6E-03
9075.42	3	1	1.2E-02
9122.97	5	3	1.89E-01
9194.64	3	3	1.76E-02
9224.50	3	5	5.03E-02
9291.53	3	1	3.26E-02
9354.22	3	3	1.06E-02
9657.78	3	3	5.43E-02
9784.50	3	5	1.47E-02
10470.05	1	3	9.8E-03
10478.0	3	3	2.44E-02
10950.7	5	3	3.96E-03
11078.9	5	5	8.3E-03
11393.7	3	1	2.22E-02
11441.8	5	3	1.39E-02
11467.5	3	5	3.69E-03
11488.11	3	3	1.9E-03
11668.7	5	5	3.76E-02
11719.5	5	3	9.52E-03
12026.6	1	3	4.2E-03
12112.2	7	7	3.1E-02
12139.8	3	3	4.5E-02
12343.7	5	7	2.0E-02
12402.9	3	3	1.1E-01
12439.2	3	5	4.9E-02
12456.1	5	3	8.9E-02
12487.6	7	5	1.1E-01
12554.4	7	5	1.2E-03
12702.4	3	3	7.1E-02
12733.6	5	5	1.1E-02
12746.3	3	3	2.0E-02
12802.7	5	5	5.7E-02
12933.3	3	1	1.0E-01
12956.6	3	3	7.4E-02
13008.5	5	3	8.9E-02
13214.7	3	1	8.1E-02
13273.1	5	7	1.5E-01
13313.4	3	5	1.3E-01
13504.0	5	7	1.1E-01
13599.2	5	5	2.2E-02
13622.4	3	5	7.3E-02
13678.5	3	5	6.2E-02
14093.6	1	3	4.3E-02
14739.1	5	7	8.8E-04
15046.4	1	3	5.2E-02
15172.3	1	3	1.3E-02
15329.6	5	5	1.2E-03
15555.5	5	7	9.8E-05
15734.9	5	3	2.9E-04
15816.8	5	3	8.7E-04
15989.3	1	3	1.9E-02
16122.7	5	3	3.9E-04
16180.0	5	5	1.2E-03
16264.1	3	3	3.0E-04
16520.1	3	5	2.6E-03
16739.8	3	5	3.1E-03
16940.4	5	5	2.5E-02
20317.0	1	3	1.6E-03
20616.5	5	5	3.9E-03
20812.0	5	7	7.6E-04
21332.2	3	3	3.2E-04
21534.9	3	5	1.1E-03
22039.2	3	1	1.2E-03
22077.4	5	3	1.4E-03
23133.4	3	3	1.7E-03
23844.8	9	7	1.1E-02
23967.5	3	1	3.6E-03
Ar II			
2317.7	6	4	1.4E-01
2891.6	4	2	1.82E-01
2942.9	4	4	5.3E-01
2979.1	2	2	4.16E-01
3033.5	2	4	9.9E-02
3139.0	6	6	5.2E-01
3169.7	4	6	4.9E-01
3181.0	6	4	3.7E-01
3212.5	4	4	5.2E-02
3221.6	6	6	1.8E-02
3226.0	4	4	2.1E-02
3243.7	4	2	1.06E+00
3249.8	2	4	6.3E-01
3263.6	2	4	1.55E-01
3281.7	2	2	4.2E-01
3430.4	6	8	6.2E-02
3454.1	6	4	3.14E-01
3466.3	8	6	3.0E-02
3476.7	6	6	1.25E+00
3491.2	4	4	1.79E+00
3491.5	6	8	2.31E+00
3509.8	2	2	2.55E+00
3514.4	4	6	1.36E+00
3520.0	6	6	5.2E-01
3521.3	8	8	2.27E-01
3535.3	2	4	5.7E-01
3548.5	4	4	8.7E-01
3550.0	6	6	2.6E-02
3556.9	2	2	5.0E-02
3559.5	6	8	2.88E+00
3565.0	2	4	5.5E-01
3576.6	6	8	2.75E+00
3581.6	2	4	1.76E+00
3582.4	4	6	2.53E+00
3588.4	8	10	3.03E+00
3605.9	4	6	4.4E-02
3656.0	6	6	7.6E-02
3682.5	4	2	1.7E-02
3709.9	4	4	4.7E-02
3717.2	6	8	5.2E-02
3729.3	6	4	4.80E-01
3746.9	4	6	2.1E-02
3763.5	8	6	1.78E-01
3766.1	4	4	7.4E-02
3777.5	2	2	1.1E-02
3780.8	8	8	7.7E-01
3786.4	8	6	1.5E-02
3799.4	6	4	1.7E-01
3808.6	6	6	1.0E-02
3826.8	6	6	2.81E-01
3841.5	4	2	2.69E-01
3844.7	6	8	4.8E-02
3845.4	6	4	1.6E-02
3850.6	4	4	3.87E-01
3868.5	4	6	1.4E+00
3872.1	4	4	1.5E-01
3875.3	4	2	8.2E-02
3880.3	2	2	2.32E-01
3891.4	2	2	4.3E-02
3892.0	6	4	6.3E-02
3900.6	4	6	7.2E-02
3911.6	2	4	7.7E-02
3914.8	4	4	3.7E-02
3928.6	2	4	2.44E-01
3931.2	2	4	2.0E-02
3932.5	4	4	9.3E-01
3944.3	8	6	4.1E-02
3952.7	4	4	2.08E-01
3958.4	6	4	3.8E-02
3968.4	6	6	4.8E-02
3979.4	4	2	9.8E-01
3988.2	6	6	4.1E-02
3992.1	4	6	1.6E-02
4013.9	8	8	1.05E-01
4031.4	4	2	7.5E-02
4035.5	4	6	4.4E-02
4038.8	6	8	1.2E-02
4042.9	4	4	4.06E-01
4045.7	4	4	1.6E-02
4052.9	2	4	6.7E-01
4065.1	4	4	1.1E-02
4072.0	6	6	5.8E-01
4079.6	6	4	1.19E-01
4082.4	6	6	2.9E-02
4112.8	4	4	1.1E-02
4128.6	8	6	1.4E-02
4131.7	4	2	8.5E-01
4178.4	6	4	1.2E-02
4202.0	2	4	2.1E-02
4228.2	4	6	1.31E-01
4237.2	4	4	1.12E-01
4266.5	6	6	1.64E-01
4277.5	6	4	8.0E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
4282.9	4	2	1.32E-01
4300.6	6	6	5.7E-02
4331.2	4	4	5.74E-01
4332.0	4	2	1.92E-01
4348.1	6	8	1.17E+00
4352.2	2	2	2.12E-01
4362.1	4	6	5.5E-02
4370.8	4	4	6.6E-01
4371.3	6	4	2.21E-01
4376.0	4	2	2.05E-01
4379.7	2	2	1.00E+00
4383.8	4	4	1.1E-02
4400.1	4	4	1.60E-01
4401.0	8	6	3.04E-01
4412.9	6	8	6.1E-02
4420.9	2	4	3.1E-02
4426.0	4	6	8.17E-01
4430.2	2	4	5.69E-01
4431.0	6	6	1.09E-01
4460.6	4	6	1.5E-02
4474.8	4	2	2.90E-01
4481.8	6	6	4.55E-01
4491.0	6	4	4.6E-02
4530.5	6	4	2.1E-02
4545.1	4	4	4.71E-01
4579.4	2	2	8.0E-01
4589.9	4	6	6.64E-01
4598.8	4	4	6.7E-02
4609.6	6	8	7.89E-01
4637.2	6	6	7.1E-02
4657.9	4	2	8.92E-01
4726.9	4	4	5.88E-01
4732.1	6	4	6.7E-02
4735.9	6	4	5.80E-01
4764.9	2	4	6.4E-01
4806.0	6	6	7.80E-01
4847.8	4	2	8.49E-01
4879.9	4	6	8.23E-01
4889.0	2	2	1.9E-01
4904.8	6	8	3.7E-02
4933.2	4	4	1.44E-01
4965.1	2	4	3.94E-01
4972.2	2	2	9.7E-02
5009.3	4	6	1.51E-01
5017.2	4	6	2.07E-01
5017.6	4	4	1.1E-02
5062.0	2	4	2.23E-01
5141.8	6	8	8.1E-02
5145.3	4	6	1.06E-01
5176.2	6	6	1.7E-02
6103.5	2	2	1.7E-02
6114.9	10	8	2.00E-01
6138.7	6	4	1.2E-02
6172.3	8	6	2.00E-01
6243.1	8	6	3.0E-02
6483.1	4	2	1.06E-01
6638.2	6	4	1.37E-01
6639.7	4	2	1.69E-01
6643.7	10	8	1.47E-01
6666.4	2	2	8.8E-02
6684.3	8	6	1.07E-01
6756.6	4	4	2.0E-02
6863.5	6	6	2.5E-02
7233.5	2	4	3.7E-02
7380.4	4	4	5.6E-02
7589.3	6	4	1.07E-01
Ar III			
769.15	5	3	6.0E+00
871.10	5	3	1.59E+00
875.53	3	1	3.74E+00
878.73	5	5	2.79E+00
879.62	3	3	9.2E-01
883.18	1	3	1.22E+00
887.40	3	5	9.0E-01
3024.1	5	7	2.6E+00
3027.2	5	5	6.4E-01
3054.8	3	5	1.9E+00
3064.8	3	3	1.0E+00
3078.2	1	3	1.4E+00
3285.9	5	7	2.0E+00
3301.9	5	5	2.0E+00
3311.3	5	3	2.0E+00
3336.1	7	9	2.0E+00
3344.7	5	7	1.8E+00
3352.1	7	7	2.2E-01
3358.5	3	5	1.6E+00
3361.3	5	5	3.0E-01
3472.6	5	7	2.0E-01
3480.6	7	7	1.6E+00
3499.7	3	3	1.3E+00
3500.6	3	5	2.6E-01
3502.7	5	3	4.3E-01
3503.6	5	5	1.2E+00
3511.7	7	5	2.6E-01
Ar IV			
840.03	4	2	2.73E+00
843.77	4	4	2.70E+00
850.60	4	6	2.63E+00
Ar VI			
292.15	2	2	6.9E+01
294.05	4	2	1.36E+02
Ar VII			
*250.41	9	3	2.78E+02
*477.54	9	15	9.92E+01
585.75	1	3	7.83E+01
*637.30	9	9	6.7E+01
Ar VIII			
158.92	2	4	1.1E+02
159.18	2	2	1.11E+02
229.44	2	2	1.12E+02
230.88	4	2	2.21E+02
337.09	4	4	1.2E+01
337.26	6	4	1.0E+02
338.22	4	2	1.1E+02
519.43	2	4	6.3E+01
526.46	4	6	7.2E+01
526.87	4	4	1.2E+01
700.24	2	4	2.55E+01
713.81	2	2	2.4E+01
Ar IX			
48.739	1	3	1.69E+03
Ar XIII			
162.96	5	3	3.4E+02
*163.08	9	3	5.3E+02
184.90	5	5	1.66E+02
186.38	1	3	8.8E+01
*207.89	9	9	9.5E+01
*245.10	9	15	3.7E+01
Ar XIV			
180.29	2	4	4.5E+01
183.41	2	2	1.69E+02
187.95	4	4	1.97E+02
191.35	4	2	7.5E+01
194.39	2	2	4.6E+01
203.35	4	2	7.8E+01
Ar XV			
25.05	1	3	1.7E+04
221.10	1	3	9.55E+01
*265.3	9	9	8.1E+01
Ar XVI			
*23.52	2	6	1.43E+04
*24.96	6	10	4.4E+04
353.88	2	4	1.5E+01
389.11	2	2	1.1E+01
1268	2	4	1.9E+00
1401	2	2	1.4E+00
2975	2	4	9.0E-02
3514	4	6	6.5E-02
Arsenic			
As I			
1890.4	4	6	2.0E+00
1937.6	4	4	2.0E+00
1972.6	4	2	2.0E+00
2288.1	6	4	2.8E+00
2344.0	2	4	3.5E-01
2349.8	4	2	3.1E+00
2369.7	4	4	6.0E-01
2370.8	4	6	4.2E-01
2456.5	6	4	7.2E-02
2492.9	4	2	1.2E-01
2745.0	2	4	2.6E-01
2780.2	4	4	7.8E-01
2860.4	2	2	5.5E-01
2898.7	4	2	9.9E-02
Barium			
Ba I			
2380.66	1	3	2.62E-04
2380.75	1	3	2.44E-04
2380.86	1	3	2.55E-04
2380.97	1	3	2.57E-04
2381.08	1	3	2.50E-04
2381.21	1	3	2.91E-04
2381.34	1	3	3.15E-04
2381.48	1	3	3.41E-04

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
2381.63	1	3	3.22E-04
2381.79	1	3	3.44E-04
2381.97	1	3	3.39E-04
2382.15	1	3	3.63E-04
2382.36	1	3	3.64E-04
2382.57	1	3	3.14E-04
2382.80	1	3	3.69E-04
2383.06	1	3	3.57E-04
2383.34	1	3	3.37E-04
2383.63	1	3	3.70E-04
2383.96	1	3	3.20E-04
2384.32	1	3	2.97E-04
2384.71	1	3	3.00E-04
2385.15	1	3	2.50E-04
2385.62	1	3	2.30E-04
2386.15	1	3	2.03E-04
2386.74	1	3	1.87E-04
2387.40	1	3	1.37E-04
2388.13	1	3	9.66E-05
2388.96	1	3	8.37E-05
2399.39	1	3	1.10E-04
2402.07	1	3	4.60E-04
2405.30	1	3	4.90E-04
2409.23	1	3	8.60E-04
2414.08	1	3	1.50E-03
2420.11	1	3	2.30E-03
2427.41	1	3	5.60E-03
2438.81	1	3	1.40E-03
2452.33	1	3	8.10E-04
2472.74	1	3	4.60E-03
3071.58	1	3	4.20E-01
3501.11	1	3	3.50E-01
3889.33	1	3	1.10E-02
4132.43	1	3	1.50E-02
4175.69	3	5	1.97E-04
4175.91	3	5	1.98E-04
4176.12	3	5	2.08E-04
4176.36	3	5	2.19E-04
4176.60	3	5	2.26E-04
4176.86	3	5	2.48E-04
4177.15	3	5	2.77E-04
4177.44	3	5	3.03E-04
4177.74	3	5	3.14E-04
4178.07	3	5	3.07E-04
4178.43	3	5	3.64E-04
4178.80	3	5	4.01E-04
4179.20	3	5	4.31E-04
4179.64	3	5	4.46E-04
4180.09	3	5	4.53E-04
4180.57	3	5	4.55E-04
4181.09	3	5	4.99E-04
4181.66	3	5	5.42E-04
4182.27	3	5	6.11E-04
4182.94	3	5	6.65E-04
4183.64	3	5	6.70E-04
4184.40	3	5	7.93E-04
4185.25	3	5	8.43E-04
4186.16	3	5	9.24E-04
4187.15	3	5	9.90E-04
4188.25	3	5	1.03E-03
4189.44	3	5	1.13E-03
4190.76	3	5	1.28E-03
4192.20	3	5	1.36E-03
4193.81	3	5	1.58E-03
4195.59	3	5	1.78E-03
4323.00	3	5	8.80E-02
4402.54	3	5	2.70E-01
4488.98	5	7	2.80E-01
4493.64	5	5	1.95E-01
4573.85	3	1	1.21E+00
4579.64	5	5	7.00E-01
4599.72	3	1	4.07E-01
4619.92	1	3	2.70E-02
4700.42	3	3	6.10E-02
4726.43	5	3	3.30E-01
4801.30	9	3	1.39E-01
4902.85	5	3	5.40E-02
5169.53	5	3	9.00E-04
5519.04	3	5	5.70E-01
5535.48	1	3	1.19E+00
5777.62	5	7	8.00E-01
5784.04	3	5	2.10E-01
5800.23	5	5	2.39E-01
5826.27	5	3	4.50E-01
5971.70	5	5	1.62E-01
5997.09	3	3	2.80E-01
6019.47	3	1	8.10E-01
6063.11	5	3	5.60E-01
6083.39	3	1	1.10E-01
6129.23	3	1	6.00E-02
6309.36	3	3	2.00E-04
6341.68	5	7	1.16E-01
6450.85	3	5	1.10E-01
6498.76	7	7	5.40E-01
6527.31	5	5	3.30E-01
6527.40	15	15	6.15E-01
6595.33	3	3	3.80E-01
6675.27	5	3	1.89E-01
6693.84	7	5	1.46E-01
6986.80	5	3	5.20E-03
7059.94	7	9	5.00E-01
7120.33	3	5	1.10E-01
7195.23	1	3	5.60E-02
7213.60	5	5	6.50E-04
7280.30	5	7	3.20E-01
7392.41	3	3	1.81E-01
7417.54	7	5	7.70E-03
7488.08	7	7	7.30E-02
7528.18	5	5	2.70E-02
7610.48	5	5	1.10E-02
7644.90	9	3	5.03E-01
7672.09	3	5	1.52E-01
7780.48	5	5	7.60E-02
7877.80	3	5	1.60E-02
7905.75	5	3	2.65E-01
8147.70	5	5	6.30E-02
8560.00	5	5	2.00E-01
8654.08	5	7	3.10E-03
9370.12	5	5	7.60E-02
9645.60	7	5	1.10E-01
9704.31	3	1	1.60E-01
9821.48	3	1	5.50E-02
10370.30	3	5	1.30E-02
10540.10	5	3	1.80E-02
10649.10	5	5	2.70E-02
11075.70	3	3	3.10E-05
11303.00	5	3	1.10E-03
11373.70	3	1	1.30E-01
12342.30	3	3	9.00E-04
14723.10	3	5	8.60E-03
14999.90	5	3	2.50E-03
17186.90	3	1	2.70E-02
18202.80	5	3	1.20E-02
21567.70	5	3	2.60E-03
30685.30	5	3	6.50E-03
Ba II			
1622.43	2	4	2.46E-02
1630.36	2	2	2.42E-02
1761.74	4	4	1.00E-02
1771.10	4	2	1.00E-01
1786.95	6	4	9.00E-02
1892.49	2	4	1.30E-01
1954.28	4	6	1.40E-01
1955.05	4	4	2.40E-02
1985.75	2	4	2.00E-01
1999.55	2	4	7.12E-02
2009.28	2	2	6.51E-02
2024.06	2	2	6.86E-02
2052.75	4	6	2.20E-01
2054.09	4	4	3.70E-02
2079.98	4	2	1.17E-01
2153.93	2	4	3.43E-01
2200.89	2	2	1.13E-01
2214.76	4	4	1.60E-02
2232.79	4	6	3.69E-01
2235.38	4	4	6.13E-02
2245.69	4	2	1.60E-01
2254.78	6	4	1.40E-01
2285.99	4	2	2.03E-01
2528.41	2	4	6.91E-01
2634.78	4	6	7.33E-01
2641.37	4	4	1.21E-01
2647.26	2	2	2.26E-01
2771.35	4	2	3.95E-01
3390.18	4	6	4.54E-03
3412.44	6	8	4.77E-03
3413.95	6	6	3.18E-04
3552.45	4	6	3.87E-03
3576.28	6	8	4.07E-03
3578.57	6	6	2.71E-04
3891.78	2	4	2.17E+00
4130.65	4	6	2.18E+00
4166.00	4	4	3.54E-01
4216.07	2	4	5.09E-02
4267.92	6	8	3.10E-01
4309.26	8	10	3.10E-01
4325.75	4	6	5.65E-02
4329.56	4	4	9.39E-03
4524.93	2	2	6.63E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
4554.03	2	4	1.11E+00
4708.90	2	4	8.47E-02
4843.48	4	6	9.34E-02
4847.19	2	2	3.49E-02
4850.92	4	4	1.55E-02
4899.93	4	2	1.04E+00
4934.08	2	2	9.53E-01
4957.09	6	8	5.13E-01
4997.79	4	2	6.37E-02
5012.95	8	10	5.15E-01
5185.06	2	4	1.10E-02
5267.01	2	2	1.00E-02
5361.35	4	6	4.01E-02
5391.59	6	8	4.22E-02
5413.57	6	6	9.21E-05
5421.06	6	6	2.77E-03
5428.84	6	4	1.92E-03
5480.25	8	6	1.78E-03
5784.15	2	4	1.59E-01
5853.67	4	4	6.00E-02
5981.26	4	6	1.73E-01
5999.91	4	4	2.86E-02
6135.60	2	2	6.64E-02
6141.71	6	4	4.12E-01
6378.92	4	2	1.18E-01
6496.90	4	2	3.10E-01
6769.48	6	8	9.35E-01
6874.08	8	10	9.26E-01
6995.14	6	8	8.90E-03
7115.03	8	10	8.80E-03
8496.80	2	4	3.31E-02
8591.43	6	6	6.19E-04
8661.90	6	4	1.27E-02
8703.69	4	6	3.69E-02
8710.77	6	8	7.88E-01
8719.12	4	4	6.12E-03
8737.75	4	6	7.29E-01
8760.61	8	6	1.17E-02
8897.46	6	6	4.93E-02
9603.12	2	4	4.16E-01
10115.00	4	6	4.27E-01
10212.80	4	4	6.92E-02
10709.80	6	6	9.90E-05
10768.00	2	4	5.56E-02
10769.70	6	4	2.04E-03
10993.40	8	6	1.83E-03
11088.50	4	6	6.11E-02
11127.50	4	4	1.01E-02
11519.50	2	2	2.47E-02
11577.10	2	2	1.75E-01
11931.90	4	2	4.44E-02
12475.00	4	2	2.80E-01
13057.80	2	4	2.14E-01
14211.50	2	2	1.66E-01
17738.90	6	8	2.16E-01
18530.70	8	10	1.96E-01
18729.70	2	4	1.23E-01
19642.60	4	6	1.28E-01
19845.10	4	4	2.07E-02
22994.70	2	2	6.18E-02
24612.50	4	4	4.75E-03
24699.00	4	2	9.98E-02
25923.20	6	4	3.66E-02
27687.20	2	4	6.10E-02
29058.90	4	2	2.89E-02
30196.00	2	2	4.70E-02
42934.70	6	8	4.82E-03
43294.30	4	6	4.39E-03
47520.80	6	6	2.37E-04
Beryllium			
Be I			
1491.8	1	3	1.3E-02
1661.5	1	3	2.0E-01
2348.6	1	3	5.55E+00
*2494.7	9	15	1.6E+00
*2650.6	9	9	4.24E+00
4572.7	3	5	7.9E-01
Be II			
1197.1	2	2	4.7E-01
1197.2	4	2	9.4E-01
1512.3	2	4	9.2E+00
1512.4	4	6	1.1E+01
1776.1	2	2	1.4E+00
1776.3	4	2	2.9E+00
*2453.8	2	6	1.42E-01
3046.5	2	4	4.8E-01
3046.7	4	6	5.9E-01
3130.4	2	4	1.14E+00
3131.1	2	2	1.15E+00
3241.6	2	2	1.41E-01
3241.8	4	2	2.8E-01
3274.6	2	4	1.9E-01
3274.7	2	2	1.9E-01
4360.7	2	4	9.2E-01
4361.0	4	6	1.1E+00
*5255.9	2	6	2.56E-02
5270.3	2	2	3.30E-01
5270.8	4	2	6.6E-01
6279.4	2	4	1.2E-01
6279.7	4	6	1.43E-01
6756.7	2	2	5.1E-02
6757.1	4	2	1.02E-01
7401.2	2	4	3.0E-02
7401.4	2	2	3.0E-02
Bismuth			
Bi I			
1954.5	4	6	1.2E+00
2021.2	4	4	6.0E-02
2061.7	4	6	9.9E-01
2110.3	4	2	9.1E-01
2177.3	4	2	2.6E-02
2228.3	4	4	8.9E-01
2230.6	4	6	2.6E+00
2276.6	4	4	2.5E-01
2515.7	4	6	4.3E-02
2627.9	4	4	4.7E-01
2696.8	4	6	6.4E-02
2780.5	4	2	3.09E-01
2798.7	6	6	3.6E-02
2898.0	4	2	1.53E+00
2938.3	6	4	1.23E+00
2989.0	4	4	5.5E-01
2993.3	4	6	1.6E-01
3024.6	6	6	8.8E-01
3067.7	4	2	2.07E+00
3076.7	4	4	3.5E-02
3397.2	6	4	1.81E-01
3402.9	6	6	1.6E-02
3510.9	6	4	6.8E-02
3596.1	2	4	1.98E-01
3888.2	2	2	6.9E-02
4121.5	2	2	1.64E-01
4308.5	2	4	1.6E-02
4493.0	2	4	1.5E-02
4722.5	4	2	1.17E-01
6134.8	4	4	1.8E-02
Boron			
B I			
1378.6	2	4	3.50E+00
1378.9	2	2	1.40E+01
1378.9	4	4	1.75E+01
1379.2	4	2	7.0E+00
1465.5	2	4	3.34E+00
1465.7	4	4	6.7E+00
1465.8	6	4	1.00E+01
1825.9	2	4	1.76E+00
1826.4	4	6	2.11E+00
2088.9	2	4	2.8E-01
2089.6	4	6	3.3E-01
2496.8	2	2	8.64E-01
2497.7	4	2	1.73E+00
Bromine			
Br I			
1488.5	4	4	1.2E+00
1540.7	4	4	1.4E+00
1574.8	2	4	2.0E-01
1576.4	4	6	2.1E-02
1633.4	2	4	8.1E-02
4365.1	2	4	7.5E-03
4425.1	4	2	4.2E-03
4441.7	6	4	7.5E-03
4472.6	4	4	9.3E-03
4477.7	6	8	1.3E-02
4513.4	6	4	2.8E-03
4525.6	6	6	7.2E-03
4575.7	4	4	1.6E-02
4614.6	4	6	5.4E-03
4979.8	4	4	2.6E-03
5245.1	2	4	3.1E-03
5345.4	2	4	7.6E-03
7348.5	4	6	1.2E-01
7513.0	6	4	1.2E-01
7803.0	2	4	5.3E-02
7938.7	6	6	1.9E-01
8131.5	2	4	3.8E-02
8343.7	2	2	2.2E-01

λ	Weights		*A*
Å	g_i	g_k	10^8 s^{-1}
8446.6	4	4	1.2E-01
8638.7	6	4	9.7E-02
Br II			
4704.9	5	7	1.1E+00
4785.5	5	5	9.4E-01
4816.7	5	3	1.1E+00
Cadmium			
Cd I			
2288.0	1	3	5.3E+00
2836.9	1	3	2.8E-01
2880.8	3	5	4.2E-01
2881.2	3	3	2.4E-01
2980.6	5	7	5.9E-01
2981.4	5	5	1.5E-01
3261.1	1	3	4.06E-03
3403.7	1	3	7.7E-01
3466.2	3	5	1.2E+00
3467.7	3	3	6.7E-01
3610.5	5	7	1.3E+00
3612.9	5	5	3.5E-01
4140.5	3	5	4.7E-02
4662.4	3	5	5.5E-02
4678.1	1	3	1.3E-01
4799.9	3	3	4.1E-01
5085.8	5	3	5.6E-01
6438.5	3	5	5.9E-01
Cd II			
2144.4	2	4	2.8E+00
2265.0	2	2	3.0E+00
2572.9	2	2	1.7E+00
2748.5	4	2	2.8E+00
4415.6	4	6	1.4E-02
Calcium			
Ca I			
2275.5	1	3	3.01E-01
2995.0	1	3	3.67E-01
2997.3	3	5	2.41E-01
2999.6	3	3	2.79E-01
3000.9	3	1	1.58E+00
3006.9	5	5	7.5E-01
3009.2	5	3	4.30E-01
3344.5	1	3	1.51E-01
3350.2	3	5	1.78E-01
3361.9	5	7	2.23E-01
3624.1	1	3	2.12E-01
3630.8	3	5	2.97E-01
3631.0	3	3	1.53E-01
3644.4	5	7	3.55E-01
3644.8	5	5	9.4E-02
3870.5	3	5	7.2E-02
3957.1	3	3	9.8E-02
3973.7	5	3	1.75E-01
4092.6	3	5	1.1E-01
4094.9	5	7	1.2E-01
4098.5	7	9	1.3E-01
4108.5	5	7	9.0E-01
4226.7	1	3	2.18E+00
4283.0	3	5	4.34E-01
4289.4	1	3	6.0E-01
4299.0	3	3	4.66E-01
4302.5	5	5	1.36E+00
4307.7	3	1	1.99E+00
4318.7	5	3	7.4E-01
4355.1	5	7	1.9E-01
4425.4	1	3	4.98E-01
4435.0	3	5	6.7E-01
4435.7	3	3	3.42E-01
4454.8	5	7	8.7E-01
4455.9	5	5	2.0E-01
4526.9	5	3	4.1E-01
4578.6	3	5	1.76E-01
4581.4	5	7	2.09E-01
4585.9	7	9	2.29E-01
4685.3	3	5	8.0E-02
4878.1	5	7	1.88E-01
5041.6	5	3	3.3E-01
5188.9	3	5	4.0E-01
5261.7	3	3	1.5E-01
5262.2	3	1	6.0E-01
5264.2	5	5	9.1E-02
5265.6	5	3	4.4E-01
5270.3	7	5	5.0E-01
5582.0	5	7	6.0E-02
5588.8	7	7	4.9E-01
5590.1	3	5	8.3E-02
5594.5	5	5	3.8E-01
5598.5	3	3	4.3E-01
5601.3	7	5	8.6E-02
5602.9	5	3	1.4E-01
5857.5	3	5	6.6E-01
6102.7	1	3	9.6E-02
6122.2	3	3	2.87E-01
6161.3	5	5	3.3E-02
6162.2	5	3	3.54E-01
6163.8	3	3	5.6E-02
6166.4	3	1	2.2E-01
6169.1	5	3	1.7E-01
6169.6	7	5	1.9E-01
6439.1	7	9	5.3E-01
6449.8	3	5	9.0E-02
6462.6	5	7	4.7E-01
6471.7	7	7	5.9E-02
6493.8	3	5	4.4E-01
6499.7	5	5	8.1E-02
Ca II			
1341.9	2	4	1.5E-02
1342.5	2	2	1.5E-02
1649.9	2	4	3.2E-03
1652.0	2	2	3.1E-03
1673.9	2	4	2.24E-01
1680.1	4	6	2.65E-01
1680.1	4	4	4.41E-02
1807.3	2	4	3.54E-01
1814.5	4	6	4.2E-01
1814.7	4	4	7.0E-02
1843.1	2	2	1.6E-01
1850.7	4	2	3.08E-01
2103.2	2	4	8.2E-01
2112.8	4	6	9.7E-01
2113.2	4	4	1.6E-01
2197.8	2	2	3.1E-01
2208.6	4	2	6.2E-01
3158.9	2	4	3.1E+00
3179.3	4	6	3.6E+00
3181.3	4	4	5.8E-01
3706.0	2	2	8.8E-01
3736.9	4	2	1.7E+00
3933.7	2	4	1.47E+00
3968.5	2	2	1.4E+00
Ca III			
357.97	1	3	8.8E+02
439.69	1	3	1.9E-01
490.55	1	3	1.6E-02
Ca V			
558.60	5	3	2.2E+01
637.93	5	3	3.9E+00
643.12	3	1	9.1E+00
646.57	5	5	6.9E+00
647.88	3	3	2.3E+00
651.55	1	3	2.9E+00
656.76	3	5	2.1E+00
Ca VII			
550.20	5	5	1.8E+01
624.39	1	3	3.3E+00
630.54	3	5	4.5E+00
630.79	3	3	2.2E+00
639.15	5	7	5.7E+00
640.41	5	5	1.3E+00
Ca VIII			
182.71	2	2	1.6E+02
184.16	4	2	3.2E+02
Ca IX			
163.23	5	3	3.76E+02
371.89	1	3	8.8E+01
373.81	3	5	1.16E+02
378.08	5	7	1.5E+02
395.03	3	5	2.2E+02
466.24	1	3	1.12E+02
498.01	3	5	2.49E+01
506.18	5	5	7.2E+01
515.57	5	3	3.75E+01
Ca X			
110.96	2	4	2.9E+02
111.20	2	2	2.92E+02
151.84	2	2	2.3E+02
153.02	4	2	4.5E+02
206.57	4	4	2.9E+01
206.75	6	4	2.6E+02
207.39	4	2	2.8E+02
411.70	2	4	8.3E+01
419.75	4	6	9.5E+01
420.47	4	4	1.6E+01
557.76	2	4	3.50E+01
574.01	2	2	3.2E+01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
Ca XI			
30.448	1	3	6.2E+03
30.867	1	3	4.9E+04
35.212	1	3	2.0E+03
Ca XII			
140.05	4	2	3.7E+02
147.27	2	2	1.6E+02
Ca XV			
141.69	5	3	4.08E+02
*142.23	9	3	6.3E+02
161.00	5	5	1.9E+02
Ca XVII			
19.558	1	3	3.8E+04
21.198	3	5	4.9E+04
192.82	1	3	1.21E+02
218.82	3	5	2.76E+01
223.02	1	3	3.44E+01
228.72	3	3	2.37E+01
232.83	5	5	6.5E+01
244.06	5	3	3.28E+01
Ca XVIII			
*18.71	2	6	2.31E+04
*19.74	6	10	7.0E+04
302.19	2	4	2.0E+01
344.76	2	2	1.3E+01
Carbon			
C I			
945.191	1	3	3.79E+00
945.338	3	3	1.14E+01
945.579	5	3	1.89E+01
1193.24	5	7	1.22E+00
1260.74	1	3	5.32E-01
1260.93	3	1	1.70E+00
1261.00	3	3	4.42E-01
1261.12	3	5	3.71E-01
1261.43	5	3	7.06E-01
1261.55	5	5	1.27E+00
1274.11	5	7	1.03E-02
1277.25	1	3	1.27E+00
1277.28	3	5	1.73E+00
1277.51	3	3	9.12E-01
1277.55	5	7	2.31E+00
1277.72	5	5	6.35E-01
1277.95	5	3	5.56E-02
1279.23	5	7	1.10E-01
1279.89	3	5	3.08E-01
1280.14	1	3	3.11E-01
1280.33	5	5	5.77E-01
1280.40	3	3	1.73E-01
1280.60	3	1	8.22E-01
1280.85	5	3	3.33E-01
1328.83	1	3	7.95E-01
1329.09	3	1	2.41E+00
1329.58	5	5	1.79E+00
1329.60	5	3	1.00E+00
1355.84	5	7	1.04E+00
1364.16	5	5	1.57E-01
1431.60	5	7	2.11E+00
1432.10	5	5	2.01E+00
1432.53	5	3	2.11E+00
1459.03	5	3	4.76E-01
1463.34	5	7	1.88E+00
1467.40	5	3	5.49E-01
1468.41	5	3	3.90E-02
1470.09	5	7	1.37E-02
1472.23	5	3	8.01E-03
1481.76	5	5	3.92E-01
1560.31	1	3	6.57E-01
1561.34	5	5	2.94E-01
1561.44	5	7	1.18E+00
1656.27	3	5	8.58E-01
1656.93	1	3	1.13E+00
1657.01	5	5	2.52E+00
1657.38	3	3	8.64E-01
1657.91	3	1	3.43E+00
1658.12	5	3	1.44E+00
1751.83	1	3	9.07E-01
1763.91	1	3	3.59E-02
1765.37	1	3	1.04E-02
1930.90	5	3	3.51E+00
2478.56	1	3	3.40E-01
2902.23	1	3	4.32E-03
2903.27	3	3	1.29E-02
2905.00	5	3	2.15E-02
4371.37	3	3	1.27E-02
4762.31	1	3	3.37E-03
4762.53	3	5	2.72E-03
4766.67	3	3	2.36E-03
4770.03	3	1	1.07E-02
4771.74	5	5	7.97E-03
4775.90	5	3	4.84E-03
4812.92	1	3	4.03E-04
4817.37	3	3	8.76E-04
4826.80	5	3	6.28E-04
4932.05	3	1	6.02E-02
5023.84	7	9	1.81E-03
5039.06	7	9	4.73E-03
5041.48	3	5	5.25E-03
5041.79	5	7	3.28E-03
5052.17	3	5	2.60E-02
5380.34	3	3	1.86E-02
5545.05	3	3	3.04E-03
5668.94	3	3	2.35E-02
5793.12	7	5	3.44E-03
5794.47	5	5	6.44E-04
5800.23	3	3	1.04E-03
5800.60	5	3	3.04E-03
5805.20	3	1	4.12E-03
6001.12	5	5	3.22E-03
6006.02	7	5	1.79E-02
6007.18	3	3	5.34E-03
6010.68	3	1	2.13E-02
6013.17	7	5	1.79E-02
6013.21	7	9	4.35E-03
6014.83	5	3	1.60E-02
6016.45	5	7	3.86E-03
6587.61	3	3	5.09E-02
6655.52	3	3	5.03E-03
6828.12	3	5	9.89E-03
7111.47	3	5	2.17E-02
7113.18	7	9	2.47E-02
7115.17	5	7	2.19E-02
7115.18	3	1	4.43E-02
7116.99	7	5	3.26E-02
7119.66	5	3	3.12E-02
7860.88	5	5	1.53E-02
8058.62	5	5	1.09E-02
8335.15	3	1	3.51E-01
9061.44	3	5	7.31E-02
9062.49	1	3	9.48E-02
9078.29	3	3	7.07E-02
9088.51	3	1	3.00E-01
9094.83	5	5	2.28E-01
9111.81	5	3	1.35E-01
9405.73	3	5	2.91E-01
9603.03	1	3	3.06E-02
9620.78	3	3	8.62E-02
9658.43	5	3	1.25E-01
C II			
687.345	4	6	2.84E+01
858.092	2	2	1.18E+00
858.559	4	2	2.35E+00
903.623	2	4	6.85E+00
903.962	2	2	2.74E+01
904.142	4	4	3.42E+01
904.480	4	2	1.37E+01
1009.86	2	4	5.71E+00
1010.08	4	4	1.14E+01
1010.37	6	4	1.71E+01
1036.34	2	2	7.61E+00
1037.02	4	2	1.52E+01
1323.91	4	4	4.33E+00
1323.95	6	6	4.49E+00
1334.53	2	4	2.37E+00
1335.71	4	6	2.84E+00
2091.14	2	4	1.00E-01
2091.19	4	6	1.69E-01
2091.65	6	8	2.41E-01
2093.16	6	6	7.20E-02
2173.85	2	4	2.31E-01
2174.17	2	2	2.31E-01
2509.13	2	4	4.53E-01
2511.74	4	4	9.04E-02
2512.06	4	6	5.42E-01
2727.31	2	4	6.63E-02
2728.72	4	4	3.31E-01
2729.21	2	2	2.65E-01
2730.63	4	2	1.32E-01
5132.95	2	4	3.89E-01
5133.28	4	6	2.80E-01
5137.26	2	2	1.55E-01
5139.17	4	4	1.24E-01
5143.49	4	2	7.73E-01
5145.16	6	6	6.49E-01
5151.08	6	4	4.16E-01
5640.55	2	4	9.89E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
5648.07	4	4	1.97E-01
5662.46	6	4	2.93E-01
5818.31	2	2	3.38E-02
5822.98	2	4	3.38E-03
5823.18	4	2	3.38E-02
5827.85	4	4	2.16E-02
5836.37	6	4	4.22E-02
5843.62	6	6	1.20E-02
5856.06	8	6	5.31E-02
6095.29	2	4	4.20E-01
6098.51	4	6	5.03E-01
6102.56	4	4	8.37E-02
6578.05	2	4	3.63E-01
6582.88	2	2	3.62E-01
6724.56	2	4	3.17E-02
6727.07	2	2	6.34E-02
6727.26	4	6	2.96E-02
6731.07	4	4	5.06E-02
6733.58	4	2	6.32E-02
6734.00	6	8	1.80E-02
6738.61	6	6	7.23E-02
6742.43	6	4	4.41E-02
6750.54	8	8	1.08E-01
6755.16	8	6	2.38E-02
6779.94	4	6	2.56E-01
6780.59	2	4	1.52E-01
6783.91	6	8	3.65E-01
6787.21	2	2	3.04E-01
6791.47	4	4	1.94E-01
6798.10	4	2	6.04E-02
6800.69	6	6	1.09E-01
6812.28	6	4	1.80E-02
7046.25	4	2	3.20E-01
7053.09	4	4	3.19E-01
7063.68	4	6	3.17E-01
7112.48	2	4	2.94E-01
7113.04	4	6	3.15E-01
7115.63	6	8	3.60E-01
7119.76	4	4	1.17E-01
7119.91	8	10	4.19E-01
7125.72	6	6	1.02E-01
7132.47	6	4	8.33E-03
7134.10	8	8	5.93E-02
7231.33	2	4	3.52E-01
7236.42	4	6	4.22E-01
7237.17	4	4	7.03E-02
8028.85	2	2	1.71E-02
8037.73	2	4	4.26E-02
8039.40	4	2	8.51E-02
8048.31	4	4	1.36E-02
8062.10	4	6	3.04E-02
8062.80	6	4	4.56E-02
8076.64	6	6	7.05E-02
9238.30	4	6	3.34E-02
9251.01	2	4	2.77E-02
9863.06	2	4	5.56E-02
9870.78	4	6	9.31E-02
9882.68	6	8	1.33E-01
C III			
310.170	1	3	6.56E+00
386.203	1	3	3.46E+01
459.466	1	3	5.91E+01
459.514	3	5	7.97E+01
459.627	5	7	1.06E+02
574.281	3	5	6.24E+01
977.020	1	3	1.767E+01
1174.93	3	5	3.293E+00
1175.26	1	3	4.385E+00
1175.59	3	3	3.287E+00
1175.71	5	5	9.856E+00
1175.99	3	1	1.313E+01
1176.37	5	3	5.468E+00
1247.38	3	1	2.082E+01
2296.87	3	5	1.376E+00
2849.05	3	1	1.95E-01
3703.70	3	3	5.90E-01
4325.56	3	5	1.24E-01
4647.42	3	5	7.26E-01
4650.25	3	3	7.25E-01
4651.02	3	5	2.28E-01
4651.47	3	1	7.24E-01
4652.05	1	3	3.04E-01
4659.06	3	3	2.27E-01
4663.64	3	1	9.05E-01
4665.86	5	5	6.78E-01
4673.95	5	3	3.75E-01
5244.66	1	3	5.30E-02
5253.58	3	3	1.58E-01
5272.52	5	3	2.61E-01
5695.92	3	5	4.27E-01
5858.34	3	1	1.34E-01
5863.25	3	3	3.35E-02
5871.68	5	3	1.00E-01
5880.56	5	5	1.99E-02
5894.07	7	5	1.11E-01
6727.48	1	3	1.12E-01
6731.04	3	5	1.50E-01
6742.15	3	3	8.32E-02
6744.39	5	7	1.99E-01
6762.17	5	5	4.95E-02
6773.39	5	3	5.47E-03
6851.18	3	5	7.60E-03
6853.68	5	7	5.64E-03
6857.24	3	3	3.79E-02
6862.69	5	5	3.51E-02
6868.78	5	3	1.26E-02
6872.04	7	7	4.46E-02
6881.10	7	5	7.80E-03
7353.88	5	3	3.09E-02
7707.43	3	5	1.30E-01
7771.76	3	1	1.77E-01
7780.41	3	3	1.76E-01
7796.00	3	5	1.75E-01
8500.32	1	3	1.01E-01
9593.32	3	3	5.32E-03
9651.47	5	5	1.57E-02
9696.48	5	7	7.53E-03
9696.54	3	5	7.12E-03
9699.57	7	9	8.47E-03
9701.10	1	3	4.40E-02
9705.41	3	5	5.93E-02
9706.44	3	3	3.29E-02
9715.09	5	7	7.88E-02
9717.75	5	5	1.97E-02
9718.79	5	3	2.19E-03
C IV			
*312.43	2	6	4.63E+01
*384.13	6	10	1.76E+02
1548.19	2	4	2.65E+00
1550.77	2	2	2.64E+00
5801.31	2	4	3.17E-01
5811.97	2	2	3.16E-01
C V			
34.9728	1	3	2.554E+03
40.2678	1	3	8.873E+03
*227.19	3	9	1.363E+02
247.315	1	3	1.278E+02
*248.71	9	15	4.247E+02
*260.19	9	3	6.680E+01
267.267	3	5	3.947E+02
*2273.9	3	9	5.646E-01
3526.66	1	3	1.663E-01
8420.72	3	5	6.898E-02
*8433.2	3	9	6.868E-02
8448.12	3	1	6.832E-02
8449.19	3	3	6.829E-02
Cesium			
Cs I			
3203.5	2	4	7.6E-06
3205.3	2	4	7.9E-06
3207.5	2	4	8.5E-06
3210.0	2	4	9.4E-06
3212.8	2	4	1.19E-05
3216.2	2	4	1.49E-05
3220.1	2	4	1.7E-05
3220.2	2	2	1.07E-07
3224.8	2	4	2.0E-05
3225.0	2	2	1.43E-07
3230.5	2	4	2.5E-05
3230.7	2	2	1.97E-07
3237.4	2	4	2.8E-05
3237.6	2	2	2.63E-07
3245.9	2	4	3.45E-05
3246.2	2	2	3.7E-07
3256.7	2	4	4.25E-05
3257.1	2	2	7.0E-07
3270.5	2	4	5.6E-05
3271.0	2	2	9.8E-07
3288.6	2	4	1.0E-04
3289.3	2	2	2.7E-06
3313.1	2	4	1.6E-04
3314.0	2	2	5.2E-06
3347.5	2	4	2.2E-04
3348.8	2	2	1.1E-05
3397.9	2	4	4.0E-04
3400.0	2	2	2.4E-05
3476.8	2	4	6.6E-04
3480.0	2	2	6.6E-05

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3611.4	2	4	1.5E-03
3617.3	2	2	2.5E-04
3876.1	2	4	3.8E-03
3888.6	2	2	9.7E-04
4555.3	2	4	1.88E-02
4593.2	2	2	8.0E-03
8521.1	2	4	3.276E-01
8943.5	2	2	2.87E-01
Chlorine			
Cl I			
1188.8	4	6	2.33E+00
1188.8	4	4	2.71E-01
1201.4	2	4	2.39E+00
1335.7	4	2	1.74E+00
1347.2	4	4	4.19E+00
1351.7	2	2	3.23E+00
1363.4	2	4	7.5E-01
4323.3	4	4	1.1E-02
4363.3	4	6	6.8E-03
4379.9	4	4	1.4E-02
4389.8	6	8	1.4E-02
4526.2	4	4	5.1E-02
4601.0	2	2	4.2E-02
4661.2	2	4	1.2E-02
7256.6	6	4	1.5E-01
7414.1	6	4	4.7E-02
7547.1	4	4	1.2E-01
7717.6	4	4	3.0E-02
7745.0	2	4	6.3E-02
7769.2	6	6	6.0E-02
7821.4	6	8	9.8E-02
7830.8	4	4	9.7E-02
7878.2	6	6	1.8E-02
7899.3	4	6	5.1E-02
7924.6	2	4	2.1E-02
7935.0	6	8	3.9E-02
7997.9	4	4	2.1E-02
Cl II			
3329.1	5	7	1.5E+00
3522.1	7	7	1.4E+00
3798.8	5	7	1.6E+00
3805.2	7	9	1.8E+00
3809.5	3	5	1.5E+00
3851.0	5	7	1.8E+00
3851.4	5	5	1.6E+00
3854.7	3	5	2.2E+00
3861.9	5	7	2.4E+00
3868.6	7	9	2.7E+00
3913.9	9	9	8.2E-01
3990.2	5	7	8.4E-01
4132.5	5	5	1.6E+00
4276.5	9	7	7.6E-01
4768.7	3	5	7.7E-01
4781.3	5	7	1.0E+00
4794.6	5	7	1.04E+00
4810.1	5	5	9.9E-01
4819.5	5	3	1.00E+00
4904.8	5	7	8.1E-01
4917.7	3	5	7.5E-01
5078.3	7	7	7.7E-01
5219.1	3	9	8.6E-01
5392.1	5	7	1.0E+00
Cl III			
2298.5	4	4	4.2E+00
2340.6	6	6	4.2E+00
2370.4	8	6	2.8E+00
2531.8	2	4	4.4E+00
2532.5	4	6	5.3E+00
2577.1	4	6	4.3E+00
2580.7	6	8	4.7E+00
2601.2	2	4	4.6E+00
2603.6	4	6	5.0E+00
2609.5	6	8	5.7E+00
2617.0	8	10	6.6E+00
2661.6	4	6	3.4E+00
2665.5	6	8	4.8E+00
2691.5	4	4	3.5E+00
2710.4	4	6	3.5E+00
3340.4	6	6	1.5E+00
3392.9	4	4	1.9E+00
3393.5	6	6	1.9E+00
3530.0	6	8	1.8E+00
3560.7	4	6	1.7E+00
3602.1	6	8	1.7E+00
3612.9	4	6	1.2E+00
3720.5	4	6	1.7E+00
Chromium			
Cr I			
1999.95	9	9	1.4E+00
2383.30	9	11	4.1E-01
2389.21	3	5	2.3E-01
2408.60	9	7	6.7E-01
2408.72	7	5	2.9E-01
2492.57	3	5	4.5E-01
2495.08	3	3	2.7E-01
2496.30	5	7	5.6E-01
2502.55	7	9	2.2E-01
2504.31	7	9	4.5E-01
2508.11	5	5	2.1E-01
2508.97	5	3	3.8E-01
2527.11	9	9	5.3E-01
2549.55	3	3	4.8E-01
2560.70	5	5	4.3E-01
2571.74	7	5	6.4E-01
2577.66	7	7	2.6E-01
2591.84	9	7	6.5E-01
2620.48	5	3	1.9E-01
2673.64	3	3	1.8E-01
2701.99	9	11	2.1E-01
2726.50	5	7	7.5E-01
2731.90	5	5	7.8E-01
2736.46	5	3	7.5E-01
2752.85	3	3	8.7E-01
2757.09	5	5	6.8E-01
2761.74	5	3	6.8E-01
2764.36	7	7	3.7E-01
2769.90	7	5	1.1E+00
2780.70	9	7	1.4E+00
2879.27	5	7	2.1E-01
2887.00	3	5	2.7E-01
2889.22	9	9	6.6E-01
2893.25	7	7	5.2E-01
2894.17	1	3	3.3E-01
2896.76	5	5	3.0E-01
2905.48	3	1	1.3E+00
2909.05	5	3	6.8E-01
2910.89	7	5	3.4E-01
2911.15	9	7	2.6E-01
2967.64	7	9	3.9E-01
2971.10	5	7	7.1E-01
2975.48	3	5	8.9E-01
2980.78	1	3	5.10E-01
2988.64	5	7	5.2E-01
2991.88	3	1	3.0E+00
2994.06	5	5	2.5E-01
2995.09	5	5	4.3E-01
2996.57	5	3	2.0E+00
2998.78	5	3	4.07E-01
3000.88	7	5	1.6E+00
3005.06	9	7	9.2E-01
3013.72	3	5	8.3E-01
3015.20	1	3	1.63E+00
3020.67	3	3	1.5E+00
3021.58	9	11	2.91E+00
3024.36	5	5	1.27E+00
3029.17	5	3	3.8E-01
3030.25	7	7	1.1E+00
3031.35	5	3	3.1E-01
3034.19	7	7	3.5E-01
3037.05	9	9	5.4E-01
3040.84	7	5	7.4E-01
3053.87	9	7	7.97E-01
3148.44	9	11	5.6E-01
3155.16	11	13	5.7E-01
3163.76	13	15	6.0E-01
3237.73	9	9	1.3E+00
3238.09	11	11	2.0E-01
3578.68	7	9	1.48E+00
3593.48	7	7	1.50E+00
3605.32	7	5	1.62E+00
3639.80	13	11	1.8E+00
3743.89	13	13	7.61E-01
3757.66	7	7	4.13E-01
3768.24	5	5	5.10E-01
3804.80	9	9	6.9E-01
3963.69	13	15	1.3E+00
3969.75	11	13	1.2E+00
3983.90	7	9	1.05E+00
3991.12	5	7	1.07E+00
4001.44	9	11	6.8E-01
4039.10	15	15	6.7E-01
4048.78	13	13	6.4E-01
4058.78	11	11	6.7E-01
4065.71	9	11	3.5E-01
4165.52	11	13	7.5E-01
4204.48	13	11	3.1E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
4254.33	7	9	3.15E-01
4263.15	15	17	6.4E-01
4274.81	7	7	3.07E-01
4275.98	11	11	2.2E-01
4280.42	13	15	4.7E-01
4289.73	7	5	3.16E-01
4291.97	7	5	2.4E-01
4297.75	11	13	4.9E-01
4298.05	9	9	2.6E-01
4300.52	9	7	1.9E-01
4301.19	11	9	2.6E-01
4302.78	11	11	2.5E-01
4319.66	5	3	1.8E-01
4337.25	5	7	2.0E-01
4373.65	9	9	2.8E-01
4376.80	13	13	3.2E-01
4413.86	7	5	2.7E-01
4422.70	5	5	2.7E-01
4424.29	9	7	2.1E-01
4429.93	3	3	2.4E-01
4432.16	1	3	1.8E-01
4432.77	15	15	4.9E-01
4443.72	3	1	4.5E-01
4482.88	3	3	3.0E-01
4490.55	9	7	3.9E-01
4492.31	5	3	4.47E-01
4495.28	9	7	2.0E-01
4500.29	7	7	2.1E-01
4506.84	13	11	2.7E-01
4540.72	11	11	3.14E-01
4564.17	11	13	5.1E-01
4595.60	13	13	4.7E-01
4622.47	7	7	4.1E-01
4663.33	3	3	2.0E-01
4665.90	3	3	3.0E-01
4689.38	7	5	2.3E-01
4698.46	9	7	2.2E-01
4708.02	11	9	4.31E-01
4718.43	13	11	3.4E-01
4730.69	7	5	3.83E-01
4737.33	9	7	3.38E-01
4741.09	3	5	2.2E-01
4752.07	13	13	6.2E-01
4756.09	11	9	4.0E-01
4792.49	7	5	2.6E-01
4801.02	9	7	3.06E-01
4816.13	9	9	1.8E-01
4870.79	7	9	3.5E-01
4887.01	9	11	3.2E-01
4922.28	11	13	4.0E-01
4966.80	3	1	3.0E-01
5204.51	5	3	5.09E-01
5206.02	5	5	5.14E-01
5208.42	5	7	5.06E-01
5243.38	5	3	2.19E-01
5297.37	7	9	3.88E-01
5297.99	7	7	3.0E-01
5328.36	9	11	6.2E-01
5329.17	9	9	2.25E-01
5783.11	3	3	2.1E-01
5783.89	5	5	2.02E-01
5787.97	5	7	2.35E-01
Cr II			
2653.57	4	6	3.5E-01
2658.59	2	4	5.8E-01
2666.02	6	8	5.9E-01
2668.71	4	2	1.4E+00
2671.80	6	4	1.0E+00
2672.83	8	6	5.5E-01
2744.97	4	6	8.5E-01
2787.61	6	6	1.5E+00
2822.38	14	16	2.3E+00
2835.63	10	12	2.0E+00
2840.01	10	12	2.7E+00
2843.24	8	10	6.4E-01
2849.83	6	8	9.2E-01
2851.35	8	10	2.2E+00
2856.77	4	6	4.3E-01
2857.40	6	8	2.8E-01
2860.92	2	4	6.9E-01
2862.57	8	8	6.3E-01
2866.72	4	4	1.2E+00
2867.09	4	4	1.1E+00
2867.65	2	2	1.1E+00
2870.43	6	6	1.3E+00
2873.81	4	2	8.8E-01
2880.86	6	4	7.9E-01
2898.53	10	12	1.2E+00
2921.81	8	10	9.0E-01
2930.83	2	4	1.1E+00
2935.12	6	8	1.8E+00
2953.34	2	2	1.8E+00
2966.03	10	8	5.4E-01
2971.90	14	14	2.0E+00
2979.73	12	12	1.8E+00
2985.32	10	10	2.2E+00
2989.18	8	8	2.2E+00
3118.64	2	4	1.7E+00
3120.36	4	6	1.5E+00
3122.59	12	12	4.4E-01
3128.69	4	4	8.1E-01
3136.68	6	6	6.4E-01
4588.22	8	6	1.2E-01
Cr V			
434.306	9	9	1.5E+01
436.351	9	7	2.4E+01
436.601	7	5	2.1E+01
437.420	7	7	1.4E+01
437.655	5	5	1.3E+01
441.056	5	3	2.3E+01
456.357	1	3	9.5E+00
456.637	3	1	3.3E+01
456.743	3	3	9.1E+00
457.028	5	5	2.7E+01
457.504	5	3	1.2E+01
464.015	9	7	3.6E+01
469.634	5	5	2.3E+01
1106.25	7	9	1.2E+01
1121.07	7	9	2.1E+01
1127.63	9	11	3.5E+01
1465.86	5	3	1.1E+01
1481.65	3	1	1.0E+01
1519.03	5	7	9.5E+00
1579.70	7	9	8.6E+00
Cr VI			
161.687	6	6	1.7E+02
168.088	4	6	2.0E+02
201.007	4	4	2.5E+03
201.224	4	6	1.8E+02
201.388	6	4	2.7E+02
201.606	6	6	2.6E+03
202.442	6	4	1.0E+03
202.739	4	2	1.2E+03
226.241	6	8	7.2E+02
227.202	4	6	6.6E+02
Cr X			
216.72	6	8	9.0E+02
223.86	4	2	7.7E+02
224.74	4	4	7.6E+02
226.24	4	6	7.3E+02
227.42	4	4	5.2E+02
227.50	4	6	1.8E+01
228.63	6	4	8.1E+01
228.71	6	6	4.5E+02
231.21	2	4	1.2E+02
232.96	4	4	4.4E+02
242.20	2	4	5.0E+01
244.19	4	6	5.8E+01
395.984	4	4	2.4E+01
398.150	6	6	2.1E+01
Cr XI			
214.31	5	7	1.4E+01
226.45	5	7	6.0E+02
232	3	1	4.1E+02
235.53	5	7	5.5E+02
240.76	1	3	4.8E+02
250.28	5	7	1.0E+01
366.491	3	3	1.2E+01
366.942	3	1	3.0E+01
374.927	5	5	2.3E+01
422.083	3	5	1.0E+01
Cr XII			
216	4	6	2.4E+02
218	6	8	2.4E+02
239	2	2	1.6E+02
244.70	2	4	3.0E+02
247	4	2	2.4E+02
247	2	2	3.3E+02
248	6	8	1.4E+02
250	6	8	3.5E+02
250	6	6	2.2E+02
251.52	4	6	3.4E+02
252	4	6	2.0E+02
256	2	2	1.5E+02
259	2	4	3.2E+02
269	2	2	2.1E+02
300.32	2	2	1.4E+02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
305.81	4	4	2.76E+02
309	4	2	2.7E+02
309	6	6	1.6E+02
311.55	4	2	1.6E+02
324	4	6	2.2E+02
327	6	8	2.2E+02
332.06	6	4	1.4E+02
Cr XIII			
49.59	1	3	9.9E+02
67.01	1	3	1.67E+03
228	5	7	1.8E+02
267.73	5	7	1.9E+02
270	3	1	1.7E+02
276.4	5	7	2.2E+02
277	1	3	2.1E+02
279.32	3	5	3.5E+02
286	3	1	4.6E+02
328.29	1	3	1.86E+02
345	7	9	1.74E+02
Cr XIV			
*38.036	2	6	2.47E+02
39.796	2	4	3.05E+02
40.018	4	6	3.6E+02
40.782	2	4	3.9E+02
40.800	2	2	3.9E+02
41.556	2	4	4.5E+02
41.788	4	6	5.3E+02
44.597	2	4	7.1E+02
44.869	4	6	8.3E+02
46.125	4	2	3.1E+02
46.468	2	4	6.6E+02
46.527	2	2	6.7E+02
48.300	4	6	5.9E+02
48.338	6	8	6.3E+02
50.821	2	4	1.2E+03
51.172	4	6	1.4E+03
51.180	4	4	2.3E+02
52.321	4	6	1.0E+03
52.363	6	8	1.1E+03
53.760	2	2	3.0E+02
54.164	4	2	5.9E+02
60.699	4	6	2.05E+03
60.756	6	8	2.19E+03
63.324	2	4	1.07E+03
63.539	2	2	1.13E+03
68.594	2	4	1.98E+03
69.213	4	6	2.31E+03
69.247	4	4	3.8E+02
86.060	4	6	5.3E+03
86.169	6	8	5.9E+03
86.185	6	6	3.9E+02
101.05	6	4	4.4E+02
101.42	4	2	4.83E+02
104.4	4	6	3.0E+02
104.5	6	8	3.1E+02
109.8	2	4	2.3E+02
110.4	4	6	2.8E+02
118.3	4	2	2.1E+02
125.2	4	6	5.0E+02
125.3	6	8	5.4E+02
148.5	2	4	2.18E+02
149.1	2	2	2.1E+02
157.1	2	4	3.3E+02
158.4	4	6	3.7E+02
187.02	4	6	9.3E+02
187.30	6	8	9.6E+02
189.1	2	2	2.13E+02
191.0	4	2	4.11E+02
222.9	4	2	2.2E+02
346.3	4	6	2.4E+02
346.5	6	8	2.5E+02
Cr XV			
18.497	1	3	1.62E+05
18.782	1	3	2.8E+04
19.015	1	3	6.3E+02
20.863	1	3	6.0E+03
21.153	1	3	5.6E+03
102	3	3	1.6E+02
102.18	5	3	7.0E+02
103	3	1	3.8E+02
105	7	5	5.3E+02
111.27	3	3	1.7E+02
Cr XVI			
17.073	4	6	1.2E+04
17.242	2	4	8.6E+04
17.299	4	4	2.5E+04
17.372	4	4	1.4E+05
17.438	4	2	1.1E+05
17.514	2	4	1.1E+05
17.587	2	4	2.0E+04
17.656	2	2	2.0E+04
19.442	4	2	9.9E+03
19.714	2	2	1.1E+04
Cr XVII			
16.31	5	3	9.6E+03
16.32	5	7	3.2E+04
16.37	3	1	9.7E+04
16.44	5	7	1.3E+05
16.59	3	1	5.7E+04
16.65	5	5	1.1E+04
16.66	1	3	1.8E+05
16.68	5	7	6.8E+04
16.80	5	7	4.4E+04
16.97	1	3	2.63E+04
16.97	3	3	1.5E+04
17.968	5	3	8.6E+03
18.336	5	3	1.7E+04
18.336	5	5	1.6E+04
18.389	1	3	9.2E+03
Cr XVIII			
95.77	4	2	3.08E+02
102.32	4	4	1.54E+02
104.98	6	4	8.7E+02
106.84	4	2	3.4E+02
110.41	4	2	7.9E+02
112.27	4	2	4.24E+02
119.62	2	2	3.2E+02
123.87	6	4	3.9E+02
125.51	4	4	3.4E+02
128.10	6	6	2.8E+02
136.52	4	2	1.66E+02
139.87	4	4	1.49E+02
140.82	4	2	2.66E+02
155.46	2	2	2.84E+02
157.40	4	4	2.83E+02
Cr XIX			
14.73	3	3	7.1E+04
14.80	1	3	1.3E+05
14.81	5	3	3.4E+04
14.84	5	7	1.3E+05
109.64	3	3	2.46E+02
110.37	5	3	6.0E+02
113.97	5	3	5.5E+02
118.31	3	1	3.29E+02
118.67	5	3	2.1E+02
118.83	3	3	1.35E+02
126.30	1	3	1.56E+02
126.33	5	5	4.35E+02
130.99	7	5	2.9E+02
134.89	3	1	1.98E+02
138.15	3	1	1.75E+02
138.45	5	5	1.71E+02
140.92	5	3	1.38E+02
143.57	3	1	7.2E+02
163.94	5	5	3.1E+02
179.18	3	1	1.45E+02
Cr XX			
14.13	2	4	1.1E+05
14.26	4	6	1.3E+05
128.42	4	4	3.8E+02
131.31	6	4	1.27E+02
133.82	2	4	8.3E+01
135.26	4	2	2.41E+02
140.75	4	4	1.35E+02
148.99	6	4	1.75E+02
156.00	2	4	8.4E+01
167.97	6	6	1.12E+02
180.85	4	4	1.6E+02
Cr XXI			
12.97	3	1	4.8E+04
12.98	5	5	3.9E+04
13.02	3	5	3.8E+04
13.02	5	7	3.9E+04
13.08	1	3	5.2E+04
13.22	3	1	4.6E+04
13.34	3	5	5.2E+04
13.49	1	3	9.0E+04
13.53	3	3	6.6E+04
13.55	3	5	1.2E+05
13.65	5	7	1.5E+05
13.66	3	1	1.2E+05
13.67	5	5	3.9E+04
13.68	3	3	8.2E+04
13.75	5	3	4.5E+04
13.75	5	5	9.5E+04

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
13.76	1	3	1.51E+05
13.78	5	7	1.7E+05
13.84	5	7	2.59E+05
13.87	3	5	8.5E+04
13.92	3	5	8.5E+04
13.93	5	7	4.2E+04
13.95	5	5	3.8E+04
14.04	3	5	1.2E+05
14.24	1	3	1.41E+05
Cr XXII			
2.190	4	2	1.7E+06
2.191	2	2	2.5E+06
2.198	4	4	4.5E+06
2.199	2	4	2.3E+06
2.202	4	6	1.6E+06
2.203	4	2	1.3E+06
13.149	2	4	1.29E+05
13.292	4	6	1.54E+05
Cr XXIII			
1.7632	1	3	3.68E+05
1.8557	1	3	8.97E+05
2.095	3	1	3.5E+06
2.101	1	3	2.0E+06
2.101	5	5	7.9E+05
2.102	3	5	2.1E+06
2.103	3	5	1.2E+06
2.104	1	3	1.4E+06
2.105	3	3	9.6E+05
2.106	3	3	2.0E+06
2.107	5	5	2.3E+06
2.107	3	5	3.3E+06
2.109	5	3	1.7E+06
2.113	3	5	5.9E+05
2.119	3	1	2.7E+05
2.129	3	1	5.1E+05
2.1818	1	3	3.37E+06
2.1923	1	3	2.34E+05
Cobalt			
Co I			
2287.80	8	8	8.6E-01
2295.22	10	8	2.2E-01
2309.03	10	10	5.6E-01
2323.13	8	8	5.0E-01
2325.53	6	8	1.1E-01
2335.98	6	6	5.1E-01
2338.66	4	4	7.7E-01
2353.36	8	10	1.5E-01
2355.48	6	8	1.3E-01
2358.18	4	6	1.4E-01
2365.06	10	10	1.3E-01
2371.85	6	8	7.3E-02
2384.86	10	8	2.4E-01
2392.03	6	6	4.0E-01
2402.06	8	6	5.1E-01
2407.25	10	12	3.6E+00
2412.76	4	6	6.5E-01
2414.46	6	8	3.4E+00
2415.29	4	6	3.6E+00
2424.93	10	10	3.2E+00
2432.21	8	8	2.6E+00
2436.66	6	6	2.6E+00
2439.04	4	4	2.7E+00
2460.80	4	6	1.2E-01
2467.69	6	8	7.0E-02
2470.27	10	12	1.5E-01
2476.64	10	8	2.2E-01
2504.52	10	8	1.8E-01
2511.02	10	10	9.2E-01
2521.36	10	8	3.0E+00
2528.97	8	6	2.8E+00
2530.13	6	6	7.1E-02
2535.96	6	4	1.9E+00
2536.50	8	8	3.0E-01
2544.25	4	2	3.0E+00
2562.12	4	4	3.9E-01
2567.34	6	6	3.0E-01
2574.35	8	8	1.7E-01
2685.34	6	8	5.5E-02
3017.55	8	6	6.9E-02
3044.00	10	10	1.9E-01
3048.89	6	4	7.5E-02
3061.82	8	8	1.6E-01
3072.34	6	6	1.5E-01
3086.78	4	4	1.9E-01
3354.37	8	6	1.1E-01
3367.11	10	8	6.0E-02
3385.22	8	6	1.1E-01
3388.16	6	4	2.4E-01
3395.37	6	8	2.9E-01
3405.12	10	10	1.0E+00
3409.17	8	8	4.2E-01
3412.34	8	10	6.1E-01
3412.63	10	8	1.2E-01
3414.74	4	4	8.8E-02
3417.15	6	6	3.2E-01
3431.58	8	6	1.1E-01
3433.05	4	4	1.0E+00
3442.92	6	4	1.2E-01
3443.64	8	8	6.9E-01
3449.17	6	6	7.6E-01
3449.44	10	10	1.8E-01
3453.51	10	12	1.1E+00
3455.24	4	2	1.9E-01
3462.80	4	6	7.9E-01
3465.79	10	12	9.2E-02
3474.02	6	8	5.6E-01
3483.41	8	10	5.5E-02
3489.40	8	6	1.3E+00
3491.32	4	4	5.0E-02
3495.68	4	6	4.9E-01
3502.28	10	8	8.0E-01
3502.63	6	6	5.2E-02
3506.32	8	6	8.2E-01
3509.84	6	8	3.2E-01
3512.64	6	4	1.0E+00
3513.48	8	10	7.8E-02
3518.34	6	4	1.6E+00
3521.58	10	8	1.8E-01
3523.42	4	2	9.8E-01
3526.85	10	10	1.3E-01
3529.03	6	8	8.8E-02
3529.82	8	10	4.6E-01
3533.36	4	6	9.1E-02
3560.89	4	4	2.3E-01
3564.95	6	8	7.0E-02
3569.37	8	8	1.6E+00
3574.97	6	6	1.5E-01
3575.36	8	8	9.6E-02
3585.15	8	8	7.1E-02
3587.19	6	6	1.4E+00
3594.87	6	6	9.2E-02
3602.08	4	4	1.0E-01
3704.06	6	8	1.2E-01
3745.49	8	8	7.5E-02
3842.05	8	6	1.3E-01
3845.47	8	10	4.6E-01
3861.16	6	4	1.4E-01
3873.12	10	8	1.2E-01
3873.95	8	6	1.0E-01
3881.87	6	4	8.2E-02
3894.07	6	8	6.9E-01
3894.98	4	2	8.8E-02
3935.96	8	10	6.2E-02
3995.31	8	10	2.5E-01
3997.90	6	8	7.0E-02
4092.39	8	8	5.7E-02
4110.53	6	6	5.5E-02
4118.77	6	8	1.6E-01
4121.32	8	10	1.9E-01
5146.75	8	8	1.5E-01
5212.70	10	10	1.9E-01
5265.79	6	8	5.0E-02
5280.63	10	8	2.8E-01
5352.05	12	10	2.7E-01
5477.09	6	8	6.8E-02
5483.96	8	10	7.3E-02
6082.43	10	10	5.4E-02
6455.00	8	10	9.0E-02
7838.12	8	10	5.4E-02
8093.93	12	10	2.0E-01
8372.79	10	10	8.7E-02
Co II			
2286.15	11	13	3.3E+00
2307.85	9	11	2.6E+00
2311.61	7	9	2.8E+00
2314.05	5	7	2.8E+00
2314.97	3	5	2.7E+00
2330.36	5	3	1.32E+00
2344.28	3	3	1.5E+00
2353.41	7	7	1.9E+00
2363.80	9	9	2.1E+00
2378.62	11	9	1.9E+00
2383.45	9	7	1.8E+00
2388.92	11	11	2.8E+00
2389.54	5	3	1.5E+00
2404.17	3	3	1.5E+00
2417.66	9	9	8.5E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
Copper			
Cu I			
*2024.3	2	6	9.8E-02
2165.1	2	4	5.1E-01
2178.9	2	4	9.13E-01
2181.7	2	2	1.0E+00
2225.7	2	2	4.6E-01
2244.3	2	4	1.19E-02
2441.6	2	2	2.0E-02
2492.2	2	4	3.11E-02
2618.4	6	4	3.07E-01
2766.4	4	4	9.6E-02
2824.4	6	6	7.8E-02
2961.2	6	8	3.76E-02
3063.4	4	4	1.55E-02
3194.1	4	4	1.55E-02
3247.5	2	4	1.39E+00
3274.0	2	2	1.37E+00
3337.8	6	8	3.8E-03
4022.6	2	4	1.90E-01
4062.6	4	6	2.10E-01
4249.0	2	2	1.95E-01
4275.1	6	8	3.45E-01
4480.4	2	2	3.0E-02
4509.4	4	2	2.75E-01
4530.8	4	2	8.4E-02
4539.7	6	4	2.12E-01
4587.0	8	6	3.20E-01
4651.1	10	8	3.80E-01
4704.6	8	8	5.5E-02
5105.5	6	4	2.0E-02
5153.2	2	4	6.0E-01
5218.2	4	6	7.5E-01
5220.1	4	4	1.50E-01
5292.5	8	8	1.09E-01
5700.2	4	4	2.4E-03
5782.1	4	2	1.65E-02
Cu II			
2489.7	5	5	1.5E-02
2544.8	9	7	1.1E+00
2689.3	7	7	4.1E-01
2701.0	5	5	6.7E-01
2703.2	3	3	1.2E+00
2713.5	5	5	6.8E-01
Dysprosium			
Dy I			
2862.7	17	15	6.5E-02
2964.6	17	17	6.5E-02
3147.7	15	17	1.1E-01
3263.2	15	13	1.4E-01
3511.0	15	13	3.1E-01
3571.4	15	13	2.0E-01
3757.1	17	19	3.0E+00
3868.8	17	17	3.1E+00
3967.5	17	19	8.7E-01
4046.0	17	15	1.5E+00
4103.9	13	11	1.7E+00
4186.8	17	17	1.32E+00
4194.8	17	17	7.2E-01
4211.7	17	19	2.08E+00
4218.1	15	15	1.85E+00
4221.1	15	17	1.52E+00
4225.2	13	15	4.5E+00
4268.3	15	15	3.6E-02
4276.7	13	13	7.3E-01
4292.0	15	15	5.8E-02
4577.8	17	19	2.2E-02
4589.4	17	15	1.3E-01
4612.3	17	15	8.2E-02
5077.7	17	17	5.7E-03
5301.6	17	15	1.1E-02
5547.3	17	17	2.7E-03
5639.5	17	19	4.7E-03
5974.5	17	17	4.0E-03
5988.6	17	15	5.3E-03
6010.8	15	15	2.6E-02
6088.3	15	13	3.5E-02
6168.4	15	17	2.5E-02
6259.1	17	19	8.5E-03
6579.4	17	15	7.5E-03
Erbium			
Er I			
3862.9	13	13	2.5E+00
4008.0	13	15	2.6E+00
4151.1	13	11	1.8E+00
Europium			
Eu I			
2372.9	8	6	1.9E-01
2375.3	8	8	2.0E-01
2379.7	8	10	2.0E-01
2619.3	8	10	7.0E-03
2643.8	8	8	6.6E-03
2659.4	8	10	1.2E-02
2682.6	8	6	1.2E-02
2710.0	8	10	1.4E-01
2724.0	8	8	1.2E-01
2731.4	8	8	3.1E-02
2732.6	8	6	3.7E-02
2735.3	8	10	4.7E-02
2738.6	8	10	1.3E-02
2743.3	8	6	1.1E-01
2745.6	8	6	5.0E-02
2747.8	8	8	5.2E-02
2772.9	8	6	1.0E-02
2878.9	8	10	2.8E-02
2892.5	8	8	1.0E-01
2893.0	8	6	1.0E-01
2909.0	8	10	6.9E-02
2958.9	8	6	1.6E-02
3059.0	8	8	3.8E-02
3067.0	8	10	9.1E-03
3106.2	8	10	5.5E-02
3111.4	8	10	3.0E-01
3168.3	8	10	6.9E-02
3185.5	8	10	5.8E-03
3210.6	8	8	1.1E-01
3212.8	8	8	2.9E-01
3213.8	8	6	1.8E-01
3235.1	8	10	1.0E-02
3241.4	8	8	2.3E-02
3246.0	8	6	1.4E-02
3247.6	8	8	2.3E-02
3322.3	8	6	3.5E-02
3334.3	8	6	3.4E-01
3350.4	8	10	1.5E-02
3353.7	8	8	5.8E-03
3457.1	8	8	8.4E-03
3467.9	8	8	1.0E-02
3589.3	8	6	6.9E-03
4594.0	8	10	1.4E+00
4627.2	8	8	1.3E+00
4661.9	8	6	1.3E+00
5645.8	8	6	5.4E-03
5765.2	8	8	1.1E-02
6018.2	8	10	8.5E-03
6291.3	8	6	1.8E-03
6864.5	8	10	5.8E-03
7106.5	8	8	2.6E-03
Fluorine			
F I			
806.96	4	6	3.3E+00
809.60	2	4	2.8E+00
951.87	4	2	2.6E+00
954.83	4	4	5.77E+00
955.55	2	2	5.1E+00
958.52	2	4	1.3E+00
6239.7	6	4	2.5E-01
6348.5	4	4	1.8E-01
6413.7	2	4	1.1E-01
6708.3	6	4	1.4E-02
6774.0	6	6	1.0E-01
6795.5	4	2	5.2E-02
6834.3	4	4	2.1E-01
6856.0	6	8	4.94E-01
6870.2	2	2	3.8E-01
6902.5	4	6	3.2E-01
6909.8	2	4	2.2E-01
6966.4	4	2	1.1E-01
7037.5	4	4	3.0E-01
7127.9	2	2	3.8E-01
7309.0	6	8	4.7E-01
7311.0	4	2	3.9E-01
7314.3	4	6	4.8E-01
7332.0	6	4	3.1E-01
7398.7	6	6	2.85E-01
7425.7	4	2	3.4E-01
7482.7	4	4	5.6E-02
7489.2	2	2	1.1E-01
7514.9	2	2	5.2E-02
7552.2	4	6	7.8E-02
7573.4	2	4	1.0E-01
7607.2	4	4	7.0E-02
7754.7	4	6	3.82E-01
7800.2	2	4	2.1E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
Gallium			
Ga I			
2195.4	2	2	1.9E-02
2199.7	4	2	3.3E-02
2214.4	4	6	1.2E-02
2235.9	4	2	4.3E-02
2255.0	2	2	3.1E-02
2259.2	4	6	3.1E-02
2294.2	2	4	7.0E-02
2297.9	4	2	5.8E-02
2338.2	4	6	9.8E-02
2371.3	2	2	5.7E-02
2418.7	4	2	1.0E-01
2450.1	2	4	2.8E-01
2500.2	4	6	3.4E-01
2659.9	2	2	1.2E-01
2719.7	4	2	2.3E-01
2874.2	2	4	1.2E+00
2943.6	4	6	1.4E+00
2944.2	4	4	2.7E-01
4033.0	2	2	4.9E-01
4172.0	4	2	9.2E-01
Ga II			
829.60	1	3	2.2E-01
1414.4	1	3	1.88E+01
Germanium			
Ge I			
1944.7	3	1	7.0E-01
1955.1	3	3	2.8E-01
1988.3	5	3	2.5E-01
1998.9	5	5	5.5E-01
2041.7	1	3	1.1E+00
2065.2	3	3	8.5E-01
2068.7	3	5	1.2E+00
2086.0	3	5	4.0E-01
2094.3	5	7	9.7E-01
2105.8	5	5	1.7E-01
2256.0	5	5	3.2E-02
2417.4	5	5	9.6E-01
2498.0	1	3	1.3E-01
2533.2	3	3	1.0E-01
2589.2	5	3	5.1E-02
2592.5	3	5	7.1E-01
2651.2	5	5	2.0E+00
2651.6	1	3	8.5E-01
2691.3	3	3	6.1E-01
2709.6	3	1	2.8E+00
2754.6	5	3	1.1E+00
3039.1	5	3	2.8E+00
3124.8	5	5	3.1E-02
3269.5	5	3	2.9E-01
4226.6	1	3	2.1E-01
4685.8	1	3	9.5E-02
Ge II			
999.10	2	4	1.9E+00
1016.6	4	6	2.1E+00
1017.1	4	4	3.5E-01
1055.0	2	2	6.9E-01
1075.1	4	2	1.3E+00
1237.1	2	4	1.9E+01
1261.9	4	6	2.2E+01
1264.7	4	4	3.5E+00
1602.5	2	2	3.4E+00
1649.2	4	2	6.5E+00
4741.8	2	4	4.6E-01
4814.6	4	6	5.1E-01
4824.1	4	4	8.6E-02
5131.8	4	6	1.9E+00
5178.5	6	6	1.3E-01
5178.6	6	8	2.0E+00
5893.4	2	4	9.2E-01
6021.0	2	2	8.4E-01
6336.4	2	2	4.4E-01
6484.2	4	2	8.5E-01
Gold			
Au I			
2427.95	2	4	1.99E+00
2675.95	2	2	1.64E+00
3122.78	6	4	1.90E-01
6278.30	4	2	3.4E-02
Helium			
He I			
510.00	1	3	4.622E-01
512.10	1	3	7.317E-01
515.62	1	3	1.258E+00
522.21	1	3	2.436E+00
537.03	1	3	5.663E+00
584.33	1	3	1.799E+01
*2677.1	3	9	4.417E-03
*2696.1	3	9	6.023E-03
*2723.2	3	9	8.500E-03
*2763.8	3	9	1.251E-02
*2829.1	3	9	1.939E-02
*2945.1	3	9	3.201E-02
*3187.7	3	9	5.636E-02
3231.3	1	3	5.102E-03
3258.3	1	3	6.963E-03
3296.8	1	3	9.843E-03
3354.6	1	3	1.454E-02
3447.6	1	3	2.269E-02
*3554.4	9	15	7.597E-03
*3563.0	9	3	4.836E-03
*3587.3	9	15	1.811E-02
3613.6	1	3	3.802E-02
*3634.2	9	15	2.606E-02
*3652.0	9	3	9.744E-03
*3705.0	9	15	3.953E-02
*3819.6	9	15	6.435E-02
3833.6	3	5	9.647E-03
*3867.5	9	3	2.447E-02
3871.8	3	5	1.339E-02
*3888.7	3	9	9.475E-02
3926.5	3	5	1.937E-02
3935.9	3	1	7.448E-03
3964.7	1	3	6.951E-02
4009.3	3	5	2.961E-02
4024.0	3	1	1.128E-02
*4026.2	9	15	1.160E-01
*4120.8	9	3	4.453E-02
4143.8	3	5	4.881E-02
4169.0	3	1	1.830E-02
4387.9	3	5	8.989E-02
4437.6	3	1	3.269E-02
*4471.5	9	15	2.458E-01
*4713.2	9	3	9.521E-02
4921.9	3	5	1.986E-01
5015.7	1	3	1.337E-01
5047.7	3	1	6.771E-02
*5875.7	9	15	7.070E-01
6678.2	3	5	6.371E-01
*7065.2	9	3	2.785E-01
7281.4	3	1	1.830E-01
*8361.7	3	9	3.813E-03
*9463.6	3	9	5.687E-03
9603.4	1	3	5.829E-03
*9702.6	9	3	8.651E-03
*10311	9	15	1.995E-02
*10668	9	3	1.447E-02
*10830	3	9	1.022E-01
*10913	15	21	1.980E-02
10917	5	7	1.608E-02
*10997	15	9	1.425E-03
11013	1	3	9.250E-03
11045	3	5	1.846E-02
11226	3	1	1.117E-02
*11969	9	15	3.478E-02
*12528	3	9	7.093E-03
12756	5	3	1.275E-03
*12785	15	21	4.134E-02
12791	5	7	3.248E-02
*12846	9	3	2.732E-02
12968	3	5	3.362E-02
*12985	15	9	2.729E-03
Indium			
In I			
2560.2	2	4	4.0E-01
2710.3	4	6	4.0E-01
3039.4	2	4	1.3E+00
3256.1	4	6	1.3E+00
4101.8	2	2	5.6E-01
4511.3	4	2	1.02E+00
In II			
2941.1	3	1	1.4E+00
Iodine			
I I			
1782.8	4	4	2.71E+00
1830.4	4	6	1.6E-01
Iridium			
Ir I			
2475.12	10	10	2.1E-01
2502.98	10	12	3.2E-01
2639.71	10	10	4.7E-01
2661.98	10	10	2.5E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
2664.79	10	8	4.0E-01
2694.23	10	12	4.8E-01
2849.72	10	10	2.2E-01
2853.31	10	10	2.0E-03
2882.64	10	8	7.2E-02
2924.79	10	12	1.42E-01
2934.64	8	10	2.0E-01
2951.22	10	8	2.8E-02
3003.63	8	10	5.9E-02
3168.88	8	10	5.47E-02
3220.78	10	8	2.4E-01
3558.99	6	8	1.5E-02
3573.72	8	10	5.4E-02
3617.21	6	8	2.0E-02
3628.67	8	8	2.8E-02
3661.71	8	10	4.0E-02
3734.77	8	8	2.7E-02
4033.76	8	10	2.7E-02
4069.92	6	8	3.6E-02
4913.35	12	12	3.3E-02
4939.24	10	12	2.5E-03
Iron			
Fe I			
1934.54	9	7	2.5E-01
1937.27	9	7	2.2E-01
1940.66	7	5	2.6E-01
2132.02	9	9	7.6E-02
2145.19	7	7	5.7E-02
2153.01	5	5	6.9E-02
2161.58	3	5	5.0E-02
2166.77	9	7	2.7E+00
2171.30	5	7	5.1E-02
2173.21	3	5	8.3E-02
2176.84	1	3	1.0E-01
2191.84	5	5	1.2E+00
2196.04	3	3	1.2E+00
2200.39	1	3	8.9E-01
2200.72	3	5	2.8E-01
2259.51	9	11	5.66E-02
2272.07	7	9	2.92E-02
2276.03	9	7	1.25E-01
2284.09	7	5	1.29E-01
2287.25	5	3	2.23E-01
2292.52	7	9	2.96E-02
2294.41	3	1	3.61E-01
2297.79	7	7	1.44E-01
2298.17	9	9	3.09E-01
2299.22	5	5	7.03E-02
2300.14	5	7	4.99E-02
2301.68	1	3	8.68E-02
2303.58	3	5	4.83E-02
2309.00	3	5	1.02E-01
2313.10	5	7	1.18E-01
2320.36	7	9	1.41E-01
2373.62	7	7	6.53E-02
2389.97	5	7	4.47E-02
2438.18	11	9	7.09E-02
2439.74	13	13	3.46E+00
2442.57	11	11	3.12E+00
2443.87	11	11	5.89E-02
2453.48	9	7	1.89E-01
2453.57	11	13	1.23E-01
2457.60	11	11	4.81E-01
2462.18	7	5	1.10E-01
2462.65	9	9	5.85E-01
2463.73	7	5	1.64E-01
2465.15	9	9	4.35E-01
2468.88	11	11	2.40E-01
2470.97	9	11	2.36E-02
2472.34	11	13	7.21E-02
2472.87	5	3	2.10E-01
2472.89	7	7	1.30E+00
2473.16	9	9	2.75E-02
2474.81	7	7	6.13E-01
2476.66	5	3	3.05E-01
2479.48	5	5	2.10E-01
2479.78	5	5	1.74E+00
2483.27	9	11	4.80E+00
2483.53	5	5	2.09E-01
2484.19	3	3	2.26E+00
2485.99	9	9	2.94E-02
2486.69	7	9	1.47E-01
2487.07	3	3	6.40E-01
2488.14	7	9	4.20E+00
2489.75	1	3	2.31E+00
2489.91	3	5	8.72E-02
2490.64	5	7	3.44E+00
2491.16	3	5	2.91E+00
2491.99	9	9	3.25E-01
2494.00	3	5	8.89E-02
2496.53	9	11	2.15E-01
2501.13	9	7	6.75E-01
2501.69	11	9	3.69E-02
2505.01	9	11	2.56E-01
2506.57	7	9	2.04E-01
2507.90	7	9	1.93E-01
2510.83	7	5	1.29E+00
2517.66	5	7	1.58E-01
2518.10	5	3	1.93E+00
2519.63	3	5	1.34E-01
2522.85	9	9	2.13E+00
2524.29	3	1	3.23E+00
2527.27	13	13	3.46E-01
2527.44	7	7	1.93E+00
2529.14	5	5	9.91E-01
2529.31	5	7	4.86E+00
2529.84	3	3	3.83E-01
2533.14	11	11	2.07E-01
2535.61	1	3	9.59E-01
2537.17	13	15	3.70E+00
2537.46	9	11	3.19E-02
2540.97	3	5	9.59E-01
2542.10	11	13	4.47E+00
2543.92	9	11	4.70E+00
2545.98	5	7	7.16E-01
2549.61	7	9	2.31E-01
2576.69	11	11	1.13E-01
2584.54	11	13	3.15E-01
2599.57	9	9	1.47E-01
2606.83	9	11	2.43E-01
2609.22	7	7	4.60E-01
2618.02	7	7	1.50E-01
2623.53	7	9	2.13E-01
2632.24	5	5	1.21E-01
2635.72	11	9	4.29E-02
2635.81	5	7	2.11E-01
2641.03	9	7	7.71E-02
2641.64	9	7	6.47E-02
2644.00	3	5	2.34E-01
2656.15	13	15	1.63E-01
2662.06	7	5	4.64E-02
2666.81	11	9	8.91E-02
2666.97	9	11	5.16E-02
2669.49	11	13	1.34E-01
2679.02	9	11	1.10E-01
2679.06	11	11	1.50E-01
2689.21	9	7	1.68E-01
2689.83	7	9	3.04E-02
2697.02	7	9	3.51E-02
2699.11	9	9	5.59E-02
2701.91	9	7	1.05E-01
2702.45	13	11	4.23E-02
2706.01	13	13	2.28E-01
2706.58	7	5	2.69E-01
2708.57	9	9	6.49E-01
2710.54	5	7	5.99E-02
2711.66	9	11	4.99E-02
2716.26	9	9	3.70E-02
2716.42	11	9	4.96E-02
2718.44	5	3	3.79E-01
2719.03	9	7	1.42E+00
2719.06	7	7	7.40E-01
2719.42	11	11	3.20E-01
2720.90	7	5	1.04E+00
2723.58	5	3	5.69E-01
2724.95	7	9	4.76E-02
2726.06	3	1	5.52E-01
2728.02	9	9	3.45E-02
2728.82	9	9	2.98E-01
2731.28	5	7	6.84E-02
2733.58	11	9	7.10E-01
2735.48	9	7	5.03E-01
2737.31	3	3	7.25E-01
2737.64	13	11	1.14E-01
2742.25	7	5	3.41E-01
2742.41	5	5	4.70E-01
2743.57	7	7	4.84E-02
2744.07	1	3	3.09E-01
2744.53	5	3	2.53E-01
2750.14	7	7	2.74E-01
2753.69	3	1	4.00E-01
2754.03	5	5	7.29E-02
2755.18	11	9	5.13E-02
2756.33	3	5	1.41E-01
2757.32	3	3	2.85E-01
2761.78	5	5	1.94E-01
2762.03	7	7	1.76E-01
2767.52	9	9	1.48E-01
2769.30	13	13	1.80E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
2772.07	11	11	2.34E-02
2772.11	5	7	4.12E-02
2778.22	11	11	9.08E-02
2780.70	9	9	9.01E-02
2784.34	11	11	2.30E-02
2787.93	9	11	2.27E-02
2788.10	11	13	5.92E-01
2789.80	11	9	2.36E-01
2797.78	9	9	4.52E-02
2803.61	9	9	1.04E-01
2804.52	9	9	1.05E-01
2804.86	9	7	2.40E-01
2806.98	9	11	1.15E-01
2812.04	9	9	5.00E-02
2813.29	9	11	3.42E-01
2823.28	7	7	1.51E-01
2825.56	7	9	1.32E-01
2832.44	7	9	2.38E-01
2834.75	9	11	5.41E-02
2838.12	5	5	1.28E-01
2843.63	9	7	6.96E-02
2843.98	5	7	3.17E-01
2845.59	7	5	7.86E-02
2851.80	3	5	3.37E-01
2853.77	7	9	5.91E-02
2863.43	9	9	4.13E-02
2868.45	5	3	1.45E-01
2877.30	9	9	4.61E-02
2883.75	11	11	2.91E-02
2887.81	11	13	7.98E-02
2892.48	9	9	8.78E-02
2894.50	5	5	4.83E-01
2895.03	7	7	4.24E-02
2899.41	5	3	4.68E-01
2901.91	11	11	1.78E-01
2907.52	9	11	1.61E-01
2908.86	7	9	8.98E-02
2918.02	13	13	1.18E+00
2919.84	9	11	7.44E-02
2920.69	5	5	6.38E-02
2923.29	11	11	1.39E+00
2923.85	11	11	2.97E-01
2925.36	7	9	1.69E-01
2929.01	7	5	5.10E-02
2929.12	9	9	1.53E+00
2936.90	9	9	1.40E-01
2947.36	5	5	9.30E-02
2947.88	7	7	1.83E-01
2948.43	9	9	3.32E-01
2953.49	7	7	3.64E-01
2953.94	5	5	1.89E-01
2954.65	5	7	1.06E-01
2957.36	3	3	1.77E-01
2957.48	5	3	1.31E-01
2959.99	11	13	5.02E-01
2960.66	11	9	8.48E-02
2965.25	1	3	1.16E-01
2966.90	9	11	2.72E-01
2968.48	3	3	8.26E-02
2970.10	3	5	1.08E-01
2973.13	5	7	1.35E-01
2973.24	7	9	1.83E-01
2976.13	5	7	9.70E-02
2980.53	7	7	1.66E-01
2981.45	7	5	6.53E-02
2981.85	7	9	1.86E-01
2982.23	9	7	3.47E-02
2983.57	9	7	2.79E-01
2987.29	9	7	5.25E-02
2990.39	9	11	3.5E-01
2994.43	7	5	4.39E-01
2996.39	3	5	1.70E-01
2999.51	11	11	1.70E-01
3000.45	9	11	5.41E-02
3000.95	5	3	6.42E-01
3003.03	7	5	7.50E-02
3004.11	11	11	2.79E-02
3005.30	13	15	2.94E-02
3007.15	9	7	7.34E-02
3008.14	3	1	1.07E+00
3009.09	13	11	7.77E-02
3009.57	9	9	1.43E-01
3011.48	7	9	3.79E-01
3015.92	11	9	6.3E-02
3016.18	5	3	8.85E-02
3018.98	7	7	1.03E-01
3019.29	9	11	2.33E-02
3020.49	5	5	1.94E-01
3020.64	9	9	7.59E-01
3021.07	7	7	4.55E-01
3024.03	3	5	4.87E-02
3025.64	13	13	5.86E-01
3025.84	1	3	3.48E-01
3026.46	5	5	1.10E-01
3030.15	11	11	5.04E-01
3031.64	3	3	1.38E-01
3037.39	3	5	2.91E-01
3040.43	9	11	2.45E-02
3041.64	7	9	4.24E-02
3041.74	7	9	5.20E-02
3042.02	3	5	4.70E-02
3042.66	5	7	5.20E-02
3047.60	5	7	2.84E-01
3053.07	3	5	1.53E-01
3055.26	7	5	9.48E-02
3057.45	11	9	3.13E-01
3059.09	7	9	1.63E-01
3060.54	9	7	6.75E-02
3066.48	9	7	9.11E-02
3067.00	11	13	1.71E-01
3067.12	5	7	3.89E-02
3067.24	9	7	3.12E-01
3068.17	5	3	1.11E-01
3073.98	11	9	3.83E-02
3075.72	7	5	3.14E-01
3078.43	1	3	1.52E-01
3079.99	9	11	8.35E-02
3083.74	5	3	3.08E-01
3091.58	3	1	5.53E-01
3098.19	11	11	7.52E-02
3099.89	3	3	1.93E-01
3099.97	9	9	8.23E-02
3100.30	5	5	1.87E-01
3100.67	7	7	1.35E-01
3100.84	13	11	2.73E-02
3101.00	9	9	5.53E-02
3112.08	11	11	5.24E-02
3119.49	11	9	8.28E-02
3120.44	9	7	7.26E-02
3125.68	13	11	8.46E-02
3132.52	9	7	3.39E-01
3142.45	7	7	3.93E-02
3142.89	5	5	5.65E-02
3143.99	9	9	6.10E-01
3145.06	9	9	4.65E-02
3147.79	7	7	7.59E-02
3153.20	7	9	7.91E-02
3154.50	5	7	4.64E-02
3156.27	7	7	6.36E-01
3157.04	9	11	1.26E-01
3157.89	5	7	1.61E-01
3160.66	9	9	1.93E-01
3161.95	11	13	4.65E-02
3165.86	7	9	5.35E-02
3166.44	9	7	1.14E-01
3171.35	9	7	1.85E-01
3175.44	11	11	1.44E-01
3178.01	11	9	1.28E-01
3180.22	7	9	4.42E-01
3181.52	7	5	1.84E-01
3182.06	9	9	3.23E-02
3182.97	5	7	1.42E-01
3188.57	11	11	5.00E-02
3188.82	3	5	2.53E-01
3190.65	9	11	5.75E-02
3190.82	9	9	5.55E-02
3192.80	3	5	5.01E-01
3193.30	5	7	3.07E-01
3194.42	5	3	1.08E-01
3196.12	11	9	1.40E-01
3196.93	9	11	5.97E-01
3199.53	9	9	2.23E-01
3202.56	9	7	6.18E-02
3205.40	3	3	9.77E-01
3210.23	9	11	1.15E-01
3210.83	5	3	9.24E-01
3211.61	9	9	3.07E-02
3211.99	11	9	4.64E-01
3214.01	7	7	8.38E-01
3214.06	7	5	1.18E+00
3215.94	5	5	6.19E-01
3217.38	11	9	1.50E-01
3219.58	7	9	4.64E-01
3219.80	9	7	3.61E-01
3221.92	3	3	1.22E-01
3222.07	11	11	8.65E-01
3225.79	11	13	1.18E+00
3227.80	9	7	4.96E-01
3228.25	5	3	3.72E-01
3229.99	9	11	1.06E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3230.21	5	5	2.06E-01
3230.96	7	5	3.7E-01
3233.05	13	15	4.19E-01
3233.97	9	9	2.08E-01
3239.43	9	9	2.95E-01
3244.19	9	11	3.06E-01
3246.96	5	3	1.09E-01
3248.20	7	7	1.92E-01
3250.76	11	11	2.85E-02
3252.91	9	11	2.20E-02
3253.60	7	9	1.62E-01
3254.36	11	13	4.24E-01
3257.23	9	9	4.76E-02
3257.59	7	5	8.94E-02
3259.99	7	9	2.99E-02
3264.51	5	3	1.01E-01
3265.62	7	5	3.06E-01
3271.00	5	3	6.4E-01
3271.48	7	7	8.47E-02
3280.26	9	11	4.21E-01
3282.89	3	5	3.42E-01
3284.59	5	5	5.64E-02
3286.75	7	7	5.99E-01
3290.99	3	5	7.58E-02
3292.02	7	9	5.77E-01
3292.59	3	3	3.0E-01
3298.13	3	5	9.01E-02
3305.97	5	7	4.05E-01
3306.34	9	9	5.74E-01
3306.35	3	5	4.84E-01
3307.23	13	13	1.97E-01
3310.34	11	11	3.78E-02
3310.49	7	9	6.17E-02
3314.74	5	7	7.25E-01
3319.25	9	9	3.73E-02
3322.47	9	11	8.21E-02
3323.74	5	5	2.8E-01
3328.87	11	11	2.21E-01
3335.77	3	5	7.48E-02
3336.26	9	9	4.91E-02
3337.67	11	9	6.06E-02
3340.56	5	5	4.95E-02
3341.91	11	11	3.02E-02
3342.29	3	3	9.42E-02
3347.93	5	5	4.91E-02
3354.06	1	3	1.34E-01
3355.23	9	9	2.59E-01
3369.55	9	9	2.15E-01
3370.78	11	11	2.89E-01
3380.11	7	7	1.66E-01
3383.69	5	3	8.33E-02
3383.98	7	7	6.52E-02
3392.30	5	5	9.93E-02
3392.65	7	7	1.88E-01
3394.58	5	3	8.70E-02
3399.33	5	5	2.76E-01
3402.26	13	13	2.19E-01
3403.29	5	7	3.98E-02
3404.35	5	7	1.09E-01
3406.44	3	5	2.7E-01
3406.80	3	3	2.08E-01
3407.46	7	9	6.09E-01
3410.17	3	5	5.07E-01
3411.35	9	9	6.0E-02
3413.13	5	7	3.23E-01
3415.53	3	5	4.64E-02
3417.84	3	3	4.01E-01
3418.51	3	1	9.88E-01
3422.66	3	5	1.38E-01
3424.28	7	7	1.61E-01
3425.01	9	7	2.57E-01
3426.63	5	3	1.94E-01
3426.67	11	11	1.07E-01
3427.12	7	9	5.04E-01
3428.19	5	5	1.71E-01
3431.81	5	7	5.53E-02
3440.61	9	7	1.71E-01
3440.99	7	5	1.24E-01
3443.88	5	3	7.92E-02
3445.15	5	7	2.34E-01
3447.28	5	5	1.07E-01
3450.33	3	3	2.34E-01
3451.91	3	5	1.13E-01
3458.30	3	1	2.92E-01
3459.91	5	3	2.17E-01
3465.86	3	3	1.19E-01
3468.84	9	11	2.61E-02
3469.01	9	9	8.58E-02
3475.45	5	5	9.75E-02
3475.65	7	5	8.61E-02
3476.34	7	7	2.70E-01
3476.85	7	9	3.21E-02
3485.34	5	3	1.30E-01
3489.67	11	13	7.47E-02
3490.57	7	7	6.14E-02
3495.29	9	7	9.46E-02
3497.10	7	7	9.02E-02
3500.56	7	5	5.28E-02
3505.06	5	3	1.77E-01
3506.50	5	5	7.35E-02
3508.47	9	11	6.46E-02
3513.82	11	11	3.40E-02
3516.41	7	9	3.6E-02
3516.56	7	5	6.82E-02
3521.26	9	9	6.14E-02
3522.27	11	11	5.03E-02
3522.90	5	7	3.51E-02
3523.31	5	3	1.06E-01
3524.07	7	5	9.9E-02
3524.24	5	7	5.04E-02
3526.17	7	7	4.14E-02
3526.24	7	9	1.70E-01
3526.38	7	7	4.13E-01
3526.47	5	5	1.29E-01
3526.67	5	5	5.26E-01
3527.79	9	9	2.17E-01
3529.82	3	3	7.75E-01
3530.39	13	13	4.65E-02
3533.01	1	3	8.52E-01
3533.20	3	5	8.25E-01
3534.53	11	11	2.20E-02
3536.56	5	7	9.95E-01
3537.73	5	3	1.33E-01
3537.89	11	11	8.0E-02
3540.12	7	9	9.48E-02
3541.08	9	11	8.65E-01
3542.08	7	9	9.51E-01
3543.67	3	5	1.6E-01
3545.64	9	9	2.05E-01
3547.19	9	9	7.13E-02
3552.11	3	5	4.8E-02
3552.83	5	5	1.74E-01
3553.74	11	9	1.09E+00
3554.50	3	5	9.87E-02
3554.92	11	13	1.40E+00
3556.88	9	11	4.1E-01
3558.52	5	7	1.77E-01
3559.50	3	3	2.2E-01
3560.70	7	9	7.4E-02
3565.38	7	9	4.29E-01
3567.03	5	7	8.34E-02
3568.82	7	9	6.72E-02
3568.97	11	9	4.64E-02
3570.10	9	11	6.76E-01
3572.00	11	11	2.89E-01
3572.59	9	9	3.31E-02
3573.39	5	7	1.05E-01
3573.83	13	13	2.41E-02
3573.89	9	7	5.73E-01
3575.11	3	3	1.60E-01
3575.25	11	9	7.43E-02
3575.37	5	5	3.06E-01
3576.76	11	9	8.8E-02
3578.38	1	3	7.82E-02
3581.19	11	13	1.02E+00
3581.65	11	9	3.21E-02
3581.81	3	5	8.68E-02
3582.20	13	11	2.35E-01
3584.66	11	11	3.29E-01
3584.79	7	5	1.56E-01
3584.96	11	9	6.74E-01
3585.19	11	9	3.19E-02
3585.32	7	7	1.17E-01
3585.71	9	9	3.75E-02
3586.11	13	11	7.02E-01
3586.74	13	13	3.62E-02
3586.98	5	5	1.66E-01
3587.24	7	9	7.73E-02
3588.53	9	7	7.21E-02
3588.61	11	11	1.19E-01
3588.92	5	3	2.15E-01
3589.45	9	7	1.05E-01
3594.63	9	9	3.14E-01
3595.30	5	5	8.21E-02
3597.02	5	3	1.8E-01
3599.63	11	9	2.33E-01
3602.46	7	7	1.02E-01
3602.53	7	5	2.12E-01
3603.20	11	11	2.59E-01
3603.82	3	3	1.70E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3605.45	9	9	4.66E-01
3605.50	13	11	2.12E-01
3606.68	11	13	8.29E-01
3608.14	9	11	6.22E-02
3608.86	3	5	8.13E-01
3610.16	13	13	5.90E-01
3610.69	5	3	1.05E-01
3612.07	11	13	1.11E-01
3613.44	7	7	7.0E-02
3617.79	5	7	7.09E-01
3618.30	11	9	4.89E-02
3618.39	9	9	8.88E-02
3618.77	5	7	7.22E-01
3621.46	9	11	4.45E-01
3621.72	11	9	1.07E-01
3622.00	7	7	5.14E-01
3623.19	13	13	6.68E-02
3625.14	11	9	8.15E-02
3630.35	9	7	1.04E-01
3631.10	11	11	2.15E-01
3631.46	7	9	5.17E-01
3632.04	3	5	6.74E-01
3632.56	11	9	5.69E-02
3633.07	9	11	3.54E-02
3634.33	9	7	1.05E-01
3636.22	5	7	2.20E-01
3637.87	9	9	5.9E-02
3638.30	7	9	2.36E-01
3640.39	9	11	3.57E-01
3644.80	7	5	8.3E-02
3645.07	9	9	2.91E-02
3645.82	1	3	4.87E-01
3647.42	3	3	3.38E-01
3647.84	9	11	2.91E-01
3649.51	11	9	3.94E-01
3650.03	7	7	2.26E-01
3650.28	11	11	6.15E-02
3651.47	7	9	5.83E-01
3655.46	5	5	1.18E-01
3659.52	9	9	6.31E-02
3664.54	7	9	4.68E-02
3666.24	11	9	3.87E-02
3667.25	9	7	1.3E-01
3668.21	7	9	3.2E-02
3669.15	9	7	8.03E-02
3669.52	9	7	2.34E-01
3670.02	3	5	8.60E-02
3670.09	11	13	7.20E-02
3674.76	5	3	7.91E-02
3676.31	9	11	4.63E-02
3677.31	5	7	2.28E-01
3677.63	7	5	6.08E-01
3682.17	7	5	1.04E-01
3682.24	5	5	1.5E+00
3684.11	9	7	2.97E-01
3684.14	9	7	9.29E-02
3686.00	9	11	3.34E-01
3687.46	11	9	8.00E-02
3687.66	9	9	7.38E-02
3688.46	7	9	7.3E-02
3689.46	9	9	3.70E-01
3690.45	1	3	1.22E-01
3690.73	11	11	2.99E-01
3694.01	5	7	8.35E-01
3695.05	7	9	2.01E-01
3697.43	7	7	1.94E-01
3698.60	5	7	3.6E-02
3699.14	5	7	4.9E-02
3701.09	7	9	6.35E-01
3702.03	3	1	3.7E-01
3703.55	7	7	3.84E-02
3703.69	9	11	6.31E-02
3703.82	1	3	1.02E-01
3704.46	11	9	1.42E-01
3707.92	7	5	3.32E-01
3709.25	9	7	1.56E-01
3711.22	7	9	3.62E-02
3711.41	3	5	1.28E-01
3716.44	9	7	3.49E-01
3718.41	7	7	5.17E-02
3719.93	9	11	1.62E-01
3721.50	5	5	1.94E-01
3722.56	5	5	4.97E-02
3724.38	5	7	1.04E-01
3726.93	5	5	4.57E-01
3727.09	9	7	1.71E-01
3727.62	7	5	2.24E-01
3727.81	7	5	1.91E-01
3730.39	9	11	9.73E-02
3730.46	7	9	3.09E-02
3730.95	5	7	3.50E-02
3732.40	5	5	2.69E-01
3734.86	11	11	9.01E-01
3735.32	9	9	2.70E-01
3737.13	7	9	1.41E-01
3738.31	11	13	3.44E-01
3740.24	7	9	1.3E-01
3742.62	9	9	6.75E-02
3743.36	5	3	2.60E-01
3743.47	11	11	6.05E-01
3744.10	5	3	3.17E-01
3745.56	5	7	1.15E-01
3746.93	7	7	2.33E-01
3748.26	3	5	9.15E-02
3748.96	9	11	1.48E-01
3749.49	9	9	7.63E-01
3753.61	7	5	1.22E-01
3756.94	11	11	2.2E-01
3757.45	5	3	8.26E-02
3758.23	7	7	6.34E-01
3759.15	13	11	4.55E-02
3760.05	13	15	4.47E-02
3760.53	3	5	5.50E-02
3762.20	9	11	2.4E-02
3763.79	5	5	5.44E-01
3765.54	13	15	9.51E-01
3765.70	11	11	2.36E-02
3767.19	3	3	6.39E-01
3778.51	7	5	1.17E-01
3779.45	3	3	1.05E-01
3781.94	5	7	3.8E-02
3785.95	11	13	4.14E-02
3786.19	5	5	1.3E-01
3787.16	5	5	9.9E-02
3787.88	3	5	1.29E-01
3789.18	9	11	2.16E-02
3789.82	9	7	4.1E-02
3793.48	7	7	7.92E-02
3794.34	9	11	4.15E-02
3795.00	5	7	1.15E-01
3797.51	13	13	4.57E-01
3798.51	9	11	3.23E-02
3799.55	7	9	7.31E-02
3801.68	5	7	6.26E-02
3801.98	11	13	3.7E-02
3802.28	5	5	5.63E-02
3804.01	11	9	4.6E-02
3805.34	9	11	8.60E-01
3806.22	3	3	2.5E-01
3806.70	11	11	4.35E-01
3807.54	3	5	9.37E-02
3808.73	9	9	3.54E-02
3810.76	5	3	1.94E-01
3812.96	7	5	7.91E-02
3813.06	7	7	5.52E-02
3813.88	13	11	6.62E-02
3815.84	9	7	1.12E+00
3816.34	5	7	4.16E-02
3817.64	11	11	7.7E-02
3819.49	7	5	4.9E-02
3820.43	11	9	6.67E-01
3821.18	11	13	5.54E-01
3821.83	5	5	7.30E-02
3825.88	9	7	5.97E-01
3827.82	7	5	1.05E+00
3829.45	3	3	1.32E-01
3833.31	9	9	4.68E-02
3834.22	7	5	4.52E-01
3836.33	5	5	3.29E-01
3839.26	9	9	2.35E-01
3840.44	5	3	4.70E-01
3841.05	5	3	1.36E+00
3843.26	9	7	3.70E-01
3845.70	5	7	5.89E-02
3845.99	9	7	4.5E-02
3846.41	11	9	1.68E-01
3846.80	7	7	6.20E-01
3849.97	3	1	6.05E-01
3852.57	7	9	3.26E-02
3854.37	9	7	5.07E-02
3856.37	7	5	4.64E-02
3859.21	13	11	7.25E-02
3859.91	9	9	9.69E-02
3865.52	3	3	1.55E-01
3867.22	5	5	3.16E-01
3871.75	11	11	5.83E-02
3872.50	5	5	1.05E-01
3873.76	11	9	6.57E-02
3878.02	7	7	7.72E-02
3878.67	9	7	7.02E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3878.73	3	3	5.34E-01
3883.28	7	7	1.28E-01
3884.36	11	9	3.99E-02
3885.51	3	5	7.26E-02
3886.28	7	7	5.29E-02
3887.05	9	9	3.52E-02
3888.51	5	5	2.50E-01
3888.82	5	3	1.95E-01
3891.93	3	3	2.71E-01
3893.39	11	11	1.00E-01
3894.01	5	5	1.03E-01
3897.89	11	13	6.20E-02
3900.52	7	7	7.9E-02
3902.95	7	7	2.14E-01
3903.90	9	9	7.61E-02
3906.75	5	7	7.05E-02
3907.93	7	5	6.67E-02
3909.66	3	5	5.7E-02
3911.00	9	9	2.68E-02
3916.73	13	11	9.83E-02
3918.42	3	1	4.22E-01
3918.64	7	7	1.17E-01
3919.07	9	9	3.72E-02
3925.64	5	5	8.04E-02
3925.94	1	3	1.67E-01
3926.01	7	7	7.26E-02
3928.08	9	9	5.64E-02
3931.12	5	7	4.8E-02
3932.63	9	11	2.70E-02
3933.60	3	5	5.92E-02
3935.81	5	5	1.14E-01
3941.28	5	5	9.1E-02
3942.44	3	5	9.62E-02
3946.99	9	11	3.91E-02
3947.53	5	5	5.12E-02
3948.10	7	9	1.31E-01
3948.77	11	9	2.08E-01
3949.95	7	5	4.79E-02
3951.16	3	5	4.29E-01
3952.60	11	11	2.97E-02
3953.15	7	9	2.97E-02
3955.34	3	3	1.5E-01
3956.46	13	11	1.76E-01
3956.68	11	13	1.22E-01
3957.02	5	7	1.67E-01
3960.28	5	7	4.10E-02
3963.10	3	5	1.5E-01
3967.42	9	7	1.52E-01
3967.96	7	9	6.09E-02
3969.26	9	7	2.26E-01
3970.39	3	1	3.9E-01
3971.32	11	9	4.97E-02
3973.65	5	7	5.81E-02
3976.61	3	5	1.20E-01
3977.74	5	5	6.41E-02
3981.77	9	9	3.57E-02
3983.96	9	7	5.72E-02
3985.39	5	5	8.53E-02
3989.86	5	7	5.3E-02
3996.96	9	9	7.95E-02
3997.39	9	11	1.26E-01
3998.05	11	9	5.70E-02
4005.24	7	5	2.04E-01
4006.31	11	9	5.1E-02
4009.71	3	5	4.64E-02
4014.53	9	7	1.53E-01
4017.15	9	11	3.25E-02
4018.27	5	7	3.44E-02
4021.87	7	9	8.55E-02
4024.73	7	9	8.09E-02
4030.49	9	11	1.04E-01
4030.89	9	7	5.02E-02
4031.96	3	5	7.6E-02
4040.64	5	7	4.8E-02
4043.90	7	7	8.69E-02
4044.61	5	3	8.17E-02
4045.59	9	7	7.39E-02
4045.81	9	9	8.62E-01
4054.87	5	3	9.61E-02
4058.22	9	7	4.47E-02
4062.44	3	3	1.85E-01
4063.59	7	7	6.65E-01
4067.98	9	9	1.51E-01
4070.77	7	5	1.1E-01
4071.74	5	5	7.64E-01
4073.76	5	3	1.68E-01
4074.79	9	9	3.43E-02
4076.63	9	9	1.32E-01
4076.80	5	7	3.81E-02
4079.17	5	5	5.4E-02
4080.21	3	1	2.3E-01
4084.49	11	9	8.66E-02
4085.00	3	5	4.7E-02
4085.30	7	7	8.92E-02
4085.98	7	5	5.1E-02
4098.18	7	7	7.49E-02
4107.49	5	3	1.74E-01
4109.80	3	3	1.51E-01
4112.96	11	13	1.1E-01
4118.55	11	13	4.96E-01
4125.62	9	11	9.9E-02
4126.18	11	11	4.2E-02
4127.61	1	3	1.43E-01
4132.06	5	7	1.18E-01
4132.90	3	5	7.70E-02
4134.68	5	7	1.25E-01
4137.00	3	5	2.75E-01
4142.59	3	5	7.5E-02
4143.41	9	9	2.70E-01
4143.87	7	9	1.33E-01
4149.37	11	13	4.23E-02
4153.90	7	9	2.05E-01
4154.50	5	3	2.64E-01
4154.81	9	11	1.40E-01
4156.80	5	5	1.20E-01
4157.78	5	7	2.18E-01
4158.79	3	5	1.6E-01
4170.90	5	5	6.29E-02
4172.12	7	5	9.80E-02
4172.64	11	11	2.24E-02
4175.64	3	5	1.14E-01
4181.75	5	7	2.32E-01
4182.38	5	5	5.04E-02
4184.89	5	5	1.03E-01
4187.04	7	5	2.15E-01
4187.80	9	7	1.52E-01
4191.43	5	3	2.73E-01
4195.33	11	11	1.11E-01
4196.21	7	7	1.09E-01
4198.25	9	9	1.47E-01
4198.30	11	9	8.03E-02
4198.63	5	5	1.25E-01
4199.10	9	11	4.92E-01
4200.92	7	9	6.25E-02
4202.03	9	9	8.22E-02
4203.94	13	13	2.97E-02
4203.98	3	5	7.37E-02
4210.34	3	3	1.48E-01
4217.55	3	5	2.46E-01
4219.36	11	13	2.88E-01
4222.21	7	7	5.76E-02
4224.17	9	11	1.06E-01
4224.51	3	5	6.81E-02
4225.45	5	7	1.65E-01
4227.43	11	13	5.29E-01
4233.60	3	5	1.85E-01
4235.94	9	9	1.88E-01
4238.81	7	9	2.41E-01
4245.26	1	3	9.0E-02
4246.09	7	5	5.85E-02
4247.43	9	11	1.94E-01
4250.12	5	7	2.07E-01
4250.79	7	7	1.02E-01
4260.47	11	11	3.99E-01
4267.83	1	3	8.17E-02
4271.15	7	9	1.82E-01
4271.76	9	11	2.28E-01
4276.68	9	9	2.6E-02
4282.40	7	5	1.21E-01
4294.12	9	9	3.12E-02
4299.23	9	11	1.29E-01
4307.90	7	9	3.38E-01
4309.03	13	13	1.96E-02
4315.08	5	5	7.76E-02
4325.76	5	7	5.16E-01
4327.10	5	5	1.12E-01
4369.77	9	9	6.09E-02
4383.55	9	11	5.00E-01
4388.41	7	7	1.03E-01
4401.29	7	7	6.4E-02
4404.75	7	9	2.75E-01
4415.12	5	7	1.19E-01
4422.57	3	3	8.72E-02
4433.22	5	3	2.1E-01
4443.19	1	3	1.02E-01
4455.03	9	7	4.1E-02
4466.55	5	7	1.20E-01
4469.38	5	7	1.59E-01
4476.02	3	5	1.01E-01
4484.22	7	9	5.04E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
4485.68	3	3	1.1E-01
4494.56	5	7	3.45E-02
4528.61	7	9	5.44E-02
4547.85	5	7	4.48E-02
4556.13	7	5	1.05E-01
4619.29	7	5	5.2E-02
4638.01	7	7	3.37E-02
4654.61	7	7	3.68E-02
4667.45	7	9	6.03E-02
4673.16	5	7	3.81E-02
4678.85	7	9	4.97E-02
4736.77	9	11	4.78E-02
4789.65	5	7	4.57E-02
4800.65	7	9	3.01E-02
4859.74	5	3	1.62E-01
4871.32	7	5	2.44E-01
4872.14	3	3	2.54E-01
4878.21	1	3	1.21E-01
4890.76	5	5	2.25E-01
4891.49	9	7	3.08E-01
4903.31	3	5	6.58E-02
4918.99	7	7	1.79E-01
4920.50	11	9	3.58E-01
4957.30	9	9	1.18E-01
4957.60	13	11	4.22E-01
4966.09	11	11	3.31E-02
4973.10	3	3	1.1E-01
4978.60	5	3	1.19E-01
4985.25	5	5	1.48E-01
4988.95	7	7	5.2E-02
5001.86	9	7	3.7E-01
5006.12	11	11	5.87E-02
5014.94	7	5	2.64E-01
5021.59	7	9	6.18E-02
5022.24	5	3	2.4E-01
5048.44	3	5	4.88E-02
5068.77	9	7	3.37E-02
5074.75	9	11	1.4E-01
5090.77	7	5	1.9E-01
5121.64	5	5	7.9E-02
5137.38	11	9	1.0E-01
5139.25	7	5	9.16E-02
5139.46	9	9	8.69E-02
5184.27	5	7	3.8E-02
5191.46	5	3	2.32E-01
5192.34	7	7	1.34E-01
5208.59	7	5	6.23E-02
5215.18	5	3	1.10E-01
5226.86	5	5	1.36E-01
5232.94	9	11	1.94E-01
5235.39	9	7	3.75E-02
5242.49	13	11	2.38E-02
5263.31	5	5	6.36E-02
5266.56	7	9	1.10E-01
5273.16	1	3	8.12E-02
5281.79	5	7	5.00E-02
5283.62	7	7	1.02E-01
5302.30	3	5	9.04E-02
5324.18	9	9	2.06E-01
5339.93	5	7	6.36E-02
5364.87	5	7	5.59E-01
5367.47	7	9	7.13E-01
5369.96	9	11	7.22E-01
5373.71	7	9	3.7E-02
5383.37	11	13	7.81E-01
5393.17	7	9	4.91E-02
5398.28	5	5	9.0E-02
5404.15	9	11	6.92E-01
5410.91	7	9	6.33E-01
5415.20	11	13	7.67E-01
5463.28	9	9	2.9E-01
5473.90	7	7	5.2E-02
5476.29	7	9	2.87E-02
5476.56	9	9	8.70E-02
5563.60	5	7	3.4E-02
5569.62	5	3	2.34E-01
5572.84	7	5	2.28E-01
5576.09	3	1	2.5E-01
5586.76	9	7	2.19E-01
5594.66	9	9	5.20E-02
5602.95	3	3	1.00E-01
5615.64	11	9	2.64E-01
5624.54	5	5	7.41E-02
5633.95	11	13	7.7E-02
5638.26	9	7	4.4E-02
5649.99	3	5	5.1E-02
5655.18	7	9	4.7E-02
5658.82	7	7	4.34E-02
5662.52	11	9	6.18E-02
5679.02	5	7	3.7E-02
5686.53	9	11	6.71E-02
5705.99	7	9	6.1E-02
5753.12	3	5	8.26E-02
5762.99	5	7	9.6E-02
5816.37	9	11	4.49E-02
5905.67	5	3	1.1E-01
6301.50	5	5	6.43E-02
6400.00	7	9	9.27E-02
6411.65	5	7	4.43E-02
6419.95	7	7	1.2E-01
6469.19	3	3	8.3E-02
6496.47	5	5	7.8E-02
6569.22	7	9	6.0E-02
6633.75	7	7	3.44E-02
6841.34	5	7	3.4E-02
6855.16	7	9	2.86E-02
7187.32	9	11	8.36E-02
7511.02	11	11	1.35E-01
8220.38	13	11	1.69E-01
8699.45	7	9	4.08E-02
9012.07	11	9	4.46E-02
9401.11	9	11	2.64E-02
9414.04	7	9	3.98E-02
9443.80	5	7	6.39E-02
9569.91	11	11	2.50E-02
9626.50	9	9	4.51E-02
9738.57	11	13	7.64E-02
9763.38	3	5	5.42E-02
9861.74	7	9	5.49E-02
9889.04	9	11	2.22E-02
22473.28	11	11	3.32E-02
23566.67	9	11	2.21E-02
24547.95	11	9	3.72E-02
24729.10	13	11	5.08E-02
Fe II			
1055.26	10	8	4.6E-01
1063.97	10	8	3.5E-01
1068.35	8	8	1.59E+00
1071.58	6	8	1.14E+00
1096.88	10	8	2.26E+00
1112.05	10	12	2.0E-01
1121.97	10	8	1.92E+00
1122.84	8	6	1.81E+00
1125.45	10	8	1.03E+00
1127.10	10	10	5.9E-02
1128.05	2	4	1.40E+00
1130.44	6	8	3.1E-01
1133.40	8	10	2.6E-01
1133.67	10	8	3.1E-01
1138.63	8	8	5.5E-01
1142.37	10	8	2.6E-01
1143.23	10	10	9.8E-01
1144.94	10	12	3.52E+00
1147.41	8	8	1.24E+00
1148.28	8	10	3.35E+00
1151.15	6	8	2.23E+00
1267.42	8	6	9.3E-01
1272.61	6	4	3.3E-01
1272.65	6	4	2.2E-01
1371.02	14	12	1.74E+00
1563.79	8	8	1.33E+00
1580.63	8	10	5.8E-01
1588.69	10	8	4.9E-03
1608.45	10	8	1.91E+00
1608.54	10	8	2.1E-02
1610.92	10	10	1.94E-01
1611.20	10	8	4.40E-02
1618.47	8	8	5.53E-01
1621.25	8	8	1.3E-02
1621.69	8	6	1.32E+00
1623.09	8	8	1.99E-01
1625.52	8	10	4.04E-01
1625.91	6	8	1.02E-01
1629.16	6	6	8.66E-01
1631.13	6	4	6.93E-01
1633.91	6	8	3.85E-01
1634.35	4	6	3.21E-01
1635.40	8	6	2.28E+00
1636.33	4	4	9.63E-01
1637.40	10	8	3.57E-01
1639.40	2	4	6.85E-01
1641.76	6	4	1.76E+00
1647.16	6	6	4.98E-01
1661.32	10	8	1.2E-02
1663.70	6	8	9.9E-03
1670.75	10	8	1.06E+00
1676.86	8	8	6.75E-02
1688.40	6	8	2.53E-02
1702.04	10	12	1.02E+00

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
1761.37	8	8	1.42E+00
1785.27	6	8	1.2E+01
1786.75	6	6	1.2E+01
1788.08	6	4	4.6E+00
1796.98	6	8	3.0E-03
1818.52	8	8	5.70E-02
1833.08	6	8	2.2E-02
1863.11	6	8	2.4E-03
2020.75	6	8	1.83E-01
2057.33	6	8	2.80E-02
2074.19	10	8	2.30E-02
2078.16	10	10	2.84E-02
2097.02	8	8	1.07E-02
2122.45	10	8	4.8E-03
2146.37	8	8	7.1E-03
2162.02	10	10	2.54E-01
2182.36	10	8	8.6E-02
2187.68	8	8	2.87E-02
2189.03	10	10	1.97E-02
2191.98	8	8	7.54E-01
2201.59	6	8	7.77E-01
2208.41	10	10	1.59E+00
2209.03	10	8	1.27E+00
2213.66	14	14	3.26E-01
2218.26	8	10	1.57E+00
2220.38	12	12	4.19E-01
2228.73	6	8	1.59E+00
2249.18	10	8	3.00E-02
2250.18	4	4	1.67E-02
2250.94	6	6	3.19E-02
2251.56	8	6	9.8E-03
2253.13	8	8	4.41E-02
2254.41	4	2	5.5E-03
2255.77	6	4	4.75E-01
2260.08	10	10	3.18E-02
2260.24	2	2	3.4E-02
2260.86	4	6	2.16E-02
2262.69	4	4	1.98E-02
2266.00	6	6	1.0E-02
2267.59	6	8	3.69E-02
2268.56	2	4	6.0E-03
2268.82	8	8	3.97E-03
2279.92	8	10	4.49E-02
2292.42	12	10	8.42E-03
2296.88	6	8	1.82E-02
2312.22	10	8	9.3E-03
2327.40	6	4	6.55E-01
2327.88	10	12	1.08E+00
2331.31	10	8	3.17E-01
2332.80	8	6	1.31E+00
2338.01	4	4	1.13E+00
2338.54	10	12	5.6E-02
2343.50	10	8	1.73E+00
2343.96	8	6	3.13E-01
2344.28	2	4	9.27E-01
2345.34	14	12	7.3E-01
2348.12	10	8	6.50E-01
2348.30	6	6	1.15E+00
2351.20	12	10	7.19E-01
2351.67	6	6	1.80E+00
2352.31	2	4	4.38E+00
2353.47	12	14	4.98E+00
2353.68	8	8	1.30E+00
2354.48	10	8	8.13E-01
2354.89	6	4	2.67E-01
2356.21	6	8	7.1E-03
2359.11	4	6	5.0E-01
2359.60	10	10	2.25E-01
2360.00	10	10	3.59E-01
2360.29	8	6	6.23E-01
2360.53	6	8	2.22E-01
2361.73	8	8	2.40E-01
2362.02	8	8	1.41E-01
2363.86	8	10	5.3E+00
2364.83	8	8	5.90E-01
2365.76	6	6	2.16E+00
2366.59	6	6	1.01E-01
2366.88	8	10	3.51E-02
2368.60	6	4	6.06E-01
2369.95	10	12	5.9E+00
2370.50	4	4	1.73E-01
2372.36	10	8	6.6E-03
2373.74	10	10	4.25E-01
2375.19	4	2	9.81E-01
2376.43	12	14	6.4E+00
2378.55	8	8	1.70E-01
2378.70	8	8	1.49E-01
2379.28	8	8	2.73E-01
2379.42	10	10	3.68E-01
2380.76	6	8	3.10E-01
2382.04	10	12	3.13E+00
2382.36	4	6	3.19E-02
2382.90	12	14	1.62E-01
2383.06	8	6	1.0E-01
2383.24	6	6	3.59E-01
2384.39	4	4	3.22E-01
2385.01	6	8	3.60E-02
2388.39	10	12	2.02E-01
2388.63	8	8	1.05E+00
2390.10	14	16	5.5E+00
2390.76	6	6	1.17E+00
2391.48	8	10	3.77E-02
2394.00	12	10	9.4E-02
2395.42	6	4	2.67E-01
2395.63	8	10	2.59E+00
2396.72	10	12	2.15E-01
2399.24	6	6	1.39E+00
2400.05	12	14	4.57E+00
2401.29	6	8	1.89E+00
2402.45	10	10	5.8E-01
2402.60	6	8	2.17E-02
2402.63	8	8	8.19E-01
2404.43	4	2	6.44E-01
2404.89	6	8	1.96E+00
2406.09	6	8	2.05E-02
2406.66	4	4	1.61E+00
2410.27	8	8	7.65E-01
2410.52	4	6	1.55E+00
2411.07	2	2	2.37E+00
2411.81	10	12	4.33E+00
2412.01	6	8	1.66E-01
2413.31	2	4	1.02E+00
2414.10	14	12	1.05E-02
2414.51	10	8	4.2E-03
2416.45	8	10	2.38E+00
2417.87	12	12	9.5E-01
2418.17	6	8	2.0E-02
2418.44	6	8	2.28E+00
2419.89	10	10	2.2E-02
2422.69	6	8	1.46E+00
2422.93	10	8	2.94E-02
2423.21	4	6	1.40E+00
2424.15	10	12	2.21E+00
2424.39	6	8	1.61E-01
2424.50	8	8	2.9E-03
2424.59	6	6	1.24E+00
2424.65	8	8	6.55E-02
2428.08	12	10	7.0E-03
2428.36	8	10	2.68E+00
2428.80	4	4	1.38E+00
2429.04	2	4	1.23E+00
2429.39	4	4	6.9E-01
2429.86	8	8	1.51E+00
2430.08	8	10	1.91E+00
2432.26	6	8	1.57E+00
2432.87	14	14	2.86E+00
2433.50	10	12	1.30E-01
2434.06	8	6	7.2E-01
2434.24	8	10	2.01E+00
2434.73	12	12	2.79E+00
2434.95	4	6	1.39E+00
2435.00	8	8	2.02E+00
2436.62	6	8	2.70E+00
2439.30	12	14	2.25E+00
2440.42	6	8	1.18E+00
2441.13	10	10	8.95E-01
2442.38	10	12	2.75E+00
2443.71	8	10	1.44E+00
2444.52	6	8	2.78E+00
2445.11	12	12	2.03E+00
2445.57	4	6	2.07E+00
2445.80	4	6	1.23E+00
2446.11	8	8	1.06E+00
2446.47	12	14	2.99E-01
2447.21	6	6	1.15E+00
2447.33	4	2	2.56E+00
2447.76	12	10	1.97E+00
2449.96	4	4	1.24E+00
2450.21	2	4	1.26E+00
2453.98	8	10	1.31E+00
2454.58	14	12	1.16E+00
2455.71	8	8	1.01E+00
2455.90	4	6	1.73E+00
2457.10	6	4	4.71E-01
2458.78	10	12	2.31E+00
2458.97	6	4	2.51E+00
2460.44	10	12	5.39E+00
2461.28	6	8	2.34E+00
2461.86	8	10	2.43E+00
2463.28	12	10	7.1E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
2464.01	10	8	1.32E+00
2464.91	6	4	2.22E+00
2465.91	8	6	1.62E+00
2466.50	2	4	2.40E+00
2466.67	4	2	2.64E+00
2466.82	6	4	1.77E+00
2468.30	10	10	9.8E-02
2469.37	10	8	2.23E-02
2469.52	8	6	2.58E+00
2470.41	6	6	6.0E-01
2470.67	8	6	1.54E+00
2470.85	8	8	5.4E-03
2471.28	10	8	4.15E-01
2472.61	8	10	3.22E+00
2473.32	2	2	2.74E+00
2475.12	4	6	3.72E+00
2475.54	6	8	3.18E+00
2476.27	8	10	9.7E-02
2477.35	8	8	1.70E-01
2478.57	6	6	9.1E-01
2480.16	10	8	1.55E+00
2481.05	12	12	1.46E-01
2482.12	14	14	6.5E-01
2482.33	4	4	2.23E+00
2482.66	12	10	1.25E+00
2482.87	6	4	1.69E+00
2483.72	8	10	5.4E-01
2484.24	4	6	8.3E-02
2484.44	8	8	2.16E+00
2489.11	4	4	2.6E-02
2489.48	12	12	5.1E-01
2489.83	12	12	1.94E+00
2490.71	10	12	1.44E+00
2490.86	8	8	8.8E-01
2491.40	10	8	1.01E+00
2492.34	10	12	2.30E-01
2493.26	14	16	3.04E+00
2493.88	6	6	1.74E+00
2494.12	12	10	2.97E-02
2497.68	10	12	8.4E-03
2497.82	6	6	1.68E+00
2500.92	6	8	2.41E+00
2501.35	2	2	1.48E+00
2502.39	8	8	1.43E+00
2503.33	12	12	7.3E-01
2503.54	8	8	3.32E-01
2503.57	10	10	2.53E-01
2503.88	10	10	2.23E+00
2506.09	10	10	9.9E-01
2506.80	8	10	1.98E+00
2508.34	8	10	3.79E-01
2510.57	8	8	1.54E-01
2511.76	8	10	2.30E+00
2513.15	10	8	2.49E-01
2514.38	8	8	2.11E+00
2517.14	2	4	9.2E-01
2519.05	8	6	2.10E+00
2521.09	6	4	2.05E+00
2521.82	8	8	2.36E+00
2525.39	14	14	1.91E+00
2525.92	8	8	7.4E-01
2526.08	10	8	3.52E-01
2526.29	6	6	2.47E+00
2527.10	12	10	3.67E-01
2527.71	10	8	9.1E-01
2528.68	10	8	2.3E-02
2529.08	4	6	1.80E+00
2529.23	12	10	3.27E-01
2529.55	10	10	2.20E+00
2530.10	4	6	6.6E-01
2533.63	12	12	1.92E+00
2534.42	8	8	1.83E+00
2535.36	6	4	2.46E+00
2535.49	10	8	7.47E-01
2536.67	12	12	5.7E-01
2536.81	10	10	1.69E+00
2536.84	12	14	6.8E-01
2537.14	10	10	1.44E+00
2538.21	14	12	1.26E+00
2538.40	6	8	3.7E-02
2538.50	8	6	5.9E-01
2538.68	6	8	7.4E-01
2538.91	10	8	1.28E+00
2538.99	14	12	1.93E+00
2539.81	8	8	5.6E-02
2540.52	2	2	1.26E+00
2540.66	6	8	1.70E+00
2541.10	8	6	9.6E-01
2541.84	8	6	8.2E-01
2542.32	4	2	3.9E-03
2542.74	2	2	1.61E+00
2543.38	10	12	6.7E-01
2543.43	6	4	8.3E-01
2544.97	4	6	3.93E-01
2545.22	8	10	5.3E-01
2545.44	8	10	1.52E-01
2545.53	8	10	1.2E-02
2546.67	8	8	7.98E-01
2547.34	8	8	2.28E-01
2548.16	6	8	8.0E-03
2548.32	4	6	2.69E-01
2548.59	10	10	2.67E-01
2548.74	4	2	2.43E+00
2548.92	12	10	6.0E-01
2549.08	10	8	1.89E+00
2549.40	4	4	1.65E+00
2549.46	6	6	1.12E+00
2549.77	8	6	2.35E-01
2550.03	10	10	1.74E+00
2550.15	8	10	3.91E-01
2550.57	12	12	1.6E-02
2550.68	12	12	1.07E+00
2551.20	10	8	2.48E-01
2554.94	8	8	2.6E-02
2555.07	6	8	1.96E-01
2555.45	4	6	2.49E-01
2557.08	8	10	2.8E-02
2557.51	10	8	1.53E-01
2559.24	8	8	6.4E-02
2559.77	6	8	2.42E-01
2559.93	6	8	2.47E-01
2560.28	4	4	1.77E+00
2561.59	10	10	1.1E-02
2562.09	4	2	1.62E+00
2562.54	8	6	1.79E+00
2563.48	6	4	1.51E+00
2566.22	8	10	2.61E+00
2566.40	8	6	2.29E+00
2566.62	10	12	7.1E-02
2566.91	4	2	1.15E+00
2568.41	2	4	4.77E-01
2568.89	8	8	2.8E-02
2569.78	2	4	1.11E+00
2570.55	6	8	1.1E-03
2570.85	8	6	1.84E+00
2571.55	10	10	2.89E-02
2572.97	6	8	7.89E-02
2573.21	8	10	1.42E-01
2573.76	8	8	2.3E-02
2574.37	6	4	2.43E+00
2576.86	10	12	1.32E+00
2577.43	6	8	7.8E-03
2577.92	2	2	1.24E+00
2580.72	8	6	2.2E-02
2581.11	6	6	7.61E-02
2582.41	6	8	2.22E-01
2582.58	4	4	8.80E-01
2583.05	8	10	2.16E-02
2583.35	8	10	9.0E-03
2585.62	10	10	3.09E-01
2585.88	10	8	8.94E-01
2586.06	6	4	5.8E-02
2587.95	8	10	1.69E+00
2588.19	2	2	1.5E-01
2588.80	8	8	8.4E-02
2590.55	4	6	7.9E-02
2591.54	6	6	5.72E-01
2592.79	14	16	2.74E+00
2593.73	2	4	1.63E-01
2594.96	8	8	1.0E-01
2595.28	12	10	1.67E-03
2595.30	10	8	1.2E-02
2598.37	8	6	1.43E+00
2599.40	10	10	2.35E+00
2604.05	8	8	1.49E-01
2604.67	8	10	1.2E-02
2605.04	6	8	2.34E+00
2605.31	4	4	1.99E+00
2605.43	6	6	3.40E-01
2605.90	4	2	1.27E+00
2606.52	6	6	2.31E+00
2607.09	6	4	1.73E+00
2608.85	10	8	5.0E-02
2609.13	8	10	2.77E-01
2609.44	6	8	6.0E-02
2609.87	8	8	1.34E-01
2611.07	4	6	7.28E-02
2611.34	8	6	1.4E-02
2611.87	8	8	1.20E+00
2613.57	10	12	2.0E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
2613.82	4	2	2.12E+00
2614.19	8	10	3.3E-02
2614.59	10	8	3.37E-02
2614.87	8	6	3.5E-02
2617.62	6	6	4.88E-01
2619.08	10	10	2.48E-01
2620.17	6	6	1.1E-01
2620.41	4	4	4.30E-02
2620.70	8	8	3.43E-01
2621.67	2	2	5.60E-01
2623.13	14	14	8.8E-02
2623.72	6	6	1.92E-01
2625.49	12	14	2.55E+00
2625.67	8	10	3.52E-01
2626.50	4	6	3.48E-01
2626.70	8	8	1.94E-02
2628.29	2	4	8.74E-01
2628.58	6	6	3.4E-02
2629.59	6	8	7.2E-01
2630.07	4	6	5.1E-01
2631.05	4	6	8.16E-01
2631.32	6	8	6.29E-01
2631.61	10	12	6.6E-01
2633.20	6	4	1.21E+00
2636.70	4	4	8.8E-02
2637.50	6	6	6.2E-01
2637.64	2	4	6.6E-01
2639.57	2	2	8.0E-01
2641.12	4	4	3.7E-02
2642.01	6	6	2.29E-01
2646.21	12	10	1.44E-02
2649.47	6	8	1.98E+00
2650.48	6	8	1.60E+00
2651.30	12	12	4.0E-03
2652.57	10	8	4.45E-02
2654.63	4	4	8.1E-01
2657.92	10	10	3.2E-02
2658.25	8	8	2.12E-01
2659.06	10	10	2.5E-03
2662.56	2	2	1.33E+00
2664.66	8	10	1.91E+00
2666.64	6	8	1.87E+00
2667.22	4	6	1.02E+00
2669.93	2	4	5.2E-01
2670.38	6	8	6.0E-02
2671.39	2	4	6.5E-01
2680.23	6	8	1.10E-01
2682.51	8	10	9.2E-01
2683.00	4	6	7.3E-01
2684.75	8	10	1.57E+00
2684.96	12	12	6.4E-03
2686.11	6	6	9.4E-03
2686.39	6	4	1.6E-02
2691.74	10	8	5.04E-02
2692.60	10	12	1.40E+00
2692.83	8	6	1.64E-02
2693.86	8	6	4.2E-02
2697.33	4	4	2.48E-01
2697.46	4	2	1.65E+00
2697.73	10	8	2.6E-02
2699.20	4	4	6.2E-01
2703.99	8	8	1.38E+00
2704.58	8	8	1.66E-02
2707.13	4	6	8.3E-01
2709.06	4	6	3.88E-01
2709.38	6	4	2.78E-03
2709.99	6	8	8.7E-03
2711.84	12	14	4.36E-01
2712.39	10	12	1.29E-01
2714.41	8	6	5.70E-01
2716.22	6	6	1.15E+00
2716.44	6	6	2.8E-02
2716.57	14	12	1.35E+00
2716.70	8	8	1.02E-03
2717.88	16	14	1.51E+00
2718.64	10	8	1.18E+00
2719.30	6	8	4.44E-01
2721.81	12	10	5.1E-02
2722.06	8	8	1.42E-01
2722.74	6	8	8.2E-01
2724.88	6	6	9.58E-02
2726.52	6	8	5.0E-02
2727.38	12	10	3.12E-01
2727.54	6	4	9.38E-01
2728.91	8	10	1.25E-01
2730.73	4	4	2.79E-01
2732.01	10	8	7.05E-02
2732.45	10	10	9.8E-04
2732.94	8	6	9.5E-01
2736.49	2	4	1.5E-02
2736.97	4	2	1.22E+00
2739.55	8	8	2.21E+00
2741.39	6	6	2.03E-01
2743.20	2	4	1.97E+00
2744.90	6	8	3.62E-02
2746.48	4	6	2.05E+00
2746.98	6	6	1.69E+00
2749.18	4	4	1.21E+00
2749.32	6	8	2.16E+00
2749.49	2	2	1.16E+00
2750.01	10	10	1.8E-02
2751.13	4	4	2.92E-01
2752.15	4	4	7.7E-01
2753.29	10	12	1.89E+00
2754.89	8	6	1.21E+00
2755.74	8	10	2.15E+00
2756.51	6	8	7.3E-02
2757.03	10	8	8.07E-02
2759.33	8	8	2.7E-04
2761.81	2	4	1.38E-01
2762.33	6	6	6.0E-01
2762.45	6	4	3.3E-02
2763.66	14	12	1.34E+00
2763.91	8	6	2.9E-02
2764.79	12	12	1.1E-02
2765.13	10	8	1.47E+00
2767.50	12	14	1.58E+00
2768.93	4	6	4.75E-02
2769.15	8	10	6.6E-02
2769.35	12	14	2.07E-01
2770.50	12	10	4.08E-02
2771.19	10	12	4.3E-02
2771.56	6	4	1.9E-02
2772.73	6	8	1.1E-03
2774.69	2	4	2.73E-01
2775.34	6	6	1.5E-04
2776.18	6	8	2.66E-02
2776.91	8	8	4.08E-01
2779.30	10	8	1.00E+00
2779.91	2	4	2.56E-01
2780.05	2	2	3.3E-01
2783.69	12	10	1.06E+00
2784.28	2	4	3.4E-02
2785.19	12	10	1.53E+00
2787.24	8	6	1.83E-01
2790.56	8	10	2.1E-02
2793.89	10	12	1.26E-01
2796.63	10	10	2.0E-01
2797.92	10	10	3.2E-02
2799.29	10	8	1.55E-01
2799.72	10	10	5.0E-03
2804.02	6	6	1.6E-02
2805.32	4	6	2.5E-02
2805.79	8	8	3.22E-02
2809.78	8	8	3.10E-01
2811.27	12	10	1.2E-02
2812.49	4	4	2.9E-02
2813.61	8	10	3.40E-02
2817.09	6	4	3.37E-01
2819.34	12	12	9.7E-03
2826.03	8	6	4.5E-02
2827.43	12	14	2.4E-02
2828.63	12	10	6.9E-02
2831.56	4	6	7.6E-01
2833.09	6	6	4.55E-01
2835.71	4	6	5.1E-01
2836.19	4	4	5.4E-02
2836.51	2	4	9.8E-02
2837.30	10	12	1.9E-02
2838.22	4	2	8.6E-01
2839.51	10	8	1.47E+00
2839.80	8	10	5.8E-01
2840.34	12	12	7.7E-02
2840.65	2	4	7.6E-01
2840.76	10	12	1.49E-01
2841.36	10	10	4.3E-03
2842.08	8	8	1.5E-02
2843.32	10	10	1.40E-02
2843.48	4	6	9.6E-02
2844.96	2	2	5.5E-01
2845.60	8	6	1.57E+00
2847.21	8	6	1.7E-04
2847.77	4	4	5.1E-01
2848.11	6	6	9.9E-01
2848.32	6	4	1.59E+00
2848.91	12	10	5.3E-02
2849.61	10	12	4.6E-02
2852.87	2	4	1.65E-02
2853.21	6	6	2.3E-02
2855.67	8	10	9.2E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
2856.15	10	10	5.0E-02
2856.38	6	8	4.42E-01
2856.91	8	8	1.32E+00
2857.17	6	8	1.22E-01
2857.42	6	6	2.0E-02
2858.34	10	12	4.85E-01
2861.17	4	4	1.7E-03
2864.97	8	8	4.3E-02
2868.87	6	6	7.3E-03
2869.16	8	10	1.4E-02
2869.31	4	6	4.04E-01
2869.70	8	6	1.1E-02
2870.61	8	10	7.5E-03
2871.06	10	12	2.2E-02
2871.13	12	10	3.0E-02
2872.38	10	8	1.70E-01
2873.40	8	10	4.56E-01
2875.35	8	10	1.35E-01
2876.80	8	8	9.56E-02
2879.25	10	8	3.6E-02
2880.76	8	8	2.21E-02
2883.71	12	14	1.48E-01
2884.76	6	8	2.46E-01
2885.93	14	12	3.8E-02
2886.24	12	10	6.9E-03
2887.31	6	4	1.9E-02
2888.10	4	6	6.1E-02
2892.83	4	6	1.8E-03
2894.78	10	12	5.7E-02
2895.22	8	10	1.09E-01
2897.27	6	4	1.8E-01
2902.32	6	8	8.81E-03
2902.46	10	10	3.2E-02
2906.12	2	4	4.4E-02
2907.86	8	6	1.3E-03
2910.76	8	8	1.5E-02
2916.15	8	8	4.8E-04
2917.08	6	8	2.7E-02
2917.47	6	8	1.4E-03
2922.02	8	10	3.8E-02
2926.59	8	10	5.1E-02
2934.49	8	10	5.6E-03
2939.51	6	4	4.0E-03
2944.40	4	2	3.5E-01
2945.26	6	6	5.6E-04
2947.65	6	4	2.01E-01
2949.18	10	8	2.45E-01
2953.77	6	8	5.2E-02
2954.05	8	8	1.2E-02
2959.60	8	6	9.7E-02
2959.84	8	6	1.36E-01
2961.28	4	2	8.9E-03
2964.13	8	6	4.6E-02
2964.62	2	2	6.5E-02
2965.03	4	4	9.43E-02
2965.41	6	4	1.1E-02
2968.74	8	10	2.4E-03
2969.94	8	6	2.28E-01
2970.52	4	6	2.70E-02
2970.69	10	8	4.15E-02
2975.94	2	2	9.1E-03
2978.85	10	10	7.2E-03
2979.35	2	4	1.61E-02
2980.96	6	8	1.1E-02
2982.06	4	6	2.41E-01
2984.82	6	6	4.29E-01
2985.54	2	4	2.39E-01
2997.30	6	8	8.6E-02
2998.85	6	8	4.2E-03
3000.06	8	6	3.0E-02
3002.32	6	8	2.0E-02
3002.65	4	6	1.79E-01
3004.26	8	8	8.6E-03
3020.01	12	10	6.4E-04
3021.42	8	6	3.8E-03
3036.96	6	6	2.22E-01
3044.84	8	10	1.2E-02
3048.99	4	4	3.84E-01
3056.80	14	12	1.7E-02
3062.24	12	10	1.36E-01
3065.32	6	6	2.9E-02
3070.69	10	8	1.28E-02
3071.12	2	4	2.59E-01
3076.44	4	6	3.75E-01
3077.17	14	12	1.35E-01
3078.68	6	8	5.5E-01
3089.38	6	8	2.2E-02
3096.29	8	8	1.9E-02
3101.89	6	8	9.1E-03
3105.17	4	2	7.5E-02
3105.55	2	2	7.0E-02
3106.57	8	8	1.88E-02
3114.30	4	4	6.4E-02
3114.69	2	4	2.5E-02
3116.58	6	4	5.5E-02
3129.01	8	10	2.3E-03
3131.72	12	10	6.6E-03
3133.05	4	6	1.5E-02
3135.36	6	6	8.8E-02
3144.75	8	6	2.7E-02
3146.75	10	10	4.9E-06
3154.20	10	10	2.06E-01
3155.95	10	8	4.17E-03
3162.80	8	8	5.5E-02
3163.09	6	6	1.92E-03
3166.67	6	4	1.4E-03
3167.86	8	8	1.59E-01
3170.34	4	2	8.2E-03
3177.53	8	8	1.74E-01
3179.50	6	8	1.11E-01
3180.15	4	6	7.7E-02
3183.11	4	6	9.80E-03
3185.32	2	4	3.00E-03
3186.74	4	4	3.85E-02
3187.30	10	10	5.0E-02
3192.07	8	10	5.2E-03
3192.91	6	6	1.27E-02
3193.80	2	2	5.4E-02
3193.86	8	8	3.86E-02
3196.07	6	8	1.61E-02
3210.44	2	4	3.63E-02
3211.08	6	8	2.1E-03
3213.31	4	6	6.12E-02
3227.74	6	8	8.9E-02
3231.71	6	8	1.4E-02
3232.78	8	6	5.0E-02
3237.40	4	4	1.8E-02
3237.82	2	4	6.8E-02
3241.69	8	8	1.9E-03
3243.72	10	8	5.1E-02
3247.17	4	6	7.1E-02
3247.39	8	8	6.0E-03
3255.89	8	8	2.78E-03
3257.36	8	6	1.5E-03
3258.77	6	8	9.39E-02
3259.05	8	10	6.7E-02
3266.94	10	10	4.5E-03
3267.04	8	10	2.0E-04
3268.51	8	6	6.8E-03
3269.77	10	8	5.2E-03
3273.49	8	8	8.5E-03
3276.60	6	8	1.0E-02
3277.35	8	10	3.31E-03
3279.64	10	10	5.8E-03
3281.29	6	6	2.31E-03
3285.41	4	2	4.5E-04
3289.35	8	8	2.1E-02
3295.23	6	8	3.6E-03
3295.82	4	4	2.04E-03
3297.88	6	4	1.0E-02
3302.86	6	8	2.78E-04
3303.46	2	2	6.5E-04
3304.43	6	8	2.0E-03
3313.99	2	4	1.4E-04
3323.06	8	10	1.4E-02
3325.01	8	8	3.35E-03
3360.11	12	12	2.1E-03
3366.97	8	6	2.2E-02
3381.01	6	4	3.0E-02
3388.14	8	10	3.8E-04
3395.33	8	8	3.66E-03
3398.36	14	14	2.5E-03
3416.02	4	2	2.6E-03
3425.57	6	8	2.1E-04
3436.11	8	6	5.7E-03
3442.22	8	6	3.2E-03
3453.62	8	10	8.5E-03
3456.92	8	6	7.1E-03
3463.96	6	6	7.6E-05
3464.50	10	8	2.2E-03
3468.68	8	8	2.0E-02
3475.74	6	8	1.7E-04
3487.99	4	6	1.7E-04
3493.47	10	10	3.2E-02
3494.67	4	6	7.1E-04
3495.62	10	8	2.62E-03
3499.88	8	8	4.29E-03
3503.47	2	2	2.6E-04
3507.40	2	4	4.1E-04
3508.20	2	4	1.2E-04

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3614.88	8	8	4.2E-03
3621.27	2	4	2.2E-02
3624.89	2	2	2.4E-02
3632.29	10	10	1.2E-03
3711.98	4	6	1.5E-03
3748.48	6	4	3.4E-02
3759.46	4	2	3.2E-02
3814.12	4	6	4.9E-03
3824.93	6	6	3.2E-05
3827.08	6	8	2.5E-03
3906.04	6	8	1.1E-02
3914.50	6	4	4.6E-05
3935.96	8	10	8.3E-03
3938.29	6	6	6.1E-05
3938.97	4	6	8.4E-03
3945.21	4	4	3.9E-05
3974.17	4	6	6.3E-05
4024.55	6	6	2.5E-03
4075.95	6	4	1.6E-05
4087.28	6	4	3.0E-05
4122.67	6	6	3.3E-04
4124.79	6	8	3.4E-05
4128.75	6	4	2.6E-04
4173.46	6	6	4.43E-03
4178.86	6	8	1.72E-03
4180.98	4	4	2.2E-04
4233.17	6	8	7.22E-03
4258.15	4	4	3.1E-04
4273.33	4	2	9.1E-04
4296.57	4	6	7.0E-04
4303.18	4	4	2.20E-03
4351.77	4	6	4.86E-03
4369.41	2	4	2.3E-04
4384.32	12	10	7.2E-05
4385.39	2	2	4.5E-03
4413.60	10	10	2.2E-05
4416.83	2	4	2.1E-03
4472.93	6	4	2.5E-04
4489.18	8	6	5.9E-04
4491.41	4	4	1.89E-03
4508.29	4	2	7.3E-03
4515.34	6	6	2.37E-03
4520.22	10	8	9.8E-04
4522.63	6	4	8.4E-03
4534.17	4	6	2.3E-04
4541.52	4	4	8.6E-04
4549.19	4	6	9.2E-03
4549.47	8	6	1.00E-02
4555.89	8	8	2.26E-03
4576.34	6	6	6.4E-04
4582.84	6	8	3.44E-04
4583.84	10	8	7.22E-03
4620.52	8	8	2.53E-04
4629.34	10	10	1.72E-03
4635.32	6	8	1.0E-02
4656.98	6	6	1.37E-04
4666.76	8	10	1.3E-04
4670.18	6	8	3.2E-05
4720.15	4	6	7.5E-06
4731.45	6	8	2.8E-04
4833.20	12	10	4.6E-06
4840.00	10	8	4.0E-06
4893.82	8	6	2.5E-05
4923.93	6	4	4.28E-02
4990.51	6	8	5.2E-01
4993.36	10	8	6.9E-05
5000.74	2	4	1.8E-05
5001.96	12	14	1.57E+00
5018.44	6	6	2.0E-02
5030.63	10	10	7.1E-01
5035.71	10	12	9.4E-01
5100.66	10	8	2.0E-05
5132.67	10	10	2.0E-05
5136.80	6	4	2.8E-05
5144.35	4	6	8.5E-01
5149.47	8	10	9.0E-01
5169.03	6	8	4.22E-02
5197.58	6	4	5.4E-03
5227.48	12	14	1.22E+00
5234.62	8	6	2.5E-03
5247.95	4	6	1.43E+00
5251.23	6	8	8.0E-01
5262.48	4	6	8.0E-07
5264.18	8	10	4.76E-01
5264.81	6	4	3.52E-04
5272.40	6	6	3.9E-03
5276.00	10	8	3.76E-03
5284.11	6	8	1.9E-04
5306.18	6	8	3.28E-01
5316.22	14	14	3.69E-01
5316.62	12	10	3.89E-03
5316.78	8	6	6.5E-04
5325.55	8	8	8.0E-04
5387.06	12	14	5.2E-01
5395.86	6	8	5.5E-01
5402.06	10	12	5.6E-01
5414.07	8	8	9.4E-05
5425.26	10	10	9.2E-05
5427.83	12	10	5.9E-03
5429.99	8	10	6.0E-01
5465.93	6	8	6.2E-01
5482.31	10	12	4.78E-01
5493.83	8	10	4.01E-01
5506.19	12	14	1.14E+00
5510.78	10	12	2.28E-01
5525.12	10	8	3.17E-05
5529.05	6	6	2.01E-01
5534.85	12	10	3.0E-04
5544.76	12	12	2.49E-01
5607.14	6	8	4.63E-05
5627.50	8	6	2.93E-05
5725.96	6	6	5.1E-06
5783.63	8	10	4.62E-01
5813.68	6	4	8.8E-04
5823.15	8	10	2.0E-04
5824.41	6	6	8.3E-07
5885.01	4	6	6.4E-01
5902.83	8	10	4.98E-01
5955.70	6	8	4.19E-01
5961.71	10	12	7.4E-01
5965.62	10	10	2.19E-01
5991.38	12	10	4.2E-05
6084.11	10	8	3.0E-05
6113.32	8	6	1.7E-05
6129.70	10	10	3.2E-06
6147.74	4	2	1.3E-03
6149.26	2	2	1.3E-03
6175.15	8	8	1.8E-03
6179.38	8	6	4.6E-04
6238.39	4	4	7.5E-04
6239.95	2	4	1.1E-04
6247.56	6	4	1.6E-03
6305.30	10	10	1.4E-03
6331.95	6	8	1.8E-03
6369.46	6	4	1.40E-04
6383.72	6	6	1.1E-03
6416.92	6	6	3.6E-04
6432.68	6	6	8.5E-05
6446.41	8	10	1.3E-03
6456.38	8	6	1.7E-03
6516.08	6	8	8.3E-05
7222.39	4	2	2.5E-04
7224.49	2	2	2.8E-04
7301.56	6	6	2.1E-05
7320.65	6	4	1.4E-04
7449.33	4	6	1.68E-04
7462.41	6	6	2.7E-04
7479.69	6	8	3.5E-05
7515.83	8	6	8.1E-05
7711.72	8	8	4.94E-04
Fe III			
1843.4	9	7	4.8E+00
1844.3	7	5	4.9E+00
1846.9	5	3	5.5E+00
1854.38	3	1	5.7E+00
1865.20	7	7	6.1E+00
1893.98	11	9	5.5E+00
1896.80	13	11	5.0E+00
1904.3	5	5	5.7E+00
1907.58	15	13	5.3E+00
1915.08	13	15	6.0E+00
1922.79	11	13	5.5E+00
1930.39	9	11	5.1E+00
1931.51	9	11	5.3E+00
1937.35	7	9	5.1E+00
1943.48	5	7	5.0E+00
1950.33	13	15	5.5E+00
1951.01	11	11	5.3E+00
1952.65	9	9	4.9E+00
1953.32	7	7	5.1E+00
1987.50	13	13	4.9E+00
Fe VII			
150.807	5	7	1.3E+03
150.852	7	9	1.3E+03
151.023	9	11	1.6E+03
151.046	7	7	2.2E+02
151.145	9	9	2.1E+02
151.432	5	7	2.2E+02
151.512	5	5	5.3E+02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
151.675	7	7	3.9E+02
151.782	9	9	2.4E+02
154.307	3	1	8.9E+02
154.335	5	7	1.2E+03
154.363	3	3	4.2E+02
154.565	5	3	3.5E+02
154.650	5	5	8.8E+02
154.848	1	3	7.7E+02
154.921	3	5	9.7E+02
154.941	3	3	2.4E+02
154.949	5	7	1.0E+03
155.994	9	11	1.8E+03
158.481	9	9	2.3E+02
165.087	1	3	6.9E+02
165.919	7	5	2.8E+03
166.365	9	7	2.9E+03
173.441	9	9	3.6E+03
176.744	9	9	2.7E+03
176.928	7	7	2.4E+03
177.172	5	5	1.5E+03
235.221	5	3	1.7E+02
240.053	3	1	1.3E+02
243.379	9	7	2.1E+02
Fe VIII			
112.472	4	4	3.6E+02
112.486	6	6	4.3E+02
116.196	4	6	4.5E+02
117.197	6	8	3.8E+02
167.486	4	4	3.0E+03
168.172	6	6	3.1E+03
168.545	6	4	2.0E+03
168.929	4	2	2.1E+03
185.213	6	8	1.0E+03
186.601	4	6	9.4E+02
Fe X			
76.822	2	2	1.8E+03
77.865	4	6	1.6E+03
100.026	8	10	2.6E+03
101.733	6	8	1.8E+03
101.846	4	6	1.7E+03
102.095	10	12	2.9E+03
102.192	10	12	2.9E+03
102.829	4	6	2.1E+03
103.319	6	8	2.6E+03
103.724	6	8	1.7E+03
104.638	8	10	2.1E+03
174.534	4	6	1.8E+03
175.266	2	4	1.72E+03
Fe XI			
72.166	5	7	2.9E+03
72.310	5	5	1.5E+03
72.635	5	7	1.6E+03
91.394	5	7	2.6E+03
91.472	7	9	2.5E+03
91.63	3	5	2.3E+03
91.63	7	9	3.4E+03
91.63	5	7	2.8E+03
91.733	9	11	4.1E+03
92.81	9	11	3.7E+03
92.87	11	13	3.9E+03
93.433	9	11	3.2E+03
179.762	5	7	1.67E+03
Fe XII			
65.905	4	4	2.0E+03
66.526	6	8	1.7E+03
66.960	4	6	1.6E+03
67.164	4	2	1.1E+03
67.821	4	6	1.4E+03
68.382	2	4	1.7E+03
80.541	6	6	8.7E+02
81.943	6	4	1.4E+03
82.226	4	2	1.9E+03
84.48	4	6	4.5E+03
84.48	8	10	4.9E+03
84.52	10	12	5.2E+03
84.52	6	8	4.0E+03
84.85	6	8	2.3E+03
85.14	8	10	3.4E+03
85.477	10	12	4.6E+03
186.880	6	8	1.0E+03
192.394	4	2	9.0E+02
193.509	4	4	9.1E+02
195.119	4	6	8.6E+02
Fe XIII			
62.353	1	3	2.0E+03
62.46	5	7	1.2E+03
62.699	3	5	2.3E+03
63.188	5	7	3.9E+03
64.139	1	3	2.1E+03
74.845	5	5	1.0E+03
75.892	5	3	7.7E+02
76.117	5	3	2.1E+03
78.452	9	11	6.3E+03
84.270	7	9	5.5E+03
107.384	7	5	1.8E+03
Fe XIV			
58.963	2	4	2.7E+03
59.579	4	6	3.1E+03
69.176	4	6	5.6E+02
69.386	2	4	7.6E+02
69.66	2	2	8.9E+02
69.66	6	6	1.3E+03
70.251	6	4	8.1E+02
70.613	4	2	1.7E+03
72.80	10	12	7.9E+03
76.022	4	6	6.6E+03
76.152	6	8	7.0E+03
91.009	6	4	5.1E+02
91.273	4	2	5.6E+02
188	4	6	2.7E+02
190	6	8	2.8E+02
207	2	2	2.1E+02
211.316	2	4	3.6E+02
213	4	2	2.8E+02
214	2	2	4.0E+02
216	6	8	1.7E+02
217	6	8	4.0E+02
217	6	6	2.6E+02
219	2	4	4.8E+02
219	4	6	2.4E+02
219.123	4	6	3.9E+02
220	4	4	3.2E+02
221	4	6	5.9E+02
226	2	4	3.9E+02
234	2	2	2.8E+02
264.787	4	4	3.38E+02
265	4	4	1.5E+02
266	6	4	1.7E+02
268	6	6	2.1E+02
268	4	2	3.3E+02
270.524	4	2	2.1E+02
274.203	2	2	1.8E+02
280	4	6	2.8E+02
283	6	8	2.7E+02
288.45	6	4	1.6E+02
Fe XV			
38.95	1	3	1.69E+03
52.911	1	3	2.94E+03
59.404	3	5	3.4E+03
63.959	5	7	1.6E+03
65.370	1	3	3.2E+02
65.612	3	3	9.8E+02
66.238	5	3	1.6E+03
68.860	9	11	9.2E+03
69.7	3	1	1.9E+03
69.942	3	5	7.4E+03
69.989	5	7	7.9E+03
70.052	7	9	8.8E+03
70.224	1	3	4.13E+03
70.53	7	5	2.6E+02
70.59	7	7	1.7E+03
73.199	7	9	8.8E+03
73.473	5	7	6.2E+03
233.857	5	7	2.2E+02
235	1	3	2.5E+02
243	1	3	2.4E+02
243	5	7	2.3E+02
243.790	3	5	4.2E+02
248	3	1	5.4E+02
284.160	1	3	2.28E+02
Fe XVI			
31.041	2	4	5.2E+02
31.242	4	6	6.1E+02
32.166	2	4	6.8E+02
32.192	2	2	6.7E+02
32.433	2	4	7.7E+02
32.652	4	6	9.1E+02
34.857	2	4	1.23E+03
35.106	4	6	1.44E+03
35.333	4	6	6.4E+02
35.368	6	8	6.8E+02
36.01	4	2	5.0E+02
36.749	2	4	1.1E+03
36.803	2	2	1.2E+03
37.096	4	6	1.0E+03

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
37.138	6	8	1.07E+03
39.827	2	4	2.1E+03
40.153	4	6	2.5E+03
40.161	4	4	4.1E+02
40.199	4	6	1.7E+03
40.245	6	8	1.8E+03
41.91	2	2	4.72E+02
42.30	4	2	9.2E+02
46.661	4	6	3.46E+03
46.718	6	8	3.7E+03
50.350	2	4	1.86E+03
50.555	2	2	1.98E+03
54.142	2	4	3.41E+03
54.728	4	6	4.16E+03
54.769	4	4	6.97E+02
62.879	2	2	1.05E+03
63.719	4	2	2.18E+03
66.263	4	6	9.39E+03
66.368	6	8	1.00E+04
66.392	6	6	6.69E+02
76.502	6	4	6.7E+02
76.796	4	2	7.72E+02
80.192	4	6	5.2E+02
80.270	6	8	5.4E+02
85.587	2	4	4.0E+02
86.133	4	6	4.8E+02
96.256	4	6	8.7E+02
96.348	6	8	9.3E+02
117.2	2	4	3.93E+02
117.7	2	2	3.9E+02
123.4	2	4	5.9E+02
124.5	4	6	7.0E+02
144.06	4	6	1.6E+03
144.25	6	8	1.6E+03
148	4	2	6.5E+02
266.7	4	6	3.9E+02
267.0	6	8	4.3E+02
Fe XVII			
11.023	1	3	2.1E+04
12.123	1	3	8.0E+04
12.264	1	3	5.9E+04
12.526	1	3	3.0E+03
12.681	1	3	3.5E+03
13.823	1	3	3.3E+04
13.891	1	3	3.4E+03
15.015	1	3	2.28E+05
15.262	1	3	6.0E+04
16.777	1	3	8.29E+03
17.054	1	3	9.33E+03
41.37	9	11	4.8E+03
49.427	3	3	4.0E+03
50.26	7	9	6.0E+03
58.76	9	11	1.2E+04
Fe XIX			
13.413	5	3	1.3E+04
13.426	5	7	4.8E+04
13.47	3	1	1.5E+05
13.520	5	7	2.0E+05
13.56	3	5	1.0E+04
13.68	3	1	8.0E+04
13.69	5	7	2.3E+04
13.700	1	3	2.7E+05
13.71	5	5	2.2E+04
13.738	5	7	1.0E+04
13.796	5	7	7.0E+04
13.83	5	5	1.4E+04
13.934	1	3	4.51E+04
13.961	3	3	2.0E+04
14.668	5	7	1.1E+04
14.671	5	3	1.1E+04
14.929	3	3	1.2E+04
14.966	5	3	2.5E+04
14.995	5	5	2.2E+04
15.015	1	3	1.4E+04
16.668	3	1	1.1E+04
Fe XX			
12.67	6	6	1.0E+04
12.69	4	6	1.2E+04
12.73	4	2	4.0E+04
12.77	4	4	2.1E+05
12.78	4	2	6.9E+04
12.78	2	4	1.4E+05
12.79	6	4	1.7E+04
12.82	4	4	1.1E+05
12.88	6	4	2.7E+04
12.89	4	4	4.4E+04
12.90	4	2	6.2E+03
12.90	4	6	1.4E+05
12.92	2	4	1.7E+04
12.93	4	6	1.6E+05
12.93	2	2	1.2E+04
12.98	2	2	6.7E+04
12.99	6	6	5.1E+04
13.00	6	4	1.1E+04
13.01	2	4	3.0E+04
13.03	4	2	8.6E+04
13.07	6	4	8.2E+03
13.13	2	4	8.9E+04
13.24	4	4	1.2E+04
13.28	4	4	6.1E+03
13.70	4	6	1.1E+04
13.71	2	2	9.9E+03
13.78	4	4	1.0E+04
13.79	6	6	1.2E+04
13.83	4	2	9.8E+03
13.90	4	2	1.2E+04
13.98	6	4	1.6E+04
13.99	4	2	2.2E+04
14.05	4	4	1.7E+04
14.23	2	2	6.3E+03
Fe XXI			
8.53	3	1	1.8E+04
8.53	3	5	6.1E+03
8.53	3	3	1.5E+04
8.56	5	7	2.0E+04
8.56	1	3	2.1E+04
8.56	5	3	6.5E+03
8.64	5	7	1.5E+04
8.65	5	7	3.9E+04
8.66	5	5	4.4E+03
8.74	1	3	2.5E+04
9.42	3	1	4.3E+04
9.42	3	3	3.3E+04
9.44	3	5	1.7E+04
9.45	1	3	5.2E+04
9.46	5	3	1.5E+04
9.47	5	7	4.9E+04
9.47	5	5	6.1E+03
9.52	3	3	8.1E+03
9.58	5	5	5.2E+03
9.59	5	5	1.0E+04
9.67	1	3	5.7E+04
9.68	5	7	4.0E+03
9.74	5	3	5.3E+03
12.02	1	3	1.3E+04
12.13	3	3	1.8E+04
12.18	5	7	2.2E+04
12.19	5	3	6.4E+03
12.21	3	1	1.5E+05
12.21	3	3	1.2E+05
12.25	1	3	2.1E+05
12.28	5	3	5.2E+04
12.30	5	7	2.1E+05
12.36	3	3	3.6E+04
12.37	5	7	3.1E+05
12.38	5	3	6.9E+03
12.47	5	7	5.8E+04
12.47	5	3	1.3E+04
12.49	5	7	1.3E+04
12.53	5	5	1.5E+04
12.57	1	3	7.2E+04
12.73	5	5	8.2E+03
12.95	3	5	6.2E+03
13.00	1	3	7.2E+03
13.03	5	5	1.3E+04
13.14	3	1	2.0E+04
13.41	1	3	7.3E+03
Fe XXII			
9.002	4	6	5.5E+04
9.006	6	8	5.7E+04
9.006	6	6	5.3E+04
9.163	4	6	6.9E+04
9.183	6	8	8.3E+04
9.241	4	6	5.1E+04
11.748	4	4	1.2E+05
11.748	4	6	1.6E+05
11.748	4	2	1.8E+05
11.763	2	4	1.6E+05
11.789	2	2	2.6E+05
11.789	6	8	1.2E+05
11.797	2	4	1.7E+05
11.823	6	4	7.9E+04
11.837	6	8	2.3E+05
11.837	6	6	1.7E+05
11.886	4	6	1.3E+05
11.898	2	4	8.2E+04
11.922	4	6	1.8E+05

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
11.976	6	8	5.9E+04
12.027	2	4	6.9E+04
12.045	6	8	2.4E+05
12.045	4	4	9.7E+04
12.053	4	6	6.1E+04
12.077	2	4	1.0E+05
12.077	4	6	2.4E+05
12.095	6	6	7.8E+04
12.193	2	4	7.2E+04
12.193	4	6	9.9E+04
12.325	2	2	1.5E+05
Fe XXIII			
7.733	5	7	3.0E+04
7.849	5	7	4.9E+04
8.307	1	3	4.8E+04
8.529	1	3	4.3E+04
8.550	3	5	6.0E+04
8.552	3	3	3.2E+04
8.614	5	7	7.7E+04
8.664	3	3	4.4E+04
8.669	5	7	6.1E+04
8.672	1	3	6.8E+04
8.752	5	7	1.2E+05
8.764	5	7	4.6E+04
8.814	3	5	6.2E+04
10.902	5	5	5.3E+04
10.910	3	1	6.7E+04
10.927	5	7	6.0E+04
10.934	3	5	5.4E+04
10.979	1	3	7.9E+04
11.018	1	3	4.9E+04
11.086	3	1	6.5E+04
11.165	3	5	6.7E+04
11.255	3	3	3.7E+04
11.298	1	3	1.3E+05
11.325	3	5	1.7E+05
11.338	3	3	9.3E+04
11.429	3	1	1.7E+05
11.433	3	3	1.2E+05
11.441	5	7	2.2E+05
11.445	5	5	5.6E+04
11.485	3	5	1.40E+05
11.491	5	3	5.9E+04
11.519	5	5	1.16E+05
11.520	1	3	2.16E+05
11.524	5	7	2.3E+05
11.593	5	7	3.58E+05
11.613	3	5	1.0E+05
11.615	3	3	4.4E+04
11.691	5	7	7.7E+04
11.698	5	5	7.3E+04
11.737	3	5	1.8E+05
11.898	1	3	2.03E+05
Fe XXIV			
1.8523	2	2	1.0E+05
1.8552	2	4	4.82E+06
1.8563	4	2	2.43E+06
1.8572	2	2	3.06E+06
1.858	2	4	1.2E+05
1.8614	4	4	6.24E+06
1.8626	2	4	3.16E+06
1.8627	2	2	5.47E+06
1.8637	2	2	1.91E+06
1.8655	4	6	2.14E+06
1.8672	4	2	1.63E+06
1.8678	4	4	3.5E+05
1.8721	4	6	3.2E+05
1.8721	2	2	2.0E+05
1.8730	2	4	1.5E+05
1.8739	4	4	8.3E+04
1.891	2	2	9.7E+04
1.897	4	2	9.8E+04
8.231	2	4	6.10E+04
8.316	4	6	7.07E+04
10.619	2	4	7.28E+04
10.663	2	2	7.51E+04
11.030	2	4	1.84E+05
11.171	4	6	2.18E+05
Fe XXV			
1.4607	1	3	2.54E+05
1.4945	1	3	5.05E+05
1.5730	1	3	1.24E+06
1.5749	1	3	1.5E+05
1.778	3	3	8.7E+04
1.782	3	1	4.69E+06
1.787	1	3	2.57E+06
1.787	5	5	1.19E+06
1.788	3	5	2.68E+06
1.788	3	5	1.63E+06
1.789	1	3	1.78E+06
1.790	3	3	1.23E+06
1.791	3	5	4.10E+06
1.791	3	3	2.59E+06
1.792	3	1	4.92E+06
1.792	5	5	2.81E+06
1.793	3	1	2.67E+06
1.794	5	3	2.22E+06
1.797	3	5	8.8E+05
1.798	3	3	1.0E+05
1.800	1	3	8.6E+04
1.802	3	1	4.1E+05
1.810	3	1	5.9E+05
1.8502	1	3	4.57E+06
1.8593	1	3	4.42E+05
10.038	3	3	8.08E+04
Krypton			
Kr I			
1164.9	1	3	3.16E+00
1235.8	1	3	3.12E+00
4274.0	5	5	2.6E-02
4351.4	3	1	3.2E-02
4362.6	5	3	8.4E-03
4376.1	3	1	5.6E-02
4400.0	3	5	2.0E-02
4410.4	3	3	4.4E-03
4425.2	3	3	9.7E-03
4453.9	3	5	7.8E-03
4463.7	3	3	2.3E-02
4502.4	3	5	9.2E-03
5562.2	5	5	2.8E-03
5570.3	5	3	2.1E-02
5649.6	1	3	3.7E-03
5870.9	3	5	1.8E-02
6904.7	3	5	1.3E-02
7224.1	3	5	1.4E-02
7587.4	3	1	5.1E-01
7601.5	5	5	3.1E-01
7685.2	3	1	4.9E-01
7694.5	5	3	5.6E-02
7854.8	1	3	2.3E-01
8059.5	1	3	1.9E-01
8104.4	5	5	1.3E-01
8112.9	5	7	3.6E-01
8190.1	3	5	1.1E-01
8263.2	3	5	3.5E-01
8281.1	3	3	1.9E-01
8298.1	3	3	3.2E-01
8508.9	3	3	2.4E-01
8776.7	3	5	2.7E-01
8928.7	5	3	3.7E-01
Kr II			
4250.6	4	4	1.2E-01
4292.9	4	4	9.6E-01
4355.5	6	8	1.0E+00
4431.7	2	2	1.8E+00
4436.8	2	4	6.6E-01
4577.2	6	8	9.6E-01
4583.0	6	4	7.6E-01
4615.3	4	4	5.4E-01
4619.2	4	6	8.1E-01
4633.9	4	6	7.1E-01
4658.9	6	4	6.5E-01
4739.0	6	6	7.6E-01
4762.4	2	4	4.2E-01
4765.7	4	6	6.7E-01
4811.8	2	4	1.7E-01
4825.2	2	4	1.9E-01
4832.1	4	2	7.3E-01
5208.3	4	4	1.4E-01
5308.7	4	6	2.4E-02
7407.0	6	6	7.0E-02
Lead			
Pb I			
2022.0	1	3	5.2E-02
2053.3	1	3	1.2E-01
2170.0	1	3	1.5E+00
2401.9	3	3	1.9E-01
2446.2	3	3	2.5E-01
2476.4	3	5	2.8E-01
2577.3	5	3	5.0E-01
2613.7	3	3	2.7E-01
2614.2	3	5	1.9E+00
2628.3	5	3	3.1E-02
2657.1	3	5	9.8E-04
2663.2	5	5	7.1E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
2802.0	5	7	1.6E+00
2823.2	5	5	2.6E-01
2833.1	1	3	5.8E-01
2873.3	5	5	3.7E-01
3572.7	5	3	9.9E-01
3639.6	3	3	3.4E-01
3671.5	5	3	4.4E-01
3683.5	3	1	1.5E+00
3739.9	5	5	7.3E-01
4019.6	5	7	3.5E-02
4057.8	5	3	8.9E-01
4062.1	5	3	9.2E-01
4168.0	5	5	1.2E-02
5005.4	1	3	2.7E-01
5201.4	1	3	1.9E-01
7229.0	5	3	8.9E-03
Lithium			
Li I			
*2741.2	2	6	1.3E-02
*3232.7	2	6	1.17E-02
*4602.9	6	10	2.23E-01
*6103.6	6	10	6.860E-01
*6707.8	2	6	3.691E-01
Lutetium			
Lu I			
3376.5	4	4	2.23E+00
3567.8	4	6	5.9E-01
3620.3	6	4	1.1E-02
3841.2	6	6	2.5E-01
4518.6	4	4	2.1E-01
Magnesium			
Mg I			
2025.8	1	3	8.4E-01
*2779.8	9	9	5.2E+00
*2850.0	9	15	2.3E-01
2852.1	1	3	4.95E+00
*3094.9	9	15	5.2E-01
3329.9	1	3	3.3E-02
3332.2	3	3	9.7E-02
3336.7	5	3	1.6E-01
*3835.3	9	15	1.68E+00
4703.0	3	5	2.55E-01
5167.3	1	3	1.16E-01
5172.7	3	3	3.46E-01
5183.6	5	3	5.75E-01
5528.4	3	5	1.99E-01
Mg II			
1239.9	2	4	1.4E-02
1240.4	2	2	1.4E-02
*2660.8	10	14	3.8E-01
2790.8	2	4	4.0E+00
2795.5	2	4	2.6E+00
2797.9	4	4	7.9E-01
2798.1	4	6	4.8E+00
2802.7	2	2	2.6E+00
2928.8	2	2	1.2E+00
2936.5	4	2	2.3E+00
*3104.8	10	14	8.1E-01
3848.2	6	4	2.8E-02
3848.3	4	4	3.0E-03
3850.4	4	2	3.0E-02
*4481.2	10	14	2.23E+00
9218.3	2	4	3.6E-01
9244.3	2	2	3.6E-01
Mg IV			
320.99	4	2	1.2E+02
323.31	2	2	5.9E+01
1219.0	6	6	5.9E+00
1375.5	4	4	4.5E+00
1459.6	6	4	4.6E+00
1495.5	4	6	6.4E+00
1510.7	4	4	6.7E+00
1683.0	6	8	5.8E+00
1698.8	4	6	3.9E+00
1893.9	6	6	2.8E+00
Mg VI			
*269.92	10	6	3.1E+02
*292.53	6	6	9.0E+01
*314.64	6	2	1.8E+02
*349.15	10	10	6.1E+01
*387.94	6	10	1.3E+01
399.29	4	2	2.8E+01
400.68	4	4	2.8E+01
403.32	4	6	2.7E+01
Mg VII			
277.01	3	3	9.5E+01
278.41	5	3	1.5E+02
280.74	5	3	2.0E+02
319.02	5	5	8.9E+01
*366.42	9	9	4.4E+01
*433.04	9	15	1.6E+01
1334.3	5	5	5.3E+00
1410.0	5	5	2.57E+00
1487.0	3	5	3.02E+00
1487.9	5	7	3.66E+00
Mg VIII			
*74.976	6	10	4.3E+03
315.02	4	4	1.2E+02
*342.29	10	6	6.3E+01
353.86	4	4	3.89E+01
356.00	6	4	5.7E+01
*428.52	10	10	3.24E+01
*434.62	6	10	1.6E+01
*489.33	6	6	3.9E+01
*686.92	6	10	9.4E+00
Mg IX			
62.751	1	3	2.87E+03
*67.189	9	15	6.20E+03
*71.965	9	3	1.22E+03
72.312	3	5	4.43E+03
77.737	3	1	3.92E+02
368.07	1	3	5.27E+01
438.69	3	1	7.9E+01
*443.74	9	9	4.19E+01
749.55	3	5	8.2E+00
1639.8	3	5	2.1E+00
2814.2	1	3	3.35E-01
Mg X			
57.876	2	4	2.09E+03
57.920	2	2	2.09E+03
63.152	2	4	5.6E+03
63.295	4	6	6.7E+03
609.79	2	4	7.53E+00
624.94	2	2	7.01E+00
2212.5	2	4	9.64E-01
2278.7	2	2	8.82E-01
5918.7	2	4	3.20E-02
6229.6	4	6	3.30E-02
Mg XI			
7.310	1	3	1.15E+04
7.473	1	3	2.27E+04
7.850	1	3	5.50E+04
9.169	1	3	1.97E+05
Manganese			
Mn I			
2794.82	6	8	3.7E+00
2798.27	6	6	3.6E+00
2801.08	6	4	3.7E+00
3007.65	6	8	1.8E-01
3011.38	8	10	3.1E-01
3016.45	10	12	2.9E-01
3043.36	8	8	5.9E-01
3044.57	10	8	5.7E-01
3045.59	10	10	6.7E-01
3045.80	8	10	1.7E-01
3047.03	12	12	6.1E-01
3054.36	8	6	4.6E-01
3070.27	6	6	1.9E-01
3073.18	4	4	3.7E-01
3082.71	14	14	2.9E-01
3110.68	6	8	2.7E-01
3113.80	12	10	2.6E-01
3118.10	4	6	1.7E-01
3122.88	10	10	1.9E-01
3126.85	8	6	2.3E-01
3132.28	10	10	2.1E-01
3132.79	8	8	2.7E-01
3175.58	8	10	1.8E-01
3201.11	4	6	2.2E-01
3228.09	10	12	6.4E-01
3230.23	10	12	1.9E-01
3230.72	8	8	3.5E-01
3240.88	6	4	2.2E-01
3243.78	6	6	5.3E-01
3251.13	4	2	2.3E-01
3252.95	4	4	1.8E-01
3256.14	4	6	5.0E-01
3258.41	2	2	9.7E-01
3260.24	2	4	3.8E-01
3267.79	14	14	3.5E-01
3268.72	6	8	3.3E-01
3270.35	12	12	2.6E-01
3273.02	10	10	2.7E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3298.23	6	4	2.8E-01
3303.28	4	4	1.9E-01
3463.66	8	8	3.2E-01
3470.01	6	8	2.4E-01
3511.83	12	12	2.7E-01
3535.30	10	10	1.7E-01
3559.81	6	6	2.1E-01
3577.87	10	8	9.4E-01
3595.11	6	4	1.8E-01
3601.27	12	10	2.3E-01
3607.53	8	8	2.3E-01
3608.49	6	6	3.6E-01
3610.30	4	4	4.2E-01
3635.70	10	8	2.1E-01
3660.40	12	14	9.1E-01
3675.67	6	8	2.2E-01
3676.96	10	12	7.3E-01
3680.15	12	10	1.9E-01
3682.09	8	10	7.6E-01
3684.87	6	8	2.6E-01
3706.08	12	14	1.4E+00
3718.92	10	12	9.6E-01
3731.94	8	10	1.0E+00
3771.44	14	14	1.9E-01
3773.86	12	12	2.5E-01
3800.55	6	8	2.7E-01
3806.72	10	12	5.9E-01
3823.51	8	10	5.21E-01
3823.89	6	6	2.31E-01
3833.87	4	4	3.14E-01
3834.37	6	8	4.29E-01
3839.78	2	2	4.64E-01
3841.07	4	6	3.3E-01
3843.99	2	4	2.11E-01
3889.46	12	14	3.1E-01
3898.37	6	8	1.7E-01
3899.34	4	6	2.4E-01
3924.08	2	4	9.4E-01
3926.48	6	8	5.4E-01
3951.98	2	2	3.1E-01
3952.84	6	6	4.1E-01
3975.88	2	4	1.8E-01
3982.16	4	2	3.5E-01
3982.58	6	4	2.3E-01
3982.90	6	4	5.5E-01
3991.60	2	2	2.1E-01
4011.91	8	8	2.3E-01
4018.11	10	8	2.54E-01
4030.76	6	8	1.7E-01
4033.07	6	6	1.65E-01
4034.49	6	4	1.58E-01
4041.36	10	10	7.87E-01
4048.75	6	4	7.5E-01
4052.48	6	8	3.8E-01
4055.55	8	8	4.31E-01
4058.94	4	2	7.25E-01
4061.74	8	6	1.9E-01
4063.53	6	6	1.69E-01
4065.08	12	14	2.5E-01
4066.24	10	8	2.2E-01
4070.28	2	2	2.3E-01
4079.42	2	4	3.8E-01
4082.95	4	6	2.95E-01
4083.63	6	8	2.8E-01
4089.94	8	10	1.7E-01
4105.37	10	8	1.7E-01
4135.03	12	12	3.0E-01
4141.06	10	10	2.6E-01
4148.80	8	8	2.3E-01
4176.61	14	12	2.4E-01
4189.99	12	10	2.0E-01
4201.78	10	8	2.3E-01
4235.30	8	6	9.17E-01
4239.74	4	2	3.9E-01
4257.67	2	2	3.7E-01
4265.93	4	4	4.92E-01
4281.10	6	6	2.3E-01
4411.87	12	10	2.6E-01
4414.89	8	6	2.93E-01
4419.77	10	8	2.1E-01
4436.36	6	4	4.37E-01
4451.58	8	8	7.98E-01
4453.01	4	2	5.44E-01
4455.82	4	6	1.7E-01
4457.04	6	4	2.34E-01
4457.55	6	6	4.27E-01
4458.26	6	8	4.62E-01
4461.09	8	8	1.7E-01
4462.03	8	10	7.00E-01
4464.68	6	6	4.39E-01
4470.14	4	4	3.00E-01
4472.79	2	2	4.35E-01
4479.40	8	10	3.4E-01
4490.08	2	4	2.49E-01
4498.90	4	6	2.49E-01
4502.22	6	8	1.86E-01
4605.37	10	12	3.6E-01
4626.54	12	14	3.6E-01
4709.71	8	8	1.72E-01
4727.46	6	6	1.7E-01
4739.11	4	4	2.40E-01
4754.05	6	8	3.03E-01
4761.53	2	4	5.35E-01
4762.38	8	10	7.83E-01
4765.86	4	6	4.1E-01
4766.43	6	8	4.6E-01
4783.43	8	8	4.01E-01
4823.53	10	8	4.99E-01
6013.48	4	6	1.72E-01
6021.79	8	6	3.32E-01
Mn II			
2593.72	7	7	2.6E+00
2605.68	7	5	2.7E+00
2933.05	5	3	2.0E+00
2939.31	5	5	1.9E+00
2949.20	5	7	1.9E+00
3441.99	9	7	4.3E-01
3460.32	7	5	3.2E-01
3474.13	5	3	1.5E-01
3482.90	5	5	2.0E-01
3488.68	3	3	2.5E-01
Mn VI			
307.999	9	9	3.7E+01
309.440	9	7	5.7E+01
309.579	7	5	4.4E+01
310.058	7	7	3.4E+01
310.182	5	5	2.8E+01
311.748	5	3	5.7E+01
320.598	3	5	1.5E+01
320.681	1	3	2.2E+01
320.874	3	1	7.8E+01
320.979	3	3	2.2E+01
321.176	5	5	6.0E+01
321.541	5	3	2.7E+01
325.146	9	7	1.3E+02
328.431	5	5	4.4E+01
328.558	3	5	1.2E+01
329.043	1	3	1.1E+01
1236.23	5	3	1.3E+01
1255.77	3	1	1.2E+01
1285.10	5	7	1.1E+01
1333.87	7	9	1.0E+01
Mercury			
Hg I			
2536.52	1	3	8.00E-02
2652.04	3	5	3.88E-01
2655.13	3	5	1.1E-01
2752.78	1	3	6.10E-02
2856.94	3	1	1.1E-02
2893.60	3	3	1.6E-01
2925.4	5	3	7.7E-02
2967.3	1	3	4.5E-01
3021.50	5	7	5.09E-01
3023.48	5	5	9.4E-02
3027.49	5	5	2.0E-02
3125.66	3	5	6.56E-01
3341.48	5	3	1.68E-01
3650.15	5	7	1.3E+00
3654.83	5	5	1.8E-01
4046.56	1	3	2.1E-01
4077.81	3	1	4.0E-02
4108.1	3	1	3.0E-02
4339.22	3	5	2.88E-02
4347.50	3	5	8.4E-02
4358.34	3	3	5.57E-01
4916.07	3	1	5.8E-02
5025.64	3	3	2.7E-04
5460.75	5	3	4.87E-01
5769.59	3	5	2.36E-01
6234.4	1	3	5.3E-03
6716.4	1	3	4.3E-03
6907.5	3	5	2.8E-02
7728.8	1	3	9.7E-03
10139.79	3	1	2.71E-01
Molybdenum			
Mo I			
2616.79	3	5	7.34E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
2621.06	7	7	1.16E-01
2628.96	3	3	2.81E-01
2629.85	5	7	7.75E-01
2631.50	1	3	2.54E-01
2638.30	5	5	7.57E-01
2640.98	7	5	1.20E+00
2644.36	5	7	1.96E-01
2649.46	7	9	9.84E-01
2655.02	9	7	4.08E-01
2658.11	7	7	6.43E-01
2665.09	7	9	1.32E-01
2679.85	9	11	1.31E+00
2684.16	9	9	4.18E-01
2706.11	3	5	2.03E-01
2710.74	3	3	1.57E-01
2725.15	3	5	2.79E-01
2728.71	3	3	1.26E-01
2733.39	5	7	2.95E-01
2743.71	1	3	2.47E-01
2745.38	13	11	1.29E-01
2751.47	7	9	2.54E-01
2756.26	5	3	1.18E-01
2761.53	9	11	2.06E-01
2763.02	3	1	4.44E-01
2766.25	3	5	1.17E-01
2787.83	9	7	2.85E-01
2792.96	5	3	1.53E-01
2798.02	7	5	1.22E-01
2801.47	5	7	1.24E-01
2825.68	5	7	2.53E-01
2826.75	7	7	4.23E-01
2876.54	9	9	2.84E-01
2886.60	11	11	4.74E-01
2906.06	3	3	8.04E-01
2913.52	5	3	1.38E-01
2915.38	5	3	7.31E-01
2918.84	5	3	3.79E-01
2930.39	1	3	1.91E-01
2936.50	11	11	2.33E-01
2945.43	7	7	3.66E-01
2945.66	3	3	4.08E-01
2946.01	5	5	1.68E-01
2951.45	9	9	1.43E-01
2959.48	9	11	1.75E-01
2972.96	5	3	2.69E-01
2977.27	9	7	3.28E-01
2978.28	7	5	1.50E-01
2983.04	1	3	2.82E-01
2987.92	3	5	8.43E-01
2988.23	5	7	4.28E-01
2988.68	7	9	1.61E-01
2989.80	9	7	9.27E-01
3000.24	9	9	1.40E-01
3000.44	5	5	1.25E-01
3000.85	5	7	2.58E-01
3001.43	5	5	2.31E-01
3007.71	7	5	1.90E-01
3013.39	7	5	6.06E-01
3016.78	9	9	2.75E-01
3025.00	5	5	8.49E-01
3036.31	3	5	5.81E-01
3041.70	13	11	5.94E-01
3046.80	13	11	1.63E-01
3047.31	11	9	5.01E-01
3055.32	9	7	4.29E-01
3057.56	7	5	2.64E-01
3061.59	7	5	4.41E-01
3064.27	13	13	8.46E-01
3065.04	13	13	3.08E-01
3069.51	5	5	1.52E-01
3069.96	11	11	2.72E-01
3070.89	9	11	1.87E-01
3074.37	11	11	1.42E+00
3079.88	9	11	9.55E-01
3080.40	7	9	3.61E-01
3081.16	3	5	2.35E-01
3085.62	9	9	1.63E+00
3089.13	11	9	1.53E-01
3089.71	5	7	2.34E-01
3094.66	7	7	1.63E+00
3099.92	9	7	1.45E-01
3100.88	7	9	1.20E+00
3101.34	5	5	1.92E+00
3106.34	7	5	2.21E-01
3117.54	13	13	1.89E-01
3123.03	3	3	2.81E-01
3125.03	5	3	1.98E-01
3132.59	7	9	1.79E+00
3135.90	9	11	3.68E-01
3136.75	9	11	1.57E-01
3142.75	3	5	4.10E-01
3147.35	13	11	2.41E-01
3155.19	7	7	2.75E-01
3158.17	7	7	4.63E-01
3170.34	7	7	1.37E+00
3171.38	5	7	2.03E-01
3175.59	13	11	8.40E-01
3179.78	11	13	2.33E-01
3183.03	11	9	3.98E-01
3184.58	7	5	2.77E-01
3185.10	7	7	2.54E-01
3185.71	5	3	6.10E-01
3188.10	7	9	3.45E-01
3188.41	5	7	4.40E-01
3192.79	9	11	1.88E-01
3193.98	7	5	1.53E+00
3194.88	9	11	1.75E-01
3195.96	9	7	4.10E-01
3197.18	1	3	1.47E-01
3198.85	15	13	7.22E-01
3200.89	3	5	1.82E-01
3205.22	1	3	4.27E-01
3205.43	9	11	2.55E-01
3205.89	9	9	5.35E-01
3208.84	7	5	2.77E-01
3210.97	7	5	6.94E-01
3214.44	9	7	2.01E-01
3215.07	3	5	4.20E-01
3216.78	15	13	2.10E-01
3221.73	3	1	1.41E+00
3228.21	5	7	3.85E-01
3229.79	9	11	1.44E-01
3233.14	13	13	6.33E-01
3237.06	7	9	2.95E-01
3244.47	5	3	2.80E-01
3247.61	5	5	1.71E-01
3249.93	5	3	1.87E-01
3251.65	3	5	3.05E-01
3256.21	5	3	6.89E-01
3256.72	3	3	1.31E-01
3259.16	11	13	1.62E-01
3262.63	7	9	3.62E-01
3264.40	11	9	5.42E-01
3265.14	5	7	2.60E-01
3266.16	9	11	1.95E-01
3270.90	7	7	3.59E-01
3276.07	11	9	1.18E-01
3285.03	1	3	1.41E-01
3285.35	9	7	4.49E-01
3287.38	5	5	1.38E-01
3289.01	9	9	5.08E-01
3290.82	7	5	5.44E-01
3305.56	5	3	1.74E-01
3305.91	7	9	3.06E-01
3307.13	7	9	1.25E-01
3312.33	7	5	1.62E-01
3323.95	9	7	2.82E-01
3325.13	5	3	2.26E-01
3325.67	5	5	1.72E-01
3327.30	1	3	2.88E-01
3336.56	9	9	1.64E-01
3340.16	5	3	1.20E-01
3344.73	3	5	6.04E-01
3346.83	11	11	1.13E-01
3347.00	3	3	2.72E-01
3358.12	5	7	7.59E-01
3361.37	9	9	1.38E-01
3363.78	5	7	2.74E-01
3363.87	5	7	1.39E-01
3373.81	3	3	2.03E-01
3375.22	7	7	1.38E-01
3375.65	7	9	1.56E-01
3378.19	3	1	1.88E-01
3378.46	13	13	3.75E-01
3379.96	5	5	4.11E-01
3382.48	3	3	2.66E-01
3384.61	7	9	7.32E-01
3385.87	9	11	3.30E-01
3389.79	5	7	1.85E-01
3392.17	9	9	1.97E-01
3393.65	11	11	2.08E-01
3404.33	7	7	2.10E-01
3413.37	11	11	1.25E-01
3415.27	9	9	1.83E-01
3415.61	7	9	1.29E-01
3416.14	9	11	2.45E-01
3418.52	5	3	1.41E-01
3419.69	7	7	1.15E-01
3420.04	5	5	3.28E-01
3422.31	9	9	2.52E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3425.13	11	11	2.29E-01
3427.90	11	13	4.09E-01
3434.79	7	7	1.75E-01
3435.45	15	15	1.50E+00
3437.21	11	9	8.06E-01
3438.87	1	3	2.34E-01
3441.87	5	3	1.34E-01
3442.66	3	3	2.94E-01
3445.03	7	9	1.53E-01
3445.26	7	5	2.96E-01
3445.80	9	9	1.14E-01
3447.12	9	11	8.75E-01
3447.29	5	3	1.79E-01
3449.07	7	9	1.52E-01
3449.85	5	7	1.65E-01
3452.60	7	7	2.48E-01
3456.15	5	5	3.60E-01
3456.52	3	3	2.96E-01
3460.22	5	3	2.77E-01
3460.78	9	7	6.03E-01
3465.84	3	1	9.99E-01
3466.19	9	7	2.11E-01
3466.96	7	7	1.52E-01
3467.85	5	7	2.63E-01
3469.22	5	3	6.96E-01
3469.63	13	15	1.51E-01
3470.92	3	5	2.91E-01
3475.03	3	3	4.68E-01
3479.42	7	5	2.26E-01
3483.67	7	7	1.13E-01
3483.83	7	5	1.41E-01
3489.43	7	7	3.27E-01
3504.41	7	9	8.06E-01
3505.31	7	9	2.25E-01
3508.11	9	9	1.59E-01
3510.77	13	13	4.75E-01
3517.55	11	11	5.41E-01
3518.21	3	3	3.64E-01
3521.38	9	9	1.39E-01
3521.41	9	11	6.06E-01
3524.65	5	3	3.10E-01
3524.98	7	9	2.25E-01
3538.92	11	11	2.24E-01
3540.57	5	3	4.46E-01
3542.17	7	5	4.93E-01
3552.71	9	7	3.64E-01
3555.64	3	3	3.46E-01
3558.09	5	7	5.43E-01
3563.75	1	3	1.53E-01
3566.05	9	9	2.67E-01
3566.74	7	7	1.43E-01
3570.64	15	15	7.18E-01
3573.88	3	5	3.58E-01
3580.54	13	11	5.49E-01
3581.88	11	13	3.81E-01
3584.25	3	3	1.73E-01
3585.57	7	5	3.95E-01
3588.95	7	7	1.18E-01
3590.74	7	9	2.23E-01
3595.55	5	5	2.32E-01
3598.88	13	11	5.67E-01
3600.73	9	9	2.07E-01
3601.88	7	9	1.15E-01
3602.94	5	7	2.96E-01
3604.07	9	7	3.25E-01
3610.61	5	3	1.78E-01
3611.99	7	7	1.16E-01
3615.16	7	9	1.96E-01
3623.22	11	9	5.58E-01
3624.46	9	11	5.27E-01
3624.62	5	7	1.37E-01
3638.20	5	3	3.51E-01
3638.21	5	3	3.33E-01
3640.62	7	5	1.94E-01
3647.84	7	7	2.11E-01
3648.70	7	5	1.15E-01
3654.58	3	3	1.80E-01
3657.36	5	7	2.03E-01
3658.13	9	9	1.86E-01
3659.36	7	9	6.70E-01
3660.92	3	5	1.34E-01
3662.15	7	9	1.45E-01
3662.99	11	11	3.48E-01
3663.27	7	5	2.30E-01
3664.81	11	13	9.54E-01
3664.88	1	3	1.92E-01
3669.34	9	7	2.16E-01
3672.81	9	11	1.95E-01
3672.82	9	9	1.13E-01
3676.23	3	1	5.22E-01
3680.68	11	11	2.96E-01
3681.72	9	7	1.68E-01
3683.01	3	5	1.20E-01
3687.96	5	7	2.12E-01
3688.97	11	9	3.26E-01
3690.59	11	9	2.07E-01
3694.94	5	7	6.36E-01
3696.04	11	11	3.59E-01
3698.07	7	5	1.48E-01
3708.55	7	9	1.28E-01
3715.75	9	7	2.38E-01
3718.48	5	7	1.34E-01
3720.25	7	9	2.86E-01
3725.55	7	7	1.60E-01
3727.68	9	11	1.51E-01
3728.30	7	5	1.55E-01
3728.50	7	9	2.20E-01
3733.02	7	7	1.45E-01
3733.41	13	13	2.80E-01
3735.62	11	11	1.66E-01
3742.28	7	7	1.56E-01
3747.19	5	7	3.07E-01
3748.48	9	11	3.95E-01
3755.10	3	5	1.41E-01
3755.16	9	9	2.48E-01
3758.52	9	9	1.22E-01
3759.60	9	7	1.82E-01
3760.88	9	9	2.16E-01
3768.73	9	9	2.88E-01
3769.99	7	9	2.46E-01
3777.72	13	11	1.66E-01
3788.25	7	9	2.87E-01
3794.43	9	9	1.22E-01
3797.47	7	5	1.48E-01
3798.25	7	9	6.90E-01
3801.84	9	7	3.16E-01
3805.99	5	5	2.44E-01
3819.78	9	11	1.47E-01
3824.78	5	7	1.40E-01
3827.15	7	7	1.94E-01
3828.88	7	7	1.35E-01
3830.81	5	5	1.83E-01
3831.07	7	9	1.20E-01
3832.11	9	9	3.05E-01
3833.75	9	9	1.70E-01
3834.64	3	5	1.20E-01
3846.18	7	7	1.26E-01
3847.25	3	1	2.41E-01
3848.30	9	9	1.26E-01
3851.99	11	9	1.78E-01
3864.10	7	7	6.24E-01
3866.69	3	5	1.74E-01
3867.67	5	3	2.22E-01
3869.08	5	3	1.35E-01
3874.15	7	5	1.67E-01
3902.95	7	5	6.17E-01
3909.54	9	7	1.13E-01
3911.94	5	5	1.15E-01
3915.43	5	5	1.40E-01
3916.43	5	3	1.78E-01
3919.55	11	13	2.24E-01
3955.48	13	11	1.71E-01
3973.76	11	13	4.39E-01
3977.90	9	7	1.35E-01
3980.20	5	3	2.70E-01
3991.85	11	9	1.29E-01
4010.13	5	3	4.38E-01
4021.01	9	11	2.65E-01
4051.18	13	11	1.36E-01
4062.08	11	9	1.96E-01
4069.88	13	11	3.25E-01
4076.19	9	9	1.16E-01
4084.37	9	7	1.94E-01
4102.15	5	3	1.22E-01
4107.46	7	5	2.02E-01
4120.09	13	15	6.05E-01
4131.92	9	11	1.56E-01
4148.98	9	11	1.56E-01
4157.40	13	11	2.17E-01
4157.90	9	11	1.60E-01
4185.82	11	13	3.82E-01
4188.32	11	13	3.32E-01
4194.56	11	11	2.70E-01
4232.59	9	11	3.17E-01
4240.83	5	5	1.68E-01
4246.02	11	13	2.00E-01
4251.88	13	11	1.76E-01
4254.95	7	9	2.01E-01
4269.28	11	11	1.36E-01
4276.91	7	9	2.85E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
4277.24	9	11	1.35E-01
4317.92	15	15	1.28E-01
4325.80	3	3	1.84E-01
4326.14	5	7	2.56E-01
4340.74	5	7	1.23E-01
4381.63	13	13	2.93E-01
4382.41	11	13	3.83E-01
4409.94	13	13	1.38E-01
4411.69	11	11	2.63E-01
4434.95	9	9	2.51E-01
4446.42	11	11	1.90E-01
4457.35	7	7	1.28E-01
4474.57	5	5	2.10E-01
4491.65	11	11	2.09E-01
4536.80	13	15	5.03E-01
4598.23	1	3	1.47E-01
4624.23	9	9	1.32E-01
4633.08	3	5	2.35E-01
4649.06	3	1	1.25E-01
4652.24	5	7	1.55E-01
4686.08	3	3	1.72E-01
4688.21	13	15	1.54E-01
4707.25	7	9	3.63E-01
4718.86	5	5	2.17E-01
4723.05	9	9	1.23E-01
4731.44	9	11	4.49E-01
4758.50	11	9	3.01E-01
4760.18	11	13	4.67E-01
4764.11	9	7	2.16E-01
4811.05	13	11	4.36E-01
4819.25	11	9	2.71E-01
4830.51	9	7	4.07E-01
4858.39	13	11	1.24E-01
4868.02	7	5	3.11E-01
5037.18	9	7	1.14E-01
5044.36	7	5	1.31E-01
5047.70	3	1	2.61E-01
5163.18	9	11	2.03E-01
5171.06	5	7	1.84E-01
5172.94	5	5	4.11E-01
5174.18	5	3	5.83E-01
5191.45	7	9	1.62E-01
5238.21	7	9	3.74E-01
5240.87	7	7	3.89E-01
5242.80	7	5	2.01E-01
5261.53	5	7	1.13E-01
5280.85	5	5	1.28E-01
5355.52	9	9	1.21E-01
5356.46	11	11	2.11E-01
5360.51	9	11	6.19E-01
5364.28	9	9	2.26E-01
5460.50	5	3	3.46E-01
5493.76	7	5	2.13E-01
5506.49	5	7	3.61E-01
5533.03	5	5	3.72E-01
5570.44	5	3	3.30E-01
5849.71	3	3	3.02E-01
5851.50	3	5	1.55E-01
5893.36	5	5	2.60E-01
5895.93	5	7	3.12E-01
5926.37	7	7	1.63E-01
5928.88	7	9	5.32E-01
7154.11	9	9	3.45E-01
Neodymium			
Nd II			
3780.4	16	18	1.4E-01
3805.4	14	16	6.9E-01
3807.2	10	12	4.9E-02
3863.3	8	10	1.5E-01
3941.5	10	10	6.1E-01
3951.2	12	12	6.0E-01
3973.3	18	18	6.3E-01
3979.5	10	12	2.7E-01
3990.1	16	16	5.2E-01
4012.3	18	20	5.5E-01
4061.1	16	18	4.4E-01
4106.6	14	16	6.8E-02
4109.5	14	16	3.7E-01
4133.4	14	12	1.5E-01
4156.1	12	14	3.4E-01
4205.6	18	16	1.8E-01
4284.5	18	18	8.5E-02
4303.6	8	10	4.7E-01
4325.8	16	16	1.6E-01
4358.2	14	14	1.5E-01
4382.7	12	10	4.0E-02
4400.8	10	10	6.8E-02
4451.6	12	14	2.5E-01
4456.4	16	18	6.4E-02
4463.0	14	16	1.8E-01
4958.1	12	10	1.2E-02
5130.6	22	20	1.6E-01
5192.6	20	18	1.7E-01
5249.6	18	16	1.8E-01
5276.9	12	10	1.2E-01
5293.2	16	14	1.2E-01
5302.3	20	18	1.1E-01
5311.5	14	12	1.1E-01
5319.8	12	10	1.6E-01
5357.0	18	16	1.8E-01
5371.9	20	20	5.1E-02
5485.7	18	18	5.7E-02
5594.4	16	16	7.0E-02
5620.6	18	18	1.3E-01
5688.5	14	14	5.9E-02
5718.1	16	16	8.7E-02
5726.8	10	10	5.6E-02
5740.9	12	12	7.2E-02
5804.0	10	10	4.6E-02
5865.1	16	18	1.3E-02
6051.9	12	10	1.1E-02
Neon			
Ne I			
615.63	1	3	3.8E-01
618.67	1	3	9.3E-01
619.10	1	3	3.3E-01
626.82	1	3	7.4E-01
629.74	1	3	4.8E-01
735.90	1	3	6.11E+00
743.72	1	3	4.86E-01
3369.8	5	5	1.0E-03
3369.9	5	3	7.6E-03
3375.6	5	3	2.2E-03
3417.9	3	5	9.2E-03
3418.0	3	3	2.2E-03
3423.9	3	3	1.0E-03
3447.7	5	5	2.1E-02
3450.8	5	3	4.9E-03
3454.2	3	1	3.7E-02
3460.5	1	3	7.0E-03
3464.3	5	5	6.7E-03
3466.6	1	3	1.3E-02
3472.6	5	7	1.7E-02
3498.1	3	5	5.1E-03
3501.2	3	3	1.2E-02
3510.7	5	3	2.2E-03
3515.2	3	5	6.9E-03
3520.5	3	1	9.3E-02
3593.5	3	5	9.9E-03
3593.6	3	3	6.6E-03
3600.2	3	3	4.3E-03
3633.7	3	1	1.1E-02
3682.2	3	5	1.6E-03
3685.7	3	3	3.9E-03
3701.2	3	5	2.2E-03
4536.3	3	3	5.0E-03
4702.5	3	3	2.1E-03
4708.9	3	3	4.2E-02
4955.4	3	3	3.3E-03
5113.7	3	3	1.0E-02
5120.5	3	3	5.6E-03
5154.4	3	3	1.9E-02
5191.3	3	3	1.3E-02
5326.4	3	3	6.8E-03
5333.3	3	3	5.3E-03
5341.1	3	3	1.1E-01
5400.6	3	1	9.0E-03
5418.6	3	3	5.2E-03
5433.7	3	3	2.83E-03
5652.6	3	3	8.9E-03
5662.5	3	3	6.9E-03
5852.5	3	1	6.82E-01
5868.4	3	3	1.4E-02
5881.9	5	3	1.15E-01
5913.6	3	3	4.8E-02
5939.3	5	3	2.00E-03
5944.8	5	5	1.13E-01
5961.6	3	3	3.3E-02
5975.5	5	3	3.51E-02
6030.0	3	3	5.61E-02
6046.1	3	3	2.26E-03
6074.3	3	1	6.03E-01
6096.2	3	5	1.81E-01
6118.0	5	3	6.09E-03
6128.5	3	3	6.7E-03
6143.1	5	5	2.82E-01
6150.3	3	3	1.5E-02
6163.6	1	3	1.46E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
6217.3	5	3	6.37E-02
6266.5	1	3	2.49E-01
6273.0	3	3	9.7E-03
6293.7	3	3	6.39E-03
6304.8	3	5	4.16E-02
6328.2	5	3	3.39E-02
6330.9	3	3	2.3E-02
6334.4	5	5	1.61E-01
6351.9	1	3	3.45E-03
6383.0	3	3	3.21E-01
6401.1	3	3	1.39E-02
6402.2	5	7	5.14E-01
6506.5	3	5	3.00E-01
6532.9	1	3	1.08E-01
6599.0	3	3	2.32E-01
6602.9	3	3	5.9E-03
6652.1	3	1	2.9E-03
6678.3	3	5	2.33E-01
6717.0	3	3	2.17E-01
6721.1	3	3	4.9E-04
6929.5	3	5	1.74E-01
7024.1	3	3	1.89E-02
7032.4	5	3	2.53E-01
7051.3	3	3	3.0E-02
7059.1	3	5	6.8E-02
7173.9	3	5	2.87E-02
7245.2	3	3	9.35E-02
7304.8	1	3	2.55E-03
7438.9	1	3	2.31E-02
7472.4	3	3	4.0E-02
7535.8	3	3	4.3E-01
7937.0	5	5	7.8E-03
8082.5	3	3	1.2E-03
8118.5	3	3	4.9E-02
8128.9	3	5	7.2E-03
8259.4	5	5	2.03E-02
8571.4	3	3	5.5E-02
8582.9	3	5	1.00E-02
8647.0	5	5	3.91E-02
8681.9	3	3	2.1E-01
8767.5	3	3	1.1E-03
8771.7	3	3	1.6E-01
8783.8	3	5	3.13E-01
8865.3	3	3	9.4E-03
9201.8	3	3	9.1E-02
9433.0	3	3	1.1E-03
9486.7	3	3	2.5E-02
9534.2	3	3	6.3E-02
10621	3	3	2.4E-03
11409	3	3	4.2E-02
11525	3	3	8.4E-02
11767	3	3	6.9E-02
12459	3	3	1.5E-02
Ne II			
*357.03	6	10	3.8E+01
*361.77	6	2	1.6E+01
*406.28	6	10	1.8E+01
*446.37	6	6	4.07E+01
460.73	4	2	4.7E+01
462.39	2	2	2.3E+01
1907.5	4	2	2.8E-01
1916.1	4	4	6.9E-01
1930.0	2	2	5.7E-01
1938.8	2	4	1.3E-01
2858.0	6	6	7.9E-01
2870.0	6	6	1.7E-01
2873.0	6	4	3.8E-01
2876.3	4	6	7.8E-01
2876.5	6	4	3.3E-01
2878.1	2	2	6.9E-02
2888.4	4	6	7.0E-02
2891.5	4	4	6.1E-02
2897.0	6	8	5.2E-02
2906.8	2	4	5.5E-01
2910.1	4	2	1.7E+00
2910.4	2	4	5.9E-01
2916.2	6	4	9.6E-02
2925.6	2	2	5.6E-01
2933.7	6	6	6.9E-02
2955.7	6	4	1.2E+00
3001.7	4	4	8.7E-01
3017.3	6	4	3.5E-01
3027.0	6	6	1.4E+00
3028.7	4	2	8.5E-01
3028.9	2	4	4.7E-01
3034.5	6	8	3.1E+00
3037.7	4	4	2.1E+00
3045.6	2	2	2.5E+00
3047.6	4	6	1.8E+00
3054.7	2	4	9.4E-01
3092.9	6	6	1.3E+00
3097.1	8	8	1.3E+00
3118.0	8	6	4.2E-02
3134.1	6	4	2.6E-01
3140.4	8	6	2.4E-01
3151.1	6	6	4.8E-02
3154.8	8	6	1.8E-02
3164.4	8	8	1.6E-01
3165.7	6	6	1.2E-01
3173.6	6	4	4.5E-02
3176.1	4	6	6.0E-02
3187.6	4	6	1.4E-02
3188.7	6	6	3.9E-01
3190.9	4	6	1.5E-01
3194.6	4	4	5.2E-01
3198.6	6	8	1.7E+00
3198.9	4	4	2.3E-01
3209.0	8	8	1.6E-01
3209.4	2	4	6.0E-01
3213.7	2	4	1.7E+00
3214.3	4	6	2.2E+00
3218.2	8	10	3.6E+00
3224.8	6	8	3.5E+00
3229.5	8	8	1.3E-01
3229.6	8	10	3.6E+00
3230.1	6	6	1.8E+00
3230.4	4	6	1.4E-01
3232.0	6	4	2.7E-01
3232.4	4	4	1.6E+00
3243.4	6	6	2.3E-01
3244.1	6	8	1.5E+00
3248.1	4	4	2.4E-01
3255.4	6	4	3.8E-02
3263.4	2	4	3.9E-01
3269.9	4	6	5.1E-01
3270.8	6	4	5.7E-02
3297.7	6	6	4.3E-01
3309.7	4	2	3.1E-01
3310.5	4	4	6.9E-02
3311.3	4	2	2.6E-01
3314.7	6	6	4.4E-02
3319.7	4	2	1.6E+00
3320.2	8	6	2.1E-01
3323.7	4	4	1.6E+00
3327.2	4	4	9.1E-01
3329.2	8	8	8.8E-01
3330.7	6	6	3.9E-02
3334.8	6	8	1.8E+00
3336.1	4	6	1.1E+00
3344.4	2	2	1.5E+00
3345.5	6	4	1.4E+00
3345.8	4	4	2.2E-01
3353.6	4	2	1.2E-01
3355.0	4	6	1.3E+00
3356.3	6	6	2.0E-01
3357.8	6	6	5.0E-01
3360.3	2	4	8.6E-01
3360.6	2	4	8.2E-01
3362.9	4	2	3.5E-01
3371.8	4	6	2.2E-01
3374.1	4	4	3.0E-01
3378.2	2	2	1.7E+00
3379.3	2	2	3.0E-01
3386.2	4	6	5.5E-02
3388.4	4	6	2.2E+00
3390.6	2	4	7.7E-02
3392.8	2	4	4.4E-01
3404.8	4	6	1.9E+00
3407.0	6	8	2.3E+00
3411.4	4	2	6.1E-01
3413.2	4	4	1.8E+00
3414.9	4	6	1.8E-02
3416.9	6	6	6.4E-01
3417.7	6	8	1.6E+00
3438.9	2	2	1.4E+00
3440.7	2	4	3.5E-01
3453.1	4	4	4.6E-01
3454.8	4	4	1.6E+00
3456.6	2	4	9.6E-01
3457.1	4	6	9.9E-02
3459.3	6	6	1.6E+00
3475.2	4	4	1.2E-02
3477.6	4	6	4.3E-01
3481.9	4	2	1.4E+00
3503.6	2	2	2.0E+00
3522.7	4	2	2.3E-02
3538.0	4	2	7.6E-01
3539.9	4	4	3.6E-02
3542.2	6	4	6.0E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3542.9	4	6	1.2E+00
3546.2	2	4	6.3E-02
3551.6	2	4	3.7E-02
3557.8	2	2	1.9E-01
3561.2	4	6	2.1E-01
3565.8	4	4	6.2E-01
3568.5	6	8	1.4E+00
3571.2	4	4	6.3E-01
3574.2	6	6	1.0E-01
3574.6	4	6	1.3E+00
3590.4	4	6	3.6E-02
3594.2	4	2	1.3E+00
3612.3	2	4	2.6E-01
3628.0	4	4	6.0E-01
3632.7	4	4	1.3E-01
3643.9	4	4	3.2E-01
3644.9	2	4	9.9E-01
3659.9	4	6	6.7E-02
3664.1	6	4	7.0E-01
3679.8	4	2	3.2E-01
3694.2	6	6	1.0E+00
3697.1	2	2	2.8E-01
3701.8	4	6	2.7E-01
3709.6	4	2	1.1E+00
3713.1	4	6	1.3E+00
3721.8	4	6	2.0E-01
3726.9	4	4	1.2E-01
3727.1	2	4	9.8E-01
3734.9	4	4	1.9E-01
3744.6	2	4	2.6E-01
3751.2	2	2	1.8E-01
3753.8	4	6	4.5E-01
3766.3	4	6	2.9E-01
3777.1	2	4	4.2E-01
3800.0	4	4	3.7E-01
3818.4	2	4	6.1E-01
3829.8	4	6	8.4E-01
3942.3	4	6	1.0E-02
Ne V			
*142.61	9	9	6.7E+02
*143.32	9	15	1.2E+03
147.13	5	7	1.5E+03
151.23	5	5	3.38E+02
154.50	1	3	7.0E+02
*167.69	9	9	1.5E+02
*358.93	9	3	2.1E+02
365.59	5	3	1.35E+02
*482.15	9	9	3.01E+01
*571.04	9	15	1.0E+01
2259.6	3	5	1.9E+00
2265.7	5	7	2.4E+00
Ne VII			
97.502	1	3	1.07E+03
*115.46	9	3	4.8E+02
116.69	3	5	1.6E+03
127.66	3	1	1.9E+02
465.22	1	3	4.09E+01
558.61	3	5	8.11E+00
559.95	1	3	1.07E+01
561.38	3	3	7.99E+00
561.73	5	5	2.39E+01
562.99	3	1	3.17E+01
564.53	5	3	1.31E+01
Ne VIII			
*88.09	2	6	8.4E+02
*98.208	6	10	2.77E+03
770.41	2	4	5.90E+00
780.32	2	2	5.69E+00
2820.7	2	4	7.20E-01
2860.1	2	2	6.88E-01
Nickel			
Ni I			
1963.85	7	7	1.1E-01
1976.87	7	9	1.1E+00
1981.61	5	5	1.3E-01
1990.25	5	7	8.3E-01
2007.01	5	5	1.7E-01
2007.69	7	7	9.0E-02
2014.25	3	5	9.3E-01
2025.40	7	5	2.3E-01
2026.62	9	7	2.4E-01
2047.35	7	5	1.8E-01
2052.04	9	9	9.7E-02
2055.50	5	3	3.3E-01
2059.92	7	5	2.1E-01
2060.20	5	3	2.3E-01
2064.39	3	1	4.0E-01
2069.52	5	5	1.1E-01
2085.57	5	5	2.6E+00
2089.09	7	5	9.7E-02
2095.13	5	7	1.1E-01
2114.43	5	5	9.7E-02
2121.40	7	5	2.8E-01
2124.80	5	3	3.8E-01
2147.80	5	3	4.7E-01
2157.83	5	3	4.1E-01
2158.31	7	5	6.9E-01
2161.04	5	5	1.3E-01
2173.54	5	3	1.5E-01
2174.48	3	1	8.9E-01
2182.38	7	5	1.3E-01
2183.91	5	5	1.2E-01
2190.22	5	5	3.0E-01
2197.35	3	3	7.8E-01
2201.59	5	3	7.3E-01
2221.94	5	3	2.2E-01
2244.46	5	5	3.8E-01
2253.57	7	7	1.9E-01
2254.81	9	9	9.6E-02
2258.15	7	5	1.7E-01
2259.56	5	3	2.0E-01
2261.42	9	7	9.1E-02
2287.32	3	5	1.8E-01
2289.98	9	7	2.1E+00
2293.11	5	5	3.8E-01
2300.77	7	7	7.5E-01
2302.97	3	3	4.5E-01
2307.35	5	7	1.6E-01
2312.34	7	7	5.5E+00
2313.98	5	5	5.0E+00
2317.16	7	5	3.8E+00
2320.03	9	11	6.9E+00
2321.38	5	7	5.6E+00
2324.65	7	9	1.8E-01
2325.79	7	9	3.5E+00
2329.96	5	3	5.3E+00
2345.54	9	7	2.2E+00
2346.63	7	5	5.5E-01
2347.51	9	9	2.2E-01
2348.73	7	7	2.2E-01
2419.31	7	5	2.0E-01
2943.91	7	5	1.1E-01
2981.65	5	3	2.8E-01
3002.48	7	7	8.0E-01
3003.62	5	5	6.9E-01
3012.00	5	5	1.3E+00
3037.93	7	7	2.8E-01
3050.82	7	9	6.0E-01
3054.31	5	5	4.0E-01
3057.64	3	3	1.0E+00
3064.62	5	7	1.1E-01
3101.56	5	7	6.3E-01
3101.88	5	7	4.9E-01
3134.11	3	5	7.3E-01
3225.02	5	3	9.3E-02
3369.56	9	7	1.8E-01
3380.57	5	3	1.3E+00
3392.98	7	7	2.4E-01
3414.76	7	9	5.5E-01
3423.71	3	3	3.3E-01
3433.56	7	7	1.7E-01
3446.26	5	5	4.4E-01
3452.88	5	7	9.8E-02
3458.46	3	5	6.1E-01
3461.66	7	9	2.7E-01
3472.55	5	7	1.2E-01
3483.77	5	3	1.4E-01
3492.96	5	3	9.8E-01
3510.33	3	1	1.2E+00
3515.05	5	7	4.2E-01
3524.54	7	5	1.0E+00
3566.37	5	5	5.6E-01
3597.70	3	3	1.4E-01
3619.39	5	7	6.6E-01
4027.67	5	7	1.3E-01
4295.88	9	7	1.7E-01
4401.54	9	11	3.8E-01
4462.46	3	5	1.7E-01
4470.48	5	7	1.9E-01
4600.37	5	3	2.6E-01
4604.99	9	7	2.3E-01
4606.23	5	3	1.0E-01
4648.66	11	9	2.4E-01
4686.22	5	5	1.4E-01
4701.54	9	9	1.4E-01
4714.42	13	11	4.6E-01
4715.78	7	7	2.0E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
4732.47	7	9	9.3E-02
4752.43	3	3	2.0E-01
4756.52	9	9	1.5E-01
4786.54	11	11	1.8E-01
4812.00	3	1	9.5E-02
4829.03	5	7	1.9E-01
4831.18	9	7	1.6E-01
4838.64	9	7	2.2E-01
4855.41	5	5	5.7E-01
4904.41	5	3	6.2E-01
4912.03	3	3	1.5E-01
4913.97	1	3	2.2E-01
4918.36	9	7	2.3E-01
4935.83	7	5	2.4E-01
4937.34	9	9	1.2E-01
4953.20	5	5	1.2E-01
4980.17	9	11	1.9E-01
5000.34	7	7	1.4E-01
5012.46	7	7	1.1E-01
5017.58	11	11	2.0E-01
5035.37	7	9	5.7E-01
5042.20	3	5	1.4E-01
5048.85	7	7	1.6E-01
5080.53	9	11	3.2E-01
5081.11	7	9	5.7E-01
5082.35	3	3	2.5E-01
5084.08	7	9	3.1E-01
5099.95	7	7	2.9E-01
5115.40	11	9	2.2E-01
5129.37	7	5	1.2E-01
5155.14	5	5	1.1E-01
5155.76	5	7	2.9E-01
5176.57	5	5	1.8E-01
5371.33	7	7	1.6E-01
5476.91	1	3	9.5E-02
5637.12	3	3	1.1E-01
5664.02	5	7	1.1E-01
5695.00	3	3	1.7E-01
6086.29	3	5	1.1E-01
6175.42	3	3	1.7E-01
7122.24	5	7	2.1E-01
7381.94	9	11	9.7E-02
7422.30	7	5	1.8E-01
7727.66	7	7	1.1E-01
Ni II			
2165.55	10	10	2.4E+00
2169.10	8	8	1.58E+00
2174.67	8	10	1.43E+00
2175.15	6	6	1.77E+00
2184.61	4	4	2.90E+00
2201.41	4	6	1.3E+00
2206.72	6	8	1.66E+00
2216.48	10	12	3.4E+00
2220.40	6	8	2.3E+00
2222.96	10	10	9.8E-01
2224.86	8	8	1.55E+00
2226.33	6	6	1.3E+00
2253.85	4	6	1.98E+00
2264.46	6	8	1.43E+00
2270.21	8	10	1.56E+00
2278.77	8	6	2.8E+00
2287.09	6	4	2.8E+00
2296.55	8	8	1.98E+00
2297.14	6	4	2.70E+00
2297.49	4	2	3.0E+00
2298.27	6	6	2.8E+00
2303.00	8	6	2.9E+00
2316.04	10	8	2.88E+00
2334.58	8	8	8.0E-01
2375.42	6	8	6.6E-01
2394.52	8	10	1.70E+00
2416.13	6	8	2.1E+00
2437.89	8	10	5.4E-01
2510.87	8	10	5.8E-01
Ni III			
1692.51	11	13	7.9E+00
1709.90	9	11	6.3E+00
1719.46	5	7	6.0E+00
1722.28	3	5	5.9E+00
1724.52	3	1	6.7E+00
1741.96	9	7	5.7E+00
1752.43	7	5	5.5E+00
1760.56	5	3	6.5E+00
1769.64	11	11	6.2E+00
1823.06	9	9	5.6E+00
Ni XIV			
164.13	6	8	1.2E+03
168	2	4	2.4E+02
168.12	4	2	8.5E+02
169.69	4	4	9.8E+02
170.50	4	4	7.1E+02
171.37	4	6	9.4E+02
172.16	6	6	4.7E+02
172.80	6	4	1.4E+02
177.28	4	4	5.6E+02
178	2	4	8.9E+01
181	4	6	7.4E+01
182.14	4	2	1.5E+02
196	4	2	3.8E+01
288.894	4	4	4.6E+01
292.399	6	6	3.6E+01
Ni XV			
50.249	5	7	6.8E+03
60.890	9	11	1.0E+04
64.635	7	9	9.6E+03
163.64	5	7	5.6E+01
173.73	5	7	7.6E+02
175	3	1	5.7E+02
179.28	5	7	7.5E+02
181	1	3	6.8E+02
269	3	1	5.3E+01
278.386	5	5	4.3E+01
Ni XVI			
166	4	6	3.1E+02
168	6	8	3.2E+02
182	2	2	2.5E+02
185.23	2	4	4.2E+02
187	4	6	1.2E+02
187	4	2	3.3E+02
188	2	2	4.7E+02
190	6	8	2.0E+02
192	6	8	4.54E+02
192	6	6	3.1E+02
194	4	6	2.8E+02
194	2	4	5.5E+02
194	2	2	1.1E+02
194	4	4	3.5E+02
194.04	4	6	4.6E+02
195.27	4	4	9.5E+01
196	4	6	6.7E+02
197	4	6	1.5E+02
197	4	2	1.2E+02
199	2	4	4.9E+02
206	2	2	3.7E+02
217	4	4	1.1E+02
218.391	2	4	9.5E+01
223.119	2	2	1.3E+02
231	4	4	1.6E+02
232.475	4	4	4.07E+02
233	6	4	2.4E+02
235	4	2	3.8E+02
235	6	6	2.5E+02
236	4	4	1.2E+02
237.875	4	2	2.6E+02
238	6	4	1.3E+02
239.550	2	2	2.6E+02
245	4	4	1.4E+02
245	4	6	3.2E+02
249	6	8	3.3E+02
249	6	4	1.2E+02
250	4	2	1.6E+02
254	6	4	1.8E+02
Ni XVII			
30.919	1	3	2.77E+03
42.855	1	3	4.75E+03
54.451	9	11	1.5E+04
55.361	1	3	6.7E+03
57.348	7	9	1.4E+04
197.39	1	3	1.6E+02
199.87	3	5	2.1E+02
204	3	3	1.8E+02
205	3	1	2.4E+02
206	1	3	3.0E+02
207.50	5	7	2.5E+02
215.89	3	5	4.8E+02
216	1	3	2.7E+02
217	5	7	2.4E+02
227	5	5	1.6E+02
249.180	1	3	2.75E+02
281.50	3	1	2.1E+02
282	3	1	2.4E+02
284	5	3	1.5E+02
292	5	7	2.2E+02
Ni XVIII			
24.881	2	4	8.6E+02
25.070	4	6	9.9E+02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
26.02	2	4	1.26E+03
26.020	2	4	1.1E+03
26.046	2	2	1.1E+03
26.218	4	6	1.5E+03
27.98	4	6	1.0E+03
27.982	2	4	2.0E+03
28.018	6	8	1.1E+03
28.220	4	6	2.33E+03
29.383	4	6	1.58E+03
29.422	6	8	1.69E+03
29.779	2	4	1.9E+03
29.829	2	2	1.9E+03
31.845	4	6	2.7E+03
31.890	6	8	3.0E+03
32.034	2	4	3.4E+03
32.340	4	6	4.0E+03
36.990	4	6	5.5E+03
37.049	6	8	5.9E+03
41.015	2	4	2.97E+03
41.218	2	2	3.2E+03
43.814	2	4	5.5E+03
44.365	4	6	6.8E+03
44.405	4	4	1.14E+03
52.615	4	6	1.5E+04
52.720	6	8	1.6E+04
52.745	6	6	1.06E+03
59.950	6	4	9.6E+02
60.212	4	2	1.1E+03
63.512	4	6	7.9E+02
63.589	6	8	8.5E+02
69.075	4	6	8.0E+02
76.254	4	6	1.38E+03
76.359	6	8	1.47E+03
99.275	2	4	1.0E+03
100.4	4	6	1.2E+03
114.46	4	6	2.5E+03
114.74	6	8	2.7E+03
Ni XIX			
9.140	1	3	3.1E+04
9.153	1	3	5.2E+03
9.977	1	3	1.1E+05
10.110	1	3	9.4E+04
10.283	1	3	4.7E+03
10.433	1	3	5.1E+03
11.539	1	3	4.8E+04
11.599	1	3	6.3E+03
12.435	1	3	3.66E+05
12.656	1	3	1.0E+05
13.779	1	3	1.23E+04
14.043	1	3	1.31E+04
40.7	3	3	6.4E+03
40.7	3	1	8.4E+03
41.132	7	9	9.4E+03
Ni XXI			
11.13	3	3	1.7E+04
11.23	5	3	1.7E+04
11.239	5	7	5.7E+04
11.28	3	1	2.2E+05
11.318	5	7	2.8E+05
11.48	3	1	1.1E+05
11.48	1	3	4.0E+05
11.517	5	7	1.4E+05
11.539	5	7	1.2E+05
11.67	1	3	8.0E+04
11.72	3	3	2.3E+04
12.454	5	3	3.3E+04
12.472	3	3	1.8E+04
12.502	5	5	2.8E+04
Ni XXII			
72.52	4	2	2.84E+02
84.06	6	4	1.2E+03
84.24	4	2	5.6E+02
85.86	4	2	4.9E+02
88.00	4	2	1.2E+03
95.95	2	2	4.4E+02
98.16	4	4	5.2E+02
98.58	4	4	2.45E+02
100.60	6	6	3.9E+02
101.31	6	4	4.83E+02
103.31	4	2	2.66E+02
106.04	4	4	2.36E+02
106.16	4	2	5.1E+02
124.31	2	2	3.7E+02
126.32	4	4	3.3E+02
Ni XXIII			
87.66	3	3	2.8E+02
88.11	5	3	8.3E+02
90.49	3	3	1.77E+02
90.96	5	3	2.5E+02
91.83	5	3	7.5E+02
92.32	3	1	4.39E+02
100.42	1	3	2.1E+02
102.08	5	5	5.3E+02
103.23	3	3	2.4E+02
103.67	5	5	1.78E+02
104.70	3	1	2.94E+02
106.02	5	5	2.87E+02
108.27	7	5	3.32E+02
111.23	3	1	2.26E+02
111.78	5	3	2.19E+02
111.86	1	3	1.7E+02
112.55	3	1	1.0E+03
128.87	5	5	4.02E+02
133.54	3	3	1.86E+02
137.55	3	1	2.53E+02
Ni XXIV			
101.13	6	4	1.63E+02
102.11	4	4	5.4E+02
103.43	2	4	1.3E+02
103.53	4	2	4.17E+02
104.64	2	2	4.7E+02
106.68	4	2	3.67E+02
113.14	4	4	1.65E+02
118.52	2	4	1.5E+02
122.72	6	4	2.17E+02
134.73	6	6	1.44E+02
135.47	4	4	8.0E+01
137.01	4	4	2.6E+02
138.80	4	6	7.2E+01
153.47	2	2	1.27E+02
159.69	2	4	8.9E+01
Ni XXV			
9.30	3	1	9.3E+04
9.31	5	7	8.2E+04
9.32	3	5	7.8E+04
9.34	1	3	1.1E+05
9.42	3	1	9.0E+04
9.49	3	5	8.9E+04
9.60	1	3	1.8E+05
9.63	3	5	2.4E+05
9.64	3	3	1.3E+05
9.71	3	1	2.3E+05
9.71	3	3	1.8E+05
9.74	5	7	3.0E+05
9.75	3	5	1.3E+05
9.76	1	3	3.03E+05
9.76	5	3	7.5E+04
9.78	5	7	2.9E+05
9.86	5	7	4.8E+05
9.87	3	5	2.03E+05
9.92	5	5	1.3E+05
9.94	5	7	1.29E+05
9.97	3	5	2.5E+05
10.08	1	3	2.80E+05
Ni XXVI			
1.5930	4	2	3.4E+06
1.5935	2	2	4.0E+06
1.5973	4	4	8.1E+06
1.5977	2	4	4.4E+06
1.5982	2	2	7.3E+06
1.5996	2	2	2.7E+06
1.6005	4	6	2.7E+06
1.6036	4	2	2.1E+06
9.390	2	4	2.59E+05
9.535	4	6	2.96E+05
Ni XXVII			
1.2534	1	3	3.35E+05
1.2824	1	3	6.38E+05
1.3500	1	3	1.63E+06
1.3516	1	3	2.4E+05
1.531	3	3	2.0E+05
1.534	3	1	6.9E+06
1.537	5	5	2.3E+06
1.537	1	3	3.7E+06
1.538	3	5	3.9E+06
1.539	1	3	2.6E+06
1.539	3	5	2.6E+06
1.540	3	3	1.7E+06
1.541	3	5	5.5E+06
1.542	3	3	3.6E+06
1.542	5	5	3.5E+06
1.544	5	3	3.2E+06
1.546	3	5	1.6E+06
1.547	3	3	2.1E+05
1.549	1	3	2.0E+05

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
1.551	3	1	8.2E+05
1.558	3	1	6.5E+05
1.5883	1	3	6.02E+06
1.5963	1	3	7.70E+05
Nitrogen			
N I			
1163.88	6	6	7.52E-01
1164.00	4	6	1.27E-02
1164.21	6	4	5.17E-02
1164.32	4	4	6.94E-01
1167.45	6	8	1.29E+00
1168.42	6	6	4.24E-02
1168.54	4	6	1.24E+00
1176.51	6	4	9.22E-01
1176.63	4	4	1.02E-01
1177.69	4	2	1.02E+00
1199.55	4	6	4.01E+00
1200.22	4	4	3.99E+00
1200.71	4	2	3.98E+00
1310.54	4	6	8.42E-01
1316.29	4	6	1.42E-02
1492.63	6	4	3.13E+00
1492.82	4	4	3.51E-01
1494.68	4	2	3.72E+00
3822.03	2	2	3.70E-02
3830.43	4	4	4.67E-02
3834.22	4	2	1.89E-02
4099.94	2	4	3.48E-02
4109.95	4	6	3.90E-02
4113.97	4	4	6.62E-03
4137.64	2	4	2.80E-03
4143.43	4	4	6.09E-03
4151.48	6	4	1.01E-02
4249.87	4	2	2.59E-02
4264.00	6	4	2.26E-02
4356.29	6	8	5.10E-02
4385.54	2	2	8.84E-03
4392.41	4	2	1.76E-02
4435.43	2	4	7.51E-03
4442.45	4	4	3.81E-02
4669.89	4	4	7.49E-03
4914.94	2	2	8.08E-03
4935.12	4	2	1.76E-02
5199.84	2	2	1.87E-02
5201.61	2	4	1.87E-02
5281.20	6	6	2.45E-03
5344.05	6	6	6.10E-04
5356.62	4	6	1.41E-03
5367.01	4	4	1.07E-03
5372.61	2	4	8.34E-04
5378.27	2	2	1.66E-03
6606.18	4	6	8.87E-04
6622.54	6	6	7.93E-03
6626.99	2	4	2.20E-03
6636.94	4	4	1.40E-02
6644.96	8	6	3.49E-02
6646.50	2	2	2.18E-02
6653.46	6	4	2.74E-02
6656.51	4	2	2.17E-02
6926.67	4	6	7.75E-03
6945.18	6	6	1.83E-02
6951.60	2	4	1.03E-02
6960.50	4	4	4.67E-03
6973.07	2	2	3.83E-03
6979.18	6	4	9.83E-03
6982.03	4	2	2.04E-02
7423.64	2	4	5.95E-02
7442.30	4	4	1.24E-01
7468.31	6	4	1.93E-01
7898.98	6	4	2.82E-01
7899.28	4	4	3.28E-02
7915.42	4	2	3.13E-01
8184.86	4	6	8.58E-02
8188.01	2	4	1.27E-01
8200.36	2	2	4.95E-02
8210.72	4	4	4.84E-02
8216.34	6	6	2.23E-01
8223.13	4	2	2.64E-01
8242.39	6	4	1.36E-01
8567.74	2	4	4.92E-02
8594.00	2	2	2.09E-01
8629.24	4	4	2.66E-01
8655.88	4	2	1.05E-01
8680.28	6	8	2.46E-01
8683.40	4	6	1.80E-01
8686.15	2	4	1.09E-01
8703.25	2	2	2.10E-01
8711.70	4	4	1.28E-01
8718.84	6	6	6.75E-02
8728.90	4	2	3.76E-02
8747.37	6	4	1.04E-02
9028.92	2	2	3.02E-01
9045.88	6	8	2.80E-01
9049.49	6	6	1.88E-02
9049.89	4	6	2.60E-01
9060.48	2	4	2.95E-01
9187.45	6	6	2.44E-01
9187.86	4	6	1.76E-02
9207.59	6	4	2.70E-02
9208.00	4	4	2.33E-01
9386.81	2	4	2.24E-01
9392.79	4	6	2.63E-01
9460.68	4	4	3.98E-02
9776.90	2	4	1.18E-02
9786.78	4	6	1.13E-02
9788.29	2	2	2.99E-02
9798.56	4	4	2.75E-02
9810.01	4	2	5.30E-02
9814.02	6	8	6.56E-03
9822.75	6	6	4.95E-02
9834.61	6	4	4.50E-02
9863.33	8	8	9.62E-02
9872.15	8	6	2.97E-02
9883.38	2	2	2.93E-02
9905.52	4	2	3.11E-03
9909.22	2	4	7.58E-03
9931.47	4	4	3.64E-02
9947.07	6	8	1.08E-02
9965.75	4	6	7.60E-03
9968.51	6	4	4.50E-03
9980.42	4	6	8.10E-03
9997.73	8	8	9.20E-03
N II			
474.891	5	5	9.66E+00
475.647	1	3	1.17E+01
475.698	3	5	1.58E+01
475.757	3	3	8.75E+00
475.803	5	7	2.10E+01
475.884	5	5	5.25E+00
508.697	5	5	1.91E+00
510.758	5	7	1.87E+01
513.849	5	5	1.24E+01
529.355	1	3	7.23E+00
529.413	3	1	2.43E+01
529.491	3	3	6.75E+00
529.637	3	5	4.92E+00
529.722	5	3	1.03E+01
529.867	5	5	1.94E+01
533.511	1	3	2.39E+01
533.581	3	5	3.20E+01
533.650	3	3	1.66E+01
533.729	5	7	4.13E+01
533.815	5	5	9.19E+00
547.818	5	3	2.16E+00
559.762	1	3	1.14E+01
574.650	5	7	3.60E+01
582.156	5	5	2.85E+01
635.197	1	3	2.33E+01
644.634	1	3	1.21E+01
644.837	3	3	3.64E+01
645.178	5	3	6.07E+01
660.286	5	3	3.69E+01
671.016	3	5	2.47E+00
671.386	5	5	7.40E+00
671.411	1	3	3.04E+00
671.630	3	3	2.27E+00
671.773	3	1	9.85E+00
672.001	5	3	3.87E+00
745.841	1	3	1.25E+01
746.984	5	3	3.85E+01
748.369	5	3	3.83E+00
775.965	5	5	3.08E+01
915.612	1	3	4.38E+00
915.962	3	1	1.32E+01
1083.99	1	3	2.18E+00
1085.55	5	5	9.47E-01
1085.70	5	7	3.87E+00
3408.13	3	1	2.19E-01
3437.14	3	1	2.07E+00
3593.60	3	5	1.21E-01
3609.10	3	3	1.41E-01
3615.86	3	1	1.53E-01
3829.80	3	5	2.42E-01
3838.37	5	5	6.98E-01
3842.19	1	3	3.06E-01
3847.40	3	3	2.22E-01
3855.10	3	1	8.82E-01
3856.06	5	3	3.71E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3919.00	3	3	6.76E-01
3955.85	3	5	1.31E-01
3995.00	3	5	1.35E+00
4114.33	3	3	1.42E-03
4124.08	3	5	3.20E-01
4133.67	5	5	5.30E-01
4145.77	7	5	7.36E-01
4374.99	3	5	5.55E-03
4447.03	3	5	1.14E+00
4459.94	3	1	1.12E-01
4465.53	3	3	2.36E-02
4477.68	5	3	8.85E-02
4488.09	5	5	1.30E-02
4507.56	7	5	1.00E-01
4564.76	3	5	1.41E-02
4601.48	3	5	2.35E-01
4607.15	1	3	3.26E-01
4613.87	3	3	2.26E-01
4621.39	3	1	9.55E-01
4630.54	5	5	7.72E-01
4643.09	5	3	4.51E-01
4654.53	3	5	2.43E-02
4667.21	3	3	2.99E-02
4674.91	3	1	1.05E-01
4694.27	1	3	1.23E-01
4695.90	3	5	1.29E-01
4697.64	3	3	3.06E-02
4698.55	3	1	3.67E-01
4700.03	5	7	1.05E-01
4702.50	5	5	9.15E-02
4704.25	5	3	2.13E-01
4706.40	7	9	6.09E-02
4709.58	7	7	1.82E-01
4712.07	7	5	1.46E-01
4718.38	9	9	3.02E-01
4721.58	9	7	7.75E-02
4774.24	3	5	3.24E-02
4779.72	3	3	2.52E-01
4781.19	5	7	2.05E-02
4788.14	5	5	2.52E-01
4793.65	5	3	7.77E-02
4803.29	7	7	3.18E-01
4810.30	7	5	4.75E-02
4860.17	3	5	1.61E-02
4987.38	3	1	7.48E-01
4991.24	3	5	3.54E-01
4994.36	5	7	2.62E-01
4994.37	3	3	7.60E-01
4997.22	3	3	1.96E-01
5001.13	3	5	9.76E-01
5001.47	5	7	1.05E+00
5002.70	1	3	8.45E-02
5005.15	7	9	1.16E+00
5005.30	5	5	6.51E-02
5007.33	3	5	7.89E-01
5010.62	3	3	2.19E-01
5011.31	5	3	5.84E-01
5012.04	7	7	5.19E-01
5016.38	5	5	1.62E-01
5023.05	7	5	3.61E-01
5025.66	7	7	1.07E-01
5040.71	7	5	3.78E-03
5045.10	5	3	3.42E-01
5073.59	3	3	2.59E-02
5168.05	3	5	3.06E-01
5170.16	3	3	6.54E-01
5171.27	3	1	8.71E-01
5171.47	5	7	5.81E-01
5172.34	3	5	6.01E-01
5172.97	1	3	5.01E-01
5173.39	5	7	7.36E-01
5174.46	5	5	5.07E-01
5175.89	7	9	8.93E-01
5176.57	5	3	2.17E-01
5177.06	3	3	5.00E-01
5179.34	7	9	8.67E-01
5179.52	9	11	1.07E+00
5180.36	5	5	4.28E-01
5183.20	7	7	2.88E-01
5184.96	7	7	3.20E-01
5185.09	5	3	7.11E-02
5186.21	7	5	5.76E-02
5190.38	9	9	1.77E-01
5191.96	7	5	4.25E-02
5199.50	9	7	1.51E-02
5313.42	3	3	1.41E-01
5320.20	5	3	4.20E-01
5320.96	3	5	2.52E-01
5327.76	5	5	4.65E-02
5338.73	5	7	1.85E-01
5340.21	7	5	2.59E-01
5351.23	7	7	3.67E-01
5383.72	3	5	3.31E-03
5452.07	1	3	8.89E-02
5454.22	3	1	3.34E-01
5462.58	3	3	1.00E-01
5478.09	3	5	4.75E-02
5480.05	5	3	1.30E-01
5495.65	5	5	2.40E-01
5526.23	3	5	2.13E-01
5530.24	5	7	4.04E-01
5535.35	7	9	6.04E-01
5535.38	3	3	4.53E-01
5540.06	3	1	6.03E-01
5543.47	5	5	3.51E-01
5551.92	7	7	2.00E-01
5552.68	5	3	1.50E-01
5565.26	7	5	3.97E-02
5666.63	3	5	3.74E-01
5676.02	1	3	2.96E-01
5679.56	5	7	5.25E-01
5686.21	3	3	1.94E-01
5710.77	5	5	1.24E-01
5730.66	5	3	1.34E-02
5747.30	3	5	3.40E-02
5767.45	3	3	2.44E-02
5893.15	5	7	2.88E-01
5897.25	3	5	2.16E-01
5899.83	1	3	1.60E-01
5927.81	1	3	3.22E-01
5931.78	3	5	4.27E-01
5940.24	3	3	2.26E-01
5941.65	5	7	5.54E-01
5952.39	5	5	1.27E-01
5960.91	5	3	1.34E-02
6065.00	3	5	2.21E-03
6284.32	5	3	7.74E-02
6379.62	3	3	6.11E-02
6482.05	3	3	3.01E-01
6610.56	5	7	6.34E-01
6857.03	5	3	2.53E-01
6869.58	5	5	2.51E-01
6887.83	5	7	2.49E-01
7762.24	5	5	8.74E-02
8438.74	1	3	2.24E-01
8831.75	1	3	8.42E-03
8855.30	3	3	2.51E-02
8893.29	5	3	4.12E-02
N III			
374.198	2	4	9.89E+01
451.871	2	2	1.03E+01
452.227	4	2	2.05E+01
684.998	2	4	9.63E+00
685.515	2	2	3.83E+01
685.817	4	4	4.54E+01
686.336	4	2	1.95E+01
763.334	2	2	9.58E+00
764.351	4	2	1.85E+01
771.545	2	4	8.19E+00
771.901	4	4	1.64E+01
772.384	6	4	2.45E+01
772.889	6	4	2.09E+01
772.955	4	2	2.34E+01
979.832	4	4	8.84E+00
979.905	6	6	9.21E+00
989.799	2	4	4.18E+00
991.511	4	4	8.17E-01
991.577	4	6	4.97E+00
1747.85	2	4	1.28E+00
1751.22	4	4	2.48E-01
1751.66	4	6	1.51E+00
2972.55	2	2	6.67E-01
2977.33	4	2	3.32E-01
2978.84	2	4	1.66E-01
2983.64	4	4	8.24E-01
3342.76	2	2	3.80E-01
3353.98	2	4	7.66E-01
3354.32	4	6	5.51E-01
3355.46	4	2	7.51E-01
3358.78	2	2	3.05E-01
3360.98	4	4	2.44E-01
3365.80	4	2	1.52E+00
3367.36	6	6	1.27E+00
3374.07	6	4	8.13E-01
3745.95	2	4	1.90E-01
3752.63	2	2	6.67E-02
3754.69	4	4	3.78E-01
3762.60	4	4	4.24E-02
3771.03	6	4	5.59E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3771.36	6	4	8.28E-02
3792.97	8	6	1.03E-01
3934.50	2	4	7.49E-01
3938.51	4	6	8.96E-01
3942.88	4	4	1.49E-01
4097.36	2	4	8.70E-01
4103.39	2	2	8.67E-01
4195.74	2	4	9.37E-01
4200.07	4	6	1.12E+00
4215.77	4	4	1.85E-01
4318.78	2	4	5.40E-02
4321.22	2	2	1.08E-01
4321.39	4	6	5.03E-02
4325.43	4	4	8.60E-02
4327.69	6	8	3.06E-02
4327.88	4	2	1.07E-01
4332.95	6	6	1.23E-01
4337.01	6	4	7.47E-02
4345.81	8	8	1.82E-01
4351.11	8	6	4.01E-02
4510.88	2	4	2.84E-01
4510.96	4	6	4.77E-01
4514.85	6	8	6.80E-01
4518.14	2	2	5.65E-01
4523.56	4	4	3.61E-01
4530.86	4	2	1.12E-01
4534.58	6	6	2.01E-01
4547.30	6	4	3.33E-02
4634.13	2	4	6.36E-01
4640.64	4	6	7.60E-01
4641.85	4	4	1.26E-01
4858.70	2	4	4.35E-01
4858.98	4	6	4.66E-01
4861.27	6	8	5.32E-01
4867.12	4	4	1.73E-01
4867.17	8	10	6.18E-01
4873.60	6	6	1.50E-01
4881.78	6	4	1.22E-02
4884.14	8	8	8.71E-02
4896.58	8	6	5.86E-03
5260.86	2	2	2.80E-02
5270.57	2	4	6.95E-02
5272.68	4	2	1.39E-01
5282.43	4	4	2.21E-02
5297.75	4	6	4.93E-02
5298.95	6	4	7.38E-02
5314.36	6	6	1.14E-01
5320.87	6	8	5.68E-01
5327.19	4	6	5.29E-01
5352.46	6	6	3.72E-02
6365.84	2	2	2.18E-01
6394.75	2	4	2.15E-01
6445.34	2	4	8.89E-02
6450.79	2	2	1.77E-01
6454.08	4	6	1.49E-01
6463.09	4	4	1.13E-01
6467.02	6	8	2.11E-01
6468.57	4	2	3.52E-02
6478.76	6	6	6.31E-02
6487.84	6	4	1.05E-02
7371.51	4	4	3.53E-02
7404.54	6	6	3.61E-02
8307.51	2	4	1.65E-02
8344.95	2	2	6.52E-02
8386.39	4	4	8.03E-02
8424.56	4	2	3.17E-02
N IV			
247.205	1	3	1.19E+02
*283.52	9	15	3.05E+02
*322.64	9	3	8.99E+01
335.047	3	5	1.845E+02
387.356	3	1	2.55E+01
765.147	1	3	2.320E+01
*923.16	9	9	1.759E+01
955.334	3	1	2.919E+01
1718.55	3	5	2.321E+00
2649.88	3	3	1.07E+00
3052.20	1	3	1.33E-01
3059.60	3	3	3.95E-01
3075.19	5	3	6.48E-01
3443.61	3	5	3.46E-01
3445.22	1	3	4.60E-01
3454.65	3	3	3.42E-01
3461.36	3	1	1.36E+00
3463.36	5	5	1.02E+00
3474.53	5	3	5.61E-01
3478.72	3	5	1.06E+00
*3480.8	3	9	1.06E+00
3483.00	3	3	1.06E+00
3484.93	3	1	1.06E+00
3689.94	3	1	9.10E-02
3694.14	3	3	2.27E-02
3707.39	5	3	6.73E-02
3714.43	5	5	1.34E-02
3735.43	7	5	7.37E-02
3747.54	3	5	9.92E-01
4057.76	3	5	6.62E-01
4740.26	3	5	1.53E-02
4747.96	3	3	7.60E-02
4752.49	5	7	1.13E-02
4762.09	5	5	6.99E-02
4769.86	5	3	2.50E-02
4786.92	7	7	8.79E-02
4796.66	7	5	1.53E-02
5200.41	3	5	2.67E-01
5204.28	5	7	3.55E-01
5205.15	1	3	1.97E-01
5226.70	3	3	1.46E-01
5245.60	5	5	8.66E-02
5272.35	5	3	9.48E-03
5288.25	5	3	3.22E-02
5736.93	3	5	1.84E-01
5776.31	1	3	1.85E-02
5784.76	3	1	5.51E-02
5795.09	3	3	1.37E-02
5812.31	3	5	1.36E-02
5826.43	5	3	2.25E-02
5843.84	5	5	4.01E-02
6380.75	1	3	1.42E-01
7103.24	1	3	6.28E-02
7109.35	3	5	8.46E-02
7111.28	3	3	4.70E-02
*7116.8	9	15	1.12E-01
7122.98	5	7	1.12E-01
7127.25	5	5	2.80E-02
7127.25	5	3	3.11E-03
9165.07	3	5	4.23E-02
9182.16	5	7	4.45E-02
9222.99	7	9	4.95E-02
9247.04	5	5	7.66E-03
9311.55	7	7	5.36E-03
N V			
*209.29	2	6	1.21E+02
*247.66	6	10	4.26E+02
1238.82	2	4	3.40E+00
1242.80	2	2	3.37E+00
4603.74	2	4	4.14E-01
4619.97	2	2	4.10E-01
N VI			
24.8980	1	3	5.158E+03
28.7870	1	3	1.809E+04
*161.220	3	9	2.859E+02
173.275	1	3	2.697E+02
*173.93	9	15	8.756E+02
185.192	3	5	8.205E+02
*1901	3	9	6.780E-01
2896.4	1	3	2.079E-01
*6991.1	3	9	8.384E-02
9622.0	1	3	3.276E-02
Oxygen			
O I			
791.973	5	5	4.94E+00
792.938	1	3	2.19E+00
792.967	3	5	1.64E+00
877.798	5	3	2.85E+00
877.879	5	5	5.12E+00
922.008	5	7	1.23E+00
935.193	5	5	1.33E+00
1028.16	1	3	4.22E-01
1152.15	5	5	5.28E+00
1217.65	1	3	2.06E+00
1302.17	5	3	3.41E+00
1304.86	3	3	2.03E+00
1306.03	1	3	6.76E-01
3823.41	7	7	6.63E-03
3823.87	5	3	1.87E-03
3824.35	5	5	5.19E-03
3825.02	3	3	5.59E-03
3825.19	5	7	8.31E-04
3855.01	5	5	1.63E-02
3947.29	5	7	4.91E-03
3947.48	5	5	4.88E-03
3947.59	5	3	4.87E-03
3951.93	3	1	3.10E-03
3952.98	5	3	1.29E-03
3953.00	1	3	1.03E-03
3954.52	3	5	7.73E-04

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3954.61	5	5	2.32E-03
3997.95	5	3	2.41E-02
4217.09	3	1	5.44E-03
4222.77	5	3	2.26E-03
4222.82	1	3	1.81E-03
4233.27	5	5	4.04E-03
4368.19	3	1	7.56E-03
4368.24	3	5	7.59E-03
4967.38	3	5	4.43E-03
4967.88	5	7	8.44E-03
4968.79	7	9	1.27E-02
5019.29	5	5	7.13E-03
5020.22	7	5	9.98E-03
5329.11	3	5	9.48E-03
5329.69	5	7	1.81E-02
5330.74	7	9	2.71E-02
5435.18	3	5	7.74E-03
5435.77	5	5	1.29E-02
5436.86	7	5	1.80E-02
5512.60	3	5	2.69E-03
5512.77	5	7	3.58E-03
5554.83	3	3	5.83E-03
5555.00	5	3	9.71E-03
5958.39	3	5	6.80E-03
5958.58	5	7	9.06E-03
6046.23	3	3	1.05E-02
6046.44	5	3	1.75E-02
6046.49	1	3	3.50E-03
6155.99	3	5	2.67E-02
6156.78	5	7	5.08E-02
6158.19	7	9	7.62E-02
6324.84	7	5	3.76E-05
6453.60	3	5	1.65E-02
6454.44	5	5	2.75E-02
6455.98	7	5	3.85E-02
6726.28	5	5	1.18E-05
6726.54	5	3	6.44E-06
7001.92	3	5	2.65E-02
7002.23	5	7	3.53E-02
7254.15	3	3	2.24E-02
7254.45	5	3	3.73E-02
7254.53	1	3	7.45E-03
7771.94	5	7	3.69E-01
7774.17	5	5	3.69E-01
7775.39	5	3	3.69E-01
7981.94	3	3	2.33E-04
7982.40	1	3	3.09E-04
7986.98	3	5	4.19E-04
7987.33	5	5	1.41E-04
7995.07	5	7	5.63E-04
8221.82	7	7	2.89E-01
8227.65	5	3	8.13E-02
8230.00	5	5	2.26E-01
8233.00	3	3	2.43E-01
8235.35	3	5	4.86E-02
8446.25	3	1	3.22E-01
8446.36	3	5	3.22E-01
8446.76	3	3	3.22E-01
8820.42	5	7	2.93E-01
9260.81	3	1	4.46E-01
9260.85	3	3	3.34E-01
9260.94	3	5	1.56E-01
9262.58	5	3	1.11E-01
9262.67	5	5	2.60E-01
9262.78	5	7	2.97E-01
9265.83	7	5	2.97E-02
9265.93	7	7	1.48E-01
9266.01	7	9	4.45E-01
9482.89	5	3	2.34E-01
9622.11	5	3	5.22E-04
9622.16	3	3	1.57E-03
9625.26	7	5	3.25E-04
9625.30	7	7	1.85E-03
9694.66	5	7	4.54E-04
9694.91	5	5	4.54E-04
9695.06	5	3	4.54E-04
O II			
429.918	4	2	4.25E+01
430.041	4	4	4.13E+01
430.176	4	6	4.36E+01
483.760	4	2	2.05E+01
483.980	6	4	1.80E+01
484.027	4	4	3.22E+00
485.087	6	8	2.60E+01
485.470	6	6	1.20E+00
485.518	4	6	1.93E+01
2290.85	2	4	7.41E-02
2293.30	2	2	3.25E-01
2300.33	4	4	4.17E-01
2302.81	4	2	1.67E-01
2365.14	4	2	1.52E-01
2375.72	6	4	1.35E-01
2406.38	6	4	1.85E-01
2407.48	4	4	2.25E-01
2411.60	4	2	2.05E-01
2411.64	2	2	1.10E-01
2415.13	4	2	2.20E-01
2418.46	6	6	2.30E-01
2425.57	6	6	1.77E-01
2433.54	2	4	4.21E-01
2436.06	4	4	1.69E-01
2444.25	4	4	7.56E-02
2445.53	4	6	4.98E-01
2517.96	4	6	7.72E-02
2523.21	2	2	9.63E-02
2526.87	4	4	1.20E-01
2530.28	6	8	8.16E-02
2571.46	2	4	1.15E-01
2575.28	4	6	1.37E-01
3134.73	8	6	1.23E+00
3273.43	8	6	9.99E-01
3377.15	2	2	1.27E+00
3390.21	2	4	1.22E+00
3407.28	6	6	1.02E+00
3712.74	2	4	2.84E-01
3727.32	4	4	5.81E-01
3749.48	6	4	9.31E-01
3833.07	6	8	1.02E-02
3842.81	2	4	7.45E-02
3843.58	4	6	3.55E-02
3847.89	2	2	1.95E-01
3850.80	4	6	6.00E-03
3851.03	4	4	1.59E-01
3851.47	8	8	2.72E-02
3856.13	4	2	2.28E-01
3857.16	6	6	6.59E-02
3863.50	6	8	6.49E-02
3864.13	2	2	9.12E-02
3864.43	6	6	2.15E-01
3864.67	6	4	1.80E-01
3874.09	2	4	3.26E-02
3875.80	8	6	3.38E-02
3882.19	8	8	5.50E-01
3882.45	4	4	8.94E-02
3883.14	8	6	1.13E-01
3893.52	4	6	1.89E-02
3907.45	6	6	8.64E-02
3911.96	6	4	1.09E+00
3912.12	4	4	1.41E-01
3919.27	4	2	1.22E+00
3945.04	2	4	2.05E-01
3954.36	2	2	8.57E-01
3973.26	4	4	1.04E+00
3982.71	4	2	4.27E-01
4069.62	2	4	1.52E+00
4069.88	4	6	1.53E+00
4072.15	6	8	1.98E+00
4075.86	8	10	2.11E+00
4078.84	4	4	5.52E-01
4084.65	6	8	7.28E-02
4085.11	6	6	4.55E-01
4092.93	8	8	2.65E-01
4094.14	6	4	4.70E-02
4096.53	4	6	1.73E-01
4097.22	2	4	3.62E-01
4103.00	2	2	5.09E-01
4104.72	4	6	3.14E-01
4104.99	4	4	9.14E-01
4106.02	8	6	1.70E-02
4109.84	6	6	1.21E-02
4110.19	6	4	2.54E-01
4110.79	4	2	7.70E-01
4112.02	6	6	1.81E-01
4113.83	8	6	2.41E-01
4119.22	6	8	1.33E+00
4120.28	6	6	2.15E-01
4120.55	6	4	2.60E-01
4121.46	2	2	5.60E-01
4129.32	4	2	1.79E-01
4132.80	2	4	9.13E-01
4140.70	4	4	4.09E-02
4153.30	4	6	7.91E-01
4156.53	6	4	2.11E-01
4169.22	6	6	2.71E-01
4185.44	6	8	1.91E+00
4189.58	8	8	7.06E-02
4189.79	8	10	1.98E+00
4192.51	6	4	3.21E-01
4196.27	4	4	3.56E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
4196.70	4	2	3.56E-01
4317.14	2	4	3.70E-01
4319.63	4	6	2.55E-01
4319.87	2	2	5.62E-01
4325.76	2	2	1.47E-01
4327.46	6	6	6.76E-01
4327.85	6	4	7.24E-02
4328.59	4	2	1.12E+00
4331.47	4	6	4.82E-02
4331.86	4	4	6.50E-01
4336.86	4	4	1.57E-01
4345.56	4	2	8.31E-01
4347.22	6	4	1.19E-01
4347.41	4	4	9.32E-01
4349.43	6	6	6.91E-01
4351.26	6	6	9.89E-01
4351.46	4	6	5.82E-02
4359.40	4	6	1.44E-02
4366.89	6	4	3.98E-01
4369.27	4	4	3.57E-01
4395.93	6	6	3.91E-01
4405.98	6	4	4.30E-02
4414.90	4	6	8.34E-01
4416.97	2	4	7.13E-01
4443.01	6	6	5.05E-01
4443.52	6	8	1.89E-02
4447.68	8	6	2.52E-02
4448.19	8	8	5.10E-01
4452.38	4	4	1.37E-01
4466.24	2	4	9.00E-01
4467.46	2	2	9.00E-01
4563.18	4	4	7.18E-03
4590.97	6	8	8.85E-01
4595.96	6	6	4.87E-02
4596.18	4	6	8.34E-01
4638.86	2	4	3.71E-01
4641.81	4	6	5.96E-01
4649.13	6	8	7.81E-01
4650.84	2	2	6.86E-01
4661.63	4	4	4.10E-01
4673.73	4	2	1.35E-01
4676.23	6	6	2.05E-01
4690.89	2	4	1.86E-01
4691.42	2	2	7.43E-01
4696.35	6	4	3.25E-02
4698.44	6	6	6.59E-02
4699.01	6	8	9.88E-01
4699.22	4	6	9.36E-01
4701.18	4	4	9.23E-01
4701.71	4	2	3.69E-01
4703.16	4	6	9.20E-01
4705.35	6	8	1.10E+00
4710.01	4	6	2.98E-01
4741.70	6	6	4.71E-02
4751.28	6	8	6.39E-02
4752.69	6	6	1.45E-02
4844.92	4	6	1.02E-02
4856.39	4	6	5.58E-02
4856.76	4	4	1.00E-01
4860.97	2	4	4.70E-01
4864.88	4	2	8.07E-02
4871.52	4	6	5.60E-01
4872.02	4	4	9.34E-02
4890.86	4	2	4.80E-01
4906.83	4	4	4.54E-01
4924.53	4	6	5.43E-01
4941.07	2	4	5.87E-01
4943.01	4	6	7.78E-01
4955.71	4	4	1.82E-01
5159.94	2	2	3.29E-01
5175.90	4	2	1.49E-01
5190.50	2	4	1.26E-01
5206.65	4	4	3.58E-01
5583.22	2	4	2.17E-02
5611.07	2	2	2.14E-02
6627.37	4	4	1.73E-01
6641.03	2	2	9.88E-02
6666.66	4	2	6.78E-02
6677.87	2	4	3.37E-02
6717.75	2	2	1.33E-01
6721.39	4	2	1.81E-01
6810.48	6	8	1.64E-03
6844.10	4	6	2.97E-03
6846.80	8	8	3.17E-02
6869.48	6	6	5.35E-02
6884.88	4	4	6.12E-02
6895.10	10	8	2.72E-01
6906.44	8	6	2.48E-01
6907.87	4	2	3.03E-01
6910.56	6	4	2.43E-01
O III			
263.694	1	3	3.32E+01
263.727	3	5	4.48E+01
263.773	3	3	2.49E+01
263.817	5	7	5.97E+01
263.861	5	5	1.49E+01
277.386	5	7	9.43E+01
279.788	5	5	4.25E+01
295.942	1	3	5.56E+01
303.413	1	3	4.29E+01
303.461	3	1	1.29E+02
303.517	3	3	3.21E+01
303.622	3	5	3.21E+01
303.695	5	3	5.34E+01
303.800	5	5	9.61E+01
305.596	1	3	1.20E+02
305.656	3	5	1.62E+02
305.702	3	3	9.01E+01
305.767	5	7	2.16E+02
305.836	5	5	5.40E+01
320.978	5	7	2.17E+02
328.448	5	5	1.04E+02
345.312	1	3	1.35E+02
374.073	5	5	2.85E+01
395.557	5	3	2.80E+01
507.388	1	3	1.61E+01
507.680	3	3	4.82E+01
508.178	5	3	8.04E+01
525.794	5	3	9.60E+01
597.814	1	3	1.49E+01
599.590	5	5	5.41E+01
702.337	1	3	6.06E+00
702.838	3	1	1.83E+01
832.929	1	3	3.41E+00
835.092	5	5	1.44E+00
835.289	5	7	5.99E+00
1679.03	3	5	6.57E-01
1686.73	3	3	6.48E-01
1760.41	3	5	8.38E-01
1764.46	5	5	2.50E+00
1766.63	1	3	1.11E+00
1772.28	3	1	3.29E+00
1772.97	5	3	1.37E+00
2390.43	3	3	1.62E+00
2454.97	3	1	3.43E+00
2665.68	3	5	6.75E-01
2674.58	5	5	1.11E+00
2683.66	3	1	1.85E+00
2686.15	7	5	1.54E+00
2687.55	3	3	1.84E+00
2695.48	3	5	1.82E+00
2794.14	3	1	1.82E-01
2798.93	3	3	4.52E-02
2809.66	5	3	1.34E-01
2818.70	5	5	2.66E-02
2836.31	7	5	1.46E-01
2959.69	3	5	1.83E+00
2983.78	3	5	2.15E+00
2992.08	3	5	9.32E-02
2996.48	3	3	4.64E-01
2997.69	5	7	6.88E-02
3004.34	5	5	4.27E-01
3008.78	5	3	1.53E-01
3017.62	7	7	5.38E-01
3023.43	3	5	4.79E-01
3024.36	7	5	9.39E-02
3024.54	1	3	6.16E-01
3035.41	3	3	4.59E-01
3042.07	3	1	1.94E+00
3047.10	5	5	1.49E+00
3059.28	5	3	8.72E-01
3064.98	1	3	2.17E-01
3068.13	3	1	6.49E-01
3068.26	3	3	5.41E-02
3068.67	3	5	2.27E-01
3074.14	5	7	1.84E-01
3074.72	5	3	3.76E-01
3075.13	5	5	1.61E-01
3075.95	7	9	1.07E-01
3083.65	7	7	3.20E-01
3084.64	7	5	2.55E-01
3088.04	9	9	5.30E-01
3095.79	9	7	1.35E-01
3115.67	3	1	1.39E+00
3121.63	3	3	1.38E+00
3132.79	3	5	1.37E+00
3198.18	3	5	9.57E-02
3201.14	3	3	4.77E-01
3202.51	5	7	7.08E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3207.61	5	5	4.40E-01
3210.58	5	3	1.58E-01
3216.07	7	7	5.58E-01
3221.21	7	5	9.75E-02
3260.86	5	7	1.68E+00
3265.33	7	9	1.88E+00
3267.20	3	5	1.58E+00
3281.83	5	5	2.89E-01
3284.45	7	7	2.06E-01
3299.39	1	3	1.64E-01
3312.33	3	3	4.60E-01
3326.06	3	3	2.65E-01
3330.30	3	5	6.81E-01
3330.32	3	5	4.76E-01
3332.41	5	3	7.92E-01
3332.93	5	7	5.04E-01
3336.67	3	3	3.76E-01
3336.69	5	5	8.77E-02
3340.76	5	3	6.57E-01
3344.20	5	5	1.25E-01
3344.51	5	7	3.48E-01
3347.98	7	5	4.86E-01
3350.62	5	3	1.12E+00
3350.92	7	7	9.91E-01
3355.86	7	7	6.89E-01
3362.31	7	5	6.87E-01
3376.61	3	1	1.49E+00
3376.76	3	3	1.12E+00
3377.26	3	5	5.20E-01
3382.61	5	7	9.86E-01
3383.31	5	3	3.70E-01
3383.81	5	5	8.62E-01
3384.90	7	9	1.48E+00
3394.22	7	7	4.88E-01
3395.43	7	5	9.75E-02
3406.88	1	3	1.93E-01
3408.13	3	1	5.79E-01
3415.26	3	3	1.44E-01
3428.63	3	5	1.42E-01
3430.57	5	3	2.37E-01
3444.05	5	5	4.21E-01
3446.68	3	5	9.71E-01
3447.15	1	3	8.09E-01
3447.97	5	7	1.19E+00
3450.91	7	9	1.44E+00
3451.30	3	3	8.06E-01
3454.84	5	5	6.89E-01
3454.99	9	11	1.72E+00
3459.48	5	3	1.14E-01
3459.94	7	7	5.14E-01
3466.13	9	9	2.84E-01
3466.85	7	5	6.82E-02
3475.24	9	7	2.42E-02
3520.94	1	3	1.50E-01
3531.22	3	1	4.45E-01
3533.38	3	3	1.11E-01
3534.90	3	5	1.11E-01
3555.24	5	3	1.82E-01
3556.78	5	5	3.26E-01
3695.38	3	5	4.01E-01
3698.72	5	7	7.62E-01
3703.36	7	9	1.14E+00
3704.75	3	3	8.53E-01
3707.27	3	5	7.34E-01
3709.54	3	1	1.13E+00
3712.49	5	5	6.59E-01
3714.03	3	3	4.06E-01
3715.09	5	7	9.73E-01
3720.89	7	7	3.74E-01
3721.95	5	3	2.80E-01
3725.31	5	5	2.41E-01
3728.51	5	7	1.29E+00
3728.84	7	9	1.45E+00
3729.80	3	5	1.22E+00
3732.13	5	3	2.67E-02
3734.83	7	5	7.40E-02
3742.63	5	5	2.24E-01
3746.90	7	7	1.59E-01
3754.70	3	5	7.53E-01
3757.23	1	3	5.56E-01
3759.88	5	7	9.79E-01
3774.03	3	3	3.91E-01
3791.28	5	5	2.24E-01
3810.98	5	3	2.37E-02
3816.75	5	3	9.63E-02
3961.57	5	7	1.25E+00
4072.64	1	3	3.37E-01
4073.98	3	5	4.54E-01
4081.02	5	7	6.02E-01
4089.30	3	3	2.49E-01
4103.07	5	5	1.48E-01
4118.60	5	3	1.63E-02
4440.09	5	3	4.42E-01
4447.69	5	5	4.40E-01
4461.61	5	7	4.36E-01
4524.22	3	1	3.38E-01
4532.78	5	3	1.40E-01
4535.29	3	3	8.40E-02
4555.39	5	5	2.49E-01
4557.91	3	5	8.27E-02
5268.30	1	3	3.50E-01
5508.24	5	5	1.06E-01
5592.25	3	3	3.27E-01
O IV			
238.360	2	4	2.96E+02
238.570	4	6	3.54E+02
238.579	4	4	5.90E+01
279.631	2	2	2.68E+01
279.933	4	2	5.34E+01
553.329	2	4	1.22E+01
554.076	2	2	4.86E+01
554.513	4	4	6.06E+01
555.263	4	2	2.41E+01
608.397	2	2	1.21E+01
609.829	4	2	2.40E+01
616.952	6	4	2.60E+01
617.005	4	4	2.89E+00
617.036	4	2	2.89E+01
624.619	2	4	1.07E+01
625.127	4	4	2.13E+01
625.853	6	4	3.19E+01
779.736	6	4	1.46E+00
779.820	4	4	1.31E+01
779.912	6	6	1.36E+01
779.997	4	6	9.70E-01
787.710	2	4	5.95E+00
790.112	4	4	1.18E+00
790.199	4	6	7.08E+00
921.296	2	4	2.21E+00
921.365	2	2	8.83E+00
923.367	4	4	1.10E+01
923.436	4	2	4.39E+00
1338.61	2	4	2.17E+00
1342.99	4	4	4.29E-01
1343.51	4	6	2.57E+00
2120.58	2	2	1.05E+00
2132.64	4	4	1.29E+00
2493.39	2	4	1.18E+00
2493.75	4	6	8.48E-01
2493.99	2	2	6.09E-01
2499.27	2	2	4.68E-01
2501.81	4	4	3.73E-01
2507.73	4	2	2.32E+00
2509.22	6	6	1.94E+00
2510.58	4	2	1.19E+00
2517.37	6	4	1.24E+00
2781.22	2	2	1.03E-01
2803.57	6	4	1.26E-01
2805.87	2	4	2.90E-01
2812.50	6	6	3.58E-02
2816.53	4	4	5.74E-01
2829.17	8	6	1.56E-01
2836.27	6	4	8.43E-01
2916.31	2	4	1.06E+00
2921.46	4	6	1.27E+00
2926.18	4	4	2.11E-01
3063.43	2	4	1.30E+00
3071.60	2	2	1.29E+00
3177.89	2	4	7.59E-02
3180.77	2	2	1.51E-01
3180.99	4	6	7.06E-02
3185.74	4	4	1.21E-01
3188.22	6	8	4.28E-02
3188.64	4	2	1.50E-01
3194.78	6	6	1.71E-01
3199.58	6	4	1.04E-01
3209.65	8	8	2.53E-01
3216.31	8	6	5.56E-02
3348.06	2	4	8.51E-01
3349.11	4	6	1.02E+00
3354.27	4	2	7.71E-01
3362.55	4	4	7.65E-01
3375.40	4	6	7.56E-01
3378.02	4	4	1.66E-01
3381.21	4	6	7.19E-01
3381.30	2	4	4.28E-01
3385.52	6	8	1.02E+00
3390.19	2	2	8.49E-01
3396.80	4	4	5.40E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3405.77	4	2	1.67E-01
3409.70	6	6	3.00E-01
3411.30	4	4	1.69E-01
3411.69	4	6	1.02E+00
3425.55	6	4	4.94E-02
3489.89	4	6	7.29E-01
3492.21	2	4	6.06E-01
3493.43	4	4	1.21E-01
3560.39	4	6	1.03E+00
3563.33	6	8	1.10E+00
3593.08	6	6	7.15E-02
3725.89	2	4	5.61E-01
3725.94	4	6	6.01E-01
3729.03	6	8	6.86E-01
3736.68	4	4	2.23E-01
3736.85	8	10	7.95E-01
3744.89	6	6	1.92E-01
3758.39	8	8	1.11E-01
3930.68	2	2	3.80E-02
3942.06	2	4	9.42E-02
3945.31	4	2	1.88E-01
3956.77	4	4	2.98E-02
3974.58	4	6	6.62E-02
3977.09	6	4	9.91E-02
3995.08	6	6	1.52E-01
4687.03	2	4	2.79E-01
4772.60	2	4	1.23E-01
4779.10	2	2	2.45E-01
4783.42	4	6	2.06E-01
4794.18	4	4	1.56E-01
4798.27	6	8	2.91E-01
4813.15	6	6	8.65E-02
5305.51	4	4	6.10E-02
5362.51	6	6	6.12E-02
6876.49	2	4	1.88E-02
6931.60	2	2	7.35E-02
7004.11	4	4	8.90E-02
7061.30	4	2	3.48E-02
O V			
172.169	1	3	2.94E+02
*192.85	9	15	6.90E+02
*215.17	9	3	1.83E+02
220.353	3	5	4.292E+02
248.460	3	1	5.59E+01
629.732	1	3	2.872E+01
758.677	3	5	5.547E+00
759.442	1	3	7.373E+00
760.227	3	3	5.514E+00
760.446	5	5	1.652E+01
761.128	3	1	2.197E+01
762.004	5	3	9.125E+00
774.518	3	1	3.804E+01
1371.30	3	5	3.336E+00
2729.31	3	5	4.52E-01
2731.45	1	3	5.90E-01
2743.61	3	3	4.38E-01
2752.23	3	1	1.82E+00
2755.13	5	5	1.37E+00
2769.69	5	3	7.88E-01
2781.01	3	5	1.40E+00
*2784.0	3	9	1.40E+00
2786.99	3	3	1.39E+00
2789.85	3	1	1.38E+00
3058.68	3	5	1.39E+00
3144.66	3	5	8.86E-01
3219.24	3	1	1.54E-01
3222.29	1	3	1.16E-01
3227.54	3	3	3.38E-02
3239.21	3	3	3.28E-01
3248.28	5	3	1.18E-01
3263.54	5	5	1.86E-02
3275.64	5	3	4.76E-01
3297.62	7	5	1.30E-01
3690.17	3	5	1.97E-02
3698.36	3	3	1.03E-01
3702.72	5	7	1.41E-02
3717.31	5	5	9.63E-02
3725.63	5	3	2.91E-02
3746.64	7	7	1.18E-01
3761.58	7	5	1.61E-02
4119.37	3	5	3.66E-01
4120.49	3	1	3.33E-01
4123.96	5	7	4.81E-01
4125.49	1	3	2.70E-01
4134.11	3	3	3.34E-01
4153.27	3	3	1.92E-01
4158.86	3	5	3.39E-01
4178.46	5	5	1.12E-01
4213.35	5	3	1.19E-02
4522.66	5	3	1.02E-02
4554.53	3	5	2.41E-01
5114.06	1	3	1.80E-01
5339.94	1	3	1.85E-02
5349.74	3	1	7.04E-02
5372.71	3	3	1.42E-02
5414.59	3	5	9.29E-03
5428.38	5	3	2.68E-02
5471.12	5	5	4.86E-02
5571.81	1	3	8.33E-02
5580.12	3	5	1.11E-01
5583.23	3	3	6.20E-02
*5589.9	9	15	1.49E-01
5597.89	5	7	1.48E-01
5604.27	5	5	3.68E-02
5607.41	5	3	4.08E-03
6330.05	5	7	1.21E-01
6460.12	3	5	9.37E-02
6466.14	5	7	1.01E-01
6500.24	7	9	1.11E-01
6543.77	5	5	1.64E-02
6601.28	7	7	1.14E-02
6764.72	1	3	4.37E-02
6789.62	3	5	5.79E-02
6817.40	3	3	3.00E-02
6828.95	5	7	7.35E-02
6878.76	5	5	1.65E-02
O VI			
*150.10	2	6	2.62E+02
*173.03	6	10	8.78E+02
1031.91	2	4	4.16E+00
1037.61	2	2	4.09E+00
3811.35	2	4	5.14E-01
3834.24	2	2	5.05E-01
O VII			
18.6270	1	3	9.365E+03
21.6020	1	3	3.309E+04
*120.33	3	9	5.334E+02
128.411	1	3	8.982E+02
*128.46	9	15	1.615E+03
135.820	3	5	1.523E+03
*1630.3	3	9	7.935E-01
2448.98	1	3	2.514E-01
*5933.1	3	9	1.002E-01
8241.76	1	3	3.864E-02
Phosphorus			
P I			
1671.7	4	2	3.9E-01
1674.6	4	4	4.0E-01
1679.7	4	6	3.9E-01
1775.0	4	6	2.17E+00
1782.9	4	4	2.14E+00
1787.7	4	2	2.13E+00
2135.5	4	4	2.11E-01
2136.2	6	4	2.83E+00
2149.1	4	2	3.18E+00
2152.9	2	4	4.85E-01
2154.1	4	4	1.73E-01
2154.1	4	6	5.8E-01
2534.0	2	4	2.00E-01
2535.6	4	4	9.5E-01
2553.3	2	2	7.1E-01
2554.9	4	2	3.00E-01
P II			
1301.9	1	3	5.0E-01
1304.5	3	1	1.5E+00
1304.7	3	3	3.7E-01
1305.5	3	5	3.8E-01
1309.9	5	3	6.2E-01
1310.7	5	5	1.1E+00
4475.3	5	7	1.3E+00
4499.2	5	7	1.4E+00
4530.8	3	5	1.0E+00
4554.8	3	5	9.6E-01
4588.0	5	7	1.7E+00
4589.9	3	5	1.6E+00
4602.1	7	9	1.9E+00
4943.5	7	5	6.3E-01
5253.5	3	5	1.0E+00
5425.9	5	5	6.9E-01
6024.2	3	5	5.1E-01
6043.1	5	7	6.8E-01
P III			
1334.8	2	4	5.5E-01
1344.3	4	6	6.4E-01
1344.8	4	4	1.1E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
4057.4	4	4	1.0E-01
4059.3	6	4	9.0E-01
4080.1	4	2	9.9E-01
Potassium			
K I			
4044.1	2	4	1.24E-02
4047.2	2	2	1.24E-02
5084.2	2	2	3.50E-03
5099.2	4	2	7.0E-03
5323.3	2	2	6.3E-03
5339.7	4	2	1.26E-02
5343.0	2	4	4.0E-03
5359.6	4	6	4.6E-03
5782.4	2	2	1.23E-02
5801.8	4	2	2.46E-02
5812.2	2	4	2.8E-03
5831.9	4	6	3.2E-03
6911.1	2	2	2.72E-02
6938.8	4	2	5.4E-02
7664.9	2	4	3.87E-01
7699.0	2	2	3.82E-01
K II			
607.93	1	3	1.3E-02
K III			
2550.0	6	4	2.0E+00
2635.1	4	4	1.2E+00
2992.4	6	8	2.5E+00
3052.1	4	6	1.7E+00
3202.0	4	4	1.8E+00
3289.1	4	6	2.0E+00
3322.4	6	6	1.3E+00
3421.8	2	4	1.5E+00
K XVI			
206.27	1	3	9.4E+01
K XVII			
22.020	2	4	4.7E+04
22.163	4	6	5.6E+04
22.18	4	4	9.3E+03
22.60	2	2	2.5E+03
22.76	4	2	4.7E+03
Praseodymium			
Pr II			
3997.0	15	15	1.87E-01
4062.8	13	15	1.00E+00
4100.7	17	19	8.4E-01
4143.1	15	17	5.8E-01
4179.4	13	15	5.2E-01
4222.9	11	13	3.91E-01
4241.0	17	15	2.30E-01
4359.8	15	15	1.1E-01
4405.8	17	17	9.0E-02
4429.3	15	15	2.28E-01
4449.8	13	13	1.24E-01
4468.7	11	13	1.54E-01
4510.2	13	15	1.16E-01
4534.2	15	17	4.9E-02
4734.2	15	13	2.5E-02
4879.1	15	15	1.8E-02
4886.0	15	15	1.3E-02
4912.6	17	15	5.7E-02
5034.4	19	19	1.1E-01
5110.8	21	19	2.78E-01
5135.1	17	17	1.25E-01
5173.9	19	17	3.18E-01
5219.1	15	15	9.5E-02
5220.1	17	15	2.35E-01
5251.7	15	13	1.1E-02
5259.7	15	13	2.24E-01
5292.6	13	13	9.3E-02
5810.6	17	19	2.3E-02
5879.3	15	15	7.6E-02
6200.8	15	17	1.8E-02
6278.7	13	15	2.6E-02
6398.0	11	13	1.9E-02
Rhodium			
Rh I			
3083.96	8	6	4.8E-02
3114.91	6	4	4.45E-02
3121.76	6	6	1.1E-01
3123.70	10	8	4.6E-02
3137.71	4	6	3.3E-02
3189.05	6	6	3.03E-01
3197.13	6	4	4.35E-02
3263.14	6	6	1.3E-01
3271.61	6	4	2.0E-01
3280.55	8	8	2.36E-01
3283.57	6	8	4.4E-01
3289.14	4	4	1.0E-01
3323.09	8	10	6.3E-01
3331.09	4	2	5.40E-02
3338.54	8	6	3.5E-02
3360.80	4	4	1.2E-01
3368.38	6	4	1.1E-01
3396.82	10	10	6.5E-01
3399.70	6	8	1.2E-01
3462.04	6	6	6.2E-01
3470.66	4	4	8.5E-01
3478.91	6	6	3.32E-01
3484.04	6	8	9.3E-03
3498.73	4	6	2.12E-01
3502.52	10	10	4.3E-01
3507.32	6	8	3.4E-01
3528.02	8	8	8.5E-01
3543.95	4	4	4.65E-01
3549.54	6	6	2.22E-01
3570.18	4	6	1.82E-01
3583.10	8	10	2.6E-01
3596.19	6	4	5.5E-01
3597.15	6	8	5.9E-01
3612.47	4	2	8.90E-01
3620.46	6	4	8.5E-02
3654.87	8	8	6.0E-02
3657.99	8	6	8.8E-01
3666.22	6	8	8.4E-02
3690.70	6	4	3.23E-01
3692.36	10	8	9.1E-01
3700.91	8	10	3.9E-01
3713.02	4	4	8.3E-02
3788.47	4	6	1.4E-01
3793.22	8	6	4.2E-01
3799.31	8	8	5.5E-01
3806.76	6	6	6.2E-02
3818.19	6	4	5.8E-01
3822.26	6	6	8.5E-01
3828.48	6	6	6.2E-01
3833.89	6	4	5.8E-01
3856.52	8	10	5.9E-01
3872.39	4	6	6.7E-03
3877.34	8	6	3.7E-02
3913.51	8	8	2.5E-03
3922.19	4	2	6.25E-02
3934.23	8	8	1.58E-01
3942.72	4	2	7.15E-01
3958.86	6	8	5.5E-01
3984.40	4	4	1.1E-01
3995.61	4	6	4.7E-02
4053.44	2	2	2.8E-02
4056.34	6	4	9.5E-03
4082.78	6	4	1.4E-01
4097.52	2	4	7.0E-02
4121.68	6	6	9.8E-02
4128.87	6	8	1.73E-01
4135.27	8	8	1.0E-01
4196.50	6	8	3.9E-02
4211.14	8	10	1.62E-01
4244.44	4	4	6.5E-03
4278.60	4	6	9.2E-03
4288.71	6	8	6.1E-02
4373.04	2	4	1.8E-02
4374.80	8	10	1.64E-01
4379.92	6	6	2.48E-02
4492.47	6	6	4.5E-03
4528.72	6	8	1.35E-02
4548.73	4	6	5.5E-03
4551.64	4	4	4.00E-02
4565.19	4	4	1.1E-02
4569.00	6	8	1.0E-02
4608.12	2	2	2.1E-02
4675.03	8	8	6.4E-03
4721.00	6	4	3.43E-03
4745.11	6	6	5.2E-03
4755.58	4	4	6.0E-03
4842.43	6	8	1.6E-03
4963.71	2	2	3.0E-02
4977.75	4	4	9.8E-03
4979.18	4	6	1.0E-02
5090.63	6	6	5.0E-03
5120.69	6	8	3.1E-03
5130.76	4	4	4.35E-03
5155.54	2	4	9.8E-03
5184.19	6	8	1.6E-03
5212.73	4	2	5.95E-03
5292.14	10	10	3.7E-03
5390.44	4	6	9.5E-03
5424.72	4	4	5.0E-03

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
5599.42	6	8	1.3E-02
5983.60	10	10	2.1E-02
Rubidium			
Rb I			
3022.5	2	4	4.13E-05
3032.0	2	4	4.93E-05
3044.2	2	4	8.2E-05
3060.2	2	4	1.05E-04
3082.0	2	4	1.49E-04
3112.6	2	4	2.5E-04
3113.1	2	2	1.3E-04
3157.5	2	4	3.38E-04
3158.3	2	2	2.0E-04
3228.0	2	4	6.4E-04
3229.2	2	2	3.8E-04
3348.7	2	4	1.37E-03
3350.8	2	2	8.9E-04
3587.1	2	4	3.97E-03
3591.6	2	2	2.9E-03
4201.8	2	4	1.8E-02
4215.5	2	2	1.5E-02
7800.3	2	4	3.70E-01
7947.6	2	2	3.40E-01
Scandium			
Sc I			
2116.7	4	4	2.0E-01
2120.4	6	6	2.0E-01
2262.3	4	4	5.8E-02
2266.6	4	2	4.8E-01
2270.9	6	4	4.6E-01
2280.8	4	6	2.8E-01
2289.6	6	6	4.1E-02
2311.29	4	6	4.1E-02
2315.69	4	4	2.5E-01
2320.32	6	6	2.4E-01
2324.75	6	4	4.1E-02
2328.19	4	6	4.6E-02
2334.67	4	2	1.7E-01
2346.03	6	4	1.3E-01
2429.19	4	4	2.8E-01
2438.63	6	6	2.1E-01
2468.40	4	2	4.9E-02
2692.78	4	2	1.61E-01
2699.02	4	6	2.4E-02
2706.74	4	4	3.1E-01
2707.93	6	4	1.49E-01
2711.34	6	6	3.2E-01
2965.88	4	6	7.5E-02
2974.01	4	4	5.5E-01
2980.76	6	6	5.4E-01
2988.97	6	4	6.9E-02
3015.37	4	6	7.8E-01
3019.35	6	8	8.7E-01
3030.76	6	6	1.00E-01
3255.68	4	4	3.2E-01
3269.90	4	2	3.13E+00
3273.63	6	4	2.81E+00
3907.48	4	6	1.66E+00
3911.81	6	8	1.79E+00
3933.38	6	6	1.62E-01
3996.60	4	6	1.65E-01
4020.39	4	4	1.63E+00
4023.22	4	4	3.0E-01
4023.68	6	6	1.65E+00
4031.38	6	6	2.9E-01
4036.86	6	4	7.9E-02
4043.80	8	8	3.11E-01
4047.80	6	4	1.54E-01
4051.83	8	6	7.7E-02
4054.54	4	2	1.67E-01
4067.00	6	8	1.91E-01
4067.63	10	8	4.1E-02
4074.96	4	6	3.7E-01
4078.56	2	4	4.3E-01
4080.57	4	4	6.6E-02
4082.39	6	4	2.73E-01
4086.66	6	8	3.7E-01
4087.47	4	6	1.12E-01
4093.12	4	4	1.23E-01
4094.86	6	6	1.44E-01
4098.36	8	8	8.7E-02
4132.98	4	6	1.19E+00
4140.27	6	8	1.17E+00
4147.38	6	6	1.74E-01
4161.85	8	8	1.77E-01
4171.53	6	4	1.36E-01
4186.42	6	8	8.4E-02
4187.61	8	6	1.28E-01
4193.53	4	6	6.1E-02
4204.52	6	8	3.5E-02
4205.20	10	8	1.12E-01
4212.32	4	6	1.58E-01
4212.48	6	6	8.6E-02
4216.08	2	4	2.36E-01
4218.23	4	4	2.26E-01
4225.54	6	8	9.5E-02
4225.69	4	6	7.6E-02
4231.64	4	4	1.31E-01
4233.59	6	6	4.0E-01
4238.05	8	8	7.1E-01
4239.55	6	4	2.27E-01
4246.14	8	6	1.15E-01
4542.55	6	4	1.28E-01
4544.67	8	6	1.33E-01
4706.94	4	6	2.81E-01
4709.31	6	8	4.0E-01
4711.72	2	4	1.81E-01
4714.30	4	4	2.14E-01
4719.31	6	6	1.04E-01
4728.77	8	8	1.16E-01
4729.20	4	4	2.20E-01
4729.24	6	6	1.93E-01
4734.11	4	2	1.10E+00
4737.65	6	4	8.8E-01
4741.02	8	6	9.1E-01
4743.82	10	8	9.8E-01
4973.67	4	2	8.4E-01
4980.36	6	4	5.6E-01
4983.43	4	4	2.58E-01
4991.91	6	6	3.8E-01
4995.00	4	6	5.9E-02
5018.41	6	4	2.09E-01
5021.52	4	4	2.30E-01
5064.31	8	10	7.3E-02
5066.38	6	6	3.6E-02
5070.17	6	8	1.16E-01
5072.71	2	4	2.0E-02
5075.82	4	6	1.15E-01
5080.22	4	4	4.1E-02
5081.56	10	10	7.6E-01
5083.72	8	8	6.2E-01
5085.55	6	6	5.7E-01
5086.94	4	4	6.6E-01
5096.72	6	4	1.69E-01
5099.27	4	6	1.50E-01
5101.12	10	8	8.8E-02
5331.79	4	4	1.11E-01
5339.43	6	6	1.06E-01
5341.07	4	2	3.8E-01
5349.34	6	4	5.9E-01
5350.28	8	8	6.8E-02
5355.79	6	4	3.0E-01
5356.10	8	6	5.7E-01
5375.37	8	6	3.4E-01
5392.06	10	8	4.2E-01
5416.16	4	6	4.4E-02
5416.41	6	6	2.0E-02
5425.55	6	8	4.5E-02
5429.42	2	4	9.0E-02
5432.98	4	4	5.4E-02
5433.25	6	4	9.7E-02
5438.28	4	6	3.4E-02
5439.04	2	2	1.74E-01
5442.62	4	2	2.15E-01
5446.20	8	8	2.8E-01
5451.37	6	6	1.50E-01
5455.24	4	4	6.6E-02
5464.95	4	2	3.2E-02
5468.40	6	4	9.7E-02
5472.19	8	6	9.7E-02
5482.01	8	8	5.2E-01
5484.63	6	6	5.2E-01
5514.23	6	8	4.1E-01
5520.52	8	10	4.3E-01
5526.10	4	4	7.1E-02
5541.07	6	6	5.5E-02
5631.04	2	4	3.0E-02
5671.83	10	12	5.4E-01
5686.86	8	10	4.9E-01
5700.19	6	8	4.6E-01
5708.64	10	10	4.7E-02
5711.79	4	6	4.5E-01
5717.31	8	8	7.5E-02
5724.13	6	6	7.4E-02
5988.43	6	6	6.6E-02
6026.16	4	4	7.2E-02
6146.20	6	8	4.2E-02
6198.43	4	6	3.5E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
6249.96	6	8	3.2E-02
6262.22	4	6	8.4E-02
6280.16	2	4	4.0E-02
6284.16	6	6	3.9E-02
6284.73	4	4	7.1E-02
6293.02	2	2	1.04E-01
7741.16	10	10	3.8E-02
7800.42	8	8	5.1E-02
Sc II			
1880.6	5	3	5.0E+00
2064.3	7	5	2.2E+00
2068.0	5	3	2.0E+00
2273.1	1	3	7.7E+00
2545.20	5	5	4.0E-01
2552.35	7	5	2.21E+00
2555.79	3	3	6.9E-01
2560.23	5	3	2.01E+00
2563.19	3	1	2.70E+00
2611.19	5	5	2.2E+00
2667.70	3	5	1.5E+00
2746.36	3	1	3.9E+00
2782.31	5	5	1.3E+00
2789.15	7	7	1.3E+00
2801.31	9	9	1.3E+00
2819.49	3	5	2.3E+00
2822.12	5	7	2.5E+00
2826.64	7	9	2.8E+00
2870.85	5	3	1.1E+00
2912.98	5	3	1.1E+00
2979.68	3	5	1.2E+00
2988.92	5	7	2.9E+00
3039.92	7	9	3.5E+00
3045.73	5	7	3.68E+00
3052.92	7	9	3.92E+00
3060.54	7	7	3.0E-01
3065.12	9	11	4.00E+00
3075.36	9	9	2.5E-01
3128.27	3	3	1.9E+00
3133.07	5	5	1.8E+00
3139.72	7	7	2.1E+00
3190.98	3	3	1.1E+00
3199.33	5	3	1.9E+00
3312.72	5	7	1.2E+00
3320.40	5	3	1.2E+00
3343.23	9	7	1.1E+00
3353.72	5	7	1.51E+00
3359.67	5	5	2.16E-01
3361.26	3	3	3.4E-01
3361.93	3	1	1.17E+00
3368.94	5	3	8.3E-01
3372.15	7	5	9.9E-01
3379.16	3	3	2.5E+00
3535.71	5	3	6.1E-01
3558.53	5	7	3.0E-01
3567.70	3	5	3.5E-01
3572.53	7	7	1.38E+00
3576.34	5	5	1.06E+00
3580.93	3	3	1.23E+00
3589.63	5	3	4.6E-01
3590.47	7	5	2.9E-01
3613.83	7	9	1.48E+00
3630.74	5	7	1.20E+00
3642.78	3	5	1.13E+00
3645.31	7	7	2.74E-01
3651.80	5	5	3.0E-01
3859.59	7	5	1.1E+00
4246.82	5	5	1.29E+00
4314.08	9	7	4.1E-01
4320.75	7	5	4.0E-01
4325.00	5	3	4.3E-01
4374.46	9	9	1.48E-01
4400.39	7	7	1.43E-01
4415.54	5	5	1.47E-01
4670.41	5	7	1.16E-01
5031.01	5	3	3.5E-01
5239.81	1	3	1.39E-01
5526.79	9	7	3.3E-01
5657.91	5	5	1.04E-01
5669.06	3	1	1.31E-01
Silicon			
Si I			
1977.6	1	3	1.8E-01
1979.2	3	1	5.1E-01
1980.6	3	3	1.3E-01
1983.2	3	5	1.4E-01
1986.4	5	3	2.1E-01
1989.0	5	5	4.1E-01
2208.0	1	3	3.11E-01
2210.9	3	5	4.16E-01
2211.7	3	3	2.32E-01
2216.7	5	7	5.5E-01
2218.1	5	5	1.38E-01
2506.9	3	5	4.66E-01
2514.3	1	3	6.1E-01
2516.1	5	5	1.21E+00
2519.2	3	3	4.56E-01
2524.1	3	1	1.81E+00
2528.5	5	3	7.7E-01
2532.4	1	3	2.6E-01
2631.3	1	3	9.7E-01
2881.6	5	3	1.89E+00
3905.5	1	3	1.18E-01
4738.8	3	3	1.0E-02
4783.0	5	3	1.7E-02
4792.3	5	5	1.7E-02
4818.1	5	7	1.1E-02
4821.2	3	5	8.0E-03
4947.6	3	1	4.2E-02
5006.1	3	5	2.8E-02
5622.2	3	3	1.6E-02
5690.4	3	3	1.2E-02
5708.4	5	5	1.4E-02
5754.2	5	3	1.5E-02
5772.1	3	1	3.6E-02
5948.5	3	5	2.2E-02
7226.2	3	5	7.9E-03
7405.8	3	5	3.7E-02
7409.1	5	7	2.3E-02
7680.3	3	5	4.6E-02
7918.4	3	5	5.2E-02
7932.3	5	7	5.1E-02
7944.0	7	9	5.8E-02
7970.3	5	5	7.1E-03
Si II			
989.87	2	4	6.7E+00
992.68	4	6	8.0E+00
1020.7	2	2	1.3E+00
1190.4	2	4	6.9E+00
1193.3	2	2	2.8E+01
1194.5	4	4	3.6E+01
1197.4	4	2	1.4E+01
1248.4	4	4	1.3E+01
1251.2	6	4	1.9E+01
1260.4	2	4	2.0E+01
1264.7	4	6	2.3E+01
1304.4	2	2	3.6E+00
1309.3	4	2	7.0E+00
1526.7	2	2	3.73E+00
1533.5	4	2	7.4E+00
1808.0	2	4	3.7E-02
2904.3	4	6	6.7E-01
2905.7	6	8	7.1E-01
3210.0	4	6	4.6E-01
4128.1	4	6	1.32E+00
4130.9	6	8	1.42E+00
5041.0	2	4	9.8E-01
5056.0	4	6	1.2E+00
5957.6	2	2	4.2E-01
5978.9	4	2	8.1E-01
6347.1	2	4	7.0E-01
6371.4	2	2	6.9E-01
7848.8	4	6	3.9E-01
7849.7	6	8	4.2E-01
Si III			
883.40	5	7	6.3E+01
994.79	3	3	7.89E+00
997.39	5	3	1.31E+01
1141.6	3	5	3.0E+01
1144.3	5	7	3.9E+01
1161.6	5	5	1.6E+01
1206.5	1	3	2.59E+01
1206.5	3	5	4.89E+01
1207.5	5	5	1.9E+01
1294.5	3	5	5.42E+00
1296.7	1	3	7.19E+00
1298.9	3	3	5.36E+00
1299.0	5	5	1.61E+01
1301.2	3	1	2.13E+01
1303.3	5	3	8.85E+00
1328.8	1	3	2.7E+01
1417.2	3	1	2.60E+01
1435.8	5	7	2.1E+01
1589.0	5	3	1.1E+01
1778.7	7	9	4.4E+00
1783.1	5	7	3.8E+00
3241.6	5	3	2.3E+00
*3486.9	15	21	1.8E+00

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3590.5	3	5	3.9E+00
4552.6	3	5	1.26E+00
4554.0	5	3	7.6E-01
4567.8	3	3	1.25E+00
4683.0	5	5	9.5E-01
4716.7	5	7	2.8E+00
5451.5	3	5	6.0E-01
5473.1	5	7	7.9E-01
5716.3	9	7	1.9E-01
5739.7	1	3	4.7E-01
7462.6	5	3	4.9E-01
7466.3	7	5	5.4E-01
7612.4	3	5	1.1E+00
Si IV			
457.82	2	4	3.6E+00
458.16	2	2	3.6E+00
515.12	2	2	4.1E+00
516.35	4	2	8.2E+00
*560.50	6	10	1.0E+00
*749.94	10	14	1.45E+01
815.05	2	2	1.23E+01
818.13	4	2	2.44E+01
*860.74	10	6	1.8E+00
*1066.6	10	14	3.91E+01
1122.5	2	4	2.05E+01
1128.3	4	4	4.03E+00
1128.3	4	6	2.42E+01
1393.8	2	4	7.73E+00
1402.8	2	2	7.58E+00
*1724.1	10	6	5.5E+00
Si V			
96.439	1	3	4.8E+02
97.143	1	3	2.0E+03
117.86	1	3	3.0E+02
Si VI			
246.00	4	2	1.7E+02
249.12	2	2	8.5E+01
Si VII			
217.83	5	3	4.3E+02
272.64	5	3	5.1E+01
274.18	3	1	1.2E+02
275.35	5	5	8.9E+01
275.67	3	3	3.0E+01
276.84	1	3	3.9E+01
278.45	3	5	2.9E+01
Si VIII			
214.76	4	2	4.1E+02
216.92	6	4	3.6E+02
232.86	2	2	8.0E+01
235.56	4	4	9.7E+01
250.45	2	2	7.7E+01
250.79	4	2	1.6E+02
314.31	4	2	5.2E+01
316.20	4	4	5.0E+01
319.83	4	6	4.9E+01
Si IX			
223.73	1	3	4.2E+01
225.03	3	3	1.2E+02
227.01	5	3	2.0E+02
227.30	5	3	2.3E+02
258.10	5	5	1.04E+02
*294.37	9	9	5.9E+01
*347.36	9	15	2.2E+01
Si X			
253.77	2	4	2.9E+01
256.57	2	2	1.1E+02
258.35	4	4	1.4E+02
261.05	4	2	5.4E+01
272.00	2	2	3.0E+01
277.26	4	2	5.7E+01
287.08	2	4	2.6E+01
289.19	4	4	5.0E+01
292.22	6	4	7.3E+01
*347.73	10	10	4.3E+01
*353.09	6	10	2.1E+01
Si XI			
43.763	1	3	6.11E+03
*49.116	9	3	2.45E+03
49.222	3	5	8.9E+03
52.296	3	1	7.6E+02
303.30	1	3	6.42E+01
358.29	3	1	1.03E+02
358.63	3	5	1.38E+01
361.41	1	3	1.80E+01
364.50	3	3	1.32E+01
365.42	5	5	3.90E+01
368.28	3	1	5.1E+01
371.48	5	3	2.07E+01
604.14	3	5	1.12E+01
2300.8	1	3	4.34E-01
Si XII			
*40.924	2	6	4.42E+03
*44.118	6	10	1.4E+04
499.43	2	4	9.56E+00
520.72	2	2	8.47E+00
1862	2	4	1.15E+00
1949	2	2	1.0E+00
4620	2	4	4.6E-02
4942	4	6	4.5E-02
Silver			
Ag I			
2061.2	2	4	3.1E-02
2069.9	2	2	1.5E-02
3280.7	2	4	1.4E+00
3382.9	2	2	1.3E+00
5209.1	2	4	7.5E-01
5465.5	4	6	8.6E-01
5471.6	4	4	1.4E-01
Sodium			
Na I			
3302.4	2	4	2.81E-02
3303.0	2	2	2.81E-02
4390.0	2	4	7.7E-03
4393.3	4	4	1.6E-03
4393.3	4	6	9.2E-03
4494.2	2	4	1.2E-02
4497.7	4	6	1.4E-02
4497.7	4	4	2.4E-03
4664.8	2	4	2.33E-02
4668.6	4	4	4.1E-03
4668.6	4	6	2.5E-02
4747.9	2	2	6.3E-03
4751.8	4	2	1.27E-02
4978.5	2	4	4.1E-02
4982.8	4	4	8.2E-03
4982.8	4	6	4.89E-02
5148.8	2	2	1.17E-02
5153.4	4	2	2.33E-02
5682.6	2	4	1.03E-01
5688.2	4	6	1.2E-01
5688.2	4	4	2.1E-02
5890.0	2	4	6.11E-01
5895.9	2	2	6.10E-01
6154.2	2	2	2.6E-02
6160.8	4	2	5.2E-02
8183.3	2	4	4.53E-01
8194.8	4	6	5.4E-01
8194.8	4	4	9.0E-02
11381	2	2	8.9E-02
11404	4	2	1.76E-01
Na II			
300.15	1	3	3.0E+01
301.44	1	3	4.9E+01
372.08	1	3	3.4E+01
Na III			
378.14	4	2	7.7E+01
380.10	2	2	3.7E+01
1991.0	4	6	8.3E+00
2004.2	2	4	4.6E+00
2011.9	6	8	8.4E+00
2151.5	2	4	4.4E+00
2174.5	4	6	5.3E+00
2230.3	6	8	3.7E+00
2232.2	4	4	3.3E+00
2246.7	4	6	2.4E+00
2459.3	4	6	3.0E+00
2468.9	2	4	2.4E+00
2497.0	6	6	1.7E+00
Na V			
*307.89	10	6	2.0E+02
*333.46	6	6	5.6E+01
*369.01	10	6	1.2E+02
*400.72	10	10	5.0E+01
*445.14	6	10	7.1E+00
459.90	4	2	2.3E+01
461.05	4	4	2.3E+01
463.26	4	6	2.2E+01
510.10	2	2	5.6E+01
511.19	4	4	6.8E+01
Na VI			
313.75	5	3	1.3E+02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
361.25	5	5	7.7E+01
*416.53	9	9	3.7E+01
*492.80	9	15	1.3E+01
1550.6	5	5	4.35E+00
1567.8	5	3	2.68E+00
1608.5	3	1	2.6E+00
1649.4	5	5	2.05E+00
1741.5	3	5	2.59E+00
1747.5	5	7	3.1E+00
Na VII			
*94.409	6	10	2.7E+03
*105.27	6	2	4.5E+02
353.29	4	4	1.0E+02
381.30	4	2	4.0E+01
397.49	4	4	3.5E+01
399.18	6	4	5.2E+01
*483.28	10	10	2.9E+01
486.74	2	4	1.1E+01
491.95	4	6	1.3E+01
555.80	4	4	2.3E+01
777.83	4	6	6.8E+00
Na VIII			
*83.34	9	15	3.94E+03
*89.88	9	3	8.09E+02
90.536	3	5	2.86E+03
411.15	1	3	4.42E+01
1239.4	3	3	3.02E+00
1802.7	3	1	2.70E+00
1867.7	3	5	2.01E+00
2059.1	3	5	1.80E+00
2558.2	5	3	2.26E-02
2772.0	3	5	4.19E-01
3021.0	5	7	4.90E-01
3108.9	1	3	2.58E-01
3182.3	1	3	2.92E-01
Na IX			
70.615	2	4	1.35E+03
70.653	2	2	1.35E+03
77.764	2	4	3.6E+03
77.911	4	6	4.3E+03
681.72	2	4	6.63E+00
694.17	2	2	6.30E+00
2487.7	2	4	8.32E-01
2535.8	2	2	7.89E-01
6841.8	2	4	2.59E-02
7103.4	4	6	2.78E-02
Strontium			
Sr I			
2206.2	1	3	6.6E-03
2211.3	1	3	8.5E-03
2217.8	1	3	1.2E-02
2226.3	1	3	1.6E-02
2237.7	1	3	2.3E-02
2253.3	1	3	3.7E-02
2275.3	1	3	6.7E-02
2307.3	1	3	1.2E-01
2354.3	1	3	1.8E-01
2428.1	1	3	1.7E-01
2569.5	1	3	5.3E-02
2931.8	1	3	1.9E-02
4607.3	1	3	2.01E+00
Sr II			
2018.7	2	2	1.2E-01
2051.9	4	2	2.4E-01
2282.0	2	4	8.3E-01
2322.4	4	6	9.1E-01
2324.5	4	4	1.5E-01
2423.5	2	2	2.4E-01
2471.6	4	2	4.8E-01
3464.5	4	6	3.1E+00
3474.9	4	4	5.1E-01
4077.7	2	4	1.42E+00
4161.8	2	2	6.5E-01
4215.5	2	2	1.27E+00
4305.5	4	2	1.4E+00
4414.8	4	6	1.1E-01
4417.5	4	4	1.8E-02
4585.9	4	2	7.0E-02
5303.1	2	4	1.9E-01
5379.1	4	6	2.2E-01
5385.5	4	4	3.7E-02
5723.7	2	2	7.1E-02
5819.0	4	2	1.4E-01
8688.9	4	6	5.5E-01
8719.6	4	4	9.7E-02
Sulfur			
S I			
1295.7	5	5	4.9E+00
1296.2	5	3	2.7E+00
1302.3	3	5	1.8E+00
1302.9	3	3	1.6E+00
1303.1	3	1	6.6E+00
1303.4	5	3	1.9E+00
1305.9	1	3	2.4E+00
1401.5	5	3	9.1E-01
1409.3	3	3	5.0E-01
1412.9	1	3	1.6E-01
1425.0	5	7	4.5E+00
1425.2	5	5	1.2E+00
1433.3	3	5	3.3E+00
1433.3	3	3	1.9E+00
1437.0	1	3	2.4E+00
1448.2	5	3	7.3E+00
1473.0	5	7	4.2E-01
1474.0	5	7	1.6E+00
1474.4	5	5	5.0E-01
1474.6	5	3	6.2E-02
1481.7	3	5	1.7E-01
1483.0	3	5	1.2E+00
1483.2	3	3	7.5E-01
1487.2	1	3	8.7E-01
1666.7	5	5	6.3E+00
1687.5	1	3	9.4E-01
1782.3	1	3	1.9E+00
1807.3	5	3	3.8E+00
1820.3	3	3	2.2E+00
1826.2	1	3	7.2E-01
4694.1	5	7	6.7E-03
4695.4	5	5	6.7E-03
4696.2	5	3	6.5E-03
6403.6	3	5	5.7E-03
6408.1	5	5	9.5E-03
6415.5	7	5	1.3E-02
*6751.2	15	25	7.9E-02
7679.6	3	5	1.2E-02
7686.1	5	5	2.0E-02
7696.7	7	5	2.8E-02
S II			
1124.4	2	4	1.0E+00
1125.0	4	4	4.6E+00
1131.0	2	2	3.5E+00
1131.6	4	2	1.4E+00
1250.5	4	2	4.6E-01
1253.8	4	4	4.2E-01
1259.5	4	6	3.4E-01
4463.6	8	6	5.3E-01
4483.4	6	4	3.1E-01
4486.7	4	2	6.6E-01
4524.7	4	4	9.3E-02
4525.0	6	4	1.2E+00
4552.4	4	2	1.2E+00
4656.7	2	4	9.0E-02
4716.2	4	4	2.9E-01
4815.5	6	4	8.8E-01
4885.6	2	4	1.7E-01
4917.2	2	2	6.6E-01
4924.1	4	6	2.2E-01
4925.3	2	4	2.4E-01
4942.5	2	2	1.5E-01
4991.9	4	4	1.5E-01
5009.5	4	2	7.0E-01
5014.0	4	4	8.4E-01
5027.2	4	2	2.6E-01
5032.4	6	6	8.1E-01
5047.3	4	2	3.6E-01
5103.3	6	4	5.0E-01
5142.3	2	2	1.9E-01
5201.0	4	4	7.5E-01
5201.3	6	4	6.5E-02
5212.6	4	6	9.8E-02
5212.6	6	6	8.5E-01
5320.7	6	8	9.2E-01
5345.7	4	6	8.8E-01
5345.7	6	6	1.1E-01
5428.6	2	4	4.2E-01
5432.8	4	6	6.8E-01
5453.8	6	8	8.5E-01
5473.6	2	2	7.3E-01
5509.7	4	4	4.0E-01
5526.2	8	8	8.1E-02
5536.8	4	6	6.6E-02
5556.0	4	2	1.1E-01
5564.9	6	6	1.7E-01
5578.8	6	6	1.1E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
5606.1	10	8	5.4E-01
5616.6	4	4	1.2E-01
5640.0	4	6	6.6E-01
5645.6	6	4	1.8E-02
5647.0	2	4	5.7E-01
5659.9	6	4	4.6E-01
5664.7	4	2	5.8E-01
5819.2	4	4	8.5E-02
6305.5	8	6	1.8E-01
6312.7	6	4	3.0E-01
S III			
2496.2	7	5	2.5E+00
2508.2	5	3	2.3E+00
2636.9	3	5	4.5E-01
2665.4	5	5	1.4E+00
2680.5	1	3	6.2E-01
2691.8	3	3	4.6E-01
2702.8	3	1	1.9E+00
2718.9	3	3	1.2E+00
2721.4	5	3	7.7E-01
2726.8	3	5	6.0E-01
2731.1	5	5	1.1E+00
2756.9	7	7	1.4E+00
2785.5	3	3	6.1E-01
2856.0	5	7	5.1E+00
2863.5	7	9	5.7E+00
2872.0	3	5	4.7E+00
2950.2	3	5	3.0E+00
2964.8	5	7	4.0E+00
3662.0	3	3	6.4E-01
3717.8	5	3	1.0E+00
3778.9	3	5	4.4E-01
3831.8	1	3	5.6E-01
3837.8	3	3	4.2E-01
3838.3	5	5	1.3E+00
3860.6	3	1	1.6E+00
3899.1	5	3	6.7E-01
4253.6	5	7	1.2E+00
4285.0	3	5	9.0E-01
S IV			
551.17	2	2	2.06E+01
554.07	4	2	4.08E+01
3097.5	2	4	2.6E+00
3117.7	2	2	2.5E+00
S V			
437.37	1	3	1.12E+01
438.19	3	3	3.33E+01
439.65	5	3	5.5E+01
*661.52	9	15	6.44E+01
*679.01	9	15	8.6E+01
*690.75	9	9	5.0E+01
786.48	1	3	5.25E+01
*854.85	9	9	4.18E+01
S VI			
248.99	2	4	3.1E+01
249.27	2	2	3.1E+01
388.94	2	2	4.5E+01
390.86	4	2	8.8E+01
706.48	2	4	4.17E+01
712.68	4	6	4.85E+01
712.84	4	4	8.1E+00
933.38	2	4	1.7E+01
944.52	2	2	1.6E+01
S VII			
60.161	1	3	9.46E+03
60.804	1	3	5.1E+02
72.029	1	3	8.61E+02
S VIII			
198.55	4	2	2.5E+02
202.61	2	2	1.2E+02
S XI			
*189.90	9	3	4.3E+02
190.37	5	3	2.8E+02
215.95	5	5	1.4E+02
217.63	1	3	7.2E+01
239.81	1	3	2.6E+01
242.57	3	5	1.9E+01
242.82	3	3	1.9E+01
246.90	5	5	5.4E+01
247.12	5	3	3.0E+01
*288.49	9	15	2.9E+01
S XII			
212.14	2	4	3.7E+01
215.18	2	2	1.4E+02
218.20	4	4	1.7E+02
221.44	4	2	6.4E+01
227.50	2	2	3.7E+01
234.48	4	2	6.8E+01
S XIII			
32.236	1	3	1.09E+04
37.600	3	1	1.3E+03
256.66	1	3	8.7E+01
299.89	3	5	1.78E+01
303.37	1	3	2.28E+01
307.36	3	3	1.64E+01
308.91	5	5	4.82E+01
312.68	3	1	6.3E+01
316.84	5	3	2.50E+01
500.42	3	5	1.43E+01
S XIV			
*30.434	2	6	8.28E+03
*32.517	6	10	2.6E+04
417.67	2	4	1.2E+01
445.71	2	2	1.0E+01
1550	2	4	1.4E+00
1663	2	2	1.2E+00
3967	2	4	5.4E-02
4153	4	6	5.7E-02
Tantalum			
Ta I			
3127.9	4	6	5.7E-03
3168.3	4	4	6.0E-03
3170.3	8	10	8.5E-02
3205.5	6	8	5.6E-03
3260.2	4	4	5.8E-03
3337.8	6	6	1.3E-02
3383.9	6	4	5.3E-03
3406.9	4	6	6.8E-02
3419.7	8	8	1.91E-02
3463.8	4	6	2.62E-02
3484.6	4	4	8.5E-03
3488.8	6	4	7.3E-03
3497.9	6	8	4.9E-02
3505.0	8	6	2.72E-02
3553.4	4	6	3.3E-03
3607.4	6	8	4.6E-02
3625.2	10	8	1.0E-02
3626.6	8	10	7.1E-02
3642.1	10	12	5.5E-02
3657.5	6	6	4.3E-03
3731.0	4	6	5.3E-03
3754.5	8	8	6.5E-03
3784.3	4	6	4.3E-02
3792.1	4	4	9.0E-03
3826.9	6	6	5.2E-03
3836.6	8	10	4.0E-03
3848.1	10	8	1.30E-02
3858.6	10	10	2.5E-03
3918.5	4	2	2.5E-02
3922.8	4	4	3.98E-02
3996.2	2	4	3.35E-02
3999.3	4	4	1.8E-02
4003.7	10	8	3.1E-03
4006.8	6	8	7.6E-03
4026.9	4	4	3.60E-02
4029.9	10	10	2.8E-02
4030.7	8	10	2.3E-03
4040.9	10	12	7.3E-03
4061.4	2	4	6.5E-02
4064.6	4	4	3.83E-02
4067.2	6	4	6.8E-03
4067.9	6	8	8.4E-03
4097.2	10	10	2.1E-03
4105.0	6	4	1.1E-02
4136.2	8	6	1.82E-02
4147.9	10	8	1.79E-02
4175.2	6	8	2.8E-02
4205.9	8	10	8.9E-03
4303.0	6	6	2.08E-02
4378.8	8	6	4.8E-03
4386.1	4	6	1.0E-02
4402.5	6	6	2.28E-02
4415.7	2	4	2.53E-02
4441.0	4	6	7.5E-03
4441.7	10	8	9.0E-03
4473.5	6	8	1.36E-02
4511.0	10	12	1.56E-02
4511.5	10	8	3.6E-03
4514.2	10	10	3.1E-03
4521.1	10	10	2.3E-03
4530.9	4	6	2.42E-02
4547.2	4	6	5.3E-03
4553.7	6	8	9.5E-03
4565.9	8	8	2.5E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
4574.3	4	4	1.2E-02
4580.7	8	10	2.1E-03
4619.5	6	4	5.3E-02
4633.1	4	4	1.2E-02
4669.1	6	4	2.85E-02
4681.9	6	6	1.5E-02
4684.9	10	8	2.8E-03
4685.3	6	8	3.4E-03
4691.9	2	4	4.08E-02
4706.1	6	6	1.4E-02
4740.2	4	4	5.0E-02
4758.0	4	6	7.5E-03
4769.0	8	8	2.8E-02
4780.9	10	8	2.16E-02
4812.8	4	4	1.2E-02
4825.4	6	6	2.63E-02
4832.2	4	4	1.7E-02
4852.2	4	4	1.7E-02
4884.0	6	8	1.1E-02
4904.6	12	10	1.95E-02
4920.9	8	10	2.1E-03
4921.3	2	4	1.2E-02
4926.0	4	4	1.5E-02
4936.4	8	6	4.5E-02
4969.7	4	4	1.0E-02
5012.5	4	4	1.9E-02
5037.4	10	8	4.4E-02
5043.3	6	4	2.73E-02
5067.9	8	6	2.92E-02
5069.9	10	12	1.7E-03
5082.3	10	12	1.9E-03
5087.4	6	4	1.5E-02
5090.7	8	6	9.5E-03
5095.3	6	6	5.0E-03
5136.5	2	2	4.5E-02
5141.6	4	2	1.2E-02
5143.7	6	4	1.7E-02
5147.6	6	4	9.0E-03
5161.8	4	6	6.3E-03
5218.7	8	6	8.2E-03
5235.4	6	6	4.7E-03
5295.0	6	6	7.5E-03
5336.1	6	8	5.5E-03
5349.6	6	4	2.2E-02
5354.7	4	4	6.5E-03
5396.0	6	8	2.5E-03
5402.5	4	2	1.4E-02
5435.3	4	6	1.1E-02
5499.4	10	10	6.1E-03
5518.9	8	10	3.8E-02
5620.7	8	10	6.0E-03
5640.2	6	8	4.9E-03
5645.9	6	8	1.43E-02
5699.2	6	6	4.2E-03
5767.9	6	8	2.6E-03
5780.7	4	6	3.3E-03
5811.1	8	6	5.7E-03
5849.7	10	8	2.8E-03
5877.4	10	12	2.3E-02
5939.8	2	4	1.6E-02
5944.0	4	6	2.13E-02
5997.2	10	10	2.4E-02
6020.7	2	4	1.0E-02
6045.4	6	8	2.6E-02
6047.3	8	10	9.0E-03
6249.8	6	6	3.5E-03
6258.7	6	8	3.3E-03
6309.6	4	6	1.83E-02
6360.8	6	8	4.6E-03
6428.6	6	6	6.0E-03
6430.8	8	8	2.9E-02
6450.4	8	10	2.2E-02
6485.4	10	10	5.8E-02
6514.4	6	4	2.2E-02
6516.1	6	8	1.25E-02
6612.0	6	4	1.9E-02
6673.7	2	4	9.0E-03
6771.7	4	4	5.8E-03
6866.2	8	6	2.58E-02
6927.4	10	12	1.01E-02
6928.5	10	8	1.69E-02
6951.3	10	10	3.7E-03
6953.9	6	8	8.3E-03
6966.1	8	8	1.2E-02
6969.5	10	10	2.9E-03
7407.9	6	4	2.0E-02
Thallium			
Tl I			
2104.6	2	4	4.0E-02
2118.9	2	2	2.0E-02
2129.3	2	4	5.8E-02
2151.9	2	2	3.1E-02
2168.6	2	4	9.8E-02
2237.8	2	4	1.9E-01
2316.0	2	2	7.8E-02
2379.7	2	4	4.4E-01
2507.9	4	2	1.1E-02
2538.2	4	2	1.6E-02
2580.1	2	2	1.8E-01
2609.0	4	6	1.0E-01
2609.8	4	4	1.9E-02
2665.6	4	2	5.7E-02
2709.2	4	6	1.7E-01
2710.7	4	4	3.7E-02
2767.9	2	4	1.26E+00
2826.2	4	2	8.0E-02
2918.3	4	6	4.2E-01
2921.5	4	4	7.6E-02
3229.8	4	2	1.73E-01
3519.2	4	6	1.24E+00
3529.4	4	4	2.20E-01
3775.7	2	2	6.25E-01
5350.5	4	2	7.05E-01
Thulium			
Tm I			
2513.8	8	10	6.9E-02
2527.0	8	8	1.7E-01
2596.5	8	10	1.6E-01
2601.1	8	6	1.7E-01
2622.5	8	10	6.1E-02
2841.1	6	6	2.0E-01
2854.2	8	6	2.7E-01
2914.8	8	8	7.7E-02
2933.0	8	6	1.0E-01
2973.2	8	8	2.3E-01
3046.9	8	8	1.8E-01
3081.1	8	8	1.9E-01
3122.5	6	6	5.2E-01
3142.4	6	6	8.8E-02
3172.7	8	8	1.8E-01
3233.7	8	10	5.1E-02
3247.0	6	8	3.0E-01
3251.8	6	4	5.2E-01
3380.7	6	8	2.0E-01
3406.0	6	8	1.5E-01
3410.1	8	10	1.0E-01
3416.6	8	8	5.7E-02
3418.6	6	6	1.1E-01
3563.9	8	6	9.8E-02
3567.4	8	10	4.2E-02
3744.1	8	8	9.5E-01
3751.8	8	10	1.9E-01
3798.5	6	4	1.2E+00
3807.7	6	6	3.9E-01
3883.1	8	6	1.0E+00
3887.4	8	8	3.8E-01
3916.5	6	8	1.5E+00
3949.3	6	6	1.0E+00
4022.6	6	8	4.0E-02
4044.5	6	4	2.9E-01
4094.2	8	6	9.0E-01
4105.8	8	10	6.0E-01
4138.3	6	4	7.0E-01
4158.6	6	8	5.5E-02
4187.6	8	8	6.1E-01
4203.7	8	10	2.5E-01
4222.7	6	8	1.5E-01
4271.7	6	6	1.1E-01
4359.9	8	6	1.3E-01
4386.4	8	8	4.2E-02
4394.4	6	4	1.1E-01
4643.1	6	6	3.4E-02
4681.9	6	8	3.9E-02
4691.1	6	6	3.9E-02
5307.1	8	10	2.3E-02
5658.3	6	8	1.0E-02
5675.8	8	10	1.3E-02
5760.2	6	6	1.3E-02
Tin			
Sn I			
2073.1	1	3	3.6E-02
2199.3	3	5	2.9E-01
2209.7	5	5	5.6E-01
2246.1	1	3	1.6E+00
2268.9	5	7	1.2E+00
2286.7	5	5	3.1E-01
2317.2	5	7	2.0E+00

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
2334.8	3	3	6.6E-01
2354.8	3	5	1.7E+00
2380.7	3	5	3.1E-02
2408.2	5	3	1.8E-01
2421.7	5	7	2.5E+00
2429.5	5	7	1.5E+00
2433.5	5	3	8.0E-03
2455.2	5	5	1.1E-02
2476.4	5	3	1.1E-02
2483.4	5	5	2.1E-01
2491.8	1	3	1.7E-01
2495.7	5	5	6.2E-01
2523.9	5	3	7.4E-02
2546.6	1	3	2.1E-01
2558.0	1	3	3.4E-01
2571.6	5	7	4.5E-01
2594.4	5	5	3.0E-01
2636.9	1	3	1.1E-01
2661.2	3	3	1.1E-01
2706.5	3	5	6.6E-01
2761.8	5	5	3.7E-03
2779.8	5	7	1.8E-01
2785.0	5	3	1.4E-01
2788.0	1	3	1.4E-01
2812.6	1	3	2.3E-01
2813.6	5	5	1.2E-01
2840.0	5	5	1.7E+00
2850.6	5	5	3.3E-01
2863.3	1	3	5.4E-01
2913.5	1	3	8.3E-01
3009.1	3	3	3.8E-01
3032.8	1	3	6.2E-01
3034.1	3	1	2.0E+00
3141.8	1	3	1.9E-01
3175.1	5	3	1.0E+00
3218.7	1	3	4.7E-02
3223.6	5	5	1.2E-03
3262.3	5	3	2.7E+00
3330.6	5	5	2.0E-01
3655.8	1	3	4.1E-02
3801.0	5	3	2.8E-01
4524.7	1	3	2.6E-01
5631.7	1	3	2.4E-02
5970.3	5	3	9.6E-02
6037.7	5	5	5.0E-02
6069.0	1	3	4.6E-02
6073.5	3	1	6.3E-02
6171.5	3	3	4.9E-02
Sn II			
2368.3	4	2	4.4E-03
2449.0	4	6	3.7E-01
2487.0	6	8	5.5E-01
3283.2	4	6	1.0E+00
3352.0	6	8	1.0E+00
3472.5	2	4	1.6E-01
3575.5	4	6	1.3E-01
5332.4	2	4	8.6E-01
5562.0	4	6	1.2E+00
5588.9	4	6	8.5E-01
5596.2	4	4	1.5E-01
5797.2	6	6	2.8E-01
5799.2	6	8	8.1E-01
6453.5	2	4	1.2E+00
6761.5	2	2	3.2E-01
6844.1	2	2	6.6E-01
Titanium			
Ti I			
2276.75	7	5	1.3E+00
2280.00	9	7	9.4E-01
2299.86	5	5	6.9E-01
2302.75	7	7	5.7E-01
2305.69	9	9	5.2E-01
2424.26	9	9	1.7E-01
2520.54	5	3	3.8E-01
2529.87	7	5	3.8E-01
2541.92	9	7	4.3E-01
2599.91	5	5	6.7E-01
2605.16	7	7	6.4E-01
2611.29	9	9	6.4E-01
2611.47	7	5	3.3E-01
2619.94	9	7	2.1E-01
2631.55	7	7	1.7E-01
2632.42	5	5	2.7E-01
2641.12	5	3	1.8E+00
2644.28	7	5	1.4E+00
2646.65	9	7	1.5E+00
2733.27	5	5	1.9E+00
2735.30	3	1	4.1E+00
2912.07	5	7	1.3E+00
2942.00	5	5	1.0E+00
2948.26	7	7	9.3E-01
2956.13	9	9	9.7E-01
2956.80	7	5	1.8E-01
3186.45	5	7	8.0E-01
3191.99	7	9	8.5E-01
3199.92	9	11	9.4E-01
3341.88	5	7	6.5E-01
3354.63	7	9	6.9E-01
3370.44	5	3	7.6E-01
3371.45	9	11	7.2E-01
3377.58	7	5	6.9E-01
3385.94	9	7	5.0E-01
3635.46	5	7	8.04E-01
3642.68	7	9	7.74E-01
3653.50	9	11	7.54E-01
3724.57	9	9	9.1E-01
3725.16	5	3	7.3E-01
3729.81	5	5	4.27E-01
3741.06	7	7	4.17E-01
3752.86	9	9	5.04E-01
3786.04	5	3	1.4E+00
3948.67	5	3	4.85E-01
3956.34	7	5	3.00E-01
3958.21	9	7	4.05E-01
3981.76	5	5	3.76E-01
3989.76	7	7	3.79E-01
3998.64	9	9	4.08E-01
4013.24	7	5	2.0E-01
4055.01	1	3	2.8E-01
4060.26	3	5	2.4E-01
4064.20	3	3	2.4E-01
4065.09	3	1	7.0E-01
4186.12	9	9	2.10E-01
4266.23	5	5	3.1E-01
4284.99	5	5	3.2E-01
4289.07	5	5	3.0E-01
4290.93	3	3	4.5E-01
4295.75	3	1	1.3E+00
4393.93	9	11	3.3E-01
4417.27	11	9	3.6E-01
4449.14	11	11	9.7E-01
4450.90	9	9	9.6E-01
4453.31	5	5	5.98E-01
4453.71	7	7	4.7E-01
4455.32	7	7	4.8E-01
4457.43	9	9	5.6E-01
4465.81	5	7	3.28E-01
4481.26	7	7	5.7E-01
4496.15	7	5	4.4E-01
4518.02	7	9	1.72E-01
4522.80	5	7	1.9E-01
4527.31	3	5	2.2E-01
4533.24	11	11	8.83E-01
4534.78	9	9	6.87E-01
4544.69	5	3	3.3E-01
4548.76	7	5	2.85E-01
4552.45	9	7	2.1E-01
4563.43	9	11	2.1E-01
4617.27	7	9	8.51E-01
4623.10	5	7	5.74E-01
4639.94	3	3	6.64E-01
4640.43	3	1	5.0E-01
4645.19	3	1	8.57E-01
4650.02	5	3	2.6E-01
4742.79	9	9	5.3E-01
4758.12	11	11	7.13E-01
4759.27	13	13	7.40E-01
4778.26	9	9	2.0E-01
4805.42	5	7	5.8E-01
4840.87	5	5	1.76E-01
4856.01	13	15	5.2E-01
4885.08	11	13	4.90E-01
4913.62	7	9	4.44E-01
4928.34	3	5	6.2E-01
4981.73	11	13	6.60E-01
4989.14	7	5	3.25E-01
4991.07	9	11	5.84E-01
4999.50	7	9	5.27E-01
5000.99	9	7	3.52E-01
5007.21	5	7	4.92E-01
5014.28	3	5	6.8E-01
5036.47	7	9	3.94E-01
5038.40	5	7	3.87E-01
5062.11	5	3	2.98E-01
5210.39	9	9	3.57E-02
5222.69	3	3	1.95E-01
5224.30	11	11	3.6E-01
5259.98	5	7	2.3E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
5351.07	7	7	3.4E-01
5503.90	11	9	2.6E-01
5774.04	9	11	5.5E-01
5785.98	11	13	6.1E-01
5804.27	13	15	6.8E-01
6098.66	9	7	2.5E-01
6220.46	9	7	1.8E-01
Ti II			
2440.91	4	4	5.1E-01
2451.18	6	6	4.5E-01
2525.59	10	8	5.6E-01
2531.28	8	6	4.9E-01
2534.63	6	4	5.4E-01
2535.89	4	2	6.8E-01
2555.99	6	8	3.2E-01
2635.44	4	4	1.9E+00
2638.56	6	6	1.7E+00
2642.02	8	8	1.9E+00
2645.86	10	10	2.7E+00
2746.54	6	8	2.6E+00
2751.59	8	10	3.7E+00
2752.68	8	10	1.1E+00
2757.62	6	8	7.2E-01
2758.35	4	6	9.9E-01
2758.79	2	4	4.4E-01
2764.28	4	4	7.4E-01
2804.82	6	8	4.6E+00
2810.30	8	10	5.1E+00
2817.83	10	12	3.8E+00
2819.87	8	8	6.5E-01
2821.26	6	8	7.9E-01
2827.12	8	10	1.0E+00
2828.06	12	14	4.4E+00
2828.64	6	6	1.2E+00
2828.83	10	10	9.1E-01
2834.02	10	12	7.9E-01
2836.47	8	8	1.2E+00
2839.64	12	12	8.3E-01
2845.93	10	10	1.2E+00
2851.11	2	4	4.1E-01
2856.10	12	12	1.5E+00
2862.33	4	6	4.0E-01
2877.47	8	8	5.7E-01
2884.13	10	10	5.2E-01
2910.65	8	8	4.6E-01
2926.64	10	8	8.9E-01
2931.10	6	6	3.2E+00
2936.02	4	6	2.7E+00
2938.57	6	8	2.4E+00
2941.90	8	10	1.8E+00
2942.97	8	8	1.1E+00
2945.30	10	12	2.7E+00
2952.00	8	8	3.0E-01
2954.59	10	12	4.0E+00
2958.80	8	10	4.0E+00
2979.06	4	6	1.2E+00
2990.06	6	8	5.6E-01
3017.17	12	12	3.6E-01
3022.64	10	10	1.2E+00
3023.67	8	8	1.0E+00
3029.76	10	10	3.5E-01
3056.75	2	4	3.2E-01
3058.08	6	6	5.0E-01
3066.34	4	4	3.3E-01
3071.25	6	4	3.6E-01
3072.99	4	2	1.6E+00
3075.23	6	4	1.13E+00
3078.65	8	6	1.09E+00
3081.52	10	8	1.1E+00
3088.04	10	8	1.25E+00
3089.44	8	6	1.3E+00
3097.20	4	6	4.4E-01
3103.81	10	8	1.1E+00
3105.10	2	4	6.3E-01
3106.26	6	6	7.8E-01
3117.67	4	2	1.1E+00
3119.83	6	4	5.9E-01
3127.86	6	6	1.6E+00
3128.50	8	8	1.1E+00
3161.23	4	2	5.9E-01
3161.80	6	4	4.6E-01
3162.59	8	6	3.9E-01
3168.55	10	8	4.1E-01
3181.73	6	8	4.6E-01
3182.54	4	6	4.3E-01
3189.49	4	4	9.2E-01
3190.91	6	8	1.3E+00
3202.56	4	6	1.1E+00
3224.25	12	10	7.0E-01
3228.62	4	2	2.0E+00
3232.29	8	6	6.0E-01
3234.51	10	10	1.38E+00
3236.13	4	4	7.0E-01
3236.58	8	8	1.11E+00
3239.04	6	6	9.87E-01
3239.66	6	4	9.4E-01
3241.99	4	4	1.16E+00
3251.91	6	4	3.38E-01
3252.92	8	6	3.9E-01
3272.07	2	4	3.2E-01
3278.28	4	4	9.6E-01
3278.91	6	4	1.0E+00
3282.32	2	2	1.6E+00
3287.66	8	10	1.4E+00
3315.32	2	4	3.8E-01
3321.70	4	4	7.2E-01
3322.94	10	10	3.96E-01
3329.46	8	8	3.25E-01
3332.11	6	4	1.1E+00
3340.34	4	4	3.6E-01
3361.23	8	10	1.1E+00
3372.80	6	8	1.11E+00
3383.77	4	6	1.09E+00
3452.49	2	2	7.7E-01
3456.40	4	4	8.2E-01
3465.56	4	2	4.1E-01
3483.63	10	8	9.7E-01
3492.37	8	6	9.8E-01
3504.90	10	10	8.2E-01
3510.86	8	8	9.3E-01
3520.27	2	4	4.8E-01
3535.41	4	6	5.5E-01
3641.33	4	2	4.9E-01
3706.23	4	4	3.1E-01
3741.64	6	6	6.2E-01
3757.70	4	4	4.1E-01
3759.30	8	8	9.4E-01
3761.33	6	6	9.9E-01
4911.18	6	4	3.2E-01
Ti III			
865.79	5	3	6.6E+01
1002.37	5	5	7.6E+00
1004.67	7	5	4.3E+01
1005.80	3	3	1.3E+01
1007.16	5	3	3.8E+01
1008.12	3	1	5.1E+01
1286.37	9	9	2.0E+00
1289.30	7	7	2.2E+00
1291.62	5	5	2.4E+00
1293.23	9	7	1.0E+00
1298.97	7	5	4.9E+00
1327.59	5	3	3.2E+00
1420.44	1	3	1.2E+00
1421.63	3	1	4.0E+00
1422.41	5	5	3.0E+00
1424.14	5	3	1.6E+00
1455.19	9	7	6.4E+00
1498.70	5	5	2.8E+00
2007.36	3	3	3.4E+00
2007.60	1	3	1.2E+00
2010.80	5	3	5.4E+00
2097.30	5	7	3.3E+00
2099.86	3	5	2.5E+00
2104.86	3	3	1.1E+00
2105.09	1	3	1.7E+00
2199.22	3	3	5.7E+00
2237.77	7	7	2.4E+00
2331.35	3	1	4.3E+00
2331.66	3	3	1.2E+00
2339.00	5	3	3.0E+00
2346.79	7	5	3.3E+00
2374.99	5	3	4.0E+00
2413.99	5	7	3.8E+00
2516.05	7	9	3.4E+00
2567.56	3	3	2.3E+00
2984.75	5	5	1.9E+00
3066.51	3	3	2.5E+00
3228.89	3	3	1.5E+00
3278.31	7	9	3.4E+00
3320.94	3	5	2.8E+00
3340.20	7	9	3.7E+00
3346.18	9	11	3.7E+00
3354.71	11	13	4.4E+00
3397.24	3	1	1.8E+00
3404.46	3	3	1.8E+00
3417.62	3	5	1.9E+00
3915.47	9	11	2.1E+00
4119.14	5	5	9.9E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
4213.26	9	11	2.2E+00
4215.53	9	11	2.2E+00
4247.62	11	13	1.1E+00
4248.54	5	7	2.3E+00
4250.09	3	5	9.5E-01
4259.01	11	13	9.4E-01
4269.84	9	11	1.7E+00
4285.61	13	15	3.0E+00
4288.66	11	13	1.1E+00
4296.70	11	13	1.6E+00
4319.56	9	11	1.1E+00
4343.25	3	1	1.0E+00
4378.94	3	5	1.6E+00
4433.91	11	13	1.8E+00
4440.66	1	3	1.2E+00
4533.26	3	5	1.5E+00
4576.53	9	7	1.3E+00
4628.07	3	1	1.5E+00
4652.86	7	9	2.6E+00
4874.00	5	7	1.5E+00
4914.32	3	3	1.1E+00
4971.19	9	11	2.1E+00
5083.80	5	3	9.7E-01
5278.33	3	3	9.4E-01
7506.87	11	13	1.1E+00
Ti IV			
423.49	4	6	4.9E+01
424.16	6	8	5.3E+01
433.63	4	2	5.5E+00
433.76	6	4	5.0E+00
729.36	4	2	5.7E+00
1183.64	2	2	6.9E+00
1195.21	4	2	1.4E+01
1451.74	2	4	1.8E+01
1467.34	4	6	2.1E+01
2067.56	2	4	5.1E+00
2103.16	2	2	5.0E+00
2541.79	4	6	6.9E+00
2546.88	6	8	7.4E+00
2862.60	4	2	4.1E+00
3576.44	4	6	4.6E+00
Ti VIII			
249	6	4	1.0E+01
258.610	6	8	7.5E+02
269.533	4	6	6.0E+02
272.037	4	4	4.3E+02
272.843	6	4	6.2E+01
276.701	2	4	9.3E+01
277.813	4	4	3.8E+02
289.375	2	4	3.6E+01
478.971	4	4	1.7E+01
480.376	6	6	1.5E+01
Ti IX			
267.941	5	7	5.1E+02
278.713	5	7	4.7E+02
281.446	3	1	3.2E+02
285.128	1	3	4.1E+02
433.567	1	3	6.9E+00
439.513	3	3	7.5E+00
439.745	3	1	2.1E+01
447.484	5	5	1.6E+01
447.701	5	3	6.5E+00
507.174	3	5	6.5E+00
516.215	5	7	6.9E+00
Ti X			
253	4	6	2.1E+02
254	6	8	2.3E+02
281	2	2	1.1E+02
289.579	2	4	2.5E+02
290.294	4	6	1.1E+02
291	4	2	1.8E+02
291	2	2	2.3E+02
292	6	8	1.1E+02
293.684	6	8	2.97E+02
293.798	6	6	1.7E+02
295.584	4	6	2.9E+02
296	4	6	1.4E+02
297	4	6	9.9E+01
298	4	6	4.3E+02
302	2	2	1.6E+02
305	2	4	2.5E+02
317	2	2	1.5E+02
355.815	2	2	1.3E+02
360.133	4	4	2.19E+02
363	4	2	2.1E+02
363	6	6	1.3E+02
365.628	4	2	1.2E+02
382	4	6	1.8E+02
385	6	8	1.8E+02
389.99	6	4	1.1E+02
Ti XI			
65.403	1	3	5.1E+02
87.725	1	3	8.5E+02
266	5	7	1.8E+02
308.250	3	5	1.3E+02
313.229	5	7	1.6E+02
318	3	1	1.4E+02
322.75	5	7	1.99E+02
323	1	3	1.8E+02
327.192	3	5	2.9E+02
332	3	1	3.25E+02
386.140	1	3	1.48E+02
408	7	9	1.37E+02
425.74	3	1	1.2E+02
446.69	3	1	1.2E+02
453	5	7	1.3E+02
Ti XII			
52.896	2	4	1.61E+02
53.140	4	6	1.9E+02
53.433	2	4	2.1E+02
53.457	2	2	2.1E+02
55.181	2	4	2.4E+02
55.443	4	6	2.81E+02
59.133	2	4	3.72E+02
59.435	4	6	4.41E+02
60.701	2	4	3.4E+02
60.762	2	2	3.5E+02
61.286	4	2	1.8E+02
62.433	4	6	2.08E+02
62.470	6	8	2.22E+02
65.540	4	6	3.2E+02
65.577	6	8	3.5E+02
67.171	2	4	6.2E+02
67.555	4	6	7.2E+02
70.986	4	6	5.7E+02
71.031	6	8	6.1E+02
71.545	2	2	1.8E+02
71.987	4	2	3.48E+02
82.121	2	4	5.9E+02
82.307	4	6	1.13E+03
82.344	2	2	5.8E+02
82.368	6	8	1.2E+03
89.844	2	4	9.9E+02
90.512	4	6	1.16E+03
90.547	4	4	1.9E+02
116.497	4	6	3.0E+03
116.597	6	8	3.2E+03
116.62	6	6	2.1E+02
139.884	6	4	2.6E+02
140.361	4	2	2.9E+02
141.6	4	6	1.7E+02
141.7	6	8	1.7E+02
169.7	4	6	2.8E+02
169.8	6	8	2.9E+02
207.2	2	4	1.5E+02
208.5	4	6	1.8E+02
252.8	4	6	4.8E+02
253.1	6	8	5.2E+02
257.5	4	2	2.4E+02
Ti XIII			
23.356	1	3	1.02E+05
23.698	1	3	1.2E+04
23.991	1	3	3.4E+02
26.641	1	3	4.06E+03
26.960	1	3	3.06E+03
117.1	3	3	1.3E+02
117.3	3	1	2.8E+02
120.2	5	3	5.4E+02
120.2	7	5	4.4E+02
128.7	3	3	1.2E+02
Ti XIV			
21.341	4	6	9.8E+03
21.522	2	4	4.5E+04
21.657	4	4	1.3E+04
21.733	4	4	8.8E+04
21.82	4	2	6.4E+04
21.883	2	4	7.0E+04
21.958	2	4	1.2E+04
22.05	2	2	1.4E+04
24.592	4	2	6.1E+03
24.891	2	2	7.5E+03
Ti XV			
20.19	5	7	6.9E+03
20.234	5	7	1.9E+04

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
20.234	3	3	4.9E+04
20.246	1	3	4.2E+04
20.250	5	3	6.5E+03
20.29	3	3	1.1E+04
20.30	1	3	3.4E+04
20.30	1	1	5.8E+04
20.313	5	3	7.5E+04
20.418	5	7	8.0E+04
20.538	3	3	3.8E+04
20.54	3	1	4.1E+04
20.551	1	3	1.3E+04
20.689	5	7	4.3E+04
20.698	1	3	1.1E+05
20.771	5	3	1.1E+04
20.897	5	7	2.85E+04
20.928	5	5	8.4E+03
21.065	3	3	1.1E+04
21.079	1	3	1.58E+04
21.102	3	5	1.3E+04
22.482	5	3	6.4E+03
22.936	5	5	1.1E+04
22.966	5	3	1.1E+04
23.034	1	3	6.3E+03
Ti XVI			
110.561	4	2	3.36E+02
116.198	4	4	1.45E+02
118.215	6	4	7.4E+02
121.382	4	2	2.4E+02
124.805	4	2	6.1E+02
129.075	4	2	3.81E+02
134.724	2	2	2.6E+02
138.800	6	4	3.5E+02
143.459	4	4	2.8E+02
145.665	6	6	2.3E+02
157.812	4	2	1.32E+02
161.168	4	4	1.2E+02
163.610	4	2	1.92E+02
169.740	4	6	1.0E+02
176.267	2	2	2.45E+02
178.240	4	4	2.52E+02
Ti XVII			
18.05	3	3	4.5E+04
18.13	5	3	2.4E+04
18.13	1	3	8.1E+04
18.176	5	7	9.2E+04
123.654	3	3	2.3E+02
124.553	5	3	5.2E+02
127.782	5	3	4.6E+02
135.202	3	1	2.93E+02
136.160	5	3	1.95E+02
136.393	3	3	1.14E+02
141.948	5	5	3.87E+02
142.589	1	3	1.35E+02
144.405	5	5	9.4E+01
146.067	7	5	2.6E+02
154.133	3	1	1.63E+02
156.54	3	1	1.44E+02
158.469	5	5	1.4E+02
159.62	5	3	1.03E+02
163.049	3	1	6.2E+02
186.863	5	5	2.66E+02
207.73	3	1	1.07E+02
Ti XVIII			
17.22	2	4	7.3E+04
17.365	4	6	8.6E+04
17.39	4	4	1.4E+04
133.852	2	4	5.2E+01
144.759	4	4	3.2E+02
150.15	6	4	1.15E+02
153.15	4	2	1.97E+02
153.23	2	4	6.7E+01
159.00	4	4	1.16E+02
166.225	6	4	1.54E+02
179.902	2	4	6.3E+01
189.663	6	6	9.6E+01
191.23	4	4	6.6E+01
197.838	4	6	4.56E+01
208.07	4	4	1.2E+02
Ti XIX			
15.67	3	1	3.3E+04
15.68	5	5	2.7E+04
15.74	5	7	2.7E+04
15.75	3	5	2.4E+04
15.83	1	3	3.2E+04
15.86	1	3	2.9E+04
16.02	3	1	3.1E+04
16.18	3	5	3.8E+04
16.41	1	3	6.1E+04
16.43	3	5	8.2E+04
16.46	3	3	4.4E+04
16.51	5	7	1.0E+05
16.55	5	5	2.7E+04
16.61	3	1	8.0E+04
16.64	3	3	5.3E+04
16.69	1	3	1.02E+05
16.71	3	5	7.3E+04
16.72	5	3	3.3E+04
16.72	5	5	7.3E+04
16.74	5	7	1.2E+05
16.77	3	3	2.6E+04
16.80	5	7	1.81E+05
16.85	3	5	4.4E+04
17.08	3	5	8.3E+04
17.36	1	3	9.5E+04
Ti XX			
2.629	2	4	4.9E+04
2.6295	4	4	3.2E+06
2.631	2	2	6.1E+05
2.6319	2	4	1.5E+06
2.632	2	2	2.7E+06
2.6355	4	6	1.2E+06
8.621	4	2	1.1E+06
9.788	4	6	5.26E+03
10.046	2	4	7.29E+03
10.109	4	6	8.6E+03
*10.278	2	6	8.4E+03
10.620	2	4	1.34E+04
10.690	4	6	1.58E+04
*11.452	2	6	1.7E+04
11.872	2	4	2.8E+04
11.958	4	6	3.4E+04
11.958	4	4	5.6E+03
15.211	2	4	3.50E+04
15.253	2	2	3.58E+04
15.907	2	4	8.84E+04
16.049	4	6	1.05E+05
16.067	4	4	1.8E+04
31.586	4	6	5.49E+03
45.650	2	4	9.6E+03
45.996	4	6	1.1E+04
Ti XXI			
2.0633	1	3	1.32E+05
2.1108	1	3	2.60E+05
2.2211	1	3	6.35E+05
2.497	3	1	2.4E+06
2.505	5	5	3.5E+05
2.505	1	3	1.4E+06
2.507	3	5	1.4E+06
2.508	3	5	7.9E+05
2.510	3	3	6.9E+05
2.510	1	3	9.6E+05
2.511	3	3	1.4E+06
2.512	5	5	1.8E+06
2.512	3	1	1.4E+06
2.513	3	1	2.7E+06
2.513	3	5	2.4E+06
2.514	5	3	1.2E+06
2.520	3	5	2.6E+05
2.527	3	1	1.2E+05
2.539	3	1	4.1E+05
2.6102	1	3	2.40E+06
2.6227	1	3	1.12E+05
Tungsten			
W I			
2879.4	1	3	2.4E-01
2911.0	1	3	7.7E-02
2923.5	7	9	1.54E-02
2935.0	3	5	1.5E-01
3013.8	7	9	6.4E-02
3016.5	9	11	9.27E-02
3017.4	7	9	1.21E-01
3024.9	3	3	1.4E-01
3046.4	3	5	5.8E-02
3049.7	7	5	1.7E-01
3064.9	5	7	1.1E-02
3084.9	5	5	1.3E-02
3093.5	7	9	4.4E-02
3107.2	5	7	2.33E-02
3108.0	7	9	1.58E-02
3145.5	9	9	4.8E-03
3170.2	7	5	6.0E-03
3176.6	3	5	2.12E-02
3183.5	7	7	2.64E-03
3184.4	5	3	2.3E-02
3191.6	1	3	3.2E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3198.8	7	9	4.6E-02
3207.3	7	9	3.0E-02
3208.3	5	5	4.4E-02
3215.6	9	11	2.1E-01
3221.9	5	7	1.61E-02
3223.1	5	3	3.53E-03
3232.5	9	9	2.4E-02
3235.1	7	5	2.68E-03
3259.7	7	7	1.3E-02
3300.8	7	9	8.1E-02
3311.4	7	5	5.6E-02
3363.3	9	7	6.6E-03
3371.0	7	5	1.0E-02
3371.4	3	3	6.7E-03
3386.1	7	7	2.64E-03
3413.0	7	9	9.7E-03
3459.5	9	9	2.04E-03
3510.0	7	9	5.2E-03
3545.2	1	3	3.2E-02
3570.6	5	3	6.7E-03
3606.1	3	5	9.6E-03
3617.5	7	7	1.1E-01
3631.9	3	5	1.3E-02
3675.6	9	11	1.20E-02
3682.1	9	11	2.0E-02
3707.9	7	7	2.9E-02
3757.9	7	9	1.38E-02
3760.1	5	7	1.99E-02
3768.5	3	3	3.47E-02
3780.8	7	5	4.2E-02
3809.2	7	5	9.0E-03
3817.5	7	7	3.1E-02
3829.1	3	3	3.83E-03
3835.1	5	5	5.2E-02
3846.3	3	5	2.14E-02
3847.5	1	3	8.3E-03
3864.3	5	5	5.6E-03
3868.0	7	9	4.6E-02
3881.4	7	7	3.6E-02
3968.5	1	3	5.07E-03
3975.5	9	11	4.1E-03
4001.4	9	9	5.6E-03
4008.8	7	9	1.63E-01
4019.3	5	3	6.7E-03
4028.8	1	3	2.0E-02
4045.6	7	5	2.88E-02
4055.2	7	9	1.79E-03
4070.0	7	5	3.60E-02
4070.6	3	5	5.6E-03
4074.4	7	7	1.0E-01
4088.3	5	3	4.13E-03
4102.7	9	7	4.9E-02
4115.6	11	11	4.8E-03
4137.5	5	7	8.4E-03
4171.2	7	9	8.6E-03
4203.8	9	7	4.9E-03
4219.4	9	7	6.1E-03
4244.4	9	11	1.38E-02
4269.4	7	5	3.04E-02
4283.8	9	7	1.69E-03
4294.6	7	5	1.2E-01
4302.1	7	7	3.6E-02
4355.2	9	9	5.1E-03
4361.8	9	7	1.64E-03
4378.5	7	5	3.48E-03
4458.1	3	5	4.2E-03
4466.3	7	5	1.5E-02
4472.5	13	11	1.55E-03
4484.2	3	5	5.6E-03
4492.3	9	11	3.6E-03
4495.3	11	11	3.3E-03
4504.8	9	7	7.0E-03
4552.5	9	9	1.42E-03
4586.8	1	3	4.20E-03
4592.6	7	9	3.4E-03
4609.9	7	9	1.42E-02
4613.3	9	9	2.9E-03
4634.8	9	9	8.8E-03
4659.9	1	3	1.0E-02
4680.5	7	7	1.4E-02
4720.4	3	5	3.22E-03
4729.6	7	5	7.8E-03
4752.6	3	3	5.20E-03
4757.5	7	5	2.72E-03
4757.8	11	9	4.1E-03
4788.4	9	11	2.6E-03
4843.8	5	5	1.9E-02
4886.9	9	11	8.1E-03
4924.6	13	11	1.75E-03
4931.6	7	5	1.0E-02
4948.6	9	11	1.36E-03
4972.6	9	11	3.9E-03
4982.6	1	3	4.17E-03
4986.9	11	9	6.3E-03
5006.2	9	7	1.2E-02
5015.3	7	9	5.4E-03
5040.4	3	5	5.2E-03
5053.3	3	3	1.9E-02
5071.5	13	11	3.4E-03
5117.6	11	11	1.61E-03
5124.2	5	5	4.0E-03
5141.2	7	9	1.12E-03
5224.7	7	5	1.2E-02
5243.0	9	7	1.1E-02
5254.5	7	5	3.86E-03
5268.6	9	9	1.4E-03
5500.5	11	9	6.9E-03
5514.7	5	3	7.3E-03
5537.7	9	11	2.2E-03
5617.1	7	7	1.47E-03
5631.9	9	7	1.43E-03
5660.7	13	11	6.8E-03
5675.4	5	5	2.20E-03
5796.5	9	7	2.21E-03
5891.6	7	7	1.47E-03
5947.6	5	7	2.40E-03
5965.9	7	5	1.0E-02
6021.5	5	3	8.7E-03
6081.4	5	3	4.7E-03
6203.5	7	7	3.0E-03
6285.9	7	5	6.6E-03
6292.0	3	5	2.26E-03
6303.2	9	9	1.84E-03
6404.2	5	7	1.50E-03
6439.7	9	9	1.29E-03
6445.1	7	5	6.4E-03
6532.4	3	5	4.6E-03
6538.1	11	9	2.7E-03
6563.2	5	5	2.04E-03
6814.9	9	9	1.46E-03
7285.8	13	11	1.47E-03
7569.9	5	3	3.73E-03
7664.9	5	3	3.80E-03
8017.2	5	7	1.6E-03
8358.7	5	7	1.89E-03
9381.4	9	7	1.53E-03

Uranium

U I

3553.0	13	13	2.0E-02
3553.0	9	7	1.4E-02
3553.4	15	13	2.2E-02
3554.5	11	9	8.4E-03
3554.9	15	17	7.9E-03
3555.3	13	15	2.7E-02
3555.8	13	11	4.1E-03
3556.9	13	11	7.5E-03
3557.8	13	13	2.9E-02
3558.0	11	13	1.6E-02
3558.6	9	7	3.9E-02
3559.4	7	9	1.5E-02
3560.3	9	7	6.4E-02
3561.4	15	13	5.5E-02
3561.5	9	9	2.5E-02
3561.8	13	11	5.7E-02
3563.7	13	13	2.9E-02
3563.8	7	7	1.1E-02
3565.0	13	11	2.9E-02
3566.0	13	15	1.7E-02
3566.6	11	11	2.4E-01
3568.8	13	13	3.8E-02
3569.1	17	15	1.1E-01
3569.4	9	9	1.5E-02
3570.1	13	11	1.3E-02
3570.2	11	9	5.3E-03
3570.6	13	15	2.7E-02
3570.7	15	15	1.2E-02
3571.2	11	11	6.3E-03
3571.6	17	15	1.3E-01
3572.9	13	15	1.5E-02
3573.9	13	11	4.0E-02
3574.1	13	15	3.5E-02
3574.8	13	15	1.9E-02
3577.1	17	15	4.3E-02
3577.5	15	13	7.8E-03
3577.8	11	11	8.3E-03
3577.9	13	13	2.3E-02
3578.3	13	11	2.0E-02
3580.0	9	9	1.2E-02
3580.2	11	9	2.9E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3580.4	11	13	7.5E-03
3580.9	13	13	2.1E-02
3582.6	13	13	2.9E-02
3584.6	7	5	2.4E-02
3584.9	13	15	1.8E-01
3585.4	11	11	1.9E-02
3585.8	11	9	2.8E-02
3587.8	9	11	1.3E-02
3588.3	7	9	1.8E-02
3589.7	11	13	2.1E-02
3589.8	15	13	5.9E-02
3590.7	9	7	2.2E-02
3591.7	11	9	5.3E-02
3593.0	11	11	1.4E-02
3593.2	13	15	4.2E-02
3593.7	11	11	7.2E-02

Vanadium

V I

3043.12	6	8	2.3E-01
3050.39	10	8	5.3E-01
3053.65	4	4	1.3E+00
3056.33	6	6	1.3E+00
3060.46	8	8	1.4E+00
3066.37	10	10	2.1E+00
3066.53	6	4	3.2E-01
3075.93	4	6	2.8E-01
3080.33	2	4	2.7E-01
3083.54	6	8	2.5E-01
3087.06	2	2	9.2E-01
3088.11	4	6	4.9E-01
3089.13	4	4	5.3E-01
3093.79	6	6	4.1E-01
3094.69	2	4	4.3E-01
3112.92	4	2	5.0E-01
3183.41	6	8	2.4E+00
3183.96	8	10	2.5E+00
3183.98	4	6	2.4E+00
3185.38	10	12	2.7E+00
3198.01	6	6	3.9E-01
3202.39	8	8	4.0E-01
3205.58	8	10	1.3E+00
3207.41	10	10	2.6E-01
3212.43	10	12	1.4E+00
3218.87	8	6	3.5E-01
3233.19	10	8	3.2E-01
3273.03	8	8	2.7E-01
3284.36	10	10	2.8E-01
3309.18	4	4	3.2E-01
3329.85	6	4	7.7E-01
3356.35	4	6	3.1E-01
3365.55	2	4	4.8E-01
3376.05	4	4	3.2E-01
3377.39	4	2	9.0E-01
3377.62	6	6	6.0E-01
3397.58	6	4	2.3E-01
3400.39	8	8	2.5E-01
3529.73	4	6	4.1E-01
3533.68	6	8	5.2E-01
3533.76	2	4	3.7E-01
3543.49	2	2	6.7E-01
3545.33	4	4	3.7E-01
3553.27	6	6	2.2E-01
3555.14	4	2	2.6E-01
3663.60	4	6	3.1E+00
3667.74	6	8	2.7E+00
3672.41	12	12	9.2E-01
3673.41	8	10	2.7E+00
3676.70	14	14	1.3E+00
3680.12	10	12	2.2E+00
3686.26	10	12	2.3E-01
3687.50	12	14	2.9E+00
3688.07	8	8	3.5E-01
3690.28	2	4	4.5E-01
3692.22	6	6	5.4E-01
3695.34	14	16	2.8E+00
3695.86	4	4	6.6E-01
3703.57	10	8	9.2E-01
3704.70	8	6	6.6E-01
3705.04	6	4	3.6E-01
3706.03	10	10	5.2E-01
3708.71	12	12	4.4E-01
3790.46	10	8	2.3E-01
3794.96	10	10	2.3E-01
3806.79	10	10	2.5E-01
3818.24	4	2	6.73E-01
3828.56	6	4	5.33E-01
3840.75	8	6	5.48E-01
3855.36	4	4	3.30E-01
3855.85	10	8	5.78E-01
3863.86	8	6	3.1E-01
3864.86	6	6	2.70E-01
3871.07	10	8	2.8E-01
3875.07	8	8	2.36E-01
3902.26	10	10	2.68E-01
3921.86	4	2	2.7E-01
3922.43	6	6	2.6E-01
3930.02	10	10	3.3E-01
3934.01	8	8	6.2E-01
3992.80	12	10	1.2E+00
3998.73	14	12	1.0E+00
4050.96	10	10	1.4E+00
4051.35	12	12	1.3E+00
4090.57	8	10	8.5E-01
4092.68	8	10	2.30E-01
4095.48	6	8	7.2E-01
4099.78	6	8	4.10E-01
4102.15	4	6	7.1E-01
4104.77	10	8	2.1E+00
4105.16	4	6	4.9E-01
4109.78	2	4	5.00E-01
4111.78	10	10	1.01E+00
4115.18	8	8	5.80E-01
4116.47	6	6	3.2E-01
4116.59	2	2	2.90E-01
4123.50	4	2	1.00E+00
4128.06	6	4	7.70E-01
4131.99	8	6	5.5E-01
4134.49	10	8	2.90E-01
4232.46	10	10	9.8E-01
4232.95	8	8	7.7E-01
4268.64	14	14	1.2E+00
4271.55	12	12	9.6E-01
4276.95	10	10	9.4E-01
4284.05	8	8	1.2E+00
4291.82	12	14	8.8E-01
4296.10	10	12	7.7E-01
4297.67	8	10	7.0E-01
4298.03	6	8	7.8E-01
4379.23	10	12	1.1E+00
4384.71	8	10	1.1E+00
4389.98	6	8	6.9E-01
4395.22	4	6	5.5E-01
4400.57	2	4	3.4E-01
4406.64	10	10	2.2E-01
4407.63	8	8	4.4E-01
4408.20	6	6	6.0E-01
4416.47	4	2	2.6E-01
4452.01	14	16	9.2E-01
4457.75	10	12	2.7E-01
4460.33	10	8	3.0E-01
4462.36	12	14	7.6E-01
4468.00	8	10	2.3E-01
4469.71	10	12	6.2E-01
4474.04	10	8	4.7E-01
4496.06	8	6	4.0E-01
4514.18	6	4	3.3E-01
4524.21	12	10	3.0E-01
4525.17	4	2	4.1E-01
4529.58	10	8	2.4E-01
4545.40	10	12	7.6E-01
4560.72	8	10	7.0E-01
4571.79	6	8	6.0E-01
4578.73	4	6	6.8E-01
4706.16	6	4	2.4E-01
4757.47	4	2	7.6E-01
4766.62	6	4	5.6E-01
4776.36	8	6	5.1E-01
4786.50	10	8	4.7E-01
4796.92	12	10	4.8E-01
4807.52	14	12	5.8E-01
5193.00	12	12	4.0E-01
5195.39	8	8	2.3E-01
5234.08	10	10	4.9E-01
5240.87	12	12	4.3E-01
5415.25	12	14	3.1E-01
5487.91	12	10	2.9E-01
5507.75	10	8	3.5E-01
6090.21	8	6	2.60E-01

V II

2527.90	13	13	6.1E-01
2528.47	9	9	5.2E-01
2528.83	11	11	5.3E-01
2554.04	9	9	5.4E-01
2589.10	9	9	7.7E-01
2640.86	5	7	1.2E+00
2677.80	3	5	3.4E-01
2679.33	7	7	3.4E-01
2683.09	1	3	3.4E-01

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
2687.96	9	9	7.6E-01
2689.88	3	1	9.2E-01
2690.25	7	5	3.4E-01
2690.79	5	3	5.2E-01
2700.94	9	11	3.5E-01
2706.17	7	9	3.4E-01
2734.22	9	7	6.2E-01
2753.41	13	11	4.2E-01
2784.20	9	9	1.3E+00
2787.91	7	9	5.0E-01
2825.86	9	7	1.2E+00
2843.82	7	5	9.9E-01
2847.57	9	7	4.6E-01
2854.34	11	9	5.0E-01
2862.31	11	11	3.6E-01
2868.11	5	3	2.1E+00
2869.13	13	11	4.8E-01
2882.49	5	5	4.2E-01
2884.78	3	3	5.6E-01
2889.61	3	1	1.9E+00
2891.64	5	3	1.4E+00
2892.43	9	9	3.6E-01
2892.65	7	5	1.3E+00
2893.31	9	7	1.2E+00
2903.07	3	5	3.4E-01
2906.45	7	7	7.8E-01
2908.81	11	9	1.6E+00
2910.01	5	5	1.1E+00
2910.38	3	3	1.2E+00
2911.05	7	9	3.7E-01
2912.46	11	9	5.0E-01
2915.88	9	7	4.9E-01
2924.02	11	11	1.7E+00
2924.63	9	9	1.2E+00
2930.80	7	7	5.8E-01
2941.37	11	9	3.5E-01
2944.57	9	7	7.6E-01
2948.08	9	11	4.0E-01
2952.07	7	5	7.2E-01
2955.58	7	9	3.3E-01
2968.37	7	9	7.0E-01
2972.26	5	7	5.2E-01
2973.98	9	11	3.5E-01
2985.18	7	9	4.4E-01
3001.20	7	7	7.5E-01
3014.82	5	3	8.9E-01
3016.78	7	5	5.0E-01
3020.21	9	7	5.0E-01
3048.21	11	13	7.0E-01
3063.25	9	11	1.0E+00
3100.94	7	7	5.8E-01
3113.56	11	11	5.0E-01
3122.89	11	13	7.6E-01
3134.93	13	13	5.9E-01
3136.50	11	11	5.3E-01
3139.73	9	9	5.2E-01
3151.32	3	5	4.4E-01
3190.69	9	9	3.3E-01
3250.78	11	9	5.2E-01
3251.87	5	7	3.5E-01
3271.12	7	9	6.9E-01
3276.12	9	11	5.2E-01
3279.84	9	11	5.8E-01
3287.71	5	7	7.5E-01
3337.85	5	7	5.3E-01
3517.30	9	7	3.8E-01
3530.77	5	3	4.5E-01
3545.19	7	5	4.3E-01
3556.80	9	7	5.1E-01
3592.01	7	5	4.4E-01
3618.92	3	5	3.3E-01
V III			
2318.06	8	10	4.6E+00
2323.82	6	8	3.8E+00
2330.42	10	10	3.2E+00
2331.75	8	8	2.5E+00
2334.21	6	6	2.2E+00
2337.13	4	4	2.7E+00
2343.10	6	8	3.6E+00
2358.73	6	8	4.2E+00
2366.31	8	10	4.2E+00
2371.06	10	12	5.2E+00
2373.06	4	6	2.9E+00
2382.46	8	10	5.0E+00
2393.58	6	8	4.3E+00
2404.18	4	6	2.5E+00
2516.14	10	10	3.7E+00
2521.55	8	8	3.5E+00
2548.21	6	4	2.0E+00
2554.22	8	6	1.2E+00
2593.05	6	6	2.8E+00
2595.10	8	8	2.8E+00
V IV			
677.345	9	9	6.7E+00
680.632	9	7	1.2E+01
681.145	7	5	1.1E+01
682.455	7	7	6.5E+00
682.923	5	5	6.9E+00
684.450	7	5	7.7E+00
691.530	5	3	1.1E+01
723.537	3	1	1.5E+01
724.068	5	5	1.1E+01
724.809	5	3	5.6E+00
737.854	9	7	2.4E+01
750.110	5	5	1.0E+01
884.146	1	3	4.7E+00
1071.05	5	5	6.1E+00
1110.72	3	3	5.0E+00
1112.20	7	7	6.3E+00
1112.44	5	5	5.0E+00
1127.84	7	5	8.9E+00
1131.26	9	7	9.4E+00
1194.46	7	5	1.0E+01
1226.52	5	5	1.5E+01
1243.72	3	1	9.4E+00
1247.07	5	3	4.7E+00
1272.97	3	1	2.7E+01
1304.17	3	5	1.5E+01
1305.42	5	7	7.0E+00
1308.06	7	9	7.9E+00
1309.50	5	5	8.7E+00
1312.72	7	7	8.6E+00
1317.57	5	7	8.7E+00
1321.92	7	9	9.9E+00
1326.81	3	5	4.0E+00
1329.29	5	5	1.5E+01
1329.97	3	3	4.8E+00
1330.36	1	3	6.0E+00
1331.67	3	1	1.7E+01
1332.46	5	3	7.5E+00
1334.49	9	9	8.3E+00
1355.13	7	9	2.5E+01
1356.53	5	3	4.9E+00
1395.00	5	7	1.4E+01
1400.42	5	7	7.5E+00
1403.62	7	9	8.4E+00
1412.69	3	3	1.1E+01
1414.41	5	7	1.2E+01
1414.84	5	5	4.6E+00
1418.53	7	7	5.2E+00
1419.58	7	9	1.3E+01
1423.72	3	5	7.1E+00
1426.65	9	11	2.2E+01
1429.11	5	5	5.0E+00
1434.84	7	7	5.4E+00
1451.04	3	3	7.0E+00
1454.00	5	3	1.1E+01
1520.14	5	7	7.2E+00
1522.49	3	5	5.5E+00
1601.92	3	3	1.2E+01
1611.88	7	7	5.2E+00
1806.18	5	3	7.3E+00
1809.85	3	1	7.2E+00
1817.68	5	3	4.8E+00
1825.84	7	5	5.3E+00
1861.56	5	7	6.6E+00
1939.07	7	9	5.8E+00
1951.43	5	7	5.0E+00
1963.10	3	5	4.8E+00
1997.72	7	7	4.7E+00
2084.43	5	5	4.0E+00
2120.05	7	9	8.1E+00
2141.20	3	5	7.0E+00
2146.83	7	9	6.6E+00
2149.85	5	7	5.1E+00
2151.09	7	9	4.3E+00
2155.34	11	13	1.2E+01
2446.80	9	11	5.3E+00
2570.72	9	11	7.6E+00
3284.56	7	9	5.3E+00
3496.42	7	9	4.4E+00
3514.25	9	11	4.7E+00
Xenon			
Xe I			
1043.8	1	3	5.9E-01
1047.1	1	3	1.3E+00
1050.1	1	3	8.5E-02
1056.1	1	3	2.45E+00

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
1061.2	1	3	1.9E-01
1068.2	1	3	3.99E+00
1085.4	1	3	4.10E-01
1099.7	1	3	4.34E-01
1110.7	1	3	1.5E+00
1129.3	1	3	4.4E-02
1170.4	1	3	1.6E+00
1192.0	1	3	6.2E+00
1250.2	1	3	1.4E-01
1295.6	1	3	2.46E+00
1469.6	1	3	2.81E+00
4501.0	5	3	6.2E-03
4524.7	5	5	2.1E-03
4624.3	5	5	7.2E-03
4671.2	5	7	1.0E-02
4807.0	3	1	2.4E-02
7119.6	7	9	6.6E-02
7967.3	1	3	3.0E-03
8409.2	5	3	1.0E-02
Xe II			
4180.1	4	4	2.2E+00
4330.5	6	8	1.4E+00
4414.8	6	6	1.0E+00
4603.0	4	4	8.2E-01
4844.3	6	8	1.1E+00
4876.5	6	8	6.3E-01
5260.4	2	4	2.2E-01
5262.0	4	4	8.5E-01
5292.2	6	6	8.9E-01
5372.4	4	2	7.1E-01
5419.2	4	6	6.2E-01
5439.0	4	2	7.4E-01
5472.6	8	8	9.9E-02
5531.1	8	6	8.8E-02
5719.6	4	6	6.1E-02
5976.5	4	4	2.8E-01
6036.2	6	6	7.5E-02
6051.2	8	6	1.7E-01
6097.6	6	4	2.6E-01
6270.8	4	6	1.8E-01
6277.5	4	6	3.6E-02
6805.7	8	6	6.1E-02
6990.9	10	8	2.7E-01
Ytterbium			
Yb I			
2464.5	1	3	9.1E-01
2672.0	1	3	1.18E-01
3464.4	1	3	6.2E-01
3988.0	1	3	1.76E+00
5556.5	1	3	1.14E-02
Yb II			
3289.4	2	4	1.8E+00
3694.2	2	2	1.4E+00
Yttrium			
Y I			
2948.41	4	4	3.5E-01
2974.59	4	6	3.5E-01
2984.25	6	8	4.8E-01
2995.26	6	4	5.1E-02
2996.94	4	6	8.4E-02
3005.26	4	4	4.8E-02
3022.28	6	6	6.6E-02
3045.36	6	6	1.07E-01
3053.95	6	4	1.9E-03
3155.65	4	6	2.7E-03
3172.84	4	4	9.9E-03
3185.96	6	8	1.2E-03
3209.38	6	6	3.0E-03
3227.16	6	4	1.10E-03
3484.05	4	6	1.2E-02
3549.66	6	6	1.0E-03
3552.69	4	4	2.3E-01
4077.36	4	6	1.1E+00
4083.71	4	4	2.5E-01
4102.36	6	8	1.3E+00
4128.30	6	6	1.6E+00
4142.84	4	4	1.6E+00
4167.51	6	6	2.38E-01
4235.93	6	4	3.0E-01
4352.40	4	4	6.7E-03
4379.33	6	4	7.83E-01
4385.47	4	4	6.9E-02
4394.01	8	8	1.9E-02
4409.70	4	6	2.7E-03
4417.43	10	8	3.2E-02
4437.34	6	6	8.64E-02
4443.65	10	8	1.1E-01
4459.01	4	6	1.8E-02
4476.95	8	6	2.8E-01
4491.74	10	10	2.3E-02
4514.01	4	6	3.34E-01
4527.78	8	6	8.33E-01
4534.09	6	8	4.4E-02
4544.31	6	6	4.10E-01
4559.36	2	4	4.0E-01
4581.33	6	4	1.5E-01
4613.00	6	4	1.8E-01
4643.70	4	6	1.8E-01
4653.78	4	6	1.6E-01
4674.85	6	8	1.3E-01
4725.84	4	4	1.5E-01
4762.96	6	4	4.2E-02
4780.16	2	4	8.9E-02
4781.03	8	10	1.0E-01
4799.30	6	8	1.6E-01
4804.31	6	4	2.6E-01
4804.80	4	4	3.84E-01
4821.63	6	6	1.0E-01
4845.67	8	8	6.8E-01
4852.68	6	6	6.2E-01
4856.71	6	6	2.0E-01
4859.84	4	4	7.26E-01
4893.44	6	4	2.2E-01
4900.08	8	6	2.0E-01
4906.11	10	8	1.2E-01
4950.01	8	6	2.0E-02
4963.49	4	4	1.4E-02
4981.97	4	6	4.7E-03
5004.44	6	4	1.2E-02
5205.01	4	4	8.4E-03
5258.47	6	6	2.9E-03
5271.82	8	6	1.1E-02
5380.63	6	4	3.2E-01
5381.24	4	4	9.9E-03
5388.39	6	8	1.1E-02
5390.81	8	6	2.9E-02
5401.88	6	8	6.0E-03
5424.36	6	4	3.47E-01
5466.24	4	4	1.0E-01
5466.47	10	12	6.3E-01
5469.10	4	6	3.6E-03
5513.65	6	6	2.39E-01
5519.88	4	6	1.2E-02
5526.43	6	4	3.9E-03
5527.56	8	10	5.4E-01
5541.63	8	8	5.2E-02
5551.00	4	4	6.9E-02
5573.03	6	4	1.8E-02
5594.12	6	8	5.0E-02
5606.34	10	10	5.84E-02
5619.96	6	4	2.0E-02
5630.14	4	6	4.9E-01
5641.78	2	4	1.9E-02
5675.27	6	6	9.3E-02
5675.64	4	6	4.3E-02
5693.63	4	4	1.1E-01
5714.94	8	6	2.0E-02
5729.25	6	6	2.2E-03
5732.09	6	6	7.5E-02
5740.22	8	6	4.0E-02
5757.59	4	6	7.6E-03
5788.36	4	4	9.4E-03
5844.13	6	4	5.6E-03
5879.93	4	2	8.5E-02
5902.91	6	8	4.0E-02
6087.94	6	4	1.1E-01
6191.72	4	4	4.7E-02
6222.58	4	6	5.9E-03
6402.01	6	4	2.7E-03
6435.02	6	6	4.0E-02
6437.17	10	8	4.8E-02
6538.57	10	10	1.5E-01
6622.48	8	6	4.5E-03
6815.15	2	4	7.18E-02
7009.89	2	4	4.4E-02
7035.15	4	4	6.3E-02
Y II			
3112.03	1	3	1.3E-02
3179.42	3	5	3.8E-02
3195.62	3	3	8.23E-01
3200.27	5	5	4.8E-01
3203.32	3	1	2.77E+00
3216.69	5	3	2.0E+00
3242.28	7	5	2.0E+00
3448.81	5	5	4.1E-02
3467.88	5	3	2.7E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
3496.08	1	3	3.49E-01
3549.01	5	7	3.97E-01
3584.51	3	5	4.02E-01
3600.74	7	7	1.4E+00
3601.91	3	3	1.13E+00
3611.04	5	5	1.04E+00
3628.70	5	3	3.3E-01
3664.62	7	5	3.7E-01
3710.29	7	9	1.5E+00
3747.55	3	3	1.9E-01
3774.34	5	7	1.1E+00
3776.56	5	3	2.42E-01
3788.70	3	5	8.1E-01
3818.34	5	5	9.70E-02
3832.90	7	7	3.0E-01
3878.29	7	5	2.9E-02
3930.66	5	5	2.1E-02
3950.36	3	5	2.80E-01
3951.59	5	3	1.5E-02
3982.60	5	5	2.7E-01
4124.91	5	7	1.8E-02
4177.54	5	5	5.27E-01
4199.27	3	5	5.36E-03
4204.69	1	3	2.20E-02
4235.73	5	5	2.3E-02
4309.62	7	5	1.29E-01
4358.73	3	3	5.55E-02
4374.95	5	5	9.97E-01
4398.01	5	3	1.16E-01
4422.59	3	1	1.83E-01
4682.33	5	5	1.9E-02
4786.58	7	7	2.1E-02
4823.31	5	5	4.3E-02
4854.87	5	3	3.9E-01
4881.44	5	3	1.5E-03
4883.69	9	7	4.7E-01
4900.11	7	5	4.51E-01
4982.13	7	9	1.5E-02
5087.42	9	9	2.0E-01
5119.11	5	7	1.6E-02
5200.41	5	5	1.3E-01
5205.73	7	7	1.6E-01
5289.82	7	5	6.7E-03
5320.78	9	7	3.9E-03
5473.39	3	5	4.3E-02
5480.73	1	3	7.62E-02
5497.41	5	5	1.2E-01
5509.90	5	5	4.24E-02
5544.61	3	1	1.8E-01
5546.01	5	3	5.8E-02
5728.89	5	5	3.0E-02
6613.74	5	7	1.7E-02
6832.48	5	5	3.3E-03
7264.16	5	3	1.3E-02

λ	Weights		A
Å	g_i	g_k	10^8 s^{-1}
Zinc			
Zn I			
748.29	1	3	6.0E-02
765.60	1	3	7.6E-02
792.05	1	3	5.7E-02
793.85	1	3	1.8E-01
809.92	1	3	2.6E-01
1109.1	1	3	3.05E-01
2138.6	1	3	7.09E+00
3075.9	1	3	3.29E-04
3282.3	1	3	9.0E-01
3302.6	3	5	1.2E+00
3302.9	3	3	6.7E-01
3345.0	5	7	1.7E+00
3345.6	5	5	4.0E-01
3345.9	5	3	4.5E-02
6362.3	3	5	4.74E-01
11054	3	1	2.43E-01
Zn II			
2025.5	2	4	3.3E+00
2064.2	2	4	4.6E+00
2099.9	4	6	5.6E+00
2102.2	4	4	9.3E-01
4911.6	4	6	1.6E+00

ELECTRON AFFINITIES

Thomas M. Miller

Electron affinity is defined as the energy difference between the lowest (ground) state of the neutral and the lowest state of the corresponding negative ion. The accuracy of electron affinity measurements has been greatly improved since the advent of laser photodetachment experiments with negative ions. Electron affinities can be determined with optical precision, though a detailed understanding of atomic and molecular states and splittings is required to specify the photodetachment threshold corresponding to the electron affinity.

Atomic and molecular electron affinities are discussed in two excellent articles reviewing photodetachment studies which appear in *Gas Phase Ion Chemistry,* Vol. 3, Bowers, M. T., Ed., Academic Press, Orlando, 1984: Chapter 21 by Drzaic, P. S., Marks, J., and Brauman, J. I., "Electron Photodetachment from Gas Phase Negative Ions," p. 167, and Chapter 22 by Mead, R. D., Stevens, A. E., and Lineberger, W. C., "Photodetachment in Negative Ion Beams," p. 213. Persons interested in photodetachment details should consult these articles and the critical review**s** of Andersen, T., Haugen, H. K., and Hotop, H., *J. Phys. Chem. Ref. Data*, 28, 1511, 1999, and Hotop, H., and Lineberger, W. C., *J. Phys. Chem. Ref. Data*, 14, 731, 1985. For simplicity in the tables below, any electron affinity which was discussed in the articles by Drzaic et al. or Hotop and Lineberger is referenced to these sources, where original references are given. The development of cluster-ion photodetachment apparatuses has brought an explosion of electron affinity estimates for atomic and molecular clusters. The policy in this tabulation is to list the electron affinities for the atoms, diatoms, and triatoms, if adiabatic electron affinities have been determined, but to refer the reader to original sources for higher-order clusters. Additional data on molecular electron affinities may be found in Lias, S. G., Bartmess, J. E., Liebman, J. F., Holmes, J. L., Levin, R. D., and Mallard, W. G., *Gas Phase Ion and Neutral Thermochemistry*, *J. Phys. Chem. Ref. Data*, 17, (Supplement No. 1), 1988 and on the NIST WebBook at the Internet address http://webbook.nist.gov/.

For the present tabulation the 2002 CODATA value e/hc = 8065.54445 ± 0.00069 cm^{-1} eV^{-1} (http://physics.nist.gov) has been used to convert electron affinities from the units used in spectroscopic work, cm^{-1}, into eV for these tables. The 86 ppb uncertainty in e/hc is insignificant compared to uncertainties in the electron affinity measurements.

Abbreviations used in the tables: calc = calculated value; PT = photodetachment threshold using a lamp as a light source; LPT = laser photodetachment threshold; LPES = laser photoelectron spectroscopy; DA = dissociative attachment; attach = electron attachment/detachment equilibrium**;** e-scat = electron scattering; kinetic = dissociation kinetics; Knud=Knudsen cell; CT = charge transfer; CD = collisional detachment; and ZEKE = zero electron kinetic energy spectroscopy.

TABLE 1. Atomic Electron Affinities

Atomic number	Atom	Electron affinity in eV	Uncertainty in eV	Method	Ref.	
1	H	0.754195	0.000019	LPT	89	
		0.75420812	-	calc	205	
	D	0.754593	0.000074	LPT	89	deuterium
	D	0.75465624	-	calc	205	deuterium
	T	0.75480540	-	calc	205	tritium
2	He	not stable	-	calc	1	
3	Li	0.618049	0.000020	LPT	185	
4	Be	not stable	-	calc	1	
5	B	0.279723	0.000025	LPES	191	
6	C	1.262119	0.000020	LPT	28	
7	N	not stable	-	DA	1	
8	O	1.4611096	0.0000007	LPT	4	
9	F	3.4011895	0.0000025	LPT	226	
10	Ne	not stable	-	calc	1	
11	Na	0.547926	0.000025	LPT	1	
12	Mg	not stable	-	e-scat	1	
13	Al	0.43283	0.00005	LPES	208	
14	Si	1.3895220	0.0000024	LPES	226	
15	P	0.7465	0.0003	LPT	1	
16	S	2.077103	0.000001	LPT	1	
17	Cl	3.612724	0.000027	LPT	52	
18	Ar	not stable	-	calc	1	
19	K	0.50147	0.00010	LPT	1	
20	Ca	0.02455	0.00010	LPT	44	
21	Sc	0.188	0.020	LPES	1	
22	Ti	0.079	0.014	LPES	1	
23	V	0.525	0.012	LPES	1	
24	Cr	0.666	0.012	LPES	1	
25	Mn	not stable	-	calc	1	

Atomic number	Atom	Electron affinity in eV	Uncertainty in eV	Method	Ref.
26	Fe	0.151	0.003	LPES	27
27	Co	0.662	0.003	LPES	27
28	Ni	1.156	0.010	LPES	1
29	Cu	1.235	0.005	LPES	37
30	Zn	not stable	-	e-scat	1
31	Ga	0.43	0.03	LPES	183
32	Ge	1.232712	0.000015	LPES	28
33	As	0.814	0.008	LPES	200
34	Se	2.020670	0.000025	LPT	1
35	Br	3.363588	0.000002	LPT	74
36	Kr	not stable	-	calc	1
37	Rb	0.48592	0.00002	LPT	1
38	Sr	0.048	0.006	LPT	122
39	Y	0.307	0.012	LPES	1
40	Zr	0.426	0.014	LPES	1
41	Nb	0.893	0.025	LPES	1
42	Mo	0.748	0.002	LPES	127
43	Tc	0.55	0.20	calc	1
44	Ru	1.05	0.15	calc	1
45	Rh	1.137	0.008	LPES	1
46	Pd	0.562	0.005	LPES	116
47	Ag	1.302	0.007	LPES	1
48	Cd	not stable	-	e-scat	1
49	In	0.3	0.2	PT	1
50	Sn	1.112067	0.000015	LPES	28
51	Sb	1.046	0.005	LPES	108
52	Te	1.970876	0.000007	LPT	261
53	I	3.059037	0.000010	LPT	92
54	Xe	not stable	-	calc	1
55	Cs	0.471626	0.000025	LPT	1
56	Ba	0.14462	0.00006	LPT	195
57	La	0.47	0.02	LPT	184
58	Ce	0.955	0.026	LPES	269
59	Pr	0.962	0.024	LPES	225
63	Eu	0.864	0.024	LPES	268
69	Tm	1.029	0.022	LPES	264
70	Yb	-0.020	-	calc	196
71	Lu	0.34	0.01	LPT	223
72	Hf	»0	-	calc	1
73	Ta	0.322	0.012	LPES	1
74	W	0.815	0.002	LPES	37
75	Re	0.15	0.15	calc	1
76	Os	1.1	0.2	calc	1
77	Ir	1.5638	0.0005	LPT	141
78	Pt	2.128	0.002	LPT	1
79	Au	2.30863	0.00003	LPT	1
80	Hg	not stable	-	e-scat	1
81	Tl	0.2	0.2	PT	1
82	Pb	0.364	0.008	LPES	1
83	Bi	0.942362	0.000013	LPT	262
84	Po	1.9	0.3	calc	1
85	At	2.8	0.2	calc	1
86	Rn	not stable	-	calc	1
87	Fr	0.46	-	calc	82
88	Ra	0.10	-	calc	273
89	Ac	0.35	-	calc	207
118	Uuo	0.056	0.01	calc	140
121	Ubu	0.57	-	calc	207

TABLE 2. Electron Affinities for Diatomic Molecules

Molecule	Electron affinity in eV	Uncertainty in eV	Method	Ref.
Ag_2	1.023	0.007	LPES	37
AgO	1.654	0.002	LPES	233
Al_2	1.10	0.15	LPES	68
AlO	2.60	0.02	LPES	143
AlP	2.043	0.020	LPES	218
AlS	2.60	0.03	LPES	129
As_2	0.739	0.008	LPES	200
AsH	1.0	0.1	PT	2
AsO	1.286	0.008	LPES	198
Au_2	1.938	0.007	LPES	37
AuPd	1.88	—	LPES	220
BN	3.160	0.005	LPES	189
BO	2.508	0.008	LPES	6
BeH	0.7	0.1	PT	2
Bi_2	1.271	0.008	LPES	119
Br_2	2.55	0.10	CT	2
BrO	2.353	0.006	LPES	88
C_2	3.269	0.006	LPES	87
CH	1.238	0.008	LPES	2
CN	3.862	0.004	LPES	111
CRh	1.46	0.02	LPES	206
CS	0.205	0.021	LPES	2
CaH	0.93	0.05	PT	2
Cl_2	2.38	0.10	CT	2
ClO	2.275	0.006	LPES	88
Co_2	1.110	0.008	LPES	27
CoD	0.680	0.010	LPES	29
CoH	0.671	0.010	LPES	29
Cr_2	0.505	0.005	LPES	114
CrD	0.568	0.010	LPES	29
CrH	0.563	0.010	LPES	29
CrO	1.221	0.006	LPES	5
Cs_2	0.469	0.015	LPES	104
CsCl	0.455	0.010	LPES	30
CsO	0.273	0.012	LPES	133
Cu_2	0.836	0.006	LPES	37
CuO	1.777	0.006	LPES	118
F_2	3.08	0.10	CT	2
FO	2.272	0.006	LPES	88
Fe_2	0.902	0.008	LPES	27
FeD	0.932	0.015	LPES	9
FeH	0.934	0.011	LPES	9
FeO	1.493	0.005	LPES	45
GaAs	1.949	0.020	LPES	218
GaP	1.988	0.020	LPES	218
Ge_2	2.035	0.001	LPES	123
I_2	2.55	0.05	CT	2
IBr	2.55	0.10	CT	2
IO	2.378	0.006	LPES	88
InP	1.845	0.020	LPES	218
K_2	0.497	0.012	LPES	104
KBr	0.642	0.010	LPES	30
KCl	0.582	0.010	LPES	30
KCs	0.471	0.020	LPES	104
KI	0.728	0.010	LPES	30
KRb	0.486	0.020	LPES	104
LiCl	0.593	0.010	LPES	30
LiD	0.337	0.012	LPES	102
LiH	0.342	0.012	LPES	102
MgCl	1.589	0.011	LPES	31
MgH	1.05	0.06	PT	2
MgI	1.899	0.018	LPES	31
MgO	1.630	0.025	LPES	178
MnD	0.866	0.010	LPES	9
MnH	0.869	0.010	LPES	9
MnO	1.375	0.010	LPES	158
MoO	1.290	0.006	LPES	127
NH	0.370	0.004	LPT	32
NO	0.026	0.005	LPES	73
NRh	1.51	0.02	LPES	206
NS	1.194	0.011	LPES	2
Na_2	0.430	0.015	LPES	104
NaBr	0.788	0.010	LPES	30
NaCl	0.727	0.010	LPES	30
NaF	0.520	0.010	LPES	30
NaI	0.865	0.010	LPES	30
NaK	0.465	0.030	LPES	104
NbO	1.29	0.02	LPES	174
Ni_2	0.926	0.010	LPES	112
NiCu	0.889	0.010	LPES	128
NiAg	0.979	0.010	LPES	128
NiD	0.477	0.007	LPES	29
NiH	0.481	0.007	LPES	29
NiO	1.470	0.003	LPES	146
O_2	0.450	0.002	LPES	222
OD	1.825533	0.000037	LPT	142
OH	1.8276534	0.0000037	LPT	142
ORh	1.58	0.02	LPES	206
P_2	0.589	0.025	LPES	42
PH	1.028	0.010	LPES	2
PO	1.092	0.010	LPES	2
Pb_2	1.366	0.010	LPES	117
PbO	0.722	0.006	LPES	105
PbS	1.049	0.010	LPES	228
Pd_2	1.685	0.008	LPES	112
PdCO	0.604	0.010	LPES	160
Pt_2	1.898	0.008	LPES	112
PtN	1.240	0.010	LPES	46
Rb_2	0.498	0.015	LPES	104
RbCl	0.544	0.010	LPES	30
RbCs	0.478	0.020	LPES	104
Re_2	1.571	0.008	LPES	33
S_2	1.670	0.015	LPES	53
SD	2.315	0.002	LPES	10
SF	2.285	0.006	LPES	93
SH	2.314343	0.000004	LPT	47
SO	1.125	0.005	LPES	84
Sb_2	1.282	0.008	LPES	108
ScO	1.35	0.02	LPES	171
Se_2	1.94	0.07	LPES	38
SeH	2.212519	0.000025	LPT	48
SeO	1.456	0.020	LPES	41
Si_2	2.201	0.010	LPES	100
SiF	0.81	0.02	LPES	278
SiH	1.277	0.009	LPES	2
SiN	2.949	0.008	LPES	274
Sn_2	1.962	0.010	LPES	117
SnO	0.598	0.006	LPES	168
SnPb	1.569	0.008	LPES	117
Te_2	1.92	0.07	LPES	38
TeH	2.102	0.015	LPES	39
TeO	1.697	0.022	LPES	40
TiO	1.30	0.03	LPES	172
VO	1.229	0.008	LPES	170
YO	1.35	0.02	LPES	171
ZnF	1.974	0.008	LPES	179
ZnH	<0.95	—	PT	2
ZnO	2.087	0.008	LPES	179
ZrO	1.3	0.3	LPES	173

TABLE 3. Electron Affinities for Triatomic Molecules

Molecule	Electron affinity in eV	Uncertainty in eV	Method	Ref.	
Ag_3	2.32	0.05	LPES	37	
AgCN	1.588	0.010	LPES	163	
Al_3	1.4	0.15	LPES	68	
AlO_2	4.23	0.02	LPES	143	
AlP_2	1.933	0.007	LPES	217	
Al_2P	2.513	0.020	LPES	217	
Al_2S	0.80	0.12	LPES	129	
As_3	1.45	0.03	LPES	200	
AsH_2	1.27	0.03	PT	2	
Au_3	3.7	0.3	LPES	37	
Au_2H	3.55	0.03	LPES	276	
Au_2Pd	3.80	—	LPES	220	
BO_2	4.3	0.2	CT	98	
B_2N	3.098	0.005	LPES	193	
B_3	2.82	0.02	LPES	221	
Bi_3	1.60	0.03	LPES	119	
C_3	1.981	0.020	LPES	11	
CBr_2	1.88	0.07	LPES	235	
CCl_2	1.59	0.07	LPES	235	
CD_2	0.645	0.006	LPES	12	
CDF	0.535	0.005	LPES	95	
CF_2	0.180	0.020	LPES	235	
CH_2	0.652	0.006	LPES	12	
CHBr	1.454	0.005	LPES	95	
CHCl	1.210	0.005	LPES	95	
CHF	0.542	0.005	LPES	95	
CHI	1.42	0.17	LPES	95	
CI_2	2.09	0.07	LPES	235	
C_2Cr	2.30	1.617	0.015	271	
C_2H	2.969	0.006	LPES	87	
C_2Nb	1.380	0.025	LPES	243	
C_2O	2.289	0.018	LPES	180	
COS	-0.04	—	LPES	272	
CS_2	0.58	0.05	LPES	278	
C_2Ti	1.542	0.020	LPES	147	
CoD_2	1.465	0.013	LPES	34	
CoH_2	1.450	0.014	LPES	34	
CrH_2	>2.5	—	LPES	34	
Cr_2D	1.464	0.005	LPES	107	
Cr_2H	1.474	0.005	LPES	107	
CrO_2	2.413	0.008	LPES	144	OCrO
CrO_2	1.5	0.06	LPES	241	$Cr(O_2)$
Cs_3	0.864	0.030	LPES	18	
Cu_3	2.11	0.05	LPES	37	
CuCN	1.466	0.010	LPES	163	
$CuCl_2$	4.35	0.05	LPES	177	
$CuBr_2$	4.35	0.05	LPES	177	
DCO	0.301	0.005	LPES	35	
DNO	0.330	0.015	LPES	14	
DO_2	1.077	0.005	LPES	15	
DS_2	1.912	0.015	LPES	53	
Fe_3	1.43	0.06	LPES	149	
FeC_2	1.9782	0.0006	LPES	254	
FeCO	1.157	0.005	LPES	103	
FeD_2	1.038	0.013	LPES	34	
FeH_2	1.049	0.014	LPES	34	
FeO_2	2.358	0.030	LPES	130	
Fe_2H	0.564	0.019	LPES	254	
Fe_2O	1.60	0.02	LPES	152	
$GaAs_2$	1.894	0.033	LPES	192	
GaP_2	1.666	0.041	LPES	192	
Ga_2As	2.428	0.020	LPES	192	
Ga_2P	2.481	0.015	LPES	192	
Ge_3	2.23	0.01	LPES	123	
GeH_2	1.097	0.015	LPES	28	
HCO	0.313	0.005	LPES	35	
HCl_2	4.896	0.005	LPES	69	
HNO	0.338	0.015	LPES	14	
HO_2	1.078	0.006	LPES	15	
HS_2	1.907	0.015	LPES	53	
I_3	4.226	0.013	LPES	162	
InP_2	1.61	0.05	LPES	137	
In_2P	2.36	0.05	LPES	137	
K_3	0.956	0.050	LPES	18	
MnD_2	0.465	0.014	LPES	34	
MnH_2	0.444	0.016	LPES	34	
MnO_2	2.06	0.03	LPES	158	
N_3	2.70	0.12	PT	2	
N_3	2.68	0.01	LPT	255	
NCN	2.484	0.006	LPES	154	
NCO	3.609	0.005	LPES	111	
NCS	3.537	0.005	LPES	111	
NH_2	0.771	0.005	LPES	58	
N_2O	-0.03	0.10	calc	59	
NO_2	2.273	0.005	LPES	63	
(NO)R	R=Ar,Kr,Xe	—	LPES	90	
Na_3	1.019	0.060	LPES	18	
$NaCS_2$	0.80	0.05	LPES	278	
Na_2CS_2	0.25	0.05	LPES	278	
Nb_3	1.032	0.010	LPES	175	
Ni_3	1.41	0.05	LPES	55	
NiCO	0.804	0.012	LPES	2	
NiD_2	1.926	0.007	LPES	34	
NiH_2	1.934	0.008	LPES	34	
NiO_2	3.05	0.01	LPES	214	ONiO
NiO_2	0.82	0.03	LPES	214	$Ni(O_2)$
O_3	2.1028	0.0025	LPT	2	
O_2Ar	0.52	0.02	LPES	75	
OClO	2.140	0.008	LPES	88	
OIO	2.577	0.008	LPES	88	
PH_2	1.271	0.010	LPES	2	
PO_2	3.42	0.01	LPES	124	
Pt_3	1.87	0.02	LPES	55	
Pd_3	<1.5	0.1	LPES	55	
Rb_3	0.920	0.030	LPES	18	
ReO_2	2.5	0.1	LPES	216	
S_3	2.093	0.025	LPES	16	
SO_2	1.107	0.008	LPES	16	
S_2O	1.877	0.008	LPES	16	
Sb_3	1.85	0.03	LPES	108	
SeO_2	1.823	0.050	LPES	38	
SiF_2	0.10	0.10	LPES	278	
SiH_2	1.124	0.020	LPES	2	
Si_2H	2.31	0.01	LPES	182	
Si_3	2.29	0.02	LPES	110	
Ta_3	1.36	0.03	LPES	169	
TiO_2	1.59	0.03	LPES	172	
V_3	1.107	0.010	LPES	176	
VO_2	2.3	0.2	CT	101	
WO_2	1.958	0.050	LPES	233	

TABLE 4. Electron Affinities for Larger Polyatomic Molecules

Molecule	Electron affinity in eV	Uncertainty in eV	Method	Ref.	
Ag_n	n=1-60	—	LPES	37	
Al_n	n=3-32	—	LPES	68	
Al_5	2.23	0.05	LPES	238	
Al_2C_2	0.64	0.05	LPES	239	acetylide
Al_3C	2.56	0.06	LPES	161	
Al_3C_2	2.19	0.03	LPES	244	
Al_3Ge_2	2.43	0.03	LPES	244	
Al_3Si_2	2.36	0.03	LPES	244	
Al_3O	1.00	0.15	LPES	68	
Al_nO_m	n=1,2	m=1-5	LPES	143	
Al_nO_m	n=3-7	m=2-5	LPES	267	
Al_nP_m	n=1-4	m=1-4	LPES	217	
Al_nS_m	n=1-5	m=1-3	LPES	129	
$Ar(H_2O)_n$	n=2,6,7	—	LPES	77	
Ar_nBr	n=2-9	—	ZEKE	212	
Ar_nI	n=2-19	—	ZEKE	212	
As_4	<0.8	—	LPES	200	
As_5	≈1.7	—	LPES	200	
As_5	≈3.5	—	LPES	253	
Au_n	n=1-233	—	LPES	37	
AuF_6	7.5	estimate	CT	98	
Au_3Pd	2.51	—	LPES	220	
Au_4Pd	2.69	—	LPES	220	
$Au_{12}Nb$	3.70	0.03	LPES	275	
$Au_{12}Ta$	3.77	0.03	LPES	275	
$Au_{12}V$	3.76	0.03	LPES	275	
B_5	2.33	0.02	LPES	245	
BD_3	0.027	0.014	LPES	62	
BH_3	0.038	0.015	LPES	62	
B_3N	2.098	0.035	LPES	193	
Bi_n	n=2-9	—	LPES	213	
Bi_4	1.05	0.010	LPES	119	
Bi_5	2.87	0.02	LPES	253	
$Br(CO_2)$	3.582	0.017	LPES	131	
$Br(H_2O)_n$	n=1-4	—	LPES	250	
C_n	n=2-84	—	LPES	70	
C_nCr	n=2-8	—	LPES	271	
C_nNb	n=2-7	—	LPES	243	
$(CO_2)_n$	n=1,2	—	LPES	75	
$(CS)_n$	n=2	—	LPES	75	
$(CS_2)_n$	n=1,2	—	LPES	75	
CAl_3Ge	2.70	0.06	LPES	224	
CAl_3Si	2.77	0.06	LPES	224	
CCl_4	≤1.14	—	CT	266	
$CCoNO_3$	1.73	0.03	LPES	199	$Co(CO_2)NO$
CDO_2	3.510	0.015	LPES	109	
CF_3	1.82	0.05	LPES	187	
CF_3Br	0.91	0.2	CD	2	
CF_3I	1.57	0.2	CD	2	
CFO_2	4.277	0.030	LPES	131	
$CHCl_3$	≤0.78	—	CT	266	
CHO_2	3.498	0.015	LPES	109	
CH_2O_4	2.1	0.2	PT	2	$CO_3(H_2O)$
CH_2S	0.465	0.023	LPES	53	
CD_3NO_2	0.24	0.08	LPES	211	
CD_3O	1.559	0.004	LPES	194	
CD_3O_2	1.154	0.004	LPES	188	d_3-methyl peroxyl radical
CD_3S	1.856	0.006	LPT	2	
CD_3S_2	1.748	0.022	LPES	53	

Molecule	Electron affinity in eV	Uncertainty in eV	Method	Ref.	
CH_3	0.08	0.03	LPES	2	
CH_3I	0.11	0.02	LPES	277	
CH_3NO_2	0.26	0.08	LPES	211	
CH_3O	1.572	0.004	LPES	194	
CH_3O_2	1.161	0.005	LPES	188	methyl peroxyl radical
CH_3S	1.867	0.004	LPES	166	
CH_3S_2	1.757	0.022	LPES	53	
CH_3Si	0.852	0.010	LPES	97	CH_3-Si
CH_3Si	2.010	0.010	LPES	97	CH_2=SiH
CH_4N	0.432	0.015	LPES	215	
CH_5Si	1.19	0.04	LPT	65	CH_3SiH_2
CO_3	2.69	0.14	LPES	2	
C_2F_2	2.255	0.006	LPES	106	difluorovinylidene
C_2DN	2.009	0.020	LPES	219	DCCN
C_2DN	1.877	0.010	LPES	219	DCNC
C_2DO	2.350	0.020	LPES	13	
C_2HF	1.718	0.006	LPES	106	monofluorovinylidene
C_2HN	2.003	0.014	LPES	219	HCCN
C_2HN	1.883	0.013	LPES	219	HCNC
C_2HO	2.338	0.008	LPES	190	
C_2D_2	0.492	0.006	LPES	83	vinylidene-d_2
C_2HD	0.489	0.006	LPES	83	vinylidene-d_1
C_2HFe	1.4512	0.0025	LPES	254	
C_2HNi	1.063	0.019	LPES	254	
C_2H_2	0.490	0.006	LPES	83	vinylidene
C_2H_2FO	2.22	0.09	PT	2	acetyl fluoride enolate
C_2D_2N	1.538	0.012	LPES	21	cyanomethyl-d_2 radical
C_2D_2N	1.070	0.024	LPES	21	isocyanomethyl-d_2 radical
C_2H_2Fe	1.328	0.019	LPES	254	
C_2H_2N	1.543	0.014	LPES	21	cyanomethyl radical
C_2H_2N	1.059	0.024	LPES	21	isocyanomethyl radical
C_2H_3	0.667	0.024	LPES	90	vinyl
C_2H_3Fe	1.587	0.019	LPES	254	
C_2H_3Ni	1.103	0.019	LPES	254	
C_2D_3O	1.81897	0.00012	LPT	22	acetaldehyde-d_3 enolate
C_2H_3O	1.82476	0.00012	LPT	22	acetaldehyde enolate
C_2D_5O	1.699	0.004	LPES	194	ethoxide-d_3
C_2H_5N	0.56	0.01	PT	2	ethyl nitrine
C_2H_5O	1.712	0.004	LPES	194	ethoxide
$C_2H_5O_2$	1.186	0.004	LPES	188	ethyl peroxyl radical
C_2H_5S	1.953	0.006	LPT	2	ethyl sulfide
C_2H_5S	0.868	0.051	LPES	53	CH_3SCH_2
$C_2H_7O_2$	2.26	0.08	PT	50	MeOHOMe
C_3Fe	1.69	0.08	LPES	132	
C_3H	1.858	0.023	LPES	11	
C_3HFe	1.58	0.06	LPES	132	
C_3H_2	1.794	0.008	LPES	153	
$C_3H_2F_3O$	2.625	0.010	LPT	113	1,1,1-trifluoroacetone enolate
C_3H_3	0.893	0.025	LPES	24	propargyl radical
C_3H_2D	0.88	0.15	LPES	24	propargyl-d_1 radical
C_3D_2H	0.907	0.023	LPES	24	propargyl-d_2 radical
C_3H_3N	1.247	0.012	LPES	21	CH_3CH-CN
C_3D_5	0.464	0.006	LPES	138	allyl-d_5
C_3H_5	0.481	0.008	LPES	138	allyl
C_3H_5	0.397	0.069	kinetic	155	cyclopropyl
C_3H_4D	0.373	0.019	LPES	25	allyl-d_1
C_3H_5O	1.758	0.019	LPT	113	acetone enolate
C_3H_5O	1.621	0.006	LPT	113	propionaldehyde enolate
$C_3H_5O_2$	1.80	0.06	PT	2	methyl acetate enolate
C_3H_7O	1.789	0.033	LPES	23	propyl oxide

Molecule	Electron affinity in eV	Uncertainty in eV	Method	Ref.	
C_3H_7O	1.847	0.004	LPES	194	isopropyl oxide
C_3H_7S	2.00	0.02	PT	2	propyl sulfide
C_3H_7S	2.02	0.02	PT	2	isopropyl sulfide
C_3O	1.34	0.15	LPES	11	
C_3O_2	0.85	0.15	LPES	11	
C_3Ti	1.561	0.015	LPES	147	
$C_4F_4Cl_2$	0.87	0.08	attach	258	1,2-dichlorotetrafluoro-cyclobutene
$C_4F_4O_3$	0.5	0.2	CD	2	tetrafluorosuccinic anhydride
C_4F_8	0.63	0.05	attach	256	octafluorocyclobutane
C_4Fe	<2.2	0.2	LPES	132	
C_4HFe	1.67	0.06	LPES	132	
C_4H_2Fe	1.633	0.019	LPES	254	
$C_4H_2O_3$	1.44	0.10	CT	61	maleic anhydride
C_4H_3Fe	1.182	0.019	LPES	254	
C_4H_3Ni	0.824	0.019	LPES	254	
C_4D_4	0.909	0.015	LPES	125	vinylvinylidene-d_4
C_4H_4	0.914	0.015	LPES	125	vinylvinylidene
C_4H_4N	2.145	0.010	LPES	265	pyrrolyl
C_4H_5O	1.801	0.008	LPT	113	cyclobutanone enolate
C_4H_6	0.431	0.006	LPES	135	trimethylenemethane
$C_4H_6O_2$	0.69	0.10	CT	61	2,3-butanedione
C_4H_6D	0.493	0.008	LPES	138	2-methylallyl-d_7
C_4H_7	0.505	0.006	LPES	138	2-methylallyl
C_4H_7O	1.67	0.05	PT	2	butyraldehyde enolate
C_4H_5DO	1.67	0.05	PT	2	2-butanone-3-d_1 enolate
$C_4H_5D_2O$	1.75	0.06	PT	2	2-butanone-3,3-d_2 enolate
C_4H_9O	1.909	0.004	LPES	194	*t*-butoxyl
C_4H_9S	2.03	0.02	PT	2	*n*-butyl sulfide
C_4H_9S	2.07	0.02	PT	2	*t*-butyl sulfide
C_4O	2.05	0.15	LPES	11	
C_4O_2	2.0	0.2	LPES	11	
C_4Ti	1.494	0.020	LPES	147	
C_5	2.853	0.001	LPT	99	
C_5F_5N	0.70	0.05	attach	259	pentafluoropyridine
$C_5F_6O_3$	1.5	0.2	CD	2	hexafluoroglutaric anhydride
C_5D_5	1.790	0.008	LPES	11	cyclopentadienyl-d_5
C_5H_5	1.804	0.007	LPES	11	cyclopentadienyl
C_5H_7	0.91	0.03	PT	2	pentadienyl
C_5H_7O	1.598	0.007	LPT	113	cyclopentanone enolate
C_5H_9O	1.69	0.05	PT	2	3-penanone enolate
$C_5H_{11}O$	1.93	0.05	LPT	2	neopentoxyl
$C_5H_{11}S$	2.09	0.02	PT	2	pentyl sulfide
C_5O_2	1.2	0.2	LPES	11	
C_5Ti	1.748	0.050	LPES	147	
C_6	4.180	0.001	LPT	8	
$C_6Br_4O_2$	2.44	0.20	CT	2	tetrabromo-BQ
$C_6Cl_4O_2$	2.78	0.10	CT	61	tetrachloro-BQ
$C_6F_4O_2$	2.70	0.10	CT	61	tetrafluoro-BQ
C_6F_5Br	1.15	0.11	CT	67	pentafluorobromobenzene
C_6F_5Cl	0.75	0.05	attach	260	pentafluorochlorobenzene
C_6F_5I	1.41	0.11	CT	67	pentafluoroiodobenzene
$C_6F_5NO_2$	1.52	0.11	CT	67	pentafluoro-NB
C_6F_6	0.53	0.05	attach	257	hexafluorobenzene
C_6F_{10}	>1.4	0.3	CT	2	perfluorocyclohexane
$C_6H_2Cl_2O_2$	2.48	0.10	CT	61	2,6-dichloro-BQ
$C_6H_3F_2NO_2$	1.17	0.10	CT	61	2,4-difluoro-NB
C_6D_4	0.551	0.010	LPES	36	*o*-benzyne-d_4
C_6H_4	0.560	0.010	LPES	36	*o*-benzyne
$C_6H_4BrNO_2$	1.16	0.10	CT	61	*o*-bromo-NB
$C_6H_4BrNO_2$	1.32	0.10	CT	61	*m*-bromo-NB

Molecule	Electron affinity in eV	Uncertainty in eV	Method	Ref.	
$C_6H_4BrNO_2$	1.29	0.10	CT	61	*p*-bromo-NB
$C_6H_4ClNO_2$	1.14	0.10	CT	61	*o*-chloro-NB
$C_6H_4ClNO_2$	1.28	0.10	CT	61	*m*-chloro-NB
$C_6H_4ClNO_2$	1.26	0.10	CT	61	*p*-chloro-NB
C_6H_4ClO	≤2.58	0.08	PT	2	*o*-chlorophenoxide
$C_6H_4FNO_2$	1.07	0.10	CT	61	*o*-fluoro-NB
$C_6H_4FNO_2$	1.23	0.10	CT	61	*m*-fluoro-NB
$C_6H_4FNO_2$	1.12	0.10	CT	61	*p*-fluoro-NB
$C_6H_4N_2O_4$	1.65	0.10	CT	61	*o*-diNB
$C_6H_4N_2O_4$	1.65	0.10	CT	61	*m*-diNB
$C_6H_4N_2O_4$	2.00	0.10	CT	61	*p*-diNB
$C_6H_4O_2$	1.91	0.10	CT	61	1,4-benzoquinone (BQ)
C_6D_5	1.092	0.020	LPES	26	phenyl-d_5
C_6D_5N	1.44	0.02	LPES	96	phenylnitrene-d_5
C_6H_5	1.096	0.006	LPES	26	phenyl
$C_6H_2O_2$	1.859	0.005	LPES	232	dehydrobenzoquinone
$C_6H_3O_2$	<2.18	-	LPES	232	benzoquinonide
C_6H_5N	1.429	0.011	LPT	115	phenylnitrene
$C_6H_5NO_2$	1.00	0.01	LPES	164	nitrobenzene (NB)
C_6H_5O	2.253	0.006	LPES	26	phenoxyl
C_6H_5S	<2.47	0.06	PT	2	thiophenoxide
C_6H_5NH	1.70	0.03	PT	2	anilide
C_6H_7	<1.67	0.04	PT	2	methylchylopentadienyl
C_6H_8	0.855	0.010	LPES	203	$(CH_2)_2C\text{-}C(CH_2)_2$
C_6H_8Si	1.435	0.004	LPT	65	$C_6H_5SiH_3$
C_6H_9	0.654	0.010	LPES	203	$CH_2{=}C(CH_3)\text{-}C(CH_2)_2$
C_6H_9O	1.526	0.010	LPT	113	cyclohexanone enolate
C_6H_{10}	0.645	0.015	LPES	126	*t*-butyl vinylidene
$C_6H_{11}O$	1.755	+0.05/-0.005	LPT	113	pinacolone enolate
$C_6H_{11}O$	1.82	0.06	PT	2	3,3-dimethylbutananl enolate
C_6N_4	2.3	0.3	PT	2	TCNE
C_7F_5N	1.11	0.11	CT	67	pentafluorobenzonitrile
C_7F_8	0.86	0.11	CT	67	octafluorotoluene
C_7F_{14}	1.08	0.10	CT	61	perfluoromethylcyclohexane
C_7HF_5O	1.10	0.11	CT	67	pentafluorobenzaldehyde
$C_7H_3N_3O_4$	2.16	0.10	CT	61	3,5-(NO2)2-benzonitrile
$C_7H_4F_3NO_2$	1.41	0.10	CT	61	*m*-trifluoromethyl-NB
$C_7H_4N_2O_2$	1.61	0.10	CT	61	*o*-cyano-NB
$C_7H_4N_2O_2$	1.56	0.10	CT	61	*m*-cyno-NB
$C_7H_4N_2O_2$	1.72	0.10	CT	61	*p*-cyano-NB
C_7H_6Br	1.308	0.008	LPES	167	*o*-bromobenzyl
C_7H_6Br	1.307	0.008	LPES	167	*m*-bromobenzyl
C_7H_6Br	1.229	0.008	LPES	167	*p*-bromobenzyl
C_7H_6Cl	1.257	0.008	LPES	167	*o*-chlorobenzyl
C_7H_6Cl	1.272	0.008	LPES	167	*m*-chlorobenzyl
C_7H_6Cl	1.174	0.008	LPES	167	*p*-chlorobenzyl
C_7H_6F	1.091	0.008	LPES	167	*o*-fluorobenzyl
C_7H_6F	1.173	0.008	LPES	167	*m*-fluorobenzyl
C_7H_6F	0.937	0.008	LPES	167	*p*-fluorobenzyl
C_7H_6FO	2.218	0.010	LPT	2	*m*-fluoroacetophenone enolate
C_7H_6FO	2.176	0.010	LPT	2	*p*-fluoroacetophenone enolate
$C_7H_6FeO_3$	0.990	0.10	CT	120	η_4-1,3-butadiene-$Fe(CO)_3$
$C_7H_6N_2O_4$	1.77	0.05	PT	60	3,4-dintrotoluene
$C_7H_6N_2O_4$	1.77	0.05	PT	60	2,3-dinitrotoluene
$C_7H_6N_2O_4$	1.60	0.05	PT	60	2,4-dinitrotoluene
$C_7H_6N_2O_4$	1.55	0.05	PT	60	2,6-dinitrotoluene
$C_7H_6O_2$	1.85	0.10	CT	61	*o*-CH_3-BQ
C_7H_7	0.912	0.006	LPES	26	benzyl
C_7H_7	0.868	0.006	LPES	136	1-quadricyclanide
C_7H_7	0.962	0.006	LPES	136	2-quadricyclanide

Molecule	Electron affinity in eV	Uncertainty in eV	Method	Ref.	
C_7H_7	1.286	0.006	LPES	136	norbornadienide
C_7H_7	0.39	0.04	LPES	136	cycloheptatrienide
C_7H_7	3.046	0.006	LPES	136	1-(1,6-heptadiynide)
C_7H_7	>1.140	0.006	LPES	136	3-(1,6-heptadiynide)
$C_7H_7NO_2$	0.92	0.10	CT	61	*o*-methyl-NB
$C_7H_7NO_2$	0.99	0.10	CT	61	*m*-methyl-NB
$C_7H_7NO_2$	0.95	0.10	CT	61	*p*-methyl-NB
$C_7H_7NO_3$	1.04	0.10	CT	61	*m*-OCH_3-NB
$C_7H_7NO_3$	0.91	0.10	CT	61	*p*-OCH_3-NB
C_7H_7O	<2.36	0.06	PT	2	*o*-methyl phenoxide
C_7H_7O	2.14	0.02	PT	50	benzyloxide
C_7H_8FO	<3.05	0.06	PT	50	$PhCH_2OHF$
C_7H_9	1.27	0.03	PT	2	heptatrienyl
C_7H_9O	1.61	0.05	PT	2	2-norbornanone enolate
C_7H_9Si	1.33	0.04	LPT	65	$C_6H_5(CH_3)SiH$
$C_7H_{11}O$	1.598	0.007	LPT	113	cycloheptanone enolate
$C_7H_{11}O$	1.49	0.04	PT	2	2,5-dimethyl-cyclopentanone enolate
$C_7H_{13}O$	1.72	0.06	PT	2	4-heptanone enolate
$C_7H_{13}O$	1.46	0.04	PT	2	diisopropyl ketone enolate
$C_8F_{14}N_2$	1.89	0.10	CT	51	1,4-$(CN)_2C_6F_4$
$C_8H_3F_5O$	0.88	0.11	CT	67	pentafluoroacetophenone
$C_8H_3F_6NO_2$	1.79	0.10	CT	61	3,5-$(CF_3)_2$-NB
$C_8H_4F_3N$	0.70	0.05	attach	263	*o*-trifluoromethylbenzonitrile
$C_8H_4F_3N$	0.67	0.05	attach	263	*m*-trifluoromethylbenzonitrile
$C_8H_4F_3N$	0.83	0.05	attach	263	*p*-trifluoromethylbenzonitrile
$C_8H_4O_3$	1.21	0.10	CT	61	phthalic anhydride
C_8H_6	1.044	0.008	LPES	148	
C_8H_7	1.091	0.008	LPES	134	
C_8H_7O	2.057	0.010	PT	2	acetophenone enolate
C_8H_7O	2.10	0.08	LPT	2	phenylacetaldehyde enolate
C_8H_8	0.55	0.02	CT	134	cyclooctatetraene
C_8H_8	0.919	0.008	LPES	139	*m*-xylylene
$C_8H_9NO_2$	1.21	0.05	PT	60	3,5-dimethyl-NB
$C_8H_9NO_2$	2.61	0.05	PT	60	2,6-dimethyl-NB
$C_8H_9NO_2$	0.86	0.10	CT	61	2,3-dimethyl-NB
$C_8H_{13}O$	1.63	0.06	PT	2	cyclooctanone enolate
$C_9H_8FeO_3$	0.76	0.10	CT	120	η_4-1,3-cyclohexadiene-$Fe(CO)_3$
C_9H_9O	2.030	0.010	LPT	2	*m*-methylacetophenone enolate
C_9H_9SiN	1.43	0.10	PT	2	trimethylsilylnitrene
$C_9H_{11}NO_2$	0.70	0.10	CT	61	2,4,6-trimethyl-NB
$C_9H_{15}O$	1.69	0.06	PT	2	cyclononanone enolate
$C_{10}H_4C_{l2}O_2$	2.19	0.10	CT	61	2,3-dichloro-1,4-naphthoquinone
$C_{10}H_6N_2O_4$	1.78	0.10	CT	61	1,3-dinitronaphthalene
$C_{10}H_6N_2O_4$	1.77	0.10	CT	61	1,5-dinitronaphthalene
$C_{10}H_6O_2$	1.81	0.10	CT	61	1,4-naphthoquinone
$C_{10}H_7$	1.403	0.015	LPES	197	1-naphthyl radical
$C_{10}H_7NO_2$	1.23	0.10	CT	61	1-nitronaphthalene
$C_{10}H_7NO_2$	1.18	0.10	CT	61	2-nitronaphthalene
$C_{10}H_8$	0.790	0.008	LPES	230	azulene
$C_{10}H_8CrO_3$	0.93	0.10	CT	120	η_4-1,3,5-cycloheptatriene $Cr(CO)_3$
$C_{10}H_8FeO_3$	0.98	0.10	CT	120	η_4-1,3,5-cycloheptatriene-$Fe(CO)_3$
$C_{10}H_{17}O$	1.83	0.06	PT	2	cyclodecanone enolate
$C_{11}H_8FeO_3$	1.29	0.10	CT	120	η_4-1,3-butadiene-$Fe(CO)_3$
$C_{12}F_{10}$	0.82	0.11	CT	67	decafluorobiphenyl
$C_{12}H_4N_4$	2.8	0.3	CD	2	TCNQ
$C_{12}H_9$	1.07	0.10	PT	2	perinaphthenyl
$C_{12}H_{15}O$	2.032	0.010	LPT	2	*t*-butylacetophenone enolate
$C_{12}H_{21}O$	1.90	0.07	PT	2	cyclododecanone enolate
$C_{13}F_{10}O$	1.52	0.11	CT	67	decafluorobenzophenone

Molecule	Electron affinity in eV	Uncertainty in eV	Method	Ref.	
$C_{13}H_9FO$	0.64	0.10	CT	61	4-fluorobenzophenone
$C_{13}H_{10}O$	0.62	0.10	CT	61	benzophenone
$C_{14}H_9NO_2$	1.43	0.10	CT	61	9-nitroanthracene
$C_{14}H_{10}$	0.530	0.008	LPES	230	anthracene
$(C_{14}H_{10})_n$	n=1-16	—	LPES	231	anthracene clusters
$C_{16}H_{10}$	0.406	0.010	LPES	270	pyrene
$C_{18}H_{12}$	1.04	0.10	CT	66	tetracene
$C_{20}H_{12}$	0.79	0.10	CT	66	benz[a]pyrene
$C_{20}H_{12}$	0.973	0.005	LPES	236	perylene
$C_{22}H_{14}$	1.35	0.10	CT	66	pentacene
$C_{44}Cl_{28}FeN_4$	2.59	0.11	CT	186	$FeTPPCl_{28}$
$C_{44}Cl_8F_{20}FeN_4$	3.21	0.03	CT	186	$FeTPP\beta Cl_8$
$C_{44}Cl_9F_{20}FeN_4$	3.35	0.03	CT	186	$FeTPPF_{20}\beta Cl_8Cl$
$C_{44}H_8F_{20}FeN_4$	2.15	0.15	CT	186	$FeTPPF_{20}$
$C_{44}H_8ClF_{20}FeN_4$	3.14	0.03	CT	186	$FeTPPF_{20}Cl$
$C_{44}H_8Cl_{21}FeN_4$	2.93	0.23	CT	186	$FeTPPoCl_{20}Cl$
$C_{44}H_{12}Cl_{17}FeN_4$	3.14	0.03	CT	186	$FeTPPoCl_8\beta Cl_8Cl$
$C_{44}H_{20}Cl_8FeN_4$	1.86	0.03	CT	186	$FeTPPoCl_8$
$C_{44}H_{20}Cl_9FeN_4$	2.10	0.19	CT	186	$FeTPPoCl_8Cl$
$C_{44}H_{28}FeN_4$	1.87	0.03	CT	186	iron tetraphenylporphyrin (FeTPP)
$C_{44}H_{28}NiN_4$	1.51	0.01	CT	186	nickel tetraphenylporphyrin (NiTPP)
$C_{44}H_{28}ClFeN_4$	2.15	0.15	CT	186	FeTPPCl
$C_{44}H_{30}N_4$	1.69	0.01	CT	186	H_2 tetraphenylporphyrin
$C_{45}H_{29}NiN_4O$	1.74	0.01	CT	186	NiTPPCHO
$C_{52}H_{39}FeN_7O$	1.97	0.03	CT	186	FeTPP-val
C_{60}	2.65	0.05	LPT	201	
$C_{60}F_2$	2.74	0.07	Knud	202	
$C_{64}H_{64}FeN_8O_4$	2.07	0.03	CT	186	FeTPP-piv
$C_{70}F_2$	2.80	0.07	Knud	202	
$(benzene)_n$	n=53-124	—	LPES	248	
$(toluene)_n$	n=33-139	—	LPES	248	
CeF_4	3.8	0.4	CT	98	
$Cl(CO_2)$	3.907	0.010	LPES	131	
$Cl(H_2O)$	n=1-4	—	LPES	250	
Co_n	n=1-108	—	LPES	251	
$CoBr_3$	4.6	0.1	LPES	249	
$CoCl_3$	4.7	0.1	LPES	249	
CoF_4	6.4	0.3	CT	98	
$Cr(CO)_3$	1.349	0.006	LPES	94	
CrO_3	3.66	0.02	LPES	241	
CrO_4	4.98	0.09	LPES	241	
CrO_5	4.4	0.1	LPES	241	
CsO_4	2.5	0.2	LPES	252	
Cu_n	n=1-411	—	LPES	37	
$CuBr_2$	4.35	0.05	LPES	237	
$Cu_n(CN)_m$	n=1-6	m=1-6	LPES	159	
$CuCl_2$	4.35	0.05	LPES	237	
$F(H_2O)_n$	n=1-4	—	LPES	242	
$F(H_2O)_n$	n=1-4	—	LPES	250	
Fe_n	n=3-34	—	LPES	149	
$Fe(CO)_2$	1.22	0.02	LPES	2	
$Fe(CO)_3$	1.8	0.2	LPES	2	
$Fe(CO)_4$	2.4	0.3	LPES	2	
$FeBr_3$	4.26	0.06	LPES	249	
$FeBr_4$	5.50	0.08	LPES	249	
$FeCl_3$	4.22	0.06	LPES	249	
$FeCl_4$	6.00	0.08	LPES	249	
FeF_3	3.6	0.1	CT	98	
FeF_4	6.0	estimate	CT	98	
Fe_2H_2	0.942	0.019	LPES	254	

Molecule	Electron affinity in eV	Uncertainty in eV	Method	Ref.	
Fe_nO_m	n=1-4	m=1-6	LPES	152	
Ga_2As_3	2.783	0.024	LPES	192	
Ga_xAs_y	n=2-50	$n=x+y$	LPES	229	
Ga_2P_3	2.991	0.026	LPES	192	
Ge_n	n=3-15	—	LPES	71	
Ge_xAs_y	n=5-30	$n=x+y$	LPES	72	
GeH_3	<1.74	0.04	PT	2	
$H(NH_3)_n$	n=1,2	—	LPES	76	
HNO_3	0.57	0.15	CD	2	
$(H_2O)_n$	n=2-19	—	LPES	77	
$I(CO_2)$	3.225	0.001	LPES	131	
$I(H_2O)_n$	n=1-4	—	LPES	250	
In_xP_y	n=2-8	$n=x+y$	LPES	137	
IrF_4	4.7	0.3	CT	98	
IrF_6	6.5	0.4	CT	98	
K_n	n=2-7	—	LPES	18	
KO_4	2.8	0.2	LPES	252	
LiO_4	3.3	0.2	LPES	252	
$MnBr_3$	5.03	0.06	LPES	249	
$MnCl_3$	5.07	0.06	LPES	249	
MnF_4	5.5	0.2	CT	98	
MnO_3	3.335	0.010	LPES	158	
$Mo(CO)_3$	1.337	0.006	LPES	94	
MoF_5	3.5	0.2	CT	98	
MoF_6	3.8	0.2	CT	98	
MoO_3	2.9	0.2	CT	98	
N_2CD	2.622	0.005	LPES	154	NCND
N_2CH	2.622	0.005	LPES	154	NCNH
$(NH_3)_n$	n=41-1100	—	LPES	77	
$NH_2(NH_3)_n$	n=1,2	—	LPES	78	
$NO(H_2O)_n$	n=1,2	—	LPES	75	
NO_3	3.937	0.014	LPES	85	
$NO_3(H_2O)_n$	n=0-6	—	LPES	240	
$NO(N_2O)_n$	n=1,2	—	LPES	79	
$(NO)_2$	>2.1	—	LPES	75	
$(N_2O)_n$	n=1,2	—	LPES	81	
Na_n	n=2-5	—	LPES	18	
$(NaF)_n$	n=1-7,12	—	LPES	64	
$Na(NaF)_n$	n=5,7-12	—	LPES	64	
NaO_4	3.1	0.2	LPES	252	
NaO_5	3.2	0.2	LPES	252	
$NaSO_3$	2.3	0.2	LPES	252	
Nb_n	n=6-17	—	LPES	181	
Nb_8	1.513	0.008	LPES	157	
Nb_3O	1.393	0.006	LPES	169	
Ni_n	n=1-100	—	LPES	247	
$NiBr_3$	4.94	0.08	LPES	249	
$NiCl_3$	5.20	0.08	LPES	249	
$Ni(CO)_2$	0.643	0.014	LPES	2	
$Ni(CO)_3$	1.077	0.013	LPES	2	
$OH(H_2O)$	<2.95	0.15	PT	2	
$OH(NH_3)$	2.35	0.07	LPES	234	
$OH(N_2O)$	2.14	0.02	LPES	209	
$OH(N_2O)_n$	n=1-5	—	LPES	209	
OsF_4	3.9	0.3	CT	98	
OsF_6	6.0	0.3	CT	98	
P_5	3.88	0.03	LPES	253	
PBr_3	1.59	0.15	CD	2	
PBr_2Cl	1.63	0.20	CD	2	
PCl_2Br	1.52	0.20	CD	2	

Molecule	Electron affinity in eV	Uncertainty in eV	Method	Ref.
PCl_3	0.82	0.10	CD	2
PF_5	0.75	0.15	CT	121
PO_3	4.95	0.06	LPES	156
$POCl_2$	3.83	0.25	CD	2
$POCl_3$	1.41	0.20	CD	2
PtF_4	5.5	0.3	CT	98
PtF_6	7.0	0.4	CT	98
ReF_6	4.7	estimate	CT	98
ReO_3	3.6	0.1	LPES	216
RhF_4	5.4	0.3	CT	98
RuF_4	4.8	0.3	CT	98
RuF_5	5.2	0.4	CT	98
RuF_6	7.5	0.3	CT	98
SF_4	1.5	0.2	CT	91
SF_5	4.23	0.12	e-scat	204
SF_6	1.05	0.10	CT	56
SO_3	1.97	0.10	LPES	165
$(SO_2)_2$	0.6	0.2	LPES	80
Sb_n	n=2-9	—	LPES	213
Sb_5	3.46	0.03	LPES	253
$ScBr_4$	6.13	0.08	LPES	249
$ScCl_4$	6.89	0.08	LPES	249
SeF_6	2.9	0.2	CD	2
Si_4	2.13	0.01	LPES	110
Si_5	2.59	0.02	LPES	110
Si_7	1.85	0.02	LPES	110
Si_n	n=3-20	—	LPES	71
SiD_3	1.386	0.022	LPES	43
SiF_3	2.41	0.22	LPES	17
SiF_4	≤0	—	LPES	17
SiF_5	≥4.66	—	LPES	17
SiH_3	1.406	0.014	LPES	43
Si_3H	2.53	0.01	LPES	182
Si_4H	2.68	0.01	LPES	182
Si_nNa_m	n=4-11	m=1-3	LPES	210
Ta_3O	1.583	0.010	LPES	169
TeF_6	3.34	0.17	CD	2
Ti_n	n=1-130	—	LPES	151
TiO_3	4.2	—	LPES	172
UF_5	3.7	0.2	CT	98
UF_6	5.1	0.2	CT	98
UO_3	<2.1	—	CT	98
V_n	n=3-65	—	LPES	150
VF_4	3.5	0.2	CT	98
V_2O_n	n=3-7	—	LPES	246
V_3O	1.218	0.008	LPES	169
V_4O_{10}	4.2	0.6	CT	101
$W(CO)_3$	1.859	0.006	LPES	94
WF_5	1.25	0.3	CD	18
WF_6	>3.5	-	CT	19
WO_3	3.33	+0.04/-0.15	LPT	86
WO_3	3.9	0.2	CT	98

References

1. Hotop, H., and Lineberger, W. C., *J. Phys. Chem. Ref. Data*, 14, 731, 1985.
2. Drzaic, P. S., Marks, J., and Brauman, J. I., in *Gas Phase Ion Chemistry, Vol. 3*, Bowers, M. T., Ed., Academic Press, Orlando, 1984, p. 167. The reference for C_6H_4ClO should read "Richardson, et al., 1975c".
3. Schulz, P. A., Mead, R. D., Jones, P. L., and Lineberger, W. C., *J. Chem. Phys.*, 77, 1153, 1982.
4. Neumark, D. M., Lykke, K. R., Anderson, T., and Lineberger, W. C., *Phys. Rev. A*, 32, 1890, 1985. EA(O) = 11,784.645 ± 0.008 cm^{-1}.
5. Wenthold, P. G., Gunion, R. F., and Lineberger, W. C., *Chem. Phys. Lett.*, 258, 101, 1996.
6. Wenthold, P. G., Kim, J. B., Jonas, K. L., and Lineberger, W. C., *J. Phys. Chem. A* 101, 4472, 1997.
7. Klein, R., McGinnis, R. P., and Leone, S. R., *Chem. Phys. Lett.*, 100, 475, 1983.
8. Arnold, D. W., Bradforth, S. E., Kitsopoulos, T. N., and Neumark, D. M., *J. Chem. Phys.*, 95, 8753, 1991; linear C_n.
9. Stevens, A. E., Fiegerle, C. S., and Lineberger, W. C., *J. Chem. Phys.*, 78, 5420, 1983.
10. Breyer, F., Frey, P., and Hotop, H., *Z. Phys., A* 300, 7, 1981.
11. Oakes, J. M., and Ellison, G. B., *Tetrahedron*, 42, 6263, 1986.
12. Leopold, D. G., Murray, K. K., Miller, A. E. S., and Lineberger, W. C., *J. Chem. Phys.*, 83, 4849, 1985.
13. Oakes, J. M., Jones, M.E., Bierbaum, V. M., and Ellison, G. B., *J. Phys. Chem.*, 87, 4810, 1983.
14. Ellis, H. B., Jr. and Ellison, G. B., *J. Chem. Phys.*, 78, 6541, 1983.
15. Ramond, T. M., Blanksby, S. J., Kato, S., Bierbaum, V. M., Davico, G. E., Schwartz, R. L., Lineberger, W. C., and Ellison, G. B., *J. Phys. Chem. A* 106, 9641, 2002.
16. Nimlos, M. E., and Ellison, G. B., *J. Chem. Phys.*, 90, 2574, 1986.
17. Kawamata, H., Negishi, Y., Kishi, R., Iwata, S., Nakajima, A., and Kaya, K., J. Chem. Phys. 105, 5369, 1996.
18. McHugh, K. M., Eaton, J. G., Lee, G. H., Sarkas, H. W., Kidder, L. H., Snodgrass, J. T., Manaa, M. R., and Bowen, K. H., *J. Chem. Phys.*, 91, 3792, 1989. See also Ref. 104.
19. Viggiano, A. A., Paulson, J. F., Dale, F., Henchman, M., Adams, N. G., and Smith, D., *J. Phys. Chem.*, 89, 2264, 1985. The upper limit given in this paper (≤3.4 eV) was later found to be incorrect when rapid charge transfer from HCO_2^- to WF_6 was observed (unpublished).
20. Burnett, S. M., Stevens, A. E., Fiegerle, C. S., and Lineberger, W. C., *Chem. Phys. Lett.*, 100, 124, 1983.
21. Moran, S., Ellis, H. B., DeFrees, D. J., McLean, A. D., and Ellison, G. B., *J. Am. Chem. Soc.*, 109, 5996, 1987; Moran, S., Ellis, H. B., DeFrees, D. J., McLean, A. D., Paulson, S. E., and Ellison, G. B., *J. Am. Chem. Soc.*, 109, 6004, 1987; see also Lykke, K. R., Neumark, D. M., Andersen, T., Trapa, V. J., and Lineberger, W. C., *J. Chem. Phys.*, 87, 6842, 1987.
22. Mead, R. D., Lykke, K. R., Lineberger, W. C., Marks, J., and Brauman, J. I., *J. Chem. Phys.*, 81, 4883, 1984; Lykke, K. R., Mead, R. D., and Lineberger, W. C., *Phys. Rev. Lett.*, 52, 2221, 1984. The EAs are 14,717.7 ± 1.0 cm^{-1} for acetaldehyde enolate and 14,671.0 ± 1.0 cm^{-1} for acetaldehyde-d_3 enolate.
23. Ellison, G. B., Engelking, P. C., and Lineberger, W. C., *J. Chem. Phys.*, 86, 4873, 1982.
24. Oakes, J. M., and Ellison, G. B., *J. Am. Chem. Soc.*, 105, 2969, 1983.
25. Ellison, G. B., and Oakes, J. M., *J. Am. Chem. Soc.*, 106, 7734, 1984. EA(allyl) and EA(allyl-d_5) are 0.119 and 0.083 eV too low, respectively, in this work, according to Ref. 138. Therefore, EA(allyl-d_1) is likely too low by a similar amount.
26. Gunion, R. F., Gilles, M. K., Polak, M. L., and Lineberger, W. C., *Int. J. Mass Spectrom. Ion Processes*, 117, 601, 1992; see also Ref. 136.
27. Leopold, D. G., and Lineberger, W. C., *J. Chem. Phys.*, 85, 51, 1986.
28. Scheer, M., Bilodeau, R. C., Brodie, C. A., and Haugen, H. K., *Phys. Rev. A*, 58, 2844, 1998.
29. Miller, A. E. S., Fiegerle, C. S., and Lineberger, W. C., *J. Chem. Phys.*, 87, 1549, 1987.
30. Miller, T. M., Leopold, D. G., Murray, K. K., and Lineberger, W. C., *J. Chem. Phys.*,85, 2368, 1986.
31. Miller, T. M., and Lineberger, W. C., *Chem. Phys. Lett.*, 146, 364, 1988.
32. Neumark, D. M., Lykke, K. R., Andersen, T., and Lineberger, W. C., *J. Chem. Phys.*, 83, 4364, 1985.
33. Leopold, D. G., Miller, T. M., and Lineberger, W. C., *J. Am. Chem. Soc.*, 108, 178, 1986.
34. Miller, A. E. S., Fiegerle, C. S., and Lineberger, W. C., *J. Chem. Phys.*, 84, 4127, 1986.
35. Murray, K. K., Miller, T. M., Leopold, D. G., and Lineberger, W. C., *J. Chem. Phys.*, 84, 2520, 1986.
36. Leopold, D. G., Miller, A. E. S., and Lineberger, W. C., *J. Am. Chem. Soc.*, 108, 1379, 1986.
*37. Li, J., Li, X., Zhai, H. J., and Wang, L.-S., Science 299, 864, 2003; Hakkinen, H., Yoon, B., Landman, U., Li, X., Zhai, H. J., and Wang, L.-S., *J. Phys. Chem. A* 107, 6168, 2003; Taylor, K. J., Pettiette-Hall, C. L., Cheshnovsky, O., and Smalley, R. E., *J. Chem. Phys.* 96, 3319, 1992; Handschuh, H., Cha, C.-Y., Bechthold, P. S., Ganteför, G., and Eberhardt, W., *J. Chem. Phys.*, 102, 6406, 1995; Cha, C.-Y., Ganteför, G., and Eberhardt, W., *J. Chem. Phys.*, 99, 6308, 1993; Ho, J., Ervin, K. M., and Lineberger, W. C., *J. Chem. Phys.*, 93, 6987, 1990; Leopold, D. G., Ho, J., and Lineberger, W. C., *J. Chem. Phys.*, 86, 1715, 1987; Pettiette, C. L., Yang, S. H., Craycraft, M. J., Conceicao, J., Laaksonen, R. T., Cheshnovsky, O., and Smalley, R. E., *J. Chem. Phys.*, 88, 5377, 1988.
38. Snodgrass, J. T., Coe, J. V., McHugh, K. M., Friedhoff, C. B., and Bowen, K. H., *J. Phys. Chem.*, 93, 1249, 1989.
39. Friedhoff, C. B., Snodgrass, J. T., Coe, J. V., McHugh, K. M., and Bowen, K. H., *J. Chem. Phys.*,84, 1051, 1986.
40. Friedhoff, C. B., Coe, J. V., Snodgrass, J. T., McHugh, K. M., and Bowen, K. H., *Chem. Phys. Lett.*, 124, 268, 1986.
41. Coe, J. V., Snodgrass, J. T., Friedhoff, C. B., McHugh, K. M., and Bowen, K. H., *J. Chem. Phys.*, 84, 619, 1986.
42. Snodgrass, J. T., Coe, J. V., Friedhoff, C. B., McHugh, K. M., and Bowen, K. H., *Chem. Phys. Lett.*, 122, 352, 1985.
43. Nimlos, M. R., and Ellison, G. B., *J. Am. Chem. Soc.*, 108, 6522, 1986.
44. Petrunin, V., Andersen, H., Balling, P., and Andersen, T., *Phys. Rev. Lett.*, 76, 744, 1996.
45. Andersen, T., Lykke, K. R., Neumark, D. M., and Lineberger, W. C., *J. Chem. Phys.*, 86, 1858, 1987.
46. Murray, K. K., Lykke, K. R., and Lineberger, W. C., *Phys. Rev. A*, 36, 699, 1987.
47. Mansour, N. B., and Larson, D. J., *Abstracts of the XV Int. Conf. on the Phys. of Electronic and Atomic Collisions*, p. 70, 1987. EA(SH) = 18666.44 ± 0.03 cm^{-1}.
48. Stonemann, R. C., and Larson, D. J., *Phys. Rev. A*, 35, 2928, 1987. EA(SeH) = 17,845.17 ± 0.20 cm^{-1}.
49. Nimlos, M. R., Harding, L. B., and Ellison, G. B., *J. Chem. Phys.*, 87, 5116, 1987.
50. Moylan, C. R., Dodd, J. A., Han, C.-C., and Braumann, J. I., *J. Chem. Phys.*, 86, 5350, 1987.
51. Chowdhury, S., Grimsrud, E. P., Heinis, T., and Kebarle, P., *J. Am. Chem. Soc.*, 108, 3630, 1986.
52. Berzinsh, U., Gustafsson, M., Hanstorp, D., Klinkmueller, A. E., Ljungblad, U., Maartensson-Pendrill, A.-M., *Phys. Rev. A* 51, 231, 1995. EA(Cl) = 29138.59 ± 0.22 cm^{-1}.
53. Moran, S., and Ellison, G. B., *J. Phys. Chem.*, 92, 1794, 1988.
54. Murray, K. K., Leopold, D. G., Miller, T. M., and Lineberger, W. C., *J. Chem. Phys.*, 89, 5442, 1988.
55. Ervin, K. M., Ho, J., and Lineberger, W. C., *J. Chem. Phys.*, 89, 4514, 1988.
56. Grimsrud, E. P., Chowdhury, S., and Kebarle, P., *J. Chem. Phys.*, 85, 4989, 1985.
57. Fischer, C. F., *Phys. Rev. A*, 39, 963, 1989.
58. Wickham-Jones, C. T., Ervin, K. M., Ellision, G. B., and Lineberger, W. C., *J. Chem. Phys.*, 91, 2762, 1989.
59. Kryachko, E. S., Vinckier, C., and Nguyen, M. T., *J. Chem. Phys.*, 114, 7911, 2001.
60. Mock, R. S., and Grimsrud, E. P., *J. Am. Chem. Soc.*, 111, 2861, 1989.
61. Chowdhury, S., Heinis, T., Grimsrud, E. P., and Kebarle, P., *J. Phys. Chem.*, 90, 2747, 1986. The uncertainty and other results are quoted in Ref. 60.
62. Wickham-Jones, C. T., Moran, S., and Ellison, G. B., *J. Chem. Phys.*, 90, 795, 1989.

63. Ervin, K. M., Ho, J., and Lineberger, W. C., *J. Phys. Chem*., 92, 5405, 1988.
64. Miller, T. M., and Lineberger, W. C., Int. *J. Mass Spectrom. Ion Processes*, 102, 239, 1990.
65. Wetzel, D. M., Salomon, K. E., Berger, S., and Brauman, J. I., *J. Am. Chem. Soc*., 111, 3835, 1989.
66. Crocker, L., Wang, T., and Kebarle, P., *J. Am. Chem. Soc*., 115, 7818, 1993.
67. Dillow, G. W., and Kebarle, P., *J. Am. Chem. Soc*., 111, 5592, 1989.
68. Gantefor, G., Gausa, M., Meiwes-Broer, K. H., and Lutz, H. O., Z. Phys. D, 9, 253, 1988; Taylor, K. J., Petteitte, C. L., Craycraft, M. J., Chesnovsky, O., and Smalley, R. E., *Chem. Phys. Lett*., 152, 347, 1988.
69. Metz, R. B., Kitsopoulos, T., Weaver, A., and Neumark, D. M., *J. Chem. Phys*., 88, 1463, 1988.
70. Yang, S., Pettiette, C. L., Conceicao, J., Cheshnovsky, O., and Smalley, R. E., *Chem. Phys. Lett*., 139, 233, 1987; Yang, S., Taylor, K. J., Craycraft, M. J., Conceicao, J., Pettiette, C. L., Cheshnovsky, O., and Smalley, R. E., *Chem. Phys. Lett*., 144, 431, 1988; Arnold, D. W., Bradforth, S. E., Kitsopoulos, T. N., and Neumark, D. M., *J. Chem. Phys*., 95, 5479, 1991.
71. Cheshnovsky, O., Yang, S., Pettiette, C. L., Craycraft, M. J., Liu, Y., and Smalley, R. E., *Chem. Phys. Lett*., 138, 119, 1987.
73. Travers, M. J., Cowles, D. C., and Ellison, G. B., *Chem. Phys. Lett*., 164, 449, 1989.
74. Blondel, C., Cacciani, P., Delsart, C., and Trainham, R., *Phys. Rev. A*, 40, 3698, 1989. EA(Br) = 27,129.170 ± 0.015 cm^{-1} and EA(F) = 27,432.440 ± 0.025 cm^{-1}.
75. Bowen, K. H., and Eaton, J. G., in *The Structure of Small Molecules and Ions*, Naaman, R., and Vager, Z., Eds., Plenum, New York, 1988, pp. 147-169; Arnold, S. T., Eaton, J. G., Patel-Mistra, D., Sarkas, H. W., and Bowen, K. H., in *Ion and Cluster Ion Spectroscopy and Structure*, Maier, J. P., Ed., Elsevier Science, New York, 1989, p. 417.
76. Snodgrass, J. T., Coe, J. V., Friedhoff, C. B., McHugh, K. M., and Bowen, K. H., *Faraday Disc. Chem. Soc*., 88, 1988.
77. Lee, G. H., Arnold, S. T., Eaton, J. G., Sarkas, H. W., Bowen, K. H., Ludewigt, C., and Haberland, H., *Z. Phys. D - Atoms, Mol. and Clusters*, 20, 9, 1991; Coe, J. V., Lee, G. H., Eaton, J. G., Arnold, S. T., Sarkas, H. W., Bowen, K. H., Ludewigt, C., Haberland, H., and Worsnop, D. R., *J. Chem. Phys*., 92, 3980, 1990.
78. Snodgrass, J. T., Coe, J. V., Freidhoff, C. B., McHugh, K. M., and Bowen, K. H., to be published, quoted in Ref. 75.
79. Coe, J. V., Snodgrass, J. T., Friedhoff, C. B., McHugh, K. M., and Bowen, K. H., *J. Chem. Phys*., 87, 4302, 1987.
80. Friedhoff, C. B., Snodgrass, J. T., and Bowen, K. H., to be published, quoted in Ref. 75.
81. Coe, J. V., Snodgrass, J. T., Friedhoff, C. B., McHugh, K. M., and Bowen, K. H., *Chem. Phys. Lett*., 124, 274, 1986.
82. Greene, C. H., *Phys. Rev. A*, 42, 1405, 1990.
83. Ervin, K. M., Ho, J., and Lineberger, W. C., *J. Chem. Phys*., 91, 5974, 1989.
84. Polak, M. L., Fiala, B. L., Ervin, K. M., and Lineberger, W. C., *J. Chem. Phys*., 94, 6924, 1991.
85. Weaver, A., Arnold, D. W., Bradforth, S. E., Neumark, D. M., *J. Chem. Phys*., 94, 1740, 1991.
86. Walter, C. W., Devynck, P., Hertzler, C. F., Bae, Y. K., Smith, G. P., and Peterson, J. R., *Bull. Am. Phys. Soc*., 35, 1163, 1990.
87. Ervin, K. M., and Lineberger, W. C., *J. Phys. Chem*., 95, 1167, 1991.
88. Gilles, M. K., Polak, M. L., and Lineberger, W. C., *J. Chem. Phys*., 96, 8012, 1992.
89. Lykke, K. R., Murray, K. K., and Lineberger, W. C., *Phys. Rev. A*, 43, 6104, 1991. EA(H) = 6082.99 ± 0.15 cm^{-1} and EA(D) = 6086.2 ± 0.6 cm^{-1}.
90. Ervin, K. M., Gronert, S., Barlow, S. E., Gilles, M. K., Harrison, A. G., Bierbaum, V. M., DePuy, C. H., Lineberger, W. C., and Ellison, G. B., *J. Am. Chem. Soc*., 112, 5750, 1990.
91. Viggiano, A. A., Miller, T. M., Miller, A. E. S., Morris, R. A., Van Doren, J. M., and Paulson, J. F., *Int. J. Mass Spectrom. Ion Processes*, 109, 327, 1991.
92. Hanstorp, D., and Gustafsson, M., *J. Phys. B: At. Mol. Opt. Phys*., 25, 1773, 1992. EA(I) = 24,672.7956 ± 0.079 cm^{-1}.
93. Polak, M. L., Gilles, M. K., and Lineberger, W. C., *J. Chem. Phys*., 96, 7191, 1992.
94. Bengali, A. A., Casey, S. M., Cheng, C.-L., Dick, J. P., Fenn, P. T., Villalta, P. W., and Leopold, D. G., *J. Am. Chem. Soc*., 114, 5257, 1992.
95. Gilles, M. K., Ervin, K. M., Ho, J., and Lineberger, W. C., *J. Phys. Chem*., 96, 1130, 1992.
96. Travers, M. J., Cowles, D. C., Clifford, E. P., and Ellison, G. B., *J. Am. Chem. Soc*., 114, 8699, 1992.
97. Bengali, A. A., and Leopold, D. G., *J. Am. Chem. Soc*., 114, 9192, 1992.
98. Rudnyi, E. B., Kaibicheva, E. A., and Sidorov, L. N., *Rapid Comm. in Mass Spectrom*., 6, 356, 1992; Sidorov, L. N., High Temp. Sci., 29, 153, 1990. See also Srivastava, R. D., Uy, O. M., and Farber, M., *Trans. Faraday Soc*., 67, 2941, 1971.
99. Kitsopoulos, T. N., Chick, C. J., Zhao, Y., and Neumark, D. M., *J. Chem. Phys*., 95, 5479, 1991.
100. Arnold, C. C., Kitsopoulos, T. N., and Neumark, D. M., *J. Chem. Phys*., 99, 766, 1993.
101. Rudnyi, E. B., Kaibicheva, E. A., and Sidorov, L. N., *J. Chem. Thermodynamics*, 25, 929, 1993.
102. Sarkas, H. W., Hendricks, J. H., Arnold, S. T., and Bowen, K. H., *J. Chem. Phys*. 100, 1884, 1994.
103. Villalta, P. W., and Leopold, D. G., *J. Chem. Phys*. 98, 7730, 1993.
104. Eaton, J. G., Sarkas, H. W., Arnold, S. T., McHugh, K. M., and Bowen, K. H., *Chem. Phys. Lett*., 193, 141, 1992. See also Ref. 18.
105. Polak, M. L., Gilles, M. K., Gunion, R. F., and Lineberger, W. C., *Chem. Phys. Lett*., 210, 55, 1993.
106. Gilles, M. K., Lineberger, W. C., and Ervin, K. M., *J. Am. Chem. Soc*., 115, 1031, 1993.
107. Casey, S. M., and Leopold, D. G., *Chem. Phys. Lett*., 201, 205, 1993.
108. Polak, M. L., Gerber, G., Ho, J., and Lineberger, W. C., *J. Chem. Phys*., 97, 8990, 1992.
109. Kim, E. H., Bradforth, S. E., Arnold, D.W., Metz, R. B., and Neumark, D. M., *J. Chem. Phys*., 103, 7801, 1995.
110. Xu, C., Taylor, T. R., Burton, G. R., and Neumark, D. M., *J. Chem. Phys*., 108, 1395, 1998.
111. Bradforth, S. E., Kim, E. H., Arnold, D. W., and Neumark, D. M., *J. Chem. Phys*., 98, 800, 1993.
112. Ho, J., Polak, M. L., Ervin, K. M., and Lineberger, W. C., *J. Chem. Phys*., 99, 8542, 1993.
113. Brinkman, E. A., Berger, S., Marks, J., and Brauman, J. I., *J. Chem. Phys*., 99, 7586, 1993.
114. Casey, S. M., and Leopold, D. G., *J. Phys. Chem*., 97, 816, 1993.
115. McDonald, R. N., and Davidson, S. J., *J. Am. Chem. Soc*., 115, 10857, 1993.
116. Ho, J., Ervin, K. M., Polak, M. L., Gilles, M. K., and Lineberger, W. C., *J. Chem. Phys*., 95, 4845, 1991.
117. Ho, J., Polak, M. L., and Lineberger, W. C., *J. Chem. Phys*., 96, 144, 1992.
118. Polak, M. L., Gilles, M. K., Ho, J., and Lineberger, W. C., *J. Phys. Chem*., 95, 3460, 1991.
119. Polak, M. L., Ho, J., Gerber, G., and Lineberger, W. C., *J. Chem. Phys*., 95, 3053, 1991.
120. Sharpe, P., and Kebarle, P., *J. Am. Chem. Soc*., 115, 782, 1993.
121. Miller, T. M., Miller, A. E. S., Viggiano, A. A., Morris, R. A., and Paulson, J. F., *J. Chem. Phys*., 100, 7200, 1994. Accurate calculations have yielded a higher result (0.90 eV); see Lau, J. K.-C. and Li, W.-K., *J. Mol. Struct. (Theochem)* 578, 221, 2002.
122. Berkovits, D., Boaretto, E., Gehlberg, S., Heber, O., and Paul, M., *Phys. Rev. Lett*., 75, 414, 1995.
123. Arnold, C. C., Xu, C., Burton, G. R., and Neumark, D. M., *J. Chem. Phys*., 102, 6982, 1995. Burton, G. R., Xu, C., Arnold, C. C., and Neumark, D. M., *J. Chem. Phys*. 104, 2757 1996.
124. Xu, C., de Beer, E., and Neumark, D. M., *J. Chem. Phys*., 104, 2749, 1996.
125. Gunion, R. F., Koppel, H., Leach, G. W., and Lineberger, W. C., *J. Chem. Phys*., 103, 1250, 1995.
126. Gunion, R. F., and Lineberger, W. C., *J. Phys. Chem*., 100, 4395, 1996.

127. Gunion, R. F., Dixon-Warren, St. J., and Lineberger, W. C., *J. Chem. Phys*., 104, 1765, 1996.
128. Dixon-Warren, St. J., Gunion, R. F., and Lineberger, W. C., *J. Chem. Phys*., 104, 4902, 1996.
129. Nakajima, A., Zhang, N., Kawamata, H., Hayase, T., Nakao, K., and Kaya, K., *Chem. Phys. Lett*., 241, 295, 1995; Nakajima, A., Taguwa, T., Nakao, K., Hoshino, K., Iwata, S., and Kaya, K., *J. Chem. Phys*., 102, 660, 1995.
130. Fan, J., and Wang, L.-S., *J. Chem. Phys*., 102, 8714, 1995.
131. Arnold, D. W., Bradforth, S. E., Kim, E. H., and Neumark, D. M., *J. Chem. Phys*., 102, 3493, 1995; Zhao, Y., Arnold, C. C., and Neumark, D. M., *J. Chem. Soc. Faraday Trans*. 2, 89, 1449, 1992.
132. Fan, J., Lou, L., and Wang, L.-S., *J. Chem. Phys*., 102, 2701, 1995.
133. Sarkas, H. W., Hendricks, J. H., Arnold, S. T., Slager, V. L., and Bowen, K. H., *J. Chem. Phys*., 100, 3358, 1994.
134. Kato, S., Lee, H. S., Gareyev, R., Wenthold, P. G., Lineberger, W. C., DePuy, C. H., and Bierbaum, V. M., *J. Am. Chem. Soc*., 119, 7863, 1997. See also Miller, T. M., Viggiano, A. A., and Miller, A. E. S., *J. Phys. Chem. A* 106, 10200, 2002.
135. Wenthold, P. G., Hu, J., Squires, R. R., and Lineberger, W. C., *J. Am. Chem. Soc*., 118, 475, 1996.
136. Gunion, R. F., Karney, W., Wenthold, P. G., Borden, W. T., and Lineberger, W. C., *J. Am. Chem. Soc*., 118, 5074, 1996. The numbers in the abstract for 1,6-heptadiyne were misprinted. EA(cycloheptatrienide) quoted here derives from the LPES data combined with other thermochemical data in Ref. 136.
137. Xu, C., de Beer, E., Arnold, D. W., Arnold, C. C., and Neumark, D. M., *J. Chem. Phys*., 101, 5406, 1996.
138. Wenthold, P. G., Polak, M. L., and Lineberger, W. C., *J. Phys. Chem*., 100, 6920, 1996.
139. Wenthold, P. G., Kim, J. B., and Lineberger, W. C., *J. Am. Chem. Soc*., 119, 1354, 1997.
140. Eliav, E., Kaldor, U., Ishikawa, Y., and Pyykko, P., *Phys. Rev. Lett.*, 77, 5350, 1996.
141. Davies, B. J., Ingram, C. W., Larson, D. J., and Ljungblad, U., *J. Chem. Phys*. 106, 5783, 1997. EA(Ir) = 12,613 ± 4 cm^{-1}.
142. Smith, J. R., Kim, J. B., and Lineberger, W. C., *Phys. Rev. A*., 55, 2036, 1997. EA(OH) = 14,741.02 ± 0.03 cm^{-1}. Schulz, P. A., Mead, R. D., Jones, P. L., and Lineberger, W. C., *J. Chem. Phys*. 77, 1153, 1982. EA(OD) = 14,723.92 ± 0.30 cm^{-1}. See also Rudmin, J. D., Ratliff, L. P., Yukich, J. N., and Larson, D. J., *J. Phys. B: At. Mol. Opt. Phys*., 29 L881, 1996.
143. Desai, S. R., Wu, H., Rohlfing, C. M., and Wang, L.-S., Int. *J. Chem. Phys*., 106, 1309, 1997.
144. Wenthold, P. G., Jonas, K.-L., and Lineberger, W. C., *J. Chem. Phys*., 106, 9961, 1997.
145. Wu, H., and Wang, L.-S., *J. Chem. Phys*., 107, 16, 1997.
146. Moravec, V. D., and Jarrold, C. C., *J. Chem. Phys*. (in press).
147. Wang, X.-B., Ding, C.-F., and Wang, L.-S., *J. Phys. Chem. A*, 101, 7699, 1997.
148. Wenthold, P. G., and Lineberger, W. C., *J. Am. Chem. Soc*., 19, 7772, 1997.
149. Wang, L.-S., Li, X., and Zhang, H.-F., Chem. Phys., 262, 53, 2000; Wang, L.-S., Cheng, H.-S., and Fan, J., *J. Chem. Phys*., 102, 9480, 1995.
150. Wu, H., Desai, S. R., and Wang, L.-S., *Phys. Rev. Lett.*, 77, 2436, 1996.
151. Liu, S.-R., Zhai, H.-J., Castro, M., and Wang, L.-S., *J. Chem. Phys*. 118, 2108, 2003.
152. Gutsev, G. L., Bauschlicher, C. W., Zhai, H.-J., and Wang, L.-S., *J. Chem. Phys*. 119, 11135, 2003; Wang, L.-S., Wu, H., and Desai, S. R., *Phys. Rev. Lett.*, 76, 4853, 1996.
153. Robinson, M. S., Polak, M. L, Bierbaum, V. M., DePuy, C. H., and Lineberger, W. C., *J. Am. Chem. Soc*., 117, 6766, 1995.
154. Clifford, E. P., Wenthold, P. G., Lineberger, W. C., Petersson, G. A., and Ellison, G. B., *J. Phys. Chem*., 101, 4338, 1997.
155. Seburg, R. A., and Squires, R. R., *Int. J. Mass Spectrom. Ion Processes*, 167/168, 541, 1997.
156. Wang, X.-B., and Wang, L.-S., *Chem. Phys. Lett*., 313, 179, 1999.
157. Marcy, T. P., and Leopold, D. G., *Int. J. Mass Spectrom*., 195/196, 653, 2000.
158. Gutsev, G. L., Rao, B. K., Jena, P., Li, X., and Wang, L.-S., *J. Chem. Phys*., 113, 1473, 2000.
159. Negishi, Y., Yasuike, T., Hayakawa, F., Kizawa, M., Yabushita, S., and Nakajima, A., *J. Chem. Phys*., 113, 1725, 2000.
160. Klopcic, S. A., Moravec, V. D., and Jarrold, C. C., *J. Chem. Phys*., 110, 8986, 1999.
161. Boldyrev, A. I., Simons, J., Li, X., Chen, W., and Wang, L.-S., *J. Chem. Phys*. 110, 8980, 1999.
162. Taylor, T. R., Asmis, K. R., Zanni, M. T., and Neumark, D. M., *J. Chem. Phys*., 110, 7607, 1999.
163. Boldyrev, A., Li, X., and Wang, L.-S., *J. Chem. Phys*., 112, 3627, 2000.
164. Defrançois, C., Périquet, V., Lyapustina, S. A., Lippa, T. P., Robinson, D. W., Bowen, K. H., Nonaka, H., and Compton, R. N., *J. Chem. Phys*., 111, 4569, 1999.
165. Dobrin, S., Boo, B. H., Alconcel, L. S., and Continetti, R. E., *J. Phys. Chem. A* 104, 10695, 2000.
166. Schwartz, R. L., Davico, G. E., and Lineberger, W. C., J. *Electron Spectros. and Related Phenomena*, 108, 163, 2000.
167. Kim, J. B., Wenthold, P. G., and Lineberger, W. C., *J. Phys. Chem*. 103, 10833, 1999.
168. Davico, G. E., Ramond, T. M., and Lineberger, W. C., *J. Chem. Phys*., 113, 8852, 2000.
169. Green, S. M. E., Alex, S., Fleischer, N. L., Millam, E. L., Marcy, T. P., and Leopold, D. G., *J. Chem. Phys*. 114, 2653, 2001.
170. Wu, H., and Wang, L.-S., *J. Chem. Phys*. 108, 5310, 1998.
171. Wu, H., and Wang, L.-S., *J. Phys. Chem. A* 102, 9129, 1998.
172. Wu, H., and Wang, L.-S., *J. Chem. Phys*. 107, 8221, 1997.
173. Thomas, O. C., Xu, S. J., Lippa, T. P., and Bowen, K. H., J. *Cluster Science* 10, 525, 1999.
174. Wang, L.-S., private communication quoted in Ref. 169.
175. Marcy, T. P., PhD dissertation, quoted in Ref. 169.
176. Alex, S., Green, M. E., and Leopold, D. G., unpublished, quoted in Ref. 169.
177. Wang, X.-B., Wang, L.-S., Brown, R., Schwerdtfeger, P., Schröder, D., and Schwarz, H., *J. Chem. Phys*. 114, 7388, 2001.
178. Kim, J. H., Li, X., Wang, L.-S., de Clercq, H. L., Fancher, C. A., Thomas, O. C., and Bowen, K. H., *J. Phys. Chem. A* 105, 5709, 2001.
179. Moravec, V. D., Klopcic, S. A., Chatterjee, B., and Jarrold, C. C., *Chem. Phys. Lett*. 341, 313, 2001.
180. Zengin, V., Persson, B. J., Strong, K. M., and Continetti, R. E., *J. Chem. Phys*. 105, 9740, 1996.
181. Kietzmann, H., Morenzin, J., Bechthold, P. S., Ganteför, G., and Eberhardt, W., *J. Chem. Phys*. 109, 2275, 1998.
182. Xu, C., Taylor, T. R., Burton, G. R., and Neumark, D. M., *J. Chem. Phys*. 108, 7645, 1998.
183. Williams, W. W., Carpenter, D. L., Covington, A. M., Koepnick, M. C., Calabrese, D., and Thompson, J. S., *J. Phys. B: At. Mol. Opt. Phys*. 31, L341, 1998.
184. Covington, A. M., Calabrese, D., Thompson, J. S., and Kvale, T. J., *J. Phys. B: At. Mol. Opt. Phys*. 31, L855, 1998.
185. Haeffler, G., Hanstrorp, D., Kiyan, I., Klinkmueller, A. E., Ljungblad, U., Pegg, D. J., *Phys. Rev. A* 53, 4127, 1996.
186. Chen, H. L., Ellis, Jr., P. E., Wijesekera, T., Hagan, T. E., Groh, S. E., Lyons, J. E., and Ridge, D. P., *J. Am. Chem. Soc*. 116, 1086, 1994.
187. Deyerl, H.-J., Alconcel, L. S., and Continetti, R. E., *J. Phys. Chem. A* 105, 552, 2001.
188. Blanksby, S. J., Ramond, T. M., Davico, G. E., Nimlos, M. R., Kato, S., Bierbaum, V. M., Lineberger, W. C., Ellison, G. B., Okumura, M., *J. Am. Chem. Soc*. 123, 9585, 2001.
189. Asmis, K. R., Taylor, T. R., Xu, C., and Neumark, D. M., *Chem. Phys. Lett*. 295, 75, 1998.
190. Schäfer-Bung, B., Engels, B., Taylor, T. R., Neumark, D. M., Botschwina, P., and Peric, M., *J. Chem. Phys*. 115, 1777, 2001.
191. Scheer, M., Bilodeau, R. C., and Haugen, H. K., Phys. Rev. Lett. 80, 2562, 1998.
192. Taylor, T. R., Gómez, H., Asmis, K. R., and Neumark, D. M., *J. Chem. Phys*. 115, 4620, 2001.
193. Asmis, K. R., Taylor, T. R., and Neumark, D. M., *J. Chem. Phys*. 111, 8838, 1999 and 111, 10491, 1999.
194. Ramond, T. M., Davico, G. E., Schwartz, R. L., and Lineberger, W. C., *J. Chem. Phys*. 112, 1158, 2000.

195. Petrunin, V. V., Voldstad, J. D., Balling, P., Kristensen, P., Andersen, T., and Haugen, H. K., *Phys. Rev. Lett.* 75, 1911, 1995.
196. Dzuba, V. A., and Gribakin, G. F., *J. Phys. B: At. Mol. Opt. Phys*. 31, L483, 1998.
197. Ervin, K. M., Ramond, T. M., Davico, G. E., G. E., Schwartz, R. L., Casey, S. M., and Lineberger, W. C., *J. Phys. Chem*. 105, 10822, 2001.
198. Lippa, T. P., Xu, S.-J., Lyapustina, S. A., and Bowen, K. H., *J. Chem. Phys*. 109, 9263, 1998.
199. Turner, N. J., Martel, A. A., and Waller, I. M., *J. Phys. Chem*. 98, 474, 1994.
200. Lippa, T. P., Xu, S.-J., Lyapustina, S. A., Nilles, J. M., and Bowen, K. H., *J. Chem. Phys*. 109, 10727, 1998.
201. Wang, L.-S., Concericao, J., Changming, C., and Smalley, R. E., *Chem. Phys. Lett*. 182, 5, 1991.
202. Boltalina, O. V., Sidorov, L. N., Sukhanova, E. V., and Sorokin, I. D., *Chem. Phys. Lett*. 230, 567, 1994.
203. Clifford, E. P., Wenthold, P. G., Lineberger, W. C., Ellison, G. B., Wang, C. X., Grabowski, J. J., Vila, F., and Jordan, K. D., *J. Chem. Soc. Perkin Trans*. 2, 1015, 1998.
204. P. Spanel, S. Matejcik, and D. Smith, J. Phys. B: At. Mol. Phys. **28** 2941 (1995). See Miller, A. E. S., Miller, T. M., Viggiano, A. A., Morris, R. A., Van Doren, J. M., Arnold, S. T., and Paulson, J. F., *J. Chem. Phys*. 102, 8865, 1995 for interpretation in terms of EA(SF_5).
205. Kinghom, D. B., and Adamowicz, L., *J. Chem. Phys*. 106, 4589, 1997. EA(H) = 6083.0994 cm^{-1}, EA(D) = 6086.7137 cm^{-1}, and EA(T) = 6087.9168 cm^{-1}.
206. Xi, L., and Wang, L.-S., *J. Chem. Phys*. 109, 5264, 1998.
207. Ephraim, E., Shmulyian, S., Kaldor, U., and Isikawa, Y., *J. Chem. Phys*. 109, 3954, 1998. Also EA(La) = 0.35 eV.
208. Scheer, M., Bilodeau, R. C., Thogersen, J., and Haugen, H. K., *Phys. Rev. A* 57, R1493, 1998.
209. Kim, J. B., Wenthold, P. G., and Lineberger, W. C., *J. Chem. Phys*. 108, 830, 1998.
210. Kishi, R., Kawamata, H., Negishi, Y., Iwata, S., Nakajima, A., and Kaya, K., *J. Chem. Phys*. 107, 10029, 1997.
211. Compton, R. N., Carman, Jr., H. S., Desfrançois, C., Abdoul-Carmine, J., Schermann, J. P., Hendricks, J. H., Lyapustina, S. A., and Bowen, K. H., *J. Chem. Phys*. 105, 3472, 1996.
212. Yourshaw, I., Zhao, Y., and Neumark, D. M., *J. Chem. Phys*. 105, 351, 1996.
213. Gausa, M., Kaschner, R., Seifert, G., Faehrmann, J. H., Lutz, H. O., and Meiwes-Broer, K., *J. Chem. Phys*. 104, 9719, 1996.
214. Wu, H., and Wang, L.-S., *J. Chem. Phys*. 107, 16, 1997; Moravec, V. D., and Jarrold, C. C., *J. Chem. Phys*. 108, 1804, 1998.
215. Radisic, D., Xu, S., and Bowen, K. H., *Chem. Phys. Lett*. 354, 9, 2002.
216. Pramann, A., and Rademann, K., *Chem. Phys. Lett*. 343, 99, 2001.
217. Gómez, H., Taylor, T. R., and Neumark, D. M., *J. Phys. Chem. A* 105, 6886, 2001.
218. Gómez, H., Taylor, T. R., Zhao, Y., and Neumark, D. M., *J. Chem. Phys*. 117, 8644, 2002.
219. Nimlos, M. R., Davico, G., Geise, C. M., Wenthold, P. G., Lineberger, W. C., Blansksby, S. J., Hadad, C. M., Petersson, G. A., Ellison, G. B., *J. Chem. Phys*. 117, 4323, 2002.
220. Koyasu, K., Mitsui, M., Nakajima, A., and Kaya, K., *Chem. Phys. Lett*. 358, 224, 2002.
221. Zhai, H.-J., Wang, L.-S., Alexandrova, A. N., Boldyrev, A. I., and Zakrzewski, V. G., *J. Phys. Chem. A* 107, 9319, 2003.
222. Schiedt, J., and Weinkauf, R., Z. Naturforsch. A 50, 1041, 1995. See also Ervin, K. M., Anusiewicz, I., Skurski, P., Simons, J., and Lineberger, W. C., *J. Phys. Chem. A* 107, 8521, 2003 [EA(O_2) = 0.448 ± 0.006 eV].
223. Davis, V. T., and Thompson, J. S., *J. Phys. B: At. Mol. Opt. Phys*. 34, L433, 2001.
224. Li, X., Zhai, H.-J., and Wang, L.-S., *Chem. Phys. Lett*. 357, 415, 2002.
225. Davis, V. T., and Thompson, J. S., *J. Phys. B: At. Mol. Opt. Phys*. 35, L11, 2002.
227. Blondel, C., Dlesart, C., and Goldfarb, F., *J. Phys. B: At. Mol. Opt. Phys*. 34, L281, 2001.
228. Fancher, C. A., de Clercq, H. L., and Bowen, K. H., *Chem. Phys. Lett*. 366, 197, 2002.
229. Jin, C., Taylor, K. J., Conceicao, J., and Smalley, R. E., *Chem. Phys. Lett*. 175, 17, 1990.
230. Schiedt, J., Knott, W. J., Le Barbu, K., Schlag, E. W., and Weinkauf, R., *J. Chem. Phys*. 113, 9470, 2000.
231. Song, J. K., Lee, N. K., Kim, J. H., Han, S. Y., and Kim, S. K., *J. Chem. Phys*. 119, 3071, 2003.
232. Davico, G. E., Schwartz, R. L., Ramond, T. M., and Lineberger, W. C., J. Amer. Chem. Soc. 121, 6047, 1999.
233. Andrews, D. H., Gianola, A. J., and Lineberger, W. C., *J. Chem. Phys*. 117, 4074, 2002.
234. Schwartz, R. L., Davico, G. E., Kim, J. B., and Lineberger, W. C., *J. Chem. Phys*. 112, 4966, 2000.
235. Schwartz, R. L., Davico, G. E., Ramond, T. M., and Lineberger, W. C., *J. Phys. Chem. A* 103, 8213, 1999.
236. Schiedt, J., and Weinkauf, R., *Chem. Phys. Lett*. 274, 18, 1997.
237. Wang, X.-B., Wang, L.-S., Brown, R., Schwerdtfeger, P., Schröder, D., and Schwartz, H., *J. Chem. Phys*. 114, 7388, 2003.
238. Geske, G. D., Boldyrev, A. I., Li, X., and Wang, L.-S., *J. Chem. Phys*. 113, 5130, 2000.
239. Cannon, N. A., Boldyrev, A. I., Li, X., and Wang, L.–S., *J. Chem. Phys*. 113, 2671, 2000.
240. Wang, X.-B., Yang, X., and Wang, L.-S., *J. Chem. Phys*. 116, 561, 2002.
241. Gutsev, G. L., Jena, P., Zhai, H.-J., and Wang, L.-S., *J. Chem. Phys*. 115, 7935, 2001.
242. Yang, X., Wang, X.-B., and Wang, L.-S., *J. Chem. Phys*. 115, 2889, 2001.
243. Zhai, H.-J., Liu, S.-R., Li, X., and Wang, L.-S., *J. Chem. Phys*. 115, 5170, 2001.
244. Li, X., Wang, L.-S., Cannon, N. A., and Boldyrev, A. I., *J. Chem. Phys*. 116, 1330, 2002.
245. Zhai, H.-J., Wang, L.-S., Alexandrova, A. N., and Boldyrev, A. I., *J. Chem. Phys*. 117, 7917, 2002.
246. Zhai, H.-J., and Wang, L.-S., *J. Chem. Phys*. 117, 7882, 2002.
247. Liu, S.-R., Zhai, H.-J., and Wang, L.-S., *J. Chem. Phys*. 117, 9758, 2002.
248. Mitsui, M., Nakajima, A., and Kaya, K., *J. Chem. Phys*. 117, 9740, 2002.
249. Yang, X., Wang, X.-B., Wang, L.-S., Niu, S., and Ichiye, T., *J. Chem. Phys*. 119, 8311, 2003.
250. Kim, J., Lee, H. M., Suh, S. B., Majumdar, D., and Kim, K. S., *J. Chem. Phys*. 113, 5259, 2000.
251. Liu, S. R., Zhai, H. J., and Wang, L.-S., *Phys. Rev. B* 64, 153402, 2001.
252. Zhai, H. J., Yang, X., Wang, X. B., Wang, L.-S., Elliott, B., and Boldyrev, A. I., *J. Am. Chem. Soc*. 124, 6742, 2002.
253. Zhai, H. J., Wang, L.-S., Kuznetsov, A. E., and Boldyrev, A. I., *J. Phys. Chem. A* 106, 5600, 2002.
254. Drechsler, G., and Boesl, U., *Int. J. Mass Spectrom*. 228, 1067, 2003.
255. Illenberger, E, Comita, P. B., Brauman, J. I., Fenzlaff, H. P., Heni, M., Heinrich, N., Koch, and W., Fenking, G., *Ber. Bunsen-Ges. Phys. Chem*. 89, 1026, 1985; Jackson, R. L., Pellerite, M. J., and Brauman, J. I., *J. Am. Chem. Soc*. 103, 1802, 1981.
256. Miller, T. M., Friedman, J. F., and Viggiano, A. A., *J. Chem. Phys*. 120, 7024, 2004.
257. Miller, T. M., Van Doren, J. M., and Viggiano, A. A., *Int. J. Mass Spectrom*. 233, 67, 2004.
258. Van Doren, J. M., McSweeney, S. A., Hargus, M. D., Kerr, D. M., Miller, T. M., Arnold, S. T., and Viggiano, A. A., *Int. J. Mass Spectrom*. 228, 541, 2003.
259. Van Doren, J. M., Miller, T. M., and Viggiano, A. A., *J. Chem. Phys*. (in press, 2005).
260. Miller, T. M., and Viggiano, A. A., *Phys. Rev. A* (in press, 2005).
261. Haeffler, G., Klinkmueller, A. E., Rangell, J., Berzinsh, U., and Hanstorp, D., *Z. Phys. D* 38, 211, 1996.
262. Bilodeau, R. C., and Haugen, H. K., *Phys. Rev. A* 64, 024501, 2001.
263. Miller, T. M., Viggiano, A. A., Friedman, J. F., and Van Doren, J. M., *J. Chem. Phys.* 121, 9993, 2004.

264. Davis, V. T., and Thompson, J. S., Phys. Rev. A 65, 010501, 2001. Theoretical work implies that the measured EA(Tm) was actually for a long-lived excited anion state, and that Tm does not form a stable anion. See O'Malley, S. M., and Beck, D. R., *Phys. Rev. A* 70, 022502, 2004.
265. Gianola, A. J., Ichino, T., Hoenigman, R. L., Kato, S., Bierbaum, V. M., and Lineberger, W. C., *J. Phys. Chem. A* 108, 10326, 2004.
266. Staneke, P. O., Groothuis, G., Ingemann, S., and Nibbering, N. M. M., *Int. J. Mass Spectrom. Ion Processes* 142, 83, 1995. A Gaussian-3 calculation yields EA(CCl_4) = 0.994 eV [Ed.].
267. Meloni, G., Ferguson, M. J., and Neumark, D. M., *Phys. Chem. Chem. Phys*. 5, 4073, 2003.
268. Davis, V. T., and Thompson, J. S., *J. Phys. B: At. Mol. Opt. Phys*. 37, 1961, 2004.
269. Davis, V. T., and Thompson, J. S., *Phys. Rev. Lett*. 88, 073003, 2002.
270. Ando, N., Kokubo, S., Mitsui, M., and Nakajima, A., *Chem. Phys. Lett*. 389, 279, 2004.
271. Zhai, H.-J., and Wang, L.-S., *J. Chem. Phys*. 120, 8996, 2004.
272. Surber, E., and Sanov, A., *J. Chem. Phys*. 116, 5921, 2002.
273. Dzuba, V. A., and Gribakin, G. F., *Phys. Rev. A* 55, 2443, 1997.
274. Meloni, G., Sheehan, S. M., Ferguson, M. J., and Neumark, D. M., *J. Phys. Chem. A* 108, 9750, 2004.
275. Zhai, H.-J., Li, J., and Wang, L.-S., *J. Chem. Phys*. 121, 8369, 2004.
276. Zhai, H.-J., Kiran, B., and Wang, L.-S., *J. Chem. Phys*. 121, 8231, 2004.
277. Kim, J., Kelley, J. A., Ayotte, P., Nielsen, S. B., Weddle, G. H., and Johnson, M. A., *J. Am. Soc. Mass Spectrom*. 10, 810, 1999.
278. Misaizu, F., Tsunoyama, H., Yasumura, Y., Ohshimo, K., and Ohno, K., *Chem. Phys. Lett.* 389, 241, 2004. See also Ref. 236 for comments on EA(CS).

ATOMIC AND MOLECULAR POLARIZABILITIES

Thomas M. Miller

The *polarizability* of an atom or molecule describes the response of the electron cloud to an external field. The atomic or molecular energy shift ΔW due to an external electric field E is proportional to E^2 for external fields which are weak compared to the internal electric fields between the nucleus and electron cloud. The *electric dipole polarizability* α is the constant of proportionality defined by $\Delta W = -\alpha E^2/2$. The induced electric dipole moment is αE. *Hyperpolarizabilities*, coefficients of higher powers of E, are less often required. Technically, the polarizability is a tensor quantity but for spherically symmetric charge distributions reduces to a single number. In any case, an *average polarizability* is usually adequate in calculations. Frequency-dependent or *dynamic polarizabilities* are needed for electric fields which vary in time, except for frequencies which are much lower than electron orbital frequencies, where *static polarizabilities* suffice.

Polarizabilities for atoms and molecules in excited states are found to be larger than for ground states and may be positive or negative. Molecular polarizabilities are very slightly temperature dependent since the size of the molecule depends on its rovibrational state. Only in the case of dihydrogen has this effect been studied enough to warrant consideration in Table 3.

Polarizabilities are normally expressed in cgs units of cm^3. Ground state polarizabilities are in the range of 10^{-24} cm^3 = 1 $Å^3$ and hence are often given in $Å^3$ units. Theorists tend to use atomic units of a_o^3 where a_o is the Bohr radius. The conversion is $\alpha(cm^3) = 0.148184 \times 10^{-24} \times \alpha(a_o^3)$. Polarizabilities are only recently encountered in SI units, $C\,m^2/V = J/(V/m)^2$. The conversion from cgs units to SI units is $\alpha(C\,m^2/V) = 4\pi\varepsilon_o \times 10^{-6}\ \alpha(cm^3)$, where ε_o is the permittivity of free space in SI units and the factor 10^{-6} simply converts cm^3 into m^3. Thus, $\alpha(C\,m^2/V) = 1.11265 \times 10^{-16} \times \alpha(cm^3)$. Persons measuring excited state polarizabilities by optical methods tend to use units of $MHz/(V/cm)^2$, where the energy shift, ΔW, is expressed in frequency units with a factor of h understood. The polarizability is $-2\,\Delta W/E^2$. The conversion into cgs units is $\alpha(cm^3) = 5.95531 \times 10^{-16} \times \alpha[MHz/(V/cm)^2]$.

The polarizability appears in many formulas for low-energy processes involving the valence electrons of atoms or molecules. These formulas are given below in cgs units: the polarizability α is in cm^3; masses m or μ are in grams; energies are in ergs; and electric charges are in esu, where $e = 4.8032 \times 10^{-10}$ esu. The symbol $\alpha(\nu)$ denotes a frequency (ν) dependent polarizability, where $\alpha(\nu)$ reduces to the static polarizability α for $\nu = 0$. For further information and references, see Miller, T. M., and Bederson, B., *Advances in Atomic and Molecular Physics*, 13, 1, 1977. Details on polarizability-related interactions, especially in regard to hyperpolarizabilities and nonlinear optical phenomena, are given by Bogaard, M. P., and Orr, B. J., in *Physical Chemistry*, Series Two, Vol. 2, *Molecular Structure and Properties*, Buckingham, A. D., Ed., Butterworths, London, 1975, pp. 149-194. A tabulation of tensor and hyperpolarizabilities is included. The gas number density, n, in Table 1 is usually taken to be that of 1 atm at 0°C in reporting experimental data.

TABLE 1. Formulas Involving Polarizability

Description	Formula	Remarks
Lorentz-Lorenz relation	$\alpha(\nu) = \frac{3}{4\pi n}\left[\frac{\eta^2(\nu)-1}{\eta^2(\nu)+2}\right]$	For a gas of atoms or nonpolar molecules; the index of refraction is $\eta(\nu)$
Refraction by polar molecules	$\alpha(\nu) + \frac{d^2}{3kT} = \frac{3}{4\pi n}\left[\frac{\eta^2(\nu)-1}{\eta^2(\nu)+2}\right]$	The dipole moment is d, in esu·cm (= 10^{-18} D)
Dielectric constant (dimensionless)	$\kappa(\nu) = 1 + 4\pi n\ \ \alpha(\nu)$	From the Lorentz-Lorenz relation for the usual case of $\kappa(\nu) \approx 1$
Index of refraction (dimensionless)	$\eta(\nu) = 1 + 2\pi n\ \ \alpha(\nu)$	From $\eta^3(\nu) = \kappa(\nu)$
Diamagnetic susceptibility	$\chi_m = e^2\left(a_o N\alpha\right)^{1/2} / 4m_e c^2$	From the approximation that the static polarizability is given by the variational formula $\alpha = (4/9a_o)\Sigma(N_i r_i^2)^2$; N is the number of electrons, m_e is the electron mass; a crude approximation is $\chi_m = (E_i/4m_e c^2)\alpha$, where E_i is the ionization energy
Long-range electron- or ion-molecule interaction energy	$V(r) = -e^2\alpha / 2r^4$	The target molecule polarizability is α
Ion mobility in a gas	$\kappa = -13.87 / \left(\alpha\mu\right)^{1/2}\,cm^2 / V\cdot s$	This one formula is not in cgs units. Enter α in $Å^3$ or 10^{-24} cm^3 units and the reduced mass μ of the ion-molecule pair in amu. Classical limit; pure polarization potential
Langevin capture cross section	$\sigma(v_o) = \left(2\pi e / v_o\right)\left(\alpha / \mu\right)^{1/2}$	The relative velocity of approach for an ion-molecule pair is v_o; the target molecular polarizability is α and the reduced mass of the ion-molecule pair is μ
Langevin reaction rate coefficient	$k = 2\pi e\left(\alpha / \mu\right)^{1/2}$	Collisional rate coefficient for an ion-molecule reaction
Rate coefficient for polar molecules	$k_d = 2\pi e\left[\left(\alpha / \mu\right)^{1/2} + cd\left(2 / \mu\pi kT\right)^{1/2}\right]$	The dipole moment of the neutral is d in esu cm; the number c is a "locking factor" that depends on $\underline{\alpha}$ and d, and is between 0 and 1

Description	Formula	Remarks
Modified effective range cross section for electron-neutral scattering	$\sigma(k) = 4\pi A^2 + 32\pi^4 \mu e^2 \alpha A k / 3h^2 + \ldots$	Here, k is the electron momentum divided by $h/2\pi$, where h is Planck's constant; A is called the "scattering length"; the reduced mass is μ
van der Waals constant between two systems A, B	$C_6 = \frac{3}{2}\left[\frac{\alpha^A \alpha^B E^A E^B}{E^A + E^B}\right]$	For the interaction potential term $V_6(r) = -C_6 r^6$; $E^{A,B}$ represents average dipole transition energiesand $\alpha^{A,B}$ the respective polarizabilities of A, B
Dipole-quadrupole constant between two systems A, B	$C_8 = \frac{15}{4}\left[\frac{\alpha^A \alpha_q{}^B E^A E_q{}^B}{E^A + E_q{}^B}\right] + \frac{15}{4}\left[\frac{\alpha_q{}^A \alpha^B E_q{}^A E^B}{E_q{}^A + E^B}\right]$	For the interaction potential term $V_8(r) = -C_8 r^8$; $E_q^{A,B}$ represents average quadrupole transition energies and $\alpha_q^{A,B}$ are the respective quadrupole polarizabilities of A, B
van der Waals constant between an atom and a surface	$C_3 = \frac{\alpha g E^A E^S}{8(E^A + E^S)}$	For an interaction potential $V_3(r) = -C_3 r^3$; $E^{A,S}$ are characteristic energies of the atom and surface; $g = 1$ for a free-electron metal and $g = (\varepsilon_\infty - 1)/(\varepsilon_\infty + 1)$ for an ionic crystal
Relationship between α(ν) and oscillator strengths	$\alpha(\nu) = \frac{e^2 h^2}{4\pi^2 m_e} \Sigma \frac{f_k}{E_k^2 - (h\nu)^2}$	Here, f_k is the oscillator strength from the ground state to an excited state k, with excitation energy E_k. This formula is often used to estimate static polarizabilities (ν = 0)
Dynamic polarizability	$\alpha(\nu) = \frac{\alpha E_r{}^2}{E_r{}^2 - (h\nu)^2}$	Approximate variation of the frequency-dependent polarizability α(ν) from ν = 0 up to the first dipole-allowed electronic transition, of energy E_r; the static dipole polarizability is α(0); infrared contributions ignored
Rayleigh scattering cross section	$\alpha(\nu) = \frac{8\pi}{9c^4}(2\pi\nu)^4 \times \left[3\alpha^2(\nu) + 2\gamma^2(\nu)/3\right]$	The photon frequency is ν; the polarizability anisotropy (the difference between polarizabilities parallel and perpendicular to the molecular axis) is γ(ν)
Verdet constant	$V(\nu) = \frac{\nu n}{2 m_e c^2}\left[\frac{d\alpha(\nu)}{d\nu}\right]$	Defined from $\theta = V(\nu)B$, where θ is the angle of rotation of linearly polarized light through a medium of number density n, per unit length, for a longitudinal magnetic field strength B (Faraday effect)

TABLE 2. Static Average Electric Dipole Polarizabilities for Ground State Atoms (in Units of 10^{-24} cm^3)

Atomic number	Atom	Polarizability	Estimated accuracy (%)	Method	Ref.
1	H	0.666793	"exact"	calc	MB77
2	He	0.2050522	"exact"	calc	LJS04
		0.2050	0.1	index/diel	NB65/ OC67
3	Li	24.3	2	beam	MB77
4	Be	5.60	2	calc	MB77
5	B	3.03	2	calc	MB77
6	C	1.76	2	calc	MB77
7	N	1.10	2	calc/index	MB77
8	O	0.802	2	calc/index	MB77
9	F	0.557	2	calc	MB77
10	Ne	0.3956	0.1	diel	OC67
11	Na	24.11	0.12	interferom	ESCHP94
12	Mg	10.6	2	calc	MB77
		11.1	5	calc	S71
		10.6	5	calc	BM02
13	Al	6.8	4.4	beam	MMD90
14	Si	5.38	2	calc	MB77
15	P	3.63	2	calc	MB77
16	S	2.90	2	calc	MB77
17	Cl	2.18	2	calc	MB77
18	Ar	1.6411	0.05	index/diel	NB65/ OC67
19	K	43.4	2	beam	MB77
20	Ca	22.8	2	calc	MB77
		29.4	6	calc	BM02
		25.0	8	beam	MB77
21	Sc	17.8	25	calc	D84
22	Ti	14.6	25	calc	D84
23	V	12.4	25	calc	D84
24	Cr	11.6	25	calc	D84
25	Mn	9.4	25	calc	D84
26	Fe	8.4	25	calc	D84
27	Co	7.5	25	calc	D84
28	Ni	6.8	25	calc	D84
29	Cu	6.2	6	calc	BM02
		6.1	25	calc	D84
30	Zn	5.75	2	index	GHM96
		6.1	6	calc	BM02
		5.6	25	calc	D84
31	Ga	8.12	2	calc	MB77
32	Ge	6.07	2	calc	MB77
33	As	4.31	2	calc	MB77
34	Se	3.77	2	calc	MB77
35	Br	3.05	2	calc	MB77
36	Kr	2.4844	0.05	diel	OC67
37	Rb	47.3	2	beam	MB77
38	Sr	27.6	8	beam	MB77
		23.5	6	calc	BM02
39	Y	22.7	25	calc	D84

Atomic number	Atom	Polarizability	Estimated accuracy (%)	Method	Ref.
40	Zr	17.9	25	calc	D84
41	Nb	15.7	25	calc	D84
42	Mo	12.8	25	calc	D84
43	Tc	11.4	25	calc	D84
44	Ru	9.6	25	calc	D84
45	Rh	8.6	25	calc	D84
46	Pd	4.8	25	calc	D84
47	Ag	7.2	25	calc	D84
48	Cd	7.36	3	index	GH95
		7.4	6	calc	BM02
		7.2	25	calc	D84
49	In	10.2	12	beam	GMBSJ84
		9.1	25	calc	D84
50	Sn	7.7	25	calc	D84
51	Sb	6.6	25	calc	D84
52	Te	5.5	25	calc	D84
53	I	5.35	25	index	A56
		4.7	25	calc	D84
54	Xe	4.044	0.5	diel	MB77
55	Cs	59.42	0.13	beam	AG03
56	Ba	39.7	8	beam	MB77
57	La	31.1	25	calc	D84
58	Ce	29.6	25	calc	D84
59	Pr	28.2	25	calc	D84
60	Nd	31.4	25	calc	D84
61	Pm	30.1	25	calc	D84
62	Sm	28.8	25	calc	D84
63	Eu	27.7	25	calc	D84
64	Gd	23.5	25	calc	D84
65	Tb	25.5	25	calc	D84
66	Dy	24.5	25	calc	D84
67	Ho	23.6	25	calc	D84
68	Er	22.7	25	calc	D84
69	Tm	21.8	25	calc	D84
70	Yb	21.0	25	calc	D84
71	Lu	21.9	25	calc	D84
72	Hf	16.2	25	calc	D84
73	Ta	13.1	25	calc	D84
74	W	11.1	25	calc	D84
75	Re	9.7	25	calc	D84
76	Os	8.5	25	calc	D84
77	Ir	7.6	25	calc	D84
78	Pt	6.5	25	calc	D84
79	Au	5.8	25	calc	D84
80	Hg	5.02	1	index	GH96
		5.7	25	calc	D84
81	Tl	7.6	15	beam	NYU84
		7.5	25	calc	D84
82	Pb	6.8	25	calc	D84
83	Bi	7.4	25	calc	D84
84	Po	6.8	25	calc	D84
85	At	6.0	25	calc	D84
86	Rn	5.3	25	calc	D84
87	Fr	47.1	5	calc	DJSB99
		48.7	25	calc	D84
88	Ra	38.3	25	calc	D84
89	Ac	32.1	25	calc	D84
90	Th	32.1	25	calc	D84
91	Pa	25.4	25	calc	D84
92	U	24.9	6	beam	KB94
93	Np	24.8	25	calc	D84
94	Pu	24.5	25	calc	D84
95	Am	23.3	25	calc	D84
96	Cm	23.0	25	calc	D84
97	Bk	22.7	25	calc	D84
98	Cf	20.5	25	calc	D84
99	Es	19.7	25	calc	D84
100	Fm	23.8	25	calc	D84
101	Md	18.2	25	calc	D84
102	No	17.5	25	calc	D84

[a] Methods: calc = calculated value; beam = atomic beam deflection technique; interferom = atomic beam interference; index = determination based on the measured index of refraction; diel = determination based on the measured dielectric constant.

References

A56. Atoji, M., *J. Chem. Phys.*, 25, 174, 1956. Semiempirical method based on molecular polarizabilities and atomic radii.

AG03. Amini, J. M., and Gould, H., *Phys. Rev. Lett.* 91, 153001, 2003.

BM02. Bromley, M. W. J., and Mitroy, *J., Phys. Rev. A* 65, 062505, 2002; 062506, 2002.

D84. Doolen, G. D., Los Alamos National Laboratory, unpublished. A relativistic linear response method was used. The method is that described by Zangwill, A., and Soven, P., *Phys. Rev. A*, 21, 1561, 1980. Adjustments of less than 10% across the periodic table have been made to these results to bring them into agreement with accurate experimental values where available, for the purpose of presenting "recommended" polarizabilities in Table 2.

DJSB99. Derevianko, A., Johnson, W. R., Safronova, M. S., and Babb, J. F., *Phys. Rev. Lett.* 82, 3589, 1999.

ESCHP94. Ekstrom, C. R., Schmiedmayer, J., Chapman, M. S., Hammond, T. D., and Pritchard, D. E., *Phys. Rev. A* 51, 3883, 1995.

GH95. Goebel, D., and Holm, U., *Phys. Rev. A* 52, 3691, 1995.

GH96. Goebel, D., and Holm, U., *J. Chem. Phys.* 100, 7710, 1996.

GHM96. Goebel, D., Holm, U., and Maroulis, G., *Phys. Rev. A* 54, 1973, 1996.

GMBSJ84. Guella, T. P., Miller, T. M., Bederson, B., Stockdale, J. A. D., and Jaduszliwer, B., *Phys. Rev. A*, 29, 2977, 1984.

KB94. Kadar-Kallen, M. A., and Bonin, K. D., *Phys. Rev. Lett.*, 72, 828, 1994.

LJS04. Lach, G., Jezionski, B., and Szalewicz, K., *Phys. Rev. Lett.* 92, 23301, 2004.

MB77. Miller, T. M., and Bederson, B., *Adv. At. Mol. Phys.*, 13, 1, 1977. For simplicity, any value in Table 2 which has not changed since this 1977 review is referenced as MB77. Persons interested in original references and further details should consult MB77.

MMD90. Milani, P., Moullet, I., and de Heer, W. A., *Phys. Rev. A*, 42, 5150, 1990. See a theoretical comment on this result, in Fuentealba, P., *Chem. Phys. Lett.*, 397, 459, 2004.

NB65. Newell, A. C., and Baird, R. D., *J. Appl. Phys.*, 36, 3751, 1965.

NYU84. Preliminary value from the New York University group. See GMBSJ84.

OC67. Orcutt, R. H., and Cole, R. H., *J. Chem. Phys.*, 46, 697, 1967; see also the later references from this group, given following the tables.

S71. Stwalley, W. C., *J. Chem. Phys.* 54, 4517, 1971.

TABLE 3. Average Electric Dipole Polarizabilities for Ground State Diatomic Molecules (in Units of 10^{-24} cm^3)

Molecule	Polarizability	Ref.
Al_2	19	23
BH	3.32*	1
Br_2	7.02	2
CO	1.95	3
Cl_2	4.61	3
Cs_2	104	22
CsK	89	22
D_2 (v=0,J=0)	0.7921*	5
D_2 (293 K)	0.7954	6
DCl	2.84	2
F_2	1.38*	7
H_2 (v=0,J=0)	0.8023*	5
H_2 (293 K)	0.8045*	5
H_2 (293 K)	0.8042	6
H_2 (322 K)	0.8059	8
HBr	3.61	3
HCl	2.63	3
	2.77	2
HD (v=0,J=0)	0.7976*	5
HF	0.80	27
HI	5.44	3
	5.35	2
HgCl	7.4*	9
ICl	12.3	2
K_2	77	22
	72	21
Li_2	32.8	29
	34	22
LiCl	3.46*	10
LiF	10.8*	11
LiH	3.84*	12
	3.68*	13
	3.88*	14
N_2	1.7403	6,8
NO	1.70	2
Na_2	40	22
	38	21
NaK	51	22
NaLi	40	4
O_2	1.5812	6
Rb2	79	22

TABLE 4. Average Electric Dipole Polarizabilities for Ground State Triatomic Molecules (in Units of 10^{-24} CM^3)

Molecule	Polarizability	Ref.
BeH_2	4.34*	14
CO_2	2.911	8
CS_2	8.74	3
	8.86	2
D_2O	1.26	2
H_2O	1.45	2
H_2S	3.782	3
	3.95	2
HCN	2.59	3
	2.46	2
$HgBr_2$	14.5	2
$HgCl_2$	11.6	2
HgI_2	19.1	2
Li_3	34.5	29
$LiNa_2$	61.2	30
Li_2Na	35.4	30
N_2O	3.03	8
NO_2	3.02	2†
Na_3	70	21
O_3	3.21	2
OCS	5.71	2
	5.2	15
SO_2	3.72	3
	4.28	2

TABLE 5. Average Electric Dipole Polarizabilities for Ground State Inorganic Polyatomic Molecules (Larger than Triatomic) (in Units of 10^{-24} cm^3)

Molecule	Polarizability	Ref.
$AsCl_3$	14.9	2
AsN_3	5.75	2
BCl_3	9.38	20
BF_3	3.31	2
$(BN_3)_2$	5.73	2
$(BH_2N)_3$	8.0	2†
ClF_3	6.32	2
$(CsBr)_2$	54.5	16
$(CsCl)_2$	42.4	16
$(CsF)_2$	28.4	16
$(CsI)_2$	51.8	16
Ga_nAs_m	n+m=4-30	28
$GeCl_4$	15.1	2
GeH_3Cl	6.7	2†
$(HgCl)_2$	14.7	9
K_n	n=2,5,7-9,11,20	21
$(KBr)_2$	42.0	16
$(KCl)_2$	32.1	16
$(KF)_2$	21.0	16
$(KI)_2$	36.3	16
Li_n	n=2-22	29
$(LiBr)_2$	18.9	16
$(LiCl)_2$	13.1	16
$(LiF)_2$	6.9	16
$(LiI)_2$	23.4	16
$LiNa_3$	75.6	30
Li_2Na_2	60.0	30
Li_3Na	54.8	30
ND_3	1.70	2
NF_3	3.62	2
NH_3	2.81	20
	2.10	2
	2.26	3
	2.22*	33
$(NO_2)_2$	6.69	2

Molecule	Polarizability	Ref.
Na_n	n=1-40	21
$(NaBr)_2$	26.8	16
$(NaCl)_2$	23.4	16
$(NaF)_2$	20.7	16
$(NaI)_2$	26.9	16
OsO_4	8.17	2
PCl_3	12.8	2
PF_5	6.10	2
PH_3	4.84	2
$(RbBr)_2$	48.2	16
$(RbCl)_2$	43.2	16
$(RbF)_2$	40.7	16
$(RbI)_2$	46.3	16
SF_6	6.54	8
$(SF_5)_2$	13.2	2
SO_3	4.84	2
SO_2Cl_2	10.5	2
SeF_6	7.33	2
SiF_4	5.45	2
SiH_4	5.44	2
$(SiH_3)_2$	11.1	2
$SiHCl_3$	10.7	2
SiH_2Cl_2	8.92	2
SiH_3Cl	7.02	2
$SnBr_4$	22.0	2
$SnCl_4$	18.0	2
	13.8	15
SnI_4	32.3	2
TeF_6	9.00	2
$TiCl_4$	16.4	2
UF6	12.5	2

TABLE 6 Average Electric Dipole Polarizabilities for Ground State Hydrocarbon Molecules (in Units of 10^{-24} cm^3)

Molecule	Name	Polarizability	Ref.
CH_4	methane	2.593	8
C_2H_2	acetylene	3.33	3
		3.93	2
C_2H_4	ethylene	4.252	8
C_2H_6	ethane	4.47	3
		4.43	2
C_3H_4	propyne	6.18	2
C_3H_6	propene	6.26	2
	cyclopropane	5.66	2
C_3H_8	propane	6.29	3
		6.37	2
C_4H_6	1-butyne	7.41	2†
	1,3-butadiene	8.64	2
C_4H_8	1-butene	7.97	2
		8.52	2
	trans-2-butene	8.49	2
	2-methylpropene	8.29	2
C_4H_{10}	butane	8.20	2
	isobutane	8.14	27
C_5H_6	1,3-cyclopentadiene	8.64	2
C_5H_8	1-pentyne	9.12	2
	trans-1,3-pentadiene	10.0	2
	isoprene	9.99	2
C_5H_{10}	cyclopentane	9.15	18
	1-pentene	9.65	27
	2-pentene	9.84	27
C_5H_{12}	pentane	9.99	2
	neopentane	10.20	18
C_6H_6	benzene	10.0	25
		10.32	3
		10.74	2
C_6H_{10}	1-hexyne	10.9	2†
	2-ethyl-1,3-butadiene	11.8	2†
	3-methyl-1,3-pentadiene	11.8	2†
	2-methyl-1,3-pentadiene	12.1	2†
	2,3-dimethyl-1,3-butadiene	11.8	2†
	cyclohexene	10.7	2†
C_6H_{12}	cyclohexane	11.0	18
		10.87	15
	1-hexene	11.65	27
C_6H_{14}	hexane	11.9	2
C_7H_8	toluene	11.8	25
		12.26	15
		12.3	2
C_7H_{12}	1-heptyne	12.8	2†
C_7H_{14}	methylcyclohexane	13.1	2
	1-heptene	13.51	27
C_7H_{16}	heptane	13.61	2
C_8H_8	styrene	15.0	2
		14.41	27
C_8H_{10}	ethylbenzene	14.2	2
	o-xylene	14.9	2
		14.1	15
	p-xylene	13.7	25
		14.2	15
		14.9	2
	m-xylene	14.2	15
C_8H_{16}	ethylcyclohexane	15.9	2
C_8H_{18}	*n*-octane	15.9	2
	3-methylheptane	15.44	27
	2,2,4-trimethylpentane	15.44	27
C_9H_{10}	α- methylstyrene	16.05	27
C_9H_{12}	isopropylbenzene	16.0	2†
	1,3,5-trimethylbenzene	15.5	25
		16.14	27
C_9H_{18}	isopropylcyclohexane	17.2	2
C_9H_{20}	nonane	17.36	27
$C_{10}H_8$	naphthalene	16.5	17
		17.48	27
$C_{10}H_{14}$	durene	17.3	25
	tert- butylbenzene	17.2	25
		17.8	2†
$C_{10}H_{20}$	*tert*-butylcyclohexane	19.8	2
$C_{10}H_{22}$	decane	19.10	27
$C_{11}H_{10}$	α-methylnaphthalene	19.35	27
	β-methylnaphthalene	19.52	27
$C_{11}H_{14}$	α,β,β-trimethylstyrene	19.64	27
$C_{11}H_{16}$	pentamethylbenzene	19.1	25
$C_{11}H_{24}$	undecane	21.03	27
$C_{12}H_{10}$	acenaphthene	20.61	27
$C_{12}H_{12}$	α-ethylnaphthalene	21.19	27
	β-ethylnaphthalene	21.36	27
$C_{12}H_{18}$	hexamethylbenzene	20.9	25

Molecule	Name	Polarizability	Ref.
$C_{12}H_{26}$	dodecane	22.75	27
$C_{13}H_{10}$	fluorene	21.68	27
$C_{14}H_{10}$	anthracene	25.4	17
		25.93	27
	phenanthrene	36.8*	17
		24.70	27
$C_{14}H_{22}$	*p*-di-*tert*-butylbenzene	24.5	25
$C_{16}H_{10}$	pyrene	28.22	27
$C_{17}H_{12}$	2,3- benzfluorene	30.21	27
$C_{18}H_{12}$	naphthacene	32.27	27
	1,2- benzanthracene	32.86	27
	chrysene	33.06	27
	triphenylene	31.07	27
$C_{18}H_{30}$	1,3,5-tri-*tert*-butylbenzene	31.8	25
$C_{24}H_{12}$	coronene	42.50	27

TABLE 7. Average Electric Dipole Polarizabilities for Ground State Organic Halides (in Units of 10^{-24} cm^3)

Molecule	Name	Polarizability	Ref.
CBr_2F_2	dibromodifluoromethane	9.0	2†
$CClF_3$	chlorotrifluoromethane	5.72	20
		5.59	2
CCl_2F_2	dichlorodifluoromethane	7.93	20
		7.81	2
CCl_2O	phosgene	7.29	2
CCl_2S	thiophosgene	10.2	2
CCl_3F	trichlorofluoromethane	9.47	2
CCl_3NO_2	trichloronitromethane	10.8	2†
CCl_4	carbon tetrachloride	11.2	2
		10.5	3
CF_4	carbon tetrafluoride	3.838	8
CF_2O	carbonylfluoride	1.88*	17
$CHBr_3$	bromoform	11.8	27
$CHBrF_2$	bromodifluoromethane	5.7	2†
$CHClF_2$	chlorodifluoromethane	6.38	20
		5.91	2
$CHCl_2F$	dichlorofluoromethane	6.82	2
$CHCl_3$	chloroform	9.5	8
		8.23	27
CHF_3	fluoroform	3.52	20
		3.57	8
CHFO	fluoroformaldehyde	1.76*	17
CHI_3	iodoform	18.0	27
CH_2Br_2	dibromomethane	9.32	2
		8.68	27
CH_2ClNO_2	chloronitromethane	6.9	2†
CH_2Cl_2	dichloromethane	6.48	3
		7.93	2
CH_2I_2	diiodomethane	12.90	27
CH_3Br	bromomethane	5.87	20
		6.03	2
		5.55	15
CH_3Cl	chloromethane	5.35	20
		4.72	8
CH_3F	fluoromethane	2.97	8
CH_3I	iodomethane	7.97	2
C_2ClF_5	chloropentafluoroethane	6.3	2†
$C_2Cl_2F_4$	1,2-dichlorotetrafluoroethane	8.5	2†
C_2Cl_3N	trichloroacetonitrile	10.42	18
C_2F_6	hexafluoroethane	6.82	2
C_2HBr	bromoacetylene	7.39	2
C_2HCl	chloroacetylene	6.07	2
C_2HCl_3	trichloroethlyene	10.03	27
C_2HCl_5	pentachloroethane	14.0	2
$C_2H_2Cl_2$	1,1-dichloroethylene	7.83	27
	trans-dichloroethylene	8.15	27
	cis-dichloroethylene	8.03	27
$C_2H_2Cl_2F_2$	1,1-dichloro-2,2-difluoroethane	8.4	2†
$C_2H_2Cl_2O$	chloroacetyl chloride	8.92	2
$C_2H_2Cl_3F$	1,2,2-trichloro-1-fluoroethane	10.2	2†
$C_2H_2Cl_4$	1,1,2,2-tetrachloroethane	12.1	2†
C_2H_2ClN	chloroacetonitrile	6.10	18
$C_2H_2F_2$	1,1-difluoroethylene	5.01	20
C_2H_3Br	bromoethylene	7.59	2
C_2H_3Cl	chloroethylene	6.41	2
$C_2H_3ClF_2$	1-chloro-1,1-difluoroethane	8.05	2
C_2H_3ClO	acetyl chloride	6.62	2
$C_2H_3ClO_2$	methyl chloroformate	7.1	2†
$C_2H_3Cl_3$	1,1,1-trichloroethane	10.7	2
$C_2H_3F_3$	1,1,1-trifluoroethane	4.4	2†
C_2H_3I	iodoethylene	9.3	2†
C_2H_4BrCl	1-bromo-2-chloroethane	9.5	2†
$C_2H_4Br_2$	1,2-dibromoethane	10.7	2†
C_2H_4ClF	1-chloro-2-fluoroethane	6.5	2†
$C_2H_4ClNO_2$	1-chloro-1-nitroethane	10.9	2
$C_2H_4Cl_2$	1,1-dichloroethane	8.64	2
	1,2-dichloroethane	8.0	2†
C_2H_5Br	bromoethane	8.05	2
		7.28	27
C_2H_5Cl	chloroethane	7.27	20
		8.29	2
		6.4	15
C_2H_5ClO	2-chloroethanol	7.1	2†
		6.88	27
	chloromethyl methyl ether	7.1	2†
C_2H_5F	fluoroethane	4.96	2
C_2H_5I	iodoethane	10.0	2
$C_3H_4Cl_2$	dichloropropene	10.1	2†
C_3H_5Cl	chloropropene	8.3	2
C_3H_5ClO	chloroacetone	8.4	2†
$C_3H_5ClO_2$	ethyl chloroformate	9.0	2†
$C_3H_6ClNO_2$	1-chloro-1-nitropropane	10.4	2†
$C_3H_6Cl_2$	dichloropropane	10.9	2†
C_3H_7Br	1-bromopropane	9.4	2†
		9.07	27
	2-bromopropane	9.6	2†
C_3H_7Cl	chloropropane	10.0	2
C_3H_7ClO	β-chloroethyl methyl ether	8.71	27
	2-chloro-1-propanol	8.89	27
	3-chloro-1-propanol	8.84	27
C_3H_7I	1-iodopropane	11.5	2†
C_4H_5Cl	4-chloro-1,2-butadiene	10.0	2†
C_4H_7Cl	1-chloro-2-methylpropene	10.8	2
$C_4H_7ClO_2$	2-chlorobutyric acid	10.87	27
	3-chlorobutyric acid	10.80	27
	4-chlorobutyric acid	10.69	27
$C_4H_8Cl_2$	1,4-dichlorobutane	12.0	2†
C_4H_9Br	bromobutane	13.9	2

Molecule	Name	Polarizability	Ref.
		10.86	27
C_4H_9Cl	1-chlorobutane	11.3	2
	1-chloro-2-methylpropane	11.1	2
	2-chloro-2-methylpropane	12.5	2†
	2-chlorobutane	12.4	2
C_4H_9ClO	β-chloroethyl ethyl ether	10.56	27
	2-chloro-1-butanol	10.70	27
	3-chloro-1-butanol	10.38	27
C_4H_9I	1-iodobutane	13.3	2†
		12.65	27
$C_5H_9ClO_2$	methyl 2-chlorobutanoate	12.33	27
	methyl 3-chlorobutanoate	12.31	27
	methyl 4-chlorobutanoate	12.27	27
	2-chloropentanoic acid	12.69	27
	3-chloropentanoic acid	12.57	27
	4-chloropentanoic acid	12.53	27
$C_5H_{11}Br$	1-bromopentane	13.1	2†
$C_5H_{11}Cl$	1-chloropentane	12.0	2†
$C_5H_{11}F$	fluoropentane	9.95	27
C_6F_6	hexafluorobenzene	9.58	27
C_6HF_5	pentafluorobenzene	9.63	27
$C_6H_2Cl_2O_2$	2,5-dichloro-1,4-benzoquinone	18.4	2
$C_6H_2F_4$	1,2,3,4-tetrafluorobenzene	9.69	27
	1,2,4,5-tetrafluorobenzene	9.69	27
$C_6H_3F_3$	1,3,5-trifluorobenzene	9.74	27
C_6H_4BrF	*p*-bromofluorobenzene	13.4	2†
$C_6H_4ClNO_2$	chloronitrobenzene	14.6	2†
$C_6H_4Cl_2$	*o*-dichlorobenzene	14.17	27
	m-dichlorobenzene	14.23	27
	p-dichlorobenzene	14.20	27
C_6H_4FI	*p*-fluoroiodobenzene	15.5	2†
$C_6H_4FNO_2$	*p*-fluoronitrobenzene	12.8	2†
$C_6H_4F_2$	*o*-difluorobenzene	9.80	27
	m-difluorobenzene	10.3	2†
	p-difluorobenzene	9.80	27
C_6H_5Br	bromobenzene	14.7	2
		13.62	27
C_6H_5Cl	chlorobenzene	14.1	2
		12.3	15
C_6H_5ClO	chlorophenol	13.0	2†
C_6H_5F	fluorobenzene	10.3	2
C_6H_5I	iodobenzene	15.5	2†
$C_6H_{11}ClO_2$	ethyl 2-chlorobutanoate	14.16	27
	ethyl 3-chlorobutanoate	14.13	27
	ethyl 4-chlorobutanoate	14.11	27
$C_6H_{13}Br$	bromohexane	14.44	27
$C_6H_{13}F$	fluorohexane	11.80	27
C_7H_7Br	*p*-bromotoluene	14.80	27
C_7H_7Cl	*p*-chlorotoluene	13.70	27
C_7H_7F	*p*-fluorotoluene	11.70	27
C_7H_7I	*p*-iodotoluene	17.10	27
$C_7H_{15}Br$	1-bromoheptane	16.8	2†
		16.23	27
$C_7H_{15}F$	fluoroheptane	13.66	27
$C_8H_{17}Br$	bromooctane	18.02	27
$C_8H_{17}F$	fluorooctane	15.46	27
$C_9H_{19}Br$	bromononane	19.81	27
$C_9H_{19}F$	fluorononane	17.34	27
$C_{10}F_8$	octafluoronaphthalene	17.64	27
$C_{10}H_7Br$	α-bromonaphthalene	20.34	27
$C_{10}H_7Cl$	α-chloronaphthalene	19.30	27
	β-chloronaphthalene	19.58	27
$C_{10}H_7I$	α-iodonaphthalene	22.41	27
	β-iodonaphthalene	22.95	27
$C_{10}H_{21}Br$	bromodecane	21.60	27
$C_{10}H_{21}F$	fluorodecane	19.18	27
$C_{11}H_{23}F$	fluoroundecane	21.00	27
$C_{12}H_{25}Br$	bromododecane	25.18	27
$C_{12}H_{25}F$	fluorododecane	22.83	27
$C_{12}H_8Br_2O$	4,4'-dibromodiphenyl ether	27.8	2†
$C_{12}H_9BrO$	4-bromodiphenyl ether	24.2	2†
$C_{13}H_{11}BrO$	*p*-bromophenyl-*p*-tolyl ether	26.6	2†
$C_{14}H_9Br$	9-bromoanthracene	28.32	27
$C_{14}H_9Cl$	9-chloroanthracene	27.35	27
$C_{14}H_9F$	fluoranthracene	28.34	27
$C_{14}H_{29}F$	fluorotetradecane	26.57	27
$C_{16}H_{33}Br$	bromohexadecane	32.34	27
$C_{18}H_{37}Br$	bromooctadecane	35.92	27

TABLE 8. Static Average Electric Dipole Polarizabilities for Other Ground State Organic Molecules (in Units of 10^{-24} cm^3)

Molecule	Name	Polarizability	Ref.
CN_4O_8	tetranitromethane	15.3	2
CH_2O	formaldehyde	2.8	2†
		2.45	18
CH_2O_2	formic acid	3.4	2†
CH_3NO	formamide	4.2	2†
		4.08	18
CH_3NO_2	nitromethane	7.37	2
CH_4O	methanol	3.29	2
		3.23	15
		3.32	18
CH_5N	methyl amine	4.7	2
		4.01	19
		4.01*	33
C_2N_2	cyanogen	7.99	2
C_2H_2O	ketene	4.4	2†
C_2H_3N	acetonitrile	4.40	2†
		4.48	18
C_2H_4O	acetaldehyde	4.6	2†
		4.59	18
	ethylene oxide	4.43	18
$C_2H_4O_2$	acetic acid	5.1	2†
	methyl formate	5.05	27
$C_2H_4O_4$	formic acid dimer	12.7	2
C_2H_5NO	acetamide	5.67	18
	N-methyl formamide	5.91	18
$C_2H_5NO_2$	nitroethane	9.63	2
	ethyl nitrite	7.0	15
C_2H_6O	ethanol	5.41	2
		5.11	18
	methyl ether	5.29	20
		5.84	2
		5.16	15
$C_2H_6O_2$	ethylene glycol	5.7	2†
		5.61	27
$C_2H_6O_2S$	dimethyl sulfone	7.3	2†
C_2H_6S	ethanethiol	7.41	2
C_2H_7N	ethyl amine	7.10	2
	dimethyl amine	6.37	2

Molecule	Name	Polarizability	Ref.
		5.90*	33
$C_2H_8N_2$	ethylene diamine	7.2	2†
$C_3H_2N_2$	malononitrile	5.79	18
C_3H_3N	acrylonitrile	8.05	2
$C_3H_4N_2$	pyrazole	7.23	27
C_3H_4O	propenal	6.38	2†
C_3H_5N	propionitrile	6.70	2
		6.24	18
		6.27*	32
C_3H_6O	acetone	6.33	15
		6.4	2†
		6.39	18
	allyl alcohol	7.65	2
	propionaldehyde	6.50	2
$C_3H_6O_2$	propionic acid	6.9	2†
	ethyl formate	8.01	2
		6.88	27
	methyl acetate	6.94	2
		6.81	27
$C_3H_6O_3$	dimethyl carbonate	7.7	2†
C_3H_7NO	*N*-methyl acetamide	7.82	18
	N,N-dimethyl formamide	7.81	18
$C_3H_7NO_2$	nitropropane	8.5	2†
C_3H_8O	2-propanol	7.61	2
		6.97	18
	1-propanol	6.74	2
	ethyl methyl ether	7.93	2
$C_3H_8O_2$	dimethoxymethane	7.7	2†
	ethylene glycol monomethyl ether	7.44	27
C_3H_9N	propylamine	7.70	27
		9.20	2
	isopropylamine	7.77	27
	trimethylamine	8.15	2
		7.78*	33
$C_4H_2N_2$	fumaronitrile	11.8	2
$C_4H_4N_2$	succinonitrile	8.1	2†
	pyrimidine	8.53*	17
	pyridazine	9.27*	17
$C_4H_4O_2$	diketene	8.0	2†
C_4H_4S	thiophene	9.67	2
C_4H_5N	methacrylonitrile	8.0	2†
	trans-crotononitrile	8.2	2†
$C_4H_6N_2$	*N*-methylpyrazole	8.99	27
C_4H_6O	crotonaldehyde	8.5	2†
	methacrylaldehyde	8.3	2†
$C_4H_6O_2$	biacetyl	8.2	2†
$C_4H_6O_3$	acetic anhydride	8.9	2†
C_4H_6S	divinyl sulfide	10.9	2†
C_4H_7N	butyronitrile	8.4	2†
	isobutyronitrile	8.05	18
		8.05*	32
C_4H_8O	butanal	8.2	2†
	methyl ethyl ketone	8.13	15
	trans-2,3-epoxy butane	8.22*	17
$C_4H_8O_2$	ethyl acetate	9.7	2
		8.62	27
	1,4-dioxane	10.0	2
	p-dioxane	8.60	18
	2-methyl-1,3-dioxolane	9.44	15
	butyric acid	8.58	27
	methyl propionate	8.97	27
$C_4H_9NO_2$	1-nitrobutane	10.4	2†
	2-methyl-2-nitropropane	10.3	2†
$C_4H_{10}O$	ethyl ether	10.2	2
		8.73	15
	1-butanol	8.88	2
	2-methylpropanol	8.92	2
	methyl propyl ether	8.86	27
	ethylene glycol monoethyl ether	9.28	27
$C_4H_{10}S$	ethyl sulfide	10.8	2
$C_4H_{11}N$	butylamine	13.5	2
	diethylamine	10.2	2
		9.61	27
C_5H_5N	pyridine	9.5	15
		9.18	27
	4-cyano-1,3-butadiene	10.5	2†
$C_5H_8N_2$	1,5-dimethylpyrazole	10.72	27
$C_5H_8O_2$	acetyl acetone	10.5	2†
C_5H_9N	valeronitrile	10.4	2
	22-DMPN	9.59	18
$C_5H_{10}O$	diethyl ketone	9.93	15
	methyl propyl ketone	9.93	15
$C_5H_{10}O_2$	ethyl propionate	10.41	27
	methyl butanoate	10.41	27
$C_5H_{10}O_3$	diethyl carbonate	11.3	2
$C_5H_{12}O$	ethyl propyl ether	10.68	27
$C_5H_{12}O_4$	tetramethyl orthocarbonate	13.0	2†
$C_6H_4N_2O_4$	*p*-dinitrobenzene	18.4	2
$C_6H_4O_2$	*p*-benzoquinone	14.5	2
$C_6H_5NO_2$	nitrobenzene	14.7	2
		12.92	15
C_6H_6O	phenol	11.1	2†
		9.94*	17
C_6H_7N	aniline	12.1	2†
$C_6H_8N_2$	phenylenediamine	13.8	2†
	phenylhydrazine	12.91	27
$C_6H_{10}N_2$	1-ethyl-5-methylpyrazole	12.50	27
$C_6H_{10}O_3$	ethyl acetoacetate	12.9	2†
$C_6H_{12}N_2$	dimethylketazine	15.6	2
$C_6H_{12}O$	cyclohexanol	11.56	18
$C_6H_{12}O_2$	amyl formate	14.2	2
$C_6H_{12}O_3$	paraldehyde	17.9	2
$C_6H_{14}O$	propyl ether	12.8	2
		12.5	15
$C_6H_{14}O_2$	1,1-diethoxyethane	13.2	2†
	1,2-diethoxyethane	11.3	2†
$C_6H_{15}N$	triethylamine	13.1	2
		13.38	27
	dipropylamine	13.29	27
$C_7H_4N_2O_2$	*p*-cyanonitrobenzene	19.0	2
C_7H_5N	benzonitrile	12.5	2†
$C_7H_7NO_3$	nitroanisole	15.7	2†
C_7H_8O	anisole	13.1	2†
C_7H_9NO	*o*-anisidine	14.2	2†
$C_7H_{10}N_2$	1,1-methylphenylhydrazine	14.81	27
$C_7H_{14}O$	cyclohexyl methyl ether	13.4	2†
	2,4-dimethyl-3-pentanone	13.5	15
$C_7H_{14}O_2$	pentyl acetate	14.9	2
$C_8H_4N_2$	*p*-dicyanobenzene	19.2	2
$C_8H_6N_2$	quinoxaline	15.13	27
C_8H_8O	acetophenone	15.0	2
$C_8H_8O_2$	2,5-dimethyl-1,4-benzoquinone	18.8	2
$C_8H_{10}O$	phenetole	14.9	2
$C_8H_{11}N$	*N*-dimethylaniline	16.2	2†
$C_8H_{12}N_2$	1,1-ethylphenylhydrazine	16.62	27
$C_8H_{12}O_2$	ethyl sorbate	17.2	2†

Molecule	Name	Polarizability	Ref.
	tetramethylcyclobutane-1,3-dione	18.6	2
$C_8H_{14}O_4$	diethyl succinate	16.8	2†
$C_8H_{18}O$	butyl ether	17.2	2
C_9H_7N	quinoline	15.70	27
	isoquinoline	16.43	27
$C_9H_{10}O_2$	ethyl benzoate	16.9	2†
$C_9H_{21}N$	tripropylamine	18.87	27
$C_{10}H_9N$	α-naphthylamine	19.50	27
	β-naphthylamine	19.73	27
	2-methylquinoline	18.65	27
	1-methylisoquinoline	18.28	27
$C_{10}H_{10}Fe$	ferrocene	17.1	26
$C_{10}H_{10}N_2$	2,3-dimethylquinoxaline	18.70	27
$C_{10}H_{14}BeO_4$	beryllium acetylacetonate	34.1	2
$C_{11}H_8O$	1-naphthaldehyde	19.75	27
	2-naphthaldehyde	20.06	27
$C_{12}H_8N_2$	phenazine	23.43	27
$C_{12}H_9NO_3$	4-nitrodiphenyl ether	24.7	2†
$C_{14}H_8O_2$	anthraquinone	24.46	27
$C_{14}H_{14}O$	di-*p*-tolyl ether	24.9	2†
$C_{15}H_{21}AlO_6$	aluminum acetylacetonate	51.9	2
$C_{15}H_{21}CrO_6$	chromium acetylacetonate	53.7	2
$C_{15}H_{21}FeO_6$	ferric acetylacetonate	58.1	2
$C_{20}H_{28}O_8Th$	thorium acetylacetonate	79.0	2
C_{60}	buckminsterfullerene	76.5	24
		79	31

Note: All polarizabilities in the tables are experimental values except those values marked by an asterisk (*), which indicates a calculated result. The experimental polarizabilities are mostly determined by measurements of a dielectric constant or refractive index which are quite accurate (0.5% or better). However, one should treat many of the results with several percent of caution because of the age of the data and because some of the results refer to optical frequencies rather than static. Comments given with the references are intended to allow one to judge the degree of caution required. Interested persons should consult these references. In many cases, the reference given is to a theoretical paper in which the experimental results are quoted. These papers, noted in the References, contain valuable information on polarizability calculations and experimental data which often includes the tensor components of the polarizability.

An emperical additive formula for molecular polarizabilities at 589 nm frequency has been given in Bosque, R., and Sales, J., *J. Chem. Inf. Comput. Sci. 42, 1154, 2002:* α=0.32 +1.51#C +0.17#H +0.57#O +1.05#N +2.99#S +2.48#P +2.16#Cl +3.29#Br +5.45#I, where "#C" denotes the number of carbon atoms in the molecule, etc.

References

Kagawa, H., Ichimura, A., Kamka, N. A., and Mori, K., J. Mol. Structure (Theochem) 546, 127, 2001. Parameters were developed for rapid estimation of molecular polarizabilities; this paper contains references for the measured polarizabilities of 371 molecules.

1. McCullough, E. A., Jr., *J. Chem. Phys.,* 63, 5050, 1975. This calculation is for the parallel component, not the average polarizability.
2. Maryott, A. A., and Buckley, F., *U. S. National Bureau of Standards Circular No. 537,* 1953. A tabulation of dipole moments, dielectric constants, and molar refractions measured between 1910 and 1952, and used here to determine polarizabilities if no more recent result exists. The polarizability is $3/(4\pi N_o)$ times the molar polarization or molar refraction, where N_o is Avogadro's number. The value $3/(4\pi N_o) = 0.3964308 \times 10^{-24}$ cm^3 was used for this conversion. A dagger (†) following the reference number in the tables indicates that the polarizability was derived from the molar refraction and hence may not include some low-frequency contributions to the static polarizability; these "static" polarizabilities are therefore low by 1 to 30%.
3. Hirschfelder, J. O., Curtis, C. F., and Bird, R. B., *Molecular Theory of Gases and Liquids,* Wiley, New York, 1954, p. 950. Fundamental information on molecular polarizabilities.
4. Miller, T. M., and Bederson, B., *Adv. At. Mol. Phys.,* 13, 1, 1977. Review emphasizing atomic polarizabilities and measurement techniques. The data quoted in Table 3 are accurate to 8 to 12%.
5. Kolos, W., and Wolniewicz, L., *J. Chem. Phys.,* 46, 1426, 1967. Highly accurate molecular hydrogen calculations. See also recent work by Machado, A.M., and Masilli, M., *J. Chem. Phys.* 120, 7505, 2004.
6. Newell, A. C., and Baird, R. C., *J. Appl. Phys.,* 36, 3751, 1965. Highly accurate refractive index measurements at 47.7 GHz (essentially static).
7. Jao, T. C., Beebe, N. H. F., Person, W. B., and Sabin, J. R., *Chem. Phys. Lett.*, 26, 474, 1974. Tensor polarizabilities, derivatives, and other results are reported.
8. Orcutt, R. H., and Cole, R. H., *J. Chem. Phys.,* 46, 697, 1967 (He, Ne, Ar, Kr, H_2, N_2); Sutter, H., and Cole, R. H., *J. Chem. Phys.,* 52, 132, 1970 (CF_3H, CFH_3, $CClF_3$, $CClH_3$); Bose, T. K., and Cole, R. H., *J. Chem. Phys.,* 52, 140, 1970 (CO_2), and 54, 3829, 1971 (C_2H_4); Nelson, R. D., and Cole, R. H., *J. Chem. Phys.,* 54, 4033, 1971 (SF_6, $CClF_3$); Bose, T. K., Sochanski, J. S., and Cole, R. H., *J. Chem. Phys.*, 57, 3592, 1972 (CH_4, CF_4); Kirouac, S., and Bose, T. K., *J. Chem. Phys.*, 59, 3043, 1973 (N_2O), and 64, 1580, 1976 (He). Highly accurate dielectric constant measurements. These modern data give the most accurate polarizabilities available. A criticism of the interpretation of these data in the case of polar molecules is given in Ref. 20, p. 2905.
9. Huestis, D. L., Technical Report #MP 78-25, SRI International (project PYU 6158), Menlo Park, CA 94025. Molar refractions for mercury-chlorine compounds are analyzed.
10. Bounds, D. G., Clarke, J. H. R., and Hinchliffe, A., *Chem. Phys. Lett.*, 45, 367, 1977. Theoretical tensor polarizability for LiCl.
11. Kolker, H. J., and Karplus, M., *J. Chem. Phys.,* 39, 2011, 1963. Theoretical.
12. Cutschick, V. P., and McKoy, V., *J. Chem. Phys.,* 58, 2397, 1973. Theoretical tensor polarizabilities.
13. Gready, J. E., Bacskay, G. B., and Hush, N. S., *Chem. Phys.,* 22, 141, 1977, and 23, 9, 1977. Theoretical.
14. Amos, A. T., and Yoffe, J. A., *J. Chem. Phys.,* 63, 4723, 1975. Theoretical.
15. Stuart, H. A., *Landolt-Börnstein Zahlenwerte and Funktionen,* Vol. 1, Part 3, Eucken, A., and Hellwege, K. H., Eds., Springer-Verlag, Berlin, 1951, p. 511. Tabulation of molecular polarizabilities. Two misprints in the chemical symbols have been corrected.
16. Guella, T., Miller, T. M., Stockdale, J. A. D., Bederson, B., and Vuskovic, L., *J. Chem. Phys.,* 94, 6857, 1991. Beam measurements with accuracies between 12-24%.
17. Marchese, F. T., and Jaff, H. H., *Theoret. Chim. Acta* (Berlin), 45, 241, 1977. Theoretical and experimental tensor polarizabilities are tabulated in this paper.
18. Applequist, J., Carl, J. R., and Fung, K.-K., *J. Am. Chem. Soc.*, 94, 2952, 1972. Excellent reference on the calculation of molecular polarizabilities, including extensive tables of tensor polarizabilities, both theoretical and experimental, at 589.3 nm wavelength.
19. Bridge, N. J., and Buckingham, A. D., *Proc. Roy. Soc.* (London), A295, 334, 1966. Measured tensor polarizabilities at 633 nm wavelength.
20. Barnes, A. N. M., Turner, D. J., and Sutton, L. E., *Trans. Faraday Soc.,* 67, 2902, 1971. Dielectric constants yielding polarizabilities accurate from 0.3-8%.
21. Knight, W. D., Clemenger, K., de Heer, W. A., and Saunders, W. A., *Phys. Rev. B*, 31, 2539, 1985. These data probably correspond to a very low internal temperature.
22. Tarnovsky, V., Bunimovicz, M., Vuskovic, L., Stumpf, B., and Bederson, B., *J. Chem. Phys.,* 98, 3894, 1993. These data correspond to internal temperatures 480-948 K.
23. Milani, P., Moullet, I., and de Heer, W. A., *Phys. Rev. A*, 42, 5150, 1990. Beam measurements accurate to 11%.
24. Antoine, R., Dugourd, P., Rayane, D., Benichou, E., Broyer, M., Chandezon, F., and Guet, C., *J. Chem. Phys.*, 110, 9771, 1999.

25. Aroney, M. J., and Pratten, S. J., *J. Chem. Soc., Faraday Trans.,* 1, 80, 1201, 1984. Uncertainties in the range 1-3%.
26. Le Fevre, R. J. W., Murthy, D. S. N., and Saxby, J. D., *Aust. J. Chem.,* 24, 1057, 1971. Kerr effect.
27. No, K. T., Cho, K. H., Jhon, M. S., and Scheraga, H. A., J. Am. Chem. Soc., 115, 2005, 1993. Theoretical; these results are quoted in numerous valuable papers on calculated polarizabilities, e.g., Miller, K. J., and Savchik, J. A., *J. Am. Chem. Soc.,* 101, 7206, 1979.
28. Schlecht, S., Schäfer, R., Woenckhaus, J., Becker, J. A., *Chem. Phys. Lett.,* 246, 315, 1995.
29. Benichou, E., Antoine, R., Rayane, D., Vezin, B., Dalby, F. W., Dugourd, P., Ristori, C., Chandezon, F., Huber, B. A., Rocco, J. C., Blundell, S. A., and Guet, C., *Phys. Rev. A* 59, R1, 1999.
30. Antoine, R., Rayane, D., Allouche, A. R., Aubert-Frécon, M., Benichou, E., Dalby, F. W., Dugourd, P., Broyer, M., and Guet, C., *J. Chem. Phys.,* 110, 5568, 1999.
31. Ballard, A., Bonin, K., and Louderback, J., *J. Chem. Phys.* 113, 5732, 2000.
32. Ritchie, G.L.D., and Watson, J.N., *J. Phys. Chem. A* 108, 4515, 2004. These measurements are at 632.8 nm frequency, and are stated accurate to 0.4%.
33. Ritchie, G.L.D., and Blanch, E.W., *J. Phys. Chem. A* 107, 2093, 2003. These measurements are at 632.8 nm frequncy, and are stated accurate to better than 1%.

IONIZATION ENERGIES OF ATOMS AND ATOMIC IONS

The ionization energies (often called ionization potentials) of neutral and partially ionized atoms are listed in this table. Data were obtained from the compilations cited below, supplemented by results from the recent research literature. Values for the first and second ionization energies come from Reference 6. All values are given in electron volts (eV).

Following the traditional spectroscopic notation, columns are headed I, II, III, etc. up to XXX, where I indicates the neutral atom, II the singly ionized atom, III the doubly ionized atom, etc. The first section of the table includes spectra I to VIII of all the elements through rutherfordium; subsequent sections cover higher spectra (ionization stages) for those elements for which data are available.

References

1. Moore, C. E., *Ionization Potentials and Ionization Limits Derived from the Analysis of Optical Spectra,* Natl. Stand. Ref. Data Ser. — Natl. Bur. Stand. (U.S.) No. 34, 1970.
2. Martin, W. C., Zalubas, R., and Hagan, L., *Atomic Energy Levels — The Rare Earth Elements,* Natl. Stand. Ref. Data Ser. — Natl. Bur. Stand. (U.S.), No. 60, 1978.
3. Sugar, J. and Corliss, C., *Atomic Energy Levels of the Iron Period Elements: Potassium through Nickel, J. Phys. Chem. Ref. Data,* Vol.14, Suppl. 2, 1985.
4. References to papers in *J. Phys. Chem. Ref. Data,* in the period 1973—91 covering other elements may be found in the cumulative index to that journal.
5. Martin, W.C., and Wiese, W.L., in *Atomic, Molecular, and Optical Physics Handbook,* Drake, G.W.F., Ed., AIP Press, New York, 1996.
6. Sansonetti, J. E., Martin, W. C., and Young, S. L., Handbook of Basic Atomic Spectroscopic Data (version 1.1), NIST Physical Data web site <http://physics.nist.gov/PhysRefData/Handbook> (October 2004); *J. Phys. Chem. Ref. Data* (to be published).

Neutral Atoms to +7 Ions

Z	Element	I	II	III	IV	V	VI	VII	VIII
1	H	13.598443							
2	He	24.587387	54.417760						
3	Li	5.391719	75.6400	122.45429					
4	Be	9.32270	18.21114	153.89661	217.71865				
5	B	8.29802	25.1548	37.93064	259.37521	340.22580			
6	C	11.26030	24.3833	47.8878	64.4939	392.087	489.99334		
7	N	14.5341	29.6013	47.44924	77.4735	97.8902	552.0718	667.046	
8	O	13.61805	35.1211	54.9355	77.41353	113.8990	138.1197	739.29	871.4101
9	F	17.4228	34.9708	62.7084	87.1398	114.2428	157.1651	185.186	953.9112
10	Ne	21.56454	40.96296	63.45	97.12	126.21	157.93	207.2759	239.0989
11	Na	5.139076	47.2864	71.6200	98.91	138.40	172.18	208.50	264.25
12	Mg	7.646235	15.03527	80.1437	109.2655	141.27	186.76	225.02	265.96
13	Al	5.985768	18.82855	28.44765	119.992	153.825	190.49	241.76	284.66
14	Si	8.15168	16.34584	33.49302	45.14181	166.767	205.27	246.5	303.54
15	P	10.48669	19.7695	30.2027	51.4439	65.0251	220.421	263.57	309.60
16	S	10.36001	23.33788	34.79	47.222	72.5945	88.0530	280.948	328.75
17	Cl	12.96763	23.8136	39.61	53.4652	67.8	97.03	114.1958	348.28
18	Ar	15.759610	27.62966	40.74	59.81	75.02	91.009	124.323	143.460
19	K	4.3406633	31.63	45.806	60.91	82.66	99.4	117.56	154.88
20	Ca	6.11316	11.87172	50.9131	67.27	84.50	108.78	127.2	147.24
21	Sc	6.56149	12.79977	24.75666	73.4894	91.65	110.68	138.0	158.1
22	Ti	6.82812	13.5755	27.4917	43.2672	99.30	119.53	140.8	170.4
23	V	6.74619	14.618	29.311	46.709	65.2817	128.13	150.6	173.4
24	Cr	6.76651	16.4857	30.96	49.16	69.46	90.6349	160.18	184.7
25	Mn	7.43402	15.6400	33.668	51.2	72.4	95.6	119.203	194.5
26	Fe	7.9024	16.1877	30.652	54.8	75.0	99.1	124.98	151.06
27	Co	7.88101	17.084	33.50	51.3	79.5	102.0	128.9	157.8
28	Ni	7.6398	18.16884	35.19	54.9	76.06	108	133	162
29	Cu	7.72638	20.2924	36.841	57.38	79.8	103	139	166
30	Zn	9.394199	17.96439	39.723	59.4	82.6	108	134	174
31	Ga	5.999301	20.51514	30.71	64				
32	Ge	7.89943	15.93461	34.2241	45.7131	93.5			
33	As	9.7886	18.5892	28.351	50.13	62.63	127.6		
34	Se	9.75239	21.19	30.8204	42.9450	68.3	81.7	155.4	
35	Br	11.8138	21.591	36	47.3	59.7	88.6	103.0	192.8
36	Kr	13.99961	24.35984	36.950	52.5	64.7	78.5	111.0	125.802
37	Rb	4.177128	27.2895	40	52.6	71.0	84.4	99.2	136
38	Sr	5.69485	11.0301	42.89	57	71.6	90.8	106	122.3
39	Y	6.2173	12.224	20.52	60.597	77.0	93.0	116	129
40	Zr	6.63390	13.1	22.99	34.34	80.348			
41	Nb	6.75885	14.0	25.04	38.3	50.55	102.057	125	

Neutral Atoms to +7 Ions

Z	Element	I	II	III	IV	V	VI	VII	VIII
42	Mo	7.09243	16.16	27.13	46.4	54.49	68.8276	125.664	143.6
43	Tc	7.28	15.26	29.54					
44	Ru	7.36050	16.76	28.47					
45	Rh	7.45890	18.08	31.06					
46	Pd	8.3369	19.43	32.93					
47	Ag	7.57623	21.47746	34.83					
48	Cd	8.99382	16.90831	37.48					
49	In	5.78636	18.8703	28.03	54				
50	Sn	7.34392	14.6322	30.50260	40.73502	72.28			
51	Sb	8.60839	16.63	25.3	44.2	56	108		
52	Te	9.0096	18.6	27.96	37.41	58.75	70.7	137	
53	I	10.45126	19.1313	33					
54	Xe	12.12984	20.9750	32.1230					
55	Cs	3.893905	23.15744						
56	Ba	5.211664	10.00383						
57	La	5.5769	11.059	19.1773	49.95	61.6			
58	Ce	5.5387	10.85	20.198	36.758	65.55	77.6		
59	Pr	5.473	10.55	21.624	38.98	57.53			
60	Nd	5.5250	10.72	22.1	40.4				
61	Pm	5.582	10.90	22.3	41.1				
62	Sm	5.6437	11.07	23.4	41.4				
63	Eu	5.67038	11.25	24.92	42.7				
64	Gd	6.14980	12.09	20.63	44.0				
65	Tb	5.8638	11.52	21.91	39.79				
66	Dy	5.9389	11.67	22.8	41.47				
67	Ho	6.0215	11.80	22.84	42.5				
68	Er	6.1077	11.93	22.74	42.7				
69	Tm	6.18431	12.05	23.68	42.7				
70	Yb	6.25416	12.176	25.05	43.56				
71	Lu	5.42586	13.9	20.9594	45.25	66.8			
72	Hf	6.82507	15	23.3	33.33				
73	Ta	7.54957							
74	W	7.86403	16.1						
75	Re	7.83352							
76	Os	8.43823							
77	Ir	8.96702							
78	Pt	8.9588	18.563						
79	Au	9.22553	20.20						
80	Hg	10.4375	18.7568	34.2					
81	Tl	6.108194	20.4283	29.83					
82	Pb	7.41663	15.03248	31.9373	42.32	68.8			
83	Bi	7.2855	16.703	25.56	45.3	56.0	88.3		
84	Po	8.414							
85	At								
86	Rn	10.7485							
87	Fr	4.072741							
88	Ra	5.278423	10.14715						
89	Ac	5.17	11.75						
90	Th	6.3067	11.9	20.0	28.8				
91	Pa	5.89							
92	U	6.1941	10.6						
93	Np	6.2657							
94	Pu	6.0260	11.2						
95	Am	5.9738							
96	Cm	5.9914							
97	Bk	6.1979							
98	Cf	6.2817	11.8						
99	Es	6.42	12.0						
100	Fm	6.50							
101	Md	6.58							
102	No	6.65							
103	Lr	4.9							
104	Rf	6.0							

+8 Ions to +15 Ions

Z	Element	IX	X	XI	XII	XIII	XIV	XV	XVI
9	F	1103.1176							
10	Ne	1195.8286	1362.1995						
11	Na	299.864	1465.121	1648.702					
12	Mg	328.06	367.50	1761.805	1962.6650				
13	Al	330.13	398.75	442.00	2085.98	2304.1410			
14	Si	351.12	401.37	476.36	523.42	2437.63	2673.182		
15	P	372.13	424.4	479.46	560.8	611.74	2816.91	3069.842	
16	S	379.55	447.5	504.8	564.44	652.2	707.01	3223.78	3494.1892
17	Cl	400.06	455.63	529.28	591.99	656.71	749.76	809.40	3658.521
18	Ar	422.45	478.69	538.96	618.26	686.10	755.74	854.77	918.03
19	K	175.8174	503.8	564.7	629.4	714.6	786.6	861.1	968
20	Ca	188.54	211.275	591.9	657.2	726.6	817.6	894.5	974
21	Sc	180.03	225.18	249.798	687.36	756.7	830.8	927.5	1009
22	Ti	192.1	215.92	265.07	291.500	787.84	863.1	941.9	1044
23	V	205.8	230.5	255.7	308.1	336.277	896.0	976	1060
24	Cr	209.3	244.4	270.8	298.0	354.8	384.168	1010.6	1097
25	Mn	221.8	248.3	286.0	314.4	343.6	403.0	435.163	1134.7
26	Fe	233.6	262.1	290.2	330.8	361.0	392.2	457	489.256
27	Co	186.13	275.4	305	336	379	411	444	511.96
28	Ni	193	224.6	321.0	352	384	430	464	499
29	Cu	199	232	265.3	369	401	435	484	520
30	Zn	203	238	274	310.8	419.7	454	490	542
36	Kr	230.85	268.2	308	350	391	447	492	541
37	Rb	150	277.1						
38	Sr	162	177	324.1					
39	Y	146.2	191	206	374.0				
42	Mo	164.12	186.4	209.3	230.28	279.1	302.60	544.0	570

+16 Ions to +23 Ions

Z	Element	XVII	XVIII	XIX	XX	XXI	XXII	XXIII	XXIV
17	Cl	3946.2960							
18	Ar	4120.8857	4426.2296						
19	K	1033.4	4610.8	4934.046					
20	Ca	1087	1157.8	5128.8	5469.864				
21	Sc	1094	1213	1287.97	5674.8	6033.712			
22	Ti	1131	1221	1346	1425.4	6249.0	6625.82		
23	V	1168	1260	1355	1486	1569.6	6851.3	7246.12	
24	Cr	1185	1299	1396	1496	1634	1721.4	7481.7	7894.81
25	Mn	1224	1317	1437	1539	1644	1788	1879.9	8140.6
26	Fe	1266	1358	1456	1582	1689	1799	1950	2023
27	Co	546.58	1397.2	1504.6	1603	1735	1846	1962	2119
28	Ni	571.08	607.06	1541	1648	1756	1894	2011	2131
29	Cu	557	633	670.588	1697	1804	1916	2060	2182
30	Zn	579	619	698	738	1856			
36	Kr	592	641	786	833	884	937	998	1051
42	Mo	636	702	767	833	902	968	1020	1082

+24 Ions to +29 Ions

Z	Element	XXV	XXVI	XXVII	XXVIII	XXIX	XXX
25	Mn	8571.94					
26	Fe	8828	9277.69				
27	Co	2219.0	9544.1	10012.12			
28	Ni	2295	2399.2	10288.8	10775.40		
29	Cu	2308	2478	2587.5	11062.38	11567.617	
36	Kr	1151	1205.3	2928	3070	3227	3381
42	Mo	1263	1323	1387	1449	1535	1601

IONIZATION ENERGIES OF GAS-PHASE MOLECULES

Sharon G. Lias

This table presents values for the first ionization energies (IP) of approximately 1000 molecules and atoms. Substances are listed by molecular formula in the modified Hill order (see Preface). Values enclosed in parentheses are considered not to be well established. Data appearing in the 1988 reference, were updated in 1996 for inclusion in the database of ionization energies available at the Internet site of the Standard Reference Data program of the National Institute of Standards and Technology (http://webbook.nist.gov). The list appearing here includes these updates.

The list also includes values for enthalpies of formation of the ions at 298 K, $\Delta_f H_{ion}$, given according to the ion convention used by mass spectrometrists; to convert these values to the electron convention used by thermodynamicists, add 6 kJ/mol. Details on the calculation of $\Delta_f H_{ion}$, as well as data for a much larger number of molecules, may be found in the reference and on the Internet site.

Reference

Lias, S. G., Bartmess, J. E., Liebman, J. F., Holmes, J. L., Levin, R. D., and Mallard, W.G., *Gas-Phase Ion and Neutral Thermochemistry, J. Phys. Chem. Ref. Data*, Vol. 17, Suppl. No. 1, 1988.

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
Substances not containing carbon			
Ac	Actinium	5.17	905
Ag	Silver	7.57624	1016
AgCl	Silver(I) chloride	(≤ 10.08)	≤ 1065
AgF	Silver(I) fluoride	(11.0 ± 0.3)	1071
Al	Aluminum	5.98577	905
AlBr	Aluminum monobromide	(9.3)	913
$AlBr_3$	Aluminum tribromide	(10.4)	593
AlCl	Aluminum monochloride	9.4	855
$AlCl_3$	Aluminum trichloride	(12.01)	573
AlF	Aluminum monofluoride	9.73 ± 0.01	673
AlF_3	Aluminum trifluoride	≤ 15.45	≤ 282
AlI	Aluminum monoiodide	9.3 ± 0.3	965
AlI_3	Aluminum triiodide	(9.1)	673
Am	Americium	5.9738 ± 0.0002	860
Ar	Argon	15.75962	1521
As	Arsenic	9.8152	1250
$AsCl_3$	Arsenic(III) chloride	(10.55 ± 0.025)	754
AsF_3	Arsenic(III) fluoride	(12.84 ± 0.05)	452
AsH_3	Arsine	(9.89)	1021
Au	Gold	9.22567	1254
B	Boron	8.29803	1363
BBr_3	Boron tribromide	(10.51)	809
BCl_3	Boron trichloride	11.60 ± 0.02	718
BF	Fluoroborane	11.12 ± 0.01	957
	Difluoroborane	(9.4)	317
BF_3	Boron trifluoride	15.7 ± 0.3	365
BH	Boron monohydride	(9.77)	1385
BH_3	Borane	12.026 ± 0.024	1261
BI_3	Boron triiodide	(9.25 ± 0.03)	964
BO_2	Boron dioxide	(13.5 ± 0.3)	1001
B_2H_6	Diborane	11.38 ± 0.05	1134
B_2O_3	Boron oxide	13.5 ± 0.15	460
B_4H_{10}	Tetraborane	10.76 ± 0.04	1105
B_5H_9	Pentaborane(9)	9.90 ± 0.04	1028
B_6H_{10}	Hexaborane	(9.0)	965
Ba	Barium	5.21170	683
BaO	Barium oxide	6.91 ± 0.06	543
Be	Beryllium	9.32263	1224
BeO	Beryllium oxide	(10.1 ± 0.4)	1111
Bi	Bismuth	7.2855	908
$BiCl_3$	Bismuth trichloride	(10.4)	736

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
Bk	Berkelium	6.23	911
Br	Bromine (atomic)	11.81381	1252
BrCl	Bromine chloride	11.01	1079
BrF	Bromine fluoride	11.86	1086
BrF_5	Bromine pentafluoride	13.172 ± 0.002	840
BrH	Hydrogen bromide	11.66 ± 0.03	1087
BrH_3Si	Bromosilane	10.6	943
BrI	Iodine bromide	9.790 ± 0.004	986
BrK	Potassium bromide	7.85 ± 0.1	578
BrLi	Lithium bromide	(8.7)	685
BrNO	Nitrosyl bromide	10.17 ± 0.03	1065
BrNa	Sodium bromide	8.31 ± 0.1	660
BrO	Bromine monoxide	10.46 ± 0.02	1135
BrRb	Rubidium bromide	7.94 ± 0.03	583
BrTl	Thallium(I) bromide	9.14 ± 0.02	844
Br_2	Bromine	10.516 ± 0.005	1046
Br_2Hg	Mercury(II) bromide	10.560 ± 0.003	935
Br_2Sn	Tin(II) bromide	9.0	839
Br_3Ga	Gallium(III) bromide	10.40	711
Br_3P	Phosphorus(III) bromide	9.7	798
Br_4Hf	Hafnium(IV) bromide	(10.9)	366
Br_4Sn	Tin(IV) bromide	10.6	709
Br_4Ti	Titanium(IV) bromide	10.3	375
Br_4Zr	Zirconium(IV) bromide	(10.7)	388
Ca	Calcium	6.11316	768
CaCl	Calcium monochloride	5.86 ± 0.07	462
CaO	Calcium oxide	6.66 ± 0.18	668
Cd	Cadmium	8.99367	980
Ce	Cerium	5.5387	957
Cf	Californium	6.30	805
Cl	Chlorine (atomic)	12.96764	1373
ClCs	Cesium chloride	(7.84 ± 0.05)	510
ClF	Chlorine fluoride	12.66 ± 0.01	1171
$ClFO_3$	Perchloryl fluoride	(12.945 ± 0.005)	1224
ClF_2	Chlorine difluoride	(12.77 ± 0.05)	1128
ClF_3	Chlorine trifluoride	(12.65 ± 0.05)	1057
ClF_5S	Sulfur chloride pentafluoride	(12.335 ± 0.005)	144
ClH	Hydrogen chloride	12.749 ± 0.009	1137
ClHO	Hypochlorous acid	(11.12 ± 0.01)	993
ClH_3Si	Chlorosilane	11.4	899
ClI	Iodine chloride	10.088 ± 0.01	991
ClIn	Indium(I) chloride	(9.51)	842
ClK	Potassium chloride	(8.0 ± 0.4)	557
ClLi	Lithium chloride	9.57	727
ClNO	Nitrosyl chloride	10.87 ± 0.01	1099
$ClNO_2$	Nitryl chloride	(11.84)	1155
ClNa	Sodium chloride	8.92 ± 0.06	681
ClO	Chlorine monoxide	10.95	1159
ClO_2	Chlorine dioxide	10.33 ± 0.02	1093
ClRb	Rubidium chloride	(8.50 ± 0.03)	590
ClTl	Thallium(I) chloride	9.70 ± 0.03	869
Cl_2	Chlorine	11.480 ± 0.005	1108
Cl_2CrO_2	Chromyl chloride	11.6	580
Cl_2Ge	Germanium(II) chloride	(10.20 ± 0.05)	813
Cl_2H_2Si	Dichlorosilane	11.4	765
Cl_2Hg	Mercury(II) chloride	11.380 ± 0.003	952
Cl_2O	Chlorine oxide	10.94	1135
Cl_2OS	Thionyl chloride	10.96	844
Cl_2O_2S	Sulfuryl chloride	12.05	807
Cl_2Pb	Lead(II) chloride	(10.2)	791

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
Cl_2S	Sulfur dichloride	9.45 ± 0.03	895
Cl_2Si	Dichlorosilylene	(10.93 ± 0.10)	887
Cl_2Sn	Tin(II) chloride	(10.0)	760
Cl_3Ga	Gallium(III) chloride	11.52	664
Cl_3HSi	Trichlorosilane	(11.7)	648
Cl_3N	Nitrogen trichloride	(10.12 ± 0.1)	1244
Cl_3OP	Phosphorus(V) oxychloride	11.36 ± 0.02	540
Cl_3OV	Vanadyl trichloride	(11.6)	425
Cl_3P	Phosphorus(III) chloride	9.91	668
Cl_3PS	Phosphorus(V) sulfide trichloride	9.71 ± 0.03	573
Cl_3Sb	Antimony(III) chloride	(≤ 10.7)	s719
Cl_4Ge	Germanium(IV) chloride	11.68 ± 0.05	629
Cl_4Hf	Hafnium(IV) chloride	(11.7)	246
Cl_4Si	Tetrachlorosilane	11.79 ± 0.01	527
Cl_4Sn	Tin(IV) chloride	11.7 ± 0.2	656
Cl_4Ti	Titanium(IV) chloride	(11.5)	349
Cl_4V	Vanadium(IV) chloride	(9.2)	361
Cl_4Zr	Zirconium(IV) chloride	(11.2)	210
Cl_5Mo	Molybdenum(V) chloride	(8.7)	392
Cl_5Nb	Niobium(V) chloride	(10.97)	356
Cl_5P	Phosphorus(V) chloride	(10.2)	608
Cl_5Ta	Tantalum(V) chloride	(11.08)	303
Cl_6W	Tungsten(VI) chloride	(9.5)	348
Cm	Curium	6.02	966
Co	Cobalt	7.8810	1187
Cr	Chromium	6.76664	1050
Cs	Cesium	3.89390	452
CsF	Cesium fluoride	(8.80 ± 0.10)	489
CsNa	Cesium sodium	(4.05 ± 0.04)	535
Cu	Copper	7.72638	1084
CuF	Copper(I) fluoride	10.15 ± 0.02	984
Dy	Dysprosium	5.9389	862
Er	Erbium	6.1078	907
Es	Einsteinium	6.42	753
Eu	Europium	5.6704	723
F	Fluorine (atomic)	17.42282	1761
FGa	Gallium monofluoride	(9.6 ± 0.5)	700
FH	Hydrogen fluoride	16.044 ± 0.003	1276
FHO	Hypofluorous acid	12.71 ± 0.01	1130
FH_3Si	Fluorosilane	11.7	752
FI	Iodine fluoride	10.54 ± 0.01	922
FIn	Indium monofluoride	(9.6 ± 0.5)	740
FNO	Nitrosyl fluoride	12.63 ± 0.03	1152
FNO_2	Nitryl fluoride	(13.09)	1154
FNS	Thionitrosyl fluoride (NSF)	11.51 ± 0.04	1090
FO	Fluorine monoxide	12.78 ± 0.03	1342
FO_2	Fluorine superoxide (FOO)	(12.6 ± 0.2)	1228
FS	Sulfur fluoride	10.09	986
FTl	Thallium(I) fluoride	10.52	835
F_2	Fluorine	15.697 ± 0.003	1515
F_2Ge	Germanium(II) fluoride	(≤ 11.65)	551
F_2HN	Difluoramine	(11.53 ± 0.08)	1046
F_2H_2Si	Difluorosilane	(12.2)	386
F_2Mg	Magnesium fluoride	(13.6 ± 0.3)	588
F_2N	Difluoroamidogen	11.628 ± 0.01	1155
F_2N_2	*trans*-Difluorodiazine	(12.8)	1315
F_2O	Fluorine monoxide	13.11 ± 0.01	1290
F_2OS	Thionyl fluoride	12.25	688
F_2O_2S	Sulfuryl fluoride	13.04 ± 0.01	501
F_2Pb	Lead(II) fluoride	(11.5)	679

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
F_2S	Sulfur difluoride	(10.08)	676
F_2Si	Difluorosilylene	10.78 ± 0.05	450
F_2Sn	Tin(II) fluoride	(11.1)	586
F_2Xe	Xenon difluoride	12.35 ± 0.01	1083
F_3HSi	Trifluorosilane	(14.0)	150
F_3N	Nitrogen trifluoride	13.00 ± 0.02	1125
F_3NO	Trifluoramine oxide	13.31 ± 0.06	1121
F_3OP	Phosphorus(V) oxyfluoride	12.76 ± 0.01	−24
F_3P	Phosphorus(III) fluoride	11.60 ± 0.05	161
F_3PS	Phosphorus(V) sulfide trifluoride	≤ 11.05 ± 0.035	≤ 58
F_3Si	Trifluorosilyl	(9.99)	− 32
F_4Ge	Germanium(IV) fluoride	(15.5)	307
F_4N_2	Tetrafluorohydrazine	11.94 ± 0.03	1119
F_4S	Sulfur tetrafluoride	12.0 ± 0.3	399
F_4Si	Tetrafluorosilane	15.24 ± 0.14	−144
F_4Xe	Xenon tetrafluoride	12.65 ± 0.1	1016
F_5I	Iodine pentafluoride	12.943 ± 0.005	408
F_5P	Phosphorus(V) fluoride	(15.1)	−137
F_5S	Sulfur pentafluoride	9.60 ± 0.05	10
F_6Mo	Molybdenum(VI) fluoride	(14.5 ± 0.1)	−159
F_6S	Sulfur hexafluoride	15.32 ± 0.02	258
F_6U	Uranium(VI) fluoride	14.00 ± 0.10	−796
Fe	Iron	7.9024	1177
Fm	Fermium	6.50	627
Ga	Gallium	5.99930	851
GaI_3	Gallium(III) iodide	9.40	765
Gd	Gadolinium	6.1500	991
Ge	Germanium	7.900	1139
GeH_4	Germane	≤ 10.53	≤ 1108
GeI_4	Germanium(IV) iodide	(9.42)	850
GeO	Germanium(II) oxide	11.25 ± 0.01	1044
GeS	Germanium(II) sulfide	(9.98)	1055
H	Hydrogen (atomic)	13.59844	1530
HI	Hydrogen iodide	10.386 ± 0.001	1028
HLi	Lithium hydride	7.7	882
HN	Imidogen	≤ 13.49 ± 0.01	1678
HNO	Nitrosyl hydride	(10.1)	1075
HNO_2	Nitrous acid	≤ 11.3	≤ 1011
HNO_3	Nitric acid	11.95 ± 0.01	1019
HN_3	Hydrazoic acid	10.72 ± 0.025	1328
HO	Hydroxyl	13.0170 ± 0.0002	1294
HO_2	Hydroperoxy	11.35 ± 0.01	1106
HS	Mercapto	10.4219 ± 0.0004	1145
H_2	Hydrogen	15.42593 ± 0.00005	1488
H_2N	Amidogen	11.14 ± 0.01	1264
H_2O	Water	12.6206 ± 0.0020	976
H_2O_2	Hydrogen peroxide	10.58 ± 0.04	885
H_2S	Hydrogen sulfide	10.457 ± 0.012	989
H_2Se	Hydrogen selenide	9.892 ± 0.005	984
H_2Si	Silylene	8.244 ± 0.025	1084
H_3N	Ammonia	10.070 ± 0.020	925
H_3NO	Hydroxylamine	(10.00)	923
H_3P	Phosphine	9.869 ± 0.002	958
H_3Sb	Stibine	9.54 ± 0.03	1067
H_4N_2	Hydrazine	8.1 ± 0.15	877
H_4Si	Silane	11.00 ± 0.02	1095
H_4Sn	Stannane	(10.75)	1200
H_6Si_2	Disilane	9.74 ± 0.02	1019
H_8Si_3	Trisilane	(9.2)	1009
He	Helium	24.58741	2372

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
Hf	Hafnium	6.82507 ± 0.00004	1278
Hg	Mercury	10.43750	1069
HgI_2	Mercury(II) iodide	9.5088 ± 0.0022	900
Ho	Holmium	6.0216	882
I	Iodine (atomic)	10.45126	1115
IK	Potassium iodide	(7.21 ± 0.3)	570
ILi	Lithium iodide	(7.5)	633
INa	Sodium iodide	7.64 ± 0.02	659
ITl	Thallium(I) iodide	8.47 ± 0.02	826
I_2	Iodine	9.3074 ± 0.0002	960
I_4Ti	Titanium(IV) iodide	(9.1)	602
I_4Zr	Zirconium(IV) iodide	(9.3)	500
In	Indium	5.78636	802
Ir	Iridium	9.1	1543
K	Potassium	4.34066	508
KLi	Lithium potassium	4.57 ± 0.04	512
KNa	Potassium sodium	4.41636 ± 0.00017	561
K_2	Dipotassium	4.0637 ± 0.0002	519
Kr	Krypton	13.99961	1351
La	Lanthanum	5.5770	969
Li	Lithium	5.39172	680
LiNa	Lithium sodium	5.05 ± 0.04	571
LiO	Lithium monoxide	(8.44)	894
LiRb	Lithium rubidium	4.3 ± 0.1	486
Li_2	Dilithium	5.1127 ± 0.0003	709
Lu	Lutetium	5.42585	950
Md	Mendelevium	6.58	635
Mg	Magnesium	7.64624	885
MgO	Magnesium oxide	(8.76 ± 0.22)	901
Mn	Manganese	7.43402	998
Mo	Molybdenum	7.09243	1343
N	Nitrogen (atomic)	14.53414	1875
NO	Nitric oxide	9.26438 ± 0.00005	985
NO_2	Nitrogen dioxide	9.586 ± 0.002	958
NP	Phosphorus nitride	11.84 ± 0.04	1247
NS	Nitrogen sulfide	8.87 ± 0.01	1119
N_2	Nitrogen	15.5808	1503
N_2O	Nitrous oxide	12.886	1325
N_2O_4	Nitrogen tetroxide	(10.8)	1050
N_2O_5	Nitrogen pentoxide	(11.9)	1161
Na	Sodium	5.13908	603
NaRb	Rubidium sodium	4.32 ± 0.04	480
Na_2	Disodium	4.894 ± 0.003	614
Nb	Niobium	6.75885	1384
Nd	Neodymium	5.5250	859
Ne	Neon	21.56454	2081
Ni	Nickel	7.6398	1167
No	Nobelium	6.65	642
Np	Neptunium	6.2657 ± 0.0003	1069
O	Oxygen (atomic)	13.61806	1563
OPb	Lead(II) oxide	9.08 ± 0.10	939
OS	Sulfur monoxide	10.294 ± 0.004	998
OS_2	Sulfur oxide (SSO)	10.584 ± 0.005	971
OSi	Silicon monoxide	11.49 ± 0.20	1008
OSn	Tin(II) oxide	9.60 ± 0.02	944
OSr	Strontium oxide	6.6 ± 0.2	623
O_2	Oxygen	12.0697 ± 0.0002	1165
O_2S	Sulfur dioxide	12.349 ± 0.001	894
O_2Th	Thorium(IV) oxide	(8.7 ± 0.15)	342
O_2Ti	Titanium(IV) oxide	(9.54 ± 0.1)	623

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
O_2U	Uranium(IV) oxide	(5.4 ± 0.1)	57
O_3	Ozone	12.43	1342
O_3S	Sulfur trioxide	12.82 ± 0.03	841
O_3U	Uranium(VI) oxide	(10.5 ± 0.5)	214
O_4Os	Osmium(VIII) oxide	(12.32)	850
O_4Ru	Ruthenium(VIII) oxide	12.15 ± 0.03	988
O_7Re_2	Rhenium(VII) oxide	(12.7 ± 0.2)	125
Os	Osmium	8.7	1630
P	Phosphorus	10.48669	1328
P_2	Diphosphorus	10.53	1160
Pa	Protactinium	5.89	1133
Pb	Lead	7.41666	911
PbS	Lead(II) sulfide	(8.5 ± 0.5)	954
Pd	Palladium	8.3367	1181
Pm	Promethium	5.55	536
Pr	Praseodymium	5.464	883
Pt	Platinum	9.0	1433
Pu	Plutonium	6.025	926
Ra	Radium	5.27892	668
Rb	Rubidium	4.17713	484
Re	Rhenium	7.88	1530
Rh	Rhodium	7.45890	1276
Rn	Radon	10.74850	1037
Ru	Ruthenium	7.36050	1355
S	Sulfur	10.36001	1277
SSn	Tin(II) sulfide	(8.8)	966
S_2	Disulfur	9.356 ± 0.002	1031
Sb	Antimony	8.64	1096
Sc	Scandium	6.56144	1010
Se	Selenium	9.75238	1168
Si	Silicon	8.15169	1238
Sm	Samarium	5.6437	751
Sn	Tin	7.34381	1011
Sr	Strontium	5.69484	713
Ta	Tantalum	7.89	1544
Tb	Terbium	5.8639	955
Tc	Technetium	7.28	1380
Te	Tellurium	9.0096	1066
Th	Thorium	6.308 ± 0.003	1207
Ti	Titanium	6.8282	1127
Tl	Thallium	6.10829	771
Tm	Thulium	6.18431	827
U	Uranium	6.19405	1129
V	Vanadium	6.746 ± 0.002	1166
W	Tungsten	7.98	1621
Xe	Xenon	12.12987	1170
Y	Yttrium	6.217	1022
Yb	Ytterbium	6.25416	754
Zn	Zinc	9.39405	1037
Zr	Zirconium	6.63390	1251
Substances containing carbon			
C	Carbon	11.26030	1803
$CBrClF_2$	Bromochlorodifluoromethane	(11.21)	642
$CBrCl_3$	Bromotrichloromethane	(10.6)	980
$CBrF_3$	Bromotrifluoromethane	(11.40)	451
CBr_2F_2	Dibromodifluoromethane	11.03 ± 0.04	683
CBr_4	Tetrabromomethane	(10.31 ± 0.02)	1079
CCl	Chloromethylidyne	(8.9 ± 0.2)	1244
$CClF_3$	Chlorotrifluoromethane	12.6 ± 0.2	505

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
CClN	Cyanogen chloride	12.34 ± 0.01	1329
CCl_2	Dichloromethylene	(9.27)	1058
CCl_2F_2	Dichlorodifluoromethane	12.05 ± 0.24	685
CCl_2O	Carbonyl chloride	(11.5)	888
CCl_3F	Trichlorofluoromethane	11.77 ± 0.02	868
CCl_4	Tetrachloromethane	11.47 ± 0.01	1010
CF	Fluoromethylidyne	9.11 ± 0.01	1134
CFN	Cyanogen fluoride	13.34 ± 0.02	1325
CF_2	Difluoromethylene	11.44 ± 0.03	899
CF_2O	Carbonyl fluoride	13.035 ± 0.030	617
CF_3	Trifluoromethyl	8.7 ± 0.2	379
CF_3I	Trifluoroiodomethane	10.23	397
CH	Methylidyne	10.64 ± 0.01	1622
$CHBrCl_2$	Bromodichloromethane	10.6	973
$CHBr_2Cl$	Chlorodibromomethane	10.59 ± 0.01	1030
$CHBr_3$	Tribromomethane	10.48 ± 0.02	1035
CHCl	Chloromethylene	9.84	1247
$CHClF_2$	Chlorodifluoromethane	(12.2)	693
$CHCl_2F$	Dichlorofluoromethane	(11.5)	829
$CHCl_3$	Trichloromethane	11.37 ± 0.02	992
CHF	Fluoromethylene	10.06 ± 0.05	1121
CHF_3	Trifluoromethane	(13.86)	643
CHI_3	Triiodomethane	9.25 ± 0.02	1010
CHN	Hydrogen cyanide	13.60 ± 0.01	1447
CHN	Hydrogen isocyanide	(12.5 ± 0.1)	1407
CHNO	Isocyanic acid	11.595 ± 0.005	1016
CHNO	Fulminic acid	(10.83)	1263
CHO	Oxomethyl (HCO)	(8.55)	826
CH_2	Methylene	10.396 ± 0.003	1392
CH_2BrCl	Bromochloromethane	10.77 ± 0.01	1085
CH_2Br_2	Dibromomethane	(10.50 ± 0.02)	1013
CH_2ClF	Chlorofluoromethane	11.71 ± 0.01	870
CH_2Cl_2	Dichloromethane	11.32 ± .01	996
CH_2F_2	Difluoromethane	12.71	774
CH_2I_2	Diiodomethane	9.46 ± 0.02	1030
CH_2N_2	Diazomethane	8.999 ± 0.001	1098
CH_2N_2	Cyanamide	(10.4)	1137
CH_2O	Formaldehyde	10.88 ± 0.01	941
CH_2O_2	Formic acid	11.33 ± 0.01	715
CH_3	Methyl	9.843 ± 0.002	1095
CH_3BO	Borane carbonyl	11.14 ± 0.02	962
CH_3Br	Bromomethane	10.541 ± 0.003	979
CH_3Cl	Chloromethane	11.22 ± 0.01	1001
CH_3Cl_3Si	Methyltrichlorosilane	(11.36 ± 0.03)	548
CH_3F	Fluoromethane	12.47 ± 0.02	956
CH_3I	Iodomethane	9.538	936
CH_3NO	Formamide	10.16 ± 0.06	796
CH_3NO_2	Nitromethane	11.08 ± 0.07	994
CH_3N_3	Methyl azide	9.81 ± 0.02	1227
CH_3O	Methoxy	(10.72)	1050
CH_4	Methane	12.61 ± 0.01	1143
CH_4N_2O	Urea	9.7	690
CH_4O	Methanol	10.85 ± 0.01	845
CH_4S	Methanethiol	9.44 ± 0.005	888
CH_5N	Methylamine	(8.80)	826
CH_6N_2	Methylhydrazine	7.7 ± 0.15	835
CH_6Si	Methylsilane	(10.7)	1003
CN	Cyanide	13.5984	1748
CNO	Cyanate	11.76 ± 0.01	1290
CO	Carbon monoxide	14.014 ± 0.0003	1242

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
COS	Carbon oxysulfide	11.18 ± 0.01	936
COSe	Carbon oxyselenide	10.36 ± 0.01	929
CO_2	Carbon dioxide	13.773 ± 0.002	935
CS	Carbon sulfide	11.33 ± 0.01	1361
CS_2	Carbon disulfide	10.0685 ± 0.0020	1089
C_2	Dicarbon	(11.4 ± 0.3)	2000
$C_2Br_2F_4$	1,2-Dibromotetrafluoroethane	(11.1)	280
C_2ClF_3	Chlorotrifluoroethylene	9.81 ± 0.03	373
C_2ClF_5	Chloropentafluoroethane	(12.6)	99
C_2Cl_2	Dichloroacetylene	9.9	1165
$C_2Cl_2F_4$	1,2-Dichlorotetrafluoroethane	12.2	252
$C_2Cl_3F_3$	1,1,1-Trichlorotrifluoroethane	11.5	386
$C_2Cl_3F_3$	1,1,2-Trichlorotrifluoroethane	11.99 ± 0.02	429
C_2Cl_4	Tetrachloroethylene	9.326 ± 0.001	887
$C_2Cl_4F_2$	1,1,2,2-Tetrachloro-1,2-difluoroethane	(11.3)	563
C_2Cl_4O	Trichloroacetyl chloride	(11.0)	827
C_2Cl_6	Hexachloroethane	(11.1)	920
C_2F_3N	Trifluoroacetonitrile	13.93 ± 0.07	845
C_2F_4	Tetrafluoroethylene	10.12 ± 0.02	315
C_2F_6	Hexafluoroethane	(13.6)	-30
C_2H	Ethynyl	(11.61 ± 0.07)	1685
C_2HBr	Bromoacetylene	10.31 ± 0.02	1242
$C_2HBrClF_3$	2-Bromo-2-chloro-1,1,1-trifluoroethane	(11.0)	363
C_2HCl	Chloroacetylene	10.58 ± 0.02	1276
C_2HClF_2	1-Chloro-2,2-difluoroethylene	9.80 ± 0.04	628
C_2HCl_3	Trichloroethylene	9.46 ± 0.02	894
C_2HCl_3O	Dichloroacetyl chloride	(10.9)	809
C_2HCl_5	Pentachloroethane	(11.0)	919
C_2HF	Fluoroacetylene	11.26	1195
C_2HF_3	Trifluoroethylene	10.14	489
$C_2HF_3O_2$	Trifluoroacetic acid	11.46	75
C_2H_2	Acetylene	11.400 ± 0.002	1328
$C_2H_2Cl_2$	1,1-Dichloroethylene	9.81 ± 0.04	949
$C_2H_2Cl_2$	*cis*-1,2-Dichloroethylene	9.66 ± 0.01	936
$C_2H_2Cl_2$	*trans*-1,2-Dichloroethylene	9.64 ± 0.02	934
$C_2H_2Cl_2O$	Chloroacetyl chloride	(≤ 10.3)	815
$C_2H_2Cl_4$	1,1,1,2-Tetrachloroethane	(11.1)	920
$C_2H_2Cl_4$	1,1,2,2-Tetrachloroethane	(≤ 11.62)	≤ 971
$C_2H_2F_2$	1,1-Difluoroethylene	10.29 ± 0.01	650
$C_2H_2F_2$	*cis*-1,2-Difluoroethylene	10.23 ± 0.02	690
C_2H_2O	Ketene	9.617 ± 0.003	880
$C_2H_2O_2$	Glyoxal	10.2	773
$C_2H_2S_2$	Thiirene	8.61	892
C_2H_3Br	Bromoethylene	9.83 ± 0.02	1028
C_2H_3Cl	Chloroethylene	9.99 ± 0.02	985
$C_2H_3ClF_2$	1-Chloro-1,1-difluoroethane	(11.98)	626
C_2H_3ClO	Acetyl chloride	10.82 ± 0.04	801
C_2H_3ClO	Chloroacetaldehyde	(10.48)	815
$C_2H_3ClO_2$	Chloroacetic acid	(10.7)	597
$C_2H_3Cl_3$	1,1,1-Trichloroethane	(11.0)	917
$C_2H_3Cl_3$	1,1,2-Trichloroethane	(11.0)	911
C_2H_3F	Fluoroethylene	10.36 ± 0.01	861
C_2H_3FO	Acetyl fluoride	(11.5)	667
$C_2H_3F_3$	1,1,1-Trifluoroethane	13.3 ± 0.5	536
C_2H_3N	Acetonitrile	12.20 ± 0.01	1253
C_2H_3NO	Methylisocyanate	(10.67)	900
C_2H_4	Ethylene	10.5138 ± 0.0006	1067
$C_2H_4Br_2$	1,2-Dibromoethane	10.35 ± 0.04	961
$C_2H_4Cl_2$	1,1-Dichloroethane	11.04 ± 0.02	935
$C_2H_4Cl_2$	1,2-Dichloroethane	11.04 ± 0.02	931

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
$C_2H_4F_2$	1,1-Difluoroethane	(11.87)	643
C_2H_4O	Acetaldehyde	10.229 ± 0.0007	821
C_2H_4O	Ethylene oxide	10.56 ± 0.01	966
$C_2H_4O_2$	Acetic acid	10.65 ± 0.02	595
$C_2H_4O_2$	Methyl formate	10.835 ± 0.005	690
C_2H_5Br	Bromoethane	10.29 ± 0.01	931
C_2H_5Cl	Chloroethane	10.98 ± 0.02	947
C_2H_5ClO	2-Chloroethanol	(10.5)	756
C_2H_5F	Fluoroethane	(11.78)	873
C_2H_5I	Iodoethane	9.3492 ± 0.0006	893
C_2H_5N	Ethyleneimine	(9.5 ± 0.3)	1044
C_2H_5NO	Acetamide	9.65 ± 0.03	693
C_2H_5NO	*N*-Methylformamide	9.83 ± 0.04	760
$C_2H_5NO_2$	Nitroethane	10.88 ± 0.05	948
C_2H_6	Ethane	11.56 ± 0.02	1031
$C_2H_6Cl_2Si$	Dichlorodimethylsilane	(10.7)	576
C_2H_6O	Ethanol	10.43 ± 0.05	772
C_2H_6O	Dimethyl ether	10.025 ± 0.025	783
C_2H_6OS	Dimethyl sulfoxide	9.10 ± 0.03	727
$C_2H_6O_2$	Ethylene glycol	10.16	593
C_2H_6S	Ethanethiol	9.31 ± 0.03	851
C_2H_6S	Dimethyl sulfide	8.69 ± 0.02	801
$C_2H_6S_2$	Dimethyl disulfide	(7.4 ± 0.3)	690
C_2H_7N	Ethylamine	8.86 ± 0.02	808
C_2H_7N	Dimethylamine	8.24 ± 0.08	777
C_2H_7NO	Ethanolamine	8.96	664
$C_2H_8N_2$	1,2-Ethanediamine	(8.6)	812
$C_2H_8N_2$	1,1-Dimethylhydrazine	7.29 ± 0.05	787
C_2N_2	Cyanogen	13.37 ± 0.01	1597
C_3F_6	Perfluoropropene	10.60 ± 0.03	−103
C_3F_6O	Perfluoroacetone	(11.57 ± 0.13)	−282
C_3F_8	Perfluoropropane	(13.38)	−491
C_3HN	Cyanoacetylene	11.64 ± 0.01	1475
C_3H_2O	2-Propynal	(10.7 ± 0.1)	1145
$C_3H_3F_3$	3,3,3-Trifluoropropene	(10.9)	437
C_3H_3N	2-Propenenitrile	10.91 ± 0.01	1237
C_3H_3NO	Oxazole	(9.9)	940
C_3H_3NO	Isoxazole	(9.93)	1038
C_3H_4	Allene	9.692 ± 0.004	1126
C_3H_4	Propyne	10.37 ± 0.01	1187
C_3H_4	Cyclopropene	9.67 ± 0.01	1209
$C_3H_4N_2$	Imidazole	(8.81)	997
C_3H_4O	Propargyl alcohol	10.49 ± 0.02	1060
C_3H_4O	Acrolein	10.103 ± 0.006	900
C_3H_4O	Cyclopropanone	(9.1 ± 0.1)	895
$C_3H_4O_2$	Propenoic acid	10.60	701
$C_3H_4O_2$	2-Oxetanone	(9.70 ± 0.01)	653
C_3H_5Br	3-Bromopropene	(9.96)	1008
C_3H_5Cl	3-Chloropropene	10.04 ± 0.01	965
C_3H_5ClO	Epichlorohydrin	(10.64)	919
$C_3H_5ClO_2$	Methyl chloroacetate	(10.3)	575
C_3H_5F	3-Fluoropropene	(10.11)	821
C_3H_5N	Propanenitrile	11.84 ± 0.02	1194
C_3H_5NO	Acrylamide	(9.5)	720
C_3H_6	Propene	9.73 ± 0.02	959
C_3H_6	Cyclopropane	9.86	1005
$C_3H_6Br_2$	1,2-Dibromopropane	(10.1)	903
$C_3H_6Br_2$	1,3-Dibromopropane	(≤ 10.2)	≤ 919
$C_3H_6Cl_2$	1,2-Dichloropropane	10.8 ± 0.1	886
$C_3H_6Cl_2$	1,3-Dichloropropane	10.89 ± 0.04	892

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
C_3H_6O	Allyl alcohol	9.67 ± 0.05	808
C_3H_6O	Methyl vinyl ether	8.95 ± 0.01	763
C_3H_6O	Propanal	9.96 ± 0.01	772
C_3H_6O	Acetone	9.703 ± 0.006	719
C_3H_6O	Methyloxirane	(10.22)	892
C_3H_6O	Oxetane	9.65 ± 0.01	851
$C_3H_6O_2$	Propanoic acid	10.525 ± 0.003	568
$C_3H_6O_2$	Ethyl formate	10.61 ± 0.01	639
$C_3H_6O_2$	Methyl acetate	10.25 ± 0.02	579
$C_3H_6O_2$	1,3-Dioxolane	(9.9)	658
$C_3H_6O_3$	1,3,5-Trioxane	(10.3)	528
C_3H_7Br	1-Bromopropane	10.18 ± 0.01	898
C_3H_7Br	2-Bromopropane	10.10 ± 0.03	877
C_3H_7Cl	1-Chloropropane	10.81 ± 0.01	911
C_3H_7Cl	2-Chloropropane	10.79 ± 0.02	896
C_3H_7F	1-Fluoropropane	(11.3)	806
C_3H_7F	2-Fluoropropane	(11.08)	776
C_3H_7I	1-Iodopropane	9.25 ± 0.01	860
C_3H_7I	2-Iodopropane	9.19 ± 0.02	845
C_3H_7N	Allylamine	(8.76)	891
C_3H_7N	Cyclopropylamine	(8.8)	926
C_3H_7N	Propyleneimine	(9.0)	960
C_3H_7NO	*N,N*-Dimethylformamide	(9.12)	688
$C_3H_7NO_2$	1-Nitropropane	(10.81)	919
$C_3H_7NO_2$	2-Nitropropane	(10.71)	894
C_3H_8	Propane	10.95 ± 0.05	952
C_3H_8O	1-Propanol	10.18 ± 0.06	727
C_3H_8O	2-Propanol	10.17 ± 0.02	709
C_3H_8O	Ethyl methyl ether	9.72 ± 0.07	722
$C_3H_8O_2$	Dimethoxymethane	9.7	588
C_3H_8S	1-Propanethiol	9.20 ± 0.01	819
C_3H_8S	2-Propanethiol	9.145 ± 0.005	806
C_3H_8S	Ethyl methyl sulfide	(8.55)	765
$C_3H_9BO_3$	Trimethyl borate	(10.0)	65
C_3H_9ClSi	Trimethylchlorosilane	(10.15)	624
C_3H_9N	Propylamine	(8.78)	777
C_3H_9N	Isopropylamine	(8.72)	758
C_3H_9N	Trimethylamine	7.82 ± 0.06	731
C_3H_9NO	3-Amino-1-propanol	(9.0)	651
$C_4H_2O_3$	Maleic anhydride	(10.8)	645
C_4H_4	1-Buten-3-yne	9.58 ± 0.02	1230
$C_4H_4N_2$	Succinonitrile	(12.1 ± 0.25)	1377
$C_4H_4N_2$	Pyrimidine	9.23	1087
$C_4H_4N_2$	Pyridazine	8.67 ± 0.03	1112
C_4H_4O	Furan	8.883 ± 0.003	822
$C_4H_4O_2$	Diketene	(9.6 ± 0.02)	736
$C_4H_4O_3$	Succinic anhydride	(10.6)	500
$C_4H_4O_4$	Fumaric acid	(10.7)	355
C_4H_4S	Thiophene	8.86 ± 0.02	970
C_4H_5N	Methylacrylonitrile	10.34	1127
C_4H_5N	Pyrrole	8.207 ± 0.005	900
C_4H_5N	Cyclopropanecarbonitrile	(10.25)	1173
C_4H_6	1,2-Butadiene	(9.03)	1034
C_4H_6	1,3-Butadiene	9.082 ± 0.004	986
C_4H_6	1-Butyne	10.19 ± 0.02	1148
C_4H_6	2-Butyne	9.59 ± 0.03	1071
C_4H_6	Cyclobutene	9.43 ± 0.02	1067
C_4H_6O	Divinyl ether	(8.7)	827
C_4H_6O	*trans*-2-Butenal	9.73 ± 0.01	835
C_4H_6O	2-Methylpropenal	(9.92)	834

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
C_4H_6O	Cyclobutanone	(9.35)	815
$C_4H_6O_2$	*cis*-Crotonic acid	(10.08)	625
$C_4H_6O_2$	*trans*-Crotonic acid	(9.9)	604
$C_4H_6O_2$	Methacrylic acid	(10.15)	611
$C_4H_6O_2$	Vinyl acetate	9.19 ± 0.05	572
$C_4H_6O_2$	Methyl acrylate	(9.9)	641
$C_4H_6O_3$	Acetic anhydride	(10.0)	398
$C_4H_6O_4$	Dimethyl oxalate	(10.0)	287
C_4H_6S	2,5-Dihydrothiophene	(8.4)	898
C_4H_7N	Butanenitrile	(11.2)	1110
C_4H_7N	2-Methylpropanenitrile	(11.3)	1115
C_4H_7NO	2-Pyrrolidone	(9.2)	674
C_4H_8	1-Butene	9.55 ± 0.06	921
C_4H_8	*cis*-2-Butene	9.11 ± 0.01	871
C_4H_8	*trans*-2-Butene	9.10 ± 0.01	866
C_4H_8	Isobutene	9.239 ± 0.003	875
C_4H_8	Cyclobutane	(9.82 ± 0.05)	976
C_4H_8	Methylcyclopropane	(9.46)	936
$C_4H_8Br_2$	1,4-Dibromobutane	(10.15)	879
C_4H_8O	Ethyl vinyl ether	(8.98)	709
C_4H_8O	1,2-Epoxybutane	(≤ 10.15)	862
C_4H_8O	Butanal	9.84 ± 0.02	742
C_4H_8O	Isobutanal	9.71 ± 0.01	721
C_4H_8O	2-Butanone	9.52 ± 0.04	678
C_4H_8O	Tetrahydrofuran	9.38 ± 0.05	721
$C_4H_8O_2$	Butanoic acid	10.17 ± 0.05	509
$C_4H_8O_2$	2-Methylpropanoic acid	10.33 ± 0.03	516
$C_4H_8O_2$	Propyl formate	10.52 ± 0.02	555
$C_4H_8O_2$	Ethyl acetate	10.01 ± 0.05	522
$C_4H_8O_2$	Methyl propanoate	10.15 ± 0.03	548
$C_4H_8O_2$	1,3-Dioxane	9.8	607
$C_4H_8O_2$	1,4-Dioxane	9.19 ± 0.01	571
$C_4H_8O_2S$	Sulfolane	(9.8)	577
C_4H_8S	Tetrahydrothiophene	8.38	774
C_4H_9Br	1-Bromobutane	(10.12)	869
C_4H_9Br	2-Bromobutane	10.01 ± 0.02	845
C_4H_9Br	1-Bromo-2-methylpropane	10.09 ± 0.02	861
C_4H_9Br	2-Bromo-2-methylpropane	9.92 ± 0.03	823
C_4H_9Cl	1-Chlorobutane	10.67 ± 0.03	875
C_4H_9Cl	2-Chlorobutane	10.53	857
C_4H_9Cl	1-Chloro-2-methylpropane	10.73 ± 0.07	877
C_4H_9Cl	2-Chloro-2-methylpropane	(10.61)	842
C_4H_9I	1-Iodobutane	9.23 ± 0.01	840
C_4H_9I	2-Iodobutane	9.10 ± 0.02	815
C_4H_9I	1-Iodo-2-methylpropane	9.19 ± 0.01	824
C_4H_9I	2-Iodo-2-methylpropane	(9.02)	798
C_4H_9N	Pyrrolidine	(8.0)	769
C_4H_9NO	*N,N*-Dimethylacetamide	8.81 ± 0.03	616
C_4H_9NO	Morpholine	(8.2)	841
C_4H_{10}	Butane	10.53 ± 0.10	890
C_4H_{10}	Isobutane	(10.57)	886
$C_4H_{10}O$	1-Butanol	9.99 ± 0.05	689
$C_4H_{10}O$	2-Butanol	9.88 ± 0.03	658
$C_4H_{10}O$	2-Methyl-1-propanol	10.02 ± 0.04	683
$C_4H_{10}O$	2-Methyl-2-propanol	9.90 ± 0.02	642
$C_4H_{10}O$	Diethyl ether	9.51 ± 0.03	666
$C_4H_{10}O$	Methyl propyl ether	9.41 ± 0.07	670
$C_4H_{10}O$	Isopropyl methyl ether	9.45 ± 0.04	661
$C_4H_{10}O_2$	Ethylene glycol monoethyl ether	(9.6)	529
$C_4H_{10}O_2$	Ethylene glycol dimethyl ether	(9.3)	558

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
$C_4H_{10}S$	1-Butanethiol	9.14 ± 0.01	794
$C_4H_{10}S$	2-Butanethiol	(9.10)	781
$C_4H_{10}S$	2-Methyl-1-propanethiol	(9.12)	783
$C_4H_{10}S$	2-Methyl-2-propanethiol	(9.03)	762
$C_4H_{10}S$	Diethyl sulfide	(8.43)	730
$C_4H_{10}S$	Methyl propyl sulfide	(8.8)	767
$C_4H_{10}S$	Isopropyl methyl sulfide	(8.7)	749
$C_4H_{10}S_2$	Diethyl disulfide	(8.27)	724
$C_4H_{11}N$	Butylamine	8.7 ± 0.1	748
$C_4H_{11}N$	*sec*-Butylamine	8.46 ± 0.1	711
$C_4H_{11}N$	*tert*-Butylamine	8.46 ± 0.1	695
$C_4H_{11}N$	Isobutylamine	8.50 ± 0.1	721
$C_4H_{11}N$	Diethylamine	7.85 ± 0.1	684
$C_4H_{12}Si$	Tetramethylsilane	9.80 ± 0.04	713
$C_4H_{12}Sn$	Tetramethylstannane	8.89 ± 0.05	837
C_4NiO_4	Nickel carbonyl	8.27 ± 0.04	200
$C_5H_4O_2$	Furfural	9.22 ± 0.01	739
C_5H_5N	Pyridine	9.25	1031
C_5H_6	1-Penten-3-yne	9.00 ± 0.01	1119
C_5H_6	*cis*-3-Penten-1-yne	9.14 ± 0.04	1137
C_5H_6	*trans*-3-Penten-1-yne	9.05 ± 0.01	1128
C_5H_6	2-Methyl-1-buten-3-yne	9.25 ± 0.02	1152
C_5H_6	1,3-Cyclopentadiene	8.55 ± 0.02	955
C_5H_6O	2-Methylfuran	8.38 ± 0.02	729
C_5H_6O	3-Methylfuran	(8.64)	763
C_5H_6S	2-Methylthiophene	(8.14)	867
C_5H_6S	3-Methylthiophene	(8.40)	893
C_5H_8	*cis*-1,3-Pentadiene	8.63 ± 0.03	914
C_5H_8	*trans*-1,3-Pentadiene	8.59 ± 0.02	905
C_5H_8	1,4-Pentadiene	9.60 ± 0.02	1032
C_5H_8	2-Methyl-1,3-butadiene	8.84 ± 0.01	928
C_5H_8	1-Pentyne	10.10 ± 0.01	1119
C_5H_8	Cyclopentene	9.01 ± 0.01	905
C_5H_8	Spiropentane	(9.26)	1078
C_5H_8O	Cyclopropyl methyl ketone	(≤ 9.46)	796
C_5H_8O	Cyclopentanone	9.26 ± 0.01	701
C_5H_8O	3,4-Dihydro-2H-pyran	8.35 ± 0.01	681
$C_5H_8O_2$	Ethyl acrylate	(≤ 10.3)	617
$C_5H_8O_2$	Methyl methacrylate	(9.7)	589
$C_5H_8O_2$	2,4-Pentanedione	8.85 ± 0.01	469
C_5H_9NO	*N*-Methyl-2-pyrrolidone	(≤ 9.17)	≤ 676
C_5H_{10}	1-Pentene	9.51 ± 0.01	896
C_5H_{10}	*cis*-2-Pentene	9.01 ± 0.03	843
C_5H_{10}	*trans*-2-Pentene	9.04 ± 0.01	841
C_5H_{10}	2-Methyl-1-butene	9.12 ± 0.01	844
C_5H_{10}	3-Methyl-1-butene	9.52 ± 0.01	891
C_5H_{10}	2-Methyl-2-butene	8.69 ± 0.01	796
C_5H_{10}	Cyclopentane	(10.33 ± 0.15)	918
$C_5H_{10}O$	2,2-Dimethylpropanal	9.51 ± 0.01	675
$C_5H_{10}O$	Cyclopentanol	(9.72)	695
$C_5H_{10}O$	Pentanal	9.74 ± 0.04	709
$C_5H_{10}O$	2-Pentanone	9.38 ± 0.01	646
$C_5H_{10}O$	3-Pentanone	9.31 ± 0.01	640
$C_5H_{10}O$	3-Methyl-2-butanone	9.30 ± 0.01	635
$C_5H_{10}O$	Tetrahydropyran	9.25 ± 0.01	670
$C_5H_{10}O_2$	Pentanoic acid	(≤ 10.53)	≤ 527
$C_5H_{10}O_2$	3-Methylbutanoic acid	(≤ 10.51)	≤ 499
$C_5H_{10}O_2$	Butyl formate	10.52 ± 0.02	584
$C_5H_{10}O_2$	Propyl acetate	(≤ 9.92)	501
$C_5H_{10}O_2$	Isopropyl acetate	9.99 ± 0.03	482

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
$C_5H_{10}O_2$	Ethyl propanoate	(10.00)	500
$C_5H_{10}O_2$	Methyl butanoate	(10.07)	520
$C_5H_{10}S$	Thiacyclohexane	(8.2)	728
$C_5H_{11}Br$	1-Bromopentane	10.10 ± 0.01	846
$C_5H_{11}I$	1-Iodopentane	9.20 ± 0.01	817
$C_5H_{11}N$	Piperidine	8.03 ± 0.11	726
$C_5H_{11}N$	*N*-Methylpyrrolidine	≤ 8.41 ± 0.02	≤ 809
C_5H_{12}	Pentane	10.28 ± 0.10	845
C_5H_{12}	Isopentane	10.32 ± 0.05	843
C_5H_{12}	Neopentane	(≤ 10.2)	≤ 818
$C_5H_{12}O$	1-Pentanol	(10.00)	668
$C_5H_{12}O$	2-Pentanol	(9.78)	630
$C_5H_{12}O$	3-Pentanol	9.78	628
$C_5H_{12}O$	2-Methyl-1-butanol	(9.86)	649
$C_5H_{12}O$	2-Methyl-2-butanol	(9.8)	615
$C_5H_{12}O$	3-Methyl-2-butanol	(9.88 ± 0.13)	637
$C_5H_{12}O$	Butyl methyl ether	(9.4 ± 0.1)	648
$C_5H_{12}O$	Methyl *tert*-butyl ether	(9.24)	608
$C_5H_{12}O$	Ethyl propyl ether	(9.45)	640
$C_5H_{12}S$	*tert*-Butyl methyl sulfide	(8.38)	687
$C_5H_{12}S$	Ethyl propyl sulfide	(8.50)	716
$C_5H_{12}S$	Ethyl isopropyl sulfide	(8.35)	689
C_6BrF_5	Bromopentafluorobenzene	(9.67)	222
C_6ClF_5	Chloropentafluorobenzene	(9.72)	126
C_6Cl_6	Hexachlorobenzene	(8.98)	822
C_6F_6	Hexafluorobenzene	9.89 ± 0.04	8
C_6F_{12}	Perfluorocyclohexane	(13.2)	−1095
C_6HF_5	Pentafluorobenzene	(9.63)	122
C_6HF_5O	Pentafluorophenol	(9.20)	−71
$C_6H_2F_4$	1,2,3,4-Tetrafluorobenzene	(9.53)	284
$C_6H_2F_4$	1,2,3,5-Tetrafluorobenzene	(9.53)	263
$C_6H_2F_4$	1,2,4,5-Tetrafluorobenzene	(9.35)	254
$C_6H_3Cl_3$	1,2,4-Trichlorobenzene	(9.04)	880
$C_6H_3Cl_3$	1,3,5-Trichlorobenzene	9.32 ± 0.02	899
$C_6H_4ClNO_2$	1-Chloro-3-nitrobenzene	(9.92 ± 0.1)	995
$C_6H_4ClNO_2$	1-Chloro-4-nitrobenzene	(9.96 ± 0.1)	999
$C_6H_4Cl_2$	*o*-Dichlorobenzene	9.06 ± 0.02	907
$C_6H_4Cl_2$	*m*-Dichlorobenzene	9.10 ± 0.02	906
$C_6H_4Cl_2$	*p*-Dichlorobenzene	8.92 ± 0.02	885
$C_6H_4FNO_2$	1-Fluoro-4-nitrobenzene	(9.90)	826
$C_6H_4F_2$	*o*-Difluorobenzene	9.29 ± 0.01	602
$C_6H_4F_2$	*m*-Difluorobenzene	9.33 ± 0.01	591
$C_6H_4F_2$	*p*-Difluorobenzene	9.1589 ± 0.0003	577
$C_6H_4O_2$	*p*-Benzoquinone	10.01 ± 0.06	844
C_6H_5Br	Bromobenzene	9.00 ± 0.02	971
C_6H_5Cl	Chlorobenzene	9.07 ± 0.02	930
C_6H_5ClO	*m*-Chlorophenol	8.655 ± 0.001	680
C_6H_5ClO	*p*-Chlorophenol	(≤ 8.69)	≤ 692
C_6H_5F	Fluorobenzene	9.20 ± 0.01	772
C_6H_5I	Iodobenzene	8.685	1003
$C_6H_5NO_2$	Nitrobenzene	9.86 ± 0.02	1019
$C_6H_5NO_3$	*o*-Nitrophenol	(9.1)	782
$C_6H_5NO_3$	*m*-Nitrophenol	(9.0)	755
$C_6H_5NO_3$	*p*-Nitrophenol	(9.1)	761
C_6H_6	Benzene	9.24378 ± 0.00007	975
C_6H_6	Fulvene	(8.36)	1031
C_6H_6ClN	*o*-Chloroaniline	(8.50)	883
C_6H_6ClN	*m*-Chloroaniline	(8.09)	835
C_6H_6ClN	*p*-Chloroaniline	(≤ 8.18)	≤ 844
$C_6H_6N_2O_2$	*o*-Nitroaniline	(8.27)	861

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
$C_6H_6N_2O_2$	*m*-Nitroaniline	(8.31)	865
$C_6H_6N_2O_2$	*p*-Nitroaniline	(8.34)	859
C_6H_6O	Phenol	8.49 ± 0.02	723
$C_6H_6O_2$	*p*-Hydroquinone	7.94 ± 0.01	503
C_6H_6S	Benzenethiol	(8.32)	915
C_6H_7N	Aniline	7.720 ± 0.002	832
C_6H_7N	2-Methylpyridine	(9.02)	970
C_6H_7N	3-Methylpyridine	(9.04)	979
C_6H_7N	4-Methylpyridine	(9.04)	976
$C_6H_8N_2$	*o*-Phenylenediamine	(7.2)	787
$C_6H_8N_2$	*m*-Phenylenediamine	(7.14)	777
$C_6H_8N_2$	*p*-Phenylenediamine	(6.87 ± 0.05)	759
C_6H_{10}	1,5-Hexadiene	9.27 ± 0.05	978
C_6H_{10}	1-Hexyne	10.03 ± 0.05	1089
C_6H_{10}	3,3-Dimethyl-1-butyne	9.90 ± 0.04	1060
C_6H_{10}	Cyclohexene	8.945 ± 0.01	859
$C_6H_{10}O$	Cyclohexanone	9.14 ± 0.01	656
$C_6H_{10}O$	Mesityl oxide	9.10 ± 0.01	694
$C_6H_{10}O_4$	Diethyl oxalate	(9.8)	205
$C_6H_{11}NO$	Caprolactam	(9.07 ± 0.02)	629
C_6H_{12}	1-Hexene	9.44 ± 0.04	869
C_6H_{12}	*cis*-2-Hexene	(8.97 ± 0.01)	818
C_6H_{12}	*trans*-2-Hexene	(8.97 ± 0.01)	814
C_6H_{12}	2-Methyl-1-pentene	(9.08 ± 0.01)	817
C_6H_{12}	4-Methyl-1-pentene	9.45 ± 0.01	862
C_6H_{12}	2-Methyl-2-pentene	(8.58)	761
C_6H_{12}	4-Methyl-*cis*-2-pentene	8.98 ± 0.01	809
C_6H_{12}	4-Methyl-*trans*-2-pentene	(8.97 ± 0.01)	804
C_6H_{12}	2-Ethyl-1-butene	(9.06 ± 0.02)	818
C_6H_{12}	2,3-Dimethyl-1-butene	(9.07 ± 0.01)	812
C_6H_{12}	2,3-Dimethyl-2-butene	8.27 ± 0.01	729
C_6H_{12}	Cyclohexane	9.86 ± 0.03	828
C_6H_{12}	Methylcyclopentane	(9.85)	845
$C_6H_{12}O$	Hexanal	9.72 ± 0.05	691
$C_6H_{12}O$	2-Hexanone	9.3 ± 0.1	626
$C_6H_{12}O$	3-Hexanone	9.12 ± 0.02	600
$C_6H_{12}O$	3-Methyl-2-pentanone	9.21 ± 0.01	600
$C_6H_{12}O$	4-Methyl-2-pentanone	9.30 ± 0.01	609
$C_6H_{12}O$	2-Methyl-3-pentanone	9.10 ± 0.01	592
$C_6H_{12}O$	3,3-Dimethyl-2-butanone	9.12 ± 0.02	589
$C_6H_{12}O$	Cyclohexanol	(9.75)	651
$C_6H_{12}O_2$	Hexanoic acid	≤ 10.12	≤ 463
$C_6H_{12}O_2$	Butyl acetate	(9.92 ± .05)	471
$C_6H_{12}O_2$	*sec*-Butyl acetate	9.90	453
$C_6H_{12}O_2$	Methyl 2,2-dimethylpropanoate	(9.90 ± 0.04)	466
$C_6H_{13}I$	1-Iodohexane	9.179	794
$C_6H_{13}N$	Cyclohexylamine	(8.86)	750
C_6H_{14}	Hexane	10.13	810
C_6H_{14}	2-Methylpentane	(10.12)	802
C_6H_{14}	3-Methylpentane	(10.08)	801
C_6H_{14}	2,2-Dimethylbutane	(10.06)	787
C_6H_{14}	2,3-Dimethylbutane	(10.02)	791
$C_6H_{14}O$	1-Hexanol	(9.89)	639
$C_6H_{14}O$	2-Hexanol	(9.80 ± 0.03)	611
$C_6H_{14}O$	3-Hexanol	(9.63 ± 0.03)	599
$C_6H_{14}O$	Dipropyl ether	(9.27)	602
$C_6H_{14}O$	Diisopropyl ether	9.20 ± 0.05	569
$C_6H_{14}O$	Butyl ethyl ether	(9.36)	610
$C_6H_{14}O$	Methyl pentyl ether	(≤ 9.67)	≤ 657
$C_6H_{14}O_2$	1,1-Diethoxyethane	(9.2)	434

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
$C_6H_{14}O_3$	Diethylene glycol dimethyl ether	≤ 9.8	≤ 448
$C_6H_{14}S$	Dipropyl sulfide	8.30 ± 0.02	676
$C_6H_{14}S$	Diisopropyl sulfide	(8.2 ± 0.2)	649
$C_6H_{15}N$	Hexylamine	(8.63 ± 0.05)	699
$C_6H_{15}N$	Dipropylamine	(7.84 ± 0.02)	641
$C_6H_{15}N$	Diisopropylamine	(7.73 ± 0.03)	602
$C_6H_{15}N$	Triethylamine	(7.50 ± 0.02)	631
$C_6H_{15}NO_3$	Triethanolamine	(7.9)	206
$C_7H_3F_5$	2,3,4,5,6-Pentafluorotoluene	(9.4)	64
C_7H_5ClO	Benzoyl chloride	(9.53)	815
$C_7H_5Cl_3$	(Trichloromethyl)benzene	(≤ 9.60)	≤ 914
$C_7H_5F_3$	(Trifluoromethyl)benzene	9.685 ± 0.005	335
C_7H_5N	Benzonitrile	9.70 ± 0.01	1154
C_7H_6O	Benzaldehyde	9.49 ± 0.02	878
$C_7H_6O_2$	Benzoic acid	(9.3)	604
C_7H_7Br	*p*-Bromotoluene	8.67 ± 0.02	908
C_7H_7Cl	*o*-Chlorotoluene	(8.7 ± 0.1)	856
C_7H_7Cl	*m*-Chlorotoluene	(8.83)	869
C_7H_7Cl	*p*-Chlorotoluene	(8.69)	855
C_7H_7Cl	(Chloromethyl)benzene	9.10 ± 0.02	897
C_7H_7F	*o*-Fluorotoluene	8.91 ± 0.01	709
C_7H_7F	*m*-Fluorotoluene	8.91 ± 0.01	709
C_7H_7F	*p*-Fluorotoluene	8.79 ± 0.01	701
C_7H_7NO	Benzamide	(9.25)	792
$C_7H_7NO_2$	*o*-Nitrotoluene	9.24	946
$C_7H_7NO_2$	*m*-Nitrotoluene	9.45 ± 0.1	941
$C_7H_7NO_2$	*p*-Nitrotoluene	9.46 ± 0.05	942
C_7H_8	Toluene	8.8276 ± 0.0006	901
C_7H_8O	*o*-Cresol	(8.24)	670
C_7H_8O	*m*-Cresol	8.29 ± 0.07	668
C_7H_8O	*p*-Cresol	(8.3)	675
C_7H_8O	Benzyl alcohol	(8.3)	701
C_7H_8O	Anisole	8.22 ± 0.03	725
C_7H_9N	Benzylamine	(8.64)	917
C_7H_9N	*o*-Methylaniline	(7.44 ± 0.02)	772
C_7H_9N	*m*-Methylaniline	(7.50 ± 0.02)	778
C_7H_9N	*p*-Methylaniline	(7.24 ± 0.02)	753
C_7H_9N	*N*-Methylaniline	7.34 ± 0.04	792
C_7H_9N	2,3-Dimethylpyridine	(8.85 ± 0.02)	922
C_7H_9N	2,4-Dimethylpyridine	(8.85 ± 0.03)	918
C_7H_9N	2,5-Dimethylpyridine	(≤ 8.80 ± 0.05)	≤ 916
C_7H_9N	2,6-Dimethylpyridine	8.86 ± 0.03	913
C_7H_9N	3,4-Dimethylpyridine	(≤ 9.15)	≤ 953
C_7H_9N	3,5-Dimethylpyridine	(≤ 9.25)	≤ 965
$C_7H_{10}O$	Dicyclopropyl ketone	(9.1)	1041
C_7H_{14}	1-Heptene	9.34 ± 0.10	839
C_7H_{14}	*trans*-3-Heptene	(8.92)	790
C_7H_{14}	Cycloheptane	9.97	844
C_7H_{14}	Methylcyclohexane	9.64	775
C_7H_{14}	*cis*-1,2-Dimethylcyclopentane	(9.92 ± 0.05)	828
C_7H_{14}	*trans*-1,2-Dimethylcyclopentane	9.7 ± 0.2	799
$C_7H_{14}O$	1-Heptanal	(9.65)	668
$C_7H_{14}O$	2-Heptanone	9.28 ± 0.10	594
$C_7H_{14}O$	3-Heptanone	9.18 ± 0.08	589
$C_7H_{14}O$	4-Heptanone	9.10 ± 0.06	577
$C_7H_{14}O$	5-Methyl-2-hexanone	(9.28)	586
$C_7H_{14}O$	2,4-Dimethyl-3-pentanone	8.95 ± 0.01	552
$C_7H_{14}O$	1-Methylcyclohexanol	(9.8 ± 0.2)	586
C_7H_{16}	Heptane	9.93 ± 0.10	771
$C_7H_{16}O$	1-Heptanol	(9.84)	614

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
$C_7H_{16}O$	2-Heptanol	(9.70)	580
$C_7H_{16}O$	3-Heptanol	(9.68)	578
$C_7H_{16}O$	4-Heptanol	(9.61)	572
$C_7H_{16}O$	Ethyl pentyl ether	(≤ 9.49)	≤ 602
$C_8H_4O_3$	Phthalic anhydride	(10.1)	603
$C_8H_6O_4$	Isophthalic acid	(9.98)	268
$C_8H_6O_4$	Terephthalic acid	(9.86)	232
C_8H_7N	2-Methylbenzonitrile	(≤ 9.38)	1085
C_8H_7N	3-Methylbenzonitrile	(≤ 9.34)	1085
C_8H_7N	4-Methylbenzonitrile	9.32 ± 0.02	1083
C_8H_7N	Indole	7.7602 ± 0.0006	908
C_8H_8	Styrene	8.464 ± 0.001	964
C_8H_8O	*p*-Tolualdehyde	(9.33)	825
C_8H_8O	Acetophenone	9.29 ± 0.03	810
$C_8H_8O_2$	*o*-Toluic acid	(9.1)	558
$C_8H_8O_2$	*m*-Toluic acid	(9.43)	579
$C_8H_8O_2$	*p*-Toluic acid	(9.23)	560
$C_8H_8O_2$	Benzeneacetic acid	(8.26)	479
$C_8H_8O_2$	Methyl benzoate	9.32 ± 0.03	611
C_8H_{10}	Ethylbenzene	8.77 ± 0.01	876
C_8H_{10}	*o*-Xylene	8.56 ± 0.01	844
C_8H_{10}	*m*-Xylene	8.56 ± 0.01	843
C_8H_{10}	*p*-Xylene	8.44 ± 0.01	832
$C_8H_{10}O$	*p*-Ethylphenol	(7.84)	613
$C_8H_{10}O$	2,3-Xylenol	(8.26)	640
$C_8H_{10}O$	2,4-Xylenol	(8.0)	609
$C_8H_{10}O$	2,6-Xylenol	(8.05)	615
$C_8H_{10}O$	3,4-Xylenol	(8.09)	624
$C_8H_{10}O$	Phenetole	(8.13)	683
$C_8H_{11}N$	2,4,6-Trimethylpyridine	(≤ 8.9)	≤ 880
$C_8H_{11}N$	*N*-Ethylaniline	(≤ 7.67)	≤ 794
$C_8H_{11}N$	*N,N*-Dimethylaniline	7.12 ± 0.02	787
C_8H_{14}	1-Octyne	(9.95 ± 0.02)	1040
C_8H_{14}	2-Octyne	9.31 ± 0.01	961
C_8H_{14}	3-Octyne	9.22 ± 0.01	952
C_8H_{14}	4-Octyne	9.20 ± 0.01	946
C_8H_{16}	1-Octene	9.43 ± 0.01	829
C_8H_{16}	Cyclooctane	9.75 ± 0.05	816
C_8H_{16}	Ethylcyclohexane	(9.54)	748
C_8H_{16}	1,1-Dimethylcyclohexane	(9.42)	728
C_8H_{16}	*cis*-1,2-Dimethylcyclohexane	(<9.78)	772
C_8H_{16}	*trans*-1,2-Dimethylcyclohexane	9.41	728
C_8H_{16}	*cis*-1,3-Dimethylcyclohexane	(<9.98)	778
C_8H_{16}	*trans*-1,3-Dimethylcyclohexane	9.53	743
C_8H_{16}	*cis*-1,4-Dimethylcyclohexane	(<9.93)	782
C_8H_{16}	*trans*-1,4-Dimethylcyclohexane	(9.56)	738
C_8H_{16}	Propylcyclopentane	(9.34)	753
$C_8H_{16}O$	2,2,4-Trimethyl-3-pentanone	(8.80)	511
C_8H_{18}	Octane	9.80 ± 0.10	737
C_8H_{18}	2-Methylheptane	(9.84)	734
C_8H_{18}	2,2,4-Trimethylpentane	(9.86)	713
C_8H_{18}	2,2,3,3-Tetramethylbutane	9.8	720
$C_8H_{18}O$	Dibutyl ether	(9.28)	s 560
$C_8H_{18}O$	Di-*sec*-butyl ether	(9.11)	511
$C_8H_{18}O$	Di-*tert*-butyl ether	8.88 ± 0.07	493
$C_8H_{18}S$	Dibutyl sulfide	(8.2)	624
$C_8H_{18}S$	Di-*tert*-butyl sulfide	(8.0)	583
$C_8H_{18}S$	Diisobutyl sulfide	(8.34)	625
$C_8H_{19}N$	Dibutylamine	(7.69)	586
$C_8H_{19}N$	Diisobutylamine	(7.8)	574

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
$C_8H_{20}Si$	Tetraethylsilane	(8.9)	595
C_9H_7N	Quinoline	8.62 ± 0.01	1041
C_9H_7N	Isoquinoline	8.53 ± 0.03	1032
C_9H_8	Indene	8.14 ± 0.01	949
C_9H_{10}	*o*-Methylstyrene	(8.20)	908
C_9H_{10}	*m*-Methylstyrene	(8.15)	899
C_9H_{10}	*p*-Methylstyrene	(8.1)	895
C_9H_{10}	Cyclopropylbenzene	(8.35)	956
C_9H_{10}	Indan	(8.3)	864
$C_9H_{10}O_2$	Ethyl benzoate	(8.9)	537
C_9H_{12}	Propylbenzene	8.713 ± 0.010	848
C_9H_{12}	Isopropylbenzene	8.73 ± 0.01	847
C_9H_{12}	1,2,3-Trimethylbenzene	8.42 ± 0.02	803
C_9H_{12}	1,2,4-Trimethylbenzene	8.27 ± 0.01	784
C_9H_{12}	1,3,5-Trimethylbenzene	8.41 ± 0.01	796
$C_9H_{13}N$	*N,N*-Dimethyl-*o*-toluidine	7.40 ± 0.02	814
$C_9H_{14}O$	Isophorone	(≤ 9.07)	≤ 670
C_9H_{18}	Butylcyclopentane	(9.95)	793
C_9H_{18}	Propylcyclohexane	(9.46)	720
C_9H_{18}	Isopropylcyclohexane	(9.33)	704
$C_9H_{18}O$	2-Nonanone	(9.16)	545
$C_9H_{18}O$	5-Nonanone	(9.07)	530
$C_9H_{18}O$	2,6-Dimethyl-4-heptanone	9.01 ± 0.06	512
C_9H_{20}	Nonane	9.71 ± 0.10	709
$C_{10}F_8$	Perfluoronaphthalene	8.85	–368
$C_{10}H_7Br$	1-Bromonaphthalene	8.08 ± 0.03	955
$C_{10}H_7Cl$	1-Chloronaphthalene	(8.13)	906
$C_{10}H_8$	Naphthalene	8.1442 ± 0.0009	936
$C_{10}H_8$	Azulene	7.38 ± 0.05	1001
$C_{10}H_8O$	1-Naphthol	7.76 ± 0.03	719
$C_{10}H_8O$	2-Naphthol	7.87 ± 0.06	729
$C_{10}H_{10}O_4$	Dimethyl phthalate	(9.64 ± 0.07)	277
$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene	8.46 ± 0.02	841
$C_{10}H_{14}$	Butylbenzene	8.69 ± 0.02	826
$C_{10}H_{14}$	*sec*-Butylbenzene	8.68 ± 0.02	820
$C_{10}H_{14}$	*tert*-Butylbenzene	8.68 ± 0.05	816
$C_{10}H_{14}$	Isobutylbenzene	8.69 ± 0.02	817
$C_{10}H_{14}$	*p*-Cymene	(8.29)	771
$C_{10}H_{14}$	*o*-Diethylbenzene	(≤ 8.51)	≤ 804
$C_{10}H_{14}$	*m*-Diethylbenzene	(8.49)	798
$C_{10}H_{14}$	*p*-Diethylbenzene	(8.40)	790
$C_{10}H_{14}$	1,2,4,5-Tetramethylbenzene	8.04 ± 0.02	730
$C_{10}H_{14}O$	*p*-tert-Butylphenol	(7.8)	552
$C_{10}H_{16}$	α-Pinene	(8.07)	808
$C_{10}H_{16}O$	Camphor	(8.76)	577
$C_{10}H_{18}$	*cis*-Decahydronaphthalene	9.36 ± 0.04	734
$C_{10}H_{18}$	*trans*-Decahydronaphthalene	9.34 ± 0.04	720
$C_{10}H_{20}$	1-Decene	9.42 ± 0.05	786
$C_{10}H_{20}$	Butylcyclohexane	(9.41)	695
$C_{10}H_{22}$	Decane	(9.65)	682
$C_{11}H_{10}$	1-Methylnaphthalene	7.97 ± 0.03	882
$C_{11}H_{10}$	2-Methylnaphthalene	7.91 ± 0.08	877
$C_{11}H_{16}$	*p-tert*-Butyltoluene	(8.12)	730
$C_{11}H_{24}$	Undecane	(9.56)	650
$C_{11}H_{24}$	2-Methyldecane	(9.7)	658
$C_{12}H_8$	Acenaphthylene	(8.22)	1053
$C_{12}H_9N$	Carbazole	(7.57)	961
$C_{12}H_{10}$	Acenaphthene	7.75 ± 0.07	903
$C_{12}H_{10}$	Biphenyl	8.23 ± 0.10	977
$C_{12}H_{10}N_2O$	*trans*-Azoxybenzene	(8.1)	1123

Mol. form.	Name	IP/eV	$\Delta_f H_{ion}$ kJ/mol
$C_{12}H_{10}O$	Diphenyl ether	(8.09)	766
$C_{12}H_{11}N$	Diphenylamine	7.16 ± 0.04	908
$C_{12}H_{18}$	5,7-Dodecadiyne	(8.67)	1079
$C_{12}H_{18}$	Hexamethylbenzene	7.85 ± 0.01	670
$C_{12}H_{22}$	Cyclohexylcyclohexane	(9.41)	690
$C_{12}H_{27}N$	Tributylamine	(7.4)	492
$C_{13}H_{10}$	9*H*-Fluorene	7.91 ± 0.02	952
$C_{13}H_{10}O$	Benzophenone	9.08 ± 0.05	926
$C_{13}H_{12}$	Diphenylmethane	(8.55)	963
$C_{14}H_{10}$	Anthracene	7.439 ± 0.006	948
$C_{14}H_{10}$	Phenanthrene	7.8914 ± 0.0006	966
$C_{14}H_{10}$	Diphenylacetylene	7.94 ± 0.03	1168
$C_{14}H_{12}$	*cis*-Stilbene	(7.80)	1005
$C_{14}H_{12}$	*trans*-Stilbene	7.656 ± 0.001	973
$C_{14}H_{14}$	1,2-Diphenylethane	8.9 ± 0.1	1002
$C_{16}H_{10}$	Fluoranthene	7.9 ± 0.1	1052
$C_{16}H_{10}$	Pyrene	7.4256 ± 0.0006	935
$C_{18}H_{12}$	Chrysene	7.60 ± 0.01	1017
$C_{18}H_{14}$	*o*-Terphenyl	(7.99)	1056
$C_{18}H_{14}$	*m*-Terphenyl	(8.01)	1057
$C_{18}H_{14}$	*p*-Terphenyl	7.80 ± 0.03	1037
$C_{20}H_{12}$	Perylene	6.960 ± 0.001	981
$C_{24}H_{12}$	Coronene	7.29 ± 0.01	1026

X-RAY ATOMIC ENERGY LEVELS

The energy levels in this tables are the values recommended by Bearden and Burr on the basis of a thorough review of the literature on x-ray wavelengths and related data. All values are in electron volts (eV). Values in parentheses are interpolated, and an asterisk * indicates a level which is not resolved from the level above it. See Reference 1 for uncertainties in the levels and a complete description of how the recommended values were obtained.

References

1. Bearden, J. A., and Burr, A. F., *Rev. Mod. Phys.*, 39, 125, 1967; also published as *X-Ray Wavelengths and X-Ray Atomic Energy* Levels, Natl. Stand. Ref. Data Sys. — Natl. Bur. Standards (U.S.), No. 14, 1967.
2. Gray, D. E., Ed., *American Institute of Physics Handbook, Third Edition*, pp. 7-158 to 7-167, McGraw-Hill, New York, 1972.

Level	^{1}H	^{2}He	^{3}Li	^{4}Be	^{5}B	^{6}C	^{7}N	^{8}O
K	13.59811	24.58678	54.75	111.0	188.0	283.8	401.6	532.0
L_I								23.7
$L_{II,III}$					4.7	6.4	9.2	7.1

Level	^{9}F	^{10}Ne	^{11}Na	^{12}Mg	^{13}Al	^{14}Si	^{15}P	^{16}S
K	685.4	866.9	1072.1	1305.0	1559.6	1838.9	2145.5	2472.0
L_I	(31)	(45)	63.3	89.4	117.7	148.7	189.3	229.2
$L_{II,III}$	8.6	18.3	31.1	51.4	73.1	99.2	132.2	164.8

Level	^{17}Cl	^{18}Ar	^{19}K	^{20}Ca	^{21}Sc	^{22}Ti	^{23}V	^{24}Cr
K	2822.4	3202.9	3607.4	4038.1	4492.8	4966.4	5465.1	5989.2
L_I	270.2	320	377.1	437.8	500.4	563.7	628.2	694.6
L_{II}	201.6	247.3	296.3	350.0	406.7	461.5	520.5	583.7
L_{III}	200.0	245.2	293.6	346.4	402.2	455.5	512.9	574.5
M_I	17.5	25.3	33.9	43.7	53.8	60.3	66.5	74.1
$M_{II,III}$	6.8	12.4	17.8	25.4	32.3	34.6	37.8	42.5
$M_{IV,V}$					6.6	3.7	2.2	2.3

Level	^{25}Mn	^{26}Fe	^{27}Co	^{28}Ni	^{29}Cu	^{30}Zn	^{31}Ga	^{32}Ge
K	6539.0	7112.0	7708.9	8332.8	8978.9	9658.6	10367.1	11103.1
L_I	769.0	846.1	925.6	1008.1	1096.1	1193.6	1297.7	1414.3
L_{II}	651.4	721.1	793.6	871.9	951.0	1042.8	1142.3	1247.8
L_{III}	640.3	708.1	778.6	854.7	931.1	1019.7	1115.4	1216.7
M_I	83.9	92.9	100.7	111.8	119.8	135.9	158.1	180.0
M_{II}	48.6	54.0	59.5	68.1	73.6	86.6	106.8	127.9
M_{III}	48.6*	54.0*	59.5*	68.1*	73.6*	86.6*	102.9	120.8
$M_{IV,V}$	3.3	3.6	2.9	3.6	1.6	8.1	17.4	28.7

Level	^{33}As	^{34}Se	^{35}Br	^{36}Kr	^{37}Rb	^{38}Sr	^{39}Y	^{40}Zr
K	11866.7	12657.8	13473.7	14325.6	15199.7	16104.6	17038.4	17997.6
L_I	1526.5	1653.9	1782.0	1921.0	2065.1	2216.3	2372.5	2531.6
L_{II}	1358.6	1476.2	1596.0	1727.2	1863.9	2006.8	2155.5	2306.7
L_{III}	1323.1	1435.8	1549.9	1674.9	1804.4	1939.6	2080.0	2222.3
M_I	203.5	231.5	256.5		322.1	357.5	393.6	430.3
M_{II}	146.4	168.2	189.3	222.7	247.4	279.8	312.4	344.2
M_{III}	140.5	161.9	181.5	213.8	238.5	269.1	300.3	330.5
M_{IV}	41.2	56.7	70.1	88.9	111.8	135.0	159.6	182.4
M_V	41.2*	56.7*	69.0	88.9*	110.3	133.1	157.4	180.0
N_I			27.3	24.0	29.3	37.7	45.4	51.3
N_{II}	2.5	5.6	5.2	10.6	14.8	19.9	25.6	28.7
N_{III}	2.5*	5.6*	4.6	10.6*	14.0	19.9*	25.6*	28.7*

Level	^{41}Nb	^{42}Mo	^{43}Tc	^{44}Ru	^{45}Rh	^{46}Pd	^{47}Ag	^{48}Cd
K	18985.6	19999.5	21044.0	22117.2	23219.9	24350.3	25514.0	26711.2
L_I	2697.7	2865.5	3042.5	3224.0	3411.9	3604.3	3805.8	4018.0
L_{II}	2464.7	2625.1	2793.2	2966.9	3146.1	3330.3	3523.7	3727.0
L_{III}	2370.5	2520.2	2676.9	2837.9	3003.8	3173.3	3351.1	3537.5
M_I	468.4	504.6		585.0	627.1	669.9	717.5	770.2
M_{II}	378.4	409.7	444.9	482.8	521.0	559.1	602.4	650.7
M_{III}	363.0	392.3	425.0	460.6	496.2	531.5	571.4	616.5
M_{IV}	207.4	230.3	256.4	283.6	311.7	340.0	372.8	410.5

Level	^{41}Nb	^{42}Mo	^{43}Tc	^{44}Ru	^{45}Rh	^{46}Pd	^{47}Ag	^{48}Cd
M_V	204.6	227.0	252.9	279.4	307.0	334.7	366.7	403.7
N_I	58.1	61.8		74.9	81.0	86.4	95.2	107.6
N_{II}	33.9	34.8	38.9	43.1	47.9	51.1	62.6	66.9
N_{III}	33.9*	34.8*	38.9*	43.1*	47.9*	51.1*	55.9	66.9*
$N_{IV,V}$	3.2	1.8		2.0	2.5	1.5	3.3	9.3

Level	^{49}In	^{50}Sn	^{51}Sb	^{52}Te	^{53}I	^{54}Xe	^{55}Cs	^{56}Ba
K	27939.9	29200.1	30491.2	31813.8	33169.4	34561.4	35984.6	37440.6
L_I	4237.5	4464.7	4698.3	4939.2	5188.1	5452.8	5714.3	5988.8
L_{II}	3938.0	4156.1	4380.4	4612.0	4852.1	5103.7	5359.4	5623.6
L_{III}	3730.1	3928.8	4132.2	4341.4	4557.1	4782.2	5011.9	5247.0
M_I	825.6	883.8	943.7	1006.0	1072.1		1217.1	1292.8
M_{II}	702.2	756.4	811.9	869.7	930.5	999.0	1065.0	1136.7
M_{III}	664.3	714.4	765.6	818.7	874.6	937.0	997.6	1062.2
M_{IV}	450.8	493.3	536.9	582.5	631.3		739.5	796.1
M_V	443.1	484.8	527.5	572.1	619.4	672.3	725.5	780.7
N_I	121.9	136.5	152.0	168.3	186.4		230.8	253.0
N_{II}	77.4	88.6	98.4	110.2	122.7	146.7	172.3	191.8
N_{III}	77.4*	88.6*	98.4*	110.2*	122.7*	146.7*	161.6	179.7
N_{IV}	16.2	23.9	31.4	39.8	49.6		78.8	92.5
N_V	16.2*	23.9*	31.4*	39.8*	49.6*		76.5	89.9
O_I	0.1	0.9	6.7	11.6	13.6		22.7	39.1
O_{II}	0.8	1.1	2.1	2.3	3.3		13.1	16.6
O_{III}	0.8*	1.1*	2.1*	2.3*	3.3*		11.4	14.6

Level	^{57}La	^{58}Ce	^{59}Pr	^{60}Nd	^{61}Pm	^{62}Sm	^{63}Eu	^{64}Gd
K	38924.6	40443.0	41990.6	43568.9	45184.0	46834.2	48519.0	50239.1
L_I	6266.3	6548.8	6834.8	7126.0	7427.9	7736.8	8052.0	8375.6
L_{II}	5890.6	6164.2	6440.4	6721.5	7012.8	7311.8	7617.1	7930.3
L_{III}	5482.7	5723.4	5964.3	6207.9	6459.3	6716.2	6976.9	7242.8
M_I	1361.3	1434.6	1511.0	1575.3		1722.8	1800.0	1880.8
M_{II}	1204.4	1272.8	1337.4	1402.8	1471.4	1540.7	1613.9	1688.3
M_{III}	1123.4	1185.4	1242.2	1297.4	1356.9	1419.8	1480.6	1544.0
M_{IV}	848.5	901.3	951.1	999.9	1051.5	1106.0	1160.6	1217.2
M_V	831.7	883.3	931.0	977.7	1026.9	1080.2	1130.9	1185.2
N_I	270.4	289.6	304.5	315.2		345.7	360.2	375.8
N_{II}	205.8	223.3	236.3	243.3	242	265.6	283.9	288.5
N_{III}	191.4	207.2	217.6	224.6	242*	247.4	256.6	270.9
$N_{IV,V}$	98.9	110.0	113.2	117.5	120.4	129.0	133.2	140.5
$N_{VI,VII}$		0.1	2.0	1.5		5.5	0.0	0.1
O_I	32.3	37.8	37.4	37.5		37.4	31.8	36.1
$O_{II,III}$	14.4	19.8	22.3	21.1		21.3	22.0	20.3

Level	^{65}Tb	^{66}Dy	^{67}Ho	^{68}Er	^{69}Tm	^{70}Yb	^{71}Lu	^{72}Hf
K	51995.7	53788.5	55617.7	57485.5	59389.6	61332.3	63313.8	65350.8
L_I	8708.0	9045.8	9394.2	9751.3	10115.7	10486.4	10870.4	11270.7
L_{II}	8251.6	8580.6	8917.8	9264.3	9616.9	9978.2	10348.6	10739.4
L_{III}	7514.0	7790.1	8071.1	8357.9	8648.0	8943.6	9244.1	9560.7
M_I	1967.5	2046.8	2128.3	2206.5	2306.8	2398.1	2491.2	2600.9
M_{II}	1767.7	1841.8	1922.8	2005.8	2089.8	2173.0	2263.5	2365.4
M_{III}	1611.3	1675.6	1741.2	1811.8	1884.5	1949.8	2023.6	2107.6
M_{IV}	1275.0	1332.5	1391.5	1453.3	1514.6	1576.3	1639.4	1716.4
M_V	1241.2	1294.9	1351.4	1409.3	1467.7	1527.8	1588.5	1661.7
N_I	397.9	416.3	435.7	449.1	471.7	487.2	506.2	538.1
N_{II}	310.2	331.8	343.5	366.2	385.9	396.7	410.1	437.0
N_{III}	385.0	292.9	306.6	320.0	336.6	343.5	359.3	380.4
N_{IV}	147.0	154.2	161.0	176.7	179.6	198.1	204.8	223.8
N_V	147.0*	154.2*	161.0*	167.6	179.6*	184.9	195.0	213.7
$N_{VI,VII}$	2.6	4.2	3.7	4.3	5.3	6.3	6.9	17.1
O_I	39.0	62.9	51.2	59.8	53.2	54.1	56.8	64.9
O_{II}	25.4	26.3	20.3	29.4	32.3	23.4	28.0	38.1
O_{III}	25.4*	26.3*	20.3*	29.4*	32.3*	23.4*	28.0*	30.6

Level	^{73}Ta	^{74}W	^{75}Re	^{76}Os	^{77}Ir	^{78}Pt	^{79}Au	^{80}Hg
K	67416.4	69525.0	71676.4	73870.8	76111.0	78394.8	80724.9	83102.3
L_I	11681.5	12099.8	12526.7	12968.0	13418.5	13879.9	14352.8	14839.3
L_{II}	11136.1	11544.0	11958.7	12385.0	12824.1	13272.6	13733.6	14208.7
L_{III}	9881.1	10206.8	10535.3	10870.9	11215.2	11563.7	11918.7	12283.9
M_I	2708.0	2819.6	2931.7	3048.5	3173.7	3296.0	3424.9	3561.6
M_{II}	2468.7	2574.9	2681.6	2792.2	2908.7	3026.5	3147.8	3278.5
M_{III}	2194.0	2281.0	2367.3	2457.2	2550.7	2645.4	2743.0	2847.1
M_{IV}	1793.2	1871.6	1948.9	2030.8	2116.1	2201.9	2291.1	2384.9
M_V	1735.1	1809.2	1882.9	1960.1	2040.4	2121.6	2205.7	2294.9
N_I	565.5	595.0	625.0	654.3	690.1	722.0	758.8	800.3
N_{II}	464.8	491.6	517.9	546.5	577.1	609.2	643.7	676.9
N_{III}	404.5	425.3	444.4	468.2	494.3	519.0	545.4	571.0
N_{IV}	241.3	258.8	273.7	289.4	311.4	330.8	352.0	378.3
N_V	229.3	245.4	260.2	272.8	294.9	313.3	333.9	359.8
N_{VI}	25.0	36.5	40.6	46.3	63.4	74.3	86.4	102.2
N_{VII}	25.0*	33.6	40.6*	46.3*	60.5	71.1	82.8	98.5
O_I	71.1	77.1	82.8	83.7	95.2	101.7	107.8	120.3
O_{II}	44.9	46.8	45.6	58.0	63.0	65.3	71.7	80.5
O_{III}	36.4	35.6	34.6	45.4	50.5	51.7	53.7	57.6
$O_{IV,V}$	5.7	6.1	3.5		3.8	2.2	2.5	6.4

Level	^{81}Tl	^{82}Pb	^{83}Bi	^{84}Po	^{85}At	^{86}Rn	^{87}Fr	^{88}Ra
K	85530.4	88004.5	90525.9	93105.0	95729.9	98404	101137	103921.9
L_I	15346.7	15860.8	16387.5	16939.3	17493	18049	18639	19236.7
L_{II}	14697.9	15200.0	15711.1	16244.3	16784.7	17337.1	17906.5	18484.3
L_{III}	12657.5	13035.2	13418.6	13813.8	14213.5	14619.4	15031.2	15444.4
M_I	3704.1	3850.7	3999.1	4149.4	(4317)	(4482)	(4652)	4822.0
M_{II}	3415.7	3554.2	3696.3	3854.1	4008	4159	4327	4489.5
M_{III}	2956.6	3066.4	3176.9	3301.9	3426	3538	3663	3791.8
M_{IV}	2485.1	2585.6	2687.6	2798.0	2908.7	3021.5	3136.2	3248.4
M_V	2389.3	2484.0	2579.6	2683.0	2786.7	2892.4	2999.9	3104.9
N_I	845.5	893.6	938.2	995.3	(1042)	(1097)	(1153)	1208.4
N_{II}	721.3	763.9	805.3	851	886	929	980	1057.6
N_{III}	609.0	644.5	678.9	705	740	768	810	879.1
N_{IV}	406.6	435.2	463.6	500.2	533.2	566.6	603.3	635.9
N_V	386.2	412.9	440.0	473.4			577	602.7
N_{VI}	122.8	142.9	161.9					298.9
N_{VII}	118.5	138.1	157.4					298.9*
O_I	136.3	147.3	159.3					254.4
O_{II}	99.6	104.8	116.8					200.4
O_{III}	75.4	86.0	92.8					152.8
O_{IV}	15.3	21.8	26.5	31.4				67.2
O_V	13.1	19.2	24.4	31.4*				67.2*
P_I		3.1						43.5
$P_{II,III}$		0.7	2.7					18.8

Level	^{89}Ac	^{90}Th	^{91}Pa	^{92}U	^{93}Np	^{94}Pu	^{95}Am	^{96}Cm
K	106755.3	109650.9	112601.4	115606.1	118678	121818	125027	128220
L_I	19840	20472.1	21104.6	21757.4	22426.8	23097.2	23772.9	24460
L_{II}	19083.2	19693.2	20313.7	20947.6	21600.5	22266.2	22944.0	23779
L_{III}	15871.0	16300.3	16733.1	17166.3	17610.0	18056.8	18504.1	18930
M_I	(5002)	5182.3	5366.9	5548.0	5723.2	5932.9	6120.5	6288
M_{II}	4656	4830.4	5000.9	5182.2	5366.2	5541.2	5710.2	5895
M_{III}	3909	4046.1	4173.8	4303.4	4434.7	4556.6	4667.0	4797
M_{IV}	3370.2	3490.8	3611.2	3727.6	3850.3	3972.6	4092.1	4227
M_V	3219.0	3332.0	3441.8	3551.7	3665.8	3778.1	3886.9	3971
N_I	(1269)	1329.5	1387.1	1440.8	1500.7	1558.6	1617.1	1643
N_{II}	1080	1168.2	1224.3	1272.6	1327.7	1372.1	1411.8	1440
N_{III}	890	967.3	1006.7	1044.9	1086.8	1114.8	(1135.7)	1154
N_{IV}	674.9	714.1	743.4	780.4	815.9	848.9	878.7	

Level	^{89}Ac	^{90}Th	^{91}Pa	^{92}U	^{93}Np	^{94}Pu	^{95}Am	^{96}Cm
N_V		676.4	708.2	737.7	770.3	801.4	827.6	
N_{VI}		344.4	371.2	391.3	415.0	445.8		
N_{VII}		335.2	359.5	380.9	404.4	432.4		
O_I		290.2	309.6	323.7		351.9		385
O_{II}		229.4	222.9	259.3	283.4	274.1		
O_{III}		181.8	222.9*	195.1	206.1	206.5		
O_{IV}		94.3	94.1	105.0	109.3	116.0	115.8	
O_V		87.9	94.1*	96.3	101.3	105.4	103.3	
P_I		59.5		70.7				
P_{II}		49.0		42.3				
P_{III}		43.0		32.3				

Level	^{97}Bk	^{98}Cf	^{99}Es	^{100}Fm	^{101}Md	^{102}No	^{103}Lr
K	131590	135960	139490	143090	146780	150540	154380
L_I	25275	26110	26900	27700	28530	29380	30240
L_{II}	24385	25250	26020	26810	27610	28440	29280
L_{III}	19452	19930	20410	20900	21390	21880	22360
M_I	6556	6754	6977	7205	7441	7675	7900
M_{II}	6147	6359	6574	6793	7019	7245	7460
M_{III}	4977	5109	5252	5397	5546	5688	5710
M_{IV}	4366	4497	4630	4766	4903	5037	5150
M_V	4132	4253	4374	4498	4622	4741	4860
N_I	1755	1799	1868	1937	2010	2078	2140
N_{II}	1554	1616	1680	1747	1814	1876	1930
N_{III}	1235	1279	1321	1366	1410	1448	1480
O_I	398	419	435	454	472	484	490

ELECTRON BINDING ENERGIES OF THE ELEMENTS

Gwyn P. Williams

This table gives the binding energies in electron volts (eV) for selected electronic levels of the elements. For metallic elements the binding energy is referred to the Fermi level; for semiconductors, to the valence band maximum; and for gases and insulators, to the vacuum level. The atomic number is listed after the element name.

References

1. Fluggle and Martensson, *J. Elect. Spect.*, 21, 275, 1980.
2. Cardona, M. and Ley, L., *Photoemission from Solids*, Springer Verlag, Heidelberg, 1978.
3. Bearden, J. A. and Burr, A. F., *Rev. Mod. Phys.*, 39, 125, 1967.

Actinium (89)		
K	1s	106755
L I	2s	19840
L II	$2p_{1/2}$	19083
L III	$2p_{3/2}$	15871
M I	3s	5002
M II	$3p_{1/2}$	4656
M III	$3p_{3/2}$	3909
M IV	$3d_{3/2}$	3370
M V	$3d_{5/2}$	3219
N I	4s	1269[a]
N II	$4p_{1/2}$	1080[a]
N III	$4p_{3/2}$	890[a]
N IV	$4d_{3/2}$	675[a]
N V	$4d_{5/2}$	639[a]
N VI	$4f_{5/2}$	319[a]
N VII	$4f_{7/2}$	319[a]
O I	5s	272[a]
O II	$5p_{1/2}$	215[a]
O III	$5p_{3/2}$	167[a]
O IV	$5d_{3/2}$	80[a]
O V	$5d_{5/2}$	80[a]
P I	6s	—
P II	$6p_{1/2}$	—
P III	$6p_{3/2}$	—
Aluminum (13)		
K	1s	1559.0
L I	2s	117.8[a]
L II	$2p_{1/2}$	72.9[a]
L III	$2p_{3/2}$	72.5[a]
Antimony (51)		
K	1s	30419
L I	2s	4698
L II	$2p_{1/2}$	4380
L III	$2p_{3/2}$	4132
M I	3s	946[b]
M II	$3p_{1/2}$	812.7[b]
M III	$3p_{3/2}$	766.4[b]
M IV	$3d_{3/2}$	537.5[b]
M V	$3d_{5/2}$	528.2[b]
N I	4s	153.2[b]
N II	$4p_{1/2}$	95.6[b,c]
N III	$4p_{3/2}$	95.6[b]
N IV	$4d_{3/2}$	33.3[b]
N V	$4d_{5/2}$	32.1[b]
Argon (18)		
K	1s	3205.9[a]
L I	2s	326.3[a]
L II	$2p_{1/2}$	250.6[a]
L III	$2p_{3/2}$	248.4[a]
M I	3s	29.3[a]
M II	$3p_{1/2}$	15.9[a]
M III	$3p_{3/2}$	15.7[a]
Arsenic (33)		
K	1s	11867
L I	2s	1527.0[a,d]
L II	$2p_{1/2}$	1359.1[a,d]
L III	$2p_{3/2}$	1323.6[a,d]
M I	3s	204.7[a]
M II	$3p_{1/2}$	146.2[a]
M III	$3p_{3/2}$	141.2[a]
M IV	$3d_{3/2}$	41.7[a]
M V	$3d_{5/2}$	41.7[a]
Astatine (85)		
K	1s	95730
L I	2s	17493
L II	$2p_{1/2}$	16785
L III	$2p_{3/2}$	14214
M I	3s	4317
M II	$3p_{1/2}$	4008
M III	$3p_{3/2}$	3426
M IV	$3d_{3/2}$	2909
M V	$3d_{5/2}$	2787
N I	4s	1042[a]
N II	$4p_{1/2}$	886[a]
N III	$4p_{3/2}$	740[a]
N IV	$4d_{3/2}$	533[a]
N V	$4d_{5/2}$	507[a]
N VI	$4f_{5/2}$	210[a]
N VII	$4f_{7/2}$	210[a]
O I	5s	195[a]
O II	$5p_{1/2}$	148[a]
O III	$5p_{3/2}$	115[a]
O IV	$5d_{3/2}$	40[a]
O V	$5d_{5/2}$	40[a]
Barium (56)		
K	1s	37441
L I	2s	5989
L II	$2p_{1/2}$	5624
L III	$2p_{3/2}$	5247
M I	3s	1293[a,d]
M II	$3p_{1/2}$	1137[a,d]
M III	$3p_{3/2}$	1063[a,d]
M IV	$3d_{3/2}$	795.7[a]
M V	$3d_{5/2}$	780.5[a]
N I	4s	253.5[b]
N II	$4p_{1/2}$	192
N III	$4p_{3/2}$	178.6[b]
N IV	$4d_{3/2}$	92.6[b]
N V	$4d_{5/2}$	89.9[b]
N VI	$4f_{5/2}$	—
N VII	$4f_{7/2}$	—
O I	5s	30.3[b]
O II	$5p_{1/2}$	17.0[b]
O III	$5p_{3/2}$	14.8[b]
Beryllium (4)		
K	1s	111.5[a]
Bismuth (83)		
K	1s	90526
L I	2s	16388
L II	$2p_{1/2}$	15711
L III	$2p_{3/2}$	13419
M I	3s	3999
M II	$3p_{1/2}$	3696
M III	$3p_{3/2}$	3177
M IV	$3d_{3/2}$	2688
M V	$3d_{5/2}$	2580
N I	4s	939[b]
N II	$4p_{1/2}$	805.2[b]
N III	$4p_{3/2}$	678.8[b]
N IV	$4d_{3/2}$	464.0[b]
N V	$4d_{5/2}$	440.1[b]
N VI	$4f_{5/2}$	162.3[b]
N VII	$4f_{7/2}$	157.0[b]
O I	5s	159.3[a,d]
O II	$5p_{1/2}$	119.0[b]
O III	$5p_{3/2}$	92.6[b]
O IV	$5d_{3/2}$	26.9[b]
O V	$5d_{5/2}$	23.8[b]
Boron (5)		
K	1s	188[a]
Bromine (35)		
K	1s	13474
L I	2s	1782[a]
L II	$2p_{1/2}$	1596[a]
L III	$2p_{3/2}$	1550[a]
M I	3s	257[a]
M II	$3p_{1/2}$	189[a]
M III	$3p_{3/2}$	182[a]
M IV	$3d_{3/2}$	70[a]
M V	$3d_{5/2}$	69[a]
Cadmium (48)		
K	1s	26711
L I	2s	4018
L II	$2p_{1/2}$	3727
L III	$2p_{3/2}$	3538
M I	3s	772.0[b]
M II	$3p_{1/2}$	652.6[b]
M III	$3p_{3/2}$	618.4[b]
M IV	$3d_{3/2}$	411.9[b]
M V	$3d_{5/2}$	405.2[b]
N I	4s	109.8[b]
N II	$4p_{1/2}$	63.9[b,c]
N III	$4p_{3/2}$	63.9[b,c]
N IV	$4d_{3/2}$	11.7[b]
N V	$4d_{5/2}$	10.7[b]
Calcium (20)		
K	1s	4038.5[a]
L I	2s	438.4[b]
L II	$2p_{1/2}$	349.7[b]
L III	$2p_{3/2}$	346.2[b]
M I	3s	44.3[b]
M II	$3p_{1/2}$	25.4[b]
M III	$3p_{3/2}$	25.4[b]
Carbon (6)		
K	1s	284.2[a]
Cerium (58)		
K	1s	40443
L I	2s	6548
L II	$2p_{1/2}$	6164
L III	$2p_{3/2}$	5723
M I	3s	1436[a,d]
M II	$3p_{1/2}$	1274[a,d]
M III	$3p_{3/2}$	1187[a,d]
M IV	$3d_{3/2}$	902.4[a]
M V	$3d_{5/2}$	883.8[a]
N I	4s	291.0[a]
N II	$4p_{1/2}$	223.3
N III	$4p_{3/2}$	206.5[a]
N IV	$4d_{3/2}$	109[a]
N V	$4d_{5/2}$	—
N VI	$4f_{5/2}$	0.1
N VII	$4f_{7/2}$	0.1
O I	5s	37.8
O II	$5p_{1/2}$	19.8[a]
O III	$5p_{3/2}$	17.0[a]
Cesium (55)		
K	1s	35985
L I	2s	5714
L II	$2p_{1/2}$	5359
L III	$2p_{3/2}$	5012
M I	3s	1211[a,d]
M II	$3p_{1/2}$	1071[a]

M III	$3p_{3/2}$	1003[a]
M IV	$3d_{3/2}$	740.5[a]
M V	$3d_{5/2}$	726.6[a]
N I	4s	232.3[a]
N II	$4p_{1/2}$	172.4[a]
N III	$4p_{3/2}$	161.3[a]
N IV	$4d_{3/2}$	79.8[a]
N V	$4d_{5/2}$	77.5[a]
N VI	$4f_{5/2}$	—
N VII	$4f_{7/2}$	—
O I	5s	22.7
O II	$5p_{1/2}$	14.2[a]
O III	$5p_{3/2}$	12.1[a]

Chlorine (17)

K	1s	2822.0
L I	2s	270[a]
L II	$2p_{1/2}$	202[a]
L III	$2p_{3/2}$	200[a]

Chromium(24)

K	1s	5989
L I	2s	696.0[b]
L II	$2p_{1/2}$	583.8[b]
L III	$2p_{3/2}$	574.1[b]
M I	3s	74.1[b]
M II	$3p_{1/2}$	42.2[b]
M III	$3p_{3/2}$	42.2[b]

Cobalt (27)

K	1s	7709
L I	2s	925.1[b]
L II	$2p_{1/2}$	793.2[b]
L III	$2p_{3/2}$	778.1[b]
M I	3s	101.0[b]
M II	$3p_{1/2}$	58.9[b]
M III	$3p_{3/2}$	58.9[b]

Copper (29)

K	1s	8979
L I	2s	1096.7[b]
L II	$2p_{1/2}$	952.3[b]
L III	$2p_{3/2}$	932.5[b]
M I	3s	122.5[b]
M II	$3p_{1/2}$	77.3[b]
M III	$3p_{3/2}$	75.1[b]

Dysprosium (66)

K	1s	53789
L I	2s	9046
L II	$2p_{1/2}$	8581
L III	$2p_{3/2}$	7790
M I	3s	2047
M II	$3p_{1/2}$	1842
M III	$3p_{3/2}$	1676
M IV	$3d_{3/2}$	1333
M V	$3d_{5/2}$	1292[a]
N I	4s	414.2[a]
N II	$4p_{1/2}$	333.5[a]
N III	$4p_{3/2}$	293.2[a]
N IV	$4d_{3/2}$	153.6[a]
N V	$4d_{5/2}$	153.6[a]
N VI	$4f_{5/2}$	8.0[a]
N VII	$4f_{7/2}$	4.3[a]
O I	5s	49.9[a]
O II	$5p_{1/2}$	26.3
O III	$5p_{3/2}$	26.3

Erbium (68)

K	1s	57486
L I	2s	9751
L II	$2p_{1/2}$	9264
L III	$2p_{3/2}$	8358
M I	3s	2206
M II	$3p_{1/2}$	2006
M III	$3p_{3/2}$	1812
M IV	$3d_{3/2}$	1453
M V	$3d_{5/2}$	1409
N I	4s	449.8[a]
N II	$4p_{1/2}$	366.2
N III	$4p_{3/2}$	320.2[a]
N IV	$4d_{3/2}$	167.6[a]
N V	$4d_{5/2}$	167.6[a]
N VI	$4f_{5/2}$	—
N VII	$4f_{7/2}$	4.7[a]
O I	5s	50.6[a]
O II	$5p_{1/2}$	31.4[a]
O III	$5p_{3/2}$	24.7[a]

Europium (63)

K	1s	48519
L I	2s	8052
L II	$2p_{1/2}$	7617
L III	$2p_{3/2}$	6977
M I	3s	1800
M II	$3p_{1/2}$	1614
M III	$3p_{3/2}$	1481
M IV	$3d_{3/2}$	1158.6[a]
M V	$3d_{5/2}$	1127.5[a]
N I	4s	360
N II	$4p_{1/2}$	284
N III	$4p_{3/2}$	257
N IV	$4d_{3/2}$	133
N V	$4d_{5/2}$	1227[a]
N VI	$4f_{5/2}$	0
N VII	$4f_{7/2}$	0
O I	5s	32
O II	$5p_{1/2}$	22
O III	$5p_{3/2}$	22

Fluorine (9)

K	1s	696.7[a]

Francium (87)

K	1s	101137
L I	2s	18639
L II	$2p_{1/2}$	17907
L III	$2p_{3/2}$	15031
M I	3s	4652
M II	$3p_{1/2}$	4327
M III	$3p_{3/2}$	3663
M IV	$3d_{3/2}$	3136
M V	$3d_{5/2}$	3000
N I	4s	1153[a]
N II	$4p_{1/2}$	980[a]
N III	$4p_{3/2}$	810[a]
N IV	$4d_{3/2}$	603[a]
N V	$4d_{5/2}$	577[a]
N VI	$4f_{5/2}$	268[a]
N VII	$4f_{7/2}$	268[a]
O I	5s	234[a]
O II	$5p_{1/2}$	182[a]
O III	$5p_{3/2}$	140[a]
O IV	$5d_{3/2}$	58[a]
O V	$5d_{5/2}$	58[a]
P I	6s	34
P II	$6p_{1/2}$	15
P III	$6p_{3/2}$	15

Gadolinium (64)

K	1s	50239
L I	2s	8376
L II	$2p_{1/2}$	7930
L III	$2p_{3/2}$	7243
M I	3s	1881
M II	$3p_{1/2}$	1688
M III	$3p_{3/2}$	1544
M IV	$3d_{3/2}$	1221.9[a]
M V	$3d_{5/2}$	1189.6[a]
N I	4s	378.6[a]
N II	$4p_{1/2}$	286
N III	$4p_{3/2}$	271
N IV	$4d_{3/2}$	—
N V	$4d_{5/2}$	142.6[a]
N VI	$4f_{5/2}$	8.6[a]
N VII	$4f_{7/2}$	8.6[a]
O I	5s	36
O II	$5p_{1/2}$	20
O III	$5p_{3/2}$	20

Gallium (31)

K	1s	10367
L I	2s	1299.0[a,d]
L II	$2p_{1/2}$	1143.2[b]
L III	$2p_{3/2}$	1116.4[b]
M I	3s	159.5[b]
M II	$3p_{1/2}$	103.5[b]
M III	$3p_{3/2}$	100.0[b]
M IV	$3d_{3/2}$	18.7[b]
M V	$3d_{5/2}$	18.7[b]

Germanium (32)

K	1s	11103
L I	2s	1414.6[a,d]
L II	$2p_{1/2}$	1248.1[a,d]
L III	$2p_{3/2}$	1217.0[a,d]
M I	3s	180.1[a]
M II	$3p_{1/2}$	124.9[a]
M III	$3p_{3/2}$	120.8[a]
M IV	$3d_{3/2}$	29.8[a]
M V	$3d_{5/2}$	29.2[a]

Gold (79)

K	1s	80725
L I	2s	14353
L II	$2p_{1/2}$	13734
L III	$2p_{3/2}$	11919
M I	3s	3425
M II	$3p_{1/2}$	3148
M III	$3p_{3/2}$	2743
M IV	$3d_{3/2}$	2291
M V	$3d_{5/2}$	2206
N I	4s	762.1[b]
N II	$4p_{1/2}$	642.7[b]
N III	$4p_{3/2}$	546.3[b]
N IV	$4d_{3/2}$	353.2[b]
N V	$4d_{5/2}$	335.1[b]
N VI	$4f_{5/2}$	87.6[b]
N VII	$4f_{7/2}$	83.9[b]
O I	5s	107.2[a,d]
O II	$5p_{1/2}$	74.2[b]
O III	$5p_{3/2}$	57.2[b]

Hafnium (72)

K	1s	65351
L I	2s	11271
L II	$2p_{1/2}$	10739
L III	$2p_{3/2}$	9561
M I	3s	2601
M II	$3p_{1/2}$	2365
M III	$3p_{3/2}$	2107
M IV	$3d_{3/2}$	1176
M V	$3d_{5/2}$	1662
N I	4s	538[a]
N II	$4p_{1/2}$	438.2[b]
N III	$4p_{3/2}$	380.7[b]
N IV	$4d_{3/2}$	220.0[b]
N V	$4d_{5/2}$	211.5[b]
N VI	$4f_{5/2}$	15.9[b]
N VII	$4f_{7/2}$	14.2[b]
O I	5s	64.2[b]
O II	$5p_{1/2}$	38[a]
O III	$5p_{3/2}$	29.9[b]

Helium (2)

K	1s	24.6[a]

Holmium (67)

K	1s	55618
L I	2s	9394
L II	$2p_{1/2}$	8918
L III	$2p_{3/2}$	8071
M I	3s	2128
M II	$3p_{1/2}$	1923
M III	$3p_{3/2}$	1741
M IV	$3d_{3/2}$	1392
M V	$3d_{5/2}$	1351
N I	4s	432.4[a]
N II	$4p_{1/2}$	343.5
N III	$4p_{3/2}$	308.2[a]
N IV	$4d_{3/2}$	160[a]
N V	$4d_{5/2}$	160[a]
N VI	$4f_{5/2}$	8.6[a]
N VII	$4f_{7/2}$	5.2[a]
O I	5s	49.3[a]
O II	$5p_{1/2}$	30.8[a]
O III	$5p_{3/2}$	24.1[a]

Hydrogen (1)

K	1s	13.6

Indium (49)

K	1s	27940
L I	2s	4238
L II	$2p_{1/2}$	3938
L III	$2p_{3/2}$	3730
M I	3s	827.2[b]
M II	$3p_{1/2}$	703.2[b]
M III	$3p_{3/2}$	665.3[b]
M IV	$3d_{3/2}$	451.4[b]

M V	$3d_{5/2}$	443.9[b]
N I	4s	122.9[b]
N II	$4p_{1/2}$	73.5[b,c]
N III	$4p_{3/2}$	73.5[b,c]
N IV	$4d_{3/2}$	17.7[b]
N V	$4d_{5/2}$	16.9[b]

Iodine (53)

K	1s	33169
L I	2s	5188
L II	$2p_{1/2}$	4852
L III	$2p_{3/2}$	4557
M I	3s	1072[a]
M II	$3p_{1/2}$	931[a]
M III	$3p_{3/2}$	875[a]
M IV	$3d_{3/2}$	631[a]
M V	$3d_{5/2}$	620[a]
N I	4s	186[a]
N II	$4p_{1/2}$	123[a]
N III	$4p_{3/2}$	123[a]
N IV	$4d_{3/2}$	50[a]
N V	$4d_{5/2}$	50[a]

Iridium (77)

K	1s	76111
L I	2s	13419
L II	$2p_{1/2}$	12824
L III	$2p_{3/2}$	11215
M I	3s	3174
M II	$3p_{1/2}$	2909
M III	$3p_{3/2}$	2551
M IV	$3d_{3/2}$	2116
M V	$3d_{5/2}$	2040
N I	4s	691.1[b]
N II	$4p_{1/2}$	577.8[b]
N III	$4p_{3/2}$	495.8[b]
N IV	$4d_{3/2}$	311.9[b]
N V	$4d_{5/2}$	296.3[b]
N VI	$4f_{5/2}$	63.8[b]
N VII	$4f_{7/2}$	60.8[b]
O I	52	95.2[a,d]
O II	$5p_{1/2}$	63.0[a,d]
O III	$5p_{3/2}$	48.0[b]

Iron (26)

K	1s	7112
L I	2s	844.6[b]
L II	$2p_{1/2}$	719.9[b]
L III	$2p_{3/2}$	706.8[b]
M I	3s	91.3[b]
M II	$3p_{1/2}$	52.7[b]
M III	$3p_{3/2}$	52.7[b]

Krypton (36)

K	1s	14326
L I	2s	1921
L II	$2p_{1/2}$	1730.9[a]
L III	$2p_{3/2}$	1678.4[a]
M I	3s	292.8[a]
M II	$3p_{1/2}$	222.2[a]
M III	$3p_{3/2}$	214.4[a]
M IV	$3d_{3/2}$	95.0[a]
M V	$3d_{5/2}$	93.8[a]
N I	4s	27.5[a]
N II	$4p_{1/2}$	14.1[a]
N III	$4p_{3/2}$	14.1[a]

Lanthanum (57)

K	1s	38925
L I	2s	6266
L II	$2p_{1/2}$	5891
L III	$2p_{3/2}$	5483
M I	3s	1362[a,d]
M II	$3p_{1/2}$	1209[a,d]
M III	$3p_{3/2}$	1128[a,d]
M IV	$3d_{3/2}$	853[a]
M V	$3d_{5/2}$	836[a]
N I	4s	247.7[a]
N II	$4p_{1/2}$	205.8
N III	$4p_{3/2}$	196.0[a]
N IV	$4d_{3/2}$	105.3[a]
N V	$4d_{5/2}$	102.5[a]
N VI	$4f_{5/2}$	—
N VII	$4f_{7/2}$	—
O I	5s	34.3[a]
O II	$5p_{1/2}$	19.3[a]
O III	$5p_{3/2}$	16.8[a]

Lead (82)

K	1s	88005
L I	2s	15861
L II	$2p_{1/2}$	15200
L III	$2p_{3/2}$	13055
M I	3s	3851
M II	$3p_{1/2}$	3554
M III	$3p_{3/2}$	3066
M IV	$3d_{3/2}$	2586
M V	$3d_{5/2}$	2484
N I	4s	891.8[b]
N II	$4p_{1/2}$	761.9[b]
N III	$4p_{3/2}$	643.5[b]
N IV	$4d_{3/2}$	434.3[b]
N V	$4d_{5/2}$	412.2[b]
N VI	$4f_{5/2}$	141.7[b]
N VII	$4f_{7/2}$	136.9[b]
O I	5s	147[a,d]
O II	$5p_{1/2}$	106.4[b]
O III	$5p_{3/2}$	83.3[b]
O IV	$5d_{3/2}$	20.7[b]
O V	$5d_{5/2}$	18.1[b]

Lithium (3)

K	1s	54.7[a]

Lutetium

K	1s	63314
L I	2s	10870
L II	$2p_{1/2}$	10349
L III	$2p_{3/2}$	9244
M I	3s	2491
M II	$3p_{1/2}$	2264
M III	$3p_{3/2}$	2024
M IV	$3d_{3/2}$	1639
M V	$3d_{5/2}$	1589
N I	4s	506.8[a]
N II	$4p_{1/2}$	412.4[a]
N III	$4p_{3/2}$	359.2[a]
N IV	$4d_{3/2}$	206.1[a]
N V	$4d_{5/2}$	196.3[a]
N VI	$4f_{5/2}$	8.9[a]
N VII	$4f_{7/2}$	7.5[a]
O I	5s	57.3[a]
O II	$5p_{1/2}$	33.6[a]
O III	$5p_{3/2}$	26.7[a]

Magnesium (12)

K	1s	1303.0[b]
L I	2s	88.6[a]
L II	$2p_{1/2}$	49.6[b]
L III	$2p_{3/2}$	49.2[a]

Manganese (25)

K	1s	6539
L I	2s	769.1[b]
L II	$2p_{1/2}$	649.9[b]
L III	$2p_{3/2}$	638.7[b]
M I	3s	82.3[b]
M II	$3p_{1/2}$	47.2[b]
M III	$3p_{3/2}$	47.2[b]

Mercury (80)

K	1s	83102
L I	2s	14839
L II	$2p_{1/2}$	14209
L III	$2p_{3/2}$	12284
M I	3s	3562
M II	$3p_{1/2}$	3279
M III	$3p_{3/2}$	2847
M IV	$3d_{3/2}$	2385
M V	$3d_{5/2}$	2295
N I	4s	802.2[b]
N II	$4p_{1/2}$	680.2[b]
N III	$4p_{3/2}$	576.6[b]
N IV	$4d_{3/2}$	378.2[b]
N V	$4d_{5/2}$	358.8[b]
N VI	$4f_{5/2}$	104.0[b]
N VII	$4f_{7/2}$	99.9[b]
O I	5s	127[b]
O II	$5p_{3/2}$	83.1[b]
O III	$5p_{3/2}$	64.5[b]
O IV	$5d_{3/2}$	9.6[b]
O V	$5d_{5/2}$	7.8[b]

Molybdenum (42)

K	1s	20000
L I	2s	2866
L II	$2p_{1/2}$	2625
L III	$2p_{3/2}$	2520
M I	3s	506.3[b]
M II	$3p_{1/2}$	411.6[b]
M III	$3p_{3/2}$	394.0[b]
M IV	$3d_{3/2}$	231.1[b]
M V	$3d_{5/2}$	227.9[b]
N I	4s	63.2[b]
N II	$4p_{1/2}$	37.6[b]
N III	$4p_{3/2}$	35.5[b]

Neodymium (60)

K	1s	43569
L I	2s	7126
L II	$2p_{1/2}$	6722
L III	$2p_{3/2}$	6208
M I	3s	1575
M II	$3p_{1/2}$	1403
M III	$3p_{3/2}$	1297
M IV	$3d_{3/2}$	1003.3[a]
M V	$3d_{5/2}$	980.4[a]
N I	4s	319.2[a]
N II	$4p_{1/2}$	243.3
N III	$4p_{3/2}$	224.6
N IV	$4d_{3/2}$	120.5[a]
N V	$4d_{5/2}$	120.5[a]
N VI	$4f_{5/2}$	1.5
N VII	$4f_{7/2}$	1.5
O I	5s	37.5
O II	$5p_{1/2}$	21.1
O III	$5p_{3/2}$	21.1

Neon (10)

K	1s	870.2[a]
L I	2s	48.5[a]
L II	$2p_{1/2}$	21.7[a]
L III	$2p_{3/2}$	21.6[a]

Nickel (28)

K	1s	8333
L I	2s	1008.6[b]
L II	$2p_{1/2}$	870.0[b]
L III	$2p_{3/2}$	852.7[b]
M I	3s	110.8[b]
M II	$3p_{1/2}$	68.0[b]
M III	$3p_{3/2}$	66.2[b]

Niobium (41)

K	1s	18986
L I	2s	2698
L II	$2p_{1/2}$	2465
L III	$2p_{3/2}$	2371
M I	3s	466.6[b]
M II	$3p_{1/2}$	376.1[b]
M III	$3p_{3/2}$	360.6[b]
M IV	$3d_{3/2}$	205.0[b]
M V	$3d_{5/2}$	202.3[b]
N I	4s	56.4[b]
N II	$4p_{1/2}$	32.6[b]
N III	$4p_{3/2}$	30.8[b]

Nitrogen (7)

K	1s	409.9[a]
L I	2s	37.3[a]

Osmium (76)

K	1s	73871
L I	2s	12968
L II	$2p_{1/2}$	12385
L III	$2p_{3/2}$	10871
M I	3s	3049
M II	$3p_{1/2}$	2792
M III	$3p_{3/2}$	2457
M IV	$3d_{3/2}$	2031
M V	$3d_{5/2}$	1960
N I	4s	658.2[b]
N II	$4p_{1/2}$	549.1[b]
N III	$4p_{3/2}$	470.7[b]
N IV	$4d_{3/2}$	293.1[b]
N V	$4d_{5/2}$	278.5[b]
N VI	$4f_{5/2}$	53.4[b]
N VII	$4f_{7/2}$	50.7[b]
O I	5s	84[a]
O II	$5p_{1/2}$	58[a]

O III	$5p_{3/2}$	44.5[b]

Oxygen (8)

K	1s	543.1[a]
L I	2s	41.6[a]

Palladium (46)

K	1s	24350
L I	2s	3604
L II	$2p_{1/2}$	3330
L III	$2p_{3/2}$	3173
M I	3s	671.6[b]
M II	$3p_{1/2}$	559.9[b]
M III	$3p_{3/2}$	532.3[b]
M IV	$3d_{3/2}$	340.5[b]
M V	$3d_{5/2}$	335.2[b]
N I	4s	87.1[a,d]
N II	$4p_{1/2}$	55.7[b,c]
N III	$4p_{3/2}$	50.9[b,c]

Phosphorus (15)

K	1s	2145.5
L I	2s	189[a]
L II	$2p_{1/2}$	136[a]
L III	$2p_{3/2}$	135[a]

Platinum (78)

K	1s	78395
L I	2s	13880
L II	$2p_{1/2}$	13273
L III	$2p_{3/2}$	11564
M I	3s	3296
M II	$3p_{1/2}$	3027
M III	$3p_{3/2}$	2645
M IV	$3d_{3/2}$	2202
M V	$3d_{5/2}$	2122
N I	4s	725.4[b]
N II	$4p_{1/2}$	609.1[b]
N III	$4p_{3/2}$	519.4[b]
N IV	$4d_{3/2}$	331.6[b]
N V	$4d_{5/2}$	314.6[b]
N VI	$4f_{5/2}$	74.5[b]
N VII	$4f_{7/2}$	71.2[b]
O I	5s	101.7[a,d]
O II	$5p_{1/2}$	65.3[a,b]
O III	$5p_{3/2}$	51.7[b]

Polonium (84)

K	1s	93105
L I	2s	16939
L II	$2p_{1/2}$	16244
L III	$2p_{3/2}$	13814
M I	3s	4149
M II	$3p_{1/2}$	3854
M III	$3p_{3/2}$	3302
M IV	$3d_{3/2}$	2798
M V	$3d_{5/2}$	2683
N I	4s	995[a]
N II	$4p_{1/2}$	851[a]
N III	$4p_{3/2}$	705[a]
N IV	$4d_{3/2}$	500[a]
N V	$4d_{5/2}$	473[a]
N VI	$4f_{5/2}$	184[a]
N VII	$4f_{7/2}$	184[a]
O I	5s	177[a]
O II	$5p_{1/2}$	132[a]
O III	$5p_{3/2}$	104[a]
O IV	$5d_{3/2}$	31[a]
O V	$5d_{5/2}$	31[a]

Potassium (19)

K	1s	3608.4[a]
L I	2s	378.6[a]
L II	$2p_{1/2}$	297.3[a]
L III	$2p_{3/2}$	294.6[a]
M I	3s	34.8[a]
M II	$3p_{1/2}$	18.3[a]
M III	$3p_{3/2}$	18.3[a]

Praseodymium (59)

K	1s	41991
L I	2s	6835
L II	$2p_{1/2}$	6440
L III	$2p_{3/2}$	5964
M I	3s	1511
M II	$3p_{1/2}$	1337
M III	$3p_{3/2}$	1242
M IV	$3d_{3/2}$	948.3[a]
M V	$3d_{5/2}$	928.8[a]
N I	4s	304.5
N II	$4p_{1/2}$	236.3
N III	$4p_{3/2}$	217.6
N IV	$4d_{3/2}$	115.1[a]
N V	$4d_{5/2}$	115.1[a]
N VI	$4f_{5/2}$	2.0
N VII	$4f_{7/2}$	2.0
O I	5s	37.4
O II	$5p_{1/2}$	22.3
O III	$5p_{3/2}$	22.3

Promethium (61)

K	1s	45184
L I	2s	7428
L II	$2p_{1/2}$	7013
L III	$2p_{3/2}$	6459
M I	3s	—
M II	$3p_{1/2}$	1471.4
M III	$3p_{3/2}$	1357
M IV	$3d_{3/2}$	1052
M V	$3d_{5/2}$	1027
N I	4s	—
N II	$4p_{1/2}$	242
N III	$4p_{3/2}$	242
N IV	$4d_{3/2}$	120
N V	$4d_{5/2}$	120

Protactinium (91)

K	1s	112601
L I	2s	21105
L II	$2p_{1/2}$	20314
L III	$2p_{3/2}$	16733
M I	3s	5367
M II	$3p_{1/2}$	5001
M III	$3p_{3/2}$	4174
M IV	$3d_{3/2}$	3611
M V	$3d_{5/2}$	3442
N I	4s	1387[a]
N II	$4p_{1/2}$	1224[a]
N III	$4p_{3/2}$	1007[a]
N IV	$4d_{3/2}$	743[a]
N V	$4d_{5/2}$	708[a]
N VI	$4f_{5/2}$	371[a]
N VII	$4f_{7/2}$	360[a]
O I	5s	310[a]
O II	$5p_{1/2}$	232[a]
O III	$5p_{3/2}$	232[a]
O IV	$5d_{3/2}$	94[a]
O V	$5d_{5/2}$	94[a]
P I	6s	—
P II	$6p_{1/2}$	—
P III	$6p_{3/2}$	—

Radium (88)

K	1s	103922
L I	2s	19237
L II	$2p_{1/2}$	18484
L III	$2p_{3/2}$	15444
M I	3s	4822
M II	$3p_{1/2}$	4490
M III	$3p_{3/2}$	3792
M IV	$3d_{3/2}$	3248
M V	$3d_{5/2}$	3105
N I	4s	1208[a]
N II	$4p_{1/2}$	1058
N III	$4p_{3/2}$	879[a]
N IV	$4d_{3/2}$	636[a]
N V	$4d_{5/2}$	603[a]
N VI	$4f_{5/2}$	299[a]
N VII	$4f_{7/2}$	299[a]
O I	5s	254[a]
O II	$5p_{1/2}$	200[a]
O III	$5p_{3/2}$	153[a]
O IV	$5d_{3/2}$	68[a]
O V	$5d_{5/2}$	68[a]
P I	6s	44
P II	$6p_{1/2}$	19
P III	$6p_{3/2}$	19

Radon (86)

K	1s	98404
L I	2s	18049
L II	$2p_{1/2}$	17337
L III	$2p_{3/2}$	14619
M I	3s	4482
M II	$3p_{1/2}$	4159
M III	$3p_{3/2}$	3538
M IV	$3d_{3/2}$	3022
M V	$3d_{5/2}$	2892
N I	4s	1097[a]
N II	$4p_{1/2}$	929[a]
N III	$4p_{3/2}$	768[a]
N IV	$4d_{3/2}$	567[a]
N V	$4d_{5/2}$	541[a]
N VI	$4f_{5/2}$	238[a]
N VII	$4f_{7/2}$	238[a]
O I	5s	214[a]
O II	$5p_{1/2}$	164[a]
O III	$5p_{3/2}$	127[a]
O IV	$5d_{3/2}$	48[a]
O V	$5d_{5/2}$	48[a]
P I	6s	26

Rhenium (75)

K	1s	71676
L I	2s	12527
L II	$2p_{1/2}$	11959
L III	$2p_{3/2}$	10535
M I	3s	2932
M II	$3p_{1/2}$	2682
M III	$3p_{3/2}$	2367
M IV	$3d_{3/2}$	1949
M V	$3d_{5/2}$	1883
N I	4s	625.4[b]
N II	$4p_{1/2}$	518.7[b]
N III	$4p_{3/2}$	446.8[b]
N IV	$4d_{3/2}$	273.9[b]
N V	$4d_{5/2}$	260.5[b]
N VI	$4f_{5/2}$	42.9[a]
N VII	$4f_{7/2}$	40.5[a]
O I	5s	83[b]
O II	$5p_{1/2}$	45.6[b]
O III	$5p_{3/2}$	34.6[a,d]

Rhodium (45)

K	1s	23220
L I	2s	3412
L II	$2p_{1/2}$	3146
L III	$2p_{3/2}$	3004
M I	3s	628.1[b]
M II	$3p_{1/2}$	521.3[b]
M III	$3p_{3/2}$	496.5[b]
M IV	$3d_{3/2}$	311.9[b]
M V	$3d_{5/2}$	307.2[b]
N I	4s	81.4[a,d]
N II	$4p_{1/2}$	50.5[b]
N III	$4p_{3/2}$	47.3[b]

Rubidium (37)

K	1s	15200
L I	2s	2065
L II	$2p_{1/2}$	1864
L III	$2p_{3/2}$	1804
M I	3s	326.7[a]
M II	$3p_{1/2}$	248.7[a]
M III	$3p_{3/2}$	239.1[a]
M IV	$3d_{3/2}$	113.0[a]
M V	$3d_{5/2}$	112[a]
N I	4s	30.5[a]
N II	$4p_{1/2}$	16.3[a]
N III	$4p_{3/2}$	15.3[a]

Ruthenium (44)

K	1s	22117
L I	2s	3224
L II	$2p_{1/2}$	2967
L III	$2p_{3/2}$	2838
M I	3s	586.2[b]
M II	$3p_{1/2}$	483.3[b]
M III	$3p_{3/2}$	461.5[b]
M IV	$3d_{3/2}$	284.2[b]
M V	$3d_{5/2}$	280.0[b]
N I	4s	75.0[b]
N II	$4p_{1/2}$	46.5[b]
N III	$4p_{3/2}$	43.2[b]

Samarium (62)

K	1s	46834
L I	2s	7737
L II	$2p_{1/2}$	7312

L III	$2p_{3/2}$	6716
M I	3s	1723
M II	$3p_{1/2}$	1541
M III	$3p_{3/2}$	1419.8
M IV	$3d_{3/2}$	1110.9[a]
M V	$3d_{5/2}$	1083.4[a]
N I	4s	347.2[a]
N II	$4p_{1/2}$	265.6
N III	$4p_{3/2}$	247.4
N IV	$4d_{3/2}$	129.0
N V	$4d_{5/2}$	129.0
N VI	$4f_{5/2}$	5.2
N VII	$4f_{7/2}$	5.2
O I	5s	37.4
O II	$5p_{1/2}$	21.3
O III	$5p_{3/2}$	21.3

Scandium (21)

K	1s	4492
L I	2s	498.0[a]
L II	$2p_{1/2}$	403.6[a]
L III	$2p_{3/2}$	389.7[a]
M I	3s	51.1[a]
M II	$3p_{1/2}$	28.3[a]
M III	$3p_{3/2}$	28.3[a]

Selenium (34)

K	1s	12658
L I	2s	1652.0[a,d]
L II	$2p_{1/2}$	1474.3[a,d]
L III	$2p_{3/2}$	1433.9[a,d]
M I	3s	229.6[a]
M II	$3p_{1/2}$	166.5[a]
M III	$3p_{3/2}$	160.7[a]
M IV	$3d_{3/2}$	55.5[a]
M V	$3d_{5/2}$	54.6[a]

Silicon (14)

K	1s	1839
L I	2s	149.7[a,d]
L II	$2p_{1/2}$	99.8[a]
L III	$2p_{3/2}$	99.2[a]

Silver (47)

K	1s	25514
L I	2s	3806
L II	$2p_{1/2}$	3524
L III	$2p_{3/2}$	3351
M I	3s	719.0[b]
M II	$3p_{1/2}$	603.8[b]
M III	$3p_{3/2}$	573.0[b]
M IV	$3d_{3/2}$	374.0[b]
M V	$3d_{5/2}$	368.0[b]
N I	4s	97.0[b]
N II	$4p_{1/2}$	63.7[b]
N III	$4p_{3/2}$	58.3[b]

Sodium (11)

K	1s	1070.8[b]
L I	2s	63.5[b]
L II	$2p_{1/2}$	30.4[b]
L III	$2p_{3/2}$	30.5[a]

Strontium (38)

K	1s	16105
L I	2s	2216
L II	$2p_{1/2}$	2007
L III	$2p_{3/2}$	1940
M I	3s	358.7[b]
M II	$3p_{1/2}$	280.3[b]
M III	$3p_{3/2}$	270.0[b]
M IV	$3d_{3/2}$	136.0[b]
M V	$3d_{5/2}$	134.2[b]
N I	4s	38.9[b]
N II	$4p_{1/2}$	21.6[b]
N III	$4p_{3/2}$	20.1[b]

Sulfur (16)

K	1s	2472
L I	2s	230.9[a,d]
L II	$2p_{1/2}$	163.6[a]
L III	$2p_{3/2}$	162.5[a]

Tantalum (73)

K	1s	67416
L I	2s	11682
L II	$2p_{1/2}$	11136
L III	$2p_{3/2}$	9881
M I	3s	2708
M II	$3p_{1/2}$	2469
M III	$3p_{3/2}$	2194
M IV	$3d_{3/2}$	1793
M V	$3d_{5/2}$	1735
N I	4s	563.4[b]
N II	$4p_{1/2}$	463.4[b]
N III	$4p_{3/2}$	400.9[b]
N IV	$4d_{3/2}$	237.9[b]
N V	$4d_{5/2}$	226.4[b]
N VI	$4f_{5/2}$	23.5[b]
N VII	$4f_{7/2}$	21.6[b]
O I	5s	69.7[b]
O II	$5p_{1/2}$	42.2[a]
O III	$5p_{3/2}$	32.7[b]

Technetium (43)

K	1s	21044
L I	2s	3043
L II	$2p_{1/2}$	2793
L III	$2p_{3/2}$	2677
M I	3s	586.1[a]
M II	$3p_{1/2}$	447.6[a]
M III	$3p_{3/2}$	417.7[a]
M IV	$3d_{3/2}$	257.6[a]
M V	$3d_{5/2}$	253.9[a]
N I	4s	69.5[a]
N II	$4p_{1/2}$	42.3[a]
N III	$4p_{3/2}$	39.9[a]

Tellurium (52)

K	1s	31814
L I	2s	4939
L II	$2p_{1/2}$	4612
L III	$2p_{3/2}$	4341
M I	3s	1006[b]
M II	$3p_{1/2}$	870.8[b]
M III	$3p_{3/2}$	820.0[b]
M IV	$3d_{3/2}$	583.4[b]
M V	$3d_{5/2}$	573.0[b]
N I	4s	169.4[b]
N II	$4p_{1/2}$	103.3[b,c]
N III	$4p_{3/2}$	103.3[b,c]
N IV	$4d_{3/2}$	41.9[b]
N V	$4d_{5/2}$	40.4[b]

Terbium (65)

K	1s	51996
L I	2s	8708
L II	$2p_{1/2}$	8252
L III	$2p_{3/2}$	7514
M I	3s	1968
M II	$3p_{1/2}$	1768
M III	$3p_{3/2}$	1611
M IV	$3d_{3/2}$	1267.9[a]
M V	$3d_{5/2}$	1241.1[a]
N I	4s	396.0[a]
N II	$4p_{1/2}$	322.4[a]
N III	$4p_{3/2}$	284.1[a]
N IV	$4d_{3/2}$	150.5[a]
N V	$4d_{5/2}$	150.5[a]
N VI	$4f_{5/2}$	7.7[a]
N VII	$4f_{7/2}$	2.4[a]
O I	5s	45.6[a]
O II	$5p_{1/2}$	28.7[a]
O III	$5p_{3/2}$	22.6[a]

Thallium (81)

K	1s	85530
L I	2s	15347
L II	$2p_{1/2}$	14698
L III	$2p_{3/2}$	12658
M I	3s	3704
M II	$3p_{1/2}$	3416
M III	$3p_{3/2}$	2957
M IV	$3d_{3/2}$	2485
M V	$3d_{5/2}$	2389
N I	4s	846.2[b]
N II	$4p_{1/2}$	720.5[b]
N III	$4p_{3/2}$	609.5[b]
N IV	$4d_{3/2}$	405.7[b]
N V	$4d_{5/2}$	385.0[b]
N VI	$4f_{5/2}$	122.2[b]
N VII	$4f_{7/2}$	117.8[b]
O I	5s	136[a,d]
O II	$5p_{1/2}$	94.6[b]
O III	$5p_{3/2}$	73.5[b]
O IV	$5d_{3/2}$	14.7[b]
O V	$5d_{5/2}$	12.5[b]

Thorium (90)

K	1s	109651
L I	2s	20472
L II	$2p_{1/2}$	19693
L III	$2p_{3/2}$	16300
M I	3s	5182
M II	$3p_{1/2}$	4830
M III	$3p_{3/2}$	4046
M IV	$3d_{3/2}$	3491
M V	$3d_{5/2}$	3332
N I	4s	1330[a]
N II	$4p_{1/2}$	1168[a]
N III	$4p_{3/2}$	966.4[b]
N IV	$4d_{3/2}$	712.1[b]
N V	$4d_{5/2}$	675.2[b]
N VI	$4f_{5/2}$	342.4[b]
N VII	$4f_{7/2}$	333.1[b]
O I	5s	290[a,c]
O II	$5p_{1/2}$	229[a,c]
O III	$5p_{3/2}$	182[a,c]
O IV	$5d_{3/2}$	92.5[b]
O V	$5d_{5/2}$	85.4[b]
P I	6s	41.4[b]
P II	$6p_{1/2}$	24.5[b]
P III	$6p_{3/2}$	16.6[b]

Thulium (69)

K	1s	59390
L I	2s	10116
L II	$2p_{1/2}$	9617
L III	$2p_{3/2}$	8648
M I	3s	2307
M II	$3p_{1/2}$	2090
M III	$3p_{3/2}$	1885
M IV	$3d_{3/2}$	1515
M V	$3d_{5/2}$	1468
N I	4s	470.9[a]
N II	$4p_{1/2}$	385.9[a]
N III	$4p_{3/2}$	332.6[a]
N IV	$4d_{3/2}$	175.5[a]
N V	$4d_{5/2}$	175.5[a]
N VI	$4f_{5/2}$	—
N VII	$4f_{7/2}$	4.6
O I	5s	54.7[a]
O II	$5p_{1/2}$	31.8[a]
O III	$5p_{3/2}$	25.0[a]

Tin (50)

K	1s	29200
L I	2s	4465
L II	$2p_{1/2}$	4156
L III	$2p_{3/2}$	3929
M I	3s	884.7[b]
M II	$3p_{1/2}$	756.5[b]
M III	$3p_{3/2}$	714.6[b]
M IV	$3d_{3/2}$	493.2[b]
M V	$3d_{5/2}$	484.9[b]
N I	4s	137.1[b]
N II	$4p_{1/2}$	83.6[b,c]
N III	$4p_{3/2}$	83.6[b,c]
N IV	$4d_{3/2}$	24.9[b]
N V	$4d_{5/2}$	23.9[b]

Titanium (22)

K	1s	4966
L I	2s	560.9[b]
L II	$2p_{1/2}$	460.2[b]
L III	$2p_{3/2}$	453.8[b]
M I	3s	58.7[b]
M II	$3p_{1/2}$	32.6[b]
M III	$3p_{3/2}$	32.6[b]

Tungsten (74)

K	1s	69525
L I	2s	12100
L II	$2p_{1/2}$	11544
L III	$2p_{3/2}$	10207
M I	3s	2820
M II	$3p_{1/2}$	2575
M III	$3p_{3/2}$	2281
M IV	$3d_{3/2}$	1949

M V	$3d_{5/2}$	1809
N I	4s	594.1[b]
N II	$4p_{1/2}$	490.4[b]
N III	$4p_{3/2}$	423.6[b]
N IV	$4d_{3/2}$	255.9[b]
N V	$4d_{5/2}$	243.5[b]
N VI	$4f_{5/2}$	33.6[a]
N VII	$4f_{7/2}$	31.4[b]
O I	5s	75.6[b]
O II	$5p_{1/2}$	453[a,d]
O III	$5p_{3/2}$	36.8[b]

Uranium (92)

K	1s	115606
L I	2s	21757
L II	$2p_{1/2}$	20948
L III	$2p_{3/2}$	17166
M I	3s	5548
M II	$3p_{1/2}$	5182
M III	$3p_{3/2}$	4303
M IV	$3d_{3/2}$	3728
M V	$3d_{5/2}$	3552
N I	4s	1439[a,d]
N II	$4p_{1/2}$	1271[a,d]
N III	$4p_{3/2}$	1043[b]
N IV	$4d_{3/2}$	778.3[b]
N V	$4d_{5/2}$	736.2[b]
N VI	$4f_{5/2}$	388.2[a]
N VII	$4f_{7/2}$	377.4[b]
O I	5s	321[a,c,d]
O II	$5p_{1/2}$	257[a,c,d]
O III	$5p_{3/2}$	192[a,c,d]
O IV	$5d_{3/2}$	102.8[b]
O V	$5d_{5/2}$	94.2[b]
P I	6s	43.9[b]
P II	$6p_{1/2}$	26.8[b]
P III	$6p_{3/2}$	16.8[b]

Vanadium (23)

K	1s	5465
L I	2s	626.7[b]
L II	$2p_{1/2}$	519.8[b]
L III	$2p_{3/2}$	521.1[b]
M I	3s	66.3[b]
M II	$3p_{1/2}$	37.2[b]
M III	$3p_{3/2}$	37.2[b]

Xenon (54)

K	1s	34561
L I	2s	5453
L II	$2p_{1/2}$	5107
L III	$2p_{3/2}$	4786
M I	3s	1148.7[a]
M II	$3p_{1/2}$	1002.1[a]
M III	$3p_{3/2}$	940.6[a]
M IV	$3d_{3/2}$	689.0[a]
M V	$3d_{5/2}$	676.4[a]
N I	4s	213.2[a]
N II	$4p_{1/2}$	146.7
N III	$4p_{3/2}$	145.5[a]
N IV	$4d_{3/2}$	69.5[a]
N V	$4d_{5/2}$	67.5[a]
N VI	$4f_{5/2}$	—
N VII	$4f_{7/2}$	—
O I	5s	23.3[a]
O II	$5p_{1/2}$	13.4[a]
O III	$5p_{3/2}$	12.1[a]

Ytterbium (70)

K	1s	61332
L I	2s	10486
L II	$2p_{1/2}$	9978
L III	$2p_{3/2}$	8944
M I	3s	2398
M II	$3p_{1/2}$	2173
M III	$3p_{3/2}$	1950
M IV	$3d_{3/2}$	1576
M V	$3d_{5/2}$	1528
N I	4s	480.5[a]
N II	$4p_{1/2}$	388.7[a]
N III	$4p_{3/2}$	339.7[a]
N IV	$4d_{3/2}$	191.2[a]
N V	$4d_{5/2}$	182.4[a]
N VI	$4f_{5/2}$	2.5[a]
N VII	$4f_{7/2}$	1.3[a]
O I	5s	52.0[a]
O II	$5p_{1/2}$	30.3[a]
O III	$5p_{3/2}$	24.1[a]

Yttrium (39)

K	1s	17038
L I	2s	2373
L II	$2p_{1/2}$	2156
L III	$2p_{3/2}$	2080
M I	3s	392.0[a,d]
M II	$3p_{1/2}$	310.6[a]
M III	$3p_{3/2}$	298.8[a]
M IV	$3d_{3/2}$	157.7[b]
M V	$3d_{5/2}$	155.8[b]
N I	4s	43.8[a]
N II	$4p_{1/2}$	24.4[a]
N III	$4p_{3/2}$	23.1[a]

Zinc (30)

K	1s	9659
L I	2s	1196.2[a]
L II	$2p_{1/2}$	1044.9[a]
L III	$2p_{3/2}$	1021.8[a]
M I	3s	139.8[a]
M II	$3p_{1/2}$	91.4[a]
M III	$3p_{3/2}$	88.6[a]
M IV	$3d_{3/2}$	10.2[a]
M V	$3d_{5/2}$	10.1[a]

Zirconium (40)

K	1s	17998
L I	2s	2532
L II	$2p_{1/2}$	2307
L III	$2p_{3/2}$	2223
M I	3s	430.3[b]
M II	$3p_{1/2}$	343.5[b]
M III	$3p_{3/2}$	329.8[b]
M IV	$3d_{3/2}$	181.1[b]
M V	$3d_{5/2}$	178.8[b]
N I	4s	50.6[b]
N II	$4p_{1/2}$	28.5[b]
N III	$4p_{3/2}$	27.1[b]

[a] Reference 1.
[b] Reference 2 (remaining values from Reference 3).
[c] One-particle approximation not valid.
[d] Derived using energy differences from Reference 3.

NATURAL WIDTH OF X-RAY LINES

Natural widths of K X-ray lines in eV:

Element	$K\alpha_1$	$K\alpha_2$	$K\beta_1$	$K\beta_3$
Ca	1.00	0.98		
Ti	1.45	2.13		
Cr	2.05	2.64		
Fe	2.45	3.20		
Ni	3.00	3.70		
Zn	3.40	3.96		
Ge	3.75	4.18		
Se	4.10	4.43		
Kr	4.23	4.62		
Sr	5.17	4.97		
Zr	5.70	5.25		
Mo	6.82	6.80		
Ru	7.41	7.96		
Pd	8.80	9.20		
Cd	9.80	10.40		
Sn	11.20	12.40	11.80	11.00
Te	12.80	14.20	13.30	13.10
Xe	14.20	15.10	15.30	14.50
Ba	16.10	16.80	18.15	16.70

Element	$K\alpha_1$	$K\alpha_2$	$K\beta_1$	$K\beta_3$
Ce	18.60	19.50	20.60	18.60
Nd	21.50	21.50	23.25	21.33
Sm	26.00	24.70	25.65	24.65
Gd	29.50	28.00	29.37	28.00
Dy	33.90	32.20	32.73	32.00
Er	35.00	35.50	36.20	35.70
Yb	38.80	40.60	41.43	41.15
Hf	42.70	44.30	46.00	46.10
W	46.80	48.00	51.83	51.50
Os	49.00	49.40	55.90	55.95
Pt	54.10	54.30	59.98	62.13
Hg	64.75	68.20	65.75	68.95
Pb	67.10	72.30	72.20	73.80
Po	73.20	75.10	78.60	80.10
Rn	80.00	81.50	85.50	86.50
Ra	87.00	88.20	94.20	95.50
Th	94.70	95.00	99.70	101.00
U	103.00	104.30	105.00	107.30

From Salem, S. I. and Lee, P. L., *At. Data Nucl. Data Tables*, 18, 233, 1976.

Natural widths of L X-ray lines in eV:

Element	$L\alpha_1$	$L\alpha_2$	$L\beta_1$	$L\beta_2$	$L\beta_3$	$L\beta_4$	$L\gamma_1$
Zr	1.68	1.52	1.87	5.13	5.50	5.60	3.34
Mo	1.86	1.80	2.03	5.30	5.90	5.78	3.76
Ru	2.03	1.98	2.18	5.45	6.35	5.96	4.15
Pd	2.21	2.16	2.36	5.63	6.80	6.18	4.50
Gd	2.43	2.40	2.54	5.82	7.23	6.28	4.83
Sn	2.62	2.62	2.75	6.10	7.70	6.60	5.23
Tc	2.88	2.88	2.96	6.25	8.22	6.82	5.60
Xe	3.15	3.15	3.20	6.43	8.70	7.15	5.95
Ba	3.39	3.45	3.45	6.70	9.20	7.42	6.35
Ce	3.70	3.78	3.73	6.86	9.70	7.82	6.75
Nd	3.93	4.08	4.00	7.18	10.30	8.15	7.16
Sm	4.13	4.50	4.33	7.42	10.80	8.60	7.50
Cd	4.46	4.90	4.63	7.70	11.20	9.08	7.83
Dy	4.81	5.35	5.03	7.90	11.50	9.60	8.30
Er	5.17	5.73	5.45	8.28	11.85	10.03	8.75
Yb	5.40	6.22	5.90	8.58	12.20	11.00	9.20
Hf	5.83	6.70	6.36	8.92	12.40	12.80	9.63
W	6.50	7.20	6.90	9.06	13.10	14.60	10.20
Os	7.04	7.70	7.42	9.60	14.60	16.50	10.65
Pt	7.60	8.28	8.00	9.95	16.10	18.00	11.20
Hg	8.10	8.80	8.70	10.40	17.40	19.70	11.80
Pb	8.82	9.35	9.35	10.75	18.65	21.30	12.30
Po	9.50	9.95	10.10	11.25	19.90	22.70	13.05
Rn	10.03	10.50	10.65	11.65	21.00	24.00	13.55
Ra	11.00	11.20	11.60	12.20	22.00	25.20	14.30
Th	11.90	11.80	12.40	12.80	22.85	26.35	15.00
U	12.40	12.40	13.50	13.30	23.70	27.50	15.70
Pu	13.20	13.00	14.10	13.90	24.10	28.30	16.40
Cm	14.80	13.60	15.70	14.60	25.00	29.40	17.10

PHOTON ATTENUATION COEFFICIENTS

Martin J. Berger and John H. Hubbell

This table gives mass attenuation coefficients for photons for all elements at energies between 1 keV (soft x-rays) and 1 GeV (hard gamma rays). The mass attenuation coefficient μ describes the attenuation of radiation as it passes through matter by the relation

$$I(x)/I_o = e^{-\mu\rho x}$$

where I_o is the initial intensity, $I(x)$ the intensity after path length x, and ρ is the mass density of the element in question. To a high approximation the mass attenuation coefficient is additive for the elements present, independent of the way in which they are bound in chemical compounds.

The power of ten is indicated beside each number in the table; i.e., 7.41 + 03 means 7.41×10^3. A vertical line between two columns indicates that an absorption edge lies between those energy values. The various edges are labeled at the bottom of the table.

The attenuation coefficients were calculated with the computer program XCOM (Reference 1), which uses a cross-section database compiled at the Photon and Charged Particle Data Center at the National Institute of Standards and Technology. Their accuracy has been confirmed at all energies by extensive comparisons with experimental attenuation coefficients. Such comparisons for X-ray energies up to 100 keV can be found in Reference 2.

References

1. Berger, M. J. and Hubbell, J. H., *National Bureau of Standards Report* NBSIR-87-3597, 1987.
2. Saloman, E. B., Hubbell, J. H., and Scofield, J. H., *Atomic Data and Nuclear Data Tables*, 38, 1, 1988.

	Atomic no.	Mass attenuation coefficient, cm^2/g — Photon energy, MeV								
		0.001	**0.002**	**0.005**	**0.01**	**0.02**	**0.05**	**0.1**	**0.2**	**0.5**
H	1	7.21 + 00	1.06 + 00	4.19-01	3.85-01	3.69-01	3.36-01	2.94-01	2.43-01	1.73-01
He	2	6.08 + 01	6.86 + 00	5.77-01	2.48-01	1.96-01	1.70-01	1.49-01	1.22-01	8.71-02
Li	3	2.34 + 02	2.71 + 01	1.62 + 00	3.40-01	1.86-01	1.49-01	1.29-01	1.06-01	7.53-02
Be	4	6.04 + 02	7.47 + 01	4.37 + 00	6.47-01	2.25-01	1.55-01	1.33-01	1.09-01	7.74-02
B	5	1.23 + 03	1.60 + 02	9.68 + 00	1.25 + 00	3.01-01	1.66-01	1.39-01	1.14-01	8.07-02
C	6	2.21 + 03	3.03 + 02	1.91 + 01	2.37 + 00	4.42-01	1.87-01	1.51-01	1.23-01	8.72-02
N	7	3.31 + 03	4.77 + 02	3.14 + 01	3.88 + 00	6.18-01	1.98-01	1.53-01	1.23-01	8.72-02
O	8	4.59 + 03	6.95 + 02	4.79 + 01	5.95 + 00	8.65-01	2.13-01	1.55-01	1.24-01	8.73-02
F	9	5.65 + 03	9.05 + 02	6.51 + 01	8.21 + 00	1.13 + 00	2.21-01	1.50-01	1.18-01	8.27-02
Ne	10	7.41 + 03	1.24 + 03	9.34 + 01	1.20 + 01	1.61 + 00	2.58-01	1.60-01	1.24-01	8.66-02
Na	11	6.54 + 02	1.52 + 03	1.19 + 02	1.56 + 01	2.06 + 00	2.80-01	1.59-01	1.20-01	8.37-02
Mg	12	9.22 + 02	1.93 + 03	1.58 + 02	2.11 + 01	2.76 + 00	3.29-01	1.69-01	1.24-01	8.65-02
Al	13	1.19 + 03	2.26 + 03	1.93 + 02	2.62 + 01	3.44 + 00	3.68-01	1.70-01	1.22-01	8.44-02
Si	14	1.57 + 03	2.78 + 03	2.45 + 02	3.39 + 01	4.46 + 00	4.38-01	1.84-01	1.28-01	8.75-02
P	15	1.91 + 03	3.02 + 02	2.86 + 02	4.04 + 01	5.35 + 00	4.92-01	1.87-01	1.25-01	8.51-02
S	16	2.43 + 03	3.85 + 02	3.49 + 02	5.01 + 01	6.71 + 00	5.85-01	2.02-01	1.30-01	8.78-02
Cl	17	2.83 + 03	4.52 + 02	3.90 + 02	5.73 + 01	7.74 + 00	6.48-01	2.05-01	1.27-01	8.45-02
Ar	18	3.18 + 03	5.12 + 02	4.23 + 02	6.32 + 01	8.63 + 00	7.01-01	2.04-01	1.20-01	7.96-02
K	19	4.06 + 03	6.59 + 02	5.19 + 02	7.91 + 01	1.09 + 01	8.68-01	2.34-01	1.32-01	8.60-02
Ca	20	4.87 + 03	8.00 + 02	6.03 + 02	9.34 + 01	1.31 + 01	1.02 + 00	2.57-01	1.38-01	8.85-02
Sc	21	5.24 + 03	8.70 + 02	6.31 + 02	9.95 + 01	1.41 + 01	1.09 + 00	2.58-01	1.31-01	8.31-02
Ti	22	5.87 + 03	9.86 + 02	6.84 + 02	1.11 + 02	1.59 + 01	1.21 + 00	2.72-01	1.31-01	8.19-02
V	23	6.50 + 03	1.11 + 03	9.29 + 01	1.22 + 02	1.77 + 01	1.35 + 00	2.88-01	1.32-01	8.07-02
Cr	24	7.40 + 03	1.28 + 03	1.08 + 02	1.39 + 02	2.04 + 01	1.55 + 00	3.17-01	1.38-01	8.28-02
Mn	25	8.09 + 03	1.42 + 03	1.21 + 02	1.51 + 02	2.25 + 01	1.71 + 00	3.37-01	1.39-01	8.19-02
Fe	26	9.09 + 03	1.63 + 03	1.40 + 02	1.71 + 02	2.57 + 01	1.96 + 00	3.72-01	1.46-01	8.41-02
Co	27	9.80 + 03	1.78 + 03	1.54 + 02	1.84 + 02	2.80 + 01	2.14 + 00	3.95-01	1.48-01	8.32-02
Ni	28	9.86 + 03	2.05 + 03	1.79 + 02	2.09 + 02	3.22 + 01	2.47 + 00	4.44-01	1.58-01	8.70-02
Cu	29	1.06 + 04	2.15 + 03	1.90 + 02	2.16 + 02	3.38 + 01	2.61 + 00	4.58-01	1.56-01	8.36-02
Zn	30	1.55 + 03	2.37 + 03	2.12 + 02	2.33 + 02	3.72 + 01	2.89 + 00	4.97-01	1.62-01	8.45-02
Ga	31	1.70 + 03	2.52 + 03	2.27 + 02	3.42 + 01	3.93 + 01	3.08 + 00	5.20-01	1.62-01	8.24-02
Ge	32	1.89 + 03	2.71 + 03	2.47 + 02	3.74 + 01	4.22 + 01	3.34 + 00	5.55-01	1.66-01	8.21-02
As	33	2.12 + 03	2.93 + 03	2.71 + 02	4.12 + 01	4.56 + 01	3.63 + 00	5.97-01	1.72-01	8.26-02
Se	34	2.32 + 03	3.10 + 03	2.90 + 02	4.41 + 01	4.82 + 01	3.86 + 00	6.28-01	1.74-01	8.13-02
Br	35	2.62 + 03	3.41 + 03	3.21 + 02	4.91 + 01	5.27 + 01	4.26 + 00	6.86-01	1.84-01	8.33-02
Kr	36	2.85 + 03	3.60 + 03	3.43 + 02	5.26 + 01	5.55 + 01	4.52 + 00	7.22-01	1.87-01	8.23-02
Rb	37	3.17 + 03	3.41 + 03	3.74 + 02	5.77 + 01	5.98 + 01	4.92 + 00	7.80-01	1.96-01	8.36-02
Sr	38	3.49 + 03	2.59 + 03	4.06 + 02	6.27 + 01	6.39 + 01	5.31 + 00	8.37-01	2.04-01	8.44-02
Y	39	3.86 + 03	7.42 + 02	4.42 + 02	6.87 + 01	6.86 + 01	5.76 + 00	9.05-01	2.15-01	8.61-02
Zr	40	4.21 + 03	8.12 + 02	4.76 + 02	7.42 + 01	7.24 + 01	6.17 + 00	9.66-01	2.24-01	8.69-02
Nb	41	4.60 + 03	8.89 + 02	5.13 + 02	8.04 + 01	7.71 + 01	6.64 + 00	1.04 + 00	2.34-01	8.83-02
Mo	42	4.94 + 03	9.60 + 02	5.45 + 02	8.58 + 01	1.31 + 01	7.04 + 00	1.10 + 00	2.42-01	8.85-02
Tc	43	5.36 + 03	1.04 + 03	5.84 + 02	9.23 + 01	1.41 + 01	7.52 + 00	1.17 + 00	2.53-01	8.97-02
Ru	44	5.72 + 03	1.12 + 03	6.17 + 02	9.80 + 01	1.50 + 01	7.92 + 00	1.23 + 00	2.62-01	8.99-02
Rh	45	6.17 + 03	1.21 + 03	6.59 + 02	1.05 + 02	1.61 + 01	8.45 + 00	1.31 + 00	2.74-01	9.13-02
Pd	46	6.54 + 03	1.29 + 03	6.91 + 02	1.11 + 02	1.70 + 01	8.85 + 00	1.38 + 00	2.83-01	9.13-02
Ag	47	7.04 + 03	1.40 + 03	7.39 + 02	1.19 + 02	1.84 + 01	9.45 + 00	1.47 + 00	2.97-01	9.32-02
Cd	48	7.35 + 03	1.47 + 03	7.69 + 02	1.24 + 02	1.92 + 01	9.78 + 00	1.52 + 00	3.04-01	9.25-02
In	49	7.81 + 03	1.58 + 03	8.13 + 02	1.32 + 02	2.04 + 01	1.03 + 01	1.61 + 00	3.17-01	9.37-02
Sn	50	8.16 + 03	1.66 + 03	8.47 + 02	1.38 + 02	2.15 + 01	1.07 + 01	1.68 + 00	3.26-01	9.37-02

L_3 L_1 L_2 **K EDGE**

	Atomic no.	Mass attenuation coefficient, cm^2/g Photon energy, MeV								
		1.0	**2.0**	**5.0**	**10.0**	**20.0**	**50.0**	**100.0**	**500.0**	**1000.0**
H	1	1.26-01	8.77-02	5.05-02	3.25-02	2.15-02	1.42-02	1.19-02	1.14-02	1.16-02
He	2	6.36-02	4.42-02	2.58-02	1.70-02	1.18-02	8.61-03	7.78-03	7.79-03	7.95-03
Li	3	5.50-02	3.83-02	2.26-02	1.53-02	1.11-02	8.68-03	8.21-03	8.61-03	8.87-03
Be	4	5.65-02	3.94-02	2.35-02	1.63-02	1.23-02	1.02-02	9.94-03	1.08-02	1.12-02
B	5	5.89-02	4.11-02	2.48-02	1.76-02	1.37-02	1.19-02	1.19-02	1.32-02	1.37-02
C	6	6.36-02	4.44-02	2.71-02	1.96-02	1.58-02	1.43-02	1.46-02	1.64-02	1.70-02
N	7	6.36-02	4.45-02	2.74-02	2.02-02	1.67-02	1.57-02	1.63-02	1.85-02	1.92-02
O	8	6.37-02	4.46-02	2.78-02	2.09-02	1.77-02	1.71-02	1.79-02	2.06-02	2.13-02
F	9	6.04-02	4.23-02	2.66-02	2.04-02	1.77-02	1.75-02	1.86-02	2.14-02	2.21-02
Ne	10	6.32-02	4.43-02	2.82-02	2.20-02	1.95-02	1.96-02	2.11-02	2.43-02	2.51-02
Na	11	6.10-02	4.28-02	2.75-02	2.18-02	1.97-02	2.03-02	2.19-02	2.53-02	2.62-02
Mg	12	6.30-02	4.43-02	2.87-02	2.31-02	2.13-02	2.23-02	2.42-02	2.81-02	2.90-02
Al	13	6.15-02	4.32-02	2.84-02	2.32-02	2.17-02	2.31-02	2.52-02	2.93-02	3.03-02
Si	14	6.36-02	4.48-02	2.97-02	2.46-02	2.34-02	2.52-02	2.76-02	3.23-02	3.34-02
P	15	6.18-02	4.36-02	2.91-02	2.45-02	2.36-02	2.58-02	2.84-02	3.33-02	3.45-02
S	16	6.37-02	4.50-02	3.04-02	2.59-02	2.53-02	2.79-02	3.08-02	3.62-02	3.75-02
Cl	17	6.13-02	4.33-02	2.95-02	2.55-02	2.52-02	2.81-02	3.11-02	3.67-02	3.80-02
Ar	18	5.76-02	4.07-02	2.80-02	2.45-02	2.45-02	2.76-02	3.07-02	3.62-02	3.75-02
K	19	6.22-02	4.40-02	3.05-02	2.70-02	2.74-02	3.11-02	3.46-02	4.09-02	4.24-02
Ca	20	6.39-02	4.52-02	3.17-02	2.84-02	2.90-02	3.32-02	3.71-02	4.40-02	4.56-02
Sc	21	5.98-02	4.24-02	3.00-02	2.72-02	2.80-02	3.23-02	3.62-02	4.30-02	4.45-02
Ti	22	5.89-02	4.18-02	2.98-02	2.73-02	2.84-02	3.30-02	3.71-02	4.40-02	4.56-02
V	23	5.79-02	4.11-02	2.96-02	2.74-02	2.88-02	3.36-02	3.78-02	4.49-02	4.65-02
Cr	24	5.93-02	4.21-02	3.06-02	2.86-02	3.03-02	3.56-02	4.01-02	4.76-02	4.93-02
Mn	25	5.85-02	4.16-02	3.04-02	2.87-02	3.07-02	3.63-02	4.09-02	4.86-02	5.04-02
Fe	26	5.99-02	4.26-02	3.15-02	2.99-02	3.22-02	3.83-02	4.33-02	5.15-02	5.33-02
Co	27	5.91-02	4.20-02	3.13-02	3.00-02	3.26-02	3.88-02	4.40-02	5.23-02	5.41-02
Ni	28	6.16-02	4.39-02	3.29-02	3.18-02	3.48-02	4.17-02	4.73-02	5.61-02	5.81-02
Cu	29	5.90-02	4.20-02	3.18-02	3.10-02	3.41-02	4.10-02	4.66-02	5.53-02	5.72-02
Zn	30	5.94-02	4.24-02	3.22-02	3.18-02	3.51-02	4.24-02	4.82-02	5.72-02	5.91-02
Ga	31	5.77-02	4.11-02	3.16-02	3.13-02	3.48-02	4.22-02	4.80-02	5.70-02	5.89-02
Ge	32	5.73-02	4.09-02	3.16-02	3.16-02	3.53-02	4.30-02	4.89-02	5.80-02	6.00-02
As	33	5.73-02	4.09-02	3.19-02	3.21-02	3.60-02	4.40-02	5.01-02	5.95-02	6.15-02
Se	34	5.62-02	4.01-02	3.14-02	3.19-02	3.60-02	4.41-02	5.03-02	5.97-02	6.17-02
Br	35	5.73-02	4.09-02	3.23-02	3.29-02	3.74-02	4.60-02	5.24-02	6.22-02	6.43-02
Kr	36	5.63-02	4.02-02	3.20-02	3.28-02	3.74-02	4.61-02	5.26-02	6.25-02	6.46-02
Rb	37	5.69-02	4.06-02	3.25-02	3.36-02	3.85-02	4.75-02	5.43-02	6.45-02	6.67-02
Sr	38	5.71-02	4.08-02	3.29-02	3.41-02	3.93-02	4.87-02	5.56-02	6.61-02	6.83-02
Y	39	5.80-02	4.14-02	3.35-02	3.50-02	4.05-02	5.03-02	5.75-02	6.83-02	7.06-02
Zr	40	5.81-02	4.15-02	3.38-02	3.55-02	4.12-02	5.13-02	5.87-02	6.98-02	7.22-02
Nb	41	5.87-02	4.18-02	3.44-02	3.63-02	4.22-02	5.27-02	6.03-02	7.17-02	7.42-02
Mo	42	5.84-02	4.16-02	3.44-02	3.65-02	4.26-02	5.33-02	6.10-02	7.26-02	7.51-02
Tc	43	5.88-02	4.19-02	3.48-02	3.71-02	4.35-02	5.45-02	6.24-02	7.43-02	7.68-02
Ru	44	5.85-02	4.16-02	3.48-02	3.73-02	4.39-02	5.50-02	6.30-02	7.51-02	7.77-02
Rh	45	5.89-02	4.20-02	3.53-02	3.80-02	4.48-02	5.63-02	6.45-02	7.69-02	7.94-02
Pd	46	5.85-02	4.16-02	3.52-02	3.80-02	4.50-02	5.66-02	6.49-02	7.73-02	8.00-02
Ag	47	5.92-02	4.21-02	3.58-02	3.88-02	4.61-02	5.81-02	6.67-02	7.93-02	8.20-02
Cd	48	5.83-02	4.14-02	3.54-02	3.85-02	4.59-02	5.79-02	6.64-02	7.91-02	8.18-02
In	49	5.85-02	4.15-02	3.56-02	3.90-02	4.65-02	5.88-02	6.75-02	8.04-02	8.32-02
Sn	50	5.80-02	4.11-02	3.55-02	3.90-02	4.66-02	5.90-02	6.78-02	8.07-02	8.35-02

	Atomic no.	Mass attenuation coefficient, cm^2/g — Photon energy, MeV								
		0.001	**0.002**	**0.005**	**0.01**	**0.02**	**0.05**	**0.1**	**0.2**	**0.5**
Sb	51	8.58 + 03	1.77 + 03	8.85 + 02	1.46 + 02	2.27 + 01	1.12 + 01	1.76 + 00	3.38-01	9.45-02
Te	52	8.43 + 03	1.83 + 03	9.01 + 02	1.50 + 02	2.34 + 01	1.14 + 01	1.80 + 00	3.43-01	9.33-02
I	53	9.10 + 03	2.00 + 03	8.43 + 02	1.63 + 02	2.54 + 01	1.23 + 01	1.94 + 00	3.66-01	9.70-02
Xe	54	9.41 + 03	2.09 + 03	6.39 + 02	1.69 + 02	2.65 + 01	1.27 + 01	2.01 + 00	3.76-01	9.70-02
Cs	55	9.37 + 03	2.23 + 03	2.30 + 02	1.79 + 02	2.82 + 01	1.34 + 01	2.12 + 00	3.94-01	9.91-02
ZB	56	8.54 + 03	2.32 + 03	2.41 + 02	1.86 + 02	2.94 + 01	1.38 + 01	2.20 + 00	4.05-01	9.92-02
La	57	9.09 + 03	2.46 + 03	2.58 + 02	1.97 + 02	3.12 + 01	1.45 + 01	2.32 + 00	4.24-01	1.01-01
Ce	58	9.71 + 03	2.61 + 03	2.74 + 02	2.08 + 02	3.31 + 01	1.52 + 01	2.45 + 00	4.45-01	1.04-01
Pr	59	1.06 + 04	2.77 + 03	2.92 + 02	2.21 + 02	3.53 + 01	1.60 + 01	2.59 + 00	4.69-01	1.07-01
Nd	60	6.63 + 03	2.88 + 03	3.06 + 02	2.30 + 02	3.68 + 01	1.65 + 01	2.69 + 00	4.84-01	1.08-01
Pm	61	2.06 + 03	3.05 + 03	3.26 + 02	2.44 + 02	3.92 + 01	1.73 + 01	2.84 + 00	5.10-01	1.12-01
Sm	62	2.11 + 03	3.12 + 03	3.36 + 02	2.50 + 02	4.03 + 01	1.77 + 01	2.90 + 00	5.19-01	1.11-01
Eu	63	2.22 + 03	3.28 + 03	3.54 + 02	2.63 + 02	4.24 + 01	1.85 + 01	3.04 + 00	5.43-01	1.14-01
Gd	64	2.29 + 03	3.36 + 03	3.65 + 02	2.69 + 02	4.36 + 01	3.86 + 00	3.11 + 00	5.54-01	1.14-01
Tb	65	2.40 + 03	3.51 + 03	3.84 + 02	2.82 + 02	4.59 + 01	4.06 + 00	3.25 + 00	5.77-01	1.17-01
Dy	66	2.49 + 03	3.47 + 03	3.99 + 02	2.90 + 02	4.76 + 01	4.23 + 00	3.36 + 00	5.95-01	1.18-01
Ho	67	2.62 + 03	3.59 + 03	4.17 + 02	3.01 + 02	4.98 + 01	4.43 + 00	3.49 + 00	6.18-01	1.20-01
Er	68	2.75 + 03	3.52 + 03	4.36 + 02	3.13 + 02	5.20 + 01	4.63 + 00	3.63 + 00	6.41-01	1.23-01
Tm	69	2.90 + 03	3.69 + 03	4.57 + 02	2.83 + 02	5.45 + 01	4.87 + 00	3.78 + 00	6.68-01	1.26-01
Yb	70	3.02 + 03	3.80 + 03	4.72 + 02	2.94 + 02	5.63 + 01	5.04 + 00	3.88 + 00	6.86-01	1.27-01
Lu	71	3.19 + 03	3.45 + 03	4.94 + 02	2.21 + 02	5.88 + 01	5.28 + 00	4.03 + 00	7.13-01	1.30-01
Hf	72	3.34 + 03	3.60 + 03	5.11 + 02	2.30 + 02	6.09 + 01	5.48 + 00	4.15 + 00	7.34-01	1.32-01
Ta	73	3.51 + 03	3.77 + 03	5.33 + 02	2.38 + 02	6.33 + 01	5.72 + 00	4.30 + 00	7.60-01	1.35-01
W	74	3.68 + 03	3.92 + 03	5.53 + 02	9.69 + 01	6.57 + 01	5.95 + 00	4.44 + 00	7.84-01	1.38-01
Re	75	3.87 + 03	3.77 + 03	5.76 + 02	1.01 + 02	6.84 + 01	6.21 + 00	4.59 + 00	8.12-01	1.41-01
Os	76	4.03 + 03	2.22 + 03	5.93 + 02	1.04 + 02	7.04 + 01	6.41 + 00	4.70 + 00	8.33-01	1.43-01
Ir	77	4.24 + 03	1.03 + 03	6.18 + 02	1.09 + 02	7.32 + 01	6.69 + 00	4.86 + 00	8.63-01	1.46-01
Pt	78	4.43 + 03	1.08 + 03	6.40 + 02	1.13 + 02	7.57 + 01	6.95 + 00	4.99 + 00	8.90-01	1.49-01
Au	79	4.65 + 03	1.14 + 03	6.66 + 02	1.18 + 02	7.88 + 01	7.26 + 00	5.16 + 00	9.22-01	1.53-01
Hg	80	4.83 + 03	1.18 + 03	6.87 + 02	1.22 + 02	8.12 + 01	7.50 + 00	5.28 + 00	9.46-01	1.56-01
Tl	81	5.01 + 03	1.23 + 03	7.07 + 02	1.26 + 02	8.36 + 01	7.75 + 00	5.40 + 00	9.69-01	1.58-01
Pb	82	5.21 + 03	1.29 + 03	7.30 + 02	1.31 + 02	8.64 + 01	8.04 + 00	5.55 + 00	9.99-01	1.61-01
Bi	83	5.44 + 03	1.35 + 03	7.58 + 02	1.36 + 02	8.95 + 01	8.38 + 00	5.74 + 00	1.03 + 00	1.66-01
Po	84	5.72 + 03	1.42 + 03	7.93 + 02	1.43 + 02	9.35 + 01	8.80 + 00	5.99 + 00	1.08 + 00	1.71-01
At	85	5.87 + 03	1.49 + 03	8.25 + 02	1.49 + 02	9.70 + 01	9.19 + 00	6.17 + 00	1.12 + 00	1.77-01
Rn	86	5.83 + 03	1.49 + 03	8.16 + 02	1.48 + 02	9.56 + 01	9.12 + 00	6.09 + 00	1.10 + 00	1.73-01
Fr	87	6.08 + 03	1.56 + 03	8.49 + 02	1.54 + 02	9.93 + 01	9.52 + 00	1.66 + 00	1.14 + 00	1.78-01
Ra	88	6.20 + 03	1.62 + 03	8.74 + 02	1.59 + 02	1.02 + 02	9.85 + 00	1.71 + 00	1.17 + 00	1.82-01
Ac	89	6.47 + 03	1.70 + 03	8.69 + 02	1.65 + 02	1.06 + 02	1.03 + 01	1.79 + 00	1.21 + 00	1.87-01
Th	90	6.61 + 03	1.74 + 03	8.88 + 02	1.69 + 02	9.37 + 01	1.05 + 01	1.83 + 00	1.23 + 00	1.90-01
Pa	91	6.53 + 03	1.83 + 03	8.76 + 02	1.77 + 02	7.03 + 01	1.10 + 01	1.92 + 00	1.29 + 00	1.97-01
U	92	6.63 + 03	1.86 + 03	8.89 + 02	1.79 + 02	7.11 + 01	1.12 + 01	1.95 + 00	1.30 + 00	1.98-01
Np	93	6.95 + 03	1.96 + 03	9.32 + 02	1.87 + 02	7.45 + 01	1.18 + 01	2.05 + 00	1.35 + 00	2.05-01
Pu	94	7.19 + 03	2.04 + 03	9.65 + 02	1.94 + 02	7.71 + 01	1.22 + 01	2.13 + 00	1.39 + 00	2.10-01
Am	95	7.37 + 03	2.10 + 03	9.90 + 02	1.98 + 02	7.93 + 01	1.25 + 01	2.19 + 00	1.42 + 00	2.14-01
Cm	96	7.54 + 03	2.15 + 03	1.02 + 03	2.03 + 02	8.14 + 01	1.28 + 01	2.25 + 00	1.44 + 00	2.18-01
Bk	97	7.84 + 03	2.25 + 03	1.06 + 03	2.10 + 02	8.39 + 01	1.34 + 01	2.35 + 00	1.50 + 00	2.25-01
Cf	98	7.89 + 03	2.31 + 03	9.27 + 02	2.15 + 02	8.58 + 01	1.37 + 01	2.41 + 00	1.52 + 00	2.29-01
Es	99	7.79 + 03	2.40 + 03	9.59 + 02	2.22 + 02	4.01 + 01	1.42 + 01	2.51 + 00	1.57 + 00	2.36-01
Fm	100	7.13 + 03	2.46 + 03	9.77 + 02	2.26 + 02	4.09 + 01	1.45 + 01	2.57 + 00	1.59 + 00	2.39-01

N_5 N_4 N_3 N_2 N_1 M_5 M_4 M_3 M_2 M_1 L_3 L_2 L_1 K EDGE

	Atomic no.	Mass attenuation coefficient, cm^2/g Photon energy, MeV								
		1.0	**2.0**	**5.0**	**10.0**	**20.0**	**50.0**	**100.0**	**500.0**	**1000.0**
Sb	51	5.80-02	4.10-02	3.56-02	3.92-02	4.70-02	5.96-02	6.85-02	8.16-02	8.44-02
Te	52	5.67-02	4.01-02	3.49-02	3.86-02	4.64-02	5.89-02	6.77-02	8.07-02	8.35-02
I	53	5.84-02	4.12-02	3.61-02	4.00-02	4.82-02	6.13-02	7.04-02	8.40-02	8.69-02
Xe	54	5.78-02	4.08-02	3.58-02	3.99-02	4.82-02	6.12-02	7.04-02	8.40-02	8.69-02
Cs	55	5.85-02	4.12-02	3.64-02	4.06-02	4.91-02	6.25-02	7.19-02	8.58-02	8.88-02
ZB	56	5.80-02	4.08-02	3.61-02	4.04-02	4.90-02	6.25-02	7.19-02	8.58-02	8.88-02
La	57	5.88-02	4.12-02	3.66-02	4.11-02	5.00-02	6.37-02	7.34-02	8.76-02	9.06-02
Ce	58	5.96-02	4.18-02	3.73-02	4.19-02	5.10-02	6.52-02	7.50-02	8.96-02	9.27-02
Pr	59	6.07-02	4.24-02	3.80-02	4.29-02	5.23-02	6.68-02	7.69-02	9.19-02	9.50-02
Nd	60	6.07-02	4.24-02	3.81-02	4.30-02	5.26-02	6.72-02	7.74-02	9.25-02	9.56-02
Pm	61	6.19-02	4.31-02	3.88-02	4.40-02	5.38-02	6.89-02	7.94-02	9.48-02	9.81-02
Sm	62	6.11-02	4.24-02	3.83-02	4.35-02	5.34-02	6.84-02	7.88-02	9.41-02	9.73-02
Eu	63	6.19-02	4.28-02	3.88-02	4.42-02	5.42-02	6.96-02	8.02-02	9.57-02	9.90-02
Gd	64	6.12-02	4.23-02	3.84-02	4.38-02	5.38-02	6.91-02	7.97-02	9.51-02	9.83-02
Tb	65	6.20-02	4.27-02	3.89-02	4.45-02	5.47-02	7.03-02	8.11-02	9.67-02	1.00-01
Dy	66	6.20-02	4.26-02	3.90-02	4.46-02	5.49-02	7.06-02	8.15-02	9.72-02	1.00-01
Ho	67	6.26-02	4.29-02	3.93-02	4.50-02	5.55-02	7.14-02	8.24-02	9.83-02	1.02-01
Er	68	6.32-02	4.32-02	3.96-02	4.55-02	5.61-02	7.23-02	8.34-02	9.95-02	1.03-01
Tm	69	6.40-02	4.36-02	4.01-02	4.61-02	5.70-02	7.35-02	8.48-02	1.01-01	1.04-01
Yb	70	6.40-02	4.35-02	4.00-02	4.61-02	5.70-02	7.35-02	8.49-02	1.01-01	1.04-01
Lu	71	6.48-02	4.39-02	4.05-02	4.66-02	5.77-02	7.45-02	8.60-02	1.02-01	1.06-01
Hf	72	6.50-02	4.39-02	4.05-02	4.68-02	5.80-02	7.48-02	8.64-02	1.03-01	1.06-01
Ta	73	6.57-02	4.41-02	4.08-02	4.72-02	5.85-02	7.56-02	8.73-02	1.04-01	1.07-01
W	74	6.62-02	4.43-02	4.10-02	4.75-02	5.89-02	7.62-02	8.80-02	1.05-01	1.08-01
Re	75	6.69-02	4.46-02	4.14-02	4.79-02	5.95-02	7.70-02	8.89-02	1.06-01	1.09-01
Os	76	6.71-02	4.46-02	4.13-02	4.79-02	5.96-02	7.71-02	8.90-02	1.06-01	1.10-01
Ir	77	6.79-02	4.50-02	4.17-02	4.84-02	6.02-02	7.80-02	9.01-02	1.07-01	1.11-01
Pt	78	6.86-02	4.52-02	4.20-02	4.87-02	6.06-02	7.86-02	9.08-02	1.08-01	1.12-01
Au	79	6.95-02	4.57-02	4.24-02	4.93-02	6.14-02	7.95-02	9.19-02	1.09-01	1.13-01
Hg	80	6.99-02	4.57-02	4.25-02	4.94-02	6.15-02	7.98-02	9.22-02	1.10-01	1.13-01
Tl	81	7.03-02	4.58-02	4.25-02	4.94-02	6.16-02	8.00-02	9.24-02	1.10-01	1.14-01
Pb	82	7.10-02	4.61-02	4.27-02	4.97-02	6.21-02	8.06-02	9.31-02	1.11-01	1.15-01
Bi	83	7.21-02	4.66-02	4.32-02	5.03-02	6.28-02	8.15-02	9.42-02	1.12-01	1.16-01
Po	84	7.39-02	4.75-02	4.40-02	5.12-02	6.40-02	8.32-02	9.61-02	1.15-01	1.18-01
At	85	7.54-02	4.82-02	4.46-02	5.20-02	6.49-02	8.44-02	9.76-02	1.16-01	1.20-01
Rn	86	7.30-02	4.65-02	4.30-02	5.01-02	6.26-02	8.14-02	9.42-02	1.12-01	1.16-01
Fr	87	7.45-02	4.72-02	4.36-02	5.08-02	6.35-02	8.26-02	9.56-02	1.14-01	1.18-01
Ra	88	7.53-02	4.75-02	4.38-02	5.10-02	6.38-02	8.31-02	9.61-02	1.15-01	1.19-01
Ac	89	7.69-02	4.82-02	4.44-02	5.17-02	6.47-02	8.43-02	9.75-02	1.16-01	1.20-01
Th	90	7.71-02	4.81-02	4.42-02	5.15-02	6.45-02	8.40-02	9.72-02	1.16-01	1.20-01
Pa	91	7.94-02	4.93-02	4.52-02	5.26-02	6.59-02	8.60-02	9.95-02	1.19-01	1.23-01
U	92	7.90-02	4.88-02	4.46-02	5.19-02	6.51-02	8.49-02	9.83-02	1.17-01	1.21-01
Np	93	8.13-02	4.99-02	4.56-02	5.30-02	6.65-02	8.68-02	1.01-01	1.20-01	1.24-01
Pu	94	8.26-02	5.05-02	4.60-02	5.34-02	6.71-02	8.76-02	1.01-01	1.21-01	1.25-01
Am	95	8.33-02	5.06-02	4.60-02	5.34-02	6.70-02	8.77-02	1.02-01	1.21-01	1.25-01
Cm	96	8.41-02	5.08-02	4.60-02	5.34-02	6.70-02	8.77-02	1.02-01	1.21-01	1.26-01
Bk	97	8.62-02	5.18-02	4.68-02	5.42-02	6.81-02	8.92-02	1.03-01	1.24-01	1.28-01
Cf	98	8.70-02	5.20-02	4.68-02	5.42-02	6.81-02	8.92-02	1.04-01	1.24-01	1.28-01
Es	99	8.89-02	5.28-02	4.74-02	5.48-02	6.89-02	9.04-02	1.05-01	1.25-01	1.29-01
Fm	100	8.94-02	5.28-02	4.72-02	5.45-02	6.86-02	9.00-02	1.05-01	1.25-01	1.29-01

CLASSIFICATION OF ELECTROMAGNETIC RADIATION

Hans Dolezalek

Basic Conversions:
$c = \lambda\nu = \nu/k$;
$\nu = c/\lambda = ck$;
$\lambda = c/\nu = 1/k$;
$k = \nu/c = 1/\lambda$
c = speed of light = 2.99792458×10^8 m/s

Frequency (ν)	Wavelength (λ)	Wave number (k)	Names of bands	Approximate photon energies
3×10^0 — 3×10^1 Hz 3 — 30 Hz	10^8 — 10^7 m 100 — 10 Mm	10^{-8} — 10^{-7} m^{-1} 10 — 100 Gm^{-1}	ELF-(ELF 1), ITU band no. 1	
3×10^1 — 3×10^2 Hz 30 — 300 Hz	10^7 — 10^6 m 10 — 1 Mm	10^{-7} — 10^{-6} m^{-1} 100 Gm^{-1} — 1Mm^{-1}	SLF-(ELF 2), ITU band no. 2, megameter waves	
3×10^2 — 3×10^3 Hz 300 Hz — 3 kHz	10^6 — 10^5 m 1 Mm — 100 km	10^{-6} — 10^{-5} m^{-1} 1 — 10 Mm^{-1}	ULF-(ELF 3), ITU band no. 3	
3×10^3 — 3×10^4 Hz 3 — 30 kHz	10^5 — 10^4 m 100 — 10 km	10^{-5} — 10^{-4} m^{-1} 10 — 100 Mm^{-1}	VLF, ITU band no. 4, myriameter waves	
3×10^4 — 3×10^5 Hz 30 — 300 kHz	10^4 — 10^3 m 10 — 1 km	10^{-4} — 10^{-3} m^{-1} 100 Mm^{-1} — 1 km^{-1}	LF, ITU band no. 5, kilometer waves	
3×10^5 — 3×10^6 Hz 300 kHz — 3 MHz	10^3 —10^2 m 1 km — 100 m	10^{-3} — 10^{-2} m^{-1} 1 — 10 km^{-1}	MF, ITU band no. 6, hectometer waves	
3×10^6 — 3×10^7 Hz 3 — 30 MHz	10^2 — 10^1 m 100 — 10 m	10^{-2} — 10^{-1} m^{-1} 10 — 100 km^{-1}	HF, ITU band no. 7, decameter waves	
3×10^7 — 3×10^8 Hz 30 — 300 MHz	10^1 — 10^0 m 10 — 1 m	10^{-1} — 10^0 m^{-1} 100 km^{-1} — 1 mm^{-1}	VHF, ITU band no. 8, meter waves	
3×10^8 — 3×10^9 Hz 300 MHz — 3 GHz	10^0 — 10^{-1} 1 m — 100 mm	10^0 — 10^1 m^{-1} 1 — 10 m^{-1}	UHF, ITU band no. 9, decimeter waves[a]	
3×10^9 — 3×10^{10} Hz 3 — 30 GHz	10^{-1} — 10^{-2} 100 —10 mm	10^1 — 10^2 m^{-1} 10 — 100 m^{-1}	SHF, ITU band no. 10, centimeter waves[a]	
3×10^{10} — 3×10^{11} Hz 30 — 300 GHz	10^{-2} — 10^{-3} m 10 —1 mm	10^2 — 10^3 m^{-1} 100 m^{-1} — 1 mm^{-1} (1 — 10 cm^{-1})	EHF, ITU band no. 11, millimeter waves	
3×10^{11} — 3×10^{12} Hz 300 GHz — 3 THz	10^{-3} — 10^{-4} 1 mm — 100 μm	10^3 — 10^4 m^{-1} (1 — 10 mm^{-1}) (10 — 100 cm^{-1})	Part of micrometer waves, includes part of far or thermal infrared; ITU band no. 12	
3×10^{12} — 3×10^{13} Hz 3 — 30 THz	10^{-4} — 10^{-5} 100 — 10 μm	10^4 — 10^5 m^{-1} 10 — 100 mm^{-1} (100 — 1000 cm^{-1})	Part of micrometer waves includes part of far (thermal) infrared	
3×10^{13} — 3×10^{14} Hz 30 — 300 THz	10^{-5} — 10^{-6} m 10 — 1 μm (100,000 — 10,000 Å)	10^5 — 10^6 m^{-1} 100 mm^{-1} — 1μm^{-1}	Part of μm waves, part of infrared	(1.6 — 16) × 10^{-20} joule {0.1 — 1 eV}
3×10^{14} — 3×10^{15} Hz 300 THz — 3 PHz	10^{-6} — 10^{-7}m 1 μm — 100 m (10,000 — 1000 Å)	10^6 — 10^7 m^{-1} 1 — 10 μm^{-1}	Near infrared, visible, near ultraviolet	(1.6 — 16) × 10^{-19} joule {1 — 10 eV}
3×10^{15} — 3×10^{16} Hz 3 — 30 PHz	10^{-7} — 10^{-8}m 100 — 10 nm (1000 — 100 Å)	10^7 — 10^8 m^{-1} 10 — 100 μm^{-1}	Part of "vacuum" - ultraviolet	(1.6 — 16) × 10^{-18} joule {10 — 100 eV}
3×10^{16} — 3×10^{17} Hz 30 — 300 PHz	10^{-8} — 10^{-9} m 10 —1 nm (100 — 10 Å)	10^8 — 10^9 m^{-1} 100 μm^{-1} — 1 nm^{-1}	Part of soft X-rays	(1.6 — 16) × 10^{-17} joule {100 — 1000 eV}
3×10^{17} — 3×10^{18} Hz 300 PHz — 3 Ehz	10^{-9} — 10^{-10} m 1 nm — 100 pm (10 — 1 Å)	10^9 — 10^{10} m^{-1} 1 — 10 nm^{-1}	Part of soft X-rays	(1.6 — 16) × 10^{-16} joule {1 — 10 keV}
3×10^{18} — 3×10^{19} Hz 3 — 30 Ehz	10^{-10} — 10^{-11} m 100 — 10 pm (1 — 0.1 Å)	10^{10} — 10^{11} m^{-1} 10 — 100 nm^{-1}	Hard X-rays and part of soft γ-rays	(1.6 — 16) × 10^{-15} joule {10 — 100 keV}
3×10^{19} — 3×10^{20} Hz 30 — 300 Ehz	10^{-11} — 10^{-12} m 10 — 1 pm (0.1 — 0.01 Å)	10^{11} — 10^{12} m^{-1} 100 nm^{-1} — 1 pm^{-1}	Part of soft and part of hard γ-rays (limit at 510 keV)	(1.6 — 16) × 10^{-14} joule {100 keV — 1 MeV}
3×10^{20} — 3×10^{21} Hz 300 — 3000 EHz	10^{-12} — 10^{-13} m 1 pm — 100 fm (0.01 — 0.001 Å)	10^{12} — 10^{13} m^{-1} 1 — 10 pm^{-1}	Part of hard γ-rays and part of "cosmic" γ-rays	(1.6 — 16) × 10^{-13} joule {1 — 10 MeV}
3×10^{21} — 3×10^{22} Hz 3000 — 30,000 EHz	10^{-13} — 10^{-14} m 100 — 10 fm (0.001 — 0.0001 Å)	10^{13} — 10^{14} m^{-1} 10 — 100 pm^{-1}	γ-rays produced by cosmic rays	(1.6 — 16) × 10^{-12} joule {10 — 100 MeV}

Note: Abbreviations used in this table: Å— ångstrom(1 Å=10^{-10} m); EHz—exahertz (10^{18} hertz); EHF—extremely high frequency; ELF— extremely low frequency; eV—electron volt (1 eV = 1.60219×10^{-19} joule); fm—femtometer (10^{-15} m); GHz—gigahertz (10^{9} hertz); Gm—gigameter (10^{9} m); HF—high frequency; Hz—hertz(s^{-1}); ITU—International Telecommunications Union; keV— kiloelectron volt (10^{3} eV); km—kilometer (10^{3} m); LF—low frequency; m—meter; MeV— megaelectron volt (10^{6} eV); MF—medium frequency; MHz—megahertz (10^{6} hertz); Mm—megameter (10^{6} meter); mm—millimeter (10^{-3} meter); µm—micrometer (10^{-6} meter); nm—nanometer (10^{-9}meter); PHz—petahertz (10^{15} hertz); pm—picometer (10^{-12} meter); SHF—super high frequency; SLF—super low frequency; THz—terahertz; UHF—ultra high frequency; ULF—ultra low frequency; VHF—very high frequency; VLF—very low frequency.

[a] Also called "microwaves"; not to be confused with "micrometer waves".

LETTER DESIGNATIONS OF MICROWAVE BANDS

Frequency (GHz)	Wavelength (cm)	Wavenumber (cm^{-1})	Band
1—2	30—15	0.033—0.067	L-Band
1—4	15—7.5	0.067—0.133	S-Band
4—8	7.5—3.7	0.133—0.267	C-Band
8—12	3.7—2.5	0.267—0.4	X-Band
12—18	2.5—1.7	0.4—0.6	Ku-Band
18—27	1.7—1.1	0.6—0.9	K-Band
27—40	1.1—0.75	0.9—1.33	Ka-Band

BLACK BODY RADIATION


The total power radiated from an ideal black body and the wavelength corresponding to maximum power are given here as a function of absolute temperature. Constants used in the calculation are taken from the table "Fundamental Physical Constants" in Section 1. The radiated power in a band $\Delta\lambda$ at λ_{max} may be calculated from:

$$P_{max} = 0.657548\ (\Delta\lambda/\lambda_{max})\ P_{tot}$$

T/K	P_{tot}	λ_{max}/μm	T/K	P_{tot}	λ_{max}/μm	T/K	P_{tot}	λ_{max}/μm
50	0.354 W/m²	57.955	740	17.004	3.916	1520	302.689	1.906
100	5.671	28.978	750	17.942	3.864	1540	318.937	1.882
150	28.707	19.318	760	18.918	3.813	1560	335.831	1.858
200	90.728	14.489	770	19.934	3.763	1580	353.387	1.834
250	221.504	11.591	780	20.989	3.715	1600	371.623	1.811
273	314.973	10.614	790	22.087	3.668	1620	390.555	1.789
280	348.541	10.349	800	23.226	3.622	1640	410.202	1.767
290	401.064	9.992	810	24.410	3.577	1660	430.581	1.746
300	459.311	9.659	820	25.638	3.534	1680	451.710	1.725
310	523.684	9.348	830	26.911	3.491	1700	473.607	1.705
320	594.596	9.055	840	28.232	3.450	1720	496.290	1.685
330	672.478	8.781	850	29.600	3.409	1740	519.779	1.665
340	757.771	8.523	860	31.018	3.369	1760	544.093	1.646
350	850.931	8.279	870	32.486	3.331	1780	569.249	1.628
360	952.428	8.049	880	34.006	3.293	1800	595.267	1.610
370	1.063 kW/m²	7.832	890	35.578	3.256	1820	622.168	1.592
380	1.182	7.626	900	37.204	3.220	1840	649.970	1.575
390	1.312	7.430	910	38.886	3.184	1860	678.694	1.558
400	1.452	7.244	920	40.623	3.150	1880	708.359	1.541
410	1.602	7.068	930	42.418	3.116	1900	738.987	1.525
420	1.764	6.899	940	44.272	3.083	1920	770.597	1.509
430	1.939	6.739	950	46.187	3.050	1940	803.210	1.494
440	2.125	6.586	960	48.162	3.018	1960	836.848	1.478
450	2.325	6.439	970	50.201	2.987	1980	871.531	1.464
460	2.539	6.299	980	52.303	2.957	2000	907.282	1.449
470	2.767	6.165	990	54.471	2.927	2020	944.121	1.435
480	3.010	6.037	1000	56.705	2.898	2040	982.071	1.420
490	3.269	5.914	1020	61.379	2.841	2060	1.021 MW/m²	1.407
500	3.544	5.796	1040	66.337	2.786	2080	1.061	1.393
510	3.836	5.682	1060	71.589	2.734	2100	1.103	1.380
520	4.146	5.573	1080	77.147	2.683	2120	1.145	1.367
530	4.474	5.467	1100	83.022	2.634	2140	1.189	1.354
540	4.822	5.366	1120	89.227	2.587	2160	1.234	1.342
550	5.189	5.269	1140	95.773	2.542	2180	1.281	1.329
560	5.577	5.175	1160	102.672	2.498	2200	1.328	1.317
570	5.986	5.084	1180	109.939	2.456	2220	1.377	1.305
580	6.417	4.996	1200	117.584	2.415	2240	1.428	1.294
590	6.871	4.911	1220	125.621	2.375	2260	1.479	1.282
600	7.349	4.830	1240	134.063	2.337	2280	1.532	1.271
610	7.851	4.750	1260	142.924	2.300	2300	1.587	1.260
620	8.379	4.674	1280	152.217	2.264	2320	1.643	1.249
630	8.933	4.600	1300	161.955	2.229	2340	1.700	1.238
640	9.514	4.528	1320	172.154	2.195	2360	1.759	1.228
650	10.122	4.458	1340	182.827	2.163	2380	1.819	1.218
660	10.760	4.391	1360	193.989	2.131	2400	1.881	1.207
670	11.427	4.325	1380	205.655	2.100	2420	1.945	1.197
680	12.124	4.261	1400	217.838	2.070	2440	2.010	1.188
690	12.853	4.200	1420	230.556	2.041	2460	2.077	1.178
700	13.615	4.140	1440	243.822	2.012	2480	2.145	1.168
710	14.410	4.081	1460	257.652	1.985	2500	2.215	1.159
720	15.239	4.025	1480	272.063	1.958	2550	2.398	1.136
730	16.103	3.970	1500	287.070	1.932	2600	2.591	1.115

T/K	P_{tot}	λ_{max}/μm	T/K	P_{tot}	λ_{max}/μm	T/K	P_{tot}	λ_{max}/μm
2650	2.796	1.093	3600	9.524	0.805	5100	38.362	0.568
2700	3.014	1.073	3650	10.065	0.794	5200	41.461	0.557
2750	3.243	1.054	3700	10.627	0.783	5300	44.743	0.547
2800	3.485	1.035	3750	11.214	0.773	5400	48.217	0.537
2850	3.741	1.017	3800	11.824	0.763	5500	51.889	0.527
2900	4.011	0.999	3850	12.458	0.753	5600	55.767	0.517
2950	4.294	0.982	3900	13.118	0.743	5700	59.858	0.508
3000	4.593	0.966	3950	13.804	0.734	5800	64.170	0.500
3050	4.907	0.950	4000	14.517	0.724	5900	68.712	0.491
3100	5.237	0.935	4100	16.024	0.707	6000	73.490	0.483
3150	5.583	0.920	4200	17.645	0.690	6500	101.222	0.446
3200	5.946	0.906	4300	19.386	0.674	7000	136.149	0.414
3250	6.326	0.892	4400	21.254	0.659	7500	179.418	0.386
3300	6.725	0.878	4500	23.253	0.644	8000	232.264	0.362
3350	7.142	0.865	4600	25.389	0.630	8500	296.004	0.341
3400	7.578	0.852	4700	27.670	0.617	9000	372.042	0.322
3450	8.033	0.840	4800	30.101	0.604	9500	461.867	0.305
3500	8.509	0.828	4900	32.689	0.591	10000	567.051	0.290
3550	9.006	0.816	5000	35.441	0.580			

The curves below show, for various temperatures, the fraction of radiant power as a function of wavelength. The function plotted is $P_\lambda/\Delta\lambda\, P_{tot}$, where P_λ is the power at wavelength λ in a small interval Δλ (in μm), and P_{tot} is the total power.




CHARACTERISTICS OF INFRARED DETECTORS

This graph summarizes the wavelength response of some semiconductors used as detectors for infrared radiation. The quantity $D^*(\lambda)$ is the signal to noise ratio for an incident radiant power density of 1 W/cm^2 and a bandwidth of 1 Hz (60° field of view). The Ge, InAs, and InSb detectors are photovoltaics, while the HgCdTe series are photoconductive devices. The cutoff wavelength of the latter can be varied by adjusting the relative amounts of Hg, Cd, and Te (three examples are shown at 77 K). The graph also shows the theoretical background limited sensitivity for ideal detectors which introduce no intrinsic noise.

Reference

Infrared Detectors 1995, EG&G Judson, Montgomeryville, PA.



REFRACTIVE INDEX AND TRANSMITTANCE OF REPRESENTATIVE GLASSES

Typical values of the index of refraction and internal transmittance (fraction of light transmitted through a one centimeter thickness) are tabulated here for selected types of glasses, as well as for synthetic fused (vitreous) silica. Nominal compositions are given in the first part of the table. The second part gives the index of refraction, relative to air, and the internal transmittance for representative samples of each glass at wavelengths in the infrared, visible, and near-ultraviolet regions. It should be emphasized that wide variation of these parameters may be found among subtypes of each glass. More detailed data may be found in Reference 3.

Assuming that the Lambert-Beer Law is followed, the transmittance of a glass plate of thickness d (in centimeters) can be obtained by raising the transmittance value in the table to the power d.

References

1. Weber, M. J., *CRC Handbook of Laser Science and Technology*, Vol. IV, Part 2, CRC Press, Boca Raton, FL ,1988.
2. Gray, D. E., Ed., *American Institute of Physics Handbook, Third Edition*, McGraw Hill, New York, 1972.
3. *Schott Optical Glass*, Schott Glass Technologies, Inc., 400 York Ave., Duryea, PA 18642.
4. Kaye, G. W. C., and Laby, T. H., *Tables of Physical and Chemical Constants*, *15th Edition*, Longman, London, 1986.

		Composition in percent by mass								
Type	**Name**	**SiO_2**	**B_2O_3**	**Al_2O_3**	**Na_2O**	**K_2O**	**CaO**	**BaO**	**ZnO**	**PbO**	**P_2O_5**
PK	Phosphate crown		3	10		12	5				70
PSK	Dense phosphate crown		3	5			4	28			60
BK	Borosilicate crown	70	10		8	8	1	3			
K	Crown	74			9	11	6				
ZK	Zinc crown	71			17				12		
BaK	Barium crown	60	3		3	10		19	5		
SK	Dense crown	39	15	5				41			
KF	Crown flint	67		2	16				3	12	
BaLF	Barium light flint	51			6	5		20	14	4	
SSK	Extra dense crown	35	10	5				42	8		
LLF	Extra light flint	63			5	8				24	
BaF	Barium flint	46				8		16	8	22	
LF	Light flint	53			5	8				34	
F	Flint	47			2	7				44	
BaSF	Dense barium flint	43			1	7		11	5	33	
SF	Dense flint	33				5				62	
KzFS	Short flint										
SiO_2	Fused silica	100									

	Index of refraction				Transmittance of 1 cm plate			
Type	**1.060 µm**	**546.1 nm**	**365.0 nm**	**312.6 nm**	**1.060 µm**	**546.1 nm**	**365.0 nm**	**310 nm**
PK	1.51519	1.52736	1.54503	1.5574	0.997	0.998	0.987	0.46
PSK	1.54154	1.55440	1.57342	1.5868	0.996	0.998	0.984	0.46
BK	1.50669	1.51872	1.53627	1.5486	0.999	0.998	0.987	0.35
K	1.50091	1.51314	1.53189	1.5454	0.998	0.998	0.988	0.40
ZK	1.52220	1.53534	1.55588	1.5708	0.996	0.998	0.976	0.27
BaK	1.55695	1.57124	1.59407	1.6108	0.998	0.997	0.986	0.28
SK	1.59490	1.60994	1.63398		0.998	0.998	0.959	0.28
KF	1.50586	1.51978	1.54251	1.5600	0.998	0.996	0.989	0.49
BaLF	1.57579	1.59166	1.61804		0.996	0.998	0.933	0.010
SSK	1.60402	1.61993	1.64595		0.999	0.998	0.915	0.010
LaK	1.69710	1.71616	1.74573		0.999	0.998	0.882	0.17
LLF	1.52775	1.54344	1.57038		0.998	0.997	0.990	0.32
BaF	1.56873	1.58565	1.61524		0.999	0.997	0.992	0.004
LF	1.56594	1.58482	1.61926		0.999	0.998	0.981	0.008
F	1.58636	1.60718	1.64606		0.997	0.998	0.959	
BaSF	1.60889	1.62987	1.66926		0.999	0.998	0.857	
SF	1.71350	1.74620	1.8145		0.998	0.997	0.650	
KzFS	1.59680	1.61639	1.64849	1.6739		0.998	0.672	0.012
SiO_2	1.44968	1.46008	1.47435[a]	1.53430[b]				

[a] At 366.3 nm.

[b] At 213.9 nm.

INDEX OF REFRACTION OF WATER

This table gives the index of refraction of liquid water at atmospheric pressure, relative to a vacuum, at several temperatures and wavelengths. It is generated from the formulation in Reference 1, which covers a wide range of temperature, pressure, and wavelength. The wavelengths listed here correspond to prominent lines of cadmium (226.50 and 361.05 nm), potassium (404.41 nm), sodium (589.00 nm), Ne (632.80 nm, from a helium - neon laser), and mercury (1.01398 μm).

References

1. Schiebener, P., Straub, J., Levelt Sengers, J. M. H., and Gallagher, J. S., *J. Phys. Chem. Ref. Data*, 19, 677, 1990; 19, 1617, 1990.
2. Marsh, K. N., Editor, *Recommended Reference Materials for the Realization of Physicochemical Properties*, Blackwell Scientific Publications, Oxford, 1987.

T/°C	226.50 nm	361.05 nm	404.41 nm	589.00 nm	632.80 nm	1.01398 μm
0	1.39450	1.34896	1.34415	1.33432	1.33306	1.32612
10	1.39422	1.34870	1.34389	1.33408	1.33282	1.32591
20	1.39336	1.34795	1.34315	1.33336	1.33211	1.32524
30	1.39208	1.34682	1.34205	1.33230	1.33105	1.32424
40	1.39046	1.34540	1.34065	1.33095	1.32972	1.32296
50	1.38854	1.34373	1.33901	1.32937	1.32814	1.32145
60	1.38636	1.34184	1.33714	1.32757	1.32636	1.31974
70	1.38395	1.33974	1.33508	1.32559	1.32438	1.31784
80	1.38132	1.33746	1.33284	1.32342	1.32223	1.31576
90	1.37849	1.33501	1.33042	1.32109	1.31991	1.31353
100	1.37547	1.33239	1.32784	1.31861	1.31744	1.31114

INDEX OF REFRACTION OF LIQUIDS FOR CALIBRATION PURPOSES

This table gives the index of refraction of six liquids which are available in highly pure form and whose index of refraction has been accurately measured as a function of wavelength and temperature. They are therefore useful for calibration of refractometers. The estimated uncertainty in the values is:

2,2,4-Trimethylpentane	±0.00003
Hexadecane	±0.00008
trans-Bicyclo[4.0.0]decane	±0.00008
1-Methylnaphthalene	±0.00008
Toluene	±0.00003
Methylcyclohexane	±0.00003

Full details are given in the references. This table is reprinted from Reference 1 by permission of the International Union of Pure and Applied Chemistry.

References

1. Marsh, K. N., Editor, *Recommended Reference Materials for the Realization of Physicochemical Properties*, Blackwell Scientific Publications, Oxford, 1987.
2. Tilton, L. W., *J. Opt. Soc. Am.*, 32, 71, 1941.

λ	2,2,4-Trimethylpentane			Hexadecane		
nm	20°C	25°C	30°C	20°C	25°C	30°C
667.81	1.38916	1.38670	1.38424	1.43204	1.43001	1.42798
656.28	1.38945	1.38698	1.38452	1.43235	1.43032	1.42829
589.26	1.39145	1.38898	1.38650	1.43453	1.43250	1.43047
546.07	1.39316	1.39068	1.38820	1.43640	1.43436	1.43232
501.57	1.39544	1.39294	1.39044	1.43888	1.43684	1.43480
486.13	1.39639	1.39389	1.39138	1.43993	1.43788	1.43583
435.83	1.40029	1.39776	1.39523	1.44419	1.44213	1.44007

λ	*trans*-Bicyclo[4.4.0]decane			1-Methylnaphthalene		
nm	20°C	25°C	30°C	20°C	25°C	30°C
667.81	1.46654	1.46438	1.46222	1.60828	1.60592	1.60360
656.28	1.46688	1.46472	1.46256	1.60940	1.60703	1.60471
589.26	1.46932	1.46715	1.46498	1.61755	1.61512	1.61278
546.07	1.47141	1.46923	1.46705	1.62488	1.62240	1.62005
501.57	1.47420	1.47200	1.46980	1.63513	1.63259	1.63022
486.13	1.47535	1.47315	1.47095	1.63958	1.63701	1.63463
435.83	1.48011	1.47789	1.47567		1.65627	1.65386

λ	Toluene			Methylcyclohexane		
nm	20°C	25°C	30°C	20°C	25°C	30°C
667.81	1.49180	1.48903	1.48619	1.42064	1.41812	1.41560
656.28	1.49243	1.48966	1.48682	1.42094	1.41842	1.41591
589.26	1.49693	1.49413	1.49126	1.42312	1.42058	1.41806
546.07	1.50086	1.49803	1.49514	1.42497	1.42243	1.41989
501.57	1.50620	1.50334	1.50041	1.42744	1.42488	1.42233
486.13	1.50847	1.50559	1.50265	1.42847	1.42590	1.42334
435.83	1.51800	1.51506	1.51206	1.43269	1.43010	1.42752

INDEX OF REFRACTION OF AIR

This is a table of the index of refraction n of dry air at 15°C and a pressure of 101.325 kPa and containing 0.045% by volume of carbon dioxide ("standard air"). The index of refraction is defined by $n = \lambda_{vac}/\lambda_{air}$ where λ is the wavelength of the radiation. The index is calculated from the expression

$$(n-1) \times 10^8 = 8342.54 + 2406147(130 - \sigma^2)^{-1} + 15998(38.9 - \sigma^2)^{-1}$$

where $\sigma = 1/\lambda_{vac}$ and λ_{vac} has units of μm. The equation is valid for λ_{vac} from 200 nm to 2 μm. The table also gives the correction $(n-1)\lambda_{air}$ which must be added to the wavelength in air to obtain λ_{vac}.

If the air is at a temperature t in °C (ITS-90) and a pressure p in pascals, a value of $(n - 1)$ from this table should be multiplied by

$$p[1 + p(60.1 - 0.972t) \times 10^{-10}]/96095.43(1 + 0.003661t)$$

References

1. Birch, K. P., and Downs, M. J., *Metrologia*, 31, 315, 1994.
2. Edlen, B., *Metrologia* 2, 71, 1966.

λ_{vac}	$(n-1) \times 10^8$	$\lambda_{vac} - \lambda_{air}$	λ_{vac}	$(n-1) \times 10^8$	$\lambda_{vac} - \lambda_{air}$	λ_{vac}	$(n-1) \times 10^8$	$\lambda_{vac} - \lambda_{air}$
200 nm	32409	0.06480 nm	540	27804	0.15010	880	27462	0.24160
210	31748	0.06665	550	27784	0.15277	890	27458	0.24431
220	31226	0.06868	560	27765	0.15544	900	27454	0.24701
230	30801	0.07082	570	27747	0.15811	910	27449	0.24972
240	30447	0.07305	580	27730	0.16079	920	27445	0.25243
250	30148	0.07535	590	27714	0.16347	930	27441	0.25513
260	29892	0.07769	600	27698	0.16614	940	27437	0.25784
270	29670	0.08009	610	27684	0.16882	950	27434	0.26055
280	29477	0.08251	620	27670	0.17151	960	27430	0.26326
290	29307	0.08497	630	27657	0.17419	970	27427	0.26597
300	29157	0.08745	640	27644	0.17688	980	27423	0.26868
310	29023	0.08995	650	27632	0.17956	990	27420	0.27138
320	28904	0.09247	660	27621	0.18225			
330	28796	0.09500	670	27610	0.18494	1.00 μm	27417	0.0002741
340	28700	0.09755	680	27600	0.18763	1.05	27402	0.0002876
350	28612	0.10011	690	27590	0.19032	1.10	27390	0.0003012
360	28532	0.10269	700	27581	0.19301	1.15	27379	0.0003148
370	28460	0.10527	710	27572	0.19570	1.20	27370	0.0003283
380	28393	0.10786	720	27563	0.19840	1.25	27361	0.0003419
390	28332	0.11046	730	27555	0.20109	1.30	27354	0.0003555
400	28276	0.11307	740	27547	0.20379	1.35	27347	0.0003691
410	28224	0.11569	750	27539	0.20649	1.40	27341	0.0003827
420	28177	0.11831	760	27532	0.20918	1.45	27336	0.0003963
430	28132	0.12094	770	27525	0.21188	1.50	27331	0.0004099
440	28091	0.12357	780	27518	0.21458	1.55	27327	0.0004234
450	28053	0.12620	790	27511	0.21728	1.60	27323	0.0004370
460	28018	0.12885	800	27505	0.21998	1.65	27319	0.0004506
470	27985	0.13149	810	27499	0.22268	1.70	27316	0.0004642
480	27954	0.13414	820	27493	0.22538	1.75	27313	0.0004778
490	27925	0.13679	830	27488	0.22808	1.80	27310	0.0004914
500	27897	0.13945	840	27482	0.23079	1.85	27307	0.0005050
510	27872	0.14211	850	27477	0.23349	1.90	27305	0.0005187
520	27848	0.14477	860	27472	0.23619	1.95	27303	0.0005323
530	27825	0.14743	870	27467	0.23890	2.00	27301	0.0005459

CHARACTERISTICS OF LASER SOURCES

William F. Krupke

Light Amplification by Stimulated Emission of Radiation was first demonstrated by Maiman in 1960, the result of a population inversion produced between energy levels of chromium ions in a ruby crystal when irradiated with a xenon flashlamp. Since then population inversions and coherent emission have been generated in literally thousands of substances (neutral and ionized gases, liquids, and solids) using a variety of incoherent excitation techniques (optical pumping, electrical discharges, gas-dynamic flow, electron-beams, chemical reactions, nuclear decay).

The extrema of laser output parameters which have been demonstrated to date and the laser media used are summarized in Table 1. Note that the extreme power and energy parameters listed in this table were attained with laser *systems* rather than with simple laser oscillators.

Laser sources are commonly classified in terms of the state-of-matter of the active medium: gas, liquid, and solid. Each of these classes is further subdivided into one or more types as shown in Table 2. A well-known representative example of each type of laser is also given in Table 2 together with its nominal operation wavelength and the methods by which it is pumped.

The various lasers together cover a wide spectral range from the far ultraviolet to the far infrared. The particular wavelength of emission (usually a narrow line) is presented for some six dozen lasers in Figures 1A and 1B.

By suitably designing the excitation source and/or by controlling the laser resonator structure, laser systems can provide continuous or pulsed radiation as shown in Table 3.

Besides the method of excitation and the temporal behavior of a laser, there are many other parameters that characterize its operation and efficiency, as shown in Tables 4 and 5.

Although many lasers only emit in one or more narrow spectral "lines", an increasing number of lasers can be tuned by changing the composition or the pressure of the medium, or by varying the wavelength of the pump bands. The spectral regions in which these tunable lasers operate are presented in Figure 2.

References

Krupke, W. F., in *Handbook of Laser Science and Technology*, Vol. I, Weber, M. J., Ed., CRC Press, Boca Raton, FL, 1986.

TABLE 1. Extrema of Output Parameters of Laser Devices or Systems

Parameter	Value	Laser medium
Peak power	1×10^{14} W(collimated)	Nd:glass
Peak power density	10^{18} W/cm^2 (focused)	Nd:glass
Pulse energy	$>10^5$ J	CO_2, Nd:glass
Average power	10^5 W	CO_2
Pulse duration	3×10^{-15} s continuous wave (cw)	Rh6G dye; various gases, liquids, solids
Wavelength	60 nm ↔ 385 μm	Many required
Efficiency (nonlaser pumped)	70%	CO
Beam quality	Diffraction limited	Various gases, liquids, solids
Spectral linewidth	20 Hz (for 10^{-1} s)	Neon-helium
Spatial coherence	10 m	Ruby

TABLE 2. Classes, Types, and Representative Examples of Laser Sources

Class	Type (characteristic)	Representative example	Nominal operating wavelength (nm)	Method(s) of excitation
Gas	Atom, neutral (electronic transition)	Neon-Helium (Ne-He)	633	Glow discharge
	Atom, ionic (electronic transition)	Argon (Ar^+)	488	Arc discharge
	Molecule, neutral (electronic transition)	Krypton fluoride (KrF)	248	Glow discharge; e-beam
	Molecule, neutral (vibrational transition)	Carbon dioxide (CO_2)	10600	Glow discharge; gasdynamic flow
	Molecule, neutral (rotational transition)	Methyl fluoride (CH_3F)	496000	Laser pumping
	Molecule, ionic (electronic transition)	Nitrogen ion (N_2^+)	420	E-beam
Liquid	Organic solvent (dye-chromophore)	Rhodamine dye (Rh6G)	580–610	Flashlamp; laser pumping
	Organic solvent (rare earth chelate)	Europium:TTF	612	Flashlamp
	Inorganic solvent (trivalent rare earth ion)	Neodymium:$POCl_4$	1060	Flashlamp
Solid	Insulator, crystal (impurity)	Neodymium:YAG	1064	Flashlamp, arc lamp
	Insulator, crystal (stoichiometric)	Neodymium:UP(NdP_5O_{14})	1052	Flashlamp
	Insulator, crystal (color center)	F_2^-:LiF	1120	Laser pumping
	Insulator, amorphous (impurity)	Neodymium:glass	1061	Flashlamp
	Semiconductor (p-n junction)	GaAs	820	Injection current
	Semiconductor (electron-hole plasma)	GaAs	890	E- beam, laser pumping

S10_18.indd 253 4/12/05 3:02:08 PM

TABLE 3. Temporal Characteristics of Lasers and Laser Systems

Form	Technique	Pulse width range (s)
Continuous wave	Excitation is continuous; resonator Q is held constant at some moderate value	∞
Pulsed	Excitation is pulsed; resonator Q is held constant at some moderate value	$10^{-8} – 10^{-3}$
Q-Switched	Excitation is continuous or pulsed; resonator Q is switched from a very low value to a moderate value	$10^{-8} – 10^{-6}$
Cavity dumped	Excitation is continuous or pulsed; resonator Q is switched from a very high value to a low value	$10^{-7} – 10^{-5}$
Mode locked	Excitation is continuous or pulsed; phase or loss of the resonator modes is modulated at a rate related to the resonator transit time	$10^{-12} – 10^{-9}$

TABLE 4. Properties and Performance of Some Continuous Wave (CW) Lasers

		Gas			Liquid	Solid	
Parameter	**Unit**	**Neon helium**	**Argon ion**	**Carbon dioxide**	**Rhodamine 6G dye**	**Nd:YAG**	**GaAs**
Excitation method		DC discharge	DC discharge	DC discharge	Ar^+ laser pump	Krypton arc lamp	DC injection
Gain medium composition		Neon:helium	Argon	CO_2:N_2:He	Rh 6G:H_2O	Nd:YAG	p:n:GaAs
Gain medium density	Torr	0.1:1.0	0.4	0.4:0.8:5.0			
	ions/cm^3				2(18):2(22)	1.5(20):2(22)	2(19):3(18):3(22)
Wavelength	nm	633	488	10600	590	1064	810
Laser cross-section	cm^{-2}	3(-13)	1.6(-12)	1.5(-16)	1.8(-16)	7(-19)	~6(-15)
Radiative lifetime (upper level)	s	~1(-7)	7.5(-9)	4(-3)	6.5(-9)	2.6(-4)	~1(-9)
Decay lifetime (upper level)	s	~1(-7)	~5.0(-9)	~4(-3)	6.0(-9)	2.3(-4)	~1(-9)
Gain bandwidth	nm	2(-3)	5(-3)	1.6(-2)	80	0.5	10
Type, gain saturation		Inhomogeneous	Inhomogeneous	Homogeneous	Homogeneous	Homogeneous	Homogeneous
Homogeneous saturation flux	W cm^{-2}			~20	3(5)	2.3(3)	~2(4)
Decay lifetime (lower level)	s	~ 1(-8)	~4(-10)	~5(-6)	<1(-12)	< 1(-7)	<1(-12)
Inversion density	cm^{-3}	~ 1(9)	2(10)	2(15)	2(16)	6(16)	1(16)
Small signal gain coefficient	cm^{-1}	~ 1(-3)	~3(-2)	1(-2)	4	5(-2)	40
Pump power density	W cm^{-3}	3	900	0.15	1(6)	150	7(7)
Output power density	W cm^{-3}	2.6(-3)	~1	2(-2)	3(5)	95	5(6)
Laser size (diameter: length)	cm:cm	0.5:100	0.3:100	5.0:600	1(-3):0.3	0.6:10	5(-4):7(-3);2(-2)[a]
Excitation current/ voltage	A/V	3(-2):2(3)	30:300	0.1:1.5(4)		90:125	1.0/1.7
Excitation current density	A cm^{-2}	0.15	600	6(-3)		140	4.5(3)
Excitation power	W	60	9(3)	1.5(3)	4	1.1(4)	1.7
Output power	W	0.06	10	240	0.3	300	0.12
Efficiency	%	0.1	0.1	13	7	2.6	7

[a] Junction thickness:width:length.
[b] Pressure dependent.

TABLE 5. Properties and Performance of Some Pulsed Lasers

		Gas				Liquid	Solid	
Parameter	**Unit**	**Carbon dixoxide**		**Krypton fluoride**		**Rhodamine 6G**	**Nd:YAG**	**Nd:glass**
Excitation method		TEA-discharge	E- beam/sust.	Glow discharge	E-beam	Xenon flashlamp	Xenon flashlamp	Xenon flashlamp
Gain medium composition		CO_2:N_2:He	CO_2:N_2:He	He:Kr:F_2	Ar:Kr:F_2	Rh6G:alcohol	Nd:YAG	Nd:Glass
Gain medium density	torr	100:50:600	240:240:320	1070:70:3	1235:52:3			–
	ions/cm^3					1(18):1.5(22)	1.5(20):1(22)	3(20):2(22)
Wavelength	nm	10600	10600	249	249	590	1064	1061
Laser cross-section	cm^{-2}	2(-18)	2(-18)	2(-16)	2(-16)	1.8(-16)	7(-19)	2.8(-20)
Radiative lifetime (upper level)	s	4(-3)	4(-3)	7(-9)	7(-9)	6.5(-9)	2.6(-4)	4.1(-4)
Decay lifetime (upper level)	s	~1(-4)	5(-5)	2(-9)	3(-9)	6.0(-9)	2.3(-4)	3.7(-4)
Gain bandwidth	nm	1	1	2	2	80	0.5	26
Homogeneous saturation fluence	J/cm^2	0.2	0.2	4(-3)	4(-3)	2(-3)	0.6	~5
Decay lifetime (lower level)	s	5(-8)[a]	1(-8)[a]	< 1(-12)	<1(-12)	<1(-12)	<1(-7)	<1(-8)
Inversion density	cm^{-3}	3(17)	6(17)	4(14)	2(14)	2(16)	4(17)	3(18)
Small signal gain coefficient	cm^{-1}	2(-2)	4(-2)	8–92)	4(-2)	4	0.3	8(-2)
Medium excitation energy density	J/cm^3	0.1	0.36	0.15	0.13	2.8	0.15	0.6
Output energy density	J/cm^3	2(-2)	1.8(-2)	1.5(-3)	1.2(-2)	0.85	5(-2)	2(-2)
Laser dimensions	cm: cm: cm	4.5:4.5:87	10:10:100	1.5:4.5:100	8.5:10:100	1.2:25	0.6:7.5	0.6:8.3
Excitation current/voltage	A/V	6(4)/3.3(3)	2.4(4)/4(4)	2.5(4)/1.5(5)	1.2(4)/2.5(5)	2(5)/2.5(4)		
Excitation current density	A cm^2	8.5	22	170	11.5	2.6(3)		
Excitation peak power	W	2(8)	9(8)	4(9)	3(9)	5.4(9)	4(4)	9(4)
Output pulse energy	J	35	180	1	102	32	0.1	1.0
Output pulse length	s	1(-6)	4(-6)	2.5(-8)	6(-7)	3.2(-6)	2(-8)	1(-4)
Output pulse power	W	3.5(7)	4(7)	4(7)	2(8)	1(7)	5(6)	1(4)
Efficiency	%	17	5	1	10[b]	0.2	1.5	3.7

[a] Pressure dependent.
[b] Intrinsic efficiency ≡ energy output/energy deposited in gas.




FIGURE 1A. Wavelengths of lasers operating in the 120 to 1200 nm spectral region.




FIGURE 1B. Wavelength of lasers operating in the 1300 to 12,000 nm spectral region.




FIGURE 2. Spectral tuning ranges of various types of tunable lasers.

INFRARED LASER FREQUENCIES

Arthur Maki

The CO_2 laser has been the subject of a number of very accurate frequency measurements. Most of the earlier measurements are given by Bradley et al.[1] That analysis was based on a single absolute frequency measurement and many laser frequency differences. New measurements of the methane frequency[2-4] have made it necessary to slightly revise that single absolute frequency measurement. In addition, there have been several other absolute frequency measurements[5-7] that have been used here to improve the accuracy of the present tables. New frequency difference measurements have also been added to the database used for the present tables.[8]

References

1. Bradley, L. C., Soohoo, K. L., and Freed, C., *IEEE J. Quantum Electron.*, QE-22, 234–267, 1986.
2. Clairon, A., Dahmani, B., Filimon, A., and Rutman, J., *IEEE Trans. Inst. Meas.*, IM-34, 265–268, 1985.
3. Weiss, C. O., Kramer, G., Lipphardt, B., and Garcia, E., *IEEE J. Quantum Electron.*, QE-24, 1970–1972, 1988.
4. Bagayev, S. N., Baklanov, A. E., Chebotayev, V. P., and Dychkov, A. S., *Appl. Phys.*, B-48, 31–35, 1989.
5. Blaney, T. G., Bradley, C. C., Edwards, G. J., Jolliffe, B. W., Knight, D. J. E., Rowley, W. R. C., Shotten, K. C., and Woods, P. T., *Proc. R. Soc. Lond.*, A-355, 61–88, 1977.
6. Chardonnet, Ch., Van Lerberghe, A., and Bordé, Ch. J., *Opt. Comm.*, 58, 333-337, 1986.
7. Clairon, A., Acef, O., Chardonnet, Ch., and Bordé, Ch. J., *Frequency Standards and Metrology*, De Marchi, A., Ed., Springer-Verlag, Berlin, Heidelberg, 1989, p. 212.
8. Evenson, K., private communication.

Frequencies for the $00^{\circ}1\text{-}(10^{\circ}0,02^{\circ}0)_{I}$ and $00^{\circ}1\text{-}(10^{\circ}0,02^{\circ}0)_{II}$ Bands of $^{12}C^{16}O_2$ with the Estimated 2-σ Uncertainties

Line	Band I frequency (MHz)	Uncertainty (MHz)	Line	Band II frequency (MHz)	Uncertainty (MHz)
P(70)	26721305.4647	0.1680	P(70)	29789856.3783	0.0308
P(68)	26794232.6712	0.1217	P(68)	29861850.7690	0.0192
P(66)	26866318.8073	0.0867	P(66)	29933216.1760	0.0122
P(64)	26937571.7234	0.0606	P(64)	30003944.2861	0.0086
P(62)	27007998.9216	0.0415	P(62)	30074026.9127	0.0072
P(60)	27077607.5643	0.0279	P(60)	30143456.0039	0.0066
P(58)	27146404.4834	0.0185	P(58)	30212223.6504	0.0061
P(56)	27214396.1873	0.0121	P(56)	30280322.0930	0.0055
P(54)	27281588.8696	0.0081	P(54)	30347743.7306	0.0049
P(52)	27347988.4161	0.0057	P(52)	30414481.1273	0.0044
P(50)	27413600.4119	0.0043	P(50)	30480527.0196	0.0041
P(48)	27478430.1487	0.0036	P(48)	30545874.3239	0.0039
P(46)	27542482.6310	0.0032	P(46)	30610516.1429	0.0039
P(44)	27605762.5826	0.0030	P(44)	30674445.7724	0.0039
P(42)	27668274.4525	0.0028	P(42)	30737656.7080	0.0039
P(40)	27730022.4206	0.0027	P(40)	30800142.6511	0.0039
P(38)	27791010.4036	0.0026	P(38)	30861897.5150	0.0038
P(36)	27851242.0594	0.0025	P(36)	30922915.4310	0.0037
P(34)	27910720.7927	0.0024	P(34)	30983190.7534	0.0037
P(32)	27969449.7593	0.0023	P(32)	31042718.0652	0.0037
P(30)	28027431.8708	0.0022	P(30)	31101492.1833	0.0036
P(28)	28084669.7981	0.0021	P(28)	31159508.1631	0.0037
P(26)	28141165.9762	0.0020	P(26)	31216761.3029	0.0037
P(24)	28196922.6067	0.0019	P(24)	31273247.1487	0.0037
P(22)	28251941.6622	0.0017	P(22)	31328961.4978	0.0037
P(20)	28306224.8888	0.0016	P(20)	31383900.4028	0.0037
P(18)	28359773.8090	0.0014	P(18)	31438060.1749	0.0037
P(16)	28412589.7245	0.0012	P(16)	31491437.3872	0.0036
P(14)	28464673.7184	0.0011	P(14)	31544028.8776	0.0036
P(12)	28516026.6574	0.0009	P(12)	31595831.7516	0.0036
P(10)	28566649.1935	0.0008	P(10)	31646843.3843	0.0035
P(8)	28616541.7661	0.0008	P(8)	31697061.4225	0.0035
P(6)	28665704.6027	0.0008	P(6)	31746483.7868	0.0035
P(4)	28714137.7205	0.0008	P(4)	31795108.6724	0.0035
P(2)	28761840.9272	0.0008	P(2)	31842934.5511	0.0035
R(0)	28832026.2198	0.0008	R(0)	31913172.5691	0.0035
R(2)	28877902.4382	0.0007	R(2)	31958996.0621	0.0034
R(4)	28923046.4303	0.0006	R(4)	32004017.3822	0.0034

Line	Band I frequency (MHz)	Uncertainty (MHz)	Line	Band II frequency (MHz)	Uncertainty (MHz)
R(6)	28967457.0657	0.0005	R(6)	32048236.2498	0.0034
R(8)	29011133.0054	0.0003	R(8)	32091652.6619	0.0034
R(10)	29054072.7010	0.0001	R(10)	32134266.8917	0.0034
R(12)	29096274.3935	0.0003	R(12)	32176079.4878	0.0034
R(14)	29137736.1129	0.0005	R(14)	32217091.2721	0.0035
R(16)	29178455.6759	0.0007	R(16)	32257303.3386	0.0036
R(18)	29218430.6852	0.0009	R(18)	32296717.0510	0.0037
R(20)	29257658.5269	0.0010	R(20)	32335334.0408	0.0038
R(22)	29296136.3689	0.0011	R(22)	32373156.2044	0.0039
R(24)	29333861.1583	0.0012	R(24)	32410185.7003	0.0041
R(26)	29370829.6191	0.0011	R(26)	32446424.9459	0.0042
R(28)	29407038.2491	0.0011	R(28)	32481876.6140	0.0042
R(30)	29442483.3168	0.0011	R(30)	32516543.6293	0.0042
R(32)	29477160.8582	0.0012	R(32)	32550429.1641	0.0042
R(34)	29511066.6733	0.0013	R(34)	32583536.6340	0.0042
R(36)	29544196.3221	0.0015	R(36)	32615869.6937	0.0041
R(38)	29576545.1205	0.0017	R(38)	32647432.2320	0.0040
R(40)	29608108.1360	0.0019	R(40)	32678228.3665	0.0039
R(42)	29638880.1831	0.0022	R(42)	32708262.4386	0.0038
R(44)	29668855.8183	0.0024	R(44)	32737539.0081	0.0039
R(46)	29698029.3350	0.0027	R(46)	32766062.8469	0.0041
R(48)	29726394.7582	0.0032	R(48)	32793838.9334	0.0045
R(50)	29753945.8385	0.0037	R(50)	32820872.4463	0.0055
R(52)	29780676.0464	0.0042	R(52)	32847168.7576	0.0071
R(54)	29806578.5659	0.0047	R(54)	32872733.4269	0.0099
R(56)	29831646.2878	0.0052	R(56)	32897572.1935	0.0141
R(58)	29855871.8032	0.0058	R(58)	32921690.9701	0.0202
R(60)	29879247.3960	0.0074	R(60)	32945095.8355	0.0288
R(62)	29901765.0357	0.0113	R(62)	32967793.0268	0.0407
R(64)	29923416.3695	0.0186	R(64)	32989788.9322	0.0567
R(66)	29944192.7145	0.0302	R(66)	33011090.0831	0.0780
R(68)	29964085.0488	0.0475	R(68)	33031703.1467	0.1060
R(70)	29983084.0036	0.0720	R(70)	33051634.9172	0.1423

Frequencies for the $00^{\circ}1\text{-}(10^{\circ}0,02^{\circ}0)_{I}$ and $00^{\circ}1\text{-}(10^{\circ}0,02^{\circ}0)_{II}$ Bands of $^{13}C^{16}O_2$ with the Estimated 2-σ Uncertainties

P(66)	25523832.1808	0.7836	P(66)	28512082.5283	1.2894
P(64)	25590013.4703	0.5415	P(64)	28585121.9396	0.9194
P(62)	25655543.6502	0.3629	P(62)	28657449.4180	0.6420
P(60)	25720428.2487	0.2339	P(60)	28729056.6374	0.4375
P(58)	25784672.4840	0.1430	P(58)	28799935.4147	0.2897
P(56)	25848281.2771	0.0810	P(56)	28870077.7187	0.1853
P(54)	25911259.2627	0.0405	P(54)	28939475.6771	0.1135
P(52)	25973610.8005	0.0157	P(52)	29008121.5846	0.0659
P(50)	26035339.9857	0.0045	P(50)	29076007.9109	0.0357
P(48)	26096450.6582	0.0079	P(48)	29143127.3077	0.0180
P(46)	26156946.4123	0.0101	P(46)	29209472.6164	0.0090
P(44)	26216830.6053	0.0101	P(44)	29275036.8754	0.0058
P(42)	26276106.3655	0.0090	P(42)	29339813.3270	0.0050
P(40)	26334776.6003	0.0077	P(40)	29403795.4243	0.0044
P(38)	26392844.0030	0.0068	P(38)	29466976.8383	0.0037
P(36)	26450311.0599	0.0063	P(36)	29529351.4635	0.0032
P(34)	26507180.0565	0.0061	P(34)	29590913.4252	0.0029
P(32)	26563453.0836	0.0060	P(32)	29651657.0844	0.0028
P(30)	26619132.0428	0.0058	P(30)	29711577.0447	0.0028
P(28)	26674218.6515	0.0055	P(28)	29770668.1566	0.0031
P(26)	26728714.4479	0.0054	P(26)	29828925.5239	0.0035
P(24)	26782620.7952	0.0054	P(24)	29886344.5074	0.0041
P(22)	26835938.8858	0.0054	P(22)	29942920.7308	0.0046
P(20)	26888669.7451	0.0055	P(20)	29998650.0838	0.0051
P(18)	26940814.2347	0.0055	P(18)	30053528.7271	0.0054

Line	Band I frequency (MHz)	Uncertainty (MHz)	Line	Band II frequency (MHz)	Uncertainty (MHz)
P(16)	26992373.0555	0.0055	P(16)	30107553.0955	0.0055
P(14)	27043346.7508	0.0054	P(14)	30160719.9016	0.0055
P(12)	27093735.7083	0.0052	P(12)	30213026.1388	0.0054
P(10)	27143540.1624	0.0051	P(10)	30264469.0839	0.0054
P(8)	27192760.1962	0.0049	P(8)	30315046.2994	0.0054
P(6)	27241395.7431	0.0048	P(6)	30364755.6359	0.0055
P(4)	27289446.5880	0.0047	P(4)	30413595.2335	0.0056
P(2)	27336912.3682	0.0046	P(2)	30461563.5231	0.0057
R(0)	27407012.8882	0.0045	P(0)	30531879.5415	0.0057
R(2)	27453013.4589	0.0043	P(2)	30577664.6138	0.0056
R(4)	27498426.5430	0.0040	P(4)	30622575.1885	0.0054
R(6)	27543251.1200	0.0037	P(6)	30666611.0128	0.0051
R(8)	27587486.0225	0.0034	P(8)	30709772.1257	0.0047
R(10)	27631129.9356	0.0031	P(10)	30752058.8571	0.0045
R(12)	27674181.3963	0.0029	P(12)	30793471.8269	0.0044
R(14)	27716638.7917	0.0029	P(14)	30834011.9425	0.0043
R(16)	27758500.3577	0.0029	P(16)	30873680.3976	0.0044
R(18)	27799764.1770	0.0029	P(18)	30912478.6694	0.0044
R(20)	27840428.1773	0.0030	P(20)	30950408.5159	0.0044
R(22)	27880490.1283	0.0029	P(22)	30987471.9732	0.0043
R(24)	27919947.6395	0.0029	P(24)	31023671.3517	0.0042
R(26)	27958798.1567	0.0028	P(26)	31059009.2327	0.0042
R(28)	27997038.9591	0.0028	P(28)	31093488.4642	0.0042
R(30)	28034667.1551	0.0027	P(30)	31127112.1569	0.0043
R(32)	28071679.6785	0.0027	P(32)	31159883.6793	0.0045
R(34)	28108073.2842	0.0026	P(34)	31191806.6529	0.0046
R(36)	28143844.5432	0.0026	P(36)	31222884.9469	0.0048
R(38)	28178989.8377	0.0026	P(38)	31253122.6730	0.0053
R(40)	28213505.3554	0.0028	P(40)	31282524.1795	0.0061
R(42)	28247387.0838	0.0033	P(42)	31311094.0452	0.0077
R(44)	28280630.8035	0.0046	P(44)	31338837.0736	0.0108
R(46)	28313232.0818	0.0083	P(46)	31365758.2858	0.0173
R(48)	28345186.2652	0.0161	P(48)	31391862.9147	0.0295
R(50)	28376488.4720	0.0301	P(50)	31417156.3972	0.0505
R(52)	28407133.5839	0.0531	P(52)	31441644.3679	0.0845
R(54)	28437116.2372	0.0887	P(54)	31465332.6516	0.1366
R(56)	28466430.8141	0.1419	P(56)	31488227.2557	0.2138
R(58)	28495071.4324	0.2188	P(58)	31510334.3631	0.3247
R(60)	28523031.9357	0.3271	P(60)	31531660.3243	0.4800
R(62)	28550305.8819	0.4763	P(62)	31552211.6497	0.6932
R(64)	28576886.5323	0.6781	P(64)	31571995.0017	0.9805
R(66)	28602766.8393	0.9467	P(66)	31591017.1868	1.3619

Frequencies for the 00°1-(10°0,02°0)$_I$ and 00°1-(10°0,02°0)$_{II}$ Bands of $^{12}C^{18}O_2$ with the Estimated 2-σ Uncertainties

P(70)	27045326.3119	0.4540	P(70)	30695237.5856	0.0858
P(68)	27114914.0922	0.3324	P(68)	30755520.2231	0.0570
P(66)	27183635.7945	0.2392	P(66)	30815311.4928	0.0364
P(64)	27251496.4118	0.1688	P(64)	30874607.2084	0.0223
P(62)	27318500.7361	0.1165	P(62)	30933403.2309	0.0131
P(60)	27384653.3618	0.0783	P(60)	30991695.4724	0.0075
P(58)	27449958.6881	0.0510	P(58)	31049479.9009	0.0049
P(56)	27514420.9224	0.0319	P(56)	31106752.5446	0.0041
P(54)	27578044.0828	0.0191	P(54)	31163509.4964	0.0040
P(52)	27640832.0010	0.0108	P(52)	31219746.9183	0.0040
P(50)	27702788.3248	0.0059	P(50)	31275461.0455	0.0039
P(48)	27763916.5206	0.0035	P(48)	31330648.1908	0.0039
P(46)	27824219.8762	0.0028	P(46)	31385304.7490	0.0039
P(44)	27883701.5029	0.0026	P(44)	31439427.2006	0.0039
P(42)	27942364.3379	0.0025	P(42)	31493012.1163	0.0038
P(40)	28000211.1464	0.0024	P(40)	31546056.1605	0.0038

Line	Band I frequency (MHz)	Uncertainty (MHz)	Line	Band II frequency (MHz)	Uncertainty (MHz)
P(38)	28057244.5242	0.0022	P(38)	31598556.0954	0.0037
P(36)	28113466.8992	0.0021	P(36)	31650508.7847	0.0037
P(34)	28168880.5335	0.0020	P(34)	31701911.1970	0.0037
P(32)	28223487.5256	0.0019	P(32)	31752760.4093	0.0037
P(30)	28277289.8118	0.0017	P(30)	31803053.6105	0.0037
P(28)	28330289.1679	0.0016	P(28)	31852788.1043	0.0038
P(26)	28382487.2111	0.0015	P(26)	31901961.3125	0.0038
P(24)	28433885.4012	0.0013	P(24)	31950570.7773	0.0038
P(22)	28484485.0420	0.0012	P(22)	31998614.1649	0.0038
P(20)	28534287.2828	0.0011	P(20)	32046089.2669	0.0037
P(18)	28583293.1193	0.0010	P(18)	32092994.0036	0.0037
P(16)	28631503.3952	0.0010	P(16)	32139326.4254	0.0036
P(14)	28678918.8025	0.0009	P(14)	32185084.7154	0.0036
P(12)	28725539.8830	0.0010	P(12)	32230267.1907	0.0036
P(10)	28771367.0288	0.0010	P(10)	32274872.3041	0.0037
P(8)	28816400.4829	0.0010	P(8)	32318898.6455	0.0038
P(6)	28860640.3403	0.0011	P(6)	32362344.9434	0.0039
P(4)	28904086.5477	0.0011	P(4)	32405210.0652	0.0041
P(2)	28946738.9048	0.0011	P(2)	32447493.0185	0.0041
R(0)	29009228.1702	0.0010	P(0)	32509824.0580	0.0042
R(2)	29049894.0586	0.0010	P(2)	32550648.1723	0.0042
R(4)	29089764.2368	0.0009	P(4)	32590887.7542	0.0042
R(6)	29128837.8426	0.0008	P(6)	32630542.4457	0.0041
R(8)	29167113.8668	0.0008	P(8)	32669612.0295	0.0041
R(10)	29204591.1529	0.0009	P(10)	32708096.4282	0.0040
R(12)	29241268.3964	0.0010	P(12)	32745995.7040	0.0040
R(14)	29277144.1444	0.0011	P(14)	32783310.0573	0.0040
R(16)	29312216.7955	0.0012	P(16)	32820039.8258	0.0040
R(18)	29346484.5984	0.0012	P(18)	32856185.4827	0.0040
R(20)	29379945.6517	0.0013	P(20)	32891747.6358	0.0040
R(22)	29412597.9024	0.0013	P(22)	32926727.0254	0.0040
R(24)	29444439.1458	0.0013	P(24)	32961124.5220	0.0040
R(26)	29475467.0236	0.0014	P(26)	32994941.1249	0.0040
R(28)	29505679.0230	0.0015	P(28)	33028177.9594	0.0040
R(30)	29535072.4755	0.0016	P(30)	33060836.2743	0.0040
R(32)	29563644.5557	0.0018	P(32)	33092917.4394	0.0041
R(34)	29591392.2794	0.0020	P(34)	33124422.9429	0.0043
R(36)	29618312.5023	0.0023	P(36)	33155354.3878	0.0046
R(38)	29644401.9182	0.0028	P(38)	33185713.4894	0.0049
R(40)	29669657.0575	0.0036	P(40)	33215502.0716	0.0056
R(42)	29694074.2853	0.0053	P(42)	33244722.0637	0.0068
R(44)	29717649.7992	0.0082	P(44)	33273375.4969	0.0092
R(46)	29740379.6276	0.0128	P(46)	33301464.5003	0.0134
R(48)	29762259.6274	0.0200	P(48)	33328991.2976	0.0199
R(50)	29783285.4820	0.0307	P(50)	33355958.2027	0.0294
R(52)	29803452.6988	0.0461	P(52)	33382367.6161	0.0427
R(54)	29822756.6072	0.0681	P(54)	33408222.0209	0.0607
R(56)	29841192.3558	0.0985	P(56)	33433523.9780	0.0848
R(58)	29858754.9100	0.1401	P(58)	33458276.1228	0.1165
R(60)	29875439.0495	0.1960	P(60)	33482481.1601	0.1576
R(62)	29891239.3658	0.2702	P(62)	33506141.8605	0.2104
R(64)	29906150.2589	0.3673	P(64)	33529261.0556	0.2775
R(66)	29920165.9352	0.4930	P(66)	33551841.6335	0.3621
R(68)	29933280.4042	0.6540	P(68)	33573886.5352	0.4679
R(70)	29945487.4756	0.8581	P(70)	33595398.7493	0.5992

Frequencies for the 00°1-(10°0,02°0)$_I$ and 00°1-(10°0,02°0)$_{II}$ Bands of $^{13}C^{18}O_2$ with the Estimated 2-σ Uncertainties

P(70)	25967863.7652	1.1146	P(70)	28960476.2278	0.4069
P(68)	26033448.2798	0.8152	P(68)	29022326.9578	0.2861
P(66)	26098273.9159	0.5860	P(66)	29083661.3546	0.1961

Line	Band I frequency (MHz)	Uncertainty (MHz)	Line	Band II frequency (MHz)	Uncertainty (MHz)
P(64)	26162346.4813	0.4129	P(64)	29144473.5795	0.1303
P(62)	26225671.5466	0.2844	P(62)	29204757.8761	0.0833
P(60)	26288254.4494	0.1906	P(60)	29264508.5768	0.0507
P(58)	26350100.2984	0.1237	P(58)	29323720.1086	0.0290
P(56)	26411213.9778	0.0772	P(56)	29382386.9988	0.0152
P(54)	26471600.1504	0.0459	P(54)	29440503.8809	0.0073
P(52)	26531263.2618	0.0258	P(52)	29498065.4997	0.0038
P(50)	26590207.5442	0.0138	P(50)	29555066.7172	0.0032
P(48)	26648437.0195	0.0077	P(48)	29611502.5178	0.0031
P(46)	26705955.5026	0.0057	P(46)	29667368.0132	0.0031
P(44)	26762766.6051	0.0055	P(44)	29722658.4475	0.0034
P(42)	26818873.7378	0.0055	P(42)	29777369.2022	0.0039
P(40)	26874280.1143	0.0056	P(40)	29831495.8006	0.0044
P(38)	26928988.7531	0.0056	P(38)	29885033.9125	0.0049
P(36)	26983002.4809	0.0056	P(36)	29937979.3584	0.0053
P(34)	27036323.9351	0.0055	P(34)	29990328.1139	0.0054
P(32)	27088955.5657	0.0054	P(32)	30042076.3132	0.0055
P(30)	27140899.6384	0.0051	P(30)	30093220.2534	0.0055
P(28)	27192158.2363	0.0049	P(28)	30143756.3978	0.0054
P(26)	27242733.2620	0.0047	P(26)	30193681.3793	0.0053
P(24)	27292626.4396	0.0044	P(24)	30242992.0038	0.0052
P(22)	27341839.3165	0.0042	P(22)	30291685.2529	0.0051
P(20)	27390373.2651	0.0040	P(20)	30339758.2870	0.0049
P(18)	27438229.4843	0.0037	P(18)	30387208.4477	0.0048
P(16)	27485409.0008	0.0035	P(16)	30434033.2603	0.0046
P(14)	27531912.6704	0.0033	P(14)	30480230.4356	0.0045
P(12)	27577741.1795	0.0031	P(12)	30525797.8725	0.0044
P(10)	27622895.0455	0.0031	P(10)	30570733.6593	0.0043
P(8)	27667374.6182	0.0031	P(8)	30615036.0750	0.0043
P(6)	27711180.0803	0.0033	P(6)	30658703.5912	0.0044
P(4)	27754311.4480	0.0034	P(4)	30701734.8727	0.0045
P(2)	27796768.5718	0.0036	P(2)	30744128.7785	0.0045
R(0)	27859189.3155	0.0036	P(0)	30806522.5414	0.0045
R(2)	27899959.0889	0.0035	P(2)	30847319.2956	0.0044
R(4)	27940052.7921	0.0033	P(4)	30887476.2168	0.0043
R(6)	27979469.5315	0.0031	P(6)	30926993.0424	0.0042
R(8)	28018208.2478	0.0028	P(8)	30965869.7046	0.0041
R(10)	28056267.7161	0.0026	P(10)	31004106.3298	0.0040
R(12)	28093646.5448	0.0025	P(12)	31041703.2379	0.0040
R(14)	28130343.1757	0.0025	P(14)	31078660.9408	0.0040
R(16)	28166355.8825	0.0025	P(16)	31114980.1420	0.0040
R(18)	28201682.7706	0.0025	P(18)	31150661.7340	0.0041
R(20)	28236321.7757	0.0025	P(20)	31185706.7976	0.0042
R(22)	28270270.6628	0.0024	P(22)	31220116.5992	0.0043
R(24)	28303527.0249	0.0024	P(24)	31253892.5891	0.0043
R(26)	28336088.2817	0.0023	P(26)	31287036.3991	0.0044
R(28)	28367951.6781	0.0024	P(28)	31319549.8396	0.0043
R(30)	28399114.2823	0.0025	P(30)	31351434.8973	0.0043
R(32)	28429572.9843	0.0026	P(32)	31382693.7318	0.0042
R(34)	28459324.4940	0.0028	P(34)	31413328.6728	0.0042
R(36)	28488365.3390	0.0029	P(36)	31443342.2165	0.0041
R(38)	28516691.8625	0.0029	P(38)	31472737.0219	0.0040
R(40)	28544300.2211	0.0031	P(40)	31501515.9074	0.0039
R(42)	28571186.3823	0.0032	P(42)	31529681.8467	0.0040
R(44)	28597346.1222	0.0032	P(44)	31557237.9646	0.0042
R(46)	28622775.0223	0.0038	P(46)	31584187.5329	0.0046
R(48)	28647468.4672	0.0071	P(48)	31610533.9656	0.0057
R(50)	28671421.6417	0.0148	P(50)	31636280.8146	0.0088
R(52)	28694629.5272	0.0286	P(52)	31661431.7650	0.0151
R(54)	28717086.8993	0.0510	P(54)	31685990.6298	0.0261
R(56)	28738788.3239	0.0852	P(56)	31709961.3449	0.0434

Line	Band I frequency (MHz)	Uncertainty (MHz)	Line	Band II frequency (MHz)	Uncertainty (MHz)
R(58)	28759728.1540	0.1355	P(58)	31733347.9642	0.0693
R(60)	28779900.5263	0.2075	P(60)	31756154.6537	0.1068
R(62)	28799299.3572	0.3078	P(62)	31778385.6867	0.1594
R(64)	28817918.3393	0.4447	P(64)	31800045.4375	0.2317
R(66)	28835750.9374	0.6283	P(66)	31821138.3761	0.3291
R(68)	28852790.3843	0.8707	P(68)	31841669.0622	0.4581
R(70)	28869029.6768	1.1863	P(70)	31861642.1394	0.6268

Frequencies for the $01^{1e}1\text{-}(11^{1e}0,03^{1e}0)_I$ and $01^{1e}1\text{-}(11^{1e}0,03^{1e}0)_{II}$ Bands of $^{12}C^{16}O_2$ with the Estimated 2-σ Uncertainties

P(59)	26125213.2723	1.6633	P(59)	30427055.2899	0.1962
P(57)	26191576.6703	1.0880	P(57)	30494640.3229	0.1332
P(55)	26257240.7898	0.6844	P(55)	30561557.5929	0.0865
P(53)	26322208.2302	0.4094	P(53)	30627802.0344	0.0530
P(51)	26386481.4313	0.2286	P(51)	30693368.7014	0.0306
P(49)	26450062.6783	0.1155	P(49)	30758252.7710	0.0175
P(47)	26512954.1076	0.0498	P(47)	30822449.5469	0.0123
P(45)	26575157.7109	0.0191	P(45)	30885954.4624	0.0114
P(43)	26636675.3402	0.0160	P(43)	30948763.0834	0.0109
P(41)	26697508.7115	0.0182	P(41)	31010871.1119	0.0100
P(39)	26757659.4084	0.0177	P(39)	31072274.3882	0.0091
P(37)	26817128.8857	0.0160	P(37)	31132968.8940	0.0091
P(35)	26875918.4726	0.0144	P(35)	31192950.7549	0.0102
P(33)	26934029.3751	0.0131	P(33)	31252216.2430	0.0118
P(31)	26991462.6787	0.0119	P(31)	31310761.7788	0.0134
P(29)	27048219.3509	0.0106	P(29)	31368583.9339	0.0147
P(27)	27104300.2431	0.0096	P(27)	31425679.4328	0.0155
P(25)	27159706.0925	0.0093	P(25)	31482045.1550	0.0157
P(23)	27214437.5237	0.0097	P(23)	31537678.1367	0.0154
P(21)	27268495.0505	0.0104	P(21)	31592575.5725	0.0147
P(19)	27321879.0769	0.0108	P(19)	31646734.8172	0.0137
P(17)	27374589.8987	0.0108	P(17)	31700153.3868	0.0127
P(15)	27426627.7040	0.0104	P(15)	31752828.9602	0.0119
P(13)	27477992.5747	0.0098	P(13)	31804759.3803	0.0113
P(11)	27528684.4867	0.0096	P(11)	31855942.6551	0.0113
P(9)	27578703.3113	0.0101	P(9)	31906376.9582	0.0116
P(7)	27628048.8151	0.0113	P(7)	31956060.6304	0.0122
P(5)	27676720.6609	0.0127	P(5)	32004992.1796	0.0129
P(3)	27724718.4080	0.0141	P(3)	32053170.2819	0.0136
R(1)	27841759.7696	0.0152	P(1)	32170312.0391	0.0149
R(3)	27887393.2105	0.0146	P(3)	32215845.0845	0.0151
R(5)	27932349.2934	0.0135	P(5)	32260620.8121	0.0152
R(7)	27976627.0108	0.0124	P(7)	32304638.8261	0.0152
R(9)	28020225.2521	0.0115	P(9)	32347898.8990	0.0150
R(11)	28063142.8031	0.0110	P(11)	32390400.9714	0.0148
R(13)	28105378.3457	0.0109	P(13)	32432145.1513	0.0145
R(15)	28146930.4576	0.0109	P(15)	32473131.7137	0.0142
R(17)	28187797.6116	0.0107	P(17)	32513361.0997	0.0140
R(19)	28227978.1750	0.0103	P(19)	32552833.9153	0.0140
R(21)	28267470.4088	0.0099	P(21)	32591550.9309	0.0141
R(23)	28306272.4666	0.0099	P(23)	32629513.0796	0.0143
R(25)	28344382.3939	0.0107	P(25)	32666721.4564	0.0144
R(27)	28381798.1267	0.0122	P(27)	32703177.3164	0.0142
R(29)	28418517.4902	0.0141	P(29)	32738882.0732	0.0136
R(31)	28454538.1976	0.0165	P(31)	32773837.2976	0.0136
R(33)	28489857.8477	0.0213	P(33)	32808044.7156	0.0174
R(35)	28524473.9240	0.0312	P(35)	32841506.2063	0.0279
R(37)	28558383.7917	0.0486	P(37)	32874223.8000	0.0462
R(39)	28591584.6963	0.0754	P(39)	32906199.6761	0.0735
R(41)	28624073.7602	0.1131	P(41)	32937436.1606	0.1114
R(43)	28655847.9806	0.1644	P(43)	32967935.7238	0.1624
R(45)	28686904.2261	0.2328	P(45)	32997700.9775	0.2292

Line	Band I frequency (MHz)	Uncertainty (MHz)	Line	Band II frequency (MHz)	Uncertainty (MHz)
R(47)	28717239.2334	0.3239	P(47)	33026734.6728	0.3151
R(49)	28746849.6038	0.4465	P(49)	33055039.6965	0.4238
R(51)	28775731.7988	0.6142	P(51)	33082619.0689	0.5595
R(53)	28803882.1361	0.8465	P(53)	33109475.9403	0.7272

Frequencies for the $01^{1f}1\text{-}(11^{1f}0,03^{1f}0)_I$ and $01^{1f}1\text{-}(11^{1f}0,03^{1f}0)_{II}$ Bands of $^{12}C^{16}O_2$ with the Estimated 2-σ Uncertainties

P(60)	26051570.0104	4.4521	P(60)	30355115.0204	0.2752
P(58)	26120964.4932	3.0629	P(58)	30425283.5969	0.1926
P(56)	26189552.8496	2.0516	P(56)	30494732.8293	0.1301
P(54)	26257339.6006	1.3305	P(54)	30563455.6325	0.0840
P(52)	26324329.0344	0.8289	P(52)	30631445.1076	0.0512
P(50)	26390525.2136	0.4901	P(50)	30698694.5456	0.0292
P(48)	26455931.9824	0.2698	P(48)	30765197.4310	0.0163
P(46)	26520552.9722	0.1334	P(46)	30830947.4444	0.0111
P(44)	26584391.6075	0.0551	P(44)	30895938.4662	0.0104
P(42)	26647451.1105	0.0181	P(42)	30960164.5794	0.0105
P(40)	26709734.5057	0.0151	P(40)	31023620.0723	0.0105
P(38)	26771244.6242	0.0174	P(38)	31086299.4415	0.0107
P(36)	26831984.1067	0.0157	P(36)	31148197.3941	0.0114
P(34)	26891955.4069	0.0126	P(34)	31209308.8510	0.0126
P(32)	26951160.7945	0.0105	P(32)	31269628.9481	0.0138
P(30)	27009602.3576	0.0096	P(30)	31329153.0395	0.0147
P(28)	27067282.0045	0.0092	P(28)	31387876.6994	0.0151
P(26)	27124201.4662	0.0090	P(26)	31445795.7236	0.0149
P(24)	27180362.2977	0.0089	P(24)	31502906.1318	0.0141
P(22)	27235765.8792	0.0090	P(22)	31559204.1695	0.0128
P(20)	27290413.4182	0.0093	P(20)	31614686.3091	0.0113
P(18)	27344305.9494	0.0096	P(18)	31669349.2515	0.0098
P(16)	27397444.3368	0.0097	P(16)	31723189.9280	0.0086
P(14)	27449829.2733	0.0096	P(14)	31776205.5007	0.0081
P(12)	27501461.2824	0.0096	P(12)	31828393.3642	0.0085
P(10)	27552340.7179	0.0101	P(10)	31879751.1463	0.0095
P(8)	27602467.7649	0.0111	P(8)	31930276.7092	0.0107
P(6)	27651842.4399	0.0125	P(6)	31979968.1497	0.0120
P(4)	27700464.5912	0.0139	P(4)	32028823.8002	0.0131
P(2)	27748333.8988	0.0148	P(2)	32076842.2290	0.0139
R(2)	27864709.8633	0.0146	P(2)	32193218.1935	0.0150
R(4)	27909939.2762	0.0135	P(4)	32238298.4853	0.0151
R(6)	27954412.3294	0.0122	P(6)	32282538.0393	0.0153
R(8)	27998127.7801	0.0112	P(8)	32325936.7244	0.0153
R(10)	28041084.2173	0.0107	P(10)	32368494.6458	0.0154
R(12)	28083280.0620	0.0108	P(12)	32410212.1438	0.0155
R(14)	28124713.5668	0.0110	P(14)	32451089.7941	0.0155
R(16)	28165382.8151	0.0112	P(16)	32491128.4063	0.0154
R(18)	28205285.7213	0.0111	P(18)	32530329.0234	0.0152
R(20)	28244420.0302	0.0110	P(20)	32568692.9211	0.0149
R(22)	28282783.3158	0.0114	P(22)	32606221.6061	0.0147
R(24)	28320372.9812	0.0129	P(24)	32642916.8154	0.0144
R(26)	28357186.2574	0.0149	P(26)	32678780.5147	0.0140
R(28)	28393220.2023	0.0168	P(28)	32713814.8971	0.0133
R(30)	28428471.6994	0.0175	P(30)	32748022.3813	0.0120
R(32)	28462937.4565	0.0165	P(32)	32781405.6101	0.0106
R(34)	28496614.0042	0.0142	P(34)	32813967.4482	0.0122
R(36)	28529497.6934	0.0163	P(36)	32845710.9809	0.0212
R(38)	28561584.6939	0.0309	P(38)	32876639.5111	0.0385
R(40)	28592870.9914	0.0593	P(40)	32906756.5580	0.0646
R(42)	28623352.3850	0.1054	P(42)	32936065.8540	0.1015
R(44)	28653024.4839	0.1779	P(44)	32964571.3426	0.1518
R(46)	28681882.7038	0.2907	P(46)	32992277.1760	0.2184
R(48)	28709922.2632	0.4635	P(48)	33019187.7118	0.3048
R(50)	28737138.1785	0.7231	P(50)	33045307.5105	0.4152

INFRARED AND FAR-INFRARED ABSORPTION FREQUENCY STANDARDS

Arthur Maki

Aside from the CO_2 laser transitions, the absorption spectrum of CO has been more accurately and thoroughly measured than any other spectrum. A bibliography of earlier measurements on CO is given by Maki and Wells,[1] and the present tables were calculated from the measurements referred to in that work. In addition, some new and very accurate frequency measurements[2,3] have been made and were incorporated in the present tables. The frequencies of the rotational transitions of HF and HCl were calculated from constants obtained from fitting the measurements of Evenson et al.[4,5] and Jennings and Wells.[6]

A new report on infrared wavenumber standards from the International Union of Pure and Applied Chemistry, Commission on Molecular Structure and Spectroscopy, may be found in Reference 7.

References

1. Maki, A. G. and Wells, J. S., *Wavenumber Calibration Tables from Heterodyne Frequency Measurements*, NIST Special Publication 821, U.S. Dept. of Commerce, Washington, D.C., 1991.
2. Evenson, K. and Stroh, F., private communication.
3. George, T., Urban, W., and co-workers, private communication.
4. Jennings, D. A., Evenson, K. M., Zink, L. R., Demuynck, C., Destombes, J. L., Lemoine, B., and Johns, J. *W. C., J. Mol. Spectrosc.*, 122, 477–480, 1987.
5. Nolt, I. G., Radostitz, J. V., DiLonardo, G., Evenson, K. M., Jennings, D. A., Leopold, K. R., Vanek, M. D., Zink, L. R., Hinz, A., and Chance, K. V., *J. Mol. Spectrosc.*, 125, 274–287, 1987.
6. Jennings, D. A. and Wells, J. S., *J. Mol. Spectrosc.*, 130, 267–268, 1988.
7. High Resolution Wavenumber Standards for the Infrared, *Pure Appl. Chemistry*, 68, 193, 1996.

Wavenumbers for the $v = 1 - 0$ Band of CO

Wavenumber (unc)*/cm^{-1}	Transition	Wavenumber (unc)/cm^{-1}	Transition
		2147.081132(01)	R(0)
2139.426071(01)	P(1)	2150.856006(01)	R(1)
2135.546178(01)	P(2)	2154.595581(01)	R(2)
2131.631574(01)	P(3)	2158.299710(01)	R(3)
2127.682404(01)	P(4)	2161.968245(01)	R(4)
2123.698816(01)	P(5)	2165.601041(01)	R(5)
2119.680957(01)	P(6)	2169.197949(01)	R(6)
2115.628973(01)	P(7)	2172.758824(01)	R(7)
2111.543012(01)	P(8)	2176.283519(01)	R(8)
2107.423221(01)	P(9)	2179.771887(01)	R(9)
2103.269746(01)	P(10)	2183.223782(01)	R(10)
2099.082734(01)	P(11)	2186.639057(01)	R(11)
2094.862333(01)	P(12)	2190.017565(01)	R(12)
2090.608688(01)	P(13)	2193.359161(01)	R(13)
2086.321947(01)	P(14)	2196.663698(01)	R(14)
2082.002256(01)	P(15)	2199.931030(01)	R(15)
2077.649762(01)	P(16)	2203.161010(01)	R(16)
2073.264612(01)	P(17)	2206.353492(01)	R(17)
2068.846952(01)	P(18)	2209.508331(02)	R(18)
2064.396929(01)	P(19)	2212.625379(02)	R(19)
2059.914688(02)	P(20)	2215.704492(02)	R(20)
2055.400377(02)	P(21)	2218.745522(02)	R(21)
2050.854140(02)	P(22)	2221.748326(03)	R(22)
2046.276126(03)	P(23)	2224.712755(03)	R(23)
2041.666479(03)	P(24)	2227.638666(03)	R(24)
2037.025345(03)	P(25)	2230.525912(04)	R(25)
2032.352870(04)	P(26)	2233.374349(04)	R(26)
2027.649200(04)	P(27)	2236.183829(04)	R(27)
2022.914480(04)	P(28)	2238.954210(05)	R(28)
2018.148857(05)	P(29)	2241.685344(05)	R(29)
2013.352474(05)	P(30)	2244.377088(06)	R(30)
2008.525477(06)	P(31)	2247.029296(07)	R(31)
2003.668012(06)	P(32)	2249.641824(08)	R(32)
1998.780224(07)	P(33)	2252.214527(10)	R(33)
1993.862257(09)	P(34)	2254.747262(14)	R(34)
1988.914257(11)	P(35)	2257.239883(18)	R(35)
1983.936367(14)	P(36)	2259.692248(24)	R(36)
1978.928733(18)	P(37)	2262.104213(33)	R(37)
1973.891500(25)	P(38)	2264.475634(45)	R(38)

Wavenumbers for the $\nu = 1 - 0$ Band of CO

Wavenumber (unc)*/cm^{-1}	Transition	Wavenumber (unc)/cm^{-1}	Transition
1968.824811(34)	P(39)	2266.806368(61)	R(39)
1963.728813(46)	P(40)	2269.096273(81)	R(40)
1958.603648(61)	P(41)	2271.345206(106)	R(41)
1953.449462(82)	P(42)	2273.553027(139)	R(42)

* The uncertainty in the last digits (twice the standard error) is given in parentheses.

Wavenumbers for the $\nu = 2 - 0$ Band of CO

Wavenumber (unc)*/cm^{-1}	Transition	Wavenumber (unc)/cm^{-1}	Transition
		4263.837198(02)	R(0)
4256.217140(02)	P(1)	4267.542066(02)	R(1)
4252.302244(02)	P(2)	4271.176630(02)	R(2)
4248.317633(02)	P(3)	4274.740746(02)	R(3)
4244.263453(02)	P(4)	4278.234264(02)	R(4)
4240.139852(02)	P(5)	4281.657039(02)	R(5)
4235.946975(02)	P(6)	4285.008924(02)	R(6)
4231.684972(02)	P(7)	4288.289772(02)	R(7)
4227.353987(02)	P(8)	4291.499437(02)	R(8)
4222.954169(02)	P(9)	4294.637773(02)	R(9)
4218.485665(02)	P(10)	4297.704631(02)	R(10)
4213.948620(02)	P(11)	4300.699868(02)	R(11)
4209.343182(02)	P(12)	4303.623334(02)	R(12)
4204.669499(02)	P(13)	4306.474886(02)	R(13)
4199.927716(02)	P(14)	4309.254375(02)	R(14)
4195.117980(02)	P(15)	4311.961657(02)	R(15)
4190.240439(02)	P(16)	4314.596584(02)	R(16)
4185.295239(02)	P(17)	4317.159011(02)	R(17)
4180.282526(02)	P(18)	4319.648791(02)	R(18)
4175.202447(02)	P(19)	4322.065779(03)	R(19)
4170.055149(03)	P(20)	4324.409829(03)	R(20)
4164.840777(03)	P(21)	4326.680794(03)	R(21)
4159.559478(03)	P(22)	4328.878530(03)	R(22)
4154.211398(03)	P(23)	4331.002889(04)	R(23)
4148.796683(04)	P(24)	4333.053728(04)	R(24)
4143.315479(04)	P(25)	4335.030899(05)	R(25)
4137.767932(04)	P(26)	4336.934259(06)	R(26)
4132.154187(05)	P(27)	4338.763661(07)	R(27)
4126.474391(06)	P(28)	4340.518961(09)	R(28)
4120.728689(07)	P(29)	4342.200014(11)	R(29)
4114.917226(09)	P(30)	4343.806675(16)	R(30)
4109.040148(12)	P(31)	4345.338799(21)	R(31)
4103.097600(16)	P(32)	4346.796243(29)	R(32)
4097.089728(21)	P(33)	4348.178862(40)	R(33)
4091.016676(29)	P(34)	4349.486513(54)	R(34)
4084.878591(40)	P(35)	4350.719052(73)	R(35)
4078.675618(54)	P(36)	4351.876336(96)	R(36)
4072.407901(73)	P(37)	4352.958224(127)	R(37)
4066.075588(97)	P(38)	4353.964572(166)	R(38)
4059.678822(127)	P(39)	4354.895240(214)	R(39)

* The uncertainty in the last digits (twice the standard error) is given in parentheses.

Wavenumbers for the $\nu = 3 - 0$ Band of CO

Wavenumber (unc)*/cm^{-1}	Transition	Wavenumber (unc)/cm^{-1}	Transition
		6354.179057(13)	R(0)
6346.594000(13)	P(1)	6357.813923(13)	R(1)
6342.644103(13)	P(2)	6361.343487(13)	R(2)
6338.589491(13)	P(3)	6364.767599(13)	R(3)
6334.430309(13)	P(4)	6368.086115(13)	R(4)

Wavenumbers for the $\nu = 3 - 0$ Band of CO

Wavenumber (unc)*/cm^{-1}	Transition	Wavenumber (unc)/cm^{-1}	Transition
6330.166705(13)	P(5)	6371.298887(13)	R(5)
6325.798826(13)	P(6)	6374.405768(12)	R(6)
6321.326819(13)	P(7)	6377.406611(12)	R(7)
6316.750831(12)	P(8)	6380.301271(12)	R(8)
6312.071008(12)	P(9)	6383.089600(12)	R(9)
6307.287498(12)	P(10)	6385.771452(12)	R(10)
6302.400447(12)	P(11)	6388.346680(13)	R(11)
6297.410003(12)	P(12)	6390.815139(13)	R(12)
6292.316311(13)	P(13)	6393.176681(13)	R(13)
6287.119520(13)	P(14)	6395.431160(13)	R(14)
6281.819775(13)	P(15)	6397.578430(13)	R(15)
6276.417224(13)	P(16)	6399.618344(13)	R(16)
6270.912012(13)	P(17)	6401.550757(13)	R(17)
6265.304287(13)	P(18)	6403.375523(13)	R(18)
6259.594194(13)	P(19)	6405.092495(14)	R(19)
6253.781880(13)	P(20)	6406.701527(14)	R(20)
6247.867492(14)	P(21)	6408.202474(14)	R(21)
6241.851176(14)	P(22)	6409.595189(15)	R(22)
6235.733077(14)	P(23)	6410.879527(15)	R(23)
6229.513342(15)	P(24)	6412.055343(16)	R(24)
6223.192117(15)	P(25)	6413.122491(17)	R(25)
6216.769547(16)	P(26)	6414.080825(19)	R(26)
6210.245778(17)	P(27)	6414.930201(23)	R(27)
6203.620957(19)	P(28)	6415.670474(28)	R(28)
6196.895229(23)	P(29)	6416.301500(37)	R(29)
6190.068739(28)	P(30)	6416.823133(50)	R(30)
6183.141633(37)	P(31)	6417.235231(67)	R(31)
6176.114058(50)	P(32)	6417.537649(90)	R(32)
6168.986159(67)	P(33)		
6161.758082(90)	P(34)		

* The uncertainty in the last digits (twice the standard error) is given in parentheses.

Frequencies and Wavenumbers for the Rotational Lines of CO

Frequency/MHz	Uncertainty*/MHz	J'	J''	Wavenumber/cm^{-1}	Uncertainty*/cm^{-1}
115271.2029	0.0004	1	0	3.84503345	0.00000001
230538.0016	0.0008	2	1	7.68991999	0.00000003
345795.9923	0.0012	3	2	11.53451273	0.00000004
461040.7712	0.0016	4	3	15.37866477	0.00000005
576267.9350	0.0019	5	4	19.22222923	0.00000006
691473.0809	0.0021	6	5	23.06505926	0.00000007
806651.8065	0.0023	7	6	26.90700800	0.00000008
921799.7104	0.0025	8	7	30.74792863	0.00000008
1036912.3919	0.0027	9	8	34.58767438	0.00000009
1151985.4515	0.0029	10	9	38.42609848	0.00000010
1267014.4906	0.0031	11	10	42.26305422	0.00000010
1381995.1119	0.0034	12	11	46.09839491	0.00000011
1496922.9195	0.0038	13	12	49.93197392	0.00000013
1611793.5189	0.0042	14	13	53.76364468	0.00000014
1726602.5173	0.0047	15	14	57.59326065	0.00000016
1841345.5237	0.0052	16	15	61.42067535	0.00000017
1956018.1486	0.0057	17	16	65.24574239	0.00000019
2070616.0050	0.0061	18	17	69.06831542	0.00000020
2185134.7075	0.0065	19	18	72.88824816	0.00000022
2299569.8733	0.0069	20	19	76.70539441	0.00000023
2413917.1217	0.0071	21	20	80.51960806	0.00000024
2528172.0747	0.0073	22	21	84.33074306	0.00000024
2642330.3567	0.0074	23	22	88.13865346	0.00000025
2756387.5949	0.0075	24	23	91.94319341	0.00000025

Frequencies and Wavenumbers for the Rotational Lines of CO

Frequency/MHz	Uncertainty*/MHz	J'	J''	Wavenumber/cm^{-1}	Uncertainty*/cm^{-1}
2870339.4194	0.0077	25	24	95.74421713	0.00000026
2984181.4631	0.0080	26	25	99.54157896	0.00000027
3097909.3621	0.0085	27	26	103.33513334	0.00000028
3211518.7558	0.0090	28	27	107.12473480	0.00000030
3325005.2869	0.0096	29	28	110.91023800	0.00000032
3438364.6013	0.0102	30	29	114.69149772	0.00000034
3551592.3489	0.0107	31	30	118.46836884	0.00000036
3664684.1829	0.0111	32	31	122.24070637	0.00000037
3777635.7608	0.0118	33	32	126.00836545	0.00000039
3890442.7435	0.0137	34	33	129.77120137	0.00000046
4003100.7965	0.0179	35	34	133.52906952	0.00000060
4115605.5892	0.0254	36	35	137.28182546	0.00000085
4227952.7954	0.0370	37	36	141.02932487	0.00000123
4340138.0932	0.0531	38	37	144.77142361	0.00000177
4452157.1657	0.0746	39	38	148.50797766	0.00000249
4564005.7001	0.1025	40	39	152.23884318	0.00000342

* The uncertainty given is twice the standard error.

Frequencies and Wavenumbers for the Rotational Lines of HF

Frequency/MHz	Uncertainty*/MHz	J'	J''	Wavenumber/cm^{-1}	Uncertainty*/cm^{-1}
1232476.21	0.12	1	0	41.110981	0.000004
2463428.09	0.19	2	1	82.171116	0.000006
3691334.81	0.25	3	2	123.129676	0.000008
4914682.58	0.51	4	3	163.936165	0.000017
6131968.11	1.10	5	4	204.540439	0.000037
7341702.00	2.00	6	5	244.892818	0.000067
8542412.1	3.21	7	6	284.944197	0.000107
9732646.8	4.72	8	7	324.646153	0.000157
10910978.2	6.51	9	8	363.951056	0.000217
12076004.8	8.55	10	9	402.81216	0.000285
13226355.2	10.81	11	10	441.18372	0.000361
14360689.8	13.25	12	11	479.02105	0.00044
15477704.4	15.86	13	12	516.28065	0.00053
16576131.8	18.61	14	13	552.92024	0.00062
17654744.4	21.48	15	14	588.89888	0.00072
18712356.5	24.44	16	15	624.17703	0.00082
19747825.6	27.43	17	16	658.71656	0.00092
20760054.3	30.32	18	17	692.4809	0.00101
21747991.7	32.91	19	18	725.4349	0.00110
22710634.7	34.94	20	19	757.5452	0.00117
23647028.7	36.08	21	20	788.7800	0.00120
24556268.8	35.93	22	21	819.1090	0.00120
25437499.9	34.12	23	22	848.5037	0.00114
26289917.4	30.32	24	23	876.9373	0.00101
27112767.2	24.41	25	24	904.38457	0.00081
27905345.6	16.88	26	25	930.82214	0.00056
28666999.3	10.80	27	26	956.22817	0.00036
29397124.8	14.65	28	27	980.58253	0.00049
30095168.2	24.62	29	28	1003.86676	0.00082
30760624.2	33.36	30	29	1026.0640	0.00111
31393035.7	36.17	31	30	1047.1590	0.00121

* The uncertainty given is twice the standard error.

Frequencies and Wavenumbers for the Rotational Lines of $H^{35}Cl$

Frequency/MHz	Uncertainty*/MHz	J'	J''	Wavenumber/cm^{-1}	Uncertainty*/cm^{-1}
1876226.517	0.065	3	2	62.584180	0.000002
2499864.439	0.066	4	3	83.386502	0.000002
3121986.563	0.064	5	4	104.138262	0.000002
3742216.601	0.076	6	5	124.826909	0.000003
4360180.042	0.098	7	6	145.439951	0.000003
4975504.51	0.11	8	7	165.964966	0.000004
5587820.10	0.12	9	8	186.389615	0.000004
6196759.76	0.22	10	9	206.701656	0.000007
6801959.63	0.50	11	10	226.888951	0.000017
7403059.41	1.02	12	11	246.939481	0.000034
7999702.7	1.8	13	12	266.841359	0.000062
8591537.3	3.1	14	13	286.582837	0.000103
9178215.8	4.8	15	14	306.152324	0.000161

* The uncertainty given is twice the standard error.

Frequencies and Wavenumbers for the Rotational Lines of $H^{37}Cl$

Frequency/MHz	Uncertainty*/MHz	J'	J''	Wavenumber/cm^{-1}	Uncertainty*/cm^{-1}
1873410.72	0.05	3	2	62.490255	0.000002
2496115.33	0.05	4	3	83.261445	0.000002
3117308.69	0.05	5	4	103.982225	0.000002
3736615.64	0.06	6	5	124.640082	0.000002
4353662.84	0.08	7	6	145.222561	0.000003
4968079.04	0.09	8	7	165.717279	0.000003
5579495.53	0.10	9	8	186.111938	0.000003
6187546.42	0.19	10	9	206.394332	0.000006
6791869.04	0.45	11	10	226.552365	0.000015
7392104.3	0.9	12	11	246.574057	0.000030
7987896.9	1.6	13	12	266.447561	0.000054
8578896.1	2.7	14	13	286.161170	0.000089

* The uncertainty given is twice the standard error.

SENSITIVITY OF THE HUMAN EYE TO LIGHT OF DIFFERENT WAVELENGTHS


The human eye responds to electromagnetic radiation in the wavelength range from about 360 nm (violet) to 820 nm (red), with a peak sensitivity near 555 nm. While the detailed shape of this response curve depends on the individual person, studies on representative samples of human subjects have led to adoption of a standard function relating the perceived brightness (luminous flux) to the actual power of the spectral radiation. This function is referred to as $V(\lambda)$, the photopic spectral luminous efficiency function, and it plays an important role in photometry.

The function $V(\lambda)$, as adopted by the International Commission on Illumination (CIE) is tabulated and plotted below.

References

1. *The Basis for Physical Photometry*, CIE Publication #18.2, 1983.
2. *CIE Standard Colorimetric Observers*, ISO/CIE #10527, 1991.
3. *Kaye and Laby Tables of Physical and Chemical Constants, Sixteenth Edition*, Longman Group Ltd., Harlow, Essex, 1995.

λ/nm	$V(\lambda)$	λ/nm	$V(\lambda)$	λ/nm	$V(\lambda)$
360	0.000004	520	0.710000	670	0.032000
370	0.000012	530	0.862000	680	0.017000
380	0.000039	540	0.954000	690	0.008210
390	0.000120	550	0.994950	700	0.004102
400	0.000396	555	1.000000	710	0.002091
410	0.001210	560	0.995000	720	0.001047
420	0.004000	570	0.952000	730	0.000520
430	0.011600	580	0.870000	740	0.000249
440	0.023000	590	0.757000	750	0.000120
450	0.038000	600	0.631000	760	0.000060
460	0.060000	610	0.503000	770	0.000030
470	0.090980	620	0.381000	780	0.000015
480	0.139020	630	0.265000	790	0.000007
490	0.208020	640	0.175000	800	0.000004
500	0.323000	650	0.107000	810	0.000002
510	0.503000	660	0.061000	820	0.000001



INDEX OF REFRACTION OF INORGANIC CRYSTALS

This table lists the index of refraction of selected crystalline inorganic compounds. When, available, values are give as a function of wavelength in the range from the ultraviolet to the far infrared region. For each compound a value at 589 nm, the wavelength of the principal sodium line, is given. The data have been taken from the references indicated; in many cases, data from a reference have been refitted to generate the index of refraction at the wavelengths used in this table. All values refer to ambient temperature. Entries marked by * are based on extrapolation beyond the range of available experimental data.

Compounds belonging to the cubic crystal system have only a single refractive index value, but other systems are anisotropic, so that the crystal is characterized by two or three unique indexes. Hexagonal, rhombohedral, and tetragonal crystals have two unique indexes which are traditionally labeled n_o and n_e for "ordinary ray" and "extraordinary ray". Orthorhombic, monoclinic, and triclinic crystals are characterized by three indexes which are here called n_x, n_y, and n_z. The table indicates the crystal system for each entry in order to identify the material uniquely.

The refractive index and other optical properties for metals, semiconductors, and certain other compounds can be found in the tables "Optical Properties of Selected Elements" and "Optical Properties of Selected Inorganic and Organic Solids" in Section 12 of this *Handbook*.

References

1. Li, H. H., "Refractive Index of Alkali Halides and its Wavelength and Temperature Derivatives", *J. Phys. Chem. Ref. Data* 5, 329, 1976.
2. Li, H. H., "Refractive Index of Alkaline Earth Halides and its Wavelength and Temperature Derivatives", *J. Phys. Chem. Ref. Data* 9, 161, 1980.
3. Li, H. H., "Refractive Index of ZnS, ZnSe, and ZnTe and its Wavelength and Temperature Derivatives", *J. Phys. Chem. Ref. Data* 13, 103, 1984.
4. Shannon, R. D., Shannon, R. C., Medenbach, O., and Fischer, R. X., "Refractive Index and Dispersion of Fluorides and Oxides", *J. Phys. Chem. Ref. Data* 31, 931, 2002.
5. Gray, D. E., ed., *American Institute of Physics Handbook*, Sec. 6b, p. **6**-12, McGraw-Hill, New York, 1972.
6. Landolt-Börnstein Numerical Data and Functional Relationships in Science and *Technology*, III/11, Elastic, Piezoelectric, Pyroelectric, Piezooptic, Electrooptic Constants, and Nonlinear Dielectric Susceptibilities of Crystals, Springer-Verlag, Berlin, 1979.
7. Landolt-Börnstein Numerical Data and Functional Relationships in Science and *Technology*, III/30A, High Frequency Properties of Dielectric Crystals. Piezooptic and Electrooptic Constants, Springer-Verlag, Berlin, 1996.
8. Weber, M. J., *CRC Handbook of Laser Science and Technology*, Vol. IV. Optical Materials. Part 2: Properties, CRC Press, Boca Raton, FL, 1986.

Compound	Crystal system	Ray	Index of Refraction at the Indicated Wavelength								Ref.
			300 nm	589 nm	750 nm	1 μm	2 μm	5 μm	10 μm	20 μm	
AgCl	cub	n		2.0668	2.0401	2.0224	2.0062	1.9975	1.9803	1.9069	5
$AlPO_4$	rhomb	n_o		1.5247	1.5203	1.5161	1.5034				6
	rhomb	n_e		1.5338	1.5290	1.5245	1.5116				6
Al_2O_3	hex	n_o		1.7673							4
	hex	n_e		1.7598							4
As_2O_3[a]	cub	n		1.7537							4
BaF_2	cub	n	1.5010	1.4744	1.4712	1.4686	1.4647	1.4511	1.4014		2
BaO	cub	n		1.9841							4
$BaSO_4$	orth	n_x		1.6362							4
	orth	n_y		1.6374							4
	orth	n_z		1.6480							4
$BaTiO_3$	tetr	n_o		2.4405							4
	tetr	n_e		2.3831							4
$BaWO_4$	tetr	n_o		1.8426							4
	tetr	n_e		1.8405							4
BeO	hex	n_o		1.7184							4
	hex	n_e		1.7342							4
$BeSO_4 \cdot 4H_2O$	tetr	n_o		1.4713							4
	tetr	n_e		1.4328							4
$CaCO_3$[b]	hex	n_o	1.7216	1.6584	1.6503	1.6436	1.6249				5
	hex	n_e	1.5145	1.4864	1.4828	1.4801	1.4753				5
CaF_2	cub	n	1.4540	1.4338	1.4311	1.4289	1.4239	1.3990	1.299		2
CaO	cub	n		1.8396							4
$CaSO_4$	orth	n_x		1.5698							4
	orth	n_y		1.5755							4
	orth	n_z		1.6137							4
$CaSO_4 \cdot 2H_2O$	monocl	n_x		1.5207							4
	monocl	n_y		1.5227							4
	monocl	n_z		1.5304							4
$CaWO_4$	tetr	n_o		1.9195							4
	tetr	n_e		1.9355							4
CdS	hex	n_o		2.507	2.390	2.334					5

Compound	Crystal system	Ray	Index of Refraction at the Indicated Wavelength 300 nm	589 nm	750 nm	1 μm	2 μm	5 μm	10 μm	20 μm	Ref.
	hex	n_e		2.525	2.409	2.352					5
CdSe	hex	n_o			2.68*	2.5502	2.4682	2.4483	2.4331		7
	hex	n_e			2.69*	2.5696	2.4873	2.4676	2.4514		7
CdTe	cub	n							2.6724	2.6302	7
CeF_3	hex	n_o		1.6183							4
	hex	n_e		1.6113							4
CsBr	cub	n	1.8047	1.6974	1.6861	1.6784	1.6711	1.6678	1.6630	1.6439	1
CsCl	cub	n	1.712	1.640	1.631	1.626	1.620	1.616	1.606	1.563	1
$CsClO_4$	orth	n_x		1.4752							4
	orth	n_y		1.4788							4
	orth	n_z		1.4804							4
CsF	cub	n	1.506	1.477	1.474	1.472	1.469*	1.461*	1.436*	1.32*	1
CsI	cub	n	1.9790	1.7873	1.7694	1.7576	1.7465	1.7428	1.7396	1.7280	1
Cs_2SO_4	orth	n_x		1.5598							4
	orth	n_y		1.5644							4
	orth	n_z		1.5662							4
CuBr	cub	n		2.117							7
CuCl	cub	n		1.9727	1.9391				1.9245		7
$CuSO_4 \cdot 5H_2O$	tricl	n_x		1.5140							4
	tricl	n_y		1.5367							4
	tricl	n_z		1.5436							4
Dy_2O_3	cub	n		1.9757							4
FeF_2	tetr	n_o		1.514							4
	tetr	n_e		1.524							4
Gd_2O_3	cub	n		1.96							4
HgS	rhomb	n_o		2.9413	2.7770	2.7120	2.6305		2.6018		6
	rhomb	n_e		3.3072	3.0896	3.0050	2.8776		2.8522		6
KBr	cub	n	1.6482	1.5598	1.5498	1.5444	1.5383	1.5345	1.5264	1.4924	1
KCl	cub	n	1.5455	1.4902	1.4840	1.4798	1.4753	1.4704	1.4564	1.3946	1
$KClO_4$	orth	n_x		1.4730							4
	orth	n_y		1.4736							4
	orth	n_z		1.4768							4
KF	cub	n	1.380	1.362	1.360	1.358	1.355	1.344	1.304*	1.09*	1
KH_2AsO_4	tetr	n_o		1.5674							7
	tetr	n_e		1.5179							7
KH_2PO_4	tetr	n_o	1.5450	1.5093	1.5030	1.4957					5
	tetr	n_e	1.4977	1.4682	1.4641	1.4606					5
KI	cub	n	1.834*	1.665	1.650	1.640	1.631	1.627	1.620	1.593	1
KIO_3	tricl	n_x		1.6959							7
	tricl	n_y		1.8317							7
	tricl	n_z		1.8343							7
KIO_4	tetr	n_o		1.6205							4
	tetr	n_e		1.6476							4
$KNbO_3$	orth	n_x		2.2480	2.3395	2.2612					7
	orth	n_y		2.3464	2.2959	2.2622					7
	orth	n_x		2.1803	2.1457	2.1288					7
K_2SO_4	orth	n_x		1.4934							4
	orth	n_y		1.4947							4
	orth	n_z		1.4973							4
LaF_3	hex	n_o		1.605							4
	hex	n_e		1.599							4
LiBr	cub	n	1.810	1.783	1.781	1.778	1.774*	1.756*	1.68*	1.33*	1
LiCl	cub	n	1.677	1.662	1.660	1.658	1.654*	1.62*	1.53*		1
$LiClO_4 \cdot 3H_2O$	hex	n_o		1.4832							4
	hex	n_e		1.4384							4
LiF	cub	n	1.4087	1.3921	1.3895	1.3871	1.3786	1.3266	1.1005		1
LiI	cub	n	1.979	1.955	1.952	1.950	1.948*	1.940*	1.91*	1.77*	1
$LiIO_3$	hex	n_o		1.8875	1.8713	1.8589	1.8410				6
	hex	n_e		1.7400	1.7268	1.7179	1.7062				6
$LiNbO_3$	rhomb	n_o		2.3007	2.2632	2.2370					7

Compound	Crystal system	Ray	Index of Refraction at the Indicated Wavelength								Ref.
			300 nm	589 nm	750 nm	1 μm	2 μm	5 μm	10 μm	20 μm	
	rhomb	n_e		2.2116	2.1804	2.1567					7
$LiTaO_3$	rhomb	n_o		2.1864	2.1590	2.1391	2.1066				7
	rhomb	n_e		2.1908	2.1634	2.1432	2.1115				7
$Li_2SO_4·H_2O$	monocl	n_x		1.4615							4
	monocl	n_y		1.4765							4
	monocl	n_z		1.4863							4
Lu_2O_3	cub	n		1.9349							4
MgF_2	tetr	n_o	1.3930	1.3776	1.375	1.373	1.368	1.34	1.21		2
	tetr	n_e	1.4055	1.3894	1.387	1.385	1.379	1.34	1.21		2
MgO	cub	n		1.7355	1.7283	1.7228	1.7084	1.6361			5
$MgSO_4·7H_2O$	orth	n_x		1.4326							4
	orth	n_y		1.4555							4
	orth	n_z		1.4607							4
MnF_2	tetr	n_o		1.472							4
	tetr	n_e		1.501							4
$NH_4H_2AsO_4$	tetr	n_o	1.6401	1.5777	1.5704	1.5583					7
	tetr	n_e	1.5754	1.5232	1.5179	1.5101					7
$NH_4H_2PO_4$	tetr	n_o	1.5668	1.5247	1.5187	1.5084					7
	tetr	n_e	1.5137	1.4797	1.4754	1.4694					7
NaBr	cub	n	1.748	1.642	1.631	1.623	1.616	1.609	1.593*	1.520*	1
$NaBrO_3$	cub	n		1.6168							4
NaCl	cub	n	1.6066	1.5441	1.5369	1.5320	1.5265	1.5188	1.4947	1.382*	1
$NaClO_3$	cub	n		1.5151							7
NaF	cub	n	1.3424	1.3252	1.3231	1.3214	1.3179	1.3017	1.2400		1
$NaH_2PO_4·2H_2O$	orth	n_x		1.4400							7
	orth	n_y		1.4628							7
	orth	n_z		1.4814							7
NaI	cub	n	1.93*	1.774	1.758	1.74	1.73*	1.73*	1.71*	1.66*	1
$NaNO_2$	orth	n_x		1.6547							7
	orth	n_y		1.3455							7
	orth	n_z		1.4125							7
$NaNO_3$	rhomb	n_o		1.5840							5
	rhomb	n_e		1.3340							5
$Na_2HPO_4·7H_2O$	monocl	n_x		1.4411							4
	monocl	n_y		1.4423							4
	monocl	n_z		1.4525							4
Na_2SO_4	orth	n_x		1.4669							4
	orth	n_y		1.4730							4
	orth	n_z		1.4809							4
NdF_3	hex	n_o		1.6191							4
	hex	n_e		1.6132							4
Nd_2O_3	cub	n		1.92							4
NiF_2	tetr	n_o		1.526							4
	tetr	n_e		1.561							4
$NiSO_4·6H_2O$	tetr	n_o		1.5107							4
	tetr	n_e		1.4870							4
PbF_2	cub	n	1.94*	1.767	1.754	1.745	1.73	1.70	1.66	1.32	5
$PbSO_4$	orth	n_x		1.8780							4
	orth	n_y		1.8834							4
	orth	n_z		1.8945							4
PrF_3	hex	n_o		1.6207							4
	hex	n_e		1.6146							4
RbBr	cub	n	1.639	1.553	1.544	1.538	1.532	1.530	1.525	1.505*	1
RbCl	cub	n	1.549	1.493	1.487	1.483	1.479	1.475	1.465	1.424*	1
$RbClO_4$	orth	n_x		1.4691							4
	orth	n_y		1.4701							4
	orth	n_z		1.4732							4
RbF	cub	n	1.428*	1.397	1.394	1.391	1.388	1.379	1.346	1.19*	1
RbH_2AsO_4	tetr	n_o	1.6183	1.5603	1.5538	1.5432					7
	tetr	n_e	1.5718	1.5232	1.5184	1.5121					7

Compound	Crystal system	Ray	Index of Refraction at the Indicated Wavelength								Ref.
			300 nm	589 nm	750 nm	1 μm	2 μm	5 μm	10 μm	20 μm	
RbH_2PO_4	tetr	n_o	1.5434	1.5078	1.5021	1.4941					7
	tetr	n_e	1.5106	1.4791	1.4754	1.4704					7
RbI	cub	n	1.808	1.647	1.633	1.623	1.615	1.612	1.608	1.595	1
Rb_2SO_4	orth	n_x		1.5131							4
	orth	n_y		1.5133							4
	orth	n_z		1.5144							4
Sb_2O_3[c]	cub	n		2.8017							4
Sc_2O_3	cub	n		1.9943							4
SiO_2[d]	hex	n_o	1.5733	1.5442	1.5394	1.5350	1.5209				5
	hex	n_e	1.5882	1.5534	1.5484	1.5438	1.5291				5
SnO_2	tetr	n_o		1.993							4
	tetr	n_e		2.088							4
SrF_2	cub	n	1.459	1.4380	1.435	1.433	1.429	1.412	1.35		2
SrO	cub	n		1.8710							4
$SrSO_4$	orth	n_x		1.6214							4
	orth	n_y		1.6231							4
	orth	n_z		1.6303							4
$SrTiO_3$	cub	n		2.4082	2.3525	2.3160	2.2676	2.1205			5
$SrWO_4$	tetr	n_o		1.8618							4
	tetr	n_e		1.8719							4
TbF_3	hex	n_o		1.6034							4
	hex	n_e		1.5603							4
TeO_2	tetr	n_o		2.2738		2.2080					7
	tetr	n_e		2.4295		2.3520					7
ThO_2	cub	n		2.1113							4
TiO_2[e]	tetr	n_o		2.612	2.533	2.485	2.399	2.220			5
	tetr	n_e		2.910	2.805	2.748					5
	tetr	n_o		2.562							4
	tetr	n_e		2.489							4
TlBr	cub	n		2.418	2.350	2.289	2.103	1.984	2.339	2.322	5
TlCl	cub	n		2.247	2.198	2.145	1.986	1.891	2.193		5
$TlClO_4$	orth	n_x		1.6427							4
	orth	n_y		1.6446							4
	orth	n_z		1.6542							4
Tl_2SO_4	orth	n_x		1.8604							4
	orth	n_y		1.8676							4
	orth	n_z		1.8857							4
Y_2O_3	cub	n		1.930							4
Yb_2O_3	cub	n		1.9468							4
ZnF_2	tetr	n_o		1.495							4
	tetr	n_e		1.525							4
ZnO	hex	n_o		2.0036	1.9662	1.9435	1.9197				7
	hex	n_e		2.0199	1.9821	1.9589	1.9330				7
ZnS[f]	cub	n		2.3691	2.3232	2.2932	2.2633				7
ZnS[g]	hex	n_o		2.372	2.331	2.303	2.26	2.25	2.20		3,5
	hex	n_e		2.368	2.327	2.301					5
ZnSe	cub	n		2.6222	2.5384	2.4888	2.4462	2.4296	2.4065		3
ZnTe	cub	n		3.060	2.880	2.789	2.719	2.698	2.684		3
$ZrSiO_4$[h]	tetr	n_o		1.9255							4
	tetr	n_e		1.9843							4

[*] Provisional value based on extrapolation beyond the range of experimental data.

[a] Arsenolite

[b] Calcite

[c] Senarmontite

[d] α-Quartz

[e] Rutile

[f] Sphalerite

[g] Wurtzite

[h] Zircon

PROTON AFFINITIES

Proton affinity is a useful parameter for describing gas phase ion-molecule reactions in fields such as atmospheric chemistry, plasma chemistry, mass spectrometry, and astrophysics. The proton affinity E_{pa} (often designated in the literature as PA) of a molecular species M is defined as the negative of the enthalpy change for the gas phase reaction

$$M + H^+ \rightarrow MH^+.$$

A closely related quantity is the gas phase basicity $\Delta_{base}G°$ (often designated as GB), which is the negative of the Gibbs energy change for the same reaction. Thus the two are related by

$$\Delta_{base}G° = E_{pa} + T\Delta S,$$

where T is the temperature and ΔS is the entropy change in the reaction (which can be calculated if the molecular structure of M and M^+ is known).

Direct measurement of the proton affinity is possible for only a few molecules, mainly olefins and carbonyl compounds. However, these measurements have been used to establish a scale of E_{pa} values that permits proton affinities to be determined for many other molecules, including unstable species and reaction intermediates. The basis for this scale is described by Hunter and Lias in Reference 1.

The E_{pa} and $\Delta_{base}G°$ values at a temperature of 298 K are tabulated below for selected molecules. Many values are given to one decimal place, but the majority are not accurate to better than one or two kilojoules per mole. The methods of measurement are described in Reference 1, which contains a much more extensive and detailed tabulation.

Compounds are listed by molecular formula in the Hill order, but with all compounds that do not contain carbon appearing before those that do contain carbon.

References

1. Hunter, E. P. L., and Lias, S. G., *J. Phys. Chem. Ref. Data* 27, 413, 1998.
2. Hunter, E. P., and Lias, S. G., "Proton Affinity Evaluation", in *NIST Chemistry WebBook*, NIST Standard Reference Database No. 69, Linstrom, P. J., and Mallard, W. G., Eds., March 2003, National Institute of Standards and Technology, Gaithersburg, MD 20899, <http://webbook.nist.gov>.
3. Do, K., Klein, T. P., Pommerening, C. A., Bachrach, S. M., and Sunderlin, L. S., *J. Am. Chem. Soc.* 120, 6093, 1998.
4. Kim, H.-T., Green, R. J., Qian, J., and Anderson, S. L., *J. Chem. Phys.* 112, 5717, 2000.
5. Park, S. T., Kim, S. K., and Kim, M. S., *J. Chem. Phys.* 114, 5568, 2001.
6. Hiraoka, K., Mizuno, T., Eguchi, D., Takao, T., and Ino, S., *J. Chem. Phys.* 116, 7574, 2002.
7. Oresmaa, L. O., Haukka, M., Vainiotalo, P., and Pakkanen, T. A., *J. Org. Chem*. 67, 8216, 2002.
8. Wang, F., Ma, S., Zhang, D., and Cooks, R. G., *J. Phys. Chem. A* 102, 2988, 1998.
9. Bouchoux, G., Gal, J.-F., Szulejko, J. E., McMahon, T. B., Tortajada, J., Luna, A., Yanez, M., and Mo, O., *J. Phys. Chem. A* 102, 9183, 1998.
10. van Beelen, E., Koblenz, T. A., Ingemann, S. and Hammerum, S., *J. Phys. Chem. A* 108, 2728, 2004.

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
Ar	Argon	369.2	346.3	
AsF_3	Arsenic(III) fluoride	636.7	604.2	
AsH_3	Arsine	747.9	712.0	
BHO_2	Metaboric acid	763.0	730.5	
BH_3O_3	Boric acid	728.1	698.4	
B_2H_6	Diborane	615	586.0	
$B_3H_6N_3$	Borazine	802.5	772.8	
B_4H_{10}	Tetraborane(10)	605	572.5	
B_5H_9	Pentaborane(9)	699.4	666.9	
BaO	Barium oxide	1215.4	1187.6	
Br	Bromine (atomic)	554.4	531.2	
BrH	Hydrogen bromide	584.2	557.7	
BrLi	Lithium bromide	819	792.5	
CaO	Calcium oxide	1190.6	1162.3	
Cl	Chlorine (atomic)	513.6	490.1	
ClH	Hydrogen chloride	556.9	530.1	
ClLi	Lithium chloride	827	800.5	
Co	Cobalt	742.7	719.8	
Cr	Chromium	791.3	768.4	
CsHO	Cesium hydroxide	1117.9	1092.2	
Cs_2O	Cesium oxide	1442.9	1412.2	
Cu	Copper	655.3	632.4	
F	Fluorine (atomic)	340.1	315.1	
FH	Hydrogen fluoride	484	456.7	
FO	Fluorine oxide	508.7	482.2	
F_2	Fluorine	332	305.5	
F_2O_2S	Sulfuryl fluoride	605.5	580.5	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
F_3N	Nitrogen trifluoride	568.4	538.6	
F_3OP	Phosphoryl fluoride	694.0	664.2	
F_3P	Phosphorus(III) fluoride	695.3	662.8	
F_4Si	Tetrafluorosilane	502.9	476.6	
F_6S	Sulfur hexafluoride	575.3	550.7	
Fe	Iron	754	731.1	
FeO	Iron(II) oxide	907	880.5	
GeH_4	Germane	713.4	687.1	
HI	Hydrogen iodide	627.5	601.3	
HKO	Potassium hydroxide	1101.8	1075.4	
HLi	Lithium hydride	1021.7	996.4	
HLiO	Lithium hydroxide	1000.1	972.1	
HNO_3	Nitric acid	751.4	731.5	
HN_3	Hydrazoic acid	756.0	723.5	
HNa	Sodium hydride	1095	1070.6	
HNaO	Sodium hydroxide	1071.8	1044.8	
HO	Hydroxyl	593.2	564.0	
HO_2	Hydroperoxy	660	627.5	
HP	Phosphorus monohydride	670.3	639.6	
H_2	Hydrogen	422.3	394.7	
$H_2N_2O_2$	Nitramide	757.4	725.0	
H_2O	Water	691	660.0	
H_2O_2	Hydrogen peroxide	674.5	643.8	
H_2O_4S	Sulfuric acid	717	681	Ref. 3
H_2P	Phosphino	709.2	675.7	
H_2S	Hydrogen sulfide	705	673.8	
H_2Se	Hydrogen selenide	707.8	676.4	
H_2Si	Silylene	839.2	804.1	
H_2Te	Hydrogen telluride	735.9	704.5	
H_3N	Ammonia	853.6	819.0	
H_3P	Phosphine	785	750.9	
H_4N_2	Hydrazine	853.2	822.4	
H_4Si	Silane	639.7	613.4	
H_6OSi_2	Disiloxane	749	718.3	
He	Helium	177.8	148.5	
I	Iodine (atomic)	608.2	583.5	
K_2O	Potassium oxide	1342.5	1311.8	
Kr	Krypton	424.6	402.4	
La	Lanthanum	1013	991.9	
Li_2	Dilithium	1162	1133.1	
Li_2O	Lithium oxide	1206	1175.3	
Lu	Lutetium	992	970.6	
Mg	Magnesium	819.6	797.3	
MgO	Magnesium oxide	988	959.4	
Mg_2	Dimagnesium	919	886.5	
Mn	Manganese	797.3	774.4	
N	Nitrogen (atomic)	342.2	318.7	
NO	Nitric oxide	531.8	505.3	
NO_2	Nitrogen dioxide	591.0	560.3	
NP	Phosphorus nitride	789.4	757.0	
N_2	Nitrogen	493.8	464.5	
N_2O	Nitrous oxide	549.8	523.3	Protonation at N
N_2O	Nitrous oxide	575.2	548.7	Protonation at O
Na_2	Disodium	1146.8	1118.2	
Na_2O	Sodium oxide	1375.9	1345.2	
Ne	Neon	198.8	174.4	
Ni	Nickel	737	714.1	
O	Oxygen (atomic)	485.2	459.6	
OP	Phosphorus monoxide	682	649.5	
OSi	Silicon monoxide	777.8	750.4	Protonation at O

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
OSi	Silicon monoxide	533	500.5	Protonation at Si
OSr	Strontium oxide	1209	1180.7	
O_2	Oxygen	421	396.3	
O_2S	Sulfur dioxide	672.3	643.3	
O_3	Ozone	625.5	595.9	
O_3S	Sulfur trioxide	588.3	560.3	
O_4Os	Osmium(VIII) oxide	676.9	650.6	
P	Phosphorus	626.8	604.8	
Pd	Palladium	696	673.4	
Rh	Rhodium	768	745.4	
Ru	Ruthenium	774	751.4	
S	Sulfur	664.3	640.2	
SSi	Silicon monosulfide	627	596.6	Protonation at Si
SSi	Silicon monosulfide	683	660.2	Protonation at S
Sc	Scandium	914	892.0	
Si	Silicon	837	814.1	
Ti	Titanium	876	853.7	
U	Uranium	995.2	973.2	
V	Vanadium	859.4	836.8	
Xe	Xenon	499.6	478.1	
Y	Yttrium	967	945.9	
Zn	Zinc	608.6	586.0	
$CBrF_3$	Bromotrifluoromethane	580.0	550.3	
CBrN	Cyanogen bromide	749.8	719.2	
$CClF_3$	Chlorotrifluoromethane	571.3	541.5	
CClN	Cyanogen chloride	722.1	691.5	
CCl_2	Dichloromethylene	861	828.5	
CCl_2S	Carbonothioic dichloride	752.5	721.8	
CFN	Cyanogen fluoride	632	601.3	
CF_2	Difluoromethylene	765	732.5	
CF_2O	Carbonyl fluoride	666.7	637.0	
CF_3I	Trifluoroiodomethane	628.0	598.2	
CF_3NO	Trifluoronitrosomethane	703.3	670.8	
CF_4	Tetrafluoromethane	529.3	503.7	
CHCl	Chloromethylene	874.1	839.9	
CHF	Fluoromethylene	797.9	763.8	
CHF_3	Trifluoromethane	619.5	589.7	
CHF_3O_3S	Trifluoromethanesulfonic acid	699.4	666.9	
CHN	Hydrogen cyanide	712.9	681.6	
CHN	Hydrogen isocyanide	772.3	739.8	
CHNO	Isocyanic acid (HNCO)	753	718.8	
CHNO	Fulminic acid	758	725.5	
CHO	Oxomethyl (HCO)	636	601.8	
CHO_2	Formyloxyl	623.4	590.9	
CH_2F_2	Difluoromethane	620.5	589.7	
CH_2N_2	Diazomethane	858.9	826.7	
CH_2N_2	Cyanamide	805.6	774.9	
CH_2O	Formaldehyde	712.9	683.3	
CH_2O_2	Formic acid	742.0	710.3	
CH_2S	Thioformaldehyde	759.7	730.5	
CH_2Se	Selenoformaldehyde	764.0	734.9	
CH_3Br	Bromomethane	664.2	638.0	
CH_3Cl	Chloromethane	647.3	621.1	
CH_3F	Fluoromethane	598.9	571.5	
CH_3I	Iodomethane	691.7	665.5	
CH_3NO	Formamide	822.2	791.2	
CH_3NO_2	Nitromethane	754.6	721.6	
CH_3NO_2	Methyl nitrite	798.9	766.4	
CH_3NO_3	Methyl nitrate	733.6	714.8	
CH_3N_3	Methyl azide	833	800.5	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
CH_4	Methane	543.5	520.6	
CH_4N	Methylamidogen	832.8	801.6	
CH_4N_2O	Urea	873.5	841.6	Protonation at O; Ref. 8
CH_4N_2S	Thiourea	893.7	863.9	
CH_4O	Methanol	754.3	724.5	
CH_4O_3S	Methanesulfonic acid	761.3	728.9	
CH_4S	Methanethiol	773.4	742	
CH_5N	Methylamine	899.0	864.5	
CH_5NO	*O*-Methylhydroxylamine	844.8	812.3	
CH_5N_3	Guanidine	986.3	949.4	
CH_5P	Methylphosphine	851.5	817.6	
CH_6N_2	Methylhydrazine	898.8	866.4	
CN	Cyanide	>595	>564	Protonation at N
CNS	Thiocyanate	751	718.5	
CO	Carbon monoxide	594	562.8	Protonation at C
CO	Carbon monoxide	426.3	402.2	Protonation at O
COS	Carbon oxysulfide	628.5	602.6	Protonation at S
COSe	Carbon oxyselenide	670	644.1	Protonation at Se
CO_2	Carbon dioxide	540.5	515.8	
CS	Carbon monosulfide	791.5	760	
CS_2	Carbon disulfide	681.9	657.7	
CSe	Carbon monoselenide	831.8	800.2	Protonation at C
CSe_2	Carbon diselenide	725	700.9	
C_2ClF_3O	Trifluoroacetyl chloride	681.6	649.8	
C_2Cl_3N	Trichloroacetonitrile	723.2	692.6	
C_2F_3N	Trifluoroacetonitrile	688.4	657.7	
C_2H	Ethynyl	753	720.8	
C_2HCl_3O	Trichloroacetaldehyde	722.3	690.5	
$C_2HCl_3O_2$	Trichloroacetic acid	770.0	739.1	
C_2HF	Fluoroacetylene	686	661.3	
C_2HF_3	Trifluoroethene	699.4	666.9	
$C_2HF_3O_2$	Trifluoroacetic acid	711.7	680.7	
C_2H_2	Acetylene	641.4	616.7	
C_2H_2ClN	Chloroacetonitrile	745.7	715.1	
$C_2H_2F_2$	1,1-Difluoroethene	734	705.1	
$C_2H_2F_2$	*trans*-1,2-Difluoroethene	688.6	657.9	
C_2H_2O	Ketene	825.3	793.6	
$C_2H_3ClO_2$	Chloroacetic acid	765.4	734.5	
$C_2H_3Cl_3O$	2,2,2-Trichloroethanol	729.3	698.9	
C_2H_3F	Fluoroethene	729	700.1	
$C_2H_3FO_2$	Fluoroacetic acid	765.4	734.5	
$C_2H_3F_3O$	2,2,2-Trifluoroethanol	700.2	669.9	
$C_2H_3F_3O$	Methyl trifluoromethyl ether	719.2	690.0	
C_2H_3N	Acetonitrile	779.2	748	
C_2H_3N	Isocyanomethane	839.1	806.6	
C_2H_3NO	Methyl isocyanate	764.4	732.0	
C_2H_3NS	Methyl thiocyanate	796.7	766.1	
C_2H_3NS	Methyl isothiocyanate	799.2	766.7	
$C_2H_3N_3$	1*H*-1,2,3-Triazole	879.3	847.4	
$C_2H_3N_3$	1*H*-1,2,4-Triazole	886.0	855.9	
C_2H_4	Ethylene	680.5	651.5	
$C_2H_4F_2O$	2,2-Difluoroethanol	727.4	697.0	
$C_2H_4F_3N$	2,2,2-Trifluoroethylamine	846.8	812.9	
$C_2H_4N_2$	Aminoacetonitrile	824.9	791.0	
C_2H_4O	Acetaldehyde	768.5	736.5	
C_2H_4O	Oxirane	774.2	745.3	
$C_2H_4O_2$	Acetic acid	783.7	752.8	
$C_2H_4O_2$	Methyl formate	782.5	751.5	
C_2H_4S	Thiirane	807.4	777.6	
C_2H_5Br	Bromoethane	696.2	669.7	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
C_2H_5BrO	2-Bromoethanol	766.1	735.7	
C_2H_5Cl	Chloroethane	693.4	666.9	
C_2H_5ClO	2-Chloroethanol	766.1	735.7	
C_2H_5F	Fluoroethane	683.4	655.8	
C_2H_5FO	2-Fluoroethanol	715.6	685.2	
C_2H_5I	Iodoethane	724.8	698.3	
C_2H_5N	Ethenamine	898.9	866.5	
C_2H_5N	Ethyleneimine	905.5	872.5	
C_2H_5NO	Acetamide	863.6	832.6	
C_2H_5NO	*N*-Methylformamide	851.3	820.3	
$C_2H_5NO_2$	Nitroethane	765.7	733.2	
$C_2H_5NO_2$	Ethyl nitrite	818.9	786.4	
$C_2H_5NO_2$	Glycine	886.5	852.2	
$C_2H_5NO_2$	Acetohydroxamic acid	854.0	823.0	
C_2H_5NS	Thioacetamide	884.6	852.8	
C_2H_6	Ethane	596.3	569.9	
C_2H_6Hg	Dimethyl mercury	771.6	740.8	
$C_2H_6N_2$	Ethanimidamide	970.7	938.2	
$C_2H_6N_2$	trans-Dimethyldiazene	865.1	834.4	
$C_2H_6N_2O$	2-Aminoacetamide		882.3	
$C_2H_6N_2O_2$	*N*-Methyl-*N*-nitromethanamine	828.3	795.8	
C_2H_6O	Ethanol	776.4	746	
C_2H_6O	Dimethyl ether	792	764.5	
C_2H_6OS	Dimethyl sulfoxide	884.4	853.7	
$C_2H_6O_2$	1,2-Ethanediol	815.9	773.6	
C_2H_6S	Ethanethiol	789.6	758.4	
C_2H_6S	Dimethyl sulfide	830.9	801.2	
$C_2H_6S_2$	Dimethyl disulfide	815.3	782.8	
C_2H_7N	Ethylamine	912.0	878	
C_2H_7N	Dimethylamine	929.5	896.5	
C_2H_7NO	Ethanolamine	930.3	896.8	
$C_2H_7O_3P$	Dimethyl hydrogen phosphite	894.8	862.4	
C_2H_7P	Dimethylphosphine	912.0	877.9	
$C_2H_8N_2$	1,2-Ethanediamine	951.6	912.5	
$C_2H_8N_2$	1,1-Dimethylhydrazine	927.1	894.7	
C_2N_2	Cyanogen	674.7	645.8	
C_2O	Dicarbon monoxide	774.7	747.0	
C_3	Carbon trimer	767.0	736.3	
C_3F_6O	Perfluoroacetone	670.4	639.7	
C_3HN	Cyanoacetylene	751.2	720.5	
$C_3H_2F_6O$	1,1,1,3,3,3-Hexafluoro-2-propanol	686.6	656.2	
$C_3H_2N_2$	Malononitrile	723.0	694.1	
C_3H_3	2-Propynyl	741	708.5	
$C_3H_3Cl_3O$	1,1,1-Trichloro-2-propanone	768.3	736.3	
$C_3H_3F_3O$	1,1,1-Trifluoroacetone	723.9	692.0	
$C_3H_3F_3O_2$	Methyl trifluoroacetate	740.5	709.6	
C_3H_3N	Acrylonitrile	784.7	753.7	
C_3H_3NO	Oxazole	876.4	844.5	
C_3H_3NO	Isoxazole	848.6	816.8	
C_3H_3NO	2-Oxopropanenitrile	746.9	716.2	
C_3H_3NS	Thiazole	904	872.1	
$C_3H_3N_3$	1,3,5-Triazine	848.8	819.6	
C_3H_4	Allene	775.3	745.8	
C_3H_4	Propyne	748.2	723.0	
C_3H_4	Cyclopropene	818.5	787.8	
C_3H_4ClN	3-Chloropropanenitrile	773.1	742.4	
$C_3H_4N_2$	1*H*-Pyrazole	894.1	860.5	
$C_3H_4N_2$	Imidazole	942.8	909.2	
$C_3H_4N_2S$	2-Thiazolamine	930.6	898.7	
C_3H_4O	Acrolein	797.0	765.1	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
C_3H_4O	1-Propen-1-one	834.1	803.4	
$C_3H_4O_3$	Ethylene carbonate	814.2	784.4	
C_3H_5	Allyl	736	707.4	
C_3H_5	Cyclopropyl	738.9	702.0	
$C_3H_5ClO_2$	Ethyl chloroformate	764.8	733.8	
C_3H_5FO	1-Fluoro-2-propanone	795.4	763.5	
$C_3H_5F_3O$	2,2,2-Trifluoroethyl methyl ether	747.6	718.4	
C_3H_5N	Propanenitrile	794.1	763.0	
C_3H_5N	2-Propyn-1-amine	887.4	853.5	
C_3H_5N	Ethyl isocyanide	851.3	818.9	
C_3H_5NO	Acrylamide	870.7	839.8	
C_3H_5NO	Methoxyacetonitrile	758.1	727.4	
C_3H_5NO	2-Azetidinone	852.6	821.7	
C_3H_5NS	(Methylthio)acetonitrile	784.8	754.1	
$C_3H_5N_3$	1*H*-Pyrazol-3-amine	921.5	889.6	
$C_3H_5N_3$	1*H*-Pyrazol-4-amine	907.6	874.0	
C_3H_6	Propene	741.6		Ref. 5
C_3H_6	Cyclopropane	750.3	722.2	
$C_3H_6N_2$	3-Aminopropanenitrile	866.4	832.5	
$C_3H_6N_2$	Dimethylcyanamide	852.1	821.4	
$C_3H_6N_2S$	2-Imidazolidinethione	921.9	891.2	
C_3H_6O	Methyl vinyl ether	859.2	830.3	
C_3H_6O	Propanal	786.0	754.0	
C_3H_6O	Acetone	812	782.1	
C_3H_6O	Oxetane	801.3	773.9	
$C_3H_6O_2$	Propanoic acid	797.2	766.2	
$C_3H_6O_2$	Ethyl formate	799.4	768.4	
$C_3H_6O_2$	Methyl acetate	821.6	790.7	
$C_3H_6O_3$	Dimethyl carbonate	830.2	799.2	
C_3H_6S	(Methylthio)ethene	858.2	829.3	
C_3H_6S	Thietane	834.8	805.0	
C_3H_6S	Methylthiirane	833.3	801.5	
C_3H_7N	Allylamine	909.5	875.5	
C_3H_7N	Cyclopropylamine	904.7	869.9	
C_3H_7N	Azetidine	943.4	908.6	
C_3H_7N	1-Methylaziridine	934.8	904.1	
C_3H_7N	Propyleneimine	925.1	892.1	
C_3H_7NO	*N,N*-Dimethylformamide	887.5	856.6	
C_3H_7NO	*N*-Methylacetamide	888.5	857.6	
C_3H_7NO	Propanamide	876.2	845.3	
$C_3H_7NO_2$	Isopropyl nitrite	845.5	813.0	
$C_3H_7NO_2$	*L*-Alanine	901.6	867.7	
$C_3H_7NO_2$	Sarcosine	921.2	888.7	
$C_3H_7NO_2S$	*L*-Cysteine	903.2	869.3	
$C_3H_7NO_3$	*L*-Serine	914.6	880.7	
C_3H_8	Propane	625.7	607.8	
$C_3H_8N_2O$	*N,N'*-Dimethylurea	903.3	873.5	
$C_3H_8N_2S$	*N,N'*-Dimethylthiourea	926.0	895.1	
C_3H_8O	1-Propanol	786.5	756.1	
C_3H_8O	2-Propanol	793.0	762.6	
C_3H_8O	Ethyl methyl ether	808.6	781.2	
$C_3H_8O_2$	1,3-Propanediol	876.2	825.9	
$C_3H_8O_2$	2-Methoxyethanol	768.8	729.8	
$C_3H_8O_3$	Glycerol	874.8	820	
C_3H_8S	1-Propanethiol	794.9	763.6	
C_3H_8S	2-Propanethiol	803.6	772.3	
C_3H_8S	Ethyl methyl sulfide	846.5	815.3	
C_3H_9As	Trimethylarsine	897.3	864.9	
$C_3H_9BO_3$	Trimethyl borate	815.8	783.4	
C_3H_9N	Propylamine	917.8	883.9	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
C_3H_9N	Isopropylamine	923.8	889.0	
C_3H_9N	Ethylmethylamine	942.2	909.2	
C_3H_9N	Trimethylamine	948.9	918.1	
C_3H_9NO	2-Methoxyethylamine	928.6	894.6	
C_3H_9NO	Trimethylamine oxide	983.2	953.5	
C_3H_9NO	3-Amino-1-propanol	962.5	917.3	
$C_3H_9O_3P$	Trimethyl phosphite	929.7	899.9	
$C_3H_9O_4P$	Trimethyl phosphate	890.6	860.8	
C_3H_9P	Trimethylphosphine	958.8	926.3	
$C_3H_{10}N_2$	1,3-Propanediamine	987.0	940.0	
$C_3H_{10}OSi$	Trimethylsilanol	814.0	781.5	
C_4F_8	Perfluorocyclobutane	>544		Ref. 6
C_4H_2	1,3-Butadiyne	737.2	712.8	
$C_4H_4F_6O$	Bis(2,2,2-trifluoroethyl) ether	702.3	674.9	
$C_4H_4N_2$	Pyrazine	877.1	847.0	
$C_4H_4N_2$	Pyrimidine	885.8	855.7	
$C_4H_4N_2$	Pyridazine	907.2	877.1	
$C_4H_4N_2O_2$	Uracil	872.7	841.7	
$C_4H_4N_2S_2$	2,4(1*H*,3*H*)-Pyrimidinedithione	911.4	880.5	
C_4H_4O	Furan	812	781	Ref. 10
$C_4H_4O_3$	Succinic anhydride	797		Ref. 9
C_4H_4S	Thiophene	815.0	784.3	
$C_4H_5Cl_3O_2$	Ethyl trichloroacetate	790.4	759.4	
$C_4H_5F_3O_2$	Ethyl trifluoroacetate	758.8	727.9	
C_4H_5N	Pyrrole	875.4	843.8	
C_4H_5N	Cyclopropanecarbonitrile	808.2	777.5	
$C_4H_5NO_2$	Ethyl cyanoformate	745.7	714.7	
C_4H_5NS	2-Methylthiazole	930.6	898.7	
$C_4H_5N_3O$	Cytosine	949.9	918	
C_4H_6	1,2-Butadiene	778.9	749.8	
C_4H_6	1,3-Butadiene	783.4	757.6	
C_4H_6	2-Butyne	775.8	745.1	
C_4H_6	Cyclobutene	784.4	753.6	
$C_4H_6F_3NO$	2,2,2-Trifluoro-*N,N*-dimethylacetamide	849.0	818.0	
$C_4H_6N_2$	1-Methylimidazol	959.6	927.7	
$C_4H_6N_2$	2-Methyl-1*H*-imidazole	963.4	929.6	
$C_4H_6N_2$	4-Methyl-1*H*-imidazole	952.8	920.9	
$C_4H_6N_2$	1-Methyl-1*H*-pyrazole	912.0	880.1	
$C_4H_6N_2$	3-Methyl-1*H*-pyrazole	906.0	874.2	
$C_4H_6N_2$	4-Methyl-1*H*-pyrazole	906.8	873.4	
C_4H_6O	2-Methylpropenal	808.7	776.8	
C_4H_6O	3-Buten-2-one	834.7	802.8	
C_4H_6O	Cyclobutanone	802.5	772.7	
C_4H_6O	2,3-Dihydrofuran	866.9	834.4	
C_4H_6O	2,5-Dihydrofuran	823.4	796	
$C_4H_6O_2$	*trans*-2-Butenoic acid	824.0	793	
$C_4H_6O_2$	Methacrylic acid	816.7	785.7	
$C_4H_6O_2$	Cyclopropanecarboxylic acid	821.4	790.4	
$C_4H_6O_2$	Vinyl acetate	813.9	782.9	
$C_4H_6O_2$	Methyl acrylate	825.8	794.8	
$C_4H_6O_2$	2,3-Butanedione	801.9	770.1	
$C_4H_6O_2$	γ-Butyrolactone	840.0	808.1	
$C_4H_6O_2$	2,3-Dihydro-1,4-dioxin	823.5	792.8	
$C_4H_6O_3$	Acetic anhydride	844		Ref. 9
C_4H_7	2-Methylallyl	778	747.3	
C_4H_7N	Butanenitrile	798.4	767.7	
C_4H_7N	2-Methylpropanenitrile	803.6	772.8	
C_4H_7N	1-Isocyanopropane	856.8	824.3	
C_4H_7NO	2-Butenamide	887.1	856.1	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
C_4H_7NO	2-Methyl-2-propenamide	880.4	849.4	
$C_4H_7NO_4$	*L*-Aspartic acid	908.9	875	
C_4H_8	*trans*-2-Butene	747	719.9	
C_4H_8	Isobutene	802.1	775.6	
$C_4H_8N_2$	(Dimethylamino)acetonitrile	884.5	853.7	
$C_4H_8N_2O_3$	*L*-Asparagine	929	891.5	
$C_4H_8N_2O_3$	*N*-Glycylglycine		882	
C_4H_8O	Ethyl vinyl ether	870.1	840.4	
C_4H_8O	2-Methoxy-1-propene	894.9	866.1	
C_4H_8O	Butanal	792.7	760.8	
C_4H_8O	Isobutanal	797.3	765.5	
C_4H_8O	2-Butanone	827.3	795.5	
C_4H_8O	Tetrahydrofuran	822.1	794.7	
$C_4H_8O_2$	Propyl formate	804.9	773.9	
$C_4H_8O_2$	Isopropyl formate	811.3	780.3	
$C_4H_8O_2$	Ethyl acetate	835.7	804.7	
$C_4H_8O_2$	Methyl propanoate	830.2	799.2	
$C_4H_8O_2$	1,3-Dioxane	825.4	796.2	
$C_4H_8O_2$	1,4-Dioxane	797.4	770.0	
$C_4H_8O_3$	Ethyl methyl carbonate	842.7	810.8	
C_4H_8S	Tetrahydrothiophene	849.1	819.3	
C_4H_9N	Pyrrolidine	948.3	915.3	
C_4H_9NO	*N*-Methylpropanamide	920.4	889.4	
C_4H_9NO	2-Methylpropanamide	878.6	846.7	
C_4H_9NO	*N*-Ethylacetamide	898.0	867.0	
C_4H_9NO	*N,N*-Dimethylacetamide	908.0	877.0	
C_4H_9NO	Morpholine	924.3	891.2	
$C_4H_9NO_2$	*tert*-Butyl nitrite	863.9	831.4	
$C_4H_9NO_2$	Ethyl *N*-methylcarbamate	888.8	857.8	
$C_4H_9NO_3$	*L*-Threonine	922.5	888.5	
C_4H_9NS	*N,N*-Dimethylthioacetamide	925.3	894.4	
C_4H_{10}	Isobutane	677.8	671.3	
$C_4H_{10}N_2$	Piperazine	943.7	914.7	
$C_4H_{10}N_2$	3-Ethyl-3-methyldiaziridine	903.8	871.3	
$C_4H_{10}O$	1-Butanol	789.2	758.9	
$C_4H_{10}O$	2-Butanol	815.7	784.6	
$C_4H_{10}O$	2-Methyl-1-propanol	793.7	762.2	
$C_4H_{10}O$	2-Methyl-2-propanol	802.6	772.2	
$C_4H_{10}O$	Diethyl ether	828.4	801	
$C_4H_{10}O$	Methyl propyl ether	814.9	785.7	
$C_4H_{10}O$	Isopropyl methyl ether	826.3	797.1	
$C_4H_{10}O_2$	1,4-Butanediol	915.6	854.9	
$C_4H_{10}O_2$	1,2-Dimethoxyethane	858.0	820.2	
$C_4H_{10}O_3$	1,2,4-Butanetriol	905.9	841	
$C_4H_{10}S$	1-Butanethiol	801.7	770.5	
$C_4H_{10}S$	2-Methyl-1-propanethiol	802.6	771.4	
$C_4H_{10}S$	2-Methyl-2-propanethiol	816.4	785.1	
$C_4H_{10}S$	Diethyl sulfide	856.7	827.0	
$C_4H_{11}N$	Butylamine	921.5	886.6	
$C_4H_{11}N$	*tert*-Butylamine	934.1	899.9	
$C_4H_{11}N$	Isobutylamine	924.8	890.8	
$C_4H_{11}N$	Diethylamine	952.4	919.4	
$C_4H_{11}N$	Isopropylmethylamine	952.4	919.4	
$C_4H_{11}N$	Ethyldimethylamine	960.1	929.1	
$C_4H_{11}NO$	*N*-Ethyl-*N*-hydroxyethanamine	914.7	882.2	
$C_4H_{11}NO$	4-Amino-1-butanol	984.5	932.1	
$C_4H_{11}NO_2$	Diethanolamine	953	920	
$C_4H_{12}N_2$	1,4-Butanediamine	1005.6	954.3	
$C_4H_{12}N_2$	*N,N'*-Dimethyl-1,2-ethanediamine	989.2	946.9	
$C_4H_{12}Sn$	Tetramethylstannane	823.7	797.4	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_4H_{14}OSi_2$	1,1,3,3-Tetramethyldisiloxane	845.3	814.6	
C_4NiO_4	Nickel carbonyl	742.3	716.0	
C_5F_5N	Perfluoropyridine	764.9	733.0	
C_5FeO_5	Iron pentacarbonyl	833.0	798.5	
$C_5H_3ClN_4$	6-Chloro-1*H*-purine	873.6	841.7	
C_5H_4BrN	2-Bromopyridine	904.8	873.0	
C_5H_4BrN	3-Bromopyridine	910.0	878.2	
C_5H_4BrN	4-Bromopyridine	917.8	886.0	
C_5H_4ClN	2-Chloropyridine	900.9	869	
C_5H_4ClN	3-Chloropyridine	903.4	871.5	
C_5H_4ClN	4-Chloropyridine	916.1	884.2	
C_5H_4FN	3-Fluoropyridine	902.0	870.1	
C_5H_4FN	2-Fluoropyridine	884.6	852.7	
$C_5H_4N_2O_2$	4-Nitropyridine	874.3	842.5	
$C_5H_4N_2O_3$	4-Nitropyridine 1-oxide	868.0	837.3	
$C_5H_4N_4$	1*H*-Purine	920.1	888.2	
$C_5H_4N_4O$	Hypoxanthine	912.3	880.5	
C_5H_5	Cyclopentadienyl	831.5	799.1	
C_5H_5N	Pyridine	930	898.1	
C_5H_5NO	3-Pyridinol	929.5	897.7	
C_5H_5NO	Pyridine-1-oxide	923.6	892.9	
$C_5H_5N_5$	Adenine	942.8	912.5	
$C_5H_5N_5O$	Guanine	959.5	927.6	
C_5H_6	1,3-Cyclopentadiene	821.6	798.4	
$C_5H_6N_2$	2-Pyridinamine	947.2	915.3	
$C_5H_6N_2$	3-Pyridinamine	954.4	922.6	
$C_5H_6N_2$	4-Pyridinamine	979.7	947.8	
$C_5H_6N_2O_2$	Thymine	880.9	850.0	
C_5H_6O	2-Methylfuran	865.9	833.5	
C_5H_6O	3-Methylfuran	854.0	821.5	
$C_5H_6O_3$	Glutaric anhydride	816		Ref. 9
$C_5H_6O_3$	3-Methylsuccinic anhydride	807		Ref. 9
C_5H_6S	2-Methylthiophene	859.0	826.5	
$C_5H_7F_3O_2$	Propyl trifluoroacetate	763.9	732.9	
C_5H_8	*trans*-1,3-Pentadiene	834.1	804.4	
C_5H_8	2-Methyl-1,3-butadiene	826.4	797.6	
C_5H_8	2-Pentyne	810.2	778.0	
C_5H_8	3-Methyl-1-butyne	814.9	787.8	
C_5H_8	Cyclopentene	766.3	733.8	
C_5H_8	1-Methylcyclobutene	841.5	807.3	
C_5H_8	Vinylcyclopropane	816.3	787.5	
C_5H_8	3,3-Dimethylcyclopropene	847.8	817.1	
$C_5H_8N_2$	1,3-Dimethyl-1*H*-pyrazole	933.9	902.3	
$C_5H_8N_2$	1,4-Dimethyl-1*H*-imidazole	976.7	944.9	
$C_5H_8N_2$	1,5-Dimethyl-1*H*-pyrazole	934.3	902.8	
$C_5H_8N_2$	3,4-Dimethyl-1*H*-pyrazole	927.3	895.4	
$C_5H_8N_2$	3,5-Dimethyl-1*H*-pyrazole	933.5	900.1	
$C_5H_8N_2$	1,2-Dimethyl-1*H*-imidazole	984.7	952.6	
$C_5H_8N_2$	1,5-Dimethyl-1*H*-imidazole	977.6	945.8	
C_5H_8O	*trans*-2-Pentenal	839.0	807.2	
C_5H_8O	3-Methyl-2-butenal	856.9	825.0	
C_5H_8O	3-Methyl-3-buten-2-one	843.1	811.3	
C_5H_8O	Cyclopropyl methyl ketone	854.9	823	
C_5H_8O	Cyclopentanone	823.7	794.0	
C_5H_8O	3,4-Dihydro-2H-pyran	865.8	833.4	
$C_5H_8O_2$	3-Methyl-2-butenoic acid	822.9	791.9	
$C_5H_8O_2$	*cis*-2-Methyl-2-butenoic acid	822.5	791.5	
$C_5H_8O_2$	Cyclobutanecarboxylic acid	817.4	786.4	
$C_5H_8O_2$	Methyl trans-2-butenoate	851.3	820.4	
$C_5H_8O_2$	Methyl methacrylate	831.4	800.5	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_5H_8O_2$	Methyl cyclopropanecarboxylate	842.1	811.2	
$C_5H_8O_2$	2,4-Pentanedione	873.5	836.8	
C_5H_9N	2-Isocyano-2-methylpropane	870.7	838.3	
C_5H_9N	3-(Dimethylamino)-1-propyne	940.3	909.5	
C_5H_9N	Pentanenitrile	802.4	771.7	
C_5H_9N	2,2-Dimethylpropanenitrile	810.9	780.2	
C_5H_9NO	3-Ethoxypropanenitrile	807.2	776.5	
C_5H_9NO	*N,N*-Dimethyl-2-propenamide	904.3	873.4	
C_5H_9NO	*N*-Methyl-2-pyrrolidone	923.5	891.6	
$C_5H_9NO_2$	*L*-Proline	920.5	886.0	
$C_5H_9NO_4$	*L*-Glutamic acid	913.0	879.1	
$C_5H_9N_3$	Histamine	999.8	961.9	
C_5H_{10}	2-Methyl-2-butene	808.8	779.9	
$C_5H_{10}N_2O$	1,3-Dimethyl-2-imidazolidinone	918.4	886.0	
$C_5H_{10}N_2O_3$	*L*-Glutamine	937.8	900	
$C_5H_{10}O$	Allyl ethyl ether	833.7	804.5	
$C_5H_{10}O$	Pentanal	796.6	764.8	
$C_5H_{10}O$	2-Pentanone	832.7	800.9	
$C_5H_{10}O$	3-Pentanone	836.8	807	
$C_5H_{10}O$	3-Methyl-2-butanone	836.3	804.4	
$C_5H_{10}O$	Tetrahydropyran	822.8	795.4	
$C_5H_{10}O$	2-Methyltetrahydrofuran	840.8	811.6	
$C_5H_{10}O_2$	Butyl formate	806.0	775	
$C_5H_{10}O_2$	Propyl acetate	836.6	805.6	
$C_5H_{10}O_2$	Isopropyl acetate	836.6	805.6	
$C_5H_{10}O_2$	Methyl butanoate	836.4	805.4	
$C_5H_{10}O_2$	Methyl isobutanoate	836.6	805.7	
$C_5H_{10}O_2$	*cis*-1,2-Cyclopentanediol	885.6	853.1	
$C_5H_{10}S$	Thiacyclohexane	855.8	826.0	
$C_5H_{11}N$	Allyldimethylamine	957.8	926.8	
$C_5H_{11}N$	Piperidine	954.0	921	
$C_5H_{11}N$	*N*-Methylpyrrolidine	965.6	934.8	
$C_5H_{11}NO$	2,2-Dimethylpropanamide	889.0	857.2	
$C_5H_{11}NO_2$	*L*-Valine	910.6	876.7	
$C_5H_{11}NO_2S$	*L*-Methionine	935.4	901.5	
$C_5H_{12}N_2O$	Tetramethylurea	930.6	899.6	
$C_5H_{12}N_2S$	Tetramethylthiourea	947.6	916.6	
$C_5H_{12}O$	2,2-Dimethyl-1-propanol	795.5	765.2	
$C_5H_{12}O$	Butyl methyl ether	820.3	791.2	
$C_5H_{12}O$	Methyl tert-butyl ether	841.6	812.4	
$C_5H_{12}O$	Ethyl isopropyl ether	842.7	813.5	
$C_5H_{12}S$	2,2-Dimethyl-1-propanethiol	809.5	778.2	
$C_5H_{12}Si$	Vinyltrimethylsilane	833	804.1	
$C_5H_{13}N$	Pentylamine	923.5	889.5	
$C_5H_{13}N$	2-Methyl-2-butanamine	937.8	903.6	
$C_5H_{13}N$	2,2-Dimethylpropylamine	928.3	894.0	
$C_5H_{13}N$	Ethylisopropylamine	960.0	926.7	
$C_5H_{13}N$	*N,N*-Dimethyl-1-propanamine	962.8	931.9	
$C_5H_{13}N$	Diethylmethylamine	971.0	940.0	
$C_5H_{13}N_3$	1,1,3,3-Tetramethylguanidine	1031.6	997.4	
$C_5H_{14}N_2$	*N,N,N′,N′*-Tetramethylmethanediamine	952.2	919.8	
$C_5H_{14}N_2$	*N,N*-Dimethyl-1,3-propanediamine	1025.0	975.3	
$C_5H_{14}N_2$	1,5-Pentanediamine	999.6	946.2	
C_6CrO_6	Chromium carbonyl	739.2	714.6	
C_6F_6	Hexafluorobenzene	648.0	624.4	
C_6HF_5	Pentafluorobenzene	690.4	662.7	
$C_6H_2F_4$	1,2,3,4-Tetrafluorobenzene	700.4	672.7	
$C_6H_2F_4$	1,2,3,5-Tetrafluorobenzene	747.3	719.6	
$C_6H_2F_4$	1,2,4,5-Tetrafluorobenzene	746.5	718.8	
$C_6H_3F_3$	1,2,3-Trifluorobenzene	724.3	696.6	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_6H_3F_3$	1,2,4-Trifluorobenzene	729.5	699.4	
$C_6H_3F_3$	1,3,5-Trifluorobenzene	741.9	715.4	
C_6H_4	Benzyne	841	808.5	
$C_6H_4F_2$	*o*-Difluorobenzene	731.2	703.5	
$C_6H_4F_2$	*m*-Difluorobenzene	749.7	722	
$C_6H_4F_2$	*p*-Difluorobenzene	718.7	692.8	
$C_6H_4N_2$	2-Pyridinecarbonitrile	872.9	841	
$C_6H_4N_2$	3-Pyridinecarbonitrile	877.0	845.1	
$C_6H_4N_2$	4-Pyridinecarbonitrile	880.6	848.8	
$C_6H_4O_2$	*p*-Benzoquinone	799.1	769.3	
C_6H_5	Phenyl	884	851.5	
C_6H_5Br	Bromobenzene	754.1	725.8	
C_6H_5Cl	Chlorobenzene	753.1	724.6	
C_6H_5F	Fluorobenzene	755.9	726.6	
C_6H_5NO	Nitrosobenzene	854.3	823.6	
C_6H_5NO	4-Pyridinecarboxaldehyde	904.6	872.8	
$C_6H_5NO_2$	Nitrobenzene	800.3	769.5	
$C_6H_5N_3$	Azidobenzene	820	787.5	
C_6H_5O	Phenoxy	873.2		Ref. 4
C_6H_6	Benzene	750.4	725.4	
C_6H_6BrN	3-Bromoaniline	873.2	841.4	
C_6H_6ClN	3-Chloroaniline	868.1	836.3	
C_6H_6ClN	4-Chloroaniline	873.8	842.0	
C_6H_6ClN	2-Chloro-4-methylpyridine	921.2	889.4	
C_6H_6ClN	2-Chloro-6-methylpyridine	908.0	876.2	
C_6H_6ClNO	2-Chloro-6-methoxypyridine	909.9	878.0	
C_6H_6FN	3-Fluoroaniline	867.3	835.5	
C_6H_6FN	4-Fluoroaniline	871.5	839.7	
C_6H_6IN	3-Iodoaniline	878.7	846.8	
C_6H_6N	Anilino	949.8	917.4	
$C_6H_6N_2O$	3-Pyridinecarboxamide	918.3	886.4	
$C_6H_6N_2O_2$	4-Nitroaniline	866.0	834.2	
$C_6H_6N_4$	6-Methyl-1*H*-purine	939.2	907.3	
C_6H_6O	Bis(2-propynyl) ether	783.9	756.5	
C_6H_6O	Phenol	817.3	786.3	
C_6H_7N	Bis(2-propynyl)amine	910.0	876.9	
C_6H_7N	Aniline	882.5	850.6	
C_6H_7N	2-Methylpyridine	949.1	917.3	
C_6H_7N	3-Methylpyridine	943.4	911.6	
C_6H_7N	4-Methylpyridine	947.2	915.3	
C_6H_7NO	1-Methyl-2(1*H*)-pyridinone	925.8	894.8	
C_6H_7NO	2-Aminophenol	898.8	866.9	
C_6H_7NO	3-Aminophenol	898.8	866.9	
C_6H_7NO	2-Methoxypyridine	934.7	902.8	
C_6H_7NO	3-Methoxypyridine	942.7	910.9	
C_6H_7NO	4-Methoxypyridine	961.7	929.8	
C_6H_7NO	3-Methylpyridine-1-oxide	935.2	902.8	
C_6H_8	1,3-Cyclohexadiene	837	804.5	
C_6H_8	1,4-Cyclohexadiene	837	808.0	
$C_6H_8N_2$	1,2-Benzenediamine	896.5	865.8	
$C_6H_8N_2$	1,3-Benzenediamine	929.9	899.2	
$C_6H_8N_2$	1,4-Benzenediamine	905.9	874.0	
$C_6H_8N_2O$	Bis(2-cyanoethyl) ether	813.8	786.4	
C_6H_8O	2,4-Dimethylfuran	894.7	862.3	
C_6H_8O	2,5-Dimethylfuran	865.9	835.2	
C_6H_8O	3,4-Dimethylfuran	869.0	838.3	
$C_6H_8O_2$	1,3-Cyclohexanedione	881.2	849.4	
$C_6H_8O_2$	1,4-Cyclohexanedione	812.5	782.7	
$C_6H_8O_2$	1,2-Cyclohexanedione	849.6	818.9	
$C_6H_8O_3$	4-Methylglutaric anhydride	820		Ref. 9

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_6H_9F_3O_2$	Butyl trifluoroacetate	764.8	733.8	
C_6H_9N	2,5-Dimethylpyrrole	918.7	887.1	
$C_6H_9N_3O_2$	*L*-Histidine	988	950.2	
C_6H_{10}	Methylenecyclopentane	832.4	803.5	
C_6H_{10}	(1-Methylvinyl)cyclopropane	871.6	842.7	
C_6H_{10}	2-Methyl-1,3-pentadiene	864.9	836	
C_6H_{10}	3-Methyl-1,3-pentadiene	852.3	823.4	
C_6H_{10}	2,3-Dimethyl-1,3-butadiene	835.0	807.8	
C_6H_{10}	1-Hexyne	799.8	774.8	
C_6H_{10}	2-Hexyne	806.1	781.1	
C_6H_{10}	Cyclohexene	784.5	752.0	
C_6H_{10}	1-Methylcyclopentene	816.5	787.1	
$C_6H_{10}N_2$	1,3,5-Trimethyl-1*H*-pyrazole	949.3	917.4	
$C_6H_{10}N_2$	3,4,5-Trimethyl-1*H*-pyrazole	949.3	916.0	
$C_6H_{10}O$	7-Oxabicyclo[2.2.1]heptane	844.2	816.8	
$C_6H_{10}O$	7-Oxabicyclo[4.1.0]heptane	848.1	815.6	
$C_6H_{10}O$	*trans*-3-Hexen-2-one	865.6	833.8	
$C_6H_{10}O$	Diallyl ether	827.4	800.0	
$C_6H_{10}O$	Cyclohexanone	841.0	811.2	
$C_6H_{10}O$	Mesityl oxide	878.7	846.9	
$C_6H_{10}O_2$	Cyclopentanecarboxylic acid	817.4	786.4	
$C_6H_{10}O_2$	2,5-Hexanedione	892.0	851.8	
$C_6H_{11}N$	*N*-Allyl-2-propen-1-amine	949.3	916.3	
$C_6H_{11}NO$	1-Methyl-2-piperidinone	924.4	892.6	
$C_6H_{11}N_3O_4$	*N*-(*N*-Glycylglycyl)glycine	966.8	916.8	
C_6H_{12}	1-Hexene	805.2	776.3	
C_6H_{12}	2-Methyl-2-pentene	812	783.1	
C_6H_{12}	2,3-Dimethyl-2-butene	813.9	785.9	
C_6H_{12}	Cyclohexane	686.9	666.9	
$C_6H_{12}N_2$	Triethylenediamine	963.4	934.6	
$C_6H_{12}N_2O_3$	*N*-*L*-Alanyl-*L*-alanine		905.6	
$C_6H_{12}O$	Oxepane	834.2	806.8	
$C_6H_{12}O$	3-Hexanone	843.2	811.3	
$C_6H_{12}O$	3,3-Dimethyl-2-butanone	840.1	808.2	
$C_6H_{12}O_2$	*cis*-1,3-Cyclohexanediol	882.2	849.7	
$C_6H_{12}O_2$	*trans*-1,3-Cyclohexanediol	828.6	797.9	
$C_6H_{12}O_2$	Methyl 2,2-dimethylpropanoate	845.2	814.2	
$C_6H_{12}O_2$	Diacetone alcohol	822.9	791.1	
$C_6H_{12}O_6$	α-*D*-Glucose		778.9	
$C_6H_{12}O_6$	β-*D*-Glucose		778.9	
$C_6H_{13}N$	*N*,*N*,2-Trimethylpropenylamine	967.0	934.5	
$C_6H_{13}N$	Cyclohexylamine	934.4	899.6	
$C_6H_{13}N$	1-Methylpiperidine	971.1	940.1	
$C_6H_{13}N$	Hexahydro-1*H*-azepine	956.7	923.5	
$C_6H_{13}NO$	*N*,*N*-Dimethylbutanamide	921.7	890.8	
$C_6H_{13}NO$	*N*,*N*-Diethylacetamide	925.4	894.4	
$C_6H_{13}NO_2$	*L*-Leucine	914.6	880.6	
$C_6H_{13}NO_2$	*L*-Isoleucine	917.4	883.5	
$C_6H_{14}N_2O_2$	*L*-Lysine	996	951.0	
$C_6H_{14}N_4O_2$	*L*-Arginine	1051.0	1006.6	
$C_6H_{14}O$	Dipropyl ether	837.9	810.5	
$C_6H_{14}O$	Diisopropyl ether	855.5	828.1	
$C_6H_{14}O$	*tert*-Butyl ethyl ether	856.0	826.9	
$C_6H_{14}O_3$	Diethylene glycol dimethyl ether	918.8	870.9	
$C_6H_{14}S$	Dipropyl sulfide	864.7	834.9	
$C_6H_{14}S$	Diisopropyl sulfide	876.4	846.6	
$C_6H_{15}N$	Butyldimethylamine	969.2	938.2	
$C_6H_{15}N$	Isobutyldimethylamine	968.7	937.8	
$C_6H_{15}N$	Hexylamine	927.5	893.5	
$C_6H_{15}N$	Dipropylamine	962.3	929.3	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_6H_{15}N$	Diisopropylamine	971.9	938.6	
$C_6H_{15}N$	Triethylamine	981.8	951	
$C_6H_{15}NO$	6-Amino-1-hexanol	969.0	915.7	
$C_6H_{15}OP$	Triethylphosphine oxide	936.6	906.8	
$C_6H_{15}O_4P$	Triethyl phosphate	909.3	879.6	
$C_6H_{15}P$	Triethylphosphine	984.5	952.0	
$C_6H_{16}N_2$	1,6-Hexanediamine	999.5	946.2	
$C_6H_{16}N_2$	*N,N,N′,N′*-Tetramethyl-1,2-ethanediamine	1012.8	970.6	
$C_6H_{16}OSi$	Triethylsilanol	822.1	794.8	
$C_6H_{18}N_3OP$	Hexamethylphosphoric triamide	958.6	928.7	
$C_6H_{18}N_3P$	Hexamethylphosphorous triamide	930.1	897.7	
$C_6H_{18}OSi_2$	Hexamethyldisiloxane	846.4	816.2	
C_6MoO_6	Molybdenum hexacarbonyl	762.6	738.1	
C_6O_6W	Tungsten carbonyl	758.0	733.4	
$C_7H_4N_2O_2$	3-Nitrobenzonitrile	781.4	750.7	
$C_7H_4N_2O_2$	4-Nitrobenzonitrile	775.7	745.1	
C_7H_5ClO	3-Chlorobenzaldehyde	813.0	781.1	
C_7H_5ClO	4-Chlorobenzaldehyde	831.3	799.4	
C_7H_5FO	3-Fluorobenzaldehyde	814.3	782.5	
C_7H_5FO	4-Fluorobenzaldehyde	827.1	795.3	
C_7H_5N	Benzonitrile	811.5	780.9	
C_7H_5N	Isocyanobenzene	868.4	836.0	
C_7H_5NO	Benzoxazole	891.6	859.8	
$C_7H_5NO_3$	4-Nitrobenzaldehyde	795.1	763.2	
C_7H_6ClNO	3-Chlorobenzamide	877.2	846.3	
C_7H_6ClNO	4-Chlorobenzamide	877.2	846.3	
C_7H_6F	*m*-Fluorobenzyl	836.5	804	
C_7H_6FNO	3-Fluorobenzamide	877.2	846.3	
C_7H_6FNO	4-Fluorobenzamide	877.2	846.3	
$C_7H_6F_3N$	3-(Trifluoromethyl)aniline	856.9	825.1	
$C_7H_6N_2$	1*H*-Benzimidazole	953.8	920.5	
$C_7H_6N_2$	1*H*-Indazole	900.8	868.9	
$C_7H_6N_2$	3-Aminobenzonitrile	842.3	810.4	
$C_7H_6N_2$	1*H*-Pyrrolo[2,3-b]pyridine	940.2	908.3	
$C_7H_6N_2O_3$	4-Nitrobenzamide	845.3	814.4	
$C_7H_6N_2O_3$	3-Nitrobenzamide	854.2	823.2	
C_7H_6O	Benzaldehyde	834.0	802.1	
C_7H_6O	2,4,6-Cycloheptatrien-1-one	920.8	891.0	
$C_7H_6O_2$	Benzoic acid	821.1	790.1	
C_7H_7	Benzyl	831.4	800.7	
C_7H_7Br	2-Bromotoluene	775.3	745.8	
C_7H_7Br	3-Bromotoluene	782.0	752.5	
C_7H_7Br	4-Bromotoluene	775.3	745.8	
C_7H_7Cl	2-Chlorotoluene	790.5	761.1	
C_7H_7Cl	3-Chlorotoluene	783.9	754.5	
C_7H_7Cl	4-Chlorotoluene	762.9	735.2	
C_7H_7F	2-Fluorotoluene	773.3	743.8	
C_7H_7F	3-Fluorotoluene	785.4	756.0	
C_7H_7F	4-Fluorotoluene	763.8	736.1	
C_7H_7I	1-Iodo-2-methylbenzene	780.3	750.8	
C_7H_7N	4-Vinylpyridine	944.1	912.3	
C_7H_7NO	1-(3-Pyridinyl)ethanone	916.2	884.3	
C_7H_7NO	1-(4-Pyridinyl)ethanone	914.7	882.9	
C_7H_7NO	4-Aminobenzaldehyde	910.4	878.6	
C_7H_7NO	Benzamide	892.1	861.2	
$C_7H_7NO_2$	Methyl 3-pyridinecarboxylate	925.6	893.8	
$C_7H_7NO_2$	Methyl 4-pyridinecarboxylate	926.6	894.7	
$C_7H_7NO_2$	Aniline-2-carboxylic acid	901.5	869.0	
$C_7H_7NO_2$	Aniline-3-carboxylic acid	864.7	832.3	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_7H_7NO_2$	Aniline-4-carboxylic acid	864.7	832.3	
$C_7H_7NO_2$	4-Nitrotoluene	815.2	782.7	
$C_7H_7NO_3$	4-Nitrobenzenemethanol	810.5	778.0	
$C_7H_7N_3$	1-Methyl-1*H*-benzotriazole	931.2	898.7	
C_7H_7O	2-Methylphenoxy	874.5	842	
C_7H_8	Toluene	784.0	756.3	
C_7H_8	2,5-Norbornadiene	849.3	820.3	
$C_7H_8N_2O$	4-Aminobenzamide	927.9	896.9	
$C_7H_8N_2O$	3-Aminobenzamide	900.9	869.9	
$C_7H_8N_2O_2$	*N*-Methyl-4-nitroaniline	891.6	865.1	
C_7H_8O	*o*-Cresol	832	800	Ref. 10
C_7H_8O	*m*-Cresol	841	809	Ref. 10
C_7H_8O	*p*-Cresol	814	782	Ref. 10
C_7H_8O	Benzyl alcohol	778.3	748.0	
C_7H_8O	Anisole	839.6	807.2	
$C_7H_8O_2$	2,6-Dimethyl-4*H*-pyran-4-one	941.5	907.3	
$C_7H_8O_2S$	Methyl phenyl sulfone	812.7	780.3	
C_7H_8S	(Methylthio)benzene	872.6	843.7	
C_7H_9N	Benzylamine	913.3	879.4	
C_7H_9N	2-Methylaniline	890.9	859.1	
C_7H_9N	3-Methylaniline	895.8	864.0	
C_7H_9N	4-Methylaniline	896.7	864.8	
C_7H_9N	*N*-Methylaniline	916.6	890.1	
C_7H_9N	2-Ethylpyridine	952.4	920.6	
C_7H_9N	3-Ethylpyridine	947.4	915.5	
C_7H_9N	4-Ethylpyridine	951.1	919.2	
C_7H_9N	2,3-Dimethylpyridine	958.9	927.0	
C_7H_9N	2,4-Dimethylpyridine	962.9	930.8	
C_7H_9N	2,5-Dimethylpyridine	958.8	926.9	
C_7H_9N	2,6-Dimethylpyridine	963.0	931.1	
C_7H_9N	3,4-Dimethylpyridine	957.3	925.5	
C_7H_9N	3,5-Dimethylpyridine	955.4	923.5	
C_7H_9NO	2-Methoxyaniline	905.2	873.3	
C_7H_9NO	3-Methoxyaniline	913.0	881.1	
C_7H_9NO	4-Methoxyaniline	900.3	868.5	
C_7H_{10}	Bicyclo[2.2.1]hept-2-ene	836.5	804.0	
$C_7H_{10}N_2$	*N,N*-Dimethyl-2-pyridinamine	968.2	941.6	
$C_7H_{10}N_2$	*N,N*-Dimethyl-4-pyridinamine	997.6	971.1	
$C_7H_{10}O$	Dicyclopropyl ketone	880.4	850.6	
$C_7H_{10}O$	Bicyclo[2.2.1]heptan-2-one	847.4	815.5	
$C_7H_{11}N$	Cyclohexanecarbonitrile	815.0	784.4	
C_7H_{12}	2,4-Dimethyl-1,3-pentadiene	886.5	857.6	
C_7H_{12}	1-Methylcyclohexene	825.1	792.6	
C_7H_{12}	1,2-Dimethylcyclopentene	822.6	791.9	
$C_7H_{12}N_2$	2,3,4,6,7,8-Hexahydropyrrolo[1,2-a]pyrimidine	1038.3	1005.9	
$C_7H_{12}O$	Cycloheptanone	845.6	815.9	
$C_7H_{12}O$	4-Methylcyclohexanone	844.9	813.0	
$C_7H_{12}O_2$	Cyclohexanecarboxylic acid	823.8	792.8	
$C_7H_{13}N$	1-Azabicyclo[2.2.2]octane	983.3	952.5	
C_7H_{14}	2,4-Dimethyl-2-pentene	812	783.1	
$C_7H_{14}O$	Methoxycyclohexane	840.5	811.3	
$C_7H_{14}O$	4-Heptanone	845.0	815.3	
$C_7H_{14}O$	2,4-Dimethyl-3-pentanone	850.3	820.5	
$C_7H_{14}O$	Cyclohexanemethanol	802.1	771.7	
$C_7H_{15}N$	Cyclohexanemethanamine	926.6	895.8	
$C_7H_{16}O$	*tert*-Butyl isopropyl ether	870.7	841.5	
$C_7H_{17}N$	Heptylamine	923.2	889.3	
$C_7H_{17}N$	Methyldipropylamine	983.5	950.9	
$C_7H_{17}N$	Diethylpropylamine	978.8	947.9	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_7H_{18}N_2$	1,7-Heptanediamine	998.5	944.9	
$C_7H_{18}N_2$	*N,N,N',N'*-Tetramethyl-1,3-propanediamine	1035.2	985.4	
$C_8H_4F_3N$	3-(Trifluoromethyl)benzonitrile	791.4	760.8	
$C_8H_4F_3N$	4-(Trifluoromethyl)benzonitrile	787.2	758.3	
$C_8H_4N_2$	*m*-Dicyanobenzene	779.3	750.4	
$C_8H_4N_2$	*p*-Dicyanobenzene	779.0	751.8	
C_8H_5Cl	1-Chloro-4-ethynylbenzene	832.4	801.7	
$C_8H_5Cl_3O$	2,2,2-Trichloro-1-phenylethanone	818.9	787.0	
$C_8H_5F_3O$	2,2,2-Trifluoro-1-phenylethanone	799.2	767.4	
$C_8H_5F_3O$	4-(Trifluoromethyl)benzaldehyde	805.6	773.8	
C_8H_5NO	4-Formylbenzonitrile	796.9	766.3	
C_8H_6	Phenylacetylene	832.0	801.3	
C_8H_6ClN	4-(Chloromethyl)benzonitrile	812.8	782.1	
C_8H_6ClN	3-(Chloromethyl)benzonitrile	811.2	780.6	
$C_8H_6N_2$	Quinoxaline	903.8	873.7	
$C_8H_6N_2$	Cinnoline	936.3	904.4	
C_8H_7Br	1-Bromo-4-vinylbenzene	838.7	809.8	
C_8H_7Br	1-Bromo-3-vinylbenzene	822.4	793.5	
C_8H_7ClO	1-(3-Chlorophenyl)ethanone	846.9	815.1	
C_8H_7ClO	1-(4-Chlorophenyl)ethanone	856.6	824.8	
$C_8H_7ClO_2$	Methyl 4-chlorobenzoate	842.1	811.1	
$C_8H_7ClO_2$	Methyl 3-chlorobenzoate	835.4	804.4	
C_8H_7FO	1-(4-Fluorophenyl)ethanone	858.6	826.8	
C_8H_7N	Benzeneacetonitrile	805.5	774.8	
C_8H_7N	1*H*-Indole	933.4	901.9	
$C_8H_7NO_3$	1-(4-Nitrophenyl)ethanone	824.3	792.5	
$C_8H_7NO_3$	1-(3-Nitrophenyl)ethanone	826.0	794.1	
$C_8H_7NO_4$	Methyl 3-nitrobenzoate	815.7	784.7	
$C_8H_7NO_4$	Methyl 4-nitrobenzoate	813.2	782.3	
C_8H_8	Styrene	839.5	809.2	
$C_8H_8N_2$	1-Methyl-1*H*-benzimidazole	967.0	935.2	
$C_8H_8N_2$	2-Methyl-2*H*-indazole	941.4	909.6	
$C_8H_8N_2$	1-Methyl-1*H*-indazole	922.4	890.5	
C_8H_8O	3-Methylbenzaldehyde	840.0	808.1	
C_8H_8O	4-Methylbenzaldehyde	851.8	820.0	
C_8H_8O	Acetophenone	861.1	829.3	
$C_8H_8O_2$	*o*-Toluic acid	838.8	807.8	
$C_8H_8O_2$	*m*-Toluic acid	829.8	798.8	
$C_8H_8O_2$	*p*-Toluic acid	836.7	805.7	
$C_8H_8O_2$	Methyl benzoate	850.5	819.5	
$C_8H_8O_2$	3-Methoxybenzaldehyde	844.1	812.2	
$C_8H_8O_2$	4-Methoxybenzaldehyde	881.1	849.3	
$C_8H_8O_2$	1-(3-Hydroxyphenyl)ethanone	863.6	831.8	
$C_8H_8O_2$	1-(4-Hydroxyphenyl)ethanone	883.7	851.9	
$C_8H_8O_3$	Methyl 4-hydroxybenzoate	863.4	832.5	
$C_8H_8O_3$	Methyl 3-hydroxybenzoate	850.0	819.1	
C_8H_9N	2,3-Dihydro-1*H*-indole	957.1	926.3	
C_8H_9NO	3-Methylbenzamide	900.9	869.9	
C_8H_9NO	4-Methylbenzamide	900.9	869.9	
C_8H_9NO	1-(4-Aminophenyl)ethanone	908.8	877.0	
$C_8H_9NO_2$	3-Methoxybenzamide	900.9	869.9	
$C_8H_9NO_2$	2,4-Dimethyl-1-nitrobenzene	831.0	798.5	
$C_8H_9NO_2$	Methyl 4-aminobenzoate	883.9	853.0	
$C_8H_9NO_2$	4-Methoxybenzamide	900.3	869.4	
C_8H_{10}	Ethylbenzene	788.0	760.3	
C_8H_{10}	*o*-Xylene	796.0	768.3	
C_8H_{10}	*m*-Xylene	812.1	786.2	
C_8H_{10}	*p*-Xylene	794.4	766.8	
$C_8H_{10}ClN$	4-Chloro-*N,N*-dimethylaniline	922.9	896.4	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_8H_{10}N_2O_2$	*N,N*-Dimethyl-4-nitroaniline	896.7	870.2	
$C_8H_{10}N_2O_2$	*N,N*-Dimethyl-3-nitroaniline	894.1	867.6	
$C_8H_{10}O$	Benzyl methyl ether	816.7	787.5	
$C_8H_{10}O$	2-Methylanisole	850	818	Ref. 10
$C_8H_{10}O$	3-Methylanisole	860	828	Ref. 10
$C_8H_{10}O$	4-Methylanisole	841	809	Ref. 10
$C_8H_{11}N$	4-Isopropylpyridine	955.7	923.8	
$C_8H_{11}N$	3-Ethylaniline	897.9	866.1	
$C_8H_{11}N$	*N*-Ethylaniline	924.8	892.9	
$C_8H_{11}N$	*N,N*-Dimethylaniline	941.1	909.2	
$C_8H_{11}N$	2,6-Dimethylaniline	901.7	869.8	
$C_8H_{11}N$	Benzeneethanamine	936.2	902.3	
$C_8H_{11}N$	2-Propylpyridine	955.7	923.8	
C_8H_{12}	2-Methyl-2-norbornene	845	812.5	
$C_8H_{12}N_2$	*N,N*-Dimethyl-1,4-benzenediamine	955.0	928.4	
$C_8H_{12}N_2O_2$	Ethyl 1,5-dimethyl-1*H*-pyrazole-3-carboxylate	933.4	901.5	
$C_8H_{14}O$	Cyclooctanone	849.4	819.6	
$C_8H_{14}O$	1-Cyclohexylethanone	841.4	809.5	
$C_8H_{14}O_2$	Methyl cyclohexanecarboxylate	846.2	815.3	
$C_8H_{16}O$	2,2,4-Trimethyl-3-pentanone	856.9	825.0	
$C_8H_{17}N$	Cyclohexyldimethylamine	983.6	952.6	
$C_8H_{18}O$	Dibutyl ether	845.7	818.3	
$C_8H_{18}O$	Di-*sec*-butyl ether	865.9	838.5	
$C_8H_{18}O$	Di-*tert*-butyl ether	887.4	860.0	
$C_8H_{18}O_4$	Triethylene glycol dimethyl ether	946.6	892.4	
$C_8H_{18}O_5$	Tetraethylene glycol		>910	
$C_8H_{18}S$	Dibutyl sulfide	871.8	842.1	
$C_8H_{18}S$	Di-*tert*-butyl sulfide	893.8	864.0	
$C_8H_{19}N$	*N*-Ethyl-*N*-isopropyl-2-propanamine	994.3	963.5	
$C_8H_{19}N$	Octylamine	928.9	895.0	
$C_8H_{19}N$	Dibutylamine	968.5	935.3	
$C_8H_{19}N$	Di-*sec*-butylamine	980.7	947.5	
$C_8H_{19}N$	Diisobutylamine	958.1	925.1	
$C_8H_{20}N_2$	*N,N,N',N'*-Tetramethyl-1,4-butanediamine	1046.3	992.7	
$C_8H_{20}N_2$	Tetraethylhydrazine	964.3	935.3	
$C_9H_7MnO_3$	Manganese 2-methylcyclopentadienyl tricarbonyl	833.8	801.3	
C_9H_7N	Quinoline	953.2	921.4	
C_9H_7N	Isoquinoline	951.7	919.9	
C_9H_7NO	4-Acetylbenzonitrile	826.8	795.0	
C_9H_8	Indene	848.8	819.6	
C_9H_8O	2-Methylbenzofuran	859.6	827.2	
$C_9H_8O_3$	Methyl 4-formylbenzoate	832.9	801.9	
C_9H_9Cl	1-Chloro-4-isopropenylbenzene	854.3	825.4	
$C_9H_9ClO_2$	3-Chloro-4-methoxyacetophenone	883.7	851.9	
C_9H_{10}	2-Methylstyrene	855.2	826.3	
C_9H_{10}	3-Methylstyrene	849.4	820.5	
C_9H_{10}	4-Methylstyrene	861.7	832.8	
C_9H_{10}	*cis*-1-Propenylbenzene	836.4	807.5	
C_9H_{10}	*trans*-1-Propenylbenzene	834.2	805.3	
C_9H_{10}	Isopropenylbenzene	864.2	835.3	
C_9H_{10}	Cyclopropylbenzene	834.9	802.4	
$C_9H_{10}N_2$	4-(Dimethylamino)benzonitrile	889.1	862.6	
$C_9H_{10}O$	1-(3-Methylphenyl)ethanone	868.2	836.4	
$C_9H_{10}O$	1-Phenyl-1-propanone	867.4	835.6	
$C_9H_{10}O$	1-Phenyl-2-propanone	842.6	810.8	
$C_9H_{10}O$	4-Methylacetophenone	875.5	843.6	
$C_9H_{10}OS$	4-Acetylthioanisole	888.2	856.3	
$C_9H_{10}O_2$	Methyl 2-methylbenzoate	858.3	827.3	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_9H_{10}O_2$	Methyl 3-methylbenzoate	857.7	826.8	
$C_9H_{10}O_2$	1-(3-Methoxyphenyl)ethanone	871.2	839.3	
$C_9H_{10}O_2$	Methyl 4-methylbenzoate	861.5	830.6	
$C_9H_{10}O_2$	4-Acetylanisole	895.6	863.7	
$C_9H_{10}O_3$	Methyl 4-methoxybenzoate	870.6	839.6	
$C_9H_{10}O_3$	Methyl 3-methoxybenzoate	856.7	825.8	
$C_9H_{11}N$	5,6,7,8-Tetrahydroquinoline	966.0	934.1	
$C_9H_{11}N$	5,6,7,8-Tetrahydroisoquinoline	966.6	934.7	
$C_9H_{11}NO$	4-(Dimethylamino)benzaldehyde	924.8	898.3	
$C_9H_{11}NO$	*N,N*-Dimethylbenzamide	932.7	901.8	
$C_9H_{11}NO_2$	1,3,5-Trimethyl-2-nitrobenzene	823.8	793.1	
$C_9H_{11}NO_2$	*L*-Phenylalanine	922.9	888.9	
$C_9H_{11}NO_3$	*L*-Tyrosine	926	892.1	
C_9H_{12}	Propylbenzene	790.1	762.4	
C_9H_{12}	Isopropylbenzene	791.6	763.9	
C_9H_{12}	1,3,5-Trimethylbenzene	836.2	808.6	
$C_9H_{12}N_2$	3-(2-Pyrrolidinyl)pyridine, (*S*)-	964.0	931.0	
$C_9H_{12}N_2O_6$	Uridine	947.6	916.6	
$C_9H_{12}O_3$	1,3,5-Trimethoxybenzene	926.7	898.2	
$C_9H_{13}N$	*N*-Ethyl-*N*-methylaniline	939.0	912.4	
$C_9H_{13}N$	2,6-Diethylpyridine	972.3	940.4	
$C_9H_{13}N$	4-*tert*-Butylpyridine	957.7	925.8	
$C_9H_{13}N$	2-*tert*-Butylpyridine	961.7	929.8	
$C_9H_{13}N$	2-Methyl-*N,N*-dimethylaniline	951.8	925.3	
$C_9H_{13}N$	3-Methyl-*N,N*-dimethylaniline	942.1	915.7	
$C_9H_{13}N$	4-Methyl-*N,N*-dimethylaniline	950.0	918.1	
$C_9H_{13}N$	*N,N*-Dimethylbenzylamine	968.4	937.4	
$C_9H_{13}NO$	4-Methoxy-*N,N*-dimethylaniline	949.1	922.4	
$C_9H_{13}N_3O_5$	Cytidine	982.5	950.0	
$C_9H_{14}O$	Isophorone	893.5	861.6	
$C_9H_{15}N$	*N,N*-Diallyl-2-propen-1-amine	972.3	941.3	
$C_9H_{15}N$	*N*-(1-Cyclopenten-1-yl)pyrrolidine	1019.2	988.4	
$C_9H_{16}O$	Cyclononanone	852.6	822.8	
$C_9H_{17}N_3O_4$	*N*-(*N*-*L*-Alanyl-*L*-alanyl)-*L*-alanine		924.1	
$C_9H_{18}O$	5-Nonanone	853.7	821.9	
$C_9H_{18}O$	Di-*tert*-butyl ketone	861.3	831.5	
$C_9H_{19}N$	1-Isobutylpiperidine	974.5	943.5	
$C_9H_{19}N$	2,2,6,6-Tetramethylpiperidine	987.0	953.9	
$C_9H_{21}N$	Tripropylamine	991.0	960.1	
$C_{10}H_8$	Naphthalene	802.9	779.4	
$C_{10}H_8$	Azulene	925.2	896	
$C_{10}H_8N_2$	2,2'-Bipyridine	965		Ref. 7
$C_{10}H_9N$	1-Naphthylamine	907.0	875.1	
$C_{10}H_{10}Fe$	Ferrocene	863.6	841.3	
$C_{10}H_{10}N_2$	1,8-Naphthalenediamine	944.5	912.1	
$C_{10}H_{10}N_2$	1-Methyl-3-phenyl-1*H*-pyrazole	932.6	900.8	
$C_{10}H_{10}N_2$	1-Methyl-5-phenyl-1*H*-pyrazole	932.4	900.5	
$C_{10}H_{10}Ni$	Nickelocene	935.7	907.3	
$C_{10}H_{10}O_2$	1,4-Diacetylbenzene	850.8	821.0	
$C_{10}H_{10}O_2$	1,3-Diacetylbenzene	852.0	822.3	
$C_{10}H_{10}O_3$	4-Acetylphenyl acetate	853.2	821.3	
$C_{10}H_{10}O_4$	Dimethyl isophthalate	843.5	814.3	
$C_{10}H_{10}O_4$	Dimethyl terephthalate	843.2	812.3	
$C_{10}H_{10}Ru$	Ruthenocene	899.1	876.8	
$C_{10}H_{12}$	1-Methyl-3-(1-methylvinyl)benzene	867.6	838.7	
$C_{10}H_{12}$	1-Methyl-4-(1-methylvinyl)benzene	881.8	852.9	
$C_{10}H_{12}$	1-Methyl-2-(1-methylvinyl)benzene	857.8	828.9	
$C_{10}H_{12}$	1,2,3,4-Tetrahydronaphthalene	809.7	782.1	
$C_{10}H_{12}O$	1-(2,4-Dimethylphenyl)ethanone	882.6	850.8	
$C_{10}H_{12}O$	1-(2,5-Dimethylphenyl)ethanone	873.5	841.6	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_{10}H_{12}O$	1-(3,4-Dimethylphenyl)ethanone	882.8	851.0	
$C_{10}H_{12}O_2$	Methyl 2,5-dimethylbenzoate	864.7	833.7	
$C_{10}H_{12}O_2$	Methyl 2,4-dimethylbenzoate	868.2	837.2	
$C_{10}H_{12}O_2$	Methyl 3,5-dimethylbenzoate	864.3	833.4	
$C_{10}H_{13}N$	1-Phenylpyrrolidine	941.6	915.1	
$C_{10}H_{13}NO$	4'-(Dimethylamino)acetophenone	932.8	906.3	
$C_{10}H_{13}NO$	*N,N*,3-Trimethylbenzamide	927.0	896.0	
$C_{10}H_{13}NO$	*N,N*,4-Trimethylbenzamide	927.0	896.0	
$C_{10}H_{13}NO$	1-[3-(Dimethylamino)phenyl]ethanone	928.0	901.5	
$C_{10}H_{13}N_5O_3$	2'-Deoxyadenosine	991.5	959.1	
$C_{10}H_{13}N_5O_4$	Adenosine	989.3	956.8	
$C_{10}H_{13}N_5O_5$	Guanosine	993.4	960.9	
$C_{10}H_{14}$	Butylbenzene	791.9	764.2	
$C_{10}H_{14}$	1,2,3,5-Tetramethylbenzene	845.6	816.5	
$C_{10}H_{14}ClN$	4-Chloro-*N,N*-diethylaniline	931.0	899.2	
$C_{10}H_{14}N_2$	*L*-Nicotine	963.4	932.6	
$C_{10}H_{14}N_2O$	*N,N*-Diethyl-3-pyridinecarboxamide	940.9	909.0	
$C_{10}H_{14}N_2O_5$	Thymidine	948.3	915.9	
$C_{10}H_{15}N$	*N,N*,2,6-Tetramethylaniline	954.1	923.2	
$C_{10}H_{15}N$	*N,N*,3,5-Tetramethylaniline	956.1	924.3	
$C_{10}H_{15}N$	*N,N*-Diethylaniline	959.8	927.9	
$C_{10}H_{16}N_2$	*N,N,N',N'*-Tetramethyl-1,2-benzenediamine	982.6	950.2	
$C_{10}H_{17}N$	Tricyclo[3.3.1.1^{3,7}]decan-1-amine	948.8	916.3	
$C_{10}H_{22}O$	Dipentyl ether	852.7	825.3	
$C_{10}H_{22}O_5$	Tetraethylene glycol dimethyl ether	953.8	897.8	
$C_{10}H_{23}N$	Decylamine	930.4	896.5	
$C_{10}H_{24}N_2$	*N,N,N',N'*-Tetramethyl-1,6-hexanediamine	1035.8	982.2	
$C_{11}H_9N$	4-Phenylpyridine	939.7	907.8	
$C_{11}H_{10}$	1-Methylnaphthalene	834.8	805.3	
$C_{11}H_{10}$	2-Methylnaphthalene	831.9	802.4	
$C_{11}H_{12}N_2O_2$	*L*-Tryptophan	948.9	915	
$C_{11}H_{14}O_2$	Methyl 2,4,6-trimethylbenzoate	866.3	835.3	
$C_{11}H_{15}N$	1-Phenylpiperidine	952.9	926.4	
$C_{11}H_{15}N$	Tricyclo[3.3.1.1^{3,7}]decane-1-carbonitrile	834.4	803.8	
$C_{11}H_{16}$	Pentamethylbenzene	850.7	823.5	
$C_{11}H_{17}N$	*N,N*-Diethyl-4-methylaniline	962.8	931.0	
$C_{11}H_{17}N$	2-Hexylpyridine	963.6	931.7	
$C_{11}H_{18}O$	1,4,7,7-Tetramethylbicyclo[2.2.1]heptan-2-one	863.3	831.4	
$C_{11}H_{24}O_4$	2,6,10,14-Tetraoxapentadecane		895.1	
$C_{12}H_8N_2$	Phenazine	938.4	908.3	
$C_{12}H_9NO$	Phenyl-3-pyridinylmethanone	934.1	902.3	
$C_{12}H_{10}$	Acenaphthene	851.7	821.0	
$C_{12}H_{10}$	Biphenyl	813.6	782.9	
$C_{12}H_{16}O$	1-(4-tert-Butylphenyl)ethanone	882.5	850.6	
$C_{12}H_{18}$	Hexamethylbenzene	860.6	836.0	
$C_{12}H_{18}O$	1-Tricyclo[3.3.1.1^{3,7}]dec-1-ylethanone	864.9	833.1	
$C_{12}H_{19}N$	*N,N*-Dipropylaniline	963.0	931.1	
$C_{12}H_{20}O$	2,5-Di-*tert*-butylfuran	894.7	863.9	
$C_{12}H_{27}N$	Tributylamine	998.5	967.6	
$C_{13}H_9N$	Acridine	972.6	940.7	
$C_{13}H_{10}$	9*H*-Fluorene	831.5	803.8	
$C_{13}H_{10}O$	Benzophenone	882.3	852.5	
$C_{13}H_{12}$	2-Methylbiphenyl	815.9	783.4	
$C_{13}H_{12}$	3-Methylbiphenyl	828.0	795.5	
$C_{13}H_{12}$	4-Methylbiphenyl	817.9	785.4	
$C_{13}H_{12}$	Diphenylmethane	802.0	769.5	
$C_{13}H_{13}P$	Methyldiphenylphosphine	972.1	939.7	

Molecular formula	Name	E_{pa} kJ/mol	$\Delta_{base}G°$ kJ/mol	Notes
$C_{13}H_{21}N$	2,6-Di-*tert*-butylpyridine	982.9	951	
$C_{13}H_{21}N$	2,4-Di-*tert*-butylpyridine	983.8	952.0	
$C_{13}H_{21}NO$	*N,N*-Dimethyltricyclo[3.3.1.1^{3,7}]decane-1-carboxamide	949.4	917.6	
$C_{14}H_{10}$	Anthracene	877.3	846.6	
$C_{14}H_{10}$	Phenanthrene	825.7	795.0	
$C_{14}H_{12}$	1,1-Diphenylethene	885.7	856.9	
$C_{14}H_{14}$	1,2-Diphenylethane	801.8	774.1	
$C_{14}H_{18}$	1,2,3,4,5,6,7,8-Octahydroanthracene	845.4	814.7	
$C_{14}H_{18}$	1,2,3,4,5,6,7,8-Octahydrophenanthrene	846.2	815.5	
$C_{14}H_{23}N$	4-Octylaniline	894.5	862	
$C_{15}H_{12}$	2-Methylanthracene	887.5	855.1	
$C_{15}H_{12}$	9-Methylanthracene	896.5	865.8	
$C_{15}H_{12}N_2$	3,5-Diphenyl-1*H*-pyrazole	946.3	912.7	
$C_{15}H_{16}$	1,3-Diphenylpropane	820.1	787.6	
$C_{15}H_{18}$	1,4-Dimethyl-7-isopropylazulene	983.1	950.6	
$C_{15}H_{24}$	1,3-Di-*tert*-butyl-5-methylbenzene	853.7	826.0	
$C_{16}H_{10}$	Fluoranthene	828.6	800.9	
$C_{16}H_{10}$	Pyrene	869.2	840.1	
$C_{16}H_{18}$	1,4-Diphenylbutane	822.0	779.8	
$C_{17}H_{20}$	1,5-Diphenylpentane	824.7	782.4	
$C_{18}H_{12}$	Chrysene	840.9	810.1	
$C_{18}H_{12}$	Naphthacene	905.5	876.5	
$C_{18}H_{12}$	Triphenylene	819.2	791.2	
$C_{18}H_{15}As$	Triphenylarsine	908.9	876.4	
$C_{18}H_{15}AsO$	Triphenylarsine oxide	906.2	876.4	
$C_{18}H_{15}N$	Triphenylamine	908.9	876.4	
$C_{18}H_{15}OP$	Triphenylphosphine oxide	906.2	876.4	
$C_{18}H_{15}P$	Triphenylphosphine	972.8	940.4	
$C_{18}H_{15}PS$	Triphenylphosphine sulfide	906.2	876.4	
$C_{18}H_{15}Sb$	Triphenylstibine	845.5	813.1	
$C_{18}H_{22}$	1,6-Diphenylhexane	826.1	783.8	
$C_{18}H_{30}$	1,3,5-Tri-*tert*-butylbenzene	848.8	822.3	
$C_{20}H_{12}$	Perylene	888.6	859.6	
$C_{22}H_{12}$	Benzo[ghi]perylene	876.0	845.2	
$C_{22}H_{14}$	Picene	851.3	820.6	
$C_{24}H_{12}$	Coronene	861.3	835.0	
C_{60}	Carbon (fullerene-C_{60})		827.5	
C_{70}	Carbon (fullerene-C_{70})		827.5	

SUMMARY TABLES OF PARTICLE PROPERTIES

Extracted from the Particle Listings of the
Review of Particle Physics
Published in Eur. Jour. Phys. **C3**, 1 (1998)
Available at http://pdg.lbl.gov

Particle Data Group Authors:

C. Caso, G. Conforto, A. Gurtu, M. Aguilar-Benitez, C. Amsler, R.M. Barnett, P.R. Burchat, C.D. Carone, O. Dahl, M. Doser, S. Eidelman, J.L. Feng, M. Goodman, C. Grab, D.E. Groom, K. Hagiwara, K.G. Hayes, J.J. Hernández, K. Hikasa, K. Honscheid, F. James, M.L. Mangano, A.V. Manohar, K. Mönig, H. Murayama, K. Nakamura, K.A. Olive, A. Piepke, M. Roos, R.H. Schindler, R.E. Shrock, M. Tanabashi, N.A. Törnqvist, T.G. Trippe, P. Vogel, C.G. Wohl, R.L. Workman, W.-M. Yao

Technical Associates: B. Armstrong, J.L. Casas Serradilla, B.B. Filimonov, P.S. Gee, S.B. Lugovsky, S. Mankov, F. Nicholson

Other Authors who have made substantial contributions to reviews since the 1994 edition:

K.S. Babu, D. Besson, O. Biebel, R.N. Cahn, R.L. Crawford, R.H. Dalitz, T. Damour, K. Desler, R.J. Donahue, D.A. Edwards, J. Erler, V.V. Ezhela, A. Fassò, W. Fetscher, D. Froidevaux, T.K. Gaisser, L. Garren, S. Geer, H.-J. Gerber, F.J. Gilman, H.E. Haber, C. Hagmann, I. Hinchliffe, C.J. Hogan, G. Höhler, J.D. Jackson, K.F. Johnson, D. Karlen, B. Kayser, K. Kleinknecht, I.G. Knowles, C. Kolda, P. Kreitz, P. Langacker, R. Landua, L. Littenberg, D.M. Manley, J. March-Russell, T. Nakada, H. Quinn, G. Raffelt, B. Renk, M.T. Ronan, L.J. Rosenberg, M. Schmitt, D.N. Schramm, D. Scott, T. Sjöstrand, G.F. Smoot, S. Spanier, M. Srednicki, T. Stanev, M. Suzuki, N.P. Tkachenko, G. Valencia, K. van Bibber, R. Voss, L. Wolfenstein, S. Youssef

©Regents of the University of California

(Approximate closing date for data: January 1, 1998)

GAUGE AND HIGGS BOSONS

γ

$I(J^{PC}) = 0\Gamma1(1^{--})$

Mass $m < 2 \times 10^{-16}$ eV
Charge $q < 5 \times 10^{-30}$ e
Mean life τ = Stable

g or gluon

$I(J^{P}) = 0(1^{-})$

Mass $m = 0$ [a]
SU(3) color octet

W

$J = 1$

Charge $= \pm 1$ e
Mass $m = 80.41 \pm 0.10$ GeV
$m_Z - m_W = 10.78 \pm 0.10$ GeV
$m_{W^+} - m_{W^-} = -0.2 \pm 0.6$ GeV
Full width $\Gamma = 2.06 \pm 0.06$ GeV

W^- modes are charge conjugates of the modes below.

W^+ DECAY MODES		Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$\ell^+\nu$	[b]	(10.74±0.33) %		–
$e^+\nu$		(10.9 ±0.4) %		40205
$\mu^+\nu$		(10.2 ±0.5) %		40205
$\tau^+\nu$		(11.3 ±0.8) %		40185
hadrons		(67.8 ±1.0) %		–
$\pi^+\gamma$		$< 2.2 \times 10^{-4}$	95%	40205

Z

$J = 1$

Charge $= 0$
Mass $m = 91.187 \pm 0.007$ GeV [c]
Full width $\Gamma = 2.490 \pm 0.007$ GeV
$\Gamma(\ell^+\ell^-) = 83.83 \pm 0.27$ MeV [b]
Γ(invisible) $= 498.3 \pm 4.2$ MeV [d]
Γ(hadrons) $= 1740.7 \pm 5.9$ MeV
$\Gamma(\mu^+\mu^-)/\Gamma(e^+e^-) = 1.000 \pm 0.005$
$\Gamma(\tau^+\tau^-)/\Gamma(e^+e^-) = 0.998 \pm 0.005$ [e]

Average charged multiplicity

$\langle N_{charged} \rangle = 21.00 \pm 0.13$

Couplings to leptons

$g^\ell_V = -0.0377 \pm 0.0007$
$g^\ell_A = -0.5008 \pm 0.0008$
$g^{\nu_e} = 0.53 \pm 0.09$
$g^{\nu_\mu} = 0.502 \pm 0.017$

Asymmetry parameters [f]

$A_e = 0.1519 \pm 0.0034$
$A_\mu = 0.102 \pm 0.034$
$A_\tau = 0.143 \pm 0.008$
$A_c = 0.59 \pm 0.19$
$A_b = 0.89 \pm 0.11$

Charge asymmetry (%) at Z pole

$A_{FB}^{(0\ell)} = 1.59 \pm 0.18$
$A_{FB}^{(0u)} = 4.0 \pm 7.3$
$A_{FB}^{(0s)} = 9.9 \pm 3.1 \quad (S = 1.2)$
$A_{FB}^{(0c)} = 7.32 \pm 0.58$
$A_{FB}^{(0b)} = 10.02 \pm 0.28$

Z DECAY MODES		Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
e^+e^-		(3.366±0.008) %		45594
$\mu^+\mu^-$		(3.367±0.013) %		45593
$\tau^+\tau^-$		(3.360±0.015) %		45559
$\ell^+\ell^-$	[b]	(3.366±0.006) %		–
invisible		(20.01 ±0.16) %		–
hadrons		(69.90 ±0.15) %		–
$(u\bar{u}+c\bar{c})/2$		(10.1 ±1.1) %		–
$(d\bar{d}+s\bar{s}+b\bar{b})/3$		(16.6 ±0.6) %		–
$c\bar{c}$		(12.4 ±0.6) %		–
$b\bar{b}$		(15.16 ±0.09) %		–
ggg		< 1.1 %	95%	–
$\pi^0\gamma$		$< 5.2 \times 10^{-5}$	95%	45593
$\eta\gamma$		$< 5.1 \times 10^{-5}$	95%	45592
$\omega\gamma$		$< 6.5 \times 10^{-4}$	95%	45590
$\eta'(958)\gamma$		$< 4.2 \times 10^{-5}$	95%	45588
$\gamma\gamma$		$< 5.2 \times 10^{-5}$	95%	45594
$\gamma\gamma\gamma$		$< 1.0 \times 10^{-5}$	95%	45594
$\pi^\pm W^\mp$	[g]	$< 7 \times 10^{-5}$	95%	10139
$\rho^\pm W^\mp$	[g]	$< 8.3 \times 10^{-5}$	95%	10114
$J/\psi(1S)X$		(3.66 ±0.23) $\times 10^{-3}$		–
$\psi(2S)X$		(1.60 ±0.29) $\times 10^{-3}$		–
$\chi_{c1}(1P)X$		(2.9 ±0.7) $\times 10^{-3}$		–
$\chi_{c2}(1P)X$		$< 3.2 \times 10^{-3}$	90%	–
$\Upsilon(1S)X + \Upsilon(2S)X + \Upsilon(3S)X$		(1.0 ±0.5) $\times 10^{-4}$		–
$\Upsilon(1S)X$		$< 5.5 \times 10^{-5}$	95%	–
$\Upsilon(2S)X$		$< 1.39 \times 10^{-4}$	95%	–
$\Upsilon(3S)X$		$< 9.4 \times 10^{-5}$	95%	–
$(D^0/\bar{D}^0)X$		(20.7 ±2.0) %		–
$D^\pm X$		(12.2 ±1.7) %		–
$D^*(2010)^\pm X$	[g]	(11.4 ±1.3) %		–
$B_s^0 X$		seen		–
anomalous γ+ hadrons	[h]	$< 3.2 \times 10^{-3}$	95%	–
$e^+e^-\gamma$	[h]	$< 5.2 \times 10^{-4}$	95%	45594
$\mu^+\mu^-\gamma$	[h]	$< 5.6 \times 10^{-4}$	95%	45593
$\tau^+\tau^-\gamma$	[h]	$< 7.3 \times 10^{-4}$	95%	45559
$\ell^+\ell^-\gamma\gamma$	[i]	$< 6.8 \times 10^{-6}$	95%	–
$q\bar{q}\gamma\gamma$	[i]	$< 5.5 \times 10^{-6}$	95%	–

$\nu\overline{\nu}\gamma\gamma$		[i] <	3.1	$\times 10^{-6}$	95%	45594
$e^{\pm}\mu^{\mp}$	LF	[g] <	1.7	$\times 10^{-6}$	95%	45593
$e^{\pm}\tau^{\mp}$	LF	[g] <	9.8	$\times 10^{-6}$	95%	45576
$\mu^{\pm}\tau^{\mp}$	LF	[g] <	1.2	$\times 10^{-5}$	95%	45576

Higgs Bosons — H^0 and $H^{\pm}$, Searches for

H^0 Mass $m >$ 77.5 GeV CL = 95%

H_1^0 in Supersymmetric Models ($m_{H_1^0} < m_{H_2^0}$)

Mass $m >$ 62.5 GeV CL = 95%

A^0 Pseudoscalar Higgs Boson in Supersymmetric Models [i]

Mass $m >$ 62.5 GeV CL = 95% $\tan\beta > 1$

$H^{\pm}$ Mass $m >$ 54.5 GeV CL = 95%

See the Particle Listings for a Note giving details of Higgs Bosons.

Heavy Bosons Other Than Higgs Bosons, Searches for

Additional W Bosons

W_R — right-handed W

Mass $m >$ 549 GeV

(assuming light right-handed neutrino)

W' with standard couplings decaying to $e\nu$ $\mu\nu$

Mass $m >$ 720 GeV CL = 95%

Additional Z Bosons

Z'_{SM} with standard couplings

Mass $m >$ 690 GeV CL = 95% ($p\overline{p}$ direct search)

Mass $m >$ 779 GeV CL = 95% (electroweak fit)

Z_{LR} of $SU(2)_L \times SU(2)_R \times U(1)$

(with $g_L = g_R$)

Mass $m >$ 630 GeV CL = 95% ($p\overline{p}$ direct search)

Mass $m >$ 389 GeV CL = 95% (electroweak fit)

Z_χ of $SO(10) \rightarrow SU(5) \times U(1)_\chi$

(coupling constant derived from G.U.T.)

Mass $m >$ 595 GeV CL = 95% ($p\overline{p}$ direct search)

Mass $m >$ 321 GeV CL = 95% (electroweak fit)

Z_ψ of $E_6 \rightarrow SO(10) \times U(1)_\psi$

(coupling constant derived from G.U.T.)

Mass $m >$ 590 GeV CL = 95% ($p\overline{p}$ direct search)

Mass $m >$ 160 GeV CL = 95% (electroweak fit)

Z_η of $E_6 \rightarrow SU(3) \times SU(2) \times U(1) \times U(1)_\eta$

(coupling constant derived from G.U.T.);

charges are $Q_\eta = \sqrt{3/8}Q_\chi - \sqrt{5/8}Q_\psi$)

Mass $m >$ 620 GeV CL = 95% ($p\overline{p}$ direct search)

Mass $m >$ 182 GeV CL = 95% (electroweak fit)

Scalar Leptoquarks

Mass $m >$ 225 GeV CL = 95% (1st generation pair prod.)

Mass $m >$ 237 GeV CL = 95% (1st gener. single prod.)

Mass $m >$ 119 GeV CL = 95% (2nd gener. pair prod.)

Mass $m >$ 73 GeV CL = 95% (2nd gener. single prod.)

Mass $m >$ 99 GeV CL = 95% (3rd gener. pair prod.)

(See the Particle Listings for assumptions on leptoquark quantum numbers and branching fractions.)

Axions (A^0) and Other Very Light Bosons, Searches for

The standard Peccei-Quinn axion is ruled out. Variants with reduced couplings or much smaller masses are constrained by various data. The Particle Listings in the full *Review* contain a Note discussing axion searches.

The best limit for the half-life of neutrinoless double beta decay with Majoron emission is $> 7.2 \times 10^{24}$ years (CL = 90%).

NOTES

In this Summary Table:

When a quantity has "(S = ...)" to its right the error on the quantity has been enlarged by the "scale factor" S defined as $S = \sqrt{\chi^2/(N-1)}$ where N is the number of measurements used in calculating the quantity. We do this when $S > 1$ which often indicates that the measurements are inconsistent. When $S > 1.25$ we also show in the Particle Listings an ideogram of the measurements. For more about S see the Introduction.

A decay momentum p is given for each decay mode. For a 2-body decay p is the momentum of each decay product in the rest frame of the decaying particle. For a 3-or-more-body decay p is the largest momentum any of the products can have in this frame.

[a] Theoretical value. A mass as large as a few MeV may not be precluded.

[b] ℓ indicates each type of lepton (e, μ, and τ), not sum over them.

[c] The Z-boson mass listed here corresponds to a Breit-Wigner resonance parameter. It lies approximately 34 MeV above the real part of the position of the pole (in the energy-squared plane) in the Z-boson propagator.

[d] This partial width takes into account Z decays into $\nu\overline{\nu}$ and any other possible undetected modes.

[e] This ratio has not been corrected for the τ mass.

[f] Here $A \equiv 2g_V g_A/(g_V^2+g_A^2)$.

[g] The value is for the sum of the charge states of particle/antiparticle states indicated.

[h] See the Z Particle Listings for the γ energy range used in this measurement.

[i] For $m_{\gamma\gamma} = (60 \pm 5)$ GeV.

[j] The limits assume no invisible decays.

LEPTONS

e

$J = \frac{1}{2}$

Mass $m = 0.51099907 \pm 0.00000015$ MeV [a]
$= (5.485799111 \pm 0.000000012) \times 10^{-4}$ u
$(m_{e^+} - m_{e^-})/m < 4 \times 10^{-8}$, CL = 90%
$|q_{e^+} + q_{e^-}|/e < 4 \times 10^{-8}$
Magnetic moment $\mu = 1.001159652193 \pm 0.000000000010\ \mu_B$
$(g_{e^+} - g_{e^-}) / g_{\rm average} = (-0.5 \pm 2.1) \times 10^{-12}$
Electric dipole moment $d = (0.18 \pm 0.16) \times 10^{-26}$ $e$cm
Mean life $\tau > 4.3 \times 10^{23}$ yr, CL = 68% [b]

μ

$J = \frac{1}{2}$

Mass $m = 105.658389 \pm 0.000034$ MeV [c]
$= 0.113428913 \pm 0.000000017$ u
Mean life $\tau = (2.19703 \pm 0.00004) \times 10^{-6}$ s
$\tau_{\mu^+}/\tau_{\mu^-} = 1.00002 \pm 0.00008$
$c\tau = 658.654$ m
Magnetic moment $\mu = 1.0011659230 \pm 0.0000000084\ e\hbar/2m_\mu$
$(g_{\mu^+} - g_{\mu^-}) / g_{\rm average} = (-2.6 \pm 1.6) \times 10^{-8}$
Electric dipole moment $d = (3.7 \pm 3.4) \times 10^{-19}$ $e$cm

Decay parameters [d]

$\rho = 0.7518 \pm 0.0026$
$\eta = -0.007 \pm 0.013$
$\delta = 0.749 \pm 0.004$
$\xi P_\mu = 1.003 \pm 0.008$ [e]
$\xi P_\mu \delta/\rho > 0.99682$, CL = 90% [e]
$\xi' = 1.00 \pm 0.04$
$\xi'' = 0.7 \pm 0.4$
$\alpha/A = (0 \pm 4) \times 10^{-3}$
$\alpha'/A = (0 \pm 4) \times 10^{-3}$
$\beta/A = (4 \pm 6) \times 10^{-3}$
$\beta'/A = (2 \pm 6) \times 10^{-3}$
$\overline{\eta} = 0.02 \pm 0.08$

μ^+ modes are charge conjugates of the modes below.

μ^- DECAY MODES		Fraction (Γ_j/Γ)	Confidence level	p (MeV/c)
$e^-\overline{\nu}_e\nu_\mu$		$\approx 100\%$		53
$e^-\overline{\nu}_e\nu_\mu\gamma$	[f]	(1.4±0.4) %		53
$e^-\overline{\nu}_e\nu_\mu e^+e^-$	[g]	$(3.4\pm0.4)\times10^{-5}$		53
Lepton Family number (LF) violating modes				
$e^-\nu_e\overline{\nu}_\mu$	LF	[h] < 1.2 %	90%	53
$e^-\gamma$	LF	$< 4.9 \times 10^{-11}$	90%	53
$e^-e^+e^-$	LF	$< 1.0 \times 10^{-12}$	90%	53
$e^-2\gamma$	LF	$< 7.2 \times 10^{-11}$	90%	53

τ

$J = \frac{1}{2}$

Mass $m = 1777.05^{+0.29}_{-0.26}$ MeV
Mean life $\tau = (290.0 \pm 1.2) \times 10^{-15}$ s
$c\tau = 86.93$ μm
Magnetic moment anomaly > -0.052 and < 0.058, CL = 95%
Electric dipole moment $d > -3.1$ and $< 3.1 \times 10^{-16}$ $e$cm, CL = 95%

Weak dipole moment

$\mathrm{Re}(d_\tau^W) < 0.56 \times 10^{-17}$ $e$cm, CL = 95%
$\mathrm{Im}(d_\tau^W) < 1.5 \times 10^{-17}$ $e$cm, CL = 95%

Weak anomalous magnetic dipole moment

$\mathrm{Re}(\alpha_\tau^W) < 4.5 \times 10^{-3}$, CL = 90%
$\mathrm{Im}(\alpha_\tau^W) < 9.9 \times 10^{-3}$, CL = 90%

Decay parameters

See the τ Particle Listings for a note concerning τ-decay parameters.

$\rho^\tau(e \text{ or } \mu) = 0.748 \pm 0.010$
$\rho^\tau(e) = 0.745 \pm 0.012$
$\rho^\tau(\mu) = 0.741 \pm 0.030$
$\xi^\tau(e \text{ or } \mu) = 1.01 \pm 0.04$
$\xi^\tau(e) = 0.98 \pm 0.05$
$\xi^\tau(\mu) = 1.07 \pm 0.08$
$\eta^\tau(e \text{ or } \mu) = 0.01 \pm 0.07$
$\eta^\tau(\mu) = -0.10 \pm 0.18$
$(\delta\xi)^\tau(e \text{ or } \mu) = 0.749 \pm 0.026$
$(\delta\xi)^\tau(e) = 0.733 \pm 0.033$
$(\delta\xi)^\tau(\mu) = 0.78 \pm 0.05$
$\xi^\tau(\pi) = 0.99 \pm 0.05$
$\xi^\tau(\rho) = 0.996 \pm 0.010$
$\xi^\tau(a_1) = 1.02 \pm 0.04$
$\xi^\tau(\text{all hadronic modes}) = 0.997 \pm 0.009$

τ^+ modes are charge conjugates of the modes below. "$h^\pm$" stands for $\pi^\pm$ or $K^\pm$. "ℓ" stands for e or μ. "Neutral" means neutral hadron whose decay products include γ's and/or π^0's.

τ^- DECAY MODES		Fraction (Γ_j/Γ)	Scale factor/ Confidence level	p (MeV/c)
Modes with one charged particle				
particle$^- \geq 0$ neutrals $\geq 0K^0_L\nu_\tau$ ("1-prong")		(84.71± 0.13) %	S=1.2	–
particle$^- \geq 0$ neutrals $\geq 0K^0\nu_\tau$		(85.30± 0.13) %	S=1.2	–
$\mu^-\overline{\nu}_\mu\nu_\tau$	[f]	(17.37± 0.09) %		885
$\mu^-\overline{\nu}_\mu\nu_\tau\gamma$	[g]	$(3.0 \pm 0.6) \times 10^{-3}$		–
$e^-\overline{\nu}_e\nu_\tau$	[f]	(17.81± 0.07) %		889
$h^- \geq 0$ neutrals $\geq 0K^0_L\nu_\tau$		(49.52± 0.16) %	S=1.2	–
$h^- \geq 0K^0_L\nu_\tau$		(12.32± 0.12) %	S=1.5	–
$h^-\nu_\tau$		(11.79± 0.12) %	S=1.5	–
$\pi^-\nu_\tau$	[f]	(11.08± 0.13) %	S=1.4	883
$K^-\nu_\tau$	[f]	$(7.1 \pm 0.5) \times 10^{-3}$		820
$h^- \geq 1$ neutralν_τ		(36.91± 0.17) %	S=1.2	–
$h^-\pi^0\nu_\tau$		(25.84± 0.14) %	S=1.1	–
$\pi^-\pi^0\nu_\tau$	[f]	(25.32± 0.15) %	S=1.1	878
$\pi^-\pi^0$non-$\rho(770)\nu_\tau$		$(3.0 \pm 3.2) \times 10^{-3}$		878
$K^-\pi^0\nu_\tau$	[f]	$(5.2 \pm 0.5) \times 10^{-3}$		814
$h^- \geq 2\pi^0\nu_\tau$		(10.79± 0.16) %	S=1.2	–
$h^-2\pi^0\nu_\tau$		(9.39± 0.14) %	S=1.2	–
$h^-2\pi^0\nu_\tau$(ex.K^0)		(9.23± 0.14) %	S=1.2	–
$\pi^-2\pi^0\nu_\tau$(ex.K^0)	[f]	(9.15± 0.15) %	S=1.2	862
$K^-2\pi^0\nu_\tau$(ex.K^0)	[f]	$(8.0 \pm 2.7) \times 10^{-4}$		796
$h^- \geq 3\pi^0\nu_\tau$		(1.40± 0.11) %	S=1.1	–
$h^-3\pi^0\nu_\tau$		(1.23± 0.10) %	S=1.1	–
$\pi^-3\pi^0\nu_\tau$(ex.K^0)	[f]	(1.11± 0.14) %		836
$K^-3\pi^0\nu_\tau$(ex.K^0)	[f]	$(4.3\ ^{+1.0}_{-2.9}) \times 10^{-4}$		766
$h^-4\pi^0\nu_\tau$(ex.K^0)		$(1.7 \pm 0.6) \times 10^{-3}$		–
$h^-4\pi^0\nu_\tau$(ex.K^0,η)	[f]	$(1.1 \pm 0.6) \times 10^{-3}$		–
$K^- \geq 0\pi^0 \geq 0K^0\nu_\tau$		(1.66± 0.10) %		–
$K^- \geq 1$ (π^0 or K^0) ν_τ		$(9.5 \pm 1.0) \times 10^{-3}$		–
Modes with K^0's				
K^0(particles)$^-\nu_\tau$		(1.66± 0.09) %	S=1.4	–
$h^-\overline{K}^0 \geq 0$ neutrals $\geq 0K^0_L\nu_\tau$		(1.62± 0.09) %	S=1.4	–
$h^-\overline{K}^0\nu_\tau$		$(9.9 \pm 0.8) \times 10^{-3}$	S=1.5	–
$\pi^-\overline{K}^0\nu_\tau$	[f]	$(8.3 \pm 0.8) \times 10^{-3}$	S=1.4	812
$\pi^-\overline{K}^0$ (non-$K^*(892)^-$)ν_τ		$< 1.7 \times 10^{-3}$	CL=95%	812
$K^-K^0\nu_\tau$	[f]	$(1.59\pm 0.24) \times 10^{-3}$		737
$h^-\overline{K}^0\pi^0\nu_\tau$		$(5.5 \pm 0.5) \times 10^{-3}$		–
$\pi^-\overline{K}^0\pi^0\nu_\tau$	[f]	$(3.9 \pm 0.5) \times 10^{-3}$		794
$\overline{K}^0\rho^-\nu_\tau$		$(1.9 \pm 0.7) \times 10^{-3}$		–
$K^-K^0\pi^0\nu_\tau$	[f]	$(1.51\pm 0.29) \times 10^{-3}$		685
$\pi^-\overline{K}^0\pi^0\pi^0\nu_\tau$		$(6 \pm 4) \times 10^{-4}$		–
$K^-K^0\pi^0\pi^0\nu_\tau$		$< 3.9 \times 10^{-4}$	CL=95%	–
$\pi^-K^0\overline{K}^0\nu_\tau$	[f]	$(1.21\pm 0.21) \times 10^{-3}$	S=1.2	682

$\pi^- K^0_S K^0_S \nu_\tau$		$(3.0 \pm 0.5) \times 10^{-4}$		S=1.2	–
$\pi^- K^0_S K^0_L \nu_\tau$		$(6.0 \pm 1.0) \times 10^{-4}$		S=1.2	–
$\pi^- K^0_S K^0_S \pi^0 \nu_\tau$		$< 2.0 \times 10^{-4}$		CL=95%	–
$\pi^- K^0_S K^0_L \pi^0 \nu_\tau$		$(3.1 \pm 1.2) \times 10^{-4}$			–
$K^- K^0 \geq 0$ neutrals ν_τ		$(3.1 \pm 0.4) \times 10^{-3}$			–
$K^0 h^+ h^- h^- \geq 0$ neutrals ν_τ		$< 1.7 \times 10^{-3}$		CL=95%	–
$K^0 h^+ h^- h^- \nu_\tau$		$(2.3 \pm 2.0) \times 10^{-4}$			–
Modes with three charged particles					
$h^- h^- h^+ \geq 0$neut. ν_τ ("3-prong")		$(15.18 \pm 0.13)\,\%$		S=1.2	–
$h^- h^- h^+ \geq 0$ neutrals ν_τ (ex. $K^0_S \to \pi^+\pi^-$)		$(14.60 \pm 0.13)\,\%$		S=1.2	–
$\pi^- \pi^+ \pi^- \geq 0$ neutrals ν_τ		$(14.60 \pm 0.14)\,\%$			–
$h^- h^- h^+ \nu_\tau$		$(9.96 \pm 0.10)\,\%$		S=1.1	–
$h^- h^- h^+ \nu_\tau$ (ex. K^0)		$(9.62 \pm 0.10)\,\%$		S=1.1	–
$h^- h^- h^+ \nu_\tau$ (ex. K^0, ω)		$(9.57 \pm 0.10)\,\%$		S=1.1	–
$\pi^- \pi^+ \pi^- \nu_\tau$		$(9.56 \pm 0.11)\,\%$		S=1.1	–
$\pi^- \pi^+ \pi^- \nu_\tau$ (ex. K^0)		$(9.52 \pm 0.11)\,\%$		S=1.1	–
$\pi^- \pi^+ \pi^- \nu_\tau$ (ex. K^0, ω)	[*l*]	$(9.23 \pm 0.11)\,\%$		S=1.1	–
$h^- h^- h^+ \geq 1$ neutrals ν_τ		$(5.18 \pm 0.11)\,\%$		S=1.2	–
$h^- h^- h^+ \geq 1$ neutrals ν_τ (ex. $K^0_S \to \pi^+\pi^-$)		$(4.98 \pm 0.11)\,\%$		S=1.2	–
$h^- h^- h^+ \pi^0 \nu_\tau$		$(4.50 \pm 0.09)\,\%$		S=1.1	–
$h^- h^- h^+ \pi^0 \nu_\tau$ (ex. K^0)		$(4.31 \pm 0.09)\,\%$		S=1.1	–
$h^- h^- h^+ \pi^0 \nu_\tau$ (ex. K^0, ω)		$(2.59 \pm 0.09)\,\%$			–
$\pi^- \pi^+ \pi^- \pi^0 \nu_\tau$		$(4.35 \pm 0.10)\,\%$			–
$\pi^- \pi^+ \pi^- \pi^0 \nu_\tau$ (ex. K^0)		$(4.22 \pm 0.10)\,\%$			–
$\pi^- \pi^+ \pi^- \pi^0 \nu_\tau$ (ex. K^0, ω)	[*l*]	$(2.49 \pm 0.10)\,\%$			–
$h^- (\rho\pi)^0 \nu_\tau$		$(2.88 \pm 0.35)\,\%$			–
$(a_1(1260) h)^- \nu_\tau$		$< 2.0 \%$		CL=95%	–
$h^- \rho\pi^0 \nu_\tau$		$(1.35 \pm 0.20)\,\%$			–
$h^- \rho^+ h^- \nu_\tau$		$(4.5 \pm 2.2) \times 10^{-3}$			–
$h^- \rho^- h^+ \nu_\tau$		$(1.17 \pm 0.23)\,\%$			–
$h^- h^- h^+ 2\pi^0 \nu_\tau$		$(5.4 \pm 0.4) \times 10^{-3}$			–
$h^- h^- h^+ 2\pi^0 \nu_\tau$ (ex. K^0)		$(5.3 \pm 0.4) \times 10^{-3}$			–
$h^- h^- h^+ 2\pi^0 \nu_\tau$ (ex. K^0, ω, η)	[*l*]	$(1.1 \pm 0.4) \times 10^{-3}$			–
$h^- h^- h^+ \geq 3\pi^0 \nu_\tau$	[*l*]	$(1.4 \pm {}^{0.9}_{0.7}) \times 10^{-3}$		S=1.5	–
$h^- h^- h^+ 3\pi^0 \nu_\tau$		$(2.9 \pm 0.8) \times 10^{-4}$			–
$K^- h^+ h^- \geq 0$ neutrals ν_τ		$(5.4 \pm 0.7) \times 10^{-3}$		S=1.1	–
$K^- \pi^+ \pi^- \geq 0$ neutrals ν_τ		$(3.1 \pm 0.6) \times 10^{-3}$		S=1.1	–
$K^- \pi^+ \pi^- \nu_\tau$		$(2.3 \pm 0.4) \times 10^{-3}$			–
$K^- \pi^+ \pi^- \nu_\tau$ (ex. K^0)	[*l*]	$(1.8 \pm 0.5) \times 10^{-3}$			–
$K^- \pi^+ \pi^- \pi^0 \nu_\tau$		$(8 \pm 4) \times 10^{-4}$			–
$K^- \pi^+ \pi^- \pi^0 \nu_\tau$ (ex. K^0)	[*l*]	$(2.4 \pm {}^{4.3}_{1.6}) \times 10^{-4}$			–
$K^- \pi^+ K^- \geq 0$ neut. ν_τ		$< 9 \times 10^{-4}$		CL=95%	–
$K^- K^+ \pi^- \geq 0$ neut. ν_τ		$(2.3 \pm 0.4) \times 10^{-3}$			–
$K^- K^+ \pi^- \nu_\tau$	[*l*]	$(1.61 \pm 0.26) \times 10^{-3}$			685
$K^- K^+ \pi^- \pi^0 \nu_\tau$	[*l*]	$(6.9 \pm 3.0) \times 10^{-4}$			–
$K^- K^+ K^- \geq 0$ neut. ν_τ		$< 2.1 \times 10^{-3}$		CL=95%	–
$K^- K^+ K^- \nu_\tau$		$< 1.9 \times 10^{-4}$		CL=90%	–
$\pi^- K^+ \pi^- \geq 0$ neut. ν_τ		$< 2.5 \times 10^{-3}$		CL=95%	–
$e^- e^- e^+ \bar{\nu}_e \nu_\tau$		$(2.8 \pm 1.5) \times 10^{-5}$			889
$\mu^- e^- e^+ \bar{\nu}_\mu \nu_\tau$		$< 3.6 \times 10^{-5}$		CL=90%	885
Modes with five charged particles					
$3h^- 2h^+ \geq 0$ neutrals ν_τ (ex. $K^0_S \to \pi^-\pi^+$) ("5-prong")		$(9.7 \pm 0.7) \times 10^{-4}$			–
$3h^- 2h^+ \nu_\tau$ (ex. K^0)	[*l*]	$(7.5 \pm 0.7) \times 10^{-4}$			–
$3h^- 2h^+ \pi^0 \nu_\tau$ (ex. K^0)	[*l*]	$(2.2 \pm 0.5) \times 10^{-4}$			–
$3h^- 2h^+ 2\pi^0 \nu_\tau$		$< 1.1 \times 10^{-4}$		CL=90%	–
Miscellaneous other allowed modes					
$(5\pi)^- \nu_\tau$		$(7.4 \pm 0.7) \times 10^{-3}$			–
$4h^- 3h^+ \geq 0$ neutrals ν_τ ("7-prong")		$< 2.4 \times 10^{-6}$		CL=90%	–
$K^*(892)^- \geq 0 (h^0 \neq K^0_S) \nu_\tau$		$(1.94 \pm 0.31)\,\%$			–
$K^*(892)^- \geq 0$ neutrals ν_τ		$(1.33 \pm 0.13)\,\%$			–
$K^*(892)^- \nu_\tau$		$(1.28 \pm 0.08)\,\%$			665
$K^*(892)^0 K^- \geq 0$ neutrals ν_τ		$(3.2 \pm 1.4) \times 10^{-3}$			–
$K^*(892)^0 K^- \nu_\tau$		$(2.1 \pm 0.4) \times 10^{-3}$			539
$\overline{K}^*(892)^0 \pi^- \geq 0$ neutrals ν_τ		$(3.8 \pm 1.7) \times 10^{-3}$			–
$\overline{K}^*(892)^0 \pi^- \nu_\tau$		$(2.2 \pm 0.5) \times 10^{-3}$			653
$(\overline{K}^*(892)\pi)^- \nu_\tau \to \pi^- \overline{K}^0 \pi^0 \nu_\tau$		$(1.1 \pm 0.5) \times 10^{-3}$			–
$K_1(1270)^- \nu_\tau$		$(4 \pm 4) \times 10^{-3}$			433
$K_1(1400)^- \nu_\tau$		$(8 \pm 4) \times 10^{-3}$			335
$K^*_2(1430)^- \nu_\tau$		$< 3 \times 10^{-3}$		CL=95%	317
$\eta\pi^- \nu_\tau$		$< 1.4 \times 10^{-4}$		CL=95%	798
$\eta\pi^- \pi^0 \nu_\tau$	[*l*]	$(1.74 \pm 0.24) \times 10^{-3}$			778
$\eta\pi^- \pi^0 \pi^0 \nu_\tau$		$(1.4 \pm 0.7) \times 10^{-4}$			746
$\eta K^- \nu_\tau$		$(2.7 \pm 0.6) \times 10^{-4}$			720
$\eta\pi^+\pi^-\pi^- \geq 0$ neutrals ν_τ		$< 3 \times 10^{-3}$		CL=90%	–
$\eta\pi^-\pi^+\pi^- \nu_\tau$		$(3.4 \pm 0.8) \times 10^{-4}$			–
$\eta a_1(1260)^- \nu_\tau \to \eta\pi^-\rho^0 \nu_\tau$		$< 3.9 \times 10^{-4}$		CL=90%	–
$\eta\eta\pi^- \nu_\tau$		$< 1.1 \times 10^{-4}$		CL=95%	637
$\eta\eta\pi^- \pi^0 \nu_\tau$		$< 2.0 \times 10^{-4}$		CL=95%	559
$\eta'(958)\pi^- \nu_\tau$		$< 7.4 \times 10^{-5}$		CL=90%	–
$\eta'(958)\pi^- \pi^0 \nu_\tau$		$< 8.0 \times 10^{-5}$		CL=90%	–
$\phi\pi^- \nu_\tau$		$< 2.0 \times 10^{-4}$		CL=90%	585
$\phi K^- \nu_\tau$		$< 6.7 \times 10^{-5}$		CL=90%	–
$f_1(1285)\pi^- \nu_\tau$		$(5.8 \pm 2.3) \times 10^{-4}$			–
$f_1(1285)\pi^- \nu_\tau \to \eta\pi^-\pi^+\pi^- \nu_\tau$		$(1.9 \pm 0.7) \times 10^{-4}$			–
$h^- \omega \geq 0$ neutrals ν_τ		$(2.36 \pm 0.08)\,\%$			–
$h^- \omega \nu_\tau$	[*l*]	$(1.93 \pm 0.06)\,\%$			–
$h^- \omega \pi^0 \nu_\tau$	[*l*]	$(4.3 \pm 0.5) \times 10^{-3}$			–
$h^- \omega 2\pi^0 \nu_\tau$		$(1.9 \pm 0.8) \times 10^{-4}$			–
Lepton Family number (*LF*), Lepton number (*L*), or Baryon number (*B*) violating modes (In the modes below, ℓ means a sum over e and μ modes)					
L means lepton number violation (*e.g.* $\tau^- \to e^+\pi^-\pi^-$). Following common usage *LF* means lepton family violation *and not* lepton number violation (*e.g.* $\tau^- \to e^-\pi^+\pi^-$). *B* means baryon number violation.					
$e^- \gamma$	*LF*	$< 2.7 \times 10^{-6}$		CL=90%	888
$\mu^- \gamma$	*LF*	$< 3.0 \times 10^{-6}$		CL=90%	885
$e^- \pi^0$	*LF*	$< 3.7 \times 10^{-6}$		CL=90%	883
$\mu^- \pi^0$	*LF*	$< 4.0 \times 10^{-6}$		CL=90%	880
$e^- K^0$	*LF*	$< 1.3 \times 10^{-3}$		CL=90%	819
$\mu^- K^0$	*LF*	$< 1.0 \times 10^{-3}$		CL=90%	815
$e^- \eta$	*LF*	$< 8.2 \times 10^{-6}$		CL=90%	804
$\mu^- \eta$	*LF*	$< 9.6 \times 10^{-6}$		CL=90%	800
$e^- \rho^0$	*LF*	$< 2.0 \times 10^{-6}$		CL=90%	722
$\mu^- \rho^0$	*LF*	$< 6.3 \times 10^{-6}$		CL=90%	718
$e^- K^*(892)^0$	*LF*	$< 5.1 \times 10^{-6}$		CL=90%	663
$\mu^- K^*(892)^0$	*LF*	$< 7.5 \times 10^{-6}$		CL=90%	657
$e^- \overline{K}^*(892)^0$	*LF*	$< 7.4 \times 10^{-6}$		CL=90%	663
$\mu^- \overline{K}^*(892)^0$	*LF*	$< 7.5 \times 10^{-6}$		CL=90%	657
$e^- \phi$	*LF*	$< 6.9 \times 10^{-6}$		CL=90%	596
$\mu^- \phi$	*LF*	$< 7.0 \times 10^{-6}$		CL=90%	590
$\pi^- \gamma$	*L*	$< 2.8 \times 10^{-4}$		CL=90%	883
$\pi^- \pi^0$	*L*	$< 3.7 \times 10^{-4}$		CL=90%	878
$e^- e^+ e^-$	*LF*	$< 2.9 \times 10^{-6}$		CL=90%	888
$e^- \mu^+ \mu^-$	*LF*	$< 1.8 \times 10^{-6}$		CL=90%	882
$e^+ \mu^- \mu^-$	*LF*	$< 1.5 \times 10^{-6}$		CL=90%	882
$\mu^- e^+ e^-$	*LF*	$< 1.7 \times 10^{-6}$		CL=90%	885
$\mu^+ e^- e^-$	*LF*	$< 1.5 \times 10^{-6}$		CL=90%	885
$\mu^- \mu^+ \mu^-$	*LF*	$< 1.9 \times 10^{-6}$		CL=90%	873
$e^- \pi^+ \pi^-$	*LF*	$< 2.2 \times 10^{-6}$		CL=90%	877
$e^+ \pi^- \pi^-$	*L*	$< 1.9 \times 10^{-6}$		CL=90%	877
$\mu^- \pi^+ \pi^-$	*LF*	$< 8.2 \times 10^{-6}$		CL=90%	866
$\mu^+ \pi^- \pi^-$	*L*	$< 3.4 \times 10^{-6}$		CL=90%	866
$e^- \pi^+ K^-$	*LF*	$< 6.4 \times 10^{-6}$		CL=90%	814
$e^- \pi^- K^+$	*LF*	$< 3.8 \times 10^{-6}$		CL=90%	814
$e^+ \pi^- K^-$	*L*	$< 2.1 \times 10^{-6}$		CL=90%	814
$e^- K^+ K^-$	*LF*	$< 6.0 \times 10^{-6}$		CL=90%	739
$e^+ K^- K^-$	*L*	$< 3.8 \times 10^{-6}$		CL=90%	739
$\mu^- \pi^+ K^-$	*LF*	$< 7.5 \times 10^{-6}$		CL=90%	800
$\mu^- \pi^- K^+$	*LF*	$< 7.4 \times 10^{-6}$		CL=90%	800
$\mu^+ \pi^- K^-$	*L*	$< 7.0 \times 10^{-6}$		CL=90%	800
$\mu^- K^+ K^-$	*LF*	$< 1.5 \times 10^{-5}$		CL=90%	699
$\mu^+ K^- K^-$	*L*	$< 6.0 \times 10^{-6}$		CL=90%	699
$e^- \pi^0 \pi^0$	*LF*	$< 6.5 \times 10^{-6}$		CL=90%	878
$\mu^- \pi^0 \pi^0$	*LF*	$< 1.4 \times 10^{-5}$		CL=90%	867
$e^- \eta\eta$	*LF*	$< 3.5 \times 10^{-5}$		CL=90%	700
$\mu^- \eta\eta$	*LF*	$< 6.0 \times 10^{-5}$		CL=90%	654
$e^- \pi^0 \eta$	*LF*	$< 2.4 \times 10^{-5}$		CL=90%	798
$\mu^- \pi^0 \eta$	*LF*	$< 2.2 \times 10^{-5}$		CL=90%	784
$\overline{p}\gamma$	*LB*	$< 2.9 \times 10^{-4}$		CL=90%	641
$\overline{p}\pi^0$	*LB*	$< 6.6 \times 10^{-4}$		CL=90%	632
$\overline{p}\eta$	*LB*	$< 1.30 \times 10^{-3}$		CL=90%	476
e^- light boson	*LF*	$< 2.7 \times 10^{-3}$		CL=95%	–
μ^- light boson	*LF*	$< 5 \times 10^{-3}$		CL=95%	–

Heavy Charged Lepton Searches

$L^{\pm}$ – charged lepton

Mass $m >$ 80.2 GeV, CL = 95% $m_\nu \approx 0$

$L^{\pm}$ – stable charged heavy lepton

Mass $m >$ 84.2 GeV, CL = 95%

Neutrinos

See the Particle Listings for a Note "Neutrino Mass" giving details of neutrinos, masses, mixing, and the status of experimental searches.

ν_e $J = \frac{1}{2}$

Mass m: Unexplained effects have resulted in significantly negative m^2 in the new, precise tritium beta decay experiments. It is felt that a real neutrino mass as large as 10–15 eV would cause observable spectral distortions even in the presence of the end-point count excesses.

Mean life/mass, $\tau/m_{\nu_e} > 7 \times 10^9$ s/eV (solar)

Mean life/mass, $\tau/m_{\nu_e} > 300$ s/eV, CL = 90% (reactor)

Magnetic moment $\mu < 1.8 \times 10^{-10}\ \mu_B$, CL = 90%

ν_μ $J = \frac{1}{2}$

Mass $m <$ 0.17 MeV, CL = 90%

Mean life/mass, $\tau/m_{\nu_\mu} >$ 15.4 s/eV, CL = 90%

Magnetic moment $\mu < 7.4 \times 10^{-10}\ \mu_B$, CL = 90%

ν_τ $J = \frac{1}{2}$

Mass $m <$ 18.2 MeV, CL = 95%

Magnetic moment $\mu < 5.4 \times 10^{-7}\ \mu_B$, CL = 90%

Electric dipole moment $d < 5.2 \times 10^{-17}\ e$ cm, CL = 95%

Number of Light Neutrino Types

(including ν_e, ν_μ, and ν_τ)

Number $N = 2.994 \pm 0.012$ (Standard Model fits to LEP data)

Number $N = 3.07 \pm 0.12$ (Direct measurement of invisible Z width)

Massive Neutrinos and Lepton Mixing, Searches for

For excited leptons, see Compositeness Limits below.

See the Particle Listings for a Note "Neutrino Mass" giving details of neutrinos, masses, mixing, and the status of experimental searches.

While no direct, uncontested evidence for massive neutrinos or lepton mixing has been obtained, suggestive evidence has come from solar neutrino observations, from anomalies in the relative fractions of ν_e and ν_μ observed in energetic cosmic-ray air showers, and possibly from a $\bar{\nu}_e$ appearance experiment at Los Alamos. Sample limits are:

Stable Neutral Heavy Lepton Mass Limits

Mass $m >$ 45.0 GeV, CL = 95% (Dirac)

Mass $m >$ 39.5 GeV, CL = 95% (Majorana)

Neutral Heavy Lepton Mass Limits

Mass $m >$ 69.0 GeV, CL = 95% (Dirac ν_L coupling to e, μ, τ with $|U_{\ell j}|^2 > 10^{-12}$)

Mass $m >$ 58.2 GeV, CL = 95% (Majorana ν_L coupling to e, μ, τ with $|U_{\ell j}|^2 > 10^{-12}$)

Solar Neutrinos

Detectors using gallium ($E_\nu \gtrsim 0.2$ MeV), chlorine ($E_\nu \gtrsim 0.8$ MeV), and Čerenkov effect in water ($E_\nu \gtrsim 7$ MeV) measure significantly lower neutrino rates than are predicted from solar models. The deficit in the solar neutrino flux compared with solar model calculations could be explained by oscillations with $\Delta m^2 \leq 10^{-5}$ eV^2 causing the disappearance of ν_e.

Atmospheric Neutrinos

Underground detectors observing neutrinos produced by cosmic rays in the atmosphere have measured a ν_μ/ν_e ratio much less than expected and also a deficiency of upward going ν_μ compared to downward. This could be explained by oscillations leading to the disappearance of ν_μ with $\Delta m^2 \approx 10^{-3}$ to 10^{-2} eV^2.

ν oscillation: $\bar{\nu}_e \not\to \bar{\nu}_e$ (θ = mixing angle)

$\Delta m^2 < 9 \times 10^{-4}$ eV^2, CL = 90% (if $\sin^2 2\theta = 1$)

$\sin^2 2\theta < 0.02$, CL = 90% (if $\Delta(m^2)$ is large)

ν oscillation: ν_μ ($\bar{\nu}_\mu$) $\to$ ν_e ($\bar{\nu}_e$) (any combination)

$\Delta m^2 < 0.075$ eV^2, CL = 90% (if $\sin^2 2\theta = 1$)

$\sin^2 2\theta < 1.8 \times 10^{-3}$, CL = 90% (if $\Delta(m^2)$ is large)

NOTES

In this Summary Table:

When a quantity has "(S = ...)" to its right, the error on the quantity has been enlarged by the "scale factor" S, defined as $S = \sqrt{\chi^2/(N-1)}$, where N is the number of measurements used in calculating the quantity. We do this when $S > 1$, which often indicates that the measurements are inconsistent. When $S > 1.25$, we also show in the Particle Listings an ideogram of the measurements. For more about S, see the Introduction.

A decay momentum p is given for each decay mode. For a 2-body decay, p is the momentum of each decay product in the rest frame of the decaying particle. For a 3-or-more-body decay, p is the largest momentum any of the products can have in this frame.

[a] The uncertainty in the electron mass in unified atomic mass units (u) is ten times smaller than that given by the 1986 CODATA adjustment, quoted in the Table of Physical Constants (Section 1). The conversion to MeV via the factor 931.49432(28) MeV/u is more uncertain because of the electron charge uncertainty. Our value in MeV differs slightly from the 1986 CODATA result.

[b] This is the best "electron disappearance" limit. The best limit for the mode $e^- \to \nu\gamma$ is $> 2.35 \times 10^{25}$ yr (CL=68%).

[c] The muon mass is most precisely known in u (unified atomic mass units). The conversion factor to MeV via the factor 931.49432(28) MeV/u is more uncertain because of the electron charge uncertainty.

[d] See the "Note on Muon Decay Parameters" in the μ Particle Listings for definitions and details.

[e] P_μ is the longitudinal polarization of the muon from pion decay. In standard $V-A$ theory, $P_\mu = 1$ and $\rho = \delta = 3/4$.

[f] This only includes events with the γ energy > 10 MeV. Since the $e^-\bar{\nu}_e\nu_\mu$ and $e^-\bar{\nu}_e\nu_\mu\gamma$ modes cannot be clearly separated, we regard the latter mode as a subset of the former.

[g] See the μ Particle Listings for the energy limits used in this measurement.

[h] A test of additive vs. multiplicative lepton family number conservation.

[i] Basis mode for the τ.

QUARK SUMMARY TABLE

QUARKS

The u-, d-, and s-quark masses are estimates of so-called "current-quark masses," in a mass-independent subtraction scheme such as $\overline{\text{MS}}$ at a scale $\mu \approx 2$ GeV. The c- and b-quark masses are estimated from charmonium, bottomonium, D, and B masses. They are the "running" masses in the $\overline{\text{MS}}$ scheme. These can be different from the heavy quark masses obtained in potential models.

u

$I(J^P) = \frac{1}{2}(\frac{1}{2}^+)$

Mass $m = 1.5$ to 5 MeV [a] Charge $= \frac{2}{3}\ e$ $I_z = +\frac{1}{2}$

$m_u/m_d = 0.20$ to 0.70

d

$I(J^P) = \frac{1}{2}(\frac{1}{2}^+)$

Mass $m = 3$ to 9 MeV [a] Charge $= -\frac{1}{3}\ e$ $I_z = -\frac{1}{2}$

$m_s/m_d = 17$ to 25

$\overline{m} = (m_u + m_d)/2 = 2$ to 6 MeV

s

$I(J^P) = 0(\frac{1}{2}^+)$

Mass $m = 60$ to 170 MeV [a] Charge $= -\frac{1}{3}\ e$ Strangeness $= -1$

$(m_s - (m_u + m_d)/2)/(m_d - m_u) = 34$ to 51

c

$I(J^P) = 0(\frac{1}{2}^+)$

Mass $m = 1.1$ to 1.4 GeV Charge $= \frac{2}{3}\ e$ Charm $= +1$

b

$I(J^P) = 0(\frac{1}{2}^+)$

Mass $m = 4.1$ to 4.4 GeV Charge $= -\frac{1}{3}\ e$ Bottom $= -1$

t

$I(J^P) = 0(\frac{1}{2}^+)$

Charge $= \frac{2}{3}\ e$ Top $= +1$

Mass $m = 173.8 \pm 5.2$ GeV (direct observation of top events)

Mass $m = 170 \pm 7\ (+14)$ GeV (Standard Model electroweak fit, assuming $M_H = M_Z$. Number in parentheses is shift from changing M_H to 300 GeV.

b′ (4th Generation) Quark, Searches for

Mass $m >$ 128 GeV, CL = 95% ($p\bar{p}$, charged current decays)

Mass $m >$ 46.0 GeV, CL = 95% (e^+e^-, all decays)

Free Quark Searches

All searches since 1977 have had negative results.

NOTES

[a] The ratios m_u/m_d and m_s/m_d are extracted from pion and kaon masses using chiral symmetry. The estimates of u and d masses are not without controversy and remain under active investigation. Within the literature there are even suggestions that the u quark could be essentially massless. The s-quark mass is estimated from SU(3) splittings in hadron masses.

LIGHT UNFLAVORED MESONS
($S = C = B = 0$)

For $I = 1$ (π, $b1$, ρ, a): $u\bar{d}$, $(u\bar{u}-d\bar{d})/\sqrt{2}$, $d\bar{u}$;
for $I = 0$ (η, η', $h1$, h', ω, ϕ, $f1$, f'): $c_1(u\bar{u}+d\bar{d}) + c_2(s\bar{s})$

$\pi^\pm$

$I^G(J^P) = 1^-(0^-)$

Mass $m = 139.56995 \pm 0.00035$ MeV
Mean life $\tau = (2.6033 \pm 0.0005) \times 10^{-8}$ s (S = 1.2)
$c\tau = 7.8045$ m

$\pi^\pm \to \ell^\pm \nu\gamma$ form factors [a]

$F_V = 0.017 \pm 0.008$
$F_A = 0.0116 \pm 0.0016$ (S = 1.3)
$R = 0.059^{+0.009}_{-0.008}$

π^- modes are charge conjugates of the modes below.

π^+ DECAY MODES		Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$\mu^+\nu_\mu$	[b]	(99.98770±0.00004) %		30
$\mu^+\nu_\mu\gamma$	[c]	(1.24 ±0.25) $\times 10^{-4}$		30
$e^+\nu_e$	[b]	(1.230 ±0.004) $\times 10^{-4}$		70
$e^+\nu_e\gamma$	[c]	(1.61 ±0.23) $\times 10^{-7}$		70
$e^+\nu_e\pi^0$		(1.025 ±0.034) $\times 10^{-8}$		4
$e^+\nu_e e^+e^-$		(3.2 ±0.5) $\times 10^{-9}$		70
$e^+\nu_e\nu\bar{\nu}$		< 5 $\times 10^{-6}$	90%	70
Lepton Family number (LF) or Lepton number (L) violating modes				
$\mu^+\bar{\nu}_e$	L	[d] < 1.5 $\times 10^{-3}$	90%	30
$\mu^+\nu_e$	LF	[d] < 8.0 $\times 10^{-3}$	90%	30
$\mu^-e^+e^+\nu$	LF	< 1.6 $\times 10^{-6}$	90%	30

π^0

$I^G(J^{PC}) = 1^-(0^{-+})$

Mass $m = 134.9764 \pm 0.0006$ MeV
$m_{\pi^\pm} - m_{\pi^0} = 4.5936 \pm 0.0005$ MeV
Mean life $\tau = (8.4 \pm 0.6) \times 10^{-17}$ s (S = 3.0)
$c\tau = 25.1$ nm

π^0 DECAY MODES		Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
2γ		(98.798±0.032) %	S=1.1	67
$e^+e^-\gamma$		(1.198±0.032) %	S=1.1	67
γpositronium		(1.82 ±0.29) $\times 10^{-9}$		67
$e^+e^+e^-e^-$		(3.14 ±0.30) $\times 10^{-5}$		67
e^+e^-		(7.5 ±2.0) $\times 10^{-8}$		67
4γ		< 2 $\times 10^{-8}$	CL=90%	67
$\nu\bar{\nu}$	[e]	< 8.3 $\times 10^{-7}$	CL=90%	67
$\nu_e\bar{\nu}_e$		< 1.7 $\times 10^{-6}$	CL=90%	67
$\nu_\mu\bar{\nu}_\mu$		< 3.1 $\times 10^{-6}$	CL=90%	67
$\nu_\tau\bar{\nu}_\tau$		< 2.1 $\times 10^{-6}$	CL=90%	67
Charge conjugation (C) or Lepton Family number (LF) violating modes				
3γ	C	< 3.1 $\times 10^{-8}$	CL=90%	67
$\mu^+e^- + e^-\mu^+$	LF	< 1.72 $\times 10^{-8}$	CL=90%	26

η

$I^G(J^{PC}) = 0^+(0^{-+})$

Mass $m = 547.30 \pm 0.12$ MeV
Full width $\Gamma = 1.18 \pm 0.11$ keV [f] (S = 1.8)

C-nonconserving decay parameters

$\pi^+\pi^-\pi^0$ Left-right asymmetry = $(0.09 \pm 0.17) \times 10^{-2}$
$\pi^+\pi^-\pi^0$ Sextant asymmetry = $(0.18 \pm 0.16) \times 10^{-2}$
$\pi^+\pi^-\pi^0$ Quadrant asymmetry = $(-0.17 \pm 0.17) \times 10^{-2}$
$\pi^+\pi^-\gamma$ Left-right asymmetry = $(0.9 \pm 0.4) \times 10^{-2}$
$\pi^+\pi^-\gamma$ β (D-wave) = 0.05 ± 0.06 (S = 1.5)

Dalitz plot parameter

$\pi^0\pi^0\pi^0$ $\alpha = -0.039 \pm 0.015$

η DECAY MODES		Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
Neutral modes				
neutral modes		(71.5 ±0.6) %	S=1.4	–
2γ	[f]	(39.21±0.34) %	S=1.4	274
$3\pi^0$		(32.2 ±0.4) %	S=1.3	178
$\pi^0 2\gamma$		(7.1 ±1.4) $\times 10^{-4}$		257
other neutral modes		< 2.8 %	CL=90%	–
Charged modes				
charged modes		(28.5 ±0.6) %	S=1.4	–
$\pi^+\pi^-\pi^0$		(23.1 ±0.5) %	S=1.4	173
$\pi^+\pi^-\gamma$		(4.77±0.13) %	S=1.3	235
$e^+e^-\gamma$		(4.9 ±1.1) $\times 10^{-3}$		274
$\mu^+\mu^-\gamma$		(3.1 ±0.4) $\times 10^{-4}$		252
e^+e^-		< 7.7 $\times 10^{-5}$	CL=90%	274
$\mu^+\mu^-$		(5.8 ±0.8) $\times 10^{-6}$		252
$\pi^+\pi^-e^+e^-$		(1.3 $^{+1.2}_{-0.8}$) $\times 10^{-3}$		235
$\pi^+\pi^-2\gamma$		< 2.1 $\times 10^{-3}$		235
$\pi^+\pi^-\pi^0\gamma$		< 6 $\times 10^{-4}$	CL=90%	173
$\pi^0\mu^+\mu^-\gamma$		< 3 $\times 10^{-6}$	CL=90%	210
Charge conjugation (C)Parity (P)or Charge conjugation × Parity (CP)or Lepton Family number (LF) violating modes				
$\pi^+\pi^-$	$PTCP$	< 9 $\times 10^{-4}$	CL=90%	235
3γ	C	< 5 $\times 10^{-4}$	CL=95%	274
$\pi^0e^+e^-$	C	[g] < 4 $\times 10^{-5}$	CL=90%	257
$\pi^0\mu^+\mu^-$	C	[g] < 5 $\times 10^{-6}$	CL=90%	210
$\mu^+e^- + \mu^-e^+$	LF	< 6 $\times 10^{-6}$	CL=90%	263

$f_0(400\text{–}1200)$ [h] or σ

$I^G(J^{PC}) = 0^+(0^{++})$

Mass $m = (400\text{–}1200)$ MeV
Full width $\Gamma = (600\text{–}1000)$ MeV

$f_0(400\text{–}1200)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\pi\pi$	dominant	–
$\gamma\gamma$	seen	–

$\rho(770)$ [l]

$I^G(J^{PC}) = 1^+(1^{--})$

Mass $m = 770.0 \pm 0.8$ MeV (S = 1.8)
Full width $\Gamma = 150.7 \pm 1.1$ MeV
$\Gamma_{ee} = 6.77 \pm 0.32$ keV

$\rho(770)$ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
$\pi\pi$	~ 100 %		358
$\rho(770)^\pm$ decays			
$\pi^\pm\gamma$	$(4.5 \pm 0.5) \times 10^{-4}$	S=2.2	372
$\pi^\pm\eta$	$< 6 \times 10^{-3}$	CL=84%	146
$\pi^\pm\pi^+\pi^-\pi^0$	$< 2.0 \times 10^{-3}$	CL=84%	249
$\rho(770)^0$ decays			
$\pi^+\pi^-\gamma$	$(9.9 \pm 1.6) \times 10^{-3}$		358
$\pi^0\gamma$	$(6.8 \pm 1.7) \times 10^{-4}$		372
$\eta\gamma$	$(2.4 \,^{+0.8}_{-0.9}) \times 10^{-4}$	S=1.6	189
$\mu^+\mu^-$ [j]	$(4.60 \pm 0.28) \times 10^{-5}$		369
e^+e^- [j]	$(4.49 \pm 0.22) \times 10^{-5}$		384
$\pi^+\pi^-\pi^0$	$< 1.2 \times 10^{-4}$	CL=90%	319
$\pi^+\pi^-\pi^+\pi^-$	$< 2 \times 10^{-4}$	CL=90%	246
$\pi^+\pi^-\pi^0\pi^0$	$< 4 \times 10^{-5}$	CL=90%	252

$\omega(782)$

$I^G(J^{PC}) = 0^-(1^{--})$

Mass $m = 781.94 \pm 0.12$ MeV (S = 1.5)
Full width $\Gamma = 8.41 \pm 0.09$ MeV
$\Gamma_{ee} = 0.60 \pm 0.02$ keV

$\omega(782)$ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
$\pi^+\pi^-\pi^0$	(88.8 ± 0.7) %		327
$\pi^0\gamma$	(8.5 ± 0.5) %		379
$\pi^+\pi^-$	(2.21 ± 0.30) %		365
neutrals (excluding $\pi^0\gamma$)	$(5.3 \,^{+8.7}_{-3.5}) \times 10^{-3}$		–
$\eta\gamma$	$(6.5 \pm 1.0) \times 10^{-4}$		199
$\pi^0 e^+e^-$	$(5.9 \pm 1.9) \times 10^{-4}$		379
$\pi^0\mu^+\mu^-$	$(9.6 \pm 2.3) \times 10^{-5}$		349
e^+e^-	$(7.07 \pm 0.19) \times 10^{-5}$	S=1.1	391
$\pi^+\pi^-\pi^0\pi^0$	< 2 %	CL=90%	261
$\pi^+\pi^-\gamma$	$< 3.6 \times 10^{-3}$	CL=95%	365
$\pi^+\pi^-\pi^+\pi^-$	$< 1 \times 10^{-3}$	CL=90%	256
$\pi^0\pi^0\gamma$	$(7.2 \pm 2.5) \times 10^{-5}$		367
$\mu^+\mu^-$	$< 1.8 \times 10^{-4}$	CL=90%	376
3γ	$< 1.9 \times 10^{-4}$	CL=95%	391
Charge conjugation (C) violating modes			
$\eta\pi^0$ C	$< 1 \times 10^{-3}$	CL=90%	162
$3\pi^0$ C	$< 3 \times 10^{-4}$	CL=90%	329

$\eta'(958)$

$I^G(J^{PC}) = 0^+(0^{-+})$

Mass $m = 957.78 \pm 0.14$ MeV
Full width $\Gamma = 0.203 \pm 0.016$ MeV (S = 1.3)

$\eta'(958)$ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
$\pi^+\pi^-\eta$	(43.8 ± 1.5) %	S=1.1	232
$\rho^0\gamma$(including non-resonant $\pi^+\pi^-\gamma$)	(30.2 ± 1.3) %	S=1.1	169
$\pi^0\pi^0\eta$	(20.7 ± 1.3) %	S=1.2	239
$\omega\gamma$	(3.01 ± 0.30) %		160
$\gamma\gamma$	(2.11 ± 0.13) %	S=1.2	479
$3\pi^0$	$(1.54 \pm 0.26) \times 10^{-3}$		430
$\mu^+\mu^-\gamma$	$(1.08 \pm 0.26) \times 10^{-4}$		467
$\pi^+\pi^-\pi^0$	< 5 %	CL=90%	427
$\pi^0\rho^0$	< 4 %	CL=90%	118
$\pi^+\pi^+\pi^-\pi^-$	< 1 %	CL=90%	372
$\pi^+\pi^+\pi^-\pi^-$ neutrals	< 1 %	CL=95%	–
$\pi^+\pi^+\pi^-\pi^-\pi^0$	< 1 %	CL=90%	298
6π	< 1 %	CL=90%	189
$\pi^+\pi^- e^+e^-$	$< 6 \times 10^{-3}$	CL=90%	458
$\pi^0\gamma\gamma$	$< 8 \times 10^{-4}$	CL=90%	469
$4\pi^0$	$< 5 \times 10^{-4}$	CL=90%	379
e^+e^-	$< 2.1 \times 10^{-7}$	CL=90%	479
Charge conjugation (C) or Parity (P) violating modes			
$\pi^+\pi^-$ P/CP	< 2 %	CL=90%	458
$\pi^0\pi^0$ P/CP	$< 9 \times 10^{-4}$	CL=90%	459
$\pi^0 e^+e^-$ C [g]	< 1.3 %	CL=90%	469
ηe^+e^- C [g]	< 1.1 %	CL=90%	322
3γ C	$< 1.0 \times 10^{-4}$	CL=90%	479
$\mu^+\mu^-\pi^0$ C [g]	$< 6.0 \times 10^{-5}$	CL=90%	445
$\mu^+\mu^-\eta$ C [g]	$< 1.5 \times 10^{-5}$	CL=90%	274

$f_0(980)$ [k]

$I^G(J^{PC}) = 0^+(0^{++})$

Mass $m = 980 \pm 10$ MeV
Full width $\Gamma = 40$ to 100 MeV

$f_0(980)$ DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$\pi\pi$	dominant		470
$K\overline{K}$	seen		–
$\gamma\gamma$	$(1.19 \pm 0.33) \times 10^{-5}$		490
e^+e^-	$< 3 \times 10^{-7}$	90%	490

$a_0(980)$ [k]

$I^G(J^{PC}) = 1^-(0^{++})$

Mass $m = 983.4 \pm 0.9$ MeV
Full width $\Gamma = 50$ to 100 MeV

$a_0(980)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\eta\pi$	dominant	321
$K\overline{K}$	seen	–
$\gamma\gamma$	seen	492

$\phi(1020)$

$I^G(J^{PC}) = 0^-(1^{--})$

Mass $m = 1019.413 \pm 0.008$ MeV
Full width $\Gamma = 4.43 \pm 0.05$ MeV

$\phi(1020)$ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
K^+K^-	(49.1 ± 0.8) %	S=1.3	127
$K^0_L K^0_S$	(34.1 ± 0.6) %	S=1.2	110
$\rho\pi + \pi^+\pi^-\pi^0$	(15.5 ± 0.7) %	S=1.5	–
$\eta\gamma$	(1.26 ± 0.06) %	S=1.1	363
$\pi^0\gamma$	$(1.31 \pm 0.13) \times 10^{-3}$		501
e^+e^-	$(2.99 \pm 0.08) \times 10^{-4}$	S=1.2	510
$\mu^+\mu^-$	$(2.5 \pm 0.4) \times 10^{-4}$		499
ηe^+e^-	$(1.3 \,^{+0.8}_{-0.6}) \times 10^{-4}$		363
$\pi^+\pi^-$	$(8 \,^{+5}_{-4}) \times 10^{-5}$	S=1.5	490
$\omega\gamma$	< 5 %	CL=84%	210
$\rho\gamma$	$< 7 \times 10^{-4}$	CL=90%	219
$\pi^+\pi^-\gamma$	$< 3 \times 10^{-5}$	CL=90%	490
$f_0(980)\gamma$	$< 1 \times 10^{-4}$	CL=90%	39
$\pi^0\pi^0\gamma$	$< 1 \times 10^{-3}$	CL=90%	492
$\pi^+\pi^-\pi^+\pi^-$	$< 8.7 \times 10^{-4}$	CL=90%	410
$\pi^+\pi^+\pi^-\pi^-\pi^0$	$< 1.5 \times 10^{-4}$	CL=95%	341
$\pi^0 e^+e^-$	$< 1.2 \times 10^{-4}$	CL=90%	501
$\pi^0\eta\gamma$	$< 2.5 \times 10^{-3}$	CL=90%	346
$a_0(980)\gamma$	$< 5 \times 10^{-3}$	CL=90%	36
$\eta'(958)\gamma$	$(1.2 \,^{+0.7}_{-0.5}) \times 10^{-4}$		–
$\mu^+\mu^-\gamma$	$(2.3 \pm 1.0) \times 10^{-5}$		–

$h_1(1170)$

$I^G(J^{PC}) = 0^-(1^{+-})$

Mass $m = 1170 \pm 20$ MeV
Full width $\Gamma = 360 \pm 40$ MeV

$h_1(1170)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\rho\pi$	seen	310

$b_1(1235)$ $I^G(J^{PC}) = 1^+(1^{+-})$

Mass $m = 1229.5 \pm 3.2$ MeV (S = 1.6)
Full width $\Gamma = 142 \pm 9$ MeV (S = 1.2)

$b_1(1235)$ DECAY MODES	Fraction (Γ_j/Γ)	Confidence level	p (MeV/c)
$\omega\pi$	dominant		348
[D/S amplitude ratio $= 0.29 \pm 0.04$]			
$\pi^\pm\gamma$	$(1.6 \pm 0.4) \times 10^{-3}$		608
$\eta\rho$	seen		–
$\pi^+\pi^+\pi^-\pi^0$	< 50 %	84%	536
$(K\overline{K})^\pm\pi^0$	< 8 %	90%	248
$K^0_S K^0_L \pi^\pm$	< 6 %	90%	238
$K^0_S K^0_S \pi^\pm$	< 2 %	90%	238
$\phi\pi$	< 1.5 %	84%	146

$a_1(1260)$ [l] $I^G(J^{PC}) = 1^-(1^{++})$

Mass $m = 1230 \pm 40$ MeV [m]
Full width $\Gamma = 250$ to 600 MeV

$a_1(1260)$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$\rho\pi$	dominant	356
[D/S amplitude ratio $= -0.100 \pm 0.028$]		
$\pi\gamma$	seen	607
$\pi(\pi\pi)_{S\text{-wave}}$	possibly seen	575

$f_2(1270)$ $I^G(J^{PC}) = 0^+(2^{++})$

Mass $m = 1275.0 \pm 1.2$ MeV
Full width $\Gamma = 185.5^{+3.8}_{-2.7}$ MeV (S = 1.5)

$f_2(1270)$ DECAY MODES	Fraction (Γ_j/Γ)	Scale factor/ Confidence level	p (MeV/c)
$\pi\pi$	$(84.6\ ^{+2.5}_{-1.3})$ %	S=1.3	622
$\pi^+\pi^-2\pi^0$	$(7.2\ ^{+1.5}_{-2.7})$ %	S=1.3	562
$K\overline{K}$	(4.6 ± 0.4) %	S=2.8	403
$2\pi^+2\pi^-$	(2.8 ± 0.4) %	S=1.2	559
$\eta\eta$	$(4.5 \pm 1.0) \times 10^{-3}$	S=2.4	327
$4\pi^0$	$(3.0 \pm 1.0) \times 10^{-3}$		564
$\gamma\gamma$	$(1.32^{+0.17}_{-0.16}) \times 10^{-5}$		637
$\eta\pi\pi$	$< 8 \times 10^{-3}$	CL=95%	475
$K^0K^-\pi^+ +$ c.c.	$< 3.4 \times 10^{-3}$	CL=95%	293
e^+e^-	$< 9 \times 10^{-9}$	CL=90%	637

$f_1(1285)$ $I^G(J^{PC}) = 0^+(1^{++})$

Mass $m = 1281.9 \pm 0.6$ MeV (S = 1.7)
Full width $\Gamma = 24.0 \pm 1.2$ MeV (S = 1.4)
$(4\pi = \rho(\pi\pi)_{Pwave})$

$f_1(1285)$ DECAY MODES	Fraction (Γ_j/Γ)	Scale factor/ Confidence level	p (MeV/c)
4π	(35 ± 4) %	S=1.6	563
$\pi^0\pi^0\pi^+\pi^-$	(23.5 ± 3.0) %	S=1.6	566
$2\pi^+2\pi^-$	(11.7 ± 1.5) %	S=1.6	563
$\rho^0\pi^+\pi^-$	(11.7 ± 1.5) %	S=1.6	340
$4\pi^0$	$< 7 \times 10^{-4}$	CL=90%	568
$\eta\pi\pi$	(50 ± 18) %		479
$a_0(980)\pi$ [ignoring $a_0(980) \to K\overline{K}$]	(34 ± 8) %	S=1.2	234
$\eta\pi\pi$ [excluding $a_0(980)\pi$]	(15 ± 7) %	S=1.1	–
$K\overline{K}\pi$	(9.6 ± 1.2) %	S=1.5	308
$K\overline{K}^*(892)$	not seen		–
$\gamma\rho^0$	(5.4 ± 1.2) %	S=2.3	410
$\phi\gamma$	$(7.9 \pm 3.0) \times 10^{-4}$		236

$\eta(1295)$ $I^G(J^{PC}) = 0^+(0^{-+})$

Mass $m = 1297.0 \pm 2.8$ MeV
Full width $\Gamma = 53 \pm 6$ MeV

$\eta(1295)$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$\eta\pi^+\pi^-$	seen	488
$a_0(980)\pi$	seen	245
$\eta\pi^0\pi^0$	seen	–
$\eta(\pi\pi)_{S\text{-wave}}$	seen	–

$\pi(1300)$ $I^G(J^{PC}) = 1^-(0^{-+})$

Mass $m = 1300 \pm 100$ MeV [m]
Full width $\Gamma = 200$ to 600 MeV

$\pi(1300)$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$\rho\pi$	seen	406
$\pi(\pi\pi)_{S\text{-wave}}$	seen	–

$a_2(1320)$ $I^G(J^{PC}) = 1^-(2^{++})$

Mass $m = 1318.1 \pm 0.6$ MeV (S = 1.1)
Full width $\Gamma = 107 \pm 5$ MeV [m] ($K^\pm K^0_S$ and $\eta\pi$ modes)

$a_2(1320)$ DECAY MODES	Fraction (Γ_j/Γ)	Scale factor/ Confidence level	p (MeV/c)
$\rho\pi$	(70.1 ± 2.7) %	S=1.2	419
$\eta\pi$	(14.5 ± 1.2) %		535
$\omega\pi\pi$	(10.6 ± 3.2) %	S=1.3	362
$K\overline{K}$	(4.9 ± 0.8) %		437
$\eta'(958)\pi$	$(5.3 \pm 0.9) \times 10^{-3}$		287
$\pi^\pm\gamma$	$(2.8 \pm 0.6) \times 10^{-3}$		652
$\gamma\gamma$	$(9.4 \pm 0.7) \times 10^{-6}$		659
$\pi^+\pi^-\pi^-$	< 8 %	CL=90%	621
e^+e^-	$< 2.3 \times 10^{-7}$	CL=90%	659

$f_0(1370)$ [k] $I^G(J^{PC}) = 0^+(0^{++})$

Mass $m = 1200$ to 1500 MeV
Full width $\Gamma = 200$ to 500 MeV

$f_0(1370)$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$\pi\pi$	seen	–
4π	seen	–
$4\pi^0$	seen	–
$2\pi^+2\pi^-$	seen	–
$\pi^+\pi^-2\pi^0$	seen	–
$2(\pi\pi)_{S\text{-wave}}$	seen	–
$\eta\eta$	seen	–
$K\overline{K}$	seen	–
$\gamma\gamma$	seen	–
e^+e^-	not seen	–

$f_1(1420)$ [n] $I^G(J^{PC}) = 0^+(1^{++})$

Mass $m = 1426.2 \pm 1.2$ MeV (S = 1.3)
Full width $\Gamma = 55.0 \pm 3.0$ MeV

$f_1(1420)$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$K\overline{K}\pi$	dominant	439
$K\overline{K}^*(892) +$ c.c.	dominant	155
$\eta\pi\pi$	possibly seen	571

$\omega(1420)$ [o] $I^G(J^{PC}) = 0^-(1^{--})$

Mass $m = 1419 \pm 31$ MeV
Full width $\Gamma = 174 \pm 60$ MeV

$\omega(1420)$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$\rho\pi$	dominant	488

$\eta(1440)$ [p]

$I^G(J^{PC}) = 0^+(0^{-+})$

Mass $m = 1400$ - 1470 MeV [m]
Full width $\Gamma = 50$ - 80 MeV [m]

$\eta(1440)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$K\overline{K}\pi$	seen	–
$K\overline{K}^*(892)+$ c.c.	seen	–
$\eta\pi\pi$	seen	–
$a_0(980)\pi$	seen	–
$\eta(\pi\pi)_S$-wave	seen	–
4π	seen	–

$a_0(1450)$

$I^G(J^{PC}) = 1^-(0^{++})$

Mass $m = 1474 \pm 19$ MeV
Full width $\Gamma = 265 \pm 13$ MeV

$a_0(1450)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\pi\eta$	seen	613
$\pi\eta'(958)$	seen	392
$K\overline{K}$	seen	530

$\rho(1450)$ [q]

$I^G(J^{PC}) = 1^+(1^{--})$

Mass $m = 1465 \pm 25$ MeV [m]
Full width $\Gamma = 310 \pm 60$ MeV [m]

$\rho(1450)$ DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$\pi\pi$	seen		719
4π	seen		665
$\omega\pi$	<2.0 %	95%	512
e^+e^-	seen		732
$\eta\rho$	<4 %		317
$\phi\pi$	<1 %		358
$K\overline{K}$	$<1.6\times10^{-3}$	95%	541

$f_0(1500)$ [r]

$I^G(J^{PC}) = 0^+(0^{++})$

Mass $m = 1500 \pm 10$ MeV (S = 1.3)
Full width $\Gamma = 112 \pm 10$ MeV

$f_0(1500)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\eta\eta'(958)$	seen	–
$\eta\eta$	seen	513
4π	seen	–
$4\pi^0$	seen	690
$2\pi^+2\pi^-$	seen	686
2π	seen	–
$\pi^+\pi^-$	seen	737
$2\pi^0$	seen	738
$K\overline{K}$	seen	563

$f_2'(1525)$

$I^G(J^{PC}) = 0^+(2^{++})$

Mass $m = 1525 \pm 5$ MeV [m]
Full width $\Gamma = 76 \pm 10$ MeV [m]

$f_2'(1525)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$K\overline{K}$	(88.8 ±3.1) %	581
$\eta\eta$	(10.3 ±3.1) %	531
$\pi\pi$	(8.2 ±1.5) $\times10^{-3}$	750
$\gamma\gamma$	(1.32±0.21) $\times10^{-6}$	763

$\omega(1600)$ [s]

$I^G(J^{PC}) = 0^-(1^{--})$

Mass $m = 1649 \pm 24$ MeV (S = 2.3)
Full width $\Gamma = 220 \pm 35$ MeV (S = 1.6)

$\omega(1600)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\rho\pi$	seen	637
$\omega\pi\pi$	seen	601
e^+e^-	seen	824

$\omega_3(1670)$

$I^G(J^{PC}) = 0^-(3^{--})$

Mass $m = 1667 \pm 4$ MeV
Full width $\Gamma = 168 \pm 10$ MeV [m]

$\omega_3(1670)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\rho\pi$	seen	647
$\omega\pi\pi$	seen	614
$b_1(1235)\pi$	possibly seen	359

$\pi_2(1670)$

$I^G(J^{PC}) = 1^-(2^{-+})$

Mass $m = 1670 \pm 20$ MeV [m]
Full width $\Gamma = 258 \pm 18$ MeV [m] (S = 1.7)

$\pi_2(1670)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
3π	(95.8±1.4) %	806
$f_2(1270)\pi$	(56.2±3.2) %	325
$\rho\pi$	(31 ±4) %	649
$f_0(1370)\pi$	(8.7±3.4) %	–
$K\overline{K}^*(892)+$ c.c.	(4.2±1.4) %	453

$\phi(1680)$

$I^G(J^{PC}) = 0^-(1^{--})$

Mass $m = 1680 \pm 20$ MeV [m]
Full width $\Gamma = 150 \pm 50$ MeV [m]

$\phi(1680)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$K\overline{K}^*(892)+$ c.c.	dominant	463
$K^0_SK\pi$	seen	620
$K\overline{K}$	seen	681
e^+e^-	seen	840
$\omega\pi\pi$	not seen	622

$\rho_3(1690)$

$I^G(J^{PC}) = 1^+(3^{--})$

J^P from the 2π and $K\overline{K}$ modes.
Mass $m = 1691 \pm 5$ MeV [m]
Full width $\Gamma = 160 \pm 10$ MeV [m] (S = 1.5)

$\rho_3(1690)$ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor	p (MeV/c)
4π	(71.1 ± 1.9) %		788
$\pi^\pm\pi^+\pi^-\pi^0$	(67 ±22) %		788
$\omega\pi$	(16 ± 6) %		656
$\pi\pi$	(23.6 ± 1.3) %		834
$K\overline{K}\pi$	(3.8 ± 1.2) %		628
$K\overline{K}$	(1.58± 0.26) %	1.2	686
$\eta\pi^+\pi^-$	seen		728

$\rho(1700)$ [q]

$I^G(J^{PC}) = 1^+(1^{--})$

Mass $m = 1700 \pm 20$ MeV [m] ($\eta\rho^0$ and $\pi^+\pi^-$ modes)
Full width $\Gamma = 240 \pm 60$ MeV [m] ($\eta\rho^0$ and $\pi^+\pi^-$ modes)

$\rho(1700)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\rho\pi\pi$	dominant	640
$2(\pi^+\pi^-)$	large	792
$\rho^0\pi^+\pi^-$	large	640
$\rho^\pm\pi^\mp\pi^0$	large	642
$\pi^+\pi^-$	seen	838
$\pi^-\pi^0$	seen	839
$K\overline{K}^*(892)+$ c.c.	seen	479
$\eta\rho$	seen	533
$K\overline{K}$	seen	692
e^+e^-	seen	850
$\pi^0\omega$	seen	662

$f_J(1710)$ [t]

$I^G(J^{PC}) = 0^+(\text{even}^{++})$

Mass $m = 1712 \pm 5$ MeV (S = 1.1)
Full width $\Gamma = 133 \pm 14$ MeV (S = 1.2)

$f_J(1710)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$K\overline{K}$	seen	690
$\eta\eta$	seen	648
$\pi\pi$	seen	837

$\pi(1800)$

$I^G(J^{PC}) = 1^-(0^{-+})$

Mass $m = 1801 \pm 13$ MeV (S = 1.9)
Full width $\Gamma = 210 \pm 15$ MeV

$\pi(1800)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\pi^+\pi^-\pi^-$	seen	–
$f_0(980)\pi^-$	seen	623
$f_0(1370)\pi^-$	seen	–
$\rho\pi^-$	not seen	728
$\eta\eta\pi^-$	seen	–
$a_0(980)\eta$	seen	459
$f_0(1500)\pi^-$	seen	240
$\eta\eta'(958)\pi^-$	seen	–
$K_0^*(1430)K^-$	seen	–
$K^*(892)K^-$	not seen	560

$\phi_3(1850)$

$I^G(J^{PC}) = 0^-(3^{--})$

Mass $m = 1854 \pm 7$ MeV
Full width $\Gamma = 87^{+28}_{-23}$ MeV (S = 1.2)

$\phi_3(1850)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$K\overline{K}$	seen	785
$K\overline{K}^*(892)+$ c.c.	seen	602

$f_2(2010)$

$I^G(J^{PC}) = 0^+(2^{++})$

Seen by one group only.
Mass $m = 2011^{+60}_{-80}$ MeV
Full width $\Gamma = 202 \pm 60$ MeV

$f_2(2010)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\phi\phi$	seen	–

$a_4(2040)$

$I^G(J^{PC}) = 1^-(4^{++})$

Mass $m = 2020 \pm 16$ MeV
Full width $\Gamma = 387 \pm 70$ MeV

$a_4(2040)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$K\overline{K}$	seen	892
$\pi^+\pi^-\pi^0$	seen	–
$\eta\pi^0$	seen	941

$f_4(2050)$

$I^G(J^{PC}) = 0^+(4^{++})$

Mass $m = 2044 \pm 11$ MeV (S = 1.4)
Full width $\Gamma = 208 \pm 13$ MeV (S = 1.2)

$f_4(2050)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\omega\omega$	(26 ±6) %	658
$\pi\pi$	(17.0±1.5) %	1012
$K\overline{K}$	$(\ 6.8^{+3.4}_{-1.8}) \times 10^{-3}$	895
$\eta\eta$	$(\ 2.1\pm0.8) \times 10^{-3}$	863
$4\pi^0$	< 1.2 %	977

$f_2(2300)$

$I^G(J^{PC}) = 0^+(2^{++})$

Mass $m = 2297 \pm 28$ MeV
Full width $\Gamma = 149 \pm 40$ MeV

$f_2(2300)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\phi\phi$	seen	529

$f_2(2340)$

$I^G(J^{PC}) = 0^+(2^{++})$

Mass $m = 2339 \pm 60$ MeV
Full width $\Gamma = 319^{+80}_{-70}$ MeV

$f_2(2340)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\phi\phi$	seen	573

STRANGE MESONS
($S = \pm 1$, $C = B = 0$)

$K^+ = u\bar{s}$, $K^0 = d\bar{s}$, $\overline{K}^0 = \bar{d}s$, $K^- = \bar{u}s$ similarly for K^*'s

$K^\pm$

$I(J^P) = \frac{1}{2}(0^-)$

Mass $m = 493.677 \pm 0.016$ MeV [u] (S = 2.8)
Mean life $\tau = (1.2386 \pm 0.0024) \times 10^{-8}$ s (S = 2.0)
$c\tau = 3.713$ m

Slope parameter g [v]

(See Particle Listings for quadratic coefficients)
$K^+ \to \pi^+\pi^+\pi^- = -0.2154 \pm 0.0035$ (S = 1.4)
$K^- \to \pi^-\pi^-\pi^+ = -0.217 \pm 0.007$ (S = 2.5)
$K^\pm \to \pi^\pm\pi^0\pi^0 = 0.594 \pm 0.019$ (S = 1.3)

$K^\pm$ decay form factors [a,w]

K^+_{e3} $\lambda_+ = 0.0286 \pm 0.0022$
$K^+_{\mu3}$ $\lambda_+ = 0.032 \pm 0.008$ (S = 1.6)
$K^+_{\mu3}$ $\lambda_0 = 0.006 \pm 0.007$ (S = 1.6)
K^+_{e3} $|f_S/f_+| = 0.084 \pm 0.023$ (S = 1.2)
K^+_{e3} $|f_T/f_+| = 0.38 \pm 0.11$ (S = 1.1)
$K^+_{\mu3}$ $|f_T/f_+| = 0.02 \pm 0.12$
$K^+ \to e^+\nu_e\gamma$ $|F_A + F_V| = 0.148 \pm 0.010$
$K^+ \to \mu^+\nu_\mu\gamma$ $|F_A + F_V| < 0.23$ CL = 90%
$K^+ \to e^+\nu_e\gamma$ $|F_A - F_V| < 0.49$
$K^+ \to \mu^+\nu_\mu\gamma$ $|F_A - F_V| = -2.2$ to 0.3

K^- modes are charge conjugates of the modes below.

K^+ DECAY MODES		Fraction (Γ_j/Γ)	Scale factor/ Confidence level	p (MeV/c)
$\mu^+\nu_\mu$		(63.51±0.18) %	S=1.3	236
$e^+\nu_e$		$(1.55 \pm 0.07) \times 10^{-5}$		247
$\pi^+\pi^0$		(21.16±0.14) %	S=1.1	205
$\pi^+\pi^+\pi^-$		(5.59±0.05) %	S=1.8	125
$\pi^+\pi^0\pi^0$		(1.73±0.04) %	S=1.2	133
$\pi^0\mu^+\nu_\mu$		(3.18±0.08) %	S=1.5	215
Called $K^+_{\mu3}$.				
$\pi^0 e^+\nu_e$		(4.82±0.06) %	S=1.3	228
Called K^+_{e3}.				
$\pi^0\pi^0 e^+\nu_e$		$(2.1 \pm 0.4) \times 10^{-5}$		206
$\pi^+\pi^- e^+\nu_e$		$(3.91 \pm 0.17) \times 10^{-5}$		203
$\pi^+\pi^-\mu^+\nu_\mu$		$(1.4 \pm 0.9) \times 10^{-5}$		151
$\pi^0\pi^0\pi^0 e^+\nu_e$		$< 3.5 \times 10^{-6}$	CL=90%	135
$\pi^+\gamma\gamma$	[x]	$(1.10 \pm 0.32) \times 10^{-6}$		227
$\pi^+ 3\gamma$	[x]	$< 1.0 \times 10^{-4}$	CL=90%	227
$\mu^+\nu_\mu\nu\overline{\nu}$		$< 6.0 \times 10^{-6}$	CL=90%	236
$e^+\nu_e\nu\overline{\nu}$		$< 6 \times 10^{-5}$	CL=90%	247
$\mu^+\nu_\mu e^+ e^-$		$(1.3 \pm 0.4) \times 10^{-7}$		236
$e^+\nu_e e^+ e^-$		$(3.0\ ^{+3.0}_{-1.5}) \times 10^{-8}$		247
$\mu^+\nu_\mu\mu^+\mu^-$		$< 4.1 \times 10^{-7}$	CL=90%	185
$\mu^+\nu_\mu\gamma$	[x,y]	$(5.50 \pm 0.28) \times 10^{-3}$		236
$\pi^+\pi^0\gamma$	[x,y]	$(2.75 \pm 0.15) \times 10^{-4}$		205
$\pi^+\pi^0\gamma$(DE)	[x,z]	$(1.8 \pm 0.4) \times 10^{-5}$		205
$\pi^+\pi^+\pi^-\gamma$	[x,y]	$(1.04 \pm 0.31) \times 10^{-4}$		125
$\pi^+\pi^0\pi^0\gamma$	[x,y]	$(7.5\ ^{+5.5}_{-3.0}) \times 10^{-6}$		133
$\pi^0\mu^+\nu_\mu\gamma$	[x,y]	$< 6.1 \times 10^{-5}$	CL=90%	215
$\pi^0 e^+\nu_e\gamma$	[x,y]	$(2.62 \pm 0.20) \times 10^{-4}$		228
$\pi^0 e^+\nu_e\gamma$(SD)	[aa]	$< 5.3 \times 10^{-5}$	CL=90%	228
$\pi^0\pi^0 e^+\nu_e\gamma$		$< 5 \times 10^{-6}$	CL=90%	206

Lepton Family number (LF) Lepton number (L) $\Delta S = \Delta Q$ (SQ) violating modes or $\Delta S = 1$ weak neutral current ($S1$) modes

$\pi^+\pi^+ e^-\overline{\nu}_e$	SQ	< 1.2	$\times 10^{-8}$	CL=90%	203
$\pi^+\pi^+\mu^-\overline{\nu}_\mu$	SQ	< 3.0	$\times 10^{-6}$	CL=95%	151
$\pi^+ e^+ e^-$	$S1$	$(2.74 \pm 0.23) \times 10^{-7}$			227
$\pi^+\mu^+\mu^-$	$S1$	$(5.0 \pm 1.0) \times 10^{-8}$			172
$\pi^+\nu\overline{\nu}$	$S1$	$(4.2\ ^{+9.7}_{-3.5}) \times 10^{-10}$			227
$\mu^- \nu e^+ e^+$	LF	< 2.0	$\times 10^{-8}$	CL=90%	236
$\mu^+\nu_e$	LF [d]	< 4	$\times 10^{-3}$	CL=90%	236
$\pi^+\mu^+ e^-$	LF	< 2.1	$\times 10^{-10}$	CL=90%	214
$\pi^+\mu^- e^+$	LF	< 7	$\times 10^{-9}$	CL=90%	214
$\pi^-\mu^+ e^+$	L	< 7	$\times 10^{-9}$	CL=90%	214
$\pi^- e^+ e^+$	L	< 1.0	$\times 10^{-8}$	CL=90%	227
$\pi^-\mu^+\mu^+$	L	[d] < 1.5	$\times 10^{-4}$	CL=90%	172
$\mu^+\overline{\nu}_e$	L	[d] < 3.3	$\times 10^{-3}$	CL=90%	236
$\pi^0 e^+\overline{\nu}_e$	L	< 3	$\times 10^{-3}$	CL=90%	228

K^0

$I(J^P) = \frac{1}{2}(0^-)$

50% K_S 50% K_L
Mass $m = 497.672 \pm 0.031$ MeV
$m_{K^0} - m_{K^\pm} = 3.995 \pm 0.034$ MeV (S = 1.1)
$|m_{K^0} - m_{\overline{K}^0}| / m_{\text{average}} < 10^{-18}$ [bb]

K^0_S

$I(J^P) = \frac{1}{2}(0^-)$

Mean life $\tau = (0.8934 \pm 0.0008) \times 10^{-10}$ s
$c\tau = 2.6762$ cm

CP-violation parameters [ac]

$\mathrm{Im}(\eta_{+-0}) = -0.002 \pm 0.008$
$\mathrm{Im}(\eta_{000})^2 < 0.1$ CL = 90%

K^0_S DECAY MODES		Fraction (Γ_j/Γ)	Scale factor/ Confidence level	p (MeV/c)
$\pi^+\pi^-$		(68.61±0.28) %	S=1.2	206
$\pi^0\pi^0$		(31.39±0.28) %	S=1.2	209
$\pi^+\pi^-\gamma$	[y,dd]	$(1.78 \pm 0.05) \times 10^{-3}$		206
$\gamma\gamma$		$(2.4 \pm 0.9) \times 10^{-6}$		249
$\pi^+\pi^-\pi^0$		$(3.4\ ^{+1.1}_{-0.9}) \times 10^{-7}$		133
$3\pi^0$		$< 3.7 \times 10^{-5}$	CL=90%	139
$\pi^\pm e^\mp\nu$	[ee]	$(6.70 \pm 0.07) \times 10^{-4}$	S=1.1	229
$\pi^\pm\mu^\mp\nu$	[ee]	$(4.69 \pm 0.06) \times 10^{-4}$	S=1.1	216
$\Delta S = 1$ weak neutral current ($S1$) modes				
$\mu^+\mu^-$	$S1$	$< 3.2 \times 10^{-7}$	CL=90%	225
$e^+ e^-$	$S1$	$< 1.4 \times 10^{-7}$	CL=90%	249
$\pi^0 e^+ e^-$	$S1$	$< 1.1 \times 10^{-6}$	CL=90%	231

K^0_L

$I(J^P) = \frac{1}{2}(0^-)$

$m_{K_L} - m_{K_S} = (0.5301 \pm 0.0014) \times 10^{10}\ \hbar\ \mathrm{s}^{-1}$
$= (3.489 \pm 0.009) \times 10^{-12}$ MeV
Mean life $\tau = (5.17 \pm 0.04) \times 10^{-8}$ s (S = 1.1)
$c\tau = 15.51$ m

Slope parameter g [v]

(See Particle Listings for quadratic coefficients)
$K^0_L \to \pi^+\pi^-\pi^0 = 0.670 \pm 0.014$ (S = 1.6)

K_L decay form factors [w]

K^0_{e3} $\lambda_+ = 0.0300 \pm 0.0016$ (S = 1.2)
$K^0_{\mu3}$ $\lambda_+ = 0.034 \pm 0.005$ (S = 2.3)
$K^0_{\mu3}$ $\lambda_0 = 0.025 \pm 0.006$ (S = 2.3)
K^0_{e3} $|f_S/f_+| < 0.04$ CL = 68%
K^0_{e3} $|f_T/f_+| < 0.23$ CL = 68%
$K^0_{\mu3}$ $|f_T/f_+| = 0.12 \pm 0.12$
$K_L \to e^+ e^-\gamma$: $\alpha_{K^*} = -0.28 \pm 0.08$

***CP*-violation parameters** [cc]

$\delta = (0.327 \pm 0.012)\%$
$|\eta_{00}| = (2.275 \pm 0.019) \times 10^{-3}$ (S = 1.1)
$|\eta_{+-}| = (2.285 \pm 0.019) \times 10^{-3}$
$|\eta_{00}/\eta_{+-}| = 0.9956 \pm 0.0023$ [ff] (S = 1.8)
$\epsilon'/\epsilon = (1.5 \pm 0.8) \times 10^{-3}$ [ff] (S = 1.8)
$\phi_{+-} = (43.5 \pm 0.6)^\circ$
$\phi_{00} = (43.4 \pm 1.0)^\circ$
$\phi_{00} - \phi_{+-} = (-0.1 \pm 0.8)^\circ$
j for $K_L^0 \to \pi^+\pi^-\pi^0 = 0.0011 \pm 0.0008$
$|\eta_{+-\gamma}| = (2.35 \pm 0.07) \times 10^{-3}$
$\phi_{+-\gamma} = (44 \pm 4)^\circ$
$|\epsilon'_{+-\gamma}|/\epsilon < 0.3$ CL = 90%

$\Delta S = -\Delta Q$ in $K^0_{\ell 3}$ decay

Re $x = 0.006 \pm 0.018$ (S = 1.3)
Im $x = -0.003 \pm 0.026$ (S = 1.2)

***CPT*-violation parameters**

Re $\Delta = 0.018 \pm 0.020$
Im $\Delta = 0.02 \pm 0.04$

K_L^0 DECAY MODES		Fraction (Γ_j/Γ)	Scale factor/ Confidence level	p (MeV/c)
$3\pi^0$		(21.12 ±0.27) %	S=1.1	139
$\pi^+\pi^-\pi^0$		(12.56 ±0.20) %	S=1.7	133
$\pi^\pm\mu^\mp\nu$ Called $K^0_{\mu 3}$.	[gg]	(27.17 ±0.25) %	S=1.1	216
$\pi^\pm e^\mp\nu_e$ Called K^0_{e3}.	[gg]	(38.78 ±0.27) %	S=1.1	229
2γ		(5.92 ±0.15) $\times 10^{-4}$		249
3γ		< 2.4 $\times 10^{-7}$	CL=90%	249
$\pi^0 2\gamma$	[hh]	(1.70 ±0.28) $\times 10^{-6}$		231
$\pi^0\pi^\pm e^\mp\nu$	[gg]	(5.18 ±0.29) $\times 10^{-5}$		207
$(\pi\mu\text{atom})\nu$		(1.06 ±0.11) $\times 10^{-7}$		–
$\pi^\pm e^\mp\nu_e\gamma$	[γgg,hh]	(3.62 $^{+0.26}_{-0.21}$) $\times 10^{-3}$		229
$\pi^+\pi^-\gamma$	[γhh]	(4.61 ±0.14) $\times 10^{-5}$		206
$\pi^0\pi^0\gamma$		< 5.6 $\times 10^{-6}$		209
Charge conjugation × Parity (*CP*, *CPV*) or Lepton Family number (*LF*) violating modes or $\Delta S = 1$ weak neutral current (*S1*) modes				
$\pi^+\pi^-$	CPV	(2.067±0.035) $\times 10^{-3}$	S=1.1	206
$\pi^0\pi^0$	CPV	(9.36 ±0.20) $\times 10^{-4}$		209
$\mu^+\mu^-$	S1	(7.2 ±0.5) $\times 10^{-9}$	S=1.4	225
$\mu^+\mu^-\gamma$	S1	(3.25 ±0.28) $\times 10^{-7}$		225
e^+e^-	S1	< 4.1 $\times 10^{-11}$	CL=90%	249
$e^+e^-\gamma$	S1	(9.1 ±0.5) $\times 10^{-6}$		249
$e^+e^-\gamma\gamma$	S1 [hh]	(6.5 ±1.2) $\times 10^{-7}$		249
$\pi^+\pi^-e^+e^-$	S1 [hh]	< 4.6 $\times 10^{-7}$	CL=90%	206
$\mu^+\mu^-e^+e^-$	S1	(2.9 $^{+6.7}_{-2.4}$) $\times 10^{-9}$		225
$e^+e^-e^+e^-$	S1	(4.1 ±0.8) $\times 10^{-8}$	S=1.2	249
$\pi^0\mu^+\mu^-$	CPTS1 [ii]	< 5.1 $\times 10^{-9}$	CL=90%	177
$\pi^0 e^+e^-$	CPTS1 [ii]	< 4.3 $\times 10^{-9}$	CL=90%	231
$\pi^0\nu\bar{\nu}$	CPTS1 [jj]	< 5.8 $\times 10^{-5}$	CL=90%	231
$e^\pm\mu^\mp$	LF [gg]	< 3.3 $\times 10^{-11}$	CL=90%	238
$e^\pm e^\pm\mu^\mp\mu^\mp$	LF [gg]	< 6.1 $\times 10^{-9}$	CL=90%	–

$K^*(892)$ $I(J^P) = \frac{1}{2}(1^-)$

$K^*(892)^\pm$ mass $m = 891.66 \pm 0.26$ MeV
$K^*(892)^0$ mass $m = 896.10 \pm 0.28$ MeV (S = 1.4)
$K^*(892)^\pm$ full width $\Gamma = 50.8 \pm 0.9$ MeV
$K^*(892)^0$ full width $\Gamma = 50.5 \pm 0.6$ MeV (S = 1.1)

$K^*(892)$ DECAY MODES	Fraction (Γ_j/Γ)	Confidence level	p (MeV/c)
$K\pi$	~ 100 %		291
$K^0\gamma$	(2.30±0.20) $\times 10^{-3}$		310
$K^\pm\gamma$	(9.9 ±0.9) $\times 10^{-4}$		309
$K\pi\pi$	< 7 $\times 10^{-4}$	95%	224

$K_1(1270)$ $I(J^P) = \frac{1}{2}(1^+)$

Mass $m = 1273 \pm 7$ MeV [m]
Full width $\Gamma = 90 \pm 20$ MeV [m]

$K_1(1270)$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$K\rho$	(42 ±6) %	76
$K_0^*(1430)\pi$	(28 ±4) %	–
$K^*(892)\pi$	(16 ±5) %	301
$K\omega$	(11.0±2.0) %	–
$Kf_0(1370)$	(3.0±2.0) %	–

$K_1(1400)$ $I(J^P) = \frac{1}{2}(1^+)$

Mass $m = 1402 \pm 7$ MeV
Full width $\Gamma = 174 \pm 13$ MeV (S = 1.6)

$K_1(1400)$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$K^*(892)\pi$	(94 ±6) %	401
$K\rho$	(3.0±3.0) %	298
$Kf_0(1370)$	(2.0±2.0) %	–
$K\omega$	(1.0±1.0) %	285
$K_0^*(1430)\pi$	not seen	–

$K^*(1410)$ $I(J^P) = \frac{1}{2}(1^-)$

Mass $m = 1414 \pm 15$ MeV (S = 1.3)
Full width $\Gamma = 232 \pm 21$ MeV (S = 1.1)

$K^*(1410)$ DECAY MODES	Fraction (Γ_j/Γ)	Confidence level	p (MeV/c)
$K^*(892)\pi$	> 40 %	95%	408
$K\pi$	(6.6±1.3) %		611
$K\rho$	< 7 %	95%	309

$K_0^*(1430)$ [kk] $I(J^P) = \frac{1}{2}(0^+)$

Mass $m = 1429 \pm 6$ MeV
Full width $\Gamma = 287 \pm 23$ MeV

$K_0^*(1430)$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$K\pi$	(93±10) %	621

$K_2^*(1430)$ $I(J^P) = \frac{1}{2}(2^+)$

$K_2^*(1430)^\pm$ mass $m = 1425.6 \pm 1.5$ MeV (S = 1.1)
$K_2^*(1430)^0$ mass $m = 1432.4 \pm 1.3$ MeV
$K_2^*(1430)^\pm$ full width $\Gamma = 98.5 \pm 2.7$ MeV (S = 1.1)
$K_2^*(1430)^0$ full width $\Gamma = 109 \pm 5$ MeV (S = 1.9)

$K_2^*(1430)$ DECAY MODES	Fraction (Γ_j/Γ)	Scale factor/ Confidence level	p (MeV/c)
$K\pi$	(49.9±1.2) %		622
$K^*(892)\pi$	(24.7±1.5) %		423
$K^*(892)\pi\pi$	(13.4±2.2) %		375
$K\rho$	(8.7±0.8) %	S=1.2	331
$K\omega$	(2.9±0.8) %		319
$K^+\gamma$	(2.4±0.5) $\times 10^{-3}$	S=1.1	627
$K\eta$	(1.5$^{+3.4}_{-1.0}$) $\times 10^{-3}$	S=1.3	492
$K\omega\pi$	< 7.2 $\times 10^{-4}$	CL=95%	110
$K^0\gamma$	< 9 $\times 10^{-4}$	CL=90%	631

$K^*(1680)$

$I(J^P) = \frac{1}{2}(1^-)$

Mass $m = 1717 \pm 27$ MeV (S = 1.4)
Full width $\Gamma = 322 \pm 110$ MeV (S = 4.2)

$K^*(1680)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$K\pi$	(38.7±2.5) %	779
$K\rho$	(31.4$^{+4.7}_{-2.1}$) %	571
$K^*(892)\pi$	(29.9$^{+2.2}_{-4.7}$) %	615

$K_2(1770)$ [l]

$I(J^P) = \frac{1}{2}(2^-)$

Mass $m = 1773 \pm 8$ MeV
Full width $\Gamma = 186 \pm 14$ MeV

$K_2(1770)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$K\pi\pi$		–
$K_2^*(1430)\pi$	dominant	287
$K^*(892)\pi$	seen	653
$Kf_2(1270)$	seen	–
$K\phi$	seen	441
$K\omega$	seen	608

$K_3^*(1780)$

$I(J^P) = \frac{1}{2}(3^-)$

Mass $m = 1776 \pm 7$ MeV (S = 1.1)
Full width $\Gamma = 159 \pm 21$ MeV (S = 1.3)

$K_3^*(1780)$ DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$K\rho$	(31 ± 9) %		612
$K^*(892)\pi$	(20 ± 5) %		651
$K\pi$	(18.8± 1.0) %		810
$K\eta$	(30 ±13) %		715
$K_2^*(1430)\pi$	< 16 %	95%	284

$K_2(1820)$ [mm]

$I(J^P) = \frac{1}{2}(2^-)$

Mass $m = 1816 \pm 13$ MeV
Full width $\Gamma = 276 \pm 35$ MeV

$K_2(1820)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$K_2^*(1430)\pi$	seen	325
$K^*(892)\pi$	seen	680
$Kf_2(1270)$	seen	186
$K\omega$	seen	638

$K_4^*(2045)$

$I(J^P) = \frac{1}{2}(4^+)$

Mass $m = 2045 \pm 9$ MeV (S = 1.1)
Full width $\Gamma = 198 \pm 30$ MeV

$K_4^*(2045)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$K\pi$	(9.9±1.2) %	958
$K^*(892)\pi\pi$	(9 ±5) %	800
$K^*(892)\pi\pi\pi$	(7 ±5) %	764
$\rho K\pi$	(5.7±3.2) %	742
$\omega K\pi$	(5.0±3.0) %	736
$\phi K\pi$	(2.8±1.4) %	591
$\phi K^*(892)$	(1.4±0.7) %	363

CHARMED MESONS ($C = \pm 1$)

$D^+ = c\bar{d}$ Γ $D^0 = c\bar{u}$ Γ $\bar{D}^0 = \bar{c}u$ Γ $D^- = \bar{c}d$ Γ similarly for D^*'s

$D^\pm$

$I(J^P) = \frac{1}{2}(0^-)$

Mass $m = 1869.3 \pm 0.5$ MeV (S = 1.1)
Mean life $\tau = (1.057 \pm 0.015) \times 10^{-12}$ s
$c\tau = 317$ μm

CP-violation decay-rate asymmetries

$A_{CP}(K^+K^-\pi^\pm) = -0.017 \pm 0.027$
$A_{CP}(K^\pm K^{*0}) = -0.02 \pm 0.05$
$A_{CP}(\phi\pi^\pm) = -0.014 \pm 0.033$
$A_{CP}(\pi^+\pi^-\pi^\pm) = -0.02 \pm 0.04$

$D^+ \to \bar{K}^*(892)^0\ell^+\nu_\ell$ form factors

$r_2 = 0.72 \pm 0.09$
$r_V = 1.85 \pm 0.12$
$\Gamma_L/\Gamma_T = 1.23 \pm 0.13$
$\Gamma_+/\Gamma_- = 0.16 \pm 0.04$

D^- modes are charge conjugates of the modes below.

D^+ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
Inclusive modes			
e^+ anything	(17.2 ±1.9) %		–
K^- anything	(24.2 ±2.8) %	S=1.4	–
$\bar{K}^0$ anything + K^0 anything	(59 ±7) %		–
K^+ anything	(5.8 ±1.4) %		–
η anything	[nn] < 13 %	CL=90%	–
Leptonic and semileptonic modes			
$\mu^+\nu_\mu$	< 7.2 $\times 10^{-4}$	CL=90%	932
$\bar{K}^0\ell^+\nu_\ell$	[oo] (6.8 ±0.8) %		868
$\bar{K}^0e^+\nu_e$	(6.7 ±0.9) %		868
$\bar{K}^0\mu^+\nu_\mu$	(7.0 $^{+3.0}_{-2.0}$) %		865
$K^-\pi^+e^+\nu_e$	(4.1 $^{+0.9}_{-0.7}$) %		863
$\bar{K}^*(892)^0e^+\nu_e$ × B($\bar{K}^{*0} \to K^-\pi^+$)	(3.2 ±0.33) %		720
$K^-\pi^+e^+\nu_e$ nonresonant	< 7 $\times 10^{-3}$	CL=90%	863
$K^-\pi^+\mu^+\nu_\mu$	(3.2 ±0.4) %	S=1.1	851
$\bar{K}^*(892)^0\mu^+\nu_\mu$ × B($\bar{K}^{*0} \to K^-\pi^+$)	(2.9 ±0.4) %		715
$K^-\pi^+\mu^+\nu_\mu$ nonresonant	(2.7 ±1.1) $\times 10^{-3}$		851
$(\bar{K}^*(892)\pi)^0e^+\nu_e$	< 1.2 %	CL=90%	714
$(\bar{K}\pi\pi)^0e^+\nu_e$ non-$\bar{K}^*(892)$	< 9 $\times 10^{-3}$	CL=90%	846
$K^-\pi^+\pi^0\mu^+\nu_\mu$	< 1.4 $\times 10^{-3}$	CL=90%	825
$\pi^0\ell^+\nu_\ell$	[pp] (3.1 ±1.5) $\times 10^{-3}$		930
Fractions of some of the following modes with resonances have already appeared above as submodes of particular charged-particle modes.			
$\bar{K}^*(892)^0\ell^+\nu_\ell$	[oo] (4.7 ±0.4) %		720
$\bar{K}^*(892)^0e^+\nu_e$	(4.8 ±0.5) %		720
$\bar{K}^*(892)^0\mu^+\nu_\mu$	(4.4 ±0.6) %	S=1.1	715
$\rho^0e^+\nu_e$	(2.2 ±0.8) $\times 10^{-3}$		776
$\rho^0\mu^+\nu_\mu$	(2.7 ±0.7) $\times 10^{-3}$		772
$\phi e^+\nu_e$	< 2.09 %	CL=90%	657
$\phi\mu^+\nu_\mu$	< 3.72 %	CL=90%	651
$\eta\ell^+\nu_\ell$	< 5 $\times 10^{-3}$	CL=90%	–
$\eta'(958)\mu^+\nu_\mu$	< 9 $\times 10^{-3}$	CL=90%	684
Hadronic modes with a $\bar{K}$ or $\bar{K}K\bar{K}$			
$\bar{K}^0\pi^+$	(2.89±0.26) %	S=1.1	862
$K^-\pi^+\pi^+$	[qq] (9.0 ±0.6) %		845
$\bar{K}^*(892)^0\pi^+$ × B($\bar{K}^{*0} \to K^-\pi^+$)	(1.27±0.13) %		712
$\bar{K}_0^*(1430)^0\pi^+$ × B($\bar{K}_0^*(1430)^0 \to K^-\pi^+$)	(2.3 ±0.3) %		368
$\bar{K}^*(1680)^0\pi^+$ × B($\bar{K}^*(1680)^0 \to K^-\pi^+$)	(3.7 ±0.8) $\times 10^{-3}$		65
$K^-\pi^+\pi^+$ nonresonant	(8.5 ±0.8) %		845
$\bar{K}^0\pi^+\pi^0$	[qq] (9.7 ±3.0) %	S=1.1	845

$\overline{K}^0\rho^+$		(6.6 ±2.5) %			680
$\overline{K}^*(892)^0\pi^+$		(6.3 ±0.4) $\times 10^{-3}$			712
× B($\overline{K}^{*0} \to \overline{K}^0\pi^0$)					
$\overline{K}^0\pi^+\pi^0$ nonresonant		(1.3 ±1.1) %			845
$K^-\pi^+\pi^+\pi^0$	[qq]	(6.4 ±1.1) %			816
$\overline{K}^*(892)^0\rho^+$ total		(1.4 ±0.9) %			423
× B($\overline{K}^{*0} \to K^-\pi^+$)					
$\overline{K}_1(1400)^0\pi^+$		(2.2 ±0.6) %			390
× B($\overline{K}_1(1400)^0 \to K^-\pi^+\pi^0$)					
$K^-\rho^+\pi^+$ total		(3.1 ±1.1) %			616
$K^-\rho^+\pi^+$ 3-body		(1.1 ±0.4) %			616
$\overline{K}^*(892)^0\pi^+\pi^0$ total		(4.5 ±0.9) %			687
× B($\overline{K}^{*0} \to K^-\pi^+$)					
$\overline{K}^*(892)^0\pi^+\pi^0$ 3-body		(2.8 ±0.9) %			687
× B($\overline{K}^{*0} \to K^-\pi^+$)					
$K^*(892)^-\pi^+\pi^+$ 3-body		(7 ±3) $\times 10^{-3}$			688
× B($K^{*-} \to K^-\pi^0$)					
$K^-\pi^+\pi^+\pi^0$ nonresonant	[rr]	(1.2 ±0.6) %			816
$\overline{K}^0\pi^+\pi^+\pi^-$	[qq]	(7.0 ±0.9) %			814
$\overline{K}^0a_1(1260)^+$		(4.0 ±0.9) %			328
× B($a_1(1260)^+ \to \pi^+\pi^+\pi^-$)					
$\overline{K}_1(1400)^0\pi^+$		(2.2 ±0.6) %			390
× B($\overline{K}_1(1400)^0 \to \overline{K}^0\pi^+\pi^-$)					
$K^*(892)^-\pi^+\pi^+$ 3-body		(1.4 ±0.6) %			688
× B($K^{*-} \to \overline{K}^0\pi^-$)					
$\overline{K}^0\rho^0\pi^+$ total		(4.2 ±0.9) %			614
$\overline{K}^0\rho^0\pi^+$ 3-body		(5 ±5) $\times 10^{-3}$			614
$\overline{K}^0\pi^+\pi^+\pi^-$ nonresonant		(8 ±4) $\times 10^{-3}$			814
$K^-\pi^+\pi^+\pi^-$	[qq]	(7.2 ±1.0) $\times 10^{-3}$			772
$\overline{K}^*(892)^0\pi^+\pi^+\pi^-$		(5.4 ±2.3) $\times 10^{-3}$			642
× B($\overline{K}^{*0} \to K^-\pi^+$)					
$\overline{K}^*(892)^0\rho^0\pi^+$		(1.9 $^{+1.1}_{-1.0}$) $\times 10^{-3}$			242
× B($\overline{K}^{*0} \to K^-\pi^+$)					
$\overline{K}^*(892)^0\pi^+\pi^+\pi^-$ no-ρ		(2.9 ±1.1) $\times 10^{-3}$			642
× B($\overline{K}^{*0} \to K^-\pi^+$)					
$K^-\rho^0\pi^+\pi^+$		(3.1 ±0.9) $\times 10^{-3}$			529
$K^-\pi^+\pi^+\pi^+\pi^-$ nonresonant		< 2.3 $\times 10^{-3}$		CL=90%	772
$K^-\pi^+\pi^+\pi^0\pi^0$		(2.2 $^{+5.0}_{-0.9}$) %			775
$\overline{K}^0\pi^+\pi^+\pi^-\pi^0$		(5.4 $^{+3.0}_{-1.4}$) %			773
$\overline{K}^0\pi^+\pi^+\pi^+\pi^-\pi^-$		(8 ±7) $\times 10^{-4}$			714
$K^-\pi^+\pi^+\pi^+\pi^-\pi^0$		(2.0 ±1.8) $\times 10^{-3}$			718
$\overline{K}^0K^0K^+$		(1.8 ±0.8) %			545

Fractions of some of the following modes with resonances have already appeared above as submodes of particular charged-particle modes.

$\overline{K}^0\rho^+$		(6.6 ±2.5) %			680
$\overline{K}^0a_1(1260)^+$		(8.0 ±1.7) %			328
$\overline{K}^0a_2(1320)^+$		< 3 $\times 10^{-3}$		CL=90%	199
$\overline{K}^*(892)^0\pi^+$		(1.90±0.19) %			712
$\overline{K}^*(892)^0\rho^+$ total	[rr]	(2.1 ±1.3) %			423
$\overline{K}^*(892)^0\rho^+$ S-wave	[rr]	(1.6 ±1.6) %			423
$\overline{K}^*(892)^0\rho^+$ P-wave		< 1 $\times 10^{-3}$		CL=90%	423
$\overline{K}^*(892)^0\rho^+$ D-wave		(10 ±7) $\times 10^{-3}$			423
$\overline{K}^*(892)^0\rho^+$ D-wave longitudinal		< 7 $\times 10^{-3}$		CL=90%	423
$\overline{K}_1(1270)^0\pi^+$		< 7 $\times 10^{-3}$		CL=90%	487
$\overline{K}_1(1400)^0\pi^+$		(4.9 ±1.2) %			390
$\overline{K}^*(1410)^0\pi^+$		< 7 $\times 10^{-3}$		CL=90%	382
$\overline{K}_0^*(1430)^0\pi^+$		(3.7 ±0.4) %			368
$\overline{K}^*(1680)^0\pi^+$		(1.43±0.30) %			65
$\overline{K}^*(892)^0\pi^+\pi^0$ total		(6.7 ±1.4) %			687
$\overline{K}^*(892)^0\pi^+\pi^0$ 3-body	[rr]	(4.2 ±1.4) %			687
$K^*(892)^-\pi^+\pi^+$ 3-body		(2.0 ±0.9) %			688
$K^-\rho^+\pi^+$ total		(3.1 ±1.1) %			616
$K^-\rho^+\pi^+$ 3-body		(1.1 ±0.4) %			616
$\overline{K}^0\rho^0\pi^+$ total		(4.2 ±0.9) %		CL=90%	614
$\overline{K}^0\rho^0\pi^+$ 3-body		(5 ±5) $\times 10^{-3}$			614
$\overline{K}^0f_0(980)\pi^+$		< 5 $\times 10^{-3}$		CL=90%	461
$\overline{K}^*(892)^0\pi^+\pi^+\pi^-$		(8.1 ±3.4) $\times 10^{-3}$		S=1.7	642
$\overline{K}^*(892)^0\rho^0\pi^+$		(2.9 $^{+1.7}_{-1.5}$) $\times 10^{-3}$		S=1.8	242
$\overline{K}^*(892)^0\pi^+\pi^+\pi^-$ no-ρ		(4.3 ±1.7) $\times 10^{-3}$			642
$K^-\rho^0\pi^+\pi^+$		(3.1 ±0.9) $\times 10^{-3}$			529

Pionic modes

$\pi^+\pi^0$	(2.5 ±0.7) $\times 10^{-3}$			925
$\pi^+\pi^+\pi^-$	(3.6 ±0.4) $\times 10^{-3}$			908
$\rho^0\pi^+$	(1.05±0.31) $\times 10^{-3}$			769
$\pi^+\pi^+\pi^-$ nonresonant	(2.2 ±0.4) $\times 10^{-3}$			908
$\pi^+\pi^+\pi^-\pi^0$	(1.9 $^{+1.5}_{-1.2}$) %			882
$\eta\pi^+$ × B($\eta \to \pi^+\pi^-\pi^0$)	(1.7 ±0.6) $\times 10^{-3}$			848
$\omega\pi^+$ × B($\omega \to \pi^+\pi^-\pi^0$)	< 6 $\times 10^{-3}$		CL=90%	764
$\pi^+\pi^+\pi^+\pi^-\pi^-$	(2.1 ±0.4) $\times 10^{-3}$			845
$\pi^+\pi^+\pi^+\pi^-\pi^-\pi^0$	(2.9 $^{+2.9}_{-2.0}$) $\times 10^{-3}$			799

Fractions of some of the following modes with resonances have already appeared above as submodes of particular charged-particle modes.

$\eta\pi^+$	(7.5 ±2.5) $\times 10^{-3}$			848
$\rho^0\pi^+$	(1.05±0.31) $\times 10^{-3}$			769
$\omega\pi^+$	< 7 $\times 10^{-3}$		CL=90%	764
$\eta\rho^+$	< 1.2 %		CL=90%	658
$\eta'(958)\pi^+$	< 9 $\times 10^{-3}$		CL=90%	680
$\eta'(958)\rho^+$	< 1.5 %		CL=90%	355

Hadronic modes with a $K\overline{K}$ pair

$K^+\overline{K}^0$		(7.4 ±1.0) $\times 10^{-3}$			792
$K^+K^-\pi^+$	[qq]	(8.8 ±0.8) $\times 10^{-3}$			744
$\phi\pi^+$ × B($\phi \to K^+K^-$)		(3.0 ±0.3) $\times 10^{-3}$			647
$K^+\overline{K}^*(892)^0$		(2.8 ±0.4) $\times 10^{-3}$			610
× B($\overline{K}^{*0} \to K^-\pi^+$)					
$K^+K^-\pi^+$ nonresonant		(4.5 ±0.9) $\times 10^{-3}$			744
$K^0\overline{K}^0\pi^+$		—			741
$K^*(892)^+\overline{K}^0$		(2.1 ±1.0) %			611
× B($K^{*+} \to K^0\pi^+$)					
$K^+K^-\pi^+\pi^0$		—			682
$\phi\pi^+\pi^0$ × B($\phi \to K^+K^-$)		(1.1 ±0.5) %			619
$\phi\rho^+$ × B($\phi \to K^+K^-$)		< 7 $\times 10^{-3}$		CL=90%	268
$K^+K^-\pi^+\pi^0$ non-ϕ		(1.5 $^{+0.7}_{-0.6}$) %			682
$K^+\overline{K}^0\pi^+\pi^-$		< 2 %		CL=90%	678
$K^0K^-\pi^+\pi^+$		(1.0 ±0.6) %			678
$K^*(892)^+\overline{K}^*(892)^0$		(1.2 ±0.5) %			273
× B^2($K^{*+} \to K^0\pi^+$)					
$K^0K^-\pi^+\pi^+$ non-$K^{*+}\overline{K}^{*0}$		< 7.9 $\times 10^{-3}$		CL=90%	678
$K^+K^-\pi^+\pi^+\pi^-$		—			600
$\phi\pi^+\pi^+\pi^-$		< 1 $\times 10^{-3}$		CL=90%	565
× B($\phi \to K^+K^-$)					
$K^+K^-\pi^+\pi^+\pi^-$ nonresonant		< 3 %		CL=90%	600

Fractions of the following modes with resonances have already appeared above as submodes of particular charged-particle modes.

$\phi\pi^+$	(6.1 ±0.6) $\times 10^{-3}$			647
$\phi\pi^+\pi^0$	(2.3 ±1.0) %			619
$\phi\rho^+$	< 1.4 %		CL=90%	268
$\phi\pi^+\pi^-$	< 2 $\times 10^{-3}$		CL=90%	565
$K^+\overline{K}^*(892)^0$	(4.2 ±0.5) $\times 10^{-3}$			610
$K^*(892)^+\overline{K}^0$	(3.2 ±1.5) %			611
$K^*(892)^+\overline{K}^*(892)^0$	(2.6 ±1.1) %			273

Doubly Cabibbo suppressed (DC) modes, $\Delta C = 1$ weak neutral current ($C1$) modes, or Lepton Family number (LF) or Lepton number (L) violating modes

$K^+\pi^+\pi^-$	DC	(6.8 ±1.5) $\times 10^{-4}$			845
$K^+\rho^0$	DC	(2.5 ±1.2) $\times 10^{-4}$			681
$K^*(892)^0\pi^+$	DC	(3.6 ±1.6) $\times 10^{-4}$			712
$K^+\pi^+\pi^-$ nonresonant	DC	(2.4 ±1.2) $\times 10^{-4}$			845
$K^+K^+K^-$	DC	< 1.4 $\times 10^{-4}$		CL=90%	550
ϕK^+	DC	< 1.3 $\times 10^{-4}$		CL=90%	527
$\pi^+e^+e^-$	$C1$	< 6.6 $\times 10^{-5}$		CL=90%	929
$\pi^+\mu^+\mu^-$	$C1$	< 1.8 $\times 10^{-5}$		CL=90%	917
$\rho^+\mu^+\mu^-$	$C1$	< 5.6 $\times 10^{-4}$		CL=90%	759
$K^+e^+e^-$	[ss]	< 2.0 $\times 10^{-4}$		CL=90%	869
$K^+\mu^+\mu^-$	[ss]	< 9.7 $\times 10^{-5}$		CL=90%	856
$\pi^+e^+\mu^-$	LF	< 1.1 $\times 10^{-4}$		CL=90%	926
$\pi^+e^-\mu^+$	LF	< 1.3 $\times 10^{-4}$		CL=90%	926
$K^+e^+\mu^-$	LF	< 1.3 $\times 10^{-4}$		CL=90%	866

$K^+e^-\mu^+$	*LF*	< 1.2	$\times 10^{-4}$	CL=90%	866
$\pi^-e^+e^+$	*L*	< 1.1	$\times 10^{-4}$	CL=90%	929
$\pi^-\mu^+\mu^+$	*L*	< 8.7	$\times 10^{-5}$	CL=90%	917
$\pi^-e^+\mu^+$	*L*	< 1.1	$\times 10^{-4}$	CL=90%	926
$\rho^-\mu^+\mu^+$	*L*	< 5.6	$\times 10^{-4}$	CL=90%	759
$K^-e^+e^+$	*L*	< 1.2	$\times 10^{-4}$	CL=90%	869
$K^-\mu^+\mu^+$	*L*	< 1.2	$\times 10^{-4}$	CL=90%	856
$K^-e^+\mu^+$	*L*	< 1.3	$\times 10^{-4}$	CL=90%	866
$K^*(892)^-\mu^+\mu^+$	*L*	< 8.5	$\times 10^{-4}$	CL=90%	703

D^0

$I(J^P) = \frac{1}{2}(0^-)$

Mass $m = 1864.6 \pm 0.5$ MeV (S = 1.1)
$m_{D^\pm} - m_{D^0} = 4.76 \pm 0.10$ MeV (S = 1.1)
Mean life $\tau = (0.415 \pm 0.004) \times 10^{-12}$ s
$c\tau = 124.4\ \mu$m
$|m_{D_1^0} - m_{D_2^0}| < 24 \times 10^{10}\ \hbar\ \mathrm{s}^{-1}$ CL = 90% [tt]
$|\Gamma_{D_1^0} - \Gamma_{D_2^0}|/\Gamma_{D^0} < 0.20$ CL = 90% [tt]
$\Gamma(K^+\ell^-\overline{\nu}_\ell$ (via $\overline{D}^0$))/$\Gamma(K^-\ell^+\nu_\ell) < 0.005$ CL = 90%
$\frac{\Gamma(K^-\pi^-\text{or}K^-\pi^-\pi^-\pi^-(\text{via}\overline{D}^0))}{\Gamma(K^-\pi^-\text{or}K^-\pi^-\pi^-\pi^-)} < 0.0085$ (or < 0.0037) CL = 90% [uu]

CP-violation decay-rate asymmetries

$A_{CP}(K^+K^-) = 0.026 \pm 0.035$
$A_{CP}(\pi^+\pi^-) = -0.05 \pm 0.08$
$A_{CP}(K^0_S\phi) = -0.03 \pm 0.09$
$A_{CP}(K^0_S\pi^0) = -0.018 \pm 0.030$

$\overline{D}^0$ modes are charge conjugates of the modes below.

D^0 DECAY MODES		Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
Inclusive modes				
e^+anything		(6.75±0.29) %		–
μ^+anything		(6.6 ±0.8) %		–
K^-anything		(53 ±4) %	S=1.3	–
$\overline{K}^0$anything + K^0anything		(42 ±5) %		–
K^+anything		(3.4 $^{+0.6}_{-0.4}$) %		–
η anything	[nn]	< 13 %	CL=90%	–
Semileptonic modes				
$K^-\ell^+\nu_\ell$	[oo]	(3.50±0.17) %	S=1.3	867
$K^-e^+\nu_e$		(3.66±0.18) %		867
$K^-\mu^+\nu_\mu$		(3.23±0.17) %		863
$K^-\pi^0e^+\nu_e$		(1.6 $^{+1.3}_{-0.5}$) %		861
$\overline{K}^0\pi^-e^+\nu_e$		(2.8 $^{+1.7}_{-0.9}$) %		860
$\overline{K}^*(892)^-e^+\nu_e$ × B($K^{*-} \to \overline{K}^0\pi^-$)		(1.35±0.22) %		719
$K^*(892)^-\ell^+\nu_\ell$		—		–
$\overline{K}^*(892)^0\pi^-e^+\nu_e$		—		708
$K^-\pi^+\pi^-\mu^+\nu_\mu$		< 1.2 $\times 10^{-3}$	CL=90%	821
$(\overline{K}^*(892)\pi)^-\mu^+\nu_\mu$		< 1.4 $\times 10^{-3}$	CL=90%	693
$\pi^-e^+\nu_e$		(3.7 ±0.6) $\times 10^{-3}$		927

A fraction of the following resonance mode has already appeared above as a submode of a charged-particle mode.

$K^*(892)^-e^+\nu_e$		(2.02±0.33) %		719
Hadronic modes with a $\overline{K}$ or $\overline{K}K\overline{K}$				
$K^-\pi^+$		(3.85±0.09) %		861
$\overline{K}^0\pi^0$		(2.12±0.21) %	S=1.1	860
$\overline{K}^0\pi^+\pi^-$	[qq]	(5.4 ±0.4) %	S=1.2	842
$\overline{K}^0\rho^0$		(1.21±0.17) %		676
$\overline{K}^0f_0(980)$ × B($f_0 \to \pi^+\pi^-$)		(3.0 ±0.8) $\times 10^{-3}$		549
$\overline{K}^0f_2(1270)$ × B($f_2 \to \pi^+\pi^-$)		(2.4 ±0.9) $\times 10^{-3}$		263
$\overline{K}^0f_0(1370)$ × B($f_0 \to \pi^+\pi^-$)		(4.3 ±1.3) $\times 10^{-3}$		–
$K^*(892)^-\pi^+$ × B($K^{*-} \to \overline{K}^0\pi^-$)		(3.4 ±0.3) %		711
$K_0^*(1430)^-\pi^+$ × B($K_0^*(1430)^- \to \overline{K}^0\pi^-$)		(6.4 ±1.6) $\times 10^{-3}$		364
$\overline{K}^0\pi^+\pi^-$ nonresonant		(1.47±0.24) %		842
$K^-\pi^+\pi^0$	[qq]	(13.9 ±0.9) %	S=1.3	844
$K^-\rho^+$		(10.8 ±1.0) %		678
$K^*(892)^-\pi^+$ × B($K^{*-} \to K^-\pi^0$)		(1.7 ±0.2) %		711
$\overline{K}^*(892)^0\pi^0$ × B($\overline{K}^{*0} \to K^-\pi^+$)		(2.1 ±0.3) %		709
$K^-\pi^+\pi^0$ nonresonant		(6.9 ±2.5) $\times 10^{-3}$		844
$\overline{K}^0\pi^0\pi^0$		—		843
$\overline{K}^*(892)^0\pi^0$ × B($\overline{K}^{*0} \to \overline{K}^0\pi^0$)		(1.1 ±0.2) %		709
$\overline{K}^0\pi^0\pi^0$ nonresonant		(7.9 ±2.1) $\times 10^{-3}$		843
$K^-\pi^+\pi^+\pi^-$	[qq]	(7.6 ±0.4) %	S=1.1	812
$K^-\pi^+\rho^0$ total		(6.3 ±0.4) %		612
$K^-\pi^+\rho^0$ 3-body		(4.8 ±2.1) $\times 10^{-3}$		612
$\overline{K}^*(892)^0\rho^0$ × B($\overline{K}^{*0} \to K^-\pi^+$)		(9.8 ±2.2) $\times 10^{-3}$		418
$K^-a_1(1260)^+$ × B($a_1(1260)^+ \to \pi^+\pi^+\pi^-$)		(3.6 ±0.6) %		327
$\overline{K}^*(892)^0\pi^+\pi^-$ total		(1.5 ±0.4) %		683
$\overline{K}^*(892)^0\pi^+\pi^-$ 3-body × B($\overline{K}^{*0} \to K^-\pi^+$)		(9.5 ±2.1) $\times 10^{-3}$		683
$K_1(1270)^-\pi^+$ × B($K_1(1270)^- \to K^-\pi^+\pi^-$)	[rr]	(3.6 ±1.0) $\times 10^{-3}$		483
$K^-\pi^+\pi^+\pi^-$ nonresonant		(1.76±0.25) %		812
$\overline{K}^0\pi^+\pi^-\pi^0$	[qq]	(10.0 ±1.2) %		812
$\overline{K}^0\eta \times$ B($\eta \to \pi^+\pi^-\pi^0$)		(1.6 ±0.3) $\times 10^{-3}$		772
$\overline{K}^0\omega \times$ B($\omega \to \pi^+\pi^-\pi^0$)		(1.9 ±0.4) %		670
$K^*(892)^-\rho^+$ × B($K^{*-} \to \overline{K}^0\pi^-$)		(4.1 ±1.6) %		422
$\overline{K}^*(892)^0\rho^0$ × B($\overline{K}^{*0} \to \overline{K}^0\pi^0$)		(4.9 ±1.1) $\times 10^{-3}$		418
$K_1(1270)^-\pi^+$ × B($K_1(1270)^- \to \overline{K}^0\pi^-\pi^0$)	[rr]	(5.1 ±1.4) $\times 10^{-3}$		483
$\overline{K}^*(892)^0\pi^+\pi^-$ 3-body × B($\overline{K}^{*0} \to \overline{K}^0\pi^0$)		(4.8 ±1.1) $\times 10^{-3}$		683
$\overline{K}^0\pi^+\pi^-\pi^0$ nonresonant		(2.1 ±2.1) %		812
$K^-\pi^+\pi^0\pi^0$		(15 ±5) %		815
$K^-\pi^+\pi^+\pi^-\pi^0$		(4.1 ±0.4) %		771
$\overline{K}^*(892)^0\pi^+\pi^-\pi^0$ × B($\overline{K}^{*0} \to K^-\pi^+$)		(1.2 ±0.6) %		641
$\overline{K}^*(892)^0\eta$ × B($\overline{K}^{*0} \to K^-\pi^+$) × B($\eta \to \pi^+\pi^-\pi^0$)		(2.9 ±0.8) $\times 10^{-3}$		580
$K^-\pi^+\omega \times$ B($\omega \to \pi^+\pi^-\pi^0$)		(2.7 ±0.5) %		605
$\overline{K}^*(892)^0\omega$ × B($\overline{K}^{*0} \to K^-\pi^+$) × B($\omega \to \pi^+\pi^-\pi^0$)		(7 ±3) $\times 10^{-3}$		406
$\overline{K}^0\pi^+\pi^+\pi^-\pi^-$		(5.8 ±1.6) $\times 10^{-3}$		768
$\overline{K}^0\pi^+\pi^-\pi^0\pi^0(\pi^0)$		(10.6 $^{+7.3}_{-3.0}$) %		771
$\overline{K}^0K^+K^-$		(9.4 ±1.0) $\times 10^{-3}$		544
$\overline{K}^0\phi \times$ B($\phi \to K^+K^-$)		(4.3 ±0.5) $\times 10^{-3}$		520
$\overline{K}^0K^+K^-$ non-ϕ		(5.1 ±0.8) $\times 10^{-3}$		544
$K^0_SK^0_SK^0_S$		(8.4 ±1.5) $\times 10^{-4}$		538
$K^+K^-K^-\pi^+$		(2.1 ±0.5) $\times 10^{-4}$		434
$K^+K^-\overline{K}^0\pi^0$		(7.2 $^{+4.8}_{-3.5}$) $\times 10^{-3}$		435

Fractions of many of the following modes with resonances have already appeared above as submodes of particular charged-particle modes. (Modes for which there are only upper limits and $\overline{K}^*(892)\rho$ submodes only appear below.)

$\overline{K}^0\eta$		(7.1 ±1.0) $\times 10^{-3}$		772
$\overline{K}^0\rho^0$		(1.21±0.17) %		676
$K^-\rho^+$		(10.8 ±1.0) %	S=1.2	678
$\overline{K}^0\omega$		(2.1 ±0.4) %		670
$\overline{K}^0\eta'(958)$		(1.72±0.26) %		565
$\overline{K}^0f_0(980)$		(5.7 ±1.6) $\times 10^{-3}$		549
$\overline{K}^0\phi$		(8.6 ±1.0) $\times 10^{-3}$		520
$K^-a_1(1260)^+$		(7.3 ±1.1) %		327
$\overline{K}^0a_1(1260)^0$		< 1.9 %	CL=90%	322
$\overline{K}^0f_2(1270)$		(4.2 ±1.5) $\times 10^{-3}$		263
$K^-a_2(1320)^+$		< 2 $\times 10^{-3}$	CL=90%	197
$\overline{K}^0f_0(1370)$		(7.0 ±2.1) $\times 10^{-3}$		–
$K^*(892)^-\pi^+$		(5.1 ±0.4) %	S=1.2	711
$\overline{K}^*(892)^0\pi^0$		(3.2 ±0.4) %		709
$\overline{K}^*(892)^0\pi^+\pi^-$ total		(2.3 ±0.5) %		683
$\overline{K}^*(892)^0\pi^+\pi^-$ 3-body		(1.43±0.32) %		683

$K^-\pi^+\rho^0$ total		(6.3 ±0.4) %			612
$K^-\pi^+\rho^0$ 3-body		(4.8 ±2.1) $\times 10^{-3}$			612
$\overline{K}^*(892)^0\rho^0$		(1.47±0.33) %			418
$\overline{K}^*(892)^0\rho^0$ transverse		(1.5 ±0.5) %			418
$\overline{K}^*(892)^0\rho^0$ S-wave		(2.8 ±0.6) %			418
$\overline{K}^*(892)^0\rho^0$ S-wave long.		< 3	$\times 10^{-3}$	CL=90%	418
$\overline{K}^*(892)^0\rho^0$ P-wave		< 3	$\times 10^{-3}$	CL=90%	418
$\overline{K}^*(892)^0\rho^0$ D-wave		(1.9 ±0.6) %			418
$K^*(892)^-\rho^+$		(6.1 ±2.4) %			422
$K^*(892)^-\rho^+$ longitudinal		(2.9 ±1.2) %			422
$K^*(892)^-\rho^+$ transverse		(3.2 ±1.8) %			422
$K^*(892)^-\rho^+$ P-wave		< 1.5	%	CL=90%	422
$K^-\pi^+ f_0(980)$		< 1.1	%	CL=90%	459
$\overline{K}^*(892)^0 f_0(980)$		< 7	$\times 10^{-3}$	CL=90%	–
$K_1(1270)^-\pi^+$	[rr]	(1.06±0.29) %			483
$K_1(1400)^-\pi^+$		< 1.2	%	CL=90%	386
$\overline{K}_1(1400)^0\pi^0$		< 3.7	%	CL=90%	387
$K^*(1410)^-\pi^+$		< 1.2	%	CL=90%	378
$K_0^*(1430)^-\pi^+$		(1.04±0.26) %			364
$K_2^*(1430)^-\pi^+$		< 8	$\times 10^{-3}$	CL=90%	367
$\overline{K}_2^*(1430)^0\pi^0$		< 4	$\times 10^{-3}$	CL=90%	363
$\overline{K}^*(892)^0\pi^+\pi^-\pi^0$		(1.8 ±0.9) %			641
$\overline{K}^*(892)^0\eta$		(1.9 ±0.5) %			580
$K^-\pi^+\omega$		(3.0 ±0.6) %			605
$\overline{K}^*(892)^0\omega$		(1.1 ±0.5) %			406
$K^-\pi^+\eta'(958)$		(7.0 ±1.8) $\times 10^{-3}$			479
$\overline{K}^*(892)^0\eta'(958)$		< 1.1	$\times 10^{-3}$	CL=90%	99

Pionic modes

$\pi^+\pi^-$		(1.53±0.09) $\times 10^{-3}$			922
$\pi^0\pi^0$		(8.5 ±2.2) $\times 10^{-4}$			922
$\pi^+\pi^-\pi^0$		(1.6 ±1.1) %		S=2.7	907
$\pi^+\pi^+\pi^-\pi^-$		(7.4 ±0.6) $\times 10^{-3}$			879
$\pi^+\pi^+\pi^-\pi^-\pi^0$		(1.9 ±0.4) %			844
$\pi^+\pi^+\pi^+\pi^-\pi^-\pi^-$		(4.0 ±3.0) $\times 10^{-4}$			795

Hadronic modes with a $K\overline{K}$ pair

K^+K^-		(4.27±0.16) $\times 10^{-3}$			791
$K^0\overline{K}^0$		(6.5 ±1.8) $\times 10^{-4}$		S=1.2	788
$K^0K^-\pi^+$		(6.4 ±1.0) $\times 10^{-3}$		S=1.1	739
$\overline{K}^*(892)^0K^0$		< 1.1	$\times 10^{-3}$	CL=90%	605
× B($\overline{K}^{*0}\to K^-\pi^+$)					
$K^*(892)^+K^-$		(2.3 ±0.5) $\times 10^{-3}$			610
× B($K^{*+}\to K^0\pi^+$)					
$K^0K^-\pi^+$ nonresonant		(2.3 ±2.3) $\times 10^{-3}$			739
$\overline{K}^0K^+\pi^-$		(5.0 ±1.0) $\times 10^{-3}$			739
$K^*(892)^0\overline{K}^0$		< 5	$\times 10^{-4}$	CL=90%	605
× B($K^{*0}\to K^+\pi^-$)					
$K^*(892)^-K^+$		(1.2 ±0.7) $\times 10^{-3}$			610
× B($K^{*-}\to \overline{K}^0\pi^-$)					
$\overline{K}^0K^+\pi^-$ nonresonant		(3.9 $^{+2.3}_{-1.9}$) $\times 10^{-3}$			739
$K^+K^-\pi^0$		(1.3 ±0.4) $\times 10^{-3}$			742
$K_S^0K_S^0\pi^0$		< 5.9	$\times 10^{-4}$		739
$K^+K^-\pi^+\pi^-$	[w]	(2.52±0.24) $\times 10^{-3}$			676
$\phi\pi^+\pi^-$ × B($\phi\to K^+K^-$)		(5.3 ±1.4) $\times 10^{-4}$			614
$\phi\rho^0$ × B($\phi\to K^+K^-$)		(3.0 ±1.6) $\times 10^{-4}$			260
$K^+K^-\rho^0$ 3-body		(9.1 ±2.3) $\times 10^{-4}$			309
$K^*(892)^0K^-\pi^+$+c.c.	[ww]	< 5	$\times 10^{-4}$		528
× B($K^{*0}\to K^+\pi^-$)					
$K^*(892)^0\overline{K}^*(892)^0$		(6 ±2) $\times 10^{-4}$			257
× $B^2(K^{*0}\to K^+\pi^-)$					
$K^+K^-\pi^+\pi^-$ non-ϕ		—			676
$K^+K^-\pi^+\pi^-$ nonresonant		< 8	$\times 10^{-4}$	CL=90%	676
$K^0\overline{K}^0\pi^+\pi^-$		(6.9 ±2.7) $\times 10^{-3}$			673
$K^+K^-\pi^+\pi^-\pi^0$		(3.1 ±2.0) $\times 10^{-3}$			600

Fractions of most of the following modes with resonances have already appeared above as submodes of particular charged-particle modes.

$\overline{K}^*(892)^0K^0$		< 1.6	$\times 10^{-3}$	CL=90%	605
$K^*(892)^+K^-$		(3.5 ±0.8) $\times 10^{-3}$			610
$K^*(892)^0\overline{K}^0$		< 8	$\times 10^{-4}$	CL=90%	605
$K^*(892)^-K^+$		(1.8 ±1.0) $\times 10^{-3}$			610
$\phi\pi^0$		< 1.4	$\times 10^{-3}$	CL=90%	644
$\phi\eta$		< 2.8	$\times 10^{-3}$	CL=90%	489
$\phi\omega$		< 2.1	$\times 10^{-3}$	CL=90%	239
$\phi\pi^+\pi^-$		(1.08±0.29) $\times 10^{-3}$			614
$\phi\rho^0$		(6 ±3) $\times 10^{-4}$			260
$\phi\pi^+\pi^-$ 3-body		(7 ±5) $\times 10^{-4}$			614
$K^*(892)^0K^-\pi^+$ + c.c.	[ww]	< 8	$\times 10^{-4}$	CL=90%	–
$K^*(892)^0\overline{K}^*(892)^0$		(1.4 ±0.5) $\times 10^{-3}$			257

Doubly Cabibbo suppressed (DC) modes or $\Delta C = 2$ forbidden via mixing ($C2M$) modes or $\Delta C = 1$ weak neutral current ($C1$) modes or Lepton Family number (LF) violating modes

$K^+\ell^-\overline{\nu}_\ell$(via $\overline{D}^0$)	$C2M$	< 1.7	$\times 10^{-4}$	CL=90%	–
$K^+\pi^-$ or	$C2M$	< 1.0	$\times 10^{-3}$	CL=90%	–
$K^+\pi^-\pi^+\pi^-$ (via $\overline{D}^0$)					
$K^+\pi^-$	DC	(2.8 ±0.9) $\times 10^{-4}$			861
$K^+\pi^-$ (via $\overline{D}^0$)		< 1.9	$\times 10^{-4}$	CL=90%	861
$K^+\pi^-\pi^+\pi^-$	DC	(1.9 ±2.7) $\times 10^{-4}$			812
$K^+\pi^-\pi^+\pi^-$ (via $\overline{D}^0$)		< 4	$\times 10^{-4}$	CL=90%	812
μ^- anything (via $\overline{D}^0$)		< 4	$\times 10^{-4}$	CL=90%	–
e^+e^-	$C1$	< 1.3	$\times 10^{-5}$	CL=90%	932
$\mu^+\mu^-$	$C1$	< 4.1	$\times 10^{-6}$	CL=90%	926
$\pi^0e^+e^-$	$C1$	< 4.5	$\times 10^{-5}$	CL=90%	927
$\pi^0\mu^+\mu^-$	$C1$	< 1.8	$\times 10^{-4}$	CL=90%	915
ηe^+e^-	$C1$	< 1.1	$\times 10^{-4}$	CL=90%	852
$\eta\mu^+\mu^-$	$C1$	< 5.3	$\times 10^{-4}$	CL=90%	838
$\rho^0e^+e^-$	$C1$	< 1.0	$\times 10^{-4}$	CL=90%	773
$\rho^0\mu^+\mu^-$	$C1$	< 2.3	$\times 10^{-4}$	CL=90%	756
ωe^+e^-	$C1$	< 1.8	$\times 10^{-4}$	CL=90%	768
$\omega\mu^+\mu^-$	$C1$	< 8.3	$\times 10^{-4}$	CL=90%	751
ϕe^+e^-	$C1$	< 5.2	$\times 10^{-5}$	CL=90%	654
$\phi\mu^+\mu^-$	$C1$	< 4.1	$\times 10^{-4}$	CL=90%	631
$\overline{K}^0e^+e^-$	[ss]	< 1.1	$\times 10^{-4}$	CL=90%	866
$\overline{K}^0\mu^+\mu^-$	[ss]	< 2.6	$\times 10^{-4}$	CL=90%	852
$\overline{K}^*(892)^0e^+e^-$	[ss]	< 1.4	$\times 10^{-4}$	CL=90%	717
$\overline{K}^*(892)^0\mu^+\mu^-$	[ss]	< 1.18	$\times 10^{-3}$	CL=90%	698
$\pi^+\pi^-\pi^0\mu^+\mu^-$	$C1$	< 8.1	$\times 10^{-4}$	CL=90%	863
$\mu^\pm e^\mp$	LF	[gg] < 1.9	$\times 10^{-5}$	CL=90%	929
$\pi^0e^\pm\mu^\mp$	LF	[gg] < 8.6	$\times 10^{-5}$	CL=90%	924
$\eta e^\pm\mu^\mp$	LF	[gg] < 1.0	$\times 10^{-4}$	CL=90%	848
$\rho^0e^\pm\mu^\mp$	LF	[gg] < 4.9	$\times 10^{-5}$	CL=90%	769
$\omega e^\pm\mu^\mp$	LF	[gg] < 1.2	$\times 10^{-4}$	CL=90%	764
$\phi e^\pm\mu^\mp$	LF	[gg] < 3.4	$\times 10^{-5}$	CL=90%	648
$\overline{K}^0e^\pm\mu^\mp$	LF	[gg] < 1.0	$\times 10^{-4}$	CL=90%	862
$\overline{K}^*(892)^0e^\pm\mu^\mp$	LF	[gg] < 1.0	$\times 10^{-4}$	CL=90%	712

$D^*(2007)^0$

$I(J^P) = \frac{1}{2}(1^-)$
I, J, P need confirmation.

Mass $m = 2006.7 \pm 0.5$ MeV (S = 1.1)
$m_{D^{*0}} - m_{D^0} = 142.12 \pm 0.07$ MeV
Full width $\Gamma < 2.1$ MeV, CL = 90%

$\overline{D}^*(2007)^0$ modes are charge conjugates of modes below.

$D^*(2007)^0$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$D^0\pi^0$	(61.9±2.9) %	43
$D^0\gamma$	(38.1±2.9) %	137

$D^*(2010)^\pm$

$I(J^P) = \frac{1}{2}(1^-)$
I, J, P need confirmation.

Mass $m = 2010.0 \pm 0.5$ MeV (S = 1.1)
$m_{D^*(2010)^-} - m_{D^-} = 140.64 \pm 0.10$ MeV (S = 1.1)
$m_{D^*(2010)^-} - m_{D^0} = 145.397 \pm 0.030$ MeV
Full width $\Gamma < 0.131$ MeV, CL = 90%

$D^*(2010)^-$ modes are charge conjugates of the modes below.

$D^*(2010)^\pm$ DECAY MODES	Fraction (Γ_j/Γ)	p (MeV/c)
$D^0\pi^+$	(68.3±1.4) %	39
$D^+\pi^0$	(30.6±2.5) %	38
$D^+\gamma$	(1.1 $^{+2.1}_{-0.7}$) %	136

$D_1(2420)^0$

$I(J^P) = \frac{1}{2}(1^+)$
I, J, P need confirmation.

Mass $m = 2422.2 \pm 1.8$ MeV (S = 1.2)
Full width $\Gamma = 18.9^{+4.6}_{-3.5}$ MeV

$\overline{D}_1(2420)^0$ modes are charge conjugates of modes below.

$D_1(2420)^0$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$D^*(2010)^+\pi^-$	seen	355
$D^+\pi^-$	not seen	474

$D_2^*(2460)^0$

$I(J^P) = \frac{1}{2}(2^+)$

$J^P = 2^+$ assignment strongly favored (ALBRECHT 89B).
Mass $m = 2458.9 \pm 2.0$ MeV (S = 1.2)
Full width $\Gamma = 23 \pm 5$ MeV

$\overline{D}_2^*(2460)^0$ modes are charge conjugates of modes below.

$D_2^*(2460)^0$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$D^+\pi^-$	seen	503
$D^*(2010)^+\pi^-$	seen	387

$D_2^*(2460)^\pm$

$I(J^P) = \frac{1}{2}(2^+)$

$J^P = 2^+$ assignment strongly favored (ALBRECHT 89B).
Mass $m = 2459 \pm 4$ MeV (S = 1.7)
$m_{D_2^*(2460)^\pm} - m_{D_2^*(2460)^0} = 0.9 \pm 3.3$ MeV (S = 1.1)
Full width $\Gamma = 25^{+8}_{-7}$ MeV

$D_2^*(2460)^-$ modes are charge conjugates of modes below.

$D_2^*(2460)^\pm$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$D^0\pi^+$	seen	508
$D^{*0}\pi^+$	seen	390

CHARMED, STRANGE MESONS ($C = S = \pm 1$)

$D_s^+ = c\bar{s}$, $D_s^- = \bar{c}s$, similarly for D_s^{*}'s

$D_s^\pm$ (was $F^\pm$)

$I(J^P) = 0(0^-)$

Mass $m = 1968.5 \pm 0.6$ MeV (S = 1.1)
$m_{D_s^\pm} - m_{D^\pm} = 99.2 \pm 0.5$ MeV (S = 1.1)
Mean life $\tau = (0.467 \pm 0.017) \times 10^{-12}$ s
$c\tau = 140\ \mu$m

D_s^+ form factors

$r_2 = 1.6 \pm 0.4$
$r_V = 1.5 \pm 0.5$
$\Gamma_L/\Gamma_T = 0.72 \pm 0.18$

Branching fractions for modes with a resonance in the final state include all the decay modes of the resonance. D_s^- modes are charge conjugates of the modes below.

D_s^+ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
Inclusive modes			
K^- anything	$(13\ ^{+14}_{-12})\%$		–
$\overline{K}^0$ anything + K^0 anything	$(39\ \pm 28)\%$		–
K^+ anything	$(20\ ^{+18}_{-14})\%$		–
non-$K\overline{K}$ anything	$(64\ \pm 17)\%$		–
e^+ anything	$(8\ ^{+6}_{-5})\%$		–
ϕ anything	$(18\ ^{+15}_{-10})\%$		–
Leptonic and semileptonic modes			
$\mu^+\nu_\mu$	$(4.0\ ^{+2.2}_{-2.0}) \times 10^{-3}$	S=1.4	981
$\tau^+\nu_\tau$	$(7 \pm 4)\%$		182
$\phi\ell^+\nu_\ell$	[xx] $(2.0 \pm 0.5)\%$		–
$\eta\ell^+\nu_\ell + \eta'(958)\ell^+\nu_\ell$	[xx] $(3.4 \pm 1.0)\%$		–
$\eta\ell^+\nu_\ell$	$(2.5 \pm 0.7)\%$		–
$\eta'(958)\ell^+\nu_\ell$	$(8.8 \pm 3.4) \times 10^{-3}$		–
Hadronic modes with a $K\overline{K}$ pair (including from a ϕ)			
$K^+\overline{K}^0$	$(3.6 \pm 1.1)\%$		850
$K^+K^-\pi^+$	[qq] $(4.4 \pm 1.2)\%$	S=1.1	806
$\phi\pi^+$	[yy] $(3.6 \pm 0.9)\%$		712
$K^+\overline{K}^*(892)^0$	[yy] $(3.3 \pm 0.9)\%$		682
$f_0(980)\pi^+$	[yy] $(1.8 \pm 0.8)\%$	S=1.3	732
$K^+\overline{K}_0^*(1430)^0$	[yy] $(7 \pm 4) \times 10^{-3}$		186
$f_J(1710)\pi^+ \to K^+K^-\pi^+$	[zz] $(1.5 \pm 1.9) \times 10^{-3}$		204
$K^+K^-\pi^+$ nonresonant	$(9 \pm 4) \times 10^{-3}$		805
$K^0\overline{K}^0\pi^+$	—		802
$K^*(892)^+\overline{K}^0$	[yy] $(4.3 \pm 1.4)\%$		683
$K^+K^-\pi^+\pi^0$	—		748
$\phi\pi^+\pi^0$	[yy] $(9 \pm 5)\%$		687
$\phi\rho^+$	[yy] $(6.7 \pm 2.3)\%$		407
$\phi\pi^+\pi^0$ 3-body	[yy] $< 2.6\ \%$	CL=90%	687
$K^+K^-\pi^+\pi^0$ non-ϕ	$< 9\ \%$	CL=90%	748
$K^+\overline{K}^0\pi^+\pi^-$	$< 2.8\ \%$	CL=90%	744
$K^0K^-\pi^+\pi^+$	$(4.3 \pm 1.5)\%$		744
$K^*(892)^+\overline{K}^*(892)^0$	[yy] $(5.8 \pm 2.5)\%$		412
$K^0K^-\pi^+\pi^+$ non-$K^{*+}\overline{K}^{*0}$	$< 2.9\ \%$	CL=90%	744
$K^+K^-\pi^+\pi^+\pi^-$	$(8.3 \pm 3.3) \times 10^{-3}$		673
$\phi\pi^+\pi^+\pi^-$	[yy] $(1.18 \pm 0.35)\%$		640
$K^+K^-\pi^+\pi^+\pi^-$ non-ϕ	$(3.0\ ^{+3.0}_{-2.0}) \times 10^{-3}$		673
Hadronic modes without K's			
$\pi^+\pi^+\pi^-$	$(1.0 \pm 0.4)\%$	S=1.2	959
$\rho^0\pi^+$	$< 8 \times 10^{-4}$	CL=90%	827
$f_0(980)\pi^+$	[yy] $(1.8 \pm 0.8)\%$	S=1.7	732
$f_2(1270)\pi^+$	[yy] $(2.3 \pm 1.3) \times 10^{-3}$		559
$f_0(1500)\pi^+ \to \pi^+\pi^-\pi^+$	[aaa] $(2.8 \pm 1.6) \times 10^{-3}$		391
$\pi^+\pi^+\pi^-$ nonresonant	$< 2.8 \times 10^{-3}$	CL=90%	959
$\pi^+\pi^+\pi^-\pi^0$	$< 12\ \%$	CL=90%	935
$\eta\pi^+$	[yy] $(2.0 \pm 0.6)\%$		902

$\omega\pi^+$	[yy]	(3.1 ± 1.4) × 10^{-3}			822
$\pi^+\pi^+\pi^+\pi^-\pi^-$		(6.9 ± 3.0) × 10^{-3}			899
$\pi^+\pi^+\pi^-\pi^0\pi^0$		—			902
$\eta\rho^+$	[yy]	(10.3 ± 3.2) %			727
$\eta\pi^+\pi^0$ 3-body	[yy]	< 3.0	%	CL=90%	886
$\pi^+\pi^+\pi^+\pi^-\pi^-\pi^0$		(4.9 ± 3.2) %			856
$\eta'(958)\pi^+$	[yy]	(4.9 ± 1.8) %			743
$\pi^+\pi^+\pi^+\pi^-\pi^-\pi^0\pi^0$		—			803
$\eta'(958)\rho^+$	[yy]	(12 ± 4) %			470
$\eta'(958)\pi^+\pi^0$ 3-body	[yy]	< 3.1	%	CL=90%	720
Modes with one or three K's					
$K^0\pi^+$		< 8	× 10^{-3}	CL=90%	916
$K^+\pi^+\pi^-$		(1.0 ± 0.4) %			900
$K^+\rho^0$		< 2.9	× 10^{-3}	CL=90%	747
$K^*(892)^0\pi^+$	[yy]	(6.5 ± 2.8) × 10^{-3}			773
$K^+K^+K^-$		< 6	× 10^{-4}	CL=90%	628
ϕK^+	[yy]	< 5	× 10^{-4}	CL=90%	607
$\Delta C = 1$ weak neutral current ($C1$) modes or Lepton number (L) violating modes					
$\pi^+\mu^+\mu^-$	[ss]	< 4.3	× 10^{-4}	CL=90%	968
$K^+\mu^+\mu^-$	$C1$	< 5.9	× 10^{-4}	CL=90%	909
$K^*(892)^+\mu^+\mu^-$	$C1$	< 1.4	× 10^{-3}	CL=90%	765
$\pi^-\mu^+\mu^+$	L	< 4.3	× 10^{-4}	CL=90%	968
$K^-\mu^+\mu^+$	L	< 5.9	× 10^{-4}	CL=90%	909
$K^*(892)^-\mu^+\mu^+$	L	< 1.4	× 10^{-3}	CL=90%	765

$D_s^{*\pm}$

$I(J^P) = 0(?^?)$

J^P is natural, width and decay modes consistent with 1^-.

Mass $m = 2112.4 \pm 0.7$ MeV (S = 1.1)

$m_{D_s^{*\pm}} - m_{D_s^{\pm}} = 143.8 \pm 0.4$ MeV

Full width $\Gamma < 1.9$ MeV, CL = 90%

D_s^{*-} modes are charge conjugates of the modes below.

D_s^{*+} DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$D_s^+\gamma$	(94.2±2.5) %	139
$D_s^+\pi^0$	(5.8±2.5) %	48

$D_{s1}(2536)^{\pm}$

$I(J^P) = 0(1^+)$

J, P need confirmation.

Mass $m = 2535.35 \pm 0.34 \pm 0.5$ MeV

Full width $\Gamma < 2.3$ MeV, CL = 90%

$D_{s1}(2536)^-$ modes are charge conjugates of the modes below.

$D_{s1}(2536)^+$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$D^*(2010)^+K^0$	seen	150
$D^*(2007)^0K^+$	seen	169
D^+K^0	not seen	382
D^0K^+	not seen	392
$D_s^{*+}\gamma$	possibly seen	389

$D_{sJ}(2573)^{\pm}$

$I(J^P) = 0(?^?)$

J^P is natural, width and decay modes consistent with 2^+.

Mass $m = 2573.5 \pm 1.7$ MeV

Full width $\Gamma = 15^{+5}_{-4}$ MeV

$D_{sJ}(2573)^-$ modes are charge conjugates of the modes below.

$D_{sJ}(2573)^+$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
D^0K^+	seen	436
$D^*(2007)^0K^+$	not seen	245

BOTTOM MESONS ($B = \pm 1$)

$B^+ = u\bar{b}$, $B^0 = d\bar{b}$, $\bar{B}^0 = \bar{d}b$, $B^- = \bar{u}b$, similarly for B^*'s

B-particle organization

Many measurements of B decays involve admixtures of B hadrons. Previously we arbitrarily included such admixtures in the $B^{\pm}$ section, but because of their importance we have created two new sections: "$B^{\pm}/B^0$ Admixture" for $\Upsilon(4S)$ results and "$B^{\pm}/B^0/B_s^0/b$-baryon Admixture" for results at higher energies. Most inclusive decay branching fractions are found in the Admixture sections. B^0-$\bar{B}^0$ mixing data are found in the B^0 section, while B_s^0-$\bar{B}_s^0$ mixing data and B-$\bar{B}$ mixing data for a B^0/B_s^0 admixture are found in the B_s^0 section. CP-violation data are found in the B^0 section. b-baryons are found near the end of the Baryon section.

The organization of the B sections is now as follows, where bullets indicate particle sections and brackets indicate reviews.

[Production and Decay of b-flavored Hadrons]

[Semileptonic Decays of B Mesons]

- $B^{\pm}$
  - mass, mean life
  - branching fractions
- B^0
  - mass, mean life
  - branching fractions
  - polarization in B^0 decay
  - B^0-$\bar{B}^0$ mixing
  - [B^0-$\bar{B}^0$ Mixing and CP Violation in B Decay]
  - CP violation
- $B^{\pm}$ B^0 Admixtures
  - branching fractions
- $B^{\pm}/B^0/B_s^0/b$-baryon Admixtures
  - mean life
  - production fractions
  - branching fractions
- B^*
  - mass
- B_s^0
  - mass, mean life
  - branching fractions
  - polarization in B_s^0 decay
  - B_s^0-$\bar{B}_s^0$ mixing
  - B-$\bar{B}$ mixing (admixture of B^0, B_s^0)

At end of Baryon Listings:

- Λ_b
  - mass, mean life
  - branching fractions
- b-baryon Admixture
  - mean life
  - branching fractions

$B^\pm$ $I(J^P) = \frac{1}{2}(0^-)$

I, *J*, *P* need confirmation. Quantum numbers shown are quark-model predictions.

Mass $m_{B^\pm} = 5278.9 \pm 1.8$ MeV
Mean life $\tau_{B^\pm} = (1.65 \pm 0.04) \times 10^{-12}$ s
$c\tau = 495\ \mu$m

B^- modes are charge conjugates of the modes below. Modes which do not identify the charge state of the B are listed in the $B^\pm/B^0$ ADMIXTURE section.

The branching fractions listed below assume 50% $B^0\overline{B}^0$ and 50% B^+B^- production at the $\Upsilon(4S)$. We have attempted to bring older measurements up to date by rescaling their assumed $\Upsilon(4S)$ production ratio to 50:50 and their assumed $D\Gamma D_s\Gamma D^*\Gamma$ and ψ branching ratios to current values whenever this would affect our averages and best limits significantly.

Indentation is used to indicate a subchannel of a previous reaction. All resonant subchannels have been corrected for resonance branching fractions to the final state so the sum of the subchannel branching fractions can exceed that of the final state.

B^+ DECAY MODES	Fraction (Γ_j/Γ)	Scale factor/ Confidence level	p (MeV/c)
Semileptonic and leptonic modes			
$\ell^+\nu_\ell$ anything	[pp] (10.3 ±0.9) %		–
$\overline{D}^0\ell^+\nu_\ell$	[pp] (1.86±0.33) %		–
$\overline{D}^*(2007)^0\ell^+\nu_\ell$	[pp] (5.3 ±0.8) %		–
$\pi^0 e^+\nu_e$	< 2.2 $\times 10^{-3}$	CL=90%	2638
$\omega\ell^+\nu_\ell$	[pp] < 2.1 $\times 10^{-4}$	CL=90%	–
$\rho^0\ell^+\nu_\ell$	[pp] < 2.1 $\times 10^{-4}$	CL=90%	–
$e^+\nu_e$	< 1.5 $\times 10^{-5}$	CL=90%	2639
$\mu^+\nu_\mu$	< 2.1 $\times 10^{-5}$	CL=90%	2638
$\tau^+\nu_\tau$	< 5.7 $\times 10^{-4}$	CL=90%	2340
$e^+\nu_e\gamma$	< 2.0 $\times 10^{-4}$	CL=90%	–
$\mu^+\nu_\mu\gamma$	< 5.2 $\times 10^{-5}$	CL=90%	–
$D\Gamma D^*\Gamma$ or D_s modes			
$\overline{D}^0\pi^+$	(5.3 ±0.5) $\times 10^{-3}$		2308
$\overline{D}^0\rho^+$	(1.34±0.18) %		2238
$\overline{D}^0\pi^+\pi^+\pi^-$	(1.1 ±0.4) %		2289
$\overline{D}^0\pi^+\pi^+\pi^-$ nonresonant	(5 ±4) $\times 10^{-3}$		2289
$\overline{D}^0\pi^+\rho^0$	(4.2 ±3.0) $\times 10^{-3}$		2209
$\overline{D}^0 a_1(1260)^+$	(5 ±4) $\times 10^{-3}$		2123
$D^*(2010)^-\pi^+\pi^+$	(2.1 ±0.6) $\times 10^{-3}$		2247
$D^-\pi^+\pi^+$	< 1.4 $\times 10^{-3}$	CL=90%	2299
$\overline{D}^*(2007)^0\pi^+$	(4.6 ±0.4) $\times 10^{-3}$		2256
$D^*(2010)^+\pi^0$	< 1.7 $\times 10^{-4}$	CL=90%	2254
$\overline{D}^*(2007)^0\rho^+$	(1.55±0.31) %		2183
$\overline{D}^*(2007)^0\pi^+\pi^+\pi^-$	(9.4 ±2.6) $\times 10^{-3}$		2236
$\overline{D}^*(2007)^0 a_1(1260)^+$	(1.9 ±0.5) %		2062
$D^*(2010)^-\pi^+\pi^+\pi^0$	(1.5 ±0.7) %		2235
$D^*(2010)^-\pi^+\pi^+\pi^+\pi^-$	< 1 %	CL=90%	2217
$\overline{D}_1^*(2420)^0\pi^+$	(1.5 ±0.6) $\times 10^{-3}$	S=1.3	2081
$\overline{D}_1^*(2420)^0\rho^+$	< 1.4 $\times 10^{-3}$	CL=90%	1997
$\overline{D}_2^*(2460)^0\pi^+$	< 1.3 $\times 10^{-3}$	CL=90%	2064
$\overline{D}_2^*(2460)^0\rho^+$	< 4.7 $\times 10^{-3}$	CL=90%	1979
$\overline{D}^0 D_s^+$	(1.3 ±0.4) %		1815
$\overline{D}^0 D_s^{*+}$	(9 ±4) $\times 10^{-3}$		1734
$\overline{D}^*(2007)^0 D_s^+$	(1.2 ±0.5) %		1737
$\overline{D}^*(2007)^0 D_s^{*+}$	(2.7 ±1.0) %		1650
$D_s^+\pi^0$	< 2.0 $\times 10^{-4}$	CL=90%	2270
$D_s^{*+}\pi^0$	< 3.3 $\times 10^{-4}$	CL=90%	2214
$D_s^+\eta$	< 5 $\times 10^{-4}$	CL=90%	2235
$D_s^{*+}\eta$	< 8 $\times 10^{-4}$	CL=90%	2177
$D_s^+\rho^0$	< 4 $\times 10^{-4}$	CL=90%	2198
$D_s^{*+}\rho^0$	< 5 $\times 10^{-4}$	CL=90%	2139
$D_s^+\omega$	< 5 $\times 10^{-4}$	CL=90%	2195
$D_s^{*+}\omega$	< 7 $\times 10^{-4}$	CL=90%	2136
$D_s^+ a_1(1260)^0$	< 2.2 $\times 10^{-3}$	CL=90%	2079
$D_s^{*+} a_1(1260)^0$	< 1.6 $\times 10^{-3}$	CL=90%	2014
$D_s^+\phi$	< 3.2 $\times 10^{-4}$	CL=90%	2141
$D_s^{*+}\phi$	< 4 $\times 10^{-4}$	CL=90%	2079
$D_s^+\overline{K}^0$	< 1.1 $\times 10^{-3}$	CL=90%	2241
$D_s^{*+}\overline{K}^0$	< 1.1 $\times 10^{-3}$	CL=90%	2184
$D_s^+\overline{K}^*(892)^0$	< 5 $\times 10^{-4}$	CL=90%	2171
$D_s^{*+}\overline{K}^*(892)^0$	< 4 $\times 10^{-4}$	CL=90%	2110
$D_s^-\pi^+K^+$	< 8 $\times 10^{-4}$	CL=90%	2222
$D_s^{*-}\pi^+K^+$	< 1.2 $\times 10^{-3}$	CL=90%	2164
$D_s^-\pi^+K^*(892)^+$	< 6 $\times 10^{-3}$	CL=90%	2137
$D_s^{*-}\pi^+K^*(892)^+$	< 8 $\times 10^{-3}$	CL=90%	2075
Charmonium modes			
$J/\psi(1S)K^+$	(9.9 ±1.0) $\times 10^{-4}$		1683
$J/\psi(1S)K^+\pi^+\pi^-$	(1.4 ±0.6) $\times 10^{-3}$		1612
$J/\psi(1S)K^*(892)^+$	(1.47±0.27) $\times 10^{-3}$		1571
$J/\psi(1S)\pi^+$	(5.0 ±1.5) $\times 10^{-5}$		1727
$J/\psi(1S)\rho^+$	< 7.7 $\times 10^{-4}$	CL=90%	1613
$J/\psi(1S)a_1(1260)^+$	< 1.2 $\times 10^{-3}$	CL=90%	1414
$\psi(2S)K^+$	(6.9 ±3.1) $\times 10^{-4}$	S=1.3	1284
$\psi(2S)K^*(892)^+$	< 3.0 $\times 10^{-3}$	CL=90%	1115
$\psi(2S)K^+\pi^+\pi^-$	(1.9 ±1.2) $\times 10^{-3}$		909
$\chi_{c1}(1P)K^+$	(1.0 ±0.4) $\times 10^{-3}$		1411
$\chi_{c1}(1P)K^*(892)^+$	< 2.1 $\times 10^{-3}$	CL=90%	1265
K or K^* modes			
$K^0\pi^+$	(2.3 ±1.1) $\times 10^{-5}$		2614
$K^+\pi^0$	< 1.6 $\times 10^{-5}$	CL=90%	2615
$\eta' K^+$	(6.5 ±1.7) $\times 10^{-5}$		2528
$\eta' K^*(892)^+$	< 1.3 $\times 10^{-4}$	CL=90%	2472
ηK^+	< 1.4 $\times 10^{-5}$	CL=90%	2587
$\eta K^*(892)^+$	< 3.0 $\times 10^{-5}$	CL=90%	2534
$K^*(892)^0\pi^+$	< 4.1 $\times 10^{-5}$	CL=90%	2561
$K^*(892)^+\pi^0$	< 9.9 $\times 10^{-5}$	CL=90%	2562
$K^+\pi^-\pi^+$ nonresonant	< 2.8 $\times 10^{-5}$	CL=90%	2609
$K^-\pi^+\pi^+$ nonresonant	< 5.6 $\times 10^{-5}$	CL=90%	–
$K_1(1400)^0\pi^+$	< 2.6 $\times 10^{-3}$	CL=90%	2451
$K_2^*(1430)^0\pi^+$	< 6.8 $\times 10^{-4}$	CL=90%	2443
$K^+\rho^0$	< 1.9 $\times 10^{-5}$	CL=90%	2559
$K^0\rho^+$	< 4.8 $\times 10^{-5}$	CL=90%	2559
$K^*(892)^+\pi^+\pi^-$	< 1.1 $\times 10^{-3}$	CL=90%	2556
$K^*(892)^+\rho^0$	< 9.0 $\times 10^{-4}$	CL=90%	2505
$K_1(1400)^+\rho^0$	< 7.8 $\times 10^{-4}$	CL=90%	2389
$K_2^*(1430)^+\rho^0$	< 1.5 $\times 10^{-3}$	CL=90%	2382
$K^+\overline{K}^0$	< 2.1 $\times 10^{-5}$	CL=90%	2592
$K^+K^-\pi^+$ nonresonant	< 7.5 $\times 10^{-5}$	CL=90%	–
$K^+K^-K^+$	< 2.0 $\times 10^{-4}$	CL=90%	2522
$K^+\phi$	< 1.2 $\times 10^{-5}$	CL=90%	2516
$K^+K^-K^+$ nonresonant	< 3.8 $\times 10^{-5}$	CL=90%	2516
$K^*(892)^+K^+K^-$	< 1.6 $\times 10^{-3}$	CL=90%	2466
$K^*(892)^+\phi$	< 7.0 $\times 10^{-5}$	CL=90%	2460
$K_1(1400)^+\phi$	< 1.1 $\times 10^{-3}$	CL=90%	2339
$K_2^*(1430)^+\phi$	< 3.4 $\times 10^{-3}$	CL=90%	2332
$K^+ f_0(980)$	< 8 $\times 10^{-5}$	CL=90%	2524
$K^*(892)^+\gamma$	(5.7 ±3.3) $\times 10^{-5}$		2564
$K_1(1270)^+\gamma$	< 7.3 $\times 10^{-3}$	CL=90%	2486
$K_1(1400)^+\gamma$	< 2.2 $\times 10^{-3}$	CL=90%	2453
$K_2^*(1430)^+\gamma$	< 1.4 $\times 10^{-3}$	CL=90%	2447
$K^*(1680)^+\gamma$	< 1.9 $\times 10^{-3}$	CL=90%	2361
$K_3^*(1780)^+\gamma$	< 5.5 $\times 10^{-3}$	CL=90%	2343
$K_4^*(2045)^+\gamma$	< 9.9 $\times 10^{-3}$	CL=90%	2243
Light unflavored meson modes			
$\pi^+\pi^0$	< 2.0 $\times 10^{-5}$	CL=90%	2636
$\pi^+\pi^+\pi^-$	< 1.3 $\times 10^{-4}$	CL=90%	2630
$\rho^0\pi^+$	< 4.3 $\times 10^{-5}$	CL=90%	2582
$\pi^+ f_0(980)$	< 1.4 $\times 10^{-4}$	CL=90%	2547
$\pi^+ f_2(1270)$	< 2.4 $\times 10^{-4}$	CL=90%	2483
$\pi^+\pi^-\pi^+$ nonresonant	< 4.1 $\times 10^{-5}$	CL=90%	–
$\pi^+\pi^0\pi^0$	< 8.9 $\times 10^{-4}$	CL=90%	2631
$\rho^+\pi^0$	< 7.7 $\times 10^{-5}$	CL=90%	2582
$\pi^+\pi^-\pi^+\pi^0$	< 4.0 $\times 10^{-3}$	CL=90%	2621
$\rho^+\rho^0$	< 1.0 $\times 10^{-3}$	CL=90%	2525
$a_1(1260)^+\pi^0$	< 1.7 $\times 10^{-3}$	CL=90%	2494
$a_1(1260)^0\pi^+$	< 9.0 $\times 10^{-4}$	CL=90%	2494
$\omega\pi^+$	< 4.0 $\times 10^{-4}$	CL=90%	2580

$\eta\pi^+$	$<$	1.5	$\times 10^{-5}$	CL=90%	2609
$\eta'\pi^+$	$<$	3.1	$\times 10^{-5}$	CL=90%	2550
$\eta'\rho^+$	$<$	4.7	$\times 10^{-5}$	CL=90%	2493
$\eta\rho^+$	$<$	3.2	$\times 10^{-5}$	CL=90%	2554
$\pi^+\pi^+\pi^+\pi^-\pi^-$	$<$	8.6	$\times 10^{-4}$	CL=90%	2608
$\rho^0 a_1(1260)^+$	$<$	6.2	$\times 10^{-4}$	CL=90%	2434
$\rho^0 a_2(1320)^+$	$<$	7.2	$\times 10^{-4}$	CL=90%	2411
$\pi^+\pi^+\pi^+\pi^-\pi^-\pi^0$	$<$	6.3	$\times 10^{-3}$	CL=90%	2592
$a_1(1260)^+ a_1(1260)^0$	$<$	1.3	%	CL=90%	2335
Baryon modes					
$p\bar{p}\pi^+$	$<$	1.6	$\times 10^{-4}$	CL=90%	2439
$p\bar{p}\pi^+$ nonresonant	$<$	5.3	$\times 10^{-5}$	CL=90%	–
$p\bar{p}\pi^+\pi^+\pi^-$	$<$	5.2	$\times 10^{-4}$	CL=90%	2369
$p\bar{p}K^+$ nonresonant	$<$	8.9	$\times 10^{-5}$	CL=90%	–
$p\bar{\Lambda}$	$<$	6	$\times 10^{-5}$	CL=90%	2430
$p\bar{\Lambda}\pi^+\pi^-$	$<$	2.0	$\times 10^{-4}$	CL=90%	2367
$\bar{\Delta}^0 p$	$<$	3.8	$\times 10^{-4}$	CL=90%	2402
$\Delta^{++}\bar{p}$	$<$	1.5	$\times 10^{-4}$	CL=90%	2402
$\Lambda_c^- p\pi^+$	(	6.2 $\pm$2.7)	$\times 10^{-4}$		–
$\bar{\Lambda}_c^- p\pi^+\pi^0$	$<$	3.12	$\times 10^{-3}$	CL=90%	–
$\bar{\Lambda}_c^- p\pi^+\pi^+\pi^-$	$<$	1.46	$\times 10^{-3}$	CL=90%	–
$\bar{\Lambda}_c^- p\pi^+\pi^+\pi^-\pi^0$	$<$	1.34	%	CL=90%	–
Lepton Family number (LF) or Lepton number (L) violating modes or $\Delta B = 1$ weak neutral current ($B1$) modes					
$\pi^+ e^+ e^-$	$B1$	$<$	3.9	$\times 10^{-3}$	CL=90%	2638
$\pi^+\mu^+\mu^-$	$B1$	$<$	9.1	$\times 10^{-3}$	CL=90%	2633
$K^+ e^+ e^-$	$B1$	$<$	6	$\times 10^{-5}$	CL=90%	2616
$K^+\mu^+\mu^-$	$B1$	$<$	1.0	$\times 10^{-5}$	CL=90%	2612
$K^*(892)^+ e^+ e^-$	$B1$	$<$	6.9	$\times 10^{-4}$	CL=90%	2564
$K^*(892)^+\mu^+\mu^-$	$B1$	$<$	1.2	$\times 10^{-3}$	CL=90%	2560
$\pi^+ e^+\mu^-$	LF	$<$	6.4	$\times 10^{-3}$	CL=90%	2637
$\pi^+ e^-\mu^+$	LF	$<$	6.4	$\times 10^{-3}$	CL=90%	2637
$K^+ e^+\mu^-$	LF	$<$	6.4	$\times 10^{-3}$	CL=90%	2615
$K^+ e^-\mu^+$	LF	$<$	6.4	$\times 10^{-3}$	CL=90%	2615
$\pi^- e^+ e^+$	L	$<$	3.9	$\times 10^{-3}$	CL=90%	2638
$\pi^-\mu^+\mu^+$	L	$<$	9.1	$\times 10^{-3}$	CL=90%	2633
$\pi^- e^+\mu^+$	LF	$<$	6.4	$\times 10^{-3}$	CL=90%	2637
$K^- e^+ e^+$	L	$<$	3.9	$\times 10^{-3}$	CL=90%	2616
$K^-\mu^+\mu^+$	L	$<$	9.1	$\times 10^{-3}$	CL=90%	2612
$K^- e^+\mu^+$	LF	$<$	6.4	$\times 10^{-3}$	CL=90%	2615

B^0

$I(J^P) = \frac{1}{2}(0^-)$

I, J, P need confirmation. Quantum numbers shown are quark-model predictions.

Mass $m_{B^0} = 5279.2 \pm 1.8$ MeV
$m_{B^0} - m_{B^\pm} = 0.35 \pm 0.29$ MeV (S = 1.1)
Mean life $\tau_{B^0} = (1.56 \pm 0.04) \times 10^{-12}$ s
$c\tau = 468\ \mu$m
$\tau_{B^-}/\tau_{B^0} = 1.02 \pm 0.04$ (average of direct and inferred)
$\tau_{B^-}/\tau_{B^0} = 1.04 \pm 0.04$ (direct measurements)
$\tau_{B^-}/\tau_{B^0} = 0.95^{+0.15}_{-0.12}$ (inferred from branching fractions)

B^0-$\bar{B}^0$ mixing parameters

$\chi_d = 0.172 \pm 0.010$
$\Delta m_{B^0} = m_{B^0_H} - m_{B^0_L} = (0.464 \pm 0.018) \times 10^{12}\ \hbar\ \mathrm{s}^{-1}$
$x_d = \Delta m_{B^0}/\Gamma_{B^0} = 0.723 \pm 0.032$

CP violation parameters

$|\mathrm{Re}(\epsilon_{B^0})| = 0.002 \pm 0.008$

$\bar{B}^0$ modes are charge conjugates of the modes below. Reactions indicate the weak decay vertex and do not include mixing. Modes which do not identify the charge state of the B are listed in the $B^\pm/B^0$ ADMIXTURE section.

The branching fractions listed below assume 50% $B^0\bar{B}^0$ and 50% B^+B^- production at the $\Upsilon(4S)$. We have attempted to bring older measurements up to date by rescaling their assumed $\Upsilon(4S)$ production ratio to 50:50 and their assumed $D\overline{D}_s$, $D^*\overline{D}$, and ψ branching ratios to current values whenever this would affect our averages and best fit limits significantly.

Indentation is used to indicate a subchannel of a previous reaction. All resonant subchannels have been corrected for resonance branching fractions to the final state so the sum of the subchannel branching fractions can exceed that of the final state.

B^0 DECAY MODES		Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
$\ell^+\nu_\ell$ anything	[pp]	(10.5 $\pm$ 0.8) %		–
$D^-\ell^+\nu_\ell$	[pp]	(2.00 $\pm$ 0.25) %		–
$D^*(2010)^-\ell^+\nu_\ell$	[pp]	(4.60 $\pm$ 0.27) %		–
$\rho^-\ell^+\nu_\ell$	[pp]	(2.5 $^{+\ 0.8}_{-\ 1.0}$) $\times 10^{-4}$		–
$\pi^-\ell^+\nu_\ell$		(1.8 $\pm$ 0.6) $\times 10^{-4}$		–
Inclusive modes				
K^+ anything		(78 $\pm$80) %		–
$D\Gamma D^*\Gamma$ or D_s modes				
$D^-\pi^+$		(3.0 $\pm$ 0.4) $\times 10^{-3}$		2306
$D^-\rho^+$		(7.9 $\pm$ 1.4) $\times 10^{-3}$		2236
$\overline{D}^0\pi^+\pi^-$		$<$ 1.6 $\times 10^{-3}$	CL=90%	2301
$D^*(2010)^-\pi^+$		(2.76 $\pm$ 0.21) $\times 10^{-3}$		2254
$D^-\pi^+\pi^+\pi^-$		(8.0 $\pm$ 2.5) $\times 10^{-3}$		2287
($D^-\pi^+\pi^+\pi^-$) nonresonant		(3.9 $\pm$ 1.9) $\times 10^{-3}$		2287
$D^-\pi^+\rho^0$		(1.1 $\pm$ 1.0) $\times 10^{-3}$		2207
$D^- a_1(1260)^+$		(6.0 $\pm$ 3.3) $\times 10^{-3}$		2121
$D^*(2010)^-\pi^+\pi^0$		(1.5 $\pm$ 0.5) %		2247
$D^*(2010)^-\rho^+$		(6.7 $\pm$ 3.3) $\times 10^{-3}$		2181
$D^*(2010)^-\pi^+\pi^+\pi^-$		(7.6 $\pm$ 1.7) $\times 10^{-3}$	S=1.3	2235
($D^*(2010)^-\pi^+\pi^+\pi^-$) non-resonant		(0.0 $\pm$ 2.5) $\times 10^{-3}$		2235
$D^*(2010)^-\pi^+\rho^0$		(5.7 $\pm$ 3.1) $\times 10^{-3}$		2151
$D^*(2010)^- a_1(1260)^+$		(1.30 $\pm$ 0.27) %		2061
$D^*(2010)^-\pi^+\pi^+\pi^-\pi^0$		(3.4 $\pm$ 1.8) %		2218
$\overline{D}_2^*(2460)^-\pi^+$		$<$ 2.2 $\times 10^{-3}$	CL=90%	2064
$\overline{D}_2^*(2460)^-\rho^+$		$<$ 4.9 $\times 10^{-3}$	CL=90%	1979
$D^- D_s^+$		(8.0 $\pm$ 3.0) $\times 10^{-3}$		1812
$D^*(2010)^- D_s^+$		(9.6 $\pm$ 3.4) $\times 10^{-3}$		1735
$D^- D_s^{*+}$		(1.0 $\pm$ 0.5) %		1731
$D^*(2010)^- D_s^{*+}$		(2.0 $\pm$ 0.7) %		1649
$D_s^+\pi^-$		$<$ 2.8 $\times 10^{-4}$	CL=90%	2270
$D_s^{*+}\pi^-$		$<$ 5 $\times 10^{-4}$	CL=90%	2214
$D_s^+\rho^-$		$<$ 7 $\times 10^{-4}$	CL=90%	2198
$D_s^{*+}\rho^-$		$<$ 8 $\times 10^{-4}$	CL=90%	2139
$D_s^+ a_1(1260)^-$		$<$ 2.6 $\times 10^{-3}$	CL=90%	2079
$D_s^{*+} a_1(1260)^-$		$<$ 2.2 $\times 10^{-3}$	CL=90%	2014
$D_s^- K^+$		$<$ 2.4 $\times 10^{-4}$	CL=90%	2242
$D_s^{*-} K^+$		$<$ 1.7 $\times 10^{-4}$	CL=90%	2185
$D_s^- K^*(892)^+$		$<$ 9.9 $\times 10^{-4}$	CL=90%	2172
$D_s^{*-} K^*(892)^+$		$<$ 1.1 $\times 10^{-3}$	CL=90%	2112
$D_s^-\pi^+ K^0$		$<$ 5 $\times 10^{-3}$	CL=90%	2221
$D_s^{*-}\pi^+ K^0$		$<$ 3.1 $\times 10^{-3}$	CL=90%	2164
$D_s^-\pi^+ K^*(892)^0$		$<$ 4 $\times 10^{-3}$	CL=90%	2136
$D_s^{*-}\pi^+ K^*(892)^0$		$<$ 2.0 $\times 10^{-3}$	CL=90%	2074
$\overline{D}^0\pi^0$		$<$ 1.2 $\times 10^{-4}$	CL=90%	2308
$\overline{D}^0\rho^0$		$<$ 3.9 $\times 10^{-4}$	CL=90%	2238
$\overline{D}^0\eta$		$<$ 1.3 $\times 10^{-4}$	CL=90%	2274
$\overline{D}^0\eta'$		$<$ 9.4 $\times 10^{-4}$	CL=90%	2198
$\overline{D}^0\omega$		$<$ 5.1 $\times 10^{-4}$	CL=90%	2235
$\overline{D}^*(2007)^0\pi^0$		$<$ 4.4 $\times 10^{-4}$	CL=90%	2256
$\overline{D}^*(2007)^0\rho^0$		$<$ 5.6 $\times 10^{-4}$	CL=90%	2183
$\overline{D}^*(2007)^0\eta$		$<$ 2.6 $\times 10^{-4}$	CL=90%	2220
$\overline{D}^*(2007)^0\eta'$		$<$ 1.4 $\times 10^{-3}$	CL=90%	2141
$\overline{D}^*(2007)^0\omega$		$<$ 7.4 $\times 10^{-4}$	CL=90%	2180
$D^*(2010)^+ D^*(2010)^-$		$<$ 2.2 $\times 10^{-3}$	CL=90%	1711
$D^*(2010)^+ D^-$		$<$ 1.8 $\times 10^{-3}$	CL=90%	1790
$D^+ D^*(2010)^-$		$<$ 1.2 $\times 10^{-3}$	CL=90%	1790
Charmonium modes				
$J/\psi(1S)K^0$		(8.9 $\pm$ 1.2) $\times 10^{-4}$		1683
$J/\psi(1S)K^+\pi^-$		(1.1 $\pm$ 0.6) $\times 10^{-3}$		1652
$J/\psi(1S)K^*(892)^0$		(1.35 $\pm$ 0.18) $\times 10^{-3}$		1570
$J/\psi(1S)\pi^0$		$<$ 5.8 $\times 10^{-5}$	CL=90%	1728
$J/\psi(1S)\eta$		$<$ 1.2 $\times 10^{-3}$	CL=90%	1672
$J/\psi(1S)\rho^0$		$<$ 2.5 $\times 10^{-4}$	CL=90%	1614

$J/\psi(1S)\omega$	$<$	2.7	$\times 10^{-4}$	CL=90%	1609
$\psi(2S)K^0$	$<$	8	$\times 10^{-4}$	CL=90%	1283
$\psi(2S)K^+\pi^-$	$<$	1	$\times 10^{-3}$	CL=90%	1238
$\psi(2S)K^*(892)^0$	(	1.4 ± 0.9)	$\times 10^{-3}$		1113
$\chi_{c1}(1P)K^0$	$<$	2.7	$\times 10^{-3}$	CL=90%	1411
$\chi_{c1}(1P)K^*(892)^0$	$<$	2.1	$\times 10^{-3}$	CL=90%	1263

K or K^* modes

$K^+\pi^-$	(	$1.5 \pm {}^{0.5}_{0.4}$)	$\times 10^{-5}$		2615
$K^0\pi^0$	$<$	4.1	$\times 10^{-5}$	CL=90%	2614
$\eta' K^0$	(	$4.7 \pm {}^{2.8}_{2.2}$)	$\times 10^{-5}$		2528
$\eta' K^*(892)^0$	$<$	3.9	$\times 10^{-5}$	CL=90%	2472
$\eta K^*(892)^0$	$<$	3.0	$\times 10^{-5}$	CL=90%	2534
ηK^0	$<$	3.3	$\times 10^{-5}$	CL=90%	2593
K^+K^-	$<$	4.3	$\times 10^{-6}$	CL=90%	2593
$K^0\overline{K}^0$	$<$	1.7	$\times 10^{-5}$	CL=90%	2592
$K^+\rho^-$	$<$	3.5	$\times 10^{-5}$	CL=90%	2559
$K^0\rho^0$	$<$	3.9	$\times 10^{-5}$	CL=90%	2559
$K^0 f_0(980)$	$<$	3.6	$\times 10^{-4}$	CL=90%	2523
$K^*(892)^+\pi^-$	$<$	7.2	$\times 10^{-5}$	CL=90%	2562
$K^*(892)^0\pi^0$	$<$	2.8	$\times 10^{-5}$	CL=90%	2562
$K_2^*(1430)^+\pi^-$	$<$	2.6	$\times 10^{-3}$	CL=90%	2445
$K^0K^+K^-$	$<$	1.3	$\times 10^{-3}$	CL=90%	2522
$K^0\phi$	$<$	8.8	$\times 10^{-5}$	CL=90%	2516
$K^-\pi^+\pi^+\pi^-$	[*bbb*] $<$	2.3	$\times 10^{-4}$	CL=90%	2600
$K^*(892)^0\pi^+\pi^-$	$<$	1.4	$\times 10^{-3}$	CL=90%	2556
$K^*(892)^0\rho^0$	$<$	4.6	$\times 10^{-4}$	CL=90%	2504
$K^*(892)^0 f_0(980)$	$<$	1.7	$\times 10^{-4}$	CL=90%	2467
$K_1(1400)^+\pi^-$	$<$	1.1	$\times 10^{-3}$	CL=90%	2451
$K^-a_1(1260)^+$	[*bbb*] $<$	2.3	$\times 10^{-4}$	CL=90%	2471
$K^*(892)^0K^+K^-$	$<$	6.1	$\times 10^{-4}$	CL=90%	2466
$K^*(892)^0\phi$	$<$	4.3	$\times 10^{-5}$	CL=90%	2459
$K_1(1400)^0\rho^0$	$<$	3.0	$\times 10^{-3}$	CL=90%	2389
$K_1(1400)^0\phi$	$<$	5.0	$\times 10^{-3}$	CL=90%	2339
$K_2^*(1430)^0\rho^0$	$<$	1.1	$\times 10^{-3}$	CL=90%	2380
$K_2^*(1430)^0\phi$	$<$	1.4	$\times 10^{-3}$	CL=90%	2330
$K^*(892)^0\gamma$	(	4.0 ± 1.9)	$\times 10^{-5}$		2564
$K_1(1270)^0\gamma$	$<$	7.0	$\times 10^{-3}$	CL=90%	2486
$K_1(1400)^0\gamma$	$<$	4.3	$\times 10^{-3}$	CL=90%	2453
$K_2^*(1430)^0\gamma$	$<$	4.0	$\times 10^{-4}$	CL=90%	2445
$K^*(1680)^0\gamma$	$<$	2.0	$\times 10^{-3}$	CL=90%	2361
$K_3^*(1780)^0\gamma$	$<$	1.0	%	CL=90%	2343
$K_4^*(2045)^0\gamma$	$<$	4.3	$\times 10^{-3}$	CL=90%	2244
$\phi\phi$	$<$	3.9	$\times 10^{-5}$	CL=90%	2435

Light unflavored meson modes

$\pi^+\pi^-$	$<$	1.5	$\times 10^{-5}$	CL=90%	2636
$\pi^0\pi^0$	$<$	9.3	$\times 10^{-6}$	CL=90%	2636
$\eta\pi^0$	$<$	8	$\times 10^{-6}$	CL=90%	2609
$\eta\eta$	$<$	1.8	$\times 10^{-5}$	CL=90%	2582
$\eta'\pi^0$	$<$	1.1	$\times 10^{-5}$	CL=90%	2551
$\eta'\eta'$	$<$	4.7	$\times 10^{-5}$	CL=90%	2460
$\eta'\eta$	$<$	2.7	$\times 10^{-5}$	CL=90%	2522
$\eta'\rho^0$	$<$	2.3	$\times 10^{-5}$	CL=90%	2493
$\eta\rho^0$	$<$	1.3	$\times 10^{-5}$	CL=90%	2554
$\pi^+\pi^-\pi^0$	$<$	7.2	$\times 10^{-4}$	CL=90%	2631
$\rho^0\pi^0$	$<$	2.4	$\times 10^{-5}$	CL=90%	2582
$\rho^\mp\pi^\pm$	[*gg*] $<$	8.8	$\times 10^{-5}$	CL=90%	2582
$\pi^+\pi^-\pi^+\pi^-$	$<$	2.3	$\times 10^{-4}$	CL=90%	2621
$\rho^0\rho^0$	$<$	2.8	$\times 10^{-4}$	CL=90%	2525
$a_1(1260)^\mp\pi^\pm$	[*gg*] $<$	4.9	$\times 10^{-4}$	CL=90%	2494
$a_2(1320)^\mp\pi^\pm$	[*gg*] $<$	3.0	$\times 10^{-4}$	CL=90%	2473
$\pi^+\pi^-\pi^0\pi^0$	$<$	3.1	$\times 10^{-3}$	CL=90%	2622
$\rho^+\rho^-$	$<$	2.2	$\times 10^{-3}$	CL=90%	2525
$a_1(1260)^0\pi^0$	$<$	1.1	$\times 10^{-3}$	CL=90%	2494
$\omega\pi^0$	$<$	4.6	$\times 10^{-4}$	CL=90%	2580
$\pi^+\pi^+\pi^-\pi^-\pi^0$	$<$	9.0	$\times 10^{-3}$	CL=90%	2609
$a_1(1260)^+\rho^-$	$<$	3.4	$\times 10^{-3}$	CL=90%	2434
$a_1(1260)^0\rho^0$	$<$	2.4	$\times 10^{-3}$	CL=90%	2434
$\pi^+\pi^+\pi^+\pi^-\pi^-\pi^-$	$<$	3.0	$\times 10^{-3}$	CL=90%	2592
$a_1(1260)^+a_1(1260)^-$	$<$	2.8	$\times 10^{-3}$	CL=90%	2336
$\pi^+\pi^+\pi^+\pi^-\pi^-\pi^-\pi^0$	$<$	1.1	%	CL=90%	2572

Baryon modes

$p\overline{p}$	$<$	1.8	$\times 10^{-5}$	CL=90%	2467
$p\overline{p}\pi^+\pi^-$	$<$	2.5	$\times 10^{-4}$	CL=90%	2406
$p\overline{\Lambda}\pi^-$	$<$	1.8	$\times 10^{-4}$	CL=90%	2401
$\Delta^0\overline{\Delta}^0$	$<$	1.5	$\times 10^{-3}$	CL=90%	2334
$\Delta^{++}\Delta^{--}$	$<$	1.1	$\times 10^{-4}$	CL=90%	2334
$\overline{\Sigma}_c^{--}\Delta^{++}$	$<$	1.0	$\times 10^{-3}$	CL=90%	1839
$\Lambda_c^-p\pi^+\pi^-$	(	1.3 ± 0.6)	$\times 10^{-3}$		–
Λ_c^-p	$<$	2.1	$\times 10^{-4}$	CL=90%	2021
$\Lambda_c^-p\pi^0$	$<$	5.9	$\times 10^{-4}$	CL=90%	–
$\Lambda_c^-p\pi^+\pi^-\pi^0$	$<$	5.07	$\times 10^{-3}$	CL=90%	–
$\Lambda_c^-p\pi^+\pi^-\pi^+\pi^-$	$<$	2.74	$\times 10^{-3}$	CL=90%	–

Lepton Family number (LF) violating modes or $\Delta B = 1$ weak neutral current ($B1$) modes

$\gamma\gamma$	$B1$	$<$	3.9	$\times 10^{-5}$	CL=90%	2640
e^+e^-	$B1$	$<$	5.9	$\times 10^{-6}$	CL=90%	2640
$\mu^+\mu^-$	$B1$	$<$	6.8	$\times 10^{-7}$	CL=90%	2637
$K^0e^+e^-$	$B1$	$<$	3.0	$\times 10^{-4}$	CL=90%	2616
$K^0\mu^+\mu^-$	$B1$	$<$	3.6	$\times 10^{-4}$	CL=90%	2612
$K^*(892)^0e^+e^-$	$B1$	$<$	2.9	$\times 10^{-4}$	CL=90%	2564
$K^*(892)^0\mu^+\mu^-$	$B1$	$<$	2.3	$\times 10^{-5}$	CL=90%	2559
$K^*(892)^0\nu\overline{\nu}$	$B1$	$<$	1.0	$\times 10^{-3}$	CL=90%	2244
$e^\pm\mu^\mp$	LF	[*gg*] $<$	5.9	$\times 10^{-6}$	CL=90%	2639
$e^\pm\tau^\mp$	LF	[*gg*] $<$	5.3	$\times 10^{-4}$	CL=90%	2341
$\mu^\pm\tau^\mp$	LF	[*gg*] $<$	8.3	$\times 10^{-4}$	CL=90%	2339

$B^\pm/B^0$ ADMIXTURE

The branching fraction measurements are for an admixture of B mesons at the $\Upsilon(4S)$. The values quoted assume that $B(\Upsilon(4S) \to B\overline{B}) = 100\%$.

For inclusive branching fractions, *e.g.*, $B \to D^\pm$ anything, the treatment of multiple D's in the final state must be defined. One possibility would be to count the number of events with one-or-more D's and divide by the total number of B's. Another possibility would be to count the total number of D's and divide by the total number of B's, which is the definition of average multiplicity. The two definitions are identical when only one of the specified particles is allowed in the final state. Even though the "one-or-more" definition seems sensible, for practical reasons inclusive branching fractions are almost always measured using the multiplicity definition. For heavy final state particles, authors call their results inclusive branching fractions while for light particles some authors call their results multiplicities. In the B sections, we list all results as inclusive branching fractions, adopting a multiplicity definition. This means that inclusive branching fractions can exceed 100% and that inclusive partial widths can exceed total widths, just as inclusive cross sections can exceed total cross sections.

$\overline{B}$ modes are charge conjugates of the modes below. Reactions indicate the weak decay vertex and do not include mixing.

B DECAY MODES	Fraction (Γ_i/Γ)		Scale factor/ Confidence level	p (MeV/c)
Semileptonic and leptonic modes				
$B \to e^+\nu_e$ anything	[*ccc*]	(10.41 ± 0.29) %	S=1.2	–
$B \to \overline{p}e^+\nu_e$ anything	$<$	1.6 $\times 10^{-3}$	CL=90%	–
$B \to \mu^+\nu_\mu$ anything	[*ccc*]	(10.3 ± 0.5) %		–
$B \to \ell^+\nu_\ell$ anything	[*pp,ccc*]	(10.45 ± 0.21) %		–
$B \to D^-\ell^+\nu_\ell$ anything	[*pp*]	(2.7 ± 0.8) %		–
$B \to \overline{D}^0\ell^+\nu_\ell$ anything	[*pp*]	(7.0 ± 1.4) %		–
$B \to \overline{D}^{**}\ell^+\nu_\ell$	[*pp,ddd*]	(2.7 ± 0.7) %		–
$B \to \overline{D}_1(2420)\ell^+\nu_\ell$ anything		(7.4 ± 1.6) $\times 10^{-3}$		–
$B \to D\pi\ell^+\nu_\ell$ anything + $D^*\pi\ell^+\nu_\ell$ anything		(2.3 ± 0.4) %		–
$B \to \overline{D}_2^*(2460)\ell^+\nu_\ell$ anything	$<$	6.5 $\times 10^{-3}$	CL=95%	–
$B \to D^{*-}\pi^+\ell^+\nu_\ell$ anything		(1.00 ± 0.34) %		–
$B \to D_s^-\ell^+\nu_\ell$ anything	[*pp*] $<$	9 $\times 10^{-3}$	CL=90%	–
$B \to D_s^-\ell^+\nu_\ell K^+$ anything	[*pp*] $<$	6 $\times 10^{-3}$	CL=90%	–
$B \to D_s^-\ell^+\nu_\ell K^0$ anything	[*pp*] $<$	9 $\times 10^{-3}$	CL=90%	–
$B \to K^+\ell^+\nu_\ell$ anything	[*pp*]	(6.0 ± 0.5) %		–
$B \to K^-\ell^+\nu_\ell$ anything	[*pp*]	(10 ± 4) $\times 10^{-3}$		–
$B \to K^0/\overline{K}^0\ell^+\nu_\ell$ anything	[*pp*]	(4.4 ± 0.5) %		–

D or D^* or D_s modes

$B \to D^{\pm}$ anything		(24.1 ±1.9) %				–
$B \to D^0/\overline{D}{}^0$ anything		(63.1 ±2.9) %			S=1.1	–
$B \to D^*(2010)^{\pm}$ anything		(22.7 ±1.6) %				–
$B \to D^*(2007)^0$ anything		(26.0 ±2.7) %				–
$B \to D_s^{\pm}$ anything	[gg]	(10.0 ±2.5) %				–
$b \to c\bar{c}s$		(22 ±4) %				–
$B \to D_s D$ or $D_s^* D$ or $D_s D^*$ or $D_s^* D^*$	[gg]	(4.9 ±1.3) %				–
$B \to D^*(2010)\gamma$		< 1.1		$\times 10^{-3}$	CL=90%	–
$B \to D_s^+ \pi^-$ or $D_s^{*+} \pi^-$ or $D_s^+ \rho^-$ or $D_s^{*+} \rho^-$ or $D_s^+ \pi^0$ or $D_s^{*+} \pi^0$ or $D_s^+ \eta$ or $D_s^{*+} \eta$ or $D_s^+ \rho^0$ or $D_s^{*+} \rho^0$ or $D_s^+ \omega$ or $D_s^{*+} \omega$	[gg]	< 5		$\times 10^{-4}$	CL=90%	–
$B \to D_{s1}(2536)^+$ anything		< 9.5		$\times 10^{-3}$	CL=90%	–

Charmonium modes

$B \to J/\psi(1S)$ anything		(1.13±0.06) %				–
$B \to J/\psi(1S)$ (direct) anything		(8.0 ±0.8)		$\times 10^{-3}$		–
$B \to \psi(2S)$ anything		(3.5 ±0.5)		$\times 10^{-3}$		–
$B \to \chi_{c1}(1P)$ anything		(4.2 ±0.7)		$\times 10^{-3}$		–
$B \to \chi_{c1}(1P)$ (direct) anything		(3.7 ±0.7)		$\times 10^{-3}$		–
$B \to \chi_{c2}(1P)$ anything		< 3.8		$\times 10^{-3}$	CL=90%	–
$B \to \eta_c(1S)$ anything		< 9		$\times 10^{-3}$	CL=90%	–

K or K^* modes

$B \to K^{\pm}$ anything	[gg]	(78.9 ±2.5) %				–
$B \to K^+$ anything		(66 ±5) %				–
$B \to K^-$ anything		(13 ±4) %				–
$B \to K^0/\overline{K}{}^0$ anything	[gg]	(64 ±4) %				–
$B \to K^*(892)^{\pm}$ anything		(18 ±6) %				–
$B \to K^*(892)^0/\overline{K}{}^*(892)^0$ anything	[gg]	(14.6 ±2.6) %				–
$B \to K_1(1400)\gamma$		< 4.1		$\times 10^{-4}$	CL=90%	–
$B \to K_2^*(1430)\gamma$		< 8.3		$\times 10^{-4}$	CL=90%	–
$B \to K_2(1770)\gamma$		< 1.2		$\times 10^{-3}$	CL=90%	–
$B \to K_3^*(1780)\gamma$		< 3.0		$\times 10^{-3}$	CL=90%	–
$B \to K_4^*(2045)\gamma$		< 1.0		$\times 10^{-3}$	CL=90%	–
$B \to \overline{b} \to \overline{s}\gamma$		(2.3 ±0.7)		$\times 10^{-4}$		–
$B \to \overline{b} \to \overline{s}$ gluon		< 6.8		%	CL=90%	–

Light unflavored meson modes

$B \to \pi^{\pm}$ anything	[gg,eee]	(359 ±7) %				–
$B \to \eta$ anything		(17.6 ±1.6) %				–
$B \to \rho^0$ anything		(21 ±5) %				–
$B \to \omega$ anything		< 81		%	CL=90%	–
$B \to \phi$ anything		(3.5 ±0.7) %			S=1.8	–

Baryon modes

$B \to \Lambda_c^{\pm}$ anything		(6.4 ±1.1) %				–
$B \to \Lambda_c^- e^+$ anything		< 3.2		$\times 10^{-3}$	CL=90%	–
$B \to \Lambda_c^- p$ anything		(3.6 ±0.7) %				–
$B \to \Lambda_c^- p e^+ \nu_e$		< 1.5		$\times 10^{-3}$	CL=90%	–
$B \to \overline{\Sigma}_c^{--}$ anything		(4.2 ±2.4)		$\times 10^{-3}$		–
$B \to \overline{\Sigma}_c^-$ anything		< 9.6		$\times 10^{-3}$	CL=90%	–
$B \to \overline{\Sigma}_c^0$ anything		(4.6 ±2.4)		$\times 10^{-3}$		–
$B \to \overline{\Sigma}_c^0 N (N = p$ or $n)$		< 1.5		$\times 10^{-3}$	CL=90%	–
$B \to \Xi_c^0$ anything $\times$ B($\Xi_c^0 \to \Xi^- \pi^+$)		(1.4 ±0.5)		$\times 10^{-4}$		–
$B \to \Xi_c^+$ anything $\times$ B($\Xi_c^+ \to \Xi^- \pi^+ \pi^+$)		(4.5 $^{+1.3}_{-1.2}$)		$\times 10^{-4}$		–
$B \to p/\overline{p}$ anything	[gg]	(8.0 ±0.4) %				–
$B \to p/\overline{p}$ (direct) anything	[gg]	(5.5 ±0.5) %				–
$B \to \Lambda/\overline{\Lambda}$ anything	[gg]	(4.0 ±0.5) %				–
$B \to \Xi^-/\overline{\Xi}^+$ anything	[gg]	(2.7 ±0.6)		$\times 10^{-3}$		–
$B \to$ baryons anything		(6.8 ±0.6) %				–
$B \to p\overline{p}$ anything		(2.47±0.23) %				–
$B \to \Lambda\overline{p}/\overline{\Lambda}p$ anything	[gg]	(2.5 ±0.4) %				–
$B \to \Lambda\overline{\Lambda}$ anything		< 5		$\times 10^{-3}$	CL=90%	–

Lepton Family number (LF) violating modes or $\Delta B = 1$ weak neutral current ($B1$) modes

$B \to e^+ e^- s$	$B1$	< 5.7		$\times 10^{-5}$	CL=90%	–
$B \to \mu^+ \mu^- s$	$B1$	< 5.8		$\times 10^{-5}$	CL=90%	–
$B \to e^{\pm} \mu^{\mp} s$	LF	< 2.2		$\times 10^{-5}$	CL=90%	–

$B^{\pm}/B^0/B_s^0/b$-baryon ADMIXTURE

These measurements are for an admixture of bottom particles at high energy (LEP, Tevatron, $S\bar{p}pS$).

Mean life $\tau = (1.564 \pm 0.014) \times 10^{-12}$ s

Mean life $\tau = (1.72 \pm 0.10) \times 10^{-12}$ s Charged b-hadron admixture

Mean life $\tau = (1.58 \pm 0.14) \times 10^{-12}$ s Neutral b-hadron admixture

$\tau_{\text{charged } b\text{-hadron}}/\tau_{\text{neutral } b\text{-hadron}} = 1.09 \pm 0.13$

The branching fraction measurements are for an admixture of B mesons and baryons at energies above the $\Upsilon(4S)$. Only the highest energy results (LEP, Tevatron, $S\bar{p}pS$) are used in the branching fraction averages. The production fractions give our best current estimate of the admixture at LEP.

For inclusive branching fractions, *e.g.*, $B \to D^{\pm}$ anything, the treatment of multiple D's in the final state must be defined. One possibility would be to count the number of events with one-or-more D's and divide by the total number of B's. Another possibility would be to count the total number of D's and divide by the total number of B's, which is the definition of average multiplicity. The two definitions are identical when only one of the specified particles is allowed in the final state. Even though the "one-or-more" definition seems sensible, for practical reasons inclusive branching fractions are almost always measured using the multiplicity definition. For heavy final state particles, authors call their results inclusive branching fractions while for light particles some authors call their results multiplicities. In the B sections, we list all results as inclusive branching fractions, adopting a multiplicity definition. This means that inclusive branching fractions can exceed 100% and that inclusive partial widths can exceed total widths, just as inclusive cross sections can exceed total cross sections.

The modes below are listed for a $\overline{b}$ initial state. b modes are their charge conjugates. Reactions indicate the weak decay vertex and do not include mixing.

$\overline{b}$ DECAY MODES	Fraction (Γ_j/Γ)	Confidence level	p (MeV/c)

PRODUCTION FRACTIONS

The production fractions for weakly decaying b-hadrons at the Z have been calculated from the best values of mean lives, mixing parameters, and branching fractions in this edition by the LEP B Oscillation Working Group as described in the note "Production and Decay of b-Flavored Hadrons" in the $B^{\pm}$ Particle Listings. Values assume

$$B(\overline{b} \to B^+) = B(\overline{b} \to B^0)$$
$$B(\overline{b} \to B^+) + B(\overline{b} \to B^0) + B(\overline{b} \to B_s^0) + B(b \to \Lambda_b) = 100\ \%.$$

The notation for production fractions varies in the literature ($f_{B^0} \cdot f(b \to \overline{B}{}^0) \cdot \text{Br}(b \to \overline{B}{}^0)$). We use our own branching fraction notation here: $B(\overline{b} \to B^0)$.

B^+		(39.7 $^{+\ 1.8}_{-\ 2.2}$) %	–
B^0		(39.7 $^{+\ 1.8}_{-\ 2.2}$) %	–
B_s^0		(10.5 $^{+\ 1.8}_{-\ 1.7}$) %	–
Λ_b		(10.1 $^{+\ 3.9}_{-\ 3.1}$) %	–

DECAY MODES

Semileptonic and leptonic modes

ν anything		(23.1 ± 1.5) %		–
$\ell^+ \nu_\ell$ anything	[pp,ccc]	(10.99± 0.23) %		–
$e^+ \nu_e$ anything	[ccc]	(10.9 ± 0.5) %		–
$\mu^+ \nu_\mu$ anything	[ccc]	(10.8 ± 0.5) %		–
$D^- \ell^+ \nu_\ell$ anything	[pp]	(2.02± 0.29) %		–
$\overline{D}{}^0 \ell^+ \nu_\ell$ anything	[pp]	(6.5 ± 0.6) %		–
$D^{*-} \ell^+ \nu_\ell$ anything	[pp]	(2.76± 0.29) %		–
$\overline{D}{}_j^0 \ell^+ \nu_\ell$ anything	[pp,fff]	seen		–
$\overline{D}{}_j^- \ell^+ \nu_\ell$ anything	[pp,fff]	seen		–
$\overline{D}{}_2^*(2460)^0 \ell^+ \nu_\ell$ anything		seen		–
$D_2^*(2460)^- \ell^+ \nu_\ell$ anything		seen		–
$\tau^+ \nu_\tau$ anything		(2.6 ± 0.4) %		–
$\overline{c} \to \ell^- \overline{\nu}_\ell$ anything	[pp]	(7.8 ± 0.6) %		–

Charmed meson and baryon modes					
$\overline{D}^0$ anything		(60.1 ± 3.2) %			–
D^- anything		(23.7 ± 2.3) %			–
$\overline{D}_s$ anything		(18 ± 5) %			–
Λ_c anything		(9.7 ± 2.9) %			–
$\overline{c}/c$ anything	[eee]	(117 ± 4) %			–
Charmonium modes					
$J/\psi(1S)$ anything		(1.16± 0.10) %			–
$\psi(2S)$ anything		(4.8 ± 2.4) $\times 10^{-3}$			–
$\chi_{c1}(1P)$ anything		(1.8 ± 0.5) %			–
K* or *K* **modes**					
$\overline{s}\gamma$		< 5.4	$\times 10^{-4}$	90%	–
$K^\pm$ anything		(88 ±19) %			–
K^0_S anything		(29.0 ± 2.9) %			–
Pion modes					
π^0 anything	[eee]	(278 ±60) %			–
Baryon modes					
$p/\overline{p}$ anything		(14 ± 6) %			–
Other modes					
charged anything	[eee]	(497 ± 7) %			–
hadron$^+$ hadron$^-$		(1.7 $^{+\ 1.0}_{-\ 0.7}$) $\times 10^{-5}$			–
charmless		(7 ±21) $\times 10^{-3}$			–
Baryon modes					
$\Lambda/\overline{\Lambda}$ anything		(5.9 ± 0.6) %			–
$\Delta B = 1$ weak neutral current (*B1*) modes					
$\mu^+\mu^-$ anything	*B1*	< 3.2	$\times 10^{-4}$	90%	–

B^*

$I(J^P) = \frac{1}{2}(1^-)$

I, *J*, *P* need confirmation. Quantum numbers shown are quark-model predictions.

Mass $m_{B^*} = 5324.9 \pm 1.8$ MeV

$m_{B^*} - m_B = 45.78 \pm 0.35$ MeV

B^* DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$B\gamma$	dominant	46

BOTTOM, STRANGE MESONS ($B = \pm 1, S = \mp 1$)

$B^0_s = s\overline{b}$, $\overline{B}^0_s = \overline{s}b$; similarly for $B^{*\prime}_s$s

B^0_s

$I(J^P) = 0(0^-)$

I, *J*, *P* need confirmation. Quantum numbers shown are quark-model predictions.

Mass $m_{B^0_s} = 5369.3 \pm 2.0$ MeV

Mean life $\tau = (1.54 \pm 0.07) \times 10^{-12}$ s

$c\tau = 462\ \mu$m

B^0_s-$\overline{B}^0_s$ mixing parameters

χ_B at high energy $= f_d\chi_d + f_s\chi_s = 0.118 \pm 0.006$

$\Delta m_{B^0_s} = m_{B^0_{sH}} - m_{B^0_{sL}} > 9.1 \times 10^{12}\ \hbar\ \mathrm{s}^{-1}$ CL = 95%

$x_s = \Delta m_{B^0_s}/\Gamma_{B^0_s} > 14.0$ CL = 95%

$\chi_s > 0.4975$ CL = 95%

These branching fractions all scale with $B(\overline{b} \to B^0_s)\Gamma$ the LEP B^0_s production fraction. The first four were evaluated using $B(\overline{b} \to B^0_s) = (10.5^{+1.8}_{-1.7})\%$ and the rest assume $B(\overline{b} \to B^0_s) = 12\%$.

The branching fraction $B(B^0_s \to D^-_s \ell^+\nu_\ell \text{anything})$ is not a pure measurement since the measured product branching fraction $B(\overline{b} \to B^0_s) \times B(B^0_s \to D^-_s \ell^+\nu_\ell \text{anything})$ was used to determine $B(\overline{b} \to B^0_s)\Gamma$ as described in the note on "Production and Decay of b-Flavored Hadrons."

B^0_s DECAY MODES		Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
D^-_s anything		(92 ±33) %		–
$D^-_s \ell^+\nu_\ell$ anything	[ggg]	(8.1 ± 2.5) %		–
$D^-_s\pi^+$		< 13 %		2321
$J/\psi(1S)\phi$		(9.3 ± 3.3) $\times 10^{-4}$		1590
$J/\psi(1S)\pi^0$		< 1.2 $\times 10^{-3}$	90%	1788
$J/\psi(1S)\eta$		< 3.8 $\times 10^{-3}$	90%	1735
$\psi(2S)\phi$		seen		1122
$\pi^+\pi^-$		< 1.7 $\times 10^{-4}$	90%	1122
$\pi^0\pi^0$		< 2.1 $\times 10^{-4}$	90%	2861
$\eta\pi^0$		< 1.0 $\times 10^{-3}$	90%	2655
$\eta\eta$		< 1.5 $\times 10^{-3}$	90%	2628
π^+K^-		< 2.1 $\times 10^{-4}$	90%	2660
K^+K^-		< 5.9 $\times 10^{-5}$	90%	2639
$p\overline{p}$		< 5.9 $\times 10^{-5}$	90%	2515
$\gamma\gamma$		< 1.48 $\times 10^{-4}$	90%	2685
$\phi\gamma$		< 7 $\times 10^{-4}$	90%	2588
Lepton Family number (*LF*) violating modes or $\Delta B = 1$ weak neutral current (*B1*) modes				
$\mu^+\mu^-$	*B1*	< 2.0 $\times 10^{-6}$	90%	2682
e^+e^-	*B1*	< 5.4 $\times 10^{-5}$	90%	2864
$e^\pm\mu^\mp$	*LF*	[gg] < 4.1 $\times 10^{-5}$	90%	2864
$\phi\nu\overline{\nu}$	*B1*	< 5.4 $\times 10^{-3}$	90%	–

$c\bar{c}$ MESONS

$\eta_c(1S)$ $I^G(J^{PC}) = 0^+(0^{-+})$

Mass $m = 2979.8 \pm 2.1$ MeV (S = 2.1)
Full width $\Gamma = 13.2^{+3.8}_{-3.2}$ MeV

$\eta_c(1S)$ DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
Decays involving hadronic resonances			
$\eta'(958)\pi\pi$	(4.1 ±1.7) %		1319
$\rho\rho$	(2.6 ±0.9) %		1275
$K^*(892)^0 K^- \pi^+$ + c.c.	(2.0 ±0.7) %		1273
$K^*(892)\overline{K}^*(892)$	(8.5 ±3.1) × 10^{-3}		1193
$\phi\phi$	(7.1 ±2.8) × 10^{-3}		1086
$a_0(980)\pi$	< 2 %	90%	1323
$a_2(1320)\pi$	< 2 %	90%	1193
$K^*(892)\overline{K}$ + c.c.	< 1.28 %	90%	1307
$f_2(1270)\eta$	< 1.1 %	90%	1142
$\omega\omega$	< 3.1 × 10^{-3}	90%	1268
Decays into stable hadrons			
$K\overline{K}\pi$	(5.5 ±1.7) %		1378
$\eta\pi\pi$	(4.9 ±1.8) %		1425
$\pi^+\pi^- K^+ K^-$	(2.0 $^{+0.7}_{-0.6}$) %		1342
$2(K^+K^-)$	(2.1 ±1.2) %		1053
$2(\pi^+\pi^-)$	(1.2 ±0.4) %		1457
$p\bar{p}$	(1.2 ±0.4) × 10^{-3}		1157
$K\overline{K}\eta$	< 3.1 %	90%	1262
$\pi^+\pi^- p\bar{p}$	< 1.2 %	90%	1023
$\Lambda\overline{\Lambda}$	< 2 × 10^{-3}	90%	987
Radiative decays			
$\gamma\gamma$	(3.0 ±1.2) × 10^{-4}		1489

$J/\psi(1S)$ $I^G(J^{PC}) = 0^-(1^{--})$

Mass $m = 3096.88 \pm 0.04$ MeV
Full width $\Gamma = 87 \pm 5$ keV
$\Gamma_{ee} = 5.26 \pm 0.37$ keV (Assuming $\Gamma_{ee} = \Gamma_{\mu\mu}$)

$J/\psi(1S)$ DECAY MODES		Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
hadrons		(87.7 ±0.5) %		–
virtual $\gamma \to$ hadrons		(17.0 ±2.0) %		–
e^+e^-		(6.02±0.19) %		1548
$\mu^+\mu^-$		(6.01±0.19) %		1545
Decays involving hadronic resonances				
$\rho\pi$		(1.27±0.09) %		1449
$\rho^0\pi^0$		(4.2 ±0.5) × 10^{-3}		1449
$a_2(1320)\rho$		(1.09±0.22) %		1125
$\omega\pi^+\pi^+\pi^-\pi^-$		(8.5 ±3.4) × 10^{-3}		1392
$\omega\pi^+\pi^-$		(7.2 ±1.0) × 10^{-3}		1435
$\omega f_2(1270)$		(4.3 ±0.6) × 10^{-3}		1143
$K^*(892)^0\overline{K}_2^*(1430)^0$ + c.c.		(6.7 ±2.6) × 10^{-3}		1005
$\omega K^*(892)\overline{K}$ + c.c.		(5.3 ±2.0) × 10^{-3}		1098
$K^+\overline{K}^*(892)^-$ + c.c.		(5.0 ±0.4) × 10^{-3}		1373
$K^0\overline{K}^*(892)^0$ + c.c.		(4.2 ±0.4) × 10^{-3}		1371
$\omega\pi^0\pi^0$		(3.4 ±0.8) × 10^{-3}		1436
$b_1(1235)^\pm\pi^\mp$	[gg]	(3.0 ±0.5) × 10^{-3}		1299
$\omega K^\pm K_S^0\pi^\mp$	[gg]	(3.0 ±0.7) × 10^{-3}		1210
$b_1(1235)^0\pi^0$		(2.3 ±0.6) × 10^{-3}		1299
$\phi K^*(892)\overline{K}$ + c.c.		(2.04±0.28) × 10^{-3}		969
$\omega K\overline{K}$		(1.9 ±0.4) × 10^{-3}		1268
$\omega f_J(1710) \to \omega K\overline{K}$		(4.8 ±1.1) × 10^{-4}		878
$\phi 2(\pi^+\pi^-)$		(1.60±0.32) × 10^{-3}		1318
$\Delta(1232)^{++}\bar{p}\pi^-$		(1.6 ±0.5) × 10^{-3}		1030
$\omega\eta$		(1.58±0.16) × 10^{-3}		1394
$\phi K\overline{K}$		(1.48±0.22) × 10^{-3}		1179
$\phi f_J(1710) \to \phi K\overline{K}$		(3.6 ±0.6) × 10^{-4}		875
$p\bar{p}\omega$		(1.30±0.25) × 10^{-3}	S=1.3	769
$\Delta(1232)^{++}\overline{\Delta}(1232)^{--}$		(1.10±0.29) × 10^{-3}		938
$\Sigma(1385)^-\overline{\Sigma}(1385)^+$ (or c.c.)	[gg]	(1.03±0.13) × 10^{-3}		692
$p\bar{p}\eta'(958)$		(9 ±4) × 10^{-4}	S=1.7	596
$\phi f_2'(1525)$		(8 ±4) × 10^{-4}	S=2.7	871
$\phi\pi^+\pi^-$		(8.0 ±1.2) × 10^{-4}		1365
$\phi K^\pm K_S^0\pi^\mp$	[gg]	(7.2 ±0.9) × 10^{-4}		1114
$\omega f_1(1420)$		(6.8 ±2.4) × 10^{-4}		1062
$\phi\eta$		(6.5 ±0.7) × 10^{-4}		1320
$\Xi(1530)^-\bar{\Xi}^+$		(5.9 ±1.5) × 10^{-4}		597
$pK^-\overline{\Sigma}(1385)^0$		(5.1 ±3.2) × 10^{-4}		645
$\omega\pi^0$		(4.2 ±0.6) × 10^{-4}	S=1.4	1447
$\phi\eta'(958)$		(3.3 ±0.4) × 10^{-4}		1192
$\phi f_0(980)$		(3.2 ±0.9) × 10^{-4}	S=1.9	1182
$\Xi(1530)^0\bar{\Xi}^0$		(3.2 ±1.4) × 10^{-4}		608
$\Sigma(1385)^-\bar{\Sigma}^+$ (or c.c.)	[gg]	(3.1 ±0.5) × 10^{-4}		857
$\phi f_1(1285)$		(2.6 ±0.5) × 10^{-4}	S=1.1	1032
$\rho\eta$		(1.93±0.23) × 10^{-4}		1398
$\omega\eta'(958)$		(1.67±0.25) × 10^{-4}		1279
$\omega f_0(980)$		(1.4 ±0.5) × 10^{-4}		1271
$\rho\eta'(958)$		(1.05±0.18) × 10^{-4}		1283
$p\bar{p}\phi$		(4.5 ±1.5) × 10^{-5}		527
$a_2(1320)^\pm\pi^\mp$	[gg]	< 4.3 × 10^{-3}	CL=90%	1263
$K\overline{K}_2^*(1430)$ + c.c.		< 4.0 × 10^{-3}	CL=90%	1159
$K_2^*(1430)^0\overline{K}_2^*(1430)^0$		< 2.9 × 10^{-3}	CL=90%	588
$K^*(892)^0\overline{K}^*(892)^0$		< 5 × 10^{-4}	CL=90%	1263
$\phi f_2(1270)$		< 3.7 × 10^{-4}	CL=90%	1036
$p\bar{p}\rho$		< 3.1 × 10^{-4}	CL=90%	779
$\phi\eta(1440) \to \phi\eta\pi\pi$		< 2.5 × 10^{-4}	CL=90%	946
$\omega f_2'(1525)$		< 2.2 × 10^{-4}	CL=90%	1003
$\Sigma(1385)^0\overline{\Lambda}$		< 2 × 10^{-4}	CL=90%	911
$\Delta(1232)^+\bar{p}$		< 1 × 10^{-4}	CL=90%	1100
$\Sigma^0\overline{\Lambda}$		< 9 × 10^{-5}	CL=90%	1032
$\phi\pi^0$		< 6.8 × 10^{-6}	CL=90%	1377
Decays into stable hadrons				
$2(\pi^+\pi^-)\pi^0$		(3.37±0.26) %		1496
$3(\pi^+\pi^-)\pi^0$		(2.9 ±0.6) %		1433
$\pi^+\pi^-\pi^0$		(1.50±0.20) %		1533
$\pi^+\pi^-\pi^0 K^+K^-$		(1.20±0.30) %		1368
$4(\pi^+\pi^-)\pi^0$		(9.0 ±3.0) × 10^{-3}		1345
$\pi^+\pi^- K^+K^-$		(7.2 ±2.3) × 10^{-3}		1407
$K\overline{K}\pi$		(6.1 ±1.0) × 10^{-3}		1440
$p\bar{p}\pi^+\pi^-$		(6.0 ±0.5) × 10^{-3}	S=1.3	1107
$2(\pi^+\pi^-)$		(4.0 ±1.0) × 10^{-3}		1517
$3(\pi^+\pi^-)$		(4.0 ±2.0) × 10^{-3}		1466
$n\bar{n}\pi^+\pi^-$		(4 ±4) × 10^{-3}		1106
$\Sigma^0\overline{\Sigma}^0$		(1.27±0.17) × 10^{-3}		992
$2(\pi^+\pi^-)K^+K^-$		(3.1 ±1.3) × 10^{-3}		1320
$p\bar{p}\pi^+\pi^-\pi^0$	[hhh]	(2.3 ±0.9) × 10^{-3}	S=1.9	1033
$p\bar{p}$		(2.14±0.10) × 10^{-3}		1232
$p\bar{p}\eta$		(2.09±0.18) × 10^{-3}		948
$p\bar{n}\pi^-$		(2.00±0.10) × 10^{-3}		1174
$n\bar{n}$		(1.9 ±0.5) × 10^{-3}		1231
$\Xi\bar{\Xi}$		(1.8 ±0.4) × 10^{-3}	S=1.8	818
$\Lambda\overline{\Lambda}$		(1.35±0.14) × 10^{-3}	S=1.2	1074
$p\bar{p}\pi^0$		(1.09±0.09) × 10^{-3}		1176
$\Lambda\overline{\Sigma}^-\pi^+$ (or c.c.)	[gg]	(1.06±0.12) × 10^{-3}		945
$pK^-\overline{\Lambda}$		(8.9 ±1.6) × 10^{-4}		876
$2(K^+K^-)$		(7.0 ±3.0) × 10^{-4}		1131
$pK^-\overline{\Sigma}^0$		(2.9 ±0.8) × 10^{-4}		820
K^+K^-		(2.37±0.31) × 10^{-4}		1468
$\Lambda\overline{\Lambda}\pi^0$		(2.2 ±0.7) × 10^{-4}		998
$\pi^+\pi^-$		(1.47±0.23) × 10^{-4}		1542
$K_S^0K_L^0$		(1.08±0.14) × 10^{-4}		1466
$\Lambda\overline{\Sigma}$ + c.c.		< 1.5 × 10^{-4}	CL=90%	1032
$K_S^0K_S^0$		< 5.2 × 10^{-6}	CL=90%	1466
Radiative decays				
$\gamma\eta_c(1S)$		(1.3 ±0.4) %		116
$\gamma\pi^+\pi^-2\pi^0$		(8.3 ±3.1) × 10^{-3}		1518
$\gamma\eta\pi\pi$		(6.1 ±1.0) × 10^{-3}		1487
$\gamma\eta(1440) \to \gamma K\overline{K}\pi$	[p]	(9.1 ±1.8) × 10^{-4}		1223
$\gamma\eta(1440) \to \gamma\gamma\rho^0$		(6.4 ±1.4) × 10^{-5}		1223
$\gamma\eta(1440) \to \gamma\eta\pi^+\pi^-$		(3.4 ±0.7) × 10^{-4}		–
$\gamma\rho\rho$		(4.5 ±0.8) × 10^{-3}		1343
$\gamma\eta'(958)$		(4.31±0.30) × 10^{-3}		1400
$\gamma 2\pi^+2\pi^-$		(2.8 ±0.5) × 10^{-3}	S=1.9	1517
$\gamma f_4(2050)$		(2.7 ±0.7) × 10^{-3}		874
$\gamma\omega\omega$		(1.59±0.33) × 10^{-3}		1337
$\gamma\eta(1440) \to \gamma\rho^0\rho^0$		(1.7 ±0.4) × 10^{-3}	S=1.3	1223
$\gamma f_2(1270)$		(1.38±0.14) × 10^{-3}		1286
$\gamma f_J(1710) \to \gamma K\overline{K}$		(8.5 $^{+1.2}_{-0.9}$) × 10^{-4}	S=1.2	1075

$\gamma\eta$	$(\ 8.6\ \pm0.8\ )\times10^{-4}$			1500
$\gamma f_1(1420) \rightarrow\ \gamma K\overline{K}\pi$	$(\ 8.3\ \pm1.5\ )\times10^{-4}$			1220
$\gamma f_1(1285)$	$(\ 6.5\ \pm1.0\ )\times10^{-4}$			1283
$\gamma f_2'(1525)$	$(\ 4.7\ ^{+0.7}_{-0.5}\ )\times10^{-4}$			1173
$\gamma\phi\phi$	$(\ 4.0\ \pm1.2\ )\times10^{-4}$		S=2.1	1166
$\gamma p\overline{p}$	$(\ 3.8\ \pm1.0\ )\times10^{-4}$			1232
$\gamma\eta(2225)$	$(\ 2.9\ \pm0.6\ )\times10^{-4}$			834
$\gamma\eta(1760) \rightarrow\ \gamma\rho^0\rho^0$	$(\ 1.3\ \pm0.9\ )\times10^{-4}$			1048
$\gamma\pi^0$	$(\ 3.9\ \pm1.3\ )\times10^{-5}$			1546
$\gamma p\overline{p}\pi^+\pi^-$	$<\ 7.9\ \times10^{-4}$		CL=90%	1107
$\gamma\gamma$	$<\ 5\ \times10^{-4}$		CL=90%	1548
$\gamma\Lambda\overline{\Lambda}$	$<\ 1.3\ \times10^{-4}$		CL=90%	1074
3γ	$<\ 5.5\ \times10^{-5}$		CL=90%	1548
$\gamma f_J(2220)$	$>\ 2.50\ \times10^{-3}$		CL=99.9%	–
$\gamma f_0(1500)$	$(\ 5.7\ \pm0.8\ )\times10^{-4}$			1184
γe^+e^-	$(\ 8.8\ \pm1.4\ )\times10^{-3}$			–

$\chi_{c0}(1P)$ $I^G(J^{PC}) = 0^+(0^{++})$

Mass $m = 3417.3 \pm 2.8$ MeV
Full width $\Gamma = 14 \pm 5$ MeV

$\chi_{c0}(1P)$ DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
Hadronic decays			
$2(\pi^+\pi^-)$	$(3.7\pm0.7)\ \%$		1679
$\pi^+\pi^-K^+K^-$	$(3.0\pm0.7)\ \%$		1580
$\rho^0\pi^+\pi^-$	$(1.6\pm0.5)\ \%$		1608
$3(\pi^+\pi^-)$	$(1.5\pm0.5)\ \%$		1633
$K^+\overline{K}^*(892)^0\pi^- + \text{c.c.}$	$(1.2\pm0.4)\ \%$		1522
$\pi^+\pi^-$	$(7.5\pm2.1)\times10^{-3}$		1702
K^+K^-	$(7.1\pm2.4)\times10^{-3}$		1635
$\pi^+\pi^-p\overline{p}$	$(5.0\pm2.0)\times10^{-3}$		1320
$p\overline{p}$	$<9.0\ \times10^{-4}$	90%	1427
Radiative decays			
$\gamma J/\psi(1S)$	$(6.6\pm1.8)\times10^{-3}$		303
$\gamma\gamma$	$<5\ \times10^{-4}$	95%	1708

$\chi_{c1}(1P)$ $I^G(J^{PC}) = 0^+(1^{++})$

Mass $m = 3510.53 \pm 0.12$ MeV
Full width $\Gamma = 0.88 \pm 0.14$ MeV

$\chi_{c1}(1P)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
Hadronic decays		
$3(\pi^+\pi^-)$	$(2.2\pm0.8)\ \%$	1683
$2(\pi^+\pi^-)$	$(1.6\pm0.5)\ \%$	1727
$\pi^+\pi^-K^+K^-$	$(9\ \pm4\ )\times10^{-3}$	1632
$\rho^0\pi^+\pi^-$	$(3.9\pm3.5)\times10^{-3}$	1659
$K^+\overline{K}^*(892)^0\pi^- + \text{c.c.}$	$(3.2\pm2.1)\times10^{-3}$	1576
$\pi^+\pi^-p\overline{p}$	$(1.4\pm0.9)\times10^{-3}$	1381
$p\overline{p}$	$(8.6\pm1.2)\times10^{-5}$	1483
$\pi^+\pi^- +\ K^+K^-$	$<2.1\ \times10^{-3}$	–
Radiative decays		
$\gamma J/\psi(1S)$	$(27.3\pm1.6)\ \%$	389

$\chi_{c2}(1P)$ $I^G(J^{PC}) = 0^+(2^{++})$

Mass $m = 3556.17 \pm 0.13$ MeV
Full width $\Gamma = 2.00 \pm 0.18$ MeV

$\chi_{c2}(1P)$ DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
Hadronic decays			
$2(\pi^+\pi^-)$	$(2.2\pm0.5)\ \%$		1751
$\pi^+\pi^-K^+K^-$	$(1.9\pm0.5)\ \%$		1656
$3(\pi^+\pi^-)$	$(1.2\pm0.8)\ \%$		1707
$\rho^0\pi^+\pi^-$	$(7\ \pm4\ )\times10^{-3}$		1683
$K^+\overline{K}^*(892)^0\pi^- + \text{c.c.}$	$(4.8\pm2.8)\times10^{-3}$		1601
$\pi^+\pi^-p\overline{p}$	$(3.3\pm1.3)\times10^{-3}$		1410
$\pi^+\pi^-$	$(1.9\pm1.0)\times10^{-3}$		1773
K^+K^-	$(1.5\pm1.1)\times10^{-3}$		1708
$p\overline{p}$	$(10.0\pm1.0)\times10^{-5}$		1510
$J/\psi(1S)\pi^+\pi^-\pi^0$	$<1.5\ \%$	90%	185
Radiative decays			
$\gamma J/\psi(1S)$	$(13.5\pm1.1)\ \%$		430
$\gamma\gamma$	$(\ 1.6\pm0.5)\times10^{-4}$		1778

$\psi(2S)$ $I^G(J^{PC}) = 0^-(1^{--})$

Mass $m = 3686.00 \pm 0.09$ MeV
Full width $\Gamma = 277 \pm 31$ keV (S = 1.1)
$\Gamma_{ee} = 2.14 \pm 0.21$ keV (Assuming $\Gamma_{ee} = \Gamma_{\mu\mu}$)

$\psi(2S)$ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
hadrons	$(98.10\pm0.30)\ \%$		–
virtual$\gamma \rightarrow$ hadrons	$(\ 2.9\ \pm0.4\ )\ \%$		–
e^+e^-	$(\ 8.5\ \pm0.7\ )\times10^{-3}$		1843
$\mu^+\mu^-$	$(\ 7.7\ \pm1.7\ )\times10^{-3}$		1840
Decays into $J/\psi(1S)$ and anything			
$J/\psi(1S)$anything	$(54.2\ \pm3.0\ )\ \%$		–
$J/\psi(1S)$neutrals	$(22.8\ \pm1.7\ )\ \%$		–
$J/\psi(1S)\pi^+\pi^-$	$(30.2\ \pm1.9\ )\ \%$		477
$J/\psi(1S)\pi^0\pi^0$	$(17.9\ \pm1.8\ )\ \%$		481
$J/\psi(1S)\eta$	$(\ 2.7\ \pm0.4\ )\ \%$	S=1.7	200
$J/\psi(1S)\pi^0$	$(\ 9.7\ \pm2.1\ )\times10^{-4}$		527
$J/\psi(1S)\mu^+\mu^-$	$(10.0\ \pm3.3\ )\times10^{-3}$		–
Hadronic decays			
$3(\pi^+\pi^-)\pi^0$	$(\ 3.5\ \pm1.6\ )\times10^{-3}$		1746
$2(\pi^+\pi^-)\pi^0$	$(\ 3.0\ \pm0.8\ )\times10^{-3}$		1799
$\pi^+\pi^-K^+K^-$	$(\ 1.6\ \pm0.4\ )\times10^{-3}$		1726
$\pi^+\pi^-p\overline{p}$	$(\ 8.0\ \pm2.0\ )\times10^{-4}$		1491
$K^+\overline{K}^*(892)^0\pi^- + \text{c.c.}$	$(\ 6.7\ \pm2.5\ )\times10^{-4}$		1673
$2(\pi^+\pi^-)$	$(\ 4.5\ \pm1.0\ )\times10^{-4}$		1817
$\rho^0\pi^+\pi^-$	$(\ 4.2\ \pm1.5\ )\times10^{-4}$		1751
$p\overline{p}$	$(\ 1.9\ \pm0.5\ )\times10^{-4}$		1586
$3(\pi^+\pi^-)$	$(\ 1.5\ \pm1.0\ )\times10^{-4}$		1774
$p\overline{p}\pi^0$	$(\ 1.4\ \pm0.5\ )\times10^{-4}$		1543
K^+K^-	$(\ 1.0\ \pm0.7\ )\times10^{-4}$		1776
$\pi^+\pi^-\pi^0$	$(\ 9\ \pm5\ )\times10^{-5}$		1830
$\rho\pi$	$<8.3\ \times10^{-5}$	CL=90%	1760
$\pi^+\pi^-$	$(\ 8\ \pm5\ )\times10^{-5}$		1838
$\Lambda\overline{\Lambda}$	$<4\ \times10^{-4}$	CL=90%	1467
$\Xi^-\overline{\Xi}^+$	$<2\ \times10^{-4}$	CL=90%	1285
$K^+K^-\pi^0$	$<2.96\ \times10^{-5}$	CL=90%	1754
$K^+\overline{K}^*(892)^- + \text{c.c.}$	$<5.4\ \times10^{-5}$	CL=90%	1698
Radiative decays			
$\gamma\chi_{c0}(1P)$	$(\ 9.3\ \pm0.9\ )\ \%$		261
$\gamma\chi_{c1}(1P)$	$(\ 8.7\ \pm0.8\ )\ \%$		171
$\gamma\chi_{c2}(1P)$	$(\ 7.8\ \pm0.8\ )\ \%$		127
$\gamma\eta_c(1S)$	$(\ 2.8\ \pm0.6\ )\times10^{-3}$		639
$\gamma\eta'(958)$	$<1.1\ \times10^{-3}$	CL=90%	1719
$\gamma\gamma$	$<1.6\ \times10^{-4}$	CL=90%	1843
$\gamma\eta(1440) \rightarrow\ \gamma K\overline{K}\pi$	$<1.2\ \times10^{-4}$	CL=90%	1569

$\psi(3770)$ $I^G(J^{PC}) = ?^?(1^{--})$

Mass $m = 3769.9 \pm 2.5$ MeV (S = 1.8)
Full width $\Gamma = 23.6 \pm 2.7$ MeV (S = 1.1)
$\Gamma_{ee} = 0.26 \pm 0.04$ keV (S = 1.2)

$\psi(3770)$ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor	p (MeV/c)
$D\overline{D}$	dominant		242
e^+e^-	$(1.12\pm0.17)\times10^{-5}$	1.2	1885

$\psi(4040)$ [iii] $I^G(J^{PC}) = ?^?(1^{--})$

Mass $m = 4040 \pm 10$ MeV
Full width $\Gamma = 52 \pm 10$ MeV
$\Gamma_{ee} = 0.75 \pm 0.15$ keV

$\psi(4040)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
e^+e^-	$(1.4\pm0.4)\times10^{-5}$	2020
$D^0\overline{D}^0$	seen	777
$D^*(2007)^0\overline{D}^0 + \text{c.c.}$	seen	578
$D^*(2007)^0\overline{D}^*(2007)^0$	seen	232

$\psi(4160)$ [iii] $I^G(J^{PC}) = ?^?(1^{--})$

Mass $m = 4159 \pm 20$ MeV
Full width $\Gamma = 78 \pm 20$ MeV
$\Gamma_{ee} = 0.77 \pm 0.23$ keV

$\psi(4160)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
e^+e^-	$(10\pm4)\times10^{-6}$	2079

$\psi(4415)$ [iii] $I^G(J^{PC}) = ?^?(1^{--})$

Mass $m = 4415 \pm 6$ MeV
Full width $\Gamma = 43 \pm 15$ MeV (S = 1.8)
$\Gamma_{ee} = 0.47 \pm 0.10$ keV

$\psi(4415)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
hadrons	dominant	–
e^+e^-	$(1.1\pm0.4)\times10^{-5}$	2207

$b\bar{b}$ MESONS

$\Upsilon(1S)$ $I^G(J^{PC}) = 0^-(1^{--})$

Mass $m = 9460.37 \pm 0.21$ MeV (S = 2.7)
Full width $\Gamma = 52.5 \pm 1.8$ keV
$\Gamma_{ee} = 1.32 \pm 0.05$ keV

$\Upsilon(1S)$ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
$\tau^+\tau^-$	$(2.67^{+0.14}_{-0.16})$ %		4384
e^+e^-	(2.52±0.17) %		4730
$\mu^+\mu^-$	(2.48±0.07) %	S=1.1	4729
Hadronic decays			
$J/\psi(1S)$anything	$(1.1\pm0.4)\times10^{-3}$		4223
$\rho\pi$	$< 2 \times10^{-4}$	CL=90%	4698
$\pi^+\pi^-$	$< 5 \times10^{-4}$	CL=90%	4728
K^+K^-	$< 5 \times10^{-4}$	CL=90%	4704
$p\bar{p}$	$< 5 \times10^{-4}$	CL=90%	4636
Radiative decays			
$\gamma 2h^+2h^-$	$(7.0\pm1.5)\times10^{-4}$		4720
$\gamma 3h^+3h^-$	$(5.4\pm2.0)\times10^{-4}$		4703
$\gamma 4h^+4h^-$	$(7.4\pm3.5)\times10^{-4}$		4679
$\gamma\pi^+\pi^-K^+K^-$	$(2.9\pm0.9)\times10^{-4}$		4686
$\gamma 2\pi^+2\pi^-$	$(2.5\pm0.9)\times10^{-4}$		4720
$\gamma 3\pi^+3\pi^-$	$(2.5\pm1.2)\times10^{-4}$		4703
$\gamma 2\pi^+2\pi^-K^+K^-$	$(2.4\pm1.2)\times10^{-4}$		4658
$\gamma\pi^+\pi^-p\bar{p}$	$(1.5\pm0.6)\times10^{-4}$		4604
$\gamma 2\pi^+2\pi^-p\bar{p}$	$(4\pm6)\times10^{-5}$		4563
$\gamma 2K^+2K^-$	$(2.0\pm2.0)\times10^{-5}$		4601
$\gamma\eta'(958)$	$< 1.3 \times10^{-3}$	CL=90%	4682
$\gamma\eta$	$< 3.5 \times10^{-4}$	CL=90%	4714
$\gamma f_2'(1525)$	$< 1.4 \times10^{-4}$	CL=90%	4607
$\gamma f_2(1270)$	$< 1.3 \times10^{-4}$	CL=90%	4644
$\gamma\eta(1440)$	$< 8.2 \times10^{-5}$	CL=90%	4624
$\gamma f_J(1710) \to \gamma K\bar{K}$	$< 2.6 \times10^{-4}$	CL=90%	4576
$\gamma f_0(2200) \to \gamma K^+K^-$	$< 2 \times10^{-4}$	CL=90%	4475
$\gamma f_J(2220) \to \gamma K^+K^-$	$< 1.5 \times10^{-5}$	CL=90%	4469
$\gamma\eta(2225) \to \gamma\phi\phi$	$< 3 \times10^{-3}$	CL=90%	4469
γX	$< 3 \times10^{-5}$	CL=90%	–
X = pseudoscalar with m< 7.2 GeV)			
$\gamma X\overline{X}$	$< 1 \times10^{-3}$	CL=90%	–
$X\overline{X}$ = vectors with m< 3.1 GeV)			

$\chi_{b0}(1P)$ [iii] $I^G(J^{PC}) = 0^+(0^{++})$
J needs confirmation.

Mass $m = 9859.8 \pm 1.3$ MeV

$\chi_{b0}(1P)$ DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$\gamma\Upsilon(1S)$	<6 %	90%	391

$\chi_{b1}(1P)$ [iii] $I^G(J^{PC}) = 0^+(1^{++})$
J needs confirmation.

Mass $m = 9891.9 \pm 0.7$ MeV

$\chi_{b1}(1P)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\gamma\Upsilon(1S)$	(35±8) %	422

$\chi_{b2}(1P)$ [iii] $I^G(J^{PC}) = 0^+(2^{++})$
J needs confirmation.

Mass $m = 9913.2 \pm 0.6$ MeV

$\chi_{b2}(1P)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\gamma\Upsilon(1S)$	(22±4) %	443

$\Upsilon(2S)$ $I^G(J^{PC}) = 0^-(1^{--})$

Mass $m = 10.02330 \pm 0.00031$ GeV
Full width $\Gamma = 44 \pm 7$ keV
$\Gamma_{ee} = 0.520 \pm 0.032$ keV

$\Upsilon(2S)$ DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$\Upsilon(1S)\pi^+\pi^-$	(18.5 ±0.8) %		475
$\Upsilon(1S)\pi^0\pi^0$	(8.8 ±1.1) %		480
$\tau^+\tau^-$	(1.7 ±1.6) %		4686
$\mu^+\mu^-$	(1.31±0.21) %		5011
e^+e^-	(1.18±0.20) %		5012
$\Upsilon(1S)\pi^0$	$< 8 \times10^{-3}$	90%	531
$\Upsilon(1S)\eta$	$< 2 \times10^{-3}$	90%	127
$J/\psi(1S)$anything	$< 6 \times10^{-3}$	90%	4533
Radiative decays			
$\gamma\chi_{b1}(1P)$	(6.7 ±0.9) %		131
$\gamma\chi_{b2}(1P)$	(6.6 ±0.9) %		110
$\gamma\chi_{b0}(1P)$	(4.3 ±1.0) %		162
$\gamma f_J(1710)$	$< 5.9 \times10^{-4}$	90%	4866
$\gamma f_2'(1525)$	$< 5.3 \times10^{-4}$	90%	4896
$\gamma f_2(1270)$	$< 2.41 \times10^{-4}$	90%	4931

$\chi_{b0}(2P)$ [iii] $I^G(J^{PC}) = 0^+(0^{++})$
J needs confirmation.

Mass $m = 10.2321 \pm 0.0006$ GeV

$\chi_{b0}(2P)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\gamma\Upsilon(2S)$	(4.6±2.1) %	210
$\gamma\Upsilon(1S)$	$(9\pm6)\times10^{-3}$	746

$\chi_{b1}(2P)$ [iii] $I^G(J^{PC}) = 0^+(1^{++})$
J needs confirmation.

Mass $m = 10.2552 \pm 0.0005$ GeV
$m_{\chi_{b1}(2P)} - m_{\chi_{b0}(2P)} = 23.5 \pm 1.0$ MeV

$\chi_{b1}(2P)$ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor	p (MeV/c)
$\gamma\Upsilon(2S)$	(21 ±4) %	1.5	229
$\gamma\Upsilon(1S)$	(8.5±1.3) %	1.3	764

$\chi_{b2}(2P)$ [iii] $I^G(J^{PC}) = 0^+(2^{++})$
J needs confirmation.

Mass $m = 10.2685 \pm 0.0004$ GeV
$m_{\chi_{b2}(2P)} - m_{\chi_{b1}(2P)} = 13.5 \pm 0.6$ MeV

$\chi_{b2}(2P)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\gamma\Upsilon(2S)$	(16.2±2.4) %	242
$\gamma\Upsilon(1S)$	(7.1±1.0) %	776

$\Upsilon(3S)$

$I^G(J^{PC}) = 0^-(1^{--})$

Mass $m = 10.3553 \pm 0.0005$ GeV
Full width $\Gamma = 26.3 \pm 3.5$ keV

$\Upsilon(3S)$ DECAY MODES	Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
$\Upsilon(2S)$anything	(10.6 ±0.8) %		296
$\Upsilon(2S)\pi^+\pi^-$	(2.8 ±0.6) %	S=2.2	177
$\Upsilon(2S)\pi^0\pi^0$	(2.00±0.32) %		190
$\Upsilon(2S)\gamma\gamma$	(5.0 ±0.7) %		327
$\Upsilon(1S)\pi^+\pi^-$	(4.48±0.21) %		814
$\Upsilon(1S)\pi^0\pi^0$	(2.06±0.28) %		816
$\Upsilon(1S)\eta$	$< 2.2 \times 10^{-3}$	CL=90%	–
$\mu^+\mu^-$	(1.81±0.17) %		5177
e^+e^-	seen		5177
Radiative decays			
$\gamma\chi_{b2}(2P)$	(11.4 ±0.8) %	S=1.3	87
$\gamma\chi_{b1}(2P)$	(11.3 ±0.6) %		100
$\gamma\chi_{b0}(2P)$	(5.4 ±0.6) %	S=1.1	123

$\Upsilon(4S)$ or $\Upsilon(10580)$

$I^G(J^{PC}) = ?^?(1^{--})$

Mass $m = 10.5800 \pm 0.0035$ GeV
Full width $\Gamma = 10 \pm 4$ MeV
$\Gamma_{ee} = 0.248 \pm 0.031$ keV (S = 1.3)

$\Upsilon(4S)$ DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$B\overline{B}$	> 96 %	95%	–
non-$B\overline{B}$	< 4 %	95%	–
e^+e^-	$(2.8\pm0.7)\times10^{-5}$		5290
$J/\psi(3097)$anything	$(2.2\pm0.7)\times10^{-3}$		–
D^{*+}anything + c.c.	< 7.4 %	90%	5099
ϕanything	$< 2.3 \times 10^{-3}$	90%	5240
$\Upsilon(1S)$anything	$< 4 \times 10^{-3}$	90%	1053

$\Upsilon(10860)$

$I^G(J^{PC}) = ?^?(1^{--})$

Mass $m = 10.865 \pm 0.008$ GeV (S = 1.1)
Full width $\Gamma = 110 \pm 13$ MeV
$\Gamma_{ee} = 0.31 \pm 0.07$ keV (S = 1.3)

$\Upsilon(10860)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
e^+e^-	$(2.8\pm0.7)\times10^{-6}$	5432

$\Upsilon(11020)$

$I^G(J^{PC}) = ?^?(1^{--})$

Mass $m = 11.019 \pm 0.008$ GeV
Full width $\Gamma = 79 \pm 16$ MeV
$\Gamma_{ee} = 0.130 \pm 0.030$ keV

$\Upsilon(11020)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
e^+e^-	$(1.6\pm0.5)\times10^{-6}$	5509

NOTES

In this Summary Table:

When a quantity has "(S = ...)" to its right, the error on the quantity has been enlarged by the "scale factor" S, defined as $S = \sqrt{\chi^2/(N-1)}$, where N is the number of measurements used in calculating the quantity. We do this when $S > 1$, which often indicates that the measurements are inconsistent. When $S > 1.25$, we also show in the Particle Listings an ideogram of the measurements. For more about S, see the Introduction.

A decay momentum p is given for each decay mode. For a 2-body decay, p is the momentum of each decay product in the rest frame of the decaying particle. For a 3-or-more-body decay, p is the largest momentum any of the products can have in this frame.

[a] See the "Note on $\pi^\pm \to \ell^\pm\nu\gamma$ and $K^\pm \to \ell^\pm\nu\gamma$ Form Factors" in the $\pi^\pm$ Particle Listings for definitions and details.

[b] Measurements of $\Gamma(e^+\nu_e)/\Gamma(\mu^+\nu_\mu)$ always include decays with γ's, and measurements of $\Gamma(e^+\nu_e\gamma)$ and $\Gamma(\mu^+\nu_\mu\gamma)$ never include low-energy γ's. Therefore, since no clean separation is possible, we consider the modes with γ's to be subreactions of the modes without them, and let $[\Gamma(e^+\nu_e) + \Gamma(\mu^+\nu_\mu)]/\Gamma_{\rm total} = 100\%$.

[c] See the $\pi^\pm$ Particle Listings for the energy limits used in this measurement; low-energy γ's are not included.

[d] Derived from an analysis of neutrino-oscillation experiments.

[e] Astrophysical and cosmological arguments give limits of order 10^{-13}; see the π^0 Particle Listings.

[f] See the "Note on the Decay Width $\Gamma(\eta \to \gamma\gamma)$" in our 1994 edition, Phys. Rev. **D50**, 1 August 1994, Part I, p. 1451.

[g] C parity forbids this to occur as a single-photon process.

[h] See the "Note on scalar mesons" in the $f_0(1370)$ Particle Listings. The interpretation of this entry as a particle is controversial.

[i] See the "Note on $\rho(770)$" in the $\rho(770)$ Particle Listings.

[j] The $e^+e^- \to \pi^+\pi^-$ experiments only. The $\omega\rho$ interference is then due to $\omega\rho$ mixing only, and is expected to be small. If $e\mu$ universality holds, $\Gamma(\rho^0 \to \mu^+\mu^-) = \Gamma(\rho^0 \to e^+e^-) \times 0.99785$.

[k] See the "Note on scalar mesons" in the $f_0(1370)$ Particle Listings.

[l] See the "Note on $a_1(1260)$" in the $a_1(1260)$ Particle Listings.

[m] This is only an educated guess; the error given is larger than the error on the average of the published values. See the Particle Listings for details.

[n] See the "Note on the $f_1(1420)$" in the $\eta(1440)$ Particle Listings.

[o] See also the $\omega(1600)$ Particle Listings.

[p] See the "Note on the $\eta(1440)$" in the $\eta(1440)$ Particle Listings.

[q] See the "Note on the $\rho(1450)$ and the $\rho(1700)$" in the $\rho(1700)$ Particle Listings.

[r] See the "Note on non-$q\overline{q}$ mesons" in the Particle Listings (see the index for the page number).

[s] See also the $\omega(1420)$ Particle Listings.

[t] See the "Note on $f_J(1710)$" in the $f_J(1710)$ Particle Listings.

[u] See the note in the $K^\pm$ Particle Listings.

[v] The definition of the slope parameter g of the $K \to 3\pi$ Dalitz plot is as follows (see also "Note on Dalitz Plot Parameters for $K \to 3\pi$ Decays" in the $K^\pm$ Particle Listings):

$$|M|^2 = 1 + g(s_3 - s_0)/m^2_{\pi^-} + \cdots .$$

[*w*] For more details and definitions of parameters see the Particle Listings.

[*x*] See the $K^{\pm}$ Particle Listings for the energy limits used in this measurement.

[*y*] Most of this radiative mode (the low-momentum γ part) is also included in the parent mode listed without γ's.

[*z*] Direct-emission branching fraction.

[*aa*] Structure-dependent part.

[*bb*] Derived from measured values of ϕ_{+-} (ϕ_{00}) $|\eta|$ ($|m_{K^0_L} - m_{K^0_S}|$) and $\tau_{K^0_S}$ (as described in the introduction to "Tests of Conservation Laws."

[*cc*] The *CP*-violation parameters are defined as follows (see also "Note on *CP* Violation in $K_S \to 3\pi$" and "Note on *CP* Violation in K^0_L Decay" in the Particle Listings):

$$\eta_{+-} = |\eta_{+-}|e^{i\phi_{+-}} = \frac{A(K^0_L \to \pi^+\pi^-)}{A(K^0_S \to \pi^+\pi^-)} = \epsilon + \epsilon'$$

$$\eta_{00} = |\eta_{00}|e^{i\phi_{00}} = \frac{A(K^0_L \to \pi^0\pi^0)}{A(K^0_S \to \pi^0\pi^0)} = \epsilon - 2\epsilon'$$

$$\delta = \frac{\Gamma(K^0_L \to \pi^-\ell^+\nu) - \Gamma(K^0_L \to \pi^+\ell^-\nu)}{\Gamma(K^0_L \to \pi^-\ell^+\nu) + \Gamma(K^0_L \to \pi^+\ell^-\nu)}$$

$$\mathrm{Im}(\eta_{+-0})^2 = \frac{\Gamma(K^0_S \to \pi^+\pi^-\pi^0)_{CP\ \mathrm{viol.}}}{\Gamma(K^0_L \to \pi^+\pi^-\pi^0)}$$

$$\mathrm{Im}(\eta_{000})^2 = \frac{\Gamma(K^0_S \to \pi^0\pi^0\pi^0)}{\Gamma(K^0_L \to \pi^0\pi^0\pi^0)} .$$

where for the last two relations *CPT* is assumed valid (*i.e.*, $\mathrm{Re}(\eta_{+-0}) \simeq 0$ and $\mathrm{Re}(\eta_{000}) \simeq 0$.

[*dd*] See the K^0_S Particle Listings for the energy limits used in this measurement.

[*ee*] Calculated from K^0_L semileptonic rates and the K^0_S lifetime assuming $\Delta S = \Delta Q$.

[*ff*] ϵ'/ϵ is derived from $|\eta_{00}/\eta_{+-}|$ measurements using theoretical input on phases.

[*gg*] The value is for the sum of the charge states of particle/antiparticle states indicated.

[*hh*] See the K^0_L Particle Listings for the energy limits used in this measurement.

[*ii*] Allowed by higher-order electroweak interactions.

[*jj*] Violates *CP* in leading order. Test of direct *CP* violation since the indirect *CP*-violating and *CP*-conserving contributions are expected to be suppressed.

[*kk*] See the "Note on $f_0(1370)$" in the $f_0(1370)$ Particle Listings and in the 1994 edition.

[*ll*] See the note in the $L(1770)$ Particle Listings in Reviews of Modern Physics **56** No. 2 Pt. II (1984) p. S200. See also the "Note on $K_2(1770)$ and the $K_2(1820)$" in the $K_2(1770)$ Particle Listings .

[*mm*] See the "Note on $K_2(1770)$ and the $K_2(1820)$" in the $K_2(1770)$ Particle Listings .

[*nn*] This is a weighted average of $D^{\pm}$ (44%) and D^0 (56%) branching fractions. See "D^+ and $D^0 \to$ (η anything) / (total D^+ and D^0)" under "D^+ Branching Ratios" in the Particle Listings.

[*oo*] This value averages the e^+ and μ^+ branching fractions after making a small phase-space adjustment to the μ^+ fraction to be able to use it as an e^+ fraction; hence our ℓ^+ here is really an e^+.

[*pp*] An ℓ indicates an e or a μ mode not a sum over these modes.

[*qq*] The branching fraction for this mode may differ from the sum of the submodes that contribute to it due to interference effects. See the relevant papers in the Particle Listings.

[*rr*] The two experiments measuring this fraction are in serious disagreement. See the Particle Listings.

[*ss*] This mode is not a useful test for a ΔC=1 weak neutral current because both quarks must change flavor in this decay.

[*tt*] The D^0_1-D^0_2 limits are inferred from the D^0-$\overline{D}^0$ mixing ratio $\Gamma(K^+\ell^-\overline{\nu}_\ell$(via $\overline{D}^0)) / \Gamma(K^-\ell^+\nu_\ell)$.

[*uu*] The larger limit (from E791) allows interference between the doubly Cabibbo-suppressed and mixing amplitudes; the smaller limit (from E691) doesn't. See the papers for details.

[*vv*] The experiments on the division of this charge mode amongst its submodes disagree and the submode branching fractions here add up to considerably more than the charged-mode fraction.

[*ww*] However these upper limits are in serious disagreement with values obtained in another experiment.

[*xx*] For now we average together measurements of the $Xe^+\nu_e$ and $X\mu^+\nu_\mu$ branching fractions. This is the *average* not the *sum*.

[*yy*] This branching fraction includes all the decay modes of the final-state resonance.

[*zz*] This value includes only K^+K^- decays of the $f_J(1710)$ because branching fractions of this resonance are not known.

[*aaa*] This value includes only $\pi^+\pi^-$ decays of the $f_0(1500)$ because branching fractions of this resonance are not known.

[*bbb*] B^0 and B^0_s contributions not separated. Limit is on weighted average of the two decay rates.

[*ccc*] These values are model dependent. See 'Note on Semileptonic Decays' in the B^+ Particle Listings.

[*ddd*] D^{**} stands for the sum of the $D(1\,^1P_1)$ $D(1\,^3P_0)$ $D(1\,^3P_1)$ $D(1\,^3P_2)$ $D(2\,^1S_0)$ and $D(2\,^1S_1)$ resonances.

[*eee*] Inclusive branching fractions have a multiplicity definition and can be greater than 100%.

[*fff*] D_j represents an unresolved mixture of pseudoscalar and tensor D^{**} (P-wave) states.

[*ggg*] Not a pure measurement. See note at head of B^0_s Decay Modes.

[*hhh*] Includes $p\overline{p}\pi^+\pi^-\gamma$ and excludes $p\overline{p}\eta$ $p\overline{p}\omega$ $p\overline{p}\eta'$.

[*iii*] J^{PC} known by production in e^+e^- via single photon annihilation. I^G is not known; interpretation of this state as a single resonance is unclear because of the expectation of substantial threshold effects in this energy region.

[*jjj*] Spectroscopic labelling for these states is theoretical pending experimental information.

See also the table of suggested $q\bar{q}$ quark-model assignments in the Quark Model section.

- • Indicates particles that appear in the preceding Meson Summary Table. We do not regard the other entries as being established.
- † Indicates that the value of J given is preferred, but needs confirmation.

LIGHT UNFLAVORED ($S = C = B = 0$)

$I^G(J^{PC})$		$I^G(J^{PC})$	
• $\pi^\pm$	$1^-(0^-)$	$X(1650)$	$0^+(?^?-)$
• π^0	$1^-(0^{-+})$	• $\omega_3(1670)$	$0^-(3^{--})$
• η	$0^+(0^{-+})$	• $\pi_2(1670)$	$1^-(2^{-+})$
• $f_0(400\text{–}1200)$	$0^+(0^{++})$	• $\phi(1680)$	$0^-(1^{--})$
• $\rho(770)$	$1^+(1^{--})$	• $\rho_3(1690)$	$1^+(3^{--})$
• $\omega(782)$	$0^-(1^{--})$	• $\rho(1700)$	$1^+(1^{--})$
• $\eta'(958)$	$0^+(0^{-+})$	• $f_J(1710)$	$0^+(\text{even}^{++})$
• $f_0(980)$	$0^+(0^{++})$	$\eta(1760)$	$0^+(0^{-+})$
• $a_0(980)$	$1^-(0^{++})$	$X(1775)$	$1^-(?^{-+})$
• $\phi(1020)$	$0^-(1^{--})$	• $\pi(1800)$	$1^-(0^{-+})$
• $h_1(1170)$	$0^-(1^{+-})$	$f_2(1810)$	$0^+(2^{++})$
• $b_1(1235)$	$1^+(1^{+-})$	• $\phi_3(1850)$	$0^-(3^{--})$
• $a_1(1260)$	$1^-(1^{++})$	$\eta_2(1870)$	$0^+(2^{-+})$
• $f_2(1270)$	$0^+(2^{++})$	$X(1910)$	$0^+(?^{?+})$
• $f_1(1285)$	$0^+(1^{++})$	$f_2(1950)$	$0^+(2^{++})$
• $\eta(1295)$	$0^+(0^{-+})$	$X(2000)$	$1^-(?^{?+})$
• $\pi(1300)$	$1^-(0^{-+})$	• $f_2(2010)$	$0^+(2^{++})$
• $a_2(1320)$	$1^-(2^{++})$	$f_0(2020)$	$0^+(0^{++})$
• $f_0(1370)$	$0^+(0^{++})$	• $a_4(2040)$	$1^-(4^{++})$
$h_1(1380)$	$?^-(1^{+-})$	• $f_4(2050)$	$0^+(4^{++})$
$\hat{\rho}(1405)$	$1^-(1^{-+})$	$f_0(2060)$	$0^+(0^{++})$
• $f_1(1420)$	$0^+(1^{++})$	$\pi_2(2100)$	$1^-(2^{-+})$
• $\omega(1420)$	$0^-(1^{--})$	$f_2(2150)$	$0^+(2^{++})$
$f_2(1430)$	$0^+(2^{++})$	$\rho(2150)$	$1^+(1^{--})$
• $\eta(1440)$	$0^+(0^{-+})$	$f_0(2200)$	$0^+(0^{++})$
• $a_0(1450)$	$1^-(0^{++})$	$f_J(2220)$	$0^+(2^{++}$ or $4^{++})$
• $\rho(1450)$	$1^+(1^{--})$	$\eta(2225)$	$0^+(0^{-+})$
• $f_0(1500)$	$0^+(0^{++})$	$\rho_3(2250)$	$1^+(3^{--})$
$f_1(1510)$	$0^+(1^{++})$	• $f_2(2300)$	$0^+(2^{++})$
• $f_2'(1525)$	$0^+(2^{++})$	$f_4(2300)$	$0^+(4^{++})$
$f_2(1565)$	$0^+(2^{++})$	• $f_2(2340)$	$0^+(2^{++})$
• $\omega(1600)$	$0^-(1^{--})$	$\rho_5(2350)$	$1^+(5^{--})$
$X(1600)$	$2^+(2^{++})$	$a_6(2450)$	$1^-(6^{++})$
$f_2(1640)$	$0^+(2^{++})$	$f_6(2510)$	$0^+(6^{++})$
$\eta_2(1645)$	$0^+(2^{-+})$	$X(3250)$	$?^?(?^{??})$

OTHER LIGHT UNFLAVORED ($S = C = B = 0$)

$e^+e^-(1100\text{–}2200)$ $?^?(1^{--})$
$\overline{N}N(1100\text{–}3600)$
$X(1900\text{–}3600)$

STRANGE ($S = \pm 1$, $C = B = 0$)

$I(J^P)$	
• $K^\pm$	$1/2(0^-)$
• K^0	$1/2(0^-)$
• K_S^0	$1/2(0^-)$
• K_L^0	$1/2(0^-)$
• $K^*(892)$	$1/2(1^-)$
• $K_1(1270)$	$1/2(1^+)$
• $K_1(1400)$	$1/2(1^+)$
• $K^*(1410)$	$1/2(1^-)$
• $K_0^*(1430)$	$1/2(0^+)$
• $K_2^*(1430)$	$1/2(2^+)$
$K(1460)$	$1/2(0^-)$
$K_2(1580)$	$1/2(2^-)$
$K_1(1650)$	$1/2(1^+)$
• $K^*(1680)$	$1/2(1^-)$
• $K_2(1770)$	$1/2(2^-)$
• $K_3^*(1780)$	$1/2(3^-)$
• $K_2(1820)$	$1/2(2^-)$
$K(1830)$	$1/2(0^-)$
$K_0^*(1950)$	$1/2(0^+)$
$K_2^*(1980)$	$1/2(2^+)$
• $K_4^*(2045)$	$1/2(4^+)$
$K_2(2250)$	$1/2(2^-)$
$K_3(2320)$	$1/2(3^+)$
$K_5^*(2380)$	$1/2(5^-)$
$K_4(2500)$	$1/2(4^-)$
$K(3100)$	$?^?(?^{??})$

CHARMED ($C = \pm 1$)

• $D^\pm$	$1/2(0^-)$
• D^0	$1/2(0^-)$
• $D^*(2007)^0$	$1/2(1^-)$
• $D^*(2010)^\pm$	$1/2(1^-)$
• $D_1(2420)^0$	$1/2(1^+)$
$D_1(2420)^\pm$	$1/2(?^?)$
• $D_2^*(2460)^0$	$1/2(2^+)$
• $D_2^*(2460)^+$	$1/2(2^+)$

CHARMED, STRANGE ($C = S = \pm 1$)

• $D_s^\pm$	$0(0^-)$
• $D_s^{*\pm}$	$0(?^?)$
• $D_{s1}(2536)^\pm$	$0(1^+)$
• $D_{sJ}(2573)^\pm$	$0(?^?)$

BOTTOM ($B = \pm 1$)

• $B^\pm$	$1/2(0^-)$
• B^0	$1/2(0^-)$
• B^*	$1/2(1^-)$
$B_J^*(5732)$	$?(?^?)$

BOTTOM, STRANGE ($B = \pm 1$, $S = \mp 1$)

$I^G(J^{PC})$	
• B_s^0	$0(0^-)$
B_s^*	$0(1^-)$
$B_{sJ}^*(5850)$	$?(?^?)$

BOTTOM, CHARMED ($B = C = \pm 1$)

$B_c^\pm$	$0(0^-)$

$c\bar{c}$

• $\eta_c(1S)$	$0^+(0^{-+})$
• $J/\psi(1S)$	$0^-(1^{--})$
• $\chi_{c0}(1P)$	$0^+(0^{++})$
• $\chi_{c1}(1P)$	$0^+(1^{++})$
$h_c(1P)$	$?^?(?^{??})$
• $\chi_{c2}(1P)$	$0^+(2^{++})$
$\eta_c(2S)$	$?^?(?^{?+})$
• $\psi(2S)$	$0^-(1^{--})$
• $\psi(3770)$	$?^?(1^{--})$
• $\psi(4040)$	$?^?(1^{--})$
• $\psi(4160)$	$?^?(1^{--})$
• $\psi(4415)$	$?^?(1^{--})$

$b\bar{b}$

• $\Upsilon(1S)$	$0^-(1^{--})$
• $\chi_{b0}(1P)$	$0^+(0^{++})$
• $\chi_{b1}(1P)$	$0^+(1^{++})$
• $\chi_{b2}(1P)$	$0^+(2^{++})$
• $\Upsilon(2S)$	$0^-(1^{--})$
• $\chi_{b0}(2P)$	$0^+(0^{++})$
• $\chi_{b1}(2P)$	$0^+(1^{++})$
• $\chi_{b2}(2P)$	$0^+(2^{++})$
• $\Upsilon(3S)$	$0^-(1^{--})$
• $\Upsilon(4S)$	$?^?(1^{--})$
• $\Upsilon(10860)$	$?^?(1^{--})$
• $\Upsilon(11020)$	$?^?(1^{--})$

NON-$q\bar{q}$ CANDIDATES

Non-$q\bar{q}$ Candidates

BARYON SUMMARY TABLE

This short table gives the name, the quantum numbers (where known), and the status of baryons in the Review. Only the baryons with 3- or 4-star status are included in the main Baryon Summary Table. Due to insufficient data or uncertain interpretation, the other entries in the short table are not established as baryons. The names with masses are of baryons that decay strongly. See our 1986 edition (Physics Letters **170B**) for listings of evidence for Z baryons (KN resonances).

p	P_{11}	****	$\Delta(1232)$	P_{33}	****	Λ	P_{01}	****	Σ^+	P_{11}	****	Ξ^0	P_{11}	****
n	P_{11}	****	$\Delta(1600)$	P_{33}	***	$\Lambda(1405)$	S_{01}	****	Σ^0	P_{11}	****	Ξ^-	P_{11}	****
$N(1440)$	P_{11}	****	$\Delta(1620)$	S_{31}	****	$\Lambda(1520)$	D_{03}	****	Σ^-	P_{11}	****	$\Xi(1530)$	P_{13}	****
$N(1520)$	D_{13}	****	$\Delta(1700)$	D_{33}	****	$\Lambda(1600)$	P_{01}	***	$\Sigma(1385)$	P_{13}	****	$\Xi(1620)$		*
$N(1535)$	S_{11}	****	$\Delta(1750)$	P_{31}	*	$\Lambda(1670)$	S_{01}	****	$\Sigma(1480)$		*	$\Xi(1690)$		***
$N(1650)$	S_{11}	****	$\Delta(1900)$	S_{31}	**	$\Lambda(1690)$	D_{03}	****	$\Sigma(1560)$		**	$\Xi(1820)$	D_{13}	***
$N(1675)$	D_{15}	****	$\Delta(1905)$	F_{35}	****	$\Lambda(1800)$	S_{01}	***	$\Sigma(1580)$	D_{13}	**	$\Xi(1950)$		***
$N(1680)$	F_{15}	****	$\Delta(1910)$	P_{31}	****	$\Lambda(1810)$	P_{01}	***	$\Sigma(1620)$	S_{11}	**	$\Xi(2030)$		***
$N(1700)$	D_{13}	***	$\Delta(1920)$	P_{33}	***	$\Lambda(1820)$	F_{05}	****	$\Sigma(1660)$	P_{11}	***	$\Xi(2120)$		*
$N(1710)$	P_{11}	***	$\Delta(1930)$	D_{35}	***	$\Lambda(1830)$	D_{05}	****	$\Sigma(1670)$	D_{13}	****	$\Xi(2250)$		**
$N(1720)$	P_{13}	****	$\Delta(1940)$	D_{33}	*	$\Lambda(1890)$	P_{03}	****	$\Sigma(1690)$		**	$\Xi(2370)$		**
$N(1900)$	P_{13}	**	$\Delta(1950)$	F_{37}	****	$\Lambda(2000)$		*	$\Sigma(1750)$	S_{11}	***	$\Xi(2500)$		*
$N(1990)$	F_{17}	**	$\Delta(2000)$	F_{35}	**	$\Lambda(2020)$	F_{07}	*	$\Sigma(1770)$	P_{11}	*			
$N(2000)$	F_{15}	**	$\Delta(2150)$	S_{31}	*	$\Lambda(2100)$	G_{07}	****	$\Sigma(1775)$	D_{15}	****	Ω^-		****
$N(2080)$	D_{13}	**	$\Delta(2200)$	G_{37}	*	$\Lambda(2110)$	F_{05}	***	$\Sigma(1840)$	P_{13}	*	$\Omega(2250)^-$		***
$N(2090)$	S_{11}	*	$\Delta(2300)$	H_{39}	**	$\Lambda(2325)$	D_{03}	*	$\Sigma(1880)$	P_{11}	**	$\Omega(2380)^-$		**
$N(2100)$	P_{11}	*	$\Delta(2350)$	D_{35}	*	$\Lambda(2350)$	H_{09}	***	$\Sigma(1915)$	F_{15}	****	$\Omega(2470)^-$		**
$N(2190)$	G_{17}	****	$\Delta(2390)$	F_{37}	*	$\Lambda(2585)$		**	$\Sigma(1940)$	D_{13}	***			
$N(2200)$	D_{15}	**	$\Delta(2400)$	G_{39}	**				$\Sigma(2000)$	S_{11}	*	Λ_c^+		****
$N(2220)$	H_{19}	****	$\Delta(2420)$	$H_{3,11}$	****				$\Sigma(2030)$	F_{17}	****	$\Lambda_c(2593)^+$		***
$N(2250)$	G_{19}	****	$\Delta(2750)$	$I_{3,13}$	**				$\Sigma(2070)$	F_{15}	*	$\Lambda_c(2625)^+$		***
$N(2600)$	$I_{1,11}$	***	$\Delta(2950)$	$K_{3,15}$	**				$\Sigma(2080)$	P_{13}	**	$\Sigma_c(2455)$		****
$N(2700)$	$K_{1,13}$	**							$\Sigma(2100)$	G_{17}	*	$\Sigma_c(2520)$		***
									$\Sigma(2250)$		***	Ξ_c^+		***
									$\Sigma(2455)$		**	Ξ_c^0		***
									$\Sigma(2620)$		**	$\Xi_c(2645)$		***
									$\Sigma(3000)$		*	Ω_c^0		***
									$\Sigma(3170)$		*			
												Λ_b^0		***
												Ξ_b^0, Ξ_b^-		*

**** Existence is certain, and properties are at least fairly well explored.

*** Existence ranges from very likely to certain, but further confirmation is desirable and/or quantum numbers, branching fractions, etc. are not well determined.

** Evidence of existence is only fair.

* Evidence of existence is poor.

N BARYONS ($S = 0$, $I = 1/2$)

p or $N^+ = uud$; n or $N^0 = udd$

p

$I(J^P) = \frac{1}{2}(\frac{1}{2}^+)$

Mass $m = 938.27231 \pm 0.00028$ MeV [a]
$= 1.007276470 \pm 0.000000012$ u
$\left|\frac{q_p}{m_p}\right|/(\frac{q_p}{m_p}) = 1.0000000015 \pm 0.0000000011$
$|q_p + q_{\bar{p}}|/e < 2 \times 10^{-5}$
$|q_p + q_e|/e < 1.0 \times 10^{-21}$ [b]
Magnetic moment $\mu = 2.79284739 \pm 0.00000006\ \mu_N$
Electric dipole moment $d = (-4 \pm 6) \times 10^{-23}$ e cm
Electric polarizability $\bar{\alpha} = (12.1 \pm 0.9) \times 10^{-4}$ fm^3
Magnetic polarizability $\bar{\beta} = (2.1 \pm 0.9) \times 10^{-4}$ fm^3
Mean life $\tau > 1.6 \times 10^{25}$ years (independent of mode)
$> 10^{31}$ to 5×10^{32} years [c] (mode dependent)

Below Γ for N decays Γ p and n distinguish proton and neutron partial lifetimes. See also the "Note on Nucleon Decay" in our 1994 edition (Phys. Rev. D50 Γ 1673) for a short review.

The "partial mean life" limits tabulated here are the limits on τ/B_i Γ where τ is the total mean life and B_i is the branching fraction for the mode in question.

p DECAY MODES	Partial mean life (10^{30} years)	Confidence level	p (MeV/c)
Antilepton + meson			
$N \to e^+\pi$	> 130 (n) Γ > 550 (p)	90%	459
$N \to \mu^+\pi$	> 100 (n) Γ > 270 (p)	90%	453
$N \to \nu\pi$	> 100 (n) Γ > 25 (p)	90%	459
$p \to e^+\eta$	> 140	90%	309
$p \to \mu^+\eta$	> 69	90%	296
$n \to \nu\eta$	> 54	90%	310
$N \to e^+\rho$	> 58 (n) Γ > 75 (p)	90%	153
$N \to \mu^+\rho$	> 23 (n) Γ > 110 (p)	90%	119
$N \to \nu\rho$	> 19 (n) Γ > 27 (p)	90%	153
$p \to e^+\omega$	> 45	90%	142
$p \to \mu^+\omega$	> 57	90%	104
$n \to \nu\omega$	> 43	90%	144
$N \to e^+K$	> 1.3 (n) Γ > 150 (p)	90%	337
$p \to e^+K^0_S$	> 76	90%	337
$p \to e^+K^0_L$	> 44	90%	337
$N \to \mu^+K$	> 1.1 (n) Γ > 120 (p)	90%	326
$p \to \mu^+K^0_S$	> 64	90%	326
$p \to \mu^+K^0_L$	> 44	90%	326
$N \to \nu K$	> 86 (n) Γ > 100 (p)	90%	339
$p \to e^+K^*(892)^0$	> 52	90%	45
$N \to \nu K^*(892)$	> 22 (n) Γ > 20 (p)	90%	45
Antilepton + mesons			
$p \to e^+\pi^+\pi^-$	> 21	90%	448
$p \to e^+\pi^0\pi^0$	> 38	90%	449
$n \to e^+\pi^-\pi^0$	> 32	90%	449
$p \to \mu^+\pi^+\pi^-$	> 17	90%	425
$p \to \mu^+\pi^0\pi^0$	> 33	90%	427
$n \to \mu^+\pi^-\pi^0$	> 33	90%	427
$n \to e^+K^0\pi^-$	> 18	90%	319
Lepton + meson			
$n \to e^-\pi^+$	> 65	90%	459
$n \to \mu^-\pi^+$	> 49	90%	453
$n \to e^-\rho^+$	> 62	90%	154
$n \to \mu^-\rho^+$	> 7	90%	120
$n \to e^-K^+$	> 32	90%	340
$n \to \mu^-K^+$	> 57	90%	330
Lepton + mesons			
$p \to e^-\pi^+\pi^+$	> 30	90%	448
$n \to e^-\pi^+\pi^0$	> 29	90%	449
$p \to \mu^-\pi^+\pi^+$	> 17	90%	425
$n \to \mu^-\pi^+\pi^0$	> 34	90%	427
$p \to e^-\pi^+K^+$	> 20	90%	320
$p \to \mu^-\pi^+K^+$	> 5	90%	279
Antilepton + photon(s)			
$p \to e^+\gamma$	> 460	90%	469
$p \to \mu^+\gamma$	> 380	90%	463
$n \to \nu\gamma$	> 24	90%	470
$p \to e^+\gamma\gamma$	> 100	90%	469
Three (or more) leptons			
$p \to e^+e^+e^-$	> 510	90%	469
$p \to e^+\mu^+\mu^-$	> 81	90%	457
$p \to e^+\nu\nu$	> 11	90%	469
$n \to e^+e^-\nu$	> 74	90%	470
$n \to \mu^+e^-\nu$	> 47	90%	464
$n \to \mu^+\mu^-\nu$	> 42	90%	458
$p \to \mu^+e^+e^-$	> 91	90%	464
$p \to \mu^+\mu^+\mu^-$	> 190	90%	439
$p \to \mu^+\nu\nu$	> 21	90%	463
$p \to e^-\mu^+\mu^+$	> 6	90%	457
$n \to 3\nu$	> 0.0005	90%	470
Inclusive modes			
$N \to e^+$ anything	> 0.6 (n Γ p)	90%	–
$N \to \mu^+$ anything	> 12 (n Γ p)	90%	–
$N \to e^+\pi^0$ anything	> 0.6 (n Γ p)	90%	–
$\Delta B = 2$ dinucleon modes			
The following are lifetime limits per iron nucleus.			
$pp \to \pi^+\pi^+$	> 0.7	90%	–
$pn \to \pi^+\pi^0$	> 2	90%	–
$nn \to \pi^+\pi^-$	> 0.7	90%	–
$nn \to \pi^0\pi^0$	> 3.4	90%	–
$pp \to e^+e^+$	> 5.8	90%	–
$pp \to e^+\mu^+$	> 3.6	90%	–
$pp \to \mu^+\mu^+$	> 1.7	90%	–
$pn \to e^+\bar{\nu}$	> 2.8	90%	–
$pn \to \mu^+\bar{\nu}$	> 1.6	90%	–
$nn \to \nu_e\bar{\nu}_e$	> 0.000012	90%	–
$nn \to \nu_\mu\bar{\nu}_\mu$	> 0.000006	90%	–

$\bar{p}$ DECAY MODES

$\bar{p}$ DECAY MODES	Partial mean life (years)	Confidence level	p (MeV/c)
$\bar{p} \to e^-\gamma$	> 1848	95%	469
$\bar{p} \to e^-\pi^0$	> 554	95%	459
$\bar{p} \to e^-\eta$	> 171	95%	309
$\bar{p} \to e^-K^0_S$	> 29	95%	337
$\bar{p} \to e^-K^0_L$	> 9	95%	337

n

$I(J^P) = \frac{1}{2}(\frac{1}{2}^+)$

Mass $m = 939.56563 \pm 0.00028$ MeV [a]
$= 1.008664904 \pm 0.000000014$ u
$m_n - m_p = 1.293318 \pm 0.000009$ MeV
$= 0.001388434 \pm 0.000000009$ u
Mean life $\tau = 886.7 \pm 1.9$ s (S = 1.2)
$c\tau = 2.658 \times 10^8$ km
Magnetic moment $\mu = -1.9130428 \pm 0.0000005\ \mu_N$
Electric dipole moment $d < 0.97 \times 10^{-25}$ e cm Γ CL = 90%
Electric polarizability $\alpha = (0.98^{+0.19}_{-0.23}) \times 10^{-3}$ fm^3 (S = 1.1)
Charge $q = (-0.4 \pm 1.1) \times 10^{-21}$ e
Mean $n\bar{n}$-oscillation time $> 1.2 \times 10^8$ s Γ CL = 90% [d] (bound n)
$> 0.86 \times 10^8$ s Γ CL = 90% (free n)

Decay parameters [e]

$pe^-\bar{\nu}_e$	$g_A/g_V = -1.2670 \pm 0.0035$ (S = 1.9)
"	$A = -0.1162 \pm 0.0013$ (S = 1.8)
"	$B = 0.990 \pm 0.008$
"	$a = -0.102 \pm 0.005$
"	$\phi_{AV} = (180.07 \pm 0.18)°$ [f]
"	$D = (-0.5 \pm 1.4) \times 10^{-3}$

n DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$pe^-\bar{\nu}_e$	100 %		1.19
Charge conservation (Q) violating mode			
$p\nu_e\bar{\nu}_e$	$Q < 8 \times 10^{-27}$	68%	1.29

$N(1440)\ P_{11}$ $I(J^P) = \frac{1}{2}(\frac{1}{2}^+)$

Breit-Wigner mass = 1430 to 1470 (≈ 1440) MeV
Breit-Wigner full width = 250 to 450 (≈ 350) MeV
p_{beam} = 0.61 GeV/c $4\pi\lambda^2$ = 31.0 mb
Re(pole position) = 1345 to 1385 (≈ 1365) MeV
−2Im(pole position) = 160 to 260 (≈ 210) MeV

$N(1440)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	60–70 %	397
$N\pi\pi$	30–40 %	342
$\Delta\pi$	20–30 %	143
$N\rho$	<8 %	†
$N(\pi\pi)^{I=0}_{S\text{-wave}}$	5–10 %	–
$p\gamma$	0.035–0.048 %	414
$p\gamma$ Helicity=1/2	0.035–0.048 %	414
$n\gamma$	0.009–0.032 %	413
$n\gamma$ Helicity=1/2	0.009–0.032 %	413

$N(1520)\ D_{13}$ $I(J^P) = \frac{1}{2}(\frac{3}{2}^-)$

Breit-Wigner mass = 1515 to 1530 (≈ 1520) MeV
Breit-Wigner full width = 110 to 135 (≈ 120) MeV
p_{beam} = 0.74 GeV/c $4\pi\lambda^2$ = 23.5 mb
Re(pole position) = 1505 to 1515 (≈ 1510) MeV
−2Im(pole position) = 110 to 120 (≈ 115) MeV

$N(1520)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	50–60 %	456
$N\pi\pi$	40–50 %	410
$\Delta\pi$	15–25 %	228
$N\rho$	15–25 %	†
$N(\pi\pi)^{I=0}_{S\text{-wave}}$	<8 %	–
$p\gamma$	0.46–0.56 %	470
$p\gamma$ Helicity=1/2	0.001–0.034 %	470
$p\gamma$ Helicity=3/2	0.44–0.53 %	470
$n\gamma$	0.30–0.53 %	470
$n\gamma$ Helicity=1/2	0.04–0.10 %	470
$n\gamma$ Helicity=3/2	0.25–0.45 %	470

$N(1535)\ S_{11}$ $I(J^P) = \frac{1}{2}(\frac{1}{2}^-)$

Breit-Wigner mass = 1520 to 1555 (≈ 1535) MeV
Breit-Wigner full width = 100 to 250 (≈ 150) MeV
p_{beam} = 0.76 GeV/c $4\pi\lambda^2$ = 22.5 mb
Re(pole position) = 1495 to 1515 (≈ 1505) MeV
−2Im(pole position) = 90 to 250 (≈ 170) MeV

$N(1535)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	35–55 %	467
$N\eta$	30–55 %	182
$N\pi\pi$	1–10 %	422
$\Delta\pi$	<1 %	242
$N\rho$	<4 %	†
$N(\pi\pi)^{I=0}_{S\text{-wave}}$	<3 %	–
$N(1440)\pi$	<7 %	†
$p\gamma$	0.15–0.35 %	481
$p\gamma$ Helicity=1/2	0.15–0.35 %	481
$n\gamma$	0.004–0.29 %	480
$n\gamma$ Helicity=1/2	0.004–0.29 %	480

$N(1650)\ S_{11}$ $I(J^P) = \frac{1}{2}(\frac{1}{2}^-)$

Breit-Wigner mass = 1640 to 1680 (≈ 1650) MeV
Breit-Wigner full width = 145 to 190 (≈ 150) MeV
p_{beam} = 0.96 GeV/c $4\pi\lambda^2$ = 16.4 mb
Re(pole position) = 1640 to 1680 (≈ 1660) MeV
−2Im(pole position) = 150 to 170 (≈ 160) MeV

$N(1650)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	55–90 %	547
$N\eta$	3–10 %	346
ΛK	3–11 %	161
$N\pi\pi$	10–20 %	511
$\Delta\pi$	1–7 %	344
$N\rho$	4–12 %	†
$N(\pi\pi)^{I=0}_{S\text{-wave}}$	<4 %	–
$N(1440)\pi$	<5 %	147
$p\gamma$	0.04–0.18 %	558
$p\gamma$ Helicity=1/2	0.04–0.18 %	558
$n\gamma$	0.003–0.17 %	557
$n\gamma$ Helicity=1/2	0.003–0.17 %	557

$N(1675)\ D_{15}$ $I(J^P) = \frac{1}{2}(\frac{5}{2}^-)$

Breit-Wigner mass = 1670 to 1685 (≈ 1675) MeV
Breit-Wigner full width = 140 to 180 (≈ 150) MeV
p_{beam} = 1.01 GeV/c $4\pi\lambda^2$ = 15.4 mb
Re(pole position) = 1655 to 1665 (≈ 1660) MeV
−2Im(pole position) = 125 to 155 (≈ 140) MeV

$N(1675)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	40–50 %	563
ΛK	<1 %	209
$N\pi\pi$	50–60 %	529
$\Delta\pi$	50–60 %	364
$N\rho$	< 1–3 %	†
$p\gamma$	0.004–0.023 %	575
$p\gamma$ Helicity=1/2	0.0–0.015 %	575
$p\gamma$ Helicity=3/2	0.0–0.011 %	575
$n\gamma$	0.02–0.12 %	574
$n\gamma$ Helicity=1/2	0.006–0.046 %	574
$n\gamma$ Helicity=3/2	0.01–0.08 %	574

$N(1680)\ F_{15}$ $I(J^P) = \frac{1}{2}(\frac{5}{2}^+)$

Breit-Wigner mass = 1675 to 1690 (≈ 1680) MeV
Breit-Wigner full width = 120 to 140 (≈ 130) MeV
p_{beam} = 1.01 GeV/c $4\pi\lambda^2$ = 15.2 mb
Re(pole position) = 1665 to 1675 (≈ 1670) MeV
−2Im(pole position) = 105 to 135 (≈ 120) MeV

$N(1680)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	60–70 %	567
$N\pi\pi$	30–40 %	532
$\Delta\pi$	5–15 %	369
$N\rho$	3–15 %	†
$N(\pi\pi)^{I=0}_{S\text{-wave}}$	5–20 %	–
$p\gamma$	0.21–0.32 %	578
$p\gamma$ Helicity=1/2	0.001–0.011 %	578
$p\gamma$ Helicity=3/2	0.20–0.32 %	578
$n\gamma$	0.021–0.046 %	577
$n\gamma$ Helicity=1/2	0.004–0.029 %	577
$n\gamma$ Helicity=3/2	0.01–0.024 %	577

$N(1700)$ D_{13} $I(J^P) = \frac{1}{2}(\frac{3}{2}^-)$

Breit-Wigner mass = 1650 to 1750 (≈ 1700) MeV
Breit-Wigner full width = 50 to 150 (≈ 100) MeV
p_{beam} = 1.05 GeV/c $4\pi\lambda^2$ = 14.5 mb
Re(pole position) = 1630 to 1730 (≈ 1680) MeV
−2Im(pole position) = 50 to 150 (≈ 100) MeV

$N(1700)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	5–15 %	580
ΛK	<3 %	250
$N\pi\pi$	85–95 %	547
$N\rho$	<35 %	†
$p\gamma$	0.01–0.05 %	591
$p\gamma$ helicity=1/2	0.0–0.024 %	591
$p\gamma$ helicity=3/2	0.002–0.026 %	591
$n\gamma$	0.01–0.13 %	590
$n\gamma$ helicity=1/2	0.0–0.09 %	590
$n\gamma$ helicity=3/2	0.01–0.05 %	590

$N(1710)$ P_{11} $I(J^P) = \frac{1}{2}(\frac{1}{2}^+)$

Breit-Wigner mass = 1680 to 1740 (≈ 1710) MeV
Breit-Wigner full width = 50 to 250 (≈ 100) MeV
p_{beam} = 1.07 GeV/c $4\pi\lambda^2$ = 14.2 mb
Re(pole position) = 1670 to 1770 (≈ 1720) MeV
−2Im(pole position) = 80 to 380 (≈ 230) MeV

$N(1710)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	10–20 %	587
ΛK	5–25 %	264
$N\pi\pi$	40–90 %	554
$\Delta\pi$	15–40 %	393
$N\rho$	5–25 %	48
$N(\pi\pi)^{I=0}_{S\text{-wave}}$	10–40 %	–
$p\gamma$	0.002–0.05%	598
$p\gamma$ helicity=1/2	0.002–0.05%	598
$n\gamma$	0.0–0.02%	597
$n\gamma$ helicity=1/2	0.0–0.02%	597

$N(1720)$ P_{13} $I(J^P) = \frac{1}{2}(\frac{3}{2}^+)$

Breit-Wigner mass = 1650 to 1750 (≈ 1720) MeV
Breit-Wigner full width = 100 to 200 (≈ 150) MeV
p_{beam} = 1.09 GeV/c $4\pi\lambda^2$ = 13.9 mb
Re(pole position) = 1650 to 1750 (≈ 1700) MeV
−2Im(pole position) = 110 to 390 (≈ 250) MeV

$N(1720)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	10–20 %	594
ΛK	1–15 %	278
$N\pi\pi$	>70 %	561
$N\rho$	70–85 %	104
$p\gamma$	0.003–0.10 %	604
$p\gamma$ helicity=1/2	0.003–0.08 %	604
$p\gamma$ helicity=3/2	0.001–0.03 %	604
$n\gamma$	0.002–0.39 %	603
$n\gamma$ helicity=1/2	0.0–0.002 %	603
$n\gamma$ helicity=3/2	0.001–0.39 %	603

$N(2190)$ G_{17} $I(J^P) = \frac{1}{2}(\frac{7}{2}^-)$

Breit-Wigner mass = 2100 to 2200 (≈ 2190) MeV
Breit-Wigner full width = 350 to 550 (≈ 450) MeV
p_{beam} = 2.07 GeV/c $4\pi\lambda^2$ = 6.21 mb
Re(pole position) = 1950 to 2150 (≈ 2050) MeV
−2Im(pole position) = 350 to 550 (≈ 450) MeV

$N(2190)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	10–20 %	888

$N(2220)$ H_{19} $I(J^P) = \frac{1}{2}(\frac{9}{2}^+)$

Breit-Wigner mass = 2180 to 2310 (≈ 2220) MeV
Breit-Wigner full width = 320 to 550 (≈ 400) MeV
p_{beam} = 2.14 GeV/c $4\pi\lambda^2$ = 5.97 mb
Re(pole position) = 2100 to 2240 (≈ 2170) MeV
−2Im(pole position) = 370 to 570 (≈ 470) MeV

$N(2220)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	10–20 %	905

$N(2250)$ G_{19} $I(J^P) = \frac{1}{2}(\frac{9}{2}^-)$

Breit-Wigner mass = 2170 to 2310 (≈ 2250) MeV
Breit-Wigner full width = 290 to 470 (≈ 400) MeV
p_{beam} = 2.21 GeV/c $4\pi\lambda^2$ = 5.74 mb
Re(pole position) = 2080 to 2200 (≈ 2140) MeV
−2Im(pole position) = 280 to 680 (≈ 480) MeV

$N(2250)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	5–15 %	923

$N(2600)$ $I_{1,11}$ $I(J^P) = \frac{1}{2}(\frac{11}{2}^-)$

Breit-Wigner mass = 2550 to 2750 (≈ 2600) MeV
Breit-Wigner full width = 500 to 800 (≈ 650) MeV
p_{beam} = 3.12 GeV/c $4\pi\lambda^2$ = 3.86 mb

$N(2600)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	5–10 %	1126

Δ BARYONS ($S = 0$, $I = 3/2$)

$\Delta^{++} = uuu$, $\Delta^+ = uud$, $\Delta^0 = udd$, $\Delta^- = ddd$

$\Delta(1232)$ P_{33} $I(J^P) = \frac{3}{2}(\frac{3}{2}^+)$

Breit-Wigner mass (mixed charges) = 1230 to 1234 (≈ 1232) MeV
Breit-Wigner full width (mixed charges) = 115 to 125 (≈ 120) MeV
p_{beam} = 0.30 GeV/c $4\pi\lambda^2$ = 94.8 mb
Re(pole position) = 1209 to 1211 (≈ 1210) MeV
−2Im(pole position) = 98 to 102 (≈ 100) MeV

$\Delta(1232)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	>99 %	227
$N\gamma$	0.52–0.60 %	259
$N\gamma$ helicity=1/2	0.11–0.13 %	259
$N\gamma$ helicity=3/2	0.41–0.47 %	259

$\Delta(1600)$ P_{33} $I(J^P) = \frac{3}{2}(\frac{3}{2}^+)$

Breit-Wigner mass = 1550 to 1700 (≈ 1600) MeV
Breit-Wigner full width = 250 to 450 (≈ 350) MeV
p_{beam} = 0.87 GeV/c $4\pi\lambda^2$ = 18.6 mb
Re(pole position) = 1500 to 1700 (≈ 1600) MeV
−2Im(pole position) = 200 to 400 (≈ 300) MeV

$\Delta(1600)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	10–25 %	512
$N\pi\pi$	75–90 %	473
$\Delta\pi$	40–70 %	301
$N\rho$	<25 %	†
$N(1440)\pi$	10–35 %	74
$N\gamma$	0.001–0.02 %	525
$N\gamma$ helicity=1/2	0.0–0.02 %	525
$N\gamma$ helicity=3/2	0.001–0.005 %	525

Δ(1620) S_{31} $I(J^P) = \frac{3}{2}(\frac{1}{2}^-)$

Breit-Wigner mass = 1615 to 1675 (≈ 1620) MeV
Breit-Wigner full width = 120 to 180 (≈ 150) MeV
p_{beam} = 0.91 GeV/c $4\pi\lambda^2$ = 17.7 mb
Re(pole position) = 1580 to 1620 (≈ 1600) MeV
−2Im(pole position) = 100 to 130 (≈ 115) MeV

Δ(1620) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	20–30 %	526
$N\pi\pi$	70–80 %	488
$\Delta\pi$	30–60 %	318
$N\rho$	7–25 %	†
$N\gamma$	0.004–0.044 %	538
$N\gamma$ Γhelicity=1/2	0.004–0.044 %	538

Δ(1700) D_{33} $I(J^P) = \frac{3}{2}(\frac{3}{2}^-)$

Breit-Wigner mass = 1670 to 1770 (≈ 1700) MeV
Breit-Wigner full width = 200 to 400 (≈ 300) MeV
p_{beam} = 1.05 GeV/c $4\pi\lambda^2$ = 14.5 mb
Re(pole position) = 1620 to 1700 (≈ 1660) MeV
−2Im(pole position) = 150 to 250 (≈ 200) MeV

Δ(1700) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	10–20 %	580
$N\pi\pi$	80–90 %	547
$\Delta\pi$	30–60 %	385
$N\rho$	30–55 %	†
$N\gamma$	0.12–0.26 %	591
$N\gamma$ Γhelicity=1/2	0.08–0.16 %	591
$N\gamma$ Γhelicity=3/2	0.025–0.12 %	591

Δ(1905) F_{35} $I(J^P) = \frac{3}{2}(\frac{5}{2}^+)$

Breit-Wigner mass = 1870 to 1920 (≈ 1905) MeV
Breit-Wigner full width = 280 to 440 (≈ 350) MeV
p_{beam} = 1.45 GeV/c $4\pi\lambda^2$ = 9.62 mb
Re(pole position) = 1800 to 1860 (≈ 1830) MeV
−2Im(pole position) = 230 to 330 (≈ 280) MeV

Δ(1905) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	5–15 %	713
$N\pi\pi$	85–95 %	687
$\Delta\pi$	<25 %	542
$N\rho$	>60 %	421
$N\gamma$	0.01–0.03 %	721
$N\gamma$ Γhelicity=1/2	0.0–0.1 %	721
$N\gamma$ Γhelicity=3/2	0.004–0.03 %	721

Δ(1910) P_{31} $I(J^P) = \frac{3}{2}(\frac{1}{2}^+)$

Breit-Wigner mass = 1870 to 1920 (≈ 1910) MeV
Breit-Wigner full width = 190 to 270 (≈ 250) MeV
p_{beam} = 1.46 GeV/c $4\pi\lambda^2$ = 9.54 mb
Re(pole position) = 1830 to 1880 (≈ 1855) MeV
−2Im(pole position) = 200 to 500 (≈ 350) MeV

Δ(1910) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	15–30 %	716
$N\gamma$	0.0–0.2 %	725
$N\gamma$ Γhelicity=1/2	0.0–0.2 %	725

Δ(1920) P_{33} $I(J^P) = \frac{3}{2}(\frac{3}{2}^+)$

Breit-Wigner mass = 1900 to 1970 (≈ 1920) MeV
Breit-Wigner full width = 150 to 300 (≈ 200) MeV
p_{beam} = 1.48 GeV/c $4\pi\lambda^2$ = 9.37 mb
Re(pole position) = 1850 to 1950 (≈ 1900) MeV
−2Im(pole position) = 200 to 400 (≈ 300) MeV

Δ(1920) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	5–20 %	722

Δ(1930) D_{35} $I(J^P) = \frac{3}{2}(\frac{5}{2}^-)$

Breit-Wigner mass = 1920 to 1970 (≈ 1930) MeV
Breit-Wigner full width = 250 to 450 (≈ 350) MeV
p_{beam} = 1.50 GeV/c $4\pi\lambda^2$ = 9.21 mb
Re(pole position) = 1840 to 1940 (≈ 1890) MeV
−2Im(pole position) = 200 to 300 (≈ 250) MeV

Δ(1930) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	10–20 %	729
$N\gamma$	0.0–0.02 %	737
$N\gamma$ Γhelicity=1/2	0.0–0.01 %	737
$N\gamma$ Γhelicity=3/2	0.0–0.01 %	737

Δ(1950) F_{37} $I(J^P) = \frac{3}{2}(\frac{7}{2}^+)$

Breit-Wigner mass = 1940 to 1960 (≈ 1950) MeV
Breit-Wigner full width = 290 to 350 (≈ 300) MeV
p_{beam} = 1.54 GeV/c $4\pi\lambda^2$ = 8.91 mb
Re(pole position) = 1880 to 1890 (≈ 1885) MeV
−2Im(pole position) = 210 to 270 (≈ 240) MeV

Δ(1950) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	35–40 %	741
$N\pi\pi$		716
$\Delta\pi$	20–30 %	574
$N\rho$	<10 %	469
$N\gamma$	0.08–0.13 %	749
$N\gamma$ Γhelicity=1/2	0.03–0.055 %	749
$N\gamma$ Γhelicity=3/2	0.05–0.075 %	749

Δ(2420) $H_{3,11}$ $I(J^P) = \frac{3}{2}(\frac{11}{2}^+)$

Breit-Wigner mass = 2300 to 2500 (≈ 2420) MeV
Breit-Wigner full width = 300 to 500 (≈ 400) MeV
p_{beam} = 2.64 GeV/c $4\pi\lambda^2$ = 4.68 mb
Re(pole position) = 2260 to 2400 (≈ 2330) MeV
−2Im(pole position) = 350 to 750 (≈ 550) MeV

Δ(2420) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\pi$	5–15 %	1023

Λ BARYONS
($S = -1$, $I = 0$)

$\Lambda^0 = uds$

Λ

$I(J^P) = 0(\frac{1}{2}^+)$

Mass $m = 1115.683 \pm 0.006$ MeV
Mean life $\tau = (2.632 \pm 0.020) \times 10^{-10}$ s (S = 1.6)
$c\tau = 7.89$ cm
Magnetic moment $\mu = -0.613 \pm 0.004\ \mu_N$
Electric dipole moment $d < 1.5 \times 10^{-16}$ e cm CL = 95%

Decay parameters

$p\pi^-$	$\alpha_- = 0.642 \pm 0.013$
"	$\phi_- = (-6.5 \pm 3.5)^\circ$
"	$\gamma_- = 0.76$ [g]
"	$\Delta_- = (8 \pm 4)^\circ$ [g]
$n\pi^0$	$\alpha_0 = +0.65 \pm 0.05$
$pe^-\overline{\nu}_e$	$g_A/g_V = -0.718 \pm 0.015$ [e]

Λ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$p\pi^-$	(63.9 ±0.5)%	101
$n\pi^0$	(35.8 ±0.5)%	104
$n\gamma$	(1.75±0.15)×10^{-3}	162
$p\pi^-\gamma$	[h] (8.4 ±1.4)×10^{-4}	101
$pe^-\overline{\nu}_e$	(8.32±0.14)×10^{-4}	163
$p\mu^-\overline{\nu}_\mu$	(1.57±0.35)×10^{-4}	131

Λ(1405) S_{01}

$I(J^P) = 0(\frac{1}{2}^-)$

Mass $m = 1407 \pm 4$ MeV
Full width $\Gamma = 50.0 \pm 2.0$ MeV
Below $\overline{K}N$ threshold

Λ(1405) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Sigma\pi$	100 %	152

Λ(1520) D_{03}

$I(J^P) = 0(\frac{3}{2}^-)$

Mass $m = 1519.5 \pm 1.0$ MeV [i]
Full width $\Gamma = 15.6 \pm 1.0$ MeV [i]
$p_{\text{beam}} = 0.39$ GeV/c $\quad 4\pi\lambda\!\!\!^{-2} = 82.8$ mb

Λ(1520) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	45 ± 1%	244
$\Sigma\pi$	42 ± 1%	267
$\Lambda\pi\pi$	10 ± 1%	252
$\Sigma\pi\pi$	0.9 ± 0.1%	152
$\Lambda\gamma$	0.8 ± 0.2%	351

Λ(1600) P_{01}

$I(J^P) = 0(\frac{1}{2}^+)$

Mass $m = 1560$ to 1700 (≈ 1600) MeV
Full width $\Gamma = 50$ to 250 (≈ 150) MeV
$p_{\text{beam}} = 0.58$ GeV/c $\quad 4\pi\lambda\!\!\!^{-2} = 41.6$ mb

Λ(1600) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	15–30 %	343
$\Sigma\pi$	10–60 %	336

Λ(1670) S_{01}

$I(J^P) = 0(\frac{1}{2}^-)$

Mass $m = 1660$ to 1680 (≈ 1670) MeV
Full width $\Gamma = 25$ to 50 (≈ 35) MeV
$p_{\text{beam}} = 0.74$ GeV/c $\quad 4\pi\lambda\!\!\!^{-2} = 28.5$ mb

Λ(1670) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	15–25 %	414
$\Sigma\pi$	20–60 %	393
$\Lambda\eta$	15–35 %	64

Λ(1690) D_{03}

$I(J^P) = 0(\frac{3}{2}^-)$

Mass $m = 1685$ to 1695 (≈ 1690) MeV
Full width $\Gamma = 50$ to 70 (≈ 60) MeV
$p_{\text{beam}} = 0.78$ GeV/c $\quad 4\pi\lambda\!\!\!^{-2} = 26.1$ mb

Λ(1690) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	20–30 %	433
$\Sigma\pi$	20–40 %	409
$\Lambda\pi\pi$	~ 25 %	415
$\Sigma\pi\pi$	~ 20 %	350

Λ(1800) S_{01}

$I(J^P) = 0(\frac{1}{2}^-)$

Mass $m = 1720$ to 1850 (≈ 1800) MeV
Full width $\Gamma = 200$ to 400 (≈ 300) MeV
$p_{\text{beam}} = 1.01$ GeV/c $\quad 4\pi\lambda\!\!\!^{-2} = 17.5$ mb

Λ(1800) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	25–40 %	528
$\Sigma\pi$	seen	493
$\Sigma(1385)\pi$	seen	345
$N\overline{K}^*(892)$	seen	†

Λ(1810) P_{01}

$I(J^P) = 0(\frac{1}{2}^+)$

Mass $m = 1750$ to 1850 (≈ 1810) MeV
Full width $\Gamma = 50$ to 250 (≈ 150) MeV
$p_{\text{beam}} = 1.04$ GeV/c $\quad 4\pi\lambda\!\!\!^{-2} = 17.0$ mb

Λ(1810) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	20–50 %	537
$\Sigma\pi$	10–40 %	501
$\Sigma(1385)\pi$	seen	356
$N\overline{K}^*(892)$	30–60 %	†

Λ(1820) F_{05}

$I(J^P) = 0(\frac{5}{2}^+)$

Mass $m = 1815$ to 1825 (≈ 1820) MeV
Full width $\Gamma = 70$ to 90 (≈ 80) MeV
$p_{\text{beam}} = 1.06$ GeV/c $\quad 4\pi\lambda\!\!\!^{-2} = 16.5$ mb

Λ(1820) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	55–65 %	545
$\Sigma\pi$	8–14 %	508
$\Sigma(1385)\pi$	5–10 %	362

Λ(1830) D_{05}

$I(J^P) = 0(\frac{5}{2}^-)$

Mass $m = 1810$ to 1830 (≈ 1830) MeV
Full width $\Gamma = 60$ to 110 (≈ 95) MeV
$p_{\text{beam}} = 1.08$ GeV/c $\quad 4\pi\lambda\!\!\!^{-2} = 16.0$ mb

Λ(1830) DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	3–10 %	553
$\Sigma\pi$	35–75 %	515
$\Sigma(1385)\pi$	>15 %	371

$\Lambda(1890)$ P_{03} $I(J^P) = 0(\frac{3}{2}^+)$

Mass $m = 1850$ to 1910 (≈ 1890) MeV
Full width $\Gamma = 60$ to 200 (≈ 100) MeV
$p_{\text{beam}} = 1.21$ GeV/c $4\pi\lambda\!\!\!^{-2} = 13.6$ mb

$\Lambda(1890)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	20–35 %	599
$\Sigma\pi$	3–10 %	559
$\Sigma(1385)\pi$	seen	420
$N\overline{K}^*(892)$	seen	233

$\Lambda(2100)$ G_{07} $I(J^P) = 0(\frac{7}{2}^-)$

Mass $m = 2090$ to 2110 (≈ 2100) MeV
Full width $\Gamma = 100$ to 250 (≈ 200) MeV
$p_{\text{beam}} = 1.68$ GeV/c $4\pi\lambda\!\!\!^{-2} = 8.68$ mb

$\Lambda(2100)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	25–35 %	751
$\Sigma\pi$	~ 5 %	704
$\Lambda\eta$	< 3 %	617
ΞK	< 3 %	483
$\Lambda\omega$	< 8 %	443
$N\overline{K}^*(892)$	10–20 %	514

$\Lambda(2110)$ F_{05} $I(J^P) = 0(\frac{5}{2}^+)$

Mass $m = 2090$ to 2140 (≈ 2110) MeV
Full width $\Gamma = 150$ to 250 (≈ 200) MeV
$p_{\text{beam}} = 1.70$ GeV/c $4\pi\lambda\!\!\!^{-2} = 8.53$ mb

$\Lambda(2110)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	5–25 %	757
$\Sigma\pi$	10–40 %	711
$\Lambda\omega$	seen	455
$\Sigma(1385)\pi$	seen	589
$N\overline{K}^*(892)$	10–60 %	524

$\Lambda(2350)$ H_{09} $I(J^P) = 0(\frac{9}{2}^+)$

Mass $m = 2340$ to 2370 (≈ 2350) MeV
Full width $\Gamma = 100$ to 250 (≈ 150) MeV
$p_{\text{beam}} = 2.29$ GeV/c $4\pi\lambda\!\!\!^{-2} = 5.85$ mb

$\Lambda(2350)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	~ 12 %	915
$\Sigma\pi$	~ 10 %	867

Σ BARYONS
$(S = -1, I = 1)$

$\Sigma^+ = uus$, $\Sigma^0 = uds$, $\Sigma^- = dds$

Σ^+ $I(J^P) = 1(\frac{1}{2}^+)$

Mass $m = 1189.37 \pm 0.07$ MeV (S = 2.2)
Mean life $\tau = (0.799 \pm 0.004) \times 10^{-10}$ s
$c\tau = 2.396$ cm
Magnetic moment $\mu = 2.458 \pm 0.010$ μ_N (S = 2.1)
$\Gamma(\Sigma^+ \to n\ell^+\nu)/\Gamma(\Sigma^- \to n\ell^-\bar{\nu}) < 0.043$

Decay parameters

$p\pi^0$	$\alpha_0 = -0.980^{+0.017}_{-0.015}$
"	$\phi_0 = (36 \pm 34)^\circ$
"	$\gamma_0 = 0.16$ [g]
"	$\Delta_0 = (187 \pm 6)^\circ$ [g]
$n\pi^+$	$\alpha_+ = 0.068 \pm 0.013$
"	$\phi_+ = (167 \pm 20)^\circ$ (S = 1.1)
"	$\gamma_+ = -0.97$ [g]
"	$\Delta_+ = (-73^{+133}_{-10})^\circ$ [g]
$p\gamma$	$\alpha_\gamma = -0.76 \pm 0.08$

Σ^+ DECAY MODES		Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$p\pi^0$		(51.57±0.30) %		189
$n\pi^+$		(48.31±0.30) %		185
$p\gamma$		(1.23±0.05) $\times 10^{-3}$		225
$n\pi^+\gamma$	[h]	(4.5 ±0.5) $\times 10^{-4}$		185
$\Lambda e^+\nu_e$		(2.0 ±0.5) $\times 10^{-5}$		71
$\Delta S = \Delta Q$ (SQ) violating modes or $\Delta S = 1$ weak neutral current ($S1$) modes				
$ne^+\nu_e$	SQ	< 5 $\times 10^{-6}$	90%	224
$n\mu^+\nu_\mu$	SQ	< 3.0 $\times 10^{-5}$	90%	202
pe^+e^-	$S1$	< 7 $\times 10^{-6}$		225

Σ^0 $I(J^P) = 1(\frac{1}{2}^+)$

Mass $m = 1192.642 \pm 0.024$ MeV
$m_{\Sigma^-} - m_{\Sigma^0} = 4.807 \pm 0.035$ MeV (S = 1.1)
$m_{\Sigma^0} - m_\Lambda = 76.959 \pm 0.023$ MeV
Mean life $\tau = (7.4 \pm 0.7) \times 10^{-20}$ s
$c\tau = 2.22 \times 10^{-11}$ m
Transition magnetic moment $|\mu_{\Sigma\Lambda}| = 1.61 \pm 0.08$ μ_N

Σ^0 DECAY MODES		Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$\Lambda\gamma$		100 %		74
$\Lambda\gamma\gamma$		< 3 %	90%	74
Λe^+e^-	[i]	5×10^{-3}		74

Σ^- $I(J^P) = 1(\frac{1}{2}^+)$

Mass $m = 1197.449 \pm 0.030$ MeV (S = 1.2)
$m_{\Sigma^-} - m_{\Sigma^+} = 8.08 \pm 0.08$ MeV (S = 1.9)
$m_{\Sigma^-} - m_{\Lambda} = 81.766 \pm 0.030$ MeV (S = 1.2)
Mean life $\tau = (1.479 \pm 0.011) \times 10^{-10}$ s (S = 1.3)
$c\tau = 4.434$ cm
Magnetic moment $\mu = -1.160 \pm 0.025\ \mu_N$ (S = 1.7)

Decay parameters

$n\pi^-$	$\alpha_- = -0.068 \pm 0.008$
"	$\phi_- = (10 \pm 15)^\circ$
"	$\gamma_- = 0.98$ [g]
"	$\Delta_- = (249^{+12}_{-120})^\circ$ [g]
$ne^-\overline{\nu}_e$	$g_A/g_V = 0.340 \pm 0.017$ [e]
"	$f_2(0)/f_1(0) = 0.97 \pm 0.14$
"	$D = 0.11 \pm 0.10$
$\Lambda e^-\overline{\nu}_e$	$g_V/g_A = 0.01 \pm 0.10$ [e] (S = 1.5)
"	$g_{WM}/g_A = 2.4 \pm 1.7$ [e]

Σ^- DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$n\pi^-$	(99.848±0.005) %	193
$n\pi^-\gamma$	[h] (4.6 ±0.6) × 10^{-4}	193
$ne^-\overline{\nu}_e$	(1.017±0.034) × 10^{-3}	230
$n\mu^-\overline{\nu}_\mu$	(4.5 ±0.4) × 10^{-4}	210
$\Lambda e^-\overline{\nu}_e$	(5.73 ±0.27) × 10^{-5}	79

$\Sigma(1385)\ P_{13}$ $I(J^P) = 1(\frac{3}{2}^+)$

$\Sigma(1385)^+$ mass $m = 1382.8 \pm 0.4$ MeV (S = 2.0)
$\Sigma(1385)^0$ mass $m = 1383.7 \pm 1.0$ MeV (S = 1.4)
$\Sigma(1385)^-$ mass $m = 1387.2 \pm 0.5$ MeV (S = 2.2)
$\Sigma(1385)^+$ full width $\Gamma = 35.8 \pm 0.8$ MeV
$\Sigma(1385)^0$ full width $\Gamma = 36 \pm 5$ MeV
$\Sigma(1385)^-$ full width $\Gamma = 39.4 \pm 2.1$ MeV (S = 1.7)
Below $\overline{K}N$ threshold

$\Sigma(1385)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Lambda\pi$	88±2 %	208
$\Sigma\pi$	12±2 %	127

$\Sigma(1660)\ P_{11}$ $I(J^P) = 1(\frac{1}{2}^+)$

Mass $m = 1630$ to 1690 (≈ 1660) MeV
Full width $\Gamma = 40$ to 200 (≈ 100) MeV
$p_{\text{beam}} = 0.72$ GeV/c $4\pi\lambda\!\!\!^{-2} = 29.9$ mb

$\Sigma(1660)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	10–30 %	405
$\Lambda\pi$	seen	439
$\Sigma\pi$	seen	385

$\Sigma(1670)\ D_{13}$ $I(J^P) = 1(\frac{3}{2}^-)$

Mass $m = 1665$ to 1685 (≈ 1670) MeV
Full width $\Gamma = 40$ to 80 (≈ 60) MeV
$p_{\text{beam}} = 0.74$ GeV/c $4\pi\lambda\!\!\!^{-2} = 28.5$ mb

$\Sigma(1670)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	7–13 %	414
$\Lambda\pi$	5–15 %	447
$\Sigma\pi$	30–60 %	393

$\Sigma(1750)\ S_{11}$ $I(J^P) = 1(\frac{1}{2}^-)$

Mass $m = 1730$ to 1800 (≈ 1750) MeV
Full width $\Gamma = 60$ to 160 (≈ 90) MeV
$p_{\text{beam}} = 0.91$ GeV/c $4\pi\lambda\!\!\!^{-2} = 20.7$ mb

$\Sigma(1750)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	10–40 %	486
$\Lambda\pi$	seen	507
$\Sigma\pi$	<8 %	455
$\Sigma\eta$	15–55 %	81

$\Sigma(1775)\ D_{15}$ $I(J^P) = 1(\frac{5}{2}^-)$

Mass $m = 1770$ to 1780 (≈ 1775) MeV
Full width $\Gamma = 105$ to 135 (≈ 120) MeV
$p_{\text{beam}} = 0.96$ GeV/c $4\pi\lambda\!\!\!^{-2} = 19.0$ mb

$\Sigma(1775)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	37–43%	508
$\Lambda\pi$	14–20%	525
$\Sigma\pi$	2–5%	474
$\Sigma(1385)\pi$	8–12%	324
$\Lambda(1520)\pi$	17–23%	198

$\Sigma(1915)\ F_{15}$ $I(J^P) = 1(\frac{5}{2}^+)$

Mass $m = 1900$ to 1935 (≈ 1915) MeV
Full width $\Gamma = 80$ to 160 (≈ 120) MeV
$p_{\text{beam}} = 1.26$ GeV/c $4\pi\lambda\!\!\!^{-2} = 12.8$ mb

$\Sigma(1915)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	5–15 %	618
$\Lambda\pi$	seen	622
$\Sigma\pi$	seen	577
$\Sigma(1385)\pi$	<5 %	440

$\Sigma(1940)\ D_{13}$ $I(J^P) = 1(\frac{3}{2}^-)$

Mass $m = 1900$ to 1950 (≈ 1940) MeV
Full width $\Gamma = 150$ to 300 (≈ 220) MeV
$p_{\text{beam}} = 1.32$ GeV/c $4\pi\lambda\!\!\!^{-2} = 12.1$ mb

$\Sigma(1940)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	<20 %	637
$\Lambda\pi$	seen	639
$\Sigma\pi$	seen	594
$\Sigma(1385)\pi$	seen	460
$\Lambda(1520)\pi$	seen	354
$\Delta(1232)\overline{K}$	seen	410
$N\overline{K}^*(892)$	seen	320

$\Sigma(2030)\ F_{17}$ $I(J^P) = 1(\frac{7}{2}^+)$

Mass $m = 2025$ to 2040 (≈ 2030) MeV
Full width $\Gamma = 150$ to 200 (≈ 180) MeV
$p_{\text{beam}} = 1.52$ GeV/c $4\pi\lambda\!\!\!^{-2} = 9.93$ mb

$\Sigma(2030)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	17–23 %	702
$\Lambda\pi$	17–23 %	700
$\Sigma\pi$	5–10 %	657
ΞK	<2 %	412
$\Sigma(1385)\pi$	5–15 %	529
$\Lambda(1520)\pi$	10–20 %	430
$\Delta(1232)\overline{K}$	10–20 %	498
$N\overline{K}^*(892)$	<5 %	438

$\Sigma(2250)$ $I(J^P) = 1(?^?)$

Mass $m = 2210$ to 2280 (≈ 2250) MeV
Full width $\Gamma = 60$ to 150 (≈ 100) MeV
$p_{beam} = 2.04$ GeV/c $4\pi\lambda^2 = 6.76$ mb

$\Sigma(2250)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$N\overline{K}$	<10 %	851
$\Lambda\pi$	seen	842
$\Sigma\pi$	seen	803

Ξ BARYONS ($S=-2, I=1/2$)

$\Xi^0 = uss$, $\Xi^- = dss$

Ξ^0 $I(J^P) = \frac{1}{2}(\frac{1}{2}^+)$

P is not yet measured; + is the quark model prediction.

Mass $m = 1314.9 \pm 0.6$ MeV
$m_{\Xi^-} - m_{\Xi^0} = 6.4 \pm 0.6$ MeV
Mean life $\tau = (2.90 \pm 0.09) \times 10^{-10}$ s
$c\tau = 8.71$ cm
Magnetic moment $\mu = -1.250 \pm 0.014\ \mu_N$

Decay parameters

$\Lambda\pi^0$	$\alpha = -0.411 \pm 0.022$	(S = 2.1)
"	$\phi = (21 \pm 12)^\circ$	
"	$\gamma = 0.85$ [g]	
"	$\Delta = (218^{+12}_{-19})^\circ$ [g]	
$\Lambda\gamma$	$\alpha = 0.4 \pm 0.4$	
$\Sigma^0\gamma$	$\alpha = 0.20 \pm 0.32$	

Ξ^0 DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$\Lambda\pi^0$	(99.54±0.05) %		135
$\Lambda\gamma$	(1.06±0.16) $\times 10^{-3}$		184
$\Sigma^0\gamma$	(3.5 ±0.4) $\times 10^{-3}$		117
$\Sigma^+ e^-\overline{\nu}_e$	< 1.1 $\times 10^{-3}$	90%	120
$\Sigma^+ \mu^-\overline{\nu}_\mu$	< 1.1 $\times 10^{-3}$	90%	64
$\Delta S = \Delta Q$ (SQ) violating modes or $\Delta S = 2$ forbidden ($S2$) modes			
$\Sigma^- e^+\nu_e$	SQ < 9 $\times 10^{-4}$	90%	112
$\Sigma^- \mu^+\nu_\mu$	SQ < 9 $\times 10^{-4}$	90%	49
$p\pi^-$	$S2$ < 4 $\times 10^{-5}$	90%	299
$pe^-\overline{\nu}_e$	$S2$ < 1.3 $\times 10^{-3}$		323
$p\mu^-\overline{\nu}_\mu$	$S2$ < 1.3 $\times 10^{-3}$		309

Ξ^- $I(J^P) = \frac{1}{2}(\frac{1}{2}^+)$

P is not yet measured; + is the quark model prediction.

Mass $m = 1321.32 \pm 0.13$ MeV
Mean life $\tau = (1.639 \pm 0.015) \times 10^{-10}$ s
$c\tau = 4.91$ cm
Magnetic moment $\mu = -0.6507 \pm 0.0025\ \mu_N$

Decay parameters

$\Lambda\pi^-$	$\alpha = -0.456 \pm 0.014$	(S = 1.8)
"	$\phi = (4 \pm 4)^\circ$	
"	$\gamma = 0.89$ [g]	
"	$\Delta = (188 \pm 8)^\circ$ [g]	
$\Lambda e^-\overline{\nu}_e$	$g_A/g_V = -0.25 \pm 0.05$ [e]	

Ξ^- DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$\Lambda\pi^-$	(99.887±0.035) %		139
$\Sigma^-\gamma$	(1.27 ±0.23) $\times 10^{-4}$		118
$\Lambda e^-\overline{\nu}_e$	(5.63 ±0.31) $\times 10^{-4}$		190
$\Lambda\mu^-\overline{\nu}_\mu$	(3.5 $^{+3.5}_{-2.2}$) $\times 10^{-4}$		163
$\Sigma^0 e^-\overline{\nu}_e$	(8.7 ±1.7) $\times 10^{-5}$		122
$\Sigma^0 \mu^-\overline{\nu}_\mu$	< 8 $\times 10^{-4}$	90%	70
$\Xi^0 e^-\overline{\nu}_e$	< 2.3 $\times 10^{-3}$	90%	6
$\Delta S = 2$ forbidden ($S2$) modes			
$n\pi^-$	$S2$ < 1.9 $\times 10^{-5}$	90%	303
$ne^-\overline{\nu}_e$	$S2$ < 3.2 $\times 10^{-3}$	90%	327
$n\mu^-\overline{\nu}_\mu$	$S2$ < 1.5 %	90%	314
$p\pi^-\pi^-$	$S2$ < 4 $\times 10^{-4}$	90%	223
$p\pi^- e^-\overline{\nu}_e$	$S2$ < 4 $\times 10^{-4}$	90%	304
$p\pi^-\mu^-\overline{\nu}_\mu$	$S2$ < 4 $\times 10^{-4}$	90%	250
$p\mu^-\mu^-$	L < 4 $\times 10^{-4}$	90%	272

$\Xi(1530)$ P_{13} $I(J^P) = \frac{1}{2}(\frac{3}{2}^+)$

$\Xi(1530)^0$ mass $m = 1531.80 \pm 0.32$ MeV (S = 1.3)
$\Xi(1530)^-$ mass $m = 1535.0 \pm 0.6$ MeV
$\Xi(1530)^0$ full width $\Gamma = 9.1 \pm 0.5$ MeV
$\Xi(1530)^-$ full width $\Gamma = 9.9^{+1.7}_{-1.9}$ MeV

$\Xi(1530)$ DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$\Xi\pi$	100 %		152
$\Xi\gamma$	<4 %	90%	200

$\Xi(1690)$ $I(J^P) = \frac{1}{2}(?^?)$

Mass $m = 1690 \pm 10$ MeV [*]
Full width $\Gamma < 50$ MeV

$\Xi(1690)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Lambda\overline{K}$	seen	240
$\Sigma\overline{K}$	seen	51
$\Xi^-\pi^+\pi^-$	possibly seen	214

$\Xi(1820)$ D_{13} $I(J^P) = \frac{1}{2}(\frac{3}{2}^-)$

Mass $m = 1823 \pm 5$ MeV [*]
Full width $\Gamma = 24^{+15}_{-10}$ MeV [*]

$\Xi(1820)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Lambda\overline{K}$	large	400
$\Sigma\overline{K}$	small	320
$\Xi\pi$	small	413
$\Xi(1530)\pi$	small	234

$\Xi(1950)$ $I(J^P) = \frac{1}{2}(?^?)$

Mass $m = 1950 \pm 15$ MeV [*]
Full width $\Gamma = 60 \pm 20$ MeV [*]

$\Xi(1950)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Lambda\overline{K}$	seen	522
$\Sigma\overline{K}$	possibly seen	460
$\Xi\pi$	seen	518

$\Xi(2030)$ $I(J^P) = \frac{1}{2}(\geq \frac{5}{2}^?)$

Mass $m = 2025 \pm 5$ MeV [*]
Full width $\Gamma = 20^{+15}_{-5}$ MeV [*]

$\Xi(2030)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Lambda\overline{K}$	~20 %	589
$\Sigma\overline{K}$	~80 %	533
$\Xi\pi$	small	573
$\Xi(1530)\pi$	small	421
$\Lambda\overline{K}\pi$	small	501
$\Sigma\overline{K}\pi$	small	430

Ω BARYONS ($S=-3, I=0$)

$\Omega^- = sss$

Ω^- $I(J^P) = 0(\frac{3}{2}^+)$

J^P is not yet measured; $\frac{3}{2}^+$ is the quark model prediction.

Mass $m = 1672.45 \pm 0.29$ MeV
Mean life $\tau = (0.822 \pm 0.012) \times 10^{-10}$ s
$c\tau = 2.46$ cm
Magnetic moment $\mu = -2.02 \pm 0.05\ \mu_N$

Decay parameters

ΛK^-	$\alpha = -0.026 \pm 0.026$
$\Xi^0\pi^-$	$\alpha = 0.09 \pm 0.14$
$\Xi^-\pi^0$	$\alpha = 0.05 \pm 0.21$

Ω^- DECAY MODES	Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
ΛK^-	(67.8±0.7) %		211
$\Xi^0\pi^-$	(23.6±0.7) %		294
$\Xi^-\pi^0$	(8.6±0.4) %		290
$\Xi^-\pi^+\pi^-$	$(\ 4.3^{+3.4}_{-1.3}) \times 10^{-4}$		190
$\Xi(1530)^0\pi^-$	$(\ 6.4^{+5.1}_{-2.0}) \times 10^{-4}$		17
$\Xi^0 e^-\overline{\nu}_e$	$(\ 5.6\pm2.8) \times 10^{-3}$		319
$\Xi^-\gamma$	$< 4.6 \times 10^{-4}$	90%	314
$\Delta S = 2$ forbidden ($S2$) modes			
$\Lambda\pi^-$	$S2$ $< 1.9 \times 10^{-4}$	90%	449

$\Omega(2250)^-$ $I(J^P) = 0(?^?)$

Mass $m = 2252 \pm 9$ MeV
Full width $\Gamma = 55 \pm 18$ MeV

$\Omega(2250)^-$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Xi^-\pi^+K^-$	seen	531
$\Xi(1530)^0K^-$	seen	437

CHARMED BARYONS ($C=+1$)

$\Lambda_c^+ = udc\Gamma\ \ \Sigma_c^{++} = uuc\Gamma\ \ \Sigma_c^+ = udc\Gamma\ \ \Sigma_c^0 = ddc\Gamma$
$\Xi_c^+ = usc\Gamma\ \ \Xi_c^0 = dsc\Gamma\ \ \Omega_c^0 = ssc$

Λ_c^+ $I(J^P) = 0(\frac{1}{2}^+)$

J not confirmed; $\frac{1}{2}$ is the quark model prediction.

Mass $m = 2284.9 \pm 0.6$ MeV
Mean life $\tau = (0.206 \pm 0.012) \times 10^{-12}$ s
$c\tau = 61.8\ \mu$m

Decay asymmetry parameters

$\Lambda\pi^+$	$\alpha = -0.98 \pm 0.19$
$\Sigma^+\pi^0$	$\alpha = -0.45 \pm 0.32$
$\Lambda\ell^+\nu_\ell$	$\alpha = -0.82^{+0.11}_{-0.07}$

Nearly all branching fractions of the Λ_c^+ are measured relative to the $pK^-\pi^+$ mode—but there are no model-independent measurements of this branching fraction. We explain how we arrive at our value of $B(\Lambda_c^+ \to pK^-\pi^+)$ in a Note at the beginning of the branching-ratio measurements in the Listings. When this branching fraction is eventually well determined, all the other branching fractions will slide up or down proportionally as the true value differs from the value we use here.

Λ_c^+ DECAY MODES		Fraction (Γ_i/Γ)	Scale factor/ Confidence level	p (MeV/c)
Hadronic modes with a p and one $\overline{K}$				
$p\overline{K}^0$		(2.5 ± 0.7) %		872
$pK^-\pi^+$	[k]	(5.0 ± 1.3) %		822
$p\overline{K}^*(892)^0$	[l]	(1.8 ± 0.6) %		681
$\Delta(1232)^{++}K^-$		(8 ± 5) $\times 10^{-3}$		709
$\Lambda(1520)\pi^+$	[l]	$(\ 4.5 \pm \frac{2.5}{2.1}) \times 10^{-3}$		626
$pK^-\pi^+$ nonresonant		(2.8 ± 0.9) %		822
$p\overline{K}^0\eta$		(1.3 ± 0.4) %		567
$p\overline{K}^0\pi^+\pi^-$		(2.4 ± 1.1) %		753
$pK^-\pi^+\pi^0$		seen		758
$pK^*(892)^-\pi^+$	[l]	(1.1 ± 0.6) %		579
$p(K^-\pi^+)_{\text{nonresonant}}\pi^0$		(3.6 ± 1.2) %		758
$\Delta(1232)\overline{K}^*(892)$		seen		416
$pK^-\pi^+\pi^+\pi^-$		(1.1 ± 0.8) $\times 10^{-3}$		670
$pK^-\pi^+\pi^0\pi^0$		(8 ± 4) $\times 10^{-3}$		676
$pK^-\pi^+\pi^0\pi^0\pi^0$		(5.0 ± 3.4) $\times 10^{-3}$		573
Hadronic modes with a p and zero or two K's				
$p\pi^+\pi^-$		(3.5 ± 2.0) $\times 10^{-3}$		926
$pf_0(980)$	[l]	(2.8 ± 1.9) $\times 10^{-3}$		621
$p\pi^+\pi^+\pi^-\pi^-$		(1.8 ± 1.2) $\times 10^{-3}$		851
pK^+K^-		(2.3 ± 0.9) $\times 10^{-3}$		615
$p\phi$	[l]	(1.2 ± 0.5) $\times 10^{-3}$		589
Hadronic modes with a hyperon				
$\Lambda\pi^+$		(9.0 ± 2.8) $\times 10^{-3}$		863
$\Lambda\pi^+\pi^0$		(3.6 ± 1.3) %		843
$\Lambda\rho^+$		< 5 %	CL=95%	638
$\Lambda\pi^+\pi^+\pi^-$		(3.3 ± 1.0) %		806
$\Lambda\pi^+\eta$		(1.7 ± 0.6) %		690
$\Sigma(1385)^+\eta$	[l]	(8.5 ± 3.3) $\times 10^{-3}$		569
$\Lambda K^+\overline{K}^0$		(6.0 ± 2.1) $\times 10^{-3}$		441
$\Sigma^0\pi^+$		(9.9 ± 3.2) $\times 10^{-3}$		824
$\Sigma^+\pi^0$		(1.00± 0.34) %		826
$\Sigma^+\eta$		(5.5 ± 2.3) $\times 10^{-3}$		712
$\Sigma^+\pi^+\pi^-$		(3.4 ± 1.0) %		803
$\Sigma^+\rho^0$		< 1.4 %	CL=95%	578
$\Sigma^-\pi^+\pi^+$		(1.8 ± 0.8) %		798
$\Sigma^0\pi^+\pi^0$		(1.8 ± 0.8) %		802
$\Sigma^0\pi^+\pi^+\pi^-$		(1.1 ± 0.4) %		762
$\Sigma^+\pi^+\pi^-\pi^0$		—		766
$\Sigma^+\omega$	[l]	(2.7 ± 1.0) %		568
$\Sigma^+\pi^+\pi^+\pi^-\pi^-$		$(\ 3.0 \pm \frac{4.1}{2.1}) \times 10^{-3}$		707
$\Sigma^+K^+K^-$		(3.5 ± 1.2) $\times 10^{-3}$		346
$\Sigma^+\phi$	[l]	(3.5 ± 1.7) $\times 10^{-3}$		292
$\Sigma^+K^+\pi^-$		$(\ 7 \pm \frac{6}{4}) \times 10^{-3}$		668
Ξ^0K^+		(3.9 ± 1.4) $\times 10^{-3}$		652
$\Xi^-K^+\pi^+$		(4.9 ± 1.7) $\times 10^{-3}$		564
$\Xi(1530)^0K^+$	[l]	(2.6 ± 1.0) $\times 10^{-3}$		471
Semileptonic modes				
$\Lambda\ell^+\nu_\ell$	[m]	(2.0 ± 0.6) %		–
$\Lambda e^+\nu_e$		(2.1 ± 0.6) %		–
$\Lambda\mu^+\nu_\mu$		(2.0 ± 0.7) %		–
e^+ anything		(4.5 ± 1.7) %		–
pe^+ anything		(1.8 ± 0.9) %		–
Λe^+ anything		—		–
$\Lambda\mu^+$ anything		—		–
$\Lambda\ell^+\nu_\ell$ anything		—		–
Inclusive modes				
p anything		(50 ±16) %		–
p anything (no Λ)		(12 ±19) %		–
p hadrons		—		–
n anything		(50 ±16) %		–
n anything (no Λ)		(29 ±17) %		–
Λ anything		(35 ±11) %	S=1.4	–
$\Sigma^\pm$ anything	[n]	(10 ± 5) %		–

$\Delta C = 1$ weak neutral current ($C1$) modes, or Lepton number (L) violating modes

$p\mu^+\mu^-$	$C1$	$<$ 3.4	$\times 10^{-4}$	CL=90%	936
$\Sigma^-\mu^+\mu^+$	L	$<$ 7.0	$\times 10^{-4}$	CL=90%	811

$\Lambda_c(2593)^+$

$I(J^P) = 0(\frac{1}{2}^-)$

The spin-parity follows from the fact that $\Sigma_c(2455)\pi$ decays, with little available phase space, are dominant.

Mass $m = 2593.9 \pm 0.8$ MeV
$m - m_{\Lambda_c^+} = 308.9 \pm 0.6$ MeV (S = 1.1)
Full width $\Gamma = 3.6^{+2.0}_{-1.3}$ MeV

$\Lambda_c^+\pi\pi$ and its submode $\Sigma_c(2455)\pi$ — the latter just barely — are the only strong decays allowed to an excited Λ_c^+ having this mass; and the $\Lambda_c^+\pi^+\pi^-$ mode seems to be largely via $\Sigma_c^{++}\pi^-$ or $\Sigma_c^0\pi^+$.

$\Lambda_c(2593)^+$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Lambda_c^+\pi^+\pi^-$	[o] ≈ 67 %	124
$\Sigma_c(2455)^{++}\pi^-$	24 ± 7 %	17
$\Sigma_c(2455)^0\pi^+$	24 ± 7 %	23
$\Lambda_c^+\pi^+\pi^-$ 3-body	18 ± 10 %	124
$\Lambda_c^+\pi^0$	not seen	261
$\Lambda_c^+\gamma$	not seen	290

$\Lambda_c(2625)^+$

$I(J^P) = 0(?^?)$

J^P is expected to be $3/2^-$.

Mass $m = 2626.6 \pm 0.8$ MeV (S = 1.2)
$m - m_{\Lambda_c^+} = 341.7 \pm 0.6$ MeV (S = 1.6)
Full width $\Gamma < 1.9$ MeV, CL = 90%

$\Lambda_c^+\pi\pi$ and its submode $\Sigma(2455)\pi$ are the only strong decays allowed to an excited Λ_c^+ having this mass.

$\Lambda_c(2625)^+$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Lambda_c^+\pi^+\pi^-$	seen	184
$\Sigma_c(2455)^{++}\pi^-$	small	100
$\Sigma_c(2455)^0\pi^+$	small	101
$\Lambda_c^+\pi^+\pi^-$ 3-body	large	184
$\Lambda_c^+\pi^0$	not seen	293
$\Lambda_c^+\gamma$	not seen	319

$\Sigma_c(2455)$

$I(J^P) = 1(\frac{1}{2}^+)$

J^P not confirmed; $\frac{1}{2}^+$ is the quark model prediction.

$\Sigma_c(2455)^{++}$ mass $m = 2452.8 \pm 0.6$ MeV
$\Sigma_c(2455)^+$ mass $m = 2453.6 \pm 0.9$ MeV
$\Sigma_c(2455)^0$ mass $m = 2452.2 \pm 0.6$ MeV
$m_{\Sigma_c^{++}} - m_{\Lambda_c^+} = 167.87 \pm 0.19$ MeV
$m_{\Sigma_c^+} - m_{\Lambda_c^+} = 168.7 \pm 0.6$ MeV
$m_{\Sigma_c^0} - m_{\Lambda_c^+} = 167.30 \pm 0.20$ MeV
$m_{\Sigma_c^{++}} - m_{\Sigma_c^0} = 0.57 \pm 0.23$ MeV
$m_{\Sigma_c^+} - m_{\Sigma_c^0} = 1.4 \pm 0.6$ MeV

$\Lambda_c^+\pi$ is the only strong decay allowed to a Σ_c having this mass.

$\Sigma_c(2455)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Lambda_c^+\pi$	≈ 100 %	90

$\Sigma_c(2520)$

$I(J^P) = 1(?^?)$

$\Sigma_c(2520)^{++}$ mass $m = 2519.4 \pm 1.5$ MeV
$\Sigma_c(2520)^0$ mass $m = 2517.5 \pm 1.4$ MeV
$m_{\Sigma_c(2520)^{++}} - m_{\Lambda_c^+} = 234.5 \pm 1.4$ MeV
$m_{\Sigma_c(2520)^0} - m_{\Lambda_c^+} = 232.6 \pm 1.3$ MeV
$m_{\Sigma_c(2520)^{++}} - m_{\Sigma_c(2520)^0} = 1.9 \pm 1.9$ MeV
$\Sigma_c(2520)^{++}$ full width $\Gamma = 18 \pm 5$ MeV
$\Sigma_c(2520)^0$ full width $\Gamma = 13 \pm 5$ MeV

Ξ_c^+

$I(J^P) = \frac{1}{2}(\frac{1}{2}^+)$

$I(J^P)$ not confirmed; $\frac{1}{2}(\frac{1}{2}^+)$ is the quark model prediction.

Mass $m = 2465.6 \pm 1.4$ MeV
Mean life $\tau = (0.35^{+0.07}_{-0.04}) \times 10^{-12}$ s
$c\tau = 106\ \mu$m

Ξ_c^+ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Lambda K^-\pi^+\pi^+$	seen	784
$\Lambda\overline{K}^*(892)^0\pi^+$	not seen	601
$\Sigma(1385)^+K^-\pi^+$	not seen	676
$\Sigma^+K^-\pi^+$	seen	808
$\Sigma^+\overline{K}^*(892)^0$	seen	653
$\Sigma^0K^-\pi^+\pi^+$	seen	733
$\Xi^0\pi^+$	seen	875
$\Xi^-\pi^+\pi^+$	seen	850
$\Xi(1530)^0\pi^+$	not seen	748
$\Xi^0\pi^+\pi^0$	seen	854
$\Xi^0\pi^+\pi^+\pi^-$	seen	817
$\Xi^0e^+\nu_e$	seen	882

Ξ_c^0

$I(J^P) = \frac{1}{2}(\frac{1}{2}^+)$

$I(J^P)$ not confirmed; $\frac{1}{2}(\frac{1}{2}^+)$ is the quark model prediction.

Mass $m = 2470.3 \pm 1.8$ MeV (S = 1.3)
$m_{\Xi_c^0} - m_{\Xi_c^+} = 4.7 \pm 2.1$ MeV (S = 1.2)
Mean life $\tau = (0.098^{+0.023}_{-0.015}) \times 10^{-12}$ s
$c\tau = 29\ \mu$m

Ξ_c^0 DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Lambda\overline{K}^0$	seen	864
$\Xi^-\pi^+$	seen	875
$\Xi^-\pi^+\pi^+\pi^-$	seen	816
$pK^-\overline{K}^*(892)^0$	seen	406
Ω^-K^+	seen	522
$\Xi^-e^+\nu_e$	seen	882
$\Xi^-\ell^+$ anything	seen	–

$\Xi_c(2645)$

$I(J^P) = ?(?^?)$

$\Xi_c(2645)^+$ mass $m = 2644.6 \pm 2.1$ MeV (S = 1.2)
$\Xi_c(2645)^0$ mass $m = 2643.8 \pm 1.8$ MeV
$m_{\Xi_c(2645)^+} - m_{\Xi_c^0} = 174.3 \pm 1.1$ MeV
$m_{\Xi_c(2645)^0} - m_{\Xi_c^+} = 178.2 \pm 1.1$ MeV
$\Xi_c(2645)^+$ full width $\Gamma < 3.1$ MeV, CL = 90%
$\Xi_c(2645)^0$ full width $\Gamma < 5.5$ MeV, CL = 90%

$\Xi_c\pi$ is the only strong decay allowed to a Ξ_c resonance having this mass.

$\Xi_c(2645)$ DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Xi_c^0\pi^+$	seen	101
$\Xi_c^+\pi^-$	seen	107

Ω_c^0 $I(J^P) = 0(\frac{1}{2}^+)$

$I(J^P)$ not confirmed; $0(\frac{1}{2}^+)$ is the quark model prediction.

Mass $m = 2704 \pm 4$ MeV (S = 1.8)
Mean life $\tau = (0.064 \pm 0.020) \times 10^{-12}$ s
$c\tau = 19$ μm

Ω_c^0 DECAY MODES	Fraction (Γ_i/Γ)	p (MeV/c)
$\Sigma^+ K^- K^- \pi^+$	seen	697
$\Xi^- K^- \pi^+ \pi^+$	seen	838
$\Omega^- \pi^+$	seen	827
$\Omega^- \pi^- \pi^+ \pi^+$	seen	759

BOTTOM BARYONS ($B = -1$)

$\Lambda_b^0 = udb$, $\Xi_b^0 = usb$, $\Xi_b^- = dsb$

Λ_b^0 $I(J^P) = 0(\frac{1}{2}^+)$

$I(J^P)$ not yet measured; $0(\frac{1}{2}^+)$ is the quark model prediction.

Mass $m = 5624 \pm 9$ MeV (S = 1.8)
Mean life $\tau = (1.24 \pm 0.08) \times 10^{-12}$ s
$c\tau = 372$ μm

These branching fractions are actually an average over weakly decaying b-baryons weighted by their production rates in Z decay (or high-energy $p\bar{p}$) branching ratios and detection efficiencies. They scale with the LEP Λ_b production fraction B($b \to \Lambda_b$) and are evaluated for our value B($b \to \Lambda_b$) $= (10.1^{+3.9}_{-3.1})$%.

The branching fractions B(b-baryon $\to \Lambda \ell^- \bar{\nu}_\ell$ anything) and B($\Lambda_b^0 \to \Lambda_c^+ \ell^- \bar{\nu}_\ell$ anything) are not pure measurements because the underlying measured products of these with B($b \to \Lambda_b$) were used to determine B($b \to \Lambda_b$) as described in the note "Production and Decay of b-Flavored Hadrons."

Λ_b^0 DECAY MODES		Fraction (Γ_i/Γ)	Confidence level	p (MeV/c)
$J/\psi(1S)\Lambda$		$(4.7 \pm 2.8) \times 10^{-4}$		1744
$\Lambda_c^+ \pi^-$		seen		2345
$\Lambda_c^+ a_1(1260)^-$		seen		2156
$\Lambda_c^+ \ell^- \bar{\nu}_\ell$ anything	[p]	$(9.0^{+3.1}_{-3.8})$ %		–
$p\pi^-$		$< 5.0 \times 10^{-5}$	90%	2732
pK^-		$< 5.0 \times 10^{-5}$	90%	2711

b-baryon ADMIXTURE (Λ_b, Ξ_b, Σ_b, Ω_b)

Mean life $\tau = (1.20 \pm 0.07) \times 10^{-12}$ s

These branching fractions are actually an average over weakly decaying b-baryons weighted by their production rates in Z decay (or high-energy $p\bar{p}$) branching ratios and detection efficiencies. They scale with the LEP Λ_b production fraction B($b \to \Lambda_b$) and are evaluated for our value B($b \to \Lambda_b$) $= (10.1^{+3.9}_{-3.1})$%.

The branching fractions B(b-baryon $\to \Lambda \ell^- \bar{\nu}_\ell$ anything) and B($\Lambda_b^0 \to \Lambda_c^+ \ell^- \bar{\nu}_\ell$ anything) are not pure measurements because the underlying measured products of these with B($b \to \Lambda_b$) were used to determine B($b \to \Lambda_b$) as described in the note "Production and Decay of b-Flavored Hadrons."

b-baryon ADMIXTURE (Λ_b, Ξ_b, Σ_b, Ω_b)	Fraction (Γ_i/Γ)	p (MeV/c)
$p\mu^- \bar{\nu}$ anything	(4.9 ± 2.4) %	–
$\Lambda \ell^- \bar{\nu}_\ell$ anything	$(3.1^{+1.0}_{-1.2})$ %	–
$\Lambda/\bar{\Lambda}$ anything	(35^{+12}_{-14}) %	–
$\Xi^- \ell^- \bar{\nu}_\ell$ anything	$(5.5^{+2.0}_{-2.4}) \times 10^{-3}$	–

NOTES

This Summary Table only includes established baryons. The Particle Listings include evidence for other baryons. The masses, widths, and branching fractions for the resonances in this Table are Breit-Wigner parameters, but pole positions are also given for most of the N and Δ resonances.

For most of the resonances, the parameters come from various partial-wave analyses of more or less the same sets of data, and it is not appropriate to treat the results of the analyses as independent or to average them together. Furthermore, the systematic errors on the results are not well understood. Thus, we usually only give ranges for the parameters. We then also give a best guess for the mass (as part of the name of the resonance) and for the width. The *Note on N and Δ Resonances* and the *Note on Λ and Σ Resonances* in the Particle Listings review the partial-wave analyses.

When a quantity has "(S = ...)" to its right, the error on the quantity has been enlarged by the "scale factor" S, defined as $S = \sqrt{\chi^2/(N-1)}$, where N is the number of measurements used in calculating the quantity. We do this when S > 1, which often indicates that the measurements are inconsistent. When S > 1.25, we also show in the Particle Listings an ideogram of the measurements. For more about S, see the Introduction.

A decay momentum p is given for each decay mode. For a 2-body decay, p is the momentum of each decay product in the rest frame of the decaying particle. For a 3-or-more-body decay, p is the largest momentum any of the products can have in this frame. For any resonance, the *nominal* mass is used in calculating p. A dagger ("†") in this column indicates that the mode is forbidden when the nominal masses of resonances are used, but is in fact allowed due to the nonzero widths of the resonances.

[a] The masses of the p and n are most precisely known in u (unified atomic mass units). The conversion factor to MeV, 1 u = 931.49432 ± 0.00028 MeV, is less well known than are the masses in u.

[b] The limit is from neutrality-of-matter experiments; it assumes $q_n = q_p + q_e$. See also the charge of the neutron.

[c] The first limit is geochemical and independent of decay mode. The second entry, a range of limits, assumes the dominant decay modes are among those investigated. For antiprotons the best limit, inferred from the observation of cosmic ray $\bar{p}$'s is $\tau_{\bar{p}} > 10^7$ yr, the cosmic-ray storage time, but this limit depends on a number of assumptions. The best direct observation of stored antiprotons gives $\tau_{\bar{p}}/B(\bar{p} \to e^- \gamma) > 1848$ yr.

[d] There is some controversy about whether nuclear physics and model dependence complicate the analysis for bound neutrons (from which the best limit comes). The second limit here is from reactor experiments with free neutrons.

[e] The parameters g_A, g_V, and g_{WM} for semileptonic modes are defined by $\bar{B}_f[\gamma_\lambda(g_V + g_A\gamma_5) + i(g_{WM}/m_{B_i})\,\sigma_{\lambda\nu}\,q^\nu]B_i$, and ϕ_{AV} is defined by $g_A/g_V = |g_A/g_V|e^{i\phi_{AV}}$. See the "Note on Baryon Decay Parameters" in the neutron Particle Listings.

[f] Time-reversal invariance requires this to be 0° or 180°.

[g] The decay parameters γ and Δ are calculated from α and ϕ using

$$\gamma = \sqrt{1-\alpha^2}\cos\phi, \qquad \tan\Delta = -\frac{1}{\alpha}\sqrt{1-\alpha^2}\sin\phi.$$

See the "Note on Baryon Decay Parameters" in the neutron Particle Listings.

[h] See the Particle Listings for the pion momentum range used in this measurement.

[i] The error given here is only an educated guess. It is larger than the error on the weighted average of the published values.

[j] A theoretical value using QED.

[k] See the "Note on Λ_c^+ Branching Fractions" in the Branching Fractions of the Λ_c^+ Particle Listings.

[l] This branching fraction includes all the decay modes of the final-state resonance.

[m] An ℓ indicates an e or a μ mode, not a sum over these modes.

[n] The value is for the sum of the charge states of particle/antiparticle states indicated.

[o] Assuming isospin conservation, so that the other third is $\Lambda_c^+ \pi^0 \pi^0$.

[p] Not a pure measurement. See note at head of Λ_b^0 Decay Modes.

MONOPOLES, SUPERSYMMETRY, COMPOSITENESS, etc., SEARCHES FOR

Magnetic Monopole Searches

Isolated supermassive monopole candidate events have not been confirmed. The most sensitive experiments obtain negative results.

Best cosmic-ray supermassive monopole flux limit:

$< 1.0 \times 10^{-15}$ cm^{-2}sr^{-1}s^{-1} for $1.1 \times 10^{-4} < \beta < 0.1$

Supersymmetric Particle Searches

Limits are based on the Minimal Supersymmetric Standard Model. Assumptions include: 1) $\widetilde{\chi}_1^0$ (or $\widetilde{\gamma}$) is lightest supersymmetric particle; 2) R-parity is conserved; 3) All scalar quarks (except $\widetilde{t}_L$ and $\widetilde{t}_R$) are degenerate in mass, and $m_{\widetilde{q}_R} = m_{\widetilde{q}_L}$. 4) Limits for selectrons and smuons refer to the $\widetilde{\ell}_R$ states.

See the Particle Listings for a Note giving details of supersymmetry.

$\widetilde{\chi}_i^0$ — neutralinos (mixtures of $\widetilde{\gamma}$, $\widetilde{Z}^0$, and $\widetilde{H}_i^0$)

Mass $m_{\widetilde{\chi}_1^0} > 10.9$ GeV, CL = 95%

Mass $m_{\widetilde{\chi}_2^0} > 45.3$ GeV, CL = 95% [$\tan\beta > 1$]

Mass $m_{\widetilde{\chi}_3^0} > 75.8$ GeV, CL = 95% [$\tan\beta > 1$]

Mass $m_{\widetilde{\chi}_4^0} > 127$ GeV, CL = 95% [$\tan\beta > 3$]

$\widetilde{\chi}_i^\pm$ — charginos (mixtures of $\widetilde{W}^\pm$ and $\widetilde{H}_i^\pm$)

Mass $m_{\widetilde{\chi}_1^\pm} > 65.7$ GeV, CL = 95% [$m_{\widetilde{\chi}_1^\pm} - m_{\widetilde{\chi}_1^0} \geq 2$ GeV]

Mass $m_{\widetilde{\chi}_2^\pm} > 99$ GeV, CL = 95% [GUT relations assumed]

$\widetilde{\nu}$ — scalar neutrino (sneutrino)

Mass $m > 37.1$ GeV, CL = 95% [one flavor]

Mass $m > 43.1$ GeV, CL = 95% [three degenerate flavors]

$\widetilde{e}$ — scalar electron (selectron)

Mass $m > 58$ GeV, CL = 95% [$m_{\widetilde{e}_R} - m_{\widetilde{\chi}_1^0} \geq 4$ GeV]

$\widetilde{\mu}$ — scalar muon (smuon)

Mass $m > 55.6$ GeV, CL = 95% [$m_{\widetilde{\mu}_R} - m_{\widetilde{\chi}_1^0} \geq 4$ GeV]

$\widetilde{\tau}$ — scalar tau (stau)

Mass $m > 45$ GeV, CL = 95% [if $m_{\widetilde{\chi}_1^0} < 38$ GeV]

$\widetilde{q}$ — scalar quark (squark)

These limits include the effects of cascade decays, evaluated assuming a fixed value of the parameters μ and $\tan\beta$. The limits are weakly sensitive to these parameters over much of parameter space. Limits assume GUT relations between gaugino masses and the gauge coupling; in particular that for $|\mu|$ not small, $m_{\widetilde{\chi}_1^0} \approx m_{\widetilde{g}}/6$.

Mass $m > 176$ GeV, CL = 95% [any $m_{\widetilde{g}} < 300$ GeV, $\mu = -250$ GeV, $\tan\beta = 2$]

Mass $m > 224$ GeV, CL = 95% [$m_{\widetilde{g}} \leq m_{\widetilde{q}}$, $\mu = -400$ GeV, $\tan\beta = 4$]

$\widetilde{g}$ — gluino

There is some controversy on whether gluinos in a low-mass window ($1 \lesssim m_{\widetilde{g}} \lesssim 5$ GeV) are excluded or not. See the Supersymmetry Listings for details.

The limits summarised here refere to the high-mass region ($m_{\widetilde{g}} \gtrsim 5$ GeV), and include the effects of cascade decays, evaluated assuming a fixed value of the parameters μ and $\tan\beta$. The limits are weakly sensitive to these parameters over much of parameter space. Limits assume GUT relations between gaugino masses and the gauge coupling; in particular that for $|\mu|$ not small, $m_{\widetilde{\chi}_1^0} \approx m_{\widetilde{g}}/6$.

Mass $m > 173$ GeV, CL = 95% [any $m_{\widetilde{q}}$, $\mu = -200$ GeV, $\tan\beta = 2$]

Mass $m > 212$ GeV, CL = 95% [$m_{\widetilde{g}} \geq m_{\widetilde{q}}$, $\mu = -250$ GeV, $\tan\beta = 2$]

Quark and Lepton Compositeness, Searches for

Scale Limits Λ for Contact Interactions (the lowest dimensional interactions with four fermions)

If the Lagrangian has the form

$$\pm \frac{g^2}{2\Lambda^2}\, \bar{\psi}_L \gamma_\mu \psi_L \bar{\psi}_L \gamma^\mu \psi_L$$

(with $g^2/4\pi$ set equal to 1), then we define $\Lambda = \Lambda_{LL}^\pm$. For the full definitions and for other forms, see the Note in the Listings on Searches for Quark and Lepton Compositeness in the full *Review* and the original literature.

$\Lambda_{LL}^+(eeee)$ > 2.4 TeV, CL = 95%

$\Lambda_{LL}^-(eeee)$ > 3.6 TeV, CL = 95%

$\Lambda_{LL}^+(ee\mu\mu)$ > 2.6 TeV, CL = 95%

$\Lambda_{LL}^-(ee\mu\mu)$ > 2.9 TeV, CL = 95%

$\Lambda_{LL}^+(ee\tau\tau)$ > 1.9 TeV, CL = 95%

$\Lambda_{LL}^-(ee\tau\tau)$ > 3.0 TeV, CL = 95%

$\Lambda_{LL}^+(\ell\ell\ell\ell)$ > 3.5 TeV, CL = 95%

$\Lambda_{LL}^-(\ell\ell\ell\ell)$ > 3.8 TeV, CL = 95%

$\Lambda_{LL}^+(eeqq)$ > 2.5 TeV, CL = 95%

$\Lambda_{LL}^-(eeqq)$ > 3.7 TeV, CL = 95%

$\Lambda_{LL}^+(eebb)$ > 3.1 TeV, CL = 95%

$\Lambda_{LL}^-(eebb)$ > 2.9 TeV, CL = 95%

$\Lambda_{LL}^+(\mu\mu qq)$ > 2.9 TeV, CL = 95%

$\Lambda_{LL}^-(\mu\mu qq)$ > 4.2 TeV, CL = 95%

$\Lambda_{LR}^\pm(\nu_\mu \nu_e \mu e)$ > 3.1 TeV, CL = 90%

$\Lambda_{LL}^\pm(qqqq)$ > 1.6 TeV, CL = 95%

Excited Leptons

The limits from $\ell^{*+}\ell^{*-}$ do not depend on λ (where λ is the $\ell\ell^*$ transition coupling). The λ-dependent limits assume chiral coupling, except for the third limit for e^* which is for nonchiral coupling. For chiral coupling, this limit corresponds to $\lambda_\gamma = \sqrt{2}$.

$e^{*\pm}$ — excited electron

Mass $m > 85.0$ GeV, CL = 95% (from $e^{*+}e^{*-}$)

Mass $m > 91$ GeV, CL = 95% (if $\lambda_Z > 1$)

Mass $m > 194$ GeV, CL = 95% (if $\lambda_\gamma = 1$)

$\mu^{*\pm}$ — excited muon

Mass $m > 85.3$ GeV, CL = 95% (from $\mu^{*+}\mu^{*-}$)

Mass $m > 91$ GeV, CL = 95% (if $\lambda_Z > 1$)

$\tau^{*\pm}$ — excited tau

Mass $m > 84.6$ GeV, CL = 95% (from $\tau^{*+}\tau^{*-}$)

Mass $m > 90$ GeV, CL = 95% (if $\lambda_Z > 0.18$)

ν^* — excited neutrino

Mass $m > 84.9$ GeV, CL = 95% (from $\nu^*\overline{\nu}^*$)

Mass $m > 91$ GeV, CL = 95% (if $\lambda_Z > 1$)

Mass $m =$ none 40–96 GeV, CL = 95% (from $ep \rightarrow \nu^* X$)

q^* — excited quark

Mass $m > 45.6$ GeV, CL = 95% (from $q^*\overline{q}^*$)

Mass $m > 88$ GeV, CL = 95% (if $\lambda_Z > 1$)

Mass $m > 570$ GeV, CL = 95% ($p\overline{p} \rightarrow q^* X$)

Color Sextet and Octet Particles

Color Sextet Quarks (q_6)

Mass $m > 84$ GeV, CL = 95% (Stable q_6)

Color Octet Charged Leptons (ℓ_8)

Mass $m > 86$ GeV, CL = 95% (Stable ℓ_8)

Color Octet Neutrinos (ν_8)

Mass $m > 110$ GeV, CL = 90% ($\nu_8 \rightarrow \nu g$)

TESTS OF CONSERVATION LAWS

Revised by L. Wolfenstein and T.G. Trippe (May 1998).

In keeping with the current interest in tests of conservation laws, we collect together a Table of experimental limits on all weak and electromagnetic decays, mass differences, and moments, and on a few reactions, whose observation would violate conservation laws. The Table is given only in the full *Review of Particle Physics*, not in the Particle Physics Booklet. For the benefit of Booklet readers, we include the best limits from the Table in the following text. Limits in this text are for CL=90% unless otherwise specified. The Table is in two parts: "Discrete Space-Time Symmetries" *i.e.*, C, T, PT, TT, CP, and CPT; and "Number Conservation Laws" *i.e.*, lepton, baryon, hadronic flavor, and charge conservation. The references for these data can be found in the the Particle Listings in the *Review*. A discussion of these tests follows.

CPT INVARIANCE

General principles of relativistic field theory require invariance under the combined transformation CPT. The simplest tests of CPT invariance are the equality of the masses and lifetimes of a particle and its antiparticle. The best test comes from the limit on the mass difference between K^0 and $\overline{K}^0$. Any such difference contributes to the CP-violating parameter ϵ. Assuming CPT invariance, ϕ_ϵ, the phase of ϵ should be very close to 44°. (See the "Note on CP Violation in K_L^0 Decay" in the Particle Listings.) In contrast, if the entire source of CP violation in K^0 decays were a $K^0 - \overline{K}^0$ mass difference, ϕ_ϵ would be $44° + 90°$. Assuming that there is no other source of CPT violation than this mass difference, it is possible to deduce that [1]

$$m_{\overline{K}^0} - m_{K^0} \approx \frac{2(m_{K_L^0} - m_{K_S^0})\,|\eta|\,(\frac{2}{3}\phi_{+-} + \frac{1}{3}\phi_{00} - \phi_0)}{\sin\phi_0}\,,$$

where $\phi_0 = 43.5°$ with an uncertainty of less than 0.1°. Using our best values of the CP-violation parameters, we get $|(m_{\overline{K}^0} - m_{K^0})/m_{K^0}| \leq 10^{-18}$. Limits can also be placed on specific CPT-violating decay amplitudes. Given the small value of $(1 - |\eta_{00}/\eta_{+-}|)$, the value of $\phi_{00} - \phi_{+-}$ provides a measure of CPT violation in $K_L^0 \to 2\pi$ decay. Results from CERN [1] and Fermilab [2] indicate no CPT-violating effect.

CP AND *T* INVARIANCE

Given CPT invariance, CP violation and T violation are equivalent. So far the only evidence for CP or T violation comes from the measurements of η_{+-}, η_{00}, and the semileptonic decay charge asymmetry for K_L *e.g.*, $|\eta_{+-}| = |A(K_L^0 \to \pi^+\pi^-)/A(K_S^0 \to \pi^+\pi^-)| = (2.285 \pm 0.019) \times 10^{-3}$ and $[\Gamma(K_L^0 \to \pi^- e^+ \nu) - \Gamma(K_L^0 \to \pi^+ e^- \overline{\nu})]/[\text{sum}] = (0.333 \pm 0.014)\%$. Other searches for CP or T violation divide into (a) those that involve weak interactions or parity violation, and (b) those that involve processes otherwise allowed by the strong or electromagnetic interactions. In class (a) the most sensitive are probably the searches for an electric dipole moment of the neutron, measured to be $< 1.0 \times 10^{-25}$ e cm, and the electron $(-0.18 \pm 0.16) \times 10^{-26}$ e cm. A nonzero value requires both P and T violation. Class (b) includes the search for C violation in η decay, believed to be an electromagnetic process *e.g.*, as measured by $\Gamma(\eta \to \mu^+\mu^-\pi^0)/\Gamma(\eta \to \text{all}) < 5 \times 10^{-6}$, and searches for T violation in a number of nuclear and electromagnetic reactions.

CONSERVATION OF LEPTON NUMBERS

Present experimental evidence and the standard electroweak theory are consistent with the absolute conservation of three separate lepton numbers: electron number L_e, muon number L_μ, and tau number L_τ. Searches for violations are of the following types:

a) $\Delta L = 2$ for one type of lepton. The best limit comes from the search for neutrinoless double beta decay $(Z, A) \to (Z + 2, A) + e^- + e^-$. The best laboratory limit is $t_{1/2} > 1.1 \times 10^{25}$ yr (CL=90%) for ^{76}Ge.

b) Conversion of one lepton type to another. For purely leptonic processes, the best limits are on $\mu \to e\gamma$ and $\mu \to 3e$, measured as $\Gamma(\mu \to e\gamma)/\Gamma(\mu \to \text{all}) < 5 \times 10^{-11}$ and $\Gamma(\mu \to 3e)/\Gamma(\mu \to \text{all}) < 1.0 \times 10^{-12}$. For semileptonic processes, the best limit comes from the coherent conversion process in a muonic atom, $\mu^- + (Z, A) \to e^- + (Z, A)$, measured as $\Gamma(\mu^-\text{Ti} \to e^-\text{Ti})/\Gamma(\mu^-\text{Ti} \to \text{all}) < 4 \times 10^{-12}$. Of special interest is the case in which the hadronic flavor also changes, as in $K_L \to e\mu$ and $K^+ \to \pi^+ e^- \mu^+$, measured as $\Gamma(K_L \to e\mu)/\Gamma(K_L \to \text{all}) < 3.3 \times 10^{-11}$ and $\Gamma(K^+ \to \pi^+ e^- \mu^+)/\Gamma(K^+ \to \text{all}) < 2.1 \times 10^{-10}$. Limits on the conversion of τ into e or μ are found in τ decay and are much less stringent than those for $\mu \to e$ conversion, *e.g.*, $\Gamma(\tau \to \mu\gamma)/\Gamma(\tau \to \text{all}) < 3.0 \times 10^{-6}$ and $\Gamma(\tau \to e\gamma)/\Gamma(\tau \to \text{all}) < 2.7 \times 10^{-6}$.

c) Conversion of one type of lepton into another type of antilepton. The case most studied is $\mu^- + (Z, A) \to e^+ + (Z - 2, A)$, the strongest limit being $\Gamma(\mu^-\text{Ti} \to e^+\text{Ca})/\Gamma(\mu^-\text{Ti} \to \text{all}) < 9 \times 10^{-11}$.

d) Relation to neutrino mass. If neutrinos have mass, then it is expected even in the standard electroweak theory that the lepton numbers are not separately conserved, as a consequence of lepton mixing analogous to Cabibbo quark mixing. However, in this case lepton-number-violating processes such as $\mu \to e\gamma$ are expected to have extremely small probability. For small neutrino masses, the lepton-number violation would be observed first in neutrino oscillations, which have been the subject of extensive experimental searches. For example, searches for $\overline{\nu}_e$ disappearance, which we label as $\overline{\nu}_e \not\to \overline{\nu}_e$, give measured limits $\Delta(m^2) < 9 \times 10^{-4}$ eV^2 for $\sin^2(2\theta) = 1$, and $\sin^2(2\theta) < 0.02$ for large $\Delta(m^2)$, where θ is the neutrino mixing angle. Possible evidence for mixing has come from two sources. The deficit in the solar neutrino flux compared with solar model calculations could be explained by oscillations with $\Delta(m^2) \leq 10^{-5}$ eV^2 causing the disappearance of ν_e. In addition underground detectors observing neutrinos produced by cosmic rays in the atmosphere have measured a ν_μ/ν_e ratio much less than expected and also a deficiency of upward going ν_μ compared to downward. This could be explained by oscillations leading to the disappearance of ν_μ with $\Delta(m^2)$ of the order 10^{-2}–10^{-3} eV^2.

CONSERVATION OF HADRONIC FLAVORS

In strong and electromagnetic interactions, hadronic flavor is conserved, *i.e.* the conversion of a quark of one flavor (d, u, s, c, b, t) into a quark of another flavor is forbidden. In the Standard Model, the weak interactions violate these conservation laws in a manner described by the Cabibbo-Kobayashi-Maskawa mixing (see the section "Cabibbo-Kobayashi-Maskawa Mixing Matrix"). The way in which these conservation laws are violated is tested as follows:

a) $\Delta S = \Delta Q$ rule. In the semileptonic decay of strange particles, the strangeness change equals the change in charge of the hadrons. Tests come from limits on decay rates such as

$\Gamma(\Sigma^+ \to ne^+\nu)/\Gamma(\Sigma^+ \to \text{all}) < 5 \times 10^{-6}$Γand from a detailed analysis of $K_L \to \pi e\nu$Γwhich yields the parameter xΓmeasured to be $(\mathrm{Re}\,x\Gamma\mathrm{Im}\,x) = (0.006 \pm 0.018\Gamma -0.003 \pm 0.026)$. Corresponding rules are $\Delta C = \Delta Q$ and $\Delta B = \Delta Q$.

b) Change of flavor by two units. In the Standard Model this occurs only in second-order weak interactions. The classic example is $\Delta S = 2$ via $K^0 - \overline{K}^0$ mixingΓwhich is directly measured by $m(K_S) - m(K_L) = (3.489 \pm 0.009) \times 10^{-12}$ MeV. There is now evidence for $B^0 - \overline{B}^0$ mixing $(\Delta B = 2)$Γwith the corresponding mass difference between the eigenstates $(m_{B^0_H} - m_{B^0_L}) = (0.723 \pm 0.032)\Gamma_{B^0} = (3.05 \pm 0.12) \times 10^{-10}$ MeVΓand for B^0_s–$\overline{B}^0_s$ mixingΓwith $(m_{B^0_{sH}} - m_{B^0_{sL}}) > 14\Gamma_{B^0_s}$ or $> 6 \times 10^{-9}$ MeV (CL=95%). No evidence exists for $D^0 - \overline{D}^0$ mixingΓwhich is expected to be much smaller in the Standard Model.

c) Flavor-changing neutral currents. In the Standard Model the neutral-current interactions do not change flavor. The low rate $\Gamma(K_L \to \mu^+\mu^-)/\Gamma(K_L \to \text{all}) = (7.2 \pm 0.5) \times 10^{-9}$ puts limits on such interactions; the nonzero value for this rate is attributed to a combination of the weak and electromagnetic interactions. The best test should come from $K^+ \to \pi^+\nu\overline{\nu}$Γ which occurs in the Standard Model only as a second-order weak process with a branching fraction of (1 to 8)×10^{-10}. Observation of one event has been reported [4]Γyielding $\Gamma(K^+ \to \pi^+\nu\overline{\nu})/\Gamma(K^+ \to \text{all}) = (4.2^{+9.7}_{-3.5}) \times 10^{-10}$. Limits for charm-changing or bottom-changing neutral currents are much less stringent: $\Gamma(D^0 \to \mu^+\mu^-)/\Gamma(D^0 \to \text{all}) < 4 \times 10^{-6}$ and $\Gamma(B^0 \to \mu^+\mu^-)/\Gamma(B^0 \to \text{all}) < 7 \times 10^{-7}$. One cannot isolate flavor-changing neutral current (FCNC) effects in non leptonic decays. For exampleΓthe FCNC transition $s \to d + (\overline{u} + u)$ is equivalent to the charged-current transition $s \to u + (\overline{u} + d)$. Tests for FCNC are therefore limited to hadron decays into lepton pairs. Such decays are expected only in second-order in the electroweak coupling in the Standard Model.

References

1. R. Carosi *et al.*Γ Phys. Lett. **B237**Γ303 (1990).
2. M. Karlsson *et al.*Γ Phys. Rev. Lett. **64**Γ2976 (1990); L.K. Gibbons *et al.*Γ Phys. Rev. Lett. **70**Γ1199 (1993).
3. B. Schwingenheuer *et al.*Γ Phys. Rev. Lett. **74**Γ4376 (1995).
4. S. Adler *et al.*Γ Phys. Rev. Lett. **79**Γ2204 (1997).

TESTS OF DISCRETE SPACE-TIME SYMMETRIES

CHARGE CONJUGATION (*C*) INVARIANCE

$\Gamma(\pi^0 \to 3\gamma)/\Gamma_{\text{total}}$		$<3.1 \times 10^{-8}$ΓCL = 90%
η *C*-nonconserving decay parameters		
$\pi^+\pi^-\pi^0$ left-right asymmetry parameter		$(0.09 \pm 0.17) \times 10^{-2}$
$\pi^+\pi^-\pi^0$ sextant asymmetry parameter		$(0.18 \pm 0.16) \times 10^{-2}$
$\pi^+\pi^-\pi^0$ quadrant asymmetry parameter		$(-0.17 \pm 0.17) \times 10^{-2}$
$\pi^+\pi^-\gamma$ left-right asymmetry parameter		$(0.9 \pm 0.4) \times 10^{-2}$
$\pi^+\pi^-\gamma$ parameter β (*D*-wave)		0.05 ± 0.06 (S = 1.5)
$\Gamma(\eta \to 3\gamma)/\Gamma_{\text{total}}$		$<5 \times 10^{-4}$ΓCL = 95%
$\Gamma(\eta \to \pi^0 e^+ e^-)/\Gamma_{\text{total}}$	[a]	$<4 \times 10^{-5}$ΓCL = 90%
$\Gamma(\eta \to \pi^0 \mu^+ \mu^-)/\Gamma_{\text{total}}$	[a]	$<5 \times 10^{-6}$ΓCL = 90%
$\Gamma(\omega(782) \to \eta\pi^0)/\Gamma_{\text{total}}$		$<1 \times 10^{-3}$ΓCL = 90%
$\Gamma(\omega(782) \to 3\pi^0)/\Gamma_{\text{total}}$		$<3 \times 10^{-4}$ΓCL = 90%
$\Gamma(\eta'(958) \to \pi^0 e^+ e^-)/\Gamma_{\text{total}}$	[a]	$<1.3 \times 10^{-2}$ΓCL = 90%
$\Gamma(\eta'(958) \to \eta e^+ e^-)/\Gamma_{\text{total}}$	[a]	$<1.1 \times 10^{-2}$ΓCL = 90%
$\Gamma(\eta'(958) \to 3\gamma)/\Gamma_{\text{total}}$		$<1.0 \times 10^{-4}$ΓCL = 90%
$\Gamma(\eta'(958) \to \mu^+\mu^-\pi^0)/\Gamma_{\text{total}}$	[a]	$<6.0 \times 10^{-5}$ΓCL = 90%
$\Gamma(\eta'(958) \to \mu^+\mu^-\eta)/\Gamma_{\text{total}}$	[a]	$<1.5 \times 10^{-5}$ΓCL = 90%

Limits are given at the 90% confidence levelΓwhile errors are given as ±1 standard deviation.

PARITY (*P*) INVARIANCE

e electric dipole moment		$(0.18 \pm 0.16) \times 10^{-26}$ *e* cm
μ electric dipole moment		$(3.7 \pm 3.4) \times 10^{-19}$ *e* cm
τ electric dipole moment (d_τ)		> -3.1 and $< 3.1 \times 10^{-16}$ *e* cmΓ CL = 95%
$\Gamma(\eta \to \pi^+\pi^-)/\Gamma_{\text{total}}$		$<9 \times 10^{-4}$ΓCL = 90%
$\Gamma(\eta'(958) \to \pi^+\pi^-)/\Gamma_{\text{total}}$		$<2 \times 10^{-2}$ΓCL = 90%
$\Gamma(\eta'(958) \to \pi^0\pi^0)/\Gamma_{\text{total}}$		$<9 \times 10^{-4}$ΓCL = 90%
p electric dipole moment		$(-4 \pm 6) \times 10^{-23}$ *e* cm
n electric dipole moment		$<0.97 \times 10^{-25}$ *e* cmΓCL = 90%
Λ electric dipole moment		$<1.5 \times 10^{-16}$ *e* cmΓCL = 95%

TIME REVERSAL (*T*) INVARIANCE

Limits on *e*, μ, τ, *p*, *n*, and Λ electric dipole moments under Parity Invariance above are also tests of Time Reversal Invariance.

μ decay parameters		
transverse e^+ polarization normal to plane of μ spinΓ e^+ momentum		0.007 ± 0.023
α'/A		$(0 \pm 4) \times 10^{-3}$
β'/A		$(2 \pm 6) \times 10^{-3}$
τ electric dipole moment (d_τ)		> -3.1 and $< 3.1 \times 10^{-16}$ *e* cmΓ CL = 95%
Im(ξ) in $K^\pm_{\mu 3}$ decay (from transverse μ pol.)		−0.017 ± 0.025
Im(ξ) in $K^0_{\mu 3}$ decay (from transverse μ pol.)		−0.007 ± 0.026
$n \to pe^-\nu$ decay parameters		
ϕ_{AV}Γphase of g_A relative to g_V	[b]	(180.07 ± 0.18)°
triple correlation coefficient *D*		$(-0.5 \pm 1.4) \times 10^{-3}$
triple correlation coefficient *D* for $\Sigma^- \to ne^-\nu_e$		0.11 ± 0.10

CP INVARIANCE

Re(d^W_τ)		$<0.56 \times 10^{-17}$ *e* cmΓCL = 95%
Im(d^W_τ)		$<1.5 \times 10^{-17}$ *e* cmΓCL = 95%
$\Gamma(\eta \to \pi^+\pi^-)/\Gamma_{\text{total}}$		$<9 \times 10^{-4}$ΓCL = 90%
$\Gamma(\eta'(958) \to \pi^+\pi^-)/\Gamma_{\text{total}}$		$<2 \times 10^{-2}$ΓCL = 90%
$\Gamma(\eta'(958) \to \pi^0\pi^0)/\Gamma_{\text{total}}$		$<9 \times 10^{-4}$ΓCL = 90%
$K^\pm \to \pi^\pm\pi^+\pi^-$ rate difference/average		(0.07 ± 0.12)%
$K^\pm \to \pi^\pm\pi^0\pi^0$ rate difference/average		(0.0 ± 0.6)%
$K^\pm \to \pi^\pm\pi^0\gamma$ rate difference/average		(0.9 ± 3.3)%
$(g_{\tau^-} - g_{\tau^+}) / (g_{\tau^-} + g_{\tau^+})$ for $K^\pm \to \pi^\pm\pi^+\pi^-$		(−0.7 ± 0.5)%
CP-violation parameters in K^0_S decay		
Im(η_{+-0}) = Im(A($K^0_S \to \pi^+\pi^-\pi^0$Γ *CP*-violating) / A($K^0_L \to \pi^+\pi^-\pi^0$))		−0.002 ± 0.008
Im(η_{000})^2 = Γ($K^0_S \to 3\pi^0$) / Γ($K^0_L \to 3\pi^0$)		<0.1ΓCL = 90%
charge asymmetry *j* for $K^0_L \to \pi^+\pi^-\pi^0$		0.0011 ± 0.0008
$\lvert\epsilon'_{+-\gamma}\rvert/\epsilon$ for $K^0_L \to \pi^+\pi^-\gamma$		<0.3ΓCL = 90%
$\Gamma(K^0_L \to \pi^0\mu^+\mu^-)/\Gamma_{\text{total}}$	[c]	$<5.1 \times 10^{-9}$ΓCL = 90%
$\Gamma(K^0_L \to \pi^0 e^+ e^-)/\Gamma_{\text{total}}$	[c]	$<4.3 \times 10^{-9}$ΓCL = 90%
$\Gamma(K^0_L \to \pi^0\nu\overline{\nu})/\Gamma_{\text{total}}$	[d]	$<5.8 \times 10^{-5}$ΓCL = 90%
$A_{CP}(K^+K^-\pi^\pm)$ in $D^\pm \to K^+K^-\pi^\pm$		−0.017 ± 0.027
$A_{CP}(K^\pm K^{*0})$ in $D^+ \to K^+\overline{K}^{*0}$ and $D^- \to K^-K^{*0}$		−0.02 ± 0.05
$A_{CP}(\phi\pi^\pm)$ in $D^\pm \to \phi\pi^\pm$		−0.014 ± 0.033
$A_{CP}(\pi^+\pi^-\pi^\pm)$ in $D^\pm \to \pi^+\pi^-\pi^\pm$		−0.02 ± 0.04
$A_{CP}(K^+K^-)$ in $D^0\Gamma\overline{D}^0 \to K^+K^-$		0.026 ± 0.035
$A_{CP}(\pi^+\pi^-)$ in $D^0\Gamma\overline{D}^0 \to \pi^+\pi^-$		−0.05 ± 0.08
$A_{CP}(K^0_S\phi)$ in $D^0\Gamma\overline{D}^0 \to K^0_S\phi$		−0.03 ± 0.09
$A_{CP}(K^0_S\pi^0)$ in $D^0\Gamma\overline{D}^0 \to K^0_S\pi^0$		−0.018 ± 0.030
$\lvert\mathrm{Re}(\epsilon_{B^0})\rvert$		0.002 ± 0.008
$[\alpha_-(\Lambda) + \alpha_+(\overline{\Lambda})] / [\alpha_-(\Lambda) - \alpha_+(\overline{\Lambda})]$		−0.03 ± 0.06

CP VIOLATION OBSERVED

K_L^0 branching ratios		
charge asymmetry in $K_{\ell 3}^0$ decays		
$\delta(\mu) = [\Gamma(\pi^-\mu^+\nu_\mu) - \Gamma(\pi^+\mu^-\overline{\nu}_\mu)]$/sum		(0.304 ± 0.025)%
$\delta(e) = [\Gamma(\pi^-e^+\nu_e) - \Gamma(\pi^+e^-\overline{\nu}_e)]$/sum		(0.333 ± 0.014)%
parameters for $K_L^0 \to 2\pi$ decay		
$\lvert\eta_{00}\rvert = \lvert A(K_L^0 \to 2\pi^0) / A(K_S^0 \to 2\pi^0)\rvert$		$(2.275 \pm 0.019) \times 10^{-3}$ (S = 1.1)
$\lvert\eta_{+-}\rvert = \lvert A(K_L^0 \to \pi^+\pi^-) / A(K_S^0 \to \pi^+\pi^-)\rvert$		$(2.285 \pm 0.019) \times 10^{-3}$
$\epsilon'/\epsilon \approx \mathrm{Re}(\epsilon'/\epsilon) = (1 - \lvert\eta_{00}/\eta_{+-}\rvert)/3$	[e]	$(1.5 \pm 0.8) \times 10^{-3}$ (S = 1.8)
ϕ_{+-} Γphase of η_{+-}		(43.5 ± 0.6)°
ϕ_{00} Γphase of η_{00}		(43.4 ± 1.0)°
parameters for $K_L^0 \to \pi^+\pi^-\gamma$ decay		
$\lvert\eta_{+-\gamma}\rvert = \lvert A(K_L^0 \to \pi^+\pi^-\gamma$ Γ*CP* violating)/$A(K_S^0 \to \pi^+\pi^-\gamma)\rvert$		$(2.35 \pm 0.07) \times 10^{-3}$
$\phi_{+-\gamma}$ = phase of $\eta_{+-\gamma}$		(44 ± 4)°
$\Gamma(K_L^0 \to \pi^+\pi^-)/\Gamma_{\text{total}}$		$(2.067 \pm 0.035) \times 10^{-3}$ (S = 1.1)
$\Gamma(K_L^0 \to \pi^0\pi^0)/\Gamma_{\text{total}}$		$(9.36 \pm 0.20) \times 10^{-4}$

CPT INVARIANCE

$(m_{W^-} - m_{W^-}) / m_{\text{average}}$		-0.002 ± 0.007
$(m_{e^-} - m_{e^-}) / m_{\text{average}}$		$< 4 \times 10^{-8}$ Γ CL = 90%
$\lvert q_{e^-} + q_{e^-}\rvert / e$		$< 2 \times 10^{-18}$
$(g_{e^-} - g_{e^-}) / g_{\text{average}}$		$(-0.5 \pm 2.1) \times 10^{-12}$
$(\tau_{\mu^-} - \tau_{\mu^-}) / \tau_{\text{average}}$		$(2 \pm 8) \times 10^{-5}$
$(g_{\mu^-} - g_{\mu^-}) / g_{\text{average}}$		$(-2.6 \pm 1.6) \times 10^{-8}$
$(m_{\pi^-} - m_{\pi^-}) / m_{\text{average}}$		$(2 \pm 5) \times 10^{-4}$
$(\tau_{\pi^-} - \tau_{\pi^-}) / \tau_{\text{average}}$		$(6 \pm 7) \times 10^{-4}$
$(m_{K^-} - m_{K^-}) / m_{\text{average}}$		$(-0.6 \pm 1.8) \times 10^{-4}$
$(\tau_{K^-} - \tau_{K^-}) / \tau_{\text{average}}$		(0.11 ± 0.09)% (S = 1.2)
$K^\pm \to \mu^\pm\nu_\mu$ rate difference/average	[f]	(−0.5 ± 0.4)%
$K^\pm \to \pi^\pm\pi^0$ rate difference/average	[f]	(0.8 ± 1.2)%
$\lvert m_{K^0} - m_{\overline{K}^0}\rvert / m_{\text{average}}$	[g]	$< 10^{-18}$
phase difference $\phi_{00} - \phi_{+-}$		(−0.1 ± 0.8)°
CPT-violation parameters in K^0 decay		
real part of Δ		0.018 ± 0.020
imaginary part of Δ		0.02 ± 0.04
$(\lvert\frac{q_p}{m_p}\rvert - \lvert\frac{q_p}{m_p}\rvert)/\lvert\frac{q}{m}\rvert_{\text{average}}$		$(1.5 \pm 1.1) \times 10^{-9}$
$\lvert q_p + q_{\overline{p}}\rvert / e$		$< 2 \times 10^{-5}$
$(\mu_p + \mu_{\overline{p}}) / \lvert\mu\rvert_{\text{average}}$		$(-2.6 \pm 2.9) \times 10^{-3}$
$(m_n - m_{\overline{n}}) / m_{\text{average}}$		$(9 \pm 5) \times 10^{-5}$
$(m_\Lambda - m_{\overline{\Lambda}}) / m_\Lambda$		$(-1.0 \pm 0.9) \times 10^{-5}$
$(\tau_\Lambda - \tau_{\overline{\Lambda}}) / \tau_{\text{average}}$		0.04 ± 0.09
$(\mu_{\Sigma^-} + \mu_{\overline{\Sigma}^-}) / \lvert\mu\rvert_{\text{average}}$		0.014 ± 0.015
$(m_{\Xi^-} - m_{\overline{\Xi}^-}) / m_{\text{average}}$		$(1.1 \pm 2.7) \times 10^{-4}$
$(\tau_{\Xi^-} - \tau_{\overline{\Xi}^-}) / \tau_{\text{average}}$		0.02 ± 0.18
$(m_{\Omega^-} - m_{\overline{\Omega}^-}) / m_{\text{average}}$		$(0 \pm 5) \times 10^{-4}$

Limits are given at the 90% confidence level Γ while errors are given as ±1 standard deviation.

TESTS OF NUMBER CONSERVATION LAWS

LEPTON FAMILY NUMBER

Lepton family number conservation means separate conservation of each of L_e, L_μ, L_τ.

$\Gamma(Z \to e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[h]	$< 1.7 \times 10^{-6}$ Γ CL = 95%
$\Gamma(Z \to e^\pm\tau^\mp)/\Gamma_{\text{total}}$	[h]	$< 9.8 \times 10^{-6}$ Γ CL = 95%
$\Gamma(Z \to \mu^\pm\tau^\mp)/\Gamma_{\text{total}}$	[h]	$< 1.2 \times 10^{-5}$ Γ CL = 95%
limit on $\mu^- \to e^-$ conversion		
$\sigma(\mu^- {}^{32}\mathrm{S} \to e^- {}^{32}\mathrm{S}) / \sigma(\mu^- {}^{32}\mathrm{S} \to \nu_\mu {}^{32}\mathrm{P}^*)$		$< 7 \times 10^{-11}$ Γ CL = 90%
$\sigma(\mu^-\mathrm{Ti} \to e^-\mathrm{Ti}) / \sigma(\mu^-\mathrm{Ti} \to \text{capture})$		$< 4.3 \times 10^{-12}$ Γ CL = 90%
$\sigma(\mu^-\mathrm{Pb} \to e^-\mathrm{Pb}) / \sigma(\mu^-\mathrm{Pb} \to \text{capture})$		$< 4.6 \times 10^{-11}$ Γ CL = 90%
limit on muonium → antimuonium conversion $R_g' = G_C / G_F$		< 0.018 Γ CL = 90%
$\Gamma(\mu^- \to e^-\nu_e\overline{\nu}_\mu)/\Gamma_{\text{total}}$	[i]	$< 1.2 \times 10^{-2}$ Γ CL = 90%
$\Gamma(\mu^- \to e^-\gamma)/\Gamma_{\text{total}}$		$< 4.9 \times 10^{-11}$ Γ CL = 90%
$\Gamma(\mu^- \to e^-e^+e^-)/\Gamma_{\text{total}}$		$< 1.0 \times 10^{-12}$ Γ CL = 90%
$\Gamma(\mu^- \to e^-2\gamma)/\Gamma_{\text{total}}$		$< 7.2 \times 10^{-11}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\gamma)/\Gamma_{\text{total}}$		$< 2.7 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\gamma)/\Gamma_{\text{total}}$		$< 3.0 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\pi^0)/\Gamma_{\text{total}}$		$< 3.7 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\pi^0)/\Gamma_{\text{total}}$		$< 4.0 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-K^0)/\Gamma_{\text{total}}$		$< 1.3 \times 10^{-3}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-K^0)/\Gamma_{\text{total}}$		$< 1.0 \times 10^{-3}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\eta)/\Gamma_{\text{total}}$		$< 8.2 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\eta)/\Gamma_{\text{total}}$		$< 9.6 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\rho^0)/\Gamma_{\text{total}}$		$< 2.0 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\rho^0)/\Gamma_{\text{total}}$		$< 6.3 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-K^*(892)^0)/\Gamma_{\text{total}}$		$< 5.1 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-K^*(892)^0)/\Gamma_{\text{total}}$		$< 7.5 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\overline{K}^*(892)^0)/\Gamma_{\text{total}}$		$< 7.4 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\overline{K}^*(892)^0)/\Gamma_{\text{total}}$		$< 7.5 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\phi)/\Gamma_{\text{total}}$		$< 6.9 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\phi)/\Gamma_{\text{total}}$		$< 7.0 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-e^+e^-)/\Gamma_{\text{total}}$		$< 2.9 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\mu^+\mu^-)/\Gamma_{\text{total}}$		$< 1.8 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^+\mu^-\mu^-)/\Gamma_{\text{total}}$		$< 1.5 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-e^+e^-)/\Gamma_{\text{total}}$		$< 1.7 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^+e^-e^-)/\Gamma_{\text{total}}$		$< 1.5 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\mu^+\mu^-)/\Gamma_{\text{total}}$		$< 1.9 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\pi^+\pi^-)/\Gamma_{\text{total}}$		$< 2.2 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\pi^+\pi^-)/\Gamma_{\text{total}}$		$< 8.2 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\pi^+K^-)/\Gamma_{\text{total}}$		$< 6.4 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\pi^-K^+)/\Gamma_{\text{total}}$		$< 3.8 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-K^+K^-)/\Gamma_{\text{total}}$		$< 6.0 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\pi^+K^-)/\Gamma_{\text{total}}$		$< 7.5 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\pi^-K^+)/\Gamma_{\text{total}}$		$< 7.4 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-K^+K^-)/\Gamma_{\text{total}}$		$< 1.5 \times 10^{-5}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\pi^0\pi^0)/\Gamma_{\text{total}}$		$< 6.5 \times 10^{-6}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\pi^0\pi^0)/\Gamma_{\text{total}}$		$< 1.4 \times 10^{-5}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\eta\eta)/\Gamma_{\text{total}}$		$< 3.5 \times 10^{-5}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\eta\eta)/\Gamma_{\text{total}}$		$< 6.0 \times 10^{-5}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-\pi^0\eta)/\Gamma_{\text{total}}$		$< 2.4 \times 10^{-5}$ Γ CL = 90%
$\Gamma(\tau^- \to \mu^-\pi^0\eta)/\Gamma_{\text{total}}$		$< 2.2 \times 10^{-5}$ Γ CL = 90%
$\Gamma(\tau^- \to e^-$ light boson$)/\Gamma_{\text{total}}$		$< 2.7 \times 10^{-3}$ Γ CL = 95%
$\Gamma(\tau^- \to \mu^-$ light boson$)/\Gamma_{\text{total}}$		$< 5 \times 10^{-3}$ Γ CL = 95%
ν oscillations. (For other lepton mixing effects in particle decays Γ see the Particle Listings.)		
$\nu_e \not\to \nu_e$		
$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		$< 9 \times 10^{-4}$ eV^2 Γ CL = 90%
$\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		< 0.02 Γ CL = 90%
$\nu_e \to \nu_\tau$		
$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		< 9 eV^2 Γ CL = 90%
$\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		< 0.25 Γ CL = 90%
$\nu_e \to \nu_\tau$		
$\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		< 0.7 Γ CL = 90%
$\nu_\mu \to \nu_e$		

$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<0.09 eV^2 CL = 90%
$\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		$<3.0 \times 10^{-3}$ CL = 90%
$\bar{\nu}_\mu \to \bar{\nu}_e$		
$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<0.14 eV^2 CL = 90%
$\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		<0.004 CL = 95%
$\nu_\mu(\bar{\nu}_\mu) \to \nu_e(\bar{\nu}_e)$		
$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<0.075 eV^2 CL = 90%
$\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		$<1.8 \times 10^{-3}$ CL = 90%
$\nu_\mu \to \nu_\tau$		
$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<0.9 eV^2 CL = 90%
$\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		<0.004 CL = 90%
$\bar{\nu}_\mu \to \bar{\nu}_\tau$		
$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<2.2 eV^2 CL = 90%
$\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		$<4.4 \times 10^{-2}$ CL = 90%
$\nu_\mu(\bar{\nu}_\mu) \to \nu_\tau(\bar{\nu}_\tau)$		
$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<1.5 eV^2 CL = 90%
$\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		$<8 \times 10^{-3}$ CL = 90%
$\nu_e \not\to \nu_e$		
$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<0.17 eV^2 CL = 90%
$\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		$<7 \times 10^{-2}$ CL = 90%
$\nu_\mu \not\to \nu_\mu$		
$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<0.23 or >1500 eV^2
$\sin^2(2\theta)$ for $\Delta(m^2) = 100$eV^2	[*j*]	<0.02 CL = 90%
$\bar{\nu}_\mu \not\to \bar{\nu}_\mu$		
$\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<7 or >1200 eV^2
$\sin^2(2\theta)$ for 190 eV^2 $<$ $\Delta(m^2)$ $<$ 320 eV^2	[*k*]	<0.02 CL = 90%
$\Gamma(\pi^+ \to \mu^+\nu_e)/\Gamma_{\text{total}}$	[*f*]	$<8.0 \times 10^{-3}$ CL = 90%
$\Gamma(\pi^+ \to \mu^-e^+e^+\nu)/\Gamma_{\text{total}}$		$<1.6 \times 10^{-6}$ CL = 90%
$\Gamma(\pi^0 \to \mu^+e^- + e^-\mu^+)/\Gamma_{\text{total}}$		$<1.72 \times 10^{-8}$ CL = 90%
$\Gamma(\eta \to \mu^+e^- + \mu^-e^+)/\Gamma_{\text{total}}$		$<6 \times 10^{-6}$ CL = 90%
$\Gamma(K^+ \to \mu^-\nu e^+e^+)/\Gamma_{\text{total}}$		$<2.0 \times 10^{-8}$ CL = 90%
$\Gamma(K^+ \to \mu^+\nu_e)/\Gamma_{\text{total}}$	[*f*]	$<4 \times 10^{-3}$ CL = 90%
$\Gamma(K^+ \to \pi^+\mu^+e^-)/\Gamma_{\text{total}}$		$<2.1 \times 10^{-10}$ CL = 90%
$\Gamma(K^+ \to \pi^+\mu^-e^+)/\Gamma_{\text{total}}$		$<7 \times 10^{-9}$ CL = 90%
$\Gamma(K_L^0 \to e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<3.3 \times 10^{-11}$ CL = 90%
$\Gamma(K_L^0 \to e^\pm e^\pm\mu^\mp\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<6.1 \times 10^{-9}$ CL = 90%
$\Gamma(D^+ \to \pi^+e^+\mu^-)/\Gamma_{\text{total}}$		$<1.1 \times 10^{-4}$ CL = 90%
$\Gamma(D^+ \to \pi^+e^-\mu^+)/\Gamma_{\text{total}}$		$<1.3 \times 10^{-4}$ CL = 90%
$\Gamma(D^+ \to K^+e^+\mu^-)/\Gamma_{\text{total}}$		$<1.3 \times 10^{-4}$ CL = 90%
$\Gamma(D^+ \to K^+e^-\mu^+)/\Gamma_{\text{total}}$		$<1.2 \times 10^{-4}$ CL = 90%
$\Gamma(D^0 \to \mu^\pm e^\mp)/\Gamma_{\text{total}}$	[*h*]	$<1.9 \times 10^{-5}$ CL = 90%
$\Gamma(D^0 \to \pi^0e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<8.6 \times 10^{-5}$ CL = 90%
$\Gamma(D^0 \to \eta e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<1.0 \times 10^{-4}$ CL = 90%
$\Gamma(D^0 \to \rho^0e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<4.9 \times 10^{-5}$ CL = 90%
$\Gamma(D^0 \to \omega e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<1.2 \times 10^{-4}$ CL = 90%
$\Gamma(D^0 \to \phi e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<3.4 \times 10^{-5}$ CL = 90%
$\Gamma(D^0 \to \bar{K}^0e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<1.0 \times 10^{-4}$ CL = 90%
$\Gamma(D^0 \to \bar{K}^*(892)^0e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<1.0 \times 10^{-4}$ CL = 90%
$\Gamma(B^+ \to \pi^+e^+\mu^-)/\Gamma_{\text{total}}$		$<6.4 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to \pi^+e^-\mu^+)/\Gamma_{\text{total}}$		$<6.4 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to K^+e^+\mu^-)/\Gamma_{\text{total}}$		$<6.4 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to K^+e^-\mu^+)/\Gamma_{\text{total}}$		$<6.4 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to \pi^-e^+\mu^+)/\Gamma_{\text{total}}$		$<6.4 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to K^-e^+\mu^+)/\Gamma_{\text{total}}$		$<6.4 \times 10^{-3}$ CL = 90%
$\Gamma(B^0 \to e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<5.9 \times 10^{-6}$ CL = 90%
$\Gamma(B^0 \to e^\pm\tau^\mp)/\Gamma_{\text{total}}$	[*h*]	$<5.3 \times 10^{-4}$ CL = 90%
$\Gamma(B^0 \to \mu^\pm\tau^\mp)/\Gamma_{\text{total}}$	[*h*]	$<8.3 \times 10^{-4}$ CL = 90%
$\Gamma(B \to e^\pm\mu^\mp s)/\Gamma_{\text{total}}$		$<2.2 \times 10^{-5}$ CL = 90%
$\Gamma(B_s^0 \to e^\pm\mu^\mp)/\Gamma_{\text{total}}$	[*h*]	$<4.1 \times 10^{-5}$ CL = 90%

TOTAL LEPTON NUMBER

Violation of total lepton number conservation also implies violation of lepton family number conservation.

limit on $\mu^- \to e^+$ conversion		
$\sigma(\mu^-{}^{32}\text{S} \to e^+{}^{32}\text{Si}^*)$ / $\sigma(\mu^-{}^{32}\text{S} \to \nu_\mu{}^{32}\text{P}^*)$		$<9 \times 10^{-10}$ CL = 90%
$\sigma(\mu^-{}^{127}\text{I} \to e^+{}^{127}\text{Sb}^*)$ / $\sigma(\mu^-{}^{127}\text{I} \to \text{anything})$		$<3 \times 10^{-10}$ CL = 90%
$\sigma(\mu^-\text{Ti} \to e^+\text{Ca})$ / $\sigma(\mu^-\text{Ti} \to \text{capture})$		$<8.9 \times 10^{-11}$ CL = 90%
$\Gamma(\tau^- \to \pi^-\gamma)/\Gamma_{\text{total}}$		$<2.8 \times 10^{-4}$ CL = 90%
$\Gamma(\tau^- \to \pi^-\pi^0)/\Gamma_{\text{total}}$		$<3.7 \times 10^{-4}$ CL = 90%
$\Gamma(\tau^- \to e^+\pi^-\pi^-)/\Gamma_{\text{total}}$		$<1.9 \times 10^{-6}$ CL = 90%
$\Gamma(\tau^- \to \mu^+\pi^-\pi^-)/\Gamma_{\text{total}}$		$<3.4 \times 10^{-6}$ CL = 90%
$\Gamma(\tau^- \to e^+\pi^-K^-)/\Gamma_{\text{total}}$		$<2.1 \times 10^{-6}$ CL = 90%
$\Gamma(\tau^- \to e^+K^-K^-)/\Gamma_{\text{total}}$		$<3.8 \times 10^{-6}$ CL = 90%
$\Gamma(\tau^- \to \mu^+\pi^-K^-)/\Gamma_{\text{total}}$		$<7.0 \times 10^{-6}$ CL = 90%
$\Gamma(\tau^- \to \mu^+K^-K^-)/\Gamma_{\text{total}}$		$<6.0 \times 10^{-6}$ CL = 90%
$\Gamma(\tau^- \to \bar{p}\gamma)/\Gamma_{\text{total}}$		$<2.9 \times 10^{-4}$ CL = 90%
$\Gamma(\tau^- \to \bar{p}\pi^0)/\Gamma_{\text{total}}$		$<6.6 \times 10^{-4}$ CL = 90%
$\Gamma(\tau^- \to \bar{p}\eta)/\Gamma_{\text{total}}$		$<1.30 \times 10^{-3}$ CL = 90%
$\nu_e \to (\bar{\nu}_e)_L$		
$\alpha\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<0.14 eV^2 CL = 90%
$\alpha^2\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		<0.032 CL = 90%
$\nu_\mu \to (\nu_e)_L$		
$\alpha\Delta(m^2)$ for $\sin^2(2\theta) = 1$		<0.16 eV^2 CL = 90%
$\alpha^2\sin^2(2\theta)$ for "Large" $\Delta(m^2)$		<0.001 CL = 90%
$\Gamma(\pi^+ \to \mu^+\nu_e)/\Gamma_{\text{total}}$	[*f*]	$<1.5 \times 10^{-3}$ CL = 90%
$\Gamma(K^+ \to \pi^-\mu^+e^+)/\Gamma_{\text{total}}$		$<7 \times 10^{-9}$ CL = 90%
$\Gamma(K^+ \to \pi^-e^+e^+)/\Gamma_{\text{total}}$		$<1.0 \times 10^{-8}$ CL = 90%
$\Gamma(K^+ \to \pi^-\mu^+\mu^+)/\Gamma_{\text{total}}$	[*f*]	$<1.5 \times 10^{-4}$ CL = 90%
$\Gamma(K^+ \to \mu^+\bar{\nu}_e)/\Gamma_{\text{total}}$	[*f*]	$<3.3 \times 10^{-3}$ CL = 90%
$\Gamma(K^+ \to \pi^0e^+\bar{\nu}_e)/\Gamma_{\text{total}}$		$<3 \times 10^{-3}$ CL = 90%
$\Gamma(D^+ \to \pi^-e^+e^+)/\Gamma_{\text{total}}$		$<1.1 \times 10^{-4}$ CL = 90%
$\Gamma(D^+ \to \pi^-\mu^+\mu^+)/\Gamma_{\text{total}}$		$<8.7 \times 10^{-5}$ CL = 90%
$\Gamma(D^+ \to \pi^-e^+\mu^+)/\Gamma_{\text{total}}$		$<1.1 \times 10^{-4}$ CL = 90%
$\Gamma(D^+ \to \rho^-\mu^+\mu^+)/\Gamma_{\text{total}}$		$<5.6 \times 10^{-4}$ CL = 90%
$\Gamma(D^+ \to K^-e^+e^+)/\Gamma_{\text{total}}$		$<1.2 \times 10^{-4}$ CL = 90%
$\Gamma(D^+ \to K^-\mu^+\mu^+)/\Gamma_{\text{total}}$		$<1.2 \times 10^{-4}$ CL = 90%
$\Gamma(D^+ \to K^-e^+\mu^+)/\Gamma_{\text{total}}$		$<1.3 \times 10^{-4}$ CL = 90%
$\Gamma(D^+ \to K^*(892)^-\mu^+\mu^+)/\Gamma_{\text{total}}$		$<8.5 \times 10^{-4}$ CL = 90%
$\Gamma(D_s^+ \to \pi^-\mu^+\mu^+)/\Gamma_{\text{total}}$		$<4.3 \times 10^{-4}$ CL = 90%
$\Gamma(D_s^+ \to K^-\mu^+\mu^+)/\Gamma_{\text{total}}$		$<5.9 \times 10^{-4}$ CL = 90%
$\Gamma(D_s^+ \to K^*(892)^-\mu^+\mu^+)/\Gamma_{\text{total}}$		$<1.4 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to \pi^-e^+e^+)/\Gamma_{\text{total}}$		$<3.9 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to \pi^-\mu^+\mu^+)/\Gamma_{\text{total}}$		$<9.1 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to K^-e^+e^+)/\Gamma_{\text{total}}$		$<3.9 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to K^-\mu^+\mu^+)/\Gamma_{\text{total}}$		$<9.1 \times 10^{-3}$ CL = 90%
$\Gamma(\Xi^- \to p\mu^-\mu^-)/\Gamma_{\text{total}}$		$<4 \times 10^{-4}$ CL = 90%
$\Gamma(\Lambda_c^+ \to \Sigma^-\mu^+\mu^+)/\Gamma_{\text{total}}$		$<7.0 \times 10^{-4}$ CL = 90%

BARYON NUMBER

$\Gamma(\tau^- \to \bar{p}\gamma)/\Gamma_{\text{total}}$		$<2.9 \times 10^{-4}$ CL = 90%
$\Gamma(\tau^- \to \bar{p}\pi^0)/\Gamma_{\text{total}}$		$<6.6 \times 10^{-4}$ CL = 90%
$\Gamma(\tau^- \to \bar{p}\eta)/\Gamma_{\text{total}}$		$<1.30 \times 10^{-3}$ CL = 90%
p mean life		$>1.6 \times 10^{25}$ years

A few examples of proton or bound neutron decay follow. For limits on many other nucleon decay channels see the Baryon Summary Table.

$\tau(N \to e^+\pi)$		> 130 (n) > 550 (p) $\times 10^{30}$ years CL = 90%
$\tau(N \to \mu^+\pi)$		> 100 (n) > 270 (p) $\times 10^{30}$ years CL = 90%
$\tau(N \to e^+K)$		> 1.3 (n) > 150 (p) $\times 10^{30}$ years CL = 90%
$\tau(N \to \mu^+K)$		> 1.1 (n) > 120 (p) $\times 10^{30}$ years CL = 90%
limit on $n\bar{n}$ oscillations (bound n)	[*m*]	$>1.2 \times 10^8$ s CL = 90%
limit on $n\bar{n}$ oscillations (free n)		$>0.86 \times 10^8$ s CL = 90%

Limits are given at the 90% confidence level while errors are given as ± 1 standard deviation.

ELECTRIC CHARGE (Q)

e mean life / branching fraction	[n]	$>4.3\times10^{23}$ yr CL = 68%
$\Gamma(n\to p\nu_e\overline{\nu}_e)/\Gamma_{\text{total}}$		$<8\times10^{-27}$ CL = 68%

$\Delta S=\Delta Q$ RULE

Allowed in second-order weak interactions.

$\Gamma(K^+\to\pi^+\pi^+e^-\overline{\nu}_e)/\Gamma_{\text{total}}$		$<1.2\times10^{-8}$ CL = 90%
$\Gamma(K^+\to\pi^+\pi^+\mu^-\overline{\nu}_\mu)/\Gamma_{\text{total}}$		$<3.0\times10^{-6}$ CL = 95%
$x=A(\overline{K}^0\to\pi^-\ell^+\nu)/A(K^0\to\pi^-\ell^+\nu)=A(\Delta S=-\Delta Q)/A(\Delta S=\Delta Q)$		
real part of x		0.006 ± 0.018 (S = 1.3)
imaginary part of x		-0.003 ± 0.026 (S = 1.2)
$\Gamma(\Sigma^+\to n\ell^+\nu)/\Gamma(\Sigma^-\to n\ell^-\overline{\nu})$		<0.043
$\Gamma(\Sigma^+\to ne^+\nu_e)/\Gamma_{\text{total}}$		$<5\times10^{-6}$ CL = 90%
$\Gamma(\Sigma^+\to n\mu^+\nu_\mu)/\Gamma_{\text{total}}$		$<3.0\times10^{-5}$ CL = 90%
$\Gamma(\Xi^0\to\Sigma^-e^+\nu_e)/\Gamma_{\text{total}}$		$<9\times10^{-4}$ CL = 90%
$\Gamma(\Xi^0\to\Sigma^-\mu^+\nu_\mu)/\Gamma_{\text{total}}$		$<9\times10^{-4}$ CL = 90%

$\Delta S=2$ FORBIDDEN

Allowed in second-order weak interactions.

$\Gamma(\Xi^0\to p\pi^-)/\Gamma_{\text{total}}$		$<4\times10^{-5}$ CL = 90%
$\Gamma(\Xi^0\to pe^-\overline{\nu}_e)/\Gamma_{\text{total}}$		$<1.3\times10^{-3}$
$\Gamma(\Xi^0\to p\mu^-\overline{\nu}_\mu)/\Gamma_{\text{total}}$		$<1.3\times10^{-3}$
$\Gamma(\Xi^-\to n\pi^-)/\Gamma_{\text{total}}$		$<1.9\times10^{-5}$ CL = 90%
$\Gamma(\Xi^-\to ne^-\overline{\nu}_e)/\Gamma_{\text{total}}$		$<3.2\times10^{-3}$ CL = 90%
$\Gamma(\Xi^-\to n\mu^-\overline{\nu}_\mu)/\Gamma_{\text{total}}$		$<1.5\times10^{-2}$ CL = 90%
$\Gamma(\Xi^-\to p\pi^-\pi^-)/\Gamma_{\text{total}}$		$<4\times10^{-4}$ CL = 90%
$\Gamma(\Xi^-\to p\pi^-e^-\overline{\nu}_e)/\Gamma_{\text{total}}$		$<4\times10^{-4}$ CL = 90%
$\Gamma(\Xi^-\to p\pi^-\mu^-\overline{\nu}_\mu)/\Gamma_{\text{total}}$		$<4\times10^{-4}$ CL = 90%
$\Gamma(\Omega^-\to\Lambda\pi^-)/\Gamma_{\text{total}}$		$<1.9\times10^{-4}$ CL = 90%

$\Delta S=2$ VIA MIXING

Allowed in second-order weak interactions, e.g. mixing.

$m_{K_L^0}-m_{K_S^0}$	$(0.5301\pm0.0014)\times10^{10}$ $\hbar$ s^{-1}
$m_{K_L^0}-m_{K_S^0}$	$(3.489\pm0.009)\times10^{-12}$ MeV

$\Delta C=2$ VIA MIXING

Allowed in second-order weak interactions, e.g. mixing.

$\lvert m_{D_1^0}-m_{D_2^0}\rvert$	[o]	$<24\times10^{10}$ $\hbar$ s^{-1} CL = 90%
$\lvert\Gamma_{D_1^0}-\Gamma_{D_2^0}\rvert/\Gamma_{D^0}$ mean life difference/average	[o]	<0.20 CL = 90%
$\Gamma(K^+\ell^-\overline{\nu}_\ell(\text{via }\overline{D}^0))/\Gamma(K^-\ell^+\nu_\ell)$		<0.005 CL = 90%
$\Gamma(K^+\pi^-\text{or }K^+\pi^-\pi^+\pi^-(\text{via }\overline{D}^0))/\Gamma(K^-\pi^+\text{or }K^-\pi^+\pi^+\pi^-)$	[p]	<0.0085 (or <0.0037) CL = 90%
$\Gamma(D^0\to K^+\ell^-\overline{\nu}_\ell(\text{via }\overline{D}^0))/\Gamma_{\text{total}}$		$<1.7\times10^{-4}$ CL = 90%
$\Gamma(D^0\to K^+\pi^-\text{or }K^+\pi^-\pi^+\pi^-(\text{via }\overline{D}^0))/\Gamma_{\text{total}}$		$<1.0\times10^{-3}$ CL = 90%

$\Delta B=2$ VIA MIXING

Allowed in second-order weak interactions, e.g. mixing.

x_d	0.172 ± 0.010
$\Delta m_{B^0}=m_{B_H^0}-m_{B_L^0}$	$(0.464\pm0.018)\times10^{12}$ $\hbar$ s^{-1}
$x_d=\Delta m_{B^0}/\Gamma_{B^0}$	0.723 ± 0.032
χ_B at high energy	0.118 ± 0.006
$\Delta m_{B_s^0}=m_{B_{sH}^0}-m_{B_{sL}^0}$	$>9.1\times10^{12}$ $\hbar$ s^{-1} CL = 95%
$x_s=\Delta m_{B_s^0}/\Gamma_{B_s^0}$	>14.0 CL = 95%
χ_s	>0.4975 CL = 95%

$\Delta S=1$ WEAK NEUTRAL CURRENT FORBIDDEN

Allowed by higher-order electroweak interactions.

$\Gamma(K^+\to\pi^+e^+e^-)/\Gamma_{\text{total}}$		$(2.74\pm0.23)\times10^{-7}$
$\Gamma(K^+\to\pi^+\mu^+\mu^-)/\Gamma_{\text{total}}$		$(5.0\pm1.0)\times10^{-8}$
$\Gamma(K^+\to\pi^+\nu\overline{\nu})/\Gamma_{\text{total}}$		$(4.2^{+9.7}_{-3.5})\times10^{-10}$
$\Gamma(K_S^0\to\mu^+\mu^-)/\Gamma_{\text{total}}$		$<3.2\times10^{-7}$ CL = 90%
$\Gamma(K_S^0\to e^+e^-)/\Gamma_{\text{total}}$		$<1.4\times10^{-7}$ CL = 90%
$\Gamma(K_S^0\to\pi^0e^+e^-)/\Gamma_{\text{total}}$		$<1.1\times10^{-6}$ CL = 90%
$\Gamma(K_L^0\to\mu^+\mu^-)/\Gamma_{\text{total}}$		$(7.2\pm0.5)\times10^{-9}$ (S = 1.4)
$\Gamma(K_L^0\to\mu^+\mu^-\gamma)/\Gamma_{\text{total}}$		$(3.25\pm0.28)\times10^{-7}$
$\Gamma(K_L^0\to e^+e^-)/\Gamma_{\text{total}}$		$<4.1\times10^{-11}$ CL = 90%
$\Gamma(K_L^0\to e^+e^-\gamma)/\Gamma_{\text{total}}$		$(9.1\pm0.5)\times10^{-6}$
$\Gamma(K_L^0\to e^+e^-\gamma\gamma)/\Gamma_{\text{total}}$	[q]	$(6.5\pm1.2)\times10^{-7}$
$\Gamma(K_L^0\to\pi^+\pi^-e^+e^-)/\Gamma_{\text{total}}$	[q]	$<4.6\times10^{-7}$ CL = 90%
$\Gamma(K_L^0\to\mu^+\mu^-e^+e^-)/\Gamma_{\text{total}}$		$(2.9^{+6.7}_{-2.4})\times10^{-9}$
$\Gamma(K_L^0\to e^+e^-e^+e^-)/\Gamma_{\text{total}}$		$(4.1\pm0.8)\times10^{-8}$ (S = 1.2)
$\Gamma(K_L^0\to\pi^0\mu^+\mu^-)/\Gamma_{\text{total}}$		$<5.1\times10^{-9}$ CL = 90%
$\Gamma(K_L^0\to\pi^0e^+e^-)/\Gamma_{\text{total}}$		$<4.3\times10^{-9}$ CL = 90%
$\Gamma(K_L^0\to\pi^0\nu\overline{\nu})/\Gamma_{\text{total}}$		$<5.8\times10^{-5}$ CL = 90%
$\Gamma(\Sigma^+\to pe^+e^-)/\Gamma_{\text{total}}$		$<7\times10^{-6}$

$\Delta C=1$ WEAK NEUTRAL CURRENT FORBIDDEN

Allowed by higher-order electroweak interactions.

$\Gamma(D^+\to\pi^+e^+e^-)/\Gamma_{\text{total}}$		$<6.6\times10^{-5}$ CL = 90%
$\Gamma(D^+\to\pi^+\mu^+\mu^-)/\Gamma_{\text{total}}$		$<1.8\times10^{-5}$ CL = 90%
$\Gamma(D^+\to\rho^+\mu^+\mu^-)/\Gamma_{\text{total}}$		$<5.6\times10^{-4}$ CL = 90%
$\Gamma(D^0\to e^+e^-)/\Gamma_{\text{total}}$		$<1.3\times10^{-5}$ CL = 90%
$\Gamma(D^0\to\mu^+\mu^-)/\Gamma_{\text{total}}$		$<4.1\times10^{-6}$ CL = 90%
$\Gamma(D^0\to\pi^0e^+e^-)/\Gamma_{\text{total}}$		$<4.5\times10^{-5}$ CL = 90%
$\Gamma(D^0\to\pi^0\mu^+\mu^-)/\Gamma_{\text{total}}$		$<1.8\times10^{-4}$ CL = 90%
$\Gamma(D^0\to\eta e^+e^-)/\Gamma_{\text{total}}$		$<1.1\times10^{-4}$ CL = 90%
$\Gamma(D^0\to\eta\mu^+\mu^-)/\Gamma_{\text{total}}$		$<5.3\times10^{-4}$ CL = 90%
$\Gamma(D^0\to\rho^0e^+e^-)/\Gamma_{\text{total}}$		$<1.0\times10^{-4}$ CL = 90%
$\Gamma(D^0\to\rho^0\mu^+\mu^-)/\Gamma_{\text{total}}$		$<2.3\times10^{-4}$ CL = 90%
$\Gamma(D^0\to\omega e^+e^-)/\Gamma_{\text{total}}$		$<1.8\times10^{-4}$ CL = 90%
$\Gamma(D^0\to\omega\mu^+\mu^-)/\Gamma_{\text{total}}$		$<8.3\times10^{-4}$ CL = 90%
$\Gamma(D^0\to\phi e^+e^-)/\Gamma_{\text{total}}$		$<5.2\times10^{-5}$ CL = 90%
$\Gamma(D^0\to\phi\mu^+\mu^-)/\Gamma_{\text{total}}$		$<4.1\times10^{-4}$ CL = 90%
$\Gamma(D^0\to\pi^+\pi^-\pi^0\mu^+\mu^-)/\Gamma_{\text{total}}$		$<8.1\times10^{-4}$ CL = 90%
$\Gamma(D_s^+\to K^+\mu^+\mu^-)/\Gamma_{\text{total}}$		$<5.9\times10^{-4}$ CL = 90%
$\Gamma(D_s^+\to K^*(892)^+\mu^+\mu^-)/\Gamma_{\text{total}}$		$<1.4\times10^{-3}$ CL = 90%
$\Gamma(\Lambda_c^+\to p\mu^+\mu^-)/\Gamma_{\text{total}}$		$<3.4\times10^{-4}$ CL = 90%

Limits are given at the 90% confidence level Γ while errors are given as ±1 standard deviation.

$\Delta B = 1$ WEAK NEUTRAL CURRENT FORBIDDEN

Allowed by higher-order electroweak interactions.

$\Gamma(B^+ \to \pi^+ e^+ e^-)/\Gamma_{\text{total}}$	$<3.9 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to \pi^+ \mu^+ \mu^-)/\Gamma_{\text{total}}$	$<9.1 \times 10^{-3}$ CL = 90%
$\Gamma(B^+ \to K^+ e^+ e^-)/\Gamma_{\text{total}}$	$<6 \times 10^{-5}$ CL = 90%
$\Gamma(B^+ \to K^+ \mu^+ \mu^-)/\Gamma_{\text{total}}$	$<1.0 \times 10^{-5}$ CL = 90%
$\Gamma(B^+ \to K^*(892)^+ e^+ e^-)/\Gamma_{\text{total}}$	$<6.9 \times 10^{-4}$ CL = 90%
$\Gamma(B^+ \to K^*(892)^+ \mu^+ \mu^-)/\Gamma_{\text{total}}$	$<1.2 \times 10^{-3}$ CL = 90%
$\Gamma(B^0 \to \gamma\gamma)/\Gamma_{\text{total}}$	$<3.9 \times 10^{-5}$ CL = 90%
$\Gamma(B^0 \to e^+ e^-)/\Gamma_{\text{total}}$	$<5.9 \times 10^{-6}$ CL = 90%
$\Gamma(B^0 \to \mu^+ \mu^-)/\Gamma_{\text{total}}$	$<6.8 \times 10^{-7}$ CL = 90%
$\Gamma(B^0 \to K^0 e^+ e^-)/\Gamma_{\text{total}}$	$<3.0 \times 10^{-4}$ CL = 90%
$\Gamma(B^0 \to K^0 \mu^+ \mu^-)/\Gamma_{\text{total}}$	$<3.6 \times 10^{-4}$ CL = 90%
$\Gamma(B^0 \to K^*(892)^0 e^+ e^-)/\Gamma_{\text{total}}$	$<2.9 \times 10^{-4}$ CL = 90%
$\Gamma(B^0 \to K^*(892)^0 \mu^+ \mu^-)/\Gamma_{\text{total}}$	$<2.3 \times 10^{-5}$ CL = 90%
$\Gamma(B^0 \to K^*(892)^0 \nu\bar{\nu})/\Gamma_{\text{total}}$	$<1.0 \times 10^{-3}$ CL = 90%
$\Gamma(B \to e^+ e^- s)/\Gamma_{\text{total}}$	$<5.7 \times 10^{-5}$ CL = 90%
$\Gamma(B \to \mu^+ \mu^- s)/\Gamma_{\text{total}}$	$<5.8 \times 10^{-5}$ CL = 90%
$\Gamma(\bar{b} \to \mu^+ \mu^-$ anything$)/\Gamma_{\text{total}}$	$<3.2 \times 10^{-4}$ CL = 90%
$\Gamma(B_s^0 \to \mu^+ \mu^-)/\Gamma_{\text{total}}$	$<2.0 \times 10^{-6}$ CL = 90%
$\Gamma(B_s^0 \to e^+ e^-)/\Gamma_{\text{total}}$	$<5.4 \times 10^{-5}$ CL = 90%
$\Gamma(B_s^0 \to \phi\nu\bar{\nu})/\Gamma_{\text{total}}$	$<5.4 \times 10^{-3}$ CL = 90%

Limits are given at the 90% confidence level; while errors are given as ± 1 standard deviation.

NOTES

In this Summary Table:

When a quantity has "(S = ...)" to its right, the error on the quantity has been enlarged by the "scale factor" S, defined as $S = \sqrt{\chi^2/(N-1)}$, where N is the number of measurements used in calculating the quantity. We do this when S > 1, which often indicates that the measurements are inconsistent. When S > 1.25, we also show in the Particle Listings an ideogram of the measurements. For more about S, see the Introduction.

[a] C parity forbids this to occur as a single-photon process.

[b] Time-reversal invariance requires this to be 0° or 180°.

[c] Allowed by higher-order electroweak interactions.

[d] Violates CP in leading order. Test of direct CP violation since the indirect CP-violating and CP-conserving contributions are expected to be suppressed.

[e] ϵ'/ϵ is derived from $|\eta_{00}/\eta_{+-}|$ measurements using theoretical input on phases.

[f] Neglecting photon channels. See, e.g., A. Pais and S.B. Treiman, Phys. Rev. D12, 2744 (1975).

[g] Derived from measured values of ϕ_{+-}, ϕ_{00}, $|\eta|$, $|m_{K_L^0} - m_{K_S^0}|$, and $\tau_{K_S^0}$, as described in the introduction to "Tests of Conservation Laws."

[h] The value is for the sum of the charge states of particle/antiparticle states indicated.

[i] A test of additive vs. multiplicative lepton family number conservation.

[j] $\Delta(m^2) = 100$ eV^2.

[k] 190 eV^2 $< \Delta(m^2) <$ 320 eV^2.

[l] Derived from an analysis of neutrino-oscillation experiments.

[m] There is some controversy about whether nuclear physics and model dependence complicate the analysis for bound neutrons (from which the best limit comes). The second limit here is from reactor experiments with free neutrons.

[n] This is the best "electron disappearance" limit. The best limit for the mode $e^- \to \nu\gamma$ is $> 2.35 \times 10^{25}$ yr (CL=68%).

[o] The D_1^0-D_2^0 limits are inferred from the D^0-$\overline{D}^0$ mixing ratio $\Gamma(K^+ \ell^- \bar{\nu}_\ell$(via $\overline{D}^0$)) / $\Gamma(K^- \ell^+ \nu_\ell)$.

[p] The larger limit (from E791) allows interference between the doubly Cabibbo-suppressed and mixing amplitudes; the smaller limit (from E691) doesn't. See the papers for details.

[q] See the K_L^0 Particle Listings for the energy limits used in this measurement.

TABLE OF THE ISOTOPES

Norman E. Holden

This table presents an evaluated set of values for the experimental quantities which characterize the decay of radioactive nuclides. A list of the major references used in this evaluation is given below. When uncertainties are not listed, they are assumed to be five or less in the last digit quoted. If they exceed five in the last digit, the value is prefaced by an approximate sign. For quasi-stable nuclides, the measured width, Γ, of the resonance is given. To estimate the approximate half-life, the Heisenberg relationship may be used, the half-life = 4.56 E-22 seconds / Γ(MeV). The effective literature cut-off date for data in this edition of the Table is December, 2002.

Table Layout

Column No.	Column Title	Description
1	Isotope or Element	For elements, the atomic number and chemical symbol are listed. For nuclides, the mass number and chemical symbol are listed. Isomers are indicated by the addition of m, m1, or m2.
2	Isotopic Abundance	in atom percent.
3	Atomic Mass or Atomic Weight	Atomic mass relative to ^{12}C = 12. Atomic weight is given on the same scale.
4	Half-life/Resonance Width	Half-life in decimal notation. μs = microseconds; ms = milliseconds; s = seconds; m = minutes; h = hours; d = days; and y = years. For quasi-stable nuclides, the measured width at half maximum of the energy resonance is given
5	Decay Mode/Energy	Decay modes are α = alpha particle emission; β^- = negative beta emission; β^+ = positron emission; EC = orbital electron capture; IT = isomeric transition from upper to lower isomeric state; n = neutron emission; SF = spontaneous fission; ββ = double beta decay. Total disintegration energy in MeV units.
6	Particle Energy/ Intensity	End point energies of beta transitions and discrete energies of alpha particles in MeV and their intensities in percent.
7	Spin and Parity	Nuclear spin or angular momentum of the nuclides in units of h/2π; parity is positive or negative.
8	Magnetic Dipole Moment	Magnetic dipole moments in nuclear magneton units.
9	Electric Quadrupole Moment	Electric quadrupole moments in barn units (10^{-24} cm^2).
10	Gamma Ray Energy/ Intensity	Gamma ray energies in MeV and intensities in percent. Ann. rad. refers to the 511.006 keV photons emitted in the annihilation of positrons in matter.

General Nuclear Data References

The following references represent the major sources of the nuclear data presented, along with subsequent published journals and reports:

1. G. Audi, O. Bersillon, J. Blachot, A.H. Wapstra, *The Nubase Evaluation of Nuclear and Decay Properties,* Nuclear Physics A624, 1 (1997).
2. International Commission on Atomic Weights, *Atomic Weights of the Elements - 1999,* Pure & Applied Chemistry 75, 667 (2001).
3. J.R. Parrington, H.D. Knox, S. Breneman, E.M. Baum, F. Feiner, *Chart of the Nuclides, 15th Edition,* Knolls Atomic Power Lab. (1996)
4. N.E. Holden, *Total and Spontaneous Fission Half-lives for Uranium, Plutonium, Americium and Curium Nuclides,* Pure & Applied Chemistry 61, 1483 (1989).
5. N.E. Holden, *Half-lives of Selected Nuclides,* Pure & Applied Chemistry 62, 941 (1990).
6. N.E. Holden, *Review of Thermal Neutron Cross Sections and Isotopic Composition of the Elements,* BNL-NCS-42224 (March 1989).
7. P. Raghavan, *Table of Nuclear Moments,* Atomic Data Nuclear Data Tables 42, 189 (1989).
8. E. Brown, R. Firestone, *Radioactivity Handbook,* Wiley Interscience Press (1986).
9. J.K. Tuli, *Nuclear Wallet Cards,* Brookhaven National Laboratory (January 2000).
10. N.E. Holden, D.C. Hoffman, *Spontaneous Fission Half-lives for Ground State Nuclides,* Pure & Applied Chemistry 72 1525 (2000).
11. N. Stone, *Table of New Nuclear Moments*, private communication, www.nndc.bnl.gov/nndc/stone_moments/moments.html (Dec 2000)

This research was carried out under the auspices of the US Department of Energy Contract No. DE-AC02-98CH10886. The author is at Brookhaven National Laboratory, Upton, NY, and can be contacted at holden@bnl.gov.

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
$_0$n		**1.008664924**	**614. s**	**β⁻ /0.78235**	**0.782/100.**	**1/2+**	**–1.913043**		
				β^-, γ	/< 0.069				
$_1$H		**1.00794(7)**							
^{1}H	99.9885(70)	1.007825032	$> 2.8 \times 10^{23}$ y			1/2+	+2.79285		
^{2}H	0.0115(70)	2.014101778				1+	+0.85744	+2.86 mb	
^{3}H		3.016049268	12.33 y	β^-/0.01859	0.01860/100.	1/2+	+2.97896		
^{4}H		4.0278	$\Gamma \approx 3$	n/	/100	2–			
^{5}H		5.040	$\Gamma = 1.9(4)$	n/	/100	(1/2+)			
^{6}H		6.0449	$\Gamma = 1.6(4)$	n/		(2–)			
$_2$He		**4.002602(2)**							
^{3}He	1.34×10^{-4}	3.016029309				1/2+	–2.12762		
^{4}He	≈100.	4.002603250				0+			
^{5}He		5.01222	$\Gamma = 0.60(2)$	n, α		3/2–			
^{6}He		6.018888	0.807 s	β^-/3.508	3.510/100.	0+			
				β, d	/0.00076				
^{7}He		7.02803	$\Gamma = 0.15(2)$	n		(3/2)–			
^{8}He		8.03392	0.119 s	β^-/10.65	/84.	0+			0.9807/84.
				n/	/16.				0.4776/5.
				β, t	/0.82				
^{9}He		9.0438	$\Gamma = 0.10(6)$	n	/100	(1/2–)			
^{10}He		10.0524	$\Gamma = 0.3(2)$	2n	/100	0+			
$_3$Li		**6.941(2)**							
^{4}Li		4.0272	$\Gamma = 6.0$	p/	/100	2–			
^{5}Li		5.01254	$\Gamma = 1.2$	p/α		3/2–			
^{6}Li	7.59(4)	6.0151223				1+	+0.82205	–0.8 mb	
^{7}Li	92.41(4)	7.0160041				3/2–	+3.25644	–0.041	
^{8}Li		8.022486	0.84 s	β^-/16.004	12.5/100.	2+	+1.6536	+0.032	
				α/	α(1.6)				
^{9}Li		9.026789	0.178 s	β^-/13.606	13.5/75.	3/2–	3.439	–0.027	
				β^-/	11/25.				
^{10}Li		10.03590	$\Gamma = 0.11(5)$	n	/7.	1+			
^{11}Li		11.04380	8.8 ms	β^-/20.6	/8.3	3/2(–)	3.668	–0.031	3.368/33.
				β^-, n	/85.7				0.320/7.8
				β^-, 2n	/4.1				2.590/6.
				β^-, 3n	/1.9				2.811/2.8
				β^-, d	/>0.01				0.219/0.78
				β^-, t	/0.02				
^{12}Li		12.054	<0.01 μs						
$_4$Be		**9.012182(3)**							
^{5}Be		5.041		p, ^{3}He		(1/2+)			
^{6}Be		6.01973	$\Gamma = 0.092(6)$	2p,α		0+			
^{7}Be		7.0169293	53.28 d	EC/0.8618		3/2–			0.4776/10.4
^{8}Be		8.00530509	$\Gamma = 6.8(17)$eV	2α/0.046		0+			
^{9}Be	100.	9.0121822				3/2–	–1.1776	+0.0529	
^{10}Be		10.0135338	1.52×10^6 y	β^-/0.5559	0.555/100.	0+			
^{11}Be		11.02166	13.8 s	β^-, $\beta^-\alpha$/11.51	11.48/61.	1/2+			2.125/35.5
									(0.478 – 7.97)
^{12}Be		12.02692	22.0 ms	β^-, (n)/11.71	n//0.5	0+			(0.95 – 4.4)
^{13}Be		13.0361	$\Gamma \approx 1.$						
^{14}Be		14.0428	4.6 ms	β^-/16.2		0+			3.5346/0.9
				β^-, n	0.288/94.				3.6845/7.
				β^-, 2n	/6.				
				β^-, α	/<0.012				
				β^-, t	/<0.04				
$_5$B		**10.811(7)**							
^{7}B		7.0299	$\Gamma = 1.4(2)$	p, α		(3/2–)			

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{8}B		8.024607	0.770 s	β^+, 2α/17.979	13.7(β^+)/93.	2+	1.0355	0.068	ann.rad.
^{9}B		9.013329	Γ = 0.5(2) keV	p, 2α/		3/2–			
^{10}B	19.9(7)	10.0129371				3+	+1.8006	+0.085	
^{11}B	80.1(7)	11.0093055				3/2–	+2.6886	+0.0406	
^{12}B		12.014352	0.0202 s	β^-/13.369		1+	+1.0027	0.0132	4.438/1.3
				β^- α/1.6/					3.215/0.00065
^{13}B		13.017780	0.0174 s	β^- /13.437	13.4	3/2–	+3.17778	0.037	3.68/7.6
				β^- n/0.25/	2.43(n)/0.09				
					3.55(n)/0.16				
^{14}B		14.02540	14. ms	β^-/20.64		2–	1.185	0.0298	6.094/90.
^{15}B		15.03110	10.4 ms	β^-, (n)/19.09		(3/2–)	2.66	0.038	
^{16}B		16.0398	Γ < 0.1	n					
^{17}B		17.0469	5.1 ms	β^-, (n)/22.7			2.54	0.039	
^{18}B		18.056	<0.026 μs			0–			
^{19}B		19.0637	3.3 ms	β^-, (n)/26.5	n//125.	(3/2–)			
$_{6}$C		**12.0107(8)**							
^{8}C		8.03768	Γ = 0.25(4)	p		0+			
^{9}C		9.031040	127. ms	β^+, p, 2α/16.498		(3/2–)	–1.391		ann.rad.
^{10}C		10.0168532	19.3 s	β^+/3.648	1.865	0+			ann.rad.
									0.71829/100.
^{11}C		11.011433	20.3 m	β^+, EC/1.982	0.9608/99.	3/2–	–0.964	0.0333	ann.rad.
^{12}C	98.93(8)	12.000000000				0+			
^{13}C	1.07(8)	13.003354838				1/2–	+0.70241		
^{14}C		14.003241991	5715. y	β^-/0.15648	0.1565/100.	0+			
^{15}C		15.010599	2.45 s	β^-/9.772	4.51/68.	1/2+	1.32		5.298/68.
					9.82/32.				(7.30–9.05)
^{16}C		16.014701	≈0.750 s	β^-/8.012	β/3.3, 4.3/84, 16	0+			
				β, n	n/0.8, 1.7/84, 16				
^{17}C		17.02258	0.19 s	β^-/13.17		3/2+			1.375
				β^-, n	n/1.6–3.7/11.				1.849
									1.906
^{18}C		18.02676	0.092 s	β^-/11.81		0+			
				β^-, n	n/0.88–4.59/21.				
^{19}C		19.0353	0.05 s	n		1/2+			
^{20}C		20.0403	0.01 s			0+			
^{21}C		21.0493	<0.03 μs						
^{22}C		22.056	9 ms	β^-, n	n//99.	0+			
$_{7}$N		**14.0067(2)**							
^{10}N		10.0426	Γ = 2.3(16)						
^{11}N		11.0268	Γ = 0.52(9)			1/2+			
^{12}N		12.018613	11.00 ms	β^+, β^+α/17.338	16.38/95.	1+	+0.457	+10. mb	ann.rad.
									4.438/2.
^{13}N		13.0057386	9.97 m	β^+ /2.2204	1.190/100.	1/2–	0.3222		
^{14}N	99.636(20)	14.003074007				1+	+0.40376	+0.0200	
^{15}N	0.364(20)	15.00010897				1/2–	–0.28319		
^{16}N		16.006100	7.13 s	β^- /10.419	4.27/68.	2–			6.129/68.8
					10.44/26.		1.986	18 mb	7.115/4.7
				β^-, α	1.85/.0012				(0.99–8.87)
^{17}N		17.00845	4.17 s	β^-, β^- n/8.68	3.7/100.	1/2–	0.352		0.871/3.
				0.4–1.7n/95.					2.1842/0.3
				β^- α/	8.0, 8.2				
^{18}N		18.01408	0.62 s	β^- /13.90	9.4/100.	1–	0.328	0.012	0.822/61.
				β^-, α	/12.				1.65/60.5
									1.982/98.
									(0.535–7.13)
^{19}N		19.01703	0.32 s	β^-/12.53					(0.096–3.14)
^{20}N		20.02337	0.14 s	β^- /17.97					
^{21}N		21.0271	0.08 s						
^{22}N		22.0344	0.02 s						
^{23}N		23.0405	15 ms	β^-, n	n//80.				

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
$_{8}$O		**15.9994(3)**							
^{12}O		12.03440	$\Gamma = 0.51(16)$	2p		0+			
^{13}O		13.02481	8.9 ms	β^+, p/17.77	1.56 (p)/	(3/2–)	1.389	0.011	ann.rad.
									4.438/0.56
^{14}O		14.0085953	70.60 s	β^+ /5.1430	1.81/99.	0+			ann.rad.
									2.312/99.4
^{15}O		15.0030655	122.2 s	β^+ /2.754	1.723/100.	1/2–	0.7195		ann.rad.
^{16}O	99.757(16)	15.994914622				0+			
^{17}O	0.038(1)	16.9991315				5/2+	–1.8938	–0.026	
^{18}O	0.205(14)	17.999160				0+			
^{19}O		19.003579	26.9 s	β^- /4.820	3.25/60.	5/2+	1.5320	3.7 mb	0.197/95.9
					4.60/40.				1.3569/50.4
									(0.11–4.18)
^{20}O		20.004076	13.5 s	β^- /3.814		0+			1.057/100.
^{21}O		21.00866	3.4 s	β^- /8.11					(0.28–4.6)
^{22}O		22.00997	2.2 s	β^- /6.5		0+			(0.64–1.86)
^{23}O		23.0157	0.08 s						
^{24}O		24.0204	≈65 ms	β^-, n	n//18.	0+			1.83/28.
									0.52/14.
									1.31/12.
^{25}O		25.029	<0.05 μs						
^{26}O		26.038	<0.04 μs			0+			
$_{9}$F		**18.9984032(5)**							
^{14}F		14.036							
^{15}F		15.0180	$\Gamma = 0.9(3)$	p		(1/2+)			
^{16}F		16.01147	$\Gamma = 0.037(14)$	p		0–			
^{17}F		17.0020952	64.5 s	β^+ /2.761	1.75/	5/2+	+4.721	0.058	ann.rad.
^{18}F		18.000938	1.830 h	β^+, EC/1.656	0.635/97.	1+			ann.rad.
^{19}F	100.	18.9984032				1/2+	+2.62887	0.072	
^{20}F		19.9999813	11.00 s	β^- /7.0245	5.398/100.	2+	+2.0934	0.042	1.634/100.
									3.33/0.009
^{21}F		20.999949	4.16 s	β^- /5.684	3.7/8.	5/2+	3.9		0.3507/90.
					5.0/63.				1.395/15.
					5.4/29.				(1.746–4.684)
^{22}F		22.00300	4.23 s	β^- /10.82	3.48/15.	4+			1.2746/100.
					4.67/7.				2.0826/82.
					5.50/62.				(0.82–4.37)
^{23}F		23.00357	2.2 s	β^- /8.5		5/2+			1.701/48.
									2.129/34.
									(0.493–3.83)
^{24}F		24.0081	0.3 s	β^- /13.5					1.9816/
^{25}F		25.0121	≈50 ms	β^-, (n)	n//14.				1.70/39.
									(0.57–2.19)
^{26}F		26.0196	10 ms	β^-, (n)	n//11.				2.02/67.
									1.67/19.
^{27}F		27.0269	5.0 ms	β^-, (n)	n//90.				2.02/18.
^{29}F		29.043	2.5 ms	β^-, (n)	n//100.				
^{31}F									
$_{10}$Ne		**20.1797(6)**							
^{16}Ne		16.02575	$\Gamma = 0.12(4)$	2p		0+			
^{17}Ne		17.01770	109. ms	β^+, p/14.53	1.4–10.6/6.9	1/2–			ann.rad./
				β^+, α	/0.014				0.495
^{18}Ne		18.005697	1.67 s	β^+ /4.446	3.416/92.	0+			ann.rad./
									1.0413/7.8
									(0.658–1.70)
^{19}Ne		19.001880	17.22 s	β^+ /3.238	2.24/99.	1/2+	–1.885		ann.rad./
									(0.11–1.55)
^{20}Ne	90.48(3)	19.992440176				0+			
^{21}Ne	0.27(1)	20.99384674				3/2+	–0.66180	+0.103	
^{22}Ne	9.25(3)	21.9913855				0+		–0.19	
^{23}Ne		22.9944673	37.2 s	β^- /4.376	3.95/32.	5/2+	–1.08		0.440/33.
					4.39/67.				(1.64–2.98)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{24}Ne		23.99362	3.38 m	β^- /2.47	1.10/8.	0+			0.4723/100.
					1.98/92.				0.874/7.9
^{25}Ne		24.99779	0.61 s	β^- /7.30	6.3/	1/2+			0.0895/96.
					7.3/				(0.98–3.69)
^{26}Ne		26.00046	197 ms	β^-, n/7.3	n//0.13	0+			0.233/
^{27}Ne		27.0076	31. ms	β^-, n/12.7	n//2.	(3/2+)			
^{28}Ne		28.0121	19. ms	β^-, n/12.3	n//11.	0+			2.06/19.
									0.86/3.
^{29}Ne		29.0194	15. ms	β^-, (n)/15.4	n//17.	(3/2+)			2.92/55.
				β^-, 2n	/<2.2				(0.22–1.18)
^{30}Ne		30.024	7. ms	β^-, (n)	n//9.	0+			0.151/9.
^{31}Ne		31.033	>0.26 μs						
^{32}Ne		32.040	>0.20 μs			0+			
^{34}Ne									
$_{11}$Na		**22.989770(2)**							
^{18}Na		18.0272							
^{19}Na		19.01388	0.03 s	β^+, p/11.18					
^{20}Na		20.00735	0.446 s	β^+ /13.89		2+	+0.3694		ann.rad./
				α	2.15/				1.634/79.
^{21}Na		20.997655	22.48 s	β^+ /3.547	2.50/95.	3/2+	+2.3863	≈ +0.05	ann.rad./
									0.351/5.
^{22}Na		21.9944366	2.605 y	β^+ /90/2.842	0.545/90.	3+	+1.746	+0.19	ann.rad./
				EC/10/					1.2745/99.9
^{23}Na	100.	22.9897697				3/2+	+2.21752	+0.106	
^{24m}Na			20.2 ms	I.T., β^-		1+			0.4723/100.
^{24}Na		23.9909633	14.96 h	β^- /5.5158	1.389/>99.	4+	+1.690		1.3686/100.
									2.754/100.
									(0.997–4.238)
^{25}Na		24.989954	59.3 s	β^- /3.835	2.6/7.	5/2+	+3.683	≈ –0.06	0.3897/12.7
					3.15/25.				0.5850/13.
					4.0/65.				0.9747/14.9
									(0.836–2.80)
^{26}Na		25.99259	1.07 s	β^- /9.31		3+	+2.851	–5.3 mb	1.809/98.9
^{27}Na		26.99401	0.290 s	β^- /9.01	7.95/	5/2+	+3.90	–7.2 mb	0.9847/87.4
				β^-, n/					1.698/11.9
^{28}Na		27.9989	31. ms	β^- /14.0	12.3/	1+	+2.42	+0.04	1.473/37.
				β^-, n/					2.389/18.6
^{29}Na		29.0028	44. ms	β^-, n/13.3	11.5/	3/2+	+2.46	+86. mb	2.560/36.
									(1.04–3.99)
^{30}Na		30.0092	50. ms	β^-, n/17.5	n//30.	2	+2.07		1.483/46.
^{31}Na		31.0136	17.2 ms	β^-, n/15.9	n//37.	3/2–	+2.30		1.483/14.
									(0.05–3.54)
^{32}Na		32.0197	13.5 ms	β^- /19.1					0.240–3.935
^{33}Na		33.027	8.0 ms	β^- /20.	/≈ 38				0.886/16
				β^-, n	0.8,1.02/47(6)				0.546/6.4
				β^-, 2n	/13(3)				0.050–2.55
^{34}Na		34.035	5. ms	β^- /24.					
^{35}Na		35.044	1.5 ms	β^- /24					
^{37}Na									
$_{12}$Mg		**24.3050(6)**							
^{20}Mg		20.01886	96. ms	β^+ /10.73	/70	0+			
				β^+, p	/30				
^{21}Mg		21.01171	122. ms	β^+, p/13.10		5/2+			0.332/51.
^{22}Mg		21.999574	3.86 s	β^+ /4.786	3.05/	0+			0.0729/60.
									0.5820/100.
									(1.28–1.93)
^{23}Mg		22.994125	11.32 s	β^+ /4.057	3.09/92.	3/2+	0.536	1.25	0.440/8.2
^{24}Mg	78.99(4)	23.9850419				0+			
^{25}Mg	10.00(1)	24.9858370				5/2+	–0.85545	+0.200	
^{26}Mg	11.01(3)	25.9825930				0+			
^{27}Mg		26.9843407	9.45 m	β^- /2.6103	1.59/41.	1/2+			0.17068/0.9
					1.75/58.				0.84376/72.
					2.65/0.3				1.01443/28.

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{28}Mg		27.983877	20.9 h	β^- /1.832	0.459/95.	0+			0.0306/95.
									0.4006/36.
									0.9418/36.
									1.342/54.
^{29}Mg		28.98855	1.3 s	β^-/7.55	5.4/	3/2+			0.960/15.
									1.398/16.
									2.224/36.
^{30}Mg		29.9905	0.32 s	β^- /7.0		0+			0.224/85.
^{31}Mg		30.9966	0.24 s	β^- /11.7		(3/2+)			1.61/26.
				β^-, n	/≈6.				
^{32}Mg		31.9992	0.12 s	β^- /10.3		0+			2.765/25.
^{33}Mg		33.0056	91. ms	β^- /13.7	/83.				1.848/
				β^-, n	/17.				
^{34}Mg		34.0091	0.02 s	β^- /11.3		0+			
^{35}Mg		35.0175	0.07 s			(7/2–)			
^{36}Mg		36.022	>0.2 μs			0+			
^{37}Mg		37.031	>0.26 μs			(7/2–)			
^{38}Mg						0+			
$_{13}$Al		**26.981538(2)**							
^{21}Al		21.028	<0.035 μs						
^{22}Al		22.0195	59. ms	β^+ /18.6	p/1.3/18.	4+			ann.rad./
				β^+, p, 2p, α/	α/3.3/0.3				
^{23m}Al			≈0.35 s	β^+, p/0.17					0.554
									0.839
^{23}Al		23.00727	0.47 s	β^+ /12.24					ann.rad./
				β^+, p/					
^{24m}Al			0.129 s	I.T./0.4259					
				β^+	13.3	1+			1.3686/5.3
^{24}Al		23.999941	2.07 s	β^+ /13.878,p	3.40/48.	4+			1.078(2)/16.
					4.42/41.				1.368(2)/96.
					6.80/3.				2.753(2)/43.
					8.74/8.				4.315(3)/15.
									5.392(3)/20.
									7.0662(2)/41.
^{25}Al		24.990429	7.17 s	β^+ /4.277	3.27/	5/2+	3.646		ann.rad./
									1.6115(2)/100.
									0.975(2)/5.
^{26m}Al			6.345 s	β^+ /	3.2/	0+			ann.rad./
^{26}Al		25.9868917	7.1×10^5 y	β^+ /82/4.0042	1.16/	5+	+2.804	+0.17	ann.rad./
				EC/18					1.8087/99.8
^{27}Al	100.	26.9815384				5/2+	+3.64151	+0.140	
^{28}Al		27.9819102	2.25 m	β^- /4.6422	2.865/100.	3+	3.24	0.18	1.7778(6)/100.
^{29}Al		28.980445	6.5 m	β^- /3.680	1.4/30.	5/2+			1.2732(8)/89.
					2.5/70.				2.0282(8)/4.
									2.4262(8)/7.
^{30}Al		29.98296	3.68 s	β^- /8.56	5.05/	3+			1.26313(3)/35.
									2.23525(5)/65.
^{31}Al		30.98395	0.64 s	β^- /8.00	6.25/	5/2+			0.75223(3)/18.
									1.69473(3)/59.
									2.31664(4)/73.
^{32}Al		31.9881	33. ms	β^- /13.0		1+			
^{33}Al		32.9909	41.7 ms	β^- /12.0	/91.5				1.940/2.5
				β^-, n	/8.5				(1.01–4.34)
^{34}Al		33.9969	56. ms	β^- /17.1	4.255/44	4			0.929/57
				β^-, n	/26.				(0.12–4.26)
^{35}Al		34.9999	39. ms	β^-/14.3	0.974/48	5/2+			0.064/45.
				β^-, n	/≈ 41.				(0.12–5.63)
^{36}Al		36.0064	0.09 s	β^-/18.3					
				β^-, n	/<31.				
^{37}Al		37.010	>1 μs	β^-/16.					
^{38}Al		38.0169	>0.2 μs						
^{39}Al		39.022	>0.2 μs						
^{40}Al			>0.26 μs						
^{41}Al									

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
$_{14}$Si		**28.0855(3)**							
^{22}Si		22.0345	29. ms	β^+, p	1.99/20	0+			
^{23}Si		23.0255	40.7 ms	β^+, p/5.9	1.32,(0.6–11.6)				
^{24}Si		24.01155	0.14 s	β^+, p/10.81	1.44,3.92,1.09	0+			ann.rad./
					(1.66–4.47)				
^{25}Si		25.00411	221 ms	β^+, p/12.74		5/2+			ann.rad./
^{26}Si		25.992330	2.23 s	β^+ /5.066	3.282/	0+			ann.rad./
									0.8294(8)/22.
^{27}Si		26.9867048	4.14 s	β^+ /4.8118	3.85/100.	5/2+	–0.8554		ann.rad./
									2.211(5)/0.2
^{28}Si	92.223(19)	27.97692653				0+			
^{29}Si	4.685(8)	28.97649472				1/2+	–0.5553		
^{30}Si	3.092(11)	29.97377022				0+			
^{31}Si		30.9753633	2.62 h	β^- /1.4920	1.471/99.9	3/2+			1.2662(5)/0.05
^{32}Si		31.974148	1.6×10^2 y	β^- /0.224	0.213/100.	0+			
^{33}Si		32.97800	6.1 s	β^- /5.85	3.92	(3/2+)	1.21		1.4313(5)/13.
									1.8477/100.
									2.538(2)/10.
^{34}Si		33.97858	2.8 s	β^- /4.60	3.09/	0+			0.42907(5)/60.
									1.17852(2)/64.
									1.60756(5)/36.
^{35}Si		34.98458	0.9 s	β^- /10.50					
^{36}Si		35.9867	0.5 s	β^- /7.9		0+			
				β^-, n	/≈12.				
^{37}Si		36.9930	≈0.09 s	β^- /12.5					
				β^-, n	/≈17.				
^{38}Si		37.9960	>1 μs	β^- /10.7		0+			
				β^-, n					
^{39}Si		39.0023	>1 μs	β^- /14.8					
^{40}Si		40.0058	>0.2 μs			0+			
^{41}Si		41.013	>0.2 μs						
^{42}Si		42.016	>0.2 μs			0+			
^{43}Si									
$_{15}$P		**30.973761(2)**							
^{24}P		24.0344							
^{25}P		25.0203	<0.03 μs						
^{26}P		26.0118	≈20. ms	β^+, p/18.1		3+			
^{27}P		26.99919	0.3 s	β^+, p/11.63	p/0.73, 0.61/0.07	1/2+			
^{28}P		27.992312	270. ms	β^+ /14.332	3.94/13.	3+			ann.rad./
					5.25/13.				1.779(2)/98.
					6.96/16.				2.839(2)/2.8
					8.8/7.				3.040(2)/3.2
					11.49/52.				4.498(2)/12.
									7.537(2)/9.
^{29}P		28.981801	4.14 s	β^+ /4.9431	3.945/98.	1/2+	1.2349		ann.rad./
									1.273/1.32
									2.426/0.39
^{30}P		29.9783138	2.50 m	β^+ /4.2323	3.245/99.9	1+			ann.rad./
									2.230(3)/0.07
^{31}P	100.	30.9737615				1/2+	+1.13160		
^{32}P		31.9739071	14.28 d	β^- /1.7106	1.710/100.	1+	–0.2524		
^{33}P		32.971725	25.3 d	β^- /0.249	0.249/100.	1/2+			
^{34}P		33.973636	12.4 s	β^- /5.374	3.2/15.	1+			1.78–4.1/
					5.1/85.				2.127(5)/15.
^{35}P		34.973314	47. s	β^- /3.989	2.34/100.	1/2+			1.572(1)/100.
^{36}P		35.97826	5.7 s	β^- /10.41					0.902/77.
									3.291/100.
^{37}P		36.97961	2.3 s	β^- /7.90					0.6462/
									1.5829/
^{38}P		37.9845	0.6 s	β^- /12.4					1.2923/
				β^-, n	/≈12.				2.224/
^{39}P		38.9864	≈0.16 s	β^- /10.5					
				β^-, n	/26				
^{40}P		39.9911	≈0.26 s	β^- /14.5					

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				β^-,n	/≈30.				
^{41}P		40.9948	0.12 s	β^-/≈13.8					
				β^-, n	/≈30.				
^{42}P		42.0001	0.11 s	β^-/17.					
				β^-, n	/≈50.				
^{43}P		43.0033	33. ms	β^-/16.					
				β^-, n	/100.				
^{44}P		44.010	>0.2 μs						
^{45}P		45.015	>0.2 μs						
^{46}P		46.024	>0.2 μs						
$_{16}$S		**32.065(5)**							
^{26}S		26.0278	≈ 10 ms			0^+			
^{27}S		27.0188	16. ms	β^+, 2p/18.3	p/2.26, 7.80				
^{28}S			0.13 s			0^+			
^{29}S		28.99661	0.188 s	β^+ /13.79		5/2+			ann.rad./
				β^+, p/					
^{30}S		29.984903	1.18 s	β^+ /6.138	4.42/78.	0+			ann.rad./
					5.08/20.				0.678/79.
^{31}S		30.979555	2.56 s	β^+ /5.396	4.39/99.	1/2+	0.48793		ann.rad./
									1.2662(5)/1.2
^{32}S	94.93(31)	31.9720707				0+			
^{33}S	0.76(2)	32.9714585				3/2+	+0.64382	–0.068	
^{34}S	4.29(28)	33.9678668				0+			
^{35}S		34.9690321	87.2 d	β^- /0.1672	0.1674/100.	3/2+	+1.00	+0.047	
^{36}S	0.02(1)	35.9670809				0+			
^{37}S		36.9711257	5.05 m	β^- /4.8653	1.64/94.	7/2–			0.9083(4)/0.06
					4.75/5.6				3.1033(2)/94.2
^{38}S		37.97116	2.84 h	β^- /2.94	1.00/	0+			0.1962(4)/0.2
									1.9421(3)/84.
^{39}S		38.97514	11.5 s	β^- /6.64					1.301/52.
									1.697/44.
^{40}S		39.9755	9. s	β^- /4.7		0+			
^{41}S		40.9800	≈2.6 s	β^- /8.7					
				β^-, n					
^{42}S		41.9815	≈0.56 s	β^- /7.8		0+			
				β^-, n	/<4.				
^{43}S		42.987	0.22 s	β^-/12.					
				β^-, n	/≈40				
^{44}S		43.9883	0.12 s	β^-/9.		0+			
				β^-, n	/18.				
^{45}S		44.9948	0.08 s	β^-/14.					
				β^-, n	/54.				
^{46}S		45.9996	>0.2 μs			0+			
^{47}S		47.008	>0.2 μs						
^{48}S		48.013	>0.2 μs			0+			
^{49}S		49.022	<0.2 μs						
$_{17}$Cl		**35.453(2)**							
^{28}Cl		28.0285							
^{29}Cl		29.0141	<0.02 μs						
^{30}Cl		30.0048	<0.03 μs						
^{31}Cl		30.99242	0.15 s	β^+, p/11.98	0.986, 1.52/0.7	3/2+			ann.rad./
^{32}Cl		31.98569	297. ms	β^+ /12.69	9.47/50.	1+	1.11		ann.rad./
				β^+, α	/0.05				2.2305/92
				β^+, p	/0.026				(1.55–4.77)
^{33}Cl		32.977452	2.511 s	β^+ /5.583	4.51/98.	3/2+	+0.752		ann.rad./
									0.8409/0.52
									1.966/0.45
									2.866/0.44
^{34m}Cl			32.2 m	β^+/	1.35/24.	3+			ann.rad./
					2.47/28.				
				I.T./					0.1457(8)/42.
									2.1276(5)/42.

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{34}Cl		33.9737620	1.528 s	β^+ /5.4922	4.50/100.	0+			ann.rad./
^{35}Cl	75.78(4)	34.96885271				3/2+	+0.82187	–0.0825	
^{36}Cl		35.9683069	3.01×10^5 y	β^- /0.7086	0.7093/98.	0+	+1.28547	–0.018	
				β^+, EC/1.1421	0.115/0.002				ann.rad./
^{37}Cl	24.22(4)	36.96590260				3/2+	+0.68412	–0.0649	
^{38m}Cl			0.715 s	I.T./		5–			0.6714/100
^{38}Cl		37.9680106	37.2 m	β^- /4.9168	1.11/31.	2–	2.05		1.64216(1)/31.
					2.77/11.				2.16760(2)/42.
					4.91/58.				
^{39}Cl		38.968008	55.6 m	β^- /3.442	1.91/85.	3/2+			0.25026(1)/47.
					2.18/8.				1.26720(5)/54.
					3.45/7.				0.986–1.517
^{40}Cl		39.97042	1.38 m	β^- /7.48		2–			0.6431(3)/6.
									1.4608(1)/77.
									2.8402(2)/17.
^{41}Cl		40.9707	34. s	β^- /5.7	3.8/				(0.167–1.359)
^{42}Cl		41.9732	6.8 s	β^- /9.4					
^{43}Cl		42.9742	3.3 s	β^- /8.0					
^{44}Cl		43.9785	≈0.43 s	β^-/12.3					
				β^-, n	/<8.				
^{45}Cl		44.980	0.40 s	β^-/11.					
				β^-, n	/24.				
^{46}Cl		45.984	0.22 s	β^-/14.9					
				β^-, n	/≈60				
^{47}Cl		46.988	>0.2 μs	β^-/15.					
				β^-, n	/<3.				
^{48}Cl		47.995	>0.2 μs						
^{49}Cl		48.9999	>0.17 s						
^{50}Cl		50.008							
^{51}Cl		51.014	>0.2 μs						
$_{18}$Ar		**39.948(1)**							
^{30}Ar		30.0216	<0.02 μs			0+			
^{31}Ar		31.0121	≈14.1 ms	β^+ /18.4	p/2.08/100.	5/2			
				β^+, p	/55.				
				β^+, 2p	/2.5				
				β^+, 3p	/0.11				
^{32}Ar		31.99766	98. ms	β^+ /11.2	p/3.35, 0.6–5.55	0+			ann.rad./
				β^+, p	/43.				
^{33}Ar		32.98993	174. ms	β^+ /11.62	3.17,2.10	1/2+	–0.72		ann.rad./
				β^+, p/	(1.32–5.72)				0.810(2)/48.
^{34}Ar		33.980270	0.844 s	β^+/6.061	5.0/95.	0+			ann.rad./
									0.6658(1)/2.5
									3.1290(1)/1.3
^{35}Ar		34.975257	1.77 s	β^+/5.965	4.94/93.	3/2+	+0.633	–0.08	ann.rad./
									1.2185(5)/1.22
									1.763(1)/0.25
									2.964(1)/0.2
^{36}Ar	0.3365(30)	35.9675463				0+			
^{37}Ar		36.9667759	35.0 d	EC/.813		3/2+	+1.15	+0.076	
^{38}Ar	0.0632(5)	37.9627322				0+			
^{39}Ar		38.964313	268. y	β^-/0.565	0.565/100.	7/2–	–1.59	–0.12	
^{40}Ar	99.6003(30)	39.962383123				0+			
^{41}Ar		40.964501	1.82 h	β^-/2.492	1.198/	7/2–			1.29364(5)/99.
									1.6770(3)/0.05
^{42}Ar		41.96305	33. y	β^-/0.60	0.60/100.	0+			
^{43}Ar		42.9657	5.4 m	β^-/4.6					0.4791(2)/10.
									0.7380(1)/43.
									0.9752(1)/100.
									1.4400(3)/39.
^{44}Ar		43.96537	11.87 m	β^-/3.55		0+			0.182–1.866
^{45}Ar		44.96809	21.5 s	β^-/6.9		7/2–			0.0610/25.
									1.020/35.
									3.707/34.
^{46}Ar		45.96809	8.4 s	β^-/5.70		0+			1.944/
^{47}Ar		46.9722	≈0.7 s	β^-					

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{48}Ar		47.9751							
^{49}Ar		48.9822	>0.17 μs	β^-					
^{50}Ar		49.986	>0.17 μs	β^-					
^{51}Ar		50.993	>0.2 μs	β^-					
^{52}Ar		51.998	10 ms	β^-					
^{53}Ar		52.994		β^-					
$_{19}$K		**39.0983(1)**							
^{32}K		32.0219							
^{33}K		33.0073	<0.025 μs						
^{34}K		33.9984	<0.04 μs						
^{35}K		34.98801	0.19 s	β^+ /11.88		3/2+			ann.rad./
				β^+, p/	/0.37				1.751/14.
									2.5698/26.
									2.9827/51.
^{36}K		35.98129	0.342 s	β^+ /12.81	5.3/42.	2+	+0.548		ann.rad./
					9.9/44.				1.97044(5)/82.
				β^+, p	/0.048				2.20783(5)/30.
									2.43343(2)/32.
^{37}K		36.9733769	1.23 s	β^+ /6.149	5.13/	3/2+	+0.2032		ann.rad./
									2.7944(8)/2.
									3.602(2)/0.05
^{38m}K			0.924 s	β^+ /6.742	5.02/100.	0+			ann.rad./
^{38}K		37.969080	7.63 m	β^+ /5.913	2.60/99.8	3+	+1.37		ann.rad./
									2.1675(3)/99.8
									3.9356(5)/0.2
^{39}K	93.2581(44)	38.9637069				3/2+	+0.39146	+0.049	
^{40}K	0.0117(1)	39.9639987	1.26×10^9 y	β^- /1.3111	1.312/89.	4–	–1.29810	–0.061	ann.rad./
				β^+, EC/1.505	1.50/10.7				1.4608/10.5
^{41}K	6.7302(44)	40.9618260				3/2+	+0.21487	+0.060	
^{42}K		41.9624031	12.36 h	β^- /3.525	1.97/19.	2–	–1.1425		0.31260(2)/0.3
					3.523/81.				1.5246(3)/18.1
^{43}K		42.96072	22.3 h	β^- /1.82	0.465/8.	3/2+	+0.163		0.2211(2)/4.
					0.825/87.				0.3729(2)/88.
					1.24/3.5				0.3971(2)/11.
					1.814/1.3				0.6178(2)/81.
^{44}K		43.96156	22.1 m	β^- /5.66	5.66/34.	2–	–0.856		0.36821/2.2
									1.15700(1)/58.
									2.15079(2)/22.
^{45}K		44.96070	17.8 m	β^- /4.20	1.1/23.	3/2+	+0.173		0.1743(5)/80.
					2.1/69.				1.2607(8)/7.
					4.0/8.				1.7056(6)/69.
									2.3542(5)/14.
^{46}K		45.96198	1.8 m	β^- /7.72	6.3/	2–	–1.05		1.347(1)/91.
									3.700(5)/28.
^{47}K		46.96168	17.5 s	β^- /6.64	4.1/99.	1/2+	+1.93		0.56474(3)/15.
					6.0/1.				0.58575(3)/85.
									2.0131/100
^{48}K		47.96551	6.8 s	β^- /12.09	5.0/	(2–)			0.67122(1)/4.
									0.6723(5)/20.
									0.78016(1)/32.
									3.83153(7)/80.
^{49}K		48.9675	1.26 s	β^- /11.0					2.025/
									2.252/
^{50}K		49.9728	0.472 s	β^- /14.2					
^{51}K		50.9764	0.365 s	β^- /					
^{52}K		51.983	0.105 s	β^-					
^{53}K		52.987	30. ms	β^-		3/2+			
^{54}K		53.994	10. ms	β^-					
$_{20}$Ca		**40.078(4)**							
^{34}Ca		34.0141	<0.035 μs						
^{35}Ca		35.0048	25.7 ms	β^+, p/15.6	p/1.43/49				
					1.9–8.8				
^{36}Ca		35.99309	0.10 s	β^+, (p)/10.99	2.52				ann.rad./

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				β^+, n/					
^{37}Ca		36.98587	0.18 s	β^+ /11.64	3.103	3/2+			ann.rad./
				β^+, n/					1.369
^{38}Ca		37.976319	0.44 s	β^+ /6.74		0+			ann.rad./
									1.5677(5)/25.
									3.210(2)/1.
^{39}Ca		38.970718	0.861 s	β^+ /6.531	5.49/100.	3/2+	1.02168		ann.rad./
^{40}Ca	96.941(156)	39.9625912				0+			
^{41}Ca		40.9622783	1.02×10^5 y	EC/0.4214		7/2–	–1.5948	–0.090	
^{42}Ca	0.647(23)	41.9586183				0+			
^{43}Ca	0.135(10)	42.9587668				7/2–	–1.3173	–0.055	
^{44}Ca	2.086(110)	43.955481				0+			
^{45}Ca		44.956186	162.7 d	β^- /0.257	0.257/100.	7/2–	–1.327	+0.05	
^{46}Ca	0.004(3)	45.953693	$>0.4 \times 10^{16}$ y	$\beta^-\beta^-$		0+			
^{47}Ca		46.954546	4.536 d	β^-/1.992	0.684/84.	7/2–	–1.38	+0.02	1.297/75
					1.98/16.				(0.041–1.88)
^{48}Ca	0.187(21)	47.952533	4.3×10^{19} y	$\beta^-\beta^-$		0+			
			$>7.1 \times 10^{19}$ y	β^-					
^{49}Ca		48.955673	8.72 m	β^- /5.262	0.89/7.	3/2–			3.0844(1)/92.
					1.95/92.				4.0719(1)/7.
^{50}Ca		49.95752	14. s	β^- /4.97	3.12/	0+			0.2569/98.
									(0.0715–1.59)
^{51}Ca		50.9615	10. s	β^- /7.3		(3/2–)			
^{52}Ca		51.9651	4.6 s	β^- /8.0					
^{53}Ca		52.9701	0.09 s	β^- /10.9					
^{54}Ca		53.975							
^{55}Ca		54.981							
^{56}Ca		55.986							
$_{21}$Sc		**44.955910(8)**							
^{36}Sc		36.0149							
^{37}Sc		37.0030							
^{38}Sc		37.9947	<0.3 μs						
^{39}Sc		38.98479	<0.3 μs	p					
^{40}Sc		39.977964	0.182 s	β^+ /14.320	5.73/50.	4–			ann.rad./
					7.53/15.				0.752/41.
					8.76/15.				3.732/99.5
					9.58/20.				(1.12–3.92)
^{41}Sc		40.9692513	0.596 s	β^+ /6.4953	5.61/100.	7/2–	+5.431	–0.156	ann.rad./
^{42m}Sc			61.6 s	β^+ /	2.82/	7+			ann.rad./
									0.4375(5)/100.
									1.2270(5)/100.
									1.5245(5)/100.
^{42}Sc		41.9655168	0.682 s	β^+ /6.4259	5.32/100.	0+			ann.rad./
^{43}Sc		42.961151	3.89 h	β^+, EC/2.221	0.82/22.	7/2–	+4.62	–0.26	ann.rad./
					1.22/78.				0.3729(1)/22.
^{44m}Sc			58.2 h	I.T./0.27		6+	+3.88		0.27124(1)/87.
				EC/3.926					(1.00–1.16)
^{44}Sc		43.959403	3.93 h	β^+, EC/3.653	1.47/	2+	+2.56	+0.10	ann.rad./
									1.157/100
^{45}Sc	100.	44.955910				7/2–	+4.75649	–0.220	
^{46m}Sc			18.7 s	I.T./0.14253		1–			0.14253(2)/62.
^{46}Sc		45.955170	83.81 d	β^- /2.367	0.357/100.	4+	+3.03	+0.12	0.8893/100
									1.121/100
^{47}Sc		46.952408	3.349 d	β^- /0.600	0.439/69.	7/2–	+5.34	–0.22	0.15938(1)/68.
					0.601/31.				
^{48}Sc		47.95224	43.7 h	β^- /3.99	0.655/	6+			0.9835/100
									1.03750(1)/97.
									1.3121/100
^{49}Sc		48.950024	57.3 m	β^- /2.006	2.00/99.9.	7/2–			1.7619(3)/0.05
^{50}Sc		49.95219	1.71 m	β^- /6.89	3.05/76.	(5+)			0.5235(1)/88.
					3.60/24.				1.1210(1)/100.
									1.5537(2)/100.
^{51}Sc		50.95360	12.4 s	β^- /6.51	4.4/	7/2–			1.4373(4)/52.
					5.0/				0.718–2.144
^{52}Sc		51.9566	8.2 s	β^- /9.0		(3+)			

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{53}Sc		52.9592	>3. ms	β^- /8.1					
^{54m}Sc			≈7 μs			(5+)			0.110/IT
^{54}Sc		53.9630	0.23 s	β^- /11.6					0.100/50
									1.70/40
									0.50/40
^{55}Sc		54.967	0.12 s	β^- /13					
^{56}Sc		55.973							
^{57}Sc		56.977							
^{58}Sc		57.983							
$_{22}$Ti		**47.867(1)**							
^{38}Ti		38.0098	<0.12 μs						
^{39}Ti		39.0013	29. ms	β^+ /15.4					
^{40}Ti		39.9905	53. ms	β^+ /11.7	p/2.16/29				
				β^+, p	3.73/23				
					1.70/22				
					0.242–5.74				
^{41}Ti		40.98313	80. ms	β^+, p/12.93	p/4.73/107	3/2+			ann.rad./
					3.10/67				
					3.75/39				
					0.744–6.73				
^{42}Ti		41.97303	0.20 s	β^+ /7.000	6.0/				ann.rad./
									0.6107(5)/56.
^{43}Ti		42.96852	0.50 s	β^+ /6.87	5.80/	7/2–	0.85		ann.rad./
^{44}Ti		43.959690	60. y	EC/0.268		0+			0.06787/91
									0.07832/97
^{45}Ti		44.958124	3.078 h	β^+/86/2.062	1.04	7/2–	0.095	0.015	ann.rad./
				EC/14/					(0.36–1.66)
^{46}Ti	8.25(3)	45.952630				0+			
^{47}Ti	7.44(2)	46.951764				5/2–	–0.78848	+0.30	
^{48}Ti	73.72(3)	47.947947				0+			
^{49}Ti	5.41(2)	48.947871				7/2–	–1.10417	+0.24	
^{50}Ti	5.18(2)	49.944792				0+			
^{51}Ti		50.946616	5.76 m	β^- /2.471	1.50/92.	3/2–			0.3197(2)/93.
					2.13/				0.6094–0.9291
^{52}Ti		51.94690	1.7 m	β^- /1.97	1.8/100.	0+			0.0170(5)/100.
									0.1245/100
^{53}Ti		52.9497	33. s	β^- /5.0	(2.2–3)/	3/2–			0.1008(1)/20.
									0.1276(1)/45.
									0.2284(1)/39.
									1.6755(5)/45.
									(1.72–2.8)/
^{54}Ti		53.9509	1.5 s	β^- /4.3					
^{55}Ti		54.9551	0.32 s	β^- /7.4					
^{56}Ti		55.9580	0.19 s	β^- /7.0					
^{57}Ti		56.963	0.06 s	β^- /11.					
^{58}Ti		57.966	≈47 ms						
^{59}Ti		58.972	0.06 s						
^{60}Ti		59.976	>0.15 μs						
^{61}Ti		60.982	>0.15 μs						
$_{23}$V		**50.9415(1)**							
^{40}V		40.0111							
^{41}V		40.9997							
^{42}V		41.9912	<0.055 μs						
^{43}V		42.9807	>0.8 s	β^+ /11.3					
^{44}V		43.9744	0.09 s	β^+, α/13.7					ann.rad./
^{45}V		44.96578	0.54 s	β^+ /7.13		7/2–			
^{46}V		45.960200	0.4223 s	β^+ /7.051	6.03/100.	0+			ann.rad./
^{47}V		46.954907	32.6 m	β^+, EC/2.928	1.90/99.+	3/2–			ann.rad./
									1.7949(8)/0.19
									(0.2–2.16)
^{48}V		47.952254	15.98 d	β^+ /4.012	0.698/50.	4+	2.01		ann.rad./
									0.9835/100
									(1.3–2.4)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{49}V		48.948517	337. d	EC/0.602		7/2–	4.47		
^{50}V	0.250(4)	49.947163	1.4×10^{17} y	EC	/82.7	6+	+3.34569	+0.21	
				β^-	/17.3				
^{51}V	99.750(4)	50.943964				7/2–	+5.148706	–0.04	
^{52}V		51.944780	3.76 m	β^- /3.976	2.47/	3+			1.4341(1)/100.
^{53}V		52.944342	1.56 m	β^- /3.436	2.52/	7/2–			1.0060(5)/90.
									1.2891(3)/10.
^{54m}V			0.9 μs			(5+)			0.108/IT
^{54}V		53.94644	49.8 s	β^- /7.04	1.00/5.	3+			0.8348/97.
					2.00/12.				0.9887/80.
					2.95/45.				2.259/46.
					5.20/11.				(0.56–3.38)
^{55}V		54.9472	6.5 s	β^- /6.0	6.0/	(7/2–)			0.5177/73.
									(0.224–1.21)
^{56}V		55.9504	0.23 s	β^- /9.1					0.70/50.
									0.34/40.
									1.00/30.
^{57}V		56.9524	0.33 s	β^- /8.1					0.30/60.
									0.60/30.
									0.80/30.
^{58}V		57.9567	0.20 s	β^- /11.6					
^{59}V		58.9593	0.13 s	β^- /9.9					0.90/80.
^{60}V		59.965	0.20 s	β^- /14.					0.102–0.208
^{61}V		60.967	0.04 s						0.646
^{62}V		61.973	≈65 ms						
^{63}V		62.977	>0.15 μs						
^{64}V			>0.15 μs						
$_{24}$Cr		**51.9961(6)**							
^{42}Cr		42.0064	13. ms	β^+, p	p/1.90/29				
					p/1.50–3.7				
^{43}Cr		42.9977	21. ms	β^+, p	p/3.83/18				
					p/4.29/15				
					p/1.01–4.59				
^{44}Cr		43.9855	53. ms	β^+, (p)/10.3	p/0.95–3.1				
^{45}Cr		44.9792	0.05 s	β^+, p/12.5		7/2–			ann.rad./
^{46}Cr		45.96836	0.3 s	β^+ /7.60					ann.rad./
^{47}Cr		46.96291	0.51 s	β^+/7.45		3/2–			ann.rad./
^{48}Cr		47.95404	21.6 h	EC/1.66					ann.rad./
									0.116(2)/95.
									0.305(10)/100.
^{49}Cr		48.951341	42.3 m	β^+, EC/2.631	1.39/	5/2–	0.476		ann.rad./
					1.45/				0.09064(1)/51.
					1.54/				0.15293(1)/27.
									(0.062–1.6)
^{50}Cr	4.345(13)	49.946050	$>1.8 \times 10^{17}$ y	β^+EC		0+			
^{51}Cr		50.944772	27.70 d	EC/0.7527		7/2–	–0.934		0.3201/10.2
^{52}Cr	83.789(18)	51.940512				0+			
^{53}Cr	9.501(17)	52.940653				3/2–	–0.47454	–0.15	
^{54}Cr	2.365(7)	53.938885				0+			
^{55}Cr		54.940844	3.497 m	β^- /2.603	2.5/	3/2–			1.5282(2)/0.04
									(0.13–2.37)
^{56}Cr		55.94065	5.9 m	β^- /1.62	1.50/100.	0+			0.026(2)/100.
									0.083(3)/100.
^{57}Cr		56.9438	21. s	β^- /5.1	3.3/	3/2–	0.0834		0.850/8.
					3.5/				(0.083–2.62)
^{58}Cr		57.9443	7.0 s	β^- /4.0					(0.131–0.683)
^{59m}Cr			0.10 ms			(9/2+)			0.208/IT
									0.193
									0.102
^{59}Cr		58.9487	1.0 s	β^- /7.7					1.236
^{60}Cr		59.9497	0.6 s	β^- /6.0					
^{61}Cr		60.9541	0.26 s	β^- /8.8					0.354–1.860
^{62}Cr		61.9558	0.19 s	β^- /7.3					0.285
^{63}Cr		62.962	0.11 s						
^{64}Cr		63.964	0.04 s						

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{65}Cr		64.970	>0.15 μs						
^{66}Cr			>0.15 μs						
^{67}Cr									
$_{25}$Mn		**54.938049(9)**							
^{44}Mn		44.0069	<0.105 μs						
^{45}Mn		44.9945	<0.07 μs						
^{46}Mn		45.9867	34. ms	β^+ /17.1					
				β^+, p	//≈58				
^{47}Mn		46.9761	≈0.1 s	β^+ /12.3					
^{48}Mn		47.9689	0.15 s	β^+ /13.5	5.79/58.	4+			
					4.43/10.				
^{49}Mn		48.95962	0.38 s	β^+ /7.72	6.69/	5/2–			ann.rad./
^{50m}Mn			1.74 m	β^+ /7.887	3.54/	5+			ann.rad./
									1.0980/94.
									0.783/91.
									(0.66–3.11)
^{50}Mn		49.954244	0.283 s	β^+ /7.6330	6.61/	0+			ann.rad./
^{51}Mn		50.948215	46.2 m	β^+, EC/3.208	2.2/	5/2–	3.568	0.4	ann.rad./
									0.7491(1)/0.26
									(1.148–1.164)
^{52m}Mn			21.1 m	β^+ /98/5.09	2.631/	2+	0.0076		ann.rad./
				I.T./2/0.378					0.3778 (I.T.)
									1.43406(1)/98.
									(0.7–4.8)
^{52}Mn		51.945570	5.591 d	β^+ /4.712	0.575/	6+	+3.063	+0.5	ann.rad./
				EC/					0.74421(1)/90.
									1.4341/100
^{53}Mn		52.941294	3.7×10^6 y	EC/0.5970		7/2–	5.024		
^{54}Mn		53.940363	312.1 d	EC/1.377		3+	+3.282	+0.33	0.8340/100
			6.7×10^8 y	β^+	$//1.3 \times 10^{-7}$				
^{55}Mn	100.	54.938049				5/2–	+3.4687	+0.32	
^{56}Mn		55.938909	2.579 h	β^- /3.6954	0.718/18.	3+	+3.2266		0.84675/99
					1.028/34.				1.81072(4)/27.
									2.113/14.5
^{57}Mn		56.938287	1.45 m	β^- /2.691		5/2–			
^{58}Mn		57.93999	65 s	β^- /6.25	3.8/	3+			0.45916(2)/20.
					5.1/				0.81076(1)/82.
									1.32309(5)/53.
^{59}Mn		58.94045	4.6 s	β^- /5.19	4.5/	5/2–			0.726/
									0.473/
									0.287–2.35
^{60m}Mn			1.77 s	β^- /IT	5.7/	3+			0.824/
^{60}Mn		59.9433	50. s	β^- /8.6		0+			1.969/
^{61}Mn		60.9446	0.67 s	β^- /7.4		(5/2)–			
^{62}Mn		61.9480	0.67 s	β^- /10.4		(3+)			0.877/
									0.942–1.299
^{63}Mn		62.9498	0.28 s	β^- /8.8					0.356,0.450
^{64m}Mn			>0.1 ms						0.135/IT
^{64}Mn		63.9537	87 ms	β^- /11.8					0.746
^{65}Mn		64.9561	0.09 s	β^- /10.					0.366
^{66}Mn		65.961	66 ms						0.471
^{67}Mn		66.964	42 ms						
^{68}Mn			28 ms						
^{69}Mn			14 ms						
$_{26}$Fe		**55.845(2)**							
^{45}Fe		45.0146	4. ms	2p	p//≈80.				
^{46}Fe		46.0008	12. ms	β^+ /13.1	p//≈36.				
^{47}Fe		46.9929	22. ms	β^+ /15.6	p//87.				
^{48}Fe		47.9806	≈ 44. ms	β^+ /11.2					
^{49}Fe		48.9763	70. ms	β^+ /13.0		(7/2–)			ann.rad./
^{50}Fe		49.9630	0.15 s	β^+ /8.2					0.651
^{51}Fe		50.95683	0.31 s	β^+ /8.02		(5/2–)			ann.rad./

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{52m}Fe			46. s	β^+ /4.4		(12+)			ann.rad./
									(0.622–2.286)/
^{52}Fe		51.94812	8.28 h	β^+ /57/2.37	0.804/	0+			ann.rad./
				EC/43/					0.16868(1)/99.
				I.T./					0.377 (I.T.)/
^{53m}Fe			2.6 m	I.T./3.0407		19/2–			0.7011(1)/99.
									1.0115(1)/87.
									1.3281(1)/87.
									2.3396(1)/13.
^{53}Fe		52.945312	8.51 m	β^+ /3.743	2.40/42.	7/2–			ann.rad./
					2.80/57.				0.3779(1)/42.
									(1.2–3.2)
^{54}Fe	5.845(35)	53.939615	>3.1 × 10^{22} y	EC-EC		0+			
^{55}Fe		54.938298	2.73 y	EC/0.2314		3/2–			Mn x-ray
^{56}Fe	91.754(36)	55.934942				0+			
^{57}Fe	2.119(10)	56.935398				1/2–	+0.0906	0.16	
^{58}Fe	0.282(4)	57.933280				0+			
^{59}Fe		58.934880	44.51 d	β^-/1.565	0.273/48.	3/2–	–0.336		1.099/57
					0.475/51.				1.292/43.
									(0.14–1.48)
^{60}Fe		59.934077	1.5 × 10^6 y	β^- /0.237	0.184/100.	0+			0.0586/100
^{61m}Fe			0.25 μs			(9/2+)			0.654/IT
									0.207
^{61}Fe		60.93675	6.0 m	β^- /3.98	2.5/13.				1.205/44.
					2.63/54.				1.028/43.
					2.80/31.				(0.12–3.37)
^{62}Fe		61.93677	68. s	β^- /2.53	2.5/100.	0+			0.5061(1)/100.
^{63}Fe		62.9404	6. s	β^- /6.3		5/2–			0.995/
									(1.365–1.427)
^{64}Fe		63.9411	2.0 s	β^- /4.9					
^{65m}Fe			0.4 μs			(5/2–)			0.364/IT
^{65}Fe		64.9449	1.3 s	β^- /7.9					
^{66}Fe		65.9460	0.44 s	β^- /5.7					0.471–1.425
^{67m}Fe			≈0.04 ms			(5/2–)			0.367/IT
^{67}Fe		66.9500	0.48 s	β^- /8.8					0.189
^{68}Fe		67.953	0.15 s	β^- /≈7.6					
^{69}Fe		68.958	0.17 s						
^{70}Fe			>0.15 μs						
^{71}Fe			>0.15 μs						
^{72}Fe			>0.15 μs						
$_{27}$Co		**58.933200(9)**							
^{48}Co		48.0018							
^{49}Co		48.990	<0.035 μs						
^{50}Co		49.9812	44. ms	β^+ /17.0	2.03–2.79				
^{51}Co		50.9705	>0.2 μs	β^+ /12.8					
^{52}Co		51.9632	0.12 s	β^+ /14.0					0.849–1.942
^{53m}Co			0.25 s	β^+, p/		19/2–			ann.rad./
^{53}Co		52.95423	0.24 s	β^+ /8.30		7/2–			ann.rad./
^{54m}Co			1.46 m	β^+ /8.44	4.25/100.	7+			ann.rad./
									0.411(1)/99.
									1.130(1)/100.
									1.408(1)/100.
^{54}Co		53.948464	0.1932 s	β^+ /8.2430	7.34/100.	0+			ann.rad./
^{55}Co		54.942003	17.53 h	β^+ /3.4513	0.53/	7/2–	+4.822		ann.rad./
				EC/	1.03/				0.9312/75.
					1.50/				0.4772/20.
									(0.092–3.11)
^{56}Co		55.939844	77.3 d	β^+/4.566	1.459/18.	4+	3.85	+0.25	ann.rad./
				EC/					0.8468/99.9
									1.2383/68.
									(0.26–3.61)
^{57}Co		56.936296	271.8 d	EC/0.8361		7/2–	+4.72	+0.5	0.12206/86
									(0.014–0.706)
^{58m}Co			9.1 h	I.T./		5+			0.02489/0.035
^{58}Co		57.935757	70.88 d	β^+ /2.307		2+	+4.04	+0.22	ann.rad./

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				EC/					0.81076/99
^{59}Co	100.	58.933200				7/2–	+4.63	+0.41	
^{60m}Co			10.47 m	I.T./99.8/0.059		2+	+4.40	+0.3	0.0586/2.0
				β^- /0.2/1.56					
^{60}Co		59.933822	5.271 y	β^- /2.824	0.315/99.7	5+	+3.799	+0.44	1.1732/100
									1.3325/100
^{61}Co		60.932479	1.650 h	β^- /1.322	1.22/95.	7/2–			0.0674/86.
									0.842–0.909
^{62m}Co			13.9 m	β^- /	0.88/25.	5+			1.1635(3)/70.
					2.88/75.				1.1730(3)/98.
									2.0039(3)/19.
^{62}Co		61.93405	1.50 m	β^- /5.32	1.03/10.	2+			1.1292(3)/13.
					1.76/5.				1.1730(3)/83.
					2.9/20.				1.9851(1)/3.
					4.05/60.				2.3020(1)/19.
^{63}Co		62.93362	27.5 s	β^- /3.67	3.6/	7/2–			0.08713(1)/49.
									0.9817(3)/2.6
									0.156–2.17
^{64}Co		63.93581	0.30 s	β^- /7.31	7.0/	1+			
^{65}Co		64.93648	1.14 s	β^- /5.96		(7/2)–			
^{66m2}Co			>0.1 ms			(8–)			0.252/IT
									0.214
									0.175
^{66m1}Co			1.2 μs			(5+)			0.175/IT
^{66}Co		65.9398	0.25 s	β^- /10.0					(1.245–1.425)
^{67}Co		66.9406	0.43 s	β^- /8.4					0.694
^{68}Co		67.9444	0.19 s	β^- /11.7					
^{69}Co		68.9452	0.20 s	β^- /9.3					
^{70}Co		69.950	0.09 s	β^- 13.					
^{71}Co		70.952	0.21 s	β					
^{72}Co		71.956	0.09 s	β					
^{73}Co			>0.15 μs						
^{74}Co			>0.15 μs						
^{75}Co			>0.15 μs						
$_{28}$Ni		**58.6934(2)**							
^{48}Ni			≈ 0.5 μs						
^{49}Ni			12. ms						
^{50}Ni		49.9959	9. ms	β^+, p	//≈75.				
^{51}Ni		50.9877	>0.2 μs	β^+ /16.0					
^{52}Ni		51.9757	38. ms	β^+ /11.7					
^{53}Ni		52.9685	0.05 s	β^+, p/13.3		7/2–			ann.rad./
^{54}Ni		53.95791	0.11 s	β^+ /8.80					0.937
^{55}Ni		54.95134	0.20 s	β^+ /8.70	7.66/	7/2–			ann.rad./
^{56}Ni		55.94214	6.08 d	EC/2.14		0+			0.15838/99
				β^+ /<10^{-6}					0.81185(3)/87.
									0.2695–0.7500
^{57}Ni		56.939800	35.6 h	β^+ /3.264	0.712/10.	3/2–	–0.798		ann.rad./
				EC/	0.849/76.				1.3776/78.
									(0.127–3.177)
^{58}Ni	68.0769(89)	57.935348	>4 × 10^{19} y	EC-EC		0+			
^{59}Ni		58.934351	≈7.6 × 10^4 y	EC/		3/2–			
^{60}Ni	26.2231(77)5	9.930790				0+			
^{61}Ni	1.1399(6)	60.931060				3/2–	–0.75002	+0.16	
^{62}Ni	3.6345(17)	61.928348				0+			
^{63}Ni		62.929673	100. y	β^- /0.066945	0.065/	1/2–			
^{64}Ni	0.9256(9)	63.927969				0+			
^{65}Ni		64.930088	2.517 h	β^- /2.137	0.65/30.	5/2–	0.69		0.36627(3)/5.
					1.020/11.				1.11553(4)/16.
					2.140/58.				1.48184(5)/23.
^{66}Ni		65.92912	54.6 h	β^- /0.23		0+			
^{67m}Ni			13.3 μs			9/2+			0.313/IT
									0.694
^{67}Ni		66.93157	21. s	β^- /3.56	3.8/	1/2–	+0.601		1.0722/100.
									1.6539/100.
									(0.10–1.98)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{68m2}Ni			0.34 μs			0+			0.511
^{68m1}Ni			0.86 ms			(5–)			0.814/IT
									2.033
^{68}Ni		67.93185	29. s	β^- /2.06					
^{69m2}Ni			0.44 μs			(17/2)			0.148/IT
									0.593
									1.959
^{69m1}Ni			3.5 s						
^{69}Ni		68.9352	11. s	β^- /5.4					0.6807(3)/100.
									(0.207–1.213)
^{70m}Ni			0.21 μs			(8+)			0.183/IT
									0.448
									0.970
									1.259
^{70}Ni		69.9361	6.0 s	β^- /3.5					
^{71}Ni		70.9400	2.56 s	β^- /6.9					
^{72}Ni		71.9413	1.6 s	β^- /5.2					
^{73}Ni		72.946	0.84 s	β^- /9.					
^{74}Ni		73.948	1.1 s	β^- /7.					
^{75}Ni		74.953	≈0.47 s						
^{76}Ni		75.955	≈0.24 s						
^{77}Ni		76.961	>0.15 μs						
^{78}Ni		77.964	>0.15 μs						
$_{29}$Cu		**63.546(3)**							
^{52}Cu		51.9972							
^{53}Cu		52.9856	<0.3 μs						
^{54}Cu		53.9767	<0.075 μs						
^{55}Cu		54.9655	>0.2 μs	β^+ /13.2					
^{56}Cu		55.9586	93. ms	β^+ /15.3					0.511/233
									2.700/100
									0.9507–3.287
^{57}Cu		56.94922	196. ms	β^+ /8.77		3/2–			0.77–3.01
^{58}Cu		57.944541	3.21 s	β^+ /8.563	4.5/15.	1+			ann.rad./
				EC/	7.439/83.				0.0403(4)/5.
									1.4483(2)/11.
									1.4546(2)/16.
^{59}Cu		58.939504	1.36 m	β^+ /4.800	1.9/	3/2–			ann.rad./
					3.75/				0.3393(1)/8.
									0.8780(1)/12.
									1.3015(1)/15.
									(0.4–2.6)
^{60}Cu		59.937368	23.7 m	β^+ /6.127	2.00/69.	2+	+1.219		ann.rad./
				EC/	3.00/18.				1.3325/88.
					3.92/6.				1.7915/45.
									(0.12–5.048)
^{61}Cu		60.933462	3.35 h	β^+ /2.237	0.56/3.	3/2–	+2.14		ann.rad./
					0.94/5.				0.2830/13.
					1.15/2.				0.6560/11.
					1.220/51.				(0.067–2.123)
^{62}Cu		61.932587	9.67 m	β^+ /98/3.948	2.93/98.	1+	–0.380		ann.rad./
				EC/					1.17302(1)/0.6
									(0.87–3.37)
^{63}Cu	69.15(15)	62.929601				3/2–	+2.2233	–0.211	
^{64}Cu		63.929768	12.701 h	β^- /38/0.579	0.578/	1+	–0.217		ann.rad./
				β^+ /19/1.6751	0.65/				1.3459(3)/0.6
				EC/41/					
^{65}Cu	30.85(15)	64.927794				3/2–	+2.3817	–0.195	
^{66}Cu		65.928873	5.09 m	β^- /2.642	1.65/6.	1+	–0.282		0.8330(1)/0.22
					2.7/94.				1.0392(2)/9.2
^{67}Cu		66.92775	2.580 d	β^- /0.58	0.395/56.	3/2–			0.09125(1)/7.
					0.484/23.				0.09325(1)/17.
					0.577/20.				0.18453(1)/47.
^{68m}Cu			3.79 m	I.T./86/		6–	+1.24		0.0843(5)/70.
				β^- /14/1.8					0.1112(5)/18.
									0.5259(5)/74.

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									(0.64–1.34)
^{68}Cu		67.92964	31. s	β^- /4.46	3.5/40.	1+	+2.48		1.0774(5)/58.
					4.6/31.				1.2613(5)/17.
									(0.15–2.34)
^{69m}Cu			0.36 μs			(13/2+)			0.075/IT
									0.190/IT
									0.680
									1.871
^{69}Cu		68.92943	2.8 m	β^- /2.68	2.48/80.	3/2–	+2.84		0.5307(3)/3.
									0.8340(5)/6.
									1.0065(8)/10.
^{70m}Cu			47. s	β^- /	2.52/10.	5–	+1.9		0.8848(2)/100.
									0.9017(2)/90.
									1.2517(5)/60.
									(0.39–3.06)
^{70}Cu		69.93241	5. s	β^- /6.60	5.42/54.	1+	+1.5		0.8848(2)/54.
					6.09/46.				
^{71m}Cu			0.28 μs			(19/2)			0.133/IT
									0.494
									0.939
									1.189
^{71}Cu		70.93262	20. s	β^- /4.56		3/2–			0.490/
^{72m}Cu			1.76 μs			(4–)			0.051/IT
									0.082
									0.138
^{72}Cu		71.9357	6.6 s	β^- /8.2		(1+)			0.652/
^{73}Cu		72.9365	4.2 s	β^- /6.3	5.8/43				0.450/100
					6.25/42				0.307–1.559
^{74}Cu		73.9401	1.6 s	β^- /9.9					
^{75}Cu		74.9414	1.2 s	β^- /7.9					
^{76}Cu		75.9455	0.64 s	β^- /11.					
^{77}Cu		76.947	0.47 s	β^- /≈10.					
^{78}Cu		77.952	0.34 s	β^- /12.					
^{79}Cu		78.954	0.19 s	β^- /11.					
^{80}Cu		79.962	>0.15 μs						
$_{30}$Zn		**65.39(2)**							
^{54}Zn		53.9929							
^{55}Zn		54.9840							
^{56}Zn		55.9724	0.04 s						
^{57}Zn		56.9649	0.04 s	β^+, p/14.6		(7/2–)			ann.rad./
^{58}Zn		57.9546	0.09 s	β^+					
^{59}Zn		58.94927	183. ms	β^+, p/9.09	8.1/	3/2–			ann.rad./
									(0.491–0.914)
^{60}Zn		59.94183	2.40 m	β^+ /97/4.16		0+			ann.rad./
				EC/3/					0.669/47.
									(0.062–0.947)
^{61}Zn		60.93951	1.485 m	β^+ /5.64	4.38/68.	3/2–			ann.rad./
									0.4748/17.
									(0.15–3.52)
^{62}Zn		61.93433	9.22 h	β^+ /3/1.63	0.66/7.	0+			ann.rad./
				EC/93/					0.0408/25
									0.5967/26.
									(0.20–1.526)/
^{63}Zn		62.933215	38.5 m	β^+ /93/3.367	1.02/	3/2–	–0.28164	+0.29	ann.rad./
				EC/7/	1.40/				0.66962(5)/8.4
					1.71/				0.96206(5)/6.6
					2.36/84.				(0.24–3.1)
^{64}Zn	48.27(32)	63.929146	>2.3 × 10^{18} y	EC-EC		0+			
^{65}Zn		64.929245	243.8 d	β^+ /98/1.3514	0.325/	5/2–	+0.7690	–0.023	ann.rad./
				EC/1.5/					1.116/50.8
^{66}Zn	27.977(77)	65.926036				0+			
^{67}Zn	4.102(21)	66.927131				5/2–	+0.8755	+0.15	
^{68}Zn	19.02(12)	67.924847				0+			
^{69m}Zn			13.76 h	I.T./99+/0.439		9/2+			0.4390(2)/95.
^{69}Zn		68.926553	56. m	β^- /0.906	0.905/99.9	1/2–			0.318/

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{70}Zn	0.631(9)	69.925325				0+			
^{71m}Zn			3.97 h	β^- /	1.45/	9/2+			0.3864/93.
									0.4874/62.
									0.6203/57.
									(0.099–2.489)
^{71}Zn		70.92773	2.4 m	β^- /2.81		1/2–			0.5116(1)/30.
									0.9103(1)/7.5
									(0.12–2.29)
^{72}Zn		71.92686	46.5 h	β^- /0.46	0.25/14.	0+			0.0164(3)/8.
					0.30/86.				0.1447(1)/83.
									0.1915(2)/9.4
^{73m}Zn			6. s		I.T./0.196	(7/2+)			0.042
^{73}Zn		72.92978	24. s	β^- /4.29	4.7/	(1/2–)			0.216(1)/100.
									0.496–0.911
^{74}Zn		73.92946	1.60 m	β^- /2.3	2.1/				0.0565/
									0.1401/
									(0.05–0.35)
^{75}Zn		74.9329	10.2 s	β^- /6.0					0.229/
^{76}Zn		75.9334	5.7 s	β^- /4.2	3.6/				0.119/
^{77m}Zn			1.0 s	β^- /		(1/2–)			0.772
^{77}Zn		76.9371	2.1 s	β^- /7.3	4.8/				0.189/
^{78m}Zn			>0.03 ms						1.070
^{78}Zn		77.9386	1.5 s	β^- /6.4					0.225/
^{79}Zn		78.9421	1.0 s	β^- /8.6					0.702/
^{80}Zn		79.9444	0.54 s	β^- /7.3					0.713/
									0.2248/
^{81}Zn		80.9505	0.29 s	β^- /11.9					
^{82}Zn		81.9548	>0.15 μs						
^{83}Zn			>0.15 μs						
$_{31}$Ga		**69.723(1)**							
^{56}Ga		55.9949							
^{57}Ga		56.9829							
^{58}Ga		57.9742							
^{59}Ga		58.9634							
^{60}Ga		59.9571	0.07 s	β^+					1.004
				β^+, p	//≈1.6				3.848
				β^+, α	//≈0.02				1.555–2.559
^{61}Ga		60.9492	0.17 s	β^+ /9.0		3/2$^-$			0.088–1.362
^{62}Ga		61.94418	0.116 s	β^+ /9.17	8.3/	0+			ann.rad./
				EC/					
^{63}Ga		62.9391	32. s	β^+ /5.5	4.5/				ann.rad./
				EC/					0.6271(2)/10.
									0.6370(2)/11.
									1.0652(4)/45.
^{64m}Ga			0.022 ms						0.0429
^{64}Ga		63.936838	2.63 m	β^+ /7.165	2.79/	0+			ann.rad./
					6.05/				0.80785(1)/14.
									0.99152(1)/43.
									1.38727(1)/12.
									3.3659(1)/13.
^{65}Ga		64.9394	15.2 m	β^+ /86/3.255	0.82/10.	3/2–			ann.rad./
				EC/	1.39/19.				0.1151(2)/55.
					2.113/56.				0.1530(2)/96.
					2.237/15.				0.2069(2)/39.
									(0.06–2.4)
^{66}Ga		65.931592	9.5 h	β^+ /56/5.175	0.74/1.	0+			ann.rad./
				EC/43/	1.84/54.				1.03935(8)/38.
					4.153/51.				2.7523(1)/23.
									(0.28–5.01)
^{67}Ga		66.928205	3.260 d	EC/1.001		3/2–	+1.8507	0.20	0.09332/37.
									0.18459/20.
									0.30024/17.
									(0.091–0.89)
^{68}Ga		67.927983	1.130 h	β^+ /90/2.921	1.83/	1+	0.01175	0.028	ann.rad./

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				EC/10/					1.0774(1)/3.
									(0.57–2.33)/
^{69}Ga	60.108(9)	68.925581				3/2–	+2.01659	+0.17	
^{70}Ga		69.926027	21.1 m	EC/0.2/0.655		1+			0.1755(5)/0.15
				β^- /99.8/1.656	1.65/99.				1.042(5)/0.48
^{71}Ga	39.892(9)	70.924707	>2.4 × 10^{26} y	β^-		3/2–	+2.56227	+0.11	
^{72}Ga		71.926372	14.10 h	β^- /4.001	0.64/40.	3–	–0.13224	+0.5	0.834
					1.51/9.				2.202
					2.52/8.				0.630
					3.15/11.				(0.113–3.678)
^{73}Ga		72.92517	74.87 h	β^- /1.59		3/2–			0.05344(5)/10.
									0.29732(5)/47.
									(0.01–1.00)/
^{74m}Ga			10. s	I.T./		1+			0.0565(1)/75.
^{74}Ga		73.92694	8.1 m	β^- /5.4	2.6/	3–			0.5959/92.
									2.354/45.
									(0.23–3.99)
^{75}Ga		74.92650	2.10 m	β^- /3.39	3.3/	3/2–			0.2529/
									0.5746/
									(0.12–2.10)
^{76}Ga		75.9289	29. s	β^- /7.0		3–			0.5629/66.
									0.5455/26.
									(0.34–4.25)
^{77}Ga		76.9293	13.0 s	β^- /5.3	5.2/				0.469/
									0.459/
^{78}Ga		77.9317	5.09 s	β^- /8.2		3+			0.619/77.
									1.187/20.
^{79}Ga		78.9329	2.85 s	β^- /7.0	4.6/				0.465/
^{80}Ga		79.9366	1.68 s	β^- /10.4	10./				0.659/
^{81}Ga		80.9377	1.22 s	β^- /8.3	5.1/				0.217/
^{82}Ga		81.9432	0.599 s	β^- /12.6					1.348/
^{83}Ga		82.9469	0.308 s	β^- /≈ 11.5					
^{84}Ga		83.952	≈0.085 s	β^- /14					
^{85}Ga			>0.15 μs						
^{86}Ga			>0.15 μs						
$_{32}$Ge		**72.64(1)**							
^{58}Ge		57.9910							
^{59}Ge		58.9817							
^{60}Ge		59.9702							
^{61}Ge		60.9638	0.04 s	β^+ /13.6					
^{62}Ge		61.9547	0.13 s						
^{63}Ge		62.9496	0.15 s	β^- /9.8					
^{64}Ge		63.9416	1.06 m	β^+ /4.4	3.0/	0+			ann.rad./
				EC/					0.1282(2)/11.
				β^+, p					0.4270(3)/37.
									0.6671(3)/17.
^{65}Ge		64.9394	31. s	β^+ /6.2	0.82/10.				ann.rad./
				EC/	1.39/19.				0.0620/27.
				EC, p	2.113/56.				0.6497/33.
					2.237/15.				0.8091/21.
				β^+, p	//0.011				(0.19–3.28)
^{66}Ge		65.93385	2.26 h	β^+ /27/2.10		0+			ann.rad./
				EC/73/					0.0438/29.
									0.3819/28.
									(0.022–1.77)
^{67}Ge		66.932738	19.0 m	β^+ /96/4.225	1.6/	1/2–			ann.rad./
				EC/4/	2.3/				0.1670/84.
					3.15/				(0.25–3.73)
^{68}Ge		67.92810	270.8 d	EC/0.11		0+			Ga k x-ray/39.
^{69}Ge		68.927973	1.63 d	β^+ /36/2.2273	0.70/	5/2–	0.735	0.02	ann.rad./
				EC/64/	1.2/				0.574/13.
									1.1068/36.
									(0.2–2.04)
^{70}Ge	20.370(89)	69.924250				0+			
^{71m}Ge			20.4 ms		I.T./0.0234	9/2+			0.1749
^{71}Ge		70.924954	11.2 d	EC/0.229		1/2–	+0.547		

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{72}Ge	27.380(60)	71.922076				0+			
^{73}Ge	7.759(78)	72.923460	$>1.8 \times 10^{23}$ y	β^-		9/2+	–0.879467	–0.17	
^{74}Ge	36.656(80)	73.921178				0+			
^{75m}Ge			48. s	I.T./		7/2+			0.13968(3)/39.
^{75}Ge		74.922860	1.380 h	β^- /1.177	1.19/	1/2–	+0.510		0.26461(5)/11.
									0.41931(5)/0.2
^{76}Ge	7.835(81)	75.921403	1.6×10^{21} y	$\beta^-\beta^-$		0+			
^{77m}Ge			53. s	I.T./20/		1/2–			1.605/0.22
				β^- /80/2.861	2.9/				1.676/0.16
									0.195–1.482
^{77}Ge		76.923549	11.25 h	β^- /2.702	0.71/23.	7/2+			0.2110/29.
					1.38/35.				0.2155/27.
					2.19/42.				0.2644/51.
									(0.15–2.35)
^{78}Ge		77.922853	1.45 h	β^- /0.95	0.70/	0+			0.2773(5)/96.
									0.2939(5)/4.
^{79m}Ge			39. s	β^- /IT		7/2+			
^{79}Ge		78.9254	19.1 s	β^- /4.2	4.0/20.	1/2–			0.1096/21.
					4.3/80.				(0.10–2.59)
									0.5427(4)/15.
^{80}Ge		79.92545	29.5 s	β^- /2.67	2.4/	0+			0.1104(4)/6.
									0.2656(4)/25.
^{81m}Ge			≈7.6 s	β^- /	3.75/	1/2+			0.3362(4)/
									0.7935(4)/
^{81}Ge		80.9288	≈7.6 s	β^- /6.2	3.44/	9/2+			0.1976(4)/21.
									0.3362(4)/100.
^{82}Ge		81.9296	4.6 s	β^- /4.7		0+			1.093/
^{83}Ge		82.9345	1.9 s	β^- /8.9					
^{84}Ge		83.9373	0.98 s	β^- /7.7					
^{85}Ge		84.943	0.54 s	β^- /10.					
^{86}Ge		85.946	>0.15 μs						
^{87}Ge			>0.15 μs						
^{88}Ge			>0.15 μs						
^{89}Ge			>0.15 μs						
$_{33}$As		**74.92160(2)**							
^{60}As		59.993							
^{61}As		60.981							
^{62}As		61.9732							
^{63}As		62.9637							
^{64}As		63.9576	0.02 s						
^{65}As		64.9495	0.13 s	β^+ /9.4					
^{66m2}As			1.9 μs						
^{66m1}As			0.018 ms						
^{66}As		65.94410	95.8 ms	β^+ /9.55					
^{67}As		66.9392	42. s	β^+ /6.0	5.0/	5/2–			0.121/
				EC/					0.123/
									0.244/
^{68}As		67.9368	2.53 m	β^+ /8.1		3+			ann.rad./
									0.652/32.
									0.762/33.
									1.016/77.
									(0.61–3.55)
^{69}As		68.93228	15.2 m	β^+ /98/4.01	2.95/	5/2–	1.6		ann.rad./
				EC/2/					0.0868(5)/1.5
									0.1458(3)/2.4
^{70}As		69.93093	52.6 m	β^+ /84/6.22	1.44/	4+	+2.1061	+0.09	ann.rad./
				EC/16/2.14					1.0395(7)/82.
				/2.89					(0.17–4.4)/
^{71}As		70.927114	2.72 d	β^+ /32/2.013		5/2–	+1.6735	–0.02	ann.rad./
				EC/68/					0.1749(2)/84.
									1.0957(2)/4.2
^{72}As		71.926753	26.0 h	β^+ /77/4.356	0.669/5.	2–	–2.1566	–0.08	ann.rad./
					1.884/12.				0.83395(5)/80.
					2.498/62.				1.0507(1)/9.6
					3.339/19.				(0.1–4.0)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{73}As		72.923825	80.3 d	EC/0.341		3/2–			0.0133/0.1
									0.0534/10.5
									Se k x-ray/90.
^{74}As		73.923829	17.78 d	β^+ /31/2.562	0.94/26.	2–	–1.597		ann.rad./
				EC/37/	1.53/3.				0.59588(1)/60.
				β^- /1.353	0.71/16.				0.6084(1)/0.6
					1.35/16.				0.6348(1)/15.
^{75m}As			0.017 s						
^{75}As	100.	74.921597				3/2–	+1.43947	+0.31	
^{76}As		75.922394	26.3 h	β^- /2.962	0.54/3.	2–	–0.903		0.5591(1)/45.
					1.785/8.				0.65703(5)/6.2
					2.410/36.				1.21602(1)/3.4
					2.97/51.				(0.3–2.67)
^{77}As		76.920648	38.8 h	β^- /0.683	0.70/98.	3/2–	+1.295		0.2391(2)/1.6
									0.2500(3)/0.4
									0.5208/0.43
^{78}As		77.92183	1.512 h	β^- /4.21	3.00/12.	2–			0.6136(3)/54.
					3.70/17.				0.6954(3)/18.
					4.42/37.				1.3088(3)/10.
^{79m}As			1.21 μs			9/2+			0.542/IT
									0.231
^{79}As		78.92095	9.0 m	β^- /2.28	1.80/95.	3/2–			0.0955(5)/16.
									0.3645(5)/1.9
^{80}As		79.92258	16. s	β^- /5.64	3.38/	1+			0.6662(2)/42.
									(2.5–3.0)
^{81}As		80.92213	33. s	β^- /3.856		3/2–			0.4676(2)/20.
									0.4911(2)/8.
^{82m}As			13.7 s	β^- /	3.6/	5–			0.6544(1)/72.
									0.8186(4)/27.
									1.7313(2)/27.
									1.8954(2)/38.
^{82}As		81.9246	19. s	β^- /7.4	7.2/80.	1+			0.6544(1)/15.
^{83}As		82.9250	13.4 s	β^- /5.5					0.7345/100.
									1.1131/34.
									2.0767/28.
^{84m}As			0.6 s	β^-					
^{84}As		83.9291	4. s	β^-, n/7.2		1–			0.6671(2)/21.
									1.4439(5)/49.
									(0.325–5.150)
^{85}As		84.9318	2.03 s	β^-, n/8.9		3/2–			0.667(1)/42.
									1.4551(2)/100.
^{86}As		85.9362	0.95 s	β^-, n/11.4					0.704/
^{87}As		86.9396	0.49 s	β^-, n/10.					0.704/
^{88}As		87.945	>0.15 μs						
^{89}As		88.949	>0.15 μs						
^{90}As			>0.15 μs						
^{91}As			>0.15 μs						
^{92}As			>0.15 μs						
$_{34}$Se		**78.96(3)**							
^{65}Se		64.965	0.011 s	β^+ /60/14.					
				β^+, p	3.55/				
^{66}Se		65.9552	0.03 s						
^{67}Se		66.9501	0.13 s	β^+ /10.2					ann.rad./
				β^+, (p)/					0.352
^{68}Se		67.9419	36. s	β^+ /4.7					ann.rad./
									(0.050–0.426)
^{69}Se		68.93956	27.4 s	β^+ /6.78	5.006/				ann.rad./
				EC/					0.0664(4)/27.
				β^+, p	//≈0.045				0.0982(4)/63.
^{70}Se		69.9335	41.1 m	β^+ /2.4		0+			ann.rad
									0.04951(5)/35.
									0.4262(2)/29.
^{71}Se		70.9319	4.7 m	β^+ /4.4	3.4/36.	5/2–			ann.rad
				EC/					0.1472(3)/47.
									0.8309(3)/13.

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									1.0960(3)/10.
^{72}Se		71.92711	8.5 d	EC/0.34		0+			0.0460(2)/57.
^{73m}Se			40. m	I.T./73/0.0257	0.85	3/2–			ann.rad.
				β^+ /27/2.77	1.45/				0.0257(2)/27.
					1.70/				0.2538(1)/2.5
^{73}Se		72.92678	7.1 h	β^+ /65/2.74	0.80/	9/2+	0.86		ann.rad
				EC/35/	1.32/95.				0.0670(1)/72.
					1.68/1.				0.3609(1)/97.
									(0.6–1.5)
^{74}Se	0.89(4)	73.922477				0+			
^{75}Se		74.922524	119.78 d	EC/0.864		5/2+	0.67	1.0	0.13600/55
									0.26465/58
									(0.024–0.821)
^{76}Se	9.37(29)	75.919214				0+			
^{77m}Se			17.4 s	I.T./		7/2+			0.1619(2)/52.
^{77}Se	7.63(16)	76.919915				1/2–	+0.53506		
^{78}Se	23.77(28)	77.917310				0+			
^{79m}Se			3.92 m	I.T./					0.09573(3)/9.5
^{79}Se		78.918500	2.9×10^5 y	β^- /0.151		7/2+	–1.018	+0.8	
^{80}Se	49.61(41)	79.916522				0+			
^{81m}Se			57.3 m	I.T./99/0.1031		7/2+			0.1031(3)/9.7
									0.2602(2)/0.06
									0.2760/0.06
^{81}Se		80.917993	18.5 m	β^- /1.585	1.6/98.	1/2–			0.2759/0.85
									0.2901/0.75
									0.8283/0.32
^{82}Se	8.73(22)	81.916700	$\approx 1 \times 10^{20}$ y	$\beta^-\beta^-$		0+			
^{83m}Se			1.17 m	β^- /3.96	2.88/	1/2–			0.35666(6)/17.
					3.92/				0.9879(1)/15.
									1.0305(1)/21.
									2.0514(2)/11.
									(0.19–3.1)
^{83}Se		82.919119	22.3 m	β^- /3.668	0.93/	9/2+			0.22516(6)/33.
					1.51/				0.35666(6)/69.
									0.51004(8)/45.
									(0.21–2.42)
^{84}Se		83.91847	3.3 m	β^- /1.83	1.41/100.	0+			0.4088(5)/100.
^{85}Se		84.92225	32. s	β^- /6.18	5.9/	5/2+			0.3450(1)/22.
									0.6094(1)/41.
^{86}Se		85.92428	15. s	β^- /5.10		5/2+			2.0124(1)/24.
									2.4433(8)/100.
									2.6619(1)/49.
^{87}Se		86.92853	5.4 s	β^- /7.28					0.468(1)/100.
				n/					1.4979(1)/23.
^{88}Se		87.93143	1.5 s	β^-, n/6.85					0.5346/
^{89}Se		88.9360	0.41 s	β^-, n/9.0					
^{90}Se		89.9394	>0.15 μs						
^{91}Se		90.945	0.27 s	β^-, n/8.					
^{92}Se		91.949	>0.15 μs						
^{93}Se			>0.15 μs						
^{94}Se			>0.15 μs						
$_{35}$Br		**79.904(1)**							
^{67}Br		66.9648							
^{68}Br		67.958	<1.2 μs						
^{69}Br		68.9502	<0.024 μs	β^+ /9.6					
^{70m}Br			2.2 s			9+			
^{70}Br		69.9446	79. ms	β^+ /10.0	/0.75				
^{71}Br		70.9392	21. s	β^+ /6.9					
^{72}Br		71.9365	1.31 m	β^+ /8.7		3	≈0.55		0.4547–1.3167
^{73}Br		72.9318	3.4 m	β^+ /4.7	3.7/	3/2–			ann.rad
									0.065–0.700
^{74m}Br			46. m	β^+ /	4.5/	4–	1.82		ann.rad
									0.6348
									0.7285
									(0.2–4.38)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{74}Br		73.92989	25.4 m	β^+ /6.91					ann.rad
									0.6341
									0.6348
									(0.2–4.7)
^{75}Br		74.92578	1.62	β^+ /76/3.03		3/2–	+0.75		ann.rad
									0.28650
									(0.1–1.56)
^{76m}Br			1.4 s	I.T./5.05		4+			0.104548
									0.05711
^{76}Br		75.92454	16.0 h	β^+ /57/4.96	1.9/	1–	0.54821	0.270	ann.rad
					3.68/				0.55911
									1.85368
									(0.4–4.6)
^{77m}Br			4.3 m	I.T./0.1059		9/2+			0.1059
^{77}Br		76.921380	2.376 d	EC/99/1.365		3/2–	0.973	+0.53	ann.rad.
									0.23898
									0.52069
									(0.08–1.2)
^{78}Br		77.921146	6.45 m	β^+ /92/3.574	1.2/	1+	0.13		ann.rad.
				EC/8/	2.5/				0.61363
									(0.7–3.0)
^{79m}Br			4.86 s	I.T./0.207		9/2+			0.2072
^{79}Br	50.69(7)	78.918338				3/2–	+2.106400	+0.331	
^{80m}Br			4.42 h	I.T./0.04885		5–	+1.3177	+0.75	Br k x-ray
									0.03705/39.1
									0.04885/0.3
^{80}Br		79.918530	17.66 m	β^- /92/2.004	1.38 β^-/7.6	1+	0.5140	0.196	ann.rad.
				EC/5.7/1.8706	1.99 β^-/82				0.6169/6.7
				β^+ /2.6/	0.85 β^+ /2.8				(0.64–1.45)
^{81}Br	49.31(7)	80.916291				3/2–	+2.270562	+0.276	
^{82m}Br			6.1 m	I.T./98/0.046		2–			0.046/0.24
				β^- /2 /3.139					(0.62–2.66)
^{82}Br		81.916805	1.471 d	β^- /3.093	0.444/	5–	+1.6270	0.751	0.5544/71
									0.61905/43
									0.77649/84
									(0.013–1.96)
^{83}Br		82.915181	2.40 h	β^- /0.972	0.395/1	3/2–			0.52964
					0.925/99				(0.12–0.68)
^{84m}Br			6.0 m	β^- /4.97	2.2/100	(6–)			0.4240/100
									0.8817/98
									1.4637/101
^{84}Br		83.91651	31.8 m	β^- /4.65	2.70/11	2–	2.		0.8816/41
					3.81/20				1.8976/13
					4.63/34				(0.23–4.12)
^{85}Br		84.91561	2.87 m	β^- /2.87	2.57	3/2–			0.80241/2.56
									0.92463/1.6
									(0.09–2.4)
^{86}Br		85.91880	55.5 s	β^- /7.63	3.3	(2–)			1.56460/64
					7.4				2.75106/21
									(0.5–6.8)
^{87}Br		86.92072	55.6 s	β^- /6.85	6.1/	3/2–			1.41983
				n/					1.4762
									(0.2–6.1)
^{88m}Br			5.1 μs						
^{88}Br		87.92407	16.3 s	β^- /8.96		1–			0.7649
				n/					0.7753
									0.8021
									(0.1–6.99)
^{89}Br		88.92640	4.35 s	β^- /8.16		3/2–			0.7753
				n/					1.0978
^{90}Br		89.9306	1.91 s	β^- /10.4	8.3/	2–			0.6555
				n/	9.8/				0.7071
									1.3626
^{91}Br		90.9339	0.54 s	β^- /90 /9.80					0.263
				β^- n/10 /					0.803
^{92}Br		91.9392	0.31 s	β^- /12.20					0.740
				β^- n/					

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{93}Br		92.9431	0.10 s	β^- /11					0.117
				β^- n	//11				(0.237–3.606)
^{94}Br		93.9487	0.07 s	β^- n/					
^{95}Br			>0.15 μs						
^{96}Br			>0.15 μs						
^{97}Br			>0.15 μs						
$_{36}$Kr		**83.80(1)**							
^{69}Kr		68.9653	0.03 s	β^+, (p)	4.07/				
^{70}Kr		69.9560	0.06 s						
^{71}Kr		70.9505	100. ms	β^+, EC/10.1					(0.198–0.207)
^{72}Kr		71.9419	17. s	β^+ /5.0		0+			ann.rad
				EC/					0.3100/29
									0.4150/36
									(0.12–0.58)
^{73}Kr		72.9389	28. s	β^+ /6.7		5/2–			ann.rad.
				EC/					0.1781/66
				β^+, p/	/0.25				(0.06–0.86)
^{74}Kr		73.9333	11.5 m	β^+ /3.1		0+			ann.rad.
				EC/					0.08970/31
									0.2030/20
									(0.010–1.06)
^{75}Kr		74.93104	4.3 m	β^+ /4.90	3.2/	5/2+	–0.531	+1.1	ann.rad.
				EC/					0.1325/68
									0.1547/21
									(0.02–1.7)
^{76}Kr		75.92595	14.8 h	EC/1.31		0+			Br k x-ray
									0.270/21
									0.3158/39
									(0.03–1.07)
^{77}Kr		76.92467	1.24 h	β^+ /80/3.06		5/2+	–0.583	+0.9	ann.rad.
				EC/20/	1.55/				0.1297/80
					1.70/				0.1465/38
					1.87/				(0.02–2.3)
^{78}Kr	0.355(3)	77.92039	>2.3 × 10^{20} y	EC-EC		0+			
^{79m}Kr			53. s	I.T./0.1299		7/2+	–0.786	+0.40	Kr x-ray
^{79}Kr		78.920083	1.455 d	β^+ /7 /1.626		1/2–	+0.536		ann.rad.
				EC/93 /					0.2613/13
									0.39756/19
									0.6061/8
									(0.04–1.3)
^{80}Kr	2.286(10)	79.916379				0+			
^{81m}Kr			13.1 s	I.T./0.1904		1/2–	+0.586		0.1904
^{81}Kr		80.916593	2.1 × 10^5 y	EC/0.2807		7/2+	–0.908	+0.63	Br k x-ray
									0.2760
^{82}Kr	11.593(3)	81.913485				0+			
^{83m}Kr			1.86 h	I.T./0.0416		1/2–	+0.591		Kr k x-ray
									0.00940
									0.03216
^{83}Kr	11.500(19)	82.914137				9/2+	–0.970699	+0.259	
^{84}Kr	56.987(15)	83.911508				0+			
^{85m}Kr			4.48 h	β^- /79 /	0.83/79	1/2–	+ 0.633		0.30487
				I.T./21 /0.305					0.15118
^{85}Kr		84.912530	10.73 y	β^- /0.687	0.15/0.4	9/2+	1.005	+0.43	0.51399
^{86}Kr	17.279(41)	85.910615				0+			
^{87}Kr		86.913359	1.27 h	β^- /3.887	1.33/8	5/2+	–1.023	–0.30	0.40258/49.6
					3.49/43				2.5548/9.2
					3.89/30				(0.13–3.31)
^{88}Kr		87.91445	2.84 h	β^- /2.91		0+			0.19632/26.
									2.392/34.6
									(0.03–2.8)
^{89}Kr		88.91764	3.15 m	β^- /4.99	3.8/	5/2+	–0.330	+0.16	0.19746
					4.6/				0.2209/19.9
					4.9/				0.5858/16.4
									1.4728/6.8
									(0.2–4.7)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{90}Kr		89.91953	32.3 s	β^- /4.39	2.6/77	0+			0.12182/32.9
					2.8/6				0.5395/28.6
									1.1187/36.2
									(0.1–4.2)
^{91}Kr		90.9234	8.6 s	β^- /6.4	4.33/	5/2+	–0.583	+0.30	0.10878/43.5
					4.59/				0.50658/19.
									(0.2–4.4)
^{92}Kr		91.92611	1.84 s	β^- /5.99					0.1424/66.
				n/					(0.14–3.7)
^{93}Kr		92.9312	1.29 s	β^- /8.6	7.1/	1/2+	–0.413		0.1820
				n/					0.2534/42.
									0.32309/24.6
									(0.057–4.03)
^{94}Kr		93.9343	0.21 s	β^- /7.3					0.2196/67
									0.6293/100.
									(0.098–0.985)
^{95}Kr		94.9397	0.78 s	β^- /9.7			–0.410		
^{96}Kr		95.9431	>50 ms						
^{97}Kr		96.9486	<0.1 s	β^-					
^{98}Kr			>0.15 μs						
^{99}Kr			>0.15 μs						
^{100}Kr			>0.15 μs						
$_{37}$Rb		**85.4678(3)**							
^{71}Rb		70.9653							
^{72}Rb		71.9591	<1.2 μs						
^{73}Rb		72.9504	<0.03 μs						
^{74}Rb		73.9445	64.8 ms	β^+ /10.4					
^{75}Rb		74.93857	19. s	β^+ /7.02	2.31/				ann. rad.
									0.179
^{76}Rb		75.93508	39. s	β^+ /8.50	4.7/	1–	–0.372623	+0.4	ann. rad.
									0.4240/92.
									(0.064–1.68)
^{77}Rb		76.93041	3.8 m	β^+ /5.34	3.86/	3/2–	+0.654468	+0.70	ann. rad.
									0.0665/59
									(0.04–2.82)
^{78m}Rb			5.7 m	I.T./0.1034		4–	+2.549	+0.81	ann. rad.
				β^+ /	3.4				0.4553/81.
				EC/					(0.103–4.01)
^{78}Rb		77.92814	17.7 m	β^+ /7.22		0+			ann. rad.
				EC/					0.4553/63.
									(0.42–5.57)
^{79}Rb		78.92400	23. m	β^+ /84/3.65		5/2+	+0.3358	–0.10	ann.rad.
				EC/16 /					0.68812/23.
									(0.017–3.02)
^{80}Rb		79.92252	34. s	β^+ /5.72	4.1/22	1+	–0.0836	+0.35	ann.rad.
					4.7/74				0.6167/25.
^{81m}Rb			30.5 m	I.T./0.85	1.4	9/2+	+5.598	–0.74	ann.rad.
				β^+, EC/					(0.085–1.9)
^{81}Rb		80.91900	4.57 h	β^+ /27/2.24	1.05/	3/2–	+2.060	+0.40	ann.rad./
				EC/73					0.19030/64.
									(0.05–1.9)
^{82m}Rb			6.47 h	β^+/26/	0.80/	5–	+1.5100	+1.0	ann.rad./
				EC/74/					0.5544/63.
									0.7765/85.
									(0.092–2.3)
^{82}Rb		81.91821	1.258 m	β^+/96/4.40	3.3/	1+	+0.554508	+0.19	ann.rad./
				EC/4/					0.7665/13.
									(0.47–3.96)
^{83}Rb		82.91511	86.2 d	EC/0.91		5/2–	+1.425	+0.20	Kr x-ray
									0.5205/46.
									(0.03–0.80)
^{84m}Rb			20.3 m	I.T./0.216		6–	+0.2129	+0.6	0.2163/34.
									0.2482/63.
									0.4645/32.

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{84}Rb		83.914387	32.9 d	β^+/22/2.681	0.780/11	2–	–1.32412	–0.015	ann.rad./
				EC/75 /	1.658/11				0.8817/68.
				β^-/3/0.894	0.893/				(1.02–1.9)
^{85}Rb	72.17(2)	84.911792				5/2–	+1.353	+0.23	
^{86m}Rb			1.018 m	I.T./0.5560		6–	+1.815	+0.37	0.556/98.
^{86}Rb		85.911170	18.65 d	β^-/1.775	1.774/8.8	2–	–1.6920	+0.19	1.0768/8.8
^{87}Rb	27.83(2)	86.909186	4.88×10^{10} y	β^-/0.283	0.273/100	3/2–	+2.7512	+0.13	
^{88}Rb		87.911323	17.7 m	β^-/5.316	5.31	2–	0.508		0.8980/14.
									1.8360/21.
									(0.34–4.85)
^{89}Rb		88.91229	15.4 m	β^-/4.50	1.26/38	3/2–	+2.304	+0.14	1.032/58.
					1.9/5				1.248/42.
					2.2/34				2.1960/13
					4.49/18				(0.12–4.09)
^{90m}Rb			4.3 m	β^-/4.50	1.7/	4–	+1.616	+0.20	0.1069(IT)
					6.5/				0.8317/94
									(0.20–5.00)
^{90}Rb		89.91481	2.6 m	β^-/6.59	6.6	1–			0.8317/28.
									(0.31–5.60)
^{91}Rb		90.91649	58.0 s	β^-/5.861	5.9	3/2–	+2.182	+0.15	0.0936/34.
									(0.35–4.70)
^{92}Rb		91.91968	4.48 s	β^-/8.11	8.1/94	1–			0.8148/8.
									(0.1–6.1)
^{93}Rb		92.92195	5.85 s	β^-/7.46	7.4/	5/2	+1.410	+0.18	0.2134/4.8
				n/1					0.4326/12.5
									0.9861/4.9
									(0.16–5.41)
^{94}Rb		93.92643	2.71 s	β^-/10.31	9.5/	3	+1.498	+0.16	0.8369/87.
				n/10					1.5775/32.
									(0.12–6.35)
^{95}Rb		94.92929	0.377 s	β^-/9.30	8.6/	5/2	+1.334	+0.21	0.352/65.
				n/8					0.680/22.
									(0.20–2.27)
^{96m}Rb			1.7 μs						0.2999
									0.4612
									0.2400
									0.093–0.369
^{96}Rb		95.93427	0.199 s	β^-/11.76	10.8/	2+	+1.466	+0.25	0.815/76.
				n/13/					(0.20–5.42)
^{97}Rb		96.93733	0.169 s	β^-/10.42	10.0	3/2	+1.841	+0.58	0.167/100.
				n/27/					0.585/79.
									0.599/56.
									1.258/52.
									(0.14–2.08)
^{98}Rb		97.94174	0.107 s	β^-/12.34	0.144/				
				n/13					(0.07–3.68)
^{99}Rb		98.9453	59. ms	β^-/11.3					
^{100}Rb		99.9499	53. ms	β^- /13.5					0.129
									(0.058–4.483)
^{101}Rb		100.9532	0.03 s	β^- /11.8					
^{102}Rb		101.9592	0.09 s	β^-					
$_{38}$Sr		**87.62(1)**							
^{73}Sr		72.966	>25 ms						
^{74}Sr		73.9563	>1.2 μs						
^{75}Sr		74.9499	≈0.08 s						
^{76}Sr		75.9416	8.9 s	β^+ /6.1					
^{77}Sr		76.9378	9.0 s	β^+ /6.9	5.6		–0.35	+1.4	0.147
				β^+, p	//0.08				
^{78}Sr		77.93218	2.7 m	β^+ /3.76					(0.047–0.793)
^{79}Sr		78.92971	2.1 m	β^+ /5.32	4.1	3/2–	–0.474	+0.74	ann.rad./
									0.039/28.
									0.105/22.
									(0.135–0.612)
^{80}Sr		79.92453	1.77 h	β^+ /1.87		0+			ann.rad./
									0.174/10.

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.589/39.
									(0.24–0.55)
^{81}Sr		80.92322	22.3 m	β^+ /87/3.93	2.43/	1/2–	+0.544		ann.rad./
				EC/13/	2.68/				0.148/31.
									0.1534/35
									(0.06–1.7)
^{82}Sr		81.91840	25.36 d	EC/0.18					Rb x-ray
^{83m}Sr			5.0 s	I.T./0.2591		1/2–	+0.582		0.2591/87.5
^{83}Sr		82.91756	1.350 d	β^+/24/2.28	0.465/	7/2+	–0.898	+0.79	ann.rad./
				EC/76/	0.803/				0.3816/12.
					1.227/				0.3816
									0.7627/30.
									(0.094–2.15)
^{84}Sr	0.56(1)	83.913426				0+			
^{85m}Sr			1.127 h	I.T./87/0.2387		1/2–	+0.601		0.2318/84.
				EC/13					(0.15–0.24)
^{85}Sr		84.912936	64.85 d	EC/1.065		9/2+	–1.001	+0.30	0.51399/99.3
^{86}Sr	9.86(1)	85.909265				0+			
^{87m}Sr			2.81 h	I.T./0.3884		1/2–	+0.63		0.3884(IT)
^{87}Sr	7.00(1)	86.908882				9/2+	–1.093	+0.34	
^{88}Sr	82.58(1)	87.905617				0+			
^{89}Sr		88.907455	50.52 d	β^-/1.497	1.492/100	5/2+	–1.149	–0.3	0.9092
^{90}Sr		89.907738	29.1 y	β^-/0.546	0.546/100	0+			
^{91}Sr		90.91020	9.5 h	β^-/2.70	0.61/7	5/2+	–0.887	+0.044	0.5556/61.
					1.09/33				0.7498/24.
					1.36/29				1.0243/33.
					2.66/26				(0.12–2.4)
^{92}Sr		91.91098	2.71 h	β^-/1.91	0.55/96	0+			1.3831/90.
					1.5/3				(0.24–1.1)
^{93}Sr		92.91394	7.4 m	β^-/4.08	2.2/10	5/2+	–0.794	+0.26	0.5903/
					2.6/25				0.7104
					3.2/65				0.87573
									0.8883/
									(0.17–3.97)
^{94}Sr		93.91537	1.25 m	β^-/3.511	2.1/	0+			0.6219
					3.3/				0.7043
									0.7241
									0.8064
									1.4283
^{95}Sr		94.91931	25.1 s	β^-/6.08		1/2+	–0.5379		0.6859
					6.1/50				0.8269
									2.7173
									2.9332
^{96}Sr		95.92165	1.06 s	β^-/5.37	4.2/	0+			0.1222
									0.5305
									0.8094
									0.9318
^{97}Sr		96.92615	0.42 s	β^-/7.47	5.3	(1/2+)	–0.500		0.2164
									0.3071
									0.6522
									0.9538
									1.2580
									1.9050
^{98}Sr		97.92845	0.65 s	β^-/5.83	5.1				0.0365
									0.1190
									0.4286
									0.4447
									0.5636
^{99}Sr		98.9333	0.27 s	β^-/8.0			–0.26	0.8	
^{100}Sr		99.9354	0.201 s	β^-/7.1					
^{101}Sr		100.9405	0.115 s	β^-/9.5					
^{102}Sr		101.9430	68. ms	β^-/8.8					
^{103}Sr		102.9490	>0.15 μs						
^{104}Sr		103.952	>0.15 μs						
^{105}Sr			>0.15 μs						
^{39}Y		**88.90585(2)**							

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{76}Y			> 0.2 μs						
^{77}Y		76.9496	≈ 57. ms						
^{78m}Y			5.8 s			(5+)			
^{78}Y		77.9435	53 ms	β+/10.5					0.279/100
									0.504/90
									0.713/40
^{79}Y		78.9374	15. s	β+/7.1					(0.152–1.106)
^{80m}Y			4.8 s						0.2285
^{80}Y		79.9320	30. s	β+/7.0	5.5	(4)			ann.rad./
					5.0/				0.3858/100
									0.5951/42
									0.756–1.396
^{81}Y		80.9291	1.21 m	β+/5.5	3.7/				ann.rad./
					4.2/				0.428
									0.469
^{82}Y		81.9268	9.5 s	β+/7.8	6.3/	1+			ann.rad./
									0.5736
									0.6017
									0.7375
^{83m}Y			2.85 m	β+/95/4.6	2.9	1/2–			ann.rad./
				EC/5 /					0.2591
									0.4218
									0.4945
^{83}Y		82.92235	7.1 m	β+/4.47	3.3	9/2+			ann.rad./
				EC/					0.0355
									0.4899
									0.8821
									(0.03–3.4)
^{84m}Y			4.6 s	β+/		1+			ann.rad./
				EC/					0.7930
^{84}Y		83.9203	40. m	β+/6.4	1.64/47	5–			ann.rad./
				EC/	2.24/25				0.4628
					2.64/21				0.6606
					3.15/7				0.7931
									0.9744
									1.0398
									(0.2–3.3)
^{85m}Y			4.9 h	β+/70/		9/2+	6.2		ann.rad./
				EC/30/					0.2317
									0.5356
									2.1238
									(0.1–3.1)
									0.7673
^{85}Y		84.91643	2.6 h	β+/55/3.26	1.54/	1/2–			ann.rad./
				EC/45/					0.2317
									0.5045
									0.9140
									(0.07–1.4)
^{86m}Y			48. m	I.T./99/		8+	4.8		ann.rad./
				β+/					0.0102(IT)
				EC/					0.2080
									(0.09–1.1)
^{86}Y		85.91489	14.74 h	β+/5.24		4–	<0.6		ann.rad./
				EC/					0.3070
									0.6277
									1.0766
									1.1531
									1.9207
									(0.1–3.8)
^{87m}Y			13. h	I.T./98/		9/2+	6.1		0.3807
				β+/0.7/	1.15/0.7				
				EC/					
^{87}Y		86.910880	3.35 d	EC/99+/1.862	0.78/	1/2–			0.3880
									0.4870
^{88}Y		87.909506	106.6 d	EC/99+/3.623	0.76/	4–			ann.rad./
				β+/0.2/					0.89802

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									1.83601
									2.73404
									3.2190
^{89m}Y			15.7 s	I.T./0.909		9/2+			0.9092(IT)
^{89}Y	100.	88.905849				1/2–	–0.13742		
^{90m}Y			3.24 h	I.T./99+/	0.68204	7+	5.1		0.2025
				β⁻/0.002/					0.4794
									0.6820
^{90}Y		89.907152	2.67 d	β⁻/2.282	2.28/	2–	–1.630	–0.155	
^{91m}Y			49.7 m	I.T./0.555		9/2+	5.96		0.5556(IT)
^{91}Y		90.907301	58.5 d	β⁻/1.544	1.545/	1/2–	0.1641		1.208
^{92}Y		91.90893	3.54 h	β⁻/3.63	3.64/	2–			0.4485
									0.5611
									0.9345
									1.4054
									(0.4–3.3)
^{93m}Y			0.82 s	I.T./0.759		9/2+			0.1686(IT)
									0.5902
^{93}Y		92.90956	10.2 h	β⁻/2.87	2.88/90	1/2–			0.2669
									0.9471
									1.9178
^{94m}Y			1.4 μs						0.4322
									0.7699
									1.2024
^{94}Y		93.91160	18.7 m	β⁻/4.919	4.92/	2–			0.3816
									0.9188
									1.1389
									(0.3–4.1)
^{95}Y		94.91279	10.3 m	β⁻/4.42		1/2–			0.4324
									0.9542
									2.1760
									3.5770
^{96m}Y			9.6 s	β⁻/		(3+)			0.1467
									0.6174
									0.9150
									1.1071
									1.7507
^{96}Y		95.91588	6.2 s	β⁻ /7.09	7.12/	0–			1.594
^{97m}Y			1.21 s	β⁻ /7.4	4.8/	9/2+			0.1614
					6.0/				0.9700
									1.1030
^{97}Y		96.91813	3.76 s	β⁻ /6.69	6.7	1/2–			0.2969
									1.9960
									3.2876
									3.4013
^{98m}Y			2.1 s	β⁻ /9.8	5.5/	(4–)			0.2415
									0.6205
									0.6473
									1.2228
									1.8016
^{98}Y		97.92224	0.59 s	β⁻ /8.83	8.7/	1+			0.2131
									1.2228
									1.5907
									2.9413
									4.4501
^{99m}Y			0.011 ms						
^{99}Y		98.92463	1.47 s	β⁻ /7.57		1/2–			0.1218/43.8
				n	/2.5/				0.5362
									0.7242
									1.0130
^{100m}Y			0.94 s	β⁻, n /		3+			
^{100}Y		99.9278	0.73 s	β⁻, n/9.3	n/1.8/	1+			
^{101}Y		100.9303	0.43 s	β⁻, n/8.6	n/1.5/	(5/2)			
^{102}Y		101.9336	0.36 s	β⁻, n/9.9	n/4.0/				
^{103}Y		102.9369	0.23 s	β⁻, n	n/8.3/				
^{104}Y		103.9414	0.18 s						
^{105}Y		104.9451	>0.15 μs						

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{106}Y		105.950	>0.15 μs						
^{107}Y			>0.15 μs						
^{108}Y			>0.15 μs						
$_{40}$Zr		**91.224(2)**							
^{78}Zr			> 0.2 μs						
^{79}Zr		78.949	0.06 s						
^{80}Zr		79.9406	≈ 4.5 s	β^+ /8.0					0.290
									0.538
^{81}Zr		80.9368	5.3 s	β^+ /7.2	6.1	(3/2–)			
^{82}Zr		81.9311	32. s	β^+ /4.0	3.				ann.rad./
^{83m}Zr			7. s	β^+ /7.0		(7/2+)			ann.rad./
^{83}Zr		82.9287	44. s	β^+ /5.9	4.8	(1/2–)			ann.rad./
				EC					0.0556
									0.1050
									0.2560
									0.474
									1.525
^{84}Zr		83.9233	26. m	β^+ /2.7		0+			ann.rad./
				EC/					0.0449
									0.1125
									0.3729
									0.667
^{85m}Zr			10.9 s	I.T./0.2922		1/2–			ann.rad./
				β^+, EC/					0.2922(IT)
									0.4165
^{85}Zr		84.9215	7.9 m	β^+ /4.7	3.1	7/2+			ann.rad./
				EC/					0.2663
									0.4163
									0.4543
^{86}Zr		85.91647	16.5 h	EC/1.47		0+			0.0280
									0.243
									0.612
^{87m}Zr			14.0 s	I.T./0.3362		1/2–			0.1352(IT)
									0.2010
^{87}Zr		86.91482	1.73 h	β^+ /3.67	2.26	9/2+			ann.rad./
				EC/					0.3811
									1.228
^{88}Zr		87.91023	83.4 d	EC/0.67		0+			0.3929
^{89m}Zr			4.18 m	I.T./94/0.5877		1/2–			ann.rad./
				β^+ /1.5/					0.5877(IT)
				EC/4.7/					1.507
^{89}Zr		88.908889	3.27 d	β^+ /23/2.832	0.9/	9/2+	–1.07		ann.rad./
				EC/77/					0.9092
^{90m}Zr			0.809 s	I.T./		5–	6.3		0.1326
									2.1862
									2.3189(IT)
^{90}Zr	51.45(40)	89.904702				0+			
^{91}Zr	11.22(5)	90.905643				5/2+	–1.30362	–0.21	
^{92}Zr	17.15(8)	91.905039				0+			
^{93}Zr		92.906474	1.5×10^6 y	β^- /0.091		5/2+			0.0304
^{94}Zr	17.38(28)	93.906314	$>10^{17}$ y	$\beta^-\beta^-$		0+			
^{95}Zr		94.908041	64.02 d	β^- /1.125	0.366/55	5/2+	1.13	+0.29	0.7242
					0.400/44				0.7567
^{96}Zr	2.80(9)	95.908275	3×10^{19} y	$\beta^-\beta^-$		0+			
			$>1.7 \times 10^{18}$ y	β^-					
^{97}Zr		96.910950	16.8 h	β^- /2.658	1.91/	1/2–			0.7434
^{98}Zr		97.91276	30.7 s	β^- /2.26	2.2/100	0+			
^{99}Zr		98.91651	2.2 s	β^- /4.56	3.9/	1/2+			0.4692/55.2
					3.5/				0.5459/48
									0.028–1.321
^{100}Zr		99.91776	7.1 s	β^- /3.34		0+			0.4006
									0.5043
^{101}Zr		100.92114	2.1 s	β^- /5.49	6.2/	3/2–			0.1194
									0.2057
									0.2089

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{102}Zr		101.92298	2.9 s	β^- /4.61					
^{103}Zr		102.9266	1.3 s	β^- /7.0					
^{104}Zr		103.9288	1.2 s	β^- /5.9					
^{105}Zr		104.9331	≈1. s	β^- /8.5					
^{106}Zr		105.9359	>0.24 μs						
^{107}Zr		106.941	>0.24 μs						
^{108}Zr		107.944	>0.15 μs						
^{109}Zr			>0.15 μs						
^{110}Zr			>0.15 μs						
$_{41}$Nb		**92.90638(2)**							
^{81}Nb		80.949	<0.08 μs						
^{82}Nb		81.9431	50 ms	β^+ /11.					
^{83}Nb		82.9367	4.1 s	β^+ /7.5					
^{84}Nb		83.9336	12. s	β^+, EC/9.6		(3+)			
^{85}Nb		84.9279	2.3 m	β^+ /6.0					
^{86m}Nb			56. s	β^+					
^{86}Nb		85.9250	1.46 m	β^+ /8.0					ann.rad./
									0.751
									1.003
^{87m}Nb			3.7 m	β^+ /		1/2–			ann.rad./
				EC/					0.1352
									0.2010
^{87}Nb		86.92036	2.6 m	β^+ 5.2/		(9/2+)			ann.rad./
				EC/					0.2010
									0.4706
									0.6165
									1.0665
									1.8842
^{88m}Nb			7.7 m	β^+ /		4–			ann. rad./
				EC/					0.2625
									0.3996
									1.0569
									1.0825
^{88}Nb		87.9183	14.3 m	β^+ /7.6	3.2/	8+			ann. rad./
				EC/					1.0570
									1.0828
									(0.07–2.5)
^{89m}Nb			2.0 h	β^+ /	3.3/	9/2+			0.5880/10(D)
				EC/					(0.17–4.0)
^{89}Nb		88.91349	1.10 h	β^+ /74/4.29	2.8/	1/2–	+6.216		ann.rad./
				EC/26 /					0.5074
									0.5880
									0.7696
									1.2775
^{90m}Nb			18.8 s	I.T./0.1246		4–			0.002
									0.1225
^{90}Nb		89.911263	14.6 h	β53 /6.111	0.86/5	8+	4.961		ann. rad./
				EC/47 /	1.5/92				0.1412
									1.1292
									2.1862
									2.3189
									(0.1–3.3)
^{91m}Nb			62. d	I.T./97 /		1/2–			0.1045(IT)
				EC/3 /					1.2050
^{91}Nb		90.906989	7×10^2 y	EC/1.253		9/2+			Mo k x-ray
^{92m}Nb			10.13 d	EC/99+/		2+	6.114		0.9126
									0.9345
									1.8475
^{92}Nb		91.907192	3.7×10^7 y	EC/2.006		7+			0.5611
									0.9345
^{93m}Nb			16.1 y	I.T./0.0304		1/2–			Nb x–ray
									0.0304
^{93}Nb	100.	92.906376				9/2+	+6.1705	–0.32	
^{94m}Nb			6.26 m	I.T./99+	/2.086	3+			Nb k x-ray
				β^- /0.5/					0.0409

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.87109
^{94}Nb		93.907282	2.4×10^4 y	β^- /2.045	0.47/	6+			0.70263
									0.87109
^{95m}Nb			3.61 d	I.T./97.5/	0.2357	1/2–			0.2040
				β^- /2.5 /					0.2356
^{95}Nb		94.906834	34.97 d	β^- /0.926	0.160/	9/2+	6.141		0.76578
^{96}Nb		95.908099	23.4 h	β^- /3.187	0.5/10	6+	4.976		0.7782
					0.75/90				0.2191–1.498
^{97m}Nb			58.1 s	I.T./0.7434	0.734/98	1/2–			0.7434
^{97}Nb		96.908096	1.23 h	β^- /1.934	1.27/98	9/2+	6.15		0.4809
									0.6579
^{98m}Nb			51. m	β^- /4.67		5+			0.7874
									0.1726–1.89
^{98}Nb		97.91033	2.9 s	β^- /4.59	4.6/	1+			0.6451
									0.7874
									1.0243
^{99m}Nb			2.6 m	β^- /	3.2/	1/2–			0.0978/100
									(0.138–3.010)
^{99}Nb		98.91162	15.0 s	β^- /3.64	3.5/100	9/2+			0.0977
									0.1378/3.1
^{100m2}Nb			0.013 ms						
^{100m1}Nb			3.0 s	β^- /6.74	5.8				Nb k x-ray
									0.159
									0.6364
									1.0637
^{100}Nb		99.91418	1.5 s	β^- /6.25	6.2/				0.5354
					5.3/				0.6001–1.566
^{101}Nb		100.91525	7.1 s	β^- /4.57	4.3/				0.1105–0.810
^{102m}Nb			4.3 s	β^- /					
^{102}Nb		101.91804	1.3 s	β^- /7.21	7.2/				0.2960–2.184
^{103}Nb		102.91914	1.5 s	β^- /5.53	5.3/	5/2+			
^{104m}Nb			0.9 s	β^-, n/	n/0.06				
^{104}Nb		103.9225	4.8 s	β^-, n/8.1	n/0.05				
^{105}Nb		104.9239	3.0 s	β^-, n/6.5	n/1.7				
^{106}Nb		105.9282	1.0 s	β^-, n/9.3	n/4.5				
^{107}Nb		106.9303	0.30 s	β^-, n/7.9	n/6.0				
^{108}Nb		107.9350	0.19 s	β, n/	n/6.2				(0.193–0.590)
^{109}Nb		108.9376	0.19 s	β, n/	n/31				
^{110}Nb		109.943	0.17 s	β, n/	n/40				
^{111}Nb			>0.15 μs						
^{112}Nb			>0.15 μs						
^{113}Nb			>0.15 μs						
$_{42}$Mo		**95.94(1)**							
^{83}Mo		82.949	≈ 6. ms						
^{84}Mo		83.9401	≈ 3.7 s	β^+ /6.					
^{85}Mo		84.9366	3.2 s	β^+/8.1		1/2+			
^{86}Mo		85.9302	20. s	β^+ /4.8					
^{87}Mo		86.9273	14. s	EC, β^+/6.5					(0.752–1.004)
^{88}Mo		87.92195	8.0 m	β^+ /3.4		0+	+0.5		ann.rad./
				EC					0.0800
									0.1399
									0.1707
^{89m}Mo			0.19 s	I.T./0.118		1/2–			0.118(IT)
									0.268
^{89}Mo		88.91948	2.2 m	β^+ /5.58		9/2+			ann.rad./
				EC/					0.659
									0.803
									1.155
									1.272
^{90}Mo		89.91394	5.7 h	β^+ /25/2.489	1.085/	0+			ann.rad./
				EC/75 /					0.04274
									0.12237
									0.25734
^{91m}Mo			1.08 m	I.T./50/0.653		1/2–			ann.rad./

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				β^+, EC/50 /	2.5/				0.6529
					2.8/				1.2081
					4.0/				1.5080
									2.2407
^{91}Mo		90.91175	15.5 m	β^+ /94/4.43	3.44/94	9/2–			ann.rad./
				EC/6/					1.6373
									2.6321
									3.0286
									(0.1–4.2)
^{92}Mo	14.77(31)	91.906810	$>3 \times 10^{17}$ y	β^+-EC		0+			
^{93m}Mo			6.9 h	I.T./99+ /2.425	21/2+	+9.21			0.26306(IT)
									0.68461
									1.47711
^{93}Mo		92.906811	3.5×10^3 y	EC/0.405		5/2+			0.0304
^{94}Mo	9.226(99)	93.905087				0+			
^{95}Mo	15.900(85)	94.905841				5/2+	–0.9142	–0.02	
^{96}Mo	16.674(12)	95.904678				0+			
^{97}Mo	9.560(50)	96.906020				5/2+	–0.9335	+0.26	
^{98}Mo	24.20(25)	97.905407				0+			
^{99}Mo		98.907711	2.7476 d	β^- /1.357	0.45/14	1/2+	0.375		0.144048
					0.84/2				0.18109
					1.21/84				0.36644
									0.73947
^{100}Mo	9.67(20)	99.90748	$\approx 1 \times 10^{19}$ y	$\beta^-\beta^-$		0+			
^{101}Mo		100.91035	14.6 m	β^- /2.82	2.23/	1/2+			0.0063
					0.7/				0.19193
									0.5909
									(0.0809–2.405)
^{102}Mo		101.91030	11.3 m	β^- /1.01	1.2/	0+			0.1493/89.
									0.2116/100.
									0.2243/32.
^{103}Mo		102.91320	1.13 m	β^- /3.8		3/2+			0.1028(2)/
									0.1440(2)
									0.2511(2)
^{104}Mo		103.91376	1.00 m	β^- /2.16		0+			0.0686(1)/100.
									0.4239(4)/21.
^{105}Mo		104.9170	36. s	β^- /4.95		3/2+			0.0642/
									0.0856/
									0.2495/
^{106}Mo		105.91814	8.4 s	β^- /3.52		0+			0.1894(2)/22.
									0.3644(2)/6.
									0.3723(2)/12.
^{107}Mo		106.9217	3.5 s	β^- /6.2					
^{108}Mo		107.9236	1.1 s	β^- /5.1					(0.028–0.636)
^{109}Mo		108.9278	0.5 s	β^- /7.2					
^{110}Mo		109.9297	0.30 s	β^- /5.7					Tc k x-ray
									0.142
									(0.039–0.599)
^{111}Mo		110.9345	>0.15 μs						
^{112}Mo		111.937	>0.15 μs						
^{113}Mo		112.942	>0.15 μs						
^{114}Mo			>0.15 μs						
^{115}Mo			>0.15 μs						
^{116}Mo			>0.15 μs						
^{117}Mo			>0.15 μs						
$_{43}$Tc									
^{85}Tc		84.949	<0.1 ms						
^{86}Tc		85.9430	0.05 s	β^+ /11.9					
^{87}Tc		86.9365	2.4 s	β^+ /8.6					
^{88}Tc		87.9328	5.8 s	β^+ /10.1					
^{89m}Tc			13. s						
^{89}Tc		88.9275	13. s	β^+ /7.5					

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{90m}Tc			49.2 s	β^+	5.3/	6+			ann.rad./
									0.9479/
									1.0542/
^{90}Tc		89.9235	8.3 s	β^+ /8.9	7.0/15	1+			ann.rad./
					7.9/95.				0.9479/
^{91m}Tc			3.3 m	β^+		1/2+			ann.rad./170.
				EC					0.8110(5)/5.
									1.6052(1)/7.8
									1.6339(1)/9.1
									1.9023(1)/6.
									2.4509(1)/13.5
^{91}Tc		90.9184	3.14 m	β^+ /6.2	5.2	9/2+			ann.rad./200.
^{92}Tc		91.91526	4.4 m	β^+ /7.87	4.1	8+			ann.rad./200.
				EC					0.0850/
									0.1475
									0.3293
									0.7731
									1.5096
^{93m}Tc			43. m	I.T./13		1/2–			0.3924(IT)
				EC/20					0.9437
									2.6445
^{93}Tc		92.910248	2.73 h	β^+ /13/3.201	0.81	9/2+	6.26		ann.rad./
				EC/87/					1.3629
									1.4771
									1.5203
									(0.1–3.0)
^{94m}Tc			52. m	β^+ /72/4.33		2+			ann.rad./
				EC/28/					0.8710
									1.8686
^{94}Tc		93.909655	4.88 h	β^+ /11/4.256		7+	5.08		ann.rad./
				EC/89/					0.4491
									0.7026
									0.8496
									0.8710
^{95m}Tc			61. d	I.T./4/		1/2–			ann.rad./
				β^+ /0.3	0.5/				0.0389(IT)
				EC/96	0.7/				0.2041
									0.5821
									0.5821
									0.8351
^{95}Tc		94.90766	20.0 h	EC/100/1.691		9/2+	5.89		0.7657
									1.0738
^{96m}Tc			52. m	I.T./90/		4+			0.0342(IT)
				β^+, EC/2/					0.7782
									1.2002
^{96}Tc		95.90787	4.3 d	EC/2.973		7+	+5.04		Mo k x-ray
									0.7782
									0.8125
									0.8498
									1.12168
^{97m}Tc			91. d	I.T./0.0965		1/2–			Tc k x-ray
				EC	/3.9				0.0965
^{97}Tc		96.906364	4.2×10^6 y	EC/100/0.320		9/2+			Mo k x-ray
^{98}Tc		97.907215	$\approx 6.6 \times 10^6$ y	β^- /1.80	0.40/100	6+			0.65241
									0.74535
^{99m}Tc			6.01 h	I.T./100/0.142		1/2–			Tc k x-ray
									0.14049
									0.14261
^{99}Tc		98.906254	2.13×10^5 y	β^- /0.294	0.293/100	9/2+	+5.6847	–0.129	
^{100}Tc		99.907657	15.8 s	β^- /3.202	2.2/	1+			0.5396
				EC /1.8(10)$^{-3}$/	0.17	2.9/			0.5908
					3.3				(0.3 79–2.30)
^{101}Tc		100.90731	14.2 m	β^- /1.61	1.32/	9/2+			0.1272
									0.1841
									0.3068
									0.5451
									(0.073–0.969)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{102m}Tc			4.4 m	I.T./2/4.8	1.8/				0.4184
				β^- /98/					0.4752
									0.6281
									0.6302
									1.0464
									1.1033
									1.6163
									2.2447
^{102}Tc		101.90921	5.3 s	β^- /4.53	3.4/	1+			0.4686
					4.2				0.4751
					2.2/				1.1055
^{103}Tc		102.90918	54. s	β^- /2.66	2.0/	5/2+			0.1361
					2.2/				0.1743
									0.2104
									0.3464
									0.5629
									(0.13–1.0)
^{104m}Tc			0.005 ms						
^{104}Tc		103.91144	18.2 m	β^- /5.60	5.3/	(3+)			0.3483
									0.3580
									0.5305
									0.5351
									0.8844
									0.8931
									1.6768
									(0.3–3.7)
^{105}Tc		104.91166	7.6 m	β^- /3.6	3.4/	5/2+			0.1079
									0.1432
									0.3215
^{106}Tc		105.91436	36. s	β^- /6.55		2+			0.2703
									0.5222
									1.9694
									2.2393
									2.7893
^{107}Tc		106.9151	21.2 s	β^- /4.8					0.1027
									0.1063
									0.1770
									0.4587
^{108}Tc		107.9185	5.1 s	β^- /7.72		(3)			0.2422
									0.4656
									0.7078
									0.7326
									1.5835
^{109}Tc		108.9200	1.4 s	β^- /6.3	p/0.08				
^{110}Tc		109.9234	0.83 s	β^- /8.8	p/0.04				0.2407
^{111}Tc		110.9250	0.30 s	β^- .n/7.0	n/0.85				0.150/92.7
									0.063–1.435
^{112}Tc		111.9292	0.26 s	β, n	n/2.6				
^{113}Tc		112.931	0.15 s	β^-, n/8.	/2.1				0.0985/100
									0.0658–1.520
^{114}Tc		113.936	0.15 s	β^-, n	/1.3				
^{115}Tc		114.938	>0.15 μs						
^{116}Tc			>0.15 μs						
^{117}Tc			>0.15 μs						
^{118}Tc			>0.15 μs						
$_{44}$Ru	**101.07(2)**								
^{87}Ru		86.949	>1.5 μs						
^{88}Ru		87.9404	1.2 s			0^+			
^{89}Ru		88.936	1.4 s	β^+ .p/8.					
^{90}Ru		89.9298	12. s	β^+ /5.9		0^+			ann.rad./
									0.155–1.551
^{91}Ru		90.9264	9. s	β^+, EC/7.4		9/2+			ann.rad./
^{92}Ru		91.9201	3.7 m	β^+ /53/4.5		0+			ann.rad./
				EC/47/					0.1346
									0.2138

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.2593
^{93m}Ru			10.8 s	I.T./21/		1/2-			ann.rad./
				β^+, EC/79/	5.3/				0.7344
									1.1112
									1.3962
									2.0931
^{93}Ru		92.9171	1.0 m	β^+ /6.3		9/2+			ann.rad./
				EC/					0.6807
									1.4349
									(0.5–4.2)weak
^{94}Ru		93.91137	52. m	EC/100/1.59		0+			0.3672
									0.5247
									0.8922
^{95}Ru		94.91042	1.64 h	EC/85/2.57	1.20/	5/2+	0.86		ann.rad./
				β^+ /15/	0.91/				0.3364
									0.6268
									0.036–2.424
^{96}Ru	5.54(14)	95.90760	>3.1 × 10^{16} y	$\beta^+\beta^+$		0+			
^{97}Ru		96.90756	2.89 d	EC/1.12		5/2+	–0.78		Tc k x-ray
									0.2157
									0.3245
									0.4606
^{98}Ru	1.87(3)	97.90529				0+			
^{99}Ru	12.76(14)	98.905939				5/2+	–0.6413	+0.079	
^{100}Ru	12.60(7)	99.904219				0+			
^{101}Ru	17.06(2)	100.905582				5/2+	–0.7188	+0.46	
^{102}Ru	31.55(14)	101.904349				0+			
^{103}Ru		102.906323	39.27 d	β^- /0.763	0.223	3/2+	0.206	+0.62	0.05329
									0.29498
									0.4438
									0.49708
									0.55704
									0.61033
									(0.04–1.6)
^{104}Ru	18.62(27)	103.905430				0+			
^{105}Ru		104.907750	4.44 h	β^- /1.917	1.11/22	3/2+	-0.3		0.12968
					1.134/13				0.1491
					1.187/49				0.2629
									0.31664
									0.46943
									0.67634
									0.72420
									(0.1–1.8)
^{106}Ru		105.90733	1.020 y	β^- /0.0394	0.0394/100	0+			
^{107}Ru		106.9099	3.8 m	β^- /2.9	2.1/				0.1939
					3.2/				0.3741
									0.4625
									0.8488
^{108}Ru		107.9102	4.5 m	β^- /1.4	1.2/	0+			0.0923
									0.1651
									0.4339
									0.4975
									0.6189
^{109}Ru		108.91320	34.5 s	β^- /4.2					0.1164
									0.3584
^{110}Ru		109.9140	15. s	β^- /2.81					0.1121
									0.3737
									0.4397
									0.7967
^{111}Ru		110.9176	1.5 s	β^- /5.5					
^{112}Ru		111.9188	4.5 s	β^- /4.5					
^{113m}Ru			0.6 s						
^{113}Ru		112.9225	0.80 s	β^- /7.					0.2632
									0.048–2.418
^{114}Ru		113.9239	0.57 s	β^- /6.1					0.127/24

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									(0.053–0.180)
^{115}Ru		114.928	≈0.74 s	β^- /8.					
^{116}Ru		115.930	>0.15 μs						
^{117}Ru		116.935	>0.15 μs						
^{118}Ru		117.937	>0.15 μs						
^{119}Ru			>0.15 μs						
^{120}Ru			>0.15 μs						
$_{45}$Rh		**102.90550(2)**							
^{89}Rh		88.9494	>0.15 μs						
^{90m}Rh			≈12. ms						
^{90}Rh		89.9429	1.0 s						
^{91}Rh		90.9366	1.9 s						
^{92}Rh		91.9320	5.6 s	β^+ /11.1					
^{93}Rh		92.9257	14. s	β^+ /8.1					(0.138–1.493)
^{94m}Rh			25.8 s	β^+ /		8+			ann.rad./
									0.1264
									0.3117
									0.7562
									1.0752
									1.4307
^{94}Rh		93.9217	1.18 m	β^+ /9.6	6.4/	3+			ann.rad./
									0.1461
									0.3117
									0.7562
									1.4307
^{95m}Rh			1.96 m	I.T./88/		1/2+			ann.rad./
				β^+, EC/12/					0.5433(IT)
									0.7837
^{95}Rh		94.9159	5.0 m	β^+ /5.1	3.2	9/2+			ann.rad./
									0.2293
									0.4103
									0.6610
									0.9416
									1.3520
									(0.2–3.8)
^{96m}Rh			1.51 m	I.T./60/0.052		2+			ann.rad./
				β^+, EC/40/	4.70/				Tc,Ru x-rays
									0.8326
									1.0985
									1.6921
									(0.4–3.3)
^{96}Rh		95.91452	9.6 m	β^+/6.45	3.3/	5+			ann.rad./
				EC/					0.4299
									0.6315
									0.6853
									0.7418
									0.8326
									(0.2–3.4)
^{97m}Rh			46. m	I.T./5 /	2.6/	1/2–			ann.rad./
				β^+, EC/95/					0.1886
									0.4215
									2.2452
^{97}Rh		96.91134	31.0 m	β^+ /3.52	2.1/	9/2+			ann.rad./
									0.1886
									0.3892
									0.4515
									0.8398
									0.8788
									(0.2–3.5)
^{98m}Rh			3.5 m	β^+ /		5+			ann.rad./
									0.6154
									0.6524
									0.7452
^{98}Rh		97.91072	8.7 m	β^+ /90/5.06	3.4/	2+			ann.rad./
									0.6524

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.7623
^{99m}Rh			4.7 h	β^+ /8/	.74/	9/2+	5.67		ann.rad./
				EC/92/					0.2766/
									0.3408
									0.6178
									1.2612
^{99}Rh		98.90820	16. d	β^+/4/2.10	0.54/	1/2–			ann.rad./
				EC/97/	0.68/				0.0894/
									0.3530
									0.5277
									(0.1–2.0)
^{100m}Rh			4.7 m	I.T./99/		5+			ann.rad./
				β^+ /0.4/					0.0748/
									0.2647(IT)
^{100}Rh		99.90812	20.8 h	β^+ /3.63	2.62/	1–			0.4462
				EC/	2.07/				0.5396
									0.5882
									0.8225
									1.5534
									2.3761
^{101m}Rh			4.35 d	EC/92/		9/2+	+5.51		Rh k x-ray
				I.T./8/0.1573					0.1272/
									0.3069
									0.5451
^{101}Rh		100.90616	3.3 y	EC/0.54		1/2–			Ru k x-ray
									0.1272
									0.1980
									0.3252
^{102m}Rh			3.74 y	EC/2.323		6+	4.04		0.4751
				IT/0.0419					0.6313
			>1.2 × 10^6 y	β^+	/<0.00025				0.6975
									0.7668
									1.0466
									1.1032
^{102}Rh		101.906842	207. d	EC/62			0.5		ann.rad./
				β^- /19/					0.4686
				β^+ /14/					0.4751
									0.5566
									0.6280
									1.1032
									(0.4–1.6)
^{103m}Rh			56.12 m	IT		7/2+	4.54		
^{103}Rh	100.	102.905504				1/2–	–0.0884		
^{104m}Rh			4.36 m	I.T./99+ /		5+			Rh k x-ray
				b^-	1.3/				0.0514
									0.0971
									0.5558
^{104}Rh		103.906655	42.3 s	β^-/99+/2.441	1.88/2	1+			0.3581
				EC/0.4/1.141	2.44/98				0.5558
									1.2370
									(0.35–1.8)
^{105m}Rh			43. s	I.T./1.296		1/2–			Rh k x-ray
									0.1296
^{105}Rh		104.905692	35.4 h	β^- /0.567	0.247/30	7/2+	+4.45		0.2801
					0.567/70				0.3061
									0.3189
^{106m}Rh			2.18 h	β^- /	0.92/	6+			0.2217
									0.4510
									0.5119
									0.6162
									0.7173
									0.7484
									1.0458
									1.5277
^{106}Rh		105.90729	29.9 s	β^- /3.54	2.4/2	1+	+2.58		0.51186/
					3.0/12				0.61612
					3.54/79				0.62187

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									(0.05–3.04)
^{107}Rh		106.90675	21.7 m	β^- /1.51	1.20/65	7/2+			0.2776
					1.5/17				0.3028
									0.3925
^{108m}Rh			6.0 m	β^- /	1.57/				0.4339
									0.4973
									0.6189
^{108}Rh		107.9087	17. s	β^- /4.5		1+			0.4046
									0.4339
									0.4973
									0.5811
									0.6146
									0.9014
									0.9471
^{109}Rh		108.90874	1.34 m	β^- /2.59	2.25/	7/2+			0.1134
									0.1780
									0.2914
									0.3254
									0.3268
									0.4261
									(0.1–1.6)
^{110m}Rh			29. s	β^- /	[.6/				0.3737
									0.4397
									0.7967
^{110}Rh		109.9110	3.1 s	β^- /5.4	5.5/	1+			0.3737
									0.4400
									0.5463
									0.6877
									0.8381
									0.9045
^{111}Rh		110.9117	11. s	β^- /3.7					0.275
^{112m}Rh			6.8 s	β^- /					
^{112}Rh		111.9140	3.5 s	β^- /6.2		1+			0.3489
^{113}Rh		112.9154	0.9 s	β^- /4.9					0.1285
^{114m}Rh			1.8 s	β^- /					
^{114}Rh		113.9173	1.8 s	β^- /6.5		1+			
^{115}Rh		114.9201	0.99 s	β^- /6.0					
^{116m}Rh			0.9 s	β^- /					0.3405
^{116}Rh		115.9228	0.7 s	β^- /8.0		1+			0.340
									0.398–1.665
^{117}Rh		116.925	0.44 s	β^- /7.					0.0346
									0.1317
^{118}Rh		117.929	≈ 0.30 ms						0.379
									0.575
									0.370–1.037
^{119}Rh		118.931	>0.15 μs						
^{120}Rh		119.936	>0.15 μs						
^{121}Rh		120.938	>0.15 μs						
^{122}Rh									
$_{46}$Pd		**106.42(1)**							
^{91}Pd		90.949	>1.5 μs						
^{92}Pd		91.9404	1.0 s						
^{93}Pd		92.9359	1.2 s	β^+, p		9/2			0.240/81
									0.382–0.864
^{94}Pd		93.9288	9. s	EC, β^+ /≈ 6.6					0.5582
									(0.0546–0.798)
^{95m}Pd		94.92684	13.4 s	EC, β^+ /10.2		21/2+			
^{95}Pd									
^{96}Pd		95.9182	2.03 m	EC, β^+ /3.5	1.15/				0.1248
									0.4995
^{97}Pd		96.9165	3.1 m	β^+, EC/4.8	3.5/	5/2+			ann.rad./
									0.2653
									0.4752
									0.7927
									(0.2–3.4)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{98}Pd		97.91273	17.7 m	β^+ /1.87		0+			ann.rad./
				EC/					0.0677
									0.1125
									0.6630
									0.8379
^{99}Pd		98.91181	21.4 m	β^+ /49/3.37	2.18/	5/2+			ann.rad./
				EC/51/					0.1360
									0.2636
									0.6734
									(0.2–2.85)
^{100}Pd		99.90851	3.7 d	EC/0.36		0+			0.03271
									0.0748
									0.0840
^{101}Pd		100.90829	8.4 h	β^+ /5/1.980	0.776/	5/2+	–0.66		ann.rad./
				EC/95/					0.0244
									0.2963
									0.5904
^{102}Pd	1.02(1)	101.905607				0+			
^{103}Pd		102.906087	16.99 d	EC/0.543		5/2+			Rh k x-ray
									0.03975
									0.3575
									0.4971
^{104}Pd	11.14(8)	103.904034				0+			
^{105}Pd	22.33(8)	104.905083				5/2+	–0.642	+0.66	
^{106}Pd	27.33(3)	105.903484				0+			
^{107m}Pd			20.9 s	I.T./0.2149		11/2–			Pd k x-ray
									0.2149(IT)
^{107}Pd		106.90513	6.5×10^6 y	β^- /0.033	0.03/	5/2+			
^{108}Pd	26.46(9)	107.903895				0+			
^{109m}Pd			4.75 m	I.T./0.1889		11/2–			Pd x-ray
									0.1889(IT)
^{109}Pd		108.905954	13.5 h	β^- /1.116	1.028	5/2+			0.0880
									(0.08–1.0)
^{110}Pd	11.72(9)	109.905153				0+			
^{111m}Pd			5.5 h	I.T./73/0.172		11/2–			0.0704
				β^- /27/	0.35				0.1722
					0.77				0.3912
									(0.1–1.97)
^{111}Pd		110.90764	23.4 m	β^- /2.19	2.2/95	5/2+			0.0598
									0.2454
									0.5800
									0.6504
									1.3885
									1.4590
^{112}Pd		111.90731	21.04 h	β^- /0.29	0.28/	0+			0.018
^{113m}Pd			1.48 m	β^- /		5/2+			0.0959
^{113}Pd		112.91015	1.64 m	β^- /3.34					0.0958
									0.4824
									0.6436
									0.7394
^{114}Pd		113.91037	2.48 m	β^- /1.45		0+			0.1266
									0.2320
									0.5582
									0.5760
^{115}Pd		114.9137	47. s	β^- /4.58					0.1255
									0.2554
									0.3428
^{116}Pd		115.9142	12.7 s	β^- /2.61					0.1015
									0.1147
									0.1778
^{117}Pd		116.9178	4.4 s	β^- /5.7					0.2473
									0.077–0.403
^{118}Pd		117.9189	2.4 s	β^- /4.1					0.1254
									0.028–0.596
^{119}Pd		118.9227	0.9 s	β^- /6.5					0.2566

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.070–0.326
^{120}Pd		119.9240	0.5 s	β^- /5.0					0.1581
									0.053–0.595
^{121}Pd		120.9282	>0.24 μs						
^{122}Pd		121.9298	>0.24 μs						
^{123}Pd		122.934	>0.15 μs						
^{124}Pd									
$_{47}$Ag		**107.8682(2)**							
^{93}Ag									
^{94m}Ag			0.03 s						
^{94}Ag		93.9428	0.38 s	β^+, p/					
^{95}Ag		94.9355	2.0 s	β^+, p/					(0.539–2.025)
^{96m}Ag			4.4 s	β^+		8+			
				β^+, p	/8.				
^{96}Ag		95.9307	7. s	β^+ /11.6		2+			ann.rad./
				EC/					0.1248
				β^+, p	/21.				0.4995
									(0.1066–1.416)
^{97}Ag		96.9240	19. s	β^+ /7.0					ann.rad./
				EC/					0.6862
									1.2941
									(0.352–3.294)
^{98}Ag		97.9218	47.6 s	β^+ /8.4		5+			ann.rad./
				EC/	/36.				0.5711
				β^+, p	/0.11				0.6786
									0.8631
									(0.153–1.185)
^{99m}Ag			11. s	I.T./100/		1/2–			Ag k x-ray
									0.1636(IT)
									0.3426
^{99}Ag		98.9176	2.07 m	β^+ /87 5.4		9/2+			ann.rad./
				EC/13/					0.2199
									0.2645
									0.8056
									0.8323
									(0.2–3.5)
^{100m}Ag			2.3 m	β^+ /		2+			ann.rad./
				EC/					0.6657
									1.6941
^{100}Ag		99.9161	2.0 m	β^+/7.1	4.7/	5+			ann.rad./
				EC/					0.2807
									0.4503
									0.6657
									0.7508
									0.7732
^{101m}Ag			3.1 s	I.T./0.23		1/2–			Ag k x-ray
									0.0981
									0.176(IT)
^{101}Ag		100.9128	11.1 m	β^+ /69/4.2	2.7/	9/2+	5.7		ann.rad./
				EC/31/					0.2610
					2.18/				0.2747
					2.73/				0.3269
					3.38/				0.4392
									0.6673
									1.1739
									(0.2–3.1)
^{102m}Ag			7.8 m	β^+ /38/	3.4	2+	+4.14		ann.rad./
				EC/13/					0.5567
				I.T./49/					0.9777
									1.8347
									2.0545
									2.1594
									3.2386
^{102}Ag		101.91197	13.0 m	β^+ /78/5.92	2.26/	5+	4.6		ann.rad./
				EC/22/					0.5564

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.7193
									0.163–2.242
^{103m}Ag			5.7 s	I.T./0.134		1/2–			Ag k x-ray
									0.1344
^{103}Ag		102.90897	1.10 h	β^+ /28/2.69	1.7	7/2+	+4.47		ann.rad./
				EC/72/	1.3				0.1187
									0.1482
^{104m}Ag			33. m	β^+ /64/	2.71/	2+	+3.7		ann.rad./
				EC/36/					0.5558
				I.T./0.07/					0.7657
									(0.5–3.4)
^{104}Ag		103.90863	69. m	β^+ /16/4.28	0.99/	5+	3.92		ann.rad./
				EC/84/					0.5558
									0.9259
									0.9416
									(0.18–2.27)
^{105m}Ag			7.2 m	I.T./98/0.0255		7/2+	+4.41		Ag x-ray
				EC/2 /					0.3063
									0.3192
									(0.1–1.0)
^{105}Ag		104.90653	41.3 d	EC/1.35		1/2–	0.1014		0.0640
									0.2804
									0.3445
									0.4434
^{106m}Ag			8.4 d	EC/		6+	3.71	+1.1	Pd k x-ray
									0.4510
									0.5118
									0.7173
									1.0458
^{106}Ag		105.90667	24.0 m	β^+ /59/2.965	/1.96	1+	+2.85		ann.rad./
				EC/41 /					0.5119
^{107m}Ag			44.2 s	I.T./0.093		7/2+	+4.40	1.0	Ag x-ray
									0.0931
^{107}Ag	51.839(8)	106.905093				1/2–	–0.11357		
^{108m}Ag			418. y	EC/92/		6+	3.580	+1.3	Ag k x-ray
				I.T./8 /0.079					Pd k x-ray
									0.43392
									0.61427
									0.72290
^{108}Ag		107.905954	2.39 m	β^- /97/1.65	1.02/1.7	1+	+2.6884		ann.rad./
				EC/2/	1.65/96				0.43392
				β^- /1/1.92	0.88/0.3				0.61885
									0.63298
^{109m}Ag			39.8 s	I.T./0.088		7/2+	+4.40	+1.0	Ag k x-ray
									0.0880
^{109}Ag	48.161(8)	108.904756				1/2–	–0.13069		
^{110m}Ag			249.8 d	β^- /99/	0.087	6+	+3.60	+1.4	0.65774
				I.T./1 /0.1164	0.530				0.76393
									0.88467
									0.93748
									1.38427
									(0.447–1.56)
^{110}Ag		109.906111	24.6 s	β^- /2.892	2.22/5	1+	+2.7271	0.2	0.65774
					2.89/95				0.8154
									1.1257
^{111m}Ag			1.08 m	IT/99/0.0598		7/2+			Ag k x-ray
				β^- /1/					0.0598
									0.2454
^{111}Ag		110.905295	7.47 d	β^- /1.037	1.035/	1/2–	–0.146		0.2454
									0.3421
^{112}Ag		111.90701	3.13 h	β^- /3.96	3.94/	2–	0.0547		0.6067
					3.4				0.6174
									1.3877
									(0.4–2.9)
^{113m}Ag			1.14 m	I.T./80 /0.043		7/2+			0.1422
				β^- /20 /	1.5				0.2983
									0.3161

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.3923
^{113}Ag		112.90657	5.3 h	β^- /2.02	2.01/	1/2–	0.159		0.2588
									0.2986
^{114}Ag		113.90881	4.6 s	β^- /5.08	4.9/	1+			0.5582
									0.5760
									1.9946
^{115m}Ag			18.7 s	β^- /		7/2+			0.1134
									0.1315
									0.2288
									0.3887
^{115}Ag		114.90876	20. m	β^- /3.10		1/2–			0.1316
									0.2128
									0.2291
									0.4727
									(0.13–2.49)
^{116m}Ag			10.5 s	I.T./2 /	3.2/	5+			0.5134
				β^- /98 /	2.9				0.7055
									0.255–2.838
^{116}Ag		115.91137	2.68 m	β^- /6.16	5.3	2–			0.5134
									0.6993
									2.4779
^{117m}Ag			5.3 s	β^- /	3.2/	7/2+			0.1354
									0.2981
									0.3868
									0.1571
^{117}Ag		116.91171	1.22 m	β^- /4.18	2.3	1/2-			0.1354
									0.3377
^{118m}Ag			2.8 s	β^- /59/					0.1277
				I.T./41 /0.1277					0.4878
									0.6771
									0.7709
									1.0586
^{118}Ag		117.9145	4.0 s	β^- /7.1					0.4878
									0.6771
									3.2259
^{119}Ag		118.9157	2.1 s	β^- /5.35		7/2+			0.0674
									0.3662
									0.3991
									0.6264
^{120m}Ag			0.32 s	β^- /					0.2030
				I.T./					0.5059
									0.6978
									0.8300
									0.9258
^{120}Ag		119.9188	1.23 s	β^- /8.2					0.5059
									0.6978
									0.8171
									1.3231
^{121}Ag		120.9198	0.78 s	β^- /6.4					0.1150
									0.3148
									0.3537
									0.3696
									0.5007
									1.5105
									(0.11–2.5)
^{122m}Ag			1. s	β^- /					
^{122}Ag		121.9233	0.44 s	β^- /9.2					
^{123}Ag		122.9249	0.31 s	β^- /7.4					
^{124}Ag		123.9285	0.22 s	β^- /10.1					
^{125}Ag		124.9305	0.17 s	β^-					
^{126}Ag		125.9345	0.11 s	β^-					
^{127}Ag		126.9369	0.11 s	β^-					
^{128}Ag			58 ms	β^-					
^{129}Ag			0.05 s	β^-, n					
$_{48}$Cd		**112.411(8)**							

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{96}Cd		95.9398							
^{97}Cd		96.9349	3. s	β^+, (p)					
^{98}Cd		97.9276	9.2 s	β^+ /5.4					
				(p)	/0.025				
^{99}Cd		98.9250	16. s	β^+, EC/6.9					ann.rad./
^{100}Cd		99.9203	1.1 m	β^+, EC/3.9					ann.rad./
									(0.090–1.043)
^{101}Cd		100.9187	1.2 m	β^+ /83/5.5	4.5	5/2+			In k x-ray
				EC/17/					0.0985
									1.7225
									0.31–2.84)
^{102}Cd		101.91474	5.8 m	β^+ /27/2.59		0+			ann.rad./
				EC/73					0.0974
									0.4810
									1.0366
									1.3598
^{103}Cd		102.91342	7.5 m	β^+ /33/4.14		5/2+	–0.81	–0.8	ann.rad./
				EC/67/					Ag k x-ray
									1.0799
									1.4487
									1.4618
									(0.1–2.8)
^{104}Cd		103.90985	58. m	EC/1.14		0+			Ag k x-ray
									0.0835
									0.7093
^{105}Cd		104.90947	55.5 m	β^+ /26/2.739	1.69/	5/2+	–0.7393	+0.43	Ag k x-ray
				EC/74/					0.3469
									0.6072
									0.9618
									1.3025
									(0.25–2.4)
^{106}Cd	1.25(6)	105.90646	>2.6 × 10^{17} y	β^+, EC		0+			
^{107}Cd		106.90661	6.52 h	EC/99+/1.417		5/2+	–0.615055	+0.68	Ag k x-ray
				β^+ /					0.0931
									0.8289
^{108}Cd	0.89(3)	107.90418	>4.1 × 10^{17} y	EC EC		0+			
^{109}Cd		108.904985	462.0 d	EC/0.214		5/2+	–0.827846	+0.69	Ag k x-ray
									0.08804
^{110}Cd	12.49(18)	109.903006				0+			
^{111m}Cd			48.5 m	I.T./		11/2–			Cd k x-ray
									0.1508(IT)
									0.2454
^{111}Cd	12.80(12)	110.904182				1/2+	–0.594886		
^{112}Cd	24.13(21)	111.902758				0+			
^{113m}Cd			14.1 y	β^- /99.9/0.59	0.59/99.9	11/2–	–1.087	–0.71	0.2637
^{113}Cd	12.22(12)	112.904401	7.7 × 10^{15} y	β^-		1/2+	–0.622301		
^{114}Cd	28.73(42)	113.903359				0+			
^{115m}Cd			44.6 d	β^- /1.629	0.68/1.6	11/2–	–1.042	–0.54	0.48450
					1.62/97				0.93381
									1.29064
^{115}Cd		114.905431	2.228 d	β^- /1.446	0.593/42	1/2+	–0.648426		0.23141
					1.11/58				0.26085
									0.33624
									0.49227
									0.52780
^{116}Cd	7.49(18)	115.904756	3.8 × 10^{19} y	$\beta^-\beta^-$		0+			
^{117m}Cd			3.4 h	β^- /2.66	0.72/	11/2–			0.1586
									0.5529
									0.37–2.42
^{117}Cd		116.907219	2.49 h	β^- /2.52	0.67/51	1/2+			0.2209
					2.2/10				0.2733
									0.3445
									1.3033
^{118}Cd		117.90692	50.3 m	β^- /0.52		0+			
^{119m}Cd			2.20 m	β^- /		11/2–			0.1056
									0.7208

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									1.0250
									2.0213
^{119}Cd		118.90992	2.69 m	β^-/3.8	≈ 3.5/	1/2+			0.1340
									0.2929
									0.3429
^{120}Cd		119.90985	50.8 s	β^- /1.76	1.5/	0+			
^{121m}Cd			8. s	β^- /		11/2–			0.1008
									0.9878
									1.0209
									1.1815
									2.0594
^{121}Cd		120.9131	13.5 s	β^- /4.9		(3/2+)			0.2102
									0.3242
									0.3492
									1.0403
^{122}Cd		121.9135	5.3 s	β^- /3.0		0+			
^{123m}Cd			1.9 s	β^- /					
^{123}Cd		122.91770	2.09 s	β^- /6.12		3+			
^{124}Cd		123.9177	1.24 s	β^- /4.17		0+			0.0365
									0.0628
									0.1799
^{125m}Cd			0.66 s	β^- /					
^{125}Cd		124.92129	0.68 s	β^- /7.16		3/+			
^{126}Cd		125.9224	0.52 s	β^- /5.49		0+			0.2601
^{127}Cd		126.9264	0.4 s	β^- /8.5		3/+			
^{128}Cd		127.9278	0.28 s	β^- /7.1		0+			0.247
^{129}Cd		128.9323	0.27 s	β^- /5.9					0.281
^{130}Cd		129.9340	0.162 s	β^- /		0+			
				β^-, n	/≈ 3.5				
^{131}Cd			68 ms						
^{132}Cd			0.10 s	β^-, n/	/60				
$_{49}$In		**114.818(3)**							
^{98m}In			≈0.03 s						
^{98}In		97.9422	1. s						
^{99}In		98.9346	≈3.8 s	β^+ /8.9					
^{100}In		99.9316	6. s	β^+, (p)/10.5					
^{101}In		100.9266	15. s	β^+ /7.3					
^{102}In		101.9243	22. s	EC/8.9		(5)			0.1566
									0.7767
									(0.397–0.923)
^{103m}In			34. s						
^{103}In		102.91991	1.1 m	β^+, EC/6.05	4.2	9/2+			ann.rad./
				EC	/45				0.1879
									(0.157–3.98)
^{104m}In			16. s	IT/0.0935					
^{104}In		103.9183	1.84 m	β^+, EC/7.9	4.8	5+	+4.44	+0.7	ann.rad./
									0.6580
									0.8341
									0.8781
^{105m}In			43. s	I.T.		1/2–			In k x-ray
									0.6740
^{105}In		104.91467	5.1 m	β^+, EC/4.85	3.7	9/2+	+5.675	+0.83	0.1310
									0.2600
									0.6038
^{106m}In			5.3 m	β^+ /85/	4.90	3+			ann.rad./
				EC/15/					0.6326
									0.8611
									1.7164
^{106}In		105.91346	6.2 m	β^+ /65/6.52	2.6	7+	+4.92	+0.97	ann.rad./
				EC/35/					0.2259
									0.6327
									0.8611
									0.9978
									1.0091
^{107m}In			51. s	I.T./0.6786		1/2–			In k x-ray

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.6785
^{107}In		106.91029	32.4 m	β^+ /35/3.43	2.20/	9/2+	+5.59	+0.81	ann.rad./
				E.C/65/					Cd k x-ray
									0.2050
									0.3209
									0.5055
									(0.2–2.99)
^{108m}In			57. m	β^+ /53/	1.3	6+	+4.94	+0.47	ann.rad./
				EC/47/					Cd k x-ray
									0.6329
									1.9863
									3.4522
^{108}In		107.90971	40. m	β^+ /33/5.15	3.49/	3+	+4.56	+1.01	ann.rad./
				EC/67/					Cd k x-ray
									0.2429
									0.6331
									0.8756
^{109m}In			1.3 m	I.T./0.650		1/2–			In k x-ray
									0.6498
^{109}In		108.90715	4.2 h	β^+ /8/2.02	0.79/	9/2+	+5.54	+0.84	ann.rad./
				EC/92/					Cd k x-ray
									0.2035
									0.6235
^{110m}In			4.9 h	EC/		7+	+4.72	+1.00	Cd k x-ray
									0.6577
									0.8847
									0.9375
									(0.1–1.98)
^{110}In		109.90717	1.15 h	β^+ /62/3.88	2.22/	2+	+4.37	+0.35	ann.rad./
				EC/38/					Cd k x-ray
									0.6577
									(0.6–3.6)
^{111m}In			7.7 m	I.T./0.537		1/2–	+5.53		In k x-ray
									0.537
^{111}In		110.90511	2.8049 d	EC/0.866		9/2+	+5.50	+0.80	Cd k x-ray
									0.1712
									0.2453
^{112m}In			20.8 m	I.T./0.155		4+			In k x-ray
									0.1555
^{112}In		111.90553	14.4 m	β^+ /22/2.586		1+	+2.82	+0.09	ann.rad./
				EC/34/					Cd k x-ray
				β^- /0.663					0.6171
^{113m}In			1.658 h	I.T./0.3917		1/2–	–0.210		In k x-ray
									0.3917
^{113}In	4.29(5)	112.904062				9/2+	+5.529	+0.80	
^{114m}In			49.51 d	I.T./97/0.190		5+	+4.65	+0.74	In k x-ray
				EC/3 /					0.19027
^{114}In		113.904918	1.198 m	β^- /97/1.989	1.984/	1+	+2.82		Cd k x-ray
				EC/3/1.453					0.5584
									0.5727
									1.2998
^{115m}In			4.486 h	I.T./95/0.336		1/2–	–0.255		In k x-ray
				β^- /5 /0.83					0.3362
									0.4974
^{115}In	95.71(5)	114.903879	4.4×10^{14} y	β^- /0.495		9/2+	+5.541	+0.81	
^{116m2}In			2.16 s	I.T./0.162		8–	+3.22	+0.31	In k x-ray
				EC	/0.023				0.1624
^{116m1}In			54.1 m	β^- /	1.0	5+	+4.43	+0.80	0.13792
									0.41688/27
									1.09723/58.5
									1.29349/85
^{116}In		115.905261	14.1 s	β^- /3.274	3.3/99	1+	2.788	0.11	0.46313
									1.2526
									1.29349
^{117m}In			1.94 h	β^- /53/1.769	1.77/	1/2–	–0.2517		In k x-ray
				I.T./47 /					0.15855
									0.31531

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.55294
^{117}In		116.90452	44. m	β⁻ /1.455	0.74/	9/2+	+5.52	+0.83	0.15855
									0.3966
									0.55294
^{118m2}In			8.5 s	I.T./98/		(8–)	+3.32	+0.44	In k x-ray
				β⁻ /2/					0.1382
^{118m1}In			4.40 m	β⁻ /	1.3	5+	+4.23	+0.80	0.2086
					2.0				0.6833
									1.2295
^{118}In		117.90636	5.0 s	β⁻ /4.42	4.2/	1+			0.5282
									1.1734
									1.2295
									2.0432
^{119m}In			17.9 m	β⁻ /97/	2.7/	1/2–	–0.32		0.3114
				I.T./3/0.311					0.7631
^{119}In		118.90585	2.3 m	β⁻ /2.36	1.6/	9/2+	+5.52	+0.85	0.0239
									0.6495
									0.7631
									1.2149
^{120m2}In			47 s	β⁻ /6.1		8–	+3.692	+0.53	1.171
									1.023
^{120m1}In			46. s	β⁻ /5.8	2.2/	5+	+4.30	+0.81	1.171
									1.023
^{120}In		119.90796	3.1 s	β⁻ /5.37	5.6/	(1+)			0.4146
					3.1/				0.5924
									0.8637
									1.0232
									1.1714
									(0.4–2.7)
^{121m}In			3.8 m	β⁻ /99/	3.7/	1/2–	–0.36		0.0601
				I.T./1/0.313					0.3136
									0.9256
									1.0412
									1.1022
									1.1204
^{121}In		120.90785	23. s	β⁻ /3.36	2.5	9/2+	+5.50	+0.81	0.2620
									0.6573
									0.9256
^{122m}In			10. s	β⁻ /	4.4/	8–	+3.78	+0.59	1.0014
									1.1403
^{122}In		121.91028	1.5 s	β⁻ /6.37	5.3/	(1+)			0.2391
									1.0014
									1.1403
									1.164
									1.1903
^{123m}In			47. s	β⁻ /	4.6/	(1/2–)	–0.40		0.1258
									1.170
									3.234
^{123}In		122.91044	6.0 s	β⁻ /4.39	3.3/	(9/2+)	+5.49	+0.76	0.6188
									1.0197
									1.1305
^{124m}In			3.4 s	b⁻		8–	+3.89	+0.66	0.1029
									0.9699
									1.0729
									1.1316
^{124}In		123.91318	3.18 s	β⁻ /7.36	5/	3+	+4.04	+0.61	0.7070
									0.9978
									1.1316
									3.2142
									(0.3–4.6)
^{125m}In			12.2 s	β⁻ /	5.5/	1/2–	–0.43		0.1876
^{125}In		124.91360	2.33 s	β⁻ /5.42	4.1/	9/2+	+5.50	+0.71	0.4260
									1.0318
									1.3350
^{126m}In			1.53 s		4.9/	3+	+4.03	+0.49	0.9086
									0.9696
									1.1411

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{126}In		125.91646	1.63 s	β^- /8.21	4.2/	8–	+4.06		0.1118
									0.9086
									1.1411
^{127m}In			3.73 s	β^- /	6.4/	(1/2–)			0.2523
									3.074
^{127}In		126.91734	1.14 s	β^- /6.51	4.9/	(9/2+)	+5.52	+0.59	0.4680
									0.6461
									0.8051
									1.5977
^{128m}In			0.7 s	β^- /	5.4/	(8–)			1.8670
									1.9739
									(0.1205–2.12)
^{128}In		127.92017	0.80 s	β^- /8.98	5.0/	3+			0.9352
									1.1688
									3.5198
									4.2970
^{129m}In			1.23 s	β^- /98/	≈7.5/	1/2–			0.3153
				n/2/					0.9067
									1.2220
^{129}In		128.9217	0.63 s	β^- /7.66	5.5/	9/2+			0.2853
									0.7693
									1.8650
									2.1180
^{130m2}In			0.53 s	β^- /	8.8/	5+			0.0892
									0.7744
									1.2212
^{130m1}In			0.51 s	β^- /	6.1/	10–			0.0892
									0.1298
									0.7744
									1.2212
									1.9052
^{130}In		129.92486	0.29 s	β^- /10.25	10.0/	1–			
^{131m2}In			0.3 s	β^- /		(21/2+)			
^{131m1}In			0.35 s	β^- /		(1/2–)			
^{131}In		130.9268	0.28 s	β^- /9.18	6.4/	(9/2+)			0.3328
									2.433
^{132}In		131.9323	≈0.206 s	β^- /13.6	6.0/	(7–)			0.1320
					8.8/				0.2992
									0.3747
									4.0406
^{133}In		132.9383	0.165 s	β^-, (n)					
^{134}In		133.9447	0.14 s						(0.354–2.005)
^{135}In			0.09 s						
$_{50}$Sn		**118.710(7)**							
^{100}Sn		99.9394	1.0 s	β^+ /7.3	3.4/				
^{101}Sn		100.9361	3. s	β^+ /9.					
^{102}Sn		101.9243	3.8 s	β^+ /5.8					
^{103}Sn		102.9281	7. s	β^+ /7.7					
^{104}Sn		103.9232	21. s	β^+, EC/4.5					
^{105}Sn		104.9214	28. s	β^+ /6.3					In-x-ray
									(0.2879–3.819)
^{106}Sn		105.91688	2.0 m	β^+ /20/3.18					ann.rad./
				EC/80/					In k x-ray
									0.3865
									0.4772
^{107}Sn		106.9157	2.92 m	EC/5.0	1.2/				0.4218
				β^+ /					0.6105
									0.6785
									1.0013
									1.1290
									1.542
^{108}Sn		107.91196	10.3 m	β^+ /1/2.09	0.36/	0+			In k x-ray
				EC/99/					0.2724
									0.3965
									(0.105–1.68)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{109}Sn		108.91129	18.0 m	β^+ /9/3.85	1.52/	7/2+	–1.08	+0.3	ann.rad./
				EC/91/					In k x-ray
									0.6498
									1.0992
^{110}Sn		109.90785	4.1 h	EC/0.64		0+			In k x-ray
									0.283
^{111}Sn		110.90774	35. m	β^+ /31/2.45	1.5/	7/2+	+0.61	+0.2	In k x-ray
				EC/69/					0.7620
									1.1530
									1.9147
^{112}Sn	0.97(1)	111.904822				0+			
^{113m}Sn			21.4 m	I.T./92/0.077		7/2+			Sn k x-ray
				EC/8/					In x-ray
									0.0774
^{113}Sn		112.905174	115.1 d	EC/1.036		1/2+	–0.879		In k x-ray
									0.25511
									0.39169
^{114}Sn	0.66(1)	113.902783				0+			
^{115}Sn	0.34(1)	114.903347				1/2+	–0.9188		
^{116}Sn	14.54(9)	115.901745				0+			
^{117m}Sn			14.0 d	I.T./0.3146		11/2–	–1.396	–0.4	Sn k x-ray
									0.15856
^{117}Sn	7.68(7)	116.902955				1/2+	–1.0010		
^{118}Sn	24.22(9)	117.901608				0+			
^{119m}Sn			293. d	I.T./0.0896		11/2–	–1.4	0.21	Sn k x-ray
									0.02387
^{119}Sn	8.59(4)	118.903311				1/2+	–1.0473		
^{120}Sn	32.58(9)	119.902199				0+			
^{121m}Sn			44. y	I.T./78/0.006		11/2–	–1.388	–0.14	Sn k x-ray
				β^- /22/	0.354/				0.03715
^{121}Sn		120.904239	1.128 d	β^- /0.388	0.383/100	3/2+	0.698	–0.02	
^{122}Sn	4.63(3)	121.903441				0+			
^{123m}Sn			40.1 m	β^- /1.428	1.26/99	3/2+			0.1603
									0.3814
^{123}Sn		122.905723	129.2 d	β^- /1.404	1.42/99.4	11/2–	–1.370	+0.03	0.1603
									1.0302
									1.0886
^{124}Sn	5.79(5)	123.905275	$>2.2 \times 10^{18}$ y	b^-b^-		0+			
^{125m}Sn			9.51 m	β^- /2.387	2.03/98	3/2+			0.3321
									1.4040
^{125}Sn		124.907785	9.63 d	β^- /2.364	2.35/82	11/2–	–1.35	+0.1	1.0671
									(0.2–2.3)
^{126}Sn		125.90765	2.34×10^5 y	β^- /0.38	0.25/100	0+			0.0643
									0.0876
									0.4148
									0.6663
									0.6950
^{127m}Sn			4.15 m	β^- /3.21	2.72/	3/2+			0.4909
									1.3480
									1.5640
^{127}Sn		126.91035	2.12 h	β^- /3.20	2.42/	11/2–			0.8231
					3.2/				1.0956
									(0.120–2.84)
^{128m}Sn			6.5 s	IT/0.091		(7–)			
^{128}Sn		127.91054	59.1 m	β^- /1.27	0.48/	0+			0.4823
					0.63/				0.5573
									0.6805
^{129m}Sn			6.9 m	β^- /		11/2–			1.1611
^{129}Sn		128.9134	2.4 m	β^- /4.0		3/2+			0.6456
^{130m}Sn			1.7 m	β^- /		(7–)			0.1449
									0.8992
^{130}Sn		129.91386	3.7 m	β^- /2.15	1.10/	0+			0.0700
									0.1925
									0.7798
^{131m}Sn			1.02 m	β^- /	3.4/	11/2–			0.3043
									0.4500

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.7985
									1.2260
									(0.08–3.21)
^{131}Sn		130.9169	39. s	β^- /4.69	3.8/	3/2+			see ^{131m}Sn
^{132}Sn		131.91775	40. s	β^- /3.12	1.8/				0.0855
									0.2467
									0.3402
									0.8985
^{133}Sn		132.9236	1.44 s	β^- /7.8	7.5/	7/2–			
^{134}Sn		133.9278	1.04 s	β^- /6.8					
^{135}Sn		134.9347	0.53 s	β^-, n	/21.				0.282
									0.733–1.855
^{136}Sn		135.9393	0.25 s	β^-, n	/30.				
^{137}Sn		136.946	0.19 s	β^-, n	/≈ 58				
$_{51}$Sb		**121.760(1)**							
^{103}Sb		102.9401	>1.5 μs						
^{104}Sb		103.9363	0.5 s						
^{105}Sb		104.9315	1.1 s						
^{106}Sb		105.9288	0.6 s	β^+ /10.5					
^{107}Sb		106.9242	4.0 s	β^+ /7.9					1.280
									0.1515
									0.6666
									0.553–2.046
^{108}Sb		107.9222	7.0 s	β^+ /9.5					(0.151–1.280)
^{109}Sb		108.91814	17.3 s	β^+ /6.38	4.42/	5/2+			0.925
				EC/	4.67/				1.062
					4.33/				0.261–2.127
^{110}Sb		109.9175	24. s	β^+ /9.0	6.8/	3+			ann.rad./
				EC/					0.6365
									0.9847
									1.2117
									1.2433
^{111}Sb		110.91254	1.25 m	β^+ /87/4.47	3.3/	5/2+			ann.rad./
				EC/13 /					0.1002
									0.1545
									0.4891
									1.0326
^{112}Sb		111.91240	51.4 s	β^+ /90/7.06	4.75/	3+			ann.rad./
				EC/10/					0.6700
									0.9909
									1.2571
^{113}Sb		112.90937	6.7 m	β^+ /65/3.91	2.42/	5/2+			ann.rad./
									(0.3–3.6)
				EC/35/					Sn k x-ray
									0.3324
									0.4980
^{114}Sb		113.9091	3.49 m	β^+ /78/5.9	3.4/	3+	1.7		ann.rad./
				EC/22/					Sn k x-ray
									0.8876
									1.2999
^{115}Sb		114.90660	32.1 m	β^+ /67/3.03	1.51/	5/2+	+3.46	–0.4	ann.rad./
				EC/33/					Sn k x-ray
									0.4973
^{116m}Sb			1.00 h	β^+ /78/	1.16/	8–	2.6		ann.rad./
				EC/22/					Sn k x-ray
									0.4073
									0.5429
									0.9725
									1.2935
									(0.0998–1.501)
^{116}Sb		115.90680	16. m	β^+ /50/4.707	1.3/	3+	2.72		ann.rad./
				EC/50/	2.3/				Sn k x-ray
									0.93180
									1.29354
									(0.138–3.903)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{117}Sb		116.90484	2.80 h	β^+ /2/1.76	0.57/	5/2+	+3.4		Sn k x-ray
				EC/98/					0.1586
^{118m}Sb			5.00 h	EC/99/		8–	2.3		Sn k x-ray
									0.25368
									1.05069
									1.22964
^{118}Sb		117.905533	3.6 m	β^+ /74/3.657	2.65/	1+	2.5		ann.rad./
				EC/26/					Sn k x-ray
									1.22964
^{119}Sb		118.90395	38.1 h	EC/0.59		5/2+	+3.45	–0.4	Sn k x-ray
									0.0239
^{120m}Sb			5.76 d	EC/		8–	2.34		Sn k x-ray
									0.0898
									0.19730
									1.02301
									1.17121
^{120}Sb		119.90508	15.89 m	β^+ /41/2.68	1.72/	1+	+2.3		ann.rad./
				EC/59/					Sn k x-ray
									0.7038
									1.17121
^{121}Sb	57.21(5)	120.903822				5/2+	+3.363	–0.4	
^{122m}Sb			4.19 m	I.T./0.162		8–			Sb x-ray
									0.0614
									0.0761
^{122}Sb		121.90518	2.72 d	β^- /98/1.979	1.414/65	2–	–1.90	+0.9	0.56409
				β^+ /2/1.620	1.980/26				0.69277
									1.14050
									1.2569
^{123}Sb	42.79(5)	122.904216				7/2+	+2.550	–0.5	
^{124m2}Sb			20.3 m	I.T./0.035		8–			
^{124m1}Sb			1.6 m	I.T./80/	1.2/	5+			0.4984
				β^- /20/	1.7/				0.6027
									0.6458
									1.1010
^{124}Sb		123.905938	60.20 d	β^- /2.905	0.61/52	3–	1.2	+1.9	0.60271/97.8
					2.301/23				0.64583/7.4
									0.72277/10.5
									1.69094/48.2
									(0.0274–2.808)
^{125}Sb		124.905247	2.758 y	β^- /0.767	0.13/30	7/2+	+2.63		0.0355
					0.302/45				0.17632
					0.62/13				0.38044
									0.42786
									0.46336
									0.60060
									0.63595
^{126m2}Sb			11. s	I.T./		3–			L x-ray
									0.0227
^{126m1}Sb			19.0 m	β^- /86 /	1.9	5+			0.4148
				I.T./14 /					0.6663
									0.6950
^{126}Sb		125.90725	12.4 d	β^- /3.67	1.9	8–	1.3		0.2786
									0.4148/83.3
									0.6663/99.7
									0.6950/99
									0.7205
^{127}Sb		126.906914	3.84 d	β^- /1.581	0.89/	7/2+	2.70		0.2524
					1.10/				0.2908
					1.50/				0.4121
									0.4370
									0.6857
									0.7837
^{128m}Sb			10.1 m	β^- /96/	2.6/	5+			0.3140
				I.T./4/					0.5941
									0.7432
									0.7539
^{128}Sb		127.90917	9.1 h	β^- /4.38	2.3/	8–	1.3		0.2148

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.3141
									0.5265
									0.7433
									0.7540
^{129m}Sb			17.7 m	β^- /					0.4338
									0.6578
									0.7598
^{129}Sb		128.90915	4.40 h	β^- /2.38	0.65/	7/2–	2.82		0.0278
									0.1808
									0.3594
									0.4596
									0.5447
									0.8128
									0.9146
									1.0301
^{130m}Sb			6.5 m	β^- /2.6	2.12/				0.1023
									0.7934
									0.8394
^{130}Sb		129.91155	38.4 m	β^- /4.96	2.9/	8–			0.1823
									0.3309
									0.4680
									0.7394
									0.8394
^{131}Sb		130.9120	23.0 m	β^- /3.20	1.31/	7/2+			0.6423
					3.0/				0.6579
									0.9331
									0.9434
^{132m}Sb			2.8 m	β^- /	3.9/	4+			0.1034
									0.3538
									0.6968
									0.9739
									0.9896
^{132}Sb		131.91420	4.2 m	β^- /5.49		8–			0.1034
									0.1506
									0.6968
									0.9739
^{133}Sb		132.9152	2.5 m	β^- /4.00	1.20/	7/2+	3.00		0.4235
									0.6318
									0.8165
									1.0764
^{134m}Sb			10.4 s	β^- /	6.1	7–			
^{134}Sb		133.9206	0.8 s	β^- /8.4	8.4	0–			0.1152
									0.2970
									0.7063
									1.2791
^{135}Sb		134.9252	1.71 s	β^- /8.12		7/2+			1.127
									1.279
^{136}Sb		135.9301	0.82 s	β^- /9.3					
^{137}Sb		136.9353	>0.15 μs						
^{138}Sb		137.9410	>0.15 μs						
^{139}Sb		138.946	>0.15 μs						
$_{52}$Te		**127.60(3)**							
^{106}Te		105.9377	0.06 ms	α/4.32	/100				
^{107}Te		106.9350	3.1 ms	α/ 70/	3.86(1)/				
				β^+, EC/10.1					
^{108}Te		107.9295	2.1 s	α /68 /	3.314(4)/	0+			
				β^+, EC/32 /6.8					
^{109}Te		108.9275	4.6 s	β^+ EC/96 /8.7					0.7523
				α/4 /	3.107(4)/				0.287–2.045
^{110}Te		109.9224	19. s	β^+, EC/4.5		0+			ann.rad./
									0.2191
									0.6059
^{111}Te		110.9211	19.3 s	β^+, EC/8.0		(7/2+)			ann.rad./
									0.267
									0.322

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.341
^{112}Te		111.9171	2.0 m	β^+, EC/4.3		0+			ann.rad./
									0.2962
									0.3727
									0.4187
^{113}Te		112.9154	1.7 s	β^+ /85/5.7	4.5/	(7/2+)			ann.rad./
				EC/15/					Sb k x-ray
									0.8144
									1.0181
									1.1812
^{114}Te		113.9125	15. m	β^+ /40/3.2		0+			ann.rad./
				EC/60/					Sb k x-ray
									0.0838
									0.0903
^{115m}Te			6.7 m	β^+ /45/		(1/2+)			ann.rad./
				EC/55/					Sb k x-ray
									0.7236
									0.7704
^{115}Te		114.9116	5.8 m	β^+ /45/4.6	2.7/	7/2+			ann.rad./
				EC/55/					Sb k x-ray
									0.7236
									1.3268
									1.3806
									(0.22–2.7)
^{116}Te		115.9084	2.49 h	EC/1.5		0+			Sb k x-ray
									0.0937
^{117}Te		116.90864	1.03 h	EC/75/3.54	1.78/	1/2+			ann.rad./
				β^+ /25/					Sb k x-ray
									0.9197
									1.7164
									2.3000
^{118}Te		117.90583	6.00 d	EC/0.28		0+			Sb k x-ray
^{119m}Te			4.69 d	EC/		11/2–	0.89		Sb k x-ray
									0.15360
									0.2705
									1.21271
^{119}Te		118.90641	16.0 h	β^+ /2/2.293	0.627/	1/2+	0.25		ann.rad.
				EC/98/					Sb k x-ray
									0.6440
									0.6998
^{120}Te	0.09(1)	119.90403				0+			
^{121m}Te			≈ 154. d	I.T. (89%)		11/2–	0.90		Te k x-ray
				EC(11%)					0.2122
^{121}Te		120.90494	16.8 d	EC/1.04		1/2+			Sb k x-ray
									0.5076
									0.5731
^{122}Te	2.55(12)	121.903056				0+			
^{123m}Te			119.7 d	I.T./0.247		11/2–	–0.93		Te k x-ray
									0.1590/84.1
^{123}Te	0.89(3)	122.904271	$>5.3 \times 10^{16}$ y	EC/0.051		1/2+	–0.73695		
^{124}Te	4.74(14)	123.902819				0+			
^{125m}Te			58. d	I.T./0.145		11/2–	–0.99	–0.06	Te k x-ray
									0.0355
^{125}Te	7.07(15)	124.904424				1/2+	–0.8885		
^{126}Te	18.84(25)	125.903305				0+			
^{127m}Te			109. d	I.T./98/0.088		11/2–	–1.04		Te k x-ray
				β^- /2/0.77					0.0883
^{127}Te		126.905217	9.4 h	β^- /0.698	0.696/	3/2+	0.64		0.3603
^{128}Te	31.74(8)	127.904462	2.2×10^{24} y	$\beta^-\beta^-$		0+			
^{129m}Te			33.6 d	I.T./63/0.105		11/2–	–1.09		Te k x-ray
				β^- /37/	1.60/				0.45984
									0.6959
^{129}Te		128.906596	1.16 h	β^- /1.498	0.99/9	3/2+	0.70	0.06	0.0278
					1.45/89				0.45984
									0.48728
^{130}Te	34.08(62)	129.906223	8×10^{20} y	$\beta^-\beta^-$		0+			
^{131m}Te			1.35 d	β^- /78/2.4	0.42/	11/2–	–1.04		0.0811

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				I.T./22/0.18					0.1021
									0.14973
									0.77369
									0.79375
									0.85225
^{131}Te		130.908522	25.0 m	β^- /2.233	1.35/12	3/2+	0.70		0.14973
					1.69/22				0.45327
					2.14/60				0.49269
^{132}Te		131.90852	3.26 d	β^- /0.51	0.215	0+			0.049725
									0.11198
									0.22830
^{133m}Te			55.4 m	β^- /82/	2.4/30	11/2–			Te k x-ray
				I.T./18/0.334					0.0949
									0.1689
									0.3121
									0.3341
^{133}Te		132.9109	12.4 m	β^- /2.94	2.25/25	3/2+			0.3121
					2.65				0.4079
									1.3334
^{134}Te		133.9116	42. m	β^- /1.51	0.6/	0+			0.7672/29
					0.7/				0.0794–0.9255
^{135}Te		134.9165	19.0 s	β^- /6.0	5.4/				0.267
					6.0				0.603
									0.870
^{136}Te		135.92010	17.5 s	β^- /5.1	2.5/	0+			2.0779/25
									0.0873–3.235
^{137}Te		136.9253	2.5 s	β^- /98 /6.9	6.8	7/2–			0.2436
				n/2 /					
^{138}Te		137.9292	1.4 s	β^- /6.4					
^{139}Te		138.9347	>0.15 μs						
^{140}Te		139.9387	>0.15 μs						
^{141}Te		140.9444	>0.15 μs						
^{142}Te		141.949	>0.15 μs						
$_{53}$I		**126.90447(3)**							
^{108}I		107.9436	0.04 s	α/91/4.	3.95				
^{109}I		108.9382	0.11 ms	p					0.593/100
									0.717/63
									0.496–1.057
^{110}I		109.9346	0.65 s	β^+, EC/83/11.4					ann.rad./
				α/17/≈3.6	3.457(10)/				
				p/11/					
^{111}I		110.9303	2.5 s	β^+, E../8.5					ann.rad./
									0.2665
									0.3215
									0.3412
^{112}I		111.9280	3.4 s	β^+, EC/10.2					ann.rad./
									0.6889
									0.7869
^{113}I		112.9237	5.9 s	β^+, EC/7.6					ann.rad./
									0.4625/100
									0.6224/74
									0.0550–1.422
^{114}I		113.9219	2.1 s	β^+, EC/8.7					ann.rad./
									0.6826
									0.7088
^{115}I		114.9188	1.3 m	β^+, EC/6.7		5/2+			ann.rad./
									0.275
									0.284
									0.460
									0.709
^{116}I		115.9167	2.9 s	β^+ /97/7.8	6.7/	1+			ann.rad./
				EC/3/					0.5402
									0.6789
^{117}I		116.9136	2.22 m	β^+, EC/4.7	3.2/	(5/2+)	3.1		ann.rad./
									0.2744

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.3259
^{118m}I			8.5 m	β^+, EC/	4.9/	7–	4.2		ann.rad./
				I.T.					0.104
									0.5998
									0.6052
									0.6138
^{118}I		117.9134	14. m	β^+, EC/7.0		2–	2.0		ann.rad./
									0.5448
									0.6052
									1.3384
^{119}I		118.9102	19. m	β^+ /54/3.5	2.4/	(5/2+)	+2.9		ann.rad./
				EC/46/					Te k x-ray
									0.2575
^{120m}I			53. m	β^+ /80/	3.8		4.2		ann.rad.
				EC/20/					Te k x-ray
									0.4257
									0.5604
									0.6147
									1.3459
^{120}I		119.91005	1.35 h	β^+ /56/5.62	4.03	2–	1.23		ann.rad./
				EC/	4.60				Te k x-ray
									0.5604
									0.6411
									1.5230
									(0.43–3.1)
^{121}I		120.90737	2.12 h	β^+ /13/2.27	1.2/	5/2+	2.3		ann.rad./
				EC/87/					Te k x-ray
									0.2122
									(0.14–1.1)
^{122}I		121.90760	3.6 m	β^+ /4.234	3.1/	1+	+0.94		ann.rad./
				EC/					Te k x-ray
									0.5641
^{123}I		122.905605	13.2 h	EC/1.242		5/2+	2.82		Te k x-ray
									0.1590
^{124}I		123.906211	4.18 d	β^+ /23/3.160	1.54/	2–	1.44		ann.rad./
				EC/77/	2.14/				Te k x-ray
					0.75/				0.6027/62.9
									0.7228/10.3
									1.6910/11.2
									(0.31–1.73)
^{125}I		124.904624	59.4 d	EC/0.1861		5/2+	2.82	–0.89	Te k x-ray
									0.0355
^{126}I		125.905619	13.0 d	EC/		2–	1.44		ann.rad./
				β^+ /2.155	1.13/				Te k x-ray
				β^- /1.258/47	0.87/				0.3887
					1.25/				0.6622
^{127}I	100.	126.904468				5/2+	+2.8133	–0.79	
^{128}I		127.905805	25.00 m	β^- /2.118	2.13/	1+			Te k x-ray
				EC/1.251					0.44287
									0.52658
^{129}I		128.904988	1.7×10^7 y	β^- /0.194	0.15/	7/2+	+2.621	–0.55	Xe k x-ray
									0.0396
^{130m}I			9.0 m	I.T./83/0.048		2+			I k x-ray
				β^- /17/					0.5361
^{130}I		129.906674	12.36 h	β^- /2.949	1.04/	5+	3.35		0.4180
					0.62				0.5361
									0.6685
									0.7395
^{131}I		130.906125	8.021 d	β^- /0.971	0.606/	7/2+	+2.742	–0.40	0.08017
									0.28431
									0.36446
									0.63699
^{132m}I			1.39 h	IT		8–			
^{132}I		131.90800	2.28 h	β^- /14/3.58	0.80/	4+	3.09	0.09	I k x-ray
				I.T./86/	1.03/				0.0980
					1.2/				0.5059
					1.6/				0.52264

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
					2.16/				0.63019
									0.6506
									0.66768
									0.77260
									0.95457
^{133m}I			9. s	I.T./1.63		19/2–			I kx-ray
									0.0730
									0.6474
									0.9126
^{133}I		132.90781	20.8 h	β^- /1.77	1.24/85	7/2+	+2.86	–0.27	0.51056
									0.52989
									0.87537
^{134m}I			3.7 m	I.T./98/0.316		8–			I k x-ray
				β^- /2/					0.0444
									0.2719
^{134}I		133.9099	52.6 m	β^- /4.05	1.2/	4+			0.1354
									0.84702
									0.88409
^{135}I		134.91005	6.57 h	β^- /2.63	0.9/	7/2+	2.94		0.2884
					1.3/				0.41768
									0.52658
									1.13156
									1.26046
^{136m}I			47. s	β^- /	4.7/	6–			0.1973
					5.2/				0.3468
									0.3701
									0.3814
									1.3130
									(0.16–2.36)
^{136}I		135.91466	1.39 m	β^- /6.93	4.3/	2–			0.3447
					5.6/				1.3130
									1.3211
									2.2896
									(0.3–6.1)
^{137}I		136.91787	24.5 s	β^- /5.88	5.0/	(7/2+)			0.6010
									1.2180
									1.2201
									1.3026
									1.5343
									(0.25–4.4)
^{138}I		137.9224	6.5 s	β^- /7.8	6.9/	2–			0.4836
					7.4/				0.5888
									0.8752
									(0.4–5.3)
^{139}I		138.92609	2.30 s	β^- /6.81					0.192
				n/					0.198
									0.273
									0.382
									0.386
									0.468
									0.683
									1.313
^{140}I		139.9310	0.86 s	β^- /8.8		(3)			0.372
				n/					0.377
									0.457
^{141}I		140.9351	0.45 s	β^- /7.8					
^{142}I		141.9402	≈0.2 s	β^-					
^{143}I		142.9441	>0.15 μs						
^{144}I		143.9496	>0.15 μs						
$_{54}$Xe		**131.293(6)**							
^{110}Xe		109.9445	0.2 s	β^+ /9.2					
				α	/≈ 64				
^{111m}Xe			0.9 s	EC, β^+					
^{111}Xe		110.9416	0.7 s	EC, β^+ /10.6					
				α/	3.58(1)/				

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{112}Xe		111.9357	3. s	EC, β^+ /7.2	α/0.8/				
^{113}Xe		112.9334	2.8 s	EC, β^+ /9.1					
^{114}Xe		113.9281	10.0 s	β^+, EC/5.9		0+			ann.rad./
									0.1031
									0.1616
									0.3085
									0.6826
									0.7088
^{115}Xe		114.9270	18. s	β^+, EC/7.6		(5/2+)			ann.rad./
^{116}Xe		115.9214	56. s	β^+, EC/4.3	3.3/	0+			ann.rad./
									0.1042
									0.1916
									0.2477
									0.3107
									0.4127
^{117}Xe		116.9206	1.02 m	β^+, EC/6.5		(5/2+)	–0.594	+1.16	ann.rad./
									0.2214
									0.5190
									0.6389
									0.6613
^{118}Xe		117.917	≈ 4. m	β^+, EC/3.	2.7/	0+			ann.rad./
									0.0535
									0.0600
									0.1199
^{119}Xe		118.9156	5.8 m	β^+, EC/5.0	3.5/	7/2+	–0.654	+1.31	0.0873
									0.1000
									0.2318
									0.4615
^{120}Xe		119.91216	40. m	β^+, EC/97/1.96		0+			I k x-ray
				β^+ /3/					0.0251
									0.0726
									0.1781
									(0.1–1.03)
^{121}Xe		120.91138	39. m	β^+ /44/3.73	2.8/	5/2+	–0.701	+1.33	ann.rad./
				EC/56/					I k x-ray
									0.1328
									0.2527
									0.4452
									(0.1–3.1)
^{122}Xe		121.9086	20.1 h	EC/0.9		0+			I k x-ray
									0.3501
^{123}Xe		122.90848	2.00 h	β^+ /23/2.68	1.51/	1/2+	–0.150		ann.rad./
				EC/77/					I k x-ray
									0.1489
									0.1781
									(0.1–2.1)
^{124}Xe	0.0953(27)	123.905895	$>10^{17}$ y	$\beta^-\beta^-$					
^{125m1}Xe			57. s	I.T./0.252		(9/2–)	–0.745	+0.42	Xe k x-ray
									0.1111
									0.141
^{125}Xe		124.906398	17.1 h	EC/1.653	0.47/	1/2+	–0.269		I k x-ray
									0.1884
									0.2434
^{126}Xe	0.0890(14)	125.90427				0+			
^{127m1}Xe			1.15 m	I.T./0.297		(9/2–)	–0.884	+0.69	Xe k x-ray
									0.1246
									0.1725
^{127}Xe		126.905179	36.34 d	EC/0.662		1/2+	–0.504		I k x-ray
									0.1721
									0.2029
									0.3750
^{128}Xe	1.910(22)	127.903531				0+			
^{129m1}Xe			8.89 d	I.T./0.236		11/2–	–0.891	+0.64	Xe k x-ray
									0.0396
									0.1966
^{129}Xe	26.40(18)	128.904780				1/2+	–0.7780		
^{130}Xe	4.071(53)	129.903509				0+			

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{131m}Xe		11.9 d	I.T./0.164			11/2–	–0.9940	+0.73	Xe k x-ray
									0.16398
^{131}Xe	21.233(62)	130.905083				3/2+	+0.69186	–0.12	
^{132}Xe	26.9087(680)	131.904155				0+			
^{133m}Xe			2.19 d	I.T./0.233		11/2–	–1.082	+0.77	Xe k x-ray
									0.23325
^{133}Xe		132.905906	5.243 d	β^- /0.427	0.346/99	3/2+	+0.813	+0.14	Cs k x-ray
									0.080998
									0.1606
^{134}Xe	10.436(29)	133.905395	$>1.1 \times 10^{16}$ Y	$\beta^-\beta^-$	0+				
^{135m}Xe			15.3 m	I.T./		11/2–	1.103	+0.62	Xe k x-ray
									0.52658
^{135}Xe		134.90721	9.10 h	β^-/1.15	0.91/	3/2+	0.903	+0.21	0.24975
									0.60807
^{136}Xe	8.858(33)	135.90722	$>0.8 \times 10^{21}$ y	$\beta^-\beta^-$		0+			
^{137}Xe		136.91156	3.82 m	β^- /4.17	4.1/	7/2–	–0.970	–0.49	0.45549
					3.6/				0.8489
									0.9822
									1.2732
									1.7834
									2.8498
^{138}Xe		137.91399	14.1 m	β^- /2.77	0.8/	0+			0.1538
					2.4/				0.2426
									0.2583
									0.4345
									1.76826
									2.0158
^{139}Xe		138.91879	39.7 s	β^- /5.06	4.5/		–0.304	+0.40	0.1750
					5.0/				0.2186
									0.2965
									(0.1–3.37)
^{140}Xe		139.9216	13.6 s	β^- /4.1	2.6	0+			0.0801
									0.6220
									0.8055
									1.4137
									(0.04–2.3)
^{141}Xe		140.9267	1.72 s	β^- /6.2	6.2/	5/2+	+0.010	–0.58	0.1187
									0.9095
									(0.05–2.55)
^{142}Xe		141.9297	1.22 s	β^- /5.0	3.7/	0+			0.0338
					4.2/				0.0729
									0.2038
									0.3091
									0.4145
									0.5382
									0.5718
									0.6181
									0.6448
^{143m}Xe			0.96 s	b^-					
^{143}Xe		142.9352	0.30 s	β^- /7.3			–0.460	+0.93	
^{144}Xe		143.9385	1.2 s	β^- /6.1					
^{145}Xe		144.9437	0.9 s	β^-, (n)					
^{146}Xe		145.9473	>0.15 μs						
^{147}Xe		146.9530	>0.15 μs						
$_{55}$Cs		**132.90545(2)**							
^{112}Cs		111.9503	0.5 ms	p	0.81				
^{113}Cs		112.9445	17. μs	p	0.96				
^{114}Cs		113.9408	0.58 s	β^+, EC/11.8		1+			ann.rad./
									0.6826
									0.7088
^{115}Cs		114.9359	≈ 1.4 s	β^+, EC/8.4					ann.rad./
^{116m}Cs			0.7 s	β, EC/					ann.rad./
									0.3935
^{116}Cs		115.9330	3.8 s	β^+, EC/10.8					ann.rad./
									0.3935

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.5243
									0.6151
									0.6223
^{117m}Cs			6.5 s	β^+, EC/					
^{117}Cs		116.9286	≈ 8.4 s	β^+, EC/7.5					ann.rad./
^{118m}Cs			17. s	β^+, EC/			5.		
^{118}Cs		117.92654	14. s	β^+, EC/9.		2	+3.88	+1.4	ann.rad./
									0.3372
									0.4727
									0.5865
									0.5906
^{119m}Cs			29. s			3/2	+0.84	+0.9	
^{119}Cs		118.92234	43. s	β^+, EC/6.3		9/2+	+5.5	+2.8	ann.rad./
									0.169
									0.176
									0.224
									0.257
^{120m}Cs			60. s	β^+, EC/					
^{120}Cs		119.92066	64. s	β^+, EC/7.92		2+	+3.87	+1.45	ann.rad./
									0.3224
									0.4735
									0.5534
									(0.3–3.28)
^{121m}Cs			2.0 m	I.T./60/		(9/2+)	+5.41	+2.7	ann.rad./
				β^+ /40/	4.4				0.1794
									0.1961
^{121}Cs		120.91718	2.3 m	β^+, EC/5.40	4.38/	3/2+	+0.77	+0.84	ann.rad./
									0.1537
									(0.08–0.56)
^{122m2}Cs			4.4 m	β^+, EC		8–	+4.77	+3.3	ann.rad./
^{122m1}Cs			0.36 s	IT					0.3311
									0.4971
									0.6385
									(0.27–2.22)
^{122}Cs		121.91614	21. s	β^+, EC/7.1	5.8/	(1+)	–0.133	–0.19	ann.rad./
									0.3311
									0.5120
									0.8179
^{123m}Cs			1.6 s	I.T./		11/2–			Cs k x-ray
									0.0946
^{123}Cs		122.91299	5.87 m	β^+ /75/4.20	3.0/	1/2+	+1.38		ann.rad./
				EC/25/					Xe k x-ray
									0.0974
									0.5964
^{124m}Cs			6.3 s	IT		7+			
^{124}Cs		123.91225	30. s	β^+ /9 /5.92	≈5.	1+	+0.673	–0.74	ann.rad./
				EC/8 /					Xe k x-ray
									0.3539
									0.4925
									0.9418
^{125}Cs		124.90972	45. m	β^+ /40/3.09	2.06/	1/2+	+1.41		ann.rad./
				EC/60/					Xe k x-ray
									0.112
									0.526
^{126}Cs		125.90945	1.64 m.	β^+ /81/4.83	3.4	1+	+0.78	–0.68	ann.rad./
				EC/19/	3.7/				Xe k x-ray
									0.3886
									0.4912
									0.9252
^{127}Cs		126.90741	6.2 h	β^+ /96/2.08	0.65/	1/2+	+1.46		Xe k x-ray
				EC/4/	1.06				0.1247
									0.4119
^{128}Cs		127.90775	3.62 m	β^+ /68/3.930	2.44/	1+	+0.97	–0.57	ann.rad./
				EC/32 /	2.88/				Xe k x-ray
									0.4429
^{129}Cs		128.90606	1.336 d	EC/1.195		1/2+	+1.49		Xe k x-ray
									0.3719

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.4115
^{130m}Cs			3.5 m	IT, β^+, EC		5–	+0.629	+1.45	
^{130}Cs		129.90671	29.21 m	β^+ /55/2.98	1.98/	1+	+1.46	–0.06	ann.rad./
				EC/43/					Xe k x-ray
				β^- /1.6/0.37	0.44/1.6				0.5361
^{131}Cs		130.90546	9.69 d	EC/0.352		5/2+	+3.54	–0.58	Xe k x-ray
^{132}Cs		131.906430	6.48 d	EC/98/		2–	+2.22	+0.51	Xe k x-ray
				β^+ /0.3/2.120					0.4646
				β^- / /1.280					0.6302
									0.66769
^{133}Cs	100.	132.905447				7/2+	+2.582	–0.0037	
^{134m}Cs			2.91 h	I.T./0.139		8–	+1.098	+1.0	Cs k x-ray
									0.12749
^{134}Cs		133.906714	2.065 y	β^- /2.059	0.089/27	4+	+2.994	+0.39	0.56327
					0.658/70				0.56935
				EC/1.22					0.60473
									0.79584
^{135m}Cs			53. m	I.T./1.627		19/2–	+2.18	+0.9	0.7869
									0.8402
^{135}Cs		134.905972	2.3×10^6 y	β^- /0.269	0.205/100	7/2+	+2.732	+0.05	
^{136m}Cs			19. s	I.T./		8	+1.32	+0.7	
^{136}Cs		135.907307	13.16 d	β^- /2.548	0.341/	5+	+3.71	+0.2	0.06691
									0.34057
									0.81850
									1.04807
^{137}Cs		136.907085	30.2 y	β^- /1.176	0.514/95	7/2+	+2.84	+0.05	Ba k x-ray
									0.66164
^{138m}Cs			2.9 m	I.T./75	/0.080	6–	+1.71	–0.40	Cs k x-ray
				β^- /25 /	3.3				0.0799
									0.1917
									0.4628
									1.43579
^{138}Cs		137.91101	32.2 m	β^- /5.37	2.9/	3–	+0.700	+0.12	0.1381
									0.46269
									1.00969
									1.43579
									2.21788
^{139}Cs		138.913359	9.3 m	β^- /4.213	4.21	7/2+	+2.70	–0.07	0.6272
									1.2832
									(0.4–3.66)
^{140}Cs		139.91727	1.06 m	β^- /6.22	5.7/	1–	+0.13390	–0.11	0.5283
					6.21/				0.6023
									0.9084
									(0.41–3.94)
^{141}Cs		140.92005	24.9 s	β^- /5.26	5.20/	7/2+	+2.44	–0.4	Ba k x-ray
									0.0485
									0.5616
									0.5887
									1.1940
									(0.05–3.33)
^{142}Cs		141.92430	1.8 s	β^- /7.31	6.9/				0.3596
					7.28				0.9668
									1.1759
									1.3265
^{143}Cs		142.92732	1.78 s	β^- /6.24	6.1	(3/2+)	+0.87	+0.47	0.1955
									0.2324
									0.3064
									(0.17–1.98)
^{144}Cs		143.93203	1.01 s	β^- /8.47	8.46/	1	–0.546	+0.30	0.1993
					7.9/				0.5598
									0.6392
									0.7587
^{145}Cs		144.93541	0.59 s	β^- /7.89	7.4/	3/2+	+0.784	+0.6	0.1126
					7.9/				0.1755
									0.1990
^{146}Cs		145.94024	0.322 s	β^-, (n)/9.38	≈ 9.0	2–	–0.515	+0.22	
^{147}Cs		146.9439	0.227 s	β^-, (n)/9.3					

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{148}Cs		147.9490	0.15 s	β^-, (n)/10.5					
^{149}Cs		148.9527	>50 ms						
^{150}Cs		149.9580	>50 ms						
^{151}Cs		150.9620	>50 ms						
$_{56}$Ba		**137.327(7)**							
^{114}Ba		113.9509	0.43 s	β^+, (p)	p/20				
				a	/0.9				
^{115}Ba		114.948	0.45 s	β^+, (p)	p/<15				
^{116}Ba		115.9417	1.3 s	β^+, (p)	p/3				
^{117}Ba		116.9377	1.8 s	β^+, (p), EC/8.4	p/13	(3/2–)			(0.0457–0.364)
^{118}Ba		117.9466	5.2 s	β^+,					(0.040–0.156)
^{119}Ba		118.931	5.4 s	β^+, EC/8.					
^{120}Ba		119.9260	24. s	β^+, EC/5.0		0+			ann.rad./
									0.140
									(0.075–0.146)
^{121}Ba		120.9245	30. s	β^+, EC/6.8		5/2	+0.660	+1.8	ann.rad./
^{122}Ba		121.9203	2.0 m	β^+, EC/3.8		0+			ann.rad./
^{123}Ba		122.9189	2.7 m	β^+, EC/5.5			–0.68	+1.5	ann.rad./
									0.0306
									0.0927
									0.1161
									0.1235
^{124}Ba		123.91509	12. m	β^+, EC/2.65					ann.rad./
									0.1695
									0.1888
									1.2160
^{125m}Ba			8. m	β^+, EC/	4.5		0.174		
^{125}Ba		124.9146	3.5 m	β^+, EC/4.6	3.4	1/2+	+0.18		ann.rad./
									0.0550
									0.0776
									0.0854
									0.1409
^{126}Ba		125.91124	1.65 h	β^+ /2/1.67		0+			Cs k x-ray
				EC/98 /					0.2179
									0.2336
									0.2576
^{127m}Ba			1.9 s	IT		7/2–	–0.723	1.6	
^{127}Ba		126.9111	12.9 m	β^+ /54/3.5		1/2+	+0.083		ann.rad./
				EC/46/					Cs k x-ray
									0.1148
									0.1808
									(0.07–2.5)
^{128}Ba		127.90831	2.43 d	EC/0.52		0+			Cs k x-ray
									0.27344
^{129m}Ba			2.17 h	EC/98/		7/2+	+0.93	+1.6	Cs k x-ray
				β^+ /2/					0.1769
									0.1823
									0.2023
									1.4593
^{129}Ba		128.90868	2.2 h	β^+ /20/2.43	1.42/	1/2+	–0.40		ann.rad./
				EC/80/					Cs k x-ray
									0.1291
									0.2143
									0.2208
^{130m}Ba			9.5 ms	I.T./2.475	/100.	8–	–0.04	+2.8	0.080–0.802
^{130}Ba	0.106(1)	129.90631	2.2×10^{21} y	$\beta^+\beta^+$		0+			
^{131m}Ba			14.6 m	I.T./0.187		9/2–	–0.87	+1.5	Ba k x-ray
									0.1085
^{131}Ba		130.90693	11.7 d	EC/1.37		1/2+	0.7081		Cs k x-ray
									0.12381/28.4
									0.21608/21.3
									0.49636/42.9
									(0.0549–1.171)
^{132}Ba	0.101(1)	131.905056	1.3×10^{21} y	EC EC		0+			
^{133m}Ba			1.621 d	I.T./0.288		11/2–	–0.91	+0.9	Ba k x-ray

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.2761
^{133}Ba		132.906003	10.53 y	EC/0.517		1/2+	0.7717		Cs k x-ray
									0.08099
									0.35600
^{134}Ba	2.417(18)	133.904504				0+			
^{135m}Ba			1.20 d	I.T./0.2682		11/2–	–1.00	+1.0	Ba k x-ray
									0.2682
^{135}Ba	6.592(12)	134.905684				3/2+	+0.838	+0.16	
^{136m}Ba			0.308 s	I.T./2.0305		7–			Ba k x-ray
									0.8185
									1.0481
^{136}Ba	7.854(24)	135.904571				0+			
^{137m}Ba			2.552 m	I.T./0.6617		11/2–	–0.99	+0.8	Ba k x-ray
									0.66164
^{137}Ba	11.232(24)	136.905822				3/2+	+0.9374	+0.245	
^{138}Ba	71.698(42)	137.905242				0+			
^{139}Ba		138.908836	1.396 h	β^- /2.317	2.14/27	7/2–	–0.97	–0.57	0.16585
					2.27/72				1.2544
									1.42033
^{140}Ba		139.91060	12.75 d	β^- /1.05	0.48	0+			0.16268
					1.0/				0.30485
					1.02/				0.53727
^{141}Ba		140.91441	18.3 m	β^- /3.22	2.59/	3/2–	–0.34	+0.45	0.1903
					2.73/				0.2770
									0.3042
									(0.1–2.5)
^{142}Ba		141.91645	10.7 m	β^- /2.212	1.0/	0+			0.23152
					1.10/				0.25512
									0.3090
									1.2040
^{143}Ba		142.92061	14.3 s	β^- /4.24	4.2/	5/2+	+0.44	–0.88	0.1786
									0.21148
									0.7988
									(0.17–2.4)
^{144}Ba		143.92294	11.4 s	β^- /3.1	2.4/	0+			La k x-ray
					2.9/				0.10386
									0.1566
									0.1728
									0.3882
									0.43048
^{145}Ba		144.9269	4.0 s	β^- /4.9	4.9/	(5/2–)	–0.28	+1.22	La k x-ray
									0.0918
									0.09709
^{146}Ba		145.9302	2.20 s	β^- /4.12	3.9/	0+			0.0644
									0.2513
									0.3270
									0.3329
									0.3622
^{147}Ba		146.9340	0.892 s	β^- /5.75	5.5/				
^{148}Ba		147.9377	0.64 s	β^-, n/5.11					
^{149}Ba		148.9421	0.36 s	β^-, (n)/7.3					
^{150}Ba		149.9456	0.3 s						
^{151}Ba		150.9507	>0.15 μs						
^{152}Ba		151.9542							
^{153}Ba		151.9596							
$_{57}$La		**138.9055(2)**							
^{117}La		116.950	23 ms	p	0.806/	3/2+			
^{118}La		117.946							
^{119}La		118.941							
^{120}La		119.938	2.8 s	EC, β^+ /11.					
^{121}La		120.9330	5.3 s						
^{122}La		121.9307	9. s	EC, β^+/≈ 9.7					
^{123}La		122.9262	17. s	EC/7.					
^{124}La		123.9245	30. s	EC/ ≈ 8.8		(7+)			
^{125m}La			0.39 s						

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{125}La		124.9207	1.2 m	β^+, EC/5.6		11/2–			ann.rad./
									0.0436
									0.0676
^{126m}La			<50. s						
^{126}La		125.9194	54. s	β^+, EC/7.6					ann.rad./
									0.256
									0.455
									0.117–3.853
^{127}La		126.9162	3.8 m	β^+, EC/4.7		3/2+			ann.rad./
									0.025
									0.0562
^{128}La		127.9155	5.0 m	β^+ /80/6.7		(5–)			ann.rad./
				EC/20/					Ba k x-ray
									0.2841/87
									0.4793/54
									(0.315–2.212)
^{129m}La			0.56 s	IT		(11/2–)			
^{129}La		128.91267	11.6 m	β^+ /58/3.72	2.42/	3/2+			ann.rad./
				EC/42/					Ba k x-ray
									0.1105
									0.2786
									(0.1–1.8)
^{130}La		129.9123	8.7 m	β^+ /78/5.6		3+			ann.rad./
				EC/22/					Ba k x-ray
									0.3573/81
									0.5506/27
									(0.1965–1.989)
^{131}La		130.9101	59. m	β^+ /76/3.0	1.42/	3/2+			ann.rad./
				EC/24/	1.94/				Ba k x-ray
									0.1085
									0.3658
									0.5263
^{132m}La			24. m	I.T./76/		6–			La k x-ray
				β^+, EC/24/					0.1352
									0.4645
^{132}La		131.91011	4.8 h	β^+ /40/4.71	2.6/	2–			ann.rad./
				EC/60/	3.2				Ba k x-ray
					3.7/				0.4645
									0.5671
^{133}La		132.9084	3.91 h	β^+ /4/2.2	1.2/	5/2+			Ba k x-ray
				EC/96/					0.2788
									0.2901
									0.3024
^{134}La		133.90849	6.5 m	β^+ /63/3.71	2.67/	1+			ann.rad./
				EC/37/					Ba k x-ray
									0.6047
									(0.5–1.9)
^{135}La		134.90697	19.5 h	EC/1.20		5/2+			Ba k x-ray
									0.4805
^{136}La		135.9077	9.87 m	β^+ /36/2.9	1.8/	1+			ann.rad./
				EC/64/					Ba k x-ray
									0.8185
^{137}La		136.90647	6×10^4 y	EC/0.60		7/2+	+2.70	+0.2	0.2836
^{138}La	0.090(1)	137.907107	1.06×10^{11} y			5+	+3.7136	+0.4	1.4358/65
									0.7887/35
^{139}La	99.910(1)	138.906349				7/2+	+2.7830	+0.20	
^{140}La		139.909473	1.678 d	β^- /3.762	1.35	3–	+0.73	+0.09	
					1.24/				
					1.67/				
^{141}La		140.910958	3.90 h	β^- /2.502	2.43/	7/2+			
^{142}La		141.91408	1.54 h	β^- /4.505	2.11/	2–			
					2.98/				
					4.52/				
^{143}La		142.91606	14.1 m	β^- /3.43	3.3/	7/2–			
^{144}La		143.9196	40.7 s	β^- /5.5	4.1/				
^{145}La		144.9217	24. s	β^- /4.1	4.1/	3/2+			
^{146m}La			10.0 s	β^- /6.7	5.5/	(6)			

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{146}La		145.9258	6.3 s	β^- /6.6	6.2/	(2–)			
^{147}La		146.9278	4.02 s	β^- /5.0	4.6/				
^{148}La		147.9322	1.1 s	β^- /7.26		2–			
^{149}La		148.9342	1.10 s	β^- /5.5					0.1335
									0.009–1.709
^{150}La		149.9386	0.51 s						x-ray
									(0.097–0.209)
^{151}La		150.9416	>0.15 μs						
^{152}La		151.946	>0.15 μs						
^{153}La		152.949	>0.15 μs						
^{154}La		153.954							
^{155}La		154.958							
$_{58}$Ce		**140.116(1)**							
^{119}Ce		118.953							
^{120}Ce		119.947							
^{121}Ce		120.944	1.1 s	β^+, p					
^{122}Ce		121.938							
^{123}Ce		122.936	3.8 s	β^+, EC/≈8.6					ann.rad./
^{124}Ce		123.931	6. s	EC/≈5.6					
^{125}Ce		124.929	9.6 s	β^+, EC/7.		7/2–			ann.rad./
									0.1346
									0.1666
									0.056–1.329
^{126}Ce		125.9241	50. s	EC/4.					
^{127}Ce		126.9228	32. s	β^+, EC/6.1					ann.rad./
									(0.058–1.148)
^{128}Ce		127.9189	4.1 m	β^+, EC/3.2					ann.rad./
									(0.023–0.880)
^{129}Ce		128.9187	3.5 m	β^+, EC/5.6					ann.rad./
									(0.0675–1.015)
^{130}Ce		129.9147	26. m	β^+, EC/2.2		0+			ann.rad./
									La k x-ray
									0.047–1.431
^{131m}Ce			5. m	β^+ EC					ann.rad./
									0.2304
									0.3955
									0.4213
^{131}Ce		130.9144	10. m	β^+, EC/4.0	2.8/				ann.rad.
									0.119
									0.169
									0.414
^{132m}Ce			9.4 ms	IT/2.340					0.3255
									0.10–0.955
^{132}Ce		131.9115	3.5 h	EC/1.3		0+			La k x-ray
									0.1554
									0.1821
^{133m}Ce			1.6 h	β^+, EC/		1/2+			ann.rad.
									0.0769
									0.0973
									0.5577
^{133}Ce		132.9116	5.4 h	β^+/8/2.9	1.3/	9/2–			ann.rad.
				EC/92/					0.0584
									0.1308
									0.4722
									0.5104
^{134}Ce		133.9090	3.16 d	EC/0.5		0+			La k x-ray
									0.1304
									0.1623
									0.6047
^{135m}Ce			20. s	I.T./0.446		11/2–			Ce k x-ray
									0.0826
									0.1497
									0.2134
^{135}Ce		134.90915	17.7 h	β^+/1 /2.026	0.8/	1/2+			La k x-ray
				EC/99 /					0.0345

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.2656
									0.3001
									0.6068
^{136}Ce	0.185(2)	135.90714	>0.7 × 10^{14} y	EC EC		0+			
^{137m}Ce			1.43 d	I.T./99 /0.254		11/2–	1.0		Ce k x-ray
				EC/0.8 /					0.1693
									0.2543
^{137}Ce		136.90778	9.0 h	β+/1.222		3/2+	0.96		La k x-ray
									0.4472
^{138}Ce	0.251(2)	137.90599	>0.9 × 10^{14} y	EC EC		0+			
^{139m}Ce			56.4 s	I.T./0.7542		11/2–			Ce k x-ray
									0.7542
^{139}Ce		138.90665	137.6 d	EC/0.28		3/2+	1.06		La k x-ray
^{140}Ce	88.450(51)	139.905435				0+			0.16585
^{141}Ce		140.908272	32.50 d	β–/0.581	0.436/69	7/2–	1.1		Pr k x-ray
					0.581/31				0.14544/48.0
^{142}Ce	11.114(51)	141.909241	>1.6 × 10^{17} y	β– β–		0+			
^{143}Ce		142.912382	1.38 d	β–/1.462	1.404/	3/2-	0.43		Pr k x-ray
					1.110/47				0.0574
									0.2933
^{144}Ce		143.913643	284.6 d	β–/0.319	0.185/20	0+			Pr k x-ray
					0.318/				0.0801
									0.1335
^{145}Ce		144.91723	3.00 m	β–/2.54	1.7/24	3/2–			Pr k x-ray
					1.3				0.0627
									0.7245
^{146}Ce		145.9187	13.5 m	β–/1.04	0.7/90	0+			Pr k x-ray
									0.0986
									0.2182
									0.3167
									0.0930
^{147}Ce		146.9225	56. s	β–/3.29	3.3/				0.2687
^{148}Ce		147.9244	56. s	β–/2.1	1.66/	0+			0.0904
									0.0985
									0.1212
									0.2918
^{149}Ce		148.9283	5.2 s	β–/4.2					0.0577
									0.0864
									0.3800
									0.1099
^{150}Ce		149.9302	4.4 s	β–/3.0					0.0526
^{151}Ce		150.9340	1.0 s	β–/5.3					Pr k x-ray
^{152}Ce		151.9366	1.4 s	β–/4.4					0.098
									0.115
^{153}Ce		152.9406	>0.15 μs						
^{154}Ce		153.943	>0.15 μs						
^{155}Ce		154.947	>0.15 μs						
^{156}Ce		155.951							
^{157}Ce		156.956							
$_{59}$Pr		**140.90765(2)**							
^{121}Pr		120.955	0.6 s						
^{122}Pr		121.952							
^{123}Pr		122.946							
^{124}Pr		123.943	1.2 s	β+, EC/12.					ann.rad./
^{125}Pr		124.9378	≈ 3.3 s	β+					ann.rad./
									0.1358
^{126}Pr		125.9353	3.1 s	β+, EC/≈10.4					ann.rad./
									(0.170–0.985)
^{127}Pr		126.9308	4.2 s	β+ /≈7.5					ann.rad./
									(0.028–0.8949)
^{128}Pr		127.9288	3.0 s	β+, EC/≈9.3					ann.rad./
									0.207/100
									0.400–1.373
^{129}Pr		128.9249	32 s	β+, EC/5.8					ann.rad./

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									(0.0395–1.865)
^{130}Pr		129.9234	40. s	β^+, EC/8.1					ann.rad./
^{131m}Pr			5.7 s						(0.06–0.16)
^{131}Pr		130.9201	1.7 m	β^+, EC/5.3				≈5.5	ann.rad./
									(0.059–0.980)
^{132}Pr		131.9191	1.6 m	β^+, EC/7.1					ann.rad./
									0.325
									0.496
									0.533
^{133m}Pr			1.1 s	IT/0.192					0.1305
									0.0617
^{133}Pr		132.9162	6.5 m	β^+, EC/4.3		5/2+			ann.rad./
									0.074
									0.1343
									0.2419
									0.3156
									0.3308
									0.4650
^{134m}Pr			≈ 11. m	β^+, EC/					ann.rad./
									0.294
									0.460
									0.495
									0.632
^{134}Pr		133.9157	17. m	β^+, EC/6.2		2+			ann.rad./
									0.294
									0.495
^{135}Pr		134.9131	24. m	β^+, EC/3.7	2.5/	3/2+			ann.rad./
									0.0826
									0.2135
									0.2961
									0.5832
^{136}Pr		135.91265	13.1 m	β^+ /57 /5.13	2.98/	2+			ann.rad./
				EC/43					Ce k x-ray
									0.5398
									0.5522
^{137}Pr		136.91068	1.28 h	β^+ /26 /2.70	1.68/	5/2+			ann.rad./
				EC/74 /					Ce k x-ray
									0.4339
									0.5140
									0.8367
									(0.16–1.8)
^{138m}Pr			2.1 h	β^+ /24 /	1.65/	7–			ann.rad./
				EC/76 /					Ce k x-ray
									0.3027
									0.7887
									1.0378
									(0.07–2.0)
^{138}Pr		137.91075	1.45 m	β^+ /75 /4.44	3.42/	1+			ann.rad./
				EC/25 /					Ce k x-ray
									0.7887
^{139}Pr		138.90893	4.41 h	β^+ /8 /2.129	1.09/	5/2+			ann.rad./
				EC/92 /					Ce k x-ray
									0.2551
									1.3473
									1.6307
^{140}Pr		139.90907	3.39 m	β^+ /51 /3.39	2.37/	1+			ann.rad./
				EC/49 /					Ce k x-ray
									0.3069
									1.5965
^{141}Pr	100.	140.907648				5/2+	+4.275	–0.08	
^{142m}Pr			14.6 m	I.T./0.004	c.e./	5–	2.2		
^{142}Pr		141.910041	19.12 h	β^- /2.162	0.58/4	2–	+0.234	+0.030	0.5088
				EC/0.744	2.16/96				1.57580
^{143}Pr		142.910813	13.57 d	β^- /0.934	0.933/	7/2+	+2.70	+0.8	0.7420
^{144m}Pr			7.2 m	IT/99+/0.059		3–			Pr k x-ray
				β^- /					0.0590
									0.6965

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.8142
^{144}Pr		143.913301	17.28 m	β^- /2.998	0.807/1	0–			0.69649
					2.30/				1.48912
					2.996/98				2.18562
^{145}Pr		144.91451	5.98 h	β^- /1.81	1.80/97	7/2+			0.0725
									0.6758
									0.7483
^{146}Pr		145.9176	24.2 m	β^- /4.2	2.2/30	2–			0.4539/48
					3.7/10				1.5247
					4.2/40				
^{147}Pr		146.91898	13.4 m	β^- /2.69	1.5/	3/2+			0.3146/24.
					2.1/				0.5779/16
									0.6413/19.
^{148m}Pr			2.0 m	β^- /	4.0/	(4)			0.3016
					3.8/				0.4506
									0.6975
^{148}Pr		147.9222	2.27 m	β^- /4.9	4.8/	1^-			0.3017
					4.5/				
^{149}Pr		148.92379	2.3 m	β^- /3.40	3.0	$(5/2^+)$			0.1085
									0.1385
									0.1651
^{150}Pr		149.9270	6.2 s	β^- /5.7		1^-			0.1302
					≈5.5				0.8044
									0.8527
^{151}Pr		150.9283	22.4 s	β^- /4.2					
^{152}Pr		151.9319	3.2 s	β^- /6.7		4^+			0.0726
									0.164
									0.285
^{153}Pr		152.9339	4.3 s	β^- /5.5					
^{154}Pr		153.9381	2.3 s	β^- /7.9					
^{155}Pr		154.9400							
^{156}Pr		155.944							
^{157}Pr		156.947							
^{158}Pr		157.952							
^{159}Pr		158.955							
$_{60}$Nd		**144.24(3)**							
^{125}Nd			0.6 s	β^+, p					
^{126}Nd		125.943							
^{127}Nd		126.941	1.8 s	β^+, EC/9.		(5/2)			ann.rad./
^{128}Nd		127.935	4. s	β^+, EC/6.					ann.rad./
^{129}Nd		128.933	4.9 s	β^+, EC/8.		5/2(–)			ann.rad./
									(0.091–0.875)
^{130}Nd		129.929	28. s	β^+, EC/5.					ann.rad./
^{131}Nd		130.9271	0.5 m	β^+, EC/6.6					ann.rad./
									(0.09–0.36)
^{132}Nd		131.9231	1.5 m	β^+, EC/3.7					ann.rad./
									(0.099–0.567)
^{133}Nd		132.9222	1.2 m	β^+, EC/5.6					ann.rad./
									(0.06–0.37)
^{134}Nd		133.9187	≈ 8.5 m	β^+ /17 /2.8		0+			ann.rad./
				EC/83 /					Pr k x-ray
									0.1631/58
									(0.09–1.00)
^{135m}Nd			5.5 m	β^+ /					
^{135}Nd		134.9182	12. m	β^+ /65 /4.8		9/2–	–0.78	+2.0	ann.rad./
				EC/35 /					Pr k x-ray
									0.0415/23.
									0.204/51.
									(0.11–1.8)
^{136}Nd		135.9150	50.6 m	EC/94 /2.21	1.04/	0+			Pr kx-ray
				β^+ /6 /					0.0401/21.
									0.1091/35.
									(0.10–0.97)
^{137m}Nd			1.6 s	I.T./0.5196		11/2–			Nd k x-ray

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.1084
									0.1775
									0.2337
^{137}Nd		136.9146	38. m	β^+ /40 /3.69	1.7/20	1/2+	–0.63		ann.rad./
				EC/60 /	2.40/20				Pr k x-ray
									0.0755
									0.5806
^{138}Nd		137.9119	5.1 h	EC/1.1		0+			Pr k x-ray
									0.1995
									0.3258
^{139m}Nd			5.5 h	I.T./12 /0.231	1.17/	11/2–			Nd k x-ray
				β^+ /88 /					Pr k x-ray
									0.1139/34.
									0.7382/30.
^{139}Nd		138.91192	30. m	β^+ /25 /2.79	1.77/	3/2+	0.91	+0.3	ann.rad./
				EC/75 /					Pr k x-ray
									0.4050
^{140}Nd		139.90931	3.37 d	EC /0.22		0+			Pr k x-ray
^{141m}Nd			1.04 m	IT/99+/0.756		11/2–			Nd k x-ray
									0.7565
^{141}Nd		140.909605	2.49 h	EC/98 /1.823	0.802/	3/2+	1.01	+0.3	Pr k x-ray
				β^+ /2 /					(0.15–1.7)
^{142}Nd	27.2(5)	141.907719				0+			
^{143}Nd	12.2(2)	142.909810				7/2–	–1.07	–0.60	
^{144}Nd	23.8(3)	143.910083	2.1×10^{15} y	α	1.83	0+			
^{145}Nd	8.3(1)	144.912569				7/2–	–0.66	–0.31	
^{146}Nd	17.2(3)	145.913113				0+			
^{147}Nd		146.916096	10.98 d	β^- /0.896	0.805/	5/2–	0.58	0.9	Pr k x-ray
									0.53102
									0.09111–0.686
^{148}Nd	5.7(1)	147.916889				0+			
^{149}Nd		148.920145	1.73 h	β^- /1.691	1.03/25	5/2–	0.35	1.3	Pr k x-ray
					1.13/26				0.1143/19.
					1.42/				0.2113/27.
									(0.06–1.6)
^{150}Nd	5.6(2)	149.920887	$\approx 1 \times 10^{19}$ y	$\beta^-\beta^-$		0+			
^{151}Nd		150.923825	12.4 m	β^- /2.442	1.2/	(3/2+)			Pm k x-ray
									0.1168
									0.2557
									1.1806
									(0.10–1.9)m
^{152}Nd		151.92468	11.4 m	β^- /1.1		0+			0.2785/29.
									0.2501/18.
									(0.016–0.66)
^{153}Nd		152.9280	28.9 s	β^- /3.6					0.418
^{154}Nd		153.9296	25.9 s	β^- /2.8					0.1519
									0.7998
^{155}Nd		154.9334	8.9 s	β^- /5.0					0.1807
^{156}Nd		155.9355	5.5 s	β^- /4.1					0.0848
^{157}Nd		156.9393							
^{158}Nd		157.942							
^{159}Nd		158.946							
^{160}Nd		159.949							
^{161}Nd		160.954							
$_{61}$Pm									
^{128}Pm		127.948	1.0 s	β^+, p					Ann.rad.
^{129}Pm		128.943							
^{130}Pm		129.940	2.5 s	β^+, EC/11.					0.1589
									0.326–1.062
^{131}Pm		130.936	≈ 6.3 s	β^+					0.185
									0.220
									0.146
^{132}Pm		131.934	6. s	β^+, EC/10.					ann.rad./
^{133}Pm		132.930	12. s	β^+, EC/≈ 7.0					ann.rad./
^{134}Pm		133.9282	24. s	β^+, EC/≈ 8.9		(5+)			ann.rad./

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.294
									0.495
^{135}Pm		134.9247	0.8 m	β^+, EC/6.0		11/2–			(0.13–0.47)
^{136}Pm		135.9235	1.8 m	β^+ /89 /7.9		(3+)			ann.rad./
				EC/11 /					Nd k x-ray
									0.3735
									0.6027
^{137}Pm		136.9206	2.4 m	β^+, EC/5.6		(11/2–)			ann.rad./
									0.1086
									0.1775
^{138m}Pm			3.2 m	β^+ /50 /≈7.0	3.9/	3+	3.		ann.rad./
				EC/50 /					Nd k x-ray
									0.5209
									0.7290
^{138}Pm		137.9193	10. s	β^+ /6.9	6.1/	1+			ann.rad./
^{139m}Pm			0.18 s	IT/		(11/2–)			0.1887
^{139}Pm		138.91678	4.14 m	β^+ /68 /4.52	3.52/	(5/2+)			ann.rad./
				EC/32 /					Nd k x-ray
									0.4028
									(0.27–2.4)
^{140m}Pm			5.87 m	β^+ /70 /	3.2	7/2–			ann.rad./
				EC/30 /					Nd k x-ray
									0.4199
									0.7738
									1.0283
^{140}Pm		139.91585	9.2 s	β^+ /89 /6.09	5.07/74	1+			ann.rad./
				EC/11 /					Nd k x-ray
									0.7738
									1.4898
^{141}Pm		140.91359	20.9 m	β^+ /52 /3.72	2.71	5/2+			ann.rad./
				EC/48 /					Nd k x-ray
									0.8862
									1.2233
^{142}Pm		141.91295	40.5 s	β^+ /86 /4.87	3.8/	1+			ann.rad./
				EC/20 /					Nd k x-ray
									0.6414
									1.5758
^{143}Pm		142.910928	265. d	EC/1.041		5/2+	3.8		Nd k x-ray
				β^+ /<6 × 10^{-6}/					0.7420
^{144}Pm		143.912586	360. d	EC/2.332		5–	1.7		Nd k x-ray
				β^+ /7 × 10^{-6}/					0.6180
									0.6965
^{145}Pm		144.912745	17.7 y	EC/0.163		5/2+	+3.8	+0.2	Nd k x-ray
									0.0723
^{146}Pm		145.914693	5.53 y	EC/63 /1.472		3–			Nd k x-ray
				β^- /37 /1.542	0.795/				0.4538
									0.7362
									0.7474
^{147}Pm		146.915134	2.623 y	β^- /0.224	0.224/	7/2+	+2.6	+0.7	0.1213
									0.1974
^{148m}Pm			41.3 d	β^- /95 /2.6	0.4/60	6–	1.8		0.5503/94.
				I.T./5 /0.137	0.5/17				0.6300/89.
					0.7/21				0.7257/33
^{148}Pm		147.91747	5.37 d	β^- /2.47	1.02/	1–	+2.0	+0.2	0.5503
					2.47/				0.9149
									1.4651
^{149}Pm		148.918330	2.212 d	β^- /1.071	0.78/9	7/2+	3.3		0.2859
					1.072/90				0.5909
									0.8594
^{150}Pm		149.92098	2.68 h	β^- /3.45	1.6/	(1–)			0.3339/69.
					2.3/				1.1658/16.
					1.8/				1.3245/17.
									(0.25–2.9)
^{151}Pm		150.92120	1.183 d	β^- /1.187	0.84/	5/2+	+1.8	1.9	0.1677/8
									0.2751/7
									0.3401/22
^{152m2}Pm			15. m	β^-, I.T./		(>6)			(0.14–1.4)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{152m1}Pm			7.5 m	β^- /		(4–)			0.1218
									0.2447
									0.3404
									1.0971
									1.4375
^{152}Pm		151.9235	4.1 m	β^- /3.5	3.5/20	1+			0.1218
					3.50/60				(0.12–2.1)
^{153}Pm		152.92414	5.4 m	β^- /1.90	1.7/	(5/2–)			0.0910
									0.1198
									0.1273
^{154m}Pm			2.7 m	β^- /	2.0/				0.0820
									0.1848
									1.4403
^{154}Pm		153.9266	1.7 m	β^- /4.1	1.9/				0.0820
									0.8396
									1.3940
									2.0589
									(0.08–2.8)
^{155}Pm		154.9280	48. s	β^- /3.2		(5/2–)			(0.05–0.78)
^{156}Pm		155.93106	26.7 s	β^- /5.16					
^{157}Pm		156.9332	10.9 s	β^- /4.6					
^{158}Pm		157.9367	5. s	β^- /6.3					
^{159}Pm		158.939	1.5 s						
^{160}Pm		159.943							
^{161}Pm		160.946							
^{162}Pm		161.950							
^{163}Pm		162.954							
$_{62}$Sm		**150.36(3)**							
^{129}Sm			≈ 0.55 s	β^+, p					
^{130}Sm		129.949							
^{131}Sm		130.946	1.2 s	β^+, EC/					ann.rad./
^{132}Sm		131.941	4.0 s	β^+					
^{133}Sm		132.939	2.9 s	β^+, EC/≈8.4		5/2+			ann.rad./
									0.3696
									0.0845
^{134}Sm		133.934	11. s	β^+, EC/5.		0+			ann.rad./
^{135}Sm		134.932	10. s	β^+, EC/7.		7/2+			ann.rad./
^{136}Sm		135.9283	42. s	β^+, EC/4.5		0+			ann.rad./
^{137}Sm		136.9271	45. s	β^+, EC/6.1					ann.rad./
^{138}Sm		137.9235	3.0 m	β^+, EC/3.9		0+			ann.rad./
									0.0536
									0.0747
^{139m}Sm			10. s	I.T./94 /0.457		(11/2–)	1.1		Sm k x-ray
				β^+ /6 /	4.7				0.1118
									0.1553
									0.1901
									0.2673
^{139}Sm		138.9226	2.6 m	β^+ /75 /5.5	4.1/	1/2+	–0.53		Pm k x-ray
				EC/25 /					0.3678
									0.4028
									(0.27–2.4)
^{140}Sm		139.9195	14.8 m	β^+, EC/3.4	1.9/	0+			ann.rad./
									Pm k x-ray
									0.1396
									0.2255
									(0.07–1.7)
^{141m}Sm			22.6 m	β^+ /32 /	1.6/	11/2–	–0.83	+1.6	ann.rad./
				EC/68 /	2.19/				Pm k x-ray
				I.T./0.3 /0.1758					0.1966
									0.4318
									0.7774
^{141}Sm		140.91847	10.2 m	β^+ /52 /4.54	3.2/	1/2+	–0.74		ann.rad./
				EC/48 /					Pm k x-ray
									0.4382
^{142}Sm		141.91520	1.208 h	β^+ /6 /2.10	1.0/	0+			ann.rad./

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				EC/94 /					Pm k x-ray
^{143m}Sm			1.10 m	IT/99/0.7540		11/2–			Sm k x-ray
									0.7540
^{143}Sm		142.914624	8.83 m	β^+ /46 /3.443	2.47/	3/2+	+1.01	+0.4	ann.rad./
				EC/54 /					Pm k x-ray
									1.0565
^{144}Sm	3.07(7)	143.911996				0+			
^{145}Sm		144.913407	340. d	EC/0.617		7/2–	–1.12	–0.60	Pm k x-ray
									0.0613
									0.4924
^{146}Sm		145.913038	1.03×10^8 y	α/	2.50/	0+			
^{147}Sm	14.99(18)	146.914894	1.06×10^{11} y	α/	2.23/	7/2–	–0.815	–0.26	
^{148}Sm	11.24(10)	147.914818	7×10^{15} y	α/	1.96/	0+			
^{149}Sm	13.82(7)	148.917180	10^{16} y	α/		7/2–	–0.672	+0.075	
^{150}Sm	7.38(1)	149.917272				0+			
^{151}Sm		150.919929	90. y	β^- /0.0768	0.076/	5/2–	–0.363	+0.7	0.02154
^{152}Sm	26.75(16)	151.919729				0+			
^{153}Sm		152.922094	1.929 d	β^- /0.808	0.64/	3/2+	–0.0216	+1.3	Eu k x-ray
					0.69/				0.0697/4.7
									0.10318/29
									0.075–0.714
^{154}Sm	22.75(29)	153.922206				0+			
^{155}Sm		154.924636	22.2 m	β^- /1.627	1.52	3/2–		1.1	Eu k x-ray
									0.1043/75.
^{156}Sm		155.92553	9.4 h	β^- /0.72	0.43/	0+			0.0872
					0.71/				0.1657
									0.2038
^{157}Sm		156.9283	8.0 m	β^- /2.7	2.4/	3/2–			Eu k x-ray
									0.1964
									0.1978
									0.3942
^{158}Sm		157.9299	5.5 m	β^- /2.0		0+			0.1894/100.
									0.3636/82.
^{159}Sm		158.9332	11.3 s	β^- /3.8					0.1898
^{160}Sm		159.9353	9.6 s	β^- /3.6		0+			0.110
^{161}Sm		160.9388	≈4.8 s						0.264
^{162}Sm		161.941							
^{163}Sm		162.945							
^{164}Sm		163.948							
^{165}Sm		164.953							
$_{63}$Eu		**151.964(1)**							
^{130}Eu			0.9 ms	p	1.027/				
^{131}Eu			≈26. ms	β^+, p	p/0.95				
^{132}Eu		131.954							
^{133}Eu		132.949							
^{134}Eu		133.946	0.5 s	EC, β^+					ann.rad./
^{135}Eu		134.942	1.5 s	EC, β^+ /≈8.7					ann.rad./
^{136m}Eu			≈ 3.2 s			7+			0.255
^{136}Eu		135.940	≈ 3.9 s	EC, β^+ /10.		1+			ann.rad./
^{137}Eu		136.935	11. s	EC/≈7.5		11/2–			ann.rad./
^{138}Eu		137.9335	12. s	EC, β^+ /≈9.2		7+	5		ann.rad./
^{139}Eu		138.9298	18. s	EC, β^+ /6.7			6		ann.rad./
^{140m}Eu			0.125 s	EC, β^+					ann.rad./
^{140}Eu		139.9285	1.51 s	EC, β^+ /8.4		1–			ann.rad./
^{141m}Eu			3.0 s	β^+ /58 /		11/2–			ann.rad./
				EC/9 /					Eu k x-ray
				I.T./33 /0.0964					(0.09–1.6)
^{141}Eu		140.9244	40. s	β^+ /81 /5.6		5/2+	+3.49	+0.85	ann.rad./
				EC/15 /					Sm k x-ray
									0.3845
									0.3940
^{142m}Eu			1.22 m	β^+ /83 /	4.8/	8–	+2.98	+1.4	ann.rad./
				EC/17 /					Sm k x-ray
									0.5566
									0.7680

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin (h/2π)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									1.0233
^{142}Eu		141.9231	2.4 s	β⁻ /94/7.4	7.0/	1+	+1.54	+0.12	ann.rad./
				EC/6 /					0.7680
^{143}Eu		142.92017	2.62 m	β⁺ /72/5.17	4.1/	5/2+	+3.67	+0.51	ann.rad./
				EC/28/	5.1/				Sm k x-ray
									0.1107/7
									1.5368/3.
									1.9127/2.
^{144}Eu		143.91879	10.2 s	β⁺ /86 /6.33	5.31/	1+	+1.89	+0.10	ann.rad./
				EC/13 /					Sm k x-ray
									1.6601
^{145}Eu		144.916263	5.93 d	β⁺ /2 /2.660	0.79/	5/2+	+4.00	+0.29	ann.rad./
				EC/98 /1.71					Sm k x-ray
									0.6535
									0.8937
									1.6587
^{146}Eu		145.91720	4.57 d	β⁺ /5 /3.88	1.47/	4–	+1.42	–0.18	ann.rad./
				EC/95 /					Sm k x-ray
									0.6336
									0.6341
									0.7470
									(0.27–2.64)
^{147}Eu		146.916742	24.4 d	EC/99. /1.722		5/2+	+3.72	+0.53	Sm k x-ray
				β⁺ /0.4 /					0.12113
									0.19725
									0.6776
^{148}Eu		147.91815	54.5 d	EC/3.11	0.92	5–	+2.34	+0.35	Sm k x-ray
									0.5503/99.
									0.6299/71.
									(0.067–2.17)
^{149}Eu		148.91792	93.1 d	EC/0.692		5/2+	+3.57	+0.75	Sm k x-ray
									0.2770
									0.3275
^{150}Eu		149.91970	36. y	EC/2.26		5–	+2.71	+1.13	Sm k x-ray
									0.3340
									0.4394
									0.5843
									(0.25–1.8)
^{150m}Eu			12.8 h	β⁻ /92 /	1.013/	0–			Sm k x-ray
				β⁺ /0.4 /	1.24/				0.3339
				EC/8 /					0.4065
^{151}Eu	47.81(6)	150.919846				5/2+	+3.472	+0.90	
^{152m2}Eu			1.60 h	I.T./0.1478		8–			Eu k x-ray
									0.0898
^{152m1}Eu			9.30 h	β⁻ /72 /	1.85/	0–			Sm k x-ray
				EC/28 /	0.89/				0.12178
									0.84153
									0.96334
^{152}Eu		151.921741	13.5 y	EC/72 /1.874	0.69/	3–	–1.941	+2.71	Sm k x-ray
				β⁻ /28 /1.818	1.47/				Gd k x-ray
									0.12178
									0.34427
									1.40802
									(0.252–1.528)
^{153}Eu	52.19(6)	152.921227				5/2+	+1.533	+2.41	
^{154m}Eu			46.1 m	I.T./≈ 0.16		8–			Eu k x-ray
									0.0682
									0.1009
^{154}Eu		153.922976	8.59 y	β⁻ /99.9/1.969	0.27/29	3–	–2.01	+2.8	Gd k x-ray
				EC/0.02/0.717	0.58/38				0.12299/40.
					0.84/17				0.72331/20.
					0.98/4				1.2745/36
					1.87/11				(0.059-1.90)
^{155}Eu		154.922890	4.76 y	β⁻ /0.252	0.15/	5/2+	+1.52	+2.4	Gd k x-ray
									0.0865/30
									0.1053/20
^{156}Eu		155.92475	15.2 d	β⁻ /2.451	0.30/11	1+	≈1.1		0.08899/9.

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
					0.49/30				0.64623/7.
					1.2/12				0.723441/6.
					2.45/31				0.8118/10.
^{157}Eu		156.92542	15.13 h	β^- /1.36	0.98/	(5/2+)	+1.50	+2.6	Gd k x-ray
					1.30/41				0.0639/100.
									0.3705/48.
									0.4107/76.
^{158}Eu		157.9278	45.9 m	β^- /3.5	2.5/	(1–)	+1.44	+0.7	0.0795
									0.8976
									0.9442
									0.9771
^{159}Eu		158.92909	18.1 m	β^- /2.51	2.4/	(5/2+)	+1.38	+2.7	0.0678
					2.57/				0.0786
									0.0957
^{160}Eu		159.9315	38. s	β^- /4.1	2.7/	(0–)			0.0753
					4.1/				0.1735
									0.4131
									0.5155
									0.8217
									0.9110
									0.9246
^{161}Eu		160.9337	27. s	β^- /3.7					0.0719
^{162}Eu		161.9370	11. s	β^- /5.6					
^{163}Eu		162.9392							
^{164}Eu		163.943							
^{165}Eu		164.946							
^{166}Eu		165.950							
^{167}Eu		166.953							
$_{64}$Gd		**157.25(3)**							
^{135}Gd			1.1 s	β^+					(0.163–0.360)
^{136}Gd		135.947							
^{137}Gd		136.945	7. s	EC, β^+ /≈8.8					ann.rad./
^{138}Gd		137.9400	≈4.7 s	EC, β^+					0.0647
^{139m}Gd			≈4.8 s						0.1216
^{139}Gd		138.9381	5. s	EC, β^+ /≈7.7					0.104–0.323
^{140}Gd		139.934	16. s	EC/4.8		0+			0.1748
^{141m}Gd			25. s	EC, β^+ /		11/2–			ann.rad./
^{141}Gd		140.9322	21. s	β^+ /7.3		0+			ann.rad./
^{142}Gd		141.9276	1.17 m	EC, β^+ /4.2		1/2+			ann.rad./
^{143m}Gd			1.84 m	β^+ /67 /		11/2–			ann.rad./
				EC/33 /					Eu k x-ray
				I.T./					0.1176
									0.2719
									0.5880
									0.6681
									0.7999
^{143}Gd		142.9266	39. s	β^+ /82 /6.0		1/2+			ann.rad./
				EC/18 /					Eu k x-ray
									0.2048
									0.2588
^{144}Gd		143.9234	4.5 m	β^+ /45 /4.3	3.3/	0+			ann.rad./
				EC/55 /					Eu k x-ray
									0.3332
^{145m}Gd			1.44 m	I.T./95 /0.749		11/2–			0.0273
				β^+ /4 /5.7					0.3295
									0.3866
									0.7214
^{145}Gd		144.92169	23.4 m	β^+ /33 /5.05	2.5/	1/2+			ann.rad./
				EC/67 /					Eu k x-ray
									1.7579
									1.8806
									(0.32–3.69)
^{146}Gd		145.91831	48.3 d	EC/99.9 /1.03	0.35/	0+			Eu k x-ray
				β^+ /0.2					0.1147
									0.1155

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.1546
^{147}Gd		146.919090	1.588 d	EC/99.8 /2.188	0.93/	7/2–	1.0		Eu k x-ray
				EC/0.2 /					0.2293
									0.3699
									0.3960
									0.9289
									(0.1–1.8)
^{148}Gd		147.918111	75. y	α/3.27	3.1828/	0+			
^{149}Gd		148.919339	9.3 d	EC/1.32		7/2–	0.9		Eu k x-ray
									0.1496
									0.2985
									0.3465
^{150}Gd		149.91866	1.8×10^6 y	α/2.80	2.73/	0+			
^{151}Gd		150.920345	124. d	EC/0.464		7/2–	0.8		Eu k x-ray
									0.1536
									0.2432
^{152}Gd	0.20(1)	151.919789				0+			
^{153}Gd		152.921747	240. d	EC/0.485		3/2–	0.4		Eu k x-ray
									0.09743
									0.10318
^{154}Gd	2.18(3)	153.920862				0+			
^{155}Gd	14.80(12)	154.922619				3/2–	–0.259	+1.30	
^{156}Gd	20.47(9)	155.922120				0+			
^{157}Gd	15.65(2)	156.923957				3/2–	–0.340	+1.36	
^{158}Gd	24.84(7)	157.924101				0+			
^{159}Gd		158.926385	18.6 h	β^- 0.971	0.971/58	3/2–	–0.44		Tb k x-ray
					0.913/29				0.36351
					0.607/12				0.058-0.855
^{160}Gd	21.86(19)	159.927051	$>1.9 \times 10^{19}$ y	$\beta^-\beta^-$		0+			
^{161}Gd		160.929666	3.66 m	β^- /1.956	1.56/85	5/2–			Tb k x-ray
									0.1023
									0.3149
									0.3609
^{162}Gd		161.930981	8.4 m	β^- /1.39	1.0/	0+			0.4030
									0.4421
^{163}Gd		162.9340	1.13 m	β^- /3.1					0.2868
									0.214
									1.685
^{164}Gd		163.9359	45. s	β^- /2.3					
^{165}Gd		164.9394	10 s	β^-					
^{166}Gd		165.942							
^{167}Gd		166.946							
^{168}Gd		167.948							
^{169}Gd		168.953							
$_{65}$Tb		**158.92534(2)**							
^{138}Tb									
^{139}Tb		138.948	1.6 s						0.109
									0.120
^{140}Tb		139.946	2.4 s	β^+, EC/11					0.329
									0.355–0.740
^{141}Tb		140.941	3.5 s	β^+, EC/≈ 8.3					
^{142m}Tb			0.30 s	β^+, EC/		4–			
^{142}Tb		141.939	0.60 s	β^+, EC/10.		0+			
^{143}Tb		142.9346	12. s	β^+, EC/7.4		11/2–			
^{144m}Tb			4.1 s	IT		5–			
^{144}Tb		143.9324	< 1.5 s	β^+, EC/8.4		1+			
^{145m}Tb			30. s	β^+, EC/≈ 6.6		11/2–			ann.rad./
									0.2577
									0.5370
									0.9876
^{145}Tb		144.9287		β^+, EC/6.5		1/2+			
^{146m}Tb			23. s	β^+ /76 /		(5–)			ann.rad./
				EC/24 /					Gd k x-ray
									1.0789
									1.5795

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{146}Tb		145.9270	≈ 8. s	β^+ /8.1		1+			
^{147m}Tb			1.8 m	β^+ /35 /		11/2–			ann.rad./
				EC/65 /					Gd k x-ray
									1.3977
									1.7978
^{147}Tb		146.92404	1.6 h	β^+ /42 /4.61		5/2+	+1.70		ann.rad./
				EC/58 /					Gd k x-ray
									0.6944
									1.1522
									(0.120–3.318)
^{148m}Tb			2.3 m	β^+ /25 /		9+			ann.rad./
				EC/75 /					Gd k x-ray
									0.3945
									0.6319
									0.7845
									0.8824
^{148}Tb		147.92422	1.00 h	β^+, EC/5.69		2–	–1.75	–0.3	ann.rad./
									Gd k x-ray
									0.4888
									0.7845
									(0.14–3.8)
^{149m}Tb			4.16 m	EC/88 /		11/2–			ann.rad./
				β^+ /12 /					Gd k x-ray
									0.1650
									0.7960
^{149}Tb		148.923243	4.13 h	β^+ /4 /3.636	1.8/	1/2+	+1.35		Gd k x-ray
				α/16/	3.97/				0.1650
									0.3522
									0.3886
									(0.1–3.2)
^{150m}Tb			6.0 m	β^+ /17 /					ann.rad./
				EC/83 /					Gd k x-ray
									0.4384
									0.6380
									0.6504
									0.8275
^{150}Tb		149.92366	3.3 h	β^+, EC/4.66		2–	–0.90		ann.rad./
									0.4963
									0.6380
									(0.3–4.29)
^{151m}Tb			25. s	I.T./95 /		11/2–			0.0229
				β^+, EC/7 /					0.0495
									0.3797
									0.8305
^{151}Tb		150.923099	17.61 h	β^+/1 /2.565	0.70/	1/2+	+0.92		Gd k x-ray
				EC/99 /					0.1083
									0.2517
									0.2870
									(0.1–1.8)
^{152m}Tb			4.3 m	I.T./79 /0.5018		(8+)			Tb k x-ray
				EC/21 /4.35					Gd k x-ray
									0.2833
									0.3443
									0.4111
^{152}Tb		151.92407	17.5 h	β^+ /20 /3.99	2.5/	2–	–0.58	+0.3	ann.rad./
				EC/80 /	2.8/				Gd k x-ray
									0.3443
									(0.2–2.88)
^{153}Tb		152.923433	2.34 d	EC/1.570		5/2+	+3.44	+1.1	Gd k x-ray
									0.2119
									(0.05–1.1)
^{154m2}Tb			23.1 h	EC/98 /		(7–)	0.9		Gd k x-ray
				I.T./2 /					0.1231
									0.2479
									0.3467
									1.4199
^{154m1}Tb			9. h	β^+ /78 /		(3–)	1.7	+3.	Gd k x-ray

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				I.T./22 /					0.1231
									0.2479
									0.5401
									(0.12–2.57)
^{154}Tb		153.92469	21.5 h	EC/99 /3.56	1.86/	0–			Gd k x-ray
				β^+ /1 /	2.45				0.1231
									1.2744
									2.1872
									(0.12–3.14)
^{155}Tb		154.92350	5.3 d	EC/0.82		3/2+	+2.01	+1.41	Gd k x-ray
									0.08654
									0.10530
^{156m2}Tb			1.02 d	I.T./		(7–)			Tb k x-ray
									0.0496
^{156m1}Tb			5.3 h	I.T./0.0884		(0+)			Tb k x-ray
									0.0884
^{156}Tb		155.924744	5.3 d	EC/2.444		3–	≈1.7	+2.	Gd k x-ray
									0.08896
									0.19921
									0.53435
									1.22245
^{157}Tb		156.924021	1.1×10^2 y	EC/0.0601		3/2+	+2.01	+1.4	Gd k x-ray
									0.0545
^{158m}Tb			10.5 s	I.T./0.11		0–			Gd k x-ray
									0.0110
^{158}Tb		157.925410	1.8×10^2 y	EC/80 /1.220		3–	+1.76	+2.7	Gd k x-ray
				β^- /20 /0.937					0.0795
									0.9442
									0.9621
^{159}Tb	100.	158.925343				3/2+	+2.014	+1.43	
^{160}Tb		159.927164	72.3 d	β^- /1.835	0.57/47	3–	+1.79	3.8	Dy k x-ray
					0.86/27				0.08678
									0.29857
									0.87936
									0.96615
^{161}Tb		160.927566	6.91 d	β^- /0.593	0.46/23	3/2+	2.2	+1.2	Dy k x-ray
					0.52/66				0.02565
					0.6/10				0.04892
									0.07458
^{162}Tb		161.92948	7.6 m	β^- /2.51	1.4	(1/2–)			Dy k x-ray
									0.2600
									0.8075
									0.8882
^{163}Tb		162.930644	19.5 m	β^- /1.785	0.80/	3/2+			Dy k x-ray
									0.3511
									0.3897
									0.4945
^{164}Tb		163.9334	3.0 m	β^- /3.9	1.7/	(5+)			Dy k x-ray
									0.1689
									0.2157
									0.6110
									0.6885
									0.7548
^{165}Tb		164.9349	2.1 m	β^- /3.0		3/2+			0.5389
									1.1785
									1.2920
									1.6648
^{166}Tb		165.9380	≈ 21 s	β^-/					
^{167}Tb		166.9401	19 s						0.057
									0.070
^{168}Tb		167.9436	8 s						0.075–0.227
^{169}Tb		168.946							
^{170}Tb		169.950							
^{171}Tb		170.953							
$_{66}$Dy		**162.50(3)**							

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{139}Dy			0.6 s	β^+, p					
^{140}Dy		139.954							
^{141}Dy		140.951	0.9 s	EC, β^+ /9.					
^{142}Dy		141.946	2.3 s	EC, β^+ /7.1					
^{143}Dy		142.9440	3.9 s	EC, β^+ /≈ 8.8					
^{144}Dy		143.9391	9.1 s	EC, β^+ /≈ 6.2					
^{145m}Dy		144.9365	14. s	EC, β^+		11/2–			
^{146m}Dy			0.15 s	I.T.		10+			
^{146}Dy		145.9325	30. s	EC, β^+ /5.2					
^{147m}Dy			56. s	I.T./40 /		(11/2–)	–0.66	+0.7	Dy k x-ray
				β^+, EC/60 /					0.072
									0.6787
^{147}Dy		146.9309	75. s	EC, β^+ /6.37		1/2+	–0.92		ann.rad./
									0.1007
									0.2534
									0.3653
^{148}Dy		147.92710	3.1 m	β^+ /4 /2.68	1.2/	0+			ann.rad./
				EC/96 /					Tb k x-ray
									0.6202
^{149}Dy		148.92734	4.2 m	β^+, EC/3.81		(7/2–)	–0.12	–0.62	ann.rad./
									0.1008
									0.1063
									0.2534
									0.6536
									0.7894
									1.7765
									1.8062
^{150}Dy		149.92558	7.18 m	β^+, EC/67 /1.79		0+			Tb k x-ray
				α/33 /	4.233/				0.3967
^{151}Dy		150.926181	17. m	β^+ /5 /2.871		7/2–	–0.95	–0.30	Tb k x-ray
				EC/89 /					0.1764
				α /6 /	4.067/				0.3030
									0.3861
									0.5463
									(0.16–2.09)
^{152}Dy		151.92472	2.37 h	EC/0.60		0+			Tb k x-ray
				α /	3.63/				0.2569
^{153}Dy		152.925763	6.3 h	β^+ /1 /2.171	0.89/	(7/2–)	–0.78	≈–0.15	Tb k x-ray
				EC/99 /					0.0807
				α /0.01 /	3.46/				0.0997
									0.2137
									(0.08–1.66)
^{154}Dy		153.92442	$3. \times 10^6$ y	α/2.95	2.87/	0+			
^{155}Dy		154.92575	9.9 h	β^+ /2 /2.095	0.845/	3/2–	–0.385	+1.04	Tb k x-ray
				EC/98 /					0.0655
									0.2269
^{156}Dy	0.056(3)	155.92428				0+			
^{157}Dy		156.92546	8.1 h	EC/1.34		3/2–	–0.301	+1.30	Tb k x-ray
									(0.0609–1.319)
^{158}Dy	0.095(3)	157.924405				0+			
^{159}Dy		158.925736	144. d	EC/0.366		3/2–	–0.354	+1.37	Tb k x-ray
									0.3262
^{160}Dy	2.39(18)	159.925194				0+			
^{161}Dy	18.889(42)	160.926930				5/2+	–0.480	+2.51	
^{162}Dy	25.475(36)	161.926795				0+			
^{163}Dy	24.896(42)	162.928728				5/2–	+0.673	+2.65	
^{164}Dy	28.260(54)	163.929171				0+			
^{165m}Dy			1.26 m	I.T./98 /0.108		1/2–			Dy k x-ray
				β^- /2 /					0.1082
									0.5155
^{165}Dy		164.931700	2.33 h	β^- /1.286	1.29/	7/2+	–0.52	+3.5	Ho k x-ray
									0.09468
^{166}Dy		165.932803	3.400 d	β^- /0.486	0.40/	0+			Ho k x-ray
									0.0282
									0.0825
^{167}Dy		166.9357	6.2 m	β^- /≈2.35	1.78	(1/2–)			Ho k x-ray
									0.2593

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.3103
									0.5697
									(0.06–1.4)
^{168}Dy		167.9372	8.5 m	β^- /1.6		0+			Ho k x-ray
									0.1925
									0.4867
^{169}Dy		168.9403	≈ 39. s	β^- /3.2					
^{170}Dy		169.9427							
^{171}Dy		170.9465							
^{172}Dy		171.949							
^{173}Dy		172.953							
$_{67}$Ho		**164.93032(2)**							
^{140}Ho			6 ms	p/	p/1.09				
^{141m}Ho			8 μs	p/	p/1.23				
^{141}Ho			4.2 ms	β^+, p	p/1.71				
^{142}Ho		141.960	0.4 s	EC/β^+, p					0.307
^{143}Ho		142.955							
^{144}Ho		143.952	0.7 s	β^+, EC/12					
^{145}Ho		144.947	2.4 s	β^+					
^{146}Ho		145.9440	3.3 s	β^+, EC/10.7		(10+)			ann.rad./
^{147}Ho		146.9396	5.8 s	β^+, EC/8.2		11/2–			ann.rad./
^{148m}Ho			9. s	β^+, EC/		4–			ann.rad./
^{148}Ho		147.9372	2. s	β^+, EC/9.4		1+			ann.rad./
									0.6615
									1.6883
^{149m}Ho			21. s	β^+, EC/		11/2–			ann.rad./
									1.0733
									1.0911
^{149}Ho		148.93379	> 30. s	β^+, EC/6.01		1/2+			
^{150m}Ho			25. s	β^+, EC/		(9+)			ann.rad./
									0.3939
									0.5511
									0.6534
									0.8034
^{150}Ho		149.9326	1.3 m	β^+, EC/6.6					ann.rad./
									0.5913
									0.6534
									0.8034
^{151m}Ho			47. s	β^+, EC/87 /					ann.rad./
				α/13	4.605/				0.2102
									0.4889
									0.6948
									0.7762
^{151}Ho		150.93169	35.2 s	β^+, EC/80/5.13					ann.rad./
				α/20 /	4.519/				0.3522
									0.5274
									0.9676
									1.0471
^{152m}Ho			50. s	β^+, EC/90/		(9+)	+5.9	–1.	ann.rad./
				α/10/	4.453/				0.4929
									0.6138
									0.6474
									0.6835
^{152}Ho		151.93166	2.4 m	β^+, EC/88/6.47		(3+)	–1.02	+0.1	ann.rad./
				α/12/	4.387/				0.6140
									0.6476
^{153m}Ho			9.3 m	β^+, EC/99+/4.12		5/2	+1.19		ann.rad./
				α/	4.01/				0.0905
									0.1089
									0.1618
									0.2302
									0.2707
									0.3659
									0.4565
^{153}Ho		152.93020	2.0 m	β^+, EC/99+/4.13		11/2–	+6.8	–1.1	ann.rad./

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				α/	3.91/				0.2958
									0.3346
									0.4381
									0.6383
^{154m}Ho			3.3 m	β^+, EC/		(8+)	5.7	–1.0	ann.rad./
									0.3346
									0.4124
									0.4771
^{154}Ho		153.93060	12. m	β^+, EC/5.75		1–	–0.64	+0.2	ann.rad./
									Dy k x-ray
									0.3346
									0.5700
									0.8734
^{155}Ho		154.92908	48. m	β^+/6/3.10		(5/2+)	+3.51	+1.5	ann.rad./
				EC/94 /					Dy k x-ray
									0.0474
									0.1363
									0.3254
									(0.06–2.24)
^{156m}Ho			5.8 m	I.T./0.0352			+2.99	+2.3	ann.rad./
				β^+ /25 /	1.8/				Dy k x-ray
				EC/75 /	2.9/				0.1378
									0.2666
									(0.28–2.9)
^{156}Ho		155.9290	56. m	β^+, EC/4.4		(5+)			ann.rad./
									0.1378
									0.2665
^{157}Ho		156.92819	12.6 m	β^+/5/2.54	1.18/	7/2–	+4.35	+3.0	ann.rad./
				EC/95/					Dy k x-ray
									0.2800
									0.3411
^{158m2}Ho			28. m	I.T./44/		2–	+2.44	+1.6	ann.rad./
				EC/56/					Dy k x-ray
									0.0989
									0.2182
^{158m1}Ho			21. m	β^+, EC/		(9+)			ann.rad./
									0.0981
									0.1664
									0.2182
									0.3205
									0.4062
									0.9774
									1.0532
									0.4846
^{158}Ho		157.92895	11.3 m	β^+/8/4.24	1.30/	5+	+3.77	+4.1	ann.rad./
				EC/92/					Dy k x-ray
									0.0989
									0.2182
									0.9488
^{159m}Ho			8.3 s	IT/0.206		1/2+			Ho k x-ray
									0.1660
									0.2059
^{159}Ho		158.927708	33.0 m	EC/1.838		7/2–	+4.28	+3.2	Dy k x-ray
									0.1210
									0.1320
									0.2529
									0.3096
									(0.06–1.2)
^{160m2}Ho			3. s			1+			
^{160m}Ho			5.0 h	IT/67/0.060		2–	+2.52	+1.8	0.0868
				EC/33/3.35					0.1970
									0.6464
									0.7281
									0.8791
									0.9619
									0.9658
^{160}Ho		159.92873	25.6 m	β^+, EC/3.29	0.57/	5+	+3.71	+4.0	See Ho[166m]

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.7282
									0.8794
^{161m}Ho			6.8 s	IT/0.211					Ho k x-ray
									0.2112
^{161}Ho		160.927852	2.48 h	EC/0.859		7/2–	+4.25	+3.2	Dy k x-ray
									0.0256
									0.0592
									0.0774
									0.1031
^{162m}Ho			1.12 h	IT/61/		6–	+3.60	+4.	Dy k x-ray
				EC/39/					Ho k x-ray
									0.0807
									0.1850
									0.2828
									0.9372
									1.2200
^{162}Ho		161.929092	15. m	EC/96 /0.295		1+			Dy k x-ray
				β^+ /4 /					0.0807
									1.3196
									1.3728
^{163m}Ho			1.09 s	I.T./0.298		(1/2+)			Ho k x-ray
									0.2798
^{163}Ho		162.928730	4.57×10^3 y	EC/0.00258		7/2–	+4.23	+3.6	Dy M x-rays
^{164m}Ho			38. m	I.T./0.140		(6–)			Ho k x-ray
									0.0373
									0.0566
									0.0940
^{164}Ho		163.930231	29. m	EC/58 /0.987		1+			Dy k x-ray
				β^- /42 /0.963					0.0734
									0.0914
^{165}Ho	100.	164.930319				7/2–	+4.17	+3.49	
^{166m}Ho			1.2×10^3 y	β^- /		7–	3.6	–3.	Er k x-ray
									0.18407
									0.71169
									0.81031
^{166}Ho		165.932281	1.117 d	β^- /1.855	1.776/48	0–			Er k x-ray
					1.855/51				0.08057
									1.37943
^{167}Ho		166.933127	3.1 h	β^- /1.007	0.31/43	(7/2–)			Er k x-ray
					0.61/21				0.0793
					0.96/15				0.0835
					0.97/15				0.2379
									0.3213
									0.3465
^{168m}Ho			2.2 m	I.T./					
^{168}Ho		167.93550	3.0 m	β^- /2.91	2.0/	3+			Er k x-ray
									0.7413
									0.8159
									0.8211
									(0.08–2.34)
^{169}Ho		168.93687	4.7 m	β^- /2.12	1.2/	(7/2–)			
					2.0/				0.1496
									0.7610
									0.7784
									0.7884
									0.8529
^{170m}Ho			43. s	β^- /		1+			0.0787
									0.8123
									1.8940
									1.9726
^{170}Ho		169.93962	2.8 m	β^- /3.87		6+			Er k x-ray
									0.1816
									0.2582
									0.8902
									0.9321
									0.9414
									1.1387

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{171}Ho		170.941	53 s	β^- /					
^{172}Ho		171.9448	25. s	β^- /					Er k x-ray
									(0.077–1.186)
^{173}Ho		172.947							
^{174}Ho		173.951							
^{175}Ho		174.954							
$_{68}$Er		**167.259(3)**							
^{144}Er		143.961							
^{145}Er		144.957	0.9 s	β^+					
^{146}Er		145.952	≈ 1.7 s	β^+					
^{147}Er		146.9494	2.5 s	E.C, β^+ /≈ 9.1					
^{148}Er		147.9444	4.5 s	β^+, EC/6.8					
^{149m}Er			10. s	IT		11/2–			
^{149}Er		148.9425	10.7 s	ECβ^+ /8.1		1/2+			
^{150}Er		149.9370	18. s	β^+ /36 /4.11		0+			ann.rad./
				EC/64 /					Ho k x-ray
									0.4758
^{151}Er		150.9373	23. s	β^+, EC/5.2		7/2–			ann.rad./
^{152}Er		151.93500	10.2 s	β^+, EC/10/3.11		0+			ann.rad./
				α/90/	4.804/				
^{153}Er		152.93509	37.1 s	α/	4.674		–0.934	–0.42	0.351
				β^+, EC/47/4.56	4.35/				(0.0945–1.700)
^{154}Er		153.93278	3.7 m	β^+, EC/99+/2.03		0+			ann.rad./
				α/0.5/	4.166/				
^{155}Er		154.93321	5.3 m	β^+, EC/47/3.84		(7/2–)	–0.669	–0.27	ann.rad./
				EC/53 /					Ho k x-ray
									0.1101
									0.2415
^{156}Er		155.9308	20. m	β^+, EC/1.7		0+			ann.rad./
									0.0298
									0.0352
									0.0522
									0.1336
^{157}Er		156.9319	25. m	β^+, EC/3.5		3/2–	–0.412	+0.92	ann.rad./
									0.117
									0.385
									1.320
									1.660
									1.820
									2.000
^{158}Er		157.93087	2.2 h	EC/99.5 /1.78	0.74/	0+			Ho k x-ray
				β^+ /0.5 /					0.0719
									0.2486
									0.3868
^{159}Er		158.930681	36. m	β^+ /7 /2.769		3/2–	–0.304	+1.17	ann.rad./
				EC/93 /					Ho k x-ray
									0.6245
									0.6493
									(0.07–2.5)
^{160}Er		159.92908	1.191 d	EC/0.33		0+			Ho k x-ray
									(0.05–0.96)
^{161}Er		160.93000	3.21 h	EC/2.00		3/2–	–0.37	+1.36	Ho k x-ray
									0.8265
									(0.07–1.74)
^{162}Er	0.139(5)	161.928775				0+			
^{163}Er		162.93003	1.25 h	EC/1.210		5/2–	+0.557	+2.55	Ho k x-ray
									0.4361
									0.4399
									1.1135
^{164}Er	1.601(3)	163.929197				0+			
^{165}Er		164.930723	10.36 h	EC/0.376		5/2–	+0.643	+2.71	Ho k x-ray
^{166}Er	33.503(36)	165.930290				0+			
^{167m}Er			2.27 s	I.T./0.208		1/2–			Er k x-ray
									0.2078
^{167}Er	22.869(9)	166.932046				7/2+	–0.5639	+3.57	

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{168}Er	26.978(18)	167.932368				0+			
^{169}Er		168.934588	9.40 d	β^- /0.351	0.35/≈ 100	1/2–	+0.485		Tm k x-ray
									0.1098
									0.1182
^{170}Er	14.910(36)	169.935461				0+			
^{171}Er		170.938026	7.52 h	β^- /1.491		5/2–	0.66	2.9	Tm k x-ray
									0.11160
									0.29591
									0.30832
									(0.08–1.4)
^{172}Er		171.939352	2.05 d	β^-/0.891	0.28/48				Tm k x-ray
					0.36/46				0.0597
									0.4073
									0.6101
^{173}Er		172.9424	1.4 m	β^- /2.6		(7/2–)			Tm k x-ray
									0.1928
									0.1992
									0.8952
^{174}Er		173.9441	3.1 m	β^- /1.8					Tm k x-ray
									(0.100–0.152)
^{175}Er		174.9479	1.2 m	β^-					(0.0765–1.168)
^{176}Er		175.9503							
^{177}Er		176.954							
$_{69}$Tm		**168.93421(2)**							
^{145}Tm			≈3.5 μs	p	1.73/91				
					1.4/9				
^{146m}Tm			0.21 s	β^+, p	p/1.118				
					1.01/				
					0.89/				
^{146}Tm		145.967	0.06 s	β^+/14.					
				p	1.119/				
					0.94/				
^{147m}Tm			0.4 ms	β^+, p	p/1.115				
^{147}Tm		146.961	0.56 s	EC, β^+/85	≈10.7				
				p/15/	1.052/				
^{148m}Tm		147.9573	0.7 s	β^+, EC/12.					ann.rad./
^{148}Tm									
^{149}Tm		148.9524	0.9 s	β^+, EC/≈9.2		11/2–			
^{150}Tm		149.9494	2.3 s	β^+, EC/≈11.5		6–			(0.1007–2.177)
^{151}Tm		150.9454	4. s	β^+, EC/7.5					ann.rad./
^{152m}Tm			8. s	β^+, EC/		9+			
^{152}Tm		151.9443	5. s	β^+, EC/8.8					ann.rad./
^{153}Tm		152.94203	1.6 s	β^+, EC/10 /6.46					ann.rad./
				α/90 /	5.109/				
^{154m}Tm			3.3 s	β^+, EC/15 /	α/5.031/100				ann.rad./
				α/	4.84/0.24				0.4605–0.7960
^{154}Tm		153.9407	8.1 s	β^+, EC/56 /7.4	α/4.956/100				ann.rad./
				α/44 /	4.83/0.45				
^{155}Tm		154.93919	30. s	β^+, EC/5.58					0.0315
				α/	4.46/				0.0638
									0.0881
									0.2268
									0.5320
									0.6067
^{156m}Tm			19. s	α/	4.46/				
^{156}Tm		155.9389	1.40 m	β^+, EC/7.6		2–	+0.40	–0.5	ann.rad./
				α/	4.23/				0.3446
									0.4529
									0.5860
^{157}Tm		156.9367	3.6 m	β^+, EC/4.5	2.6	1/2	+0.48		ann.rad./
				α/	3.97/				0.1104
									0.3484
									0.3855
									0.4550
									(0.1–1.58)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{158}Tm		157.9379	4.0 m	β^+, EC/74 /6.5		(2–)	+0.04	+0.7	ann.rad./
				EC/26 /					Er k x-ray
									0.1921
									0.3351
									0.6280
									1.1498
									(0.18–2.81)
^{159}Tm		158.9348	9.1 m	β^+/23 /3.9		5/2+	+3.42	+1.9	ann.rad./
				EC/77 /					Er k x-ray
									0.0591
									0.0848
									0.2713
									(0.05–1.27)
^{160m}Tm			1.24 m	IT		(5)			
^{160}Tm		159.9354	9.4 m	β^+/15 /5.9		1–	+0.16	+0.58	ann.rad./
				EC/85 /					Er k x-ray
									0.1264
									0.2642
									0.7285
									0.8544
									0.8614
									1.3685
^{161}Tm		160.9334	31. m	β^+, EC/3.2		7/2+	+2.40	+2.9	ann.rad./
									Er k x-ray
									0.0595
									0.0844
									1.6481
									(0.04–2.15)
^{162m}Tm			24. s	I.T./90 /		5+			Tm k x-ray
				β^+, EC/10 /					Er k x-ray
									0.0669
									0.8115
									0.9003
^{162}Tm		161.93394	21.7 m	β^+ /8 /4.81		1–	+0.07	+0.69	ann.rad./
				EC/92 /					Er k x-ray
									0.1020
									0.7987
									(0.1–3.75)m
^{163}Tm		162.93265	1.81 h	EC/98 /2.439		1/2+	–0.082		Er k x-ray
				β^+ /1 /					0.0692
									0.1043
									0.2414
^{164m}Tm			5.1 m	I.T./80 /		6–			0.0914
				β^+, EC/20 /					0.1394
									0.2081
									0.2405
									0.3149
^{164}Tm		163.93345	2.0 m	β^+ /36 /3.96	2.94/	1+	+2.38	+0.71	ann.rad./
				EC/64 /					Er k x-ray
									0.0914
^{165}Tm		164.932433	1.253 d	EC/1.593		1/2+	–0.139		Er k x-ray
									0.0472
									0.0544
									0.29728
									0.80636
^{166}Tm		165.93355	7.70 h	EC/98 /3.04		2+	+0.092	+2.14	Er k x-ray
				β^+ /2 /					0.0806
									0.1844
									0.7789
									1.2734
									2.0524
^{167}Tm		166.932849	9.24 d	EC/0.748		1/2+	–0.197		Er k x-ray
									0.0571
									0.20778
^{168}Tm		167.934171	93.1 d	EC/1.679		3+	+0.23	+3.2	Er k x-ray
									0.19825
									0.4475

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.81595
^{169}Tm	100	168.934211				1/2+	–0.232	–1.2	
^{170}Tm		169.935798	128.6 d	β^- /99.8/0.968	0.883/24	1–	+0.247	+0.74	Yb k x-ray
				EC/0.2 /0.314	0.968/76				0.08425
^{171}Tm		170.936426	1.92 y	β^- /0.096	0.03/2	1/2+	–0.230		0.06674
					0.096/98				
^{172}Tm		171.93840	2.65 d	β^- /1.88	1.79/36	2–			Yb k x-ray
					1.88/29				0.07879
									1.38722
									1.46601
									1.52982
									1.60861
^{173}Tm		172.93960	8.2 h	β^- /1.298	0.80/21	1/2+			Yb k x-ray
					0.86/71				0.3988
									0.4613
^{174}Tm		173.94216	5.4 m	β^- /3.08	0.70/14	(4–)			Yb k x-ray
					1.20/83				0.07664
									0.17669
									0.27332
									0.3666
									0.99205
									(0.08–1.6)
^{175}Tm		174.94383	15.2 m	β^- /2.39	0.9/36	(1/2+)			Yb k x-ray
					1.9/23				0.36396
									0.51487
									0.94125
									0.98247
^{176}Tm		175.9471	1.9 m	β^-/4.2	2.0/	(4+)			Yb k x-ray
					1.2/				0.1898
									0.3819
									1.0691
^{177}Tm		176.9490	1.4 m	β^-					
^{178}Tm		177.9526							
^{179}Tm		178.9553							
$_{70}$Yb		**173.04(3)**							
^{148}Yb		147.967							
^{149}Yb		148.963	0.7 s	β^+, p	p/2.5–6.4/				0.647
^{150}Yb		149.958							
^{151}Yb		150.9545	1.6 s	β^+ /8.5					
^{152}Yb		151.9502	3.2 s	β^+ EC/5.5					
^{153}Yb		152.9492	4. s	β^+ EC/6.7					
^{154}Yb		153.9455	0.40 s	β^+ EC/7 /4.49					ann.rad./
				α/93 /	5.32/				
^{155}Yb		154.9456	1.7 s	β^+, EC/16 /6.0			–0.8	–1.	ann.rad./
				α/84 /	5.19/				
^{156}Yb		155.94277	26. s	β^+, EC/21/3.57		0+			ann.rad./
				α/79 /	4.69/				
^{157}Yb		156.9427	39. s	β^+, EC/99+/5.5			–0.64		ann.rad./
				α/0.5/	4.69/				0.231
									(0.035–0.670)
^{158}Yb		157.93986	1.5 m	β^+, EC/1.9		0+			ann.rad./
									0.0741
									0.2526
^{159}Yb		158.9402	1.4 m	EC, β^+/5.1			–0.37	–.022	Tm k x-ray
									0.1661
									0.1772
									0.3297
									0.3903
^{160}Yb		159.9376	4.8 m	β^+, EC/2.0		0+			ann.rad./
									0.1404
									0.1737
									0.2158
^{161}Yb		160.9375	4.2 m	β^+, EC/3.9		3/2–	–0.33	+1.03	ann.rad./
									Tm k x-ray
									0.0782

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.5999
									0.6315
^{162}Yb		161.9358	18.9 m	β^+, EC/1.7		0+			ann.rad./
									Tm k x-ray
									0.1188
									0.1635
^{163}Yb		162.9363	11.1 m	β^+ /26 /3.4	1.4/	3/2–	–0.37	+1.24	ann.rad./
									Tm k x-ray
									0.0636
									0.8603
									(0.06 –1.9)
^{164}Yb		163.9345	1.26 h	EC/1.0		0+			Tm k x-ray
									0.0914
									0.6752
^{165}Yb		164.93540	9.9 m	β^+ /10 /2.76	1.58/	(5/2–)	+0.48	+2.48	ann.rad./
				EC/90 /					Tm k x-ray
									0.0801
									1.0903
^{166}Yb		165.93388	2.363 d	EC/0.30		0+			Tm k x-ray
									0.0828
									0.1844
									0.7789
									1.2734
									2.0524
^{167}Yb		166.934947	17.5 m	β^+ /0.5 /1.954	0.639/	5/2–	+0.62	+2.70	Tm k x-ray
				EC/99.5 /					0.06296
									0.10616
									0.11337
									0.17633
^{168}Yb	0.13(1)	167.933895				0+			
^{169m}Yb			46. s	I.T./0.0242		1/2–			Yb L x-ray
									0.0242
^{169}Yb		168.935187	32.02 d	EC/0.909		7/2+	–0.63	+3.5	0.1979/35.9
									0.3078/10.05
									0.0207–0.2611
^{170}Yb	3.04(15)	169.934759				0+			
^{171}Yb	14.28(57)	170.936323				1/2–	+0.49367		
^{172}Yb	21.83(67)	171.936378				0+			
^{173}Yb	16.13(27)	172.938207				5/2–	–0.67989	+2.80	
^{174}Yb	31.83(92)	173.938858				0+			
^{175}Yb		174.941273	4.19 d	β^- /0.470	0.466/73	7/2–	0.77		Lu k x-ray
					0.071/21				0.3963/13
					0.353/6.2				(0.114–0.28)
^{176m}Yb			11.4 s	I.T./1.051		(8–)			Yb k x-ray
									0.0961
									0.1901
									0.2929
									0.3897
^{176}Yb	12.76(41)	175.942569	10^{26} y	$\beta^-\beta^-$		0+			
^{177m}Yb			6.41 s	I.T./0.3315		1/2–			Yb k x-ray
									0.1131
									0.2084
^{177}Yb		176.945257	1.9 h	β^- /1.399	1.40	9/2+			Lu k x-ray
									0.1504
^{178}Yb		177.94664	1.23 h	β^- /0.65	0.25/	0+			0.1415
									0.3246
									0.3516
									0.3815
									0.6125
^{179}Yb		178.9499	8. m	β^- /2.4					
^{180}Yb		179.9523	2. m	β^-					0.1028–0.4423
^{181}Yb		180.9561							
$_{71}$Lu		**174.967(1)**							
^{150m}Lu			≈0.03 ms	p/1.295					
^{150}Lu		149.973	49. ms	p					

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{151m}Lu			16 μs	p/1.31					
^{151}Lu		150.967	0.08 s	p/1.231					
^{152}Lu		151.963	0.7 s						
^{153}Lu		152.959							
^{154}Lu		153.9571	1.0 s	β^+, EC/10.8					
^{155m}Lu			2.6 ms	α/7.41					
^{155}Lu		154.9542	0.07 s	EC/8.0					
				α/	5.66/90				
^{156m}Lu			0.20 s	α/	5.57/				
^{156}Lu		155.9529	≈ 0.5 s	β^+, EC/9.5					ann.rad./
				α/	5.45/				
^{157m}Lu			≈9.6 s	α	4.925/				
^{157}Lu		156.95010	4.8 s	β^+, EC/94 /6.93					ann.rad./
				α/	5.00/				
^{158}Lu		157.94984	10.4 s	β^+, EC/99 /8.0					ann.rad./
				α/	4.67/				0.3682
									0.4770
^{159}Lu		158.9467	12.3 s	β^+, EC/6.0					ann.rad./
									0.1505
									0.1875
									0.3693
^{160}Lu		159.94654	36.1 s	β^+, EC/7.3					ann.rad./
									0.2434
									0.3957
									0.5773
^{161}Lu		160.9432	1.2 m	β^+, EC/5.3					ann.rad./
									0.0437
									0.0671
									0.1003
									0.1108
									0.1562
									0.2562
^{162m}Lu			≈ 1.5 m	EC/		4–			
^{162}Lu		161.9432	1.37 m	β^+, EC/6.9		1–			ann.rad./
									0.1666
									0.6314
^{163}Lu		162.9412	4.1 m	β^+, EC/4.6					ann.rad./
									0.0539
									0.0581
									0.1504
									0.1631
									0.3717
^{164}Lu		163.9412	3.14 m	β^+, EC/6.3	1.6/				0.1238
					3.8/				0.2621
									0.7404
									0.8639
									0.8804
^{165}Lu		164.9396	10.7 m	β^+, EC/3.9	2.06/	1/2+			ann.rad./
									0.1206
									0.1324
									0.1742
									0.2036
									(0.04–2.0)
^{166m2}Lu			2.1 m	β^+ /35 /		(0–)			ann.rad./
				EC/65 /					Yb k x-ray
									1.0673
									1.2566
									2.0986
^{166m1}Lu			1.4 m	β^+, EC/58 /		(3–)			ann.rad./
				I.T./42 /0.0344					0.1024
									0.2281
									0.2861
									0.8119
									0.8301
^{166}Lu		165.9398	2.8 m	β^+ /25 /5.5		(6–)			ann.rad./
				EC/75 /					Yb k x-ray
									0.1024

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.2281
									0.3375
									0.3679
^{167}Lu		166.9383	52. m	β^+ /2 /3.1	2.1/	7/2+			Yb k x-ray
				EC/98 /					0.0297
									0.2392
									(0.03–2.0)
^{168m}Lu			6.7 m	β^+ /12 /		3+			ann.rad./
				EC/88 /					Yb k x-ray
				IT/<0.8					0.1988/190
									0.8960/100
									0.9792/128
									0.018–2.65
^{168}Lu		167.9387	5.5 m	β^+ /6 /4.5	1.2/	(6–)			ann.rad./
				EC/94 /					Yb k x-ray
									0.1114
									0.1124
									0.2286
									0.3483
									1.4836
^{169m}Lu			2.7 m	I.T./0.0290		1/2–			Lu L x-ray
									0.0290
^{169}Lu		168.93765	1.419 d	EC/2.293	1.271/	7/2+	2.30	3.5	Yb k x-ray
									0.19121
									0.9606
									(0.08–2.1)
^{170m}Lu			0.7 s	I.T./0.0929		4–			Lu L x-ray
									0.04449
									0.0484
^{170}Lu		169.93847	2.01 d	EC/3.46	2.44/	0+			Yb k x-ray
									0.58711
									0.5908
									1.28029
									(0.1–3.38)
^{171m}Lu			1.31 m	I.T./0.0711		1/2–			Lu k x-ray
									0.07119
^{171}Lu		170.937910	8.24 d	EC/1.479	0.362/	7/2+	2.30	3.42	Yb k x-ray
									0.01939
									0.66744
									(0.02–1.3)
^{172m}Lu			3.7 m	I.T./0.0419		1–			Lu L x-rays
									0.04186
^{172}Lu		171.939082	6.64 d	EC/2.519		4–	2.90	3.80	Yb k x-ray
									0.18156
									1.09367
									(0.07–2.2)
^{173}Lu		172.938927	1.37 y	EC/0.671		7/2+	2.28	3.63	Yb k x-ray
									0.07860
									0.27198
^{174m}Lu			142. d	IT/99.3/	0.17086	6–	1.50		Lu k x-ray
				EC/0.7 /					0.067055
^{174}Lu		173.940334	3.3 y	EC/1.374		1–	1.9		Yb k x-ray
									0.07664
									1.2419
^{175}Lu	97.41(2)	174.940768				7/2+	+2.2327	+3.49	
^{176m}Lu			3.66 h	β^- /1.315	1.229/	1–	+0.318	–1.47	Hf k x-ray
					1.317/				0.088372
^{176}Lu	2.59(2)	175.942683	3.73×10^{10} y	β^- /1.192		7–	+3.169	+4.92	Hf k x-ray
									0.20187
									0.30691
^{177m2}Lu			6. m	β^-		39/2–			
^{177m}Lu			160.7 d	IT/22/0.9702		23/2–	2.33	5.4	Lu k x-ray
				β^- /78					Hf k x-ray
									0.11295
									0.20836
									0.37850
									0.41853

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{177}Lu		176.943755	6.65 d	β^- /0.498	0.497/	7/2+	+2.239	+3.39	0.11295
									0.20836
^{178m}Lu			23.1 m	β^- /		(9–)			0.2166
									0.3317
^{178}Lu		177.945952	28.5 m	β^-/2.099	2.03/	1+			Hf k x-ray
									0.0932
									1.3099
									1.3408
									(0.09–1.7)
^{179}Lu		178.94732	4.6 h	β^- /1.405	1.35/	7/2+			0.2143
									0.3377
^{180}Lu		179.9499	5.7 m	β^- /3.1	1.49/				0.40795/50.
									(0.07–1.9)
^{181}Lu		180.9518	3.5 m	β^- /2.5		(7/2+)			0.0458
									0.2059
									0.5749
^{182}Lu		181.9552	2.0 m	β^- /≈ 4.1					0.0978
									0.7208
									0.8182
^{183}Lu		182.9576	58. s	β^- /		7/2+			
^{184}Lu		183.9612	20 s	β^-					
$_{72}$Hf		**178.49(2)**							
^{154}Hf		153.964	2. s	EC, β^+/≈ 6.7					
^{155}Hf		154.963	0.9 s	EC, β^+/8.					
^{156}Hf		155.9593	25. ms	α/					
^{157}Hf		156.9581	0.11 s	α/					
^{158}Hf		157.9539	2.9 s	EC/54 /5.1		0+			
				α/46 /	5.27/				
^{159}Hf		158.9538	5.6 s	β^+, EC/88 /6.9					ann.rad./
				α/12 /	5.09/				
^{160}Hf		159.95063	≈ 12. s	β^+, EC/97 /4.9		0+			ann.rad./
				α/4.78					
^{161}Hf		160.9503	17. s	α/	4.60/				
^{162}Hf		161.94720	38. s	β^+, EC/3.7		0+			ann.rad./
									0.1739
									0.1963
									0.4101
^{163}Hf		162.9471	40. s	β^+, EC/5.5					ann.rad./
									0.0454
									0.0621
									0.0710
									0.6882
^{164}Hf		163.9536	2.8 m	EC, β^+/3.0					
^{165}Hf		164.9445	1.32 m	EC/4.6		11/2–			
^{166}Hf		165.9423	6.8 m	EC/93 /2.3					ann.rad./
				β^+ /7 /					Lu k x-ray
									0.0788
^{167}Hf		166.9426	2.0 m	β^+ /40 /4.0		(5/2–)			ann.rad./
				EC/60 /					Lu k x-ray
									0.1754
									0.3152
^{168}Hf		167.9406	25.9 m	β^+, EC/1.8		0+			ann.rad./
									(0.0144–1.311)
^{169}Hf		168.9412	3.25 m	EC/85 /3.3		(5/2–)			ann.rad./
				β^+ /15 /					Lu k x-ray
									0.3695
									0.4929
^{170}Hf		169.9397	16.0 h	EC/1.1		0+			Lu k x-ray
									0.0985
									0.1202
									0.1647
									0.5729
									0.6207
^{171m}Hf			30. s			(1/2–)	+0.53		
^{171}Hf		170.9405	12.2 h	EC, β^+ /2.4		7/2+	–0.67	+3.46	ann.rad./

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									Lu k x-ray
									0.1221
									0.6620
									1.0714
^{172}Hf		171.93946	1.87 y	EC/0.35		0+			Lu k x-ray
									0.02399
									0.12582
									(0.0818–0.123)
^{173}Hf		172.9407	23.6 h	EC/1.6		1/2–			Lu k x-ray
									0.12367
									0.13963
									0.29697
									0.31124
									(0.1–2.1)
^{174}Hf	0.16(1)	173.940042	2.0×10^{15} y			0+			
^{175}Hf		174.941504	71. d	EC/0.686		5/2–	–0.60	+2.7	Lu k x-ray
									0.08936
									0.34340
^{176}Hf	5.26(7)	175.941403				0+			
^{177m2}Hf			51.4 m	I.T./2.740		37/2–			Hf k x-ray
									0.2140
									0.2951
									0.3115
									0.3267
^{177m1}Hf			1.1 s	I.T./		23/2+			Hf k x-ray
									0.20836
									0.22847
									0.37851
^{177}Hf	18.60(9)	176.943220				7/2–	+0.7935	+0.337	
^{178m2}Hf			31. y	I.T./		16+	+8.16	+6.00	Hf k x-ray
									0.32555
									0.42635
									0.089–0.574
^{178m1}Hf			4.0 s	I.T./		8–			Hf k x-ray
									0.21342
									0.32555
									0.42635
^{178}Hf	27.28(7)	177.943698				0+			
^{179m2}Hf			25.1 d	I.T./1.1057		25/2–	7.4		Hf k x-ray
									0.1227
									0.1461
									0.3626
									0.4537
^{179m1}Hf			18.7 s	I.T./0.375		1/2–			Hf k x-ray
									0.1607
									0.2141
^{179}Hf	13.62(2)	178.945815				9/2+	–0.641	+3.79	
^{180m}Hf			5.52 h	I.T./1.1416		8–	+9.	+4.6	Hf k x-ray
									0.2152
									0.3323
									0.4432
^{180}Hf	35.08(16)	179.946549				0+			
^{181m}Hf			1.5 ms	/1.738		25/2–			
^{181}Hf		180.949099	42.4 d	β^- /1.027	0.408/	1/2–			Ta k x-ray
									0.13294/54
									0.48200/100
									0.3459/20
^{182m}Hf			62. m	β^- /54 /1.60	0.49/43	8–			Hf k x-ray
				IT/46 /1.173	0.95/10				0.0509
									0.2244
									0.3441
									0.4558
									0.5066
									0.9428
^{182}Hf		181.95055	$9. \times 10^6$ y	β^- /0.37		0+			Ta k x-ray
									0.2704
^{183}Hf		182.95353	1.07 h	β^- /2.01	1.18/68	3/2–			Ta k x-ray

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
					1.54/25				0.0732
									0.4591
									0.7837
^{184}Hf		183.95545	4.1 h	β^- /1.34	0.74/38	0+			Ta k x-ray
					0.85/16				0.0414
					1.10/46				0.1391
									0.3449
^{185}Hf		184.9588	≈3.5 m	β^- /					0.165
^{186}Hf		185.9609	≈2.6 m						0.738
$_{73}$Ta		**180.9479(1)**							
^{155}Ta			12 μs	p/1.77					
^{156}Ta		155.972	0.11 s	β^+ /≈11.6					
				p/	1.02/≈100				
^{157}Ta		156.968	10 ms	α/	6.117				
				p/	0.927/3.4				
^{158}Ta		157.9664	37. ms	α/	6.05/100				
					5.97/100				
^{159}Ta		158.9629	0.6 s	β^+, EC/20 /8.5	α/5.52/34				ann.rad./
				α/80 /	5.60/55				
^{160}Ta		159.9615	1.4 s	β^+, EC/10.1					ann.rad./
				α	5.41/				
^{161}Ta		160.9584	2.9 s	β^+, EC/7.5					ann.rad./
				α/	5.15				
^{162}Ta		161.9564	4. s	EC/8.6					
^{163}Ta		162.9544	10.6 s	EC/6.8					
^{164}Ta		163.9536	14.2 s	β^+ /8.5		3+			ann.rad./
				α/	4.62/				0.2110
									0.3768
^{165}Ta		164.9508	31. s	ECβ^+/5.9					
^{166}Ta		165.9505	34. s	β^+ /82 /7.7					ann.rad./
				EC/18 /					Hf k x-ray
									0.1587
									0.3117
									0.8101
^{167}Ta		166.9486	1.4 m	β^+, EC/5.6					ann.rad./
^{168}Ta		167.9478	2.4 m	β^+ /77 /6.7		3+			ann.rad./
				EC/23 /					Hf k x-ray
									0.1239
									0.2615
									0.7502
^{169}Ta		168.9459	4.9 m	β^+, EC/4.4					ann.rad./
									0.0288
									0.1535
									0.1924
^{170}Ta		169.9461	6.8 m	β^+/70 /6.0		(3+)			ann.rad./
				EC/35 /					Hf k x-ray
									0.1008
									0.2212
^{171}Ta		170.9445	23.3 m	β^+, EC/3.7		(5/2–)			0.0496
									0.5018
									0.5064
									(0.05–1.02)
^{172}Ta		171.9447	36.8 m	β^+ /25 /4.9		(3–)			ann.rad./
				EC/75 /					Hf k x-ray
									0.21396
									1.10923
									(0.09 –3.8)
^{173}Ta		172.9446	3.6 h	β^+ /24 /3.7		(5/2–)	1.70	–1.9	ann.rad./
				EC/76 /					Hf k x-ray
									0.06972
									0.17219
									(0.06 –2.7)
^{174}Ta		173.9442	1.12 h	β^+ /27 /3.8		(3+)			ann.rad./
				EC/73 /					Hf k x-ray
									0.09089

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.20638
									(0.09–3.64)
^{175}Ta		174.9437	10.5 h	EC/2.0		7/2+	2.27	+3.7	Hf k x-ray
									0.2077
									0.2671
									0.3487
^{176}Ta		175.9447	8.1 h	EC/3.1		1–			Hf k x-ray
									0.08837
									1.15735
^{177}Ta		176.944472	2.356 d	EC/1.166		7/2+	2.25		Hf k x-ray
									0.11295
									(0.07–1.06)
^{178m}Ta			2.4 h	EC/		(7–)			Hf k x-ray
									0.08886
									0.21342
									0.32555
									0.42635
^{178}Ta		177.9458	9.29 m	EC/99 /1.9		1+	+2.74	+0.65	ann.rad./
				β^+ /1 /					Hf k x-ray
									0.09316
^{179}Ta		178.94593	1.8 y	EC/0.110		7/2+	2.29	3.37	Hf k x-ray
^{180m}Ta	0.012(2)		$>1.2 \times 10^{15}$ y			(9–)	4.82		
^{180}Ta		179.947466	8.15 h	EC/87 /0.854		1+			Hf k x-ray
				β^- /13 /0.708	0.61/3				W k x-ray
					0.71/10				0.09333
									0.10340
^{181}Ta	99.988(2)	180.947996				7/2+	+2.370	+3.3	
^{182m}Ta			15.8 m	I.T./0.5198		10–			Ta k x-ray
									0.14678
									0.17157
^{182}Ta		181.950152	114.43 d	β^- /1.814	0.25/30	3–	+3.02	+2.6	W k x-ray
					0.44/20				1.12127/100
					0.52/40				1.22138/79
									0.085–1.289
^{183}Ta		182.951373	5.1 d	β^- /1.070	0.45/5	7/2+	+2.36		W k x-ray
					0.62/91				0.0847
									0.0991
									0.1079
									0.2461
									0.3540
^{184}Ta		183.95401	8.7 h	β^- /2.87	1.11/15	(5–)			W k x-ray
					1.17/81				0.2528/44.
									0.4140/74.
									(0.09–1.4)
^{185}Ta		184.95556	49. m	β^- /1.99	1.21/5	(7/2+)			W k x-ray
					1.77/81				0.0697
									0.1739
									0.1776
^{186}Ta		185.9586	10.5 m	β^- /3.9	2.2/	(3–)			W k x-ray
									0.1979
									0.2149
									0.5106
									(0.09–1.5)
^{187}Ta		186.9604							
^{188}Ta		187.9637							
$_{74}$W		**183.84(1)**							
^{158m}W			0.14 ms	α	8.28(3)/				
^{158}W		157.974	1.3 ms	α/	6.433/96				
^{159}W		158.972	7. ms	α/					
^{160}W		159.9684	0.08 s	α/	5.92/	0+			
^{161}W		160.9671	0.41 s	β^+, EC/18 /8.1					
				α/82 /	5.78/				
^{162}W		161.9626	1.39 s	β^+, EC/54 /5.8		0+			
				α/46 /	5.54/				
^{163}W		162.9624	2.8 s	β^+, EC/59 /7.5					

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				α/41 /	5.38/				
^{164}W		163.95890	6. s	β^+, EC/97 /5.0		0+			ann.rad./
				α/3 /	5.15/				
^{165}W		164.9583	5.1 s	β^+, EC/99 /7.0					ann.rad./
				α/1 /	4.91/				
^{166}W		165.95502	16. s	β^+, EC/99 /4.2		0+			ann.rad./
				α/1 /	4.74/				
^{167}W		166.9547	20. s	EC/5.6					
^{168}W		167.9519	53. s	EC/3.8					ann.rad./
				α/10^{-5}/	4.40(1)				Ta k x-ray
									0.1755
									(0.037–0.573)
^{169}W		168.9518	1.3 m	EC/5.4					ann.rad./
									Ta k x-ray
									0.123
									(0.097–0.699)
^{170}W		169.9485	2.4 m	EC/2.2					ann.rad./
									Ta k x-ray
									0.3162
									(0.060–0.144)
^{171}W		170.9494	2.4 m	EC/4.6					ann.rad./
									Ta k x-ray
									0.1842
									(0.052–0.479)
^{172}W		171.9474	6.6 m	β^+, EC/2.5					ann.rad./
									Ta k x-ray
									0.0389
									(0.034–0.674)
^{173}W		172.9489	6.3 m	EC/4.0					ann.rad./
									Ta k x-ray
									0.4576
									(0.035–0.623)
^{174}W		173.9462	35. m	EC/1.9		0+			ann.rad./
									Ta k x-ray
									0.3287
									0.4288
									(0.056–0.429)
^{175}W		174.9468	35. m	EC/2.9		1/2–			(0.015–0.27)
^{176}W		175.9456	2.5 h	β^+, EC/0.8		0+			0.03358
									0.06129
									0.09487
									0.10020
^{177}W		176.9466	2.21 h	EC/2.0		(1/2–)			Ta k x-ray
									0.15505
									0.18569
									0.42694
^{178}W		177.9459	21.6 d	EC/0.091		0+			Ta k x-ray
^{179m}W			6.4 m	IT/99.7/0.222		(1/2–)			W k x-ray
				EC/0.3/					0.2220
^{179}W		178.94707	38. m	EC/1.06		(7/2–)			Ta k x-ray
									0.0307
^{180}W	0.12(1)	179.946706	7.4×10^{16} y	α/		0+			
^{181}W		180.94820	121.1 d	EC/0.188		9/2+			Ta k x-ray
									0.13617
									0.15221
^{182}W	26.50(16)	181.948205	8.3×10^{18} y	α/		0+			
^{183m}W			5.15 s	I.T./		(11/2+)			W k x-ray
									0.0465
									0.0526
									0.0991
									0.1605
^{183}W	14.31(4)	182.950224	1.9×10^{18} y	α/		1/2–	+0.1177848		
^{184}W	30.64(2)	183.950932	4.0×10^{18} y	α/		0+			
^{185m}W			1.6 m	I.T./0.1974		11/2+			W k x-ray
									0.0659
									0.1315
									0.1737

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{185}W		184.953420	74.8 d	β^- /0.433	0.433/99.9	3/2–			0.12536
^{186}W	28.43(19)	185.954362	6.5×10^{18} y	α/		0+			
^{187}W		186.957158	23.9 h	β^- /1.311	0.624/66	3/2–	0.62		Re k x-ray
					1.315/16				0.68572/33
					0.081–1.18				0.134–0.773
^{188}W		187.958487	69.78 d	β^- /0.349	0.349/99	0+			0.0636
									0.2271
									0.2907
^{189}W		188.9619	10.6 m	β^- /2.5	1.4/	(3/2–)			(0.1262–1.466)
					2.5/				
^{190m}W			0.3 ms						
^{190}W		189.9632	30. m	β^- /1.3	0.95/	0+			Re k x-ray
									0.1576
									0.1621
$_{75}$Re		**186.207(1)**							
^{160}Re		159.981	0.7 ms	p/	1.261(6)/91				
				α/	6.54/				
^{161}Re		160.978	14 ms	α/	6.24				
				p	1.35				
^{162}Re		161.9757	0.10 s	α/	6.12/94				
					6.09/94				
^{163}Re		162.9721	0.26 s	β^+, EC/9.0	α/5.87/32				
				α/	5.92/66				
^{164}Re		163.9704	0.9 s	β^+, EC/10.7					
				α/	5.78/				
^{165}Re		164.9671	2. s	β^+, EC/87 /8.1					
				α/	5.51/				
^{166}Re		165.9651	2.5 s	β^+, EC/9.4					
				α/	5.50/				
^{167m}Re			6.2 s	α, EC/					
^{167}Re		166.9626	3.4 s	β^+, EC/7.4					
				α/	5.015/				
^{168}Re		167.9616	4.4 s	β^+, EC/9.1					
				α/	4.833/				0.1117
^{169m}Re			8.1 s	α	4.70/				
					4.87/				
^{169}Re		168.9588	16. s						
^{170}Re		169.9582	9.2 s	β^+, EC/9.0					0.1560
									0.3055
									0.4125
^{171}Re		170.9555	15.2 s	EC/≈ 5.7					
^{172m}Re			55. s	β^+, EC/		(2)			ann.rad./
									0.1234
									0.2537
									0.3504
^{172}Re		171.9553	15. s	β^+, EC/7.3					ann.rad./
									0.1234
									0.2537
^{173}Re		172.9531	2.0 m	EC/≈3.9					ann.rad./
^{174}Re		173.9521	2.4 m	β^+, EC/5.6					ann.rad./
									0.1119
									0.2430
^{175}Re		174.9514	5.8 m	β^+, EC/4.3					ann.rad./
^{176}Re		175.9516	5.3 m	β^+, EC/5.6		(3+)			ann.rad./
									0.1089
									0.2406
^{177}Re		176.9503	14. m	EC/78 /3.4		(5/2–)			ann.rad./
				β^+ /22 /					W k x-ray
									0.0797
									0.0843
									0.1968
^{178}Re		177.9509	13.2 m	β^+ /11 /4.7	3.3/	(3)			ann.rad./
				EC/89 /					W k x-ray
									0.1059
									0.2373

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.9391
^{179}Re		178.9500	19.7 m	EC/99 /2.71	0.95/	(5/2+)	2.8		W k x-ray
				β^+ /1 /					0.1199
									0.2900
									0.4154
									0.4302
									1.6803
^{180}Re		179.95079	2.45 m	EC/92 /3.80	1.76/	1–	1.6		ann.rad./
				β^+ /8 /					W k x-ray
									0.1036
									0.9028
									(0.07–2.2)
^{181}Re		180.95006	20. h	EC /1.74		5/2+	3.19		W k x-ray
									0.3607
									0.3655
									0.6390
^{182m}Re			12.7 h	EC/	0.55/	2+	3.3	+1.8	W k x-ray
					1.74/				0.0677
									1.1214
									1.2215
									(0.06–2.2)
^{182}Re		181.9512	2.67 d	EC/2.8		(7+)	2.8	+4.1	W k x-ray
									0.0678
									0.2293
									1.1213
									1.2214
^{183}Re		182.95082	70. d	EC/0.56		(5/2+)	+3.17	+2.3	W k x-ray
									0.16232
^{184m}Re			165. d	I.T./75 /0.188		8+	+2.9		Re k x-ray
				EC/25 /					0.1047
									0.2165
									0.92093
									(0.10–1.1)
^{184}Re		183.95252	38. d	EC/1.48		3–	+2.53	+2.8	W k x-ray
									0.79207
									0.90328
									(0.1–1.4)
^{185}Re	37.40(2)	184.952955				5/2+	+3.1871	+2.18	
^{186m}Re			2.0×10^5 y	I.T./0.150		8+			Re k x-ray
									0.0590
^{186}Re		185.954986	3.718 d	β^- /92 /1.070	0.973/21	1–	+1.739	+0.62	W k x-ray
				EC/8 /0.582	1.07/71				0.1227/0.6
									0.1372/9.5
									(0.63–0.77)
^{187}Re	62.60(2)	186.955751	4.2×10^{10} y	β^- /0.00266	0.0025/	5/2+	+3.2197	+2.07	
^{188m}Re			18.6 m	I.T./0.172		(6–)			Re k x-ray
									0.0925
									0.1059
^{188}Re		187.958112	17.00 h	β^- /2.120	1.962/20	1–	+1.788	+0.57	Os k x-ray
					2.118/79				0.15502
									0.309–2.022
^{189}Re		188.959228	24. h	β^- /1.01	1.01/	(5/2+)			0.1471
									0.2167
									0.2194
									0.2451
^{190m}Re			3.0 h	β^- /51 /		(6–)			Re k x-ray
				I.T./49 /					0.1191
									0.2238
									0.6731
									(0.1–1.79)
^{190}Re		189.9618	3.0 m	β^- /3.2	1.8/	(2–)			Os k x-ray
									0.1867
									0.5580
									0.6051
^{191}Re		190.96312	9.7 m	β^- /2.05	1.8/				
^{192}Re		191.9660	16. s	β^- /4.2	$\approx$ 2.5/				(0.2–0.75)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
$_{76}$Os		**190.23(3)**							
^{162}Os		161.984	1.8 ms	α/	6.60				
^{163}Os		162.982	5.5 ms	α/	6.51				
^{164}Os		163.9779	0.04 s	α					
^{165}Os		164.9765	0.07 s	α					
^{166}Os		165.9718	0.18 s	β^+, EC/28 /6.3	6.27/	0+			ann. rad./
				α/72 /	5.98/				
^{167}Os		166.9714	0.7 s	β^+, EC/76 /8.2					ann.rad./
				α/24 /	5.84/				
^{168}Os		167.96775	2.2 s	β^+, EC/51 /5.7		0+			ann. rad./
				α/49 /					
^{169}Os		168.9671	3.3 s	β^+, EC/89 /7.7	5.57/80				ann.rad./
				α/13 /	5.51/12				
					5.54/8				
^{170}Os		169.96357	7.1 s	β^+, EC/5.0		0+			ann.rad./
				α/	5.40/				(0.162–0.216)
^{171}Os		170.9630	8.4 s	β^+, EC/98 /7.1	α/5.24/93.5				ann.rad./
				α/19 /	5.17/6.5				0.190–0.705
^{172}Os		171.9601	19. s	β^+, EC/99 /4.5		0+			ann.rad./
				α/1.1/	5.10/				(0.063–1.120)
^{173}Os		172.9598	16. s	β^+, EC/6.3					ann.rad./
				α/0.4 /	4.94/				0.142–0.299
^{174}Os		173.9563	44. s	β^+, EC/3.9		0+			0.118
				α/0.02 /	4.76/				0.138 / 0.001
									0.158
									0.325
^{175}Os		174.9570	1.4 m	β^+, EC/5.3					0.125
									0.181
									0.248
^{176}Os		175.9550	3.6 m	β^+, EC/3.2		0+			0.8155
									0.7758
									0.8573
									1.2093
									1.2909
^{177}Os		176.9551	2.8 m	β^+, EC/4.5		(1/2–)			0.0848
									0.1958
									0.3002
									1.2686
^{178}Os		177.9534	5.0 m	β^+, EC/2.3		0+			ann.rad./
									0.5946
									0.6850
									0.9687
									1.3311
^{179}Os		178.9539	7. m	β^+, EC/3.7					ann.rad./
									0.0654
									0.2186
									0.5938
^{180}Os		179.9524	21.5 m	β^+, EC/1.5		0+			Re k x-ray
									0.0202–0.7174
^{181m}Os			1.75 h	EC/		(1/2–)			ann.rad./
									0.0489
^{181}Os		180.9532	2.7 m	EC/2.9		(7/2–)			ann.rad./
									0.11794
									0.23868
									0.8267
									(0.07–2.64)
^{182}Os		181.95219	21.5 h	EC/0.9		0+			Re k x-ray
									0.1802
									0.5100
^{183m}Os			9.9 h	EC/84 /		1/2–			Os k x-ray
				I.T./16 /					Re k x-ray
									1.1020
									1.1080
^{183}Os		182.9531	13. h	EC/2.1		9/2+	–0.79	+3.1	Re k x-ray
									0.1144
									0.3818

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{184}Os	0.02(1)	183.952491				0+			
^{185}Os		184.954043	93.6 d	EC/1.013		1/2–			Re k x-ray
									0.6461
									0.8748
									0.8805
^{186}Os	1.59(3)	185.953838	2. × 10^{15} y	α/	≈ 2.75/	0+			
^{187}Os	1.96(2)	186.955748				1/2–	+0.0646519		
^{188}Os	13.24(8)	187.955836				0+			
^{189m}Os			5.8 h	I.T./0.0308		9/2–			Os L x-ray
									0.0308
^{189}Os	16.15(5)	188.958145				3/2+	+0.65993	+0.86	
^{190m}Os			9.9 m	I.T./1.705		10–	–0.6		Os k x-ray
									0.1867
									0.3611
									0.5026
									0.6161
^{190}Os	26.26(2)	189.958445				0+			
^{191m}Os			13.1 h	I.T./0.0744		3/2–			Os k x-ray
									0.0744
^{191}Os		190.960928	15.4 d	β^- /0.314	0.140/100	9/2–		+2.5	Ir k x-ray
									0.1294
^{192m}Os			6.0 s	I.T./2.0154		(10–)			Os k x-ray
									0.2058/65.9
									0.5692/70
									(0.201–1.000)
^{192}Os	40.78(19)	191.961479				0+			
^{193}Os		192.964148	30.5 h	β^- /1.141	1.04/20	3/2–	+0.730	+0.47	Ir k x-ray
									0.1389
									0.4605
^{194}Os		193.965179	6.0 y	β^- /0.097	0.054/33	0+			Ir L x-ray
					0.096/67				0.0429
^{195}Os		194.9681	6.5 m	β^- /2.0	2.0/				
^{196}Os		195.96962	34.9 m	β^- /1.16	0.84/	0+			0.1262/5
									0.4079/5.9
$_{77}$Ir		**192.217(3)**							
^{164}Ir			0.06 ms	p	1.78				
^{165}Ir		164.9876	0.3 ms	p/87	1.71				
				α/13	6.72				
^{166m}Ir			15 ms	α/98.2	6.56				
				p/1.8	1.32				
^{166}Ir		165.9855	≈ 11 ms	α/93	6.56				
				p/6.9	1.15				
^{167m}Ir			30 ms	α/48, β^+	6.41/80				
				p/32	1.24/0.4				
^{167}Ir		166.9817	35. ms	α/80, β^+	6.35/48				
				p/0.4	1.04/32				
^{168}Ir		167.9799	0.16 s	α/82					
^{169m}Ir			0.3 s	α/	6.11/84				
^{169}Ir		168.9764	0.6 s	α/	6.00/50				
^{170}Ir		169.9743	0.43 s	α/	6.03/				
^{171}Ir		170.9718	1.3 s	α/	5.91/				
^{172}Ir		171.9706	2.1 s	α/	5.811/				0.228
									(0.379–0.475)
^{173}Ir		172.9677	3.0 s	α/	5.665/				0.0493
									(0.092–0.296)
^{174}Ir		173.9668	4. s	α/	5.478/				0.1587
									(0.276–1.33)
^{175}Ir		174.9641	≈ 4.5 s	α/	5.393/				0.1056
^{176}Ir		175.9635	8. s	EC, β^+/80					0.260
				α/3.2/	5.118/				(0.135–0.415)
^{177}Ir		176.9612	30. s	EC, β^+/5.7					0.184
				α/0.06/	5.011/				(0.062–0.194)
^{178}Ir		177.9601	12. s	β^+, EC/6.3					
									0.1320
									0.2667

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.3633
^{179}Ir		178.9592	4. m	EC/4.9					0.0975
									(0.045–0.220)
^{180}Ir		179.9593	1.5 m	EC/6.4					0.2765
									((0.132–1.106)
^{181}Ir		180.9576	4.9 m	β^+, EC/4.1		(7/2+)			ann.rad./
									0.1076
									(0.0196–1.715)
^{182}Ir		181.9582	15. m	β^+ /44 /5.6					ann.rad./
				EC/56 /					Os k x-ray
									0.1273
									0.2370
^{183}Ir		182.9568	57. m	β^+, EC/3.5					ann.rad./
									0.0877
									0.2285
									0.2824
^{184}Ir		183.9574	3.0 h	β^+ /12 /4.6	2.3/	5–	0.70	+2.41	ann.rad./
				EC/88 /	2.9/				Os k x-ray
									0.11968
									0.2640
									0.3904
^{185}Ir		184.9566	14. h	β^+ /3 /2.4		(5/2–)	2.60	–2.1	ann.rad./
				EC/97 /					Os k x-ray
									0.2543
									1.8288
^{186m}Ir			1.7 h	EC /		(2–)	0.64	+1.46	Os k x-ray
									0.1371
									0.7675
^{186}Ir		185.95795	15.7 h	EC/98 /3.83		(5+)	3.9	–2.55	Os k x-ray
				β^+ /2 /					0.1372
									0.2968
									0.4348
									(0.13–3.0)
^{187}Ir		186.95736	10.5 h	EC/1.50		3/2+		+0.94	Os k x-ray
									0.0743
									0.4009
									0.4271
									0.6109
									0.9128
^{188}Ir		187.95885	1.72 d	β^+ /2.81	1.13/	(2–)	0.30	+0.48	Os k x-ray
				EC/99+ /	1.64/				0.1550
									0.4780
									0.6330
									2.2146
^{189}Ir		188.95872	13.2 d	EC/0.53		3/2+	0.13	+0.88	Os k x-ray
									0.2449
^{190m2}Ir			3.09 h	β^+, EC/95 /		(11–)			0.376
				I.T./5 /					
^{190m1}Ir			1.12 h	I.T. /0.0263		7+			Ir L x-ray
^{190}Ir		189.9606	11.8 d	EC/2.0		(4+)	0.04	+2.8	Os k x-ray
									0.1867
									0.4072
									0.5186
									0.5580
									0.6051
									(0.2–1.4)
^{191m}Ir			4.93 s	I.T./0.1714		11/2–	+0.603		Ir k x-ray
									0.1294
^{191}Ir	37.3(2)	190.960591				3/2+	+0.151	+0.82	
^{192m2}Ir			241. y	I.T./0.161		(9+)			Ir k x-ray
^{192m1}Ir			1.44 m	I.T./0.0580		(1+)			Ir L x-ray
									0.0580
									0.3165
^{192}Ir		191.962602	73.83 d	β^- /1.460		(4–)	+1.92	+2.15	Pt k x-ray
									0.31649/83.
									0.46806/48.
^{193m}Ir			10.53 d	I.T./0.0802		11/2–			Ir L x-ray

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.0803
^{193}Ir	62.7(2)	192.962923				3/2+	+0.164	+0.75	
^{194m}Ir			170. d	β^- /		11			Pt k x-ray
									0.3284
									0.4829
									0.5624
^{194}Ir		193.965075	19.3 h	β^-/2.247	1.92/9	1–	+0.39	+0.34	0.2935
					2.25/86				0.3284
									0.6451
									(0.1–2.2)
^{195m}Ir			3.9 h	β^- /	0.41/	(11/2–)			Pt k x-ray
					0.97/				0.3199/9.6
									0.3649/9.5
									0.4329/9.6
									0.6849/9.6
^{195}Ir		194.965976	2.8 h	β^- /1.120	1.0/80	(3/2+)			Pt k x-ray
					1.11/13				0.0989/9.7
^{196m}Ir			1.40 h	β^-/	1.16/				Pt k x-ray
									0.3557
									0.3935
									0.4471
									0.5214
									0.6473
^{196}Ir		195.96838	52. s	β^- /3.21	2.1/15	0–			0.3329
					3.2/80				0.3557
									0.7796
^{197m}Ir			8.9 m	β^- /		(11/2–)			0.3465
				I.T./					See Ir[197]
^{197}Ir		196.96964	5.8 m	β^- /2.16	1.5/	(3/2+)			0.0531
					2.0/				0.1351
									0.4306
									0.4697
^{198}Ir		197.9723	8. s	β^- /4.1					0.4074
									0.5070
^{199}Ir		198.97378							
$_{78}$Pt		**195.078(2)**							
^{166}Pt			0.3 ms	α/	7.11/				
^{167}Pt			0.7 ms	α/	6.99/				
^{168}Pt		167.9880	2.0 ms	α	6.83				0.582/69
									0.594/69
									0.725/62
^{169}Pt		168.9864	3. ms	α					
^{170}Pt		169.9816	14 ms	α	6.55				0.509/100
									0.662/86
									0.214–0.726
^{171}Pt		170.9811	0.05 s	α	6.45				
^{172}Pt		171.97730	0.10 s	α/	6.31/94	0+			
^{173}Pt		172.9765	0.36 s	β^+, EC/8.2	6.23				
				α/	6.20/				
^{174}Pt		173.97281	0.89 s	β^+, EC/17 /5.6		0+			
				α/83 /	6.040/				
^{175}Pt		174.9723	2.5 s	β^+, EC/65 /7.6					0.0774
				α/35 /	5.831/5				0.1354
					5.96/54				0.2128
					6.038/				
^{176}Pt		175.9690	6.3 s	β^+, EC/60 /5.1		0+			ann.rad./
				α/40 /	5.528/0.6				0.2277
					5.750/41				
^{177}Pt		176.9685	11. s	EC/91 /6.8	5.53/				0.0908
				α/9 /	5.485/3				
					5.525/6				
^{178}Pt		177.9649	21. s	EC/93 /4.5		0+			
				α/7 /	5.286/0.2				
					5.442/7				
^{179}Pt		178.9653	33. s	β^+, EC/5.7			+0.43		

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				α/	5.16/				
^{180}Pt		179.9632	52. s	β^+, EC/99.7 /3.7	0+				
				α/0.3 /	5.140/				
^{181}Pt		180.9632	51. s	β^+, EC/5.2			+0.48		
^{182}Pt		181.9613	2.7 m	β^+, EC/2.9		0+			ann.rad./
									0.1360
									0.1460
									0.2100
^{183m}Pt			43. s	β^+, EC/		(7/2–)	+0.78	+3.4	ann.rad./
				I.T./					0.3132/26
									0.3164/59
									0.6296/100
									0.058–1.75
^{183}Pt		182.9617	7. m	β^+, EC/4.6			+0.50		ann.rad./
									0.119/100
									0.307/93
									0.260/90
									0.058–1.377
^{184}Pt		183.9599	17.3 m	β^+, EC/2.3					ann.rad./
									0.1549
									0.1919
									0.5484
^{185m}Pt			33. m	β^+, EC/		1/2–	+0.5		
^{185}Pt		184.9607	1.18 h	β^+, EC/3.8		(9/2+)	–0.75	+3.7	ann.rad./
									0.1353
									0.1974
									0.2296
									0.2551
^{186}Pt		185.95943	2.0 h	β^+, EC/1.38		0+			ann.rad./
									0.6115
									0.6892
^{187}Pt		186.9607	2.35 h	β^+, EC/3.1		3/2	–0.41	–1.1	ann.rad./
									Ir k x-ray
									0.1064
									0.1100
									0.2015
									0.2849
									0.7092
^{188}Pt		187.95940	10.2 d	EC/0.51		0+			Ir k x-ray
									0.1876
									0.1951
^{189}Pt		188.96083	10.9 h	β^+, EC/1.97		3/2–	–0.43	–1.2	Ir k x-ray
									0.0943
									0.6076
									0.7214
									(0.09–1.47)
^{190}Pt	0.014(1)	189.95993	4.5×10^{11} y			0+			
^{191}Pt		190.961684	2.86 d	EC/1.02		(3/2–)	–0.50	–0.9	Ir k x-ray
									0.3599
									0.4094
									0.5389
^{192}Pt	0.782(7)	191.961035				0+			
^{193m}Pt			4.33 d	I.T./0.1498		13/2+	–0.75		Pt k x-ray
									0.1355
^{193}Pt		192.962984	60. y	EC/0.0566		(1/2–)	+0.60		Ir k x-rays
^{194}Pt	32.967(99)	193.962663				0+			
^{195m}Pt			4.01 d	I.T./0.2952		13/2+	–0.61	+1.4	Pt k x-ray
									0.0989
^{195}Pt	33.832(10)	194.964774				1/2–	+0.6095		
^{196}Pt	25.242(41)	195.964934				0+			
^{197m}Pt			1.590 h	I.T./97 /		13/2+			Pt k x-ray
				β^- /3 /					0.0530
									0.3465
^{197}Pt		196.967323	19.9 h	β^- /0.719		1/2–	0.51		Au k x-ray
									0.1914
									0.2688
^{198}Pt	7.163(55)	197.967875				0+			

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{199m}Pt			13.6 s	I.T./0.424		13/2+			Pt k x-ray
									0.3919
^{199}Pt		198.970576	30.8 m	β^- /1.70	0.90/18	(5/2–)			0.3170/4.9
					1.14/14				0.49375/5.7
									0.5430/14.8
									(0.055–1.293)
^{200}Pt		199.97142	12.5 h	β^- /≈0.66		0+			Au k x-ray
									0.13590
									0.22747
									0.24371
^{201}Pt		200.9745	2.5 m	β^- /2.66		(5/2–)			0.070
									0.152
									0.222
									1.760
^{202}Pt		201.9757	1.8 d						0.440
$_{79}$Au		**196.96655(2)**							
^{170m}Au			0.62 ms	p/58	1.74/				
				α/42	7.11/				
^{170}Au			0.30 ms	p/85	1.47/				
				α/15	7.01/				
^{171}Au		170.9918	1.0 ms	p/46	1.44/100				
				α/54	7.00				
^{172}Au		171.9901	4 ms	α/7.02	6.86				
^{173m}Au			15 ms	α/92	6.732				
^{173}Au		172.9864	0.02 s	α/94	6.672				
^{174}Au		173.9842	0.14 s	α	6.54				
^{175}Au		174.9817	0.15 s	α					
^{176}Au		175.9803	0.9 s	β^+, EC/10.5					
				α/	6.260/80				
					6.290/20				
^{177}Au		176.9772	1.2 s	α/	6.115/				
					6.150/				
^{178}Au		177.9760	2.6 s	α/	5.920/				
^{179}Au		178.9732	7.5 s	α/	5.85/				
^{180}Au		179.9724	8.1 s	EC/8.6	5.65				0.1522
				α/	5.61				0.2564
					5.50				0.5242
									0.6765
									0.8084
									0.8597
^{181}Au		180.9700	11.4 s	EC/97.5/6.3	5.482/				
				α/2.7/					
^{182}Au		181.9686	21. s	β^+, EC/6.9					ann.rad./
				α/0.13/					0.1549
									0.2649
									(0.13–1.4)
^{183}Au		182.9676	42. s	EC/5.5			+1.97		0.1630
				α/0.8/					0.2730
									0.3625
^{184m}Au			48 s			(2+)	+1.44	+1.9	0.069(IT)
^{184}Au		183.9675	21. s	EC, β^+/7.1		(5+)	+2.07	+4.7	
				α/0.013/					
^{185m}Au			6.8 m	β^+, EC/					
				I.T./0.145					
^{185}Au		184.9657	4.3 m	β^+, EC/4.71		(5/2–)	+2.17	–1.1	ann.rad./
				α/0.26/					
^{186m}Au			< 2. m	β^+, EC/					0.1915
^{186}Au		185.9659	10.7 m	β^+, EC/6.0		3–	–1.26	+3.1	ann.rad./
				α/8(10)$^{-4}$/					0.1915
									0.2988
^{187m}Au			2.3 s	IT		9/2–			
^{187}Au		186.9646	8.3 m	β^+, EC/3.60		1/2+	+0.54		ann.rad./
									0.9152
									1.2668
									1.3321

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									1.4081
^{188}Au		187.9651	8.8 m	β^+, EC/5.3		(1–)	–0.07		ann.rad./
									0.2660
									0.3404
									0.6061
^{189m}Au			4.6 m	β^+, EC/		11/2–	+6.19		0.1667
^{189}Au		188.9642	28.7 m	EC/96 /3.2		1/2+	+0.49		ann.rad./
				β^+ /4 /					Pt k x-ray
									0.4478
									0.7133
									0.8128
^{190}Au		189.96470	43. m	β^+ /2 /4.44		1–	–0.07		ann.rad./
				EC/98 /					Pt k x-ray
									0.2958
									0.3018
									0.5977
^{191m}Au			0.9 s	I.T./0.2663		(11/2–)	6.6		Au k x-ray
									0.2414
									0.2526
^{191}Au		190.96365	3.2 h	EC/1.83		3/2+	+0.137	+0.72	Pt k x-ray
									0.5864/16
									(0.088–1.30)
^{192}Au		191.96481	4.9 h	β^+ /5 /3.52	2.19/	1–	–0.011	–0.23	ann.rad./
				EC/95 /	2.49/				Pt k x-ray
									0.2959
									0.3165
^{193m}Au			3.9 s	I.T./0.2901		11/2–	6.2	+1.98	Au k x-ray
									0.2580
^{193}Au		192.96413	17.6 h	EC/1.07		3/2+	+0.140	+0.66	Pt k x-ray
									0.1862
									0.2556
^{194}Au		193.96534	1.64 d	β^+ /3 /2.49	1.49/	1–	+0.076	–0.24	ann.rad./
				EC/97 /					Pt k x-ray
									0.2935
									0.3284/61
^{195m}Au			30.5 s	I.T./0.3186		11/2–	6.2	+1.9	Au k x-ray
									0.2617
^{195}Au		194.965017	186.10 d	EC/0.227		3/2+	+0.149	+0.61	Pt k x-ray
^{196m2}Au			9.7 h	I.T./0.5954		12–	5.7		Au k x-ray
									0.1478
									0.1883
^{196m1}Au			8.1 s	I.T./0.0846		8+			0.0847
^{196}Au		195.966551	6.17 d	EC/92 /1.506		2–	+0.591	0.81	Pt k x-ray
^{197m}Au			7.8 s	I.T./0.4094		11/2–	+6.0	+1.7	Au k x-ray
				β^- /8 /0.686					0.1302
									0.2790
^{197}Au	100.	196.966551				3/2+	+0.14575	+0.55	
^{198m}Au			2.30 d	I.T./0.812		(12–)			Au k x-ray
									0.0972
									0.1803
									0.2419
^{198}Au		197.968225	2.695 d	β^- /1.372	0.290/1	2–	+0.5934	+0.64	Hg k x-ray
					0.961/99				0.411794
^{199}Au		198.968748	3.14 d	β^- /0.453	0.25/22	3/2+	+0.2715	+0.51	Hg k x-ray
					0.292/72				0.15837
					0.462/6				0.20820
^{200m}Au			18.7 h	β^- /84 /1.0	0.56/	12–	5.9		Au k x-ray
				I.T./16 /					0.2559/71
									0.3680/77
									0.4978/73
									0.5793/72
									0.084–0.904)
^{200}Au		199.97072	48.4 m	β^- /2.24	0.7/15	1–			0.3679/19
					2.2/77				1.2254/10.6
									(0.077–1.570)
^{201}Au		200.97165	26. m	β^- /1.28	1.27/82	3/2+			(0.027–0.732)
^{202}Au		201.9738	29. s	β^- /3.0		(1–)			0.4396

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{203}Au		202.97515	1.0 m	β^- /2.14	≈ 1.9/	3/2+			(0.04–0.37)
^{204}Au		203.9783	40. s	β^- /4.5		(2–)			0.4366
									1.5113
^{205}Au		204.9796	31. s	β^- /					(0.38–1.33)
$_{80}$Hg		**200.59(2)**							
^{172}Hg			≈0.25 ms	α	7.35				
^{173}Hg			0.9 ms	α	7.21				
^{174}Hg			1.9 ms	α	7.07				
^{175}Hg		174.9912	0.02 s	α					
^{176}Hg		175.98733	21 ms	α	6.74/94				
^{177}Hg		176.9863	0.13 s	α	6.58				
^{178}Hg		177.98248	0.26 s	EC/50 /6.1		0+			
				α/50 /	6.43/				
^{179}Hg		178.9818	1.05 s	EC/8.0					
				α/	6.29/				
^{180}Hg		179.9783	2.6 s	EC/5.5		0+			0.1250
				α/	6.12/33				0.3005
					5.69/.03				0.3812
^{181}Hg		180.9778	3.6 s	β^+ EC/74 /≈7.3		(1/2–)	+0.507		0.0663
				α/26 /					0.0811
									0.0924
									0.1474
									0.1587
									0.2142
									0.2398
^{182}Hg		181.9739	10.8 s	β^+, EC/85/5.0		0+			0.129/122
				α/15/	5.87/8.6				0.2176/66
					5.45/0.03				0.0256–0.543
^{183}Hg		182.9744	9. S	β^+, EC/77/6.3		1/2–	+0.524		0.0714
				α/	5.83/				0.0874
					5.91/				0.1538
^{184}Hg		183.9719	30.9 s	β^+, EC/99/4.1		0+			0.0915
				α/1/	5.54/1.3				0.1265
					5.07/0.002				0.1560
									0.2362
^{185m}Hg			21.s	β^+, EC, IT, α/	5.37/	13/2+	–1.02	+0.2	0.211
									0.292
^{185}Hg		184.9720	51. S	β^+, EC/95/5.8		1/2–	+0.509		0.02–0.55
^{186}Hg		185.9695	1.4 m	β^+, EC/3.3		0+			0.1119
				α	5.09/0.02				0.2518
^{187m}Hg			1.7 m	β^+, EC/		13/2+	–1.04	+0.5	see Hg187
^{187}Hg		186.9698	2.4 m	β^+, EC/4.9		3/2–	–0.594	–0.8	0.1034/32
									0.2334/100
									0.2403/33
									0.27151/31
									0.3763/38
									0.5254/30
									0.10–2.18
^{188}Hg		187.9676	3.2 m	β^+, EC/2.3		0+			0.0988
				α	4.61				0.1148
									0.1424
									0.1900
^{189m}Hg			8.6 m	EC/		13/2+	–1.06	+0.7	0.0780
									0.3210
									0.4345
									0.5655
									(0.08–2.170)
^{189}Hg		188.9687	7.6 m	EC/4.2		3/2–	–0.6086	–0.8	0.2005
									0.2038
									0.2386
									0.2485
^{190}Hg		189.9663	20.0 m	EC/1.5		0+			0.1296
									0.1426
^{191m}Hg			51. m	β^+ /6 /		13/2+	–1.07	+0.6	ann.rad./
				EC/94 /					Au k x-ray

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.2741
									0.4203
									0.5787
									(0.07–1.9)
^{191}Hg		190.9671	50. m	β^+, EC/3.2		(3/2–)	–0.62	–0.8	0.1963
									0.2247
									0.2524
^{192}Hg		191.9653	5.0 h	EC/≈0.5		0+			Au k x-ray
									0.1572
									0.2748
									0.3065
^{193m}Hg			11.8 h	β^+, EC/91 /		13/2+	–1.05843	+0.92	Hg k x-ray
				I.T./9 /0.2901					0.1866
									0.2580
									0.4076
									0.5733
									0.9324
									(0.1–1.96)
^{193}Hg		192.96664	3.8 h	EC, B^+/2.34		3/2–	–0.6276	–0.7	0.1866
									0.2580
									0.8611
^{194}Hg		193.96538	520. y	EC/0.04		0+			Au L x-rays
^{195m}Hg			1.67 d	I.T./(54)/0.3186		13/2+	–1.04465	+1.1	Hg k x-ray
				EC/(46)/					Au k x-ray
									0.2617
									0.5603
									0.7798
^{195}Hg		194.96664	10.5 h	EC/1.51		1/2–	+0.541475		Au k x-ray
									0.0614
									0.7798
^{196}Hg	0.15(1)	195.965814	$>2.5 \times 10^{18}$ y			0+			
^{197m}Hg			23.8 h	I.T./(93)/0.2989		13/2+	–1.02768	+1.2	Hg k x-ray
									Au k x-ray
									0.13398
^{197}Hg		196.967195	2.69 d	EC/0.600		1/2–	+0.527374		Au k x-ray
									0.07735
^{198}Hg	9.97(20)	197.966752				0+			
^{199m}Hg			42.7 m	I.T./0.532		13/2+	–1.014703	+1.2	Hg k x-ray
									0.15841
^{199}Hg	16.87(22)	198.968262				1/2–	+0.505885		
^{200}Hg	23.10(19)	199.968309				0+			
^{201}Hg	13.18(9)	200.970285				3/2–	–0.560226	+0.39	
^{202}Hg	29.86(26)	201.970625				0+			
^{203}Hg		202.972857	46.61 d	β^- /0.492	0.213/100	5/2–	+0.8489	+0.34	Tl k x-ray
									0.279188
^{204}Hg	6.87(15)	203.973475				0+			
^{205}Hg		204.976056	5.2 m	β^- /1.531	1.33/4	1/2–	+0.6010		0.20378
									(0.2–1.4)
^{206}Hg		205.97750	8.2 m	β^- /1.31	0.935/34	0+			Tl k x-ray
					1.3/63				0.3052
									0.6502
^{207}Hg		206.9825	2.9 m	β^- /4.8		(9/2+)			
^{208}Hg		207.9859	0.7 h	β^-					0.474
$_{81}$Tl		**204.3833(2)**							
^{177m}Tl			0.23 ms	p/51					
				α/49					
^{177}Tl		176.9969	0.017 s	α/73					
				p/27					
^{178}Tl		177.9952	0.25 s	α/	6.704				
					6.785				
					6.62				
					6.859				
^{179m}Tl			1.7 ms	α	/7.21/80				
				α	/7.10/20				
^{179}Tl		178.9917	0.3 s	α	6.57/				

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{180}Tl		179.9912	1.5 s	α	6.28/30				
					6.36/30				
					6.21/18				
					6.56/15				
					6.47/7				
^{181m}Tl			1.4 ms	α	6.58/100				
^{181}Tl		180.9869	3.2 ms	α	6.19/100				
^{182}Tl		181.9856	3. s	β^+, EC/10.9					0.351
									(0.26–0.41)
^{183m}Tl			0.06 s	α		9/2–			
^{183}Tl		182.9826	5. s	β^+, EC/7.7		1/2+			0.208
^{184}Tl		183.9818	11. s	β^+, EC/(98)/9.2					0.2868
				α/(2)/	6.16/				0.3399
									0.3667
^{185m}Tl			1.8 s	I.T./0.453		(9/2–)			0.1688
				α/5.97	6.01				0.2840
^{185}Tl		184.9791	20. s	EC/β^+/6.6					
^{186m}Tl			4. s	I.T./0.374					0.3738
^{186}Tl		185.9776	28. s	β^+, EC/7.5					0.3567
									0.4026
									0.4053
^{187m}Tl			15.6 s	I.T./≈0.33		(9/2+)	+3.8	–2.4	0.2995
^{187}Tl		186.9762	50. s	β^+, EC/6.0		1/2+	1.6		
^{188m}Tl			1.18 m	β^+, EC/		(7+)			Hg k x-ray
									0.4129
									0.5043
									0.5921
^{188}Tl		187.9759	1.2 m	β^+, EC/7.8		(2–)	+0.48	+0.13	See Tl[188m]
									0.4129
^{189m}Tl			1.4 m	β^+, EC/		(9/2–)	+3.878	–2.29	0.2156
									0.2284
									0.3175
									0.4452
^{189}Tl		188.9743	2.3 m	β^+, EC/5.2		(1/2+)			0.3337
									0.4510
									0.5223
									0.9422
^{190m}Tl			3.7 m	β^+, EC/	4.2/	(7+)	+0.495	+0.29	0.1968
									0.4164
									0.7311
^{190}Tl		189.9738	2.6 m	β^+, EC/7.0	5.7/	(2–)	+0.25	–0.33	0.4164
									0.6254
									0.6838
									1.0999
^{191m}Tl			5.2 m	β^+, EC/(98)/		(9/2+)	+3.903	–2.3	0.2157
									0.2647
									0.3256
									0.3359
^{191}Tl		190.9723				(1/2)	1.59		
^{192m}Tl			10.8 m	β^+, EC/		(7+)	+0.518	0.46	0.1740
									0.4228
									0.6348
									0.7863
									0.7455
^{192}Tl		191.972	9.6 m	β^+, EC/6.4		(2–)	+0.20	–0.33	0.3975
									0.4228
									0.6908
^{193m}Tl			2.1 m	I.T./(75)/		(9/2–)	+3.948	–2.2	0.3650
^{193}Tl		192.9706	22. m	β^+, EC/3.6		(1/2+)	+1.591		0.2077
									0.3244
									0.3440
									0.6761
									1.0447
									1.5793
^{194m}Tl			32.8 m	β^+ /(20)/≈0.30		(7+)	+0.540	+0.61	ann.rad./
				EC/(80)/					Hg k x-ray
									0.4282

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.6363
									0.7490
^{194}Tl		193.9711	34. m	β^+, EC/5.3		2–	0.140	–0.28	0.3955
									0.4282
									0.6363
^{195m}Tl			3.6 s	I.T./0.483		9/2–			Tl k x-ray
									0.0990
									0.3836
^{195}Tl		194.9697	1.16 h	EC/97/2.8		1/2+	+1.58		ann.rad./
				β^+ /(3)/					Hg k x-ray
									0.2422
									0.5635
									0.8845
									1.3639
									(0.13–2.5)
^{196m}Tl			1.41 h	β^+, EC/95/4.9		(7+)	0.55	+0.76	0.0840
									0.4261
									0.6353
									0.6954
									(0.08–1.0)
^{196}Tl		195.9705	1.84 h	β^+ /(15)/4.4		2–	+0.072	–0.18	ann.rad./
				EC/(85)/					Hg k x-ray
									0.4257
									0.6105
									(0.03–2.4)
^{197m}Tl			0.54 s	IT/53/0.608		9/2–			Tl k x-ray
				β^+, EC/47/					0.2262
									0.4118
									0.5872
									0.6367
^{197}Tl		196.96954	2.83 h	β^+ /(1)/2.18		1/2+	+1.58		Hg k x-ray
				EC/(99)/					0.1522/8.2
									0.4258
^{198m}Tl			1.87 h	β^+, EC/(53)/		7+	+0.64		Hg k x-ray
				IT/47/0.5347					Tl k x-ray
									0.4118
									0.5872
									0.6367
^{198}Tl		197.9405	5.3 h	EC, β^+ /(1)/3.5	1.4/	2–			Hg k x-ray
					2.1/				0.4118
					2.4/				0.6367
									0.6759
									(0.23–2.8)
^{199}Tl		198.9698	7.4 h	EC/1.4		1/2–	+1.60		Hg k x-ray
									0.2082
									0.2473
									0.4555
^{200}Tl		199.97095	1.087 d	EC/2.46	1.07/	2–	0.04		Hg k x-ray
					1.44/				0.36799
									1.2057
									(0.11–2.3)
^{201}Tl		200.97080	3.042 d	EC/0.48		1/2+	+1.605		Hg k x-ray
									0.13528
									0.16740/10.0
^{202}Tl		201.97209	12.47 d	EC/1.36		2–	0.06		Hg k x-ray
									0.43957
^{203}Tl	29.524(14)	202.972329				1/2+	+1.622258		
^{204}Tl		203.973848	3.78 y	β^- /97/0.7637	0.763/97	2–	0.09		Hg k x-ray
				EC/(3)/0.347					
^{205}Tl	70.476(14)	204.974412				1/2+	+1.638215		
^{206m}Tl			3.76 m	I.T./2.644		12–			Tl k x-ray
									0.2166
									0.2661
									0.4534
									0.6866
									1.0219
^{206}Tl		205.976095	4.20 m	β^- /1.533	1.53/99.9	0–			Pb k x-ray

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.80313
^{207m}Tl			1.3 s	I.T./1.350		11/2–			Tl k x-ray
									0.3501
									1.0000
^{207}Tl		206.97741	4.77 m	β^- /1.423	1.43/99.8	1/2+	+1.88		0.89723
^{208}Tl		207.982004	3.053 m	β^- /5.001	1.28/23	(5+)	+0.29		Pb k x-ray
					1.52/22				0.27728
					1.796/51				0.51061
									0.58302
									2.61448
^{209}Tl		208.98535	2.16 m	β^-/3.98	1.8 /100	(1/2+)			Pb k x-ray
									1.5670/100
									0.4651/95
									(0.12–1.33)
^{210}Tl		209.99006	1.30 m	β^- /5.48	1.3/25	(5+)			Pb k x-ray
					1.9/56				0.081
									0.2981
									0.79788
$_{82}$Pb		**207.2(1)**							
^{178}Pb			≈0.2 ms						
^{180}Pb			5 ms	α/	7.25				
^{181}Pb		180.9967	0.05 s	α/	7.07				
^{182}Pb		181.99268	55 ms	α	6.90				
^{183m}Pb			0.42 s	α	6.70/82.7	13/2+			
					6.86/1.9				
^{183}Pb		182.9919	0.54 s	α/	6.57/4.3	(3/2–)			
					6.78/11.0				
^{184}Pb		183.9882	0.48 s	α/94	6.63/	0+			
^{185m}Pb			4.3 s	α	6.41/	13/2+	–1.2		
^{185}Pb		184.9876	6.3 s	α/	6.29/56	3/2–	–1.1		0.205
					6.49/44				0.269
					6.48/				
^{186}Pb		185.9835	5. s	β^+, EC/95/5.5		0+			
				α/(5)/	6.32/				
					6.34/<100				
					6.01/<0.2				
^{187m}Pb			15.2 s	β^+, EC/	5.99/	(1/2–)			0.0674
				α/12	6.19/				0.2080
									0.2755
									0.2995
									0.4487
									0.7477
^{187}Pb		186.9839	18.3 s	EC/7.2		13/2+			0.1930
				α/7	6.08/				0.3314
									0.3435
									0.3934
^{188}Pb		187.9811	23. s	EC/(78)/4.8		0+			0.1850
				α/(22)/	5.98/<10				0.7582
					5.61/<0.1				
^{189}Pb		188.9809	51. s	EC/6.1					
				α/	5.58/				
^{190}Pb		189.9782	1.2 m	β^+ (13)/4.1		0+			ann.rad./
				EC/(86)/					Tl k x-ray
				α/(0.9)/	5.58/				0.1415
									0.1512
									0.9422
^{191m}Pb			2.2 m	β^+, EC/		13/2+	–1.17	+0.085	ann.rad./
									0.3871
									0.6135
									0.7122
^{191}Pb		190.9782	1.3 m	β^+, EC/5.5					ann.rad./
									0.9368
^{192}Pb		191.9758	3.5 m	β^+, EC/≈3.4		0+			ann.rad./
				α/.006/	5.11				0.1675
									0.6082

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									1.1954
^{193m}Pb			5.8 m	β^+, EC/		13/2+	–1.15	+0.19	ann.rad./
									0.3650
									0.3922
^{193}Pb		192.9761	≈ 2. m	EC/5.2		3/2			
^{194}Pb		193.9740	11. m	β^+, EC/2.7		0+			ann.rad./
				α	4.64				0.2036
^{195m}Pb			15. m	β^+ /(8)/		13/2+	–1.132	+0.30	ann.rad./
				EC/(92)/					Tl k x-ray
									0.3836
									0.3942
									0.8784
^{195}Pb		194.976	≈ 15. m	β^+, EC/5.8					ann.rad./
									0.3836
									0.3937
									0.7776
^{196}Pb		195.9727	37. m	β^+, EC/2.1		0+			Tl k x-ray
									0.2531
									0.5021
^{197m}Pb			43. m	EC/79/		13/2+	–1.104	+0.38	Tl k x-ray
				β^+ /2/					0.3079
				IT/19/0.3193					0.3877
									0.7743
									(0.2–2.2)
^{197}Pb		196.9734	≈8. m	EC/97/3.6		(3/2–)	–1.075	–0.08	Tl k x-ray
				β^+ /3/					0.3755
									0.3858
									0.7611
^{198}Pb		197.9720	2.4 h	EC/1.4		0+			Tl k x-ray
									0.1734
									0.2903
									0.3654
^{199m}Pb			12.2 m	IT/93/0.4248		13/2+			Pb k x-ray
				β^+, EC/(7)/					0.4255
^{199}Pb		198.9729	1.5 h	EC/(99)/2.9		5/2–	–1.074	+0.08	Tl k x-ray
				β^+ /(1)/					0.3534
									0.7202
									1.1350
									(0.22–2.4)
^{200}Pb		199.97182	21.5 h	EC/0.81		0+			Tl k x-ray
									0.14763
^{201m}Pb			1.02 m	I.T./0.6291		13/2+			Pb k x-ray
									0.6288
^{201}Pb		200.97285	9.33 h	EC/1.90		5/2–	+0.675	–0.009	Tl k x-ray
									0.33120
									0.36131
									(0.11–1.8)
^{202m}Pb			3.53 h	IT/90/2.170		9–	–0.228	+0.58	Pb k x-ray
				β^+ /10/					Tl k x-ray
									0.42219
									0.78700
									0.96271
^{202}Pb		201.97214	5.3×10^4 y	EC/0.05		0+			Tl L x-ray
^{203m}Pb			6.2 s	I.T./0.8252		13/2+			Pb k x-ray
									0.8203
									0.8252
^{203}Pb		202.97338	2.163 d	EC/0.98		5/2–	+0.686	+0.10	Tl k x-ray
									0.279188
^{204m}Pb			1.13 h	I.T./2.185		9–			Pb k x-ray
									0.37481
									0.89922
									0.91175
^{204}Pb	1.4(1)	203.973028				0+			
^{205}Pb		204.974467	1.51×10^7 y	EC/0.0512		5/2–	+0.712	+0.23	Tl L x-ray
^{206}Pb	24.1(1)	205.974449				0+			
^{207m}Pb			0.80 s	I.T./1.632		13/2+			Pb k x-ray
									0.56915

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									1.06310
^{207}Pb	22.1(1)	206.975880				1/2–	+0.59258		
^{208}Pb	52.4(1)	207.976636	$>2 \times 10^{19}$ y	SF		0+			
^{209}Pb		208.981075	3.25 h	β^- /0.644	0.645/100	9/2+	–1.474	–0.3	
^{210}Pb		209.984174	22.6 y	β^- /0.0635	0.017/81	0+			
					0.061/19				
				α	3.72				
^{211}Pb		210.988732	36.1 m	β^- /1.37	0.57/5	(9/2+)	–1.404	+0.09	0.40486
					1.36/92				0.42700
									0.83186
									(0.09–1.27)
^{212}Pb		211.991887	10.64 h	β^- /0.574	0.28/83	0+			Bi k x-ray
					0.57/12				0.23858
^{213}Pb		212.9966	10.2 m	β^- /2.1					
^{214}Pb		213.999797	26.9 m	β^- /1.0	0.67/48	0+			Bi k x-ray
					0.73/42				0.24192
									0.29509
									0.35187
^{215}Pb			36 s						
$_{83}$Bi		**208.98038(2)**							
^{185}Bi		184.9977	0.04 ms	p/86	1.59				
				α/14					
^{186}Bi		185.9965	10 ms	α	7.16				
					7.26				
^{187m}Bi			≈ 8. ms	α/12					
^{187}Bi		186.9935	32. ms	α/7	7.00/88.3				
					7.61/8.0				
					7.37/3.7				
^{188}Bi		187.9922		α					
^{189m}Bi			7.0 ms	α	7.30				
^{189}Bi		188.9895	0.68 s	α					
^{190}Bi		189.9875	5. s	β^+, EC/(10)/8.7					
				α/(90)/	6.45/				
^{191m}Bi			0.12 ms	α	6.87				
^{191}Bi		190.9861	12. s	β^+, EC/(60)/7.3					
				α/(40)/	6.32/				
^{192}Bi		191.9854	40. s	β^+, EC/(80)/9.0					
				α/(20)/	6.06/				
^{193m}Bi			3.2 s	β^+, EC/		1/2+			
				α/	6.48/				
^{193}Bi		192.9837	1.11 m	β^+, EC/40/7.1		9/2+			
				α/(60)/	5.91/				
^{194}Bi		193.9828	1.8 m	β^+, EC/99.9/8.2		(10–)			0.1661
				α/0.1/					0.1740
									0.2802
									0.421
									0.5754
									0.9650
^{195m}Bi			1.45 m	β^+, EC/(94)/					
				α/(6)/	6.11/				
^{195}Bi		194.9811	2.9 m	β^+, EC/99.8/5.8		3/2–			
				α/(0.2)	5.45/				
^{196}Bi		195.9806	5. m	EC/≈7.4					0.1376
									0.3720
									0.6880
									1.0486
^{197}Bi		196.9789	5. m	β^+, EC/5.2		1/2+			
^{198m}Bi			7.7 s	I.T./0.2485		(10–)			0.2485
^{198}Bi		197.9790	11.8 m	β^+, EC/6.6		(7+)			0.0900
									0.1976
									0.5624
									1.0635
^{199m}Bi			24.7 m	β^+, EC/					ann.rad./
^{199}Bi		198.9776	27. m	β^+, EC/4.3		9/2–	4.6		0.7203
									0.8374

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.8417
									0.9460
									1.0528
									1.3056
									(0.12–3.2)
^{200m}Bi			31. m	β^+, EC/		(2+)			0.2453
									0.4198
									0.4624
									1.0265
^{200}Bi		199.9781	36. m	EC/(90)/5.9		7+			ann.rad./
				β^+ /(10)/					Pb k x-ray
									0.4198
									0.4623
									1.0265
^{201m}Bi			59.1 m	I.T./0.846		(1/2+)			Bi k x-ray
				β^+, EC/					0.8464
^{201}Bi		200.97697	1.8 h	EC/3.84		9/2–	4.8		Pb k x-ray
									0.6288
									0.9357
									1.0138
									(0.13–2.4)
^{202}Bi		201.97768	1.72 h	β^+ /(3)/5.16		5+	+4.26	–0.72	ann.rad./
				EC/(97)/					Pb k x-ray
									0.57860
									0.92734
									(0.08–3.5)
^{203}Bi		202.97687	11.8 h	EC/99.8/3.25		9/2–	+4.02	–0.69	Pb k x-ray
				β^+ /(0.2)/	1.35/				0.1865
									0.8203
									0.8969
									1.8475
									(0.1–2.9)
^{204}Bi		203.97779	11.2 h	EC/4.44		6+	+4.32	–0.43	Pb k x-ray
									0.37481
									0.89922
									0.98409
^{205}Bi		204.97737	15.31 d	EC/2.71		9/2–	+4.07	–0.59	Pb k x-ray
									0.70347
									1.76435
^{206}Bi		205.97848	6.243 d	EC/3.76		6+	+4.36	–0.39	Pb k x-ray
									0.51619
									0.80313
									0.88100
^{207}Bi		206.978456	31.55 y	EC/2.399		9/2–	4.08	–0.6	Pb k x-ray
									0.56915
									1.06310
^{208}Bi		207.979727	3.68×10^5 y	EC/2.880		5+	4.63	–0.64	Pb k x-ray
									2.61435
^{209}Bi	100.	208.980384				9/2–	+4.111	–0.37	
^{210m}Bi			3.0×10^6 y	α/	4.420(3)/0.29	9–	+2.73	–0.47	Tl k x-ray
					4.569(3)/3.9				0.2661
					4.584(3)/1.4				0.3052
					4.908(4)/39				0.6502
					4.946(3)/55				
^{210}Bi		209.984105	5.01 d	β^- /1.163	1.16/99	1–	–0.0445	+0.136	0.2661
									0.3.52
^{211}Bi		210.98726	2.14 m	α/(99.7)/	6.279/16	9/2–			Tl k x-ray
				β^- /(0.3)/0.58	6.623/84				0.3501
^{212m2}Bi			7. m	β^- /		(15–)			
^{212m1}Bi			25.0 m	α/(93)/	6.300/40	(9–)			0.120
				β^- /(7)/	6.340/53				0.233
									0.275
									0.404
									0.727
^{212}Bi		211.991271	1.009 h	β^- /(64)/2.254		(1–)	+0.32	+0.1	Tl k x-ray
				α/(36)/	6.051/25				Po k x-ray
					6.090/9.6				0.2881

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.72725
									0.78551
									1.62066
^{213}Bi		212.99437	45.6 m	β^- /(98)/1.43	1.02/31	9/2–	+3.72	–0.60	Po k x-ray
				α/(2)/	1.42/66				0.4404
					5.549/0.16				(0.15–1.328)
					5.869/2.0				
									1.10006
^{214}Bi		213.99870	19.7 m	β^- /3.27					0.60931
									1.12027
									1.76449
									(0.19–3.2)
^{215}Bi		215.0018	7.7 m	β^- /2.3					0.2937
									(0.27–0.835)
^{216}Bi		216.0062	2.3 m	β^-/4.0					0.5498
									0.4192
^{217}Bi			97 s	β/					
$_{84}$Po									
^{188}Po			0.30 ms	α	7.91				
					7.35				
^{189}Po			5 ms	α	7.54				
					7.25				
					7.32				
^{190}Po		189.9951	2.4 ms	α/	7.53				
^{191m}Po			93. ms	α	7.376/50				
					6.888/46				
^{191}Po		190.9947	22 ms	α/	7.334/77				
					6.97/8				
^{192}Po		191.9915	34. ms	α/8.5	7.17				
^{193m}Po			0.24 s	α/	7.00				
^{193}Po		192.9911	0.45 s	α/	6.95				
^{194}Po		193.9883	0.39 s	α/	6.84/93	0+			
					6.19/0.22				
^{195m}Po			1.9 s	α/	6.70/				
^{195}Po		194.9881	4.6 s	α/	6.61/				
^{196}Po		195.9855	5.8 s	α/(95)/	6.52/94	0+			
				β^+, EC/(5)/≈4.6	5.77/0.02				
^{197m}Po			25.8 s	α/(84)/	6.385(3)/55	13/2+			
				β^+, EC/(16)/					
^{197}Po		196.9856	53. s	α/(44)/	6.282(4)/76	(3/2–)			
				β^+, EC/(56)/6.2					
^{198}Po		197.9834	1.76 m	α/(70)/	6.18/57	0+			
				β^+, EC/(30)/4.0	$5.27/7.6 \times 10^{-4}$				
^{199m}Po			4.2 m	β^+, EC/(51)/		13/2+	0.99		ann.rad./
				α/(39)/	6.059/24				0.2745
									0.4998
									1.0020
^{199}Po		198.985	5.2 m	β^+, EC/(88)/7.		(3/2–)			Bi k x-ray
				α/(12)/	5.952/7.5				0.1877
									0.3616
									1.0214
									1.0344
^{200}Po		199.9817	11.5 m	β^+, EC/85/3.4		0+			0.14748
				α/(15)/	5.863/11.1				0.32792
									0.6176
									0.6709
^{201m}Po			8.9 m	β^+, EC/(57)/		13/2+	1.00		Bi k x-ray
				IT/40/0.418					Po k x-ray
				α/(3)/	5.786/≈3.				0.2726
									0.4123
									0.4179
									0.9670
^{201}Po		200.9822	15.3 m	β^+, EC/98/4.9		3/2–	0.94		Bi k x-ray
				α/(2)/	5.683(3)/1.1				0.2056
									0.2250

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.8483
									0.9048
^{202}Po		201.9807	45. m	β^+, EC/98/2.8		0+			0.0410
				α/(2)/	5.588/1.9				0.1656
									0.3158
									0.6884
^{203m}Po			1.2 m	IT/96/0.6414		13/2+			Bi k x-ray
				β^-EC/(4)/					Po k x-ray
									0.6414
^{203}Po		202.9814	35. m	β^+, EC/4.2		5/2–	+0.74		0.17516
									0.21477
									0.89350
									0.90863
									1.09095
^{204}Po		203.98031	3.53 h	EC/2.34		0+			Bi k x-ray
				α	5.377/0.66				0.2702
									0.8844
									1.0162
									(0.11–1.9)
^{205}Po		204.98117	1.7 h	β^+, EC/3.53		5/2–	+0.76	+0.17	Bi k x-ray
									0.83681
									0.84983
									0.87241
									1.00124
									(0.12–2.7)
^{206}Po		205.98047	8.8 d	EC/(95)/1.85		0+			Bi k x-ray
				α/(5)/	5.223/5.5				0.28644
									0.31156
									0.51134
									0.80737
									1.03228
									(0.11–1.5)
^{207m}Po			2.8 s	I.T./1.383		19/2–			Po k x-ray
									0.2682
									0.30074
									0.81448
^{207}Po		206.98158	5.80 h	EC, β^+/2.91		5/2–	+0.79	+0.28	Bi k x-ray
									0.74263
									0.91176
									0.99225
^{208}Po		207.981231	2.898 y	α/5.213	4.233/0.0002	0+			
					5.1158/100				
^{209}Po		208.982415	102. y	α/4.976	4.624/0.56	1/2–	≈+0.77		0.26049
					4.879/99.2				0.8964
^{210}Po		209.982857	138.4 d	α/5.407	4.516/0.001	0+			0.80313
					5.304/100				
^{211m}Po			25.2 s	α/	7.273/91	25/2+			Pb k x-ray
					7.994/1.7				0.32808
					8.316/0.25				0.56915
					8.875/7.0				0.89723
									1.06310
^{211}Po		210.986637	0.516 s	α/7.594	6.570/0.54	9/2+			0.56915
					6.892/0.55				0.89723
					7.450/98.9				
^{212m}Po			45. s	α/	8.514/2.0	16+			
					9.086/1.0				
					11.650/97				
^{212}Po		211.988852	0.298 μs	α/8.953	8.784/100	0+			
^{213}Po		212.992843	3.7 μs	α/8.537	7.614/0.003	9/2+			
					8.375/100				
^{214}Po		213.995186	163.7 μs	α/7.833	6.904/0.01	0+			0.7995
					7.686/99.99				0.298
^{215}Po		214.999415	1.780 ms	α/7.526	6.950/0.02	(9/2+)			
					6.957/0.03				
					7.386/100				
^{216}Po		216.001905	0.145 s	α/6.906	5.895/0.002	0+			
					6.778/99.99				

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{217}Po		217.0064	< 10. s	α/6.662	6.539/				
^{218}Po		218.008965	3.04 m	α/6.114	5.181/1.00	0+			
$_{85}$At									
^{193}At		192.9998	40 ms	α/					
^{194}At		193.9990	40 ms	α/					
^{195m}At			0.39 s	α	6.96				
^{195}At		194.9965	140 ms	α/	7.11				
^{196m}At			8 μs						0.158
^{196}At		195.9957	0.39 s	α/	7.05/				
^{197m}At			4. s	α		(1/2+)			
^{197}At		196.9939	0.35 s	β^+, EC/7.8		(9/2–)			
				α/	6.96/				
^{198m}At			1.5 s	β^+, EC/(75)/					
				α/(25)/	6.85/86				
^{198}At		197.9928	5. s	α/	6.75/94				
^{199}At		198.9910	7.1 s	β^+, EC/8/5.6		9/2–			
				α/(92)/	6.64/				
^{200m}At			4.3 s	β^+, EC/(80)		10–			
				α/(20)/	6.536/12				
^{200}At		199.990	43. s	β^+, EC/65/≈8.0		5+			
				α/(35)/	6.412/44				
					6.465/57				
^{201}At		200.9885	1.48 s	β^+, EC/29/5.9		9/2–			
				α/(71)/6.474	6.344/				
^{202m}At			≤ 1.5 s	I.T./0.391					
^{202}At		201.9885	3.02 m	β^+, EC/88/7.2		5+			ann.rad./
				α/(12)/	6.135/7.7				0.4413
					6.225/4.3				0.5697
									0.6753
^{203}At		202.9868	7.4 m	β^+, EC/69/5.1		9/2–			0.1458
				α/(31)/6.210	6.088/				0.2459
									0.6414
									1.0020
									1.0340
^{204}At		203.9873	9.1 m	β^+, EC/95/6.5		(5+)			Po k x-ray
				α/(5)/	5.951/				0.3271
									0.4254
									0.5156
									0.6837
^{205}At		204.98604	26. m	β^+, EC/90/4.54		(9/2–)			Po k x-ray
				α/(10)/6.020	5.902/				0.1543
									0.6696
									0.7194
^{206}At		205.98660	29.4 m	β^+, EC/99/5.72		5+			Po k x-ray
				α/(1)/5.881	5.703/				0.20186
									0.39561
									0.47716
									0.70071
^{207}At		206.98578	1.81 h	β^+, EC/90/3.91		9/2–			Po k x-ray
				α/(10)/5.873	5.758/				0.16801
									0.58842
									0.81448
^{208}At		207.98657	1.63 h	β^+, EC/99/4.97		(6+)			Po k x-ray
				α/(1)/5.752	5.626/0.01				0.1770
					5.641/0.53				0.2060
									0.6601
									0.6852
									0.8450
									1.0281
^{209}At		208.98616	5.4 h	β^+, EC/96/3.49		(6+)			Po k x-ray
				α/(4)/5.757	5.647/4.1				0.10422
									0.54503
									0.78189
									0.79020
									(0.1–2.6)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{210}At		209.98713	8.1 h	EC/99.8/3.98		5+			Po k x-ray
				α/(0.2)/5.632	5.361/0.05				0.24535
					5.442/0.05				0.52758
									1.18143
									1.43678
									1.48335
									(0.04–2.4)
^{211}At		210.987481	7.21 h	EC/(58)/0.787		9/2–			Po k x-ray
				α/(42)/5.980	5.211/0.004				0.66956
					5.868/42				0.6870
									0.74263
^{212m}At			0.119 s	α/	7.837/65	(9–)			
					7.897/33				
^{212}At		211.990735	0.314 s	α/7.828	7.058/0.4	(1–)			
					7.088/0.6				
					7.618/15				
					7.681/84				
^{213}At		212.992922	0.11 μs	α/9.254	9.080/	9/2–			
^{214m}At			0.76 μs	α/8.762		(9–)			
^{214}At		213.996357	0.56 μs	α/8.987	8.819/100	(1–)			
^{215}At		214.99864	0.10 ms	α/8.178	7.626/0.045	(9/2–)			0.40486
					8.023/99.9				
^{216}At		216.002408	0.30 ms	α/7.947	7.595/0.2	(1–)			
					7.697/2.1				
					7.800/97				
^{217}At		217.00471	32. ms	α/7.202	6.812/0.06	(9/2–)			0.2595
					7.067/99.9				0.3345
									0.5940
^{218}At		218.00868	1.6 s	α/6.883	6.654/6				
					6.695/90				
					6.748/4				
^{219}At		219.0113	50. s	α/6.390	6.275/				
^{220}At		220.0153	3.71 m	β^- /3.7					(0.24–0.70)
^{221}At		221.0181	2.3 m	β					
^{222}At		222.0223	0.9 m	β					
^{223}At		223.0253	50. s	β					
$_{86}$Rn									
^{195m}Rn			5 ms	α	7.56				
^{195}Rn			6 ms	α	7.54				
^{196}Rn		195.9977	4. ms	α/	7.46				
^{197m}Rn			0.02 s	α	7.36				
^{197}Rn		196.9983	0.07 s	α/	7.26				
^{198}Rn		197.9988	0.05 s	α					
^{199m}Rn			0.3 s	α		(13/2+)			
^{199}Rn		198.9983	0.62 s	α/		3/2–			
^{200}Rn		199.9957	1.06 s	α/(98)/	6.901/	0+			0.4329
				EC/(2)/5.					0.5043
^{201m}Rn			3.8 s	EC/(10)/		13/2+			
				α/(90)/	6.773/				
^{201}Rn		200.9955	7.0 s	α/(80)/	6.725/	(3/2–)			
				EC/(20)/	α/6.778				
^{202}Rn		201.9932	9.9 s	α/(12)/	6.641/	0+			0.5695
				EC/(88)/					0.2876–0.6255
^{203m}Rn			28. s	α/	6.551	13/2+	–0.96	+1.3	
^{203}Rn		202.9948	45. s	α/(66)/6.629	6.499/	0			
				EC/(34)/≈7.4					
^{204}Rn		203.9914	1.24 m	α/(68)/	6.420/	0+			
				EC/(32)/3.8					
^{205}Rn		204.9917	2.8 m	α/(23)/6.390	6.123(3)/0.02	(5/2–)	+0.80	+0.06	0.2652
				EC/(77)/5.2	6.262(3)/23				0.3553
									0.4648
									0.6205
									0.6753
									0.7300

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin (h/2π)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{206}Rn		205.9902	5.7 m	α/(68)/6.384	6.258(3)/	0+			0.06170
				EC/(32)/3.3					0.0968
									0.3245
									0.3862
									0.4822
									0.4973
									0.7728
^{207}Rn		206.9907	9.3 m	β^+, EC/77/4.6		5/2–	+0.82	+0.22	At k x-ray
				α/(23)/6.252	5.995(4)/0.02				0.32947
					6.068(3)/0.15				0.34455
					6.126(3)/22.8				0.36767
									0.40267
									0.74723
									(0.18–1.4)
^{208}Rn		207.98963	24.3 m	α/(60)/6.260	5.469(2)/0.003	0+			
				EC/(40)/2.85	6.140(2)/60				
^{209}Rn		208.99038	29. m	β^+ /(83)/3.93	2.16/2.3	5/2–	+0.8388	+0.31	At k x-ray
				α/(17)/	5.887(3)/0.04				0.27933
					5.898(3)/0.02				0.33753
					6.039(2)/16.9				0.40841
									0.68942
									0.74594
									(0.18–3.2)
^{210}Rn		209.98968	2.4 h	α/(96)/6.157	5.351(2)/0.005	0+			At k x-ray
				EC/(4)/2.37	6.039(2)/96				0.19625
									0.45824
									0.57104
									0.64868
									(0.14–1.7)
^{211}Rn		210.99059	14.6 h	β^+, EC/74/2.89		1/2–	+0.60		At k x-ray
				α/(26)/5.964	5.619(1)/0.7				0.16877
					5.784(1)/16.4				0.25022
					5.851(1)/8.8				0.37049
									0.67412
									0.67839
									1.36298
									(0.11–2.7)
^{212}Rn		211.990689	24. m	α/6.385	5.587(4)/0.05	0+			
					6.260(4)/99.95				
^{213}Rn		212.99387	20 ms	α/8.243	7.552(8)/1.0	9/2+			0.540
					8.087(8)/98.2				
					7.254/0.8				
^{214}Rn		213.99535	0.27 μs	α/9.209	9.037(9)/	0+			
^{215}Rn		214.99873	2.3 μs	α/8.840	8.674(8)/	(9/2+)			
^{216}Rn		216.00026	45. μs	α					
^{217}Rn		217.003915	0.6 ms	α/7.885	7.500/0.1	9/2+			
					7.742(4)/100				
^{218}Rn		218.005586	35. ms	α/7.267	6.534(1)/0.16	0+			0.6093
					7.133(1)/99.8				0.6653
^{219}Rn		219.009475	3.96 s	α/6.946(1)	6.3130(5)/0.05	(5/2+)	–0.44	+0.93	Po k x-ray
					6.425(3)/7.5				0.13057
					6.5309(4)/0.12				0.27113
					6.5531(3)/12.2				0.40170
					6.8193(3)/81				(0.1–1.05)
^{220}Rn		220.011384	55.6 s	α/6.404	5.7486(5)/0.07	0+			
					6.2883(1)/99.9				
^{221}Rn		221.0156	25. m	α/(22)/6.148	5.778(3)/1.8	7/2+	–0.020	–0.38	Fr L x-ray
				β^- /(78)/1.2	5.788(3)/2.2				0.07384
					6.037(3)/18				0.08323
									0.0610
									0.18639
^{222}Rn		222.017570	3.823 d	α/5.590	4.987(1)/0.08	0+			0.510
					5.4897(3)/99.9				
^{223}Rn		223.0218	23. m	β^- /			–0.78	+0.80	
^{224}Rn		224.0241	1.8 h	β^- /		0+			0.1085
									0.2601
									0.2655

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{225}Rn		225.0284	4.5 m	β^- /		7/2	–0.70	+0.84	
^{226}Rn		226.0309	7.4 m	β^- /					
^{227}Rn		227.0354	2. s	β^- /					
^{228}Rn		228.0381	65. s	β^- /					
$_{87}$Fr									
^{199}Fr			12 s	α	7.66				
^{200}Fr		200.0065	≈ 20 ms	α	7.47				
^{201}Fr		201.0046	0.05 s	α/	7.36/	(9/2–)			
^{202}Fr		202.0033	0.34 s	α/7.590	7.237(8)/100				
^{203}Fr		203.0014	0.55 s	α/7.280	7.132(5)/	(9/2–)			
^{204}Fr		204.001	2.1 s	α/	7.03/96				
					6.97/90				
					7.01/74				
^{205}Fr		204.9987	3.9 s	α/7.050	6.914(5)/	(9/2–)			
^{206m}Fr			0.7 s	α/	6.93				0.531(IT)
^{206}Fr		205.9985	16.0 s	α/7.416	6.792(5)/84				
^{207}Fr		206.9969	14.8 s	α/6.900	6.766(5)/	9/2–	+3.9	–0.16	
^{208}Fr		207.99713	59.1 s	α/(77)/6.770	6.636(5)/	7+	–4.8	+0.004	
				EC/(23)/6.99					
^{209}Fr		208.99592	50.0 s	α/(89)/5.1	6.646(3)/	9/2–	+3.9	–0.24	0.7978
				EC/(11)/5.16					(0.1103–1.384)
^{210}Fr		209.99640	3.2 m	α/6.670	6.543(5)/	6+	+4.4	+0.19	0.2030
				EC/6.26					0.6438
									0.8175
									0.9008
^{211}Fr		210.99553	3.10 m	α/6.660	6.534(5)/	9/2–	+4.0	–0.19	0.220
				EC/4.61					0.2799
									0.5389
									0.9169
^{212}Fr		211.99618	20. m	EC/(57)/5.12	6.261(1)/16	(5+)	+4.6	–0.10	Rn x-ray
				α/(43)/6.529	6.335(1)/4				0.08107
					6.335(1)/4				0.08378
					6.343(1)/1.3				0.2277
					6.383(1)/10				1.1856
					6.406(1)/9.5				1.2748
					6.08–6.18				0.014–1.178
^{213}Fr		212.99617	34.6 s	α/6.905	8.476(4)/51	9/2–	+4.0	–0.14	
^{214m}Fr			3.4 ms	α/	8.547(4)/46	9–			
					6.775–8.046				
^{214}Fr		213.99895	5.1 ms	α/8.587	7.409(3)/0.3	(1–)			
					7.605(8)/1.0				
					7.940(3)/1.0				
					8.355(3)/4.7				
					8.427(3)/93				
^{215}Fr		215.00033	0.12 μs	α/9.537	9.360(8)/	(9/2–)			
^{216}Fr		216.00319	0.70 μs	α/9.175	9.005(10)/95				(0.045–0.160)
^{217}Fr		217.00462	0.016 ms	α/8.471	8.315(8)/	(9/2–)			
^{218m}Fr			22. ms	α					
^{218}Fr		218.00756	1. ms	α/8.014	7.384(10)/0.5	(1–)			
					7.542(15)/1.0				
					7.572(10)/5				
					7.732(10)/0.5				
					7.867(2)/93				
^{219}Fr		219.00924	21. ms	α/8.132	6.802(2)/0.25	(9/2–)			
					6.967(2)/0.6				
					7.146(2)/0.25				
					7.313(2)/99				
^{220}Fr		220.012313	27.4 s	α/6.800	6.582(1)/10	1+	–0.67	+0.47	0.0450
					6.630(2)/6				0.061
					6.641(1)/12				0.1060
					6.686(1)/61				0.1539
					6.39–6.58				0.1617
^{221}Fr		221.01425	4.8 m	α/6.457	5.9393(7)/0.17	(5/2–)	+1.58	–1.0	At k x-ray
					5.9797(7)/0.49				0.0995
					6.0751(7)/0.15				0.21798

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
					6.1270(7)/				0.4091
					6.2433(3)/1.3				
					6.3410(7)/83.4				
^{222}Fr		222.01754	14.3 m	β^- /2.03	1.78/	2–	+0.63	+0.51	
				α/5.850					
^{223}Fr		223.019731	22.0 m	β^- /1.149	α/5.291	(3/2+)	+1.17	+1.17	0.1509
				α//0.006	5.314				0.0589
					5.403				0.1453
^{224}Fr		224.02323	3.0 m	β^- /2.82		1–	+0.40	+0.517	0.13150
									0.21575
									0.8367
									(0.1–2.21)
^{225}Fr		225.02561	3.9 m	β^- /1.87		3/2	+1.07	+1.3	
^{226}Fr		226.0293	49. s	β^- /3.6		1	+0.071	–1.35	0.18606
									0.25373
^{227}Fr		227.0318	2.48 m	β^- /2.5		1/2	+1.50		
^{228}Fr		228.0357	39. s	β^- /≈3.5		2–	–0.76	+2.4	
^{229}Fr		229.0384	50. s	β^- /					
^{230}Fr		230.0425	19. s	β^- /		(3)			
^{231}Fr		231.0454	17. s	β^- /					
^{232}Fr		232.0500	5. s	β^- /					
$_{88}$Ra									
^{202}Ra			≈ 3 ms	α	7.86				
^{203m}Ra			0.03 s	α	7.62				
^{203}Ra		203.0092	≈ 4 ms	α	7.58				
^{204}Ra		204.0065	0.06 s	α	7.48				
^{205m}Ra			≈ 0.17 s						
^{205}Ra		205.0062	0.22 s	α	7.34				
^{206}Ra		206.0038	0.4 s	α/7.416	7.272(5)/	0+			
^{207}Ra		207.0037	1.3 s	α/7.270	7.133(5)/				
^{208}Ra		208.0018	1.4 s	α/7.273	7.133(5)/	0+			
^{209}Ra		209.0019	4.6 s	α/7.150	7.008(5)/	5/2	+0.87	+0.40	
^{210}Ra		210.0005	3.7 s	α/7.610	7.020(5)/	0+			
^{211}Ra		211.0009	13. s	α/7.046	6.912(5)/	(5/2–)	+0.878	+0.48	
				EC/5.0					
^{212}Ra		211.99978	13.0 s	α/7.033	6.901(2)/	0+			
^{213m}Ra			2.1 ms	IT					
^{213}Ra		213.00034	2.7 m	EC/(20)/3.88		(1/2–)	+0.613		0.1024
				α/(80)/6.860	6.521(3)/4.8				0.11010
					6.622(3)/39				0.2125
					6.730(3)/36				
^{214}Ra		214.00009	2.46 s	α/7.272	7.14/99.8/	0+			0.642
					6.51/0.2				
^{215}Ra		215.00270	1.7 ms	α/8.864	7.883(6)/2.8	(9/2+)			0.773/100
					8.171(3)/1.4				0.852/74
					8.700(3)/95.9				0.055–1.048
^{216}Ra		216.00352	0.18 μs	α/9.526	9.349(8)/	0+			
^{217}Ra		217.00631	1.6 μs	α/9.161	8.992(8)/	9/2–			
^{218}Ra		218.00712	26. μs	α/8.547	8.390(8)/	0+			
^{219}Ra		219.01006	0.010 s	α/8.132	7.680(10)/65				
					7.982(9)/35				
^{220}Ra		220.01101	18. ms	α/7.593	7.39/5	0+			0.465
					7.45/95				
^{221}Ra		221.01391	29. s	α/6.879	6.254(10)/0.7	5/2	–0.180	+1.9	
					6.578(5)/3				
					6.585(3)/8				
					6.608(3)/35				
					6.669(3)/21				
					6.758(3)/31				
^{222}Ra		222.015361	36.2 s	α/5.590	6.237(2)/3.0	0+			0.324
					6.556(2)/97				0.1448–0.8402
^{223}Ra		223.018497	11.43 d	α/5.979	5.287(1)/0.15	(3/2+)	+0.271	+1.25	Rn k x-ray
					5.338(1)/0.13				0.12231
					5.365(1)/0.13				0.14418
					5.433(5)/2.3				0.15418

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
					5.502(1)/1.0				0.15859
					5.540(1)/9.2				0.26939
					5.607(3)/24				0.32388
					5.716(3)/52				0.33328
					5.747(1)/9				0.44494
					5.857(1)/0.32				(0.10–0.7)
					5.872(1)/0.85				
^{224}Ra		224.020202	3.66 d	α/5.789	5.034(10)/0.003	0+			Rn k x-ray
					5.047(1)/0.007				0.2407
					5.164(5)/0.007				0.4093
					5.449(2)/4.9				0.6501
					5.685(2)/95				
^{225}Ra		225.023603	14.9 d	β^- /0.36	0.32/100	(3/2+)	–0.734		Ac k x-ray
				α	5.01/2×$^{-5}$				0.0434
					4.98×10^{-6}				
^{226}Ra		226.025402	1599. y	α/4.870	4.194(1)/0.001	0+			Rn k x-ray
			$>4 \times 10^{18}$ y	Sf/4×10^{-14}	4.343(1)/0.006				0.1861/3.64
					4.601(1)/6.16				0.2624
					4.784(1)/93.8				0.053–2.448
^{227}Ra		227.029170	42. m	β^- /1.325	1.03/	(3/2+)	–0.404	+1.5	Ac L x-ray
					1.30/				Ac k x-ray
									0.02739
^{228}Ra		228.031063	5.76 y	β^- /0.046	0.039/50	0+			0.0135
					0.014/30				(0.006–0.0306)
					0.026/20				
^{229}Ra		229.0348	4.0 m	β^- /1.76	1.76/	(3/2+)	+0.503	+3.1	0.0145–0.1715
^{230}Ra		230.03708	1.5 h	β^- /1.0	0.7/	0+			0.0631
									0.0720
									0.2028
									0.4698
									0.4787
^{231}Ra		231.0412	1.7 m	β^-					
^{232}Ra		232.0437	4. m	β^-					
^{233}Ra		233.0480	30. s	β^-					
^{234}Ra		234.051	≈ 30. s	β^-/					
$_{89}$Ac									
^{206m}Ac			0.04 s	α	7.79				
^{206}Ac			≈26 ms	α	7.75				
^{207}Ac		207.0121	27 ms	α/	7.69				
^{208m}Ac			≈25. ms	α/	7.72				
^{208}Ac		208.0115	≈0.1 s	α/	7.62				
^{209}Ac		209.0096	≈0.10 s	α/	7.58				
^{210}Ac		210.0093	0.34 s	α/7.610	7.462(8)/				
^{211}Ac		211.0076	0.20 s	α/7.620	7.480(8)/				
^{212}Ac		212.0078	0.9 s	α/7.520	7.379(8)/				
^{213}Ac		213.0066	0.73 s	α/7.500	7.364(8)/	(9/2–)			
^{214}Ac		214.0069	8.2 s	α/(86)/7.350	7.007(8)/3	(5+)			
				EC/(14)/6.34	7.082(5)/38				
					7.214(5)/45				
^{215}Ac		215.0065	0.17 s	α/7.750	7.60/99.2	(9/2–)			0.399
					7.21/0.46				0.582
					7.03/0.20				0.654
					6.96/0.14				
^{216m}Ac			0.44 ms	α/	8.198(8)/1.7	(9–)			
					8.283(8)/2.5				
					9.028(5)/49				
					9.106(5)/46				
^{216}Ac		216.00871	≈0.3 ms	α/9.241	8.990(2)/10	(1)			
					9.070(8)/90				
^{217m}Ac			0.7 μs	α/	10.540/100				
^{217}Ac		217.00933	0.07 μs	α/9.832	9.650(10)/100	9/2–			
^{218}Ac		218.01162	1.1 μs	α/9.380	9.205(15)/				
^{219}Ac		219.01241	0.012 ms	α/8.830	8.664(10)/	(9/2–)			
^{220}Ac		220.0148	26. ms	α/8.350	7.610(20)/23				
					4.680(20)/21				

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
					7.790(10)/13				
					7.850(10)/24				
					7.985(10)/4				
					8.005(10)/5				
					8.060(10)/6				
					8.195(10)/3				
^{221}Ac		221.01558	52. ms	α/7.790	7.170(10)/2				
					7.375(10)/10				
					7.440(15)/20				
					7.645(10)/70				
^{222m}Ac			63. s	α/(>89)/	6.710(20)/7				
				EC/(1)/	6.750(20)/13				
				I.T./(<10)/	6.810(20)/24				
					6.840(20)/9				
					6.890(20)/13				
					6.970(20)/7				
					7.000(20)/13				
^{222}Ac		222.01782	5. s	α/7.141	6.967(10)/6	1–			
					7.013(2)/94				
^{223}Ac		223.01913	2.1 m	α/(99)/6.783	6.131(2)/0.12	(5/2–)			0.0725
				EC/(1)/0.59	6.177(2)/0.94				0.0839
					6.293(1)/0.47				0.0927
					6.326(1)/0.3				0.0990
					6.332(2)/0.14				0.1917
					6.360(1)/0.22				0.2158
					6.397(1)/0.13				0.3588
					6.448(1)/0.2				0.4768
					6.473(1)/3.1				
					6.523(2)/0.6				
					6.528(1)/3.1				
					6.563(1)/13.6				
					6.582(3)/0.3				
					6.646(1)/44				
					6.661(1)/31				
^{224}Ac		224.021708	2.7 h	EC/(90)/1.403	5.841(1)/0.5	0–			Ra L kx-ray
				α/(10)/6.323	5.860(1)/0.75				Ra k x-ray
					5.875(1)/1.7				0.08426
					5.941(1)/4.4				0.13150
					6.000(1)/6.7				0.1571
					6.013(1)/1.4				0.21575
					6.056(1)/22				0.2619
					6.138(1)/26				(0.03–0.3)
					6.154(1)/1.0				
					6.204(1)/12				
					6.210(1)/20				
^{225}Ac		225.02322	10.0 d	α/5.935	5.286(1)/0.2	3/2			Fr k x-ray
					5.444(3)/0.1				0.06296/0.48
					5.554(1)/0.1				0.09982/1.36
					5.608(1)/1.1				0.1084
					5.636(1)/4.5				0.1116
					5.681(1)/1.4				0.1451
					5.722(1)/2.9				0.150.02/0.691
					5.731(1)/10				0.15724
					5.791(1)/9				0.18795/0.54
					5.793(1)/18				0.0075–0.8085
^{226}Ac		226.026089	1.224 d	EC/(17)/0.640		(1–)			Ra k x-ray
				β^- /(83)/1.116					Th k x-ray
				α/(0.006)/5.51	5.399(5)/0.006				0.07218
									0.15816
									0.23034
^{227}Ac		227.027747	21.77 y	β^- /98.6/0.045	0.045/54	(3/2–)	+1.1	+1.7	0.0838/23.
				α/(1.4)/5.043	4.869(1)/0.09				0.0811/14.
					4.938(1)/0.52				0.2696/13.
					4.951(1)/0.65				(0.044–1.27)
^{228}Ac		228.031014	6.15 h	β^- /2.127	1.11/32	(3+)			Th L x-ray
					1.85/12				Th k x-ray
					2.18/11				0.12903

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									0.33842
									0.91116
									0.96897
									(0.2–1.96)
^{229}Ac		229.03293	1.04 h	β^- /1.10	1.1/	(3/2+)			0.09335/2.43
									0.16451/2.61
									0.56916/2.24
									0.0111–0.898
^{230}Ac		230.0360	2.03 m	β^- /2.7	1.4/	1+			Th k x-ray
				β^- sf	/0.000119				0.45497
									0.50820
									(0.12–2.5)
^{231}Ac		231.0386	7.5 m	β^- /2.1	2.1/100	(1/2+)			0.14379
									0.18574
									0.22140
									0.28250
									0.3070
^{232}Ac		232.0420	2.0 m	β^- /3.7		(2–)			
^{233}Ac		233.0446	2.4 m	β^- /		(1/2+)			
^{234}Ac		234.0484	40. s	β^- /		(1+)			
$_{90}$Th		**232.0381(1)**							
^{209}Th			≈ 0.01 s	α	8.08				
^{210}Th		210.0150	≈ 12 ms	α	7.90				
^{211}Th		211.0149	0.04 s	α	7.79				
^{212}Th		212.0129	≈ 30. ms	α/	7.80/	0+			
^{213}Th		213.0130	0.14 s	α/7.840	7.692(10)/				
^{214}Th		214.0115	0.09 s	α/7.825	7.677(10)/	0+			
^{215}Th		215.0117	1.2 s	α/7.660	7.33(10)/8	(1/2–)			0.134
					7.395(8)/52				0.192
					7.524(8)/40				
^{216m}Th			0.14 ms	α	9.93				
^{216}Th		216.01105	28. ms	α/8.071	7.92/99.46	0+			0.628
					7.30/0.54				
^{217}Th		217.01306	0.25 ms	α/9.424	9.27/94.6				
					8.46/3.8				
					8.73/1.6				
^{218}Th		218.01327	0.11 μs	α/9.847	9.665(10)/	0+			
^{219}Th		219.01552	1.05 μs	α/9.510	9.340(20)/				
^{220}Th		220.01573	10. μs	α/8.953	8.790(20)/	0+			
^{221}Th		221.01817	1.73 ms	α/8.628	7.732/7				
					8.142/72				
					8.469/21				
^{222}Th		222.01845	2.24 ms	α/8.129	7.980/97.7	0+			
					7.599/2.3				
^{223}Th		223.02079	0.65 s	α/7.454	7.29(1)/41(5)				
					7.32(1)/29(5)				
					7.350(15)/20(5)				
					7.390(15)/10(4)				
^{224}Th		224.02146	1.05 s	α/7.305	6.768(5)/1.2				
					6.997(5)/19				
					7.170(5)/7				
^{225}Th		225.02394	8.72 m	EC/(10)/0.68		(3/2+)			
				α/(90)/6.920	6.441(2)/15				
					6.479(2)/43				
					6.501(3)/14				
					6.627(3)/3				
					6.650(5)/3				
					6.700(5)/2				
					6.743(3)/7				
					6.796(2)/9				
^{226}Th		226.024891	30.83 m	α/6.454	6.026(1)/0.2	0+			Ra k x-ray
					6.041(1)/0.19				0.1112
					6.098(1)/1.3				0.2421
					6.2283(4)/23				0.1310
					6.3375(4)/75				0.1733–0.9295

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{227}Th		227.027699	18.72 d	α/6.146		(3/2+)			Ra L x-ray
									Ra k x-ray
									0.05014
									0.23597
									0.25624
									(0.02–1.0)
^{228}Th		228.028731	1.913 y	α/5.520	5.1770(2)/0.18	0+			
					5.2114(1)/0.4				
					5.3405(1)/26.7				
					5.4233(1)/73				
^{229}Th		229.031754	7.9×10^3 y	α/5.168	4.814/9.3	5/2+	+0.46	+4.	0.1935/4.3
					4.845(5)/56				0.21089/277
					4.9008(5)/10.2				0.13697/1.21
					4.689–5.077				0.0111–0.6036
^{230}Th		230.033126	7.54×10^4 y	α/4.771	4.4383(6)/0.03	0+			0.0677/0.46
					4.4798(6)/0.12				0.1439/0.078
			$>2. \times 10^{18}$ y	SF/$<4 \times 10^{-12}$	4.6211(6)/23.4				
					4.6876(6)/76.3				
^{231}Th		231.036296	1.063 d	β^- /0.390	0.138/22	5/2+			Pa L x-ray
					0.218/20				Pa k x-ray
					0.305/52				0.02564
									0.084203/
									(0.02–0.3)
^{232}Th	100.	232.038050	1.40×10^{10} y	α/4.081	3.830(10)/0.2	0+			0.0590
			1.2×10^{21} y	SF/1.1×10^{-9}	3.952(5)/23				0.124
					4.010(5)/77				
^{233}Th		233.041576	22.3 m	β^-/1.245	1.245/	1/2+			Pa L x-ray
									Pa k x-ray
									0.02938
									0.08653
									0.45930
									(0.02–1.2)
^{234}Th		234.043596	24.10 d	β^- /0.273	0.102/20	0+			Pa L x-ray
					0.198/72				0.06329/4.1
									0.09235/2.4
									0.09278/2.4
^{235}Th		235.04751	7.2 m	β^- /1.9					0.4162
									0.6594
									0.7272
									0.747
									0.9318
^{236}Th		236.0497	37.5 m	β^- /≈ 1.0					Pa k x-ray
									0.1107
^{237}Th		237.0539	5.0 m	β^-					
^{238}Th			9.4 m						0.0890
$_{91}$Pa		**231.03588(2)**							
^{212}Pa			≈ 5 ms	α	8.27				
^{213}Pa		213.0212	7 ms	α	8.24				
^{214}Pa		214.0207	17 ms	α	8.12				
^{215}Pa		215.0190	15. ms	α	8.08/100				
^{216}Pa		216.0190	0.19 s	α/	7.95/51				0.134
					7.82/45				
					7.79/4				
^{217m}Pa			1.5 ms	α/	10.16/72				0.4504–0.8208
					8.306/11				
					9.55/6				
					9.69/2				
^{217}Pa		217.0183	3.8 ms	α/8.490	8.337/99				0.0466–0.634
					7.873/0.4				
					7.728/0.3				
					7.710/0.3				
^{218}Pa		218.0200	0.12 ms	α/	9.54/31				0.092
					9.61/69				
^{219}Pa		219.0199	0.05 μs	α					
^{220}Pa		220.0219	0.8 μs	α					

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{221}Pa		221.0219	6. μs	α	9.08(3)				
^{222}Pa		222.0237	≈ 4.3 ms	α/8.700	8.180/50				
					8.330/20				
					8.540/30				
^{223}Pa		223.0240	≈ 6.5 ms	α/8.340	8.006(10)/55				
					8.196(10)/45				
^{224}Pa		224.0256	0.84 s	α/7.630	7.555(10)/75(3)				0.1945
					7.46(1)/25(3)				(0.028–0.412)
^{225}Pa		225.0261	1.8 s	α/7.380	7.195(10)/30				
					7.245(10)/70				
^{226}Pa		226.02792	1.8 m	α/(74)/6.987	6.728(10)/0.7				
				EC/(26)/2.83	6.823(10)/35				
					6.863(10)/39				
^{227}Pa		227.02879	38.3 m	α/(85)/6.582	6.357(4)/7	(5/2–)			0.0649
				EC/(15)/1.02	6.376(10)/2.2				0.0669
					6.401(4)/8				0.1100
					6.416(4)/13				
					6.423(10)/10				
					6.465(4)/43				
^{228}Pa		228.03100	22. h	EC/(98)/2.111		(3+)	+3.5		Th k x-ray
				α/(2)	5.779/0.23				0.409/100
					5.805/0.15				0.4631/222
					6.078/0.4				0.91116/242
					6.105/0.25				0.96464/120
					6.118/0.22				0.96897/149
									0.058–1.96
^{229}Pa		229.03209	1.5 d	EC/(99.8)/0.32		(5/2)			0.04244
				α/(0.2)/5.836	5.536(2)/0.02				(0.024–0.18)
					5.579(2)/0.09				
					5.668(2)/0.05				
^{230}Pa		230.034532	17.4 d	EC/(90)/1.310	0.51/	(2–)	2.0		Th L x-ray
				β^-/(10)/0.563					Th k x-ray
									0.4437
									0.45477
									0.89876
									0.91856
									0.95199
									(0.053–1.07)
^{231}Pa		231.035878	3.25×10^4 y	α/5.148	4.6781(5)/1.5	3/2–	2.01	–1.7	Ac L x-ray
					4.7102(5)/1.0				Ac k x-ray
			$>2 \times 10^{17}$ y	SF/$<1.6 \times 10^{-15}$	4.7343(5)/8.4				0.01899
					4.8513(5)/1.4				0.027396
					4.9339(5)/3				0.03823
					4.9505(5)/22.8				0.04639
					4.9858(5)/1.4				0.25586
					5.0131(5)/25.4				0.26029
					5.0292(5)/20				0.28367
					5.0318(5)/2.5				0.30007
					5.0587(5)/11				0.30264
									0.33007
									(0.02–0.61)
^{232}Pa		232.03858	1.31 d	β^- /1.34		(2–)			U k x-ray
									0.10900
									0.15009
									0.89439
									0.96934
									(0.10–1.17)
^{233}Pa		233.040239	27.0 d	β^-/0.571	0.15/40	3/2–	+4.0	–3.0	U L x-ray
					0.256/60				U k x-ray
									0.30017
									0.31201
									0.34059
^{234m}Pa			1.17 m	β^- /99.9/2.29		(0–)			U k x-ray
				IT/0.13/					0.25818/0.07
									0.76641/0.32
									1.0009/0.85
									(0.06–1.96)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{234}Pa		234.043303	6.69 h	β^- /2.197	0.51/	(4+)			U L x-ray
									U k x-ray
									0.1312/0.03
									0.5695/0.02
									0.9256/0.02
									(0.02–1.99)
^{235}Pa		235.04544	24.4 m	β^- /1.41	1.4/97	(3/2–)			0.0308–0.65893
^{236}Pa		236.0487	9.1 m	β^- /2.9	1.1/40	(1–)			U k x-ray
					2.0/50				0.64235
					3.1/10				0.68759
									1.7630
									(0.04–2.18)
^{237}Pa		237.0511	8.7 m	β^- /2.3	1.1/60	(1/2+)			0.4986
					1.6/30				0.5293
					2.3/10				0.5407
									0.8536
									0.8650
									(0.04–1.4)
^{238}Pa		238.0545	2.3 m	β^- /3.5	1.2/	(3–)			0.10350
					1.7/				0.1785
									0.4484
									0.6350
									0.6800
									1.01446
									(0.04–2.5)
^{239}Pa		239.0571	1.8 h						
$_{92}$U		**238.02891(3)**							
^{217}U			≈16 ms	α	8.005				
^{218}U		218.0235	≈0.002 s	α	8.63(3)/				
^{219}U		219.0249	0.04 ms	α	9.68(4)/				
^{222}U		222.0261	≈ 1.μs	α					
^{223}U		223.0277	0.02 s	α/	8.78(4)/				
^{224}U		224.02759	≈ 1. ms	α/	8.46/100				
^{225}U		225.02938	84. ms	α/	7.87/83				
					7.82/15				
					7.63/2				
^{226}U		226.02933	0.26 s	α/7.560	7.56/86	0+			
					7.38/14				
^{227}U		227.03113	1.1 m	α/7.200	6.870/				
^{228}U		228.03137	9.1 m	α/6.803	6.404(6)/0.6	0+			0.095
					6.440(5)/0.7				0.152
					6.589(5)/29				0.187
					6.681(6)/70				0.246
^{229}U		229.03350	58. m	EC/(80)/1.31	6.223/3	(3/2+)			
				α/(20)/6.473	6.297(3)/11				
					6.332(3)/20				
					6.360(3)/64				
^{230}U		230.033927	20.8 d	α/5.992	5.5866(3)/0.01	0+			Th L x-ray
			$>4 \times 10^{10}$ y	SF/$<10^{-10}$	5.6624(3)/0.26				0.07218
					5.6663(3)/0.38				0.15421
					5.8178(3)/32				0.23034
					5.8887(3)/67				(0.081–0.8565)
^{231}U		231.03626	4.2 d	EC/0.36		(5/2–)			Pa L x-ray
				α/(10^{-3})	5.46/1.6×10^{-3}				Pa k x-ray
					5.47/1.4×10^{-3}				0.02564
					5.40/$1. \times 10^{-3}$				0.08420
^{232}U		232.037146	70. y	α/5.414	4.9979(1)/0.003	0+			
			2.6×10^{15} y	SF/2.7×10^{-12}	5.1367(1)/0.3				
					5.2635(1)/31				
					5.3203(1)/69				
^{233}U		233.039627	1.592×10^5 y	α/4.909	4.7830(8)/13.2	5/2+	+0.59	3.66	Th L x-ray
			$>2.7 \times 10^{17}$ y	SF/6×10^{-11}	4.8247(8)/84.4				0.04244
					4.510–4.804				0.09714
									(0.0252–1.119)
^{234}U	0.0054(5)	234.040945	2.455×10^5 y	α/4.856	4.604(1)/0.24	0+			0.05323/0.156
			1.5×10^{16} y	SF/1.6×10^{-9}	4.7231(1)/27.5				0.12091

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
					4.776(1)/72.5				
^{235m}U			26. m	IT/0.0007		1/2+			
^{235}U	0.7204(6)	235.043922	7.04×10^{8} y	α/4.6793	4.1525(9)/0.9	7/2–	–0.38	4.9	Th L x-ray
			1.0×10^{19} y	SF/7×10^{-9}	4.2157(9)/5.7				Th k x-ray
					4.3237(9)/4.6				0.10917
					4.3641(9)/11				0.14378
					4.370(4)/6				0.16338
					4.3952(9)/55				0.18574
					4.4144(9)/2.1				0.20213
					4.5025(9)/1.7				0.20533
					4.5558(9)/4.2				0.22140
					4.5970(9)/5.0				(0.03–0.79)
^{236}U		236.045561	2.342×10^{7} y	α/4.569	4.332(8)/0.26	0+			Th L x-ray
			2.5×10^{16} y	SF/9×10^{-8}	4.445(5)/26				0.04946/100
					4.494(3)/74				0.11279/24.1
									0.17115/0.080
^{237}U		237.048723	6.75 d	β⁻ /0.519	0.24/	1/2+			Np L x-ray
					0.25/				Np k x-ray
									0.05953
									0.20801
^{238}U	99.2742(10)	238.050784	4.47×10^{9} y	α	4.0395/0.23	0+			Th L x-ray
			8.2×10^{15}y	SF/5×10^{-5}	4.147(5)/23				0.04955/.06
					4.196(5)/77				0.1135/.01
^{239}U		239.054289	23.5 m	β⁻ /1.265	1.2/	5/2+			(0.522–0.681)
					1.3/				
^{240}U		240.056585	14.1 h	β⁻ /0.39	0.36/	0+			Np L x-ray
									0.04410
									0.05558
									0.06760
^{242}U		242.0629	16.8 m	β⁻ /≈ 1.2					
$_{93}$Np									
^{225}Np		225.0339	> 2 μs						
^{226}Np		226.0351	0.03 s	α/	8.04(2)/				
^{227}Np		227.0350	0.51 s	α/	7.65(2)/				
					7.68(1)/				
^{228}Np		228.0362	61. s	EC/60(7)/					
				α/40(7)/, SF					
^{229}Np		229.0363	4.0 m	α/7.010	6.890(20)				
^{230}Np		230.0378	4.6 m	EC/97 /3.6					
				α/3	6.660(20)				
^{231}Np		231.03823	48.8 m	EC/98 /1.8		5/2			0.2629
				α/2 /6.368	6.280/2				0.3475
									0.3703
^{232}Np		232.0400	14.7 m	EC/99 /2.7		(4–)			U L x-ray
									U k x-ray
									0.3268
									0.81925
									0.86683
^{233}Np		233.0410	36.2 m	EC/1.2		(5/2+)			U L x-ray
									U k x-ray
									0.29887
									0.31201
^{234}Np		234.04289	4.4 d	β⁺, EC/1.81	0.79/	(0+)			U L x-ray
									U k x-ray
									1.5272
									1.5587
									1.6022
^{235}Np		235.044055	1.085 y	EC/99.9 /0.124		5/2+			U k x-ray
				α/0.001/5.191					
^{236m}Np			22.5 h	EC/52 /		(1–)			U L x-ray
				β⁻ /48 /					Pu L x-ray
									U k x-ray
									0.64235
									0.68759
^{236}Np		236.04657	1.55×10^{5} y	EC/91 /0.94		(6–)			U L x-ray

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
				β⁻ /9 /0.49					U k x-ray
									0.10423
									0.16031
^{237}Np		237.048166	2.14×10^{6} y	α/4.957	4.6395(5)/6.5	5/2+	+3.14	+3.89	Pa L x-ray
			1×10^{18} y	SF/2.1×10^{-10}	4.766(5)/9.7				Pa k x-ray
					4.7715(5)/22.7				0.029378/15
					4.7884(5)/47.8				0.08653/12
					4.558–4.873				(0.03–0.28)
^{238}Np		238.050940	2.117 d	β⁻ /1.292	1.2/	2+			Pu L x-ray
									Pu k x-ray
									0.98447/25.2
									1.02855/18.3
									(.044–1.026)
^{239}Np		239.052931	2.355 d	β⁻ /0.722	0.341/30	5/2+			Pu L x-ray
					0.438/48				Pu k x-ray
									0.10613
									0.228186/11
									0.27760/15
									(0.04–0.50)
^{240m}Np			7.22 m	β⁻ /99.9 /	2.18/	(1+)			0.25143
				IT/0.1 /					0.26333
									0.55454
									0.59735
^{240}Np		240.05617	1.032 h	β⁻ /2.20	0.89/	5+			0.1471/
									0.5664
									0.6008
^{241}Np		241.0583	13.9 m	β⁻ /1.3	1.3/	5/2+			0.1330/
									0.1740
									0.280
^{242m}Np			2.2 m	β⁻ /		(1+)			0.15910
									0.2651/
									0.78570
									0.9448/
^{242}Np		242.0616	5.5 m	β⁻ /2.7	2.7/	6+			0.6209
									0.73620
									0.78074
									1.47340
									(0.04–2.37)
^{243}Np		243.0643	1.9 m						
^{244}Np		244.0678	2.3 m						
$_{94}$Pu									
^{228}Pu		228.0387		α/	7.81(2)/				
^{229}Pu		229.0362	≈1.5 m	α/	7.46/				
^{230}Pu		230.03964	1.7 m	α/	7.06/81				
					7.00/19				
^{231}Pu		231.04126	8.6 m	EC/90					
				α/10	6.72				
^{232}Pu		232.04118	34. m	EC/>80/1.1		0+			
				α/<20/6.716	6.542(10)/38				
					6.600(10)/62				
^{233}Pu		233.04299	20.9 m	EC(99.9)/1.9					0.1503
				α/0.1 /6.416	6.300(20)/0.1				0.1804
									0.2353
									0.5002
									0.5346/
									1.0352/
^{234}Pu		234.04331	8.8 h	EC/94 /0.39		0+			
				α/6 /6.310	6.035(3)/0.024				
					6.149(3)/1.9				
					6.200(3)/4.				
^{235}Pu		235.0453	25.3 m	EC/99+ /1.2		(5/2+)			
				α/0.003/5.957	5.850(20)/0.003				
^{236}Pu		236.046048	2.87 y	α/5.867	5.611/0.21	0+			0.0476/0.07
			1.5×10^{9} y	SF/1.9×10^{-7}	5.7210/30.5				0.109/0.02
					5.7677(1)/69.3				(0.17–0.97)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{237}Pu		237.048403	45.7 d	EC/99.9 /0.220		7/2–			Np L x-ray
				α/0.003 /5.747	5.334(4)/0.0015				Np k x-ray
					5.356(4)/0.0006				0.026344
					5.650(4)/0.0007				0.03319
									0.05954
									(0.03–0.5)
^{238}Pu		238.049553	87.7 y	α/5.593	5.3583(1)/0.10	0+			U k x-ray
			4.75×10^{10} y	SF/1.8×10^{-7}	5.465(1)/28.3				0.04347
					5.4992(1)/71.6				(0.04–1.1)
^{239}Pu		239.052156	2.410×10^{4} y	α/5.244	5.055/0.047	1/2+	+0.203		U k x-ray
			$8. \times 10^{15}$ y	SF/3×10^{-10}	5.076/0.078				0.05162
					5.106/11.9				0.05682
					5.144/17.1				0.12928
					5.157/70.8				0.37502
					(4.74 –5.03)				0.41369
^{240}Pu		240.053807	6.56×10^{3} y	α/5.255	5.0212(1)/0.07	0+			U L x-ray
			1.14×10^{11} y	SF/5.7×10^{-6}	5.1237(1)/26.4				0.04524
					5.1681(1)/73.5				0.10423
									(0.04–0.97)
^{241}Pu		241.056844	14.4 y	β⁻/99+/0.0208	$4.853(7)/3 \times 10^{-4}$	5/2+	–0.683	+6.	0.14854
				α/0.002 /5.139	4.8966(7)/0.002				0.1600
			<$6. \times 10^{16}$ y	SF/>2.4×10^{-14}					
^{242}Pu		242.058736	3.75×10^{5} y	α/4.983	4.7546(7)/0.098	0+			U L x-ray
			6.77×10^{10} y	SF/5.5×10^{-4}	4.8564(7)/22.4				0.04491
					4.9006(7)/78				0.10350
^{243}Pu		243.061996	4.956 h	β⁻ /0.582	0.49/21	7/2+			Am L x-ray
					0.58/60				0.0417
									0.0839
^{244}Pu		244.064197	8.00×10^{7} y	α/99.9/4.665	4.546(1)/19.4	0+			U L x-ray
			6.6×10^{10} y	SF/0.12	4.589(1)/80.5				0.0439
^{245}Pu		245.06774	10.5 h	β⁻ /1.21	0.93/57	(9/2–)			Am L x-ray
					1.21/11				Am k x-ray
									0.2804 /
									0.30832
									0.32752
									0.56014
									(0.03–1.2)
^{246}Pu		246.07020	10.85 d	β⁻ /0.40	0.150/85	0+			Am L x-ray
					0.35/10				Am k x-ray
									0.04379
									0.22371
^{247}Pu		247.0741	2.3 d						
$_{95}$Am									
^{232}Am		232.0466	0.9 m	EC/≈ 5.0					
^{233}Am		233.0465	≈3.2 m	α	6.78				
^{234}Am		234.0478	2.3 m	EC/4.2					
^{235}Am		235.0480	≈15 m	EC					Pu K x-ray
^{236}Am		236.0456	54. s						
^{237}Am		237.0503	1.22 h	EC/99.98 /1.7		(5/2–)			Pu k x-ray
				α/0.02 /6.20	6.042(5)/0.02				0.14559
									0.28026
									0.43845
^{238}Am		238.05198	1.63 h	EC/2.26		1+			Pu L x-ray
				α/0.0001 /6.04	5.940/0.0001				Pu k x-ray
									0.91870
									0.96278
^{239}Am		239.053018	11.9 h	EC/99.99/0.803		5/2–			Pu L x-ray
				α/0.01/5.924	5.734(2)/0.001				Pu k x-ray
					5.776(2)/0.008				0.18172
									0.22818
									0.27760
^{240}Am		240.05529	2.12 d	EC/1.38		(3–)			Pu L x-ray
				α/5.592	$5.378(1)/16 \times 10^{-4}$				Pu k x-ray
									0.88878
									0.98764

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
									(0.1–1.3)
^{241}Am		241.056822	432.7 y	α/5.637	5.2443(1)/0.002	5/2–	+1.58	+3.1	Np L x-ray
			1.2×10^{14} y	SF/3.6×10^{-10}	5.3221(1)/0.015				0.02634 /.024
					5.3884(1)/1.4				0.03319/.00126
					5.4431(1)/12.8				0.05954/0.359
					5.4857(1)/85.2				(0.03–1.128)
					5.5116(1)/0.20				
					5.5442(1)/0.34				
^{242m}Am			141. y	IT/99.5/0.048		5–	+1.0	+6.5	Am L x-ray
				α/0.5/5.62	5.141(4)/0.026				0.04863
			$>3. \times 10^{12}$ y	SF/$<4.7 \times 10^{-9}$	5.2070(2)/0.4				0.08648
									0.10944
									0.16304
^{242}Am		242.059542	16.02 h	β⁻ /83 /0.665	0.63/46	1–	+0.388	–2.4	Pu L x-ray
				EC/17 /0.750	0.67/37				Cm L x-ray
									Pu k x-ray
									0.0422
									0.04453
^{243}Am		243.061372	7.37×10^{3} y	α/5.438	5.1798(5)/1.1	5/2–	+1.5	+2.9	0.04354
			$2. \times 10^{14}$ y	SF/3.7×10^{-9}	5.2343(5)/11				0.07467
					5.2766(5)/88				0.08657
					5.394(5)/0.12				0.11770
					5.3500(5)/0.16				0.14197
^{244m}Am			≈ 26. m	β⁻ /1.498		(1–)			0.0429
^{244}Am		244.064279	10.1 h	β⁻ /1.428					Am L x-ray
									Cm k x-ray
									0.7460
									0.9000
^{245}Am		245.066444	2.05 h	β⁻ /0.894	0.65/19	(5/2+)			Cm L x-ray
					0.90/77				Cm k x-ray
									0.25299
^{246m}Am			25.0 m	β⁻ /	1.3/79.	2–			Cm L x-ray
					1.60/14				Cm k x-ray
					2.1/7				0.27002
									0.79881
									1.06201
									1.07885
									(0.04–2.29)
^{246}Am		246.06977	39. m	β⁻ /2.38	1.2/	(7–)			Cm L x-ray
									Cm k x-ray
									0.1529
									0.2046
									0.6786
^{247}Am		247.0722	22. m	β⁻ /1.7					Cm L x-ray
									Cm k x-ray
									0.2267 /
									0.2853 /
$_{96}$Cm									
^{233}Cm		233.0508		α/	7.34/				
^{234}Cm		234.0502	≈51. s	α	7.24/				
^{235}Cm		235.0516							
^{236}Cm		236.0514		EC/1.7					
^{237}Cm		237.0529		EC/2.5					
^{238}Cm		238.05302	2.4 h	EC/>90 /0.97		0+			
				α/<10 /6.632	6.520(50)/<10				
^{239}Cm		239.0548	≈ 3. h	EC/1.7					
									0.0407
									0.1466
									0.1874
^{240}Cm		240.055519	27. d	α/6.397	5.989/0.014	0+			
					6.147/0.05				
			1.9×10^{6} y	SF/3.9×10^{-6}	6.2478(6) /28.8				
					6.2906(6) /70.6				
^{241}Cm		241.057646	32.8 d	EC/99 /0.768		1/2+			Am k x-ray
				α/1 /6.184	5.8842(4)/0.12				0.13241

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
					5.9291(4)/0.18				0.16505
					5.9389(4)/0.69				0.18028
									0.43063
									0.47181
^{242}Cm		242.058828	162.8 d	α/6.216	5.9694(1)/0.035	0+			Pu L x-ray
					6.069(1)/25				0.04408
			7.0×10^{6} y	SF/6.4×10^{-6}	6.1129(1)/74				0.10189
									(0.04–1.2)
^{243}Cm		243.061381	29.1 y	α/6.167	5.6815(5) /0.2	5/2+	0.41		Pu L x-ray
					5.6856(5)/1.6				Pu k x-ray
			5.5×10^{11} y	SF/5.3×10^{-9}	5.7420(5)/10.6				0.10612
					5.7859(5)/73.3				0.20975
					5.9922(5)/6.5				0.22819
					6.0103(5)/1.0				0.27760
					6.0589(5)/5				0.28546
					6.0666(5)/1.5				0.33431
									(0.04–0.7)
^{244}Cm		244.062745	18.1 y	α/5.902	5.6656/0.02	0+			Pu L x-ray
					5.7528/23				0.04282
			1.32×10^{7} y	SF/1.4×10^{-4}	5.8050/77				0.09885
					5.515/0.004				0.15262
^{245}Cm		245.065485	8.48×10^{3} y	α/5.623	5.235(10)/0.3	7/2+	0.5		Pu L x-ray
					5.3038(10)/5.0				Pu k x-ray
			1.4×10^{12} y	SF/6.1×10^{-7}	5.3620(7)/93				0.04195
					5.4927(11)/0.8				0.13299
					5.5331(11)/0.6				0.13606
									0.17494
^{246}Cm		246.067217	4.76×10^{3} y	α/5.476	5.343(3)/21	0+			Pu L x-ray
			1.8×10^{7} y	SF/0.026	5.386(3)/79				0.04453
^{247}Cm		247.070346	1.56×10^{7} y	α/5.352	4.818(4)/4.7	9/2–	0.37		Pu k x-ray
					4.8690(20)/71	9/2–			0.2792
					4.941(4)/1.6				0.2886
					4.9820(20)/2.0				0.3471
					5.1436(20)/1.2				0.4035
					5.2104(20)/5.7				
					5.2659(20)/13.8				
^{248}Cm		248.072341	3.48×10^{5} y	α/99.92 /5.162	4.931(5)/0.07	0+			
					5.0349(2)/16.5				
			4.15×10^{6} y	SF/8.38	5.0784(2)/(75)/1				
^{249}Cm		249.075946	64.15 m	β^- /0.900	0.9/	1/2+			Bk k x-ray
									0.56039
									0.63431
^{250}Cm		250.07835	$\approx 9.7 \times 10^{3}$ y	SF/85.8		0+			
				α/5.27					
^{251}Cm		251.08228	16.8 m	β^- /1.42	0.90/16	(1/2+)			0.3896 /
									0.5299
									0.5425
^{252}Cm		252.0849	< 2 d						
$_{97}$Bk									
^{238}Bk		238.0583	2.4 m	EC/5.0					
^{239}Bk		239.0584							
^{240}Bk		240.0598	≈ 4.8 m						
^{242}Bk		242.0621	7.0 m	EC/3.0					
^{243}Bk		243.063001	4.5 h	EC/99.8 /1.508	6.542(4)/0.03	(3/2–)			0.1466
				α/0.15 /6.871	6.5738(2)/0.04				0.1874
					6.7180(22)/0.02				0.755
					6.7581(20)/0.02				0.840
									0.946
^{244}Bk		244.0652	4.4 h	EC/99.99 /2.26		(4–)			0.1445
				α/0.01 /6.778	6.625(4)/0.003				0.1876
					6.667(4)/0.003				0.2176
									0.9815
									0.9215/
^{245}Bk		245.066355	4.94 d	EC/99.9 /0.810		3/2–			Cm L x-ray
				α/0.1 /6.453	5.8851(5)/0.03				Cm k x-ray
					6.1176(9)/0.01				0.25299

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin (h/2π)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
					6.1467(5)/0.02				0.3809
					6.3087(5)/0.014				0.3851
					6.3492(5)/0.018				
^{246}Bk		246.0687	1.80 d	EC/1.35		(2–)			Cm L x-ray
									Cm k x-ray
									0.79881
									1.08142
^{247}Bk		247.07030	1.4×10^3 y	α/5.889	5.465(5)/1.5	(3/2–)			0.04175
					5.501(5)/7				0.0839
					5.532(5)/45				0.268
					5.6535(20)/5.5				
					5.678(2)/13				
					5.712(2)/17				
					5.753(2)/4.3				
					5.794(2)/5.5				
^{248}Bk		248.07311	23.7 h	β^- /70 /0.87	0.86/	(1–)			Cm L x-ray
				EC/30 /0.72					Cf L x-ray
									Cm k x-ray
									Cf k x-ray
									0.5507
^{249}Bk		249.074980	320. d	β^- /0.125	0.125/100	7/2+	2.0		$0.327/10^{-5}$
				α/0.001 /5.525	5.390(1)/0.0002				$0.308/10^{-6}$
			1.8×10^9 y	SF/4.9×10^{-8}	5.4174(6)/0.001				
^{250}Bk		250.078309	3.217 h	β^- /1.780	0.74/	2–			Cf L x-ray
									Cf k x-ray
									0.98912
									1.03184
									(0.04–1.6)
^{251}Bk		251.08075	56. m	β^- /1.09		(3/2–)			0.02481
									0.1528
									0.1776
^{252}Bk		252.0843	1.8 m						
$_{98}$Cf									
^{237}Cf		237.0621	2.1 s	α, SF/10					
^{238}Cf		238.0614	21 ms	SF/					
^{239}Cf		239.0626	≈ 0.7 m	α					
^{240}Cf		240.0623	1.1 m	α/7.719	7.590(10)/	0+			
				SF/ ≈2.1					
^{241}Cf		241.0637	4. m	EC/3.3					
				α/7.60	7.335(5)/				
^{242}Cf		242.06369	3.5 m	α/7.509	7.351(6)/20	0+			
				SF/≤0.014	7.385(4)/80				
^{243}Cf		243.0654	11. m	EC/86 /2.2	7.060(6)/20	(1/2+)			
				α/14 /7.40	7.170/4				
^{244}Cf		244.065990	20. m	α/7.328	7.168(5)/25	0+			
					7.210(5)/75				
^{245}Cf		245.068038	44. m	α/36 /7.255	7.15/91.7				Cm K x-ray
				EC/64 /1.569	6.983/0.31				0.5709
					7.09/7				0.6014
					7.065/0.68				0.6163
^{246}Cf		246.068798	1.49 d	α/6.869	6.6156(10)/0.18	0+			Cm L x-ray
					6.7086(7)/21.8				0.04221
			1.8×10^3 y	SF/2.3×10^{-4}	6.7501(7)/78.0				0.0945
									0.147
^{247}Cf		247.07099	3.11 h	EC/99.96 /0.65		7/2+			Bk k x-ray
				α/0.04 /6.55	6.301(5)/				0.2941
									0.4778
^{248}Cf		248.07218	334. d	α/6.369	6.220(5)/17	0+			
			3.2×10^4 y	SF/0.0029	6.262(5)/83				
^{249}Cf		249.074846	351. y	α/6.295	5.758/3.7	9/2–			Cm L x-ray
					5.812/85.7				Cm k x-ray
			$8. \times 10^{10}$ y	SF/4.4×10^{-7}	5.8488(2)/1.0				0.25299/2.5
					5.9029(2)/2.8				0.33351/13.6
					5.9451(2)/4.0				0.38832/63.6
					6.1401(2)/1.1				(0.0376–1.103)

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin (h/2π)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
					6.1940(2)/2.2				
^{250}Cf		250.076399	13.1 y	α/6.129	5.8913(4)/0.3	0+			Cm L x-ray
			1.7×10^4 y	SF/0.077	5.9889(4)/15				0.04285
					6.0310(4)/84.5				
^{251}Cf		251.079579	9.0×10^2 y	α/6.172	5.56448(7)/1.5	1/2+			
					5.632(1)/4.5				
					5.648(1)/3.5				
					5.6773(6)/35				
					5.762(3)/3.8				
					5.7937(7)/2.0				
					5.8124(8)/4.2				
					5.8514(6)/27				
					6.0140(7)/11.6				
					6.0744(7)/2.7				
^{252}Cf		252.081619	2.65 y	α/96.9 /6.217	5.7977(1)/0.23	0+			Cm L x-ray
			86. y	SF/3.1/	6.0756(4)/15.2				0.04339
					6.1184(4)/81.6				0.1002
^{253}Cf		253.08512	17.8 d	β⁻ /99.7 /0.29	0.27/100	(7/2+)			
				α/0.3 /6.126	5.921(5)/0.02				
^{254}Cf		254.08732	60.5 d	SF/99.7/		0+			
				α/0.3/5.930	5.792(5)/0.05				
					5.834(5)/0.26				
^{255}Cf		255.0910	1.4 h	β⁻ /0.7					
^{256}Cf		256.0934	12. m	SF					
$_{99}$Es									
^{241}Es		241.0687	≈ 8 s	α	8.11				
^{242}Es		242.0697	16 s	α	7.92				
^{243}Es		243.0696	21. s	α/>30 /	7.89/>30				
				EC/<70 /4.0					
^{244}Es		244.0709	37. s	EC/76 /4.6					
				α/4 /	7.57/4				
^{245}Es		245.0713	1.3 m	α/40 /7.858	7.74				
				EC/60 /3.1					
^{246}Es		246.0730	7.7 m	EC/90 /3.9					
				α/10 /	7.35				
^{247}Es		247.07365	4.8 m	EC/93 /2.48					
				α/7 /	7.32				
^{248}Es		248.0755	26. m	EC/99.7 /3.1					
				α/0.3 /	6.87				
^{249}Es		249.07640	1.70 h	EC/99.4 /1.45		(7/2+)			0.3795
				α/0.6 /	6.77				0.8132
^{250m}Es			2.2 h	EC/		(1–)			Cf L x-ray
				β⁺					Cf k x-ray
									0.9891
									1.0319
^{250}Es		250.0787	8.6 h	EC/2.1		(6+)			Cf L x-ray
									Cf k x-ray
									0.30339
									0.34948
									0.82883
^{251}Es		251.07998	1.38 d	EC/99.5 /0.38		(3/2–)			
				α/0.5 /	6.462/0.05				
					6.492/0.4				
^{252}Es		252.08297	1.29 y	α/76 /	6.632/61.0	(5–)			
				EC/24 /1.26	6.562/10.3				
^{253}Es		253.084818	20.47 d	α/	6.633/89.8	7/2+	+4.10	7.	0.04180
			6.3×10^5 y	SF/8.9×10^{-6}	6.5916/6.6				0.3892
^{254m}Es			1.64 d	β⁻ /99.6 /	0.475	2+	2.9	3.7	Fm L x-ray
				α/0.3 /6.67	6.382	2+			Fm k x-ray
			>10. y	SF/0.045					0.6488
									0.6938
^{254}Es		254.088017	276. d	α/	6.429	(7+)			0.064
			$>2.5 \times 10^7$ y	SF/$<3 \times 10^{-6}$					
^{255}Es		255.09027	40. d	β⁻ /92 /0.29		(7/2+)			
				α/8 /	6.26				

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
			2.6×10^3 y	SF/0.0042	6.300				
^{256m}Es			7.6 h	β^- /		(8+)			0.218
									0.232
									0.862
^{256}Es		256.0936	25. m	β^-/1.7		(1+)			
^{257}Es		257.0960	7.7 d	β^-					
$_{100}$Fm									
^{242}Fm		242.0734	0.8 ms	SF/>96					
^{243}Fm		243.0745	0.2 s	α/	8.55				
				<SF/0.4					
^{244}Fm		244.0741	3.3 ms	SF/>97		0+			
^{245}Fm		245.0754	4. s	α/	8.15/				
				SF/<0.1					
^{246}Fm		246.07528	1.2 s	α/85/	8.24/	0+			
				SF/15/					
^{247m}Fm			9. s	α/	8.18/				
^{247}Fm		247.0768	35. s	α/8.20	7.87/70				
				EC/2.9	7.93/30				
^{248}Fm		248.07718	34. s	α/99.9 /8.001	7.83/20	0+			
				SF/0.1/	7.87/80				
^{249}Fm		249.0790	3. m	EC/2.4		(7/2+)			
				α/	7.53				
^{250m}Fm			1.8 s	IT/					
				SF/<8×10^{-5}					
^{250}Fm		250.07951	30. m	α/	7.43/	0+			
				EC/0.8					
				SF/0.007					
^{251}Fm		251.08157	5.3 h	EC/98 /1.47		(9/2–)			
				α/2 /	6.833				
^{252}Fm		252.08246	1.058 d	α/7.154	6.998/15	0+			
				SF/0.0023	7.039/85				
^{253}Fm		253.085175	3.0 d	EC/88/0.333	6.676/	1/2+			Es k x-ray
				α/12 /	6.943/				0.2719
^{254}Fm		254.086847	3.240 h	α/	7.150	0+			
				SF/0.059	7.192				
^{255}Fm		255.089955	20.1 h	α/	6.9635(5)/5.0	7/2+			
			1.0×10^4 y	SF/2.3×10^{-5}	7.0225(5)/93.4				
^{256}Fm		256.09177	2.63 h	SF/91		0+			
				α/19	6.92/				
^{257}Fm		257.09510	100.5 d	α/99.79	6.519	(9/2+)			0.1794
				SF/0.21					0.2410
^{258}Fm		258.0971	0.37 ms	SF/					
^{259}Fm		259.1006	1.5 s	SF/					
^{260}Fm			≈ 4 ms	SF/					
$_{101}$Md									
^{245m}Md			≈0.4 s	α	8.64, 8.68				
^{245}Md		245.0810	0.9 ms	SF					
^{246}Md		246.0819	1.0 s	α	8.74				
					8.50–8.56				
^{247m}Md			≈0.2 s	SF/					
^{247}Md		247.0818	3. s	α	8.43				
^{248}Md		248.0828	7. s	EC/80 /5.3	8.32/15				
				α/20 /	8.36/5				
				SF/<0.05					
^{249}Md		249.0830	24. s	EC>/<80 /3.7					
				α/>20 /8.46	8.030(20)/				
^{250}Md		250.0845	50. s	EC/94 /4.6	7.75/4				
				α/6 /8.25	7.83/2				
^{251}Md		251.0849	4.0 m	EC/>94 /3.1					
				α/<6 /	7.55/				
^{252}Md		252.0866	2. m	EC/>50 /3.9					
				α/<50 /	7.73/				
^{253}Md		253.0873	≈6 m	EC/2.0					

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{254m}Md			30. m	EC/					
^{254}Md		254.0897	10. m	EC/2.7					
^{255}Md		255.09108	27. m	EC/92 /1.04	α/7.33/93	(7/2–)			0.121/100
				α/8 /	7.27/5				0.115/65
				SF/≤0.15	7.75/1				0.136/35
					7.71/1				0.141–0.453
^{256}Md		256.0941	1.30 h	EC/89 /2.13	7.21/71				Fm k x-ray
				α/11 /	7.14/22				0.121/409
				SF/<2.6	7.68/2.5				0.115/266
					7.25/2.5				0.136/143
					7.64/2.1				0.634/119
									0.141–1.37
^{257}Md		257.095535	5.5 h	EC/85 /0.41	7.074	(7/2–)			Fm k x-ray
				α/15, SF/≤1	7.014				(0.181–0.389)
^{258m}Md			57. m	EC/		(1–)			Fm k x-ray
				SF/≤30					
^{258}Md		258.098427	51.5 d	α/7.40	6.718(2)/	(8–)			0.3678
				SF/≤0.003	6.763(4)/				0.057–0.448
^{259}Md		259.1005	1.64 h	SF/>98.7		7/2+			
				α/<1.3					
^{260}Md		260.104	≈ 27.8 d	SF/73–100					
$_{102}$No									
^{250}No		250.0875	≈ 0.036 ms	SF/		0+			
^{251}No		251.0889	0.76 s	α/91	8.62/96				
				SF/0.26	8.58/4				
^{252}No		252.08897	2.44 s	α/68/8.551	8.42	0+			
			7.6 s	SF/32/	8.37				
				EC, β^+/<1.6					
^{253}No		253.0907	1.7 m	α/	8.010(20)	(9/2–)			
				EC/3.2					
^{254m}No			0.28 s	I.T./					
				SF/≤.2					
^{254}No		254.09095	49. s	α/	8.09	0+			
				EC/1.1					
				SF/0.17					
^{255}No		255.09323	3.1 m	α/62 /	8.12/	1/2+			0.187
				EC/38/2.01	7.93				
					8.08				
^{256}No		256.09428	2.9 s	α/	8.43	0+			
				SF/0.5					
^{257}No		257.09685	25. s	α/	8.22	(7/2+)			
				SF/<1.5	8.27				
					8.32				
^{258}No		258.0983	≈1.2 ms	SF/		0+			
^{259}No		259.1011	58. m	α/78 /7.794	7.52	(9/2+)			
				EC/22/0.5	7.55				
				SF/<9.7					
^{260}No		260.103	0.11 s	SF/					
^{262}No		262.108	≈ 8. ms	SF/					
$_{103}$Lr									
^{251}Lr		251.0944	39 m	SF					
^{252}Lr		252.0953	≈0.36 s	α	9.02/73				
				SF/<1	8.97/27				
^{253m}Lr			≈0.57 s	α	8.79				
				SF/1.3					
^{253}Lr		253.0953	1.5 s	α/	8.72				
				SF/8					
^{254}Lr		254.0965	13. s	α/	8.45				
				EC/5.2					
				SF/<0.1					
^{255}Lr		255.0967	22. s	α/	8.37/60				
				EC/3.2	8.43/40				
				SF/<0.1					

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{256}Lr		256.0988	28. s	α/99.7 /8.554	8.43/				
				EC/4.2	8.39				
				SF/<0.03					
^{257}Lr		257.0996	0.65 s	α/	8.80	7/2+			
				EC/2.5	8.80				
				SF/<0.03					
^{258}Lr		258.1019	3.9 s	α/	8.60/46				
				EC/3.4	8.62/25				
				SF/<5	8.56/20				
					8.65/9				
^{259}Lr		259.1030	6.1 s	α/80	8.44(1)				
				SF/20					
^{260}Lr		260.1056	3. m	α/	8.03				
^{261}Lr		261.1069	40. m	SF					
^{262}Lr		262.1097	3.6 h	EC/2.					
				SF/<10					
$_{104}$Rf									
^{253}Rf		253.1007	≈ 48. μs	SF					
				α/<10					
^{254}Rf		254.1002	23. μs	SF/>98.5					
				α/<1.5					
^{255}Rf		255.1015	1.6 s	α	8.72/<0.05				0.203
				SF/52	8.77/94				0.142
					8.67/<0.05				
					8.58/<0.05				
					8.92/<0.05				
^{256}Rf		256.10118	6.2 ms	SF/99.68					
				α/0.32	8.81				
^{257}Rf		257.1031	4.7 s	α/9.22	8.77				0.117
				EC/11	9.01				
				SF/<1.4	8.95				
					8.62				
^{258}Rf		258.1036	12. ms	SF/87					
				α/13					
^{259}Rf		259.1056	3.4 s.	α/9.09/93	8.77(2)/				
				SF/7	8.86/				
^{260}Rf		260.1064	20. ms	SF/					
^{261}Rf		261.1088	1.1 m	α/8.78, SF/<10	8.28/				
^{262}Rf		262.1099	2.1 s	SF/>99.2					
^{263}Rf		263.1125	22. m	SF, α					
$_{105}$Db									
^{255}Db		255.1074	≈1.5 s	α,					
				SF/≈20					
^{256}Db		256.1081	1.6 s	α/64	9.02/67				
				EC/35	8.89/11				
				SF/0.05	9.08/11				
					9.12/11				
^{257m}Db			0.8 s	α	9.16				
				SF/<13					
^{257}Db		257.1079	1.5 s	α/	8.97/33				
				SF/<6	9.07/38				
					9.12/5.5				
					8.94/9				
					9.02/9				
					8.89/5.5				
^{258}Db		258.1094	4.2 s	α/	9.30/				
				E.C/5.3	9.17/				
				SF/<33	9.08/				
^{259}Db		259.1097	≈ 0.51 s	SF/					
				α/	9.47/				
^{260}Db		260.1114	1.5 s	α/	9.05/				
				SF/<9.6	9.08/				
					9.13/				

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{261}Db		261.1121	1.8 s	α/	8.93/				
				SF/<18					
^{262}Db		262.1141	34. s	SF/<33					
				α/	8.45/				
					8.53/				
					8.67/				
^{263}Db		263.1151	≈ 0.45 m	SF/57	8.36/				
				α/41	8.41/				
				EC/3					
$_{106}$Sg									
^{258}Sg		258.1132	≈2.9 ms	SF					
				α/<20					
^{259}Sg		259.1147	0.5 s	α/	9.62				
				SF/<20	9.35				
					9.03				
^{260}Sg		260.11444	4. ms	α/50	9.76				
				SF/50	9.72				
					9.81				
^{261}Sg		261.1162	0.3 s	α, SF/<10	9.56				
^{262}Sg			0.007 s	SF					
				α/<22					
^{263}Sg		263.1183	0.8 s	α	9.06				
				SF/<30	9.25				
^{265}Sg		265.1211	≈7.4 s	α/>65	8.84/46				
				SF/<35	8.76/23				
					8.94/23				
					8.69/8				
^{266}Sg		266.1219	≈21. s	α/	8.77/66				
				SF/<82	8.52/33				
$_{107}$Bh									
^{260}Bh		260.122		α					
^{261}Bh		261.1218	12. ms	α/, SF<10	10.40				
					10.10				
					10.03				
^{262m}Bh			8. ms	α/	10.37				
				SF/<12	10.24				
^{262}Bh		262.1230	0.10 s	α/	10.06				
				SF/<12	9.91				
					9.74				
^{264}Bh		264.1247	0.44 s	α/	9.48				
				SF/	9.62				
^{266}Bh		266.1270	≈1 s	9.29					
^{267}Bh		267.1277	≈17 s	8.83					
$_{108}$Hs									
^{263}Hs		263.1287		α/					
^{264}Hs		264.1284	≈0.08 ms	α/, SF/≈50	11.0				
^{265m}Hs			≈0.75 ms	α	10.57/63				
					10.73				
					10.52				
					10.34				
^{265}Hs		265.1300	2.0 ms	α/	10.30/90				
				SF/<1	10.43				
					10.37				
					10.25				
^{266}Hs		266.1300	≈2.3 ms	α	10.2				
^{267}Hs		267.1371	33 ms	α/>88	9.88				
					9.83				
					9.75				
^{269}Hs		269.1341	9.3 s	α	9.23				
					9.17				
^{270}Hs			2–7 s	α	9.16				

Elem. or Isot.	Natural Abundance (Atom %)	Atomic Mass or Weight	Half-life/ Resonance Width (MeV)	Decay Mode/ Energy (/MeV)	Particle Energy/ Intensity (MeV/%)	Spin ($h/2\pi$)	Nuclear Magnetic Mom. (nm)	Elect. Quadr. Mom. (b)	γ-Energy /Intensity (MeV/%)
^{277}Hs			≈11 m	SF					
$_{109}$Mt									
^{266m}Mt			≈1.2 ms	α	10.46–10.81				
^{266}Mt		266.1379	≈0.7 ms	α	10.48–11.31				
^{267}Mt		267.138	19 ms	α					
^{268}Mt		268.1388	0.07 s	α/>68	10.10, 10.24				
$_{110}$DS									
^{267}110		267.1440	≈ 3 μs	α/>32	11.6				
^{269}110		269.1451	0.17 ms	α/>75	11.11				
^{271m}110			≈1.1 ms	α	10.68				
					10.74				
^{270m}110			≈6 ms	α	10.95				
					11.15				
					12.15				
^{270}110		270.1446	0.1 ms	α	11.03				
^{271}110		271.1461	≈ 56 ms	α	10.71				
^{273m}110			0.076 ms	α	11.8				
^{273}110		273.1492	118 ms	α/	9.73				
^{280}110			≈7.5 s	SF/					
^{281}110			≈ 1 m	α	8.83				
$_{111}$Rg									
^{272}111		272.1535	≈ 1.5 ms	α/>68	10.82				
$_{112}$112									
^{277}112			≈ 0.24 ms	α	11.45				
					11.65				
^{283}112			≈ 3. m	sf/>0.7					
				α/<0.3					
^{284}112			≈9.8 s	α	9.17				
^{285}112			≈11. m	α	8.67				
$_{114}$114									
^{287}114			≈5.5 s	α	10.3				
^{288}114			≈1.9 s	α	9.84				
^{289}114			≈ 20. s	α	9.71				
$_{116}$116									
^{292}116			≈ 0.03 s	α	10.6				

NEUTRON SCATTERING AND ABSORPTION PROPERTIES

Norman E. Holden

This table presents an evaluated set of values for experimental quantities that characterize the properties for scattering and absorption of neutrons. The neutron cross section is given for room temperature neutrons, 20.43°C, corresponding to a thermal neutron energy of 0.0253 electron volts (eV) or a neutron velocity of 2200 meters/second. The neutron resonance integral is defined over the energy range from 0.5 eV to 0.1×10^6 eV, or 0.1 MeV. Bound neutron scattering lengths and neutron cross sections averaged over a Maxwellian spectrum at 30 keV for astrophysical applications are also presented. A list of the major references used is given below. The literature cutoff date is January 2003. Uncertainties are given in parentheses. Parentheses with two or more numbers indicate values to the excited state(s) and to the ground state of the product nucleus.

Table Layout

Column Number	Column Title	Description
1	Isotope/Element	For elements, atomic number and chemical symbol are listed. For nuclides, mass number and chemical symbol are listed. Isomers are indicated by the addition of m, m1, or m2.
2	Isotopic Abundance	in atom percent
3	Half-life	Half-life in decimal notation. μs = microsecond; ms = millisecond; s = second; m = minute; h = hour; d = day; y = year.
4	Thermal Neutron Cross Sections	Cross sections for neutron capture reactions in units of barns (10^{-24} cm^2) or millibarns (mb). Proton, alpha production and fission reactions are designated by σ_p, σ_α, σ_f, respectively. Separate values are listed for isomeric production.
5	Neutron Resonance Integrals	Resonance integrals for neutron capture reactions in barns (10^{-24} cm^2) or millibarns (mb). Proton, alpha production and fission reactions are designated by R.I.$_p$, R.I.$_\alpha$, R.I.$_f$, respectively. Separate values are listed for isomeric production.
6	Neutron Scattering Lengths	Bound coherent scattering lengths for neutron scattering reactions in units of femtometers (fm), which is equal to fermis (10^{-13} cm).
7	Maxwellian Averaged Cross Section	Astrophysical Cross Sections, averaged over a stellar neutron maxwellian spectrum characterized by a thermal energy of 30 keV, expressed in barns (10^{-24} cm^2), millibarns (mb) or microbarns (μb).

General Nuclear Data References

The following references represent the major sources of the nuclear data presented:

Mughabghab, S.F., Divadeenam, M., Holden, N.E.; Neutron Cross Sections, Vol. 1 *Neutron Resonance Parameters and Thermal Cross Sections,* Part A, *Z* = 1-60. Academic Press Inc., New York, New York (1981); Mughabghab, S.F.; Part B, *Z* = 61-100. Academic Press Inc., Orlando, Florida (1984).

Holden, N.E.; *Fifty Years with Nuclear Fission* Conference, Wash., D.C., Gaithersburg, Md. April 26-29, 1989, p. 946. American Nuclear Society, LaGrange Park, Illinois (1989).

Tuli, J.K.; *Nuclear Wallet Cards*, Brookhaven National Laboratory (Jan. 2000).

Holden, N.E.; *Half-lives of Selected Nuclides*, Pure & Applied Chemistry 62, 941 (1990).

Holden, N.E., Hoffman, D.C.; *Spontaneous Fission Half-lives for Ground State Nuclides*, Pure & Applied Chemistry 72, 1525 (2000).

Koester, L., Rauch, H., Seymann, E.; *Neutron Scattering Lengths: A Survey of Experimental Data and Methods*, Atomic Data Nuclear Data Tables 49, 65 (1991).

Sears, V.F.; *Neutron Scattering Lengths and Cross Sections*, Neutron News 3, (3), 26 (1992).

Bao, Z.Y., Beer, H., Käppeler, F., Voss, F., Wisshak, K., Raucher,T.; *Neutron Cross Sections for Nucleo-synthesis Studies*, Atomic Data Nuclear Data Tables 76, 70 (2000).

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	σ (30 keV) Maxw. Avg. (barns)
$_1$H			0.332(2)	0.149(1)	-3.739(1)	
^{1}H	99.9885(70)	>2.8×10^{23} y	0.332(2)	0.149(1)	- 3.741(1)	0.25(2) mb*
^{2}H	0.0115(70)		0.51(1)mb	0.23(2) mb	6.671(4)	2.1(4) μb
^{3}H		12.33 y	< 6. μb		4.79(3)	
$_2$He			< 0.05		3.26(3)	
^{3}He	0.000134(3)		$\sigma_p = 5.33(1)\times10^3$	$RI_p = 2.39(1)\times10^3$	5.74(7)	
			0.05(1) mb			8.(1) μb*
^{4}He	99.999867(3)				3.26(3)	
$_3$Li			71.(2)	32.(1)	- 1.90(2)	
^{6}Li	7.59(4)		$\sigma_t = 9.4(1)\times10^2$	RI_t = 422.(4)	2.0(1)	$\sigma_t \approx 1.$

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	(30 keV) Maxw. Avg. (barns)
			39.(5) mb	17.(2) mb		0.06(1) mb*
^{7}Li	92.41(4)		45.(5) mb	20.(2) mb	- 2.22(2)	42.(3) b
^{8}Li		0.84 s				< ≈ 5.5 b
$_{4}$Be			8.8(4) mb	3.9(2) mb	7.79(1)	
^{7}Be		53.28 d	$_{p}$ = 3.9(1)10^{4}	RI$_{p}$ = 1.75(5)10^{4}		$_{p}$ = 16(4)*
			$_{}$ ≈ 0.1			
^{9}Be	100.		8.8(4) mb	3.9(2) mb	7.79(1)	
^{10}Be		1.5210^{6} y	<1. mb			
$_{5}$B			7.6(1)10^{2}	3.4(1)10^{2}	5.30(4)	
^{10}B	19.9(7)		$_{}$ = 38.4(1)10^{2}	RI$_{}$ = 17.3(1)10^{2}	- 0.1(3)	
			0.3(1)	0.13(4)		
			$_{p}$ = 7.(1) mb			
			$_{t}$ = 8.(2) mb			
^{11}B	80.1(7)		5.(3) mb	2.(1) mb	6.65(4)	
$_{6}$C			3.5(1) mb	1.6(1) mb	6.646(1)	
^{12}C	98.93(8)		3.5(1) mb	1.6(1) mb	6.651(2)	16.(1) b*
^{13}C	1.07(8)		1.4(1) mb	1.7(2) mb	6.19(9)	0.021(4) mb
^{14}C		5715. y	<1.4 b			3.(1) b*
$_{7}$N			2.00(6)	0.90(3)	9.36(2)	
^{14}N	99.636(20)		$_{p}$ = 1.93(5)	RI$_{p}$ = 0.87(3)	9.37(2)	$_{p}$ = 1.8(2) mb*
			0.080(1)	0.034(1)		0.04(1) mb
^{15}N	0.364(20)		0.04(1) mb	0.11(3) mb	6.44(3)	6.(1) b*
$_{8}$O			0.29(1) mb	0.40(4) mb	5.805(4)	
^{16}O	99.757(16)		0.19(1) mb	0.36(4) mb	5.805(5)	34.(4) b
^{17}O	0.038(1)		$_{}$ = 0.257(10)	0.11(1)	5.8(2)	$_{}$ = 3.9(5) mb*
			0.54(7) mb	0.39(5) mb		
^{18}O	0.205(14)		0.16(1) mb	0.81(4) mb	5.84(7)	9.(1) b*
$_{9}$F			9.5(1) mb	21.(3) mb	5.65(1)	6.(1) mb
^{19}F	100.		9.5(1) mb	21.(3) mb	5.65(1)	6.(1) mb
$_{10}$Ne			42.(5) mb	19.(3) mb	4.566(6)	
^{20}Ne	90.48(3)		39.(5) mb	18.(3) mb	4.631(6)	0.12(1) mb
^{21}Ne	0.27(1)		0.7(1)	0.31(5)	6.7(2)	≈ 1.5 mb
			$_{}$ = 0.18(9) mb			
^{22}Ne	9.25(3)		51.(5) mb	23.(3) mb	3.87(1)	58.(4) b*
$_{11}$Na			0.53(2)	0.32(2)	3.63(2)	2.1(2) mb
^{22}Na		2.605 y	$_{p}$ = 2.8(3)10^{4}	RI$_{p}$< 2.10^{5}		
			$_{}$ = 2.6(4)10^{2}	RI$_{}$ = 1.2(2) x 10^{2}		
^{23}Na	100.		$_{m}$ = 0.43(3)	RI$_{m}$ = 0.30(6)	3.63(2)	2.1(2) mb
$_{12}$Mg			66.(6) mb	38.(5) mb	5.375(4)	
^{24}Mg	78.99(4)		0.053(6)	32.(4) mb	5.7(2)	3.3(4) mb
^{25}Mg	10.00(1)		0.20(1)	98.(15) mb	3.6(2)	6.4(4) mb
^{26}Mg	11.01(3)		0.038(1)	25.(2) mb	4.9(2)	0.13(1) mb*
^{27}Mg		9.45 m	0.07(2)	0.03(1)		
$_{13}$Al			0.230(2)	0.17(1)	3.45(1)	
^{26}Al		7.110^{5} y	$_{p}$ = 1.97(10)			0.14(2)
			$_{}$ = 0.34(1)			
^{27}Al	100.		0.230(2)	0.17(1)	3.45(1)	2.9(3) mb
$_{14}$Si			0.166(9)	0.12(2)	4.15(1)	
^{28}Si	92.223(19)		0.17(1)	0.11(2)	4.11(1)	2.9(3) mb
^{29}Si	4.685(8)		0.12(1)	0.08(2)	4.7(1)	7.9(9) mb
^{30}Si	3.092(11)		0.107(3)	0.62(6)	4.61(1)	3.2(3) mb*
^{31}Si		2.62 h	73.(6) mb	33.(3) mb		
^{32}Si		1.610^{2} y	< 0.5			
$_{15}$P			0.17(1)	0.08(1)	5.13(1)	
^{31}P	100.		0.17(1)	0.08(1)	5.13(1)	1.7(1) mb
$_{16}$S			0.54(2)	0.24(2)	2.847(1)	
^{32}S	94.93(31)		0.55(5)	0.25(2)	2.804(2)	4.1(2) mb
			$_{}$ < 0.5 mb			

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	(30 keV) Maxw. Avg. (barns)
^{33}S	0.76(2)		0.46(3)	0.21(2)	4.7(2)	7.4(15) mb
			σ_γ = 0.12(1)	RI_γ = 0.05(1)		σ_γ = 0.18(1)
			σ_p = 2. mb			
^{34}S	4.29(28)		0.25(1)	0.13	3.48(3)	0.23(1) mb
^{36}S	0.02(1)		0.24(2)	0.26(3)		0.17(1) mb*
$_{17}$Cl			33.6(3)	15.(2)	9.58(1)	
^{35}Cl	75.78(4)		43.7(4)	20.(2)	11.7(1)	9.4(3) mb
			σ_p = 0.44(1)	RI_p = 0.2		σ_p = 1.7(2) mb*
			$\sigma_\gamma \approx$ 0.08 mb			
^{36}Cl		3.01×10^5 y	σ_p = 46.(2) mb	RI_p = 0.02		σ_p = 91.(8) mb
			<10.			
			σ_γ = 0.59(7) mb			σ_γ = 0.9(2) mb
^{37}Cl	24.22(4)		(0.05 + 0.38)	(0.04+0.26)	3.1(1)	2.0(2) mb
$_{18}$Ar			0.66(3)	0.42(5)	1.91(1)	
^{36}Ar	0.3365(30)		5.(1)	2.(1)	24.9(1)	
			σ_γ = 5.4(3) mb			
			σ_p < 1.5 mb			
^{37}Ar		35.0 d	σ_γ = 1.08(8)×10^3	RI_γ = 900.		$\sigma_\gamma \approx$ 1.3
			σ_p = 37.(4)	RI_p = 31.		$\sigma_p \approx$ 0.04
^{38}Ar	0.0632(5)		0.8(2)	0.4(1)	3.5(35)	
^{39}Ar		268. y	6.(2)×10^2			
			σ_γ <0.29			
^{40}Ar	99.6003(30)		0.64(3)	0.41(5)	1.83(1)	2.5(3) mb
^{41}Ar		1.82 h	0.5(1)	0.2(1)		
$_{19}$K			2.1(1)	1.0(1)	3.67(2)	
^{39}K	93.2581(44)		2.1(2)	0.9(1)	3.74(2)	11.8(4) mb
			σ_γ = 4.3(5) mb			
			σ_p < 0.05 mb			
^{40}K	0.0117(1)	1.26×10^9 y	30.(8)	13.(4)		σ_p = 7.(1) mb
			σ_p = 4.4(4)	2.0(2)		σ_γ = 40.(6) mb
			σ_γ = 0.42(8)			
^{41}K	6.7302(44)		1.46(3)	1.4(2)	2.69(8)	22.(1) mb
$_{20}$Ca			0.43(2)	0.23(2)	4.70(2)	
^{40}Ca	96.941(156)		0.41(3)	0.22(4)	4.80(2)	6.7(7) mb
			σ_γ = 0.13(4) mb			
^{41}Ca		1.02×10^5 y	≈ 4.			
			σ_γ = 0.18(3)			
			σ_p = 7.(2) mb			
^{42}Ca	0.647(23)		0.65(10)	0.39(4)	3.4(1)	16.(2) mb
^{43}Ca	0.135(10)		6.(1)	3.9(2)	- 1.56(9)	51.(6) mb
^{44}Ca	2.086(110)		0.8(2)	0.56(1)	1.42(6)	9.(1) mb
^{45}Ca		162.7 d	≈ 15.			
^{46}Ca	0.004(3)	>4×10^{15} y	0.70(3)	0.9(1)	3.6(2)	5.3(5) mb*
^{48}Ca	0.187(21)	4.3×10^{19} y	1.0(1)	0.5(1)	0.39(9)	0.8(1) mb*
$_{21}$Sc			27.2(2)	12.(1)	12.3(1)	
^{45}Sc	100.		(10.+17.)	(5.6+6.4)	12.3(1)	69.(5) mb
^{46}Sc		83.81 d	8.(1)	3.6(5)		
$_{22}$Ti			6.1(1)	2.8(2)	- 3.438(2)	
^{44}Ti		60 y	1.1(2)			
			σ_p<0.2			
^{46}Ti	8.25(3)		0.6(2)	0.4(1)	4.93(6)	27.(3) mb
^{47}Ti	7.44(2)		1.6(2)	1.6(2)	3.63(1)	64.(8) mb
^{48}Ti	73.72(3)		7.9(9)	3.6(2)	- 6.09(2)	32.(5) mb
^{49}Ti	5.41(2)		1.9(5)	1.2(2)	1.04(5)	22.(2) mb
^{50}Ti	5.18(2)		0.179(3)	0.12(2)	6.18(8)	3.6(4) mb
$_{23}$V			5.0(2)	2.8(1)	- 0.382(1)	
^{50}V	0.250(4)	1.4×10^{17} y	21.(4)	50.(20)	7.6(6)	
			σ_p = 0.7(4) mb			

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	(30 keV) Maxw. Avg. (barns)
^{51}V	99.750(4)		4.9(1)	2.7(2)	- 0.402(2)	38.(4) mb
$_{24}$Cr			3.0(2)	1.7(1)	3.635(7)	
^{50}Cr	4.345(13)	>1.8×10^{17} y	15.(1)	8.(1)	- 4.5(1)	0.05(1)
^{51}Cr		27.70 d	< 10.			
^{52}Cr	83.789(18)		0.8(1)	0.6(2)	4.91(2)	8.8(4) mb
^{53}Cr	9.501(17)		18.(2)	9.(1)	- 4.2(1)	0.06(1)
^{54}Cr	2.365(7)		0.36(4)	0.25(5)	4.6(1)	7.(2) mb
$_{25}$Mn			13.3(1)	14.0(3)	- 3.75(2)	
^{53}Mn		3.7×10^{6} y	70.(10)	32.(5)		
^{54}Mn		312.1 d	< 10.			
^{55}Mn	100.		13.3(1)	14.0(3)	- 3.75(2)	40.(3) mb
$_{26}$Fe			2.7(1)	1.4(2)	9.45(2)	
^{54}Fe	5.845(35)		2.3(2)	1.3(2)	4.2(1)	29.(2) mb
			σ_{γ} = 10. b	RI$_{\gamma}$ = 1.1(1) mb		
^{55}Fe		2.73 y	13.(2)	6.(1)		
			σ_{γ} = 0.01			
^{56}Fe	91.754(36)		2.8(3)	1.4(2)	9.93(3)	11.7(5) mb
^{57}Fe	2.119(10)		1.4(2)	0.8(4)	2.3(1)	40.(4) mb
^{58}Fe	0.282(4)		1.3(1)	1.3(2)	15.(7)	12.(1) mb
^{59}Fe		44.51 d	13.(3)	6.(1)		
$_{27}$Co			37.19(8)	74.(2)	2.49(2)	
^{58m}Co		9.1 h	1.4(1)×10^{5}	2.5(10)×10^{5}		
^{58}Co		70.88 d	1.9(2)×10^{3}	7.(1)×10^{3}		
^{59}Co	100.		(20.7+16.5)	(39.+35.)	2.49(2)	38.(4) mb
^{60m}Co		10.47 m	58.(3)	230.(50)		
^{60}Co		5.271 y	2.0(2)	4.3(10)		
$_{28}$Ni			4.5(2)	2.3(2)	10.3(1)	
^{58}Ni	68.0769(89)	>4×10^{19} y	4.6(4)	2.3(2)	14.4(1)	41.(2) mb
			σ_{γ} < 0.03 mb			
^{59}Ni		≈ 7.6×10^{4} y	σ_{abs} = 92.(4)	RI$_{abs}$ = 1.4(1)×10^{2}		
			σ_{γ} = 14.(2)			
			σ_{p} = 2.(1)			
^{60}Ni	26.2231(77)		2.9(3)	1.5(2)	2.8(1)	25.(1) mb
^{61}Ni	1.1399(6)		2.5(5)	1.5(4)	7.60(6)	82.(8) mb
			σ_{γ} = 0.03 mb			
^{62}Ni	3.6345(17)		15.(1)	6.8(3)	- 8.7(2)	13.(4) mb
^{63}Ni		100. y	20.(5)	9.(2)		
^{64}Ni	0.9256(9)		1.6(1)	1.2(2)	- 0.37(7)	9.(1) mb
^{65}Ni		2.517 h	22.(2)	10.(1)		
$_{29}$Cu			3.8(1)	4.1(4)	7.718(4)	
^{63}Cu	69.15(15)		4.5(2)	5.(1)	6.43(15)	0.09(1)
^{64}Cu		12.701 h	≈ 270.			
^{65}Cu	30.85(15)		2.17(3)	2.2(1)	10.61(19)	41.(5) mb
^{66}Cu		5.09 m	1.4(1)×10^{2}	60.(20)		
$_{30}$Zn			1.1(2)	2.8(4)	5.680(5)	
^{64}Zn	48.27(32)	>2.3×10^{18} y	0.74(5)	1.4(3)	5.23(4)	59.(5) mb
			σ_{p} < 12. b			
			σ_{γ} = 11.(3) b			
^{65}Zn		243.8 d	66.(8)	30.(4)		
			σ_{γ} = 2.0(2)			
^{66}Zn	27.977(77)		0.9(3)	1.8(2)	5.98(5)	35.(3) mb
			σ_{γ} < 0.02 mb			
^{67}Zn	4.102(21)		6.9(1.4)	25.(5)	7.58(8)	0.15(2)
			σ_{γ} = 0.4 mb			
^{68}Zn	19.02(12)		(0.072 + 0.8)	(0.2 + 2.9)	6.04(3)	19.(2) mb
			σ_{γ} <0.02 mb			σ_{m} = 3.(1) mb
^{70}Zn	0.631(9)		(8.1+83.) mb	0.9(2)		0.02(1)
$_{31}$Ga			2.9(1)	22.(3)	7.288(2)	

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	□ (30 keV) Maxw. Avg. (barns)
^{69}Ga	60.108(9)		1.68(7)	16.(2)	7.88(4)	0.14(1)
^{71}Ga	39.892(9)	>2.4□10^{26} y	4.7(2)	31.(3)	6.40(3)	0.12(1)
			□$_m$ = 0.15(5)			
$_{32}$Ge			2.2(1)	6.(2)	8.19(2)	
^{68}Ge		270.8 d	1.0(5)			
^{70}Ge	20.370(89)		(0.3 + 2.7)	2.3(1)	10.0(1)	88.(5) mb
^{72}Ge	27.380(60)		0.9(2)	0.8(3)	8.5(1)	0.07(2)
^{73}Ge	7.759(78)	>1.8□10^{23} y	15.(1)	66.(20)	5.02(4)	0.3(1)
^{74}Ge	36.656(80)		(0.14 + 0.28)	(0.4+0.5)	7.6(1)	53.(7) mb
^{76}Ge	7.835(81)	1.6□10^{21} y	(0.09 + 0.06)	(1.3+0.6)	8.2(15)	0.03(2)
$_{33}$As			4.0(4)	61.(5)	6.58(1)	
^{75}As	100.		4.0(4)	61.(5)	6.58(1)	0.57(4)
$_{34}$Se			12.(1)	14.(3)	7.970(9)	
^{74}Se	0.89(4)		50.(2)	520(50)	0.8(3)	0.2(1)
^{75}Se		119.78 d	3.3(10)□10^2			
^{76}Se	9.37(29)		(22. + 63.)	(9.+31.)	12.2(1)	0.16(1)
^{77}Se	7.63(16)		42.(4)	30.(5)	8.25(8)	0.3(1)
			□□ = 0.97(3) □b			
^{78}Se	23.77(28)		□$_m$ = 0.38(2)	RI$_m$ = 4.3(4)	8.24(9)	0.1
^{80}Se	49.61(41)		(0.05+0.54)	(0.15+0.85)	7.48(3)	42.(3) mb
^{82}Se	8.73(22)	≈ 1□10^{20} y	(39.+ 5.2) mb	39.(4) mb	6.34(8)	0.04(2)
$_{35}$Br			6.8(2)	92.(8)	6.79(2)	
^{76}Br		16.0 h	224.(42)			
^{79}Br	50.69(7)		(2.5+8.3)	(36.+96.)	6.79(7)	0.63(4)
						□$_m$ = 0.08(1)
^{81}Br	49.31(7)		(2.4+0.24)	51.(5)	6.78(7)	0.31(2)
$_{36}$Kr			24.(1)	39.(6)	7.81(2)	
^{78}Kr	0.353(3)	>2.3□10^{20} y	(0.17+6.)	20.(1)		(0.11+0.19)
^{80}Kr	2.286(10)		(4.6+7.)	57.(6)		(0.09+0.18)
^{82}Kr	11.593(3)		(14.+7.)	130.(13)		90.(6) mb
^{83}Kr	11.500(19)		183.(30)	183.(20)		0.24(2)
^{84}Kr	56.987(15)		(□$_m$+ □$_g$) = 0.11	2.4(3)		(16.+33.) mb
			□$_m$ = 0.09			
^{85}Kr		10.73 y	1.7(2)	1.8(10)		0.07(2)
^{86}Kr	17.279(41)		3.(2) mb	≈ 1. mb	8.1(3)	3.2(4) mb
$_{37}$Rb			0.39(4)	6.(3)	7.08(2)	
^{84}Rb		32.9 d	□$_p$ = 12.(2)			
^{85}Rb	72.17(2)		(0.06+0.38)	(0.7+7.)	7.0(1)	0.24(1)
^{86}Rb		18.65 d	<20.			
^{87}Rb	27.83(2)	4.88□10^{10} y	0.10(1)	2.3(4)	7.3(1)	16.(1) mb
^{88}Rb		17.7 m	1.2(3)	0.5(1)		
$_{38}$Sr			1.2(1)	10.(1)	7.02(2)	
^{84}Sr	0.56(1)		(0.6+0.2)	(9.+1.)		0.4(1)
^{86}Sr	9.86(1)		□$_m$ = 0.81(4)	RI$_m$ = 4.(1)	5.68(5)	(48.+22.) mb
^{87}Sr	7.00(1)		16.(3)	118.(30)	7.41(7)	97.(5) mb
^{88}Sr	82.58(1)		5.8(4) mb	0.07(3)	7.16(6)	6.0(2) mb
^{89}Sr		50.52 d	0.42(4)	0.2		
^{90}Sr		29.1 y	10.(1) mb	0.10(2)		
$_{39}$Y			1.25(5)	1.0(1)	7.75(2)	
^{89}Y	100.		(0.001+1.25)	(0.006+1.0)	7.75(2)	19.(1) mb
^{90}Y		2.67 d	<6.5			
^{91}Y		58.5 d	1.4(3)	0.6(1)		
$_{40}$Zr			0.19(1)	0.95(9)	7.16(3)	
			□□ <0.1 mb			
^{90}Zr	51.45(40)		≈ 0.014	0.2(1)	6.4(1)	21.(2) mb
^{91}Zr	11.22(5)		1.2(3)	5.(2)	8.8(1)	60.(8) mb
^{92}Zr	17.15(8)		0.2(1)	0.6(2)	7.5(2)	33.(4) mb
^{93}Zr		1.5□10^6 y	<4.	16.(5)		0.10(1)

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	σ (30 keV) Maxw. Avg. (barns)
^{94}Zr	17.38(28)	$>10^{17}$ y	0.049(6)	0.25(3)	8.3(2)	26.(1) mb
^{96}Zr	2.80(9)	$>1.7\times10^{18}$ y	0.020(3)	5.0(5)	5.5(1)	11.(1) mb
$_{41}$Nb			1.11(1)	8.5(6)	7.14(3)	
			σ_i <0.1 mb			
^{93}Nb	100.		1.1	(6.3+2.2)	7.14(3)	266.(5) mb
			σ_m = 0.86			
^{94}Nb		2.4×10^{4} y	(σ_m+ σ_g) = 15.(1)	126.(13)		
			σ_m = 0.6(1)			
^{95}Nb		34.97 d	<7.	<200.		
$_{42}$Mo			2.5(1)	26.(5)	6.72(2)	
			σ_i <0.1 mb			
^{92}Mo	14.77(31)	$>3\times10^{17}$ y	0.06	≈ 0.8	6.93(8)	0.07(1)
			σ_m = 0.2 b			
^{94}Mo	9.226(99)		0.02	≈ 0.8	6.82(7)	0.10(2)
^{95}Mo	15.900(85)		13.4(3)	109.(5)	6.93(6)	0.29(1)
			σ_i = 30.(4) b			
^{96}Mo	16.674(12)		0.5	17.(3)	6.22(6)	0.11(1)
^{97}Mo	9.560(50)		2.5(2)	14.(3)	7.26(8)	0.34(1)
			σ_i = 0.4(2) b			
^{98}Mo	24.20(25)		0.14(1)	7.2(7)	6.60(7)	0.10(1)
^{100}Mo	9.67(20)	$\approx 1\times10^{19}$ y	0.19(1)	3.6(3)	6.75(7)	0.11(1)
$_{43}$Tc						
^{98}Tc		$\approx 6.6\times10^{6}$ y	σ_m = 0.9(2)			
^{99}Tc		2.13×10^{5} y	23.(2)	$4.0(4)\times10^{2}$	6.8(3)	0.93(5)
$_{44}$Ru			2.6 (1)	48.(5)	7.03(3)	
^{96}Ru	5.54(14)	$>3.1\times10^{16}$ y	0.23(4)	7.(2)		0.21(1)
^{98}Ru	1.87(3)		< 8.			0.3(1)
^{99}Ru	12.76(14)		4.(1)	195.(20)		1.2(3)
^{100}Ru	12.60(7)		5.8(6)	11.(2)		0.21(1)
^{101}Ru	17.06(2)		5.(1)	$1.1(3)\times10^{2}$		1.00(4)
			σ_i <0.15 b			
^{102}Ru	31.55(14)		1.2(1)	4.3(5)		0.15(1)
^{103}Ru		39.27 d	<20.	≈ 30.		
^{104}Ru	18.62(27)		0.49(2)	6.(2)		0.15(1)
^{105}Ru		4.44 h	0.29(3)	0.13(1)		
^{106}Ru		1.020 y	0.15(4)	2.0(6)		
$_{45}$Rh			145.(2)	$1.2(1)\times10^{3}$	5.88(4)	
^{103}Rh	100.		(11.+ 134.)	$(0.08+1.1)\times10^{3}$	5.88(4)	0.81(1)
^{104m}Rh		4.36 m	800.(100)			
^{104}Rh		42.3 s	40.(30)			
^{105}Rh		35.4 h	$1.1(3)\times10^{4}$	$1.7(4)\times10^{4}$		
$_{46}$Pd			7.(1)	82.(8)	5.91(6)	
^{102}Pd	1.02(1)		3.2(10)	10.(2)		0.3(1)
^{104}Pd	11.14(8)			16.(2)		0.29(3)
^{105}Pd	22.33(8)		22.(2)	60.(20)	5.5(3)	1.20(6)
			σ_i = 0.5(2) b			
^{106}Pd	27.33(3)		(0.013+0.28)	(0.2+5.5)	6.4(4)	0.25(3)
^{107}Pd		6.5×10^{6} y	1.8(2)	108.(4)		1.34(6)
^{108}Pd	26.46(9)		(0.19+8.5)	(2.+240.)	4.1(3)	0.20(2)
^{110}Pd	11.72(9)		(0.033+0.7)	(0.7+8.)		0.15(2)
$_{47}$Ag			62.(1)	767.(60)	5.922(7)	
^{107}Ag	51.839(8)		(1.+35.)	(3.+105.)	7.56(1)	0.80(3)
^{109}Ag	48.161(8)		(4.1 + 87.)	$(0.7+14.1)\times10^{2}$	4.17(1)	0.79(3)
^{110m}Ag		249.8 d	82.(11)	20.(4)		
^{111}Ag		7.47 d	3.(2)	105.(20)		
$_{48}$Cd			$2.52(5)\times10^{3}$	73.(8)	4.87(5)	
^{106}Cd	1.25(6)	$>2.6\times10^{17}$ y	0.20(3)	4.(1)		0.30(2)
^{108}Cd	0.89(3)	$>4.1\times10^{17}$ y	1.	14.(3)	5.4(1)	0.20(1)

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	(30 keV) Maxw. Avg. (barns)
^{109}Cd		462.0 d	≈ 180.	6.7(12)×10^3		
			σ_a <0.05			
^{110}Cd	12.49(18)		(0.06+11.)	(6.+34.)	5.9(1)	(0.01+0.22)
^{111}Cd	12.80(12)		3.5(20)	51.(6)	6.5(1)	0.75(1)
^{112}Cd	24.13(21)		(0.012+2.2)	15.	6.4(1)	0.19(1)
^{113}Cd	12.22(12)	7.7×10^{15} y	2.06(4)×10^4	390.(40)	- 8.0(2)	0.67(1)
			σ_a <1. b			
^{114}Cd	28.73(42)		(0.04+0.29)	16.(7)	7.5(1)	(0.01+0.12)
^{116}Cd	7.49(18)	3.8×10^{19} y	(26.+52.) mb	1.2	6.3(1)	(12.+47.) mb
$_{49}$In			197.(4)	3.3(2)×10^3	4.07(2)	
^{113}In	4.29(5)		(3.1+5.0+3.9)	(220.+90.)	5.39(6)	(0.48+0.31)
^{115}In	95.71(5)	4.4×10^{14} y	(88.+73.+44.)	(1.5+1.2+0.7)×10^3	4.01(2)	(0.69+0.02)
$_{50}$Sn			0.61(3)	8.(2)	6.225(2)	
^{112}Sn	0.97(1)		(0.15+0.40)	(8.+19.)		0.21(1)
^{113}Sn		115.1 d	≈ 9.	210.(50)		
^{114}Sn	0.66(1)		≈ 0.12	5.(1)	6.2(3)	134.(3) mb
^{115}Sn	0.34(1)		σ_a = 0.06 mb	29.(6)		0.34(1)
^{116}Sn	14.54(9)		(0.006+0.14)	(0.5+11.)	5.93(5)	91.(2) mb
^{117}Sn	7.68(7)		1.1(1)	16.(5)	6.48(5)	319.(7) mb
^{118}Sn	24.22(9)		σ_m = 4. mb	4.7(5)	6.07(5)	62.(1) mb
^{119}Sn	8.59(4)		2.(1)	2.9(5)	6.12(5)	0.18(1)
^{120}Sn	32.58(9)		(0.001+0.13)	1.2(3)	6.49(5)	(0.5+36.) mb
^{122}Sn	4.63(3)		(0.15+0.001)	0.81(4)	5.74(5)	(18.+4.) mb
^{124}Sn	5.79(5)	>2.2×10^{18} y	(0.13+0.004)	(8.0+0.08)	5.97(5)	12.(2) mb
$_{51}$Sb			5.2(2)	169.(20)	5.57(3)	
^{121}Sb	57.21(5)		(0.4+5.8)	(13.+192.)	5.71(6)	0.53(2)
^{123}Sb	42.79(5)		(0.02+0.04+4.0)	(1.+119.)	5.38(7)	0.30(1)
^{124}Sb		60.20 d	17.(3)	≈ 8.		
$_{52}$Te			4.2(1)	47.(3)	5.80(3)	
^{120}Te	0.09(1)		(1.+5.)	≈ 1.	5.3(5)	0.4(1)
^{122}Te	2.55(12)		(0.4+3.)	(5.+75.)	3.8(2)	295.(3) mb
^{123}Te	0.89(3)	>5.3×10^{16} y	370.(40)	4.5(3)×10^3	- 0.05	0.83(1)
			σ_a = 0.05 mb			
^{124}Te	4.74(14)		(1.+6.)	(1.4+4.)	8.0(1)	155.(2) mb
^{125}Te	7.07(15)		1.1(2)	21.(4)	5.02(8)	431.(4) mb
^{126}Te	18.84(25)		(0.12+0.8)	(0.6+7.4)	5.56(7)	(28.+53.) mb
^{128}Te	31.74(8)	2.2×10^{24} y	(0.03+0.2)	(0.2+1.6)	5.89(7)	(3.+41.) mb
^{130}Te	34.08(62)	8.×10^{20} y	(0.01+0.19)	(0.03+0.3)	6.02(7)	(4.+11.) mb
$_{53}$I			6.2(1)	1.5(1)×10^2	5.28(2)	
^{125}I		59.4 d	900.(100)	1.4(2)×10^4		
^{127}I	100.		6.2(1)	1.5(1)×10^2	5.28(2)	0.64(3)
^{128}I		25.00 m	22.(4)	≈ 10.		
^{129}I		1.7×10^7 y	(20.7+10.3)	36.(4)		0.44(2)
^{130}I		12.36 h	18.(3)	≈ 8.		
^{131}I		8.021 d	≈ 0.7	8.(4)		
$_{54}$Xe			25.(1)	263.(50)	4.92(3)	
^{124}Xe	0.0953(27)	>10^{17} y	(28.+137.)	(0.6+3.0)×10^3		(0.13+0.51)
^{125}Xe		17.1 h	σ_a < 0.03			
^{126}Xe	0.0890(14)		(0.45+3.)	(8.+52.)		(0.04+0.32)
^{127}Xe		36.34 d	σ_a ≤ 0.01			
^{128}Xe	1.910(22)		σ_m = 0.48	RI_m = 38.(10)		0.26(1)
^{129}Xe	26.40(18)		22.(5)	250.(50)		0.62(2)
^{130}Xe	4.071(53)		σ_m = 0.45	RI_m = 16.(4)		0.132(3)
^{131}Xe	21.233(62)		90.(10)	9.(1)×10^2		0.45(8)
^{132}Xe	26.9087(680)		(0.05+0.4)	(0.9+3.7)		(5.+60.) mb
^{133}Xe		5.243 d	190.(90)			
^{134}Xe	10.436(29)	>1.1×10^{16} y	(0.003 + 0.26)	0.40(4)		20.(2) mb
^{135}Xe		9.10 h	2.65(11)×10^6	7.6(5)×10^3		

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	(30 keV) Maxw. Avg. (barns)
^{136}Xe	8.858(33)	>8×10^{20} y	0.26(2)	0.7(2)		0.9(1) mb
$_{55}$Cs			30.4(8)	422.(50)	5.42(2)	
^{132}Cs		6.48 d	σ_a < 0.15			
^{133}Cs	100.		(2.7+27.3)	(32.+360.)	5.42(2)	(0.04+0.47)
^{134}Cs		2.065 y	140.(10)	54.(9)		
^{135}Cs		2.3×10^{6} y	8.3(3)	38.(3)		
^{137}Cs		30.2 y	(0.20+0.07)	0.36(7)		
$_{56}$Ba			1.3(2)	10.(2)	5.07(3)	
^{130}Ba	0.106(1)	2.2×10^{21} y	(1.+8.)	(25.+200.)	- 3.6(6)	0.76(11)
^{132}Ba	0.101(1)	1.3×10^{21} y	(0.84+9.7)	(4.7+24.)	7.8(3)	0.6(1)
^{133}Ba		10.53 y	4.(1)	85.(30)		
^{134}Ba	2.417(18)		(0.1+1.3)	(5.6+18.)	5.7(1)	0.18(1)
^{135}Ba	6.592(12)		(0.014+5.8)	(0.47+131.)	4.7(1)	0.46(2)
^{136}Ba	7.854(24)		(0.010+0.44)	(0.1+1.5)	4.91(8)	61.(2) mb
^{137}Ba	11.232(24)		5.(1)	4.(1)	6.8(1)	76.(3) mb
^{138}Ba	71.698(42)		0.41(2)	0.4(1)	4.84(8)	4.0(2) mb
^{139}Ba		1.396 h	5.(1)	2.2(5)		
^{140}Ba		12.75 d	1.6(3)	14.(1)		
$_{57}$La			9.2(2)	12.(1)	8.24(4)	
^{138}La	0.090(1)	1.06×10^{11} y	57.(6)	4.1(9)×10^{2}		
^{139}La	99.910(1)		9.2(2)	12.(1)	8.24(4)	38.(3) mb
^{140}La		1.678 d	2.7(3)	69.(4)		
$_{58}$Ce			0.64(4)	0.71(6)	4.84(2)	
^{136}Ce	0.185(2)		(1.0+6.5)	58.(12)	5.80(9)	(0.028+0.3)
^{138}Ce	0.251(2)		(0.025+1.0)	(1.5+5.2)	6.70(9)	179.(5) mb
^{140}Ce	88.450(51)		0.58(4)	0.50(5)	4.84(9)	11.0(4) mb
^{141}Ce		32.50 d	29.(3)	13.(2)		
^{142}Ce	11.114(51)	>1.6×10^{17} y	0.97(3)	1.3(3)	4.75(9)	28.(1) mb
^{143}Ce		1.38 d	6.1(7)	2.7(3)		
^{144}Ce		284.6 d	1.0(1)	2.6(3)		
$_{59}$Pr			11.5(4)	14.(3)	4.58(5)	
^{141}Pr	100.		(4.+7.5)	14.(3)	4.58(5)	111.(2) mb
^{142}Pr		19.12 h	20.(3)	9.(1)		
^{143}Pr		13.57 d	90.(10)	190.(25)		
$_{60}$Nd			51.(2)	49.(5)	7.69(5)	
^{142}Nd	27.2(5)		19.(1)	34.(11)	7.7(3)	35.(1) mb
^{143}Nd	12.2(2)		330.(10)	128.(30)		0.24(1)
			σ_a = 17. mb			
^{144}Nd	23.8(3)	2.1×10^{15} y	3.6(3)	3.9(5)	2.8(3)	81.(2) mb
^{145}Nd	8.3(1)		47.(6)	260.(40)		0.42(1)
			σ_a = 12. b			
^{146}Nd	17.2(3)		1.5(2)	3.0(4)	8.7(2)	91.(1) mb
^{147}Nd		10.98 d	440.(150)	200.		
^{148}Nd	5.7(1)		2.4(1)	13.(2)	5.7(3)	147.(2) mb
^{150}Nd	5.6(2)	≈ 1×10^{19} y	1.0(1)	14.(2)	5.3(2)	0.16(1)
$_{61}$Pm						
^{146}Pm		5.53 y	8.4(1.7)×10^{3}			
^{147}Pm		2.623 y	(84.+96.)	(1000.+1280.)	12.6(4)	2.(1)
^{148m}Pm		41.3 d	10600.(800)			
^{148}Pm		5.37 d	≈ 10^{3}	2.6(2.4)×10^{3}		
^{149}Pm		2.212 d	1400.(200)			
^{151}Pm		1.183 d	≈ 150.			
$_{62}$Sm			5.6(1)×10^{3}	1.4(2)×10^{3}		
^{144}Sm	3.07(7)		1.6(1)	2.4(3)		92.(6) mb
^{145}Sm		340. d	280.(20)	600.(90)		
^{147}Sm	14.99(18)	1.06×10^{11} y	56.(4), σ_a = 0.6 mb	710.(50)	14.(3)	0.97(1)
^{148}Sm	11.24(10)	7×10^{15} y	2.4(6)	27.(14)		241.(2) mb
^{149}Sm	13.82(7)	10^{16} y	4.01(6)×10^{4}, σ_a = 31. mb	3.1(5)×10^{3}		1.82(2)

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	(30 keV) Maxw. Avg. (barns)
^{150}Sm	7.38(1)		102.(5)	290.(30)	14.(3)	422.(4) mb
^{151}Sm		90. y	1.52(3)×10^{4}	3520.(60)		2.(1)
^{152}Sm	26.75(16)		206.(15)	3.0(3)×10^{3}	- 5.0(6)	473.(4) mb
^{153}Sm		1.929 d	420.(180)			
^{154}Sm	22.75(29)		7.5(3)	32.(6)	9.(1)	0.21(1)
$_{63}$Eu			4570.(100)	3.8(5)×10^{3}	5.3(3)	
^{151}Eu	47.81(6)		(4.+3150.+6000.)	(2.+4.)×10^{3}		(1.6+2.2)
			σ_γ = 8.7(3) b			
^{152m1}Eu		9.30 h	6.8(15)×10^{4}	< 10^{5}		
^{152}Eu		13.5 y	1.1(2)×10^{4}	1.6(2)×10^{3}		5.(2)
^{153}Eu	52.19(6)		300.(20), σ_γ <1. b	1.8(4)×10^{3}	8.2(1)	2.8(1)
^{154}Eu		8.59 y	1.5(3)×10^{3}	1.6(2)×10^{3}		4.4(7)
^{155}Eu		4.76 y	3.9(2)×10^{3}	1.6(2)×10^{4}		1.3(1)
$_{64}$Gd			48.8(6)×10^{3}	400.(10)	9.5(2)	
^{148}Gd		75. y	1.40(14)×10^{4}			
^{152}Gd	0.20(1)	1.1×10^{14} y	700.(200), σ_γ <7. mb	700.(200)		1.05(2)
^{153}Gd		240. d	2.(1)×10^{4}, σ_γ = 0.03			
^{154}Gd	2.18(3)		(0.035+60.)	230.(50)		1.03(1)
^{155}Gd	14.80(12)		61.(1)×10^{3}, σ_γ = .08 mb	1540.(100)		2.65(3)
^{156}Gd	20.47(9)		≈ 2.0	104.(15)	6.3(4)	615.(5) mb
^{157}Gd	15.65(2)		2.54(3)×10^{5}, σ_γ <0.05	800.(100)		1.37(2)
^{158}Gd	24.84(7)		2.3(3)	73.(7)	9.(2)	324.(3) mb
^{160}Gd	21.86(19)	>1.9×10^{19} y	1.5(7)	6.(1)	9.15(5)	0.15(2)
^{161}Gd		3.66 m	2.0(6)×10^{4}			
$_{65}$Tb			23.2(5)	420.(50)	7.34(2)	
^{159}Tb	100.		23.2(5)	420.(50)	7.34(2)	1.6(2)
^{160}Tb		72.3 d	570.(110)			
$_{66}$Dy			9.5(2)×10^{2}	1.5(2)×10^{3}	16.9(3)	
^{156}Dy	0.056(3)		33.(3), σ_γ < 9. mb	1000.(100)		1.6(2)
^{158}Dy	0.095(3)		43.(6), σ_γ < 6. mb	120.(10)	6.1(5)	0.8(2)
^{159}Dy		144. d	8.(2)×10^{3}			
^{160}Dy	2.39(18)		60.(10), σ_γ < 0.3 mb	1100.(200)	6.7(4)	0.89(1)
^{161}Dy	18.889(42)		600.(50), σ_γ < 1. b	1100.(100)	10.3(4)	1.96(2)
^{162}Dy	25.475(36)		170.(20)	2755.(300)	- 1.4(5)	446.(4) mb
^{163}Dy	24.896(42)		120.(10), σ_γ < 20. b	1600.(400)	5.0(4)	1.11(1)
^{164}Dy	28.260(54)		(1.7+1.0)×10^{3}	(4.+2.)×10^{2}	49.4(2)	212.(3) mb
^{165m}Dy		1.26 m	2.0(6)×10^{3}			
^{165}Dy		2.33 h	3.5(3)×10^{3}	2.2(3)×10^{4}		
$_{67}$Ho			61.(2)	670.(40)	8.01(8)	
^{163}Ho		4.57×10^{3} y				(0.4+1.7)
^{165}Ho	100.		(3.1+58.), σ_γ < 20. b	(?+670.)	8.01(8)	(0.8+0.5)
^{166m}Ho		1.2×10^{3} y	3.1(8)×10^{3}	10.(3)×10^{3}		
$_{68}$Er			1.5(2)×10^{2}	730.(10)	7.79(2)	
^{162}Er	0.139(5)		19.(3), σ_γ < 11. mb	480.(50)	8.8(2)	1.6(1)
^{164}Er	1.601(3)		13.(3), σ_γ < 1.2 mb	105.(10)	8.2(2)	1.08(5)
^{166}Er	33.503(36)		(3.+14.), σ_γ < 70. b	96.(12)	10.6(2)	0.56(6)
^{167}Er	22.869(9)		6.5(8)×10^{2}, σ_γ = 3. b	2970.(70)	3.0(3)	1.4(2)
^{168}Er	26.978(18)		2.3(3), σ_γ = 0.09 mb	37.(5)	7.4(4)	0.34(4)
^{170}Er	14.910(36)		8.(2)	26.(4)	9.6(5)	0.17(1)
^{171}Er		7.52 h	370.(40)	170.(20)		
$_{69}$Tm			108.(4)	1.5(2)×10^{3}	7.07(3)	
^{169}Tm	100		(8.+100.)	1.5(2)×10^{3}	7.07(3)	1.13(6)
^{170}Tm		128.6 d	100.(20)	460.(50)		
^{171}Tm		1.92 y	≈ 160.	118.(6)		
$_{70}$Yb			52.(10)	1.7(2)×10^{2}	12.43(3)	
^{168}Yb	0.13(1)		2.4(2)×10^{3}, σ_γ < 0.1 mb	2.0(5)×10^{4}	-4.07(2)	0.7(4)
^{169}Yb		32.02 d	3.6(3)×10^{3}	5200.(500)		
^{170}Yb	3.04(15)		12.(2), σ_γ < 10. b	320.(30)	6.8(1)	0.77(1)

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	(30 keV) Maxw. Avg. (barns)
^{171}Yb	14.28(57)		53.(5), σ_a < 1.5 b	315.(30)	9.7(1)	1.21(1)
^{172}Yb	21.83(67)		≈ 1.3, σ_a < 1. b	25.(3)	9.4(1)	0.34(1)
^{173}Yb	16.13(27)		16.(2), σ_a < 1. b	380.(30)	9.56(7)	0.75(1)
^{174}Yb	31.83(92)		(46.+17.), σ_a < 0.02 mb	(13.+16.)	19.3(1)	151.(2) mb
^{176}Yb	12.76(41)		3.1(2), σ_a < 1. b	8.(2)	8.7(1)	116.(2) mb
$_{71}$Lu			78.(7)	8.3(7)×10^2	7.21(3)	
^{175}Lu	97.41(2)		(16.+8.)	(550.+270.)	7.24(3)	(1.04+0.11)
^{176}Lu	2.59(2)	3.73×10^{10} y	(2.+2100.)	(3.+930.)	6.1(2)	1.53(7)
^{177m}Lu		160.7 d	3.2(3)	1.4(2)		
^{177}Lu		6.65 d	1000.(300)			
$_{72}$Hf			106.(3)	19.7(5)×10^2	7.8(1)	
^{174}Hf	0.16(1)	2.0×10^{15} y	600.(50)	400.(50)	11.(1)	0.8(2)
^{176}Hf	5.26(7)		23.(4)	700.(100)	6.6(2)	0.46(2)
^{177}Hf	18.60(9)		(1.+375.), σ_a < 20. b	7170.(200)		1.5(1)
^{178m2}Hf		31. y	$\sigma_{a,m2}$ = 45.(5)	RI_{m2} = 8(1)×10^2		
^{178}Hf	27.28(7)		(54.+32.)	(0.9+1.0)×10^3	5.9(2)	0.31(1)
^{179}Hf	13.62(2)		(0.43+46.)	(6.8+620.)	7.5(2)	(0.01+0.95)
^{180}Hf	35.08(16)		13.0(5), σ_a < 13. b	32.(1)	13.2(3)	179.(5) mb
^{181}Hf		42.4 d	30.(25)			
$_{73}$Ta			20.(1)	650(20.)	6.91(7)	
^{179}Ta		1.8 y	9.3(6)×10^2	1.22(7)×10^3		
^{180m}Ta	0.012(2)	> 1.2×10^{15} y	≈ 560.	1350.(100)		
^{181}Ta	99.988(2)		(0.012 + 20.), σ_a <1. b	(0.4+650.)	6.91(7)	0.77(2)
^{182}Ta		114.43 d	8200.(600)	900.(90)		
$_{74}$W			18.(1)	3.6(3)×10^2	4.86(2)	
^{180}W	0.12(1)	7.4×10^{16} y	≈ 4.	210.(30)		0.54(6)
^{182}W	26.50(16)	8.3×10^{18} y	20.(1)	600.(90)	6.97(4)	274.(8) mb
^{183}W	14.31(4)	1.9×10^{18} y	10.5(3)	340.(50)	6.53(4)	0.52(2)
^{184}W	30.64(2)	4.0×10^{18} y	(0.002 + 2.0)	15.(2)	7.48(6)	0.22(1)
^{185}W		74.8 d	≈ 3.3	300.(50)		
^{186}W	28.43(19)	6.5×10^{18} y	37.(2)	510.(50)	- 0.72(4)	176.(5) mb
^{187}W		23.9 h	70.(10)	2760.(550)		
^{188}W		69.78 h	12.(1)			
$_{75}$Re			90.(4)	8.4(2)×10^2	9.2(3)	
^{185}Re	37.40(2)		(0.33+110.)	1700.(50)	9.0(3)	1.54(6)
^{187}Re	62.60(2)	4.2×10^{10} y	(2.+72.)	(9.+310.)	9.3(3)	1.16(6)
$_{76}$Os			17.(1)	1.5(1)×10^2	10.7(2)	
^{184}Os	0.02(1)	>5.6×10^{13} y	3.3(3)×10^3, σ_a <10. mb	1.4(1)×10^3		0.4(2)
^{186}Os	1.59(3)	2.×10^{15} y	≈ 80., σ_a < 0.1 mb	3.8(9)×10^2	12(2)	0.42(2)
^{187}Os	1.96(2)		2.(1)×10^2, σ_a < 0.1 mb	5.0(7)×10^2		0.90(3)
^{188}Os	13.24(8)		≈ 5., σ_a < 30. b	1.5(2)×10^2	7.6(3)	0.40(2)
^{189}Os	16.15(5)		(0.00026+40.),σ_a<10. b	(0.013+670.)	10.7(3)	1.17(5)
^{190}Os	26.26(2)		(9.+4.), σ_a < 20. b	(22.+8.)	11.0(3)	0.30(5)
^{191}Os		15.4 d	3.8(6)×10^2	1.7(3)×10^2		
^{192}Os	40.78(19)		3.(1), σ_a < 10. b	7.(1)	11.5(4)	0.31(5)
^{193}Os		30.5 h	2.5(5)×10^2	1.1(2)×10^2		
$_{77}$Ir			4.2(1)×10^2	2.8(4)×10^3	10.6(3)	
^{191}Ir	37.3(2)		(0.14+660.+260.)	(1.0+4.2)×10^3		1.35(4)
^{192}Ir		73.83 d	1.4(3)×10^3	4.8(7)×10^3		
^{193}Ir	62.7(2)		(0.04+6.+109.)	1.4(2)×10^3		0.99(7)
^{194}Ir		19.3 h	1.6(3)×10^3	7.(2)×10^2		
$_{78}$Pt			10.(1)	1.3(1)×10^2	9.60(1)	
^{190}Pt	0.014(1)	4.5×10^{11} y	1.5(1)×10^2, σ_a < 8. mb	70.(10)	9.(1)	0.7(2)
^{192}Pt	0.782(7)		(2.0+6.), σ_a < 0.2 mb	115.(20)	9.9(5)	0.6(1)
^{194}Pt	32.967(99)		(0.1+1.1), σ_a < 5. b	(4.+?)	10.55(8)	(0.03+0.34)
^{195}Pt	33.832(10)		28.(1), σ_a < 5. b	365.(50)	8.8(1)	0.9(2)
^{196}Pt	25.242(41)		(0.045+0.55)	7.(2)	9.89(8)	(0.01+0.19)
^{198}Pt	7.163(55)		(0.3+3.1)	(5.+53.)	7.8(1)	(3.+79.) mb

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	(30 keV) Maxw. Avg. (barns)
^{199}Pt		30.8 m	≈ 15.	≈ 7.		
$_{79}$Au			98.7(1)	1.55(3)×10^3	7.63(6)	
^{197}Au	100.		σ_{m+g} = 98.7(1)	RI_{m+g} = 1.55(3)×10^3	7.63(6)	582.(9) mb
			σ_m = 8.(2) mb	RI_m = 0.06(2)		
^{198}Au		2.695 d	26.5(15)×10^3	≈ 4.×10^4		
^{199}Au		3.14 d	≈ 30.			
$_{80}$Hg			3.7(1)×10^2	87.(5)	12.69(2)	
^{196}Hg	0.15(1)	>2.5×10^{18} y	(105.+3000.)	(53.+410.)	30.(1)	0.4(2)
^{198}Hg	9.97(8)		(0.017+2.)	(1.7+70.)		0.17(2)
^{199}Hg	16.87(10)		2.1(2)×10^3	435(20)	16.9(4)	0.37(2)
^{200}Hg	23.10(16)		≈ 1.	2.1(5)		0.12(1)
^{201}Hg	13.18(8)		≈ 8.	30.(3)		0.26(1)
^{202}Hg	29.86(20)		4.9(5)	4.5(2)	11.(1)	74.(6) mb
^{204}Hg	6.87(4)		0.4(1)	0.8(2)		42.(4) mb
$_{81}$Tl			3.3(1)	12.5(8)	8.776(5)	
^{203}Tl	29.524(14)		11.(1), σ_g < 0.3 mb	41.(2)	7.0(2)	124.(8) mb
^{204}Tl		3.78 y	22.(2)	90.(20)		0.14(5)
^{205}Tl	70.476(14)		0.11(2)	0.6(2)	9.52(7)	54.(4) mb
$_{82}$Pb			0.172(2)	0.14(4)	9.402(2)	
^{204}Pb	1.4(1)		0.68(7)	2.0(2)	10.9(1)	90.(6) mb
^{205}Pb		1.51×10^7 y	≈ 5.	≈ 2.		0.06(1)
^{206}Pb	24.1(1)		0.027(1)	0.10(1)	9.23(5)	16.(1) mb
^{207}Pb	22.1(1)		0.61(3)	0.38(1)	9.28(2)	10.(1) mb
^{208}Pb	52.4(1)	>2×10^{19} y	0.23(1) mb, σ_g < 8. b	2.0(2) mb	9.50(3)	0.36(4) mb
^{210}Pb		22.6 y	< 0.5			
$_{83}$Bi			0.034(1)	0.19(2)	8.532(2)	
^{209}Bi	100.		(11.+23.) mb, σ_g<0.3 b	0.19(2)	8.532(2)	2.7(5) mb
^{210m}Bi		3.0×10^6 y	54.(4) mb	0.20(3)		
$_{84}$Po						
^{210}Po		138.4 d	σ_m<0.5 mb, σ_g < 2. mb			
			σ_g<30. mb, σ_f< 0.1			
$_{85}$At						
$_{86}$Rn						
^{220}Rn		55.6 s	<0.2			
^{222}Rn		3.823 d	0.74(5)			
$_{88}$Ra						
^{223}Ra		11.43 d	1.3(2)×10^2, σ_f< 0.7			
^{224}Ra		3.66 d	12.0(5)			
^{226}Ra		1599. y	≈ 13., σ_f< 7. b	280.(50)	10.(1)	
^{228}Ra		5.76 y	36.(5), σ_f< 2.			
$_{89}$Ac						
^{227}Ac		21.77 y	8.8(7)×10^2, σ_f< 0.35 mb	1.5(4)×10^3		
$_{90}$Th			7.4	85.(3)	10.31(3)	
^{227}Th		18.72 d	σ_f = 2.0(2)×10^2			
^{228}Th		1.913 y	1.2(2)×10^2, σ_f<0.3	1014.(400)		
^{229}Th		7.9×10^3 y	≈ 60.	1.0(2)×10^3		
			σ_f = 30.(3)	RI_f = 466.(75)		
^{230}Th		7.54×10^4 y	23.4(5)	1.0(1)×10^3		
			σ_f < 0.5 mb			
^{232}Th	100.	1.40×10^{10} y	7.37(4)	85.(3)	10.31(3)	
			σ_f = 3.(1) b			
			σ_g < 1. b			
^{233}Th		22.3 m	1.5(1)×10^3	4.(1)×10^2		
			σ_f = 15.(2)			
^{234}Th		24.10 d	1.8(5)			
			σ_f < 0.01			

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	(30 keV) Maxw. Avg. (barns)
$_{91}$Pa						
^{230}Pa		17.4 d	1.5(3)×10^3			
^{231}Pa		3.25×10^4 y	2.0(1)×10^2	750.(80)	9.1(3)	
			σ_f = 20.(1) mb	RI$_f$ = 0.05(1)		
^{232}Pa		1.31 d	4.6(10)×10^2	300.(70)		
			σ_f = 1.5(5)×10^3	RI$_f$ = 1.0(1)×10^3		
^{233}Pa		27.0 d	39.(2)	(460.+440.)		
			σ_m = 20.(4)			
			σ_g = 19.(3)			
			σ_f < 0.1			
$_{92}$U			3.4(3); σ_f = 4.2(1)	280.(20),RI$_f$ = 2.0	8.417(5)	
^{230}U		20.8 d	$\sigma_f \approx$ 25.			
^{231}U		4.2 d	$\sigma_f \approx$ 250.			
^{232}U		70. y	73.(2)	280.(15)		
			σ_f = 74.(8)	RI$_f$ = 350.(30)		
^{233}U		1.592×10^5 y	47.(2)	137.(6)	10.1(2)	
			σ_f = 5.3(1)×10^2	RI$_f$ = 760.(17)		
			σ_γ < 0.2 mb			
^{234}U	0.0054(5)	2.455×10^5 y	96.(2)	660.(70)	12.(4)	
			σ_f = 0.07(2)	RI$_f$ = 6.5		
^{235}U	0.7204(6)	7.04×10^8 y	95.(5)	144.(6)	10.47(4)	
			σ_f = 586.(2)	RI$_f$ = 275(5)		
			σ_γ < 0.1 mb			
^{236}U		2.342×10^7 y	5.1(3)	360.(15)		
			σ_f < 1.3 mb	RI$_f$ = 4.38(50)		
^{237}U		6.75 d	≈ 10^2	1200.(200)		
			σ_f < 0.35			
^{238}U	99.2742(10)	4.47×10^9 y	2.7(1)	277.(3)	8.402(5)	
			$\sigma_f \approx$ 3. μb	1.54(15) mb		
			σ_γ = 1.4(5) μb			
^{239}U		23.5 m	22.(2)			
			σ_f = 15.(3)			
$_{93}$Np						
^{234}Np		4.4 d	σ_f = 9.(3)×10^2			
^{235}Np		1.085 y	1.6(1)×10^2			
^{236m}Np		22.5 h	σ_f = 2.7(2)×10^3	7.(4)×10^2		
^{236}Np		1.55×10^5 y	σ_f = 3.0(2)×10^3	1.35(30)×10^3		
^{237}Np		2.14×10^6 y	1.7(1)×10^2	6.5(3)×10^2	10.6(1)	
			σ_f = 20.(1) mb	RI$_f$ = 4.7		
^{238}Np		2.117 d	σ_f = 2.6(3)×10^3	1.4(3)×10^3		
^{239}Np		2.355 d	(32.+19.)			
			σ_f < 1.			
$_{94}$Pu						
^{236}Pu		2.87 y	σ_f = 1.6(3)×10^2	1000.(60)		
^{237}Pu		45.7 d	σ_f = 2.3(3)×10^3			
^{238}Pu		87.7 y	5.1(2)×10^2	1.6(2)×10^2	14.1(5)	
			σ_f = 17.(1)	RI$_f$ = 26.(2)		
^{239}Pu		2.410 x 10^4 y	2.7(1)×10^2	2.0(2)×10^2	7.7(1)	
			σ_f = 752.(3)	3.0(1)×10^2		
			$\sigma_\gamma \leq$ 0.3 mb			
^{240}Pu		6.56×10^3 y	2.9(1)×10^2	8.4(3)×10^3	3.5(1)	
			$\sigma_f \approx$ 59. mb	RI$_f$ = 3.2		
^{241}Pu		14.4 y	3.7(1)×10^2, σ_γ <0.2 mb	1.6(1)×10^2		
			σ_f = 1.01(1)×10^3	5.7(4)×10^2		
^{242}Pu		3.75 x 10^5 y	19.(1)	1.1(1)×10^3	8.1(1)	
			σ_f<0.2	RI$_f$ = 0.23		
^{243}Pu		4.956 h	<100.			
			σ_f = 2.0(2)×10^2			

*Extrapolated value.

Elem. or Isot.	Natural Abundance (%)	Half-Life	Thermal Neut. Cross-Section (barns)	Resonance Integral (barns)	Coh. Scat. Length (fm)	(30 keV) Maxw. Avg. (barns)
^{244}Pu		8.00×10^{7} y	1.7(1)	41.(3)		
^{245}Pu		10.5 h	1.5(3)×10^{2}	220.(40)		
$_{95}$Am						
^{241}Am		432.7 y	(0.6+6.4)×10^{2}	(1.+14.)×10^{2}		
			σ_f = 3.15(10)	14.(1)		
^{242m}Am		141. y	1.7(4)×10^{3}	≈ 200.		
			σ_f = 5.9(3)×10^{3}	RI$_f$ = 1.8(1)×10^{3}		
^{242}Am		16.02 h	σ_f = 2.1(2)×10^{3}	RI$_f$ = < 300.		
			3.3(5)×10^{2}	≈ 1.5×10^{2}		
^{243}Am		7.37×10^{3} y	(75.+5.)	(17.1+1.0)×10^{2}	8.3(2)	
			σ_f = 79.(2) mb	RI$_f$ = 0.056		
^{244m}Am		≈ 26. m	σ_f = 1.6(3)×10^{3}			
^{244}Am		10.1 h	σ_f = 2.2(3)×10^{3}			
$_{96}$Cm						
^{242}Cm		162.8 d	≈ 20.	120.(50)		
			σ_f ≈ 5.			
^{243}Cm		29.1 y	1.3(1)×10^{2}	214.(20)		
			σ_f = 6.2(2)×10^{2}	RI$_f$ = 1.6(1)×10^{3}		
^{244}Cm		18.1 y	15.(1)	640.(50)	9.5(3)	
			σ_f = 1.1(2)	RI$_f$ = 10.8(8)		
^{245}Cm		8.48×10^{3} y	3.5(2)×10^{2}	110.(10)		
			σ_f = 2.1(1)×10^{3}	RI$_f$ = 8.(1)×10^{2}		
^{246}Cm		4.76×10^{3} y	1.2(2)	120.(10)	9.3(2)	
			σ_f = 0.16(7)	13.(2)		
^{247}Cm		1.56×10^{7} y	60.(30)	5.(1)×10^{2}		
			σ_f = 82.(5)	7.3(7)×10^{2}		
^{248}Cm		3.48×10^{5} y	2.6(3)	270.(30)	7.7(2)	
			σ_f = 0.36(7)	13.(2)		
^{249}Cm		64.15 m	≈ 1.6			
^{250}Cm		≈ 9.7×10^{3} y	≈ 80.			
$_{97}$Bk						
^{249}Bk		320. d	7.(1)×10^{2}	9.(1)×10^{2}		
			σ_f ≈ 0.1			
^{250}Bk		3.217 h	σ_f = 1.0(2)×10^{3}			
$_{98}$Cf						
^{249}Cf		351. y	5.0(3)×10^{2}	7.7(4)×10^{2}		
			σ_f = 1.7(1)×10^{3}	RI$_f$ = 2.1(3)×10^{3}		
^{250}Cf		13.1 y	2.0(2)×10^{3}	12.(2)×10^{3}		
			σ_f = 110.(90)	RI$_f$ = 160.(40)		
^{251}Cf		9.0×10^{2} y	2.9(2)×10^{3}	1.6(1)×10^{3}		
			σ_f = 4.5(5)×10^{3}	RI$_f$ = 5.5(3)×10^{3}		
^{252}Cf		2.65 y	20.(2)	43.(3)		
			σ_f = 32.(4)	RI$_f$ = 1.1(3)×10^{2}		
^{253}Cf		17.8 d	18.(2)	8.(1)		
			σ_f = 1.3(2)×10^{3}			
^{254}Cf		60.5 d	4.5(10)	2.		
$_{99}$Es						
^{253}Es		20.47 d	(180.+5.8)	(37.5+1.1)×10^{2}		
^{254m}Es		1.64 d	σ_f = 1.8(1)×10^{3}			
^{254}Es		276. d	28.(3)	18.(2)		
			σ_f = 1.8(2)×10^{3}	RI$_f$ = 1.2(3)×10^{3}		
^{255}Es		40. d	≈ 55.			
$_{100}$Fm						
^{255}Fm		20.1 h	26.(3)	14.(2)		
			σ_f = 3.3(2)×10^{3}			
^{257}Fm		100.5 d	σ_f = 3.0(2)×10^{3}			

*Extrapolated value.

COSMIC RADIATION

A.G. Gregory and R.W. Clay

The Nature of Cosmic Rays

Primary cosmic radiation, in the form of high energy nuclear particles, electrons and photons from outside the solar system and from the Sun, continually bombards our atmosphere. Secondary radiation, resulting from the interaction of the primary cosmic rays with atmospheric gas, is present at sea-level and throughout the atmosphere.

The secondary radiation is collimated by absorption and scattering in the atmosphere and consists of a number of components associated with different particle species. High energy primary particles can produce large numbers of secondary particles forming an extensive air shower. Thus, a number of particles may then be detected simultaneously at sea-level.

Primary particle energies accessible in the vicinity of the earth range from ~10^8 eV to ~10^{20} eV. At the lower energies, the limit is determined by the inability of charged particles to traverse the heliosphere to us through the outward-moving solar wind. The upper energy limit is set by the practicality of building detectors to record particles with the extremely low fluxes found at those energies (J.G. Wilson, 1976; O.C. Allkofer, 1975a).

Primary Cosmic Rays

Primary Particle Energy Spectrum

Figure 1 shows the spectrum of primary particle energies. This includes all particle species. In differential form it is roughly a power law of intensity versus energy with an index of ~ −3. There appears to be a knee (a steepening) at a little above 10^{15} eV and an ankle (a flattening) above ~10^{18} eV. Figure 2 emphasizes the features in the spectrum at the highest energies through multiplying the flux with a strongly rising power law of energy. This figure should be used with caution as errors for the two axes are not now independent.

Data on the high energy cosmic ray spectrum are uncertain largely because of limited event statistics due to the very low flux which might best be measured in particles per square kilometer per century. The highest energy event recorded to 1995 had an energy of 3×10^{20} eV (D.J. Bird et al., 1993).

It is expected that the highest energy cosmic rays will interact with the 2.7 K cosmic microwave background through photoproduction or photodisintegration. These interactions will appreciably reduce the observed flux of cosmic rays with energies above 5×10^{19} eV if they travel further than ~150 million light years. This process is known as the Greisen-Zatsepin-Kuz'min (GZK) cut off (P. Sokolsky, 1989).

At energies below ~10^{13} eV, solar system magnetic fields and plasma can modulate the primary component and Figure 3 shows the extent of this modulation between solar maximum and minimum (E. Juliusson, 1975; J. Linsley, 1981).

Primary Particle Energy Density

If the above spectrum is corrected for solar effects, the energy density above a particle energy of 10^9 eV outside the solar system is found to be ~5×10^5 eV m^{-3}. As the threshold energy is increased, the energy density decreases rapidly, being 2×10^4 eV m^{-3} above 10^{12} eV and 10^2 eV m^{-3} above 10^{15} eV. The energy density at lower energies outside the heliosphere is unknown but may be substantially greater if the particle rest mass energy is included together with the kinetic energy (A. W. Wolfendale, 1979).

Primary Particle Isotropy

This is measured as an anisotropy $(I_{max} - I_{min})/(I_{max} + I_{min}) \times 100\%$, where I, the intensity (m^{-2}s^{-1}sr^{-1}), is usually measured with an angular resolution of a few degrees.

The measured anisotropy is small and energy dependent. It is roughly constant in amplitude at between 0.05 and 0.1% (with a phase of 0 to 6 hours in right ascension) for energies between 10^{11} eV and 10^{14} eV and appears to increase at higher energies roughly as $0.4 \times (\text{Energy(eV)}/10^{16})^{0.5}$ % up to ~10^{18} eV. The latter rise may well be an artifact of the progressively more limited statistics as the flux drops rapidly with energy. It appears possible that a real anisotropy has been observed at the highest energies (above a few times 10^{19} eV) with a directional preference for the supergalactic plane (this plane reflects the directions of galaxies within about 100 million light years) (A.W. Wolfendale, 1979; R.W. Clay, 1987; T. Stanev et al., 1995).

Primary Particle Composition

The composition of low energy cosmic rays is close to universal nuclear abundances except where propagation effects are present. For example, Li, Be, and B which are spallation products, are overabundant by about six orders of magnitude.

Composition at 10^{11} eV per nucleus

Charge	1	2	(3–5)	(6–8)	(10–14)	(16–24)	(26–28)	≥30
% Composition (10% uncertainty)	50	25	1	12	7	4	4	0.1

Measurements at higher energies indicate that there is an increase in the relative abundances of nuclei with charge greater than 6 at energies above 50 TeV/nucleus (K. Asakimori et al., 1993) (1 TeV = 10^{12} eV).

Cosmic ray composition at low energies is often quoted at a fixed energy per nucleon. When presented in this way, protons constitute roughly 90% of the flux, helium nuclei about 10% and the remainder sum to a total of about 1%.

Certain radioactive isotopic ratios show lifetime effects. The ratio of Be^{10}/B^9 abundances is used to measure an "age" of cosmic rays since Be^{10} is unstable with a half life of about 1.6×10^6 years. A ratio of 0.6 is expected in the absence of Be^{10} decay and a ratio of about 0.2 is found experimentally (E. Juliusson, 1975; P. Meyer, 1981).

At higher energies, composition determinations are indirect and are rather contradictory and controversial. Experiments aim to differentiate between broad composition models. The measurement technique is based on studies of cosmic ray shower development. A rather direct technique for such studies is to use fluorescence observations of the shower development to determine the atmospheric depth of maximum development of the shower. Such observations suggest a heavy composition (large atomic number) at energies ~10^{17} eV which changes with increasing energy to a light composition (perhaps protonic) above ~10^{19} eV (T. K. Gaisser et al., 1993).